

Interim Drainage Report  
for  
**Windingwalk Grading**  
at  
**Meridian Ranch**



EL PASO COUNTY, COLORADO

February 2018

Prepared For:

**GTL DEVELOPMENT, INC.**  
**P.O. Box 80036**  
**San Diego, CA 92138**

Prepared By:  
Tech Contractors  
11886 Stapleton Drive  
Falcon, CO 80831  
719.495.7444

PCD Project No. EGP-17-001



CERTIFICATIONS

**Design Engineer's Statement:**

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.


  
\_\_\_\_\_  
Thomas A. Kerby, P.E. #31429



2-20-18  
Date

**Owner/Developer's Statement:**

I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

  
\_\_\_\_\_  
Raul Guzman, Vice President  
GTL Development, Inc.  
P.O. Box 80036  
San Diego, CA 92138

2/12/18  
Date

**El Paso County:**

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 & 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

\_\_\_\_\_  
Jennifer Irvine, P.E.  
County Engineer / ECM Administrator

\_\_\_\_\_  
Date





# Windingwalk at Meridian Ranch Preliminary Drainage Plan

## Table of Contents

<b>EXECUTIVE SUMMARY</b>	<b><i>i</i></b>
<b>INTRODUCTION</b>	<b><i>1</i></b>
Purpose	1
Scope	1
Background	1
<b>EXISTING CONDITIONS</b>	<b>2</b>
General Location	2
Land Use	2
Climate	2
Topography and Floodplains	2
Geology	2
Natural Hazards Analysis	6
<b>DRAINAGE BASINS AND SUB-BASINS</b>	<b>6</b>
<b>DRAINAGE DESIGN CRITERIA</b>	<b>7</b>
SCS Hydrograph Procedure	7
Full Spectrum Design	7
<b>DRAINAGE CALCULATIONS</b>	<b>8</b>
General Concept	8
Historic Drainage - SCS Calculation Method	10
Interim Drainage - SCS Calculation Method	11
Future Drainage - SCS Calculation Method	14
Proposed Pond H Detention Storage Criteria	17
Existing Pond E Detention Storage Criteria	18
<b>EROSION CONTROL DESIGN</b>	<b>20</b>
General Concept	20
Four Step Process	20
Detention Pond	21
Silt Fence	21
Erosion Bales	21
Miscellaneous	21
<b>DRAINAGE FEES</b>	<b>22</b>
<b>REFERENCES</b>	<b>23</b>



**Figures**

Figure 1: Vicinity Map..... 3  
Figure 2: FEMA Floodplain Map ..... 4  
Figure 3: Soils Map..... 5  
Figure 4 - Meridian Ranch SCS Method – Historic Basin Map .....BACK POCKET  
Figure 5- Meridian Ranch SCS Method – Interim Basin Map .....BACK POCKET  
Figure 6- Meridian Ranch SCS Method – Future Basin Map .....BACK POCKET

**Tables**

Table 1: SCS Runoff Curve Numbers ..... 7  
Table 2: Detention Pond Summaries: ..... 8  
Table 3: Historic Drainage Basins – SCS ..... 10  
Table 4: Interim Drainage Basins-SCS..... 11  
Table 5: Future Drainage Basins-SCS ..... 14  
Table 6: Key Design Point Comparison - SCS..... 16  
Table 7: Proposed Pond H Summary Data ..... 17  
Table 8: Existing Pond E Summary Data ..... 19

**Appendices:**

- Appendix A - HEC-HMS Data
- Appendix B - Detention Pond Information
- Appendix C – Temporary Sedimentation
- Appendix D – Soil Resource Report
- Appendix E – Drainage Maps



## **EXECUTIVE SUMMARY**

The purpose of the following Preliminary Drainage Report (PDR) is to present proposed changes for Windingwalk at Meridian Ranch due to grading operations. Runoff quantities and proposed facilities have been calculated using the current City of Colorado Springs/El Paso County Drainage Criteria Manual (DCM) (1994 version) and portions of the City of Colorado Springs Drainage Criteria Manual, Volume 1 (DCM-1) ((2014 version). Concepts presented in this report will be refined and specific improvements addressed during the Final Plat process.

This report anticipates the revisions to the most recent sketch plan amendment in process with the Planning and Community Development Department. The submitted Sketch Plan includes a change of use from business to residential resulting in lower developed runoff. Another significant change from previous drainage reports submitted to El Paso County concerning development associated within Meridian Ranch is the adopted changes to the drainage criteria. El Paso County by Resolution 15-042 adopted Chapter 6 of the 2014 version of the City of Colorado Springs Drainage Criteria Manual (COSDCM). Chapter 6 addresses the hydrologic calculations and includes an updated hydrograph to be used with storm drainage runoff. The new hydrograph results in lower historic values for runoff rates and higher developed values given the same input values. The county adopted Section 3.2.1 of Chapter 13 of the COSDCM referencing Full Spectrum Detention; the concept “provides better control of the full range of runoff rates that pass through detention facilities than the convention multi-stage concept. By providing an Excess Urban Runoff Volume (EURV) in the lower portion of the facility storage with an outlet similar to the Water Quality Capture Volume (WQCV), *frequent and infrequent inflows are released at rates approximating undeveloped conditions.*” This report includes hydrologic models from HEC-HMS for the historic, interim and future conditions for the 2-yr, 5-yr, 10-yr, 25-yr, 50-yr, and 100-yr design storm frequencies. The interim and the future conditions include detention facilities sized and modeled such that “*frequent and infrequent inflows are released at rates approximating undeveloped conditions*”

On November 16, 2000 the El Paso County Board of County Commissioners approved the rezoning of the Meridian Ranch project (PUD-00-010) from A-35 to PUD with several conditions. Condition number seven stated in part that “drainage plans shall release and/or retain at approximately eight percent (80%) of historic rates.” At the time of the initial approvals there were no drainage improvements downstream of the Meridian Ranch project and the existing natural channels were shallow and undefined. Since the time of the original approvals development has occurred downstream of Meridian Ranch with drainage facilities designed and constructed of sufficient size to safely convey the historic flow rates off of Meridian Ranch further downstream.

Windingwalk at Meridian Ranch grading encompasses 178± acres and is located in Sections 29 and 30, Township 12 South, Range 64 West of the 6<sup>th</sup> Principal Meridian. It is approximately 12 miles northeast of the city of Colorado Springs, 2.5 miles north of the unincorporated town of Falcon, and immediately north of the Woodmen Hills development.

Windingwalk at Meridian Ranch is currently within three separate drainage basins; the Bennett Ranch Basin, the Haegler Ranch Basin and the Gieck Ranch Basin. Each have been studied as part of the respective Drainage Basin Study, the Gieck Ranch DBPS is currently waiting for some minor revisions prior to final approval from the El Paso County. The condition set by the Board of County Commissioners is more stringent than those anticipated in the DBPS. However, the project developer has agreed to be in substantial conformance with the appropriate “to-be approved” DBPS.

Based on the aforementioned design parameters the development of the project will not adversely affect downstream properties.

## **INTRODUCTION**

### ***Purpose***

The purpose of the following Preliminary Drainage Report (PDR) is to present proposed changes for Windingwalk at Meridian Ranch due to grading operations with drainage mitigation based on calculated developed flows in excess of allowable exiting runoff discharge.

### ***Scope***

The scope of this report includes:

- Location and description of the proposed grading stating the proposed land use, density, acreage and adjacent features to the site.
- Calculations for design peak flows from all off-site tributary drainage areas.
- Calculations for design peak flows within the proposed project area for all drainage areas.
- Discussion of major drainage facilities required as a result of the grading.
- Discussion and analysis of existing and proposed facilities.

Runoff quantities and proposed facilities have been calculated using the current City of Colorado Springs/El Paso County Drainage Criteria Manual (DCM) (1994 version) and those portions of the City of Colorado Springs Drainage Criteria Manual, Volume 1 (DCM-1) ((2014 version) adopted by Resolution 15-042 of the El Paso County Board of County Commissioners.

### ***Background***

On November 16, 2000 the El Paso County Board of County Commissioners approved the rezoning of the Meridian Ranch project (PUD-00-010) from A-35 to PUD with several conditions. Condition number seven stated in part that “drainage plans shall release and/or retain at approximately eight percent (80%) of historic rates.” At the time of the initial approvals there were no drainage improvements downstream of the Meridian Ranch project and the existing natural channels were shallow and undefined.

Since the time of the original approvals development has occurred downstream of Meridian Ranch with drainage facilities designed and constructed of sufficient size to safely convey the historic flow rates off of Meridian Ranch further downstream. The 4-Way Ranch development located adjacent and downstream of Meridian Ranch has processed a Letter of Map Revision (LOMR) and constructed storm drainage improvements downstream of the existing Pond E outlets. The LOMR was processed and the improvements constructed assuming historic flow rates from Meridian Ranch. Storm drain improvements near the intersection of Stapleton Drive and Eastonville have also been designed and constructed to convey the historic flow rates from Meridian Ranch. The design of these improvements and the downstream system anticipated 87 CFS to be collected near outlet of the future Pond H from Meridian Ranch. The preliminary design of Pond H has yielded a 100-year flow rate of 60 CFS, well below the anticipated 87 CFS figure.

Current estimates show the design discharge Pond E to 4-Way are near or below 90% of historic flow rates for the 100-year discharge at full buildout and the 5-year discharge at or slightly above historic.

## **EXISTING CONDITIONS**

### ***General Location***

Windingwalk at Meridian Ranch grading encompasses 178± acres and is located in Sections 29 and 30, Township 12 South, Range 64 West of the 6<sup>th</sup> Principal Meridian. It is approximately 12 miles northeast of the city of Colorado Springs, 2.5 miles north of the unincorporated town of Falcon, and immediately north of the Woodmen Hills development.

### ***Land Use***

Historically, ranching dominated the area surrounding Meridian Ranch; however, currently urbanization has occurred in the general vicinity. Most notably, urbanization is occurring to the north with Latigo Trails, to the south in the Woodmen Hills Subdivision, to the east in Four Way Ranch, to the west in the Falcon Hills subdivision, and to the northwest in the Paint Brush Hills subdivision.

### ***Climate***

Mild summers and winter, light precipitation; high evaporation and moderately high wind velocities characterize the climate of the study area. The average annual monthly temperature is 48.4 F with an average monthly low of 30.3 F in the winter and an average monthly high of 68.1 F in the summer. Two years in ten will have maximum temperature higher than 98 F and a minimum temperature lower than -16 F. Precipitation averages 15.73" annually, with 80% of this occurring during the months of April through September. The average annual Class A pan evaporation is 45 inches. (Soil Survey of El Paso County Area, Colorado).

### ***Topography and Floodplains***

The topography of the site is typical of a high desert, short prairie grass with relatively flat slopes generally ranging from 2% to 4%. The project site drains generally from the northwest to southeast and is tributary to the Black Squirrel Creek.

The Flood Insurance Rate Maps (FIRM No. 08041C0575-F dated 3/17/1997) indicates that the Windingwalk at Meridian Ranch development is outside of any designated flood plain. Letter of Map Revision (LOMR), Case No. 14-08-1121P was approved by FEMA on November 6, 2014 with an effective date of March 24, 2015. Please see Figure 2: Windingwalk at Meridian Ranch Federal Emergency Management Agency (FEMA) Floodplain Map.


### ***Geology***

The National Resources Conservation Service (NRCS) soil survey records indicate that the service area is predominately covered by soils classified in the Stapleton series. This series is categorized in the Hydrological Group B.




WINDINGWALK AT MERIDIAN RANCH

Figure 1: Vicinity Map



WINDINGWALK AT MERIDIAN RANCH

Figure 2: FEMA Floodplain Map



N.T.S.

MAP # 08041C0575 F  
EFFECTIVE DATE: JUNE 27, 2017


**MERIDIAN RANCH  
WINDINGWALK  
FEMA FLOODPLAIN MAP**

**FIGURE 2**

**TECH CONTRACTORS**  
11886 STAPLETON DRIVE  
FALCON, CO 80831  
TELEPHONE: 719.495.7444  
FAX: 719.495.2457

WINDINGWALK AT MERIDIAN RANCH

Figure 3: Soils Map



N.T.S.

**MERIDIAN RANCH  
WINDINGWALK  
SOILS MAP**

**FIGURE 3**

**TECH CONTRACTORS  
11886 STAPLETON DRIVE  
FALCON, CO 80831  
TELEPHONE: 719.495.7444  
FAX: 719.495.2457**

The Columbine (19) gravelly sandy loam is a deep, well-drained to excessively drained soil formed in coarse textured material on alluvial terraces, fans and flood plains. Permeability of this soil is very rapid. Available water capacity is low to moderate, surface runoff is slow, and the hazard of erosion is slight to moderate. This soil is used mainly for grazing livestock, for wildlife habitat and for home sites. The main limitation of this soil for urban development is a hazard of flooding in some areas.

The Stapleton (83) sandy loam is a deep, non-calcareous, well-drained soil formed in alluvium derived from arkosic bedrock on uplands. Permeability of this soil is rapid. Available water capacity is moderate, surface runoff is slow, and the hazard of erosion and soil blowing is moderate. This soil is suited to habitat for open land and rangeland wildlife. The main limitation of this soil for urban development is frost-action potential.

Typically, these soils are well-drained, gravelly sandy loams that form on alluvial terraces and fans and exhibit high permeability and low available water capacity with depth to bedrock greater than 6 feet.

Note: (#) indicates Soil Conservation Survey soil classification number. See Figure 3 Windingwalk at Meridian Ranch – Soils Map.

### ***Natural Hazards Analysis***

Natural hazards analysis indicates that no unusual surface or subsurface hazards are located near the vicinity. However, because the soils are cohesionless, sloughing of steep banks during drilling and/or excavation could occur. By citing improvements in a manner that provides an opportunity to lay the banks of excavations back at a 1:1 slope during construction, the problems associated with sloughing soils can be minimized.

### **DRAINAGE BASINS AND SUB-BASINS**

The site is within the Bennett Ranch, the Haegler Ranch, and the Gieck Ranch Drainage Basins and accepts flow from areas north of the project site within portions of Meridian Ranch.

Three different scenarios were analyzed for the drainage condition for the Windingwalk at Meridian Ranch grading.

The first scenario analyzes the historic conditions for Windingwalk at Meridian Ranch. This condition has all of the Meridian Ranch development in the pre-development state. Windingwalk and other future phases were considered as undisturbed.

The second scenario, the interim conditions scenario is the existing conditions with the addition of Windingwalk in the graded condition. This condition was analyzed to ensure that historic conditions at given design points along Eastonville Road and Stapleton Drive were maintained after the grading is completed in Windingwalk.

The final scenario analyzes the future build out conditions to ensure the storm drain facilities located at the discharge points of the project are able to properly convey the historic peak flow rates as the storm drainage exits the project.

**DRAINAGE DESIGN CRITERIA**

***SCS Hydrograph Procedure***

The US Army Corp of Engineers HEC-HMS computer program was used to model the Soil Conservation Service (SCS) Hydrograph procedure was used to determine final design parameters for the major drainage facilities within the project. Onsite basin areas were calculated using aerial topography of the site and approved final design data. Times of concentration were estimated using the SCS procedures described in the DCM. Based upon the hydrologic soil type, the natural conditions found in the basins and the runoff curve numbers (CN) chart from Table 6-10 of the City of Colorado Springs DCM for Antecedent Runoff Condition II (ARC II), the following CN values were used for the given conditions.

**Table 1: SCS Runoff Curve Numbers**

Condition	CN		
Residential Lots (5 acre)	63	School	80
Residential Lots (2.5 acre)	66	Parks/Open Space	62
Residential Lots (1 acre)	68	Commercial	85
Residential Lots (1/2 acre)	70	Roadways	98
Residential Lots (1/3 acre)	72	Graded	67
Residential Lots (1/4 acre)	75	Golf Course	62
Residential Lots (1/5 acre)	78	Latigo Undeveloped	65
Residential Lots (1/6 acre)	80	Undeveloped	61

\*Curve Numbers were interpolated and based on amount of impervious area per lot. The 24 hour storm precipitation values were selected from the NOAA Atlas 14, Volume 8, Version 2 for the Meridian Ranch location (Latitude 38.9783°, Longitude -104.5842°, Elevation 7054 ft). These numbers along with SCS information were used as input to the U.S. Army Corp of Engineers HEC-HMS computer model to determine design runoffs. See the table for all the design storm events in Appendix A. These numbers along with SCS information were used as input to the U.S. Army Corp of Engineers HEC-HMS computer model to determine design runoffs.

***Full Spectrum Design***

The City of Colorado Springs adopted a new Drainage Criteria Manual (DCM) in 2014 which incorporated the use of *Full Spectrum Design* for storm drainage analysis for projects located within the city limits. Full Spectrum analyzes the storm water runoff for the 2-year, 5-year, 10-year, 25-year, 50-year and the 100-year design storms in order ensure the analysis more accurately project the conditions of post development. El Paso County adopted portions of the City’s 2014 DCM by resolution in January 2015; the County resolution adopted Chapter 6 (Hydrology) and Section 3.2.1 of Chapter 13 (Full Spectrum Detention) for projects outside of the City of Colorado Springs establishing a 1 year review period to analyze the impacts of the Full Spectrum Design on the storm drainage analysis of projects. This report has incorporated the use of full spectrum in the analysis of the interim and future conditions.

The idea behind full spectrum detention is to release the developed runoff flows to at or below those of the pre-developed condition. The design of the proposed Pond H and control structure meets or exceeds the intent and spirit of the concept.

**Table 2: Detention Pond Summaries:**

POND E						
	PEAK INFLOW	PEAK OUTFLOW	TOTAL INFLOW	TOTAL OUTFLOW	PEAK STORAGE	PEAK ELEVATION
	CFS	CFS	AC-FT	AC-FT	AC-FT	FT
INTERIM CONDITIONS						
5-YEAR STORM	113	15	22.9	14.0	11.2	6970.6
10-YEAR STORM	175	25	36.3	22.0	17.8	6970.4
25-YEAR STORM	282	57	59.7	40.3	25.8	6970.1
50-YEAR STORM	383	113	82.4	61.5	31.9	6972.7
100-YEAR STORM	508	188	110.0	87.7	38.0	6973.2
FUTURE CONDITIONS						
5-YEAR STORM	133	18	28.5	17.2	14.3	6971.0
10-YEAR STORM	210	32	43.5	27.6	20.3	6971.6
25-YEAR STORM	340	82	69.4	49.6	28.9	6972.4
50-YEAR STORM	461	151	94.2	73.0	35.3	6973.0
100-YEAR STORM	631	242	123.0	101.0	41.3	6973.5

POND H						
	PEAK INFLOW	PEAK OUTFLOW	TOTAL INFLOW	TOTAL OUTFLOW	PEAK STORAGE	PEAK ELEVATION
	CFS	CFS	AC-FT	AC-FT	AC-FT	FT
INTERIM CONDITIONS						
5-YEAR STORM	10	1	2.2	1.3	1.4	6971.1
10-YEAR STORM	21	2	3.7	1.9	2.4	6971.6
25-YEAR STORM	42	6	6.5	4.1	3.4	6972.0
50-YEAR STORM	64	13	9.2	6.7	4.5	6972.4
100-YEAR STORM	90	23	12.6	9.9	5.7	6972.8
FUTURE CONDITIONS						
5-YEAR STORM	36	3	4.5	2.4	2.7	6971.7
10-YEAR STORM	56	8	6.7	4.4	3.6	6972.1
25-YEAR STORM	91	18	10.5	7.9	5.1	6972.6
50-YEAR STORM	123	32	13.9	11.2	6.5	6973.1
100-YEAR STORM	160	58	18.0	15.2	7.7	6973.5

**DRAINAGE CALCULATIONS**

***General Concept***

The grading operations associated with Windingwalk are located within portions of the Bennett Ranch, the Haegler Ranch, and the Gieck Ranch Drainage Basins. Storm water runoff will be conveyed across the site overland through proposed temporary sedimentation ponds prior to release from either existing detention ponds (Pond E, Bennett Regional Pond) or the proposed permanent detention Pond H. Portions of the site tributary to the Bennett Ranch Basin will be directed to an existing sedimentation pond located near the southwest corner of the project prior to being released into the adjacent channel then conveyed

downstream to the existing Bennett Ranch Regional Detention facility. Other portions of the project tributary to the Bennett Ranch will be directed to a proposed sedimentation basin prior to being released into an existing 48" RCP located at Lambert Rd. and Stapleton Dr. Those portions of the site tributary to the Gieck Ranch Basin will be directed to an existing sedimentation pond located upstream gradient to the Vistas Filing 1 then conveyed downstream to the existing Pond E then released across Eastonville Road. Those portions of the site tributary to the Haegler Ranch Basin will be directed overland to a series of sedimentation ponds prior to being directed to the proposed Pond H detention. The proposed detention Pond H will be utilized as a combination sedimentation/detention pond until such time as the tributary areas establish sufficient ground cover or development in the area is complete. At the time when the project grading has established 70% of the original native cover, the temporary sedimentation riser pipe will be replaced with the permanent water quality riser pipe.

The facilities have been adequately sized such that the developed flows will be detained and released at or below the historic flow rates for the various design storm events as outlined in the El Paso County DCM and those sections of the City of Colorado Springs DCM adopted by the El Paso County Board of County Commissioners. Existing facilities located downstream of the proposed grading have been designed to accept historic flow rates from Meridian Ranch.

The temporary CMP outlet structures constructed with Pond E will be replaced with the permanent concrete structures with this project. That portion of the site located within the Gieck Ranch Basin, tributary to Pond E was designed using the old criteria hydrologic methods and with a release rate approximating 80% of the historic peak flow rates for the 5-year and the 100-year storm events. The analysis shows the pond releasing the developed peak flows with the permanent concrete structures to be below the historic flow rates for the full spectrum of design storms and near 90 percent of historic flow rate for the 100-year storm event using the newly adopted unit hydrograph from the City DCM.

A portion of the project is located within the Bennett Ranch Drainage Basin the Bennett Ranch Regional Detention pond was designed and constructed with the necessary water quality for the upstream tributary area. An existing drainage channel conveys overland flow to an existing sedimentation pond prior releasing the flow to the North Bennett Channel and travelling downstream to the regional pond. Another portion of the project will have the temporary overland flow be directed to a temporary sedimentation pond then into an existing 48" RCP located in Lambert Road. The 48" RCP will be connected to a storm drain system constructed with WindingWalk Filing 1 during the next phase of construction.

The portion of the site located within the Bennett Ranch Basin is tributary to the existing 48" RCP storm drain pipe located within Lambert Road conveys the flow southerly toward the North Channel where it discharges into the Bennett Regional Detention Pond located within the Bennett Ranch Basin. The storm drain was designed using the old criteria hydrologic methods and was expected to accept 143 CFS for the 100-year storm event, the results of this analysis estimates 148 CFS will be discharged into the 48" RCP. The storm drain was hydraulically analyzed against the new CFS value and found to be sized adequately to convey the flow.



A portion of the site is tributary to the existing Bennett Regional Detention Pond located within the Bennett Ranch Basin, the pond was designed using the old criteria hydrologic methods and with a release rate approximating 80% of the historic peak flow rates for the 5-year and the 100-year storm events. The analysis shows the pond releasing the developed peak flows below the historic flow rates for the full spectrum of design storms. The necessary water quality capture volume was incorporated into the design and construction of the pond.

A portion of the site is tributary to the proposed Pond H located within the Haegler Ranch Basin, the pond was designed with this report using the new criteria hydrologic methods and with a release rate approximating the historic peak flow rates for the full spectrum of storm events. The analysis shows the pond releasing the developed peak flows below the historic flow rates for the full spectrum of design storms and below 90 percent of the 100-year historic flow rate for that location. Additional, the release rate of the 2-year storm event has been calculated to be 2 CFS.

Figure 4: Meridian Ranch SCS Calculations – Historic Conditions Map, Figure 5: Meridian Ranch SCS Calculations – Interim Conditions and Figure 6: Meridian Ranch SCS Calculations – Future Conditions Map depict the historic, graded and future general drainage patterns for Windingwalk portion of Meridian Ranch.

The purpose of this report is to show that the grading of Windingwalk at Meridian Ranch will not adversely impact the existing drainage facilities adjacent and downstream of the graded area and the proposed Pond H is properly sized for the anticipated future development of the area tributary to the pond. Further evaluation will be necessary at each stage of future development within the Meridian Ranch and the anticipated build-out is reached.

Historic Drainage - SCS Calculation Method

Following is a tabulation of the surface drainage characteristics under Existing Conditions using the SCS calculation method. Please refer to Figure 4 - Meridian Ranch SCS Calculations - Historic Basin Map.

**Table 3: Historic Drainage Basins – SCS**

HISTORIC							
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
OS02	0.2219	148	102	65	30	13	3.0
B01	0.2219	148	102	65	30	13	3.0
B01-B07	0.2219	148	102	65	30	13	3.0
OS03	0.1984	130	88	55	23	9	2.0
B02-B03	0.1984	129	88	55	23	9	2.0
HB01	0.0234	19	13	8	3	1	0.0
B03	0.2218	140	95	59	25	10	2.0
B03-B07	0.2218	140	94	59	25	10	2.0
OS04	0.1359	83	54	32	12	4	1.0
B04-B05	0.1359	82	54	32	12	4	1.0
HB03	0.1266	103	68	41	15	5	1.0
B05	0.2625	144	91	52	20	7	1.0
B05-B07	0.2625	144	91	52	20	7	1.0
HB02	0.1063	77	51	30	11	4	0.0
HB04	0.0609	47	31	19	7	2	0.0
B07	0.8734	519	344	207	86	33	6.0



HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
B07-B12	0.8734	518	343	207	86	33	6.0
HB05	0.1375	102	67	40	15	5	1.0
HB06	0.1641	111	73	43	16	5	1.0
B12	1.175	679	440	259	103	40	7.0
B12-PB	1.175	677	440	259	103	39	7.0
HB07	0.0313	29	19	12	4	1	0.0
POND B	1.2063	688	446	262	105	40	7.0
PB-19	1.2063	687	444	261	104	40	7.0
OS01	1.5594	757	510	316	136	55	11
OS01-B19	1.5594	756	509	315	136	55	11
HB08	0.1344	81	53	32	12	4	1.0
HB09	0.3047	138	90	54	21	7	1.0
B19	3.2048	1563	1041	635	266	105	20
B19-B26	3.2048	1563	1039	634	266	105	20
HB10	0.3047	172	113	67	26	9	1.0
HB12	0.0797	54	36	21	8	3	0.0
HB12-B26	0.0797	54	35	21	8	3	0.0
B26	3.5892	1737	1147	693	288	113	21
B26-32	3.5892	1734	1146	693	287	113	21
HB11	0.1125	60	40	23	9	3	0.0
32	3.7017	1782	1177	709	293	115	22
32-37	3.7017	1782	1175	708	293	115	22
B-14	0.4039	178	117	70	27	10	2.0
B-13	0.2813	127	83	50	19	7	1.0
36	0.6852	306	200	119	47	17	3.0
36-37	0.6852	305	200	119	47	17	3.0
B-15	0.075	39	26	15	6	2	0.0
37	4.4619	2117	1391	834	338	131	25
HG07	0.0984	50	32	19	7	3	0.0
HG07-G11	0.0984	50	32	19	7	3	0.0
HG08	0.1328	77	51	30	11	4	1.0
G11	0.2312	122	79	47	18	6	1.0
G11-G12	0.2312	121	79	47	18	6	1.0
HG09	0.1781	76	50	30	12	4	1.0
G12	0.4093	196	128	76	29	10	2.0
G12-H08	0.4093	196	128	76	29	10	2.0
HG10	0.1375	40	26	16	7	3	1.0
H08	0.5468	227	149	89	35	13	2.0
HG11	0.2047	80	53	31	13	5	1.0
H09	0.2047	80	53	31	13	5	1.0
HH01	0.0984	70	46	27	10	3	0.0
H12	0.0984	70	46	27	10	3	0.0
HG12	0.1297	60	39	23	9	3	1.0
H10	0.1297	60	39	23	9	3	1.0

#### Interim Drainage - SCS Calculation Method

Following is a tabulation of the surface drainage characteristics for the interim conditions using the SCS calculation method. Please refer to Figure 5 - Meridian Ranch SCS Calculations – Interim Basins Map

**Table 4: Interim Drainage Basins-SCS**

INTERIM GRADED CONDITIONS							
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
OS01	1.5594	757	510	316	136	55	11
DB16	0.0578	92	72	54	35	23	13
B10	1.6172	794	537	335	147	62	13
B10-B11	1.6172	793	537	335	147	62	13
DB17	0.0048	16	13	11	9	7	6
B11	1.622	795	538	336	148	63	15
B11-POND C	1.622	795	538	336	148	63	15

HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK (CFS) Q5	DISCHARGE PEAK (CFS) Q2
DB21	0.0519	54	38	25	12	5	1
DB18	0.0346	64	50	39	26	18	10
DB19	0.0281	36	27	20	11	7	3
DB20	0.0147	25	19	15	9	6	3
POND C	1.7513	749	507	310	129	50	11
POND C-B16	1.7513	749	507	310	128	50	11
DB25	0.0211	45	35	27	18	12	7
B16	1.7724	754	511	313	130	51	11
B16-B17	1.7724	754	510	312	130	51	11
DB26	0.0682	136	110	88	62	46	29
B17	1.8406	778	529	326	138	56	34
B17-B18	1.8406	778	529	326	138	56	34
OS03	0.1984	130	88	55	24	9	2
DB01	0.0719	90	66	46	25	14	5
B01	0.2703	199	139	89	42	19	5
B01-B02	0.2703	199	138	89	42	19	5
OS02	0.2219	148	102	65	30	13	3
DB02	0.0516	71	52	36	20	10	3
B02	0.5438	380	263	169	79	36	9
B02-POND A	0.5438	379	263	169	79	36	9
OS04	0.1359	83	54	32	12	4	1
DB03	0.0703	70	49	32	16	7	2
B03	0.2062	145	98	61	26	10	2
B03-B04	0.2062	145	98	60	26	10	2
DB04	0.0422	44	31	21	10	5	1
DB05	0.0384	37	27	18	9	5	1
B04	0.2868	218	150	94	42	18	4
B04-B05	0.2868	218	149	94	42	18	4
DB06	0.0219	44	35	28	19	14	9
B05	0.3087	253	176	115	55	26	10
B05-POND A	0.3087	252	176	114	55	26	10
DB07	0.0254	35	26	18	10	6	2
DB08	0.0297	32	22	15	7	3	1
POND A	0.9076	554	396	238	88	27	4
POND A-B06	0.9076	554	395	237	88	27	4
DB09	0.0189	34	26	19	12	8	4
B06	0.9265	562	401	241	90	28	4
B06-B07	0.9265	561	400	241	90	28	4
DB11	0.0969	114	85	60	35	20	8
DB10	0.0364	56	43	32	19	12	6
B07	1.0598	648	462	277	105	37	16
B07-B09	1.0598	647	461	276	105	37	16
DB12	0.0453	81	63	48	31	21	11
B09	1.1051	672	478	287	110	47	20
B09-POND B	1.1051	672	477	287	110	47	20
DB15	0.1234	105	75	50	25	12	3
DB13	0.0703	89	67	49	29	18	8
DB14	0.0556	93	72	54	35	23	12
POND B	1.3544	684	528	324	128	71	31
POND B-B12	1.3544	684	528	323	128	71	31
DB22	0.0516	91	72	55	36	25	14
DB23	0.0172	45	38	31	23	18	13
B12	1.4232	711	550	339	150	85	39
B12-B14	1.4232	711	550	338	150	85	39
DB24	0.0531	94	73	56	36	24	13
B14	1.4763	740	565	348	164	94	47
B14-B15	1.4763	738	564	348	164	94	47
DB28	0.0741	72	51	34	17	8	2
B15	1.5504	775	582	358	175	100	49
B15-B18	1.5504	775	582	358	175	100	49
DB29	0.1697	146	105	71	37	19	6
DB27	0.0508	68	53	40	25	17	9
B26	3.6115	1606	1158	717	298	175	89
B26-27	3.6115	1605	1158	716	298	175	88
FB-02	0.05	46	33	22	11	5	1
FB-01	0.0373	32	23	15	7	4	1
FB01-27a	0.0373	32	23	15	7	4	1
B19	0.0873	77	55	36	18	9	2
B19-27	0.0873	77	55	36	18	9	2
FB-03	0.0078	21	17	14	10	8	5

HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
27	3.7066	1634	1178	729	304	184	91
27-32	3.7066	1633	1178	728	304	184	91
WH-24	0.1325	218	171	129	84	57	31
WH-26	0.0839	49	33	20	8	3	1
WH-27	0.0217	23	16	10	4	1	0
30	0.2381	271	205	150	91	59	31
30-31	0.2381	270	205	149	91	59	31
WH-28	0.0398	60	47	36	23	15	8
31	0.2779	330	252	185	114	74	39
31-32	0.2779	329	251	185	113	74	39
WH-29	0.0495	77	60	45	29	19	10
WH-31	0.0406	75	60	46	30	21	12
WH-30	0.0159	26	19	13	7	4	1
32	4.0905	1773	1269	787	415	252	121
WH32	0.0458	55	38	24	10	4	0
BEN POND	4.1363	1379	966	581	243	97	44
WH-33	0.0064	12	9	7	5	3	2
33	4.1427	1380	967	582	243	97	44
33-37	4.1427	1380	967	581	243	97	44
WH35	0.155	171	124	84	44	22	6
WH34	0.045	68	52	38	23	15	7
B34-36	0.045	68	52	38	23	15	7
36	0.2	239	176	122	67	37	13
36-37	0.2	238	174	121	66	37	13
WH36	0.075	63	43	27	11	4	1
37	4.4177	1419	997	601	252	101	47
FG08A	0.075	125	97	73	46	30	15
FG08A-G05	0.075	125	97	72	45	30	15
FG08B	0.063	94	72	54	34	22	11
FG08B-G05	0.063	93	72	54	34	22	11
FG11	0.0625	81	63	47	30	20	11
FG09	0.0484	52	39	28	16	9	4
FG09-G05	0.0484	52	39	27	16	9	4
HG10	0.0467	31	21	13	6	2	0
G05	0.2956	370	281	206	126	80	39
FG13	0.0661	46	32	21	11	5	2
FG12	0.0328	55	44	33	22	15	9
POND D	0.3945	108	70	35	15	9	3
POND D-G17	0.3945	107	70	35	15	9	3
HG15	0.0297	14	9	6	2	1	0
FG15a	0.0156	30	24	18	12	8	4
G17	0.4398	120	77	38	17	9	5
G17-G18	0.4398	120	77	38	17	9	5
FG16	0.0773	135	105	79	51	34	18
G18	0.5171	179	135	100	64	42	23
G18-POND E	0.5171	178	134	100	63	42	22
HG30	0.1844	51	34	21	9	3	1
FG30-PONDHS	0.1844	51	34	21	9	3	1
FG31	0.0922	123	97	74	49	33	19
POND HS	0.2766	103	62	40	28	19	10
FG17a	0.0694	117	91	69	44	29	16
FG17a-POND E	0.0694	116	90	68	44	29	16
FG18	0.0644	42	30	20	10	5	1
FG18-POND E	0.0644	42	30	20	10	5	1
FG19	0.0527	82	63	47	30	19	10
FG17c	0.0313	34	24	16	8	3	1
FG17b	0.0214	42	34	26	17	12	7
POND E	1.0329	188	113	57	25	15	9
FG20	0.0109	31	26	22	16	13	9
H08-H09	1.0438	189	114	57	25	18	12
FH01	0.1344	90	64	42	21	10	3
H08		154	95	46	19	10	6
H09		34	19	11	6	4	3
POND H	0.1344	23	13	6	2	1	1
FH02	0.0138	18	14	10	5	3	1
H12	0.1482	25	14	10	6	3	1

A comparison of the peak flow rates at Eastonville Road for the design storms may be found in Table 6 – Key Design Point Comparison (below). As a result of the grading of the Windingwalk, the calculations show that the project does not adversely affect the existing drainage facilities.

## Future Drainage - SCS Calculation Method

Following is a tabulation of the surface drainage characteristics for the future conditions using the SCS calculation method. Please refer to Figure 6 - Meridian Ranch SCS Calculations – Future Basins Map

**Table 5: Future Drainage Basins-SCS**

FUTURE CONDITIONS							
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
OS01	1.5594	757	510	316	136	55	11.0
DB16	0.0578	92	72	54	35	23	12.7
B10	1.6172	794	537	335	147	62	13.2
B10-B11	1.6172	793	537	335	147	62	13.2
DB17	0.0048	16	13	11	9	7	5.7
B11	1.6220	795	538	336	148	63	15.3
B11-POND C	1.6220	795	538	336	148	63	15.2
DB21	0.0519	54	38	25	12	5	1.1
DB18	0.0346	64	50	39	26	18	10.0
DB19	0.0281	36	27	20	11	7	2.8
DB20	0.0147	25	19	15	9	6	3.4
POND C	1.7513	749	507	310	129	50	10.9
POND C-B16	1.7513	749	507	310	128	50	10.9
DB25	0.0211	45	35	27	18	12	7.1
B16	1.7724	754	511	313	130	51	11.3
B16-B17	1.7724	754	510	312	130	51	11.3
DB26	0.0682	136	110	88	62	46	29.4
B17	1.8406	778	529	326	138	56	34.4
B17-B26	1.8406	778	529	326	138	56	34.0
OS03	0.1984	130	88	55	24	9	1.6
DB01	0.0719	90	66	46	25	14	4.7
B01	0.2703	199	139	89	42	19	5.0
B01-B02	0.2703	199	138	89	42	19	5.0
OS02	0.2219	148	102	65	30	13	2.6
DB02	0.0516	71	52	36	20	10	3.4
B02	0.5438	380	263	169	79	36	8.6
B02-POND A	0.5438	379	263	169	79	36	8.6
OS04	0.1359	83	54	32	12	4	0.6
DB03	0.0703	70	49	32	16	7	1.5
B03	0.2062	145	98	61	26	10	1.5
B03-B04	0.2062	145	98	60	26	10	1.5
DB04	0.0422	44	31	21	10	5	1.2
DB05	0.0384	37	27	18	9	5	1.4
B04	0.2868	218	150	94	42	18	3.6
B04-B05	0.2868	218	149	94	42	18	3.6
DB06	0.0219	44	35	28	19	14	8.6
B05	0.3087	253	176	115	55	26	10.3
B05-POND A	0.3087	252	176	114	55	26	10.2
DB07	0.0254	35	26	18	10	6	1.9
DB08	0.0297	32	22	15	7	3	0.5
POND A	0.9076	545	380	217	69	18	1.5
POND A-B06	0.9076	544	380	217	69	18	1.5
DB09	0.0189	34	26	19	12	8	3.7
B06	0.9265	552	385	221	70	18	3.7
B06-B07	0.9265	551	384	220	70	18	3.7
DB11	0.0969	114	85	60	35	20	8.1
DB10	0.0364	56	43	32	19	12	5.8
B07	1.0598	635	441	252	82	36	14.8
B07-B09	1.0598	634	440	252	82	35	14.4
DB12	0.0453	81	63	48	31	21	11.2
B09	1.1051	659	455	261	86	45	19.4
B09-POND B	1.1051	658	455	260	86	45	19.3

HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
DB15	0.1234	105	75	50	25	12	3.3
DB13	0.0703	89	67	49	29	18	7.9
DB14	0.0556	93	72	54	35	23	12.4
POND B	1.3544	676	501	291	126	69	29.6
POND B-B12	1.3544	676	501	290	126	69	29.6
DB22	0.0516	91	72	55	36	25	14.1
DB23	0.0172	45	38	31	23	18	13.1
B12	1.4232	703	521	304	148	83	37.5
B12-B14	1.4232	703	521	304	148	83	37.5
DB24	0.0531	94	73	56	36	24	13.2
B14	1.4763	727	535	313	162	92	45.9
B14-B15	1.4763	726	535	313	161	92	45.9
DB28	0.0741	85	63	44	24	14	5.0
B15	1.5504	764	554	326	177	103	50.9
B15-B26	1.5504	763	553	325	176	103	50.8
DB29	0.1697	146	105	71	37	19	6.1
DB27	0.0508	68	53	40	25	17	8.9
B26	3.6115	1601	1134	685	288	180	89.9
B26-27	3.6115	1601	1133	684	287	180	89.6
FB-02	0.0500	67	53	40	26	17	9.5
FB-01	0.0373	62	49	37	23	15	8.2
FB01-B19	0.0373	62	48	36	23	15	8.1
B19	0.0873	124	97	73	47	31	16.8
B19-27	0.0873	124	96	73	47	31	16.8
FB-03	0.0078	22	18	15	11	8	5.9
27	3.7066	1639	1161	702	326	206	101.7
27-32	3.7066	1639	1160	701	326	205	101.3
WH-24	0.1325	218	171	129	84	57	31.1
WH-26	0.0839	49	33	20	8	3	0.5
WH-27	0.0217	23	16	10	4	1	0.1
30	0.2381	271	205	150	91	59	31.1
30-31	0.2381	270	205	149	91	59	31.1
WH-28	0.0398	60	47	36	23	15	8.1
31	0.2779	330	252	185	114	74	39.2
31-32	0.2779	329	251	185	113	74	38.9
WH-29	0.0495	77	60	45	29	19	10.2
WH-31	0.0406	75	60	46	30	21	11.8
WH-30	0.0159	26	19	13	7	4	1.3
32	4.0905	1780	1249	757	445	277	131.5
WH32	0.0458	55	38	24	10	4	0.3
BEN POND	4.1363	1385	967	578	237	95	45.5
WH-33	0.0064	12	9	7	5	3	1.9
33	4.1427	1386	968	579	237	95	45.7
33-37	4.1427	1386	967	579	237	95	45.7
WH35	0.1550	171	124	84	44	22	6.4
WH34	0.0450	68	52	38	23	15	7.0
B34-36	0.0450	68	52	38	23	15	6.9
36	0.2000	239	176	122	67	37	13.3
36-37	0.2000	238	174	121	66	37	13.2
WH36	0.0750	63	43	27	11	4	0.6
37	4.4177	1425	997	598	246	100	49.0
FG08A	0.0750	125	97	73	46	30	15.3
FG08A-G05	0.0750	125	97	72	45	30	15.2
FG10	0.0669	47	35	25	15	9	3.7
FG08B	0.0630	94	72	54	34	22	11.1
FG08B-G05	0.0630	93	72	54	34	22	11.1
FG11	0.0625	81	63	47	30	20	10.6
FG09	0.0484	52	39	28	16	9	3.6
FG09-G05	0.0484	52	39	27	16	9	3.6
G05	0.3158	367	281	208	128	82	40.7
FG13	0.0661	46	32	21	11	5	1.5
FG14	0.0331	44	34	26	16	11	5.5
FG12	0.0328	55	44	33	22	15	8.5
POND D	0.4478	132	90	51	19	12	4.2
POND D-G17	0.4478	132	90	51	19	12	4.2
FG15	0.1017	100	75	54	31	19	7.9
G17a	0.1017	100	75	54	31	19	7.9
FG15a	0.0156	30	24	18	12	8	4.3

HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
G17	0.5651	190	124	75	41	24	11.0
G17-G18	0.5651	190	124	75	41	24	10.9
FG16	0.0773	135	105	79	51	34	18.0
G18	0.6424	248	186	134	82	52	25.7
G18-POND E	0.6424	246	185	133	82	51	25.6
FG31	0.0922	123	97	74	49	33	18.5
FG30	0.0400	82	65	50	33	23	13.1
FG30-PONDHS	0.0400	81	64	49	33	23	12.9
POND HS	0.1322	159	113	63	37	27	15.5
FG17a	0.0694	111	85	64	40	26	13.1
FG17a-POND E	0.0694	110	85	63	40	26	13.0
FG18	0.0644	59	45	32	19	11	5.0
FG18-POND E	0.0644	59	45	32	19	11	5.0
FG19	0.0527	92	73	56	37	25	14.5
FG17c	0.0313	34	24	16	8	3	0.6
FG17b	0.0214	42	34	26	17	12	6.6
POND E	1.0138	242	151	82	32	18	10.7
H08	1.0138	207	135	72	25	14	7.2
H09	0.0000	34	16	10	7	5	3.4
FH01	0.1344	161	123	91	56	36	17.8
POND H	0.1344	58	32	18	8	3	1.2
FH02	0.0091	12	9	6	4	2	0.8

A comparison of the peak flow rates at Eastonville Road for the design storms may be found in Table 6 – Key Design Point Comparison (below). As a result of the future development of the Windingwalk, the calculations show that the project does not adversely affect the existing drainage facilities.

**Table 6: Key Design Point Comparison - SCS**

KEY DESIGN POINT FLOW RATES					
EVENT	HISTORIC PEAK FLOW (CFS)	INTERIM PEAK FLOW (CFS)	PERCENT OF HISTORIC	FUTURE PEAK FLOW (CFS)	PERCENT OF HISTORIC
<b>EASTONVILLE ROAD (H08)</b>					
5-YEAR	13	10	80%	14	105%
10-YEAR	35	19	54%	25	71%
25-YEAR	89	46	51%	72	81%
50-YEAR	149	95	64%	135	91%
100-YEAR	227	154	68%	207	91%
<b>EASTONVILLE ROAD (H09)</b>					
5-YEAR	5	4	83%	5	94%
10-YEAR	13	6	45%	7	52%
25-YEAR	31	11	36%	10	32%
50-YEAR	53	19	36%	16	30%
100-YEAR	80	34	43%	34	43%
<b>STAPLETON DR/EASTONVILLE ROAD (H12)</b>					
5-YEAR	3	3	103%	3	100%
10-YEAR	10	6	56%	8	75%
25-YEAR	27	10	37%	18	67%
50-YEAR	46	14	31%	32	70%
100-YEAR	70	25	36%	58	83%
<b>BENNETT POND OUTLET (B32)</b>					
5-YEAR	115	97	84%	95	82%
10-YEAR	293	243	83%	237	81%
25-YEAR	709	581	82%	578	82%
50-YEAR	1177	966	82%	967	82%
100-YEAR	1782	1379	77%	1385	78%
<b>JUDGE ORR ROAD (B37)</b>					
5-YEAR	131	101	77%	100	76%
10-YEAR	338	252	75%	246	73%
25-YEAR	834	601	72%	598	72%
50-YEAR	1391	997	72%	997	72%
100-YEAR	2117	1419	67%	1425	67%

***Proposed Pond H Detention Storage Criteria***

Detention Pond H is to be constructed as a part of the Windingwalk Grading operations in anticipation of future development in accordance with the approved Sketch Plan within the tributary area. The proposed pond is located within the Haegler Ranch Drainage Basin near the southeastern corner of Meridian Ranch near the intersection of Eastonville Road and Stapleton Drive. The pond will be owned and maintained by the Meridian Service Metropolitan District (MSMD). A maintenance agreement between the Meridian Service Metropolitan District and El Paso County is included with the grading package.

The SCS calculation method was used with the aid of the Army Corp HEC-HMS computer program to determine inflow and outflow from the detention pond to ensure the excess runoff as a result of the grading and the future development will not adversely impact drainage patterns downstream of the project.

The pond is designed to accommodate the final inflow from Windingwalk at Meridian Ranch as well as the ultimate build out of all the tributary areas. Permanent concrete control structures has been designed to handle full build out of the tributary area and reduce the developed flows to at or below the historic full spectrum peak flow rates.

A WQCV analysis for Pond H was also performed based on proposed future development of the proposed tributary area to the pond; this analysis shows that Pond H will require 0.3 acre-ft of storage for first flush water quality for all the areas tributary to the pond. The control structure at DP H12 is proposed to consist of a 10” water quality control riser with a trash grate having a top elevation of 6970.0 to achieve the required 0.3 ac-ft of storage.

**Table 7: Proposed Pond H Summary Data**

POND H						
	PEAK INFLOW	PEAK OUTFLOW	TOTAL INFLOW	TOTAL OUTFLOW	PEAK STORAGE	PEAK ELEVATION
	CFS	CFS	AC-FT	AC-FT	AC-FT	FT
INTERIM CONDITIONS						
5-YEAR STORM	10	1	2.2	1.3	1.4	6971.1
10-YEAR STORM	21	2	3.7	1.9	2.4	6971.6
25-YEAR STORM	42	6	6.5	4.1	3.4	6972.0
50-YEAR STORM	64	13	9.2	6.7	4.5	6972.4
100-YEAR STORM	90	23	12.6	9.9	5.7	6972.8
FUTURE CONDITIONS						
5-YEAR STORM	36	3	4.5	2.4	2.7	6971.7
10-YEAR STORM	56	8	6.7	4.4	3.6	6972.1
25-YEAR STORM	91	18	10.5	7.9	5.1	6972.6
50-YEAR STORM	123	32	13.9	11.2	6.5	6973.1
100-YEAR STORM	160	58	18.0	15.2	7.7	6973.5

The WQCV was calculated by using the equations found in Volume 2, of the Drainage Criteria Manual (DCM). The release rate from the WQCV is generally very small, which helps minimize downstream impacts. Detaining the WQCV also serves to cleanse the “first flush” of runoff from the higher initial concentration of sediment and pollutants by allowing for settlement to occur. This greatly improves the quality of runoff, leaving the facility and

reduces the potential for erosion. The positive impact on water quality is expected to be significant, particularly during the construction phase of the development.

A concrete control structure is proposed for the outlet of Pond H. The structure will attenuate the peak developed flow rates to historic peak rates or less for the full spectrum of design storms as per the requirements set forth in Resolution 15-042 adopted by the Board of County Commissioners, County of El Paso. The control structure will consist of a water quality control standpipe, a rectangular slotted orifice located on the front and a grated top to reduce the developed peak flow rates. Table 7 provides summary data for the various design storms in both the interim graded condition and future developed condition.

A small sediment/detention pond was constructed off the northwest corner of the intersection of Stapleton Drive and Eastonville Road as a part of the Stapleton Drive extension. This area will remain in place and be used as a micro-pool as a post detention bio-cleanse for the storm water. The finished volume of the depression will be 0.65 ac-ft providing more than sufficient capacity to hold and convey the storm runoff. The area will be minimally maintained in such a way as to allow wetland vegetation to establish in the pool bottom and promote bio-filtration. The total surface area of the depression is approximately 0.2 acres.

#### ***Existing Pond E Detention Storage Criteria***

Existing Detention Pond E is located south of Londonderry and west of Eastonville, and was constructed as a part of the Meridian Ranch Filing 11 Grading, is owned and maintained by the Meridian Service Metropolitan District (MSMD). It has been in operation since 2013 with no reported issues. A maintenance agreement between the Meridian Service Metropolitan District and El Paso County has been recorded as a part of the Meridian Ranch Filing 11A Final Plat process.

The SCS calculation method was used to determine inflow and outflow from the detention pond to ensure the developed runoff does not overcharge the pond and the discharges do not adversely impact drainage patterns downstream of Eastonville Road. Storm drainage runoff will enter the pond from upstream development via an existing pipe network and overland from existing rear lots of the Vistas Filing 1 at Meridian Ranch. The ultimate future build-out design of the tributary areas was analyzed to insure the sizing of the pond would be adequate after development of Meridian Ranch is complete. This SCS calculation can be found in the appendix.

An analysis of the SCS calculations show that with the proposed permanent concrete control structures, installed with this project the developed flow rates are reduced sufficiently to peak rates at or below the historic rates at Eastonville Road. Temporary CMP control structures installed at the time of the original pond construction with the Meridian Ranch Filing 11 grading operations will be replaced with the permanent concrete control structures. The extent of the current upstream development within the area tributary to Pond E now requires the permanent concrete control structures to be installed.



**Table 8: Existing Pond E Summary Data**

POND E						
	PEAK INFLOW	PEAK OUTFLOW	TOTAL INFLOW	TOTAL OUTFLOW	PEAK STORAGE	PEAK ELEVATION
	CFS	CFS	AC-FT	AC-FT	AC-FT	FT
INTERIM CONDITIONS						
5-YEAR STORM	113	15	22.9	14.0	11.2	6970.6
10-YEAR STORM	175	25	36.3	22.0	17.8	6970.4
25-YEAR STORM	282	57	59.7	40.3	25.8	6970.1
50-YEAR STORM	383	113	82.4	61.5	31.9	6972.7
100-YEAR STORM	508	188	110.0	87.7	38.0	6973.2
FUTURE CONDITIONS						
5-YEAR STORM	133	18	28.5	17.2	14.3	6971.0
10-YEAR STORM	210	32	43.5	27.6	20.3	6971.6
25-YEAR STORM	340	82	69.4	49.6	28.9	6972.4
50-YEAR STORM	461	151	94.2	73.0	35.3	6973.0
100-YEAR STORM	631	242	123.0	101.0	41.3	6973.5

A water quality capture volume (WQCV) was added to the required storage volume for the final build out condition. The purpose of the WQCV is to allow particulates to settle out and accumulate over time to improve water quality and to maintain full volume for detention during the life of the facility for a major storm event. 332 acres are tributary to the detention pond during the developed condition resulting in a required WQCV of 1.6 ac-ft.

The WQCV of 1.6 ac-ft. was added to the detention of the minor storm and half (0.8 ac-ft.) was added to the detention volume of the major storm. This was accomplished with respect to the HEC-HMS computer run by providing a starting detention volume of 1.6 ft. for the 5-year storm and 0.8 ft. for the 100-year storm. The resulting storage elevations remain well below the emergency spillway elevation. See Appendix B for more information.

The WQCV was calculated by using the equations found in Volume 2, of the Drainage Criteria Manual (DCM). The release rate from the WQCV is generally very small, which helps minimize downstream impacts. Detaining the WQCV also serves to cleanse the “first flush” of runoff from the higher initial concentration of sediment and pollutants by allowing for settlement to occur. This greatly improves the quality of runoff, leaving the facility and reduces the potential for erosion. The positive impact on water quality is expected to be significant, particularly during the construction phase of the development. An established wetland is located downstream of the existing Pond E which acts as a final bio-cleanse for the storm water negating any need for a micro-pool.

## **EROSION CONTROL DESIGN**

### ***General Concept***

Historically, erosion on this property has been held to a minimum by a variety of natural features and agricultural practices including:

- Substantial prairie grass growth
- Construction of drainage arresting berms
- Construction of multiple stock ponds along drainage courses

Existing detention ponds will also help to minimize erosion by reducing both the volume and velocity of the peak runoff.

During construction, best management practices (BMP) for erosion control will be employed based on El Paso county Criteria. BMP's will be utilized as deemed necessary by the contractor and/or engineer and are not limited to the measures shown on the construction drawing set. The contractor shall minimize the amount of area disturbed during all construction activities.

In general the following shall be applied in developing the sequence of major activities:

- Install down-slope and side-slope perimeter BMP's before the land disturbing activity occurs.
- Do not disturb an area until it is necessary for the construction activity to proceed
- Cover or stabilize as soon as possible.
- Time the construction activities to reduce the impacts from seasonal climatic changes or weather events.
- The construction of filtration BMP's should wait until the end of the construction project when upstream drainage areas have been stabilized.
- Do not remove the temporary perimeter controls until after all upstream areas are stabilized.

### ***Four Step Process***

The following four step process is recommended for selecting structural BMP's in developing urban areas:

#### **Step 1: Employ Runoff Reduction Practices**

This development incorporates wider rights-of-way than other developments, thus decreasing the amount area devoted to pavement. The rights-of-way within Meridian Ranch are 20% wider, 60 ft. instead of 50 ft., creating more landscaped area within the development.

The project has over ten acres of open space, accounting for over 20% of the entire project, creating a lower density development.

Home owners and builders are encouraged to direct roof drains to the sideyards where the runoff will travel overland to the streets and creating an opportunity to allow the runoff to infiltrate into the ground.

#### **Step 2: Stabilize Drainageways**

The drainage swale located adjacent and south of the project was designed to have a wide flat bottom and slope reducing the velocity of the concentrated flow traveling along the drainageway. The construction of the swale also included erosion control mat along the entire length of the swale. At steeper sections of the swale straw logs or rip-rap has been installed to reduce velocities and erosion.

**Step 3: Provide Water Quality Capture Volume (WQCV)**

An existing extended detention pond with water quality capture volume is located to the east of the project that was designed to accommodate the runoff from this development.

**Step 4: Consider Need for Industrial and Commercial BMP's**

This project is neither industrial nor commercial and therefore this section does not apply.

***Detention Pond***

The existing (E, Bennett and Sedimentation) and proposed (H) detention ponds will act as the primary sedimentation control facility for the areas upstream. The ponds serve a dual purpose: first, by facilitating the settling of sediment in runoff during and after construction (by means of the WQCV) and, second, by maintaining runoff at or below existing levels.

***Silt Fence***

Silt fence will be placed along downstream limits of disturbed areas. This will prevent suspended sediment from leaving the site during infrastructure construction. Silt fencing is to remain in place until vegetation is reestablished.

***Erosion Bales***

Erosion bales will be placed ten (10) feet from the inlet of all culverts during construction to prevent culverts from filling with sediment. Erosion bales will remain in place until vegetation is reestablished. Erosion bale checks will be used on slopes greater than 1 percent to reduce flow velocities until vegetation is reestablished.

***Miscellaneous***

Best erosion control practices will be utilized as deemed necessary by the Contractor or Engineer and are not limited to the measures described above.

**DRAINAGE FEES**

There are no fees associated with project as the grading is not a part of the Land Development Process.

---

Drainage Fees:        There are no drainage fees for this project until Final Plat.

---

Bridge Fees:         There are no bridge fees for this project until Final Plat.

---

## REFERENCES

1. “City of Colorado Springs/El Paso County Drainage Criteria Manual” September 1987, Revised November 1991, Revised October 1994.
2. Chapter 6, Hydrology and Chapter 11, Storage, Section 3.2.1 of the “City of Colorado Springs Drainage Criteria Manual” May 2014.
3. “Volume 2, El Paso County/City of Colorado Springs Drainage Criteria Manual-Stormwater Quality Policies, Procedures and Best Management Practices” November 1, 2002.
4. Flood Insurance Rate Study for El Paso County, Colorado and Incorporated Areas. Federal Emergency Management Agency, Revised March 17, 1997.
5. Soils Survey of El Paso County area, Natural Resources Conservation Services of Colorado.
6. Master Development Drainage Plan Meridian Ranch. August 2000. Prepared by URS Corp.
7. Revision to Master Development Drainage Plan Meridian Ranch. May 2015. Prepared by Tech Contractors.
8. Master Development Drainage Plan Latigo Trails. October 2001. Prepared by URS Corp.
9. Final Drainage Report for Meridian Ranch Filing 1. November 2001. Prepared by URS Corp.
10. Preliminary Drainage Plan for Meridian Ranch Phase II. September 2003. Prepared by URS.
11. Final Drainage Plan for The Trails Filing No.7. March 2005. Prepared by URS.
12. Final Drainage Report for Meridian Ranch Filing 3. August 2011. Prepared by Tech Contractors.
13. Preliminary and Final Drainage Report for Meridian Ranch Filing 7. June 2012. Prepared by Tech Contractors.
14. Final Drainage Report for Meridian Ranch Estates Filing 2. July 2013. Prepared by Tech Contractors.
15. Final Drainage Report for Meridian Ranch Filing 11A. March 2014. Prepared by Tech Contractors.

16. Preliminary and Final Drainage Report for Meridian Ranch Filing 8. December 2014. Prepared by Tech Contractors.
17. Preliminary and Final Drainage Report for Meridian Ranch Filing 4B. April 2014. Prepared by Tech Contractors.
18. Final Drainage Report for Stonebridge Filing 1 at Meridian Ranch. June 2014. Prepared by Tech Contractors.
19. Final Drainage Report for Meridian Ranch Filing 9. May 2015. Prepared by Tech Contractors.
20. Revision to Master Development Drainage Plan Meridian Ranch. July 2015. Prepared by Tech Contractors.
21. Final Drainage Report for Meridian Ranch Estates Filing 3. October 2015. Prepared by Tech Contractors.
22. Final Drainage Report for the Vistas Filing 1 at Meridian Ranch. July 2016. Prepared by Tech Contractors.
23. Final Drainage Report for Stonebridge Filing 2 at Meridian Ranch. September 2016. Prepared by Tech Contractors.
24. Final Drainage Report for Stonebridge Filing 3 at Meridian Ranch. April 2017. Prepared by Tech Contractors.
25. Revision to Master Development Drainage Plan Meridian Ranch. November 2017. Prepared by Tech Contractors.

## **Appendices**





## Appendix A - HEC-HMS Data



## Input Data Winding Walk Grading

BASIN	AREA		CURVE NO.	PERCENT IMPERV.	LAG TIME (min)	
	(acre)	(mi <sup>2</sup> )				
<b>HISTORIC</b>						
OS01	998	1.5594	62.9	7%	35.5	
OS02	142	0.2219	64.5	8%	25.5	
OS03	127	0.1984	63.2	5%	23.6	
OS04	87	0.1359	61.0	0%	21.4	
HB01	15	0.0234	61.0	0%	12.6	
HB02	68	0.1063	61.0	0%	16.2	
HB03	81	0.1266	61.0	0%	13.2	
HB04	39	0.0609	61.0	0%	14.4	
HB05	88	0.1375	61.0	0%	15.6	
HB06	105	0.1641	61.0	0%	18.0	
HB07	20	0.0313	61.0	0%	10.2	
HB08	86	0.1344	61.0	0%	21.6	
HB09	195	0.3047	61.0	0%	33.0	
HB10	195	0.3047	61.0	0%	24.0	
HB12	51	0.0797	61.0	0%	18.0	
B-11	72	0.1125	61.0	0%	25.8	
B-13	180	0.2813	61.0	0%	33.0	
B-14	259	0.4039	61.0	0%	34.2	
B-15	48	0.0750	61.0	0%	27.0	
<b>GRADED</b>						
HG07	63	0.0984	61.0	0%	28.3	
HG08	85	0.1328	61.0	0%	22.9	
HG09	114	0.1781	61.0	0%	35.6	
HG10	88	0.1375	61.0	0%	61.4	
HG11	131	0.2047	61.0	0%	40.4	
HG12	83	0.1297	61.0	0%	32.0	
HH01	63	0.0984	61.0	0%	16.6	

<b>GRADED</b>						
OS01	998	1.5594	62.9	7%	35.5	
OS02	142	0.2219	64.5	8%	25.5	
OS03	127	0.1984	63.2	5%	23.6	
OS04	87	0.1359	61.0	0%	21.4	
DB01	46	0.0719	69.7	24%	13.7	
DB02	33	0.0516	69.0	22%	10.5	
DB03	45	0.0703	65.8	13%	15.0	
DB04	27	0.0422	66.8	16%	15.3	
DB05	25	0.0384	68.0	20%	19.1	
DB06	14	0.0219	84.0	63%	14.6	
DB07	16	0.0254	70.0	25%	11.7	
DB08	19	0.0297	64.9	10%	11.9	
DB09	12	0.0189	75.0	40%	9.6	
DB10	23	0.0364	75.0	40%	13.7	
DB11	62	0.0969	72.0	31%	18.4	

BASIN	AREA		CURVE NO.	PERCENT IMPERV.	LAG TIME (min)	
	(acre)	(mi <sup>2</sup> )				
<b>GRADED</b>						
DB12	29	0.0453	78.2	43%	12.7	
DB13	45	0.0703	73.9	33%	18.6	
DB14	36	0.0556	78.0	43%	14.6	
DB15	79	0.1234	67.1	17%	21.8	
DB16	37	0.0578	78.5	47%	16.4	
DB17	3	0.0048	98.0	100%	7.4	
DB18	22	0.0346	80.0	47%	13.4	
DB19	18	0.0281	72.6	29%	16.2	
DB20	9	0.0147	78.7	46%	15.2	
DB21	33	0.0519	65.6	11%	13.6	
DB22	33	0.0516	80.0	48%	14.8	
DB23	11	0.0172	91.6	81%	11.3	
DB24	34	0.0531	78.5	43%	13.3	
DB25	14	0.0211	80.0	47%	9.7	
DB26	44	0.0692	85.8	72%	16.1	
DB27	33	0.0508	78.1	42%	21.9	
DB28	47	0.0741	67.0	7%	17.6	
DB29	109	0.1697	68.5	22%	23.9	
FB01	24	0.0373	66.6	0%	20.7	
FB02	32	0.0500	67.0	0%	19.2	
FB03	5	0.0078	87.9	68%	9.0	
WH-24	85	0.1325	79.0	46%	16.0	
WH-26	54	0.0839	62.0	2%	25.1	
WH-27	14	0.0217	62.0	2%	8.6	
WH-28	26	0.0398	78.3	44%	17.7	
WH-29	32	0.0495	78.0	43%	16.6	
WH-30	10	0.0159	68.6	19%	6.0	
WH-31	26	0.0406	80.0	47%	13.2	
WH-32	29	0.0458	62.0	2%	6.0	
WH-33	4	0.0064	80.0	47%	13.0	
WH-34	29	0.0453	75.0	N/A	14.4	
WH-35	99	0.1547	68.0	N/A	15.0	
WH-36	48	0.0750	63.0	N/A	15.6	
FG08A	48	0.0750	76.8	43%	13.3	✓
FG08B	40	0.0630	76.7	40%	16.6	✓
FG09	31	0.0484	71.7	27%	20.8	
HG10	30	0.0467	63.2	6%	23.1	
FG11	40	0.0625	78.2	44%	23.2	
FG12	21	0.0328	80.0	47%	16.1	
FG13	42	0.0661	66.9	14%	29.6	
HG15	19	0.0297	62.1	3%	35.0	
FG15a	10	0.0156	78.7	44%	11.2	
FG16	50	0.0773	78.8	45%	13.0	
FG17a	44	0.0694	76.5	39%	14.4	✓✓
FG17b	14	0.0214	79.9	47%	11.4	✓✓
FG17c	20	0.0313	65.2	10%	11.8	✓✓
FG18	41	0.0644	64.9	1%	29.9	✧
FG19	34	0.0527	76.8	38%	15.3	✓✓

BASIN	AREA		CURVE NO.	PERCENT IMPERV.	LAG TIME (min)
	(acre)	(mi <sup>2</sup> )			
GRADED					
FG20	7	0.0109	92.9	86%	10.1
HG30	118	0.1844	61.0	0%	65.1
FG31	59	0.0922	80.0	52%	24.0
FH01	86	0.1344	66.9	1%	30.9
FH02	9	0.0138	70.7	15%	13.1

FUTURE						
OS01	998	1.5594	62.9	7%	35.5	◆◆
OS02	142	0.2219	64.5	8%	25.5	◆◆
OS03	127	0.1984	63.2	5%	23.6	◆◆
OS04	87	0.1359	61.0	0%	21.4	◆◆
DB01	46	0.0719	69.7	24%	13.7	◆◆
DB02	33	0.0516	69.0	22%	10.5	◆◆
DB03	45	0.0703	65.8	13%	15.0	◆◆
DB04	27	0.0422	66.8	16%	15.3	◆◆
DB05	25	0.0384	68.0	20%	19.1	◆◆
DB06	14	0.0219	84.0	63%	14.6	◆◆
DB07	16	0.0254	70.0	25%	11.7	◆◆
DB08	19	0.0297	64.9	10%	11.9	◆◆
DB09	12	0.0189	75.0	40%	9.6	◆◆
DB10	23	0.0364	75.0	40%	13.7	◆◆
DB11	62	0.0969	72.0	31%	18.4	◆◆
DB12	29	0.0453	78.2	43%	12.7	◆◆
DB13	45	0.0703	73.9	33%	18.6	◆◆
DB14	36	0.0556	78.0	43%	14.6	◆◆
DB15	79	0.1234	67.1	17%	21.8	◆◆
DB16	37	0.0578	78.5	47%	16.4	◆◆
DB17	3	0.0048	98.0	100%	7.4	◆◆
DB18	22	0.0346	80.0	47%	13.4	◆◆
DB19	18	0.0281	72.6	29%	16.2	◆◆
DB20	9	0.0147	78.7	46%	15.2	◆◆
DB21	33	0.0519	65.6	11%	13.6	◆◆
DB22	33	0.0516	80.0	48%	14.8	◆◆
DB23	11	0.0172	91.6	81%	11.3	◆◆
DB24	34	0.0531	78.5	43%	13.3	◆◆
DB25	14	0.0211	80.0	47%	9.7	◆◆
DB26	44	0.0692	85.8	72%	16.1	◆◆
DB27	33	0.0508	78.1	42%	21.9	◆◆
DB28	47	0.0741	70.7	24%	17.6	◆◆
DB29	109	0.1697	68.5	22%	23.9	◆◆
FB01	24	0.0373	77.7	41%	14.2	◆◆
FB02	32	0.0500	79.1	45%	22.8	◆◆
FB03	5	0.0078	90.1	78%	9.0	◆◆
WH-24	85	0.1325	79.0	46%	16.0	◆◆
WH-26	54	0.0839	62.0	2%	25.1	◆◆
WH-27	14	0.0217	62.0	2%	8.6	◆◆
WH-28	26	0.0398	78.3	44%	17.7	◆◆
WH-29	32	0.0495	78.0	43%	16.6	◆◆
WH-30	10	0.0159	68.6	19%	6.0	◆◆

WH-33	4	0.0064	80.0	47%	13.0	
WH-34	29	0.0453	75.0	N/A	14.4	
WH-35	99	0.1547	68.0	N/A	15.0	
WH-36	48	0.0750	63.0	N/A	15.6	
FG08A	48	0.0750	76.8	43%	13.3	✓
FG08B	40	0.0630	76.7	40%	16.6	✓
FG09	31	0.0484	71.7	27%	20.8	
FG10	43	0.0669	72.7	29%	41.8	
FG11	40	0.0625	78.2	44%	23.2	
FG12	21	0.0328	80.0	47%	16.1	
FG13	42	0.0661	66.9	14%	29.6	
FG14	21	0.0331	77.5	42%	20.9	
FG15	65	0.1017	72.9	30%	25.9	
FG15a	10	0.0156	78.7	44%	11.2	
FG16	50	0.0773	78.8	45%	13.0	
FG17a	44	0.0694	76.5	39%	14.4	✓✓
FG17b	14	0.0214	79.9	47%	11.4	✓✓
FG17c	20	0.0313	65.2	10%	11.8	✓✓
FG18	41	0.0644	73.5	31%	29.9	✧
FG19	34	0.0527	80.3	48%	15.3	✓✓
FG19a	5	0.0077	75.2	36%	16.4	✓✓
FG20	7	0.0109	92.9	86%	10.1	
FH01	86	0.1344	76.2	38%	23.4	
FH02	6	0.0091	71.3	25%	14.6	
FH03	5	0.0081	80.7	52%	14.4	
4W-H6B	22	0.0344	64.0	9%	6.8	
4W-B	52	0.0806	64.0	9%	8.3	
4W-C	53	0.0827	64.0	9%	10.8	
4W-D	36	0.0558	64.0	9%	12.6	
4W-E	21	0.0322	64.0	9%	6.8	

✧	From Meridian Ranch Drainage Reports (Windingwalk Rational Calcs., September 2017)
✓	From Retrofit Drainage Analysis For Bennett Regional Detention Pond, Jun 2014)
	From Approved Meridian Ranch Filing MDDP, Aug 2015
✧✧	From Approved Meridian Ranch Final Drainage Reports (Stonebridge Filing 2, Oct 2016)
	From Estates Filing 2 Final Drainage Report, July 2013
✧	From Estates Filing 3 Final Drainage Report, Nov 2015
✓	From Meridian Ranch Filing 11b Approved Final Drainage Report, Nov 2014
✧✧	From Meridian Ranch Filing 3 Approved Final Drainage Report, Aug 2012
✧	From Meridian Ranch Filing 7 Approved Final Drainage Report, Aug 2012
	From Meridian Ranch Filing 8 Approved Final Drainage Report, Feb 2015
✓	From Meridian Ranch Filing 9 Approved Final Drainage Report, July 2015
✓✓	From Stonebridge Filing 3 Approved Final Drainage Report, April 2017



NOAA Atlas 14, Volume 6, Version 2  
 Location name: Peyton, Colorado, USA\*  
 Latitude: 38.9783°, Longitude: -104.8842°  
 Elevation: 7054.14 ft\*



\* source: E8RI Maps  
 \*\* source: USGS

**POINT PRECIPITATION FREQUENCY ESTIMATES**

Benja Petras, Deborah Meath, Sandra Perovich, Ishant Roy, Michael Di Laurent, Carl Tysalluk,  
 Dale Urrut, Michael Yelton, Geoffrey Bannin

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

**PF tabular**

**PDF-based point precipitation frequency estimates with 90% confidence intervals (in inches)<sup>1</sup>**

Duration	Average recurrence Interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.239 (0.190-0.301)	0.281 (0.232-0.327)	0.341 (0.302-0.482)	0.400 (0.353-0.595)	0.576 (0.442-0.764)	0.870 (0.501-0.997)	0.770 (0.598-1.05)	0.870 (0.500-1.23)	1.02 (0.590-1.45)	1.14 (0.737-1.65)
10-min	0.348 (0.278-0.441)	0.426 (0.338-0.538)	0.558 (0.443-0.705)	0.874 (0.632-0.957)	0.843 (0.647-1.12)	0.882 (0.734-1.32)	1.13 (0.814-1.55)	1.28 (0.888-1.80)	1.50 (0.908-2.16)	1.67 (1.08-2.44)
15-min	0.426 (0.340-0.538)	0.518 (0.413-0.660)	0.680 (0.540-0.801)	0.822 (0.648-1.04)	1.03 (0.788-1.38)	1.20 (0.885-1.81)	1.37 (0.989-1.89)	1.58 (1.08-2.20)	1.82 (1.22-2.54)	2.03 (1.31-2.87)
30-min	0.568 (0.486-0.768)	0.741 (0.630-0.938)	0.969 (0.788-1.23)	1.17 (0.923-1.48)	1.46 (1.12-1.94)	1.70 (1.27-2.25)	1.93 (1.41-2.68)	2.31 (1.53-3.12)	2.58 (1.72-3.73)	2.87 (1.88-4.20)
60-min	0.778 (0.620-0.982)	0.934 (0.744-1.18)	1.21 (0.982-1.54)	1.47 (1.16-1.88)	1.84 (1.42-2.48)	2.18 (1.62-2.81)	2.50 (1.81-3.44)	2.87 (1.88-4.05)	3.38 (2.25-4.81)	3.80 (2.48-5.58)
2-hr	0.948 (0.782-1.18)	1.13 (0.905-1.41)	1.46 (1.16-1.83)	1.78 (1.40-2.22)	2.23 (1.73-2.88)	2.82 (1.98-3.91)	3.08 (2.23-4.18)	3.82 (2.47-4.88)	4.18 (2.82-5.04)	4.73 (3.08-6.87)
3-hr	1.04 (0.839-1.28)	1.22 (0.985-1.52)	1.57 (1.26-1.86)	1.90 (1.51-2.38)	2.41 (1.90-3.21)	2.96 (2.18-3.83)	3.35 (2.47-4.58)	3.90 (2.75-5.47)	4.68 (3.18-6.75)	5.33 (3.50-7.71)
6-hr	1.21 (0.980-1.48)	1.48 (1.14-1.73)	1.78 (1.44-2.21)	2.18 (1.74-2.88)	2.78 (2.19-3.85)	3.29 (2.53-4.38)	3.88 (2.88-5.28)	4.83 (3.23-6.84)	5.48 (3.76-7.88)	6.28 (4.17-8.84)
12-hr	1.38 (1.14-1.70)	1.62 (1.23-1.96)	2.08 (1.68-2.68)	2.48 (2.02-3.08)	3.18 (2.63-4.14)	3.78 (2.92-4.98)	4.42 (3.31-5.87)	5.18 (3.70-7.14)	6.22 (4.30-8.88)	7.10 (4.76-10.1)
24-hr	1.81 (1.33-1.95)	1.88 (1.65-2.28)	2.38 (1.97-2.92)	2.88 (2.35-3.52)	3.53 (2.91-4.88)	4.27 (3.34-5.68)	4.98 (3.76-6.88)	5.78 (4.17-7.88)	6.87 (4.78-9.70)	7.78 (5.25-11.1)






<b>HISTORIC 100-YEAR</b>				
<b>HYDROLOGIC ELEMENT</b>	<b>DRAINAGE AREA (SQ. MI.)</b>	<b>DISCHARGE PEAK Q<sub>100</sub> (CFS)</b>	<b>TIME OF PEAK</b>	<b>TOTAL VOLUME Q<sub>100</sub> (AC. FT.)</b>
OS02	0.2219	148	01Jul2015, 12:20	19
B01	0.2219	148	01Jul2015, 12:20	19
B01-B07	0.2219	148	01Jul2015, 12:24	19
OS03	0.1984	130	01Jul2015, 12:18	16
B02-B03	0.1984	129	01Jul2015, 12:20	16
HB01	0.0234	19	01Jul2015, 12:08	2
B03	0.2218	140	01Jul2015, 12:20	17
B03-B07	0.2218	140	01Jul2015, 12:22	17
OS04	0.1359	83	01Jul2015, 12:16	10
B04-B05	0.1359	82	01Jul2015, 12:24	10
HB03	0.1266	103	01Jul2015, 12:08	9
B05	0.2625	144	01Jul2015, 12:16	19
B05-B07	0.2625	144	01Jul2015, 12:16	19
HB02	0.1063	77	01Jul2015, 12:12	8
HB04	0.0609	47	01Jul2015, 12:10	4
B07	0.8734	519	01Jul2015, 12:18	67
B07-B12	0.8734	518	01Jul2015, 12:24	66
HB05	0.1375	102	01Jul2015, 12:10	10
HB06	0.1641	111	01Jul2015, 12:14	12
B12	1.1750	679	01Jul2015, 12:20	88
B12-PB	1.1750	677	01Jul2015, 12:22	88
HB07	0.0313	29	01Jul2015, 12:06	2
POND B	1.2063	688	01Jul2015, 12:22	90
PB-19	1.2063	687	01Jul2015, 12:26	89
OS01	1.5594	757	01Jul2015, 12:32	122
OS01-B19	1.5594	756	01Jul2015, 12:38	121
HB08	0.1344	81	01Jul2015, 12:16	10
HB09	0.3047	138	01Jul2015, 12:30	22
B19	3.2048	1563	01Jul2015, 12:30	241
B19-B26	3.2048	1563	01Jul2015, 12:32	241
HB10	0.3047	172	01Jul2015, 12:20	22
HB12	0.0797	54	01Jul2015, 12:14	6
HB12-B26	0.0797	54	01Jul2015, 12:16	6
<b>B26</b>	<b>3.5892</b>	<b>1737</b>	<b>01Jul2015, 12:30</b>	<b>268</b>
26-32	3.5892	1734	01Jul2015, 12:34	267
HB11	0.1125	60	01Jul2015, 12:22	8
32	3.7017	1782	01Jul2015, 12:34	275
32-37	3.7017	1782	01Jul2015, 12:36	273
B-14	0.4039	178	01Jul2015, 12:32	29
B-13	0.2813	127	01Jul2015, 12:30	20
36	0.6852	306	01Jul2015, 12:30	49
36-37	0.6852	305	01Jul2015, 12:34	49
B-15	0.0750	39	01Jul2015, 12:22	5
<b>37</b>	<b>4.4619</b>	<b>2117</b>	<b>01Jul2015, 12:36</b>	<b>327</b>

HISTORIC 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
HG07	0.0984	50	01Jul2015, 12:24	7
HG07-G11	0.0984	50	01Jul2015, 12:28	7
HG08	0.1328	77	01Jul2015, 12:18	10
G11	0.2312	122	01Jul2015, 12:22	17
G11-G12	0.2312	121	01Jul2015, 12:26	16
HG09	0.1781	76	01Jul2015, 12:32	13
G12	0.4093	196	01Jul2015, 12:28	29
G12-H08	0.4093	196	01Jul2015, 12:38	28
HG10	0.1375	40	01Jul2015, 13:04	10
H08	0.5468	227	01Jul2015, 12:40	38
HG11	0.2047	80	01Jul2015, 12:38	15
H09	0.2047	80	01Jul2015, 12:38	15
HH01	0.0984	70	01Jul2015, 12:12	7
H12	0.0984	70	01Jul2015, 12:12	7
HG12	0.1297	60	01Jul2015, 12:28	9
H10	0.1297	60	01Jul2015, 12:28	9


BENNETT HISTORIC



HISTORIC 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
OS02	0.2219	102	01Jul2015, 12:22	14
B01	0.2219	102	01Jul2015, 12:22	14
B01-B07	0.2219	102	01Jul2015, 12:24	14
OS03	0.1984	88	01Jul2015, 12:20	11
B02-B03	0.1984	88	01Jul2015, 12:22	11
HB01	0.0234	13	01Jul2015, 12:08	1
B03	0.2218	95	01Jul2015, 12:20	12
B03-B07	0.2218	94	01Jul2015, 12:24	12
OS04	0.1359	54	01Jul2015, 12:18	7
B04-B05	0.1359	54	01Jul2015, 12:26	7
HB03	0.1266	68	01Jul2015, 12:08	6
B05	0.2625	91	01Jul2015, 12:18	13
B05-B07	0.2625	91	01Jul2015, 12:20	13
HB02	0.1063	51	01Jul2015, 12:12	5
HB04	0.0609	31	01Jul2015, 12:10	3
B07	0.8734	344	01Jul2015, 12:20	47
B07-B12	0.8734	343	01Jul2015, 12:26	47
HB05	0.1375	67	01Jul2015, 12:12	7
HB06	0.1641	73	01Jul2015, 12:14	8
B12	1.1750	440	01Jul2015, 12:22	62
B12-PB	1.1750	440	01Jul2015, 12:24	62
HB07	0.0313	19	01Jul2015, 12:06	2
POND B	1.2063	446	01Jul2015, 12:24	64
PB-19	1.2063	444	01Jul2015, 12:28	63
OS01	1.5594	510	01Jul2015, 12:34	87
OS01-B19	1.5594	509	01Jul2015, 12:40	86
HB08	0.1344	53	01Jul2015, 12:18	7
HB09	0.3047	90	01Jul2015, 12:32	15
B19	3.2048	1041	01Jul2015, 12:34	171
B19-B26	3.2048	1039	01Jul2015, 12:34	171
HB10	0.3047	113	01Jul2015, 12:20	15
HB12	0.0797	36	01Jul2015, 12:14	4
HB12-B26	0.0797	35	01Jul2015, 12:18	4
B26	3.5892	1147	01Jul2015, 12:34	190
26-32	3.5892	1146	01Jul2015, 12:36	189
HB11	0.1125	40	01Jul2015, 12:22	6
32	3.7017	1177	01Jul2015, 12:36	194
32-37	3.7017	1175	01Jul2015, 12:40	193
B-14	0.4039	117	01Jul2015, 12:32	20
B-13	0.2813	83	01Jul2015, 12:32	14
36	0.6852	200	01Jul2015, 12:32	34
36-37	0.6852	200	01Jul2015, 12:36	34
B-15	0.0750	26	01Jul2015, 12:24	4
37	4.4619	1391	01Jul2015, 12:38	231

HISTORIC 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
HG07	0.0984	32	01Jul2015, 12:26	5
HG07-G11	0.0984	32	01Jul2015, 12:30	5
HG08	0.1328	51	01Jul2015, 12:20	7
G11	0.2312	79	01Jul2015, 12:24	12
G11-G12	0.2312	79	01Jul2015, 12:28	11
HG09	0.1781	50	01Jul2015, 12:34	9
G12	0.4093	128	01Jul2015, 12:30	20
G12-H08	0.4093	128	01Jul2015, 12:42	20
HG10	0.1375	26	01Jul2015, 13:06	7
H08	0.5468	149	01Jul2015, 12:42	27
HG11	0.2047	53	01Jul2015, 12:40	10
H09	0.2047	53	01Jul2015, 12:40	10
HH01	0.0984	46	01Jul2015, 12:12	5
H12	0.0984	46	01Jul2015, 12:12	5
HG12	0.1297	39	01Jul2015, 12:30	7
H10	0.1297	39	01Jul2015, 12:30	7


### GIECK HISTORIC



HISTORIC 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
OS02	0.2219	65	01Jul2015, 12:22	9.3
B01	0.2219	65	01Jul2015, 12:22	9.3
B01-B07	0.2219	65	01Jul2015, 12:26	9.2
OS03	0.1984	55	01Jul2015, 12:20	7.7
B02-B03	0.1984	55	01Jul2015, 12:24	7.6
HB01	0.0234	8	01Jul2015, 12:08	0.8
B03	0.2218	59	01Jul2015, 12:22	8.4
B03-B07	0.2218	59	01Jul2015, 12:26	8.4
OS04	0.1359	32	01Jul2015, 12:18	4.5
B04-B05	0.1359	32	01Jul2015, 12:28	4.4
HB03	0.1266	41	01Jul2015, 12:10	4.2
B05	0.2625	52	01Jul2015, 12:24	8.7
B05-B07	0.2625	52	01Jul2015, 12:26	8.7
HB02	0.1063	30	01Jul2015, 12:12	3.6
HB04	0.0609	19	01Jul2015, 12:10	2.0
B07	0.8734	207	01Jul2015, 12:24	31.9
B07-B12	0.8734	207	01Jul2015, 12:30	31.5
HB05	0.1375	40	01Jul2015, 12:12	4.6
HB06	0.1641	43	01Jul2015, 12:14	5.5
B12	1.1750	259	01Jul2015, 12:26	41.6
B12-PB	1.1750	259	01Jul2015, 12:28	41.5
HB07	0.0313	12	01Jul2015, 12:06	1.0
POND B	1.2063	262	01Jul2015, 12:28	42.6
PB-19	1.2063	261	01Jul2015, 12:34	42.1
OS01	1.5594	316	01Jul2015, 12:36	58.6
OS01-B19	1.5594	315	01Jul2015, 12:44	57.8
HB08	0.1344	32	01Jul2015, 12:20	4.5
HB09	0.3047	54	01Jul2015, 12:34	10.1
B19	3.2048	635	01Jul2015, 12:38	114.5
B19-B26	3.2048	634	01Jul2015, 12:38	114.3
HB10	0.3047	67	01Jul2015, 12:22	10.1
HB12	0.0797	21	01Jul2015, 12:14	2.7
HB12-B26	0.0797	21	01Jul2015, 12:20	2.6
B26	3.5892	693	01Jul2015, 12:38	127.0
26-32	3.5892	693	01Jul2015, 12:42	126.0
HB11	0.1125	23	01Jul2015, 12:24	3.7
32	3.7017	709	01Jul2015, 12:42	129.8
32-37	3.7017	708	01Jul2015, 12:44	128.7
B-14	0.4039	70	01Jul2015, 12:34	13.3
B-13	0.2813	50	01Jul2015, 12:34	9.3
36	0.6852	119	01Jul2015, 12:34	22.6
36-37	0.6852	119	01Jul2015, 12:38	22.5
B-15	0.0750	15	01Jul2015, 12:26	2.5
37	4.4619	834	01Jul2015, 12:44	153.7

HISTORIC 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
HG07	0.0984	19	01Jul2015, 12:28	3.3
HG07-G11	0.0984	19	01Jul2015, 12:32	3.2
HG08	0.1328	30	01Jul2015, 12:20	4.4
G11	0.2312	47	01Jul2015, 12:24	7.6
G11-G12	0.2312	47	01Jul2015, 12:32	7.5
HG09	0.1781	30	01Jul2015, 12:36	5.9
G12	0.4093	76	01Jul2015, 12:32	13.4
G12-H08	0.4093	76	01Jul2015, 12:46	13.1
HG10	0.1375	16	01Jul2015, 13:08	4.5
H08	0.5468	89	01Jul2015, 12:48	17.6
HG11	0.2047	31	01Jul2015, 12:42	6.7
H09	0.2047	31	01Jul2015, 12:42	6.7
HH01	0.0984	27	01Jul2015, 12:14	3.3
H12	0.0984	27	01Jul2015, 12:14	3.3
HG12	0.1297	23	01Jul2015, 12:32	4.3
H10	0.1297	23	01Jul2015, 12:32	4.3

MISC. HISTORIC



HISTORIC 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
OS02	0.2219	30	01 Jul2015, 12:26	5.1
B01	0.2219	30	01 Jul2015, 12:26	5.1
B01-B07	0.2219	30	01 Jul2015, 12:30	5.0
OS03	0.1984	23	01 Jul2015, 12:24	4.1
B02-B03	0.1984	23	01 Jul2015, 12:26	4.0
HB01	0.0234	3	01 Jul2015, 12:10	0.4
B03	0.2218	25	01 Jul2015, 12:26	4.4
B03-B07	0.2218	25	01 Jul2015, 12:30	4.4
OS04	0.1359	12	01 Jul2015, 12:22	2.3
B04-B05	0.1359	12	01 Jul2015, 12:34	2.2
HB03	0.1266	15	01 Jul2015, 12:12	2.1
B05	0.2625	20	01 Jul2015, 12:30	4.4
B05-B07	0.2625	20	01 Jul2015, 12:32	4.4
HB02	0.1063	11	01 Jul2015, 12:16	1.8
HB04	0.0609	7	01 Jul2015, 12:12	1.0
B07	0.8734	86	01 Jul2015, 12:30	16.6
B07-B12	0.8734	86	01 Jul2015, 12:38	16.4
HB05	0.1375	15	01 Jul2015, 12:14	2.3
HB06	0.1641	16	01 Jul2015, 12:18	2.8
B12	1.1750	103	01 Jul2015, 12:36	21.5
B12-PB	1.1750	103	01 Jul2015, 12:38	21.4
HB07	0.0313	4	01 Jul2015, 12:08	0.5
POND B	1.2063	105	01 Jul2015, 12:38	22.0
PB-19	1.2063	104	01 Jul2015, 12:46	21.7
OS01	1.5594	136	01 Jul2015, 12:38	30.9
OS01-B19	1.5594	136	01 Jul2015, 12:48	30.4
HB08	0.1344	12	01 Jul2015, 12:22	2.3
HB09	0.3047	21	01 Jul2015, 12:38	5.1
B19	3.2048	266	01 Jul2015, 12:46	59.4
B19-B26	3.2048	266	01 Jul2015, 12:48	59.2
HB10	0.3047	26	01 Jul2015, 12:26	5.1
HB12	0.0797	8	01 Jul2015, 12:18	1.3
HB12-B26	0.0797	8	01 Jul2015, 12:24	1.3
B26	3.5892	288	01 Jul2015, 12:48	65.7
26-32	3.5892	287	01 Jul2015, 12:52	65.0
HB11	0.1125	9	01 Jul2015, 12:28	1.9
32	3.7017	293	01 Jul2015, 12:52	66.9
32-37	3.7017	293	01 Jul2015, 12:58	66.1
B-14	0.4039	27	01 Jul2015, 12:38	6.7
B-13	0.2813	19	01 Jul2015, 12:38	4.7
36	0.6852	47	01 Jul2015, 12:38	11.4
36-37	0.6852	47	01 Jul2015, 12:42	11.3
B-15	0.0750	6	01 Jul2015, 12:30	1.3
37	4.4619	338	01 Jul2015, 12:56	78.7

HISTORIC 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
HG07	0.0984	7	01 Jul 2015, 12:30	1.6
HG07-G11	0.0984	7	01 Jul 2015, 12:38	1.6
HG08	0.1328	11	01 Jul 2015, 12:24	2.2
G11	0.2312	18	01 Jul 2015, 12:30	3.9
G11-G12	0.2312	18	01 Jul 2015, 12:38	3.8
HG09	0.1781	12	01 Jul 2015, 12:40	3.0
G12	0.4093	29	01 Jul 2015, 12:38	6.8
G12-H08	0.4093	29	01 Jul 2015, 12:56	6.5
HG10	0.1375	7	01 Jul 2015, 13:18	2.2
H08	0.5468	35	01 Jul 2015, 12:58	8.8
HG11	0.2047	13	01 Jul 2015, 12:48	3.4
H09	0.2047	13	01 Jul 2015, 12:48	3.4
HH01	0.0984	10	01 Jul 2015, 12:16	1.7
H12	0.0984	10	01 Jul 2015, 12:16	1.7
HG12	0.1297	9	01 Jul 2015, 12:36	2.2
H10	0.1297	9	01 Jul 2015, 12:36	2.2



HISTORIC 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
OS02	0.2219	13	01Jul2015, 12:28	2.8
B01	0.2219	13	01Jul2015, 12:28	2.8
B01-B07	0.2219	13	01Jul2015, 12:34	2.8
OS03	0.1984	9	01Jul2015, 12:28	2.2
B02-B03	0.1984	9	01Jul2015, 12:32	2.2
HB01	0.0234	1	01Jul2015, 12:14	0.2
B03	0.2218	10	01Jul2015, 12:32	2.4
B03-B07	0.2218	10	01Jul2015, 12:36	2.4
OS04	0.1359	4	01Jul2015, 12:28	1.2
B04-B05	0.1359	4	01Jul2015, 12:44	1.1
HB03	0.1266	5	01Jul2015, 12:14	1.1
B05	0.2625	7	01Jul2015, 12:42	2.2
B05-B07	0.2625	7	01Jul2015, 12:44	2.2
HB02	0.1063	4	01Jul2015, 12:20	0.9
HB04	0.0609	2	01Jul2015, 12:16	0.5
B07	0.8734	33	01Jul2015, 12:38	8.9
B07-B12	0.8734	33	01Jul2015, 12:48	8.7
HB05	0.1375	5	01Jul2015, 12:18	1.2
HB06	0.1641	5	01Jul2015, 12:22	1.4
B12	1.175	40	01Jul2015, 12:48	11.3
B12-PB	1.175	39	01Jul2015, 12:52	11.3
HB07	0.0313	1	01Jul2015, 12:10	0.3
POND B	1.2063	40	01Jul2015, 12:52	11.5
PB-19	1.2063	40	01Jul2015, 13:00	11.3
OS01	1.5594	55	01Jul2015, 12:46	16.6
OS01-B19	1.5594	55	01Jul2015, 12:58	16.3
HB08	0.1344	4	01Jul2015, 12:28	1.2
HB09	0.3047	7	01Jul2015, 12:46	2.6
B19	3.2048	105	01Jul2015, 13:00	31.4
B19-B26	3.2048	105	01Jul2015, 13:02	31.3
HB10	0.3047	9	01Jul2015, 12:32	2.6
HB12	0.0797	3	01Jul2015, 12:22	0.7
HB12-B26	0.0797	3	01Jul2015, 12:30	0.7
<b>B26</b>	<b>3.5892</b>	<b>113</b>	<b>01Jul2015, 13:02</b>	<b>34.6</b>
26-32	3.5892	113	01Jul2015, 13:08	34
HB11	0.1125	3	01Jul2015, 12:34	1
32	3.7017	115	01Jul2015, 13:08	35
32-37	3.7017	115	01Jul2015, 13:14	34.5
B-14	0.4039	10	01Jul2015, 12:48	3.4
B-13	0.2813	7	01Jul2015, 12:46	2.4
36	0.6852	17	01Jul2015, 12:46	5.8
36-37	0.6852	17	01Jul2015, 12:54	5.8
B-15	0.075	2	01Jul2015, 12:36	0.6
<b>37</b>	<b>4.4619</b>	<b>131</b>	<b>01Jul2015, 13:14</b>	<b>40.9</b>

HISTORIC 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
HG07	0.0984	3	01Jul2015, 12:38	0.8
HG07-G11	0.0984	3	01Jul2015, 12:48	0.8
HG08	0.1328	4	01Jul2015, 12:30	1.1
G11	0.2312	6	01Jul2015, 12:40	2
G11-G12	0.2312	6	01Jul2015, 12:54	1.9
HG09	0.1781	4	01Jul2015, 12:50	1.5
G12	0.4093	10	01Jul2015, 12:52	3.4
G12-H08	0.4093	10	01Jul2015, 13:16	3.3
HG10	0.1375	3	01Jul2015, 13:30	1.1
H08	0.5468	13	01Jul2015, 13:18	4.4
HG11	0.2047	5	01Jul2015, 12:58	1.7
H09	0.2047	5	01Jul2015, 12:58	1.7
HH01	0.0984	3	01Jul2015, 12:20	0.9
H12	0.0984	3	01Jul2015, 12:20	0.9
HG12	0.1297	3	01Jul2015, 12:44	1.1
H10	0.1297	3	01Jul2015, 12:44	1.1

HISTORIC 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
OS02	0.2219	3.00	01 Jul 2015, 12:46	1.1
B01	0.2219	3.00	01 Jul 2015, 12:46	1.1
B01-B07	0.2219	3.00	01 Jul 2015, 12:56	1.1
OS03	0.1984	2.00	01 Jul 2015, 13:02	0.8
B02-B03	0.1984	2.00	01 Jul 2015, 13:08	0.8
HB01	0.0234	0.00	01 Jul 2015, 13:08	0.1
B03	0.2218	2.00	01 Jul 2015, 13:08	0.9
B03-B07	0.2218	2.00	01 Jul 2015, 13:16	0.8
OS04	0.1359	1.00	01 Jul 2015, 13:30	0.4
B04-B05	0.1359	1.00	01 Jul 2015, 13:58	0.3
HB03	0.1266	1.00	01 Jul 2015, 13:10	0.3
B05	0.2625	1.00	01 Jul 2015, 13:42	0.7
B05-B07	0.2625	1.00	01 Jul 2015, 13:46	0.7
HB02	0.1063	0.00	01 Jul 2015, 13:22	0.3
HB04	0.0609	0.00	01 Jul 2015, 13:16	0.2
B07	0.8734	6.00	01 Jul 2015, 13:26	3.1
B07-B12	0.8734	6.00	01 Jul 2015, 13:44	3.0
HB05	0.1375	1.00	01 Jul 2015, 13:20	0.4
HB06	0.1641	1.00	01 Jul 2015, 13:24	0.4
B12	1.1750	7.00	01 Jul 2015, 13:42	3.8
B12-PB	1.1750	7.00	01 Jul 2015, 13:46	3.8
HB07	0.0313	0.00	01 Jul 2015, 13:06	0.1
POND B	1.2063	7.00	01 Jul 2015, 13:46	3.9
PB-19	1.2063	7.00	01 Jul 2015, 14:02	3.7
OS01	1.5594	11.00	01 Jul 2015, 13:24	5.9
OS01-B19	1.5594	11.00	01 Jul 2015, 13:44	5.7
HB08	0.1344	1.00	01 Jul 2015, 13:30	0.4
HB09	0.3047	1.00	01 Jul 2015, 13:50	0.8
B19	3.2048	20.00	01 Jul 2015, 13:44	10.6
B19-B26	3.2048	20.00	01 Jul 2015, 13:48	10.6
HB10	0.3047	1.00	01 Jul 2015, 13:34	0.8
HB12	0.0797	0.00	01 Jul 2015, 13:24	0.2
HB12-B26	0.0797	0.00	01 Jul 2015, 13:38	0.2
B26	3.5892	21.00	01 Jul 2015, 13:46	11.6
26-32	3.5892	21.00	01 Jul 2015, 13:58	11.3
HB11	0.1125	0.00	01 Jul 2015, 13:38	0.3
32	3.7017	22.00	01 Jul 2015, 13:58	11.6
32-37	3.7017	22.00	01 Jul 2015, 14:10	11.3
B-14	0.4039	2.00	01 Jul 2015, 13:52	1.1
B-13	0.2813	1.00	01 Jul 2015, 13:50	0.7
36	0.6852	3.00	01 Jul 2015, 13:50	1.8
36-37	0.6852	3.00	01 Jul 2015, 14:02	1.8
B-15	0.0750	0.00	01 Jul 2015, 13:40	0.2
37	4.4619	25.00	01 Jul 2015, 14:10	13.2

HISTORIC 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
HG07	0.0984	0.00	01 Jul 2015, 13:42	0.3
HG07-G11	0.0984	0.00	01 Jul 2015, 13:58	0.3
HG08	0.1328	1.00	01 Jul 2015, 13:32	0.4
G11	0.2312	1.00	01 Jul 2015, 13:46	0.6
G11-G12	0.2312	1.00	01 Jul 2015, 14:08	0.6
HG09	0.1781	1.00	01 Jul 2015, 13:54	0.5
G12	0.4093	2.00	01 Jul 2015, 14:04	1.0
G12-H08	0.4093	2.00	01 Jul 2015, 14:50	0.9
HG10	0.1375	1.00	01 Jul 2015, 14:40	0.3
H08	0.5468	2.00	01 Jul 2015, 14:48	1.3
HG11	0.2047	1.00	01 Jul 2015, 14:04	0.5
H09	0.2047	1.00	01 Jul 2015, 14:04	0.5
HH01	0.0984	0.00	01 Jul 2015, 13:22	0.3
H12	0.0984	0.00	01 Jul 2015, 13:22	0.3
HG12	0.1297	1.00	01 Jul 2015, 13:48	0.3
H10	0.1297	1.00	01 Jul 2015, 13:48	0.3

INTERIM 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
OS01	1.5594	757	01 Jul2015, 12:32	122
DB16	0.0578	92	01 Jul2015, 12:10	8
B10	1.6172	794	01 Jul2015, 12:30	130
B10-B11	1.6172	793	01 Jul2015, 12:32	130
DB17	0.0048	16	01 Jul2015, 12:02	1
B11	1.6220	795	01 Jul2015, 12:32	131
B11-POND C	1.6220	795	01 Jul2015, 12:34	131
DB21	0.0519	54	01 Jul2015, 12:08	5
DB18	0.0346	64	01 Jul2015, 12:08	5
DB19	0.0281	36	01 Jul2015, 12:10	3
DB20	0.0147	25	01 Jul2015, 12:08	2
POND C	1.7513	749	01 Jul2015, 12:46	141
POND C-B16	1.7513	749	01 Jul2015, 12:48	141
DB25	0.0211	45	01 Jul2015, 12:04	3
B16	1.7724	754	01 Jul2015, 12:48	144
B16-B17	1.7724	754	01 Jul2015, 12:50	144
DB26	0.0682	136	01 Jul2015, 12:10	12
B17	1.8406	778	01 Jul2015, 12:50	156
B17-B18	1.8406	778	01 Jul2015, 12:52	156
OS03	0.1984	130	01 Jul2015, 12:18	16
DB01	0.0719	90	01 Jul2015, 12:08	8
B01	0.2703	199	01 Jul2015, 12:14	23
B01-B02	0.2703	199	01 Jul2015, 12:14	23
OS02	0.2219	148	01 Jul2015, 12:20	19
DB02	0.0516	71	01 Jul2015, 12:06	5
B02	0.5438	380	01 Jul2015, 12:14	48
B02-POND A	0.5438	379	01 Jul2015, 12:16	47
OS04	0.1359	83	01 Jul2015, 12:16	10
DB03	0.0703	70	01 Jul2015, 12:10	6
B03	0.2062	145	01 Jul2015, 12:12	16
B03-B04	0.2062	145	01 Jul2015, 12:18	16
DB04	0.0422	44	01 Jul2015, 12:10	4
DB05	0.0384	37	01 Jul2015, 12:14	4
B04	0.2868	218	01 Jul2015, 12:16	24
B04-B05	0.2868	218	01 Jul2015, 12:16	24
DB06	0.0219	44	01 Jul2015, 12:08	4
B05	0.3087	253	01 Jul2015, 12:14	28
B05-POND A	0.3087	252	01 Jul2015, 12:16	27
DB07	0.0254	35	01 Jul2015, 12:06	3
DB08	0.0297	32	01 Jul2015, 12:06	3
POND A	0.9076	554	01 Jul2015, 12:26	77
POND A-B06	0.9076	554	01 Jul2015, 12:26	77
DB09	0.0189	34	01 Jul2015, 12:04	2
B06	0.9265	562	01 Jul2015, 12:26	80
B06-B07	0.9265	561	01 Jul2015, 12:30	79
DB11	0.0969	114	01 Jul2015, 12:12	11
DB10	0.0364	56	01 Jul2015, 12:08	5
B07	1.0598	648	01 Jul2015, 12:26	95
B07-B09	1.0598	647	01 Jul2015, 12:28	95
DB12	0.0453	81	01 Jul2015, 12:06	7

INTERIM 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
B09	1.1051	672	01 Jul2015, 12:28	101
B09-POND B	1.1051	672	01 Jul2015, 12:28	101.1
DB15	0.1234	105	01 Jul2015, 12:16	12
DB13	0.0703	89	01 Jul2015, 12:12	9
DB14	0.0556	93	01 Jul2015, 12:08	8
POND B	1.3544	684	01 Jul2015, 12:42	129
POND B-B12	1.3544	684	01 Jul2015, 12:44	129
DB22	0.0516	91	01 Jul2015, 12:08	8
DB23	0.0172	45	01 Jul2015, 12:04	4
B12	1.4232	711	01 Jul2015, 12:38	140
B12-B14	1.4232	711	01 Jul2015, 12:38	140
DB24	0.0531	94	01 Jul2015, 12:08	8
B14	1.4763	740	01 Jul2015, 12:28	148
B14-B15	1.4763	738	01 Jul2015, 12:30	147
DB28	0.0741	72	01 Jul2015, 12:12	7
B15	1.5504	775	01 Jul2015, 12:28	154
B15-B18	1.5504	775	01 Jul2015, 12:34	153
DB29	0.1697	146	01 Jul2015, 12:18	17
DB27	0.0508	68	01 Jul2015, 12:16	7
<b>B26</b>	<b>3.6115</b>	<b>1606</b>	<b>01 Jul2015, 12:48</b>	<b>333</b>
B26-27	3.6115	1605	01 Jul2015, 12:48	332
FB-02	0.0500	46	01 Jul2015, 12:14	5
FB-01	0.0373	32	01 Jul2015, 12:16	4
FB01-27a	0.0373	32	01 Jul2015, 12:16	4
B19	0.0873	77	01 Jul2015, 12:14	8
B19-27	0.0873	77	01 Jul2015, 12:16	8
FB-03	0.0078	21	01 Jul2015, 12:04	2
27	3.7066	1634	01 Jul2015, 12:48	342
27-32	3.7066	1633	01 Jul2015, 12:48	341
WH-24	0.1325	218	01 Jul2015, 12:10	20
WH-26	0.0839	49	01 Jul2015, 12:20	6
WH-27	0.0217	23	01 Jul2015, 12:04	2
30	0.2381	271	01 Jul2015, 12:10	28
30-31	0.2381	270	01 Jul2015, 12:12	28
WH-28	0.0398	60	01 Jul2015, 12:12	6
31	0.2779	330	01 Jul2015, 12:12	33
31-32	0.2779	329	01 Jul2015, 12:14	33
WH-29	0.0495	77	01 Jul2015, 12:10	7
WH-31	0.0406	75	01 Jul2015, 12:06	6
WH-30	0.0159	26	01 Jul2015, 12:02	2
<b>32</b>	<b>4.0905</b>	<b>1773</b>	<b>01 Jul2015, 12:40</b>	<b>389</b>
WH32	0.0458	55	01 Jul2015, 12:02	4
BEN POND	4.1363	1379	01 Jul2015, 13:18	373
WH-33	0.0064	12	01 Jul2015, 12:06	1
33	4.1427	1380	01 Jul2015, 13:18	374
33-37	4.1427	1380	01 Jul2015, 13:20	372
WH35	0.1550	171	01 Jul2015, 12:10	15
WH34	0.0450	68	01 Jul2015, 12:08	6
B34-36	0.0450	68	01 Jul2015, 12:10	6
36	0.2000	239	01 Jul2015, 12:10	21

INTERIM 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
36-37	0.2000	238	01 Jul 2015, 12:12	21
WH36	0.0750	63	01 Jul 2015, 12:10	6
<b>37</b>	<b>4.4177</b>	<b>1419</b>	<b>01 Jul 2015, 13:20</b>	<b>399</b>
FG08A	0.075	125.2	01 Jul 2015, 12:08	10.3
FG08A-G05	0.0750	125	01 Jul 2015, 12:10	10
FG08B	0.0630	94	01 Jul 2015, 12:10	9
FG08B-G05	0.0630	93	01 Jul 2015, 12:12	9
FG11	0.0625	81	01 Jul 2015, 12:16	9
FG09	0.0484	52	01 Jul 2015, 12:14	6
FG09-G05	0.0484	52	01 Jul 2015, 12:16	6
HG10	0.0467	31	01 Jul 2015, 12:18	4
G05	0.2956	370	01 Jul 2015, 12:12	37
FG13	0.0661	46	01 Jul 2015, 12:24	6
FG12	0.0328	55	01 Jul 2015, 12:10	5
POND D	0.3945	108	01 Jul 2015, 13:00	39
POND D-G17	0.3945	107	01 Jul 2015, 13:00	39
HG15	0.0297	14	01 Jul 2015, 12:32	2
FG15a	0.0156	30	01 Jul 2015, 12:06	2
G17	0.4398	120	01 Jul 2015, 12:52	43
G17-G18	0.4398	120	01 Jul 2015, 12:52	43
FG16	0.0773	135	01 Jul 2015, 12:06	11
G18	0.5171	179	01 Jul 2015, 12:08	54
G18-POND E	0.5171	178	01 Jul 2015, 12:08	54
HG30	0.1844	51	01 Jul 2015, 13:08	13
FG30-PONDHS	0.1844	51	01 Jul 2015, 13:14	13
FG31	0.0922	123	01 Jul 2015, 12:18	14
POND HS	0.2766	103	01 Jul 2015, 12:34	27
FG17a	0.0694	117	01 Jul 2015, 12:08	10
FG17a-POND E	0.0694	116	01 Jul 2015, 12:08	10
FG18	0.0644	42	01 Jul 2015, 12:24	6
FG18-POND E	0.0644	42	01 Jul 2015, 12:26	6
FG19	0.0527	82	01 Jul 2015, 12:08	7
FG17c	0.0313	34	01 Jul 2015, 12:06	3
FG17b	0.0214	42	01 Jul 2015, 12:06	3
<b>POND E</b>	<b>1.0329</b>	<b>188</b>	<b>01 Jul 2015, 13:52</b>	<b>88</b>
FG20	0.0109	31	01 Jul 2015, 12:04	2
H08-H09	1.0438	189	01 Jul 2015, 13:52	90
FH01	0.1344	90	01 Jul 2015, 12:26	13
<b>POND H</b>	<b>0.1344</b>	<b>23</b>	<b>01 Jul 2015, 13:30</b>	<b>10</b>
FH02	0.0138	18	01 Jul 2015, 12:08	2
H12	0.1482	25	01 Jul 2015, 13:26	11

INTERIM 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
OS01	1.5594	510	01Jul2015, 12:34	87
DB16	0.0578	72	01Jul2015, 12:10	7
B10	1.6172	537	01Jul2015, 12:32	93
B10-B11	1.6172	537	01Jul2015, 12:32	93
DB17	0.0048	13	01Jul2015, 12:02	1
B11	1.6220	538	01Jul2015, 12:32	94
B11-POND C	1.6220	538	01Jul2015, 12:36	94
DB21	0.0519	38	01Jul2015, 12:08	3
DB18	0.0346	50	01Jul2015, 12:08	4
DB19	0.0281	27	01Jul2015, 12:10	3
DB20	0.0147	19	01Jul2015, 12:08	2
POND C	1.7513	507	01Jul2015, 12:48	101
POND C-B16	1.7513	507	01Jul2015, 12:50	101
DB25	0.0211	35	01Jul2015, 12:04	3
B16	1.7724	511	01Jul2015, 12:50	103
B16-B17	1.7724	510	01Jul2015, 12:54	103
DB26	0.0682	110	01Jul2015, 12:10	10
B17	1.8406	529	01Jul2015, 12:52	113
B17-B18	1.8406	529	01Jul2015, 12:54	113
OS03	0.1984	88	01Jul2015, 12:20	11
DB01	0.0719	66	01Jul2015, 12:08	6
B01	0.2703	139	01Jul2015, 12:14	17
B01-B02	0.2703	138	01Jul2015, 12:16	17
OS02	0.2219	102	01Jul2015, 12:22	14
DB02	0.0516	52	01Jul2015, 12:06	4
B02	0.5438	263	01Jul2015, 12:16	34
B02-POND A	0.5438	263	01Jul2015, 12:16	34
OS04	0.1359	54	01Jul2015, 12:18	7
DB03	0.0703	49	01Jul2015, 12:10	5
B03	0.2062	98	01Jul2015, 12:14	11
B03-B04	0.2062	98	01Jul2015, 12:18	11
DB04	0.0422	31	01Jul2015, 12:10	3
DB05	0.0384	27	01Jul2015, 12:14	3
B04	0.2868	150	01Jul2015, 12:16	17
B04-B05	0.2868	149	01Jul2015, 12:16	17
DB06	0.0219	35	01Jul2015, 12:08	3
B05	0.3087	176	01Jul2015, 12:16	20
B05-POND A	0.3087	176	01Jul2015, 12:16	20
DB07	0.0254	26	01Jul2015, 12:06	2
DB08	0.0297	22	01Jul2015, 12:06	2
POND A	0.9076	396	01Jul2015, 12:26	56
POND A-B06	0.9076	395	01Jul2015, 12:26	56
DB09	0.0189	26	01Jul2015, 12:04	2
B06	0.9265	401	01Jul2015, 12:26	57
B06-B07	0.9265	400	01Jul2015, 12:30	57
DB11	0.0969	85	01Jul2015, 12:12	9
DB10	0.0364	43	01Jul2015, 12:08	4
B07	1.0598	462	01Jul2015, 12:28	69
B07-B09	1.0598	461	01Jul2015, 12:32	69
DB12	0.0453	63	01Jul2015, 12:06	5



INTERIM 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
B09	1.1051	478	01Jul2015, 12:30	74
B09-POND B	1.1051	477.4	01Jul2015, 12:32	73.8
DB15	0.1234	75	01Jul2015, 12:16	9
DB13	0.0703	67	01Jul2015, 12:12	7
DB14	0.0556	72	01Jul2015, 12:08	6
POND B	1.3544	528	01Jul2015, 12:38	95
POND B-B12	1.3544	528	01Jul2015, 12:40	95
DB22	0.0516	72	01Jul2015, 12:08	6
DB23	0.0172	38	01Jul2015, 12:04	3
B12	1.4232	550	01Jul2015, 12:40	104
B12-B14	1.4232	550	01Jul2015, 12:40	104
DB24	0.0531	73	01Jul2015, 12:08	6
B14	1.4763	565	01Jul2015, 12:40	110
B14-B15	1.4763	564	01Jul2015, 12:42	110
DB28	0.0741	51	01Jul2015, 12:12	5
B15	1.5504	582	01Jul2015, 12:40	115
B15-B18	1.5504	582	01Jul2015, 12:46	114
DB29	0.1697	105	01Jul2015, 12:18	13
DB27	0.0508	53	01Jul2015, 12:16	6
<b>B26</b>	<b>3.6115</b>	<b>1158</b>	<b>01Jul2015, 12:50</b>	<b>244</b>
B26-27	3.6115	1158	01Jul2015, 12:52	244
FB-02	0.0500	33	01Jul2015, 12:14	4
FB-01	0.0373	23	01Jul2015, 12:16	3
FB01-27a	0.0373	23	01Jul2015, 12:16	3
B19	0.0873	55	01Jul2015, 12:16	6
B19-27	0.0873	55	01Jul2015, 12:16	6
FB-03	0.0078	17	01Jul2015, 12:04	1
27	3.7066	1178	01Jul2015, 12:50	251
27-32	3.7066	1178	01Jul2015, 12:52	250
WH-24	0.1325	171	01Jul2015, 12:10	15
WH-26	0.0839	33	01Jul2015, 12:22	5
WH-27	0.0217	16	01Jul2015, 12:04	1
30	0.2381	205	01Jul2015, 12:10	21
30-31	0.2381	205	01Jul2015, 12:12	21
WH-28	0.0398	47	01Jul2015, 12:12	5
31	0.2779	252	01Jul2015, 12:12	25
31-32	0.2779	251	01Jul2015, 12:14	25
WH-29	0.0495	60	01Jul2015, 12:10	6
WH-31	0.0406	60	01Jul2015, 12:08	5
WH-30	0.0159	19	01Jul2015, 12:02	1
<b>32</b>	<b>4.0905</b>	<b>1269</b>	<b>01Jul2015, 12:50</b>	<b>287</b>
WH32	0.0458	38	01Jul2015, 12:02	3
BEN POND	4.1363	966	01Jul2015, 13:16	273
WH-33	0.0064	9	01Jul2015, 12:06	1
33	4.1427	967	01Jul2015, 13:16	273
33-37	4.1427	967	01Jul2015, 13:20	272
WH35	0.1550	124	01Jul2015, 12:10	11
WH34	0.0450	52	01Jul2015, 12:08	5
B34-36	0.0450	52	01Jul2015, 12:10	5
36	0.2000	176	01Jul2015, 12:10	16

INTERIM 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
36-37	0.2000	174	01Jul2015, 12:14	16
WH36	0.0750	43	01Jul2015, 12:10	4
<b>37</b>	<b>4.4177</b>	<b>997</b>	<b>01Jul2015, 13:20</b>	<b>292</b>
FG08A	0.075	97	01Jul2015, 12:08	8
FG08A-G05	0.0750	97	01Jul2015, 12:10	8
FG08B	0.0630	72	01Jul2015, 12:10	7
FG08B-G05	0.0630	72	01Jul2015, 12:12	7
FG11	0.0625	63	01Jul2015, 12:16	7
FG09	0.0484	39	01Jul2015, 12:16	4
FG09-G05	0.0484	39	01Jul2015, 12:16	4
HG10	0.0467	21	01Jul2015, 12:18	3
G05	0.2956	281	01Jul2015, 12:12	29
FG13	0.0661	32	01Jul2015, 12:26	5
FG12	0.0328	44	01Jul2015, 12:10	4
POND D	0.3945	70	01Jul2015, 13:08	29
POND D-G17	0.3945	70	01Jul2015, 13:10	29
HG15	0.0297	9	01Jul2015, 12:34	2
FG15a	0.0156	24	01Jul2015, 12:06	2
G17	0.4398	77	01Jul2015, 13:04	32
G17-G18	0.4398	77	01Jul2015, 13:06	32
FG16	0.0773	105	01Jul2015, 12:08	9
G18	0.5171	135	01Jul2015, 12:08	40
G18-POND E	0.5171	134	01Jul2015, 12:08	40
HG30	0.1844	34	01Jul2015, 13:10	9
FG30-PONDHS	0.1844	34	01Jul2015, 13:18	9
FG31	0.0922	97	01Jul2015, 12:18	11
POND HS	0.2766	62	01Jul2015, 12:48	20
FG17a	0.0694	91	01Jul2015, 12:08	8
FG17a-POND E	0.0694	90	01Jul2015, 12:08	8
FG18	0.0644	30	01Jul2015, 12:26	4
FG18-POND E	0.0644	30	01Jul2015, 12:26	4
FG19	0.0527	63	01Jul2015, 12:10	6
FG17c	0.0313	24	01Jul2015, 12:06	2
FG17b	0.0214	34	01Jul2015, 12:06	3
<b>POND E</b>	<b>1.0329</b>	<b>113</b>	<b>01Jul2015, 14:32</b>	<b>62</b>
FG20	0.0109	26	01Jul2015, 12:04	2
H08-H09	1.0438	114	01Jul2015, 14:30	64
FH01	0.1344	64	01Jul2015, 12:26	9
<b>POND H</b>	<b>0.1344</b>	<b>13</b>	<b>01Jul2015, 13:50</b>	<b>7</b>
FH02	0.0138	14	01Jul2015, 12:08	1
H12	0.1482	14	01Jul2015, 12:08	8

INTERIM 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
OS01	1.5594	316	01Jul2015, 12:36	58.6
DB16	0.0578	54	01Jul2015, 12:10	5.0
B10	1.6172	335	01Jul2015, 12:34	63.6
B10-B11	1.6172	335	01Jul2015, 12:34	63.5
DB17	0.0048	11	01Jul2015, 12:02	0.9
B11	1.6220	336	01Jul2015, 12:34	64.4
B11-POND C	1.6220	336	01Jul2015, 12:38	64.0
DB21	0.0519	25	01Jul2015, 12:08	2.3
DB18	0.0346	39	01Jul2015, 12:08	3.2
DB19	0.0281	20	01Jul2015, 12:10	1.9
DB20	0.0147	15	01Jul2015, 12:10	1.3
POND C	1.7513	310	01Jul2015, 12:52	68.6
POND C-B16	1.7513	310	01Jul2015, 12:54	68.4
DB25	0.0211	27	01Jul2015, 12:04	2.0
B16	1.7724	313	01Jul2015, 12:54	70.3
B16-B17	1.7724	312	01Jul2015, 12:58	69.9
DB26	0.0682	88	01Jul2015, 12:10	8.0
B17	1.8406	326	01Jul2015, 12:58	77.9
B17-B18	1.8406	326	01Jul2015, 13:00	77.5
OS03	0.1984	55	01Jul2015, 12:20	7.7
DB01	0.0719	46	01Jul2015, 12:08	4.1
B01	0.2703	89	01Jul2015, 12:14	11.7
B01-B02	0.2703	89	01Jul2015, 12:16	11.7
OS02	0.2219	65	01Jul2015, 12:22	9.3
DB02	0.0516	36	01Jul2015, 12:06	2.8
B02	0.5438	169	01Jul2015, 12:16	23.8
B02-POND A	0.5438	169	01Jul2015, 12:18	23.8
OS04	0.1359	32	01Jul2015, 12:18	4.5
DB03	0.0703	32	01Jul2015, 12:10	3.2
B03	0.2062	61	01Jul2015, 12:14	7.7
B03-B04	0.2062	60	01Jul2015, 12:20	7.6
DB04	0.0422	21	01Jul2015, 12:10	2.0
DB05	0.0384	18	01Jul2015, 12:14	2.0
B04	0.2868	94	01Jul2015, 12:18	11.7
B04-B05	0.2868	94	01Jul2015, 12:18	11.7
DB06	0.0219	28	01Jul2015, 12:08	2.4
B05	0.3087	115	01Jul2015, 12:16	14.0
B05-POND A	0.3087	114	01Jul2015, 12:18	14.0
DB07	0.0254	18	01Jul2015, 12:06	1.5
DB08	0.0297	15	01Jul2015, 12:08	1.3
POND A	0.9076	238	01Jul2015, 12:30	37.9
POND A-B06	0.9076	237	01Jul2015, 12:30	37.9
DB09	0.0189	19	01Jul2015, 12:04	1.4
B06	0.9265	241	01Jul2015, 12:30	39.3
B06-B07	0.9265	241	01Jul2015, 12:36	38.9
DB11	0.0969	60	01Jul2015, 12:12	6.2
DB10	0.0364	32	01Jul2015, 12:08	2.7
B07	1.0598	277	01Jul2015, 12:34	47.8
B07-B09	1.0598	276	01Jul2015, 12:38	47.6
DB12	0.0453	48	01Jul2015, 12:06	3.9

INTERIM 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
B09	1.1051	287	01Jul2015, 12:36	51.4
B09-POND B	1.1051	286.6	01Jul2015, 12:38	51.4
DB15	0.1234	50	01Jul2015, 12:18	6.1
DB13	0.0703	49	01Jul2015, 12:12	4.9
DB14	0.0556	54	01Jul2015, 12:08	4.7
POND B	1.3544	324	01Jul2015, 12:44	66.6
POND B-B12	1.3544	323	01Jul2015, 12:46	66.5
DB22	0.0516	55	01Jul2015, 12:08	4.8
DB23	0.0172	31	01Jul2015, 12:04	2.5
B12	1.4232	339	01Jul2015, 12:44	73.8
B12-B14	1.4232	338	01Jul2015, 12:46	73.6
DB24	0.0531	56	01Jul2015, 12:08	4.6
B14	1.4763	348	01Jul2015, 12:46	78.2
B14-B15	1.4763	348	01Jul2015, 12:48	78.0
DB28	0.0741	34	01Jul2015, 12:12	3.6
B15	1.5504	358	01Jul2015, 12:46	81.7
B15-B18	1.5504	358	01Jul2015, 12:54	80.7
DB29	0.1697	71	01Jul2015, 12:20	9.0
DB27	0.0508	40	01Jul2015, 12:16	4.3
<b>B26</b>	<b>3.6115</b>	<b>717</b>	<b>01Jul2015, 12:56</b>	<b>171.6</b>
B26-27	3.6115	716	01Jul2015, 12:58	170.9
FB-02	0.0500	22	01Jul2015, 12:14	2.4
FB-01	0.0373	15	01Jul2015, 12:16	1.8
FB01-27a	0.0373	15	01Jul2015, 12:18	1.8
B19	0.0873	36	01Jul2015, 12:16	4.2
B19-27	0.0873	36	01Jul2015, 12:18	4.2
FB-03	0.0078	14	01Jul2015, 12:04	1.0
27	3.7066	729	01Jul2015, 12:58	176.1
27-32	3.7066	728	01Jul2015, 12:58	175.7
WH-24	0.1325	129	01Jul2015, 12:10	11.7
WH-26	0.0839	20	01Jul2015, 12:22	3.0
WH-27	0.0217	10	01Jul2015, 12:04	0.8
30	0.2381	150	01Jul2015, 12:10	15.5
30-31	0.2381	149	01Jul2015, 12:12	15.5
WH-28	0.0398	36	01Jul2015, 12:12	3.4
31	0.2779	185	01Jul2015, 12:12	18.9
31-32	0.2779	185	01Jul2015, 12:14	18.8
WH-29	0.0495	45	01Jul2015, 12:10	4.2
WH-31	0.0406	46	01Jul2015, 12:08	3.8
WH-30	0.0159	13	01Jul2015, 12:02	0.9
<b>32</b>	<b>4.0905</b>	<b>787</b>	<b>01Jul2015, 12:58</b>	<b>203.3</b>
WH32	0.0458	24	01Jul2015, 12:02	1.6
BEN POND	4.1363	581	01Jul2015, 13:28	192.1
WH-33	0.0064	7	01Jul2015, 12:08	0.6
33	4.1427	582	01Jul2015, 13:28	192.7
33-37	4.1427	581	01Jul2015, 13:32	191.2
WH35	0.1550	84	01Jul2015, 12:10	8.0
WH34	0.0450	38	01Jul2015, 12:08	3.3
B34-36	0.0450	38	01Jul2015, 12:10	3.3
36	0.2000	122	01Jul2015, 12:10	11.4

INTERIM 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
36-37	0.2000	121	01Jul2015, 12:14	11.3
WH36	0.0750	27	01Jul2015, 12:12	2.9
<b>37</b>	<b>4.4177</b>	<b>601</b>	<b>01Jul2015, 13:32</b>	<b>205.4</b>
FG08A	0.075	72.6	01Jul2015, 12:08	6
FG08A-G05	0.0750	72	01Jul2015, 12:10	6.0
FG08B	0.0630	54	01Jul2015, 12:10	5.0
FG08B-G05	0.0630	54	01Jul2015, 12:14	5.0
FG11	0.0625	47	01Jul2015, 12:18	5.3
FG09	0.0484	28	01Jul2015, 12:16	3.0
FG09-G05	0.0484	27	01Jul2015, 12:18	3.0
HG10	0.0467	13	01Jul2015, 12:20	1.8
G05	0.2956	206	01Jul2015, 12:14	21.2
FG13	0.0661	21	01Jul2015, 12:26	3.2
FG12	0.0328	33	01Jul2015, 12:10	3.0
POND D	0.3945	35	01Jul2015, 13:38	20.1
POND D-G17	0.3945	35	01Jul2015, 13:40	20.1
HG15	0.0297	6	01Jul2015, 12:36	1.1
FG15a	0.0156	18	01Jul2015, 12:06	1.4
G17	0.4398	38	01Jul2015, 13:30	22.5
G17-G18	0.4398	38	01Jul2015, 13:32	22.5
FG16	0.0773	79	01Jul2015, 12:08	6.5
G18	0.5171	100	01Jul2015, 12:08	28.9
G18-POND E	0.5171	100	01Jul2015, 12:08	28.9
HG30	0.1844	21	01Jul2015, 13:12	6.0
FG30-PONDHS	0.1844	21	01Jul2015, 13:22	5.9
FG31	0.0922	74	01Jul2015, 12:18	8.5
POND HS	0.2766	40	01Jul2015, 12:56	14.3
FG17a	0.0694	69	01Jul2015, 12:08	5.9
FG17a-POND E	0.0694	68	01Jul2015, 12:10	5.9
FG18	0.0644	20	01Jul2015, 12:26	3.0
FG18-POND E	0.0644	20	01Jul2015, 12:28	3.0
FG19	0.0527	47	01Jul2015, 12:10	4.2
FG17c	0.0313	16	01Jul2015, 12:08	1.4
FG17b	0.0214	26	01Jul2015, 12:06	2.0
<b>POND E</b>	<b>1.0329</b>	<b>57</b>	<b>01Jul2015, 15:28</b>	<b>40.3</b>
FG20	0.0109	22	01Jul2015, 12:04	1.7
H08-H09	1.0438	57	01Jul2015, 15:26	42.0
FH01	0.1344	42	01Jul2015, 12:28	6.5
<b>POND H</b>	<b>0.1344</b>	<b>6</b>	<b>01Jul2015, 14:32</b>	<b>4.1</b>
FH02	0.0138	10	01Jul2015, 12:08	0.8
H12	0.1482	10	01Jul2015, 12:08	4.9

INTERIM 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
OS01	1.5594	136	01 Jul 2015, 12:38	30.9
DB16	0.0578	35	01 Jul 2015, 12:10	3.3
B10	1.6172	147	01 Jul 2015, 12:36	34.2
B10-B11	1.6172	147	01 Jul 2015, 12:38	34.1
DB17	0.0048	9	01 Jul 2015, 12:02	0.7
B11	1.6220	148	01 Jul 2015, 12:38	34.8
B11-POND C	1.6220	148	01 Jul 2015, 12:42	34.5
DB21	0.0519	12	01 Jul 2015, 12:10	1.3
DB18	0.0346	26	01 Jul 2015, 12:08	2.1
DB19	0.0281	11	01 Jul 2015, 12:12	1.1
DB20	0.0147	9	01 Jul 2015, 12:10	0.8
POND C	1.7513	129	01 Jul 2015, 13:02	36.3
POND C-B16	1.7513	128	01 Jul 2015, 13:06	36.1
DB25	0.0211	18	01 Jul 2015, 12:04	1.3
B16	1.7724	130	01 Jul 2015, 13:06	37.4
B16-B17	1.7724	130	01 Jul 2015, 13:10	37.1
DB26	0.0682	62	01 Jul 2015, 12:10	5.6
B17	1.8406	138	01 Jul 2015, 13:08	42.7
B17-B18	1.8406	138	01 Jul 2015, 13:12	42.4
OS03	0.1984	24	01 Jul 2015, 12:24	4.1
DB01	0.0719	25	01 Jul 2015, 12:10	2.4
B01	0.2703	42	01 Jul 2015, 12:14	6.5
B01-B02	0.2703	42	01 Jul 2015, 12:16	6.5
OS02	0.2219	30	01 Jul 2015, 12:26	5.1
DB02	0.0516	20	01 Jul 2015, 12:06	1.7
B02	0.5438	79	01 Jul 2015, 12:18	13.2
B02-POND A	0.5438	79	01 Jul 2015, 12:20	13.1
OS04	0.1359	12	01 Jul 2015, 12:22	2.3
DB03	0.0703	16	01 Jul 2015, 12:12	1.8
B03	0.2062	26	01 Jul 2015, 12:16	4.1
B03-B04	0.2062	26	01 Jul 2015, 12:22	4.0
DB04	0.0422	10	01 Jul 2015, 12:12	1.2
DB05	0.0384	9	01 Jul 2015, 12:16	1.1
B04	0.2868	42	01 Jul 2015, 12:20	6.3
B04-B05	0.2868	42	01 Jul 2015, 12:20	6.3
DB06	0.0219	19	01 Jul 2015, 12:08	1.6
B05	0.3087	55	01 Jul 2015, 12:18	8.0
B05-POND A	0.3087	55	01 Jul 2015, 12:20	8.0
DB07	0.0254	10	01 Jul 2015, 12:08	0.9
DB08	0.0297	7	01 Jul 2015, 12:08	0.7
POND A	0.9076	88	01 Jul 2015, 12:42	20.2
POND A-B06	0.9076	88	01 Jul 2015, 12:42	20.1
DB09	0.0189	12	01 Jul 2015, 12:04	0.9
B06	0.9265	90	01 Jul 2015, 12:42	21.0
B06-B07	0.9265	90	01 Jul 2015, 12:48	20.8
DB11	0.0969	35	01 Jul 2015, 12:14	3.8
DB10	0.0364	19	01 Jul 2015, 12:08	1.7
B07	1.0598	105	01 Jul 2015, 12:48	26.3
B07-B09	1.0598	105	01 Jul 2015, 12:52	26.1
DB12	0.0453	31	01 Jul 2015, 12:08	2.5

INTERIM 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
B09	1.1051	110	01 Jul 2015, 12:52	28.7
B09-POND B	1.1051	109.7	01 Jul 2015, 12:52	28.7
DB15	0.1234	25	01 Jul 2015, 12:20	3.4
DB13	0.0703	29	01 Jul 2015, 12:14	3.1
DB14	0.0556	35	01 Jul 2015, 12:08	3.1
POND B	1.3544	128	01 Jul 2015, 12:26	37.9
POND B-B12	1.3544	128	01 Jul 2015, 12:28	37.8
DB22	0.0516	36	01 Jul 2015, 12:08	3.2
DB23	0.0172	23	01 Jul 2015, 12:06	1.8
B12	1.4232	150	01 Jul 2015, 12:26	42.9
B12-B14	1.4232	150	01 Jul 2015, 12:28	42.7
DB24	0.0531	36	01 Jul 2015, 12:08	3.0
B14	1.4763	164	01 Jul 2015, 12:26	45.7
B14-B15	1.4763	164	01 Jul 2015, 12:28	45.6
DB28	0.0741	17	01 Jul 2015, 12:14	2.1
B15	1.5504	175	01 Jul 2015, 12:26	47.7
B15-B18	1.5504	175	01 Jul 2015, 12:34	47.0
DB29	0.1697	37	01 Jul 2015, 12:20	5.2
DB27	0.0508	25	01 Jul 2015, 12:16	2.8
<b>B26</b>	<b>3.6115</b>	<b>298</b>	<b>01 Jul 2015, 13:12</b>	<b>97.5</b>
B26-27	3.6115	298	01 Jul 2015, 13:16	97.0
FB-02	0.0500	11	01 Jul 2015, 12:16	1.4
FB-01	0.0373	7	01 Jul 2015, 12:18	1.0
FB01-27a	0.0373	7	01 Jul 2015, 12:20	1.0
B19	0.0873	18	01 Jul 2015, 12:18	2.4
B19-27	0.0873	18	01 Jul 2015, 12:18	2.4
FB-03	0.0078	10	01 Jul 2015, 12:04	0.7
27	3.7066	304	01 Jul 2015, 13:14	100.0
27-32	3.7066	304	01 Jul 2015, 13:16	99.7
WH-24	0.1325	84	01 Jul 2015, 12:10	7.7
WH-26	0.0839	8	01 Jul 2015, 12:26	1.5
WH-27	0.0217	4	01 Jul 2015, 12:06	0.4
30	0.2381	91	01 Jul 2015, 12:10	9.7
30-31	0.2381	91	01 Jul 2015, 12:12	9.7
WH-28	0.0398	23	01 Jul 2015, 12:12	2.2
31	0.2779	114	01 Jul 2015, 12:12	11.9
31-32	0.2779	113	01 Jul 2015, 12:14	11.9
WH-29	0.0495	29	01 Jul 2015, 12:10	2.7
WH-31	0.0406	30	01 Jul 2015, 12:08	2.5
WH-30	0.0159	7	01 Jul 2015, 12:02	0.5
<b>32</b>	<b>4.0905</b>	<b>415</b>	<b>01 Jul 2015, 12:24</b>	<b>117.3</b>
WH32	0.0458	10	01 Jul 2015, 12:04	0.9
BEN POND	4.1363	243	01 Jul 2015, 13:56	110.1
WH-33	0.0064	5	01 Jul 2015, 12:08	0.4
33	4.1427	243	01 Jul 2015, 13:56	110.4
33-37	4.1427	243	01 Jul 2015, 14:02	109.4
WH35	0.1550	44	01 Jul 2015, 12:10	4.6
WH34	0.0450	23	01 Jul 2015, 12:10	2.1
B34-36	0.0450	23	01 Jul 2015, 12:12	2.1
36	0.2000	67	01 Jul 2015, 12:12	6.7

INTERIM 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
36-37	0.2000	66	01 Jul 2015, 12:16	6.7
WH36	0.0750	11	01 Jul 2015, 12:14	1.5
<b>37</b>	<b>4.4177</b>	<b>252</b>	<b>01 Jul 2015, 14:00</b>	<b>117.6</b>
FG08A	0.075	45.8	01 Jul 2015, 12:08	3.9
FG08A-G05	0.0750	45	01 Jul 2015, 12:12	3.9
FG08B	0.0630	34	01 Jul 2015, 12:12	3.2
FG08B-G05	0.0630	34	01 Jul 2015, 12:14	3.2
FG11	0.0625	30	01 Jul 2015, 12:18	3.5
FG09	0.0484	16	01 Jul 2015, 12:16	1.8
FG09-G05	0.0484	16	01 Jul 2015, 12:18	1.8
HG10	0.0467	6	01 Jul 2015, 12:22	1.0
G05	0.2956	126	01 Jul 2015, 12:14	13.4
FG13	0.0661	11	01 Jul 2015, 12:28	1.8
FG12	0.0328	22	01 Jul 2015, 12:10	2.0
POND D	0.3945	15	01 Jul 2015, 14:24	11.8
POND D-G17	0.3945	15	01 Jul 2015, 14:26	11.8
HG15	0.0297	2	01 Jul 2015, 12:38	0.5
FG15a	0.0156	12	01 Jul 2015, 12:06	0.9
G17	0.4398	17	01 Jul 2015, 13:36	13.2
G17-G18	0.4398	17	01 Jul 2015, 13:38	13.2
FG16	0.0773	51	01 Jul 2015, 12:08	4.2
G18	0.5171	64	01 Jul 2015, 12:08	17.4
G18-POND E	0.5171	63	01 Jul 2015, 12:10	17.4
HG30	0.1844	9	01 Jul 2015, 13:24	3.0
FG30-PONDHS	0.1844	9	01 Jul 2015, 13:34	2.9
FG31	0.0922	49	01 Jul 2015, 12:18	5.7
POND HS	0.2766	28	01 Jul 2015, 12:40	8.6
FG17a	0.0694	44	01 Jul 2015, 12:08	3.9
FG17a-POND E	0.0694	44	01 Jul 2015, 12:10	3.9
FG18	0.0644	10	01 Jul 2015, 12:30	1.7
FG18-POND E	0.0644	10	01 Jul 2015, 12:30	1.7
FG19	0.0527	30	01 Jul 2015, 12:10	2.7
FG17c	0.0313	8	01 Jul 2015, 12:08	0.8
FG17b	0.0214	17	01 Jul 2015, 12:06	1.3
<b>POND E</b>	<b>1.0329</b>	<b>25</b>	<b>01 Jul 2015, 18:10</b>	<b>22.0</b>
FG20	0.0109	16	01 Jul 2015, 12:04	1.2
H08-H09	1.0438	25	01 Jul 2015, 17:54	23.3
FH01	0.1344	21	01 Jul 2015, 12:30	3.7
<b>POND H</b>	<b>0.1344</b>	<b>2</b>	<b>01 Jul 2015, 18:20</b>	<b>1.9</b>
FH02	0.0138	5	01 Jul 2015, 12:08	0.5
H12	0.1482	6	01 Jul 2015, 12:08	2.4



INTERIM 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
OS01	1.5594	55	01 Jul 2015, 12:46	16.6
DB16	0.0578	23	01 Jul 2015, 12:12	2.3
B10	1.6172	62	01 Jul 2015, 12:42	18.9
B10-B11	1.6172	62	01 Jul 2015, 12:42	18.9
DB17	0.0048	7	01 Jul 2015, 12:02	0.6
B11	1.6220	63	01 Jul 2015, 12:42	19.4
B11-POND C	1.6220	63	01 Jul 2015, 12:48	19.2
DB21	0.0519	5	01 Jul 2015, 12:12	0.7
DB18	0.0346	18	01 Jul 2015, 12:08	1.5
DB19	0.0281	7	01 Jul 2015, 12:12	0.7
DB20	0.0147	6	01 Jul 2015, 12:10	0.6
POND C	1.7513	50	01 Jul 2015, 13:28	19.4
POND C-B16	1.7513	50	01 Jul 2015, 13:32	19.2
DB25	0.0211	12	01 Jul 2015, 12:04	0.9
B16	1.7724	51	01 Jul 2015, 13:32	20.1
B16-B17	1.7724	51	01 Jul 2015, 13:36	19.9
DB26	0.0682	46	01 Jul 2015, 12:10	4.1
B17	1.8406	56	01 Jul 2015, 12:12	24.0
B17-B18	1.8406	56	01 Jul 2015, 12:16	23.8
OS03	0.1984	9	01 Jul 2015, 12:28	2.2
DB01	0.0719	14	01 Jul 2015, 12:10	1.5
B01	0.2703	19	01 Jul 2015, 12:14	3.7
B01-B02	0.2703	19	01 Jul 2015, 12:18	3.7
OS02	0.2219	13	01 Jul 2015, 12:28	2.8
DB02	0.0516	10	01 Jul 2015, 12:06	1.0
B02	0.5438	36	01 Jul 2015, 12:18	7.6
B02-POND A	0.5438	36	01 Jul 2015, 12:22	7.5
OS04	0.1359	4	01 Jul 2015, 12:28	1.2
DB03	0.0703	7	01 Jul 2015, 12:14	1.0
B03	0.2062	10	01 Jul 2015, 12:16	2.2
B03-B04	0.2062	10	01 Jul 2015, 12:26	2.2
DB04	0.0422	5	01 Jul 2015, 12:14	0.7
DB05	0.0384	5	01 Jul 2015, 12:18	0.7
B04	0.2868	18	01 Jul 2015, 12:22	3.5
B04-B05	0.2868	18	01 Jul 2015, 12:24	3.5
DB06	0.0219	14	01 Jul 2015, 12:08	1.2
B05	0.3087	26	01 Jul 2015, 12:22	4.7
B05-POND A	0.3087	26	01 Jul 2015, 12:22	4.7
DB07	0.0254	6	01 Jul 2015, 12:08	0.5
DB08	0.0297	3	01 Jul 2015, 12:10	0.4
POND A	0.9076	27	01 Jul 2015, 13:16	10.8
POND A-B06	0.9076	27	01 Jul 2015, 13:18	10.8
DB09	0.0189	8	01 Jul 2015, 12:06	0.6
B06	0.9265	28	01 Jul 2015, 13:18	11.4
B06-B07	0.9265	28	01 Jul 2015, 13:26	11.2
DB11	0.0969	20	01 Jul 2015, 12:14	2.4
DB10	0.0364	12	01 Jul 2015, 12:08	1.1
B07	1.0598	37	01 Jul 2015, 12:16	14.8
B07-B09	1.0598	37	01 Jul 2015, 12:22	14.7
DB12	0.0453	21	01 Jul 2015, 12:08	1.7

INTERIM 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
B09	1.1051	47	01 Jul 2015, 12:18	16.4
B09-POND B	1.1051	46.9	01 Jul 2015, 12:20	16.4
DB15	0.1234	12	01 Jul 2015, 12:22	2.0
DB13	0.0703	18	01 Jul 2015, 12:14	2.0
DB14	0.0556	23	01 Jul 2015, 12:10	2.1
POND B	1.3544	71	01 Jul 2015, 12:30	22.3
POND B-B12	1.3544	71	01 Jul 2015, 12:32	22.3
DB22	0.0516	25	01 Jul 2015, 12:10	2.2
DB23	0.0172	18	01 Jul 2015, 12:06	1.4
B12	1.4232	85	01 Jul 2015, 12:28	25.9
B12-B14	1.4232	85	01 Jul 2015, 12:30	25.8
DB24	0.0531	24	01 Jul 2015, 12:08	2.1
B14	1.4763	94	01 Jul 2015, 12:26	27.9
B14-B15	1.4763	94	01 Jul 2015, 12:28	27.8
DB28	0.0741	8	01 Jul 2015, 12:16	1.2
B15	1.5504	100	01 Jul 2015, 12:24	29.0
B15-B18	1.5504	100	01 Jul 2015, 12:34	28.5
DB29	0.1697	19	01 Jul 2015, 12:24	3.2
DB27	0.0508	17	01 Jul 2015, 12:16	1.9
<b>B26</b>	<b>3.6115</b>	<b>175</b>	<b>01 Jul 2015, 12:22</b>	<b>57.4</b>
B26-27	3.6115	175	01 Jul 2015, 12:28	57.0
FB-02	0.0500	5	01 Jul 2015, 12:18	0.8
FB-01	0.0373	4	01 Jul 2015, 12:20	0.6
FB01-27a	0.0373	4	01 Jul 2015, 12:22	0.6
B19	0.0873	9	01 Jul 2015, 12:20	1.4
B19-27	0.0873	9	01 Jul 2015, 12:22	1.4
FB-03	0.0078	8	01 Jul 2015, 12:04	0.5
27	3.7066	184	01 Jul 2015, 12:26	59.0
27-32	3.7066	184	01 Jul 2015, 12:30	58.7
WH-24	0.1325	57	01 Jul 2015, 12:10	5.4
WH-26	0.0839	3	01 Jul 2015, 12:32	0.8
WH-27	0.0217	1	01 Jul 2015, 12:08	0.2
30	0.2381	59	01 Jul 2015, 12:10	6.4
30-31	0.2381	59	01 Jul 2015, 12:12	6.4
WH-28	0.0398	15	01 Jul 2015, 12:12	1.5
31	0.2779	74	01 Jul 2015, 12:12	7.9
31-32	0.2779	74	01 Jul 2015, 12:16	7.9
WH-29	0.0495	19	01 Jul 2015, 12:12	1.9
WH-31	0.0406	21	01 Jul 2015, 12:08	1.8
WH-30	0.0159	4	01 Jul 2015, 12:02	0.3
<b>32</b>	<b>4.0905</b>	<b>252</b>	<b>01 Jul 2015, 12:28</b>	<b>70.5</b>
WH32	0.0458	4	01 Jul 2015, 12:04	0.5
BEN POND	4.1363	97	01 Jul 2015, 14:54	64.8
WH-33	0.0064	3	01 Jul 2015, 12:08	0.3
33	4.1427	97	01 Jul 2015, 14:54	65.0
33-37	4.1427	97	01 Jul 2015, 15:02	64.2
WH35	0.1550	22	01 Jul 2015, 12:12	2.8
WH34	0.0450	15	01 Jul 2015, 12:10	1.4
B34-36	0.0450	15	01 Jul 2015, 12:12	1.4
36	0.2000	37	01 Jul 2015, 12:12	4.2

INTERIM 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
36-37	0.2000	37	01 Jul 2015, 12:18	4.1
WH36	0.0750	4	01 Jul 2015, 12:16	0.8
<b>37</b>	<b>4.4177</b>	<b>101</b>	<b>01 Jul 2015, 14:50</b>	<b>69.2</b>
FG08A	0.075	29.8	01 Jul 2015, 12:08	2.6
FG08A-G05	0.0750	30	01 Jul 2015, 12:12	2.6
FG08B	0.0630	22	01 Jul 2015, 12:12	2.2
FG08B-G05	0.0630	22	01 Jul 2015, 12:16	2.2
FG11	0.0625	20	01 Jul 2015, 12:18	2.4
FG09	0.0484	9	01 Jul 2015, 12:18	1.2
FG09-G05	0.0484	9	01 Jul 2015, 12:20	1.2
HG10	0.0467	2	01 Jul 2015, 12:26	0.5
G05	0.2956	80	01 Jul 2015, 12:14	8.9
FG13	0.0661	5	01 Jul 2015, 12:32	1.1
FG12	0.0328	15	01 Jul 2015, 12:10	1.4
POND D	0.3945	9	01 Jul 2015, 14:56	6.8
POND D-G17	0.3945	9	01 Jul 2015, 15:00	6.8
HG15	0.0297	1	01 Jul 2015, 12:46	0.3
FG15a	0.0156	8	01 Jul 2015, 12:06	0.6
G17	0.4398	9	01 Jul 2015, 14:36	7.7
G17-G18	0.4398	9	01 Jul 2015, 14:38	7.7
FG16	0.0773	34	01 Jul 2015, 12:08	2.9
G18	0.5171	42	01 Jul 2015, 12:08	10.6
G18-POND E	0.5171	42	01 Jul 2015, 12:10	10.6
HG30	0.1844	3	01 Jul 2015, 13:36	1.5
FG30-PONDHS	0.1844	3	01 Jul 2015, 13:50	1.5
FG31	0.0922	33	01 Jul 2015, 12:18	4.0
POND HS	0.2766	19	01 Jul 2015, 12:40	5.4
FG17a	0.0694	29	01 Jul 2015, 12:10	2.7
FG17a-POND E	0.0694	29	01 Jul 2015, 12:10	2.7
FG18	0.0644	5	01 Jul 2015, 12:32	1.0
FG18-POND E	0.0644	5	01 Jul 2015, 12:34	1.0
FG19	0.0527	19	01 Jul 2015, 12:10	1.9
FG17c	0.0313	3	01 Jul 2015, 12:10	0.4
FG17b	0.0214	12	01 Jul 2015, 12:06	0.9
<b>POND E</b>	<b>1.0329</b>	<b>15</b>	<b>01 Jul 2015, 19:02</b>	<b>14.0</b>
FG20	0.0109	13	01 Jul 2015, 12:04	1.0
H08-H09	1.0438	18	01 Jul 2015, 12:06	15.0
FH01	0.1344	10	01 Jul 2015, 12:32	2.2
<b>POND H</b>	<b>0.1344</b>	<b>1</b>	<b>01 Jul 2015, 20:10</b>	<b>1.3</b>
FH02	0.0138	3	01 Jul 2015, 12:10	0.3
H12	0.1482	3	01 Jul 2015, 12:10	1.6

INTERIM 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
OS01	1.5594	11.0	01Jul2015, 13:24	5.9
DB16	0.0578	12.7	01Jul2015, 12:12	1.3
B10	1.6172	13.2	01Jul2015, 12:12	7.3
B10-B11	1.6172	13.2	01Jul2015, 12:14	7.2
DB17	0.0048	5.7	01Jul2015, 12:02	0.4
B11	1.6220	15.3	01Jul2015, 12:12	7.7
B11-POND C	1.6220	15.2	01Jul2015, 12:20	7.5
DB21	0.0519	1.1	01Jul2015, 12:18	0.3
DB18	0.0346	10.0	01Jul2015, 12:08	0.9
DB19	0.0281	2.8	01Jul2015, 12:14	0.4
DB20	0.0147	3.4	01Jul2015, 12:10	0.3
POND C	1.7513	10.9	01Jul2015, 15:00	6.3
POND C-B16	1.7513	10.9	01Jul2015, 15:06	6.2
DB25	0.0211	7.1	01Jul2015, 12:06	0.6
B16	1.7724	11.3	01Jul2015, 15:06	6.7
B16-B17	1.7724	11.3	01Jul2015, 15:16	6.6
DB26	0.0682	29.4	01Jul2015, 12:10	2.7
B17	1.8406	34.4	01Jul2015, 12:14	9.3
B17-B18	1.8406	34.0	01Jul2015, 12:20	9.1
OS03	0.1984	1.6	01Jul2015, 13:02	0.8
DB01	0.0719	4.7	01Jul2015, 12:12	0.7
B01	0.2703	5.0	01Jul2015, 12:14	1.5
B01-B02	0.2703	5.0	01Jul2015, 12:18	1.5
OS02	0.2219	2.6	01Jul2015, 12:46	1.1
DB02	0.0516	3.4	01Jul2015, 12:08	0.5
B02	0.5438	8.6	01Jul2015, 12:18	3.1
B02-POND A	0.5438	8.6	01Jul2015, 12:22	3.1
OS04	0.1359	0.6	01Jul2015, 13:30	0.4
DB03	0.0703	1.5	01Jul2015, 12:20	0.4
B03	0.2062	1.5	01Jul2015, 12:20	0.8
B03-B04	0.2062	1.5	01Jul2015, 12:36	0.8
DB04	0.0422	1.2	01Jul2015, 12:18	0.3
DB05	0.0384	1.4	01Jul2015, 12:22	0.3
B04	0.2868	3.6	01Jul2015, 12:32	1.4
B04-B05	0.2868	3.6	01Jul2015, 12:34	1.4
DB06	0.0219	8.6	01Jul2015, 12:10	0.8
B05	0.3087	10.3	01Jul2015, 12:12	2.2
B05-POND A	0.3087	10.2	01Jul2015, 12:14	2.1
DB07	0.0254	1.9	01Jul2015, 12:10	0.3
DB08	0.0297	0.5	01Jul2015, 12:16	0.2
POND A	0.9076	4.2	01Jul2015, 18:16	3.4
POND A-B06	0.9076	4.2	01Jul2015, 18:18	3.4
DB09	0.0189	3.7	01Jul2015, 12:06	0.3
B06	0.9265	4.4	01Jul2015, 18:18	3.7
B06-B07	0.9265	4.4	01Jul2015, 18:34	3.6
DB11	0.0969	8.1	01Jul2015, 12:16	1.2
DB10	0.0364	5.8	01Jul2015, 12:10	0.6
B07	1.0598	15.6	01Jul2015, 12:22	5.5
B07-B09	1.0598	15.5	01Jul2015, 12:30	5.4
DB12	0.0453	11.2	01Jul2015, 12:08	1.0


INTERIM 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
B09	1.1051	20.1	01Jul2015, 12:20	6.5
B09-POND B	1.1051	20.1	01Jul2015, 12:22	6.4
DB15	0.1234	3.3	01Jul2015, 12:28	0.9
DB13	0.0703	7.9	01Jul2015, 12:16	1.1
DB14	0.0556	12.4	01Jul2015, 12:10	1.2
POND B	1.3544	31.1	01Jul2015, 12:34	9.5
POND B-B12	1.3544	31.0	01Jul2015, 12:36	9.5
DB22	0.0516	14.1	01Jul2015, 12:10	1.3
DB23	0.0172	13.1	01Jul2015, 12:06	1.0
B12	1.4232	38.9	01Jul2015, 12:28	11.8
B12-B14	1.4232	38.9	01Jul2015, 12:32	11.8
DB24	0.0531	13.2	01Jul2015, 12:08	1.2
B14	1.4763	47.0	01Jul2015, 12:16	13.0
B14-B15	1.4763	46.9	01Jul2015, 12:18	12.9
DB28	0.0741	2.1	01Jul2015, 12:20	0.5
B15	1.5504	49.0	01Jul2015, 12:18	13.5
B15-B18	1.5504	48.8	01Jul2015, 12:30	13.1
DB29	0.1697	6.1	01Jul2015, 12:28	1.5
DB27	0.0508	8.9	01Jul2015, 12:18	1.1
<b>B26</b>	<b>3.6115</b>	<b>88.7</b>	<b>01Jul2015, 12:26</b>	<b>24.9</b>
B26-27	3.6115	87.8	01Jul2015, 12:32	24.6
FB-02	0.0500	1.4	01Jul2015, 12:24	0.4
FB-01	0.0373	0.9	01Jul2015, 12:26	0.3
FB01-27a	0.0373	0.9	01Jul2015, 12:28	0.3
B19	0.0873	2.3	01Jul2015, 12:26	0.6
B19-27	0.0873	2.2	01Jul2015, 12:28	0.6
FB-03	0.0078	5.1	01Jul2015, 12:04	0.4
27	3.7066	90.9	01Jul2015, 12:32	25.5
27-32	3.7066	90.6	01Jul2015, 12:34	25.4
WH-24	0.1325	31.1	01Jul2015, 12:12	3.2
WH-26	0.0839	0.5	01Jul2015, 13:18	0.3
WH-27	0.0217	0.1	01Jul2015, 12:50	0.1
30	0.2381	31.1	01Jul2015, 12:12	3.5
30-31	0.2381	31.1	01Jul2015, 12:14	3.5
WH-28	0.0398	8.1	01Jul2015, 12:14	0.9
31	0.2779	39.2	01Jul2015, 12:14	4.4
31-32	0.2779	38.9	01Jul2015, 12:16	4.4
WH-29	0.0495	10.2	01Jul2015, 12:12	1.1
WH-31	0.0406	11.8	01Jul2015, 12:08	1.1
WH-30	0.0159	1.3	01Jul2015, 12:04	0.1
<b>32</b>	<b>4.0905</b>	<b>120.8</b>	<b>01Jul2015, 12:34</b>	<b>32.1</b>
WH32	0.0458	0.3	01Jul2015, 12:48	0.2
BEN POND	4.1363	43.7	01Jul2015, 13:48	27.5
WH-33	0.0064	1.9	01Jul2015, 12:08	0.2
33	4.1427	43.9	01Jul2015, 13:48	27.7
33-37	4.1427	43.8	01Jul2015, 13:58	27.2
WH35	0.1550	6.4	01Jul2015, 12:16	1.3
WH34	0.0450	7.0	01Jul2015, 12:10	0.8
B34-36	0.0450	6.9	01Jul2015, 12:14	0.8
36	0.2000	13.3	01Jul2015, 12:14	2.0

INTERIM 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
36-37	0.2000	13.2	01Jul2015, 12:22	2.0
WH36	0.0750	0.6	01Jul2015, 12:52	0.3
<b>37</b>	<b>4.4177</b>	<b>47.2</b>	<b>01Jul2015, 13:54</b>	<b>29.5</b>
FG08A	0.075	15.3	01Jul2015, 12:10	1.5
FG08A-G05	0.0750	15.2	01Jul2015, 12:14	1.5
FG08B	0.0630	11.1	01Jul2015, 12:12	1.3
FG08B-G05	0.0630	11.1	01Jul2015, 12:16	1.2
FG11	0.0625	10.6	01Jul2015, 12:20	1.4
FG09	0.0484	3.6	01Jul2015, 12:20	0.6
FG09-G05	0.0484	3.6	01Jul2015, 12:24	0.6
HG10	0.0467	0.4	01Jul2015, 13:00	0.2
G05	0.2956	39.4	01Jul2015, 12:16	4.9
FG13	0.0661	1.5	01Jul2015, 12:40	0.5
FG12	0.0328	8.5	01Jul2015, 12:12	0.9
POND D	0.3945	2.7	01Jul2015, 20:16	2.7
POND D-G17	0.3945	2.7	01Jul2015, 20:18	2.7
HG15	0.0297	0.2	01Jul2015, 13:34	0.1
FG15a	0.0156	4.3	01Jul2015, 12:06	0.4
G17	0.4398	4.6	01Jul2015, 12:06	3.1
G17-G18	0.4398	4.5	01Jul2015, 12:10	3.1
FG16	0.0773	18.0	01Jul2015, 12:08	1.7
G18	0.5171	22.5	01Jul2015, 12:08	4.8
G18-POND E	0.5171	22.4	01Jul2015, 12:10	4.8
HG30	0.1844	0.7	01Jul2015, 14:46	0.5
FG30-PONDHS	0.1844	0.7	01Jul2015, 15:08	0.4
FG31	0.0922	18.5	01Jul2015, 12:20	2.4
POND HS	0.2766	10.4	01Jul2015, 12:42	2.8
FG17a	0.0694	15.8	01Jul2015, 12:10	1.6
FG17a-POND E	0.0694	15.6	01Jul2015, 12:10	1.5
FG18	0.0644	1.2	01Jul2015, 12:42	0.4
FG18-POND E	0.0644	1.2	01Jul2015, 12:44	0.4
FG19	0.0527	9.9	01Jul2015, 12:12	1.1
FG17c	0.0313	0.6	01Jul2015, 12:16	0.2
FG17b	0.0214	6.6	01Jul2015, 12:06	0.6
<b>POND E</b>	<b>1.0329</b>	<b>9.2</b>	<b>01Jul2015, 15:22</b>	<b>9.2</b>
FG20	0.0109	9.4	01Jul2015, 12:04	0.7
H08-H09	1.0438	11.5	01Jul2015, 12:06	9.9
FH01	0.1344	2.9	01Jul2015, 12:42	0.9
<b>POND H</b>	<b>0.1344</b>	<b>0.7</b>	<b>01Jul2015, 18:24</b>	<b>0.9</b>
FH02	0.0138	1.1	01Jul2015, 12:12	0.2
H12	0.1482	1.2	01Jul2015, 12:12	1.1





### GIECK GRADED CONDITIONS



### HAEGLER GRADED CONDITIONS





FUTURE 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
OS01	1.5594	757	01Jul2015, 12:32	122
DB16	0.0578	92	01Jul2015, 12:10	8
B10	1.6172	794	01Jul2015, 12:30	130
B10-B11	1.6172	793	01Jul2015, 12:32	130
DB17	0.0048	16	01Jul2015, 12:02	1
B11	1.6220	795	01Jul2015, 12:32	131
B11-POND C	1.6220	795	01Jul2015, 12:34	131
DB21	0.0519	54	01Jul2015, 12:08	5
DB18	0.0346	64	01Jul2015, 12:08	5
DB19	0.0281	36	01Jul2015, 12:10	3
DB20	0.0147	25	01Jul2015, 12:08	2
POND C	1.7513	749	01Jul2015, 12:46	141
POND C-B16	1.7513	749	01Jul2015, 12:48	141
DB25	0.0211	45	01Jul2015, 12:04	3
B16	1.7724	754	01Jul2015, 12:48	144
B16-B17	1.7724	754	01Jul2015, 12:50	144
DB26	0.0682	136	01Jul2015, 12:10	12
B17	1.8406	778	01Jul2015, 12:50	156
B17-B26	1.8406	778	01Jul2015, 12:52	156
OS03	0.1984	130	01Jul2015, 12:18	16
DB01	0.0719	90	01Jul2015, 12:08	8
B01	0.2703	199	01Jul2015, 12:14	23
B01-B02	0.2703	199	01Jul2015, 12:14	23
OS02	0.2219	148	01Jul2015, 12:20	19
DB02	0.0516	71	01Jul2015, 12:06	5
B02	0.5438	380	01Jul2015, 12:14	48
B02-POND A	0.5438	379	01Jul2015, 12:16	47
OS04	0.1359	83	01Jul2015, 12:16	10
DB03	0.0703	70	01Jul2015, 12:10	6
B03	0.2062	145	01Jul2015, 12:12	16
B03-B04	0.2062	145	01Jul2015, 12:18	16
DB04	0.0422	44	01Jul2015, 12:10	4
DB05	0.0384	37	01Jul2015, 12:14	4
B04	0.2868	218	01Jul2015, 12:16	24
B04-B05	0.2868	218	01Jul2015, 12:16	24
DB06	0.0219	44	01Jul2015, 12:08	4
B05	0.3087	253	01Jul2015, 12:14	28
B05-POND A	0.3087	252	01Jul2015, 12:16	27
DB07	0.0254	35	01Jul2015, 12:06	3
DB08	0.0297	32	01Jul2015, 12:06	3
POND A	0.9076	545	01Jul2015, 12:26	75
POND A-B06	0.9076	544	01Jul2015, 12:28	75
DB09	0.0189	34	01Jul2015, 12:04	2
B06	0.9265	552	01Jul2015, 12:26	77
B06-B07	0.9265	551	01Jul2015, 12:30	77
DB11	0.0969	114	01Jul2015, 12:12	11
DB10	0.0364	56	01Jul2015, 12:08	5
B07	1.0598	635	01Jul2015, 12:26	92
B07-B09	1.0598	634	01Jul2015, 12:30	92
DB12	0.0453	81	01Jul2015, 12:06	7

FUTURE 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
B09	1.1051	659	01Jul2015, 12:28	99
B09-POND B	1.1051	658	01Jul2015, 12:28	99
DB15	0.1234	105	01Jul2015, 12:16	12
DB13	0.0703	89	01Jul2015, 12:12	9
DB14	0.0556	93	01Jul2015, 12:08	8
POND B	1.3544	676	01Jul2015, 12:42	126
POND B-B12	1.3544	676	01Jul2015, 12:44	126
DB22	0.0516	91	01Jul2015, 12:08	8
DB23	0.0172	45	01Jul2015, 12:04	4
B12	1.4232	703	01Jul2015, 12:38	137
B12-B14	1.4232	703	01Jul2015, 12:38	137
DB24	0.0531	94	01Jul2015, 12:08	8
B14	1.4763	727	01Jul2015, 12:32	145
B14-B15	1.4763	726	01Jul2015, 12:32	145
DB28	0.0741	85	01Jul2015, 12:12	8
B15	1.5504	764	01Jul2015, 12:32	153
B15-B26	1.5504	763	01Jul2015, 12:38	152
DB29	0.1697	146	01Jul2015, 12:18	17
DB27	0.0508	68	01Jul2015, 12:16	7
<b>B26</b>	<b>3.6115</b>	<b>1601</b>	<b>01Jul2015, 12:46</b>	<b>331</b>
B26-27	3.6115	1601	01Jul2015, 12:48	331
FB-02	0.0500	67	01Jul2015, 12:16	7
FB-01	0.0373	62	01Jul2015, 12:08	5
FB01-B19	0.0373	62	01Jul2015, 12:08	5
B19	0.0873	124	01Jul2015, 12:12	13
B19-27	0.0873	124	01Jul2015, 12:12	13
FB-03	0.0078	22	01Jul2015, 12:04	2
27	3.7066	1639	01Jul2015, 12:48	345
27-32	3.7066	1639	01Jul2015, 12:48	344
WH-24	0.1325	218	01Jul2015, 12:10	20
WH-26	0.0839	49	01Jul2015, 12:20	6
WH-27	0.0217	23	01Jul2015, 12:04	2
30	0.2381	271	01Jul2015, 12:10	28
30-31	0.2381	270	01Jul2015, 12:12	28
WH-28	0.0398	60	01Jul2015, 12:12	6
31	0.2779	330	01Jul2015, 12:12	33
31-32	0.2779	329	01Jul2015, 12:14	33
WH-29	0.0495	77	01Jul2015, 12:10	7
WH-31	0.0406	75	01Jul2015, 12:06	6
WH-30	0.0159	26	01Jul2015, 12:02	2
32	4.0905	1780	01Jul2015, 12:42	392
WH32	0.0458	55	01Jul2015, 12:02	4
BEN POND	4.1363	1385	01Jul2015, 13:16	376
WH-33	0.0064	12	01Jul2015, 12:06	1
33	4.1427	1386	01Jul2015, 13:16	377
33-37	4.1427	1386	01Jul2015, 13:20	375
WH35	0.1550	171	01Jul2015, 12:10	15
WH34	0.0450	68	01Jul2015, 12:08	6
B34-36	0.0450	68	01Jul2015, 12:10	6
36	0.2000	239	01Jul2015, 12:10	21

FUTURE 100-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>100</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>100</sub> (AC. FT.)
36-37	0.2000	238	01Jul2015, 12:12	21
WH36	0.0750	63	01Jul2015, 12:10	6
<b>37</b>	<b>4.4177</b>	<b>1425</b>	<b>01Jul2015, 13:20</b>	<b>402</b>
FG08A	0.0750	125	01Jul2015, 12:08	10
FG08A-G05	0.0750	125	01Jul2015, 12:10	10
FG10	0.0669	47	01Jul2015, 12:36	8
FG08B	0.0630	94	01Jul2015, 12:10	9
FG08B-G05	0.0630	93	01Jul2015, 12:12	9
FG11	0.0625	81	01Jul2015, 12:16	9
FG09	0.0484	52	01Jul2015, 12:14	6
FG09-G05	0.0484	52	01Jul2015, 12:16	6
G05	0.3158	367	01Jul2015, 12:12	41
FG13	0.0661	46	01Jul2015, 12:24	6
FG14	0.0331	44	01Jul2015, 12:14	5
FG12	0.0328	55	01Jul2015, 12:10	5
POND D	0.4478	132	01Jul2015, 13:04	47
POND D-G17	0.4478	132	01Jul2015, 13:04	47
FG15	0.1017	100	01Jul2015, 12:20	12
G17a	0.1017	100	01Jul2015, 12:20	12
FG15a	0.0156	30	01Jul2015, 12:06	2
G17	0.5651	190	01Jul2015, 12:30	61
G17-G18	0.5651	190	01Jul2015, 12:32	61
FG16	0.0773	135	01Jul2015, 12:06	11
G18	0.6424	248	01Jul2015, 12:10	72
G18-POND E	0.6424	246	01Jul2015, 12:10	72
FG31	0.0922	123	01Jul2015, 12:18	14
FG30	0.0400	82	01Jul2015, 12:04	6
FG30-PONDHS	0.0400	81	01Jul2015, 12:10	6
POND HS	0.1322	159	01Jul2015, 12:22	20
FG17a	0.0694	111	01Jul2015, 12:08	9
FG17a-POND E	0.0694	110	01Jul2015, 12:08	9
FG18	0.0644	59	01Jul2015, 12:24	8
FG18-POND E	0.0644	59	01Jul2015, 12:24	8
FG19	0.0527	92	01Jul2015, 12:08	8
FG17c	0.0313	34	01Jul2015, 12:06	3
FG17b	0.0214	42	01Jul2015, 12:06	3
POND E	1.0138	242	01Jul2015, 13:28	101
H08	1.0138	207	01Jul2015, 13:28	87
H09	0.0000	34	01Jul2015, 13:28	14
FH01	0.1344	161	01Jul2015, 12:16	18
POND H	0.1344	58	01Jul2015, 12:50	15

FUTURE 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
OS01	1.5594	510	01 Jul2015, 12:34	87
DB16	0.0578	72	01 Jul2015, 12:10	7
B10	1.6172	537	01 Jul2015, 12:32	93
B10-B11	1.6172	537	01 Jul2015, 12:32	93
DB17	0.0048	13	01 Jul2015, 12:02	1
B11	1.6220	538	01 Jul2015, 12:32	94
B11-POND C	1.6220	538	01 Jul2015, 12:36	94
DB21	0.0519	38	01 Jul2015, 12:08	3
DB18	0.0346	50	01 Jul2015, 12:08	4
DB19	0.0281	27	01 Jul2015, 12:10	3
DB20	0.0147	19	01 Jul2015, 12:08	2
POND C	1.7513	507	01 Jul2015, 12:48	101
POND C-B16	1.7513	507	01 Jul2015, 12:50	101
DB25	0.0211	35	01 Jul2015, 12:04	3
B16	1.7724	511	01 Jul2015, 12:50	103
B16-B17	1.7724	510	01 Jul2015, 12:54	103
DB26	0.0682	110	01 Jul2015, 12:10	10
B17	1.8406	529	01 Jul2015, 12:52	113
B17-B26	1.8406	529	01 Jul2015, 12:54	113
OS03	0.1984	88	01 Jul2015, 12:20	11
DB01	0.0719	66	01 Jul2015, 12:08	6
B01	0.2703	139	01 Jul2015, 12:14	17
B01-B02	0.2703	138	01 Jul2015, 12:16	17
OS02	0.2219	102	01 Jul2015, 12:22	14
DB02	0.0516	52	01 Jul2015, 12:06	4
B02	0.5438	263	01 Jul2015, 12:16	34
B02-POND A	0.5438	263	01 Jul2015, 12:16	34
OS04	0.1359	54	01 Jul2015, 12:18	7
DB03	0.0703	49	01 Jul2015, 12:10	5
B03	0.2062	98	01 Jul2015, 12:14	11
B03-B04	0.2062	98	01 Jul2015, 12:18	11
DB04	0.0422	31	01 Jul2015, 12:10	3
DB05	0.0384	27	01 Jul2015, 12:14	3
B04	0.2868	150	01 Jul2015, 12:16	17
B04-B05	0.2868	149	01 Jul2015, 12:16	17
DB06	0.0219	35	01 Jul2015, 12:08	3
B05	0.3087	176	01 Jul2015, 12:16	20
B05-POND A	0.3087	176	01 Jul2015, 12:16	20
DB07	0.0254	26	01 Jul2015, 12:06	2
DB08	0.0297	22	01 Jul2015, 12:06	2
POND A	0.9076	380	01 Jul2015, 12:28	53
POND A-B06	0.9076	380	01 Jul2015, 12:28	53
DB09	0.0189	26	01 Jul2015, 12:04	2
B06	0.9265	385	01 Jul2015, 12:28	55
B06-B07	0.9265	384	01 Jul2015, 12:32	54
DB11	0.0969	85	01 Jul2015, 12:12	9
DB10	0.0364	43	01 Jul2015, 12:08	4
B07	1.0598	441	01 Jul2015, 12:30	66
B07-B09	1.0598	440	01 Jul2015, 12:34	66
DB12	0.0453	63	01 Jul2015, 12:06	5

FUTURE 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
B09	1.1051	455	01 Jul2015, 12:32	71
B09-POND B	1.1051	455	01 Jul2015, 12:34	71
DB15	0.1234	75	01 Jul2015, 12:16	9
DB13	0.0703	67	01 Jul2015, 12:12	7
DB14	0.0556	72	01 Jul2015, 12:08	6
POND B	1.3544	501	01 Jul2015, 12:40	92
POND B-B12	1.3544	501	01 Jul2015, 12:42	92
DB22	0.0516	72	01 Jul2015, 12:08	6
DB23	0.0172	38	01 Jul2015, 12:04	3
B12	1.4232	521	01 Jul2015, 12:42	101
B12-B14	1.4232	521	01 Jul2015, 12:42	101
DB24	0.0531	73	01 Jul2015, 12:08	6
B14	1.4763	535	01 Jul2015, 12:42	107
B14-B15	1.4763	535	01 Jul2015, 12:44	107
DB28	0.0741	63	01 Jul2015, 12:12	6
B15	1.5504	554	01 Jul2015, 12:42	113
B15-B26	1.5504	553	01 Jul2015, 12:48	112
DB29	0.1697	105	01 Jul2015, 12:18	13
DB27	0.0508	53	01 Jul2015, 12:16	6
<b>B26</b>	<b>3.6115</b>	<b>1134</b>	<b>01 Jul2015, 12:50</b>	<b>243</b>
B26-27	3.6115	1133	01 Jul2015, 12:52	242
FB-02	0.0500	53	01 Jul2015, 12:16	6
FB-01	0.0373	49	01 Jul2015, 12:08	4
FB01-B19	0.0373	48	01 Jul2015, 12:10	4
B19	0.0873	97	01 Jul2015, 12:12	10
B19-27	0.0873	96	01 Jul2015, 12:12	10
FB-03	0.0078	18	01 Jul2015, 12:04	1
27	3.7066	1161	01 Jul2015, 12:52	253
27-32	3.7066	1160	01 Jul2015, 12:52	253
WH-24	0.1325	171	01 Jul2015, 12:10	15
WH-26	0.0839	33	01 Jul2015, 12:22	5
WH-27	0.0217	16	01 Jul2015, 12:04	1
30	0.2381	205	01 Jul2015, 12:10	21
30-31	0.2381	205	01 Jul2015, 12:12	21
WH-28	0.0398	47	01 Jul2015, 12:12	5
31	0.2779	252	01 Jul2015, 12:12	25
31-32	0.2779	251	01 Jul2015, 12:14	25
WH-29	0.0495	60	01 Jul2015, 12:10	6
WH-31	0.0406	60	01 Jul2015, 12:08	5
WH-30	0.0159	19	01 Jul2015, 12:02	1
32	4.0905	1249	01 Jul2015, 12:52	290
WH32	0.0458	38	01 Jul2015, 12:02	3
BEN POND	4.1363	967	01 Jul2015, 13:16	275
WH-33	0.0064	9	01 Jul2015, 12:06	1
33	4.1427	968	01 Jul2015, 13:16	276
33-37	4.1427	967	01 Jul2015, 13:20	274
WH35	0.1550	124	01 Jul2015, 12:10	11
WH34	0.0450	52	01 Jul2015, 12:08	5
B34-36	0.0450	52	01 Jul2015, 12:10	5
36	0.2000	176	01 Jul2015, 12:10	16

FUTURE 50-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>50</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>50</sub> (AC. FT.)
36-37	0.2000	174	01 Jul2015, 12:14	16
WH36	0.0750	43	01 Jul2015, 12:10	4
<b>37</b>	<b>4.4177</b>	<b>997</b>	<b>01 Jul2015, 13:20</b>	<b>294</b>
FG08A	0.0750	97	01 Jul2015, 12:08	8
FG08A-G05	0.0750	97	01 Jul2015, 12:10	8
FG10	0.0669	35	01 Jul2015, 12:38	6
FG08B	0.0630	72	01 Jul2015, 12:10	7
FG08B-G05	0.0630	72	01 Jul2015, 12:12	7
FG11	0.0625	63	01 Jul2015, 12:16	7
FG09	0.0484	39	01 Jul2015, 12:16	4
FG09-G05	0.0484	39	01 Jul2015, 12:16	4
G05	0.3158	281	01 Jul2015, 12:14	32
FG13	0.0661	32	01 Jul2015, 12:26	5
FG14	0.0331	34	01 Jul2015, 12:14	4
FG12	0.0328	44	01 Jul2015, 12:10	4
POND D	0.4478	90	01 Jul2015, 13:10	35
POND D-G17	0.4478	90	01 Jul2015, 13:12	35
FG15	0.1017	75	01 Jul2015, 12:20	9
G17a	0.1017	75	01 Jul2015, 12:20	9
FG15a	0.0156	24	01 Jul2015, 12:06	2
G17	0.5651	124	01 Jul2015, 12:38	46
G17-G18	0.5651	124	01 Jul2015, 12:40	46
FG16	0.0773	105	01 Jul2015, 12:08	9
G18	0.6424	186	01 Jul2015, 12:10	54
G18-POND E	0.6424	185	01 Jul2015, 12:12	54
FG31	0.0922	97	01 Jul2015, 12:18	11
FG30	0.0400	65	01 Jul2015, 12:04	5
FG30-PONDHS	0.0400	64	01 Jul2015, 12:12	5
POND HS	0.1322	113	01 Jul2015, 12:26	16
FG17a	0.0694	85	01 Jul2015, 12:08	7
FG17a-POND E	0.0694	85	01 Jul2015, 12:08	7
FG18	0.0644	45	01 Jul2015, 12:24	6
FG18-POND E	0.0644	45	01 Jul2015, 12:24	6
FG19	0.0527	73	01 Jul2015, 12:08	6
FG17c	0.0313	24	01 Jul2015, 12:06	2
FG17b	0.0214	34	01 Jul2015, 12:06	3
POND E	1.0138	151	01 Jul2015, 13:58	73
H08	1.0138	135	01 Jul2015, 13:58	63
H09	0.0000	16	01 Jul2015, 13:58	10
FH01	0.1344	123	01 Jul2015, 12:18	14
POND H	0.1344	32	01 Jul2015, 13:02	11

FUTURE 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
OS01	1.5594	316	01Jul2015, 12:36	58.6
DB16	0.0578	54	01Jul2015, 12:10	5.0
B10	1.6172	335	01Jul2015, 12:34	63.6
B10-B11	1.6172	335	01Jul2015, 12:34	63.5
DB17	0.0048	11	01Jul2015, 12:02	0.9
B11	1.6220	336	01Jul2015, 12:34	64.4
B11-POND C	1.6220	336	01Jul2015, 12:38	64.0
DB21	0.0519	25	01Jul2015, 12:08	2.3
DB18	0.0346	39	01Jul2015, 12:08	3.2
DB19	0.0281	20	01Jul2015, 12:10	1.9
DB20	0.0147	15	01Jul2015, 12:10	1.3
POND C	1.7513	310	01Jul2015, 12:52	68.6
POND C-B16	1.7513	310	01Jul2015, 12:54	68.4
DB25	0.0211	27	01Jul2015, 12:04	2.0
B16	1.7724	313	01Jul2015, 12:54	70.3
B16-B17	1.7724	312	01Jul2015, 12:58	69.9
DB26	0.0682	88	01Jul2015, 12:10	8.0
B17	1.8406	326	01Jul2015, 12:58	77.9
B17-B26	1.8406	326	01Jul2015, 13:00	77.5
OS03	0.1984	55	01Jul2015, 12:20	7.7
DB01	0.0719	46	01Jul2015, 12:08	4.1
B01	0.2703	89	01Jul2015, 12:14	11.7
B01-B02	0.2703	89	01Jul2015, 12:16	11.7
OS02	0.2219	65	01Jul2015, 12:22	9.3
DB02	0.0516	36	01Jul2015, 12:06	2.8
B02	0.5438	169	01Jul2015, 12:16	23.8
B02-POND A	0.5438	169	01Jul2015, 12:18	23.8
OS04	0.1359	32	01Jul2015, 12:18	4.5
DB03	0.0703	32	01Jul2015, 12:10	3.2
B03	0.2062	61	01Jul2015, 12:14	7.7
B03-B04	0.2062	60	01Jul2015, 12:20	7.6
DB04	0.0422	21	01Jul2015, 12:10	2.0
DB05	0.0384	18	01Jul2015, 12:14	2.0
B04	0.2868	94	01Jul2015, 12:18	11.7
B04-B05	0.2868	94	01Jul2015, 12:18	11.7
DB06	0.0219	28	01Jul2015, 12:08	2.4
B05	0.3087	115	01Jul2015, 12:16	14.0
B05-POND A	0.3087	114	01Jul2015, 12:18	14.0
DB07	0.0254	18	01Jul2015, 12:06	1.5
DB08	0.0297	15	01Jul2015, 12:08	1.3
POND A	0.9076	217	01Jul2015, 12:32	35.3
POND A-B06	0.9076	217	01Jul2015, 12:34	35.2
DB09	0.0189	19	01Jul2015, 12:04	1.4
B06	0.9265	221	01Jul2015, 12:34	36.6
B06-B07	0.9265	220	01Jul2015, 12:38	36.3
DB11	0.0969	60	01Jul2015, 12:12	6.2
DB10	0.0364	32	01Jul2015, 12:08	2.7
B07	1.0598	252	01Jul2015, 12:38	45.2
B07-B09	1.0598	252	01Jul2015, 12:40	44.9
DB12	0.0453	48	01Jul2015, 12:06	3.9

FUTURE 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
B09	1.1051	261	01Jul2015, 12:40	48.8
B09-POND B	1.1051	260	01Jul2015, 12:40	48.7
DB15	0.1234	50	01Jul2015, 12:18	6.1
DB13	0.0703	49	01Jul2015, 12:12	4.9
DB14	0.0556	54	01Jul2015, 12:08	4.7
POND B	1.3544	291	01Jul2015, 12:48	63.9
POND B-B12	1.3544	290	01Jul2015, 12:50	63.8
DB22	0.0516	55	01Jul2015, 12:08	4.8
DB23	0.0172	31	01Jul2015, 12:04	2.5
B12	1.4232	304	01Jul2015, 12:48	71.1
B12-B14	1.4232	304	01Jul2015, 12:50	70.9
DB24	0.0531	56	01Jul2015, 12:08	4.6
B14	1.4763	313	01Jul2015, 12:50	75.5
B14-B15	1.4763	313	01Jul2015, 12:52	75.3
DB28	0.0741	44	01Jul2015, 12:12	4.4
B15	1.5504	326	01Jul2015, 12:22	79.8
B15-B26	1.5504	325	01Jul2015, 12:28	78.8
DB29	0.1697	71	01Jul2015, 12:20	9.0
DB27	0.0508	40	01Jul2015, 12:16	4.3
<b>B26</b>	<b>3.6115</b>	<b>685</b>	<b>01Jul2015, 12:58</b>	<b>169.7</b>
B26-27	3.6115	684	01Jul2015, 13:00	169.0
FB-02	0.0500	40	01Jul2015, 12:16	4.4
FB-01	0.0373	37	01Jul2015, 12:08	3.1
FB01-B19	0.0373	36	01Jul2015, 12:10	3.1
B19	0.0873	73	01Jul2015, 12:12	7.5
B19-27	0.0873	73	01Jul2015, 12:14	7.5
FB-03	0.0078	15	01Jul2015, 12:04	1.1
27	3.7066	702	01Jul2015, 13:00	177.6
27-32	3.7066	701	01Jul2015, 13:02	177.2
WH-24	0.1325	129	01Jul2015, 12:10	11.7
WH-26	0.0839	20	01Jul2015, 12:22	3.0
WH-27	0.0217	10	01Jul2015, 12:04	0.8
30	0.2381	150	01Jul2015, 12:10	15.5
30-31	0.2381	149	01Jul2015, 12:12	15.5
WH-28	0.0398	36	01Jul2015, 12:12	3.4
31	0.2779	185	01Jul2015, 12:12	18.9
31-32	0.2779	185	01Jul2015, 12:14	18.8
WH-29	0.0495	45	01Jul2015, 12:10	4.2
WH-31	0.0406	46	01Jul2015, 12:08	3.8
WH-30	0.0159	13	01Jul2015, 12:02	0.9
32	4.0905	757	01Jul2015, 13:00	204.8
WH32	0.0458	24	01Jul2015, 12:02	1.6
BEN POND	4.1363	578	01Jul2015, 13:28	193.5
WH-33	0.0064	7	01Jul2015, 12:08	0.6
33	4.1427	579	01Jul2015, 13:28	194.1
33-37	4.1427	579	01Jul2015, 13:32	192.5
WH35	0.1550	84	01Jul2015, 12:10	8.0
WH34	0.0450	38	01Jul2015, 12:08	3.3
B34-36	0.0450	38	01Jul2015, 12:10	3.3
36	0.2000	122	01Jul2015, 12:10	11.4



FUTURE 25-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>25</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>25</sub> (AC. FT.)
36-37	0.2000	121	01Jul2015, 12:14	11.3
WH36	0.0750	27	01Jul2015, 12:12	2.9
<b>37</b>	<b>4.4177</b>	<b>598</b>	<b>01Jul2015, 13:32</b>	<b>206.7</b>
FG08A	0.0750	73	01Jul2015, 12:08	6.0
FG08A-G05	0.0750	72	01Jul2015, 12:10	6.0
FG10	0.0669	25	01Jul2015, 12:38	4.4
FG08B	0.0630	54	01Jul2015, 12:10	5.0
FG08B-G05	0.0630	54	01Jul2015, 12:14	5.0
FG11	0.0625	47	01Jul2015, 12:18	5.3
FG09	0.0484	28	01Jul2015, 12:16	3.0
FG09-G05	0.0484	27	01Jul2015, 12:18	3.0
G05	0.3158	208	01Jul2015, 12:14	23.7
FG13	0.0661	21	01Jul2015, 12:26	3.2
FG14	0.0331	26	01Jul2015, 12:14	2.7
FG12	0.0328	33	01Jul2015, 12:10	3.0
POND D	0.4478	51	01Jul2015, 13:28	24.6
POND D-G17	0.4478	51	01Jul2015, 13:28	24.6
FG15	0.1017	54	01Jul2015, 12:20	6.8
G17a	0.1017	54	01Jul2015, 12:20	6.8
FG15a	0.0156	18	01Jul2015, 12:06	1.4
G17	0.5651	75	01Jul2015, 12:22	32.7
G17-G18	0.5651	75	01Jul2015, 12:24	32.7
FG16	0.0773	79	01Jul2015, 12:08	6.5
G18	0.6424	134	01Jul2015, 12:10	39.2
G18-POND E	0.6424	133	01Jul2015, 12:10	39.1
FG31	0.0922	74	01Jul2015, 12:18	8.5
FG30	0.0400	50	01Jul2015, 12:04	3.7
FG30-PONDHS	0.0400	49	01Jul2015, 12:12	3.7
POND HS	0.1322	63	01Jul2015, 12:34	12.1
FG17a	0.0694	64	01Jul2015, 12:08	5.5
FG17a-POND E	0.0694	63	01Jul2015, 12:10	5.5
FG18	0.0644	32	01Jul2015, 12:24	4.4
FG18-POND E	0.0644	32	01Jul2015, 12:26	4.4
FG19	0.0527	56	01Jul2015, 12:10	4.9
FG17c	0.0313	16	01Jul2015, 12:08	1.4
FG17b	0.0214	26	01Jul2015, 12:06	2.0
POND E	1.0138	82	01Jul2015, 14:32	49.6
H08	1.0138	72	01Jul2015, 14:32	41.3
H09	0.0000	10	01Jul2015, 14:32	8.3
FH01	0.1344	91	01Jul2015, 12:18	10.5
POND H	0.1344	18	01Jul2015, 13:18	7.9

FUTURE 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
OS01	1.5594	136	01 Jul 2015, 12:38	30.9
DB16	0.0578	35	01 Jul 2015, 12:10	3.3
B10	1.6172	147	01 Jul 2015, 12:36	34.2
B10-B11	1.6172	147	01 Jul 2015, 12:38	34.1
DB17	0.0048	9	01 Jul 2015, 12:02	0.7
B11	1.6220	148	01 Jul 2015, 12:38	34.8
B11-POND C	1.6220	148	01 Jul 2015, 12:42	34.5
DB21	0.0519	12	01 Jul 2015, 12:10	1.3
DB18	0.0346	26	01 Jul 2015, 12:08	2.1
DB19	0.0281	11	01 Jul 2015, 12:12	1.1
DB20	0.0147	9	01 Jul 2015, 12:10	0.8
POND C	1.7513	129	01 Jul 2015, 13:02	36.3
POND C-B16	1.7513	128	01 Jul 2015, 13:06	36.1
DB25	0.0211	18	01 Jul 2015, 12:04	1.3
B16	1.7724	130	01 Jul 2015, 13:06	37.4
B16-B17	1.7724	130	01 Jul 2015, 13:10	37.1
DB26	0.0682	62	01 Jul 2015, 12:10	5.6
B17	1.8406	138	01 Jul 2015, 13:08	42.7
B17-B26	1.8406	138	01 Jul 2015, 13:12	42.4
OS03	0.1984	24	01 Jul 2015, 12:24	4.1
DB01	0.0719	25	01 Jul 2015, 12:10	2.4
B01	0.2703	42	01 Jul 2015, 12:14	6.5
B01-B02	0.2703	42	01 Jul 2015, 12:16	6.5
OS02	0.2219	30	01 Jul 2015, 12:26	5.1
DB02	0.0516	20	01 Jul 2015, 12:06	1.7
B02	0.5438	79	01 Jul 2015, 12:18	13.2
B02-POND A	0.5438	79	01 Jul 2015, 12:20	13.1
OS04	0.1359	12	01 Jul 2015, 12:22	2.3
DB03	0.0703	16	01 Jul 2015, 12:12	1.8
B03	0.2062	26	01 Jul 2015, 12:16	4.1
B03-B04	0.2062	26	01 Jul 2015, 12:22	4.0
DB04	0.0422	10	01 Jul 2015, 12:12	1.2
DB05	0.0384	9	01 Jul 2015, 12:16	1.1
B04	0.2868	42	01 Jul 2015, 12:20	6.3
B04-B05	0.2868	42	01 Jul 2015, 12:20	6.3
DB06	0.0219	19	01 Jul 2015, 12:08	1.6
B05	0.3087	55	01 Jul 2015, 12:18	8.0
B05-POND A	0.3087	55	01 Jul 2015, 12:20	8.0
DB07	0.0254	10	01 Jul 2015, 12:08	0.9
DB08	0.0297	7	01 Jul 2015, 12:08	0.7
POND A	0.9076	69	01 Jul 2015, 12:52	17.6
POND A-B06	0.9076	69	01 Jul 2015, 12:54	17.5
DB09	0.0189	12	01 Jul 2015, 12:04	0.9
B06	0.9265	70	01 Jul 2015, 12:52	18.4
B06-B07	0.9265	70	01 Jul 2015, 13:00	18.2
DB11	0.0969	35	01 Jul 2015, 12:14	3.8
DB10	0.0364	19	01 Jul 2015, 12:08	1.7
B07	1.0598	82	01 Jul 2015, 12:58	23.7
B07-B09	1.0598	82	01 Jul 2015, 13:04	23.4
DB12	0.0453	31	01 Jul 2015, 12:08	2.5

FUTURE 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
B09	1.1051	86	01 Jul 2015, 13:02	26.0
B09-POND B	1.1051	86	01 Jul 2015, 13:04	25.9
DB15	0.1234	25	01 Jul 2015, 12:20	3.4
DB13	0.0703	29	01 Jul 2015, 12:14	3.1
DB14	0.0556	35	01 Jul 2015, 12:08	3.1
POND B	1.3544	126	01 Jul 2015, 12:26	35.2
POND B-B12	1.3544	126	01 Jul 2015, 12:28	35.1
DB22	0.0516	36	01 Jul 2015, 12:08	3.2
DB23	0.0172	23	01 Jul 2015, 12:06	1.8
B12	1.4232	148	01 Jul 2015, 12:26	40.2
B12-B14	1.4232	148	01 Jul 2015, 12:28	40.0
DB24	0.0531	36	01 Jul 2015, 12:08	3.0
B14	1.4763	162	01 Jul 2015, 12:26	43.0
B14-B15	1.4763	161	01 Jul 2015, 12:28	42.9
DB28	0.0741	24	01 Jul 2015, 12:14	2.7
B15	1.5504	177	01 Jul 2015, 12:26	45.6
B15-B26	1.5504	176	01 Jul 2015, 12:34	44.9
DB29	0.1697	37	01 Jul 2015, 12:20	5.2
DB27	0.0508	25	01 Jul 2015, 12:16	2.8
B26	3.6115	288	01 Jul 2015, 12:22	95.4
B26-27	3.6115	287	01 Jul 2015, 12:26	94.8
FB-02	0.0500	26	01 Jul 2015, 12:18	2.9
FB-01	0.0373	23	01 Jul 2015, 12:08	2.0
FB01-B19	0.0373	23	01 Jul 2015, 12:10	2.0
B19	0.0873	47	01 Jul 2015, 12:12	5.0
B19-27	0.0873	47	01 Jul 2015, 12:14	4.9
FB-03	0.0078	11	01 Jul 2015, 12:04	0.8
27	3.7066	326	01 Jul 2015, 12:24	100.5
27-32	3.7066	326	01 Jul 2015, 12:26	100.2
WH-24	0.1325	84	01 Jul 2015, 12:10	7.7
WH-26	0.0839	8	01 Jul 2015, 12:26	1.5
WH-27	0.0217	4	01 Jul 2015, 12:06	0.4
30	0.2381	91	01 Jul 2015, 12:10	9.7
30-31	0.2381	91	01 Jul 2015, 12:12	9.7
WH-28	0.0398	23	01 Jul 2015, 12:12	2.2
31	0.2779	114	01 Jul 2015, 12:12	11.9
31-32	0.2779	113	01 Jul 2015, 12:14	11.9
WH-29	0.0495	29	01 Jul 2015, 12:10	2.7
WH-31	0.0406	30	01 Jul 2015, 12:08	2.5
WH-30	0.0159	7	01 Jul 2015, 12:02	0.5
32	4.0905	445	01 Jul 2015, 12:24	117.8
WH32	0.0458	10	01 Jul 2015, 12:04	0.9
BEN POND	4.1363	237	01 Jul 2015, 13:58	110.4
WH-33	0.0064	5	01 Jul 2015, 12:08	0.4
33	4.1427	237	01 Jul 2015, 13:58	110.8
33-37	4.1427	237	01 Jul 2015, 14:04	109.7
WH35	0.1550	44	01 Jul 2015, 12:10	4.6
WH34	0.0450	23	01 Jul 2015, 12:10	2.1
B34-36	0.0450	23	01 Jul 2015, 12:12	2.1
36	0.2000	67	01 Jul 2015, 12:12	6.7

FUTURE 10-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>10</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>10</sub> (AC. FT.)
36-37	0.2000	66	01 Jul 2015, 12:16	6.7
WH36	0.0750	11	01 Jul 2015, 12:14	1.5
37	4.4177	246	01 Jul 2015, 14:02	117.9
FG08A	0.0750	46	01 Jul 2015, 12:08	3.9
FG08A-G05	0.0750	45	01 Jul 2015, 12:12	3.9
FG10	0.0669	15	01 Jul 2015, 12:40	2.7
FG08B	0.0630	34	01 Jul 2015, 12:12	3.2
FG08B-G05	0.0630	34	01 Jul 2015, 12:14	3.2
FG11	0.0625	30	01 Jul 2015, 12:18	3.5
FG09	0.0484	16	01 Jul 2015, 12:16	1.8
FG09-G05	0.0484	16	01 Jul 2015, 12:18	1.8
G05	0.3158	128	01 Jul 2015, 12:14	15.1
FG13	0.0661	11	01 Jul 2015, 12:28	1.8
FG14	0.0331	16	01 Jul 2015, 12:16	1.8
FG12	0.0328	22	01 Jul 2015, 12:10	2.0
POND D	0.4478	19	01 Jul 2015, 14:28	14.6
POND D-G17	0.4478	19	01 Jul 2015, 14:30	14.5
FG15	0.1017	31	01 Jul 2015, 12:22	4.2
G17a	0.1017	31	01 Jul 2015, 12:22	4.2
FG15a	0.0156	12	01 Jul 2015, 12:06	0.9
G17	0.5651	41	01 Jul 2015, 12:26	19.6
G17-G18	0.5651	41	01 Jul 2015, 12:28	19.6
FG16	0.0773	51	01 Jul 2015, 12:08	4.2
G18	0.6424	82	01 Jul 2015, 12:10	23.8
G18-POND E	0.6424	82	01 Jul 2015, 12:12	23.8
FG31	0.0922	49	01 Jul 2015, 12:18	5.7
FG30	0.0400	33	01 Jul 2015, 12:06	2.5
FG30-PONDHS	0.0400	33	01 Jul 2015, 12:12	2.4
POND HS	0.1322	37	01 Jul 2015, 12:38	8.1
FG17a	0.0694	40	01 Jul 2015, 12:08	3.5
FG17a-POND E	0.0694	40	01 Jul 2015, 12:10	3.5
FG18	0.0644	19	01 Jul 2015, 12:26	2.7
FG18-POND E	0.0644	19	01 Jul 2015, 12:26	2.7
FG19	0.0527	37	01 Jul 2015, 12:10	3.3
FG17c	0.0313	8	01 Jul 2015, 12:08	0.8
FG17b	0.0214	17	01 Jul 2015, 12:06	1.3
POND E	1.0138	32	01 Jul 2015, 16:58	27.6
H08	1.0138	25	01 Jul 2015, 16:58	21.2
H09	0.0000	7	01 Jul 2015, 16:58	6.4
FH01	0.1344	56	01 Jul 2015, 12:18	6.7
POND H	0.1344	8	01 Jul 2015, 13:54	4.4

FUTURE 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
OS01	1.5594	55	01Jul2015, 12:46	16.6
DB16	0.0578	23	01Jul2015, 12:12	2.3
B10	1.6172	62	01Jul2015, 12:42	18.9
B10-B11	1.6172	62	01Jul2015, 12:42	18.9
DB17	0.0048	7	01Jul2015, 12:02	0.6
B11	1.6220	63	01Jul2015, 12:42	19.4
B11-POND C	1.6220	63	01Jul2015, 12:48	19.2
DB21	0.0519	5	01Jul2015, 12:12	0.7
DB18	0.0346	18	01Jul2015, 12:08	1.5
DB19	0.0281	7	01Jul2015, 12:12	0.7
DB20	0.0147	6	01Jul2015, 12:10	0.6
POND C	1.7513	50	01Jul2015, 13:28	19.4
POND C-B16	1.7513	50	01Jul2015, 13:32	19.2
DB25	0.0211	12	01Jul2015, 12:04	0.9
B16	1.7724	51	01Jul2015, 13:32	20.1
B16-B17	1.7724	51	01Jul2015, 13:36	19.9
DB26	0.0682	46	01Jul2015, 12:10	4.1
B17	1.8406	56	01Jul2015, 12:12	24.0
B17-B26	1.8406	56	01Jul2015, 12:16	23.8
OS03	0.1984	9	01Jul2015, 12:28	2.2
DB01	0.0719	14	01Jul2015, 12:10	1.5
B01	0.2703	19	01Jul2015, 12:14	3.7
B01-B02	0.2703	19	01Jul2015, 12:18	3.7
OS02	0.2219	13	01Jul2015, 12:28	2.8
DB02	0.0516	10	01Jul2015, 12:06	1.0
B02	0.5438	36	01Jul2015, 12:18	7.6
B02-POND A	0.5438	36	01Jul2015, 12:22	7.5
OS04	0.1359	4	01Jul2015, 12:28	1.2
DB03	0.0703	7	01Jul2015, 12:14	1.0
B03	0.2062	10	01Jul2015, 12:16	2.2
B03-B04	0.2062	10	01Jul2015, 12:26	2.2
DB04	0.0422	5	01Jul2015, 12:14	0.7
DB05	0.0384	5	01Jul2015, 12:18	0.7
B04	0.2868	18	01Jul2015, 12:22	3.5
B04-B05	0.2868	18	01Jul2015, 12:24	3.5
DB06	0.0219	14	01Jul2015, 12:08	1.2
B05	0.3087	26	01Jul2015, 12:22	4.7
B05-POND A	0.3087	26	01Jul2015, 12:22	4.7
DB07	0.0254	6	01Jul2015, 12:08	0.5
DB08	0.0297	3	01Jul2015, 12:10	0.4
POND A	0.9076	18	01Jul2015, 14:04	8.2
POND A-B06	0.9076	18	01Jul2015, 14:04	8.2
DB09	0.0189	8	01Jul2015, 12:06	0.6
B06	0.9265	18	01Jul2015, 14:04	8.8
B06-B07	0.9265	18	01Jul2015, 14:16	8.6
DB11	0.0969	20	01Jul2015, 12:14	2.4
DB10	0.0364	12	01Jul2015, 12:08	1.1
B07	1.0598	36	01Jul2015, 12:18	12.1
B07-B09	1.0598	35	01Jul2015, 12:24	12.0
DB12	0.0453	21	01Jul2015, 12:08	1.7

FUTURE 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
B09	1.1051	45	01Jul2015, 12:16	13.7
B09-POND B	1.1051	45	01Jul2015, 12:18	13.7
DB15	0.1234	12	01Jul2015, 12:22	2.0
DB13	0.0703	18	01Jul2015, 12:14	2.0
DB14	0.0556	23	01Jul2015, 12:10	2.1
POND B	1.3544	69	01Jul2015, 12:30	19.6
POND B-B12	1.3544	69	01Jul2015, 12:32	19.6
DB22	0.0516	25	01Jul2015, 12:10	2.2
DB23	0.0172	18	01Jul2015, 12:06	1.4
B12	1.4232	83	01Jul2015, 12:28	23.2
B12-B14	1.4232	83	01Jul2015, 12:30	23.1
DB24	0.0531	24	01Jul2015, 12:08	2.1
B14	1.4763	92	01Jul2015, 12:26	25.2
B14-B15	1.4763	92	01Jul2015, 12:28	25.1
DB28	0.0741	14	01Jul2015, 12:14	1.7
B15	1.5504	103	01Jul2015, 12:20	26.8
B15-B26	1.5504	103	01Jul2015, 12:30	26.3
DB29	0.1697	19	01Jul2015, 12:24	3.2
DB27	0.0508	17	01Jul2015, 12:16	1.9
<b>B26</b>	<b>3.6115</b>	<b>180</b>	<b>01Jul2015, 12:22</b>	<b>55.2</b>
B26-27	3.6115	180	01Jul2015, 12:26	54.7
FB-02	0.0500	17	01Jul2015, 12:18	2.0
FB-01	0.0373	15	01Jul2015, 12:08	1.4
FB01-B19	0.0373	15	01Jul2015, 12:10	1.4
B19	0.0873	31	01Jul2015, 12:14	3.4
B19-27	0.0873	31	01Jul2015, 12:14	3.4
FB-03	0.0078	8	01Jul2015, 12:04	0.6
27	3.7066	206	01Jul2015, 12:26	58.8
27-32	3.7066	205	01Jul2015, 12:28	58.5
WH-24	0.1325	57	01Jul2015, 12:10	5.4
WH-26	0.0839	3	01Jul2015, 12:32	0.8
WH-27	0.0217	1	01Jul2015, 12:08	0.2
30	0.2381	59	01Jul2015, 12:10	6.4
30-31	0.2381	59	01Jul2015, 12:12	6.4
WH-28	0.0398	15	01Jul2015, 12:12	1.5
31	0.2779	74	01Jul2015, 12:12	7.9
31-32	0.2779	74	01Jul2015, 12:16	7.9
WH-29	0.0495	19	01Jul2015, 12:12	1.9
WH-31	0.0406	21	01Jul2015, 12:08	1.8
WH-30	0.0159	4	01Jul2015, 12:02	0.3
32	4.0905	277	01Jul2015, 12:26	70.3
WH32	0.0458	4	01Jul2015, 12:04	0.5
BEN POND	4.1363	95	01Jul2015, 14:28	64.5
WH-33	0.0064	3	01Jul2015, 12:08	0.3
33	4.1427	95	01Jul2015, 14:28	64.8
33-37	4.1427	95	01Jul2015, 14:36	64.0
WH35	0.1550	22	01Jul2015, 12:12	2.8
WH34	0.0450	15	01Jul2015, 12:10	1.4
B34-36	0.0450	15	01Jul2015, 12:12	1.4
36	0.2000	37	01Jul2015, 12:12	4.2


FUTURE 5-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>5</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>5</sub> (AC. FT.)
36-37	0.2000	37	01Jul2015, 12:18	4.1
WH36	0.0750	4	01Jul2015, 12:16	0.8
<b>37</b>	<b>4.4177</b>	<b>100</b>	<b>01Jul2015, 14:22</b>	<b>68.9</b>
FG08A	0.0750	30	01Jul2015, 12:08	2.6
FG08A-G05	0.0750	30	01Jul2015, 12:12	2.6
FG10	0.0669	9	01Jul2015, 12:42	1.7
FG08B	0.0630	22	01Jul2015, 12:12	2.2
FG08B-G05	0.0630	22	01Jul2015, 12:16	2.2
FG11	0.0625	20	01Jul2015, 12:18	2.4
FG09	0.0484	9	01Jul2015, 12:18	1.2
FG09-G05	0.0484	9	01Jul2015, 12:20	1.2
G05	0.3158	82	01Jul2015, 12:16	10.1
FG13	0.0661	5	01Jul2015, 12:32	1.1
FG14	0.0331	11	01Jul2015, 12:16	1.2
FG12	0.0328	15	01Jul2015, 12:10	1.4
POND D	0.4478	12	01Jul2015, 14:44	8.9
POND D-G17	0.4478	12	01Jul2015, 14:46	8.8
FG15	0.1017	19	01Jul2015, 12:24	2.7
G17a	0.1017	19	01Jul2015, 12:24	2.7
FG15a	0.0156	8	01Jul2015, 12:06	0.6
G17	0.5651	24	01Jul2015, 12:20	12.2
G17-G18	0.5651	24	01Jul2015, 12:22	12.1
FG16	0.0773	34	01Jul2015, 12:08	2.9
G18	0.6424	52	01Jul2015, 12:10	15.0
G18-POND E	0.6424	51	01Jul2015, 12:12	15.0
FG31	0.0922	33	01Jul2015, 12:18	4.0
FG30	0.0400	23	01Jul2015, 12:06	1.7
FG30-PONDHS	0.0400	23	01Jul2015, 12:14	1.7
POND HS	0.1322	27	01Jul2015, 12:38	5.7
FG17a	0.0694	26	01Jul2015, 12:10	2.4
FG17a-POND E	0.0694	26	01Jul2015, 12:10	2.4
FG18	0.0644	11	01Jul2015, 12:28	1.8
FG18-POND E	0.0644	11	01Jul2015, 12:28	1.8
FG19	0.0527	25	01Jul2015, 12:10	2.3
FG17c	0.0313	3	01Jul2015, 12:10	0.4
FG17b	0.0214	12	01Jul2015, 12:06	0.9
POND E	1.0138	18	01Jul2015, 18:14	17.2
H08	1.0138	14	01Jul2015, 18:14	12.5
H09	0.0000	5	01Jul2015, 18:14	4.7
FH01	0.1344	36	01Jul2015, 12:20	4.5
POND H	0.1344	3	01Jul2015, 15:36	2.4



FUTURE 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
OS01	1.5594	11.0	01Jul2015, 13:24	5.9
DB16	0.0578	12.7	01Jul2015, 12:12	1.3
B10	1.6172	13.2	01Jul2015, 12:12	7.3
B10-B11	1.6172	13.2	01Jul2015, 12:14	7.2
DB17	0.0048	5.7	01Jul2015, 12:02	0.4
B11	1.6220	15.3	01Jul2015, 12:12	7.7
B11-POND C	1.6220	15.2	01Jul2015, 12:20	7.5
DB21	0.0519	1.1	01Jul2015, 12:18	0.3
DB18	0.0346	10.0	01Jul2015, 12:08	0.9
DB19	0.0281	2.8	01Jul2015, 12:14	0.4
DB20	0.0147	3.4	01Jul2015, 12:10	0.3
POND C	1.7513	10.9	01Jul2015, 15:00	6.3
POND C-B16	1.7513	10.9	01Jul2015, 15:06	6.2
DB25	0.0211	7.1	01Jul2015, 12:06	0.6
B16	1.7724	11.3	01Jul2015, 15:06	6.7
B16-B17	1.7724	11.3	01Jul2015, 15:16	6.6
DB26	0.0682	29.4	01Jul2015, 12:10	2.7
B17	1.8406	34.4	01Jul2015, 12:14	9.3
B17-B26	1.8406	34.0	01Jul2015, 12:20	9.1
OS03	0.1984	1.6	01Jul2015, 13:02	0.8
DB01	0.0719	4.7	01Jul2015, 12:12	0.7
B01	0.2703	5.0	01Jul2015, 12:14	1.5
B01-B02	0.2703	5.0	01Jul2015, 12:18	1.5
OS02	0.2219	2.6	01Jul2015, 12:46	1.1
DB02	0.0516	3.4	01Jul2015, 12:08	0.5
B02	0.5438	8.6	01Jul2015, 12:18	3.1
B02-POND A	0.5438	8.6	01Jul2015, 12:22	3.1
OS04	0.1359	0.6	01Jul2015, 13:30	0.4
DB03	0.0703	1.5	01Jul2015, 12:20	0.4
B03	0.2062	1.5	01Jul2015, 12:20	0.8
B03-B04	0.2062	1.5	01Jul2015, 12:36	0.8
DB04	0.0422	1.2	01Jul2015, 12:18	0.3
DB05	0.0384	1.4	01Jul2015, 12:22	0.3
B04	0.2868	3.6	01Jul2015, 12:32	1.4
B04-B05	0.2868	3.6	01Jul2015, 12:34	1.4
DB06	0.0219	8.6	01Jul2015, 12:10	0.8
B05	0.3087	10.3	01Jul2015, 12:12	2.2
B05-POND A	0.3087	10.2	01Jul2015, 12:14	2.1
DB07	0.0254	1.9	01Jul2015, 12:10	0.3
DB08	0.0297	0.5	01Jul2015, 12:16	0.2
POND A	0.9076	1.5	02Jul2015, 00:00	1.1
POND A-B06	0.9076	1.5	02Jul2015, 00:00	1.1
DB09	0.0189	3.7	01Jul2015, 12:06	0.3
B06	0.9265	3.7	01Jul2015, 12:06	1.4
B06-B07	0.9265	3.7	01Jul2015, 12:24	1.4
DB11	0.0969	8.1	01Jul2015, 12:16	1.2
DB10	0.0364	5.8	01Jul2015, 12:10	0.6
B07	1.0598	14.8	01Jul2015, 12:22	3.2
B07-B09	1.0598	14.4	01Jul2015, 12:32	3.2
DB12	0.0453	11.2	01Jul2015, 12:08	1.0



FUTURE 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
B09	1.1051	19.4	01Jul2015, 12:20	4.2
B09-POND B	1.1051	19.3	01Jul2015, 12:22	4.2
DB15	0.1234	3.3	01Jul2015, 12:28	0.9
DB13	0.0703	7.9	01Jul2015, 12:16	1.1
DB14	0.0556	12.4	01Jul2015, 12:10	1.2
POND B	1.3544	29.6	01Jul2015, 12:34	7.3
POND B-B12	1.3544	29.6	01Jul2015, 12:38	7.3
DB22	0.0516	14.1	01Jul2015, 12:10	1.3
DB23	0.0172	13.1	01Jul2015, 12:06	1.0
B12	1.4232	37.5	01Jul2015, 12:28	9.6
B12-B14	1.4232	37.5	01Jul2015, 12:32	9.5
DB24	0.0531	13.2	01Jul2015, 12:08	1.2
B14	1.4763	45.9	01Jul2015, 12:16	10.8
B14-B15	1.4763	45.9	01Jul2015, 12:18	10.7
DB28	0.0741	5.0	01Jul2015, 12:16	0.8
B15	1.5504	50.9	01Jul2015, 12:18	11.6
B15-B26	1.5504	50.8	01Jul2015, 12:30	11.3
DB29	0.1697	6.1	01Jul2015, 12:28	1.5
DB27	0.0508	8.9	01Jul2015, 12:18	1.1
<b>B26</b>	<b>3.6115</b>	<b>89.9</b>	<b>01Jul2015, 12:26</b>	<b>23.0</b>
B26-27	3.6115	89.6	01Jul2015, 12:32	22.7
FB-02	0.0500	9.5	01Jul2015, 12:18	1.2
FB-01	0.0373	8.2	01Jul2015, 12:10	0.8
FB01-B19	0.0373	8.1	01Jul2015, 12:12	0.8
B19	0.0873	16.8	01Jul2015, 12:14	2.0
B19-27	0.0873	16.8	01Jul2015, 12:16	2.0
FB-03	0.0078	5.9	01Jul2015, 12:04	0.4
27	3.7066	101.7	01Jul2015, 12:32	25.1
27-32	3.7066	101.3	01Jul2015, 12:34	25.0
WH-24	0.1325	31.1	01Jul2015, 12:12	3.2
WH-26	0.0839	0.5	01Jul2015, 13:18	0.3
WH-27	0.0217	0.1	01Jul2015, 12:50	0.1
30	0.2381	31.1	01Jul2015, 12:12	3.5
30-31	0.2381	31.1	01Jul2015, 12:14	3.5
WH-28	0.0398	8.1	01Jul2015, 12:14	0.9
31	0.2779	39.2	01Jul2015, 12:14	4.4
31-32	0.2779	38.9	01Jul2015, 12:16	4.4
WH-29	0.0495	10.2	01Jul2015, 12:12	1.1
WH-31	0.0406	11.8	01Jul2015, 12:08	1.1
WH-30	0.0159	1.3	01Jul2015, 12:04	0.1
32	4.0905	131.5	01Jul2015, 12:34	31.7
WH32	0.0458	0.3	01Jul2015, 12:48	0.2
BEN POND	4.1363	45.5	01Jul2015, 13:46	27.3
WH-33	0.0064	1.9	01Jul2015, 12:08	0.2
33	4.1427	45.7	01Jul2015, 13:46	27.5
33-37	4.1427	45.7	01Jul2015, 13:58	27.0
WH35	0.1550	6.4	01Jul2015, 12:16	1.3
WH34	0.0450	7.0	01Jul2015, 12:10	0.8
B34-36	0.0450	6.9	01Jul2015, 12:14	0.8
36	0.2000	13.3	01Jul2015, 12:14	2.0

FUTURE 2-YEAR				
HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q <sub>2</sub> (CFS)	TIME OF PEAK	TOTAL VOLUME Q <sub>2</sub> (AC. FT.)
36-37	0.2000	13.2	01Jul2015, 12:22	2.0
WH36	0.0750	0.6	01Jul2015, 12:52	0.3
<b>37</b>	<b>4.4177</b>	<b>49.0</b>	<b>01Jul2015, 13:54</b>	<b>29.3</b>
FG08A	0.0750	15.3	01Jul2015, 12:10	1.5
FG08A-G05	0.0750	15.2	01Jul2015, 12:14	1.5
FG10	0.0669	3.7	01Jul2015, 12:46	0.9
FG08B	0.0630	11.1	01Jul2015, 12:12	1.3
FG08B-G05	0.0630	11.1	01Jul2015, 12:16	1.2
FG11	0.0625	10.6	01Jul2015, 12:20	1.4
FG09	0.0484	3.6	01Jul2015, 12:20	0.6
FG09-G05	0.0484	3.6	01Jul2015, 12:24	0.6
G05	0.3158	40.7	01Jul2015, 12:16	5.6
FG13	0.0661	1.5	01Jul2015, 12:40	0.5
FG14	0.0331	5.5	01Jul2015, 12:18	0.7
FG12	0.0328	8.5	01Jul2015, 12:12	0.9
POND D	0.4478	4.2	01Jul2015, 18:10	3.7
POND D-G17	0.4478	4.2	01Jul2015, 18:12	3.6
FG15	0.1017	7.9	01Jul2015, 12:26	1.4
G17a	0.1017	7.9	01Jul2015, 12:26	1.4
FG15a	0.0156	4.3	01Jul2015, 12:06	0.4
G17	0.5651	11.0	01Jul2015, 12:26	5.4
G17-G18	0.5651	10.9	01Jul2015, 12:28	5.4
FG16	0.0773	18.0	01Jul2015, 12:08	1.7
G18	0.6424	25.7	01Jul2015, 12:10	7.1
G18-POND E	0.6424	25.6	01Jul2015, 12:12	7.1
FG31	0.0922	18.5	01Jul2015, 12:20	2.4
FG30	0.0400	13.1	01Jul2015, 12:06	1.0
FG30-PONDHS	0.0400	12.9	01Jul2015, 12:16	1.0
POND HS	0.1322	15.5	01Jul2015, 12:40	3.4
FG17a	0.0694	13.1	01Jul2015, 12:10	1.4
FG17a-POND E	0.0694	13.0	01Jul2015, 12:12	1.4
FG18	0.0644	5.0	01Jul2015, 12:30	0.9
FG18-POND E	0.0644	5.0	01Jul2015, 12:32	0.9
FG19	0.0527	14.5	01Jul2015, 12:10	1.4
FG17c	0.0313	0.6	01Jul2015, 12:16	0.2
FG17b	0.0214	6.6	01Jul2015, 12:06	0.6
POND E	1.0138	10.7	01Jul2015, 17:02	10.7
H08	1.0138	7.2	01Jul2015, 17:02	7.2
H09	0.0000	3.4	01Jul2015, 17:02	3.5
FH01	0.1344	17.8	01Jul2015, 12:20	2.5
POND H	0.1344	1.2	01Jul2015, 19:54	1.2





## Appendix B - Detention Pond Information



**STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS**

**Meridian Ranch Existing Detention Pond E- FINAL WINDINGWALK INTERIM GRADED CONDITIONS (TOTAL FLOWS)**

Gieck Basin - El Paso County, Colorado

embankment length =	1860
embankment elev =	6976
spillway length =	200
spillway elevation =	6974.5
100 year storage elev.=	6973.1
100 year storage vol.=	36.9
100 year discharge=	188
5 year storage elev.=	6970.6
5 year storage vol.=	11.2
5 year discharge=	15
WQCV storage elev.=	6968.9
WQCV storage vol.=	1.5
WQCV depth =	1.9
1/2 WQCV storage elev.=	6968.3
1/2 WQCV storage vol.=	0.8

50 year storage elev.=	6972.6
50 year storage vol.=	31.3
50 year discharge=	114
25 year storage elev.=	6972.1
25 year storage vol.=	25.5
25 year discharge=	57
10 year storage elev.=	6971.4
10 year storage vol.=	17.7
10 year discharge=	25
2 year storage elev.=	6969.7
2 year storage vol.=	5.6
2 year discharge=	9

STAGE		STORAGE				TOTAL DISCHARGE												
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)		PIPE		REALIZED CULVERT OUTFLOW	TOTAL FLOW	
		sqft	acre	acft	cumacft			1	2	3	4	Rectangular		1	2			
6967	0	1808	0.04	0.0	0.00	-	-	-	-	-	-	-	-	-	1.4	-	-	-
6967.5	0.5	16136.5	0.37	0.1	0.10	-	-	0.1	-	-	-	-	-	-	13	-	0.1	0.073
6968	1	30465	0.70	0.3	0.37	-	-	0.2	-	-	-	-	-	-	26	-	0.2	0.207
6968.5	1.5	81028.5	1.86	0.6	1.01	-	-	0.4	-	-	-	-	-	-	47	-	0.4	0.380
6969	2	131592	3.02	1.2	2.23	-	-	0.5	-	4.6	-	-	-	-	77	-	5.2	5.153
6969.5	2.5	201294.5	4.62	1.9	4.14	-	-	0.6	-	8.1	-	-	-	-	110	-	8.7	8.697
6970	3	270997	6.22	4.6	6.85	-	-	0.7	-	10.1	-	-	-	-	146	-	10.8	10.775
6970.5	3.5	329360	7.56	3.4	10.30	-	-	0.7	1.0	11.8	-	-	-	-	183	-	13.5	13.496
6970.75	3.75	358540.75	8.23	2.0	12.27	-	-	0.8	2.4	12.5	-	-	-	-	203	-	15.7	15.740
6971	4	387722	8.90	7.6	14.41	-	-	0.8	4.6	13.2	-	-	-	-	218	-	19	18.606
6971.25	4.25	408751	9.38	2.3	16.70	-	-	0.8	7.3	13.9	0.2	-	-	-	236	-	22	22.185
6971.5	4.5	429780	9.87	4.7	19.10	-	-	0.9	10.1	14.5	3.0	-	-	-	252	-	28	28.434
6971.75	4.75	450809	10.35	2.5	21.63	-	-	0.9	12.1	15.1	7.3	-	-	-	266	-	36	35.503
6972	5	471838	10.83	5.2	24.28	-	-	0.9	14.1	15.7	14.2	2.4	-	-	280	-	47	47.331
6972.25	5.25	482595.75	11.08	2.7	27.02	-	-	0.9	15.6	16.3	20.6	15.5	-	-	292	-	69	69.017
6972.5	5.5	493354	11.33	5.5	29.82	-	-	1.0	17.0	16.9	26.5	34.9	-	-	304	-	96	96.174
6973	6	514869	11.82	5.8	35.60	-	-	1.0	19.4	17.9	39.0	86.5	-	-	327	-	164	163.861
6973.25	6.25	518272	11.90	3.0	38.57	-	-	1.1	20.8	18.6	48.7	128.5	-	-	338	-	218	217.633
6973.5	6.5	521675	11.98	5.9	41.55	-	-	1.1	22.1	19.2	55.1	182.5	-	-	349	-	280	280.010
6974	7	528481	12.13	12.0	47.58	-	-	1.2	25.4	20.9	71.8	334.6	-	-	369	-	369	369.370
6976	9	553685	12.71	24.8	72.42	-	1,102	1.3	30.0	23.2	82.8	729.0	-	-	443	-	443	1,545.090

## STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS

### Meridian Ranch Existing Detention Pond E-FINAL WINDINGWALK INTERIM GRADED CONDITIONS (H08)

#### Gieck Basin - El Paso County, Colorado

Data for spillway and embankment:

embankment length =	1860
embankment elev =	6976
spillway length =	200
spillway elevation =	6974
100 year storage elev.=	6973.1
100 year storage vol.=	36.9
100 year discharge=	154
5 year storage elev.=	6970.61
5 year storage vol.=	11.2
5 year discharge=	10
WQCV storage elev.=	6968.9
WQCV storage vol.=	1.5
1/2 WQCV storage elev.=	6968.3
1/2 WQCV storage vol.=	0.8

Data for outlet pipe and grate:

Type	H or V	Dimensions Width (ft.) X Height (ft.)	Dia.(in)	(sqft)		
<b>Rectangular</b>	Orifice 1:	V	0.0345	1.33	Area = 0.046	Invert Elev = 6967.00
<b>Rectangular</b>	Orifice 2:	V	2	1	Area = 2.000	Invert Elev = 6970.20
<b>Circular</b>	Orifice 3:	H		15	Area = 1.227	Invert Elev = 6968.60
<b>Rectangular</b>	Orifice 4:	V	6	0.7	Area = 4.200	Invert Elev = 6971.20

Stand Pipe Dimensions

Rec Grate	11	x	7	Elev = 6971.90
Circ. Grate		dia.		Elev = 6971.90

50 year storage elev.=	6972.6
50 year discharge=	95
25 year storage elev.=	6972.1
25 year discharge=	46
10 year storage elev.=	6971.4
10 year discharge=	19
2 year storage elev.=	6969.7
2 year discharge=	6

Outlet Culvert Dimensions

Outlet Culvert	Width (ft.)	Height (ft.)	Dia. (ft.)	Type
	x		3.5	<b>Circular</b>
Area	9.6	TOP		
Outlet I. E.	6966.8	6970.58		
Wall Thick.	4	in.		

STAGE		STORAGE				DISCHARGE										REALIZED CULVERT OUTFLOW	TOTAL FLOW
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)		PIPE			
		sqft	acre	acft	cum acft			1	2	3	4	<b>Rectangular</b>		1	2		
6967	0	1808	0.04	0.0	0.0			-	-	-	-	-	-	1		-	-
6967.5	0.5	16136.5	0.37	0.1	0.10			0.0	-	-	-	-	-	8		0.0	0.0
6968	1	30465	0.70	0.3	0.37			0.1	-	-	-	-	-	18		0.1	0.1
6968.5	1.5	81028.5	1.86	0.6	1.01			0.2	-	-	-	-	-	30		0.2	0.2
6969	2	131592	3.02	1.2	2.23			0.3	-	3.0	-	-	-	52		3.2	3.2
6969.5	2.5	201294.5	4.62	1.9	4.14			0.3	-	5.6	-	-	-	75		5.9	5.9
6970	3	270997	6.22	4.6	6.85			0.3	-	7.0	-	-	-	97		7.3	7.3
6970.5	3.5	329360	7.56	3.4	10.30			0.4	1.0	8.1	-	-	-	122		9.5	9.5
6970.75	3.75	358540.75	8.23	2.0	12.27			0.4	2.4	8.7	-	-	-	135		11.5	11.5
6971	4	387722	8.90	7.6	14.41			0.4	4.3	9.2	-	-	-	146		14	13.9
6971.25	4.25	408751	9.38	2.3	16.70			0.4	6.5	9.6	0.2	-	-	157		17	16.70
6971.5	4.5	429780	9.87	4.7	19.10			0.4	8.6	10.1	3.0	-	-	167		22	22.07
6971.75	4.75	450809	10.35	2.5	21.63			0.4	9.9	10.5	7.3	-	-	176		28	28.14
6972	5	471838	10.83	5.2	24.28			0.5	11.0	10.9	12.9	2	-	185		38	37.59
6972.25	5.25	482595.75	11.08	2.7	27.02			0.5	12.0	11.3	16.9	16	-	193		56	56.20
6972.5	5.5	493354	11.33	5.5	29.82			0.5	12.9	11.7	19.7	35	-	201		80	79.64
6973	6	514869	11.82	5.8	35.60			0.5	14.6	12.4	24.4	87	-	217		138	138.39
6973.25	6.25	518272	11.90	3.0	38.57			0.5	15.4	12.7	26.4	118	-	224		173	172.65
6973.5	6.5	521675	11.98	5.9	41.55			0.5	16.1	13.1	28.2	152	-	231		210	209.76
6974	7	528481	12.13	12.0	47.58			0.6	17.5	13.7	31.7	228	-	244		244	244.06
6976	9	553685	12.71	24.8	72.42			0.6	22.2	16.1	42.7	623	-	291		291	291.42



## STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS

### Meridian Ranch Existing Detention Pond E-FINAL WINDINGWALK INTERIM GRADED CONDITIONS (H09)

#### Gieck Basin - El Paso County, Colorado

Data for spillway and embankment:

embankment length =	1860
embankment elev =	6976
spillway length =	200
spillway elevation =	6974.5
100 year storage elev.=	6973.1
100 year storage vol.=	36.9
100 year discharge=	34
5 year storage elev.=	6970.61
5 year storage vol.=	11.2
5 year discharge=	4
WQCV storage elev.=	6968.9
WQCV storage vol.=	1.5
1/2 WQCV storage elev.=	6968.3
1/2 WQCV storage vol.=	0.8

Data for outlet pipe and grate:

Type	H or V	Dimensions Width (ft.) X Height (ft.)		Dia.(in)	(sqft)		
<b>Rectangular</b>	Orifice 1:	V	0.0345	1.33	Area =	0.046	Invert Elev = 6967.00
<b>Rectangular</b>	Orifice 2:	V	0.75	1	Area =	0.750	Invert Elev = 6970.75
<b>Circular</b>	Orifice 3:	H		10	Area =	0.545	Invert Elev = 6968.60
<b>Rectangular</b>	Orifice 4:	V	3.5	1.25	Area =	4.375	Invert Elev = 6971.75

Stand Pipe Dimensions

Rec Grate	4.25	x	3	Elev =	6973.00
Circ. Grate		dia.		Elev =	6973.00

50 year storage elev.=	6972.63
50 year discharge=	19
25 year storage elev.=	6972.11
25 year discharge=	11
10 year storage elev.=	6971.36
10 year discharge=	6
2 year storage elev.=	6969.72
2 year discharge=	3

Outlet Culvert Dimensions

Outlet Culvert	Width (ft.)	H or V	Height (ft.)	Dia. (ft.)	Type
Outlet Culvert	9.6	x	3.5	3.5	<b>Circular</b>
Area	9.6		TOP		
Outlet I. E.	6966.8		6970.7		
Wall Thick.	5	in.			

STAGE		STORAGE		DISCHARGE												REALIZED CULVERT OUTFLOW	TOTAL FLOW	
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)		PIPE				
		sqft	acre	acft	cum acft			1	2	3	4	<b>Rectangular</b>		1	2			
6967	0	1808	0.04	0.0	0.0			-	-	-	-	-	-	-	0.5		-	-
6967.5	0.5	16136.5	0.37	0.1	0.10			0.0	-	-	-	-	-	-	5.0		0.0	0.0
6968	1	30465	0.70	0.3	0.37			0.1	-	-	-	-	-	-	8.8		0.1	0.1
6968.5	1.5	81028.5	1.86	0.6	1.01			0.2	-	-	-	-	-	-	17		0.2	0.2
6969	2	131592	3.02	1.2	2.23			0.3	-	-	1.7	-	-	-	26		1.9	1.9
6969.5	2.5	201294.5	4.62	1.9	4.14			0.3	-	-	2.5	-	-	-	35		2.8	2.8
6970	3	270997	6.22	4.6	6.85			0.3	-	-	3.1	-	-	-	48		3.4	3.4
6970.5	3.5	329360	7.56	3.4	10.30			0.4	-	-	3.6	-	-	-	61		4.0	4.0
6970.75	3.75	358540.75	8.23	2.0	12.27			0.4	-	-	3.9	-	-	-	68		4.2	4.2
6971	4	387722	8.90	7.6	14.41			0.4	0.3	-	4.1	-	-	-	73		4.8	4.8
6971.25	4.25	408751	9.38	2.3	16.70			0.4	0.8	-	4.3	-	-	-	79		5.5	5.49
6971.5	4.5	429780	9.87	4.7	19.10			0.4	1.5	-	4.5	-	-	-	85		6.4	6.37
6971.75	4.75	450809	10.35	2.5	21.63			0.4	2.3	-	4.7	-	-	-	90		7.4	7.36
6972	5	471838	10.83	5.2	24.28			0.5	3.1	-	4.8	-	-	-	95		9.7	9.74
6972.25	5.25	482595.75	11.08	2.7	27.02			0.5	3.6	-	5.0	-	-	-	99		12.8	12.82
6972.5	5.5	493354	11.33	5.5	29.82			0.5	4.0	-	5.2	-	-	-	103		16.5	16.53
6973	6	514869	11.82	5.8	35.60			0.5	4.8	-	5.5	-	-	-	111		25.5	25.47
6973.25	6.25	518272	11.90	3.0	38.57			0.5	5.4	-	5.8	-	-	-	114	11	45.0	44.98
6973.5	6.5	521675	11.98	5.9	41.55			0.6	6.0	-	6.1	-	-	-	118	31	70.3	70.25
6974	7	528481	12.13	12.0	47.58			0.6	7.9	-	7.1	-	-	-	125	106	125.3	125.31
6976	9	553685	12.71	24.8	72.42			0.6	7.9	-	7.1	-	-	-	151	106	151.4	151.40

**STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS**

**Meridian Ranch Proposed Detention Pond H-INTERIM  
Gieck Basin - El Paso County, Colorado**

Data for spillway and embankment:

embankment length =	500
embankment elev =	6976
spillway length =	50
spillway elevation =	6974.5
100 year storage elev.=	6972.8
100 year storage vol.=	5.7
100 year discharge=	23
5 year storage elev.=	6970.98
5 year storage vol.=	1.3
5 year discharge=	1.1
WQCV storage elev.=	6971.0
WQCV storage vol.=	0.5
1/2 WQCV storage elev.=	6970.3
1/2 WQCV storage vol.=	0.25

Data for outlet pipe and grate:

Type	Orifice	H or V	Dimensions		Area (sqft)	Invert Elev
			Width (ft.)	Height (ft.)		
Rectangular	Orifice 1:	V	0.0195	1.33	0.026	6968.50
Rectangular	Orifice 2:	V	4.5000	1.40	6.300	6971.50
None Selected	Orifice 3:	H			0.000	
Circular	Orifice 4:	H			0.196	6970.00

Stand Pipe Dimensions	
Rec Grate	9 x 4.5 Elev = 6972.90
Circ. Grate	dia. Elev = 6972.90

Outlet Culvert Dimensions	
Outlet Culvert	9.6 x 3.5 Circular
Area	TOP 6968.5
Outlet I. E.	6972.38
Wall Thick.	4.5 in.

50 year storage elev.=	6972.4
50 year discharge=	13
25 year storage elev.=	6972.0
25 year discharge=	6.4
10 year storage elev.=	6972.9
10 year discharge=	2.0
2 year storage elev.=	6970.4
2 year discharge=	0.7

STAGE		STORAGE				DISCHARGE											
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)		PIPE		REALIZED CULVERT OUTFLOW	TOTAL FLOW
		sqft	acre	acft	cumacft			1	2	3	4	Rectangular		1	2		
6968.5	0	0	0.00	0.0	0.000	-	-	-	-	-	-	-	-	-	-	-	-
6969	0.5	477	0.01	0.00	0.003	-	-	0.02	-	-	-	-	-	-	1	0.02	0.021
6969.5	1	11450	0.26	0.07	0.07	-	-	0.06	-	-	-	-	-	-	5	0.06	0.059
6970	1.5	22422	0.51	0.19	0.27	-	-	0.11	-	-	-	-	-	-	10	0.11	0.107
6970.25	1.75	33514	0.77	0.16	0.43	-	-	0.13	-	-	0.5	-	-	-	14	0.60	0.603
6970.5	2	44606	1.02	0.22	0.65	-	-	0.14	-	-	0.7	-	-	-	18	0.81	0.813
6971	2.5	67898	1.56	0.65	1.30	-	-	0.17	-	-	0.9	-	-	-	27	1.11	1.115
6971.5	3	92319	2.12	0.92	2.22	-	-	0.19	-	-	1.2	-	-	-	36	1.35	1.349
6971.75	3.25	104529	2.40	0.56	2.78	-	-	0.20	1.7	-	1.3	-	-	-	42	3.14	3.139
6972	3.5	116739	2.68	1.20	3.42	-	-	0.21	4.8	-	1.3	-	-	-	41	6.32	6.321
6972.5	4	125636	2.88	1.39	4.81	-	-	0.23	13.5	-	1.5	-	-	-	50	15.2	15.223
6973	4.5	134533	3.09	1.49	6.30	-	-	0.25	24.8	-	1.6	2	-	-	56	28.4	28.391
6973.5	5	141972	3.26	1.59	7.89	-	-	0.26	34.6	-	1.8	25	-	-	61	61	61.340
6974	5.5	149410	3.43	1.67	9.56	-	-	0.28	40.7	-	1.9	62	-	-	66	66	66.260
6975	6.5	165140	3.79	3.61	13.17	53.0	53.0	0.30	50.8	-	2.1	164	-	-	75	75	128.173
6976	7.5	192114	4.41	4.10	17.27	275.6	275.6	0.33	59.1	-	2.3	295	-	-	83	83	358.648

Notes: 1) Top-of-bank and spillway flows are weir equations from section 11.3.1 in the DCM.  $Q=CLH^{1.5}$  (C=3.0)

**STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS**

**Meridian Ranch Existing Detention Pond E- FINAL FUTURE (TOTAL FLOWS)**

Gieck Basin - El Paso County, Colorado

embankment length =	1860
embankment elev =	6976
spillway length =	200
spillway elevation =	6974.5
100 year storage elev.=	6973.5
100 year storage vol.=	41.3
100 year discharge=	242
5 year storage elev.=	6971.0
5 year storage vol.=	14.3
5 year discharge=	18
WQCV storage elev.=	6968.9
WQCV storage vol.=	1.5
WQCV depth =	1.9
1/2 WQCV storage elev.=	6968.3
1/2 WQCV storage vol.=	0.8

50 year storage elev.=	6973.0
50 year storage vol.=	35.3
50 year discharge=	151
25 year storage elev.=	6972.4
25 year storage vol.=	28.9
25 year discharge=	82
10 year storage elev.=	6971.6
10 year storage vol.=	20.3
10 year discharge=	32
2 year storage elev.=	6970.0
2 year storage vol.=	6.8
2 year discharge=	11

STAGE		STORAGE				TOTAL DISCHARGE												
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)		PIPE		REALIZED CULVERT OUTFLOW	TOTAL FLOW	
		sqft	acre	acft	cum acft			1	2	3	4	Rectangular		1	2			
6967	0	1808	0.04	0.0	0.00	-	-	-	-	-	-	-	-	-	1.4	-	-	-
6967.5	0.5	16136.5	0.37	0.1	0.10	-	-	0.1	-	-	-	-	-	-	13	-	0.1	0.073
6968	1	30465	0.70	0.3	0.37	-	-	0.2	-	-	-	-	-	-	26	-	0.2	0.207
6968.5	1.5	81028.5	1.86	0.6	1.01	-	-	0.4	-	-	-	-	-	-	47	-	0.4	0.380
6969	2	131592	3.02	1.2	2.23	-	-	0.5	-	4.6	-	-	-	-	77	-	5.2	5.153
6969.5	2.5	201294.5	4.62	1.9	4.14	-	-	0.6	-	8.1	-	-	-	-	110	-	9	8.697
6970	3	270997	6.22	4.6	6.85	-	-	0.7	-	10.1	-	-	-	-	146	-	11	10.775
6970.5	3.5	329360	7.56	3.4	10.30	-	-	0.7	1.0	11.8	-	-	-	-	183	-	13	13.496
6970.75	3.75	358540.75	8.23	2.0	12.27	-	-	0.8	2.4	12.5	-	-	-	-	203	-	16	15.740
6971	4	387722	8.90	7.6	14.41	-	-	0.8	4.6	13.2	-	-	-	-	218	-	19	18.606
6971.25	4.25	408751	9.38	2.3	16.70	-	-	0.8	7.3	13.9	0.2	-	-	-	236	-	22	22.185
6971.5	4.5	429780	9.87	4.7	19.10	-	-	0.9	10.1	14.5	3.0	-	-	-	252	-	28	28.434
6971.75	4.75	450809	10.35	2.5	21.63	-	-	0.9	12.1	15.1	7.3	-	-	-	266	-	36	35.503
6972	5	471838	10.83	5.2	24.28	-	-	0.9	14.1	15.7	12.9	2.4	-	-	280	-	46	46.019
6972.25	5.25	482595.75	11.08	2.7	27.02	-	-	0.9	15.6	16.3	16.9	15.5	-	-	292	-	65	65.304
6972.5	5.5	493354	11.33	5.5	29.82	-	-	1.0	17.0	16.9	20.2	34.9	-	-	304	-	90	89.819
6973	6	514869	11.82	5.8	35.60	-	-	1.0	19.4	17.9	29.5	86.5	-	-	327	-	154	154.375
6973.25	6.25	518272	11.90	3.0	38.57	-	-	1.0	20.5	18.4	35.0	121.5	-	-	338	-	196	196.384
6973.5	6.5	521675	11.98	5.9	41.55	-	-	1.1	21.5	18.9	40.8	162.7	-	-	349	-	245	244.924
6974	7	528481	12.13	12.0	47.58	-	-	1.1	23.5	19.8	53.4	259.0	-	-	369	-	309	309.209
6976	9	553685	12.71	24.8	72.42	-	1,102	1.3	30.0	23.2	82.8	729.0	-	-	443	-	443	1,545.090

## STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS

### Meridian Ranch Existing Detention Pond E-FINAL FUTURE (H08)

#### Gieck Basin - El Paso County, Colorado

Data for spillway and embankment:

embankment length =	1860
embankment elev =	6976
spillway length =	200
spillway elevation =	6974
100 year storage elev.=	6973.5
100 year storage vol.=	41.3
100 year discharge=	207
5 year storage elev.=	6970.98
5 year storage vol.=	14.3
5 year discharge=	14
WQCV storage elev.=	6968.9
WQCV storage vol.=	1.5
1/2 WQCV storage elev.=	6968.3
1/2 WQCV storage vol.=	0.8

Data for outlet pipe and grate:

Type	H or V	Dimensions Width (ft.) X Height (ft.)		Dia.(in)	(sqft)
<b>Rectangular</b>	Orifice 1:	V	0.0345	1.33	Area = 0.046
<b>Rectangular</b>	Orifice 2:	V	2	1	Area = 2.000
<b>Circular</b>	Orifice 3:	H		15	Area = 1.227
<b>Rectangular</b>	Orifice 4:	V	6	0.7	Area = 4.200

Stand Pipe Dimensions

Rec Grate	11	x	7	Elev = 6971.90
Circ. Grate		dia.		Elev = 6971.90

50 year storage elev.=	6973.0
50 year discharge=	135
25 year storage elev.=	6972.4
25 year discharge=	72
10 year storage elev.=	6971.6
10 year discharge=	25
2 year storage elev.=	6970.0
2 year discharge=	7

Outlet Culvert Dimensions

	Width (ft.)		Height (ft.)	Dia. (ft.)	Type
Outlet Culvert		x		3.5	<b>Circular</b>
Area	9.6		TOP		
Outlet I. E.	6966.8		6970.58		
Wall Thick.	4	in.			

STAGE		STORAGE				DISCHARGE								REALIZED CULVERT OUTFLOW	TOTAL FLOW		
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow) <b>Rectangular</b>	PIPE				
		sqft	acre	acft	cum acft			1	2	3	4		1			2	
6967	0	1808	0.04	0.0	0.0			-	-	-	-	-	-	1		-	-
6967.5	0.5	16136.5	0.37	0.1	0.1			0.0	-	0.1	-	-	-	8		0.0	0.04
6968	1	30465	0.70	0.3	0.4			0.1	-	-	-	-	-	18		0.1	0.10
6968.5	1.5	81028.5	1.86	0.6	1.0			0.2	-	-	-	-	-	30		0.2	0.19
6969	2	131592	3.02	1.2	2.2			0.3	-	3.0	-	-	-	52		3.2	3.24
6969.5	2.5	201294.5	4.62	1.9	4.1			0.3	-	5.6	-	-	-	75		5.9	5.91
6970	3	270997	6.22	4.6	6.9			0.3	-	7.0	-	-	-	97		7.3	7.33
6970.5	3.5	329359.5	7.56	3.4	10			0.4	1.0	8.1	-	-	-	122		9.5	9.50
6970.75	3.75	358540.75	8.23	2.0	12.3			0.4	2.4	8.7	-	-	-	135		12	11.50
6971	4	387722	8.90	7.6	14			0.4	4.3	9.2	-	-	-	146		14	13.85
6971.25	4.25	408751	9.38	2.3	17			0.4	6.5	9.6	0.2	-	-	157		17	16.70
6971.5	4.5	429780	9.87	4.7	19			0.4	8.6	10.1	3.0	-	-	167		22	22.07
6971.75	4.75	450809	10.35	2.5	22			0.4	9.9	10.5	7.3	-	-	176		28	28.14
6972	5	471838	10.83	5.2	24			0.5	11.0	10.9	12.9	2	-	185		38	37.59
6972.25	5.25	482595.75	11.08	2.7	27			0.5	12.0	11.3	16.9	16	-	193		56	56.20
6972.5	5.5	493354	11.33	5.5	30			0.5	12.9	11.7	19.7	35	-	201		80	79.64
6973	6	514869	11.82	5.8	36			0.5	14.6	12.4	24.4	87	-	217		138	138.39
6973.25	6.25	518272	11.90	3.0	39			0.5	15.4	12.7	26.4	118	-	224		173	172.65
6973.5	6.5	521675	11.98	5.9	42			0.5	16.1	13.1	28.2	152	-	231		210	209.76
6974	7	528481	12.13	12.0	48			0.6	17.5	13.7	31.7	228	-	244		244	244.06
6976	9	553685	12.71	24.8	72			0.6	22.2	16.1	42.7	623	-	291		291	291.42

## STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS

### Meridian Ranch Existing Detention Pond E-FINAL FUTURE (H09)

#### Gieck Basin - El Paso County, Colorado

Data for spillway and embankment:

embankment length =	1860
embankment elev =	6976
spillway length =	200
spillway elevation =	6974.5
100 year storage elev.=	6973.5
100 year storage vol.=	41.3
100 year discharge=	34
5 year storage elev.=	6970.98
5 year storage vol.=	14.3
5 year discharge=	4.7
WQCV storage elev.=	6968.9
WQCV storage vol.=	1.5
1/2 WQCV storage elev.=	6968.3
1/2 WQCV storage vol.=	0.8

Data for outlet pipe and grate:

		Dimensions						
Type	H or V	Width (ft.)	Height (ft.)	Dia.(in)	(sqft)			
<b>Rectangular</b>	Orifice 1:	V	0.0345	1.33	Area =	0.046	Invert Elev =	6967.00
<b>Rectangular</b>	Orifice 2:	V	0.75	1	Area =	0.750	Invert Elev =	6970.75
<b>Circular</b>	Orifice 3:	H		10	Area =	0.545	Invert Elev =	6968.60
<b>Rectangular</b>	Orifice 4:	V	3.5	1.25	Area =	4.375	Invert Elev =	6971.75
Stand Pipe Dimensions								
Rec Grate		4.25	x	3	Elev =	6973.00		
Circ. Grate			dia.		Elev =	6973.00		
Outlet Culvert Dimensions								
		Width (ft.)		Height (ft.)		Dia. (ft.)	Type	
Outlet Culvert			x			3.5	<b>Circular</b>	
Area		9.6		TOP				
Outlet I. E.		6966.8		6970.7				
Wall Thick.		5	in.					

50 year storage elev.=	6972.97
50 year discharge=	16
25 year storage elev.=	6972.42
25 year discharge=	10
10 year storage elev.=	6971.62
10 year discharge=	7
2 year storage elev.=	6969.99
2 year discharge=	3.4

STAGE		STORAGE				DISCHARGE										REALIZED CULVERT OUTFLOW	TOTAL FLOW	
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)		PIPE				
		sqft	acre	acft	cum acft			1	2	3	4	<b>Rectangular</b>		1	2			
6967	0	1808	0.04	0.0	0.0			-	-	-	-	-	-	-	0.5		-	-
6967.5	0.5	16136.5	0.37	0.1	0.37			0.0	-	-	-	-	-	-	5.0		0.0	0.04
6968	1	30465	0.70	0.3	0.4			0.1	-	-	-	-	-	-	8.8		0.1	0.10
6968.5	1.5	81028.5	1.86	0.6	1.0			0.2	-	-	-	-	-	-	17.0		0.2	0.19
6969	2	131592	3.02	1.2	2.2			0.3	-	-	1.7	-	-	-	25.8		1.9	1.92
6969.5	2.5	201294.5	4.62	1.9	4.1			0.3	-	-	2.5	-	-	-	35.0		2.8	2.79
6970	3	270997	6.22	4.6	6.9			0.3	-	-	3.1	-	-	-	48.4		3.4	3.45
6970.5	3.5	329359.5	7.56	3.4	10.3			0.4	-	-	3.6	-	-	-	60.7		4.0	3.99
6970.75	3.75	358540.75	8.23	2.0	12.3			0.4	-	-	3.9	-	-	-	68.0		4.2	4.24
6971	4	387722	8.90	7.6	14.4			0.4	0.3	-	4.1	-	-	-	72.6		4.8	4.75
6971.25	4.25	408751	9.38	2.3	16.7			0.4	0.8	-	4.3	-	-	-	78.9		5.5	5.49
6971.5	4.5	429780	9.87	4.7	19.1			0.4	1.5	-	4.5	-	-	-	84.7		6.4	6.37
6971.75	4.75	450809	10.35	2.5	21.6			0.4	2.3	-	4.7	-	-	-	90.1		7.4	7.36
6972	5	471838	10.83	5.2	24.3			0.5	3.1	-	4.8	-	-	-	94.8		8.4	8.43
6972.25	5.25	482595.75	11.08	2.7	27.0			0.5	3.6	-	5.0	-	-	-	98.7		9.1	9.10
6972.5	5.5	493354	11.33	5.5	29.8			0.5	4.0	-	5.2	0.5	-	-	102.7		10.2	10.17
6973	6	514869	11.82	5.8	35.6			0.5	4.8	-	5.5	5.2	-	-	110.5		16.0	15.99
6973.25	6.25	518272	11.90	3.0	38.6			0.5	5.1	-	5.7	8.6	4	-	114.3		23.7	23.73
6973.5	6.5	521675	11.98	5.9	41.6			0.5	5.4	-	5.8	12.5	11	-	118.1		35.2	35.17
6974	7	528481	12.13	12.0	47.6			0.6	6.0	-	6.1	21.8	31	-	125.3		65.1	65.15
6976	9	553685	12.71	24.8	72.4			0.6	7.9	-	7.1	40.1	106	-	151.4		151.4	151.40

## STAGE/STORAGE/DISCHARGE CURVES FOR DETENTION POND ANALYSIS

### Meridian Ranch Proposed Detention Pond H-FUTURE

#### Gieck Basin - El Paso County, Colorado

Data for spillway and embankment:

embankment length =	500
embankment elev =	6976
spillway length =	50
spillway elevation =	6974.5
100 year storage elev.=	6973.4
100 year storage vol.=	7.7
100 year discharge=	58
5 year storage elev.=	6971.7
5 year storage vol.=	2.6
5 year discharge=	3.0
WQCV storage elev.=	6970.3
WQCV storage vol.=	0.5
1/2 WQCV storage elev.=	6969.9
1/2 WQCV storage vol.=	0.25

Data for outlet pipe and grate:

Type	H or V	Dimensions		Dia.(in)	(sqft)	Bottom	
		Width (ft.)	X Height (ft.)				
Rectangular	Orifice 1: V	0.0195	1.33		Area = 0.026	Invert Elev =	6968.5
Rectangular	Orifice 2: V	4.5000	1.40		Area = 6.300	Invert Elev =	6971.50
None Selected	Orifice 3: V				Area = 0.000	Invert Elev =	
Circular	Orifice 4: H			6	Area = 0.196	Invert Elev =	6970

Stand Pipe Dimensions

Rec Grate	9	x	4.5	Elev =	6972.90
Circ. Grate		dia.		Elev =	6972.90

50 year storage elev.=	6973.1
50 year discharge=	32
25 year storage elev.=	6972.6
25 year discharge=	18
10 year storage elev.=	6972.1
10 year discharge=	8
2 year storage elev.=	6971.1
2 year discharge=	1.2

Outlet Culvert Dimensions

	Width (ft.)		Height (ft.)	Dia. (ft.)	Type
Outlet Culvert		x		3.5	Circular
Area	9.6		TOP		
Outlet I. E.	6968.5		6972.38		
Wall Thick.	4.5		in.		

STAGE		STORAGE				DISCHARGE								REALIZED CULVERT OUTFLOW		TOTAL FLOW
ELEV	HEIGHT	AREA		VOLUME		TOP OF BANK	SPILLWAY	ORIFICE (max outflow)				GRATE (max outflow)	PIPE		REALIZED CULVERT OUTFLOW	TOTAL FLOW
		sqft	acre	acft	cum acft			1	2	3	4		1	2		
6968.5	0	0	0.00	0.0	0.0	-	-	-	-	-	-	-	-	-	-	-
6969	0.5	477	0.01	0.00	0.003	-	-	0.02	-	-	-	-	-	1		0.02
6969.5	1	11450	0.26	0.07	0.07	-	-	0.06	-	-	-	-	-	5		0.06
6970	1.5	22422	0.51	0.26	0.27	-	-	0.11	-	-	-	-	-	10		0.107
6970.25	1.75	33514	0.77	0.16	0.43	-	-	0.13	-	-	0.5	-	-	14		0.603
6970.5	2	44606	1.02	0.78	0.78	-	-	0.14	-	-	0.7	-	-	18		0.813
6971	2.5	67898	1.56	1.04	1.30	-	-	0.17	-	-	0.9	-	-	27		1.115
6971.5	3	92319	2.12	0.92	2.22	-	-	0.19	-	-	1.2	-	-	36		1.349
6971.75	3.25	104529	2.40	0.56	2.79	-	-	0.20	1.7	-	1.3	-	-	42		3.139
6972	3.5	116739	2.68	1.20	3.42	-	-	0.21	4.8	-	1.3	-	-	47		6.321
6972.5	4	125636	2.88	1.39	4.81	-	-	0.23	13.5	-	1.5	-	-	58		15.223
6973	4.5	134533	3.09	1.49	6.31	-	-	0.25	24.8	-	1.6	-	-	70		28.391
6973.5	5	141972	3.26	1.59	7.89	-	-	0.26	34.6	-	1.8	25	-	79		61.713
6974	5.5	149410	3.43	1.67	9.57	-	-	0.28	40.7	-	1.9	62	-	86		85.780
6975	6.5	165140	3.79	3.61	13.18	53.0	53.0	0.30	50.8	-	2.1	164	-	98		151.443
6976	7.5	192114	4.41	4.10	17.28	275.6	275.6	0.33	59.1	-	2.3	295	-	110		385.158

Notes: 1) Top-of-bank and spillway flows are weir equations from section 11.3.1 in the DCM.  $Q=CLH^{1.5}$  (C=3.0)

## FUTURE POND E

### WQCV Control Riser Calculations

TRIBUTARY AREA	290	acres
DRAIN TIME	40	hr
<i>a</i>	1	
IMPERVIOUSNESS RATIO	0.36	<i>i</i>
DEPTH OF OUTLET	1.6	
WQCV	0.17	inches
WQCV DESIGN VOL	1.5	ac-ft
$K_{40}$	0.29	
AREA PER ROW <sup>1</sup>	1.30	in <sup>2</sup>
No. of columns	3	per riser
Hole size	3/4	in
Steel Plate Thickness	3/8	in
	5	rows of holes per riser
<sup>1</sup> AREA PER ROW PER RISER		
Actual area per row per riser:	1.33	in <sup>2</sup>
Actual area per riser:	6.7	in <sup>2</sup>
Actual area per riser:	0.046	ft <sup>2</sup>

TABLE SB-2							
Hole Dia (in)		Area per Row (in <sup>2</sup> )					
Holes per Row		1	2	3	4	5	6
Min steel thickness		1/4	5/16	3/8	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
1/2	0.5000	0.20	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
7/8	0.8750	0.60	1.20	1.80	2.41	3.01	3.61
1	1.0000	0.79	1.57	2.36	3.14	3.93	4.71
1 1/8	1.1250	0.99	1.99	2.98	3.98	4.97	5.96
1 1/4	1.2500	1.23	2.45	3.68	4.91	6.14	7.36
1 3/8	1.3750	1.48	2.97	4.45	5.94	7.42	8.91
1 1/2	1.5000	1.77	3.53	5.30	7.07	8.84	10.60
1 5/8	1.6250	2.07	4.15	6.22	8.30	10.37	12.44
1 3/4	1.7500	2.41	4.81	7.22	9.62	12.03	14.43
1 7/8	1.8750	2.76	5.52	8.28	11.04	13.81	16.57
2	2.0000	3.14	6.28	9.42	12.57	15.71	18.85
n = Number of columns of perforations							

## FUTURE POND H

### WQCV Control Riser Calculations

TRIBUTARY AREA	86	acres
DRAIN TIME	40	hr
	<i>a</i>	1
IMPERVIOUSNESS RATIO	<i>i</i>	0.38
DEPTH OF OUTLET	1.8	
WQCV	0.17 inches	
WQCV DESIGN VOL	0.5 ac-ft	
	$K_{40}$	0.34
AREA PER ROW <sup>1</sup>	<i>a</i>	0.69 in <sup>2</sup>
No. of holes	2	per row
Hole size	1 1/16 in	
Steel Plate Thickness	5/16 in	
	5 rows of holes per riser	
<sup>1</sup> AREA PER ROW PER RISER		
Actual area per row per riser:	0.74 in <sup>2</sup>	
Actual area per riser:	3.7 in <sup>2</sup>	
Actual area per riser:	0.026 ft <sup>2</sup>	

Hole Dia (in)		Area per Row (in <sup>2</sup> )					
Holes per Row		1	2	3	4	5	6
Min steel thickness		1/4	5/16	3/8	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
1/2	0.5000	0.20	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
7/8	0.8750	0.60	1.20	1.80	2.41	3.01	3.61
1	1.0000	0.79	1.57	2.36	3.14	3.93	4.71
1 1/8	1.1250	0.99	1.99	2.98	3.98	4.97	5.96
1 1/4	1.2500	1.23	2.45	3.68	4.91	6.14	7.36
1 3/8	1.3750	1.48	2.97	4.45	5.94	7.42	8.91
1 1/2	1.5000	1.77	3.53	5.30	7.07	8.84	10.60
1 5/8	1.6250	2.07	4.15	6.22	8.30	10.37	12.44
1 3/4	1.7500	2.41	4.81	7.22	9.62	12.03	14.43
1 7/8	1.8750	2.76	5.52	8.28	11.04	13.81	16.57
2	2.0000	3.14	6.28	9.42	12.57	15.71	18.85

n = Number of columns of perforations



**WINDINGWALK INTERIM CONDITION**  
**Simulation Run: WWG-100 YR Reservoir: POND E**

Start of Run: 01Jul2015, 00:00      Basin Model: WW Grading  
End of Run: 02Jul2015, 00:00      Meteorologic Model: SCS TYPE IIA 100YR  
Compute Time: 05Sep2017 13:11:34      Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 508 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 06:14
Peak Outflow: 188(CFS)	Date/Time of Peak Outflow: 01Jul2015, 06:58
Total Inflow : 109.8 (AC-FT)	Peak Storage: 38.0 (AC-FT)
Total Outflow: 87.7 (AC-FT)	Peak Elevation: 6973.2 (FT)

**Simulation Run: WWG-005 YR Reservoir: POND E**

Start of Run: 01Jul2015, 00:00      Basin Model: WW Grading  
End of Run: 02Jul2015, 00:00      Meteorologic Model: SCS TYPE IIA 005YR  
Compute Time: 05Sep2017 13:11:34      Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 113 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 06:14
Peak Outflow: 15(CFS)	Date/Time of Peak Outflow: 01Jul2015, 08:10
Total Inflow : 22.9 (AC-FT)	Peak Storage: 11.2 (AC-FT)
Total Outflow: 14.0 (AC-FT)	Peak Elevation: 6970.6 (FT)

**Simulation Run: WWG-100 YR Reservoir: POND H**

Start of Run: 01Jul2015, 00:00      Basin Model: WW Grading  
End of Run: 02Jul2015, 00:00      Meteorologic Model: SCS TYPE IIA 100YR  
Compute Time: 05Sep2017 13:11:34      Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 90(CFS)	Date/Time of Peak Inflow: 01Jul2015, 06:12
Peak Outflow: 23 (CFS)	Date/Time of Peak Outflow: 01Jul2015, 07:24
Total Inflow : 12.6 (AC-FT)	Peak Storage: 5.7 (AC-FT)
Total Outflow: 9.9 (AC-FT)	Peak Elevation: 6972.8 (FT)

**Simulation Run: WWG-005 YR Reservoir: POND H**

Start of Run: 01Jul2015, 00:00 Basin Model: WW Grading  
End of Run: 02Jul2015, 00:00 Meteorologic Model: SCS TYPE IIA 005YR  
Compute Time: 11Sep2017 13:11:34 Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 10 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 06:14
Peak Outflow: 1 (CFS)	Date/Time of Peak Outflow: 01Jul2015, 08:24
Total Inflow : 2.2 (AC-FT)	Peak Storage: 1.4 (AC-FT)
Total Outflow: 1.3 (AC-FT)	Peak Elevation: 6971.1 (FT)

**WINDINGWALK FUTURE CONDITION**

**Simulation Run: F-100 YR Reservoir: POND E**

Start of Run: 01Jul2015, 00:00 Basin Model: Future SCS  
End of Run: 02Jul2015, 00:00 Meteorologic Model: SCS TYPE IIA 100YR  
Compute Time: 11Sep2017 13:11:34 Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 632 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 12:16
Peak Outflow: 242(CFS)	Date/Time of Peak Outflow: 01Jul2015, 13:18
Total Inflow : 123.0 (AC-FT)	Peak Storage: 41.3 (AC-FT)
Total Outflow: 101.0 (AC-FT)	Peak Elevation: 6973.5 (FT)

**Simulation Run: F-005 YR Reservoir: POND E**

Start of Run: 01Jul2015, 00:00 Basin Model: Future SCS  
End of Run: 02Jul2015, 00:00 Meteorologic Model: SCS TYPE IIA 005YR  
Compute Time: 11Sep2017 13:26:34 Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 137 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 06:14
Peak Outflow: 18(CFS)	Date/Time of Peak Outflow: 01Jul2015, 08:10
Total Inflow : 28.5 (AC-FT)	Peak Storage: 14. (AC-FT)
Total Outflow: 17.2 (AC-FT)	Peak Elevation: 6971.0 (FT)

**Simulation Run: F-100 YR Reservoir: POND H**

Start of Run: 01Jul2015, 00:00 Basin Model: Future SCS  
End of Run: 02Jul2015, 00:00 Meteorologic Model: SCS TYPE IIA 100YR  
Compute Time: 11Sep2017 13:11:34 Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 160 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 12:06
Peak Outflow: 58 (CFS)	Date/Time of Peak Outflow: 01Jul2015, 12:32
Total Inflow : 18.0 (AC-FT)	Peak Storage: 7.7 (AC-FT)
Total Outflow: 15.2 (AC-FT)	Peak Elevation: 6973.5 (FT)

**Simulation Run: F-005 YR Reservoir: POND H**

Start of Run: 01Jul2015, 00:00 Basin Model: Future SCS  
End of Run: 02Jul2015, 00:00 Meteorologic Model: SCS TYPE IIA 005YR  
Compute Time: 11Sep2017 13:26:34 Control Specifications: 24 HR-2 MIN.

Volume Units: AC-FT

Computed Results:

Peak Inflow: 36 (CFS)	Date/Time of Peak Inflow: 01Jul2015, 06:14
Peak Outflow: 3 (CFS)	Date/Time of Peak Outflow: 01Jul2015, 08:24
Total Inflow : 4.5 (AC-FT)	Peak Storage: 2.7 (AC-FT)
Total Outflow: 2.4 (AC-FT)	Peak Elevation: 6971.7 (FT)

## RIP RAP PLUNGE POOL

Urban Drainage & Flood Control District Pipe Outlet Design  
Low Tailwater Design ( $y_t \leq D/3$ )

OUTLET # **POND H**

Outlet Size (D):	<b>42</b>	in.	Discharge (q):	<b>51</b>	CFS
Capacity (Q): (full flow)	<b>71</b>	CFS	Flow depth (d): (calculated)	<b>2.23</b>	ft.

Q <sub>full</sub> =	<b>71</b>	CFS	q/Q <sub>full</sub> =	0.72
A <sub>full</sub> =	9.6	SF		
V <sub>full</sub> =	7.4	FPS	Q/D <sup>2.5</sup> =	2.2

d/D	<b>0.70</b>	from HS-20a using q/Q <sub>full</sub>
d/D	<b>0.50</b>	from HS-20b using Q/D <sup>2.5</sup>

A' (A/A <sub>full</sub> )	0.50	from HS-20a using smaller d/D from above	Flow Area (a=A' x A <sub>full</sub> )	4.8	SF
------------------------------	------	---	--	-----	----

Outlet Velocity (V = q/a)      10.6      FPS

$$P_d = (V^2 + gd)^{1/2} = 13$$

RIP-RAP SIZE: **L** from HS-20c  
d<sub>50</sub> = 9 in      T=1.75xd<sub>50</sub>      1.313 ft

Basin Length (L)	14.0 FT.	Cutoff Wall Depth (B=D/2+T)	3.063	FT
Basin Width (W)	14.0 FT.			

## **Appendix C – Temporary Sedimentation**



**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 1**

Tributary Area: 12.6 ac.      Required Volume: 0.5 ac-ft      Depth at Outlet: 1.9 ft.

Area required  
per Row  
1.9 in<sup>2</sup>

WS Elev: 7020.9

No. of  
columns  
**4**

Hole size  
3/4 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	7019	0	629	0.014	0.000	0.00
2	7020	1	14341	0.33	0.17	0.17
3	7021	2	19014	0.44	0.38	0.55
4	7022	3	25889	0.59	0.52	1.07
5	7023	4	32619	0.75	0.67	1.74
6	7024	5	40586	0.93	0.84	2.58

Minimum steel thickness		1	2	3	<b>4</b>	5	6
		1/4	5/16	3/8	<b>3/8</b>	3/8	1/2
1/2	0.5000	0.20	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
<b>13/16</b>	0.8125	0.52	1.04	1.56	<b>2.07</b>	2.59	3.11
7/8	0.8750	0.60	1.20	1.80	2.41	3.01	3.61
15/16	0.9375	0.69	1.38	2.07	2.76	3.45	4.14
1	1.0000	0.79	1.57	2.36	3.14	3.93	4.71
1 1/16	1.0625	0.89	1.77	2.66	3.55	4.43	5.32

\* 4 Columns of 13/16 holes existing.

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 2**

Tributary Area: Required Volume Depth at Outlet  
**16.4** ac. 0.7 ac-ft 6.0 ft.

Area required  
per Row  
0.6 in<sup>2</sup>

WS Elev: 7045.8

No. of  
columns  
**3**

Hole size  
1/2 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	7039.8	0	0	0.000	0.000	0.00
2	7040	0.2	664	0.015	0.002	0.00
3	7041	1.2	3342	0.08	0.05	0.05
4	7042	2.2	4357	0.10	0.09	0.14
5	7043	3.2	5416	0.12	0.11	0.25
5	7044	4.2	6551	0.15	0.14	0.39
6	7045	5.2	7750	0.18	0.16	0.55
7	7046	6.2	9003	0.21	0.19	0.74

Minimum steel thickness		1	2	<b>3</b>	4	5	6
		1/4	5/16	<b>3/8</b>	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
<b>1/2</b>	0.5000	0.20	0.39	<b>0.59</b>	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.8125	0.52	1.04	1.56	2.07	2.59	3.11



**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 3**

Tributary Area: Required Volume Depth at Outlet  
**6.5** ac. 0.3 ac-ft 2.6 ft.

Area required  
per Row  
0.4 in<sup>2</sup>

WS Elev: 7036.8

No. of  
columns  
**2**

Hole size  
1/2 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	7034.2	0	0	0.000	0.000	0.00
2	7034.5	0.3	1336	0.031	0.005	0.00
3	7035	0.8	3750	0.09	0.03	0.03
4	7036	1.8	6389	0.15	0.12	0.15
5	7037	2.8	10332	0.24	0.19	0.34

Minimum steel thickness		1	<b>2</b>	3	4	5	6
		1/4	<b>5/16</b>	3/8	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
<b>1/2</b>	<b>0.5000</b>	0.20	<b>0.39</b>	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.8125	0.52	1.04	1.56	2.07	2.59	3.11

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 4**

Tributary Area: Required Volume Depth at Outlet  
**32.0** ac. 1.3 ac-ft 6.3 ft.

Area required  
per Row  
1.1 in<sup>2</sup>

WS Elev: 7004.8

No. of  
columns  
**3**

Hole size  
5/8 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	6998.5	0	0	0.000	0.000	0.00
2	6999	0.5	1701	0.04	0.01	0.01
3	7000	1.5	5758	0.13	0.09	0.10
4	7001	2.5	8748	0.20	0.17	0.26
5	7002	3.5	10282	0.24	0.22	0.48
6	7003	4.5	11887	0.27	0.25	0.73
7	7004	5.5	13562	0.31	0.29	1.03
8	7005	6.5	15307	0.35	0.33	1.36

Minimum steel thickness		1	2	<b>3</b>	4	5	6
		1/4	5/16	<b>3/8</b>	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
1/2	0.5000	0.20	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
<b>5/8</b>	0.6250	0.31	0.61	<b>0.92</b>	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.8125	0.52	1.04	1.56	2.07	2.59	3.11

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 5**

Tributary Area: Required Volume    Depth at Outlet  
**4.4** ac.                      0.2 ac-ft                      3.7 ft.

Area required  
per Row  
0.2 in<sup>2</sup>

WS Elev: 7044.7

No. of  
columns                      Hole size  
**1**                              1/2 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	7041	0	0	0.000	0.000	0.00
2	7042	1	2030	0.05	0.02	0.02
3	7043	2	2607	0.06	0.05	0.08
4	7044	3	3247	0.07	0.07	0.14
5	7045	4	3950	0.09	0.08	0.23

TABLE SB-2							
Minimum steel thickness		1	2	3	4	5	6
		1/4	5/16	3/8	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
<b>1/2</b>	0.5000	<b>0.20</b>	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.8125	0.52	1.04	1.56	2.07	2.59	3.11

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 6**

Tributary Area: Required Volume Depth at Outlet  
**8.2** ac. 0.3 ac-ft 3.4 ft.

Area required  
 per Row  
 0.3 in<sup>2</sup>

WS Elev: 7033.4

No. of  
 columns

Hole size

**2**

7/16 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	7030	0	0	0.000	0.000	0.00
2	7031	1	3890	0.09	0.04	0.04
3	7032	2	4705	0.11	0.10	0.14
4	7033	3	5582	0.13	0.12	0.26
5	7033.7	3.7	6043	0.14	0.09	0.35

**TABLE SB-2**

Minimum steel thickness	1	<b>2</b>	3	4	5	6	
	1/4	<b>5/16</b>	3/8	3/8	3/8	1/2	
1/4	0.25	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.31	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.38	0.11	0.22	0.33	0.44	0.55	0.66
<b>7/16</b>	0.44	0.15	<b>0.30</b>	0.45	0.60	0.75	0.90
1/2	0.50	0.20	0.39	0.59	0.79	0.98	1.18
9/16	0.56	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.63	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.69	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.75	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.81	0.52	1.04	1.56	2.07	2.59	3.11

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**TEMP POND 7**

Tributary Area: Required Volume Depth at Outlet  
**8.4** ac. 0.3 ac-ft 6.6 ft.

Area required  
per Row  
0.2 in<sup>2</sup>

WS Elev: 7006.6

No. of  
columns  
**1**

Hole size  
1/2 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	7000	0	0	0.000	0.000	0.00
2	7001	1	910	0.02	0.01	0.01
3	7002	2	1301	0.03	0.03	0.04
4	7003	3	1754	0.04	0.04	0.07
5	7004	4	2265	0.05	0.05	0.12
6	7005	5	2835	0.07	0.06	0.18
7	7006	6	3462	0.08	0.07	0.25
8	7006.95	6.95	4104	0.09	0.08	0.33

Minimum steel thickness		1	2	3	4	5	6
		1/4	5/16	3/8	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
3/8	0.3750	0.11	0.22	0.33	0.44	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
<b>1/2</b>	0.5000	<b>0.20</b>	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.8125	0.52	1.04	1.56	2.07	2.59	3.11

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**LAMBERT POND**

Tributary Area: Required Volume Depth at Outlet  
**8.1** ac. 0.3 ac-ft 4.1 ft.

Area required  
 per Row  
 0.2 in<sup>2</sup>

WS Elev: 6988.6

No. of  
 columns  
**2**

Hole size  
 5/16 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	6984.5	0	32	0.001	0.000	0.00
2	6985	0.5	884	0.02	0.01	0.01
3	6986	1.5	2594	0.06	0.04	0.05
4	6987	2.5	3881	0.09	0.07	0.12
5	6988	3.5	5238	0.12	0.10	0.22
6	6989	4.5	6669	0.15	0.14	0.36
7	6990	5.5	8172	0.19	0.17	0.53
8	6991	6.5	9748	0.22	0.21	0.74

Minimum steel thickness		1	2	3	4	5	6
		1/4	5/16	3/8	3/8	3/8	1/2
1/4	0.2500	0.05	0.10	0.15	0.20	0.25	0.29
5/16	0.3125	0.08	0.15	0.23	0.31	0.38	0.46
<b>3/8</b>	0.3750	0.11	0.22	0.33	<b>0.44</b>	0.55	0.66
7/16	0.4375	0.15	0.30	0.45	0.60	0.75	0.90
1/2	0.5000	0.20	0.39	0.59	0.79	0.98	1.18
9/16	0.5625	0.25	0.50	0.75	0.99	1.24	1.49
5/8	0.6250	0.31	0.61	0.92	1.23	1.53	1.84
11/16	0.6875	0.37	0.74	1.11	1.48	1.86	2.23
3/4	0.7500	0.44	0.88	1.33	1.77	2.21	2.65
13/16	0.8125	0.52	1.04	1.56	2.07	2.59	3.11

**WINDING WALK GRADING  
TEMPORARY SEDIMENTATION SIZING**

**POND H TEMP POND**

Tributary Area: Required Volume Depth at Outlet  
**76.0** ac. 3.1 ac-ft 3.1 ft.

Area required  
per Row  
3.0 in<sup>2</sup>

WS Elev: 6971.6

No. of  
columns  
**6**

Hole size  
3/4 in

STAGE			STORAGE			
STAGE	ELEV	HEIGHT	AREA		VOLUME	
			sqft	acre	acft	cum acft
1	6968.5	0	0	0.000	0.000	0.00
2	6969	0.5	4127	0.095	0.024	0.02
3	6970	1.5	37142	0.85	0.47	0.50
4	6971	2.5	82122	1.89	1.37	1.87
5	6972	3.5	110378	2.53	2.21	4.08
6	6973	4.5	125282	2.88	2.71	6.78
7	6974	5.5	138866	3.19	3.03	9.81
8	6975	6.5	153432	3.52	3.36	13.17

**TABLE SB-2**

Minimum steel thickness	1	2	3	4	5	<b>6</b>
	1/4	5/16	3/8	3/8	3/8	<b>1/2</b>
3/8	0.38	0.11	0.22	0.33	0.44	0.66
7/16	0.44	0.15	0.30	0.45	0.60	0.90
1/2	0.50	0.20	0.39	0.59	0.79	1.18
9/16	0.56	0.25	0.50	0.75	0.99	1.49
5/8	0.63	0.31	0.61	0.92	1.23	1.84
11/16	0.69	0.37	0.74	1.11	1.48	2.23
<b>3/4</b>	0.75	0.44	0.88	1.33	1.77	<b>2.65</b>
13/16	0.81	0.52	1.04	1.56	2.07	3.11
7/8	0.88	0.60	1.20	1.80	2.41	3.61
15/16	0.94	0.69	1.38	2.07	2.76	4.14





## **Appendix D – Soil Resource Report**





United States  
Department of  
Agriculture

**NRCS**

Natural  
Resources  
Conservation  
Service

A product of the National  
Cooperative Soil Survey,  
a joint effort of the United  
States Department of  
Agriculture and other  
Federal agencies, State  
agencies including the  
Agricultural Experiment  
Stations, and local  
participants

# Custom Soil Resource Report for El Paso County Area, Colorado



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

<b>Preface</b> .....	2
<b>How Soil Surveys Are Made</b> .....	5
<b>Soil Map</b> .....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
El Paso County Area, Colorado.....	13
19—Columbine gravelly sandy loam, 0 to 3 percent slopes.....	13
83—Stapleton sandy loam, 3 to 8 percent slopes.....	14
<b>References</b> .....	16

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

## Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and



## Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map


---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

# Custom Soil Resource Report Soil Map




Soil Map may not be valid at this scale.





### MAP LEGEND

**Area of Interest (AOI)**

 Area of Interest (AOI)




















**Soils**







 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

**Special Point Features**






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features


**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 14, Sep 23, 2016

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Apr 15, 2011—Sep 22, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

El Paso County Area, Colorado (CO625)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
19	Columbine gravelly sandy loam, 0 to 3 percent slopes	23.0	10.7%
83	Stapleton sandy loam, 3 to 8 percent slopes	191.8	89.3%
<b>Totals for Area of Interest</b>		<b>214.8</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the

## Custom Soil Resource Report

development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## El Paso County Area, Colorado

### 19—Columbine gravelly sandy loam, 0 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 367p  
*Elevation:* 6,500 to 7,300 feet  
*Mean annual precipitation:* 14 to 16 inches  
*Mean annual air temperature:* 46 to 50 degrees F  
*Frost-free period:* 125 to 145 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Columbine and similar soils:* 85 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Columbine

##### Setting

*Landform:* Flood plains, fan terraces, fans  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Alluvium

##### Typical profile

*A - 0 to 14 inches:* gravelly sandy loam  
*C - 14 to 60 inches:* very gravelly loamy sand

##### Properties and qualities

*Slope:* 0 to 3 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Well drained  
*Runoff class:* Very low  
*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (5.95 to 19.98 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water storage in profile:* Very low (about 2.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 4e  
*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* Gravelly Foothill (R049BY214CO)  
*Hydric soil rating:* No

#### Minor Components

##### Fluvaquentic haplaquolls

*Percent of map unit:*  
*Landform:* Swales  
*Hydric soil rating:* Yes

##### Other soils

*Percent of map unit:*

*Hydric soil rating:* No

**Pleasant**

*Percent of map unit:*

*Landform:* Depressions

*Hydric soil rating:* Yes

**83—Stapleton sandy loam, 3 to 8 percent slopes**

**Map Unit Setting**

*National map unit symbol:* 369z

*Elevation:* 6,500 to 7,300 feet

*Mean annual precipitation:* 14 to 16 inches

*Mean annual air temperature:* 46 to 48 degrees F

*Frost-free period:* 125 to 145 days

*Farmland classification:* Not prime farmland

**Map Unit Composition**

*Stapleton and similar soils:* 80 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Stapleton**

**Setting**

*Landform:* Hills

*Landform position (three-dimensional):* Side slope

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Parent material:* Sandy alluvium derived from arkose

**Typical profile**

*A - 0 to 11 inches:* sandy loam

*Bw - 11 to 17 inches:* gravelly sandy loam

*C - 17 to 60 inches:* gravelly loamy sand

**Properties and qualities**

*Slope:* 3 to 8 percent

*Depth to restrictive feature:* More than 80 inches

*Natural drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* High (2.00 to 6.00 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Available water storage in profile:* Low (about 4.7 inches)

**Interpretive groups**

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 3e

*Hydrologic Soil Group:* B



## Custom Soil Resource Report

*Ecological site:* Gravelly Foothill (R049BY214CO)

*Hydric soil rating:* No

### **Minor Components**

#### **Fluvaquentic haplaquolls**

*Percent of map unit:*

*Landform:* Swales

*Hydric soil rating:* Yes

#### **Other soils**

*Percent of map unit:*

*Hydric soil rating:* No

#### **Pleasant**

*Percent of map unit:*

*Landform:* Depressions

*Hydric soil rating:* Yes

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)







## **Appendix E – Drainage Maps**





# SCS DRAINAGE MAP MERIDIAN RANCH WINDING WALK GRADING



HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q30 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
OS02	0.2219	148	102	65	30	13	3.0
B01	0.2219	148	102	65	30	13	3.0
B01-B07	0.2219	148	102	65	30	13	3.0
OS03	0.1984	130	88	55	23	9	2.0
B02-B03	0.1984	129	88	55	23	9	2.0
HB01	0.0234	19	13	8	3	1	0.0
B03	0.2218	140	95	59	25	10	2.0
B03-B07	0.2218	140	94	59	25	10	2.0
OS04	0.1359	83	54	32	12	4	1.0
B04-B05	0.1359	82	54	32	12	4	1.0
HB03	0.1266	103	68	41	15	5	1.0
B05	0.2625	144	91	52	20	7	1.0
B05-B07	0.2625	144	91	52	20	7	1.0
HB02	0.1063	77	51	30	11	4	0.0
HB04	0.0609	47	31	19	7	2	0.0
B07	0.8734	519	344	207	86	33	6.0
B07-B12	0.8734	518	343	207	86	33	6.0
HB05	0.1375	102	67	40	15	5	1.0
HB06	0.1641	111	73	43	16	5	1.0
B12	1.175	679	440	259	103	40	7.0
B12-PB	1.175	677	440	259	103	39	7.0
HB07	0.0313	29	19	12	4	1	0.0
POND B	1.2063	688	446	262	105	40	7.0
PB-19	1.2063	687	444	261	104	40	7.0
OS01	1.5594	757	510	316	136	55	11
OS01-B19	1.5594	756	509	315	136	55	11
HB08	0.1344	81	53	32	12	4	1.0
HB09	0.3047	138	90	54	21	7	1.0
B19	3.2048	1563	1041	635	266	105	20
B19-B26	3.2048	1563	1039	634	266	105	20
HB10	0.3047	172	113	67	26	9	1.0
HB12	0.0797	54	36	21	8	3	0.0
HB12-B26	0.0797	54	35	21	8	3	0.0
B26	3.3692	1737	1147	693	288	113	21
B26-32	3.3692	1734	1146	693	287	113	21
HB11	0.1125	60	40	23	9	3	0.0
32	3.7017	1782	1177	709	293	115	22
32-37	3.7017	1782	1175	708	293	115	22
B-14	0.4039	178	117	70	27	10	2.0
B-13	0.2813	127	83	50	19	7	1.0
36	0.6852	306	200	119	47	17	3.0
36-37	0.6852	305	200	119	47	17	3.0
B-15	0.075	39	26	15	6	2	0.0
37	4.4619	2117	1391	834	338	131	25
HG07	0.0984	50	32	19	7	3	0.0
HG07-G11	0.0984	50	32	19	7	3	0.0
HG08	0.1328	77	51	30	11	4	1.0
G11	0.2312	122	79	47	18	6	1.0
G11-G12	0.2312	121	79	47	18	6	1.0
HG09	0.1781	76	50	30	12	4	1.0
G12	0.4093	196	128	76	29	10	2.0
G12-H08	0.4093	196	128	76	29	10	2.0
HG10	0.1375	40	26	16	7	3	1.0
H08	0.5488	227	149	89	35	13	2.0
H09	0.2047	80	53	31	13	5	1.0
H01	0.0984	70	46	27	10	3	0.0
H12	0.0984	70	46	27	10	3	0.0
HG12	0.1297	60	39	23	9	3	1.0
H10	0.1297	60	39	23	9	3	1.0




**HISTORIC CONDITIONS**

TECH CONTRACTORS  
11886 STAPLETON DR  
FALCON, CO 80831  
TELEPHONE: 719.495.7444

**FIGURE 4**



# SCS DRAINAGE MAP MERIDIAN RANCH WINDING WALK GRADING



TEMPORARY SEDIMENTATION PONDS		
POND	TRIB AREA (AC)	REQ'D VOL (AC-FT)
EX #1	12.6	0.5
#2	16.4	0.7
#3	6.5	0.3
#4	32.0	1.3
#5	4.4	0.2
#6	8.2	0.3
#7	8.4	0.3
TEMP H	76.0	3.1
LAMBERT	8.1	0.3

HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
OS01	1.5594	757	510	316	136	55	11
DB16	0.0578	92	72	54	35	23	13
B10	1.6172	794	537	335	147	62	13
B10-B11	1.6172	793	537	335	147	62	13
DB17	0.0048	16	13	11	9	7	6
B11	1.622	795	538	336	148	63	15
B11-POND C	1.622	795	538	336	148	63	15
DB21	0.0519	54	38	25	12	5	1
DB18	0.0346	64	50	39	26	18	10
DB19	0.0281	36	27	20	11	7	3
DB20	0.0147	25	19	15	9	6	3
POND C	1.7513	749	507	310	129	50	11
POND C-B16	1.7513	749	507	310	128	50	11
DB25	0.0211	45	35	27	18	12	7
B16	1.7724	754	511	313	130	51	11
B16-B17	1.7724	754	510	312	130	51	11
DB26	0.0682	136	110	88	62	46	29
B17	1.8406	778	529	326	138	56	34
B17-B18	1.8406	778	529	326	138	56	34
OS03	0.1884	130	88	55	24	9	2
DB01	0.0719	90	66	46	25	14	5
B01	0.2703	199	139	89	42	19	5
B01-B02	0.2703	199	138	89	42	19	5
OS02	0.2219	148	102	65	30	13	3
DB02	0.0516	71	52	36	20	10	3
B02	0.5438	380	263	169	79	36	9
B02-POND A	0.5438	379	263	169	79	36	9
OS04	0.1569	83	54	32	12	4	1
DB03	0.0703	70	49	32	16	7	2
B03	0.2062	145	98	61	26	10	2
B03-B04	0.2062	145	98	60	26	10	2
DB04	0.0422	44	31	21	10	5	1
DB05	0.0384	37	27	18	9	5	1
B04	0.2868	218	150	94	42	18	4
B04-B05	0.2868	218	149	94	42	18	4
DB06	0.0219	44	35	26	19	14	9
B05	0.3087	253	176	115	55	26	10
B05-POND A	0.3087	252	176	114	55	26	10
DB07	0.0254	35	26	18	10	6	2
DB08	0.0297	32	22	15	7	3	1
POND A	0.9076	554	386	238	88	27	4
POND A-B06	0.9076	554	385	237	88	27	4
DB09	0.0189	34	26	19	12	8	4
B06	0.9285	562	401	241	90	28	4
B06-B07	0.9285	561	400	241	90	28	4
DB11	0.0969	114	85	60	35	20	8
DB10	0.0364	56	43	32	19	12	6
B07	1.0598	648	462	277	105	37	16
B07-B09	1.0598	647	461	276	105	37	16
DB12	0.0453	61	43	28	11	21	11
B09	1.1051	672	478	287	110	47	20
B09-POND B	1.1051	672	477	287	110	47	20
DB15	0.1234	105	75	50	25	12	3
DB13	0.0703	89	67	49	29	18	8
DB14	0.0556	93	72	54	35	23	12
POND B	1.3544	684	528	324	128	71	31
POND B-B12	1.3544	684	528	323	128	71	31
DB22	0.0516	91	72	55	36	25	14
DB23	0.0172	45	38	31	23	18	13
B12	1.4232	711	500	339	150	85	39
B12-B14	1.4232	711	500	338	150	85	39
DB24	0.0531	94	73	56	36	24	13
B14	1.4763	740	565	348	164	94	47
B14-B15	1.4763	738	564	348	164	94	47
DB28	0.0741	72	51	34	17	8	2
B15	1.5504	775	582	358	175	100	49
B15-B18	1.5504	775	582	358	175	100	49
DB29	0.1897	148	105	71	37	19	6
DB27	0.0508	68	53	40	25	17	9
B26	3.6115	1606	1158	717	298	175	89
B26-27	3.6115	1605	1158	716	298	175	88

HYDROLOGIC ELEMENT	DRAINAGE AREA (SQ. MI.)	DISCHARGE PEAK Q100 (CFS)	DISCHARGE PEAK Q50 (CFS)	DISCHARGE PEAK Q25 (CFS)	DISCHARGE PEAK Q10 (CFS)	DISCHARGE PEAK Q5 (CFS)	DISCHARGE PEAK Q2 (CFS)
FB-02	0.05	46	33	22	11	5	1
FB-01	0.0373	32	23	15	7	4	1
FB01-27a	0.0373	32	23	15	7	4	1
B19	0.0873	77	55	36	18	9	2
B19-27	0.0873	77	55	36	18	9	2
FB-03	0.0078	21	17	14	10	8	5
WH-27	3.7066	1634	1178	729	304	184	91
WH-32	3.7066	1633	1177	728	304	184	91
WH-24	0.1325	218	171	129	84	57	31
WH-26	0.0839	49	33	20	8	3	1
WH-27	0.0217	23	16	10	4	1	0
WH-30	0.2381	271	205	150	91	59	31
WH-28	0.0398	60	47	36	23	15	8
WH-31	0.2779	330	252	185	114	74	39
WH-33	0.2779	329	251	185	113	74	39
WH-29	0.0495	77	60	45	29	19	10
WH-31	0.0406	75	60	46	30	21	12
WH-30	0.0159	26	19	13	7	4	1
WH-32	0.0055	173	1289	787	415	252	121
WH-32	0.0458	55	38	24	10	4	0
BEN POND	4.1363	1379	966	581	243	97	44
WH-33	0.0064	12	9	7	5	3	2
WH-33	4.1427	1380	967	582	243	97	44
WH-33	4.1427	1380	967	581	243	97	44
WH-35	0.155	171	124	84	44	22	6
WH-34	0.045	68	52	38	23	15	7
B34-36	0.045	68	52	38	23	15	7
B36	0.2	239	176	122	67	37	13
B36-37	0.2	238	174	121	66	37	13
WH-36	0.075	63	43	27	11	4	1
B37	4.1777	1419	997	601	252	101	47
FG-8A	0.075	97	73	46	30	15	5
FG-8A-G05	0.075	125	97	72	45	30	15
FG-9B	0.063	94	72	54	34	22	11
FG-9B-G05	0.063	93	72	54	34	22	11
FG-11	0.0625	81	63	47	30	20	11
FG-9	0.0484	52	39	28	16	9	4
FG-9-G05	0.0484	52	39	27	16	9	4
FG-10	0.0467	31	21	13	6	2	0
G05	0.2955	370	281	206	126	80	39
FG-13	0.0661	46	32	21	11	5	2
FG-12	0.0328	55	44	33	22	15	9
G17	0.4398	120	77	38	17	9	5
G17-G18	0.4398	120	77	38	17	9	5
FG-16	0.0773	135	105	79	51	34	18
G18	0.5171	179	135	100	64	42	23
G18-POND E	0.5171	178	134	100	63	42	22
H02	0.1844	51	34	21	9	3	1
FG-30-PONDHS	0.1844	51	34	21	9	3	1
FG-31	0.0922	123	97	74	49	33	19
POND HS	0.2766	103	62	40	28	19	10
FG-17a	0.0694	117	91	69	44	29	16
FG-17a-POND E	0.0694	116	90	68	44	29	16
FG-18	0.0644	42	30	20	10	5	1
FG-18-POND E	0.0644	42	30	20	10	5	1
FG-19	0.0527	82	63	47	30	19	10
FG-17c	0.0313	34	24	16	8	3	1
FG-17b	0.0214	42	34	26	17	12	7
POND E	1.0329	188	113	57	25	15	9
FG-0	0.0109	31	28	22	16	13	9
H08-H09	1.0438	189	114	57	25	18	12
FH01	0.1344	90	64	42	21	10	3
H08	154	95	48	19	10	6	3
H09	34	19	6	11	6	4	3
POND H	0.1344	23	13	6	2	1	1
FH02	0.0138	18	14	10	5	3	1
H12	0.1482	25	14	10	6	3	1

## GRADED CONDITIONS

TECH CONSTRUCTION CORP.  
12311 REX ROAD  
PEYTON, CO 80831  
TELEPHONE: 719.495.7444  
FAX: 719.495.3349

FIGURE 5

S:\C:\p\p\Winding Walk Filing\10\DWG\PLAN SHEETS\BASIN\MASS\GRADING\WV\SCS-GRAD\ED.dwg, Fig. 5, 2/22/2018, 12:39:43 PM



