

To: Adelaida Romens/Trustee 5135 Cornflower Lane Colorado Springs CO 80917

CC: David Mijares, PE Catamount Engineering

From: Julia Murphy, MS PG Professional Geologist

Date: January 6, 2022

(Updated August 19, 2023)

RE: Water Resources Report, Romens Subdivision

This Water Resources Report was completed by Julia Murphy of Groundwater Investigations LLC, a Professional Geologist, on behalf of Romens Living Trust ("Applicant") in accordance with the requirements of the El Paso County Land Development Code described in Section 8.4.7 (B)(1)(c). Ms. Murphy has over 20 years' experience in hydrogeologic analysis. She has been involved in evaluating water supply for subdivisions in El Paso County for over 15 years. This report presents the data, documentation and analysis in sufficient detail to determine sufficiency of the proposed subdivision's water supply in terms of dependability, quantity and quality.

1.0 Summary of the Proposed Subdivision

The Romens' property (Attachment 1) consists of a 40-acre parcel zoned RR-5 located in the Northeast ¼ of the Northeast ¼ of Section 24, Township 11 South, Range 64 West, of the 6th P.M. ("Property"). The Property is situated within the Upper Black Squirrel Designated Groundwater Basin having the address 17720 Cleese Court, in Peyton in El Paso County Colorado (Figure 1). There is an existing well having Permit 195628 drilled in 1997 completed into the Dawson aquifer (Attachment 2). There are no other wells or existing homes on the Property.



The 40 acre property will be subdivided to create a 7-lot subdivision. The following is a list of the size of each proposed lot (Figure 2):

Proposed Lots Size							
1	5.082						
2	5.199						
3	5.585						
4	5.447						
5	5.037						
6	5.185						
7	5.004						

2.0 Information Regarding Sufficient Quantity of Water

2.1 Calculation of Quantity of Water Available and Supply Source

Groundwater underlying the Property will be used as the source of water supply for the subdivision. Determination of Water Rights for the four underlying groundwater aquifers: Dawson (4278-BD), Denver (4277-BD), Arapahoe (4276-BD), and Laramie Fox Hills Aquifers (4375-BD) and Replacement Plan for the not non-tributary Dawson Aquifer (4278-RP) was approved by the Colorado Groundwater Commission ("Commission") on January 5, 2022. Table 1 quantifies the groundwater underlying the property in each of the four aquifers.



Table 1 Aquifer Quantification											
Annual Average AQUIFER NET Withdrawal 100 SAND Years Withdrawal (feet) (Acre Feet) (Acre Feet)											
Dawson (NNT)	110	8.85	855(1)								
Denver (NT)	300	20.40	2040								
Arapahoe (NT)	1500										
Laramie-Fox Hills (NT) 210 12.60 1260											
(1) Reduced by 25 Al	F to accou	int for the existing we	ell use								

The Dawson aquifer is the shallow most aquifer and was determined to have 855 acre feet of available groundwater. Removal of this groundwater over 300 years would allow for 2.85 acre feet per year to be used by the subdivision or 0.407 acre feet per year per lot.

2.2 Water Demand

In home use established as acceptable by the State Engineer is a presumed 0.20 acre feet per year. This differs from the current El Paso County Land Development Code's presumptive of 0.26 acre feet per year. Using the County's more conservative approach, there would be a remaining 0.147 acre feet per year available for domestic use including domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and/or the watering of stock animals, either directly or after storage in accordance with the Determination of Water Rights 4278-BD (Attachment 3).

2.3. Meeting Replacement Requirements

Pumping from the Dawson aquifer was simulated using a groundwater flow model to evaluate stream depletions to prevent any material injury to existing water rights in



alluvial aquifers. At a continuous withdrawal rate of 2.85 acre-feet annually for 300 years, depletions to the alluvial aquifer systems would steadily increase to a maximum of 0.142 acre-feet per year in the 300th year, which is equal to 4.98% of pumping. Replacement of the depletions will occur from recharge from individual on-site wastewater treatment systems.

In accordance with replacement plan 4278-RP, it is accepted that the septic/leach field return flows from each lot will consist of 90% of the water used for in-house purposes (Attachment 4). Assuming values established as acceptable by the State Engineer, 0.20 acre-feet per lot was used for annual in-home use resulting in a total annual return rate of 1.26 acre-feet for all 7 lots at full build out. This exceeds the maximum depletion of 0.142 acre-feet that is projected to occur in the 300th year. Flow meters will be required on each well to quantify annual use and ensure compliance with the replacement plan. The onsite wastewater treatment systems will be installed and maintained according to the El Paso County Guidelines and approved by the El paso County Department of Health.

Based on accepted methods of quantification, the water supply is sufficient in quantity to meet the average annual demand of the proposed subdivision for a period of 300 years.

3.0 Information Regarding Sufficient Dependability of Water Supply

3.1 Proof of Ownership.

Attachment 1 provides the Warranty Deed for the property and its legal description. The original Well Permit for the existing well and Determination of Water Rights for the Dawson Aquifer are provided as Attachments 2 and 3, respectively. The Romens Living Trust is listed as owner in the Determination of Water Rights and the transfer of water rights for the Dawson aquifer, the sole source of water supply, will occur with the sale of each lot such that each lot will be allocated 122.1 Acre feet of water.

3.2 Water Supply



The 6 proposed new wells and one existing well for the 7 lots will use the not-nontributary Dawson Aquifer groundwater for their water supply. The Dawson aquifer was determined by the Commission to have 855 acre feet of available groundwater underlying the property which will provide a 300 year supply at a rate of 2.85 acre feet per year or 0.407 acre feet per year per lot.

4.0 Information Regarding Sufficient Quality

Water quality samples were collected by GWI using standard collection and preservation methods and are presented in a separate Water Quality Report dated June 23, 2021. Analytes measured are in agreement with the Land Development Code Section 8.4.7(B)(10)(a). The analysis results are presented in the Water Quality Report and provides evidence that the groundwater in the Dawson aquifer collected on the property meets the Colorado Primary Drinking Water Standards for the required analytes at the sample location except for Radium 226/228 which can be mitigated using a Reverse Osmosis or ion exchange treatment system.

5.0 Summary and Conclusions

The proposed subdivision of 40 acres will create 7 new lots. The purpose of the Water Resources Report is to provide the data, documentation and analysis in sufficient detail to determine sufficiency of the proposed subdivision's water supply in terms of dependability, quantity and quality. Water delivered by wells completed in the not non tributary Dawson aquifer underlying the Property will be used to supply each home. The Determination of Water Rights 4278-BD and Replacement Plan 4278-RPwere approved by the Colorado Groundwater Commission on January 5, 2022. Based on the proposed uses and quantification of available groundwater, there is sufficient quantity to meet the County required 300 year water supply criteria providing each home/lot with 0.407 acre feet of water per year. The Dawson aquifer has successfully been a primary source of water supply for similar homes at sufficient rates and duration to meet similar uses; the source is a dependable supply. The quality of the Dawson aquifer groundwater underlying the new proposed lot was evaluated within the parameters specified in the Land Development Code and have been determined to meet Primary Drinking



Water Standards for the selected analytes with the exception of Radionuclides which can be mitigated with a point of use reverse osmosis treatment system. The proposed water supply for the subdivision is in compliance with the Land Development Code requirement of dependability, quantity and quality.

To: Adelaida Romens

5135 Cornflower Lane

Colorado Springs CO 80917

From: Julia Murphy MS PG

Professional Geologist

Date: June 23, 2021

RE: Water Quality Report, Romens Subdivision

This Water Quality Report was completed for Adelaida Romens ("Applicant") by Julia Murphy of Groundwater Investigations LLC ("GWI"), a Professional Geologist, in accordance with the requirements of the El Paso County Land Development Code and the Amendment to the Land Development Code dated August 27, 2019 Section 8.4.7 (B)(10). Ms. Murphy has over 25 years' experience in geologic and hydrogeologic investigations with 9 years experience in water quality sampling and analysis of drinking water aquifers with specialization in contaminant hydrogeology.

This report presents a description of groundwater sampling and analysis for the purpose of providing all necessary information for determination of sufficiency in water quality for the Romens' Subdivision water supply. The subdivision water quality is required to be compared with the Colorado Primary Drinking Water Regulations (5CCR 1002-11).

1.0 Site Location

The 40 acre property is described as generally the NE 1/4 of the NE 1/4 of Section 24 Township 11 South, Range 64 west of the 6th P.M., in El Paso, Colorado and having the address of 17720 Cleese Street Colorado Springs, CO (Figure 1). The Property is located within the boundaries of the Upper Black Squirrel Creek Designated Ground Water Basin and within the Upper Black

Squirrel Creek Ground Water Management District. The Applicants intend to subdivide the property into seven lots ranging from 5.004 to 5.585 acres each.

2.0 Subdivision Water Source

The source of water for all Lots is the not-nontributary Denver Basin, Dawson Bedrock aquifer. The Dawson aquifer is the principal aquifer serving as the primary water supply for private wells in the area that range in depth from about 200 to 600 feet below ground surface. There is one existing well having Permit 195628 drilled in 1996 on the Property and located 1020 feet from the North and 1020 feet from the East section lines.

3.0 Sample Location and Collection

The water samples were collected from the existing well. As no home exists on the property, the well was pumped by the Pump installer. Representative water quality samples were collected by GWI on April 01, 2021 using laboratory accepted collection and preservation methods. Water quality samples were received by a Colorado Certified Laboratory on April 2, 2021; all holding times were met. A Chain of Custody was maintained for the transfer of samples to the Colorado Certified Laboratory from GWI and any subcontracted laboratory. Constituents selected to be measured are listed in the Amendment to the Land Development Code dated August 27, 2019, Section 8.4.7(B)(3)(d)(10)(a). Laboratory results and chain of custody forms are included in Exhibit A.

4.0 Analysis Results

4.1 Primary Drinking Water Standards

The analysis results for each constituent were compared to the Colorado Primary Drinking Water Standards maximum contaminant levels (MCL) and secondary MCLs. The primary MCL is the legal threshold limit on the amount of a substance that is allowed in *public water systems* under the Safe Drinking Water Act (SDWA). Private wells are not regulated under the SDWA however the El Paso County Public Health has required that new subdivisions evaluate their water supply based on the same criteria. Constituent concentrations that exceeded the MCL and possible treatment techniques are as follows:

Radium-226/228 and Gross Alpha & Beta

Radium-226/228 are combined for the purpose of evaluating compliance with the MCL. Radium 226/228 was detected at a concentration exceeding the MCL of 5.0 PCi/L. The occurrence and distribution of radionuclides in groundwater is controlled primarily by the local geology and the waters' geochemistry. Gross alpha and Beta were detected at levels greater than the MCl of 15 PCi/L. It is recommended that water samples be collected from the new wells when they are drilled and tested to assess local concentrations of these constituents and determine appropriate treatment options, if needed. A Point of Use (POU) treatment technology such as ion exchange or reverse osmosis may be installed for the purpose of reducing concentrations.

4.2 Secondary Drinking Water Standards

The secondary MCL was exceeded for Iron, aluminum, and manganese. Secondary MCLs primarily affect the aesthetic qualities of the water and are not enforceable in public water systems but are intended as guidelines. Iron is naturally occurring and can result in a red discoloration to clothing and thereby is considered a "nuisance" mineral however it does not have any known health effects. Excessive Iron can be mitigated by use of a water softener if desired by the homeowner but should not be required.

5.0 Sources of Potential Contaminants

The Romens Subdivision is situated in a rural residential area surrounded by lots of about 5 to 40 acres. There are no existing commercial sites in the area or upgradient of the property. Zoning is rural residential and there is no proposed plan that would indicate future commercial or industrial use. Domestic wells in the vicinity are completed to depths generally ranging from about 200 to 500 feet below ground surface and completed in the Dawson bedrock aquifers. Due to slow vertical infiltration as a result of impeding clay layers, there is a low possibility for on-site or off-site sources of potential water quality degradation from standard property uses. On-site septic system with leach field will be used to treat wastewater, however septic systems are not considered a potential contaminant source when they are constructed in accordance with existing protective regulations regarding design and setbacks from the well.

6.0. Recommendations

It is recommended that the groundwater be resampled and tested for the Radiological parameters when the new wells are drilled. If above the MCL, a POU reverse osmosis system or ion exchange may be used to reduce concentrations.



Analytical Results

TASK NO: 210402002

Report To: Julia M. Murphy

Company: Groundwater Investigations LLC 11590 Black Forest Road, Suite 15 Colorado Springs CO 80908 Bill To: Julia M. Murphy

Company: Groundwater Investigations LLC 11590 Black Forest Road, Suite 15

Colorado Springs CO 80908

Task No.: 210402002

Client PO:

Client Project: Romens Subdivision

Date Received: 4/2/21

Date Reported: 4/13/21

Matrix: Water - Drinking

Customer Sample ID R0421

Sample Date/Time: 4/1/21 9:30 AM **Lab Number:** 210402002-01

Test	Result	Method	ML	Date Analyzed	Analyzed By	MCL
Nitrate/ Nitrite Nitrogen	0.50 mg/L	Calculation	0.05 mg/L	4/7/21	MAT	
Chloride	2.8 mg/L	EPA 300.0	0.1 mg/L	4/2/21	MAT	
Fluoride	0.41 mg/L	EPA 300.0	0.10 mg/L	4/2/21	MAT	4
Nitrate Nitrogen	0.50 mg/L	EPA 300.0	0.05 mg/L	4/2/21	MAT	10
Nitrite Nitrogen	< 0.03 mg/L	EPA 300.0	0.03 mg/L	4/2/21	MAT	1
Sulfate	19.0 mg/L	EPA 300.0	0.1 mg/L	4/2/21	MAT	
Cyanide-Total	< 0.005 mg/L	EPA 335.4	0.005 mg/L	4/8/21	CES	0.02
<u>Total</u>						
Iron	6.636 mg/L	EPA 200.7	0.005 mg/L	4/6/21	MBN	0.3
Aluminum	2.957 mg/L	EPA 200.8	0.001 mg/L	4/5/21	IPC	0.05
Antimony	< 0.0012 mg/L	EPA 200.8	0.0012 mg/L	4/5/21	IPC	0.006
Arsenic	0.0049 mg/L	EPA 200.8	0.0006 mg/L	4/5/21	IPC	0.01
Barium	0.0685 mg/L	EPA 200.8	0.0007 mg/L	4/5/21	IPC	2
Beryllium	0.0044 mg/L	EPA 200.8	0.0001 mg/L	4/5/21	IPC	0.004
Cadmium	< 0.0001 mg/L	EPA 200.8	0.0001 mg/L	4/5/21	IPC	0.005
Chromium	0.0077 mg/L	EPA 200.8	0.0015 mg/L	4/5/21	IPC	0.1
Manganese	0.2635 mg/L	EPA 200.8	0.0008 mg/L	4/5/21	IPC	0.05
Mercury	0.0001 mg/L	EPA 200.8	0.0001 mg/L	4/5/21	IPC	0.002
Selenium	0.0027 mg/L	EPA 200.8	0.0008 mg/L	4/5/21	IPC	0.05

Abbreviations/ References:

ML = Minimum Level = LRL = RL
MCL = Maximum Contaminant Level per The EPA
mg/L = Milligrams Per Liter or PPM
ug/L = Micrograms Per Liter or PPB

mpn/100 mls = Most Probable Number Index/ 100 mls

Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY



Analytical Results

TASK NO: 210402002

Report To: Julia M. Murphy

Company: Groundwater Investigations LLC 11590 Black Forest Road, Suite 15

Colorado Springs CO 80908

Bill To: Julia M. Murphy

Company: Groundwater Investigations LLC

11590 Black Forest Road, Suite 15

Colorado Springs CO 80908

Task No.: 210402002

Client PO:

Client Project: Romens Subdivision

Date Received: 4/2/21 Date Reported: 4/13/21

Matrix: Water - Drinking

Customer Sample ID R0421

Sample Date/Time: 4/1/21 9:30 AM Lab Number: 210402002-01


Test	Result	Method	ML	Date Analyzed	Analyzed By	MCL
<u>Total</u>						
Silver	< 0.0005 mg/L	EPA 200.8	0.0005 mg/L	4/5/21	IPC	
Thallium	< 0.0002 mg/L	EPA 200.8	0.0002 mg/L	4/5/21	IPC	0.002
Zinc	0.061 mg/L	EPA 200.8	0.001 mg/L	4/5/21	IPC	5

Abbreviations/ References:

ML = Minimum Level = LRL = RLMCL = Maximum Contaminant Level per The EPA mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpn/100 mls = Most Probable Number Index/ 100 mls Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

Chain of Custody Form





Commerce City Lab 10411 Heinz Way **Commerce City CO 80640**

Lakewood Service Center 12860 W. Cedar Dr, Suite 100A Lakewood CO 80228

Phone: 303-659-2313

www.coloradolab.com

Sample Collector Phone: (7/9)338-1805 I	O No.:	/
		Tests Requested
Sample Matrix (Select One C	Only)	
Waste Water Soil S	Onitio	
Ground Water Sludge	Drinking Water	18614 250 1
Surface Water	Con Con Sixte	\$ 2 3 N F E Z 3 1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Surface Water	Duly) Out (Check One Only) Composite Outly	Colifornia ACCIONIA
Date Time Sample	z ပြော	36 KU Z 9 Z W F 6 4.
4/1/2/930 720421	Na2504 1	
1/1/01/		
	1	
	1/	
	17403	
	NaOH	
	(α_i)	
DED 50000001		
Instructions:	C/S Info:	Seals Present Yes No N
Instructions: KAdd Langlin Index	Deliver Via: Fedl X	5 4 w V = 16 =
Relinquished By: Date/Time: Received By	Date/Time; Relinquished By:	C/S Charge Temp. 7 °C/Ice Sample Pres. You No Date/Time: Received By: Date/Time:



Quotation for Analytical Services

Quote ID: QBO20060094

Prepared For:

Groundwater Investigations LLC 11590 Black Forest Road, Suite 15 Quote Date: Monday, June 29, 2020 Turn Around Time: 10 Working Days

Colorado Springs, CO 80908

Attn: Julia M. Murphy

		Service Control of the Control of th	
Project:		e Parker and the	
i rojece.		Section Contracts	
Project.		Additional Control of the Control of	The second secon

			ı

Matrix	Description	Method	Qty.	Price - each	Total
Water - Drinking	Nitrate/ Nitrite Nitrogen	Calculation	1	\$0.00	\$0.00
Water - Drinking	Fe - Total	EPA 200.7	1	\$12.00	\$12.00
Water - Drinking	Ph	SM 4500-H-B	1	\$12.00	\$12.00
Water - Drinking	Ag - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Al - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Alkalinity	SM 2320-B	1	\$15.00	\$15.00
Water - Drinking	As - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Ba - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Be - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Cd - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Cr - Total	EPA 200.8	1	\$15.00	\$15.00
Nater - Drinking	Hg	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Mn - Total	EPA 200.8	1	\$15.00	\$15.00
Nater - Drinking	Sb - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Se - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	TDS	SM 2540-C	1	\$15.00	\$15.00
Water - Drinking	TI - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Zn - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Chloride	EPA 300.0	1	\$17.00	\$17.00
Nater - Drinking	Nitrate Nitrogen	EPA 300.0	1	\$17.00	\$17.00
Water - Drinking	Nitrite Nitrogen	EPA 300.0	1	\$17.00	\$17.00
Water - Drinking	Sulfate	EPA 300.0	1	\$17.00	\$17.00
Water - Drinking	Fluoride	EPA 300.0	1	\$18.00	\$18.00
Water - Drinking	Total Coliform P/A	SM 9223	1	\$23.00	\$23.00
Water - Drinking	Cyanide-Total	EPA 335.4	1	\$38.00	\$38.00
Water - Drinking	Gross Alpha/Beta (Sub)	SM 7110-B	1	\$56.16	\$56.16
Water - Drinking	Radium 226 (Sub)	SM 7500-Ra B	1	\$75.60	\$75.60
Nater - Drinking	Radium 228 (Sub)	EPA Ra-05	1	\$118.80	\$118.80
Shipping	Cooler Shipment - UPS	UPS	1	\$10.00	\$10.00
Shipping	Sample Shipment to Outside Lab	UPS	1	\$30.00	\$30.00
$\sim M \hat{z}_{i}$.					



Analytical Results

TASK NO: 210402002

Report To: Julia M. Murphy

Company: Groundwater Investigations LLC

11590 Black Forest Road, Suite 15 Colorado Springs CO 80908 Bill To: Julia M. Murphy

Company: Groundwater Investigations LLC

11590 Black Forest Road, Suite 15 Colorado Springs CO 80908

Task No.: 210402002

Client PO:

Client Project: Romens Subdivision

Date Received: 4/2/21 Date Reported: 4/13/21

Matrix: Water - Drinking

Customer Sample ID R0421

Sample Date/Time: 4/1/21

9:30 AM

Lab Number: 210402002-01


Test	Result	Method	ML	Date Analyzed	Analyzed By
Bicarbonate	71.9 mg/L as CaCO3	SM 2320-B	4	4/6/21	ECM
Calcium as CaCO3	50.6 mg/L	EPA 200.7	0.1	4/6/21	MBN
Carbonate	< 4 mg/L as CaCO3	SM 2320-B	4	4/6/21	ECM
Hydroxide	< 4 mg/L as CaCO3	SM 2320-B	4	4/6/21	ECM
Langelier Index	-0.73 units	SM 2330-B		4/12/21	SAN
pH	7.49 units	SM 4500-H-B	0.01	4/2/21	PJL
Temperature	20 °C	SM 4500-H-B	1	4/2/21	PJL
Total Alkalinity	71.9 mg/L as CaCO3	SM 2320-B	4	4/6/21	ECM
Total Dissolved Solids	150 mg/L	SM 2540-C	5	4/6/21	ISG

Abbreviations/ References:

ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpn/100 mls = Most Probable Number Index/ 100 mls Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

Chain of Custody Form





Commerce City Lab 10411 Heinz Way **Commerce City CO 80640**

Lakewood Service Center 12860 W. Cedar Dr, Suite 100A Lakewood CO 80228

Phone: 303-659-2313

www.coloradolab.com

Sample Collector Phone:	(719)338-1805	PO No.:																
						- :					Tes	ts Re	eque	sted				1.1
	Sample Matrix (Select O	ne Only)			\$													
Waste Water	Soil	Deinkin - Wiston		ers	Onl			(%)		1 2) ~	\	İ	í	,			
Ground Water	Sludge 🗌	Drinking Water		tain	One	3	10	77		3/2	0 2)			9			
Surface Water				Con	eck (Site	S 5	3.0	Ŋ	4 3	ج اِ ک	5		1	\forall			
Surface Water				No. of Containers	Grab or (Check One Only)	omposite		200	A	MET		18	1	7	7			
Date Time	Sai	nple ID		ž	5 5	ပိ 🤨	0	Ki	Y	36	کالخ	N/	Ť.	. 9	7			
4/1/2/930	720421	Na	2504	1		V												
177701				1			/											
				1													+	
				1														
			/	/					7					\dashv	+-	+++		+
		1+14	03.,	1		- -	-			<u> </u>						+-+	+	+
		Na	OH	1					_	<u> </u>	4_		_	\dashv		+		\bot
				1							V	Y	\ \ <u>\</u>	1/1	4			
				'														
			(a)															
	DER DRONDE	Sladall																+
Instructions:	on Jovage	69977	C/S Info:	L							Seals Pro	esent Y	es 🔲	No 🔲				
KAdd Land	TER DBOZOR		Deliver Via:	Fe	de	X		C/S°C	harge		<i>[</i> Гетр.	1 .	C/Ice	V	Sample	Pres. Yes	И N.	. [7]
Relinquished By:	Date/Time: Received	By: Date/Tim	e: Re	lingu of 3	ished I	By:		Date/	Time		Recei				- mpie	Date/	Time:	<u> </u>



Quotation for Analytical Services

Quote ID: QBO20060094

Prepared For:

- 35a

Groundwater Investigations LLC 11590 Black Forest Road, Suite 15 Quote Date: Monday, June 29, 2020 Turn Around Time: 10 Working Days

Colorado Springs, CO 80908

Attn: Julia M. Murphy

	1
Project:	
\:_4.	
rolect:	
roject.	
	,
	1
	- 1
	- 1

Matrix	Description	Method	Qty.	Price - each	Total
Water - Drinking	Nitrate/ Nitrite Nitrogen	Calculation	1	\$0.00	\$0.00
Water - Drinking	Fe - Total	EPA 200.7	1	\$12.00	\$12.00
Water - Drinking	Ph	SM 4500-H-B	1	\$12.00	\$12.00
Water - Drinking	Ag - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Al - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Alkalinity	SM 2320-B	1	\$15.00	\$15.00
Water - Drinking	As - Total	EPA 200.8	1	\$15.00	\$15.00
Nater - Drinking	Ba - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Be - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Cd - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Cr - Total	EPA 200.8	1	\$15.00	\$15.00
Nater - Drinking	Hg	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Mn - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Sb - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Se - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	TDS	SM 2540-C	1	\$15.00	\$15.00
Vater - Drinking	TI - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Zn - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Chloride	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Nitrate Nitrogen	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Nitrite Nitrogen	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Sulfate	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Fluoride	EPA 300.0	1	\$18.00	\$18.00
Vater - Drinking	Total Coliform P/A	SM 9223	1	\$23.00	\$23.00
Vater - Drinking	Cyanide-Total	EPA 335.4	1	\$38.00	\$38.00
Vater - Drinking	Gross Alpha/Beta (Sub)	SM 7110-B	1	\$56.16	\$56.16
Vater - Drinking	Radium 226 (Sub)	SM 7500-Ra B	1	\$75.60	\$75.60
Vater - Drinking	Radium 228 (Sub)	EPA Ra-05	1	\$118.80	\$118.80
Shipping	Cooler Shipment - UPS	UPS	1	\$10.00	\$10.00
Shipping	Sample Shipment to Outside Lab	UPS	1	\$30.00	\$30.00



Analytical Results

TASK NO: 210402002

Report To: Julia M. Murphy

Company: Groundwater Investigations LLC

11590 Black Forest Road, Suite 15 Colorado Springs CO 80908 Bill To: Julia M. Murphy

Company: Groundwater Investigations LLC

11590 Black Forest Road, Suite 15 Colorado Springs CO 80908

Task No.: 210402002 Date Received: 4/2/21 Client PO: Date Reported: 4/13/21

Client Project: Romens Subdivision Matrix: Water - Drinking

Lab Number	Customer Sample ID	Sample Date/Time		Sample Date/Time		Test	Result	Method	Date Analyzed
210402002-01C	R0421	4/1/21	9:30 AM	Total Coliform	Present	SM 9223	4/3/21		
				F-Coli	∆hsent	SM 9223	4/3/21		


Abbreviations/ References:

Absent = Coliform Not Detected
Present = Coliform Detected - Chlorination Recommended
Date Analyzed = Date Test Completed

SM = "Standard Methods for the Examination of Water and Wastewater"; APHA; 19th Edition; 1995

Shore Nielson

Chain of Custody Form





Commerce City Lab 10411 Heinz Way **Commerce City CO 80640**

Lakewood Service Center 12860 W. Cedar Dr, Suite 100A Lakewood CO 80228

Phone: 303-659-2313

www.coloradolab.com

Sample Collector Phone:	(719)338-1805	PO No.:																
						- :					Tes	ts Re	eque	sted				1.1
	Sample Matrix (Select O	ne Only)			\$													
Waste Water	Soil	Deinkin - Wiston		ers	Onl			(%)		1 2) ~	\	İ	í	,			
Ground Water	Sludge 🗌	Drinking Water		tain	One	3	10	77		3/2	0 2)			9			
Surface Water				Con	eck (Site	S 5	3.0	Ŋ	4 3	ج اِ ک	5		1	\forall			
Surface Water				No. of Containers	Grab or (Check One Only)	omposite		200	A	MET		18	1	7	7			
Date Time	Sai	nple ID		ž	5 5	ပိ 🤨	0	Ki	Y	36	کالخ	N/	Ť.	. 9	7			
4/1/2/930	720421	Na	2504	1		V												
177701				1			/											
				1													+	
				1														
			/	/					7					\dashv	+-	+++		+
		1+14	03.,	1		- -	-			<u> </u>						+-+	+	+
		Na	OH	1					_	<u> </u>	4_		_	\dashv		+		\bot
				1							V	Y	\ \ <u>\</u>	1/1	4			
				'														
			(a)															
	DER DRONDE	Sladall																+
Instructions:	on Jovage	69977	C/S Info:	L							Seals Pro	esent Y	es 🔲	No 🔲				
KAdd Land	TER DBOZOR		Deliver Via:	Fe	de	X		C/S°C	harge		<i>[</i> Гетр.	1 .	C/Ice	V	Sample	Pres. Yes	И N.	. [7]
Relinquished By:	Date/Time: Received	By: Date/Tim	e: Re	lingu of 3	ished I	By:		Date/	Time		Recei				- mpie	Date/	Time:	<u> </u>



Quotation for Analytical Services

Quote ID: QBO20060094

Prepared For:

- 35a

Groundwater Investigations LLC 11590 Black Forest Road, Suite 15 Quote Date: Monday, June 29, 2020 Turn Around Time: 10 Working Days

Colorado Springs, CO 80908

Attn: Julia M. Murphy

	1
Project:	
\:_4.	
rolect:	
roject.	
	,
	1
	- 1
	- 1

Matrix	Description	Method	Qty.	Price - each	Total
Water - Drinking	Nitrate/ Nitrite Nitrogen	Calculation	1	\$0.00	\$0.00
Water - Drinking	Fe - Total	EPA 200.7	1	\$12.00	\$12.00
Water - Drinking	Ph	SM 4500-H-B	1	\$12.00	\$12.00
Water - Drinking	Ag - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Al - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Alkalinity	SM 2320-B	1	\$15.00	\$15.00
Water - Drinking	As - Total	EPA 200.8	1	\$15.00	\$15.00
Nater - Drinking	Ba - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Be - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Cd - Total	EPA 200.8	1	\$15.00	\$15.00
Water - Drinking	Cr - Total	EPA 200.8	1	\$15.00	\$15.00
Nater - Drinking	Hg	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Mn - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Sb - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Se - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	TDS	SM 2540-C	1	\$15.00	\$15.00
Vater - Drinking	TI - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Zn - Total	EPA 200.8	1	\$15.00	\$15.00
Vater - Drinking	Chloride	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Nitrate Nitrogen	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Nitrite Nitrogen	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Sulfate	EPA 300.0	1	\$17.00	\$17.00
Vater - Drinking	Fluoride	EPA 300.0	1	\$18.00	\$18.00
Vater - Drinking	Total Coliform P/A	SM 9223	1	\$23.00	\$23.00
Vater - Drinking	Cyanide-Total	EPA 335.4	1	\$38.00	\$38.00
Vater - Drinking	Gross Alpha/Beta (Sub)	SM 7110-B	1	\$56.16	\$56.16
Vater - Drinking	Radium 226 (Sub)	SM 7500-Ra B	1	\$75.60	\$75.60
Vater - Drinking	Radium 228 (Sub)	EPA Ra-05	1	\$118.80	\$118.80
Shipping	Cooler Shipment - UPS	UPS	1	\$10.00	\$10.00
Shipping	Sample Shipment to Outside Lab	UPS	1	\$30.00	\$30.00



Customer ID: 20040H Account ID: Z01034 Lab Control ID: 21M01591 Received: Apr 02, 2021 Reported: Apr 23, 2021 Purchase Order No. None Received

Stuart Nielson Colorado Analytical Laboratories, Inc. 10411 Heinz Way Commerce City, CO 80640

ANALYTICAL REPORT

Report may only be copied in its entirety.
Results reported herein relate only to discrete samples submitted by the client. Hazen Research, Inc. does not warrant that the results are representative of anything other than the samples that were received in the laboratory

File: 21M01591 R1.pdf

Jessica Axen
Analytical Laboratories Director

Lab Control ID: 21M01591

Received: Apr 02, 2021 Reported: Apr 23, 2021 Purchase Order No. None Received

Customer ID: 20040H Account ID: Z01034

ANALYTICAL REPORT

Stuart Nielson Colorado Analytical Laboratories, Inc.

La Custom			21M01591-001 210402003- 0)1 - RO421 -	- Romens S	Subdivision		
				sampled or	n 04/01/21 (@ 0900		
				Precision*	Detection		Analysis	
Parameter	Units	Code	Result	+/-	Limit	Method	Date / Time	Analyst
Gross Alpha	pCi/L	Т	^ 89	15	0.1	SM 7110 B	4/7/21 @ 1034	KT
Gross Beta	pCi/L	Т	^ 63	8	7.3	SM 7110 B	4/7/21 @ 1034	KT
Radium-226	pCi/L	Т	NR	-	-	SM 7500-Ra B	-	-
Radium-228	pCi/L	Т	NR	-	-	EPA Ra-05	-	-

NR - Not Requested - Analysis not requested on this sample.

Certification ID's: CO/EPA CO00008

File: 21M01591 R1.pdf

Codes: (T) = Total (D) = Dissolved (S) = Suspended (R) = Total Residual (AR) = As Received < = Less Than

^{*}Variability of the radioactive decay process (counting error) at the 95% confidence level, 1.96 sigma.

[^] Due to the large amount of total or dissolved solids in the sample, reduced aliquots were used for the gross alpha and beta analysis.

Lab Control ID: 21M01591

Received: Apr 02, 2021 Reported: Apr 23, 2021 Purchase Order No. None Received

Customer ID: 20040H Account ID: Z01034

ANALYTICAL REPORT

Stuart Nielson Colorado Analytical Laboratories, Inc.

Lá	ab Sam	ple ID	21M01591-002					
Custom	er Sam	iple ID	210402003-0)1A - RO421	I - Romens	Subdivision		
				sampled or	า 04/01/21 (@ 0900		
				Precision*	Detection		Analysis	
Parameter	Units	Code	Result	+/-	Limit	Method	Date / Time	Analyst
Gross Alpha	pCi/L	Т	NR	-	-	SM 7110 B	-	-
Gross Beta	pCi/L	Т	NR	-	-	SM 7110 B	-	-
Radium-226	pCi/L	Т	2.8	8.0	0.2	SM 7500-Ra B	4/6/21 @ 1430	AS
Radium-228	pCi/L	Т	9.9	1.3	0.2	EPA Ra-05	4/19/21 @ 1033	JR

NR - Not Requested - Analysis not requested on this sample.

Certification ID's: CO/EPA CO00008

File: 21M01591 R1.pdf

Codes: (T) = Total (D) = Dissolved (S) = Suspended (R) = Total Residual (AR) = As Received < = Less Than

^{*}Variability of the radioactive decay process (counting error) at the 95% confidence level, 1.96 sigma.

[^] Due to the large amount of total or dissolved solids in the sample, reduced aliquots were used for the gross alpha and beta analysis.

Batch QC Summary Form

Analyte: Gross Alpha

Control Standard/LFB: ID: C-11 pCi/mL: 57.4 (use 1 diluted)

Spike Solution: ID: C-11 pCi/mL: 57.4 (use 1 mL)

Spike Recovery Calculation: Sample: Tap*

Calculation: (50.7) (1.000) - (0.3) (0.200) x 100 = 88%

Date:

04/07/2021

Batch QC Evaluation:

Parameter	Criteria	Pass	Fail	N/A
Control Std./LFB	+/- 30 %	Х		
Spike Recovery	70 - 130 %	Х		
Blank	< or = 3 x Uncertainty	Х		
Duplicate 1	95% confidence interval overlap	Х		
Duplicate 2 *	95% confidence interval overlap			х

^{*} Required for batch size greater than 10 samples.

Conc	lusions
COLIC	usions

X	Batch QC Passes**
	Batch QC Fails
	Batch QC Passes, with exceptions**:
	Reruns Required:
	Narrative:

Batch Listing by Lab Control Number:

21M01586 21M01589		
21M01591		
21M01603		
21M01604		<u>Evaluator:</u>
21M01609		Jynnea Rockwell_
		O.g. view
	<u></u>	04/08/2021
		Date

^{**}All QC data provided in this section of the report met the acceptance criteria specified in the analytical methods and procedures. State Maximum Contamination Levels (MCLs) are not evaluted in this report.

Batch QC Summary Form

Analyte: Gross Beta

Control Standard/LFB: ID: C-11 pCi/mL: 44 (use 1 diluted)

Spike Solution: ID: C-11 pCi/mL: 44 (use 1 mL)

Spike Recovery Calculation: Sample: Tap*

Calculation: (38.0) (1.000) - (0.0) (0.200) x 100 = 86%

Date:

04/07/2021

Batch QC Evaluation:

Parameter	Criteria	Pass	Fail	N/A
Control Std./LFB	+/- 20 %	Х		
Spike Recovery	80 - 120 %	Х		
Blank	< or = 3 x Uncertainty	Х		
Duplicate 1	95% confidence interval overlap	Х		
Duplicate 2 *	95% confidence interval overlap			х

^{*} Required for batch size greater than 10 samples.

Conc	lusions
COLIC	usions

X	Batch QC Passes**
	Batch QC Fails
	Batch QC Passes, with exceptions**:
	Reruns Required:
	Narrative:

Batch Listing by Lab Control Number:

21M01586 21M01589 21M01591	
21M01603 21M01604	 Evaluator:
21M01609	 Tynnea Rockwell
	04/08/2021
	Date

^{**}All QC data provided in this section of the report met the acceptance criteria specified in the analytical methods and procedures. State Maximum Contamination Levels (MCLs) are not evaluted in this report.

Batch QC Summary Form

Analyte: Radium-226

Control Standard/LFB: ID: NBL-6A pCi/mL: 23 (use 2 diluted)

Spike Solution: ID: NBL-6A pCi/mL: 23 (use 2 mL)

Spike Recovery Calculation: Sample: 21M01575-2a

Calculation: (54.6) (0.980) - (2.5) (0.950) x 100 = 111%

Date:

04/06/2021

Batch QC Evaluation:

Parameter	Criteria	Pass	Fail	N/A
Control Std./LFB	+/- 20 %	Х		
Spike Recovery	80 - 120 %	Х		
Blank	< or = 3 x Uncertainty	Х		
Duplicate 1	95% confidence interval overlap	Х		
Duplicate 2 *	95% confidence interval overlap	х		

^{*} Required for batch size greater than 10 samples.

('ANA	LICIONO
COLIC	lusions:

X	Batch QC Passes**
	Batch QC Fails
	Batch QC Passes, with exceptions**:
	Reruns Required:
	Narrative:

Batch Listing by Lab Control Number:

21M01575	21M01609	
21M01580	21M01617	
21M01592	21M01618	
21M01599	21M01621	
21M01551	21M01619	Evaluator:
21M01570	21M01620	
21M01591		Jynnea Kextwell
21M01603		Oly Wild
21M01604		U
21M01612		04/09/2021
		Date

page 6 of 8

^{**}All QC data provided in this section of the report met the acceptance criteria specified in the analytical methods and procedures. State Maximum Contamination Levels (MCLs) are not evaluted in this report.

Batch QC Summary Form

Analyte: Radium-228

Control Standard/LFB: ID: NBL-7A pCi/mL: 13 (use 10 diluted)

Spike Solution: ID: NBL-7A pCi/mL: 13 (use 10 mL)

Spike Recovery Calculation: Sample: 21M01652

Calculation: (140.8) (0.990) - (4.0) (0.990) x 100 = 104%

Date:

04/19/2021

Batch QC Evaluation:

Parameter	Criteria	Pass	Fail	N/A
Control Std./LFB	+/- 20 %	Х		
Spike Recovery	80 - 120 %	Х		
Blank	< or = 3 x Uncertainty	Х		
Duplicate 1	95% confidence interval overlap	Х		
Duplicate 2 *	95% confidence interval overlap			х

^{*} Required for batch size greater than 10 samples.


\sim			
('An	~ 11.16	าเกก	0
Con	เมเม	うしい ロ	

Х	Batch QC Passes**
	Batch QC Fails
	Batch QC Passes, with exceptions**:
	Reruns Required:
	Narrative:

Batch Listing by Lab Control Number:

21M01575 21M01591 21M01592 21M01599 21M01603 21M01652	Evaluator: Tynnea Rodwell
21M01665	04/22/2021
	 Date

^{**}All QC data provided in this section of the report met the acceptance criteria specified in the analytical methods and procedures. State Maximum Contamination Levels (MCLs) are not evaluted in this report.



1 of 1



Sub-Lab Chain of Custody Form

	LABORATORIES, INC.																<u>21</u>	Mols	591
Report To Informa Company Name: Report To:	Colorado Analytical Laboratory Stuart Nielson	Bill To Inform	nation (If different from r	report to)				***************************************		Projec Romer			risio	n					
E-Mail: stuartnielson@coloradolab.com Address: 10411 Heinz Way Commerce City, CO 80640 Phone: 303-659-2313		Address:	210402003					Compliance Samples: Yes Submit Data to CDPHE: Yes											
						Tes	ts I	Req	ues	ted							**		
				Gross Alpha/Beta (Sub) Radium 226 (Sub)	Badisson 228 (Suh)										30 30 30 30 30 30 30 30	THE REPORT OF THE PARTY OF THE			
Sample Date/Time	1		Matrix									q						ntainer ⁻	
4/1/21 9:00 A	AM 210402003-01 - R0421		Water - Ground											- dansaturined				Cylinder -	1
4/1/21 9:00 A	AM 210402003-01A - R0421		Water - Ground	NII	X												3 - 1L	Cylinder -	HNO3
Sany	ples contain fine:	Sedement																	
Relinquished by: (Signature)	Date: Time: Received b 4/2/2/ (Signature)	()	Date: Time: 4001	Relinquis (Signatur		by:	3). 3).	D	ate:	Time:		Recei Sign:				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		Date	: Time
Fed &	1779 5422 822		Recid presid	,						gang garindan den kelebe							- Almain	Page 1 o	f 1

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4275-BD

AQUIFER: Laramie-Fox Hills

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Laramie-Fox Hills Aquifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Laramie-Fox Hills aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 1,260 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 15 percent.

Determination No.: 4275-BD Page 2

Aquifer: Laramie-Fox Hills
Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 210 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that none of the groundwater in the Aquifer underlying the Overlying Land has been either previously determined to be allocated by the Commission, has been permitted for withdrawal by large capacity wells that have rights that were initiated prior to November 19, 1973 that are subject to section 37-90-107(7)(b), or has been permitted for withdrawal by existing small capacity wells withdrawing water under permits issued pursuant to section 37-90-105, C.R.S. The amount of designated groundwater in the Aquifer underlying the Overlying Land that is available for allocation in this Determination is 1,260 acre-feet.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 1,260 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 12.6 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is nontributary groundwater as defined in Rule 4.2.22 of the Designated Basin Rules.

Determination No.: 4275-BD Page 3

Aquifer: Laramie-Fox Hills
Applicant: Romens Living Trust

Pursuant to the Rules, no more than 98% of the amount of the groundwater in the Aquifer underlying the Overlying Land withdrawn annually shall be consumed.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Laramie-Fox Hills Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 1,260 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.
- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 1,260 acre-feet, less any amount of the Underlying Groundwater allocated

-BD Page 4

Determination No.: 4275-BD Aquifer: Laramie-Fox Hills Applicant: Romens Living Trust

herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.

- b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
- c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
- d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- e. No more than 98% of the amount of Underlying Groundwater withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the Underlying Groundwater withdrawn annually is being consumed.
- f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.
- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Laramie-Fox Hills Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

Determination No.: 4275-BD Aquifer: Laramie-Fox Hills Applicant: Romens Living Trust

- k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.
- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 21. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4275-BD.doc

Joanna Williams, P.E. Water Resource Engineer

ATTACHMENT 1

Exhibit A

Determination No. 4275-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 DEPARTMENT OF NATURAL RESOURCES (1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, <u>www.colorado.gov/water</u>, dwrpermitsonline@state.co.us

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

RCVD DWR 08/03/2021

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

4 ADDLICANT IN	FORMATION				
1. APPLICANT IN Name of Applica					
Name of Applicat	Romens Living Trust				
Mailing Address		City	· · · · · · · · · · · · · · · · · · ·	State	Zip Code
	5135 Coneflower Lane	Colorado S	prings	Colorado	80917
Telephone Numb	per (include area code)		Email		
	719-331-3310		ajlolly	@msn.com	
2. AQUIFER					
2. AQUIFER	Laramie Fox Hills				
3. CLAIM OF OW	NERSHIP - I hereby claim that I am	the owner o	f the following	described property, as ev	videnced by
				-14	
the attached co	py of a deed recorded in the county	in which the	property is loc	atea.	
Number of acre	s: 40	in the co	unty of:	I Paso	
described as fo	llows (insert legal description).				
NE1/4 of the NE	E1/4 of Section 24 Township 11 Sou	th Range 64	West of the 6	th PM	
TVE 174 OF BIOTYL	2174 Or Oction 24 Township 11 Cou	an, raango o i	77000 01 010 0		
					· ·
-					
	7317 16				
- I further clain	n that the right to withdraw the grou	ndwater in th	e aquifer und	erlying the above describ	ed property
	reserved by another, nor has conse				
4. THE APPLICA	NT MUST PROVIDE – a Verification	of Notice of	Application (for	orm no. GWS-43) (see ins	structions for
exceptions).	Exhibit A				
	Sign or enter name(s) of applicant(s) of				
	cond degree, which is punishable as a cl				have read the
	n, know the contents thereof, and state	4		edge.	
Ciamatura.	10.1 1 2	To To		Data: O 2 2	0
Signature: (2	delaida Komens,	VILLO CE		Date: Jene 30,	1021
					•
Print name and title:	Adelaida Romens, Trustee			-	
i int hame and the.					

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4276-BD

AQUIFER: Arapahoe

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Arapahoe Aguifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Arapahoe aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 1,500 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 17 percent.

Determination No.: 4276-BD Page 2

Aguifer: Arapahoe

Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 220 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that none of the groundwater in the Aquifer underlying the Overlying Land has been either previously determined to be allocated by the Commission, has been permitted for withdrawal by large capacity wells that have rights that were initiated prior to November 19, 1973 that are subject to section 37-90-107(7)(b), or has been permitted for withdrawal by existing small capacity wells withdrawing water under permits issued pursuant to section 37-90-105, C.R.S. The amount of designated groundwater in the Aquifer underlying the Overlying Land that is available for allocation in this Determination is 1,500 acre-feet.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 1,500 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 15 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is nontributary groundwater as defined in Rule 4.2.22 of the Designated Basin Rules.

Aguifer: Arapahoe

Applicant: Romens Living Trust

Pursuant to the Rules, no more than 98% of the amount of the groundwater in the Aquifer underlying the Overlying Land withdrawn annually shall be consumed.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Arapahoe Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 1,500 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.
- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 1,500 acre-feet, less any amount of the Underlying Groundwater allocated

Aquifer: Arapahoe

Applicant: Romens Living Trust

herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.

- b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
- c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
- d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- e. No more than 98% of the amount of Underlying Groundwater withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the Underlying Groundwater withdrawn annually is being consumed.
- f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.
- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Arapahoe Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

Aquifer: Arapahoe

Applicant: Romens Living Trust

k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.

- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 21. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4276-BD.doc

Joanna Williams, P.E. Water Resource Engineer Page 5

ATTACHMENT 1

Exhibit A

Determination No. 4276-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 DEPARTMENT OF NATURAL RESOURCES (1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, www.colorado.gov/water, dwrpermitsonline@state.co.us

RCVD DWR 08/03/2021

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

1. APPLICANT INFORMATION				
Name of Applicant				
Romens Living Trust				
Mailing Address	City		State	Zip Code
5135 Coneflower Lane	Colorado S	prings	Colorado	80917
Telephone Number (include area code)		Email		
719-331-3310			lolly@msn.com	
A AGUIETO				
2. AQUIFER Arapahoe				
3. CLAIM OF OWNERSHIP - I hereby claim that I a	m the owner of	the follow	ring described property, as evide	enced by
the attached copy of a deed recorded in the county	v in which the r	ronerty is	Incated	
Number of acres: 40	in the cou	unty of:	El Paso	
described as follows (insert legal description).				
NE1/4 of the NE1/4 of Section 24 Township 11 So	uth Range 64	West of th	ne 6th PM	
NE 1/4 of the NE 1/4 of Section 24 Township 11 So	dui, italige o-	West of a	ic out i w	1
- I further claim that the right to withdraw the gro	undwater in th	e aquifer i	inderlying the above described	property
has not been reserved by another, nor has cons				p, op oy
4. THE APPLICANT MUST PROVIDE – a Verification	on of Notice of	Application	n (form no. GWS-43) (see instru	ctions for
exceptions). Exhibit A				
5. SIGNATURE - Sign or enter name(s) of applicant(s)	or authorized ag	gent. The	making of false statements herein	constitutes
periury in the second degree, which is punishable as a	class 1 misdeme	anor pursu	ant to C.R.S. 24-4-104(13)(a). I hav	e read the
statements herein, know the contents thereof, and state			nowledge.	
Signature: allelacke Kemens	truste	e	Date: June 30, 20	21
Print name and title: Adelaida Romens, Trustee			€CRI	
Fillit Hailie and due.				

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4277-BD

AQUIFER: Denver

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Denver Aquifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Denver aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 2,040 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 17 percent.

Aquifer: Denver

Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 300 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that none of the groundwater in the Aquifer underlying the Overlying Land has been either previously determined to be allocated by the Commission, has been permitted for withdrawal by large capacity wells that have rights that were initiated prior to November 19, 1973 that are subject to section 37-90-107(7)(b), or has been permitted for withdrawal by existing small capacity wells withdrawing water under permits issued pursuant to section 37-90-105, C.R.S. The amount of designated groundwater in the Aquifer underlying the Overlying Land that is available for allocation in this Determination is 2,040 acre-feet.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 2,040 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 20.4 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is nontributary groundwater as defined in Rule 4.2.22 of the Designated Basin Rules.

Aquifer: Denver

Applicant: Romens Living Trust

Pursuant to the Rules, no more than 98% of the amount of the groundwater in the Aquifer underlying the Overlying Land withdrawn annually shall be consumed.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Denver Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 2,040 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.
- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 2,040 acre-feet, less any amount of the Underlying Groundwater allocated

Aquifer: Denver

Applicant: Romens Living Trust

herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.

- b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
- c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
- d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- e. No more than 98% of the amount of Underlying Groundwater withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the Underlying Groundwater withdrawn annually is being consumed.
- f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.
- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Denver Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

Determination No.: 4277-BD

Aguifer: Denver

Applicant: Romens Living Trust

k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.

- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 21. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4277-BD.doc

Joanna Williams, P.E. Water Resource Engineer Page 5

ATTACHMENT 1

Exhibit A

Determination No. 4277-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 DEPARTMENT OF NATURAL RESOURCES

(1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, www.colorado.gov/water, dwrpermitsonline@state.co.us

RCVD DWR 08/03/2021

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

1. APPLICANT INFORMATION				
Name of Applicant				
Romens Living Trust				
Mailing Address	City		State	Zip Code
5135 Coneflower Lane	Colorado S	prings	Colorado	80917
Telephone Number (include area code)		Email		
719-331-3310		aj	lolly@msn.com	
2. AQUIFER Deriver				
Denver				
a at any or ountrooms. The sales that I a	- the aumor of	f the follow	ing described property as	ovidenced by
3. CLAIM OF OWNERSHIP - I hereby claim that I a	im the owner of	i the lollow	ing described property, as	s evidenced by
the attached copy of a deed recorded in the count	y in which the p	property is	located.	
Number of acres: 40	in the co	unty of	El Paso	
Number of acres	iii tile coi	unity on		
described as follows (insert legal description).				
NE1/4 of the NE1/4 of Section 24 Township 11 So	outh Range 64	West of th	e 6th PM	
NE 1/4 OF BIE NE 1/4 OF OCCURN 24 TOWNSHIP TO SE	dai, rango o .			
3 				
				
- I further claim that the right to withdraw the gro	oundwater in th	e aquifer i	underlying the above desc	cribed property
has not been reserved by another, nor has con-	sent been give	n to anothe	er for the right to its withdr	awal.
4. THE APPLICANT MUST PROVIDE – a Verification	on of Notice of	Application	n (form no. GWS-43) (see	instructions for
exceptions). Exhibit A				
5. SIGNATURE – Sign or enter name(s) of applicant(s) perjury in the second degree, which is punishable as a	or authorized a	gent. The	making of false statements h	erein constitutes
statements herein, know the contents thereof, and state	te that they are tr	ue to mv kr	ant to C.N.S. 24-4-104(15)(a nowledge.). I liave lead tile
Signature: adelorda Komens	- Trust	re	Date: June 30,	2021
	,			
Print name and title: Adelaida Romens, Trustee			~	
Finit name and due.				

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4278-BD

AQUIFER: Dawson

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Dawson Aquifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Dawson aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 880 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 20 percent.

Aquifer: Dawson

Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 110 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that a well operating pursuant to section 37-90-105, C.R.S., (i.e. a small-capacity well), permit no. 195628, is located on the Overlying Land and is permitted to withdraw 1 acre-foot per year of groundwater from the Aquifer from beneath the Overlying Land. The applicant has indicated that permit no. 195628 will be cancelled and the well re-permitted to operate pursuant to this Determination. The amount of water considered to have been historically withdrawn from the aquifer by this well is 25 acre-feet. In applying Rule 5.3.2.5 of the Designated Basin Rules to computing the amount of water available for allocation in this Determination, the amount of groundwater in the Aquifer underlying the Overlying Land available for allocation in this Determination is reduced by 25 acre-feet to 855 acre-feet. Except for that well, review of the records in the Office of the State Engineer finds no other previous allocations or permitted withdrawals from the Aquifer underlying the Overlying Land.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 855 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 8.55 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will, within one hundred years, deplete the flow of a natural steam or an alluvial aquifer at an annual

Aquifer: Dawson

Applicant: Romens Living Trust

rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is considered to be not-nontributary groundwater as defined in Rule 4.2.23 of the Designated Basin Rules. Withdrawal of water from the Aquifer underlying the Overlying Land would impact the alluvial aquifer of the Upper Black Squirrel Creek Designated Groundwater Basin, which has been determined to be over-appropriated. Commission approval of a replacement plan pursuant to section 37-90-107.5, C.R.S., and Rule 5.6 of the Designated Basin Rules, that provides for the replacement of the actual depletion to the alluvial aquifer and is adequate to prevent any material injury to existing water rights of other appropriators, is required prior to approval of well permits for wells to be located on this land area to withdraw the groundwater in the Aquifer underlying the Overlying Land. Pursuant to the Rules the replacement plan shall provide for the depletion of the alluvial water for the first 100 years due to all previous pumping, and if pumping continues beyond 100 years shall replace actual impact until pumping ceases, assuming water table conditions in the Aquifer.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Dawson Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 855 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information

Aquifer: Dawson

Applicant: Romens Living Trust

obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.

- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 855 acre-feet, less any amount of the Underlying Groundwater allocated herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.
 - b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
 - c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
 - d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
 - e. Commission approval of a replacement plan, that provides for the replacement of the actual depletion to the alluvial aquifer and is adequate to prevent any material injury to existing water rights of other appropriators in the alluvial aquifer, is required prior to approval of well permits that allow the withdraw of the Underlying Groundwater. The replacement plan shall provide for the depletion of the alluvial water for the first 100 years due to all previous pumping, and if pumping continues beyond 100 years shall replace actual impact until pumping ceases, assuming water table conditions in the Aquifer.
 - f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system

Aquifer: Dawson

Applicant: Romens Living Trust

into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.

- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Dawson Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.
- k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.
- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. Existing well permit no. 195628 must be canceled and a new permit issued for that well to operate pursuant to this Determination.
- 21. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 22. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Aquifer: Dawson

Applicant: Romens Living Trust

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4278-BD.doc

By: Joanna Williams, P.E. Water Resource Engineer

Page 6

ATTACHMENT 1

Exhibit A

Determination No. 4278-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 **DEPARTMENT OF NATURAL RESOURCES** (1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, www.colorado.gov/water, dwrpermitsonline@state.co.us

10014221

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

RCVD DWR 08/03/2021

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

1. APPLICANT INFORMATION			
Name of Applicant			
Romens Living Trust			
Mailing Address	City	State	Zip Code
5135 Coneflower Lane	Colorado Springs	Colorado	80917
Telephone Number (include area code)	Email		
719-331-3310	1	ajlolly@msn.com	
2. AQUIFER Dawson			
3. CLAIM OF OWNERSHIP - I hereby claim that	at I am the owner of the follo	wing described property, as	evidenced by
the attached copy of a deed recorded in the c	ounty in which the property i	is located.	
Number of acres: 40	in the county of:	El Paso	
described as follows (insert legal description).			
, , ,		the CAL DAA	
NE1/4 of the NE1/4 of Section 24 Township 1	1 South, Range 64 West of	tne otn PM	
*			
			-
- I further claim that the right to withdraw the	e groundwater in the aquifer	underlying the above desc	ribed property
has not been reserved by another, nor has			
4. THE APPLICANT MUST PROVIDE – a Verifi	cation of Notice of Application	on (form no. GWS-43) (see	instructions for
exceptions). Exhibit A			
 SIGNATURE – Sign or enter name(s) of application perjury in the second degree, which is punishable statements herein, know the contents thereof, and 	as a class 1 misdemeanor purs	suant to C.R.S. 24-4-104(13)(a)	
Signature: Adelaida Romenz,	trustee	Date: June 30	, 2021
Print name and title: Adelaida Romens, Trustee			

Replacement Plan Accounting Reporting Form

Determination of Water Right Number: 4278-BD

Aquifer from which wells produce water: Dawson

Submit to: Colorado Ground Water Commission, 1313 Sherman St., Room 821, Denver, CO 80203

Person responsible for gathering and submitting data (required) Name: Email address: Mailing Address: Telephone: Calendar year being reported 1: Calendar year operation of the plan was initiated 2: Year number of operation of the plan 3: Annual replacement water requirement (acre-feet/year) 4: Meter Meter Meter Meter Meter Metered initiation of Reading at Reading at Reading at Metered reading at pumping operation of operation operation of operation operation operation operation operation operation operation operation operation operation operation operation operation operation operation operation operation operati

								Pumping of this
						Date of		well since
		Meter	Meter			Meter	Metered	initiation of
		Reading at	Reading at	Metered		reading at	pumping	operation of
Well Permit		beginning of	end of year	pumping	Meter's	end of year	this year 12	the plan 13
no. ⁵	Address of property served by this well ⁶	year ⁷	8	this year ⁹	Units 10	11	(acre-feet)	(acre-feet)
		l	1		I	I	1	

Well Permit	Address of property served by this well ⁶	Number of Ocupied Single Family Dwellings ¹⁴	Amount of Irrigated Land ¹⁵ (ft ²)	Number of Large Domestic Animals ¹⁶	Estimated Return Flow ¹⁷ (acre-feet)
110.	ridaress of property served by this well	Divenings	(10)	7.11111013	(dere reet)

Conversion rates:

- 1 acre-foot equals 325,851 gallons
- 1 acre-foot equals 43,560 cubic feet

See reverse side for notes.

Notes:

- 1) Calendar year for which this report is being submitted.
- 2) The calendar year when the first well permitted pursuant to this plan was constructed, or when the first permit for an existing well was issued pursuant to the plan. Once the plan has been initiated this year will not change.
- 3) The number of years after initiation of operation of the plan. The year of initiation is year number 1.
- 4) Equal to "Annual Depletion" on Exhibit A of the Replacement Plan.
- 5) The well permit number of the well being operated pursuant to the plan.
- 6) The address of the property served by the well.
- 7) The reading on the meter at the beginning of the year. Equal to reading on the meter at end of year on last year's reporting form. For the first year of operation of a well this is the meter reading prior to pumping under the plan.
- 8) Reading on the meter at the end of the year.
- 9) The amount of water pumped by the well this year. Equal to the reading on the meter at the end of this year minus reading on the meter at the beginning of the year. If a new meter was installed during the year, explain that fact and report the sum of the readings of the old and new meters over the year.
- 10) Units of measurement shown on the meter.
- 11) Date that the meter was read this year. This should be on December 31st or as close to that date as possible.
- 12) The amount pumped this year, reported in acre-feet.
- 13) The cumulative amount of water pumped by this well (and all previous wells serving this address) since initiation of operation of the plan. Equal to "Pumping of this well since initiation of operation of the plan" on last year's reporting form plus "Pumping of this well this year" on this year's reporting form.
- 14) The number of occuped single family dwellings supplied by the well.
- 15) The amount of irrigated land supplied by the well.
- 16) The number of large domestic animals supplied by the well.
- 17) Return flow consists of water recharged into the alluvial aquifer by way of non-evaporative septic and leaching field sytem discharges, which are estimated as 0.25 acre-feet per year (90 percent of the amount of water supplied to in-house uses by each well supplying an occupied dwelling). Refer to the Findings and Orders of the approved replacement plan.

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR REPLACEMENT PLAN TO ALLOW THE WITHDRAWAL OF GROUNDWATER FROM THE DAWSON AQUIFER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN.

REPLACEMENT PLAN NO. 4278-RP

FOR DETERMINATION OF WATER RIGHT NO. 4278-BD

AQUIFER: DAWSON

APPLICANT: ROMENS LIVING TRUST

In compliance with section 37-90-107.5, C.R.S. and the Designated Basin Rules, 2 CCR 410-1 (Rules or Rule), Romens Living Trust (Applicant) submitted an application for a replacement plan to allow the withdrawal of groundwater from the Dawson Aquifer that has been allocated by Determination of Water Right No. 4278-BD.

FINDINGS

- 1. Pursuant to section 37-90-107(7), C.R.S., in a Findings and Order dated January 5, 2022, the Ground Water Commission (Commission) approved a Determination of a Right to an Allocation of Groundwater, No. 4278-BD, from the Dawson Aquifer (Aquifer), summarized as follows.
 - a. The determination quantified an amount of water from beneath 40 acres of overlying land described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land).
 - b. The amount of water in the aquifer that was allocated was 855 acre-feet, and the allowed average annual amount of groundwater to be withdrawn from the aquifer was limited to 8.55 acre-feet per year (subject to adjustment by the Commission to conform to actual local aquifer characteristics).
 - c. The use of groundwater is limited to the following beneficial uses: domestic including in-house use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage.
 - d. Withdrawal of the subject groundwater will, within one hundred years, deplete the flow of a natural stream or its alluvial aquifer at an annual rate greater than onetenth of one percent of the annual rate of withdrawal, the groundwater is considered to be not-nontributary, and Commission approval of a replacement plan providing for actual depletion of affected alluvial aquifers and adequate to prevent any material injury to existing water rights in such alluvial aquifers is required prior to approval of well permits for wells to withdraw the subject groundwater.
- 2. The subject water is Designated Groundwater located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the withdrawal of the water by large capacity wells that are permitted pursuant to section 37-90-107(7).
- 3. Withdrawal of the subject groundwater would deplete the alluvial aguifer of the Kiowa-Bijou

Replacement Plan - Determination No.: 4278-BD

Aquifer: Dawson

Applicant: Romens Living Trust

Designated Groundwater Basin, the alluvial aquifer of the Upper Big Sandy Designated Groundwater Basin and the alluvial aquifer of the Upper Black Squirrel Creek Designated Groundwater Basin, all of which, according to Rules 5.2.4.2, 5.2.7.2 and 5.2.6.2, respectively, have been determined to be over appropriated. Such depletion would unreasonably impair existing large capacity alluvial rights withdrawing water from those alluvial aquifers.

Page 2

- 4. Pursuant to Rule 5.6.1.A this plan must be adequate to prevent any material injury to water rights of other appropriators, which for purposes of this plan means large capacity wells withdrawing water from the alluvial aquifer of the Kiowa-Bijou Designated Groundwater Basin, the alluvial aquifer of the Upper Big Sandy Designated Groundwater Basin and the alluvial aquifer of the Upper Black Squirrel Creek Designated Groundwater Basin.
- 5. Pursuant to Rule 5.3.6.2(C) the amount of replacement water shall provide for the depletion of alluvial water for the first 100 years due to all previous pumping and if pumping continues beyond 100 years, shall replace actual impact until pumping ceases.
- 6. The application for the replacement plan was received by the Commission on August 3, 2021.
- 7. The Applicant proposes to divert 2.85 acre-feet annually from the Dawson Aquifer for a period of 300 years. The Dawson aquifer water will be withdrawn through one or more wells to be located on seven (7) residential lots. Each Dawson Aquifer well is proposed to divert 0.407 acre-feet of water annually for domestic including in-house use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The land on which the wells will be located is the Overlying Land described above.
- 8. At a continuous withdrawal of 2.85 acre-feet annually for 300 years, depletions to the alluvial aquifer systems of the Kiowa-Bijou Designated Groundwater Basin, Upper Big Sandy Designated Groundwater Basin and Upper Black Squirrel Creek Designated Groundwater Basin would steadily increase to 0.142 acre-feet per year in the 300th year, which is equal to 4.98% of pumping, as shown in Exhibit A.
- 9. The Applicant proposes to provide 1.260 acre-feet per year of replacement water to the alluvial aquifer system of the Upper Black Squirrel Creek Designated Groundwater Basin. The proposed source of replacement water is septic return flows from the in-house use of the groundwater to be pumped under the plan. The Applicant estimates that return flows from each lot will consist of 90% of the water used for in-house purposes. Assuming each lot uses a total annual amount for in-house use of 0.20 acre-feet, the return flow per lot would be 0.18 acre-feet annually, and the return flows under the plan will total 1.260 acre-feet per year for all seven (7) lots at full build out.
- 10. The subject property is located within the drainage of West Bijou Creek, and the return flows will flow to the alluvial aquifer of the Kiowa-Bijou Designated Groundwater Basin. The Applicant proposes to aggregate all replacements to the drainage in which the well or wells will operate, in accordance with Guideline 2007-1.
- 11. Pursuant to Rule 5.6.1.B this plan must be adequate to prevent unreasonable impairment of water quality. Pursuant to Rule 5.6.1.B.1.b, if the replacement source water is from an onsite wastewater treatment system permitted by a local health agency and the applicant demonstrates the source is in compliance with that permit there shall be a rebuttable presumption of no unreasonable impairment of water quality.

Replacement Plan - Determination No.: 4278-BD

Aquifer: Dawson

Applicant: Romens Living Trust

12. Pursuant to Rule 5.6.1.C this plan, including the proposed uses of the water withdrawn pursuant to the plan, must not be speculative, and must be technically and financially feasible and within the Applicant's ability to complete. The plan, including the proposed uses of the water withdrawn pursuant to the plan, is not speculative. The plan appears technically and financially feasible and within the Applicant's ability to complete.

Page 3

- 13. Pursuant to Rule 5.6.1.D this plan must be able to be operated and administered on an ongoing and reliable basis. The plan appears to be able to be operated and administered on an ongoing and reliable basis.
- 14. Pursuant to Rule 5.6.1.F replacement source water must be physically and legally available in time, place and amount to prevent material injury. As determined in Determination of Water Right No. 4278-BD water is currently available in the amounts and for the number of years proposed to be diverted.
- 15. Pursuant to Rule 5.6.1.G the replacement source water must be legally available for use. Records in this office indicate that the Applicant controls the water right to be used as the source of replacement water, consisting of Determination of Water Right No. 4278-BD, and such water is legally available for use pursuant to this plan.
- 16. In accordance with Rule 5.6.4 the application was referred to the Upper Black Squirrel Creek Ground Water Management District on October 25, 2021. No response was received from the District.
- 17. In accordance with sections 37-90-107.5 and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.
- 18. According to Rule 5.6.1:
 - a. The Applicant has the burden of proving the adequacy of the plan in all respects.
 - b. If the applicant meets its burden of proof, the Commission shall grant approval of the plan which shall include any terms and conditions established the Commission.
- 19. The Commission Staff has evaluated the application pursuant to section 37-90-107.5, and the requirements of Rule 5.3.6.2(C) and Rule 5.6, finds that the requirements have been meet, and the plan may be approved to allow diversions from the Dawson Aquifer if operated subject to the conditions given below.

ORDER

In accordance with section 37-90-107.5, and the Designated Basin Rules, the Colorado Ground Water Commission orders that the application for a replacement plan to allow the withdrawal of groundwater from the Dawson Aquifer underlying 40 acres that are the subject of Determination of Water Right no. 4278-BD is approved subject to the following conditions:

20. The Dawson aquifer water will be withdrawn through one or more wells to be located on seven (7) residential lots. The allowed use of groundwater for each well under this plan is domestic including in-house use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The land on which the wells will be located is the Overlying

Replacement Plan - Determination No.: 4278-BD

Aquifer: Dawson

Applicant: Romens Living Trust

Land described above.

21. The allowed annual amount of groundwater to be withdrawn from the Aquifer by all wells operating under this plan shall not exceed 2.85 acre-feet. The allowed annual amount of water to be withdrawn from each on-lot well shall not exceed 0.407 acre-feet.

- 22. A totalizing flow meter shall be installed on each well. The well owner shall maintain the meter in good working order.
- 23. Permanent records of all withdrawals of groundwater from each well shall be recorded at least annually by the well owners, permanently maintained, and provided to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.
- 24. Pumping under this plan is limited to a period of 300 years. The year of first use of this replacement plan shall be the calendar year of construction of a well permitted pursuant to this plan or permitting of an existing well pursuant to the plan.
- 25. Return flows from in-house use of groundwater shall occur through individual on-lot non-evaporative septic systems located within the 40 acres of Overlying Land that are the subject of Determination of Water Right No. 4278-BD. The septic systems must be constructed and operated in compliance with a permit issued by a local health agency.
- 26. Replacement of depletions must be provided annually in the acre-feet amounts shown in Exhibit A. Annual replacement requirements may be computed by pro-rating between the values given on Exhibit A, or for simplicity may be taken as the amount shown in the next succeeding 5 year increment.
- 27. The Applicant or their successor(s) are responsible for ensuring that replacement water is provided to the alluvial aquifer as required by this plan. The annual replacement requirement and the annual amount of replacement water provided shall be calculated and reported on a form acceptable to the Commission. The annual amount of replacement water provided must be no less than the annual replacement requirement on a yearly basis. No credit shall be claimed by the Applicant for an oversupply of replacement water provided to the alluvium during previous years.
- 28. The Applicant must provide the required annual amount of replacement water for the first 100 years, or for as long as a well is operated pursuant to this plan, whichever is longer.
- 29. To assure adequate return flows, at least one well must be serving the in-house uses for an occupied dwelling that is generating return flows via a non-evaporative septic system before any other use is allowed.
- 30. So long as at least one well continues to pump and supply the in-house uses for an occupied dwelling, the plan's required replacement obligations, shown in Exhibit A, will be met. Should all wells cease pumping for in-house use within the first 100 years an amended or alternate replacement plan must be obtained that will replace actual depletions to the alluvial aquifer so as to prevent any material injury to water rights of other appropriators.
- 31. The Applicant (and their successors) must gather and maintain permanent records of all information pertaining to operation of this plan, which shall include, but is not be limited to, those items identified below. The Applicant must submit records to the Commission and the Upper Black Squirrel Creek Ground Water Management District on forms acceptable to the

Page 4

Aquifer: Dawson

Applicant: Romens Living Trust

Commission, on an annual basis for the previous calendar year, by February 15th of the following year.

- a. Identification of all well permits issued and wells constructed under this plan.
- b. The amount of water diverted by each well and all wells in total, both annually and cumulatively since operation of the plan began.
- c. The number of occupied dwellings served by each well.
- d. The return flows occurring from use of all wells operating under the plan, assuming 0.18 acre-feet per year per occupied single family dwelling (90% of the water used for in-house purposes) enters the alluvial aquifer as replacement water.
- e. Any other information the Commission deems relevant and necessary to operation, monitoring, accounting, or administration of the plan.
- 32. The Applicant (and their successors) are fully responsible for the operation, monitoring, and accounting of the replacement plan. In the event a lot with a well permitted or operating pursuant to this plan is sold, identification of the well that was sold and evidence that the new owner has been notified of their responsibilities under the replacement plan shall accompany that year's accounting.
- 33. Any covenants adopted for this subdivision should contain a description of the replacement plan, including the limitations on diversions and use of water for each well and lot, the requirement to meter and record all well pumping, and information on how records are to be reported and the plan is to be administered.
- 34. In the event the permitted well or wells are not operated in accordance with the conditions of this replacement plan, they shall be subject to administration, including orders to cease diverting groundwater.
- 35. All terms and conditions of Determination of Water Right No. 4278-BD must be meet.
- 36. Pursuant to Rule 5.6.1.E, a copy of this Findings and Order shall be recorded by the Applicant in the clerk and recorder's records of El Paso County, so that a title examination of the land on which the structures involved in this plan are located reveals the existence of this plan.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Joanna Williams, P.E. Water Resource Engineer

F&O4278-RP.docx Prepared by: wad

Exhibit A Replacement Plan - Determination No.: 4278-BD

Page 1 of 1

Designated Basin Summary Table for Romens Living Trust							
Pumping Rate of 2.85 acre-feet per year for 300 Years from the Dawson aquifer							
Section(s): Sec. 24, T11S, R64W, 6th P.M.							
Pumping (Q) Annual Depletion (q) Depletion as a % of Pumping (Q) Annual Depletion (q) Depletion as a							Depletion as a % of
Year	(AF/YR)	(AF/YR)	Pumping (q/Q)	Year	(AF/YR)	(AF/YR)	Pumping (q/Q)
5	2.9	0.000	0.00	155	2.9	0.065	2.30
10	2.9	0.000	0.01	160	2.9	0.068	2.39
15	2.9	0.001	0.02	165	2.9	0.071	2.49
20	2.9	0.001	0.04	170	2.9	0.074	2.59
25	2.9	0.002	0.07	175	2.9	0.077	2.69
30	2.9	0.003	0.11	180	2.9	0.079	2.78
35	2.9	0.005	0.16	185	2.9	0.082	2.88
40	2.9	0.006	0.22	190	2.9	0.085	2.97
45	2.9	0.008	0.28	195	2.9	0.087	3.07
50	2.9	0.010	0.35	200	2.9	0.090	3.16
55	2.9	0.012	0.42	205	2.9	0.093	3.26
60	2.9	0.014	0.50	210	2.9	0.096	3.35
65	2.9	0.017	0.59	215	2.9	0.098	3.45
70	2.9	0.019	0.67	220	2.9	0.101	3.54
75	2.9	0.022	0.76	225	2.9	0.104	3.63
80	2.9	0.024	0.85	230	2.9	0.106	3.73
85	2.9	0.027	0.94	235	2.9	0.109	3.82
90	2.9	0.030	1.04	240	2.9	0.111	3.91
95	2.9	0.032	1.13	245	2.9	0.114	4.00
100	2.9	0.035	1.23	250	2.9	0.117	4.09
105	2.9	0.038	1.32	255	2.9	0.119	4.18
110	2.9	0.040	1.42	260	2.9	0.122	4.27
115	2.9	0.043	1.52	265	2.9	0.124	4.36
120	2.9	0.046	1.61	270	2.9	0.127	4.45
125	2.9	0.049	1.71	275	2.9	0.129	4.54
130	2.9	0.052	1.81	280	2.9	0.132	4.63
135	2.9	0.054	1.91	285	2.9	0.134	4.72
140	2.9	0.057	2.00	290	2.9	0.137	4.80
145	2.9	0.060	2.10	295	2.9	0.139	4.89
150	2.9	0.063	2.20	300	2.9	0.142	4.98

Created by Wenli Dickinson on October 18, 2021

Values for 'Depletion as a % of Pumping' (q/Q) are not calculated when the pumping rate (Q) is changed to anything but zero

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4275-BD

AQUIFER: Laramie-Fox Hills

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Laramie-Fox Hills Aquifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Laramie-Fox Hills aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 1,260 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 15 percent.

Aquifer: Laramie-Fox Hills
Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 210 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that none of the groundwater in the Aquifer underlying the Overlying Land has been either previously determined to be allocated by the Commission, has been permitted for withdrawal by large capacity wells that have rights that were initiated prior to November 19, 1973 that are subject to section 37-90-107(7)(b), or has been permitted for withdrawal by existing small capacity wells withdrawing water under permits issued pursuant to section 37-90-105, C.R.S. The amount of designated groundwater in the Aquifer underlying the Overlying Land that is available for allocation in this Determination is 1,260 acre-feet.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 1,260 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 12.6 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is nontributary groundwater as defined in Rule 4.2.22 of the Designated Basin Rules.

Aquifer: Laramie-Fox Hills
Applicant: Romens Living Trust

Pursuant to the Rules, no more than 98% of the amount of the groundwater in the Aquifer underlying the Overlying Land withdrawn annually shall be consumed.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Laramie-Fox Hills Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 1,260 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.
- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 1,260 acre-feet, less any amount of the Underlying Groundwater allocated

-BD Page 4

Determination No.: 4275-BD Aquifer: Laramie-Fox Hills Applicant: Romens Living Trust

herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.

- b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
- c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
- d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- e. No more than 98% of the amount of Underlying Groundwater withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the Underlying Groundwater withdrawn annually is being consumed.
- f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.
- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Laramie-Fox Hills Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

Determination No.: 4275-BD Aquifer: Laramie-Fox Hills Applicant: Romens Living Trust

- k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.
- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 21. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4275-BD.doc

Joanna Williams, P.E. Water Resource Engineer

ATTACHMENT 1

Exhibit A

Determination No. 4275-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 DEPARTMENT OF NATURAL RESOURCES (1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, <u>www.colorado.gov/water</u>, dwrpermitsonline@state.co.us

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

RCVD DWR 08/03/2021

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

4 ADDLICANT IN	IFORMATION				
1. APPLICANT IN Name of Applica	30/A 10 - C 10 -				
Name of Applica	Romens Living Trust				
Mailing Address		City		State	Zip Code
	5135 Coneflower Lane	Colorado S	prings	Colorado	80917
Telephone Numi	per (include area code)		Email		
	719-331-3310		ajlol	y@msn.com	
2. AQUIFER					
Z. AQUIFER	Laramie Fox Hills				
3. CLAIM OF OW	NERSHIP - I hereby claim that I	am the owner of	f the followin	g described property, as e	evidenced by
the attached co	py of a deed recorded in the cour	nty in which the I	property is io	cated.	
Number of acre	es: 40	in the co	unty of:	El Paso	
			,		
described as fo	llows (insert legal description).				
NF1/4 of the Ni	E1/4 of Section 24 Township 11 S	South Range 64	West of the	6th PM	
INE I/4 OF BIOTH	Ent of coolon 24 Township The	Journ, Marigo o 1		out i tit	
-					
-					
=					
- I further clair	n that the right to withdraw the g	roundwater in th	e aquifer un	derlying the above descri	bed property
	reserved by another, nor has co				
4. THE APPLICA	NT MUST PROVIDE — a Verificat	tion of Notice of	Application (form no. GWS-43) (see in	structions for
exceptions).	Exhibit A				
	- Sign or enter name(s) of applicant(s				
	cond degree, which is punishable as				have read the
	in, know the contents thereof, and sta	4		vledge.	
Signature:	delaida Komens	turto		Date: () () 30	9 22.
Signature: (2	accarac romans	- vueste		Date: June 30	2021
	_				•
Print name and title	- Adelaida Romens, Trustee				
dila dido	- company con to see not best to be to the to the				

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4276-BD

AQUIFER: Arapahoe

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Arapahoe Aguifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Arapahoe aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 1,500 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 17 percent.

Aguifer: Arapahoe

Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 220 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that none of the groundwater in the Aquifer underlying the Overlying Land has been either previously determined to be allocated by the Commission, has been permitted for withdrawal by large capacity wells that have rights that were initiated prior to November 19, 1973 that are subject to section 37-90-107(7)(b), or has been permitted for withdrawal by existing small capacity wells withdrawing water under permits issued pursuant to section 37-90-105, C.R.S. The amount of designated groundwater in the Aquifer underlying the Overlying Land that is available for allocation in this Determination is 1,500 acre-feet.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 1,500 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 15 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is nontributary groundwater as defined in Rule 4.2.22 of the Designated Basin Rules.

Aguifer: Arapahoe

Applicant: Romens Living Trust

Pursuant to the Rules, no more than 98% of the amount of the groundwater in the Aquifer underlying the Overlying Land withdrawn annually shall be consumed.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Arapahoe Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 1,500 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.
- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 1,500 acre-feet, less any amount of the Underlying Groundwater allocated

Aquifer: Arapahoe

Applicant: Romens Living Trust

herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.

- b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
- c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
- d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- e. No more than 98% of the amount of Underlying Groundwater withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the Underlying Groundwater withdrawn annually is being consumed.
- f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.
- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Arapahoe Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

Aguifer: Arapahoe

Applicant: Romens Living Trust

k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.

- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 21. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4276-BD.doc

Joanna Williams, P.E. Water Resource Engineer Page 5

ATTACHMENT 1

Exhibit A

Determination No. 4276-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 DEPARTMENT OF NATURAL RESOURCES (1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, www.colorado.gov/water, dwrpermitsonline@state.co.us

RCVD DWR 08/03/2021

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

1. APPLICANT INFORMATION				
Name of Applicant				
Romens Living Trust				
Mailing Address	City		State	Zip Code
5135 Coneflower Lane	Colorado S	prings	Colorado	80917
Telephone Number (include area code)		Email		
719-331-3310			lolly@msn.com	
A AGUIETO				
2. AQUIFER Arapahoe				
3. CLAIM OF OWNERSHIP - I hereby claim that I a	m the owner of	the follow	ring described property, as evide	enced by
the attached copy of a deed recorded in the county	v in which the r	ronerty is	Incated	
Number of acres: 40	in the co	unty of:	El Paso	
described as follows (insert legal description).				
NE1/4 of the NE1/4 of Section 24 Township 11 So	uth Range 64	West of th	ne 6th PM	
NE 1/4 of the NE 1/4 of Section 24 Township 11 So	dui, italige o-	West of a	ic out i w	1
- I further claim that the right to withdraw the gro	undwater in th	e aquifer i	inderlying the above described	property
has not been reserved by another, nor has cons				p, up ay
4. THE APPLICANT MUST PROVIDE – a Verification	on of Notice of	Application	n (form no. GWS-43) (see instru	ctions for
exceptions). Exhibit A				
5. SIGNATURE - Sign or enter name(s) of applicant(s)	or authorized ag	gent. The	making of false statements herein	constitutes
periury in the second degree, which is punishable as a	class 1 misdeme	anor pursu	ant to C.R.S. 24-4-104(13)(a). I hav	e read the
statements herein, know the contents thereof, and state			nowledge.	
Signature: allelacke Kemens	truste	e	Date: June 30, 20	21
Print name and title: Adelaida Romens, Trustee			€CRI	
Fillit Hailie and due.				

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4277-BD

AQUIFER: Denver

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Denver Aquifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Denver aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 2,040 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 17 percent.

Aquifer: Denver

Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 300 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that none of the groundwater in the Aquifer underlying the Overlying Land has been either previously determined to be allocated by the Commission, has been permitted for withdrawal by large capacity wells that have rights that were initiated prior to November 19, 1973 that are subject to section 37-90-107(7)(b), or has been permitted for withdrawal by existing small capacity wells withdrawing water under permits issued pursuant to section 37-90-105, C.R.S. The amount of designated groundwater in the Aquifer underlying the Overlying Land that is available for allocation in this Determination is 2,040 acre-feet.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 2,040 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 20.4 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is nontributary groundwater as defined in Rule 4.2.22 of the Designated Basin Rules.

Aquifer: Denver

Applicant: Romens Living Trust

Pursuant to the Rules, no more than 98% of the amount of the groundwater in the Aquifer underlying the Overlying Land withdrawn annually shall be consumed.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Denver Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 2,040 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.
- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 2,040 acre-feet, less any amount of the Underlying Groundwater allocated

Aquifer: Denver

Applicant: Romens Living Trust

herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.

- b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
- c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
- d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- e. No more than 98% of the amount of Underlying Groundwater withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the Underlying Groundwater withdrawn annually is being consumed.
- f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.
- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Denver Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

Determination No.: 4277-BD

Aguifer: Denver

Applicant: Romens Living Trust

k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.

- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 21. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4277-BD.doc

Joanna Williams, P.E. Water Resource Engineer Page 5

ATTACHMENT 1

Exhibit A

Determination No. 4277-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 DEPARTMENT OF NATURAL RESOURCES

(1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, www.colorado.gov/water, dwrpermitsonline@state.co.us

RCVD DWR 08/03/2021

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

1. APPLICANT INFORMATION				
Name of Applicant				
Romens Living Trust				
Mailing Address	City		State	Zip Code
5135 Coneflower Lane	Colorado S	prings	Colorado	80917
Telephone Number (include area code)		Email		
719-331-3310		aj	lolly@msn.com	
2. AQUIFER Deriver				
Denver				
a at any or ountrooms. The sales that I a	- the aumor of	f the follow	ing described property as	ovidenced by
3. CLAIM OF OWNERSHIP - I hereby claim that I a	im the owner of	i the lollow	ing described property, as	s evidenced by
the attached copy of a deed recorded in the count	y in which the p	property is	located.	
Number of acres: 40	in the co	unty of	El Paso	
Number of acres	iii tile coi	unity on		
described as follows (insert legal description).				
NE1/4 of the NE1/4 of Section 24 Township 11 So	outh Range 64	West of th	e 6th PM	
NE 1/4 OF BIE NE 1/4 OF OCCURN 24 TOWNSHIP TO SE	dai, rango o .			
3 				
				
- I further claim that the right to withdraw the gro	oundwater in th	e aquifer i	underlying the above desc	cribed property
has not been reserved by another, nor has con-	sent been give	n to anothe	er for the right to its withdr	awal.
4. THE APPLICANT MUST PROVIDE – a Verification	on of Notice of	Application	n (form no. GWS-43) (see	instructions for
exceptions). Exhibit A				
5. SIGNATURE – Sign or enter name(s) of applicant(s) perjury in the second degree, which is punishable as a	or authorized a	gent. The	making of false statements h	erein constitutes
statements herein, know the contents thereof, and state	te that they are tr	ue to mv kr	ant to C.N.S. 24-4-104(15)(a nowledge.). I liave lead tile
Signature: adelorda Komens	- Trust	re	Date: June 30,	2021
	,			
Print name and title: Adelaida Romens, Trustee			~	
Finit name and due.				

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR A DETERMINATION OF A RIGHT TO AN ALLOCATION OF GROUNDWATER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN

DETERMINATION NO.: 4278-BD

AQUIFER: Dawson

APPLICANT: Romens Living Trust

In compliance with section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, Romens Living Trust (Applicant) submitted an application to the Colorado Ground Water Commission (Commission) for a determination of a right to an allocation of designated groundwater from the Dawson Aquifer.

FINDINGS

- 1. The application was received by the Commission on August 3, 2021.
- 2. The Applicant requests a determination of right to an allocation of designated groundwater (Determination) in the Dawson aquifer (Aquifer) underlying 40 acres, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land). According to a Nontributary Groundwater Landownership Statement dated June 30, 2021, attached hereto as Exhibit A, the Applicant owns the 40 acres of land, which are further described in said Ownership Statement, and claims control of the right to the groundwater in the Aquifer underlying the land.
- 3. The Overlying Land is located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and within the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the designated groundwater that is the subject of this Determination.
- 4. The Commission's Staff has evaluated the application relying on the claims to control of the groundwater in the Aquifer underlying the Overlying Land made by the Applicant.
- 5. The Applicant intends to apply the groundwater in the Aquifer underlying the Overlying Land to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The Applicant's proposed place of use of the groundwater in the Aquifer underlying the Overlying Land is the above described 40 acres of Overlying Land.
- 6. Pursuant to section 37-90-107(7)(a), and in accordance with the Designated Basin Rules, the Commission shall allocate the groundwater in the Aquifer underlying the Overlying Land on the basis of the ownership of the Overlying Land.
- 7. The amount of water in storage in the Aquifer underlying the 40 acres of Overlying Land claimed by the Applicant is 880 acre-feet. This determination was based on the following as specified in the Designated Basin Rules.
 - a. The average specific yield of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 20 percent.

Aquifer: Dawson

Applicant: Romens Living Trust

b. The average thickness of those saturated aquifer materials containing sufficient water that can be drained by gravity and placed to beneficial use is 110 feet.

- 8. A review of the records in the Office of the State Engineer has disclosed that a well operating pursuant to section 37-90-105, C.R.S., (i.e. a small-capacity well), permit no. 195628, is located on the Overlying Land and is permitted to withdraw 1 acre-foot per year of groundwater from the Aquifer from beneath the Overlying Land. The applicant has indicated that permit no. 195628 will be cancelled and the well re-permitted to operate pursuant to this Determination. The amount of water considered to have been historically withdrawn from the aquifer by this well is 25 acre-feet. In applying Rule 5.3.2.5 of the Designated Basin Rules to computing the amount of water available for allocation in this Determination, the amount of groundwater in the Aquifer underlying the Overlying Land available for allocation in this Determination is reduced by 25 acre-feet to 855 acre-feet. Except for that well, review of the records in the Office of the State Engineer finds no other previous allocations or permitted withdrawals from the Aquifer underlying the Overlying Land.
- 9. Pursuant to section 37-90-107(7)(c)(III), an approved determination of a right to an allocation shall be considered a final determination of the amount of groundwater so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 10. Pursuant to section 37-90-107(7)(d), the Commission has authority to issue well permits pursuant to subsection 107(7) (i.e. permits for large capacity wells) for the withdrawal of designated groundwater from the Aquifer. Pursuant to section 37-90-107(7)(a) the Commission shall adopt the necessary rules to carry out the provisions of subsection (7). Pursuant to section 37-90-111(h), C.R.S., the Commission is empowered to adopt rules necessary to carry out the provisions of Article 90 of Title 37. In accordance with that authority, the Commission has adopted the Rules and Regulations for the Management and Control of Designated Ground Water (2 CCR 410-1) ("Designated Basin Rules", or "Rules").
- 11. Large capacity well permits issued pursuant to section 37-90-107(7) are subject to the following provisions of statute and the Designated Basin Rules.
 - a. Pursuant to section 37-90-107(7)(a) well permits issued pursuant to subsection 107(7) shall allow withdrawals on the basis of an aquifer life of one hundred years. The 855 acre-feet of water in the Aquifer underlying the Overlying Land available for allocation in this Determination, if permitted for withdrawal by large capacity wells on the basis of an aquifer life of one hundred years, would result in an allowed average annual amount of withdrawal of 8.55 acre-feet per year.
 - b. Any amounts of groundwater in the Aquifer allocated in this Determination that are permitted for withdrawal pursuant to section 37-90-105, by small capacity well permits issued after the issuance of this Determination reduce the amount of water, and the allowed average annual amount of withdrawal, that may be withdrawn by wells permitted pursuant to section 37-90-107(7).
 - c. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of groundwater from the Aquifer underlying the Overlying Land will, within one hundred years, deplete the flow of a natural steam or an alluvial aquifer at an annual

Aquifer: Dawson

Applicant: Romens Living Trust

rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the groundwater in the Aquifer underlying the Overlying Land is considered to be not-nontributary groundwater as defined in Rule 4.2.23 of the Designated Basin Rules. Withdrawal of water from the Aquifer underlying the Overlying Land would impact the alluvial aquifer of the Upper Black Squirrel Creek Designated Groundwater Basin, which has been determined to be over-appropriated. Commission approval of a replacement plan pursuant to section 37-90-107.5, C.R.S., and Rule 5.6 of the Designated Basin Rules, that provides for the replacement of the actual depletion to the alluvial aquifer and is adequate to prevent any material injury to existing water rights of other appropriators, is required prior to approval of well permits for wells to be located on this land area to withdraw the groundwater in the Aquifer underlying the Overlying Land. Pursuant to the Rules the replacement plan shall provide for the depletion of the alluvial water for the first 100 years due to all previous pumping, and if pumping continues beyond 100 years shall replace actual impact until pumping ceases, assuming water table conditions in the Aquifer.

- 12. Pursuant to section 37-90-105(1), the State Engineer has the authority to approve small capacity well permits. While water withdrawn from the Aquifer from beneath the Overlying Land by small capacity wells may consist of the groundwater allocated herein, the Commission recognizes that in approving small capacity permits the State Engineer is not bound by the terms and conditions of this Determination, and may approve small capacity permits based on standards and with such conditions as the State Engineer considers appropriate.
- 13. The ability of wells permitted to withdraw the authorized amount of water from this nonrenewable Aquifer may be less than the one hundred years upon which the amount of water in the Aquifer is allocated, due to anticipated water level declines.
- 14. On October 25, 2021, in accordance with Rule 9.1 of the Designated Basin Rules, written recommendations concerning this application were requested from the Upper Black Squirrel Creek Ground Water Management District. No written recommendations from the District were received.
- 15. In accordance with sections 37-90-107(7)(c)(II) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.

ORDER

In accordance with section 37-90-107(7) and the Designated Basin Rules, the Commission hereby determines a right to an allocation of designated groundwater in the Dawson Aquifer underlying 40 acres of land, generally described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., further described in Exhibit A, subject to the following conditions.

- 16. The amount (i.e. volume) of water in the Aquifer underlying the 40 acres of Overlying Land allocated herein is 855 acre-feet (Underlying Groundwater).
- 17. The amount (i.e. volume) of Underlying Groundwater allocated herein shall be considered final, except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information

Aquifer: Dawson

Applicant: Romens Living Trust

obtained from well drilling or test holes, if such information indicates that the initial estimate of the amount of Underlying Groundwater in the Aquifer was incorrect.

- 18. Approval of this Determination meets the requirements of section 37-90-107(7)(d)(II), that requires a determination of groundwater to be withdrawn by a well be made prior to the granting of a well permit pursuant to section 37-90-107(7).
- 19. Well permits issued pursuant to section 37-90-107(7), (i.e. large capacity wells) and this Determination are subject to the following conditions.
 - a. The total amount of Underlying Groundwater that may be withdrawn from the Aquifer by all large capacity wells permitted pursuant to this Determination may not exceed a volume of 855 acre-feet, less any amount of the Underlying Groundwater allocated herein permitted to be withdrawn by small capacity wells issued permits pursuant to section 37-90-105 after the issuance of this Determination. The amounts of water permitted to be withdrawn by such small capacity wells shall be considered to be one-hundred times the annual withdrawals permitted to be withdrawn by those wells.
 - b. The allowed average annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water shall be equal to the volume of water permitted to be withdrawn by that well (or well field) divided by one-hundred years.
 - c. The allowed maximum annual amount of withdrawal by any large capacity well (or well field) permitted to withdraw the allocated water may exceed the allowed average annual amount of withdrawal allowed by the well permit(s) as long as the total volume of water withdrawn by such well(s) does not exceed the product of the number of years since the date(s) of issuance of the well permit(s) times the allowed average annual amount of withdrawal allowed by the well permit(s).
 - d. The Applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
 - e. Commission approval of a replacement plan, that provides for the replacement of the actual depletion to the alluvial aquifer and is adequate to prevent any material injury to existing water rights of other appropriators in the alluvial aquifer, is required prior to approval of well permits that allow the withdraw of the Underlying Groundwater. The replacement plan shall provide for the depletion of the alluvial water for the first 100 years due to all previous pumping, and if pumping continues beyond 100 years shall replace actual impact until pumping ceases, assuming water table conditions in the Aquifer.
 - f. The use of the Underlying Groundwater shall be limited to the following beneficial uses: domestic including in-home use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The place of use of the Underlying Groundwater shall be limited to the above described 40 acres of Overlying Land. The Underlying Groundwater that is the subject of this Determination may be reused and successively used to extinction to the extent dominion and control over the water is maintained and its volume can be distinguished from the volume of any stream system

Aquifer: Dawson

Applicant: Romens Living Trust

into which it is introduced to the satisfaction of the Commission. The Underlying Groundwater is located within the Upper Black Squirrel Creek Ground Water Management District where local District rules apply which may further limit the withdrawal and use of the subject designated groundwater.

- g. The wells must be located on the above described 40 acres of Overlying Land.
- h. No well shall be located within 600 feet of any existing large-capacity well in the same Aquifer unless a Waiver of Claim of Injury is obtained from the owner of the existing well or unless the Commission, after a hearing, finds that circumstances in a particular instance warrant that a well may be permitted without regard to this limitation.
- i. The wells must be constructed to withdraw water from only the Dawson Aquifer.
- j. The entire depth of each well must be geophysically logged prior to installing the casing in the same manner as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.
- k. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and permanently maintained by the well owner and submitted to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.
- l. The well shall be marked in a conspicuous place with this determination number, the well permit number, and the name of the Aquifer. The well owner shall take necessary means and precautions to preserve these markings.
- 20. Existing well permit no. 195628 must be canceled and a new permit issued for that well to operate pursuant to this Determination.
- 21. A copy of this Determination shall be recorded by the Applicant in the public records of the county in which the Overlying Land is located so that a title examination of the above described 40 acres of Overlying Land area, or any part thereof, shall reveal the existence of this Determination.
- 22. The right to an allocation of designated groundwater determined herein is a vested property right with specific ownership. Some or all of the water right may be transferred independent of the land under which the right originated. Any action taken that is intended to convey, transfer, and/or sell the subject water right shall explicitly identify this Determination number, the specific Aquifer, and the total amount (i.e. volume) of the right that is being conveyed.

Aquifer: Dawson

Applicant: Romens Living Trust

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Prepared by: wad F&O4278-BD.doc

By: Joanna Williams, P.E. Water Resource Engineer

Page 6

ATTACHMENT 1

Exhibit A

Determination No. 4278-BD

Page 1 of 1

Form no. DIVISION OF WATER RESOURCES

GWS-1 **DEPARTMENT OF NATURAL RESOURCES** (1/2020) 1313 Sherman St, Room 821, Denver, CO 80203

(303) 866-3581, www.colorado.gov/water, dwrpermitsonline@state.co.us

10014221

NONTRIBUTARY GROUNDWATER LANDOWNERSHIP STATEMENT

RCVD DWR 08/03/2021

This form is to be submitted with applications for the following, when the applicant is the owner of the overlying land.

1) A well permit to withdraw groundwater from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or other aquifer the applicant claims contains nontributary groundwater, outside of a Designated Groundwater Basin subject to section 37-90-137(4), C.R.S., except when the right to withdraw the groundwater has been determined by a valid decree; OR

2) A determination of water right in the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifers, or a well permit to withdraw groundwater from those aquifers that are subject to Designated Basin Rule 5.4, within a Designated Groundwater Basin. NOTE: Form submittal instructions can be found on our website Colorado.gov/water. See instructions on the reverse of this form. Type or print in black or blue ink.

1. APPLICANT INFORMATION			
Name of Applicant			
Romens Living Trust			
Mailing Address	City	State	Zip Code
5135 Coneflower Lane	Colorado Springs	Colorado	80917
Telephone Number (include area code)	Email		
719-331-3310	1	ajlolly@msn.com	
2. AQUIFER Dawson			
3. CLAIM OF OWNERSHIP - I hereby claim that	at I am the owner of the follo	wing described property, as	evidenced by
the attached copy of a deed recorded in the c	ounty in which the property i	is located.	
Number of acres: 40	in the county of:	El Paso	
described as follows (insert legal description).			
, , ,		the CAL DAA	
NE1/4 of the NE1/4 of Section 24 Township 1	1 South, Range 64 West of	tne otn PM	
*			
			-
- I further claim that the right to withdraw the	e groundwater in the aquifer	underlying the above desc	ribed property
has not been reserved by another, nor has			
4. THE APPLICANT MUST PROVIDE – a Verifi	cation of Notice of Application	on (form no. GWS-43) (see	instructions for
exceptions). Exhibit A			
 SIGNATURE – Sign or enter name(s) of application perjury in the second degree, which is punishable statements herein, know the contents thereof, and 	as a class 1 misdemeanor purs	suant to C.R.S. 24-4-104(13)(a)	
Signature: Adelaida Romenz,	trustee	Date: June 30	, 2021
Print name and title: Adelaida Romens, Trustee			

Replacement Plan Accounting Reporting Form

Determination of Water Right Number: 4278-BD

Aquifer from which wells produce water: Dawson

Submit to: Colorado Ground Water Commission, 1313 Sherman St., Room 821, Denver, CO 80203

Person responsible for gathering and submitting data (required) Name: Email address: Mailing Address: Telephone: Calendar year being reported 1: Calendar year operation of the plan was initiated 2: Year number of operation of the plan 3: Annual replacement water requirement (acre-feet/year) 4: Meter Meter Meter Meter Meter Metered initiation of Reading at Reading at Reading at Metered reading at pumping operation of operation operation of operation operation operation operation operation operation operation operation operation operation operation operation operation operation operation operation operation operati

								Pumping of this
						Date of		well since
		Meter	Meter			Meter	Metered	initiation of
		Reading at	Reading at	Metered		reading at	pumping	operation of
Well Permit		beginning of	end of year	pumping	Meter's	end of year	this year 12	the plan 13
no. ⁵	Address of property served by this well ⁶	year ⁷	8	this year ⁹	Units 10	11	(acre-feet)	(acre-feet)
		l	1		I	I	1	

Well Permit	Address of property served by this well ⁶	Number of Ocupied Single Family Dwellings ¹⁴	Amount of Irrigated Land ¹⁵ (ft ²)	Number of Large Domestic Animals ¹⁶	Estimated Return Flow ¹⁷ (acre-feet)
110.	ridaress of property served by this well	Divenings	(10)	7.11111013	(dere reet)

Conversion rates:

- 1 acre-foot equals 325,851 gallons
- 1 acre-foot equals 43,560 cubic feet

See reverse side for notes.

Notes:

- 1) Calendar year for which this report is being submitted.
- 2) The calendar year when the first well permitted pursuant to this plan was constructed, or when the first permit for an existing well was issued pursuant to the plan. Once the plan has been initiated this year will not change.
- 3) The number of years after initiation of operation of the plan. The year of initiation is year number 1.
- 4) Equal to "Annual Depletion" on Exhibit A of the Replacement Plan.
- 5) The well permit number of the well being operated pursuant to the plan.
- 6) The address of the property served by the well.
- 7) The reading on the meter at the beginning of the year. Equal to reading on the meter at end of year on last year's reporting form. For the first year of operation of a well this is the meter reading prior to pumping under the plan.
- 8) Reading on the meter at the end of the year.
- 9) The amount of water pumped by the well this year. Equal to the reading on the meter at the end of this year minus reading on the meter at the beginning of the year. If a new meter was installed during the year, explain that fact and report the sum of the readings of the old and new meters over the year.
- 10) Units of measurement shown on the meter.
- 11) Date that the meter was read this year. This should be on December 31st or as close to that date as possible.
- 12) The amount pumped this year, reported in acre-feet.
- 13) The cumulative amount of water pumped by this well (and all previous wells serving this address) since initiation of operation of the plan. Equal to "Pumping of this well since initiation of operation of the plan" on last year's reporting form plus "Pumping of this well this year" on this year's reporting form.
- 14) The number of occuped single family dwellings supplied by the well.
- 15) The amount of irrigated land supplied by the well.
- 16) The number of large domestic animals supplied by the well.
- 17) Return flow consists of water recharged into the alluvial aquifer by way of non-evaporative septic and leaching field sytem discharges, which are estimated as 0.25 acre-feet per year (90 percent of the amount of water supplied to in-house uses by each well supplying an occupied dwelling). Refer to the Findings and Orders of the approved replacement plan.

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR REPLACEMENT PLAN TO ALLOW THE WITHDRAWAL OF GROUNDWATER FROM THE DAWSON AQUIFER IN THE UPPER BLACK SQUIRREL CREEK DESIGNATED GROUNDWATER BASIN.

REPLACEMENT PLAN NO. 4278-RP

FOR DETERMINATION OF WATER RIGHT NO. 4278-BD

AQUIFER: DAWSON

APPLICANT: ROMENS LIVING TRUST

In compliance with section 37-90-107.5, C.R.S. and the Designated Basin Rules, 2 CCR 410-1 (Rules or Rule), Romens Living Trust (Applicant) submitted an application for a replacement plan to allow the withdrawal of groundwater from the Dawson Aquifer that has been allocated by Determination of Water Right No. 4278-BD.

FINDINGS

- 1. Pursuant to section 37-90-107(7), C.R.S., in a Findings and Order dated January 5, 2022, the Ground Water Commission (Commission) approved a Determination of a Right to an Allocation of Groundwater, No. 4278-BD, from the Dawson Aquifer (Aquifer), summarized as follows.
 - a. The determination quantified an amount of water from beneath 40 acres of overlying land described as the NE 1/4 of the NE 1/4 of Section 24, Township 11 South, Range 64 West, 6th P.M., in El Paso County (Overlying Land).
 - b. The amount of water in the aquifer that was allocated was 855 acre-feet, and the allowed average annual amount of groundwater to be withdrawn from the aquifer was limited to 8.55 acre-feet per year (subject to adjustment by the Commission to conform to actual local aquifer characteristics).
 - c. The use of groundwater is limited to the following beneficial uses: domestic including in-house use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage.
 - d. Withdrawal of the subject groundwater will, within one hundred years, deplete the flow of a natural stream or its alluvial aquifer at an annual rate greater than onetenth of one percent of the annual rate of withdrawal, the groundwater is considered to be not-nontributary, and Commission approval of a replacement plan providing for actual depletion of affected alluvial aquifers and adequate to prevent any material injury to existing water rights in such alluvial aquifers is required prior to approval of well permits for wells to withdraw the subject groundwater.
- 2. The subject water is Designated Groundwater located within the boundaries of the Upper Black Squirrel Creek Designated Groundwater Basin and the Upper Black Squirrel Creek Ground Water Management District. The Commission has jurisdiction over the withdrawal of the water by large capacity wells that are permitted pursuant to section 37-90-107(7).
- 3. Withdrawal of the subject groundwater would deplete the alluvial aguifer of the Kiowa-Bijou

Replacement Plan - Determination No.: 4278-BD

Aquifer: Dawson

Applicant: Romens Living Trust

Designated Groundwater Basin, the alluvial aquifer of the Upper Big Sandy Designated Groundwater Basin and the alluvial aquifer of the Upper Black Squirrel Creek Designated Groundwater Basin, all of which, according to Rules 5.2.4.2, 5.2.7.2 and 5.2.6.2, respectively, have been determined to be over appropriated. Such depletion would unreasonably impair existing large capacity alluvial rights withdrawing water from those alluvial aquifers.

Page 2

- 4. Pursuant to Rule 5.6.1.A this plan must be adequate to prevent any material injury to water rights of other appropriators, which for purposes of this plan means large capacity wells withdrawing water from the alluvial aquifer of the Kiowa-Bijou Designated Groundwater Basin, the alluvial aquifer of the Upper Big Sandy Designated Groundwater Basin and the alluvial aquifer of the Upper Black Squirrel Creek Designated Groundwater Basin.
- 5. Pursuant to Rule 5.3.6.2(C) the amount of replacement water shall provide for the depletion of alluvial water for the first 100 years due to all previous pumping and if pumping continues beyond 100 years, shall replace actual impact until pumping ceases.
- 6. The application for the replacement plan was received by the Commission on August 3, 2021.
- 7. The Applicant proposes to divert 2.85 acre-feet annually from the Dawson Aquifer for a period of 300 years. The Dawson aquifer water will be withdrawn through one or more wells to be located on seven (7) residential lots. Each Dawson Aquifer well is proposed to divert 0.407 acre-feet of water annually for domestic including in-house use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The land on which the wells will be located is the Overlying Land described above.
- 8. At a continuous withdrawal of 2.85 acre-feet annually for 300 years, depletions to the alluvial aquifer systems of the Kiowa-Bijou Designated Groundwater Basin, Upper Big Sandy Designated Groundwater Basin and Upper Black Squirrel Creek Designated Groundwater Basin would steadily increase to 0.142 acre-feet per year in the 300th year, which is equal to 4.98% of pumping, as shown in Exhibit A.
- 9. The Applicant proposes to provide 1.260 acre-feet per year of replacement water to the alluvial aquifer system of the Upper Black Squirrel Creek Designated Groundwater Basin. The proposed source of replacement water is septic return flows from the in-house use of the groundwater to be pumped under the plan. The Applicant estimates that return flows from each lot will consist of 90% of the water used for in-house purposes. Assuming each lot uses a total annual amount for in-house use of 0.20 acre-feet, the return flow per lot would be 0.18 acre-feet annually, and the return flows under the plan will total 1.260 acre-feet per year for all seven (7) lots at full build out.
- 10. The subject property is located within the drainage of West Bijou Creek, and the return flows will flow to the alluvial aquifer of the Kiowa-Bijou Designated Groundwater Basin. The Applicant proposes to aggregate all replacements to the drainage in which the well or wells will operate, in accordance with Guideline 2007-1.
- 11. Pursuant to Rule 5.6.1.B this plan must be adequate to prevent unreasonable impairment of water quality. Pursuant to Rule 5.6.1.B.1.b, if the replacement source water is from an onsite wastewater treatment system permitted by a local health agency and the applicant demonstrates the source is in compliance with that permit there shall be a rebuttable presumption of no unreasonable impairment of water quality.

Replacement Plan - Determination No.: 4278-BD

Aquifer: Dawson

Applicant: Romens Living Trust

12. Pursuant to Rule 5.6.1.C this plan, including the proposed uses of the water withdrawn pursuant to the plan, must not be speculative, and must be technically and financially feasible and within the Applicant's ability to complete. The plan, including the proposed uses of the water withdrawn pursuant to the plan, is not speculative. The plan appears technically and financially feasible and within the Applicant's ability to complete.

Page 3

- 13. Pursuant to Rule 5.6.1.D this plan must be able to be operated and administered on an ongoing and reliable basis. The plan appears to be able to be operated and administered on an ongoing and reliable basis.
- 14. Pursuant to Rule 5.6.1.F replacement source water must be physically and legally available in time, place and amount to prevent material injury. As determined in Determination of Water Right No. 4278-BD water is currently available in the amounts and for the number of years proposed to be diverted.
- 15. Pursuant to Rule 5.6.1.G the replacement source water must be legally available for use. Records in this office indicate that the Applicant controls the water right to be used as the source of replacement water, consisting of Determination of Water Right No. 4278-BD, and such water is legally available for use pursuant to this plan.
- 16. In accordance with Rule 5.6.4 the application was referred to the Upper Black Squirrel Creek Ground Water Management District on October 25, 2021. No response was received from the District.
- 17. In accordance with sections 37-90-107.5 and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on November 4, 2021 and November 11, 2021. No objections to the application were received within the time limit set by statute.
- 18. According to Rule 5.6.1:
 - a. The Applicant has the burden of proving the adequacy of the plan in all respects.
 - b. If the applicant meets its burden of proof, the Commission shall grant approval of the plan which shall include any terms and conditions established the Commission.
- 19. The Commission Staff has evaluated the application pursuant to section 37-90-107.5, and the requirements of Rule 5.3.6.2(C) and Rule 5.6, finds that the requirements have been meet, and the plan may be approved to allow diversions from the Dawson Aquifer if operated subject to the conditions given below.

ORDER

In accordance with section 37-90-107.5, and the Designated Basin Rules, the Colorado Ground Water Commission orders that the application for a replacement plan to allow the withdrawal of groundwater from the Dawson Aquifer underlying 40 acres that are the subject of Determination of Water Right no. 4278-BD is approved subject to the following conditions:

20. The Dawson aquifer water will be withdrawn through one or more wells to be located on seven (7) residential lots. The allowed use of groundwater for each well under this plan is domestic including in-house use; domestic animal watering; irrigation of landscape, gardens and greenhouse; commercial; fire protection; recreational; and the watering of stock animals, either directly or after storage. The land on which the wells will be located is the Overlying

Replacement Plan - Determination No.: 4278-BD

Aquifer: Dawson

Applicant: Romens Living Trust

Land described above.

21. The allowed annual amount of groundwater to be withdrawn from the Aquifer by all wells operating under this plan shall not exceed 2.85 acre-feet. The allowed annual amount of water to be withdrawn from each on-lot well shall not exceed 0.407 acre-feet.

- 22. A totalizing flow meter shall be installed on each well. The well owner shall maintain the meter in good working order.
- 23. Permanent records of all withdrawals of groundwater from each well shall be recorded at least annually by the well owners, permanently maintained, and provided to the Commission and the Upper Black Squirrel Creek Ground Water Management District upon request.
- 24. Pumping under this plan is limited to a period of 300 years. The year of first use of this replacement plan shall be the calendar year of construction of a well permitted pursuant to this plan or permitting of an existing well pursuant to the plan.
- 25. Return flows from in-house use of groundwater shall occur through individual on-lot non-evaporative septic systems located within the 40 acres of Overlying Land that are the subject of Determination of Water Right No. 4278-BD. The septic systems must be constructed and operated in compliance with a permit issued by a local health agency.
- 26. Replacement of depletions must be provided annually in the acre-feet amounts shown in Exhibit A. Annual replacement requirements may be computed by pro-rating between the values given on Exhibit A, or for simplicity may be taken as the amount shown in the next succeeding 5 year increment.
- 27. The Applicant or their successor(s) are responsible for ensuring that replacement water is provided to the alluvial aquifer as required by this plan. The annual replacement requirement and the annual amount of replacement water provided shall be calculated and reported on a form acceptable to the Commission. The annual amount of replacement water provided must be no less than the annual replacement requirement on a yearly basis. No credit shall be claimed by the Applicant for an oversupply of replacement water provided to the alluvium during previous years.
- 28. The Applicant must provide the required annual amount of replacement water for the first 100 years, or for as long as a well is operated pursuant to this plan, whichever is longer.
- 29. To assure adequate return flows, at least one well must be serving the in-house uses for an occupied dwelling that is generating return flows via a non-evaporative septic system before any other use is allowed.
- 30. So long as at least one well continues to pump and supply the in-house uses for an occupied dwelling, the plan's required replacement obligations, shown in Exhibit A, will be met. Should all wells cease pumping for in-house use within the first 100 years an amended or alternate replacement plan must be obtained that will replace actual depletions to the alluvial aquifer so as to prevent any material injury to water rights of other appropriators.
- 31. The Applicant (and their successors) must gather and maintain permanent records of all information pertaining to operation of this plan, which shall include, but is not be limited to, those items identified below. The Applicant must submit records to the Commission and the Upper Black Squirrel Creek Ground Water Management District on forms acceptable to the

Page 4

Aquifer: Dawson

Applicant: Romens Living Trust

Commission, on an annual basis for the previous calendar year, by February 15th of the following year.

- a. Identification of all well permits issued and wells constructed under this plan.
- b. The amount of water diverted by each well and all wells in total, both annually and cumulatively since operation of the plan began.
- c. The number of occupied dwellings served by each well.
- d. The return flows occurring from use of all wells operating under the plan, assuming 0.18 acre-feet per year per occupied single family dwelling (90% of the water used for in-house purposes) enters the alluvial aquifer as replacement water.
- e. Any other information the Commission deems relevant and necessary to operation, monitoring, accounting, or administration of the plan.
- 32. The Applicant (and their successors) are fully responsible for the operation, monitoring, and accounting of the replacement plan. In the event a lot with a well permitted or operating pursuant to this plan is sold, identification of the well that was sold and evidence that the new owner has been notified of their responsibilities under the replacement plan shall accompany that year's accounting.
- 33. Any covenants adopted for this subdivision should contain a description of the replacement plan, including the limitations on diversions and use of water for each well and lot, the requirement to meter and record all well pumping, and information on how records are to be reported and the plan is to be administered.
- 34. In the event the permitted well or wells are not operated in accordance with the conditions of this replacement plan, they shall be subject to administration, including orders to cease diverting groundwater.
- 35. All terms and conditions of Determination of Water Right No. 4278-BD must be meet.
- 36. Pursuant to Rule 5.6.1.E, a copy of this Findings and Order shall be recorded by the Applicant in the clerk and recorder's records of El Paso County, so that a title examination of the land on which the structures involved in this plan are located reveals the existence of this plan.

Dated this 5th day of January, 2022.

Kevin G. Rein, P.E Executive Director

Colorado Ground Water Commission

Joanna Williams, P.E. Water Resource Engineer

F&O4278-RP.docx Prepared by: wad

Exhibit A Replacement Plan - Determination No.: 4278-BD

Page 1 of 1

Designated Basin Summary Table for Romens Living Trust							
Pumping Rate of 2.85 acre-feet per year for 300 Years from the Dawson aquifer							
Section(s): Sec. 24, T11S, R64W, 6th P.M.							
V	Pumping (Q)	Annual Depletion (q)	Depletion as a % of	V	Pumping (Q)	Annual Depletion (q)	Depletion as a % of
Year	(AF/YR)	(AF/YR)	Pumping (q/Q)	Year	(AF/YR)	(AF/YR)	Pumping (q/Q)
5	2.9	0.000	0.00	155	2.9	0.065	2.30
10	2.9	0.000	0.01	160	2.9	0.068	2.39
15	2.9	0.001	0.02	165	2.9	0.071	2.49
20	2.9	0.001	0.04	170	2.9	0.074	2.59
25	2.9	0.002	0.07	175	2.9	0.077	2.69
30	2.9	0.003	0.11	180	2.9	0.079	2.78
35	2.9	0.005	0.16	185	2.9	0.082	2.88
40	2.9	0.006	0.22	190	2.9	0.085	2.97
45	2.9	0.008	0.28	195	2.9	0.087	3.07
50	2.9	0.010	0.35	200	2.9	0.090	3.16
55	2.9	0.012	0.42	205	2.9	0.093	3.26
60	2.9	0.014	0.50	210	2.9	0.096	3.35
65	2.9	0.017	0.59	215	2.9	0.098	3.45
70	2.9	0.019	0.67	220	2.9	0.101	3.54
75	2.9	0.022	0.76	225	2.9	0.104	3.63
80	2.9	0.024	0.85	230	2.9	0.106	3.73
85	2.9	0.027	0.94	235	2.9	0.109	3.82
90	2.9	0.030	1.04	240	2.9	0.111	3.91
95	2.9	0.032	1.13	245	2.9	0.114	4.00
100	2.9	0.035	1.23	250	2.9	0.117	4.09
105	2.9	0.038	1.32	255	2.9	0.119	4.18
110	2.9	0.040	1.42	260	2.9	0.122	4.27
115	2.9	0.043	1.52	265	2.9	0.124	4.36
120	2.9	0.046	1.61	270	2.9	0.127	4.45
125	2.9	0.049	1.71	275	2.9	0.129	4.54
130	2.9	0.052	1.81	280	2.9	0.132	4.63
135	2.9	0.054	1.91	285	2.9	0.134	4.72
140	2.9	0.057	2.00	290	2.9	0.137	4.80
145	2.9	0.060	2.10	295	2.9	0.139	4.89
150	2.9	0.063	2.20	300	2.9	0.142	4.98

Created by Wenli Dickinson on October 18, 2021

Values for 'Depletion as a % of Pumping' (q/Q) are not calculated when the pumping rate (Q) is changed to anything but zero