# Briargate Bridge at Sand Creek
# Design Report
## Sand Creek Drainageway

## El Paso County, Colorado

Prepared for:
SR Land, LLC
20 Boulder Crescent Suite 200
Colorado Springs, Colorado 80903

Prepared by:

Kiowa Engineering Corporation
1604 South 21st Street
Colorado Springs, Colorado 80904
Ph: (719)630-7342

Kiowa Project No. 19032

June 27, 2022

CDR-21-013

**Design Engineer's Statement:**

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

6/30/2022

Stephen A. Brown, P.E. #40190 Date

**Owner/Developer's Statement:**

I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

6/30/2022

~~James Morley~~ LOREN J. MOREAU Date

Sterling Ranch Metropolitan District

20 Boulder Crescent Suite 2nd Floor

**El Paso County**:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

County Engineer / ECM Administrator Date

Conditions:

**TABLE OF CONTENTS**


Table of Contents ..... iii

Appendix Table of Contents ..... iv

I. Executive Summary ..... 5

II. General Location and Description ..... 5

III. Project Background ..... 6

IV. Previous Reports and Jurisdictional Requirements ..... 6

V. Site Description ..... 6

VI. Hydrology ..... 7

VII. Hydraulics ..... 7

VII. Hydraulic Design and Criteria ..... 8

VIII. Hydraulic Modelling Results ..... 10

IX. Scour Analysis ..... 12

X. Construction PErmitting ..... 12

XI. Drainage and Bridge Fees ..... 12

XII. Phasing ..... 13

XIII. Conclusions ..... 13

Appendix Table of Contents ..... 14

# APPENDIX TABLE OF CONTENTS

**Appendix A: Floodplain**
Figure 1 Vicinity Map
Figure 2 Briargate Bridge Floodplain Workmap
Annotated FIRM

**Appendix B: Hydrology**
2018 MDDP Hydrology Existing Conditions Map

**Appendix C: Drop Structure and Riprap Calculations**

**Appendix D: HECRAS Hydraulic Modelling**

**Appendix E: Contech Bridge Design Analysis**

**Appendix F: Improvement Costs**

## I. EXECUTIVE SUMMARY

This design report presents descriptions and design calculations for the Briargate Parkway crossing of Sand Creek in the Sterling Ranch Development. The crossing consists of a bridge with associated upstream and downstream channel improvements that will provide a transition to the natural channel of Sand Creek. A separate report by others will address design, drainage, and water quality design of the Briargate Parkway. Design elements in the descriptions below and associated documents in the Appendix include floodplain analysis, hydrology, design calculations, hydraulic modelling results.

## II. GENERAL LOCATION AND DESCRIPTION

The proposed crossing consists of a 43-foot wide Conspan steel arch bridge sized to convey 100-year frequency flows without resulting in increases to the effective base flood elevations (BFEs) for Sand Creek. Two grouted sloping boulder (GSB) drop structures are proposed upstream of the bridge crossing to provide necessary grade control for the bridge. The current incised natural channel upstream and downstream of the bridge will be graded to provide stable 4:1 side embankment slopes and adequate capacity for major storm flows. The proposed channel revision, including the 228-foot long Conspan bridge crossing, will extend for approximately 625 feet along Sand Creek. The proposed channel and bridge improvements lie within El Paso County. The location of the site is shown on Figure 1 of the Appendix.

Upon the completion of the crossing and acceptance by El Paso County and Sterling Ranch Metropolitan District, easements and or tracts will be dedicated for the purposes of maintenance access. The bridge and channel work will occur adjacent to Tracts A, B, and D of Sterling Ranch Filing No. 1. Operation and maintenance of the bridge will be performed by El Paso County while the channel will be the responsibility of the Sterling Ranch Metropolitan District. A "No-Rise" floodplain certification study will be conducted in lieu of a CLOMR submittal to FEMA. However, a LOMR submittal will be required after construction to account for the floodplain revision. No residential lots within future Sterling Ranch Filings that will lie within the 100-year floodplain.

The bridge over Sand Creek at Briargate Parkway is included within the design plans. The bridge consists of a Conspan steel arch structure that have the capacity to pass the 100-year discharge. The typical road right-of-way is 130 feet for Briargate Parkway. The ultimate roadway section for Briargate Parkway as shown on the roadway design plans includes four 12-foot lanes and a 16-foot raised median, Type A curb and gutter, and 8-foot and 10-foot detached sidewalks. Protective guardrails as shown on the drawings have been designed in conformance with Colorado Department of Transportation M-standards.

Once the bridge and roadway facilities are completed and accepted by El Paso County, El Paso County will assume maintenance responsibility for the structures and roadways. A deed will be provided to transfer ownership to the County. The developer intends to request reimbursement for the cost to construct the bridges and drainageway facilities, or request credit against future drainage and bridge fees. Reimbursement will be processed in accordance with sections 1.7 and 3.3 of the Drainage Criteria Manual (DCM). The drainageway facilities will be operated and maintained by the Sterling Ranch Metropolitan District.

## III. PROJECT BACKGROUND

Sand Creek within Sterling Ranch is a natural drainageway at his time that was shown to be stabilized in the Sterling Ranch Master Development Drainage Plan (MDDP). The MDDP showed Sand Creek to be reconfigured into a trapezoidal channel section capable of conveying the 100-year discharge as listed in the MDDP. The original channel design was a benched trapezoidal channel with numerous drop structures to provide grade control. However, after subsequent consideration by El Paso County and the Army Corps of Engineering, the decision was made to provide a design mimicking the current natural configuration of the channel. The present average slope of the drainageway within the design reach is 1.8 percent. As seen from the Briargate Bridge Plan and Profile, two drop structures upstream of the bridge were designed to reduce the channel slope through the bridge reach to 0.2 percent. Riprap channel and embankment lining through the bridge reach will provide erosion protection during major storm events.

## IV. PREVIOUS REPORTS AND JURISDICTIONAL REQUIREMENTS

The basis for the development of the design has been developed from referencing the following reports:

1. ***Sterling Ranch Master Development Drainage Plan (MDDP), prepared by M & S Civil Consultants, July 2018.***
2. ***Sand Creek Drainage Basin Planning Study (DBPS), prepared by Kiowa Engineering, 1996.***
3. ***City of Colorado Springs and El Paso County Drainage Criteria Manual, 1987.***
4. ***El Paso County Engineering Criteria Manual, most current version.***
5. ***City of Colorado Springs Drainage Criteria Manual, May 2014.***
6. ***The City of Colorado Springs and El Paso County Flood Insurance Study (FIS), prepared by the Federal Emergency Management Agency, effective 2018.***
7. ***Sterling Ranch Channel Improvements and Mitigation Plan, prepared by Core Consultants, October 2015.***
8. ***Master Development Drainage Plan for Sterling Ranch, M&S Civil Consultants, October 2018.***

## V. SITE DESCRIPTION

The Sand Creek floodplain within the Briargate Bridge reach is well vegetated with native grasses that are in fair to good condition that exists on the floodplain overbanks and within the greater valley in general. There is little evidence of active invert degradation or bank sloughing except for the channel bends that occur at the location of future Sterling Ranch Road. Current longitudinal slope is approximately 1.4 percent. There is presently no base flow in this segment. There are presently no developed lots that lie within the 100-year floodplain. Lots in the Homestead at Sterling Ranch Filing No. 2 and Branding Iron at Sterling Ranch Filing No. 2 subdivisions do not encroach into the 100-year floodplain.

A 24-inch water line is proposed to cross the drainageway just upstream of future Briargate Boulevard. The water and wastewater facilities that may impact the drainageway are all owned and maintained by the Sterling Ranch Metropolitan District.

## VI. HYDROLOGY

Hydrology for use in determining the typical channel sections shown on the plans were obtained from Reference 6. The 100-year discharges shown in Reference 6 is 2,600 cubic feet per second. The 100-year peak discharges from references 1 and 2 were reviewed as well. A comparison if peak discharges is presented below.

**Existing Development Condition Peak Discharges**

**Sand Creek at Sterling Ranch**

| Location: South Property Line (cfs) | 5yr | 10yr | 100yr |
|---|---|---|---|
| City of Colorado Springs FIS | NR | 1,200 | 2,600 |
| Sand Creek DBPS | NR | 770 | 2,620 |
| Sterling Ranch MDDP | 435 | 713 | 1,912 |

The above listed discharges all assume existing, or pre-development conditions. The hydrology used in the FIS was obtained from a Soil Conservation Service study conducted in 1975 for the Sand Creek watershed using the "SCS method. The hydrology developed in the DBPS also used the SCS method and obtained similar results. The MDDP used the U. S. Army Corps of Engineers HEC-1 hydrograph model and the SCS curve numbers to develop the peak discharges shown above. The MDDP applied a Type II storm distribution as proposed to the Type IIA distribution applied in the FIS and DBPS. This will typically cause peak discharges to decrease 10 to 15 percent. As the difference in the peak discharges cause relatively small differences in the hydraulic design the channel and the bridges, the FIS 100-year discharge was used in the hydraulic design of the channel and bridge improvements. According to the criteria set forth in Reference 4, the low flow channel was sized using 10 percent of the 100-year discharge, or 260 cubic feet per second.

The assumption that FSD will be required for all future development is reflected in the use of the existing development discharges in this design. There is a good correlation between the FIS and 1996 DBPS 100-year discharges for the segment of Sand Creek subject to this design. The future FSD's within Sterling Ranch will be publicly operated and maintained facilities by the Sterling Ranch Metropolitan District.

## VII. HYDRAULICS

The goal of the bridge crossing design was to provide adequate conveyance capacity for the effective 100-yr frequency flows per FEMA and avoid any increase in the effective BFEs for the Sand Creek Floodplain. In addition, the proposed crossing was designed to produce flow characteristics that meet El Paso County criteria. Two grouted sloping boulder drop structures are proposed upstream of the crossing to lower the channel invert and provide grade control through the crossing reach. In addition to the grouted boulders, the entire invert upstream, through the proposed bridge, and downstream outlet are to be riprap lined. The bridge, a Conspan 58S steel arch, will convey flows at a depth of 5.8 to 7.6 feet with freeboard to the crown in excess of 14 feet. The excess height of the bridge was required to match the roadway grade for Briargate Parkway and provide necessary invert elevation for the channel.

The hydraulic design of the bridge crossing of Sand Creek performed using with US Army Corps of Engineers HEC-RAS modeling system version 6.1. A corrected effective model was

developed to establish existing conditions and provide a basis for comparison with the proposed conditions model. The downstream tie-in with the effective FIS model is located at section 63+79 of project mapping which corresponds to FIS section DG shown on the FIRM. Starting water surface elevations for the proposed model were taken from the effective model (NGVD 29 elevation datum to match project mapping). The upstream tie-in occurs at section 74+11 and corresponds to FIS section DI shown on the FIRM. The 100-year water surface elevation of the corrected effective and proposed models match the effective within 0.0 feet. The corrected effective model 100-year delineation closely matches the effective floodplain as shown on the Annotated FIMR in the Appendix.

The model was used to determine the 100-year hydraulic grade line shown on the plan and profiles. The 100-year profile for the FIS hydrology has been determined. The location for the proposed 100-year floodplain using FIS hydrology has been presented on the plan view of the design plans and on the grading plan. Appendix A of this report has the floodplain maps that show the effective 100-year floodplain. The locations for HEC-RAS cross-sections are shown on the design profile. The HEC-RAS model cross-sections are also contained within Appendix A. The summary output for the 10-. 50- 100-year and 500-year recurrence intervals have been included in the Appendix of this report.

A riprap apron is included on the downstream end of the bridge to prevent channel degradation and undercutting of the bridge and wingwalls. A sheet pile cutoff wall is included on the downstream end of the riprap apron extending one foot above the proposed 100-year water surface.

## VII. HYDRAULIC DESIGN AND CRITERIA

A "No-Rise" floodplain certification study will be submitted in lieu of a CLOMR submittal to FEMA. However, a LOMR submittal will be required after construction to account for the floodplain revision. There are no residential lots within future Sterling Ranch Filings that will lie within the 100-year floodplain.

Freeboard (between bridge low chord and 100-year design flow water surface) for the Briargate bridge is in excess of 10 feet and well above the 2-foot minimum per section 6.4.2 of the El Paso County Drainage Criteria Manual bridge.

Analysis of bridge scour was performed at upstream and downstream cross sections. Since the Conspan crossing structure is entered as a culvert, the bridge scour analysis was not available in the HEC-RAS program. Therefore, the shear force variable, also referred to as tractive force, was used to determine the adequacy of riprap erosion protection shown on the design plans.

Presented on the design plans associated with this design memorandum are the proposed drainageway conditions. Design criteria for the project are summarized as follows:

| | |
|---|---|
| Channel design slope: | 0.2 percent |
| Maximum drop height: | 4 feet |
| Manning's n-values: | .025-.045 |
| Froude number-(excluding crests of drops): | 0.75 |
| Permissible shear stress: channel and embankment: | |
| Type M soil riprap | 5.0 psf |

Drop Structure Design

The drops will be constructed using grouted boulders. The selection of grouted boulders was chosen to address long-term durability of the drop. The Grouted Sloping Boulder (GSBD) design follows the criteria included in the Mile High Flood District's Urban Storm Drainage Criteria Manual (USDCM). Two 4-foot-high GSBD's are proposed for this reach of Sand Creek. The longitudinal slope of the drop face is designed at 5:1 (USDCM Criteria is 4:1 maximum). Calculations were performed to determine the boulder size within the grouted sloping boulder drops. The minimum boulder size for the drop structures will be 30-inches. These boulders must be carefully placed to create a stepped appearance which helps to increase roughness. The boulders will be placed on either undisturbed soil, compacted subgrade or shallow bedrock (where encountered). Full penetration of grout around the lower one-half of the rock is essential for successful grouted boulder performance. The grout should be injected to a depth equal to one-half of the boulders being used and keep the upper one-half ungrouted and clean. Typically, the grout will not extend to the top of the boulders.

A grout cutoff wall will be located at the upstream end of each drop approach, for the full width of the drop, to minimize seepage from occurring under the structure and possible uplift forces. The cutoff wall will be installed to the specified depth below the proposed channel invert. A 30-inch to 36-inch grouted boulder sill will be installed at the downstream end of the drops. Weep drains will be installed in the drops to release hydrostatic pressure from under the drops and reduce the uplift forces on the grouted channel lining.

HEC-RAS and specific force calculations under both supercritical and subcritical flow regimes were used to determine the hydraulic jump location along the drops, and the stilling basin length and depth. The analysis was completed using varying flowrates such as for the 100-year, 10-year and low flow conditions, to determine the controlling hydraulic jump location (located the farthest downstream) and longest jump length for each drop. The controlling storm event for each drop is included in Appendix C. The 100-year storm event was the controlling condition for the upstream drop. However, due to backwater effects of the arch culvert, the downstream drop is submerged during a 100-year storm. The 10-year storm event is therefore the controlling condition for sizing the drop basin. Riprap will be placed downstream of the sill for a minimum distance of 10-feet to minimize erosion that may occur due to secondary currents.

Seepage analyses using the Lane's Weighted Creep Method were completed to determine the upstream cutoff depth required at each drop. Due to the drops being in either close proximity to or within bedrock, a low Creep Ratio of 1.6 was used. Calculations show that a cutoff depth in addition to what the boulders provide is not needed. However, a minimum 2-foot cutoff depth below the bottom of boulders (or 4.5-feet below the channel invert elevation) is still recommended, and will help key each structure into the shallow bedrock where encountered.

Based upon the hydraulic calculations and USDCM, the following design criteria have been established for the grouted sloping boulder drops.

- Drop height ($H_d$)(elevation difference between crest and top of sill): 4.0-ft
- Typical trapezoidal or composite channel section to continue through drop. Grouted boulders to extend on each side to 1.0-ft vertically above the 100-year water surface elevation.
- Drop face slope: 5:1
- Boulder size: 30-inch minimum, with 30-inch to 36-inch boulders for sill.

- Grouted boulder bedding: Undisturbed soil or compacted subgrade. For areas where shallow bedrock is encountered, bedding will be a minimum 12-inch thick layer of 1-1/2" to 2-1/2" crushed rock.
- Approach length: 10-ft grouted boulders followed by 10-ft Type M soil riprap (2.0-ft thick), not buried along the channel bottom.
- Upstream cutoff wall depth: 4.5-ft grout cutoff wall, placed monolithically with grout placed for boulders.
- Weep drain system: Yes
- Stilling basin depth: 2.0-ft
- Stilling basin length: 20-ft
- Downstream length of riprap protection: Minimum of 10 linear feet of Type M soil riprap (2.0-ft thick), not buried along channel bottom.

Refer to Appendix C for drop structure design and rock sizing calculations.

Wherever soil riprap linings are proposed, rock sizing and freeboard criteria followed is in accordance with Chapter 8 of the Mile High Flood District's Urban Storm Drainage Criteria Manual, Equation 8-11.

A geotechnical investigation was conducted to support the design of the foundation for the bridge at Sterling Ranch Road and Briargate Parkway. The geotechnical report is included with this submittal. Two soil borings were drilled near the locations of the proposed footings for the bridges. Bedrock is shallow at Sterling Ranch Road and Briargate Parkway, so spread footings will be used. A precast bridge section has been chosen that has a 43-foot clear span and a 24.5-foot rise. The 100-year discharge can be passed through the bridge at a maximum depth of approximately 7.6 feet and headwater to depth of 0.31. The velocity during a 100-year event at the upstream and downstream reach of the bridge is 5.9 feet per second and 12.1 feet per second, respectively. A Type M void-filled riprap invert will be provided at each bridge crossing. The construction of the improvements shown on the plans will prevent erosion due to changes in the channel hydraulic characteristics of the bridge and extend downstream to an extent where current conditions are matched.

## VIII. HYDRAULIC MODELLING RESULTS

HECRAS model output including tables and sections are included in the Appendix. The results indicate that the proposed Briargate crossing has conveyance capacity is well in excess during 100-year storm events. As seen in the following, the 100-year water surface elevations are below those of corrected effective model throughout the revised channel reach. Freeboard from the crown of the Conspan crossing is well in excess of 2 feet per El Paso County criteria. HECRAS model output is included in the Appendix.




HECRAS profile comparison of proposed (blue filled) and existing 100-yr WSEL




Upstream face Conspan crossing 100-yr WSEL.

## IX. SCOUR ANALYSIS

Scour analysis was performed to determine if bridge foundations and channel drop structures are susceptible to undermining during major storm events. Per CDOT Drainage Manual Section 10.4.3, the 500-year storm was used for scour analysis of the Conspan crossing abutment and foundation. Scour analysis in HECRAS is limited to bridges and therefor not available for the Conspan crossing modelled as a culvert. Therefor the shear stress variable calculated in HECRAS was used to determine the likelihood of scour. The crossing design includes riprap lining of the channel invert with added protection for the embankment on the downstream end of the crossing. This is shown on Figure 2 of Appendix A.

As seen from Table 1 below, shear stress through the bridge reach is well below 5 lbs/ft$^2$ tolerance for the type M soil riprap lining of the channel bottom and embankments during 100-year and 500-year simulations. Velocities downstream of the bridge are comparable to existing conditions and will not result in an increase of erosive conditions.

**Table 1 HECRAS Shear Stress and Velocity at Proposed Conspan Crossing**

| | | 100-Yr Profile | | 500-Yr Profile | |
|---|---|---|---|---|---|
| Location | Section | Maximum Velocity (ft/s) | Shear Stress Channel(lb/ft$^2$) | Maximum Velocity (ft/s) | Shear Stress Channel(lb/ft$^2$) |
| 30' Upstream of Bridge | 7205 | 3.5 | 0.4 | 3.7 | 0.4 |
| Upstream Bridge Face | 7175 | 5.9 | 1.0 | 6.8 | 1.3 |
| Downstream Bridge Face | 6929 | 12.1 | 4.0 | 13.7 | 4.7 |
| 40' Downstream of Bridge | 6889 | 10.1 | 1.4 | 11.4 | 1.6 |
| 69' Downstream of Bridge | 6760 | 8.7 | 1.2 | 9.9 | 1.4 |

Note: Permissible shear stress Type M soil riprap is 5 lb/ft$^2$

## X. CONSTRUCTION PERMITTING

The following permits are anticipated to allow for the construction of the project as shown on the design plans. A copy of the Sterling Ranch 404 Permit is included within the Appendix.

USACE notification of project in conformance with 404 permit - USACE

No-Rise Floodway Certification, Floodplain Development Permit – Pikes Peak Regional Building Department

Grading and Erosion Control Permit (ESQCP) – El Paso County

Construction Stormwater Discharge Permit – CDPHE

Construction Dewatering Permit - CDPHE

Letter of Map Revision (post construction) - FEMA

## XI. DRAINAGE AND BRIDGE FEES

The Sterling Ranch Development and specifically Sterling Ranch East lies wholly within the Sand Creek drainage basin. Drainage and bridge fees have been established by the County for the

Sand Creek drainage basin for assessment against platted land within the watershed. The bridge will be public and owned and maintained by the El Paso County upon acceptance. The costs for the public drainageway improvements are reimbursable or creditable against drainage and bridge fees owed when land within Sterling Ranch is platted. Reimbursement of drainage and bridge improvements require approval through the DCM reimbursement process. Construction of the bridge at Sterling Ranch Road and at Briargate Parkway will be creditable against bridge fees owed pending approval through the DCM reimbursement process.

The 1996 Sand Creek DBPS identifies the project section as reaches SC-8 and SC-9 with two check structures for conveyance improvements and a (4) 10'W x 8'H CBC crossing at Briargate Parkway. Adjusted for 2022 dollars, the total cost for the 1996 DBPS improvements is $359,731. The total cost estimate for the current crossing and channel improvement design is $1,610,466. Detailed cost estimates and comparison to the 1996 DBPS are included in Appendix F.

The current 2021 drainage and bridge fees for the Sand Creek drainage basin are as follows:

| | |
|---|---|
| Drainage Fee: | $20,387 per impervious acre |
| Bridge Fee: | $ 8,339 per acre |

## XII. PHASING

Construction of the drainage and bridge facilities shown on the plans is to be completed all at once and no phasing of the construction is proposed. The construction will commence prior to or concurrent with the subdivisions east of Sand Creek.

## XIII. CONCLUSIONS

The development of the future subdivisions to the east requires the Briargate Bridge crossing of Sand Creek. Per direction of El Paso County and the Army Corps of Engineers, improvements to Sand Creek through the Sterling Ranch Development were limited to stabilize the channel upstream and downstream reach of the proposed Briargate Boulevard Bridge. Results of hydraulic analysis demonstrate that the channel and Conspan crossing have adequate capacity to carry effective 100-year flows without causing an increase to existing water surface elevations. Shear stress analysis indicates that the riprap channel protection is sufficient to prevent undermining of the structure during major storm events and will not result in adverse impacts to the downstream natural channel compared to existing conditions.

# APPENDIX TABLE OF CONTENTS

**Appendix A: Floodplain**
Figure 1 Vicinity Map
Figure 2 Briargate Bridge Floodplain Workmap
Annotated FIRM

**Appendix B: Hydrology**
2018 MDDP Hydrology Existing Conditions Map

**Appendix C: Drop Structure and Riprap Calculations**

**Appendix D: HECRAS Hydraulic Modelling**

**Appendix E: Contech Bridge Design Analysis**

**Appendix F: Improvement Costs**

## Appendix A: Floodplain

**Figure 1 Vicinity Map**

**Figure 2 Briargate Bridge Floodplain Workmap**

**Annotated FIRM**

FIGURE 1
VICINITY MAP
BRAIRGATE BRIDGE




0 100'

SCALE: 1"=100'

Kiowa
Engineering Corporation
7175 West Jefferson Avenue, Suite 2200
Lakewood, Colorado 80235
(303) 692-0369

## LEGEND

- HECRAS MODEL SECTION
- EFFECTIVE 100–YEAR
- CORRECTED EFFECTIVE 100–YEAR
- PROPOSED 100–YEAR
- PARCEL

FIGURE 2
FLOODPLAIN WORKMAP
BRIARGATE BRIDGE AT SAND CREEK




# SAND CREEK ANNOTATED FIRM
## BRIARGATE BRIDGE

JUNE 2022
PROJECT NO. 19032

Kiowa Engineering Corporation
7175 West Jefferson Avenue, Suite 2200
Lakewood, Colorado 80235
(303) 692-0369

# Appendix B: Hydrology

## 2018 MDDP Hydrology Existing Conditions Map




0 600 1200 2400
Scale in Feet

**LEGEND**

BASIN ID – SC3-77

DESIGN POINT – 87

REACH IDENTIFIER – RT-17A

BASIN BOUNDARY

EAST FORK SAND CREEK BASIN BOUNDARY

FLOW DIRECTION –

FOR LOCATING & MARKING GAS, ELECTRIC, WATER & TELEPHONE LINES

FOR BURIED UTILITY INFORMATION 48 HRS BEFORE YOU DIG CALL 1-800-922-1987

File: O:\09002A\Sterling Ranch District\dwg\Eng Exhibits\2018 MDDP\2018-MDDP-ExistCondWSMapMap.dwg Plotstamp: 11/13/2018 1:52 PM

**BASIN SUMMARY**

| BASIN | CN | AREA (acres) | AREA (sq mi) | $Q_2$ (cfs) | $Q_5$ (cfs) | $Q_{10}$ (cfs) | $Q_{25}$ (cfs) | $Q_{50}$ (cfs) | $Q_{100}$ (cfs) |
|---|---|---|---|---|---|---|---|---|---|
| EX-0 | 62 | 23.8 | 0.037 | 5.0 | 8.2 | 13.0 | 19.6 | 25.7 | 32.2 |
| EX-1 | 62 | 25.7 | 0.040 | 4.8 | 7.9 | 12.4 | 18.7 | 24.5 | 30.9 |
| EX-2 | 62 | 5.5 | 0.009 | 1.1 | 1.8 | 2.8 | 4.3 | 5.6 | 7.1 |
| EX-3 | 62 | 136.8 | 0.214 | 22.0 | 36.4 | 57.6 | 86.9 | 114.0 | 143.1 |
| EX-3A | 61 | 188.1 | 0.294 | 28.3 | 47.4 | 75.7 | 115.1 | 152.2 | 192.6 |
| EX-4 | 62 | 192.0 | 0.300 | 30.1 | 49.9 | 79.1 | 119.5 | 157.0 | 197.3 |
| EX-4A | 62 | 151.5 | 0.237 | 24.7 | 40.8 | 64.4 | 97.0 | 127.2 | 160.1 |
| EX-5 | 62 | 153.9 | 0.240 | 24.2 | 40.0 | 63.4 | 95.9 | 125.9 | 158.2 |
| EX-6 | 62 | 90.2 | 0.141 | 15.3 | 25.5 | 40.1 | 60.7 | 79.9 | 100.5 |
| EX-7 | 56 | 165.0 | 0.258 | 11.6 | 21.5 | 37.5 | 60.9 | 83.1 | 107.4 |
| EX-8 | 45 | 42.0 | 0.066 | 0.5 | 1.7 | 4.5 | 9.4 | 14.5 | 20.5 |
| EX-9 | 54 | 131.9 | 0.206 | 12.2 | 23.9 | 43.1 | 70.9 | 97.0 | 125.2 |
| EX-10 | 60 | 270.7 | 0.423 | 32.7 | 56.0 | 91.1 | 140.1 | 185.9 | 236.1 |
| EX-10A | 41 | 179.3 | 0.280 | 0.6 | 2.2 | 7.3 | 17.4 | 29.1 | 43.1 |
| EX-11 | 43 | 209.3 | 0.327 | 18.0 | 29.8 | 47.7 | 73.4 | 98.3 | 126.1 |
| EX-12 | 51 | 39.5 | 0.062 | 2.2 | 5.1 | 10.1 | 17.7 | 25.1 | 33.3 |
| EX-13 | 55 | 89.3 | 0.139 | 7.7 | 15.2 | 27.1 | 44.2 | 60.5 | 78.4 |
| EX-20 | 62 | 143.4 | 0.224 | 25.4 | 42.1 | 66.7 | 100.7 | 132.3 | 166.2 |
| EX-20A | 64 | 179.7 | 0.281 | 32.2 | 51.9 | 80.5 | 119.8 | 155.9 | 194.6 |
| EX-21 | 65 | 33.3 | 0.052 | 8.6 | 13.5 | 20.7 | 30.5 | 39.4 | 49.0 |
| EX-24 | 59 | 63.1 | 0.099 | 9.5 | 16.6 | 27.5 | 42.9 | 57.4 | 73.0 |
| EX-25 | 43 | 54.4 | 0.085 | 0.3 | 1.5 | 4.8 | 10.7 | 17.2 | 25.1 |
| EX-73 | 63 | 90.0 | 0.141 | 16.4 | 26.4 | 41.3 | 62.1 | 81.3 | 102.0 |
| EX-74 | 63 | 119.7 | 0.187 | 22.3 | 36.5 | 57.3 | 85.9 | 112.3 | 140.7 |
| EX-75 | 63 | 79.3 | 0.124 | 13.1 | 21.5 | 33.7 | 50.5 | 66.1 | 82.8 |
| EX-76 | 63 | 86.4 | 0.135 | 14.2 | 23.1 | 36.4 | 54.6 | 71.4 | 89.6 |
| EX-77 | 62 | 230.6 | 0.360 | 34.7 | 56.9 | 90.6 | 137.5 | 180.9 | 227.7 |
| EX-78 | 63 | 155.6 | 0.243 | 28.1 | 45.3 | 70.6 | 106.2 | 139.1 | 174.5 |
| EX-79 | 63 | 189.0 | 0.295 | 34.9 | 57.0 | 89.5 | 134.3 | 175.6 | 220.1 |
| EX-80 | 63 | 147.7 | 0.231 | 27.3 | 44.3 | 69.6 | 104.5 | 136.8 | 171.4 |
| EX-81 | 62 | 262.9 | 0.411 | 42.6 | 70.2 | 111.0 | 167.4 | 219.6 | 275.7 |
| EX-82 | 62 | 117.8 | 0.184 | 20.0 | 33.2 | 52.8 | 80.0 | 105.1 | 132.3 |
| EX-88 | 62 | 139.2 | 0.217 | 22.2 | 36.7 | 58.0 | 87.6 | 115.0 | 144.4 |

**DESIGN POINT SUMMARY (PEAK FLOW)**

| DESIGN POINT | AREA (sq mi) | $Q_2$ (cfs) | $Q_5$ (cfs) | $Q_{10}$ (cfs) | $Q_{25}$ (cfs) | $Q_{50}$ (cfs) | $Q_{100}$ (cfs) | LOCATION |
|---|---|---|---|---|---|---|---|---|
| DP-74 | 0.371 | 39.3 | 65.3 | 104.8 | 158.9 | 209.1 | 262.8 | |
| DP-75 | 1.413 | 141.2 | 235.1 | 376.6 | 566.6 | 750.9 | 950.5 | |
| DP-78 | 0.538 | 59.7 | 98.4 | 154.0 | 232.6 | 306.2 | 385.3 | |
| DP-73 | 2.528 | 225.9 | 380.7 | 618.0 | 957.0 | 1260.4 | 1582.3 | |
| DP-71 | 2.669 | 229.3 | 388.9 | 629.7 | 978.8 | 1277.3 | 1637.9 | STERLING RANCH NORTHERN BNDRY |
| DP-69 | 3.209 | 253.0 | 434.8 | 707.7 | 1100.0 | 1453.3 | 1870.4 | |
| DP-63 | 3.446 | 251.4 | 430.7 | 713.1 | 1113.2 | 1496.2 | 1911.5 | STERLING RANCH SOUTHERN BNDRY |
| DP-10 | 0.508 | 36.5 | 56.0 | 106.4 | 162.9 | 220.6 | 287.2 | COLORADO SPRINGS/EL PASO BNDRY |
| DP-9A | 0.557 | 55.3 | 94.3 | 150.3 | 227.7 | 299.5 | 380.5 | VOLLMER/TAHITI DRIVE |
| DP-9 | 0.505 | 52.8 | 88.8 | 142.1 | 214.2 | 281.0 | 351.4 | VOLLMER/LOCHWINNOCH LN |
| DP-8A | 0.139 | 7.7 | 15.2 | 27.1 | 44.2 | 60.5 | 78.4 | D/S STERLING RANCH EASTERN BNDRY |
| DP-8 | 0.528 | 24.2 | 45.1 | 77.8 | 124.4 | 169.5 | 220.9 | D/S STERLING RANCH SOUTHERN BNDRY |
| DP-7 | 0.703 | 32.4 | 57.1 | 97.3 | 156.1 | 213.8 | 277.9 | STERLING RANCH SOUTHERN BNDRY |
| DP-6 | 0.206 | 12.2 | 23.9 | 43.1 | 70.9 | 97.0 | 125.2 | STERLING RANCH SOUTHERN BNDRY |
| DP-5 | 0.066 | 0.5 | 1.7 | 4.5 | 9.4 | 14.5 | 20.5 | STERLING RANCH SOUTHERN BNDRY |
| DP-4 | 0.258 | 11.6 | 21.5 | 37.5 | 60.9 | 83.1 | 107.4 | STERLING RANCH SOUTHERN BNDRY |
| DP-3 | 0.009 | 1.1 | 1.8 | 2.8 | 4.3 | 5.6 | 7.1 | STERLING RANCH SOUTHERN BNDRY |
| DP-2 | 0.040 | 4.8 | 7.9 | 12.4 | 18.7 | 24.5 | 30.9 | STERLING RANCH SOUTHERN BNDRY |
| DP-1 | 0.037 | 5.0 | 8.2 | 13.0 | 19.6 | 25.7 | 32.2 | STERLING RANCH SOUTHERN BNDRY |
| DP-60A | 3.545 | 247.7 | 430.2 | 707.1 | 1113.0 | 1496.6 | 1913.5 | FUTURE MARKSHEFFEL X-ING |
| DP-56 | 0.466 | 23.2 | 42.5 | 71.9 | 115.6 | 157.4 | 202.9 | STERLING RANCH SOUTHERN BNDRY |
| DP-53A | 4.138 | 262.1 | 454.0 | 763.2 | 1196.5 | 1609.8 | 2061.5 | SAND CREEK AND POND 3 |

**DESIGN POINT SUMMARY (VOLUME)**

| DESIGN POINT | AREA (sq mi) | $V_2$ (ac-ft) | $V_5$ (ac-ft) | $V_{10}$ (ac-ft) | $V_{25}$ (ac-ft) | $V_{50}$ (ac-ft) | $V_{100}$ (ac-ft) | LOCATION |
|---|---|---|---|---|---|---|---|---|
| DP-74 | 0.371 | 5.9 | 9.0 | 13.6 | 19.8 | 25.5 | 31.6 | |
| DP-75 | 1.413 | 22.7 | 34.5 | 51.7 | 75.4 | 97.1 | 120.5 | |
| DP-78 | 0.538 | 8.9 | 13.5 | 20.1 | 29.3 | 37.7 | 46.7 | |
| DP-73 | 2.528 | 40.4 | 61.5 | 92.1 | 134.3 | 173.1 | 214.9 | |
| DP-71 | 2.669 | 42.5 | 64.9 | 97.1 | 141.6 | 182.5 | 226.6 | STERLING RANCH NORTHERN BNDRY |
| DP-69 | 3.209 | 50.7 | 77.4 | 116.1 | 169.4 | 218.6 | 271.4 | |
| DP-63 | 3.446 | 54.1 | 82.5 | 123.8 | 180.8 | 233.3 | 289.9 | STERLING RANCH SOUTHERN BNDRY |
| DP-10 | 0.508 | 7.6 | 11.7 | 17.6 | 25.8 | 33.4 | 41.6 | COLORADO SPRINGS/EL PASO BNDRY |
| DP-9A | 0.557 | 9.3 | 14.1 | 21.1 | 30.7 | 39.4 | 48.8 | VOLLMER/TAHITI DRIVE |
| DP-9 | 0.505 | 8.4 | 12.7 | 19.0 | 27.6 | 35.5 | 44.0 | VOLLMER/LOCHWINNOCH LN |
| DP-8A | 0.139 | 1.3 | 2.1 | 3.4 | 5.2 | 7.0 | 8.9 | D/S STERLING RANCH EASTERN BNDRY |
| DP-8 | 0.528 | 4.4 | 7.0 | 11.1 | 16.8 | 22.3 | 28.4 | D/S STERLING RANCH SOUTHERN BNDRY |
| DP-7 | 0.703 | 6.1 | 10.0 | 15.9 | 24.3 | 32.4 | 41.3 | STERLING RANCH SOUTHERN BNDRY |
| DP-6 | 0.206 | 2.4 | 4.0 | 6.3 | 9.6 | 12.7 | 16.0 | STERLING RANCH SOUTHERN BNDRY |
| DP-5 | 0.066 | 0.2 | 0.4 | 0.8 | 1.4 | 1.9 | 2.6 | STERLING RANCH SOUTHERN BNDRY |
| DP-4 | 0.258 | 2.6 | 4.2 | 6.7 | 10.2 | 13.5 | 17.2 | STERLING RANCH SOUTHERN BNDRY |
| DP-3 | 0.009 | 0.1 | 0.2 | 0.3 | 0.5 | 0.6 | 0.8 | STERLING RANCH SOUTHERN BNDRY |
| DP-2 | 0.040 | 0.6 | 0.9 | 1.4 | 2.1 | 2.7 | 3.4 | STERLING RANCH SOUTHERN BNDRY |
| DP-1 | 0.037 | 0.6 | 0.9 | 1.3 | 1.9 | 2.5 | 3.1 | STERLING RANCH SOUTHERN BNDRY |
| DP-60A | 3.545 | 55.3 | 84.4 | 126.4 | 184.8 | 238.5 | 296.6 | FUTURE MARKSHEFFEL X-ING |
| DP-56 | 0.466 | 4.0 | 6.3 | 9.9 | 14.9 | 19.8 | 25.1 | SAND CREEK AND POND 3 |
| DP-53A | 4.138 | 63.0 | 96.4 | 144.7 | 211.8 | 273.9 | 340.9 | SAND CREEK AND POND 3 |

**EFSC DBPS DESIGN POINT SUMMARY (PEAK FLOW)**

| DBPS DESIGN POINT | AREA (sq mi) | $Q_{50}$ (cfs) | $Q_{100}$ (cfs) |
|---|---|---|---|
| DP-50 | 0.32 | 47.0 | 195.7 |
| DP-51 (BASIN 86) | 0.33 | 17.7 | 74.1 |
| DP-52 | 1.67 | 80.5 | 455.5 |
| DP-56 | 0.79 | 63.6 | 265.0 |

Values reported from SCDBPS
(DP 50, 51, 52 Not analyzed as a part of this study)
DBPS Reach 85(Basin91)=Q10=28.8cfs Q100=115.2cfs

Discharge Summary
Sand Creek

DP-63 So PL 1912

DP 69 @ Briargate +/- 1870

DP 71 No PL 1637

Q100 FIS = 2600 cfs


M&S CIVIL CONSULTANTS, INC
20 BOULDER CRESCENT, SUITE 110
COLORADO SPRINGS, CO 80903
PHONE: 719.955.5485


# 2018 STERLING RANCH MDDP

## EXISTING HYDROLOGIC CONDITIONS MAP

PROJECT NO. 09-002
FILE: \dwg\Eng Exhibits\2018-MDDP-ExistCondWSMapMap.dwg
DESIGNED BY: DLM
DRAWN BY: DLM
CHECKED BY: VAS
SCALE
HORIZ: NTS
VERT: NTS
DATE: 08-22-18

DM1

# Appendix C: Drop Structure and Riprap Calculations

# Briargate Bridge at Sand Creek
## Hydraulic Jump and Basin Length Calculations

**4' Drop Structure A (Crest Station 73+60)**

Hec Ras Mixed Flow Analysis (100-year)

| | | | | Supercritical Analysis | | | | | | Subcritical Analysis | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | River Sta | Q Total | Min Ch El | W.S. Elev | Crit W.S. | Vel Chnl | Froude # Chl | Max Chl Dpth | Specif Force | W.S. Elev | Crit W.S. | Vel Chnl | Froude # Chl | Max Chl Dpth | Specif Force |
| | | (cfs) | (ft) | (ft) | (ft) | (ft/s) | | (ft) | (cu ft) | (ft) | (ft) | (ft/s) | | (ft) | (cu ft) |
| Drop Crest | 7360 | 2600 | 7097.00 | 7099.17 | 7099.72 | 11.38 | 1.45 | 2.17 | 1151.50 | 7099.72 | 7099.72 | 8.82 | 1.00 | 2.72 | 1088.12 |
| | 7359 | 2600 | 7096.80 | 7099.47 | 7099.57 | 9.26 | 1.07 | 2.67 | 1094.59 | 7099.57 | 7099.57 | 8.86 | 1.01 | 2.77 | 1092.22 |
| | 7358 | 2600 | 7096.60 | 7099.16 | 7099.42 | 9.98 | 1.19 | 2.56 | 1110.86 | 7099.42 | 7099.42 | 8.89 | 1.01 | 2.82 | 1096.46 |
| | 7357 | 2600 | 7096.40 | 7099.28 | 7099.28 | 8.92 | 1.01 | 2.88 | 1101.01 | 7099.28 | 7099.28 | 8.90 | 1.01 | 2.88 | 1100.98 |
| | 7356 | 2600 | 7096.20 | 7098.91 | 7099.14 | 9.85 | 1.16 | 2.71 | 1116.11 | 7099.14 | 7099.14 | 8.93 | 1.01 | 2.94 | 1105.68 |
| | 7355 | 2600 | 7096.00 | 7098.64 | 7098.99 | 10.43 | 1.25 | 2.64 | 1134.70 | 7098.99 | 7098.99 | 8.95 | 1.01 | 2.99 | 1110.59 |
| | 7354 | 2600 | 7095.80 | 7098.81 | 7098.85 | 9.13 | 1.03 | 3.00 | 1116.09 | 7098.85 | 7098.85 | 8.98 | 1.00 | 3.05 | 1115.66 |
| | 7353 | 2600 | 7095.60 | 7098.45 | 7098.70 | 10.00 | 1.17 | 2.85 | 1132.47 | 7098.70 | 7098.70 | 9.01 | 1.01 | 3.10 | 1120.80 |
| | 7352 | 2600 | 7095.40 | 7098.20 | 7098.55 | 10.52 | 1.25 | 2.80 | 1150.24 | 7098.56 | 7098.56 | 9.01 | 1.00 | 3.16 | 1126.17 |
| | 7351 | 2600 | 7095.20 | 7098.37 | 7098.41 | 9.22 | 1.03 | 3.16 | 1132.02 | 7098.41 | 7098.41 | 9.07 | 1.01 | 3.21 | 1131.59 |
| | 7350 | 2600 | 7095.00 | 7098.02 | 7098.25 | 10.05 | 1.16 | 3.02 | 1148.10 | 7098.26 | 7098.26 | 9.09 | 1.01 | 3.26 | 1137.28 |
| | 7349 | 2600 | 7094.80 | 7097.76 | 7098.12 | 10.57 | 1.24 | 2.96 | 1165.81 | 7098.12 | 7098.12 | 9.11 | 1.00 | 3.32 | 1142.91 |
| | 7348 | 2600 | 7094.60 | 7097.93 | 7097.96 | 9.30 | 1.03 | 3.33 | 1149.10 | 7097.97 | 7097.97 | 9.15 | 1.01 | 3.37 | 1148.70 |
| | 7347 | 2600 | 7094.40 | 7097.57 | 7097.81 | 10.14 | 1.16 | 3.17 | 1165.50 | 7097.98 | 7097.82 | 8.65 | 0.92 | 3.58 | 1157.82 |
| | 7346 | 2600 | 7094.20 | 7097.31 | 7097.67 | 10.68 | 1.24 | 3.11 | 1183.78 | 7098.04 | 7097.67 | 8.05 | 0.83 | 3.84 | 1178.62 |
| Jump Begins | 7345 | 2600 | 7094.00 | 7097.48 | 7097.52 | 9.41 | 1.03 | 3.48 | 1166.90 | 7098.09 | 7097.53 | 7.58 | 0.76 | 4.09 | 1207.68 |
| | 7344 | 2600 | 7093.80 | 7097.12 | 7097.37 | 10.24 | 1.16 | 3.32 | 1183.37 | 7098.12 | 7097.38 | 7.18 | 0.71 | 4.32 | 1242.90 |
| | 7343 | 2600 | 7093.60 | 7096.86 | 7097.23 | 10.78 | 1.23 | 3.25 | 1201.65 | 7098.15 | 7097.23 | 6.84 | 0.66 | 4.55 | 1283.53 |
| | 7342 | 2600 | 7093.40 | 7097.03 | 7097.07 | 9.52 | 1.03 | 3.63 | 1185.01 | 7098.17 | 7097.07 | 6.54 | 0.61 | 4.77 | 1328.30 |
| | 7341 | 2600 | 7093.20 | 7096.67 | 7096.93 | 10.35 | 1.15 | 3.47 | 1201.32 | 7098.19 | 7096.93 | 6.27 | 0.58 | 4.99 | 1376.75 |
| | 7340 | 2600 | 7093.00 | 7096.40 | 7096.77 | 10.89 | 1.23 | 3.40 | 1219.05 | 7098.21 | 7096.78 | 6.03 | 0.55 | 5.21 | 1429.02 |
| | 7339 | 2600 | 7092.80 | 7096.57 | 7096.62 | 9.65 | 1.04 | 3.77 | 1202.93 | 7098.22 | 7096.63 | 5.82 | 0.52 | 5.42 | 1483.67 |
| | 7338 | 2600 | 7092.60 | 7096.20 | 7096.47 | 10.49 | 1.16 | 3.60 | 1219.34 | 7098.24 | 7096.48 | 5.62 | 0.49 | 5.64 | 1542.41 |
| | 7337 | 2600 | 7092.40 | 7096.32 | 7096.32 | 9.52 | 1.01 | 3.92 | 1213.62 | 7098.25 | 7096.32 | 5.43 | 0.47 | 5.85 | 1603.32 |
| | 7336 | 2600 | 7092.20 | 7095.92 | 7096.17 | 10.46 | 1.14 | 3.72 | 1228.56 | 7098.26 | 7096.17 | 5.27 | 0.45 | 6.06 | 1666.79 |
| | 7335 | 2600 | 7092.00 | 7095.64 | 7096.02 | 11.04 | 1.22 | 3.64 | 1246.66 | 7098.27 | 7096.02 | 5.11 | 0.43 | 6.27 | 1733.43 |
| | 7334 | 2600 | 7091.80 | 7095.81 | 7095.86 | 9.81 | 1.03 | 4.01 | 1230.89 | 7098.28 | 7095.86 | 4.96 | 0.41 | 6.48 | 1802.53 |
| | 7333 | 2600 | 7091.60 | 7095.44 | 7095.72 | 10.65 | 1.15 | 3.84 | 1246.72 | 7098.29 | 7095.71 | 4.83 | 0.39 | 6.69 | 1872.97 |
| | 7332 | 2600 | 7091.40 | 7095.17 | 7095.56 | 11.19 | 1.23 | 3.77 | 1263.96 | 7098.29 | 7095.56 | 4.70 | 0.38 | 6.89 | 1946.54 |
| | 7331 | 2600 | 7091.20 | 7095.34 | 7095.41 | 9.96 | 1.04 | 4.14 | 1247.38 | 7098.30 | 7095.41 | 4.58 | 0.36 | 7.10 | 2021.13 |
| Drop Toe | 7330 | 2600 | 7091.00 | 7094.98 | 7095.25 | 10.79 | 1.16 | 3.98 | 1263.40 | 7098.31 | 7095.25 | 4.47 | 0.35 | 7.31 | 2098.36 |
| | 7329 | 2600 | 7091.00 | 7094.96 | 7095.25 | 10.85 | 1.17 | 3.96 | 1264.56 | 7098.30 | 7095.26 | 4.47 | 0.35 | 7.30 | 2098.11 |
| | 7328 | 2600 | 7091.00 | 7094.94 | 7095.25 | 10.92 | 1.18 | 3.94 | 1265.58 | 7098.30 | 7095.25 | 4.46 | 0.35 | 7.30 | 2098.21 |
| | 7327 | 2600 | 7091.00 | 7094.93 | 7095.25 | 10.94 | 1.18 | 3.93 | 1265.97 | 7098.30 | 7095.25 | 4.46 | 0.35 | 7.30 | 2097.58 |

Jump begins at Sta. 73+45 which is on the drop face, 15' upstream of the drop toe (Sta. 73+30). Calculate minimum drop basin length starting from drop toe:

Hydraulic Jump Length, Figure 15-4 (Chow)

| | | | |
|---|---|---|---|
| $F_1$ = | 1.24 | $L/Y_2$ = | 3.5 |
| $Y_2$ (ft)= | 7.31 | L (ft)= | 25.59 |
| | | 60%L (ft)= | 15.35 |

| (Minimum required length from toe for protection, minimum Basin Length) = **15.4'** | **use 20'** |
|---|---|

Froude No. at beginning of hydraulic jump

Specific Force (cu ft) at beginning of hydraulic jump (at location where Specific Force (subcritical) > Specific Force (supercritical))

Maximum Channel Depth (ft) at approximate downstream end of hydraulic jump

# Briargate Bridge at Sand Creek
## Hydraulic Jump and Basin Length Calculations

**4' Drop Structure B (Crest Station 72+55)**

Hec Ras Mixed Flow Analysis (10-year)

| | | | | Supercritical Analysis | | | | | | Subcritical Analysis | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | River Sta | Q Total | Min Ch El | W.S. Elev | Crit W.S. | Vel Chnl | Froude # Chl | Max Chl Dpth | Specif Force | W.S. Elev | Crit W.S. | Vel Chnl | Froude # Chl | Max Chl Dpth | Specif Force |
| | | (cfs) | (ft) | (ft) | (ft) | (ft/s) | | (ft) | (cu ft) | (ft) | (ft) | (ft/s) | | (ft) | (cu ft) |
| Drop Crest | 7255 | 1200 | 7093.00 | 7094.98 | 7094.98 | 7.56 | 1.00 | 1.98 | 430.85 | 7094.97 | 7094.97 | 7.57 | 1.01 | 1.97 | 430.86 |
| | 7254 | 1200 | 7092.80 | 7094.62 | 7094.82 | 8.55 | 1.19 | 1.82 | 438.99 | 7094.82 | 7094.82 | 7.60 | 1.00 | 2.02 | 433.33 |
| | 7253 | 1200 | 7092.60 | 7094.36 | 7094.66 | 9.15 | 1.30 | 1.76 | 448.88 | 7094.66 | 7094.66 | 7.66 | 1.01 | 2.06 | 436.01 |
| | 7252 | 1200 | 7092.40 | 7094.14 | 7094.50 | 9.59 | 1.38 | 1.74 | 458.36 | 7094.51 | 7094.51 | 7.68 | 1.00 | 2.11 | 438.76 |
| Jump Begins | 7251 | 1200 | 7092.20 | 7094.35 | 7094.35 | 7.70 | 1.00 | 2.15 | 441.66 | 7094.39 | 7094.35 | 7.57 | 0.98 | 2.19 | 441.77 |
| | 7250 | 1200 | 7092.00 | 7093.99 | 7094.20 | 8.72 | 1.19 | 1.99 | 450.43 | 7094.46 | 7094.20 | 6.79 | 0.83 | 2.46 | 451.73 |
| | 7249 | 1200 | 7091.80 | 7093.73 | 7094.04 | 9.32 | 1.29 | 1.93 | 460.78 | 7094.50 | 7094.04 | 6.23 | 0.73 | 2.70 | 468.85 |
| | 7248 | 1200 | 7091.60 | 7093.50 | 7093.88 | 9.80 | 1.38 | 1.90 | 471.20 | 7094.53 | 7093.89 | 5.80 | 0.66 | 2.93 | 490.68 |
| | 7247 | 1200 | 7091.40 | 7093.73 | 7093.73 | 7.88 | 1.01 | 2.33 | 454.37 | 7094.55 | 7093.73 | 5.44 | 0.60 | 3.15 | 516.22 |
| | 7246 | 1200 | 7091.20 | 7093.36 | 7093.57 | 8.89 | 1.18 | 2.16 | 463.35 | 7094.57 | 7093.57 | 5.13 | 0.55 | 3.37 | 544.91 |
| | 7245 | 1200 | 7091.00 | 7093.10 | 7093.42 | 9.47 | 1.28 | 2.10 | 473.72 | 7094.58 | 7093.42 | 4.88 | 0.51 | 3.58 | 575.78 |
| | 7244 | 1200 | 7090.80 | 7093.26 | 7093.26 | 8.01 | 1.01 | 2.46 | 464.66 | 7094.60 | 7093.27 | 4.64 | 0.47 | 3.80 | 609.70 |
| | 7243 | 1200 | 7090.60 | 7092.90 | 7093.11 | 9.01 | 1.18 | 2.29 | 473.81 | 7094.61 | 7093.11 | 4.44 | 0.44 | 4.01 | 645.31 |
| | 7242 | 1200 | 7090.40 | 7092.64 | 7092.95 | 9.58 | 1.27 | 2.24 | 483.78 | 7094.62 | 7092.96 | 4.26 | 0.42 | 4.22 | 683.08 |
| | 7241 | 1200 | 7090.20 | 7092.80 | 7092.80 | 8.13 | 1.00 | 2.60 | 475.60 | 7094.62 | 7092.80 | 4.10 | 0.39 | 4.42 | 721.84 |
| | 7240 | 1200 | 7090.00 | 7092.43 | 7092.65 | 9.14 | 1.17 | 2.43 | 484.70 | 7094.63 | 7092.65 | 3.96 | 0.37 | 4.63 | 762.36 |
| | 7239 | 1200 | 7089.80 | 7092.17 | 7092.49 | 9.73 | 1.26 | 2.37 | 494.89 | 7094.64 | 7092.50 | 3.82 | 0.35 | 4.84 | 804.61 |
| | 7238 | 1200 | 7089.60 | 7092.34 | 7092.34 | 8.29 | 1.01 | 2.74 | 486.94 | 7094.64 | 7092.34 | 3.70 | 0.34 | 5.04 | 846.99 |
| | 7237 | 1200 | 7089.40 | 7091.96 | 7092.18 | 9.30 | 1.17 | 2.56 | 495.95 | 7094.65 | 7092.19 | 3.59 | 0.32 | 5.25 | 891.70 |
| | 7236 | 1200 | 7089.20 | 7091.69 | 7092.03 | 9.94 | 1.26 | 2.48 | 506.56 | 7094.65 | 7092.03 | 3.49 | 0.31 | 5.45 | 936.76 |
| | 7235 | 1200 | 7089.00 | 7091.88 | 7091.88 | 8.43 | 1.00 | 2.88 | 498.25 | 7094.65 | 7091.88 | 3.40 | 0.30 | 5.65 | 982.83 |
| | 7234 | 1200 | 7088.80 | 7091.51 | 7091.72 | 9.40 | 1.15 | 2.71 | 506.42 | 7094.66 | 7091.72 | 3.31 | 0.29 | 5.86 | 1029.37 |
| | 7233 | 1200 | 7088.60 | 7091.23 | 7091.57 | 10.03 | 1.24 | 2.63 | 516.38 | 7094.66 | 7091.57 | 3.23 | 0.28 | 6.06 | 1076.65 |
| | 7232 | 1200 | 7088.40 | 7091.41 | 7091.41 | 8.64 | 1.01 | 3.01 | 509.33 | 7094.66 | 7091.42 | 3.16 | 0.27 | 6.26 | 1125.33 |
| | 7231 | 1200 | 7088.20 | 7091.04 | 7091.26 | 9.58 | 1.14 | 2.84 | 517.30 | 7094.66 | 7091.26 | 3.09 | 0.26 | 6.46 | 1173.67 |
| | 7230 | 1200 | 7088.00 | 7090.77 | 7091.11 | 10.20 | 1.23 | 2.76 | 527.06 | 7094.66 | 7091.11 | 3.02 | 0.25 | 6.66 | 1222.33 |
| | 7229 | 1200 | 7087.80 | 7090.92 | 7090.96 | 8.93 | 1.02 | 3.12 | 520.52 | 7094.67 | 7090.96 | 2.96 | 0.24 | 6.87 | 1271.51 |
| | 7228 | 1200 | 7087.60 | 7090.57 | 7090.81 | 9.79 | 1.15 | 2.97 | 528.58 | 7094.67 | 7090.81 | 2.91 | 0.24 | 7.07 | 1320.91 |
| | 7227 | 1200 | 7087.40 | 7090.31 | 7090.65 | 10.35 | 1.22 | 2.91 | 537.54 | 7094.67 | 7090.66 | 2.85 | 0.23 | 7.27 | 1371.09 |
| | 7226 | 1200 | 7087.20 | 7090.48 | 7090.51 | 9.09 | 1.02 | 3.28 | 531.54 | 7094.67 | 7090.51 | 2.81 | 0.22 | 7.47 | 1419.63 |
| Drop Toe | 7225 | 1200 | 7087.00 | 7090.14 | 7090.36 | 9.93 | 1.14 | 3.13 | 539.29 | 7094.67 | 7090.36 | 2.76 | 0.22 | 7.67 | 1469.72 |
| | 7224 | 1200 | 7087.00 | 7090.13 | 7090.36 | 9.94 | 1.14 | 3.13 | 539.41 | 7094.67 | 7090.36 | 2.76 | 0.22 | 7.67 | 1468.88 |
| | 7223 | 1200 | 7087.00 | 7090.13 | 7090.37 | 9.96 | 1.14 | 3.13 | 539.54 | 7094.67 | 7090.36 | 2.76 | 0.22 | 7.67 | 1468.50 |
| | 7222 | 1200 | 7087.00 | 7090.13 | 7090.36 | 9.97 | 1.14 | 3.13 | 539.61 | 7094.67 | 7090.37 | 2.76 | 0.22 | 7.67 | 1468.44 |

Jump begins at Sta. 72+51 which is on the drop face, 26' upstream of the drop toe (Sta. 72+25). Calculate minimum drop basin length starting from drop toe:

Hydraulic Jump Length, Figure 15-4 (Chow)

| | | | |
|---|---|---|---|
| $F_1$ = | 1.38 | $L/Y_2$ = | 3.5 |
| $Y_2$ (ft)= | 7.67 | L (ft)= | 26.85 |
| | | 60%L (ft)= | 16.11 |

| (Minimum required length from toe for protection, minimum Basin Length) = **16.1'** | **use 20'** |
|---|---|

Froude No. at beginning of hydraulic jump

Specific Force (cu ft) at beginning of hydraulic jump (at location where Specific Force (subcritical) > Specific Force (supercritical))

Maximum Channel Depth (ft) at approximate downstream end of hydraulic jump

# Briargate Bridge at Sand Creek
## Hydraulic Jump and Basin Length Calculations

Hydraulic jump locations were calculated using criteria from the Urban Storm Drainage Criteria Manual Vol. II, Hydraulic Structures section 2.3.4
Hydraulic jump lengths were calculated using criteria from the Urban Storm Drainage Criteria Manual Vol. II, Hydraulic Structures section 2.3.5
and from Open Channel Hydraulics by Ven Te Chow
HEC-RAS was used for the frontwater (supercirtical profile analysis) and for the backwater (subcritical profile analysis)

To determine the location of the hydraulic jump, a tailwater elevation has to be established by water surface profile analysis that starts from a downstream control point and works upstream to the drop basin. This backwater analysis is based upon entire cross sections for the downstream waterway. The hydraulic jump, in either the low-flow, trickle channel, or the main drop, will begin to form where the unit specific force of the downstream tailwater is greater than the specific force of the supercritical flow below the drop. Special consideration must be given to submerged hydraulic jumps because it is here that reverse rollers are most common. For submerged jumps, the resulting downstream hydraulics should be evaluated (Cotton 1995).

The determination of the jump location is usually accomplished through the comparison of specific force between supercritical inflow and the downstream subcritical flow (i.e., tailwater) conditions:

$$F = \left(\frac{q^2}{gy}\right) + \left(\frac{y^2}{2}\right) \qquad \text{(HS-6)}$$

in which:

$F$ = specific force ($ft^2$)

$q$ = unit discharge (determined at crest, for low-flow, trickle, and main channel zones) (cfs/ft)

$y$ = depth at analysis point (ft)

$g$ = acceleration of gravity = 32.2 $ft/sec^2$

The depth, $y$, for downstream specific energy determination is the tailwater water surface elevation minus the ground elevation at the point of interest, which is typically the main basin elevation or the trickle channel invert (if the jump is to occur in the basin). The depth, for the upstream specific energy (supercritical flow), is the supercritical flow depth at the point in question.




FIG. 15-4. Length in terms of sequent depth $y_2$ of jumps in horizontal channels. (*Based on data and recommendations of U.S. Bureau of Reclamation* [34].)

Figure 15-4 (Chow), Used to determine the length of the hydraulic jump

## Seepage Analysis (Lane's Weighted Creep Method Calculation)

| Location | $C_w$ | Weep Drain System | $C_w$ | $H_s$ | Drop Height | $L_a$ | $L_f$ | $L_s$ | $L_H$ | Required $L_{v\text{-calc}}$ | $L_{V\text{-Struct}}$ | $L_v$ Difference $L_{v\text{-calc}}$ and $L_{v\text{-Struct}}$ | Additional Calculated Cut off Wall Depth | **Additional Cut off Wall Depth** |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sta. 73+70 | 1.6 | Yes | **1.4** | **4.5 ft** | 4.0 ft | 10.0ft | 30.0ft | 20.0ft | **60.0 ft** | -13.5 ft | **7.0 ft** | 0.0 ft | 0.0 ft | **0 ft** |
| Sta. 72+65 | 1.6 | Yes | **1.4** | **3.3 ft** | 4.0 ft | 10.0ft | 30.0ft | 20.0ft | **60.0 ft** | -15.2 ft | **7.0 ft** | 0.0 ft | 0.0 ft | **0 ft** |

Equations:

$C_w = [(L_H/3)+L_v] / H_s$ (USDCM Eqn 9-5)

$C_w$ = Lane's Weighted Creep Ratio

Table 9-3: Lane's Weighted Creep Recommended Ratios (USDCM)

- $C_w$ = 8.5 Very fine sand or silt
- $C_w$ = 7.0 Fine Sand
- $C_w$ = 6.0 Medium Sand
- $C_w$ = 5.0 Coarse Sand
- $C_w$ = 4.0 Fine Gravel
- $C_w$ = 3.0 Coarse gravel including cobbles or Soft Clay
- $C_w$ = 2.0 Medium Clay
- $C_w$ = 1.8 Hard Clay
- $C_w$ = 1.6 Very Hard Clay or hardpan

Weep Drain System: 10% Reduction is $C_w$ if weep drain system is used

$H_s$ = Head Differential between analysis points -- Taken from HEC-Ras

Drop Height = Difference between Crest and Sill

$L_H$ = Sum of the Horizontal Creep Distances (Less than 45 degrees)

$L_H = L_a + L_f + L_s$

$L_a$ = Approach Length

$L_s$ = Length of stilling basin (Toe to Sill)

$L_f$ = Drop Face Length (Crest to Toe)

$L_v$ = Sum of the Vertical Creep Distances (Steeper than 45 degrees)

$L_{v\text{-Struct}}$ = Vertical creep distances of structure w/o cut off wall

Additional Calculated Cutoff Wall Depth = Half of $L_v$ Difference if Sheet Pile

### 2.3.7 Evaluate Additional Return Period Flow Rates

Evaluate the design flow and then assess additional return-period flow rates, as appropriate. For all flows, the actual downstream tailwater should be greater than the tailwater required to force a hydraulic jump to start near the toe of the drop structure face. When this condition is met for a range of events a stilling basin length of 60% of the hydraulic jump length should be adequate.

### 2.3.8 Rock Sizing for Drop Approach and Downstream of End Sill

Calculate the appropriate rock size for the drop approach and downstream of the end sill. The hydraulic conditions at the approach include the acceleration effects of the upstream drawdown as the water approaches the drop crest. Turbulence generated from the hydraulic jump will impact the area downstream of the end sill. Determine riprap size using the equations provided in the *Open Channels* chapter for channel lining. Because normal depth conditions do not exist upstream and downstream of the drop structure, refer to the HEC-RAS output and use the energy grade line slope (rather than channel slope) to determine the appropriate riprap size.

Riprap at the approach and downstream of the end sill should be a minimum $D_{50}$ of 12-inches, or larger as determined using the channel lining equation in the *Open Channels* chapter. Use either void-filled or soil-filled riprap in these areas.

## 2.4 Seepage Control

### 2.4.1 Introduction

Subgrade erosion caused by seepage and structure failures caused by high seepage pressures or inadequate mass are two failure modes of critical concern.

Seepage analyses can range from hand-drawn flow nets to computerized groundwater flow modeling. Use advanced geotechnical field and laboratory testing techniques confirm permeability values where complicated seepage problems are anticipated. Several flow net analysis programs are currently available that are suitable for this purpose. Full description of flow net analysis is beyond the scope of the Urban Storm Drainage Criteria Manual (USDCM). Referred to Cedergren 1967; USBR 1987; and Taylor 1967 for more information and instruction in the use of flow net analysis techniques. See Section 2.4.3 for Lane's Weighted Creep method, a simplified approach.

### 2.4.2 Weep Drains

Install weep drains in all grade control structures greater than 5 feet in net height or as recommended by the geotechnical engineer. Weep drains assist in reducing the uplift pressure on a structure by providing a location for groundwater to escape safely through a filter. For concept, see Figure 9-10. Weep drains should be placed outside of the low-flow path of the structure and spaced to provide adequate relief of subsurface pressures.

### 2.4.3 Lane's Weighted Creep Method

As a minimum level of analysis and as a first order of estimation, Lane's Weighted Creep (Lane's) Method can be used to identify probable seepage problems, evaluate the need for control measures, and estimate rough uplift forces. It is not as definitive as the flow net analyses mentioned above. Lane's method was proposed by E.W. Lane in 1935. This method was removed from the 1987 revision of *Design of Small Dams* (USBR 1987), possibly indicating greater use of flow net and computer modeling

methods or perhaps for other reasons not documented. Although Lane's method is relatively well founded, it is a guideline, and when marginal conditions or complicated geological conditions exist, use the more sophisticated flow-net analysis.

The essential elements of Lane's method are as follows:

1. The weighted-creep distance through a cross section of a structure is the sum of the vertical creep distances, Lv (along contact surfaces steeper than 45 degrees), plus one-third of the horizontal creep distances, $L_H$ (along contact surfaces less than 45 degrees).

2. The weighted-creep head ratio is defined as:

$$C_W = \frac{\left(\frac{L_H}{3} + L_V\right)}{H_S}$$ Equation 9-5

Where:

$C_W$ = creep ratio

$H_S$ = differential head between analysis points (ft)

3. Reverse filter drains, weep holes, and pipe drains help to reduce seepage problems, and recommended creep head ratios may be reduced as much as 10% if they are used.

4. In the case where two vertical cutoffs are used, then Equation 9-6 should be used along with Equation 9-2 to check the short path between the bottom of the vertical cutoffs.

$$C_{W2} = \frac{\left(L_{V-US} + \quad 2L_{H-C} + L_{V-DS}\right)}{H_S}$$ Equation 9-6

Where:

$C_{W2}$ = creep ratio where two vertical cutoffs are used

$L_{V\text{-}US}$ = vertical distance on the upstream side of the upstream cutoff (ft)

$L_{V\text{-}DS}$ = vertical distance on the downstream side of the downstream cutoff (ft)

$L_{H\text{-}C}$ = horizontal distance between the two vertical cutoffs (ft)

5. If there are seepage lengths upstream or downstream of the cutoffs, they should be treated in the numerator of Equation 9-6 similar to Equation 9-5. Seepage is controlled by increasing the total seepage length such that $C_W$ or $C_{W2}$ is raised to the value listed in Table 9-3. Test soils during design and again during construction.

6. Estimate the upward pressure in design by assuming that the drop in uplift pressure from headwater to tailwater along the contact line of the drop structure is proportional to the weighted-creep distance.

**Table 9-3. Lane's weighted creep: Recommended minimum ratios**

| Material | Ratio |
|---|---|
| Very fine sand or silt | 8.5 |
| Fine sand | 7.0 |
| Medium sand | 6.0 |
| Coarse sand | 5.0 |
| Fine gravel | 4.0 |
| Medium gravel | 3.0 |
| Coarse gravel including cobbles | 3.0 |
| Boulders with some cobbles and gravel | 3.0 |
| Soft clay | 3.0 |
| Medium clay | 2.0 |
| Hard clay | 1.8 |
| Very hard clay or hardpan | 1.6 |

### 2.4.4 Foundation/Seepage Control Systems

As a general rule, groundwater flow cutoffs should not be installed at the downstream ends of drop structures. They can cause greater hydraulic uplift forces than would exist without a downstream cutoff. The design goal is to relieve the hydrostatic pressures along the structure and not to block the groundwater flow and cause higher pressures to build up.

The hydraulic engineer must calculate hydraulic loadings that can occur for a variety of conditions such as dominant low flows, flood flows, design flows and other critical loading scenarios. A geotechnical engineer should combine this information with the on-site soils information to determine foundation requirements. Both engineers should work with a structural engineer to establish final loading diagrams and to determine and size structural components.

The designer needs to be cognizant of field conditions that may affect construction of a drop structure, including site water control and foundation moisture and compaction. A common problem is destabilization of the foundation soils by rapid local dewatering of fine-grained, erosive soils or soils with limited hydraulic conductivity. Since subsurface water control during construction is so critical to the successful installation of a drop structure, the designer needs to develop ways to ensure that the contractor adequately manages subsurface water conditions.

During construction, check design assumptions in the field including the actual subgrade condition with respect to seepage control assumptions be inspected and field verified. Ideally, the engineer who established the design assumptions and calculated the required cutoffs should inspect the cutoff for each drop structure and adjust the cutoff for the actual conditions encountered. For example, if the inspection of a cutoff trench reveals a sandy substrate rather than clay, the designer may choose to extend the cutoff trench, or specify a different cutoff type. Pre-construction soil testing is an advisable precaution to minimize changes and avoid failures.

Proper dewatering in construction will also improve conditions for construction structures. See Fact Sheet SM-08, Temporary Diversion Methods, located in Volume 3 of this manual.

# Briargate Bridge at Sand Creek
## Riprap and Boulder Design Calculations

| Station | Description | Riprap or Boulder | Straight or Curved Section | Flow Velocity | Channel Slope | For Curved Sections | | | Velocity for Calc | Super-elevation dY | Rock Sizing Parameter | Calculated Riprap Type | Calculated Boulder Size | Riprap or Boulder Classification | Note |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | rc | T | $V_a$ | | | | | | | |
| 73+80 | Upstream of Upper Drop Crest | Riprap | Curve | 8.1ft/sec | 1.40% | 500ft | 112ft | 12.3ft/sec | 12.3ft/sec | 0.23ft | 4.5 | M | --- | **M** | 1 |
| 73+10 | Downstream of Upper Drop Sill | Riprap | Curve | 5.5ft/sec | 0.20% | 500ft | 116ft | 8.5ft/sec | 8.5ft/sec | 0.11ft | 2.2 | VL | --- | **M** | 2 |
| 72+75 | Upstream of Lower Drop Crest | Riprap | Curve | 5.9ft/sec | 0.20% | 500ft | 113ft | 9.0ft/sec | 9.0ft/sec | 0.12ft | 2.3 | VL | --- | **M** | 1 |
| 72+05 | Downstream of Lower Drop Sill | Riprap | Straight | 5.9ft/sec | 0.20% | | | | 5.9ft/sec | | 1.5 | VL | --- | **M** | 2 |
| 69+34 | Culvert Protection | Riprap | Straight | 12.1ft/sec | 0.20% | | | | 12.1ft/sec | | 3.2 | VL | --- | **M** | 3 |
| 73+60 | Upper Drop Structure | Boulder | Straight | 10.1ft/sec | 20.0% | | | | 10.1ft/sec | | 5.8 | --- | B30 | **B30** | |
| 72+55 | Lower Drop Structure | Boulder | Straight | 7.6ft/sec | 20.0% | | | | 7.6ft/sec | | 4.3 | --- | B24 | **B24** | |

Equations:

Rock Sizing Parameter = $VS^{0.17}/(G_s\text{-}1)^{0.66}$

V = Mean channel flow velocity for Riprap Sizing

V = Critical Velocity for Grouted Boulder Sizing

S = Longitudinal channel slope

$G_s$ = Specific Gravity of stone (minimum $G_s$ = 2.50)

$G_s$ = 2.55 (UDFCD Recommended) (2'x3' is about 1 ton, able to be moved by skid steer)

$G_s$ = 2.55

| Rock Sizing Parameter | | Riprap Type | D50 |
|---|---|---|---|
| 0.00 | 3.29 | VL | 6 inches |
| 3.30 | 3.99 | L | 9 inches |
| 4.00 | 4.59 | M | 12 inches |
| 4.60 | 5.59 | H | 18 inches |
| 5.60 | 6.40 | VH | 24 inches |

Equations taken from *UDFCD USDCM (Eqn MD-13 & HS-9)* and *City of Colorado Springs & El Paso County Drainage Criteria Manual*

| Rock Sizing Parameter | | Grouted Boulder Classification | Grouted Boulder Min. Dimension |
|---|---|---|---|
| 0.00 | 4.49 | B18 | 18 inches |
| 4.50 | 4.99 | B18 | 18 inches |
| 5.00 | 5.59 | B24 | 24 inches |
| 5.60 | 6.39 | B30 | 30 inches |
| 6.40 | 6.99 | B36 | 36 inches |
| 7.00 | 7.49 | B42 | 42 inches |
| 7.50 | 8.00 | B48 | 48 inches |

$v_a = (-0.147\ r_c/T + 2.176)V$ (Eqn UDFCD MD-10)

$V_a$ = Adjusted channel velocity for riprap sizing along outside of channel bends

$r_c$ = channel centerline radius

T = Top width of water during the major design flood

Superelevation (dY) = $V^2T/2gr_c$ (Eqn UDFCD MD-9)

V = Mean channel flow velocity

T = Top Width of the channel under design flow conditions

g = Gravitational constant = 32.2 ft/sec$^2$

$r_c$ = channel centerline radius

Notes:
1. Type M Riprap is minimum size recommended for areas immediately upstream of drop structures (water surface drawdown area).
2. Type M Riprap is minimum size recommended for areas immediately downstream of drop structures (hydraulic jump area).
3. Type M Riprap is minimum size recommended for channel lining through and downstream of culvert.

## 8.1 Riprap Sizing

Procedures for sizing rock to be used in soil riprap, void-filled riprap, and riprap over bedding are the same.

### 8.1.1 Mild Slope Conditions

When subcritical flow conditions occur and/or slopes are mild (less than 2 percent), UDFCD recommends the following equation (Hughes, et al, 1983):

$$d_{50} \geq \left[ \frac{VS^{0.17}}{4.5(G_s - 1)^{0.66}} \right]^2 \qquad \text{Equation 8-11}$$

Where:

V = mean channel velocity (ft/sec)

S = longitudinal channel slope (ft/ft)

$d_{50}$ = mean rock size (ft)

Gs = specific gravity of stone (minimum = 2.50, typically 2.5 to 2.7), Note: In this equation (Gs -1) considers the buoyancy of the water, in that the specific gravity of water is subtracted from the specific gravity of the rock.

Note that Equation 8-11 is applicable for sizing riprap for channel lining with a longitudinal slope of no more than 2%. This equation is not intended for use in sizing riprap for steep slopes (typically in excess of 2 percent), rundowns, or protection downstream of culverts. Information on rundowns is provided in Section 7.0 of the *Hydraulic Structures* chapter of the USDCM, and protection downstream of culverts is discussed in the *Culverts and Bridges* chapter. For channel slopes greater than 2% use one of the methods presented in 8.1.2.

Rock size does not need to be increased for steeper channel side slopes, provided the side slopes are no steeper than 2.5H:1V (UDFCD 1982). Channel side slopes steeper than 2.5H:1V are not recommended because of stability, safety, and maintenance considerations. See Figure 8-34 for riprap placement specifications. At the upstream and downstream termination of a riprap lining, the thickness should be increased 50% for at least 3 feet to prevent undercutting.

### 8.1.2 Steep Slope Conditions

Steep slope rock sizing equations are used for applications where the slope is greater than 2 percent and/or flows are in the supercritical flow regime. The following rock sizing equations may be referred to for riprap design analysis on steep slopes:

- CSU Equation, *Development of Riprap Design Criteria by Riprap Testing in Flumes: Phase II* (prepared by S.R. Abt, et al, Colorado State University, 1988). This method was developed for steep slopes from 2 to 20 percent.

- USDA- Agricultural Research Service Equations, *Design of Rock Chutes* (by K.M. Robinson, et al, USDA- ARS, 1998 Transactions of ASAE) and *An Excel Program to Design Rock Chutes for Grade*

# DESIGN OF ROADSIDE CHANNELS WITH FLEXIBLE LININGS

Hydraulic Engineering Circular No. 15

Prepared By

Simons, Li & Associates, Inc.
3555 Stanford Road
P.O. Box 1816
Fort Collins, Colorado 80522

For

U.S. Department of Transportation
Federal Highway Administration

October 25, 1985

Table 4.1. Permissible Shear Stresses for Lining Materials.

| Lining Category | Lining Type | Permissible Unit Shear Stress (lb/ft2) |
|---|---|---|
| Temporary | Woven Paper Net | 0.15 |
| | Jute Net | 0.45 |
| | Fiberglass Roving* | 0.75 |
| | Straw and Erosion Net | 1.45 ← OB slope |
| | Curled Wood Mat (TRM) | 1.55 ← bench |
| | Nylon Mat | 2.00 |
| Vegetative | Class A | 3.70 |
| | Class B | 2.10 ← OB slope |
| | Class C | 1.00 |
| | Class D | 0.60 |
| | Class E | 0.35 |
| Gravel Riprap | 1-inch | 0.40 |
| | 2-inch | 0.80 |
| Rock Riprap | 6-inch | 2.50 |
| | 12-inch | 5.00 |

* single and double applications

TABLE 3.1.--Classification of vegetal covers as to degree of retardance (6)

Note: Covers classified have been tested in experimental channels. Covers were green and generally uniform.

| Retardance | Cover | Condition |
|---|---|---|
| A | Weeping lovegrass ..... | Excellent stand, tall, (average 30") |
| | Yellow bluestem Ischaemum .. | Excellent stand, tall, (average 36") |
| B | Kudzu ..... | Very dense growth, uncut |
| | Bermudagrass ..... | Good stand, tall (average 12") |
| | Native grass mixture (little bluestem, blue grama, and other long and short midwest grasses) ..... | Good stand, unmowed |
| | Weeping lovegrass ..... | Good stand, tall, (average 24") |
| | Lespedeza sericea ..... | Good stand, not woody, tall (average 19") |
| | Alfalfa ..... | Good stand, uncut, (average 11") |
| | Weeping lovegrass ..... | Good stand, mowed, (average 13") |
| | Kudzu ..... | Dense growth, uncut |
| | Blue grama ..... | Good stand, uncut,(average 13") |
| C | Crabgrass ..... | Fair stand, uncut (10 to 48") |
| | Bermudagrass ..... | Good stand, mowed (average 6") |
| | Common lespedeza ..... | Good stand, uncut (average 11") |
| | Grass-legume mixture--summer (orchard grass, redtop, Italian ryegrass, and common lespedeza) ..... | Good stand, uncut (6 to 8 inches) |
| | Centipedegrass ..... | Very dense cover (average 6 inches) |
| | Kentucky bluegrass ..... | Good stand, headed (6 to 12 inches) |
| D | Bermudagrass ..... | Good stand, cut to 2.5-inch height |
| | Common lespedeza ..... | Excellent stand, uncut (average 4.5") |
| | Buffalograss ..... | Good stand, uncut (3 to 6 inches) |
| | Grass-legume mixture--fall, spring (Orchardgrass, redtop, Italian ryegrass, and common lespedeza) ..... | Good stand, uncut (4 to 5 inches) |
| | Lespedeza sericea ..... | After cutting to 2-inch height. Very good stand before cutting. |
| E | Bermudagrass ..... | Good stand, cut to 1.5 inches height |
| | Bermudagrass ..... | Burned stubble. |

# Appendix D: HECRAS Hydraulic Modelling


7636
7411
7380
7360
7311
7255
7275
7205
7039
Seal Creek
6929
6889
Alignment - (6760
6379


2021 Sand Creek at Briargate Pkwy Plan: Proposed Profiles 3/7/2022
Sand Creek Alignment - (1)
Legend
WS 500yr
WS 100yr
WS 50yr
WS DP-69
WS 10yr
Ground
Elevation (ft)
7120
7110
7100
7090
7080
0
200
400
600
800
1000
1200
1400
Main Channel Distance (ft)

2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

FIS Section DI




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Approach




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Approach



2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Crest




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Toe




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Basin




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Sill



2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Approach




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Approach




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Crest




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Toe



2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Basin




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Drop Sill




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Upstream Bridge Face




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022

Briargate Parkway




2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022
Downstream Bridge Face
.035
.04
Legend
WS 500yr
WS 100yr
Ground
Ineff
Bank Sta
Elevation (ft)
Station (ft)
2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022
.035
.027
.035
Legend
WS 500yr
WS 100yr
Ground
Bank Sta
Elevation (ft)
Station (ft)
2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022
.035
.027
.035
Legend
WS 500yr
WS 100yr
Ground
Bank Sta
Elevation (ft)
Station (ft)
2021 Sand Creek at Briargate Pkwy Plan: Prop Design Subcritical 6/27/2022
.04
.027
.04
Legend
WS 500yr
WS 100yr
Ground
Bank Sta
Elevation (ft)
Station (ft)

HEC-RAS Plan: PropDesignSubcritical River: Sand Creek Reach: Alignment - (1)

| Reach | River Sta | Profile | Q Total | Min Ch El | W.S. Elev | Vel Chnl | Froude # Chl | Shear Chan |
|---|---|---|---|---|---|---|---|---|
| | | | (cfs) | (ft) | (ft) | (ft/s) | | (lb/sq ft) |
| Alignment - (1) | 7636 | Low Flow | 260.00 | 7100.00 | 7101.31 | 5.39 | 1.00 | 0.62 |
| Alignment - (1) | 7636 | 10yr | 1200.00 | 7100.00 | 7102.80 | 7.92 | 1.01 | 1.04 |
| Alignment - (1) | 7636 | 100yr | 2600.00 | 7100.00 | 7104.13 | 9.82 | 1.01 | 1.39 |
| Alignment - (1) | 7636 | 500yr | 3800.00 | 7100.00 | 7105.03 | 10.95 | 0.98 | 1.58 |
| Alignment - (1) | 7636 | DP-69 | 1870.00 | 7100.00 | 7103.50 | 8.96 | 1.01 | 1.23 |
| | | | | | | | | |
| Alignment - (1) | 7411 | Low Flow | 260.00 | 7096.90 | 7098.19 | 4.58 | 0.89 | 0.46 |
| Alignment - (1) | 7411 | 10yr | 1200.00 | 7096.90 | 7099.45 | 7.90 | 1.00 | 1.03 |
| Alignment - (1) | 7411 | 100yr | 2600.00 | 7096.90 | 7100.77 | 9.95 | 0.98 | 1.38 |
| Alignment - (1) | 7411 | 500yr | 3800.00 | 7096.90 | 7101.66 | 11.26 | 0.98 | 1.64 |
| Alignment - (1) | 7411 | DP-69 | 1870.00 | 7096.90 | 7100.15 | 8.96 | 0.98 | 1.21 |
| | | | | | | | | |
| Alignment - (1) | 7380 | Low Flow | 260.00 | 7097.00 | 7098.11 | 2.90 | 0.51 | 0.49 |
| Alignment - (1) | 7380 | 10yr | 1200.00 | 7097.00 | 7099.30 | 5.88 | 0.73 | 1.57 |
| Alignment - (1) | 7380 | 100yr | 2600.00 | 7097.00 | 7100.36 | 8.19 | 0.86 | 2.72 |
| Alignment - (1) | 7380 | 500yr | 3800.00 | 7097.00 | 7100.88 | 10.07 | 0.99 | 3.94 |
| Alignment - (1) | 7380 | DP-69 | 1870.00 | 7097.00 | 7099.86 | 7.12 | 0.80 | 2.16 |
| | | | | | | | | |
| Alignment - (1) | 7370 | Low Flow | 260.00 | 7097.00 | 7098.03 | 2.84 | 0.52 | 0.48 |
| Alignment - (1) | 7370 | 10yr | 1200.00 | 7097.00 | 7099.21 | 5.56 | 0.70 | 1.42 |
| Alignment - (1) | 7370 | 100yr | 2600.00 | 7097.00 | 7100.29 | 7.62 | 0.80 | 2.36 |
| Alignment - (1) | 7370 | 500yr | 3800.00 | 7097.00 | 7100.80 | 9.38 | 0.92 | 3.42 |
| Alignment - (1) | 7370 | DP-69 | 1870.00 | 7097.00 | 7099.78 | 6.67 | 0.76 | 1.90 |
| | | | | | | | | |
| Alignment - (1) | 7360 | Low Flow | 260.00 | 7097.00 | 7097.68 | 4.28 | 1.00 | 1.27 |
| Alignment - (1) | 7360 | 10yr | 1200.00 | 7097.00 | 7098.68 | 7.00 | 1.01 | 2.45 |
| Alignment - (1) | 7360 | 100yr | 2600.00 | 7097.00 | 7099.71 | 8.83 | 1.01 | 3.35 |
| Alignment - (1) | 7360 | 500yr | 3800.00 | 7097.00 | 7100.43 | 9.86 | 1.01 | 3.88 |
| Alignment - (1) | 7360 | DP-69 | 1870.00 | 7097.00 | 7099.21 | 8.00 | 1.01 | 2.93 |
| | | | | | | | | |
| Alignment - (1) | 7330 | Low Flow | 260.00 | 7091.00 | 7094.53 | 1.29 | 0.15 | 0.07 |
| Alignment - (1) | 7330 | 10yr | 1200.00 | 7091.00 | 7096.37 | 3.22 | 0.29 | 0.38 |
| Alignment - (1) | 7330 | 100yr | 2600.00 | 7091.00 | 7098.34 | 4.43 | 0.35 | 0.66 |
| Alignment - (1) | 7330 | 500yr | 3800.00 | 7091.00 | 7100.36 | 4.54 | 0.32 | 0.64 |
| Alignment - (1) | 7330 | DP-69 | 1870.00 | 7091.00 | 7097.22 | 4.05 | 0.34 | 0.58 |
| | | | | | | | | |
| Alignment - (1) | 7311 | Low Flow | 260.00 | 7091.00 | 7094.52 | 1.27 | 0.15 | 0.07 |
| Alignment - (1) | 7311 | 10yr | 1200.00 | 7091.00 | 7096.34 | 3.20 | 0.29 | 0.38 |
| Alignment - (1) | 7311 | 100yr | 2600.00 | 7091.00 | 7098.30 | 4.40 | 0.35 | 0.65 |
| Alignment - (1) | 7311 | 500yr | 3800.00 | 7091.00 | 7100.33 | 4.49 | 0.32 | 0.63 |
| Alignment - (1) | 7311 | DP-69 | 1870.00 | 7091.00 | 7097.18 | 4.03 | 0.34 | 0.58 |
| | | | | | | | | |
| Alignment - (1) | 7310 | Low Flow | 260.00 | 7093.00 | 7094.45 | 2.29 | 0.35 | 0.27 |
| Alignment - (1) | 7310 | 10yr | 1200.00 | 7093.00 | 7096.15 | 4.41 | 0.47 | 0.80 |
| Alignment - (1) | 7310 | 100yr | 2600.00 | 7093.00 | 7098.11 | 5.37 | 0.46 | 1.03 |
| Alignment - (1) | 7310 | 500yr | 3800.00 | 7093.00 | 7100.22 | 5.09 | 0.38 | 0.84 |
| Alignment - (1) | 7310 | DP-69 | 1870.00 | 7093.00 | 7096.94 | 5.28 | 0.51 | 1.07 |
| | | | | | | | | |
| Alignment - (1) | 7275 | Low Flow | 260.00 | 7093.00 | 7094.26 | 2.70 | 0.45 | 0.40 |
| Alignment - (1) | 7275 | 10yr | 1200.00 | 7093.00 | 7095.83 | 5.04 | 0.57 | 1.08 |
| Alignment - (1) | 7275 | 100yr | 2600.00 | 7093.00 | 7097.87 | 5.75 | 0.51 | 1.19 |
| Alignment - (1) | 7275 | 500yr | 3800.00 | 7093.00 | 7100.09 | 5.28 | 0.38 | 0.89 |
| Alignment - (1) | 7275 | DP-69 | 1870.00 | 7093.00 | 7096.55 | 6.03 | 0.61 | 1.44 |
| | | | | | | | | |

HEC-RAS Plan: PropDesignSubcritical River: Sand Creek Reach: Alignment - (1) (Continued)

| Reach | River Sta | Profile | Q Total | Min Ch El | W.S. Elev | Vel Chnl | Froude # Chl | Shear Chan |
|---|---|---|---|---|---|---|---|---|
| | | | (cfs) | (ft) | (ft) | (ft/s) | | (lb/sq ft) |
| Alignment - (1) | 7265 | Low Flow | 260.00 | 7093.00 | 7094.17 | 2.93 | 0.50 | 0.48 |
| Alignment - (1) | 7265 | 10yr | 1200.00 | 7093.00 | 7095.69 | 5.34 | 0.61 | 1.23 |
| Alignment - (1) | 7265 | 100yr | 2600.00 | 7093.00 | 7097.80 | 5.85 | 0.52 | 1.24 |
| Alignment - (1) | 7265 | 500yr | 3800.00 | 7093.00 | 7100.06 | 5.31 | 0.39 | 0.90 |
| Alignment - (1) | 7265 | DP-69 | 1870.00 | 7093.00 | 7096.38 | 6.40 | 0.66 | 1.65 |
| | | | | | | | | |
| Alignment - (1) | 7255 | Low Flow | 260.00 | 7093.00 | 7093.76 | 4.71 | 1.00 | 1.44 |
| Alignment - (1) | 7255 | 10yr | 1200.00 | 7093.00 | 7094.97 | 7.58 | 1.01 | 2.73 |
| Alignment - (1) | 7255 | 100yr | 2600.00 | 7093.00 | 7097.72 | 5.97 | 0.53 | 1.30 |
| Alignment - (1) | 7255 | 500yr | 3800.00 | 7093.00 | 7100.03 | 5.34 | 0.39 | 0.91 |
| Alignment - (1) | 7255 | DP-69 | 1870.00 | 7093.00 | 7096.05 | 7.21 | 0.78 | 2.16 |
| | | | | | | | | |
| Alignment - (1) | 7225 | Low Flow | 260.00 | 7087.00 | 7091.49 | 1.32 | 0.13 | 0.07 |
| Alignment - (1) | 7225 | 10yr | 1200.00 | 7087.00 | 7094.67 | 2.76 | 0.22 | 0.26 |
| Alignment - (1) | 7225 | 100yr | 2600.00 | 7087.00 | 7097.85 | 3.45 | 0.24 | 0.37 |
| Alignment - (1) | 7225 | 500yr | 3800.00 | 7087.00 | 7100.11 | 3.71 | 0.23 | 0.39 |
| Alignment - (1) | 7225 | DP-69 | 1870.00 | 7087.00 | 7096.30 | 3.18 | 0.23 | 0.32 |
| | | | | | | | | |
| Alignment - (1) | 7205 | Low Flow | 260.00 | 7087.00 | 7091.48 | 1.32 | 0.13 | 0.07 |
| Alignment - (1) | 7205 | 10yr | 1200.00 | 7087.00 | 7094.66 | 2.77 | 0.22 | 0.26 |
| Alignment - (1) | 7205 | 100yr | 2600.00 | 7087.00 | 7097.83 | 3.46 | 0.24 | 0.37 |
| Alignment - (1) | 7205 | 500yr | 3800.00 | 7087.00 | 7100.09 | 3.74 | 0.22 | 0.39 |
| Alignment - (1) | 7205 | DP-69 | 1870.00 | 7087.00 | 7096.28 | 3.19 | 0.23 | 0.33 |
| | | | | | | | | |
| Alignment - (1) | 7204 | Low Flow | 260.00 | 7089.00 | 7091.43 | 2.07 | 0.25 | 0.19 |
| Alignment - (1) | 7204 | 10yr | 1200.00 | 7089.00 | 7094.59 | 3.34 | 0.29 | 0.40 |
| Alignment - (1) | 7204 | 100yr | 2600.00 | 7089.00 | 7097.78 | 3.84 | 0.28 | 0.47 |
| Alignment - (1) | 7204 | 500yr | 3800.00 | 7089.00 | 7100.05 | 4.01 | 0.25 | 0.47 |
| Alignment - (1) | 7204 | DP-69 | 1870.00 | 7089.00 | 7096.22 | 3.65 | 0.28 | 0.45 |
| | | | | | | | | |
| Alignment - (1) | 7175 | Low Flow | 260.00 | 7089.00 | 7091.28 | 2.91 | 0.38 | 0.40 |
| Alignment - (1) | 7175 | 10yr | 1200.00 | 7089.00 | 7094.33 | 4.59 | 0.38 | 0.74 |
| Alignment - (1) | 7175 | 100yr | 2600.00 | 7089.00 | 7097.31 | 5.94 | 0.38 | 1.04 |
| Alignment - (1) | 7175 | 500yr | 3800.00 | 7089.00 | 7099.40 | 6.77 | 0.39 | 1.25 |
| Alignment - (1) | 7175 | DP-69 | 1870.00 | 7089.00 | 7095.86 | 5.31 | 0.38 | 0.89 |
| | | | | | | | | |
| Alignment - (1) | 7039 | | Culvert | | | | | |
| | | | | | | | | |
| Alignment - (1) | 6929 | Low Flow | 260.00 | 7088.70 | 7090.30 | 5.01 | 0.76 | 1.03 |
| Alignment - (1) | 6929 | 10yr | 1200.00 | 7088.70 | 7092.02 | 9.38 | 0.99 | 2.85 |
| Alignment - (1) | 6929 | 100yr | 2600.00 | 7088.70 | 7093.88 | 12.13 | 0.99 | 4.01 |
| Alignment - (1) | 6929 | 500yr | 3800.00 | 7088.70 | 7095.23 | 13.73 | 0.99 | 4.72 |
| Alignment - (1) | 6929 | DP-69 | 1870.00 | 7088.70 | 7092.97 | 10.87 | 0.99 | 3.46 |
| | | | | | | | | |
| Alignment - (1) | 6889 | Low Flow | 260.00 | 7088.70 | 7090.28 | 2.80 | 0.44 | 0.15 |
| Alignment - (1) | 6889 | 10yr | 1200.00 | 7088.70 | 7091.45 | 6.63 | 0.75 | 0.67 |
| Alignment - (1) | 6889 | 100yr | 2600.00 | 7088.70 | 7092.41 | 10.12 | 0.97 | 1.40 |
| Alignment - (1) | 6889 | 500yr | 3800.00 | 7088.70 | 7093.33 | 11.38 | 0.97 | 1.64 |
| Alignment - (1) | 6889 | DP-69 | 1870.00 | 7088.70 | 7091.87 | 8.74 | 0.91 | 1.11 |
| | | | | | | | | |
| Alignment - (1) | 6760 | Low Flow | 260.00 | 7088.70 | 7089.57 | 4.48 | 1.01 | 0.49 |
| Alignment - (1) | 6760 | 10yr | 1200.00 | 7088.70 | 7090.58 | 6.86 | 1.01 | 0.86 |
| Alignment - (1) | 6760 | 100yr | 2600.00 | 7088.70 | 7091.57 | 8.74 | 0.99 | 1.17 |
| Alignment - (1) | 6760 | 500yr | 3800.00 | 7088.70 | 7092.26 | 9.85 | 0.98 | 1.37 |

HEC-RAS Plan: PropDesignSubcritical River: Sand Creek Reach: Alignment - (1) (Continued)

| Reach | River Sta | Profile | Q Total | Min Ch El | W.S. Elev | Vel Chnl | Froude # Chl | Shear Chan |
|---|---|---|---|---|---|---|---|---|
| | | | (cfs) | (ft) | (ft) | (ft/s) | | (lb/sq ft) |
| Alignment - (1) | 6760 | DP-69 | 1870.00 | 7088.70 | 7091.09 | 7.88 | 1.00 | 1.03 |
| | | | | | | | | |
| Alignment - (1) | 6379 | Low Flow | 260.00 | 7080.17 | 7082.78 | 5.12 | 1.00 | 0.58 |
| Alignment - (1) | 6379 | 10yr | 1200.00 | 7080.17 | 7084.21 | 6.13 | 1.03 | 0.75 |
| Alignment - (1) | 6379 | 100yr | 2600.00 | 7080.17 | 7085.10 | 7.21 | 0.92 | 0.86 |
| Alignment - (1) | 6379 | 500yr | 3800.00 | 7080.17 | 7085.52 | 8.63 | 1.00 | 1.16 |
| Alignment - (1) | 6379 | DP-69 | 1870.00 | 7080.17 | 7085.10 | 5.18 | 0.66 | 0.45 |

## Appendix E: Contech Bridge Design Analysis

*Finite Element Analysis Report by CANDE (Culvert Analysis and Design)*

# Sterling Ranch Colorado Springs

## Merlin# 635632

### Colorado Springs, Colorado

March 2, 2022

The purpose of this report is to present the study of how a BridgeCor structure is expected to behave with the site conditions including soils information. A CANDE analysis was performed assuming the soil conditions based on provided information and some assumptions, which are summarized on the following pages. This report will examine: combined thrust and moment, seam strength, wall area, global buckling, and deflection, and unfactored footing reactions. The analysis was in accordance with the AASHTO LRFD Bridge Design Specification.

Structure:

Maximum Span: 43'-0"
Bottom Span: 41'-11"
Rise: 26'-4"
Design cover: 7'-0"
Gage: 5

Summary:

a. Load Factors: 1.75 for Live Load and 1.50 for Dead Load
b. Modified Load Factors: 1.05 for Live Load (Multiple Presence Factor)
c. For this structure, HL-93 design truck (32,000 pound axles spaced at 14 feet) and HL-93 tandem (25,000 pound axles spaced at 4 feet) loading were used as live load. The HL-93 design truck governed. As required by AASHTO, the combination of loads was the factored Dead Load plus the factored Live Load, which is determined as the controlling load case.
d. Resistance Factors: Plastic Hinge Resistance Factor ($\varphi_h$) = 0.90, Wall Area and Buckling Resistance Factor ($\varphi_w$) = 0.70, Seam Strength Resistance Factor ($\varphi_{SS}$) = 0.67.
e. Properties: Area of the Wall Cross-Section = 0.3003 in.$^2$/in., Moment of Inertia = 1.1436 in.$^4$/in., Section Modulus = 0.3741 in.$^3$/in., Plastic Section Modulus = 0.5224 in.$^3$/in.
f. Profile of the BridgeCor deep corrugated plate (See next page for profile and data table). Profile is 15" Pitch and 5.5" Depth.
g. Density of the backfill soil on top of the structure = 120 pcf (pounds per cubic foot)
h. Density of the soil outside of the excavation of the arches = 120 pcf (pounds per cubic foot)
i. Calculations of the Live loads, dead loads, etc.: See the following summary report.

COLORADO LICENSED
DARRELL J. SANDERS
55263
PROFESSIONAL ENGINEER
3/7/22




## Table 2.14

Sectional properties of 15 x 5 1/2 in. (Annular)

| Specified Thickness | Uncoated Thickness $T$ | Area of Section $A$ | Tangent Length $TL$ | Tangent Angle $\Delta$ | Moment of Inertia $I$ | Section Modulus $S$ | Radius of Gyration $r$ | Developed Width Factor |
|---|---|---|---|---|---|---|---|---|
| (in.) | (in.) | (in.$^2$/ft) | (in.) | (Degrees) | (in.$^4$/in) | (in.$^3$/ft) | (in.) | |
| 0.140 | 0.1345 | 2.260 | 4.361 | 49.75 | 0.7146 | 2.8406 | 1.9481 | 1.400 |
| 0.170 | 0.1644 | 2.762 | 4.323 | 49.89 | 0.8746 | 3.4602 | 1.9494 | 1.400 |
| 0.188 | 0.1838 | 3.088 | 4.299 | 49.99 | 0.9786 | 3.8599 | 1.9502 | 1.400 |
| 0.218 | 0.2145 | 3.604 | 4.259 | 50.13 | 1.1436 | 4.4888 | 1.9515 | 1.400 |
| 0.249 | 0.2451 | 4.118 | 4.220 | 50.28 | 1.3084 | 5.1114 | 1.9527 | 1.400 |
| 0.280 | 0.2758 | 4.633 | 4.179 | 50.43 | 1.4722 | 5.7317 | 1.9540 | 1.400 |
| 0.193 | 0.1875 | 3.150 | 4.293 | 50.00 | 0.9985 | 3.9359 | 1.9503 | 1.400 |
| 0.255 | 0.2500 | 4.200 | 4.213 | 50.31 | 1.3349 | 5.2107 | 1.9529 | 1.400 |
| 0.318 | 0.3125 | 5.250 | 4.131 | 50.62 | 1.6730 | 6.4678 | 1.9555 | 1.400 |
| 0.380 | 0.3750 | 6.300 | 4.047 | 50.94 | 2.0128 | 7.7076 | 1.9580 | 1.400 |

Notes: 1. Per foot of projection about the neutral axis.
To obtain $A$ or $S$ per *inch* of width, divide the above values by 12.
2. Developed width factor measures the increase in profile length due to corrugating.
Dimensions are subject to manufacturing tolerances.

CANDE Generated Cross Section



Single Radius Arch BridgeCor: 58S 41'-11" Bottom Span x 26'-4" Rise (Inside Dimensions) Gage: 5

Height of cover above crown: 7'-0"

| | |
|---|---|
| Red mesh: | Assumed: Isotropic-linear elastic, Young's modulus = 3,000 psi, Poisson's ratio = 0.30, density = 1 pcf (Density assumed to be 1 pcf to represent existing, consolidated soil – modeled to approximate no displacement) |
| Green mesh: | Embankment fill (assumed): Duncan/Selig SM90 , Density = 120 pcf |
| Yellow mesh: | Select backfill (assumed): Backfill width = 8'-0", Duncan/Selig SW95, Density = 120 pcf |
| Orange mesh: | Reinforced concrete footing (assumed): Isotropic-linear elastic, Young's modulus = 3,500,000 psi, Poisson's ratio = 0.18, Density = 150 pcf |
| Green boundary point: | Displacement restricted in the vertical direction |
| Blue boundary point: | Displacement restricted in the horizontal direction |
| Red boundary point: | Force above crown of arch representing 32,000 pound, HL-93 Design Truck live load |

*Design Criterion Summary:

- Wall Thrust Resistance Ratio = 32.77 / 111.0 = 0.295 < 1.00 OK
- Global Buckling Resistance Ratio = 2.73103 / 10.96 = 0.249 < 1.00 OK
- Seam Thrust Resistance Ratio = 32.77 / 85.09 = 0.385 < 1.00 OK
- Combined Thrust & Moment Ratio = 0.732 < 1.00 OK

*See sections below for more on calculations

CANDE Unfactored Thrust Reactions




Base Angle: -12.95 degrees

Unfactored Vertical Footing Reaction: $R_V$ = cos (-12.95) x 2925.56 x 12 = 34,214 lbs/ft

Unfactored Horizontal Footing Reaction: $R_H$ = sin (-12.95) x 2925.56 x 12 = -7,867 lbs/ft

Notes:

Each node represents a location along perimeter of cross-section
Unfactored reactions are for each leg

AASHTO 12.8.9.5 (Combined Thrust & Moment Resistance) requires deep-corrugated metal plate structures to be analyzed using a finite element analysis. The results from the analysis are then used to compute a combined thrust and moment ratio (Combined T&M Ratio):

Combined T&M Ratio = $(T_f/R_t)^2 + M_u/M_n \leq 1.00$

(Factored thrust / Factored Thrust Resistance)$^2$ + (Factored moment / Factored Moment Resistance) ≤ 1.00

The factored thrust resistance is the minimum yield point ($F_y$ = 44,000 psi) multiplied by the area of wall cross-section (0.3003 in$^2$/in for 5 gage) multiplied by the plastic hinge resistance factor (0.90). The factored moment resistance is the plastic moment capacity (23070 lbs-in/in for 5 gage) multiplied by the plastic hinge resistance factor. Refer to the NCSPA Design manual (Table 2.14, pg. 37) for cross-section properties of BridgeCor.

The following graphs show the bending moments and thrust forces along the cross-section of the BridgeCor structure. The x-axis correlates to the distance along the perimeter of the cross-section of the Single Radius Arch BridgeCor structure in inches.

Combined Thrust & Moment Ratio = (1763.55/(44,000 x 0.3003 x 0.90))$^2$ + (14744.5/(23070x0.90)) = 0.732 < 1.00 OK






CANDE Controlling Node Output

| NODE | X-COORD<br>Y-COORD | X-DISP.<br>Y-DISP. | N-PRES.<br>S-PRES. | MOMENT<br>THRUST | MAX-STRESS<br>HOOP-STRESS | SHEAR<br>S-STRESS |
|---|---|---|---|---|---|---|
| 20 | 0.00<br>319.17 | -0.141E-01<br>0.805E+00 | -0.375E+01<br>-0.498E-01 | -0.147E+05<br>-0.176E+04 | -0.440E+05<br>-0.587E+04 | -0.338E+01<br>-0.113E+02 |
| 39 | 254.12<br>0.00 | 0.326E+00<br>-0.246E+01 | -0.777E+01<br>-0.130E+01 | -0.161E-10<br>-0.277E+04 | -0.923E+04<br>-0.923E+04 | -0.143E+03<br>-0.476E+03 |

AASHTO Section 12.8.9.6 (Global Buckling) requires that the factored thrust in the culvert wall under the final installed condition shall not exceed the nominal resistance to general buckling capacity of the culvert, computed as:

$R_{b,}$ nominal axial force in culvert wall to cause general buckling $= 1.2\Phi_b C_n (E_m I_p)^{1/3} (\Phi_s M_s K_b)^{2/3} R_h$

$\Phi_b$ , resistance factor for general buckling = 0.70
$C_n$ , scalar calibration factor to account for some nonlinear effects = 0.55
$E_m$ , modulus of elasticity of pipe wall material = 29000 ksi
$I_p$ , moment of inertia of stiffened culvert wall per unit length= 1.144 $in^4/in$
$\Phi_s$ , resistance factor for soil = 0.9
γ, soil density = 120 pcf
$R_{sp}$, rise above springline= 258 inches
$P_{sp} = 0.5\gamma R_{sp}$ = 8.96 psi
$M_s$ , constrained modulus of embedment computed = 2.92 ksi
based on the free field vertical stress at a depth
halfway between the top and springline of the
structure (Table 12.12.3.5-1)
v, Poisson's ratio of soil = 0.30
$K_b = (1—2v)/(1—v^2)$ = 0.44
$R_h$, correction factor for backfill geometry = 11.4/(11+S/H) = 0.67
S, culvert span = 503 inches
H, depth of fill over top of culvert = 84 inches

$R_b = 1.2 \times 0.70 \times 0.55 \times (29000 \times 1.144)^{1/3} (0.9 \times 2.92 \times 0.44)^{2/3} (0.67) =$ 10.96 kips/in

$R_b$ = 10.96 kips/in > Max Factored Buckling Thrust = 2.73103 kips/in

Global Buckling Resistance Ratio = 2.73103 / 10.96 = 0.249 < 1.00 OK

**Table 12.12.3.5-1—$M_s$ Based on Soil Type and Compaction Condition**

| $P_{sp}$ Stress Level (psi) | Sn-100 (ksi) | Sn-95 (ksi) | Sn-90 (ksi) | Sn-85 (ksi) |
|---|---|---|---|---|
| 1.0 | 2.350 | 2.000 | 1.275 | 0.470 |
| 5.0 | 3.450 | 2.600 | 1.500 | 0.520 |
| 10.0 | 4.200 | 3.000 | 1.625 | 0.570 |
| 20.0 | 5.500 | 3.450 | 1.800 | 0.650 |
| 40.0 | 7.500 | 4.250 | 2.100 | 0.825 |
| 60.0 | 9.300 | 5.000 | 2.500 | 1.000 |
| $P_{sp}$ Stress Level (psi) | | Si-95 (ksi) | Si-90 (ksi) | Si-85 (ksi) |

AASHTO Section 12.7.2.3 (Wall Resistance) requires the wall resistance to be greater than the factored thrust.

The wall resistance is defined as:
$R_w = \Phi_w F_y A_w$
$A_w$ = wall area ($in^2/ft$) = 3.604 $in^2/ft$
$F_y$ = yield strength of metal = 44 ksi

$R_w = \Phi_w F_y A_w$ = 0.70 x 44 x 3.604 = 111.0 kips/ ft > Max Factored Material Thrust = 32.77 kips/ft

Wall Thrust Resistance Ratio = 32.77 / 111.0 = 0.295 < 1.00 OK

AASHTO Section 12.7.2.5 (Seam Strength) requires the factored seam strength to be greater than the factored thrust.

The factored seam strength is defined as:

$R_s = \Phi_{SS} SS$

$\Phi_{SS}$, Seam Strength = 0.67 (AASHTO Table 12.5.5-1)

SS = Seam Strength = 127 kips/ft (from Table 7.4B on page 376 of the NCSPA Design Manual).

$R_s$ = 0.67 x 127 = 85.09 kips/ft > Max Factored Seam Thrust = 32.77 kips/ft

Seam Thrust Resistance Ratio = 32.77 / 85.09 = 0.385 < 1.00 OK

CANDE Output Summary for controlling load step

```
ASSESSMENT SUMMARY STEEL-GROUP  1, LOAD-STEP 19

  LRFD STRENGTH-LIMIT RATIOS AT STEP 19, FOR STEEL GROUP #  1

   DESIGN-CRITERION           CONTROL     FACTORED     FACTORED        RATIO
                                 NODE       DEMAND     CAPACITY        VALUE

   MATERIAL THRUST (psi)           39        9233.       30800.        0.300

   BUCKLING THRUST (psi)           39        9233.       46744.        0.198

   SEAM THRUST (psi)               39        9233.       23052.        0.401

   PLASTIC-PENETRATE (%)           20         1.68        90.00        0.019

   COMBINED T&M Ratio              20        0.735        1.000        0.735
```

Displacement Y-Direction(in): Load steps 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19,20,21,22,23,



CANDE OUTPUT FOR CONTROLLING LOAD STEP 19

STRUCTURAL RESPONSES OF STEEL-GROUP 1, LOAD STEP 19
UNITS INCH-LB SYSTEM: (FORCE = LB/IN, MOMENT = IN-LB/IN, STRESS = PSI)

| NODE | X-COORD / Y-COORD | X-DISP. / Y-DISP. | N-PRES. / S-PRES. | MOMENT / THRUST | MAX-STRESS / HOOP-STRESS | SHEAR / S-STRESS |
|---|---|---|---|---|---|---|
| 1 | -254.12 | -0.320E+00 | -0.799E+01 | 0.371E-10 | -0.922E+04 | 0.139E+03 |
| | 0.00 | -0.246E+01 | 0.146E+01 | -0.277E+04 | -0.922E+04 | 0.462E+03 |
| 2 | -258.50 | -0.165E+00 | -0.818E+01 | -0.276E+04 | -0.165E+05 | 0.824E+02 |
| | 24.26 | -0.244E+01 | 0.200E+01 | -0.272E+04 | -0.907E+04 | 0.274E+03 |
| 3 | -260.57 | 0.329E-01 | -0.837E+01 | -0.412E+04 | -0.199E+05 | 0.311E+02 |
| | 48.82 | -0.243E+01 | 0.254E+01 | -0.267E+04 | -0.890E+04 | 0.104E+03 |
| 4 | -260.31 | 0.296E+00 | -0.796E+01 | -0.430E+04 | -0.202E+05 | -0.172E+02 |
| | 73.47 | -0.245E+01 | 0.240E+01 | -0.261E+04 | -0.869E+04 | -0.572E+02 |
| 5 | -257.73 | 0.625E+00 | -0.765E+01 | -0.321E+04 | -0.171E+05 | -0.681E+02 |
| | 97.98 | -0.249E+01 | 0.228E+01 | -0.255E+04 | -0.848E+04 | -0.227E+03 |
| 6 | -252.84 | 0.998E+00 | -0.780E+01 | -0.831E+03 | -0.105E+05 | -0.115E+03 |
| | 122.14 | -0.257E+01 | 0.227E+01 | -0.248E+04 | -0.825E+04 | -0.382E+03 |
| 7 | -245.70 | 0.137E+01 | -0.865E+01 | 0.259E+04 | -0.149E+05 | -0.142E+03 |
| | 145.73 | -0.270E+01 | 0.245E+01 | -0.241E+04 | -0.801E+04 | -0.474E+03 |
| 8 | -236.35 | 0.169E+01 | -0.102E+02 | 0.634E+04 | -0.247E+05 | -0.133E+03 |
| | 168.54 | -0.284E+01 | 0.281E+01 | -0.233E+04 | -0.775E+04 | -0.443E+03 |
| 9 | -224.90 | 0.190E+01 | -0.105E+02 | 0.929E+04 | -0.323E+05 | -0.935E+02 |
| | 190.36 | -0.296E+01 | 0.292E+01 | -0.224E+04 | -0.747E+04 | -0.311E+03 |
| 10 | -211.44 | 0.198E+01 | -0.111E+02 | 0.111E+05 | -0.368E+05 | -0.344E+02 |
| | 211.01 | -0.301E+01 | 0.320E+01 | -0.216E+04 | -0.719E+04 | -0.115E+03 |
| 11 | -196.08 | 0.191E+01 | -0.874E+01 | 0.111E+05 | -0.366E+05 | 0.107E+02 |
| | 230.29 | -0.296E+01 | 0.254E+01 | -0.209E+04 | -0.695E+04 | 0.357E+02 |
| 12 | -178.98 | 0.171E+01 | -0.925E+01 | 0.106E+05 | -0.350E+05 | 0.398E+02 |
| | 248.04 | -0.278E+01 | 0.279E+01 | -0.202E+04 | -0.673E+04 | 0.133E+03 |
| 13 | -160.27 | 0.142E+01 | -0.103E+02 | 0.912E+04 | -0.309E+05 | 0.950E+02 |
| | 264.09 | -0.245E+01 | 0.324E+01 | -0.195E+04 | -0.650E+04 | 0.316E+03 |

| | | | | | | |
|---|---|---|---|---|---|---|
| 14 | -140.14 | 0.106E+01 | -0.904E+01 | 0.585E+04 | -0.219E+05 | 0.154E+03 |
| | 278.31 | -0.198E+01 | 0.291E+01 | -0.189E+04 | -0.628E+04 | 0.513E+03 |
| 15 | -118.75 | 0.712E+00 | -0.746E+01 | 0.140E+04 | -0.984E+04 | 0.183E+03 |
| | 290.56 | -0.139E+01 | 0.246E+01 | -0.184E+04 | -0.611E+04 | 0.610E+03 |
| 16 | -96.30 | 0.407E+00 | -0.628E+01 | -0.338E+04 | -0.150E+05 | 0.182E+03 |
| | 300.73 | -0.752E+00 | 0.159E+01 | -0.180E+04 | -0.600E+04 | 0.607E+03 |
| 17 | -72.98 | 0.183E+00 | -0.542E+01 | -0.783E+04 | -0.269E+05 | 0.159E+03 |
| | 308.74 | -0.140E+00 | 0.892E+00 | -0.179E+04 | -0.595E+04 | 0.530E+03 |
| 18 | -49.02 | 0.501E-01 | -0.489E+01 | -0.115E+05 | -0.365E+05 | 0.120E+03 |
| | 314.51 | 0.366E+00 | 0.785E+00 | -0.178E+04 | -0.592E+04 | 0.398E+03 |
| 19 | -24.62 | -0.419E-02 | -0.410E+01 | -0.139E+05 | -0.431E+05 | 0.648E+02 |
| | 318.00 | 0.697E+00 | 0.688E+00 | -0.177E+04 | -0.589E+04 | 0.216E+03 |
| 20 | 0.00 | -0.141E-01 | -0.375E+01 | -0.147E+05 | -0.440E+05 | -0.338E+01 |
| | 319.17 | 0.805E+00 | -0.498E-01 | -0.176E+04 | -0.587E+04 | -0.113E+02 |
| 21 | 24.62 | -0.253E-01 | -0.413E+01 | -0.137E+05 | -0.426E+05 | -0.713E+02 |
| | 318.00 | 0.673E+00 | -0.696E+00 | -0.177E+04 | -0.589E+04 | -0.237E+03 |
| 22 | 49.02 | -0.830E-01 | -0.490E+01 | -0.111E+05 | -0.357E+05 | -0.126E+03 |
| | 314.51 | 0.320E+00 | -0.782E+00 | -0.178E+04 | -0.592E+04 | -0.418E+03 |
| 23 | 72.98 | -0.220E+00 | -0.548E+01 | -0.735E+04 | -0.256E+05 | -0.164E+03 |
| | 308.74 | -0.203E+00 | -0.921E+00 | -0.179E+04 | -0.595E+04 | -0.547E+03 |
| 24 | 96.30 | -0.447E+00 | -0.642E+01 | -0.279E+04 | -0.135E+05 | -0.185E+03 |
| | 300.73 | -0.823E+00 | -0.170E+01 | -0.180E+04 | -0.600E+04 | -0.617E+03 |
| 25 | 118.75 | -0.752E+00 | -0.765E+01 | 0.201E+04 | -0.115E+05 | -0.182E+03 |
| | 290.56 | -0.146E+01 | -0.252E+01 | -0.184E+04 | -0.612E+04 | -0.606E+03 |
| 26 | 140.14 | -0.110E+01 | -0.919E+01 | 0.637E+04 | -0.233E+05 | -0.149E+03 |
| | 278.31 | -0.204E+01 | -0.295E+01 | -0.189E+04 | -0.630E+04 | -0.496E+03 |
| 27 | 160.27 | -0.144E+01 | -0.107E+02 | 0.947E+04 | -0.318E+05 | -0.841E+02 |
| | 264.09 | -0.250E+01 | -0.334E+01 | -0.196E+04 | -0.652E+04 | -0.280E+03 |
| 28 | 178.98 | -0.172E+01 | -0.928E+01 | 0.106E+05 | -0.350E+05 | -0.250E+02 |
| | 248.04 | -0.281E+01 | -0.278E+01 | -0.203E+04 | -0.676E+04 | -0.831E+02 |
| 29 | 196.08 | -0.190E+01 | -0.844E+01 | 0.107E+05 | -0.356E+05 | -0.104E+00 |
| | 230.29 | -0.297E+01 | -0.244E+01 | -0.210E+04 | -0.698E+04 | -0.347E+00 |

| | | | | | | |
|---|---|---|---|---|---|---|
| 30 | 211.44 | -0.195E+01 | -0.107E+02 | 0.105E+05 | -0.353E+05 | 0.356E+02 |
| | 211.01 | -0.301E+01 | -0.308E+01 | -0.217E+04 | -0.722E+04 | 0.119E+03 |
| 31 | 224.90 | -0.187E+01 | -0.104E+02 | 0.884E+04 | -0.311E+05 | 0.880E+02 |
| | 190.36 | -0.295E+01 | -0.290E+01 | -0.225E+04 | -0.749E+04 | 0.293E+03 |
| 32 | 236.35 | -0.165E+01 | -0.102E+02 | 0.606E+04 | -0.240E+05 | 0.126E+03 |
| | 168.54 | -0.283E+01 | -0.283E+01 | -0.233E+04 | -0.776E+04 | 0.421E+03 |
| 33 | 245.70 | -0.134E+01 | -0.876E+01 | 0.246E+04 | -0.146E+05 | 0.137E+03 |
| | 145.73 | -0.269E+01 | -0.249E+01 | -0.241E+04 | -0.803E+04 | 0.457E+03 |
| 34 | 252.84 | -0.967E+00 | -0.790E+01 | -0.861E+03 | -0.106E+05 | 0.112E+03 |
| | 122.14 | -0.257E+01 | -0.230E+01 | -0.248E+04 | -0.827E+04 | 0.372E+03 |
| 35 | 257.73 | -0.599E+00 | -0.777E+01 | -0.319E+04 | -0.170E+05 | 0.673E+02 |
| | 97.98 | -0.248E+01 | -0.231E+01 | -0.255E+04 | -0.850E+04 | 0.224E+03 |
| 36 | 260.31 | -0.275E+00 | -0.806E+01 | -0.429E+04 | -0.202E+05 | 0.183E+02 |
| | 73.47 | -0.244E+01 | -0.243E+01 | -0.262E+04 | -0.871E+04 | 0.611E+02 |
| 37 | 260.57 | -0.157E-01 | -0.836E+01 | -0.415E+04 | -0.200E+05 | -0.296E+02 |
| | 48.82 | -0.243E+01 | -0.254E+01 | -0.268E+04 | -0.892E+04 | -0.987E+02 |
| 38 | 258.50 | 0.177E+00 | -0.807E+01 | -0.282E+04 | -0.166E+05 | -0.831E+02 |
| | 24.26 | -0.244E+01 | -0.192E+01 | -0.273E+04 | -0.909E+04 | -0.277E+03 |
| 39 | 254.12 | 0.326E+00 | -0.777E+01 | -0.161E-10 | -0.923E+04 | -0.143E+03 |
| | 0.00 | -0.246E+01 | -0.130E+01 | -0.277E+04 | -0.923E+04 | -0.476E+03 |

Finite Element Analysis Report by CANDE (Culvert Analysis and Design)

# Sterling Ranch Colorado Springs
# Merlin# 635632
## Colorado Springs, Colorado
March 2, 2022

The purpose of this report is to present the study of how a BridgeCor structure is expected to behave with the site conditions including soils information. A CANDE analysis was performed assuming the soil conditions based on provided information and some assumptions, which are summarized on the following pages. This report will examine: combined thrust and moment, seam strength, wall area, global buckling, and deflection, and unfactored footing reactions. The analysis was in accordance with the AASHTO LRFD Bridge Design Specification.

Structure:

Maximum Span: 43'-0"
Bottom Span: 41'-11"
Rise: 26'-4"
Design cover: 5'-0"
Gage: 5

Summary:

a. Load Factors: 1.75 for Live Load and 1.50 for Dead Load
b. Modified Load Factors: 1.05 for Live Load (Multiple Presence Factor)
c. For this structure, HL-93 design truck (32,000 pound axles spaced at 14 feet) and HL-93 tandem (25,000 pound axles spaced at 4 feet) loading were used as live load. The HL-93 design truck governed. As required by AASHTO, the combination of loads was the factored Dead Load plus the factored Live Load, which is determined as the controlling load case.
d. Resistance Factors: Plastic Hinge Resistance Factor ($\varphi_h$) = 0.90, Wall Area and Buckling Resistance Factor ($\varphi_w$) = 0.70, Seam Strength Resistance Factor ($\varphi_{SS}$) = 0.67.
e. Properties: Area of the Wall Cross-Section = 0.3003 in.$^2$/in., Moment of Inertia = 1.1436 in.$^4$/in., Section Modulus = 0.3741 in.$^3$/in., Plastic Section Modulus = 0.5224 in.$^3$/in.
f. Profile of the BridgeCor deep corrugated plate (See next page for profile and data table). Profile is 15" Pitch and 5.5" Depth.
g. Density of the backfill soil on top of the structure = 120 pcf (pounds per cubic foot)
h. Density of the soil outside of the excavation of the arches = 120 pcf (pounds per cubic foot)
i. Calculations of the Live loads, dead loads, etc.: See the following summary report.




## Table 2.14

Sectional properties of 15 x 5 1/2 in. (Annular)

| Specified Thickness | Uncoated Thickness $T$ | Area of Section $A$ | Tangent Length $TL$ | Tangent Angle $\Delta$ | Moment of Inertia $I$ | Section Modulus $S$ | Radius of Gyration $r$ | Developed Width Factor |
|---|---|---|---|---|---|---|---|---|
| (in.) | (in.) | (in.$^2$/ft) | (in.) | (Degrees) | (in.$^4$/in) | (in.$^3$/ft) | (in.) | |
| 0.140 | 0.1345 | 2.260 | 4.361 | 49.75 | 0.7146 | 2.8406 | 1.9481 | 1.400 |
| 0.170 | 0.1644 | 2.762 | 4.323 | 49.89 | 0.8746 | 3.4602 | 1.9494 | 1.400 |
| 0.188 | 0.1838 | 3.088 | 4.299 | 49.99 | 0.9786 | 3.8599 | 1.9502 | 1.400 |
| 0.218 | 0.2145 | 3.604 | 4.259 | 50.13 | 1.1436 | 4.4888 | 1.9515 | 1.400 |
| 0.249 | 0.2451 | 4.118 | 4.220 | 50.28 | 1.3084 | 5.1114 | 1.9527 | 1.400 |
| 0.280 | 0.2758 | 4.633 | 4.179 | 50.43 | 1.4722 | 5.7317 | 1.9540 | 1.400 |
| 0.193 | 0.1875 | 3.150 | 4.293 | 50.00 | 0.9985 | 3.9359 | 1.9503 | 1.400 |
| 0.255 | 0.2500 | 4.200 | 4.213 | 50.31 | 1.3349 | 5.2107 | 1.9529 | 1.400 |
| 0.318 | 0.3125 | 5.250 | 4.131 | 50.62 | 1.6730 | 6.4678 | 1.9555 | 1.400 |
| 0.380 | 0.3750 | 6.300 | 4.047 | 50.94 | 2.0128 | 7.7076 | 1.9580 | 1.400 |

Notes: 1. Per foot of projection about the neutral axis.
To obtain $A$ or $S$ per *inch* of width, divide the above values by 12.
2. Developed width factor measures the increase in profile length due to corrugating.
Dimensions are subject to manufacturing tolerances.

CANDE Generated Cross Section



Single Radius Arch BridgeCor: 58S 41'-11" Bottom Span x 26'-4" Rise (Inside Dimensions) Gage: 5

Height of cover above crown: 5'-0"

| | |
|---|---|
| Red mesh: | Assumed: Isotropic-linear elastic, Young's modulus = 3,000 psi, Poisson's ratio = 0.30, density = 1 pcf (Density assumed to be 1 pcf to represent existing, consolidated soil – modeled to approximate no displacement) |
| Green mesh: | Embankment fill (assumed): Duncan/Selig SM90 , Density = 120 pcf |
| Yellow mesh: | Select backfill (assumed): Backfill width = 8'-0", Duncan/Selig SW95, Density = 120 pcf |
| Orange mesh: | Reinforced concrete footing (assumed): Isotropic-linear elastic, Young's modulus = 3,500,000 psi, Poisson's ratio = 0.18, Density = 150 pcf |
| Green boundary point: | Displacement restricted in the vertical direction |
| Blue boundary point: | Displacement restricted in the horizontal direction |
| Red boundary point: | Force above crown of arch representing 32,000 pound, HL-93 Design Truck live load |

*Design Criterion Summary:

- Wall Thrust Resistance Ratio = 32.79 / 111.0 = 0.295 < 1.00 OK
- Global Buckling Resistance Ratio = 2.73216 / 9.60 = 0.284 < 1.00 OK
- Seam Thrust Resistance Ratio = 32.79 / 85.09 = 0.385 < 1.00 OK
- Combined Thrust & Moment Ratio = 0.727 < 1.00 OK

*See sections below for more on calculations

CANDE Unfactored Thrust Reactions




2457.62lb/in at Node 1

Base Angle: -12.95 degrees

Unfactored Vertical Footing Reaction: $R_V$ = cos (-12.95) x 2457.62 x 12 = 28,741 lbs/ft

Unfactored Horizontal Footing Reaction: $R_H$ = sin (-12.95) x 2457.62 x 12 = -6,609 lbs/ft

Notes:

Each node represents a location along perimeter of cross-section
Unfactored reactions are for each leg

AASHTO 12.8.9.5 (Combined Thrust & Moment Resistance) requires deep-corrugated metal plate structures to be analyzed using a finite element analysis. The results from the analysis are then used to compute a combined thrust and moment ratio (Combined T&M Ratio):

Combined T&M Ratio = $(T_f/R_t)^2 + M_u/M_n \leq 1.00$

(Factored thrust / Factored Thrust Resistance)$^2$ + (Factored moment / Factored Moment Resistance) ≤ 1.00

The factored thrust resistance is the minimum yield point ($F_y$ = 44,000 psi) multiplied by the area of wall cross-section (0.3003 in$^2$/in for 5 gage) multiplied by the plastic hinge resistance factor (0.90). The factored moment resistance is the plastic moment capacity (23070 lbs-in/in for 5 gage) multiplied by the plastic hinge resistance factor. Refer to the NCSPA Design manual (Table 2.14, pg. 37) for cross-section properties of BridgeCor.

The following graphs show the bending moments and thrust forces along the cross-section of the BridgeCor structure. The x-axis correlates to the distance along the perimeter of the cross-section of the Two Radius Arch BridgeCor structure in inches.

Combined Thrust & Moment Ratio = (1759.78/(44,000 x 0.3003 x 0.90))$^2$ + (14634.7/(23070x0.90)) = 0.727 < 1.00 OK






CANDE Controlling Node Output

| NODE | X-COORD<br>Y-COORD | X-DISP.<br>Y-DISP. | N-PRES.<br>S-PRES. | MOMENT<br>THRUST | MAX-STRESS<br>HOOP-STRESS | SHEAR<br>S-STRESS |
|---|---|---|---|---|---|---|
| 20 | 0.00<br>319.17 | -0.140E-01<br>0.742E+00 | -0.374E+01<br>-0.477E-01 | -0.146E+05<br>-0.176E+04 | -0.440E+05<br>-0.586E+04 | -0.338E+01<br>-0.113E+02 |
| 39 | 254.12<br>0.00 | 0.355E+00<br>-0.247E+01 | -0.781E+01<br>-0.127E+01 | -0.290E-10<br>-0.277E+04 | -0.923E+04<br>-0.923E+04 | -0.144E+03<br>-0.479E+03 |

AASHTO Section 12.8.9.6 (Global Buckling) requires that the factored thrust in the culvert wall under the final installed condition shall not exceed the nominal resistance to general buckling capacity of the culvert, computed as:

$R_{b,}$ nominal axial force in culvert wall to cause general buckling $= 1.2\Phi_b C_n (E_m I_p)^{1/3} (\Phi_s M_s K_b)^{2/3} R_h$

$\Phi_b$ , resistance factor for general buckling = 0.70
$C_n$ , scalar calibration factor to account for some nonlinear effects = 0.55
$E_m$ , modulus of elasticity of pipe wall material = 29000 ksi
$I_p$ , moment of inertia of stiffened culvert wall per unit length= 1.144 $in^4/in$
$\Phi_s$ , resistance factor for soil = 0.9
γ, soil density = 120 pcf
$R_{sp}$, rise above springline= 258 inches
$P_{sp} = 0.5\gamma R_{sp}$ = 8.96 psi
$M_s$ , constrained modulus of embedment computed = 2.92 ksi
based on the free field vertical stress at a depth
halfway between the top and springline of the
structure (Table 12.12.3.5-1)
v, Poisson's ratio of soil = 0.30
$K_b = (1—2v)/(1—v^2)$ = 0.44
$R_h$, correction factor for backfill geometry = 11.4/(11+S/H) = 0.59
S, culvert span = 503 inches
H, depth of fill over top of culvert = 60 inches

$R_b = 1.2 \times 0.70 \times 0.55 \times (29000 \times 1.144)^{1/3} (0.9 \times 2.92 \times 0.44)^{2/3} (0.59) =$ 9.60 kips/in

$R_b$ = 9.60 kips/in > Max Factored Buckling Thrust = 2.73216 kips/in

Global Buckling Resistance Ratio = 2.73216 / 9.60 = 0.284 < 1.00 OK

**Table 12.12.3.5-1—$M_s$ Based on Soil Type and Compaction Condition**

| $P_{sp}$ Stress Level (psi) | Sn-100 (ksi) | Sn-95 (ksi) | Sn-90 (ksi) | Sn-85 (ksi) |
|---|---|---|---|---|
| 1.0 | 2.350 | 2.000 | 1.275 | 0.470 |
| 5.0 | 3.450 | 2.600 | 1.500 | 0.520 |
| 10.0 | 4.200 | 3.000 | 1.625 | 0.570 |
| 20.0 | 5.500 | 3.450 | 1.800 | 0.650 |
| 40.0 | 7.500 | 4.250 | 2.100 | 0.825 |
| 60.0 | 9.300 | 5.000 | 2.500 | 1.000 |
| $P_{sp}$ Stress Level (psi) | | Si-95 (ksi) | Si-90 (ksi) | Si-85 (ksi) |

AASHTO Section 12.7.2.3 (Wall Resistance) requires the wall resistance to be greater than the factored thrust.

The wall resistance is defined as:
$R_w = \Phi_w F_y A_w$
$A_w$ = wall area ($in^2/ft$) = 3.604 $in^2/ft$
$F_y$ = yield strength of metal = 44 ksi

$R_w = \Phi_w F_y A_w$ = 0.70 x 44 x 3.604 = 111.0 kips/ ft > Max Factored Material Thrust = 32.79 kips/ft

Wall Thrust Resistance Ratio = 32.79 / 111.0 = 0.295 < 1.00 OK

AASHTO Section 12.7.2.5 (Seam Strength) requires the factored seam strength to be greater than the factored thrust.

The factored seam strength is defined as:

$R_s = \Phi_{SS} SS$

$\Phi_{SS}$, Seam Strength = 0.67 (AASHTO Table 12.5.5-1)

SS = Seam Strength = 127 kips/ft (from Table 7.4B on page 376 of the NCSPA Design Manual).

$R_s$ = 0.67 x 127 = 85.09 kips/ft > Max Factored Seam Thrust = 32.79 kips/ft

Seam Thrust Resistance Ratio = 32.79 / 85.09 = 0.385 < 1.00 OK

CANDE Output Summary for controlling load step

```
ASSESSMENT SUMMARY STEEL-GROUP  1, LOAD-STEP 19

  LRFD STRENGTH-LIMIT RATIOS AT STEP 19, FOR STEEL GROUP #  1

   DESIGN-CRITERION           CONTROL     FACTORED     FACTORED        RATIO
                                 NODE       DEMAND     CAPACITY        VALUE

   MATERIAL THRUST (psi)           39        9235.       30800.        0.300

   BUCKLING THRUST (psi)           39        9235.       40838.        0.226

   SEAM THRUST (psi)               39        9235.       23052.        0.401

   PLASTIC-PENETRATE (%)           20         1.28        90.00        0.014

   COMBINED T&M Ratio              20        0.729        1.000        0.729
```

Displacement Y-Direction(in): Load steps 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19,20,21,22,



CANDE OUTPUT FOR CONTROLLING LOAD STEP 19

STRUCTURAL RESPONSES OF STEEL-GROUP 1, LOAD STEP 19
UNITS INCH-LB SYSTEM: (FORCE = LB/IN, MOMENT = IN-LB/IN, STRESS = PSI)

| NODE | X-COORD<br>Y-COORD | X-DISP.<br>Y-DISP. | N-PRES.<br>S-PRES. | MOMENT<br>THRUST | MAX-STRESS<br>HOOP-STRESS | SHEAR<br>S-STRESS |
|---|---|---|---|---|---|---|
| 1 | -254.12<br>0.00 | -0.350E+00<br>-0.248E+01 | -0.803E+01<br>0.142E+01 | 0.986E-10<br>-0.277E+04 | -0.922E+04<br>-0.922E+04 | 0.140E+03<br>0.466E+03 |
| 2 | -258.50<br>24.26 | -0.198E+00<br>-0.246E+01 | -0.819E+01<br>0.198E+01 | -0.279E+04<br>-0.273E+04 | -0.165E+05<br>-0.908E+04 | 0.835E+02<br>0.278E+03 |
| 3 | -260.57<br>48.82 | -0.263E-02<br>-0.245E+01 | -0.834E+01<br>0.254E+01 | -0.418E+04<br>-0.267E+04 | -0.201E+05<br>-0.890E+04 | 0.319E+02<br>0.106E+03 |
| 4 | -260.31<br>73.47 | 0.259E+00<br>-0.246E+01 | -0.797E+01<br>0.240E+01 | -0.437E+04<br>-0.261E+04 | -0.204E+05<br>-0.869E+04 | -0.169E+02<br>-0.563E+02 |
| 5 | -257.73<br>97.98 | 0.588E+00<br>-0.250E+01 | -0.764E+01<br>0.228E+01 | -0.329E+04<br>-0.255E+04 | -0.173E+05<br>-0.848E+04 | -0.681E+02<br>-0.227E+03 |
| 6 | -252.84<br>122.14 | 0.961E+00<br>-0.259E+01 | -0.780E+01<br>0.227E+01 | -0.899E+03<br>-0.248E+04 | -0.107E+05<br>-0.826E+04 | -0.115E+03<br>-0.383E+03 |
| 7 | -245.70<br>145.73 | 0.134E+01<br>-0.271E+01 | -0.866E+01<br>0.245E+01 | 0.253E+04<br>-0.241E+04 | -0.148E+05<br>-0.802E+04 | -0.143E+03<br>-0.475E+03 |
| 8 | -236.35<br>168.54 | 0.166E+01<br>-0.285E+01 | -0.102E+02<br>0.282E+01 | 0.629E+04<br>-0.233E+04 | -0.246E+05<br>-0.775E+04 | -0.133E+03<br>-0.444E+03 |
| 9 | -224.90<br>190.36 | 0.187E+01<br>-0.298E+01 | -0.105E+02<br>0.293E+01 | 0.925E+04<br>-0.224E+04 | -0.322E+05<br>-0.747E+04 | -0.935E+02<br>-0.311E+03 |
| 10 | -211.44<br>211.01 | 0.195E+01<br>-0.303E+01 | -0.111E+02<br>0.320E+01 | 0.110E+05<br>-0.216E+04 | -0.367E+05<br>-0.720E+04 | -0.345E+02<br>-0.115E+03 |
| 11 | -196.08<br>230.29 | 0.189E+01<br>-0.299E+01 | -0.875E+01<br>0.254E+01 | 0.110E+05<br>-0.209E+04 | -0.365E+05<br>-0.695E+04 | 0.106E+02<br>0.354E+02 |
| 12 | -178.98<br>248.04 | 0.169E+01<br>-0.281E+01 | -0.925E+01<br>0.278E+01 | 0.106E+05<br>-0.202E+04 | -0.349E+05<br>-0.674E+04 | 0.396E+02<br>0.132E+03 |
| 13 | -160.27<br>264.09 | 0.140E+01<br>-0.249E+01 | -0.103E+02<br>0.323E+01 | 0.909E+04<br>-0.195E+04 | -0.308E+05<br>-0.650E+04 | 0.944E+02<br>0.314E+03 |
| 14 | -140.14<br>278.31 | 0.105E+01<br>-0.202E+01 | -0.903E+01<br>0.291E+01 | 0.584E+04<br>-0.189E+04 | -0.219E+05<br>-0.629E+04 | 0.153E+03<br>0.510E+03 |

| | | | | | | |
|---|---|---|---|---|---|---|
| 15 | -118.75 | 0.706E+00 | -0.746E+01 | 0.142E+04 | -0.991E+04 | 0.182E+03 |
| | 290.56 | -0.143E+01 | 0.247E+01 | -0.184E+04 | -0.612E+04 | 0.606E+03 |
| 16 | -96.30 | 0.403E+00 | -0.628E+01 | -0.333E+04 | -0.149E+05 | 0.181E+03 |
| | 300.73 | -0.802E+00 | 0.167E+01 | -0.180E+04 | -0.600E+04 | 0.604E+03 |
| 17 | -72.98 | 0.181E+00 | -0.543E+01 | -0.775E+04 | -0.267E+05 | 0.158E+03 |
| | 308.74 | -0.195E+00 | 0.937E+00 | -0.179E+04 | -0.594E+04 | 0.527E+03 |
| 18 | -49.02 | 0.496E-01 | -0.489E+01 | -0.114E+05 | -0.363E+05 | 0.119E+03 |
| | 314.51 | 0.307E+00 | 0.816E+00 | -0.178E+04 | -0.591E+04 | 0.396E+03 |
| 19 | -24.62 | -0.420E-02 | -0.410E+01 | -0.138E+05 | -0.428E+05 | 0.646E+02 |
| | 318.00 | 0.635E+00 | 0.729E+00 | -0.177E+04 | -0.588E+04 | 0.215E+03 |
| 20 | 0.00 | -0.140E-01 | -0.374E+01 | -0.146E+05 | -0.440E+05 | -0.338E+01 |
| | 319.17 | 0.742E+00 | -0.477E-01 | -0.176E+04 | -0.586E+04 | -0.113E+02 |
| 21 | 24.62 | -0.252E-01 | -0.413E+01 | -0.136E+05 | -0.423E+05 | -0.710E+02 |
| | 318.00 | 0.610E+00 | -0.736E+00 | -0.177E+04 | -0.588E+04 | -0.237E+03 |
| 22 | 49.02 | -0.824E-01 | -0.490E+01 | -0.110E+05 | -0.354E+05 | -0.125E+03 |
| | 314.51 | 0.260E+00 | -0.813E+00 | -0.178E+04 | -0.591E+04 | -0.417E+03 |
| 23 | 72.98 | -0.218E+00 | -0.549E+01 | -0.727E+04 | -0.254E+05 | -0.163E+03 |
| | 308.74 | -0.258E+00 | -0.967E+00 | -0.178E+04 | -0.594E+04 | -0.544E+03 |
| 24 | 96.30 | -0.443E+00 | -0.643E+01 | -0.274E+04 | -0.133E+05 | -0.184E+03 |
| | 300.73 | -0.873E+00 | -0.177E+01 | -0.180E+04 | -0.600E+04 | -0.613E+03 |
| 25 | 118.75 | -0.745E+00 | -0.765E+01 | 0.203E+04 | -0.116E+05 | -0.181E+03 |
| | 290.56 | -0.150E+01 | -0.252E+01 | -0.184E+04 | -0.613E+04 | -0.602E+03 |
| 26 | 140.14 | -0.109E+01 | -0.919E+01 | 0.637E+04 | -0.233E+05 | -0.148E+03 |
| | 278.31 | -0.208E+01 | -0.295E+01 | -0.189E+04 | -0.630E+04 | -0.493E+03 |
| 27 | 160.27 | -0.142E+01 | -0.107E+02 | 0.945E+04 | -0.318E+05 | -0.835E+02 |
| | 264.09 | -0.253E+01 | -0.333E+01 | -0.196E+04 | -0.653E+04 | -0.278E+03 |
| 28 | 178.98 | -0.170E+01 | -0.928E+01 | 0.105E+05 | -0.349E+05 | -0.248E+02 |
| | 248.04 | -0.284E+01 | -0.278E+01 | -0.203E+04 | -0.677E+04 | -0.825E+02 |
| 29 | 196.08 | -0.187E+01 | -0.845E+01 | 0.107E+05 | -0.355E+05 | 0.106E-01 |
| | 230.29 | -0.300E+01 | -0.244E+01 | -0.210E+04 | -0.698E+04 | 0.352E-01 |

| | | | | | | |
|---|---|---|---|---|---|---|
| 30 | 211.44 | -0.193E+01 | -0.107E+02 | 0.105E+05 | -0.352E+05 | 0.356E+02 |
| | 211.01 | -0.303E+01 | -0.308E+01 | -0.217E+04 | -0.722E+04 | 0.119E+03 |
| 31 | 224.90 | -0.184E+01 | -0.104E+02 | 0.879E+04 | -0.310E+05 | 0.879E+02 |
| | 190.36 | -0.297E+01 | -0.290E+01 | -0.225E+04 | -0.749E+04 | 0.293E+03 |
| 32 | 236.35 | -0.162E+01 | -0.102E+02 | 0.601E+04 | -0.238E+05 | 0.127E+03 |
| | 168.54 | -0.285E+01 | -0.284E+01 | -0.233E+04 | -0.777E+04 | 0.422E+03 |
| 33 | 245.70 | -0.130E+01 | -0.877E+01 | 0.240E+04 | -0.145E+05 | 0.137E+03 |
| | 145.73 | -0.271E+01 | -0.249E+01 | -0.241E+04 | -0.803E+04 | 0.458E+03 |
| 34 | 252.84 | -0.929E+00 | -0.790E+01 | -0.929E+03 | -0.108E+05 | 0.112E+03 |
| | 122.14 | -0.258E+01 | -0.231E+01 | -0.249E+04 | -0.828E+04 | 0.373E+03 |
| 35 | 257.73 | -0.561E+00 | -0.777E+01 | -0.327E+04 | -0.172E+05 | 0.674E+02 |
| | 97.98 | -0.250E+01 | -0.231E+01 | -0.255E+04 | -0.850E+04 | 0.224E+03 |
| 36 | 260.31 | -0.237E+00 | -0.805E+01 | -0.436E+04 | -0.204E+05 | 0.181E+02 |
| | 73.47 | -0.246E+01 | -0.243E+01 | -0.262E+04 | -0.872E+04 | 0.601E+02 |
| 37 | 260.57 | 0.196E-01 | -0.834E+01 | -0.421E+04 | -0.202E+05 | -0.305E+02 |
| | 48.82 | -0.245E+01 | -0.253E+01 | -0.268E+04 | -0.893E+04 | -0.101E+03 |
| 38 | 258.50 | 0.210E+00 | -0.807E+01 | -0.285E+04 | -0.167E+05 | -0.842E+02 |
| | 24.26 | -0.245E+01 | -0.190E+01 | -0.273E+04 | -0.910E+04 | -0.280E+03 |
| 39 | 254.12 | 0.355E+00 | -0.781E+01 | -0.290E-10 | -0.923E+04 | -0.144E+03 |
| | 0.00 | -0.247E+01 | -0.127E+01 | -0.277E+04 | -0.923E+04 | -0.479E+03 |

# Appendix F: Improvement Costs

**Table 1: Opinion of Cost - 2022 Proposed Public Improvements**

| Item | Quantity | Unit | Unit Cost | **Item Total** |
|---|---|---|---|---|
| **Bridge Improvements** | | | | |
| Bridge Crossing, 58S Bridgecor Conspan Arch, 43ft Span | 1 | LS | $ 750,000 | $ 750,000 |
| Contingency 10% | | | | $ 75,000 |
| **Total** | | | | **$ 825,000** |
| | | | | |
| **Drainage Improvements** | | | | |
| Handrail | 637 | LF | $ 130 | $ 82,810 |
| 30" Grouted Boulders | 1,450 | CY | $ 275 | $ 398,750 |
| 30" to 36" Grouted Boulders | 24 | CY | $ 375 | $ 9,000 |
| Grout Cutoff Wall | 250 | LF | $ 140 | $ 35,000 |
| Type M Soil Riprap, d50=12" | 980 | CY | $ 85 | $ 83,300 |
| Type M Void-Filled Riprap, d50=12" | 740 | CY | $ 100 | $ 74,000 |
| Concrete Grade Control Structure | 38 | CY | $ 800 | $ 30,400 |
| Seeding and Mulch | 0.5 | AC | $ 1,600 | $ 800 |
| Subtotal | | | | $ 714,060 |
| Contingency 10% | | | | $ 71,406 |
| **Total** | | | | **$ 785,466** |
| | | | | |
| **Bridge and Drainage Improvements Total Cost** | | | | **$ 1,610,466** |

**Table 2: Proposed Public Improvements 1996 DBPS vs 2022 Design Cost Comparsion**

| Item | Quantity | Unit | Unit Cost | **Item Total** |
|---|---|---|---|---|
| **Bridge Improvements** | | | | |
| 2022 Bridge Crossing, 58S Bridgecor Conspan Arch, 43ft Span[1] | 1 | LS | $ 825,000 | $ 825,000 |
| 1996 DBPS (4) 10'Wx8'H CBC[2] | 1 | LS | $ 292,282 | $ 292,282 |
| **Drainage Improvements** | | | | |
| 2022 Drop Structures and Channel Improvements[1] | 630 | LF | $ 1,247 | $ 785,466 |
| 1996 DBPS Check Structures[2] | 2 | LS | $ 33,725 | $ 67,450 |
| 2022 Design Total Cost | | | | $ 1,610,466 |
| 1996 DBPS Total Costs[2] | | | | $ 359,731 |
| | | | Difference | $ 1,250,735 |

[1] See Table 1 cost details

[2] 1996 DBPS dollars adjusted to 2022 (x 2.342)

# Briargate Bridge at Sand Creek at Sterling Ranch
## Cost Comparison

| El Paso County Drainage Basin Fee Increases | | | | |
|---|---|---|---|---|
| Year | Increase Amount | Resolution | Reception # | |
| 1996 | 4% (effectively none to 1999) | 96-60 | 096025092 | |
| 1997 | None (effectively to 1999) | | | |
| 1998 | None (effectively to 1999) | | | |
| 1999 | New /imp ac Setup | 99-383 | 099175333 | 1.000 |
| 2000 | 4.00% | 02-80 | 202038189 | 1.040 |
| 2001 | None | N/A | | 1.040 |
| 2002 | 7.00% | 02-52 | | 1.113 |
| 2003 | 3.00% | 03-34 | 203016420 | 1.146 |
| 2004 | 3.00% | 04-41 | 204020181 | 1.181 |
| 2005 | 5.00% | | | 1.240 |
| 2006 | 4.00% | 06-31 | 206018243 | 1.289 |
| 2007 | 10.00% | 07-57 | 207020477 | 1.418 |
| 2008 | None | N/A | | 1.418 |
| 2009 | 6.00% | 09-23 | 209006307 | 1.503 |
| 2010 | None | N/A | | 1.503 |
| 2011 | None | N/A | | 1.503 |
| 2012 | 6.00% | 11-449 | 211129092 | 1.593 |
| 2013 | None | N/A | | 1.593 |
| 2014 | 4.30% | | 214028996 | 1.662 |
| 2015 | None | N/A | 215109527 | 1.662 |
| 2016 | 4.80% | | 216031430 | 1.742 |
| 2017 | 3.50% | | 217021072 | 1.803 |
| 2018 | 5.70% | 17-348 | 217150646 | 1.905 |
| 2019 | 6.70% | 18-470 | 218142446 | 2.033 |
| 2020 | 4.0% | 19-441 | 219156065 | 2.114 |
| 2021 | 3.5% | 20-424 | 220200117 | 2.188 |
| 2022 | 7.0% | 21-468 | 221224001 | 2.342 |

1996 Sand Creek DBPS

STA 863+50
DROP

STA 861+50 CHECK

NEW 6'H x 10'W CBC
100-YR CAPACITY

REACH SC-8

PROP. 4-8'H x 10'W CBC
100-YR CAPACITY

ANNEL DATA,
T 51

BRIARGATE BLVD

STA 857+00 CHECK

MATCH STA 854+20 SHT 51

SAND CREEK DR
BASIN PLANNING
PRELIMINARY DESIGN

| | |
|---|---|
| Project No | 90-04-09 |
| Date: | 11/92 |
| Design: | RNW |
| Drawn: | EAK |
| Check: | RNW |
| Revisions: | |

52

RIPRAP CHANNEL
= 3', S = 1.3%
@ 450' INTERVALS
cfs

STA 852+00 CHECK

150

va Engineering Corporat
W. Bijou Street
rado Springs, Colorado
05-1308

Table VIII-7:

SAND CREEK DRAINAGE BASIN PLANNING STUDY
BRIDGE CROSSING COST ESTIMATE
SAND CREEK DRAINAGE BASINS

| ROADWAY | REACH NUMBER | DRAINAGEWAY SEGMENT | CROSSING TYPE | JURISIDICTION CITY | JURISIDICTION COUNTY | SIZE | UNIT | UNIT COST | TOTAL COST COUNTY | TOTAL COST CITY |
|---|---|---|---|---|---|---|---|---|---|---|
| | | SAND CREEK | | | | | | | | |
| CHELTON ROAD | SC-1 | 115 | 210' TWO-SPAN BRIDGE | X | | 16800 | SF | $80 | $0 | $1,344,000 |
| STETSON HILLS BLVD. | SC-6 | 130 | 3- 8'Hx10'W CBC | X | | 200 | LF | $1,110 | $0 | $222,000 |
| JEDEDIAH SMITH RD. | SC-6 | 137 | 3- 8'Hx10'W CBC | X | | 60 | LF | $1,110 | $0 | $66,600 |
| PETERSON ROAD | SC-6 | 141 | 80' CLEAR SPAN BRIDGE | X | | 6400 | SF | $80 | $0 | $512,000 |
| DUBLIN BOULEVARD | SC-7 | 141 | 80' CLEAR SPAN BRIDGE | X | | 6400 | SF | $80 | $0 | $512,000 |
| MARKSHEFFEL ROAD | SC-8 | 151 | 3- 10'Hx10'W CBC | | X | 80 | LF | $1,260 | $100,800 | $0 |
| RESEARCH PARKWAY | SC-8 | 163 | 4- 8'Hx10'W CBC | | X | 80 | LF | $1,560 | $124,800 | $0 |
| BANNING-LEWIS PRKWY | SC-8 | 187 | 4- 8'Hx10'W CBC | | X | 80 | LF | $1,560 | $124,800 | $0 |
| | | CENTER TRIBUTARY | | | | | | | | |
| W. FRONTAGE ROAD | CT-1 | 142 | 3- 6'Hx16'W CBC | | X | 60 | LF | $1,770 | $106,200 | $0 |
| US 24 BYPASS | CT-1 | 142 | 3- 6'Hx14'W CBC | | X | 150 | LF | $1,410 | $211,500 | $0 |
| E. FRONTAGE RD, US 24 | CT-1 | 142 | 3- 6'Hx14'W CBC | | X | 60 | LF | $1,410 | $84,600 | $0 |
| BIJOU STREET, US 24 | CT-1 | 142 | 3- 6'Hx14'W CBC | | X | 60 | LF | $1,410 | $84,600 | $0 |
| PLATTE AVENUE, US 24 | CT-2 | 142 | 3- 6'Hx14'W CBC | | X | 120 | LF | $1,410 | $169,200 | $0 |
| GALLEY ROAD | CT-4 | 144 | 3- 5'Hx8'W CBC | | X | 100 | LF | $900 | $90,000 | $0 |
| | | WEST FORK SAND CREEK | | | | | | | | |
| GALLEY ROAD | WF-2 | 155 | 54' CLEAR SPAN BRIDGE | X | | 5130 | SF | $80 | $0 | $410,400 |
| PALMER PARK BLVD. | WF-2 | 156 | 54' CLEAR SPAN BRIDGE | X | | 5130 | SF | $80 | $0 | $410,400 |
| CONSTITUTION AVE. | WF-3 | 159 | 40' CLEAR SPAN BRIDGE | X | | 3200 | SF | $80 | $0 | $256,000 |
| MAIZELAND ROAD | WF-3 | 170 | 30' CLEAR SPAN BRIDGE | X | | 2400 | SF | $80 | $0 | $192,000 |
| SO. CAREFREE | WF-3 | 170 | 2- 6'Hx15'W CBC | X | | 80 | LF | $1,200 | $0 | $96,000 |
| TOTAL BRIDGE CONSTRUCTION COSTS, SAND CREEK | | | | | | | | | $1,096,500 | $4,021,400 |

TABLE VIII-2: SAND CREEK DRAINAGE BASIN PLANNING STUDY
DRAINAGEWAY CONVEYANCE COST ESTIMATE
WITH SELECTED DETENTION ALTERNATIVES

| SEGMENT NUMBER | REACH NUMBER | SEGMENT LENGTH (FT) | IMPROVEMENT TYPE | IMP. LENGTH (FT) | UNIT COST ($/LF) | NUMBER OF GRADE CONTROLS | GRADE CONTROL LENGTH (FT) | TOTAL REIMBURSABL COSTS | TOTAL COST |
|---|---|---|---|---|---|---|---|---|---|
| 148-2 | " | 2600 | " | 2150 | 127 | 5 | 620 | $384,650 | $384,650 |
| 151 | SC-8 | 1700 | 10-YEAR RIPRAP | 500 | 238 | 3 | 250 | $164,000 | $164,000 |
| 160 | " | 5100 | SEL. LININGS (1 SIDE) | 4400 | 127 | 6 | 720 | $688,400 | $688,400 |
| | | | 10-YR RIPRAP | 600 | 238 | 0 | 0 | $142,800 | $142,800 |
| 163 | " | 6300 | SEL. LININGS (1 SIDE) | 2600 | 127 | 15 | 1200 | $546,200 | $546,200 |
| | | | 10-YR RIPRAP | 350 | 238 | 0 | 0 | $83,300 | $83,300 |
| 187 | " | 1200 | SEL. LININGS (1 SIDE) | 0 | 0 | 2 | 160 | $28,800 | $28,800 |
| 170 | SC-9 | 3200 | " | 0 | 0 | 4 | 320 | $57,600 | $57,600 |
| 171 | " | 5000 | " | 0 | 0 | 2 | 170 | $30,600 | $30,600 |
| 172 | " | 3650 | " | 0 | 0 | 2 | 150 | $27,000 | $27,000 |
| TOTAL SAND CREEK DRAINAGEWAY | | | | | | | | $15,560,220 | $18,279,420 |