
WOLF RANCH NORTH FILING NO. 5

A SUBDIVISION OF PORTIONS OF THE SOUTHWEST QUARTER OF THE NORTHWEST QUARTER (SW1/4NW1/4), THE NORTHWEST QUARTER OF THE SOUTHWEST QUARTER (NW1/4SW1/4), OF SECTION 30, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER (SE1/4NE1/4), AND THE NORTHEAST QUARTER OF THE SOUTHEAST QUARTER (NE1/4SE1/4) OF SECTION 25, TOWNSHIP 12 SOUTH, RANGE 66 WEST OF THE 6TH P.M., CITY OF COLORADO SPRINGS, EL PASO COUNTY, COLORADO



KNOW ALL MEN BY THESE PRESENTS:

That Wolf Ranch North, LLC. a Colorado limited liability company being the Owner of the following described Tract of Land:

A tract of land being portions of the Southwest quarter of the Northwest quarter (SW1/4NW1/4), the Northwest quarter of the Southwest quarter (NW1/4SW1/4) of Section 30, Township 12 South, Range 65 West of the 6th P.M., the Southeast quarter of the Northeast quarter (SE1/4NE1/4), and the Northeast quarter of the Southeast quarter of Section 25, Township 12 South, Range 66 West of the 6th P.M., El Paso County, Colorado being more particularly described as follows:

BEGINNING at the Northeast corner on Lot 40, Wolf Ranch North Filing No. 3 as recorded at of the records of said El Paso County, the following eleven (11) courses are on the Southerly and Southeasterly line of said Wolf Ranch North Filing No. 3; thence: 1) S86°23'07"W a distance of 120.00 feet; 2) S85°34'08"W a distance of 50.01 feet; 3) N85°34'19"W a distance of 67.66 feet; 4) N67°58'27"W a distance of 40.83 feet; 5) N22°54'10"W a distance of 41.16 feet; 6) N09°56'04"W a distance of 65.93 feet; 7) N14°13'29"W a distance of 67.51 feet; 8) N18'10'59"W a distance of 55.61 feet; 9) N22'07'04"W a distance of 66.77 feet; 10) N26°23'08"W a distance of 66.77 feet; 11) N29°01'52"W a distance of 304.67 feet to the Northeast corner thereof: thence N60°58'08"E a distance of 734.78 feet: thence N64°03'57"E a distance of 66.00 feet to a point on a curve, from which a radial line bears N64*03'57"E; thence on a curve to the left having a central angle of 08°26'25", a radius of 461.50 feet for an arc distance of 67.98 feet, whose chord bears S30'09'15"E; thence S34'22'28"E a distance of 397.08 feet to a point of curve; thence on a curve to the left having a central angle of 14'27'47". a radius of 661.50 feet for an arc distance of 166.98 feet, whose chord bears S41'36'21"E to the Northeast corner of Wolf Lake Drive, dedicated to the public in Wolf Ranch North Filing No. 4 as of the records of said El Paso County, the

following six (6) courses are on the Northwesterly line of said Wolf Ranch North Filing No. 4; thence: 1) S51*02'40"W a distance of 394.08 feet; 2) N44*05'17"W a distance of 51.86 feet; 3) S60*58'08"W a distance of 241.72 feet; 4) S10*26'10"E a distance of 35.97 feet; 5) S08*30'54"E a distance of 65.27 feet; 6) S05*12'16"E a distance of 65.27 feet to the POINT OF BEGINNING and containing 13.274 acres of land, more or less.

OWNER:

The aforementioned Wolf Ranch North, LLC. a Colorado limited liability company, Nor'wood Limited, Inc., a Colorado corporation by Timothy W. Seibert, as Vice President, has executed this instrument this ______ day of ______, 2019 A.D.

Timothy W. Seibert, as Vice President

STATE OF COLORADO)
) ss
COUNTY OF EL PASO)

The foregoing instrument was acknowledged before me this _____ day of _______ 2019 A.D. by Timothy W. Seibert as, Vice President of Nor'wood Limited, Inc., a Colorado corporation, Manager of Wolf Ranch North, LLC, a Colorado limited liability company

WITNESS MY HAND AND OFFICIAL SEAL

My commission expires:


DEDICATION:

The above owner has caused said tract of land to be platted into Lots, a Tract, Streets and Easements as shown on the plat. The undersigned does hereby dedicate, grant and convey to the City of Colorado Springs those public streets and public easements as shown on the plat; and further restricts the use of all public easements to the City of Colorado Springs and/or its assigns; provided, however, that the sole right and authority to vacate, release or quitclaim all or any public streets, tracts, and public easements shall remain exclusively vested in the City of Colorado Springs. All public streets or additional right of way are hereby dedicated to the City of Colorado Springs for public use. This tract of land as herein platted shall be known as "WOLF RANCH NORTH FILING NO. 5". City of Colorado Springs, El Paso County, Colorado.


EASEMENTS:

All Lots will have a 5 foot wide front and 7 foot wide rear yard easement for public utilities and drainage purposes only. All side lot lines will have a 5 foot wide easement for public utilities and drainage purposes only. All lot lines abutting a public Right—of—Way are hereby platted with a 5 foot wide easement for public utilities, public drainage and public improvements. All lots adjacent to two street right—of—ways are hereby platted with a 25 foot by 25 foot triangle easement for public improvements only. Surface maintenance of all public easements is vested in the property owners.

All easements that are dedicated hereon for public utility purposes shall be subject to those terms and conditions as specified in the instrument recorded at Reception Number 212112548 of the records of El Paso County, Colorado. All other easements or interests of record affecting any of the platted property depicted hereon shall not be affected and shall remain in full force and effect.



TYPICAL LOT EASEMENTS



TYPICAL 25'X25' CORNER EASEMENT FOR PUBLIC IMPROVEMENTS

NOTICE IS HEREBY GIVEN:

That the area included in the Plat described herein, is subject to the Code of the City of Colorado Springs, 2001, as Amended.

No building permits shall be issued for building sites within this plat until all required fees have been paid and all required public and private improvements have been installed as specified by the City of Colorado Springs, or, alternatively, until acceptable assurances, including but not limited to letters of credit, cash, subdivision bonds, or combinations thereof, guaranteeing the completion of all required public improvements including but not limited to drainage, street and erosion control and private drainage improvements have been placed on file with the City of Colorado Springs.

NOTES:

- 1. No man-made or non-man-made obstructions allowed to penetrate the 40:1 approach surface of the Colorado Springs Municipal Airport.
- 2. All exterior lighting plans to be approved by the Director of Avigation to prevent a hazard to aircraft.
- 3. No electromagnetic, light, or any physical emission which might interfere with aircraft, aviation, communications or navigational aids to be allowed.
- 4. This subdivision plat does not constitute a title search by Rockwell Consulting, Inc. to determine ownership, easements, or Rights—of—Way record. Rockwell Consulting, Inc. was not provided a current title commitment or requested to search said records.
- 5. The lineal units of measure used for the survey of land described herein, was the U.S. survey foot.
- 6. The parcel in this request lies beneath the 40:1 approach surface of Runway 17R.
- 7. NOTICE: This property may be impacted by noise and similar incidental sensory effects of flight caused by aircraft used in the USAF Academy's Airmanship Program. This notice shall remain in effect until the Academy shall cease to be actively used. This notice shall run with the land. Existing Avigation Easement as recorded in Book 5144 at Page 1022.
- Bearings used herein are based on a Northeasterly line of Lot 25—29, Wolf Ranch North Filing No. 4 as recorded at Reception No. ______ of the records of El Paso County, Colorado, which bears \$51.02.40.W a distance of 383.94 feet, between two found monuments as shown.
- 9. Tract A is for public open space easement, public trail and sidewalk easement, public drainage easement, public improvement easement, public utility easement, landscape, irrigation, and fencing Tract A shall be owned and maintained by the Old Ranch Metropolitan District as recorded at Reception No. 202204061. Said Tract will be conveyed by separate document to the Old Ranch Metropolitan District.
- 10. This subdivision is in the Upper Cottonwood Creek Three (UCC-3) Metropolitan District.
- 11. This property is located within Zone X (Areas determined to be outside the 500—year floodplain) as established by F.E.M.A. flood plain as determined by the Flood Insurance Rate Map (FIRM), Community Panel Number 08041C0530 G effective date December 7, 2018.

SURVEYOR'S STATEMENT:

The undersigned Registered Professional Land Surveyor licensed in the State of Colorado, hereby states and declares that the accompanying plat was surveyed and drawn under his responsible charge and accurately shows the described tract of land, and subdivision thereof, and that the requirements of Title 38 of the Colorado Revised Statues, 1973, as Amended, have been met to the best of his knowledge and belief.

ROCKWELL CONSULTING, INC.

JOHN L. BAILEY, PLS #19586

CITY APPROVAL:

City Engineer

On behalf of the City of Colorado Springs, the undersigned hereby approve for filing the accompanying plat of "WOLF RANCH NORTH FILING NO. 5".

City	Planning Director	:	Date

			s	
Cit	y Clerk			Date
* 1	• • •			

CLERK AND RECORDER:

STATE OF COLORADO)
COUNTY OF EL PASO)
hereby certify that this instrument was filed for record in my office
o'clockM., this day of
2019 A.D., and is duly recorded at Reception No.
of the Records of El Paso County, Colorado.
Chuck Broerman, RECORDER
BY:
CUPCHARCE: Deputy

FEES:							
SCHOOL FEE:	<u> </u>			· · · · · · · · · · · · · · · · · · ·			
BRIDGE FEE:						<u> </u>	
PARK FEE:							
DRAINAGE FEE							

CITY FILE NO.: AR FP ____ FILE: 18020FP1.DWG 01/26/19


NOTICE: ACCORDING TO COLORADO LAW YOU MUST COMMENCE
ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY
WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT.
IN NO EVENT, MAY ANY ACTION BASED UPON ANY DEFECT IN
THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE

DATE OF THE CERTIFICATION SHOWN HEREON.



WOLF RANCH NORTH FILING NO. 5

A SUBDIVISION OF PORTIONS OF THE SOUTHWEST QUARTER OF THE NORTHWEST QUARTER (SW1/4NW1/4), THE NORTHWEST QUARTER OF THE SOUTHWEST QUARTER (NW1/4SW1/4), OF SECTION 30, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER (SE1/4NE1/4), AND THE NORTHEAST QUARTER OF THE SOUTHEAST QUARTER (NE1/4SE1/4) OF SECTION 25, TOWNSHIP 12 SOUTH, RANGE 66 WEST OF THE 6TH P.M., CITY OF COLORADO SPRINGS, EL PASO COUNTY, COLORADO



ROCKWELL
1955 N. UNION BLVD., SUITE 200
COLORADO SPRINGS, CO 80909
(719) 475-2575 • FAX (719) 475-9223

IN NO EVENT, MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.

DRAWN BY: JLB CHECKED BY: JLB DATE: 09/23/18

SHEET 2 OF 2