

Notice: This review specifically focused on Cross Roads Mixed Use. Similar approach to the review of the TIS under the preliminary plan applications for the Crossroads North and Meadowbrook Park.

Traffic Impact Study

Provide recommendations for the internal private road classification/cross section Crossroads Mixed Use. The trip generation estimate is 13,076 ADT while the preliminary plan showed a local road cross section which has a design ADT of 3,000.

What is the intent regarding the continuation of Meadowbrook Parkway to the west?

Prepared for:

Colorado Springs Equities LLC

Kimley»»Horn

Add PCD File No.
P208 and SP2011

T R A F F I C I M P A C T S T U D Y

Crossroads-Meadowbrook

El Paso County, Colorado

Prepared for
Colorado Springs Equities LLC
c/o The Equity Group
90 South Cascade Avenue
Suite 1500
Colorado Springs, Colorado 80903

Prepared by
Kimley-Horn and Associates, Inc.
Curtis D. Rowe, P.E., PTOE
4582 South Ulster Street
Suite 1500
Denver, Colorado 80237
(303) 228-2300



October 2020

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

The attached traffic report and supporting information were prepared under my responsible charge and they comport with the standard of care. So far as is consistent with the standard of care, said report was prepared in general conformance with the criteria established by the County for traffic reports.

TABLE OF CONTENTS

TABLE OF CONTENTS	i
LIST OF TABLES	ii
LIST OF FIGURES	ii
1.0 EXECUTIVE SUMMARY	1
2.0 INTRODUCTION.....	6
3.0 EXISTING AND FUTURE CONDITIONS	8
3.1 Existing and Future Study Area	8
3.2 Existing and Future Roadway Network	8
3.3 Existing Traffic Volumes	12
3.4 Unspecified Development Traffic Growth.....	12
4.0 PROJECT TRAFFIC CHARACTERISTICS.....	16
4.1 Trip Generation.....	16
4.2 Trip Distribution	18
4.3 Traffic Assignment and Total (Background Plus Project) Traffic	18
5.0 TRAFFIC OPERATIONS ANALYSIS	28
5.1 Analysis Methodology.....	28
5.2 Key Intersection Operational Analysis	29
5.3 Project Access Operational Analysis	34
5.4 Sight Distance Evaluation.....	35
5.5 Bicycle and Pedestrian Access.....	36
5.6 CDOT Access Permit Analysis Need	37
5.7 Queuing Analysis.....	41
5.8 Intersection Improvement Summary	42
6.0 CONCLUSIONS AND RECOMMENDATIONS	46

APPENDICES

- Appendix A – Intersection Count Sheets
- Appendix B – CDOT Annual Traffic Data
- Appendix C – Trip Generation Worksheets
- Appendix D – Intersection Analysis Worksheets
- Appendix E – Signal Warrant Analysis
- Appendix F – Queueing Analysis Worksheets
- Appendix G – Conceptual Site Plan

LIST OF TABLES

Table 1 – Crossroads-Meadowbrook Project External Traffic Generation	17
Table 2 – Level of Service Definitions	28
Table 3 – Meadowbrook Parkway and Marksheffel Road LOS Results	29
Table 4 – Marksheffel Road and US-24 LOS Results.....	30
Table 5 – Newt Drive and Meadowbrook Parkway LOS Results	31
Table 6 – SH-94 and US-24 LOS Results	32
Table 7 – SH-94 and Marksheffel Road LOS Results.....	33
Table 8 – Project Access LOS Results.....	35
Table 9 – Turn Lane Storage Length Analysis Results.....	41
Table 10 – Crossroads – Meadowbrook Intersection Improvement Summary	45

LIST OF FIGURES

Figure 1 – Vicinity Map.....	7
Figure 2 – Surrounding Site Area.....	9
Figure 3 – Existing Lane Configurations.....	11
Figure 4 – 2020 Existing Adjusted Traffic Volumes	13
Figure 5 – 2025 Background Traffic Volumes.....	14
Figure 6 – 2040 Background Traffic Volumes.....	15
Figure 7 – Meadowbrook Park Trip Distribution.....	19
Figure 8 – Crossroads North Trip Distribution	20
Figure 9 – Crossroads Mix Use Trip Distribution	21
Figure 10 – Meadowbrook Park Traffic Assignment	22
Figure 11 – Crossroads North Traffic Assignment.....	23
Figure 12 – Crossroads Mix Use Traffic Assignment.....	24
Figure 13 – Total Traffic Assignment.....	25
Figure 14 – 2025 Background Plus Project Traffic Volumes	26
Figure 15 – 2040 Background Plus Project Traffic Volumes	27
Figure 16 – 2025 Recommended Lane Configurations	43
Figure 17 – 2040 Recommended Lane Configurations	44

1.0 EXECUTIVE SUMMARY

The Crossroads-Meadowbrook development areas are proposed along the north and south sides of US-24 in El Paso County, Colorado. This traffic study evaluates three separate project areas; the first area, named Meadowbrook Park, is located on the northeast corner of the US-24 and Newt Drive/SH-94 intersection, the second area, Crossroads North, is located within the triangle area between US-24, Marksheffel Road, and SH-94, and the third development area, Crossroads Mix Use, is located on the northwest corner of the US-24 and Newt Drive/SH-94 intersection.

All three of these development areas are anticipated to include approximately 70 single-family detached housing units, 280 multifamily (mid-rise) housing units, a 18.28-acre public park, a 52,000 square foot movie theater, 44,942 square feet of retail space, a 7,200 square foot tire store, a 127,000 square foot home improvement store, a 114,000 square foot furniture store, 21,200 square feet of sit down restaurant space, 20,909 square feet of fast food restaurants, a 2,400 square foot coffee shop, and a gas station with a 5,000 square foot convenience market. It is expected that buildout of these development areas would be completed in the next five years. Therefore, for purposes of this analysis, this project was evaluated for the short-term 2025 and long-term 2040 horizons.

The purpose of this study is to identify development area traffic generation characteristics, to identify potential traffic related impacts on the local street system, and to develop mitigation measures required for identified impacts. The following intersections were incorporated into this traffic study in accordance with El Paso County and CDOT standards and requirements:

- Meadowbrook Parkway and Marksheffel Road
- US-24 and Marksheffel Road
- Meadowbrook Parkway and Newt Drive
- US-24 and SH-94
- SH-94 and Marksheffel Road

Regional access to Crossroads-Meadowbrook is provided by Interstate 25 (I-25), Powers Boulevard (SH-21), and US-24. Primary access to the development areas will be provided by Marksheffel Road and Meadowbrook Parkway. Direct access to Meadowbrook Park is proposed

at one full movement access along Meadowbrook Parkway to align with the existing Preble Drive. Direct access to Crossroads North is proposed from two full movement accesses along Marksheffel Road approximately 1,000 feet and 2,000 feet north of SH-94. Direct access to Crossroads Mix Use is proposed along the future extension of Meadowbrook Parkway at two full movement accesses and an eastern right-in/right-out access.

All three development areas of the Crossroads-Meadowbrook project evaluated in the study are expected to generate a total of approximately 31,118 external daily weekday trips with 2,118 of these trips occurring during the morning peak hour and 2,394 trips occurring during the afternoon peak hour.

Distribution of site traffic on the street system was based on the area street system characteristics, existing traffic patterns, and volumes, anticipated surrounding development area characteristics, and traffic volumes. The following recommendations were provided for each project area:

1. Provide roundabout analysis. Current policy is to design per the Wisconsin DOT roundabout design criteria.
2. Provide autoturn analysis of the intersection. Per ECM Table 2-7 design vehicle is WB-50.
3. Provide table of critical design parameters.
4. Provide the rodel model report.
5. Provide the fastest path analysis/exhibit.
6. Provide the entry angle exhibit.

Based on the analysis presented in this report, Kimley-Horn believes the proposed Crossroads-Meadowbrook project areas will be successfully incorporated into the existing and future roadway network. The proposed project development and expected traffic volumes resulted in the following recommendations/conclusions:

2025 Recommendations:

- A CDOT Access Permit will be required for the Newt Drive north leg of the US-24 intersection in association with the Crossroads Mix Use development. Likewise, CDOT Access Permits will be required for the south leg of SH-94 at US-24 and north leg of Marksheffel Road at SH-94 in association with the Crossroads North development.
- It is recommended that a single lane roundabout be constructed at the Meadowbrook Parkway and Newt Drive intersection with development of the Crossroads Mix Use project. It is recommended that the roundabout have single lane approaches on the

eastbound Newt Drive, northbound Meadowbrook Parkway, and southbound Meadowbrook Parkway approaches and a two-lane approach on westbound Newt Drive with a shared left turn/through lane into the roundabout and a separate right turn lane.

- The intersection of SH-94 and US-24 is projected to operate poorly in 2025 with the existing intersection configuration. Therefore, US-24 may need to provide three through lanes in each direction through this intersection in the near-term horizon. The additional through lanes are a regional capacity improvement that should be considered by CDOT and El Paso County in the near future. If and when US-24 is improved to provide three through lanes in each direction, it is recommended that a separate 600-foot plus 225-foot taper right turn lane be constructed to maintain free right turn movements to eastbound SH-94. The third southwestbound through lane along US-24 can be designated by absorbing the existing right turn lane. The six-lane section of US-24 can occur between the Peterson Road interchange to the west and transition back to a four-lane roadway east of SH-94. In addition to these regional improvements, it is recommended that the existing single 900-foot left turn lane be changed to 860-feet plus 225-foot taper with dual left turn lanes on the northeastbound US-24 approach for the left turn to Newt Drive. The area for these dual lefts is presently mostly available; however, the lane is striped out which will require restriping and a slight extension may also need to be constructed. A traffic signal modification will be required at the intersection to incorporate these improvements.
- Traffic signals are anticipated to be needed and warranted at both full movement access intersections along Marksheffel Road for Crossroads North. Therefore, traffic signals are recommended for installation at these intersections with development of Crossroads North. It is recommended that a 235-foot with 200-foot taper (based on El Paso County standards for 50 mph) southbound right turn lane be constructed at both access intersections along Marksheffel Road due to the volume of traffic entering Crossroads North at this access. Likewise, separate eastbound left turn and right turn lanes are recommended to serve exiting traffic out of Crossroads North.

- All project access driveways for Meadowbrook Park and Crossroads Mix Use are recommended to be two-way stop-controlled with R1-1 “STOP” signs installed for the exiting approaches.
- From the CDOT SHAC analysis it was found that a westbound acceleration lane is needed from the southbound right turn at the intersection of SH-94 and Marksheffel Road in association with the Crossroads North project. It is recommended that the acceleration lane be constructed as a continuous lane to tie into the outside through lane on the westbound approach to US-24.
- It is recommended that the following turn lanes be lengthened to CDOT standards and accommodate future projected queue lengths; the 475-foot westbound SH-94 dual left turn lanes at the intersection of US-24 and SH-94 need to be lengthened to 740 feet with a 145 foot taper (in association with Crossroads North), and the 300-foot eastbound left turn lane and the 250-foot westbound right turn lane at the intersection of SH-94 and Marksheffel Road need to be lengthened to 850 feet with a 225 foot taper and 600 feet with a 225 foot taper, respectively (in association with Crossroads North).
- Meadowbrook Parkway will be extended along Crossroads Mix Use development project area in association with that project. It is recommended that this roadway be designated as a three-lane roadway with a center two-way left turn lane.

2040 Recommendations:

- If future traffic volume projections are realized, US-24 may need to provide three through lanes in each direction through the Marksheffel Road intersection. If and when this occurs, it is believed that the existing separate eastbound and westbound US-24 right turn lanes could be converted to shared through/right turn lanes.
- At the SH-94 and Marksheffel Road intersection, dual eastbound left turn lanes operating with protected only phasing may be needed to provide acceptable operations.

General Recommendations:

- Any on-site and off-site roadway, signing, striping, and signal improvements should be incorporated into the Civil Drawings, and conform to El Paso County and/or CDOT standards as applicable, as well as the Manual on Uniform Traffic Control Devices – 2009 Edition (MUTCD).


2.0 INTRODUCTION

Kimley-Horn and Associates, Inc. (Kimley-Horn) has prepared this report to document the results of a Traffic Impact Study of future traffic conditions associated with the proposed Crossroads-Meadowbrook project to be located along the north and south sides of US-24 in El Paso County, Colorado. A vicinity map illustrating the location of the Crossroads-Meadowbrook project is shown in **Figure 1**.

This traffic study evaluates three separate development areas; the first area, named Meadowbrook Park, is located on the northeast corner of the US-24 and Newt Drive/SH-94 intersection, the second area, Crossroads North, is located within the triangle area between US-24, Marksheffel Road, and SH-94, and the third development area, Crossroads Mix Use, is located on the northwest corner of the US-24 and Newt Drive/SH-94 intersection. All three of these development areas are anticipated to include approximately 70 single-family detached housing units, 280 multifamily (mid-rise) housing units, a 18.28-acre public park, a 52,000 square foot movie theater, 44,942 square feet of retail space, a 7,200 square foot tire store, a 127,000 square foot home improvement store, a 114,000 square foot furniture store, 21,200 square feet of sit down restaurant space, 20,909 square feet of fast food restaurants, a 2,400 square foot coffee shop, and a gas station with a 5,000 square foot convenience market. A conceptual site plan for the project is attached in **Appendix G**. It is expected that buildout of these development areas would be completed in the next five years. Therefore, for purposes of this analysis, this project was evaluated for the short-term 2025 and long-term 2040 horizons.

The purpose of this study is to identify development area traffic generation characteristics, to identify potential traffic related impacts on the local street system, and to develop mitigation measures required for identified impacts. The following intersections were incorporated into this traffic study in accordance with El Paso County and CDOT standards and requirements:

- Meadowbrook Parkway and Marksheffel Road
- US-24 and Marksheffel Road
- Meadowbrook Parkway and Newt Drive
- US-24 and SH-94
- SH-94 and Marksheffel Road



CROSSROADS-MEADOWBROOK
COLORADO SPRINGS, CO
VICINITY MAP

FIGURE 1

3.0 EXISTING AND FUTURE CONDITIONS


3.1 Existing and Future Study Area

The existing site areas are comprised of vacant land. The surrounding area contains a mix of uses. Directly to the east of Crossroads North exists a water treatment plant. Directly to the south are industrial uses. Directly to the west is mainly residential neighborhoods. Other industrial uses are proposed north of Meadowbrook Park. Outside of these areas, the Colorado Springs Airport and Peterson Air Force Base exists to the southwest. The site area is shown in the aerial of **Figure 2**.

3.2 Existing and Future Roadway Network

Regional access to Crossroads-Meadowbrook is provided by Interstate 25 (I-25), Powers Boulevard (SH-21), and US-24. Primary access to the development areas will be provided by Marksheffel Road and Meadowbrook Parkway. Direct access to Meadowbrook Park is proposed at one full movement access along Meadowbrook Parkway to align with the existing Preble Drive. Direct access to Crossroads North is proposed from two full movement accesses along Marksheffel Road approximately 1,000 feet and 2,000 feet north of SH-94. Direct access to Crossroads Mix Use is proposed along the future extension of Meadowbrook Parkway at two full movement accesses and an eastern right-in/right-out access.

SH-94 is a CDOT Highway, categorized E-X: Expressway, Major Bypass that provides one through lane of travel both eastbound and westbound in the development area. SH-94 has a 55 mile per hour speed limit through the study area. US-24 is a CDOT Highway, categorized E-X: Expressway, Major Bypass that provides two through lanes of travel both eastbound and westbound in the vicinity of the project areas. US-24 has a 55 mile per hour speed limit through the study area. Marksheffel Road is an El Paso County arterial that provides two through lanes of travel in each direction, northbound and southbound, with a 55 mile per hour speed limit through the study area. Meadowbrook Parkway is a collector roadway that provides one lane of travel in each direction, with a 35 mile per hour speed limit through the study area.



CROSSROADS—MEADOWBROOK
COLORADO SPRINGS, CO
SITE AREA

FIGURE 2


The Meadowbrook Parkway and Marksheffel Road intersection is a four-leg signalized intersection. The eastbound Meadowbrook Parkway approach consists of dual left turn lanes, one through lane, and a right turn lane. The westbound approach consists of a left turn lane, a through lane, and one right turn lane. The northbound and southbound approaches of Marksheffel Road consist of one left turn lane, two through lanes, and a right turn lane.

The Marksheffel Road and US-24 intersection is a four-leg signalized intersection. The northbound, southbound, and westbound approaches consist of a left turn lane, two through lanes, and separate right turn lanes operating with a free right turn movement. The eastbound US-24 approach consists of dual left turn lanes, two through lanes, and a right turn lane with free movements.

The Newt Drive and Meadowbrook Parkway intersection is a T-intersection with stop control on the eastbound and westbound approaches of Newt Drive. The westbound approach consists of one through lane and a right turn lane. The eastbound approach consists of one left turn lane and one through lane. The southbound approach consists of a two-way left turn lane and a right turn lane. With the construction of the Crossroads Mix Use project, a southwest leg will be constructed at this intersection by extension of Meadowbrook Parkway adjacent to the development area.

The intersection of SH-94 and US-24 is signalized with four-legs. Since both state highways run east-west, the traffic software for this intersection assigned SH-94 as east-west and US-24 as north-south. The eastbound Newt Drive approach consists of dual left turn lanes, one through lane, and a free right turn lane. The westbound SH-94 approach consists of dual left turn lanes, two through lanes, and a free right turn lane. The US-24 approaches each consist of a left turn lane, two through lanes, and a right turn lane. The westbound US-24 right turn operates with free turning movements.

The SH-94 and Marksheffel Road intersection is a four-leg signalized intersection. The eastbound and westbound approaches consist of a left turn lane, one through lane, and one right turn lane. The northbound and southbound approaches consist of a left turn lane, two through lanes, and a right turn lane. Existing intersection lane configurations and control for the study area are shown in **Figure 3**.



LEGEND

- Study Area Key Intersection
- ⋮ Signalized Intersection
- STOP Stop Controlled Approach
- XX Roadway Speed Limit
- ↪ 100' Turn Lane Length (feet)

CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 EXISTING LANE CONFIGURATIONS


FIGURE 3

3.3 Existing Traffic Volumes

Due to the effects on traffic from COVID-19, traffic counts at each intersection were derived by different methodologies. Existing peak hour turning movement counts, pedestrian counts, and bicycle counts were conducted at the intersections of SH-94 and Marksheffel Road, Meadowbrook Parkway and Newt Drive, and SH-94 and US-24 on Tuesday, June 2, 2020 and at the intersections of Marksheffel Road and US-24 and Meadowbrook Parkway and Marksheffel Road on Thursday, June 4, 2020 during the morning and afternoon peak hours. The weekday counts were conducted in 15-minute intervals during the AM and PM peak hours of adjacent street traffic from 7:00 AM to 9:00 AM and 4:00 PM to 6:00 PM. The turning movement counts were grown based on data obtained from hourly counts from the CDOT OTIS database to account for a COVID-19 adjustment for this area. The morning and afternoon peak hour counts were adjusted by 20% and 10%, respectively except for the counts at the intersection of SH-94 and Marksheffel Road which were not adjusted in the morning peak hour but were adjusted by 44% for the afternoon peak hour. These adjusted turning movement counts are shown in **Figure 4** with vehicle, pedestrian, bicycle count sheets, and CDOT OTIS data provided in **Appendix A**.

3.4 Unspecified Development Traffic Growth

According to information provided on the website for the Colorado Department of Transportation (CDOT), the average 20-year growth factor along SH-94 in the vicinity of the site is 1.29. This value equates to an annual growth rate of 1.16 percent. SH-94 traffic information from the CDOT Online Transportation Information System (OTIS) website is included in **Appendix B**. Based on this, an annual growth rate of 1.16 percent was used to calculate future traffic volumes within the project study area. This annual growth rate was used to estimate near term 2025 and long term 2040 traffic volume projections at the key intersections. Along with the growth of existing traffic volumes, project traffic from the single-family housing development to the west at Newt Drive were estimated based on the number of homes yet to be occupied and added to the background traffic volumes. Background traffic volumes for 2025 and 2040 are shown in **Figures 5** and **6**, respectively.




LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume

CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2020 EXISTING ADJUSTED
 TRAFFIC VOLUMES

FIGURE 4




LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume

CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2025 BACKGROUND
 TRAFFIC VOLUMES

FIGURE 5



LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume

CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2040 BACKGROUND
 TRAFFIC VOLUMES

FIGURE 6

4.0 PROJECT TRAFFIC CHARACTERISTICS

4.1 Trip Generation

Site-generated traffic estimates are determined through a process known as trip generation. Rates and equations are applied to the proposed land use to estimate traffic generated by the development during a specific time interval. The acknowledged source for trip generation rates is the *Trip Generation Manual*¹ published by the Institute of Transportation Engineers (ITE). ITE has established trip rates in nationwide studies of similar land uses.

For purposes of this traffic evaluation, the project was studied to include approximately 70 single-family detached housing units, 280 multifamily (mid-rise) housing units, a 18.28-acre public park, a 52,000 square foot movie theater, 44,942 square feet of retail space, a 7,200 square foot tire store, a 127,000 square foot home improvement store, a 114,000 square foot furniture store, 21,200 square feet of sit down restaurant space, 20,909 square feet of fast food restaurants, a 2,400 square foot coffee shop, and a gas station with a 5,000 square foot convenience market. Based on this, Kimley-Horn used the ITE Trip Generation Manual average rates and equations that apply to Single-Family Detached House (ITE Code 210), Multifamily Housing (Mid-Rise) (ITE Code 221), Public Park (ITE Code 411), Movie Theater (ITE Code 444), Shopping Center (ITE Code 820), Tire Superstore (ITE Code 849), Home Improvement Superstore (ITE Code 862), Furniture Store (ITE Code 890), High-Turnover (Sit-Down) Restaurant (ITE Code 932), Fast-Food Restaurant with Drive Through (ITE Code 934), Coffee/Donut Shop with Drive Through (ITE Code 937), and Gasoline Station with Convenience Market (ITE Code 960) for traffic associated with the proposed Crossroads-Meadowbrook project. The trip generation calculations are included in **Appendix C**. These calculations illustrate the equations used and directional distribution of trips based on ITE studies.

The Crossroads-Meadowbrook project is expected to generate a total of approximately 31,118 daily weekday external driveway trips. Of these, a total of 2,118 weekday morning peak hour and 2,394 weekday afternoon peak hour trips peak hour trips are expected. Calculations were based on the procedure and information provided in the ITE *Trip Generation Manual*, 10th

¹ Institute of Transportation Engineers, *Trip Generation Manual*, Tenth Edition, Washington DC, 2017.

Edition – Volume 1: User’s Guide and Handbook, 2017. **Table 1** provides the estimated external trip generation for the Crossroads-Meadowbrook project.

Table 1 – Crossroads-Meadowbrook Project External Traffic Generation

Use and Quantity	Daily	Weekday Vehicles Trips					
		AM Peak Hour			PM Peak Hour		
		In	Out	Total	In	Out	Total
Crossroads Mix Use							
Multifamily Housing (Mid-Rise) (ITE 221) – 280 DU	1,526	24	70	94	73	46	119
Shopping Center (ITE 820) – 44,942 SF	1,696	26	16	42	82	89	171
High-Turnover (Sit-Down) Restaurant (ITE 932) – 10,200 SF	1,146	56	45	101	62	38	100
Fast-Food Restaurant w/ D.T. (ITE 934) – 14,309 SF	6,740	293	282	575	243	224	467
Coffee/Donut Shop w/ D.T. (ITE 937) – 2,400 SF	1,968	109	105	214	53	53	106
Crossroads Mix Use Total	13,076	508	518	1,026	513	450	963
Crossroads North							
Public Park (ITE 411) – 18.28 Acres	14	0	0	0	1	1	2
Movie Theater (ITE 444) – 52,000 SF	4,062	5	6	11	302	19	321
Tire Superstore (ITE 849) – 7,200 SF	148	6	4	10	7	8	15
Home Improvement Superstore (ITE 862) – 127,000 SF	3,904	113	86	199	145	151	296
Furniture Store (ITE 890) – 114,000 SF	720	21	9	30	28	31	59
High-Turnover (Sit-Down) Restaurant (ITE 932) – 11,000 SF	1,234	60	49	109	66	41	107
Fast-Food Restaurant w/ D.T. (ITE 934) – 6,600 SF	3,110	135	130	265	112	104	216
Gasoline Station w/ Convenience Market (ITE 960) – 5,000 SF	4,188	208	208	416	173	173	346
Crossroads North Total	17,380	548	492	1,040	834	528	1,362
Meadowbrook Park							
Single-Family Detached Housing (ITE 210) – 70 Dwelling Units	662	13	39	52	44	25	69
Total Site Trip Generation	31,118	1,069	1,049	2,118	1,391	1,003	2,394

4.2 Trip Distribution

Distribution of site traffic on the street system was based on the area street system characteristics, existing traffic patterns, existing and anticipated surrounding demographic information, expected roadway improvements, and the proposed access system for the project. The directional distribution of traffic is a means to quantify the percentage of site-generated traffic that approaches the site from a given direction and departs the site back to the original source. The project trip distribution is illustrated for Meadowbrook Park in **Figure 7**, for Crossroads North in **Figure 8**, and for Crossroads Mix Use in **Figure 9**.





4.3 Traffic Assignment and Total (Background Plus Project) Traffic

Traffic assignment was obtained by applying the project trip distribution of each area to the estimated traffic generation of the associated development shown in the trip generation tables. Project traffic assignment for the Crossroads-Meadowbrook project during the peak hours studied is shown for Meadowbrook Park in **Figure 10**, for Crossroads North in **Figure 11**, and for Crossroads Mix Use in **Figure 12**. The total traffic assignment for all three development areas were summed together as shown in **Figure 13**. Project traffic volumes were added to the background volumes to represent estimated traffic conditions for the short term 2025 horizon and long term 2040 horizon. These background plus project (total) traffic volumes for the project are illustrated for the 2025 and 2040 horizon years in **Figures 14** and **15**, respectively.

Based on the Jan 14 meeting, the applicant stated Reagan Ranch TIS was accounted for in this study. As such, update the narrative to identify other studies/development that was incorporated in this study.

Provide trip distribution analysis for the proposed access to Crossroads Mixed Use and provide recommendations for the intersection configuration and auxiliary lanes.

State/list ECM criteria for stacking, storage, and taper for every affected auxiliary lane and access and state whether this access can be met. If it can't be met, state the required modification so it can be met (a deviation request may be required if an alternative to the criteria is proposed)




LEGEND

- Study Area Key Intersection
- XX% External Trip Distribution

CROSSROADS-MEADOWBROOK
 COLORADO SPRINGS, CO
 MEADOWBROOK PARK
 TRIP DISTRIBUTION

FIGURE 7






CROSSROADS-MEADOWBROOK
 COLORADO SPRINGS, CO
 CROSSROADS NORTH
 TRIP DISTRIBUTION

LEGEND

- Study Area Key Intersection
- XX% External Trip Distribution

FIGURE 8




CROSSROADS-MEADOWBROOK
 COLORADO SPRINGS, CO
 CROSSROADS MIX USE
 TRIP DISTRIBUTION

LEGEND

- Study Area Key Intersection
- XX% External Trip Distribution

FIGURE 9




LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume

CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 MEADOWBROOK PARK
 TRAFFIC ASSIGNMENT

FIGURE 10




LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume

CROSSROADS-MEADOWBROOK
 COLORADO SPRINGS, CO
 CROSSROADS NORTH
 TRAFFIC ASSIGNMENT

FIGURE 11




LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume


CROSSROADS-MEADOWBROOK
 COLORADO SPRINGS, CO
 CROSSROADS MIX USE
 PROJECT TRAFFIC ASSIGNMENT

FIGURE 12



CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 TOTAL PROJECT TRAFFIC ASSIGNMENT

FIGURE 13




LEGEND

- Study Area Key Intersection
- XXX(XXX) Weekday AM(PM) Peak Hour Traffic Volumes
- XX,X00 Estimated Daily Traffic Volume

CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2025 TOTAL TRAFFIC VOLUMES

FIGURE 14



CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2040 TOTAL TRAFFIC VOLUMES

FIGURE 15

5.0 TRAFFIC OPERATIONS ANALYSIS

Kimley-Horn’s analysis of traffic operations in the site vicinity was conducted to determine potential capacity deficiencies in the 2025 and 2040 development horizons at the identified key intersections. The acknowledged source for determining overall capacity is the *Highway Capacity Manual*².

5.1 Analysis Methodology

Capacity analysis results are listed in terms of Level of Service (LOS). LOS is a qualitative term describing operating conditions a driver will experience while traveling on a particular street or highway during a specific time interval. It ranges from A (very little delay) to F (long delays and congestion). For intersections and roadways in this study area, El Paso County recommends LOS D as the minimum threshold for acceptable operations. **Table 2** shows the definition of level of service for signalized and unsignalized intersections.

Table 2 – Level of Service Definitions

Level of Service	Signalized Intersection Average Total Delay (sec/veh)	Unsignalized Intersection Average Total Delay (sec/veh)
A	≤ 10	≤ 10
B	> 10 and ≤ 20	> 10 and ≤ 15
C	> 20 and ≤ 35	> 15 and ≤ 25
D	> 35 and ≤ 55	> 25 and ≤ 35
E	> 55 and ≤ 80	> 35 and ≤ 50
F	> 80	> 50

Definitions provided from the Highway Capacity Manual, Sixth Edition, Transportation Research Board, 2016.

Study area intersections were analyzed based on average total delay analysis for signalized and unsignalized intersections. Under the unsignalized analysis, the level of service (LOS) for a two-way stop-controlled intersection is determined by the computed or measured control delay and is defined for each minor movement. Level of service for a two-way stop-controlled intersection is not defined for the intersection as a whole. Level of service for a signalized and four-way stop controlled intersection is defined for each approach and for the intersection.

² Transportation Research Board, *Highway Capacity Manual*, Sixth Edition, Washington DC, 2016.

5.2 Key Intersection Operational Analysis

Calculations for the level of service at the key intersections identified for study are provided in **Appendix D**. The existing and background traffic analyses are based on the lane geometry and intersection control shown in **Figure 3**. The signalized intersection analysis utilizes the observed cycle lengths with existing phasing and timing. Based on increased national attention given to appropriate yellow and all-red clearance intervals to improve intersection safety, these have been calculated and are applied for the approaches to the signalized intersections. The increase in the yellow and all red time sacrifices intersection capacity for improved safety. Existing peak hour factors were used for the existing and 2025 background conditions. The standardized peak hour factor of 0.92 was used for 2025 background plus project and 2040 conditions due to the amount of additional project traffic on the street network. Synchro traffic analysis software was used to analyze the study area intersections and access drives for level of service. The Synchro Highway Capacity Manual (HCM) methodology reports were used to analyze intersection delay and level of service.

Meadowbrook Parkway and Marksheffel Road

Meadowbrook Parkway and Marksheffel Road is a four-leg signalized intersection. This intersection currently operates with LOS B during the morning and afternoon peak hours under the existing lane configuration and signal control. With or without the completion of the proposed developments, the intersection is anticipated to operate acceptably with LOS B during both the morning and afternoon peak hours throughout 2040. **Table 3** provides the results of the level of service at this intersection.

Table 3 – Meadowbrook Parkway and Marksheffel Road LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2020 Existing	10.8	B	12.1	B
2025 Background	11.5	B	12.8	B
2025 Background Plus Project	13.4	B	13.7	B
2040 Background	11.9	B	13.3	B
2040 Background Plus Project	14.8	B	15.6	B

Marksheffel Road and US-24

Marksheffel Road and US-24 is a four-leg signalized intersection. Although US-24 is east-west and Marksheffel Road is north-south, the traffic software at this intersection assigned US-24 as north-south. This intersection currently operates with a LOS D during the morning and afternoon peak hours under the existing lane configuration and signal control. With or without the completion of the proposed developments in 2025, the intersection is anticipated to operate acceptably with LOS D during both the morning and afternoon peak hours.

During the morning peak hour in 2040, the intersection may operate with a LOS E with the addition of development project traffic. If future traffic volumes are realized, it is recommended that the eastbound and westbound right turn lanes along US-24 be converted to a shared through/right turn lane. If this occurs, the existing free northbound and southbound right turn movements on the Marksheffel Road approaches will need to be converted to yield control. With these improvements, the intersection is expected to operate with LOS D during both peak hours in the 2040 total condition. **Table 4** provides the results of the level of service at this intersection.

Table 4 – Marksheffel Road and US-24 LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2020 Existing	37.3	D	39.5	D
2025 Background	39.5	D	39.7	D
2025 Background Plus Project	42.5	D	41.6	D
2040 Background	53.5	D	45.0	D
2040 Background Plus Project	61.2	E	51.8	D
2040 Background Plus Project #	43.8	D	43.5	D

Three Through Lanes along US-24 approaches by absorbing existing right turn lanes as through lanes

Newt Drive and Meadowbrook Parkway

The existing intersection of Newt Drive and Meadowbrook Parkway is a three-leg stop-controlled intersection with the east and west legs along Newt Drive providing stop control. This intersection currently operates with all movements at LOS B. In the 2025 background condition the movements at this intersection are anticipated to continue to operate at LOS B. With the completion of the proposed development and specifically the Crossroads Mix Use development area in 2025, a south leg of Meadowbrook Parkway will be constructed. Once this northbound leg is constructed the westbound approach is anticipated to operate at LOS F during both peak hours. Based on projected traffic volumes, it is recommended that a roundabout with single lane approaches eastbound, northbound and southbound and a shared left turn/through lane with separate right turn lane on westbound Newt Drive be constructed at this intersection in 2025. With the recommended improvements, it is anticipated that the intersection will operate acceptably throughout 2040, with or without the addition of project traffic, with LOS B or better. **Table 5** provides the results of the level of service at this intersection.

Table 5 – Newt Drive and Meadowbrook Parkway LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2020 Existing				
Eastbound Approach	12.5	B	13.7	B
Westbound Approach	12.1	B	13.7	B
2025 Background				
Eastbound Approach	13.3	B	14.6	B
Westbound Approach	12.5	B	14.7	B
2025 Background Plus Project				
Eastbound Approach	26.4	D	27.5	D
Westbound Approach	305.6	F	355.5	F
Northbound Left	0.0	A	0.0	A
Southbound Left	9.8	A	9.5	A
2025 Background Plus Project #	8.8	A	9.1	A
2040 Background #	4.1	A	4.4	A
2040 Background Plus Project #	9.5	A	10.0	B

Roundabout

SH-94 and US-24

SH-94 and US-24 is a four-leg signalized intersection. Although both highways are east-west, the traffic software at this intersection assigned US-24 as north-south. This intersection currently operates with LOS C during the morning and afternoon peak hours under the existing lane configuration and signal control. With the completion of the proposed development in 2025, the intersection is anticipated to operate poorly during the morning and afternoon peak hours with LOS F. If future project volumes are realized it is recommended that an additional through lane be considered as a regional improvement on the US-24 approaches. The US-24 right turn to eastbound SH-94 is recommended to include a separate right turn lane operating with free movements. The US-24 right turn lane for Newt Drive can be absolved as a shared through/right turn lane. A 150 second cycle length is also needed during the morning peak hour in order to improve operations. It is believed that with these improvements the intersection is at its ultimate configuration. With the ultimate configuration the intersection is anticipated to operate poorly during the morning peak hour during the 2040 buildout condition. **Table 6** provides the results of the level of service at this intersection.

Table 6 – SH-94 and US-24 LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2020 Existing	32.4	C	24.0	C
2025 Background	40.0	D	25.6	C
2025 Background Plus Project	172.1	F	93.0	F
2025 Background Plus Project #	67.1	E	43.0	D
2040 Background #	35.1	D	25.3	C
2040 Background Plus Project #	96.5	F	48.8	D

Three northbound through lanes, southbound right turn lane changed to a shared through/right turn lane, eastbound and westbound right turn lane changed from free to yield control. 150 second cycle length for morning peak hour.

SH-94 and Marksheffel Road

The existing intersection of SH-94 and Marksheffel Road is currently a four-leg signalized intersection. This intersection currently operates with LOS C during the morning and afternoon peaks hours with existing traffic volumes and lane configurations. With the completion of the proposed development in 2025 the southbound right turn at this intersection is anticipated to be a free southbound right turn due to CDOT State Highway Access Code guidelines. This intersection is anticipated to operate acceptable with LOS D or better during the 2025 buildout. By 2040 buildout, this intersection operates poorly with LOS E during the afternoon peak hour. For the intersection to operate acceptably during the 2040 buildout, it is recommended to construct dual eastbound left turn lanes with protected only. With this improvement, the intersection is anticipated to operate with LOS D or better in 2040 with project traffic. **Table 7** provides the results of the level of service at this intersection.

Table 7 – SH-94 and Marksheffel Road LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2020 Existing	24.2	C	28.3	C
2025 Background	24.3	C	27.5	C
2025 Background Plus Project #	25.3	C	43.7	D
2040 Background #	22.5	C	30.9	C
2040 Background Plus Project #	37.2	D	66.9	E
2040 Background Plus Project ##	33.5	C	50.7	D

Free southbound right turn

Dual eastbound left turn lanes (protected phasing)

Along with intersection operational analysis roadway link ADT's were analyzed to see if they meet the El Paso County TIS guidelines. It was found that all estimated roadway link ADT's meet the threshold capacities set forth in the El Paso County TIS guidelines with the exception of the segment of US-24 south of SH-94 during the 2040 buildout condition.

for clarity revise sentence. Specify the total proposed access for Mixed Use and Meadowbrook park separately.

5.3 Project Access Operational Analysis

With completion of the Crossroads-Meadowbrook project, the site proposes two project accesses along the west side of Marksheffel Road for the Crossroads North development area and four project accesses along the east side of Meadowbrook Parkway for Meadowbrook Park and Crossroads Mix Use. Both accesses along Marksheffel Road are proposed to be full movement signalized accesses. Three of the four accesses along Meadowbrook Parkway are

Since the TIS is provided for three separate projects, Staff is requesting you consider formatting the project in a way that organizes the analysis per project for ease in review. Right now the paragraphs are constantly moving from one area to another making it difficult to follow recommendations and analysis.

One recommendation using section 5.3 as an example is to provide a subsection for each project based on the individual project site.

STOP signs installed for the exiting approaches, except for the two accesses along Marksheffel Road which are recommended for signalization.

The north and south accesses along Marksheffel Road are proposed as full movement accesses. El Paso County uses the CDOT State Highway Access Code for determination of turn lanes. Based on this, a right turn lane is required for any access with a projected peak hour right ingress turning volume of 25 vehicles per hour or greater for principal arterials, therefore it is recommended that a southbound right turn lane be constructed at both intersections due to the volumes being 295 vehicles per hour at the north access and 170 vehicles per hour at the south access.

which project?

With the recommended lane configurations and two-way stop control, all movements at the project accesses are expected to operate acceptably with LOS D or better during the peak hours in the 2025 and 2040 horizons with exception of movements at both full movement accesses along Marksheffel Road. A four-hour vehicle volume signal warrant analysis was performed at both accesses along Marksheffel Road and the 2025 traffic volume projections do warrant signalization. Therefore, it is recommended that these intersections be signalized with development of Crossroads North. The signal warrant analysis is attached in **Appendix E**. With the signal improvements at both full movement accesses along Marksheffel Road the intersections operate acceptably with LOS B or better throughout the 2040 horizon. The operational analysis at the proposed project driveways is summarized in **Table 8** for the short-term 2025 horizon and for the long-term 2040 horizon. Detailed results of the operational analysis are also provided in **Appendix D**.

Table 8 – Project Access LOS Results

Access and Movement	2022 Total Traffic				2040 Total Traffic			
	AM Peak Hour		PM Peak Hour		AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
Marksheffel Road & North Full Access								
Eastbound Left	28.0	D	163.2	F	-	-	-	-
Eastbound Right	12.9	B	15.1	C	-	-	-	-
Northbound Left	11.6	B	15.8	C	-	-	-	-
Marksheffel Road & North Full Access #	4.6	A	5.6	A	4.3	A	5.4	A
Marksheffel Road & South Full Access								
Eastbound Left	24.2	C	48.1	E	-	-	-	-
Eastbound Right	19.2	C	27.4	D	-	-	-	-
Northbound Left	12.0	B	17.3	C	-	-	-	-
Marksheffel Road & South Full Access #	8.1	A	11.7	B	7.5	A	8.2	A
Meadowbrook Parkway & Full Access/Preble Dr								
Eastbound Approach	10.4	B	10.8	B	10.6	B	11.1	B
Westbound Approach	11.3	B	11.4	B	11.3	B	11.6	B
Northbound Left	7.9	A	8.0	A	8.0	A	8.2	A
Southbound Left	7.7	A	7.7	A	7.7	A	7.7	A

Signalized, free eastbound right turn

5.4 Sight Distance Evaluation

It is recommended that appropriate sight distance triangles be provided at all site access points to give drivers exiting the development areas a clear view of oncoming traffic. Landscaping and objects within sight triangles must not obstruct drivers' views of the adjacent travel lanes. Intersection sight distances for left turn from stop and right turn from stop were analyzed for the proposed project accesses along Marksheffel Road and Meadowbrook Parkway.

With AASHTO standards and a design speed of 55 miles per hour along Marksheffel Road, the intersection sight distance for a vehicle turning left from stop is 610 feet, while the sight distance for a vehicle turning right from stop is 530 feet. Therefore, all obstructions for left turning vehicles from stop should be clear to the right within the triangle created with a vertex point located 14.5 feet from the edge of the major road traveled way (typical position of the minor road driver's eye when stopped) and a line of sight distance of 555 feet located in the middle of the nearest lane opposite of the center median for both accesses along Marksheffel Road. Likewise, all obstructions for right turning vehicles from stop should be clear to the left within the

provide an exhibit showing the sight distance/line-of-sight for the proposed accesses to the mixed use.

traveled
for both

Along with the accesses along Marksheffel Road, the access along Meadowbrook Parkway was analyzed for sight distance requirements. With AASHTO standards and a design speed of 35 miles per hour along Meadowbrook Parkway, the intersection sight distance for a vehicle turning left from stop is 390 feet, while the sight distance for a vehicle turning right from stop is 335 feet. Therefore, all obstructions for left turning vehicles from stop should be clear to the right within the triangle created with a vertex point located 14.5 feet from the edge of the major road traveled way (typical position of the minor road driver's eye when stopped) and a line of sight distance of 445 feet located in the middle of the nearest lane opposite of the center median for the access along Meadowbrook Parkway. Likewise, all obstructions for right turning vehicles from stop should be clear to the left within the triangle created with a vertex point located 14.5 feet from the edge of the major road traveled way and a line of sight distance of 335 feet located in the middle of the nearest lane for the access along Meadowbrook Parkway.

5.5 Bicycle and Pedestrian Access

Bicycle and pedestrian access evaluations were conducted for the Crossroads-Meadowbrook project. This focused on the areas of Meadowbrook Parkway, Marksheffel Road, US-24, and SH-94 adjacent to the site development areas. The following provides a description of the assessment.

Adjacent to the site, Meadowbrook Parkway provides the only sidewalks within the project area along both sides of the street. Pedestrian access is good along Meadowbrook Parkway between Newt Drive and Marksheffel Road with wide sidewalks with minimal gaps and signalized crossings of Marksheffel Road, where a great level of service exists for pedestrians. To the east of Marksheffel Road, Meadowbrook Parkway leads into a neighborhood with no sidewalks on either side of the road. Although the only sidewalks that exist within the study area are on Meadowbrook Parkway there are very few destinations outside of the ones provided on Meadowbrook Parkway. The only new sidewalks shown on the site plan are along the east side of Meadowbrook Parkway at the Meadowbrook Park development.

Transit within the Colorado Springs area is provided by Mountain Metropolitan Transit. From review of the most recent route map from August 1, 2019 there are currently no transit routes that run through the site area.

5.6 CDOT Access Permit Analysis Need

The threshold for requiring an access permit along CDOT roadways occurs when project traffic is anticipated to increase the existing access traffic volumes by more than 20 percent. Based on traffic projections, the addition of project traffic at the SH-94 and US-24 intersection, along with the project traffic on the north leg of SH-94 and Marksheffel Road is anticipated to increase existing access traffic volumes by more than 20 percent during the peak hour; therefore, it is believed that access permits will be required by CDOT for these approaches in association with this project.

Since US-24 and SH-94 are state owned and maintained facilities, it is recommended that auxiliary turn lanes along US-24 and SH-94 be constructed in accordance with the current CDOT State Highway Access Code (SHAC). CDOT categorizes the segments of US-24 and SH-94 through the study area as E-X: Expressway, Major Bypass. According to the State Highway Access Code for category E-X roadways, the following thresholds apply:

- A left turn deceleration lane and taper with storage length is required for any access with a projected peak hour left ingress turning volume greater than 10 vehicles per hour (vph), a left turn lane with deceleration, storage, and transition taper lengths is required for any access.
- A right turn lane with deceleration and taper lengths is required for any access with a projected peak hour right ingress turning volume greater than 10 vph.
- A right turn lane with acceleration and taper lengths is required for any access with a project peak hour turning volume greater than 10 vph.

Based on traffic projections and the above thresholds, auxiliary turn lane requirements were calculated for SH-94/US-24 intersection and the north leg of the SH-94/Marksheffel Road intersection. SH-94 provides one lane of travel in each direction and has a posted speed limit of

40 miles per hour at US-24 and 55 miles per hour at Marksheffel Road. US-24 provides two lanes of travel in each direction and has a posted speed limit of 55 miles per hour within the study area. As such, turn lane requirements at the study area intersections along SH-94 and US-24 are as follows:

US-24 and SH-94

- A westbound left turn deceleration lane **is** warranted along the SH-94 approach to US-24 based on projected 2025 background plus project traffic being 735 westbound left turns during the peak hour and the threshold being 10 vph. Since SH-94 has a category of E-X the left turn lane requirement is deceleration, storage, and taper lengths. There are currently dual westbound left-turn lanes with an average length of 475 and the taper is approximately 300 feet. Based on the 40-mile per hour speed limit, the deceleration lane length is 370 feet plus a 145-foot taper. The storage requirement is 735 feet in two lanes, or 370 feet per lane. Therefore, the existing dual westbound left turn lanes are recommended to be lengthened to 740 feet with a 145 foot taper.
- A northeastbound left turn deceleration lane **is** warranted along US-24 approach to Newt Drive/SH-94 based on projected 2025 background plus project traffic being 515 left turns during the peak hour. Since US-24 has a category of E-X the left turn lane requirement is deceleration, storage, and taper lengths. Currently the northbound left-turn lane is approximately 900 feet long and the taper is approximately 150 feet. Based on the 55-mile per hour speed limit, the deceleration lane length is 600 feet, plus a 225-foot taper, and 515 feet of storage for a total length of 1,120 feet plus 225-foot taper. However, by 2025 it is recommended that dual northeastbound US-24 left turn lanes be designated at this intersection. Dividing the storage in half results in 860-foot plus 225-foot taper northeastbound dual left turn lanes.
- A northbound right turn deceleration lane **is** warranted based on projected 2025 background plus project traffic being 530 northbound right turns during the peak hour and the threshold being 10 vph. Since US-24 has a category of E-X the right turn lane requirement is deceleration, and taper lengths. The northbound right turn lane is currently 600 feet with a 225-foot taper, which meets CDOT SHAC standards based on the 55-mile per hour speed limit. Therefore, no turn lane modifications would be

recommended for the northbound right turn lane at this intersection of SH-94 and US-24, but this northeastbound US-24 right turn lane should be maintained and constructed if and when US-24 is converted to three through lanes.

- An eastbound right turn acceleration lane along SH-94 from the northeastbound US-24 right turn **is** warranted based on projected 2025 background plus project traffic being 530 northbound right turns during the peak hour and the threshold being 10 vph. Since US-24 has a category of E-X the right turn lane requirement is acceleration, and taper lengths. The right turn lane currently has a 425-foot acceleration lane with a 350-foot taper. Based on the 40-mile per hour speed limit, the acceleration lane length is 380 feet plus a 145-foot taper. Therefore, the existing northbound right turn acceleration lane meets current CDOT SHAC requirements and no turn lane modifications are anticipated to be needed for this acceleration lane.
- A southwestbound US-24 left turn deceleration lane **is not** warranted based on projected 2040 background plus project traffic being 5 southbound left turns during the peak hour and the threshold being 10 vph.
- A southwestbound US-24 right turn deceleration lane **is** warranted based on projected 2025 background plus project traffic being 65 southbound right turns during the peak hour and the threshold being 10 vph. Since US-24 has a category of E-X the right turn lane requirement is deceleration, and taper lengths. The southbound right turn lane is currently 800 feet long with a 200-foot taper. Based on the 55-mile per hour speed limit, the deceleration lane length is 600 feet plus a 225-foot taper. Therefore, the existing southbound right turn lane meets current CDOT SHAC requirements. Of note, by 2025 this southbound right turn lane may need to be absorbed by the construction of a third southbound through lane.
- A southwestbound right turn acceleration lane along US-24 from the Newt Drive right turn **is** warranted based on projected 2025 background plus project traffic being 560 eastbound right turns during the peak hour and the threshold being 10 vph. Since US-24 has a category of E-X and a speed limit of 55 mph the right turn lane requirement is acceleration, and taper lengths. This acceleration lane exists today for a length of 760

feet plus 225-foot taper, which meets current CDOT SHAC requirements. Therefore, no turn lane modifications are recommended for this acceleration lane along southwestbound US-24.

SH-94 and Marksheffel Road

- An eastbound left turn deceleration lane **is** warranted based on projected 2025 background plus project traffic being 250 eastbound left turns during the peak hour and the threshold being 10 vph. Since SH-94 has a category of E-X the left turn lane requirement is deceleration, storage, and taper lengths. Currently the eastbound left-turn lane is approximately 300 feet long and the taper is approximately 125 feet. Based on the 55-mile per hour speed limit, the deceleration lane length is 600 feet, plus a 225-foot taper. It is recommended that this lane be constructed to 850 feet with a 225 foot taper by 2025.
- A westbound right turn deceleration lane **is** warranted based on projected 2025 background plus project traffic being 450 westbound right turns during the peak hour and the threshold being 10 vph. Since SH-94 has a category of E-X the right turn lane requirement is deceleration and taper lengths. The westbound right turn lane is currently 250 feet with a 250-foot taper. Based on the 55-mile per hour speed limit, the deceleration lane length is 600 feet plus a 225-foot taper. Therefore, the existing westbound right turn lane does not meet current CDOT SHAC requirements. It is recommended that this lane be constructed to 600 feet with a 225-foot taper by 2025.
- A westbound acceleration lane along SH-94 from the Marksheffel Road southbound right turn **is** warranted based on projected 2025 background plus project traffic being 450 westbound right turns during the peak hour and the threshold being 10 vph. Since SH-94 has a category of E-X the right turn lane requirement is acceleration, and taper lengths. The right turn lane currently has no acceleration lane. Based on the 50-mile per hour speed limit, a 760-foot acceleration lane with a 225-foot taper is recommended. It is recommended that this acceleration lane be a continuous lane to tie into the outside westbound through lane on the approach to US-24.

5.7 Queuing Analysis

A vehicle queuing analysis was conducted for the study area intersections. The queuing analysis was performed using Synchro presenting the results of the 95th percentile queue lengths. Results are shown in the following **Table 9** with calculations provided within the level of service operational sheets of **Appendix D** for the unsignalized intersections and **Appendix F** for signalized intersections.

Table 9 – Turn Lane Storage Length Analysis Results

Intersection Turn Lane	Existing Turn Lane Length (feet)	2025 Total Queue Length (feet)	2025 Recommended Turn Lane Length (feet)	2040 Total Queue Length (feet)	2040 Recommended Turn Lane Length (feet)
Meadowbrook Pkwy & Marksheffel Rd					
Eastbound Left	200' DL	135' DL	200' DL	155' DL	200' DL
Eastbound Right	150'	10'	150'	22'	150'
Westbound Left	250'	52'	250'	63'	250'
Westbound Right	200'	0'	200'	4'	200'
Northbound Left	425'	23'	425'	19'	425'
Southbound Left	350'	33'	350'	66'	350'
Southbound Right	350'	29'	350'	30'	350'
Marksheffel Rd & US-24					
Marksheffel Eastbound Left	375'	31'	375'	34'	375'
Marksheffel Westbound Left	300'	16'	300'	27'	300'
Marksheffel Westbound Right	375'	0'	375'	0'	375'
US-24 Northbound Left	1000' DL	206' DL	1000' DL	277' DL	1000' DL
US-24 Northbound Right	575'	0'	575'	0' #	C #
US-24 Southbound Left	1000'	347'	1000'	406'	1000'
US-24 Southbound Right	700'	0'	700'	0' #	C #
US-24 & SH-94					
SH-94 Eastbound Left	375' DL	52' DL	375' DL	51' DL	375' DL
SH-94 Westbound Left	475' DL	578' DL	740' (CDOT) DL	683' DL	740' (CDOT) DL
SH-94 Westbound Right	475'	0'	475'	0'	475'
US-24 Northbound Left	900'	383' DL	860' (CDOT) DL	454' DL	860' (CDOT) DL
US-24 Northbound Right	600'	0'	600'	0'	600'
US-24 Southbound Left	800'	10'	800'	15'	800'
US-24 Southbound Right	800'	0' #	C #	0' #	C #
SH-94 & Marksheffel Rd					
Eastbound Left	300'	402'	850' (CDOT)	203' DL	850' CDOT DL
Eastbound Right	250'	21'	250'	34'	250'
Westbound Left	225'	50'	225'	70'	225'
Westbound Right	250'	257'	600' (CDOT)	555'	600' (CDOT)
Northbound Left	375'	95'	375'	95'	375'
Northbound Right	400'	0'	400'	0'	400'
Southbound Left	400'	325'	400'	372'	400'
Southbound Right	400'	0'	C	52'	C


Intersection Turn Lane	Existing Turn Lane Length (feet)	2025 Total Queue Length (feet)	2025 Recommended Turn Lane Length (feet)	2040 Total Queue Length (feet)	2040 Recommended Turn Lane Length (feet)
Marksheffel Rd & North Full Access ^					
Eastbound Left	DNE	88'	C	88'	C
Eastbound Right	DNE	57'	C	57'	C
Northbound Left	TWLTL	133'	TWLTL	98'	TWLTL
Southbound Right	DNE	45'	235'	60'	235'
Marksheffel Rd & South Full Access ^					
Eastbound Left	DNE	83'	C	84'	C
Eastbound Right	DNE	89'	C	138'	C
Northbound Left	250'	76'	250'	92'	250'
Southbound Right	DNE	4'	235'	11'	235'
Meadowbrook Pkwy & Full Access/Preble Dr					
Westbound Approach	C	25'	C	25'	C
Eastbound Approach	DNE	25'	C	25'	C
Northbound Left	TWLTL	25'	TWLTL	25'	TWLTL
Southbound Left	TWLTL	25'	TWLTL	25'	TWLTL

^ = Signalized, # = Through/Right Turn Lane, DL = Dual Turn Lanes, TWLTL = Two-Way Left Turn Lane, * = Maximum Length, DNE = Does Not Exist, C = Continuous

If future traffic volumes are realized by 2025, the following turn lanes need to be lengthened to accommodate the queues; the westbound left turn lanes at the intersection of US-24 and SH-94 needs to be lengthened to 740 feet with a 145 foot taper, and the eastbound left turn and westbound right turn lane at the intersection of SH-94 and Marksheffel Road need to be lengthened to 850 feet with a 225 foot taper and 600 feet with a 225 foot taper, respectively per CDOT SHAC requirements.

5.8 Intersection Improvement Summary


Based on the results of the level of service operational and turn lane analysis for Crossroads-Meadowbrook, the recommended lane configurations and control of the study area intersections for the 2025 short term build out horizon as well as the 2040 long-term twenty-year horizon are shown in **Figures 16** and **17**, respectively. Likewise, a recommended improvements summary table is provided in **Table 10**. The recommended improvements for nonregional commitments identified in the table shows all geometry, control, and storage lane improvements along with the project participation percentage and development area associated with that recommended improvement.



CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2025 RECOMMENDED
 LANE CONFIGURATIONS AND CONTROL

LEGEND	
	Study Area Key Intersection
	Signalized Intersection
	Stop Controlled Approach
	Improvement
	100' Turn Lane Length (feet)

FIGURE 16



CROSSROADS—MEADOWBROOK
 COLORADO SPRINGS, CO
 2040 RECOMMENDED
 LANE CONFIGURATIONS AND CONTROL

LEGEND

- Study Area Key Intersection
- ⋮ Signalized Intersection
- STOP Stop Controlled Approach
- Improvement
- ↪ 100' Turn Lane Length (feet)

FIGURE 17

Table 10 – Crossroads – Meadowbrook Intersection Improvement Summary

Intersection	Improvements	Project Participation Percentage	Associated Development Area
Newt Drive and Meadowbrook Parkway	Roundabout Control	PM Peak $\frac{1022}{1470}$ 69.5%	Crossroads Mix Use
SH-94 and US-24	Restripe and extend 900-foot northeastbound dual left turn lanes along US-24 to 860-feet with 225-foot taper	PM Peak $\frac{362}{520}$ 69.6%	Crossroads Mix Use
	Extend the 475-foot westbound dual left turn lanes along SH-94 to 740 feet with a 145-foot taper	AM Peak $\frac{320}{735}$ 43.5%	Crossroads North
SH-94 and Marksheffel Road	Extend the 300-foot eastbound left turn lane to 850 feet with a 225-foot taper	PM Peak $\frac{250}{250}$ 100%	Crossroads North
	Extend the 250-foot westbound right turn lane to 600 feet with a 225-foot taper	PM Peak $\frac{83}{450}$ 18.4%	Crossroads North
	Construct acceleration lane along westbound SH-94 from southbound right turn at Marksheffel Road (free rights)	PM Peak $\frac{343}{355}$ 96.6%	Crossroads North
Marksheffel Road and North Full Access	Signalized control	100%	Crossroads North
Marksheffel Road and South Full Access	Signalized control	100%	Crossroads North
Meadowbrook Parkway	Three-lane roadway west of Newt Drive	100%	Crossroads Mix Use

6.0 CONCLUSIONS AND RECOMMENDATIONS

Based on the analysis presented in this report, Kimley-Horn believes the proposed Crossroads-Meadowbrook project areas will be successfully incorporated into the existing and future roadway network. The proposed project development and expected traffic volumes resulted in the following recommendations/conclusions:

2025 Recommendations:

- A CDOT Access Permit will be required for the Newt Drive north leg of the US-24 intersection in association with the Crossroads Mix Use development. Likewise, CDOT Access Permits will be required for the south leg of SH-94 at US-24 and north leg of Marksheffel Road at SH-94 in association with the Crossroads North development.
- It is recommended that a single lane roundabout be constructed at the Meadowbrook Parkway and New Drive intersection with development of the Crossroads Mix Use project. It is recommended that the roundabout have single lane approaches on the eastbound Newt Drive, northbound Meadowbrook Parkway, and southbound Meadowbrook Parkway approaches and a two-lane approach on westbound Newt Drive with a shared left turn/through lane into the roundabout and a separate right turn lane.
- The intersection of SH-94 and US-24 is projected to operate poorly in 2025 with the existing intersection configuration. Therefore, US-24 may need to provide three through lanes in each direction through this intersection in the near-term horizon. The additional through lanes are a regional capacity improvement that should be considered by CDOT and El Paso County in the near future. If and when US-24 is improved to provide three through lanes in each direction, it is recommended that a separate 600-foot plus 225-foot taper right turn lane be constructed to maintain free right turn movements to eastbound SH-94. The third southwestbound through lane along US-24 can be designated by absorbing the existing right turn lane. The six-lane section of US-24 can occur between the Peterson Road interchange to the west and transition back to a four-lane roadway east of SH-94. In addition to these regional improvements, it is recommended that the existing single 900-foot left turn lane be changed to 860-feet plus 225-foot taper with dual left turn lanes on the northeastbound US-24 approach for the

left turn to Newt Drive. The area for these dual lefts is presently mostly available; however, the lane is striped out which will require restriping and a slight extension may also need to be constructed. A traffic signal modification will be required at the intersection to incorporate these improvements.

- Traffic signals are anticipated to be needed and warranted at both full movement access intersections along Marksheffel Road for Crossroads North. Therefore, traffic signals are recommended for installation at these intersections with development of Crossroads North. It is recommended that a 235-foot with 200-foot taper (based on El Paso County standards for 50 mph) southbound right turn lane be constructed at both access intersections along Marksheffel Road due to the volume of traffic entering Crossroads North at this access. Likewise, separate eastbound left turn and right turn lanes are recommended to serve exiting traffic out of Crossroads North.
- All project access driveways for Meadowbrook Park and Crossroads Mix Use are recommended to be two-way stop-controlled with R1-1 “STOP” signs installed for the exiting approaches.
- From the CDOT SHAC analysis it was found that a westbound acceleration lane is needed from the southbound right turn at the intersection of SH-94 and Marksheffel Road in association with the Crossroads North project. It is recommended that the acceleration lane be constructed as a continuous lane to tie into the outside through lane on the westbound approach to US-24.
- It is recommended that the following turn lanes be lengthened to CDOT standards and accommodate future projected queue lengths; the 475-foot westbound SH-94 dual left turn lanes at the intersection of US-24 and SH-94 need to be lengthened to 740 feet with a 145 foot taper (in association with Crossroads North), and the 300-foot eastbound left turn lane and the 250-foot westbound right turn lane at the intersection of SH-94 and Marksheffel Road need to be lengthened to 850 feet with a 225 foot taper and 600 feet with a 225 foot taper, respectively (in association with Crossroads North).

- Meadowbrook Parkway will be extended along Crossroads Mix Use development project area in association with that project. It is recommended that this roadway be designated as a three-lane roadway with a center two-way left turn lane.

2040 Recommendations:

- If future traffic volume projections are realized, US-24 may need to provide three through lanes in each direction through the Marksheffel Road intersection. If and when this occurs, it is believed that the existing separate eastbound and westbound US-24 right turn lanes could be converted to shared through/right turn lanes.
- At the SH-94 and Marksheffel Road intersection, dual eastbound left turn lanes operating with protected only phasing may be needed to provide acceptable operations.

General Recommendations:

- Any on-site and off-site roadway, signing, striping, and signal improvements should be incorporated into the Civil Drawings, and conform to El Paso County and/or CDOT standards as applicable, as well as the Manual on Uniform Traffic Control Devices – 2009 Edition (MUTCD).


APPENDICES

APPENDIX A


Intersection Count Sheets



Marksheffel Rd SH 94



Date: Tue, Jun 02, 2020
Count Period: 7:00 AM to 9:00 AM
Peak Hour: 7:00 AM to 8:00 AM



Two-Hour Count Summaries


Interval Start	SH 94				SH 94				Marksheffel Rd				Marksheffel Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	0	57	8	0	2	73	22	0	11	71	7	0	79	110	0	440	0
7:15 AM	0	0	79	16	0	7	87	21	0	10	51	3	0	74	143	1	492	0
7:30 AM	0	0	61	21	0	8	69	13	0	24	76	4	0	67	133	1	477	0
7:45 AM	0	0	57	9	0	11	68	21	0	9	72	4	0	36	115	1	403	1,812
8:00 AM	0	4	39	14	0	2	43	12	0	10	50	2	0	47	115	1	339	1,711
8:15 AM	0	0	61	11	0	2	49	21	0	8	59	2	0	32	89	0	334	1,553
8:30 AM	0	1	50	15	0	6	67	25	0	9	52	4	0	32	85	1	347	1,423
8:45 AM	0	0	36	14	0	4	44	17	0	14	49	1	0	21	85	2	287	1,307
Count Total	0	5	440	108	0	42	500	152	0	95	480	27	0	388	875	7	3,119	0
Peak Hour	0	0	254	54	0	28	297	77	0	54	270	18	0	256	501	3	1,812	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	4	2	5	5	16	0	0	0	0	0	0	0	0	0	0
7:15 AM	6	4	4	4	18	0	0	0	0	0	0	0	0	0	0
7:30 AM	9	6	4	8	27	0	0	0	0	0	0	0	0	0	0
7:45 AM	6	10	3	3	22	0	0	0	0	0	0	0	0	0	0
8:00 AM	3	7	2	9	21	0	0	0	0	0	0	0	0	0	0
8:15 AM	10	5	2	4	21	0	0	0	0	0	0	0	0	0	0
8:30 AM	8	5	8	7	28	0	0	0	0	0	0	0	0	0	0
8:45 AM	8	6	1	5	20	0	0	0	0	0	0	0	0	0	0
Count Total	54	45	29	45	173	0	0	0	0	0	0	0	0	0	0
Peak Hour	25	22	16	20	83	0	0	0	0	0	0	0	0	0	0




Marksheffel Rd SH 94



Date: Tue, Jun 02, 2020
 Count Period: 4:00 PM to 6:00 PM
 Peak Hour: 4:00 PM to 5:00 PM

	HV %:	PHF
EB	3.3%	0.79
WB	2.7%	0.84
NB	2.3%	0.92
SB	3.9%	0.97
TOTAL	3.0%	0.94



Two-Hour Count Summaries


Interval Start	SH 94 Eastbound				SH 94 Westbound				Marksheffel Rd Northbound				Marksheffel Rd Southbound				15-min Total	Rolling One Hour
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
	4:00 PM	0	0	58	27	0	7	63	49	0	14	140	2	0	24	94		
4:15 PM	0	0	57	15	0	10	65	78	1	10	142	6	0	28	102	1	515	0
4:30 PM	0	0	42	13	0	6	47	62	0	12	159	2	0	25	105	1	474	0
4:45 PM	0	0	47	10	0	4	72	49	0	17	128	6	0	33	97	2	465	1,933
5:00 PM	1	1	72	14	0	5	52	48	0	8	107	2	0	20	84	2	416	1,870
5:15 PM	1	0	73	13	0	5	37	44	0	18	112	3	0	29	110	0	445	1,800
5:30 PM	0	0	69	19	0	1	40	31	0	12	75	3	0	28	115	0	393	1,719
5:45 PM	0	0	47	21	0	0	32	31	0	7	122	2	0	28	110	0	400	1,654
Count Total	2	1	465	132	0	38	408	392	1	98	985	26	0	215	817	7	3,587	0
Peak Hour	0	0	204	65	0	27	247	238	1	53	569	16	0	110	398	5	1,933	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
4:00 PM	1	5	4	7	17	0	0	0	0	0	0	0	0	0	0
4:15 PM	2	3	4	4	13	0	0	0	0	0	0	0	0	0	0
4:30 PM	2	4	5	8	19	0	0	0	0	0	0	0	0	0	0
4:45 PM	4	2	2	1	9	0	0	0	0	0	0	0	0	0	0
5:00 PM	1	2	2	4	9	0	0	0	0	0	0	0	0	0	0
5:15 PM	2	1	3	2	8	0	0	1	0	1	0	0	0	0	0
5:30 PM	3	0	2	1	6	0	0	0	0	0	0	0	0	0	0
5:45 PM	1	1	3	4	9	0	0	0	0	0	0	0	0	0	0
Count Total	16	18	25	31	90	0	0	1	0	1	0	0	0	0	0
Peak Hour	9	14	15	20	58	0	0	0	0	0	0	0	0	0	0



**US 24
SH 94**



Date: Tue, Jun 02, 2020
Count Period: 7:00 AM to 9:00 AM
Peak Hour: 7:00 AM to 8:00 AM



Two-Hour Count Summaries


Interval Start	SH 94				SH 94				US 24				US 24				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	1	6	45	0	81	10	0	0	27	147	65	0	1	319	7	709	0
7:15 AM	0	6	7	21	0	90	10	1	0	25	145	79	0	0	336	8	728	0
7:30 AM	0	5	6	47	0	85	5	0	0	20	152	80	0	0	310	6	716	0
7:45 AM	0	0	2	32	0	70	4	0	1	35	147	57	0	2	320	6	676	2,829
8:00 AM	0	4	4	25	0	51	7	1	0	28	120	54	0	3	230	5	532	2,652
8:15 AM	0	4	4	34	0	51	6	0	1	17	107	64	0	1	207	10	506	2,430
8:30 AM	0	1	4	26	0	66	2	0	0	25	128	55	0	0	223	4	534	2,248
8:45 AM	0	3	7	29	0	48	6	1	1	23	131	44	0	1	197	9	500	2,072
Count Total	0	24	40	259	0	542	50	3	3	200	1,077	498	0	8	2,142	55	4,901	0
Peak Hour	0	12	21	145	0	326	29	1	1	107	591	281	0	3	1,285	27	2,829	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	4	1	19	20	44	0	0	0	0	0	0	0	0	0	0
7:15 AM	0	5	27	16	48	0	0	0	0	0	0	0	0	0	0
7:30 AM	4	3	31	15	53	0	0	0	0	0	0	0	0	0	0
7:45 AM	1	5	25	21	52	0	0	0	0	0	0	0	0	0	0
8:00 AM	1	8	20	15	44	0	0	0	0	0	0	0	0	0	0
8:15 AM	3	2	24	9	38	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	7	27	13	47	0	0	0	0	0	0	0	0	0	0
8:45 AM	2	5	15	18	40	0	0	0	0	0	0	0	0	0	0
Count Total	15	36	188	127	366	0	0	0	0	0	0	0	0	0	0
Peak Hour	9	14	102	72	197	0	0	0	0	0	0	0	0	0	0



**US 24
SH 94**



Date: Tue, Jun 02, 2020
Count Period: 4:00 PM to 6:00 PM
Peak Hour: 4:15 PM to 5:15 PM



Two-Hour Count Summaries


Interval Start	SH 94				SH 94				US 24				US 24				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
4:00 PM	0	5	4	32	0	73	7	0	1	31	284	80	1	2	177	7	704	0
4:15 PM	0	5	4	45	0	51	2	2	1	30	327	62	0	3	153	7	692	0
4:30 PM	0	4	13	33	0	66	7	0	1	29	300	46	0	0	194	7	700	0
4:45 PM	0	9	1	40	0	83	5	1	0	31	307	53	0	0	158	7	695	2,791
5:00 PM	2	3	11	58	0	59	3	2	1	27	316	76	0	0	186	6	750	2,837
5:15 PM	0	8	7	36	0	49	8	0	0	19	299	80	0	0	170	8	684	2,829
5:30 PM	0	5	4	29	0	44	7	1	0	19	267	85	0	0	183	4	648	2,777
5:45 PM	0	3	8	24	0	38	4	1	0	12	252	62	0	0	142	10	556	2,638
Count Total	2	42	52	297	0	463	43	7	4	198	2,352	544	1	5	1,363	56	5,429	0
Peak Hour	2	21	29	176	0	259	17	5	3	117	1,250	237	0	3	691	27	2,837	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
4:00 PM	0	4	16	12	32	0	0	0	0	0	0	0	0	0	0
4:15 PM	0	3	11	12	26	0	0	0	0	0	0	0	0	0	0
4:30 PM	1	1	20	12	34	0	0	0	0	0	0	0	0	0	0
4:45 PM	1	1	14	5	21	0	0	0	0	0	0	0	0	0	0
5:00 PM	0	3	4	7	14	0	0	0	0	0	0	0	0	0	0
5:15 PM	1	2	10	6	19	0	0	0	0	0	0	0	0	0	0
5:30 PM	2	1	7	11	21	0	0	0	0	0	0	0	0	0	0
5:45 PM	1	2	3	7	13	0	0	0	0	0	0	0	0	0	0
Count Total	6	17	85	72	180	0	0	0	0	0	0	0	0	0	0
Peak Hour	2	8	49	36	95	0	0	0	0	0	0	0	0	0	0



Meadowbrook Parkway Newt Dr



Date: Tue, Jun 02, 2020
Count Period: 4:00 PM to 6:00 PM
Peak Hour: 4:30 PM to 5:30 PM



Two-Hour Count Summaries


Interval Start	Newt Dr				Newt Dr				Meadowbrook Parkway				Meadowbrook Parkway				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
4:00 PM	0	2	2	0	4	0	6	26	0	0	0	0	0	38	0	0	78	0
4:15 PM	0	2	3	0	4	0	6	15	0	0	0	0	0	44	0	1	75	0
4:30 PM	0	2	6	0	2	0	3	23	0	0	0	0	0	42	0	4	82	0
4:45 PM	0	1	8	0	2	0	7	21	0	0	0	0	0	41	0	0	80	315
5:00 PM	0	2	3	0	4	0	12	9	0	0	0	0	0	70	0	1	101	338
5:15 PM	0	3	7	0	2	0	4	17	0	0	0	0	0	42	0	2	77	340
5:30 PM	0	0	4	0	6	0	4	8	0	0	0	0	0	27	0	0	49	307
5:45 PM	0	1	4	0	2	0	6	7	0	0	0	0	0	29	0	1	50	277
Count Total	0	13	37	0	26	0	48	126	0	0	0	0	0	333	0	9	592	0
Peak Hour	0	8	24	0	10	0	26	70	0	0	0	0	0	195	0	7	340	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:30 PM	0	4	0	1	5	0	0	0	0	0	0	0	0	0	0
4:45 PM	0	1	0	1	2	0	0	0	0	0	0	0	0	0	0
5:00 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
5:15 PM	2	2	0	1	5	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	1	0	1	2	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	1	0	1	2	0	0	0	0	0	0	0	0	0	0
Count Total	2	10	0	5	17	0	0	0	0	0	0	0	0	0	0
Peak Hour	2	8	0	3	13	0	0	0	0	0	0	0	0	0	0



US 24 Marksheffel Rd



Date: Thu, Jun 04, 2020
Count Period: 7:00 AM to 9:00 AM
Peak Hour: 7:00 AM to 8:00 AM



	HV %:	PHF
EB	5.5%	0.93
WB	3.2%	0.91
NB	10.5%	0.93
SB	3.9%	0.94
TOTAL	5.7%	0.96

Two-Hour Count Summaries


Interval Start	Marksheffel Rd Eastbound				Marksheffel Rd Westbound				US 24 Northbound				US 24 Southbound				15-min Total	Rolling One Hour
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
	7:00 AM	0	0	122	138	0	0	94	6	0	68	96	0	0	50	203		
7:15 AM	0	0	155	127	0	0	96	8	1	59	96	0	0	43	213	3	801	0
7:30 AM	0	3	123	142	0	1	80	14	0	62	78	0	0	59	214	5	781	0
7:45 AM	0	4	124	115	0	0	66	12	0	59	90	0	0	57	190	4	721	3,081
8:00 AM	0	8	106	109	0	2	57	17	0	50	75	0	0	37	125	7	593	2,896
8:15 AM	0	1	87	90	0	0	48	16	0	50	73	1	0	42	138	1	547	2,642
8:30 AM	0	3	83	105	0	1	84	13	0	48	71	0	0	30	155	1	594	2,455
8:45 AM	0	0	92	85	0	2	58	8	0	52	91	0	0	39	162	5	594	2,328
Count Total	0	19	892	911	0	6	583	94	1	448	670	1	0	357	1,400	27	5,409	0
Peak Hour	0	7	524	522	0	1	336	40	1	248	360	0	0	209	820	13	3,081	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	18	3	10	8	39	0	0	0	0	0	0	0	0	0	0
7:15 AM	12	3	17	10	42	0	0	0	0	0	0	0	0	0	0
7:30 AM	14	4	21	13	52	0	0	0	0	0	0	0	0	0	0
7:45 AM	14	2	16	10	42	0	0	0	0	0	0	0	0	0	0
8:00 AM	9	3	18	11	41	0	0	0	0	0	0	0	0	0	0
8:15 AM	9	1	12	7	29	0	0	0	0	0	0	0	0	0	0
8:30 AM	9	2	10	9	30	0	0	0	0	0	0	0	0	0	0
8:45 AM	11	4	22	21	58	0	0	0	0	0	0	0	0	0	0
Count Total	96	22	126	89	333	0	0	0	0	0	0	0	0	0	0
Peak Hour	58	12	64	41	175	0	0	0	0	0	0	0	0	0	0



US 24 Marksheffel Rd



Date: Thu, Jun 04, 2020
Count Period: 4:00 PM to 6:00 PM
Peak Hour: 4:30 PM to 5:30 PM



	HV %:	PHF
EB	2.8%	0.90
WB	1.3%	0.92
NB	1.7%	0.97
SB	2.8%	0.91
TOTAL	2.1%	0.98

Two-Hour Count Summaries


Interval Start	Marksheffel Rd Eastbound				Marksheffel Rd Westbound				US 24 Northbound				US 24 Southbound				15-min Total	Rolling One Hour
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
	4:00 PM	0	2	102	84	0	3	163	33	0	78	159	0	1	21	132		
4:15 PM	0	7	82	73	0	1	172	39	2	131	166	1	0	32	121	4	831	0
4:30 PM	0	4	92	73	0	4	165	37	0	119	207	0	0	23	100	2	826	0
4:45 PM	0	5	117	92	0	1	162	34	0	128	185	4	0	17	90	5	840	3,275
5:00 PM	0	3	96	92	0	2	140	34	1	96	210	1	0	27	101	1	804	3,301
5:15 PM	0	0	105	93	0	2	148	27	0	118	213	0	0	37	98	3	844	3,314
5:30 PM	0	3	111	87	0	1	115	29	0	108	178	1	0	15	109	2	759	3,247
5:45 PM	0	3	78	62	0	6	110	20	0	96	122	0	0	24	91	1	613	3,020
Count Total	0	27	783	656	0	20	1,175	253	3	874	1,440	7	1	196	842	18	6,295	0
Peak Hour	0	12	410	350	0	9	615	132	1	461	815	5	0	104	389	11	3,314	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
4:00 PM	12	3	7	8	30	0	0	0	0	0	0	0	0	0	0
4:15 PM	6	2	10	5	23	0	0	0	0	0	0	0	0	0	0
4:30 PM	4	4	6	6	20	0	0	0	1	1	0	0	0	0	0
4:45 PM	6	2	6	1	15	0	0	0	0	0	0	0	0	0	0
5:00 PM	7	2	6	3	18	0	0	0	0	0	0	0	0	0	0
5:15 PM	5	2	4	4	15	0	0	0	1	1	0	0	0	0	0
5:30 PM	6	0	5	5	16	0	0	0	0	0	0	0	0	0	0
5:45 PM	2	2	3	2	9	0	0	0	1	1	0	0	0	0	0
Count Total	48	17	47	34	146	0	0	0	3	3	0	0	0	0	0
Peak Hour	22	10	22	14	68	0	0	0	2	2	0	0	0	0	0



Marksheffel Rd Meadowbrook Parkway



Date: Thu, Jun 04, 2020
Count Period: 7:00 AM to 9:00 AM
Peak Hour: 7:00 AM to 8:00 AM




	HV %:	PHF
EB	10.2%	0.82
WB	0.0%	0.79
NB	6.7%	0.87
SB	5.7%	0.92
TOTAL	6.1%	0.96

Two-Hour Count Summaries

Interval Start	Meadowbrook Parkway				Meadowbrook Parkway				Marksheffel Rd				Marksheffel Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	12	2	7	0	11	3	5	0	3	167	2	0	0	268	24	504	0
7:15 AM	0	24	1	5	0	5	3	2	0	4	144	4	0	0	256	26	474	0
7:30 AM	0	18	1	5	0	5	4	6	0	8	130	3	0	3	276	38	497	0
7:45 AM	0	24	0	9	0	6	4	6	0	5	128	3	0	3	229	38	455	1,930
8:00 AM	0	25	2	9	0	3	4	6	0	9	100	7	0	5	219	24	413	1,839
8:15 AM	0	21	1	3	0	4	2	8	0	2	98	3	1	3	159	25	330	1,695
8:30 AM	0	7	2	4	0	8	4	5	0	4	127	5	0	2	200	27	395	1,593
8:45 AM	0	24	1	4	0	11	2	6	0	4	103	4	0	2	158	30	349	1,487
Count Total	0	155	10	46	0	53	26	44	0	39	997	31	1	18	1,765	232	3,417	0
Peak Hour	0	78	4	26	0	27	14	19	0	20	569	12	0	6	1,029	126	1,930	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	2	0	8	21	31	0	0	0	0	0	0	0	0	0	0
7:15 AM	3	0	9	14	26	0	0	0	0	0	0	0	0	0	0
7:30 AM	4	0	10	16	30	1	0	0	0	1	0	0	0	0	0
7:45 AM	2	0	13	15	30	0	0	0	0	0	0	0	0	0	0
8:00 AM	3	0	12	10	25	0	0	0	0	0	0	0	0	0	0
8:15 AM	4	0	4	12	20	0	0	0	0	0	0	0	1	0	1
8:30 AM	2	0	6	7	15	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	1	9	12	22	0	0	0	0	0	0	0	0	0	0
Count Total	20	1	71	107	199	1	0	0	0	1	0	0	1	0	1
Peak Hour	11	0	40	66	117	1	0	0	0	1	0	0	0	0	0



Two-Hour Count Summaries

Interval Start	Meadowbrook Parkway				Meadowbrook Parkway				Marksheffel Rd				Marksheffel Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
4:00 PM	0	43	0	5	0	5	3	10	0	12	227	7	0	5	183	21	521	0
4:15 PM	0	29	3	9	0	5	2	6	0	8	294	16	1	6	164	25	568	0
4:30 PM	0	39	2	11	0	1	1	5	0	5	260	11	1	10	150	27	523	0
4:45 PM	0	20	3	12	0	3	3	4	0	6	280	20	0	9	206	24	590	2,202
5:00 PM	0	42	5	10	0	6	0	5	0	5	226	12	0	10	173	13	507	2,188
5:15 PM	0	29	3	10	0	4	0	9	0	3	260	14	0	7	193	23	555	2,175
5:30 PM	0	18	3	9	0	4	1	5	0	3	214	13	0	12	200	29	511	2,163
5:45 PM	0	24	0	4	0	3	0	8	1	4	194	10	0	7	123	12	390	1,963
Count Total	0	244	19	70	0	31	10	52	1	46	1,955	103	2	66	1,392	174	4,165	0
Peak Hour	0	131	8	37	0	14	9	25	0	31	1,061	54	2	30	703	97	2,202	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
4:00 PM	0	0	5	12	17	0	0	0	0	0	0	0	0	0	0
4:15 PM	2	0	3	6	11	0	1	0	0	1	0	0	2	0	2
4:30 PM	0	0	4	7	11	0	0	0	0	0	0	0	3	0	3
4:45 PM	1	0	5	7	13	0	0	0	0	0	0	0	0	0	0
5:00 PM	2	0	2	6	10	0	0	0	0	0	0	0	0	0	0
5:15 PM	0	0	5	6	11	0	0	0	0	0	0	0	0	0	0
5:30 PM	2	0	2	8	12	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	2	5	7	0	0	0	0	0	0	0	0	0	0
Count Total	7	0	28	57	92	0	1	0	0	1	0	0	5	0	5
Peak Hour	3	0	17	32	52	0	1	0	0	1	0	0	5	0	5

APPENDIX B

CDOT Annual Traffic Data

Station ID: 103943
 Date: 7/11/2019
 Route: 094A

Description: SH 94 E/O Marksheffel Rd, Colorado Springs

COUNTDIR	12:00 AM	1:00 AM	2:00 AM	3:00 AM	4:00 AM	5:00 AM	6:00 AM	7:00 AM	8:00 AM	9:00 AM	10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM	5:00 PM	6:00 PM	7:00 PM	8:00 PM	9:00 PM	10:00 PM	11:00 PM			
P	21	16	9	23	82	299	705	500	366	246	211	243	253	246	252	271	391	383	282	193	178	120	99	54			
S	17	6	10	14	45	141	322	359	287	278	237	292	270	272	395	606	824	541	282	153	90	54	40	51			
Marsheffel and SH 94								Peak Hour Counts		528		95%		Marsheffel and SH 94								Peak Hour Counts		330		118%	
								Percent Difference		402		89%										Percent Difference		512		161%	
								Percent Difference		92%										Percent Difference		144%					

Station ID: 100851
 Date: 2/20/2020
 Route: 024G

Description: SH 24 NE/O SH 94, Colorado Springs

COUNTDIR	12:00 AM	1:00 AM	2:00 AM	3:00 AM	4:00 AM	5:00 AM	6:00 AM	7:00 AM	8:00 AM	9:00 AM	10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM	5:00 PM	6:00 PM	7:00 PM	8:00 PM	9:00 PM	10:00 PM	11:00 PM			
P	55	33	24	26	94	150	465	601	503	409	468	614	622	633	920	1088	1495	1289	704	712	452	268	159	82			
S	36	17	38	95	301	818	1863	1716	1023	715	636	665	609	577	613	655	693	685	369	224	183	124	79	53			
US 24 and SH 94								Peak Hour Counts		604		100%		US 24 and SH 94								Peak Hour Counts		1276		117%	
								Percent Difference		1315		130%										Percent Difference		721		96%	
								Percent Difference		121%										Percent Difference		110%					
US 24 and Marksheffel								Peak Hour Counts		609		99%		US 24 and Marksheffel								Peak Hour Counts		1282		117%	
								Percent Difference		1344		128%										Percent Difference		749		93%	
								Percent Difference		119%										Percent Difference		108%					

Reagan Ranch Growth Rate

Station ID	2018 AADT	2040 AADT	Growth Factor	Yearly Growth Rate
103943	10000	13630	1.33	1.30%
103944	11000	14025	1.25	1.02%
			Avg Growth Rate	1.16%

APPENDIX C

Trip Generation Worksheets

Trip Generation Planner (ITE 10th Edition) - Summary Report

Weekday Trip Generation
Trips Based on Average Rates/Equations

Project Name Crossroads-Meadowbrook (Total)
Project Number 096956010



ITE Code	Internal Capture Land Use	Land Use Description	Independent Variable	Setting/Location	No. of Units	Avg Rate or Eq	Rates			Total Trips						
							Daily Rate	AM Rate	PM Rate	Daily Trips	AM Trips	PM Trips	AM Trips In	AM Trips Out	PM Trips In	PM Trips Out
210	Residential	Single-Family Detached Housing	Dwelling Unit(s)	General Urban/Suburban	70	Avg	9.44	0.74	0.99	662	52	69	13	39	44	25
221	Residential	Multifamily Housing (Mid-Rise)	Dwelling Unit(s)	General Urban/Suburban	280	Eq	N/A	N/A	N/A	1,526	94	119	24	70	73	46
411	Other	Public Park	Acre(s)	General Urban/Suburban	18.28	Avg	0.78	0.02	0.11	14		2			1	1
444	Cinema/Entertainment	Movie Theater	1,000 Sq Ft	General Urban/Suburban	52	Avg	78.09	0.22	6.17	4,062	11	321	5	6	302	19
820	Retail	Shopping Center	1,000 Sq Ft GLA	General Urban/Suburban	44.942	Avg	37.75	0.94	3.81	1,696	42	171	26	16	82	89
849	Retail	Tire Superstore	1,000 Sq Ft	General Urban/Suburban	7.2	Avg	20.37	1.34	2.11	148	10	15	6	4	7	8
862	Retail	Home Improvement Superstore	1,000 Sq Ft	General Urban/Suburban	127	Avg	30.74	1.57	2.33	3,904	199	296	113	86	145	151
890	Retail	Furniture Store	1,000 Sq Ft	General Urban/Suburban	114	Avg	6.30	0.26	0.52	720	30	59	21	9	28	31
932	Restaurant	High-Turnover (Sit-Down) Restaurant	1,000 Sq Ft	General Urban/Suburban	21.2	Avg	112.18	9.94	9.77	2,380	210	207	116	94	128	79
934	Restaurant	Fast-Food Restaurant w/ D.T.	1,000 Sq Ft	General Urban/Suburban	20.909	Avg	470.95	40.19	32.67	9,850	840	683	428	412	355	328
937	Restaurant	Coffee/Donut Shop w/ D.T.	1,000 Sq Ft	General Urban/Suburban	2.4	Avg	820.38	88.99	43.38	1,968	214	106	109	105	53	53
960	Retail	Gasoline Station w/ Convenience Market	1,000 Sq Ft	General Urban/Suburban	5	Avg	837.58	83.14	69.28	4,188	416	346	208	208	173	173
Grand Total							31,118	2,118	2,394	1,069	1,049	1,391	1,003			

- Notes:
- (1) AM and/or PM rates correspond to peak hour of generator
 - (2) Land use was removed in *Trip Generation, 10 Edition*, trip generation data from the *ITE Trip Generation, 9th Edition*

Project Crossroads-Meadowbrook (Meadowbrook Park)
 Subject Trip Generation for Single-Family Detached Housing
 Designed by TES Date September 09, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Single-Family Detached Housing (210)

Independant Variable - Dwelling Units (X)

$$X = 70$$

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (200 Series Page 3)

Average Weekday

$$(T) = 0.74(X)$$

$$(T) = 0.74 * (70.0)$$

Directional Distribution: 25% entering, 75% exiting

$$T = 52 \quad \text{Average Vehicle Trip Ends}$$

$$13 \text{ entering} \quad 39 \text{ exiting}$$

$$13 + 39 = 52$$

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (200 Series Page 4)

Average Weekday

$$(T) = 0.99(X)$$

$$(T) = 0.99 * (70.0)$$

Directional Distribution: 63% entering, 37% exiting

$$T = 69 \quad \text{Average Vehicle Trip Ends}$$

$$44 \text{ entering} \quad 25 \text{ exiting}$$

$$44 + 25 = 69$$

Peak Hour of Generator, Saturday (200 Series Page 8)

Average Saturday

$$(T) = 0.93(X)$$

$$(T) = 0.93 * (70.0)$$

Directional Distribution: 54% entering, 46% exiting

$$T = 65 \quad \text{Average Vehicle Trip Ends}$$

$$35 \text{ entering} \quad 30 \text{ exiting}$$

$$35 + 30 = 65$$

Weekday (200 Series Page 2)

Average Weekday

$$(T) = 9.44(X)$$

$$(T) = 9.44 * (70.0)$$

Directional Distribution: 50% entering, 50% exiting

$$T = 662 \quad \text{Average Vehicle Trip Ends}$$

$$331 \text{ entering} \quad 331 \text{ exiting}$$

$$331 + 331 = 662$$

Trip Generation Planner (ITE 10th Edition) - Summary Report

Weekday Trip Generation
Trips Based on Average Rates/Equations

Project Name Crossroads-Meadowbrook (Crossroads North)
Project Number 096956010



ITE Code	Internal Capture Land Use	Land Use Description	Independent Variable	Setting/Location	No. of Units	Avg Rate or Eq	Rates			Total Trips						
							Daily Rate	AM Rate	PM Rate	Daily Trips	AM Trips	PM Trips	AM Trips In	AM Trips Out	PM Trips In	PM Trips Out
411	Other	Public Park	Acre(s)	General Urban/Suburban	18.28	Avg	0.78	0.02	0.11	14		2			1	1
444	Cinema/Entertainment	Movie Theater	1,000 Sq Ft	General Urban/Suburban	52	Avg	78.09	0.22	6.17	4,062	11	321	5	6	302	19
849	Retail	Tire Superstore	1,000 Sq Ft	General Urban/Suburban	7.2	Avg	20.37	1.34	2.11	148	10	15	6	4	7	8
862	Retail	Home Improvement Superstore	1,000 Sq Ft	General Urban/Suburban	127	Avg	30.74	1.57	2.33	3,904	199	296	113	86	145	151
890	Retail	Furniture Store	1,000 Sq Ft	General Urban/Suburban	114	Avg	6.30	0.26	0.52	720	30	59	21	9	28	31
932	Restaurant	High-Turnover (Sit-Down) Restaurant	1,000 Sq Ft	General Urban/Suburban	11	Avg	112.18	9.94	9.77	1,234	109	107	60	49	66	41
934	Restaurant	Fast-Food Restaurant w/ D.T.	1,000 Sq Ft	General Urban/Suburban	6.6	Avg	470.95	40.19	32.67	3,110	265	216	135	130	112	104
960	Retail	Gasoline Station w/ Convenience Market	1,000 Sq Ft	General Urban/Suburban	5	Avg	837.58	83.14	69.28	4,188	416	346	208	208	173	173
Grand Total							17,380	1,040	1,362	548	492	834	528			

- Notes:
- (1) AM and/or PM rates correspond to peak hour of generator
 - (2) Land use was removed in *Trip Generation, 10 Edition*, trip generation data from the ITE *Trip Generation, 9th Edition*

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation - Public Park
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. 1 of 1

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations
 Land Use Code - Public Park (411)
 Independent Variable - Acres (X)

Acres 18
 X = 18
 T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (400 Series Page 3)

Directional Distribution: 59% ent. 41% exit.
 (T) = 0.02 (X) T = 0 Average Vehicle Trip Ends
 (T) = 0.02 * (18.3) 0 entering 0 exiting
 0 + 0 = 0

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (400 Series Page 4)

Directional Distribution: 55% ent. 45% exit.
 (T) = 0.11 (X) T = 2 Average Vehicle Trip Ends
 (T) = 0.11 * (18.3) 1 entering 1 exiting
 1 + 1 = 2

Weekday (400 Series page 2)

Average Weekday Directional Distribution: 50% entering, 50% exiting
 T = 0.78* (X) T = 14 Average Vehicle Trip Ends
 T = 0.78 * 18 7 entering 7 exiting
 7 + 7 = 14

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for Movie Theater
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. 1 of 1

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Movie Theater (444)

Independent Variable - Gross Floor Area

Gross Floor Area = **52,000** Square Feet

X = 52.0

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (400 Series Page 111)

		Directional Distribution:	50% ent.	50% exit.
T = 0.22 (X)		T = 11	Average Vehicle Trip Ends	
T = 0.22 *	52	5 entering	6	exiting
		5 (*) - 6 =	11	

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (400 Series Page 112)

		Directional Distribution:	94% ent.	6% exit.
T = 6.17 (X)		T = 321	Average Vehicle Trip Ends	
T = 6.17 *	52	302 entering	19	exiting
		302 + 19 =	321	

Weekday (400 Series Page 110)

Average Weekday		Directional Distribution:	50% entering,	50% exiting
T = 78.09 (X)		T = 4062	Average Vehicle Trip Ends	
T = 78.09*	52	2031 entering	2031	exiting
		2031 + 2031 =	4062	

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for Tire Superstore
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Tire Superstore (849)

Independant Variable - 1000 Square Feet Gross Floor Area (X)

Gross Floor Area = **7,200** Square Feet

X = 7.200

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (800 Series Page 262)

		Directional Distribution:	65% ent.	35% exit.
T = 1.34 (X)		T =	10	Average Vehicle Trip Ends
T = 1.34 *	7.200	6	entering	4 exiting
		6	+	4 (*) = 10

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (800 Series Page 263)

		Directional Distribution:	47% ent.	53% exit.
T = 2.11 (X)		T =	15	Average Vehicle Trip Ends
T = 2.11 *	7.200	7	entering	8 exiting
		7	+	8 = 15

Weekday (800 Series Page 261)

Average Weekday		Directional Distribution:	50% entering,	50% exiting
T = 20.37 (X)		T =	148	Average Vehicle Trip Ends
T = 20.37*	7.200	74	entering	74 exiting
		74	+	74 = 148

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for Home Improvements Superstore
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. 1 of 1

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Home Improvement Superstore (862)

Independant Variable - 1000 Square Feet Gross Floor Area (X)

Gross Floor Area = **127,000** Square Feet

X = 127.000

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (800 Series Page 437)

		Directional Distribution:	57% ent.	43% exit.
T = 1.57 (X)		T =	199	Average Vehicle Trip Ends
T = 1.57 *	127.000	113	entering	86 exiting
		113	(*) · 86 =	199

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (800 Series Page 438)

		Directional Distribution:	49% ent.	51% exit.
T = 2.33 (X)		T =	296	Average Vehicle Trip Ends
T = 2.33 *	127.000	145	entering	151 exiting
		145	+	151 = 296

Weekday (800 Series Page 436)

Average Weekday		Directional Distribution:	50% entering,	50% exiting
T = 30.74 (X)		T =	3904	Average Vehicle Trip Ends
T = 30.74*	127.000	1952	entering	1952 exiting
		1952	+	1952 = 3904

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for Furniture Store
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. 1 of 1

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rates

Land Use Code - Furniture Store (890)

Independent Variable - 1000 Square Feet (X)

SF = 114,000

X = 114.000

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (800 Series Page 585)

(T) = 0.26 (X)		Directional Distribution:	71% ent.	29% exit.
(T) = 0.26 *	(114.0)	T = 30	Average Vehicle Trip Ends	
		21 entering	9	exiting
		21 + 9	=	30

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (800 Series Page 586)

(T) = 0.52 (X)		Directional Distribution:	47% ent.	53% exit.
(T) = 0.52 *	(114.0)	T = 59	Average Vehicle Trip Ends	
		28 entering	31	exiting
		28 + 31	=	59

Weekday (800 Series Page 584)

Average Weekday		Directional Distribution:	50% ent.	50% exit.
(T) = 6.30 (X)		T = 720	Average Vehicle Trip Ends	
(T) = 6.30 *	(114.0)	360 entering	360	exiting
		360 + 360	=	720

Saturday, Peak Hour of Generator (800 Series Page 590)

Daily Weekday		Directional Distribution:	54% ent.	46% exit.
(T) = 1.10 (X)		T = 125	Average Vehicle Trip Ends	
(T) = 1.10 *	(114.0)	68 entering	57	exiting
		68 + 57	=	125

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for High-Turnover (Sit-Down) Restaurant
 Designed by TES Date June 24, 2020 Job No. 096956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - High Turnover Sit-Down Restaurant (932)

Independant Variable - 1000 Square Feet Gross Floor Area (X)

Gross Floor Area = **11,000** Square Feet

X = 11.000

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (900 Series Page 97)

Average Weekday	Directional Distribution:	55% ent.	45% exit.
T = 9.94 (X)	T =	109	Average Vehicle Trip Ends
T = 9.94 * 11.000	60 entering	49	exiting

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (900 Series Page 98)

Average Weekday	Directional Distribution:	62% ent.	38% exit.
T = 9.77 (X)	T =	107	Average Vehicle Trip Ends
T = 9.77 * 11.000	66 entering	41	exiting

Weekday (900 Series Page 96)

Average Weekday	Directional Distribution:	50% entering, 50% exiting
T = 112.18 (X)	T =	1234 Average Vehicle Trip Ends
T = 112.18 * 11.000	617 entering	617 exiting

P.M. Peak Hour of Generator (900 Series Page 100)

Average Weekday	Directional Distribution:	52% ent.	48% exit.
T = 17.41 (X)	T =	192	Average Vehicle Trip Ends
T = 17.41 * 11.000	100 entering	92	exiting

Saturday Peak Hour of Generator (900 Series Page 105)

Average Saturday	Directional Distribution:	51% ent.	49% exit.
T = 11.19 (X)	T =	124	Average Vehicle Trip Ends
T = 11.19 * 11.000	63 entering	61	exiting

Non Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017-Page 207)

AM Peak Hour =	57%	Non-Pass By	PM Peak Hour =	57%	Non-Pass By
	IN	Out	Total		
AM Peak	34	28	62		
PM Peak	38	23	61		
Daily	352	352	704		PM Peak Hour Rate Applied to Daily

Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017 -Page 207)

AM Peak Hour =	43%	Pass By	PM Peak Hour =	43%	Pass By
	IN	Out	Total		
AM Peak	26	21	48		
PM Peak	28	18	46		
Daily	265	265	530		PM Peak Hour Rate Applied to Daily

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for Fast-Food Restaurant with Drive-Through Window
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Fast Food Restaurant With Drive-Through Window (934)

Independant Variable - 1000 Square Feet Gross Floor Area (X)

Gross Floor Area = 6,600 Square Feet

X = 6.600

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (900 Series page 158)

Average Weekday		Directional Distribution:	51% ent.	49% exit.
T = 40.19 (X)		T = 265	Average Vehicle Trip Ends	
T = 40.19 *	6.600	135 entering	130 exiting	
		135 + 130 =	265	

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (900 Series page 159)

Average Weekday		Directional Distribution:	52% ent.	48% exit.
T = 32.67 (X)		T = 216	Average Vehicle Trip Ends	
T = 32.67 *	6.600	112 entering	104 exiting	
		112 + 104 (*) =	216	

Weekday (900 Series page 157)

Average Weekday		Directional Distribution:	50% entering,	50% exiting
T = 470.95 (X)		T = 3110	Average Vehicle Trip Ends	
T = 470.95 *	6.600	1555 entering	1555 exiting	
		1555 + 1555 =	3110	

Saturday Peak Hour of Generator (900 Series page 163)

		Directional Distribution:	51% ent.	49% exit.
T = 54.86 (X)		T = 362	Average Vehicle Trip Ends	
T = 54.86 *	6.600	185 entering	177 exiting	
		185 + 177 =	362	

Non Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017)

AM Peak Hour =	51%	Non-Pass By	PM Peak Hour =	50%	Non-Pass By
	IN	Out	Total		
AM Peak	69	66	135		
PM Peak	56	52	108		
Daily	778	778	1556	PM Peak Hour Rate Applied to Daily	

Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017)

AM Peak Hour =	49%	Pass By	PM Peak Hour =	50%	Pass By
	IN	Out	Total		
AM Peak	66	64	130		
PM Peak	56	52	108		
Daily	777	777	1554	PM Peak Hour Rate Applied to Daily	

Project Crossroads-Meadowbrook (Crossroads North)
 Subject Trip Generation for Super Convenience Market/Gas Station
 Designed by TES Date June 24, 2020 Job No. 096956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Super Convenience Market/Gas Station (960)

Independant Variable - 1000 Square Feet Gross Leasable Area (X)

Gross Leasable Area = **5,000** Square Feet

X = 5.000

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (900 Series Page 404)

		Directional Distribution:	50% ent.	50% exit.
T = 83.14 (X)		T =	416	Average Vehicle Trip Ends
T = 83.14 *	5.000	208	entering	208 exiting
		208	+	208 = 416

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (900 Series page 405)

		Directional Distribution:	50% ent.	50% exit.
T = 69.28 (X)		T =	346	Average Vehicle Trip Ends
T = 69.28 *	5.000	173	entering	173 exiting
		173	+	173 = 346

Weekday (800 Series page 335)

Average Weekday		Directional Distribution:	50% entering,	50% exiting
T = 837.58 (X)		T =	4188	Average Vehicle Trip Ends
T = 837.58 *	5.000	2094	entering	2094 exiting
		2094	+	2094 = 4188

Non Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017)

PM Peak Hour =	44%	Non-Pass By	AM Peak Hour =	38%	Non-Pass By
	IN	Out	Total	* Utilized ITE 945 pass-by calculations	
AM Peak	79	79	158		
PM Peak	76	76	152		
Daily	921	921	1842	PM Peak Hour Rate Applied to Daily	

Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017)

PM Peak Hour =	56%	Pass By	AM Peak Hour =	62%	Pass By
	IN	Out	Total		
AM Peak	129	129	258		
PM Peak	97	97	194		
Daily	1173	1173	2346	PM Peak Hour Rate Applied to Daily	

Trip Generation Planner (ITE 10th Edition) - Summary Report

Weekday Trip Generation
Trips Based on Average Rates/Equations

Project Name Crossroads-Meadowbrook (Crossroads Mix Use)
Project Number 096956010



ITE Code	Internal Capture Land Use	Land Use Description	Independent Variable	Setting/Location	No. of Units	Avg Rate or Eq	Rates			Total Trips						
							Daily Rate	AM Rate	PM Rate	Daily Trips	AM Trips	PM Trips	AM Trips In	AM Trips Out	PM Trips In	PM Trips Out
221	Residential	Multifamily Housing (Mid-Rise)	Dwelling Unit(s)	General Urban/Suburban	280	Eq	N/A	N/A	N/A	1,526	94	119	24	70	73	46
820	Retail	Shopping Center	1,000 Sq Ft GLA	General Urban/Suburban	44.942	Avg	37.75	0.94	3.81	1,696	42	171	26	16	82	89
932	Restaurant	High-Turnover (Sit-Down) Restaurant	1,000 Sq Ft	General Urban/Suburban	10.2	Avg	112.18	9.94	9.77	1,146	101	100	56	45	62	38
934	Restaurant	Fast-Food Restaurant w/ D.T.	1,000 Sq Ft	General Urban/Suburban	14.309	Avg	470.95	40.19	32.67	6,740	575	467	293	282	243	224
937	Restaurant	Coffee/Donut Shop w/ D.T.	1,000 Sq Ft	General Urban/Suburban	2.4	Avg	820.38	88.99	43.38	1,968	214	106	109	105	53	53
Grand Total										13,076	1,026	963	508	518	513	450

- Notes:
- (1) AM and/or PM rates correspond to peak hour of generator
 - (2) Land use was removed in *Trip Generation, 10 Edition*, trip generation data from the *ITE Trip Generation, 9th Edition*

Project Crossroads-Meadowbrook (Crossroads Mix Use)
 Subject Trip Generation for Multifamily Housing (Mid-Rise)
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Fitted Curve Equations

Land Use Code - Multifamily Housing (Mid-Rise) (221)

Independent Variable - Dwelling Units (X)

$$X = 280$$

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (Series 200 Page 74)

$\ln(T) = 0.98 \ln(X) - 0.98$	Directional Distribution:	26% ent.	74% exit.
$\ln(T) = 0.98 * \ln(280.0) - 0.98$	T =	94	Average Vehicle Trip Ends
	24 entering	70 exiting	
	24 + 70 =	94	

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (Series 200 Page 75)

$\ln(T) = 0.96 \ln(X) - 0.63$	Directional Distribution:	61% ent.	39% exit.
$\ln(T) = 0.96 * \ln(280.0) - 0.63$	T =	119	Average Vehicle Trip Ends
	73 entering	46 exiting	
	73 + 46 =	119	

Weekday (Series 200 Page 73)

$(T) = 5.45*(X) - 1.75$	Directional Distribution:	50% ent.	50% exit.
$(T) = 5.45 * 280 - 1.75$	T =	1526	Average Vehicle Trip Ends
	763 entering	763 exiting	
	763 + 763 =	1526	

Peak Hour of Generator, Saturday (Series 200 Page 79)

$(T) = 0.42*(X) + 6.73$	Directional Distribution:	49% ent.	51% exit.
$(T) = 0.42 * 280 + 6.73$	T =	124	Average Vehicle Trip Ends
	61 entering	63 exiting	
	61 + 63 =	124	

Project Crossroads-Meadowbrook (Crossroads Mix Use)
 Subject Trip Generation for Shopping Center
 Designed by TES Date June 24, 2020 Job No. 096956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Shopping Center (820)

Independant Variable - 1000 Square Feet Gross Leasable Area (X)

Gross Leasable Area = **44,942** Square Feet

X = 44.942

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (800 Series Page 139)

Average Weekday		Directional Distribution:	62% ent.	38% exit.
T = 0.94 * (X)		T =	42	Average Vehicle Trip Ends
T = 0.94 *	44.942	26	entering	16 exiting
		26	+	16 = 42

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (800 Series page 140)

Average Weekday		Directional Distribution:	48% ent.	52% exit.
T = 3.81 * (X)		T =	171	Average Vehicle Trip Ends
T = 3.81 *	44.942	82	entering	89 exiting
		82	+	89 = 171

Weekday (800 Series page 138)

Average Weekday		Directional Distribution:	50% entering,	50% exiting
T = 37.75 * (X)		T =	1696	Average Vehicle Trip Ends
T = 37.75 *	44.942	848	entering	848 exiting
		848	+	848 = 1696

Non Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017-Page 190)

AM Peak Hour =	66%	Non-Pass By	PM Peak Hour =	66%	Non-Pass By
	IN	Out	Total		
AM Peak	17	11	28		
PM Peak	54	59	113		
Daily	560	560	1120		PM Peak Hour Rate Applied to Daily

Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017 -Page 190)

AM Peak Hour =	34%	Pass By	PM Peak Hour =	34%	Pass By
	IN	Out	Total		
AM Peak	9	5	15		
PM Peak	28	30	58		
Daily	288	288	576		PM Peak Hour Rate Applied to Daily

Project Crossroads-Meadowbrook (Crossroads Mix Use)
 Subject Trip Generation for Fast-Food Restaurant with Drive-Through Window
 Designed by TES Date June 24, 2020 Job No. 96956010
 Checked by _____ Date _____ Sheet No. 1 of 1

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Fast Food Restaurant With Drive-Through Window (934)

Independant Variable - 1000 Square Feet Gross Floor Area (X)

Gross Floor Area = 14,309 Square Feet

X = 14.309

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (900 Series page 158)

Average Weekday		Directional Distribution:	51% ent.	49% exit.
T = 40.19 (X)		T = 575	Average Vehicle Trip Ends	
T = 40.19 *	14.309	293 entering	282	exiting
		293 + 282 =	575	

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (900 Series page 159)

Average Weekday		Directional Distribution:	52% ent.	48% exit.
T = 32.67 (X)		T = 467	Average Vehicle Trip Ends	
T = 32.67 *	14.309	243 entering	224	exiting
		243 + 224 =	467	

Weekday (900 Series page 157)

Average Weekday		Directional Distribution:	50% entering, 50% exiting	
T = 470.95 (X)		T = 6740	Average Vehicle Trip Ends	
T = 470.95 *	14.309	3370 entering	3370	exiting
		3370 + 3370 =	6740	

Saturday Peak Hour of Generator (900 Series page 163)

		Directional Distribution:	51% ent.	49% exit.
T = 54.86 (X)		T = 785	Average Vehicle Trip Ends	
T = 54.86 *	14.309	400 entering	385	exiting
		400 + 385 =	785	

Non Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017)

AM Peak Hour =	51%	Non-Pass By	PM Peak Hour =	50%	Non-Pass By
	IN	Out	Total		
AM Peak	149	144	293		
PM Peak	122	112	234		
Daily	1685	1685	3370	PM Peak Hour Rate Applied to Daily	

Pass-By Trip Volumes (Per ITE Trip Generation Handbook, 3rd Edition September 2017)

AM Peak Hour =	49%	Pass By	PM Peak Hour =	50%	Pass By
	IN	Out	Total		
AM Peak	144	138	282		
PM Peak	122	112	234		
Daily	1685	1685	3370	PM Peak Hour Rate Applied to Daily	

Project Crossroads-Meadowbrook (Crossroads Mix Use)
 Subject Trip Generation for Coffee/Donut Shop with Drive Through
 Designed by TES Date June 24, 2020 Job No. 096956010
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 10th Edition, Average Rate Equations

Land Use Code - Coffee/Donut Shop with Drive Through (937)

Independant Variable - 1000 Square Feet Gross Floor Feet (X)

Gross Floor Area = 2,400

X = 2.4

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (Series 900 Page 232)

T = 88.99 (X)		Directional Distribution:	51% ent.	49% exit.
T = 88.99 *	2.4	T = 214	Average Vehicle Trip Ends	
		109 entering	105 exiting	

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (Series 900 Page 233)

T = 43.38 (X)		Directional Distribution:	50% ent.	50% exit.
T = 43.38 *	2.4	T = 106	Average Vehicle Trip Ends	
		53 entering	53 exiting	

Weekday (Series 900 Page 231)

Average Weekday		Directional Distribution:	50% entering, 50% exiting	
(T) = 820.38 (X)		T = 1968	Average Vehicle Trip Ends	
(T) = 820.38 *	(2.4)	984 entering	984 exiting	
		984 + 984 = 1968		

APPENDIX D

Intersection Analysis Worksheets

Timings


1: Marksheffel Rd & Meadowbrook Pkwy

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	94	5	31	32	17	23	24	683	14	7	1235	151
Future Volume (vph)	94	5	31	32	17	23	24	683	14	7	1235	151
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm
Protected Phases	7	4		3	8			2			6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5
Total Split (s)	16.0	29.0	29.0	11.0	24.0	24.0	80.0	80.0	80.0	80.0	80.0	80.0
Total Split (%)	13.3%	24.2%	24.2%	9.2%	20.0%	20.0%	66.7%	66.7%	66.7%	66.7%	66.7%	66.7%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes						
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min
Act Effct Green (s)	9.7	8.5	8.5	14.9	7.0	7.0	88.2	88.2	88.2	88.2	88.2	88.2
Actuated g/C Ratio	0.08	0.07	0.07	0.12	0.06	0.06	0.74	0.74	0.74	0.74	0.74	0.74
v/c Ratio	0.45	0.05	0.21	0.20	0.20	0.17	0.13	0.32	0.01	0.02	0.54	0.14
Control Delay	57.8	51.0	2.5	42.4	57.6	2.1	9.0	10.5	0.3	6.1	8.8	1.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.8	51.0	2.5	42.4	57.6	2.1	9.0	10.5	0.3	6.1	8.8	1.2
LOS	E	D	A	D	E	A	A	B	A	A	A	A
Approach Delay		44.3			33.3			10.2			8.0	
Approach LOS		D			C			B			A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.54
 Intersection Signal Delay: 11.8
 Intersection LOS: B
 Intersection Capacity Utilization 57.1%
 ICU Level of Service B
 Analysis Period (min) 15

Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2020 Adjusted Existing AM.syn
 06/24/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	94	5	31	32	17	23	24	683	14	7	1235	151
Future Volume (veh/h)	94	5	31	32	17	23	24	683	14	7	1235	151
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1752	1752	1752	1870	1870	1870	1796	1796	1796	1811	1811	1811
Adj Flow Rate, veh/h	115	6	38	41	22	29	28	785	16	8	1342	164
Peak Hour Factor	0.82	0.82	0.82	0.79	0.79	0.79	0.87	0.87	0.87	0.92	0.92	0.92
Percent Heavy Veh, %	10	10	10	2	2	2	7	7	7	6	6	6
Cap, veh/h	167	93	79	171	77	65	263	2599	1159	514	2620	1169
Arrive On Green	0.05	0.05	0.05	0.03	0.04	0.04	0.76	0.76	0.76	0.76	0.76	0.76
Sat Flow, veh/h	3237	1752	1485	1781	1870	1585	334	3413	1522	658	3441	1535
Grp Volume(v), veh/h	115	6	38	41	22	29	28	785	16	8	1342	164
Grp Sat Flow(s),veh/h/ln	1618	1752	1485	1781	1870	1585	334	1706	1522	658	1721	1535
Q Serve(g_s), s	4.2	0.4	3.0	2.6	1.4	2.1	4.3	8.6	0.3	0.5	18.3	3.4
Cycle Q Clear(g_c), s	4.2	0.4	3.0	2.6	1.4	2.1	22.6	8.6	0.3	9.0	18.3	3.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	167	93	79	171	77	65	263	2599	1159	514	2620	1169
V/C Ratio(X)	0.69	0.06	0.48	0.24	0.29	0.44	0.11	0.30	0.01	0.02	0.51	0.14
Avail Cap(c_a), veh/h	297	350	297	190	281	238	263	2599	1159	514	2620	1169
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	56.0	54.0	55.2	52.9	55.8	56.2	10.0	4.4	3.5	5.8	5.6	3.8
Incr Delay (d2), s/veh	5.0	0.3	4.5	0.7	2.0	4.7	0.8	0.3	0.0	0.1	0.7	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.8	0.2	1.2	1.2	0.7	0.9	0.4	2.7	0.1	0.1	5.9	1.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	61.0	54.2	59.6	53.6	57.8	60.8	10.8	4.7	3.5	5.9	6.3	4.1
LnGrp LOS	E	D	E	D	E	E	B	A	A	A	A	A
Approach Vol, veh/h		159			92			829			1514	
Approach Delay, s/veh		60.4			56.9			4.9			6.1	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		97.9	9.7	12.4		97.9	11.2	10.9				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		73.5	5.0	* 24		73.5	11.0	18.0				
Max Q Clear Time (g_c+I1), s		24.6	4.6	5.0		20.3	6.2	4.1				
Green Ext Time (p_c), s		7.7	0.0	0.1		16.6	0.1	0.1				

Intersection Summary

HCM 6th Ctrl Delay	10.8
HCM 6th LOS	B

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings

1: Marksheffel Rd & Meadowbrook Pkwy

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	
Lane Configurations													
Traffic Volume (vph)	144	9	41	15	10	28	34	1167	59	33	773	107	
Future Volume (vph)	144	9	41	15	10	28	34	1167	59	33	773	107	
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm	
Protected Phases	7	4		3	8			2			6		
Permitted Phases			4	8		8	2		2	6		6	
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6	
Switch Phase													
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5	
Total Split (s)	18.0	32.0	32.0	11.0	25.0	25.0	77.0	77.0	77.0	77.0	77.0	77.0	
Total Split (%)	15.0%	26.7%	26.7%	9.2%	20.8%	20.8%	64.2%	64.2%	64.2%	64.2%	64.2%	64.2%	
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0	
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5	
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag							
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes							
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min	
Act Effct Green (s)	11.2	13.5	13.5	12.1	6.6	6.6	87.0	87.0	87.0	87.0	87.0	87.0	
Actuated g/C Ratio	0.09	0.11	0.11	0.10	0.06	0.06	0.72	0.72	0.72	0.72	0.72	0.72	
v/c Ratio	0.53	0.05	0.19	0.14	0.15	0.20	0.09	0.51	0.06	0.16	0.35	0.11	
Control Delay	57.5	48.7	3.8	40.5	56.7	2.1	7.1	13.5	0.7	8.8	7.3	1.3	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	57.5	48.7	3.8	40.5	56.7	2.1	7.1	13.5	0.7	8.8	7.3	1.3	
LOS	E	D	A	D	E	A	A	B	A	A	A	A	
Approach Delay		45.8			23.2			12.8				6.6	
Approach LOS		D			C			B				A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.53
 Intersection Signal Delay: 13.5
 Intersection Capacity Utilization 55.2%
 Analysis Period (min) 15
 Intersection LOS: B
 ICU Level of Service B

Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2020 Adjusted Existing PM.syn
 06/24/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	144	9	41	15	10	28	34	1167	59	33	773	107
Future Volume (veh/h)	144	9	41	15	10	28	34	1167	59	33	773	107
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	169	11	48	22	15	42	38	1297	66	38	889	123
Peak Hour Factor	0.85	0.85	0.85	0.67	0.67	0.67	0.90	0.90	0.90	0.87	0.87	0.87
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	4	4	4
Cap, veh/h	229	149	126	157	81	68	426	2646	1180	295	2605	1162
Arrive On Green	0.07	0.08	0.08	0.02	0.04	0.04	0.74	0.74	0.74	0.74	0.74	0.74
Sat Flow, veh/h	3456	1870	1585	1781	1870	1585	557	3554	1585	393	3497	1560
Grp Volume(v), veh/h	169	11	48	22	15	42	38	1297	66	38	889	123
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1781	1870	1585	557	1777	1585	393	1749	1560
Q Serve(g_s), s	5.8	0.7	3.4	1.4	0.9	3.1	3.0	17.6	1.3	5.2	10.4	2.6
Cycle Q Clear(g_c), s	5.8	0.7	3.4	1.4	0.9	3.1	13.4	17.6	1.3	22.8	10.4	2.6
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	229	149	126	157	81	68	426	2646	1180	295	2605	1162
V/C Ratio(X)	0.74	0.07	0.38	0.14	0.19	0.61	0.09	0.49	0.06	0.13	0.34	0.11
Avail Cap(c_a), veh/h	374	421	357	192	296	251	426	2646	1180	295	2605	1162
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	55.0	51.1	52.4	53.1	55.4	56.4	7.5	6.2	4.1	10.7	5.2	4.2
Incr Delay (d2), s/veh	4.6	0.2	1.9	0.4	1.1	8.6	0.4	0.7	0.1	0.9	0.4	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.7	0.3	1.4	0.6	0.5	1.4	0.4	6.0	0.4	0.5	3.5	0.8
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.6	51.4	54.3	53.5	56.5	65.0	8.0	6.8	4.2	11.6	5.6	4.4
LnGrp LOS	E	D	D	D	E	E	A	A	A	B	A	A
Approach Vol, veh/h		228			79			1401			1050	
Approach Delay, s/veh		58.1			60.2			6.7			5.7	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		95.9	8.6	15.5		95.9	13.0	11.2				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		70.5	5.0	* 27		70.5	13.0	19.0				
Max Q Clear Time (g_c+I1), s		19.6	3.4	5.4		24.8	7.8	5.1				
Green Ext Time (p_c), s		15.5	0.0	0.1		9.5	0.2	0.1				

Intersection Summary

HCM 6th Ctrl Delay	12.1
HCM 6th LOS	B


Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2025 Background AM.syn

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↔↔	↑	↔	↔	↑	↔	↔	↑↑	↔	↔	↑↑	↔
Traffic Volume (veh/h)	105	10	35	35	20	25	30	725	15	10	1310	160
Future Volume (veh/h)	105	10	35	35	20	25	30	725	15	10	1310	160
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1752	1752	1752	1870	1870	1870	1796	1796	1796	1811	1811	1811
Adj Flow Rate, veh/h	128	12	43	44	25	32	34	833	17	11	1424	174
Peak Hour Factor	0.82	0.82	0.82	0.79	0.79	0.79	0.87	0.87	0.87	0.92	0.92	0.92
Percent Heavy Veh, %	10	10	10	2	2	2	7	7	7	6	6	6
Cap, veh/h	180	99	84	173	78	66	239	2584	1153	486	2605	1162
Arrive On Green	0.06	0.06	0.06	0.03	0.04	0.04	0.76	0.76	0.76	0.76	0.76	0.76
Sat Flow, veh/h	3237	1752	1485	1781	1870	1585	306	3413	1522	628	3441	1535
Grp Volume(v), veh/h	128	12	43	44	25	32	34	833	17	11	1424	174
Grp Sat Flow(s),veh/h/ln	1618	1752	1485	1781	1870	1585	306	1706	1522	628	1721	1535
Q Serve(g_s), s	4.7	0.8	3.4	2.8	1.6	2.4	6.2	9.4	0.3	0.7	20.6	3.7
Cycle Q Clear(g_c), s	4.7	0.8	3.4	2.8	1.6	2.4	26.8	9.4	0.3	10.1	20.6	3.7
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	180	99	84	173	78	66	239	2584	1153	486	2605	1162
V/C Ratio(X)	0.71	0.12	0.51	0.25	0.32	0.49	0.14	0.32	0.01	0.02	0.55	0.15
Avail Cap(c_a), veh/h	270	336	285	190	281	238	239	2584	1153	486	2605	1162
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	55.7	53.8	55.0	52.8	55.9	56.3	11.6	4.7	3.6	6.3	6.0	4.0
Incr Delay (d2), s/veh	5.1	0.5	4.7	0.8	2.4	5.5	1.2	0.3	0.0	0.1	0.8	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.0	0.4	1.4	1.3	0.8	1.0	0.5	3.0	0.1	0.1	6.6	1.1
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	60.8	54.3	59.7	53.6	58.2	61.8	12.8	5.0	3.6	6.4	6.9	4.3
LnGrp LOS	E	D	E	D	E	E	B	A	A	A	A	A
Approach Vol, veh/h		183			101			884			1609	
Approach Delay, s/veh		60.1			57.3			5.3			6.6	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		97.4	9.8	12.8		97.4	11.7	11.0				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		74.5	5.0	* 23		74.5	10.0	18.0				
Max Q Clear Time (g_c+I1), s		28.8	4.8	5.4		22.6	6.7	4.4				
Green Ext Time (p_c), s		8.6	0.0	0.1		18.4	0.1	0.1				

Intersection Summary

HCM 6th Ctrl Delay	11.5
HCM 6th LOS	B


Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings

1: Marksheffel Rd & Meadowbrook Pkwy

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (vph)	155	10	45	20	15	30	40	1240	65	35	820	115
Future Volume (vph)	155	10	45	20	15	30	40	1240	65	35	820	115
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm
Protected Phases	7	4		3	8			2			6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5
Total Split (s)	18.0	31.0	31.0	11.0	24.0	24.0	78.0	78.0	78.0	78.0	78.0	78.0
Total Split (%)	15.0%	25.8%	25.8%	9.2%	20.0%	20.0%	65.0%	65.0%	65.0%	65.0%	65.0%	65.0%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes						
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min
Act Effct Green (s)	11.7	14.0	14.0	13.0	7.0	7.0	86.1	86.1	86.1	86.1	86.1	86.1
Actuated g/C Ratio	0.10	0.12	0.12	0.11	0.06	0.06	0.72	0.72	0.72	0.72	0.72	0.72
v/c Ratio	0.54	0.06	0.20	0.17	0.20	0.21	0.12	0.54	0.06	0.20	0.38	0.11
Control Delay	57.4	47.9	4.9	40.3	57.7	2.2	7.7	12.6	1.4	10.4	7.9	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.4	47.9	4.9	40.3	57.7	2.2	7.7	12.6	1.4	10.4	7.9	1.4
LOS	E	D	A	D	E	A	A	B	A	B	A	A
Approach Delay		45.7			26.5			11.9			7.2	
Approach LOS		D			C			B			A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.54
 Intersection Signal Delay: 13.5
 Intersection LOS: B
 Intersection Capacity Utilization 57.4%
 ICU Level of Service B
 Analysis Period (min) 15


Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2025 Background PM.syn

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	155	10	45	20	15	30	40	1240	65	35	820	115
Future Volume (veh/h)	155	10	45	20	15	30	40	1240	65	35	820	115
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	182	12	53	30	22	45	44	1378	72	40	943	132
Peak Hour Factor	0.85	0.85	0.85	0.67	0.67	0.67	0.90	0.90	0.90	0.87	0.87	0.87
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	4	4	4
Cap, veh/h	242	151	128	168	85	72	397	2625	1171	267	2583	1152
Arrive On Green	0.07	0.08	0.08	0.03	0.05	0.05	0.74	0.74	0.74	0.74	0.74	0.74
Sat Flow, veh/h	3456	1870	1585	1781	1870	1585	525	3554	1585	361	3497	1560
Grp Volume(v), veh/h	182	12	53	30	22	45	44	1378	72	40	943	132
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1781	1870	1585	525	1777	1585	361	1749	1560
Q Serve(g_s), s	6.2	0.7	3.8	1.9	1.4	3.3	3.9	19.9	1.5	6.4	11.6	2.9
Cycle Q Clear(g_c), s	6.2	0.7	3.8	1.9	1.4	3.3	15.5	19.9	1.5	26.2	11.6	2.9
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	242	151	128	168	85	72	397	2625	1171	267	2583	1152
V/C Ratio(X)	0.75	0.08	0.41	0.18	0.26	0.62	0.11	0.53	0.06	0.15	0.37	0.11
Avail Cap(c_a), veh/h	374	405	343	195	281	238	397	2625	1171	267	2583	1152
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	54.8	51.0	52.4	52.6	55.3	56.3	8.4	6.7	4.3	12.3	5.6	4.5
Incr Delay (d2), s/veh	4.6	0.2	2.1	0.5	1.6	8.6	0.6	0.8	0.1	1.2	0.4	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.9	0.3	1.6	0.9	0.7	1.5	0.5	6.8	0.5	0.6	3.9	0.9
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.4	51.2	54.6	53.1	56.9	64.8	9.0	7.5	4.4	13.5	6.0	4.7
LnGrp LOS	E	D	D	D	E	E	A	A	A	B	A	A
Approach Vol, veh/h		247			97			1494			1115	
Approach Delay, s/veh		58.0			59.4			7.3			6.1	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		95.1	9.2	15.7		95.1	13.4	11.5				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		71.5	5.0	* 26		71.5	13.0	18.0				
Max Q Clear Time (g_c+I1), s		21.9	3.9	5.8		28.2	8.2	5.3				
Green Ext Time (p_c), s		17.2	0.0	0.2		10.4	0.2	0.1				

Intersection Summary


HCM 6th Ctrl Delay	12.8
HCM 6th LOS	B

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2025 Total AM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	190	10	35	35	20	25	30	800	15	10	1395	240
Future Volume (veh/h)	190	10	35	35	20	25	30	800	15	10	1395	240
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1752	1752	1752	1870	1870	1870	1796	1796	1796	1811	1811	1811
Adj Flow Rate, veh/h	207	11	38	38	22	27	33	870	16	11	1516	261
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	10	10	10	2	2	2	7	7	7	6	6	6
Cap, veh/h	266	149	126	169	77	65	193	2494	1112	448	2514	1122
Arrive On Green	0.08	0.09	0.09	0.03	0.04	0.04	0.73	0.73	0.73	0.73	0.73	0.73
Sat Flow, veh/h	3237	1752	1485	1781	1870	1585	257	3413	1522	607	3441	1535
Grp Volume(v), veh/h	207	11	38	38	22	27	33	870	16	11	1516	261
Grp Sat Flow(s),veh/h/ln	1618	1752	1485	1781	1870	1585	257	1706	1522	607	1721	1535
Q Serve(g_s), s	7.5	0.7	2.9	2.4	1.4	2.0	8.5	11.1	0.3	0.8	25.4	6.6
Cycle Q Clear(g_c), s	7.5	0.7	2.9	2.4	1.4	2.0	34.0	11.1	0.3	11.9	25.4	6.6
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	266	149	126	169	77	65	193	2494	1112	448	2514	1122
V/C Ratio(X)	0.78	0.07	0.30	0.22	0.29	0.41	0.17	0.35	0.01	0.02	0.60	0.23
Avail Cap(c_a), veh/h	432	380	322	235	281	238	193	2494	1112	448	2514	1122
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	54.0	50.5	51.5	52.9	55.8	56.1	15.9	5.8	4.4	8.0	7.8	5.2
Incr Delay (d2), s/veh	4.9	0.2	1.3	0.7	2.0	4.1	1.9	0.4	0.0	0.1	1.1	0.5
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.2	0.3	1.1	1.1	0.7	0.9	0.6	3.7	0.1	0.1	8.7	2.1
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	58.9	50.7	52.8	53.6	57.8	60.2	17.9	6.2	4.4	8.1	8.9	5.7
LnGrp LOS	E	D	D	D	E	E	B	A	A	A	A	A
Approach Vol, veh/h		256			87			919			1788	
Approach Delay, s/veh		57.6			56.7			6.6			8.4	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		94.2	9.6	16.2		94.2	14.9	10.9				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		68.5	8.0	* 26		68.5	16.0	18.0				
Max Q Clear Time (g_c+I1), s		36.0	4.4	4.9		27.4	9.5	4.0				
Green Ext Time (p_c), s		8.6	0.0	0.1		19.4	0.4	0.1				
Intersection Summary												
HCM 6th Ctrl Delay				13.4								
HCM 6th LOS				B								
Notes												
* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.												

Timings


1: Marksheffel Rd & Meadowbrook Pkwy

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	230	10	45	20	15	30	40	1320	65	35	945	200
Future Volume (vph)	230	10	45	20	15	30	40	1320	65	35	945	200
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm
Protected Phases	7	4		3	8			2			6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5
Total Split (s)	23.0	33.0	33.0	14.0	24.0	24.0	73.0	73.0	73.0	73.0	73.0	73.0
Total Split (%)	19.2%	27.5%	27.5%	11.7%	20.0%	20.0%	60.8%	60.8%	60.8%	60.8%	60.8%	60.8%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes						
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min
Act Effct Green (s)	14.0	14.1	14.1	11.0	6.6	6.6	86.5	86.5	86.5	86.5	86.5	86.5
Actuated g/C Ratio	0.12	0.12	0.12	0.09	0.06	0.06	0.72	0.72	0.72	0.72	0.72	0.72
v/c Ratio	0.62	0.05	0.19	0.14	0.16	0.16	0.13	0.56	0.06	0.20	0.41	0.18
Control Delay	57.3	45.7	3.7	39.4	56.9	1.6	7.5	12.7	1.2	11.3	8.4	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	45.7	3.7	39.4	56.9	1.6	7.5	12.7	1.2	11.3	8.4	1.4
LOS	E	D	A	D	E	A	A	B	A	B	A	A
Approach Delay		48.4			25.8			12.0			7.3	
Approach LOS		D			C			B			A	

Intersection Summary


Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 75
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.63
 Intersection Signal Delay: 14.0
 Intersection LOS: B
 Intersection Capacity Utilization 61.8%
 ICU Level of Service B
 Analysis Period (min) 15

Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2025 Total PM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	230	10	45	20	15	30	40	1320	65	35	945	200
Future Volume (veh/h)	230	10	45	20	15	30	40	1320	65	35	945	200
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	250	11	49	22	16	33	43	1435	71	38	1027	217
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	4	4	4
Cap, veh/h	317	192	163	154	77	65	331	2564	1143	242	2523	1125
Arrive On Green	0.09	0.10	0.10	0.02	0.04	0.04	0.72	0.72	0.72	0.72	0.72	0.72
Sat Flow, veh/h	3456	1870	1585	1781	1870	1585	447	3554	1585	342	3497	1560
Grp Volume(v), veh/h	250	11	49	22	16	33	43	1435	71	38	1027	217
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1781	1870	1585	447	1777	1585	342	1749	1560
Q Serve(g_s), s	8.5	0.6	3.4	1.4	1.0	2.4	5.0	22.6	1.6	7.0	13.9	5.4
Cycle Q Clear(g_c), s	8.5	0.6	3.4	1.4	1.0	2.4	18.9	22.6	1.6	29.6	13.9	5.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	317	192	163	154	77	65	331	2564	1143	242	2523	1125
V/C Ratio(X)	0.79	0.06	0.30	0.14	0.21	0.51	0.13	0.56	0.06	0.16	0.41	0.19
Avail Cap(c_a), veh/h	518	436	370	234	281	238	331	2564	1143	242	2523	1125
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	53.4	48.6	49.8	53.4	55.6	56.3	10.3	7.8	4.9	14.7	6.6	5.4
Incr Delay (d2), s/veh	4.4	0.1	1.0	0.4	1.3	6.0	0.8	0.9	0.1	1.4	0.5	0.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.9	0.3	1.4	0.6	0.5	1.1	0.6	8.0	0.5	0.6	4.8	1.7
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	57.8	48.7	50.9	53.8	57.0	62.3	11.1	8.7	5.0	16.1	7.1	5.8
LnGrp LOS	E	D	D	D	E	E	B	A	A	B	A	A
Approach Vol, veh/h		310			71			1549			1282	
Approach Delay, s/veh		56.4			58.5			8.6			7.1	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		93.1	8.6	18.3		93.1	16.0	10.9				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		66.5	8.0	* 28		66.5	18.0	18.0				
Max Q Clear Time (g_c+I1), s		24.6	3.4	5.4		31.6	10.5	4.4				
Green Ext Time (p_c), s		17.5	0.0	0.1		11.5	0.5	0.1				

Intersection Summary

HCM 6th Ctrl Delay	13.7
HCM 6th LOS	B

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings

1: Marksheffel Rd & Meadowbrook Pkwy

07/16/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	120	10	40	45	25	30	35	865	20	10	1560	195
Future Volume (vph)	120	10	40	45	25	30	35	865	20	10	1560	195
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm
Protected Phases	7	4		3	8			2			6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5
Total Split (s)	15.0	27.0	27.0	13.0	25.0	25.0	80.0	80.0	80.0	80.0	80.0	80.0
Total Split (%)	12.5%	22.5%	22.5%	10.8%	20.8%	20.8%	66.7%	66.7%	66.7%	66.7%	66.7%	66.7%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes						
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min
Act Effct Green (s)	9.3	9.7	9.7	13.0	7.3	7.3	88.2	88.2	88.2	88.2	88.2	88.2
Actuated g/C Ratio	0.08	0.08	0.08	0.11	0.06	0.06	0.74	0.74	0.74	0.74	0.74	0.74
v/c Ratio	0.53	0.08	0.22	0.28	0.24	0.19	0.29	0.38	0.02	0.03	0.68	0.18
Control Delay	61.1	50.9	3.2	45.1	58.2	2.3	14.8	8.7	0.9	5.9	11.1	1.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.1	50.9	3.2	45.1	58.2	2.3	14.8	8.7	0.9	5.9	11.1	1.1
LOS	E	D	A	D	E	A	B	A	A	A	B	A
Approach Delay		47.0			35.4			8.8			9.9	
Approach LOS		D			D			A			A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.68
 Intersection Signal Delay: 12.6
 Intersection LOS: B
 Intersection Capacity Utilization 66.0%
 ICU Level of Service C
 Analysis Period (min) 15


Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2040 Background AM.syn

07/16/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	120	10	40	45	25	30	35	865	20	10	1560	195
Future Volume (veh/h)	120	10	40	45	25	30	35	865	20	10	1560	195
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1752	1752	1752	1870	1870	1870	1796	1796	1796	1811	1811	1811
Adj Flow Rate, veh/h	130	11	43	49	27	33	38	940	22	11	1696	212
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	10	10	10	2	2	2	7	7	7	6	6	6
Cap, veh/h	182	96	82	177	78	66	178	2582	1151	435	2603	1161
Arrive On Green	0.06	0.05	0.05	0.03	0.04	0.04	0.76	0.76	0.76	0.76	0.76	0.76
Sat Flow, veh/h	3237	1752	1485	1781	1870	1585	226	3413	1522	565	3441	1535
Grp Volume(v), veh/h	130	11	43	49	27	33	38	940	22	11	1696	212
Grp Sat Flow(s),veh/h/ln	1618	1752	1485	1781	1870	1585	226	1706	1522	565	1721	1535
Q Serve(g_s), s	4.7	0.7	3.4	3.1	1.7	2.4	11.6	11.1	0.4	0.8	28.4	4.7
Cycle Q Clear(g_c), s	4.7	0.7	3.4	3.1	1.7	2.4	40.0	11.1	0.4	11.9	28.4	4.7
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	182	96	82	177	78	66	178	2582	1151	435	2603	1161
V/C Ratio(X)	0.71	0.11	0.53	0.28	0.35	0.50	0.21	0.36	0.02	0.03	0.65	0.18
Avail Cap(c_a), veh/h	270	321	272	220	296	251	178	2582	1151	435	2603	1161
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	55.7	53.9	55.2	52.7	55.9	56.3	16.6	4.9	3.6	6.9	7.0	4.1
Incr Delay (d2), s/veh	5.1	0.5	5.2	0.8	2.7	5.8	2.7	0.4	0.0	0.1	1.3	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.1	0.3	1.4	1.4	0.9	1.1	0.7	3.5	0.1	0.1	9.2	1.4
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	60.8	54.5	60.4	53.5	58.6	62.1	19.4	5.3	3.6	7.0	8.3	4.5
LnGrp LOS	E	D	E	D	E	E	B	A	A	A	A	A
Approach Vol, veh/h		184			109			1000			1919	
Approach Delay, s/veh		60.3			57.4			5.8			7.9	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		97.3	10.1	12.6		97.3	11.8	11.0				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		73.5	7.0	* 22		73.5	10.0	19.0				
Max Q Clear Time (g_c+I1), s		42.0	5.1	5.4		30.4	6.7	4.4				
Green Ext Time (p_c), s		9.8	0.0	0.1		22.9	0.1	0.1				

Intersection Summary

HCM 6th Ctrl Delay	11.9
HCM 6th LOS	B


Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2040 Background PM.syn

07/16/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	185	15	55	20	15	40	45	1470	75	45	975	140
Future Volume (veh/h)	185	15	55	20	15	40	45	1470	75	45	975	140
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	201	16	60	22	16	43	49	1598	82	49	1060	152
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	4	4	4
Cap, veh/h	261	168	142	157	82	70	345	2610	1164	210	2569	1146
Arrive On Green	0.08	0.09	0.09	0.02	0.04	0.04	0.73	0.73	0.73	0.73	0.73	0.73
Sat Flow, veh/h	3456	1870	1585	1781	1870	1585	461	3554	1585	289	3497	1560
Grp Volume(v), veh/h	201	16	60	22	16	43	49	1598	82	49	1060	152
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1781	1870	1585	461	1777	1585	289	1749	1560
Q Serve(g_s), s	6.9	0.9	4.3	1.4	1.0	3.2	5.4	26.0	1.7	11.8	13.9	3.4
Cycle Q Clear(g_c), s	6.9	0.9	4.3	1.4	1.0	3.2	19.3	26.0	1.7	37.8	13.9	3.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	261	168	142	157	82	70	345	2610	1164	210	2569	1146
V/C Ratio(X)	0.77	0.10	0.42	0.14	0.19	0.62	0.14	0.61	0.07	0.23	0.41	0.13
Avail Cap(c_a), veh/h	374	358	304	237	281	238	345	2610	1164	210	2569	1146
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	54.4	50.2	51.7	53.0	55.3	56.4	9.7	7.7	4.5	16.8	6.1	4.7
Incr Delay (d2), s/veh	5.9	0.2	2.0	0.4	1.1	8.6	0.9	1.1	0.1	2.6	0.5	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.2	0.5	1.8	0.6	0.5	1.4	0.6	9.0	0.6	0.9	4.7	1.1
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	60.4	50.4	53.7	53.4	56.5	64.9	10.6	8.8	4.6	19.4	6.6	4.9
LnGrp LOS	E	D	D	D	E	E	B	A	A	B	A	A
Approach Vol, veh/h		277			81			1729			1261	
Approach Delay, s/veh		58.3			60.1			8.6			6.9	
Approach LOS		E			E			A			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		94.6	8.6	16.8		94.6	14.1	11.3				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		71.5	8.0	* 23		71.5	13.0	18.0				
Max Q Clear Time (g_c+I1), s		28.0	3.4	6.3		39.8	8.9	5.2				
Green Ext Time (p_c), s		21.0	0.0	0.2		11.8	0.2	0.1				

Intersection Summary

HCM 6th Ctrl Delay	13.3
HCM 6th LOS	B

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings

1: Marksheffel Rd & Meadowbrook Pkwy

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	205	10	40	45	25	30	35	940	20	10	1645	275
Future Volume (vph)	205	10	40	45	25	30	35	940	20	10	1645	275
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm
Protected Phases	7	4		3	8			2			6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5
Total Split (s)	20.0	29.0	29.0	15.0	24.0	24.0	76.0	76.0	76.0	76.0	76.0	76.0
Total Split (%)	16.7%	24.2%	24.2%	12.5%	20.0%	20.0%	63.3%	63.3%	63.3%	63.3%	63.3%	63.3%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes						
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min
Act Effct Green (s)	13.1	12.7	12.7	13.9	7.3	7.3	84.4	84.4	84.4	84.4	84.4	84.4
Actuated g/C Ratio	0.11	0.11	0.11	0.12	0.06	0.06	0.70	0.70	0.70	0.70	0.70	0.70
v/c Ratio	0.64	0.06	0.19	0.26	0.24	0.19	0.40	0.43	0.02	0.04	0.75	0.26
Control Delay	59.8	47.7	2.4	41.0	58.2	2.3	27.4	9.9	1.2	7.6	15.0	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	59.8	47.7	2.4	41.0	58.2	2.3	27.4	9.9	1.2	7.6	15.0	1.4
LOS	E	D	A	D	E	A	C	A	A	A	B	A
Approach Delay		50.4			33.6			10.3			13.0	
Approach LOS		D			C			B			B	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.75
 Intersection Signal Delay: 15.7
 Intersection LOS: B
 Intersection Capacity Utilization 68.4%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2040 Total AM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	205	10	40	45	25	30	35	940	20	10	1645	275
Future Volume (veh/h)	205	10	40	45	25	30	35	940	20	10	1645	275
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1752	1752	1752	1870	1870	1870	1796	1796	1796	1811	1811	1811
Adj Flow Rate, veh/h	223	11	43	49	27	33	38	1022	22	11	1788	299
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	10	10	10	2	2	2	7	7	7	6	6	6
Cap, veh/h	281	150	127	178	78	66	141	2477	1105	379	2498	1114
Arrive On Green	0.09	0.09	0.09	0.03	0.04	0.04	0.73	0.73	0.73	0.73	0.73	0.73
Sat Flow, veh/h	3237	1752	1485	1781	1870	1585	190	3413	1522	523	3441	1535
Grp Volume(v), veh/h	223	11	43	49	27	33	38	1022	22	11	1788	299
Grp Sat Flow(s),veh/h/ln	1618	1752	1485	1781	1870	1585	190	1706	1522	523	1721	1535
Q Serve(g_s), s	8.1	0.7	3.3	3.1	1.7	2.4	17.1	14.1	0.5	1.0	35.6	8.0
Cycle Q Clear(g_c), s	8.1	0.7	3.3	3.1	1.7	2.4	52.7	14.1	0.5	15.1	35.6	8.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	281	150	127	178	78	66	141	2477	1105	379	2498	1114
V/C Ratio(X)	0.79	0.07	0.34	0.28	0.35	0.50	0.27	0.41	0.02	0.03	0.72	0.27
Avail Cap(c_a), veh/h	405	350	297	250	281	238	141	2477	1105	379	2498	1114
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	53.7	50.5	51.7	52.7	55.9	56.3	24.4	6.4	4.6	9.4	9.4	5.6
Incr Delay (d2), s/veh	6.8	0.2	1.6	0.8	2.7	5.8	4.6	0.5	0.0	0.1	1.8	0.6
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.6	0.3	1.3	1.4	0.9	1.1	0.9	4.7	0.1	0.1	12.2	2.5
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	60.5	50.7	53.3	53.5	58.6	62.1	29.0	6.9	4.6	9.5	11.2	6.2
LnGrp LOS	E	D	D	D	E	E	C	A	A	A	B	A
Approach Vol, veh/h		277			109			1082			2098	
Approach Delay, s/veh		59.0			57.4			7.7			10.5	
Approach LOS		E			E			A			B	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		93.6	10.2	16.2		93.6	15.4	11.0				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		69.5	9.0	* 24		69.5	15.0	18.0				
Max Q Clear Time (g_c+I1), s		54.7	5.1	5.3		37.6	10.1	4.4				
Green Ext Time (p_c), s		7.6	0.0	0.1		21.1	0.3	0.1				

Intersection Summary

HCM 6th Ctrl Delay	14.8
HCM 6th LOS	B

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings

2040 Total PM.syn

1: Marksheffel Rd & Meadowbrook Pkwy

09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	260	15	55	20	15	40	45	1550	75	45	1100	225
Future Volume (vph)	260	15	55	20	15	40	45	1550	75	45	1100	225
Turn Type	Prot	NA	Perm	pm+pt	NA	Perm	Perm	NA	Perm	Perm	NA	Perm
Protected Phases	7	4		3	8			2			6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	2	2	2	6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	23.0	23.0	11.0	24.0	24.0	24.5	24.5	24.5	24.5	24.5	24.5
Total Split (s)	21.0	29.0	29.0	16.0	24.0	24.0	75.0	75.0	75.0	75.0	75.0	75.0
Total Split (%)	17.5%	24.2%	24.2%	13.3%	20.0%	20.0%	62.5%	62.5%	62.5%	62.5%	62.5%	62.5%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.5	1.5	1.5	2.5	2.5	2.5	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes	Yes						
Recall Mode	None	None	None	None	None	None	C-Min	C-Min	C-Min	C-Min	C-Min	C-Min
Act Effct Green (s)	14.3	16.6	16.6	12.3	6.6	6.6	83.8	83.8	83.8	83.8	83.8	83.8
Actuated g/C Ratio	0.12	0.14	0.14	0.10	0.06	0.06	0.70	0.70	0.70	0.70	0.70	0.70
v/c Ratio	0.69	0.06	0.20	0.13	0.16	0.26	0.19	0.68	0.07	0.43	0.49	0.21
Control Delay	59.8	46.3	5.9	38.5	56.9	4.3	7.8	12.5	2.5	24.8	10.0	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	59.8	46.3	5.9	38.5	56.9	4.3	7.8	12.5	2.5	24.8	10.0	1.4
LOS	E	D	A	D	E	A	A	B	A	C	A	A
Approach Delay		50.2			24.0			11.9			9.1	
Approach LOS		D			C			B			A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.69
 Intersection Signal Delay: 14.7
 Intersection LOS: B
 Intersection Capacity Utilization 69.0%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 1: Marksheffel Rd & Meadowbrook Pkwy



HCM 6th Signalized Intersection Summary
 1: Marksheffel Rd & Meadowbrook Pkwy

2040 Total PM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	260	15	55	20	15	40	45	1550	75	45	1100	225
Future Volume (veh/h)	260	15	55	20	15	40	45	1550	75	45	1100	225
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	283	16	60	22	16	43	49	1685	82	49	1196	245
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	4	4	4
Cap, veh/h	346	214	181	157	82	70	267	2523	1125	179	2483	1108
Arrive On Green	0.10	0.11	0.11	0.02	0.04	0.04	0.71	0.71	0.71	0.71	0.71	0.71
Sat Flow, veh/h	3456	1870	1585	1781	1870	1585	370	3554	1585	266	3497	1560
Grp Volume(v), veh/h	283	16	60	22	16	43	49	1685	82	49	1196	245
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1781	1870	1585	370	1777	1585	266	1749	1560
Q Serve(g_s), s	9.6	0.9	4.2	1.4	1.0	3.2	8.1	31.4	1.9	14.9	18.1	6.5
Cycle Q Clear(g_c), s	9.6	0.9	4.2	1.4	1.0	3.2	26.2	31.4	1.9	46.3	18.1	6.5
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	346	214	181	157	82	70	267	2523	1125	179	2483	1108
V/C Ratio(X)	0.82	0.07	0.33	0.14	0.19	0.62	0.18	0.67	0.07	0.27	0.48	0.22
Avail Cap(c_a), veh/h	461	374	317	267	281	238	267	2523	1125	179	2483	1108
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	52.9	47.5	48.9	53.0	55.3	56.4	13.4	9.6	5.3	22.4	7.7	6.0
Incr Delay (d2), s/veh	8.3	0.1	1.1	0.4	1.1	8.6	1.5	1.4	0.1	3.7	0.7	0.5
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	4.6	0.4	1.7	0.6	0.5	1.4	0.8	11.4	0.6	1.1	6.4	2.1
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	61.2	47.6	50.0	53.4	56.5	64.9	14.9	11.0	5.4	26.1	8.3	6.4
LnGrp LOS	E	D	D	D	E	E	B	B	A	C	A	A
Approach Vol, veh/h		359			81			1816			1490	
Approach Delay, s/veh		58.8			60.1			10.9			8.6	
Approach LOS		E			E			B			A	
Timer - Assigned Phs		2	3	4		6	7	8				
Phs Duration (G+Y+Rc), s		91.7	8.6	19.7		91.7	17.0	11.3				
Change Period (Y+Rc), s		6.5	6.0	* 6		6.5	5.0	6.0				
Max Green Setting (Gmax), s		68.5	10.0	* 24		68.5	16.0	18.0				
Max Q Clear Time (g_c+I1), s		33.4	3.4	6.2		48.3	11.6	5.2				
Green Ext Time (p_c), s		20.5	0.0	0.2		11.2	0.4	0.1				

Intersection Summary

HCM 6th Ctrl Delay	15.6
HCM 6th LOS	B

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings
2: US-24 & Marksheffel Rd




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Configurations	↙	↑↑	↗	↙	↑↑	↗	↙↗	↑↑	↙	↑↑	↗
Traffic Volume (vph)	8	629	626	1	403	48	298	432	251	984	16
Future Volume (vph)	8	629	626	1	403	48	298	432	251	984	16
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2	1	6	
Permitted Phases			Free			Free			6		Free
Detector Phase	7	4		3	8		5	2	1	6	
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0	5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0	12.0	12.0	
Total Split (s)	10.5	44.5		11.5	45.5		31.0	41.0	23.0	33.0	
Total Split (%)	8.8%	37.1%		9.6%	37.9%		25.8%	34.2%	19.2%	27.5%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5	5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5	1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0	7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max	None	C-Max	
Act Effct Green (s)	8.1	30.5	120.0	5.6	27.6	120.0	17.4	54.3	63.2	50.1	120.0
Actuated g/C Ratio	0.07	0.25	1.00	0.05	0.23	1.00	0.14	0.45	0.53	0.42	1.00
v/c Ratio	0.08	0.78	0.44	0.01	0.55	0.03	0.70	0.32	0.48	0.72	0.01
Control Delay	42.2	40.0	1.5	49.0	30.1	0.0	50.3	43.0	16.2	34.7	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	42.2	40.0	1.5	49.0	30.1	0.0	50.3	43.0	16.2	34.7	0.0
LOS	D	D	A	D	C	A	D	D	B	C	A
Approach Delay		20.9			27.0			46.0		30.6	
Approach LOS		C			C			D		C	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.78
 Intersection Signal Delay: 29.9
 Intersection Capacity Utilization 69.3%
 Analysis Period (min) 15
 Intersection LOS: C
 ICU Level of Service C

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2020 Adjusted Existing AM.syn
06/24/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	8	629	626	1	403	48	298	432	0	251	984	16
Future Volume (veh/h)	8	629	626	1	403	48	298	432	0	251	984	16
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	9	676	0	1	443	0	320	465	0	267	1047	0
Peak Hour Factor	0.93	0.93	0.93	0.91	0.91	0.91	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	118	816		2	570		388	1456		561	1483	
Arrive On Green	0.07	0.24	0.00	0.00	0.16	0.00	0.12	0.44	0.00	0.10	0.42	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	3300	1472	1753	3497	1560
Grp Volume(v), veh/h	9	676	0	1	443	0	320	465	0	267	1047	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1650	1472	1753	1749	1560
Q Serve(g_s), s	0.6	22.4	0.0	0.1	14.5	0.0	11.7	11.0	0.0	10.2	29.5	0.0
Cycle Q Clear(g_c), s	0.6	22.4	0.0	0.1	14.5	0.0	11.7	11.0	0.0	10.2	29.5	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	118	816		2	570		388	1456		561	1483	
V/C Ratio(X)	0.08	0.83		0.41	0.78		0.82	0.32		0.48	0.71	
Avail Cap(c_a), veh/h	118	1118		74	1146		642	1456		613	1483	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	52.4	43.5	0.0	59.9	48.2	0.0	51.5	21.8	0.0	16.3	28.4	0.0
Incr Delay (d2), s/veh	0.3	3.9	0.0	85.9	2.3	0.0	4.4	0.6	0.0	0.6	2.9	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	9.9	0.0	0.1	6.5	0.0	4.9	4.4	0.0	4.1	12.8	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	52.6	47.3	0.0	145.8	50.5	0.0	55.9	22.4	0.0	16.9	31.3	0.0
LnGrp LOS	D	D		F	D		E	C		B	C	
Approach Vol, veh/h		685	A		444	A		785	A		1314	A
Approach Delay, s/veh		47.4			50.7			36.1			28.3	
Approach LOS		D			D			D			C	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	19.5	59.9	6.7	33.9	21.5	57.9	14.7	25.9				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	16.0	34.0	5.0	39.0	24.0	26.0	5.0	* 39				
Max Q Clear Time (g_c+I1), s	12.2	13.0	2.1	24.4	13.7	31.5	2.6	16.5				
Green Ext Time (p_c), s	0.3	3.1	0.0	4.1	0.8	0.0	0.0	3.0				

Intersection Summary

HCM 6th Ctrl Delay	37.3
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd


2020 Adjusted Existing PM.syn
06/24/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	13	451	385	10	677	145	507	897	6	114	428	12
Future Volume (vph)	13	451	385	10	677	145	507	897	6	114	428	12
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0		12.0	12.0	
Total Split (s)	10.5	49.5		11.5	50.5		44.0	47.0		12.0	15.0	
Total Split (%)	8.8%	41.3%		9.6%	42.1%		36.7%	39.2%		10.0%	12.5%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5		5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5		1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0		7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effct Green (s)	6.6	34.2	120.0	8.5	32.9	120.0	26.1	51.9	120.0	44.7	35.2	120.0
Actuated g/C Ratio	0.06	0.28	1.00	0.07	0.27	1.00	0.22	0.43	1.00	0.37	0.29	1.00
v/c Ratio	0.15	0.50	0.27	0.09	0.77	0.10	0.79	0.69	0.00	0.45	0.45	0.01
Control Delay	50.7	36.6	0.6	35.8	34.9	0.1	39.5	49.1	0.0	28.1	40.0	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	50.7	36.6	0.6	35.8	34.9	0.1	39.5	49.1	0.0	28.1	40.0	0.0
LOS	D	D	A	D	C	A	D	D	A	C	D	A
Approach Delay		20.5			28.8			45.5			36.7	
Approach LOS		C			C			D			D	

Intersection Summary


Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.79
 Intersection Signal Delay: 34.5
 Intersection LOS: C
 Intersection Capacity Utilization 66.9%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2020 Adjusted Existing PM.syn
06/24/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↗	↘	↑↑	↗
Traffic Volume (veh/h)	13	451	385	10	677	145	507	897	6	114	428	12
Future Volume (veh/h)	13	451	385	10	677	145	507	897	6	114	428	12
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	14	485	0	11	744	0	545	965	0	121	455	0
Peak Hour Factor	0.93	0.93	0.93	0.91	0.91	0.91	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	27	619		179	906		631	1521		269	1070	
Arrive On Green	0.02	0.18	0.00	0.10	0.26	0.00	0.20	0.46	0.00	0.04	0.31	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	3300	1472	1753	3497	1560
Grp Volume(v), veh/h	14	485	0	11	744	0	545	965	0	121	455	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1650	1472	1753	1749	1560
Q Serve(g_s), s	1.0	16.1	0.0	0.7	23.9	0.0	19.7	26.7	0.0	5.0	12.5	0.0
Cycle Q Clear(g_c), s	1.0	16.1	0.0	0.7	23.9	0.0	19.7	26.7	0.0	5.0	12.5	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	27	619		179	906		631	1521		269	1070	
V/C Ratio(X)	0.52	0.78		0.06	0.82		0.86	0.63		0.45	0.43	
Avail Cap(c_a), veh/h	72	1262		179	1293		990	1521		269	1070	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.6	47.0	0.0	48.8	42.0	0.0	46.7	24.6	0.0	28.8	33.2	0.0
Incr Delay (d2), s/veh	14.8	2.2	0.0	0.1	2.9	0.0	5.0	2.0	0.0	1.2	1.2	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	7.1	0.0	0.3	10.7	0.0	8.3	10.7	0.0	0.5	5.5	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	73.5	49.2	0.0	48.9	44.9	0.0	51.6	26.7	0.0	30.0	34.5	0.0
LnGrp LOS	E	D		D	D		D	C		C	C	
Approach Vol, veh/h		499	A		755	A		1510	A		576	A
Approach Delay, s/veh		49.9			45.0			35.7			33.5	
Approach LOS		D			D			D			C	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	12.0	62.3	18.6	27.1	30.6	43.7	8.4	37.3				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	5.0	40.0	5.0	44.0	37.0	8.0	5.0	* 44				
Max Q Clear Time (g_c+I1), s	7.0	28.7	2.7	18.1	21.7	14.5	3.0	25.9				
Green Ext Time (p_c), s	0.0	5.2	0.0	3.4	1.9	0.0	0.0	5.0				

Intersection Summary

HCM 6th Ctrl Delay	39.5
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↘	↑↑	↗
Traffic Volume (vph)	10	670	665	5	430	55	320	460	270	1045	20
Future Volume (vph)	10	670	665	5	430	55	320	460	270	1045	20
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2	1	6	
Permitted Phases			Free			Free			6		Free
Detector Phase	7	4		3	8		5	2	1	6	
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0	5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0	12.0	12.0	
Total Split (s)	10.5	45.5		11.5	46.5		32.0	38.0	25.0	31.0	
Total Split (%)	8.8%	37.9%		9.6%	38.8%		26.7%	31.7%	20.8%	25.8%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5	5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5	1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0	7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max	None	C-Max	
Act Effct Green (s)	8.3	32.5	120.0	5.7	29.3	120.0	18.3	51.4	61.5	47.3	120.0
Actuated g/C Ratio	0.07	0.27	1.00	0.05	0.24	1.00	0.15	0.43	0.51	0.39	1.00
v/c Ratio	0.09	0.78	0.47	0.06	0.55	0.04	0.72	0.36	0.54	0.81	0.01
Control Delay	41.9	40.2	1.7	44.6	27.6	0.0	50.5	47.7	18.3	39.7	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	41.9	40.2	1.7	44.6	27.6	0.0	50.5	47.7	18.3	39.7	0.0
LOS	D	D	A	D	C	A	D	D	B	D	A
Approach Delay		21.2			24.7			48.8		34.8	
Approach LOS		C			C			D		C	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.81
 Intersection Signal Delay: 31.6
 Intersection LOS: C
 Intersection Capacity Utilization 72.8%
 ICU Level of Service C
 Analysis Period (min) 15


Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
 2: US-24 & Marksheffel Rd

2025 Background AM.syn

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	10	670	665	5	430	55	320	460	0	270	1045	20
Future Volume (veh/h)	10	670	665	5	430	55	320	460	0	270	1045	20
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	11	720	0	5	473	0	344	495	0	287	1112	0
Peak Hour Factor	0.93	0.93	0.93	0.91	0.91	0.91	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	133	863		11	605		414	1357		535	1390	
Arrive On Green	0.08	0.25	0.00	0.01	0.17	0.00	0.13	0.41	0.00	0.12	0.40	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	3300	1472	1753	3497	1560
Grp Volume(v), veh/h	11	720	0	5	473	0	344	495	0	287	1112	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1650	1472	1753	1749	1560
Q Serve(g_s), s	0.7	23.8	0.0	0.3	15.4	0.0	12.5	12.5	0.0	11.5	33.7	0.0
Cycle Q Clear(g_c), s	0.7	23.8	0.0	0.3	15.4	0.0	12.5	12.5	0.0	11.5	33.7	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	133	863		11	605		414	1357		535	1390	
V/C Ratio(X)	0.08	0.83		0.44	0.78		0.83	0.36		0.54	0.80	
Avail Cap(c_a), veh/h	133	1147		74	1175		669	1357		596	1390	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	51.4	42.6	0.0	59.4	47.5	0.0	51.0	24.5	0.0	17.8	32.0	0.0
Incr Delay (d2), s/veh	0.3	4.2	0.0	24.8	2.2	0.0	4.8	0.8	0.0	0.8	4.9	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	10.6	0.0	0.2	6.9	0.0	5.3	5.0	0.0	4.7	15.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	51.7	46.7	0.0	84.2	49.8	0.0	55.8	25.2	0.0	18.6	36.9	0.0
LnGrp LOS	D	D		F	D		E	C		B	D	
Approach Vol, veh/h		731	A		478	A		839	A		1399	A
Approach Delay, s/veh		46.8			50.2			37.8			33.1	
Approach LOS		D			D			D			C	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	20.8	56.3	7.3	35.6	22.5	54.7	15.8	27.1				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	18.0	31.0	5.0	40.0	25.0	24.0	5.0	* 40				
Max Q Clear Time (g_c+I1), s	13.5	14.5	2.3	25.8	14.5	35.7	2.7	17.4				
Green Ext Time (p_c), s	0.4	3.0	0.0	4.3	0.9	0.0	0.0	3.2				

Intersection Summary

HCM 6th Ctrl Delay	39.5
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.


Timings
2: US-24 & Marksheffel Rd

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	15	480	410	15	720	155	540	955	10	125	455	15
Future Volume (vph)	15	480	410	15	720	155	540	955	10	125	455	15
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0		12.0	12.0	
Total Split (s)	10.5	51.2		11.8	52.5		45.0	44.0		13.0	12.0	
Total Split (%)	8.8%	42.7%		9.8%	43.8%		37.5%	36.7%		10.8%	10.0%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5		5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5		1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0		7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	6.8	30.8	120.0	10.8	34.3	120.0	25.1	49.4	120.0	45.3	34.8	120.0
Actuated g/C Ratio	0.06	0.26	1.00	0.09	0.29	1.00	0.21	0.41	1.00	0.38	0.29	1.00
v/c Ratio	0.17	0.59	0.29	0.10	0.78	0.11	0.78	0.68	0.01	0.52	0.49	0.01
Control Delay	49.7	42.1	0.6	31.0	39.0	0.1	34.3	46.3	0.0	31.3	40.9	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	49.7	42.1	0.6	31.0	39.0	0.1	34.3	46.3	0.0	31.3	40.9	0.0
LOS	D	D	A	C	D	A	C	D	A	C	D	A
Approach Delay		23.4			32.1			41.7			37.9	
Approach LOS		C			C			D			D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.78
 Intersection Signal Delay: 34.5
 Intersection LOS: C
 Intersection Capacity Utilization 70.3%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2025 Background PM.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↗	↘	↑↑	↗
Traffic Volume (veh/h)	15	480	410	15	720	155	540	955	10	125	455	15
Future Volume (veh/h)	15	480	410	15	720	155	540	955	10	125	455	15
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1856	1856	1856
Adj Flow Rate, veh/h	17	533	0	16	783	0	557	985	0	137	500	0
Peak Hour Factor	0.90	0.90	0.90	0.92	0.92	0.92	0.97	0.97	0.97	0.91	0.91	0.91
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	3	3	3
Cap, veh/h	32	678		182	954		652	1559		275	1057	
Arrive On Green	0.02	0.19	0.00	0.10	0.27	0.00	0.19	0.44	0.00	0.05	0.30	0.00
Sat Flow, veh/h	1767	3526	1572	1781	3554	1585	3456	3554	1585	1767	3526	1572
Grp Volume(v), veh/h	17	533	0	16	783	0	557	985	0	137	500	0
Grp Sat Flow(s),veh/h/ln	1767	1763	1572	1781	1777	1585	1728	1777	1585	1767	1763	1572
Q Serve(g_s), s	1.1	17.3	0.0	1.0	24.8	0.0	18.7	25.8	0.0	6.0	13.9	0.0
Cycle Q Clear(g_c), s	1.1	17.3	0.0	1.0	24.8	0.0	18.7	25.8	0.0	6.0	13.9	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	32	678		182	954		652	1559		275	1057	
V/C Ratio(X)	0.53	0.79		0.09	0.82		0.85	0.63		0.50	0.47	
Avail Cap(c_a), veh/h	74	1343		182	1362		1094	1559		275	1057	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.4	46.1	0.0	48.8	41.2	0.0	47.1	26.2	0.0	28.7	34.3	0.0
Incr Delay (d2), s/veh	13.2	2.1	0.0	0.2	2.8	0.0	3.5	2.0	0.0	1.4	1.5	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.6	7.7	0.0	0.4	11.2	0.0	8.3	11.2	0.0	2.9	6.2	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	71.6	48.2	0.0	49.0	44.0	0.0	50.6	28.1	0.0	30.1	35.8	0.0
LnGrp LOS	E	D		D	D		D	C		C	D	
Approach Vol, veh/h		550	A		799	A		1542	A		637	A
Approach Delay, s/veh		48.9			44.1			36.2			34.6	
Approach LOS		D			D			D			C	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	13.0	59.6	18.8	28.6	29.6	43.0	8.7	38.7				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	6.0	37.0	5.3	45.7	38.0	5.0	5.0	* 46				
Max Q Clear Time (g_c+I1), s	8.0	27.8	3.0	19.3	20.7	15.9	3.1	26.8				
Green Ext Time (p_c), s	0.0	4.5	0.0	3.8	1.9	0.0	0.0	5.4				

Intersection Summary

HCM 6th Ctrl Delay	39.7
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd


2025 Total AM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	10	755	665	5	505	80	320	490	195	300	1075	20
Future Volume (vph)	10	755	665	5	505	80	320	490	195	300	1075	20
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0		12.0	12.0	
Total Split (s)	10.5	44.5		11.5	45.5		28.0	37.0		27.0	36.0	
Total Split (%)	8.8%	37.1%		9.6%	37.9%		23.3%	30.8%		22.5%	30.0%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5		5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5		1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0		7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effct Green (s)	7.3	34.9	120.0	5.4	32.6	120.0	17.8	46.7	120.0	62.0	45.5	120.0
Actuated g/C Ratio	0.06	0.29	1.00	0.04	0.27	1.00	0.15	0.39	1.00	0.52	0.38	1.00
v/c Ratio	0.11	0.82	0.47	0.06	0.58	0.06	0.73	0.42	0.14	0.63	0.87	0.01
Control Delay	44.2	40.1	1.4	56.2	38.6	0.1	46.6	58.8	0.2	21.1	44.3	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	44.2	40.1	1.4	56.2	38.6	0.1	46.6	58.8	0.2	21.1	44.3	0.0
LOS	D	D	A	E	D	A	D	E	A	C	D	A
Approach Delay		22.2			33.5			43.5			38.7	
Approach LOS		C			C			D			D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.87
 Intersection Signal Delay: 33.7
 Intersection LOS: C
 Intersection Capacity Utilization 76.0%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary

2: US-24 & Marksheffel Rd

2025 Total AM.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	10	755	665	5	505	80	320	490	195	300	1075	20
Future Volume (veh/h)	10	755	665	5	505	80	320	490	195	300	1075	20
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	11	812	0	5	549	0	344	527	0	319	1144	0
Peak Hour Factor	0.93	0.93	0.93	0.92	0.92	0.92	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	133	944		11	688		408	1227		507	1313	
Arrive On Green	0.08	0.27	0.00	0.01	0.20	0.00	0.13	0.37	0.00	0.13	0.38	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	3300	1472	1753	3497	1560
Grp Volume(v), veh/h	11	812	0	5	549	0	344	527	0	319	1144	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1650	1472	1753	1749	1560
Q Serve(g_s), s	0.7	26.9	0.0	0.3	17.8	0.0	12.6	14.3	0.0	13.3	36.4	0.0
Cycle Q Clear(g_c), s	0.7	26.9	0.0	0.3	17.8	0.0	12.6	14.3	0.0	13.3	36.4	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	133	944		11	688		408	1227		507	1313	
V/C Ratio(X)	0.08	0.86		0.44	0.80		0.84	0.43		0.63	0.87	
Avail Cap(c_a), veh/h	133	1118		74	1146		562	1227		570	1313	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	51.4	41.4	0.0	59.4	46.0	0.0	51.2	28.2	0.0	19.5	34.8	0.0
Incr Delay (d2), s/veh	0.3	6.1	0.0	24.8	2.2	0.0	8.3	1.1	0.0	1.8	8.1	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	12.1	0.0	0.2	8.0	0.0	5.5	5.8	0.0	5.6	16.7	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	51.7	47.5	0.0	84.2	48.2	0.0	59.5	29.3	0.0	21.3	42.9	0.0
LnGrp LOS	D	D		F	D		E	C		C	D	
Approach Vol, veh/h		823	A		554	A		871	A		1463	A
Approach Delay, s/veh		47.5			48.6			41.2			38.2	
Approach LOS		D			D			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	22.7	51.6	7.3	38.4	22.3	52.1	15.8	29.9				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	20.0	30.0	5.0	39.0	21.0	29.0	5.0	* 39				
Max Q Clear Time (g_c+l1), s	15.3	16.3	2.3	28.9	14.6	38.4	2.7	19.8				
Green Ext Time (p_c), s	0.4	3.0	0.0	4.0	0.7	0.0	0.0	3.6				

Intersection Summary

HCM 6th Ctrl Delay	42.5
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd


2025 Total PM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	15	605	410	15	800	185	540	980	305	170	485	15
Future Volume (vph)	15	605	410	15	800	185	540	980	305	170	485	15
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0		12.0	12.0	
Total Split (s)	10.5	50.2		11.8	51.5		41.0	46.0		12.0	17.0	
Total Split (%)	8.8%	41.8%		9.8%	42.9%		34.2%	38.3%		10.0%	14.2%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5		5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5		1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0		7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	6.1	34.8	120.0	9.3	37.4	120.0	24.9	41.1	120.0	47.9	32.4	120.0
Actuated g/C Ratio	0.05	0.29	1.00	0.08	0.31	1.00	0.21	0.34	1.00	0.40	0.27	1.00
v/c Ratio	0.18	0.65	0.28	0.12	0.79	0.13	0.78	0.83	0.20	0.61	0.56	0.01
Control Delay	50.2	38.8	0.4	52.5	53.6	0.1	26.7	49.8	0.0	40.3	43.5	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	50.2	38.8	0.4	52.5	53.6	0.1	26.7	49.8	0.0	40.3	43.5	0.0
LOS	D	D	A	D	D	A	C	D	A	D	D	A
Approach Delay		23.7			43.7			34.7			41.7	
Approach LOS		C			D			C			D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.83
 Intersection Signal Delay: 35.2
 Intersection LOS: D
 Intersection Capacity Utilization 75.7%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2025 Total PM.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↗	↘	↑↑	↗
Traffic Volume (veh/h)	15	605	410	15	800	185	540	980	305	170	485	15
Future Volume (veh/h)	15	605	410	15	800	185	540	980	305	170	485	15
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1856	1856	1856
Adj Flow Rate, veh/h	16	658	0	16	870	0	557	1010	0	185	527	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.92	0.92	0.92
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	3	3	3
Cap, veh/h	30	816		154	1038		648	1507		242	981	
Arrive On Green	0.02	0.23	0.00	0.09	0.29	0.00	0.19	0.42	0.00	0.04	0.28	0.00
Sat Flow, veh/h	1767	3526	1572	1781	3554	1585	3456	3554	1585	1767	3526	1572
Grp Volume(v), veh/h	16	658	0	16	870	0	557	1010	0	185	527	0
Grp Sat Flow(s),veh/h/ln	1767	1763	1572	1781	1777	1585	1728	1777	1585	1767	1763	1572
Q Serve(g_s), s	1.1	21.2	0.0	1.0	27.5	0.0	18.7	27.4	0.0	5.0	15.2	0.0
Cycle Q Clear(g_c), s	1.1	21.2	0.0	1.0	27.5	0.0	18.7	27.4	0.0	5.0	15.2	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	30	816		154	1038		648	1507		242	981	
V/C Ratio(X)	0.53	0.81		0.10	0.84		0.86	0.67		0.77	0.54	
Avail Cap(c_a), veh/h	74	1313		154	1333		979	1507		242	981	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.5	43.6	0.0	50.6	39.8	0.0	47.2	27.8	0.0	38.9	36.8	0.0
Incr Delay (d2), s/veh	13.3	2.0	0.0	0.3	3.9	0.0	5.1	2.4	0.0	13.6	2.1	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.6	9.4	0.0	0.5	12.5	0.0	8.5	12.0	0.0	3.9	6.9	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	71.8	45.5	0.0	50.9	43.7	0.0	52.3	30.2	0.0	52.4	38.9	0.0
LnGrp LOS	E	D		D	D		D	C		D	D	
Approach Vol, veh/h		674	A		886	A		1567	A		712	A
Approach Delay, s/veh		46.2			43.8			38.0			42.4	
Approach LOS		D			D			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	12.0	57.9	16.8	33.3	29.5	40.4	8.6	41.5				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	5.0	39.0	5.3	44.7	34.0	10.0	5.0	* 45				
Max Q Clear Time (g_c+I1), s	7.0	29.4	3.0	23.2	20.7	17.2	3.1	29.5				
Green Ext Time (p_c), s	0.0	4.8	0.0	4.6	1.8	0.0	0.0	5.5				

Intersection Summary

HCM 6th Ctrl Delay	41.6
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↘	↑↑	↗
Traffic Volume (vph)	15	795	790	5	510	65	380	550	320	1240	25
Future Volume (vph)	15	795	790	5	510	65	380	550	320	1240	25
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2	1	6	
Permitted Phases			Free			Free			6		Free
Detector Phase	7	4		3	8		5	2	1	6	
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0	5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0	12.0	12.0	
Total Split (s)	11.0	36.5		11.5	37.0		23.0	41.0	31.0	49.0	
Total Split (%)	9.2%	30.4%		9.6%	30.8%		19.2%	34.2%	25.8%	40.8%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5	5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5	1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0	7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max	None	C-Max	
Act Effct Green (s)	6.1	33.0	120.0	5.0	29.5	120.0	19.4	47.3	63.5	45.8	120.0
Actuated g/C Ratio	0.05	0.28	1.00	0.04	0.25	1.00	0.16	0.39	0.53	0.38	1.00
v/c Ratio	0.18	0.91	0.56	0.07	0.64	0.05	0.81	0.46	0.68	1.00	0.02
Control Delay	51.8	48.6	2.5	61.6	45.3	0.0	61.9	30.5	21.0	61.3	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.8	48.6	2.5	61.6	45.3	0.0	61.9	30.5	21.0	61.3	0.0
LOS	D	D	A	E	D	A	E	C	C	E	A
Approach Delay		25.8			40.4			43.3		52.2	
Approach LOS		C			D			D		D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 130
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.00
 Intersection Signal Delay: 40.0
 Intersection Capacity Utilization 83.3%
 Analysis Period (min) 15

Intersection LOS: D
 ICU Level of Service E


Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
 2: US-24 & Marksheffel Rd

2040 Background AM.syn

07/16/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↗	↘	↑↑	↗
Traffic Volume (veh/h)	15	795	790	5	510	65	380	550	0	320	1240	25
Future Volume (veh/h)	15	795	790	5	510	65	380	550	0	320	1240	25
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	16	855	0	5	554	0	409	591	0	340	1319	0
Peak Hour Factor	0.93	0.93	0.93	0.92	0.92	0.92	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	114	889		11	670		428	1255		502	1347	
Arrive On Green	0.07	0.26	0.00	0.01	0.19	0.00	0.13	0.38	0.00	0.14	0.39	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	3300	1472	1753	3497	1560
Grp Volume(v), veh/h	16	855	0	5	554	0	409	591	0	340	1319	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1650	1472	1753	1749	1560
Q Serve(g_s), s	1.0	29.4	0.0	0.3	18.1	0.0	15.2	16.2	0.0	13.9	44.7	0.0
Cycle Q Clear(g_c), s	1.0	29.4	0.0	0.3	18.1	0.0	15.2	16.2	0.0	13.9	44.7	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	114	889		11	670		428	1255		502	1347	
V/C Ratio(X)	0.14	0.96		0.44	0.83		0.96	0.47		0.68	0.98	
Avail Cap(c_a), veh/h	114	889		74	896		428	1255		610	1347	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	52.8	43.9	0.0	59.4	46.7	0.0	51.6	28.1	0.0	19.1	36.4	0.0
Incr Delay (d2), s/veh	0.6	21.4	0.0	24.8	4.8	0.0	32.3	1.3	0.0	2.3	20.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	15.0	0.0	0.2	8.4	0.0	8.0	6.6	0.0	5.9	22.4	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	53.4	65.3	0.0	84.2	51.5	0.0	83.9	29.3	0.0	21.4	56.4	0.0
LnGrp LOS	D	E		F	D		F	C		C	E	
Approach Vol, veh/h		871	A		559	A		1000	A		1659	A
Approach Delay, s/veh		65.1			51.8			51.7			49.2	
Approach LOS		E			D			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	23.6	52.6	7.3	36.5	23.0	53.2	14.5	29.3				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	24.0	34.0	5.0	31.0	16.0	42.0	5.5	* 31				
Max Q Clear Time (g_c+l1), s	15.9	18.2	2.3	31.4	17.2	46.7	3.0	20.1				
Green Ext Time (p_c), s	0.7	3.6	0.0	0.0	0.0	0.0	0.0	2.7				

Intersection Summary

HCM 6th Ctrl Delay	53.5
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2040 Background PM.syn
07/16/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	20	570	485	15	855	185	640	1135	10	145	545	20
Future Volume (veh/h)	20	570	485	15	855	185	640	1135	10	145	545	20
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1856	1856	1856
Adj Flow Rate, veh/h	22	620	0	16	929	0	660	1170	0	158	592	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.92	0.92	0.92
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	3	3	3
Cap, veh/h	38	763		195	1050		764	1479		195	834	
Arrive On Green	0.02	0.22	0.00	0.11	0.30	0.00	0.22	0.42	0.00	0.04	0.24	0.00
Sat Flow, veh/h	1767	3526	1572	1781	3554	1585	3456	3554	1585	1767	3526	1572
Grp Volume(v), veh/h	22	620	0	16	929	0	660	1170	0	158	592	0
Grp Sat Flow(s),veh/h/ln	1767	1763	1572	1781	1777	1585	1728	1777	1585	1767	1763	1572
Q Serve(g_s), s	1.5	20.1	0.0	1.0	29.9	0.0	22.1	34.4	0.0	5.0	18.5	0.0
Cycle Q Clear(g_c), s	1.5	20.1	0.0	1.0	29.9	0.0	22.1	34.4	0.0	5.0	18.5	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	38	763		195	1050		764	1479		195	834	
V/C Ratio(X)	0.57	0.81		0.08	0.88		0.86	0.79		0.81	0.71	
Avail Cap(c_a), veh/h	74	1137		195	1155		1296	1479		195	834	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.2	44.7	0.0	48.0	40.3	0.0	45.0	30.5	0.0	42.6	42.0	0.0
Incr Delay (d2), s/veh	12.9	2.8	0.0	0.2	7.9	0.0	3.3	4.4	0.0	21.8	5.1	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.8	9.0	0.0	0.4	14.1	0.0	9.8	15.4	0.0	3.5	8.6	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	71.0	47.6	0.0	48.2	48.2	0.0	48.3	34.9	0.0	64.4	47.1	0.0
LnGrp LOS	E	D		D	D		D	C		E	D	
Approach Vol, veh/h		642	A		945	A		1830	A		750	A
Approach Delay, s/veh		48.4			48.2			39.7			50.7	
Approach LOS		D			D			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	12.0	56.9	19.6	31.5	33.5	35.4	9.1	42.0				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	5.0	45.0	5.3	38.7	45.0	5.0	5.0	* 39				
Max Q Clear Time (g_c+I1), s	7.0	36.4	3.0	22.1	24.1	20.5	3.5	31.9				
Green Ext Time (p_c), s	0.0	5.1	0.0	3.9	2.5	0.0	0.0	3.6				

Intersection Summary

HCM 6th Ctrl Delay	45.0
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd

2040 Total AM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	15	880	790	5	585	90	380	580	195	350	1270	25
Future Volume (vph)	15	880	790	5	585	90	380	580	195	350	1270	25
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0		12.0	12.0	
Total Split (s)	11.0	37.0		13.0	39.0		22.0	37.0		33.0	48.0	
Total Split (%)	9.2%	30.8%		10.8%	32.5%		18.3%	30.8%		27.5%	40.0%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5		5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5		1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0		7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effct Green (s)	6.1	34.1	120.0	5.9	31.0	120.0	19.9	42.2	120.0	64.0	43.9	120.0
Actuated g/C Ratio	0.05	0.28	1.00	0.05	0.26	1.00	0.17	0.35	1.00	0.53	0.37	1.00
v/c Ratio	0.19	0.98	0.56	0.06	0.70	0.06	0.78	0.55	0.14	0.76	1.06	0.02
Control Delay	55.4	59.6	2.0	68.2	45.7	0.1	60.2	35.9	0.2	25.8	81.3	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.4	59.6	2.0	68.2	45.7	0.1	60.2	35.9	0.2	25.8	81.3	0.0
LOS	E	E	A	E	D	A	E	D	A	C	F	A
Approach Delay		32.6			39.8			37.9			68.3	
Approach LOS		C			D			D			E	

Intersection Summary


Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 150
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.06
 Intersection Signal Delay: 46.0
 Intersection LOS: D
 Intersection Capacity Utilization 86.5%
 ICU Level of Service E
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2040 Total AM.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↗	↘	↑↑	↗
Traffic Volume (veh/h)	15	880	790	5	585	90	380	580	195	350	1270	25
Future Volume (veh/h)	15	880	790	5	585	90	380	580	195	350	1270	25
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	16	946	0	5	636	0	409	624	0	372	1351	0
Peak Hour Factor	0.93	0.93	0.93	0.92	0.92	0.92	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	79	903		11	757		401	1190		496	1362	
Arrive On Green	0.05	0.26	0.00	0.01	0.21	0.00	0.13	0.36	0.00	0.15	0.39	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	3300	1472	1753	3497	1560
Grp Volume(v), veh/h	16	946	0	5	636	0	409	624	0	372	1351	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1650	1472	1753	1749	1560
Q Serve(g_s), s	1.1	31.5	0.0	0.3	20.7	0.0	15.0	17.9	0.0	15.7	46.1	0.0
Cycle Q Clear(g_c), s	1.1	31.5	0.0	0.3	20.7	0.0	15.0	17.9	0.0	15.7	46.1	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	79	903		11	757		401	1190		496	1362	
V/C Ratio(X)	0.20	1.05		0.44	0.84		1.02	0.52		0.75	0.99	
Avail Cap(c_a), veh/h	79	903		96	955		401	1190		606	1362	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	55.1	44.3	0.0	59.4	45.2	0.0	52.5	30.3	0.0	20.5	36.4	0.0
Incr Delay (d2), s/veh	1.2	43.1	0.0	24.8	5.5	0.0	50.0	1.7	0.0	4.1	22.5	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	18.7	0.0	0.2	9.6	0.0	8.8	7.4	0.0	6.8	23.5	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	56.4	87.3	0.0	84.2	50.7	0.0	102.5	31.9	0.0	24.6	59.0	0.0
LnGrp LOS	E	F		F	D		F	C		C	E	
Approach Vol, veh/h		962	A		641	A		1033	A		1723	A
Approach Delay, s/veh		86.8			51.0			59.9			51.6	
Approach LOS		F			D			E			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	25.5	50.3	7.3	37.0	22.0	53.7	12.0	32.3				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	26.0	30.0	6.5	31.5	15.0	41.0	5.5	* 33				
Max Q Clear Time (g_c+I1), s	17.7	19.9	2.3	33.5	17.0	48.1	3.1	22.7				
Green Ext Time (p_c), s	0.8	3.0	0.0	0.0	0.0	0.0	0.0	3.0				

Intersection Summary

HCM 6th Ctrl Delay	61.2
HCM 6th LOS	E

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd


2040 Total PM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	20	695	485	15	935	215	640	1160	305	190	575	20
Future Volume (vph)	20	695	485	15	935	215	640	1160	305	190	575	20
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0		12.0	12.0	
Total Split (s)	10.5	42.2		11.8	43.5		41.0	50.0		16.0	25.0	
Total Split (%)	8.8%	35.2%		9.8%	36.3%		34.2%	41.7%		13.3%	20.8%	
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5		5.5	5.5	
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5		1.5	1.5	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0		7.0	7.0	
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effct Green (s)	5.1	39.2	120.0	5.9	36.8	120.0	28.3	43.2	120.0	41.3	28.1	120.0
Actuated g/C Ratio	0.04	0.33	1.00	0.05	0.31	1.00	0.24	0.36	1.00	0.34	0.23	1.00
v/c Ratio	0.30	0.66	0.34	0.19	0.94	0.15	0.81	0.94	0.20	0.78	0.76	0.01
Control Delay	55.8	35.0	0.5	67.9	57.8	0.2	29.2	56.6	0.0	54.2	51.6	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.8	35.0	0.5	67.9	57.8	0.2	29.2	56.6	0.0	54.2	51.6	0.0
LOS	E	C	A	E	E	A	C	E	A	D	D	A
Approach Delay		21.4			47.3			40.1			50.9	
Approach LOS		C			D			D			D	

Intersection Summary


Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 100
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.94
 Intersection Signal Delay: 39.0
 Intersection LOS: D
 Intersection Capacity Utilization 85.5%
 ICU Level of Service E
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2040 Total PM.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑	↗	↘	↑↑	↗
Traffic Volume (veh/h)	20	695	485	15	935	215	640	1160	305	190	575	20
Future Volume (veh/h)	20	695	485	15	935	215	640	1160	305	190	575	20
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1856	1856	1856
Adj Flow Rate, veh/h	22	755	0	16	1016	0	660	1196	0	207	625	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.92	0.92	0.92
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	3	3	3
Cap, veh/h	38	887		146	1080		751	1331		219	819	
Arrive On Green	0.02	0.25	0.00	0.08	0.30	0.00	0.22	0.37	0.00	0.08	0.23	0.00
Sat Flow, veh/h	1767	3526	1572	1781	3554	1585	3456	3554	1585	1767	3526	1572
Grp Volume(v), veh/h	22	755	0	16	1016	0	660	1196	0	207	625	0
Grp Sat Flow(s),veh/h/ln	1767	1763	1572	1781	1777	1585	1728	1777	1585	1767	1763	1572
Q Serve(g_s), s	1.5	24.5	0.0	1.0	33.4	0.0	22.2	38.1	0.0	9.0	19.9	0.0
Cycle Q Clear(g_c), s	1.5	24.5	0.0	1.0	33.4	0.0	22.2	38.1	0.0	9.0	19.9	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	38	887		146	1080		751	1331		219	819	
V/C Ratio(X)	0.57	0.85		0.11	0.94		0.88	0.90		0.94	0.76	
Avail Cap(c_a), veh/h	74	1078		146	1096		979	1331		219	819	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.2	42.8	0.0	51.0	40.7	0.0	45.4	35.4	0.0	38.8	43.0	0.0
Incr Delay (d2), s/veh	12.9	5.7	0.0	0.3	15.0	0.0	7.5	9.9	0.0	45.4	6.7	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.8	11.3	0.0	0.5	16.7	0.0	10.2	18.0	0.0	4.7	9.4	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	71.0	48.4	0.0	51.3	55.7	0.0	52.9	45.2	0.0	84.3	49.7	0.0
LnGrp LOS	E	D		D	E		D	D		F	D	
Approach Vol, veh/h		777	A		1032	A		1856	A		832	A
Approach Delay, s/veh		49.1			55.7			48.0			58.3	
Approach LOS		D			E			D			E	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	16.0	51.9	16.4	35.7	33.1	34.9	9.1	43.0				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	9.0	43.0	5.3	36.7	34.0	18.0	5.0	* 37				
Max Q Clear Time (g_c+I1), s	11.0	40.1	3.0	26.5	24.2	21.9	3.5	35.4				
Green Ext Time (p_c), s	0.0	2.1	0.0	3.7	1.9	0.0	0.0	1.0				

Intersection Summary

HCM 6th Ctrl Delay	51.8
HCM 6th LOS	D


Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd

2040 Total AM Improved.syn

09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑↗	↘	↑↑↗
Traffic Volume (vph)	15	880	790	5	585	90	380	580	350	1270
Future Volume (vph)	15	880	790	5	585	90	380	580	350	1270
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+pt	NA
Protected Phases	7	4		3	8		5	2	1	6
Permitted Phases			Free			Free				6
Detector Phase	7	4		3	8		5	2	1	6
Switch Phase										
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0	5.0	5.0
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0	12.0	12.0
Total Split (s)	11.0	47.5		11.5	48.0		29.0	29.0	32.0	32.0
Total Split (%)	9.2%	39.6%		9.6%	40.0%		24.2%	24.2%	26.7%	26.7%
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5	5.5	5.5
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0	7.0	7.0
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag	Lead	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes
Recall Mode	None	None		None	None		None	C-Max	None	C-Max
Act Effct Green (s)	7.3	39.8	120.0	5.4	35.1	120.0	19.9	32.8	63.9	38.6
Actuated g/C Ratio	0.06	0.33	1.00	0.04	0.29	1.00	0.17	0.27	0.53	0.32
v/c Ratio	0.15	0.84	0.56	0.06	0.62	0.06	0.78	0.65	0.81	0.86
Control Delay	54.4	41.5	2.1	57.4	42.5	0.1	59.0	40.3	39.6	46.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.4	41.5	2.1	57.4	42.5	0.1	59.0	40.3	39.6	46.0
LOS	D	D	A	E	D	A	E	D	D	D
Approach Delay		23.1			37.0			46.5		44.6
Approach LOS		C			D			D		D

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 100
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.86
 Intersection Signal Delay: 37.0
 Intersection LOS: D
 Intersection Capacity Utilization 76.5%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
2: US-24 & Marksheffel Rd

2040 Total AM Improved.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	15	880	790	5	585	90	380	580	195	350	1270	25
Future Volume (veh/h)	15	880	790	5	585	90	380	580	195	350	1270	25
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1811	1811	1811	1856	1856	1856	1737	1737	1737	1841	1841	1841
Adj Flow Rate, veh/h	16	946	0	5	636	0	409	624	0	372	1351	0
Peak Hour Factor	0.93	0.93	0.93	0.92	0.92	0.92	0.93	0.93	0.93	0.94	0.94	0.94
Percent Heavy Veh, %	6	6	6	3	3	3	11	11	11	4	4	4
Cap, veh/h	151	1075		11	786		473	1415		502	1594	
Arrive On Green	0.09	0.31	0.00	0.01	0.22	0.00	0.15	0.30	0.00	0.17	0.32	0.00
Sat Flow, veh/h	1725	3441	1535	1767	3526	1572	3209	4898	0	1753	5191	0
Grp Volume(v), veh/h	16	946	0	5	636	0	409	624	0	372	1351	0
Grp Sat Flow(s),veh/h/ln	1725	1721	1535	1767	1763	1572	1605	1581	0	1753	1675	0
Q Serve(g_s), s	1.0	31.3	0.0	0.3	20.5	0.0	14.9	12.8	0.0	17.3	30.1	0.0
Cycle Q Clear(g_c), s	1.0	31.3	0.0	0.3	20.5	0.0	14.9	12.8	0.0	17.3	30.1	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		0.00	1.00		0.00
Lane Grp Cap(c), veh/h	151	1075		11	786		473	1415		502	1594	
V/C Ratio(X)	0.11	0.88		0.44	0.81		0.87	0.44		0.74	0.85	
Avail Cap(c_a), veh/h	151	1204		74	1219		588	1415		577	1594	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	50.4	39.1	0.0	59.4	44.2	0.0	50.0	34.0	0.0	23.1	38.3	0.0
Incr Delay (d2), s/veh	0.3	7.2	0.0	24.8	2.4	0.0	10.9	1.0	0.0	4.4	5.8	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	14.1	0.0	0.2	9.2	0.0	6.7	5.0	0.0	7.7	13.1	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	50.7	46.3	0.0	84.2	46.6	0.0	60.9	35.0	0.0	27.5	44.1	0.0
LnGrp LOS	D	D		F	D		E	D		C	D	
Approach Vol, veh/h		962	A		641	A		1033	A		1723	A
Approach Delay, s/veh		46.3			46.9			45.2			40.5	
Approach LOS		D			D			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	26.9	42.8	7.3	43.0	24.7	45.1	17.0	33.3				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	25.0	22.0	5.0	42.0	22.0	25.0	5.5	* 42				
Max Q Clear Time (g_c+l1), s	19.3	14.8	2.3	33.3	16.9	32.1	3.0	22.5				
Green Ext Time (p_c), s	0.6	2.5	0.0	4.2	0.7	0.0	0.0	4.2				

Intersection Summary

HCM 6th Ctrl Delay	43.8
HCM 6th LOS	D


Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
2: US-24 & Marksheffel Rd

2040 Total PM Improved.syn

09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↗
Traffic Volume (vph)	20	695	485	15	935	215	640	1160	190	575
Future Volume (vph)	20	695	485	15	935	215	640	1160	190	575
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+pt	NA
Protected Phases	7	4		3	8		5	2	1	6
Permitted Phases			Free			Free				6
Detector Phase	7	4		3	8		5	2	1	6
Switch Phase										
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0	5.0	5.0
Minimum Split (s)	10.5	10.5		11.5	11.5		12.0	12.0	12.0	12.0
Total Split (s)	10.6	54.2		11.8	55.4		42.0	37.0	17.0	12.0
Total Split (%)	8.8%	45.2%		9.8%	46.2%		35.0%	30.8%	14.2%	10.0%
Yellow Time (s)	4.5	4.5		5.0	5.0		5.5	5.5	5.5	5.5
All-Red Time (s)	1.0	1.0		1.5	1.5		1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0
Total Lost Time (s)	5.5	5.5		6.5	6.5		7.0	7.0	7.0	7.0
Lead/Lag	Lag	Lead		Lag	Lead		Lead	Lag	Lead	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes
Recall Mode	None	None		None	None		None	C-Max	None	C-Max
Act Effect Green (s)	6.2	42.5	120.0	9.5	42.9	120.0	28.6	36.1	34.2	20.9
Actuated g/C Ratio	0.05	0.35	1.00	0.08	0.36	1.00	0.24	0.30	0.28	0.17
v/c Ratio	0.24	0.61	0.34	0.11	0.80	0.15	0.81	0.99	0.77	0.74
Control Delay	50.6	36.0	0.5	42.3	29.1	0.2	29.2	58.4	54.9	54.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	50.6	36.0	0.5	42.3	29.1	0.2	29.2	58.4	54.9	54.2
LOS	D	D	A	D	C	A	C	E	D	D
Approach Delay		21.9			23.9			49.5		54.4
Approach LOS		C			C			D		D

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 97 (81%), Referenced to phase 2:NBT and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.99
 Intersection Signal Delay: 38.0
 Intersection Capacity Utilization 82.7%
 Analysis Period (min) 15

Intersection LOS: D
 ICU Level of Service E

Splits and Phases: 2: US-24 & Marksheffel Rd



HCM 6th Signalized Intersection Summary
 2: US-24 & Marksheffel Rd

2040 Total PM Improved.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↘	↑↑	↗	↘	↑↑	↗	↘↗	↑↑↗		↘	↑↑↗	
Traffic Volume (veh/h)	20	695	485	15	935	215	640	1160	305	190	575	20
Future Volume (veh/h)	20	695	485	15	935	215	640	1160	305	190	575	20
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1856	1856	1856
Adj Flow Rate, veh/h	22	755	0	16	1016	0	660	1196	0	207	625	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.92	0.92	0.92
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	3	3	3
Cap, veh/h	38	928		183	1194		753	1705		268	1010	
Arrive On Green	0.02	0.26	0.00	0.10	0.34	0.00	0.22	0.33	0.00	0.08	0.20	0.00
Sat Flow, veh/h	1767	3526	1572	1781	3554	1585	3456	5274	0	1767	5233	0
Grp Volume(v), veh/h	22	755	0	16	1016	0	660	1196	0	207	625	0
Grp Sat Flow(s),veh/h/ln	1767	1763	1572	1781	1777	1585	1728	1702	0	1767	1689	0
Q Serve(g_s), s	1.5	24.1	0.0	1.0	31.9	0.0	22.2	24.4	0.0	10.0	13.5	0.0
Cycle Q Clear(g_c), s	1.5	24.1	0.0	1.0	31.9	0.0	22.2	24.4	0.0	10.0	13.5	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		0.00	1.00		0.00
Lane Grp Cap(c), veh/h	38	928		183	1194		753	1705		268	1010	
V/C Ratio(X)	0.57	0.81		0.09	0.85		0.88	0.70		0.77	0.62	
Avail Cap(c_a), veh/h	75	1431		183	1448		1008	1705		268	1010	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.2	41.4	0.0	48.7	37.0	0.0	45.4	34.8	0.0	37.1	43.9	0.0
Incr Delay (d2), s/veh	12.9	2.1	0.0	0.2	4.3	0.0	6.9	2.4	0.0	13.1	2.8	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.8	10.7	0.0	0.4	14.4	0.0	10.2	10.4	0.0	1.9	5.9	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	71.0	43.6	0.0	48.9	41.3	0.0	52.3	37.2	0.0	50.2	46.7	0.0
LnGrp LOS	E	D		D	D		D	D		D	D	
Approach Vol, veh/h		777	A		1032	A		1856	A		832	A
Approach Delay, s/veh		44.4			41.5			42.6			47.6	
Approach LOS		D			D			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	17.0	47.1	18.8	37.1	33.2	30.9	9.1	46.8				
Change Period (Y+Rc), s	7.0	7.0	6.5	5.5	7.0	7.0	6.5	* 6.5				
Max Green Setting (Gmax), s	10.0	30.0	5.3	48.7	35.0	5.0	5.1	* 49				
Max Q Clear Time (g_c+I1), s	12.0	26.4	3.0	26.1	24.2	15.5	3.5	33.9				
Green Ext Time (p_c), s	0.0	2.4	0.0	5.5	2.0	0.0	0.0	6.4				

Intersection Summary

HCM 6th Ctrl Delay	43.5
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Intersection												
Int Delay, s/veh	0											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗		↖	↗	↖		↔		↖	↗	
Traffic Vol, veh/h	5	24	0	0	8	108	0	0	0	179	0	1
Future Vol, veh/h	5	24	0	0	8	108	0	0	0	179	0	1
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	100	-	0	-	-	-	50	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	75	75	75	87	87	87	92	92	92	74	74	74
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	6	6	2
Mvmt Flow	7	32	0	0	9	124	0	0	0	242	0	1

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	552	485	1	501	485	0	1	0	0	0	0	0
Stage 1	485	485	-	0	0	-	-	-	-	-	-	-
Stage 2	67	0	-	501	485	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.16	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.254	-	-
Pot Cap-1 Maneuver	444	482	1084	480	482	-	1622	-	-	-	-	-
Stage 1	563	552	-	-	-	-	-	-	-	-	-	-
Stage 2	943	-	-	552	552	-	-	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	482	1084	457	482	-	1622	-	-	-	-	-
Mov Cap-2 Maneuver	285	511	-	484	515	-	-	-	-	-	-	-
Stage 1	563	552	-	-	-	-	-	-	-	-	-	-
Stage 2	943	-	-	520	552	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0			
HCM LOS	-			

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	WBLn2	WBLn3	SBL	SBT	SBR
Capacity (veh/h)	1622	-	-	-	511	-	515	-	-	-	-
HCM Lane V/C Ratio	-	-	-	-	0.063	-	0.018	-	-	-	-
HCM Control Delay (s)	0	-	-	-	12.5	0	12.1	-	-	-	-
HCM Lane LOS	A	-	-	-	B	A	B	-	-	-	-
HCM 95th %tile Q(veh)	0	-	-	-	0.2	-	0.1	-	-	-	-

Intersection												
Int Delay, s/veh	0											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗		↖	↗	↖		↔		↖	↗	
Traffic Vol, veh/h	9	26	0	0	29	77	0	0	0	215	0	8
Future Vol, veh/h	9	26	0	0	29	77	0	0	0	215	0	8
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	100	-	0	-	-	-	50	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	80	80	80	88	88	88	92	92	92	71	71	71
Heavy Vehicles, %	6	6	6	8	8	8	2	2	2	2	2	2
Mvmt Flow	11	33	0	0	33	88	0	0	0	303	0	11

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	673	612	6	628	617	0	11	0	0	0	0	0
Stage 1	612	612	-	0	0	-	-	-	-	-	-	-
Stage 2	61	0	-	628	617	-	-	-	-	-	-	-
Critical Hdwy	7.16	6.56	6.26	7.18	6.58	6.28	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.16	5.56	-	6.18	5.58	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.16	5.56	-	6.18	5.58	-	-	-	-	-	-	-
Follow-up Hdwy	3.554	4.054	3.354	3.572	4.072	3.372	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	364	403	1065	387	398	-	1608	-	-	-	-	-
Stage 1	474	478	-	-	-	-	-	-	-	-	-	-
Stage 2	940	-	-	461	472	-	-	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	403	1065	365	398	-	1608	-	-	-	-	-
Mov Cap-2 Maneuver	248	444	-	405	446	-	-	-	-	-	-	-
Stage 1	474	478	-	-	-	-	-	-	-	-	-	-
Stage 2	940	-	-	430	472	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0			
HCM LOS	-			

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	WBLn2	WBLn3	SBL	SBT	SBR
Capacity (veh/h)	1608	-	-	-	444	-	446	-	-	-	-
HCM Lane V/C Ratio	-	-	-	-	0.073	-	0.074	-	-	-	-
HCM Control Delay (s)	0	-	-	-	13.7	0	13.7	-	-	-	-
HCM Lane LOS	A	-	-	-	B	A	B	-	-	-	-
HCM 95th %tile Q(veh)	0	-	-	-	0.2	-	0.2	-	-	-	-

Intersection												
Int Delay, s/veh	0											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗		↖	↗	↖		↔		↖	↗	
Traffic Vol, veh/h	10	45	0	0	15	115	0	0	0	190	0	5
Future Vol, veh/h	10	45	0	0	15	115	0	0	0	190	0	5
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	100	-	0	-	-	-	50	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	75	75	75	87	87	87	92	92	92	74	74	74
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	6	6	2
Mvmt Flow	13	60	0	0	17	132	0	0	0	257	0	7

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	593	518	4	548	521	0	7	0	0	0	0	0
Stage 1	518	518	-	0	0	-	-	-	-	-	-	-
Stage 2	75	0	-	548	521	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.16	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.254	-	-
Pot Cap-1 Maneuver	417	462	1080	447	460	-	1614	-	-	-	-	-
Stage 1	541	533	-	-	-	-	-	-	-	-	-	-
Stage 2	934	-	-	521	532	-	-	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	462	1080	405	460	-	1614	-	-	-	-	-
Mov Cap-2 Maneuver	274	494	-	430	498	-	-	-	-	-	-	-
Stage 1	541	533	-	-	-	-	-	-	-	-	-	-
Stage 2	934	-	-	462	532	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0			
HCM LOS	-			

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	WBLn2	WBLn3	SBL	SBT	SBR
Capacity (veh/h)	1614	-	-	-	494	-	498	-	-	-	-
HCM Lane V/C Ratio	-	-	-	-	0.121	-	0.035	-	-	-	-
HCM Control Delay (s)	0	-	-	-	13.3	0	12.5	-	-	-	-
HCM Lane LOS	A	-	-	-	B	A	B	-	-	-	-
HCM 95th %tile Q(veh)	0	-	-	-	0.4	-	0.1	-	-	-	-

Intersection												
Int Delay, s/veh	0											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗		↖	↗	↖		↔		↖	↗	
Traffic Vol, veh/h	15	40	0	0	50	85	0	0	0	230	0	10
Future Vol, veh/h	15	40	0	0	50	85	0	0	0	230	0	10
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	100	-	0	-	-	-	50	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	80	80	80	88	88	88	92	92	92	71	71	71
Heavy Vehicles, %	6	6	6	8	8	8	2	2	2	2	2	2
Mvmt Flow	19	50	0	0	57	97	0	0	0	324	0	14

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	732	655	7	680	662	0	14	0	0	0	0	0
Stage 1	655	655	-	0	0	-	-	-	-	-	-	-
Stage 2	77	0	-	680	662	-	-	-	-	-	-	-
Critical Hdwy	7.16	6.56	6.26	7.18	6.58	6.28	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.16	5.56	-	6.18	5.58	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.16	5.56	-	6.18	5.58	-	-	-	-	-	-	-
Follow-up Hdwy	3.554	4.054	3.354	3.572	4.072	3.372	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	332	381	1064	357	375	-	1604	-	-	-	-	-
Stage 1	448	457	-	-	-	-	-	-	-	-	-	-
Stage 2	922	-	-	431	450	-	-	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	381	1064	325	375	-	1604	-	-	-	-	-
Mov Cap-2 Maneuver	233	426	-	362	428	-	-	-	-	-	-	-
Stage 1	448	457	-	-	-	-	-	-	-	-	-	-
Stage 2	922	-	-	384	450	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0			
HCM LOS	-	-		

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	WBLn2	WBLn3	SBL	SBT	SBR
Capacity (veh/h)	1604	-	-	-	426	-	428	-	-	-	-
HCM Lane V/C Ratio	-	-	-	-	0.117	-	0.133	-	-	-	-
HCM Control Delay (s)	0	-	-	-	14.6	0	14.7	-	-	-	-
HCM Lane LOS	A	-	-	-	B	A	B	-	-	-	-
HCM 95th %tile Q(veh)	0	-	-	-	0.4	-	0.5	-	-	-	-

Intersection												
Int Delay, s/veh	123.3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗		↖	↗	↖		↔		↖	↗	
Traffic Vol, veh/h	10	45	0	435	15	125	0	80	440	220	80	5
Future Vol, veh/h	10	45	0	435	15	125	0	80	440	220	80	5
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	100	-	0	-	-	-	50	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	6	6	2
Mvmt Flow	11	49	0	473	16	136	0	87	478	239	87	5

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	970	1133	90	918	896	326	92	0	0	565	0	0
Stage 1	568	568	-	326	326	-	-	-	-	-	-	-
Stage 2	402	565	-	592	570	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.16	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.254	-	-
Pot Cap-1 Maneuver	233	203	968	~ 252	280	715	1503	-	-	987	-	-
Stage 1	508	506	-	687	648	-	-	-	-	-	-	-
Stage 2	625	508	-	493	505	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	147	154	968	~ 170	212	715	1503	-	-	987	-	-
Mov Cap-2 Maneuver	210	211	-	~ 265	306	-	-	-	-	-	-	-
Stage 1	508	384	-	687	648	-	-	-	-	-	-	-
Stage 2	493	508	-	~ 326	383	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	26.4	\$ 305.6	0	7.1
HCM LOS	D	F		

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	WBLn2	WBLn3	SBL	SBT	SBR
Capacity (veh/h)	1503	-	-	210	211	265	306	715	987	-	-
HCM Lane V/C Ratio	-	-	-	0.052	0.232	1.784	0.053	0.19	0.242	-	-
HCM Control Delay (s)	0	-	-	23.1	27.1	\$ 400.1	17.4	11.2	9.8	-	-
HCM Lane LOS	A	-	-	C	D	F	C	B	A	-	-
HCM 95th %tile Q(veh)	0	-	-	0.2	0.9	31.6	0.2	0.7	0.9	-	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Intersection												
Int Delay, s/veh	151.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗		↖	↗	↖		↔		↖	↗	
Traffic Vol, veh/h	15	40	0	440	50	120	0	70	385	250	80	10
Future Vol, veh/h	15	40	0	440	50	120	0	70	385	250	80	10
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	100	-	0	-	-	-	50	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	6	6	6	8	8	8	2	2	2	2	2	2
Mvmt Flow	16	43	0	478	54	130	0	76	418	272	87	11

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	1014	1131	93	943	927	285	98	0	0	494	0	0
Stage 1	637	637	-	285	285	-	-	-	-	-	-	-
Stage 2	377	494	-	658	642	-	-	-	-	-	-	-
Critical Hdwy	7.16	6.56	6.26	7.18	6.58	6.28	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.16	5.56	-	6.18	5.58	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.16	5.56	-	6.18	5.58	-	-	-	-	-	-	-
Follow-up Hdwy	3.554	4.054	3.354	3.572	4.072	3.372	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	213	200	953	~ 237	262	740	1495	-	-	1070	-	-
Stage 1	459	465	-	709	665	-	-	-	-	-	-	-
Stage 2	636	540	-	~ 444	460	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	121	149	953	~ 160	195	740	1495	-	-	1070	-	-
Mov Cap-2 Maneuver	174	204	-	~ 242	281	-	-	-	-	-	-	-
Stage 1	459	347	-	709	665	-	-	-	-	-	-	-
Stage 2	481	540	-	~ 290	343	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	27.5	\$ 355.5	0	7
HCM LOS	D	F		

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	WBLn2	WBLn3	SBL	SBT	SBR
Capacity (veh/h)	1495	-	-	174	204	242	281	740	1070	-	-
HCM Lane V/C Ratio	-	-	-	0.094	0.213	1.976	0.193	0.176	0.254	-	-
HCM Control Delay (s)	0	-	-	27.8	27.4	\$ 487.5	20.9	10.9	9.5	-	-
HCM Lane LOS	A	-	-	D	D	F	C	B	A	-	-
HCM 95th %tile Q(veh)	0	-	-	0.3	0.8	34.7	0.7	0.6	1	-	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Intersection					
Intersection Delay, s/veh	8.8				
Intersection LOS	A				
Approach	EB	WB		NB	SB
Entry Lanes	1	2		1	1
Conflicting Circle Lanes	1	1		1	1
Adj Approach Flow, veh/h	60	625		565	331
Demand Flow Rate, veh/h	61	637		577	350
Vehicles Circulating, veh/h	827	100		314	498
Vehicles Exiting, veh/h	21	791		574	239
Ped Vol Crossing Leg, #/h	0	0		0	0
Ped Cap Adj	1.000	1.000		1.000	1.000
Approach Delay, s/veh	7.4	5.9		11.4	10.0
Approach LOS	A	A		B	A
Lane	Left	Left	Right	Left	Left
Designated Moves	LTR	LT	R	LTR	LTR
Assumed Moves	LTR	LT	R	LTR	LTR
RT Channelized					
Lane Util	1.000	0.782	0.218	1.000	1.000
Follow-Up Headway, s	2.609	2.535	2.535	2.609	2.609
Critical Headway, s	4.976	4.544	4.544	4.976	4.976
Entry Flow, veh/h	61	498	139	577	350
Cap Entry Lane, veh/h	594	1297	1297	1002	830
Entry HV Adj Factor	0.984	0.981	0.978	0.980	0.945
Flow Entry, veh/h	60	489	136	565	331
Cap Entry, veh/h	584	1272	1269	981	785
V/C Ratio	0.103	0.384	0.107	0.576	0.422
Control Delay, s/veh	7.4	6.5	3.7	11.4	10.0
LOS	A	A	A	B	A
95th %tile Queue, veh	0	2	0	4	2

Intersection					
Intersection Delay, s/veh	9.1				
Intersection LOS	A				
Approach	EB	WB		NB	SB
Entry Lanes	1	2		1	1
Conflicting Circle Lanes	1	1		1	1
Adj Approach Flow, veh/h	59	662		494	370
Demand Flow Rate, veh/h	63	714		504	377
Vehicles Circulating, veh/h	882	95		340	574
Vehicles Exiting, veh/h	69	749		605	235
Ped Vol Crossing Leg, #/h	0	0		0	0
Ped Cap Adj	1.000	1.000		1.000	1.000
Approach Delay, s/veh	8.2	6.8		10.3	11.7
Approach LOS	A	A		B	B
Lane	Left	Left	Right	Left	Left
Designated Moves	LTR	LT	R	LTR	LTR
Assumed Moves	LTR	LT	R	LTR	LTR
RT Channelized					
Lane Util	1.000	0.804	0.196	1.000	1.000
Follow-Up Headway, s	2.609	2.535	2.535	2.609	2.609
Critical Headway, s	4.976	4.544	4.544	4.976	4.976
Entry Flow, veh/h	63	574	140	504	377
Cap Entry Lane, veh/h	561	1302	1302	976	768
Entry HV Adj Factor	0.943	0.926	0.929	0.981	0.982
Flow Entry, veh/h	59	532	130	494	370
Cap Entry, veh/h	529	1207	1209	957	755
V/C Ratio	0.112	0.441	0.107	0.517	0.491
Control Delay, s/veh	8.2	7.5	3.9	10.3	11.7
LOS	A	A	A	B	B
95th %tile Queue, veh	0	2	0	3	3

Intersection					
Intersection Delay, s/veh	4.1				
Intersection LOS	A				
Approach	EB	WB		NB	SB
Entry Lanes	1	2		1	1
Conflicting Circle Lanes	1	1		1	1
Adj Approach Flow, veh/h	65	174		0	255
Demand Flow Rate, veh/h	66	177		0	270
Vehicles Circulating, veh/h	265	11		331	22
Vehicles Exiting, veh/h	27	320		0	166
Ped Vol Crossing Leg, #/h	0	0		0	0
Ped Cap Adj	1.000	1.000		1.000	1.000
Approach Delay, s/veh	4.0	3.4		0.0	4.5
Approach LOS	A	A		-	A
Lane	Left	Left	Right	Left	Left
Designated Moves	LTR	LT	R	LTR	LTR
Assumed Moves	LTR	LT	R	LTR	LTR
RT Channelized					
Lane Util	1.000	0.124	0.876	1.000	1.000
Follow-Up Headway, s	2.609	2.535	2.535	2.609	2.609
Critical Headway, s	4.976	4.544	4.544	4.976	4.976
Entry Flow, veh/h	66	22	155	0	270
Cap Entry Lane, veh/h	1053	1406	1406	985	1349
Entry HV Adj Factor	0.984	0.980	0.981	1.000	0.944
Flow Entry, veh/h	65	22	152	0	255
Cap Entry, veh/h	1036	1378	1379	985	1274
V/C Ratio	0.063	0.016	0.110	0.000	0.200
Control Delay, s/veh	4.0	2.7	3.5	3.7	4.5
LOS	A	A	A	A	A
95th %tile Queue, veh	0	0	0	0	1

Intersection					
Intersection Delay, s/veh	4.4				
Intersection LOS	A				
Approach	EB	WB		NB	SB
Entry Lanes	1	2		1	1
Conflicting Circle Lanes	1	1		1	1
Adj Approach Flow, veh/h	65	169		0	315
Demand Flow Rate, veh/h	69	183		0	321
Vehicles Circulating, veh/h	305	17		374	65
Vehicles Exiting, veh/h	81	357		0	135
Ped Vol Crossing Leg, #/h	0	0		0	0
Ped Cap Adj	1.000	1.000		1.000	1.000
Approach Delay, s/veh	4.4	3.4		0.0	5.0
Approach LOS	A	A		-	A
Lane	Left	Left	Right	Left	Left
Designated Moves	LTR	LT	R	LTR	LTR
Assumed Moves	LTR	LT	R	LTR	LTR
RT Channelized					
Lane Util	1.000	0.355	0.645	1.000	1.000
Follow-Up Headway, s	2.609	2.535	2.535	2.609	2.609
Critical Headway, s	4.976	4.544	4.544	4.976	4.976
Entry Flow, veh/h	69	65	118	0	321
Cap Entry Lane, veh/h	1011	1398	1398	942	1291
Entry HV Adj Factor	0.943	0.926	0.924	1.000	0.981
Flow Entry, veh/h	65	60	109	0	315
Cap Entry, veh/h	953	1295	1292	942	1267
V/C Ratio	0.068	0.046	0.084	0.000	0.249
Control Delay, s/veh	4.4	3.1	3.5	3.8	5.0
LOS	A	A	A	A	A
95th %tile Queue, veh	0	0	0	0	1

Intersection					
Intersection Delay, s/veh	9.5				
Intersection LOS	A				
Approach	EB	WB		NB	SB
Entry Lanes	1	2		1	1
Conflicting Circle Lanes	1	1		1	1
Adj Approach Flow, veh/h	65	658		565	375
Demand Flow Rate, veh/h	66	670		577	397
Vehicles Circulating, veh/h	874	100		366	504
Vehicles Exiting, veh/h	27	843		574	266
Ped Vol Crossing Leg, #/h	0	0		0	0
Ped Cap Adj	1.000	1.000		1.000	1.000
Approach Delay, s/veh	7.9	5.9		12.7	11.2
Approach LOS	A	A		B	B
Lane	Left	Left	Right	Left	Left
Designated Moves	LTR	LT	R	LTR	LTR
Assumed Moves	LTR	LT	R	LTR	LTR
RT Channelized					
Lane Util	1.000	0.752	0.248	1.000	1.000
Follow-Up Headway, s	2.609	2.535	2.535	2.609	2.609
Critical Headway, s	4.976	4.544	4.544	4.976	4.976
Entry Flow, veh/h	66	504	166	577	397
Cap Entry Lane, veh/h	566	1297	1297	950	825
Entry HV Adj Factor	0.984	0.981	0.982	0.980	0.944
Flow Entry, veh/h	65	495	163	565	375
Cap Entry, veh/h	557	1272	1273	931	779
V/C Ratio	0.117	0.389	0.128	0.607	0.481
Control Delay, s/veh	7.9	6.6	3.9	12.7	11.2
LOS	A	A	A	B	B
95th %tile Queue, veh	0	2	0	4	3

Intersection					
Intersection Delay, s/veh	10.0				
Intersection LOS	B				
Approach	EB	WB		NB	SB
Entry Lanes	1	2		1	1
Conflicting Circle Lanes	1	1		1	1
Adj Approach Flow, veh/h	65	685		494	424
Demand Flow Rate, veh/h	69	740		504	432
Vehicles Circulating, veh/h	932	95		396	581
Vehicles Exiting, veh/h	81	805		605	254
Ped Vol Crossing Leg, #/h	0	0		0	0
Ped Cap Adj	1.000	1.000		1.000	1.000
Approach Delay, s/veh	8.9	6.8		11.4	13.7
Approach LOS	A	A		B	B
Lane	Left	Left	Right	Left	Left
Designated Moves	LTR	LT	R	LTR	LTR
Assumed Moves	LTR	LT	R	LTR	LTR
RT Channelized					
Lane Util	1.000	0.785	0.215	1.000	1.000
Follow-Up Headway, s	2.609	2.535	2.535	2.609	2.609
Critical Headway, s	4.976	4.544	4.544	4.976	4.976
Entry Flow, veh/h	69	581	159	504	432
Cap Entry Lane, veh/h	533	1302	1302	921	763
Entry HV Adj Factor	0.943	0.926	0.925	0.981	0.982
Flow Entry, veh/h	65	538	147	494	424
Cap Entry, veh/h	503	1207	1204	904	749
V/C Ratio	0.129	0.446	0.122	0.547	0.566
Control Delay, s/veh	8.9	7.6	4.0	11.4	13.7
LOS	A	A	A	B	B
95th %tile Queue, veh	0	2	0	3	4

Timings
4: US-24 & Newt Dr/SH-94


2020 Adjusted Existing AM.syn
08/03/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	14	25	174	391	35	1	128	709	337	4	1542	32
Future Volume (vph)	14	25	174	391	35	1	128	709	337	4	1542	32
Turn Type	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free	2		Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5	
Total Split (s)	15.0	24.5		24.5	34.0		17.0	58.0		13.0	54.0	
Total Split (%)	12.5%	20.4%		20.4%	28.3%		14.2%	48.3%		10.8%	45.0%	
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5	
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5	
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max	
Act Effect Green (s)	6.2	7.6	120.0	18.1	21.9	120.0	76.8	66.8	120.0	67.8	62.3	120.0
Actuated g/C Ratio	0.05	0.06	1.00	0.15	0.18	1.00	0.64	0.56	1.00	0.56	0.52	1.00
v/c Ratio	0.11	0.28	0.15	0.87	0.06	0.00	0.68	0.40	0.24	0.01	0.91	0.02
Control Delay	55.3	59.0	0.2	44.2	19.4	0.0	54.9	17.3	0.4	6.0	27.7	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.3	59.0	0.2	44.2	19.4	0.0	54.9	17.3	0.4	6.0	27.7	0.0
LOS	E	E	A	D	B	A	D	B	A	A	C	A
Approach Delay		10.6			42.0			16.5			27.1	
Approach LOS		B			D			B			C	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 130
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.91
 Intersection Signal Delay: 24.3
 Intersection LOS: C
 Intersection Capacity Utilization 84.6%
 ICU Level of Service E
 Analysis Period (min) 15

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2020 Adjusted Existing AM.syn
 08/03/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	14	25	174	391	35	1	128	709	337	4	1542	32
Future Volume (veh/h)	14	25	174	391	35	1	128	709	337	4	1542	32
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1826	1826	1826	1841	1841	1841	1752	1752	1752	1811	1811	1811
Adj Flow Rate, veh/h	18	32	0	444	40	0	132	731	0	4	1606	0
Peak Hour Factor	0.77	0.77	0.77	0.88	0.88	0.88	0.97	0.97	0.97	0.96	0.96	0.96
Percent Heavy Veh, %	5	5	5	4	4	4	10	10	10	6	6	6
Cap, veh/h	63	72		499	571		171	1934		372	1870	
Arrive On Green	0.02	0.04	0.00	0.15	0.16	0.00	0.04	0.58	0.00	0.01	0.54	0.00
Sat Flow, veh/h	3374	1826	1547	3401	3497	1560	1668	3328	1485	1725	3441	1535
Grp Volume(v), veh/h	18	32	0	444	40	0	132	731	0	4	1606	0
Grp Sat Flow(s),veh/h/ln	1687	1826	1547	1700	1749	1560	1668	1664	1485	1725	1721	1535
Q Serve(g_s), s	0.6	2.1	0.0	15.4	1.2	0.0	1.9	14.2	0.0	0.0	47.9	0.0
Cycle Q Clear(g_c), s	0.6	2.1	0.0	15.4	1.2	0.0	1.9	14.2	0.0	0.0	47.9	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	63	72		499	571		171	1934		372	1870	
V/C Ratio(X)	0.28	0.44		0.89	0.07		0.77	0.38		0.01	0.86	
Avail Cap(c_a), veh/h	239	274		524	816		242	1934		438	1870	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	0.68	0.68	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	58.1	56.3	0.0	50.3	42.5	0.0	52.5	13.5	0.0	19.4	23.5	0.0
Incr Delay (d2), s/veh	2.4	4.2	0.0	12.1	0.0	0.0	9.4	0.6	0.0	0.0	5.4	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	1.0	0.0	7.4	0.5	0.0	4.3	5.3	0.0	0.1	20.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	60.5	60.5	0.0	62.4	42.5	0.0	61.9	14.1	0.0	19.4	28.8	0.0
LnGrp LOS	E	E		E	D		E	B		B	C	
Approach Vol, veh/h		50	A		484	A		863	A		1610	A
Approach Delay, s/veh		60.5			60.8			21.4			28.8	
Approach LOS		E			E			C			C	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.4	76.7	23.6	11.3	12.4	72.7	8.8	26.1				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	51.0	18.5	18.0	10.0	* 47	8.5	* 28				
Max Q Clear Time (g_c+I1), s	2.0	16.2	17.4	4.1	3.9	49.9	2.6	3.2				
Green Ext Time (p_c), s	0.0	5.9	0.2	0.1	0.2	0.0	0.0	0.2				

Intersection Summary

HCM 6th Ctrl Delay	32.4
HCM 6th LOS	C

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94


2020 Adjusted Existing PM.syn
08/03/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	23	32	194	285	19	6	129	1375	261	3	760	30
Future Volume (vph)	23	32	194	285	19	6	129	1375	261	3	760	30
Turn Type	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free	2		Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5	
Total Split (s)	11.5	24.5		22.0	35.0		17.5	61.0		12.5	56.0	
Total Split (%)	9.6%	20.4%		18.3%	29.2%		14.6%	50.8%		10.4%	46.7%	
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5	
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5	
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max	
Act Effct Green (s)	5.0	8.2	120.0	15.5	20.9	120.0	77.2	66.7	120.0	66.2	61.2	120.0
Actuated g/C Ratio	0.04	0.07	1.00	0.13	0.17	1.00	0.64	0.56	1.00	0.55	0.51	1.00
v/c Ratio	0.21	0.33	0.16	0.82	0.04	0.01	0.31	0.74	0.17	0.02	0.48	0.02
Control Delay	59.2	59.6	0.2	44.3	18.7	0.0	13.8	24.2	0.2	6.3	17.1	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	59.2	59.6	0.2	44.3	18.7	0.0	13.8	24.2	0.2	6.3	17.1	0.0
LOS	E	E	A	D	B	A	B	C	A	A	B	A
Approach Delay		13.4			41.8			19.9			16.4	
Approach LOS		B			D			B			B	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 100
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.82
 Intersection Signal Delay: 20.9
 Intersection LOS: C
 Intersection Capacity Utilization 74.1%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
4: US-24 & Newt Dr/SH-94

2020 Adjusted Existing PM.syn
08/03/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	23	32	194	285	19	6	129	1375	261	3	760	30
Future Volume (veh/h)	23	32	194	285	19	6	129	1375	261	3	760	30
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1856	1856	1856	1856	1856	1856	1826	1826	1826
Adj Flow Rate, veh/h	30	42	0	361	24	0	134	1432	0	3	844	0
Peak Hour Factor	0.77	0.77	0.77	0.79	0.79	0.79	0.96	0.96	0.96	0.90	0.90	0.90
Percent Heavy Veh, %	2	2	2	3	3	3	3	3	3	5	5	5
Cap, veh/h	91	75		418	463		414	2147		175	1954	
Arrive On Green	0.03	0.04	0.00	0.12	0.13	0.00	0.05	0.61	0.00	0.00	0.56	0.00
Sat Flow, veh/h	3456	1870	1585	3428	3526	1572	1767	3526	1572	1739	3469	1547
Grp Volume(v), veh/h	30	42	0	361	24	0	134	1432	0	3	844	0
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1714	1763	1572	1767	1763	1572	1739	1735	1547
Q Serve(g_s), s	1.0	2.6	0.0	12.4	0.7	0.0	0.0	32.1	0.0	0.0	16.8	0.0
Cycle Q Clear(g_c), s	1.0	2.6	0.0	12.4	0.7	0.0	0.0	32.1	0.0	0.0	16.8	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	91	75		418	463		414	2147		175	1954	
V/C Ratio(X)	0.33	0.56		0.86	0.05		0.32	0.67		0.02	0.43	
Avail Cap(c_a), veh/h	144	281		457	852		488	2147		240	1954	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	0.69	0.69	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	57.4	56.6	0.0	51.7	45.6	0.0	21.4	15.4	0.0	29.7	15.1	0.0
Incr Delay (d2), s/veh	2.1	6.5	0.0	10.7	0.0	0.0	0.4	1.7	0.0	0.0	0.7	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	1.4	0.0	5.9	0.3	0.0	2.6	12.7	0.0	0.1	6.7	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.5	63.0	0.0	62.4	45.6	0.0	21.8	17.1	0.0	29.7	15.8	0.0
LnGrp LOS	E	E		E	D		C	B		C	B	
Approach Vol, veh/h		72	A		385	A		1566	A		847	A
Approach Delay, s/veh		61.5			61.4			17.5			15.9	
Approach LOS		E			E			B			B	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.0	80.1	20.6	11.3	13.0	75.1	9.7	22.3				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.0	54.0	16.0	18.0	10.5	* 49	5.0	* 29				
Max Q Clear Time (g_c+I1), s	2.0	34.1	14.4	4.6	2.0	18.8	3.0	2.7				
Green Ext Time (p_c), s	0.0	11.1	0.2	0.1	0.2	6.8	0.0	0.1				

Intersection Summary

HCM 6th Ctrl Delay	24.0
HCM 6th LOS	C

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94


Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	20	30	200	415	40	5	145	755	360	5	1635	35
Future Volume (vph)	20	30	200	415	40	5	145	755	360	5	1635	35
Turn Type	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free	2		Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5	
Total Split (s)	15.8	24.5		24.3	33.0		12.2	58.2		13.0	59.0	
Total Split (%)	13.2%	20.4%		20.3%	27.5%		10.2%	48.5%		10.8%	49.2%	
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5	
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5	
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max	
Act Effct Green (s)	6.4	8.0	120.0	18.3	19.7	120.0	71.4	66.2	120.0	72.0	66.5	120.0
Actuated g/C Ratio	0.05	0.07	1.00	0.15	0.16	1.00	0.60	0.55	1.00	0.60	0.55	1.00
v/c Ratio	0.15	0.32	0.17	0.92	0.08	0.00	1.16	0.43	0.25	0.01	0.90	0.02
Control Delay	55.6	59.7	0.2	51.5	22.2	0.0	165.9	17.9	0.4	6.2	26.3	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.6	59.7	0.2	51.5	22.2	0.0	165.9	17.9	0.4	6.2	26.3	0.0
LOS	E	E	A	D	C	A	F	B	A	A	C	A
Approach Delay		11.8			48.4			29.9			25.7	
Approach LOS		B			D			C			C	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 150
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.16
 Intersection Signal Delay: 29.0
 Intersection Capacity Utilization 88.8%
 Analysis Period (min) 15

Intersection LOS: C
 ICU Level of Service E

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2025 Background AM.syn

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	20	30	200	415	40	5	145	755	360	5	1635	35
Future Volume (veh/h)	20	30	200	415	40	5	145	755	360	5	1635	35
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1826	1826	1826	1841	1841	1841	1752	1752	1752	1811	1811	1811
Adj Flow Rate, veh/h	26	39	0	472	45	0	149	778	0	5	1703	0
Peak Hour Factor	0.77	0.77	0.77	0.88	0.88	0.88	0.97	0.97	0.97	0.96	0.96	0.96
Percent Heavy Veh, %	5	5	5	4	4	4	10	10	10	6	6	6
Cap, veh/h	81	74		519	576		153	1770		408	1839	
Arrive On Green	0.02	0.04	0.00	0.15	0.16	0.00	0.04	0.53	0.00	0.05	0.53	0.00
Sat Flow, veh/h	3374	1826	1547	3401	3497	1560	1668	3328	1485	1725	3441	1535
Grp Volume(v), veh/h	26	39	0	472	45	0	149	778	0	5	1703	0
Grp Sat Flow(s),veh/h/ln	1687	1826	1547	1700	1749	1560	1668	1664	1485	1725	1721	1535
Q Serve(g_s), s	0.9	2.5	0.0	16.4	1.3	0.0	4.9	17.1	0.0	0.0	54.7	0.0
Cycle Q Clear(g_c), s	0.9	2.5	0.0	16.4	1.3	0.0	4.9	17.1	0.0	0.0	54.7	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	81	74		519	576		153	1770		408	1839	
V/C Ratio(X)	0.32	0.53		0.91	0.08		0.98	0.44		0.01	0.93	
Avail Cap(c_a), veh/h	261	274		519	787		153	1770		408	1839	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.00	0.68	0.68	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	57.6	56.4	0.0	50.0	42.4	0.0	55.3	17.2	0.0	19.0	25.8	0.0
Incr Delay (d2), s/veh	2.2	5.7	0.0	15.0	0.0	0.0	65.4	0.8	0.0	0.0	9.5	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.4	1.3	0.0	8.0	0.6	0.0	7.1	6.6	0.0	0.1	23.7	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.8	62.1	0.0	65.0	42.4	0.0	120.7	18.0	0.0	19.0	35.3	0.0
LnGrp LOS	E	E		E	D		F	B		B	D	
Approach Vol, veh/h		65	A		517	A		927	A		1708	A
Approach Delay, s/veh		61.2			63.0			34.5			35.2	
Approach LOS		E			E			C			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	13.5	70.8	24.3	11.4	12.7	71.6	9.4	26.3				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	51.2	18.3	18.0	5.2	* 52	9.3	* 27				
Max Q Clear Time (g_c+I1), s	2.0	19.1	18.4	4.5	6.9	56.7	2.9	3.3				
Green Ext Time (p_c), s	0.0	6.3	0.0	0.1	0.0	0.0	0.0	0.2				

Intersection Summary

HCM 6th Ctrl Delay	40.0
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.


Timings
4: US-24 & Newt Dr/SH-94

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	30	35	215	305	25	10	155	1460	280	5	810	35
Future Volume (vph)	30	35	215	305	25	10	155	1460	280	5	810	35
Turn Type	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free	2		Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5	
Total Split (s)	14.0	24.5		23.5	34.0		17.0	59.0		13.0	55.0	
Total Split (%)	11.7%	20.4%		19.6%	28.3%		14.2%	49.2%		10.8%	45.8%	
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5	
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5	
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max	
Act Effct Green (s)	6.7	8.3	120.0	16.8	21.0	120.0	74.8	64.8	120.0	65.8	60.3	120.0
Actuated g/C Ratio	0.06	0.07	1.00	0.14	0.18	1.00	0.62	0.54	1.00	0.55	0.50	1.00
v/c Ratio	0.20	0.35	0.18	0.81	0.05	0.01	0.41	0.80	0.19	0.04	0.52	0.03
Control Delay	56.4	59.9	0.2	42.2	22.4	0.0	18.3	28.1	0.3	8.0	21.1	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.4	59.9	0.2	42.2	22.4	0.0	18.3	28.1	0.3	8.0	21.1	0.0
LOS	E	E	A	D	C	A	B	C	A	A	C	A
Approach Delay		13.7			39.5			23.1			20.1	
Approach LOS		B			D			C			C	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 100
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.81
 Intersection Signal Delay: 23.4
 Intersection Capacity Utilization 77.0%
 Analysis Period (min) 15
 Intersection LOS: C
 ICU Level of Service D

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
4: US-24 & Newt Dr/SH-94

2025 Background PM.syn
09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	30	35	215	305	25	10	155	1460	280	5	810	35
Future Volume (veh/h)	30	35	215	305	25	10	155	1460	280	5	810	35
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1856	1856	1856	1856	1856	1856	1826	1826	1826
Adj Flow Rate, veh/h	39	45	0	386	32	0	161	1521	0	6	900	0
Peak Hour Factor	0.77	0.77	0.77	0.79	0.79	0.79	0.96	0.96	0.96	0.90	0.90	0.90
Percent Heavy Veh, %	2	2	2	3	3	3	3	3	3	5	5	5
Cap, veh/h	105	76		445	480		381	2102		159	1938	
Arrive On Green	0.03	0.04	0.00	0.13	0.14	0.00	0.04	0.60	0.00	0.01	0.56	0.00
Sat Flow, veh/h	3456	1870	1585	3428	3526	1572	1767	3526	1572	1739	3469	1547
Grp Volume(v), veh/h	39	45	0	386	32	0	161	1521	0	6	900	0
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1714	1763	1572	1767	1763	1572	1739	1735	1547
Q Serve(g_s), s	1.3	2.8	0.0	13.2	0.9	0.0	0.0	36.8	0.0	0.0	18.6	0.0
Cycle Q Clear(g_c), s	1.3	2.8	0.0	13.2	0.9	0.0	0.0	36.8	0.0	0.0	18.6	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	105	76		445	480		381	2102		159	1938	
V/C Ratio(X)	0.37	0.59		0.87	0.07		0.42	0.72		0.04	0.46	
Avail Cap(c_a), veh/h	216	281		500	823		455	2102		224	1938	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	0.72	0.72	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	57.1	56.6	0.0	51.2	45.2	0.0	25.0	17.2	0.0	33.4	15.8	0.0
Incr Delay (d2), s/veh	2.2	7.1	0.0	10.4	0.0	0.0	0.7	2.2	0.0	0.1	0.8	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.6	1.5	0.0	6.3	0.4	0.0	3.5	14.8	0.0	0.1	7.4	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.2	63.6	0.0	61.5	45.2	0.0	25.7	19.4	0.0	33.5	16.6	0.0
LnGrp LOS	E	E		E	D		C	B		C	B	
Approach Vol, veh/h		84	A		418	A		1682	A		906	A
Approach Delay, s/veh		61.6			60.3			20.0			16.7	
Approach LOS		E			E			C			B	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.5	78.5	21.6	11.4	12.5	74.5	10.1	22.9				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	52.0	17.5	18.0	10.0	* 48	7.5	* 28				
Max Q Clear Time (g_c+I1), s	2.0	38.8	15.2	4.8	2.0	20.6	3.3	2.9				
Green Ext Time (p_c), s	0.0	8.9	0.3	0.1	0.2	7.2	0.0	0.1				

Intersection Summary

HCM 6th Ctrl Delay	25.6
HCM 6th LOS	C

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94


2025 Total AM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	50	115	560	735	120	5	485	950	525	5	1635	65
Future Volume (vph)	50	115	560	735	120	5	485	950	525	5	1635	65
Turn Type	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free	2		Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5	
Total Split (s)	16.4	24.5		26.5	34.6		22.0	56.0		13.0	47.0	
Total Split (%)	13.7%	20.4%		22.1%	28.8%		18.3%	46.7%		10.8%	39.2%	
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5	
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5	
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max	
Act Effct Green (s)	7.3	13.4	120.0	20.5	29.0	120.0	66.6	53.6	120.0	49.6	44.1	120.0
Actuated g/C Ratio	0.06	0.11	1.00	0.17	0.24	1.00	0.56	0.45	1.00	0.41	0.37	1.00
v/c Ratio	0.27	0.62	0.40	1.39	0.16	0.00	1.90	0.67	0.37	0.03	1.36	0.04
Control Delay	56.5	63.6	0.8	217.2	31.6	0.0	448.2	29.6	0.7	10.4	192.7	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.5	63.6	0.8	217.2	31.6	0.0	448.2	29.6	0.7	10.4	192.7	0.0
LOS	E	E	A	F	C	A	F	C	A	B	F	A
Approach Delay		14.5			190.2			125.5			184.9	
Approach LOS		B			F			F			F	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 150
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.90
 Intersection Signal Delay: 139.7
 Intersection LOS: F
 Intersection Capacity Utilization 116.8%
 ICU Level of Service H
 Analysis Period (min) 15

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2025 Total AM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	50	115	560	735	120	5	485	950	525	5	1635	65
Future Volume (veh/h)	50	115	560	735	120	5	485	950	525	5	1635	65
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1826	1826	1826	1841	1841	1841	1752	1752	1752	1811	1811	1811
Adj Flow Rate, veh/h	54	125	0	799	130	0	500	979	0	5	1703	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.96	0.96	0.96
Percent Heavy Veh, %	5	5	5	4	4	4	10	10	10	6	6	6
Cap, veh/h	117	158		581	764		269	1557		239	1337	
Arrive On Green	0.03	0.09	0.00	0.06	0.07	0.00	0.13	0.47	0.00	0.05	0.39	0.00
Sat Flow, veh/h	3374	1826	1547	3401	3497	1560	1668	3328	1485	1725	3441	1535
Grp Volume(v), veh/h	54	125	0	799	130	0	500	979	0	5	1703	0
Grp Sat Flow(s),veh/h/ln	1687	1826	1547	1700	1749	1560	1668	1664	1485	1725	1721	1535
Q Serve(g_s), s	1.9	8.1	0.0	20.5	4.2	0.0	15.0	26.6	0.0	0.0	46.6	0.0
Cycle Q Clear(g_c), s	1.9	8.1	0.0	20.5	4.2	0.0	15.0	26.6	0.0	0.0	46.6	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	117	158		581	764		269	1557		239	1337	
V/C Ratio(X)	0.46	0.79		1.38	0.17		1.86	0.63		0.02	1.27	
Avail Cap(c_a), veh/h	278	274		581	834		269	1557		239	1337	
HCM Platoon Ratio	1.00	1.00	1.00	0.33	0.33	0.33	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	0.89	0.89	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	56.8	53.8	0.0	56.6	45.5	0.0	50.8	24.1	0.0	37.1	36.7	0.0
Incr Delay (d2), s/veh	2.8	8.6	0.0	178.4	0.1	0.0	401.8	1.9	0.0	0.0	129.1	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.8	4.1	0.0	23.8	1.9	0.0	37.6	10.7	0.0	0.1	43.1	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.6	62.3	0.0	235.0	45.6	0.0	452.6	26.0	0.0	37.2	165.8	0.0
LnGrp LOS	E	E		F	D		F	C		D	F	
Approach Vol, veh/h		179	A		929	A		1479	A		1708	A
Approach Delay, s/veh		61.5			208.5			170.2			165.4	
Approach LOS		E			F			F			F	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	13.5	63.1	26.5	16.9	22.5	54.1	10.7	32.7				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	49.0	20.5	18.0	15.0	* 40	9.9	* 29				
Max Q Clear Time (g_c+I1), s	2.0	28.6	22.5	10.1	17.0	48.6	3.9	6.2				
Green Ext Time (p_c), s	0.0	7.3	0.0	0.3	0.0	0.0	0.0	0.7				

Intersection Summary

HCM 6th Ctrl Delay	172.1
HCM 6th LOS	F

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94


2025 Total PM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	55	110	525	650	110	10	515	1755	530	5	810	65
Future Volume (vph)	55	110	525	650	110	10	515	1755	530	5	810	65
Turn Type	Prot	NA	Free	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			Free			Free	2		Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5	
Total Split (s)	12.4	24.5		25.5	37.6		36.0	57.0		13.0	34.0	
Total Split (%)	10.3%	20.4%		21.3%	31.3%		30.0%	47.5%		10.8%	28.3%	
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5	
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5	
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max	
Act Effct Green (s)	5.9	13.0	120.0	19.5	29.1	120.0	68.0	55.0	120.0	37.0	31.5	120.0
Actuated g/C Ratio	0.05	0.11	1.00	0.16	0.24	1.00	0.57	0.46	1.00	0.31	0.26	1.00
v/c Ratio	0.36	0.59	0.36	1.28	0.14	0.01	1.07	1.14	0.35	0.04	0.98	0.05
Control Delay	61.5	62.5	0.6	180.3	32.8	0.0	98.8	102.1	0.6	11.6	60.7	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.5	62.5	0.6	180.3	32.8	0.0	98.8	102.1	0.6	11.6	60.7	0.0
LOS	E	E	A	F	C	A	F	F	A	B	E	A
Approach Delay		15.4			156.8			82.3			55.9	
Approach LOS		B			F			F			E	

Intersection Summary


Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 150
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.28
 Intersection Signal Delay: 79.9
 Intersection Capacity Utilization 95.0%
 Analysis Period (min) 15
 Intersection LOS: E
 ICU Level of Service F

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2025 Total PM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	55	110	525	650	110	10	515	1755	530	5	810	65
Future Volume (veh/h)	55	110	525	650	110	10	515	1755	530	5	810	65
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1856	1856	1856	1856	1856	1856	1826	1826	1826
Adj Flow Rate, veh/h	60	120	0	707	120	0	536	1828	0	5	880	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.96	0.96	0.96	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	3	3	3	3	3	3	5	5	5
Cap, veh/h	125	154		557	721		502	1693		147	987	
Arrive On Green	0.04	0.08	0.00	0.05	0.07	0.00	0.24	0.48	0.00	0.05	0.28	0.00
Sat Flow, veh/h	3456	1870	1585	3428	3526	1572	1767	3526	1572	1739	3469	1547
Grp Volume(v), veh/h	60	120	0	707	120	0	536	1828	0	5	880	0
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1714	1763	1572	1767	1763	1572	1739	1735	1547
Q Serve(g_s), s	2.0	7.6	0.0	19.5	3.9	0.0	29.0	57.6	0.0	0.0	29.2	0.0
Cycle Q Clear(g_c), s	2.0	7.6	0.0	19.5	3.9	0.0	29.0	57.6	0.0	0.0	29.2	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	125	154		557	721		502	1693		147	987	
V/C Ratio(X)	0.48	0.78		1.27	0.17		1.07	1.08		0.03	0.89	
Avail Cap(c_a), veh/h	170	281		557	928		502	1693		147	987	
HCM Platoon Ratio	1.00	1.00	1.00	0.33	0.33	0.33	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.00	0.91	0.91	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	56.7	54.0	0.0	56.8	46.3	0.0	43.3	31.2	0.0	54.2	41.2	0.0
Incr Delay (d2), s/veh	2.9	8.3	0.0	133.6	0.1	0.0	59.1	46.8	0.0	0.1	12.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.9	3.9	0.0	19.3	1.7	0.0	22.2	34.5	0.0	0.1	14.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.6	62.3	0.0	190.4	46.4	0.0	102.4	78.0	0.0	54.2	53.2	0.0
LnGrp LOS	E	E		F	D		F	F		D	D	
Approach Vol, veh/h		180	A		827	A		2364	A		885	A
Approach Delay, s/veh		61.4			169.5			83.5			53.2	
Approach LOS		E			F			F			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	13.5	64.6	25.5	16.4	36.5	41.6	10.8	31.0				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	50.0	19.5	18.0	29.0	* 27	5.9	* 32				
Max Q Clear Time (g_c+I1), s	2.0	59.6	21.5	9.6	31.0	31.2	4.0	5.9				
Green Ext Time (p_c), s	0.0	0.0	0.0	0.3	0.0	0.0	0.0	0.7				

Intersection Summary

HCM 6th Ctrl Delay	93.0
HCM 6th LOS	F

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94

2025 Total AM Improved.syn

09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑
Traffic Volume (vph)	50	115	560	735	120	5	485	950	525	5	1635
Future Volume (vph)	50	115	560	735	120	5	485	950	525	5	1635
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA
Protected Phases	7	4		3	8		5	2		1	6
Permitted Phases			Free			Free			Free	6	
Detector Phase	7	4		3	8		5	2		1	6
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5
Total Split (s)	12.4	24.5		39.0	51.1		30.1	72.6		13.9	56.4
Total Split (%)	8.3%	16.3%		26.0%	34.1%		20.1%	48.4%		9.3%	37.6%
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max
Act Effct Green (s)	5.9	15.0	150.0	33.0	44.5	150.0	23.1	68.6	150.0	58.3	51.9
Actuated g/C Ratio	0.04	0.10	1.00	0.22	0.30	1.00	0.15	0.46	1.00	0.39	0.35
v/c Ratio	0.42	0.69	0.40	1.08	0.13	0.00	1.02	0.45	0.37	0.02	1.05
Control Delay	80.2	84.7	0.8	110.6	39.2	0.0	107.2	29.1	0.7	19.4	83.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	80.2	84.7	0.8	110.6	39.2	0.0	107.2	29.1	0.7	19.4	83.0
LOS	F	F	A	F	D	A	F	C	A	B	F
Approach Delay		19.5			100.1			40.8			82.8
Approach LOS		B			F			D			F

Intersection Summary


Cycle Length: 150
 Actuated Cycle Length: 150
 Offset: 0 (0%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 150
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.08
 Intersection Signal Delay: 61.3
 Intersection Capacity Utilization 91.6%
 Analysis Period (min) 15
 Intersection LOS: E
 ICU Level of Service F

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2025 Total AM Improved.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↔↔	↑	↗	↔↔	↑↑	↗	↔↔	↑↑↑	↗	↖	↑↑↑	↖
Traffic Volume (veh/h)	50	115	560	735	120	5	485	950	525	5	1635	65
Future Volume (veh/h)	50	115	560	735	120	5	485	950	525	5	1635	65
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1826	1826	1826	1841	1841	1841	1752	1752	1752	1811	1811	1811
Adj Flow Rate, veh/h	54	125	0	799	130	0	500	979	0	5	1703	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.96	0.96	0.96
Percent Heavy Veh, %	5	5	5	4	4	4	10	10	10	6	6	6
Cap, veh/h	101	151		748	942		498	2255		252	1781	
Arrive On Green	0.03	0.08	0.00	0.22	0.27	0.00	0.15	0.47	0.00	0.05	0.36	0.00
Sat Flow, veh/h	3374	1826	1547	3401	3497	1560	3237	4782	1485	1725	5107	0
Grp Volume(v), veh/h	54	125	0	799	130	0	500	979	0	5	1703	0
Grp Sat Flow(s),veh/h/ln	1687	1826	1547	1700	1749	1560	1618	1594	1485	1725	1648	0
Q Serve(g_s), s	2.4	10.1	0.0	33.0	4.2	0.0	23.1	20.4	0.0	0.0	50.4	0.0
Cycle Q Clear(g_c), s	2.4	10.1	0.0	33.0	4.2	0.0	23.1	20.4	0.0	0.0	50.4	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		0.00
Lane Grp Cap(c), veh/h	101	151		748	942		498	2255		252	1781	
V/C Ratio(X)	0.54	0.83		1.07	0.14		1.00	0.43		0.02	0.96	
Avail Cap(c_a), veh/h	133	219		748	1052		498	2255		252	1781	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.90	0.90	0.00	0.89	0.89	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	71.7	67.8	0.0	58.5	41.6	0.0	63.5	26.3	0.0	40.3	46.8	0.0
Incr Delay (d2), s/veh	4.0	14.5	0.0	50.8	0.1	0.0	41.1	0.6	0.0	0.0	13.2	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.1	5.3	0.0	19.5	1.9	0.0	12.4	8.0	0.0	0.1	22.8	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	75.7	82.3	0.0	109.3	41.7	0.0	104.5	26.9	0.0	40.3	60.0	0.0
LnGrp LOS	E	F		F	D		F	C		D	E	
Approach Vol, veh/h		179	A		929	A		1479	A		1708	A
Approach Delay, s/veh		80.3			99.8			53.2			60.0	
Approach LOS		F			F			D			E	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	14.4	77.7	39.0	18.9	30.6	61.5	11.0	46.9				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	6.4	65.6	33.0	18.0	23.1	* 49	5.9	* 45				
Max Q Clear Time (g_c+I1), s	2.0	22.4	35.0	12.1	25.1	52.4	4.4	6.2				
Green Ext Time (p_c), s	0.0	8.9	0.0	0.2	0.0	0.0	0.0	0.8				

Intersection Summary

HCM 6th Ctrl Delay	67.1
HCM 6th LOS	E

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑
Traffic Volume (vph)	55	110	525	650	110	10	515	1755	530	5	810
Future Volume (vph)	55	110	525	650	110	10	515	1755	530	5	810
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA
Protected Phases	7	4		3	8		5	2		1	6
Permitted Phases			Free			Free			Free	6	
Detector Phase	7	4		3	8		5	2		1	6
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5
Total Split (s)	13.4	24.5		33.5	44.6		36.0	49.0		13.0	26.0
Total Split (%)	11.2%	20.4%		27.9%	37.2%		30.0%	40.8%		10.8%	21.7%
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max
Act Effct Green (s)	6.6	13.0	120.0	27.0	35.8	120.0	29.0	47.5	120.0	29.5	24.0
Actuated g/C Ratio	0.06	0.11	1.00	0.22	0.30	1.00	0.24	0.40	1.00	0.25	0.20
v/c Ratio	0.32	0.59	0.36	0.93	0.11	0.01	0.65	0.92	0.35	0.04	0.97
Control Delay	69.3	57.6	0.6	61.0	26.7	0.0	45.4	43.4	0.6	16.4	60.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	69.3	57.6	0.6	61.0	26.7	0.0	45.4	43.4	0.6	16.4	60.2
LOS	E	E	A	E	C	A	D	D	A	B	E
Approach Delay		15.2			55.3			35.7			59.9
Approach LOS		B			E			D			E

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 110
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.97
 Intersection Signal Delay: 40.1
 Intersection LOS: D
 Intersection Capacity Utilization 80.4%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2025 Total PM Improved.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↔↔	↑	↗	↔↔	↑↑	↗	↔↔	↑↑↑	↗	↖	↑↑↑	↖
Traffic Volume (veh/h)	55	110	525	650	110	10	515	1755	530	5	810	65
Future Volume (veh/h)	55	110	525	650	110	10	515	1755	530	5	810	65
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1856	1856	1856	1856	1856	1856	1826	1826	1826
Adj Flow Rate, veh/h	60	120	0	707	120	0	536	1828	0	5	880	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.96	0.96	0.96	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	3	3	3	3	3	3	5	5	5
Cap, veh/h	125	154		769	939		679	2341		71	1328	
Arrive On Green	0.04	0.08	0.00	0.07	0.09	0.00	0.20	0.46	0.00	0.01	0.27	0.00
Sat Flow, veh/h	3456	1870	1585	3428	3526	1572	3428	5066	1572	1739	5149	0
Grp Volume(v), veh/h	60	120	0	707	120	0	536	1828	0	5	880	0
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1714	1763	1572	1714	1689	1572	1739	1662	0
Q Serve(g_s), s	2.0	7.6	0.0	24.6	3.8	0.0	17.8	36.4	0.0	0.0	18.9	0.0
Cycle Q Clear(g_c), s	2.0	7.6	0.0	24.6	3.8	0.0	17.8	36.4	0.0	0.0	18.9	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		0.00
Lane Grp Cap(c), veh/h	125	154		769	939		679	2341		71	1328	
V/C Ratio(X)	0.48	0.78		0.92	0.13		0.79	0.78		0.07	0.66	
Avail Cap(c_a), veh/h	199	281		786	1134		829	2341		140	1328	
HCM Platoon Ratio	1.00	1.00	1.00	0.33	0.33	0.33	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.90	0.90	0.00	0.90	0.90	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	56.7	54.0	0.0	54.5	41.9	0.0	45.7	27.2	0.0	59.2	39.2	0.0
Incr Delay (d2), s/veh	2.6	7.5	0.0	14.5	0.1	0.0	4.2	2.7	0.0	0.4	2.6	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.9	3.9	0.0	12.9	1.7	0.0	8.0	14.9	0.0	0.2	8.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.3	61.5	0.0	69.0	41.9	0.0	50.0	29.8	0.0	59.6	41.8	0.0
LnGrp LOS	E	E		E	D		D	C		E	D	
Approach Vol, veh/h		180	A		827	A		2364	A		885	A
Approach Delay, s/veh		60.8			65.1			34.4			41.9	
Approach LOS		E			E			C			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.3	62.5	32.9	16.4	31.3	39.5	10.8	38.4				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	42.0	27.5	18.0	29.0	* 19	6.9	* 39				
Max Q Clear Time (g_c+I1), s	2.0	38.4	26.6	9.6	19.8	20.9	4.0	5.8				
Green Ext Time (p_c), s	0.0	3.1	0.3	0.3	1.4	0.0	0.0	0.7				

Intersection Summary

HCM 6th Ctrl Delay	43.0
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑
Traffic Volume (vph)	20	35	235	495	50	5	170	895	425	10	1945
Future Volume (vph)	20	35	235	495	50	5	170	895	425	10	1945
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA
Protected Phases	7	4		3	8		5	2		1	6
Permitted Phases			Free			Free			Free	6	
Detector Phase	7	4		3	8		5	2		1	6
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5
Total Split (s)	14.0	24.6		34.4	45.0		21.0	78.0		13.0	70.0
Total Split (%)	9.3%	16.4%		22.9%	30.0%		14.0%	52.0%		8.7%	46.7%
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max
Act Effct Green (s)	6.4	8.5	150.0	27.1	31.6	150.0	14.0	84.3	150.0	81.3	75.8
Actuated g/C Ratio	0.04	0.06	1.00	0.18	0.21	1.00	0.09	0.56	1.00	0.54	0.51
v/c Ratio	0.15	0.37	0.17	0.89	0.07	0.00	0.59	0.35	0.30	0.03	0.84
Control Delay	71.2	77.4	0.2	77.1	47.1	0.0	74.0	19.3	0.5	13.1	37.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	71.2	77.4	0.2	77.1	47.1	0.0	74.0	19.3	0.5	13.1	37.0
LOS	E	E	A	E	D	A	E	B	A	B	D
Approach Delay		14.5			73.7			20.2			36.9
Approach LOS		B			E			C			D

Intersection Summary

Cycle Length: 150
 Actuated Cycle Length: 150
 Offset: 0 (0%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 120
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.89
 Intersection Signal Delay: 34.5
 Intersection LOS: C
 Intersection Capacity Utilization 81.3%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2040 Background AM.syn

08/03/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↔↔	↑	↗	↔↔	↑↑	↗	↔↔	↑↑↑	↗	↘	↑↑↑	↘
Traffic Volume (veh/h)	20	35	235	495	50	5	170	895	425	10	1945	45
Future Volume (veh/h)	20	35	235	495	50	5	170	895	425	10	1945	45
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1826	1826	1826	1841	1841	1841	1752	1752	1752	1811	1811	1811
Adj Flow Rate, veh/h	22	38	0	538	54	0	175	923	0	10	2026	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.96	0.96	0.96
Percent Heavy Veh, %	5	5	5	4	4	4	10	10	10	6	6	6
Cap, veh/h	67	62		589	644		220	2860		334	2677	
Arrive On Green	0.02	0.03	0.00	0.17	0.18	0.00	0.07	0.60	0.00	0.01	0.54	0.00
Sat Flow, veh/h	3374	1826	1547	3401	3497	1560	3237	4782	1485	1725	5107	0
Grp Volume(v), veh/h	22	38	0	538	54	0	175	923	0	10	2026	0
Grp Sat Flow(s),veh/h/ln	1687	1826	1547	1700	1749	1560	1618	1594	1485	1725	1648	0
Q Serve(g_s), s	1.0	3.1	0.0	23.3	1.9	0.0	8.0	14.4	0.0	0.0	47.8	0.0
Cycle Q Clear(g_c), s	1.0	3.1	0.0	23.3	1.9	0.0	8.0	14.4	0.0	0.0	47.8	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		0.00
Lane Grp Cap(c), veh/h	67	62		589	644		220	2860		334	2677	
V/C Ratio(X)	0.33	0.61		0.91	0.08		0.80	0.32		0.03	0.76	
Avail Cap(c_a), veh/h	169	220		644	909		302	2860		372	2677	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.98	0.98	0.00	0.65	0.65	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	72.5	71.5	0.0	60.9	50.7	0.0	68.9	15.0	0.0	22.3	26.7	0.0
Incr Delay (d2), s/veh	2.7	9.1	0.0	11.9	0.0	0.0	9.9	0.3	0.0	0.0	2.1	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.4	1.6	0.0	11.1	0.9	0.0	3.6	5.4	0.0	0.2	19.1	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	75.2	80.6	0.0	72.8	50.8	0.0	78.8	15.3	0.0	22.3	28.8	0.0
LnGrp LOS	E	F		E	D		E	B		C	C	
Approach Vol, veh/h		60	A		592	A		1098	A		2036	A
Approach Delay, s/veh		78.6			70.7			25.4			28.7	
Approach LOS		E			E			C			C	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	9.7	96.7	32.0	11.6	17.7	88.7	9.5	34.1				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	71.0	28.4	18.1	14.0	* 63	7.5	* 39				
Max Q Clear Time (g_c+I1), s	2.0	16.4	25.3	5.1	10.0	49.8	3.0	3.9				
Green Ext Time (p_c), s	0.0	8.4	0.7	0.1	0.2	10.4	0.0	0.3				

Intersection Summary

HCM 6th Ctrl Delay	35.1
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑
Traffic Volume (vph)	30	45	255	360	30	10	180	1735	330	5	960
Future Volume (vph)	30	45	255	360	30	10	180	1735	330	5	960
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA
Protected Phases	7	4		3	8		5	2		1	6
Permitted Phases			Free			Free			Free		6
Detector Phase	7	4		3	8		5	2		1	6
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5
Total Split (s)	13.0	24.5		22.5	34.0		21.0	60.0		13.0	52.0
Total Split (%)	10.8%	20.4%		18.8%	28.3%		17.5%	50.0%		10.8%	43.3%
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max
Act Effct Green (s)	6.2	8.5	120.0	16.1	21.0	120.0	14.0	65.2	120.0	62.2	56.7
Actuated g/C Ratio	0.05	0.07	1.00	0.13	0.18	1.00	0.12	0.54	1.00	0.52	0.47
v/c Ratio	0.19	0.37	0.17	0.86	0.05	0.01	0.47	0.66	0.22	0.04	0.47
Control Delay	51.4	58.0	0.2	45.0	25.1	0.0	53.9	22.0	0.3	7.8	19.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.4	58.0	0.2	45.0	25.1	0.0	53.9	22.0	0.3	7.8	19.8
LOS	D	E	A	D	C	A	D	C	A	A	B
Approach Delay		12.8			42.4			21.4			19.8
Approach LOS		B			D			C			B

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.86
 Intersection Signal Delay: 22.4
 Intersection LOS: C
 Intersection Capacity Utilization 71.7%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
4: US-24 & Newt Dr/SH-94

2040 Background PM.syn
08/03/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑	↖
Traffic Volume (veh/h)	30	45	255	360	30	10	180	1735	330	5	960	40
Future Volume (veh/h)	30	45	255	360	30	10	180	1735	330	5	960	40
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1856	1856	1856	1856	1856	1856	1826	1826	1826
Adj Flow Rate, veh/h	33	49	0	391	33	0	188	1807	0	5	1043	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.96	0.96	0.96	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	3	3	3	3	3	3	5	5	5
Cap, veh/h	96	79		446	496		250	3019		148	2618	
Arrive On Green	0.03	0.04	0.00	0.13	0.14	0.00	0.07	0.60	0.00	0.01	0.53	0.00
Sat Flow, veh/h	3456	1870	1585	3428	3526	1572	3428	5066	1572	1739	5149	0
Grp Volume(v), veh/h	33	49	0	391	33	0	188	1807	0	5	1043	0
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1714	1763	1572	1714	1689	1572	1739	1662	0
Q Serve(g_s), s	1.1	3.1	0.0	13.4	1.0	0.0	6.5	26.9	0.0	0.0	15.1	0.0
Cycle Q Clear(g_c), s	1.1	3.1	0.0	13.4	1.0	0.0	6.5	26.9	0.0	0.0	15.1	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		0.00
Lane Grp Cap(c), veh/h	96	79		446	496		250	3019		148	2618	
V/C Ratio(X)	0.34	0.62		0.88	0.07		0.75	0.60		0.03	0.40	
Avail Cap(c_a), veh/h	187	281		471	823		400	3019		216	2618	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.97	0.97	0.00	0.66	0.66	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	57.3	56.5	0.0	51.2	44.7	0.0	54.5	15.2	0.0	29.3	17.1	0.0
Incr Delay (d2), s/veh	2.0	7.3	0.0	11.5	0.0	0.0	4.5	0.9	0.0	0.1	0.5	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	1.6	0.0	6.5	0.4	0.0	2.9	10.2	0.0	0.1	5.8	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.3	63.8	0.0	62.7	44.8	0.0	59.0	16.1	0.0	29.4	17.6	0.0
LnGrp LOS	E	E		E	D		E	B		C	B	
Approach Vol, veh/h		82	A		424	A		1995	A		1048	A
Approach Delay, s/veh		62.0			61.3			20.2			17.6	
Approach LOS		E			E			C			B	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.3	78.5	21.6	11.6	16.3	70.5	9.8	23.4				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	53.0	16.5	18.0	14.0	* 45	6.5	* 28				
Max Q Clear Time (g_c+I1), s	2.0	28.9	15.4	5.1	8.5	17.1	3.1	3.0				
Green Ext Time (p_c), s	0.0	15.4	0.2	0.1	0.3	8.6	0.0	0.1				

Intersection Summary

HCM 6th Ctrl Delay	25.3
HCM 6th LOS	C

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94

2040 Total AM.syn
09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑
Traffic Volume (vph)	50	120	595	815	130	5	510	1090	590	10	1945
Future Volume (vph)	50	120	595	815	130	5	510	1090	590	10	1945
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA
Protected Phases	7	4		3	8		5	2		1	6
Permitted Phases			Free			Free			Free	6	
Detector Phase	7	4		3	8		5	2		1	6
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5
Total Split (s)	14.5	25.6		38.0	49.1		26.4	73.0		13.4	60.0
Total Split (%)	9.7%	17.1%		25.3%	32.7%		17.6%	48.7%		8.9%	40.0%
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max
Act Effect Green (s)	7.3	15.5	150.0	32.0	42.6	150.0	19.4	69.6	150.0	62.0	56.1
Actuated g/C Ratio	0.05	0.10	1.00	0.21	0.28	1.00	0.13	0.46	1.00	0.41	0.37
v/c Ratio	0.33	0.70	0.42	1.23	0.14	0.00	1.28	0.51	0.41	0.06	1.15
Control Delay	74.4	83.9	0.8	165.1	40.9	0.0	193.5	29.7	0.9	19.8	118.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	74.4	83.9	0.8	165.1	40.9	0.0	193.5	29.7	0.9	19.8	118.3
LOS	E	F	A	F	D	A	F	C	A	B	F
Approach Delay		18.6			147.3			60.1			117.8
Approach LOS		B			F			E			F

Intersection Summary

Cycle Length: 150
 Actuated Cycle Length: 150
 Offset: 0 (0%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 150
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.28
 Intersection Signal Delay: 88.6
 Intersection Capacity Utilization 100.8%
 Analysis Period (min) 15
 Intersection LOS: F
 ICU Level of Service G

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2040 Total AM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↔↔	↑	↗	↔↔	↑↑	↗	↔↔	↑↑↑	↗	↘	↑↑↑	↘
Traffic Volume (veh/h)	50	120	595	815	130	5	510	1090	590	10	1945	75
Future Volume (veh/h)	50	120	595	815	130	5	510	1090	590	10	1945	75
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1826	1826	1826	1841	1841	1841	1752	1752	1752	1811	1811	1811
Adj Flow Rate, veh/h	54	130	0	886	141	0	526	1124	0	10	2026	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97	0.96	0.96	0.96
Percent Heavy Veh, %	5	5	5	4	4	4	10	10	10	6	6	6
Cap, veh/h	101	156		726	929		419	2289		232	1921	
Arrive On Green	0.03	0.09	0.00	0.21	0.27	0.00	0.13	0.48	0.00	0.04	0.39	0.00
Sat Flow, veh/h	3374	1826	1547	3401	3497	1560	3237	4782	1485	1725	5107	0
Grp Volume(v), veh/h	54	130	0	886	141	0	526	1124	0	10	2026	0
Grp Sat Flow(s),veh/h/ln	1687	1826	1547	1700	1749	1560	1618	1594	1485	1725	1648	0
Q Serve(g_s), s	2.4	10.5	0.0	32.0	4.6	0.0	19.4	24.0	0.0	0.0	58.3	0.0
Cycle Q Clear(g_c), s	2.4	10.5	0.0	32.0	4.6	0.0	19.4	24.0	0.0	0.0	58.3	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		0.00
Lane Grp Cap(c), veh/h	101	156		726	929		419	2289		232	1921	
V/C Ratio(X)	0.54	0.83		1.22	0.15		1.26	0.49		0.04	1.05	
Avail Cap(c_a), veh/h	180	232		726	1005		419	2289		232	1921	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.87	0.87	0.00	0.78	0.78	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	71.7	67.6	0.0	59.0	42.2	0.0	65.3	26.7	0.0	40.7	45.9	0.0
Incr Delay (d2), s/veh	3.8	13.2	0.0	109.3	0.1	0.0	133.6	0.8	0.0	0.1	36.6	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.1	5.5	0.0	24.8	2.0	0.0	15.8	9.4	0.0	0.3	30.2	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	75.6	80.8	0.0	168.3	42.2	0.0	198.9	27.4	0.0	40.8	82.5	0.0
LnGrp LOS	E	F		F	D		F	C		D	F	
Approach Vol, veh/h		184	A		1027	A		1650	A		2036	A
Approach Delay, s/veh		79.3			151.0			82.1			82.3	
Approach LOS		E			F			F			F	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	13.9	78.8	38.0	19.3	26.9	65.8	11.0	46.3				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.9	66.0	32.0	19.1	19.4	* 53	8.0	* 43				
Max Q Clear Time (g_c+I1), s	2.0	26.0	34.0	12.5	21.4	60.3	4.4	6.6				
Green Ext Time (p_c), s	0.0	10.5	0.0	0.3	0.0	0.0	0.0	0.9				

Intersection Summary

HCM 6th Ctrl Delay	96.5
HCM 6th LOS	F

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
4: US-24 & Newt Dr/SH-94

2040 Total PM.syn
09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Configurations	↖↗	↑	↖	↖↗	↑↑	↖	↖↗	↑↑↑	↖	↖	↑↑↑
Traffic Volume (vph)	55	120	565	705	115	10	540	2030	580	5	960
Future Volume (vph)	55	120	565	705	115	10	540	2030	580	5	960
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	Free	pm+pt	NA
Protected Phases	7	4		3	8		5	2		1	6
Permitted Phases			Free			Free			Free	6	
Detector Phase	7	4		3	8		5	2		1	6
Switch Phase											
Minimum Initial (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0
Minimum Split (s)	11.5	24.5		11.0	24.0		12.0	25.0		12.5	25.5
Total Split (s)	15.4	24.5		33.5	42.6		35.0	49.0		13.0	27.0
Total Split (%)	12.8%	20.4%		27.9%	35.5%		29.2%	40.8%		10.8%	22.5%
Yellow Time (s)	3.5	3.5		4.0	4.0		5.0	5.0		5.5	5.5
All-Red Time (s)	3.0	3.0		2.0	2.0		2.0	2.0		2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0
Total Lost Time (s)	6.5	6.5		6.0	6.0		7.0	7.0		7.5	7.5
Lead/Lag	Lead	Lag		Lead	Lag		Lag	Lead		Lag	Lead
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes		Yes	Yes
Recall Mode	None	None		None	None		C-Max	Max		C-Max	Max
Act Effct Green (s)	7.4	13.5	120.0	27.5	36.0	120.0	28.0	46.5	120.0	29.5	24.0
Actuated g/C Ratio	0.06	0.11	1.00	0.23	0.30	1.00	0.23	0.39	1.00	0.25	0.20
v/c Ratio	0.28	0.62	0.39	0.98	0.12	0.01	0.71	1.08	0.39	0.04	1.14
Control Delay	67.4	58.6	0.7	57.1	23.3	0.0	48.0	83.0	0.7	14.4	107.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	67.4	58.6	0.7	57.1	23.3	0.0	48.0	83.0	0.7	14.4	107.0
LOS	E	E	A	E	C	A	D	F	A	B	F
Approach Delay		15.0			51.7			61.8			106.6
Approach LOS		B			D			E			F

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 110 (92%), Referenced to phase 1:SBL and 5:NBL, Start of Green
 Natural Cycle: 130
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.14
 Intersection Signal Delay: 62.4
 Intersection Capacity Utilization 87.3%
 Analysis Period (min) 15

Intersection LOS: E
 ICU Level of Service E

Splits and Phases: 4: US-24 & Newt Dr/SH-94



HCM 6th Signalized Intersection Summary
 4: US-24 & Newt Dr/SH-94

2040 Total PM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↔↔	↑	↗	↔↔	↑↑	↗	↔↔	↑↑↑	↗	↘	↑↑↑	↘
Traffic Volume (veh/h)	55	120	565	705	115	10	540	2030	580	5	960	70
Future Volume (veh/h)	55	120	565	705	115	10	540	2030	580	5	960	70
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1856	1856	1856	1856	1856	1856	1826	1826	1826
Adj Flow Rate, veh/h	60	130	0	766	125	0	562	2115	0	5	1043	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.96	0.96	0.96	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	3	3	3	3	3	3	5	5	5
Cap, veh/h	125	164		786	975		650	2289		71	1318	
Arrive On Green	0.04	0.09	0.00	0.08	0.09	0.00	0.19	0.45	0.00	0.01	0.26	0.00
Sat Flow, veh/h	3456	1870	1585	3428	3526	1572	3428	5066	1572	1739	5149	0
Grp Volume(v), veh/h	60	130	0	766	125	0	562	2115	0	5	1043	0
Grp Sat Flow(s),veh/h/ln	1728	1870	1585	1714	1763	1572	1714	1689	1572	1739	1662	0
Q Serve(g_s), s	2.0	8.2	0.0	26.8	3.9	0.0	19.1	47.1	0.0	0.0	23.4	0.0
Cycle Q Clear(g_c), s	2.0	8.2	0.0	26.8	3.9	0.0	19.1	47.1	0.0	0.0	23.4	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		0.00
Lane Grp Cap(c), veh/h	125	164		786	975		650	2289		71	1318	
V/C Ratio(X)	0.48	0.79		0.97	0.13		0.86	0.92		0.07	0.79	
Avail Cap(c_a), veh/h	256	281		786	1075		800	2289		140	1318	
HCM Platoon Ratio	1.00	1.00	1.00	0.33	0.33	0.33	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.84	0.84	0.00	0.59	0.59	0.00	1.00	1.00	0.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	56.7	53.7	0.0	55.1	41.2	0.0	47.1	30.9	0.0	59.2	41.1	0.0
Incr Delay (d2), s/veh	2.4	7.1	0.0	18.9	0.0	0.0	8.3	7.8	0.0	0.4	4.9	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.9	4.2	0.0	14.4	1.7	0.0	8.9	20.3	0.0	0.2	10.1	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.2	60.8	0.0	74.0	41.3	0.0	55.4	38.7	0.0	59.6	46.0	0.0
LnGrp LOS	E	E		E	D		E	D		E	D	
Approach Vol, veh/h		190	A		891	A		2677	A		1048	A
Approach Delay, s/veh		60.3			69.4			42.2			46.1	
Approach LOS		E			E			D			D	
Timer - Assigned Phs	1	2	3	4	5	6	7	8				
Phs Duration (G+Y+Rc), s	8.3	61.2	33.5	17.0	30.3	39.2	10.8	39.7				
Change Period (Y+Rc), s	7.5	7.0	6.0	6.5	7.5	* 7.5	6.5	* 6.5				
Max Green Setting (Gmax), s	5.5	42.0	27.5	18.0	28.0	* 20	8.9	* 37				
Max Q Clear Time (g_c+I1), s	2.0	49.1	28.8	10.2	21.1	25.4	4.0	5.9				
Green Ext Time (p_c), s	0.0	0.0	0.0	0.3	1.3	0.0	0.0	0.8				

Intersection Summary

HCM 6th Ctrl Delay	48.8
HCM 6th LOS	D

Notes

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.
 Unsignalized Delay for [NBR, EBR, WBR, SBR] is excluded from calculations of the approach delay and intersection delay.

Timings

5: Marksheffel Rd & SH-94




Lane Group	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↗	↖	↑	↗	↖	↑↑	↗	↖	↑↑	↗
Traffic Volume (vph)	254	54	28	297	77	54	270	18	256	501	3
Future Volume (vph)	254	54	28	297	77	54	270	18	256	501	3
Turn Type	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	4			8		5	2		1	6	
Permitted Phases		4	8		8	2		2	6		6
Detector Phase	4	4	8	8	8	5	2	2	1	6	6
Switch Phase											
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	51.0	51.0	51.0	51.0	51.0	16.0	32.0	32.0	37.0	53.0	53.0
Total Split (%)	42.5%	42.5%	42.5%	42.5%	42.5%	13.3%	26.7%	26.7%	30.8%	44.2%	44.2%
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag						Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)	29.0	29.0	29.0	29.0	29.0	64.9	57.6	57.6	78.2	67.1	67.1
Actuated g/C Ratio	0.24	0.24	0.24	0.24	0.24	0.54	0.48	0.48	0.65	0.56	0.56
v/c Ratio	0.74	0.14	0.24	0.79	0.19	0.14	0.20	0.03	0.42	0.29	0.00
Control Delay	48.6	0.6	38.3	55.3	1.2	10.9	20.7	0.1	6.8	6.2	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	48.6	0.6	38.3	55.3	1.2	10.9	20.7	0.1	6.8	6.2	0.0
LOS	D	A	D	E	A	B	C	A	A	A	A
Approach Delay	40.2			43.7			18.1			6.4	
Approach LOS	D			D			B			A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 28 (23%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.79
 Intersection Signal Delay: 22.8
 Intersection Capacity Utilization 60.7%
 Analysis Period (min) 15
 Intersection LOS: C
 ICU Level of Service B

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary

2020 Adjusted Existing AM.syn

5: Marksheffel Rd & SH-94

06/24/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	0	254	54	28	297	77	54	270	18	256	501	3
Future Volume (veh/h)	0	254	54	28	297	77	54	270	18	256	501	3
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	0	314	67	32	341	89	66	329	22	294	576	3
Peak Hour Factor	0.81	0.81	0.81	0.87	0.87	0.87	0.82	0.82	0.82	0.87	0.87	0.87
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	60	394	334	127	400	339	534	1820	812	715	2057	918
Arrive On Green	0.00	0.44	0.44	0.22	0.22	0.22	0.04	0.52	0.52	0.10	0.58	0.58
Sat Flow, veh/h	912	1781	1510	970	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	0	314	67	32	341	89	66	329	22	294	576	3
Grp Sat Flow(s),veh/h/ln	912	1781	1510	970	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	0.0	18.2	3.3	3.8	21.7	5.8	2.1	6.0	0.8	8.7	9.8	0.1
Cycle Q Clear(g_c), s	0.0	18.2	3.3	22.0	21.7	5.8	2.1	6.0	0.8	8.7	9.8	0.1
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	60	394	334	127	400	339	534	1820	812	715	2057	918
V/C Ratio(X)	0.00	0.80	0.20	0.25	0.85	0.26	0.12	0.18	0.03	0.41	0.28	0.00
Avail Cap(c_a), veh/h	200	668	566	276	679	576	607	1820	812	994	2057	918
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.00	0.98	0.98	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	0.0	31.2	27.0	53.8	44.9	38.6	12.0	15.0	13.8	9.8	12.4	10.4
Incr Delay (d2), s/veh	0.0	3.7	0.3	1.0	5.3	0.4	0.1	0.2	0.1	0.4	0.3	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	6.6	1.2	1.0	10.3	2.2	0.8	2.4	0.3	3.3	3.9	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	0.0	34.8	27.3	54.8	50.1	39.1	12.1	15.2	13.8	10.2	12.8	10.4
LnGrp LOS	A	C	C	D	D	D	B	B	B	B	B	B
Approach Vol, veh/h		381			462			417			873	
Approach Delay, s/veh		33.5			48.3			14.6			11.9	
Approach LOS		C			D			B			B	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	18.0	69.5		32.5	10.9	76.5		32.5				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5		6.0				
Max Green Setting (Gmax), s	30.5	25.5		45.0	9.5	46.5		45.0				
Max Q Clear Time (g_c+l1), s	10.7	8.0		20.2	4.1	11.8		24.0				
Green Ext Time (p_c), s	0.8	2.0		2.1	0.0	4.4		2.5				

Intersection Summary

HCM 6th Ctrl Delay	24.2
HCM 6th LOS	C

Timings
5: Marksheffel Rd & SH-94


2020 Adjusted Existing PM.syn
06/24/2020

	→	↘	↙	←	↖	↗	↑	↘	↙	↓	↖
Lane Group	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↗	↙	↑	↗	↙	↑↑	↗	↙	↑↑	↗
Traffic Volume (vph)	294	94	39	356	343	76	819	23	158	573	7
Future Volume (vph)	294	94	39	356	343	76	819	23	158	573	7
Turn Type	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	4			8		5	2		1	6	
Permitted Phases		4	8		8	2		2	6		6
Detector Phase	4	4	8	8	8	5	2	2	1	6	6
Switch Phase											
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	51.0	51.0	51.0	51.0	51.0	16.0	32.0	32.0	37.0	53.0	53.0
Total Split (%)	42.5%	42.5%	42.5%	42.5%	42.5%	13.3%	26.7%	26.7%	30.8%	44.2%	44.2%
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag						Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)	35.1	35.1	35.1	35.1	35.1	61.9	53.8	53.8	69.6	57.9	57.9
Actuated g/C Ratio	0.29	0.29	0.29	0.29	0.29	0.52	0.45	0.45	0.58	0.48	0.48
v/c Ratio	0.71	0.21	0.28	0.78	0.54	0.22	0.65	0.04	0.57	0.39	0.01
Control Delay	41.8	1.9	34.8	49.1	5.6	13.9	30.6	0.1	16.0	15.5	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	41.8	1.9	34.8	49.1	5.6	13.9	30.6	0.1	16.0	15.5	0.3
LOS	D	A	C	D	A	B	C	A	B	B	A
Approach Delay	32.1			28.1			28.4			15.5	
Approach LOS	C			C			C			B	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 28 (23%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 65
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.78
 Intersection Signal Delay: 25.6
 Intersection Capacity Utilization 75.1%
 Analysis Period (min) 15
 Intersection LOS: C
 ICU Level of Service D

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary

2020 Adjusted Existing PM.syn

5: Marksheffel Rd & SH-94

06/24/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	0	294	94	39	356	343	76	819	23	158	573	7
Future Volume (veh/h)	0	294	94	39	356	343	76	819	23	158	573	7
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	0	363	116	45	409	394	93	999	28	182	659	8
Peak Hour Factor	0.81	0.81	0.81	0.87	0.87	0.87	0.82	0.82	0.82	0.87	0.87	0.87
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	60	520	441	192	529	448	429	1656	738	333	1788	797
Arrive On Green	0.00	0.58	0.58	0.29	0.29	0.29	0.04	0.48	0.48	0.07	0.51	0.51
Sat Flow, veh/h	646	1781	1510	887	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	0	363	116	45	409	394	93	999	28	182	659	8
Grp Sat Flow(s),veh/h/ln	646	1781	1510	887	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	0.0	17.2	4.5	5.5	24.8	29.3	3.3	25.4	1.2	6.2	13.6	0.3
Cycle Q Clear(g_c), s	0.0	17.2	4.5	22.6	24.8	29.3	3.3	25.4	1.2	6.2	13.6	0.3
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	60	520	441	192	529	448	429	1656	738	333	1788	797
V/C Ratio(X)	0.00	0.70	0.26	0.23	0.77	0.88	0.22	0.60	0.04	0.55	0.37	0.01
Avail Cap(c_a), veh/h	113	668	566	266	679	576	493	1656	738	654	1788	797
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.00	0.99	0.99	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	0.0	21.2	18.6	45.8	38.8	40.4	15.1	23.0	16.7	17.6	17.9	14.6
Incr Delay (d2), s/veh	0.0	2.2	0.3	0.6	4.2	12.0	0.3	1.6	0.1	1.4	0.6	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	5.3	1.5	1.2	11.6	12.5	1.3	10.6	0.4	2.6	5.6	0.1
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	0.0	23.4	18.9	46.4	43.0	52.5	15.4	24.7	16.8	19.0	18.5	14.7
LnGrp LOS	A	C	B	D	D	D	B	C	B	B	B	B
Approach Vol, veh/h		479			848			1120			849	
Approach Delay, s/veh		22.3			47.6			23.7			18.6	
Approach LOS		C			D			C			B	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	15.2	63.8		41.1	11.6	67.4		41.1				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5		6.0				
Max Green Setting (Gmax), s	30.5	25.5		45.0	9.5	46.5		45.0				
Max Q Clear Time (g_c+I1), s	8.2	27.4		19.2	5.3	15.6		31.3				
Green Ext Time (p_c), s	0.5	0.0		2.7	0.1	5.1		3.7				

Intersection Summary

HCM 6th Ctrl Delay	28.3
HCM 6th LOS	C


Timings
5: Marksheffel Rd & SH-94

	→	↘	↙	←	↖	↗	↑	↘	↙	↓	↖
Lane Group	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↗	↙	↑	↗	↙	↑↑	↗	↙	↑↑	↗
Traffic Volume (vph)	275	60	30	315	85	60	290	20	275	535	5
Future Volume (vph)	275	60	30	315	85	60	290	20	275	535	5
Turn Type	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	4			8		5	2		1	6	
Permitted Phases		4	8		8	2		2	6		6
Detector Phase	4	4	8	8	8	5	2	2	1	6	6
Switch Phase											
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	54.0	54.0	54.0	54.0	54.0	16.0	30.0	30.0	36.0	50.0	50.0
Total Split (%)	45.0%	45.0%	45.0%	45.0%	45.0%	13.3%	25.0%	25.0%	30.0%	41.7%	41.7%
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag						Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)	30.8	30.8	30.8	30.8	30.8	62.2	54.6	54.6	76.6	65.1	65.1
Actuated g/C Ratio	0.26	0.26	0.26	0.26	0.26	0.52	0.46	0.46	0.64	0.54	0.54
v/c Ratio	0.75	0.15	0.26	0.79	0.20	0.16	0.23	0.03	0.47	0.32	0.01
Control Delay	47.5	0.6	37.7	53.5	1.8	12.1	23.0	0.1	8.0	7.1	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.5	0.6	37.7	53.5	1.8	12.1	23.0	0.1	8.0	7.1	0.0
LOS	D	A	D	D	A	B	C	A	A	A	A
Approach Delay	39.1			42.2			20.0			7.4	
Approach LOS	D			D			C			A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 28 (23%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.79
 Intersection Signal Delay: 23.1
 Intersection LOS: C
 Intersection Capacity Utilization 64.0%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94





Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	0	275	60	30	315	85	60	290	20	275	535	5
Future Volume (veh/h)	0	275	60	30	315	85	60	290	20	275	535	5
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	0	340	74	34	362	98	73	354	24	316	615	6
Peak Hour Factor	0.81	0.81	0.81	0.87	0.87	0.87	0.82	0.82	0.82	0.87	0.87	0.87
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	60	422	357	130	429	363	499	1730	772	688	1999	892
Arrive On Green	0.00	0.47	0.47	0.24	0.24	0.24	0.04	0.50	0.50	0.11	0.57	0.57
Sat Flow, veh/h	888	1781	1510	941	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	0	340	74	34	362	98	73	354	24	316	615	6
Grp Sat Flow(s),veh/h/ln	888	1781	1510	941	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	0.0	19.5	3.4	4.2	22.9	6.2	2.4	6.8	0.9	9.9	11.0	0.2
Cycle Q Clear(g_c), s	0.0	19.5	3.4	23.7	22.9	6.2	2.4	6.8	0.9	9.9	11.0	0.2
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	60	422	357	130	429	363	499	1730	772	688	1999	892
V/C Ratio(X)	0.00	0.81	0.21	0.26	0.84	0.27	0.15	0.20	0.03	0.46	0.31	0.01
Avail Cap(c_a), veh/h	205	713	604	284	724	614	570	1730	772	935	1999	892
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.00	0.98	0.98	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	0.0	29.3	25.0	53.4	43.7	37.3	13.5	16.8	15.3	10.9	13.6	11.3
Incr Delay (d2), s/veh	0.0	3.6	0.3	1.1	4.6	0.4	0.1	0.3	0.1	0.5	0.4	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	6.9	1.2	1.0	10.7	2.4	1.0	2.8	0.4	3.8	4.4	0.1
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	0.0	32.9	25.3	54.4	48.3	37.7	13.6	17.1	15.4	11.4	14.0	11.3
LnGrp LOS	A	C	C	D	D	D	B	B	B	B	B	B
Approach Vol, veh/h		414			494			451			937	
Approach Delay, s/veh		31.5			46.6			16.4			13.1	
Approach LOS		C			D			B			B	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	19.3	66.3		34.4	11.1	74.5		34.4				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5		6.0				
Max Green Setting (Gmax), s	29.5	23.5		48.0	9.5	43.5		48.0				
Max Q Clear Time (g_c+l1), s	11.9	8.8		21.5	4.4	13.0		25.7				
Green Ext Time (p_c), s	0.9	2.0		2.4	0.1	4.7		2.7				

Intersection Summary

HCM 6th Ctrl Delay	24.3
HCM 6th LOS	C


Timings
5: Marksheffel Rd & SH-94

	→	↘	↙	←	↖	↗	↑	↘	↙	↓	↖
Lane Group	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↗	↙	↑	↗	↙	↑↑	↗	↙	↑↑	↗
Traffic Volume (vph)	315	105	45	380	365	85	870	25	170	610	10
Future Volume (vph)	315	105	45	380	365	85	870	25	170	610	10
Turn Type	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	4			8		5	2		1	6	
Permitted Phases		4	8		8	2		2	6		6
Detector Phase	4	4	8	8	8	5	2	2	1	6	6
Switch Phase											
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	66.8	66.8	66.8	66.8	66.8	12.5	31.0	31.0	22.2	40.7	40.7
Total Split (%)	55.7%	55.7%	55.7%	55.7%	55.7%	10.4%	25.8%	25.8%	18.5%	33.9%	33.9%
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag						Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)	39.5	39.5	39.5	39.5	39.5	57.3	48.7	48.7	65.7	52.9	52.9
Actuated g/C Ratio	0.33	0.33	0.33	0.33	0.33	0.48	0.41	0.41	0.55	0.44	0.44
v/c Ratio	0.66	0.22	0.30	0.75	0.61	0.22	0.66	0.04	0.56	0.41	0.01
Control Delay	35.9	2.3	31.3	42.8	12.6	16.4	34.3	0.1	16.1	19.9	1.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	35.9	2.3	31.3	42.8	12.6	16.4	34.3	0.1	16.1	19.9	1.0
LOS	D	A	C	D	B	B	C	A	B	B	A
Approach Delay	27.5			28.2			31.9			18.8	
Approach LOS	C			C			C			B	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 28 (23%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 65
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.75
 Intersection Signal Delay: 27.0
 Intersection Capacity Utilization 78.5%
 Analysis Period (min) 15
 Intersection LOS: C
 ICU Level of Service D


Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary
 5: Marksheffel Rd & SH-94

2025 Background PM.syn

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	0	315	105	45	380	365	85	870	25	170	610	10
Future Volume (veh/h)	0	315	105	45	380	365	85	870	25	170	610	10
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1856	1856	1856	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	0	399	133	54	452	435	92	946	27	175	629	10
Peak Hour Factor	0.79	0.79	0.79	0.84	0.84	0.84	0.92	0.92	0.92	0.97	0.97	0.97
Percent Heavy Veh, %	3	3	3	3	3	3	2	2	2	4	4	4
Cap, veh/h	60	595	504	220	595	504	423	1597	712	328	1674	747
Arrive On Green	0.00	0.64	0.64	0.32	0.32	0.32	0.04	0.45	0.45	0.07	0.48	0.48
Sat Flow, veh/h	622	1856	1572	865	1856	1572	1781	3554	1585	1753	3497	1560
Grp Volume(v), veh/h	0	399	133	54	452	435	92	946	27	175	629	10
Grp Sat Flow(s),veh/h/ln	622	1856	1572	865	1856	1572	1781	1777	1585	1753	1749	1560
Q Serve(g_s), s	0.0	16.3	4.4	6.5	26.3	31.2	3.3	24.0	1.1	6.4	13.7	0.4
Cycle Q Clear(g_c), s	0.0	16.3	4.4	22.8	26.3	31.2	3.3	24.0	1.1	6.4	13.7	0.4
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	60	595	504	220	595	504	423	1597	712	328	1674	747
V/C Ratio(X)	0.00	0.67	0.26	0.25	0.76	0.86	0.22	0.59	0.04	0.53	0.38	0.01
Avail Cap(c_a), veh/h	176	940	797	381	940	797	437	1597	712	431	1674	747
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.00	0.99	0.99	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	0.0	17.6	15.4	42.5	36.6	38.3	16.8	24.8	18.5	18.7	19.9	16.4
Incr Delay (d2), s/veh	0.0	1.3	0.3	0.6	2.0	5.9	0.3	1.6	0.1	1.4	0.6	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	4.9	1.5	1.4	12.2	12.7	1.4	10.3	0.4	2.7	5.7	0.2
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	0.0	18.9	15.7	43.1	38.7	44.2	17.1	26.4	18.6	20.1	20.5	16.4
LnGrp LOS	A	B	B	D	D	D	B	C	B	C	C	B
Approach Vol, veh/h		532			941			1065			814	
Approach Delay, s/veh		18.1			41.5			25.4			20.4	
Approach LOS		B			D			C			C	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	15.1	60.4		44.5	11.6	64.0		44.5				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5		6.0				
Max Green Setting (Gmax), s	15.7	24.5		60.8	6.0	34.2		60.8				
Max Q Clear Time (g_c+I1), s	8.4	26.0		18.3	5.3	15.7		33.2				
Green Ext Time (p_c), s	0.3	0.0		3.2	0.0	4.2		5.3				

Intersection Summary

HCM 6th Ctrl Delay	27.5
HCM 6th LOS	C

Timings
5: Marksheffel Rd & SH-94


2025 Total AM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	165	330	90	30	370	140	90	320	20	325	560	325
Future Volume (vph)	165	330	90	30	370	140	90	320	20	325	560	325
Turn Type	Perm	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free
Protected Phases		4			8		5	2		1	6	
Permitted Phases	4		4	8		8	2		2	6		Free
Detector Phase	4	4	4	8	8	8	5	2	2	1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	58.0	58.0	58.0	58.0	58.0	58.0	16.0	27.0	27.0	35.0	46.0	
Total Split (%)	48.3%	48.3%	48.3%	48.3%	48.3%	48.3%	13.3%	22.5%	22.5%	29.2%	38.3%	
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag							Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	
Recall Mode	None	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	
Act Effct Green (s)	38.5	38.5	38.5	38.5	38.5	38.5	51.8	43.5	43.5	68.7	54.2	120.0
Actuated g/C Ratio	0.32	0.32	0.32	0.32	0.32	0.32	0.43	0.36	0.36	0.57	0.45	1.00
v/c Ratio	1.10	0.64	0.17	0.17	0.70	0.26	0.25	0.28	0.03	0.57	0.38	0.23
Control Delay	133.0	35.1	0.6	26.9	41.3	4.5	18.0	32.5	0.1	14.1	16.8	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	133.0	35.1	0.6	26.9	41.3	4.5	18.0	32.5	0.1	14.1	16.8	0.3
LOS	F	D	A	C	D	A	B	C	A	B	B	A
Approach Delay		57.3			30.9			27.9				11.6
Approach LOS		E			C			C				B

Intersection Summary


Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 28 (23%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.10
 Intersection Signal Delay: 27.6
 Intersection LOS: C
 Intersection Capacity Utilization 76.3%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary
 5: Marksheffel Rd & SH-94

2025 Total AM.syn
 09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	165	330	90	30	370	140	90	320	20	325	560	325
Future Volume (veh/h)	165	330	90	30	370	140	90	320	20	325	560	325
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	179	359	33	33	402	70	98	348	22	353	609	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	256	704	597	372	716	607	364	1002	447	549	1383	
Arrive On Green	0.79	0.79	0.79	0.40	0.40	0.40	0.05	0.29	0.29	0.16	0.39	0.00
Sat Flow, veh/h	878	1781	1510	961	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	179	359	33	33	402	70	98	348	22	353	609	0
Grp Sat Flow(s),veh/h/ln	878	1781	1510	961	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	22.9	8.5	0.6	2.9	20.7	3.5	4.7	9.5	1.2	16.1	15.2	0.0
Cycle Q Clear(g_c), s	43.6	8.5	0.6	11.4	20.7	3.5	4.7	9.5	1.2	16.1	15.2	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	256	704	597	372	716	607	364	1002	447	549	1383	
V/C Ratio(X)	0.70	0.51	0.06	0.09	0.56	0.12	0.27	0.35	0.05	0.64	0.44	
Avail Cap(c_a), veh/h	289	772	654	408	785	665	408	1002	447	690	1383	
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	0.92	0.92	0.92	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	21.9	8.5	7.7	28.3	28.2	23.0	27.5	33.7	30.8	22.5	26.8	0.0
Incr Delay (d2), s/veh	5.9	0.5	0.0	0.1	0.8	0.1	0.4	1.0	0.2	1.4	1.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	4.3	2.4	0.2	0.7	9.1	1.3	2.0	4.2	0.5	6.8	6.6	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	27.7	9.0	7.7	28.4	29.0	23.1	27.9	34.7	31.0	23.8	27.8	0.0
LnGrp LOS	C	A	A	C	C	C	C	C	C	C	C	C
Approach Vol, veh/h		571			505			468			962	A
Approach Delay, s/veh		14.8			28.1			33.1			26.4	
Approach LOS		B			C			C			C	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	25.4	41.2		53.4	13.0	53.6		53.4				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5		6.0				
Max Green Setting (Gmax), s	28.5	20.5		52.0	9.5	39.5		52.0				
Max Q Clear Time (g_c+l1), s	18.1	11.5		45.6	6.7	17.2		22.7				
Green Ext Time (p_c), s	0.8	1.5		1.8	0.0	4.3		3.1				

Intersection Summary


HCM 6th Ctrl Delay	25.3
HCM 6th LOS	C

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
5: Marksheffel Rd & SH-94


2025 Total PM.syn
09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	250	365	130	45	435	450	115	915	25	225	640	355
Future Volume (vph)	250	365	130	45	435	450	115	915	25	225	640	355
Turn Type	Perm	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free
Protected Phases		4			8		5	2		1	6	
Permitted Phases	4		4	8		8	2		2	6		Free
Detector Phase	4	4	4	8	8	8	5	2	2	1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	59.0	59.0	59.0	59.0	59.0	59.0	16.0	45.0	45.0	16.0	45.0	120.0
Total Split (%)	49.2%	49.2%	49.2%	49.2%	49.2%	49.2%	13.3%	37.5%	37.5%	13.3%	37.5%	100%
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag							Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	
Act Effct Green (s)	53.0	53.0	53.0	53.0	53.0	53.0	47.5	38.5	38.5	48.5	39.0	120.0
Actuated g/C Ratio	0.44	0.44	0.44	0.44	0.44	0.44	0.40	0.32	0.32	0.40	0.32	1.00
v/c Ratio	1.03	0.49	0.18	0.15	0.58	0.60	0.43	0.88	0.05	1.17	0.58	0.24
Control Delay	93.3	22.6	2.1	21.7	28.7	16.1	24.2	48.5	0.2	141.4	33.0	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	93.3	22.6	2.1	21.7	28.7	16.1	24.2	48.5	0.2	141.4	33.0	0.4
LOS	F	C	A	C	C	B	C	D	A	F	C	A
Approach Delay		42.8			22.3			44.8				43.5
Approach LOS		D			C			D				D

Intersection Summary
 Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 28 (23%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.17
 Intersection Signal Delay: 38.6 Intersection LOS: D
 Intersection Capacity Utilization 95.3% ICU Level of Service F
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



5: Marksheffel Rd & SH-94



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	250	365	130	45	435	450	115	915	25	225	640	355
Future Volume (veh/h)	250	365	130	45	435	450	115	915	25	225	640	355
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1856	1856	1856	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	272	397	32	49	473	239	125	995	27	232	660	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97
Percent Heavy Veh, %	3	3	3	3	3	3	2	2	2	4	4	4
Cap, veh/h	243	820	695	397	820	695	313	1140	509	230	1180	
Arrive On Green	0.74	0.74	0.74	0.44	0.44	0.44	0.06	0.32	0.32	0.08	0.34	0.00
Sat Flow, veh/h	732	1856	1572	951	1856	1572	1781	3554	1585	1753	3497	1560
Grp Volume(v), veh/h	272	397	32	49	473	239	125	995	27	232	660	0
Grp Sat Flow(s),veh/h/ln	732	1856	1572	951	1856	1572	1781	1777	1585	1753	1749	1560
Q Serve(g_s), s	30.1	10.5	0.7	4.2	22.9	12.0	5.6	31.7	1.4	9.5	18.5	0.0
Cycle Q Clear(g_c), s	53.0	10.5	0.7	14.7	22.9	12.0	5.6	31.7	1.4	9.5	18.5	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	243	820	695	397	820	695	313	1140	509	230	1180	
V/C Ratio(X)	1.12	0.48	0.05	0.12	0.58	0.34	0.40	0.87	0.05	1.01	0.56	
Avail Cap(c_a), veh/h	243	820	695	397	820	695	343	1140	509	230	1180	
HCM Platoon Ratio	1.67	1.67	1.67	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.93	0.93	0.93	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.00
Uniform Delay (d), s/veh	30.9	10.2	8.9	26.4	25.1	22.1	25.9	38.4	28.2	33.4	32.5	0.0
Incr Delay (d2), s/veh	90.8	0.4	0.0	0.1	1.0	0.3	0.8	9.3	0.2	62.1	1.9	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	13.1	3.4	0.2	1.0	10.2	4.5	2.4	15.1	0.6	8.5	8.1	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	121.7	10.6	8.9	26.5	26.1	22.3	26.7	47.7	28.4	95.5	34.4	0.0
LnGrp LOS	F	B	A	C	C	C	C	D	C	F	C	
Approach Vol, veh/h		701			761			1147			892	A
Approach Delay, s/veh		53.6			25.0			45.0			50.3	
Approach LOS		D			C			D			D	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	16.0	45.0		59.0	14.0	47.0		59.0				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5		6.0				
Max Green Setting (Gmax), s	9.5	38.5		53.0	9.5	38.5		53.0				
Max Q Clear Time (g_c+l1), s	11.5	33.7		55.0	7.6	20.5		24.9				
Green Ext Time (p_c), s	0.0	2.8		0.0	0.1	4.3		4.4				

Intersection Summary

HCM 6th Ctrl Delay	43.7
HCM 6th LOS	D

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.


Timings
5: Marksheffel Rd & SH-94

	→	↘	↙	←	↖	↗	↑	↘	↙	↓	↖	Ø7
Lane Group	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	Ø7
Lane Configurations	↑	↗	↙	↑	↗	↙	↑↑	↗	↙	↑↑	↗	
Traffic Volume (vph)	325	70	40	375	100	70	345	25	325	635	5	
Future Volume (vph)	325	70	40	375	100	70	345	25	325	635	5	
Turn Type	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free	
Protected Phases	4			8		5	2		1	6		7
Permitted Phases		4	8		8	2		2	6		Free	
Detector Phase	4	4	8	8	8	5	2	2	1	6		
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5	9.5
Total Split (s)	61.9	61.9	51.9	51.9	51.9	13.1	23.1	23.1	35.0	45.0	10.0	
Total Split (%)	51.6%	51.6%	43.3%	43.3%	43.3%	10.9%	19.3%	19.3%	29.2%	37.5%	8%	
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5	
Lead/Lag			Lag	Lag	Lag	Lead	Lag	Lag	Lead	Lag		Lead
Lead-Lag Optimize?			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes		Yes
Recall Mode	None	None	None	None	None	None	C-Max	C-Max	None	C-Max		None
Act Effct Green (s)	33.8	33.8	33.8	33.8	33.8	55.1	47.3	47.3	73.7	61.8	120.0	
Actuated g/C Ratio	0.28	0.28	0.28	0.28	0.28	0.46	0.39	0.39	0.61	0.52	1.00	
v/c Ratio	0.71	0.14	0.28	0.81	0.19	0.20	0.28	0.04	0.54	0.38	0.00	
Control Delay	46.2	0.6	35.6	52.2	0.8	14.7	28.7	0.1	32.2	38.4	0.0	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	46.2	0.6	35.6	52.2	0.8	14.7	28.7	0.1	32.2	38.4	0.0	
LOS	D	A	D	D	A	B	C	A	C	D	A	
Approach Delay	38.1			40.9			24.8			36.1		
Approach LOS	D			D			C			D		

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.81
 Intersection Signal Delay: 35.4
 Intersection LOS: D
 Intersection Capacity Utilization 71.0%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94





Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	0	325	70	40	375	100	70	345	25	325	635	5
Future Volume (veh/h)	0	325	70	40	375	100	70	345	25	325	635	5
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	0	353	11	43	408	27	76	375	27	353	690	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	1	468	397	139	476	403	451	1532	683	667	1906	
Arrive On Green	0.00	0.26	0.26	0.26	0.26	0.26	0.04	0.44	0.44	0.27	1.00	0.00
Sat Flow, veh/h	1697	1781	1510	986	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	0	353	11	43	408	27	76	375	27	353	690	0
Grp Sat Flow(s),veh/h/ln	1697	1781	1510	986	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	0.0	21.9	0.6	5.0	25.7	1.6	2.9	8.1	1.2	13.6	0.0	0.0
Cycle Q Clear(g_c), s	0.0	21.9	0.6	26.9	25.7	1.6	2.9	8.1	1.2	13.6	0.0	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	1	468	397	139	476	403	451	1532	683	667	1906	
V/C Ratio(X)	0.00	0.75	0.03	0.31	0.86	0.07	0.17	0.24	0.04	0.53	0.36	
Avail Cap(c_a), veh/h	78	830	703	257	693	587	480	1532	683	844	1906	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00	2.00	2.00
Upstream Filter(I)	0.00	0.96	0.96	1.00	1.00	1.00	1.00	1.00	1.00	0.98	0.98	0.00
Uniform Delay (d), s/veh	0.0	40.7	32.9	53.0	42.1	33.2	17.0	21.0	19.0	11.1	0.0	0.0
Incr Delay (d2), s/veh	0.0	2.4	0.0	1.2	7.3	0.1	0.2	0.4	0.1	0.6	0.5	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	9.9	0.2	1.3	12.4	0.6	1.2	3.4	0.5	3.9	0.1	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	0.0	43.1	32.9	54.3	49.4	33.3	17.1	21.3	19.1	11.7	0.5	0.0
LnGrp LOS	A	D	C	D	D	C	B	C	B	B	A	
Approach Vol, veh/h		364			478			478			1043	A
Approach Delay, s/veh		42.8			48.9			20.6			4.3	
Approach LOS		D			D			C			A	
Timer - Assigned Phs	1	2		4	5	6	7	8				
Phs Duration (G+Y+Rc), s	23.0	59.5		37.5	11.1	71.4	0.0	37.5				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5	4.5	6.0				
Max Green Setting (Gmax), s	28.5	16.6		55.9	6.6	38.5	5.5	45.9				
Max Q Clear Time (g_c+I1), s	15.6	10.1		23.9	4.9	2.0	0.0	28.9				
Green Ext Time (p_c), s	0.9	1.3		2.4	0.0	5.5	0.0	2.6				

Intersection Summary

HCM 6th Ctrl Delay	22.5
HCM 6th LOS	C

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.




Lane Group	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR	Ø7
Lane Configurations	↑	↗	↖	↑	↗	↖	↑↑	↗	↖	↑↑	↗	
Traffic Volume (vph)	375	120	50	450	435	100	1035	30	200	725	10	
Future Volume (vph)	375	120	50	450	435	100	1035	30	200	725	10	
Turn Type	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free	
Protected Phases	4			8		5	2		1	6		7
Permitted Phases		4	8		8	2		2	6		Free	
Detector Phase	4	4	8	8	8	5	2	2	1	6		
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5	9.5
Total Split (s)	57.0	57.0	47.0	47.0	47.0	14.0	44.0	44.0	19.0	49.0	10.0	
Total Split (%)	47.5%	47.5%	39.2%	39.2%	39.2%	11.7%	36.7%	36.7%	15.8%	40.8%	8%	
Yellow Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5	
Lead/Lag			Lag	Lag	Lag	Lead	Lag	Lag	Lead	Lag		Lead
Lead-Lag Optimize?			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes		Yes
Recall Mode	None	None	None	None	None	None	C-Max	C-Max	None	C-Max		None
Act Effct Green (s)	40.0	40.0	40.0	40.0	40.0	54.6	46.5	46.5	66.6	52.8	120.0	
Actuated g/C Ratio	0.33	0.33	0.33	0.33	0.33	0.46	0.39	0.39	0.56	0.44	1.00	
v/c Ratio	0.66	0.21	0.30	0.80	0.66	0.31	0.82	0.05	0.75	0.49	0.01	
Control Delay	37.2	3.6	31.5	45.6	16.5	17.6	40.9	0.1	55.5	18.2	0.0	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	37.2	3.6	31.5	45.6	16.5	17.6	40.9	0.1	55.5	18.2	0.0	
LOS	D	A	C	D	B	B	D	A	E	B	A	
Approach Delay	29.1			31.3			37.8			26.0		
Approach LOS	C			C			D			C		

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.82
 Intersection Signal Delay: 31.8
 Intersection LOS: C
 Intersection Capacity Utilization 87.1%
 ICU Level of Service E
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary
5: Marksheffel Rd & SH-94

2040 Background PM.syn
08/03/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	0	375	120	50	450	435	100	1035	30	200	725	10
Future Volume (veh/h)	0	375	120	50	450	435	100	1035	30	200	725	10
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1856	1856	1856	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	0	408	21	54	489	223	109	1125	33	206	747	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97
Percent Heavy Veh, %	3	3	3	3	3	3	2	2	2	4	4	4
Cap, veh/h	1	544	461	184	544	461	384	1675	747	304	1754	
Arrive On Green	0.00	0.59	0.59	0.29	0.29	0.29	0.05	0.47	0.47	0.05	0.34	0.00
Sat Flow, veh/h	1767	1856	1572	951	1856	1572	1781	3554	1585	1753	3497	1560
Grp Volume(v), veh/h	0	408	21	54	489	223	109	1125	33	206	747	0
Grp Sat Flow(s),veh/h/ln	1767	1856	1572	951	1856	1572	1781	1777	1585	1753	1749	1560
Q Serve(g_s), s	0.0	19.5	0.7	6.3	30.4	14.0	3.8	29.4	1.3	7.1	19.9	0.0
Cycle Q Clear(g_c), s	0.0	19.5	0.7	25.8	30.4	14.0	3.8	29.4	1.3	7.1	19.9	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	1	544	461	184	544	461	384	1675	747	304	1754	
V/C Ratio(X)	0.00	0.75	0.05	0.29	0.90	0.48	0.28	0.67	0.04	0.68	0.43	
Avail Cap(c_a), veh/h	81	789	668	230	634	537	411	1675	747	351	1754	
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	0.67	0.67	0.67
Upstream Filter(l)	0.00	0.98	0.98	1.00	1.00	1.00	1.00	1.00	1.00	0.96	0.96	0.00
Uniform Delay (d), s/veh	0.0	21.6	17.7	48.1	40.7	34.9	16.1	24.5	17.1	20.9	26.5	0.0
Incr Delay (d2), s/veh	0.0	2.3	0.0	0.9	14.4	0.8	0.4	2.2	0.1	4.1	0.7	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	6.2	0.3	1.5	15.9	5.5	1.6	12.6	0.5	3.3	9.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	0.0	23.9	17.7	49.0	55.1	35.7	16.5	26.7	17.2	25.0	27.2	0.0
LnGrp LOS	A	C	B	D	E	D	B	C	B	C	C	
Approach Vol, veh/h		429			766			1267			953	A
Approach Delay, s/veh		23.6			49.0			25.6			26.7	
Approach LOS		C			D			C			C	
Timer - Assigned Phs	1	2		4	5	6	7	8				
Phs Duration (G+Y+Rc), s	15.8	63.1		41.2	12.2	66.7	0.0	41.2				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5	4.5	6.0				
Max Green Setting (Gmax), s	12.5	37.5		51.0	7.5	42.5	5.5	41.0				
Max Q Clear Time (g_c+I1), s	9.1	31.4		21.5	5.8	21.9	0.0	32.4				
Green Ext Time (p_c), s	0.2	3.8		2.8	0.0	5.3	0.0	2.8				

Intersection Summary


HCM 6th Ctrl Delay	30.9
HCM 6th LOS	C

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.

Timings

5: Marksheffel Rd & SH-94




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗↘	↘	↖	↗↘	↘
Traffic Volume (vph)	165	380	100	40	430	155	100	375	25	375	660	325
Future Volume (vph)	165	380	100	40	430	155	100	375	25	375	660	325
Turn Type	Prot	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free
Protected Phases	7	4			8		5	2		1	6	
Permitted Phases			4	8		8	2		2	6		Free
Detector Phase	7	4	4	8	8	8	5	2	2	1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	9.5	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	29.0	72.0	72.0	43.0	43.0	43.0	13.5	17.0	17.0	31.0	34.5	
Total Split (%)	24.2%	60.0%	60.0%	35.8%	35.8%	35.8%	11.3%	14.2%	14.2%	25.8%	28.8%	
Yellow Time (s)	3.5	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead			Lag	Lag	Lag	Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?	Yes			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	
Act Effct Green (s)	18.0	58.1	58.1	35.6	35.6	35.6	24.9	16.7	16.7	49.4	34.7	120.0
Actuated g/C Ratio	0.15	0.48	0.48	0.30	0.30	0.30	0.21	0.14	0.14	0.41	0.29	1.00
v/c Ratio	0.71	0.49	0.14	0.16	0.88	0.29	0.51	0.86	0.07	0.90	0.71	0.23
Control Delay	63.7	22.0	1.1	31.3	58.6	4.1	38.7	69.8	0.4	64.1	53.2	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	63.7	22.0	1.1	31.3	58.6	4.1	38.7	69.8	0.4	64.1	53.2	0.3
LOS	E	C	A	C	E	A	D	E	A	E	D	A
Approach Delay		29.4			43.4			60.1			43.6	
Approach LOS		C			D			E			D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.90
 Intersection Signal Delay: 43.3
 Intersection LOS: D
 Intersection Capacity Utilization 82.5%
 ICU Level of Service E
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary

2040 Total AM.syn

09/09/2020

5: Marksheffel Rd & SH-94



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	165	380	100	40	430	155	100	375	25	375	660	325
Future Volume (veh/h)	165	380	100	40	430	155	100	375	25	375	660	325
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	179	413	44	43	467	86	109	408	27	408	717	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	208	784	664	305	507	430	306	701	313	503	1210	
Arrive On Green	0.12	0.44	0.44	0.28	0.28	0.28	0.06	0.20	0.20	0.33	0.57	0.00
Sat Flow, veh/h	1697	1781	1510	905	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	179	413	44	43	467	86	109	408	27	408	717	0
Grp Sat Flow(s),veh/h/ln	1697	1781	1510	905	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	12.4	20.3	2.0	4.4	30.0	5.1	5.9	12.8	1.7	21.8	15.8	0.0
Cycle Q Clear(g_c), s	12.4	20.3	2.0	5.4	30.0	5.1	5.9	12.8	1.7	21.8	15.8	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	208	784	664	305	507	430	306	701	313	503	1210	
V/C Ratio(X)	0.86	0.53	0.07	0.14	0.92	0.20	0.36	0.58	0.09	0.81	0.59	
Avail Cap(c_a), veh/h	346	980	830	331	558	473	306	701	313	511	1210	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.67	1.67	1.67
Upstream Filter(I)	0.89	0.89	0.89	1.00	1.00	1.00	1.00	1.00	1.00	0.86	0.86	0.00
Uniform Delay (d), s/veh	51.6	24.5	19.4	33.5	41.9	33.0	35.0	43.3	38.9	23.4	20.2	0.0
Incr Delay (d2), s/veh	9.9	0.5	0.0	0.2	19.8	0.2	0.7	3.5	0.5	8.2	1.8	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.8	8.6	0.7	1.0	16.1	2.0	2.6	5.8	0.7	8.6	5.4	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	61.6	25.0	19.4	33.7	61.7	33.2	35.7	46.8	39.4	31.6	22.0	0.0
LnGrp LOS	E	C	B	C	E	C	D	D	D	C	C	
Approach Vol, veh/h		636			596			544			1125	A
Approach Delay, s/veh		34.9			55.6			44.2			25.5	
Approach LOS		C			E			D			C	
Timer - Assigned Phs	1	2		4	5	6	7	8				
Phs Duration (G+Y+Rc), s	30.5	30.7		58.8	13.5	47.7	19.2	39.6				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5	4.5	6.0				
Max Green Setting (Gmax), s	24.5	10.5		66.0	7.0	28.0	24.5	37.0				
Max Q Clear Time (g_c+I1), s	23.8	14.8		22.3	7.9	17.8	14.4	32.0				
Green Ext Time (p_c), s	0.1	0.0		3.0	0.0	3.5	0.3	1.6				

Intersection Summary

HCM 6th Ctrl Delay	37.2
HCM 6th LOS	D

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.

Timings
5: Marksheffel Rd & SH-94


2040 Total PM.syn
09/09/2020

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	250	425	145	50	505	520	130	1080	30	255	755	355
Future Volume (vph)	250	425	145	50	505	520	130	1080	30	255	755	355
Turn Type	Prot	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free
Protected Phases	7	4			8		5	2		1	6	
Permitted Phases			4	8		8	2		2	6		Free
Detector Phase	7	4	4	8	8	8	5	2	2	1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	9.5	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	19.0	57.0	57.0	38.0	38.0	38.0	12.0	47.0	47.0	16.0	51.0	
Total Split (%)	15.8%	47.5%	47.5%	31.7%	31.7%	31.7%	10.0%	39.2%	39.2%	13.3%	42.5%	
Yellow Time (s)	3.5	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead			Lag	Lag	Lag	Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?	Yes			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	
Act Effect Green (s)	14.5	51.0	51.0	32.0	32.0	32.0	46.0	40.5	40.5	54.0	44.5	120.0
Actuated g/C Ratio	0.12	0.42	0.42	0.27	0.27	0.27	0.38	0.34	0.34	0.45	0.37	1.00
v/c Ratio	1.29	0.59	0.21	0.22	1.12	1.10	0.59	0.98	0.05	1.33	0.60	0.24
Control Delay	204.5	27.2	3.9	37.3	117.3	101.7	31.9	62.0	0.2	209.8	32.1	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	204.5	27.2	3.9	37.3	117.3	101.7	31.9	62.0	0.2	209.8	32.1	0.3
LOS	F	C	A	D	F	F	C	E	A	F	C	A
Approach Delay		77.1			106.1			57.4			57.1	
Approach LOS		E			F			E			E	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 130
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.33
 Intersection Signal Delay: 72.8 Intersection LOS: E
 Intersection Capacity Utilization 104.0% ICU Level of Service G
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary

2040 Total PM.syn

5: Marksheffel Rd & SH-94

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖	↗	↘	↖	↗	↘	↖	↗	↘	↖	↗	↘
Traffic Volume (veh/h)	250	425	145	50	505	520	130	1080	30	255	755	355
Future Volume (veh/h)	250	425	145	50	505	520	130	1080	30	255	755	355
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1856	1856	1856	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	272	462	49	54	549	315	141	1174	33	263	778	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97
Percent Heavy Veh, %	3	3	3	3	3	3	2	2	2	4	4	4
Cap, veh/h	214	789	668	295	495	419	327	1199	535	204	1297	
Arrive On Green	0.24	0.85	0.85	0.27	0.27	0.27	0.05	0.34	0.34	0.16	0.74	0.00
Sat Flow, veh/h	1767	1856	1572	882	1856	1572	1781	3554	1585	1753	3497	1560
Grp Volume(v), veh/h	272	462	49	54	549	315	141	1174	33	263	778	0
Grp Sat Flow(s),veh/h/ln	1767	1856	1572	882	1856	1572	1781	1777	1585	1753	1749	1560
Q Serve(g_s), s	14.5	8.9	0.6	5.7	32.0	22.0	5.5	39.2	1.7	9.5	12.4	0.0
Cycle Q Clear(g_c), s	14.5	8.9	0.6	5.7	32.0	22.0	5.5	39.2	1.7	9.5	12.4	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	214	789	668	295	495	419	327	1199	535	204	1297	
V/C Ratio(X)	1.27	0.59	0.07	0.18	1.11	0.75	0.43	0.98	0.06	1.29	0.60	
Avail Cap(c_a), veh/h	214	789	668	295	495	419	327	1199	535	204	1297	
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00	2.00	2.00
Upstream Filter(l)	0.91	0.91	0.91	1.00	1.00	1.00	1.00	1.00	1.00	0.80	0.80	0.00
Uniform Delay (d), s/veh	45.5	5.8	5.2	34.4	44.0	40.3	26.1	39.3	26.9	27.9	11.4	0.0
Incr Delay (d2), s/veh	152.1	1.0	0.0	0.3	73.9	7.4	0.9	21.4	0.2	157.3	1.6	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	14.5	2.3	0.2	1.3	24.7	9.4	2.8	20.4	0.7	12.3	3.5	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	197.6	6.9	5.3	34.7	117.9	47.8	27.0	60.7	27.1	185.2	13.0	0.0
LnGrp LOS	F	A	A	C	F	D	C	E	C	F	B	
Approach Vol, veh/h		783			918			1348			1041	A
Approach Delay, s/veh		73.0			88.9			56.4			56.5	
Approach LOS		E			F			E			E	
Timer - Assigned Phs	1	2		4	5	6	7	8				
Phs Duration (G+Y+Rc), s	16.0	47.0		57.0	12.0	51.0	19.0	38.0				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5	4.5	6.0				
Max Green Setting (Gmax), s	9.5	40.5		51.0	5.5	44.5	14.5	32.0				
Max Q Clear Time (g_c+l1), s	11.5	41.2		10.9	7.5	14.4	16.5	34.0				
Green Ext Time (p_c), s	0.0	0.0		3.5	0.0	6.2	0.0	0.0				

Intersection Summary

HCM 6th Ctrl Delay	66.9
HCM 6th LOS	E


Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.

Timings

5: Marksheffel Rd & SH-94

09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (vph)	165	380	100	40	430	155	100	375	25	375	660	325
Future Volume (vph)	165	380	100	40	430	155	100	375	25	375	660	325
Turn Type	Prot	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	7	4			8		5	2		1	6	
Permitted Phases			4	8		8	2		2	6		6
Detector Phase	7	4	4	8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	9.5	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	16.0	62.0	62.0	46.0	46.0	46.0	16.0	25.0	25.0	33.0	42.0	42.0
Total Split (%)	13.3%	51.7%	51.7%	38.3%	38.3%	38.3%	13.3%	20.8%	20.8%	27.5%	35.0%	35.0%
Yellow Time (s)	3.5	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead			Lag	Lag	Lag	Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?	Yes			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)	10.7	50.9	50.9	35.7	35.7	35.7	34.9	26.1	26.1	56.6	41.3	41.3
Actuated g/C Ratio	0.09	0.42	0.42	0.30	0.30	0.30	0.29	0.22	0.22	0.47	0.34	0.34
v/c Ratio	0.62	0.55	0.15	0.16	0.88	0.29	0.40	0.55	0.06	0.81	0.60	0.46
Control Delay	62.4	28.4	1.5	30.6	57.8	3.9	26.8	47.4	0.2	43.6	33.5	5.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	62.4	28.4	1.5	30.6	57.8	3.9	26.8	47.4	0.2	43.6	33.5	5.2
LOS	E	C	A	C	E	A	C	D	A	D	C	A
Approach Delay		32.9			42.7			40.9			29.5	
Approach LOS		C			D			D			C	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.88
 Intersection Signal Delay: 34.7
 Intersection LOS: C
 Intersection Capacity Utilization 78.1%
 ICU Level of Service D
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary

2040 Total AM Improved.syn

5: Marksheffel Rd & SH-94

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	165	380	100	40	430	155	100	375	25	375	660	325
Future Volume (veh/h)	165	380	100	40	430	155	100	375	25	375	660	325
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1781	1781	1781	1811	1811	1811	1826	1826	1826	1856	1856	1856
Adj Flow Rate, veh/h	179	413	44	43	467	86	109	408	27	408	717	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	8	8	8	6	6	6	5	5	5	3	3	3
Cap, veh/h	234	700	593	250	514	436	351	897	400	548	1368	
Arrive On Green	0.07	0.39	0.39	0.28	0.28	0.28	0.06	0.26	0.26	0.32	0.65	0.00
Sat Flow, veh/h	3291	1781	1510	905	1811	1535	1739	3469	1547	1767	3526	1572
Grp Volume(v), veh/h	179	413	44	43	467	86	109	408	27	408	717	0
Grp Sat Flow(s),veh/h/ln	1646	1781	1510	905	1811	1535	1739	1735	1547	1767	1763	1572
Q Serve(g_s), s	6.4	22.0	2.2	4.7	29.9	5.1	5.5	11.9	1.6	20.3	13.0	0.0
Cycle Q Clear(g_c), s	6.4	22.0	2.2	13.7	29.9	5.1	5.5	11.9	1.6	20.3	13.0	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	234	700	593	250	514	436	351	897	400	548	1368	
V/C Ratio(X)	0.76	0.59	0.07	0.17	0.91	0.20	0.31	0.46	0.07	0.75	0.52	
Avail Cap(c_a), veh/h	315	831	705	294	604	512	383	897	400	601	1368	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.67	1.67	1.67
Upstream Filter(I)	0.89	0.89	0.89	1.00	1.00	1.00	1.00	1.00	1.00	0.87	0.87	0.00
Uniform Delay (d), s/veh	54.7	28.8	22.8	39.4	41.4	32.6	29.7	37.4	33.6	20.1	15.2	0.0
Incr Delay (d2), s/veh	6.7	0.7	0.0	0.3	16.0	0.2	0.5	1.7	0.3	4.0	1.3	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	2.9	9.5	0.8	1.1	15.5	1.9	2.3	5.3	0.6	7.3	4.3	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	61.4	29.5	22.8	39.7	57.5	32.8	30.2	39.1	33.9	24.1	16.5	0.0
LnGrp LOS	E	C	C	D	E	C	C	D	C	C	B	
Approach Vol, veh/h		636			596			544			1125	A
Approach Delay, s/veh		38.0			52.6			37.0			19.2	
Approach LOS		D			D			D			B	
Timer - Assigned Phs	1	2		4	5	6	7	8				
Phs Duration (G+Y+Rc), s	29.4	37.5		53.1	13.8	53.1	13.0	40.1				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5	4.5	6.0				
Max Green Setting (Gmax), s	26.5	18.5		56.0	9.5	35.5	11.5	40.0				
Max Q Clear Time (g_c+I1), s	22.3	13.9		24.0	7.5	15.0	8.4	31.9				
Green Ext Time (p_c), s	0.6	1.1		3.0	0.0	5.0	0.2	2.2				

Intersection Summary

HCM 6th Ctrl Delay	33.5
HCM 6th LOS	C

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.

Timings


5: Marksheffel Rd & SH-94

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	250	425	145	50	505	520	130	1080	30	255	755	355
Future Volume (vph)	250	425	145	50	505	520	130	1080	30	255	755	355
Turn Type	Prot	NA	Perm	Perm	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free
Protected Phases	7	4			8		5	2		1	6	
Permitted Phases			4	8		8	2		2	6		Free
Detector Phase	7	4	4	8	8	8	5	2	2	1	6	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	9.5	11.0	11.0	11.0	11.0	11.0	11.5	11.5	11.5	11.5	11.5	11.5
Total Split (s)	14.2	53.2	53.2	39.0	39.0	39.0	18.1	49.8	49.8	17.0	48.7	
Total Split (%)	11.8%	44.3%	44.3%	32.5%	32.5%	32.5%	15.1%	41.5%	41.5%	14.2%	40.6%	
Yellow Time (s)	3.5	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.5	1.5	1.5	1.5	1.5	1.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	6.0	6.0	6.0	6.0	6.0	6.5	6.5	6.5	6.5	6.5	6.5
Lead/Lag	Lead			Lag	Lag	Lag	Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?	Yes			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	None	C-Max	C-Max	None	C-Max	
Act Effct Green (s)	9.7	47.2	47.2	33.0	33.0	33.0	53.4	43.3	43.3	54.2	43.7	120.0
Actuated g/C Ratio	0.08	0.39	0.39	0.28	0.28	0.28	0.44	0.36	0.36	0.45	0.36	1.00
v/c Ratio	0.99	0.64	0.22	0.25	1.08	0.99	0.47	0.92	0.05	1.24	0.62	0.24
Control Delay	110.4	30.2	3.8	37.8	105.7	64.2	21.7	49.2	0.1	168.2	30.2	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	110.4	30.2	3.8	37.8	105.7	64.2	21.7	49.2	0.1	168.2	30.2	0.3
LOS	F	C	A	D	F	E	C	D	A	F	C	A
Approach Delay		50.0			82.5			45.2			48.2	
Approach LOS		D			F			D			D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
 Natural Cycle: 120
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 1.24
 Intersection Signal Delay: 56.0
 Intersection LOS: E
 Intersection Capacity Utilization 97.3%
 ICU Level of Service F
 Analysis Period (min) 15

Splits and Phases: 5: Marksheffel Rd & SH-94



HCM 6th Signalized Intersection Summary

2040 Total PM Improved.syn

5: Marksheffel Rd & SH-94

09/09/2020



Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↖↗	↑	↖	↖	↑	↖	↖	↑↑	↖	↖	↑↑	↖
Traffic Volume (veh/h)	250	425	145	50	505	520	130	1080	30	255	755	355
Future Volume (veh/h)	250	425	145	50	505	520	130	1080	30	255	755	355
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1856	1856	1856	1856	1856	1856	1870	1870	1870	1841	1841	1841
Adj Flow Rate, veh/h	272	462	49	54	549	315	141	1174	33	263	778	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.97	0.97	0.97
Percent Heavy Veh, %	3	3	3	3	3	3	2	2	2	4	4	4
Cap, veh/h	277	730	619	303	510	432	378	1282	572	234	1336	
Arrive On Green	0.16	0.79	0.79	0.28	0.28	0.28	0.07	0.36	0.36	0.17	0.76	0.00
Sat Flow, veh/h	3428	1856	1572	882	1856	1572	1781	3554	1585	1753	3497	1560
Grp Volume(v), veh/h	272	462	49	54	549	315	141	1174	33	263	778	0
Grp Sat Flow(s),veh/h/ln	1714	1856	1572	882	1856	1572	1781	1777	1585	1753	1749	1560
Q Serve(g_s), s	9.5	12.7	0.9	5.7	33.0	21.8	5.9	37.8	1.6	10.5	11.3	0.0
Cycle Q Clear(g_c), s	9.5	12.7	0.9	5.7	33.0	21.8	5.9	37.8	1.6	10.5	11.3	0.0
Prop In Lane	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Lane Grp Cap(c), veh/h	277	730	619	303	510	432	378	1282	572	234	1336	
V/C Ratio(X)	0.98	0.63	0.08	0.18	1.08	0.73	0.37	0.92	0.06	1.12	0.58	
Avail Cap(c_a), veh/h	277	730	619	303	510	432	432	1282	572	234	1336	
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00	2.00	2.00
Upstream Filter(l)	0.91	0.91	0.91	1.00	1.00	1.00	1.00	1.00	1.00	0.94	0.94	0.00
Uniform Delay (d), s/veh	50.2	9.1	7.9	33.6	43.5	39.4	21.8	36.6	25.0	26.9	10.1	0.0
Incr Delay (d2), s/veh	46.4	1.6	0.0	0.3	61.8	6.1	0.6	11.6	0.2	94.2	1.7	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.5	3.4	0.3	1.2	23.7	9.1	2.5	18.2	0.7	9.9	3.2	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	96.6	10.7	7.9	33.9	105.3	45.5	22.4	48.3	25.2	121.1	11.8	0.0
LnGrp LOS	F	B	A	C	F	D	C	D	C	F	B	
Approach Vol, veh/h		783			918			1348			1041	A
Approach Delay, s/veh		40.4			80.6			45.0			39.4	
Approach LOS		D			F			D			D	
Timer - Assigned Phs	1	2		4	5	6	7	8				
Phs Duration (G+Y+Rc), s	17.0	49.8		53.2	14.4	52.4	14.2	39.0				
Change Period (Y+Rc), s	6.5	6.5		6.0	6.5	6.5	4.5	6.0				
Max Green Setting (Gmax), s	10.5	43.3		47.2	11.6	42.2	9.7	33.0				
Max Q Clear Time (g_c+I1), s	12.5	39.8		14.7	7.9	13.3	11.5	35.0				
Green Ext Time (p_c), s	0.0	2.4		3.4	0.1	6.1	0.0	0.0				

Intersection Summary

HCM 6th Ctrl Delay	50.7
HCM 6th LOS	D

Notes

Unsignalized Delay for [SBR] is excluded from calculations of the approach delay and intersection delay.

Intersection						
Int Delay, s/veh	1.4					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↕	↕	↗
Traffic Vol, veh/h	50	100	85	1395	810	195
Future Vol, veh/h	50	100	85	1395	810	195
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	150	-	-	150
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	54	109	92	1516	880	212

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	1822	440	1092	0	-	0
Stage 1	880	-	-	-	-	-
Stage 2	942	-	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-	-
Pot Cap-1 Maneuver	*246	565	635	-	-	-
Stage 1	*366	-	-	-	-	-
Stage 2	*474	-	-	-	-	-
Platoon blocked, %	1			-	-	-
Mov Cap-1 Maneuver	*210	565	635	-	-	-
Mov Cap-2 Maneuver	*210	-	-	-	-	-
Stage 1	*313	-	-	-	-	-
Stage 2	*474	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	17.9	0.7	0
HCM LOS	C		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	635	-	210	565	-	-
HCM Lane V/C Ratio	0.145	-	0.259	0.192	-	-
HCM Control Delay (s)	11.6	-	28	12.9	-	-
HCM Lane LOS	B	-	D	B	-	-
HCM 95th %tile Q(veh)	0.5	-	1	0.7	-	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Intersection						
Int Delay, s/veh	4.9					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↙	↗	↙	↑↑	↑↑	↗
Traffic Vol, veh/h	55	110	125	960	1025	295
Future Vol, veh/h	55	110	125	960	1025	295
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	150	-	-	150
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	60	120	136	1043	1114	321

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	1908	557	1435	0	-	0
Stage 1	1114	-	-	-	-	-
Stage 2	794	-	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-	-
Pot Cap-1 Maneuver	*101	474	469	-	-	-
Stage 1	*276	-	-	-	-	-
Stage 2	*646	-	-	-	-	-
Platoon blocked, %	1			-	-	-
Mov Cap-1 Maneuver	*71	474	469	-	-	-
Mov Cap-2 Maneuver	*71	-	-	-	-	-
Stage 1	*196	-	-	-	-	-
Stage 2	*646	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	64.5	1.8	0
HCM LOS	F		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	469	-	71	474	-	-
HCM Lane V/C Ratio	0.29	-	0.842	0.252	-	-
HCM Control Delay (s)	15.8	-	163.2	15.1	-	-
HCM Lane LOS	C	-	F	C	-	-
HCM 95th %tile Q(veh)	1.2	-	4.1	1	-	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Timings
6: Marksheffel Rd & North Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	50	100	85	1395	810	195
Future Volume (vph)	50	100	85	1395	810	195
Turn Type	Prot	Perm	Perm	NA	NA	Perm
Protected Phases	4			2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	2	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	27.0	27.0	93.0	93.0	93.0	93.0
Total Split (%)	22.5%	22.5%	77.5%	77.5%	77.5%	77.5%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	9.0	9.0	102.0	102.0	102.0	102.0
Actuated g/C Ratio	0.08	0.08	0.85	0.85	0.85	0.85
v/c Ratio	0.41	0.50	0.18	0.50	0.29	0.15
Control Delay	61.2	17.4	4.7	7.0	2.7	1.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.2	17.4	4.7	7.0	2.7	1.1
LOS	E	B	A	A	A	A
Approach Delay	31.9			6.9	2.4	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.50
 Intersection Signal Delay: 6.6
 Intersection Capacity Utilization 50.2%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service A

Splits and Phases: 6: Marksheffel Rd & North Full Access



HCM 6th Signalized Intersection Summary
 6: Marksheffel Rd & North Full Access

2025 Total AM Improved.syn
 09/09/2020



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	50	100	85	1395	810	195
Future Volume (veh/h)	50	100	85	1395	810	195
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	54	109	92	1516	880	212
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	154	137	465	2979	2979	1329
Arrive On Green	0.09	0.09	1.00	1.00	0.84	0.84
Sat Flow, veh/h	1781	1585	516	3647	3647	1585
Grp Volume(v), veh/h	54	109	92	1516	880	212
Grp Sat Flow(s),veh/h/ln	1781	1585	516	1777	1777	1585
Q Serve(g_s), s	3.4	8.1	1.7	0.0	6.4	3.0
Cycle Q Clear(g_c), s	3.4	8.1	8.1	0.0	6.4	3.0
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	154	137	465	2979	2979	1329
V/C Ratio(X)	0.35	0.79	0.20	0.51	0.30	0.16
Avail Cap(c_a), veh/h	334	297	465	2979	2979	1329
HCM Platoon Ratio	1.00	1.00	2.00	2.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.84	0.84	1.00	1.00
Uniform Delay (d), s/veh	51.6	53.7	0.3	0.0	2.1	1.8
Incr Delay (d2), s/veh	1.3	9.8	0.8	0.5	0.3	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.6	3.6	0.1	0.2	1.6	0.7
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	53.0	63.6	1.1	0.5	2.3	2.1
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h	163			1608	1092	
Approach Delay, s/veh	60.1			0.6	2.3	
Approach LOS	E			A	A	
Timer - Assigned Phs		2		4		6
Phs Duration (G+Y+Rc), s		105.1		14.9		105.1
Change Period (Y+Rc), s		4.5		4.5		4.5
Max Green Setting (Gmax), s		88.5		22.5		88.5
Max Q Clear Time (g_c+l1), s		10.1		10.1		8.4
Green Ext Time (p_c), s		23.6		0.4		9.1
Intersection Summary						
HCM 6th Ctrl Delay			4.6			
HCM 6th LOS			A			

Timings

6: Marksheffel Rd & North Full Access




Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	55	110	125	960	1025	295
Future Volume (vph)	55	110	125	960	1025	295
Turn Type	Prot	Perm	Perm	NA	NA	Perm
Protected Phases	4			2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	2	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	25.0	25.0	95.0	95.0	95.0	95.0
Total Split (%)	20.8%	20.8%	79.2%	79.2%	79.2%	79.2%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	9.4	9.4	101.6	101.6	101.6	101.6
Actuated g/C Ratio	0.08	0.08	0.85	0.85	0.85	0.85
v/c Ratio	0.43	0.51	0.35	0.35	0.37	0.23
Control Delay	61.6	16.9	11.1	6.4	3.7	1.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.6	16.9	11.1	6.4	3.7	1.3
LOS	E	B	B	A	A	A
Approach Delay	31.8			7.0	3.1	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.51
 Intersection Signal Delay: 6.6
 Intersection LOS: A
 Intersection Capacity Utilization 50.7%
 ICU Level of Service A
 Analysis Period (min) 15

Splits and Phases: 6: Marksheffel Rd & North Full Access



HCM 6th Signalized Intersection Summary
 6: Marksheffel Rd & North Full Access

2025 Total PM Improved.syn
 09/09/2020



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	55	110	125	960	1025	295
Future Volume (veh/h)	55	110	125	960	1025	295
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	60	120	136	1043	1114	321
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	167	148	341	2955	2955	1318
Arrive On Green	0.09	0.09	1.00	1.00	0.83	0.83
Sat Flow, veh/h	1781	1585	372	3647	3647	1585
Grp Volume(v), veh/h	60	120	136	1043	1114	321
Grp Sat Flow(s),veh/h/ln	1781	1585	372	1777	1777	1585
Q Serve(g_s), s	3.8	8.9	7.2	0.0	9.2	5.1
Cycle Q Clear(g_c), s	3.8	8.9	16.5	0.0	9.2	5.1
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	167	148	341	2955	2955	1318
V/C Ratio(X)	0.36	0.81	0.40	0.35	0.38	0.24
Avail Cap(c_a), veh/h	304	271	341	2955	2955	1318
HCM Platoon Ratio	1.00	1.00	2.00	2.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.93	0.93	1.00	1.00
Uniform Delay (d), s/veh	51.0	53.3	0.8	0.0	2.5	2.1
Incr Delay (d2), s/veh	1.3	10.0	3.2	0.3	0.4	0.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.8	4.0	0.3	0.1	2.4	1.3
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	52.3	63.3	4.0	0.3	2.9	2.6
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h				1179	1435	
Approach Delay, s/veh				0.7	2.8	
Approach LOS				A	A	
Timer - Assigned Phs		2		4		6
Phs Duration (G+Y+Rc), s		104.3		15.7		104.3
Change Period (Y+Rc), s		4.5		4.5		4.5
Max Green Setting (Gmax), s		90.5		20.5		90.5
Max Q Clear Time (g_c+l1), s		18.5		10.9		11.2
Green Ext Time (p_c), s		15.6		0.3		13.8
Intersection Summary						
HCM 6th Ctrl Delay			5.6			
HCM 6th LOS			A			

Timings
6: Marksheffel Rd & North Full Access




Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (vph)	50	100	85	1650	940	195
Future Volume (vph)	50	100	85	1650	940	195
Turn Type	Prot	Perm	Perm	NA	NA	Perm
Protected Phases	4			2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	2	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	24.0	24.0	96.0	96.0	96.0	96.0
Total Split (%)	20.0%	20.0%	80.0%	80.0%	80.0%	80.0%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	9.0	9.0	102.0	102.0	102.0	102.0
Actuated g/C Ratio	0.08	0.08	0.85	0.85	0.85	0.85
v/c Ratio	0.41	0.50	0.21	0.60	0.34	0.15
Control Delay	61.2	17.4	1.7	2.7	7.7	3.2
Queue Delay	0.0	0.0	0.0	0.2	0.0	0.0
Total Delay	61.2	17.4	1.7	2.9	7.7	3.2
LOS	E	B	A	A	A	A
Approach Delay	31.9			2.8	7.0	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.60
 Intersection Signal Delay: 5.8
 Intersection Capacity Utilization 57.3%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service B

Splits and Phases: 6: Marksheffel Rd & North Full Access



HCM 6th Signalized Intersection Summary
6: Marksheffel Rd & North Full Access

2040 Total AM.syn
09/09/2020



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	50	100	85	1650	940	195
Future Volume (veh/h)	50	100	85	1650	940	195
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	54	109	92	1793	1022	212
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	154	137	409	2981	2981	1329
Arrive On Green	0.09	0.09	1.00	1.00	0.84	0.84
Sat Flow, veh/h	1781	1585	451	3647	3647	1585
Grp Volume(v), veh/h	54	109	92	1793	1022	212
Grp Sat Flow(s),veh/h/ln	1781	1585	451	1777	1777	1585
Q Serve(g_s), s	3.4	8.1	2.5	0.0	7.8	3.0
Cycle Q Clear(g_c), s	3.4	8.1	10.3	0.0	7.8	3.0
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	154	137	409	2981	2981	1329
V/C Ratio(X)	0.35	0.80	0.22	0.60	0.34	0.16
Avail Cap(c_a), veh/h	289	258	409	2981	2981	1329
HCM Platoon Ratio	1.00	1.00	2.00	2.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.75	0.75	1.00	1.00
Uniform Delay (d), s/veh	51.7	53.8	0.4	0.0	2.2	1.8
Incr Delay (d2), s/veh	1.4	10.1	1.0	0.7	0.3	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.6	3.6	0.1	0.3	1.9	0.7
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	53.0	63.9	1.4	0.7	2.5	2.1
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h	163			1885	1234	
Approach Delay, s/veh	60.3			0.7	2.4	
Approach LOS	E			A	A	
Timer - Assigned Phs		2		4		6
Phs Duration (G+Y+Rc), s		105.2		14.8		105.2
Change Period (Y+Rc), s		4.5		4.5		4.5
Max Green Setting (Gmax), s		91.5		19.5		91.5
Max Q Clear Time (g_c+l1), s		12.3		10.1		9.8
Green Ext Time (p_c), s		33.5		0.3		11.3
Intersection Summary						
HCM 6th Ctrl Delay			4.3			
HCM 6th LOS			A			

Timings
6: Marksheffel Rd & North Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	55	110	125	1130	1180	295
Future Volume (vph)	55	110	125	1130	1180	295
Turn Type	Prot	Perm	Perm	NA	NA	Perm
Protected Phases	4			2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	2	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	23.0	23.0	97.0	97.0	97.0	97.0
Total Split (%)	19.2%	19.2%	80.8%	80.8%	80.8%	80.8%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	9.4	9.4	101.6	101.6	101.6	101.6
Actuated g/C Ratio	0.08	0.08	0.85	0.85	0.85	0.85
v/c Ratio	0.43	0.51	0.43	0.41	0.43	0.23
Control Delay	61.6	16.9	12.1	6.2	5.4	2.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.6	16.9	12.1	6.2	5.4	2.0
LOS	E	B	B	A	A	A
Approach Delay	31.8			6.8	4.7	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.51
 Intersection Signal Delay: 7.2
 Intersection Capacity Utilization 55.0%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service A

Splits and Phases: 6: Marksheffel Rd & North Full Access



HCM 6th Signalized Intersection Summary
 6: Marksheffel Rd & North Full Access

2040 Total PM.syn
 09/09/2020



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	55	110	125	1130	1180	295
Future Volume (veh/h)	55	110	125	1130	1180	295
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	60	120	136	1228	1283	321
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	166	148	293	2956	2956	1318
Arrive On Green	0.09	0.09	1.00	1.00	0.83	0.83
Sat Flow, veh/h	1781	1585	317	3647	3647	1585
Grp Volume(v), veh/h	60	120	136	1228	1283	321
Grp Sat Flow(s),veh/h/ln	1781	1585	317	1777	1777	1585
Q Serve(g_s), s	3.8	8.9	12.2	0.0	11.4	5.1
Cycle Q Clear(g_c), s	3.8	8.9	23.6	0.0	11.4	5.1
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	166	148	293	2956	2956	1318
V/C Ratio(X)	0.36	0.81	0.46	0.42	0.43	0.24
Avail Cap(c_a), veh/h	275	244	293	2956	2956	1318
HCM Platoon Ratio	1.00	1.00	2.00	2.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	0.90	0.90	1.00	1.00
Uniform Delay (d), s/veh	51.1	53.4	1.3	0.0	2.7	2.1
Incr Delay (d2), s/veh	1.3	10.2	4.7	0.4	0.5	0.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.8	4.0	0.5	0.2	2.9	1.2
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	52.4	63.6	6.0	0.4	3.1	2.6
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h	180			1364	1604	
Approach Delay, s/veh	59.8			1.0	3.0	
Approach LOS	E			A	A	
Timer - Assigned Phs		2		4		6
Phs Duration (G+Y+Rc), s		104.3		15.7		104.3
Change Period (Y+Rc), s		4.5		4.5		4.5
Max Green Setting (Gmax), s		92.5		18.5		92.5
Max Q Clear Time (g_c+I1), s		25.6		10.9		13.4
Green Ext Time (p_c), s		20.6		0.3		17.5
Intersection Summary						
HCM 6th Ctrl Delay			5.4			
HCM 6th LOS			A			

Intersection						
Int Delay, s/veh	3.1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↕↕	↕↕	↗
Traffic Vol, veh/h	50	295	165	1430	800	110
Future Vol, veh/h	50	295	165	1430	800	110
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	150	-	-	150
Veh in Median Storage, #	2	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	54	321	179	1554	870	120

Major/Minor	Minor2	Major1		Major2	
Conflicting Flow All	2005	435	990	0	0
Stage 1	870	-	-	-	-
Stage 2	1135	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-
Pot Cap-1 Maneuver	*156	569	694	-	-
Stage 1	*370	-	-	-	-
Stage 2	*449	-	-	-	-
Platoon blocked, %	1	-	-	-	-
Mov Cap-1 Maneuver	*116	569	694	-	-
Mov Cap-2 Maneuver	*241	-	-	-	-
Stage 1	*275	-	-	-	-
Stage 2	*449	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	19.9	1.2	0
HCM LOS	C		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	694	-	241	569	-	-
HCM Lane V/C Ratio	0.258	-	0.226	0.564	-	-
HCM Control Delay (s)	12	-	24.2	19.2	-	-
HCM Lane LOS	B	-	C	C	-	-
HCM 95th %tile Q(veh)	1	-	0.8	3.5	-	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Intersection						
Int Delay, s/veh	5.6					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↙	↗	↙	↑↑	↑↑	↗
Traffic Vol, veh/h	55	320	250	1030	965	170
Future Vol, veh/h	55	320	250	1030	965	170
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	150	-	-	150
Veh in Median Storage, #	2	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	60	348	272	1120	1049	185

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	2153	525	1234	0	-	0
Stage 1	1049	-	-	-	-	-
Stage 2	1104	-	-	-	-	-
Critical Hdwy	6.84	6.94	4.14	-	-	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	2.22	-	-	-
Pot Cap-1 Maneuver	*~ 58	497	560	-	-	-
Stage 1	*298	-	-	-	-	-
Stage 2	*622	-	-	-	-	-
Platoon blocked, %	1			-	-	-
Mov Cap-1 Maneuver	*~ 30	497	560	-	-	-
Mov Cap-2 Maneuver	*141	-	-	-	-	-
Stage 1	*153	-	-	-	-	-
Stage 2	*622	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	30.4	3.4	0
HCM LOS	D		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	560	-	141	497	-	-
HCM Lane V/C Ratio	0.485	-	0.424	0.7	-	-
HCM Control Delay (s)	17.3	-	48.1	27.4	-	-
HCM Lane LOS	C	-	E	D	-	-
HCM 95th %tile Q(veh)	2.6	-	1.9	5.4	-	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Timings

7: Marksheffel Rd & South Full Access




Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	50	295	165	1430	800	110
Future Volume (vph)	50	295	165	1430	800	110
Turn Type	Prot	Perm	pm+pt	NA	NA	Perm
Protected Phases	4		5	2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	5	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	9.5	22.5	22.5	22.5
Total Split (s)	53.0	53.0	20.0	67.0	47.0	47.0
Total Split (%)	44.2%	44.2%	16.7%	55.8%	39.2%	39.2%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag			Lead		Lag	Lag
Lead-Lag Optimize?			Yes		Yes	Yes
Recall Mode	None	None	None	C-Max	C-Max	C-Max
Act Effect Green (s)	10.1	10.1	100.9	100.9	88.5	88.5
Actuated g/C Ratio	0.08	0.08	0.84	0.84	0.74	0.74
v/c Ratio	0.36	0.75	0.34	0.52	0.33	0.10
Control Delay	57.1	17.2	4.7	5.6	2.5	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.1	17.2	4.7	5.6	2.5	0.3
LOS	E	B	A	A	A	A
Approach Delay	22.9			5.5	2.2	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.75
 Intersection Signal Delay: 6.6
 Intersection Capacity Utilization 51.2%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service A

Splits and Phases: 7: Marksheffel Rd & South Full Access





Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	50	295	165	1430	800	110
Future Volume (veh/h)	50	295	165	1430	800	110
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	54	321	179	1554	870	120
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	399	355	505	2491	2160	963
Arrive On Green	0.22	0.22	0.07	0.93	1.00	1.00
Sat Flow, veh/h	1781	1585	1781	3647	3647	1585
Grp Volume(v), veh/h	54	321	179	1554	870	120
Grp Sat Flow(s),veh/h/ln	1781	1585	1781	1777	1777	1585
Q Serve(g_s), s	2.9	23.6	4.4	8.5	0.0	0.0
Cycle Q Clear(g_c), s	2.9	23.6	4.4	8.5	0.0	0.0
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	399	355	505	2491	2160	963
V/C Ratio(X)	0.14	0.90	0.35	0.62	0.40	0.12
Avail Cap(c_a), veh/h	720	641	636	2491	2160	963
HCM Platoon Ratio	1.00	1.00	1.33	1.33	2.00	2.00
Upstream Filter(l)	1.00	1.00	0.87	0.87	0.96	0.96
Uniform Delay (d), s/veh	37.2	45.3	6.7	1.5	0.0	0.0
Incr Delay (d2), s/veh	0.2	8.6	0.4	1.0	0.5	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.3	19.8	1.6	1.7	0.2	0.1
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	37.4	53.9	7.1	2.5	0.5	0.3
LnGrp LOS	D	D	A	A	A	A
Approach Vol, veh/h	375			1733	990	
Approach Delay, s/veh	51.5			3.0	0.5	
Approach LOS	D			A	A	
Timer - Assigned Phs		2		4	5	6
Phs Duration (G+Y+Rc), s		88.6		31.4	11.2	77.4
Change Period (Y+Rc), s		4.5		4.5	4.5	4.5
Max Green Setting (Gmax), s		62.5		48.5	15.5	42.5
Max Q Clear Time (g_c+l1), s		10.5		25.6	6.4	2.0
Green Ext Time (p_c), s		19.5		1.3	0.3	8.1
Intersection Summary						
HCM 6th Ctrl Delay			8.1			
HCM 6th LOS			A			

Timings

7: Marksheffel Rd & South Full Access




Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	55	320	250	1030	965	170
Future Volume (vph)	55	320	250	1030	965	170
Turn Type	Prot	Perm	pm+pt	NA	NA	Perm
Protected Phases	4		5	2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	5	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	9.5	22.5	22.5	22.5
Total Split (s)	49.0	49.0	29.0	71.0	42.0	42.0
Total Split (%)	40.8%	40.8%	24.2%	59.2%	35.0%	35.0%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag			Lead		Lag	Lag
Lead-Lag Optimize?			Yes		Yes	Yes
Recall Mode	None	None	None	C-Max	C-Max	C-Max
Act Effect Green (s)	10.5	10.5	100.5	100.5	81.2	81.2
Actuated g/C Ratio	0.09	0.09	0.84	0.84	0.68	0.68
v/c Ratio	0.39	0.76	0.54	0.38	0.44	0.17
Control Delay	57.3	16.8	3.7	2.1	4.2	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	16.8	3.7	2.1	4.2	0.4
LOS	E	B	A	A	A	A
Approach Delay	22.7			2.4	3.7	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.76
 Intersection Signal Delay: 5.6
 Intersection LOS: A
 Intersection Capacity Utilization 55.9%
 ICU Level of Service B
 Analysis Period (min) 15

Splits and Phases: 7: Marksheffel Rd & South Full Access



HCM 6th Signalized Intersection Summary

2025 Total PM Improved.syn

7: Marksheffel Rd & South Full Access

09/09/2020



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	55	320	250	1030	965	170
Future Volume (veh/h)	55	320	250	1030	965	170
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	60	348	272	1120	1049	185
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	429	382	462	2431	2002	893
Arrive On Green	0.24	0.24	0.08	0.68	1.00	1.00
Sat Flow, veh/h	1781	1585	1781	3647	3647	1585
Grp Volume(v), veh/h	60	348	272	1120	1049	185
Grp Sat Flow(s),veh/h/ln	1781	1585	1781	1777	1777	1585
Q Serve(g_s), s	3.2	25.6	7.3	17.4	0.0	0.0
Cycle Q Clear(g_c), s	3.2	25.6	7.3	17.4	0.0	0.0
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	429	382	462	2431	2002	893
V/C Ratio(X)	0.14	0.91	0.59	0.46	0.52	0.21
Avail Cap(c_a), veh/h	661	588	678	2431	2002	893
HCM Platoon Ratio	1.00	1.00	1.00	1.00	2.00	2.00
Upstream Filter(l)	1.00	1.00	0.45	0.45	0.93	0.93
Uniform Delay (d), s/veh	35.8	44.3	8.1	8.7	0.0	0.0
Incr Delay (d2), s/veh	0.1	13.1	0.5	0.3	0.9	0.5
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.4	21.8	2.7	6.4	0.3	0.1
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	35.9	57.4	8.6	9.0	0.9	0.5
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h	408			1392	1234	
Approach Delay, s/veh	54.2			8.9	0.9	
Approach LOS	D			A	A	
Timer - Assigned Phs		2		4	5	6
Phs Duration (G+Y+Rc), s		86.6		33.4	14.5	72.1
Change Period (Y+Rc), s		4.5		4.5	4.5	4.5
Max Green Setting (Gmax), s		66.5		44.5	24.5	37.5
Max Q Clear Time (g_c+l1), s		19.4		27.6	9.3	2.0
Green Ext Time (p_c), s		11.0		1.3	0.7	10.4
Intersection Summary						
HCM 6th Ctrl Delay			11.7			
HCM 6th LOS			B			

Timings
7: Marksheffel Rd & South Full Access

2040 Total AM.syn
09/09/2020




Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	50	295	165	1685	930	110
Future Volume (vph)	50	295	165	1685	930	110
Turn Type	Prot	Perm	pm+pt	NA	NA	Perm
Protected Phases	4		5	2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	5	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	9.5	22.5	22.5	22.5
Total Split (s)	41.0	41.0	18.0	79.0	61.0	61.0
Total Split (%)	34.2%	34.2%	15.0%	65.8%	50.8%	50.8%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag			Lead		Lag	Lag
Lead-Lag Optimize?			Yes		Yes	Yes
Recall Mode	None	None	None	C-Max	C-Max	C-Max
Act Effect Green (s)	12.4	12.4	98.6	98.6	85.9	85.9
Actuated g/C Ratio	0.10	0.10	0.82	0.82	0.72	0.72
v/c Ratio	0.30	0.81	0.39	0.63	0.40	0.10
Control Delay	51.0	27.4	5.7	5.2	3.6	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.0	27.4	5.7	5.2	3.6	0.2
LOS	D	C	A	A	A	A
Approach Delay	30.8			5.2	3.2	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green
 Natural Cycle: 65
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.81
 Intersection Signal Delay: 7.3
 Intersection Capacity Utilization 58.2%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service B

Splits and Phases: 7: Marksheffel Rd & South Full Access



HCM 6th Signalized Intersection Summary
 7: Marksheffel Rd & South Full Access

2040 Total AM.syn
 09/09/2020



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	50	295	165	1685	930	110
Future Volume (veh/h)	50	295	165	1685	930	110
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	54	321	179	1832	1011	120
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	396	352	463	2497	2164	965
Arrive On Green	0.22	0.22	0.11	1.00	1.00	1.00
Sat Flow, veh/h	1781	1585	1781	3647	3647	1585
Grp Volume(v), veh/h	54	321	179	1832	1011	120
Grp Sat Flow(s),veh/h/ln	1781	1585	1781	1777	1777	1585
Q Serve(g_s), s	2.9	23.7	4.5	0.0	0.0	0.0
Cycle Q Clear(g_c), s	2.9	23.7	4.5	0.0	0.0	0.0
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	396	352	463	2497	2164	965
V/C Ratio(X)	0.14	0.91	0.39	0.73	0.47	0.12
Avail Cap(c_a), veh/h	542	482	563	2497	2164	965
HCM Platoon Ratio	1.00	1.00	2.00	2.00	2.00	2.00
Upstream Filter(l)	1.00	1.00	0.66	0.66	0.94	0.94
Uniform Delay (d), s/veh	37.4	45.5	6.4	0.0	0.0	0.0
Incr Delay (d2), s/veh	0.2	17.4	0.3	1.3	0.7	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.3	20.7	1.5	0.4	0.2	0.1
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	37.6	62.9	6.8	1.3	0.7	0.2
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h	375			2011	1131	
Approach Delay, s/veh	59.2			1.8	0.6	
Approach LOS	E			A	A	
Timer - Assigned Phs		2		4	5	6
Phs Duration (G+Y+Rc), s		88.8		31.2	11.3	77.6
Change Period (Y+Rc), s		4.5		4.5	4.5	4.5
Max Green Setting (Gmax), s		74.5		36.5	13.5	56.5
Max Q Clear Time (g_c+I1), s		2.0		25.7	6.5	2.0
Green Ext Time (p_c), s		29.7		1.0	0.3	10.3
Intersection Summary						
HCM 6th Ctrl Delay			7.5			
HCM 6th LOS			A			
Notes						
User approved volume balancing among the lanes for turning movement.						

Timings
7: Marksheffel Rd & South Full Access

2040 Total PM.syn
09/09/2020



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↖	↗	↖	↑↑	↑↑	↗
Traffic Volume (vph)	55	320	250	1200	1120	170
Future Volume (vph)	55	320	250	1200	1120	170
Turn Type	Prot	Perm	pm+pt	NA	NA	Perm
Protected Phases	4		5	2	6	
Permitted Phases		4	2			6
Detector Phase	4	4	5	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	9.5	22.5	22.5	22.5
Total Split (s)	42.0	42.0	28.0	78.0	50.0	50.0
Total Split (%)	35.0%	35.0%	23.3%	65.0%	41.7%	41.7%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag			Lead		Lag	Lag
Lead-Lag Optimize?			Yes		Yes	Yes
Recall Mode	None	None	None	C-Max	C-Max	C-Max
Act Effect Green (s)	10.5	10.5	100.5	100.5	79.9	79.9
Actuated g/C Ratio	0.09	0.09	0.84	0.84	0.67	0.67
v/c Ratio	0.39	0.76	0.59	0.44	0.52	0.17
Control Delay	57.5	16.8	10.3	5.4	4.8	0.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.5	16.8	10.3	5.4	4.8	0.6
LOS	E	B	B	A	A	A
Approach Delay	22.8			6.2	4.3	
Approach LOS	C			A	A	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.76
 Intersection Signal Delay: 7.4
 Intersection Capacity Utilization 60.2%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service B

Splits and Phases: 7: Marksheffel Rd & South Full Access



HCM 6th Signalized Intersection Summary

2040 Total PM.syn

09/09/2020

7: Marksheffel Rd & South Full Access



Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	55	320	250	1200	1120	170
Future Volume (veh/h)	55	320	250	1200	1120	170
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00	1.00			1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No	No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	60	348	272	1304	1217	185
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	426	379	433	2437	1988	887
Arrive On Green	0.24	0.24	0.18	1.00	1.00	1.00
Sat Flow, veh/h	1781	1585	1781	3647	3647	1585
Grp Volume(v), veh/h	60	348	272	1304	1217	185
Grp Sat Flow(s),veh/h/ln	1781	1585	1781	1777	1777	1585
Q Serve(g_s), s	3.2	25.7	8.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	3.2	25.7	8.0	0.0	0.0	0.0
Prop In Lane	1.00	1.00	1.00			1.00
Lane Grp Cap(c), veh/h	426	379	433	2437	1988	887
V/C Ratio(X)	0.14	0.92	0.63	0.54	0.61	0.21
Avail Cap(c_a), veh/h	557	495	624	2437	1988	887
HCM Platoon Ratio	1.00	1.00	2.00	2.00	2.00	2.00
Upstream Filter(l)	1.00	1.00	0.09	0.09	0.90	0.90
Uniform Delay (d), s/veh	35.9	44.5	7.3	0.0	0.0	0.0
Incr Delay (d2), s/veh	0.1	18.7	0.1	0.1	1.3	0.5
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.4	22.4	2.4	0.0	0.4	0.1
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	36.1	63.2	7.5	0.1	1.3	0.5
LnGrp LOS	D	E	A	A	A	A
Approach Vol, veh/h	408			1576	1402	
Approach Delay, s/veh	59.2			1.4	1.2	
Approach LOS	E			A	A	
Timer - Assigned Phs		2		4	5	6
Phs Duration (G+Y+Rc), s		86.8		33.2	15.1	71.6
Change Period (Y+Rc), s		4.5		4.5	4.5	4.5
Max Green Setting (Gmax), s		73.5		37.5	23.5	45.5
Max Q Clear Time (g_c+I1), s		2.0		27.7	10.0	2.0
Green Ext Time (p_c), s		15.0		1.0	0.7	13.5

Intersection Summary

HCM 6th Ctrl Delay	8.2
HCM 6th LOS	A

Notes

User approved volume balancing among the lanes for turning movement.

Intersection												
Int Delay, s/veh	1.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↕	↕		↕	↕	
Traffic Vol, veh/h	5	0	10	30	0	5	5	205	10	5	275	5
Future Vol, veh/h	5	0	10	30	0	5	5	205	10	5	275	5
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	150	-	-	150	-	-
Veh in Median Storage, #	-	2	-	-	2	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	5	0	11	33	0	5	5	223	11	5	299	5

Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	553	556	302	556	553	229	304	0	0	234	0	0
Stage 1	312	312	-	239	239	-	-	-	-	-	-	-
Stage 2	241	244	-	317	314	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	444	439	738	442	441	810	1257	-	-	1333	-	-
Stage 1	699	658	-	764	708	-	-	-	-	-	-	-
Stage 2	762	704	-	694	656	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	438	435	738	433	437	810	1257	-	-	1333	-	-
Mov Cap-2 Maneuver	594	564	-	586	563	-	-	-	-	-	-	-
Stage 1	696	655	-	761	705	-	-	-	-	-	-	-
Stage 2	754	701	-	681	653	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	10.4		11.3		0.2		0.1	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1257	-	-	683	610	1333	-
HCM Lane V/C Ratio	0.004	-	-	0.024	0.062	0.004	-
HCM Control Delay (s)	7.9	-	-	10.4	11.3	7.7	-
HCM Lane LOS	A	-	-	B	B	A	-
HCM 95th %tile Q(veh)	0	-	-	0.1	0.2	0	-

Intersection												
Int Delay, s/veh	1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↕	↕		↕	↕	
Traffic Vol, veh/h	5	0	10	20	0	5	10	170	35	10	320	5
Future Vol, veh/h	5	0	10	20	0	5	10	170	35	10	320	5
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	150	-	-	150	-	-
Veh in Median Storage, #	-	2	-	-	2	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	5	0	11	22	0	5	11	185	38	11	348	5

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	602	618	351	604	601	204	353	0	0	223	0	0
Stage 1	373	373	-	226	226	-	-	-	-	-	-	-
Stage 2	229	245	-	378	375	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	412	405	692	410	414	837	1206	-	-	1346	-	-
Stage 1	648	618	-	777	717	-	-	-	-	-	-	-
Stage 2	774	703	-	644	617	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	404	398	692	398	407	837	1206	-	-	1346	-	-
Mov Cap-2 Maneuver	560	532	-	549	534	-	-	-	-	-	-	-
Stage 1	642	613	-	770	711	-	-	-	-	-	-	-
Stage 2	762	697	-	629	612	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	10.8		11.4		0.4		0.2	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1206	-	-	642	590	1346	-
HCM Lane V/C Ratio	0.009	-	-	0.025	0.046	0.008	-
HCM Control Delay (s)	8	-	-	10.8	11.4	7.7	-
HCM Lane LOS	A	-	-	B	B	A	-
HCM 95th %tile Q(veh)	0	-	-	0.1	0.1	0	-

Intersection												
Int Delay, s/veh	1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↕	↕		↕	↕	
Traffic Vol, veh/h	5	0	10	30	0	5	5	230	10	5	315	5
Future Vol, veh/h	5	0	10	30	0	5	5	230	10	5	315	5
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	150	-	-	150	-	-
Veh in Median Storage, #	-	2	-	-	2	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	5	0	11	33	0	5	5	250	11	5	342	5

Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	623	626	345	626	623	256	347	0	0	261	0	0
Stage 1	355	355	-	266	266	-	-	-	-	-	-	-
Stage 2	268	271	-	360	357	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	437	421	698	435	423	*894	1212	-	-	*1338	-	-
Stage 1	662	630	-	840	736	-	-	-	-	-	-	-
Stage 2	838	732	-	658	628	-	-	-	-	-	-	-
Platoon blocked, %	1	1		1	1	1		-	-	1	-	-
Mov Cap-1 Maneuver	432	418	698	425	420	*894	1212	-	-	*1338	-	-
Mov Cap-2 Maneuver	588	552	-	576	551	-	-	-	-	-	-	-
Stage 1	659	627	-	837	733	-	-	-	-	-	-	-
Stage 2	829	729	-	645	625	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	10.6		11.3		0.2		0.1	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1212	-	-	657	607	*1338	-
HCM Lane V/C Ratio	0.004	-	-	0.025	0.063	0.004	-
HCM Control Delay (s)	8	0	-	10.6	11.3	7.7	-
HCM Lane LOS	A	A	-	B	B	A	-
HCM 95th %tile Q(veh)	0	-	-	0.1	0.2	0	-

Notes
 -: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon

Intersection												
Int Delay, s/veh	1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↕	↕		↕	↕	
Traffic Vol, veh/h	5	0	10	20	0	5	10	185	35	10	370	5
Future Vol, veh/h	5	0	10	20	0	5	10	185	35	10	370	5
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	150	-	-	150	-	-
Veh in Median Storage, #	-	2	-	-	2	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	5	0	11	22	0	5	11	201	38	11	402	5

Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	672	688	405	674	671	220	407	0	0	239	0	0
Stage 1	427	427	-	242	242	-	-	-	-	-	-	-
Stage 2	245	261	-	432	429	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	388	377	646	387	387	908	1152	-	-	1353	-	-
Stage 1	606	585	-	832	738	-	-	-	-	-	-	-
Stage 2	828	723	-	602	584	-	-	-	-	-	-	-
Platoon blocked, %	1	1		1	1	1		-	-	1	-	-
Mov Cap-1 Maneuver	381	370	646	375	380	908	1152	-	-	1353	-	-
Mov Cap-2 Maneuver	538	512	-	523	511	-	-	-	-	-	-	-
Stage 1	600	580	-	823	731	-	-	-	-	-	-	-
Stage 2	815	715	-	587	579	-	-	-	-	-	-	-


Approach	EB		WB		NB		SB	
HCM Control Delay, s	11.1		11.6		0.4		0.2	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1152	-	-	605	571	1353	-
HCM Lane V/C Ratio	0.009	-	-	0.027	0.048	0.008	-
HCM Control Delay (s)	8.2	-	-	11.1	11.6	7.7	-
HCM Lane LOS	A	-	-	B	B	A	-
HCM 95th %tile Q(veh)	0	-	-	0.1	0.1	0	-

APPENDIX E

Signal Warrant Analysis

WARRANT 2 - FOUR HOUR VEHICULAR VOLUME



* NOTE: 115 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACH WITH TWO OR MORE LANES AND 80 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACHING WITH ONE LANE.

CROSSROADS—MEADOBROOK
 NEWT DRIVE AND MEADOWBROK PKWY
 FOUR HOUR VOLUME WARRANT


● 2025 Traffic Volume Projections
 Source: Manual of Uniform Traffic Control Devices 2009

APPENDIX FIGURE E1



WARRANT 2 - FOUR HOUR VEHICULAR VOLUME (70% FACTOR)

(COMMUNITY LESS THAN 10,000 POPULATION OR ABOVE 70 km/h (40 mph) ON MAJOR STREET)



* NOTE: 80 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACH WITH TWO OR MORE LANES AND 60 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACHING WITH ONE LANE.

MARKSHEFFEL RD AND NORTH FULL ACCESS

CROSSROADS-MEADOWBROOK

FOUR HOUR VOLUME WARRANT


● 2025 Peak Hour Traffic Volume Projections

Source: Manual of Uniform Traffic Control Devices 2009



WARRANT 2 - FOUR HOUR VEHICULAR VOLUME (70% FACTOR)

(COMMUNITY LESS THAN 10,000 POPULATION OR ABOVE 70 km/h (40 mph) ON MAJOR STREET)



* NOTE: 80 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACH WITH TWO OR MORE LANES AND 60 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACHING WITH ONE LANE.

MARKSHEFFEL RD AND SOUTH FULL ACCESS
 CROSSROADS-MEADOWBROOK
 FOUR HOUR VOLUME WARRANT

● 2025 Peak Hour Traffic Volume Projections

Source: Manual of Uniform Traffic Control Devices 2009




APPENDIX F

Queueing Analysis Worksheets

Queues

1: Marksheffel Rd & Meadowbrook Pkwy




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	207	11	38	38	22	27	33	870	16	11	1516	261
v/c Ratio	0.60	0.06	0.16	0.23	0.20	0.12	0.20	0.35	0.01	0.03	0.61	0.22
Control Delay	58.4	47.0	1.5	42.2	57.6	1.2	9.8	8.6	0.0	7.3	10.8	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	58.4	47.0	1.5	42.2	57.6	1.2	9.8	8.6	0.0	7.3	10.8	1.4
Queue Length 50th (ft)	79	8	0	24	17	0	14	188	0	2	313	0
Queue Length 95th (ft)	117	26	0	52	44	0	m21	182	m0	10	441	29
Internal Link Dist (ft)		333			407			398			517	
Turn Bay Length (ft)	150		150	250		200	425			350		350
Base Capacity (vph)	424	374	385	178	279	349	164	2453	1132	397	2477	1179
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.49	0.03	0.10	0.21	0.08	0.08	0.20	0.35	0.01	0.03	0.61	0.22

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

Queues

1: Marksheffel Rd & Meadowbrook Pkwy



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	250	11	49	22	16	33	43	1435	71	38	1027	217
v/c Ratio	0.62	0.05	0.19	0.14	0.16	0.16	0.13	0.56	0.06	0.20	0.41	0.18
Control Delay	57.3	45.7	3.7	39.4	56.9	1.6	7.5	12.7	1.2	11.3	8.4	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	45.7	3.7	39.4	56.9	1.6	7.5	12.7	1.2	11.3	8.4	1.4
Queue Length 50th (ft)	96	8	0	14	12	0	16	328	3	10	170	0
Queue Length 95th (ft)	135	25	10	35	35	0	m23	285	m11	33	246	27
Internal Link Dist (ft)		333			407			398			517	
Turn Bay Length (ft)	150		150	250		200	425			350		350
Base Capacity (vph)	514	434	435	179	279	349	334	2551	1176	186	2502	1180
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.49	0.03	0.11	0.12	0.06	0.09	0.13	0.56	0.06	0.20	0.41	0.18

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

Queues

2040 Total AM.syn

09/09/2020

1: Marksheffel Rd & Meadowbrook Pkwy



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	223	11	43	49	27	33	38	1022	22	11	1788	299
v/c Ratio	0.64	0.06	0.19	0.26	0.24	0.19	0.40	0.43	0.02	0.04	0.75	0.26
Control Delay	59.8	47.7	2.4	41.0	58.2	2.3	27.4	9.9	1.2	7.6	15.0	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	59.8	47.7	2.4	41.0	58.2	2.3	27.4	9.9	1.2	7.6	15.0	1.4
Queue Length 50th (ft)	86	8	0	31	20	0	12	175	0	3	444	0
Queue Length 95th (ft)	126	26	4	63	51	0	m19	216	m1	10	600	30
Internal Link Dist (ft)		333			407			398			517	
Turn Bay Length (ft)	150		150	250		200	425			350		350
Base Capacity (vph)	397	345	362	204	279	310	96	2373	1085	313	2395	1160
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.56	0.03	0.12	0.24	0.10	0.11	0.40	0.43	0.02	0.04	0.75	0.26

Intersection Summary


m Volume for 95th percentile queue is metered by upstream signal.

Queues

2040 Total PM.syn

1: Marksheffel Rd & Meadowbrook Pkwy

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	283	16	60	22	16	43	49	1685	82	49	1196	245
v/c Ratio	0.69	0.06	0.20	0.13	0.16	0.26	0.19	0.68	0.07	0.43	0.49	0.21
Control Delay	59.8	46.3	5.9	38.5	56.9	4.3	7.8	12.5	2.5	24.8	10.0	1.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	59.8	46.3	5.9	38.5	56.9	4.3	7.8	12.5	2.5	24.8	10.0	1.4
Queue Length 50th (ft)	109	11	0	14	12	0	16	295	9	16	221	0
Queue Length 95th (ft)	155	33	22	35	35	4	m19	m322	m12	66	291	27
Internal Link Dist (ft)		333			407			398			517	
Turn Bay Length (ft)	150		150	250		200	425			350		350
Base Capacity (vph)	457	376	388	211	279	310	252	2472	1130	113	2425	1158
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.62	0.04	0.15	0.10	0.06	0.14	0.19	0.68	0.07	0.43	0.49	0.21

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

Queues
2: US-24 & Marksheffel Rd

2025 Total AM.syn
09/09/2020




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	11	812	715	5	549	87	344	527	210	319	1144	21
v/c Ratio	0.11	0.82	0.47	0.06	0.58	0.06	0.73	0.42	0.14	0.63	0.87	0.01
Control Delay	44.2	40.1	1.4	56.2	38.6	0.1	46.6	58.8	0.2	21.1	44.3	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	44.2	40.1	1.4	56.2	38.6	0.1	46.6	58.8	0.2	21.1	44.3	0.0
Queue Length 50th (ft)	8	292	4	3	195	0	147	228	0	116	423	0
Queue Length 95th (ft)	m11	273	17	m16	m206	m0	187	288	0	228	#750	0
Internal Link Dist (ft)		711			1080			2518			924	
Turn Bay Length (ft)	375			300		375	1000		575	1000		700
Base Capacity (vph)	104	1106	1524	78	1139	1568	552	1266	1455	559	1314	1553
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.11	0.73	0.47	0.06	0.48	0.06	0.62	0.42	0.14	0.57	0.87	0.01

Intersection Summary

- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.
- m Volume for 95th percentile queue is metered by upstream signal.

Queues
2: US-24 & Marksheffel Rd

2025 Total PM.syn
09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	16	658	446	16	870	201	557	1010	314	185	527	16
v/c Ratio	0.18	0.65	0.28	0.12	0.79	0.13	0.78	0.83	0.20	0.61	0.56	0.01
Control Delay	50.2	38.8	0.4	52.5	53.6	0.1	26.7	49.8	0.0	40.3	43.5	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	50.2	38.8	0.4	52.5	53.6	0.1	26.7	49.8	0.0	40.3	43.5	0.0
Queue Length 50th (ft)	12	187	0	11	322	0	182	443	0	65	173	0
Queue Length 95th (ft)	m31	260	0	m14	m326	m0	m206	m393	m0	#347	#401	0
Internal Link Dist (ft)		711			1080			2518			924	
Turn Bay Length (ft)	375			300		375	1000		575	1000		700
Base Capacity (vph)	88	1305	1568	137	1327	1583	972	1212	1583	304	946	1568
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.18	0.50	0.28	0.12	0.66	0.13	0.57	0.83	0.20	0.61	0.56	0.01

Intersection Summary


- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.
- m Volume for 95th percentile queue is metered by upstream signal.

Queues

2040 Total AM Improved.syn

2: US-24 & Marksheffel Rd

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT
Lane Group Flow (vph)	16	946	849	5	636	98	409	834	372	1378
v/c Ratio	0.15	0.84	0.56	0.06	0.62	0.06	0.78	0.65	0.81	0.86
Control Delay	54.4	41.5	2.1	57.4	42.5	0.1	59.0	40.3	39.6	46.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.4	41.5	2.1	57.4	42.5	0.1	59.0	40.3	39.6	46.0
Queue Length 50th (ft)	11	239	9	3	206	0	156	198	187	364
Queue Length 95th (ft)	m14	365	24	m7	330	m0	210	#309	#406	#608
Internal Link Dist (ft)		711			1080			2518		924
Turn Bay Length (ft)	375			300		375	1000		1000	
Base Capacity (vph)	104	1211	1524	78	1212	1568	582	1274	476	1599
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.15	0.78	0.56	0.06	0.52	0.06	0.70	0.65	0.78	0.86

Intersection Summary

95th percentile volume exceeds capacity, queue may be longer.


Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.

Queues
2: US-24 & Marksheffel Rd

2040 Total PM Improved.syn

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	SBL	SBT
Lane Group Flow (vph)	22	755	527	16	1016	234	660	1510	207	647
v/c Ratio	0.24	0.61	0.34	0.11	0.80	0.15	0.81	0.99	0.77	0.74
Control Delay	50.6	36.0	0.5	42.3	29.1	0.2	29.2	58.4	54.9	54.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	50.6	36.0	0.5	42.3	29.1	0.2	29.2	58.4	54.9	54.2
Queue Length 50th (ft)	16	129	0	11	253	0	283	~523	111	~189
Queue Length 95th (ft)	m34	282	0	m27	296	0	m277	m#528	#336	#406
Internal Link Dist (ft)		711			1080			2518		924
Turn Bay Length (ft)	375			300		375	1000		1000	
Base Capacity (vph)	90	1470	1568	140	1442	1583	1001	1520	270	873
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.24	0.51	0.34	0.11	0.70	0.15	0.66	0.99	0.77	0.74

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.
- m Volume for 95th percentile queue is metered by upstream signal.

Queues

4: US-24 & Newt Dr/SH-94



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	54	125	609	799	130	5	500	979	541	5	1771
v/c Ratio	0.42	0.69	0.40	1.08	0.13	0.00	1.02	0.45	0.37	0.02	1.05
Control Delay	80.2	84.7	0.8	110.6	39.2	0.0	107.2	29.1	0.7	19.4	83.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	80.2	84.7	0.8	110.6	39.2	0.0	107.2	29.1	0.7	19.4	83.0
Queue Length 50th (ft)	27	120	0	~448	50	0	~266	238	0	2	~697
Queue Length 95th (ft)	52	190	0	#578	76	0	#383	289	0	10	#823
Internal Link Dist (ft)		610			2306			785			727
Turn Bay Length (ft)	375			475		475	900		600	800	
Base Capacity (vph)	131	217	1538	740	1063	1553	490	2157	1468	202	1686
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.41	0.58	0.40	1.08	0.12	0.00	1.02	0.45	0.37	0.02	1.05

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues

2025 Total PM Improved.syn

4: US-24 & Newt Dr/SH-94

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	60	120	571	707	120	11	536	1828	552	5	951
v/c Ratio	0.32	0.59	0.36	0.93	0.11	0.01	0.65	0.92	0.35	0.04	0.97
Control Delay	69.3	57.6	0.6	61.0	26.7	0.0	45.4	43.4	0.6	16.4	60.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	69.3	57.6	0.6	61.0	26.7	0.0	45.4	43.4	0.6	16.4	60.2
Queue Length 50th (ft)	24	91	0	231	26	0	193	489	0	3	258
Queue Length 95th (ft)	48	142	0	#380	49	m0	254	#653	0	m4	#438
Internal Link Dist (ft)		610			2306			785			727
Turn Bay Length (ft)	375			475		475	900		600	800	
Base Capacity (vph)	197	279	1583	779	1132	1568	821	1994	1568	138	985
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.30	0.43	0.36	0.91	0.11	0.01	0.65	0.92	0.35	0.04	0.97

Intersection Summary

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.

Queues
4: US-24 & Newt Dr/SH-94

2040 Total AM.syn
09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	54	130	647	886	141	5	526	1124	608	10	2104
v/c Ratio	0.33	0.70	0.42	1.23	0.14	0.00	1.28	0.51	0.41	0.06	1.15
Control Delay	74.4	83.9	0.8	165.1	40.9	0.0	193.5	29.7	0.9	19.8	118.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	74.4	83.9	0.8	165.1	40.9	0.0	193.5	29.7	0.9	19.8	118.3
Queue Length 50th (ft)	26	125	0	~551	55	0	~335	281	0	4	~894
Queue Length 95th (ft)	51	195	0	#683	83	0	#454	339	0	15	#1025
Internal Link Dist (ft)		610			2306			785			727
Turn Bay Length (ft)	375			475		475	900		600	800	
Base Capacity (vph)	177	230	1538	718	1023	1553	411	2188	1468	180	1822
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.31	0.57	0.42	1.23	0.14	0.00	1.28	0.51	0.41	0.06	1.15

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues
4: US-24 & Newt Dr/SH-94

2040 Total PM.syn
09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	60	130	614	766	125	11	563	2115	604	5	1119
v/c Ratio	0.28	0.62	0.39	0.98	0.12	0.01	0.71	1.08	0.39	0.04	1.14
Control Delay	67.4	58.6	0.7	57.1	23.3	0.0	48.0	83.0	0.7	14.4	107.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	67.4	58.6	0.7	57.1	23.3	0.0	48.0	83.0	0.7	14.4	107.0
Queue Length 50th (ft)	24	97	0	263	29	0	207	~673	0	1	~382
Queue Length 95th (ft)	m45	152	0	m#298	m44	m0	271	#823	0	m3	#533
Internal Link Dist (ft)		610			2306			785			727
Turn Bay Length (ft)	375			475		475	900		600	800	
Base Capacity (vph)	254	279	1583	779	1104	1568	793	1951	1568	138	984
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.24	0.47	0.39	0.98	0.11	0.01	0.71	1.08	0.39	0.04	1.14

Intersection Summary


- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.
- m Volume for 95th percentile queue is metered by upstream signal.



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	179	359	98	33	402	152	98	348	22	353	609	353
v/c Ratio	1.10	0.64	0.17	0.17	0.70	0.26	0.25	0.28	0.03	0.57	0.38	0.23
Control Delay	133.0	35.1	0.6	26.9	41.3	4.5	18.0	32.5	0.1	14.1	16.8	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	133.0	35.1	0.6	26.9	41.3	4.5	18.0	32.5	0.1	14.1	16.8	0.3
Queue Length 50th (ft)	~151	183	0	18	269	0	33	100	0	92	102	0
Queue Length 95th (ft)	#261	215	0	38	320	39	76	183	0	155	188	0
Internal Link Dist (ft)		2306			1405			5693			958	
Turn Bay Length (ft)	300		250	225		250	375		400	400		400
Base Capacity (vph)	219	762	732	267	776	746	413	1245	649	695	1584	1568
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.82	0.47	0.13	0.12	0.52	0.20	0.24	0.28	0.03	0.51	0.38	0.23

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	272	397	141	49	473	489	125	995	27	232	660	366
v/c Ratio	1.03	0.49	0.18	0.15	0.58	0.60	0.43	0.88	0.05	1.17	0.58	0.24
Control Delay	93.3	22.6	2.1	21.7	28.7	16.1	24.2	48.5	0.2	141.4	33.0	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	93.3	22.6	2.1	21.7	28.7	16.1	24.2	48.5	0.2	141.4	33.0	0.4
Queue Length 50th (ft)	~225	176	0	22	269	146	56	382	0	~165	249	0
Queue Length 95th (ft)	#402	296	21	50	379	257	95	#480	0	#325	290	0
Internal Link Dist (ft)		2306			1405			5693			958	
Turn Bay Length (ft)	300		250	225		250	375		400	400		400
Base Capacity (vph)	265	814	771	325	814	820	302	1135	566	198	1129	1553
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	1.03	0.49	0.18	0.15	0.58	0.60	0.41	0.88	0.05	1.17	0.58	0.24

Intersection Summary


- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues

2040 Total AM Improved.syn

5: Marksheffel Rd & SH-94

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	179	413	109	43	467	168	109	408	27	408	717	353
v/c Ratio	0.62	0.55	0.15	0.16	0.88	0.29	0.40	0.55	0.06	0.81	0.60	0.46
Control Delay	62.4	28.4	1.5	30.6	57.8	3.9	26.8	47.4	0.2	43.6	33.5	5.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	62.4	28.4	1.5	30.6	57.8	3.9	26.8	47.4	0.2	43.6	33.5	5.2
Queue Length 50th (ft)	69	225	0	24	333	0	49	160	0	193	226	18
Queue Length 95th (ft)	108	311	14	52	459	36	89	#220	0	#348	212	52
Internal Link Dist (ft)		2306			1405			5693			958	
Turn Bay Length (ft)	300		250	225		250	375		400	400		400
Base Capacity (vph)	310	820	777	310	597	635	286	747	480	533	1204	770
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.58	0.50	0.14	0.14	0.78	0.26	0.38	0.55	0.06	0.77	0.60	0.46

Intersection Summary

95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues

2040 Total PM Improved.syn

5: Marksheffel Rd & SH-94

09/09/2020



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group Flow (vph)	272	462	158	54	549	565	141	1174	33	263	778	366
v/c Ratio	0.99	0.64	0.22	0.25	1.08	0.99	0.47	0.92	0.05	1.24	0.62	0.24
Control Delay	110.4	30.2	3.8	37.8	105.7	64.2	21.7	49.2	0.1	168.2	30.2	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	110.4	30.2	3.8	37.8	105.7	64.2	21.7	49.2	0.1	168.2	30.2	0.3
Queue Length 50th (ft)	111	236	0	33	-476	314	57	454	0	-196	224	0
Queue Length 95th (ft)	#203	353	34	70	#694	#555	95	#591	0	#372	267	0
Internal Link Dist (ft)		2306			1405			5693			958	
Turn Bay Length (ft)	300		250	225		250	375		400	400		400
Base Capacity (vph)	274	725	712	214	507	571	325	1276	652	212	1263	1553
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.99	0.64	0.22	0.25	1.08	0.99	0.43	0.92	0.05	1.24	0.62	0.24

Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

6: Marksheffel Rd & North Full Access

09/09/2020



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	54	109	92	1516	880	212
v/c Ratio	0.41	0.50	0.18	0.50	0.29	0.15
Control Delay	61.2	17.4	4.7	7.0	2.7	1.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.2	17.4	4.7	7.0	2.7	1.1
Queue Length 50th (ft)	41	0	13	161	65	6
Queue Length 95th (ft)	81	55	55	555	113	29
Internal Link Dist (ft)	194			890	666	
Turn Bay Length (ft)			150			
Base Capacity (vph)	331	385	501	3007	3007	1377
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.16	0.28	0.18	0.50	0.29	0.15

Intersection Summary

6: Marksheffel Rd & North Full Access

09/09/2020



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	60	120	136	1043	1114	321
v/c Ratio	0.43	0.51	0.35	0.35	0.37	0.23
Control Delay	61.6	16.9	11.1	6.4	3.7	1.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.6	16.9	11.1	6.4	3.7	1.3
Queue Length 50th (ft)	45	0	33	134	84	4
Queue Length 95th (ft)	88	57	133	324	173	45
Internal Link Dist (ft)	194			890	666	
Turn Bay Length (ft)			150			150
Base Capacity (vph)	302	369	386	2995	2995	1389
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.20	0.33	0.35	0.35	0.37	0.23

Intersection Summary

6: Marksheffel Rd & North Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	54	109	92	1793	1022	212
v/c Ratio	0.41	0.50	0.21	0.60	0.34	0.15
Control Delay	61.2	17.4	1.7	2.7	7.7	3.2
Queue Delay	0.0	0.0	0.0	0.2	0.0	0.0
Total Delay	61.2	17.4	1.7	2.9	7.7	3.2
Queue Length 50th (ft)	41	0	9	174	224	33
Queue Length 95th (ft)	81	55	m0	3	m243	m60
Internal Link Dist (ft)	194			890	666	
Turn Bay Length (ft)			150			
Base Capacity (vph)	287	348	430	3007	3007	1377
Starvation Cap Reductn	0	0	0	346	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.19	0.31	0.21	0.67	0.34	0.15

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

6: Marksheffel Rd & North Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	60	120	136	1228	1283	321
v/c Ratio	0.43	0.51	0.43	0.41	0.43	0.23
Control Delay	61.6	16.9	12.1	6.2	5.4	2.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	61.6	16.9	12.1	6.2	5.4	2.0
Queue Length 50th (ft)	45	0	35	165	205	31
Queue Length 95th (ft)	88	57	98	350	290	m58
Internal Link Dist (ft)	194			890	666	
Turn Bay Length (ft)			150			150
Base Capacity (vph)	272	345	318	2995	2995	1389
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.22	0.35	0.43	0.41	0.43	0.23

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

7: Marksheffel Rd & South Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	54	321	179	1554	870	120
v/c Ratio	0.36	0.75	0.34	0.52	0.33	0.10
Control Delay	57.1	17.2	4.7	5.6	2.5	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.1	17.2	4.7	5.6	2.5	0.3
Queue Length 50th (ft)	41	0	15	102	40	0
Queue Length 95th (ft)	77	86	m76	411	65	4
Internal Link Dist (ft)	256			958	890	
Turn Bay Length (ft)			150			150
Base Capacity (vph)	715	831	610	2976	2611	1190
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.08	0.39	0.29	0.52	0.33	0.10

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

7: Marksheffel Rd & South Full Access

09/09/2020



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	60	348	272	1120	1049	185
v/c Ratio	0.39	0.76	0.54	0.38	0.44	0.17
Control Delay	57.3	16.8	3.7	2.1	4.2	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	16.8	3.7	2.1	4.2	0.4
Queue Length 50th (ft)	45	0	10	7	61	1
Queue Length 95th (ft)	83	89	m51	m198	177	1
Internal Link Dist (ft)	256			958	890	
Turn Bay Length (ft)			150			150
Base Capacity (vph)	656	805	618	2963	2394	1104
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.09	0.43	0.44	0.38	0.44	0.17

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

7: Marksheffel Rd & South Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	54	321	179	1832	1011	120
v/c Ratio	0.30	0.81	0.39	0.63	0.40	0.10
Control Delay	51.0	27.4	5.7	5.2	3.6	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.0	27.4	5.7	5.2	3.6	0.2
Queue Length 50th (ft)	40	45	14	106	54	0
Queue Length 95th (ft)	73	138	m43	261	82	0
Internal Link Dist (ft)	256			958	890	
Turn Bay Length (ft)			150			150
Base Capacity (vph)	538	662	514	2907	2533	1158
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.10	0.48	0.35	0.63	0.40	0.10

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

7: Marksheffel Rd & South Full Access



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Group Flow (vph)	60	348	272	1304	1217	185
v/c Ratio	0.39	0.76	0.59	0.44	0.52	0.17
Control Delay	57.5	16.8	10.3	5.4	4.8	0.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.5	16.8	10.3	5.4	4.8	0.6
Queue Length 50th (ft)	45	0	90	158	66	0
Queue Length 95th (ft)	84	89	m92	m229	281	11
Internal Link Dist (ft)	256			958	890	
Turn Bay Length (ft)			150			150
Base Capacity (vph)	553	733	554	2965	2357	1087
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.11	0.47	0.49	0.44	0.52	0.17

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

APPENDIX G

Conceptual Site Plan



WARRENT FOR SIGNAL

MEADOWBROOK PARK

CROSSROADS NORTH

CROSSROADS MIX USE

EPC DEIVATION REQUEST FOR RI/RO

WARRENT FOR SIGNAL

REGAN RANCH SITE




Clubhouse / Leasing
 • Pool/Primary Amenity

Primary Entry
 • Gated Entry

56-Plex Building
 • 4 Stories
 • Elevator Served
 • Attached Garages

Dog Run




Concept Plan 2 - 4 Stories

CROSSROADS APARTMENTS

COLORADO SPRINGS, CO

4.22.2020





SITE DATA					
	USE	SITE AREA	BUILDING AREA	PARKING	SITE UTILIZATION
A	HOME IMPROVEMENT	11.40 AC	127,000 SF	425	25.6%
B	FURNITURE	9.33 AC	114,000 SF	350	23.0%
C	THEATER	8.00 AC	52,000 SF	388	14.92%
D	RESTAURANT	3.00 AC	11,000 SF	132	8.42%
E	GAS/CONVENIENCE	2.00 AC	5,000 SF	27	5.74%
F	FAST FOOD	1.35 AC	3,800 SF	41	6.46%
G	TIRE CENTER	1.30 AC	7,200 SF	26	12.71%
H	FAST FOOD	1.25 AC	2,800 SF	45	5.2%
	UNASSIGNED	2.74 AC	-	-	-
	ROAD R.O.W	.76 AC	-	-	-
	W.Q. DETENTION	2.50 AC	-	-	-
	TOTAL	44.68 AC	322,800 SF	1,434	102.05%

COLORADO HWY 94
 CDOT LICENSE REQUEST
 FENCE

U.S. HIGHWAY 24

N. MARKSHEFFEL RD

796,318 sf

W.Q. DETENTION

W.Q. DETENTION



0 50 100 200
 SCALE: 1" = 100'



CROSSROADS NORTH - CONCEPT PLAN

Kimley»Horn



RESIDENTIAL

Meadowbrook Parkway


US HWY 24 EXPRESSWAY

CIRCLE K

POND

GYM/ ROCK

3.41 AC



STAMP:

REV #	REVISIONS	DATE
1		
2		
3		
4		
5		
6		

DESIGNED	STB	09.06.19
DRAWN	STB	09.06.19
CHECKED	JH	09.06.19
PROJECT NUMBER:	383204	
SCALE:	AS NOTED	

TIS V_1 engr comments.pdf Markup Summary

dsdlaforce (13)

Add PCD File No. P208 and SP2011

Subject: Text Box
Page Label: 1
Lock: Unlocked
Author: dsdlaforce
Date: 1/20/2021 4:24:17 PM
Status:
Color: ■
Layer:
Space:

Add PCD File No. P208 and SP2011

Subject: Callout
Page Label: 6
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 10:24:35 AM
Status:
Color: ■
Layer:
Space:

1. Provide roundabout analysis. Current policy is to design per the Wisconsin DOT roundabout design criteria.
2. Provide autoturn analysis of the intersection. Per ECM Table 2-7 design vehicle is WB-50.
3. Provide table of critical design parameters.
4. Provide the rodel model report.
5. Provide the fastest path analysis/exhibit.
6. Provide the entry angle exhibit.

Subject: Text Box
Page Label: 1
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 10:42:50 AM
Status:
Color: ■
Layer:
Space:

Notice: This review specifically focused on Cross Roads Mixed Use. Similar approach to the review of the TIS under the preliminary plan applications for the Crossroads North and Meadowbrook Park.

Subject: Callout
Page Label: 38
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 10:50:57 AM
Status:
Color: ■
Layer:
Space:

for clarity revise sentence. Specify the total proposed access for Mixed Use and Meadowbrook park separately.

Subject: Highlight
Page Label: 38
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 10:51:14 AM
Status:
Color: ■
Layer:
Space:

d four project accesses along the east side of Meadowbrook Parkway for Meadowbrook Park and Crossroads Mix Use.

right ingress turning volume of 25 vehicles per hour is recommended that a southbound right turn lane the volumes being 295 vehicles per hour at the n south access. which project?
With the recommended lane configurations and project accesses are expected to operate accept hours in the 2025 and 2040 horizons with exit accesses along Marshfield Road. A four-hour performed at both accesses along Marshfield Ro

Subject: Callout
Page Label: 38
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:01:02 AM
Status:
Color: ■
Layer:
Space:

which project?




Subject: Callout
Page Label: 38
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:01:31 AM
Status:
Color: ■
Layer:
Space:

Since the TIS is provided for three separate projects, Staff is requesting you consider formatting the project in a way that organizes the analysis per project for ease in review. Right now the paragraphs are constantly moving from one area to another making it difficult to follow recommendations and analysis.

One recommendation using section 5.3 as an example is to provide a subsection for each project based on the individual project site.




Subject: Image
Page Label: 23
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:09:33 AM
Status:
Color: ■
Layer:
Space:



Subject: Text Box
Page Label: 23
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:10:29 AM
Status:
Color: ■
Layer:
Space:

Provide trip distribution analysis for the proposed access to Crossroads Mixed Use and provide recommendations for the intersection configuration and auxiliary lanes.

State/list ECM criteria for stacking, storage, and taper for every affected auxiliary lane and access and state whether this access can be met. If it can't be met, state the required modification so it can be met (a deviation request may be required if an alternative to the criteria is proposed)



Pinpointed_Mountainhawk

Subject: Text Box
Page Label: 1
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:15:24 AM
Status:
Color: ■
Layer:
Space:

Provide recommendations for the internal private road classification/cross section Crossroads Mixed Use. The trip generation estimate is 13,076 ADT while the preliminary plan showed a local road cross section which has a design ADT of 3,000.




Subject: Callout
Page Label: 22
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:22:21 AM
Status:
Color: ■
Layer:
Space:

Based on the Jan 14 meeting, the applicant stated Reagan Ranch TIS was accounted for in this study. As such, update the narrative to identify other studies/development that was incorporated in this study.



Subject: Text Box
Page Label: 40
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:25:47 AM
Status:
Color: ■
Layer:
Space:

provide an exhibit showing the sight distance/line-of-sight for the proposed accesses to the mixed use.



Subject: Text Box
Page Label: 1
Lock: Unlocked
Author: dsdlaforce
Date: 1/22/2021 11:29:31 AM
Status:
Color: ■
Layer:
Space:

What is the intent regarding the continuation of Meadowbrook Parkway to the west?