

T--Mobile--

2323 DELGANY STREET DENVER, CO 80216

CROWN
CASTLE
200 SPECTRUM CENTER DRIVE,
SUITE 1700 & 1800

IRVINE, CA 92618



TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX, AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE
SITE NUMBER: **DN06123A**(SPRINT RETAIN)

BU #: 877092 F3/FILL-IN/COLORADO SPGS/CSP18

125 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

	ISSUED FOR:									
REV	DATE	DRWN	DESCRIPTION	DES./QA						
5	09/12/22	GBP	CONSTRUCTION	JFJ						
6	09/27/22	DRC	CONSTRUCTION	JFJ						
7	11/03/22	KDP	CONSTRUCTION	JFJ						
8	02/02/23	DRS	CONSTRUCTION	JFJ						
9	02/16/23	SSO	CONSTRUCTION	JFJ						



02/16/23

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

9



SITE NUMBER: **DN**06123A **DN63XC091** SITE NAME:

SITE TYPE: SELF SUPPORT

69'-7'' TOWER HEIGHT:

BUSINESS UNIT #: 877092

125 NORTH GATE RD SITE ADDRESS: COLORADO SPRINGS, CO 80921

EL PASO COUNTY:

T-MOBILE PROJECT: SPRINT RETAIN

SITE INFORMATION

CROWN CASTLE USA INC. F3/FILL-IN/COLORADO SPGS/CSP18 SITE NAME:

SITE ADDRESS: 125 NORTH GATE RD COLORADO SPRINGS, CO 80921

COUNTY: EL PASO 6207200017 MAP/PARCEL #: AREA OF CONSTRUCTION: **EXISTING** 39° 01' 30.72" LATITUDE: -104° 49' 38.65" LONGITUDE: NAD83 LAT/LONG TYPE: 6,788 FT GROUND ELEVATION:

CURRENT ZONING: RR-5 **JURISDICTION:** EL PASO COUNTY

OCCUPANCY CLASSIFICATION: U

TYPE OF CONSTRUCTION: A.D.A. COMPLIANCE:

FACILITY IS UNMANNED AND NOT FOR **HUMAN HABITATION**

WESTERN MUSEUM OF MINING INDUSTRY PROPERTY OWNER:

125 NORTH GATE RD

COLORADO SPRINGS CO, 80921

TOWER OWNER: GLOBAL SIGNAL ACQUISITIONS II LLC 2000 CORPORATE DRIVE

CANONSBURG, PA 15317

CARRIER/APPLICANT: T-MOBILE

A&E FIRM:

2323 DELGANY STREET DENVER, CO 80216

ELECTRIC PROVIDER: MOUNTAIN VIEW ELECTRIC

TELCO PROVIDER: CENTURYLINK

CHARITABLE

RESIDENTIAL CHARITABLE

DRAWING INDEX

SHEET#	SHEET DESCRIPTION
T-1	TITLE SHEET
T-2	GENERAL NOTES
C-1.1	OVERALL SITE PLAN
C-1.2	EXISTING EQUIPMENT LAYOUT
C-1.3	NEW EQUIPMENT LAYOUT
C-2	TOWER ELEVATIONS
C-3	ANTENNA PLANS
C-4	FINAL EQUIPMENT SCHEDULE
C-5.1	EQUIPMENT SPECS
C-5.2	EQUIPMENT SPECS
C-5.3	EQUIPMENT SPECS
E-1	ELECTRICAL DETAILS
E-2	ELECTRICAL DETAILS
G-1	GROUNDING DETAILS
ATTACHED	RF CABLING DIAGRAM

ALL DRAWINGS CONTAINED HEREIN ARE FORMATTED FOR FULL SIZE. CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.



CALL COLORADO ONE CALL (800) 922-1987 CALL 3 WORKING DAYS BEFORE YOU DIG!



THE PURPOSE OF THIS PROJECT IS TO ENHANCE BROADBAND CONNECTIVITY AND CAPACITY TO THE EXISTING ELIGIBLE

• REMOVE UNUSED EQUIPMENT


- REMOVE EXISTING CONCEALMENT

- ADD (2) HCS 2.0 PART 1 PENDANTS
- ADD (2) HCS 2.0 HYBRID CABLES
- ADD (3) PV-SFA10-B-R1 SECTOR MOUNT

GROUND SCOPE OF WORK:

- REMOVE UNUSED EQUIPMENT
- ADD (2) ASIBs
- ADD (2) ASIKs
- ADD (3) ABIAs
- ADD (3) ABICs
- ADD (1) GENERIC 600A CABINET
- ADD (1) GENERIC BATTERY CABINET FOR 600A SSC
- ADD (1) VOLTAGE BOOSTER
- ADD (1) EXTRA BOOSTER AMPLIFIER
- ADD (2) HCS 2.0 JUNCTION BOXES

LOCATION MAP



SITE PHOTO





T---Mobile--

2323 DELGANY STREET DENVER, CO 80216

IRVINE, CA 92618

CROWN

CASTLE

F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

	ISSUED FOR:									
REV	DATE	DRWN	DESCRIPTION	DES./QA						
0	05/05/21	VBP	CONSTRUCTION	JFJ						
1	05/24/21	JLB	CONSTRUCTION	JFJ						
2	06/21/21	AOW	CONSTRUCTION	JFJ						
3	09/16/21	GVM	CONSTRUCTION	JFJ						
4	04/14/22	PSS	CONSTRUCTION	JFJ						

PROJECT TEAM PROJECT DESCRIPTION

TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST. STE 9

PHOENIX, AZ 85040 OFFICE: (480) 285-0036

CROWN CASTLE USA INC. 200 SPECTRUM CENTER DRIVE, SUITE 1700 & 1800 DISTRICT CONTACTS: IRVINE, CA 92618

> BRYCE NORTHCUTT - PROJECT MANAGER BRYCENORTHCUTT@CROWNCASTLE.COM

JONATHAN BAIN - CONSTRUCTION MANAGER JONATHANBAIN@CROWNCASTLE.COM

#208013928, TOG W/ THAT PT DESC BY REC # 208013927

29.000 26.63 Acres 6.950

Legal Description: LOT 1 BLK 1 MINING MUSEUM SUB NO 1, TOG WIH VAC OLD NORTH GATE RD ADJ BY REC #208007172, EX THAT PT CONV BY REC

WIRELESS FACILITY.

TOWER SCOPE OF WORK:

- ADD (3) FFVV-65C-R3-V1 ANTENNAS, (1) PER SECTOR
- ADD (3) AEHC ANTENNAS, (1) PER SECTOR
- ADD (3) RADIO AHLOA, (1) PER SECTOR
- ADD (3) RADIO AHFIG, (1) PER SECTOR

- ADD (9) SITE PRO 1 R5-LL (8') MOUNT PIPES

- ADD (1) FSMF
- ADD (6) ABILs
- ADD (2) AMIAs

APPLICABLE CODES/REFERENCE DOCUMENTS

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE CODE BUILDING 2018 IBC **MECHANICAL** 2018 IMC ELECTRICAL 2017 NEC

REFERENCE DOCUMENTS:

STRUCTURAL ANALYSIS: B+T GROUP DATED: 04/06/2022 MOUNT ANALYSIS: INFINIGY DATED: 03/21/2022 RFDS REVISION: 1 DATED: 01/25/2021 ORDER ID: 608670

REVISION: 0

PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE CROWN NOC AT (800) 788-7011 & CROWN CONSTRUCTION MANAGER.



04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, JNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

CROWN CASTLE USA INC. SITE ACTIVITY REQUIREMENTS:

- 1. NOTICE TO PROCEED— NO WORK SHALL COMMENCE PRIOR TO CROWN CASTLE USA INC. WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE CROWN CASTLE USA INC. NOC AT 800-788-7011 & THE CROWN CASTLE USA INC. CONSTRUCTION MANAGER.
- 2. "LOOK UP" CROWN CASTLE USA INC. SAFETY CLIMB REQUIREMENT
- THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR CROWN CASTLE USA INC. POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
- PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS
- ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND CROWN CASTLE USA INC. STANDARD CED-STD-10253, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION)
- 5. ALL SITE WORK TO COMPLY WITH QAS-STD-10068 "INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON CROWN CASTLE USA INC. TOWER SITE," CED-STD-10294 "STANDARD FOR INSTALLATION OF MOUNTS AND APPURTENANCES," AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS.
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS. THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY CROWN CASTLE USA INC. PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES PRIOR TO THE START OF CONSTRUCTION.
- 10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- 11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- 12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY
- 13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF CONTRACTOR, TOWER OWNER, CROWN CASTLE USA INC., AND/OR LOCAL UTILITIES
- 14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- 15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- 16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED JRFACE APPLICATION.
- 17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- 18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- 19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION
- 20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- 22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY: GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION CONTRACTOR:
- CARRIER: T-MOBILE TOWER OWNER: CROWN CASTLE USA INC.
- 2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
- SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSI<mark>ONS AND MEASUREMENTS ON</mark> THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE
- PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CROWN CASTLE
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND CROWN CASTLE PRIOR TO PROCEEDING
- WITH ANY SUCH CHANGE OF INSTALLATION. 11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION AND IS TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN
- DRAWINGS 12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY
- DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF CROWN CASTLE USA INC. 13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

- ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE. 2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED
- TO BE 1000 psf. 3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF
- CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE
- TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
- #4 BARS AND SMALLER... #5 BARS AND LARGER.... ..60 ksi THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE
- ON DRAWINGS: CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH... CONCRETE EXPOSED TO EARTH OR WEATHER:
- #6 BARS AND LARGER ... #5 BARS AND SMALLER1-1/2" CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
- SLAB AND WALLS.... BEAMS AND COLUMNS ..
- 7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

GREENFIELD GROUNDING NOTES:

- ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
- THE CONTRACTOR SHALL PERFORM IEEE FALL—OF—POTENTAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
- THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE
- 4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS
- METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED
- COPPER FOR OUTDOOR BTS. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
- ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
- ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
- USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED. 11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
- 12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS. 13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
- 14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
- 15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
- 16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL. 17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
- 18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
- 19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT
- 20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
- 21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY).

ELECTRICAL INSTALLATION NOTES:

- ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
- CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED
- AND TRIP HAZARDS ARE ELIMINATED.
- 3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC. 4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERYIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
- EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
- ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
- PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS
- 8. ALL TIE WRAPS SHALL BE CUT FLUSH WITH APPROVED CUTTING TOOL TO REMOVE SHARP EDGES ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH
- TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED. 11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS
- OTHERWISE SPECIFIED. 12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP—STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
- 14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE
- 15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR
- EXPOSED INDOOR LOCATIONS
- 16. ELECTRICAL METALLIC TUBING (EMT) OR METAL—CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS. 17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT
- 18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION
- OCCURS OR FLEXIBILITY IS NEEDED. 19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET
- SCREW FITTINGS ARE NOT ACCEPTABLE. 20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND
- 21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS
- (WIREMOLD SPECMATE WIREWAY). 22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
- 23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED
- MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE 24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3R (OR
- METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY—COATED OR NON—CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- 26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED

APWA UNIFORM COLOR CODE:

PROPOSED EXCAVATION

GASEOUS MATERIALS

POTABLE WATER

SLURRY LINES

EMPORARY SURVEY MARKINGS

CONDUIT, AND LIGHTING CABLES

LECTRIC POWER LINES, CABLES,

GAS, OIL, STEAM, PETROLEUM, OR

COMMUNICATION, ALARM OR SIGNAL LINES, CABLES, OR CONDUIT AND TRAFFIC LOOPS

ECLAIMED WATER, IRRIGATION, AND

SEWERS AND DRAIN LINES

- NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS. 27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR CROWN CASTLE USA INC. BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
- 28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY. 29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "T-MOBILE"
- 30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.

COND	CONDUCTOR COLOR CODE							
SYSTEM	CONDUCTOR	COLOR						
	A PHASE	BLACK						
 120/240V, 1Ø	B PHASE	RED						
120/2400, 10	NEUTRAL	WHITE						
	GROUND	GREEN						
	A PHASE	BLACK						
	B PHASE	RED						
120/208V, 3Ø	C PHASE	BLUE						
	NEUTRAL	WHITE						
	GROUND	GREEN						
	A PHASE	BROWN						
	B PHASE	ORANGE OR PURPLE						
277/480V, 3Ø	C PHASE	YELLOW						
	NEUTRAL	GREY						
	GROUND	GREEN						
DC VOLTAGE	POS (+)	RED**						
DO VOLTAGE	NEG (-)	BLACK**						

SEE NEC 210.5(C)(1) AND (2) ** POLARITY MARKED AT TERMINATION

ABBREVIATIONS:

Τ	ANTENNA	
	EXISTING	

FACILITY INTERFACE FRAME GEN GENERATOR GPS GLOBAL POSITIONING SYSTEM

MASTER GROUND BAR

- GSM GLOBAL SYSTEM FOR MOBILE LONG TERM EVOLUTION
- MW MICROWAVE
- NEC NATIONAL ELECTRIC CODE PROPOSED POWER PLANT
- QTY QUANTITY RECT RECTIFIER RBS

MGB

- RADIO BASE STATION RET REMOTE ELECTRIC TILT RFDS RADIO FREQUENCY DATA SHEET
- REMOTE RADIO HEAD RRU REMOTE RADIO UNIT SIAD SMART INTEGRATED DEVICE
- TMA TOWER MOUNTED AMPLIFIER TYP TYPICAL UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
- W.P. WORK POINT

2323 DELGANY STREET DENVER, CO 80216





TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX. AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

		ISSU	ED FOR:	
REV	DATE	DRWN	DESCRIPTION	DES./QA
0	05/05/21	VBP	CONSTRUCTION	JFJ
1	05/24/21	JLB	CONSTRUCTION	JFJ
2	06/21/21	AOW	CONSTRUCTION	JFJ
3	09/16/21	GVM	CONSTRUCTION	JFJ
4	04/14/22	PSS	CONSTRUCTION	JFJ




04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER,

TO ALTER THIS DOCUMENT.


SHEET NUMBER:







SUITE 1700 & 1800 IRVINE, CA 92618



TOWER ENGINEERING PROFESSIONALS
4710 E ELWOOD ST, STE 9
PHOENIX, AZ 85040
OFFICE: (480) 285-0036
www.tepgroup.net

T-MOBILE
SITE NUMBER: **DN06123A**(SPRINT RETAIN)

BU #: 877092 F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

DATE 05/05/21	DRWN VBP	DESCRIPTION CONSTRUCTION	DES./QA
05/05/21	VBP	CONSTRUCTION	ICI
		331,811,631,611	JFJ
05/24/21	JLB	CONSTRUCTION	JFJ
06/21/21	AOW	CONSTRUCTION	JFJ
09/16/21	GVM	CONSTRUCTION	JFJ
04/14/22	PSS	CONSTRUCTION	JFJ
	06/21/21 09/16/21	06/21/21 AOW 09/16/21 GVM	06/21/21 AOW CONSTRUCTION 09/16/21 GVM CONSTRUCTION




04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

4









TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX, AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

	ISSUED FOR:											
REV	DATE	DRWN	DESCRIPTION	DES./QA								
0	05/05/21	VBP	CONSTRUCTION	JFJ								
1	05/24/21	JLB	CONSTRUCTION	JFJ								
2	06/21/21	AOW	CONSTRUCTION	JFJ								
3	09/16/21	GVM	CONSTRUCTION	JFJ								
4	04/14/22	PSS	CONSTRUCTION	JFJ								




04/14/22

REVISION:

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:









TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX, AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

	ISSUED FOR:										
REV	REV DATE		DESCRIPTION	DES./QA							
0	05/05/21	VBP	CONSTRUCTION	JFJ							
1	05/24/21	JLB	CONSTRUCTION	JFJ							
2	06/21/21	AOW	CONSTRUCTION	JFJ							
3	09/16/21	GVM	CONSTRUCTION	JFJ							
4	04/14/22	PSS	CONSTRUCTION	JFJ							




04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:









TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX, AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE
SITE NUMBER: **DN06123A**(SPRINT RETAIN)

BU #: 877092 F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

ISSUED FOR:									
DATE	DRWN	DESCRIPTION	DES./QA						
05/05/21	VBP	CONSTRUCTION	JFJ						
05/24/21	JLB	CONSTRUCTION	JFJ						
06/21/21	AOW	CONSTRUCTION	JFJ						
09/16/21	GVM	CONSTRUCTION	JFJ						
04/14/22	PSS	CONSTRUCTION	JFJ						
	05/05/21 05/24/21 06/21/21 09/16/21	DATE DRWN 05/05/21 VBP 05/24/21 JLB 06/21/21 AOW 09/16/21 GVM	DATE DRWN DESCRIPTION 05/05/21 VBP CONSTRUCTION 05/24/21 JLB CONSTRUCTION 06/21/21 AOW CONSTRUCTION 09/16/21 GVM CONSTRUCTION						




04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

C-2





200 SPECTRUM CENTER DRIVE, SUITE 1700 & 1800 IRVINE, CA 92618



TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX, AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

ISSUED FOR:									
REV	DATE	DRWN	DESCRIPTION	DES./QA					
0	05/05/21	VBP	CONSTRUCTION	JFJ					
1	05/24/21	JLB	CONSTRUCTION	JFJ					
2	06/21/21	AOW	CONSTRUCTION	JFJ					
3	09/16/21	GVM	CONSTRUCTION	JFJ					
4	04/14/22	PSS	CONSTRUCTION	JFJ					



04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

						FINA	AL EQ	UIF	PMENT S	SCHEE)UL	 .E						
ALPHA									H CURRE									
ALITIA		ANTENNA				RADIO			DIPLEXER			ТМА		SURGE PROTECTION		CABLI	ES	
POSITION	TECH.	STATUS/MANUFACTURER MODEL	AZIMUTH	RAD CENTER	QTY.	STATUS/MODEL	LOCATION	QTY.	STATUS	LOCATION	QTY.	STATUS	QTY.	STATUS/MODEL	QTY.	STATUS/TYPE	SIZE	LENGTH
A1	L700 N600 N600 L2100 L1900 G1900 N2100 N1900	(N) NOKIA AEHC	350°	70'-0"	-	_	_	_	_	_	_	_	_	_	_	_	_	_
A2	L2500 N2500	(N) COMMSCOPE FFVV-65C-R3-V1_	350°	70'-0"	1 1	(N) NOKIA AHFIG (N) NOKIA AHLOA	TOWER TOWER	-	-	-	_	-	1	(N) HCS 2.0 PART 1	1	(N) HYBRID	1-1/2"	115'-0"
BETA																		
B1	L700 N600 N600 L2100 L1900 G1900 N2100 N1900	(N) NOKIA AEHC	110*	70'-0"	_	_	_	_	_	_	-	_	-	_	_	-	_	_
B2	-	(E) ANDREW VHLP1-23	120°	70'-0"	1	(E) DRAGONWAVE HORIZON COMPACT PLUS	TOWER	_	-	-	_	_	_	_	1	(E) COAX	1/2"	115'-0"
В3	L2500 N2500	(N) COMMSCOPE FFW-65C-R3-V1_	110*	70'-0"	1 1	(N) NOKIA AHFIG (N) NOKIA AHLOA	TOWER TOWER	_	-	-	_	-	1	(N) HCS 2.0 PART 1	1	(N) HYBRID	1-1/2"	115'-0"
GAMMA																		
C1	L700 N600 N600 L2100 L1900 G1900 N2100 N1900	(N) NOKIA AEHC	230°	70'-0"	-	_	-	_	_	_	ı	-		_	_	_	_	_
C2	L2500 N2500	(N) COMMSCOPE FFVV-65C-R3-V1_	230°	70'-0"	1 1	(N) NOKIA AHFIG (N) NOKIA AHLOA	TOWER TOWER	_	-	-	_	-	_	-	_	-	_	-
<u>NOTE:</u> (E) – EX (N) – NE	ISTING W							•			•				0	(E) UNUSED	_	-







T-MOBILE
SITE NUMBER: **DN06123A**(SPRINT RETAIN)

BU #: 877092 F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

ISSUED FOR:								
REV	DATE	DRWN	DESCRIPTION	DES./QA				
0	05/05/21	VBP	CONSTRUCTION	JFJ				
1	05/24/21	JLB	CONSTRUCTION	JFJ				
2	06/21/21	AOW	CONSTRUCTION	JFJ				
3	09/16/21	GVM	CONSTRUCTION	JFJ				
4	04/14/22	PSS	CONSTRUCTION	JFJ				




04/14/22


Andrew R. Berglund, P.E. Professional Engineer License: #58272


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER:

 $\begin{array}{c} -4 \end{array}$
















SIGNAL	#OF NTERFACES	CONNECTOR	DESCRIPTION
DC IN	1	DC TERMINA	48V DC INPUT
EAC	1	HDMI	EXTERNAL ALARM & CONTROL, 6 ALARMS, 6 ALARMS/CTRLS
SIN	1	HDMI S	YNCHRONIZATION INPUT, GNSS INTERFACE
SOUT	1	HDMI S	YNCHRONIZATION OUTPUT
LMP	1	RJ45 L	OCAL MANAGEMENT PORT, 1G ETHERNET
EIF	2	SFP28	BACKHAUL/HIGHER LAYER FRONTHAUL INTERFACE. U TO 25GE PER PORT. SUPPORT FOR SYNCE IEEE1588.
SEI	1	QSFP+	SYSTEM EXTENSION INTERSFACE, 4 X 10GE
RESET	Ť		PLUG IN RESET
SERVICE	1		SERVICE BUTTON, RECOVERY RESET
LEDS	7		VISUAL INDICATION OF STATUS



Property	Value	Dimensions orientation
Height	128.5 mm (5.1 in.)	
Depth	400 mm (15.7 in.)	
Width	447 mm (17.6 in.)	





COMMSCOPE HCS 2.0 PART 1

JUNCTION BOX MAKE: COMMSCOPE JUNCTION BOX MODEL: HCS 2.0 PART 1 DIMENSIONS, HxWxD: 14.0"x16.0"x8.0" 23.50 LBS

COMMSCOPE/HCS 2.0 PART 1 SCALE: NOT TO SCALE







T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

	ISSUED FOR:								
REV	DATE	DRWN	DESCRIPTION	DES./QA					
0	05/05/21	VBP	CONSTRUCTION	JFJ					
1	05/24/21	JLB	CONSTRUCTION	JFJ					
2	06/21/21	AOW	CONSTRUCTION	JFJ					
3	09/16/21	GVM	CONSTRUCTION	JFJ					
4	04/14/22	PSS	CONSTRUCTION	JFJ					



04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER:

REVISION:



Table: AMIA dimensions and weight









FSMF DETAILS


SCALE: NOT TO SCALE





SIGNAL	#OF NTERFACES	CONNECTOR	DESCRIPTION
Q-RFN	2	QSFP28	4 X 25/10 GBPS PER EACH CONNECTOR, SUPPORTS 10GE AND 25 GE ETHERNET PROTOCOLS
S-RFN	2	SFP28	1 X 25/10 GBPS PER EACH CONNECTOR, SUPPORTS 10GE AND 25 GE ETHERNET PROTOCOLS
LEDS	5	,	/ISUAL INDICATION OF STATUS



(15) SCALE: NOT TO SCALE







ANTENNA PIPE DETAILS

T··Mobile··· 2323 DELGANY STREET

DENVER, CO 80216





T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

		ISSUED FOR:									
	REV	DATE	DRWN	DESCRIPTION	DES./QA						
٦	0	05/05/21	VBP	CONSTRUCTION	JFJ						
1	1	05/24/21	JLB	CONSTRUCTION	JFJ						
	2	06/21/21	AOW	CONSTRUCTION	JFJ						
	3	09/16/21	GVM	CONSTRUCTION	JFJ						
	4	04/14/22	PSS	CONSTRUCTION	JFJ						




04/14/22

Andrew R. Berglund, P.E. Professional Engineer License: #58272

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


ELECTRICAL DETAILS NOTES:

- 1. EXISTING EQUIPMENT LAYOUT WAS MADE USING INFORMATION PROVIDED BY CROWN CASTLE. CONTRACTOR TO VERIFY ALL EXISTING INFORMATION IS AS INDICATED ON SITE PLAN. CONTRACTOR IS TO ESTABLISH THE EXISTENCE AND LOCATION OF ALL EXISTING OVERHEAD AND UNDERGROUND UTILITIES. IMMEDIATELY NOTIFY THE CONSTRUCTION MANAGER OF ANY DISCREPANCIES.
- 2. CONTRACTOR TO ENSURE THAT ALL T-MOBILE EQUIPMENT IS INSTALLED INSIDE T-MOBILE'S LEASE AREA, INCLUDING BUT NOT LIMITED TO, EQUIPMENT CABINETS, UTILITY CABINETS, H-FRAMES, ETC.
- 3. CONTRACTOR TO VERIFY THAT ALL T-MOBILE EQUIPMENT IS INSTALLED TO MEET THE WORKING CLEARANCE REQUIREMENTS OF NEC 110.26



ELECTRICAL DETAILS NOTES:

- 1. EXISTING EQUIPMENT LAYOUT WAS MADE USING INFORMATION PROVIDED BY CROWN CASTLE. CONTRACTOR TO VERIFY ALL EXISTING INFORMATION IS AS INDICATED ON SITE PLAN. CONTRACTOR IS TO ESTABLISH THE EXISTENCE AND LOCATION OF ALL EXISTING OVERHEAD AND UNDERGROUND UTILITIES. IMMEDIATELY NOTIFY THE CONSTRUCTION MANAGER OF ANY DISCREPANCIES.
- 2. CONTRACTOR TO ENSURE THAT ALL T-MOBILE EQUIPMENT IS INSTALLED INSIDE T-MOBILE'S LEASE AREA, INCLUDING BUT NOT LIMITED TO, EQUIPMENT CABINETS, UTILITY CABINETS, H-FRAMES, ETC.
- 3. CONTRACTOR TO VERIFY THAT ALL T-MOBILE EQUIPMENT IS INSTALLED TO MEET THE WORKING CLEARANCE REQUIREMENTS OF NEC 110.26
- 4. CONTRACTOR TO VERIFY CONDITION AND LOCATION OF ALL EXISTING GROUNDING EQUIPMENT PRIOR TO CONSTRUCTION. TEP DID NOT CONFIRM EXISTING SITE CONDITIONS INCLUDING, BUT NOT LIMITED TO, GROUND RINGS, GROUND RODS, AND GROUND BARS.
- 5. CONTRACTOR TO VERIFY WITH LOCAL INSPECTOR THAT EGRESS IS OF SUFFICIENT AREA TO GIVE ACCESS TO AND EGRESS FROM THE EQUIPMENT





2323 DELGANY STREET DENVER, CO 80216





TOWER ENGINEERING PROFESSIONALS 4710 E ELWOOD ST, STE 9 PHOENIX, AZ 85040 OFFICE: (480) 285-0036 www.tepgroup.net

T-MOBILE SITE NUMBER: **DN06123A** (SPRINT RETAIN)

BU #: **877092** F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

EXISTING 69'-7" SELF **SUPPORT**

	ISSUED FOR:									
REV	DATE	DRWN	DESCRIPTION	DES./QA						
0	05/05/21	VBP	CONSTRUCTION	JFJ						
1	05/24/21	JLB	CONSTRUCTION	JFJ						
2	06/21/21	AOW	CONSTRUCTION	JFJ						
3	09/16/21	GVM	CONSTRUCTION	JFJ						



09/16/21

Mark S. Quakenbush, P.E. Professional Engineer License: #51287

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

REVISION:

LEGEND

MECHANICAL CONNECTION EXOTHERMIC CONNECTION

ANTENNA GROUND BAR



EQUIPMENT GROUNDING PLAN 3/4"=1'-0" (FULL SIZE)






NEW PANEL: PPC							PANEL			<u>,</u>			VOLTAGE:	240 /	120 V 1ø,3W
OCATION: PPC CABINET				0:	9/10	UKAIC S.	ERIES R	AIL.	ע				MAINS:	240 / 200 A	
MOUNTING: SURFACE	NFMA R	ATING:3R											BUS:	200 A	
LOAD	EMT	CU	PHASE	СКТ	CIR	LOAD	AMPS	CIR	СКТ	PHASE	CU	EMT	LOAD	200 N	
DESCRIPTION	COND	GRND	NEUT	BRKR	NO.	PHASE A	PHASE B	NO.	BRKR	NEUT	GRND	COND	DESCRIPTION		
MISC	3/4"	10	10	30	1	0.0			20	10	10	3/4"	LIGHTING &		LES
(E) TVSS	'					4.0	1	2	1			'	(E) LIGHT &		
MISC			10		3		0.0		70	4	8	1"	MISC		
Cont.				2			56.0	4]				(E) 2.5		
MISC	3/4"	12	12	15	5	1.5]	4			MISC		
(E) GFCI				1		56.0		6	2				Cont.		
MISC	1-1/4"	8	3	100	7		0.0		15	12	12	3/4"	MISC		
(RL) SPARE / OFF							0.0	8	1				(E) SPARE	OFF	
MISC			3		9	0.0	1		20	10	10	3/4"			
Cont.				2		0.0		10	1				(E) SPARE /	OFF	
MISC	3/4"	12	12	15	11		0.0		50	8	10	3/4"			
(RL) SPARE / OFF					<u> </u>		0.0	12					(E) SPARE	OFF	
MISC			12		13	0.0	-	<u> </u>	_	8			MISC		
Cont. MISC	1"		-	2	45	0.0	0.0	14	2			4 "	Cont.		
	1	8	4	80	15	-	0.0	46	80	4	8	1"	MISC	/ 055	
(E) SPARE / OFF MISC			4		17	0.0	0.0	16		4			(E) SPARE /	UFF	
Cont.			•	2	 ''	0.0	1	18	2	•			Cont.		
MISC	1-1/4"	6	1	125	19	0.0	65.8	118	80	4	8	1"	MISC		
(N) 6160 SITE SUPPORT CABINET	'''	"	'	125	13		0.0	20	00		"	'	(E) SPARE	/ OFF	
MISC			1		21	65.8	0.0	120	1	4			MISC	011	
Cont.			`	2	<u> </u>	0.0	1	22	2	`			Cont.		
BUSSED SPACE					23		0.0						BUSSED SPA	.CE	
							0.0	24							
AMPS PER PHASE (CODE LOAD)			•		•	127.3	121.8		CONTRA	CTOR TO	INSTALL	_ APPRO	VED HANDLE	TIE ON ALL	_ SHARED
,							•	-	NEUTRA	L CIRCUI	TS.				
1 PHASE DEMAND (VA)											SYMBOL	LIST			
LIGHTING							300	-							
25% OF LIGHTING							75	-							
RECEPTACLES							360	-							
nest moles	_						300	_							
	_							-							
MISCELL ANECUS	_						00070	-							
MISCELLANEOUS	_						29232	-							
25% OF MISCELLANEOUS	<u>—</u>						7308	-							
	_							_							
								-							
	_							_							
	_							-							
TOTAL VA							37275	_							
	27 KVA @	240	V 1ø						I						
37.2	Z/ NVA W	210													

LEGEND:
(E) — EXISTING
(RL) — RELABELED
(N) — NEW

DC -48V FEEDER CABLING CHART

CALCULATIONS ARE BASE ON WORST CASE FULL LOAD AMPS AT 104A -48VDC, NOT EXCEEDING 3% VOLTAGE DROP. IF FIELD CONDITIONS ARE DIFFERENT THAN INDICATED, CONTACT ENGINEER FOR REVISED CALCULATIONS.

DISTANCE FROM FUEL CELL TO EQUIP. CABINET.	-48V, DC SINGLE CABLE	-48V, DC PARALLEL CABLE	CONDUIT SIZE
1'-70'	1-#1/0 CU. AWG		1-1/4"
71'–90'	1-#2/0 CU. AWG		1-1/2"
91'-110'	1-#3/0 CU. AWG		1-1/2"
111'-140'	1-#4/0 CU. AWG		2"
141'–175'		2-#2/0 CU. AWG	2"



#6 COPPER WIRE AND GREATER SHALL BE (COPPER) THWN WIRE OR (COPPER) XHHW.

NOTE:
PRIOR TO RUNNING CONDUIT ROUTE — CONTRACTOR
SHALL CONTACT THE T-MOBILE PROJECT MANAGER
AND VERIFY THE EQUIPMENT CABINET LAYOUT
CONFIGURATION AND ROUTE CONDUITS ACCORDINGLY.

NOTE:
PRE-CONSTRUCTION MEETING AND
ELECTRICAL EASEMENT REQUIRED.

NOTE:
CONTRACTOR SHALL TAG EACH
CIRCUIT CONDUCTOR AT EACH
J-BOX, OUTLET, SWITCH, ETC.
WITH THE CIRCUITS IDENTIFICATION.

NOTE:
CONTRACTOR SHALL TAG EACH
CIRCUIT CONDUCTOR AT EACH
J-BOX, OUTLET, SWITCH, ETC.
WITH THE CIRCUITS IDENTIFICATION

NOTE:
PROPOSED CONDUCTORS FROM
PPC TO SSC CABINET EXCLUDE
NEUTRAL CONDUCTOR AT THE
DIRECTION OF T-MOBILE.

NOTE:
ALL EQUIPMENT SHOWN IN THE ONE—LINE DIAGRAM
AND PANEL SCHEDULE IN THESE DRAWINGS IS
EXISTING UNLESS NOTED OTHERWISE. ONLY NEW
CONDUIT AND CONDUCTORS ARE SHOWN ON
ONE—LINE DIAGRAM FOR CLARITY.







T-MOBILE
SITE NUMBER: **DN06123A**(SPRINT RETAIN)

BU #: 877092 F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

EXISTING 69'-7" SELF SUPPORT

ISSUED FOR:							
REV	DATE	DRWN	DESCRIPTION	DES./QA			
0	05/05/21	VBP	CONSTRUCTION	JFJ			
1	05/24/21	JLB	CONSTRUCTION	JFJ			
2	06/21/21	AOW	CONSTRUCTION	JFJ			
3	09/16/21	GVM	CONSTRUCTION	JFJ			



09/16/21


Mark S. Quakenbush, P.E. Professional Engineer License: #51287

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

E-2







NOTES:

- DOUBLING UP "OR STACKING" OF CONNECTIONS IS NOT PERMITTED.
 EXTERIOR ANTIOXIDANT JOINT COMPOUND TO BE USED ON ALL EXTERIOR CONNECTIONS.
 GROUND BAR SHALL NOT BE ISOLATED FROM TOWER. MOUNT DIRECTLY TO TOWER STEEL.
- ANTENNA GROUND BAR DETAIL

CALE: NOT TO SCALE




4 GROUNDWIRE INSTALLATION SCALE: NOT TO SCALE




NOTES:

- 1. EXTERIOR ANTIOXIDANT JOINT COMPOUND TO BE USED ON ALL EXTERIOR CONNECTIONS.
- 2. GROUND BAR SHALL NOT BE ISOLATED FROM TOWER. MOUNT DIRECTLY TO TOWER STEEL (TOWER ONLY). 3. GROUND BAR SHALL BE ISOLATED FROM BUILDING OR SHELTER.
- TOWER/SHELTER GROUND BAR DETAIL SCALE: NOT TO SCALE



NOTES:

- 1. DOWN LEAD (HOME RUN) CONDUCTORS ARE <u>NOT</u> TO BE INSTALLED ON CROWN CASTLE USA INC. TOWER, PER THE GROUNDING DOWN CONDUCTOR POLICY QAS—STD—10091. NO MODIFICATION OR DRILLING TO TOWER STEEL IS ALLOWED IN ANY FORM OR FASHION, CAD—WELDING ON THE TOWER AND/OR IN THE AIR ARE NOT PERMITTED.
- 2. OMIT INSULATOR WHEN MOUNTING TO TOWER STEEL OR PLATFORM STEEL USE INSULATORS WHEN ATTACHING TO BUILDING OR SHELTERS.
- 5 GROUND BAR DETAIL
 SCALE: NOT TO SCALE




NOTES:

- 1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND
- WIRE DOWN TO GROUND BAR.

 2. GROUNDING KIT SHALL BE TYPE AND PART NUMBER AS SUPPLIED OR
- RECOMMENDED BY CABLE MANUFACTURER.


 3. WEATHER PROOFING SHALL BE TWO-PART TAPE KIT, COLD SHRINK SHALL NOT BE USED.







7 SCALE: NOT TO SCALE

WIRE SIZE	BURNDY LUG	BOLT SIZE
#6 GREEN INSULATED	YA6C-2TC38	3/8" - 16 NC SS 2 BOLT
#2 SOLID TINNED	YA3C-2TC38	3/8" - 16 NC SS 2 BOLT
#2 STRANDED	YA2C-2TC38	3/8" - 16 NC SS 2 BOLT
#2/0 STRANDED	YA26-2TC38	3/8" - 16 NC SS 2 BOLT
#4/0 STRANDED	YA28-2N	1/2" - 16 NC SS 2 BOLT










SINGLE CONNECTOR AT STEEL OBJECTS



SINGLE CONNECTOR AT METALLIC/STEEL OBJECTS

8 HARDWARE DETAIL FOR EXTERIOR CONNECTIONS
SCALE: NOT TO SCALE

T - Mobile - - - 2323 DELGANY STREET DENVER, CO 80216





T-MOBILE
SITE NUMBER: **DN06123A**(SPRINT RETAIN)

BU #: 877092 F3/FILL-IN/COLORADO SPGS/CSP18

255 NORTH GATE BLVD COLORADO SPRINGS, CO 80921

> EXISTING 69'-7" SELF SUPPORT

	ISSUED FOR:									
REV	DATE	DRWN	DESCRIPTION	DES./Q						
0	05/05/21	VBP	CONSTRUCTION	JFJ						
1	05/24/21	JLB	CONSTRUCTION	JFJ						
2	06/21/21	AOW	CONSTRUCTION	JFJ						
3	09/16/21	GVM	CONSTRUCTION	JFJ						



09/16/21

Mark S. Quakenbush, P.E. Professional Engineer License: #51287

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

Section 3 - Proposed Template Images

56790EZ_SR_T.jpg

