
SITE PLAN AS REPLATTED

A PORTION OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO



LEGAL DESCRIPTION

QUARTER OF SECTION 18;

PARCEL 1

A PARCEL OF LAND BEING A PORTION OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: THE BASIS OF BEARINGS FOR THIS DESCRIPTION IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18, BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP, ASSUMED TO BEAR N 02°34'24" W A

DISTANCE OF 2630.10 FEET. COMMENCING AT THE SOUTHWEST CORNER OF SAID NORTHWEST

THENCE N 02°34'24" W ALONG THE WEST LINE OF SAID NORTHWEST QUARTER A DISTANCE OF 1016.69 FEET; THENCE S 89°45'14" E A DISTANCE OF 676.09 FEET; THENCE S 49°34'59" E A DISTANCE OF 184.96 FEET TO THE POINT OF **BEGINNING:**

THENCE N 48°17' 28" E A DISTANCE OF 559.22 FEET, THENCE S 43°15'00" E A DISTANCE OF 584.41 FEET TO A POINT ON THE NORTHWESTERLY RIGHT OF WAY LINE OF STATE HIGHWAY 115; THENCE ALONG SAID NORTHWESTERLY RIGHT OF WAY LINE THE FOLLOWING THREE (3) COURSES;

1) THENCE S 48°09'41" W A DISTANCE OF 440.33 FEET; 2) THENCE N 42°41'41" W A DISTANCE OF 10.00 FEET; 3) THENCE S 51°59'51" W A DISTANCE OF 55.50 FEET; THENCE N 49°34'59" W A DISTANCE OF 577.07 FEET TO THE POINT OF

CONTAINING 307,174 SQUARE FEET OR 7.053 ACRES MORE OR LESS.

PARCEL 2

A PARCEL OF LAND BEING A PORTION OF THE NORTHWEST QUARTER OF SECTION 18. TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BASIS OF BEARINGS FOR THIS DESCRIPTION IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18. BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP, ASSUMED TO BEAR N 02°34'24" W A DISTANCE OF 2630.10 FEET.

COMMENCING AT THE SOUTHWEST CORNER OF SAID NORTHWEST QUARTER OF SECTION 18;

THENCE N 02°34'24" W ALONG THE WEST LINE OF SAID NORTHWEST QUARTER A DISTANCE OF 1016.69 FEET TO THE POINT OF BEGINNING; THENCE CONTINUING N 02°34'24" W ALONG SAID WEST LINE OF THE NORTHWEST QUARTER A DISTANCE OF 601.83 FEET; THENCE S 85°13'22" E A DISTANCE OF 864.46 FEET; THENCE S 62°45'00" E A DISTANCE OF 298.00 FEET; THENCE S 43°15'00" E A DISTANCE OF 197.06 FEET: THENCE S 48°17' 28" W A DISTANCE OF 559.22 FEET; THENCE N 49°34'59" W A DISTANCE OF 184.96 FEET;

THENCE N 89°45'14" W A DISTANCE OF 676.09 FEET TO THE POINT OF BEGINNING.

CONTAINING 627,582 SQUARE FEET OR 14.407 ACRES MORE OR LESS.

TOGETHER WITH:

A 30 FOOT EASEMENT FOR INGRESS, EGRESS AND UTILITIES LOCATED IN THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: THE BASIS OF BEARINGS FOR THIS DESCRIPTION IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18, BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP. ASSUMED TO BEAR N 02°34'24" W A DISTANCE OF 2630.10 FEET.

COMMENCING AT THE SOUTHWEST CORNER OF SAID NORTHWEST QUARTER OF SECTION 18; THENCE N 02°34'24" W ALONG THE WEST LINE OF SAID NORTHWEST QUARTER A DISTANCE OF 1016.69 FEET;

THENCE S 89°45'14" E A DISTANCE OF 676.09 FEET, THENCE S 49°34'59" E A DISTANCE OF 184.96 FEET; THENCE N 48°17' 28" E A DISTANCE OF 212.64 FEET TO A POINT ON THE CENTERLINE OF SAID 30' EASEMENT, SAID POINT BEING THE POINT OF BEGINNING; THE FOLLOWING SEVEN (7) COURSES ARE ALONG THE CENTERLINE OF

SAID 30 FOOT EASEMENT:

1) THENCE S 18°34'51" E A DISTANCE OF 42.31 FEET TO A POINT OF 2) THENCE ALONG SAID CURVE TO THE LEFT HAVING A RADIUS OF 75.00 FEET, A CENTRAL ANGLE OF 36°29'10", A LENGTH OF 47.76

FEET AND WHOSE CHORD BEARS S 36°49'25" E A DISTANCE OF 46.96


FEET TO THE POINT OF A REVERSE CURVE; 3) THENCE ALONG SAID CURVE TO THE RIGHT HAVING A RADIUS OF 50.00 FEET, A CENTRAL ANGLE OF 48°20'31", A LENGTH OF 42.19 FEET AND WHOSE CHORD BEARS S 30°53'45" E A DISTANCE OF 40.95

4) THENCE S 06°43'29" E A DISTANCE OF 60.17 FEET TO A POINT OF

CURVF: 5) THENCE ALONG SAID CURVE TO THE LEFT HAVING A RADIUS OF 200.00 FEET, A CENTRAL ANGLE OF 30°13'12", A LENGTH OF 105.49 FEET AND WHOSE CHORD BEARS S 21°50'05" E A DISTANCE OF 104.27 FEET;

6) THENCE S 36°56'41" E A DISTANCE OF 108.76 FEET; 7) THENCE S 42°24'10" E A DISTANCE TO 191.84 FEET TO A POINT ON THE NORTHWESTERLY RIGHT OF WAY LINE OF STATE HIGHWAY 115, SAID POINT BEING THE POINT OF TERMINUS OF SAID CENTERLINE OF A 30 FOOT EASEMENT AND BEING N 51°59'51" E A DISTANCE OF 28.69 FEET FROM THE SOUTHWEST CORNER OF A PARCEL OF LAND RECORDED AT RECEPTION NUMBER RECORDS OF EL PASO COUNTY.

SIDELINES ARE 15 FEET EACH SIDE OF THE DESCRIBED CENTERLINE AND EXTEND OR SHORTEN AS NEEDED.



NOTES:

1. THE BASIS OF BEARINGS IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18, BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP, ASSUMED TO BEAR N 02°34'24" W A DISTANCE OF 2630.10 FEET.

2. UNITS OF MEASUREMENT ARE U.S. SURVEY FEET.

- 3. THIS SITE PLAN DOES NOT CONSTITUTE A TITLE SEARCH BY MARR LAND SURVEYING TO DETERMINE OWNERSHIP OR EASEMENTS. FOR THIS A TITLE COMMITMENT FROM COMMONWEALTH LAND TITLE INSURANCE COMPANY, COMMITMENT NO . 598-H0457732-071-AW8, AMENDMENT NO. 2, EFFECTIVE DATE: FEBRUARY 17, 2016 AT 7:00 A.M. WAS RELIED ON.
- 4. FLOODPLAIN STATEMENT: THE SURVEYED PARCELS ARE LOCATED IN ZONE X, (AREA OF MINIMAL FLOOD HAZARD), MAP NUMBER 08041C1125G, MAP REVISED DECEMBER 7, 2018

5. DATE OF SURVEY 04/08/20.

- 6. ALL PROPERTY OWNERS ARE RESPONSIBLE FOR MAINTAINING PROPER STORM WATER DRAINAGE IN AND THROUGH THEIR PROPERTY. PUBLIC DRAINAGE EASEMENTS AS SPECIFICALLY NOTED ON THE PLAT SHALL BE MAINTAINED BY THE INDIVIDUAL LOT OWNERS UNLESS OTHERWISE INDICATED. STRUCTURES, FENCES, MATERIALS OR LANDSCAPING THAT COULD IMPEDE THE FLOW OF RUNOFF SHALL NOT BE PLACED IN DRAINAGE EASEMENTS.
- 7. MAILBOXES SHALL BE INSTALLED IN ACCORDANCE WITH ALL EL PASO COUNTY AND UNITED STATES POSTAL SERVICE REGULATIONS.
- 8. INDIVIDUAL LOT PURCHASERS ARE RESPONSIBLE FOR CONSTRUCTING DRIVEWAYS, INCLUDING NECESSARY DRAINAGE CULVERTS FROM STATE HIGHWAY 115 ROAD PER LAND DEVELOPMENT CODE SECTION 6.3.3.C.2 AND 6.3.3.C.3. DUE TO THEIR LENGTH, SOME OF THE DRIVEWAYS WILL NEED TO BE SPECIFICALLY APPROVED BY THE SOUTHWESTERN HIGHWAY 115 FPD.

ZONING:

PROPERTY OWNER: RED CREEK PROPERTIES LLC MAILING ADDRESS: 18780 SOUTH STATE HIGHWAY 115, COLORADO SPRINGS, CO 80926

PROPERTY ADDRESS: 18780 SOUTH STATE HIGHWAY 115,

COLORADO SPRINGS, CO

SCHEDULE NO.: 7700000022, 7700000082, 770000087


ZONING DESIGNATION: RR-5 SETBACKS: FRONT - 25' SIDES - 25'

REAR - 25' MAXIMUM LOT COVERAGE - 25% MAXIMUM BUILDING HEIGHT - 30'

DESCRIPTION	SQUARE FEET	PERCENT OF COVERAGE
LOT AREA PARCEL 1	307,174	
EXISTING RESIDENCE	2,810	0.91
EXISTING BARN	1,058	0.34
TOTAL LOT COVERAGE		1.26

SURVEYOR'S CERTIFICATION:

I, THOMAS S. MARR, A REGISTERED LAND SURVEYOR IN THE STATE OF COLORADO, HEREBY STATE AND DECLARE THAT THE ACCOMPANYING SITE PLAN WAS SURVEYED AND DRAWN UNDER MY RESPONSIBLE CHARGE AND ACCURATELY SHOWS THE DESCRIBED TRACT OF LAND ON THE DATE OF THE SURVEY TO THE BEST OF MY KNOWLEDGE.



MARR LAND SURVEYING	REVISIONS			
	NO.	DESCRIPTION	BY	DATE
506 Bonfoy Ave. B Colorado Springs, CO 80909 Ph. (719) 660—8623 tmarr@marrlandsurveying.com	1	COUNTY COMMENTS	TSM	02/21/21
			Τ '	

(IN FEET)

1 inch = 100 ft.

FOUND CDOT ROW MARKER AS NOTED

FOUND ALIQUOT CORNER AS NOTED

---- EASEMENT LINE

——O——O——O—— WIRE PENS

CONCRETE

DECK/PORCH

* NOT A PART OF THIS SURVEY

R.O.W. - RIGHT-OF-WAY

SQ.FT. - SQUARE FEET

AC. - ACRES

BOUNDARY LINE

— SECTION LINE

— WIRE FENCE LINE

· ---- 25' SETBACK LINE

GRAVEL/DIRT ROAD /PARKING

LEGEND:

-O- POWER POLE

☆^{LP} LIGHT POLE

© CLEAN OUT

(w) WELL HOUSE

(s) SEPTIC SYSTEM ACCESS

A PARCEL LOCATED IN SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO


ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT, MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF THE CERTIFICATION SHOWN HEREON.


Drawn By: TSM Date: 04/11/20 Checked By: TSM Sheet: 1 of 4



SITE PLAN

A PORTION OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO





LEGEND:

- SET 5/8"X18" REBAR WITH ORANGE PLASTIC CAP "PLS 30106"
- O FOUND 1/2" REBAR WITH 1-1/2" ALUMINUM CAP "PLS 25955"
- FOUND CDOT ROW MARKER AS NOTED
- FOUND ALIQUOT CORNER AS NOTED
- -O- POWER POLE
- ↓ GUY WRE
- ☆^{LP} LIGHT POLE
- S SEPTIC SYSTEM ACCESS
- © CLEAN OUT
- W WELL HOUSE

——————————————————————————————————————
RIGHT-OF-WAY LINE
——————————————————————————————————————
———— — ———————————————————————————————
OHE OVERHEAD ELECTRIC LINE
WIRE FENCE LINE WIRE PENS
— — — — BUILDING OVERHANG

GRAVEL/DIRT ROAD /PARKING

CONCRETE

DECK/PORCH

* NOT A PART OF THIS SURVEY R.O.W. - RIGHT-OF-WAY SQ.FT. - SQUARE FEET AC. - ACRES

MARR LAND SURVEYING	REVISIONS			
	NO.	DESCRIPTION	BY	DATE
506 Bonfoy Ave. B Colorado Springs, CO 80909 Ph. (719) 660—8623 tmarr@marrlandsurveying.com	1	COUNTY COMMENTS	TSM	02/21/21

47.76'

42.19'


105.49'

A PARCEL LOCATED IN SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6 TH P.M., COUNTY OF EL PASO, STATE OF COLORADO

NOTICE:
ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT
IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT, MAY
ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS
FROM THE DATE OF THE CERTIFICATION SHOWN HEREON. PROJECT 20-026 Drawn By: TSM
Checked By: TSM Date: 4/11/20

Sheet 3 of 4





LEGAL DESCRIPTION

PARCEL 1

A PARCEL OF LAND BEING A PORTION OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BASIS OF BEARINGS FOR THIS DESCRIPTION IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18, BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP, ASSUMED TO BEAR N 02°34'24" W A DISTANCE OF 2630.10 FEET.

COMMENCING AT THE SOUTHWEST CORNER OF SAID NORTHWEST QUARTER OF SECTION 18;

THENCE N 02°34'24" W ALONG THE WEST LINE OF SAID NORTHWEST QUARTER A DISTANCE OF 1016.69 FEET;

THENCE S 89°45'14" E A DISTANCE OF 676.09 FEET;

THENCE S 49°34'59" E A DISTANCE OF 184.96 FEET TO THE POINT OF BEGINNING;

THENCE N 48°17' 28" E A DISTANCE OF 559.22 FEET;

THENCE S 43°15'00" E A DISTANCE OF 584.41 FEET TO A POINT ON THE NORTHWESTERLY RIGHT OF WAY LINE OF STATE HIGHWAY 115;

THENCE ALONG SAID NORTHWESTERLY RIGHT OF WAY LINE THE FOLLOWING THREE (3) COURSES;

- 1) THENCE S 48°09'41" W A DISTANCE OF 440.33 FEET;
- 2) THENCE N 42°41'41" W A DISTANCE OF 10.00 FEET;
- 3) THENCE S 51°59'51" W A DISTANCE OF 55.50 FEET;

THENCE N 49°34'59" W A DISTANCE OF 577.07 FEET TO THE POINT OF BEGINNING.

CONTAINING 307,174 SQUARE FEET OR 7.053 ACRES MORE OR LESS.

LEGAL DESCRIPTION

PARCEL 2

A PARCEL OF LAND BEING A PORTION OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BASIS OF BEARINGS FOR THIS DESCRIPTION IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18, BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP, ASSUMED TO BEAR N 02°34'24" W A DISTANCE OF 2630.10 FEET.

COMMENCING AT THE SOUTHWEST CORNER OF SAID NORTHWEST QUARTER OF SECTION 18;

THENCE N 02°34'24" W ALONG THE WEST LINE OF SAID NORTHWEST QUARTER A DISTANCE OF 1016.69 FEET TO THE POINT OF BEGINNING;

THENCE CONTINUING N 02°34'24" W ALONG SAID WEST LINE OF THE NORTHWEST QUARTER A DISTANCE OF 601.83 FEET;

THENCE S 85°13'22" E A DISTANCE OF 864.46 FEET;

THENCE S 62°45'00" E A DISTANCE OF 298.00 FEET;

THENCE S 43°15'00" E A DISTANCE OF 197.06 FEET;

THENCE S 48°17' 28" W A DISTANCE OF 559.22 FEET;

THENCE N 49°34'59" W A DISTANCE OF 184.96 FEET;

THENCE N 89°45'14" W A DISTANCE OF 676.09 FEET TO THE POINT OF BEGINNING.

CONTAINING 627,582 SQUARE FEET OR 14.407 ACRES MORE OR LESS.

TOGETHER WITH:

A 30 FOOT EASEMENT FOR INGRESS, EGRESS AND UTILITIES LOCATED IN THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 17 SOUTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF EL PASO, STATE OF COLORADO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE BASIS OF BEARINGS FOR THIS DESCRIPTION IS THE WEST LINE OF THE NORTHWEST QUARTER OF SECTION 18, BEING MONUMENTED AT THE SOUTH END BY A FOUND 3-1/4" BLM BRASS CAP AND AT THE NORTH END BY A FOUND 3-1/4" BLM BRASS CAP, ASSUMED TO BEAR N 02°34'24" W A DISTANCE OF 2630.10 FEET.

COMMENCING AT THE SOUTHWEST CORNER OF SAID NORTHWEST QUARTER OF SECTION 18;

THENCE N 02°34'24" W ALONG THE WEST LINE OF SAID NORTHWEST QUARTER A DISTANCE OF 1016.69 FEET;

THENCE S 89°45'14" E A DISTANCE OF 676.09 FEET;

THENCE S 49°34'59" E A DISTANCE OF 184.96 FEET;

THENCE N 48°17' 28" E A DISTANCE OF 212.64 FEET TO A POINT ON THE CENTERLINE OF SAID 30' EASEMENT, SAID POINT BEING THE POINT OF BEGINNING;

THE FOLLOWING SEVEN (7) COURSES ARE ALONG THE CENTERLINE OF SAID 30 FOOT EASEMENT;

- 1) THENCE S 18°34'51" E A DISTANCE OF 42.31 FEET TO A POINT OF CURVE;
- 2) THENCE ALONG SAID CURVE TO THE LEFT HAVING A RADIUS OF 75.00 FEET, A CENTRAL ANGLE OF 36°29'10", A LENGTH OF 47.76 FEET AND WHOSE CHORD BEARS S 36°49'25" E A DISTANCE OF 46.96 FEET TO THE POINT OF A REVERSE CURVE;
- 3) THENCE ALONG SAID CURVE TO THE RIGHT HAVING A RADIUS OF 50.00 FEET, A CENTRAL ANGLE OF 48°20'31", A LENGTH OF 42.19 FEET AND WHOSE CHORD BEARS S 30°53'45" E A DISTANCE OF 40.95 FEET;
- 4) THENCE S 06°43'29" E A DISTANCE OF 60.17 FEET TO A POINT OF CURVE;
- 5) THENCE ALONG SAID CURVE TO THE LEFT HAVING A RADIUS OF
 200.00 FEET, A CENTRAL ANGLE OF 30°13'12", A LENGTH OF 105.49
 FEET AND WHOSE CHORD BEARS S 21°50'05" E A DISTANCE OF
 104.27 FEET;
- 6) THENCE S 36°56'41" E A DISTANCE OF 108.76 FEET;
- 7) THENCE S 42°24'10" E A DISTANCE TO 191.84 FEET TO A POINT ON THE NORTHWESTERLY RIGHT OF WAY LINE OF STATE HIGHWAY 115, SAID POINT BEING THE POINT OF TERMINUS OF SAID CENTERLINE OF A 30 FOOT EASEMENT AND BEING N 51°59'51" E A DISTANCE OF 28.69 FEET FROM THE SOUTHWEST CORNER OF A

PARCEL OF LAND RECORDED AT RECEPTION NUMBER,	
RECORDS OF EL PASO COUNTY.	

SIDELINES ARE 15 FEET EACH SIDE OF THE DESCRIBED CENTERLINE AND EXTEND OR SHORTEN AS NEEDED.