



**B** SINGLE FACE REVERSE/FACE LIT PAN CHANNEL LETTERS/LOGO  
 QUANTITY: ONE (1) REQUIRED SCALE: 3/8" = 1'-0"

**FABRICATE & INSTALL:**

**LETTERS/LOGO:** FABRICATED ALUMINUM WITH 5" BLACK RETURNS  
**FACES:** #7328 3/16" WHITE ACRYLIC WITH #143 POPPY RED VINYL ON LETTERS & PRINTED LOGO  
**TRIM:** 1" BLACK  
**BACKER:** ALUMINUM 3" OUTLINE AROUND LETTERS PAINTED TO MATCH BUILDING AROUND LOGO PAINTED SILVER

**ILLUM:** WHITE LED HALO AND FACE LIT WITH 60W POWER SUPPLIES AS REQUIRED

**INSTALLATION:** FLUSH MOUNTED ON BUILDING

**NOTE:** FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS PRIOR TO ANY FABRICATION



**CLIENT:** Shoco Oil  
**ADDRESS:** 7981 Red Granite Loop  
**CITY/STATE ZIP:** Colorado Springs, CO  
**SCALE:** As Noted  
**ACCT MGR:** Stephanie German  
**File Location:**

**DATE:** May 29, 2018  
**SHEET:** 1 of 1  
**DRAWN BY:** BS

© Copyright Colorado Sign Systems, Inc.  
 This design is the property of Colorado Sign Systems. Any use of this design by others without written permission of Colorado Sign Systems is prohibited and will be prosecuted to the fullest extent of the law. Any unauthorized use of this design will result in a minimum art charge of \$3000.00.

PLEASE NOTE: Colors depicted here are for representation only. Actual color samples can be obtained from your sales representative upon request.

**CLIENT APPROVAL**  
**SIGNATURE:** [Signature] **DATE:** 10-1-18  
 All copy is initially checked for errors by Colorado Sign Systems. Final proofreading and corrections are the sole responsibility of the client. Subsequent revision for typographical errors will be done at the clients expense.

**OWNER LANDLORD APPROVAL** **SIGNATURE:** [Signature] **DATE:** 10-1-18