



December 6, 2024

PCD File No. PPR2417

**LETTER OF INTENT
2217 JANITELL ROAD
SITE DEVELOPMENT PLAN
(MVE Proj. No. 61195)**

Owner:

Sombers Investments LLC
5565 Piedra Vista
Colorado Springs, CO 80908
(719) 491-0466

Consultant:

M.V.E., Inc.
1903 Lelaray Street, Suite 200
Colorado Springs, CO 80909
(719) 635-5736

Developer/Applicant:

High Country Crane & Rigging, LLC
2165 Janitell Road, Suite 104
Colorado Springs, CO 80906
(719) 491-0466

Site Location Size and Zoning:

The site proposed to be the location of the 22,500 Square Foot (SF) Office Warehouse is located in the Southwest Quarter of Section 28, Township 14 South, Range 66 West of the 6th P.M., El Paso County, Colorado. The property has an assigned address of 2165 Janitell Road. The site is located on the southeastern side of Janitell Road and about 300' southwest of East Las Vegas Street. The site borders Tract 4, Valley Gardens on the northeast, Tract 11, Valley Gardens on the southwest, and an unplatted Tract of land on the southeast. The proposed office/warehouse site is 5.35 acres in size and is platted as Tract 5, Valley Gardens except the part conveyed to El Paso County, Book 5657 at page 231 for Janitell Road right of way, with the Lot having El Paso County Tax Schedule No. 64283-01-005. The property is currently developed land with an obsolete zone of M1 (General Industrial and Manufacturing Activities).

Request and Justification:

The request is for Site Development Plan Approval of the new Office/Warehouse to be located in Tract 5 Valley Gardens, titled '**2217 Janitell Road**'. The project will consist of one (1) office/warehouse building having 22,500 SF building footprint, graveled access driveways, paved parking area, non-irrigated landscaping and a Full Spectrum – Sand Filter Basin (FS-SFB). The existing 13,200 SF office/warehouse will have about 2.0 Acres of open storage area. Said open storage area required maintenance and the existing recycled asphalt surface has been reconditioned in the past. The proposed 22,500 SF office/warehouse site will have about 1.0 acres of open storage. A portion of the 1.0 acre open storage area will be used as Full Spectrum-Sand Filter Basin (FS-SFB). The FS-SFB flows will be regulated to keep the storm water flows at a rate less than historic. These flows will drain from the

Engineers • Surveyors
1903 Lelaray Street, Suite 200 • Colorado Springs, CO 80909 • Phone 719-635-5736
Fax 719-635-5450 • e-mail mve@mvecivil.com

proposed pond outlet structure via pipe flow to Fountain Creek discharging onto a riprap pad into the Creek. Total area to be disturbed for this project will be about 93,860 square feet (SF) which is 2.15+/- acres.

The purpose of this Site Development Plan application is to provide a site for an additional office/warehouse and outside storage space for the area.

Access

The main access to the proposed 22,500 SF office/warehouse project is from the southwestern existing entrance from Janitell Road. The existing office/warehouse will use both the southwestern and northeastern existing accesses from Janitell Road. The southwesterly access leads along the the existing drive along the southerly side of said Tract 5 Valley Gardens to the area of the proposed 22,500 SF building, parking, and open storage area. New Driveway permits will be obtained for the site, if required, as part of the Building Permit process.

Parking

Thirty-one (30) parking spaces are provided for the proposed facility including two (2) van accessible ADA spaces. Thirty parking spaces will be sufficient for the proposed facility.

ADA Requirements

The site is provided with the required number ADA parking spaces. All dimensions, slopes, ramps and building access ways have been examined and are deemed compliant with the Department of Justice 2010 ADA Standards for Accessible Design.

Landscaping/Screening

Currently, the site is covered with an existing 13,200 SF office warehouse , 15,537 SF paved entrance drives, parking & sidewalk, along with a 19,200 SF concrete slab and some on-site portable sheds. Their is about 6375 SF of non-irrigated landscaping.

The existing water well does not allow water for irrigation. Rock and non-irrigated type plants will be utilized in the designated landscape areas for the new office/warehouse. Screening is not required.

Grading/Erosion Control/Storm Drainage

The site for the proposed office/warehouse & appurtenances will be graded to accept the new improvements and to tie into the existing grades on the four edges of the 2.15 +/- acre site. The proposed area to be disturbed is more than one acre and it is anticipated to move more than 500 cubic yards (CY) of soils.

The site will contain a stormwater FS-SFB to provide storm detention and water quality treatment. Runoff from the impervious surfaces of the proposed graded site will exit the site at the southern corner via the SFB outlet structure via storm. Existing flows are presently directed to said southern corner of the site for discharge.

The resulting outflow discharges will be less than or equal to existing conditions pursuant to the outlet structure design exiting the site via underground storm water piping directing the collected flows into Fountain Creek. A Final Drainage Report has been prepared as part of the submittal material for this application. The development of this site shall be in conformance with the drainage report. Drainage and Bridge Fees are not applicable as the ground is already platted.

Water, Sanitary Sewer, Electric and Gas Utilities

The site will utilize the existing well for water with no landscape watering allowance. The is wastewater will be pumped to the existing subsurface OWTS. Colorado Springs Utilities provides electricity.

Construction Documents for the proposed building will be reviewed by the required utility organizations.

Fire Protection

Tract 5 Valley Gardens is not in a Tax Entity for Fire Protection. Tract 5 Valley Gardens area is surrounded by the Colorado Springs Fire Tax Entity. Construction Documents for the proposed building will be reviewed by PPRBD and the Fire Department.

Traffic Impact

The proposed new office/warehouse will access the public Janitell Road. The proposed office/warehouse is expected to generate a total of 100 trips per day (Average weekday trips ends) based on Warehousing 150 for 19,700SF of warehouse and General Office 710 for 2,700 SF of office pursuant to Trip Generation, 9th Edition, 2017 by the Institute of Transportation Engineers. This number of trips is at the County threshold of 100 trips per day. Therefore, a Transportation Impact Study (TIS) is not required for the project. This development will not be subject to fees established by the El Paso County Road Impact Fee Program per El Paso County Resolution Number 18-471.

Existing and Proposed Facilities

The site at 2217 Janitell Drive requires no new facilities or public improvements. Construction Drawings for the buildings will be reviewed and approved by Pike Peak Regional Building Department.

Z:\61195\Documents\Letter of Intent\61195 LetterOfIntent-Site Dev Plan.odt