

**Letter of Intent**

**Waterview North Rezone Plan A-5 to I-2**

9/21

**Owners:** CPR Entitlements, LLC  
31 North Tejon St., Suite 500  
Colorado Springs, CO 80903  
(719) 377-0224  
hli.pak7@gmail.com

**Applicant:** CPR Entitlements, LLC  
31 North Tejon St., Suite 500  
Colorado Springs, CO 80903  
(719) 377-0224  
hli.pak7@gmail.com

**Consultant:** Dakota Springs Engineering  
31 North Tejon St., Suite 500  
Colorado Springs, CO 80903  
(719) 432-6889  
charlescothern@springseng.com

**Tax Schedule Nos.:** 5500000436, 5500000439

**Site Information:**

**History**

Waterview North is a proposed mixed-use development on 116.5 acres south of the Colorado Springs Airport and northeast of Powers Boulevard and Bradley Road. Waterview North is part of the Waterview Sketch Plan; the Waterview Sketch Plan was recently approved modifying the proposed land uses in Waterview North from Commercial and Industrial uses only, to 22.1 acres of Commercial, 26 acres of Industrial, and introduced a 68.4 acre mix of detached, attached, and multifamily Residential densities and land uses.

We are rezoning 22.1 acres of the Amended Waterview Sketch Plan Parcel P-14 from the current A-5 zoning to a land use associated with El Paso County Industrial (I-2) zoning.

**The legal description of the proposed I-2 zone is as follows:**

**PARCEL P-14 (INDUSTRIAL USE)**

A TRACT OF LAND LOCATED IN A PORTION OF SECTION 8 AND SECTION 9, BOTH IN TOWNSHIP 15 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE NW CORNER OF SAID SECTION 9;

THENCE S81°51'23"E ALONG THE NORTH LINE OF SAID SECTION 9, A DISTANCE OF 331.37 FEET;

THENCE S00°00'00"E DEPARTING SAID NORTH LINE, A DISTANCE OF 665.89 FEET TO A POINT OF CURVE TO THE LEFT;

THENCE ON SAID CURVE, HAVING A RADIUS OF 585.00 FEET, AN ARC LENGTH OF 342.60 FEET, A DELTA ANGLE OF 33°33'18", WHOSE LONG CHORD BEARS S16°46'39"E A DISTANCE OF 337.73 FEET;

THENCE S56°26'42"W A DISTANCE OF 545.66 FEET TO A POINT OF NON-TANGENT CURVE TO THE LEFT, SAID POINT BEING ON THE NORTHEASTERLY RIGHT-OF-WAY LINE OF POWESRS BOULEVARD DESCRIBED IN SAID BOOK 5307 AT PAGE 1472 (NOW HIGHWAY 21) OF THE RECORDS OF SAID EL PASO COUNTY;

THE FOLLOWING COURSE IS ON SAID RIGHT-OF-WAY LINE:

THENCE ON SAID CURVE, HAVING A RADIUS OF 2105.00 FEET; AN ARC LENGTH OF 2462.00 FEET, A DELTA ANGLE OF 67°00'46", WHOSE LONG CHORD BEARS N56°40'27"W A DISTANCE OF 2324.05 FEET TO THE NORTH LINE OF THE NE ¼ OF SAID SECTION 8;

THENCE N89°34'04"E ON SAID NORTH LINE, A DISTANCE OF 1967.80 FEET TO THE NE CORNER OF SAID SECTION 8 AND THE POINT OF BEGINNING.

PARCEL CONTAINS 1,134,540 SQUARE FEET OR 26.045 ACRES MORE OR LESS

**Request and Reason:**

To approve an Industrial I-2 rezone for the 26.0 acres currently zoned as A-5. This letter serves as a request to receive El Paso County approval of the proposed I-2 zoning for this site.

## **El Paso County Land Development Code**

The proposed Zoning Request is in conformance with the El Paso County Land Development Code based on the following Code analysis:

### **Rezoning Approval: Section 5.3.5(B)**

This request meets the criteria for approval outlined in Section 5.3.5 of the El Paso County Land Development Code by the following:

- The application is in **general conformance with the County Master Plan and previous county approvals**; in this case Sketch Planned Industrial and Commercial uses.

The **proposed Land Use and Zone District is compatible with the existing and permitted land uses in the area**, a mix of industrial, and urban density residential land uses included on the approved Amended Waterview Sketch Plan.

This Criteria is met by selecting land uses to compliment the neighboring facilities including the Colorado Springs Airport; all industrial/commercial uses are located within and near the APZ Zones while residential uses are further east and take advantage of the Open Space in the Peak Innovation Park Master Plan. Grading is held to a minimum while at the same time enhancing views to the west and southwest. Future plans include building and landscape arrangements per the airport recommendations and shared parking scenarios are being considered for commercial and multifamily development.

Proposed Commercial Development is located within or near the APZ area and focused on the Bradley Road Powers Boulevard intersection with direct access to Bradley Road at an existing intersection. This commercial/industrial development will provide both local and regional services and may provide support business opportunities near to Schriever AFB.

- **The site is suitable for the intended use.** Necessary urban and public services, available including access, stormwater facilities, public safety, recreation, utilities are or will be adequate and available to serve the site. Geologic conditions are also favorable to develop the site following accepted and adopted engineering guidelines.

The development will be within an existing previously approved Sketch Plan. Access is focused on Bradley road at previously approved access points. The commercial and Industrial proposed uses are focused at the Bradley Road and Powers Boulevard Corridors within a ¼ mile of an existing Intersection with Bradley Road. All urban residential land uses access within a ½ mile distance from Bradley Road.

There are city and county trails planned for the area. Waterview development welcomes the opportunity to provide conductivity to these trails and the adjoining open spaces of the Bluestem Prairie Open Space (Originally part of Waterview) and the Peak Innovation park Open Space.

## **YOUR EL PASO MASTER PLAN**

The County Master Plan locates the development within in the Colorado Springs Airport/Peterson Airforce Base Area on the **Key Area Map** as an area anticipating “New Development” on the **Areas of Change Map** with as a projected “Employment Center” by the **Placetypes Map**. The Plan recommends prioritization of nonresidential growth in this area to help expand Employment Center land uses and densities in this area.

The proposed zoning, which was developed in response to market demand and absorption is in general conformance with the intent, policies, goals, and recommendations of the Master Plan. Approval of the Waterview North Commercial and Industrial zoning reflects the prioritization of supporting commercial land uses.

The land uses and densities proposed and approved under the Amended Waterview Sketch Plan have been in review by the County prior to development and adoption of the current El Paso County Master Plan. The individual rezone applications needed to implement the uses authorized by the Sketch Plan are currently being reviewed for consistency with the newly adopted El Paso County Master Plan Land Use framework and typology recommendations. Chapter 14, Implementation states in the Land Use Applications and Master Plan Consistency narrative:

*...Approval of a land use application does not necessarily require a finding that the application is fully consistent with each and every applicable component of the Master Plan. [The Planning Commission and BOCC] have the discretion to give greater weight to individual components of the Master Plan compared to other components when taking a formal action to either approve, approve with conditions, or deny an application.*

### ***Goal 1.1 - Ensure compatibility with established character and infrastructure capacity.***

Proposed zoning, land uses, and densities are compatible with the approved 23.1 acres of commercial, the ± 167 acre urban residential Trails at Aspen Ridge, and ±5 acres of multifamily zone located along the southern border of Bradley Road opposite of the site and within the approved Sketch Plan Area.

The development will be within an existing previously approved Sketch Plan. Access is focused on Bradley road at previously approved access points. The commercial and Industrial proposed uses are focused at the Bradley Road and Powers Boulevard Corridors within a ¼ mile of an existing Intersection with Bradley Road. All urban residential land uses access within a ½ mile distance from Bradley Road.

### ***Goal 1.2 - Coordinate context-sensitive annexation and growth strategies with municipalities.***

The area is identified in the 3-mile Land Use Map (Map 3-1 Potential Annexation Areas) of the City of Colorado Springs Annexation Guide. It is identified as eligible, not recommended. The site lies within the Waterview Metropolitan District Service Boundaries which has committed to provide water and wastewater and other municipal type services.

***Goal 1.3 - Encourage a range of development types to support a variety of land uses.***

The proposed zoning is planned together with zoning applications supportive of mixed land uses as depicted on the Amended Waterview Sketch Plan (PCD File No. 20-2) that is pending approval. Uses approved under the sketch plan include light industrial, commercial retail, office, multifamily, and urban density single-family attached and detached residential.

**Goal 1.4 - Continue to encourage policies that ensure “development pays for itself”.**

Development in the proposed Waterview North area (inclusive of commercial, light industrial, and residential zones) will be developer and district funded including:

- Developer funded site and infrastructure improvements (roads, site preparation, and wet/dry utilities)
- Applicable drainage/bridge, park, and school fees payable at individual plat recordation
- Applicable County Road Impact Fees
- Utility Service Design, Construction, and/or Service Connection (Tap) Fees

Public services are being provided by Widefield Water and Sanitation District through extension of existing service lines. CSU Gas has recently increased service to this area (costs being shared by this development) and existing Mountain View electrical facilities are being extended underground through the development as construction commences. The area has been annexed into the Security Fire Protection District for taxing and service purposes. Screening and buffering will be considerations moving forward.

***Area: Colorado Springs Airport/Peterson Air Force Base***

The industrial zoning is consistent with the Colorado Springs Airport/Peterson Air Force Base Area. The Plan recommends prioritization of nonresidential growth in this area to help expand the Employment Center Placetype in this area to:

- implement policies, plans, programs, and partnerships in support of BOCC efforts to attract local businesses and promote development on the available land in the Area.
- provide additional job opportunities for County residents
- expand the County’s tax base, to:
  - providing more opportunities to address other County issues such as upgrades to infrastructure,
  - expansion of services,
  - and development of new roadways.
  - (See discussion on **Goal 1.4 - Continue to encourage policies that ensure “development pays for itself”**, above)

This commercial/industrial development will provide both local and regional services and may provide support business opportunities near to the Colorado Springs Airport and Peterson AFB.

***Areas of Change: New Development***

The industrial zoning is consistent with the New Development Area of Change. The plan assumes undeveloped areas Undeveloped “that are adjacent to a built out area ***will be developed to match the character of that adjacent development or to a different supporting or otherwise complementary one such as an employment hub or business park adjacent to an urban neighborhood***”. *[Emphasis Supplied]*

Proposed zoning, land uses, and densities are compatible with the approved 23.1 acres of commercial adjacent to the site, the ± 167 acre urban residential Trails at Aspen Ridge, and ±5 acres of multifamily zone located along the southern border of Bradley Road opposite of the site and within the approved Sketch Plan Area. The proposed development areas and zones have been planned to mutually support each other and upon development will create the land use scenario with employment hub/business park uses.

***Placetype: Employment Center***

Primary Employment Center uses include, Light Industrial/Business Park, Heavy Industrial, and Office Uses. Supporting land uses include Commercial Retail, Commercial Service, and Restaurant land uses.

The proposed light industrial zoning conforms with the primary uses in this Placetype. and proposed, commercial and mix of residential land use densities in the Amended Waterview Sketch Plan (2020) is consistent and compatible with the existing land use mixes within the Waterview South Sketch Plan Area and approved zoning and subdivision applications located on the south side of Bradley Road.

### **County Water Master Plan Conformance:**

The proposed subdivision satisfies the following policies of the County Water Master Plan:

**Policy 5.2.4:** Encourage the locating of new development where it can take advantage of existing or proposed water supply projects that would allow shared infrastructure costs.

The proposed subdivision is located within the service area of the Widefield Water and Sanitation District (WWSD). Service will be provided based on a recently approved inclusion agreement with this District. Water and Sewer service will be provided by extending water and sewer lines from south of Bradley Road. A Will Serve Letter is provided noting the District's ability to serve the proposed development in an efficient manor with the current infrastructure provided with extension as noted above.

**Policy 5.5.1:** Discourage individual wells for new subdivisions with 2.5 acre or smaller average lot sizes, especially in the near-surface aquifers, when there is a reasonable opportunity to connect to an existing central system, alternatively, or construct a new central water supply system when economies of scale to do so can be achieved.

The proposed subdivision is located within the service area of the Widefield Water and Sanitation District (WWSD). A Will Serve Letter is provided noting the District's ability to serve the proposed development in an efficient manor with the current infrastructure.

**Policy 6.0.1:** Continue to require documentation of the adequacy or sufficiency of water, as appropriate for proposed development.

An appropriate Will Serve Letter is provided noting the WWSD's ability to serve the proposed development in an efficient manor with the current infrastructure and noting their current capacity to serve.

The project is located within Region 7, Fountain Area, and is projected to be the largest growth area in El Paso County. Specifically, the Water Master Plan states:

Region 7 could experience the largest demand growth in the County by 2060. Areas projected to develop by 2040 are located south of Fountain on the north and south sides of Link Road. Areas northwest of Fountain along the east and west sides of Marksheffel Road are also expected to grow by then, as well as the area south of Fountain on the west side of I-25. Directly west of Fountain, areas north and south of Squirrel Creek Road are expected to grow by 2060. One large development is expected south of Fountain by 2060, along the west side of I-25. Another is expected in the northeast corner of Region 7, along both sides of Bradley Road.

Full Build out of the Widefield Water and Sanitation District is expected in the 2040 to 2060 time frame. The Water Resources Report indicates that the District has sufficient water supply to meet the expected need to full build out. Region 7 has a current water supply of 15,376 acre-feet per year and a current demand of 10,141 acre-feet per year.

The 2040 water supply is project to be 25,241 acre-feet per year and the demand is projected to be 15,846 acre-feet. As stated in the water resources report, this development is projected to need 437 acre-feet of water per year.

The District currently incorporates a 15% reserve into future planning. Based on the needs, current supply and reserve the District has sufficient water to meet the needs expected now and into the future.

A Will Serve letter has been provided by WWSD, the water system that serves Waterview North and all of WWSD is classified as a Public Water System and meets all CDPHE applicable requirements.

The water system uses a combination of groundwater and renewable sources and is part of the southern delivery system. There are multiple pressure zones within the WWSD system served by both gravity and pumped systems. Waterview North is in the highest pumped pressure zone.

### **Existing and Proposed Facilities:**

The site currently is vacant. Proposed services in the development include the following:

- Water/Sewer-Widefield Water and Sanitation District
- Electric Service-Mountain View Electric and City of Colorado Springs
- Natural Gas Service – City of Colorado Springs
- Telephone Service – Century Link
- Fire Protection – Security Fire Protection District

The applicant anticipates county approval of Water Quality and Sufficiency at Preliminary Plan approval.

### **Offsite Improvements**

Extension of Water and Sewer lines from the development currently underway south of Bradley Road.

### **Impact Identification:**

#### Wildlife

Preexisting wildlife habitats and migration routes are noted for the usual prairie animals. This site has existing Bradley Road to the south and Powers Boulevard to the west. Wildlife impact to the area has already occurred due to these existing roads. A wildlife study was commissioned and completed and has been submitted as part of the Preliminary Plan submittal and can be reviewed as part of that land use application.

#### Colorado Springs Airport



The applicant has met with Colorado Springs Airport staff to discuss the Waterview Sketch Plan Amendment particularly concerning the east half of the application. The primary discussion point concerning the application had to do with the Airports plans to upgrade their landing lights for the east runway; the east runway is roughly in line with Powers Boulevard and due north of the proposed Industrial use. The new lighting system will be more powerful than the existing system and the airport is concerned that the strobe function of the lighting system could be detected in the development.

The airport indicated that the following steps could be taken to mitigate any effects from the strobe runway lighting:

1. Installation of landscaping (evergreen) and/or other barriers (berming/fencing) perpendicular to the runway.
2. Orientation of housing to account for runway lights.
3. Addition of plat notes indicating proximity to the airport.

The applicant notes the following in coordination with airport concerns.

1. The proposed land use should not be significantly affected by the runway lighting.
2. The applicant will continue to consider the airport concerns as development progresses.
3. The following language, suggested by the Airport Staff, will be incorporated on the plat in coordination with El Paso County review and approval:

*The development and its occupants may be impacted by air illumination or approach lighting systems that use medium and high-intensity lights to guide aircraft to the runway centerline used for navigation or flight in air.*

In addition to the above the applicant would like to state the following concerning mitigation of the runway lighting:

Industrial Land Use seems like the least likely land use to be negatively affected by any activity or lighting from the Colorado Springs Airport.

#### Transportation (TIS Summary)

Access will be from Bradley Road via Powers Boulevard. Capacity of these roads is addressed in the TIS provided and approved with the Waterview Sketch Plan Amendment in July of 2021. In said TIS, two access points to Waterview North will be provided along Bradley Road, one as a full access and a secondary right-in/right-out access. Primary access to the industrial parcel is the westerly full-movement intersection approved and constructed for the development on the South side of Bradley Road.