

FALCON FIELD

EL PASO COUNTY, COLORADO

REZONE

NORTH EAST 1/4, SECTION 7, TOWNSHIP 13 SOUTH, RANGE 64 WEST

LEGAL DESCRIPTION PARCEL SOUTH

A PARCEL OF LAND SITUATED IN SECTION 7, TOWNSHIP 13 SOUTH, AND RANGE 64 WEST OF THE 6TH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO, BEING A PORTION OF THAT TRACT OF LAND DESCRIBED UNDER RECEPTION NO. 202131510 OF THE RECORDS OF SAID COUNTY, SAID PARCEL OF LAND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

(BEARINGS REFERED TO HEREIN ARE BASED ON THE NORTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 7, SAID LINE BEING MONUMENTED AT HE WEST END BY A 3" ALUMINUM CAP STAMPED WITH COLORADO REGISTERED LAND SURVEYOR NO. 17664, AND MONUMENTED AT THE EAST END BY A 2" ALUMINUM CAP STAMPED WITH COLORADO REGISTERED LAND SURVEYOR NO. 17665, SAID LINE IS ASSUMED TO BEAR N89°08'49"W)

BEGINNING AT THE NORTHWEST CORNER OF "ARROWHEAD ESTATES FILING NO.1" AS DESCRIBED IN PLAT BOOK Y-3, PAGE 39 OF THE RECORDS OF SAID COUNTY; SAID CORNER ALSO BEING THE NORTHWEST CORNER OF LOT 13, OF SAID "ARROWHEAD ESTATES FILING NO.1";

THE FOLLOWING (3) THREE COURSES ARE ON THE WESTERLY AND NORTHERLY LINES OF SAID "ARROWHEAD ESTATES FILING NO.1";

- 1) THENCE S00°46'01"W A DISTANCE OF 1,185.50 FEET;
- 2) THENCE S86°02'56"W A DISTANCE OF 327.55 FEET;
- 3) THENCE S00°19'57"W A DISTANCE OF 68.25 FEET TO THE NORTHERLY LINE OF THAT TRACT OF LAND DESCRIBED UNDER RECEPTION NO. 202090702 OF SAID RECORDS;

THENCE N89°59'12"W A DISTANCE OF 430.50 FEET ON SAID NORTHERLY LINE TO THE SOUTHWESTERLY CORNER OF "VERBURG SUBDIVISION WAIVER", A TRACT OF LAND DESCRIBED UNDER RECEPTION NO. 201000639 OF SAID RECORDS;

THENCE N00°14'16"E A DISTANCE OF 784.95 FEET ON THE EASTERLY LINE OF SAID "VERBURG SUBDIVISION WAIVER";

THENCE N50°03'23"E, DEPARTING SAID EASTERLY LINE, A DISTANCE OF 517.17 FEET TO A POINT OF CURVE TO THE LEFT;

THENCE ON THE ARC OF SAID CURVE, HAVING A RADIUS OF 2,181.70 FEET, A DELTA ANGLE OF 07°26'01", AN ARC LENGTH OF 283.06 FEET, WHOSE LONG CHORD BEARS N46°20'23"E A DISTANCE OF 282.86 FEET;

THENCE S78°00'01"E A DISTANCE OF 172.92 FEET TO THE POINT OF BEGINNING.

THE ABOVE TRACT OF LAND CONTAINS 808,035 SQUARE FEET OR 18.550 ACRES, MORE OR LESS.

LEGAL DESCRIPTION PARCEL EAST

A PARCEL OF LAND SITUATED IN SECTION 7, TOWNSHIP 13 SOUTH, AND RANGE 64 WEST OF THE 6TH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO, BEING A PORTION OF THAT TRACT OF LAND DESCRIBED UNDER RECEPTION NO. 202131510 OF THE RECORDS OF SAID COUNTY, SAID PARCEL OF LAND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

(BEARINGS REFERED TO HEREIN ARE BASED ON THE NORTH LINE OF THE NORTHEAST QUARTER OF SAID SECTION 7, SAID LINE BEING MONUMENTED AT HE WEST END BY A 3" ALUMINUM CAP STAMPED WITH COLORADO REGISTERED LAND SURVEYOR NO. 17664, AND MONUMENTED AT THE EAST END BY A 2" ALUMINUM CAP STAMPED WITH COLORADO REGISTERED LAND SURVEYOR NO. 17665, SAID LINE IS ASSUMED TO BEAR N89°08'49"W)

COMMENCING AT THE NORTHWEST CORNER OF "ARROWHEAD ESTATES FILING NO.1" AS DESCRIBED IN PLAT BOOK Y-3, PAGE 39 OF THE RECORDS OF SAID COUNTY; SAID CORNER ALSO BEING THE NORTHWEST CORNER OF LOT 13, OF SAID "ARROWHEAD ESTATES FILING NO.1";

THENCE S88°55'09"E, ALONG SAID NORTHERLY LINE, A DISTANCE OF 415.41 FEET TO THE POINT OF BEGINNING;

THENCE N16°00'57"W A DISTANCE OF 361.04 FEET TO A POINT OF NON-TANGENT CURVE TO THE RIGHT;

THENCE ON THE ARC OF SAID CURVE, HAVING A RADIUS OF 565.00 FEET, A DELTA ANGLE OF 05°30'50", AN ARC LENGTH OF 54.37 FEET, WHOSE LONG CHORD BEARS N78°42'31"E A DISTANCE OF 54.35 FEET;

THENCE N08°32'04"W A DISTANCE OF 26.64 FEET TO A POINT OF CURVE TO THE LEFT;

THENCE ON THE ARC OF SAID REVERSE CURVE, HAVING A RADIUS OF 700.00 FEET, A DELTA ANGLE OF 15°31'41", AN ARC LENGTH OF 189.71 FEET, WHOSE LONG CHORD BEARS N16°17'54"W A DISTANCE OF 189.13 FEET TO A POINT OF REVERSE CURVE;

THENCE ON THE ARC OF SAID CURVE, HAVING A RADIUS OF 500.00 FEET, A DELTA ANGLE OF 24°55'00", AN ARC LENGTH OF 217.44 FEET, WHOSE LONG CHORD BEARS N11°36'14"W A DISTANCE OF 215.73 FEET;


THENCE N00°51'15"E A DISTANCE OF 78.63 FEET TO A POINT ON THE SOUTHERLY RIGHT OF WAY LINE OF RIO ROAD, A 60 FOOT WIDE RIGHT OF WAY SHOWN ON "FALCON RANCH ESTATES SUBDIVISION" AS RECORDED IN PLAT BOOK T-2 AT PAGE 47 OF SAID RECORDS;

THENCE S89°08'45"E, ALONG SAID SOUTHERLY RIGHT OF WAY LINE, A DISTANCE OF 1041.23 FEET;

THENCE S00°13'30"E A DISTANCE OF 856.92 FEET TO THE NORTHERLY LNE OF SAID "ARROWHEAD ESTATES FILING NO.1";


THENCE N88°55'09"W, ALONG SAID NORTHERLY LINE, A DISTANCE OF 899.08 FEET TO THE POINT OF BEGINNING.

THE ABOVE TRACT OF LAND CONTAINS 839,151 SQUARE FEET OR 19.265 ACRES, MORE OR LESS.



OVERALL SITE KEY MAP

VICINITY MAP



Site Data


OWNER:
FALCON FIELDS LLC.
3230 N ELECTRA DR
COLORADO SPRINGS CO, 80906

Site Location:
Tax ID Numbers:
Master Plan:
Existing Zoning:
Proposed Zoning:

Current Use:
Proposed Use:

PREPARED BY:
NES INC.
619 N. CASCADE AVE STE 200
COLORADO SPRINGS CO 80903

Highway 24 & East Woodmen Rd.
4307200015 & 4307000001
Falcon/Peyton Small Area Plan
CR Resolution No. 20-160
Parcel South RM-12 (18.5 AC)
Parcel East RS-5000 (19.2 AC)
Agricultural Grazing Land
Residential



N.E.S. Inc.
619 N. Cascade Avenue, Suite 200
Colorado Springs, CO 80903
Tel. 719.471.0073
Fax 719.471.0267
www.nescolorado.com

© 2012. All Rights Reserved.

FALCON FIELD

HIGHWAY 24 &
EAST WOODMEN RD.

DATE: 09.22.2021
PROJECT MGR: J. ROMERO
PREPARED BY: B.ITEN



DATE:	BY:	DESCRIPTION:

COVERSHEET

1

OF 2

P:\Mike Berger\East Woodmen & Highway 24 - Falcon\Drawings\Planning\Drawings\Falcon Fields - rezoning.dwg (2-Plan) 9/22/2021 12:51:57 PM biten



Land Planning
Landscape Architecture
Urban Design

N.E.S. Inc.
619 N. Cascade Avenue, Suite 200
Colorado Springs, CO 80903

Tel. 719.471.0073
Fax 719.471.0267

www.nescolorado.com

© 2012. All Rights Reserved.

PLANNER / LANDSCAPE ARCHITECT
IN ASSOCIATION WITH

FALCON FIELD

HIGHWAY 24 & EAST WOODMEN RD.

DATE: 09.22.2021
PROJECT MGR: J. ROMERO
PREPARED BY: B. ITTEN

DATE:	BY:	DESCRIPTION:

REZONE MAP

2
OF 2