

August 27, 2024

Ellicott Sand and Gravel, LLC.
 235 S. Franceville Coal Mine Road
 Colorado Springs, Colorado 80929

Attention: Mr. Perry Hastings

Subject: Gradation Analysis, -200 Wash
 Class 6 Road Base – Asphalt Concrete Recycling
 Colorado Springs, Colorado
 Project No. CS19156.000F-400

Gentlemen:


As requested, we performed a gradation analysis and a -200 wash on a sample of road base material from Asphalt Concrete Recycling submitted on August 9, 2024. Testing was performed in accordance with applicable ASTM and CDOT Standards. The test results are presented below:

Sieve Size	Percent Passing	CDOT Specifications Class 6
1"	100	100
3/4"	100	95-100
1/2"	81	-
3/8"	74	-
No. 4	56	30-65
No. 8	43	25-55
No. 16	31	-
No. 30	21	-
No. 50	13	-
No. 100	8	-
No. 200	5.2	3-12
Moisture:	11.6	-
Date Sampled:	08/09/2024	

If we can be of further service, please call.

Respectfully submitted,

CTL | THOMPSON, INC.



Daniel Harford
 Senior Engineering Technician

DH:vc

Via Email: gatewaytrucking@gmail.com