


COLORADO SPRINGS UTILITIES LOCH FYNE 20" GAS PIPELINE

LEGEND

EXISTING GAS LINE	
GAS LINE TO BE ABANDONED	
EXISTING GAS VALVE	
PURGE POINT	
PROPOSED GAS LINE	
ROW/PROPERTY LINE	
EDGE OF PAVEMENT/SIDEWALK	
ELECTRIC—OVERHEAD	
ELECTRIC—UNDERGROUND	
PHONE UNDERGROUND	
PHONE UNDERGROUND ABANDON	
FIBER OPTIC	
FIBER OPTIC ABANDON	
STORM WATER	
WATER	
FENCE (ALL)	
PERM. GAS EASEMENT	
TEMP. GAS EASEMENT	
UTILITY PEDESTALS	
MANHOLE	
POWER POLE	
BOLLARD	
IRON PIN FOUND	
POST	
SIGN	
RIP—RAP	



DRAWING PREPARATION NOTE:

THE DRAWINGS COMPLETED IN THIS PACKAGE WERE PREPARED FROM VARIOUS SOURCES. IN SOME INSTANCES DISCREPANCIES MAY EXIST BETWEEN THE VARIOUS SOURCES, ESPECIALLY RELATED TO LOCATION OF EXISTING UTILITIES THAT MAY EXIST AND THE ACTUAL LOCATIONS WHERE UTILITIES NOT YET INSTALLED ARE PLACED.

PATRICK ENGINEERING COMPLETED A SURVEY OF THE PROJECT INCLUDING POT HOLING UTILITIES WHERE FOUND BY SURVEY AND SUE SOURCES.

THE FOLLOWING SOURCES WERE USED:

CSU PROVIDED DRAWING INFORMATION RELATED TO THE TIE-IN OF THE 16" GAS MAIN THAT THE 20" PIPELINE WILL CONNECT TOO, AND THEIR RELOCATION OF THE LOW PRESSURE GAS MAIN ALONG THE EAST SIDE OF BLACK FOREST RD.

CSU ALSO PROVIDE DRAWINGS FOR THE PROPOSED PROJECT WORK ALONG VOLLMER RD. PREPARED BY JR ENGINEERING.

TERRA TECHNOLOGIES PROVIDE DRAWINGS RELATED TO REPLACEMENT OF CENTURYLINK'S FIBER AND TELEPHONE RELOCATIONS AT BLACK FOREST ROAD.

THE BLACK FOREST RD. PROJECT WAS PREPARED AND PROVIDED BY AECOM.

PATRICK ENGINEERING DOES NOT TAKE RESPONSIBILITY FOR THESE DESIGNS PROVIDED BY OTHERS. PATRICK ENGINEERING UTILIZED THEM AS THE BEST SOURCE OF INFORMATION TO DETERMINE THE ROUTE OF THE GAS MAIN.

CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES, AND UTILITIES THAT ARE NOT INSTALLED YET, BUT ARE EXPECTED TO BE IN PLACE PRIOR TO THE CONSTRUCTION OF THE GAS MAIN.

IF THERE ARE ANY CONFLICTS FOUND THAT CANNOT BE ADJUSTED IN THE FIELD THAT REQUIRE AN ENGINEERING EVALUATION, CONTACT PATRICK ENGINEERING.

TRANSITION WELDS - CONNECTION METHOD NOTE:

IF WALL THICKNESS BETWEEN PIPE ENDS OR PIPE FITTING ENDS EXCEED 3/32" OR 0.09375". REQUEST FOR ENGINEERING APPROVAL OF A TRANSITION PIPE WHEN AVAILABLE TO ELIMINATE THE NEED FOR BACK WELDING AND TAPER BORES. WHEN BACK WELDING AND/OR TAPER BORE IS REQUIRED INDICATE LOCATION AND METHOD OF EACH CONNECTION MADE ON THE WELD DIAGRAM NEXT TO THE WELD NO.

GPS WELDS NOTE:

GPS ALL NEW WELDS AND EXISTING WELDS THAT ARE UNCOVERED IN THE TRENCH DURING CONSTRUCTION. ENSURE ALL WALL THICKNESS, AND OTHER PIPE INFORMATION AND WELD INFORMATION IS RECORDED.


DESIGN PIPE SUMMARY		ABANDONED PIPE SUMMARY	
DESIGN QUANTITY	DESCRIPTION	ABANDONED QUANTITY	DESCRIPTION
8727	20" PIPE, STL, 0.375", API 5L-X52, FBE	2464	12" FBE 0.219 WT X-42
1440	20" PIPE, STL, 0.375", API 5L-X52, FBE/ARO	4807	12" TAR COAT
40	10" PIPE, STL, 0.365", API 5L-X52, FBE	1000	16" TAR WRAP
40	2" PIPE, STL, 0.154", ASTM A-105, FBE	5	1" XTRU

BLACK FOREST ROAD OPEN CUT ROAD CROSSING

SCALE 1" = 500'

SHEET INDEX

PG. #	DWG. #	DWG. TITLE	PG. #	DWG. #	DWG. TITLE
1	COVER	COVER SHEET	30	C-206	PLAN & PROFILE 18+00-21+00
2	C-100	SIGNATURES SHEET	31	C-207	PLAN & PROFILE 21+00-24+00
3	C-101	PRESSURE TEST SHEET (TEST 1)	32	C-208	PLAN & PROFILE 24+00-27+00
4	C-102	PRESSURE TEST SHEET (TEST 2)	33	C-209	PLAN & PROFILE 27+00-30+00
5	C-103	PRESSURE TEST SHEET (PRETEST HDD)	34	C-210	PLAN & PROFILE 30+00-33+00
6	C-104	PRESSURE TEST SHEET (TEST 3)	35	C-211	PLAN & PROFILE 33+00-36+00
7	C-105	PRESSURE TEST SHEET (TEST 4)	36	C-212	PLAN & PROFILE 36+00-40+00
8	C-106	CONSTRUCTION NOTES	37	C-213	PLAN & PROFILE 40+00-43+00
9	D-100	TRAFFIC CONTROL DETAIL NOTES	38	C-214	PLAN & PROFILE 43+00-46+00
10	D-101	MAINTENANCE OF TRAFFIC DETAILS	39	C-215	PLAN & PROFILE 46+00-49+00
11	D-102	UTILITY TRENCH REPAIR DETAILS	40	C-216	PLAN & PROFILE 49+00-52+00
12	D-103	BEST MANAGEMENT PRACTICES DETAILS - 1	41	C-217	PLAN & PROFILE 52+00-55+00
13	D-104	BEST MANAGEMENT PRACTICES DETAILS - 2 & CLSM	42	C-218	PLAN & PROFILE 55+00-58+00
14	D-105	CLSM SPECIFICATIONS	43	C-219	PLAN & PROFILE 58+00-61+00
15	W-100	WELD, X-RAY, NDT DOCUMENTATION 0+00-5+00	44	C-220	PLAN & PROFILE 61+00-64+00
16	W-101	WELD, X-RAY, NDT DOCUMENTATION 5+00-21+00	45	C-221	PLAN & PROFILE 64+00-66+00
17	W-102	WELD, X-RAY, NDT DOCUMENTATION 21+00-37+00	46	C-222	PLAN & PROFILE 66+00-68+00
18	W-103	WELD, X-RAY, NDT DOCUMENTATION 37+00-56+00	47	C-223	PLAN & PROFILE 68+00-71+00
19	W-104	WELD, X-RAY, NDT DOCUMENTATION 56+00-74+00	48	C-224	PLAN & PROFILE 71+00-74+00
20	W-105	WELD, X-RAY, NDT DOCUMENTATION 74+00-92+00	49	C-225	PLAN & PROFILE 74+00-77+00
21	W-106	WELD, X-RAY, NDT DOCUMENTATION 92+00-101+67	50	C-226	PLAN & PROFILE 77+00-80+00
22	W-107	PIPE, FITTINGS & VALVES LOGS	51	C-227	PLAN & PROFILE 80+00-83+00
23	W-108	WELD LOG	52	C-228	PLAN & PROFILE 83+00-86+00
24	C-200	PLAN & PROFILE 0+00-3+00	53	C-229	PLAN & PROFILE 86+00-89+00
25	C-201	PLAN & PROFILE 3+00-6+00	54	C-230	PLAN & PROFILE 89+00-92+00
26	C-202	PLAN & PROFILE 6+00-9+00	55	C-231	PLAN & PROFILE 92+00-95+00
27	C-203	PLAN & PROFILE 9+00-12+00	56	C-232	PLAN & PROFILE 95+00-98+00
28	C-204	PLAN & PROFILE 12+00-15+00	57	C-233	PLAN & PROFILE 98+00-101+00
29	C-205	PLAN & PROFILE 15+00-18+00	58	C-234	PLAN & PROFILE 101+00-101+70
			59	HDD-001	COTTONWOOD CREEK HDD



CSU SYSTEM MAP
NTS

Add the following EPC statements to the CD plans for approval.

Design Engineer's Statement:
These detailed plans and specifications were prepared under my direction and supervision. Said plans and specifications have been prepared according to the criteria established by the County for detailed roadway, drainage, grading and erosion control plans and specifications, and said plans and specifications are in conformity with applicable master drainage plans and master transportation plans. Said plans and specifications meet the purposes for which the particular roadway and drainage facilities are designed and are correct to the best of my knowledge and belief. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparation of these detailed plans and specifications.

[Name, P.E. # _____] Date _____

Owner/Developer's Statement:
I, the owner/developer have read and will comply with the requirements of the grading and erosion control plan and all of the requirements specified in these detailed plans and specifications.

[Name, Title] Date _____
[Business Name] _____
[Address] _____

El Paso County:
County plan review is provided only for general conformance with County Design Criteria. The County is not responsible for the accuracy and adequacy of the design, dimensions, and/or elevations which shall be confirmed at the job site. The County through the approval of this document assumes no responsibility for completeness and/or accuracy of this document.


Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual, Volumes 1 and 2, and Engineering Criteria Manual as amended.

In accordance with ECM Section 1.12, these construction documents will be valid for construction for a period of 2 years from the date signed by the El Paso County Engineer. If construction has not started within those 2 years, the plans will need to be resubmitted for approval, including payment of review fees at the Planning and Community Development Directors discretion.

Joshua Palmer, P.E. Date _____
County Engineer / ECM Administrator

PUBLIC LANDS	21,806	0.5
PUBLIC LANDS	244,069	5.6
TOTAL DISTURBED AREA	576,083	13.2

Add PCD File No. CDR-231



8902 Vincennes Circle, Suite F
Indianapolis, IN 46268
TEL. (317) 217-1701
www.patrickco.com

PROJ. NO. 22282.003

REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER:	PHONE:
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			SCOTT JENSEN	(719) 668-8196
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	PROJECT MANAGER: MELISSA LINGO	(719) 668-8794
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		CONSTRUCTION LEAD: JOSH RICHARD	(719) 668-3675
NO.	N/A	BY:	DATE:	APPROV:			SHEET NO. 1 OF 59	SCALE: NTS
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	PATRICK ENGINEERING TEAM	
N/A				N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-17, P-18, P-19	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
							APPD. BY: JEREMIAH SMITH	
							LOCH FYNE 20" GAS PIPELINE	
							COLORADO SPRINGS, COLORADO	
							COVER SHEET	
							DWG. NO. COVER	

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\1 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: COVER PLOTTED: Monday, November 14, 2022 - 5:53pm USER: mwest

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-100 PLOTFILE: Monday, November 14, 2022 - 12:43pm USER: mwest

PRESSURE TEST PERFORMED AND VERIFIED BY SIGNATURES
 I HAVE PERFORMED THE PRESSURE TESTS AS SHOWN ON THE AS-BUILT AND IN ACCORDANCE WITH THE OPERATIONS MANUAL
 I HAVE VALIDATED THE PRESSURE TESTS AS SHOWN ON THE AS-BUILT AND IN ACCORDANCE WITH THE OPERATIONS MANUAL

PRESSURE TEST # _____	PERFORMED BY _____	DATE _____
	VALIDATE BY _____	DATE _____
PRESSURE TEST # _____	PERFORMED BY _____	DATE _____
	VALIDATE BY _____	DATE _____
PRESSURE TEST # _____	PERFORMED BY _____	DATE _____
	VALIDATE BY _____	DATE _____
PRESSURE TEST # _____	PERFORMED BY _____	DATE _____
	VALIDATE BY _____	DATE _____

PURGE PLAN PERFORMED BY SIGNATURE
 PURGE PLAN WAS COMPLETED IN ACCORDANCE WITH THE OPERATIONS MANUAL

PERFORMED BY _____ DATE _____ SHEET# _____
 LOCATION _____

PIPE JOINER VISUAL INSPECTION CERTIFICATION
 I HAVE VISUALLY INSPECTED ALL HEATED FUSIONS, SOLVENT, CEMENT MECHANICAL JOINTS AND WELDS THAT I HAVE PERFORMED

NAME _____ WELDER# _____

PROJECT INSPECTION & OVERSIGHT VERIFIED BY SIGNATURES
 I HAVE PERFORMED INSPECTION AND OVERSIGHT FOR THE INSPECTION WORK ASSIGNED TO ME, VERIFYING THAT THE WORK COMPLETED BY CONTRACTOR, AND WITNESSED BY ME, HAS COMPLIED WITH THE DESIGN REQUIREMENTS, PERMIT REQUIREMENTS, FEDERAL, STATE, COUNTY, AND CITY REQUIREMENTS, AND IN ACCORDANCE WITH CSU' STANDARDS, PROCEDURES, STANDARDS, AND OTHER CONTRACT DOCUMENTS.

CONSTRUCTION LEAD	PERFORMED BY _____	DATE _____
	SIGNATURE _____	DATE _____
WELD/NDT INSPECTOR	PERFORMED BY _____	DATE _____
	SIGNATURE _____	DATE _____
HDD INSPECTOR	PERFORMED BY _____	DATE _____
	SIGNATURE _____	DATE _____
TEST INSPECTOR	PERFORMED BY _____	DATE _____
	SIGNATURE _____	DATE _____
UTILITY INSPECTOR 1	PERFORMED BY _____	DATE _____
	SIGNATURE _____	DATE _____
UTILITY INSPECTOR 2	PERFORMED BY _____	DATE _____
	SIGNATURE _____	DATE _____

ONE PERSON MAY BE ASSIGNED TO ONE OR MORE OF THESE INSPECTIONS ROLLS. THE PERSON SHALL BE REQUIRED TO SIGN OFF ON EACH ROLL THEY ARE ASSIGNED TOO.

CONSTRUCTION LEAD HAS THE ROLL TO VERIFY THAT ALL THE INSPECTIONS SERVICES HAVE BEEN COMPLETED AND VERIFY THAT THE ASSIGNED INSPECTOR FOR EACH ROLL HAS COMPLETED ALL DOCUMENTATION, REQUIRED AND HAVE THEM SIGNED OFF ABOVE TO ATTEST THAT THE ALL WORK HAS BEEN COMPLETED AS REQUIRED.

CONSTRUCTION LEAD SHALL IN CORPORATE NOTES FROM ALL INSPECTORS, OR OTHER SOURCES ON THIS SHEET.

CONSTRUCTION FIELD NOTES

CONSTRUCTION FIELD NOTES

- Add the following El Paso County Construction Notes:
- Standard Notes for El Paso County Construction Plans
- All drainage and roadway construction shall meet the standards and specifications of the City of Colorado Springs/El Paso County Drainage Criteria Manual, Volumes 1 and 2, and the El Paso County Engineering Criteria Manual.
 - Contractor shall be responsible for the notification and field notification of all existing utilities, whether shown on the plans or not, before beginning construction. Location of existing utilities shall be verified by the contractor prior to construction. Call 811 to contact the Utility Notification Center of Colorado (UNCC).
 - Contractor shall keep a copy of these approved plans, the Grading and Erosion Control Plan, the Stormwater Management Plan (SWMP), the soils and geotechnical report, and the appropriate design and construction standards and specifications at the job site at all times, including the following:
 - El Paso County Engineering Criteria Manual (ECM)
 - City of Colorado Springs/El Paso County Drainage Criteria Manual, Volumes 1 and 2
 - Colorado Department of Transportation (CDOT) Standard Specifications for Road and Bridge Construction
 - CDOT M & S Standards
 - Notwithstanding anything depicted in these plans in words or graphic representation, all design and construction related to roads, storm drainage and erosion control shall conform to the standards and requirements of the most recent version of the relevant adopted El Paso County standards, including the Land Development Code, the Engineering Criteria Manual, the Drainage Criteria Manual, and the Drainage Criteria Manual Volume 2. Any deviations from regulations and standards must be requested, and approved, in writing. Any modifications necessary to meet criteria after-the-fact will be entirely the developer's responsibility to rectify.
 - It is the design engineer's responsibility to accurately show existing conditions, both onsite and offsite, on the construction plans. Any modifications necessary due to conflicts, omissions, or changed conditions will be entirely the developer's responsibility to rectify.
 - Contractor shall schedule a pre-construction meeting with El Paso County Planning and Community Development (PCD) – Inspections, prior to starting construction.
 - It is the contractor's responsibility to understand the requirements of all jurisdictional agencies and to obtain all required permits, including but not limited to El Paso County Erosion and Stormwater Quality Control Permit (ESQCP), Regional Building Floodplain Development Permit, U.S. Army Corps of Engineers-issued 401 and/or 404 permits, and county and state fugitive dust permits.
 - Contractor shall not deviate from the plans without first obtaining written approval from the design engineer and PCD. Contractor shall notify the design engineer immediately upon discovery of any errors or inconsistencies.
 - All storm drain pipe shall be Class III RCP unless otherwise noted and approved by PCD.
 - Contractor shall coordinate geotechnical testing per ECM standards. Pavement design shall be approved by El Paso County PCD prior to placement of curb and gutter and pavement.
 - All construction traffic must enter/exit the site at approved construction access points.
 - Sight visibility triangles as identified in the plans shall be provided at all intersections. Obstructions greater than 18 inches above flowline are not allowed within sight triangles.
 - Signing and striping shall comply with El Paso County DOT and MUTCD criteria. [If applicable, additional signing and striping notes will be provided.]
 - Contractor shall obtain any permits required by El Paso County DOT, including Work Within the Right-of-Way and Special Transport permits.
 - The limits of construction shall remain within the property line unless otherwise noted. The owner/developer shall obtain written permission and easements, where required, from adjoining property owner(s) prior to any off-site disturbance, grading, or construction.



8902 Vincennes Circle, Suite F
 Indianapolis, IN 46268
 TEL: (317) 217-1701
 www.patrickco.com

PROJ. NO. 22282.003

REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
4	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				
3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
NO.	N/A	BY:	DATE:	APPVD:			SHEET NO. 2 OF 59	SCALE: NTS
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	PATRICK ENGINEERING TEAM	
N/A				N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A				N/A	SYSTEM MAOP:	3789816	APPD. BY: JEREMIAH SMITH	
N/A				N/A	SYSTEM MOP:		LOCH FYNE 20" GAS PIPELINE	
N/A				N/A			COLORADO SPRINGS, COLORADO	
N/A				N/A			SIGNATURES SHEET	
N/A				N/A			DWG. NO. C-100	

MAINLINE AIR TEST DETAIL & PROCEDURE TM2

MAOP DETERMINED USING THE FOLLOWING TEST METHODS FOR SPECIFIED SECTIONS

- TM1 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH WATER (150 HYDRO)
- TM2 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH AIR, NITROGEN, OR NATURAL GAS (150 OTHER)

DETAIL NOTES
1. TEST THE VALVES IN THE OPEN POSITION..

AS-BUILT DRAWING—PRESSURE TEST DATA TEST # _____

DESCRIPTION: _____ TEST MEDIUM _____ TEST METHOD _____

AIR GAUGE
 NITROGEN CHART
 WATER SOAP
 NATURAL GAS

DESCRIPTION POINTS _____

PIPE DIA. _____ GAUGE SN# _____

TOTAL LENGTH _____ PRESSURE REC SN# _____

PRESSURE (ALL TESTS) (START) _____ (STOP) _____

PRESSURE (CHART ONLY) (MIN) _____ (MAX) _____

TIME (START) _____ (STOP) _____

DATE (START) _____ (STOP) _____


INTERMEDIATE LEAK TEST YES NO

LEAK SURVEY WR# (NATURAL GAS TEST ONLY) _____

ANY LEAKS OR FAILURES ON A TEST YES NO

IF YES, NOTE THE LEAKS AND FAILURES AND THEIR DISPOSITION: _____

PERFORMED BY (PRINT NAME AND EMPLOYEE # OR CONTRACTOR #): _____



COLORADO SPRINGS UTILITIES

RECORD OF STEEL PIPELINES FOR 145 PSIG MOP OPERATION

Designer instructions PLEASE ENTER THE DATA REQUESTED ON THE HIGHLIGHTED CELLS IN SECTIONS I THROUGH IV OF THIS FORM. DESIGN PRESSURE OF WEAKEST PIPE/COMPONENT MUST EQUAL OR EXCEED DESIRED MAOP.

I. JOB DESCRIPTION/LOCATION: Loch Fyne 20" Gas Line Relocation GRID: R-18
TEST DETAIL (IF APPLICABLE): TEST 1 McClintock Station to Station 2+00 20" Piping and 10" and 2" LP System Tie-in.

A. CLASS LOCATION: 3 **F. TEST DURATION REQUIRED:** 2 HR **W.R. #** 3747144
B. MOP: 145 **G. TEST MEDIUM REQUIRED:** Air **RELATED W.R. #** _____
C. DESIRED MAOP: 275
D. TEST PRESSURE (MIN): 413 **H. TEST PRESS (MIN) MULTIPLE:** 1.5
E. TEST PRESSURE (MAX): 433 **I. TEST PRES (MAX) ADJUSTER:** 20

II. ITEMS LISTED IN THIS SECTION MUST BE PRESSURE TESTED

II. A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2S/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

Insert/Delete Selected Row :

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	COMPONENT SPECIFICATION	DURING TEST															
						AT MOP		AT MAOP		MINIMUM		MAXIMUM		SMYS		SMYS%		SMYS%			
SMYS	WT (t)	D	F	E	T	P	σ_h	%SMYS	σ_h	%SMYS	σ_h	SMYS%	σ_h	SMYS%	σ_h	SMYS%					
1	240-375-920	200			20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2	
7	240-154-238	40			2" PIPE, STL, 0.154" WT, ASTM A-105, FBE	35000	0.154	2.375	0.5	1	1	975	1118	3.2	2121	6.1	3181	9.1	3335	9.5	
6	240-365-910	40			10" PIPE, STL, 0.365" WT, API 5L-X52, FBE	52000	0.365	10.750	0.5	1	1	975	2135	4.1	4050	7.8	6074	11.7	6369	12.2	
3	220-647-920	4			20" ELBOW, 0.375 WT, STL, 45 DEG, 3R, WPHY S2	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2	
4	220-692-920	2			20" ELBOW, 0.375 WT, STL, 90 DEG, 3R, WPHY S2	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2	
8	220-692-910	1			10" ELBOW, 0.365 WT, STL, 90 DEG, 3R, WPHY S2	52000	0.365	10.750	0.5	1	1	1766	2135	4.1	4050	7.8	6074	11.7	6369	12.2	
10	215-790-100	1			REDUCER, CONC, 12"x10", 0.375x0.365", WPHY-S2	52000	0.375	12.750	0.5	1	1	1529	2465	4.7	4875	9.0	7013	13.5	7353	14.1	
9	215-742-900	1			REDUCER, CONC, 20"x12", 0.375x0.375", WPHY-S2	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2	
11	280-700-920	1			20" TEE, WELD, WT, 0.375", CS, WPHY-S2	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2	
TARE 1	209-700-920	2			20" CAP, WELD, WPHY-S2, CARBON STEEL, 0.375" WT	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2	
TARE 2	209-700-200	1			2" CAP, WELD, WPHY-S2, CARBON STEEL, 0.154" W	52000	0.154	2.375	0.5	1	1	3372	1118	2.2	2121	4.1	3181	6.1	3335	6.4	
TARE 3	209-700-910	1			10" CAP, WELD, WPHY-S2, CARBON STEEL, 0.365" WT	52000	0.365	10.750	0.5	1	1	1766	2135	4.1	4050	7.8	6074	11.7	6369	12.2	

II. B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS INSERT/DELETE ROWS:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)
12	254-960-058	1			WELD-O-LET 2"x20", CS, ASTM A105	3000	
13	290-100-920	1			VALVE, BALL, 20", API 6D CL150, VERTICAL GEAR OPER., FULL PORT	285	450
14	290-100-911	1			VALVE, BALL, 10", API 6D CL150, VERTICAL GEAR OPER., FULL PORT	285	450
15	290-100-200	1			VALVE, BALL, CLISO, VERTICAL GEAR OPER., WELD END, 2" 0.154"	285	450

III. ITEMS LISTED IN THIS SECTION ARE SINGLE PRE-CERTIFIED COMPONENT INSTALL ONLY. PRESSURE TEST NOT REQUIRED. SOAP TEST REQUIRED.

III. A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2S/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	SMYS	WT (t)	D	F	E	T	P	σ_h	%SMYS	σ_h	%SMYS

III. B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)

IF, DURING THE TEST, THE PIPELINE IS TO BE STRESSED TO 20% OF SMYS OR GREATER AND THE TEST MEDIUM IS OTHER THAN WATER, A SPECIAL LEAK SURVEY OR LEAK TEST IS REQUIRED. IF APPLICABLE, CONDUCT THE SPECIAL LEAK TEST OR SURVEY AT 100 PSIG AND HOLD PRESSURE AT THIS LEVEL FOR A MINIMUM OF 10 MIN. CONDUCT LEAK SURVEY IF NATURAL GAS IS USED. SUBSTITUTION OR ADDITION OF MATERIAL LISTED ON THIS SHEET IS NOT PERMITTED UNLESS APPROVED BY ENGINEERING SUPERVISOR.

CALC/ANALYSIS BY: _____ DATE: _____ ENGINEERING SUPERVISOR'S APPROVAL: _____ DATE: _____

ENGINEERING REMARKS: _____

IV. INFORMATION TO BE SUPPLIED BY TEST PERSONNEL

A. TEST PERFORMED BY: _____ COMPANY: _____ TEST # _____

B. (SIGNATURE): _____ TEST DATE: _____

C. LOCATION OF TEST: _____

D. FACILITY TESTED: REGULATOR STATION (SPOOL (FAB SHOP) MAIN OTHER (SPECIFY IN REMARKS)

E. TEST MEDIUM (CHECK AIR #NAME? NATURAL GAS INERT GAS (NITROGEN) WATER

F. TEST PRESSURE: MAX (PSIG): _____ MIN (PSIG): _____

G. TEST DURATION: START TIME: _____ END TIME: _____ DURATION (HR:MIN): _____

H. TEST PRESSURE DOC MECHANICAL CHART GAUGE OTHER

I. RECORDING DEVICE NO: _____ CALIBRATION DUE DATE: _____

J. LEAK TEST CONDUCTED: YES* IF YES, IDENTIFY METHOD(S) LEAK SURVEY SOAP TEST INTERMEDIATE LEAK TEST (100 PSIG MINIMUM) NO

K. PIPE MANUFACTURER'S NAME: _____ P.O. NO: _____ HEAT CODE NO: _____

L. WELDING ELECTRODE MFR: _____ PART NUMBER: _____ LOT NUMBER: _____

REMARKS: _____

CSU REPRESENTATIVE (Sign/Print): _____ DATE: _____

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs\8-22-22.dwg LAYOUT NAME: C-101 PLOTTED: Tuesday, November 15, 2022 - 7:25am USER: nwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
4	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 3 OF 59	SCALE: NTS
N/A				SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	3747144	PATRICK ENGINEERING TEAM	
N/A				SYSTEM MOP: 145 psig	DISTRIBUTION: <input checked="" type="checkbox"/>	RELATED W/O #s	DWN BY: NORM WEST CHKD BY: SETH BROWN APPD BY: JEREMIAH SMITH	
PERMIT INFORMATION				ISOLATION AREA	FEEDER: <input type="checkbox"/>	3789816	LOCH FYNE 20" GAS PIPELINE	
N/A				LOCATION	TRANS. BY DEF. <input type="checkbox"/>		COLORADO SPRINGS, COLORADO	
N/A				ATLAS OR TITLE	TRANS v 20% <input type="checkbox"/>		PRESSURE TEST SHEET (TEST 1)	
N/A				N/A			DWG. NO: C-101	
N/A				SYSTEM MAOP:			PROJ. NO. 22282.003	
N/A				SYSTEM MOP:			COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.	

MAINLINE AIR TEST DETAIL & PROCEDURE TM2

MAOP DETERMINED USING THE FOLLOWING TEST METHODS FOR SPECIFIED SECTIONS

- TM TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH WATER (150 HYDRO)
- TM2 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH AIR, NITROGEN, OR NATURAL GAS (150 OTHER)

COLORADO SPRINGS UTILITIES

Designer Instructions PLEASE ENTER THE DATA REQUESTED ON THE HIGHLIGHTED CELLS IN SECTIONS I THROUGH IV OF THIS FORM. DESIGN PRESSURE OF WEAKEST PIPE/COMPONENT MUST EQUAL OR EXCEED DESIRED MAOP.

RECORD OF STEEL PIPELINES FOR 145 PSIG MOP OPERATION

I. JOB DESCRIPTION/LOCATION: Loch Fyne 20" Gas Line Relocation GRID: Q-19 & R-19
TEST DETAIL (F APPLICABLE): TEST 2 From 2+00 to 46+60

A. CLASS LOCATION: 3 F. TEST DURATION REQUIRED: 24 HR
 B. MOP: 145 G. TEST MEDIUM REQUIRED: Air W.R. # 3747144
 C. DESIRED MAOP: 275 RELATED W.R. #
 D. TEST PRESSURE (MIN): 413 H. TEST PRESS (MIN) MULTIPLIER: 1.5
 E. TEST PRESSURE (MAX): 433 I. TEST PRESS (MAX) ADJUSTER: 20

II. ITEMS LISTED IN THIS SECTION MUST BE PRESSURE TESTED

II.A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2S/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

Insert/Delete Selected Row:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	COMPONENT SPECIFICATION	SMYS	WT (t)	D	F	E	T	P	AT MOP		AT MAOP		DURING TEST			
													σ_h	%SMYS	σ_h	%SMYS	σ_h	SMYS%	σ_h	SMYS%
1	240-375-920	4480			20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
3	220-647-920	5			20" ELBOW, 0.375 WT, STL, 45 DEG, 3R, WPHY 52	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
4	220-692-920	6			20" ELBOW, 0.375 WT, STL, 90 DEG, 3R, WPHY 52	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
TARE 1	209-700-920	2			20" CAP, WELD, WPHY52, CARBON STEEL, 0.375"	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2

II.B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS INSERT/DELETE ROWS:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING	MANUFACTURER'S TEST PRESSURE (PSIG)

III. ITEMS LISTED IN THIS SECTION ARE SINGLE PRE-CERTIFIED COMPONENT INSTALL ONLY. PRESSURE TEST NOT REQUIRED. SOAP TEST REQUIRED.

III.A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2S/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	SMYS	WT (t)	D	F	E	T	P	AT MOP		AT MAOP	
												σ_h	%SMYS	σ_h	%SMYS

III.B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)

IF, DURING THE TEST, THE PIPELINE IS TO BE STRESSED TO 20% OF SMYS OR GREATER AND THE TEST MEDIUM IS OTHER THAN WATER, A SPECIAL LEAK SURVEY OR LEAK TEST IS REQUIRED. IF APPLICABLE, CONDUCT THE SPECIAL LEAK TEST OR SURVEY AT 100 PSIG AND HOLD PRESSURE AT THIS LEVEL FOR A MINIMUM OF 10 MIN. CONDUCT LEAK SURVEY IF NATURAL GAS IS USED. SUBSTITUTION OR ADDITION OF MATERIAL LISTED ON THIS SHEET IS NOT PERMITTED UNLESS APPROVED BY ENGINEERING SUPERVISOR.

CALC/ANALYSIS BY: _____ DATE: _____ ENGINEERING SUPERVISOR'S APPROVAL: _____ DATE: _____

ENGINEERING REMARKS: _____

IV. INFORMATION TO BE SUPPLIED BY TEST PERSONNEL

A. TEST PERFORMED BY: _____ COMPANY: _____ TEST # _____

B. (SIGNATURE): _____ TEST DATE: _____

C. LOCATION OF TEST: _____

D. FACILITY TESTED: REGULATOR STATION SPOOL (FAB SHOP) MAIN OTHER (SPECIFY IN REMARKS)

E. TEST MEDIUM (CHECK AIR #NAME? NATURAL GAS INERT GAS (NITROGEN) WATER

F. TEST PRESSURE: MAX (PSIG): _____ MIN (PSIG): _____

G. TEST DURATION: START TIME: _____ END TIME: _____ DURATION (HR/MIN): _____

H. TEST PRESSURE DOC MECHANICAL CHART GAUGE OTHER

I. RECORDING DEVICE NO: _____ CALIBRATION DUE DATE: _____

J. LEAK TEST CONDUCTED: YES* IF YES, IDENTIFY METHOD(S) LEAK SURVEY SOAP TEST INTERMEDIATE LEAK TEST (100 PSIG MINIMUM) NO

K. PIPE MANUFACTURER'S NAME: _____ P.O. NO.: _____ HEAT CODE NO.: _____

L. WELDING ELECTRODE MFR: _____ PART NUMBER: _____ LOT NUMBER: _____

REMARKS: _____

CSU REPRESENTATIVE (Sign/Print): _____ DATE: _____

AS-BUILT DRAWING—PRESSURE TEST DATA TEST # _____

DESCRIPTION: _____ TEST MEDIUM _____ TEST METHOD _____

AIR GAUGE
 NITROGEN CHART
 WATER SOAP
 NATURAL GAS

DESCRIPTION POINTS: _____

PIPE DIA. _____ GAUGE SN# _____

TOTAL LENGTH _____ PRESSURE REC SN# _____

PRESSURE (ALL TESTS) (START) _____ (STOP) _____

PRESSURE (CHART ONLY) (MIN) _____ (MAX) _____

TIME (START) _____ (STOP) _____

DATE (START) _____ (STOP) _____


INTERMEDIATE LEAK TEST YES NO

LEAK SURVEY WR# (NATURAL GAS TEST ONLY) _____





ANY LEAKS OR FAILURES ON A TEST YES NO

IF YES, NOTE THE LEAKS AND FAILURES AND THEIR DISPOSITION: _____

PERFORMED BY (PRINT NAME AND EMPLOYEE # OR CONTRACTOR #): _____



FILE NAME: P:\indianapolis\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs\3-8-22.dwg LAYOUT NAME: C-102 PLOT/ED: Monday, November 14, 2022 - 12:43pm USER: mwest

 Colorado Springs Utilities <i>It's how we're all connected</i>	 JEREMIAH SMITH PROFESSIONAL ENGINEER No. 2022-11-15 09:27:46-09:00	 PATRICK ENGINEERING 8902 Vincennes Circle, Suite F Indianapolis, IN 46268 TEL. (317) 217-1701 www.patrickco.com PROJ. NO. 22282.003	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2">REVISIONS</th> <th>SYSTEM NAME: 150P</th> <th>JOB TYPE:</th> <th>W/O #</th> <th>ENGINEER: SCOTT JENSEN</th> <th>PHONE: (719) 668-8196</th> </tr> </thead> <tbody> <tr> <td>4</td> <td>ISSUED FOR CONSTRUCTION</td> <td>NEW 11/14/22 JMS</td> <td>SYSTEM MAOP: 275 psig</td> <td rowspan="2">3747144</td> <td>PROJECT MANAGER: MELISSA LINGO</td> <td>PHONE: (719) 668-8794</td> </tr> <tr> <td>3</td> <td>100% DESIGN PACKAGE ISSUED FOR REVIEW</td> <td>NEW 10/14/22 JMS</td> <td>SYSTEM MOP: 145 psig</td> <td>CONSTRUCTION LEAD: JOSH RICHARD</td> <td>PHONE: (719) 668-3675</td> </tr> <tr> <td>2</td> <td>90% DESIGN PACKAGE ISSUED FOR REVIEW</td> <td>NEW 8/30/22 JMS</td> <td></td> <td></td> <td>SHEET NO. 4 OF 59</td> <td>SCALE: NTS</td> </tr> <tr> <td colspan="2">N/A</td> <td>BY: _____ DATE: _____ APPVD: _____</td> <td></td> <td></td> <td colspan="2" style="text-align: center;">PATRICK ENGINEERING TEAM</td> </tr> <tr> <td colspan="2">PERMIT INFORMATION</td> <td>ISOLATION AREA</td> <td>LOCATION</td> <td>ATLAS OR TITLE</td> <td colspan="2">DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH</td> </tr> <tr> <td colspan="2">N/A</td> <td>N/A</td> <td>TWN. 12S, RNG. 65W, SECTIONS 33</td> <td>R-19, Q-19</td> <td colspan="2"></td> </tr> <tr> <td colspan="2"></td> <td></td> <td></td> <td></td> <td colspan="2" style="text-align: center;">LOCH FYNE 20" GAS PIPELINE</td> </tr> <tr> <td colspan="2"></td> <td></td> <td></td> <td></td> <td colspan="2" style="text-align: center;">COLORADO SPRINGS, COLORADO</td> </tr> <tr> <td colspan="2"></td> <td></td> <td></td> <td></td> <td colspan="2" style="text-align: center;">PRESSURE TEST SHEET (TEST 2)</td> </tr> <tr> <td colspan="2"></td> <td></td> <td></td> <td></td> <td colspan="2" style="text-align: right;">DWG. NO. C-102</td> </tr> </tbody> </table>	REVISIONS		SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196	4	ISSUED FOR CONSTRUCTION	NEW 11/14/22 JMS	SYSTEM MAOP: 275 psig	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794	3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW 10/14/22 JMS	SYSTEM MOP: 145 psig	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675	2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW 8/30/22 JMS			SHEET NO. 4 OF 59	SCALE: NTS	N/A		BY: _____ DATE: _____ APPVD: _____			PATRICK ENGINEERING TEAM		PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH		N/A		N/A	TWN. 12S, RNG. 65W, SECTIONS 33	R-19, Q-19								LOCH FYNE 20" GAS PIPELINE							COLORADO SPRINGS, COLORADO							PRESSURE TEST SHEET (TEST 2)							DWG. NO. C-102		 Colorado Springs Utilities <i>It's how we're all connected</i>
REVISIONS		SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196																																																																										
4	ISSUED FOR CONSTRUCTION	NEW 11/14/22 JMS	SYSTEM MAOP: 275 psig	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794																																																																										
3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW 10/14/22 JMS	SYSTEM MOP: 145 psig		CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675																																																																										
2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW 8/30/22 JMS			SHEET NO. 4 OF 59	SCALE: NTS																																																																										
N/A		BY: _____ DATE: _____ APPVD: _____			PATRICK ENGINEERING TEAM																																																																											
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH																																																																											
N/A		N/A	TWN. 12S, RNG. 65W, SECTIONS 33	R-19, Q-19																																																																												
					LOCH FYNE 20" GAS PIPELINE																																																																											
					COLORADO SPRINGS, COLORADO																																																																											
					PRESSURE TEST SHEET (TEST 2)																																																																											
					DWG. NO. C-102																																																																											

MAINLINE AIR TEST DETAIL & PROCEDURE TM2

MAOP DETERMINED USING THE FOLLOWING TEST METHODS FOR SPECIFIED SECTIONS

- TM TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH WATER (150 HYDRO)
- TM2 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH AIR, NITROGEN, OR NATURAL GAS (150 OTHER)

AS-BUILT DRAWING—PRESSURE TEST DATA TEST # _____

DESCRIPTION: _____ TEST MEDIUM _____ TEST METHOD _____

AIR GAUGE
 NITROGEN CHART
 WATER SOAP
 NATURAL GAS

DESCRIPTION POINTS _____

PIPE DIA. _____ GAUGE SN# _____

TOTAL LENGTH _____ PRESSURE REC SN# _____

PRESSURE (ALL TESTS) (START) _____ (STOP) _____

PRESSURE (CHART ONLY) (MIN) _____ (MAX) _____

TIME (START) _____ (STOP) _____

DATE (START) _____ (STOP) _____


INTERMEDIATE LEAK TEST YES NO

LEAK SURVEY WR# (NATURAL GAS TEST ONLY) _____

ANY LEAKS OR FAILURES ON A TEST YES NO

IF YES, NOTE THE LEAKS AND FAILURES AND THEIR DISPOSITION: _____

PERFORMED BY (PRINT NAME AND EMPLOYEE # OR CONTRACTOR #): _____



COLORADO SPRINGS UTILITIES

Designer Instructions PLEASE ENTER THE DATA REQUESTED ON THE HIGHLIGHTED CELLS IN SECTIONS I THROUGH IV OF THIS FORM. DESIGN PRESSURE OF WEAKEST PIPE/COMPONENT MUST EQUAL OR EXCEED DESIRED MAOP.

RECORD OF STEEL PIPELINES FOR 145 PSIG MOP OPERATION

I. JOB DESCRIPTION/LOCATION: Loch Fyne 20" Gas Line Relocation GRID: Q-19
 TEST DETAIL (IF APPLICABLE): Pre-HDD Pullback Pipe String

A. CLASS LOCATION: 3 F. TEST DURATION REQUIRED: 8 HR WR # 3747144
 B. MOP: 145 G. TEST MEDIUM REQUIRED: Air RELATED WR # _____
 C. DESIRED MAOP: 275
 D. TEST PRESSURE (MIN): 413 H. TEST PRESS (MIN) MULTIPLIER: 1.5
 E. TEST PRESSURE (MAX): 433 I. TEST PRES (MAX) ADJUSTER: 20

II. ITEMS LISTED IN THIS SECTION MUST BE PRESSURE TESTED

II.A. DESIGN PRESSURE FOR PIPE/BUTT-WELDED FITTING, P=(2St/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

Insert/Delete Selected Row:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	COMPONENT SPECIFICATION	SMYS	WT (t)	D	F	E	T	P	DURING TEST							
													AT MOP		AT MAOP		MINIMUM		MAXIMUM	
													σ_h	%SMYS	σ_h	%SMYS	σ_h	SMYS%	σ_h	SMYS%
2	241-375-920	1530			20" Pipe, STL, 0.375" WT, API 5L-X52, FBE/ARO	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
TARE 1	209-700-920	2			20" CAP. WELD, WPHY52, CARBON STEEL, 0.375" WT	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2

II.B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS INSERT/DELETE ROWS:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING	MANUFACTURER'S TEST PRESSURE (PSIG)

III. ITEMS LISTED IN THIS SECTION ARE SINGLE PRE-CERTIFIED COMPONENT INSTALL ONLY. PRESSURE TEST NOT REQUIRED. SOAP TEST REQUIRED.

III.A. DESIGN PRESSURE FOR PIPE/BUTT-WELDED FITTING, P=(2St/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	SMYS	WT (t)	D	F	E	T	P	AT MOP		AT MAOP	
												σ_h	%SMYS	σ_h	%SMYS

III.B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)

IF, DURING THE TEST, THE PIPELINE IS TO BE STRESSED TO 20% OF SMYS OR GREATER AND THE TEST MEDIUM IS OTHER THAN WATER, A SPECIAL LEAK SURVEY OR LEAK TEST IS REQUIRED. IF APPLICABLE, CONDUCT THE SPECIAL LEAK TEST OR SURVEY AT 100 PSIG AND HOLD PRESSURE AT THIS LEVEL FOR A MINIMUM OF 10 MIN. CONDUCT LEAK SURVEY IF NATURAL GAS IS USED. SUBSTITUTION OR ADDITION OF MATERIAL LISTED ON THIS SHEET IS NOT PERMITTED UNLESS APPROVED BY ENGINEERING SUPERVISOR.

CALC/ANALYSIS BY: _____ DATE: _____ ENGINEERING SUPERVISOR'S APPROVAL: _____ DATE: _____

ENGINEERING REMARKS: _____

IV. INFORMATION TO BE SUPPLIED BY TEST PERSONNEL

A. TEST PERFORMED BY: _____ COMPANY: _____ TEST # _____

B. (SIGNATURE): _____ TEST DATE: _____

C. LOCATION OF TEST: _____

D. FACILITY TESTED: REGULATOR STATION (SPOOL (FAB SHOP) MAIN OTHER (SPECIFY IN REMARKS)

E. TEST MEDIUM (CHECK AIR #NAME? NATURAL GAS INERT GAS (NITROGEN) WATER

F. TEST PRESSURE: MAX (PSIG): _____ MIN (PSIG): _____

G. TEST DURATION: START TIME: _____ END TIME: _____ DURATION (HR:MIN): _____

H. TEST PRESSURE DOC MECHANICAL CHART GAUGE OTHER

I. RECORDING DEVICE NO: _____ CALIBRATION DUE DATE: _____

J. LEAK TEST CONDUCTED: YES* IF YES, IDENTIFY METHOD(S) LEAK SURVEY SOAP TEST INTERMEDIATE LEAK TEST (100 PSIG MINIMUM) NO

K. PIPE MANUFACTURER'S NAME: _____ P.O. NO.: _____ HEAT CODE NO.: _____

L. WELDING ELECTRODE MFR: _____ PART NUMBER: _____ LOT NUMBER: _____

REMARKS: _____

CSU REPRESENTATIVE (Sign/Print): _____ DATE: _____

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-103 PLOTTED: Monday, November 14, 2022 - 12:44pm USER: mwest

 Colorado Springs Utilities <i>It's how we're all connected</i>	 JEREMIAH SMITH PROFESSIONAL ENGINEER No. 2022-11-15 09:27:46-09:00	 PATRICK ENGINEERING 8902 Vincennes Circle, Suite F Indianapolis, IN 46268 TEL. (317) 217-1701 www.patrickco.com PROJ. NO. 22282.003	REVISIONS 4 ISSUED FOR CONSTRUCTION 3 100% DESIGN PACKAGE ISSUED FOR REVIEW 2 90% DESIGN PACKAGE ISSUED FOR REVIEW NO. N/A		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig		JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>		W/O # 3747144 RELATED W/O #s 3789816		ENGINEER: SCOTT JENSEN PROJECT MANAGER: MELISSA LINGO CONSTRUCTION LEAD: JOSH RICHARD SHEET NO. 5 OF 59 SCALE: NTS PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH		PHONE: (719) 668-8196 PHONE: (719) 668-8794 PHONE: (719) 668-3675	
			PERMIT INFORMATION: N/A ISOLATION AREA: N/A LOCATION: TWN. 12S, RNG. 65W, SECTIONS 32 ATLAS OR TITLE: Q-19			SYSTEM MAOP: _____ SYSTEM MOP: _____		TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>		DWG. NO.: C-103		COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.		

MAINLINE AIR TEST DETAIL & PROCEDURE TM2

MAOP DETERMINED USING THE FOLLOWING TEST METHODS FOR SPECIFIED SECTIONS

- TM TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH WATER (150 HYDRO)
- TM2 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH AIR, NITROGEN, OR NATURAL GAS (150 OTHER)

COLORADO SPRINGS UTILITIES

Designer instructions PLEASE ENTER THE DATA REQUESTED ON THE HIGHLIGHTED CELLS IN SECTIONS I THROUGH IV OF THIS FORM. DESIGN PRESSURE OF WEAKEST PIPE/COMPONENT MUST EQUAL OR EXCEED DESIRED MAOP.

RECORD OF STEEL PIPELINES FOR 145 PSIG MOP OPERATION

I. JOB DESCRIPTION/LOCATION: Loch Fyne 20" Gas Line Relocation GRID: Q-19
 TEST DETAIL (F APPLICABLE): TEST 3 HDD section for Cottonwood Creek

A. CLASS LOCATION: 3 F. TEST DURATION REQUIRED: 8 HR W.R # 3747144
 B. MOP: 145 G. TEST MEDIUM REQUIRED: Air RELATED W.R. #
 C. DESIRED MAOP: 275
 D. TEST PRESSURE (MIN): 413 H. TEST PRESS (MIN) MULTIPLE: 1.5
 E. TEST PRESSURE (MAX): 433 I. TEST PRES (MAX) ADJUSTER: 20

II. ITEMS LISTED IN THIS SECTION MUST BE PRESSURE TESTED

II. A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2Si/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

Insert/Delete Selected Row:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	COMPONENT SPECIFICATION	SMYS	WT (t)	D	F	E	T	P	DURING TEST							
													AT MOP		AT MAOP		MINIMUM		MAXIMUM	
													σ_h	SMYS%	σ_h	SMYS%				
2	241-375-920	1530			20" Pipe, STL, 0.375" WT, API 5L-X52, FBE/ARO	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
TARE 1	209-700-920	2			20" CAP, WELD, WPHY52, CARBON STEEL, 0.375" WT	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2

II. B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS INSERT/DELETE ROWS:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)

III. ITEMS LISTED IN THIS SECTION ARE SINGLE PRE-CERTIFIED COMPONENT INSTALL ONLY. PRESSURE TEST NOT REQUIRED. SOAP TEST REQUIRED.

III. A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2Si/D) FET; Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	SMYS	WT (t)	D	F	E	T	P	DURING TEST				
												AT MOP		AT MAOP		MINIMUM
												σ_h	SMYS%	σ_h	SMYS%	

III. B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)

IF, DURING THE TEST, THE PIPELINE IS TO BE STRESSED TO 20% OF SMYS OR GREATER AND THE TEST MEDIUM IS OTHER THAN WATER, A SPECIAL LEAK SURVEY OR LEAK TEST IS REQUIRED. IF APPLICABLE, CONDUCT THE SPECIAL LEAK TEST OR SURVEY AT 100 PSIG AND HOLD PRESSURE AT THIS LEVEL FOR A MINIMUM OF 10 MIN. CONDUCT LEAK SURVEY IF NATURAL GAS IS USED. SUBSTITUTION OR ADDITION OF MATERIAL LISTED ON THIS SHEET IS NOT PERMITTED UNLESS APPROVED BY ENGINEERING SUPERVISOR.

CALC/ANALYSIS BY: _____ DATE: _____ ENGINEERING SUPERVISOR'S APPROVAL: _____ DATE: _____
 ENGINEERING REMARKS: _____

IV. INFORMATION TO BE SUPPLIED BY TEST PERSONNEL

A. TEST PERFORMED BY: _____ COMPANY: _____ TEST # _____
 B. (SIGNATURE): _____ TEST DATE: _____
 C. LOCATION OF TEST: _____
 D. FACILITY TESTED: [] REGULATOR STATION [] SPOOL (FAB SHOP) [] MAIN [] OTHER (SPECIFY IN REMARKS)
 E. TEST MEDIUM (CHECK [] AIR #NAME? [] NATURAL GAS [] INERT GAS (NITROGEN) [] WATER
 F. TEST PRESSURE: MAX (PSIG): _____ MIN (PSIG): _____
 G. TEST DURATION: START TIME: _____ END TIME: _____ DURATION (HR:MIN): _____
 H. TEST PRESSURE DOC [] MECHANICAL CHART [] GAUGE [] OTHER
 I. RECORDING DEVICE NO: _____ CALIBRATION DUE DATE: _____
 J. LEAK TEST CONDUCTED: [] YES* IF YES, IDENTIFY METHOD(S) [] LEAK SURVEY [] SOAP TEST [] INTERMEDIATE LEAK TEST (100 PSIG MINIMUM) [] NO
 K. PIPE MANUFACTURER'S NAME: _____ P.O. NO.: _____ HEAT CODE NO.: _____
 L. WELDING ELECTRODE MFR: _____ PART NUMBER: _____ LOT NUMBER: _____


REMARKS: _____
 CSU REPRESENTATIVE (Sign/Print): _____ DATE: _____

AS-BUILT DRAWING—PRESSURE TEST DATA TEST # _____

DESCRIPTION: _____ TEST MEDIUM _____ TEST METHOD _____

AIR GAUGE
 NITROGEN CHART
 WATER SOAP
 NATURAL GAS

DESCRIPTION POINTS: _____
 PIPE DIA. _____ GAUGE SN# _____
 TOTAL LENGTH _____ PRESSURE REC SN# _____
 PRESSURE (ALL TESTS) (START) _____ (STOP) _____
 PRESSURE (CHART ONLY) (MIN) _____ (MAX) _____
 TIME (START) _____ (STOP) _____
 DATE (START) _____ (STOP) _____
 INTERMEDIATE LEAK TEST YES NO
 LEAK SURVEY WR# (NATURAL GAS TEST ONLY) _____
 ANY LEAKS OR FAILURES ON A TEST YES NO
 IF YES, NOTE THE LEAKS AND FAILURES AND THEIR DISPOSITION: _____
 PERFORMED BY (PRINT NAME AND EMPLOYEE # OR CONTRACTOR #): _____



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-104 PLOT/DWG: Monday, November 14, 2022 - 12:44pm USER: mwest

				REVISIONS 4 ISSUED FOR CONSTRUCTION NEW 11/14/22 JMS 3 100% DESIGN PACKAGE ISSUED FOR REVIEW NEW 10/14/22 JMS 2 90% DESIGN PACKAGE ISSUED FOR REVIEW NEW 8/30/22 JMS NO. N/A BY: DATE: APPVD:		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF: <input type="checkbox"/> TRANS v 20%: <input type="checkbox"/>	W/O # 3747144 RELATED W/O #s 3789816	ENGINEER: SCOTT JENSEN PHONE: (719) 668-8196 PROJECT MANAGER: MELISSA LINGO PHONE: (719) 668-8794 CONSTRUCTION LEAD: JOSH RICHARD PHONE: (719) 668-3675 SHEET NO. 6 OF 59 SCALE: NTS PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH
				PERMIT INFORMATION N/A	ISOLATION AREA N/A	LOCATION TWN. 12S, RNG. 65W, SECTIONS 32	ATLAS OR TITLE Q-19	SYSTEM MAOP: SYSTEM MOP:	PROJ. NO. 22282.003

MAINLINE AIR TEST DETAIL & PROCEDURE TM2

MAOP DETERMINED USING THE FOLLOWING TEST METHODS FOR SPECIFIED SECTIONS

- TM1 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH WATER (150 HYDRO)
- TM2 TEST PRESSURE EXCEEDING OF EQUAL TO 150% MAOP, TESTED WITH AIR, NITROGEN, OR NATURAL GAS (150 OTHER)

AS-BUILT DRAWING—PRESSURE TEST DATA TEST # _____

DESCRIPTION: _____ TEST MEDIUM _____ TEST METHOD _____

AIR GAUGE
 NITROGEN CHART
 WATER SOAP
 NATURAL GAS

DESCRIPTION POINTS _____

PIPE DIA. _____ GAUGE SN# _____

TOTAL LENGTH _____ PRESSURE REC SN# _____

PRESSURE (ALL TESTS) (START) _____ (STOP) _____

PRESSURE (CHART ONLY) (MIN) _____ (MAX) _____

TIME (START) _____ (STOP) _____

DATE (START) _____ (STOP) _____

INTERMEDIATE LEAK TEST YES NO

LEAK SURVEY WR# (NATURAL GAS TEST ONLY) _____

ANY LEAKS OR FAILURES ON A TEST YES NO

IF YES, NOTE THE LEAKS AND FAILURES AND THEIR DISPOSITION: _____

PERFORMED BY (PRINT NAME AND EMPLOYEE # OR CONTRACTOR #): _____

COLORADO SPRINGS UTILITIES

Designer Instructions PLEASE ENTER THE DATA REQUESTED ON THE HIGHLIGHTED CELLS IN SECTIONS I THROUGH IV OF THIS FORM. DESIGN PRESSURE OF WEAKEST PIPE/COMPONENT MUST EQUAL OR EXCEED DESIRED MAOP.

RECORD OF STEEL PIPELINES FOR 145 PSIG MOP OPERATION

I. JOB DESCRIPTION/LOCATION: Loch Fyne 20" Gas Line Relocation GRID: P-18, P-19, Q-19
TEST DETAIL (F APPLICABLE): TEST 4 60+90 to 101+67

A. CLASS LOCATION: 3
B. MOP: 145
C. DESIRED MAOP: 275
D. TEST PRESSURE (MIN): 413
E. TEST PRESSURE (MAX): 433

F. TEST DURATION REQUIRED: 21 HR
G. TEST MEDIUM REQUIRED: Air
H. TEST PRESS (MIN) MULTIPLIER: 1.5
I. TEST PRESS (MAX) ADJUSTER: 20

WR # 3747144
RELATED WR # _____

II. ITEMS LISTED IN THIS SECTION MUST BE PRESSURE TESTED

II. A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2S/D) FET, Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

Insert/Delete Selected Row:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	COMPONENT SPECIFICATION	SMYS	WT (t)	D	F	E	T	P	DURING TEST							
													σ_h	%SMYS	σ_h	%SMYS				
1	240-375-920	4087			20" Pipe, STL, 0.375" WT, API 5L-X52, FBE	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
3	220-647-920	4			20" Elbow, 0.375 WT, STL, 45 Deg, 3R, WPHY 52	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
4	220-692-920	2			20" Elbow, 0.375 WT, STL, 90 Deg, 3R, WPHY 52	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
5	215-796-920	1			REDUCER, CONC, 20"X16", 0.375"X0.375", WPHY-52	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
TARE 1	209-700-920	1			20" CAP, WELD, WPHY52, CARBON STEEL, 0.375" WT	52000	0.375	20.000	0.5	1	1	975	3867	7.4	7333	14.1	11000	21.2	11533	22.2
TARE 4	209-700-916	1			16" CAP, WELD, WPHY52, CARBON STEEL, 0.375" WT	52000	0.375	16.000	0.5	1	1	1219	3093	5.9	5867	11.3	8800	16.9	9227	17.7

II. B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS INSERT/DELETE ROWS:

PLAN REF NO.	ITEM NO.	DESIGN QTY	TESTED QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING	MANUFACTURER'S TEST PRESSURE (PSIG)

III. ITEMS LISTED IN THIS SECTION ARE SINGLE PRE-CERTIFIED COMPONENT INSTALL ONLY. PRESSURE TEST NOT REQUIRED. SOAP TEST REQUIRED.

III. A. DESIGN PRESSURE FOR PIPE/BUTT-WELD FITTING, P=(2S/D) FET, Where E = 1.0, T = 1.0 HOOP STRESS EQUATION, $\sigma_h = PD/2t$

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	SMYS	WT (t)	D	F	E	T	P	AT MOP		AT MAOP	
												σ_h	%SMYS	σ_h	%SMYS

III. B. VALVES, REGULATORS, COMPONENTS AND OTHER FITTINGS

PLAN REF NO.	ITEM NO.	DESIGN QTY	ASBUILT QTY	PRE-CERTIFIED COMPONENTS(S)	MANUFACTURER'S PRESSURE RATING (PSIG)	MANUFACTURER'S TEST PRESSURE (PSIG)

IF, DURING THE TEST, THE PIPELINE IS TO BE STRESSED TO 20% OF SMYS OR GREATER AND THE TEST MEDIUM IS OTHER THAN WATER, A SPECIAL LEAK SURVEY OR LEAK TEST IS REQUIRED. IF APPLICABLE, CONDUCT THE SPECIAL LEAK TEST OR SURVEY AT 100 PSIG AND HOLD PRESSURE AT THIS LEVEL FOR A MINIMUM OF 10 MIN. CONDUCT LEAK SURVEY IF NATURAL GAS IS USED. SUBSTITUTION OR ADDITION OF MATERIAL LISTED ON THIS SHEET IS NOT PERMITTED UNLESS APPROVED BY ENGINEERING SUPERVISOR.

CALC/ANALYSIS BY: _____ DATE: _____ ENGINEERING SUPERVISOR'S APPROVAL: _____ DATE: _____

ENGINEERING REMARKS: _____

IV. INFORMATION TO BE SUPPLIED BY TEST PERSONNEL

A. TEST PERFORMED BY: _____ COMPANY: _____ TEST # _____

B. (SIGNATURE): _____ TEST DATE: _____

C. LOCATION OF TEST: _____

D. FACILITY TESTED: REGULATOR STATION (SPOOL (FAB SHOP) MAIN OTHER (SPECIFY IN REMARKS)

E. TEST MEDIUM (CHECK AIR #NAME? NATURAL GAS INERT GAS (NITROGEN) WATER

F. TEST PRESSURE: MAX (PSIG): _____ MIN (PSIG): _____

G. TEST DURATION: START TIME: _____ END TIME: _____ DURATION (HR:MIN): _____

H. TEST PRESSURE DOC MECHANICAL CHART GAUGE OTHER

I. RECORDING DEVICE NO: _____ CALIBRATION DUE DATE: _____


J. LEAK TEST CONDUCTED: YES* IF YES, IDENTIFY METHOD(S) LEAK SURVEY SOAP TEST INTERMEDIATE LEAK TEST (100 PSIG MINIMUM) NO

K. PIPE MANUFACTURER'S NAME: _____ P.O. NO.: _____ HEAT CODE NO.: _____

L. WELDING ELECTRODE MFR: _____ PART NUMBER: _____ LOT NUMBER: _____

REMARKS: _____

CSU REPRESENTATIVE (Sign/Print): _____ DATE: _____



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\08 Colorado Springs\3-8-22.dwg LAYOUT NAME: C-105 PLOT/DRAW: Monday, November 14, 2022 - 12:44pm USER: mwest

<p style="font-weight: bold;">Colorado Springs Utilities</p> <p style="font-style: italic;">It's how we're all connected</p>	<p style="font-weight: bold;">JEREMIAH SMITH</p> <p>PROFESSIONAL ENGINEER</p>	<p style="font-weight: bold;">PATRICK ENGINEERING</p> <p>PROJ. NO. 22282.003</p>	REVISIONS 4 ISSUED FOR CONSTRUCTION 3 100% DESIGN PACKAGE ISSUED FOR REVIEW 2 90% DESIGN PACKAGE ISSUED FOR REVIEW NO. N/A		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	W/O # 3747144 RELATED W/O #s 3789816	ENGINEER: SCOTT JENSEN PROJECT MANAGER: MELISSA LINGO CONSTRUCTION LEAD: JOSH RICHARD SHEET NO. 7 OF 59 SCALE: NTS PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	PHONE: (719) 668-8196 PHONE: (719) 668-8794 PHONE: (719) 668-3675
			PERMIT INFORMATION: N/A ISOLATION AREA: N/A LOCATION: TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33 ATLAS OR TITLE: Q-19, P-18, P-19 N/A			SYSTEM MAOP: _____ SYSTEM MOP: _____			LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PRESSURE TEST SHEET (TEST 4) DWG. NO. C-105

FILE NAME: P:\indianapolis\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-106 PLOT/DTE: Monday, November 14, 2022 - 12:44pm USER: mwest

TIE-IN PROCEDURES		
STEP NO.	CHECK COMPLETE	PROCEDURE
1		INSTALL ALL MAINS AND FITTINGS PER DRAWINGS
2		INSTALL TEMPORARY 20", 16", 10" AND 2" STEEL END CAPS AS NEEDED FOR PRESSURE TESTING. PRESSURE TEST THROUGH END CAP FITTINGS
3		PRESSURE TEST ALL NEW PIPING IN SEGMENTS PER PRESSURE TEST SHEETS
4		LEAVE APPROX 50 PSIG OF AIR PRESSURE ON COMPLETED SEGMENTS UNTIL READY TO MAKE TIE-INS
5		COMPLETE TIE-INS OF ALL NEW PIPELINE SEGMENTS AFTER ALL PRESSURE TESTS HAVE BEEN COMPLETED
6		WITH THE EXISTING 20" VALVE CLOSED, COMPLETE 20" TIE-IN AT MCCLINTOCK STATION (SHEET C-200)
7		INSTALL BYPASS AND PURGE AND DE-GAS THE EXISTING 10" LINE, AND COMPLETE 10" STEEL TIE-IN AT MCCLINTOCK STATION (SHEET C-200)
8		PURGE AND DE-GAS THE 2" LINE, AND COMPLETE 2" STEEL TIE-IN AT MCLINTOCK STATION (SHEET C-200)
9		COMPLETE TIE-IN OF THE NEW 20" LINE TO THE EXISTING 16" LINE AT FORESTGATE DR. WEST OF BLACK FOREST RD. (SHEET C-234)
10		VERIFY ODORIZER SET UP FOR PURGE OF NEW STEEL PIPE HAS BEEN COMPLETED (SHEET C-200)
11		INSTALL GROUNDED PURGE STACK AT TIE-IN POINT ON FORESTGATE DR WEST OF BLACK FOREST RD. TO BE MANNED BY A QUALIFIED STATION TECHNICIAN WITH CGI AND RADIO. (SHEET C-234)
12		PRIOR TO STARTING PURGE OF THE 20", COMPLETE A TAILGATE MEETING WITH PURGE TEAM ABOUT THE PURGE PROCEDURE, AND COMPLETE A RADIO CHECK.
13		INFORM TECHNICIAN AT THE PURGE LOCATION THAT THE PURGE IS BEGINNING THEN SLOWLY OPEN THE 20' VALVE AT MCCLINTOCK TIE-IN. THROTTLE THROUGH THE VALVE TO CONTROL PUGE RATE (SHEET C-200)
14		TECHNICIAN TO MONITOR PURGE WITH CGI AT FORESTGATE DR AND BLACK FOREST RD, AND VERIFY THAT AT 2 READINGS OF AT LEAST 80% GAS IS RECORDED. TECHNICIAN SHALL INFORM PURGE TEAM THAT PURGE CAN BE COMPLETED, AND CLOSE THE PURGE VENT.
15		VERIFY SUFFICIENT PICKLING OF NEW STEEL PIPE HAS BEEN ACHIEVED
16		VERIFY 20" VALVE AT MCCLINTOCK STATION TIE IN IS FULLY OPEN (SHEET C-200)
17		VERIFY THAT PRESSURE IN THE NEW 20" LOCH FYNE PIPELINE HAS STABILIZED
18		COMPLETE THE TAP ON THE 16" SPHERICAL TEE AT THE WEST TIE-IN TO COMPLETE THE CONNECTION OF THE 20" PIPELINE TO THE 16" PIPELINE (SHEET C-234)
19		INSTALL GROUNDED PURGE VENT AND PURGE AIR FROM THE NEW 10" STEEL LINE AT MCCLINTOCK STATION (SHEET C-200)
20		INSTALL GROUNDED PURGE VENT AND PURGE AIR FROM NEW 2" STEEL LINE AT MCCLINTOCK STATION (SHEET C-200)
21		VERIFY ALL MAINS ARE LOCATABLE

ANY DEVIATIONS FROM PROCEDURES MUST BE COMMUNICATED TO GPD (SCOTT JENSEN 605-430-4798)

- CREW SUPERVISOR TO CHECK OF EACH STEP OF THE PROCEDURE AS IT IS COMPLETED IN THE FIELD
- VERIFY AND ADD TEST STATIONS ACCORDING TO CATHOIC PROTECTION NOTES


TIE-IN PROCEDURE APPROVED BY

NAME	TITLE	SIGNATURE	DATE
SCOTT JENSEN	ENGINEER		
JOSH RICHARD	CONSTRUCTION LEAD		

TIE-IN COMPLETED

NAME	TITLE	SIGNATURE	DATE
SCOTT JENSEN	ENGINEER		
JOSH RICHARD	CONSTRUCTION LEAD		

CATHODIC PROTECTION NOTES	
1 CP	INSTALL TEST STATIONS AT LOCATIONS SHOWN IN THE DESIGN PACKAGE.
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
3 CP	TEST STATIONS SHALL BE ATTACHED PER THE DETAIL BELOW.



CONSTRUCTION NOTES	
1	ALL WORK SHALL BE IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE, COUNTY, AND CITY LAWS AND STANDARDS
2	ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH APPLICABLE CSU STANDARDS AND SPECIFICATIONS.
3	ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH PERMITS ISSUED FOR THE PROJECT
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL HAVE MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
5	IF ROCK IS ENCOUNTERED IN THE TRENCH, CONTRACTOR SHALL INCREASE TRENCH DEPTH BY 1' IN ORDER TO PLACE 12" OF ROCK-FREE PADDING SOIL. PRIOR TO LOWERING THE PIPELINE INTO THE TRENCH.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
7	PRIOR TO BACKFILLING THE TRENCH WHERE ROCK IS PRESENT IN THE BACKFILL, 12" OF ROCK-FREE SOIL SHALL BE FILLED OVER THE TOP OF THE PIPELINE. NO ROCK GREATER THAN 6" WILL BE ALLOWED IN THE REMAINING BACKFILL. NO ROCK WILL BE ALLOWED IN THE TOP 12" OF THE TRENCH.
8	PREFERRED METHOD OF BACKFILLING THE TWO ROAD CROSSING IS USING A CDOT APPROVED EXCAVATABLE FLOWABLE FILL. OTHERWISE THE BACKFILL WILL NEED TO BE COMPACTED IN 6" MAXIMUM LEFTS AND COMPACTED TO 98% PROCTOR READING
9	FOR BOTH ROAD CROSSING, PAVEMENT SHALL BE THE SAME AS THE EXISTING CROSSING.
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
12	THE COTTONWOOD CREEK SHALL BE COMPLETED USING AN HDD IN ACCORDANCE WITH THE HDD DESIGN THAT IS PART OF THIS DESIGN.
13	PRIOR TO PULLING IN THE HDD PIPE STRING, AN AIR TEST WILL BE COMPLETED ON THE PIPE, AFTER PULL BACK, THE PIPE SEGMENT WILL BE AIR TESTED AGAIN.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
4	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 8 OF 59	SCALE: NTS
NO.	N/A	BY:	DATE:	APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	SYSTEM MAOP:	3789816	APPD. BY: JEREMIAH SMITH	
					SYSTEM MOP:		LOCH FYNE 20" GAS PIPELINE	
							COLORADO SPRINGS, COLORADO	
							CONSTRUCTION NOTES	
							DWG. NO. C-106	

**TRAFFIC CONTROL FOR STREET CONSTRUCTION,
UTILITY WORK AND MAINTENANCE OPERATIONS**
CITY OF COLORADO SPRINGS

SPECIFIC REQUIREMENTS

Temporary Traffic Barrier:

The Contractor shall install Pre-cast Type 7F concrete, Type IV concrete, or Plastic Water Filled barrier between any lanes carrying public traffic and any excavation, obstacle, or storage area when the following conditions exist:

- When an excavation is 12 inches or greater in depth a minimum clear zone (CZ) in feet shall be required for the following design speeds:

30 MPH	35 MPH	40 MPH	45 MPH	50 MPH	55 MPH	60 MPH
12' CZ	14' CZ	16' CZ	20' CZ	22' CZ	24' CZ	30' CZ

- If the minimum Clear Zone cannot be maintained, then a temporary traffic barrier shall be required for work site protection.
- A temporary traffic barrier shall be supplemented with standard delineation (reflectors), pavement markings, or channelizing devices to provide nighttime visibility for vehicle traffic. The delineation or pavement marking color shall conform to the latest edition of the MUTCD.
- Temporary traffic barrier ends shall be installed in accordance with AASHTO's "Roadside Design Guide" by flaring until the end is outside the acceptable clear zone (clear zone is based on 85th percentile speed) or by providing crashworthy end treatments that meet or exceed MASH 350 Report.
- A temporary traffic barrier is required when the contractor has installed a permanent obstacle and the protective system, such as guardrail has not been installed or when a portion of an existing protective guardrail has been removed.
- A temporary traffic barrier is required when materials or equipment are stored within the clear zone of the work site.
- The use of a 12 ft. transition section is allowed at the downstream end of the installation pointing away from approaching traffic out of the clear zone, or at locations outside the clear zone, generally more than 30 ft. from the high speed travel lane edge.
- Glare Screens may be required, if used the blade height shall be 24".

Excavation and Trenches:

Excavations and/or trenches, which cannot be properly back-filled and patched prior to the end of the work day, shall be bridged to permit unobstructed traffic flow. Trench walls and adjacent soils shall be sufficiently stabilized prior to the use of steel plates for bridging.

Where traffic must cross trenches:

- The use of steel plates shall be approved by City Traffic Engineering prior to installation.
- The Colorado Springs Fire Department - Heavy Rescue Response Group shall be notified when the excavation or trench is 5 feet or greater in depth.
- Steel Trench Plate width and thickness requirements:

18" or less in width	Minimum thickness of 3/4"
> 18" in width to 72" in width	Minimum thickness of 1"

- The thickness of Steel Plates for trench widths exceeding 72" a structural design shall be prepared by a Licensed Professional Engineer Registered in Colorado.
- Steel Plates can be installed in two ways. First, the Steel Plates can be installed flush with the existing pavement, milling out the pavement surface to ensure that the top of plate elevation matches the existing elevations of adjacent pavement surface. Second, the Steel Plates can be installed on top of the asphalt with transitional ramps (cold mix) on all four sides of the plates, with feathered edges to match the existing asphalt (8% or a lesser slope).
- The Steel Plates shall extend beyond the edge of the trench a minimum of 18" but no more than 30" on both sides.
- A non-skid surface treatment shall be applied to the entire surface area of the plate in the direction of traffic flow.
- The contractor should avoid using a long series of plates that run parallel to traffic wheel paths. If allowed, the length of a series of plates running parallel to traffic wheel paths shall not exceed 30'.
- The trench shall be adequately shored to support the steel plates and traffic loads.
- Steel Plates shall be installed to operate with minimum noise.
- All Steel Plates within the right-of-way, whether used in or out of the traveled way, shall be without deformation (free from any clips, chains, attachments, weldments, or surface irregularities).
- No one is allowed in the trench while covered by the Steel Plate.
- The use of Steel Plates shall not exceed four weeks and Rough Road or Bump signs shall be required during this period of time.

revise the statement accordingly.

DETAIL NOTES

- THE DETAILS ON THE NEXT FOUR SHEETS ARE FROM EL PASO COUNTY DEPARTMENT OF TRANSPORTATION "ENGINEERING CRITERIA MANUAL", THE CITY OF COLORADO SPRINGS "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", AND OTHER ONLINE DETAIL DRAWINGS FROM THE CITY OF COLORADO SPRINGS PUBLIC WORKS DEPARTMENT.
- ONLY THOSE DETAILS THAT APPEAR TO BE MOST APPLICABLE TO THIS PROJECT ARE ATTACHED. HOWEVER, THIS DOES NOT RELIEVE THE CONTRACTOR FROM OBTAINING THESE MANUALS FOR REVIEW FOR OTHER APPLICABLE STANDARDS..
- THERE ARE TWO PAVED ROADS ON THIS PROJECT THAT ARE EXPECTED TO OPEN CUT. THEREFORE, THE DRAWINGS RELATED TO TRENCHING OPERATIONS UNDER THE ROADS, AND PAVEMENT REPAIR AND REPLACEMENT ARE PROVIDED. **IN ADDITION, THESE DETAILS.**
- IF WORK IN THE ROADWAY IS REQUIRED, CONTRACTOR SHALL CONSULT ADDITIONAL MUT DRAWINGS REQUIRED FOR LANE CLOSURES, DETOURS AND TRAFFIC CONTROL DEVICES.
- ENVIRONMENTAL DETAILS WERE DETERMINED TO BE THE MOST APPLICABLE DRAWINGS FOR THIS PROJECT. IF THERE ARE CIRCUMSTANCES THAT ARE NOT COVERED BY THESE STANDARDS, THE CONTRACTOR SHALL WORK WITH CSU TO PROVIDE ADEQUATE BEST MANAGEMENT PRACTICES.

**APPENDIX C
GENERAL GUIDE TO WORK ZONE TRAFFIC CONTROL**

	General Guide to Work Zone Traffic Control									
	Interstate (I)	Expressway (E)	Principal Arterial (PA)	Minor Arterial (MA)	Industrial Commercial	Major Res. Collector	Minor Res. Collector	Residential Street	Minor Residential	Hillside
Number of Traffic Lanes	2-4 L	2-4 L	2-4 L	2-4 L	2-3-4	2-3-4	2-2	2	2	2
ADT	80,000	75,000	15,000 to 25,000	10,000 to 25,000	7,000 to 10,000	5,000 to 10,000	1,000 to 5,000	750 to 100 to 200	100 to 200	200
Time Restrictions (No Work 6 AM to 8 AM & 4 PM to 7 PM)	yes	yes	yes	yes	yes	yes				
Noise Restriction (7 PM to 7 AM in All Residential Areas)			possibly	possibly	possibly	yes	yes	yes	yes	yes
Shoulder Closures Allowed	yes	yes	yes	yes	yes	yes	yes	yes	yes	yes
Stewalk Closures Allowed	yes	yes	yes	yes	yes	yes	yes	yes	yes	yes
Single Lane Closure (8 AM to 3 PM) Allowed	yes-night	yes-night	yes	yes	yes	yes	yes	yes	yes	yes
Multi-Lane Closure (Weekends & Nights) Allowed	note #6	note #6	note #5	yes	yes	yes	yes	yes	yes	yes
Street Closure Allowed	note #6	note #6	note #5	note #6	yes	yes	yes	yes	yes	yes
Night Work Allowed	yes	yes	yes	yes	yes	yes				
Weekend Work Allowed	yes	yes	yes	yes	yes	yes	yes	yes	yes	yes
Flaggers Required			possibly	yes	yes	yes	yes	yes	yes	yes
Detour Routes (reasonable distance w/o cut thru's) Required	yes	yes	yes	yes	yes	yes	yes	yes	yes	yes
Portable VMS's Required	yes	yes	yes	yes	yes	yes				
Arrow Boards Required	yes	yes	yes	yes	possibly	possibly				
Portable Traffic Signals Allowed			yes	yes	yes	yes	yes	yes	yes	yes

Note:
 * This table represents general requirements under average conditions.
 1. All subject to change pending on site evaluation, roadway design, ADT, hourly vpi, speed, # of lanes, weather, time of year, school walk routes, Fire, Transit, and Truck routes.
 2. All roadways which are under CDOT jurisdiction requires CDOT's approval and permit.
 3. Flaggers required for One-Lane Roadways and Truck Access (entering & exiting).
 4. Uniform Traffic Control (UTC) required where traffic is routed against a traffic signal.
 5. Requires extensive coordination with City, County and CDOT and only allowed under extreme conditions.
 6. All requirements subject to City Code.

**APPENDIX D
LETTER CODES & FORMULAS**

LETTER CODES

Road Type	Distance between Signs in Ft (metric)		
	A	B	C
Urban (low speed)	100 (30)	100 (30)	100 (30)
Urban (high speed)	350 (100)	350 (100)	350 (100)
Rural	500 (150)	500 (150)	500 (150)
Expressway / Freeway	1000 (300)	1500 (450)	2640 (800)

Type of Taper	Taper Length (L)*
Merging Taper	At least L
Shifting Taper	At least 0.5 L
Shoulder Taper	At least 0.33 L
One-Lane, Two-Way Traffic Taper	100 ft (30m) maximum
Downstream Taper	100 ft (30m) per lane

FORMULAS

Speed Limits of 40 mph (60 km/h) or less / Speed Limits of 45 mph (70 km/h) or >:

$$L = WS^2 / 60 \quad (L = WS^2 / 155) \quad L = WS \quad (L = WS / 1.6)$$

Lane Width	Speed in MPH	25 MPH	30 MPH	35 MPH	40 MPH	45 MPH	50 MPH	55 MPH	60 MPH	65 MPH
10 ft. Merging Taper	105' 150' 205' 270' 450' 500' 550'									
11 ft. Merging Taper	115' 165' 225' 294' 495' 550' 605'								600' 650'	
12 ft. Merging Taper	125' 180' 245' 320' 540' 600' 660'								660' 715'	
									720' 780'	









Where: L = Taper length in feet (meters)
 W = Width of offset in feet (meters)
 S = Posted speed limit, or off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in mph (km/h)

* Distances are shown in feet (meters)



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig			
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig			
NO.	N/A	BY:	DATE:	APPVD:				
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A			
N/A		N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	SYSTEM MAOP:			
					SYSTEM MOP:			
HP SERVICE: <input type="checkbox"/>						3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
DISTRIBUTION: <input checked="" type="checkbox"/>							CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
FEEDER: <input type="checkbox"/>							SHEET NO. 9 OF 59	SCALE: NTS
TRANS. BY DEF. <input type="checkbox"/>							PATRICK ENGINEERING TEAM	
TRANS v 20% <input type="checkbox"/>							DWN BY: NORM WEST	CHKD. BY: SETH BROWN
						3789816	APPD. BY: JEREMIAH SMITH	
LOCH FYNE 20" GAS PIPELINE								
COLORADO SPRINGS, COLORADO								
TRAFFIC CONTROL NOTES								
								DWG. NO. D-100

FILE NAME: P:\indianapolis\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: D-101 - RLOTTED Monday, November 14, 2022 - 12:44pm USER: mwest



8902 Vincennes Circle, Suite F
Indianapolis, IN 46268
TEL. (317) 217-1701
www.patrickco.com

PROJ. NO. 22282.003

REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	HP SERVICE: <input type="checkbox"/>	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	DISTRIBUTION: <input checked="" type="checkbox"/>		CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	FEEDER: <input type="checkbox"/>		SHEET NO. 10 OF 59	SCALE: NTS
NO.	N/A	BY:	DATE:	APPVD:	TRANS. BY DEF. <input type="checkbox"/>		PATRICK ENGINEERING TEAM	
	PERMIT INFORMATION	ISOLATION AREA	LOCATION	ATLAS OR TITLE	TRANS. v 20% <input type="checkbox"/>	3789816	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
	N/A	N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	SYSTEM MAOP: 145 psig		APPD. BY: JEREMIAH SMITH	





**LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
MAINTENANCE OF TRAFFIC DETAILS**

DWG. NO. D-101

General Notes:

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CURRENT CITY OF COLORADO SPRINGS ENGINEERING DIVISION (THE CITY) STANDARD SPECIFICATIONS.
- THE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS. FOR CITY PERMITS CONTRACTORS SHALL USE THE ACELA ON-LINE PERMIT SYSTEM. ONCE CITY PERMITS ARE APPROVED AND PAID, THEN APPROPRIATE SCHEDULING AND NOTIFICATIONS SHALL BE IN ACELA.
- PRIOR TO CUTTING INTO A ROADWAY, A MEETING IS REQUIRED WITH CITY INSPECTOR.
- EXISTING PAVEMENT MAY BE INITIALLY ROUGH CUT. A SQUARE, VERTICAL CUT SHALL BE MADE IN THE EXISTING ASPHALT PAVEMENT PRIOR TO PAVEMENT PLACEMENT.
- BACKFILL SHALL BE COMPACTED WITH SECTION 206 OF CITY STANDARD SPECIFICATIONS.
- CLSM (FLOW-FILL) IS REQUIRED AS BACKFILL FOR TRENCHES LESS THAN 1-FOOT IN WIDTH. CLSM SHALL NOT EXTEND INTO PAVEMENT SECTION.
- CLSM SHALL BE USED WHERE PAVEMENT SECTION IS LESS THAN 5-YEARS OLD.
- HOT MIX ASPHALT (ASPHALT PAVING MATERIAL) SHALL MEET THE REQUIREMENTS OF THE PIKES PEAK ASPHALT SPECIFICATION AND BE APPROVED BY CITY ENGINEERING.
- NEW ASPHALT SHALL NOT BE PLACED AGAINST FRESHLY POURED CONCRETE. CONCRETE SHALL BE 5-DAYS OLD OR HAVE REACHED A COMPRESSIVE STRENGTH OF 3,200 PSI AS DEMONSTRATED BY FIELD CURE CYLINDERS.
- A TACK COAT SHALL BE APPLIED TO ALL VERTICAL EDGES INCLUDING CONCRETE EDGES. THE TACK COAT SHALL HAVE 100% COVERAGE AND BE APPLIED BETWEEN LIFTS.
- A MINIMUM PAVEMENT SECTION OF:
 - A) RESIDENTIAL/COLLECTOR: SHALL MATCH EXISTING OR A MINIMUM 6-INCHES OF CLASS 6 AGGREGATE BASE COURSE WITH 6-INCHES OF HOT-MIX ASPHALT (ASPHALT PAVING MATERIAL);
 - B) ARTERIAL: 12-INCHES OF CLASS 6 AGGREGATE BASE COURSE WITH 8-INCHES OF HOT-MIX ASPHALT (ASPHALT PAVING MATERIAL).

- THE NEW PAVEMENT SECTION SHALL MATCH EXISTING PAVEMENT REPORT. FOR ROADWAYS WHERE THE SUBGRADE IS CHEMICALLY TREATED (CTS), CTS OR FLOW-FILL SHALL BE EQUIVALENT TO THE REQUIREMENT IN THE PAVEMENT DESIGN REPORT.
- ALTERNATE REPAIR SECTIONS MAY BE APPROVED PROVIDED THEY ARE COMPLETED BY THE PAVEMENT DESIGN GEOTECHNICAL ENGINEER, AND APPROVED BY CITY ENGINEERING.
- NEW HOT-MIX ASPHALT (ASPHALT PAVING MATERIAL) SHALL BE FLUSH TO EXISTING ASPHALT AND CONCRETE EDGES AND SHALL NOT HAVE HUMPS OR VALLEYS.
- WHERE CONCRETE PAVEMENT EXISTS BELOW THE ASPHALT, NEW CONCRETE SHALL BE PLACED TO MATCH THE EXISTING CONCRETE THICKNESS UNLESS OTHERWISE APPROVED BY CITY ENGINEERING.
- IF A PLATE TAMPER IS USED FOR COMPACTION OF ASPHALT, THE MAXIMUM LOOSE LIFT THICKNESS SHALL BE 2-INCHES.
- THESE DETAILS ARE FOR PAVEMENT CUTS LESS THAN 200-SF. CUTS GREATER THAN 200-SF SHALL BE IN CONFORMANCE WITH AN ENGINEERED DESIGN.
- ANY DISTURBED PAVEMENT MARKINGS SHALL BE RESTORED TO CITY STANDARDS.



- NOTES:**
- REMOVE AND REPLACE A MINIMUM OF 4- FEET LONGITUDINAL OR 2- FEET FROM THE EDGE OF THE TRENCH, WHICHEVER IS GREATER.
 - IF WITHIN 5- FEET OF AN EXISTING JOINT THEN REMOVE TO THE EXISTING JOINT.
 - MULTIPLE LOCATIONS ARE TO BE A MINIMUM OF 10- FEET APART FROM EDGE OF REPAIR TO EDGE OF REPAIR; IF REPAIRS ARE LESS THAN 10- FEET APART, A CONTINUOUS SECTION MUST BE REPLACED.
 - CURB & GUTTER MAY REMAIN, PROVIDED THE CURB AND GUTTER ARE NOT DAMAGED BY THE CONSTRUCTION ACTIVITY.
 - EXACT RESTORATION LIMITS/LOCATIONS SHALL BE APPROVED BY THE CITY REPRESENTATIVE PRIOR TO REPAIRS.
 - LONGITUDINAL REPAIRS GREATER THAN 40- FEET IN LENGTH SHALL BE MILLED AND PAVED.

UTILITY TRENCH REPAIR GENERAL NOTES

APPROVED: _____

CITY ENGINEER

ISSUED: 11/2/20 REVISED: _____ DRAWING NO. 44

UTILITY TRENCH REPAIR TYPICAL SECTIONS

APPROVED: _____

CITY ENGINEER


ISSUED: 11/2/20 REVISED: _____ DRAWING NO. 46

UTILITY TRENCH REPAIR RESTORATION LIMITS

APPROVED: _____

CITY ENGINEER

ISSUED: 11/2/20 REVISED: _____ DRAWING NO. 4C




8/11/11 Utility Trench Repair Detail Asphalt Pavement Standard Drawing

DATE APPROVED: _____

André P. Brackin

DEPARTMENT OF TRANSPORTATION

REVISION DATE: 11/10/04 FILE NAME: SD_4-20




8/11/11 Utility Trench Repair Detail Newly Overlayed Pavement Standard Drawing

DATE APPROVED: _____

André P. Brackin

DEPARTMENT OF TRANSPORTATION

REVISION DATE: 11/10/04 FILE NAME: SD_4-21




8/11/11 Utility Trench Repair Detail Concrete Pavement Standard Drawing

DATE APPROVED: _____

André P. Brackin

DEPARTMENT OF TRANSPORTATION

REVISION DATE: 11/10/04 FILE NAME: SD_4-22



8/11/11 Utility Trench Repair Detail Flowable Fill Standard Drawing

DATE APPROVED: _____

André P. Brackin

DEPARTMENT OF TRANSPORTATION


REVISION DATE: 11/10/04 FILE NAME: SD_4-23

FILE NAME: P:\indianapolis\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: D-102 PLOTTED: Monday, November 14, 2022 - 12:44pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	HP SERVICE: <input type="checkbox"/>	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	DISTRIBUTION: <input checked="" type="checkbox"/>		CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	FEEDER: <input type="checkbox"/>		SHEET NO. 11 OF 59	SCALE: NTS
N/A				BY: DATE: APPVD:	TRANS. BY DEF. <input type="checkbox"/>		PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	TRANS. v 20% <input type="checkbox"/>	3789816	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				LOCATION			LOCH FYNE 20" GAS PIPELINE	
N/A				ATLAS OR TITLE			COLORADO SPRINGS, COLORADO	
N/A				N/A			UTILITY TRENCHING REPAIR DETAILS	
N/A				SYSTEM MAOP:			DWC. NO. D-102	
N/A				SYSTEM MOP:			COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.	

FILE NAME: P:\indianapolis\Colorado Springs Utilities\06 Alignment\Colorado Springs_3-8-22.dwg LAYOUT NAME: D-103 RLOTEDT Monday, November 14, 2022 12:44pm USER: mwest



CD


STORMWATER ENTERPRISE

APPROVED: [Signature]

DESIGNED: 10/7/19

REVISIONS: 8/16/2020

DRAWING NO. 900-CD



CIP


STORMWATER ENTERPRISE

APPROVED: [Signature]

DESIGNED: 10/7/19

REVISIONS: 8/16/2020

DRAWING NO. 900-CIP



RS


STORMWATER ENTERPRISE

APPROVED: [Signature]

DESIGNED: 10/7/19

REVISIONS: 8/16/2020

DRAWING NO. 900-RS



ECB


STORMWATER ENTERPRISE

APPROVED: [Signature]

DESIGNED: 10/7/19

REVISIONS: 8/16/2020

DRAWING NO. 900-ECB-1



ECB


STORMWATER ENTERPRISE

APPROVED: [Signature]

DESIGNED: 10/7/19

REVISIONS: 8/16/2020

DRAWING NO. 900-ECB-2



SCL

STORMWATER ENTERPRISE

APPROVED: [Signature]

DESIGNED: 10/7/19

REVISIONS: 8/16/2020

DRAWING NO. 900-SCL



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS		
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		
NO.	N/A	BY:	DATE:	APPYD:		
PERMIT INFORMATION	ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		
N/A	N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	3747144
				SYSTEM MOP: 145 psig	DISTRIBUTION: <input checked="" type="checkbox"/>	RELATED W/O #s
					FEEDER: <input type="checkbox"/>	3789816
					TRANS. BY DEF. <input type="checkbox"/>	
					TRANS. v 20% <input type="checkbox"/>	

ENGINEER:	SCOTT JENSEN	PHONE:	(719) 668-8196
PROJECT MANAGER:	MELISSA LINGO	PHONE:	(719) 668-8794
CONSTRUCTION LEAD:	JOSH RICHARD	PHONE:	(719) 668-3675
SHEET NO. 12 OF 59	SCALE: NTS		
PATRICK ENGINEERING TEAM			
DWN BY:	NORM WEST	CHKD. BY:	SETH BROWN
APPD. BY:	JEREMIAH SMITH		
LOCH FYNE 20" GAS PIPELINE			
COLORADO SPRINGS, COLORADO			
BEST MANAGEMENT PRACTICES DETAILS - 1			
		DWG. NO.:	D-103

SEEDING & MULCHING

ALL SOIL TESTING, SOILS AMENDMENT AND FERTILIZER DOCUMENTATION, AND SEED LOAD AND BAG TICKETS MUST BE ADDED TO THE CSWMP.

SOIL PREPARATION


- IN AREAS TO BE SEEDED, THE UPPER 6 INCHES OF THE SOIL MUST NOT BE HEAVILY COMPACTED, AND SHOULD BE IN FRIABLE CONDITION. LESS THAN 85% STANDARD PROCTOR DENSITY IS ACCEPTABLE. AREAS OF COMPACTION OR GENERAL CONSTRUCTION ACTIVITY MUST BE SCARRIFIED TO A DEPTH OF 6 TO 12 INCHES PRIOR TO SPREADING TOPSOIL TO BREAK UP COMPACTED LAYERS AND PROVIDE A BLENDING ZONE BETWEEN DIFFERENT SOIL LAYERS.
- AREAS TO BE PLANTED SHALL HAVE AT LEAST 4 INCHES OF TOPSOIL SUITABLE TO SUPPORT PLANT GROWTH.
- THE CITY RECOMMENDS THAT EXISTING AND/OR IMPORTED TOPSOIL BE TESTED TO IDENTIFY SOIL DEFICIENCIES AND ANY SOIL AMENDMENTS NECESSARY TO ADDRESS THESE DEFICIENCIES. SOIL AMENDMENTS AND/OR FERTILIZERS SHOULD BE ADDED TO CORRECT TOPSOIL DEFICIENCIES BASED ON SOIL TESTING RESULTS.
- TOPSOIL SHALL BE PROTECTED DURING THE CONSTRUCTION PERIOD TO RETAIN ITS STRUCTURE AVOID COMPACTION, AND TO PREVENT EROSION AND CONTAMINATION. STRIPPED TOPSOIL MUST BE STORED IN AN AREA AWAY FROM MACHINERY AND CONSTRUCTION OPERATIONS, AND CARE MUST BE TAKEN TO PROTECT THE TOPSOIL AS A VALUABLE COMMODITY. TOPSOIL MUST NOT BE STRIPPED DURING UNDESIRABLE WORKING CONDITIONS (E.G. DURING WET WEATHER OR WHEN SOILS ARE SATURATED). TOPSOIL SHALL NOT BE STORED IN SWALES OR IN AREAS WITH POOR DRAINAGE.


SEEDING

- ALLOWABLE SEED MIXES ARE INCLUDED IN THE CITY OF COLORADO SPRINGS STORMWATER CONSTRUCTION MANUAL. ALTERNATIVE SEED MIXES ARE ACCEPTABLE IF INCLUDED IN AN APPROVED LANDSCAPING PLAN.
- SEED SHOULD BE DRILL-SEEDED WHENEVER POSSIBLE.
 - SEED DEPTH MUST BE 1/2 TO 3/4 INCHES WHEN DRILL-SEEDED IS USED
- BROADCAST SEEDING OR HYDRO-SEEDED WITH TACKIFIER MAY BE SUBSTITUTED ON SLOPES STEEPER THAN 3:1 OR ON OTHER AREAS NOT PRACTICAL TO DRILL SEED.
 - SEEDING RATES MUST BE DOUBLED FOR BROADCAST SEEDING OR INCREASED BY 50% IF USING A BRILLIANT DRILL OR HYDRO-SEEDED
 - BROADCAST SEEDING MUST BE LIGHTLY HAND-RAKED INTO THE SOIL


MULCHING

- MULCHING SHOULD BE COMPLETED AS SOON AS PRACTICABLE AFTER SEEDING, HOWEVER PLANTED AREAS MUST BE MULCHED NO LATER THAN 14 DAYS AFTER PLANTING.
- MULCHING REQUIREMENTS INCLUDE:
 - HAY OR STRAW MULCH
 - ONLY CERTIFIED WEED-FREE AND CERTIFIED SEED-FREE MULCH MAY BE USED. MULCH MUST BE APPLIED AT 2 TONS/ACRE AND ADEQUATELY SECURED BY CRIMPING AND/OR TACKIFIER.
 - CRIMPING MUST NOT BE USED ON SLOPES GREATER THAN 3:1 AND MULCH FIBERS MUST BE TUCKED INTO THE SOIL TO A DEPTH OF 3 TO 4 INCHES.
 - TACKIFIER MUST BE USED IN PLACE OF CRIMPING ON SLOPES STEEPER THAN 3:1.
 - HYDRAULIC MULCHING
 - HYDRAULIC MULCHING IS AN OPTION ON STEEP SLOPES OR WHERE ACCESS IS LIMITED.
 - IF HYDRO-SEEDED IS USED, MULCHING MUST BE APPLIED AS A SEPARATE, SECOND OPERATION.
 - WOOD CELLULOSE FIBERS MIXED WITH WATER MUST BE APPLIED AT A RATE OF 2,000 TO 2,500 POUNDS/ACRE, AND TACKIFIER MUST BE APPLIED AT A RATE OF 100 POUNDS/ACRE.
 - EROSION CONTROL BLANKET
 - EROSION CONTROL BLANKET MAY BE USED IN PLACE OF TRADITIONAL MULCHING METHODS.






SEEDING & MULCHING			
APPROVED:	[Signature]		
DRAWN BY:	[Signature]		
ISSUED:	10/7/19	REVISED:	8/19/2020
DRAWING NO.	900-SM		



STOCKPILE PROTECTION PLAN




STOCKPILE PROTECTION ELEVATION


INSTALLATION NOTES

- INSTALL PERIMETER CONTROL AROUND STOCKPILE ON DOWNGRADIENT SIDE. PERIMETER CONTROL MUST BE SUITABLE TO SITE CONDITIONS AND INSTALLED ACCORDING TO THE RELEVANT DETAIL.
- FOR STOCKPILES ON THE INTERIOR PORTION OF A CONSTRUCTION SITE, WHERE OTHER DOWNGRADIENT CONTROLS INCLUDING PERIMETER CONTROL ARE IN PLACE, STOCKPILE PERIMETER CONTROLS MAY NOT BE REQUIRED.


MAINTENANCE NOTES

- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN CONTROL MEASURES IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- IF PERIMETER CONTROLS MUST BE MOVED TO ACCESS STOCKPILE, REPLACE PERIMETER CONTROLS BY THE END OF THE WORK DAY.
- ACCUMULATED SEDIMENT MUST BE REMOVED ACCORDING TO PERIMETER CONTROL DETAIL.






STOCKPILE PROTECTION			
APPROVED:	[Signature]		
DRAWN BY:	[Signature]		
ISSUED:	10/7/19	REVISED:	8/19/2020
DRAWING NO.	900-SP		



SILT FENCE




J-HOOK INSTALLATION


INSTALLATION NOTES

- SILT FENCE MUST BE PLACED ON A FLAT SURFACE 2'-5' AWAY FROM TOE OF THE SLOPE TO ALLOW FOR PONDING AND DEPOSITION.
- COMPACT THE TRENCH USING A JUMPING JACK OR WHEEL ROLLING TO THE POINT THAT THE FENCE RESISTS BEING PULLED OUT OF THE GROUND BY HAND.
- SILT FENCE SHALL BE TAUT WITH NO SAGS AFTER IT HAS BEEN ANCHORED.
- FABRIC SHALL BE ATTACHED TO POSTS WITH 1" HEAVY DUTY STAPLES OR 1" NAILS. THESE SHOULD BE PLACED VERTICALLY DOWN THE POST, 3" APART.
- THE PREFERRED INSTALLATION METHOD USES A TRENCHER OR SILT FENCE INSTALLATION DEVICE.
- INSTALL SILT FENCE ALONG THE CONTOUR OF THE SLOPES OR IN A MANNER TO AVOID CREATING CONCENTRATED FLOW (SUCH AS A "J-HOOK" INSTALLATION).

MAINTENANCE NOTES

- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN CONTROL MEASURES IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE HEIGHT REACHES 1/2 OF THE DESIGN HEIGHT OF THE SILT FENCE.
- SILT FENCE MUST REMAIN UNTIL THE UPSTREAM DISTURBANCE AREA IS STABILIZED.
- PERMANENTLY STABILIZE AREA AFTER SILT FENCE IS REMOVED.





SILT FENCE			
APPROVED:	[Signature]		
DRAWN BY:	[Signature]		
ISSUED:	10/7/19	REVISED:	8/19/2020
DRAWING NO.	900-SF		

INTERIM RELEASE: CLSM (to the City Standard Specifications Manual)

206 Backfill of Utility Trenches using Controlled Low Strength Materials (CLSM)

UTILITY CUT, BACKFILL AND PATCHING

1 DESCRIPTION OF WORK

This work shall consist of the excavation and rapid backfill of trenches for the installation or repair of utility and underground features. The work also includes utilizing temporary pavement patching materials, and final permanent pavement surfaces. The work requires the use of removable, controlled low-strength materials (CLSM) for the backfill material, as an alternative to traditional compacted soil, for trenches and cuts too small for traditional soil compaction and safe human entry for testing. Various temporary pavement materials may also be utilized, prior to permanent pavement repairs. The use of traditional compacted backfill (for installation and repair of utilities) remains an acceptable method of backfill. The use of CLSM provides the advantage of being a self-compacting material.

1A Description of removable, flowable, controlled low strength materials CLSM

The term CLSM used in this Section shall mean the same as Removable CLSM or flowable backfill. This material is covered in detail due to the many time saving and engineering benefits of this type of backfill material. CLSM does not need compaction, or moisture density compaction testing. Only a few physical tests of the CLSM properties are needed to assure durability and future removability with light excavating equipment. A low strength is desired so that surrounding utilities or structures will be accessible without causing damage if the CLSM must be removed in the future. Air entrainment is required to prevent damage and heave displacement of trench patches due to freeze-thaw damage.

In addition, CLSM may be used for other applications apart from trench or street cut backfill. These include filling voids due to pipe abandonment or undercutting of excavation in caving or normal soils. CLSM offers quick restoration of the trench and improving other subgrade conditions for roadway or structure support in a rapid time frame without the need for traditional soil backfill testing requirements or when a quick strength is needed to support upper layers. These benefits may outweigh the extra costs vs. using traditional methods that require compaction and testing.

Other applications include: backfilling behind retaining walls and abutments, filling void areas including pipe abandonment, annular spaces, undercut areas and other approved void filling

STANDARD SPECIFICATIONS MANUAL
SECTION 200 - STREET SECTION
Page 1

applications. Other suitable applications include structural support for utilities and replacement of unstable subgrade during pavement repairs.

Utility types that can utilize CLSM include: conduits or pipes for electrical, wired or fiber optic communications, traffic signal or other utilities such as gas and water lines, sanitary and storm sewer lines, and other types of utilities under existing pavements or ground surfaces to be built upon or improved later.

1B Objectives for Required Use of CLSM

The objectives of requiring the use of the CLSM specified below, instead of reusing excavated soils, is to provide a self-leveling, frost heave-resistant, non-setting, controlled low-strength material (defined by American Concrete Institute in ACI 229 as a CLSM), that does not normally require compactive effort and compaction testing. Traditional use of compacted soil or aggregate materials for backfill shall require CITY approval and testing for acceptance.

1C Requirements for CLSM - Flow-Fill or Flashfill

This ITEM further specifies two distinct CLSM material products: The **Flashfill** products will allow trench backfill, temporary or permanent pavement restoration and traffic access to occur more quickly than **Flow-Fill**. The term "CLSM" in this Section shall mean either or both.

A **high slump** is required to aid in the self-leveling and void filling objective. The visual consistency may appear to range in appearance from thin batter or mud, to thick water. It must be foremost removable with light machinery in the future, and also quickly stable to support paving operations and traffic.

Minimum air contents are required in the top 4 feet of CLSM fill to limit permanent frost heave. This air content requirement should be used for the entire depth, to aid in the ability to remove or excavate CLSM in the future. The air content requirement may be forbidden by some utility applications, such as for thrust blocks or for pipe bedding normally used for lateral support of pressurized pipes.

A **Removability Modulus (RE)** is specified at a maximum 1.5, and is based on compressive strength and unit weight of the CLSM Backfill. Refer to section 2C

STANDARD SPECIFICATIONS MANUAL
SECTION 200 - STREET SECTION
Page 2

2 CLSM MATERIALS

2A Flow-Fill

Flow-Fill shall consist of a controlled low-strength, self-leveling concrete material composed of various combinations of cement, fly ash, aggregates, water, chemical admixtures and/or cellular foam for air-entrainment. Generally, the **CONTRACTOR** may place Flow-Fill in approximate 3 feet thick layers, allow bleed water to rise and divert away from placement before another layer may be added. Refer to Section 3 for more information.

The Flow-Fill shall be limited to a maximum Removability Modulus (RE, as described in section 2C) of 1.5 to ensure ability to excavate in the future. Slumps of less than 7 inches will not be permitted for placement, since the flowability to fill voids and avoid future settlement is impaired, and strengths may increase beyond specified removability limits.

The **CONTRACTOR** shall submit a mix design for approval by the **CITY**, prior to placement. The mix design shall be supported by laboratory test data verifying compliance with air content, slump, strength and removability (RE) requirements.

Flow-Fill Property	Flow-Fill Specification
Air Content, ASTM C231	15% - 25%
Compressive Strength, ASTM D4832	50psi - 150psi at 28 days
Slump, ASTM C143	7" - 10"
Removability Modulus, RE	1.5 Maximum

*All other requirements for Flow-Fill shall meet CDOT Section 206 for CLSM.

2B Flashfill

Flashfill shall consist of a controlled low-strength, self-leveling cementitious material composed of various combinations of fly ash, water, chemical admixtures and/or cellular foam for air-entrainment. No aggregate or sand is usually needed. It shall have a minimum specified air content to provide suitable resistance to frost-heave. Flashfill may generally be placed without lift thickness limits.

STANDARD SPECIFICATIONS MANUAL
SECTION 200 - STREET SECTION
Page 3

Higher strengths may be permitted over Flow-Fill, however, the Flashfill shall still be limited to a maximum Removability Modulus (RE) of 1.5. Slumps of less than 8 inches or spreads of less than 8 inches will not be permitted for placement, since the flowability to fill voids and avoid future settlement is impaired, and strengths may increase beyond removability limits.

The **CONTRACTOR** shall submit a mix design for approval by the **CITY**, prior to placement. The mix design shall be supported by laboratory test data verifying compliance with air content, slump, strength and removability (RE) requirements.

Flashfill Property	Flashfill Specification
Air Content, ASTM C231, or by Section 2D volumetric calculations (recommended)	15% Minimum
Compressive Strength, ASTM D4832	100psi - 300psi at 28 days
Slump, ASTM C143 (one lift, no rodding)	8" - 11"
Spread, ASTM D6103 (recommended)	8" - 12", or greater
Removability Modulus, RE	1.5 Maximum

*All other requirements for Flashfill shall meet CDOT Section 206 for CLSM.

2C Removability Modulus

The Removability Modulus "RE" is a value calculated by

$$RE = \frac{W^{1.5} \times 104 \times C^{0.5}}{10^6}$$

where: W = in-situ unit weight (pcf) and C = 28-day compressive strength

*RE was developed & is used by Hamilton County, Ohio; per the NCHRP #597 CLSM Report. A lower RE means CLSM is easier to excavate or remove.

STANDARD SPECIFICATIONS MANUAL
SECTION 200 - STREET SECTION
Page 4

Some examples of RE based on strength and unit weights are shown below:

Compressive strength, psi [C]	Unit Weight, pcf [W]										
	50	60	70	80	90	100	110	120	130	140	150
25	0.18	0.24	0.30	0.37	0.44	0.52	0.60	0.68	0.77	0.86	0.96
50	0.26	0.34	0.43	0.53	0.63	0.74	0.85	0.97	1.09	1.22	1.35
75	0.32	0.42	0.53	0.64	0.77	0.90	1.04	1.18	1.33	1.49	1.65
100	0.37	0.48	0.61	0.74	0.89	1.04	1.20	1.37	1.54	1.72	1.91
125	0.41	0.54	0.68	0.83	0.99	1.16	1.34	1.53	1.72	1.93	2.14
150	0.45	0.59	0.75	0.91	1.09	1.27	1.47	1.67	1.89	2.11	2.34
175	0.49	0.64	0.81	0.98	1.17	1.38	1.59	1.81	2.04	2.28	2.53
200	0.52	0.68	0.86	1.05	1.26	1.47	1.70	1.93	2.18	2.44	2.70

RE less than or equal to 1.50 indicates Removable
1.70 Shading indicates Not Readily Removable

2D Air Content Volumetric Calculation

Air content can be calculated as follows (using wet unit weights before and after foaming or entraining air):


$$\text{Air Content} = \frac{(\text{Unit Weight not Air-Entrained} - \text{Unit Weight Air-Entrained}) \times 100\%}{\text{Unit Weight not Air-Entrained}}$$

2E Flow Consistency of CLSM


Flow shall be measured by ASTM D6103, which utilizes a moistened 3" diameter, 6" high open-ended cylinder, filled with the flashfill. When the cylinder is lifted, the resulting "pancake" is measured at its longest and shortest dimensions and averaged.

STANDARD SPECIFICATIONS MANUAL
SECTION 200 - STREET SECTION
Page 5


FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: D-104_RL01.DWG Monday, November 14, 2022 12:44pm USER: mwest




COLORADO 811
CALL BEFORE YOU DIG



Colorado Springs Utilities
It's how we're all connected



JEREMIAH SMITH
PROFESSIONAL ENGINEER
No. 2022-11-15 09:27:46-09-00



PATRICK ENGINEERING
8902 Vincennes Circle, Suite F
Indianapolis, IN 46268
TEL: (317) 217-1701
www.patrickco.com

REVISONS		SYSTEM NAME:	150P	JOB TYPE:		W/O #		ENGINEER:	SCOTT JENSEN	PHONE:	(719) 668-8196		
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				PROJECT MANAGER:	MELISSA LINGO	PHONE:	(719) 668-8794		
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP:	275 psig		CONSTRUCTION LEAD:	JOSH RICHARD	PHONE:	(719) 668-3675		
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP:	145 psig		SHEET NO. 13 OF 59	SCALE: NTS				
NO.	N/A	BY:	DATE:	APPVD:				PATRICK ENGINEERING TEAM					
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A			DWN BY:	NORM WEST	CHKD. BY:	SETH BROWN	APPD. BY:	JEREMIAH SMITH
N/A		N/A		TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	SYSTEM MAOP:		LOCH FYNE 20" GAS PIPELINE					
						SYSTEM MOP:		COLORADO SPRINGS, COLORADO					
								BEST MANAGEMENT PRACTICES DETAILS - 2					
								AND CLSM SPECIFICATIONS					

PROJ. NO. 22282.003

DWG. NO. **D-104**

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 - Design\01 - Drawings\06 - Alignment\Colorado Springs_3-8-22.dwg LAYOUT NAME: D-105 - R10TRED - Monday, November 14, 2023 - 12:44pm USER: mwest

MATERIAL CONSTITUENTS

2F Cement

Cement shall meet the standard chemical requirements of Type II or Type IP, ASTM C150 or ASTM C595, respectively.

2G Fly Ash

Fly ash shall meet the requirements of ASTM C618 Type C or Type F. Fly ash not meeting the requirements of ASTM C618 may be used if prior testing indicates acceptable, consistent results for strength and air content.

2H Water

Potable water or reasonably clean and free of chemicals injurious to the final product are to be used.

2I Chemical Admixtures

Air-entraining admixtures shall conform to ASTM C260 requirements; other chemical admixtures shall conform to ASTM C494 requirements.

2J Foaming Agents

Foaming agents shall conform to ASTM C869 and C796, or as approved by the CITY.

2K Suitability of CLSM Constituents

The supplier shall have the required Beneficial Use Determination (BUD) from the CDPHE for the product they are supplying. Material Safety Data Sheets (MSDS) must be available for any cement, flyash or admixture component of the mixture upon request. Flowable Backfill shall be compatible with bedding materials, electrochemically and otherwise if used as a metal pipe backfill application. Thermal compatibility with plastic pipes should be considered for direct contact of the CLSM with the pipe; heat generation of the mix must not exceed the softening point of the pipe material.

2L CLSM Use Restrictions

CLSM products containing coal combustion residuals (CCR) (i.e. fly ash, bottom ash, boiler slag, and flue gas desulfurization materials generated from burning coal for the purpose of generating electricity by electric utilities and independent power producers) may not be placed below groundwater, or into permanent standing water, without the CONTRACTOR obtaining a

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 6

written waiver from the Colorado Department of Public Health & Environment's (CDPHE's) Hazardous Materials and Waste Management Division (HMMWD), and providing such waiver to the CITY for review / concurrence prior to placement.

The above noted use restriction with respect to groundwater and permanent standing water is not applicable if the CLSM product is being used in association with an emergency. An emergency is an occurrence involving a clear and imminent danger to human health or the environment, or similar occurrence demanding immediate attention, such as the restoration of a damaged utility, roadway, or storm water conveyance. If the emergency has subsided and sufficient time is available for planning (e.g., three weeks or more) the project is not considered an emergency with sole respect to CLSM placement.

Additionally, if a project involves the placement of CLSM on the land in non-roadway applications and the CLSM will contain 12,400 tons of CCR or more, the CONTRACTOR shall obtain written project specific approval from the CDPHE's HMMWD and provide such approval to the CITY for review / concurrence prior to placement. To obtain such approval, the CONTRACTOR shall adequately demonstrate that environmental releases to groundwater, surface water, soil and air are comparable to or lower than those from analogous products made without CCR, or that environmental releases to groundwater, surface water, soil and air will be at or below relevant regulatory and health-based benchmarks for human and ecological receptors during use.

2M Aggregates

The final blend of aggregates for CLSM, including rock, gravel or sand, shall conform to the following gradations:

TABLE 2L

Sieve Size	% Passing
1 inch (25 mm)	100
No. 200	0 to 10

When coarse aggregate is used, 100 percent shall pass the 1 inch sieve, and it shall comprise not more than 40 percent of the total aggregate content. Other aggregate products such as aggregate base, crushed rock, pea gravel, or reject sand which has no more than 20 percent passing the No. 200 sieve and is free of organic material and other deleterious substances, may

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 7

be accepted by the CITY if a flowable, workable mix can be produced without segregation of the aggregate.

3 TRENCH BACKFILL WITH CLSM

Except as otherwise provided or approved by the CITY, after the pipe or conduit is laid, trenches shall be backfilled with CLSM in the pipe zone as defined in the following table:

TABLE 3

Pipe or Conduit	Pipe Zone ^{1,2}
2-inch or less diameter	6 inches above the top of the pipe up to subgrade
Greater than 2-inch diameter, except vitrified clay pipe	12 inches above the top of the pipe up to subgrade
Vitrified clay pipe	24 inches above the top of the pipe up to subgrade

¹ The Utility Owner shall dictate any variance to these CLSM separation distances.
² Where depths of flashfill exceed 3 feet over water or wastewater mains please contact Colorado Springs Utilities for bedding depths.

CLSM should be well mixed and discharged directly from the truck into the space to be filled, or by other methods approved by the CITY. The mix may be placed part depth or full depth as conditions at the site and CLSM type dictate. When used as backfill in the pipe zone, care should be taken to prevent flotation or misalignment of the pipe by means of straps, soil anchors or other approved means of restraint. Material may be placed in stages with initially lesser flowability, to prevent movement or flotation of pipe. Refer to Section 2K for thermal compatibility when using CLSM directly against plastic pipe materials. CLSM shall not be placed when the trench bottom or walls are frozen or contain frozen materials.

Compaction of CLSM shall not be performed.

The maximum layer thickness for CLSM shall be determined by the Contractor. Additional layers shall not be placed until the backfill has lost sufficient moisture to be walked on without indenting more than 2 inches. Allow bleed water to rise and divert away from placement area before another layer may be added. Do not place CLSM on top of bleed water or on any water above the bearing layer. Any damage resulting from placing Flow-Fill in layers that are too thick

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 8

or from not allowing sufficient strength gain time between placement of layers shall be repaired at the CONTRACTOR's expense.

The maximum layer thickness for Flashfill is not restricted except to prevent flowing or running into undesired areas.

Contractor shall observe all other Construction Requirements as provided in CDOT Section 206 for placement of CLSM.

4 STREET SURFACING and PATCHING

Placement of pavement materials for vehicle traffic shall not be allowed until the removable CLSM backfill has cured 24 hours (Flow-Fill only) or achieved sufficient resistance to allow paving. CLSM (either type) should be subjected to standard proofroll criteria, or penetration resistance tests. CLSM should achieve a penetration resistance of at least 3.6 tsf (tons per square foot) (equivalent to 50 psi) using a hand-held soil penetrometer, typically pushed to 1/4" depth, in accordance with the penetrometer manufacturer's instructions. Alternately, penetration resistance shall be considered achieved when a person weighing 100 pounds by use of their body weight as an axial load, cannot penetrate the CLSM backfill with the square cut end of a 1/2" diameter (#4) steel reinforcing bar.

4A Temporary Pavement Selection

Whenever permanent pavement patches are not constructed immediately following trench backfilling operations, temporary pavement patch construction consisting of:

- A minimum of 3 inches of hot mix asphalt (or approved warm mix if allowed) or cold plant mix asphalt on Flashfill or cured Flow-Fill CLSM, or
- A thickness of Flash-Patch equal to existing pavement thickness on CLSM, or
- Steel plates per CITY requirements on CLSM,

must be utilized to provide the required number of paved travel lanes. Sufficient excavation of backfill shall be done to allow the temporary surfacing to be level with surrounding pavement. Use of steel plates may be left in place for a short duration as approved by the CITY. Temporary pavement patches may be left in place for a maximum of 30 working days following completion of backfilling operations unless otherwise approved by the CITY.

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 9

or from not allowing sufficient strength gain time between placement of layers shall be repaired at the CONTRACTOR's expense.

The maximum layer thickness for Flashfill is not restricted except to prevent flowing or running into undesired areas.

Contractor shall observe all other Construction Requirements as provided in CDOT Section 206 for placement of CLSM.

4 STREET SURFACING and PATCHING

Placement of pavement materials for vehicle traffic shall not be allowed until the removable CLSM backfill has cured 24 hours (Flow-Fill only) or achieved sufficient resistance to allow paving. CLSM (either type) should be subjected to standard proofroll criteria, or penetration resistance tests. CLSM should achieve a penetration resistance of at least 3.6 tsf (tons per square foot) (equivalent to 50 psi) using a hand-held soil penetrometer, typically pushed to 1/4" depth, in accordance with the penetrometer manufacturer's instructions. Alternately, penetration resistance shall be considered achieved when a person weighing 100 pounds by use of their body weight as an axial load, cannot penetrate the CLSM backfill with the square cut end of a 1/2" diameter (#4) steel reinforcing bar.

4A Temporary Pavement Selection

Whenever permanent pavement patches are not constructed immediately following trench backfilling operations, temporary pavement patch construction consisting of:

- A minimum of 3 inches of hot mix asphalt (or approved warm mix if allowed) or cold plant mix asphalt on Flashfill or cured Flow-Fill CLSM, or
- A thickness of Flash-Patch equal to existing pavement thickness on CLSM, or
- Steel plates per CITY requirements on CLSM,

must be utilized to provide the required number of paved travel lanes. Sufficient excavation of backfill shall be done to allow the temporary surfacing to be level with surrounding pavement. Use of steel plates may be left in place for a short duration as approved by the CITY. Temporary pavement patches may be left in place for a maximum of 30 working days following completion of backfilling operations unless otherwise approved by the CITY.

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 9

CLSM strengths, but are limited in thickness to the existing pavement thickness to allow removal.

- Flash-Patch usage on arterial roadways will require that **Small Aggregate topping** be used. Gradations shall meet ASTM C33 for size #9, and be crushed stone or natural gravels, with gradations requirements listed below:

TABLE 4B

Sieve	3/8"	#4	#8	#16	#50
% Passing	100	85 - 100	10 - 40	0 - 10	0 - 5

4C Temporary Pavement Patch Placement

Temporary asphalt should ideally be placed according to the Pikes Peak Region Asphalt Paving Specifications requirements. Any temporary asphalt pavement patch shall be placed and compacted and shall be maintained by the CONTRACTOR so that the patched surface and the surrounding area remain a single even (smooth) unbroken plane, suitable to handle the traffic, for the duration of Temporary Patch.

Flash-Patch usage on arterial roadways will require that the **Small Aggregate** shall be broadcast on and embedded into the surface, for increased skid-resistance. Aggregate application will occur on patches within 100 feet of approaching stop signs or signal lights on other city streets. This aggregate shall be applied at approximately 5 lb per SY of patch surface, before the Flash-Patch hardens. The CONTRACTOR shall be responsible to apply and embed the surface aggregate in a timely manner before set occurs.

The following **surface tolerance** for any temporary patches shall be observed. When a 10 foot straight edge is laid across the temporary patch parallel to the centerline of the street and in the direction transverse to the centerline, there shall be no more than a 3/4 inch rut, hump, or depression evident. Deteriorated temporary patches exhibiting ruts, humps, or depressions shall be repaired or replaced immediately. If the existing street exceeded the above tolerances prior to patching, then the temporary patch shall be equal to or better than the condition of the surrounding pavements.

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 11

Temporary patches with hot or cold mix asphalt may be opened to traffic after proper compaction and clean-up of the adjacent areas has occurred. Temporary patches of Flash-Patch may be opened to traffic usually within 1-1/2 hours after placement on arterial roadways, and usually within one hour on other streets.

4D Permanent Pavement Materials

Asphalt for replacement of Asphalt Pavement streets, shall be HMA (Hot Mix Asphalt), or WMA (Warm Mix Asphalt) if allowed by CITY, and shall meet the material requirements in the Pikes Peak Region Asphalt Paving Specifications for Grading S or SX with PG 64-22 binder, unless specified otherwise. Completion of the permanent patch in areas where an open graded surface course (SMA) exists shall include placement of a surface course to match the existing surface texture.

4E Permanent Pavement Construction

Prior to placing the permanent patch, the existing cuts made for trenches shall be properly prepared for final pavement patching.

Existing Asphalt Pavement shall be saw cut to a neat straight line and to a minimum 12 inches outside of the trench area. The CITY may require just the top lift be outside the trench edges. The resulting "T patch" edges shall not fall within existing wheel paths. Patches parallel to the direction of traffic and encompassing the wheel path shall extend to lane lines.

The asphalt thickness shall be the thicker of the existing depth, or the minimum depth of at least 4 inches. A tack coat shall be applied to all edges to the existing freshly cut and/or approved well cleaned edges of asphalt pavement prior to placing new pavement.

Compaction of each lift shall be to a density of 94% (± 2%) of the maximum theoretical density of the approved Job Mix Formula, and conforming to the Pikes Peak Region Asphalt Paving Specifications.

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 12

The top of CLSM for temporary paving or for steel plates in section 4A shall be excavated to the top of subgrade/bottom of the final asphalt or concrete pavement level. The depth of excavation shall allow for the permanent pavement section to be equal to, or greater than, the existing section, or as otherwise required by the CITY.

Any improvements in the right-of-way or on private property disturbed or damaged during construction shall be replaced prior to placement of the permanent pavement patch. Damaged sections of concrete sidewalk shall be removed and replaced to the nearest expansion joint or score line. Damaged concrete curb and gutter shall be removed and replaced to the nearest contraction joint. Replacement of less than a standard length of curb and gutter will not be permitted. Integral curb, gutters, and/or sidewalk shall be replaced in their entirety.

The following **surface tolerance** for permanent pavement patch for asphalt, including any surface treatment before striping, shall be observed. The surface shall be thoroughly compacted, smooth, and free from ruts, humps, depressions, or irregularities. When a 10 foot straight-edge is laid across the permanent patch parallel to the centerline of the street and in a direction transverse to the centerline, the surface shall not vary more than 1/4 inch from the lower edge of the straight edge. Patches exhibiting deviations greater than 1/4 inch shall be replaced prior to acceptance of the patch. If the existing street exceeds the above tolerances, then the patch shall be equal or better than the condition of the surrounding pavement.

Patches shall also have a cross slope or cross section consistent with the design of the existing roadway.

STANDARD SPECIFICATIONS MANUAL SECTION 200 - STREET SECTION

Page 13




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794	
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675	
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 14 OF 59	SCALE: NTS	
NO.	N/A	BY:	DATE:	APPVD:	SYSTEM MOP: 145 psig		PATRICK ENGINEERING TEAM		
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN	APPD. BY: JEREMIAH SMITH
N/A		N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-18, P-19	SYSTEM MAOP:	3789816	LOCH FYNE 20" GAS PIPELINE		
					SYSTEM MOP:		COLORADO SPRINGS, COLORADO		
							CLSM SPECIFICATIONS		
							DWN NO. 14 OF 59		
							SCALE: NTS		
							PATRICK ENGINEERING TEAM		
							DWN BY: NORM WEST		
							CHKD. BY: SETH BROWN		
							APPD. BY: JEREMIAH SMITH		


DWG. NO. D-105

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

WELD & X-RAY (NDT) DOCUMENTATION



HORIZONTAL SCALE 1" = 5'



HORIZONTAL SCALE 1" = 20'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: W-100 PLOTTED: Monday, November 14, 2022 - 12:48pm USER: rwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #
4	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS		3747144
3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		
2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		
NO.	N/A	BY:	DATE:	APPVD:		
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s
N/A		N/A	TWN. 12S, RNG. 65W, SECTION 33	R-18, R-19	SYSTEM MAOP: 275 psig	3789816
					SYSTEM MOP: 145 psig	

HP SERVICE:	<input type="checkbox"/>
DISTRIBUTION:	<input checked="" type="checkbox"/>
FEEDER:	<input type="checkbox"/>
TRANS. BY DEF.	<input type="checkbox"/>
TRANS v 20%:	<input type="checkbox"/>




ENGINEER:	SCOTT JENSEN	PHONE:	(719) 668-8196
PROJECT MANAGER:	MELISSA LINGO	PHONE:	(719) 668-8794
CONSTRUCTION LEAD:	JOSH RICHARD	PHONE:	(719) 668-3675
SHEET NO. 15 OF 59			
SCALE: AS NOTED			
PATRICK ENGINEERING TEAM			
DWN BY:	NORM WEST	CHKD. BY:	SETH BROWN
APPD. BY:	JEREMIAH SMITH		

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
WELD, X-RAY, NDT DOCUMENTATION
0+00 - 5+00

DWG. NO: **W-100**

Copyright Protected © 2018 Patrick Engineering Inc.

WELD & X-RAY DOCUMENTATION



HORIZONTAL SCALE 1" = 20'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: W-101 PLOTTED: Monday, November 14, 2022 - 12:55pm USER: mwest



REVISIONS				SYSTEM NAME: 150P		JOB TYPE:	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	SYSTEM MAOP: 275 psig	HP SERVICE:	<input type="checkbox"/>
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MOP: 145 psig	DISTRIBUTION:	<input checked="" type="checkbox"/>
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		FEEDER:	<input type="checkbox"/>
NO.	N/A	BY:	DATE:	APPVD:		TRANS. BY DEF.	<input type="checkbox"/>
						TRANS v 20%	<input type="checkbox"/>
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		
N/A		N/A	TWN. 12S, RING. 65W, SECTIONS 32, 33	R-19 & Q-19			


W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
	SHEET NO. 16 OF 59	
	SCALE: 1" = 20'-0"	
	PATRICK ENGINEERING TEAM	
	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
	APPD. BY: JEREMIAH SMITH	
3789816		

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
WELD, X-RAY, NDT DOCUMENTATION
5+00 - 21+00

DWG. NO: **W-101**

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

WELD & X-RAY (NDT) DOCUMENTATION



HORIZONTAL SCALE 1" = 20'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: W-102 PLOTTED: Monday, November 14, 2023 - 10:05am USER: jsmith






REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	3747144
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		
N/A				SYSTEM MAOP: 275 psig	SYSTEM MOP: 145 psig	RELATED W/O #s
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	3789816
N/A		N/A	TWN. 12S, RNG. 65W, SECTION 32	Q-19	SYSTEM MAOP:	
					SYSTEM MOP:	

ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
SHEET NO. 17 OF 59	
SCALE: 1" = 20'-0"	
PATRICK ENGINEERING TEAM	
DWN BY: NORM WEST	CHKD. BY: SETH BROWN
APPD. BY: JEREMIAH SMITH	

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
WELD, X-RAY, NDT DOCUMENTATION
 21+00 - 37+00

DWG. NO: **W-102**

WELD & X-RAY (NDT) DOCUMENTATION



HORIZONTAL SCALE 1" = 20'






REVISIONS				SYSTEM NAME: 150P		JOB TYPE:	
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	W/O #
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			
2	REVISED 60% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/8/22	JMS			
NO.	N/A			BY:	DATE:	APPROV:	RELATED W/O #s
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		
N/A		N/A	TWN. 12S, RING. 65W, SECTIONS 32	Q-19	SYSTEM MAOP:	DISTRIBUTION: <input checked="" type="checkbox"/>	3789816
					SYSTEM MOP:	FEEDER: <input type="checkbox"/>	
						TRANS. BY DEF. <input type="checkbox"/>	
						TRANS v 20% <input type="checkbox"/>	

ENGINEER:	SCOTT JENSEN	PHONE:	(719) 668-8196
PROJECT MANAGER:	MELISSA LINGO	PHONE:	(719) 668-8794
CONSTRUCTION LEAD:	JOSH RICHARD	PHONE:	(719) 668-3675
SHEET NO. 18 OF 59	SCALE: 1" = 20'-0"		
PATRICK ENGINEERING TEAM			
DWN BY:	NORM WEST	CHKD. BY:	SETH BROWN
APPD. BY:	JEREMIAH SMITH		
LOCH FYNE 20" GAS PIPELINE			
COLORADO SPRINGS, COLORADO			
WELD, X-RAY, NDT DOCUMENTATION			
37+00 - 56+00			
			DWG. NO. W-103

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_3-8-22.dwg LAYOUT NAME: W-103 PLOTFILE: Monday, November 14, 2022 - 1:03pm USER: mwest

WELD & X-RAY (NDT) DOCUMENTATION



HORIZONTAL SCALE 1" = 20'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: W-104 PLOTTED: Monday, November 14, 2022 - 10:08am USER: mwest



REVISIONS				SYSTEM NAME: 150P		JOB TYPE:	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	SYSTEM MAOP: 275 psig	HP SERVICE:	<input type="checkbox"/>
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MOP: 145 psig	DISTRIBUTION:	<input checked="" type="checkbox"/>
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		FEEDER:	<input type="checkbox"/>
NO.	N/A	BY:	DATE:	APPVD:		TRANS. BY DEF.	<input type="checkbox"/>
PERMIT INFORMATION		ISOLATION AREA		LOCATION		ATLAS OR TITLE	
N/A		N/A		TWN. 12S, RNG. 65W, SECTION 32		P-19, Q-19	


W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
	SHEET NO. 19 OF 59	
	SCALE: 1" = 20'-0"	
	PATRICK ENGINEERING TEAM	
RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
3789816	APPD. BY: JEREMIAH SMITH	

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
WELD, X-RAY, NDT DOCUMENTATION
 56+00 - 74+00

DWG. NO: **W-104**


COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

WELD & X-RAY (NDT) DOCUMENTATION



HORIZONTAL SCALE 1" = 20'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: W-105 PLOTTED: Monday, November 14, 2022 - 11:30m USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 20 OF 59	SCALE: 1" = 20'-0"
NO. N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32	P-19	SYSTEM MAOP: 275 psig	3789816	APPD. BY: JEREMIAH SMITH	
					SYSTEM MOP: 145 psig		LOCH FYNE 20" GAS PIPELINE	
							COLORADO SPRINGS, COLORADO	
							WELD, X-RAY, NDT DOCUMENTATION	
							74+00 - 92+00	
							DWG. NO. W-105	



HP SERVICE:	<input type="checkbox"/>
DISTRIBUTION:	<input checked="" type="checkbox"/>
FEEDER:	<input type="checkbox"/>
TRANS. BY DEF.	<input type="checkbox"/>
TRANS v 20%:	<input type="checkbox"/>

ENGINEER: SCOTT JENSEN		PHONE: (719) 668-8196
PROJECT MANAGER: MELISSA LINGO		PHONE: (719) 668-8794
CONSTRUCTION LEAD: JOSH RICHARD		PHONE: (719) 668-3675
SHEET NO. 20 OF 59		
SCALE: 1" = 20'-0"		
PATRICK ENGINEERING TEAM		
DWN BY: NORM WEST		CHKD. BY: SETH BROWN
APPD. BY: JEREMIAH SMITH		

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

WELD & X-RAY (NDT) DOCUMENTATION

BLACK FOREST ROAD



HORIZONTAL SCALE 1" = 20'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: W-106 PLOTTED: Monday, November 14, 2022 - 11:17pm USER: mwest



PATRICK ENGINEERING
 8902 Vincennes Circle, Suite F
 Indianapolis, IN 46268
 TEL: (317) 217-1701
 www.patrickco.com
 PROJ. NO. 22282.003

REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS		3747144
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		
NO.	N/A	BY:	DATE:	APPVD:		
PERMIT INFORMATION	ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	FEEDER:	RELATED W/O #s
N/A	N/A	TWN. 12S, RNG. 65W, SECTION 31	P-18, P-19	SYSTEM MAOP: 275 psig	<input type="checkbox"/> HP SERVICE <input checked="" type="checkbox"/> DISTRIBUTION <input type="checkbox"/> FEEDER <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20%	3789816

ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
SHEET NO. 21 OF 59	SCALE: 1" = 20'-0"
PATRICK ENGINEERING TEAM	
DWN BY: NORM WEST	CHKD. BY: SETH BROWN
APPD. BY: JEREMIAH SMITH	

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
WELD, X-RAY, NDT DOCUMENTATION
 92+00 - 101+67

DWG. NO: **W-106**

WELD CHART - FABRICATION

TAG #	WELD #	COMP. #	WELD #	X-RAY DATE	X-RAY TYPE	RESULT	REPAIR	X-RAY DATE	X-RAY TYPE	RESULT	TAG #	WELD #	COMP. #	WELD #	X-RAY DATE	X-RAY TYPE	RESULT	REPAIR	X-RAY DATE	X-RAY TYPE	RESULT	TAG #	WELD #	COMP. #	WELD #	X-RAY DATE	X-RAY TYPE	RESULT	REPAIR	X-RAY DATE	X-RAY TYPE	RESULT	

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_3-8-22.dwg LAYOUT NAME: W-108 PLOTTED: Monday, November 14, 2022 - 11:19pm USER: nwest




PATRICK ENGINEERING
 8902 Vincennes Circle, Suite F
 Indianapolis, IN 46268
 TEL: (317) 217-1701
 www.patrickco.com
 PROJ. NO. 22282.003

REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #
4	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	SYSTEM MAOP: 275 psig	3747144
3	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	HP SERVICE: <input type="checkbox"/>	
2	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	DISTRIBUTION: <input checked="" type="checkbox"/>	
1	N/A	BY:	DATE:	APPVD:	FEEDER: <input type="checkbox"/>	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE
N/A				N/A	TWN. 12S, RNG. 65W, SECTIONS 31, 32, 33	R-18, R-19, Q-19, P-17, P-18, P-19
SYSTEM MAOP:				RELATED W/O #s		
SYSTEM MOP: 145 psig				3789816		
SYSTEM MOP:				TRANS. BY DEF. <input type="checkbox"/>		
				TRANS v 20% <input type="checkbox"/>		

ENGINEER: SCOTT JENSEN
 PROJECT MANAGER: MELISSA LINGO
 CONSTRUCTION LEAD: JOSH RICHARD
 SHEET NO. 23 OF 59
 SCALE: NTS
 PATRICK ENGINEERING TEAM
 DWN BY: NORM WEST
 CHKD. BY: SETH BROWN
 APPD. BY: JEREMIAH SMITH

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
WELD CHART
 DWG. NO. **W-108**

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Alignment\06 Colorado Springs\3-8-22.dwg LAYOUT NAME: C-200 PLOTTED: Tuesday, November 15, 2022 - 7:44am USER: nwest




CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
1 CP	INSTALL TEST STATIONS AT LOCATIONS SHOWN IN THE DESIGN PACKAGE.
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

CROSSING TABLE				
ITEM	CROSSING	SIZE	DEPTH (TOP PIPE)	MIN. VERT. SEPERATION
1	CSU HP GAS LINE	12"	FIELD VERIFY ¹	2'
2	CSU HP GAS LINE	12"	2.9"	2'
3	CSU HP GAS LINE	2"	FIELD VERIFY ¹	2'
4	CSU HP GAS LINE	2"	FIELD VERIFY ¹	2'
5	CSU HP GAS LINE	12"	3.1"	2'
6	CSU HP GAS LINE	12"	FIELD VERIFY ¹	2'


1 POT HOLE COULD NOT FIND



CSU SPECIFICATION VARIANCE APPROVAL REQUEST	
1	THE PROPOSED 20" CSU GAS LINE IN THE MCLINTOCH STATION IS ROUTED ADJACENT TO AND LESS THAN 15 FEET FROM A STATION BUILDING THAT IS NOT MEANT FOR HUMAN OCCUPANCY, AND A VARIANCE REQUEST IS BEING APPLIED FOR APPROVAL.
APPROVED BY	

PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

HIGH PRESSURE MATERIALS LIST (WO# 3747144)							
CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
3	4		220-647-920	20" ELBOW, 0.375" WT, STL, 45 DEG., 3R, WPHY 52	FORGED	FBE	
4	2		220-692-920	20" ELBOW, 0.375" WT, STL, 90 DEG., 3R, WPHY 52	FORGED	FBE	
6	13'		240-365-910	10" PIPE, STL, 0.365" WT, API 5L-X52, FBE	ERW	FBE	
7	4'		240-154-238	2" PIPE, STL, 0.154" WT, X-52, FBE		SMLS	
8	1		220-692-910	10" ELBOW, 0.365" WT, STL, 90 DEG., 3R, WPHY 52	FORGED	FBE	
9	1		215-792-920	REDUCER, WELD, WPHY52, CARBON STEEL, STD., 20IN X 12 NPS	FORGED	FBE	
10	1		215-790-100	REDUCER, WELD, WPHY52, CARBON STEEL, STD., 12IN X 10 NPS	FORGED	FBE	
11	1		220-700-920	20" TEE, WELD, WPHY 52, CARBON STEEL, STD. WALL	FORGED	FBE	
12	1		254-960-055	BRANCH CONNECTION, WELDOLET, CS, CL3000, 20"X2"	FORGED	N/A	
13	1		290-100-920	20" BALL VALVE, API 6D, CL150, VERTICAL GEAR OPERATED, FULL PORT, STD 0.375" WALL	FORGED	FBE	
14	1		290-100-911	10" BALL VALVE, API 6D, CL150, VERTICAL GEAR OPERATED, FULL PORT, STD 0.365" WALL	FORGED	FBE	
15	1		290-100-200	2" BALL VALVE, API 6D, CL150, VERTICAL GEAR OPERATED, FULL PORT, STD. 0.154" WALL	FORGED	FBE	



HIGH PRESSURE TIE-IN DETAIL
SCALE 1" = 10'-0"



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS				
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS				
NO.	N/A	BY:	DATE:	APPROV:				

PERMIT INFORMATION	ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	FEEDER:	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN	APPD. BY: JEREMIAH SMITH
N/A	N/A	SEC. 33 TOWN 12S, RANG. 65W	R-18			3789816			


PROJECT MANAGER: MELISSA LINGO
 CONSTRUCTION LEAD: JOSH RICHARD
 SHEET NO. 24 OF 59
 SCALE: AS NOTED
 PATRICK ENGINEERING TEAM
LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
PLAN & PROFILE
0+00 - 3+00

DWG. NO. C-200

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
3	1		220-647-920	20" ELBOW, 0.375" WT, STL, 45 DEG., 3R, WPHY 52	FORGED	FBE	




PLAN
HORIZONTAL SCALE 1" = 20'

CROSSING TABLE				
ITEM	CROSSING	SIZE	DEPTH (TOP OF PIPE)	MIN. VERT. SEPERATION
1	CENTURY-LINK TEL DUCT	4"1	FIELD VERIFY ¹	5'

1 POTHOLE COULD NOT FIND

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-201 PLOTTED: Tuesday, November 15, 2022 - 8:16am USER: nwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS		
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		3747144
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS		
NO.				N/A	BY: DATE: APPVD:	RELATED W/O #s
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE
N/A				N/A	SEC. 33 TWN. 12S, RNG. 65W	R-18, R-19


SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>
SYSTEM MOP: 145 psig	DISTRIBUTION: <input checked="" type="checkbox"/>
	FEEDER: <input type="checkbox"/>
	TRANS. BY DEF. <input type="checkbox"/>
	TRANS v 20% <input type="checkbox"/>

ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
SHEET NO. 25 OF 59	SCALE: AS NOTED
PATRICK ENGINEERING TEAM	
DWN BY: NORM WEST	CHKD. BY: SETH BROWN
APPD. BY: JEREMIAH SMITH	
LOCH FYNE 20" GAS PIPELINE	
COLORADO SPRINGS, COLORADO	
PLAN & PROFILE	
3+00 - 6+00	
DWG. NO. C-201	

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-202 PLOTTED: Tuesday, November 15, 2022 - 7:51 am USER: nwest

HIGH PRESSURE MATERIALS LIST (WO# 3747144)


CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
3	4		220-647-920	20" ELBOW, 0.375" WT, STL, 45 DEG., 3R, WPHY 52	FORGED	FBE	



CROSSING TABLE			
ITEM	CROSSING	SIZE	MIN. VERT. SEPERATION
1	MT. VIEW ELECTRIC DUCT	2"	FIELD VERIFY ¹ 2'

1 POT HOLE COULD NOT FIND

HORIZONTAL SCALE 1" = 20'



HORIZONTAL SCALE 1" = 20'



VERTICAL SCALE 1" = 10'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 26 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 33 TOWN, 12S, RANG. 65W	R-19	SYSTEM MAOP:	3789816	APPD. BY: JEREMIAH SMITH	
					SYSTEM MOP:		LOCH FYNE 20" GAS PIPELINE	
							COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							6+00 - 9+00	
							DWG. NO. C-202	



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES

2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
------	-----------------------------------------------------------------------------------------------------------------------


FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Springs_8-8-22.dwg LAYOUT NAME: C-203 PLOTTED: Monday, November 14, 2022 - 10:29pm USER: jsmith




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 27 OF 59	
NO. N/A				BY: DATE: APPVD:			PATTERN ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				N/A	SEC. 33 TWN. 12S, RNG. 65W	R-19	LOCH FYNE 20" GAS PIPELINE	
				SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	3747144	COLORADO SPRINGS, COLORADO	
				SYSTEM MOP: 145 psig	DISTRIBUTION: <input checked="" type="checkbox"/>	RELATED W/O #s	PLAN & PROFILE	
					FEEDER: <input type="checkbox"/>	3789816	9+00 - 12+00	
					TRANS. BY DEF. <input type="checkbox"/>		DWG. NO. C-203	
					TRANS v 20% <input type="checkbox"/>			

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



PLAN
HORIZONTAL SCALE 1" = 20'



PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.



CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-204 PLOTTED: Monday, November 14, 2022 - 1:45pm USER: mwest

				REVISIONS 5 ISSUED FOR CONSTRUCTION NEW 11/14/22 JMS 4 100% DESIGN PACKAGE ISSUED FOR REVIEW NEW 10/14/22 JMS 3 90% DESIGN PACKAGE ISSUED FOR REVIEW NEW 8/30/22 JMS NO. N/A BY: DATE: APPVD:		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	W/O # 3747144 RELATED W/O #s 3789816	ENGINEER: SCOTT JENSEN PHONE: (719) 668-8196 PROJECT MANAGER: MELISSA LINGO PHONE: (719) 668-8794 CONSTRUCTION LEAD: JOSH RICHARD PHONE: (719) 668-3675 SHEET NO. 28 OF 59 PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH
				PERMIT INFORMATION: N/A ISOLATION AREA: N/A LOCATION: SEC. 33 TWN. 12S, RNG. 65W SEC. 32 TWN. 12S, RNG. 65W ATLAS OR TITLE: R-19 SYSTEM MAOP: N/A SYSTEM MOP: N/A	LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 12+00 - 15+00 DWG. NO: C-204				

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	





CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-22.dwg LAYOUT NAME: C-205 PLOTTED: Monday, November 14, 2022 - 1:46pm USER: mwest

				REVISIONS 5 ISSUED FOR CONSTRUCTION NEW 11/14/22 JMS 4 100% DESIGN PACKAGE ISSUED FOR REVIEW NEW 10/14/22 JMS 3 90% DESIGN PACKAGE ISSUED FOR REVIEW NEW 8/30/22 JMS NO. N/A BY: DATE: APPVD:		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	W/O # 3747144 RELATED W/O #s 3789816	ENGINEER: SCOTT JENSEN PHONE: (719) 668-8196 PROJECT MANAGER: MELISSA LINGO PHONE: (719) 668-8794 CONSTRUCTION LEAD: JOSH RICHARD PHONE: (719) 668-3675 SHEET NO. 29 OF 59 PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH
				PERMIT INFORMATION N/A	ISOLATION AREA N/A	LOCATION SEC. 32 TWN. 12S, RNG. 65W	ATLAS OR TITLE R-19	SYSTEM MAOP: SYSTEM MOP:	LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 15+00 - 18+00 DWG. NO. C-205 COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-206 PLOTTED: Tuesday, November 15, 2022 - 7:58am USER: nwest



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
4	1		220-692-920	20" ELBOW, 0.375" WT, STL, 90 DEG., 3R, WPHY 52	FORGED	FBE	

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES




2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
------	-----------------------------------------------------------------------------------------------------------------------



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-8794
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 30 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	R-19 & Q-19	SYSTEM MAOP: 275 psig	3747144	LOCH FYNE 20" GAS PIPELINE	
					SYSTEM MOP: 145 psig	3789816	COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							18+00 - 21+00	
							DWG. NO. C-206	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

CROSSING TABLE				
ITEM	CROSSING	SIZE	DEPTH	MIN. VERT. SEPERATION
1	CENTURY-LINK TEL DUCT	4" ¹	FIELD VERIFY	5'
2	MT. VIEW ELECTRIC DUCT	3"	3.2'	5'

1 POTHOLE COULD NOT FIND

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-207 PLOTTED: Monday, November 14, 2022 - 1:55pm USER: mwest



REVISIONS			
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22 JMS
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22 JMS
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22 JMS
NO.	N/A	BY:	DATE: APPVD:

SYSTEM NAME:	150P
SYSTEM MAOP:	275 psig
SYSTEM MOP:	145 psig
PERMIT INFORMATION	N/A
ISOLATION AREA	N/A
LOCATION	SEC. 32 TWN. 12S, RNG. 65W
ATLAS OR TITLE	Q-19
SYSTEM MAOP:	
SYSTEM MOP:	


JOB TYPE:	
W/O #	3747144
RELATED W/O #s	3789816
HP SERVICE:	<input type="checkbox"/>
DISTRIBUTION:	<input checked="" type="checkbox"/>
FEEDER:	<input type="checkbox"/>
TRANS. BY DEF.	<input type="checkbox"/>
TRANS v 20%:	<input type="checkbox"/>

ENGINEER:	SCOTT JENSEN	PHONE:	(719) 668-8196
PROJECT MANAGER:	MELISSA LINGO	PHONE:	(719) 668-8794
CONSTRUCTION LEAD:	JOSH RICHARD	PHONE:	(719) 668-3675
SHEET NO.	31 OF 59	SCALE:	AS NOTED
PATRICK ENGINEERING TEAM			
DWN BY:	NORM WEST	CHKD. BY:	SETH BROWN
APPD. BY:	JEREMIAH SMITH		
LOCH FYNE 20" GAS PIPELINE			
COLORADO SPRINGS, COLORADO			
PLAN & PROFILE			
21+00 - 24+00			
			DWG. NO. C-207


FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-208 PLOTTED: Tuesday, November 15, 2022 - 9:00am USER: nwest

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	355'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
4	3		220-692-920	20" ELBOW, 0.375" WT, STL, 90 DEG., 3R, WPHY 52	FORGED	FBE	



HORIZONTAL SCALE 1" = 20'



VERTICAL SCALE 1" = 10'




HORIZONTAL SCALE 1" = 20'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794	
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675	
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 32 OF 59		
NO.	N/A	BY:	DATE:	APPVD:			PATRICK ENGINEERING TEAM		
PERMIT INFORMATION		ISOLATION AREA		LOCATION		ATLAS OR TITLE		N/A	
N/A		N/A		SEC. 32 TWN. 12S, RNG. 65W		Q-19		SYSTEM MAOP: 275 psig	
								SYSTEM MOP: 145 psig	
								HP SERVICE: <input type="checkbox"/>	
								DISTRIBUTION: <input checked="" type="checkbox"/>	
								FEEDER: <input type="checkbox"/>	
								TRANS. BY DEF. <input type="checkbox"/>	
								TRANS v 20% <input type="checkbox"/>	
								RELATED W/O #s	
								3789816	
								DWN BY: NORM WEST	
								CHKD. BY: SETH BROWN	
								APPD. BY: JEREMIAH SMITH	
								SCALE: AS NOTED	
								LOCH FYNE 20" GAS PIPELINE	
								COLORADO SPRINGS, COLORADO	
								PLAN & PROFILE	
								24+00 - 27+00	
								DWG. NO. C-208	




HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	


CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-209 PLOTTED: Monday, November 14, 2022 - 2:05pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 3.3 OF 59	
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19	LOCH FYNE 20" GAS PIPELINE	
				SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	3747144	COLORADO SPRINGS, COLORADO	
				SYSTEM MOP: 145 psig	DISTRIBUTION: <input checked="" type="checkbox"/>	RELATED W/O #s	PLAN & PROFILE	
					FEEDER: <input type="checkbox"/>	3789816	27+00 - 30+00	
					TRANS. BY DEF. <input type="checkbox"/>		DWG. NO. C-209	
					TRANS v 20% <input type="checkbox"/>		COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.	




40' WIDE EASEMENT
SEE PROPERTY EXHIBIT
TURKEY CANNON CREEK
QUARRY, EXHIBITS A-B-C
SIGNED FIMS 720813
FOR DETAILS

1,209' X 167'
TEMPORARY WORKSPACE

PULLBACK ALIGNMENT

PLAN

HORIZONTAL SCALE 1" = 20'



PROFILE

HORIZONTAL SCALE 1" = 20'



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES

2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
------	-----------------------------------------------------------------------------------------------------------------------

FILE NAME: P:\indianapolis\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-210 PLOTTED: Monday, November 14, 2022 - 2:10pm USER: mwest




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 33 OF 59	SCALE: AS NOTED
NO.	N/A	BY:	DATE:	APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA		LOCATION	ATLAS OR TITLE	N/A	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A		SEC. 32 TWN. 12S, RNG. 65W	Q-19		APPD. BY: JEREMIAH SMITH	
				SYSTEM MAOP:		RELATED W/O #s	LOCH FYNE 20" GAS PIPELINE	
				SYSTEM MOP:		3789816	COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							30+00 - 33+00	
							DWG. NO. C-210	

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_3-8-22.dwg LAYOUT NAME: C-211 PLOTTED: Monday, November 14, 2022 - 2:15pm USER: mwest

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



40' WIDE EASEMENT
SEE PROPERTY EXHIBIT
TURKEY CANNON CREEK
QUARRY, EXHIBITS A-B-C
SIGNED FIMS 720813
FOR DETAILS


1,209' X 167'
TEMPORARY WORKSPACE

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES


2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
------	-----------------------------------------------------------------------------------------------------------------------



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS		3747144		PROJECT MANAGER: MELISSA LINGO PHONE: (719) 668-8794
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS				CONSTRUCTION LEAD: JOSH RICHARD PHONE: (719) 668-3675
NO.	N/A	BY:	DATE:	APPVD:				SHEET NO. 35 OF 59 SCALE: AS NOTED
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	PATRICK ENGINEERING TEAM
N/A				N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19		DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH
SYSTEM MAOP: 275 psig				SYSTEM MOP: 145 psig	HP SERVICE: <input type="checkbox"/>	RELATED W/O #s	3789816	
SYSTEM MAOP:				SYSTEM MOP:	DISTRIBUTION: <input checked="" type="checkbox"/>			
					FEEDER: <input type="checkbox"/>			
					TRANS. BY DEF. <input type="checkbox"/>			
					TRANS v 20% <input type="checkbox"/>			
LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 33+00 - 36+00								DWG. NO: C-211



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	400'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
4	2		220-692-920	20" ELBOW, 0.375" WT, STL, 90 DEG., 3R, WPHY 52	FORGED	FBE	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003






REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 36 OF 59	SCALE: AS NOTED
NO.				N/A	BY:	DATE:	APPVD:	PATRICK ENGINEERING TEAM
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19	SYSTEM MAOP: 275 psig			
					SYSTEM MOP: 145 psig			
						HP SERVICE: <input type="checkbox"/>	RELATED W/O #s	
						DISTRIBUTION: <input checked="" type="checkbox"/>	3747144	
						FEEDER: <input type="checkbox"/>	3789816	
						TRANS. BY DEF. <input type="checkbox"/>		
						TRANS v 20% <input type="checkbox"/>		
LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 36+00 - 40+00								DWG. NO: C-212

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-212 PLOTTED: Tuesday, November 15, 2022 - 8:32am USER: nwest

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-213 PLOTTED: Monday, November 14, 2022 - 2:25pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS				
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS				
NO.	N/A	BY:	DATE:	APPVD:				
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A			
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19				
					SYSTEM MAOP: 275 psig			
					SYSTEM MOP: 145 psig			

HP SERVICE: <input type="checkbox"/>	3747144	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
DISTRIBUTION: <input checked="" type="checkbox"/>		PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
FEEDER: <input type="checkbox"/>		CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
TRANS. BY DEF. <input type="checkbox"/>		SHEET NO. 37 OF 59	
TRANS v 20% <input type="checkbox"/>		SCALE: AS NOTED	
	3789816	PATRICK ENGINEERING TEAM	
		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
		APPD. BY: JEREMIAH SMITH	





LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
PLAN & PROFILE
40+00 - 43+00

DWG. NO. **C-213**

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Springs_8-22.dwg LAYOUT NAME: C-214 PLOTTED: Tuesday, November 15, 2022 - 9:22am USER: nwest






REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 38 OF 59	SCALE: AS NOTED
NO. N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TOWN. 12S, RANG. 65W	Q-19			APPD. BY: JEREMIAH SMITH	
				SYSTEM MAOP:	275 psig		LOCH FYNE 20" GAS PIPELINE	
				SYSTEM MOP:	145 psig		COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							43+00 - 46+00	
							DWG. NO. C-214	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	60'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
2	240'		241-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE/ARO	ERW	FBE/ARO	
3	1		220-647-920	20" ELBOW, 0.375" WT, STL, 45 DEG., 3R, WPHY 52	FORGED	FBE	

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-215 PLOTTED: Tuesday, November 15, 2022 - 9:28am USER: nwest



				REVISIONS 5 ISSUED FOR CONSTRUCTION NEW 11/14/22 JMS 4 100% DESIGN PACKAGE ISSUED FOR REVIEW NEW 10/14/22 JMS 3 90% DESIGN PACKAGE ISSUED FOR REVIEW NEW 8/30/22 JMS NO. N/A BY: DATE: APPVD:		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	W/O # 3747144 RELATED W/O #s 3789816	ENGINEER: SCOTT JENSEN PHONE: (719) 668-8196 PROJECT MANAGER: MELISSA LINGO PHONE: (719) 668-8794 CONSTRUCTION LEAD: JOSH RICHARD PHONE: (719) 668-3675 SHEET NO. 39 OF 59 SCALE: AS NOTED PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH
				PERMIT INFORMATION N/A	ISOLATION AREA N/A	LOCATION SEC. 32 TWN. 12S, RNG. 65W	ATLAS OR TITLE Q-19	SYSTEM MAOP: SYSTEM MOP:	LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 46+00 - 49+00 DWG. NO. C-215

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
2	300'		241-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE/ARO	ERW	FBE/ARO	

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.


CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-216 PLOTTED: Monday, November 14, 2022 - 2:45pm USER: mwest




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794	
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675	
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 40 OF 59	SCALE: AS NOTED	
NO.	N/A	BY:	DATE:	APPVD:			PATRICK ENGINEERING TEAM		
PERMIT INFORMATION		ISOLATION AREA		LOCATION		ATLAS OR TITLE		N/A	
N/A		N/A		SEC. 32 TWN. 12S, RNG. 65W		Q-19		SYSTEM MAOP:	
								SYSTEM MOP:	
								HP SERVICE: <input type="checkbox"/>	
								DISTRIBUTION: <input checked="" type="checkbox"/>	
								FEEDER: <input type="checkbox"/>	
								TRANS. BY DEF. <input type="checkbox"/>	
								TRANS v 20% <input type="checkbox"/>	
						RELATED W/O #s		3789816	
								DWN BY: NORM WEST	
								CHKD. BY: SETH BROWN	
								APPD. BY: JEREMIAH SMITH	
								LOCH FYNE 20" GAS PIPELINE	
								COLORADO SPRINGS, COLORADO	
								PLAN & PROFILE	
								49+00 - 52+00	
								DWG. NO. C-216	



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
2	300'		241-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE/ARO	ERW	FBE/ARO	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-217 - RLOTEDL Monday, November 14, 2022 - 2:48pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 41 OF 59	SCALE: AS NOTED
NO.	N/A	BY:	DATE:	APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19	SYSTEM MAOP:	3789816	APPD. BY: JEREMIAH SMITH	
					SYSTEM MOP:		LOCH FYNE 20" GAS PIPELINE	
							COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							52+00 - 55+00	
							DWG. NO. C-217	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
2	300'		241-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE/ARO	ERW	FBE/ARO	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20in Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-218 PLOTTED: Monday, November 14, 2022 - 2:54pm USER: mwest



REVISIONS				SYSTEM NAME: 150P		JOB TYPE:		W/O #		ENGINEER: SCOTT JENSEN		PHONE: (719) 668-8196	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	DISTRIBUTION: <input checked="" type="checkbox"/>	3747144	PROJECT MANAGER: MELISSA LINGO			PHONE: (719) 668-8794	
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS					CONSTRUCTION LEAD: JOSH RICHARD			PHONE: (719) 668-3675	
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS					SHEET NO. 42 OF 59			SCALE: AS NOTED	
N/A				BY:	DATE:	APPVD:	3789816		PATRICK ENGINEERING TEAM				
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE		N/A		DWN BY: NORM WEST		CHKD. BY: SETH BROWN		APPD. BY: JEREMIAH SMITH	
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19		SYSTEM MAOP: 145 psig		TRANS. BY DEF. <input type="checkbox"/>		LOCH FYNE 20" GAS PIPELINE		DWG. NO. C-218	
						SYSTEM MOP:		TRANS v 20% <input type="checkbox"/>		COLORADO SPRINGS, COLORADO		55+00 - 58+00	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
2	300'		241-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE/ARO	ERW	FBE/ARO	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003



FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-219 PLOTTED: Monday, November 14, 2022 - 3:00pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196	
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794	
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675	
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 4-3 OF 59	SCALE: AS NOTED	
NO.	N/A	BY:	DATE:	APPVD:			PATRICK ENGINEERING TEAM		
PERMIT INFORMATION		ISOLATION AREA		LOCATION		ATLAS OR TITLE		N/A	
N/A		N/A		SEC. 32 TWN. 12S, RNG. 65W		Q-19		SYSTEM MAOP:	
								SYSTEM MOP:	
								HP SERVICE: <input type="checkbox"/>	
								DISTRIBUTION: <input checked="" type="checkbox"/>	
								FEEDER: <input type="checkbox"/>	
								TRANS. BY DEF. <input type="checkbox"/>	
								TRANS v 20% <input type="checkbox"/>	
								RELATED W/O #s	
						3789816		DWN BY: NORM WEST	
								CHKD. BY: SETH BROWN	
								APPD. BY: JEREMIAH SMITH	
								LOCH FYNE 20" GAS PIPELINE	
								COLORADO SPRINGS, COLORADO	
								PLAN & PROFILE	
								58+00 - 61+00	
								DWG. NO. C-219	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
3	1		220-647-920	20" ELBOW, 0.375" WT, STL, 45 DEG., 3R, WPHY 52	FORGED	FBE	





CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
1 CP	NOT ON THIS SHEET.
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\08 Colorado Springs_8-22.dwg LAYOUT NAME: C-220 PLOTTED: Tuesday, November 15, 2022 - 9:15am USER: nwest


<p>Colorado Springs Utilities It's how we're all connected</p>	<p>JEREMIAH SMITH PROFESSIONAL ENGINEER 2022.11.15 09:27:46-09:00</p>	<p>8902 Vincennes Circle, Suite F Indianapolis, IN 46268 TEL: (317) 217-1701 www.patrickco.com</p> <p>PROJ. NO. 22282.003</p>	REVISIONS 5 ISSUED FOR CONSTRUCTION NEW 11/14/22 JMS 4 100% DESIGN PACKAGE ISSUED FOR REVIEW NEW 10/14/22 JMS 3 90% DESIGN PACKAGE ISSUED FOR REVIEW NEW 8/30/22 JMS NO. N/A BY: DATE: APPVD:		SYSTEM NAME: 150P SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	JOB TYPE: HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	W/O # 3747144 RELATED W/O #s 3789816	ENGINEER: SCOTT JENSEN PHONE: (719) 668-8196 PROJECT MANAGER: MELISSA LINGO PHONE: (719) 668-8794 CONSTRUCTION LEAD: JOSH RICHARD PHONE: (719) 668-3675 SHEET NO. 44 OF 59 PATRICK ENGINEERING TEAM DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH
			PERMIT INFORMATION N/A	ISOLATION AREA N/A	LOCATION SEC. 32 TWN. 12S, RNG. 65W	ATLAS OR TITLE Q-19	SYSTEM MAOP: SYSTEM MOP:	LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 61+00 - 64+00 DWG. NO. C-220 COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Springs_8-8-22.dwg LAYOUT NAME: C-221 PLOTTED: Tuesday, November 15, 2022 - 9:34am USER: nwest



CROSSING TABLE					
ITEM	CROSSING	SIZE	DEPTH (TOP OF PIPE)	MIN. VERT. SEPERATION	MIN. HORZ. SEPERATION
1	MT. VIEW ELECTRIC DUCT	4"	3'-1"	5'	6'
2	CCPPW STORM	36"	8.4'-1"	5'	10'
3	CENTURY-LINK FO DUCT	4"	13.4'-1"	5'	6'

- 1 PROPOSED UTILITIES, VERIFY DEPTH AND LOCATION BEFORE CONSTRUCTION.
- 2. CCPPW- COLORADO CITY OF PARKS AND PUBLIC WORKS.



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	200'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
3	3		220-647-920	20" ELBOW, 0.375" WT, STL, 45 DEG., 3R, WPHY 52	FORGED	FBE	

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
1 CP	INSTALL TEST STATIONS AT LOCATIONS SHOWN IN THE DESIGN PACKAGE.
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003





REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 45 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:	SYSTEM MAOP: 275 psig	RELATED W/O #s	PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	DWN BY: NORM WEST
N/A				N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19	SYSTEM MAOP: 145 psig	CHKD. BY: SETH BROWN
N/A				N/A	N/A	N/A	APPD. BY: JEREMIAH SMITH	

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
PLAN & PROFILE
64+00 - 66+00

DWG. NO: **C-221**

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	200'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
4	2		220-692-920	20" ELBOW, 0.375" WT, STL, 90 DEG., 3R, WPHY 52	FORGED	FBE	




CROSSING TABLE				
ITEM	CROSSING	SIZE	DEPTH (TOP OF PIPE)	MIN. VERT. SEPERATION
1	CSU PROP LP GAS LINE	4"	14.9 ¹	1'
2	CENTURY-LINK ABANDON FO DUCT	2"	2.5 ²	NONE
3	CENTURY-LINK ABANDON FO DUCT	2"	2.5 ²	NONE
4	CENTURY-LINK ABANDON FO DUCT	2"	2.5 ²	NONE
5	CSU ABANDON LP GAS LINE	4"	5.2 ³	NONE
6	CCPPW ⁶ PROP. RCP STORM	36"	8.7 ⁴	5'
7	CENTURY-LINK ABANDON FO DUCT	2"	2.1 ²	NONE
8	CENTURY-LINK ABANDON FO DUCT	2"	2.2 ²	NONE
9	CENTURY-LINK ABANDON FO DUCT	2"	2.3 ²	NONE
10	CENTURY-LINK ABANDON FO DUCT	2"	2.9 ²	NONE
11	PROP. FO DUCT	4"	5.6 ⁵	5'

- (1) PROPOSED CSU PROPOSED LP LINE LINE, VERIFY DEPTH AND LOCATION BEFORE CONSTRUCTION. THE DEPTH IS BASED ON THE NEED TO CROSS A PROPOSED STORM SEWER.
- (2, 3, 4, 7, 8, 9, 10) FIBER OPTIC DUCTS ARE EXPECTED TO BE ABANDON IN PLACE, BUT THEY MAY HAVE BEEN REMOVED DURING ROAD CONSTRUCTION.
- (5) EXISTING CSU 4" LP GAS LINE THAT WILL BE ABANDON. DEPTH IS MEASURED FROM TOP OF THE PROPOSED BLACK FOREST RD.
- (6) PROPOSED STORM SEWER, VERIFY LOCATION AND DEPTH BEFORE CONSTRUCTION.
- (11) PROPOSED FO DUCT, VERIFY LOCATION AND DEPTH BEFORE CONSTRUCTION. (MIN. 10' HORIZONTAL SEPERATION).
- CCPPW - COLORADO CITY PARKS AND PUBLIC WORKS.


CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPERATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
1 CP	INSTALL TEST STATIONS AT LOCATIONS SHOWN IN THE DESIGN PACKAGE.
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003


FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-222 PLOTTED: Tuesday, November 15, 2022 - 9:38am USER: nwest



Colorado Springs Utilities
It's how we're all connected



Jeremiah Smith
2022.11.15 09:27:46-09:00



PATRICK ENGINEERING

8902 Vincennes Circle, Suite F
Indianapolis, IN 46268
TEL: (317) 217-1701
www.patrickco.com


PROJ. NO. 22282.003

REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-8794
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 46 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:		RELATED W/O #s	PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	3789816	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19	SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig		LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 66+00 - 68+00	


DWG. NO. **C-222**

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-223 PLOTTED: Monday, November 14, 2022 - 3:34pm USER: mwest



HORIZONTAL SCALE 1" = 20'



HORIZONTAL SCALE 1" = 20'

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	

CONSTRUCTION NOTES

- 4 MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
- 6 BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
- 10 WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
- 11 THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
- 14 CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES

- 2 CP STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

CROSSING TABLE

SIZE	CROSSING	SIZE	DEPTH (TOP OF PIPE)	MIN. VERT. SEPERATION	MIN. HORZ. SEPERATION
1	PROP. CENTURY-LINK FO DUCT	4"	-	-	10'
2	CCPPW RCP STORM	15"	7.2'	2'	-
3	CCPPW RCP STORM	15"	7.7'	2'	-

CCPPW - COLORADO CITY PARKS AND PUBLIC WORKS





REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 47 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TOWN 12S, RANG. 65W	Q-19			APPD. BY: JEREMIAH SMITH	
					SYSTEM MAOP: 275 psig	3747144		
					SYSTEM MOP: 145 psig	RELATED W/O #s		
						3789816		
					HP SERVICE: <input type="checkbox"/>		LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 68+00 - 71+00	
					DISTRIBUTION: <input checked="" type="checkbox"/>			
					FEEDER: <input type="checkbox"/>			
					TRANS. BY DEF. <input type="checkbox"/>			
					TRANS v 20% <input type="checkbox"/>			

DWG. NO. C-223

COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-22.dwg LAYOUT NAME: C-224 PLOTTED: Monday, November 14, 2022 - 3:46pm USER: nwest



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES


2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
---------	-----------------------------------------------------------------------------------------------------------------------




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 48 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	Q-19 & P-19			APPD. BY: JEREMIAH SMITH	
				SYSTEM MAOP:	275 psig		LOCH FYNE 20" GAS PIPELINE	
				SYSTEM MOP:	145 psig		COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							71+00 - 74+00	
							DWG. NO. C-224	
							COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



PLAN
HORIZONTAL SCALE 1" = 20'



PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-225 PLOTTED: Monday, November 14, 2022 - 3:50pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 49 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 32 TWN. 12S, RNG. 65W	P-19		3789816	APPD. BY: JEREMIAH SMITH	

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
PLAN & PROFILE
74+00 - 77+00

DWG. NO. C-225


HP SERVICE:
DISTRIBUTION:
FEEDER:
TRANS. BY DEF.
TRANS v 20%

Copyright Protected © 2018 Patrick Engineering Inc.


FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-226 PLOTTED: Monday, November 14, 2022 - 3:58pm USER: nwest

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



PLAN
HORIZONTAL SCALE 1" = 20'



PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003





REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 50 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 31 TWN. 12S, RNG. 65W	P-19		3789816	APPD. BY: JEREMIAH SMITH	
					HP SERVICE: <input type="checkbox"/>		LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 77+00 - 80+00	
					DISTRIBUTION: <input checked="" type="checkbox"/>			
					FEEDER: <input type="checkbox"/>			
					TRANS. BY DEF. <input type="checkbox"/>		DWG. NO: C-226	
					TRANS v 20% <input type="checkbox"/>		COPYRIGHT PROTECTED © 2018 PATRICK ENGINEERING INC.	

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\1 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-22.dwg LAYOUT NAME: C-227 PLOTTED: Monday, November 14, 2022 - 4:08pm USER: mwest

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.


CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 51 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				N/A	SEC. 31 TWN. 12S, RNG. 65W	P-19	LOCH FYNE 20" GAS PIPELINE	
				SYSTEM MAOP: 275 psig	SYSTEM MOP: 145 psig		COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							80+00 - 83+00	
							DWG. NO. C-227	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



PLAN
HORIZONTAL SCALE 1" = 20'



PROFILE
VERTICAL SCALE 1" = 10'
HORIZONTAL SCALE 1" = 20'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.



CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-22.dwg LAYOUT NAME: C-228 PLOTTED: Monday, November 14, 2022 - 4:15pm USER: mwest

<p>Colorado Springs Utilities It's how we're all connected</p>	<p>Jeremiah Smith 2022.11.15 09:27:46-0000 PROFESSIONAL ENGINEER</p>	<p>8902 Vincennes Circle, Suite F Indianapolis, IN 46268 TEL: (317) 217-1701 www.patrickco.com PROJ. NO. 22282.003</p>	REVISIONS		SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN PHONE: (719) 668-8196	
			5 ISSUED FOR CONSTRUCTION NEW 11/14/22 JMS	4 100% DESIGN PACKAGE ISSUED FOR REVIEW NEW 10/14/22 JMS	3 90% DESIGN PACKAGE ISSUED FOR REVIEW NEW 8/30/22 JMS	NO. N/A BY: DATE: APPVD:	SYSTEM MAOP: 275 psig SYSTEM MOP: 145 psig	HP SERVICE: <input type="checkbox"/> DISTRIBUTION: <input checked="" type="checkbox"/> FEEDER: <input type="checkbox"/> TRANS. BY DEF. <input type="checkbox"/> TRANS v 20% <input type="checkbox"/>	3747144 RELATED W/O #s 3789816
PERMIT INFORMATION: N/A ISOLATION AREA: N/A LOCATION: SEC. 31 TWN. 12S, RNG. 65W ATLAS OR TITLE: P-19 SYSTEM MAOP: N/A SYSTEM MOP: N/A			LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 83+00 - 86+00						DWG. NO: C-228

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.


CATHODIC PROTECTION NOTES

2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
---------	-----------------------------------------------------------------------------------------------------------------------


FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-22.dwg LAYOUT NAME: C-229 PLOTTED: Monday, November 14, 2022 - 4:23pm USER: mwest

<p>Colorado Springs Utilities It's how we're all connected</p>	<p>JEREMIAH SMITH 2022.11.15 09:27:46-09:00 PROFESSIONAL ENGINEER</p>	<p>8902 Vincennes Circle, Suite F Indianapolis, IN 46268 TEL: (317) 217-1701 www.patrickco.com</p> <p>PROJ. NO. 22282.003</p>	<p>REVISIONS</p> <table border="1"> <tr> <td>5</td> <td>ISSUED FOR CONSTRUCTION</td> <td>NEW</td> <td>11/14/22</td> <td>JMS</td> </tr> <tr> <td>4</td> <td>100% DESIGN PACKAGE ISSUED FOR REVIEW</td> <td>NEW</td> <td>10/14/22</td> <td>JMS</td> </tr> <tr> <td>3</td> <td>90% DESIGN PACKAGE ISSUED FOR REVIEW</td> <td>NEW</td> <td>8/30/22</td> <td>JMS</td> </tr> <tr> <td>NO.</td> <td>N/A</td> <td>BY:</td> <td>DATE:</td> <td>APPVD:</td> </tr> </table>		5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS	4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	NO.	N/A	BY:	DATE:	APPVD:	<p>SYSTEM NAME: 150P</p> <p>SYSTEM MAOP: 275 psig</p> <p>SYSTEM MOP: 145 psig</p>	<p>JOB TYPE:</p> <p>HP SERVICE: <input type="checkbox"/></p> <p>DISTRIBUTION: <input checked="" type="checkbox"/></p> <p>FEEDER: <input type="checkbox"/></p> <p>TRANS. BY DEF. <input type="checkbox"/></p> <p>TRANS v 20% <input type="checkbox"/></p>	<p>W/O #</p> <p>3747144</p> <p>RELATED W/O #s</p> <p>3789816</p>	<p>ENGINEER: SCOTT JENSEN</p> <p>PROJECT MANAGER: MELISSA LINGO</p> <p>CONSTRUCTION LEAD: JOSH RICHARD</p> <p>SHEET NO. 5.3 OF 59</p> <p>DWN BY: NORM WEST</p> <p>CHKD. BY: SETH BROWN</p> <p>APPD. BY: JEREMIAH SMITH</p>	<p>PHONE: (719) 668-8196</p> <p>PHONE: (719) 668-8794</p> <p>PHONE: (719) 668-3675</p> <p>SCALE: AS NOTED</p> <p>PATRICK ENGINEERING TEAM</p>
			5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS																						
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS																									
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS																									
NO.	N/A	BY:	DATE:	APPVD:																									
<p>PERMIT INFORMATION: N/A</p> <p>ISOLATION AREA: N/A</p> <p>LOCATION: SEC. 31 TWN. 12S, RNG. 65W</p> <p>ATLAS OR TITLE: P-19</p>			<p>SYSTEM MAOP: N/A</p> <p>SYSTEM MOP: N/A</p>		<p>LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 86+00 - 89+00</p> <p>DWG. NO. C-229</p>																								

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-230 PLOTTED: Monday, November 14, 2022 - 4:31pm USER: mwest



PLAN
HORIZONTAL SCALE 1" = 20'



PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES


2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
------	-----------------------------------------------------------------------------------------------------------------------



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 54 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				N/A	SEC. 31 TWN. 12S, RNG. 65W	P-19 & P-18	LOCH FYNE 20" GAS PIPELINE	
N/A				SYSTEM MAOP: 275 psig	SYSTEM MOP: 145 psig		COLORADO SPRINGS, COLORADO	
N/A				SYSTEM MAOP:	SYSTEM MOP:		PLAN & PROFILE	
N/A							89+00 - 92+00	
N/A							DWG. NO. C-230	


HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	



PLAN

HORIZONTAL SCALE 1" = 20'



PROFILE

HORIZONTAL SCALE 1" = 20'

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.

CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-22.dwg LAYOUT NAME: C-231 PLOTTED: Monday, November 14, 2022 - 4:39pm USER: mwest



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 55 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				N/A	SEC. 31 TWN. 12S, RNG. 65W	P-18	LOCH FYNE 20" GAS PIPELINE	
N/A				SYSTEM MAOP: 275 psig	SYSTEM MOP: 145 psig		COLORADO SPRINGS, COLORADO	
N/A				SYSTEM MAOP:	SYSTEM MOP:		PLAN & PROFILE	
N/A							92+00 - 95+00	

HP SERVICE:	<input type="checkbox"/>
DISTRIBUTION:	<input checked="" type="checkbox"/>
FEEDER:	<input type="checkbox"/>
TRANS. BY DEF.	<input type="checkbox"/>
TRANS v 20%:	<input type="checkbox"/>



3747144

3789816

DWG. NO. C-231

LOCH FYNE 20" GAS PIPELINE
COLORADO SPRINGS, COLORADO
PLAN & PROFILE
92+00 - 95+00

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-8-22.dwg LAYOUT NAME: C-232 PLOTTED: Monday, November 14, 2022 - 4:46pm USER: mwest



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	

CONSTRUCTION NOTES

4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.



CATHODIC PROTECTION NOTES

2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003
------	-----------------------------------------------------------------------------------------------------------------------



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS	SYSTEM MAOP: 275 psig	3747144	CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS	SYSTEM MOP: 145 psig		SHEET NO. 56 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	RELATED W/O #s	DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 31 TWN. 12S, RNG. 65W	P-18	SYSTEM MAOP:	3789816	APPD. BY: JEREMIAH SMITH	
					SYSTEM MOP:		LOCH FYNE 20" GAS PIPELINE	
							COLORADO SPRINGS, COLORADO	
							PLAN & PROFILE	
							95+00 - 98+00	
							DWG. NO. C-232	

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\Colorado Springs_8-8-22.dwg LAYOUT NAME: C-233 PLOTTED: Monday, November 14, 2022 - 4:55pm USER: mwest



HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	300'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
4	1		220-692-920	20" ELBOW, 0.375" WT, STL, 90 DEG., 3R, WPHY 52	N/A	FBE	

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.


CATHODIC PROTECTION NOTES	
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 57 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	DWN BY: NORM WEST CHKD. BY: SETH BROWN APPD. BY: JEREMIAH SMITH	
N/A				N/A	SEC. 31 TWN. 12S, RNG. 65W	P-18	LOCH FYNE 20" GAS PIPELINE	
N/A				SYSTEM MAOP: 275 psig	SYSTEM MOP: 145 psig		COLORADO SPRINGS, COLORADO	
N/A				SYSTEM MAOP:	SYSTEM MOP:		PLAN & PROFILE	
N/A							98+00 - 101+00	
N/A							DWG. NO. C-233	

HIGH PRESSURE MATERIALS LIST (WO# 3747144)

CODE	DESIGN QTY.	AS-BUILT QTY.	STOCK ID	DESCRIPTION	SEAM	COATING	COMPONENT NO.
1	62'		240-375-920	20" PIPE, STL, 0.375" WT, API 5L-X52, FBE	ERW	FBE	
5	1		215-796-920	REDUCER, WELD, WPHY52, CARBON STEEL, STD., 20IN X 16 NPS	FORGED	FBE	



PLAN
HORIZONTAL SCALE 1" = 20'



PROFILE
HORIZONTAL SCALE 1" = 20'
VERTICAL SCALE 1" = 10'

WEST TIE-IN PROCEDURE NOTES	
1	AFTER THE TIE-IN OF THE NEW 20" GAS LINE TO THE NEWLY INSTALLED 16" LINE IS COMPLETED, COMPLETE THE PURGE OUT OF AIR FROM THE NEW 20" LINE AND PACK WITH GAS (SEE PURGE PROCEDURE FOR ADDITIONAL INFORMATION).
2	REMOVE THE BLIND FLANGE FROM THE EXISTING 16" SPHERICAL TEE, AND INSTALL A TEMPORARY 16" TAPPING FULL PORT BALL VALVE, THEN INSTALL TAPPING MACHINE.
3	OPEN THE TAPPING VALVE AND USE THE TAPPING MACHINE TO REMOVE THE INNER PLUG IN THE SPHERICAL TEE. THEN RECLOSE THE VALVE, AND REMOVE THE TAPPING MACHINE WITH THE INNER PLUG.
4	REINSTALL THE TAPPING MACHINE WITH A CUTTER HEAD ON THE TAPPING VALVE. CUT OUT THE COUPON FROM THE EXISTING 16" PIPE AND WITHDRAW THE COUPON. CLOSE THE TAPPING VALVE AND REMOVE THE TAPPING MACHINE AND COUPON.
5	REINSTALL THE TAPPING MACHINE WITH A STOPPLE PLUG REOPEN THE TAPPING VALVE AND SET THE STOPPLE PLUG IN PLACE.
5	WITH THE STOPPLE IN PLACE, COMPLETE THE PURGE OF THE EXISTING 16" SECTION TO BE RETIRED USING A CSU PREPARED PURGE PROCEDURE. ONCE THE LINE HAS BEEN PURGE, COLD-CUT OUT A SECTION OF THE 16" PIPE BETWEEN THE NEW AND EXISTING 16" LINE AND INSTALL 16" WED CAPS ON EACH END.
7	REMOVE AND WITHDRAW THE STOPPLE PLUG AND RECLOSE THE TAPPING VALVE. THEN REMOVE THE TAPPING MACHINE WITH THE STOPPLE.
8	REINSTALL THE TAPPING MACHINE WITH THE INNER PLUG TO THE TAPPING VALVE. THEN REOPEN THE TAPPING VALVE AND REINSTALL INNER PLUG IN THE SPHERICAL TEE. REMOVE TAPPING MACHINE AND TAPPING VALVE AND REPLACE BLIND FLANGE TO SPHERICAL TEE.

CONSTRUCTION NOTES	
4	MINIMUM DEPTH OF COVER FOR THE ENTIRE PIPELINE IS 5'. THE PIPELINE SHALL MEET THE MINIMUM VERTICAL SEPARATION FROM UTILITIES BEING CROSSED AS INDICATED IN THE CROSSING TABLES.
6	BACKFILL OF THE TRENCH SHALL NOT BE COMPLETED UNTIL ALL WELDS HAVE BEEN GPS'ED
10	WELDING SHALL BE COMPLETED IN ACCORDANCE WITH THE MOST CURRENT VERSIONS OF API 1104, AND CSU APPROVED WELDING PROCEDURES. WELDERS SHALL BE REQUIRED TO QUALIFY ON THE CSU APPROVED WELDING PROCEDURES.
11	THE PIPE SEGMENTS SHALL BE AIR TESTED IN ACCORDANCE WITH CSU STANDARD PROCEDURES.
14	CONTRACTOR SHALL RESTORE ALL CONSTRUCTION AREAS, AND REMOVE ALL TRASH, DEBRIS, AND MATERIALS AFTER COMPLETION OF CONSTRUCTION.


CATHODIC PROTECTION NOTES	
1 CP	INSTALL TEST STATIONS AT LOCATIONS SHOWN IN THE DESIGN PACKAGE.
2 CP	STEEL PIPE WILL BE PROTECTED WITH THE EXISTING IMPRESSED CURRENT CATHODIC PROTECTIONS SYSTEM UTILIZING RECTIFIER 1003

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs\8-22.dwg LAYOUT NAME: C-234 PLOTTED: Tuesday, November 15, 2023 - 9:46am USER: nwest




REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
5	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS			PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
4	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS			CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
3	90% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/30/22	JMS			SHEET NO. 58 OF 59	SCALE: AS NOTED
N/A				BY: DATE: APPVD:			PATRICK ENGINEERING TEAM	
PERMIT INFORMATION		ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
N/A		N/A	SEC. 31 TOWN 12S, RANG. 65W	P-18	SYSTEM MAOP: 275 psig		APPD. BY: JEREMIAH SMITH	
					SYSTEM MOP: 145 psig			
						HP SERVICE: <input type="checkbox"/>	3747144	
						DISTRIBUTION: <input checked="" type="checkbox"/>	RELATED W/O #s	
						FEEDER: <input type="checkbox"/>	3789816	
						TRANS. BY DEF. <input type="checkbox"/>		
						TRANS v 20% <input type="checkbox"/>		
LOCH FYNE 20" GAS PIPELINE COLORADO SPRINGS, COLORADO PLAN & PROFILE 101+00 - 101+70								DWG. NO. C-234

FILE NAME: P:\indiana\Colorado Springs Utilities\22282.003 - Loch Fyne 20" Gas Line\11 Design\01 Drawings\06 Alignment\06 Colorado Springs_8-22.dwg LAYOUT NAME: HDD-001 PLOTTED: Monday, November 14, 2022 - 5:38pm USER: jsmith



PLAN



NOTES
 PC - POINT OF CURVATURE
 PT - POINT OF TANGENT
 USE 45° 3R ELBOWS AND TRIM THEM TO 5° AND 10° ANGLES FOR THE OVERBENDS

HDD TOLERANCES (UNLESS OTHERWISE APPROVED BY ENGINEER)	
LENGTH - NOT TO BE MORE THAN 10' SHORT OR 20' LONG	
LEFT-RIGHT OF CENTERLINE +/- 5'	
DEPTH NOT TO BE 0' SHALLOWER, OR 10' DEEPER	
RADIUS OF CURVATURE NOT TO BE LESS THAN 1,800' PER 3-JOINT RULE	

COTTONWOOD CREEK HDD

SOIL TYPE	SOIL DESCRIPTION
1	SM-SW SAND, SILTY, FINE TO COURSE GRAINED, TAN, MEDIUM DENSE, DRY TO MOIST
2	SANDSTONE, SM-SC, SLIGHTLY SILTY-CLAYEY, FINE TO COURSE GRAINED, GRAY-BROWN, DENSE TO VERY DENSE, MOIST
3	CLAYSTONE, SC, SANDY TO VERY SANDY, GRAY-BROWN, VERY DENSE, MOIST

PROFILE



REVISIONS				SYSTEM NAME: 150P	JOB TYPE:	W/O #	ENGINEER: SCOTT JENSEN	PHONE: (719) 668-8196
3	ISSUED FOR CONSTRUCTION	NEW	11/14/22	JMS				
2	100% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	10/14/22	JMS				
1	REVISED 60% DESIGN PACKAGE ISSUED FOR REVIEW	NEW	8/8/22	JMS				
NO.	N/A	BY:	DATE:	APPVD:				
PERMIT INFORMATION				ISOLATION AREA	LOCATION	ATLAS OR TITLE	N/A	
N/A				N/A	SEC. 31 TWN. 12S, RNG. 65W	P-18		
				SYSTEM MAOP: 275 psig	HP SERVICE: <input type="checkbox"/>	3747144	PROJECT MANAGER: MELISSA LINGO	PHONE: (719) 668-8794
				SYSTEM MOP: 145 psig	DISTRIBUTION: <input checked="" type="checkbox"/>		CONSTRUCTION LEAD: JOSH RICHARD	PHONE: (719) 668-3675
					FEEDER: <input type="checkbox"/>		SHEET NO. 59 OF 59	SCALE: 1" = 100'
					TRANS. BY DEF. <input type="checkbox"/>		PATRICK ENGINEERING TEAM	
					TRANS v 20% <input type="checkbox"/>		DWN BY: NORM WEST	CHKD. BY: SETH BROWN
						3789816	APPD. BY: JEREMIAH SMITH	
LOCH FYNE 20" GAS PIPELINE								
COLORADO SPRINGS, COLORADO								
HDD PLAN & PROFILE								
								DWG. NO. HDD-001