

PRELIMINARY & FINAL DRAINAGE REPORT
for
WIDEFIELD PK-8 SCHOOL

Widefield, CO

August 2018

Prepared for:

Widefield School District 3
1820 Main St.
Colorado Springs, CO 80911
Contact: Dennis Neal
(719) 391-3530

Prepared by:

Drexel, Barrell & Co.
3 South Seventh Street
Colorado Springs, CO 80905
Contact: Tim McConnell, P.E.
(719) 260-0887

TABLE OF CONTENTS

1.0 CERTIFICATION STATEMENTS III

2.0 PURPOSE 1

3.0 GENERAL SITE DESCRIPTION 1

4.0 PROPOSED HYDROLOGY (RATIONAL METHOD) & HYDRAULIC SUMMARY 2

5.0 PROPOSED DETENTION/WATER QUALITY FACILITIES 6

6.0 FOUR-STEP PROCESS 6

7.0 GEOTECHNICAL HAZARDS 7

8.0 DRAINAGE/BRIDGE FEES 7

9.0 CONCLUSIONS 7

10.0 REFERENCES 8

APPENDICES

- VICINITY MAP
- SOILS MAP
- FLOODPLAIN MAP
- DRAINAGE CALCULATIONS
- DRAINAGE MAP

PRELIMINARY DRAINAGE REPORT
for
WIDEFIELD PK-8 SCHOOL
Widefield, Colorado

1.0 CERTIFICATION STATEMENTS

ENGINEER'S STATEMENT

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by El Paso County for drainage reports, and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omission on my part in preparing this report.

Tim D. McConnell, P.E. Date
Colorado P.E. License No. 33797
For and on Behalf of Drexel, Barrell & Co.

DEVELOPER'S STATEMENT

I, the developer have read and will comply with all the requirements specified in this drainage report and plan.

Business Name: Widefield School District 3

By: _____
Dennis Neal Date
Title: Chief Operations Officer
Address: 1820 Main St.
Colorado Springs, CO 80911

EL PASO COUNTY

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual Volumes 1 and 2, and the Engineering Criteria Manual, as amended.

For the County Engineer Date
CONDITIONS:

2.0 PURPOSE

This report is prepared by Drexel, Barrel & Co in support of the Widefield PK-8 School project at Lorson Ranch. The purpose of this report is to identify onsite and offsite drainage patterns, storm sewer, inlet locations, and areas tributary to the site, and to safely route developed storm water runoff to adequate outfall facilities.

3.0 GENERAL SITE DESCRIPTION

Location

The site is located at the northeast corner of Fontaine Blvd. and Lamprey Road - the SW 1/4 of Section 13, Township 15 S, Range 65 W of the 6th P.M., El Paso County, Colorado.

The site is bound on the west and north by Lamprey Road, the south by Fontaine Blvd. and on the east by an undeveloped lot to be developed as residential in the future. Also to the east of the site is a utility easement/open space.

Site Conditions

The site is approximately 25.1 acres in size and is proposed as school site use. The site is currently undeveloped and is covered with native grass and vegetation. It is gently sloping from east to west.

This proposed school site calls for a two story building with approx. 81,000 sf footprint, a track and field, associated parking, drive aisles, sidewalks, landscaping and utilities. Public access is provided off of Fontaine Blvd. and bus access is off of Lamprey Dr.

Soils

According to the Soil Survey of El Paso County Area, Colorado, prepared by the U.S. Department of Agriculture Soil Conservation Service, the site is underlain by Manzanst clay loam, a type 'C' hydrologic soil and by Razor-Midway complex, a type 'D' hydrologic soil. See appendix for map.

Climate

This area of El Paso County can be described as the foothills, with total precipitation amounts typical of a semi-arid region. Winters are generally cold and dry, and summers relatively warm and dry. Precipitation ranges from 12 to 14 inches per year, with the majority of this moisture occurring in the spring and summer in the form of rainfall. Thunderstorms are common during the summer months.

Floodplain Statement

According to the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) Panel #08041C1000 F (March 17, 1997) the project site is within a designated Zone X area described as "areas determined to be outside 500-year

floodplain". A firmette map is included in the appendix.

4.0 PROPOSED HYDROLOGY (RATIONAL METHOD) & HYDRAULIC SUMMARY

For the purposes of site specific analysis, the project site has been divided into several grouped drainage basins as shown on the proposed drainage plan. Thirty four (34) Design Points have been analyzed for sizing of the drainage facilities.

The Rational Method was used to determine runoff quantities for the 5- and 100-year storm recurrence intervals. Urban Drainage UD-Detention, UD-Inlet and Flowmaster were also used to identify pond and storm system sizing (see appendix for calculations). See below for a summary runoff table.

Rational Method Runoff Summary

| BASIN | AREA (AC) | Q5 (cfs) | Q100 (cfs) |
|-------|-----------|----------|------------|
| A0 | 0.42 | 0.8 | 2.3 |
| A1 | 1.18 | 1.0 | 4.9 |
| A2 | 0.45 | 1.0 | 2.3 |
| A3 | 0.15 | 0.1 | 0.5 |
| A4 | 1.72 | 0.9 | 5.3 |
| A5 | 0.38 | 0.3 | 1.4 |
| A6 | 0.36 | 1.1 | 2.4 |
| A7 | 0.21 | 0.9 | 1.7 |
| A8 | 0.13 | 0.2 | 0.6 |
| A9 | 0.24 | 0.7 | 1.6 |
| A10 | 0.66 | 2.3 | 4.6 |
| A11 | 0.54 | 0.8 | 2.8 |
| A12 | 0.85 | 2.5 | 5.3 |
| A13 | 0.08 | 0.1 | 0.3 |
| A14 | 0.17 | 0.3 | 1.0 |
| A15 | 0.12 | 0.4 | 0.8 |
| A16 | 0.17 | 0.4 | 1.1 |
| A17 | 1.62 | 0.8 | 4.9 |
| A18 | 1.09 | 1.3 | 4.1 |
| A19 | 3.13 | 2.8 | 13.9 |
| A20 | 0.33 | 1.4 | 2.8 |
| A21 | 0.38 | 1.7 | 3.2 |
| A22 | 0.93 | 0.6 | 3.6 |
| B1 | 2.91 | 1.9 | 9.6 |
| B2 | 0.72 | 3.2 | 6.2 |

| DP | AREA (AC) | Q5 (cfs) | Q100 (cfs) |
|-------|-----------|----------|------------|
| DP-0 | 0.42 | 0.8 | 2.3 |
| DP-1 | 1.60 | 1.7 | 7.0 |
| DP-2 | 0.45 | 1.0 | 2.3 |
| DP-3 | 0.15 | 1.8 | 6.5 |
| DP-4 | 1.72 | 0.9 | 5.3 |
| DP-5 | 3.50 | 2.6 | 11.4 |
| DP-6 | 0.36 | 1.1 | 2.4 |
| DP-7 | 4.07 | 4.0 | 14.2 |
| DP-8 | 0.21 | 0.9 | 1.7 |
| DP-9 | 4.41 | 4.7 | 15.7 |
| DP-10 | 0.24 | 0.7 | 1.6 |
| DP-11 | 5.31 | 6.8 | 19.9 |
| DP-12 | 0.54 | 0.8 | 2.8 |
| DP-13 | 1.39 | 3.2 | 7.8 |
| DP-14 | 1.47 | 2.9 | 7.4 |
| DP-15 | 1.64 | 3.2 | 8.1 |
| DP-16 | 0.12 | 0.4 | 0.8 |
| DP-17 | 1.76 | 3.5 | 8.7 |
| DP-18 | 1.93 | 3.8 | 9.4 |
| DP-19 | 1.62 | 0.8 | 4.9 |
| DP-20 | 8.86 | 10.6 | 32.2 |
| DP-21 | 9.95 | 11.7 | 35.6 |
| DP-22 | 3.13 | 2.8 | 13.9 |
| DP-23 | 3.46 | 4.1 | 16.4 |
| DP-24 | 3.84 | 5.6 | 19.4 |

| | | | |
|----|------|-----|-----|
| B3 | 0.69 | 3.1 | 5.9 |
| B4 | 0.77 | 1.6 | 4.3 |
| B5 | 1.56 | 0.8 | 4.7 |
| C1 | 1.31 | 0.9 | 5.4 |
| C2 | 2.09 | 1.5 | 8.0 |
| C3 | 0.84 | 0.6 | 3.3 |

| | | | |
|-------|-------|------|------|
| DP-25 | 14.72 | 16.0 | 51.4 |
| DP-26 | 2.91 | 1.9 | 9.6 |
| DP-27 | 0.72 | 3.2 | 6.2 |
| DP-28 | 1.41 | 6.1 | 11.7 |
| DP-29 | 2.18 | 7.2 | 15.0 |
| DP-30 | 1.56 | 0.8 | 4.7 |
| DP-31 | 16.28 | 1.1 | 29.8 |
| DP-32 | 1.31 | 0.9 | 5.4 |
| DP-33 | 2.09 | 1.5 | 8.0 |
| DP-34 | 0.84 | 0.6 | 3.3 |

A-group basins represent flows that are captured by the pond proposed Full Spectrum EDB and outfall via a 24" pipe.

DP-0 is located at the proposed area inlet in Basin A0. The flows leave this inlet via a 15" storm pipe. This design point captures all of the flows from Basin A0.

DP-1 is located at the proposed area inlet in Basin A1. The flows leave this inlet via a 15" storm pipe. This design point captures all of the flows from Basin A0 and A1.

DP-2 is located at the proposed area inlet in Basin A2. The flows leave this inlet via a 12" storm pipe. This design point captures all of the flows from Basin A2.

DP-3 is located at the proposed area inlet in Basin A3. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basins A0, A1, A2 and A3.

DP-4 is located at the proposed area inlet in Basin A4. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basin A4.

DP-5 is located at the proposed 18"x18" wye in Basin A5. The flows leave this wye via an 18" storm pipe. This design point reflects all of the flows from Basins A0, A1, A2, A3, A4 and A5.

DP-6 is located at the proposed area inlet in Basin A6. The flows leave this inlet via a 12" storm pipe. This design point reflects all of the flows from Basin A6.

DP-7 is located at the proposed area inlet in Basin A7. The flows leave this inlet via a 24" storm pipe. This design point reflects all of the flows from Basins A0, A1, A2, A3, A4, A5 and A6.

DP-8 is located at the proposed at-grade Type 16 inlet in Basin A7. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basin A7.

DP-9 is located at the proposed area inlet in Basin A8. The flows leave this inlet via a 24" storm pipe. This design point reflects all of the flows from Basins A0, A1, A2, A3, A4, A5, A6, A7 and A8.

DP-10 is located at the proposed at-grade Type 16 inlet in Basin A9. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basin A9.

DP-11 is located at the proposed sump Type R inlet in Basin A10. The flows leave this manhole via a 24" storm pipe. This design point reflects all of the flows from Basins A0, A1, A2, A3, A4, A5, A6, A7, A8, A9 and A10.

DP-12 is located at the proposed area inlet in Basin A11. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basin A11.

DP-13 is located at the proposed area inlet in Basin A12. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basins A11 and A12.

DP-14 is located at the proposed area inlet in Basin A13. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basins A11, A12 and A13.

DP-15 is located where the underground drain connects to the storm pipe in Basin A14. The flows leave via an 18" storm pipe. This design point reflects all of the flows from Basins A11, A12, A13 and A14.

DP-16 is located at the proposed roof drains in Basin A15. The flows from the roof drains connect to the 18" storm pipe. This design point reflects all of the flows from Basin A15.

DP-17 is located at the pipe junction where the roof drains from DP-16 connects to the 18" storm pipe. The flows leave this junction via an 18" storm pipe. This design point reflects all of the flows from Basins A11, A12, A13, A14 and A15.

DP-18 is located where the underground drain connects to the storm pipe in Basin A16. The flows leave via an 18" storm pipe. This design point reflects all of the flows from Basins A11, A12, A13, A14, A15 and A16.


DP-19 is located where the perimeter drain around the east side of the track outfalls to connect to the storm system in Basin A17. The flows leave via a 12" storm pipe. This design point reflects all of the flows from Basin A17.

DP-20 is located at the proposed manhole in Basin A18. The flows leave this manhole via a 30" storm pipe. This design point reflects all of the flows from Basins A0 through A17.

DP-21 is located at the proposed area inlet in Basin A18. The flows leave this inlet via a 30" storm pipe that discharges into the pond. This design point reflects all of the flows from Basins A0 through A18.

DP-22 is located at the proposed flared end section in Basin A19. The flows leave via an 18" storm pipe. This design point reflects all of the flows from Basin A19.

DP-23 is located at the proposed at-grade Type 16 inlet in Basin A20. The flows leave this inlet via a 24" storm pipe. This design point reflects all of the flows from Basins A19 and A20.



**Are these
combination
inlets? Provide
a detail.**

DP-24 is located at the proposed at-grade Type 16 inlet in Basin A21. The flows leave this inlet via a 24" storm pipe that discharges into the pond. This design point reflects all of the flows from Basins A19, A20 and A21.

Pond backflow is accommodated for in the two inlets at DP-23 and DP-24. The flowline elevations for these 2 inlets is higher than the 100-yr elevation of the pond.

DP-25 is located at the bottom of the proposed Full Spectrum EDB pond in Basin A22. The flows leave the pond via an outlet structure and a 24" storm pipe. This design point reflects all of the flows from all "A" basins.

B-group basins represent flows that are captured by the proposed on-site storm system, but not directed to the pond.

DP-26 is located at the proposed at-grade double Type R inlet in Basin B1. The flows leave this inlet via a 24" storm pipe that connects to the existing storm system in Fontaine Blvd., which carries the flows to the west. This design point reflects all of the flows from Basin B1.

DP-27 is located at the proposed at-grade Type R inlet in Basin B2. The flows leave this inlet via an 18" storm pipe. This design point reflects all of the flows from Basin B2.

DP-28 is located at the proposed sump Type R inlet in Basin B3. The flows leave this inlet via a 24" storm pipe. This design point reflects all of the flows from Basins B2 and B3.

DP-29 is located at the proposed at-grade Type R inlet in Basin B4. The flows leave this inlet via a 24" storm pipe that connects to the existing storm system in Fontaine Blvd., which carries the flows to the west. This design point reflects all of the flows from Basins B2, B3 and B4.

DP-30 is located where the perimeter drain around the west side of the track outfalls to connect to the storm system in Basin B5. The flows leave via a 12" storm pipe. This design point reflects all of the flows from Basin B5.

C-group basins represent flows that leave the project site and are captured by existing curb and gutter in either Fontaine Blvd. or Lamprey Dr. and then carried to inlets in the existing storm system.

DP-31 is located at the proposed manhole in Basin C1. The manhole connects to the existing storm sewer system that will carry the flows to the west to a pond that has accounted for these flows. This design point reflects all of the flows from all "A" Basins and from Basin B5.

DP-32 is located at the existing inlet in Lamprey Dr. adjacent to Basin C1. The inlet was designed to handle the flows from the existing project it is a part of as well as from our Basin C1. DP-32 reflects all of the flows leaving the project site from Basin C1.

DP-33 is located at the existing inlet in Lamprey Dr. adjacent to Basin C2. The inlet was designed to handle the flows from the existing project it is a part of as well as from our

Basin C2. DP-33 reflects all of the flows leaving the project site from Basin C2.

DP-34 is located at the existing inlet in Fontaine Blvd. adjacent to Basin C3. The inlet was designed to handle the flows from the existing project it is a part of as well as from our Basin C3. DP-34 reflects all of the flows leaving the project site from Basin C3.

5.0 PROPOSED DETENTION/WATER QUALITY FACILITIES

The proposed on-site pond is a 2.6 ac-ft extended detention basin (EDB) located at the northwest end of the project site. Although it does not capture flows from the entire site, it has been oversized by using impervious coverage and the area of the entire site. The required pond volume when using the entire site area for 100-yr detention is 1.594 acre-feet. The actual pond volume is 2.592 acre-feet. It will capture then release the flows at a reduced flow rate into a proposed 24" pipe, which connects to the existing storm sewer system and continues to the west. In accordance with El Paso County criteria, a modified Type C outlet structure with a permanent micropool will release the WQCV over a 40-hour period. A spillway has been placed on the north side of the pond. In the event that water overtops the spillway, it will flow to the curb in Lamprey Dr. then continue to the southwest to the existing storm sewer system where it is then carried to an existing downstream pond in Lorson Ranch. According to the "Final Drainage Plan for Lorson Ranch East Filing No. 1," by Core Engineering Group, this pond was designed to accommodate the flows from the school site for water quality. See report for full drainage analysis.

Calculations are provided in the appendix for the on-site pond, forebay volumes, micropool surface area, outlet structure, discharge pipe and spillway.

Private maintenance agreements and O&M manuals will be established for this pond as required by the County.

6.0 FOUR-STEP PROCESS

This project conforms to the City of Colorado Springs/El Paso County Four Step Process. The process focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainage ways, and implementing long-term source controls.

1. ***Employ Runoff Reduction Practices:*** Proposed impervious areas on this site (roofs, asphalt/sidewalk) will sheet flow across landscaped ground as much as possible to slow runoff and increase time of concentration prior to being conveyed to the proposed public streets and storm sewer system. This will minimize directly connected impervious areas within the project site.
2. ***Implement BMP's that provide a Water Quality Capture Volume with slow release:*** Runoff from this project will be treated through capture and slow release of the WQCV in a permanent Extended Detention Basin facility designed per current City of Colorado Springs/El Paso County drainage criteria.

3. **Stabilize Drainage Ways:** Flows from this project are not directly released into any drainage ways. They are released into the existing storm sewer system at a rate less than the historical rate, so there will be no adverse effects on the existing drainage ways.
4. **Implement Site Specific and Other Source Control BMP's:** A site specific storm water quality and erosion control plan and narrative will be submitted and approved by El Paso County Engineering prior to any disturbance within the project area. Details such as site specific source control construction BMP's as well as permanent BMP's will be detailed in this plan and narrative to protect receiving waters.

7.0 GEOTECHNICAL HAZARDS

In accordance with geotechnical recommendations, the project design is intended to direct runoff away from structures, and into the receiving storm sewer system and water quality/detention basins. This will be accomplished by a variety of means, i.e. curb and gutter and storm sewer.

8.0 DRAINAGE/BRIDGE FEES

The project lies within the Jimmy Camp Creek Drainage Basin.

The percent imperviousness for this subdivision is calculated as follows:

Project site imperviousness = 34.0%

25.27 Acres at 34.0% Impervious = 8.6 Impervious Acres

The following calculations are based on the 2018 drainage/bridge fees for the Jimmy Camp Creek Drainage Basin:

Drainage Fee

\$17,197 x 8.6 Impervious Ac = \$147,894.20

Bridge Fee

\$804 x 8.6 Impervious Ac. = \$6,914.40

Surety

\$7,285 x 8.6 Impervious Ac. = \$62,651.00

Fees will be paid by the Widefield School District #3.


9.0 CONCLUSIONS

The new Widefield PK-8 school project has been designed in accordance with El Paso County criteria. The EDB/water quality pond has been designed to limit the release of storm runoff. This development will not negatively impact the downstream facilities.

10.0 REFERENCES


The sources of information used in the development of this study are listed below:

1. City of Colorado Springs "Drainage Criteria Manual", 2016.
2. Urban Storm Drainage Criteria Manuals, Urban Drainage and Flood Control District. June 2001, Revised April 2008.
3. Soil Survey for Colorado Springs and El Paso County, Colorado, U.S. Department of Agriculture, Soil Conservation Service, June 1980.
4. "Flood Insurance Studies for Colorado Springs and El Paso County, Colorado", prepared by the Federal Emergency Management Agency (FEMA), 1997.
5. Geotechnical Engineering Report. Prepared by Terracon Consultants, Inc, February 7, 2018.
6. "Final Drainage Plan Lorson Ranch East Filing No. 1," prepared by Core Engineering Group, LLC, March 1, 2018.



July 2, 2018

APPENDIX



Vicinity Map
Not to scale



NEW WIDFIELD PK-8 SCHOOL
WIDFIELD, CO
VICINITY MAP

Drexel, Barrell & Co.
Engineers • Surveyors

DATE:

DWG. NO.



JOB NO:

21126-00CSCV

VMAP

SHEET 1 OF 1


Hydrologic Soil Group—El Paso County Area, Colorado
(New Widefield PK-8 school)



Hydrologic Soil Group—El Paso County Area, Colorado
(New Widefield PK-8 school)

MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Lines

-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Points






-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available


Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
Survey Area Data: Version 15, Oct 10, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Nov 7, 2015—Mar 9, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

| Map unit symbol | Map unit name | Rating | Acres in AOI | Percent of AOI |
|------------------------------------|---|--------|--------------|----------------|
| 52 | Manzanst clay loam, 0 to 3 percent slopes | C | 11.4 | 23.8% |
| 75 | Razor-Midway complex | D | 36.4 | 76.2% |
| Totals for Area of Interest | | | 47.8 | 100.0% |

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

104°37'30"
38°45'00"

JOINS PANEL 0790



APPROXIMATE SCALE IN FEET
 2000 0 2000

NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

EL PASO COUNTY,
 COLORADO AND
 INCORPORATED AREAS

PANEL 1000 OF 1300
 (SEE MAP INDEX FOR PANELS NOT PRINTED)

| CONTAINS: COMMUNITY | NUMBER | PANEL | SUFFIX |
|---|--------|-------|--------|
| COLORADO SPRINGS, CITY OF | 080060 | 1000 | F |
| EL PASO COUNTY, UNINCORPORATED AREAS | 080059 | 1000 | F |

MAP NUMBER
08041C1000 F

EFFECTIVE DATE:
MARCH 17, 1997



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

| PROJECT INFORMATION | | | | | | | | |
|---|--------------------------|------|-------------------------------|------|------|------|----------|----------|
| PROJECT: | Widefield PK-8 School | | | | | | | |
| PROJECT NO: | 21126-00 | | | | | | | |
| DESIGN BY: | SBN | | | | | | | |
| REV. BY: | TDM | | | | | | | |
| AGENCY: | City of Colorado Springs | | | | | | | |
| REPORT TYPE: | Final | | | | | | | |
| DATE: | 5/10/2018 | | | | | | | |
| Soil Type: C | | | | | | | | |
| | | | | C2* | C5* | C10* | C100* | % IMPERV |
| Landscape/Lawn | | | | | 0.15 | | 0.50 | 0 |
| Roof | | | | | 0.75 | | 0.83 | 90 |
| Asphalt/Sidewalk | | | | | 0.90 | | 0.96 | 100 |
| *C-Values and Basin Imperviousness based on Table 5-1, City of Colorado Springs and El Paso County "Drainage Criteria Manual" | | | | | | | | |
| PROPOSED | | | | | | | | |
| SUB-BASIN | SURFACE DESIGNATION | AREA | COMPOSITE RUNOFF COEFFICIENTS | | | | % IMPERV | |
| | | ACRE | C2 | C5 | C10 | C100 | | |
| A1 | Landscape/Lawn | 1.33 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.07 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.25 | | 0.52 | 5% | |
| TOTAL A1 | | 1.40 | | | | | | |
| A2 | Landscape/Lawn | 0.12 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.33 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.27 | | 0.74 | 66% | |
| TOTAL A2 | | 0.45 | | | | | | |
| A3 | Landscape/Lawn | 0.15 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.15 | | 0.50 | 0% | |
| TOTAL A3 | | 0.15 | | | | | | |
| A4 | Landscape/Lawn | 1.70 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.02 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.16 | | 0.51 | 1% | |
| TOTAL A4 | | 1.72 | | | | | | |
| A5 | Landscape/Lawn | 0.35 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.03 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.21 | | 0.54 | 8% | |
| TOTAL A5 | | 0.38 | | | | | | |
| A6 | Landscape/Lawn | 0.07 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.29 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.63 | | 0.77 | 73% | |
| TOTAL A6 | | 0.36 | | | | | | |
| A7 | Landscape/Lawn | 0.00 | | 0.15 | | 0.50 | 0 | |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 | |
| | Asphalt/Sidewalk | 0.21 | | 0.90 | | 0.96 | 100 | |
| | WEIGHTED AVERAGE | | | 0.90 | | 0.96 | 100% | |
| TOTAL A7 | | 0.21 | | | | | | |

| | | | | | | | |
|------------------|------------------|------|--|------|--|------|-----|
| A8 | Landscape/Lawn | 0.10 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.03 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.32 | | 0.61 | 23% |
| TOTAL A8 | | 0.13 | | | | | |
| A9 | Landscape/Lawn | 0.07 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.17 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.68 | | 0.83 | 71% |
| TOTAL A9 | | 0.24 | | | | | |
| A10 | Landscape/Lawn | 0.07 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.45 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.14 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.72 | | 0.82 | 83% |
| TOTAL A10 | | 0.66 | | | | | |
| A11 | Landscape/Lawn | 0.47 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.29 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.38 | | 0.63 | 34% |
| TOTAL A11 | | 0.76 | | | | | |
| A12 | Landscape/Lawn | 0.17 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.60 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.06 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.64 | | 0.77 | 72% |
| TOTAL A12 | | 0.83 | | | | | |
| A13 | Landscape/Lawn | 0.07 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.01 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.24 | | 0.56 | 13% |
| TOTAL A13 | | 0.08 | | | | | |
| A14 | Landscape/Lawn | 0.11 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.06 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.41 | | 0.66 | 35% |
| TOTAL A14 | | 0.17 | | | | | |
| A15 | Landscape/Lawn | 0.05 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.12 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.09 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.69 | | 0.81 | 76% |
| TOTAL A15 | | 0.26 | | | | | |
| A16 | Landscape/Lawn | 0.10 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.07 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.46 | | 0.69 | 41% |
| TOTAL A16 | | 0.17 | | | | | |
| A17 | Landscape/Lawn | 1.62 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.15 | | 0.50 | 0% |
| TOTAL A17 | | 1.62 | | | | | |
| A18 | Landscape/Lawn | 0.81 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.28 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.34 | | 0.62 | 26% |
| TOTAL A18 | | 1.09 | | | | | |

| | | | | | | | |
|-------------------|------------------|-------|--|------|--|------|-------|
| A19 | Landscape/Lawn | 2.97 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.16 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.19 | | 0.52 | 5% |
| TOTAL A19 | | 3.13 | | | | | |
| A20 | Landscape/Lawn | 0.00 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.26 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.90 | | 0.96 | 100% |
| TOTAL A20 | | 0.26 | | | | | |
| A21 | Landscape/Lawn | 0.00 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.31 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.90 | | 0.96 | 100% |
| TOTAL A21 | | 0.31 | | | | | |
| A22 | Landscape/Lawn | 0.93 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.15 | | 0.50 | 0% |
| TOTAL A22 | | 0.93 | | | | | |
| B1 | Landscape/Lawn | 2.78 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.13 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.18 | | 0.52 | 4% |
| TOTAL B1 | | 2.91 | | | | | |
| B2 | Landscape/Lawn | 0.03 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.69 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.87 | | 0.94 | 96% |
| TOTAL B2 | | 0.72 | | | | | |
| B3 | Landscape/Lawn | 0.03 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.66 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.87 | | 0.94 | 96% |
| TOTAL B3 | | 0.69 | | | | | |
| B4 | Landscape/Lawn | 0.46 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.31 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.45 | | 0.69 | 40% |
| TOTAL B4 | | 0.77 | | | | | |
| B5 | Landscape/Lawn | 1.56 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.15 | | 0.50 | 0% |
| TOTAL B5 | | 1.56 | | | | | |
| C1 | Landscape/Lawn | 1.31 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.15 | | 0.50 | 0% |
| TOTAL C1 | | 1.31 | | | | | |
| C2 | Landscape/Lawn | 2.05 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.04 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.16 | | 0.51 | 2% |
| TOTAL C2 | | 2.09 | | | | | |
| C3 | Landscape/Lawn | 0.84 | | 0.15 | | 0.50 | 0 |
| | Roof | 0.00 | | 0.75 | | 0.83 | 90 |
| | Asphalt/Sidewalk | 0.00 | | 0.90 | | 0.96 | 100 |
| | WEIGHTED AVERAGE | | | 0.15 | | 0.50 | 0% |
| TOTAL C3 | | 0.84 | | | | | |
| TOTAL SITE | | 26.20 | | 0.30 | | 0.59 | 21.6% |

PROJECT INFORMATION

PROJECT: Widefield PK-8 School
 PROJECT NO: 21126-00
 DESIGN BY: SBN
 REV. BY: TDM
 AGENCY: City of Colorado Springs
 REPORT TYPE: Final
 DATE: 5/10/2018



RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

PROPOSED TIME OF CONCENTRATION STANDARD FORM SF-2

| SUB-BASIN DATA | | | | | INITIAL/OVERLAND TIME (t _i) | | | | TRAVEL TIME (t _t) | | | | | PIPE TRAVEL TIME (t _p) | | | | TIME OF CONC. t _c | | FINAL t _c |
|----------------|------------|----------------|------------------|------|---|------|-------|----------------|-------------------------------|-----|-------|------|----------------|------------------------------------|-------|------|----------------|------------------------------|------------------------|----------------------|
| BASIN | DESIGN PT. | C ₅ | C ₁₀₀ | AREA | LENGTH | HT | SLOPE | t _i | LENGTH | HT | SLOPE | VEL. | t _t | LENGTH | SLOPE | VEL. | t _t | COMP. t _c | MINIMUM t _c | Min |
| | | | | Ac | Ft | FT | % | Min | Ft | FT | % | FPS | Min | Ft | % | FPS | Min | t _c | t _c | Min |
| A1 | DP-1 | 0.25 | 0.52 | 1.40 | 75 | 12.3 | 16.4 | 5.4 | 425 | 6 | 1.4 | 3.7 | 1.9 | | | | | 7.3 | 5 | 7.3 |
| A2 | DP-2 | 0.27 | 0.74 | 0.45 | 80 | 1.6 | 2.0 | 11.1 | 30 | 0.6 | 2.0 | 4.8 | 0.1 | | | | | 11.2 | 5 | 11.2 |
| A3 | | 0.15 | 0.50 | 0.15 | 75 | 1 | 1.3 | 14.0 | 10 | 0.1 | 1.0 | 3.1 | 0.1 | | | | | 14.0 | 5 | 14.0 |
| | DP-3 | 0.25 | 0.57 | 2.00 | | | | | | | | | | | | | | 14.0 | 5 | 14.0 |
| A4 | DP-4 | 0.16 | 0.51 | 1.72 | 100 | 2 | 2.0 | 14.0 | 340 | 6.5 | 1.9 | 4.4 | 1.3 | | | | | 15.3 | 5 | 15.3 |
| | DP-5 | 0.21 | 0.54 | 3.72 | | | | | | | | | | 100 | 1.0 | 4.8 | 0.3 | 15.6 | 5 | 15.6 |
| A5 | | 0.21 | 0.54 | 0.38 | 80 | 1.6 | 2.0 | 11.8 | 10 | 0.2 | 2.0 | 4.4 | 0.0 | | | | | 11.9 | 5 | 11.9 |
| A6 | DP-6 | 0.63 | 0.77 | 0.36 | 70 | 1.4 | 2.0 | 5.8 | 55 | 1.1 | 2.0 | 4.8 | 0.2 | | | | | 6.0 | 5 | 6.0 |
| | DP-7 | 0.28 | 0.58 | 4.29 | | | | | | | | | | 50 | 1.5 | 7.2 | 0.1 | 15.7 | 5 | 15.7 |
| A7 | DP-8 | 0.90 | 0.96 | 0.21 | 100 | 2.8 | 2.8 | 2.7 | 70 | 1.1 | 1.6 | 7.4 | 0.2 | | | | | 2.8 | 5 | 5.0 |
| A8 | | 0.32 | 0.61 | 0.13 | 55 | 1.2 | 2.2 | 8.3 | 10 | 0.2 | 2.0 | 4.4 | 0.0 | | | | | 8.3 | 5 | 8.3 |
| | DP-9 | 0.31 | 0.60 | 4.63 | | | | | | | | | | 125 | 0.8 | 5.2 | 0.4 | 16.1 | 5 | 16.1 |
| A9 | DP-10 | 0.68 | 0.83 | 0.24 | 100 | 1.2 | 1.2 | 7.4 | 180 | 4.3 | 2.4 | 9.1 | 0.3 | | | | | 7.7 | 5 | 7.7 |
| A10 | | 0.72 | 0.82 | 0.66 | 100 | 2 | 2.0 | 5.7 | 230 | 5 | 2.2 | 5.0 | 0.8 | | | | | 6.4 | 5 | 6.4 |
| | DP-11 | 0.37 | 0.63 | 5.53 | | | | | | | | | | 170 | 2.1 | 8.5 | 0.3 | 16.5 | 5 | 16.5 |
| A11 | DP-12 | 0.38 | 0.63 | 0.76 | 50 | 12 | 24.0 | 3.3 | 180 | 3.6 | 2.0 | 4.4 | 0.7 | | | | | 4.0 | 5 | 5.0 |
| A12 | | 0.64 | 0.77 | 0.83 | 100 | 2 | 2.0 | 6.9 | 185 | 3.7 | 2.0 | 4.8 | 0.6 | | | | | 7.5 | 5 | 7.5 |
| | DP-13 | 0.51 | 0.70 | 1.59 | | | | | | | | | | | | | | 7.5 | 5 | 7.5 |
| A13 | | 0.24 | 0.56 | 0.08 | 50 | 0.7 | 1.4 | 10.1 | 10 | 0.1 | 1.0 | 3.1 | 0.1 | | | | | 10.2 | 5 | 10.2 |
| | DP-14 | 0.50 | 0.70 | 1.67 | | | | | | | | | | | | | | 10.2 | 5 | 10.2 |
| A14 | | 0.41 | 0.66 | 0.17 | 25 | 0.3 | 1.2 | 6.0 | 70 | 0.7 | 1.0 | 3.4 | 0.3 | | | | | 6.4 | 5 | 6.4 |
| | DP-15 | 0.49 | 0.69 | 1.84 | | | | | | | | | | 75 | 1.0 | 4.8 | 0.3 | 10.4 | 5 | 10.4 |
| A15 | DP-16 | 0.69 | 0.81 | 0.26 | 60 | 0.3 | 0.5 | 7.5 | 10 | 0.1 | 1.0 | 5.9 | 0.0 | | | | | 7.6 | 5 | 7.6 |
| | DP-17 | 0.52 | 0.71 | 2.10 | | | | | | | | | | 70 | 0.9 | 4.6 | 0.3 | 10.7 | 5 | 10.7 |
| A16 | | 0.46 | 0.69 | 0.17 | 15 | 0.2 | 1.3 | 4.2 | 70 | 0.7 | 1.0 | 3.4 | 0.3 | | | | | 4.6 | 5 | 5.0 |
| | DP-18 | 0.51 | 0.71 | 2.27 | | | | | | | | | | 115 | 0.5 | 4.1 | 0.5 | 11.2 | 5 | 11.2 |

| | | | | | | | | | | | | | | | | | | | | |
|-----|-------|------|------|-------|-----|------|------|------|------|------|-----|------|-----|-----|------|------|-----|------|---|------|
| A17 | DP-19 | 0.15 | 0.50 | 1.62 | 95 | 2.2 | 2.3 | 13.1 | 355 | 1.9 | 0.5 | 2.4 | 2.5 | | | | | 15.6 | 5 | 15.6 |
| | DP-20 | 0.37 | 0.63 | 9.42 | | | | | | | | | | 165 | 1.0 | 6.8 | 0.4 | 16.9 | 5 | 16.9 |
| A18 | | 0.34 | 0.62 | 1.09 | 100 | 1 | 1.0 | 14.2 | 205 | 3 | 1.5 | 3.8 | 0.9 | | | | | 15.1 | 5 | 15.1 |
| | DP-21 | 0.36 | 0.63 | 10.51 | | | | | | | | | | 215 | 1.8 | 9.1 | 0.4 | 17.3 | 5 | 17.3 |
| A19 | DP-22 | 0.19 | 0.52 | 3.13 | 50 | 12 | 24.0 | 4.2 | 570 | 11.2 | 2.0 | 4.4 | 2.2 | | | | | 6.3 | 5 | 6.3 |
| A20 | | 0.90 | 0.96 | 0.26 | 45 | 0.9 | 2.0 | 2.0 | 260 | 9.5 | 3.7 | 11.3 | 0.4 | | | | | 2.4 | 5 | 5.0 |
| | DP-23 | 0.24 | 0.56 | 3.39 | | | | | | | | | | 40 | 1.3 | 5.5 | 0.1 | 6.5 | 5 | 6.5 |
| A21 | | 0.90 | 0.96 | 0.31 | 55 | 1.1 | 2.0 | 2.2 | 275 | 9.2 | 3.3 | 10.6 | 0.4 | | | | | 2.6 | 5 | 5.0 |
| | DP-24 | 0.30 | 0.59 | 3.70 | | | | | | | | | | 35 | 1.9 | 8.1 | 0.1 | 6.5 | 5 | 6.5 |
| A22 | | 0.15 | 0.50 | 0.93 | 100 | 10.5 | 10.5 | 8.1 | 195 | 2 | 1.0 | 5.9 | 0.6 | | | | | 8.7 | 5 | 8.7 |
| | DP-25 | 0.34 | 0.61 | 15.14 | | | | | | | | | | 130 | 13.4 | 24.9 | 0.1 | 17.3 | 5 | 17.3 |
| B1 | DP-26 | 0.18 | 0.52 | 2.91 | 100 | 8.8 | 8.8 | 8.3 | 385 | 13 | 3.4 | 5.7 | 1.1 | | | | | 9.4 | 5 | 9.4 |
| B2 | DP-27 | 0.87 | 0.94 | 0.72 | 10 | 0.1 | 1.0 | 1.4 | 365 | 6.5 | 1.8 | 7.8 | 0.8 | | | | | 2.1 | 5 | 5.0 |
| B3 | | 0.87 | 0.94 | 0.69 | 100 | 2.9 | 2.9 | 3.1 | 260 | 5.4 | 2.1 | 8.5 | 0.5 | | | | | 3.6 | 5 | 5.0 |
| | DP-28 | 0.87 | 0.94 | 1.41 | | | | | | | | | | 230 | 1.5 | 5.9 | 0.6 | 5.6 | 5 | 5.6 |
| B4 | | 0.45 | 0.69 | 0.77 | 95 | 4.4 | 4.6 | 7.1 | 225 | 7.5 | 3.3 | 10.6 | 0.4 | | | | | 7.4 | 5 | 7.4 |
| | DP-29 | 0.72 | 0.85 | 2.18 | | | | | | | | | | | | | | 7.4 | 5 | 7.4 |
| B5 | DP-30 | 0.15 | 0.50 | 1.56 | 95 | 2.2 | 2.3 | 13.1 | 340 | 1.6 | 0.5 | 2.4 | 2.4 | | | | | 15.5 | 5 | 15.5 |
| | DP-31 | 0.32 | 0.60 | 16.70 | | | | | | | | | | 345 | 1.0 | 6.8 | 0.8 | 18.2 | 5 | 18.2 |
| C1 | DP-32 | 0.15 | 0.50 | 1.31 | 45 | 4 | 8.9 | 5.8 | 575 | 8 | 1.4 | 6.9 | 1.4 | | | | | 7.1 | 5 | 7.1 |
| C2 | DP-33 | 0.16 | 0.51 | 2.09 | 100 | 7 | 7.0 | 9.1 | 1120 | 18 | 1.6 | 7.4 | 2.5 | | | | | 11.7 | 5 | 11.7 |
| C3 | DP-34 | 0.15 | 0.50 | 0.84 | 100 | 2 | 2.0 | 14.1 | 320 | 19.8 | 6.2 | 7.7 | 0.7 | 170 | 1.2 | 6.4 | 0.4 | 15.2 | 5 | 15.2 |

PROJECT INFORMATION

PROJECT: Widefield PK-8 School
 PROJECT NO: 21126-00
 DESIGN BY: SBN
 REV. BY: TDM
 AGENCY: City of Colorado Springs
 REPORT TYPE: Final
 DATE: 5/10/2018



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

PROPOSED

RUNOFF 5 YR STORM

P1= 1.50

| BASIN (S) | DESIGN POINT | AREA (AC) | DIRECT RUNOFF | | | | PIPE SIZING | | | | |
|-----------|--------------|-----------|---------------|----------------------|-------|-----------|-------------|---|---------------|---------------------|-----------|
| | | | RUNOFF COEFF | t _c (MIN) | C * A | I (IN/HR) | Q (CFS) | n | Slope (ft/ft) | Calculated Pipe Dia | Used Pipe |
| A1 | DP-1 | 1.40 | 0.25 | 7.7 | 0.35 | 4.50 | 1.6 | | | | |
| A2 | DP-2 | 0.45 | 0.27 | 11.2 | 0.12 | 3.93 | 0.5 | | | | |
| A3 | | 0.15 | 0.15 | 14.0 | 0.02 | 3.57 | 0.1 | | | | |
| | DP-3 | 2.00 | 0.25 | 14.0 | 0.49 | 3.57 | 1.8 | | | | |
| A4 | DP-4 | 1.72 | 0.16 | 15.3 | 0.27 | 3.43 | 0.9 | | | | |
| | DP-5 | 3.72 | 0.21 | 15.6 | 0.77 | 3.40 | 2.6 | | | | |
| A5 | | 0.38 | 0.21 | 11.2 | 0.08 | 3.92 | 0.3 | | | | |
| A6 | DP-6 | 0.36 | 0.63 | 6.0 | 0.23 | 4.86 | 1.1 | | | | |
| | DP-7 | 4.29 | 0.28 | 15.9 | 1.18 | 3.37 | 4.0 | | | | |
| A7 | DP-8 | 0.21 | 0.90 | 7.1 | 0.19 | 4.61 | 0.9 | | | | |
| A8 | | 0.13 | 0.32 | 8.3 | 0.04 | 4.38 | 0.2 | | | | |
| | DP-9 | 4.63 | 0.31 | 16.3 | 1.42 | 3.33 | 4.7 | | | | |
| A9 | DP-10 | 0.24 | 0.68 | 7.7 | 0.16 | 4.50 | 0.7 | | | | |
| A10 | | 0.66 | 0.72 | 6.4 | 0.47 | 4.76 | 2.3 | | | | |
| | DP-11 | 5.53 | 0.37 | 16.6 | 2.05 | 3.30 | 6.8 | | | | |
| A11 | DP-12 | 0.76 | 0.38 | 5.0 | 0.29 | 5.10 | 1.5 | | | | |
| A12 | | 0.83 | 0.64 | 7.5 | 0.53 | 4.54 | 2.4 | | | | |
| | DP-13 | 1.59 | 0.51 | 7.5 | 0.82 | 4.54 | 3.7 | | | | |
| A13 | | 0.08 | 0.24 | 10.2 | 0.02 | 4.08 | 0.1 | | | | |
| | DP-14 | 1.67 | 0.50 | 10.2 | 0.84 | 4.08 | 3.4 | | | | |
| A14 | | 0.17 | 0.41 | 6.4 | 0.07 | 4.78 | 0.3 | | | | |
| | DP-15 | 1.84 | 0.49 | 10.4 | 0.91 | 4.04 | 3.7 | | | | |
| A15 | DP-16 | 0.26 | 0.69 | 7.6 | 0.18 | 4.53 | 0.8 | | | | |
| | DP-17 | 2.10 | 0.52 | 10.7 | 1.09 | 4.00 | 4.3 | | | | |
| A16 | | 0.17 | 0.46 | 5.0 | 0.08 | 5.10 | 0.4 | | | | |
| | DP-18 | 2.27 | 0.51 | 11.2 | 1.16 | 3.93 | 4.6 | | | | |
| A17 | DP-19 | 1.62 | 0.15 | 15.6 | 0.24 | 3.40 | 0.8 | | | | |
| | DP-20 | 9.42 | 0.37 | 17.0 | 3.46 | 3.27 | 11.3 | | | | |
| A18 | | 1.09 | 0.34 | 15.8 | 0.37 | 3.38 | 1.3 | | | | |
| | DP-21 | 10.51 | 0.36 | 17.5 | 3.83 | 3.22 | 12.3 | | | | |
| A19 | DP-22 | 3.13 | 0.19 | 6.3 | 0.59 | 4.78 | 2.8 | | | | |
| A20 | | 0.26 | 0.90 | 5.0 | 0.23 | 5.10 | 1.2 | | | | |
| | DP-23 | 3.39 | 0.24 | 6.5 | 0.82 | 4.76 | 3.9 | | | | |
| A21 | | 0.31 | 0.90 | 5.0 | 0.28 | 5.10 | 1.4 | | | | |

| | | | | | | | | | | | |
|--------------|-------|-------|------|------|------|------|------|--|--|--|--|
| | DP-24 | 3.70 | 0.30 | 6.5 | 1.10 | 4.74 | 5.2 | | | | |
| A22 | | 0.93 | 0.15 | 8.7 | 0.14 | 4.32 | 0.6 | | | | |
| | DP-25 | 15.14 | 0.34 | 17.6 | 5.08 | 3.21 | 16.3 | | | | |
| Pond Release | | | | | | | 0.3 | | | | |
| B1 | DP-26 | 2.91 | 0.18 | 13.9 | 0.53 | 3.58 | 1.9 | | | | |
| B2 | DP-27 | 0.72 | 0.87 | 5.0 | 0.63 | 5.10 | 3.2 | | | | |
| B3 | | 0.69 | 0.87 | 5.0 | 0.60 | 5.10 | 3.1 | | | | |
| | DP-28 | 1.41 | 0.87 | 5.6 | 1.22 | 4.94 | 6.1 | | | | |
| B4 | | 0.77 | 0.45 | 7.4 | 0.35 | 4.55 | 1.6 | | | | |
| | DP-29 | 2.18 | 0.72 | 7.4 | 1.57 | 4.55 | 7.2 | | | | |
| B5 | DP-30 | 1.56 | 0.15 | 15.5 | 0.23 | 3.41 | 0.8 | | | | |
| | DP-31 | | | | | | 1.1 | | | | |
| C1 | DP-32 | 1.31 | 0.15 | 7.1 | 0.20 | 4.61 | 0.9 | | | | |
| C2 | DP-33 | 2.09 | 0.16 | 9.2 | 0.34 | 4.24 | 1.5 | | | | |
| C3 | DP-34 | 0.84 | 0.15 | 8.4 | 0.13 | 4.37 | 0.6 | | | | |

PROJECT INFORMATION

PROJECT: Widefield PK-8 School
 PROJECT NO: 21126-00
 DESIGN BY: SBN
 REV. BY: TDM
 AGENCY: City of Colorado Springs
 REPORT TYPE: Final
 DATE: 5/10/2018



Drexel, Barrell & Co.

RATIONAL METHOD CALCULATIONS FOR STORM WATER RUNOFF

PROPOSED

RUNOFF 100 YR STORM

P1= 2.67


| BASIN (S) | DESIGN POINT | AREA (AC) | DIRECT RUNOFF | | | | PIPE SIZING | | | | |
|-----------|--------------|-----------|---------------|----------------------|-------|-----------|-------------|-------|---------------|--------------------------|----------------|
| | | | RUNOFF COEFF | t _c (MIN) | C * A | I (IN/HR) | Q (CFS) | n | Slope (ft/ft) | Calculated Pipe Dia (ft) | Used Pipe (in) |
| A1 | DP-1 | 1.40 | 0.52 | 7.7 | 0.72 | 8.00 | 5.8 | 0.016 | 0.01 | 1.30 | 15" |
| A2 | DP-2 | 0.45 | 0.74 | 11.2 | 0.33 | 6.99 | 2.3 | 0.016 | 0.012 | 0.89 | 12" |
| A3 | | 0.15 | 0.50 | 14.0 | 0.08 | 6.35 | 0.5 | | | | |
| | DP-3 | 2.00 | 0.57 | 14.0 | 1.13 | 6.35 | 7.2 | 0.016 | 0.005 | 1.65 | 18" |
| A4 | DP-4 | 1.72 | 0.51 | 15.3 | 0.87 | 6.11 | 5.3 | 0.016 | 0.005 | 1.43 | 18" |
| | DP-5 | 3.72 | 0.54 | 15.6 | 2.00 | 6.05 | 12.1 | 0.016 | 0.01 | 1.71 | 18" |
| A5 | | 0.38 | 0.54 | 11.2 | 0.20 | 6.98 | 1.4 | | | | |
| A6 | DP-6 | 0.36 | 0.77 | 6.0 | 0.28 | 8.66 | 2.4 | 0.016 | 0.01 | 0.93 | 12" |
| | DP-7 | 4.29 | 0.58 | 15.9 | 2.48 | 6.01 | 14.9 | 0.016 | 0.008 | 1.93 | 24" |
| A7 | DP-8 | 0.21 | 0.96 | 7.1 | 0.20 | 8.21 | 1.7 | 0.016 | 0.005 | 0.93 | 18" |
| A8 | | 0.13 | 0.61 | 8.3 | 0.08 | 7.80 | 0.6 | | | | |
| | DP-9 | 4.63 | 0.60 | 16.3 | 2.76 | 5.94 | 16.4 | 0.016 | 0.021 | 1.69 | 24" |
| A9 | DP-10 | 0.24 | 0.83 | 7.7 | 0.20 | 8.01 | 1.6 | 0.016 | 0.005 | 0.91 | 18" |
| A10 | | 0.66 | 0.82 | 6.4 | 0.54 | 8.48 | 4.6 | | | | |
| | DP-11 | 5.53 | 0.63 | 16.6 | 3.50 | 5.88 | 20.6 | 0.016 | 0.01 | 2.11 | 24" |
| A11 | DP-12 | 0.76 | 0.63 | 5.0 | 0.48 | 9.09 | 4.3 | 0.016 | 0.005 | 1.32 | 15" |
| A12 | | 0.83 | 0.77 | 7.5 | 0.64 | 8.08 | 5.2 | | | | |
| | DP-13 | 1.59 | 0.70 | 7.5 | 1.12 | 8.08 | 9.0 | 0.016 | 0.005 | 1.74 | 18" |
| A13 | | 0.08 | 0.56 | 10.2 | 0.04 | 7.25 | 0.3 | | | | |
| | DP-14 | 1.67 | 0.70 | 10.2 | 1.16 | 7.25 | 8.4 | 0.016 | 0.01 | 1.49 | 18" |
| A14 | | 0.17 | 0.66 | 6.4 | 0.11 | 8.50 | 1.0 | | | | |
| | DP-15 | 1.84 | 0.69 | 10.4 | 1.27 | 7.18 | 9.1 | 0.016 | 0.009 | 1.57 | 18" |
| A15 | DP-16 | 0.26 | 0.81 | 7.6 | 0.21 | 8.06 | 1.7 | 0.016 | 0.005 | 0.93 | 12" |
| | DP-17 | 2.10 | 0.71 | 10.7 | 1.48 | 7.12 | 10.6 | 0.016 | 0.005 | 1.85 | 18" |
| A16 | | 0.17 | 0.69 | 5.0 | 0.12 | 9.09 | 1.1 | | | | |
| | DP-18 | 2.27 | 0.71 | 11.2 | 1.60 | 7.00 | 11.2 | 0.016 | 0.015 | 1.54 | 18" |
| A17 | DP-19 | 1.62 | 0.50 | 15.6 | 0.81 | 6.06 | 4.9 | 0.016 | 0.005 | 1.39 | 12" |
| | DP-20 | 9.42 | 0.63 | 17.0 | 5.91 | 5.81 | 34.4 | 0.016 | 0.018 | 2.28 | 30" |
| A18 | | 1.09 | 0.62 | 15.8 | 0.67 | 6.02 | 4.1 | | | | |
| | DP-21 | 10.51 | 0.63 | 17.5 | 6.59 | 5.73 | 37.7 | 0.016 | 0.134 | 1.63 | 30" |
| A19 | DP-22 | 3.13 | 0.52 | 6.3 | 1.64 | 8.51 | 13.9 | 0.016 | 0.013 | 1.71 | 18" |
| A20 | | 0.26 | 0.96 | 5.0 | 0.25 | 9.09 | 2.3 | | | | |
| | DP-23 | 3.39 | 0.56 | 6.5 | 1.89 | 8.46 | 16.0 | 0.016 | 0.019 | 1.68 | 18" |
| A21 | | 0.31 | 0.96 | 5.0 | 0.30 | 9.09 | 2.7 | | | | |

| | | | | | | | | | | | |
|--------------|-------|-------|------|------|------|------|------|-------|--------|------|-----|
| | DP-24 | 3.70 | 0.59 | 6.5 | 2.19 | 8.44 | 18.4 | 0.016 | 0.078 | 1.36 | 24" |
| A22 | | 0.93 | 0.50 | 8.7 | 0.47 | 7.69 | 3.6 | | | | |
| | DP-25 | 15.14 | 0.61 | 17.6 | 9.24 | 5.72 | 52.8 | | | | |
| Pond Release | | | | | | | 25.1 | 0.016 | 0.0225 | 1.93 | 24" |
| B1 | DP-26 | 2.91 | 0.52 | 13.9 | 1.51 | 6.37 | 9.6 | 0.016 | 0.04 | 1.21 | 24" |
| B2 | DP-27 | 0.72 | 0.94 | 5.0 | 0.68 | 9.09 | 6.2 | 0.016 | 0.015 | 1.23 | 18" |
| B3 | | 0.69 | 0.94 | 5.0 | 0.65 | 9.09 | 5.9 | | | | |
| | DP-28 | 1.41 | 0.94 | 5.6 | 1.33 | 8.80 | 11.7 | 0.016 | 0.04 | 1.30 | 24" |
| B4 | | 0.77 | 0.69 | 7.4 | 0.53 | 8.10 | 4.3 | | | | |
| | DP-29 | 2.18 | 0.85 | 7.4 | 1.85 | 8.10 | 15.0 | 0.016 | 0.04 | 1.43 | 24" |
| B5 | DP-30 | 1.56 | 0.50 | 15.5 | 0.78 | 6.08 | 4.7 | 0.016 | 0.085 | 0.80 | 12" |
| | DP-31 | | | | | | 29.8 | 0.016 | 0.02 | 2.48 | 30" |
| C1 | DP-32 | 1.31 | 0.50 | 7.1 | 0.66 | 8.21 | 5.4 | | | | |
| C2 | DP-33 | 2.09 | 0.51 | 9.2 | 1.06 | 7.54 | 8.0 | | | | |
| C3 | DP-34 | 0.84 | 0.50 | 8.4 | 0.42 | 7.79 | 3.3 | | | | |


Figure 8-7. Inlet Capacity Chart Continuous Grade Conditions, Residential (Local)
(Attached and Detached Sidewalk)

Street Section Data: Street Width Flowline to Flowline = 34'
Type of Curb and Gutter: D-10-R = 8" vertical
Type 16 = 6" vertical

Minor Storm



Major Storm




*A7: Q100 = 1.7 cfs → single Type 16
A9: Q100 = 1.6 cfs → single Type 16
A20: Q100 = 2.3 cfs → single Type 16
A21: Q100 = 2.7 cfs → single Type 16
B1: Q100 = 9.6 cfs → double Type R*

The standard street section parameters as defined in Chapter 7 must apply to use these charts. For non-standard sections, the inlet capacity shall be calculated using the UDFCD spreadsheets. The maximum spread width is limited by the curb height based on no curb overtopping during a minor storm and flow being contained within the public right-of-way during the major storm. Calculations were done using UD-Inlet 3.00.xls, Mar., 2011 with the default clogging factors.


Figure 8-7. Inlet Capacity Chart Continuous Grade Conditions, Residential (Local)
(Attached and Detached Sidewalk)

Street Section Data: Street Width Flowline to Flowline = 34'
Type of Curb and Gutter: D-10-R = 8" vertical
Type 16 = 6" vertical

Minor Storm




Major Storm



*B2: Q100 = 6.2 cfs → Single Type R
B4: Q100 = 4.3 cfs → Single Type R*

The standard street section parameters as defined in Chapter 7 must apply to use these charts. For non-standard sections, the inlet capacity shall be calculated using the UDFCD spreadsheets. The maximum spread width is limited by the curb height based on no curb overtopping during a minor storm and flow being contained within the public right-of-way during the major storm. Calculations were done using UD-Inlet 3.00.xls, Mar., 2011 with the default clogging factors.

Figure 8-11. Inlet Capacity Chart Sump Conditions , Curb Opening (Type R) Inlet



A10: $Q_{100} = 4.6 \text{ cfs} \rightarrow 5' \text{ inlet}$
 B3: $Q_{100} = 5.9 \text{ cfs} \rightarrow 5' \text{ inlet}$

Notes:

1. The standard inlet parameters must apply to use this chart.

Site-Level Low Impact Development (LID) Design Effective Impervious Calculator

LID Credit by Impervious Reduction Factor (IRF) Method

User Input

Calculated cells

| | | | |
|--|----------------|------|--------|
| ***Design Storm: 1-Hour Rain Depth | WQCV Event | 0.53 | inches |
| ***Minor Storm: 1-Hour Rain Depth | 5-Year Event | 1.50 | inches |
| ***Major Storm: 1-Hour Rain Depth | 100-Year Event | 2.52 | inches |
| Optional User Defined Storm | CUHP | | |
| (CUHP) NOAA 1 Hour Rainfall Depth and Frequency for User Defined Storm | 100-Year Event | 2.52 | |

Max Intensity for Optional User Defined Storm: 2.51496

Designer: SBN

Company: Drexel Barrell

Date: May 10, 2018

Project: CSPD Sand Creek Substation

Location: _____

SITE INFORMATION (USER-INPUT)

| Sub-basin Identifier | EDB Wtrshd | | | | | | | | | | | | | | | | | | | |
|--|------------|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| Receiving Pervious Area Soil Type | Clay Loam | | | | | | | | | | | | | | | | | | | |
| Total Area (ac., Sum of DCIA, UIA, RPA, & SPA) | 15.190 | | | | | | | | | | | | | | | | | | | |
| Directly Connected Impervious Area (DCIA, acres) | 3.000 | | | | | | | | | | | | | | | | | | | |
| Unconnected Impervious Area (UIA, acres) | 2.160 | | | | | | | | | | | | | | | | | | | |
| Receiving Pervious Area (RPA, acres) | 0.000 | | | | | | | | | | | | | | | | | | | |
| Separate Pervious Area (SPA, acres) | 10.030 | | | | | | | | | | | | | | | | | | | |
| RPA Treatment Type: Conveyance (C), Volume (V), or Permeable Pavement (PP) | C | | | | | | | | | | | | | | | | | | | |

CALCULATED RESULTS (OUTPUT)

| | | | | | | | | | | | | | | | | | | | | |
|--|--------|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| Total Calculated Area (ac, check against input) | 15.190 | | | | | | | | | | | | | | | | | | | |
| Directly Connected Impervious Area (DCIA, %) | 19.7% | | | | | | | | | | | | | | | | | | | |
| Unconnected Impervious Area (UIA, %) | 14.2% | | | | | | | | | | | | | | | | | | | |
| Receiving Pervious Area (RPA, %) | 0.0% | | | | | | | | | | | | | | | | | | | |
| Separate Pervious Area (SPA, %) | 66.0% | | | | | | | | | | | | | | | | | | | |
| A _p (RPA / UIA) | 0.000 | | | | | | | | | | | | | | | | | | | |
| I _p Check | 1.000 | | | | | | | | | | | | | | | | | | | |
| f / i for WQCV Event: | 0.5 | | | | | | | | | | | | | | | | | | | |
| f / i for 5-Year Event: | 0.2 | | | | | | | | | | | | | | | | | | | |
| f / i for 100-Year Event: | 0.1 | | | | | | | | | | | | | | | | | | | |
| f / i for Optional User Defined Storm CUHP: | 0.12 | | | | | | | | | | | | | | | | | | | |
| IRF for WQCV Event: | 1.00 | | | | | | | | | | | | | | | | | | | |
| IRF for 5-Year Event: | 1.00 | | | | | | | | | | | | | | | | | | | |
| IRF for 100-Year Event: | 1.00 | | | | | | | | | | | | | | | | | | | |
| IRF for Optional User Defined Storm CUHP: | 1.00 | | | | | | | | | | | | | | | | | | | |
| Total Site Imperviousness: I _{total} | 34.0% | | | | | | | | | | | | | | | | | | | |
| Effective Imperviousness for WQCV Event: | 34.0% | | | | | | | | | | | | | | | | | | | |
| Effective Imperviousness for 5-Year Event: | 34.0% | | | | | | | | | | | | | | | | | | | |
| Effective Imperviousness for 100-Year Event: | 34.0% | | | | | | | | | | | | | | | | | | | |
| Effective Imperviousness for Optional User Defined Storm CUHP: | 34.0% | | | | | | | | | | | | | | | | | | | |


LID / EFFECTIVE IMPERVIOUSNESS CREDITS

| | | | | | | | | | | | | | | | | | | | | |
|--|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|--|
| WQCV Event CREDIT: Reduce Detention By: | 0.0% | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | |
| This line only for 10-Year Event | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | |
| 100-Year Event CREDIT**: Reduce Detention By: | 0.0% | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | |
| User Defined CUHP CREDIT: Reduce Detention By: | 0.0% | | | | | | | | | | | | | | | | | | | |

| | |
|---|-------|
| Total Site Imperviousness: | 34.0% |
| Total Site Effective Imperviousness for WQCV Event: | 34.0% |
| Total Site Effective Imperviousness for 5-Year Event: | 34.0% |
| Total Site Effective Imperviousness for 100-Year Event: | 34.0% |
| Total Site Effective Imperviousness for Optional User Defined Storm CUHP: | 34.0% |

Notes:


- * Use Green-Ampt average infiltration rate values from Table 3-3.
- ** Flood control detention volume credits based on empirical equations from Storage Chapter of USDCM.
- *** Method assumes that 1-hour rainfall depth is equivalent to 1-hour intensity for calculation purposed



- LEGEND
- UNCONNECTED IMPERVIOUS AREA (UIA)
 - DIRECTLY CONNECTED IMPERVIOUS AREA (DCIA)
 - SEPARATE PERVIOUS AREA (SPA)

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

UD-Detention, Version 3.07 (February 2017)




Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)

Project: _____

Basin ID: _____



Example Zone Configuration (Retention Pond)

| | Stage (ft) | Zone Volume (ac-ft) | Outlet Type |
|-------------------|------------|---------------------|----------------------|
| Zone 1 (WQCV) | 1.74 | 0.207 | Orifice Plate |
| Zone 2 (EURV) | 3.12 | 0.267 | Orifice Plate |
| Zone 3 (100-year) | 5.32 | 0.596 | Weir&Pipe (Circular) |
| | | 1.070 | Total |

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
 Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain

Underdrain Orifice Area = ft²
 Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
 Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
 Orifice Plate: Orifice Vertical Spacing = inches
 Orifice Plate: Orifice Area per Row = sq. inches (diameter = 1-9/16 inches)

Calculated Parameters for Plate

WQ Orifice Area per Row = ft²
 Elliptical Half-Width = feet
 Elliptical Slot Centroid = feet
 Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

| | Row 1 (required) | Row 2 (optional) | Row 3 (optional) | Row 4 (optional) | Row 5 (optional) | Row 6 (optional) | Row 7 (optional) | Row 8 (optional) |
|--------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| Stage of Orifice Centroid (ft) | 0.00 | 1.28 | 2.56 | | | | | |
| Orifice Area (sq. inches) | 1.89 | 1.89 | 1.89 | | | | | |

| | Row 9 (optional) | Row 10 (optional) | Row 11 (optional) | Row 12 (optional) | Row 13 (optional) | Row 14 (optional) | Row 15 (optional) | Row 16 (optional) |
|--------------------------------|------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|
| Stage of Orifice Centroid (ft) | | | | | | | | |
| Orifice Area (sq. inches) | | | | | | | | |

User Input: Vertical Orifice (Circular or Rectangular)

| | Not Selected | Not Selected | |
|---|----------------------------------|----------------------------------|---|
| Invert of Vertical Orifice = | <input type="text" value="N/A"/> | <input type="text" value="N/A"/> | ft (relative to basin bottom at Stage = 0 ft) |
| Depth at top of Zone using Vertical Orifice = | <input type="text" value="N/A"/> | <input type="text" value="N/A"/> | ft (relative to basin bottom at Stage = 0 ft) |
| Vertical Orifice Diameter = | <input type="text" value="N/A"/> | <input type="text" value="N/A"/> | inches |

Calculated Parameters for Vertical Orifice

| | Not Selected | Not Selected | |
|-----------------------------|----------------------------------|----------------------------------|-----------------|
| Vertical Orifice Area = | <input type="text" value="N/A"/> | <input type="text" value="N/A"/> | ft ² |
| Vertical Orifice Centroid = | <input type="text" value="N/A"/> | <input type="text" value="N/A"/> | feet |

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped)

| | Zone 3 Weir | Not Selected | |
|---------------------------------------|-----------------------------------|----------------------------------|---|
| Overflow Weir Front Edge Height, Ho = | <input type="text" value="3.75"/> | <input type="text" value="N/A"/> | ft (relative to basin bottom at Stage = 0 ft) |
| Overflow Weir Front Edge Length = | <input type="text" value="3.91"/> | <input type="text" value="N/A"/> | feet |
| Overflow Weir Slope = | <input type="text" value="0.00"/> | <input type="text" value="N/A"/> | H:V (enter zero for flat grate) |
| Horiz. Length of Weir Sides = | <input type="text" value="3.91"/> | <input type="text" value="N/A"/> | feet |
| Overflow Grate Open Area % = | <input type="text" value="70%"/> | <input type="text" value="N/A"/> | %, grate open area/total area |
| Debris Clogging % = | <input type="text" value="50%"/> | <input type="text" value="N/A"/> | % |

Calculated Parameters for Overflow Weir

| | Zone 3 Weir | Not Selected | |
|--|------------------------------------|----------------------------------|-----------------|
| Height of Grate Upper Edge, H ₁ = | <input type="text" value="3.75"/> | <input type="text" value="N/A"/> | feet |
| Overflow Weir Slope Length = | <input type="text" value="3.91"/> | <input type="text" value="N/A"/> | feet |
| Grate Open Area / 100-yr Orifice Area = | <input type="text" value="3.41"/> | <input type="text" value="N/A"/> | should be ≥ 4 |
| Overflow Grate Open Area w/o Debris = | <input type="text" value="10.70"/> | <input type="text" value="N/A"/> | ft ² |
| Overflow Grate Open Area w/ Debris = | <input type="text" value="5.35"/> | <input type="text" value="N/A"/> | ft ² |

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

| | Zone 3 Circular | Not Selected | |
|----------------------------------|------------------------------------|----------------------------------|--|
| Depth to Invert of Outlet Pipe = | <input type="text" value="2.50"/> | <input type="text" value="N/A"/> | ft (distance below basin bottom at Stage = 0 ft) |
| Circular Orifice Diameter = | <input type="text" value="24.00"/> | <input type="text" value="N/A"/> | inches |

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

| | Zone 3 Circular | Not Selected | |
|--|-----------------------------------|----------------------------------|-----------------|
| Outlet Orifice Area = | <input type="text" value="3.14"/> | <input type="text" value="N/A"/> | ft ² |
| Outlet Orifice Centroid = | <input type="text" value="1.00"/> | <input type="text" value="N/A"/> | feet |
| Half-Central Angle of Restrictor Plate on Pipe = | <input type="text" value="N/A"/> | <input type="text" value="N/A"/> | radians |

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = ft (relative to basin bottom at Stage = 0 ft)
 Spillway Crest Length = feet
 Spillway End Slopes = H:V
 Freeboard above Max Water Surface = feet

Calculated Parameters for Spillway




Spillway Design Flow Depth = feet
 Stage at Top of Freeboard = feet
 Basin Area at Top of Freeboard = acres

Routed Hydrograph Results

| | WQCV | EURV | 2 Year | 5 Year | 10 Year | 25 Year | 50 Year | 100 Year | 500 Year |
|---|-------|-------|--------|------------------|------------------|------------------|------------------|------------------|----------------|
| Design Storm Return Period = | | | | | | | | | |
| One-Hour Rainfall Depth (in) = | 0.53 | 1.07 | 1.19 | 1.50 | 1.75 | 2.00 | 2.25 | 2.52 | 3.49 |
| Calculated Runoff Volume (acre-ft) = | 0.207 | 0.474 | 0.437 | 0.704 | 0.979 | 1.490 | 1.857 | 2.320 | 3.581 |
| OPTIONAL Override Runoff Volume (acre-ft) = | | | | | | | | | |
| Inflow Hydrograph Volume (acre-ft) = | 0.206 | 0.473 | 0.437 | 0.703 | 0.978 | 1.488 | 1.855 | 2.317 | 3.577 |
| Predevelopment Unit Peak Flow, q (cfs/acre) = | 0.00 | 0.00 | 0.01 | 0.12 | 0.33 | 0.76 | 1.01 | 1.32 | 2.12 |
| Predevelopment Peak Q (cfs) = | 0.0 | 0.0 | 0.2 | 1.8 | 5.0 | 11.6 | 15.3 | 20.0 | 32.2 |
| Peak Inflow Q (cfs) = | 3.4 | 7.7 | 7.1 | 11.3 | 15.7 | 23.8 | 29.6 | 36.9 | 56.5 |
| Peak Outflow Q (cfs) = | 0.1 | 0.2 | 0.2 | 0.8 | 6.2 | 14.7 | 20.9 | 27.0 | 40.0 |
| Ratio Peak Outflow to Predevelopment Q = | N/A | N/A | N/A | 0.5 | 1.3 | 1.3 | 1.4 | 1.3 | 1.2 |
| Structure Controlling Flow Plate = | Plate | Plate | Plate | Overflow Grate 1 | Overflow Grate 1 | Overflow Grate 1 | Overflow Grate 1 | Overflow Grate 1 | Outlet Plate 1 |
| Max Velocity through Grate 1 (fps) = | N/A | N/A | N/A | 0.0 | 0.5 | 1.4 | 1.9 | 2.5 | 3.7 |
| Max Velocity through Grate 2 (fps) = | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Time to Drain 97% of Inflow Volume (hours) = | 38 | 54 | 53 | 61 | 58 | 55 | 52 | 49 | 42 |
| Time to Drain 99% of Inflow Volume (hours) = | 40 | 58 | 56 | 65 | 64 | 63 | 62 | 60 | 57 |
| Maximum Ponding Depth (ft) = | 1.63 | 2.97 | 2.81 | 3.81 | 4.06 | 4.32 | 4.47 | 4.68 | 5.49 |
| Area at Maximum Ponding Depth (acres) = | 0.16 | 0.22 | 0.21 | 0.25 | 0.26 | 0.27 | 0.28 | 0.29 | 0.33 |
| Maximum Volume Stored (acre-ft) = | 0.189 | 0.440 | 0.406 | 0.639 | 0.703 | 0.770 | 0.812 | 0.872 | 1.126 |

Detention Basin Outlet Structure Design

UD-Detention, Version 3.07 (February 2017)



| S-A-V-D Chart Axis Override | X-axis | Left Y-Axis | Right Y-Axis |
|-----------------------------|--------|-------------|--------------|
| minimum bound | | | |
| maximum bound | | | |

Widefield PK-8 school - Forebay volumes

$$\text{Forebay} = 3\% \text{ of WQCV} = 0.03 \times 0.207 = 0.0062 \text{ ac-ft}$$

$$Q_{\text{in east}} = 18.4 \text{ cfs}$$

$$Q_{\text{in south}} = 37.7 \text{ cfs}$$

$$Q_{\text{total}} = 56.1 \text{ cfs}$$

$$\frac{18.4 \text{ cfs}}{56.1 \text{ cfs}} = \frac{x \text{ ac-ft}}{0.0062 \text{ ac-ft}}$$

$$\begin{aligned} x &= 0.0020 \text{ ac-ft} \\ &= 88.6 \text{ ft}^3 \end{aligned}$$

← East forebay volume

$$\frac{37.7 \text{ cfs}}{56.1 \text{ cfs}} = \frac{x \text{ ac-ft}}{0.0062 \text{ ac-ft}}$$

$$\begin{aligned} x &= 0.0042 \text{ ac-ft} \\ &= 181.5 \text{ ft}^3 \end{aligned}$$

← South forebay volume




Figure 1 – Micropool surface area (SA) determination chart

The tributary impervious area is the effective number of impervious acres that will be treated by the extended detention basin (EDB). It is calculated by multiplying the tributary area to be treated by the impervious fraction of that area.

$$TIA = I \times A$$

TIA = Tributary impervious area (acres)
 I = Imperviousness (fraction)
 A = Tributary catchment area upstream (acres)

$\frac{34}{100} \times 15.19 = 5.16 \text{ ac}$

For EDBs with tributary impervious areas greater than 100 acres, the micropool surface area is 400 sf. The initial surcharge depth (ISD) is defined as the depth of the initial surcharge volume (ISV). The surface area determined using Figure 1 assumes an ISD of 4 inches. The initial surcharge volume is thus calculated by multiplying the micropool surface area by 4 inches.

$$ISV = SA \times 4 \text{ inches}$$

ISV = Initial surcharge volume (cf)
 SA = Surface area (from Figure 1, sf)

FOREBAY VOLUME

$$V = 3\% \times \text{WQCV}$$

$$\text{WQCV} = 0.207 \text{ ac-ft}$$

$$V = 0.0062 \text{ ac-ft}$$

FOREBAY RELEASE NOTCH WIDTH - EAST

$$Q = CLH^{2/3}$$

$$Q_{100} = 18.4 \text{ cfs}$$

$$2\% \text{ of } Q = 0.37 \text{ cfs}$$

$$C = 2.6$$

$$H \text{ (height of forebay wall)} = 1 \text{ ft}$$

$$L = 2 \text{ in}$$

FOREBAY RELEASE NOTCH WIDTH - SOUTH

$$Q = CLH^{2/3}$$


$$Q_{100} = 37.7 \text{ cfs}$$

$$2\% \text{ of } Q = 0.75 \text{ cfs}$$

$$C = 2.6$$

$$H \text{ (height of forebay wall)} = 1 \text{ ft}$$

$$L = 3 \text{ in}$$



LEGEND

- PROPOSED INTERMEDIATE CONTOUR
- PROPOSED INDEX CONTOUR
- EX. INTERMEDIATE CONTOUR
- EX. INDEX CONTOUR
- PROPOSED STORM SEWER
- PROPOSED INLET
- PROPOSED FLARED END SECTION
- PROPOSED SITE LIGHTING
- PROPOSED PEDESTRIAN LIGHTING
- EX. MANHOLE
- EX. STORM SEWER
- BASIN BOUNDARY
- FLOW DIRECTION
- DESIGN POINT

AREA (ACRE) $\frac{A1}{Q100}$ 05 (cfs)
Q100 (cfs)

SCALE: 1"=50'

50 20 0 50 100

| DP | AREA (AC) | Q5 (cfs) | Q100 (cfs) |
|-------|-----------|----------|------------|
| DP-0 | 0.42 | 0.8 | 2.3 |
| DP-1 | 1.80 | 1.7 | 7.0 |
| DP-2 | 0.45 | 1.0 | 2.3 |
| DP-3 | 0.15 | 1.8 | 5.5 |
| DP-4 | 1.72 | 0.9 | 5.3 |
| DP-5 | 3.50 | 2.6 | 11.4 |
| DP-6 | 0.36 | 1.1 | 2.4 |
| DP-7 | 4.07 | 4.0 | 14.2 |
| DP-8 | 0.21 | 0.9 | 1.7 |
| DP-9 | 4.41 | 4.7 | 15.7 |
| DP-10 | 0.24 | 0.7 | 1.6 |
| DP-11 | 5.31 | 6.8 | 19.9 |
| DP-12 | 0.54 | 0.8 | 2.6 |
| DP-13 | 1.38 | 3.2 | 7.8 |
| DP-14 | 1.47 | 2.9 | 7.4 |
| DP-15 | 1.64 | 3.2 | 8.1 |
| DP-16 | 0.12 | 0.4 | 0.8 |
| DP-17 | 1.76 | 3.5 | 8.7 |
| DP-18 | 1.93 | 3.8 | 9.4 |
| DP-19 | 1.62 | 0.8 | 4.9 |
| DP-20 | 8.88 | 10.6 | 32.2 |
| DP-21 | 9.95 | 11.7 | 35.8 |
| DP-22 | 3.13 | 2.8 | 13.9 |
| DP-23 | 3.46 | 4.1 | 18.4 |
| DP-24 | 3.84 | 5.6 | 19.4 |
| DP-25 | 14.72 | 18.0 | 51.4 |
| DP-26 | 2.81 | 1.9 | 9.6 |
| DP-27 | 0.72 | 3.2 | 6.2 |
| DP-28 | 1.41 | 6.1 | 11.7 |
| DP-29 | 2.18 | 7.2 | 15.0 |
| DP-30 | 1.56 | 0.8 | 4.7 |
| DP-31 | 16.28 | 11 | 29.8 |
| DP-32 | 1.31 | 0.9 | 3.4 |
| DP-33 | 2.09 | 1.5 | 8.0 |
| DP-34 | 0.84 | 0.6 | 3.3 |

LKA PARTNERS
INCORPORATED
A Professional Corporation for Architecture and Planning
430 North Tejon Street, Suite 200
Colorado Springs, Colorado 80903
Tel: 719.473.8446 Fax: 719.473.8448
Web: www.lkpartners.com

DREXEL, BARRELL & CO.
Engineers & Surveyors
13001 7TH STREET
COLORADO SPRINGS, COLORADO 80905
CONTACT: TIM D. MCCONNELL, P.E.
(719) 588-8887
BOULDER COLORADO SPRINGS WIRELEY

© Copyright 2017 The LKA Partners, Inc. This document and its information contained herein may not be reproduced or copied from without the express written permission of The LKA Partners, Inc. Unauthorized copying, disclosure or construction use are prohibited by copyright law.

New Widefield PK-8 School
11060 Fontaine Blvd., Widefield, CO
Widefield School District 3
1820 Main Street
Colorado Springs, CO 80911



Construction Documents

Drawn: SBN
Checked: TDM
Issued: 03 July 2018
Revised:

DRAINAGE MAP

PROPOSED DRAINAGE MAP

DR-PR

Markup Summary

dsdrice (2)

ical Engineering Report. Prepared by Terracon Cons
1, 2018.
lage Plan Lorson Ranch East Filling No. 1," prepared t
2, March 1, 2018.

July 2, 2018

Subject: Callout
Page Label: 11
Lock: Unlocked
Author: dsdrice
Date: 1/15/2019 1:53:03 PM
Color: ■

July 2, 2018

... This design point reflects all of the flows from

flowed end section in Basin A19. The flows leave via an
effects all of the flows from Basin A19.

at grade flow to inlet in Basin A20. The flows leave this
sign point reflects all of the flows from Basins A19 and

Are these
combination
inlets? Provide
a detail.

Subject: Cloud+
Page Label: 7
Lock: Unlocked
Author: dsdrice
Date: 1/15/2019 1:53:19 PM
Color: ■

Are these combination inlets? Provide a detail.