

6825 Silver Ponds Heights #101 Colorado Springs, CO 80908 (719) 481-4560

SOILS REPORT

FOR

PALACE HOMES

JOB #17-0765

Site #237,
Crystal Park Subdivision,
5320 Lost Cabin Road,
El Paso County,
Colorado

Respectfully submitted,

Charles E. Milligan, P.E.

Civil Engineer



TABLE OF CONTENTS

INTRODUCTION	1
CONCLUSIONS	1
GENERAL	1
FIELD AND LABORATORY INVESTIGATION	1
TOPOGRAPHY	2
WEATHER	2
DESIGN AND CONSTRUCTION CONSIDERATIONS	2 - 3
RECOMMENDATION REMARKS	3
COLD TEMPERATURE CONSIDERATIONS	3
SURFACE DRAINAGE	4
SUBSURFACE DRAINAGE	4
REINFORCING	4
FOOTING DESIGN	4
CONSTRUCTION DETAILS	4
MINIMUM MATERIALS SPECIFICATIONS	5
OPEN HOLE OBSERVATION	5
LOGS	6
SITE MAP	7
SIEVE ANALYSIS RESULTS	8
PERIMETER DRAIN SKETCH	9
TIMITATIONS	10

INTRODUCTION

The owners must be made aware of the contents of this report. If there are any questions or concerns regarding the information in this report please contact us. This is to ensure that the recommendations and requirements of the report, especially regarding the surface drainage, are acknowledged and followed. This report is prepared for Palace Homes, builder on Site #237, Crystal Park Subdivision, 5320 Lost Cabin Road, El Paso County, Colorado. It is my understanding that a single-family residence is planned for this site. The site is currently vacant.

CONCLUSIONS

A satisfactory foundation for this structure is a properly designed shallow foundation system consisting of foundation components resting directly on undisturbed materials. Foundation components resting directly on undisturbed moderate-density decomposed granite materials shall be designed for a loading of not greater than 2,000 pounds per square foot. Foundation components resting directly on undisturbed high-density materials shall be designed for a loading of not greater than 4,000 pounds per square foot. Any design by any engineer is subject to revision based on the results of the open hole observation. The compressibility of this material is low. This bearing capacity is calculated with a safety factor of three. The type of foundation configuration used depends on the building loads applied. depth of foundation elements shall be determined by the foundation engineer, but should be at least as deep as the minimum depth required by the governing building authority. The laboratory testing revealed that the on-site soil is silty sand with underlying poorly-graded silty sand (U.S.C. Classification Symbol SM, SP). The unit weight of equivalent fluid soil pressure of this material is 40 (SM) and 34 (SP) pounds per cubic foot. The owners shall be made aware that movement will occur if surface or subsurface water is allowed to collect around the foundation wall.

GENERAL

The investigation was made to reveal important characteristics of the soils and of the site influencing the foundation design. Also evaluated during the investigation were subsurface conditions that affect the depth of the foundation and subsequent loading design, such as ground water levels, soil types, and other factors which affect the bearing capacity of the soils. Design loadings are based on soils characteristics and represent the maximum permissible loads for these conditions.

FIELD AND LABORATORY INVESTIGATION

One exploratory hole was drilled on August 25, 2017, at the location shown on the enclosed site map. The location of this test hole was determined by Palace Homes. The test hole was drilled with a 4-inch diameter auger. At intervals anticipated to be the foundation depths, and as determined by the soils conditions, the drill tools were removed and a sample was taken by the use of a 2-inch split barrel sampler connected to a 140-pound drop-hammer. This hammer is dropped 30 inches to drive the penetration sampler into the soil (ASTM D-1586). The depths and descriptions of the materials encountered in the test boring at which the sample was taken is shown on the enclosed log sheets. The sample was classified both in the field and in the laboratory to evaluate the physical and mechanical properties of the materials encountered.

TOPOGRAPHY

The topography of this site is that of man-made flat.

WEATHER

The weather at the time of the soil examination consisted of clear skies with hot temperatures.

DESIGN AND CONSTRUCTION CONSIDERATIONS

Residential basement slabs-on-grade may move and crack. Vertical slab movement of one to three inches is considered normal for soils of low to moderate expansion potential and for compacted structural fill after removal of highly expansive soils. In some cases, vertical movement may exceed this range. If movement and associated damage to basement floors and finish cannot be tolerated, a structural floor system should be installed. If compaction is not performed, settlement may occur causing cracking of foundation walls and floors. Soil located beneath concrete walls shall be compacted to at least 95% Modified Proctor density. Soil located beneath concrete floors shall be compacted to at least 85% Modified Proctor density. Special care is to be taken to re-compact the material above utility lines to a minimum of 85% Modified Proctor density. During construction, conditions that could cause settlement shall be eliminated. Interior non-bearing partition walls shall be constructed such that they do not transmit floor slab movement to the roof or overlying floor. The gap or void (1.5" min.) installed in these non-bearing partitions may require re-construction over the life of the structure to re-establish the gap or void to allow for vertical slab movement. Stairwells, doorways and sheeted walls should be designed for this movement. following are general recommendations of on-grade slabs:

- 1. Slabs shall be placed on well-compacted, non-expansive materials, and all soft spots shall be thoroughly excavated and replaced with non-expansive fill materials as stated above.
- 2. Separate the slab from all foundation walls, load bearing members, and utility lines.
- 3. At intervals not to exceed 12 feet in each direction, provide control joints to reduce problems with shrinkage and curling as recommended by the American Concrete Institute (ACI). Moisten the ground beneath the slab prior to placement of concrete.
- 4. All concrete placed must be cured properly as recommended by the American Concrete Institute (ACI). Separate load bearing members from slabs, as discussed above. Care must be exercised to prevent excess moisture from entering the soil under the structure, both during and after construction.
- 5. Due to the exposure of exterior concrete to variations in moisture fluctuations, heaving and cracking of exterior slabs-on-grade should be expected. Placement of at least 3 feet of non-expansive fill beneath the slabs can help to reduce the impact of differential movement and cracking but may not eliminate movement.

DESIGN AND CONSTRUCTION CONSIDERATIONS (CONTINUED)

The soil has been analyzed for its expansion and/or consolidation potential. Basement slabs, garage slabs, and all concrete floor slabs, however, exert a very low dead-load pressure on the soil. Since almost any soil contains at least a small amount of expansion potential, slabs may crack and heave or settle if excess water is allowed to penetrate the sub-grade. For example, column openings to pads below the placed slab, if exposed to precipitation during construction, will conduct water to the sub-grade, possibly causing it to expand. Also, if the slab is placed with concrete too wet, expansion may occur. We recommend 3,000 psi concrete placed at a maximum slump of 4 inches.

RECOMMENDATION REMARKS

The recommendations provided in this report are based upon the observed soil parameters, anticipated foundation loads, and accepted engineering procedures. The recommendations are intended to minimize differential movement resulting from the heaving of expansive soil or from the settlement induced by the application of loads. It must be recognized that the foundation will undergo some movement on all soil types. In addition, concrete floor slabs will move vertically, therefore, adherence to those recommendations which isolate floor slabs from columns, walls, partitions or other structural components is extremely important, if damage to the superstructure is to be minimized. Any subsequent owners should be apprised of the soil conditions and advised to maintain good practice in the future with regard to surface and subsurface drainage and partition framing, drywall and finish work above floor slabs.

Geoquest, LLC does not assure that the contractor and/or homeowner will comply with the recommendations provided in this report. Geoquest, LLC provides recommendations and requirements only and does not supervise, direct or control the implementation of such.

COLD TEMPERATURE CONSIDERATIONS

- 1. Concrete shall not be placed upon frozen soil.
- 2. Concrete shall be protected from freezing until it has been allowed to cure for at least 7 days after placement in forms.
- 3. Snow or other frozen water shall not be allowed in the forms during placement of concrete.
- 4. Concrete shall be cured in forms for at least 72 hours.
- 5. The site shall be kept well drained at all times.

SURFACE DRAINAGE

After construction of foundation walls, the backfill material shall be well compacted to 80% Modified Proctor density, to prevent future settlement. Any areas that settle after construction shall be filled to eliminate ponding of water adjacent to the foundation walls. The finished grade shall have a positive slope away from the structure with an initial slope of 6" in the first 10'. If a 10' zone is not possible on the upslope site of the structure, then a well-defined swale should be created a minimum of 5' from the foundation and sloped parallel with the wall at a 2% grade to intercept the surface water and carry it around and away from the structure. Homeowners shall maintain the surface grading and drainage installed by the builder to prevent water directed in the wrong direction. All downspouts shall have splash blocks that will remove runoff to outside the foundation area and carried across backfill zones. No irrigation devices shall be placed within 7' of the foundation. Shrubs and plants requiring minimal watering shall be established in this area. Irrigated grass shall not be located within 5' of the foundation. Sprinklers shall not discharge water within 5' of the foundation. Irrigation should be limited to the minimum amount sufficient to maintain vegetation. Application of more water will increase likelihood of floor slab and foundation movement.

SUBSURFACE DRAINAGE

The necessity for perimeter drains will be determined at the time of the Open Hole Observation.

REINFORCING

The concrete foundation walls shall be properly reinforced as per the specific design for this foundation by a Professional Engineer. Exact requirements are a function of the design of the structure. Questions concerning the specific design requirements shall be referred to the design engineer.

FOOTING DESIGN

The design for footings for this structure is determined by applying the dead load and full live load to the foundation walls.

CONSTRUCTION DETAILS

It is necessary with any soils investigation to assume that the materials from the test holes are representative of the materials in the area. On occasion variations in the subsurface materials do occur, therefore, should such variations become apparent during construction, the owner is advised to contact this office for a determination as to whether these variations will affect the design of the structure's foundation. If clay layers are observed during the excavation for the dwelling, this office should be contacted to determine whether the layers will adversely affect the design.

MINIMUM MATERIALS SPECIFICATIONS

- 1. Minimum materials specifications of the concrete, reinforcing, etc., shall be determined by the Professional Engineer.
- 2. Compact beneath foundation walls a minimum of 95% Modified Proctor density to prevent settlement.
- 3. Compact all backfill material located around the perimeter of the foundation to a minimum of 80% Modified Proctor density.
- 4. Concrete shall be vibrated or rodded in forms to avoid segregation and cold joints.
- The site shall be kept well drained at all times.


OPEN HOLE OBSERVATION (added cost)

If anyone other than Geoquest performs the Open Hole Observation, that person/company assumes liability for the soils, and any possible changes to the foundation design.

The owner, or a representative of the construction company shall contact Geoquest, LLC. a minimum of 24 hours prior to excavating for the foundation. An Open Hole Observation must be performed on each individual structure prior to the placement of concrete, and preferably prior to the placement of forms in the excavated area. The failure to request or obtain an Open Hole Observation prior to the placement of foundation components may result in this Soils Report being declared null and void. This is to ensure that soft areas, anomalies, etc., are not present in the foundation region. At the time of the open hole observation the foundation type recommendations, maximum allowable bearing capacity may be revised according to soil conditions found at that time. If revisions are made to the Soils Report Due to the soil conditions of the excavation, the Foundation Design Engineer must be notified of all revisions.



EXTERIOR DRAIN DETAIL



- 1. Gravel to be Not More Than 1-1/2" and Not Less Than 1/2" Diameter.
- 2. Perforated Pipe Diameter Varies With Expected Seepage. 3"Ø and 4"Ø are Most Common. ABS and PVC are Most Common Materials for Pipe.
- 3. Pipe to be Laid out in a Minimum Slope of 1" in 10'.
- 4. Gravity Outfall is Desired if Possible. Portion of Pipe in Area Not Drained Shall be Non-Perforated. Daylight Must be Maintained Clear of Debris in Order to Function Properly.
- 5. If Gravity Outfall is Not Possible, Provide a Sump With Operational Pump. Pump May Not Connect to Any Sanitary or Storm Sewer.
- 6. Soil Backfill Should be Compacted to at Least 80% of the Modified Proctor Denisty in the Upper Three Feet of Fill.
- 7. Filter Fabric to be Mirafi 140s or Approved Equivalent. Roofing Felt and Sheet Plastic are Not Acceptable.
- 8. Drain Pipe Shall be Laid Below Protected Area, as Shown in The Detail Above.
- 9. Mop Polyethylene Film to Wall Approximately One Foot Above Joint of Footing and Wall and Carry Beneath Gravel and Pipe.
- 10. The Polyethylene Film Shall be Continued to the Edge of the Excavation.

LIMITATIONS

This report is issued based on the understanding that the owner or his representative will bring the information, data, and recommendations contained in this report to the attention of the project engineer and architect, in order that they may be incorporated into the plans for the structure. It is also the owner's responsibility to ensure that all contractors and sub-contractors carry out these recommendations during the construction phase.

This report was prepared in accordance with generally accepted professional geotechnical/engineering methods. However, Geoquest, LLC makes no other warranty, express or implied, as to the findings, data, specifications, or professional advice rendered hereunder.

This report is considered valid as of the present date. The owner acknowledges, however, that changes in the conditions of the property might occur with the passage of time, such as those caused by natural effects or man-made changes, both on this land and on abutting properties. Further, changes in acceptable tolerances or standards might arise as the result of new legislative actions, new engineering advances, or the broadening of geotechnical knowledge. Thus, certain developments beyond our control may invalidate this report, in whole or in part.

This report and its recommendations do not apply to any other site than the one described herein and are predicated on the assumption that the soil conditions do not deviate from those described. In the event that any variations or undesirable conditions should be detected during the construction phase or if the proposed construction varies from that planned as of this report date, the owner shall immediately notify Geoquest, LLC in order that supplemental recommendations can be provided, if so required.



ROCKY MOUNTAIN GROUP

Job No. 166667

October 5, 2018

Palace Homes 1216 W. Colorado Ave. #110 Colorado Springs, CO 80904

Re:

Geologic Hazard Study 5320 Lost Cabin Rd S-237, Crystal Park El Paso County, Colorado

Dear Gordon Stegner:

This report presents the findings of an evaluation performed by RMG – Rocky Mountain Group of the above-referenced site in El Paso County, Colorado. The purpose of our report is to evaluate the site conditions and present our opinions of the observed conditions on the proposed development with respect to the intended usage.

Revisions and modifications to the conclusions and recommendations presented in this report may be issued subsequently by RMG based upon additional observations made during grading and construction (which may indicate conditions that require re-evaluation of some of the criteria presented in this report) and/or upon receipt of review comments from El Paso County and/or any third-party reviewing agencies.

Qualifications of Preparers

This Geologic Hazard Study was prepared by a professional geologist as defined by Colorado Revised Statures section 34-1-201(3) and by a qualified geotechnical engineer as defined by policy statement 15, "Engineering in Designated Natural Hazards Areas" of the Colorado State Board of Registration for Professional Engineers and Professional Land Surveyors. (Ord. 96-74; Ord. 01-42)

The principle investigators for this study are Kelli Zigler, P.G. and Tony Munger, P.E. Ms. Zigler is a professional Geologist with over 18 years of experience in the geological and geotechnical engineering field. Ms. Zigler holds a Bachelor of Science in Geology from the University of Tulsa. Ms. Zigler has supervised and performed numerous geological and geotechnical field investigations in Colorado. Tony Munger is a licensed professional engineer with over 18 years of experience in the construction engineering (residential) field. Mr. Munger and holds a Bachelor of Science in Architectural Engineering from the University of Wyoming.

Fort Collins: 970.616.4364

Existing and Proposed Land Use

The site is to consist of an approximately 30,492 square foot parcel zoned as "PUD" Planned Unit Development per El Paso County zoning. The proposed land use is to create an approximately 0.70 acre single-family parcel known as Site S-237(R) within the Crystal Park subdivision.

Project Description

The proposed development of this site is to consist of the construction of a single-family dwelling with a onsite wastewater treatment system and well. This geologic hazards study was performed to evaluate geologic conditions that may impact the proposed development and provide recommendations for mitigation and design for residential construction.

Site Evaluation Techniques

The information included in this report has been compiled from

- 1. Field reconnaissance
- 2. Geologic and topographic maps
- 3. Review of previous reports performed by RMG in the same subdivision
- 4. Available aerial photographs
- 5. Geologic research and analysis
- 6. Site development plans prepared by others

Geophysical investigations were not considered necessary for characterization of the site geology.

Previous Studies and Field Investigation

Reports of previous geotechnical engineering/geologic investigations specifically addressed to this site were available for our review and are listed below:

- 1. Soils Report for Palace Homes, Site #237, Crystal Park Subdivision, 5320 Lost Cabin Road, El Paso County, Colorado, prepared by Geoquest, Inc., Job #17-0765 dated November 9, 2017.
- 2. Profile Pit Evaluation for Palace Homes, Site #237, Crystal Park Subdivision, 5320 Lost Cabin Road, El Paso County, Colorado, prepared by Geoquest, Inc., Job #17-0765 dated November 9, 2017.
- 3. Site Plan, Bomgaars Residence, prepared by LGA Studios, last dated June 27, 2018.

Site Conditions

We performed a site visit for field reconnaissance on September 7, 2018. At the time of the field reconnaissance, the site consisted of vacant land generally located east of the intersection of Crystal Park Road and Palmer Trail in El Paso County, Colorado. The ground surface within the proposed building area was covered with vegetation consisting of tall grasses, weeds. The remainder of the site contained a moderate to high growth of coniferous trees, aspens, and boulders scattered throughout the entire property. Topographically, the site is located on a hillside east of Crystal Park Lake. The slopes within the footprint of the proposed residence varied from approximately 10 to 25 percent, but slopes across the

remainder of the site ranged up to a 70 percent grade. The site has generally good drainage in the form of surface sheet flow directed to the north and east. Minor slope creep was observed in the vicinity of the site as evidenced by occasional curved trees.

General Geology

Based upon mapping presented by the Colorado Geological Survey (CGS) (¹Keller et al, 2003), the bedrock underlying the subject site is comprised of the Pikes Peak Granite of Middle Proterozoic Era. The Pikes Peak Granite is comprised of light-gray to pink and reddish brown, coarse grained, porphyritic granite. The Pikes Peak Granite often produces grus (disaggregated loose mass of constituent minerals) when weathered. Resistant outcrops typically are round and bouldery. The principal minerals composing the Pikes Peak Granite are perthitic microcline, quartz, biotite and plagioclase (oligoclase).

The surficial deposits as observed during our site visit consist of residuum and colluvium generally composed of sands and gravels with varying amounts of silt and clay. Several large outcrops of boulders on the order of 12 to 20-foot diameter or greater were observed on the property, generally outside of the proposed building area. Evidence of natural rockfall or debris flow deposits were not observed in the vicinity of the building site.

The site is located in the vicinity of the Ute Pass Fault zone and an unnamed fault is mapped approximately 1/2 mile to the northeast of the site. The Ute Pass Fault is located approximately 3/4 of a mile to the west. According to information presented by the CGS (²Kirkham et al, 2004-2007), several earthquakes have occurred in the vicinity of the Ute Pass Fault near Colorado Springs and Woodland Park. The earthquakes, with magnitudes in the range of 3.0 to 3.9, occurred approximately from 1962 to 2007.

Subsurface Materials

Based on the review of the soils report referenced above, one test boring was performed on August 25, 2017. The test boring log was not included in the version of the report provided to RMG by personnel of Palace Homes. However, the laboratory testing indicated that the on-site soil is composed predominantly of sand.

BEARING OF GEOLOGIC FACTORS UPON PROPOSED DEVELOPMENT

General Geologic Considerations

Based upon our evaluation of the geologic conditions, it is our opinion that the proposed development is feasible. The geologic hazards identified are not considered unusual for mountainous regions of Colorado. Mitigation of geologic hazards is most effectively accomplished by avoidance. However,

http://geosurvey.state.co.us/Default.aspx?tabid=270

¹ Keller, John W., Siddoway, Christine, Morgan, Matthew L., Route, Erik E., Grizzell, Matthew T., Sacerdoti, Raffaello, and Stevenson, Adair, 2003 *Geologic Map of the Manitou Springs Quadrangle, El Paso and Teller Counties, Colorado*, Colorado Geological Survey, Open File Map 03-19.

² Kirkham, R. M., Rogers, W. P., Powell, L., Morgan, M. L., Matthews, V., and Pattyn, G. R., 2004-2007, *Colorado Earthquake Map Server*: Colorado Geological Survey Bulletin 52b.

where avoidance is not a practical or acceptable alternative, geologic hazards should be mitigated by implementing appropriate planning, engineering, and local construction practices.

Potentially Unstable Slopes

Downslope creep, which is the slow downslope movement of superficial soil and rock materials, is common to the area. However, the potential for relatively rapid downslope movement at the site is considered to be low. Nevertheless, the structural design of the residence should consider its placement on the hillside and the additional pressures that could be generated by downslope creep and by retaining upslope materials. Proper surface grading and positive drainage away from the structure will reduce (but not eliminate) the potential for downslope creep to impact the proposed residence. Any landscaping should utilize xeriscape techniques in order to minimize the amount of irrigation necessary to maintain landscaping. Further, stormwater and snowmelt runoff from parking areas should be directed towards drainage channels and away from potentially unstable slopes, both during construction activities and upon completion of site development.

Rockfall

The subject site does have a very steep slope to the south of the proposed build area. However, the rock and boulders on the surface of the slope were low lying and relatively "flat". The slope is not anticipated to generate rockfall. The subject property is not considered to be prone to rockfall.

Debris Flows and Debris Fans

Terrain features consistent in the formation of debris flows and debris fans are not present in the vicinity of the property.

Seismicity

The Pikes Peak Regional Building Code, 2017 Edition, indicates maximum considered earthquake spectral response accelerations of 0.193g for a short period (S_s) and 0.063g for a 1-second period (S₁). Specific recommendations should be provided by the Geotechnical Engineer of Record during the design phase of the project.

Surface Drainage and Erosion

The permeability of the sands and gravels at the site is generally considered to be high. Surface runoff could also be rapid and the potential for rapid erosion of unvegetated slopes could be high. Long-term slopes should not be steeper than 3:1 (horizontal:vertical) in both cut and fill areas. Revegetation of any disturbed areas should be performed as soon as possible with revegetation/erosion mats placed as required. Excavation cuts and soil disturbance should be kept to a minimum. Proper surface drainage, as recommended in a geotechnical engineering report should be provided and maintained by the Homeowner.

Radioactivity/Radon Gas

Based upon a Map of Radon Zones by the Colorado Department of Public Health and Environment (CDPHE) (Ref. 11), two zones of radon potential are indicated in Colorado, Zone 1 - High Radon Potential (probable indoor radon average >4 pCi/L) and Zone 2 -Moderate Radon Potential (probable indoor radon average 2-4 pCi/L). El Paso County is located within Zone 1.

Potential radon hazards are best mitigated at the building design and construction phases. Providing increased ventilation of basements, crawlspaces, creating slightly positive pressures within structures, and sealing of joints and cracks in the foundations and below-grade walls can help mitigate radon hazards.

CLOSING

This report has been prepared for the exclusive purpose of providing geologic hazards information and recommendations for development described in this report. RMG should be retained to review the final construction documents prior to construction to verify our findings, conclusions and recommendations have been appropriately implemented.

This report has been prepared for the exclusive use by the Client for application as an aid in the design and construction of the proposed development in accordance with generally accepted geotechnical and geological engineering practices. The analyses and recommendations in this report are based in part upon data obtained from site observations and the information presented in referenced reports. The nature and extent of variations may not become evident until construction. If variations then become evident, RMG should be retained to review the recommendations presented in this report considering the varied condition, and either verify or modify them in writing.

Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by geotechnical engineers practicing in this or similar localities. RMG does not warrant the work of regulatory agencies or other third parties supplying information which may have been used during the preparation of this report. No warranty, express or implied, is made by the preparation of this report. Third parties reviewing this report should draw their own conclusions regarding site conditions and specific construction techniques to be used on this project.

The scope of services for this project does not include, either specifically or by implication, environmental assessment of the site or identification of contaminated or hazardous materials or conditions. Development of recommendations for the mitigation of environmentally related conditions, including but not limited to biological or toxicological issues, are beyond the scope of this report. If the Client desires investigation into the potential for such contamination or conditions, other studies should be undertaken.

If we can be of further assistance in discussing the contents of this report or analysis of the proposed development, from a geotechnical engineering point-of-view, please feel free to contact us.

If we can be of further assistance in discussing the contents of this report or analysis of the proposed development, from a geotechnical engineering point-of-view, please feel free to contact our office.

Cordially, Reviewed by,

RMG – Rocky Mountain Group RMG – Rocky Mountain Group

li Zigler O Tony Munger, P.E.

Project Geologist Geotechnical Project Manager