JPS ENGINEERING
19 E. Willamette Ave.
Colorado Springs, CO 80903
(719)-477-9429
www.jpsengr.com

November 17, 2026

El Paso County Planning and Community Development Department
2880 International Circle
Colorado Springs, CO 80910

**SUBJECT: Clearway, Lot 5 (PPR-22-034)**
**Engineer's Certification Letter – Permanent Control Measures**

Ladies and Gentlemen:

Drainage Permanent Control Measures (PCM's) for this project include one private Sand Filter Detention Basin. The PCM(s) provide the required storage volume and meet the required release rates, storage areas, elevations, and outlet dimensions, as documented by the attached revised MHFD-Detention spreadsheet that shows the as-built conditions. The As-Built drawings accurately depict the installation of the PCM improvements and verify that adequate detention volume has been provided. According to the attached MHFD-Detention spreadsheet, the as-built Water Quality Capture Volume (WQCV) drain time has been calculated as 10 hours, which is less than 12 hours as originally designed.

Based upon information gathered from periodic site visits to the project, JPS Engineering, Inc. is of the opinion that the Permanent Control Measures have been constructed in general compliance with the approved design plans as filed with El Paso County.

The site and adjacent properties (as affected by work performed under the County permit) appear to be stable with respect to settlement and subsidence, sloughing of cut and fill slopes, revegetation or other ground cover, and the improvements (public improvements, common development improvements, site grading and paving) meet or exceed the minimum design requirements.

Sincerely,
**JPS Engineering, Inc.**





John P. Schwab, P.E.
Colorado P.E. No. 29891

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.06 (July 2022)*

**Project:** **Clearway - Lot 5**

**Basin ID:** **Pond 1 - As-Built**




**Example Zone Configuration (Retention Pond)**

NOTE: AS-BUILT TRIBUTARY BASINS ARE CONSISTENT WITH APPROVED FDR

Watershed Information

| | | |
|---|---|---|
| Selected BMP Type = | SF | |
| Watershed Area = | 2.15 | acres |
| Watershed Length = | 335 | ft |
| Watershed Length to Centroid = | 165 | ft |
| Watershed Slope = | 0.020 | ft/ft |
| Watershed Imperviousness = | 85.60% | percent |
| Percentage Hydrologic Soil Group A = | 100.0% | percent |
| Percentage Hydrologic Soil Group B = | 0.0% | percent |
| Percentage Hydrologic Soil Groups C/D = | 0.0% | percent |
| Target WQCV Drain Time = | 12.0 | hours |
| Location for 1-hr Rainfall Depths = | Denver - Capitol Building | |

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

| | | | Optional User Overrides | |
|---|---|---|---|---|
| Water Quality Capture Volume (WQCV) = | 0.053 | acre-feet | | acre-feet |
| Excess Urban Runoff Volume (EURV) = | 0.247 | acre-feet | | acre-feet |
| 2-yr Runoff Volume (P1 = 1.19 in.) = | 0.161 | acre-feet | 1.19 | inches |
| 5-yr Runoff Volume (P1 = 1.52 in.) = | 0.212 | acre-feet | 1.52 | inches |
| 10-yr Runoff Volume (P1 = 1.75 in.) = | 0.246 | acre-feet | 1.75 | inches |
| 25-yr Runoff Volume (P1 = 2 in.) = | 0.289 | acre-feet | 2.00 | inches |
| 50-yr Runoff Volume (P1 = 2.25 in.) = | 0.331 | acre-feet | 2.25 | inches |
| 100-yr Runoff Volume (P1 = 2.52 in.) = | 0.378 | acre-feet | 2.52 | inches |
| 500-yr Runoff Volume (P1 = 3.14 in.) = | 0.484 | acre-feet | | inches |
| Approximate 2-yr Detention Volume = | 0.162 | acre-feet | | |
| Approximate 5-yr Detention Volume = | 0.214 | acre-feet | | |
| Approximate 10-yr Detention Volume = | 0.251 | acre-feet | | |
| Approximate 25-yr Detention Volume = | 0.297 | acre-feet | | |
| Approximate 50-yr Detention Volume = | 0.323 | acre-feet | | |
| Approximate 100-yr Detention Volume = | 0.347 | acre-feet | | |

Define Zones and Basin Geometry

| | | |
|---|---|---|
| Zone 1 Volume (WQCV) = | 0.053 | acre-feet |
| Zone 2 Volume (EURV - Zone 1) = | 0.194 | acre-feet |
| Zone 3 Volume (100-year - Zones 1 & 2) = | 0.100 | acre-feet |
| Total Detention Basin Volume = | 0.347 | acre-feet |

Depth Increment = ft


| Stage - Storage Description | Stage (ft) | Optional Override Stage (ft) | Length (ft) | Width (ft) | Area ($ft^2$) | Optional Override Area ($ft^2$) | Area (acre) | Volume ($ft^3$) | Volume (ac-ft) |
|---|---|---|---|---|---|---|---|---|---|
| **Media Surface** | -- | 0.00 | -- | -- | -- | 2,300 | 0.053 | | |
| **EL=6252.0** | -- | 0.50 | -- | -- | -- | 3,583 | 0.082 | 1,471 | 0.034 |
| | -- | 1.50 | -- | -- | -- | 4,450 | 0.102 | 5,487 | 0.126 |
| **EL=6254.0** | -- | 2.50 | -- | -- | -- | 5,395 | 0.124 | 10,410 | 0.239 |
| **Berm EL=6256.0** | -- | 4.50 | -- | -- | -- | 7,700 | 0.177 | 23,505 | 0.540 |

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*

**Project:** **Clearway - Lot 5**

**Basin ID:** **Pond 1 - As-Built**




**Example Zone Configuration (Retention Pond)**

| | Estimated Stage (ft) | Estimated Volume (ac-ft) | Outlet Type |
|---|---|---|---|
| Zone 1 (WQCV) | 0.73 | 0.053 | Filtration Media |
| Zone 2 (EURV) | 2.57 | 0.194 | Rectangular Orifice |
| Zone 3 (100-year) | 3.31 | 0.100 | Weir&Pipe (Restrict) |
| Total (all zones) | | 0.347 | |

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

| | | | | | |
|---|---|---|---|---|---|
| Underdrain Orifice Invert Depth = | 3.32 | ft (distance below the filtration media surface) | Underdrain Orifice Area = | 0.0 | $ft^2$ |
| Underdrain Orifice Diameter = | 1.10 | inches | Underdrain Orifice Centroid = | 0.05 | feet |

Calculated Parameters for Underdrain

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

| | | | | | |
|---|---|---|---|---|---|
| Centroid of Lowest Orifice = | N/A | ft (relative to basin bottom at Stage = 0 ft) | WQ Orifice Area per Row = | N/A | $ft^2$ |
| Depth at top of Zone using Orifice Plate = | N/A | ft (relative to basin bottom at Stage = 0 ft) | Elliptical Half-Width = | N/A | feet |
| Orifice Plate: Orifice Vertical Spacing = | N/A | inches | Elliptical Slot Centroid = | N/A | feet |
| Orifice Plate: Orifice Area per Row = | N/A | sq. inches | Elliptical Slot Area = | N/A | $ft^2$ |

Calculated Parameters for Plate

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

| | Row 1 (optional) | Row 2 (optional) | Row 3 (optional) | Row 4 (optional) | Row 5 (optional) | Row 6 (optional) | Row 7 (optional) | Row 8 (optional) |
|---|---|---|---|---|---|---|---|---|
| Stage of Orifice Centroid (ft) | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Orifice Area (sq. inches) | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |

| | Row 9 (optional) | Row 10 (optional) | Row 11 (optional) | Row 12 (optional) | Row 13 (optional) | Row 14 (optional) | Row 15 (optional) | Row 16 (optional) |
|---|---|---|---|---|---|---|---|---|
| Stage of Orifice Centroid (ft) | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Orifice Area (sq. inches) | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |

User Input: Vertical Orifice (Circular or Rectangular)

| | Zone 2 Rectangular | Not Selected | | | Zone 2 Rectangular | Not Selected | |
|---|---|---|---|---|---|---|---|
| Invert of Vertical Orifice = | 0.80 | N/A | ft (relative to basin bottom at Stage = 0 ft) | Vertical Orifice Area = | 0.03 | N/A | $ft^2$ |
| Depth at top of Zone using Vertical Orifice = | 2.57 | N/A | ft (relative to basin bottom at Stage = 0 ft) | Vertical Orifice Centroid = | 0.08 | N/A | feet |
| Vertical Orifice Height = | 2.00 | N/A | inches | | | | |
| Vertical Orifice Width = | 2.50 | | inches | | | | |

Calculated Parameters for Vertical Orifice

User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

| | Zone 3 Weir | Not Selected | | | Zone 3 Weir | Not Selected | |
|---|---|---|---|---|---|---|---|
| Overflow Weir Front Edge Height, Ho = | 2.36 | N/A | ft (relative to basin bottom at Stage = 0 ft) | Height of Grate Upper Edge, $H_t$ = | 2.36 | N/A | feet |
| Overflow Weir Front Edge Length = | 2.91 | N/A | feet | Overflow Weir Slope Length = | 2.91 | N/A | feet |
| Overflow Weir Grate Slope = | 0.00 | N/A | H:V | Grate Open Area / 100-yr Orifice Area = | 47.82 | N/A | |
| Horiz. Length of Weir Sides = | 2.91 | N/A | feet | Overflow Grate Open Area w/o Debris = | 6.70 | N/A | $ft^2$ |
| Overflow Grate Type = | Close Mesh Grate | N/A | | Overflow Grate Open Area w/ Debris = | 3.35 | N/A | $ft^2$ |
| Debris Clogging % = | 50% | N/A | % | | | | |

Calculated Parameters for Overflow Weir

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

| | Zone 3 Restrictor | Not Selected | | | Zone 3 Restrictor | Not Selected | |
|---|---|---|---|---|---|---|---|
| Depth to Invert of Outlet Pipe = | 3.46 | N/A | ft (distance below basin bottom at Stage = 0 ft) | Outlet Orifice Area = | 0.14 | N/A | $ft^2$ |
| Outlet Pipe Diameter = | 18.00 | N/A | inches | Outlet Orifice Centroid = | 0.12 | N/A | feet |
| Restrictor Plate Height Above Pipe Invert = | 2.40 | | inches | Half-Central Angle of Restrictor Plate on Pipe = | 0.75 | N/A | radians |

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

User Input: Emergency Spillway (Rectangular or Trapezoidal)

| | | | | |
|---|---|---|---|---|
| Spillway Invert Stage= | 3.15 | ft (relative to basin bottom at Stage = 0 ft) | Spillway Design Flow Depth= | 0.23 feet |
| Spillway Crest Length = | 22.00 | feet | Stage at Top of Freeboard = | 4.38 feet |
| Spillway End Slopes = | 4.00 | H:V | Basin Area at Top of Freeboard = | 0.17 acres |
| Freeboard above Max Water Surface = | 1.00 | feet | Basin Volume at Top of Freeboard = | 0.52 acre-ft |

Calculated Parameters for Spillway


Routed Hydrograph Results


*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).*


| Design Storm Return Period = | WQCV | EURV | 2 Year | 5 Year | 10 Year | 25 Year | 50 Year | 100 Year | 500 Year |
|---|---|---|---|---|---|---|---|---|---|
| One-Hour Rainfall Depth (in) = | N/A | N/A | 1.19 | 1.52 | 1.75 | 2.00 | 2.25 | 2.52 | 3.14 |
| CUHP Runoff Volume (acre-ft) = | 0.053 | 0.247 | 0.161 | 0.212 | 0.246 | 0.289 | 0.331 | 0.378 | 0.484 |
| Inflow Hydrograph Volume (acre-ft) = | N/A | N/A | 0.161 | 0.212 | 0.246 | 0.289 | 0.331 | 0.378 | 0.484 |
| CUHP Predevelopment Peak Q (cfs) = | N/A | N/A | 0.0 | 0.0 | 0.1 | 0.5 | 1.0 | 1.6 | 2.9 |
| OPTIONAL Override Predevelopment Peak Q (cfs) = | N/A | N/A | | | | | | | |
| Predevelopment Unit Peak Flow, q (cfs/acre) = | N/A | N/A | 0.01 | 0.02 | 0.03 | 0.24 | 0.46 | 0.75 | 1.33 |
| Peak Inflow Q (cfs) = | N/A | N/A | 3.4 | 4.5 | 5.2 | 6.3 | 7.2 | 8.0 | 10.3 |
| Peak Outflow Q (cfs) = | 0.1 | 1.5 | 0.2 | 0.2 | 0.3 | 0.7 | 1.3 | 1.7 | 2.5 |
| Ratio Peak Outflow to Predevelopment Q = | N/A | N/A | N/A | 5.8 | 4.8 | 1.3 | 1.4 | 1.0 | 0.9 |
| Structure Controlling Flow = | Filtration Media | Outlet Plate 1 | Vertical Orifice 1 | Vertical Orifice 1 | Vertical Orifice 1 | Overflow Weir 1 | Overflow Weir 1 | Outlet Plate 1 | Spillway |
| Max Velocity through Grate 1 (fps) = | N/A | 0.20 | N/A | N/A | N/A | 0.1 | 0.2 | 0.2 | 0.2 |
| Max Velocity through Grate 2 (fps) = | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Time to Drain 97% of Inflow Volume (hours) = | 10 | 22 | 20 | 22 | 23 | 23 | 23 | 23 | 22 |
| Time to Drain 99% of Inflow Volume (hours) = | **10** | 23 | 20 | 23 | 24 | 25 | 24 | 24 | 24 |
| Maximum Ponding Depth (ft) = | 0.73 | 2.57 | 1.58 | 1.99 | 2.26 | 2.44 | 2.50 | 2.70 | 3.20 |
| Area at Maximum Ponding Depth (acres) = | 0.09 | 0.13 | 0.10 | 0.11 | 0.12 | 0.12 | 0.12 | 0.13 | 0.14 |
| Maximum Volume Stored (acre-ft) = | 0.053 | 0.248 | 0.134 | 0.179 | 0.210 | 0.230 | 0.239 | 0.264 | 0.331 |

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*




| S-A-V-D Chart Axis Override | X-axis | Left Y-Axis | Right Y-Axis |
|---|---|---|---|
| minimum bound | | | |
| maximum bound | | | |

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*Outflow Hydrograph Workbook Filename:*

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

| | SOURCE | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP | CUHP |
|---|---|---|---|---|---|---|---|---|---|---|
| Time Interval | TIME | WQCV [cfs] | EURV [cfs] | 2 Year [cfs] | 5 Year [cfs] | 10 Year [cfs] | 25 Year [cfs] | 50 Year [cfs] | 100 Year [cfs] | 500 Year [cfs] |
| 5.00 min | 0:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.06 | 0.01 | 0.20 |
| | 0:15:00 | 0.00 | 0.00 | 0.56 | 0.93 | 1.12 | 0.75 | 0.92 | 0.91 | 1.25 |
| | 0:20:00 | 0.00 | 0.00 | 1.81 | 2.35 | 2.70 | 1.68 | 1.94 | 2.10 | 2.69 |
| | 0:25:00 | 0.00 | 0.00 | 3.41 | 4.49 | 5.23 | 3.34 | 3.84 | 4.09 | 5.24 |
| | 0:30:00 | 0.00 | 0.00 | 3.35 | 4.25 | 4.79 | 6.27 | 7.20 | 8.02 | 10.28 |
| | 0:35:00 | 0.00 | 0.00 | 2.58 | 3.23 | 3.63 | 5.74 | 6.57 | 7.85 | 10.01 |
| | 0:40:00 | 0.00 | 0.00 | 1.99 | 2.42 | 2.72 | 4.74 | 5.43 | 6.39 | 8.15 |
| | 0:45:00 | 0.00 | 0.00 | 1.43 | 1.83 | 2.09 | 3.55 | 4.06 | 5.02 | 6.42 |
| | 0:50:00 | 0.00 | 0.00 | 1.05 | 1.42 | 1.56 | 2.87 | 3.28 | 3.95 | 5.06 |
| | 0:55:00 | 0.00 | 0.00 | 0.80 | 1.06 | 1.21 | 2.06 | 2.35 | 3.00 | 3.83 |
| | 1:00:00 | 0.00 | 0.00 | 0.69 | 0.91 | 1.08 | 1.54 | 1.76 | 2.35 | 3.00 |
| | 1:05:00 | 0.00 | 0.00 | 0.66 | 0.86 | 1.04 | 1.32 | 1.50 | 2.08 | 2.66 |
| | 1:10:00 | 0.00 | 0.00 | 0.56 | 0.84 | 1.02 | 1.10 | 1.25 | 1.54 | 1.97 |
| | 1:15:00 | 0.00 | 0.00 | 0.50 | 0.77 | 1.02 | 0.99 | 1.12 | 1.25 | 1.59 |
| | 1:20:00 | 0.00 | 0.00 | 0.47 | 0.70 | 0.92 | 0.83 | 0.94 | 0.93 | 1.17 |
| | 1:25:00 | 0.00 | 0.00 | 0.45 | 0.66 | 0.79 | 0.75 | 0.85 | 0.75 | 0.95 |
| | 1:30:00 | 0.00 | 0.00 | 0.44 | 0.63 | 0.70 | 0.64 | 0.72 | 0.64 | 0.80 |
| | 1:35:00 | 0.00 | 0.00 | 0.43 | 0.62 | 0.66 | 0.57 | 0.65 | 0.58 | 0.72 |
| | 1:40:00 | 0.00 | 0.00 | 0.43 | 0.53 | 0.63 | 0.54 | 0.61 | 0.56 | 0.70 |
| | 1:45:00 | 0.00 | 0.00 | 0.43 | 0.48 | 0.61 | 0.52 | 0.59 | 0.55 | 0.69 |
| | 1:50:00 | 0.00 | 0.00 | 0.43 | 0.45 | 0.61 | 0.51 | 0.58 | 0.55 | 0.69 |
| | 1:55:00 | 0.00 | 0.00 | 0.34 | 0.43 | 0.58 | 0.51 | 0.57 | 0.55 | 0.69 |
| | 2:00:00 | 0.00 | 0.00 | 0.29 | 0.40 | 0.51 | 0.51 | 0.57 | 0.55 | 0.69 |
| | 2:05:00 | 0.00 | 0.00 | 0.16 | 0.22 | 0.29 | 0.29 | 0.33 | 0.31 | 0.39 |
| | 2:10:00 | 0.00 | 0.00 | 0.09 | 0.13 | 0.16 | 0.16 | 0.19 | 0.18 | 0.22 |
| | 2:15:00 | 0.00 | 0.00 | 0.04 | 0.07 | 0.08 | 0.09 | 0.10 | 0.09 | 0.12 |
| | 2:20:00 | 0.00 | 0.00 | 0.02 | 0.03 | 0.04 | 0.04 | 0.05 | 0.05 | 0.06 |
| | 2:25:00 | 0.00 | 0.00 | 0.01 | 0.01 | 0.01 | 0.01 | 0.02 | 0.02 | 0.02 |
| | 2:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 2:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 2:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 2:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 2:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 2:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 3:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 4:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:05:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:10:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:15:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:20:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:25:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:30:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:35:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:40:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:45:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:50:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 5:55:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 6:00:00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |