

VILLAGES AT STERLING RANCH


COUNTY OF EL PASO, STATE OF COLORADO SECT. 34, TOWNSHIP 12S, RANGE 65 WEST

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN

VILLAGES AT STERLING RANCH DEVELOPMENT GUIDELINES:

A. PERMITTED USES AND STRUCTURES:

USE	NOTES
PRINCIPAL USES	
DWELLINGS: SINGLE FAMILY ATTACHED (DUPEX PRODUCT) WITH ATTACHED 1-CAR OR 2-CAR GARAGE (LOTS 1-54)	SEE "SETBACKS" BELOW AND ON SHEET 3 DEVELOPMENT STANDARDS DETAIL SHEET
SINGLE FAMILY DETACHED WITH OPTIONAL INTEGRAL ACCESSORY DWELLING UNIT (ADU) ABOVE ATTACHED GARAGE. ADU OPTION ONLY FOR (LOTS 55-92) MAX. ADU SIZE = 700 SF	
SINGLE FAMILY DETACHED (PREAMBLE PRODUCT) WITH OPTIONAL ATTACHED OR DETACHED GARAGE OR NO GARAGE W/TWO PARKING STALLS (LOTS 93-227)	
ACCESSORY USES	
OPEN SPACE, PARKS AND TRAILS RECREATION AMENITIES	SUCH AS TRAILS, WALKS THROUGHOUT OPEN SPACE
FAMILY CARE HOME, CHILD CARE CENTER, OR GROUP HOME	THESE USES ARE CONTROLLED BY STATE LAW AND RULES AND REGULATIONS, AND ARE EITHER ALLOWED OR SPECIAL USES DEPENDING ON THE SPECIFIC FACILITY TYPE AND NUMBER OF RESIDENTS / ENROLLMENTS.
DISTRICT UTILITIES / DETENTION FACILITIES	TO INCLUDE DETENTION FACILITIES AND ASSOCIATED ACCESS ROADS AND UTILITY LINES.
ATTACHED GARAGES	LOTS 1-92 WILL INCL. 1-CAR OR 2-CAR GARAGES LOTS 93-227 MAY INCL. 2-CAR GARAGES (ATT.)
DETACHED GARAGES	LOTS 93-227 MAY INCL. 2-CAR GARAGES (DET.)
NO GARAGE	LOTS 93-227 OPTIONAL NO GARAGE WILL INCL. 2 PARKING STALLS ON THE LOT (18' MIN. DEPTH)



VICINITY MAP
N.T.S.

PARKING REQUIREMENTS:

2 STALLS PER SINGLE FAMILY DETACHED UNIT (LOTS 55-227)	173 X 2 = 346	TOTAL = 474
2 STALLS PER SINGLE FAMILY ATTACHED UNIT (LOTS 1-54)	54 X 2 = 108	PARKING SPACES
1 GUEST STALL PER 4 SINGLE FAMILY ATTACHED UNITS (LOTS 1-54)	54 / 4 = 14	
171 OFF-STREET SPACES INCL. 6 DISABLED PARKING SPACES REQ.	6	

PARKING PROVIDED: *(NOTE: TANDEM PARKING DOES NOT COUNT TOWARDS PARKING TOTAL)

DUPEX ATTACHED PRODUCT (LOTS 1-54)			
1-CAR GARAGE AND 18' MIN. DRIVEWAY (*1 SPACE)	54 X 1 = 54	PARKING RANGE =	
OPTIONAL 2-CAR GARAGE AND 18' MIN. DRIVEWAY (*2 SPACES)	54 X 2 = 108	65-119	
11 OFF-STREET PARKING STALLS ALSO PROVIDED		PARKING SPACES	
SINGLE FAMILY DETACHED W/ADU OPTION (LOTS 55-92)			
2-CAR GARAGE AND 18' MIN. DRIVEWAY (*2 SPACES)	38 X 2 = 76	PARKING RANGE =	
OPTIONAL ADU INCL. EXTRA SPACE ON DRIVEWAY (3 SPACES)	38 X 3 = 114	137-175	
61 OFF-STREET PARKING STALLS (INCL. 2 DISABLED SPACES)		PARKING SPACES	
SINGLE FAMILY DETACHED (PREAMBLE) (LOTS 93-227)			
2-CAR ATTACHED GARAGE AND 18' MIN. DRIVEWAY (*2 SPACES)	135 X 2 = 270	PARKING =	
NO GARAGE BUT TWO 18' MIN. PARKING STALLS (2 SPACES)	135 X 2 = 270	369	
2-CAR DETACHED GARAGE BUT NO DRIVEWAY (2 SPACES)	135 X 2 = 270	PARKING SPACES	
99 OFF-STREET PARKING STALLS (INCL. 4 DISABLED SPACES)			
TOTAL PARKING RANGE PROVIDED BASED ON PRODUCT OPTIONS (INCL. 6 DISABLED SPACES PER CODE REQ.)	571-663	PARKING SPACES	

PUD MODIFICATION TABLE (AS ALLOWED BY LDC SECTION 4.2.6.(F)(2)(g))

LDC/ECM SECTION	CATEGORY	STANDARD	MODIFICATION	JUSTIFICATION
1 LDC CHAPTER 8.4.4.(E)(2)	PRIVATE ROADS REQUIRE WAIVER	USE OF PRIVATE ROADS SHALL BE LIMITED.	PRIVATE ROADS PROPOSED TO SERVE ONLY PORTIONS OF THIS COMMUNITY	PRIVATE ROADS PROVIDE MORE FLEXIBILITY FOR THE DEVELOPMENT TO ACCOMMODATE THE UNIQUE COMMUNITY HOMES AND MULTIPLE PRODUCT LINES PROPOSED ON THE SITE.
2 LDC CHAPTER 8.4.4.(E)(3)	PRIVATE ROADS TO MEET COUNTY STANDARDS	PRIVATE ROADS SHALL BE CONSTRUCTED AND MAINTAINED TO ECM STANDARDS	ROAD WIDTH AND ROADWAY TERMINATIONS (SEE 3 AND 4 BELOW)	MANY OF THE HOMES FRONT OPEN SPACE TRACTS WITH REAR GARAGE ACCESS FROM THE PRIVATE ROADS. THIS DESIGN ALLOWS FOR A MORE EFFICIENT PEDESTRIAN SYSTEM WITHIN ADDITIONAL OPEN SPACE PROVIDED.
3 8.4.4.C PUBLIC ROADS REQ. LDC CHAPTER	LOT AREA AND DIMENSIONS	LOTS TO HAVE FRONTAGE ON AND ACCESS FROM A PUBLIC ROAD	LOTS UTILIZING PRIVATE SHARED DRIVEWAYS WILL NOT HAVE DIRECT FRONTAGE ON OR ACCESS FROM A PUBLIC ROAD. HOWEVER, LOTS WILL HAVE DIRECT ACCESS FROM PRIVATE ROADS (TRACTS) THAT THEN CONNECT DIRECTLY TO A PUBLIC ROAD.	THE PROPOSED MODIFICATIONS ARE GRANTED IN EXCHANGE FOR THE ADDITIONAL OPEN SPACE/AMENITY DESIGN PROVIDED IN THIS PUD DEVELOPMENT PLAN.

LEGAL DESCRIPTION

A PARCEL OF LAND LOCATED IN THE WEST HALF OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS WITH REFERENCES TO RECORDED DOCUMENTS BEING THOSE CERTAIN DOCUMENTS RECORDED IN THE OFFICE OF THE EL PASO COUNTY CLERK AND RECORDER'S OFFICE AND WITH BEARINGS REFERENCED TO THE EASTERLY RIGHT OF WAY LINE OF STERLING RANCH ROAD AS DEDICATED IN HOMESTEAD NORTH AT STERLING RANCH FILING NO. 1 RECORDED ON MAY 19, 2023 UNDER RECEPTION NO. 223715150, BEING MONUMENTED AT BOTH ENDS BY NO.5 REBAR WITH 1-1/2" ALUMINUM SURVEYORS CAP STAMPED "JR ENG LS 38252" ASSUMED TO BEAR N13°28'38"E, A DISTANCE OF 1168.84 FEET.

BEGINNING AT THE NORTHEASTERLY CORNER OF SAID STERLING RANCH ROAD ALSO BEING THE NORTHEAST END OF THE ABOVE DESCRIBED BEARING REFERENCE;

THENCE ON THE EASTERLY RIGHT OF WAY LINE OF SAID STERLING RANCH ROAD THE FOLLOWING THREE (3) COURSES:

1. THENCE N58°28'29"E, A DISTANCE OF 49.50 FEET;
2. THENCE S76°31'31"E, A DISTANCE OF 10.00 FEET;
3. THENCE N13°28'38"E, A DISTANCE OF 130.00 FEET;

- THENCE S76°31'31"E, A DISTANCE OF 1,424.76 FEET;
- THENCE S13°28'29"W, A DISTANCE OF 440.00 FEET;
- THENCE S76°31'31"E, A DISTANCE OF 66.21 FEET;
- THENCE S13°28'29"W, A DISTANCE OF 690.84 FEET;

THENCE N76°31'31"W, A DISTANCE OF 1,535.98 FEET TO A POINT ON SAID EASTERLY RIGHT OF WAY LINE;

THENCE N13°28'29"E, ON SAID EASTERLY RIGHT OF WAY LINE, A DISTANCE OF 965.84 FEET TO THE POINT OF BEGINNING.

THE ABOVE DESCRIPTION PRODUCES A CALCULATED AREA OF 1,701,352 SQUARE FEET (39.058 ACRES).

SHEET INDEX

COVER SHEET	SHEET 1	OF 29
PUD & PRELIMINARY PLAN	SHEETS 2-9	OF 29
PRELIMINARY GRADING & UTILITIES PLAN	SHEETS 10-17	OF 29
LANDSCAPE TITLE SHEET	SHEET 18	OF 29
LANDSCAPE PLAN - OVERALL	SHEET 19	OF 29
LANDSCAPE PLAN	SHEETS 20-28	OF 29
DETAILS	SHEET 29	OF 29

GENERAL PROVISIONS SECTION:

- A. AUTHORITY: THIS PUD IS AUTHORIZED BY CHAPTER 4 OF THE EL PASO COUNTY LAND DEVELOPMENT CODE, ADOPTED PURSUANT TO THE COLORADO PLANNED UNIT DEVELOPMENT ACT OF 1972, AS AMENDED.
- B. APPLICABILITY: THE PROVISIONS OF THIS PUD SHALL RUN WITH THE LAND. THE LANDOWNERS, THEIR SUCCESSORS, HEIRS, OR ASSIGNS SHALL BE BOUND BY THIS DEVELOPMENT PLAN, AS AMENDED AND APPROVED BY THE PLANNING AND COMMUNITY DEVELOPMENT DEPARTMENT DIRECTOR OR BOARD OF COUNTY COMMISSIONERS.
- C. ADOPTION: THE ADOPTION OF THIS DEVELOPMENT PLAN SHALL EVIDENCE THE FINDINGS AND DECISIONS OF THE EL PASO COUNTY BOARD OF COUNTY COMMISSIONERS THAT THIS DEVELOPMENT PLAN FOR VILLAGES AT STERLING RANCH IS IN GENERAL CONFORMITY WITH THE EL PASO COUNTY MASTER PLAN, EL PASO COUNTY POLICY PLAN AND APPLICABLE SMALL AREA PLAN; IS AUTHORIZED UNDER THE PROVISIONS OF THE EL PASO COUNTY LAND DEVELOPMENT CODE; AND THAT THE EL PASO COUNTY LAND DEVELOPMENT CODE AND THIS DEVELOPMENT PLAN COMPLIES WITH THE COLORADO PLANNED UNIT DEVELOPMENT ACT OF 1972, AS AMENDED.
- D. RELATIONSHIP TO COUNTY REGULATIONS: THE PROVISIONS OF THIS DEVELOPMENT PLAN SHALL PREVAIL AND GOVERN THE DEVELOPMENT OF VILLAGES AT STERLING RANCH, PROVIDED HOWEVER, THAT WHERE THE PROVISIONS OF THIS DEVELOPMENT PLAN DO NOT ADDRESS A PARTICULAR SUBJECT, THE RELEVANT PROVISIONS OF THE EL PASO COUNTY LAND DEVELOPMENT CODE IN EFFECT AT THE TIME OF THE PUD PLAN APPROVAL (OR OWNER ACKNOWLEDGE THE PUD CHANGES WITH THE CODE), OR ANY OTHER APPLICABLE RESOLUTIONS OR REGULATIONS OF THE PASO COUNTY, SHALL BE APPLICABLE.
- E. ENFORCEMENT: TO FURTHER THE MUTUAL INTEREST OF THE RESIDENTS, OCCUPANTS, AND OWNERS OF THE PUD AND OF THE PUBLIC IN THE PRESERVATION OF THE INTEGRITY OF THIS DEVELOPMENT PLAN, THE PROVISIONS OF THIS PLAN RELATING TO THE USE OF LAND AND THE LOCATION OF COMMON OPEN SPACE SHALL RUN IN FAVOR OF EL PASO COUNTY AND SHALL BE ENFORCEABLE AT LAW OR IN EQUITY BY THE COUNTY WITHOUT LIMITATIONS ON ANY POWER OR REGULATION OTHERWISE GRANTED BY LAW.
- F. CONFLICT: WHERE THERE IS MORE THAN ONE PROVISION WITHIN THE DEVELOPMENT PLAN THAT COVERS THE SAME SUBJECT MATTER, THE PROVISION WHICH IS MOST RESTRICTIVE OR IMPOSES HIGHER STANDARDS OR REQUIREMENTS SHALL GOVERN.
- G. MAXIMUM LEVEL OF DEVELOPMENT: THE TOTAL OF DWELLINGS IS THE MAXIMUM DEVELOPMENT REQUESTED FOR PLATTING OR CONSTRUCTION (PLUS ANY APPROVED DENSITY TRANSFER). THE ACTUAL NUMBER OF DWELLINGS OR LEVEL OF DEVELOPMENT MAY BE LESS DUE TO SUBDIVISION OF SITE DEVELOPMENT PLAN REQUIREMENTS, LAND CARRYING CAPACITY, OR OTHER REQUIREMENTS OF THE BOARD OF COUNTY COMMISSIONERS.
- H. PROJECT TRACKING: AT THE TIME OF ANY FINAL PLAT APPLICATION, THE APPLICANT SHALL PROVIDE A SUMMARY OF THE DEVELOPMENT TO DATE, TO PLANNING AND COMMUNITY DEVELOPMENT DEPARTMENT, IN ORDER TO ASSURE MAXIMUM DEVELOPMENT LIMITS ARE NOT EXCEEDED.
- I. OVERALL PROJECT STANDARDS: THE STANDARD ZONING REQUIREMENTS OF EL PASO COUNTY LAND DEVELOPMENT CODE, AS AMENDED, INCLUDING OFF-STREET PARKING, LANDSCAPING, SITE DEVELOPMENT, ACCESSORY AND TEMPORARY USES, AND USE BY SPECIAL REVIEW AND VARIANCE PROCESSES SHALL APPLY TO THIS PUD, EXCEPT AS MODIFIED HEREIN.

PURPOSE AND INTENT:

THE VILLAGES AT STERLING RANCH PUD DEVELOPMENT PLAN AND PRELIMINARY PLAN IS A PROPOSED 227 LOT SINGLE-FAMILY RESIDENTIAL COMMUNITY COMPRISED OF THREE DISTINCT RESIDENTIAL PRODUCTS UTILIZING BOTH PUBLIC AND PRIVATE ROADS TO ACCESS BOTH FRONT AND REAR LOADED HOMES.

GENERAL NOTES:

1. PUBLIC UTILITY/DRAINAGE EASEMENTS SHALL BE PROVIDED ON ALL LOTS AS FOLLOWS:
 - a. FRONT: FIVE (5) FEET ALONG PUBLIC ROW WITH TEN (10) FEET PUBLIC UTILITY
 - b. SIDE: FIVE (5) FEET PER TYPICAL LOTS DETAILS (SEE DEV. STANDARD DETAILS SHEET 3) / OR ZERO (0) FEET ON COMMON LOT LINE ONLY (DUPEX PRODUCT - LOTS 1-54)
 - c. REAR: FIVE (5) FEET
2. ALL OPEN SPACE/LANDSCAPE TRACTS, SIDEWALKS AND RETAINING WALLS SHALL BE OWNED AND MAINTAINED BY THE STERLING RANCH METROPOLITAN DISTRICT.
3. DEVELOPMENT OF THE PROPERTY SHALL BE IN ACCORDANCE WITH THE APPROVED PUD DEVELOPMENT PLAN AND SHALL BE LIMITED TO A TOTAL OF FIFTY FOUR (54) SINGLE FAMILY ATTACHED DUPEX UNITS (LOTS 1-54), THIRTY EIGHT (38) SINGLE FAMILY DETACHED UNITS WITH OPTIONAL ADU (LOTS 55-92) AND ON HUNDRED THIRTY FIVE (135) SINGLE FAMILY DETACHED UNITS WITH NO OPTIONAL ADU (LOTS 93-227).
4. THE PLANNING AND COMMUNITY DEVELOPMENT DIRECTOR SHALL HAVE THE ABILITY TO GRANT AN ADMINISTRATIVE VARIANCE OF UP TO 20% OF DIMENSIONAL STANDARD LISTED ON THIS PUD DEVELOPMENT PLAN ON A CASE BY CASE BASIS.
5. FLOODPLAIN STATEMENT: NO PORTION OF THE SITE IS WITHIN A FEMA FLOODPLAIN PER MAP NO. 08041C0533G, DATED DECEMBER 7, 2018.
6. SIGHT DISTANCE TRIANGLE EASEMENTS ARE IDENTIFIED ON THESE PLANS.
7. GEOLOGIC HAZARD NOTE: THE FOLLOWING LOTS HAVE BEEN FOUND TO BE IMPACTED BY GEOLOGIC HAZARDS. MITIGATION MEASURES AND A MAP OF THE HAZARD AREA CAN BE FOUND IN THE REPORT "SOIL, GEOLOGY, AND GEOLOGIC HAZARD STUDY" VILLAGES AT STERLING RANCH PRELIMINARY PLAN PARCEL NO. 14, 15, 20, & 21" BY ENTER ENGINEERING INC. DATED APRIL 13, 2022 IN FILE PUDSP226 AVAILABLE AT THE EL PASO COUNTY PLANNING AND COMMUNITY DEVELOPMENT DEPARTMENT:
 - POTENTIALLY SEASONAL SHALLOW GROUNDWATER AND EROSION (LOTS 208-210)
 - POTENTIALLY UNSTABLE SLOPE (LOTS 43-54, 64, 73-77)
 - HYDROCOMPACTION (LOTS 2-11, 15-34, 43-64, 73-92)
8. SNOW STORAGE SHALL BE ACCOMMODATED ONSITE IN AVAILABLE TRACTS AND AT DEAD ENDS OF THE PRIVATE DRIVE ROADWAYS, NOT IN THE PUBLIC RIGHT-OF-WAY.
9. ADA COMPLIANCE: APPROVAL OF THE PLAN AND ASSOCIATED CONSTRUCTION DOCUMENTS BY EL PASO COUNTY DOES NOT ASSURE COMPLIANCE WITH THE ADA OR ANY REGULATIONS OR GUIDELINES ENACTED OR PROMULGATED UNDER OR WITH RESPECT TO SUCH LAWS. IT IS THE RESPONSIBILITY OF THE DEVELOPER / HOME BUILDER TO ENSURE ADA ACCESSIBILITY DURING CONSTRUCTION OF THE PUBLIC AND PRIVATE SIDEWALKS. THE SUBDIVIDER/DEVELOPER HAS FAMILIARIZED ITSELF WITH CURRENT AMERICANS WITH DISABILITIES ACT (ADA) LAWS AND ACCESSIBILITY STANDARDS AND HAS LAID OUT THE PLAN AND ASSOCIATED GRADING AND CONSTRUCTION PLANS TO THAT ALL SITE ELEMENTS MEET THE APPLICABLE ADA DESIGN STANDARDS AS PUBLISHED BY THE UNITED STATES DEPARTMENT OF JUSTICE. APPROVAL OF THIS PLAN AND ASSOCIATED CONSTRUCTION DOCUMENTS BY EL PASO COUNTY DOES NOT ASSURE COMPLIANCE WITH THE ADA OR ANY REGULATIONS OR GUIDELINES ENACTED OR PROMULGATED UNDER OR WITH RESPECT TO SUCH LAWS. IT IS THE RESPONSIBILITY OF THE DEVELOPER / HOME BUILDER TO ENSURE ADA ACCESSIBILITY DURING CONSTRUCTION OF THE PRIVATE STREETS.
10. NO LANDSCAPING SHALL OBSTRUCT SIGHT DISTANCE TRIANGLES OR PEDESTRIAN FACILITIES PER ENGINEERING CRITERIA MANUAL. REFERENCE: 2.3.6.6.2 & 2.5.3.4 RESPECTIVELY. THE MINIMUM HORIZONTAL CLEARANCE FOR SIDEWALKS AROUND UTILITY STRUCTURES, FURNITURE AND OTHER ENCROACHMENTS SHALL BE 4 FEET OR GREATER TO PROVIDE SAFE CONDITIONS FOR PEDESTRIAN AND BICYCLISTS PER THE ENGINEERING CRITERIA MANUAL.
11. SPECIAL DISTRICT DISCLOSURE: A TITLE 32 SPECIAL DISTRICT ANNUAL REPORT AND DISCLOSURE FORM SATISFACTORY TO THE PLANNING AND COMMUNITY DEVELOPMENT DEPARTMENT SHALL BE RECORDED WITH EACH PLAT.
STERLING RANCH METROPOLITAN DISTRICT NOTE:
NOTICE: THIS PROPERTY WILL BE INCLUDED WITHIN A SPECIAL TAXING DISTRICT, STERLING RANCH METROPOLITAN DISTRICT, CREATED FOR THE PURPOSE OF CONSTRUCTING AND MAINTAINING CERTAIN DRAINAGE, UTILITY, ROADWAY AND PARK AND RECREATION IMPROVEMENTS. SPECIAL TAXING DISTRICTS ARE SUBJECT TO A GENERAL OBLIGATION INDEBTEDNESS THAT IS PAID BY REVENUES PRODUCED FROM ANNUAL TAX LEVIES ON THE TAXABLE PROPERTY WITHIN SUCH DISTRICTS. THE BUYER SHOULD FAMILIARIZE HIMSELF / HERSELF WITH THIS POTENTIALITY AND RAMIFICATIONS THEREOF.
12. THE SUBDIVIDER(S) AGREES ON BEHALF OF HIM/HERSELF AND ANY DEVELOPER OR BUILDER SUCCESSORS AND ASSIGNEES THAT SUBDIVIDER AND/OR SAID SUCCESSORS AND ASSIGNS SHALL BE REQUIRED TO PAY TRAFFIC IMPACT FEES IN ACCORDANCE WITH THE EL PASO COUNTY ROAD IMPACT FEE PROGRAM RESOLUTION (RESOLUTION NO. 19-471), OR ANY AMENDMENTS THERETO, AT OR PRIOR TO THE TIME OF BUILDING PERMIT SUBMITTALS. THE FEE OBLIGATION, IF NOT PAID AT FINAL PLAT RECORDING, SHALL BE DOCUMENTED ON ALL SALES DOCUMENTS AND ON PLAT NOTES TO ENSURE THAT A TITLE SEARCH WOULD FIND THE FEE OBLIGATION BEFORE SALE OF THE PROPERTY.
13. AS NOTED IN THIS PUD DEVELOPMENT PLAN & PRELIMINARY PLAN, SOME LOTS WILL INCLUDE A 5' USE EASEMENT FOR EACH UNIT AT THE PATIO SIDE OR SIDE HOUSE ACCESS OF THE TENANT. HOWEVER, PATIOS MAY NOT ENDOURCH INTO THE 5' SIDE YARD SETBACK/EASEMENT. ADDITIONALLY, EACH UNIT WILL BE SUBJECT TO A 5' MAINTENANCE ACCESS FOR THE BENEFIT OF AN ADJOINING UNIT. END UNITS WILL NOT HAVE A USE EASEMENT IF ADJACENT TO A TRACT OR OPEN SPACE. SPECIFICS OF THE USE AND PERMISSIONS FOR THESE AREAS ARE DEFINED IN THE CCR'S.
14. ACCESSORY DWELLING UNITS (ADU) WILL NOT BE ALLOWED TO BE SOLD VIA CONDO PLAT BUT MAY BE RENTED OUT BY THE OWNER. ONLY LOTS 55-92 ALLOW FOR ADU OPTION.

B. DEVELOPMENT STANDARD FOR ALL RESIDENTIAL LOTS

SEE DEVELOPMENT DATA ABOVE AND STANDARD DETAILS ON SHEET 3

SETBACKS: (SEE DEV. STANDARD DETAILS - SEE SHEET 3)

LOTS 1-54 - SINGLE FAMILY ATTACHED DUPEX PRODUCT	
FRONT YARD:	15 FEET MIN. (FACING PUBLIC ROW)
SIDE YARD:	0 FEET FOR COMMON LOT LINE ONLY, 5 FEET FOR ADJACENT DUPEX LOT
REAR YARD:	5 FEET
CORNER LOT:	5 FEET + ADJACENT 10' WIDE TRACT, 15' TOTAL

LOTS 55-92 - SINGLE FAMILY DETACHED WITH OPTIONAL ADU

FRONT YARD:	12 FEET MIN. (FACING OPEN SPACE TRACT)
SIDE YARD:	5 FEET
REAR YARD:	18.5 FEET (FACING PRIVATE ROAD TRACT)
CORNER LOT:	5 FEET + ADJACENT 10' WIDE TRACT, 15' TOTAL

LOTS 93-227 - SINGLE FAMILY DETACHED PREAMBLE PRODUCT

FRONT YARD:	5 FEET MIN. (FACING OPEN SPACE TRACT)
SIDE YARD:	5 FEET
REAR YARD:	10 FEET (FACING PRIVATE ROAD TRACT)
CORNER LOT:	5 FEET + ADJACENT 10' WIDE TRACT, 15' TOTAL

NOTE: WHERE A CONFLICT ARISES BETWEEN THESE DEVELOPMENT STANDARDS AND WHAT IS DEPICTED ON THE PLAN, THE PLAN GOVERNS.

C. LOT LINES:

1. THE PUD DEVELOPMENT/PRELIMINARY PLAN AND THE PLAT ESTABLISH THE LOT SIZES FOR EACH LOT.
2. FOLLOWING INITIAL SUBDIVISION, NO VACATIONS AND REPLATS SHALL BE ALLOWED IF THESE WOULD RESULT IN THE ADDITION OF LOTS IN A MANNER NOT FULLY CONSISTENT WITH THE PUD DEVELOPMENT/PRELIMINARY PLAN.
3. MINOR ADJUSTMENTS TO LOT LINES AND TRACT AREAS CAN BE MADE WITH THE FINAL PLATS WITHOUT REQUIRING AN AMENDMENT TO THIS PUD DEVELOPMENT/PRELIMINARY PLAN.

D. STREETS:

STREETS WITHIN VILLAGES AT STERLING RANCH PROVIDE GENERAL VEHICULAR CIRCULATION THROUGHOUT THE DEVELOPMENT, STREETS SHALL BE PUBLICLY AND PRIVATELY OWNED (AS NOTED BELOW).
ALL PUBLIC STREETS WITH APPROVED DEVIATIONS, SHALL BE CONSTRUCTED TO EL PASO COUNTY STANDARDS, DEDICATED TO EL PASO COUNTY, AND UPON ACCEPTANCE BY EL PASO COUNTY, SHALL BE MAINTAINED BY EL PASO COUNTY.

ALL PRIVATE STREET TRACTS WITH APPROVED DEVIATIONS, SHALL BE OWNED AND MAINTAINED BY THE STERLING RANCH METROPOLITAN DISTRICT.

E. ARCHITECTURAL CONTROL COMMITTEE REVIEW/COVENANTS:

COVENANTS FOR VILLAGES AT STERLING RANCH WILL BE CREATED BY SEPARATE DOCUMENTS AND RECORDED PRIOR TO FINAL PLAT. THE COVENANTS ESTABLISH RULES AND REGULATIONS FOR THE PROPERTY WITHIN THE SUBDIVISIONS AND ESTABLISH THE GOVERNANCE MECHANISM OF THE SUBDIVISION, INCLUDING THE CREATION OF THE ARCHITECTURAL CONTROL COMMITTEE.

F. ACCESS LIMITATION:

THERE SHALL BE NO DIRECT VEHICULAR LOT ACCESS TO STERLING RANCH ROAD, BRIARGATE PARKWAY AND OAK PARK DRIVE.

DEVELOPMENT DATA:

EXISTING ZONING:	RR-5
TAX SCHEDULE NO.:	5200000552
TOTAL AREA:	39.058 ACRES
NUMBER OF LOTS:	227
TOTAL LOT AREA:	16.22 ACRES (41.5%)
AVERAGE LOT SIZE:	3,113 SF
MINIMUM LOT SIZE:	2900 SF
MINIMUM LOT WIDTH:	30.0'
MINIMUM LOT DEPTH:	80.0'
MAXIMUM LOT COVERAGE:	68%
MAXIMUM BUILDING HEIGHT:	35'
GROSS DENSITY:	5.81 DU/AC
NET DENSITY (W/O PUBLIC ROW & PRIVATE TRACTS):	9.20 DU/AC
PUBLIC ROADWAY (50' ROW - URBAN LOCAL)	10.99 ACRES (28.1%)
PRIVATE ACCESS ROAD (TRACTS)	3.45 ACRES (8.8%)
TOTAL OPEN SPACE:	8.40 ACRES (21.6%)
OPEN SPACE REQUIRED: 10% OF 39.058 AC = 3.9 AC	
OPEN SPACE PROVIDED:	8.46 AC (21.7% TRACTS A-O AND R)
CONTIGUOUS USABLE OPEN SPACE REQUIRED: (25% OF 3.9 AC) = 0.975 AC	
CONTIGUOUS USABLE OPEN SPACE PROVIDED:	2.9 AC (TRACT A OUTSIDE OF PARKING STALLS)

APPLICANT/DEVELOPER/ PROPERTY OWNER

CLASSIC SRJ LAND, LLC
2138 FLYING HORSE CLUB DRIVE
COLORADO SPRINGS, CO 80921
MR. LOREN MORELAND
(719) 592-9333

PROPERTY ADDRESS

SE CORNER OF BRIARGATE PARKWAY
& STERLING RANCH ROAD
COLORADO SPRINGS, CO 80922

APPLICANT REPRESENTATION

CLASSIC CONSULTING ENGINEERS
& SURVEYORS, LLC
619 N. CASCADE AVENUE, SUITE 200
COLORADO SPRINGS, CO 80903
MR. KYLE CAMPBELL, P.E.
(719) 785-0790

OWNER CERTIFICATION:

CLASSIC SRJ LAND, LLC
NAME OF LANDOWNER

LANDOWNER'S SIGNATURE

STATE OF COLORADO }
COUNTY OF EL PASO }ss

THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS _____ DAY OF _____, 20____ A.D. BY _____

OF ELITE PROPERTIES OF AMERICA, INC., A COLORADO CORPORATION.

WITNESS MY HAND AND OFFICIAL SEAL.

MY COMMISSION EXPIRES: _____

NOTARY PUBLIC

I / WE, CAPSTONE TITLE, A (ONE OF THE FOLLOWING: QUALIFIED TITLE INSURANCE COMPANY, TITLE COMPANY, TITLE ATTORNEY, OR ATTORNEY AT LAW) DULY QUALIFIED, INSURED, OR LICENSED BY THE STATE OF COLORADO, DO HEREBY CERTIFY THAT I / WE HAVE EXAMINED THE TITLE OF ALL LANDS DEPICTED AND DESCRIBED HEREON AND THAT TITLE TO SUCH LAND IS OWNER IN FEE SIMPLE BY _____ AT THE TIME OF THIS APPLICATION.

SIGNATURE

STATE OF COLORADO }
COUNTY OF EL PASO }ss

THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS _____ DAY OF _____, 20____ A.D. BY _____

WITNESS MY HAND AND OFFICIAL SEAL.

MY COMMISSION EXPIRES: _____

NOTARY PUBLIC

COUNTY CERTIFICATION:

THIS REZONING REQUEST TO PUD HAS BEEN REVIEWED AND FOUND TO BE COMPLETE AND IN THE ACCORDANCE WITH THE _____ (BOARD RESOLUTION OR MOTION #) _____ (DATE) APPROVING THE PUD AND ALL APPLICABLE EL PASO COUNTY REGULATIONS.

DIRECTOR, PLANNING & COMMUNITY DEVELOPMENT

DATE

BOARD OF COUNTY COMMISSIONER

DATE

CLERK AND RECORDER CERTIFICATION:

STATE OF COLORADO }
COUNTY OF EL PASO }ss

I HEREBY CERTIFY THAT THIS PLAN WAS FILED FOR RECORD IN MY OFFICE AT _____ O'CLOCK _____ M. THIS _____ DAY OF _____, 20____, A.D., AND IS DULY RECORDED AT RECEPTION NO. _____ OF THE RECORDS OF EL PASO COUNTY, COLORADO.

BY:

EL PASO COUNTY CLERK AND RECORDER

EL PASO COUNTY FILE NO.: PUD SP-22--006



VILLAGES AT STERLING RANCH

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN

TITLE SHEET

DESIGNED BY EAS SCALE DATE 11/27/2023

DRAWN BY EAS (H) 1"= 30' SHEET 1 OF 29


CHECKED BY (V) 1"= N/A JOB NO. 1183.26

619 N. Cascade Avenue, Suite 200 (719) 785-0790
Colorado Springs, Colorado 80903 (719) 785-0799 (Fax)

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34. TOWNSHIP 12S, RANGE 65W

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN




6' COMPOSITE PRIVACY FENCE FOR LOT SIDE YARDS

NOTE:

GEOLOGIC HAZARD NOTE: THE FOLLOWING LOTS HAVE BEEN FOUND TO BE IMPACTED BY GEOLOGIC HAZARDS. MITIGATION MEASURES AND A MAP OF THE HAZARD AREA CAN BE FOUND IN THE REPORT "SOIL, GEOLOGY, AND GEOLOGIC HAZARD STUDY VILLAGES AT STERLING RANCH PRELIMINARY PLAN PARCEL NO. 14, 15, 20, & 21" BY ENTECH ENGINEERING INC. DATED APRIL 13, 2022 IN FILE PUDSP228 AVAILABLE AT THE EL PASO COUNTY PLANNING AND COMMUNITY DEVELOPMENT DEPARTMENT:

- POTENTIALLY SEASONAL SHALLOW GROUNDWATER AND EROSION (LOTS 208-210)
- POTENTIALLY UNSTABLE SLOPE (LOTS 43-54, 64, 73-77)
- HYDROCOMPACTION (LOTS 2-11, 15-34, 43-64, 73-92)

NO BASEMENTS ARE PROPOSED WITHIN THIS SUBDIVISION. EITHER SLAB ON GRADE OR CRAWL SPACE WILL BE DESIGNED FOR ALL UNITS.



TRACT KEY MAP
SCALE: 1"=150'


- OPEN SPACE TRACTS
- PRIVATE ACCESS TRACTS
- PUBLIC ROW
- SINGLE FAMILY DUPLEX PRODUCT (LOTS 1-54)
- SINGLE FAMILY DETACHED W/ ADU OPTION (LOTS 55-92)
- PREAMBLE PRODUCT SINGLE FAMILY DETACHED (LOTS 93-227)

VILLAGES AT STERLING RANCH TRACT SUMMARY TABLE:

TRACTS	SQUARE FEET	PERCENTAGE	OWNER	MAINTENANCE
TRACTS (OPEN SPACE) A-Q, R (SEE TABLE BELOW)	365,988	21.6%	STERLING RANCH METROPOLITAN DISTRICT	STERLING RANCH METROPOLITAN DISTRICT
TRACTS (PRIVATE ACCESS) P, Q (SEE TABLE BELOW)	150,120	8.8%	STERLING RANCH METROPOLITAN DISTRICT	STERLING RANCH METROPOLITAN DISTRICT
LOTS (227 TOTAL)	706,557	41.5%	INDIVIDUAL LOT OWNERS	
PUBLIC R.O.W.	478,688	28.1%	COUNTY	COUNTY
TOTAL	1,701,353	100.0%		

TRACT TABLE

TRACT	SIZE (SF)	SIZE (AC)	LANDSCAPE/PARK/SPACE/TRAIL	PRIVATE ACCESS	MAILBOXES	SIGNAGE/PUBLIC IMPROVEMENTS	PUBLIC UTILITIES	ELECTRIC EASEMENTS	FENCE/WALLS	OWNED BY	MAINTAINED BY
TRACT A	148,218	3.403	X			X	X	X	X	SRMD	SRMD
TRACT B	8,745	0.201	X		X	X	X	X	X	SRMD	SRMD
TRACT C	3,729	0.086	X			X	X	X	X	SRMD	SRMD
TRACT D	58,805	1.350	X		X	X	X	X	X	SRMD	SRMD
TRACT E	7,966	0.183	X			X	X	X	X	SRMD	SRMD
TRACT F	7,966	0.183	X			X	X	X	X	SRMD	SRMD
TRACT G	5,296	0.122	X			X	X	X	X	SRMD	SRMD
TRACT H	16,128	0.370	X		X	X	X	X	X	SRMD	SRMD
TRACT I	21,329	0.490	X			X	X	X	X	SRMD	SRMD
TRACT J	21,329	0.490	X			X	X	X	X	SRMD	SRMD
TRACT K	9,360	0.215	X			X	X	X	X	SRMD	SRMD
TRACT L	9,360	0.215	X			X	X	X	X	SRMD	SRMD
TRACT M	26,272	0.603	X		X	X	X	X	X	SRMD	SRMD
TRACT N	9,425	0.216	X			X	X	X	X	SRMD	SRMD
TRACT O	9,425	0.216	X			X	X	X	X	SRMD	SRMD
TRACT P	81,258	1.865		X		X	X	X		SRMD	SRMD
TRACT Q	68,862	1.581		X		X	X	X		SRMD	SRMD
TRACT R	2,635	0.060	X			X	X	X	X	SRMD	SRMD
TOTALS	516,108	11.85									



LEGEND:


- Qes - Eolian Sand of Holocene and Pleistocene? Age; wind deposited sands
- Qao - Old Alluvium one of late-middle Pleistocene Age; older terrace deposit
- er - erosion
- h - hydrocompaction
- psw - potentially seasonal shallow groundwater area
- pu - potentially unstable slope

REVISION BY



GEOTECHNICAL ENGINEERING
GEOLOGY MAP
FOR THE
PRELIMINARY PLAN NO. 3
COLORADO SPRINGS, CO.
FOR: CLASSIC SRJ

DATE: 4/2/25
BY: [Signature]
AS SHOWN
SUBJECT: PUD SP-228



EL PASO COUNTY FILE NO.: PUD SP-22-006

VILLAGES AT STERLING RANCH
PUD DEVELOPMENT PLAN & PRELIMINARY PLAN
TRACT USE TABLE / GEOLOGIC HAZARD MAP


DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1"= 20'	SHEET	2 OF 29
CHECKED BY	(V) 1"= N/A	JOB NO.	1183.26	

619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903
(719) 785-0790
(719) 785-0799 (Fax)


VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34. TOWNSHIP 12S, RANGE 65W


PUD DEVELOPMENT PLAN & PRELIMINARY PLAN




TYPICAL LOT CONFIGURATION DETAIL (DUPLIX PRODUCT)
 SCALE: 1"=20' (H)
 (LOTS 1-54)




TYPICAL LOT CONFIGURATION DETAIL (SINGLE FAMILY DETACHED W/ OPTIONAL ADU)
 ACCESS FROM 50' PUBLIC ROW
 SCALE: 1"=20' (H)
 (LOTS 55-66)




TYPICAL LOT CONFIGURATION DETAIL (SINGLE FAMILY DETACHED W/ OPTIONAL ADU)
 ACCESS FROM PRIVATE ROAD TRACT
 SCALE: 1"=20' (H)
 (LOTS 67-92)
 NO PARKING / FIRE LANE SIGNAGE PER FIRE DEPT. STDS




TYPICAL LOT CONFIGURATION DETAIL (PREMABLE PRODUCT - SINGLE FAMILY DETACHED 20'x40' BLDG.)
 ACCESS FROM PRIVATE ROAD TRACT
 SCALE: 1"=20' (H)
 (LOTS 93-227)
 NO PARKING / FIRE LANE SIGNAGE PER FIRE DEPT. STDS.




TYPICAL LOT CONFIGURATION DETAIL (PREMABLE PRODUCT - SINGLE FAMILY DETACHED 14'x40' BLDG.)
 ACCESS FROM PRIVATE ROAD TRACT
 SCALE: 1"=20' (H)
 (LOTS 93-227)
 NO PARKING / FIRE LANE SIGNAGE PER FIRE DEPT. STDS.



PRIVATE ROAD (30' WIDE TRACT)
 OWNED & MAINTAINED BY THE STERLING RANCH METRO. DISTRICT
 N.T.S.
 NO PARKING ALLOWED



50' R.O.W. TYPICAL STREET/UTILITY SECTION URBAN LOCAL ROADWAY
 N.T.S.



60' R.O.W. TYPICAL STREET/UTILITY SECTION URBAN RESIDENTIAL COLLECTOR
 N.T.S.

EL PASO COUNTY FILE NO.: PUD SP-22-006

VILLAGES AT STERLING RANCH

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN
 DEVELOPMENT STANDARD DETAILS

CLASSIC CONSULTING

DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1"= 20'	SHEET	3 OF 29
CHECKED BY	(V) 1"= N/A	JOB NO.	1183.26	


619 N. Cascade Avenue, Suite 200 (719)785-0790
 Colorado Springs, Colorado 80903 (719)785-0799 (Fax)

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34, TOWNSHIP 12S, RANGE 65W

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN

UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE SINGLE FAMILY RESIDENTIAL
CURRENT ZONING: RR-5



KEY MAP
NOT TO SCALE

LEGEND

- BOUNDARY LINE —————
- PROPERTY LINE —————
- EASEMENT SETBACK LINE - - - - -
- LINE OF SIGHT - · - · -
- EXISTING WATER LINE — W — W —
- EXISTING SANITARY SEWER - - S - - S - -
- EXISTING STORM LINE —————



NO PARKING ALONG CURB
WITHIN PRIVATE ACCESS ROADS

EXACT LOCATION OF "NO PARKING"
SIGNS DETERMINED ON CDS.

BRIARGATE PARKWAY
(PUBLIC ARTERIAL, 130' ROW)


ROADWAY TO BE BUILT WITH
FUTURE NORTHERLY & EASTERLY
ADJACENT DEVELOPMENT

UNPLATTED
FUTURE BRIARGATE PARKWAY
RIGHT OF WAY

MATCHLINE SEE SHEET 5

MATCHLINE SEE SHEET 9

UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE PUD DEVELOPMENT (5-8DU/AC)
CURRENT ZONING: RR-5
FUTURE ZONING: PUD



SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006



VILLAGES AT STERLING RANCH
PUD DEVELOPMENT PLAN & PRELIMINARY PLAN

DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET	6 OF 29
CHECKED BY	(V) 1" = N/A	JOB NO.	1183.26	


619 N. Cascade Avenue, Suite 200 (719) 785-0790
Colorado Springs, Colorado 80903 (719) 785-0799 (Fax)



VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34, TOWNSHIP 12S, RANGE 65W

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN




KEY MAP
NOT TO SCALE

LEGEND

- BOUNDARY LINE
- PROPERTY LINE
- EASEMENT SETBACK LINE
- LINE OF SIGHT
- EXISTING WATER LINE
- EXISTING SANITARY SEWER
- EXISTING STORM LINE



NO PARKING ALONG CURB
WITHIN PRIVATE ACCESS ROADS
EXACT LOCATION OF "NO PARKING"
SIGNS DETERMINED ON CDS.



SCALE: 1" = 30'


EL PASO COUNTY FILE NO.: PUD SP-22-006



VILLAGES AT STERLING RANCH			
PUD DEVELOPMENT PLAN & PRELIMINARY PLAN			
DESIGNED BY	EAS	SCALE	DATE 11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET 7 OF 29
CHECKED BY	(V) 1" = N/A	JOB NO.	1183.26

619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903
(719) 785-0790
(719) 785-0799 (Fax)


UNPLATTED
STERLING RANCH EAST FILING NO. 5
SINGLE FAMILY DETACHED
CURRENT ZONING: RS-5000



V:\118326\UPDRAWINGS\DEVELOPMENT\118326_05-07.dwg, 11/17/2023, 4:09:22 PM, 1:1

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO
 SECT. 34. TOWNSHIP 12S, RANGE 65W
PUD DEVELOPMENT PLAN & PRELIMINARY PLAN




KEY MAP
NOT TO SCALE

LEGEND

- BOUNDARY LINE
- PROPERTY LINE
- EASEMENT SETBACK LINE
- LINE OF SIGHT
- EXISTING WATER LINE
- EXISTING SANITARY SEWER
- EXISTING STORM LINE



NO PARKING ALONG CURB
 WITHIN PRIVATE ACCESS ROADS
 EXACT LOCATION OF "NO PARKING"
 SIGNS DETERMINED ON CDS.



30 15 0 30 60

SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006

VILLAGES AT STERLING RANCH

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN

DESIGNED BY: EAS SCALE: DATE: 11/27/2023

DRAWN BY: EAS (H) 1" = 30' SHEET 8 OF 29


CHECKED BY: (V) 1" = N/A JOB NO. 1183.26



619 N. Cascade Avenue, Suite 200 (719) 785-0790
 Colorado Springs, Colorado 80903 (719) 785-0799 (Fax)



UNPLATTED
 OWNER: CLASSIC SRJ LAND, LLC
 FUTURE SINGLE FAMILY DETACHED
 CURRENT ZONING: RR-5
 PROPOSED ZONING: RS-5000




V:\18326\UPDATING\DEVELOPMENT\18326-06.dwg, 11/17/2023, 4:04:04 PM, 1:1

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34, TOWNSHIP 12S, RANGE 65W

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN



KEY MAP
NOT TO SCALE

LEGEND

- BOUNDARY LINE
- PROPERTY LINE
- EASEMENT SETBACK LINE
- LINE OF SIGHT
- EXISTING WATER LINE
- EXISTING SANITARY SEWER
- EXISTING STORM LINE



NO PARKING ALONG CURB
WITHIN PRIVATE ACCESS ROADS

EXACT LOCATION OF "NO PARKING"
SIGNS DETERMINED ON CDS.

UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE PUD DEVELOPMENT (5-8DU/AC)
CURRENT ZONING: RR-5
FUTURE ZONING: PUD



30 15 0 30 60

SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006




VILLAGES AT STERLING RANCH
PUD DEVELOPMENT PLAN & PRELIMINARY PLAN



DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET	9 OF 29
CHECKED BY		(V) 1" = N/A	JOB NO.	1183.26

619 N. Cascade Avenue, Suite 200 (719) 785-0790
Colorado Springs, Colorado 80903 (719) 785-0799 (Fax)




UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE SINGLE FAMILY DETACHED
CURRENT ZONING: RR-5
PROPOSED ZONING: RS-5000

MATCHLINE SEE SHEET 8

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34. TOWNSHIP 12S, RANGE 65W


PUD DEVELOPMENT PLAN & PRELIMINARY PLAN



KEY MAP
NOT TO SCALE

LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT




SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006

	VILLAGES AT STERLING RANCH		
	PRELIMINARY GRADING AND UTILITY PLAN		
	DESIGNED BY	EAS	SCALE
	DRAWN BY	EAS	(H) 1" = 30'
CHECKED BY	(V) 1" = N/A	DATE	11/27/2023
		SHEET	10 OF 29
		JOB NO.	1183.26

619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903

(719) 785-0790
(719) 785-0799 (Fax)



MATCHLINE SEE SHEET 11

MATCHLINE SEE SHEET 13



V:\18326\DRAWINGS\DEVELOPMENT\18326-PUD-06-10.dwg, 11/14/2024 8:25:12 AM, 1:1

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34. TOWNSHIP 12S, RANGE 65W

PUD DEVELOPMENT PLAN & PRELIMINARY PLAN


TRACT H
OWNER: CLASSIC SRJ LAND, LLC
FOURSQUARE AT STERLING RANCH FIL. 1
CURRENT ZONING: PUD



KEY MAP
NOT TO SCALE

LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT



EL PASO COUNTY FILE NO.: PUD SP-22-006

619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903

(719) 785-0790
(719) 785-0799 (Fax)

VILLAGES AT STERLING RANCH

PRELIMINARY GRADING AND UTILITY PLAN

DESIGNED BY	EAS	SCALE	DATE
DRAWN BY	EAS	(H) 1" = 30'	11/27/2023
CHECKED BY	(V) 1" = N/A	SHEET	11 OF 29
		JOB NO.	1183.26

V:\18326\DRAWINGS\DEVELOPMENT\18326_PUD-SP-22-006_PUD-SP-22-006_11.dwg, 11/14/2024 8:28:15 AM, 1:1

MATCHLINE SEE SHEET 10



MATCHLINE SEE SHEET 12

MATCHLINE SEE SHEET 14

VILLAGES AT STERLING RANCH


COUNTY OF EL PASO, STATE OF COLORADO SECT. 34. TOWNSHIP 12S, RANGE 65W
PUD DEVELOPMENT PLAN & PRELIMINARY PLAN

UNPLATTED
 OWNER: CLASSIC SRJ LAND, LLC
 FUTURE SINGLE FAMILY RESIDENTIAL
 CURRENT ZONING: RR-5



LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT



SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006

VILLAGES AT STERLING RANCH

PRELIMINARY GRADING AND UTILITY PLAN



619 N. Cascade Avenue, Suite 200
 Colorado Springs, Colorado 80903
 (719) 785-0790
 (719) 785-0799 (Fax)

DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET	12 OF 29
CHECKED BY	(V)	1" = N/A	JOB NO.	1183.26




MATCHLINE SEE SHEET 11

MATCHLINE SEE SHEET 15

V:\18326\DRAWINGS\DEVELOPMENT\18326_PUD-PG-12.dwg, 11/14/2024, 8:30:02 AM, 1:1


VILLAGES AT STERLING RANCH
 COUNTY OF EL PASO, STATE OF COLORADO
 SECT. 34. TOWNSHIP 12S, RANGE 65W
**PUD DEVELOPMENT PLAN &
 PRELIMINARY PLAN**



KEY MAP
 NOT TO SCALE

LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT



SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006


VILLAGES AT STERLING RANCH

PRELIMINARY GRADING AND UTILITY PLAN

DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET	13 OF 29
CHECKED BY		(V) 1" = N/A	JOB NO.	1183.26



619 N. Cascade Avenue, Suite 200
 Colorado Springs, Colorado 80903
 (719) 785-0790
 (719) 785-0799 (Fax)




V:\18326\DRAWINGS\DEVELOPMENT\18326_PUD-06-13.dwg, 11/14/2024 8:32:51 AM, 1:1

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO
SECT. 34, TOWNSHIP 12S, RANGE 65W


PUD DEVELOPMENT PLAN & PRELIMINARY PLAN



KEY MAP
NOT TO SCALE

LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT




SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006

VILLAGES AT STERLING RANCH


PRELIMINARY GRADING AND UTILITY PLAN

DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET	14 OF 29
CHECKED BY	(V) 1" = N/A	JOB NO.	1183.26	



619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903

(719) 785-0790
(719) 785-0799 (Fax)



UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE SINGLE FAMILY DETACHED
CURRENT ZONING: RR-5
PROPOSED ZONING: RS-5000

V:\18326\DRAWINGS\DEVELOPMENT\18326_PUD-06-14.dwg, 11/14/2024 8:35:14 AM, 1:1

MATCHLINE SEE SHEET 13

MATCHLINE SEE SHEET 15


MATCHLINE SEE SHEET 11

MATCHLINE SEE SHEET 16

VILLAGES AT STERLING RANCH

COUNTY OF EL PASO, STATE OF COLORADO SECT. 34. TOWNSHIP 12S, RANGE 65W


PUD DEVELOPMENT PLAN & PRELIMINARY PLAN



KEY MAP
NOT TO SCALE

LEGEND

- (6770) --- EXISTING CONTOUR
- 6770 --- PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- ➔ PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT



SCALE: 1" = 30'

EL PASO COUNTY FILE NO.: PUD SP-22-006

VILLAGES AT STERLING RANCH

PRELIMINARY GRADING AND UTILITY PLAN


DESIGNED BY	EAS	SCALE	DATE	11/27/2023
DRAWN BY	EAS	(H) 1" = 30'	SHEET	15 OF 29
CHECKED BY	(V) 1" = N/A	JOB NO.	1183.26	



619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903
(719) 785-0790
(719) 785-0799 (Fax)



619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903
(719) 785-0790
(719) 785-0799 (Fax)



UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE SINGLE FAMILY DETACHED
CURRENT ZONING: RR-5
PROPOSED ZONING: RS-5000

UNPLATTED
OWNER: CLASSIC SRJ LAND, LLC
FUTURE PUD DEVELOPMENT (5-8DU/AC)
CURRENT ZONING: RR-5
FUTURE ZONING: PUD

MATCHLINE SEE SHEET 14



MATCHLINE SEE SHEET 12

V:\118326\DRAWINGS\DEVELOPMENT\118326_PUD-06-15.dwg, 11/14/2024 8:36:59 AM, 1:1

MATCHLINE SEE SHEET 13


MATCHLINE SEE SHEET 14

VILLAGES AT STERLING RANCH
 COUNTY OF EL PASO, STATE OF COLORADO
 SECT. 34. TOWNSHIP 12S, RANGE 65W
**PUD DEVELOPMENT PLAN &
 PRELIMINARY PLAN**



LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP PROPOSED HIGH POINT
- LP PROPOSED LOW POINT



EL PASO COUNTY FILE NO.: PUD SP-22-006



VILLAGES AT STERLING RANCH			
PRELIMINARY GRADING AND UTILITY PLAN OFF-SITE			
DESIGNED BY	EAS	SCALE	DATE 11/8/2024
DRAWN BY	EAS	(H) 1" = 60'	SHEET 16 OF 29
CHECKED BY		(V) 1" = N/A	JOB NO. 1183.26

619 N. Cascade Avenue, Suite 200
 Colorado Springs, Colorado 80903
 (719) 785-0790
 (719) 785-0799 (Fax)



MATCHLINE SEE SHEET 17

V:\18326\DRAWINGS\DEVELOPMENT\18326_PUD-PG-16-17.dwg, 11/14/2024 8:33:24 AM, 1:1

MATCHLINE SEE SHEET 16

VILLAGES AT STERLING RANCH


COUNTY OF EL PASO, STATE OF COLORADO
SECT. 34, TOWNSHIP 12S, RANGE 65W
**PUD DEVELOPMENT PLAN &
PRELIMINARY PLAN**



KEY MAP
NOT TO SCALE

LEGEND

- (6770) EXISTING CONTOUR
- 6770 PROPOSED CONTOUR
- BOUNDARY/FILING LINE
- EXISTING FLOW DIRECTION
- PROPOSED FLOW DIRECTION
- PROPOSED INLET
- PROPOSED STORM PIPE
- EXISTING STORM PIPE
- HP** PROPOSED HIGH POINT
- LP** PROPOSED LOW POINT



EL PASO COUNTY FILE NO.: PUD SP-22-006


CLASSIC CONSULTING
619 N. Cascade Avenue, Suite 200
Colorado Springs, Colorado 80903
(719) 785-0790
(719) 785-0799 (Fax)

VILLAGES AT STERLING RANCH			
PRELIMINARY GRADING AND UTILITY PLAN OFF-SITE			
DESIGNED BY	EAS	SCALE	DATE 11/8/2024
DRAWN BY	EAS	(H) 1" = 60'	SHEET 17 OF 29
CHECKED BY	(V)	1" = N/A	JOB NO. 1183.26

V:\18326\DRAWINGS\DEVELOPMENT\18326_PUD-PG-16-17.dwg, 11/14/2024 8:40:39 AM, 1:1

Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan



DATE	REVISION DESCRIPTION
9/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION




VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO

JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	TITLE SHEET
SHEET #	L-TS 18 OF 29

PLANTING LEGEND					
Notes Key:					
X=Xeric plant, R=Rabbit Resistant, DE=Deer Resistant, F=Firewise plant					
Z=Zone, K=Altitude, Water Use inch / year. D=Dry (13-20"), A=Adaptable (18-28")					
S=Steady (23-38"), W=Wet (36"+) SIG=Signature plant (City of Colorado Springs)					
ABBR.	QTY.	BOTANICAL NAME	COMMON NAME	SIZE	NOTES
DECIDUOUS TREES					
ABM	38	Acer x freemanii 'Autumn Blaze'	Maple, Autumn Blaze	1-1/2"	Z=4, 6.5K, S, SIG
ACT	2	Acer tataricum	Maple tatarian	1-1/2"	Z=3, 8.5K, A, SIG
ANM	16	Acer platanoides	Maple, Norway	1-1/2"	Z=4, 6.5K, S, SIG
ARR	13	Acer platanoides 'Royal Red'	Maple, Royal Red	1-1/2"	Z=4, 6.5K, S, SIG
CCH	18	Crataegus crus-galli 'Inermis'	Hawthorn, Cockspur (Thornless)	1-1/2"	R, DE, F, Z=4, 8.5K, A, D, SIG
COH	12	Celtis occidentalis	Hackberry	1-1/2"	R, DE, F, Z=3, 7K, A, D, SIG
GSH	12	Gleditsia triacanthos 'Skyline'	Honeylocust, Skyline	1-1/2"	R, DE, F, Z=4, 6.5K, A, S, SIG
MSS	34	Malus 'Spring Snow'	Crabapple, Spring Snow	1-1/2"	F, Z=4, 8.5K, S, SIG
PCR	6	Prunus virginiana 'Schubert'	Cherry, Canada Red	1-1/2"	R, DE, F, Z=2, 9.5K, A, S, SIG
TAR	15	Tilia americana 'Redmond'	Linden, Redmond	1-1/2"	Z=3, 6K, S, SIG
EVERGREEN TREES					
JCJ	6	Juniperus scopulorum 'Cologreen'	Juniper, Cologreen	15 Gal (6')	R, DE, Z=3, 8.5K, D, SIG
PIB	14	Picea pungens 'Baker'	Spruce, Baker	6'	R, DE, Z=2, 8K, S, SIG
PIE	9	Pinus edulis	Pine, Pinyon	6'	X, R, DE, Z=3, 7.5K, D, SIG
PIP	6	Picea pungens	Spruce, Colorado Blue	6'	R, DE, Z=3, 10K, S, SIG
PON	21	Pinus ponderosa	Pine, Ponderosa	6'	R, DE, Z=3, 9.5K, D, SIG
DECIDUOUS SHRUBS					
ABR	58	Aronia arbutifolia 'Brilliantissima'	Chokeberry, Brilliant Red	5 Gal	R, DE, Z=5, 7.5K, S, SIG
ARB	12	Aronia melanocarpa	Chokeberry, Black	5 Gal	R, DE, Z=2, 8.5K, A, SIG
COP	56	Cornosteaster acutifolia	Cornosteaster, peking	5 Gal	R, DE, Z=4, 10K, S, SIG
CRD	24	Cornus stolonifera 'colorodensis'	Dogwood, Red Twig	5 Gal	R, DE, Z=2, F, 8K, S, SIG
EBB	9	Euonymus alatus	Burning Bush	5 Gal	R, DE, F, Z=3, 7.5K, S, SIG
FNP	13	Forestica neomexicana	Privet, New Mexican	5 Gal	R, DE, Z=3-4, 7.5K, A, D, SIG
POA	111	Potentilla fruticosa 'Abbotswood'	Potentilla, Abbotswood	5 Gal	R, DE, F, Z=2, 10K, S, SIG
POG	34	Potentilla fruticosa 'Gold finger'	Potentilla, Gold finger	5 Gal	R, DE, F, Z=2, 10K, S, SIG
PRS	72	Potentilla fruticosa 'Red sunset'	Potentilla, 'Red Sunset'	5 Gal	R, DE, Z=3, S, SIG
RFB	32	Rhamnus frangula 'Columnaris'	Buckthorn, Columnar	5 Gal	R, DE, Z=2, 7.5K, D, SIG
RGL	84	Rhus aromatica 'Gro-low'	Sumac, Gro-Low	5 Gal	DE, Z=3, 8.5K, A, D, SIG
SCL	9	Syringa x chinensis	Lilac, Chinese	5 Gal	R, DE, Z=3, 9K, A, SIG
SPG	103	Spiraea x bumalda 'Goldmound'	Spiraea, Goldmound	5 Gal	R, DE, Z=3, 7.5K, A, S, SIG
SPV	72	Spiraea x 'Vanhouttei'	Spiraea, Vanhouttei	5 Gal	R, DE, Z=3, 7.5K, A, S, SIG
VOS	29	Viburnum opulus 'Roseum'	Viburnum Snowball	5 Gal	R, DE, Z=3, 7.5K, A, SIG
EVERGREEN SHRUBS					
JBJ	105	Juniperus Sabina	Juniper, Buffalo	5 Gal	R, DE, Z=3, 8.5K, A, SIG
JBM	22	Juniperus sabina 'Broadmoor'	Juniper, Broadmoor	5 Gal	R, DE, Z=3, 8K, A, SIG
JCS	24	Juniperus chinensis 'Spartan'	Juniper, Spartan	5 Gal	R, DE, Z=5, 7.5K, A, D, SIG
JUA	26	Juniperus chinensis 'Armstrong'	Juniper, Armstrong	5 Gal	R, DE, Z=3, 7.5K, A, D, SIG
PGS	35	Picea pungens 'Glauca Globosa'	Spruce, Globe Blue	5 Gal	Z=2, 10K, S, SIG
PIM	20	Pinus mugo 'Slowmound'	Pine, Slowmound Mugo	5 Gal	Z=3, 9.5K, D, SIG
ORNAMENTAL GRASSES					
CAA	180	Calamagrostis x acutiflora 'Karl Foerster'	Feather Reed Grass	1 Gal	R, DE, Z=3, 6.5K, A, SIG
PSR	35	Panicum virgatum 'Rebraun'	Switch grass 'Rebraun'	1 Gal	R, DE, Z=5, 7K, D, SIG

GROUNDCOVER LEGEND		
SYMBOL	DESCRIPTION	QUANTITY
	STEEL EDGING	5,464 LF
	3/4" BLACK GRANITE ROCK 3" IN DEPTH WITH WEED FABRIC	28,016 SF
	1-1/2" BLUE GLACIER ROCK 3" IN DEPTH WITH WEED FABRIC	116,266 SF
	3" SADDLEBACK SWIRL ROCK 3" IN DEPTH WITH WEED FABRIC	46,056 SF
	2"-6" CLEAR CREEK ROCK 3" IN DEPTH WITH WEED FABRIC	9,223 SF
	CASCADE MULCH 3" IN DEPTH WITH NO WEED FABRIC (QUANTITY AT RIGHT NOT SHOWN FOR MULCH RINGS AT TREES LOCATED IN TURF OR NATIVE SEED)	TBD
	KENTUCKY BLUEGRASS SOD	77,648 SF
	IRRIGATED NATIVE SEED EL PASO COUNTY ALL PURPOSE LOW GROW MIX (PROVIDE EROSION CONTROL BLANKETS ON SLOPES 3:1 OR STEEPER SEE NOTES)	66,177 SF



PROJECT SITE DATA
ZONING: PUD
PROPERTY AREA: 1,388,499 SF
PARKING SPOTS: 171
TOTAL LANDSCAPE AREA: 343,341 SF

LANDSCAPE REQUIREMENTS						
LANDSCAPE SETBACKS (LS)						
Street Name / Boundary	Street Classification	Width (ft.)	Linear	Tree Req. / Ft.	Tree Req. /Prov.	Evergreen trees
Req. / Prov.	Req. / Prov.	Footage				Req. /Prov.
Briargate Parkway	Minor Arterial	20'/20'	1485'	1/25	59.4 / 48	0 / 0
Sterling Ranch Road	Minor Arterial	20'/20'	917'	1/25	36.7 / 31	0 / 0
Oak Park Drive	Non Arterial	10'/10'	1001'	1/30	33.4 / 26	11 / 11
Indianapolis Road	Non Arterial	10'/10'	522'	1/30	17.4 / 17	6 / 6
Shrub Substitutions		Ornamental grass	Setback	Percent Ground Plane Cov. Req./Pro		
Req. / Prov.	Req. / Prov.	Abbr.				
110 / 110	0 / 0	LS		75%/75%		
60 / 60	0 / 0	LS		75%/75%		
70 / 70	0 / 0	LS		75%/75%		
0 / 0	0 / 0	LS		75%/75%		
Motor Vehicle (MV)						
Number of Parking Spots	Shade Trees (1/15 Spaces) Req. / Prov.	Vehicle Lot Frontage	Linear Footage	2/3 Length Frontage		
171	11.4 / 12	East Drive	54 Ft.	36 Ft.		
Min. 3' High Screening Plants Req. / Prov.		Length Screen Wall / Berm	Abbrev. on Plan	Plane	% Ground Plane Cov. Req. /Prov.	
8/9		NA	MV		75%/75%	

Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan

CALLOUT KEY

- PLANT ABBREVIATION
- SITE CATEGORY ABBREVIATION
- TREE CALLOUT
- SHRUB & ORN. GRASS CALLOUT
- PERENNIAL CALLOUT
- PLANT QUANTITY

PLANT SYMBOL KEY

- DECIDUOUS TREE
- ORNAMENTAL TREE
- EVERGREEN TREE
- DECIDUOUS SHRUBS
- EVERGREEN SHRUBS
- ORNAMENTAL GRASSES
- PERENNIALS

PLANT AND TREE WARRANTY NOTE

ALL STOCK IS WARRANTED TO BE TRUE TO NAME. IF ANY STOCK PROVES TO BE OTHERWISE, SELLER WILL NOT BE LIABLE FOR ANY AMOUNT GREATER THAN ORIGINAL PURCHASE PRICE. THIS WARRANTY IS MADE EXPRESSLY IN LIEU OF ANY AND ALL OTHER WARRANTIES, EXPRESSED OR FIT FOR ANY PARTICULAR PURPOSE EXCEPT EXPRESSLY PROVIDED FOR. LIABILITY OF SELLER IS LIMITED TO REPLACEMENT OF ANY GOODS WHICH DO NOT CONFIRM TO WARRANTIES.

WINTER WATERING IS TO BE DONE AFTER MOISTURE CHECKS HAVE BEEN COMPLETED OF ALL PLANTS AND TREES. WARRANTY DOES NOT COVER PLANTS AND TREES DUE TO LACK OF WATER.

WARRANTY IS GOOD FOR ONE GROWING SEASON (APPROXIMATELY SIX MONTHS). PLANTS PURCHASED AFTER JULY 1ST ARE WARRANTED UNTIL MAY 1ST. PLANTS PURCHASED JANUARY 1ST THROUGH JULY 2ND ARE WARRANTED UNTIL NOVEMBER 30TH. SOME PLANTS CARRY NO WARRANTY. (TUBE INCLUDED) SUCH AS ANNUALS, PERENNIALS, ROSES, ARBORSVITAE, AND A FEW OTHER VARIETIES. INSTALLATION IS NOT COVERED UNDER WARRANTY.

ALL NON-IRRIGATED NATIVE SEED CARRIES NO WARRANTY.

LANDSCAPE IRRIGATION NOTE

LANDSCAPE TO BE IRRIGATED WITH A PROGRAMMABLE IRRIGATION CONTROLLER. TREES, SHRUBS, ORNAMENTAL GRASSES, AND PERENNIALS TO BE DRIP IRRIGATED WHEN LOCATED IN MULCH AREAS. TURF OR IRRIGATED NATIVE SEED AREAS TO BE SPRAY IRRIGATED WITH POP UP SPRAY OR ROTOR HEADS.

UTILITY NOTE

CALL 1-800-922-1987 FOR UTILITY LOCATIONS TO VERIFY LOCATION AND DEPTH OF ALL UNDERGROUND UTILITIES PRIOR TO START OF WORK. KEEP TREES 1' FROM GAS MAINS & 15' FROM SEWER AND WATER MAIN LINES. KEEP TREES 6' MINIMUM DISTANCE FROM ANY OTHER UTILITIES. RESOLVE ANY TREE/UTILITY CONFLICTS SHOWN ON PLANS IN THE FIELD. CONTACT LANDSCAPE ARCHITECT FOR RECOMMENDATIONS IF NEEDED.

PROVIDE CLEARANCE OF ALL PLANT MATERIALS AT ELECTRIC VAULTS AND TRANSFORMERS (REFER TO COLORADO SPRINGS UTILITIES CONSTRUCTION STANDARD DRAWING 19-302 FOR SPECIFIC CLEARANCE REQUIREMENTS).

KEEP ALL SHRUBS 3' CLEAR OF ALL FIRE HYDRANTS AT MATURE SIZE.


SITE CONDITIONS NOTE

THE LANDSCAPE IS SUBJECT TO CHANGE BASED ON SITE GRADING, DRAINAGE, CONFIGURATION, AND SIZE. ANY ADJUSTMENTS WILL BE MADE DURING LANDSCAPE CONSTRUCTION. PLANT MATERIAL SYMBOLS ARE SHOWN AT MATURE WIDTH.

LANDSCAPE INSTALLATION NOTES

- EDGING FOR TURF, PLANTING BEDS, ROCK, OR MULCH AREAS TO BE ROLL TOP STEEL EDGING WITH PINS OR APPROVED EQUAL. EDGING TO BE EXPOSED 1/2" +/- ABOVE FINISHED GRADES. INSTALL PER MANUFACTURE RECOMMENDATIONS.
- EXISTING SOIL IN ALL PLANTING BED AREAS TO BE AMENDED WITH THE FOLLOWING: 4 CUBIC YARDS OF ORGANIC SOIL AMENDMENT PER 1,000 SF FILLED INTO TOP 6" OF SOIL.
- SOD AREAS TO BE AMENDED WITH: 4 CUBIC YARDS OF ORGANIC SOIL AMENDMENT PER 1,000 SF FILLED INTO THE TOP 6" OF SOIL.

SEE SHEET L-TS FOR PLANTING AND GROUNDCOVER LEGEND



DATE	REVISION DESCRIPTION
9/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions


- FOR CONSTRUCTION
- NOT FOR CONSTRUCTION



VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO

JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	FINAL OVERALL LANDSCAPE PLAN
SHEET #	L-1 19 OF 29



SCALE 1"=80'-0"



SEE SHEET L-TS FOR
PLANTING AND
GROUND COVER LEGEND

Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan



DATE	REVISION DESCRIPTION
9/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION



VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO

JOB NUMBER
2674-0122


DATE
8/15/2024

DRAWN BY
MIB

DRAWING DESCRIPTION
FINAL LANDSCAPE PLAN

SHEET #
L-2 20 OF 29

© 2023 BY SUNFLOWER LANDSCAPES. ALL RIGHTS RESERVED.



SEE SHEET L-2

SEE SHEET L-5

SEE SHEET L-2

SEE SHEET L-3

DECORATIVE ROCK SEE LEGEND FOR TYPE

DECORATIVE ROCK SEE LEGEND FOR TYPE

RETAINING WALL HEIGHT 8' MAX. (TYPE TBD - BY BUILDER).

NO EDGING AT 2 ROCK TYPES - TYPICAL AS SHOWN (DASHED LINE).

PROP. RETAINING WALL 2' HT. ±

SCREEN WALL - BY BUILDER

SCREEN WALL - BY BU

SNOW STORAGE AREA

GREEN BAY HEIGHTS

GREEN BAY HEIGH

AMES HEIGHTS

JANESVILLE HEIGHTS

STERLING RANCH ROAD (PUBLIC NON-RES. COLLECTOR, 80' ROW)

SHOREWOOD DRIVE (Public Res. collector)

DECORATIVE ROCK SEE LEGEND FOR TYPE

IRRIGATED NATIVE SEED

IRRIGATED NATIVE SEED

IRRIGATED TURF

STEEL EDGING

IRR

1-ABM

1-MSS

DECORATIVE ROCK SEE LEGEND FOR TYPE

RETAINING WALL HEIGHT 8' MAX. (TYPE TBD - BY BUILDER).

DECORATIVE ROCK SEE LEGEND FOR TYPE

DECORATIVE ROCK SEE LEGEND FOR TYPE

RETAINING WALL HEIGHT 8' MAX. (TYPE TBD - BY BUILDER).



DECORATIVE ROCK SEE LEGEND FOR TYPE


DECORATIVE ROCK SEE LEGEND FOR TYPE

Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan

SEE SHEET L-TS
FOR PLANTING AND
GROUND COVER
LEGEND





SUNFLOWER LANDSCAPES
 LANDSCAPE ARCHITECTURE & IRRIGATION DESIGN
 RESIDENTIAL & COMMERCIAL LANDSCAPE INSTALLATION
 1922 AEROPOLAZA DRIVE
 COLORADO SPRINGS, CO 80916
 719-537-8315


DATE	REVISION DESCRIPTION
9/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION



VILLAGES AT STERLING RANCH
 A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
 BRIARGATE PARKWAY & STERLING RANCH ROAD
 COLORADO SPRINGS, CO

JOB NUMBER: 2674-0122
 DATE: 8/15/2024
 DRAWN BY: MB
 DRAWING DESCRIPTION: FINAL LANDSCAPE PLAN
 SHEET #: L-5 23 OF 29
 © 2023 BY SUNFLOWER LANDSCAPES • ALL RIGHTS RESERVED



Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan




DATE	REVISION DESCRIPTION
9/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION



VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO

JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	FINAL LANDSCAPE PLAN
SHEET #	L-6 24 OF 29



SEE SHEET L-TS FOR
PLANTING AND
GROUND COVER LEGEND

RETAINING WALL HEIGHT 2'-4"
(TYPE TBD - BY BUILDER)

IRRIGATED NATIVE SEED

NO EDGING AT 2' ROC
TYPICAL AS SHOWN (

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

DECORATIVE ROCK
LEGEND FOR TYP

IRRIGATED TURF

STEEL EDGING

DECORATIVE ROCK
LEGEND FOR TYP

Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan

CEDAR RAPIDS LOOP
(Public Res. collector)

CEDAR F
(Public R)



SUNFLOWER LANDSCAPES
LANDSCAPE ARCHITECTURE & IRRIGATION DESIGN
RESIDENTIAL & COMMERCIAL LANDSCAPE INSTALLATION
1922 AEROPOLAZA DRIVE
COLORADO 80102
719-437-2315


DATE	REVISION DESCRIPTION
9/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION





VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO

JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	FINAL LANDSCAPE PLAN
SHEET #	L-8 26 OF 29




UNPLATTED
STERLING RANCH EAST FILING NO. 5
SINGLE FAMILY RESIDENTIAL

**SEE SHEET L-TS FOR
PLANTING AND
GROUND COVER LEGEND**



Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan



SUNFLOWER LANDSCAPES
LANDSCAPE ARCHITECTURE & IRRIGATION DESIGN
RESIDENTIAL & COMMERCIAL LANDSCAPE INSTALLATION
1922 AEROPOLAZA DRIVE
COLORADO SPRINGS, CO 80916
719-537-2315

DATE	REVISION DESCRIPTION
3/10/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION




VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO

JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	FINAL LANDSCAPE PLAN
SHEET #	L-9 27 OF 29


UNPLATTED
STERLING RANCH EAST FILING NO. 5
SINGLE FAMILY RESIDENTIAL

**SEE SHEET L-TS FOR
PLANTING AND
GROUNDCOVER LEGEND**



Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan



DATE	REVISION DESCRIPTION
01/02/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions


FOR CONSTRUCTION
 NOT FOR CONSTRUCTION



VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO


JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	FINAL LANDSCAPE PLAN
SHEET #	L-10 28 OF 29

SEE SHEET L-TS FOR
PLANTING AND
GROUNDCOVER LEGEND



Villages at Sterling Ranch

County of El Paso, State of Colorado Sect. 34, Township 12S, Range 65 West
PUD Development Plan & Preliminary Plan




DATE	REVISION DESCRIPTION
01/02/2024	County comment revisions
11/14/2024	County comment revisions
12/19/2024	County comment revisions

FOR CONSTRUCTION
 NOT FOR CONSTRUCTION




VILLAGES AT STERLING RANCH
A PORTION OF SECTION 34, TOWNSHIP 12 SOUTH, RANGE 65 WEST
BRIARGATE PARKWAY & STERLING RANCH ROAD
COLORADO SPRINGS, CO


JOB NUMBER	2674-0122
DATE	8/15/2024
DRAWN BY	MB
DRAWING DESCRIPTION	PLANTING DETAILS & NOTES
SHEET #	L-11 29 OF 29




A DECIDUOUS TREE PLANTING DETAIL
NOT TO SCALE



B EVERGREEN TREE PLANTING DETAIL
NOT TO SCALE



C SHRUB PLANTING DETAIL
NOT TO SCALE



D PERENNIAL PLANTING DETAIL
NOT TO SCALE

LANDSCAPE CONTRACTOR NOTES

- STOCKPILE SOIL (IF APPLICABLE) ON SITE AS SHOWN ON PLANS. STOCKPILED SOIL TO BE USED FOR FILL SOIL FOR LANDSCAPE AREAS AS NEEDED.
- REMOVE WEEDS, DEAD TREES / SHRUBS, DEBRIS FROM SITE PRIOR TO BEGINNING LANDSCAPE CONSTRUCTION.
- PLANT QUANTITIES IN PLANT LEGEND ARE FOR CONVENIENCE ONLY. CONTRACTOR TO INSTALL ALL PLANT MATERIAL PER PLANS.
- INSTALLATION OF PLANT MATERIALS TO BE IN ACCORDANCE WITH THE ASSOCIATED LANDSCAPE CONTRACTORS OF COLORADO HANDBOOK (ALCC), 2007 OR CURRENT EDITION FOR ALL LANDSCAPE CONSTRUCTION ON THIS SITE.
- LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR THEFTS OR DAMAGE TO ALL PLANT MATERIAL AFTER PLANT MATERIAL IS DELIVERED TO THE JOB SITE.
- CONTRACTOR IS RESPONSIBLE FOR CONTACTING LANDSCAPE ARCHITECT FOR ALL REQUIRED INSPECTIONS. PROVIDE 48 HOURS MINIMUM NOTICE PRIOR TO SCHEDULE INSPECTIONS. INSPECTIONS TO INCLUDE:
 - PLANT PLACEMENT, PLANT SPECIES, MATERIAL SIZE AND QUALITY.
 - HARDSCAPE MATERIAL PLACEMENT / PLANTING BED EDGING.
 - IRRIGATION MAIN LINE / HEAD PLACEMENT INSPECTION (AS APPLICABLE).

LANDSCAPE INSTALLATION NOTES

- EDGING FOR TURF, PLANTING BEDS, ROCK, OR MULCH AREAS TO BE ROLL TOP STEEL EDGING WITH PINS OR APPROVED EQUAL. EDGING TO BE EXPOSED 1/2" +/- ABOVE FINISHED GRADES. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- SOD TO BE BLUEGRASS SOD. LAY SOD WITH TIGHT STAGGERED EDGES. (IF APPLICABLE)
- ALL SEEDED TURF / SOD AREAS TO BE AMENDED WITH: 4 CUBIC YARDS OF ORGANIC SOIL AMENDMENT PER 1,000 SF FILLED INTO THE TOP 6" OF SOIL. (IF APPLICABLE)
- LANDSCAPE WEED FABRIC TO BE INSTALLED PRIOR TO INSTALLING ROCK. INSTALL FABRIC STAPLES AT 5" O.C. SEAMS IN FABRIC TO BE OVERLAPPED 6" MIN. AND SECURED WITH STAPLES. (IF APPLICABLE)
- ROCK OR MULCH COVER SHALL BE CONTINUOUS UNDER ALL SHRUBS THROUGHOUT THE PROJECT SITE. INSTALL A MULCH RING AROUND ALL PLANT MATERIAL IN ROCK AREAS AS FOLLOWS: TREES = 36" DIAMETER MULCH RING, SHRUBS = 18" DIAMETER MULCH RING, PERENNIALS AND ORNAMENTAL GRASSES = 12" MULCH RING. MULCH RINGS TO BE CASCADE MULCH 3" IN DEPTH WITH NO WEED FABRIC NOTE: ALL TREES IN TURF AREAS TO RECEIVE A 24" DIAMETER MULCH RING. (IF APPLICABLE)
- ALL BOULDERS (IF APPLICABLE) TO BE BURIED 1/3 BELOW GRADE TO PROVIDE A NATURAL APPEARANCE.
- CONTRACTOR TO INSTALL ALL LANDSCAPE AS SHOWN ON THIS PLAN AND MAKE ANY ADJUSTMENTS NECESSARY DUE TO FIELD VARIATIONS OR ANY UTILITY CHANGES OR DEVIATIONS. MAJOR DEVIATIONS FROM THIS PLAN ARE TO BE APPROVED BY OWNERS REPRESENTATIVE OR LANDSCAPE ARCHITECT.
- EXISTING SOIL IN ALL PLANTING BED AREAS TO BE AMENDED WITH THE FOLLOWING: 4 CUBIC YARDS OF ORGANIC SOIL AMENDMENT PER 1,000 SF FILLED INTO TOP 6" OF SOIL.
- IF APPLICABLE -ALL PARKING LOT ISLAND PLANTERS SHALL BE TILLED / REMOVED TO A DEPTH OF 30" AND REPLACED WITH GRADE 'B' TOPSOIL OR EQUAL.
- ALL NURSERY PLANT MATERIAL BOTANICAL NAME TAGS TO REMAIN ATTACHED TO THE PLANT MATERIAL. AFTER FINAL INSPECTION THEY ARE TO BE REMOVED.
- LANDSCAPE CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT IF DOWNSPOUTS OR STORM DRAINAGE FROM ADJACENT LOTS WILL ADVERSELY AFFECT LANDSCAPED AREAS ON THESE PLANS.

EXISTING TREE PROTECTION (IF APPLICABLE)
ANY EXISTING TREES OR PLANT MATERIAL NOTED TO BE PROTECTED ON THESE PLANS ARE TO BE PROTECTED FROM CONSTRUCTION DAMAGE. CONTRACTOR WILL TAKE RESPONSIBILITY FOR ANY DAMAGE TO EXISTING PROTECTED TREES OR LANDSCAPE.

ANY DAMAGE TO EXISTING TREES OR PLANT MATERIAL CALLED OUT TO BE PROTECTED SHALL BE REPLACED WITH EQUIVALENT PLANT MATERIAL.

BARK BEETLE PROTECTION NOTE (IF APPLICABLE)
LANDSCAPE CONTRACTOR TO PROVIDE PROTECTION FOR ALL NEW PINE TREES FOR BARK BEETLE PROTECTION. INSPECT ALL PINE TREES PRIOR TO PLANTING AND SPRAY TREES WITH THE FOLLOWING:
--ASTROBRAND PERMITHRIN
--APPLY TREATMENT 2 TIMES A YEAR FOR TWO CONSECUTIVE YEARS PER MANUFACTURER'S GUIDELINES

SLOPE PROTECTION (IF APPLICABLE)
CONTRACTOR TO INSTALL EROSION CONTROL BLANKETS OR EQUAL ON SEEDED SLOPES 3:1 AND STEEPER. SECURE BLANKETS TO SLOPE PER MANUFACTURER'S RECOMMENDATIONS.

EROSION CONTROL BLANKET TO CONTAIN 100% AGRICULTURAL STRAW BLANKET WITH PHOTO-DEGRADABLE NETTING ON BOTH SIDES.

CONTRACTOR TO PROVIDE 4-8" DIAMETER COBBLE (WITH LANDSCAPE FABRIC) FOR ALL CURB INLETS INTO DETENTION AREAS IF APPLICABLE. PROVIDE A SWALE FROM INLET TO DETENTION AREA A MINIMUM OF 2' WIDE AND MAXIMUM 3' WIDE. (IF APPLICABLE)

SEEDING NOTES

IRRIGATED NATIVE SEED TO BE EL PASO COUNTY CONSERVATION DISTRICT ALL-PURPOSE LOW GROW MIX 42 LBS/ACRE USING A ONE STEP HYDRO-SEED PROCESS. SEE BELOW FOR WHAT THE MIX CONTAINS.

-BUFFALOGRASS	25%
-GRAMMA BLUE	20%
-GRAMMA SIDEOATS	29%
-GREEN NEEDLEGRASS	5%
-WHEATGRASS WESTERN	20%
-DROPSSEED SAND	1%

SOIL IN IRRIGATED SEED AREAS TO BE AMENDED WITH: 1/3 HIGH QUALITY TOP SOIL, 2/3 COW MANURE, AND 1/3 NATIVE SOIL AT 4 C.Y./1000 SF FILLED INTO TOP 4-6" OF SOIL PRIOR TO SEEDING. 2-3 WEEKS AFTER EMERGENCE ADD SUPER CROP FERTILIZER 20-20-10 AT 4 LBS PER 1,000 SF. ADD 1 LB. NITROGEN PER 1000 SF IN MID TO LATE JUNE, IN EARLY TO MID AUGUST, AND LATE SEPTEMBER.

IRRIGATED NATIVE SEED TO BE EL PASO COUNTY CONSERVATION DISTRICT ALL-PURPOSE MIX 42 LBS/ACRE USING A ONE STEP HYDRO-SEED PROCESS (AT POND BOTTOM). SEE BELOW FOR WHAT THE MIX CONTAINS.

-BIG BLUESTEM	20%	-SWITCHGRASS	10%
-GRAMMA BLUE	10%	-PRAIRIE SANDREED	10%
-GREEN NEEDLEGRASS	10%	-YELLOW INDIANGRASS	10%
-WHEATGRASS WESTERN	20%	-GRAMMA SIDEOATS	10%

SOIL IN IRRIGATED SEED AREAS TO BE AMENDED WITH: 1/3 HIGH QUALITY TOP SOIL, 2/3 COW MANURE, AND 1/3 NATIVE SOIL AT 4 C.Y./1000 SF FILLED INTO TOP 4-6" OF SOIL PRIOR TO SEEDING. 2-3 WEEKS AFTER EMERGENCE ADD SUPER CROP FERTILIZER 20-20-10 AT 4 LBS PER 1,000 SF. ADD 1 LB. NITROGEN PER 1000 SF IN MID TO LATE JUNE, IN EARLY TO MID AUGUST, AND LATE SEPTEMBER.

ANY EXISTING SEEDED AREAS THAT ARE DISTURBED NEAR PROPERTY BOUNDARIES TO BE SEEDED WITH THE ALL PURPOSE MIX USING A ONE STEP HYDRO-MULCH.

ANY BARE AREAS LARGER THAN A SQUARE FOOT AFTER SEED GERMINATION TO BE SEEDED TO FILL IN SUCH AREAS.