

# Final Drainage Report

# **Freedom Springs**

Project No. 61090

November 8, 2018

PCD File No.: PPR-18-040

## **Final Drainage Report**

for

Freedom Springs
Multifamily Residential Community

Project No. 61090

### November 8, 2018

prepared for

Freedom Springs, LLC 305 W. Commercial Street Springfield, MO 65803 417.720.1577

prepared by

MVE, Inc. 1903 Lelaray Street, Suite 200 Colorado Springs, CO 80909 719.635.5736


Copyright © MVE, Inc., 2019

61090-Freedom Springs-Final Drainage Report.odt

# Statements and Acknowledgments

#### **Engineer's Statement**

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.



#### **Developer's Statement**

I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

Richard Manzardo
Authorized Representative
Freedom Springs, LLC
305 W. Commercial Street
Springfield, MO 65803

# Date

#### **El Paso County**

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

by El	Approved Elizabeth Nijkamp Paso County Planning and Community Development behalf of Jennifer Irvine, County Engineer, ECM Administrator 01/29/2019 4:15:19 PM	
Jennif	er Irvine, P.E.,	Date
County	y Engineer / ECM Administrator	

# Contents

S	tatements and Acknowledgments	iii
C	ontents	٧
Fi	inal Drainage Report	1
1	General Location and Description	1
	1.1 Location	1
	1.2 Description of Property	1
2	Drainage Basins and Sub-Basins	2
	2.1 Major Basin Descriptions	2
	2.2 Sub-Basin Description	2
3	Drainage Design Criteria	3
	3.1 Development Criteria Reference	3
	3.2 Hydrologic Criteria	3
4	Drainage Facility Design	4
	4.1 General Concept	4
	4.2 Specific Details	4
	4.3 Erosion Control	7
	4.4 Water Quality Enhancement Best Management Practices	7
5	Opinion of Probable Cost for Drainage Facilities	8
6	Drainage and Bridge Fees	8
_	Canalysian	

Re	eferences	9
$\mathbf{A}_{\mathbf{j}}$	ppendices	10
8	General Maps and Supporting Data	10
9	Hydrologic Calculations	11
10	Hydraulic Calculations	33
11	Report Mans	11

# Final Drainage Report

The purpose of this Final Drainage Report is to identify drainage patterns and quantities within and affecting the proposed Freedom Springs project located in Lot 2, Western Hills Filing No. 2. This project is the development of the existing platted lot having an area of approximately 3.87± Acres with a multi-family use. The report will "identify specific solutions to problems on-site and off-site resulting from the proposed project.¹ The report and included maps present results of hydrologic and drainage facilities analyses. The report will discuss the recommended drainage improvements to the site and identify drainage requirements relative to the proposed project. This report has been prepared and submitted in accordance with the requirements of the El Paso County land development approval process. An Appendix is included with this report with pertinent calculations and graphs used in the drainage analyses and design.

#### 1 General Location and Description

#### 1.1 Location

The proposed Freedom Springs site is located within the southeast one-quarter of Section 7, Township 14 South, Range 65 west of the 6th principal meridian in El Paso County, Colorado. The 3.87± acre site is situated on the north side of Western Drive, east of Hathaway Drive and west of Dale Road. The proposed site is platted as Lot 2, Western Hills Filing No. 2 in 1994. A **Vicinity Map** is included in the **Appendix**.

The unplatted property to the southwest of the site contains a manufacturing facility and is zoned M (Industrial). The property to the northwest of the site, platted as a portion of Aerospace Gardens, is zoned R-4 (Planned Development) and used as multi-family residential. A Multi-family residential property, zoned R-4, and platted as Lots 1 and 3, Block 1, Western Hills Subdivision and Lot 1 Western Hills Subdivision Filing No. 2 is adjacent to the site on the north. Western Drive, a paved public road with concrete curb and gutter in a 60 foot right-of-way, borders the site along the south. A golf course, platted as Lot 1, Cimarron Southeast Filing No. 2B is adjacent to Western Drive on the northeast. Vacant commercial lots, platted as Lot 1, Cimarron Southeast Filing No. 2C, is adjacent to the Western Drive on the southwestern side.

#### 1.2 Description of Property

The Freedom Springs project contains 3.87± acres and is zoned R-4 (Planned Development), which is an obsolete county zone. The property contains no structures, but has a paved access road in and easement and various utilities with easements.

The site is covered with native prairie grasses and weeds in good condition. There are also sparse trees around the site. The existing site topography slopes to the south towards Western Drive with grades that range from 1% to 6% with isolated areas of up to 20%.

There are no major drainageways in the Freedom Springs site. All storm runoff flows south or southeast to Western Drive that collects the flows and conveys it to the northeast. There is no storm drain system in the Western Drive or or the surrounding area. The site is located in the Sand Creek

<sup>1</sup> DCM

#### Final Drainage Report

Major Drain Basin. The flows from the site continue northeast in Western Drive and eventually enters the East Fork of Sand Creek, continuing southwest.

According to the National Resource Conservation Service, the dominant soil in the immediate area of the Freedom Springs site is Blakeland loamy sand (map unit 8). The Blakeland loamy sand is typically deep and somewhat excessively drained. Permeability is rapid, surface runoff is slow, and the hazard of erosion is moderate. Blakeland loamy sand is classified as being part of Hydrologic Soil Group A.A portion of the **Soil Map** and data tables from the National Cooperative Soil Survey and relevant **Official Soil Series Descriptions (OSD)** are included in the **Appendix**.<sup>2</sup>

The current Flood Insurance Study of the region includes Flood Insurance Rate Maps (FIRMs), effective March 17, 1997. <sup>4 5</sup> The project site is included in Community Panel Number 08041C0754 F of the FIRMs for El Paso County, Colorado. No portion of the site lies within FEMA designated Special Flood Hazard Areas (SFHAs). An excerpt of the current **FEMA Flood Insurance Rate Maps** with the site delineated is included in the **Appendix**.

A new multi-family residential facility will be constructed on the site. The proposed building and parking area will be located on the western side if the site. The development will include a new building, parking lot, landscaping and recreational open area. Also, the east side of the site will be improved with a new Full Spectrum Sand Filter Basin (FS SFB) which will collect, detain and treat the flows from the new development.

#### 2 Drainage Basins and Sub-Basins

#### 2.1 Major Basin Descriptions

Freedom Springs site is located in the Sand Creek Major Drainage Basin (FOFO4000) on the east side of Colorado Springs, which contains properties in both City of Colorado Springs and unincorporated El Paso County jurisdictions. The basin is a studied basin with an approved and operative Drainage Basin Planning Study (DBPS). The Basin stretches for approximately 17 miles on the east side of Colorado Springs and drains from northeast to southwest into Fountain Creek at a point just north of the crossing of Interstate 25 and US Highway 85-87. The site is located in the southeastern portion of the Sand Creek Major Drainage Basin, in the East Fork sub-area and eventually drains into the East Fork of Sand Creek. A copy of a portion of the "*Drainage Area Identification Study*" map, showing the site location within the Basin is included in the **Appendix**. <sup>6</sup>

The Drainage Basin Planning Study for the Sand Creek Major Drainage Basin was completed in 1996 by Kiowa Engineering Corporation.<sup>7</sup> The site is contained within sub-basin 3, located just upstream of Design Point No. 3, as indicated in the 1996 report. There are not drainage improvements noted in the DBPS for the site.

A drainage report for Western Hills Subdivision was prepared in 1971 by G.L. Williams and Partners, LTD. No other drainage reports for this or any of the adjacent properties were available for review during the course of preparing this drainage report.

#### 2.2 Sub-Basin Description

#### 2.2.1 Existing Drainage Patterns (Off-Site)

Off-site drainage flows enter the north edge of the Freedom Springs property from two off-site drainage basins located north of the site. The hydrologic analyses used in the drainage design of the proposed subdivision considered the existing Land Use Conditions of the offsite sub-basins. The off-site drainage sub-basins are depicted on the included **Existing Drainage Basin Map**.

<sup>2</sup> WSS

<sup>3</sup> OS

<sup>5</sup> FIRM, Map No. 08041C0754 F

<sup>6</sup> Drain. Area Ident. Study

<sup>7 1996</sup> DBPS

Existing off-site sub-basin OS1 is located north of the western portion of the site (west of the existing payed access drive), and contains an existing multi-family residential development. The basin runoff flows south towards the site and enters exiting sub-basin A1 by way of the existing paved access drive. These flows continue to drain south towards Western Drive in the sub-basin A1, but remain mostly separated from sub-basin A1 runoff. The flows enter Western Drive and flow northeast in the street.

Existing off-site sub-basin OS2 is located north of the eastern portion of the site (west of the existing paved access drive). The sub-basin contains a part of the existing multi-family residential development, including the clubhouse and swimming pool area. The basin runoff flows southeast towards the site and enters exiting sub-basin B1 by overland sheet flow. These flows enter the site and join other flows generated in sub-basing B1 and continue to drain southeast towards Western Drive.

#### 2.2.2 Existing Drainage Patterns (On-Site)

The site is mostly undeveloped, except for the existing paved access drive that extends north from Western Drive to the existing multi-family development north of the site. The entire site drains from north to south and southeast to Western Drive. However, the existing paved drive conveys most of the offsite flows from existing off-site sub-basing OS1 to Western Drive. All off-site and on-site runoff reaches Western Drive and travels northeast in the existing concrete curb and gutter. There is no storm drain in Western Drive adjacent to the site, but two storm drain inlets located northeast of the site collect storm flows which drain into the pond adjacent to the south side of Western Drive. existing drainage patterns for the site are described by two on-site basins. The drainage sub-basins are shown on the included Existing Drainage Map.

Existing sub-basin A1 is located on the western side of the site and contains open field (meadow) and paved access drive along the east side of the basin. Sub-basin A1 accepts the flows form offsite sub-basin OS1. These offsite flows travel south through the site, mostly contained in the payed drive, to Western Drive on the south. Storm runoff from sub-basin A1 also flows south to Western Drive and enters the street. Once in the street, all the flows from OS1 and A1 travel northeast in the street.

Existing sub-basin B1 contains the eastern portion of the property and contains grassed field (meadow) and trees. The basin accepts the sheet flow from off-site sub-basin OS2 on the north. The combined flows from drain toward Western Drive on the southeast, joining the flows from from OS1, A1, and other off-site flows in the street. The combined flows continue northeast in the street to an off-site inlet that drains into the existing pond located on the south side of Western Drive. These flows eventually reach the east fork of sand creek and continue to the southeast in the creek.

#### 3 Drainage Design Criteria

#### 3.1 Development Criteria Reference

This Final Drainage Report for Freedom Springs has been prepared according to the report guidelines presented in the latest edition of El Paso County Drainage Criteria Manual (DCM)8. The County has also adopted portions of the City of Colorado Springs Drainage Criteria Manual Volumes 1 and 2, especially concerning the calculation of rainfall runoff flow rates. <sup>9</sup> <sup>10</sup> The hydrologic analysis is based on a collection of data from the DCM, the NRCS Web Soil Survey11, Existing topographic data and proposed site plan by by Land Development Consultants, Inc.

#### 3.2 Hydrologic Criteria

For this Final Drainage Report, the Rational Method as described in the Drainage Criteria Manual has been used for all Storm Runoff calculations, as the development and all sub-basins are less than

DCM Section 4.3 and Section 4.4

<sup>10</sup> CS DCM Vol 2

<sup>11</sup> WSS

#### 4 Final Drainage Report

130 acres in area. "Colorado Springs Rainfall Intensity Duration Frequency" curves, Figure 6-5 in the DCM, was used to obtain the design rainfall values; a copy is included in the **Appendix**. The "Overland (Initial) Flow Equation" (Eq. 6-8) in the DCM, and Manning's equation with estimated depths were used in time of concentration calculations. "Runoff Coefficients for Rational Method", Table 6-6 in the DCM, was utilized as a guide in estimating runoff coefficient and Percent Impervious values; a copy is included in the Appendix. Peak runoff discharges were calculated for each drainage sub-basin for both the 5-year storm event and the 100-year storm event with the Rational Method formula, (Eq. 6-5) in the DCM.<sup>12</sup>

The Water Quality Control Volume procedure, Section 3.3 of the Urban Drainage and Flood Control District Drainage Criteria Manual, Volume 3 (UDFCD) was used for water quality volume calculations with the aid of the worksheet "UD-BMP v3.06" spreadsheet developed by the Urban Drainage and Flood Control District. 13 14 Full Spectrum Detention utilizing the Excess Urban Runoff Volume (EURV) concept was sized and storm routing calculations were performed in accordance with Urban Drainage and Flood Control District Drainage Criteria Manual, Volume 2 using the aid of the detention design spreadsheet, "UD-Detention v3.07", developed by the Urban Drainage and Flood Control District. 15 16

#### 4 Drainage Facility Design

#### 4.1 General Concept

The intent of the drainage concept presented in this Final Drainage Report is to maintain the existing drainage patterns & quantities on the site. Major and minor storm flows will continue to be safely conveyed through the site and downstream. The runoff from all developed areas will drain to the proposed Full Spectrum Sand Filter Basin (FS SFB). A proposed private on-site storm drain system will collect the flow from the various developed on-site sub-basin and convey them to the proposed FS SFB. The developed flows will be detained and released to Western Drive at flow rates less than the calculated existing flow rates.

The existing and proposed drainage hydrologic conditions are described in more detail below. Input data and results for all calculations are included in the **Appendix**. Drainage maps for the hydrology are also included in the **Appendix**.

#### 4.2 Specific Details

#### 4.2.1 Existing Hydrologic Conditions

The off-site drainage area north of the western portion of the site, sub-basin OS1, contains the existing adjacent multi-family residential development known as Western Hills Apartments. The subbasin is 2.84 acres in area and drains southerly towards the northeast corner of existing on-site subbasin A1 at the paved access drive that extends from Western Drive. Basin OS1 generates peak storm runoff discharges of  $Q_5 = 4.7$  cfs and  $Q_{100} = 10.4$  cfs (existing flows). These flows continue south through sub-basin A1 to Western Drive.

Existing off-site sub-basin OS2 is located north of the eastern portion of the site and also contains a portion of existing Western Hills Apartments. The sub-basin is 0.57 acres in area and drains southeasterly towards the northeast corner of the site with peak discharges of Q<sub>5</sub> = 1.1 cfs and Q<sub>100</sub> = 2.5 cfs (existing flows). These flows enter existing on-site sub-basin B1 and continue southeast towards Western Drive.

Existing on-site sub-basin A1 is 2.72 acres in area and comprises the western portion of the site. containing the existing paved access drive and open field area. The sub-basin accepts the offsite flows from sub-basin OS1 as described above. Sub-basin A1 produces peak discharges of Q<sub>5</sub> = 1.7 cfs and  $Q_{100} = 7.2$  cfs (existing flows) which drain southerly towards Western Drive. The combined

UDFCDV.3

<sup>14</sup> UDFCD 15 UDFCD V.2

<sup>16</sup> UDFCD

flow rate of the runoff from sub-basins OS1 and A1 are  $Q_5 = 6.2$  cfs and  $Q_{100} = 17.0$  cfs (existing flows). These flows enter Western all along the street frontage, however concentrated flows, mostly from off-site sub-basin OS1, enter the street at the existing drive connection. The combined flows of continue northeast in the street.

Existing sub-basin B1 (1.16 acres) is comprised of the east side of the site, east of the existing paved access drive. The sub-basin accepts the off-site sheet flows from sub-basin OS2. Sub-basin B1 contains open field area and drains southeast towards Western Drive. The peak discharges generated by sub-basin B1 are  $Q_5 = 0.4$  cfs and  $Q_{100} = 2.8$  cfs (existing flow), which joins with the off-site flows for combined peak discharges of  $Q_5 = 1.4$  cfs and  $Q_{100} = 5.0$  cfs (existing flow). These flows enter Western Drive and are directed to the northeast in street.

The existing combined total flows entering Western Drive from the off-site and on-site basins are  $Q_5$  = 7.6 cfs and  $Q_{100}$  = 22.0 cfs (existing flow).

Western Drive an existing public 39 ft wide, paved street with concrete curb on both sides in a 60' right-of-way. The roadway drains to the northeast and does not contain a storm drain system adjacent to the site. However, there are two curb inlets located approximately 110 feet to the northeast of the site. The inlets drain street flows to the existing pond adjacent to the south side of the road.

The **Existing Drainage Map** depicts the existing topographic mapping, drainage basin delineations, drainage patterns, existing streets, drainage facilities, and runoff quantities with a data table including drainage areas and flow rates.

#### 4.2.2 Proposed Hydrologic Conditions

The off-site drainage basin, OS1 (2.84 acres), will continue to drain south toward the site as in existing conditions. The discharges are  $Q_5 = 4.7$  cfs and  $Q_{100} = 10.4$  cfs (proposed flow), which drain to the north edge of the site and into proposed sub-basins H1.

Proposed sub-basin H1 (0.45 acres) consists of the north edge of the site together with with the improved access drive to Western Drive. This sub-basin will accept the flows from off-site sub-basin OS1, which will continue south in the access drive to Western Drive as in existing conditions. Sub-basin H1 will produce runoff at peak flow rates of  $Q_5$  = 1.6 cfs and  $Q_{100}$  = 3.1 cfs (proposed flow), which drains to the access drive and then south towards Western Drive. The combined discharges of sub-basins OS1 and H1 are  $Q_5$  = 5.7 cfs and  $Q_{100}$  = 12.3 cfs (proposed flow). A proposed single Type 16 combination inlet at Design Point 4 (DP4) will collect the developed 100-year discharge from on-site sub-basin H1 of 3.1 cfs and allow the existing offsite flows from sub-basin OS1 to continue to flow by and reach Western Drive as in existing conditions. The collected flows will be carried to the proposed FS SFB located east of the access drive.

Proposed sub-basin A1 (0.63 acres) will consist of the paved parking area on the south side of the proposed building. The discharges generated by A1 are  $Q_5$  = 2.7 cfs and  $Q_{100}$  = 4.9 cfs (proposed flow), which drain southerly in the parking lot to a proposed double Type 16 combination inlet in sump condition at DP1. The collected storm runoff will be conveyed to the proposed FS SFB in the proposed private storm drain line.

Proposed sub-basin B1 (0.17 acres) is parking lot area located east of sub-basin A1. Sub-basin B1 drains to a proposed single Type 16 combination inlet in sump condition at DP2 with peak discharges of  $Q_5 = 0.7$  cfs and  $Q_{100} = 1.3$  cfs (proposed flow). The inlet will collect up to the 100-year flows and the flows will be conveyed to the FS SFB in the storm drain system.

Proposed sub-basin C1 (0.11 acres) is comprised of the parking, drive and landscape area located north of sub-basin B1. The discharges from sub-basin C1 are  $Q_5$  = 0.4 cfs and  $Q_{100}$  = 0.8 cfs (proposed flows) which drain south to DP3, being the location of a proposed single Type 16 combination inlet on grade. The proposed inlet will collect flows of  $Q_5$  = 0.3 cfs and  $Q_{100}$  = 0.5 cfs and bypass flows of  $Q_5$  = 0.1 cfs and  $Q_{100}$  = 0.3 cfs to sub-basin H1.

Proposed sub-basin D1 (0.36 acres) consists of the proposed building footprint on the western side of the site. The sub-basin generates storm runoff peak discharges of  $Q_5 = 1.4$  cfs and  $Q_{100} = 2.6$  cfs

(proposed flows). Building roof drains will direct all flows to the underground drainage system and then to the FS SFB.

Proposed sub-basin E1 (0.17 acres) will consist of the recreation yard on the north side of the building. The discharges generated by E1 are  $Q_5$  = 0.1 cfs and  $Q_{100}$  = 0.5 cfs (proposed flow), which drain to a low point in the center of the basin (DP5). A proposed grated area inlet in sump condition will collect the flows which will be conveyed to the proposed FS SFB in the proposed private storm drain line.

Proposed sub-basin F1 (0.17 acres) is also part of the recreation yard on the north side of the building. Sub-basin F1 drains to a proposed area inlet in sump condition at DP6 with peak discharges of  $Q_5 = 0.3$  cfs and  $Q_{100} = 0.8$  cfs (proposed flow). The inlet will collect up to the 100-year flows and the flows will be conveyed to the FS SFB in the storm drain system.

Proposed sub-basin G1 (0.58 acres) contains open landscape area and the proposed FS SFB located on the east side of the existing paved access drive at DP7. The discharges from sub-basin G1 are  $Q_5$  = 0.2 cfs and  $Q_{100}$  = 1.3 cfs (proposed flows) which drain south into the FS SFB at DP7. The pond also collects the flows from sub-basins A1, B1, C1, D1, E1, F1, G1 and H1. The combined peak discharges of all in-flowing basins are  $Q_5$  = 7.2 cfs and  $Q_{100}$  = 15.2 cfs (proposed flow). The proposed FS SFB will treat and detain the developed flows and release them to Western drive by way of a outlet pipe and County Standard curb opening with steel cover. The released flows are  $Q_5$  = 0.2 cfs and  $Q_{100}$  = 1.1 cfs (proposed flow).

Proposed sub-basin J1 (0.46 acres) is comprised of open yard and landscape area adjacent to Western Drive on the westerly side of the site. The proposed landscaping will consist of trees, shrubs in wood mulch, and non-irrigated native grass. The basin will drain south by sheet flow into Western Drive as this area does in the existing condition. Sub-basin J1 produces peak runoff discharges of  $Q_5 = 0.1$  cfs and  $Q_{100} = 1.1$  cfs (proposed flows).

Proposed sub-basin M1 (0.13 acres) consists of narrow landscape area on the west edge of the site. The area drains westerly into the adjacent site and generates storm runoff peak discharges of  $Q_5$  = 0.1 cfs and  $Q_{100}$  = 0.4 cfs (proposed flows). Most of the area of this sub-basin historically drains into the site to the southeast. In the developed condition, this area will drain offsite to the west and then south to Western Drive. The area of this basin is minor, is landscaped pervious area, and results in runoff of negligible magnitude. The flows leaving the site from this basin will not present problems for the adjacent or downstream properties.

The off-site drainage basin, OS2 (0.57 acres), will continue to drain southeast toward the site as in existing conditions. The discharges are  $Q_5$  = 1.1 cfs and  $Q_{100}$  = 2.5 cfs (proposed flow), which drain onto the site into proposed sub-basins L1.

Proposed sub-basin L1 (0.45 acres) consists of open landscape area along the east edge of the site. Grading contours will remain the same as existing conditions. Sub-basin L1 will continue to accept the off-site flows from sub-basin OS2. The discharges generated by L1 are  $Q_5 = 0.1$  cfs and  $Q_{100} = 1.1$  cfs (proposed flow), which drain to the southeast towards Western Drive. The combined flows of OS2 and L1 are  $Q_5 = 1.1$  cfs and  $Q_{100} = 3.3$  cfs (proposed flow), which enter Western Drive along the street frontage by sheet flow.

Proposed sub-basin K1 (0.15 acres) is the south edge of the eastern portion of the site. This basin consist of the landscaped area between the proposed FS SFB and Western Drive which drains southwest into the street. Proposed peak runoff discharges from this basin are  $Q_5 = 0.1$  cfs and  $Q_{100} = 0.4$  cfs (proposed flow).

The combined total developed flows entering Western Drive from the off-site and on-site basins are  $Q_5 = 4.7$  cfs and  $Q_{100} = 14.1$  cfs (proposed flow). These flows represent a decrease of 2.9 cfs in the 5-year rainfall event and a decrease of 7.9 cfs in the 100-year event. The flows that enter Western Drive will continue to drain northeast in the street to the existing inlets located northeast of the site.

#### 4.2.3 Proposed Drainage Facilities

The proposed on-site storm drain system will be owned and maintained by Freedom Springs. The pipe system will be 6", 12" and 18" HDPE material. The proposed inlets will be Type 16 combination inlets with concrete boxes and adjustable steel grate and curb openings. The area inlet will be PVC and non-traffic bearing located in landscaped areas. The proposed pipe system discharges into the Full Spectrum Sand Filter Basin, which is designed to detain the WQCV, EURV and 100-year developed runoff volumes. The proposed FS Sand Filter Basin has storage volume of 0.281 acrefeet. The facility is located in Type A soils and will be full-infiltration type. The EURV and 100-year flows will be regulated by a concrete outlet box with steel orifice plate and outlet pipe. The facility will have an emergency spillway with 6' bottom width discharging to Western Drive and protected by riprap lining.

#### 4.3 Erosion Control

During future construction, best management practices (BMP's) for erosion control will be employed based on the previously referenced City of Colorado Springs Drainage Criteria Manual Volume 2 and the Erosion Control Plan to minimize erosion from the site. The BMP's will remain in place until the site is stabilized with the new hard surfacing or landscape seeding, planting and cover materials. Also, BMP's will be utilized as deemed necessary by the contractor, engineer, owner, or County inspector and are not limited to the measures described on the Erosion Control Plan.

#### 4.4 Water Quality Enhancement Best Management Practices

The Full Spectrum Sand Filter Basin described above will provide storage for the WQCV, EURV and developed 100-year runoff volume for the site. A Grading and Erosion Control Plan for the construction of the site has been prepared in accordance with the provisions of the County's Engineering Criteria Manual. Placement of construction stormwater BMP's will as required by the plan will limit soil erosion and deposition by stormwater flowing over the site.

The El Paso County Engineering Criteria Manual (Appendix I, Section I.7.2) requires the consideration of a "Four Step Process for receiving water protection that focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainageways, and implementing long term source controls". The Four Step Process is incorporated in this project and the elements are discussed below.

- 1) Runoff Reduction Practices are employed in this project. Impervious surfaces have been reduced as much as practically possible. The parking lot contains landscape islands and the entire east side of the site will remain as pervious surface.
- 2) All drainage paths on the site are stabilized with pavement or appropriate landscape treatment. The Full Spectrum Sand Filter Basin will intercept flows from developed areas. Additionally, the pond outflow point will be stabilized with outlet protection.
- 3) The project contains no potentially hazardous uses. All developed areas drain into a proposed a WQCV BMP.
- 4) The site contains no storage of potentially harmful substances or use of potentially harmful substances. No Site Specific or Other Source Control BMP's are required.

The total area of the site is 3.87 acres. An existing paved access drive splits the lot into the east and west portions. All areas to be developed with impervious building or paved areas will be collected in the proposed storm drain inlets and directed to the proposed Full Spectrum Detention Sand Filter Basin (FSD SFB) on the west side of the site, except 0.08 acres of the existing paved access drive that is not possible to direct to the pond due to grade elevations. A total of 2.56 acres out of the 3.87 acres drains to the FSD SFB. Other areas of the site do not drain to the pond. Other than the 0.08 acres of existing paved area already discussed, these areas are unpaved pervious landscape areas of the site totaling 1.19 acres. An ECM Deviation Request will be processed to allow for the landscape area to not receive WQCV treatment. As the design volume of WQCV treatment is determined based on percent impervious, the required treatment volume for ground having 0% imperviousness is 0.0 cubic feet (no WQCV required).

#### 5 Opinion of Probable Cost for Drainage Facilities

There are no public drainage improvements associated with this project. Costs for the private non-reimbursable drainage improvements for this project are listed in the table below:

Freedom Springs Pr	ivate Drainage	Costs	(Non-Reimbursab	e)
Item	Quantity	Unit	Unit Cost	Cost
HDPE Storm Drain Pipe with Appurtenances	1040	LF	\$45.00	\$46,800
Type 16 Combination Inlets	4	EA	\$3,800.00	\$15,200
Sand Filter Basin (Full Spectrum)	1	EA	\$10,500.00	\$10,500
GRAND TOTAL				\$72,500.00

#### 6 Drainage and Bridge Fees

The site is not being platted. No Drainage or Bridge Fees are due for this project.

#### 7 Conclusion

This Final Drainage Report presents existing and proposed drainage conditions for the proposed Freedom Springs project. The development will have negligible and inconsequential effects on the existing site drainage and drainage conditions downstream. Full Spectrum Detention and Water Quality treatment will be provided. A Permanent BMP Maintenance Agreement and Easement is being provided for this project. Also, an Operations and Maintenance Manual (O&M Manual) is being provided. The proposed project will not, with respect to stormwater runoff, negatively impact the adjacent properties and downstream properties.

# References

City of Colorado Springs/El Paso County Drainage Criteria Manual. City of Colorado Springs, Department of Public Works, Engineering Division; HDR Infrastructure, Inc.; El Paso County, Department of Public Works, Engineering Division (Colorado Springs: City of Colorado Springs, Revised November 1991).

NRCS Official Soil Series Descriptions. United States Department of Agriculture, Natural Resources Conservation Service

("http://soils.usda.gov/technical/classification/osd/index.html", accessed March, 2018).

NRCS Web Soil Survey. United States Department of Agriculture, Natural Resources Conservation Service ("http://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx", accessed March 2018).

Flood Insurance Rate Map. Federal Emergency Management Agency, National Flood Insurance Program (Washington D.C.: FEMA, March 17, 1997).

Flood Insurance Study for El Paso County, Colorado and incorporated Areas. Federal Emergency Management Agency (Washington D.C.: FEMA, March 17, 1997).

Drainage Area Identification Study. Muller Engineering Company, Inc. (Lakewood, CO: , 1986).

Sand Creek Drainage Basin Planning Study, Preliminary Design Report. Kiowa Engineering Corporation Inc. (Colorado Springs, Colorado: , March 1996).

Drainage Criteria Manual Volume 2, Stormwater Quality Policies, Procedures and Best Management Practices (BMPs). City of Colorado Spring Engineering Division (Colorado Springs: , May 2014).

City of Colorado Springs Drainage Criterial Manual, Volume 1. City of Colorado Springs Engineering Division Staff, Matrix Desgin Group/Wright Water Engineers (Colorado Springs: , May 2014).

City of Colorado Springs Drainage Criteria Manual Volume 1. City of Colorado Springs Engineering Division with Matrix Design Group and Wright Water Engineers (Colorado Springs, Colorado: , May 2014).

*Drainage Criteria Manual (Volume 2)*. Urban Drainage and Flood Control District (Denver, Colorado: Urban Drainage and Flood Control District, Rev. September 2017).


Detention Design Spreadsheet. Urban Drainage and Flood Control District ("http://www.udfcd.org/downloads/software/UD-Detention v2.2.xls", accessed February 2017).

*Urban Storm Drainage Criteria Manual Volume 3*. Urban Drainage and Flood Control District (Denver, Colorado: , August, 2011).

# Appendices


#### 8 General Maps and Supporting Data


Vicinity Map
Portions of Flood Insurance Rate Map
Portion of Drainage Area Identification Study Map
NRCS Soil Map and Tables
SCS Soil Type Descriptions
Hydrologic Soil Group Map and Tables



VICINITY MAP

NO SCALE









# MAP LEGEND

## W Soil Map Unit Polygons Area of Interest (AOI) Soil Map Unit Points Soil Map Unit Lines Special Point Features Area of Interest (AOI) Soils

#### Very Stony Spot Stony Spot Spoil Area Wet Spot Other 8



Water Features



Borrow Pit

Blowout

Clay Spot




Closed Depression



**Gravelly Spot** 

Gravel Pit





Marsh or swamp

Lava Flow

Landfill

Mine or Quarry

Miscellaneous Water

0

Perennial Water

Rock Outcrop

# MAP INFORMATION

The soil surveys that comprise your AOI were mapped at

line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil Warning: Soil Map may not be valid at this scale.

Please rely on the bar scale on each map sheet for map measurements. Source of Map: Natural Resources Conservation Service Coordinate System: Web Mercator (EPSG:3857) Web Soil Survey URL:

distance and area. A projection that preserves area, such as the Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado Survey Area Data: Version 15, Oct 10, 2017 Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Jun 3, 2014—Jun 17,

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Severely Eroded Spot

Slide or Slip

Sinkhole

Sodic Spot

Sandy Spot

Saline Spot

### **Map Unit Legend**

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	10.9	99.9%
28	Ellicott loamy coarse sand, 0 to 5 percent slopes	0.0	0.1%
Totals for Area of Interest		10.9	100.0%

is severely eroded and blowouts have developed, the new seeding should be fertilized.

Windbreaks and environmental plantings are generally suited to this soil. Soil blowing is the main limitation for the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be necessary when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. In cropland areas, habitat favorable for ring-necked pheasant, mourning dove, and many nongame species can be developed by establishing areas for nesting and escape cover. For pheasant, the provision of undisturbed nesting cover is vital and should be included in plans for habitat development. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for use as homesites. Shallow excavation is severely limited because cut banks cave in. This sandy soil requires special management practices to reduce water erosion and soil blowing. Capability subclasses IIIe, irrigated, and IVe, nonirrigated.

7—Bijou sandy loam, 3 to 8 percent slopes. This deep, well drained soil is on flood plains, terraces, and uplands. It formed in sandy alluvium and eolian material derived from arkose deposits. Elevation ranges from 5,400 to 6,200 feet. The average annual precipitation is about 13 inches, the average annual air temperature is about 49 degrees F, and the average frost-free period is about 145 days.

Typically, the surface layer is brown sandy loam about 4 inches thick. The subsoil is brown or grayish brown sandy loam about 24 inches thick. The substratum is pale brown loamy coarse sand.

Included with this soil in mapping are small areas of Olney sandy loam, 3 to 5 percent slopes; Valent sand, 1 to 9 percent slopes; Vona sandy loam, 3 to 9 percent slopes; and Wigton loamy sand, 1 to 8 percent slopes.

Permeability of this Bijou soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Organic matter content of the surface layer is low. Surface runoff is slow, and the hazards of erosion and soil blowing are moderate.

Almost all areas of this soil are used for range.

This soil is suited to the production of native vegetation suitable for grazing. Because of the hazards of water erosion and soil blowing, the soil is not suited to nonirrigated crops.

Native vegetation is dominantly blue grama, sand dropseed, needleandthread, side-oats grama, and buckwheat. Seeding is a suitable practice if the range has deteriorated. Seeding the native grasses is a good practice. If the range is severely eroded and blowouts have developed, the new seeding should be fertilized. Brush control and grazing management may be needed to improve the depleted range. Grazing should be managed so that enough forage is left standing to protect the soil from blowing, to increase infiltration of water, and to catch and hold snow.

Windbreaks and environmental plantings are generally suited to this soil. Soil blowing is the main limitation for the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, by properly managing livestock grazing, and by reseeding range where needed.

This soil has good potential for use as homesites. Shallow excavation is severely limited because cut banks cave in. This soil requires special management practices to reduce water erosion and soil blowing. Capability subclass VIe.

8—Blakeland loamy sand, 1 to 9 percent slopes. This deep, somewhat excessively drained soil formed in alluvial and eolian material derived from arkosic sedimentary rock on uplands. The average annual precipitation is about 15 inches, the average annual air temperature is about 47 degrees F, and the average frost-free period is about 135 days.

Typically, the surface layer is dark grayish brown loamy sand about 11 inches thick. The substratum, to a depth of 27 inches, is brown loamy sand; it grades to pale brown sand that extends to a depth of 60 inches.

Included with this soil in mapping are small areas of Bresser sandy loam, 0 to 3 percent slopes; Bresser sandy loam, 3 to 5 percent slopes; Truckton sandy loam, 0 to 3 percent slopes; Truckton sandy loam, 3 to 9 percent slopes; and Stapleton sandy loam, 3 to 8 percent slopes. In some areas, mainly north of Colorado Springs in the Cottonwood Creek area, arkosic beds of sandstone and shale are at a depth of 0 to 40 inches.

Permeability of this Blakeland soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Organic matter content of the surface layer is medium. Surface runoff is slow, the hazard of erosion is moderate, and the hazard of soil blowing is severe.

Most areas of this soil are used for range, homesites, and wildlife habitat.

ಎಲ್ ಆಕ್ರೀಮಿಕ ಎಂದು ಕಾರ್ಯ ಕ್ರಮಿಸಿಸ್ ಕರೆ <sub>ಕ್</sub>ರೀಡಿಕ

12 SOIL SURVEY

Native vegetation is dominantly western wheatgrass, side-oats grama, and needleandthread. This soil is best suited to deep-rooted grasses.

Proper range management is necessary to prevent excessive removal of plant cover from the soil. Interseeding improves the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Proper location of livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings are fairly well suited to this soil. Blowing sand and low available water capacity are the main limitations for the establishment of trees and shrubs. The soil is so loose that trees need to be planted in shallow furrows and plant cover needs to be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redeedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for urban development. Soil blowing is a hazard if protective vegetation is removed. Special erosion control practices must be provided to minimize soil losses. Capability subclass VIe.

9—Blakeland complex, 1 to 9 percent slopes. This complex is on uplands, mostly in the Falcon area. The average annual precipitation is about 15 inches, the average annual air temperature is about 47 degrees F, and the frost-free period is about 135 days.

This complex is about 60 percent Blakeland loamy sand, about 30 percent Fluvaquentic Haplaquolls, and 10 percent other soils.

Included with these soils in mapping are areas of Columbine gravelly sandy loam, 0 to 3 percent slopes, Ellicott loamy coarse sand, 0 to 5 percent slopes, and Ustic Torrifluvents, loamy.

The Blakeland soil is in the more sloping areas. It is deep and somewhat excessively drained. It formed in sandy alluvium and eolian material derived from arkosic sedimentary rock. Typically, the surface layer is dark grayish brown loamy sand about 11 inches thick. The substratum, to a depth of 27 inches, is brown loamy sand; it grades to pale brown sand that extends to a depth of 60 inches or more.

Permeability of the Blakeland soil is rapid. The effective rooting depth is more than 60 inches. The available water capacity is moderate to low. Surface runoff is slow, and the hazard of erosion is moderate.

The Fluvaquentic Haplaquolls are in swale areas. They are deep, poorly drained soils. They formed in alluvium derived from arkosic sedimentary rock. Typically, the surface layer is brown. The texture is variable throughout. The water table is at a depth of 0 to 3 feet.

The Blakeland soil is well suited to deep-rooted grasses. Native vegetation is dominantly western wheatgrass, side-oats grama, and needleandthread. Rangeland vegetation on the Fluvaquentic Haplaquolls is dominantly tall grasses, including sand bluestem, switchgrass, prairie cordgrass, little bluestem, and sand reedgrass. Cattails and bulrushes are common in the swampy areas.


Proper range management is needed to prevent excess removal of plant cover from these soils. It is also needed to maintain the productive grasses. Interseeding improves the existing vegetation. Deferment of grazing during the growing season increases plant vigor and soil stability, and it helps to maintain and improve range condition. Proper location of livestock watering facilities helps to control grazing of animals.

Windbreaks and environmental plantings are fairly well suited to these soils. Blowing sand and low available water capacity are the main limitations to the establishment of trees and shrubs. The soils are so loose that trees need to be planted in shallow furrows and plant cover needs to be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

The Blakeland soil is well suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed. Wetland wildlife can be attracted to the Fluvaquentic Haplaquolls and the wetland habitat can be enhanced by several means. Shallow water developments can be created by digging or by blasting potholes to create open-water areas. Fencing to control livestock grazing is beneficial, and it allows wetland plants such as cattails, reed canarygrass, and rushes to grow. Control of unplanned burning and prevention of drainage that would remove water from the wetlands are good practices. Openland wildlife use the vegetation on these soils for nesting and escape cover. These shallow marsh areas are especially important for winter cover if natural vegetation is allowed to grow.

The Blakeland soil has good potential for homesites, roads, and streets. It needs to be protected from erosion when vegetation has been removed from building sites. The Fluvaquentic Haplaquolls have poor potential for homesites. Their main limitations for this use are the high water table and the hazard of flooding. Capability subclass VIe.

10—Blendon sandy loam, 0 to 3 percent slopes. This deep, well drained soil formed in sandy arkosic alluvium on alluvial fans and terraces. The average annual precipitation is about 15 inches, the mean annual air temperature is about 47 degrees F, and the average frost-free period is about 135 days.



# MAP INFORMATION

The soil surveys that comprise your AOI were mapped at

Soils

line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed misunderstanding of the detail of mapping and accuracy of soil Enlargement of maps beyond the scale of mapping can cause Warning: Soil Map may not be valid at this scale. scale.

Please rely on the bar scale on each map sheet for map measurements. Source of Map: Natural Resources Conservation Service Coordinate System: Web Mercator (EPSG:3857) Web Soil Survey URL:

Maps from the Web Soil Survey are based on the Web Mercator distance and area. A projection that preserves area, such as the projection, which preserves direction and shape but distorts Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado Survey Area Data: Version 15, Oct 10, 2017 Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Jun 3, 2014—Jun 17,

Not rated or not available

Soil Rating Points

B/D

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

#### Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	А	10.9	99.9%
28	Ellicott loamy coarse sand, 0 to 5 percent slopes	A	0.0	0.1%
Totals for Area of Inter	rest		10.9	100.0%

#### Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

### **Rating Options**

Aggregation Method: Dominant Condition Component Percent Cutoff: None Specified

Tie-break Rule: Higher

#### 9 Hydrologic Calculations

Runoff Coefficients and Percent Imperviousness Table 6-6
Colorado Springs Rainfall Intensity Duration Frequency Table 6-5
Hydrologic Calculations Summary Form SF-1 for Existing & Developed Conditions
Hydrologic Calculations Summary 5-yr Form SF-2 for Existing & Developed Conditions
Hydrologic Calculations Summary 100-yr Form SF-2 for Existing & Developed Conditions

Table 6-6. Runoff Coefficients for Rational Method (Source: UDFCD 2001)

Land Use or Surface	Percent						Runoff Coefficients	efficients					
Characteristics	Impervious	2-y	year	λ.	5-year	10-)	10-year	75-1	25-year	50-1	50-year	100	100-year
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSGC&D	HSG A&B	HSGC&D
Business									_		200	2000	_
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	09'0	0.65	0.62	0.68
Residential													
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0 59	0.65
	40	0.23	0.28	0:30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.47	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0:30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	09'0	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	`0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Parks and Cemeteries	7	0.05	0.09	0.12	0.19	0.20	0.29	0:30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0:20	0.58
Undeveloped Areas													
Historic Flow Analysis Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0:30	0.44	(0.35)	0.50
	0	0.02	0.04	0.08	0,15	0.15	0.25	0.25	0.37	0:30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	96'0	96.0
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	(96.0)	0.96
Gravel	80	0.57	09'0	(0.59)	0.63	0.63	99.0	99'0	0.70	89'0	0.72	0.70	0.74
				)		X							
Drive and Walks	100	0.89	0.89	0.90	06'0	0.92	0.92	0.94	0.94	0.95	0.95	96.0	96'0
Roofs	06	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	080	0.82	0,87	0.83
Lawns	0	0.02	0.04	0-08	210	24.0	30.0	200	200	000	.,,	(	0




Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency

#### **IDF** Equations

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

Sub-Basin Data   Overland   Ove	Job No.: Project:	Freedom Springs	prings									5	Calcs By:		WCT			,	
Sub-Basin Data         Overland         Shallow Channel         Channelized         Channelized         Ccheck         Channelized         Ccheck         Channelized         Ccheck         Channelized         Ccheck         Channelized         Ccheck         Log Strong         Log Strong <th></th> <th></th> <th></th> <th></th> <th>Time</th> <th>of Con</th> <th>centra</th> <th>tion (M</th> <th>odified t</th> <th>rom Star</th> <th>ndard Fc</th> <th>) rm SF-1</th> <th>Checked )</th> <th>By:</th> <th></th> <th></th> <th></th> <th></th> <th></th>					Time	of Con	centra	tion (M	odified t	rom Star	ndard Fc	) rm SF-1	Checked )	By:					
Sub- Area  Sub- Area  Composition  Compositi			Sub-Basir	ו Data		0	verland		0)	hallow C	Shannel			Chann	elized		t, Ch	ack	
2.84         0.5         Coordon Line         (ff)	-qns	Area	10		%	L <sub>o</sub>	So	17	Ļ	Sot	Vosc	43"	Loc	Soc	V <sub>0c</sub>	وب	_	t <sub>c,alt</sub>	٠,
2.84         0.45         0.59         65%         19         11.4         125         0.010         2.0         1.0         360         0.019         3.0         2.0         580         13.2           2.72         0.17         0.49         0.66         65%         100         1%         11.0         90         0.020         1.0         1.5         0         0.000         0.0         0.0         11.1           1.16         0.09         0.36         2%         100         4%         11.2         285         0.00         0.0         0.0         0.0         0.0         11.1           0.17         0.75         0.86         0.92         94%         100         2%         3.2         4.4         1.4         1.7         0         0.00         0.0	Basin	(Acres)	చ	C100/CN	lmp.	(£)	(%)	(min)	(£)	(ft/ft)	(£/s)	(min)	Œ	(ft/ft)	(ft/s)	(min)	(min)	(min)	(min)
2.72         0.17         0.49         0.66         65%         100         11.0         90         0.020         1.0         1.5         0         0.000         0.0         0.0         11.1           2.72         0.17         0.41         11%         100         4%         11.2         266         0.000         0.7         0.000         0.0	081	2.84	0.45	0.59	%59	92	1%	11.4	125	0.010	2.0	1.0	360	0.019	3.0	2.0	580	13.2	13.2
2.72         0.17         0.41         11%         100         4%         11.2         2.66         0.009         0.7         6.5         0         0.000         0.0         0.0         245         11.4           1.16         0.09         0.36         2%         100         3%         12.4         145         0.041         1.4         0.00         0.0         0.0         0.0         245         11.4           0.17         0.75         0.85         0.94%         100         2%         3.2         16         0.000         0.0	082	0.57	0.49	0.65	%59	100	1%	11.0	06	0.020	1.0	1.5	0	0.000	0.0	0.0	190	1.1	11.1
0.63         0.86         0.99         0.36         2%         100         3%         12.4         146         0.041         1.4         1.7         0         0.000         0.0         245         11.6           0.63         0.85         0.86         0.92         94%         100         2%         3.9         35         0.014         2.4         0.0         0.000         0.0         1.3         295         11.6           0.17         0.70         0.81         76%         32         2%         3.1         0         0.000         0.0         1.0         0.000         0.0         116         10.6           0.17         0.20         0.73         0.81         76%         37         0         0.000         0.0	EX A1	2.72	0.17	0.41	11%	100	4%	11.2	265	0.009	0.7	6.5	0	0.000	0.0	0.0	365	12.0	12.0
0.63 0.85 0.92 94% 100 2% 3.9 35 0.014 2.4 0.2 160 0.011 2.0 1.3 295 116 0.000 0.1 0.000 0.0 0.0 116 10.0 0.1 0.1 0.70 0.81 76% 3.2 2% 3.1 0 0.000 0.0 0.1 128 0.057 2.5 0.9 160 10.9 0.1 0.01 0.000 0.0 0.0 0.0 0.0 0.0 0.0	EX B1	1.16	0.09	0.36	2%	100	3%	12.4	145	0.041	4.1	1.7	0	0.000	0.0	0.0	245	11.4	11.4
0.17     0.75     0.86     81%     100     8%     3.2     16     0.063     5.0     0.1     0     0.00     0.0     116     10.0       0.11     0.70     0.81     76%     3.2     2%     3.1     0     0.000     0.0     178     0.057     2.5     0.9     160     10.9       0.17     0.20     0.44     0.84     0.84     3%     1.7     0.000     0.0	A1	0.63	0.85	0.92	94%	100	2%	3.9	35	0.014	2.4	0.2	160	0.011	2.0	1.3	295	11.6	5.5
0.11 0.70 0.81 76% 32 2% 3.1 0 0.000 0.0 128 0.057 2.5 0.9 160 10.9 10.36 0.73 0.81 90% 30 1% 3.7 0 0.000 0.0 0.0 175 0.010 5.0 0.6 205 11.1 0.17 0.20 0.44 14% 87 3% 10.7 0 0.000 0.0 0.0 0.0 0.0 0.0 0.0 0.0	B1	0.17	0.75	0.85	81%	100	8%	3.2	16	0.063	5.0	0.1	0	0.000	0.0	0.0	116	10.6	5.0
0.36       0.73       0.81       90%       30       1%       3.7       0       0.000       0.0       175       0.010       5.0       0.65       11.1         0.17       0.20       0.44       14%       87       3%       10.7       0       0.000       0.0	5	0.11	0.70	0.81	%92	32	2%	3.1	0	0.000	0.0	0.0	128	0.057	2.5	0.9	160	10.9	2.0
0.17 0.20 0.44 14% 87 3% 10.7 0 0.000 0.0 0 0 0.00 0.0 0.0 0.0 0.0	10	0.36	0.73	0.81	%06	30	1%	3.7	0	0.000	0.0	0.0	175	0.010	5.0	9.0	205	11.1	2.0
0.17     0.45     0.62     45%     87     2%     9.2     0     0.000     0.0     0     0.000     0.0     0     0.000     0.0 </td <td>E1</td> <td>0.17</td> <td>0.20</td> <td>0.44</td> <td>14%</td> <td>87</td> <td>3%</td> <td>10.7</td> <td>0</td> <td>0.000</td> <td>0.0</td> <td>0.0</td> <td>0</td> <td>0.000</td> <td>0.0</td> <td>0.0</td> <td>87</td> <td>10.5</td> <td>10.5</td>	E1	0.17	0.20	0.44	14%	87	3%	10.7	0	0.000	0.0	0.0	0	0.000	0.0	0.0	87	10.5	10.5
0.58     0.08     0.35     0%     100     4%     11.7     160     0.063     1.8     1.5     0     0.000     0.0     260     11.4       0.45     0.73     0.83     79%     65     2%     4.7     0     0.000     0.0     245     0.045     3.0     1.4     310     11.7       0.46     0.08     0.35     0%     100     4%     11.7     25     0.000     0.0     0.0     0.000     0.0     0.000     0.0     0.000     0.0     0.0     0.000     0.0 <td>F1</td> <td>0.17</td> <td>0.45</td> <td>0.62</td> <td>45%</td> <td>87</td> <td>5%</td> <td>9.5</td> <td>0</td> <td>0.000</td> <td>0.0</td> <td>0.0</td> <td>0</td> <td>0.000</td> <td>0.0</td> <td>0.0</td> <td>87</td> <td>10.5</td> <td>9.2</td>	F1	0.17	0.45	0.62	45%	87	5%	9.5	0	0.000	0.0	0.0	0	0.000	0.0	0.0	87	10.5	9.2
0.45     0.73     0.83     79%     65     2%     4.7     0     0.000     0.0     245     0.045     3.0     1.4     310     11.7       0.46     0.08     0.35     0%     100     4%     11.7     25     0.080     2.0     0     0.00     0.0     0.0     125     10.7       0.15     0.08     0.35     0%     33     11%     4.9     0     0.000     0.0     0     0.00     0.0	G1	0.58	0.08	0.35	%0	100	4%	11.7	160	0.063	1.8	1,5	0	0.000	0.0	0.0	260	11.4	11.4
0.46     0.08     0.35     0%     100     4%     11.7     25     0.080     2.0     0.000     0.0     0.000     0.0     0.0     0.000     0.0     <	Ŧ	0.45	0.73	0.83	%62	92	5%	4.7	0	0.000	0.0	0.0	245	0.045	3.0	1,4	310	11.7	6.0
0.15     0.08     0.35     0.%     33     11%     4.9     0     0.000     0.0     0     0.000     0.0<	71	0.46	0.08	0.35	%0	100	4%	11.7	25	0.080	2.0	0.2	0	0.000	0.0	0.0	125	10.7	10.7
0.45     0.08     0.35     0%     10.6     10.068     1.8     1.3     0     0.000     0.0     240     11.3       0.13     0.08     0.35     0%     32     9%     5.1     0     0.000     0.0     0     0.00     0.0     32     10.2       10     0.08     0.35     0.09     0.09     0.0     0.0     0.0     0.0     0.0     0.0     0.0     0.0     0.0     0.0	ž	0.15	0.08	0.35	%0	33	11%	4.9	0	0.000	0.0	0.0	0	0.000	0.0	0.0	33	10.2	5.0
0.13 0.08 0.35 0% 5.1 0 0.000 0.0 0 0.000 0.0 32 10.2	17	0.45	0.08	0.35	%0	100	%9	10.5	140	0.068	1.8	1.3	0	0.000	0.0	0.0	240	11.3	11.3
	M1	0.13	0.08	0.35	%0	32	%6	5.1	0	0.000	0.0	0.0	0	0.000	0.0	0.0	32	10.2	5.1

 Job No.:
 61090

 Project:
 Freedom Springs

 Design Storm:
 5-Year Storm

 Jurisdiction:
 DCM

(20% Probability)

Sub-Basin and Combined Flows (Modified from Standard Form SF-2)

3/22/18 10:03

WCT

Date: Calcs By: Checked By:

Sub- Area C (min) (A Cres) C5						Direct Runoff	Joun			Combined Runoff	Runoff		Str	Streetflow			Pipe	Pipe Flow		-	Travel Time	Travel Time	
Besin Arcras) GG (min) (Accas) (min) (Accas) (min) (Accas) (min) (More) (min)		-qns	Area		ور	CA	15	92	و.	CA	15		Slope L	ength	T.			Anngs L		_		-	45
Cost	DP	Basin	(Acres)	CS	(min)	(Acres)	(in/hr)	(cfs)	(min)	(Acres)	(in/hr)	(cfs)	-	-	4	(cfs)	(%)	_	-	+	-	-	(min)
OS1   OS4   O.54   13.2   1.28   3.71   4.7     EXA1   2.72   O.47   12.0   O.45   3.85   1.7     EXA1   EX.   1.16   O.09   11.4   O.11   3.94   O.4     EX.   1.16   O.09   11.4   O.11   3.94   O.4     I.17   O.25   O.27   O.20   O.28   S.5   O.27     I.18   O.22, EX. B1   I.72   O.21     I.19   O.35   O.35   S.5   O.35   S.5     I.10   O.35   O.35   S.5   O.35   S.5     I.11   O.35   O.35   O.35   S.5     I.12   O.37   O.38   O.38   S.5     I.13   O.34   O.35   O.35   O.35     I.14   O.35   O.35   O.35   O.35     I.15   O.35   O.35   O.35   O.35     I.17   O.45   O.35   O.35   O.35     I.19   O.45   O.49     I.14   O.29   O.39     I.14   O.29   O.35     I.15   O.35   O.35   O.35     I.17   O.45   O.35   O.35     I.18   O.45   O.45     I.19   O.45   O.45     I.11   O.45   O.45     I.14   O.29   O.35     I.14   O.29   O.35     I.14   O.35   O.35     I.15   O.45   O.45     I.14   O.29   O.35     I.15   O.45   O.45     I.14   O.29   O.35     I.15   O.45   O.45     I.15   O.45   O.45     I.16   O.45   O.45     I.17   O.45   O.45     I.18   O.45   O.45     I.19   O.45     I.19   O.45     I.19   O.45   O.45     I.19   O.45   O.45     I.19	Offsite													_									Т
EX A1   2.72   0.47   11.0   0.45   3.96   1.1   1.16   0.09   11.1   0.28   3.96   1.1   0.81, EX A1   2.72   0.17   12.0   0.45   3.85   1.7   11.4   0.03   3.94   0.4   14.1   1.72   0.34   0.4   14.1   1.72   0.34   0.4   14.1   0.36   3.94   1.1   0.82, EX B1   1.72   0.21   0.17   0.20   0.25   0.20   0.27   0.11   0.70   0.00   0.27   0.14   0.17   0.20   0.14   0.05   0.14   0.05   0.14   0.05   0.14   0.05   0.14   0.05   0.14   0.05   0.14   0.15   0.00   0.14   0.05   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.00   0.14   0.15   0.14   0.15   0.00   0.14   0.15   0.15		081	2.84	0.45		1.28	3.71	4.7															
EXAL STATE S		OSZ	0.57	0.49		0.28	3.98	17															
EX 81 1.72 0.17 12.0 0.45 3.85 1.7 EX 81 1.73 3.61 1.70 0.85 EX 81 1.72 0.21 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.7 1.72 0.85 1.72 0.85 1.7 1.74 0.85 1.7 1.74 0.85 1.7 1.74 0.85 1.7 1.74 0.85 1.7 1.74 0.85 1.7 1.74 0.85 1.7 1.74 0.85 1.7 1.7 1.7 1.7 1.7 1.7 1.7 1.7 1.7 1.7	Existing	1				1000	1000	11							-								
EX B1		EX A1	2.72	0.17		0.45	3.85	1.7															
A1 OS1, EX A1		EX 81	1.16	60.0		0.11	3.94	0.4	7		k												
H1 OS2, EX B1 1.72 0.21  A1 0.63 0.85 5.5 0.54 5.02 2.7  B1 0.17 0.75 5.0 0.13 5.17 0.4  C1 0.11 0.20 0.20 5.17 0.4  D1 0.20 0.17 0.20 0.00 5.17 0.4  E1 0.17 0.45 0.03 4.06 0.1  F1 0.45 0.08 1.4 0.03 4.89 1.6  A1 1.0 0.45 0.08 1.3 4.89 1.6  M1 0.13 0.08 5.1 0.01 5.14 0.1  OS2, L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.65 0.56 0.56		0S1, EX A1	5.56	0.31					14.1	1.73	3.61	6.2			_								
A1 0.683 0.85 5.5 0.54 5.02 2.7  B1 0.17 0.75 5.0 0.13 5.17 0.7  D1 0.36 0.77 5.0 0.08 5.17 0.4  D1 0.36 0.77 0.20 0.20 5.17 0.4  E1 0.17 0.20 10.5 0.03 4.06 0.1  E1 0.45 0.08 10.7 0.4  H1 0.45 0.08 10.7 0.04 4.03 0.1  K1 0.46 0.08 10.7 0.04 4.03 0.1  K1 0.13 0.08 5.1 0.01 5.14 0.1  OS2, L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.66 0.56 0.56  A1-H1 2.66 1.56 0.56		0S2, EX B1	1.72	0.21					11.4	0.36	3.94	4.1											
H1 052, L1 1,02 0.29 0.54 5.02 2.7  H1 052, L1 1,02 0.29 0.49  H1 052, L1 1,02 0.29  H1 053, H1 0.08 0.09  H1 052, L1 1,02 0.29  H1 053, H1 0.08 0.09  H1 053, H1 0.08 0.09  H1 053, H1 0.09 0.09  H1 053, H1 0.09  H1 053, H1 0.09  H1 054, H1 0.09  H1 0.09 0.	Developed																						
Bit   0.17   0.75   5.0   0.13   5.17   0.7     C1	DP1	A1	0.63	0.85		0.54	5.02	2.7															
C1 0.11 0.70 5.0 0.08 5.17 0.4  E1 0.17 0.20 0.73 5.0 0.08 5.17 1.4  E1 0.17 0.20 0.03 4.26 0.3  H1 0.45 0.73 6.0 0.33 4.89 1.6  H1 0.45 0.08 11.4 0.05 3.93 0.2  K1 0.15 0.08 10.7 0.04 4.03 0.1  K1 0.45 0.08 10.7 0.04 4.03 0.1  M1 0.45 0.08 11.3 0.04 3.94 0.1  M1 0.45 0.29 5.1 0.01 5.14 0.1  CS2, L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.65 0.56 6.2 1.49 4.84	DP2	81	0.17	0.75		0.13	5.17	0.7						_									
D1 0.36 0.73 5.0 0.27 5.17 1.4  E1 0.17 0.20 10.5 0.03 4.06 0.1  E1 0.17 0.45 9.2 0.03 4.06 0.1  H1 0.45 0.08 11.4 0.05 3.93 0.2  H1 0.46 0.08 10.7 0.04 4.03 0.1  K1 0.45 0.08 11.3 0.04 4.03 0.1  M1 0.13 0.08 5.1 0.01 5.14 0.1  OS2, L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.65 0.56 0.56 6.2 1.49 4.84	DP3	5	0.11	0.70		0.08	5.17	0.4															
E1 0.17 0.20 10.5 0.03 4.06 0.1 F1 0.17 0.45 9.2 0.08 4.25 0.3 G1 0.58 0.08 11.4 0.05 3.33 0.2 J1 0.45 0.08 10.7 0.04 4.03 0.1 K1 0.45 0.08 10.7 0.04 4.03 0.1 K1 0.45 0.08 11.3 0.04 3.94 0.1 M1 0.13 0.08 5.1 0.01 5.14 0.1 G22.L1 1.02 0.29 5.1 0.01 5.14 0.1 A1-H1 2.65 0.56 6.2 0.56 6.2 1.49 4.34		10	0.36	0.73		0.27	5.17	1.4						_									
F1 0.17 0.45 9.2 0.08 4.25 0.3  G1 0.58 0.08 11.4 0.05 3.83 0.2  H1 0.45 0.08 11.4 0.05 3.83 0.2  J1 0.46 0.08 10.7 0.04 4.03 0.1  K1 0.15 0.08 5.0 0.04 4.03 0.1  M1 0.13 0.08 5.1 0.01 5.14 0.1  OS2.L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.65 0.56 6.2 1.49 4.84	DP5	E1	0.17	0.20		0.03	4.06	0.1															
G1 0.58 0.08 11.4 0.05 3.93 0.2 H1 0.45 0.73 6.0 0.33 4.89 1.6 J1 0.46 0.08 10.7 0.04 4.03 0.1 L1 0.45 0.08 11.3 0.04 3.94 0.1 M1 0.13 0.08 5.1 0.01 5.14 0.1 A1-H1 2.65 0.56  G1 0.48 0.05 3.94 A1-H1 4.05 0.08 1.00 0.00 0.00 0.00 0.00 0.00 0.00	DP6	F1	0.17	0.45		0.08	4.25	0.3															
H1 0.45 0.73 6.0 0.33 4.89 1.6  K1 0.46 0.08 10.7 0.04 4.03 0.1  K1 0.45 0.08 10.7 0.04 4.03 0.1  L1 0.45 0.08 11.3 0.04 4.03 0.1  M1 0.13 0.08 5.1 0.01 5.14 0.1  OS2. L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.65 0.56 6.2 1.49 4.84		G1	0.58	0.08		0.05	3.93	0.2															
J1 0.46 0.08 10.7 0.04 4.03 0.1  K1 0.15 0.08 5.0 0.01 5.17 0.1  L1 0.45 0.08 11.3 0.04 3.94 0.1  OS2.L1 1.02 0.29 5.1 0.01 5.14 0.1  A1-H1 2.65 0.56 6.2 1.49 4.84		Ξ	0.45	0.73		0.33	4.89	1.6															
K1 0.15 0.08 5.0 0.01 5.17 0.1  L1 0.45 0.08 11.3 0.04 3.94 0.1  M1 0.13 0.08 5.1 0.01 5.14 0.1  OS2, L1 1.02 0.29 0.49  A1-H1 2.65 0.56  A1-H1 4.4 1.61 3.58		11	0.46	0.08		0.04	4.03	0.1															
L1 0.45 0.08 11.3 0.04 3.94 0.1 M1 0.13 0.08 5.1 0.01 5.14 0.1 OS2, L1 1.02 0.29 0.49 A1-H1 2.65 0.56  L1 1.02 0.29 3.94 E.2 1.49 4.84		K1	0.15	0.08		0.01	5.17	0.1							_								
M1 0.13 0.08 5.1 0.01 5.14 0.1  OS2, L1 1.02 0.29 OS3, H1 3.29 0.49 A1-H1 2.65 0.56  6.2 1.49 4.84			0.45	0.08	11.3	0.04	3.94	0.1							_								
0SS, L1 1.02 0.29 11.4 0.29 3.94 OS1, H1 3.29 0.49 14.4 1.61 3.58 A1-H1 2.65 0.56 6.2 1.49 4.84		M1	0.13	0.08	5.1	0.01	5.14	0.1															Ī
OSY, H1 3.29 0.49 A1-H1 2.65 0.56 A1-H1 4.4 1.61 3.58 A1-H1 2.65 0.56 A1-H2 4.84	0S2+L1	0S2, L1	1.02	0.29					11.4	0.29	3.94	1.1											
A1-H1 2.65 0.56 6.2 1.49 4.84	DP4	OS1, H1	3.29	0.49					14.4	1.61	3.58	5.7											
	DP7	A1-H1	2.65	0.56					6.2	1.49	4.84	7.2											
														-									
										-													
																			=	1			

DCM: 1 = C1 \* In (tc) + C2 C1: 1.5 C1: 7.583

Job No.: 61090
Project: Freedom Springs
Design Storm: 100-Year Storm (1% Probability)
Jurisdiction: DCM

Sub-Basin and Combined Flows (Modified from Standard Form SF-2)

3/22/18 10:03

WCT

Date: Calcs By: Checked By:

Sub- Area   Sub-						Direct Runoff	Runoff			Combined Runoff	Runoff		S	Streetflow			Pip	Pipe Flow			Trave	Travel Time	
Section   Cores   Core   Cor	1	-qnS	Area		ور	CA	1100	0100	29	CA	1100	1				o		Mnngs L	_	_		-	-3"
CS1   CS4   O.59   13.2   1.68   6.23   10.4	OP	Basin	(Acres)	C100	(min)	(Acres)	(in/hr)	(cfs)	(min)	(Acres)	(in/hr)	(cfs)	(%)	-	4	(cts)	(%)	c	Œ	+	-		(min)
Cost	Offsite																				-		
EX A1   2.72   0.65   11.1   0.37   6.68   2.5   EX A1   2.72   0.41   12.0   11.2   6.47   7.2   EX B1   1.16   0.36   11.4   0.42   6.61   2.8   14.1   2.80   6.06   0.52, EX B1   1.72   0.44   10.2   0.45   8.68   1.3   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   6.61   11.4   0.75   0		081	2.84	0.59			9	10.4															
EXAL EXAL EX B1 EX		082	0.57	0.65			9	2.5															
EXA1	Existing						Ţ																
EX B1 1.16 0.36 11.4 0.42 6.61 2.8 14.1 2.80 6.06 0.51, EX A1 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.72 0.44 1.05 0.15 8.88 1.3 1.3 0.11 0.17 0.44 10.5 0.03 8.88 1.3 1.3 0.17 0.44 10.5 0.03 8.88 1.3 1.3 0.17 0.45 0.35 11.4 0.20 6.59 1.3 1.3 0.15 0.35 11.4 0.20 6.59 1.3 1.3 0.15 0.35 11.3 0.16 6.62 1.1 1.4 0.48 0.44 0.44		EX A1	2.72	0.41			6.47	7.2															
14.1   2.80   6.05     15.2   2.44   1.72   0.44   1.12   0.44   1.12   0.44   1.12   0.44   1.12   0.44   1.12   0.44   1.12   0.44   1.12   0.44   1.12   0.45		EX B1	1.16	0.36			6.61	2.8															
A1 0.63 0.92 5.5 0.58 8.43 4.9 11.4 0.75 6.61 1.3 0.63 0.92 5.5 0.58 8.43 4.9 4.9 1.3 0.17 0.85 5.0 0.15 8.68 0.8 1.3 0.17 0.85 5.0 0.09 8.68 0.8 0.8 0.17 0.04 10.5 0.07 6.81 0.5 0.9 1.3 0.17 0.04 10.5 0.07 6.81 0.5 0.1 1.3 0.17 0.04 0.35 11.4 0.20 6.59 1.3 1.3 0.4 0.45 0.35 11.3 0.16 6.62 1.1 0.45 0.35 11.3 0.16 6.62 1.1 0.4 0.48 0.35 11.3 0.16 6.62 1.1 0.4 0.48 0.35 0.4 0.4 0.48 0.35 0.4 0.4 0.48 0.35 0.4 0.4 0.48 0.35 0.4 0.4 0.48 0.4 0.48 0.4 0.48 0.4 0.48 0.4 0.48 0.4 0.48 0.4 0.48 0.4 0.48 0.4 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.48 0.44 0.44		0S1, EX A1	5.56	0.50					14.1	2.80	90'9	17.0									_		
A1 0.63 0.92 5.5 0.56 8.43 4.9  B1 0.17 0.85 5.0 0.15 8.68 1.3  B1 0.17 0.85 5.0 0.09 8.68 0.8  E1 0.17 0.44 10.5 0.00 8.68 2.6  E1 0.17 0.44 10.5 0.07 6.81 0.5  F1 0.17 0.44 10.5 0.07 6.81 0.5  H1 0.45 0.35 11.4 0.20 6.39 1.3  H1 0.45 0.35 11.3 0.16 6.62 1.1  M1 0.45 0.35 5.0 0.05 8.68 0.4  K1 0.45 0.35 5.0 0.05 8.68 0.4  K1 0.45 0.35 5.0 0.05 8.68 0.4  A1-H1 2.85 0.71 8.39 0.62 8.63 0.4  A1-H1 2.85 0.71 8.39 8.60 0.71  A1-H1 2.85 0.77 8.13 0.16 6.81 0.4  A1-H1 2.85 0.77 8.13		0S2, EX B1	1.72	0.44	Ĩ				11.4	0.75	6.61	5.0								_			
A1 0.63 0.92 5.5 0.58 843 4.9  C1 0.17 0.85 5.0 0.15 8.68 1.3  C1 0.17 0.85 5.0 0.09 8.68 0.8  C1 0.17 0.84 10.5 0.09 8.68 0.8  C1 0.17 0.44 10.5 0.07 6.81 0.5  C1 0.17 0.44 10.5 0.07 6.81 0.5  C1 0.17 0.44 10.5 0.07 6.81 0.5  C1 0.17 0.45 0.35 11.4 0.20 6.59 1.3  C2 0.11 7.14 0.49 6.61  C3 0.25 1.1 0.05 8.68 0.4  C1 0.35 0.35 5.1 0.05 8.68 0.4  C2 0.18 0.35 0.11  C3 0.48 0.35 0.11  C3 0.48 0.35 0.11  C4 0.48 0.35 0.11  C5 0.71 0.49 6.61  C6 0.71 0.72 0.48 0.71  C6 0.71 0.72 0.48 0.71  C6 0.73 0.73 0.74  C7 0.74 0.75 0.75 0.75 0.75 0.75 0.75 0.75 0.75	Developed																						
State   Stat	DP1	A1	0.63	0.92				6.4															
C1 0.11 0.81 5.0 0.09 8.68 0.8  E1 0.17 0.44 10.5 0.07 8.68 2.6  E1 0.17 0.44 10.5 0.07 6.81 0.5  E1 0.17 0.44 10.5 0.07 6.81 0.5  E1 0.17 0.44 10.5 0.07 6.81 0.5  E1 0.17 0.45 0.82 11.4 0.8  E1 0.17 0.45 0.83 11.4 0.20 6.59 1.3  E1 0.18 0.45 0.85 11.1  E1 0.45 0.85 11.1  E2 0.85 0.97 11.1  E2 0.95 1.11  E2 0.95 1.	DP2	181	0.17	0.85				1.3													_		
D1 0.36 0.81 5.0 0.30 8.68 2.6 E1 0.17 0.44 10.5 0.07 6.81 0.5 G1 0.58 0.35 11.4 0.20 6.59 1.3 H1 0.45 0.83 6.0 0.37 8.21 3.1 M1 0.45 0.85 10.7 0.16 6.62 1.1 M1 0.45 0.35 11.3 0.16 6.62 1.1 M1 0.13 0.35 5.1 0.05 8.63 0.4 A1-H1 2.65 0.71  E1 0.30 0.81 8.68 2.6  E1 0.44 2.05 6.01	DP3	5	0.11	0.81				0.8													_		
E1 0.17 0.44 10.5 0.07 6.81 0.5   F1 0.17 0.62 9.2 0.11 7.14 0.8   G1 0.58 0.35 11.4 0.20 6.59 1.3   H1 0.46 0.35 11.4 0.20 6.59 1.3   K1 0.45 0.35 10.7 0.16 6.62 1.1   M1 0.45 0.35 11.3 0.16 6.62 1.1   OS2_L1 1.02 0.48 5.1 0.05 8.63 0.4   A1-H1 2.65 0.71   E1 0.45 0.37 8.13   E1 0.49 6.61   E1 0.49 6.61		10	0.36	0.81				2.6													_		
F1 0.17 0.62 9.2 0.11 7.14 0.8  G1 0.58 0.35 11.4 0.20 6.59 1.3  H1 0.45 0.83 6.0 0.37 8.21 3.1  J1 0.46 0.35 10.7 0.16 6.76 1.1  K1 0.45 0.35 11.3 0.16 6.82 1.1  M1 0.43 0.35 5.1 0.05 8.63 0.4  A1-H1 2.65 0.71  F1 0.49 6.61  A1-H1 2.65 0.71  F1 0.49 6.61	DP5	i iii	0.17	0.44				0.5											_			_	
G1 0.58 0.35 11.4 0.20 6.59 1.3 H1 0.45 0.83 6.0 0.37 8.21 3.1 J1 0.46 0.35 10.7 0.16 6.76 1.1 Kri 0.15 0.35 11.3 0.16 6.62 1.1 M1 0.13 0.35 5.1 0.05 8.63 0.4 A1-H1 2.65 0.71  G1 0.58 0.71  G1 0.45 0.85 6.01  A1-H 0.45 0.85 6.01	DP6	F	0.17					0.8															
H1 0.45 0.83 6.0 0.37 8.21 3.1  K1 0.46 0.35 10.7 0.16 6.76 1.11  K1 0.45 0.35 5.0 0.05 8.68 0.4  L1 0.45 0.35 11.3 0.16 6.62 1.11  OS2, L1 1.02 0.48  OS1, H1 2.65 0.71  A1-H1 2.65 0.71  A1-H1 8.29 6.61  A1-H1 8.29 8.83 8.43		61	0.58					1.3															
Ji 0.46 0.35 10.7 0.16 6.76 1.11  Kri 0.15 0.35 5.0 0.05 8.68 0.04  Li 0.45 0.35 11.3 0.16 6.62 1.11  OS2, Li 1.02 0.48  OS1, Hi 2.65 0.71  A1-Hi 2.65 0.71  A1-Hi 8.29 0.62		Ŧ	0.45					3.1															
K1 0.15 0.35 5.0 0.05 8.68 0.4 L1 0.45 0.35 11.3 0.16 6.62 1.11 OS2, L1 1.02 0.48 OS1, H1 2.65 0.71 A1-H1 2.65 0.71  K1 0.45 0.48  B.63 0.4  11.4 0.49 6.61  A1-H1 2.65 0.71  B.62 1.87 8.13		5	0.46					1.1														-	
L1 0.45 0.35 11.3 0.16 6.62 1.1 M1 0.13 0.35 5.1 0.05 8.63 0.4 OS2, L1 1.02 0.48 OS2, L1 2.65 0.71 A1-H1 2.65 0.71  6.2 1.87 8.13		×	0.15					4.0															
M1 0.13 0.35 5.1 0.05 8.63 0.4  OS2, L1 1.02 0.48  OS1, H1 2.65 0.71  A1-H1 2.65 0.71  OS1, H1 0.49 6.61  OS2, L1 0.05 8.63 0.4		-	0.45					1.1															
0S2,L1 1.02 0.48 11.4 0.49 6.61 15.4 0.51 14.4 2.05 6.01 14.4 2.05 6.01 14.4 2.05 6.01 14.4 1.3 15.6 0.71 15.65 0.71 15.6		M	0.13					0.4															
0S2, L1 1.02 0.48 11.4 0.49 6.61 0S1, H1 3.29 0.62 0.71															-						_		
0S1, H1 3.29 0.62 A1-H1 2.65 0.71 6.2 1.87 8.13		OS2, L1	1.02	0.48					11.4	0.49	6.61	3.3											
A1-H1 2.65 0.71 6.2 1.87 8.13		OS1, H1	3.29	0.62					14.4	2.05	6.01	12.3											
		A1-H1	2.65	0.71					6.2	1.87	8.13	15.2			-								
															_								
														-									
													1									i	

DCM: 1 = C1 \* In (te) + C2 C1: 2.52 C1: 12.735

#### Sub-Basin OS1 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03 TJW Calcs by: Project: Freedom Springs Checked by: DRG A Jurisdiction DCM Soil Type Urbanization Urban Runoff Coefficient Surface Type

#### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
1/8 Acre or less	123,800	2.84	0.41	0.45	0.49	0.54	0.57	0.59	65%
Combined	123,800	2.84	0.41	0.45	0.49	0.54	0.57	0.59	65.0%

123800

#### **Basin Travel Time**

Shallow Channel Ground Cover Paved areas/shallow paved swales

	L <sub>max,Overland</sub>	100 f	t		Cv	20
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	580	9	-	1		1000
Initial Time	95	1	0.010	- 6	11.4	13.2 DCM Eq. 6-8
Shallow Channel	125	1	0.010	2.0	1.0	- DCM Eq. 6-9
Channelized	360	7	0.019	3.0	2.0	- C&G
				tc	13.2	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.96	3.71	4.33	4.95	5.57	6.23
Runoff (cfs)	3.5	4.7	6.0	7.6	9.0	10.4
Release Rates (cfs/ac)	-	-	17.2	1-1	-	
Allowed Release (cfs)	3.5	4.7	6.0	7.6	9.0	10.4

DCM: J = C1 + In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

Notes

#### Sub-Basin OS2 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03 TJW Project: Freedom Springs Calcs by:

Checked by: DRG

Jurisdiction DCM OS2 Soil Type Urbanization Urban **Runoff Coefficient Surface Type** 

#### **Basin Land Use Characteristics**

	Area		Runoff Coefficient							
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.	
1/8 Acre or less	24,712	0.57	0.45	0.49	0.54	0.59	0.62	0.65	65%	
Combined	24,712	0.57	0.45	0.49	0.54	0.59	0.62	0.65	65.0%	

24712

#### **Basin Travel Time**

#### Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	190	3			-	A
Initial Time	100	1	0.010		11.0	11.1 DCM Eq. 6-8
Shallow Channel	90	2	0.020	1.0	1.5	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
						- N. C.

11.1 min.

#### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.18	3.98	4.64	5.31	5.97	6.68
Runoff (cfs)	0.8	1.1	1.4	1.8	2.1	2.5
Release Rates (cfs/ac)	7	-	10.04	-	-	
Allowed Release (cfs)	0.8	1.1	1.4	1.8	2.1	2.5

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7,583 8.847 10,111 11.375 12.735

#### Notes

#### Sub-Basin EX A1 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

JurisdictionDCMSoil TypeARunoff CoefficientSurface TypeUrbanizationUrban

**Basin Land Use Characteristics** 

	Area	Runoff Coefficient							
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	103,361	2.37	0.02	0.08	0.15	0.25	0.3	0.35	0%
Paved	7,926	0.18	0.89	0.9	0.92	0.94	0.95	0.96	100%
Gravel	7,102	0.16	0.57	0.59	0.63	0.66	0.68	0.7	80%
Combined	118,389	2.72	0.11	0.17	0.23	0.32	0.37	0.41	11.5%

118389

**Basin Travel Time** 

Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	365	6			4	A
Initial Time	100	4	0.035		11.2	12.0 DCM Eq. 6-8
Shallow Channel	265	3	0.009	0.7	6.5	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
					400	

t<sub>c</sub> 12.0 min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.08	3.85	4.49	5.14	5.78	6.47
Runoff (cfs)	0.9	1.7	2.8	4.5	5.8	7.2
Release Rates (cfs/ac)	-	- 6	- 0.4	-	-	- 3
Allowed Release (cfs)	0.9	1.7	2.8	4.5	5.8	7.2

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

Notes

## Sub-Basin EX B1 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

JurisdictionDCMSoil TypeARunoff CoefficientSurface TypeUrbanizationUrban

Basin Land Use Characteristics

	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	49,443	1.14	0.02	0.08	0.15	0.25	0.3	0.35	0%
Paved	749	0.02	0.89	0.9	0.92	0.94	0.95	0.96	100%
Gravel	214	0.00	0.57	0.59	0.63	0.66	0.68	0.7	80%
Combined	50,406	1.16	0.04	0.09	0.16	0.26	0.31	0.36	1.8%

50406

**Basin Travel Time** 

Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	245	9	-			
Initial Time	100	3	0.032		12.4	11.4 DCM Eq. 6-8
Shallow Channel	145	6	0.041	1.4	1.7	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
					44.4	min

1,11,11111

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.14	3.94	4.59	5.25	5.91	6.61
Runoff (cfs)	0.1	0.4	0.9	1.6	2.1	2.8
Release Rates (cfs/ac)	-	7-	-	T 0-	-	
Allowed Release (cfs)	0.1	0.4	0.9	1.6	2.1	2.8

DCM: I = C1 ° In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10,111 11.375 12.735

Includes Basins OS1 EX A1

Job No.:

61090

Date:

3/22/18 10:03

Project:

Freedom Springs

Calcs by: Checked by: TJW

Jurisdiction

DCM

Soil Type

Α

Runoff Coefficient

Surface Type

Urbanization

Urban

## **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
1/8 Acre or less	123,800	2.84	0.41	0.45	0.49	0.54	0.57	0.59	65%
Pasture/Meadow	103,361	2.37	0.02	0.08	0.15	0.25	0.3	0.35	0%
Paved	7,926	0.18	0.89	0.9	0.92	0.94	0.95	0.96	100%
Gravel	7,102	0.16	0.57	0.59	0.63	0.66	0.68	0.7	80%
Combined	242,189	5.56	0.26	0.31	0.36	0.43	0.47	0.50	38.8%

## **Basin Travel Time**

, , , , , , ,									
	Sub-basin or	Material		Elev.		Base or	Sides		
	Channel Type	Type	L (ft)	$\Delta Z_0$ (ft)	Q <sub>i</sub> (cfs)	Dia (ft)	z:1 (ft/ft)	v (ft/s)	t (min)
Furthest Reach	OS1		580	9			-		13.2
Channelized-1 Channelized-2 Channelized-3	V-Ditch	1	296	12	10	1	2	5.5	0.9
Total			876	21					
	-	= Man-made	Smooth Stra	ight					

t<sub>c</sub> 14.1 (min)

Contributing Offsite Flows (Added to Runoff and Allowed Release, below.)

Contributing Basins/Areas

Q<sub>Minor</sub>

(cfs) - 5-year Storm

Q<sub>Major</sub>

(cfs) - 100-year Storm

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.88	3.61	4.21	4.82	5.42	6.06
Site Runoff (cfs)	4.23	6.24	8.51	11.59	14.17	16.95
OffSite Runoff (cfs)	-	0.00		-		0.00
Release Rates (cfs/ac)		- 4	-	-	-	
Allowed Release (cfs)	- 4	6.2	-	-	-	17.0

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## Notes

Includes Basins OS2 EX B1

Job No.:

61090

Date:

3/22/18 10:03

Project:

Freedom Springs

Calcs by: Checked by: TJW DRG

Jurisdiction

DCM

Soil Type

A

Runoff Coefficient

Surface Type

Urbanization

Urban

## **Basin Land Use Characteristics**

	Area	-0.0	Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
1/8 Acre or less	24,712	0.57	0.41	0.45	0.49	0.54	0.57	0.59	65%
Pasture/Meadow	49,443	1.14	0.02	0.08	0.15	0.25	0.3	0.35	0%
Paved	749	0.02	0.89	0.9	0.92	0.94	0.95	0.96	100%
Gravel	214	0.00	0.57	0.59	0.63	0.66	0.68	0.7	80%
Combined	75,118	1.72	0.16	0.21	0.27	0.35	0.40	0.44	22.6%

## **Basin Travel Time**

er rime	Sub-basin or Channel Type	Material Type	L (ft)	Elev. ΔZ <sub>0</sub> (ft)	Q <sub>i</sub> (cfs)	Base or Dia (ft)	Sides z:1 (ft/ft)	v (ft/s)	t (min)
Furthest Reach Channelized-1 Channelized-2 Channelized-3	EX B1		245	9		1 1			11.4
Total			245	9					

t<sub>c</sub> 11.4 (min)

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.14	3.94	4.59	5.25	5.91	6.61
Site Runoff (cfs)	0.86	1.44	2.15	3.20	4.04	4.97
OffSite Runoff (cfs)	-	0.00	,	-	-	0.00
Release Rates (cfs/ac)	4	-	-	-	-	
Allowed Release (cfs)		1.4	-		- 2	5.0
DCM: [ =	C1 * In (tc)	+ C2				

DCM: J = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## Notes

## **Sub-Basin A1 Runoff Calculations**



Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

Jurisdiction DCM Soil Type A
Runoff Coefficient Surface Type Urbanization Urban

## **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Driveways & Walks	25,793	0.59	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	1,662	0.04	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	27,455	0.63	0.84	0.85	0.87	0.90	0.91	0.92	93.9%

## **Basin Travel Time**

Shallow Channel Ground Cover Paved areas/shallow paved swales

	L <sub>max,Overland</sub>	100 f	t		Cv	20
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	295	4				
Initial Time	100	2	0.015		3.9	11.6 DCM Eq. 6-8
Shallow Channel	35	1	0.014	2.4	0.2	- DCM Eq. 6-9
Channelized	160	2	0.011	2.0	1.3	- C&G
					E E	min

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	4.00	5.02	5.86	6.69	7.53	8.43
Runoff (cfs)	2.1	2.7	3.2	3.8	4.3	4.9
Release Rates (cfs/ac)	-	-		-	-	
Allowed Release (cfs)	2.1	2.7	3.2	3.8	4.3	4.9

DGM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

# **Sub-Basin B1 Runoff Calculations**



Job No.: 61090

Date:

3/22/18 10:03

Project:

**Freedom Springs** 

Calcs by:

TJW

Jurisdiction

DCM

Checked by:

Soil Type

DRG

Α

Runoff Coefficient

Surface Type

Urbanization

Urban

## **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Driveways & Walks	6,096	0.14	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	1,386	0.03	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	7,482	0.17	0.73	0.75	0.78	0.81	0.83	0.85	81.5%

## **Basin Travel Time**

Shallow Channel Ground Cover Paved areas/shallow paved swales

Olimio	in bilailiei biba					
	L <sub>max,Overland</sub>	100 f	t		C <sub>v</sub>	20
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	116	9		-		
Initial Time	100	8	0.080		3.2	10.6 DCM Eq. 6-8
Shallow Channel	16	1	0.063	5.0	0.1	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- C&G
				tc	5.0	min.

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	4.12	5.17	6.03	6.89	7.75	8.68
Runoff (cfs)	0.5	0.7	0.8	1.0	1.1	1.3
Release Rates (cfs/ac)	- 19 <del>3</del>	-		-	-	-
Allowed Release (cfs)	0.5	0.7	0.8	1.0	1.1	1.3

DOIN.	1-01 111/10	1 7 62				
C1	1,19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8,847	10.111	11.375	12.735

# **Sub-Basin C1 Runoff Calculations**



Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

JurisdictionDCMSoil TypeARunoff CoefficientSurface TypeUrbanizationUrban

## **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Driveways & Walks	3,650	0.08	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	1,169	0.03	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	4,819	0.11	0.68	0.70	0.73	0.77	0.79	0.81	75.7%

## **Basin Travel Time**

## Shallow Channel Ground Cover Paved areas/shallow paved swales

	L <sub>max,Overland</sub>	100 f	t		Cv	20
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	160	8		-1	-	
Initial Time	32	1	0.022	- 5	3.1	10.9 DCM Eq. 6-8
Shallow Channel			0.000	0.0	0.0	- DCM Eq. 6-9
Channelized	128	7	0.057	2.5	0.9	- C&G
				tc	5.0	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	4.12	5.17	6.03	6.89	7.75	8.68
Runoff (cfs)	0.3	0.4	0.5	0.6	0.7	0.8
Release Rates (cfs/ac)	-		-	-	0.7	
Allowed Release (cfs)	0.3	0.4	0.5	0.6	0.7	0.

DCM: J = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## Sub-Basin D1 Runoff Calculations

 Job No.:
 61090
 Date:
 3/22/18 10:03

 Project:
 Freedom Springs
 Calcs by:
 TJW

 Checked by:
 DRG

JurisdictionDCMSoil TypeARunoff CoefficientSurface TypeUrbanizationUrban

## **Basin Land Use Characteristics**

7 7 7 7 7 7 7 7 7	Area	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.	
Roofs	15,888	0.36	0.71	0.73	0.75	0.78	0.8	0.81	90%	
Combined	15,888	0.36	0.71	0.73	0.75	0.78	0.80	0.81	90.0%	

## **Basin Travel Time**

Shallow Channel Ground Cover Paved areas/shallow paved swales 20 100 ft Cv L<sub>max,Overland</sub>  $\Delta Z_0$  (ft) So (ft/ft) v (ft/s) t (min) t<sub>All</sub> (min) L (ft) Total 205 2 3.7 Initial Time 30 0 0.010 11.1 DCM Eq. 6-8 Shallow Channel 0.000 0.0 0.0 - DCM Eq. 6-9 2 0.010 5.0 0.6 Channelized 175 - Pipe tc 5.0 min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	4.12	5.17	6.03	6.89	7.75	8.68
Runoff (cfs)	1.1	1.4	1.6	2.0	2.3	2.6
Release Rates (cfs/ac)	-	32		9-	-	
Allowed Release (cfs)	1.1	1.4	1.6	2.0	2.3	2.6

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## **Sub-Basin E1 Runoff Calculations**



Job No.: 61090 Date: 3/22/18 10:03

TJW Project: Calcs by: Freedom Springs Checked by: DRG

Jurisdiction DCM Soil Type Urbanization Urban

Runoff Coefficient Surface Type

## **Basin Land Use Characteristics**

	Area			Runo	off Coeffici	ent	-		%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Driveways & Walks	1,047	0.02	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	6,356	0.15	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	7,403	0.17	0.14	0.20	0.26	0.35	0.39	0.44	14.1%

## **Basin Travel Time**

## Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	87	3			-	
Initial Time	87	3	0.029	- 6	10.7	10.5 DCM Eq. 6-8
Shallow Channel			0.000	0.0	0.0	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- C&G
				to	10.5	min.

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.24	4.06	4.73	5.41	6.09	6.81
Runoff (cfs)	0.1	0.1	0.2	0.3	0.4	0.5
Release Rates (cfs/ac)		-	100		(8)	
Allowed Release (cfs)	0.1	0.1	0.2	0.3	0.4	0.5

DCM: I = C1 \* In (tc) + C2 C1 1,19 1.5 1,75 2.25 2,52 6.035 7.583 8.847 10.111 11.375 12.735

## Sub-Basin F1 Runoff Calculations



Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

JurisdictionDCMSoil TypeARunoff CoefficientSurface TypeUrbanizationUrban

## **Basin Land Use Characteristics**

	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Driveways & Walks	3,305	0.08	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	4,102	0.09	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	7,407	0.17	0.41	0.45	0.49	0.56	0.59	0.62	44.6%

## **Basin Travel Time**

Shallo	w Channel Grou	ind Cover S	Short Pastu	ire/Lawns		
	L <sub>max,Overland</sub>	100 f	ft		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	87	2	-			1.1.4
Initial Time	87	2	0.017		9.2	10.5 DCM Eq. 6-8
Shallow Channel			0.000	0.0	0.0	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- C&G
				t <sub>c</sub>	9.2	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.39	4.25	4.96	5.67	6.38	7.14
Runoff (cfs)	0.2	0.3	0.4	0.5	0.6	0.8
Release Rates (cfs/ac)	-	-	76	-	-	
Allowed Release (cfs)	0.2	0.3	0.4	0.5	0.6	0.8

## Sub-Basin G1 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03 TJW Project: **Freedom Springs** Calcs by: DRG Checked by:

Jurisdiction DCM Soil Type A

Runoff Coefficient Urbanization Urban Surface Type

## **Basin Land Use Characteristics**

	Area	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.	
Lawns	25,376	0.58	0.02	0.08	0.15	0.25	0.3	0.35	0%	
Combined	25,376	0.58	0.02	0.08	0.15	0.25	0.30	0.35	0.0%	

## **Basin Travel Time**

## Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	260	14				
Initial Time	100	4	0.040	0.00	11.7	11.4 DCM Eq. 6-8
Shallow Channel	160	10	0.063	1.8	1.5	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
				t <sub>c</sub>	11.4	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.13	3.93	4.58	5.24	5.89	6.59
Runoff (cfs)	0.0	0.2	0.4	0.8	1.0	1.3
Release Rates (cfs/ac)	(7)	/-	1.0	-	-	
Allowed Release (cfs)	0.0	0.2	0.4	0.8	1.0	1.3

DCM: I = C1 \* In (tc) + C2 CT 2.25 2,52 1 19 1.5 1.75 2 7,583 8.847 10 111 11.375

## Sub-Basin H1 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03 Project: Calcs by: TJW Freedom Springs Checked by: DRG DCM Α Jurisdiction Soil Type Urbanization Urban **Runoff Coefficient** Surface Type

## **Basin Land Use Characteristics**

	Area			Runo	off Coeffici	ent		A 74 G C	%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Driveways & Walks	15,473	0.36	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	4,028	0.09	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	19,501	0.45	0.71	0.73	0.76	0.80	0.82	0.83	79.3%

## **Basin Travel Time**

Shallow Channel Ground Cover Paved areas/shallow paved swales

	L <sub>max,Overland</sub>	100 f	t		C <sub>v</sub>	20
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	310	12			- 2	
Initial Time	65	1	0.015	- 4	4.7	11.7 DCM Eq. 6-8
Shallow Channel			0.000	0.0	0.0	- DCM Eq. 6-9
Channelized	245	11	0.045	3.0	1.4	- C&G
				tc	6.0	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.90	4.89	5.71	6.52	7.34	8.21
Runoff (cfs)	1.2	1.6	1.9	2.3	2.7	3.1
Release Rates (cfs/ac)	0.0	-	-	-	-	-
Allowed Release (cfs)	1.2	1.6	1.9	2.3	2.7	3.1

## Sub-Basin J1 Runoff Calculations

 Job No.:
 61090
 Date:
 3/22/18 10:03

 Project:
 Freedom Springs
 Calcs by:
 TJW

 Checked by:
 DRG

 Jurisdiction
 DCM
 Soil Type
 A

 Runoff Coefficient
 Surface Type
 Urbanization
 Urban

## **Basin Land Use Characteristics**

	Area	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.	
Lawns	20,091	0.46	0.02	0.08	0.15	0.25	0.3	0.35	0%	
Combined	20,091	0.46	0.02	0.08	0.15	0.25	0.30	0.35	0.0%	

## **Basin Travel Time**

## Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		C <sub>v</sub>	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	125	6		-		
Initial Time	100	4	0.040		11.7	10.7 DCM Eq. 6-8
Shallow Channel	25	2	0.080	2.0	0.2	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
				tc	10.7	min.

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.22	4.03	4.70	5.37	6.04	6.76
Runoff (cfs)	0.0	0.1	0.3	0.6	0.8	1.1
Release Rates (cfs/ac)	-	-	-	4.74	-	
Allowed Release (cfs)	0.0	0.1	0.3	0.6	0.8	1.1

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## Sub-Basin K1 Runoff Calculations

Job No.:

61090

Date:

3/22/18 10:03

Project:

Freedom Springs

Calcs by:

TJW

Jurisdiction

....

Checked by:

DRG

Runoff Coefficient

DCM Surface Type Soil Type Urbanization

Urban

## **Basin Land Use Characteristics**

- A page 4-1	Area	Runoff Coefficient							
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Lawns	6,322	0.15	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	6,322	0.15	0.02	0.08	0.15	0.25	0.30	0.35	0.0%

## **Basin Travel Time**

Shallow Channel Ground Cover Paved areas/shallow paved swales

	L <sub>max,Overland</sub>	100 f	t		Cv	20
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	33	4	-	-		
Initial Time	33	4	0.106		4.9	10.2 DCM Eq. 6-8
Shallow Channel			0.000	0.0	0.0	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- C&G
				t <sub>c</sub>	5.0	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	4.12	5.17	6.03	6.89	7.75	8.68
Runoff (cfs)	0.0	0.1	0.1	0.3	0.3	0.4
Release Rates (cfs/ac) Allowed Release (cfs)	0.0	0.1	0.1	0.3	0.3	0.4

DOIVI.	1-01 111/10	1 42				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10,111	11.375	12.735

## Sub-Basin L1 Runoff Calculations

 Job No.:
 61090
 Date:
 3/22/18 10:03

 Project:
 Freedom Springs
 Calcs by:
 TJW

 Checked by:
 DRG

JurisdictionDCMSoil TypeARunoff CoefficientSurface TypeUrbanizationUrban

## **Basin Land Use Characteristics**

	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Lawns	19,790	0.45	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	19,790	0.45	0.02	0.08	0.15	0.25	0.30	0.35	0.0%

## **Basin Travel Time**

## Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	240	15		5	-	
Initial Time	100	6	0.055	-	10.5	11.3 DCM Eq. 6-8
Shallow Channel	140	10	0.068	1.8	1.3	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
				tc	11.3 1	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	3.15	3.94	4.60	5.26	5.91	6.62
Runoff (cfs)	0.0	0.1	0.3	0.6	0.8	1.1
Release Rates (cfs/ac)	-	-		1	- 2	
Allowed Release (cfs)	0.0	0.1	0.3	0.6	0.8	1.1

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## Sub-Basin M1 Runoff Calculations

Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

 Jurisdiction
 DCM
 Soil Type
 A

 Runoff Coefficient
 Surface Type
 Urbanization
 Urban

**Basin Land Use Characteristics** 

F - T	Area	Runoff Coefficient							
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Lawns	5,771	0.13	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	5,771	0.13	0.02	0.08	0.15	0.25	0.30	0.35	0.0%

## **Basin Travel Time**

Shallow Channel Ground Cover Short Pasture/Lawns

	L <sub>max,Overland</sub>	100 f	t		Cv	7
	L (ft)	$\Delta Z_0$ (ft)	So (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	32	3				5 - 2 - 3 - 3
Initial Time	32	3	0.088		5.1	10.2 DCM Eq. 6-8
Shallow Channel			0.000	0.0	0.0	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
				tc	5.1	min.

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Үг	50-Yr	100-Yr
Intensity (in/hr)	4.10	5.14	6.00	6.86	7.71	8.63
Runoff (cfs)	0.0	0.1	0.1	0.2	0.3	0.4
Release Rates (cfs/ac) Allowed Release (cfs)	0.0	0.1	0.1	0.2	0.3	0.4

Includes Basins OS2 L1

Job No.:

61090

Date:

3/22/18 10:03

Project:

Freedom Springs

Calcs by: Checked by: TJW DRG

Jurisdiction

DCM

Soil Type

Α

Runoff Coefficient

**Surface Type** 

Urbanization

Urban

## **Basin Land Use Characteristics**

	Area		Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
1/8 Acre or less	24,712	0.57	0.41	0.45	0.49	0.54	0.57	0.59	65%
Lawns	19,790	0.45	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	44,502	1.02	0.24	0.29	0.34	0.41	0.45	0.48	36.1%

## **Basin Travel Time**

	Sub-basin or	Material		Elev.		Base or	Sides		
	Channel Type	Type	L (ft)	$\Delta Z_0$ (ft)	Q <sub>i</sub> (cfs)	Dia (ft)	z:1 (ft/ft)	v (ft/s)	t (min)
Furthest Reach	OS2	1	190	3	4	- 4		14	11.1
Channelized-1	V-Ditch	2	76	12	2	1	2	4.0	0.3
Channelized-2						1			
Channelized-3									
Total			266	15					
	2	2 = Natural, Wi	nding, minima	vegetation/s	hallow grass			t.	77.2

t<sub>c</sub> 11.4 (min)

## Contributing Offsite Flows (Added to Runoff and Allowed Release, below.)

Contributing Basins/Areas

Q<sub>Minor</sub> Q<sub>Major</sub> (cfs) - 5-year Storm (cfs) - 100-year Storm

Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yi
Intensity (in/hr)	3.14	3.94	4.59	5.25	5.90	6.61
Site Runoff (cfs)	0.76	1.15	1.59	2.20	2.71	3.26
OffSite Runoff (cfs)	-	0.00	-		-	0.00
Release Rates (cfs/ac)		- 1	-	-	-	
Allowed Release (cfs)	-	1.1		-	-	3.3

## Notes



Urbanization

Urban

Includes Basins OS1 H1

Job No.: 61090 Date: 3/22/18 10:03

Project: Freedom Springs Calcs by: TJW Checked by: DRG

Jurisdiction DCM Soil Type A

Runoff Coefficient Surface Type

## **Basin Land Use Characteristics**

	Area		7	Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
1/8 Acre or less	123,800	2.84	0.41	0.45	0.49	0.54	0.57	0.59	65%
Driveways & Walks	15,473	0.36	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	4,028	0.09	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	143,301	3.29	0.45	0.49	0.53	0.58	0.60	0.62	67.0%

## **Basin Travel Time**

	Sub-basin or	Material		Elev.		Base or	Sides		
	Channel Type	Type	L (ft)	$\Delta Z_0$ (ft)	Q <sub>i</sub> (cfs)	Dia (ft)	z:1 (ft/ft)	v (ft/s)	t (min)
Furthest Reach	OS1		580	9					13.2
Channelized-1	C&G	Asphalt	286	12	10	1	0	4.0	1.2
Channelized-2						1			
Channelized-3									
Total			866	21					

t<sub>c</sub> 14.4 (min)

## Contributing Offsite Flows (Added to Runoff and Allowed Release, below.)

Contributing Basins/Areas

 Q<sub>Minor</sub>
 (cfs) - 5-year Storm

 Q<sub>Major</sub>
 (cfs) - 100-year Storm

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.86	3.58	4.18	4.77	5.37	6.01
Site Runoff (cfs)	4.24	5.75	7.24	9.03	10.66	12.32
OffSite Runoff (cfs)	- 2	0.00	-	-	- 9	0.00
Release Rates (cfs/ac) Allowed Release (cfs)		5.7				12.3
DCM: 1 = C1	C1 * In (tc	+ C2 1.5	1.75	2	2.25	2.52

C2 6.035 7.583 8.847 10.111 11.375 12.735

## Notes



Includes Basins A1 B1 C1 D1 E1 F1 G1 H1

Job No.:

61090

Date:

3/22/18 10:03

Project:

Freedom Springs

Calcs by: Checked by: TJW DRG

Jurisdiction

DCM

Soil Type

Α

**Runoff Coefficient** 

Surface Type

Urbanization

Urban

## **Basin Land Use Characteristics**

	Area	encorpt of the control		Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Roofs	15,888	0.36	0.71	0.73	0.75	0.78	0.8	0.81	90%
Driveways & Walks	55,364	1.27	0.89	0.9	0.92	0.94	0.95	0.96	100%
Lawns	44,079	1.01	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	115,331	2.65	0.53	0.56	0.60	0.65	0.68	0.71	60.4%

## **Basin Travel Time**

71 1111									
	Sub-basin or	Material		Elev.		Base or	Sides		
	Channel Type	Type	L (ft)	$\Delta Z_0$ (ft)	Q <sub>i</sub> (cfs)	Dia (ft)	z:1 (ft/ft)	v (ft/s)	t (min)
Furthest Reach	A1		295	4				Ce.	5.5
Channelized-1	Pipe	HDPE	119	5	5	1	0	5.9	0.3
Channelized-2	Pipe	HDPE	116	4	5	1	0	5.4	0.4
Channelized-3									
Total			530	12					

t<sub>c</sub> 6.2 (min)

## Contributing Offsite Flows (Added to Runoff and Allowed Release, below.)

Contributing Basins/Areas

Q<sub>Minor</sub> Q<sub>Maior</sub> (cfs) - 5-year Storm (cfs) - 100-year Storm

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yi
Intensity (in/hr)	3.86	4.84	5.65	6.46	7.26	8.13
Site Runoff (cfs)	5.45	7.22	9.01	11.19	13.10	15.20
OffSite Runoff (cfs)		0.00		-	-	0.00
Release Rates (cfs/ac)		-		-	-	
Allowed Release (cfs)	-	7.2	-	-	-	15.2

DCM: I = C1 \* In (tc) + C2 C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

## Notes


# 10 Hydraulic Calculations

Inlet Calculations Storm Drain Pipe Calculations Detention Pond Calculations

### Version 4.05 Released March 2017

## ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread) Freedom Springs Inlet DP1



Project: Inlet ID:


Gutter Geometry (Enter data in the blue cells)				
Maximum Allowable Width for Spread Behind Curb	TBACK =	0.0	ft	
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	SBACK =	0.020	ft/ft	
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	n <sub>BACK</sub> =	0.020		
Height of Curb at Gutter Flow Line	H <sub>cure</sub> =	6.00	inches	
Distance from Curb Face to Street Crown	T <sub>CROWN</sub> =	18.0	ft	
Gutter Width	W =	2.00	n	
Street Transverse Slope	S <sub>X</sub> =	0.035	ft/ft	
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	S <sub>W</sub> =	0.083	ft/ft	
Street Longitudinal Slope - Enter 0 for sump condition	So =	0.000	ft/ft	
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	n <sub>STREET</sub> =	0.016	]	
		Minor Storm	Major Storm	
Max. Allowable Spread for Minor & Major Storm	T <sub>MAX</sub> =	9.0	18.0	it.
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	d <sub>MAX</sub> =	6.0	6.0	inches
Check boxes are not applicable in SUMP conditions	-	F		70.7

Max. Allowable Spread for Minor & Major Storm	Tuax =	9.0	18.0	R
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	d <sub>MAX</sub> =	6.0	6.0	inches
Check boxes are not applicable in SUMP conditions		F		30.7
Maximum Capacity for 1/2 Street based On Allowable Spread		Minor Storm	Major Storm	
Water Depth without Gutter Depression (Eq. ST-2)	y=	3.78	7.56	inches
Vertical Depth between Gutter Lip and Gutter Flowline (usually 2")	d <sub>c</sub> =	2.0	2.0	inches
Gutter Depression (d <sub>C</sub> - (W * S <sub>x</sub> * 12))	a =	1.15	1.15	inches
Water Depth at Gutter Flowline	d =	4.93	8.71	inches
Allowable Spread for Discharge outside the Gutter Section W (T - W)	T <sub>x</sub> =	7.0	16.0	n
Gutter Flow to Design Flow Ratio by FHWA HEC-22 method (Eq. ST-7)	E <sub>0</sub> =	0.556	0.296	
Discharge outside the Gutter Section W, carried in Section $T_X$	Q <sub>x</sub> =	0.0	0.0	cfs
Discharge within the Gutter Section W (Q <sub>T</sub> - Q <sub>x</sub> )	Q <sub>w</sub> =	0.0	0.0	cfs
Discharge Behind the Curb (e.g., sidewalk, driveways, & lawns)	Q <sub>BACK</sub> =	0.0	0.0	cfs
Maximum Flow Based On Allowable Spread	Q <sub>7</sub> =	SUMP	SUMP	cfs
Flow Velocity within the Gutter Section	V=	0.0	0.0	fps
V*d Product: Flow Velocity times Gutter Flowline Depth	V*d =	0.0	0.0	
Maximum Capacity for 1/2 Street based on Allowable Depth		Minor Storm	Major Storm	
Theoretical Water Spread	Tru =	11.5	11,5	n
Theoretical Spread for Discharge outside the Gutter Section W (T - W)	T <sub>XTH</sub> =	9.5	9.5	ft
Gutter Flow to Design Flow Ratio by FHWA HEC-22 method (Eq. ST-7)	E <sub>o</sub> =	0.449	0.449	7
Theoretical Discharge outside the Gutter Section W, carried in Section TxTH	Q <sub>XTH</sub> =	0.0	0.0	cfs
Actual Discharge outside the Gutter Section W, (limited by distance TCROWN)	Q <sub>X</sub> =	0.0	0.0	cfs
Discharge within the Gutter Section W (Q <sub>g</sub> - Q <sub>y</sub> )	Q <sub>w</sub> =	0.0	0.0	cfs
Discharge Behind the Curb (e.g., sidewalk, driveways, & lawns)	Q <sub>BACK</sub> =	0.0	0.0	cfs
Total Discharge for Major & Minor Storm (Pre-Safety Factor)	Q=	0.0	0.0	cfs
Average Flow Velocity Within the Gutter Section	V=	0.0	0.0	fps
V*d Product: Flow Velocity Times Gutter Flowline Depth	V*d =	0.0	0.0	
Slope-Based Depth Safety Reduction Factor for Major & Minor (d ≥ 6") Storm	R =	SUMP	SUMP	
Max Flow Based on Allowable Depth (Safety Factor Applied)	Q <sub>0</sub> =	SUMP	SUMP	cfs
Resultant Flow Depth at Gutter Flowline (Safety Factor Applied)	d =			inches
Resultant Flow Depth at Street Crown (Safety Factor Applied)	d <sub>CROWN</sub> =			inches

MINOR STORM Allowable Capacity is based on Depth Criterion		Minor Storm	Major Storm	-
MAJOR STORM Allowable Capacity is based on Depth Criterion	Q <sub>allow</sub> =	SUMP	SUMP	cfs

## INLET IN A SUMP OR SAG LOCATION

## Version 4.05 Released March 2017



Design Information (Input) Denver No. 16 Co	mbination		MINOR	MAJOR	
Type of inlet	in bill audit	Type =	Denver No. 1	6 Combination	11 200
Local Depression (additional to continuous gutter depressi	on 'a' from above)	a <sub>local</sub> =	2.00	5.00	inches
Number of Unit Inlets (Grate or Curb Opening)		No =	2	2,	
Water Depth at Flowline (outside of local depression)		Ponding Depth =	4.9	6.0	inches
Grate Information			MINOR	MAJOR	C Override Depth
Length of a Unit Grate		L <sub>a</sub> (G) =	3.00	3.00	feet
Width of a Unit Grate		W <sub>o</sub> =	1.73	1.73	feet
Area Opening Ratio for a Grate (typical values 0.15-0.90)		A <sub>ratio</sub> =	0.31	031	
Clogging Factor for a Single Grate (typical value 0.50 - 0.7	(0)	C, (G) =	0.50	0.50	
Grate Weir Coefficient (typical value 2.15 - 3.60)		C, (G) =	3.60	3.50	
Grate Orifice Coefficient (typical value 0.60 - 0.80)		C <sub>a</sub> (G) =	0.60	0.50	
Curb Opening Information			MINOR	MAJOR	
Length of a Unit Curb Opening		La (C) =	3.00	3.00	feet
Height of Vertical Curb Opening in Inches		H <sub>vert</sub> =	6.50	6.50	inches
Height of Curb Orifice Throat in Inches		H <sub>pypat</sub> =	5.25	5.25	inches
Angle of Throat (see USDCM Figure ST-5)		Theta =	0.00	0.00	degrees
Side Width for Depression Pan (typically the gutter width o	of 2 feet)	W <sub>p</sub> =	1.00	1.00	feet
Clogging Factor for a Single Curb Opening (typical value	0.10)	$C_t(C) =$	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)		C,, (C) =	3.70	3.70	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70	)	C <sub>o</sub> (C) =	0.66	33.0	
Low Head Performance Reduction (Calculated)			MINOR	MAJOR	
Depth for Grate Midwidth		d <sub>Grate</sub> =	0.434	0,523	ft
Depth for Curb Opening Weir Equation		d <sub>Curb</sub> =	0.25	0.33	ft
Combination Inlet Performance Reduction Factor for Long	Inlets	RFCombination =	0.58	0.71	
Curb Opening Performance Reduction Factor for Long Inl	ets	RF <sub>curb</sub> =	1.00	1.00	
Grated Inlet Performance Reduction Factor for Long Inlets		RF <sub>Grate</sub> =	0.58	0.71	1
		-	MINOR	MAJOR	57.
Total Inlet Interception Capacity (assumes of	logged condition)	Q <sub>a</sub> =	3.6	6.2	cfs
Inlet Capacity IS GOOD for Minor and Major Storms(>	O PEAK)	Q PEAK REQUIRED =	2.7	4.9	cfs


Warning 1: Dimension entered is not a typical dimension for inlet type specified.

## Version 4.05 Released March 2017

## ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)
Freedom Springs
Inlet DP2


Project: Inlet ID:



Sutter Geometry (Enter data in the blue cells)	and the second second		_	
Maximum Allowable Width for Spread Behind Curb	T <sub>BACK</sub> =	0.0	n	
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	SBACK =	0.020	first	
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	n <sub>BACK</sub> =	0.020	1	
Height of Curb at Gutter Flow Line	H <sub>cura</sub> =	6.00	inches	
Distance from Curb Face to Street Crown	TCROWN =	18,0	n	
Sutter Width	W=	2.00	n	
Street Transverse Slope	S <sub>X</sub> =	0.017	rvrt.	
Gutter Cross Slope (typically 2 inches over 24 inches or 0,083 ft/ft)	S <sub>W</sub> =	0.083	rvn	
Street Longitudinal Slope - Enter 0 for sump condition	So=	0.000	rvn	
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	n <sub>STREET</sub> =	0,016	1	
		Minor Storm	Major Storm	
Max, Allowable Spread for Minor & Major Storm	T <sub>MAX</sub> =	9,0	18,0	ft
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	d <sub>MAX</sub> =	6.0	6,0	inches
Check boxes are not applicable in SUMP conditions	-	- п	F	
MINOR STORM Allowable Consider to based as Posts Calcula		Minor Storm	Major Storm	
MINOR STORM Allowable Capacity is based on Depth Criterion MAJOR STORM Allowable Capacity is based on Depth Criterion	Q <sub>allow</sub> =	SUMP	SUMP	cfs

## INLET IN A SUMP OR SAG LOCATION

## Version 4.05 Released March 2017



Design Information (Input)	[ B		MINOR	MAJOR	
Type of Inlet	Denver No. 16 Combination	Type =	Denver No. 16	Combination	
Local Depression (additional to c	ontinuous gutter depression 'a' from above)	a <sub>local</sub> =	2.00	2:00	inches
Number of Unit Inlets (Grate or C	curb Opening)	No =	1	- p	
Water Depth at Flowline (outside	of local depression)	Ponding Depth =	3.4	5.3	inches
Grate Information			MINOR	MAJOR	Coverride Depths
Length of a Unit Grate		L <sub>0</sub> (G) =	3,00	3.00	feet
Width of a Unit Grate		W <sub>o</sub> =	1,73	173.	feet
Area Opening Ratio for a Grate (	typical values 0,15-0,90)	A <sub>ratio</sub> =	0,31	-0.31	
Clogging Factor for a Single Gra	te (typical value 0.50 - 0.70)	C, (G) =	0.50	0.50	
Grate Weir Coefficient (typical va	alue 2.15 - 3.60)	C, (G) =	3,60	3.67	
Grate Orifice Coefficient (typical	value 0.60 - 0.80)	C <sub>o</sub> (G) =	0.60	0.83	
Curb Opening Information	-5.00-22.		MINOR	MAJOR	
Length of a Unit Curb Opening		L <sub>2</sub> (C) =	3.00	3.00	feet
Height of Vertical Curb Opening	in Inches	H <sub>vert</sub> =	6.50	6.50	inches
Height of Curb Orifice Throat in I	nches	H <sub>Dynat</sub> =	5.25	5,05	inches
Angle of Throat (see USDCM Fig	jure ST-5)	Theta =	0.00	0.03	degrees
Side Width for Depression Pan (	typically the gutter width of 2 feet)	W <sub>p</sub> =	2.00	2.00	feet
Clogging Factor for a Single Cur	b Opening (typical value 0,10)	C <sub>f</sub> (C) =	0.10	0.10	
Curb Opening Weir Coefficient (	typical value 2.3-3.7)	C, (C) =	3.70	3.70	
Curb Opening Orifice Coefficient	(typical value 0.60 - 0.70)	C <sub>o</sub> (C) =	0.66	0.05	3
Low Head Performance Reduc	tion (Calculated)		MINOR	MAJOR	
Depth for Grate Midwidth		d <sub>Grate</sub> =	0,308	0.461	ft.
Depth for Curb Opening Weir Ed	uation	d <sub>Curb</sub> =	0.12	0.27	n
Combination Inlet Performance I	Reduction Factor for Long Inlets	RF <sub>Combination</sub> =	0.53	0.82	3
Curb Opening Performance Red	uction Factor for Long Inlets	RF <sub>Curb</sub> =	1.00	1.00	
Grated Inlet Performance Reduc	tion Factor for Long Intets	RF <sub>Grate</sub> =	0.53	0,82	
			MINOR	MAJOR	2.
Total Inlet Interception C	apacity (assumes clogged condition)	Q <sub>a</sub> =	0,9	2.9	cfs
Inlet Capacity IS GOOD for Mir	nor and Major Storms(>Q PEAK)	Q PEAK REQUIRED =	0.7	1.3	cfs

#### Version 4.05 Released March 2017 ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm) (Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread) Freedom Springs Project: Inlet ID: Inlet DP3 STREET ō. Gutter Geometry (Enter data in the blue cells) Maximum Allowable Width for Spread Behind Curb 0.0 Side Slope Behind Curb (leave blank for no conveyance credit behind curb) ft/ft 0.020 Manning's Roughness Behind Curb (typically between 0.012 and 0.020) 0.020 Height of Curb at Gutter Flow Line Distance from Curb Face to Street Crown HOURE 6.00 18.0 Gutter Width W: 2.00 Street Transverse Slope Sx 0.063 n/n Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft) Sw 0.083 frit Street Longitudinal Stope - Enter 0 for sump condition So 0.084 ft/ft Manning's Roughness for Street Section (typically between 0.012 and 0.020) **N**STREET 0.016 Minor Storm Major Storm Max. Allowable Spread for Minor & Major Storm 9.0 18.0 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm 6.0 6.0 Allow Flow Depth at Street Crown (leave blank for no) check = yes

Minor Storm

Qatlow =

Major Storm

3/7/18, 4:51 PM

MINOR STORM Allowable Capacity is based on Depth Criterion


MAJOR STORM Allowable Capacity is based on Depth Criterion

Minor storm max, allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management Major storm max, allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'

61090-UD-Inlet\_v4.05-1.xlsm, Inlet DP3

## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017



Design Information (Input)	Describe as Sections	-1		MINOR	MAJOR	
Type of Inlet	Denver No. 16 Combination	-	Type =	Denver No. 16	Combination	
Local Depression (additional to co	ntinuous gutter depression 'a')		BLOCAL =	2.0	2.0	inches
Total Number of Units in the Inlet	(Grate or Curb Opening)		No=	1	1	
Length of a Single Unit Inlet (Grate	e or Curb Opening)		Lo=	3.00	3 00	n
Width of a Unit Grate (cannot be g	realer than W, Gutter Width)		W <sub>o</sub> =	1.73	1.73	it
Clogging Factor for a Single Unit	Grate (typical min. value = 0.5)		CrG =	0.50	0.50	
Clogging Factor for a Single Unit	Curb Opening (typical min. value = 0.1)		CrC =	0.10	0.10	4 11 15
Street Hydraulics; OK - Q < Allo	wable Street Capacity'			MINOR	MAJOR	
Total Inlet Interception Capacity			Q=	0.3	0.5	cfs
Total Inlet Carry-Over Flow (flow	v bypassing inlet)		Q <sub>b</sub> =	0.1	0.3	cfs
Capture Percentage = QJQ =			C% =	69	66	%

## Version 4.05 Released March 2017

#### ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm) (Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread) Freedom Springs Project: Inlet ID: STREET Ó. Gutter Geometry (Enter data in the blue cells) 0.0 Maximum Allowable Width for Spread Behind Curb Side Slope Behind Curb (leave blank for no conveyance credit behind curb) n/n 0.020 Manning's Roughness Behind Curb (typically between 0.012 and 0.020) 0.020 HOURB Height of Curb at Gutter Flow Line 6.00 Distance from Curb Face to Street Crown 16,0 Gutter Width W: 2.00 Street Transverse Slope Sx 0.020 ft/ft Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft) SW 0.083 ivit Street Longitudinal Stope - Enter 0 for sump condition So 0.043 fvft Manning's Roughness for Street Section (typically between 0.012 and 0.020) **NSTREET** 0.016 Minor Storm Major Storm Max. Allowable Spread for Minor & Major Storm 16,0 16.0 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm inches 6.0 6,0 check = yes Allow Flow Depth at Street Crown (leave blank for no) MINOR STORM Allowable Capacity is based on Depth Criterion Minor Storm Major Storm

Q<sub>allow</sub> =

15.9

15.9


cfs

MAJOR STORM Allowable Capacity is based on Depth Criterion

Minor storm max, allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Managemen' Major storm max, allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'


## INLET ON A CONTINUOUS GRADE

Version 4.05 Released March 2017




Design Information (Input)	D	-1		MINOR	MAJOR	
Type of Inlet	Denver No. 16 Combination	71	Type =	Denver No. 16	6 Combination	
Local Depression (additional to co	ntinuous gutter depression 'a')		aLOCAL =	2.0	20	inches
Total Number of Units in the Inlet	(Grate or Curb Opening)		No=	1		
Length of a Single Unit Inlet (Grate	e or Curb Opening)		L <sub>o</sub> =	3.00	3.00	ft
Width of a Unit Grate (cannot be g	reater than W, Gutter Width)		W <sub>o</sub> =	1.73	1.73	n
Clogging Factor for a Single Unit	Grate (typical min. value = 0.5)		CrG =	0,50	0,50	
Clogging Factor for a Single Unit (	Curb Opening (typical min. value = 0.1)		CrC =	0.10	0.10	
Street Hydraulics: OK - Q < Allo	wable Street Capacity'			MINOR	MAJOR	
<b>Total Inlet Interception Capacity</b>			Q=	2.3	3.1	cfs
Total Inlet Carry-Over Flow (flow	v bypassing inlet)		Q <sub>6</sub> =	3.4	9,2	cfs
Capture Percentage = Q /Q =			C% =	40	25	%


61090-UD-Inlet\_v4.05-1.xism, Inlet DP4



Major storm max, allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'



## Freedom Springs Inlet DP6



This worksheet uses the NRCS vegetal retardance method to determine Manning's n.

For more information see Section 7.2.3 of the USDCM.

	dal Grass-Lined Channel L	Daning acco method		C	1	
	ance (A, B, C, D, or E)	Electric Section	A, B, C, D or E		-	
	ell D16 blank to manually en	iter an n value)		see details below	4	
Channel Invert Slope			So=	0.0200	fuft	
Bottom Width			B=	3.00	n	
Left Side Slope			Z1 =	20.00	n/n	
Right Side Slope			Z2 =	20.00	ft/ft	
Check one of the follo			ro	Choose One:		7
Soil Type:	Max. Velocity (Vusx)	Max Froude No. (Fwar)		Non-Cohesiv	e	
Non-Cohesive	5.0 fps	0,60		Cohesive		
Mary Control						
Cohesive	7.0 fps	0.80		C Paved		
Mary Control		0.80 N/A		71.3 22.5	12'17 AUTO	
Cohesive Paved	7.0 fps N/A	N/A		Minor Storm	Major Storm	
Cohesive Paved Max. Allowable Top W	7.0 fps N/A Vidth of Channel for Minor &	N/A Major Storm	T <sub>MAX</sub> =	Minor Storm 16,00	23.00	feet
Cohesive Paved Max. Allowable Top W	7.0 fps N/A	N/A Major Storm	T <sub>MAX</sub> = d <sub>MAX</sub> =	Minor Storm		feet feet
Cohesive Paved Max. Allowable Top W Max. Allowable Water	7.0 fps N/A Vidth of Channel for Minor &	N/A Major Storm & Major Storm		Minor Storm 16,00	23.00	- C C
Cohesive Paved Max. Allowable Top W Max. Allowable Water Allowable Channel C	7.0 fps N/A N/dth of Channel for Minor & Depth in Channel for Minor	N/A Major Storm & Major Storm		Minor Storm 16,00 0,33	23.00 0.50	- C C
Cohesive Paved  Max. Allowable Top W Max. Allowable Water  Allowable Channel C MINOR STORM Allow	7.0 fps N/A  Vidth of Channel for Minor & Depth in Channel for Minor	N/A Major Storm & Major Storm I Geometry Top Width Criterion	d <sub>MAX</sub> =	Minor Storm 16,00 0,33 Minor Storm	23.00 0.50 Major Storm	feet
Cohesive Paved  Max. Allowable Top W Max. Allowable Water  Allowable Channel C MINOR STORM Allow	7.0 fps N/A  Vidth of Channel for Minor & Depth in Channel for Minor  apacity Based On Channel Vable Capacity is based or	N/A Major Storm & Major Storm I Geometry Top Width Criterion	d <sub>MAX</sub> =	Minor Storm 16,00 0.33 Minor Storm 0.5	23.00 0.50 Major Storm	feet
Cohesive Paved  Max. Allowable Top W Max. Allowable Water  Allowable Channel C  MINOR STORM Allow  MAJOR STORM Allow	7.0 fps N/A  Vidth of Channel for Minor & Depth in Channel for Minor  apacity Based On Channel Vable Capacity is based or	N/A Major Storm & Major Storm I Geometry n Top Width Criterion n Depth Criterion	d <sub>MAX</sub> =	Minor Storm 16,00 0.33 Minor Storm 0.5	23.00 0.50 Major Storm	feet
Cohesive Paved  Max. Allowable Top W Max. Allowable Water  Allowable Channel C  MINOR STORM Allow  MAJOR STORM Allow	7.0 fps N/A  fidth of Channel for Minor & Depth in Channel for Minor  apacity Based On Channel wable Capacity is based or wable Capacity is based or	N/A Major Storm & Major Storm I Geometry n Top Width Criterion n Depth Criterion	d <sub>MAX</sub> =	Minor Storm 16,00 0.33 Minor Storm 0.5	23.00 0.50 Major Storm	feet


#### Freedom Springs Inlet DP6 Inlet Design Information (Input) User-Defined + User-Defined Inlet Type = Type of Inlet Angle of Inclined Grate (must be <= 30 degrees) Width of Grate degrees W= 1.00 feet Length of Grate 1.00 feet L= Open Area Ratio 0.70 ARATIO Height of Inclined Grate Ha : 0.00 feet Clogging Factor C,= 0.50 Grate Discharge Coefficient Cd = N/A Orifice Coefficient C. 0.64 FLON Weir Coefficient 2.05 MINOR MAJOR Water Depth at Inlet (for depressed inlets, 1 foot is added for depression) 0.26 0.40 Total Inlet Interception Capacity (assumes clogged condition) Qa= 8,0 1.1 cfs Bypassed Flow, Qb 0.0 0.0 cfs Capture Percentage = Q\_/Q\_ = C% 100 100

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Wednesday, Mar 7 2018

# Pipe from DP1 inlet to MH1

Circular		Highlighted	
Diameter (ft)	= 1.00	Depth (ft)	= 0.80
		Q (cfs)	= 4.900
		Area (sqft)	= 0.67
Invert Elev (ft)	= 100.00	Velocity (ft/s)	= 7.27
Slope (%)	= 2.00	Wetted Perim (ft)	= 2.22
N-Value	= 0.013	Crit Depth, Yc (ft)	= 0.92
		Top Width (ft)	= 0.80
Calculations		EGL (ft)	= 1.62
Compute by:	Known Q	2.14004	
Known O (cfs)	= 4 90		




Reach (ft)

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Wednesday, Mar 7 2018

# Pipe from DP2 inlet to MH1

Circular		Highlighted	
Diameter (ft)	= 1.00	Depth (ft)	= 0.42
Common Services		Q (cfs)	= 1.300
		Area (sqft)	= 0.32
Invert Elev (ft)	= 100.00	Velocity (ft/s)	= 4.12
Slope (%)	= 1.00	Wetted Perim (ft)	= 1.41
N-Value	= 0.013	Crit Depth, Yc (ft)	= 0.48
		Top Width (ft)	= 0.99
Calculations		EGL (ft)	= 0.68
Compute by:	Known Q	100 110 120 100 1	
Known Q (cfs)	= 1.30		




Reach (ft)

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Wednesday, Mar 7 2018

# Pipe from DP3 inlet to MH1

Circular		Highlighted	
Diameter (ft)	= 1.00	Depth (ft)	= 0.33
		Q (cfs)	= 0.800
		Area (sqft)	= 0.23
Invert Elev (ft)	= 100.00	Velocity (ft/s)	= 3.53
Slope (%)	= 1.00	Wetted Perim (ft)	= 1.22
N-Value	= 0.013	Crit Depth, Yc (ft)	= 0.38
		Top Width (ft)	= 0.94
Calculations		EGL (ft)	= 0.52
Compute by:	Known Q	71.55	
Known Q (cfs)	= 0.80		




Reach (ft)

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Wednesday, Mar 7 2018

# Pipe from MH1 to Pond

Circular		Highlighted	
Diameter (ft)	= 1.50	Depth (ft)	= 1.07
		Q (cfs)	= 12.70
		Area (sqft)	= 1.35
Invert Elev (ft)	= 100.00	Velocity (ft/s)	= 9.40
Slope (%)	= 2.00	Wetted Perim (ft)	= 3.02
N-Value	= 0.013	Crit Depth, Yc (ft)	= 1.34
		Top Width (ft)	= 1.35
Calculations		EGL (ft)	= 2.44
Compute by:	Known Q		
Known Q (cfs)	= 12.70		



Reach (ft)

	Design Procedure Fo	orm: Sand Filter (SF)	
	UD-BMP (Version 3.0	3, November 2016)	Sheet 1 of
Designer:	TJW		
Company:	M.V.E., Inc.		
Date:	March 23, 2018		
Project:	Freedom Springs	<del></del>	
	DP 7		
Location:	DF 7	<del></del>	
1. Basin Sto	rage Volume		
The state of the s	ve Imperviousness of Tributary Area, I <sub>a</sub> if all paved and roofed areas upstream of sand filter)	I <sub>a</sub> =%	
B) Tribut	ary Area's Imperviousness Ratio (i = I <sub>a</sub> /100)	i =0.618	
	Quality Capture Volume (WQCV) Based on 12-hour Drain Time $V = 0.8 * (0.91*i^3 - 1.19*i^2 + 0.78*i)$	WQCV = 0.19 watershed inches	
D) Contri	buting Watershed Area (including sand filter area)	Area = <u>97,781</u> sq ft	
	Quality Capture Volume (WQCV) Design Volume CV = WQCV / 12 * Area	V <sub>wacv</sub> =1,580 cu ft	
	fatersheds Outside of the Denver Region, Depth of age Runoff Producing Storm	d <sub>6</sub> = in	
	Vatersheds Outside of the Denver Region, r Quality Capture Volume (WQCV) Design Volume	V <sub>WGCV OTHER</sub> =1,543 cu ft	
	Input of Water Quality Capture Volume (WQCV) Design Volume if a different WQCV Design Volume is desired)	V <sub>WQCV USER</sub> = cu ft	
2. Basin Ge	ometry		
A) WQC	/ Depth	D <sub>Wacv</sub> =ft	
	Filter Side Slopes (Horizontal distance per unit vertical, flatter preferred). Use "0" if sand filter has vertical walls.	Z =ft / ft	
C) Minim	um Filter Area (Flat Surface Area)	A <sub>Mm</sub> = 55 sq ft	
D) Actual	Filter Area	A <sub>Actual</sub> =sq ft	
E) Volum	e Provided	V <sub>T</sub> =cu ft	
3. Filter Mat	terial	Choose One  ●18" CDOT Class B or C Filter Material  Other (Explain):	
4. Underdra	nin System	Choose One	
A) Are ur	nderdrains provided?	OYES NO	
B) Under	drain system orifice diameter for 12 hour drain time		
	Distance From Lowest Elevation of the Storage     Volume to the Center of the Orifice	y = <u>N/A</u> ft	
	ii) Volume to Drain in 12 Hours	Vol <sub>12</sub> = <u>N/A</u> cu ft	
	iii) Orifice Diameter, 3/8" Minimum	$D_0 = N/A$ in	


	Design Procedure	Form: Sand Filter (SF)
Designer:	TJW	Sheet 2 of 2
Company:	M.V.E., Inc.	
Date:	March 23, 2018	
Project:	Freedom Springs	
Location:	DP 7	
	impermeable liner provided due to proximity ructures or groundwater contamination?	OYES ●NO
	utlet Works  ribe the type of energy dissipation at inlet points and means of  eying flows in excess of the WQCV through the outlet	Outflows are small and will discharge to concrete channel to Western Drive  Emergency spillway lined with rip rap to Western Drive
Notes:		

## **DETENTION BASIN STAGE-STORAGE TABLE BUILDER**

UD-Detention, Version 3.07 (February 2017)

Project: Freedom Springs

Basin ID: Full Spectrum Sand Filter Basin - DP7



## Required Volume Calculation

lired volume Calculation		77
Selected BMP Type =	SF	
Watershed Area =	2.25	acres
Watershed Length =	430	ft
Watershed Slope =	0.036	ft/ft
Watershed Imperviousness =	61.80%	percent
Percentage Hydrologic Soil Group A =	100.0%	percent
Percentage Hydrologic Soil Group B =	0.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Desired WQCV Drain Time =	12.0	hours
	S- 12	

Location for 1-hr Rainfall Depths = U	ser Input	7
Water Quality Capture Volume (WQCV) =	0.036	acre-feet
Excess Urban Runoff Volume (EURV) =	0.170	acre-feet
2-yr Runoff Volume (P1 = 1.19 in.) =	0.117	acre-feet
5-yr Runoff Volume (P1 = 1.5 in.) =	0.152	acre-feet
10-yr Runoff Volume (P1 = 1.75 in.) =	0.186	acre-feet
25-yr Runoff Volume (P1 = 2 in.) =	0.226	acre-feet
50-yr Runoff Volume (P1 = 2.25 in.) =	0.272	acre-feet
100-yr Runoff Volume (P1 = 2.52 in.) =	0.326	acre-feet
500-yr Runoff Volume (P1 = 3.25 in.) =	0.464	acre-feet
Approximate 2-yr Detention Volume =	0.110	acre-feet
Approximate 5-yr Detention Volume =	0.144	acre-feet
Approximate 10-yr Detention Volume =	0.174	acre-feet
Approximate 25-yr Detention Volume =	0.210	acre-feet
Approximate 50-yr Detention Volume =	0.232	acre-feet
Approximate 100-yr Detention Volume =	0.256	acre-feet

## Optional User Override

1-hr Precipi	tation
1.19	inches
1.50	inches
1.75	inches
2.00	inches
2.25	inches
2.52	Inches
3.25	inches

### Stage-Storage Calculation

Zone 1 Volume (WQCV) =	0.036	acre-feet
Zone 2 Volume (EURV - Zone 1) =	0.133	acre-feet
Zone 3 Volume (100-year - Zones 1 & 2) =	0.086	acre-feet
Total Detention Basin Volume =	0.256	acre-feet
Initial Surcharge Volume (ISV) =	N/A	ft^3
Initial Surcharge Depth (ISD) =	N/A	ft.
Total Available Detention Depth (Htotal) =	user	ft
Depth of Trickle Channel (H <sub>TC</sub> ) =	N/A	ft
Slope of Trickle Channel (Stc) =	N/A	fvft
Slopes of Main Basin Sides (Smain) =	user	H:V
Basin Length-to-Width Ratio (R <sub>L/W</sub> ) =	user	Till a


Depth Increment = Stage - Storage Description	0.25 Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft^2)	Optional Override Area (ft^2)	Area (acre)	Volume (ft^3)	Volume (ac-ft)
Media Surface	-	0.00		- 4		3,208	0.074		
	-	0.25	-	-	-	3,500	0.080	804	0.018
WQCV=6301.46	-	0.50	102.11	- a	-	3,818	0.088	1,715	0.039
20,22,33,33,400	-	0.75	-	-		4,148	0.095	2,708	0.062
	-	1.00	-	-	-	4,505	0.103	3,786	0.087
		1.25	-			4,844	0,111	4,951	0.114
	- 12	1.50		-		5,214	0.120	6,204	0.142
EURV=6302.71	-	1.75		-	-	5,596	0.128	7,552	0.173
	94	2.00			-	6,011	0.138	8,999	0.207
	- 14	2.25	- 14	- 2	-	6,396	0.147	10,609	0.244
100 YR=6303.34	-	2.50			- 2	6,817	0.156	12,261	0.281
	-	2.75	-	-		7,250	0.166	14,019	0.322
		3.00	-	-	-	7,715	0.177	15,890	0.365
	- 2	3.25		-		8,151	0.187	17,873	0.410
	+	3.50	4	-	-	8,622	0.198	19,970	0.458
	-	3.75	147	-		9,105	0.209	22,186	0.509
	-0	4.00	+	**	-	9,631	0.221	24,528	0.563
	-		+	-	-				
	_				-				
	4		- 4	+					
			-	· +	-				
-	-		-	-					
				-	-				
	- 60		100		100				
	-		-	-	12				
			-	-	÷				
	-			-	T				
	-		- 4	-					
	-		-		1 4				0
	-			+	-				
	-		H .		-				
			-	12	+				
	-			- · +	-				
	-		-		- +				
	-		-	-4	2				-
	- 44				-				
	-			-					-
				-					
	- 60		- 4	-	- 4				

## **Detention Basin Outlet Structure Design**

UD-Detention, Version 3.07 (February 2017)

## Project: Freedome Springs

Basin ID: Full Spectrum Sand Filter Basin - DP7



	Stage (ft)	Zone Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.46	0.036	Filtration Media
Zone 2 (EURV)	1.72	0.133	Orifice Plate
one 3 (100-year)	2.34	0.086	Weir&Pipe (Restrict)
_		0.256	Total

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface) Underdrain Orifice Diameter = inches 0.97

Calculated F	arameters to	r Underd
Underdrain Orifice Area =	0.0	ft <sup>2</sup>
Underdrain Orifice Centroid =	0.04	feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP) Calculated Parameters for Plate Invert of Lowest Orifice = 0.46 ft (relative to basin bottom at Stage = 0 ft) WQ Orifice Area per Row = Depth at top of Zone using Orifice Plate : 1.75 ft (relative to basin bottom at Stage = 0 ft) Elliptical Half-Width Orifice Plate: Orifice Vertical Spacing 5.00 inches

Orifice Plate: Orifice Area per Row = sq. inches (diameter = 1-15/16 inches) 2.94

2.042E-02 N/A feet Elliptical Slot Centroid feet Elliptical Slot Area

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

CARL CALL	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.46	0.89	1.32					
Orifice Area (sq. inches)	2.94	2.94	2.94					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)					1			
Orifice Area (sq. inches)								1

User Input: Vertical Orifice (Circular or Rectangular)

	Not Selected	Not Selected	
Invert of Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =	N/A	N/A	inches

Calculated P	arameters for Vert	tical Orifice	
	Not Selected	Not Selected	
Vertical Orifice Area =	N/A	N/A	ft2
Vertical Orifice Centroid =	N/A	N/A	feet

User Input: Overflow Weir (Dropbox) and Grate (Flat or Sloped) Zone 3 Weir Not Selected Overflow Weir Front Edge Height, Ho = 1.75 N/A ft (relative to basin bottom at Stage = 0 ft) Overflow Weir Front Edge Length = 2.92 N/A feet Overflow Weir Slope : 0.00 N/A H:V (enter zero for flat grate) Horiz. Length of Weir Sides = 2.92 N/A feet Overflow Grate Open Area % = 81% N/A %, grate open area/total area

arameters for Ove	rtiow Weir	
Zone 3 Welr	Not Selected	
1.75	N/A	feet
2.92	N/A	feet
59.91	N/A	should be ≥ 4
6.91	N/A	ft <sup>2</sup>
3.45	N/A	ft <sup>2</sup>
	Zone 3 Weir 1.75 2.92 59.91 6.91	1.75 N/A 2.92 N/A 59.91 N/A 6.91 N/A

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

Not Selected N/A N/A N/A

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected			Zone 3 Restrictor	Г
	Zone 3 Restrictor	MULSEIECIEU			Lone 3 Restrictor	-
Depth to Invert of Outlet Pipe =	2.00	N/A	ft (distance below basin bottom at Stage = 0 ft)	Outlet Orifice Area =	0.12	
Outlet Pipe Diameter =	18.00	N/A	inches	Outlet Orifice Centrold =	0.10	
Restrictor Plate Height Above Pipe Invert =	2.10		Inches Half-Central	Angle of Restrictor Plate on Pipe =	0.70	Г

Debris Clogging % =

nzet int	out: Emergency Spillway (Rectangular	or trapezon	181)
	Spillway Invert Stage=	2.50	ft (relative to basin bottom at Stage = 0 ft)
	Spillway Crest Length =	6.00	feet
	Spillway End Slopes =	4.00	H:V
Freeb	oard above Max Water Surface =	1.00	feet


50%

	culculated i alameters for spinitro					
0.42	feet					
3.92	feet					

Basin Area at Top of Freeboard =


Routed Hydrograph Results									
Design Storm Return Period =	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
One-Hour Rainfall Depth (in) =	0.53	1.07	1.19	1.50	1.75	2.00	2.25	2.52	3.25
Calculated Runoff Volume (acre-ft) =	0.036	0.170	0.117	0.152	0.186	0.226	0.272	0.326	0.464
OPTIONAL Override Runoff Volume (acre-ft) =									
Inflow Hydrograph Volume (acre-ft) =	0.035	0.169	0.116	0.152	0.185	0.226	0.272	0.325	0.463
Predevelopment Unit Peak Flow, q (cfs/acre) =	0.00	0.00	0.00	0.01	0.01	0.03	0.23	0.55	1.27
Predevelopment Peak Q (cfs) =	0.0	0.0	0.0	0.0	0.0	0.1	0.5	1.2	2.9
Peak Inflow Q (cfs) =	0.7	3.2	2.2	2.8	3.5	4.2	5.1	6.0	8.6
Peak Outflow Q (cfs) =	0.0	0.3	0.2	0.2	0.3	0.8	1.1	1.1	3.1
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	17.5	9.3	11.8	2.1	0.9	1,1
Structure Controlling Flow =	Filtration Media	Plate	Plate	Plate	Plate	Overflow Grate 1	Outlet Plate 1	Outlet Plate 1	Spillway
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	N/A	N/A	0.1	0.1	0.1	0.1
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	12	23	21	22	23	24	23	23	22
Time to Drain 99% of Inflow Volume (hours) =	12	24	22	23	25	25	25	25	26
Maximum Ponding Depth (ft) =	0.38	1.50	1.11	1.38	1.61	1.82	1.98	2.24	2.71
Area at Maximum Ponding Depth (acres) =	0.08	0.12	0.11	0.12	0.12	0.13	0.14	0.15	0.16
Maximum Volume Stored (acre-ft) =	0.030	0.144	0.098	0.128	0,157	0.182	0,205	0.242	0.314


## **Detention Basin Outlet Structure Design**



# 11 Report Maps

Existing Condition Hydraulic Analysis Map (Map Pocket) Proposed Condition Hydraulic Analysis Map (Map Pocket)





VICINITY MAP

NO SCALE

<u>LEGEND</u>


- - - BUILDING SETBACK LINE

EXISTING -----84----- INTERMEDIATE CONTOUR

-----×------- BARBED WIRE FENCE TREE (EVERGREEN/DECID.)

GENERAL FLOW/DIRECTION SLOPE DIRECTION AND GRADE

BASIN LABEL AREA IN ACRES PERCENT IMPERVIOUS POINT OF INTEREST



BENCHMARK

1" = 50' 1:600



REVISIONS

RUNOFF Q100 (CFS)

Q5 (CFS)

DESIGNED BY DRAWN BY CHECKED BY AS-BUILTS BY CHECKED BY


FREEDOM SPRINGS 734 WESTERN DRIVE

Existing Drainage Map

MVE PROJECT 61090 <sub>MVE DRAWING</sub> Ex-Drain-Map

November 8, 2018 SHEET 1 OF 1





VICINITY MAP

NO SCALE

LEGEND

- — — — — — BUILDING SETBACK LINE


EXISTING

हिंदि TREE (EVERGREEN/DECID.)

BASIN BOUNDARY

Q = 2 cfs
Q = 7 cfs

GENERAL FLOW/DIRECTION



POINT OF INTEREST

PROPOSED DRAINAGE SUMMARY TABLE

POINT OF		AREA	RUNOFF		
	terest/basin(s) Asin(s)	(AC)	Q5 (CFS)	Q100 (CFS)	
	OS1	2.84	4.7	10.4	
	Н1	0.45	1.6	3.1	
DP1	A1	0.63	2.7	4.9	
DP2	B1	0.17	0.7	1.3	
DP3	C1	0.11	0.4	0.8	
DP4	O\$1,H1	3.29	5.7	12.3	
	D1	0.36	1.4	2.6	
DP5	E1	0.17	0.1	0.5	
DP6	F1	0.17	0.3	0.8	
	Gl	0.58	0.2	1.3	
DP7	A1,B1,C1,D1,E1,F1,G1,H1	2.65	7.2	15.2	
DP7	POND OUTFLOW	2.65	0.2	1.1	
	J1	0.46	0.1	1.1	
	K1	0.15	0.1	0.4	
	M1	0.13	0.1	0.4	
	O\$2	0.57	1.1	2.5	
	L1	0.45	0.1	1.1	
	OS2,L1	1.02	1.1	3.3	
	O\$1,H1,A1,B1,C1,D1, E1, F1,G1,H1,J1, K1, O\$2,L1	7.11	4.7	14.4	
		I			

BENCHMARK



10 0 20 50 100 1" = 50' 1:600



revisions

DESIGNED BY
DRAWN BY
CHECKED BY \_\_\_\_\_
AS-BUILTS BY
CHECKED BY \_\_\_\_\_

FREEDOM SPRINGS 734 WESTERN DRIVE

Proposed Drainage Map

> MVE PROJECT 61090 MVE DRAWING Ex-Drain-Map

November 8, 2018 SHEET <sup>1</sup> OF <sup>1</sup>