Architecture Structural Geotechnical



ROCKY MOUNTAIN GROUP EMPLOYEE OWNED Materials Testing Forensic Civil/Planning

> APPROVED Engineering Department

03/18/2019 5:18:48 PM dsdnijkamp EPC Planning & Community Development Department

### **PAVEMENT DESIGN REPORT**

Lorson Boulevard Crossing East Tributary Jimmy Camp Creek Lorson Ranch East, Filing No. 1 El Paso County, Colorado

### **PREPARED FOR:**

Lorson Ranch Metropolitan District 212 N. Wahsatch Ave. Ste 301 Colorado Springs, CO

### **JOB NO. 162626**

### November 30, 2018

**RMG – Rocky Mountain Group** 

**Respectfully Submitted,** 


Reviewed by,

RMG – Rocky Mountain Group

Kelli Zigler

Kelli Zigler Project Geologist

Geoff Webster, P.E. Sr. Geotechnical Project Manager



SF Number – 18-008

### TABLE OF CONTENTS

GENERAL SITE AND PROJECT DESCTIPTION	.3
Location	.3
Existing Conditions	.3
Project Description	.3
SUBSURFACE CONDITIONS	.3
Introduction	.3
Subsurface Materials	.3
LABORATORY DOCUMENTATION	
Laboratory Testing	4
PAVEMENT DESIGN	4
Pavement Thickness	.5
Pavement Materials	.5
Soil Mitigation	.5
Subgrade Preparation	.5
Surface Drainage	.6
Subgrade Observations and Testing	.6
CLOSING	.6
FIGURES	

#### Site Vicinity Map ......1

#### APPENDIX A

Laboratory Test Results for Subgrade Structural Fill

#### AAPENDIX B

AASHTO Structural Number Calculation for Flexible Pavements – Urban Principal Arterial, 4-lane

# GENERAL SITE AND PROJECT DESCTIPTION

#### Location

Lorson Ranch East Filing No. 1 is located east of Marksheffel Road and between Fontaine Boulevard to the north and Lorson Boulevard to the south in El Paso County, Colorado. The East Tributary of Jimmy Camp Creek forms the western boundary of the development. The location of the site is shown on the Site Vicinity Map, Figure 1.

#### **Existing Conditions**

At the time of this report Lorson Boulevard is close to grade and utility mains and services had been installed. Curb and gutter is being installed.

#### **Project Description**

This Pavement Design Report provides recommendations specific to the design and construction of Lorson Boulevard where it crosses the ConSpan Arch Bridge spanning the East Tributary of Jimmy Camp Creek. The approximate roadway stationing along Lorson Boulevard to which this pavement design report is applicable is Station 82+25 to Station 82+75. Lorson Boulevard is classified a Residential Urban Collector, with an 80-foot ROW and two 20-foot wide travel lanes.

## SUBSURFACE CONDITIONS

#### Introduction

RMG previously prepared a Pavement Design Report for Lorson Ranch East, Filing No. 1 (SF Number 18-008) that included a pavement section for Lorson Boulevard consisting of 4.5-inches of Hot Mix Asphalt (HMA) over 11-inches of Cement Treated Subgrade (CTS). Where Lorson Boulevard crosses the East Tributary of Jimmy Camp Creek, however, a ConSpan Arch Bridge has been constructed to carry the roadway. It has proven impractical to construct the prescribed pavement section across the span due to space limitations and construction considerations, and therefore a different pavement section is necessary. This report provides documentation and design of a pavement section that can be constructed in the available space and meets El Paso County development requirements.

#### Subsurface Materials

The approved bridge plans indicate the steel ConSpan arch receives a cover of select structural backfill upon which the pavement may be constructed. The structural backfill serves in essence the role of a prepared subgrade beneath a composite section of Hot Mix Asphalt over Aggregate Base Course. CDOT Class I material has been installed as the select structural fill over the arch.

# LABORATORY DOCUMENTATION

#### Laboratory Testing

The annual laboratory testing report for the soil being utilized as structural backfill over the ConSpan arch is presented in Appendix A. The results indicate this soil classifies as SW-SM, well-graded silty sand in accordance with the Unified Soils Classification System (USCS), which correlates to A-1 soil in the AASHTO classification system. In accordance with AASHTO this soil is rated "excellent" for use as subgrade material.

The laboratory report further indicates the soil meets the gradation and physical properties of CDOT Class I Structural Fill, and has an R-value of 75.

### PAVEMENT DESIGN

This pavement design was performed in accordance with the El Paso County Engineering Criteria Manual, Appendix D. Pavement design parameters and design calculations are presented below utilizing an R-value of 75 for the subgrade soil. The recommended pavement section is supported by the calculations below.

#### Street Classification – Residential Urban Collector

- 1) Lorson Boulevard ESAL = 821,000 (Table D-2) Serviceability Index = 2.5 (Table D-1)
- 2) Strength coefficients (Table D-3) Asphalt (HMA): a<sub>1</sub> = 0.44 Aggregate Base Course (ABC): a<sub>2</sub> = 0.11
- 3) Subgrade (Section D.4.1.C)  $S_1 = [(R-5) / 11.29] + 3 = [(75-5) / 11.29] + 3 = 9.2$  $M_r = 10$  exponent  $[(S_1 + 18.72) / 6.24] = 10$  exp [(9.2 + 18.72) / 6.24] = 29,812
- 4) Structural number (SN) = 1.95 (1993 AASHTO Empirical Equation, Appendix B)
- 5) Composite asphalt/base course section Minimum HMA thickness =  $D_1 = 4$  inches (Table D-2) ABC thickness =  $D_2 = \{SN - (D_1 x a_1)\} / a_2 = \{1.95 - (4 x 0.44)\} / 0.11 = 1.7$  inches Use Minimum ABC thickness,  $D_2 = 8.0$ -inches Check SN = (4.0x 0.44) + (8.0 x 0.11) = 2.64 > 1.95 (Min. SN required) => OK

6) Developer desires to use 4.5-inches of HMA over 8-inches ABC Check SN = (4.5 x 0.44) + (8.0 x 0.11) = 2.86 > 1.95 (Min. SN required) => OK

#### **Pavement Thickness**

Based on the soil types and the design calculations, the recommended pavement section is presented below.

#### **Recommended Pavement Section**

Street	HMA (in)	ABC (in)	Subgrade Class I Structural Fill (in)
Lorson Boulevard over ConSpan Bridge Approx. Sta. 82+25 to Sta. 82+75	4.5	8.0	7.5

#### **Pavement Materials**

Pavement materials should be selected, prepared, and placed in accordance with El Paso County specifications and the *Pikes Peak Region Asphalt Paving Specifications*. Tests should be performed in accordance with the applicable procedures presented in the specifications.

#### Soil Mitigation

The PDCM notes that mitigation measures may be required for expansive soils, shallow ground water, subgrade instability, etc. Based on the laboratory test results, the subgrade soils evaluated for this pavement design are expected to have no expansive potential. Groundwater or wet and unstable soil will not be present. Therefore, special mitigation measures do not appear to be necessary for subgrade preparation.

#### **Subgrade Preparation**

Subgrade for Lorson Boulevard over the ConSpan Arch Bridge shall be CDOT Class I Structural Backfill. RMG understands the structural fill has been placed and compacted to 95 percent of the maximum dry density as determined by the Modified Proctor test (ASTM D-1557). Prior to installation of the composite pavement section, the subgrade should be proof-rolled to a firm and unyielding condition. Areas which deform under wheel loads should be removed and replaced.

#### **Surface Drainage**

Surface drainage is important for the satisfactory performance of pavement. Wetting of the subgrade soils or base course will cause a loss of strength which can result in pavement distress. Surface drainage should provide for efficient removal of storm-water runoff. Water should not pond on the pavement or at the edges of the pavement.

#### **Subgrade Observations and Testing**

The pavement thicknesses presented above assume pavement construction is completed in accordance with El Paso County specifications and the *Pikes Peak Region Asphalt Paving Specifications*. RMG should be present at the site during subgrade preparation, placement of fill, and construction of pavements to perform site observations and testing.

### CLOSING

This report has been prepared for the exclusive purpose of providing geotechnical engineering information and recommendations for development described in this report. RMG should be retained to review the final construction documents prior to construction to verify our findings, conclusions and recommendations have been appropriately implemented.


This report has been prepared for the exclusive use by the Landhuis Company for application as an aid in the design and construction of the proposed development in accordance with generally accepted geotechnical engineering practices. The analyses and recommendations in this report are based in part upon data obtained from test borings, site observations and the information presented in referenced reports. The nature and extent of variations may not become evident until construction. If variations then become evident, RMG should be retained to review the recommendations presented in this report considering the varied condition, and either verify or modify them in writing.

Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by geotechnical engineers practicing in this or similar localities. RMG does not warrant the work of regulatory agencies or other third parties supplying information which may have been used during the preparation of this report. No warranty, express or implied is made by the preparation of this report. Third parties reviewing this report should draw their own conclusions regarding site conditions and specific construction techniques to be used on this project.

The scope of services for this project does not include, either specifically or by implication, environmental assessment of the site or identification of contaminated or hazardous materials or conditions. Development of recommendations for the mitigation of environmentally related conditions, including but not limited to biological or toxicological issues, are beyond the scope of this report. If the Client desires investigation into the potential for such contamination or conditions, other studies should be undertaken.

If we can be of further assistance in discussing the contents of this report or analysis of the proposed development, from a geotechnical engineering point-of-view, please feel free to contact us.

FIGURES



# APPENDIX A

# Transit Mix Concrete Co. Materials Laboratory

444 East Costilla Avenue Colorado Springs, Colorado 80903 Ph. (719) 475-0700 Fax (719) 475-0226

2596 Hwy 96 East Pueblo, Colorado 81002 Ph. (719) 543-7898 Fax (719) 583-0345

February 12, 2018

RE: Class 1 Structure Backfill/Fine Fill Daniels Sand Company 3710 Bradley Road Colorado Springs, CO 80916

#### Gentlemen:

This letter presents the results of physical properties and deleterious substances tests performed on a Class 1 Structural Backfill that was sampled on January 17, 2018. Please be advised this is a raw bank product and variations may occur in test results. Testing was conducted to evaluate the suitability of the material for use as "Select Fill" for the City of Colorado Springs,CO. The results are as follows:

Test Procedure	Test Description	Test Results	Specifications
ASTM C 117	-200 Wash	8.4%	N/A
ASTM C 136	Gradation	Satisfactory	N/A
ASTM D 4318	Liquid Limit	No Value	N/A
ASTM D 4318	Plastic Index	Non-Plastic	N/A
ASTM D 1557	Moisture-Density Relationship (Modified)	131.8 pcf @ 8.0%	N/A
ASTM D 698	Moisture-Density Relationship (Standard)	124.0 pcf @ 9.2%	N/A
ASTM D 2844	Resistance R-Value/Expansion Pressure	75	Please see Table
CP-L 2103	Water Soluble Sulfate	0	Please see Table

More detailed test results are indicated on the attached tables. ACI Certified technicians performed all tests in accordance to procedures prescribed by the American Society for Testing and Materials (ASTM) and Colorado Procedures.


If you have any questions feel free to contact me at your convenience.

Respectfully Submitted,

Robert L. Montoya, BSCET NICET Technologist #1001



Т	444 I	East Co Springs	stilla Avenue , Colorado 80	903	Co. 1	Co. Materials Laboratory 2596 Hwy 96 East Pueblo, Colorado Ph. (719) 543-7898 Fax (719) 583-0345								
	FIN	EA	GGREC	GATE R	EPC	DRT	T No.					9D-1-18		
JOB NAME/SO	URCE:	D	aniels Sai	nd Pit		SAMPL	E DESCR	IPTION:		Fin	ıe Fill			
										Tube	Samp	ole		
DATE S	SAMPLED:	Ianua	гу 17, 2018		Т	IME SAMPLED:	10:0	D AM		SAMPLED	BY:	MG		
DATE		-	ry 18, 2018			TIME TESTED:		PM	-	TESTED	-	MG		
ASTMO	: 136	AA	SHTO T 27 & M	192					-					
SIEVE S											_			
50.0 mm		NDIVIDI	UAL WEIGHT	CUMULATIVE	WEIGHT	% RE	TAINED	%	PASSING					
37.5 mm			0.0	0.0		0.0%		-	00.0%					
25.0 mm			0.0	0.0		0.0%		L	00.0%					
19.0 mm (			0.0	0.0		0.0%			00.0%					
12.5 mm (	or 1/2"		0.0	0.0		0.0%		1	00.0%		d	and the second second		
9.5 mm o	r 3/8*		0.0	0.0		0.0%		1	00.0%	-	200	AL 00 110 830		
4.75 mm	or 4		13.5	13.5		1.3%			98.7%	6	80.	P MO		
2.36 mm	or 8		72.7	86.2		8.6%			91.4%	Ĩ	10.22	XI-ANE D		
1.18 mm	or 16	1	161.5	247.7	,	24.7%	)		75.3%		- 64	15806 F. J		
600 um (	or 30	1	180.8	428.5	428.5		)		57.3%	<b>B</b>	2.	1016 195		
300 um (	or 50		208.9	637.4		63.5%	)		<b>36.5</b> %	2	3%	1 . K. &		
150 um o	ir 100	1	157.6	795.0		79.2%	,		20.8%		an	SONAL EN CON		
75 um oi	· · · · · · · · · · · · · · · · · · ·	1	125.0	920.0		91.6%	3		8.4%		- 99	Contraction of the second seco		
Pan/Oven	Dry Wt.	9	920.0	1004.	)									
ASTM C 56		SHTO 1		]						TM D 422 (0. mm)				
	nal Size (in)	4.	75 mm (#4)	9.5 mm (3/8	in)	12.5 mm (1/2 in	) 1			5.0 mm 4000	(1 in)	37.5 mm (1 <sup>1</sup> / <sub>2</sub> in)		
	ple Size (g)	<u> </u>	500	1500		2000	2000		3000			6000		
	iginal Sample (W)		1056.7								Moisture Content			
Mass of Dr	ied Sample (D,B)	1	1004.0		p = 100 (W - D)/D							5.2%		
ASTM C 11	17 A/	ASHTO	T 11											
Max. Nomi	nal Size (in)		≤ 4.75 mm	(#4)	> 4.75	5 mm (#4) to 9.5 mm (1	(ni 6V	>9.5 m	m (3/8 in) to 19.0 mr	n (3/4 in)		> 19.0 mm (3/4 in)		
	ple Size (g)		300			1000			2500			5000		
	ied Sample (D,B)		1004.0								% Mat	Finer than #200 Sieve		
Dry Mass of S	ample-Washed ( C	)	920.0			A = [(	8 - C)/8] X	K 100				8.4%		
ASTM D 24 Solution Temperatu		SHTO T	176											
Sample Identification	Sample Weigh	ıt	Clay Reading	Sand Reading		Actual SE	Adju S	sted E	Average SE			oorted Sand ivalent Value		
A	109.5		3,3	2.2		66.7	6	7						
В	109,1		2.9	1.8		62.1	6	3	65.3			66		
С	110,4		3.2	2.1		65.6	6	6			00			



\_

MOISTURE DENSITY TEST DATA


Client: VARIOUS Project: VARIOUS Project Number: 2017

```
Specimen Data
```

Source: Dan's Fine Fill 2018 Sample No.: D-FF-Std. Elev. or Depth: Stockpile Sample Length (in./cm.): Stockpile Location: Daniels Sand Pit Description: Daniels Fine Fill/ Structural Fill Plasticity Index: NP Natural Moisture: 5.2 Liquid Limit: NV Date: 2-11-2018 USCS Classification: AASHTO Classification: Testing Remarks: Daniels Fine Fill/ Structural Fill 9D-698) Percent retained on No.4 sieve: 1.3 Percent passing No. 200 sieve: 8.4 Specific gravity:

#### Test Data And Results For Curve DFF-S

Type of test: ASTM D 698-91 Procedure A Standard Mold Dia.: 4.00 in. Hammer Wt.: 5.5 lb. Drop: 12 in. Layers: three Blows per Layer: 25




+ WS +T +T RE IST	6152.5 4253.0 610.20 576.10 0.00 5.9	6221.6 4253.0 684.20 638.20 0.00 7.2	6287.9 4253.0 537.40 494.40 0.00 8.7	6281.1 4253.0 649.80 582.30 0.00 11.6	6213.5 4253.0 675.40 595.80 0.00 13.4
ISTURE	5.9	7.2	8.7	11.6	13.4
Y DEN	118.6	121.5	123.8	120.2	114.4

Max dry den= 124.0 pcf Opt moisture= 9.2 % Oversize Correction Not Applied



5



MOISTURE DENSITY TEST DATA


Client: VARIOUS Project: VARIOUS Project Number: 2017

Specimen Data

Source: Dan's Fine Fill 2018Sample No.: D-FF-Mod.Elev. or Depth: StockpileLocation: Daniels Sand PitDescription: Daniels Fine Fill (Structural Fill)Liquid Limit: NVPlasticity Index: NPNatural Moisture: 5.2Date: 2-11-2018USCS Classification:AASHTO Classification:Testing Remarks: Daniels Fine Fill/Structural Fill (D-1557-A)Percent retained on No.4 sieve: 1.3Percent passing No. 200 sieve: 8.4Specific gravity:

Test Data And Results For Curve DFF-M

Type of test: ASTM D 1557-91 Procedure A Modified Mold Dia.: 4.00 in. Hammer Wt.: 10 lb. Drop: 18 in. Layers: five Blows per Layer: 25



Oversize Correction Not Applied





February 8, 2018

Transit Mix Concrete Company 2596 Highway 96 East Pueblo, Colorado 81006

Attention: Mr. Robert Montoya

Subject: Laboratory Test Results Hveem Stabilometer and Sulfate Testing Project No. DN48,806.001-300

This letter transmits the results of laboratory tests performed on samples delivered to our office on January 23, 2018. The test results transmitted at this time are those requested by Mr. Robert Montoya when the samples were submitted.

The samples were tested in accordance with American Association of State Highway and Transportation Offices (AASHTO). Test results are presented in Table 1 and 1A and in Figs. 1 through 6. Gradation analysis, used in Hveem stabilometer tests were performed by Transit Mix Concrete Company's material laboratory.

Sample ID	R-Value	Sulfate (%) CDOT Method
Fine Fill, Daniels Sand Pit	75	0.00
Class 1, Pikeview Quarry	83	0.00
Colorado White Fines, Pikeview Quarry	61	0.00
Class 6, Rec. Concrete, Daniels Sand	82	0.02
Class 6 Roadbase, Pikeview Quarry	80	0.01
Class 5 Roadbase, Pikeview Quarry	87	0.02

TABLE 1

Should you have any questions regarding these test results, please call.

Very truly yours,

FROMPSON Frank Schenck Asphalt Laboratory Supervisor

FS/bg

Via email: robert montoya@transitmix.com

1971 West 12th Avenue | Denver, Colorado 80204 | Phone: 303-825-0777 | Fax: 303-825-4252 | www.ctit.com


Project No. DN48806.001-300

CLIENT NAME Transit Mix Concrete Company Date Submitted: January 23, 2018 TABLE 1A HVEEMSTABILOMETER DATA

N	COMPACTION	FI APSED TIME	SAMPLE DATA	DATA	EXIDATION	EXILIDATION EXPANSION		AN MADED	E ANDI F		
i	PRESSURE (PSI)	TO REACH EXUDATION	DENSITY (PCF)	WATER (%)	PRESSURE (LBS)	PRESSURE (PSI)		OF TURNS (D)	HEIGHT (INCHES)	UNCORRECTED R-VALUE *	CORRECTED R- VALUE
FINE FII	105	0.97	113.2	12.7	1940	154	26	5.04	2.63	72	74
Daniels	105	2.02	114.1	12.0	4040	322	24	5.19	2.63	73	75
Sand Pit	105	4.74	113,9	11.4	9480	755	24	4.75	2.73	75	78
Class I	200	0.99	131.8	9.9	1980	158	22	4.30	2.54	78	78
Pikeview	200	1.60	131.7	9.6	3200	255	17	4.51	2.55	82	82
Quarry	200	2.35	131.8	8.9	4700	374	15	4.36	2.56	85	85
Colorado White Fines	50	0.89	130.9	10.4	1780	142	121	3.62	2.62	18	19
Pikeview	125	1.90	134.6	8.3	3800	302	47	3.86	2.49	61	6
Quarry	200	2.69	135 - 0	8.1	5380	428	34	3.84	2.49	71	71
Class 6 Rec. Concrete	200	1.07	103.3	17.1	2140	170	21	7.52	2.56	69	71
Daniels	200	1.82	104.8	16.3	3640	290	14	5.63	2.54	82	82
Sand	200	2.51	105.2	15.2	5020	400	13	6.12	2.56	82	83
Class 6 Roadbase	200	1.74	130.3	9.1	3480	277	14	6.53	2.56	62	80
Pikeview	200	2.90	132.0	8.9	5800	462	13	6.14	2.54	82	82
Quarry	200	3.75	132.3	8.3	7500	597	11	6.62	2.55	84	84
Class 5 Roadbase	200	1.70	137.9	8.0	3400	270	6	5.98	2.45	87	87
Pikeview	200	2.49	137.2	7.5	4980	396	6	5.49	2.49	88	88
Оиапту	200	3.50	138.8	6.9	7000	557	10	5.21	2.48	88	88


100 2.5 160-1 +1 D Ph

\*\* AT 2,000 Lb. VERTICAL LOAD



Transit Mix Concrete Co. Fine Fill, Daniels Sand Pit Submitted: January 23rd,2018


### **Hveem Stabilometer**



Transit Mix Concrete Co. Class 1, Pikeview Quarry Submitted: January 23rd,2018

### **Hveem Stabilometer**


Project No. DN48,806.001-300



Transit Mix Concrete Co. Colorado White Fines, Pikeview Quarry Submitted: January 23rd, 2018


### **Hveem Stabilometer**

Project No. DN48,806.001-300



Transit Mix Concrete Co. Class 6 Recycled Concrete, Daniels Sand Submitted: January 23rd,2018


### **Hveem Stabilometer**



Transit Mix Concrete Co. Class 6 Roadbase, Pikeview Quarry Submitted: January 23rd, 2018

### **Hveem Stabilometer**

Project No. DN48,806.001-300



Transit Mix Concrete Co. Class 5 Roadbase,Pikeview Quarry Submitted: January 23rd,2018

## **Hveem Stabilometer**

Project No. DN48,806.001-300

Fig.6

Westest

CONCRETE PHYSICAL PROPERTY TEST REPORT PROJECT: Barrington Heights, Colorado Springs, CO WesTest PROJECT NO.: 568917 REPOR

VVB: 627 Sheridan Boulevard - Latewood, CO 80214 303.875.9559 - office@westest.net

CLIENT. Reconstruction Experts, Inc. Mr. Aaron Acker 5310 Vivian Street Arvada, CO 80002

REPORT DATE: February 8, 2018 DATE TESTED: February 7, 2018 TECHNICIAN: ATS SUPPLIER: Transit Mix Concrete SAMPLE LOCATION: Chute

SLUMP (IN.) UNIT WEIGHT WATER VIELD CYLINDER (PCF) RATIO 3-5 0.45 Max.	5 - 1/2* 141.8 0.31 56899	4 - 1/4 142.6	6 - 1/2° 141.6 0.32 568910								
	5.5	5.2	5.4								-
TEMP. ("F) AIR CONTENT (%) 5.0 - 8.0	69	71	74						1		
PLACEMENT LOCATION	Curb and gutter, 15' South and 250' East of SE corner of High Knolls Grove and Baytree Grove	V-Pan, 30' South and 185' East of SE comer of High Knolls Grove and Baytree Grove	V-Pan, Hogback Pt. 80' South and 80' East of SE corner of High Knoils Grove and Baytree Grove								
CUBIC YARDS	8	7	G								
GALS. WATER ADDED	Û	0	10								
TICKET NO.	289913	289923	289930					11			
AMBIENT TEMP. (°F)	27	29	32								
TâME	10:08 AM	11:05 AM	11:58 AM								

commenta. Jury with Reconstruction Experts approved the placement of this concrete. CC: Jerry Harper with Reconstruction Experts, Robert Montoya with Transit Mix.

# APPENDIX B

# 1993 AASHTO Empirical Equation for Flexible Pavements

<b>Equation Solver</b> Variable Descriptions	and Typical Values Precautions
Type in data in the grey boxes and click the c additional calculations, change the desired inp Click on the text descriptions of the input or c	out data and click the calculate button again.
INPUT	OUTPUT
1. Loading	1. Calculation Parameters
Total Design ESALs (W <sub>18</sub> ): 821000	Standard Normal Deviate (z <sub>R</sub> ): -1.037
2. Reliability	∆ <b>PSI: 2.5</b>
Reliability Level in percent (R): 85	Design Structural Number (SN): 1.945
Combined Standard Error (S <sub>0</sub> ): 0.5	2. Layer Depths (to the nearest 1/2 inch)
3. Serviceability	Surface: 4.5
Initial Serviceability Index (p <sub>i</sub> ): 4.5	Total SN based on layer depths: 1.98
Terminal Serviceability Index (pt): 2	
4. Layer Parameters Number of Base Layers: 0 ▼ a m M <sub>R</sub> Min. Depth Surface 0.44 1.0 N/A 0 Subgrade N/A N/A 29812 N/A	See Solution Details Comments
Calcu	llate