



November 22, 2021

Lupe Packman  
El Paso County  
Planning and Community Development  
2880 International Circle, Suite 110  
Colorado Springs, CO 80910

Re: ***Final Drainage Report, Colorado Springs Utilities Northeast Gravel Staging Area***

Dear Ms. Packman:

On behalf of Colorado Springs Utilities, Burns & McDonnell Engineering Company Inc. (Burns & McDonnell) is submitting this Final Drainage Report for the Colorado Springs Utilities (Utilities) Northeast Gravel Staging Area. It has been prepared as a submittal in accordance with the list of required documents provided by the El Paso County Planning and Community Development Department during the Pre-Application meeting for this project.

This Final Drainage Report has been prepared to present proposed stormwater management improvements associated with the development of the Northeast Gravel Staging Area, as it alters the grading and imperviousness of the site. Standards presented in the El Paso County Drainage Criteria Manual, Volumes 1 and 2 were adhered to in this Report and its analysis.

***Closing***

Please feel free to contact the undersigned at [jilee@burnsmcd.com](mailto:jilee@burnsmcd.com) or 720-826-9882 should you have any questions.

Sincerely,

A handwritten signature in blue ink that reads "Joshua Lee".

Joshua Lee, PE  
Senior Civil Engineer

Attachments:

- Attachment 1 – Colorado Springs Utilities Northeast Gravel Staging Area Final Drainage Report, Revision 0
- Attachment 2 – El Paso County PCD Final Drainage Report (FDR) Checklist

# Final Drainage Report



## Colorado Springs Utilities

Northeast Gravel Staging Area  
Project No. 128056  
Document No. LP-PLAT-RT-0002

Revision 0  
11/22/2021

PCD Filing No.: PPR-21-050

# **Final Drainage Report**

prepared for

**Colorado Springs Utilities  
Northeast Gravel Staging Area  
El Paso, Colorado**

**Project No. 128056**

**Revision 0  
11/22/2021**

prepared by

**Burns & McDonnell Engineering Company, Inc.  
Denver, CO**

# INDEX AND CERTIFICATION

## Final Drainage Report

Project No. 128056

### Report Index

<u>Chapter Number</u>	<u>Chapter Title</u>
1.0	GENERAL LOCATION AND DESCRIPTION
2.0	DRAINAGE BASINS AND SUB-BASINS
3.0	DRAINAGE DESIGN CRITERIA
4.0	DRAINAGE FACILITY DESIGN
5.0	CONCLUSIONS
6.0	REFERENCES
APPENDIX A	NRCS SOILS REPORT
APPENDIX B	FEMA FLOODPLAIN MAP
APPENDIX C	HYDROLOGIC CALCULATIONS
APPENDIX D	HYDRAULIC CALCULATIONS
APPENDIX E	FINANCIAL ASSURANCE
APPENDIX F	DRAINAGE FIGURES

### Certification

I hereby certify, as a Professional Engineer in the state of Colorado, that the information in this document was assembled under my direct personal charge. This report is not intended or represented to be suitable for reuse by the Colorado Springs Utilities or others without specific verification or adaptation by the Engineer.



---

Joshua Lee, PE  
Senior Civil Engineer

Date: November 24, 2021


# EL PASO COUNTY DRAINAGE STATEMENTS

## Engineer's Statement

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

*Joshua Lee*

\_\_\_\_\_  
Name



← Please add PE #.

## Developer's Statement

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

\_\_\_\_\_  
Business Name

By: \_\_\_\_\_

Title: \_\_\_\_\_

Address: \_\_\_\_\_  
\_\_\_\_\_

Please replace with the following:

"El Paso County:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

\_\_\_\_\_  
Jennifer Irvine, P.E.  
County Engineer / ECM Administrator

\_\_\_\_\_  
Date

Conditions: "

## TABLE OF CONTENTS

		<u>Page No.</u>
<b>1.0</b>	<b>GENERAL LOCATION AND DESCRIPTION .....</b>	<b>1-1</b>
1.1	Site Location .....	1-1
1.2	Description of Property .....	1-1
1.2.1	Existing Site .....	1-1
1.2.2	Existing Site Drainage .....	1-2
1.2.3	Natural Resources Conservations Service (NRCS) Soil Survey .....	1-2
1.2.4	Project Description.....	1-2
<b>2.0</b>	<b>DRAINAGE BASINS AND SUB-BASINS .....</b>	<b>2-1</b>
2.1	Major Basin Descriptions .....	2-1
2.2	Sub-Basin Descriptions.....	2-1
<b>3.0</b>	<b>DRAINAGE DESIGN CRITERIA.....</b>	<b>3-1</b>
3.1	Development Criteria Reference.....	3-1
3.2	Hydrologic Criteria .....	3-1
3.3	Hydraulic Criteria .....	3-1
3.4	Water Quality Management.....	3-2
3.4.1	Water Quality Control BMP Selection .....	3-2
<b>4.0</b>	<b>DRAINAGE FACILITY DESIGN.....</b>	<b>4-1</b>
4.1	General Concept.....	4-1
4.2	Existing Drainage Patterns.....	4-1
4.3	Improvements Analysis .....	4-1
4.4	Hydraulic Structures .....	4-2
4.4.1	Detention Pond.....	4-2
4.4.2	Cost Estimate of Proposed Facilities .....	4-3
4.4.3	Cost of Drainage and Bridge Fees .....	4-3
4.5	Other Government Agency Requirements.....	4-3
<b>5.0</b>	<b>CONCLUSIONS .....</b>	<b>5-1</b>
5.1	Compliance with Standards .....	5-1
<b>6.0</b>	<b>REFERENCES .....</b>	<b>6-1</b>
<b>APPENDIX A – NRCS SOILS REPORT</b>		
<b>APPENDIX B – FEMA FLOODPLAIN MAP</b>		
<b>APPENDIX C – HYDROLOGIC CALCULATIONS</b>		
<b>APPENDIX D – HYDRAULIC CALCULATIONS</b>		
<b>APPENDIX E – FINANCIAL ASSURANCE</b>		
<b>APPENDIX F – DRAINAGE FIGURES</b>		

**LIST OF TABLES**

	<b><u>Page No.</u></b>
Table 1-1: NRCS Soil Report Summary.....	1-2
Table 3-1: Rainfall Depths for Colorado Springs.....	3-1
Table 4-1: Pre-Development Hydrologic Conditions.....	4-1
Table 4-2: Post-Development Hydrologic Conditions .....	4-2

**LIST OF ABBREVIATIONS**

<b><u>Abbreviation</u></b>	<b><u>Term/Phrase/Name</u></b>
BMcD	Burns & McDonnell
CDPHE	Colorado Department of Public Health and Environment
CMP	Corrugated Metal Pipe
cfs	Cubic feet per second
EURV	Excess Urban Runoff Volume
FDR	Final Drainage Report
FEMA	Federal Emergency Management Agency
FHWA	Federal Highway Association
fps	feet per second
ft	feet
GPAP	Gas Propane Air Plant
HEC	Hydraulic Engineering Circular
MHFD	Mile High Flood District
NOAA	National Oceanic and Atmospheric Administration
NRCS	Natural Resources Conservation Service
SCS	Soil Conservation Service
Utilities	Colorado Springs Utilities
WQCD	Water Quality Control Division
WQCV	Water Quality Capture Volume

## **1.0 GENERAL LOCATION AND DESCRIPTION**

This Final Drainage Report (FDR) is being prepared as part of the required submittal documents to El Paso County for the Northeast Gravel Staging Area Relocation in conjunction with the Colorado Springs Utilities (Utilities) Site Development Plan.

### **1.1 Site Location**

The Utilities site is bounded by North Carefree Circle to the north, the Gas Propane Air Plant (GPAP) to the east, the El Paso County Department of Public Works facility to the south, and residential development to the west. The Northeast Gravel Staging Area Relocation is planned to be within the NE 1/4 of the SE 1/4 of Section 29, T13S, R65W in El Paso County, Colorado. The site is an undeveloped parcel located at 7723 North Carefree Circle, southwest of the intersection of North Carefree Circle and Akers Drive. The proposed location is just west of the Utilities' existing GPAP. A map showing the Staging Area location is provided as Figure 1 in Appendix F.

The Staging Area is located within a RR-5 (residential rural 5-acres intended to accommodate low-density, rural, single family residential development) CAD-O (commercial airport overlay district) zoned area of the City of Colorado Springs. The surrounding platted developments include The Gardens at North Carefree Circle (Plat No. 14488) to the west and a storage warehouse (Plat No. 2510) to the southeast of the site.

### **1.2 Description of Property**

#### **1.2.1 Existing Site**

The proposed Staging Area is located on a 9.58-acre parcel owned by City of Colorado Springs. The parcel is undeveloped with a ground cover consisting of rangeland grass. No groundwater characterization has been accomplished to date. Stormwater features constructed in 1996 were constructed to capture the flows from the western portion of the GPAP site and the property on which the Staging Area will be built. The features constructed included a detention pond in the northeast part of the GPAP property and berm running north and south along the western boundary of the GPAP property. The work also included the construction of a concrete lined channel to collect and convey flows from the western portion of the GPAP site to the detention pond. Figure 2 in Appendix F show the existing stormwater features.

### 1.2.2 Existing Site Drainage

Topographic data consisting of 2-foot contours was used as a basis of analysis for the project and shows the site sloping west to east ranging from 0-4 percent. Offsite flows are shown on Figure 2 in Appendix F. A portion of flows from the western portion of the site flow west toward Akers Drive. Flows from the majority of the site are captured by the berm along the eastern boundary and are conveyed to an 18-inch corrugated steel culvert that discharges through the berm into the existing detention pond. According to the details on Figure 2, the existing detention pond has a bottom elevation of approximately 6569 and a depth of approximately ten feet. An elliptical 18-inch by 29-inch corrugated steel outlet pipe was installed to discharge flows from the detention pond to the existing GPAP retention pond.

### 1.2.3 Natural Resources Conservations Service (NRCS) Soil Survey

Soil data was obtained from the U.S. Department of Agriculture, Natural Resources Conservation Service (NRCS) website – Web Soil Survey Tool. The site soil is Truckton sandy loam which is classified under Hydrologic Soil Group (HSG) A. This soil exhibits low runoff rates and high infiltration rates. The NRCS soil survey report for the project area is provided in Appendix A.

**Table 1-1: NRCS Soil Report Summary**

Soil Type	Map Unit Symbol	Hydrologic Soil Group
Truckton sandy loam, 3 to 9 percent slopes	97	A

### 1.2.4 Project Description

Utilities is expanding the existing Briargate substation, located at the John Pinkerton site (East Woodmen Road and North Powers Blvd.), into the adjacent parcel that currently contains Utilities' Northeast gravel staging area. As a result of the substation expansion, Utilities is looking to relocate the Staging Area. The relocated Storage Area will include grading and surfacing of the north 5 acres of the parcel to accommodate the storing of material. Other improvements include the installation of a 7-foot chain link fence, a new asphalt driveway and tracking pad, a new gate, and a new scale and scale house. Excess material from the site grading will be used for the creation of a berm along the north and west side of the site. The new driveway will come off the existing driveway for the GPAP. The post-development conditions are shown on Figure 3 in Appendix F.

## 2.0 DRAINAGE BASINS AND SUB-BASINS

### 2.1 Major Basin Descriptions

The project area is within the Sand Creek (FOFO4000) El Paso County drainage basin. The basin slopes from north to south with flow eventually draining into the Sand Creek Main Stem. The average channel slope is approximately 1.5 percent.

The Sand Creek Drainage Basin Planning Study (Stantec, HDR and Dewberry, 2021) stated that the basin is heavily impacted by sedimentation. The project location, however, is not within any areas of concern for the basin. Recommendations provided in the drainage basin planning study include maintaining current reach improvements. No specific improvements will be required for this development.

Based on the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) Map No. 08041C0543G for El Paso County, Colorado, Effective Date December 7, 2018, the development is located within Zone X. Zone X is an area of minimal flood hazard. The flood hazard map is provided in Appendix B.

### 2.2 Sub-Basin Descriptions

Pre-development drainage, within the project area, flows from west to east toward an existing swale just outside the east property line. Flow is then conveyed from the property into an existing 18-inch culvert and into an existing detention pond on the adjacent parcel. As described in Section 1.2.3, the basin is HSG Type A soil, with primarily native vegetation ground cover. These conditions create low runoff potential and high infiltration rates.

The detention pond is a part of a stormwater facility that handles flows from the western portion of the GPAP property. Flows from the western area of the GPAP property are captured and conveyed by a concrete flow pan extending from the southern portion of the site to the pond. Based on the existing drainage design shown in Figure 2 of Appendix F the pond capacity is approximately 24,667 cubic feet at a depth 10-feet. The pond is lined with 12-inches of rip rap and discharges flows through an 18-inch x 29-inch elliptical pipe to the retention basin in the GPAP active area. The active areas of the GPAP facility are bounded by rectangular concrete ditches that collect flows and convey them to a lined retention pond. Pre-development drainage patterns and the culvert location are shown on Figure 2 in Appendix F.

### 3.0 DRAINAGE DESIGN CRITERIA

#### 3.1 Development Criteria Reference

The design criteria for the proposed drainage system for the CSU Northeast Gravel Staging Area are in accordance with El Paso County's *Drainage Criteria Manual, Volumes 1 and 2* (El Paso County 1994, 2002). Criteria from the Mile High Flood District (MHFD) Urban Storm Drainage Criteria Manual (USDCM), Volume 2 was also utilized in the design of the proposed drainage system. The Sand Creek Drainage Basin Planning Study was also referenced while developing the drainage plan for CSU. Based on the Project location in a Type 1 – improved – no modelled problems area, recommendations were to maintain current improvements.

#### 3.2 Hydrologic Criteria

Hydrologic calculations used in the analysis presented in this drainage report can be found in Appendix C. Peak runoff rates for the existing conditions 5-year and 100-year storm events are shown on Figure 2 in Appendix F and were found to be reasonable as the site conditions have not changed. Therefore, the 100-year design flow rates from Figure 2 is considered the pre-development flow rates for the project. To evaluate the existing culvert a 10-year pre-development flow rate was calculated. Flow rates were calculated for the post-development site conditions using the rational method option in Hydraflow Hydrographs extension of Autodesk Civil 3D. Time of concentration for the basin was calculated using Technical Release 55 (TR55) within the Hydrographs program. Runoff coefficients used in the calculations were obtained from Table 6-6 of the El Paso County Drainage Criteria Manual, Volume 1. Rainfall depths were sourced from Table 6-2 of the El Paso County Drainage Criteria Manual, Volume 1 and are shown below in Table 3-1.

**Table 3-1: Rainfall Depths for Colorado Springs**

Duration	Average Recurrence Interval (Years)					
	2-Year	5-Year	10-Year	25-Year	50-Year	100-Year
1-Hour	1.19	1.50	1.75	2.00	2.25	2.52
6-Hour	1.70	2.10	2.40	2.90	3.20	3.50
24-Hour	2.10	2.70	3.20	3.60	4.20	4.60

#### 3.3 Hydraulic Criteria

As described above the Staging Area will be constructed in an area that has existing stormwater controls to capture, convey, and store the stormwater runoff from the project. The existing detention basin and retention basin will control 100 percent of the runoff from the project. The controls hydraulic

performance will be evaluated using the post-development flow rates from the project to verify the capacity to accommodate the increased flows.

### 3.4 Water Quality Management

state the estimated acreage of proposed soil disturbance.

To verify compliance with the County's criteria and promote enhanced water quality in stormwater leaving the site, Best Management Practices (BMP's) were utilized. A Four-Step Process for water quality control BMP selection is provided in Appendix I of the El Paso County Engineering Criteria Manual (El Paso County, 2016). The Four-Step Process was adhered to in the drainage design and is discussed below.

#### 3.4.1 Water Quality Control BMP Selection

##### 3.4.1.1 Employ Runoff Reduction Practices

The first step of the BMP selection process is to reduce runoff from the proposed facility by reducing impervious areas to the extent practicable and routing runoff from impervious spaces over grass-lined areas. The proposed drainage design does increase impervious land cover. To counteract this change, the site drainage is directed into grass swales to promote infiltration prior to entering the existing culvert.

##### 3.4.1.2 Stabilize Drainageways

The second step of the BMP selection process is to choose appropriate stabilization methods for existing and new drainageways to prevent erosion. No new drainageways are included in the construction of the Staging Area. The Staging Area is being constructed at the top of the drainage basin and existing vegetated swales will remain in place for receiving runoff from the new gravel area.

##### 3.4.1.3 Provide Water Quality Capture Volume (WQCV)

In accordance with Section I.7.1C of Appendix I of the El Paso County Engineering Criteria Manual, the drainage basin that contains the new Staging Area is required to meet the "base design standard".

Although the existing detention basin is already present on site and receives runoff from the tributary area, it does not provide any treatment for the WQCV. The inlet of the discharge pipe from the detention pond is placed 2-feet above the bottom of the pond to accommodate a water quality volume. The grass buffer between the new Staging Area and existing culvert will also aid in water quality before discharging to the existing pond.

##### 3.4.1.4 Consider

Per Step 3 of the 4-Step Process (ECM Appendix I.7.2, ECM Chap 3.2.5.E, and MS4 Section 4.a.vi.B) - "all applicable development sites must have operational permanent stormwater quality control measures at the completion of construction." Between runoff reduction of the grass buffer/swale, the detention pond, and the retention pond, is it possible to show that the WQCV is being treated? Otherwise you will need to add capabilities on the site to treat the WQCV of the proposed disturbed area.

In accordance with Appendix I of the El Paso County Engineering Criteria Manual, the need for specialized BMPs must be considered if redevelopment activity will be significant. Due to the nature of the construction activities taking place on the project area, no specialized BMPs will be required.

Consider doing runoff reduction calcs to see what % of WQCV is infiltrated by grass buffer.

## 4.0 DRAINAGE FACILITY DESIGN

### 4.1 General Concept

The relocated Storage Area will include grading and surfacing of the north 5 acres of the parcel to accommodate the storing of material. Excess material from the site grading will be used for the creation of a berm along the north and west side of the site. The berm will not change existing drainage patterns significantly, it will only increase the barrier between the west bordering property, further decreasing the possibility of offsite flow onto the project. There is no change in site outfall overall, even though there is an increase in impervious landcover and changes in slope. **The drainage into the existing detention pond will increase but will be mitigated using a grass swale.** During construction activities, no special measures will be taken to prevent additional runoff from the site. There will be an adherence to the current Site SWMP plan to prevent any additional flow.

1) support/quantify this statement with runoff reduction calcs.  
 2) based on increased flows/velocities in the swale, discuss need (or lack there of) for erosion control (check dams, lining of flowline with ECM/TRM/riprap, vegetation, etc).

### 4.2 Existing Drainage Patterns

Table 4-1 – Predevelopment Hydrologic Conditions, shown below, provides a summary of the predevelopment runoff calculations included in Appendix C and shown on Figure 2 in Appendix F.

**Table 4-1: Pre-Development Hydrologic Conditions**

Minor Drainage Basin	Runoff Coefficient 10-year <sup>1</sup>	Runoff Coefficient 100-year	Area (Acres)	Time of Concentration, T <sub>c</sub>	10-Year, 24-Hour Flow <sup>2</sup> (cfs)	100-Year, 24-Hour Flow <sup>3</sup> (cfs)
EX-1	0.35	--	6.43	23	7.4	10.7
EX-2	0.35	--	3.58	21	4.5	6.4

<sup>1</sup> – Runoff coefficients chosen to achieve flow rates equal to those shown on Figure 2 of Appendix F then used to calculate to 10-year rates.

<sup>2</sup> – 10-year flow rates calculation in Appendix C.

<sup>3</sup> – 100-year flow rates from previous design shown in Figure 2 of Appendix F.

### 4.3 Improvements Analysis

The drainage patterns in the post development condition will remain like the pre-development condition with runoff flowing east toward the existing swale and culvert along the eastern boundary. The berm along the north and west boundary will create a drainage divide between the project site and adjacent property. The addition of the gravel surface and decrease in the vegetative cover will increase the imperviousness of the site. The proposed condition C-values were weighted based on the new gravel surfacing and remaining vegetated areas. Rational method calculations for the post-development conditions are included in Appendix C and summarized below in Table 4-2 - Post-Development Hydrologic Conditions.

**Table 4-2: Post-Development Hydrologic Conditions**

Minor Drainage Basin	Runoff Coefficient 10-year	Runoff Coefficient 100-year	Area (Acres)	Time of Concentration, $T_c$	10-Year, 24-Hour Flow (cfs)	100-Year, 24-Hour Flow (cfs)
PD-1	0.34	0.49	8.21	22	9.4	19.3
Pond Inflow <sup>1</sup>	--	--	11.79	--	13.6	25.5

<sup>1</sup> – Pond Inflow represents all flows to pond from combined hydrographs for EX-2 and PD-1.

## 4.4 Hydraulic Structures

The analysis of the existing 18-inch culvert includes post-development flows for the 10-year flow storm event. The analysis shows the culvert has the capacity to convey the post-development 10-year storm in an inlet condition with the headwater depth of approximately 2.3 feet. In the event of a 100-year storm in the post-development condition flows would be conveyed by the culvert and would most likely flow around the northern end of the berm and sheet flow toward the GPAP where it would be captured by the concrete ditches and routed to the retention pond. Calculations for the existing culvert are provided in Appendix D.

Using Existing Pond: Engineer must confirm in the Drainage Report that the existing pond is functioning as intended (ie: appears to have sufficient capacity based on visual inspection and no other maintenance is required or list if there are maintenance needs).

### 4.4.1 Detention Pond

The post-development flows from the site and the offsite area will be conveyed to the existing detention pond. The pond has a footprint of roughly 5,000 square feet measured at the top of the pond, which is at elevation 6579, and a volume of 24,667 cubic feet. **The existing detention pond is lined with rip rap and has some vegetation, so stormwater will be lost to infiltration and will not be discharged from the pond.**

The existing pond is sufficiently sized to hold the 100-year, 24-hour storm event even with the increase in post-development runoff from pre-development conditions. The drainage area for the detention pond includes basins PD-1 and EX-2 (11.79 total acres). The 100-year storage volume is based on a peak inflow, calculated by the Hydraflow Hydrographs software, of 25.5 cfs and results in maximum storage volume of 6,324 cubic feet at an elevation of 6573.39. **how much?**

The existing 18-inch x 29-inch elliptical CMP will be maintained as the outlet pipe for the detention pond. The discharge pipe is capable of conveying the increased runoff from the 10-year and 100-year storm events from the Staging Area project. Appendix D contains the hydraulic calculations for the culvert, detention pond, and discharge pipe.

#### **4.4.2 Cost Estimate of Proposed Facilities**

The cost estimate for all proposed facilities associated with the Staging Area is included in Appendix E.

#### **4.4.3 Cost of Drainage and Bridge Fees**

Drainage fees for the project area as of 2021 are \$20,387. Bridge fees as of 2021 are \$8,339.

#### **4.5 Other Government Agency Requirements**

Construction activities involved with the CSU Northeast Gravel Staging Area relocation are also governed by the Colorado Department of Public Health (CDPHE) Water Quality Control Division (WQD).

## **5.0 CONCLUSIONS**

### **5.1 Compliance with Standards**

In review of the proposed development for the Staging Area relocation, the improvements were found to be compliant with the El Paso County Land Development Code 2016 and the Urban Drainage and Flood Control District's Urban Storm Drainage Criteria Manual (USDCM) requirements.

## 6.0 REFERENCES

El Paso County, 1994. *Drainage Criteria Manual Volume 1*. October.

El Paso County, 2002. *Drainage Criteria Manual Volume 2*. November 1.


El Paso County, 2016. *Engineering Criteria Manual*. December 13.

GMS, 2008. *Final Drainage Report for Black Squirrel Creek Wastewater Treatment Plant*. March.


MHFD, 2010. *Urban Storm Drainage Criteria Manual, Volume 3*. November

**APPENDIX A – NRCS SOILS REPORT**

Hydrologic Soil Group—El Paso County Area, Colorado



Soil Map may not be valid at this scale.



### MAP LEGEND

**Area of Interest (AOI)**

 Area of Interest (AOI)

**Soils**

**Soil Rating Polygons**

-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

**Soil Rating Lines**

-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

**Soil Rating Points**

-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available

**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

**Warning:** Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado  
 Survey Area Data: Version 18, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 19, 2018—Sep 23, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	A	12.6	5.0%
10	Blendon sandy loam, 0 to 3 percent slopes	B	51.4	20.5%
28	Ellicott loamy coarse sand, 0 to 5 percent slopes	A	0.0	0.0%
97	Truckton sandy loam, 3 to 9 percent slopes	A	187.0	74.5%
<b>Totals for Area of Interest</b>			<b>251.1</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

**APPENDIX B – FEMA FLOODPLAIN MAP**

# National Flood Hazard Layer FIRMMette




104°41'23"W 38°53'18"N



## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

- |                                    |  |                                                                                                                                                                   |
|------------------------------------|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>SPECIAL FLOOD HAZARD AREAS</b>  |  | Without Base Flood Elevation (BFE)<br>Zone A, V, A99                                                                                                              |
|                                    |  | With BFE or Depth Zone AE, AO, AH, VE, AR                                                                                                                         |
|                                    |  | Regulatory Floodway                                                                                                                                               |
| <b>OTHER AREAS OF FLOOD HAZARD</b> |  | 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X |
|                                    |  | Future Conditions 1% Annual Chance Flood Hazard Zone X                                                                                                            |
|                                    |  | Area with Reduced Flood Risk due to Levee. See Notes. Zone X                                                                                                      |
|                                    |  | Area with Flood Risk due to Levee Zone D                                                                                                                          |
| <b>OTHER AREAS</b>                 |  | NO SCREEN Area of Minimal Flood Hazard Zone X                                                                                                                     |
|                                    |  | Effective LOMRs                                                                                                                                                   |
|                                    |  | Area of Undetermined Flood Hazard Zone D                                                                                                                          |
| <b>GENERAL STRUCTURES</b>          |  | Channel, Culvert, or Storm Sewer                                                                                                                                  |
|                                    |  | Levee, Dike, or Floodwall                                                                                                                                         |
| <b>OTHER FEATURES</b>              |  | 20.2 Cross Sections with 1% Annual Chance Water Surface Elevation                                                                                                 |
|                                    |  | 17.5 Coastal Transect                                                                                                                                             |
|                                    |  | Base Flood Elevation Line (BFE)                                                                                                                                   |
|                                    |  | Limit of Study                                                                                                                                                    |
|                                    |  | Jurisdiction Boundary                                                                                                                                             |
|                                    |  | Coastal Transect Baseline                                                                                                                                         |
|                                    |  | Profile Baseline                                                                                                                                                  |
|                                    |  | Hydrographic Feature                                                                                                                                              |
| <b>MAP PANELS</b>                  |  | Digital Data Available                                                                                                                                            |
|                                    |  | No Digital Data Available                                                                                                                                         |
|                                    |  | Unmapped                                                                                                                                                          |
- The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.



Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 8/26/2021 at 12:42 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

## **APPENDIX C – HYDROLOGIC CALCULATIONS**


# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Monday, 11 / 22 / 2021

## EX-1


Hydrograph type	= Rational	Peak discharge	= 7.415 cfs
Storm frequency	= 10 yrs	Time to peak	= 23 min
Time interval	= 1 min	Hyd. volume	= 10,233 cuft
Drainage area	= 6.430 ac	Runoff coeff.	= 0.35
Intensity	= 3.295 in/hr	Tc by TR55	= 23.00 min
IDF Curve	= CSU Storage Yard.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

## EX-2

Hydrograph type	= Rational	Peak discharge	= 4.467 cfs
Storm frequency	= 10 yrs	Time to peak	= 21 min
Time interval	= 1 min	Hyd. volume	= 5,629 cuft
Drainage area	= 3.580 ac	Runoff coeff.	= 0.36
Intensity	= 3.466 in/hr	Tc by TR55	= 21.00 min
IDF Curve	= CSU Storage Yard.IDF	Asc/Rec limb fact	= 1/1




# Hydrograph Report

## PD-1

Hydrograph type	= Rational	Peak discharge	= 9.430 cfs
Storm frequency	= 10 yrs	Time to peak	= 22 min
Time interval	= 1 min	Hyd. volume	= 12,447 cuft
Drainage area	= 8.210 ac	Runoff coeff.	= 0.34*
Intensity	= 3.378 in/hr	Tc by TR55	= 22.00 min
IDF Curve	= CSU Storage Yard.IDF	Asc/Rec limb fact	= 1/1

\* Composite (Area/C) = [(3.330 x 0.63) + (4.880 x 0.15)] / 8.210




# Hydrograph Report

## PD-1

Hydrograph type	= Rational	Peak discharge	= 19.34 cfs
Storm frequency	= 100 yrs	Time to peak	= 22 min
Time interval	= 1 min	Hyd. volume	= 25,527 cuft
Drainage area	= 8.210 ac	Runoff coeff.	= 0.49*
Intensity	= 4.807 in/hr	Tc by TR55	= 22.00 min
IDF Curve	= CSU Storage Yard.IDF	Asc/Rec limb fact	= 1/1

\* Composite (Area/C) = [(3.330 x 0.70) + (4.880 x 0.35)] / 8.210



## **APPENDIX D – HYDRAULIC CALCULATIONS**

# Culvert Report

## Ex. 18-inch CMP

Invert Elev Dn (ft)	= 6577.50
Pipe Length (ft)	= 95.00
Slope (%)	= 8.00
Invert Elev Up (ft)	= 6585.10
Rise (in)	= 18.0
Shape	= Circular
Span (in)	= 18.0
No. Barrels	= 1
n-Value	= 0.024
Culvert Type	= Circular Corrugate Metal Pipe
Culvert Entrance	= Projecting
Coeff. K,M,c,Y,k	= 0.034, 1.5, 0.0553, 0.54, 0.9

### Embankment


Top Elevation (ft)	= 6589.00
Top Width (ft)	= 8.00
Crest Width (ft)	= 100.00

### Calculations

Qmin (cfs)	= 9.00
Qmax (cfs)	= 10.00
Tailwater Elev (ft)	= 0.00

### Highlighted

Qtotal (cfs)	= 9.40
Qpipe (cfs)	= 9.40
Qovertop (cfs)	= 0.00
Veloc Dn (ft/s)	= 9.45
Veloc Up (ft/s)	= 6.28
HGL Dn (ft)	= 6578.32
HGL Up (ft)	= 6586.28
Hw Elev (ft)	= 6587.42
Hw/D (ft)	= 1.54
Flow Regime	= Inlet Control




# Hydrograph Report

## Pond Inlet

Hydrograph type = Combine  
Storm frequency = 10 yrs  
Time interval = 1 min  
Inflow hyds. = 2, 3

Peak discharge = 13.63 cfs  
Time to peak = 23 min  
Hyd. volume = 18,159 cuft  
Contrib. drain. area = 3.830 ac




# Hydrograph Report

## Pond Inlet

Hydrograph type = Combine  
Storm frequency = 100 yrs  
Time interval = 1 min  
Inflow hyds. = 2, 3

Peak discharge = 25.49 cfs  
Time to peak = 23 min  
Hyd. volume = 33,665 cuft  
Contrib. drain. area = 3.830 ac



# Pond Report

## Pond No. 1 - Detention Pond

### Pond Data

Contours -User-defined contour areas. Average end area method used for volume calculation. Beginning Elevation = 6569.00 ft

### Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	6569.00	800	0	0
1.00	6570.00	1,056	928	928
2.00	6571.00	1,344	1,200	2,128
3.00	6572.00	1,664	1,504	3,632
4.00	6573.00	2,016	1,840	5,472
5.00	6574.00	2,400	2,208	7,680
6.00	6575.00	2,816	2,608	10,288
7.00	6576.00	3,264	3,040	13,328
8.00	6577.00	3,744	3,504	16,832
9.00	6578.00	4,256	4,000	20,832
10.00	6579.00	4,800	4,528	25,360

### Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 18.00	Inactive	Inactive	Inactive
Span (in)	= 29.00	0.00	0.00	0.00
No. Barrels	= 1	1	0	1
Invert El. (ft)	= 6571.00	0.00	0.00	0.00
Length (ft)	= 395.00	0.00	0.00	0.00
Slope (%)	= 4.60	0.00	0.00	n/a
N-Value	= .024	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	No	No	No

### Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	Inactive	0.00	0.00	0.00
Crest El. (ft)	= 0.00	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= ---	---	---	---
Multi-Stage	= No	No	No	No
Exfil.(in/hr)	= 0.000	(by Wet area)		
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).

### Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
0.00	0	6569.00	0.00	---	---	---	---	---	---	---	---	---	0.000
0.10	93	6569.10	0.00	---	---	---	---	---	---	---	---	---	0.000
0.20	186	6569.20	0.00	---	---	---	---	---	---	---	---	---	0.000
0.30	278	6569.30	0.00	---	---	---	---	---	---	---	---	---	0.000
0.40	371	6569.40	0.00	---	---	---	---	---	---	---	---	---	0.000
0.50	464	6569.50	0.00	---	---	---	---	---	---	---	---	---	0.000
0.60	557	6569.60	0.00	---	---	---	---	---	---	---	---	---	0.000
0.70	650	6569.70	0.00	---	---	---	---	---	---	---	---	---	0.000
0.80	742	6569.80	0.00	---	---	---	---	---	---	---	---	---	0.000
0.90	835	6569.90	0.00	---	---	---	---	---	---	---	---	---	0.000
1.00	928	6570.00	0.00	---	---	---	---	---	---	---	---	---	0.000
1.10	1,048	6570.10	0.00	---	---	---	---	---	---	---	---	---	0.000
1.20	1,168	6570.20	0.00	---	---	---	---	---	---	---	---	---	0.000
1.30	1,288	6570.30	0.00	---	---	---	---	---	---	---	---	---	0.000
1.40	1,408	6570.40	0.00	---	---	---	---	---	---	---	---	---	0.000
1.50	1,528	6570.50	0.00	---	---	---	---	---	---	---	---	---	0.000
1.60	1,648	6570.60	0.00	---	---	---	---	---	---	---	---	---	0.000
1.70	1,768	6570.70	0.00	---	---	---	---	---	---	---	---	---	0.000
1.80	1,888	6570.80	0.00	---	---	---	---	---	---	---	---	---	0.000
1.90	2,008	6570.90	0.00	---	---	---	---	---	---	---	---	---	0.000
2.00	2,128	6571.00	0.00	---	---	---	---	---	---	---	---	---	0.000
2.10	2,278	6571.10	0.26 ic	---	---	---	---	---	---	---	---	---	0.261
2.20	2,429	6571.20	0.74 ic	---	---	---	---	---	---	---	---	---	0.737
2.30	2,579	6571.30	1.35 ic	---	---	---	---	---	---	---	---	---	1.351
2.40	2,730	6571.40	2.08 ic	---	---	---	---	---	---	---	---	---	2.081
2.50	2,880	6571.50	2.91 ic	---	---	---	---	---	---	---	---	---	2.909
2.60	3,030	6571.60	3.83 ic	---	---	---	---	---	---	---	---	---	3.834
2.70	3,181	6571.70	4.83 ic	---	---	---	---	---	---	---	---	---	4.831
2.80	3,331	6571.80	5.90 ic	---	---	---	---	---	---	---	---	---	5.896
2.90	3,482	6571.90	7.04 ic	---	---	---	---	---	---	---	---	---	7.036
3.00	3,632	6572.00	8.23 ic	---	---	---	---	---	---	---	---	---	8.228
3.10	3,816	6572.10	9.49 ic	---	---	---	---	---	---	---	---	---	9.494

Continues on next page...

Detention Pond

**Stage / Storage / Discharge Table**

Stage ft	Storage cuft	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
3.20	4,000	6572.20	10.82 ic	---	---	---	---	---	---	---	---	---	10.82
3.30	4,184	6572.30	12.19 ic	---	---	---	---	---	---	---	---	---	12.19
3.40	4,368	6572.40	13.63 ic	---	---	---	---	---	---	---	---	---	13.63
3.50	4,552	6572.50	15.12 ic	---	---	---	---	---	---	---	---	---	15.12
3.60	4,736	6572.60	16.10 ic	---	---	---	---	---	---	---	---	---	16.10
3.70	4,920	6572.70	17.02 ic	---	---	---	---	---	---	---	---	---	17.02
3.80	5,104	6572.80	17.89 ic	---	---	---	---	---	---	---	---	---	17.89
3.90	5,288	6572.90	18.72 ic	---	---	---	---	---	---	---	---	---	18.72
4.00	5,472	6573.00	19.51 ic	---	---	---	---	---	---	---	---	---	19.51
4.10	5,693	6573.10	20.28 ic	---	---	---	---	---	---	---	---	---	20.28
4.20	5,914	6573.20	21.02 ic	---	---	---	---	---	---	---	---	---	21.02
4.30	6,134	6573.30	21.73 ic	---	---	---	---	---	---	---	---	---	21.73
4.40	6,355	6573.40	22.42 ic	---	---	---	---	---	---	---	---	---	22.42
4.50	6,576	6573.50	23.09 ic	---	---	---	---	---	---	---	---	---	23.09
4.60	6,797	6573.60	23.75 ic	---	---	---	---	---	---	---	---	---	23.75
4.70	7,018	6573.70	24.38 ic	---	---	---	---	---	---	---	---	---	24.38
4.80	7,238	6573.80	25.00 ic	---	---	---	---	---	---	---	---	---	25.00
4.90	7,459	6573.90	25.60 ic	---	---	---	---	---	---	---	---	---	25.60
5.00	7,680	6574.00	26.18 ic	---	---	---	---	---	---	---	---	---	26.18
5.10	7,941	6574.10	26.76 ic	---	---	---	---	---	---	---	---	---	26.76
5.20	8,202	6574.20	27.32 ic	---	---	---	---	---	---	---	---	---	27.32
5.30	8,462	6574.30	27.87 ic	---	---	---	---	---	---	---	---	---	27.87
5.40	8,723	6574.40	28.41 ic	---	---	---	---	---	---	---	---	---	28.41
5.50	8,984	6574.50	28.94 ic	---	---	---	---	---	---	---	---	---	28.94
5.60	9,245	6574.60	29.37 oc	---	---	---	---	---	---	---	---	---	29.37
5.70	9,506	6574.70	29.44 oc	---	---	---	---	---	---	---	---	---	29.44
5.80	9,766	6574.80	29.52 oc	---	---	---	---	---	---	---	---	---	29.52
5.90	10,027	6574.90	29.59 oc	---	---	---	---	---	---	---	---	---	29.59
6.00	10,288	6575.00	29.66 oc	---	---	---	---	---	---	---	---	---	29.66
6.10	10,592	6575.10	29.73 oc	---	---	---	---	---	---	---	---	---	29.73
6.20	10,896	6575.20	29.80 oc	---	---	---	---	---	---	---	---	---	29.80
6.30	11,200	6575.30	29.87 oc	---	---	---	---	---	---	---	---	---	29.87
6.40	11,504	6575.40	29.94 oc	---	---	---	---	---	---	---	---	---	29.94
6.50	11,808	6575.50	30.01 oc	---	---	---	---	---	---	---	---	---	30.01
6.60	12,112	6575.60	30.09 oc	---	---	---	---	---	---	---	---	---	30.09
6.70	12,416	6575.70	30.16 oc	---	---	---	---	---	---	---	---	---	30.16
6.80	12,720	6575.80	30.23 oc	---	---	---	---	---	---	---	---	---	30.23
6.90	13,024	6575.90	30.30 oc	---	---	---	---	---	---	---	---	---	30.30
7.00	13,328	6576.00	30.37 oc	---	---	---	---	---	---	---	---	---	30.37
7.10	13,678	6576.10	30.44 oc	---	---	---	---	---	---	---	---	---	30.44
7.20	14,029	6576.20	30.51 oc	---	---	---	---	---	---	---	---	---	30.51
7.30	14,379	6576.30	30.58 oc	---	---	---	---	---	---	---	---	---	30.58
7.40	14,730	6576.40	30.65 oc	---	---	---	---	---	---	---	---	---	30.65
7.50	15,080	6576.50	30.72 oc	---	---	---	---	---	---	---	---	---	30.72
7.60	15,430	6576.60	30.79 oc	---	---	---	---	---	---	---	---	---	30.79
7.70	15,781	6576.70	30.85 oc	---	---	---	---	---	---	---	---	---	30.85
7.80	16,131	6576.80	30.92 oc	---	---	---	---	---	---	---	---	---	30.92
7.90	16,482	6576.90	30.99 oc	---	---	---	---	---	---	---	---	---	30.99
8.00	16,832	6577.00	31.06 oc	---	---	---	---	---	---	---	---	---	31.06
8.10	17,232	6577.10	31.13 oc	---	---	---	---	---	---	---	---	---	31.13
8.20	17,632	6577.20	31.20 oc	---	---	---	---	---	---	---	---	---	31.20
8.30	18,032	6577.30	31.26 oc	---	---	---	---	---	---	---	---	---	31.26
8.40	18,432	6577.40	31.33 oc	---	---	---	---	---	---	---	---	---	31.33
8.50	18,832	6577.50	31.40 oc	---	---	---	---	---	---	---	---	---	31.40
8.60	19,232	6577.60	31.47 oc	---	---	---	---	---	---	---	---	---	31.47
8.70	19,632	6577.70	31.54 oc	---	---	---	---	---	---	---	---	---	31.54
8.80	20,032	6577.80	31.60 oc	---	---	---	---	---	---	---	---	---	31.60
8.90	20,432	6577.90	31.67 oc	---	---	---	---	---	---	---	---	---	31.67
9.00	20,832	6578.00	31.74 oc	---	---	---	---	---	---	---	---	---	31.74
9.10	21,285	6578.10	31.80 oc	---	---	---	---	---	---	---	---	---	31.80
9.20	21,738	6578.20	31.87 oc	---	---	---	---	---	---	---	---	---	31.87
9.30	22,190	6578.30	31.94 oc	---	---	---	---	---	---	---	---	---	31.94
9.40	22,643	6578.40	32.00 oc	---	---	---	---	---	---	---	---	---	32.00
9.50	23,096	6578.50	32.07 oc	---	---	---	---	---	---	---	---	---	32.07
9.60	23,549	6578.60	32.14 oc	---	---	---	---	---	---	---	---	---	32.14
9.70	24,002	6578.70	32.20 oc	---	---	---	---	---	---	---	---	---	32.20
9.80	24,454	6578.80	32.27 oc	---	---	---	---	---	---	---	---	---	32.27
9.90	24,907	6578.90	32.34 oc	---	---	---	---	---	---	---	---	---	32.34
10.00	25,360	6579.00	32.40 oc	---	---	---	---	---	---	---	---	---	32.40

...End

# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Monday, 11 / 22 / 2021

## Pond Discharge

Hydrograph type = Reservoir  
Storm frequency = 10 yrs  
Time interval = 1 min  
Inflow hyd. No. = 4 - Pond Inlet  
Reservoir name = Detention Pond

Peak discharge = 12.89 cfs  
Time to peak = 24 min  
Hyd. volume = 16,030 cuft  
Max. Elevation = 6572.35 ft  
Max. Storage = 4,273 cuft

Storage Indication method used.




# Hydrograph Report

## Pond Discharge

Hydrograph type = Reservoir  
Storm frequency = 100 yrs  
Time interval = 1 min  
Inflow hyd. No. = 4 - Pond Inlet  
Reservoir name = Detention Pond

Peak discharge = 22.32 cfs  
Time to peak = 25 min  
Hyd. volume = 31,537 cuft  
Max. Elevation = 6573.39 ft  
Max. Storage = 6,324 cuft

Storage Indication method used.



# Culvert Report

## Ex. 18x29-inch Pond Discharge CMP

Invert Elev Dn (ft)	= 6552.80
Pipe Length (ft)	= 395.00
Slope (%)	= 4.61
Invert Elev Up (ft)	= 6571.00
Rise (in)	= 18.0
Shape	= Elliptical
Span (in)	= 29.0
No. Barrels	= 1
n-Value	= 0.024
Culvert Type	= Horizontal Ellipse Concrete
Culvert Entrance	= Groove end projecting (H)
Coeff. K,M,c,Y,k	= 0.0045, 2, 0.0317, 0.69, 0.2


<b>Embankment</b>	
Top Elevation (ft)	= 6579.00
Top Width (ft)	= 8.00
Crest Width (ft)	= 100.00

### Calculations

Qmin (cfs)	= 10.00
Qmax (cfs)	= 13.00
Tailwater Elev (ft)	= 0.00

### Highlighted

Qtotal (cfs)	= 12.90
Qpipe (cfs)	= 12.90
Qovertop (cfs)	= 0.00
Veloc Dn (ft/s)	= 7.75
Veloc Up (ft/s)	= 7.02
HGL Dn (ft)	= 6553.61
HGL Up (ft)	= 6571.90
Hw Elev (ft)	= 6572.73
Hw/D (ft)	= 1.15
Flow Regime	= Inlet Control



# Culvert Report

## Ex. 18x29-inch Pond Discharge CMP

Invert Elev Dn (ft)	= 6552.80
Pipe Length (ft)	= 395.00
Slope (%)	= 4.61
Invert Elev Up (ft)	= 6571.00
Rise (in)	= 18.0
Shape	= Elliptical
Span (in)	= 29.0
No. Barrels	= 1
n-Value	= 0.024
Culvert Type	= Horizontal Ellipse Concrete
Culvert Entrance	= Groove end projecting (H)
Coeff. K,M,c,Y,k	= 0.0045, 2, 0.0317, 0.69, 0.2


<b>Embankment</b>	
Top Elevation (ft)	= 6579.00
Top Width (ft)	= 8.00
Crest Width (ft)	= 100.00

### Calculations

Qmin (cfs)	= 22.00
Qmax (cfs)	= 24.00
Tailwater Elev (ft)	= 0.00

### Highlighted

Qtotal (cfs)	= 22.30
Qpipe (cfs)	= 22.30
Qovertop (cfs)	= 0.00
Veloc Dn (ft/s)	= 9.00
Veloc Up (ft/s)	= 9.00
HGL Dn (ft)	= 6553.94
HGL Up (ft)	= 6572.20
Hw Elev (ft)	= 6573.95
Hw/D (ft)	= 1.96
Flow Regime	= Inlet Control



## **APPENDIX E – FINANCIAL ASSURANCE**

Please submit this as FAE and fill out quantities for BMPs that will be used on the site.

2021 Financial Assurance Estimate Form  
(with pre-plat construction)

Updated: 12/22/2020

PROJECT INFORMATION			
Project Name	GPAP Staging Area	Date	11/1/2021 PCD File No. PPR2150

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining
<b>SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)</b>						
* Earthwork						
less than 1,000; \$5,300 min		CY	\$ 8.00	= \$ -		\$ -
1,000-5,000; \$8,000 min		CY	\$ 6.00	= \$ -		\$ -
5,001-20,000; \$30,000 min	14,100	CY	\$ 5.00	= \$ 70,500.00		\$ 70,500.00
20,001-50,000; \$100,000 min		CY	\$ 3.50	= \$ -		\$ -
50,001-200,000; \$175,000 min		CY	\$ 2.50	= \$ -		\$ -
greater than 200,000; \$500,000 min		CY	\$ 2.00	= \$ -		\$ -
* Permanent Seeding (inc. noxious weed mgmnt.)	1	AC	\$ 828.00	= \$ 828.00		\$ 828.00
* Mulching	0	AC	\$ 777.00	= \$ -		\$ -
* Permanent Erosion Control Blanket	0	SY	\$ 6.00	= \$ -		\$ -
* Permanent Pond/BMP Construction	0	CY	\$ 21.00	= \$ -		\$ -
* Permanent Pond/BMP (provide engineer's estimate)	0	EA		= \$ -		\$ -
Safety Fence	0	LF	\$ 3.00	= \$ -		\$ -
Temporary Erosion Control Blanket	0	SY	\$ 3.00	= \$ -		\$ -
Vehicle Tracking Control	1	EA	\$ 2,453.00	= \$ 2,453.00		\$ 2,453.00
Silt Fence	0	LF	\$ 2.60	= \$ -		\$ -
Temporary Seeding	0	AC	\$ 650.00	= \$ -		\$ -
Temporary Mulch	0	AC	\$ 777.00	= \$ -		\$ -
Erosion Bales	0	EA	\$ 26.00	= \$ -		\$ -
Erosion Logs/Straw Waddle	0	LF	\$ 5.00	= \$ -		\$ -
Rock Check Dams	0	EA	\$ 518.00	= \$ -		\$ -
Inlet Protection	1	EA	\$ 173.00	= \$ 173.00		\$ 173.00
Sediment Basin	0	EA	\$ 1,824.00	= \$ -		\$ -
Concrete Washout Basin	1	EA	\$ 932.00	= \$ 932.00		\$ 932.00
[insert items not listed but part of construction plans]				= \$ -		\$ -
<b>MAINTENANCE (35% of Construction BMPs)</b>				= \$ 1,245.30		\$ 1,245.30
<b>Section 1 Subtotal</b>				= \$ <b>76,131.30</b>		\$ <b>76,131.30</b>

\* Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

**SECTION 2 - PUBLIC IMPROVEMENTS \***

ROADWAY IMPROVEMENTS						
Construction Traffic Control		LS		= \$ -		\$ -
Aggregate Base Course (135 lbs/cf)		Tons	\$ 29.00	= \$ -		\$ -
Aggregate Base Course (135 lbs/cf)		CY	\$ 52.00	= \$ -		\$ -
Asphalt Pavement (3" thick)		SY	\$ 14.50	= \$ -		\$ -
Asphalt Pavement (4" thick)		SY	\$ 20.00	= \$ -		\$ -
Asphalt Pavement (6" thick)		SY	\$ 30.00	= \$ -		\$ -
Asphalt Pavement (147 lbs/cf) ___" thick		Tons	\$ 91.00	= \$ -		\$ -
Raised Median, Paved		SF	\$ 8.30	= \$ -		\$ -
Regulatory Sign/Advisory Sign		EA	\$ 311.00	= \$ -		\$ -
Guide/Street Name Sign		EA		= \$ -		\$ -
Epoxy Pavement Marking		SF	\$ 14.00	= \$ -		\$ -
Thermoplastic Pavement Marking		SF	\$ 24.00	= \$ -		\$ -
Barricade - Type 3		EA	\$ 207.00	= \$ -		\$ -
Delineator - Type I		EA	\$ 25.00	= \$ -		\$ -
Curb and Gutter, Type A (6" Vertical)		LF	\$ 31.00	= \$ -		\$ -
Curb and Gutter, Type B (Median)		LF	\$ 31.00	= \$ -		\$ -
Curb and Gutter, Type C (Ramp)		LF	\$ 31.00	= \$ -		\$ -
4" Sidewalk (common areas only)		SY	\$ 50.00	= \$ -		\$ -
5" Sidewalk		SY	\$ 62.00	= \$ -		\$ -
6" Sidewalk		SY	\$ 75.00	= \$ -		\$ -
8" Sidewalk		SY	\$ 99.00	= \$ -		\$ -
Pedestrian Ramp		EA	\$ 1,190.00	= \$ -		\$ -
Cross Pan, local (8" thick, 6' wide to include return)		LF	\$ 63.00	= \$ -		\$ -
Cross Pan, collector (9" thick, 8' wide to include return)		LF	\$ 95.00	= \$ -		\$ -
Curb Chase		EA	\$ 1,532.00	= \$ -		\$ -
Guardrail Type 3 (W-Beam)		LF	\$ 51.00	= \$ -		\$ -
Guardrail Type 7 (Concrete)		LF	\$ 75.00	= \$ -		\$ -
Guardrail End Anchorage		EA	\$ 2,172.00	= \$ -		\$ -
Guardrail Impact Attenuator		EA	\$ 3,899.00	= \$ -		\$ -
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 81.00	= \$ -		\$ -
Sound Barrier Fence (panels, 6' high)		LF	\$ 83.00	= \$ -		\$ -
Electrical Conduit, Size =		LF	\$ 17.00	= \$ -		\$ -
Traffic Signal, complete intersection		EA	\$ 439,875	= \$ -		\$ -

**PROJECT INFORMATION**

**Project Name** GPAP Staging Area      **Date** 11/1/2021      **PCD File No.** PPR2150

Description	Quantity	Units	Unit Cost	=	\$	Total	(with Pre-Plat Construction)		
							% Complete	Remaining	
<i>[insert items not listed but part of construction plans]</i>								\$	-
<b>STORM DRAIN IMPROVEMENTS</b>								\$	-
Concrete Box Culvert (M Standard), Size ( W x H )		LF		=	\$	-	\$	-	
18" Reinforced Concrete Pipe		LF	\$ 67.00	=	\$	-	\$	-	
24" Reinforced Concrete Pipe		LF	\$ 81.00	=	\$	-	\$	-	
30" Reinforced Concrete Pipe		LF	\$ 100.00	=	\$	-	\$	-	
36" Reinforced Concrete Pipe		LF	\$ 124.00	=	\$	-	\$	-	
42" Reinforced Concrete Pipe		LF	\$ 166.00	=	\$	-	\$	-	
48" Reinforced Concrete Pipe		LF	\$ 202.00	=	\$	-	\$	-	
54" Reinforced Concrete Pipe		LF	\$ 254.00	=	\$	-	\$	-	
60" Reinforced Concrete Pipe		LF	\$ 298.00	=	\$	-	\$	-	
66" Reinforced Concrete Pipe		LF	\$ 344.00	=	\$	-	\$	-	
72" Reinforced Concrete Pipe		LF	\$ 393.00	=	\$	-	\$	-	
18" Corrugated Steel Pipe		LF	\$ 87.00	=	\$	-	\$	-	
24" Corrugated Steel Pipe		LF	\$ 99.00	=	\$	-	\$	-	
30" Corrugated Steel Pipe		LF	\$ 126.00	=	\$	-	\$	-	
36" Corrugated Steel Pipe		LF	\$ 152.00	=	\$	-	\$	-	
42" Corrugated Steel Pipe		LF	\$ 174.00	=	\$	-	\$	-	
48" Corrugated Steel Pipe		LF	\$ 184.00	=	\$	-	\$	-	
54" Corrugated Steel Pipe		LF	\$ 269.00	=	\$	-	\$	-	
60" Corrugated Steel Pipe		LF	\$ 290.00	=	\$	-	\$	-	
66" Corrugated Steel Pipe		LF	\$ 352.00	=	\$	-	\$	-	
72" Corrugated Steel Pipe		LF	\$ 414.00	=	\$	-	\$	-	
78" Corrugated Steel Pipe		LF	\$ 476.00	=	\$	-	\$	-	
84" Corrugated Steel Pipe		LF	\$ 569.00	=	\$	-	\$	-	
Flared End Section (FES) RCP Size =		EA		=	\$	-	\$	-	
<i>(unit cost = 6x pipe unit cost)</i>									
Flared End Section (FES) CSP Size =		EA		=	\$	-	\$	-	
<i>(unit cost = 6x pipe unit cost)</i>									
End Treatment- Headwall		EA		=	\$	-	\$	-	
End Treatment- Wingwall		EA		=	\$	-	\$	-	
End Treatment - Cutoff Wall		EA		=	\$	-	\$	-	
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 5,736.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 7,440.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=5', 10' ≤ Depth < 15'		EA	\$ 8,637.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=10', Depth < 5'		EA	\$ 7,894.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=10', 5' ≤ Depth < 10'		EA	\$ 8,136.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=10', 10' ≤ Depth < 15'		EA	\$ 10,185.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=15', Depth < 5'		EA	\$ 10,265.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=15', 5' ≤ Depth < 10'		EA	\$ 11,005.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=15', 10' ≤ Depth < 15'		EA	\$ 12,034.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=20', Depth < 5'		EA	\$ 10,940.00	=	\$	-	\$	-	
Curb Inlet (Type R) L=20', 5' ≤ Depth < 10'		EA	\$ 12,075.00	=	\$	-	\$	-	
Grated Inlet (Type C), Depth < 5'		EA	\$ 4,802.00	=	\$	-	\$	-	
Grated Inlet (Type D), Depth < 5'		EA	\$ 5,932.00	=	\$	-	\$	-	
Storm Sewer Manhole, Box Base		EA	\$ 12,034.00	=	\$	-	\$	-	
Storm Sewer Manhole, Slab Base		EA	\$ 6,619.00	=	\$	-	\$	-	
Geotextile (Erosion Control)		SY	\$ 6.20	=	\$	-	\$	-	
Rip Rap, d50 size from 6" to 24"		Tons	\$ 83.00	=	\$	-	\$	-	
Rip Rap, Grouted		Tons	\$ 98.00	=	\$	-	\$	-	
Drainage Channel Construction, Size ( W x H )		LF		=	\$	-	\$	-	
Drainage Channel Lining, Concrete		CY	\$ 590.00	=	\$	-	\$	-	
Drainage Channel Lining, Rip Rap		CY	\$ 116.00	=	\$	-	\$	-	
Drainage Channel Lining, Grass		AC	\$ 1,520.00	=	\$	-	\$	-	
Drainage Channel Lining, Other Stabilization				=	\$	-	\$	-	
<i>[insert items not listed but part of construction plans]</i>								\$	-
<i>* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)</i>								\$	-
<b>Section 2 Subtotal</b>				=	\$	-	\$	-	

**PROJECT INFORMATION**

<b>Project Name</b>	GPAP Staging Area	<b>Date</b>	11/1/2021	<b>PCD File No.</b>	PPR2150
---------------------	-------------------	-------------	-----------	---------------------	---------

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining
<b>SECTION 3 - COMMON DEVELOPMENT IMPROVEMENTS (Private or District and NOT Maintained by EPC)**</b>						
<b>ROADWAY IMPROVEMENTS</b>						
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
<b>STORM DRAIN IMPROVEMENTS</b> (Exception: Permanent Pond/BMP shall be itemized under Section 1)						
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
				= \$	-	\$ -
<b>WATER SYSTEM IMPROVEMENTS</b>						
Water Main Pipe (PVC), Size 8"		LF	\$ 66.00	= \$	-	\$ -
Water Main Pipe (Ductile Iron), Size 8"		LF	\$ 78.00	= \$	-	\$ -
Gate Valves, 8"		EA	\$ 1,923.00	= \$	-	\$ -
Fire Hydrant Assembly, w/ all valves		EA	\$ 6,828.00	= \$	-	\$ -
Water Service Line Installation, inc. tap and valves		EA	\$ 1,370.00	= \$	-	\$ -
Fire Cistern Installation, complete		EA		= \$	-	\$ -
				= \$	-	\$ -
<i>[insert items not listed but part of construction plans]</i>						
				= \$	-	\$ -
<b>SANITARY SEWER IMPROVEMENTS</b>						
Sewer Main Pipe (PVC), Size 8"		LF	\$ 66.00	= \$	-	\$ -
Sanitary Sewer Manhole, Depth < 15 feet		EA	\$ 4,540.00	= \$	-	\$ -
Sanitary Service Line Installation, complete		EA	\$ 1,451.00	= \$	-	\$ -
Sanitary Sewer Lift Station, complete		EA		= \$	-	\$ -
				= \$	-	\$ -
<i>[insert items not listed but part of construction plans]</i>						
				= \$	-	\$ -
<b>LANDSCAPING IMPROVEMENTS</b> (For subdivision specific condition of approval, or PUD)						
		EA		= \$	-	\$ -
		EA		= \$	-	\$ -
		EA		= \$	-	\$ -
		EA		= \$	-	\$ -
		EA		= \$	-	\$ -
		EA		= \$	-	\$ -
<b>Section 3 Subtotal</b>				<b>= \$</b>	<b>-</b>	<b>\$ -</b>

\*\* Section 3 is not subject to defect warranty requirements

**PROJECT INFORMATION**


**Project Name** GPAP Staging Area      **Date** 11/1/2021      **PCD File No.** PPR2150

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS	= \$	-		\$ -
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS	= \$	-		\$ -
<b>Total Construction Financial Assurance</b>						<b>\$ 76,131.30</b>
(Sum of all section subtotals plus as-builts and pond/BMP certification)						
<b>Total Remaining Construction Financial Assurance (with Pre-Plat Construction)</b>						<b>\$ 76,131.30</b>
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)						
<b>Total Defect Warranty Financial Assurance</b>						<b>\$ 14,265.60</b>
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)						

**Approvals**

I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.

  
 Richard Sebastian-Coleman, Engineer (P.E. Seal Required)



Clint Barden, Owner / Applicant


Date

Approved by El Paso County Engineer / ECM Administrator

Date


Please sign across seal.

## **APPENDIX F – DRAINAGE FIGURES**



- Briargate Substation at John Pinkerton site
- Existing Northeast Staging Area
- ◆ Briargate Staging Area Relocation Site

FIGURE 1






**BURNS  
& MCDONNELL**


**GRAVEL STAGING AREA  
RELOCATION  
BRIARGATE SUBSTATION**

COLORADO SPRINGS UTILITIES  
COLORADO SPRINGS, CO


FIGURE 2





TYPICAL CHANNEL SECTION  
SCALE 1" = 2'



SECTION A-A



DETENTION POND DETAIL  
SCALE 1" = 10'



SITE HYDROLOGY DATA					
DESIGN POINT	INCL. BASINS	AREA (Ac)	Q <sub>5</sub> (cfs)	Q <sub>100</sub> (cfs)	NOTE
▽1	1	6.43	4.4	10.7	PEAK DISCHARGE WEST OF BERM INTO 2-12" PIPES & ENTERING POND
▽2	2	3.58	2.6	6.4	PEAK DISCHARGE IN CHANNEL FROM BASIN 1 ENTERING POND
▽3	1, 2	10.01	--	16.3	TOTAL PEAK DISCHARGE INTO POND (TOTAL INFLOW)
▽4	1, 2	10.01	--	13.2	TOTAL PEAK DISCHARGE FROM 24" 18" ARCH CSP OUTLET PIPE (TOTAL OUTFLOW)

LEGEND

- DRAINAGE BASIN BOUNDARY LINE
- DRAINAGE BASIN DESIGNATION
- DRAINAGE BASIN AREA
- PROPOSED STORM DRAIN PIPE
- DESIGN POINT DESIGNATION
- FLOW DIRECTION ARROW

NOTE: THE EXISTING TOPOGRAPHY SHOWN ON THIS MAP IS FROM THE COLORADO SPRINGS UTILITIES FACILITY INFORMATION MANAGEMENT SYSTEMS (FIMS) PROVIDED BY THE GAS DEPARTMENT


PROJECT: COLORADO SPRINGS UTILITIES - GAS DEPT.  
TITLE: DRAINAGE IMPROVEMENTS PLAN - PROF. PEAK PLAN



MONUMENT VALLEY ENGINEERS INC.  
ENGINEERS • SURVEYORS  
191 LELAND STREET  
COLORADO SPRINGS, CO 80909  
PHONE 719.533.6337

PROJ. NO. 0577  
DRAWN: DRG  
ENGINEER: DRG  
CHECKED:  
SCALE: 1" = 10'  
DATE: 5-21-96  
REVISIONS:  
NO. DATE ITR

SHEET  
DRAWN: DRG  
057701



**LEGEND**

- PROPERTY LINE
- - - EXISTING FENCE
- x — PROPOSED FENCE
- 4350 — EXISTING 2' CONTOUR
- 4350 — PROPOSED 2' CONTOUR
- (Blue Line) — DRAINAGE BOUNDARY
- (Green Line with Arrow) — DESIGN DRAINAGE PATH
- (Black Arrow) — FLOW DIRECTION
- (Blue Star) — DRAINAGE DESIGN POINT
- GAS — EXISTING GAS LINE
- (Gravel Pattern) — GRAVEL

**BASIN ID** **XX**

**BASIN AREA** **1.23 | 0.10**  
**AC. | 0.11**

**RUNOFF COEFFICIENTS (10 & 100 YEAR)**

**DRAINAGE POINT SUMMARY TABLE**

POINT ID	TIME OF CONCENTRATION (MIN)	10 YEAR PEAK FLOW (cfs)	100 YEAR PEAK FLOW (cfs)
POI-1	22.0	9.4	19.3
POI-2	24.0	13.6	25.5

**NORTH**

0 150' 300'

**SCALE IN FEET**

**BURNS MCDONNELL**

**FIGURE 3**  
COLORADO SPRINGS UTILITIES  
BRIARGATE STORAGE YARD  
RELOCATION  
POST-DEVELOPMENT DRAINAGE  
EL PASO COUNTY, COLORADO



CREATE AMAZING.

Burns & McDonnell World Headquarters  
9400 Ward Parkway  
Kansas City, MO 64114  
O 816-333-9400  
F 816-333-3690  
[www.burnsmcd.com](http://www.burnsmcd.com)



2880 International Circle, Suite 110  
 Colorado Springs, CO 80910  
 Phone 719-520-6300  
 Fax 719-520-6695  
 www.elpasoco.com

**EL PASO COUNTY PLANNING AND  
 COMMUNITY DEVELOPMENT  
 DEPARTMENT**

**FINAL DRAINAGE REPORT (FDR) CHECKLIST**

Revised: July 2019

Applicant	PCD
-----------	-----

**1 Final Drainage Report**

The final drainage report finalizes concepts and presents the design details for the drainage facilities. Any changes to the preliminary design concepts presented in a preliminary drainage plan due to review comments by the County are incorporated into the final drainage plan. A final drainage report is generally required to accompany any site development plan, final plat or major development that utilized a preliminary drainage report, or which does not qualify for a letter report. A determination of whether a final drainage report is required shall be made by the ECM Administrator in conformance with the requirements of the ECM. When specific improvements are required, the construction drawings and specifications shall be submitted for review with the final drainage plan, and any improvements included in the construction financial assurance required by the ECM.

The purpose of the Final Drainage Report is to finalize concepts and to present the design details for the drainage facilities presented in the PDR. Also, any change to the preliminary design concepts which were incorporated due to review comments by the County, must be presented. The FDR shall contain all components of the PDR checklist plus additional necessary information relating to the design of specific facilities associated with the development.

<b>a</b>	<b>Report Contents</b>		
1	Table of contents, pages numbered	X	
2	Existing/Historic and Developed Conditions Plans at the end of the report	X	
<b>b</b>	<b>General Location</b>		
1	City and County, and local streets within and adjacent to the subdivision.	Sect 1.1	
2	Township, Range, section, 1/4 section.	Sect 1.1	
3	Major drainage ways and existing facilities.	Sect 1.2.2	
4	Names of surrounding platted developments.	Sect 1.1	
<b>c</b>	<b>Description of Property</b>		
1	Area in acres.	Sect 1.2.1	
2	Ground cover, (type of trees, shrubs, vegetation).	Sect 1.2.1	
3	General topography	Sect 1.2.2	
4	General soil conditions.	Sect 1.2.3	
5	Major drainageways	Sect 2.1	
6	Irrigation facilities	N/A	
7	Utilities and other encumbrances	Sect 1.2.1	
<b>d</b>	<b>Major Basin Descriptions</b>		
1	Reference should be made to major drainageway planning studies; Such as Drainage Basin Planning Studies; Flood Hazard delineation reports, and flood insurance studies or maps if available.	Sect 2.1	
2	A flood plain statement shall be provided indicating whether any portion of the development is in a designated floodplain as delineated on the current FEMA mapping.	Sect 2.1	
3	Major basin drainage characteristics.	Sect 2.1	
4	Identification of all nearby irrigation facilities and other obstructions which could influence or be influenced by local drainage.	N/A	
<b>e</b>	<b>Sub-Basin Descriptions</b>		
1	Discussion of historic drainage patterns of the property in question	Sect 2.2	
2	Discussion of offsite drainage flow patterns and their impact on the development.	Sect 2.2	
<b>f</b>	<b>Drainage Design Criteria</b>		
1	Reference all criteria, master plans, and technical information used for report preparation and design; any deviation from such material must be discussed and justified.	Sect 3.1	
2	Discussion of previous drainage studies (i.e. PDR, drainage basin planning studies, master plans, flood insurance studies) for the site in question that influence or are influenced by the drainage design and how the studies affect drainage design for the site	Sect 2.1	



2880 International Circle, Suite 110  
 Colorado Springs, CO 80910  
 Phone 719-520-6300  
 Fax 719-520-6695  
 www.elpasoco.com

**EL PASO COUNTY PLANNING AND  
 COMMUNITY DEVELOPMENT  
 DEPARTMENT**

**FINAL DRAINAGE REPORT (FDR) CHECKLIST**

Revised: July 2019

		Applicant	PCD
<b>g</b>	<b>Four Step Process</b>		
1	Runoff reduction proposed.	Sect 3.4.1	
2	Stabilization of drainage ways proposed/discussed.	Sect 3.4.2	
3	Proposed Stormwater Quality Capture Volume (WQCV) proposed.	Sect 3.4.3	
4	Identify Best Management Practices (BMP's) to be used to control industrial and commercial pollutants.	Sect 3.4.4	
<b>h</b>	<b>Hydrologic Criteria</b>		
1	Identify design rainfall.	Sect 3.2	
2	Identify runoff calculation method.	Sect 3.2	
3	Identify design storm recurrence intervals	Sect 3.2	
4	Identify detention discharge and storage calculation method.	Sect 3.3	
5	Note ECM Appendix I Full Spectrum Detention (FSD) requirement.	N/A	
<b>i</b>	<b>Drainage Facility Design - General Concept</b>		
1	Discussion of compliance with offsite runoff considerations.	N/A	
2	Discussion of anticipated and proposed drainage patterns.	Sect 4.1	
3	Discussion of the content of tables, charts, figures, plates or drawings presented in the report.	X	
<b>j</b>	<b>Drainage Facility Design - Specific Details</b>		
1	Presentation of existing and proposed hydrologic conditions including approximate flow rates entering and exiting the subdivision with all necessary calculation	Sect 4.2	
2	Presentation of approach to accommodate drainage impacts on existing or proposed improvements and facilities	Sect 4.3	
3	Presentation of proposed facilities with respect to alignment, material and structure type.	N/A	
4	Discussion of drainage impact of site constraints such as streets, utilities existing and proposed structures.	Sect 4.4	
5	Environmental features and issues shall be presented if applicable.	N/A	
6	Discussion of maintenance access and aspects of the preliminary design.	N/A	
7	Discussion and analysis of existing and proposed downstream drainage facilities and their ability to convey developed runoff from the proposed development.	Sect 4.4	
8	Presentation of detention storage and outlet design (including reservoir routings) when applicable. Note the Engineering Critreia Manual Appendix I which requires Full Spectrum Detention.	App C&D	
9	Presentations of all hydrologic and hydraulic calculations including hydraulic grade line computations as appropriate. Recommended use of Urban Drainage and Flood Control District (UDFCD) spreadsheets and calculations to properly meet this requirement.	App C&D	
10	Presentation of an accurate, complete current estimate of cost of proposed facilities.	Sect 4.4.2	
11	Presentation of all drainage fees bridge fees for the property in question as applicable.	Sect 4.4.3	
<b>k</b>	<b>Other Government agency requirements</b>		
1	Federal Emergency Management Agency (FEMA)	N/A	
2	Army Corps of Engineers (COE)	N/A	
3	Colorado State Engineer	N/A	
4	Colorado Water Conservation Board (CWCB)	N/A	
5	Others	N/A	
<b>l</b>	<b>Drawing Contents, two maps/plans are required, existing conditions &amp; the proposed plans.</b>		
1	General Location Map: A map shall be provided in sufficient detail to identify drainage flows entering and leaving the development and general drainage patterns. The map should be at a scale of 1"=50' to 1"=2000'. The map shall identify any major construction (i.e. development, irrigation ditches, existing detention facilities, culverts, storm sewers, etc.) that shall influence or be influenced by the subdivision.	App F	
2	Drainage Plan: Map(s) of the proposed development at a scale of 1"=20' to 1"=200' shall be included to identify existing and proposed conditions on or adjacent to the site in question.	App F	



2880 International Circle, Suite 110  
 Colorado Springs, CO 80910  
 Phone 719-520-6300  
 Fax 719-520-6695  
 www.elpasoco.com

**EL PASO COUNTY PLANNING AND  
 COMMUNITY DEVELOPMENT  
 DEPARTMENT**

**FINAL DRAINAGE REPORT (FDR) CHECKLIST**

Revised: July 2019

		Applicant	PCD
i	Existing and proposed contours at 2 feet maximum intervals. For subdivisions involving rural lots greater than 1.0 acre, the maximum interval may be 5 feet where approved. In terrain greater than 10% the intervals should be 10 foot intervals.	App F	
ii	Property lines and existing or proposed easements with purposes noted.	App F	
iii	All Streets	App F	
iv	Existing drainage facilities and structures, including irrigation ditches roadside ditches, drainageways, gutters and culverts, all indicating flow direction. All pertinent information such as material, size, shape, slope and locations shall also be included.	App F	
v	Overall drainage area boundary and drainage sub-area boundaries relating to the subdivision.	App F	
vi	Proposed type of street sections (i.e., vertical or ramp curb and gutters roadside ditch, gutter flow and/or cross pans).	N/A	
vii	Proposed storm sewers and open drainageways, including inlets, manholes, culverts, and other appurtenances.	N/A	
viii	Proposed outfall point for runoff from the developed area and facilities to convey flows to the final outfall point without damage to downstream properties.	App F	
ix	Routing and summary of initial and major flow rates at various design points for all storm runoff associated with the property.	App F	
x	Path (s) chosen for computation of time of concentration.	App F	
xi	Details of and design computations for detention storage facilities including outlet.	App F	
xii	Location and elevations of all defined 100-year flood plains affecting the property.	N/A	
xiii	Location of all existing and proposed utilities affected by or affecting the drainage design.	App F	

**4. Applicant Comments:**

If the applicant has failed to provide any of the required items they must provide justification in the comment section below indicating why the requirement is unnecessary.

1			
2			
3			