

**SAND CREEK - CENTER TRIBUTARY
CHANNEL ANALYSIS REPORT
FOR
SOLACE APARTMENTS**

**Prepared For:
Jackson Dearborn Partners
404 S. Wells Street, Suite 400
Chicago, IL 60607
(734) 216-2577**

**June 30, 2020
Project No. 25174.00**

**Prepared By:
JR Engineering, LLC
5475 Tech Center Drive
Colorado Springs, CO 80919
719-593-2593**

PCD File NO. SP201

CONTENTS

OVERVIEW	3
GENERAL LOCATION AND DESCRIPTION	3
LOCATION.....	3
DESCRIPTION OF PROPERTY	3
FLOODPLAIN STATEMENT.....	3
PREVIOUS SAND CREEK STUDIES	3
DRAINAGE DESIGN CRITERIA	8
DEVELOPMENT CRITERIA REFERENCE	8
HYDROLOGIC CRITERIA.....	8
HYDRAULIC CRITERIA.....	8
SUMMARY	8
REFERENCES:	10

APPENDICES

- A. Figures and Exhibits
- B. Hydraulic Calculations
- C. Reference Material

OVERVIEW

This report was prepared to provide design information for the existing Sand Creek -Center Tributary Drainageway as part of the Solace Apartment development. This document is the Channel Analysis report for the Solace Apartments. The Sand Creek-Center Tributary Drainageway has been studied as part of a Flood Insurance Study (FIS) for El Paso County Colorado, Volume 7 of 8, revised December 7, 2018 and Sand Creek Drainage Basin Planning Study, dated January 1993. Existing flow rates from the Sand Creek Planning Study were used as the basis for the design of the existing channel condition.

GENERAL LOCATION AND DESCRIPTION

Location

The proposed Solace Apartments, known as “Solace” from herein, is a parcel of land located in Section 7, Township 14 South, Range 65 West of the 6th Principal Meridian in El Paso County, Colorado. Solace is a 28.99 acre, urban, multifamily-development and is comprised of 16 apartment buildings and associated infrastructure. Solace is bound by existing industrial developments to the North and vacant land to the West. Galley Road bounds the property to the south and existing light industrial businesses to the east. A vicinity map of the area is presented in Appendix A.

Description of Property

Solace is currently unoccupied and undeveloped. The existing ground cover is sparse vegetation and open space, typical of a Colorado rolling range land condition. In general, Solace slopes from northwest to southeast. The existing conditions of the Sand Creek -Center Tributary Drainageway on the site are heavily wooded for the length of the channel throughout the Solace site.

Per an NRCS web soil survey of the area, Solace is made up of Type B soils with a very small percentage of Type A in the northwest corner of the property. This Type B soil is a blendon sandy loam. This soil type has a moderate infiltration rate when thoroughly wet. It also consists of moderately deep or deep, moderately well drained or well drained soil. A soil survey map has been presented in Appendix A.

Floodplain Statement

Based on the FEMA FIRM Map numbers 08041C0751G & 08041C0752G, dated December 7, 2018, a portion of the existing drainageway lies within Zone AE and Zone X. Zone AE is defined as area subject to inundation by the 1-percent-annual-chance flood event and is a flood hazard area. Zone X is defined as area outside the Special Flood Hazard Area (SFHA) and higher than the elevation of the 0.2-percent-annual-chance (or 500-year) flood. The FIRM Map has been presented in Appendix A. Currently a portion of the Solace site lies within Zone AE at the extension of Paonia Street to Galley Road, as seen in FEMA FIRM Map number 08041C0752G.

PREVIOUS SAND CREEK STUDIES

Solace lies within Sand Creek Drainage Basin based on the “*Sand Creek Drainage Basin Planning Study*” prepared by Kiowa Engineering in January 1993.

The Sand Creek Drainage Basin covers approximately 54 square miles in unincorporated El Paso County, CO. The Sand Creek Drainage Basin is tributary to Fountain Creek. In its existing condition, the basin is comprised of developed land with the exception of the Solace Parcel which is comprised of rolling rangeland with fair to good vegetative cover associated with Colorado’s semi-arid climate. The natural Drainageway within the site limits is typically deep and narrow with a well-defined flow path in most areas. Anticipated land use for the Solace parcel includes multifamily residential and open space.


As part of its drainage research, JR Engineering reviewed the following drainage studies, reports and LOMRs:

- Sand Creek Drainage Basin Planning Study prepared by Kiowa Engineering Corporation in January 1993.
- Flood Insurance Study– El Paso County, Colorado & Incorporated Areas Vol 7 of 8, December 2018.
- LOMR- Case No. 05-08-0368P Federal Emergency Management Agency, May 23, 2007.

The *Sand Creek Drainage Basin Planning Study* was used to establish a stormwater management plan for the existing and future stormwater infrastructure needs within the Sand Creek Drainage Basin. The *Sand Creek Drainage Basin Planning Study* conducted a hydrologic analysis using a runoff model named the Soil Conservation Service (SCS) Computer Program for the Project Formulation Hydrology (TR20). Based on provided drainage maps and analysis, in its existing condition, the Sand Creek-Center Tributary Drainageway contains a 100-year flow of 720 cfs at upstream station 1053 then jumps to 960 cfs at station 1030 in Sand Creek along Solace’s east property line. The flow then changes again at station 1014, to a value of 956 cfs, where the flow from the secondary drainageway on Paonia Street converges with the Sand Creek Drainageway, this flow was based on JR Engineering analysis. These flows were used in the model as they were depicted as being the flows present in the project section of the Sand Creek Tributary Drainageway as called out in *Sand Creek Drainage Basin Planning Study*. The major Sand Creek-Center Tributary Drainageway conveys the stormwater south along the eastern property line where it ultimately outfalls into the Fountain Creek. JR Engineering also performed a hydrologic analysis to determine the flows in the Sand Creek-Center Tributary Drainageway and arrived at similar results to those shown in the *Sand Creek Drainage Basin Planning Study*, thus verifying the validity of these flows. These basin calculations show that the 720-960 cfs, based on the *Sand Creek Drainage Basin Planning Study*, are still valid for this existing condition, a summary table of the flows in the Sand Creek Drainageway based on various studies can be found below.

After further review by staff it appears that Section B of the FEMA Floodway data table outlined (790cfs) may not be the flow that corresponds with section B of the FIRM MAP. Provide the floodway data table for the section B that corresponds to the FEMA flood profile shown on page 337P. The flow at this section should be used for your analysis of the secondary drainageway not the difference in the flows from the sections upstream at Omaha blvd. Also, staff has found a previous preliminary drainage report for the site (PCD File No. SP07011) that indicates that the DBPS indicated a flow of 500 cfs at this secondary drainageway. Please revise your analysis accordingly.

FLOODING SOURCE		FLOODWAY			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQ. FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY
Sand Creek Center Tributary				Revised Data	
A	940	40	92	8.6	6,106.5
B	990	40	118	6.7	6,107.2
C	2,238	91	120	6.6	6,120.2
D	3,948	46	95	8.0	6,138.3
E	4,547	170	159	4.8	6,147.4
F	5,539	52	97	7.8	6,156.8
G	7,191	63	104	7.3	6,176.2
H	7,940	52	98	7.8	6,189.6
I	8,527	40	92	8.6	6,197.6
@ STA 125+00		960			
@ STA 132+30		6284			
Flood Insurance Study, El Paso County, Rev. December 7, 2018		Section N, @ Galley Road			
JR Engineering October 2019		@ Galley Road			



FEMA prepared a revised FIS for El Paso County Colorado, Volume 7 of 8, dated 2018. The effective floodplain for the site is shown on the FIRM 08041C0752G, revised to reflect LOMR, dated May 23, 2007. The study area of the FIS where the Sand Creek Drainageway crosses Galley Road, was found to overtop the culverts and flow onto the road. According to the FIS, this crossing has a 10% annual chance of flooding and is located in Zone AE of the FIRM. This location is a Special Flood Hazard Area (SFHA) inundated by the 100-year flood, Zone AE (base flood elevations determined). The Sand Creek Drainage Basin LOMR was executed on May 23, 2007. The LOMR revised the flood zone or the area south of Galley Road. See FIRM Map Panel 08041C0752G for limits of LOMR study and revised flood zones, presented in Appendix C.

To the west of the Sand Creek-Center Tributary Drainageway is a secondary Drainageway that captures the flow coming from the west side of Paonia Street. This drainage way is located at the proposed extension of Paonia Street to meet Galley Road. The flows created by the secondary drainageway and the development north of the site will be captured on the Solace site, and transported to the Sand Creek-Center Tributary Drainageway. According to Sand Creek Drainage Basin LOMR, the flow present in this secondary drainageway in a 1-percent-annual-chance flood event is 213 cfs. This was calculated by use of the LOMR maps, and evaluating the difference in flow as the Sand Creek Center Tributary Drainageway splits as it crosses Omaha Boulevard. Section R of the FEMA Map Panel 08041C0752G, shows the split as the flow present in the channel drops to 421 cfs from 634 cfs at section S just upstream. The difference in these flows is 213 cfs this flow is assumed to overtop the road at Omaha Boulevard crossing structure, and travel west to Paonia Street and is routed south in the Sand Creek Center Tributary onto the Solace site. Just north of the Solace site, exist a concrete channel that diverts flows present on the east side of Paonia in to the creek, however the size of this channel will not convey all flows present in Paonia to the Sand Creek-Center Tributary Drainageway, therefore improvements are necessary to mitigate the offsite flows. To mitigate offsite flows from coming onto the site, the future Paonia Street will be graded with a super elevation that will direct the majority of the flows present on Paonia towards the east side of the road.

These flows will be captured by the proposed extension of Paonia Street. **Per County Criteria (ECM 2.3.3.D) super elevation is not permitted on roadways with design speeds less than 50 mph. This proposal would require a deviation request form to be submitted for review and a decision by the ECM administrator. Submitting a deviation request does not imply that it will be approved. Alternatively multiple options may be provided for diverting the flow with a statement indicating that final analysis will be provided with the final drainage report.**

Sand Creek-Center Tributary Drainageway. The spillway is a 50'-80' wide riprap lined channel that will safely direct flows off Paonia Street and into the existing drainageway. Flow calculations for the overflow can be found in Appendix B, along with flow capacity calculations for existing Paonia Street & existing concrete channel north of the site.

Channel Deficiencies

The *Sand Creek Drainage Basin Planning Study* performed a hydraulic analysis of the Sand Creek-Center Tributary Drainageway between Galley Road and Paonia Street, and an analysis of the crossing structure for Sand Creek at Galley Road. For the crossing structure at Galley Road they determined that the existing crossing structures were inadequate for the demands of the Drainageway and would require improvements to expand the capacity of these structures. These results can be seen in Table IV-1 Summary of Hydraulic Structures – Crossings: Sand Creek Drainage Basin Planning Study shown below. The Study proposed improvements to the existing crossing structures by replacing them with 3-8'Wx 5'H Concrete Box Culverts.

LOCATION	REACH #	SIZE	TYPE	CAPACITY EXISTING	CAPACITY FUTURE (1)	COMMENTS
Airport Road	CT-1	5-6'x8'	BOX CULVERT	ADEQUATE	ADEQUATE	
Pikes Peak Ave.	CT-1	NONE		INADEQUATE	INADEQUATE	POWERS BLVD. OVERTOPPED FREQUENTLY BETWEEN BIJOU ST. AND PIKES PEAK AVE.
Powers Blvd.	CT-1	VARIOUS	METAL PIPE	INADEQUATE	INADEQUATE	
Platte Ave (US 24)	CT-1	8'x4'	BOX CULVERT	INADEQUATE	INADEQUATE	APPROACH CHANNEL IN NEED OF REALIGNMENT
Terminal Avenue	CT-2	2-4'x8'	BOX CULVERT	INADEQUATE	INADEQUATE	
Galley Road	CT-2	3-42"x72"	METAL ARCH PIPE	INADEQUATE	INADEQUATE	
Omaha Boulevard	CT-2	2-36"x57"	METAL ARCH PIPE	INADEQUATE	INADEQUATE	

The study also found the existing channel for the Sand Creek-Center Tributary Drainageway between Galley Road and Paonia Street to be inadequate for the given flow rate. The report says that the existing channel has limited maintenance access, leading to the channel degrading and being filled with obstructions. Those findings can be seen in Table IV-2 Summary of Hydraulic Structures – Channels: Sand Creek Drainage Basin Planning Study. The *Sand Creek Drainage Basin Planning Study* recommended improvements to the existing channel by lining the channel with concrete.

LOCATION FROM/ TO	REACH #	DIMENSIONS			TYPE	CAPACITY (I)		COMMENTS
		TW (ft)	SS	DEPTH (ft)		ADQ	INADQ	
CENTER TRIBUTARY								
East Fork Sand Creek to Airport Road	CT-1	45	2:1	6	Riprap lined trapezoidal channel	X	X	Riprap has failed or is non-existent along some portions of this segment of the Center Tributary
Pikes Peak to Bijou St.	CT-1			N/A	Rubble lined ditches along Powers Blvd.			Flow passes over and along Powers Blvd. street section on a frequent basis. Road closures common.
Bijou St. to Platte Ave.	CT-1			N/A	Unlined, natural.			Overbanks vegetated, channel dry with sand invert, no vegetation. Channel eroded at outlet of US24 culvert.
Platte Ave. to Terminal Ave.	CT-2	15-25	1:1	4-6	Trapezoidal concrete lined.	X		Channel has adequate capacity.
Terminal Avenue to Galley Road	CT-2	21	1:1	5	Trapezoidal concrete lined.	X		Channel has adequate capacity.
Galley Road to Paonia Ct. (ext)	CT-2	30-40	varies	4-5	Unimproved segment.		X	Channel is degraded and filled with debris. Poor maintenance access.
Paonia Ct. to Omaha Blvd.	CT-2	21	1:1	5	Trapezoidal concrete lined channel.	X		Maintenance access poor. Debris and trash in channel.

The GeoHecRas model results completed with this report contain similar findings to those in the drainage basin planning study. This model was based on the existing channel conditions; a model will be created for the sites proposed conditions in the final drainage report. Average velocities of 10-12 fps for a majority of the channel reach exceed allowable limits for an unprotected channel. The current Galley road crossing structures lack of capacity also leads to overtopping of the road during these events. This report confirms that both this Sand Creek channel reach and Galley Road crossing structures are inadequate for the 100-yr storm event.

Channel Improvement Recommendations

The *Sand Creek Drainage Basin Planning Study (DBPS)* concluded that the Sand Creek-Center Tributary Drainageway channel, in its current state, is inadequate to handle the historical flows tributary to the channel. This report falls in line, indicating that improvements shall be made to the channel in order to provide adequate capacity and prevent erosion. In the DBPS improvements are also designated for the crossing structures at Galley Road to provide adequate capacity and prevent overtopping of the road. Upon further investigation, this report found that overtopping of Galley Road appears to be addressed via the overflow structure and associate downstream bank protections shown in Figure 1. This weir was analyzed to determine the effectiveness to safely pass overtopping flows. From the HEC-RAS model, it was determined that approximately 581 cfs overtops the roadway during a 100-



Figure 1: Existing Drainage Structures at Galley Road (Viewed from South)

year event. The weir in its current configuration could only adequately pass approximately 40 cfs of this flow. On the north side of the Galley road crossing, there is a section of roadway without curb & gutter; this allows the water transported along the north half of galley road to directly flow into the Sand Creek Center Tributary Drainageway. A picture of this curb opening is shown below in figure 2.



Figure 2: Curb Opening on North Half of the Galley Road Crossing
(Looking to the North)

This analysis notes existing overtopping, further discussion with the county engineer to discuss potential solutions is recommended. One possible solution is that the existing culverts be replaced to prevent overtopping at Galley Road by upsizing to a larger culvert(s). Ultimately, culvert improvements will be necessary when the County deems the historic overtopping of Galley Road above acceptable tolerance. Currently, no adjacent structures are impacted by this overtopping. Weir calculations can be found in the appendix.

Based upon the findings to the *Sand Creek Drainage Basin Planning Study* and the conforming GeoHecRas modeling contained in this report, potential recommended channel improvements include:

- Widening of the channel west bank to reduce flow depth, thus corresponding velocities
- Lining portions of the channel with riprap or other protective surfaces
- Adding check structures and potentially drop structures to reduce channel grade, a conceptual profile can be seen in Appendix A.
- Replacing existing culverts at Galley Road to prevent roadway overtopping

Stable slopes of 1% were chosen for the channel based on stable slope specified by the *The Sand Creek Drainage Basin Planning Study (DBPS.)*

CONCEPT COST ESTIMATE

Below is Conceptual Cost Estimate for the proposed channel improvements to the Sand Creek-Center Tributary Drainageway.

Table 3: Cost Opinion-Public Reimbursable

PUBLIC DRAINAGE FACILITIES				
Item	Quantity	Unit	Unit Price	Extended Cost
Clearing & Grubbing	2	AC	\$5,000.00	\$10,000.00
Channel Widening Earthwork (Cut)	7000	CY	\$3.00	\$21,000.00
Riprap Lining (Type M)	5100	CY	\$85.00	\$433,500.00
Drop Structures	2	EA	\$20,000.00	\$40,000.00
			Sub-Total	\$504,500.00
			10% Eng. And Contingency	\$50,450.00
			Grand Total	\$554,950.00

DRAINAGE DESIGN CRITERIA

Development Criteria Reference

Storm drainage analysis techniques were taken from the “*City of Colorado Spring/El Paso County Drainage Criteria Manual*” Volumes 1 and 2 (EPCDCM), dated October 12, 1994, the “*Urban Storm Drainage Criteria Manual*” Volumes 1 - 3 (USDCM) and Chapter 6 and Section 3.2.1 of Chapter 13 of the “*Colorado Springs Drainage Criteria Manual (CCSDCM)*, dated May 2014, as adopted by El Paso County.

Hydrologic Criteria

The hydrologic analysis for this project is based on the *Sand Creek Drainage Basin Planning Study*. The flow rates for the 100-yr storm event were taken from sheets CTP-2 & CTP-3 of this study. The Baseline Flows from the *Sand Creek Drainage Basin Planning Study* are included in Appendix C.

Hydraulic Criteria

GeoHecRas was used as the primary analysis method for the site. GeoHecRas was used to model existing flows within the Sand Creek-Center Tributary Drainageway. This model was used to verify flood plains and analyze any overtopping that may occur within the project site. The 100-year water surface profiles for the model were analyzed from the north property line of the site to the area 100 feet south of the Galley Road Crossing. Hydraulic computations for the models are contained in Appendix B. In the model the value for the roughness coefficient (n) were based upon those shown in Table 12-2 of the City of Colorado Springs Drainage Criteria Manual, Volume 1. The manning’s

roughness coefficient for the sides of the channel was evaluated as $n = 0.05$, as the channel sides are most closely categorized as sluggish reaches with weeds, the minimum value of n was taken. For the bottom of the channel a manning's roughness coefficient value of $n = 0.025$, as the existing channel bottom being very clear and free of plants or other debris, the minimum value of n was taken. Table 12-2 highlights the manning values used for the model. The channel was analyzed as a winding channel in the GeoHecRas model.

Table 12-2. Roughness Coefficients

Channel Description	Roughness Coefficient (n)		
	Minimum	Typical	Maximum
Natural Streams (top width at flood stage <100 feet			
1. Streams on Plain			
a. Clean, straight, full stage, no rifts or deep pools	0.025	0.030	0.033
b. Same as above, but more stones and weeds	0.030	0.035	0.040
c. Clean, winding, some pools and shoals	0.033	0.040	0.045
d. Same as above, but some weeds and stones	0.035	0.045	0.050
e. Same as above, lower stages, more ineffective slopes and sections	0.040	0.048	0.055
f. Same as c, but more stones	0.045	0.050	0.060
g. Sluggish reaches, weedy, deep pools	0.050	0.070	0.080
h. Very weedy reaches, deep pools, or floodways with heavy stand of timber and underbrush	0.075	0.100	0.150
2. Mountain Streams, no vegetation in channel, banks usually steep, trees and brush along banks submerged at high stages			
a. Bottom: gravels, cobbles, and few boulders	See Jarrett's equation*		
b. Bottom: cobbles with large boulders	See Jarrett's equation*		

The flows in the channel, upstream and downstream of the Solace site, were determined using the sheet CTP-2 of the *Sand Creek Drainage Basin Planning Study*, with the flow 720 cfs being used at the upstream end of the channel till river station 1031 where the flow changes to 960 cfs, and once again at the Galley Road crossing to 1340 cfs. These can be seen in the GeoHecRas output table. Geometry of the channel and the crossing structure at Galley Road was determined from survey conducted by JR Engineering's internal survey department. The Galley road crossing structure was modeled in the GeoHecRas model; its geometric parameters were determined using survey obtained data to the crossing. The sizes of the 48" CMP culverts in the crossing were also determined from survey data.

SUMMARY

This analysis of the Sand Creek-Center Tributary Drainageway remains consistent with previous studies. Velocities in the drainageway are of concern and require channel improvements, such as widening and riprap lining to ensure the Sand Creek Drainageway remains stable during a 100-yr event. This report meets the latest El Paso County Drainage Criteria requirements for this site. The results of JR Engineering's GeoHecRas model for the channel appear accurate as the water surface elevations of the channel matchup very closely to the elevations called out in the FEMA FIS along the channel. The overtopping elevation at Galley Road shown in the model matches the elevation shown in the FEMA floodplain map of 6249, showing that the GeoHecRas model results are valid.


REFERENCES:

1. El Paso County Drainage Criteria Manual Volume 1, El Paso County, CO, 1994.
2. Urban Storm Drainage Criteria Manual, Urban Drainage and Flood Control District, Latest Revision.
3. Flood Insurance Study- El Paso County, Colorado & Incorporated Areas Vol 7 of 8, Federal Emergency Management Agency, December 7, 2018.
4. Sand Creek Drainage Basin Planning Study, Kiowa Engineering, January 1993.
5. Sand Creek Drainage Basin LOMR, Federal Emergency Management Agency, May 23, 2007.

APPENDIX A

FIGURES AND EXHIBITS

X:\2510000.all\2517400\Drawings\Blocks\Vicinity Map - Drainage.dwg, 8.5x11 Portrait, 12/17/2019 11:14:34 AM, PhillipsJ



SITE




ORIGINAL SCALE: 1" = 500'

VICINITY MAP
 SOLACE APARTMENTS
 JOB NO. 15504.03
 4/27/2018




Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

Hydrologic Soil Group—El Paso County Area, Colorado



Map Scale: 1:15,300 if printed on A landscape (11" x 8.5") sheet.




Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84



MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Lines

-  A
-  A/D
-  B
-  B/D
-  C
-  C/D
-  D
-  Not rated or not available

Soil Rating Points



-  A
-  A/D
-  B
-  B/D

-  C
-  C/D
-  D
-  Not rated or not available


Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
 Survey Area Data: Version 17, Sep 13, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 19, 2018—Sep 23, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	A	373.7	35.4%
10	Blendon sandy loam, 0 to 3 percent slopes	B	321.4	30.5%
11	Bresser sandy loam, cool, 0 to 3 percent slopes	B	31.9	3.0%
12	Bresser sandy loam, cool, 3 to 5 percent slopes	B	69.8	6.6%
13	Bresser sandy loam, cool, 5 to 9 percent slopes	B	41.4	3.9%
28	Ellicott loamy coarse sand, 0 to 5 percent slopes	A	96.1	9.1%
56	Nelson-Tassel fine sandy loams, 3 to 18 percent slopes	B	3.7	0.3%
70	Pits, gravel	A	10.3	1.0%
94	Travessilla-Rock outcrop complex, 8 to 90 percent slopes	D	51.5	4.9%
95	Truckton loamy sand, 1 to 9 percent slopes	A	35.7	3.4%
96	Truckton sandy loam, 0 to 3 percent slopes	A	19.7	1.9%
Totals for Area of Interest			1,055.2	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options


Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

S
P
R
I
N
G
S

E
D



1370000 FT

38° 50' 37.50"

104° 43' 7.50"

5'25"000m E

JOINS PANEL 0754



MAP SCALE 1" = 500'



PANEL 0752G

FIRM
FLOOD INSURANCE RATE MAP
EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS

PANEL 752 OF 1300
 (SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
COLORADO SPRINGS, CITY OF	080060	0752	G
EL PASO COUNTY	080059	0752	G

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.



MAP NUMBER
08041C0752G

MAP REVISED
DECEMBER 7, 2018

Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations (BFEs)** and/or **floodways** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of 0.0' North American Vertical Datum of 1988 (NAVD88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this jurisdiction.

The **projection** used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The **horizontal datum** was NAD83, GRS80 spheroid. Differences in datum, spheroid, projection or UTM zones zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the **North American Vertical Datum of 1988 (NAVD88)**. These flood elevations must be compared to structure and ground elevations referenced to the same **vertical datum**. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov/> or contact the National Geodetic Survey at the following address:

NGS Information Services
 NOAA, NINGS12
 National Geodetic Survey
 SSMC-3, #9202
 1315 East-West Highway
 Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242 or visit its website at <http://www.ngs.noaa.gov/>.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, City of Fountain, Bureau of Land Management, National Oceanic and Atmospheric Administration, United States Geological Survey, and Anderson Consulting Engineers, Inc. These data are current as of 2006.

This map reflects more detailed and up-to-date **stream channel configurations and floodplain delineations** than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables if applicable, in the FIS report. As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels; community map repository addresses; and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.


Contact **FEMA Map Service Center (MSC)** via the FEMA Map Information eXchange (FIMIX) 1-877-336-2627 for information on available products associated with this FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-358-9620 and its website at <http://www.msc.fema.gov/>.

If you have **questions about this map** or questions concerning the National Flood Insurance Program in general, please call 1-877-FEMA MAP (1-877-336-2627) or visit the FEMA website at <http://www.fema.gov/business/nfp>.


El Paso County Vertical Datum Offset Table

Flooding Source	Vertical Datum Offset (ft)
REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM BY STREAM VERTICAL DATUM CONVERSION INFORMATION	


Panel Location Map



This Digital Flood Insurance Rate Map (DFIRM) was produced through a Cooperating Technical Partner (CTP) agreement between the State of Colorado Water Conservation Board (CWCB) and the Federal Emergency Management Agency (FEMA).



Additional Flood Hazard information and resources are available from local communities and the Colorado Water Conservation Board.



LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equalled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

- ZONE A** No Base Flood Elevations determined.
- ZONE AE** Base Flood Elevations determined.
- ZONE AH** Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.
- ZONE AO** Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
- ZONE AR** Special Flood Hazard Area Formerly protected from the 1% annual chance flood by a flood control system that was subsequently decreedified. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.
- ZONE A99** Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
- ZONE V** Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.
- ZONE VE** Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.

FLOODWAY AREAS IN ZONE AE

The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.

OTHER FLOOD AREAS

ZONE X Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot, or with drainage areas less than 1 square mile, and areas protected by levees from 1% annual chance flood.

OTHER AREAS

ZONE X Areas determined to be outside the 0.2% annual chance floodplain.

ZONE D Areas in which flood hazards are undetermined, but possible.

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS

OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

- Floodplain boundary
- Floodway boundary
- Zone D Boundary
- CBRS and OPA boundary

Boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths or flood velocities.

513 Base Flood Elevation line and value; elevation in feet* (EL 987)

Base Flood Elevation value where uniform within zone; elevation in feet* (EL 987)

* Referenced to the North American Vertical Datum of 1988 (NAVD 88)

A-A Cross section line

23-23 Transsect line

97° 07' 30.00" Geographic coordinates referenced to the North American Datum of 1983 (NAD 83)

4750000N 1000-meter Universal Transverse Mercator grid ticks, zone 13

6000000 FT 5000-foot grid ticks: Colorado State Plane coordinate system, central zone (FIPSZONE 0902), Lambert Conformal Conic Projection

DX5510 Bench mark (see explanation in Notes to Users section of this FIRM panel)

M1.5 River Mile

MAP REPOSITORIES Refer to Map Repositories list on Map Index

EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP MARCH 17, 1997

EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL DECEMBER 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

For community map revision history prior to countywide mapping, refer to the Community Map History Table located in the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

MAP SCALE 1" = 500'

250 0 500 1000 FEET

150 0 150 300 METERS

NFP

PANEL 0751G

FIRM

FLOOD INSURANCE RATE MAP

EL PASO COUNTY, COLORADO AND INCORPORATED AREAS

PANEL 751 OF 1300

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:





COMMUNITY	NUMBER	PANEL	SUFFIX
COLORADO SPRINGS, CITY OF	08060	0751	G
EL PASO COUNTY	08059	0751	G

Notice to User: The Map Number shown below should be used when placing map orders. The Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER 08041C0751G

MAP REVISED DECEMBER 7, 2018

Federal Emergency Management Agency




100-YEAR FLOOD MAP
 SOLACE APARTMENTS
 JOB NO. 25174.00
 6/25/20
 SHEET 1 OF 1


J-R ENGINEERING
 A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

SOLACE PROPOSED CHANNEL PROFILE



CHANNEL PROFILE
STA 1+50.00 TO 16+92.59



PROPOSED CHANNEL PROFILE
SOLACE
JOB NO. 25174.00
6/29/20
SHEET 1 OF 1



APPENDIX B

HYDRAULIC CALCULATIONS

Sand Creek Center Tributary Upstream of Gally Road.txt

EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.012)

Element Count

 Number of rain gages 1
 Number of subcatchments ... 1
 Number of nodes 1
 Number of links 0
 Number of pollutants 0
 Number of land uses 0

Raingage Summary

Name	Data Source	Data Type	Recording Interval
100Year	100YR_24_Hour_Type_2	CUMULATIVE	15 min.

Subcatchment Summary

Name	Area	Width	%Imperv	%Slope	Rain Gage
EX_SandCreekCenter SCCT	486.00	14000.00	2.00	2.0000	100Year

Node Summary

Name	Type	Invert Elev.	Max. Depth	Ponded Area	External Inflow
SCCT	OUTFALL	0.00	0.00	0.0	

 NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.

Analysis Options

Flow Units CFS
 Process Models:
 Rainfall/Runoff YES
 RDI NO
 Snowmelt NO
 Groundwater NO
 Flow Routing NO

Sand Creek Center Tributary Upstream of Gally Road.txt

Water Quality NO
 Infiltration Method HORTON
 Starting Date 04/11/2019 00: 00: 00
 Ending Date 04/12/2019 00: 00: 00
 Antecedent Dry Days 0.0
 Report Time Step 00: 01: 00
 Wet Time Step 00: 05: 00
 Dry Time Step 01: 00: 00

 Control Actions Taken

*****	Vol ume	Depth
Runoff Quanti ty Conti nui ty	acre-feet	i nches
*****	-----	-----
Total Preci pi tati on	211. 410	5. 220
Evaporati on Loss	0. 000	0. 000
Infi ltrati on Loss	169. 021	4. 173
Surface Runoff	42. 648	1. 053
Fi nal Storage	0. 065	0. 002
Conti nui ty Error (%)	-0. 153	

*****	Vol ume	Vol ume
Flow Routi ng Conti nui ty	acre-feet	10^6 gal
*****	-----	-----
Dry Weather Inflow	0. 000	0. 000
Wet Weather Inflow	42. 646	13. 897
Groundwater Inflow	0. 000	0. 000
RDII Inflow	0. 000	0. 000
External Inflow	0. 000	0. 000
External Outflow	42. 646	13. 897
Floodi ng Loss	0. 000	0. 000
Evaporati on Loss	0. 000	0. 000
Exfi ltrati on Loss	0. 000	0. 000
Ini ti al Stored Vol ume	0. 000	0. 000
Fi nal Stored Vol ume	0. 000	0. 000
Conti nui ty Error (%)	0. 000	

 Subcatchment Runoff Summary

-----			-----					
Total	Peak	Runoff	Total	Total	Total	Total	Total	
Runoff	Runoff	Coeff	Preci p	Runon	Evap	Infi l	Runoff	
Subcatchment	Subcatchment	CFS	i n	i n	i n	i n	i n	
10^6 gal	10^6 gal							
-----			-----					
EX_SandCreekCenter	13. 90	956. 31	0. 202	5. 22	0. 00	0. 00	4. 17	1. 05

Sand Creek Center Tributary Upstream of Gally Road.txt
Analysis begun on: Wed Oct 09 08:37:59 2019
Analysis ended on: Wed Oct 09 08:37:59 2019
Total elapsed time: < 1 sec

L	Asmall	Am	A	Z	Am/A	Z	Am/A
	9900	137.26	349.17	486.43	0.717822		


W L+2L(1-Z)
15487.13

W = A/L
2140.292

Area in SQ MI
0.760047

SOLACE APARTMENTS

BASIN DELINEATION MAP



*NOTE: BASIN SHOWN ON MAP IS BASED USGS MAP CONTOURS

BASIN DELINEATION MAP
SOLACE APARTMENTS
JOB NO. 25174.00
5/1/20
SHEET 1 OF 1

J-R ENGINEERING
A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com

X:\251006\ar2517400\Drawings\Working\Digital\Basin Delineation.dwg, 24x36 Title Portal, 5/1/2020 11:27:26 AM, mmm

HEC-RAS Plan: Default Scenario River: Channel 01 Reach: CH01 Profile: Sand Creek

Reach	River Sta	Profile	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
CH01	1053	Sand Creek	760.00	6265.00	6269.27	6269.27	6269.74	0.003352	7.27	265.89	243.35	0.71
CH01	1052	Sand Creek	760.00	6258.01	6263.76	6262.24	6264.43	0.001753	6.61	120.58	30.96	0.54
CH01	1051	Sand Creek	760.00	6258.57	6262.80	6262.80	6264.31	0.006159	9.87	79.48	28.51	0.97
CH01	1050	Sand Creek	760.00	6257.06	6261.64	6261.64	6263.15	0.006075	9.92	79.79	28.39	0.97
CH01	1049	Sand Creek	760.00	6257.00	6260.98	6260.98	6262.54	0.005893	10.13	80.82	29.13	0.96
CH01	1048	Sand Creek	760.00	6255.13	6259.57	6259.57	6261.19	0.006100	10.29	78.56	27.47	0.98
CH01	1047	Sand Creek	760.00	6254.02	6258.35	6258.35	6259.87	0.006418	9.92	79.03	28.83	0.99
CH01	1046	Sand Creek	760.00	6253.47	6257.37	6257.37	6258.82	0.006297	9.71	81.92	31.36	0.99
CH01	1045	Sand Creek	760.00	6253.08	6257.17	6256.95	6258.41	0.004864	9.10	92.60	33.75	0.88
CH01	1044	Sand Creek	760.00	6252.01	6257.49		6258.08	0.001547	6.27	134.04	36.72	0.52
CH01	1043	Sand Creek	760.00	6252.00	6257.64		6257.98	0.000808	4.90	186.27	47.17	0.39
CH01	1042	Sand Creek	760.00	6251.48	6257.77		6257.90	0.000275	2.98	296.45	70.08	0.23
CH01	1041	Sand Creek	760.00	6251.03	6257.64	6254.94	6257.87	0.000520	4.00	217.80	52.54	0.31
CH01	1040	Sand Creek	760.00	6250.92	6255.95	6255.83	6257.69	0.004945	10.93	83.66	25.94	0.91
CH01	1039	Sand Creek	720.00	6250.29	6255.93	6255.93	6257.59	0.006615	10.37	71.60	22.59	0.97
CH01	1038	Sand Creek	720.00	6250.04	6254.73	6254.73	6256.41	0.006208	10.49	72.40	24.16	0.97
CH01	1037	Sand Creek	720.00	6249.57	6254.27	6254.27	6255.96	0.006002	10.56	73.73	25.26	0.97
CH01	1036	Sand Creek	720.00	6249.00	6254.22	6253.79	6255.45	0.004264	8.97	84.73	27.81	0.82
CH01	1035	Sand Creek	720.00	6248.01	6254.30		6255.24	0.002270	8.27	115.22	32.52	0.64
CH01	1034	Sand Creek	720.00	6248.55	6254.06	6253.35	6255.13	0.003139	8.41	94.27	28.00	0.72
CH01	1033	Sand Creek	720.00	6248.00	6254.06	6253.17	6255.07	0.002681	8.30	101.17	28.79	0.68
CH01	1032	Sand Creek	720.00	6248.02	6254.07	6252.89	6254.98	0.002246	7.82	105.15	28.34	0.62
CH01	1031	Sand Creek	720.00	6247.75	6253.21	6253.03	6254.83	0.004594	10.51	81.57	25.53	0.88
CH01	1030	Sand Creek	960.00	6247.20	6253.81		6254.47	0.001427	6.84	180.29	47.17	0.52
CH01	1029	Sand Creek	960.00	6247.03	6253.83		6254.41	0.001218	6.38	186.11	44.77	0.47
CH01	1028	Sand Creek	960.00	6247.00	6253.68	6251.90	6254.37	0.001399	7.18	182.94	43.84	0.52
CH01	1027	Sand Creek	960.00	6247.00	6253.74		6254.26	0.001014	6.19	205.14	47.04	0.44
CH01	1026	Sand Creek	960.00	6247.00	6253.72		6254.23	0.000999	6.00	201.50	47.61	0.44
CH01	1025	Sand Creek	960.00	6246.34	6253.81	6250.86	6254.16	0.000613	4.87	233.22	49.08	0.35
CH01	1024	Sand Creek	960.00	6246.08	6253.75	6250.63	6254.13	0.000641	5.26	233.70	47.83	0.36
CH01	1023	Sand Creek	960.00	6246.00	6253.64	6250.84	6254.12	0.000802	6.01	222.99	45.25	0.40
CH01	1022	Sand Creek	960.00	6246.00	6253.57	6250.86	6254.09	0.000873	6.35	214.27	43.66	0.43
CH01	1021	Sand Creek	960.00	6246.00	6253.05	6251.51	6254.01	0.001852	8.56	157.25	36.51	0.60
CH01	1020	Sand Creek	960.00	6246.31	6252.64	6251.77	6253.93	0.002822	9.48	124.92	32.42	0.71
CH01	1019	Sand Creek	960.00	6246.00	6252.58	6251.68	6253.84	0.002565	9.77	141.40	37.00	0.70
CH01	1018	Sand Creek	960.00	6246.00	6251.70	6251.70	6253.67	0.004727	12.34	114.00	32.74	0.94
CH01	1017	Sand Creek	960.00	6245.00	6251.54	6250.92	6253.01	0.003198	10.75	133.43	34.94	0.78
CH01	1016	Sand Creek	960.00	6245.16	6250.82	6250.82	6252.82	0.004651	12.35	113.17	33.47	0.94
CH01	1015	Sand Creek	960.00	6244.00	6250.31	6248.73	6250.93	0.001456	7.15	204.38	54.06	0.53
CH01	1014	Sand Creek	956.00	6244.00	6249.48	6248.90	6250.77	0.003430	9.39	125.21	44.69	0.77
CH01	1013	Sand Creek	956.00	6243.52	6249.67	6249.02	6250.61	0.002495	8.55	225.00	190.16	0.67
CH01	1012	Sand Creek	956.00	6243.06	6249.77	6249.77	6250.51	0.002086	8.10	273.64	192.41	0.61
CH01	1011	Sand Creek	956.00	6244.00	6249.40	6249.40	6250.19	0.002397	8.18	250.87	177.33	0.66
CH01	1010	Sand Creek	956.00	6243.67	6249.23	6249.23	6250.00	0.002552	8.18	248.04	170.75	0.66
CH01	1009	Sand Creek	956.00	6242.38	6248.82	6248.82	6249.72	0.002216	8.61	231.69	158.88	0.64
CH01	1008	Sand Creek	956.00	6242.45	6248.42	6247.88	6249.21	0.002504	7.88	225.97	155.89	0.65
CH01	1007	Sand Creek	956.00	6242.01	6248.61	6247.35	6249.05	0.001237	6.36	323.08	166.15	0.47
CH01	1006	Sand Creek	956.00	6242.18	6248.59	6247.48	6249.02	0.001286	6.16	312.53	159.55	0.48
CH01	1005	Sand Creek	956.00	6242.27	6248.58	6246.87	6249.01	0.001029	6.07	322.55	166.37	0.44
CH01	1004	Sand Creek	956.00	6242.00	6248.59	6246.97	6248.98	0.000780	5.39	241.78	63.80	0.39
CH01	1003.56		Culvert									
CH01	1003	Sand Creek	956.00	6240.00	6244.28	6242.76	6244.81	0.000389	5.82	164.22	129.55	0.50
CH01	1002	Sand Creek	956.00	6239.84	6243.20	6243.20	6244.65	0.001748	9.70	102.54	39.52	1.00
CH01	1001	Sand Creek	956.00	6239.00	6242.73	6242.73	6244.20	0.001723	9.74	99.35	35.44	0.99
CH01	1000	Sand Creek	956.00	6239.00	6242.59	6242.59	6244.00	0.001866	9.51	100.49	36.12	1.01

Sol ace (v2). rep

HEC-RAS Versi on 4. 1. 0 Jan 2010
U. S. Army Corps of Engi neers
Hydrol ogi c Engi neeri ng Center
609 Second Street
Davi s, Cal i forni a

```
X      X  XXXXXX      XXXX      XXXX      XX      XXXX
X      X  X          X      X      X      X      X
X      X  X          X          X      X      X      X
XXXXXXXX XXXX      X          XXX XXXX      XXXXXX      XXXX
X      X  X          X          X      X      X      X
X      X  X          X      X      X      X      X
X      X  XXXXXX      XXXX      X      X      X      XXXXX
```

PROJECT DATA

Project Title: HEC-RAS Model
Project File : Sol ace (v2). prj
Run Date and Time: 6/24/2020 12: 11: 02 PM

Project in English units

Project Description:

CRS Info=<Spatial Reference> <CoordinateSystem Code="WGS84_Mercator"
Unit="Foot" AcadCode="" /> <Registration OffsetX="0" OffsetY="0" OffsetZ="0"
ScaleX="1" ScaleY="1" ScaleZ="1" /></Spatial Reference>

PLAN DATA

Plan Title: Default Scenario
Plan File : X:\2510000. al I\2517400\Drawings\Working Dwgs\JaredP\Sol ace (v2). p01

Geometry Title: Default Geometry
Geometry File : X:\2510000. al I\2517400\Drawings\Working
Dwgs\JaredP\Sol ace (v2). g01

Flow Title : Default Steady Flow
Flow File : X:\2510000. al I\2517400\Drawings\Working
Dwgs\JaredP\Sol ace (v2). f01

Plan Description:
Default Scenario

Plan Summary Information:

Number of:	Cross Sections	=	54	Multiple Openings	=	0
	Culverts	=	1	Inline Structures	=	0
	Bridges	=	0	Lateral Structures	=	0

Computational Information

Water surface calculation tolerance	=	0.01
Critical depth calculation tolerance	=	0.01
Maximum number of iterations	=	20
Maximum difference tolerance	=	0.33
Flow tolerance factor	=	0.001

Sol ace (v2). rep

Computati on Opti ons

Critical depth computed only where necessary
 Conveyance Calculation Method: At breaks in n values only
 Friction Slope Method: Average Conveyance
 Computational Flow Regime: Subcritical Flow

FLOW DATA

Flow Title: Default Steady Flow
 Flow File : X:\2510000.al\2517400\Drawings\Working Dwg\JaredP\Sol ace (v2). f01

Flow Data (cfs)

River	Reach	RS	Sand Creek
Channel 01	CH01	1053	760
Channel 01	CH01	1039	720
Channel 01	CH01	1030	960
Channel 01	CH01	1014	956

Boundary Condi ti ons

River	Reach	Profile	Upstream
Downstream			
Channel 01 Critical	CH01	Sand Creek	Normal S = 0.058173

GEOMETRY DATA

Geometry Title: Default Geometry
 Geometry File : X:\2510000.al\2517400\Drawings\Working Dwg\JaredP\Sol ace (v2). g01

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1053

INPUT

Description:

Stati on Elevati on Data		num=		57							
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6274.93	3.52	6274.77	4.34	6274.63	9.51	6274	51.86	6274		
57.46	6273.99	57.8	6273.98	63.45	6273.71	63.74	6273.7	69.45	6273.43		
69.68	6273.42	75.44	6273.15	75.62	6273.14	81.43	6272.58	81.56	6272.54		
87.43	6270.58	87.5	6270.54	93.42	6267.55	95.54	6266.64	99.38	6265.01		
99.41	6265	100.62	6265.11	105.32	6265.55	105.41	6265.56	111.26	6267.58		
111.4	6267.64	117.2	6267.66	117.39	6267.68	123.14	6267.72	123.39	6267.72		
129.08	6267.75	129.38	6267.75	135.02	6267.77	135.37	6267.77	140.96	6267.81		
141.37	6267.81	146.9	6267.99	147.36	6268	219.28	6268	224.58	6268.05		
225.27	6268.05	230.56	6268.1	231.26	6268.1	236.53	6268	242.51	6268		
243.25	6268.03	248.48	6268.44	249.24	6268.52	254.46	6268.98	255.24	6268.99		
260.43	6268.99	261.23	6269	300	6269	327.15	6269	332.14	6269.11		

333. 15 6269. 16 334. 77 6270

Manni ng' s n Val ues num= 3
 Sta n Val Sta n Val Sta n Val
 0 .05 93. 42 .025 111. 4 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 93. 42 111. 4 61. 75 61. 75 61. 75 . 1 . 3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6269. 74	El ement	Left OB	Channel
Right OB				
Vel Head (ft)	0. 47	Wt. n-Val .	0. 050	0. 025
0. 050				
W. S. El ev (ft)	6269. 27	Reach Len. (ft)	61. 75	61. 75
61. 75				
Crit W. S. (ft)	6269. 27	Flow Area (sq ft)	2. 93	57. 96
205. 00				
E. G. Slope (ft/ft)	0. 003352	Area (sq ft)	2. 93	57. 96
205. 00				
Q Total (cfs)	760. 00	Flow (cfs)	4. 23	421. 31
334. 46				
Top Width (ft)	243. 35	Top Width (ft)	3. 41	17. 98
221. 96				
Vel Total (ft/s)	2. 86	Avg. Vel. (ft/s)	1. 44	7. 27
1. 63				
Max Chl Dpth (ft)	4. 27	Hydr. Depth (ft)	0. 86	3. 22
0. 92				
Conv. Total (cfs)	13126. 5	Conv. (cfs)	73. 0	7276. 8
5776. 7				
Length Wtd. (ft)	61. 75	Wetted Per. (ft)	3. 82	18. 88
222. 04				
Min Ch El (ft)	6265. 00	Shear (lb/sq ft)	0. 16	0. 64
0. 19				
Al pha	3. 73	Stream Power (lb/ft s)	334. 77	0. 00
0. 00				
Frctn Loss (ft)	0. 15	Cum Volume (acre-ft)	0. 72	4. 57
1. 23				
C & E Loss (ft)	0. 02	Cum SA (acres)	0. 34	1. 09
1. 04				

Warning: The energy equati on coul d not be balanced wi thi n the speci fi ed number of i terations. The program used cri tical depth

for the water surface and conti nued on wi th the cal culati ons.

Warning: The energy loss was greater than 1. 0 ft (0. 3 m). between the current and previ ous cross secti on. Thi s may indi cate the need for addi ti onal cross secti ons.

Warning: During the standard step i terations, when the assumed water surface was set equal to cri tical depth, the cal culated water surface came back below cri tical depth. Thi s indi cates that there i s not a val id subcri tical answer. The program default ed to cri tical depth.

CROSS SECTI ON

RIVER: Channel 01
 REACH: CH01

RS: 1052

Sol ace (v2). rep

INPUT

Descripti on:

Stati on El evati on Data		num= 65		Sta El ev		Sta El ev		Sta El ev	
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6272.77	1.79	6272.78	7.03	6272.96	7.88	6272.98	11.66	6273.13
13.98	6273.23	14.5	6273.25	20.07	6273.4	21.98	6273.37	26.17	6273.4
29.45	6273.19	32.26	6273.03	36.92	6272.91	38.36	6272.86	44.39	6272.78
44.71	6272.78	50.54	6272.83	51.86	6272.84	56.64	6272.88	59.34	6272.89
62.73	6272.67	66.81	6272.76	68.83	6272.82	74.28	6272.93	74.92	6272.94
77.76	6271.3	81.02	6269.29	81.75	6268.8	87.11	6265.25	89.22	6263.84
93.2	6261.2	96.7	6259.48	99.3	6258.01	105.39	6258.01	110.81	6258.49
111.49	6258.55	111.64	6258.66	117.58	6262.29	119.11	6263.14	123.67	6265.5
126.58	6265.61	129.77	6265.94	134.06	6266.09	135.86	6266.16	141.53	6266.28
141.96	6266.29	143.86	6266.32	148.05	6266.4	149	6266.41	154.15	6266.54
156.47	6266.59	160.24	6266.64	163.94	6266.69	166.33	6266.72	171.42	6266.75
172.43	6266.76	176.9	6266.78	178.52	6266.79	178.89	6266.79	184.62	6266.8
186.36	6266.81	190.71	6266.84	193.83	6266.88	196.8	6266.92	200	6266.94

Manni ng' s n Val ues		num= 3		Sta n Val	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	93.2	.025	117.58	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	93.2	117.58		14	14		.1	.3
Left Levee		Stati on=	75.59	El evati on=	6273			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	El ev (ft)		Element	Left OB	Channel
Right OB		6264.43			
Vel Head (ft)		0.67	Wt. n-Val.	0.050	0.025
0.050					
W. S. El ev (ft)		6263.76	Reach Len. (ft)	14.00	14.00
14.00					
Crit W. S. (ft)		6262.24	Flow Area (sq ft)	4.93	113.69
1.96					
E. G. Slope (ft/ft)		0.001753	Area (sq ft)	4.93	113.69
1.96					
Q Total (cfs)		760.00	Flow (cfs)	6.40	751.79
1.80					
Top Width (ft)		30.96	Top Width (ft)	3.86	24.38
2.72					
Vel Total (ft/s)		6.30	Avg. Vel. (ft/s)	1.30	6.61
0.92					
Max Chl Dpth (ft)		5.75	Hydr. Depth (ft)	1.28	4.66
0.72					
Conv. Total (cfs)		18150.7	Conv. (cfs)	152.9	17954.7
43.1					
Length Wtd. (ft)		14.00	Wetted Per. (ft)	4.63	26.25
3.09					
Min Ch El (ft)		6258.01	Shear (lb/sq ft)	0.12	0.47
0.07					
Alpha		1.09	Stream Power (lb/ft s)	200.00	75.59
0.00					
Frctn Loss (ft)		0.04	Cum Volume (acre-ft)	0.71	4.45
1.08					
C & E Loss (ft)		0.08	Cum SA (acres)	0.34	1.06
0.88					

Warni ng: The veloci ty head has changed by more than 0.5 ft (0.15 m). Thi s may

indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Channel 01
REACH: CH01

RS: 1051

INPUT

Description:

Station		Elevation		Data		num=		67	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6271.8	3.85	6271.83	4.58	6271.83	7.13	6271.85	10.72	6271.9
11.76	6271.91	16.86	6271.95	19.66	6271.97	23	6271.98	27.57	6272.01
29.14	6272	34.61	6271.97	35.48	6271.97	41.43	6271.9	43.39	6271.9
47.57	6271.84	51.29	6271.79	53.71	6271.76	59.2	6271.67	59.85	6271.66
62.1	6271.54	65.99	6271.35	67.11	6271.31	72.13	6271.03	75.02	6269.56
78.27	6268.15	82.93	6265.69	84.41	6264.95	89.58	6262.25	90.55	6261.76
90.83	6261.61	96.69	6258.77	98.74	6258.71	100.04	6258.66	102.84	6258.57
106.65	6259.13	108.98	6259.48	114.56	6261.6	115.12	6261.77	117.07	6262.82
121.26	6265.02	122.46	6265.08	127.4	6265.33	130.37	6265.49	133.54	6265.63
138.28	6265.83	139.68	6265.88	144.55	6265.99	145.82	6266.02	146.19	6266.03
151.96	6266.17	154.09	6266.21	158.1	6266.28	162	6266.32	164.24	6266.34
169.91	6266.38	170.39	6266.38	172.04	6266.39	176.53	6266.42	177.82	6266.43
182.67	6266.45	185.73	6266.46	188.81	6266.45	193.63	6266.52	194.95	6266.54
199.52	6266.62	200	6266.63						

Manning's n Values		num=		3	
Station	n Value	Station	n Value	Station	n Value
0	.05	90.83	.025	114.56	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	90.83	114.56		16.76	16.76		.1	.3
Left Levee		Station=	71.68	Elevation=	6271			

CROSS SECTION OUTPUT Profile #Sand Creek

Right OB	E. G. Elev (ft)	6264.31	Element	Left OB	Channel
	Vel Head (ft)	1.50	Wt. n-Val.	0.050	0.025
0.050					
	W. S. Elev (ft)	6262.80	Reach Len. (ft)	16.76	16.76
16.76					
	Crit W. S. (ft)	6262.80	Flow Area (sq ft)	1.37	76.50
1.61					
	E. G. Slope (ft/ft)	0.006159	Area (sq ft)	1.37	76.50
1.61					
	Q Total (cfs)	760.00	Flow (cfs)	2.10	755.28
2.62					
	Top Width (ft)	28.51	Top Width (ft)	2.30	23.73
2.47					
	Vel Total (ft/s)	9.56	Avg. Vel. (ft/s)	1.53	9.87
1.63					
	Max Chl Dpth (ft)	4.23	Hydr. Depth (ft)	0.60	3.22
0.65					
	Conv. Total (cfs)	9683.8	Conv. (cfs)	26.7	9623.7
33.4					
	Length Wtd. (ft)	16.76	Wetted Per. (ft)	2.59	24.84
2.76					

Min Ch El (ft)	6258.57	Solace (v2).rep Shear (lb/sq ft)	0.20	1.18
0.22				
Alpha	1.06	Stream Power (lb/ft s)	200.00	71.68
0.00				
Frctn Loss (ft)	0.10	Cum Volume (acre-ft)	0.71	4.42
1.08				
C & E Loss (ft)	0.00	Cum SA (acres)	0.33	1.06
0.88				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: The energy loss was greater than 1.0 ft (0.3 m) between the current and previous cross section. This may indicate the need for additional cross sections.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1050

INPUT

Description:

Station		Elevation		Data		num=		69	
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6271.38	.84	6271.37	1.17	6271.37	6.98	6271.35	9.08	6271.36
13.12	6271.39	16.98	6271.41	19.26	6271.42	24.89	6271.35	25.4	6271.35
27.17	6271.3	31.54	6271.18	32.8	6271.13	37.68	6270.99	40.71	6270.89
43.82	6270.73	48.62	6270.46	49.96	6270.39	54.65	6270.27	56.11	6270.24
56.52	6270.23	62.25	6270.04	64.43	6269.81	68.39	6269.39	72.34	6268.37
74.53	6267.91	80.25	6264.67	80.67	6264.43	82.14	6263.63	86.81	6261.11
88.15	6260.46	92.95	6258.06	96.06	6257.48	99.09	6257.06	100.21	6257.32
103.97	6258.18	105.23	6258.37	109.62	6259.46	111.37	6259.91	111.88	6260.19
117.51	6263.67	119.78	6264.07	123.66	6264.79	127.69	6264.95	129.8	6265.11
135.6	6265.31	135.94	6265.32	137.11	6265.35	142.08	6265.47	143.51	6265.5
148.22	6265.65	151.42	6265.72	154.36	6265.76	159.32	6265.8	160.5	6265.82
164.59	6265.84	166.64	6265.85	167.23	6265.85	172.78	6265.87	175.14	6265.88
178.92	6265.9	183.05	6265.93	185.06	6265.93	190.95	6265.97	191.21	6265.97
192.08	6265.98	197.35	6266.04	198.86	6266.08	200	6266.08		

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	88.15	.025	111.37	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	88.15	111.37		45.02	45.02		.1	.3
Left Levee		Station=	37.06	Elevation=	6271.12			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6263.15	Element	Left OB	Channel
Right OB				

Sol ace (v2).rep				
Vel Head (ft)	1.52	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6261.64	Reach Len. (ft)	45.02	45.02
45.02				
Crit W. S. (ft)	6261.64	Flow Area (sq ft)	1.40	75.88
2.51				
E. G. Slope (ft/ft)	0.006075	Area (sq ft)	1.40	75.88
2.51				
Q Total (cfs)	760.00	Flow (cfs)	2.15	753.06
4.79				
Top Width (ft)	28.39	Top Width (ft)	2.32	23.22
2.85				
Vel Total (ft/s)	9.53	Avg. Vel. (ft/s)	1.53	9.92
1.91				
Max Chl Dpth (ft)	4.58	Hydr. Depth (ft)	0.60	3.27
0.88				
Conv. Total (cfs)	9750.9	Conv. (cfs)	27.6	9661.9
61.5				
Length Wtd. (ft)	45.02	Wetted Per. (ft)	2.60	24.20
3.34				
Min Ch El (ft)	6257.06	Shear (lb/sq ft)	0.20	1.19
0.28				
Alpha	1.08	Stream Power (lb/ft s)	200.00	37.06
0.00				
Frctn Loss (ft)	0.27	Cum Volume (acre-ft)	0.71	4.39
1.08				
C & E Loss (ft)	0.00	Cum SA (acres)	0.33	1.05
0.88				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1049

INPUT

Description:

Station Elevaton Data num= 66									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6270.76	1.51	6270.76	2.46	6270.74	7.56	6270.62	8.36	6270.61
13.61	6270.49	15.35	6270.47	19.66	6270.39	22.35	6270.37	25.7	6270.34
29.34	6270.25	31.75	6270.19	36.34	6270.08	37.8	6270.06	43.33	6270
43.85	6270	47.13	6269.77	49.89	6269.59	50.33	6269.55	55.94	6268.93
57.32	6268.81	61.99	6268.36	64.32	6268.18	68.04	6267.88	71.31	6267.46
74.09	6267.2	78.31	6265.61	80.13	6264.91	85.3	6262.41	86.18	6261.98
91.8	6259.26	92.23	6259.05	98.28	6257	99.29	6257.01	104.32	6257.01
106.29	6257.25	110.37	6257.36	113.28	6258.82	116.42	6260.56	120.28	6262.23
122.47	6263.12	127.27	6263.76	128.52	6263.96	134.27	6264.22	134.56	6264.24
136.47	6264.32	140.61	6264.5	141.26	6264.52	146.66	6264.59	148.26	6264.62
152.71	6264.71	155.25	6264.73	158.76	6264.75	162.24	6264.77	164.8	6264.81

Sol ace (v2).rep

169.24	6264.85	170.85	6264.86	176.9	6264.86	181.14	6264.88	182.95	6264.89
183.23	6264.89	188.99	6264.92	190.22	6264.92	195.04	6264.94	197.22	6264.95
200	6264.96								

Manning's n Values	num=	3
Sta n Val	Sta n Val	Sta n Val
0 .05	91.8	.025 113.28 .05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	91.8	113.28		32.7	32.7		.1	.3
Left Levee		Station=	45.99	Elevation=	6270.04			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6262.54	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.56	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6260.98	Reach Len. (ft)	32.70	32.70
32.70				
Crit W. S. (ft)	6260.98	Flow Area (sq ft)	3.04	73.54
4.24				
E. G. Slope (ft/ft)	0.005893	Area (sq ft)	3.04	73.54
4.24				
Q Total (cfs)	760.00	Flow (cfs)	5.84	745.06
9.10				
Top Width (ft)	29.13	Top Width (ft)	3.54	21.48
4.10				
Vel Total (ft/s)	9.40	Avg. Vel. (ft/s)	1.92	10.13
2.15				
Max Chl Dpth (ft)	3.98	Hydr. Depth (ft)	0.86	3.42
1.03				
Conv. Total (cfs)	9900.2	Conv. (cfs)	76.1	9705.6
118.6				
Length Wtd. (ft)	32.70	Wetted Per. (ft)	3.94	22.23
4.64				
Min Ch El (ft)	6257.00	Shear (lb/sq ft)	0.28	1.22
0.34				
Alpha	1.14	Stream Power (lb/ft s)	200.00	45.99
0.00				
Frctn Loss (ft)	0.20	Cum Volume (acre-ft)	0.71	4.31
1.08				
C & E Loss (ft)	0.01	Cum SA (acres)	0.33	1.02
0.87				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

Sol ace (v2). rep

RIVER: Channel 01
 REACH: CH01

RS: 1048

INPUT

Description:

Station		Elevation		Data		num= 68		Station		Elevation		Station		Elevation	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6269.99	1.6	6269.99	2.45	6269.98	6.34	6269.88	8.54	6269.83						
9.03	6269.81	14.64	6269.65	16.47	6269.6	20.73	6269.49	23.91	6269.51						
26.82	6269.45	31.34	6269.52	32.91	6269.53	38.78	6269.5	39.99	6269.5						
45.09	6269.46	46.22	6269.37	51.18	6269.06	53.65	6268.77	57.27	6268.26						
61.09	6267.88	63.36	6267.63	68.53	6267.25	69.45	6267.2	73.63	6266.59						
75.54	6266.29	75.96	6266.07	81.63	6263.23	83.4	6262.19	87.72	6259.65						
90.84	6258.01	93.81	6256.38	98.27	6255.51	99.9	6255.13	100.12	6255.16						
105.71	6255.87	105.99	6255.89	107.28	6256.2	112.08	6257.37	113.15	6258.09						
118.17	6261.47	120.58	6262.03	124.27	6263.16	128.02	6263.37	130.36	6263.48						
135.46	6263.71	136.45	6263.76	140.92	6263.95	142.54	6264.01	142.89	6264.02						
148.63	6264.11	150.33	6264.14	154.72	6264.2	157.77	6264.22	160.81	6264.25						
165.2	6264.27	166.9	6264.27	172.64	6264.28	172.99	6264.28	174.57	6264.27						
179.08	6264.24	180.08	6264.23	185.17	6264.2	187.51	6264.22	191.26	6264.24						
194.95	6264.29	197.35	6264.34	200	6264.41										

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.05	90.84	.025
		112.08	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	90.84	112.08		22.36	22.36		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

	E. G. Elev (ft)		Element	Left OB	Channel
Right OB		6261.19			
Vel Head (ft)		1.62	Wt. n-Val.	0.050	0.025
0.050					
W. S. Elev (ft)		6259.57	Reach Len. (ft)	22.36	22.36
22.36					
Crit W. S. (ft)		6259.57	Flow Area (sq ft)	2.31	72.67
3.59					
E. G. Slope (ft/ft)		0.006100	Area (sq ft)	2.31	72.67
3.59					
Q Total (cfs)		760.00	Flow (cfs)	4.18	748.00
7.82					
Top Width (ft)		27.47	Top Width (ft)	2.96	21.24
3.26					
Vel Total (ft/s)		9.67	Avg. Vel. (ft/s)	1.81	10.29
2.18					
Max Chl Dpth (ft)		4.44	Hydr. Depth (ft)	0.78	3.42
1.10					
Conv. Total (cfs)		9731.0	Conv. (cfs)	53.5	9577.4
100.2					
Length Wtd. (ft)		22.36	Wetted Per. (ft)	3.35	22.01
3.93					
Min Ch El (ft)		6255.13	Shear (lb/sq ft)	0.26	1.26
0.35					
Alpha		1.11	Stream Power (lb/ft s)	200.00	0.00
0.00					
Frctn Loss (ft)		0.14	Cum Volume (acre-ft)	0.70	4.26
1.08					
C & E Loss (ft)		0.03	Cum SA (acres)	0.33	1.01
0.87					

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1047

INPUT

Description:

Station Elevation Data num= 66

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6269.49	4.5	6269.39	6.54	6269.36	10.59	6269.28	13.98	6269.2
16.68	6269.15	21.42	6269.01	22.77	6268.97	28.85	6268.76	28.89	6268.76
34.95	6268.55	36.29	6268.49	41.04	6268.28	43.73	6268.14	47.13	6268
51.16	6267.58	53.22	6267.38	58.6	6267.05	59.31	6267	65.4	6267
66.04	6266.93	71.49	6266.25	73.47	6265.27	77.59	6263.24	80.91	6261.41
83.68	6260.06	88.35	6258.05	89.77	6257.44	95.78	6254.86	95.86	6254.82
96.18	6254.78	100.01	6254.27	101.95	6254.02	103.22	6254.25	108.04	6254.87
110.66	6255.9	114.13	6256.68	118.1	6259.52	120.22	6261.66	125.53	6262.2
126.31	6262.27	129.83	6262.66	132.4	6262.98	132.97	6263	138.49	6263.25
140.41	6263.31	144.58	6263.47	147.84	6263.54	150.67	6263.59	155.28	6263.66
156.76	6263.69	162.72	6263.77	163.48	6263.77	168.94	6263.82	170.15	6263.82
175.03	6263.85	177.59	6263.87	181.12	6263.89	185.03	6263.91	187.22	6263.93
192.46	6263.97	193.31	6263.98	197.12	6264.03	199.4	6264.07	199.9	6264.08
200	6264.08								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.05	89.77	.025	114.13	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	89.77	114.13		23.82	23.82		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

	E. G. Elev (ft)		Element	Left OB	Channel
Right OB		6259.87			
Vel Head (ft)		1.52	Wt. n-Val.	0.050	0.025
0.050					
W. S. Elev (ft)		6258.35	Reach Len. (ft)	23.82	23.82
23.82					
Crit W. S. (ft)		6258.35	Flow Area (sq ft)	0.97	76.09
1.96					
E. G. Slope (ft/ft)		0.006418	Area (sq ft)	0.97	76.09
1.96					
Q Total (cfs)		760.00	Flow (cfs)	1.30	755.09
3.61					
Top Width (ft)		28.83	Top Width (ft)	2.13	24.36
2.34					

		Solace (v2).rep		
Vel Total (ft/s)	9.62	Avg. Vel. (ft/s)	1.34	9.92
1.84				
Max Chl Dpth (ft)	4.33	Hydr. Depth (ft)	0.46	3.12
0.84				
Conv. Total (cfs)	9486.4	Conv. (cfs)	16.2	9425.1
45.1				
Length Wtd. (ft)	23.82	Wetted Per. (ft)	2.32	25.29
2.88				
Min Ch El (ft)	6254.02	Shear (lb/sq ft)	0.17	1.21
0.27				
Alpha	1.06	Stream Power (lb/ft s)	200.00	0.00
0.00				
Frctn Loss (ft)	0.15	Cum Volume (acre-ft)	0.70	4.22
1.07				
C & E Loss (ft)	0.02	Cum SA (acres)	0.33	1.00
0.87				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth

for the water surface and continued on with the calculations.

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1046

INPUT

Description:

Station	Elevation	Data	num=	69					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6269.33	1.41	6269.3	5.98	6269.19	7.42	6269.16	11.97	6269.05
13.42	6269	17.96	6268.87	19.43	6268.82	23.96	6268.68	25.44	6268.62
29.95	6268.47	31.44	6268.42	35.94	6268.26	37.45	6268.21	41.94	6268.05
43.45	6267.98	47.93	6267.93	49.46	6267.84	53.92	6267.63	55.46	6267.54
59.92	6267.25	61.47	6266.99	65.91	6265.88	67.47	6265.06	71.9	6262.54
73.48	6261.63	77.9	6259.05	79.48	6258.28	83.89	6255.95	85.49	6255.46
89.88	6254.52	91.49	6254.26	95.87	6253.71	97.5	6253.74	100	6253.59
101.87	6253.47	103.5	6253.74	107.86	6255.14	109.51	6255.64	113.85	6258.11
115.52	6258.58	119.85	6259.88	121.52	6260.72	125.84	6261.8	127.53	6262.06
131.83	6262.23	133.53	6262.31	137.83	6262.5	139.54	6262.58	143.82	6262.77
145.54	6262.82	149.81	6263	155.81	6263	157.55	6263.01	161.8	6263.01
163.56	6263.04	167.79	6263.06	169.56	6263.09	173.79	6263.12	175.57	6263.13
179.78	6263.14	181.57	6263.15	185.77	6263.17	187.58	6263.17	191.77	6263.2
193.58	6263.23	197.76	6263.29	199.59	6263.32	200	6263.32		

Manning's n Values	num=	3			
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	83.89	.025	109.51	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	83.89	109.51		24.71	24.71		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6258.82	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.45	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6257.37	Reach Len. (ft)	24.71	24.71
24.71				
Crit W. S. (ft)	6257.37	Flow Area (sq ft)	1.91	77.36
2.64				
E. G. Slope (ft/ft)	0.006297	Area (sq ft)	1.91	77.36
2.64				
Q Total (cfs)	760.00	Flow (cfs)	3.31	751.54
5.15				
Top Width (ft)	31.36	Top Width (ft)	2.69	25.62
3.04				
Vel Total (ft/s)	9.28	Avg. Vel. (ft/s)	1.73	9.71
1.95				
Max Chl Dpth (ft)	3.90	Hydr. Depth (ft)	0.71	3.02
0.87				
Conv. Total (cfs)	9577.6	Conv. (cfs)	41.8	9471.0
64.9				
Length Wtd. (ft)	24.71	Wetted Per. (ft)	3.05	26.17
3.50				
Min Ch El (ft)	6253.47	Shear (lb/sq ft)	0.25	1.16
0.30				
Alpha	1.08	Stream Power (lb/ft s)	200.00	0.00
0.00				
Frctn Loss (ft)	0.14	Cum Volume (acre-ft)	0.70	4.18
1.07				
C & E Loss (ft)	0.06	Cum SA (acres)	0.33	0.98
0.87				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1045

INPUT

Description:

Station	Elevation	Data	num=	74	Station	Elevation	Data	num=	74
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6269.16	.01	6269.16	4.13	6269.06	5.71	6269.03	5.8	6269.02
11.41	6268.89	11.8	6268.88	17.11	6268.74	17.8	6268.72	22.82	6268.58
23.8	6268.56	28.52	6268.43	29.8	6268.4	34.22	6268.28	35.8	6268.24
39.92	6268.11	41.81	6268.06	45.62	6268.02	47.81	6267.97	51.32	6267.77
53.81	6267.59	57.02	6267.4	59.81	6267.25	62.72	6266.25	65.81	6265.3
68.42	6263.7	71.81	6261.62	74.12	6260.26	77.81	6257.99	79.82	6256.95
83.82	6254.91	85.52	6254.75	89.82	6254.37	91.22	6254.21	95.82	6253.63
96.92	6253.55	99.94	6253.26	101.82	6253.08	102.63	6253.21	107.82	6253.9

Solace (v2).rep									
108.33	6254.21	113.82	6257.57	114.03	6257.67	117.88	6259.98	119.73	6261.1
119.82	6261.15	125.43	6261.87	125.83	6261.94	131.13	6262.18	131.83	6262.21
136.83	6262.35	137.83	6262.37	142.53	6262.45	143.83	6262.47	148.23	6262.55
149.83	6262.58	153.93	6262.58	155.83	6262.59	159.63	6262.56	161.84	6262.54
165.33	6262.53	167.84	6262.53	171.03	6262.54	173.84	6262.54	176.73	6262.55
179.84	6262.57	182.43	6262.59	185.84	6262.61	188.14	6262.63	191.84	6262.67
193.84	6262.69	197.84	6262.73	199.54	6262.75	200	6262.75		

Manning's n Values					
Station	Value	Station	Value	Station	Value
0	.05	83.82	.025	108.33	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	83.82	108.33		51.49	51.49	.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

Parameter	Value	Element	Left OB	Channel
E. G. Elev (ft)	6258.41	Element		
Right OB				
Vel Head (ft)	1.24	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6257.17	Reach Len. (ft)	51.49	51.49
51.49				
Crit W. S. (ft)	6256.95	Flow Area (sq ft)	4.98	80.49
7.13				
E. G. Slope (ft/ft)	0.004864	Area (sq ft)	4.98	80.49
7.13				
Q Total (cfs)	760.00	Flow (cfs)	10.36	732.40
17.24				
Top Width (ft)	33.75	Top Width (ft)	4.41	24.51
4.83				
Vel Total (ft/s)	8.21	Avg. Vel. (ft/s)	2.08	9.10
2.42				
Max Chl Dpth (ft)	4.08	Hydr. Depth (ft)	1.13	3.28
1.48				
Conv. Total (cfs)	10897.6	Conv. (cfs)	148.6	10501.8
247.3				
Length Wtd. (ft)	51.49	Wetted Per. (ft)	4.96	24.75
5.66				
Min Chl El (ft)	6253.08	Shear (lb/sq ft)	0.31	0.99
0.38				
Alpha	1.19	Stream Power (lb/ft s)	200.00	0.00
0.00				
Frctn Loss (ft)	0.13	Cum Volume (acre-ft)	0.70	4.13
1.07				
C & E Loss (ft)	0.20	Cum SA (acres)	0.32	0.97
0.87				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1044

Sol ace (v2). rep

INPUT

Descripti on:

Stati on		El evati on		Data		num=		57	
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6269.93	3.09	6269.7	6.14	6269.46	9.08	6269.23	9.79	6269.18
14.64	6268.87	15.58	6268.81	16.75	6268.75	22.15	6268.46	26.55	6268.22
28.72	6268.1	31.39	6267.91	35.29	6267.63	38.46	6267.4	41.86	6267.15
46.03	6266.86	48.43	6266.69	50.37	6266.54	55	6266.21	60.68	6264.56
61.56	6264.28	62.29	6263.92	68.13	6261	74.2	6257.97	74.7	6257.72
75.32	6257.41	81.27	6254.44	86.11	6253.69	87.84	6253.36	89.96	6253.05
94.41	6252.35	98.02	6252.19	99.94	6252.07	100.97	6252.01	104.61	6253.18
107.54	6254.16	109.93	6256.02	114.11	6259.17	119.25	6261.42	120.68	6262
148.53	6262	153.52	6262.02	157.58	6262.1	160.09	6262.14	163.18	6262.15
166.66	6262.16	169.49	6262.17	173.23	6262.19	177.82	6262.25	179.8	6262.27
181.4	6262.3	186.36	6262.38	192.46	6262.48	192.93	6262.49	193.31	6262.49
199.5	6262.59	200	6262.59						

Manni ng' s n		Val ues		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.05	81.27	.025	107.54	.05		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	81.27	107.54		24.27	24.27		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	El ev (ft)		6258.08	El ement		Left OB	Channel
Right OB							
Vel Head (ft)		0.59		Wt. n-Val.		0.050	0.025
0.050							
W. S. El ev (ft)		6257.49		Reach Len. (ft)		24.27	24.27
24.27							
Crit W. S. (ft)				Flow Area (sq ft)		9.31	117.56
7.16							
E. G. Slope (ft/ft)		0.001547		Area (sq ft)		9.31	117.56
7.16							
Q Total (cfs)		760.00		Flow (cfs)		13.38	736.59
10.02							
Top Width (ft)		36.72		Top Width (ft)		6.11	26.27
4.34							
Vel Total (ft/s)		5.67		Avg. Vel. (ft/s)		1.44	6.27
1.40							
Max Chl Dpth (ft)		5.48		Hydr. Depth (ft)		1.52	4.48
1.65							
Conv. Total (cfs)		19325.7		Conv. (cfs)		340.3	18730.5
254.9							
Length Wtd. (ft)		24.27		Wetted Per. (ft)		6.83	26.79
5.47							
Min Ch El (ft)		6252.01		Shear (lb/sq ft)		0.13	0.42
0.13							
Alpha		1.19		Stream Power (lb/ft s)		200.00	0.00
0.00							
Frctn Loss (ft)		0.03		Cum Volume (acre-ft)		0.69	4.02
1.06							
C & E Loss (ft)		0.07		Cum SA (acres)		0.32	0.94
0.86							

CROSS SECTION

Sol ace (v2). rep

RIVER: Channel 01
 REACH: CH01

RS: 1043

INPUT

Description:

Station		Elevation		Data		num=		57	
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6269.5	3.92	6269.19	5.6	6269.06	9.92	6268.76	11.76	6268.64
15.91	6268.38	17.92	6268.25	21.91	6267.99	24.08	6267.82	27.91	6267.52
30.24	6267.33	33.9	6267.05	36.4	6266.87	39.9	6266.6	42.56	6266.41
45.89	6266.17	48.72	6265.28	51.89	6264.35	54.88	6262.83	57.88	6261.25
61.04	6259.77	63.69	6258.51	63.89	6258.42	70.38	6255.67	70.45	6255.64
77	6253.63	82.14	6253	83.56	6252.84	85.34	6252.69	90.11	6252.25
93.9	6252.13	96.66	6252	99.88	6252.43	100.14	6252.47	103.22	6252.9
105.66	6253.71	109.77	6254.59	114.95	6259.61	116.33	6260.93	117.42	6261.01
122.88	6262	129.44	6262	129.75	6261.99	135.99	6261.93	140.94	6261.97
142.54	6261.98	144.56	6262	174.17	6262	175.31	6262.01	176.22	6262.02
181.87	6262.11	187.98	6262.22	188.42	6262.23	188.97	6262.24	194.98	6262.36
199.74	6262.46	200	6262.46						

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	77	.025	105.66	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	77	105.66		39.09	39.09		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

	E. G. El ev (ft)	6257.98	Element	Left OB	Channel
Right OB	Vel Head (ft)	0.35	Wt. n-Val.	0.050	0.025
0.050	W. S. El ev (ft)	6257.64	Reach Len. (ft)	39.09	39.09
39.09	Crit W. S. (ft)		Flow Area (sq ft)	24.34	142.82
19.11	E. G. Slope (ft/ft)	0.000808	Area (sq ft)	24.34	142.82
19.11	Q Total (cfs)	760.00	Flow (cfs)	33.01	699.46
27.52	Top Width (ft)	47.17	Top Width (ft)	11.26	28.66
7.25	Vel Total (ft/s)	4.08	Avg. Vel. (ft/s)	1.36	4.90
1.44	Max Chl Dpth (ft)	5.63	Hydr. Depth (ft)	2.16	4.98
2.63	Conv. Total (cfs)	26741.0	Conv. (cfs)	1161.6	24611.1
968.4	Length Wtd. (ft)	39.09	Wetted Per. (ft)	11.96	28.93
8.58	Min Ch El (ft)	6252.00	Shear (lb/sq ft)	0.10	0.25
0.11	Alpha	1.34	Stream Power (lb/ft s)	200.00	0.00
0.00	Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.68	3.94
1.05	C & E Loss (ft)	0.06	Cum SA (acres)	0.31	0.92
0.86					

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Channel 01
REACH: CH01

RS: 1042

INPUT

Description:

Station		Elevation		Data		num=		83	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6268.31	4.55	6268.01	5.47	6267.95	10.71	6267.55	11.46	6267.49
16.87	6267.07	17.46	6267.03	23.03	6266.61	23.45	6266.58	29.19	6266.15
29.45	6266.13	35.35	6264.41	35.44	6264.38	38.85	6262.6	41.44	6261.23
41.51	6261.2	47.33	6258.43	47.44	6258.37	47.59	6258.31	47.97	6258.14
52.23	6256.24	53.85	6255.52	56.88	6254.6	60.27	6253.63	61.53	6253.49
64.84	6253.14	66.17	6252.99	66.68	6252.94	70.82	6252.71	73.09	6252.6
75.46	6252.47	79.5	6252.31	80.11	6252.3	81.71	6252.22	84.75	6252.09
85.91	6252.05	89.4	6252.06	92.32	6251.97	94.05	6251.97	98.58	6251.49
98.69	6251.48	98.85	6251.54	103.34	6253.16	105.14	6253.77	107.98	6254.23
111.56	6255.35	112.63	6255.51	115.45	6256.35	117.27	6257.03	117.97	6257.39
121.92	6259.02	124.38	6260.13	126.57	6261.12	130.79	6261.05	131.21	6261.14
132.32	6261.12	135.86	6261.06	137.2	6261	140.5	6261.07	143.61	6261.13
145.15	6261.18	149.19	6261.31	149.8	6261.32	150.02	6261.33	154.44	6261.47
156.43	6261.53	159.09	6261.61	162.85	6261.72	163.73	6261.75	166.07	6261.79
168.38	6261.82	169.26	6261.82	173.02	6261.75	175.67	6261.69	177.67	6261.61
182.08	6261.41	182.32	6261.4	182.94	6261.37	186.96	6261.2	188.49	6261.14
191.61	6261.01	194.9	6261	200	6261				

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	60.27	.025	105.14	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	60.27	105.14		39.32	39.32		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

	E. G. Elev (ft)		Element	Left OB	Channel
Right OB		6257.90			
Vel Head (ft)	0.050	0.13	Wt. n-Val.	0.050	0.025
W. S. Elev (ft)	39.32	6257.77	Reach Len. (ft)	39.32	39.32
Crit W. S. (ft)	31.57		Flow Area (sq ft)	26.26	238.63
E. G. Slope (ft/ft)	31.57	0.000275	Area (sq ft)	26.26	238.63
Q Total (cfs)	26.31	760.00	Flow (cfs)	21.57	712.12
Top Width (ft)	13.74	70.08	Top Width (ft)	11.46	44.87
Vel Total (ft/s)	0.83	2.56	Avg. Vel. (ft/s)	0.82	2.98
Max Chl Dpth (ft)	2.30	6.29	Hydr. Depth (ft)	2.29	5.32
Conv. Total (cfs)	1585.2	45792.3	Conv. (cfs)	1299.8	42907.3
Length Wtd. (ft)		39.32	Wetted Per. (ft)	12.22	45.35

Sol ace (v2). rep

14.37	Min Ch El (ft)	6251.48	Shear (lb/sq ft)	0.04	0.09
0.04	Alpha	1.28	Stream Power (lb/ft s)	200.00	0.00
0.00	Frctn Loss (ft)	0.01	Cum Volume (acre-ft)	0.66	3.77
1.03	C & E Loss (ft)	0.01	Cum SA (acres)	0.30	0.89
0.85					

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1041

INPUT

Descripti on:

Station	Elevation	Data	num=	87	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6268.5	3.15	6268.3	3.47	6268.28	3.65	6268.27	7.85	6268			
10.57	6267.82	12.24	6267.7	15.11	6267.51	16.62	6267.41	17.5	6267.35			
21.01	6267.11	24.43	6266.87	25.39	6266.8	27.06	6266.68	29.78	6266.49			
31.35	6266.38	34.16	6266.15	38.28	6265.72	38.55	6265.66	39.02	6265.56			
42.94	6264.74	45.21	6264.49	47.32	6263.69	50.97	6262.05	51.71	6261.71			
52.13	6261.53	56.09	6259.75	59.06	6258.41	60.48	6257.77	62.93	6256.67			
64.86	6255.8	65.98	6255.3	69.25	6254.55	72.91	6253.59	73.63	6253.53			
74.88	6253.43	78.02	6253.04	79.84	6252.93	82.4	6252.73	86.76	6252.53			
91.18	6252.21	93.69	6252.08	95.56	6251.8	98.79	6251.27	99.61	6251.1			
99.95	6251.03	100.62	6251.12	104.33	6252.35	107.54	6254.17	108.72	6254.94			
110.75	6256.08	113.1	6257.51	114.47	6258.33	117.49	6260.33	121.39	6261.91			
121.87	6262	126.26	6262	128.32	6261.97	130.65	6261.88	131.9	6261.8			
134.84	6261.61	135.58	6261.55	139.63	6261.2	140.73	6261.1	140.93	6261.1			
145.89	6261.05	147.03	6261.11	151.04	6261.3	153.12	6261.44	156.2	6261.64			
159.21	6261.82	161.35	6261.91	165.3	6261.99	166.51	6261.9	171.39	6261.96			
171.66	6261.96	173.15	6261.87	176.82	6261.69	177.48	6261.68	181.97	6261.49			
183.57	6261.41	187.13	6261.49	189.66	6260.96	192.28	6260.95	195.76	6260.85			
197.43	6260.83	200	6260.79									

Manning's n	Values	num=	3
Sta	n Val	Sta	n Val
0	.05	72.91	.025
		107.54	.05

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	72.91	107.54		30.04	30.04	30.04		.1	.3
Right Levee		Station=	121.94		Elevation=	6261.95			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6257.87	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.24	Wt. n-Val.	0.050	0.025
0.050				
W. S. El ev (ft)	6257.64	Reach Len. (ft)	30.04	30.04
30.04				
Crit W. S. (ft)	6254.94	Flow Area (sq ft)	28.01	179.84
9.95				
E. G. Slope (ft/ft)	0.000520	Area (sq ft)	28.01	179.84
9.95				
Q Total (cfs)	760.00	Flow (cfs)	31.91	719.35

Sol ace (v2). rep

8.74				
Top Width (ft)	52.54	Top Width (ft)	12.13	34.63
5.77				
Vel Total (ft/s)	3.49	Avg. Vel. (ft/s)	1.14	4.00
0.88				
Max Chl Dpth (ft)	6.61	Hydr. Depth (ft)	2.31	5.19
1.72				
Conv. Total (cfs)	33334.3	Conv. (cfs)	1399.7	31551.4
383.3				
Length Wtd. (ft)	30.04	Wetted Per. (ft)	12.84	35.46
6.74				
Min Ch El (ft)	6251.03	Shear (lb/sq ft)	0.07	0.16
0.05				
Alpha	1.25	Stream Power (lb/ft s)	200.00	0.00
121.94				
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.64	3.58
1.01				
C & E Loss (ft)	0.15	Cum SA (acres)	0.29	0.85
0.84				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.
 Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1040

INPUT

Description:

Station	Elevation	Data	num=	69					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6266.5	.35	6266.5	6.36	6266.47	6.77	6266.47	12.5	6266.45
13.65	6266.45	18.58	6266.47	20.95	6266.48	24.66	6266.48	28.24	6266.49
30.73	6266.49	35.54	6266.41	36.81	6266.4	42.83	6266.23	43.14	6266.22
48.96	6266.04	50.13	6265.99	55.04	6265.78	57.42	6265.67	61.11	6265.51
64.72	6265.34	67.19	6265.24	72.01	6264.58	73.27	6264.46	79.31	6261.15
79.34	6261.13	79.5	6261.04	85.42	6257.53	86.61	6256.82	91.49	6253.87
93.9	6252.89	97.57	6250.98	100.07	6250.96	101.2	6250.96	103.65	6250.92
108.49	6252.73	109.72	6253.44	115.79	6257	115.86	6257.04	121.88	6260.17
123.08	6260.68	127.95	6261.53	130.38	6261.75	134.03	6261.89	137.67	6261.87
140.1	6261.85	142.7	6261.7	144.3	6261.61	146.19	6261.48	149.46	6261.19
152.28	6261.2	154.61	6261.18	158.37	6261.37	159.77	6261.43	164.46	6261.76
164.92	6261.79	167.44	6261.94	170.08	6262.14	170.55	6262.16	175.23	6262.3
176.65	6262.34	180.39	6262.37	182.74	6262.45	185.54	6262.31	188.83	6262.27
190.69	6262.19	194.92	6261.98	195.85	6262	200	6261.12		

Manning's n Values	num=	3	
Sta	n Val	Sta	n Val
0	.05	93.9	.025
		108.49	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	93.9	108.49		12.65	12.65		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

Sol ace (v2). rep

E. G. El ev (ft)	6257. 69	El ement	Left OB	Channel
Ri ght OB				
Vel Head (ft)	1. 74	Wt. n-Val .	0. 050	0. 025
0. 050				
W. S. El ev (ft)	6255. 95	Reach Len. (ft)	12. 65	12. 65
12. 65				
Crit W. S. (ft)	6255. 83	Fl ow Area (sq ft)	9. 76	65. 02
8. 88				
E. G. Slope (ft/ft)	0. 004945	Area (sq ft)	9. 76	65. 02
8. 88				
Q Total (cfs)	760. 00	Fl ow (cfs)	26. 41	710. 45
23. 14				
Top Width (ft)	25. 94	Top Wi dth (ft)	5. 85	14. 59
5. 51				
Vel Total (ft/s)	9. 08	Avg. Vel. (ft/s)	2. 71	10. 93
2. 61				
Max Chl Dpth (ft)	5. 03	Hydr. Depth (ft)	1. 67	4. 46
1. 61				
Conv. Total (cfs)	10807. 4	Conv. (cfs)	375. 6	10102. 8
329. 1				
Length Wtd. (ft)	12. 65	Wetted Per. (ft)	6. 62	15. 39
6. 38				
Min Ch El (ft)	6250. 92	Shear (lb/sq ft)	0. 46	1. 30
0. 43				
Alpha	1. 36	Stream Power (lb/ft s)	200. 00	0. 00
0. 00				
Frctn Loss (ft)	0. 07	Cum Volume (acre-ft)	0. 62	3. 50
1. 01				
C & E Loss (ft)	0. 02	Cum SA (acres)	0. 29	0. 84
0. 84				

CROSS SECTI ON

RIVER: Channel 01
 REACH: CH01 RS: 1039

I NPUT

Descr ipti on:

Stati on	El evati on	Data	num=	71							
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6266. 05	3. 54	6266. 03	4. 35	6266. 03	8. 41	6266. 01	10. 43	6266		
10. 83	6266	16. 5	6265. 99	22. 58	6265. 99	25. 41	6265. 98	28. 65	6265. 98		
32. 7	6265. 97	34. 73	6265. 96	39. 99	6265. 93	40. 81	6265. 93	44. 86	6265. 9		
46. 88	6265. 88	47. 29	6265. 87	52. 96	6265. 73	54. 58	6265. 66	59. 03	6265. 47		
61. 87	6265. 35	65. 11	6265. 21	69. 16	6264. 9	71. 19	6264. 72	76. 45	6262. 14		
77. 26	6261. 78	81. 32	6259. 55	83. 34	6258. 45	83. 74	6258. 22	89. 41	6255. 11		
91. 03	6254. 17	95. 49	6251. 73	98. 32	6251. 26	99. 54	6250. 9	101. 56	6250. 29		
105. 61	6252. 71	107. 64	6253. 83	112. 9	6257. 69	113. 72	6258. 29	117. 77	6260. 17		
119. 79	6261. 05	120. 2	6261. 08	125. 87	6261. 14	127. 49	6261. 16	131. 94	6261. 21		
134. 78	6261. 24	138. 02	6261. 27	142. 07	6261. 13	144. 09	6261. 11	149. 36	6261. 81		
150. 17	6261. 94	154. 23	6262. 44	156. 25	6262. 63	156. 65	6262. 64	162. 32	6262. 61		
163. 94	6262. 64	168. 4	6262. 59	171. 23	6262. 54	173	6262. 55	174. 48	6262. 55		
176. 91	6262. 57	180. 57	6262. 7	182. 06	6262. 62	186. 66	6262. 57	187. 22	6262. 54		
190. 27	6262. 39	192. 37	6262. 23	192. 75	6262. 18	197. 52	6261. 17	198. 84	6260. 88		
200	6260. 85										

Manni ng' s n Val ues	num=	3
Sta n Val	Sta n Val	Sta n Val

0 .05 91.03 .025
 Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 91.03 200 28.43 28.43 28.43 .1 .3
 Right Levee Station= 119.71 Elevation= 6261.04

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6257.59	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.66	Wt. n-Val.	0.050	0.025
W. S. Elev (ft)	6255.93	Reach Len. (ft)	28.43	28.43
28.43				
Crit W. S. (ft)	6255.93	Flow Area (sq ft)	2.71	68.90
E. G. Slope (ft/ft)	0.006615	Area (sq ft)	2.71	68.90
Q Total (cfs)	720.00	Flow (cfs)	5.42	714.58
Top Width (ft)	22.59	Top Width (ft)	3.12	19.47
Vel Total (ft/s)	10.06	Avg. Vel. (ft/s)	2.01	10.37
Max Chl Dpth (ft)	5.64	Hydr. Depth (ft)	0.87	3.54
Conv. Total (cfs)	8852.6	Conv. (cfs)	66.7	8785.9
Length Wtd. (ft)	28.43	Wetted Per. (ft)	3.58	21.92
Min Ch El (ft)	6250.29	Shear (lb/sq ft)	0.31	1.30
Alpha	1.06	Stream Power (lb/ft s)	200.00	0.00
119.71				
Frctn Loss (ft)	0.18	Cum Volume (acre-ft)	0.62	3.48
1.01				
C & E Loss (ft)	0.00	Cum SA (acres)	0.28	0.83
0.84				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
 Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.
 Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.
 Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1038

INPUT

Sol ace (v2). rep

Descripti on:

Station		Elevation		Data		num=		62	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6264.96	2.12	6264.96	2.61	6264.95	2.83	6264.95	8.88	6264.84
11.92	6264.8	15.16	6264.76	21.01	6264.77	21.43	6264.77	22.37	6264.78
27.71	6264.79	42.63	6264.79	46.53	6264.78	48.28	6264.77	52.8	6264.73
57.37	6264.59	59.08	6264.56	62.88	6264.41	65.35	6264.32	66.46	6264.17
71.63	6263.82	75.55	6261.48	77.9	6260.11	83.13	6256.98	84.17	6256.36
84.64	6256.09	90.45	6252.67	93.73	6251.34	96.72	6250.04	100.14	6250.12
102.82	6250.19	103	6250.18	103.39	6250.38	109.27	6253.6	111.91	6255.21
115.54	6257.42	121	6259.73	121.82	6260.16	123.64	6260.31	128.09	6260.68
130.09	6260.73	134.37	6260.8	139.18	6260.85	140.64	6260.86	143.9	6260.9
146.91	6260.95	148.27	6260.96	153.19	6261.01	157.36	6261.02	159.46	6261.05
164.15	6261.05	165.74	6261.11	166.45	6261.16	172.01	6261.45	175.54	6261.7
178.29	6261.87	184.4	6261.85	184.56	6261.85	190.83	6261.4	193.72	6260.95
197.11	6260.75	200	6260.67						

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	90.45	.025	109.27	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	90.45	109.27		26.37	26.37		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

	E. G. Elev (ft)		Element	Left OB	Channel
Right OB		6256.41			
Vel Head (ft)		1.69	Wt. n-Val.	0.050	0.025
0.050					
W. S. Elev (ft)		6254.73	Reach Len. (ft)	26.37	26.37
26.37					
Crit W. S. (ft)		6254.73	Flow Area (sq ft)	3.59	67.77
1.04					
E. G. Slope (ft/ft)		0.006208	Area (sq ft)	3.59	67.77
1.04					
Q Total (cfs)		720.00	Flow (cfs)	7.76	710.75
1.49					
Top Width (ft)		24.16	Top Width (ft)	3.49	18.82
1.85					
Vel Total (ft/s)		9.94	Avg. Vel. (ft/s)	2.16	10.49
1.44					
Max Chl Dpth (ft)		4.69	Hydr. Depth (ft)	1.03	3.60
0.56					
Conv. Total (cfs)		9138.0	Conv. (cfs)	98.4	9020.6
19.0					
Length Wtd. (ft)		26.37	Wetted Per. (ft)	4.05	20.22
2.16					
Min Ch El (ft)		6250.04	Shear (lb/sq ft)	0.34	1.30
0.19					
Alpha		1.10	Stream Power (lb/ft s)	200.00	0.00
0.00					
Frctn Loss (ft)		0.16	Cum Volume (acre-ft)	0.62	3.44
1.01					
C & E Loss (ft)		0.00	Cum SA (acres)	0.28	0.82
0.83					

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1037

INPUT

Description:

Station		Elevation		Data		num=		58	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6264.9	2.25	6264.84	5.85	6264.72	8.12	6264.67	11.85	6264.57
13.99	6264.55	17.84	6264.49	19.87	6264.48	23.81	6264.45	26.01	6264.44
29.86	6264.41	32.7	6264.39	35.88	6264.37	39.39	6264.34	41.91	6264.31
46.07	6264.27	47.93	6264.25	52.76	6264.16	53.95	6264.14	59.45	6264.02
59.98	6263.99	64.7	6263.51	66	6263.39	66.14	6263.34	72.02	6261.78
72.83	6261.35	78.04	6258.91	79.52	6258.11	84.07	6255.67	86.21	6254.5
90.09	6252.42	92.9	6251.17	96.11	6249.66	99.59	6249.67	100.12	6249.65
102.13	6249.57	106.28	6251.55	108.16	6252.3	112.97	6254.82	114.18	6255.44
119.66	6258.45	120.2	6258.73	125.15	6259.79	126.23	6260	156.34	6260
159.79	6259.96	162.36	6259.91	166.48	6259.82	168.39	6259.78	173.17	6259.69
174.41	6259.66	179.86	6259.63	180.43	6259.62	185.61	6259.59	186.45	6259.59
186.55	6259.58	192.48	6259.57	200	6259.57				

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	90.09	.025	108.16	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	90.09	108.16		21.74	21.74		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	Elev (ft)	6255.96	Element	Left OB	Channel
Right OB	Vel Head (ft)	1.70	Wt. n-Val.	0.050	0.025
0.050	W. S. Elev (ft)	6254.27	Reach Len. (ft)	21.74	21.74
21.74	Crit W. S. (ft)	6254.27	Flow Area (sq ft)	3.17	66.87
3.68	E. G. Slope (ft/ft)	0.006002	Area (sq ft)	3.17	66.87
3.68	Q Total (cfs)	720.00	Flow (cfs)	6.36	705.90
7.73	Top Width (ft)	25.26	Top Width (ft)	3.44	18.07
3.75	Vel Total (ft/s)	9.77	Avg. Vel. (ft/s)	2.01	10.56
2.10	Max Chl Dpth (ft)	4.69	Hydr. Depth (ft)	0.92	3.70
0.98	Conv. Total (cfs)	9293.9	Conv. (cfs)	82.2	9112.0
99.8	Length Wtd. (ft)	21.74	Wetted Per. (ft)	3.90	19.27
4.23	Min Ch El (ft)	6249.57	Shear (lb/sq ft)	0.30	1.30
0.33					

Sol ace (v2).rep				
Alpha	1.15	Stream Power (lb/ft s)	200.00	0.00
0.00				
Frctn Loss (ft)	0.11	Cum Volume (acre-ft)	0.62	3.40
1.00				
C & E Loss (ft)	0.14	Cum SA (acres)	0.28	0.81
0.83				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1036

INPUT

Description:

Station Elevation Data num= 74									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6264.78	2.62	6264.68	3.29	6264.66	8.49	6264.53	9.29	6264.5
14.37	6264.43	15.28	6264.41	20.24	6264.37	21.28	6264.37	25.63	6264.31
27.33	6264.29	30.93	6264.24	33.38	6264.19	36.23	6264.15	39.44	6264.09
41.53	6264.06	45.49	6263.96	46.84	6263.93	51.54	6263.78	52.14	6263.75
56.31	6263.59	57.44	6263.54	57.6	6263.53	62.74	6263.14	63.65	6263.1
68.04	6261.59	69.7	6260.93	73.34	6259.33	75.76	6258.28	78.64	6257.01
81.81	6255.62	83.94	6254.69	87.86	6252.97	89.24	6252.26	93.92	6250.26
94.54	6250.15	98.96	6249.21	99.84	6249.02	99.97	6249	105.15	6250.31
106.02	6250.6	110.45	6252.96	112.08	6253.82	115.75	6255.78	118.13	6257.05
121.05	6258.16	124.18	6259.13	126.35	6259.25	130.24	6259.3	131.65	6259.34
136.29	6259.38	136.95	6259.39	141.62	6259.43	142.34	6259.43	147.55	6259.48
148.4	6259.48	152.85	6259.45	154.45	6259.46	158.16	6259.38	160.5	6259.36
163.46	6259.28	166.56	6259.22	168.76	6259.15	172.61	6259.06	174.06	6259.02
178.66	6258.91	179.36	6258.9	184.27	6258.78	184.66	6258.78	189.96	6258.71
190.77	6258.7	195.26	6258.63	196.82	6258.61	200	6258.57		

Manning's n Values num= 3					
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	89.24	.025	110.45	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	89.24	110.45		41.42	41.42	.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6255.45	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.23	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6254.22	Reach Len. (ft)	41.42	41.42
41.42				
Crit W. S. (ft)	6253.79	Flow Area (sq ft)	3.98	79.25
1.50				
E. G. Slope (ft/ft)	0.004264	Area (sq ft)	3.98	79.25

Sol ace (v2). rep

1. 50					
Q Total (cfs)	720. 00	Flow (cfs)	6. 97	711. 07	
1. 97					
Top Width (ft)	27. 81	Top Width (ft)	4. 22	21. 21	
2. 37					
Vel Total (ft/s)	8. 50	Avg. Vel. (ft/s)	1. 75	8. 97	
1. 31					
Max Chl Dpth (ft)	5. 22	Hydr. Depth (ft)	0. 94	3. 74	
0. 63					
Conv. Total (cfs)	11026. 1	Conv. (cfs)	106. 7	10889. 3	
30. 1					
Length Wtd. (ft)	41. 42	Wetted Per. (ft)	4. 66	22. 55	
2. 69					
Min Ch El (ft)	6249. 00	Shear (lb/sq ft)	0. 23	0. 94	
0. 15					
Alpha	1. 10	Stream Power (lb/ft s)	200. 00	0. 00	
0. 00					
Frctn Loss (ft)	0. 13	Cum Volume (acre-ft)	0. 61	3. 36	
1. 00					
C & E Loss (ft)	0. 09	Cum SA (acres)	0. 28	0. 80	
0. 83					

CROSS SECTI ON

RIVER: Channel 01
 REACH: CH01 RS: 1035

INPUT

Descripti on:

Stati on	El evati on	Data	num=	86					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6264. 74	. 46	6264. 72	2. 72	6264. 64	6. 67	6264. 48	7. 61	6264. 44
11. 09	6264. 31	12. 5	6264. 25	12. 87	6264. 24	17. 38	6264. 07	19. 08	6264
22. 27	6263. 88	25. 29	6263. 76	27. 16	6263. 7	31. 5	6263. 53	32. 04	6263. 52
34. 04	6263. 43	36. 93	6263. 33	37. 71	6263. 3	41. 81	6263. 16	43. 92	6263. 07
46. 7	6263. 03	50. 13	6263	51. 59	6262. 92	56. 33	6262. 68	56. 47	6262. 68
56. 99	6262. 64	61. 36	6262. 32	62. 54	6262. 22	66. 25	6261. 14	68. 75	6260. 11
71. 13	6258. 87	74. 96	6256. 86	76. 02	6256. 36	79. 94	6254. 39	80. 91	6253. 91
81. 17	6253. 77	85. 79	6251. 73	87. 38	6251. 17	90. 68	6250. 21	93. 59	6249. 41
95. 57	6248. 89	99. 27	6248. 12	99. 79	6248. 01	100. 45	6248. 21	102. 89	6249. 24
105. 34	6250. 26	106	6250. 65	110. 23	6252. 96	112. 21	6254. 05	115. 11	6255. 65
118. 42	6257. 46	120	6257. 92	124. 63	6258. 24	124. 89	6258. 25	125. 84	6258. 29
129. 77	6258. 48	130. 84	6258. 53	134. 66	6258. 71	137. 05	6258. 83	139. 55	6258. 93
143. 26	6258. 84	144. 43	6258. 83	148. 79	6258. 76	149. 32	6258. 76	149. 46	6258. 75
154. 21	6258. 65	155. 67	6258. 63	159. 09	6258. 6	161. 88	6258. 57	163. 98	6258. 55
168. 09	6258. 51	168. 87	6258. 49	171. 73	6258. 47	173. 75	6258. 45	174. 3	6258. 44
178. 64	6258. 35	180. 51	6258. 34	183. 53	6258. 25	186. 72	6258. 19	188. 41	6258. 15
192. 92	6258. 03	193. 3	6258. 02	194. 68	6257. 99	198. 18	6257. 92	199. 13	6257. 9
200	6257. 9								

Manni ng' s n	Val ues	num=	3
Sta	n Val	Sta	n Val
0	. 05	90. 68	. 025
		105. 34	. 05

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	90. 68	105. 34		36. 85	36. 85	36. 85		. 1	. 3

CROSS SECTI ON OUTPUT Profi le #Sand Creek

		Sol ace (v2). rep		Left OB	Channel
E. G. El ev (ft)	6255. 24	El ement			
Right OB					
Vel Head (ft)	0. 94	Wt. n-Val .		0. 050	0. 025
0. 050					
W. S. El ev (ft)	6254. 30	Reach Len. (ft)		36. 85	36. 85
36. 85					
Crit W. S. (ft)		Flow Area (sq ft)		23. 83	76. 71
14. 69					
E. G. Slope (ft/ft)	0. 002270	Area (sq ft)		23. 83	76. 71
14. 69					
Q Total (cfs)	720. 00	Flow (cfs)		55. 35	634. 37
30. 29					
Top Width (ft)	32. 52	Top Width (ft)		10. 55	14. 66
7. 31					
Vel Total (ft/s)	6. 25	Avg. Vel. (ft/s)		2. 32	8. 27
2. 06					
Max Chl Dpth (ft)	6. 29	Hydr. Depth (ft)		2. 26	5. 23
2. 01					
Conv. Total (cfs)	15113. 4	Conv. (cfs)		1161. 8	13315. 9
635. 7					
Length Wtd. (ft)	36. 85	Wetted Per. (ft)		11. 34	15. 37
8. 35					
Min Ch El (ft)	6248. 01	Shear (lb/sq ft)		0. 30	0. 71
0. 25					
Alpha	1. 56	Stream Power (lb/ft s)		200. 00	0. 00
0. 00					
Frctn Loss (ft)	0. 10	Cum Volume (acre-ft)		0. 60	3. 28
0. 99					
C & E Loss (ft)	0. 01	Cum SA (acres)		0. 27	0. 78
0. 83					

CROSS SECTI ON

RIVER: Channel 01
REACH: CH01

RS: 1034

INPUT

Descr i ption:

Stati on El evati on Data		num=		83							
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6264	1. 13	6263. 99	4. 21	6263. 9	6. 02	6263. 85	10. 42	6263. 71		
10. 91	6263. 69	12. 73	6263. 64	15. 79	6263. 56	16. 62	6263. 54	20. 68	6263. 44		
22. 83	6263. 39	25. 57	6263. 32	29. 04	6263. 24	30. 45	6263. 21	35. 25	6263. 09		
35. 34	6263. 09	35. 67	6263. 08	40. 23	6262. 97	41. 46	6262. 94	45. 11	6262. 81		
47. 67	6262. 76	50	6262. 66	53. 88	6262. 54	54. 89	6262. 5	58. 62	6262. 36		
59. 77	6262. 31	60. 08	6262. 3	64. 66	6262. 1	66. 29	6262. 04	69. 55	6261. 35		
72. 5	6260. 87	74. 43	6260. 05	78. 71	6257. 52	79. 32	6257. 11	81. 57	6255. 57		
84. 21	6253. 75	84. 92	6253. 24	89. 09	6251. 26	91. 13	6250. 53	93. 98	6249. 75		
97. 34	6248. 77	98. 87	6248. 55	99. 98	6248. 73	103. 54	6249. 31	103. 75	6249. 43		
104. 52	6249. 86	108. 64	6252. 07	109. 75	6252. 75	113. 52	6255. 2	115. 96	6256. 6		
118. 41	6257. 74	122. 17	6259. 8	123. 3	6259. 9	127. 47	6260	128. 38	6260		
133. 07	6259. 84	134. 59	6259. 86	137. 96	6259. 71	140. 8	6259. 78	142. 84	6259. 72		
145. 55	6259. 71	146. 97	6259. 71	147. 9	6259. 67	153. 03	6259. 24	153. 17	6259. 23		
154. 11	6259. 13	158. 44	6258. 71	159. 09	6258. 64	163. 71	6258. 5	165. 15	6258. 43		
168. 98	6258. 3	171. 21	6258. 23	174. 25	6258. 23	177. 27	6258. 11	179. 52	6258. 12		
183. 33	6258	184. 79	6258	189. 39	6257. 95	190. 06	6257. 94	194. 49	6257. 87		
195. 33	6257. 86	195. 45	6257. 86	200	6257. 78						

Manni ng' s n Val ues
Sta n Val

num= 3
Sta n Val

Sta n Val

0 .05 89.09 .025 108.64 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 89.09 108.64 13.77 13.77 13.77 .1 .3
 Right Levee Station= 121.38 Elevati on= 6260.11

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6255.13	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.07	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6254.06	Reach Len. (ft)	13.77	13.77
13.77				
Crit W. S. (ft)	6253.35	Flow Area (sq ft)	8.02	83.11
3.15				
E. G. Slope (ft/ft)	0.003139	Area (sq ft)	8.02	83.11
3.15				
Q Total (cfs)	720.00	Flow (cfs)	16.13	699.16
4.71				
Top Width (ft)	28.00	Top Width (ft)	5.33	19.55
3.12				
Vel Total (ft/s)	7.64	Avg. Vel. (ft/s)	2.01	8.41
1.49				
Max Chl Dpth (ft)	5.51	Hydr. Depth (ft)	1.50	4.25
1.01				
Conv. Total (cfs)	12850.4	Conv. (cfs)	287.8	12478.5
84.0				
Length Wtd. (ft)	13.77	Wetted Per. (ft)	6.04	20.70
3.70				
Min Ch El (ft)	6248.55	Shear (lb/sq ft)	0.26	0.79
0.17				
Alpha	1.18	Stream Power (lb/ft s)	200.00	0.00
121.38				
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.59	3.22
0.99				
C & E Loss (ft)	0.02	Cum SA (acres)	0.26	0.77
0.82				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1033

INPUT

Descripti on:

Station Elevati on Data num= 69

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6263.27	2.27	6263.22	5.07	6263.17	8.07	6263.1	11.07	6263.04
13.87	6262.98	17.07	6262.91	19.68	6262.86	23.06	6262.78	25.48	6262.73
29.06	6262.66	31.28	6262.61	35.06	6262.54	37.08	6262.49	41.05	6262.41
42.88	6262.37	47.05	6262.28	48.68	6262.23	53.05	6262.13	54.48	6262.09
59.04	6262	60.28	6261.97	65.04	6261.7	66.08	6261.62	71.04	6261.28
71.88	6261.08	77.03	6259.49	77.68	6259.03	83.03	6255.11	83.48	6254.82
89.03	6251.16	89.28	6251.07	95.02	6249.6	96.92	6249.09	99.95	6248.28
100.88	6248.03	101.02	6248	106.68	6250.21	107.01	6250.36	112.49	6253.52

Sol ace (v2).rep

113.01	6253.82	118.29	6256.86	119.01	6257.27	124.09	6259.63	125	6260
142.99	6260	147.14	6259.89	147.28	6259.88	149.01	6259.89	152.55	6259.56
155.07	6259.49	157.81	6259.22	161.13	6258.9	163.08	6258.84	167.19	6258.63
168.35	6258.59	173.25	6258.43	173.62	6258.43	176.09	6258.33	178.89	6258.23
179.31	6258.2	184.16	6258.04	185.37	6257.99	189.43	6257.95	191.43	6257.92
194.7	6257.87	197.49	6257.82	199.97	6257.78	200	6257.78		

Manning's n Values num= 3

Sta n Val	Sta n Val	Sta n Val
0 .05	89.28 .025	107.01 .05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	89.28	107.01		26.23	26.23		.1	.3
Right Levee		Station=	123.9	Elevation=	6260.08			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6255.07	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.02	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6254.06	Reach Len. (ft)	26.23	26.23
26.23				
Crit W. S. (ft)	6253.17	Flow Area (sq ft)	7.10	82.21
11.86				
E. G. Slope (ft/ft)	0.002681	Area (sq ft)	7.10	82.21
11.86				
Q Total (cfs)	720.00	Flow (cfs)	12.91	682.12
24.97				
Top Width (ft)	28.79	Top Width (ft)	4.64	17.73
6.41				
Vel Total (ft/s)	7.12	Avg. Vel. (ft/s)	1.82	8.30
2.11				
Max Chl Dpth (ft)	6.06	Hydr. Depth (ft)	1.53	4.64
1.85				
Conv. Total (cfs)	13905.2	Conv. (cfs)	249.4	13173.5
482.3				
Length Wtd. (ft)	26.23	Wetted Per. (ft)	5.53	18.57
7.40				
Min Ch El (ft)	6248.00	Shear (lb/sq ft)	0.21	0.74
0.27				
Alpha	1.29	Stream Power (lb/ft s)	200.00	0.00
123.90				
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.59	3.19
0.98				
C & E Loss (ft)	0.03	Cum SA (acres)	0.26	0.76
0.82				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01 RS: 1032
 REACH: CH01

INPUT

Descripti on:
 Station Elevation Data num= 67

Sol ace (v2). rep									
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6262.7	1.46	6262.68	5.94	6262.62	7.23	6262.6	11.94	6262.55
13.01	6262.54	17.94	6262.52	18.78	6262.5	23.93	6262.43	24.55	6262.42
29.93	6262.31	30.33	6262.3	35.93	6262.17	36.1	6262.17	40.55	6262.06
41.88	6262.03	47.65	6261.86	47.92	6261.85	53.42	6261.69	53.92	6261.68
59.2	6261.52	59.92	6261.49	64.97	6261.3	65.92	6261.27	70.74	6261.08
71.91	6261.03	76.52	6258.77	77.91	6258.12	82.29	6255.26	83.91	6254.2
88.06	6251.67	89.91	6250.52	93.84	6249.32	95.91	6248.66	99.61	6248.22
99.95	6248.19	101.9	6248.02	105.39	6249.79	107.9	6251.15	111.16	6253.22
113.9	6254.98	116.93	6256.91	119.9	6258.66	122.71	6259.03	125.89	6259.41
128.48	6259.58	131.89	6259.72	134.25	6259.77	137.89	6259.93	140.03	6259.93
143.89	6260	161.88	6260	163.12	6259.86	167.88	6259.58	168.9	6259.45
173.88	6258.71	174.67	6258.64	179.87	6258	180.44	6257.99	185.87	6257.89
186.22	6257.88	191.87	6257.78	191.99	6257.78	195.14	6257.72	197.76	6257.68
197.87	6257.67	200	6257.67						

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
0	.05	89.91	.025
		107.9	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	89.91	107.9		25.6	25.6		.1	.3
Right Levee		Station=	138.69	Elevation=	6259.96			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	El ev (ft)		Element	Left OB	Channel
Right OB		6254.98			
Vel Head (ft)	0.91		Wt. n-Val.	0.050	0.025
0.050					
W. S. El ev (ft)		6254.07	Reach Len. (ft)	25.60	25.60
25.60					
Crit W. S. (ft)		6252.89	Flow Area (sq ft)	10.20	88.26
6.69					
E. G. Slope (ft/ft)	0.002246		Area (sq ft)	10.20	88.26
6.69					
Q Total (cfs)	720.00		Flow (cfs)	18.86	690.31
10.82					
Top Width (ft)	28.34		Top Width (ft)	5.78	17.99
4.58					
Vel Total (ft/s)	6.85		Avg. Vel. (ft/s)	1.85	7.82
1.62					
Max Chl Dpth (ft)	6.05		Hydr. Depth (ft)	1.77	4.91
1.46					
Conv. Total (cfs)	15193.5		Conv. (cfs)	398.1	14567.0
228.4					
Length Wtd. (ft)	25.60		Wetted Per. (ft)	6.78	19.07
5.43					
Min Ch El (ft)	6248.02		Shear (lb/sq ft)	0.21	0.65
0.17					
Alpha	1.25		Stream Power (lb/ft s)	200.00	0.00
138.69					
Frctn Loss (ft)	0.08		Cum Volume (acre-ft)	0.58	3.14
0.98					
C & E Loss (ft)	0.07		Cum SA (acres)	0.26	0.75
0.82					

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance)

Solace (v2).rep

is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1031

INPUT

Description:

Station		Elevation		Data		num=		67	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6259.43	.79	6259.43	2.41	6259.49	6.8	6259.44	8.84	6259.31
12.81	6259.4	15.27	6259.34	18.81	6259.22	21.7	6259.33	24.82	6259.37
28.13	6259.51	30.83	6259.66	34.57	6259.82	36.83	6259.97	41	6260.11
42.84	6260.25	47.43	6260.4	48.84	6260.49	53.86	6260.65	54.85	6260.7
60.3	6260.76	60.86	6260.79	66.73	6260.77	66.86	6260.77	68.77	6260.59
72.87	6260.09	73.16	6259.99	78.88	6258.24	79.59	6257.74	84.88	6254.14
86.02	6253.39	90.89	6250.09	92.46	6249.51	96.89	6247.75	98.89	6247.99
100.11	6248.24	102.9	6248.81	105.32	6250.2	108.91	6251.86	111.75	6253.18
114.91	6254.64	118.19	6256.15	120.92	6257.41	124.62	6258.31	126.93	6258.83
131.05	6258.89	132.93	6258.95	137.48	6259.04	138.94	6259.09	143.92	6259.23
144.95	6259.27	150.35	6259.42	150.95	6259.44	156.78	6259.61	162.96	6259.61
163.21	6259.58	167.07	6259.18	169.05	6258.98	170.61	6258.83	175.29	6258.42
179.46	6258.12	181.54	6258	187.79	6258	188.31	6257.98	194.03	6257.93
197.16	6257.83	200	6257.74						

Manning's n Values		num=		3	
Station	n Val	Station	n Val	Station	n Val
0	.05	90.89	.025	105.32	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
Right Levee	90.89	105.32	34.57	34.57	34.57	.1	.3	
		Station=	134.78	Elevation=	6259.04			

CROSS SECTION OUTPUT Profile #Sand Creek

Right OB	E. G. Elev (ft)	6254.83	Element	Left OB	Channel
0.050	Vel Head (ft)	1.62	Wt. n-Val.	0.050	0.025
34.57	W. S. Elev (ft)	6253.21	Reach Len. (ft)	34.57	34.57
9.79	Crit W. S. (ft)	6253.03	Flow Area (sq ft)	7.19	64.59
9.79	E. G. Slope (ft/ft)	0.004594	Area (sq ft)	7.19	64.59
24.30	Q Total (cfs)	720.00	Flow (cfs)	17.17	678.52
6.50	Top Width (ft)	25.53	Top Width (ft)	4.61	14.43
2.48	Vel Total (ft/s)	8.83	Avg. Vel. (ft/s)	2.39	10.51
1.51	Max Chl Dpth (ft)	5.46	Hydr. Depth (ft)	1.56	4.48
358.6	Conv. Total (cfs)	10622.7	Conv. (cfs)	253.4	10010.7
7.16	Length Wtd. (ft)	34.57	Wetted Per. (ft)	5.56	15.34

Min Ch El (ft)	6247.75	Solace (v2).rep		
0.39		Shear (lb/sq ft)	0.37	1.21
Alpha	1.34	Stream Power (lb/ft s)	200.00	0.00
134.78		Cum Volume (acre-ft)	0.58	3.09
Frctn Loss (ft)	0.08	Cum SA (acres)	0.26	0.74
0.97				
C & E Loss (ft)	0.29			
0.81				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
This may indicate the need for additional cross sections.
Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
REACH: CH01 RS: 1030

INPUT

Description:

Station	Elevation	Data	num=	59					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6260.05	.45	6260.05	2.09	6260.06	6.43	6260.72	8.31	6260.98
9.02	6260.9	14.53	6260.51	17.6	6260.2	20.74	6259.81	26.17	6259.4
26.96	6259.32	29.02	6259.21	33.17	6259	51.82	6259	51.9	6258.98
58.04	6258.62	58.1	6258.6	62.35	6257.06	64.88	6256.19	66.92	6255.37
71.73	6253.48	77.72	6251.42	78.58	6251.07	79.28	6250.93	85.44	6249.77
91.65	6248.77	92.29	6248.64	93.09	6248.49	99.14	6247.2	99.24	6247.22
104.01	6247.9	105.99	6248.39	108.45	6249.5	112.84	6251.4	116.38	6253.03
119.69	6254.57	123.82	6256.56	126.55	6258.02	128.74	6258.11	133.4	6258.3
139.18	6258.48	140.25	6258.52	141.11	6258.55	147.1	6258.77	153.47	6258.95
153.95	6258.97	154.55	6258.98	160.8	6259.16	165.84	6259.16	167.66	6259.2
169.91	6259.07	173.3	6258.96	174.4	6258.92	180.2	6258.41	180.65	6258.37
181.72	6258.31	186.89	6258	199.39	6258	199.96	6257.99		

Manning's n Values	num=	3
Sta n Val	Sta n Val	Sta n Val
0 .05	85.44 .025	108.45 .05

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
85.44	108.45	24.7	24.7	24.7	.1	.3	

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6254.47	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.65	Wt. n-Val.	0.050	0.025
0.050				
W. S. El ev (ft)	6253.81	Reach Len. (ft)	24.70	24.70
24.70				
Crit W. S. (ft)		Flow Area (sq ft)	33.79	125.43
21.07				
E. G. Slope (ft/ft)	0.001427	Area (sq ft)	33.79	125.43
21.07				
Q Total (cfs)	960.00	Flow (cfs)	64.76	857.70

Sol ace (v2). rep

37. 54				
Top Width (ft)	47. 17	Top Width (ft)	14. 55	23. 01
9. 61				
Vel Total (ft/s)	5. 32	Avg. Vel. (ft/s)	1. 92	6. 84
1. 78				
Max Chl Dpth (ft)	6. 61	Hydr. Depth (ft)	2. 32	5. 45
2. 19				
Conv. Total (cfs)	25413. 2	Conv. (cfs)	1714. 4	22705. 1
993. 8				
Length Wtd. (ft)	24. 70	Wetted Per. (ft)	15. 15	23. 60
10. 53				
Min Ch El (ft)	6247. 20	Shear (lb/sq ft)	0. 20	0. 47
0. 18				
Alpha	1. 49	Stream Power (lb/ft s)	199. 96	0. 00
0. 00				
Frctn Loss (ft)	0. 03	Cum Volume (acre-ft)	0. 56	3. 02
0. 96				
C & E Loss (ft)	0. 02	Cum SA (acres)	0. 25	0. 73
0. 81				

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1029

INPUT

Descripti on:

Stati on	El evati on	Data	num=	62					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6260. 65	1. 48	6260. 82	6. 31	6260. 68	7. 69	6260. 72	11. 33	6260. 32
13. 91	6260	14. 89	6259. 93	20. 13	6259. 38	23. 46	6259. 2	26. 34	6259
51. 2	6259	52. 1	6258. 78	56. 19	6257. 77	57. 23	6257. 68	62. 38	6255. 45
63. 23	6255. 06	68. 57	6252. 55	69. 22	6252. 24	74. 75	6250. 59	75. 22	6250. 4
80. 94	6249. 32	81. 22	6249. 26	87. 13	6248. 41	87. 21	6248. 39	89. 79	6248. 07
93. 21	6247. 62	93. 32	6247. 63	99. 2	6247. 03	99. 37	6247. 13	99. 51	6247. 2
105. 2	6250. 28	105. 69	6250. 6	111. 2	6254. 22	111. 88	6254. 58	117. 19	6258
123. 19	6258	124. 26	6258. 02	129. 18	6258. 05	130. 45	6258. 07	135. 18	6258. 15
136. 64	6258. 17	141. 18	6258. 24	142. 82	6258. 24	147. 17	6258. 23	149. 01	6258. 23
153. 17	6258. 22	155. 2	6258. 18	159. 17	6258. 11	161. 39	6258. 06	165. 16	6258. 02
167. 58	6258	171. 16	6258	173. 77	6257. 79	177. 15	6257. 73	179. 95	6257. 48
183. 15	6256. 95	186. 14	6256. 88	189. 15	6256. 77	192. 33	6256. 64	195. 14	6256. 53
198. 52	6256. 38	200	6256. 32						

Manni ng' s n	Val ues	num=	3
Sta	n Val	Sta	n Val
0	. 05	80. 94	. 025
		105. 2	. 05

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	80. 94	105. 2		24. 82	24. 82	24. 82	. 1		. 3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6254. 41	El ement	Left OB	Channel
Right OB				
Vel Head (ft)	0. 58	Wt. n-Val .	0. 050	0. 025
0. 050				
W. S. El ev (ft)	6253. 83	Reach Len. (ft)	24. 82	24. 82
24. 82				
Crit W. S. (ft)		Flow Area (sq ft)	40. 35	136. 15

Sol ace (v2). rep

9. 61					
E. G. Slope (ft/ft)	0. 001218	Area (sq ft)	40. 35	136. 15	
9. 61					
Q Total (cfs)	960. 00	Flow (cfs)	78. 07	868. 94	
12. 98					
Top Width (ft)	44. 77	Top Width (ft)	15. 10	24. 26	
5. 41					
Vel Total (ft/s)	5. 16	Avg. Vel. (ft/s)	1. 94	6. 38	
1. 35					
Max Chl Dpth (ft)	6. 80	Hydr. Depth (ft)	2. 67	5. 61	
1. 78					
Conv. Total (cfs)	27503. 1	Conv. (cfs)	2236. 8	24894. 3	
372. 0					
Length Wtd. (ft)	24. 82	Wetted Per. (ft)	15. 83	25. 23	
6. 47					
Min Ch El (ft)	6247. 03	Shear (lb/sq ft)	0. 19	0. 41	
0. 11					
Alpha	1. 40	Stream Power (lb/ft s)	200. 00	0. 00	
0. 00					
Frctn Loss (ft)	0. 03	Cum Volume (acre-ft)	0. 54	2. 95	
0. 95					
C & E Loss (ft)	0. 01	Cum SA (acres)	0. 24	0. 71	
0. 80					

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1028

INPUT

Descripti on:

Stati on	El evati on	Data	num=	64					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6260. 33	2. 5	6259. 55	5. 03	6260. 64	8. 49	6260. 77	10. 84	6260. 52
14. 49	6260. 15	16. 66	6259. 95	20. 49	6259. 64	22. 47	6259. 49	26. 48	6259. 19
28. 28	6259. 15	32. 48	6259	56. 46	6259	57. 34	6258. 62	62. 46	6256. 64
63. 16	6256. 34	68. 45	6254. 02	68. 97	6253. 79	74. 45	6251. 4	74. 78	6251. 3
80. 45	6249. 47	80. 59	6249. 45	85. 25	6248. 67	86. 41	6248. 48	86. 44	6248. 48
92. 22	6247. 72	92. 44	6247. 68	98. 03	6247. 04	98. 44	6247	99. 78	6247. 34
103. 84	6248. 38	104. 43	6248. 51	109. 66	6251. 65	110. 43	6252. 07	115. 47	6255. 14
116. 42	6255. 72	121. 28	6256. 79	122. 42	6257. 11	127. 09	6257. 08	128. 42	6257. 08
132. 91	6257. 04	134. 41	6257. 04	138. 72	6257. 01	140. 41	6257. 01	144. 53	6257
146. 4	6257	150. 34	6256. 65	152. 4	6256. 5	156. 16	6256. 31	158. 4	6256. 21
161. 97	6256. 12	164. 39	6256	167. 78	6256. 17	170. 39	6256. 16	173. 6	6256. 2
176. 39	6256. 25	179. 41	6256. 14	182. 38	6256. 06	185. 22	6255. 95	188. 38	6255. 87
191. 03	6255. 81	194. 37	6255. 73	196. 85	6255. 67	200	6255. 59		

Manni ng' s n Val ues	num=	3
Sta n Val	Sta n Val	Sta n Val
0 . 05	85. 25	104. 43 . 05

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
85. 25	104. 43	50. 43	50. 43	50. 43	. 1	. 3	
Right Levee	Stati on=	122. 22	El evati on=	6257. 11			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6254. 37	El ement	Left OB	Channel
Right OB				

Solace (v2).rep				
Vel Head (ft)	0.69	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6253.68	Reach Len. (ft)	50.43	50.43
50.43				
Crit W. S. (ft)	6251.90	Flow Area (sq ft)	47.49	113.10
22.34				
E. G. Slope (ft/ft)	0.001399	Area (sq ft)	47.49	113.10
22.34				
Q Total (cfs)	960.00	Flow (cfs)	105.28	812.47
42.25				
Top Width (ft)	43.84	Top Width (ft)	16.02	19.18
8.64				
Vel Total (ft/s)	5.25	Avg. Vel. (ft/s)	2.22	7.18
1.89				
Max Chl Dpth (ft)	6.68	Hydr. Depth (ft)	2.96	5.90
2.59				
Conv. Total (cfs)	25663.9	Conv. (cfs)	2814.6	21720.0
1129.4				
Length Wtd. (ft)	50.43	Wetted Per. (ft)	16.87	19.47
10.07				
Min Ch El (ft)	6247.00	Shear (lb/sq ft)	0.25	0.51
0.19				
Alpha	1.61	Stream Power (lb/ft s)	200.00	0.00
122.22				
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.51	2.87
0.94				
C & E Loss (ft)	0.05	Cum SA (acres)	0.23	0.70
0.80				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1027

INPUT

Description:

Station Elevati on Data num= 68									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6259.48	2.55	6259.48	8.37	6259.5	8.57	6259.5	10.35	6259.49
14.59	6259.47	15.08	6259.47	20.62	6259.33	21.79	6259.3	26.64	6259.18
28.5	6258.98	32.67	6258.58	35.21	6258.33	38.69	6258	41.92	6258.23
44.72	6258.39	48.63	6258.77	50.74	6259	56.77	6259	62.05	6258.04
62.79	6257.92	68.76	6254.94	68.81	6254.91	69.31	6254.67	74.84	6251.95
75.47	6251.68	80.86	6249.47	82.18	6249.25	86.89	6248.34	88.89	6248.07
92.91	6247.51	95.6	6247.3	98.94	6247	99.74	6247.09	102.31	6247.36
104.96	6247.65	109.02	6249.39	110.98	6250.13	115.73	6252.5	117.01	6253.14
122.44	6255.75	123.03	6256.06	128.28	6256.51	129.06	6256.58	129.15	6256.58
135.08	6256.6	135.86	6256.57	141.11	6256.54	142.57	6256.47	147.13	6256.25
149.28	6256.17	153.15	6255.99	155.99	6255.92	159.18	6255.81	162.7	6255.71
165.2	6255.64	169.41	6255.52	171.23	6255.46	176.12	6255.29	177.25	6255.26
182.83	6255.09	183.28	6255.08	187.25	6255.01	189.3	6254.98	189.53	6254.97
195.33	6254.92	196.24	6254.91	200	6254.88				

Manning's n Values num= 3					
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	86.89	.025	109.02	.05

Sol ace (v2).rep

Bank Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
86.89	109.02	25.05	25.05	25.05	.1	.3	

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6254.26	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.52	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6253.74	Reach Len. (ft)	25.05	25.05
25.05				
Crit W. S. (ft)		Flow Area (sq ft)	50.54	133.77
20.83				
E. G. Slope (ft/ft)	0.001014	Area (sq ft)	50.54	133.77
20.83				
Q Total (cfs)	960.00	Flow (cfs)	100.06	828.23
31.71				
Top Width (ft)	47.04	Top Width (ft)	15.68	22.13
9.23				
Vel Total (ft/s)	4.68	Avg. Vel. (ft/s)	1.98	6.19
1.52				
Max Chl Dpth (ft)	6.74	Hydr. Depth (ft)	3.22	6.04
2.26				
Conv. Total (cfs)	30153.8	Conv. (cfs)	3142.9	26014.8
996.0				
Length Wtd. (ft)	25.05	Wetted Per. (ft)	16.69	22.60
10.21				
Min Chl El (ft)	6247.00	Shear (lb/sq ft)	0.19	0.37
0.13				
Alpha	1.53	Stream Power (lb/ft s)	200.00	0.00
0.00				
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.46	2.73
0.92				
C & E Loss (ft)	0.00	Cum SA (acres)	0.21	0.68
0.79				

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1026

INPUT

Descripti on:

Station	Elevation	Data	num=	60					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6258.85	1.43	6258.88	3.64	6259	8.23	6258.82	9.68	6258.76
15.04	6258.49	15.71	6258.46	20.96	6258.2	21.74	6258.16	21.84	6258.16
27.77	6258	40.11	6258	45.26	6258.28	46.34	6258.3	49.03	6258.27
52.58	6258.25	54.02	6258.15	58.82	6258.04	62.79	6256.61	65.06	6255.83
70.64	6253.6	71.3	6253.34	71.56	6253.23	77.53	6250.84	80.33	6249.97
83.77	6248.87	89.1	6248.43	90.01	6248.36	92.26	6248.06	96.25	6247.49
97.86	6247.4	100.12	6247.21	102.48	6247	106.63	6248.23	108.72	6248.81
113.87	6251.54	114.96	6252.12	115.4	6252.36	121.2	6255.45	124.17	6255.67
127.43	6256	141.7	6256	146.15	6255.98	150.47	6255.86	152.39	6255.81
157.1	6255.66	158.62	6255.61	159.24	6255.59	164.86	6255.41	168.01	6255.32
171.1	6255.22	176.78	6255.05	177.34	6255.04	178.72	6255.02	183.57	6254.93
185.54	6254.91	189.81	6254.86	194.31	6254.82	196.05	6254.81	200	6254.78

Manning's n Values num= 3

Sol ace (v2).rep

Sta n Val Sta n Val Sta n Val
 0 .05 83.77 .025 108.72 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 83.77 108.72 27.07 27.07 27.07 .1 .3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6254.23	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.51	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6253.72	Reach Len. (ft)	27.07	27.07
27.07				
Crit W. S. (ft)		Flow Area (sq ft)	34.42	144.38
22.70				
E. G. Slope (ft/ft)	0.000999	Area (sq ft)	34.42	144.38
22.70				
Q Total (cfs)	960.00	Flow (cfs)	58.11	866.14
35.75				
Top Width (ft)	47.61	Top Width (ft)	13.43	24.95
9.23				
Vel Total (ft/s)	4.76	Avg. Vel. (ft/s)	1.69	6.00
1.58				
Max Chl Dpth (ft)	6.72	Hydr. Depth (ft)	2.56	5.79
2.46				
Conv. Total (cfs)	30368.1	Conv. (cfs)	1838.2	27399.1
1130.8				
Length Wtd. (ft)	27.07	Wetted Per. (ft)	14.29	25.31
10.46				
Min Ch El (ft)	6247.00	Shear (lb/sq ft)	0.15	0.36
0.14				
Alpha	1.44	Stream Power (lb/ft s)	200.00	0.00
0.00				
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.43	2.65
0.91				
C & E Loss (ft)	0.05	Cum SA (acres)	0.20	0.66
0.78				

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1025

INPUT

Descripti on:

Stati on Elevati on Data num= 60

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6258.95	4.76	6258.75	6.69	6258.65	10.79	6258.45	13.49	6258.31
16.82	6258.14	20.29	6258.05	22.85	6258	52.88	6258	55.55	6257.14
58.89	6256.16	61.24	6255.13	64.89	6253.55	66.93	6252.68	70.89	6250.96
72.61	6250.38	76.89	6248.89	78.3	6248.79	82.9	6248.43	83.99	6248.34
88.9	6247.93	89.68	6247.8	94.9	6246.9	95.36	6246.88	99.96	6246.43
100.9	6246.34	101.05	6246.4	103.68	6247.37	106.74	6248.52	106.91	6248.58
112.42	6253.23	112.91	6253.63	118.11	6255.69	118.91	6255.99	123.8	6255.91
124.91	6255.89	129.48	6255.75	130.91	6255.71	135.17	6255.57	136.92	6255.52
140.86	6255.39	142.92	6255.33	146.54	6255.21	148.92	6255.14	152.23	6255.03
154.92	6254.95	157.92	6254.87	160.93	6254.78	163.6	6254.7	166.93	6254.62
169.29	6254.56	172.93	6254.46	174.98	6254.41	178.93	6254.3	180.67	6254.25

Sol ace (v2).rep
 184. 94 6254. 15 186. 35 6254. 12 190. 94 6254. 02 192. 04 6254 200 6254
 Manni ng' s n Val ues num= 3
 Sta n Val Sta n Val Sta n Val
 0 .05 76. 89 .025 106. 91 .05
 Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 76. 89 106. 91 31. 34 31. 34 31. 34 .1 .3
 Ri ght Levee Stati on= 118. 87 El evati on= 6256. 03

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6254. 16	El ement	Left OB	Channel
Ri ght OB				
Vel Head (ft)	0. 35	Wt. n-Val .	0. 050	0. 025
0. 050				
W. S. El ev (ft)	6253. 81	Reach Len. (ft)	31. 34	31. 34
31. 34				
Cri t W. S. (ft)	6250. 86	Fl ow Area (sq ft)	32. 65	184. 33
16. 24				
E. G. Slope (ft/ft)	0. 000613	Area (sq ft)	32. 65	184. 33
16. 24				
Q Total (cfs)	960. 00	Fl ow (cfs)	43. 20	898. 17
18. 63				
Top Wi dth (ft)	49. 08	Top Wi dth (ft)	12. 60	30. 02
6. 46				
Vel Total (ft/s)	4. 12	Avg. Vel . (ft/s)	1. 32	4. 87
1. 15				
Max Chl Dpth (ft)	7. 47	Hydr. Depth (ft)	2. 59	6. 14
2. 52				
Conv. Total (cfs)	38786. 3	Conv. (cfs)	1745. 2	36288. 3
752. 8				
Length Wtd. (ft)	31. 34	Wetted Per. (ft)	13. 54	30. 58
8. 33				
Min Ch El (ft)	6246. 34	Shear (lb/sq ft)	0. 09	0. 23
0. 07				
Alpha	1. 32	Stream Power (lb/ft s)	200. 00	0. 00
118. 87				
Frctn Loss (ft)	0. 02	Cum Volume (acre-ft)	0. 41	2. 55
0. 89				
C & E Loss (ft)	0. 00	Cum SA (acres)	0. 20	0. 64
0. 78				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1024

INPUT

Descri pti on:

Stati on	El evati on	Data	num=	52					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6258	18. 19	6258	19. 79	6257. 9	24. 22	6257. 59	26. 61	6257. 41
30. 25	6257. 15	33. 44	6257. 13	36. 29	6257. 08	40. 27	6257. 49	42. 32	6257. 7
47. 1	6257. 92	48. 35	6258	53. 92	6257. 69	54. 39	6257. 66	57. 9	6257. 38
60. 42	6257. 18	60. 75	6257. 05	66. 45	6255. 16	67. 58	6254. 58	72. 49	6252. 1

Sol ace (v2). rep									
74. 41	6251. 15	78. 52	6249. 1	81. 24	6248. 62	84. 55	6247. 76	88. 06	6247. 51
90. 59	6247. 33	94. 89	6246. 7	96. 62	6246. 58	100. 32	6246. 28	101. 72	6246. 17
102. 66	6246. 08	108. 55	6248. 64	108. 69	6248. 69	109. 77	6249. 46	114. 72	6252. 97
115. 37	6253. 18	120. 76	6255	144. 89	6255	149. 51	6254. 92	150. 92	6254. 89
156. 34	6254. 72	156. 96	6254. 71	161. 64	6254. 57	162. 99	6254. 53	163. 17	6254. 53
169. 02	6254. 36	170	6254. 34	175. 06	6254. 2	176. 82	6254. 15	181. 09	6254. 03
183. 65	6254	200	6254						

Manni ng' s n Val ues num= 3
Sta n Val Sta n Val Sta n Val
0 .05 84. 55 .025 108. 69 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
84. 55 108. 69 16. 62 16. 62 16. 62 .1 .3
Right Levee Stati on= 120. 82 El evati on= 6255

CROSS SECTI ON OUTPUT Profi le #Sand Creek

E. G. El ev (ft)	6254. 13	El ement	Left OB	Channel
Right OB				
Vel Head (ft)	0. 39	Wt. n-Val .	0. 050	0. 025
0. 050				
W. S. El ev (ft)	6253. 75	Reach Len. (ft)	16. 62	16. 62
16. 62				
Crit W. S. (ft)	6250. 63	Fl ow Area (sq ft)	53. 36	161. 84
18. 50				
E. G. Slope (ft/ft)	0. 000641	Area (sq ft)	53. 36	161. 84
18. 50				
Q Total (cfs)	960. 00	Fl ow (cfs)	87. 53	851. 28
21. 19				
Top Wi dth (ft)	47. 83	Top Wi dth (ft)	15. 32	24. 14
8. 36				
Vel Total (ft/s)	4. 11	Avg. Vel. (ft/s)	1. 64	5. 26
1. 15				
Max Chl Dpth (ft)	7. 67	Hydr. Depth (ft)	3. 48	6. 70
2. 21				
Conv. Total (cfs)	37915. 4	Conv. (cfs)	3457. 1	33621. 3
837. 0				
Length Wtd. (ft)	16. 62	Wetted Per. (ft)	16. 57	24. 77
9. 85				
Min Ch El (ft)	6246. 08	Shear (lb/sq ft)	0. 13	0. 26
0. 08				
Alpha	1. 47	Stream Power (lb/ft s)	200. 00	0. 00
120. 82				
Frctn Loss (ft)	0. 01	Cum Volume (acre-ft)	0. 38	2. 42
0. 88				
C & E Loss (ft)	0. 01	Cum SA (acres)	0. 19	0. 63
0. 77				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTI ON

RIVER: Channel 01
REACH: CH01 RS: 1023

INPUT
Descri pti on:

Sol ace (v2). rep

Station		Elevation		Data		num=		60	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6258	10.22	6258	12.46	6257.96	16.25	6257.85	19.28	6257.64
22.29	6257.43	26.11	6257.17	28.32	6257.02	32.94	6257	34.35	6257
39.77	6257.21	40.39	6257.21	45.09	6257.17	46.6	6257.17	52.45	6257.15
53.42	6257.12	58.49	6257.09	60.25	6256.92	64.52	6256.89	67.08	6255.51
70.56	6253.69	73.91	6251.71	76.59	6250.12	80.73	6248.68	82.62	6247.94
87.56	6247.49	88.66	6247.38	94.39	6246.71	94.69	6246.68	96.96	6246.42
99.91	6246.09	100.72	6246	101.22	6246.17	106.76	6247.72	108.05	6248.71
112.79	6252.33	114.87	6253.17	118.82	6255	135.36	6255	136.92	6254.97
142.18	6254.88	142.96	6254.86	148.83	6254.69	148.99	6254.69	155.03	6254.5
155.84	6254.48	161.06	6254.32	162.67	6254.27	167.09	6254.13	169.5	6254.06
173.13	6253.97	176.32	6253.95	179.16	6253.9	183.15	6253.92	185.19	6253.93
189.98	6253.96	191.23	6253.96	196.81	6253.99	197.26	6253.99	200	6254

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	87.56	.025	106.76	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	87.56	106.76		20.93	20.93		.1	.3
Right Levee		Station=	118.87	Elevation=	6255.01			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	Elev (ft)		Element	Left OB	Channel
Right OB		6254.12			
Vel Head (ft)	0.47		Wt. n-Val.	0.050	0.025
0.050					
W. S. Elev (ft)		6253.64	Reach Len. (ft)	20.93	20.93
20.93					
Crit W. S. (ft)		6250.84	Flow Area (sq ft)	67.41	131.67
23.91					
E. G. Slope (ft/ft)	0.000802		Area (sq ft)	67.41	131.67
23.91					
Q Total (cfs)	960.00		Flow (cfs)	135.33	790.83
33.84					
Top Width (ft)	45.25		Top Width (ft)	16.92	19.20
9.13					
Vel Total (ft/s)	4.31		Avg. Vel. (ft/s)	2.01	6.01
1.42					
Max Chl Dpth (ft)	7.64		Hydr. Depth (ft)	3.98	6.86
2.62					
Conv. Total (cfs)	33908.2		Conv. (cfs)	4780.0	27933.1
1195.1					
Length Wtd. (ft)	20.93		Wetted Per. (ft)	18.29	19.53
10.96					
Min Ch El (ft)	6246.00		Shear (lb/sq ft)	0.18	0.34
0.11					
Alpha	1.64		Stream Power (lb/ft s)	200.00	0.00
118.87					
Frctn Loss (ft)	0.02		Cum Volume (acre-ft)	0.36	2.37
0.87					
C & E Loss (ft)	0.01		Cum SA (acres)	0.18	0.62
0.77					

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

Sol ace (v2). rep

RIVER: Channel 01
REACH: CH01

RS: 1022

INPUT

Description:

Station		Elevation		Data		num=		56	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6258	8.38	6258	13.72	6257.76	14.38	6257.72	19.59	6257.37
20.37	6257.31	25.46	6257.04	26.36	6257	62.33	6257	66.56	6255.85
68.33	6255.57	72.43	6252.94	74.32	6251.82	78.3	6249.7	80.31	6248.5
84.17	6247.93	86.31	6247.43	90.04	6247.13	92.3	6246.8	95.91	6246.24
98.3	6246	99.86	6246.19	101.78	6246.42	104.29	6246.78	107.65	6249.28
110.29	6251.04	113.52	6252.73	116.28	6254.17	119.39	6254.23	122.28	6254.22
125.26	6254.28	128.27	6254.33	131.13	6254.31	134.27	6254.37	137	6254.3
140.26	6254.32	142.87	6254.25	146.25	6254.17	148.74	6254.1	152.25	6254
154.61	6253.95	158.24	6253.87	160.48	6253.83	164.24	6253.74	166.35	6253.7
170.23	6253.63	172.22	6253.59	176.23	6253.52	178.09	6253.48	182.22	6253.4
183.96	6253.37	188.22	6253.27	189.83	6253.28	194.21	6253.26	195.7	6253.27
200	6253.28								

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	86.31	.025	104.29	.05

Bank	Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
		86.31	104.29		26.45	26.45		.1	.3
Right	Levee		Station=	134.51	Elevation=	6254.46			

CROSS SECTION OUTPUT Profile #Sand Creek

	E. G. Elev (ft)		Element	Left OB	Channel
Right OB		6254.09			
Vel Head (ft)	0.53		Wt. n-Val.	0.050	0.025
0.050					
W. S. Elev (ft)		6253.57	Reach Len. (ft)	26.45	26.45
26.45					
Crit W. S. (ft)		6250.86	Flow Area (sq ft)	55.93	124.66
33.68					
E. G. Slope (ft/ft)	0.000873		Area (sq ft)	55.93	124.66
33.68					
Q Total (cfs)	960.00		Flow (cfs)	111.71	791.95
56.34					
Top Width (ft)	43.66		Top Width (ft)	14.85	17.98
10.83					
Vel Total (ft/s)	4.48		Avg. Vel. (ft/s)	2.00	6.35
1.67					
Max Chl Dpth (ft)	7.56		Hydr. Depth (ft)	3.76	6.93
3.11					
Conv. Total (cfs)	32486.1		Conv. (cfs)	3780.2	26799.2
1906.7					
Length Wtd. (ft)	26.45		Wetted Per. (ft)	16.30	18.12
12.81					
Min Ch El (ft)	6246.00		Shear (lb/sq ft)	0.19	0.38
0.14					
Alpha	1.69		Stream Power (lb/ft s)	200.00	0.00
134.51					
Frctn Loss (ft)	0.03		Cum Volume (acre-ft)	0.33	2.31
0.86					
C & E Loss (ft)	0.04		Cum SA (acres)	0.17	0.61
0.77					

Sol ace (v2).rep

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
REACH: CH01

RS: 1021

INPUT

Description:

Station		Elevation		Data		num=		64	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6257.73	2.14	6257.6	2.49	6257.59	8.18	6257.25	9.45	6257.2
14.23	6257.06	16.4	6256.93	20.27	6256.84	23.36	6256.54	26.31	6256.28
30.32	6256.07	32.36	6256	37.27	6256.3	38.4	6256.35	44.23	6256.46
56.54	6256.46	58.14	6256.43	62.58	6256.42	65.1	6256.33	68.63	6256.28
72.06	6255.79	74.67	6255.63	79.01	6253.16	80.71	6252.19	85.97	6249.2
86.76	6248.77	91.98	6247.33	92.8	6247.11	92.93	6247.09	98.85	6246
99.88	6246.21	100.19	6246.26	104.89	6247.07	106.84	6248.11	110.94	6250.5
113.8	6252.18	116.98	6253.61	120.75	6253.68	123.03	6253.96	127.71	6253.98
129.07	6254	135.11	6254	138.08	6253.98	141.16	6253.97	141.62	6253.96
147.2	6253.85	148.58	6253.82	153.25	6253.72	155.54	6253.67	159.29	6253.6
162.49	6253.54	165.34	6253.49	169.45	6253.42	171.38	6253.39	176.41	6253.3
177.43	6253.28	183.36	6253.19	183.47	6253.19	184.17	6253.18	189.51	6253.1
190.32	6253.09	195.56	6253.02	197.28	6253.04	200	6253.08		

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	91.98	.025	106.84	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	91.98	106.84		19.84	19.84		.1	.3
Right	Levee	Station=	123.06	Elevation=	6254.04			

CROSS SECTION OUTPUT Profile #Sand Creek

Right OB	E. G. Elev (ft)	6254.01	Element	Left OB	Channel
	Vel Head (ft)	0.97	Wt. n-Val.	0.050	0.025
	0.050				
	W. S. Elev (ft)	6253.05	Reach Len. (ft)	19.84	19.84
	19.84				
	Crit W. S. (ft)	6251.51	Flow Area (sq ft)	42.29	93.92
	21.05				
	E. G. Slope (ft/ft)	0.001852	Area (sq ft)	42.29	93.92
	21.05				
	Q Total (cfs)	960.00	Flow (cfs)	112.52	803.79
	43.70				
	Top Width (ft)	36.51	Top Width (ft)	12.77	14.86
	8.88				
	Vel Total (ft/s)	6.10	Avg. Vel. (ft/s)	2.66	8.56
	2.08				
	Max Chl Dpth (ft)	7.05	Hydr. Depth (ft)	3.31	6.32
	2.37				
	Conv. Total (cfs)	22308.9	Conv. (cfs)	2614.7	18678.8

Sol ace (v2).rep

1015.5				
Length Wtd. (ft)	19.84	Wetted Per. (ft)	14.09	15.34
10.17				
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.35	0.71
0.24				
Alpha	1.67	Stream Power (lb/ft s)	200.00	0.00
123.06				
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.30	2.24
0.84				
C & E Loss (ft)	0.03	Cum SA (acres)	0.16	0.60
0.76				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1020

INPUT

Descripti on:

Stati on	Elevati on	Data	num=	59					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6257.59	.1	6257.59	5.78	6257.15	6.16	6257.13	11.41	6256.91
12.17	6256.89	17.04	6256.74	18.18	6256.7	22.66	6256.28	24.18	6256.19
28.29	6256.04	30.19	6256	33.92	6256.15	36.2	6256.15	39.55	6256.12
42.2	6256.11	45.18	6256.09	48.21	6256.08	50.81	6256.06	54.22	6256.06
56.43	6256.04	60.22	6256.04	62.06	6256.03	66.23	6256.02	67.69	6256.01
72.24	6256.01	73.32	6255.49	78.24	6253.77	78.95	6253.42	84.25	6250.94
84.58	6250.81	89.43	6248.52	90.2	6248.16	95.83	6246.55	96.26	6246.39
99.59	6246.34	101.46	6246.31	102.27	6246.38	107.09	6249.28	108.28	6249.91
112.72	6252.44	114.28	6253.41	118.34	6253.83	120.29	6254	123.97	6253.93
126.3	6253.87	129.6	6253.78	132.3	6253.71	135.23	6253.64	138.31	6253.56
140.86	6253.5	144.32	6253.41	146.49	6253.36	150.32	6253.26	152.11	6253.22
156.33	6253.11	157.74	6253.08	162.34	6253	200	6253		

Manni ng' s n	Val ues	num=	3
Sta	n Val	Sta	n Val
0	.05	90.2	.025
		107.09	.05

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	90.2	107.09		32.65	32.65	32.65		.1	.3
Right Levee		Stati on=	120.54		El evati on=	6254.01			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6253.93	El ement	Left OB	Channel
Right OB				
Vel Head (ft)	1.29	Wt. n-Val.	0.050	0.025
0.050				
W. S. El ev (ft)	6252.64	Reach Len. (ft)	32.65	32.65
32.65				
Crit W. S. (ft)	6251.77	Flow Area (sq ft)	21.40	93.37
10.15				
E. G. Slope (ft/ft)	0.002822	Area (sq ft)	21.40	93.37
10.15				
Q Total (cfs)	960.00	Flow (cfs)	54.04	885.09
20.87				

		Sol ace (v2).rep		
Top Width (ft)	32.42	Top Width (ft)	9.58	16.89
5.95				
Vel Total (ft/s)	7.68	Avg. Vel. (ft/s)	2.53	9.48
2.06				
Max Chl Dpth (ft)	6.33	Hydr. Depth (ft)	2.23	5.53
1.71				
Conv. Total (cfs)	18070.0	Conv. (cfs)	1017.2	16659.9
392.8				
Length Wtd. (ft)	32.65	Wetted Per. (ft)	10.58	17.95
6.83				
Min Ch El (ft)	6246.31	Shear (lb/sq ft)	0.36	0.92
0.26				
Alpha	1.41	Stream Power (lb/ft s)	200.00	0.00
120.54				
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)	0.28	2.20
0.84				
C & E Loss (ft)	0.01	Cum SA (acres)	0.16	0.59
0.76				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1019

INPUT

Description:

Station	Elevation	Data	num=	69					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6256.71	.99	6256.66	4.47	6256.54	7.19	6256.46	9.37	6256.38
13.39	6256.25	14.27	6256.21	17.6	6256.12	19.18	6256.06	19.59	6256.03
24.08	6255.68	25.79	6255.58	28.98	6255.5	31.99	6255.31	33.88	6255.32
38.19	6255.62	38.79	6255.63	41.04	6255.78	43.69	6255.89	44.39	6255.99
48.59	6255.97	50.59	6256	69.19	6256	73.1	6255.3	75.39	6254.8
78	6253.67	81.58	6252.13	82.91	6251.56	87.78	6249.46	87.81	6249.45
87.9	6249.41	92.71	6247.31	93.98	6246.7	97.61	6246.12	99.84	6246.02
100.18	6246	102.52	6246.49	106.38	6247.65	107.42	6248.11	111.34	6249.88
112.32	6250.32	112.58	6250.44	117.22	6252.47	118.78	6253	141.74	6253
143.58	6252.98	146.64	6252.96	149.78	6252.9	151.54	6252.87	155.98	6252.79
156.44	6252.78	158.21	6252.75	161.35	6252.7	162.18	6252.68	166.25	6252.59
168.38	6252.56	171.15	6252.5	174.57	6252.43	176.05	6252.41	180.77	6252.31
180.96	6252.3	181.64	6252.3	185.86	6252.26	186.97	6252.23	190.76	6252.18
193.17	6252.16	195.66	6252.15	199.37	6252.11	200	6252.1		

Manning's n Values	num=	3			
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	92.71	.025	106.38	.05

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
92.71	106.38	27.27	27.27	27.27	.1	.3	
Right	Levee	Stati on=	118.87	El evati on=	6252.97		

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6253.84	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.26	Wt. n-Val.	0.050	0.025

Sol ace (v2). rep

0.050					
W. S. Elev (ft)	6252.58	Reach Len. (ft)	27.27	27.27	
27.27					
Crit W. S. (ft)	6251.68	Flow Area (sq ft)	31.95	82.29	
27.16					
E. G. Slope (ft/ft)	0.002565	Area (sq ft)	31.95	82.29	
27.16					
Q Total (cfs)	960.00	Flow (cfs)	86.40	803.89	
69.71					
Top Width (ft)	37.00	Top Width (ft)	12.17	13.67	
11.16					
Vel Total (ft/s)	6.79	Avg. Vel. (ft/s)	2.70	9.77	
2.57					
Max Chl Dpth (ft)	6.58	Hydr. Depth (ft)	2.62	6.02	
2.43					
Conv. Total (cfs)	18953.8	Conv. (cfs)	1705.9	15871.6	
1376.3					
Length Wtd. (ft)	27.27	Wetted Per. (ft)	13.26	14.08	
12.20					
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.39	0.94	
0.36					
Alpha	1.76	Stream Power (lb/ft s)	200.00	0.00	
118.87					
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)	0.26	2.13	
0.82					
C & E Loss (ft)	0.07	Cum SA (acres)	0.15	0.58	
0.75					

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01

REACH: CH01

RS: 1018

INPUT

Description:

Station	Elevation	Data	num=	72	Station	Elevation	Data	num=	72	Station	Elevation	Data	num=	72
0	6254.23				1.5	6254.23				4.94	6254.41			
12.63	6254.21				16.96	6253.96				18.19	6253.88			
28.99	6253.01				29.31	6253.01				33.21	6253			
41.01	6253				45.99	6253.46				47.03	6253.53			
57.11	6254.83				59.05	6254.95				62.67	6255.01			
71.08	6255.12				73.79	6255.02				77.09	6255.02			
84.91	6252				89.12	6249.79				90.47	6249.14			
99.68	6246.14				101.14	6246				101.59	6246.05			
112.71	6249.33				113.17	6249.53				118.27	6251.72			
125.2	6253				129.39	6253				131.21	6252.98			
140.51	6252.86				143.23	6252.81				146.07	6252.77			
155.26	6252.64				157.19	6252.61				161.27	6252.56			
168.31	6252.45				173.3	6252.37				173.87	6252.36			
180.9	6252.24				184.99	6252.17				185.33	6252.17			
196.11	6252				200	6252				190.55	6252.07			
										191.34	6252.06			

Manning's n Values

Station	n Val	Station	n Val	Station	n Val

0 .05 95.13 .025 107.15 .05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	95.13	107.15		36.97	36.97		.1	.3
Left Levee		Station=	68.05	Elevation=	6255.16			
Right Levee		Station=	125.29	Elevation=	6253.01			

CROSS SECTION OUTPUT Profile #Sand Creek

		Element	Left OB	Channel
E. G. Elev (ft)	6253.67			
Right OB				
Vel Head (ft)	1.97	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6251.70	Reach Len. (ft)	36.97	36.97
36.97				
Crit W. S. (ft)	6251.70	Flow Area (sq ft)	24.12	63.74
26.14				
E. G. Slope (ft/ft)	0.004727	Area (sq ft)	24.12	63.74
26.14				
Q Total (cfs)	960.00	Flow (cfs)	83.83	786.52
89.65				
Top Width (ft)	32.74	Top Width (ft)	9.65	12.02
11.07				
Vel Total (ft/s)	8.42	Avg. Vel. (ft/s)	3.48	12.34
3.43				
Max Chl Dpth (ft)	5.70	Hydr. Depth (ft)	2.50	5.30
2.36				
Conv. Total (cfs)	13962.4	Conv. (cfs)	1219.3	11439.3
1303.8				
Length Wtd. (ft)	36.97	Wetted Per. (ft)	10.87	12.15
12.02				
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.65	1.55
0.64				
Alpha	1.79	Stream Power (lb/ft s)	200.00	68.05
125.29				
Frctn Loss (ft)	0.14	Cum Volume (acre-ft)	0.25	2.09
0.81				
C & E Loss (ft)	0.15	Cum SA (acres)	0.14	0.57
0.74				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1017

INPUT
 Description:
 Station Elevation Data num= 66

Sol ace (v2). rep									
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6255	8. 68	6255	14. 24	6254. 92	14. 63	6254. 88	20. 23	6254. 34
20. 57	6254. 31	26. 22	6253. 76	26. 52	6253. 73	32. 22	6253. 2	32. 47	6253. 17
38. 21	6252. 63	38. 41	6252. 62	44. 2	6252. 07	44. 36	6252. 09	50. 2	6252. 59
50. 3	6252. 6	56. 19	6253. 32	56. 25	6253. 32	62. 18	6253. 44	63. 57	6253. 43
68. 14	6253. 42	68. 18	6253. 42	74. 09	6253. 32	74. 17	6253. 32	80. 03	6253. 05
80. 17	6253. 05	85. 98	6248. 84	86. 16	6248. 7	91. 93	6246. 76	92. 15	6246. 66
97. 87	6245. 02	98. 15	6245	100. 07	6245. 31	103. 82	6245. 93	104. 14	6245. 99
109. 76	6248. 51	110. 13	6248. 68	115. 71	6251. 25	116. 13	6251. 44	121. 66	6251. 97
122. 12	6252	128. 11	6252	133. 55	6252. 05	134. 11	6252. 05	139. 5	6252. 22
140. 1	6252. 22	145. 44	6252. 16	146. 09	6252. 16	151. 39	6252. 11	152. 09	6252. 1
157. 33	6252. 06	158. 08	6252. 05	163. 28	6252. 01	164. 07	6252	169. 23	6251. 96
170. 07	6251. 95	175. 17	6251. 9	176. 06	6251. 89	181. 12	6251. 84	182. 05	6251. 83
187. 06	6251. 73	188. 05	6251. 72	193. 01	6251. 67	194. 04	6251. 65	198. 96	6251. 63
200	6251. 62								

Manning's n Values num= 3
 Sta n Val Sta n Val Sta n Val
 0 .05 91. 93 .025 104. 14 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 91. 93 104. 14 35. 86 35. 86 35. 86 .1 .3
 Left Levee Station= 63. 31 Elevati on= 6253. 45
 Right Levee Station= 139. 53 Elevati on= 6252. 25

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6253. 01	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1. 47	Wt. n-Val.	0. 050	0. 025
0. 050				
W. S. Elev (ft)	6251. 54	Reach Len. (ft)	35. 86	35. 86
35. 86				
Crit W. S. (ft)	6250. 92	Flow Area (sq ft)	27. 53	71. 76
34. 14				
E. G. Slope (ft/ft)	0. 003198	Area (sq ft)	27. 53	71. 76
34. 14				
Q Total (cfs)	960. 00	Flow (cfs)	85. 70	771. 49
102. 81				
Top Width (ft)	34. 94	Top Width (ft)	9. 68	12. 21
13. 05				
Vel Total (ft/s)	7. 19	Avg. Vel. (ft/s)	3. 11	10. 75
3. 01				
Max Chl Dpth (ft)	6. 54	Hydr. Depth (ft)	2. 84	5. 88
2. 62				
Conv. Total (cfs)	16975. 1	Conv. (cfs)	1515. 3	13641. 8
1818. 0				
Length Wtd. (ft)	35. 86	Wetted Per. (ft)	10. 92	12. 54
14. 23				
Min Ch El (ft)	6245. 00	Shear (lb/sq ft)	0. 50	1. 14
0. 48				
Alpha	1. 83	Stream Power (lb/ft s)	200. 00	63. 31
139. 53				
Frctn Loss (ft)	0. 14	Cum Volume (acre-ft)	0. 22	2. 03
0. 78				
C & E Loss (ft)	0. 05	Cum SA (acres)	0. 14	0. 56
0. 73				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1016

INPUT

Description:

Station Elevation Data num= 68

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6252.98	2.54	6253.03	3.12	6253.03	8.53	6253.05	9.06	6253.03
14.52	6252.89	15.01	6252.87	20.52	6252.73	20.96	6252.72	26.51	6252.61
26.9	6252.59	32.5	6252.49	32.85	6252.46	38.5	6252.06	38.8	6252.03
44.49	6251.62	44.74	6251.63	50.48	6251.3	50.69	6251.31	56.48	6251.67
56.63	6251.68	62.47	6252.07	62.58	6252.07	68.46	6252.04	74.46	6252
76.41	6251.76	80.42	6251.26	80.45	6251.26	86.36	6248.46	86.44	6248.42
92.31	6245.64	92.44	6245.58	98.26	6245.18	98.43	6245.16	100.13	6245.38
104.2	6245.92	104.42	6245.95	110.15	6249.6	110.42	6249.78	116.09	6251.11
116.41	6251.17	122.04	6251.25	122.4	6251.26	127.99	6251.34	128.4	6251.34
133.93	6251.42	134.39	6251.43	139.88	6251.45	140.38	6251.45	145.83	6251.35
146.38	6251.34	151.77	6251.24	152.37	6251.23	157.72	6251.15	158.36	6251.14
163.66	6251.05	164.36	6251.04	169.61	6250.99	170.35	6250.99	175.56	6250.95
176.34	6250.95	181.5	6250.92	182.34	6250.91	187.45	6250.88	188.33	6250.87
193.39	6250.84	194.32	6250.83	200	6250.83				

Manning's n Values num= 3

Station	n Value	Station	n Value	Station	n Value
0	.05	92.31	.025	104.42	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	92.31	104.42		34.77	34.77		.1	.3
Left Levee		Station=	62.75	Elevation=	6252.08			
Right Levee		Station=	140.37	Elevation=	6251.47			

CROSS SECTION OUTPUT Profile #Sand Creek

Right OB	E. G. Elev (ft)	6252.82	Element	Left OB	Channel
	Vel Head (ft)	2.00	Wt. n-Val.	0.050	0.025
0.050	W. S. Elev (ft)	6250.82	Reach Len. (ft)	34.77	34.77
34.77	Crit W. S. (ft)	6250.82	Flow Area (sq ft)	28.30	64.83
20.04	E. G. Slope (ft/ft)	0.004651	Area (sq ft)	28.30	64.83
20.04	Q Total (cfs)	960.00	Flow (cfs)	101.09	800.65
58.26	Top Width (ft)	33.47	Top Width (ft)	10.93	12.11
10.43	Vel Total (ft/s)	8.48	Avg. Vel. (ft/s)	3.57	12.35
2.91	Max Chl Dpth (ft)	5.66	Hydr. Depth (ft)	2.59	5.35
1.92	Conv. Total (cfs)	14076.9	Conv. (cfs)	1482.3	11740.3
854.3	Length Wtd. (ft)	34.77	Wetted Per. (ft)	12.09	12.19
11.67	Min Ch El (ft)	6245.16	Shear (lb/sq ft)	0.68	1.54

Sol ace (v2).rep

0.50	Alpha	1.79	Stream Power (lb/ft s)	200.00	62.75
140.37	Frctn Loss (ft)	0.08	Cum Volume (acre-ft)	0.20	1.97
0.76	C & E Loss (ft)	0.41	Cum SA (acres)	0.13	0.55
0.72					

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

Warning: The energy loss was greater than 1.0 ft (0.3 m) between the current and previous cross section. This may indicate the need for additional cross sections.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1015

INPUT

Description:

Station Elevati on Data num= 61

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6252	45.17	6252	45.57	6251.95	47.67	6252	51.27	6252
55.82	6251.66	57.37	6251.68	60.95	6251.14	63.47	6251	66.07	6250.39
69.57	6248.93	71.2	6248.89	75.67	6247.13	76.32	6247.08	79.78	6246.93
81.45	6246.96	81.77	6246.84	86.58	6246.29	87.87	6246.19	91.7	6245.64
93.97	6245.38	96.83	6244.32	100.07	6244	101.96	6244	106.17	6244.72
107.08	6244.83	111.89	6245.56	112.21	6245.59	117.34	6249.59	118.37	6250.08
122.46	6250.56	124.47	6250.86	127.59	6250.82	130.57	6251	132.71	6251
136.67	6250.89	137.84	6250.86	142.77	6250.6	142.97	6250.59	143.99	6250.56
148.09	6250.42	148.87	6250.4	154.97	6250.4	158.35	6250.37	161.07	6250.36
163.47	6250.31	167.17	6250.28	168.6	6250.27	173.27	6250.21	173.72	6250.2
176.1	6250.17	178.85	6250.14	179.37	6250.14	183.98	6250.1	185.47	6250.07
189.1	6250.03	191.57	6249.89	194.23	6249.85	197.68	6249.54	199.36	6249.48
200	6249.48								

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.05	93.97	.025	111.89	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	93.97	111.89		47.19	47.19	.1	.3
Right Levee		Station=	132.55	Elevati on=	6251.06		

CROSS SECTION OUTPUT Profile #Sand Creek

Sol ace (v2). rep

E. G. El ev (ft)	6250.93	El ement	Left OB	Channel
Ri ght OB				
Vel Head (ft)	0.62	Wt. n-Val .	0.050	0.025
0.050				
W. S. El ev (ft)	6250.31	Reach Len. (ft)	47.19	47.19
47.19				
Crit W. S. (ft)	6248.73	Fl ow Area (sq ft)	86.05	102.15
16.18				
E. G. Slope (ft/ft)	0.001456	Area (sq ft)	86.05	102.15
16.18				
Q Total (cfs)	960.00	Fl ow (cfs)	204.19	730.41
25.40				
Top Width (ft)	54.06	Top Wi dth (ft)	27.71	17.92
8.44				
Vel Total (ft/s)	4.70	Avg. Vel. (ft/s)	2.37	7.15
1.57				
Max Chl Dpth (ft)	6.31	Hydr. Depth (ft)	3.11	5.70
1.92				
Conv. Total (cfs)	25157.1	Conv. (cfs)	5350.8	19140.7
665.6				
Length Wtd. (ft)	47.19	Wetted Per. (ft)	28.43	18.25
9.94				
Min Ch El (ft)	6244.00	Shear (lb/sq ft)	0.28	0.51
0.15				
Al pha	1.82	Stream Power (lb/ft s)	200.00	0.00
132.55				
Frctn Loss (ft)	0.10	Cum Vol ume (acre-ft)	0.15	1.91
0.74				
C & E Loss (ft)	0.07	Cum SA (acres)	0.11	0.54
0.72				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.

This may indicate the need for additional cross sections.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01

REACH: CH01

RS: 1014

INPUT

Descripti on:

Stati on El evati on Data num= 101

Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6250.34	.21	6250.34	.92	6250.33	5.81	6250.32	6.93	6250.31
11.4	6250.34	12.94	6250.34	16.99	6250.35	22.58	6250.35	24.96	6250.33
28.18	6250.38	30.97	6250.42	33.77	6250.48	36.98	6250.52	39.36	6250.56
42.99	6250.63	44.95	6250.68	49	6250.79	50.55	6250.86	55.01	6251
56.14	6251.06	61.02	6251.31	61.73	6251.34	67.03	6251.64	67.32	6251.66
71.27	6252	72.92	6252.14	73.04	6252.15	78.51	6251.99	79.05	6252
84.1	6249.99	85.06	6249.63	89.69	6247.32	91.07	6246.62	95.28	6244.94
97.08	6244.56	100.26	6244.49	100.88	6244.47	103.09	6244	106.47	6244.68
109.1	6245.12	112.06	6245.87	115.11	6246.82	117.65	6247.64	121.12	6248.8
123.25	6249.2	127.13	6249.42	128.84	6249.42	133.14	6249.62	134.43	6249.63
139.15	6249.67	140.02	6249.67	145.16	6249.8	145.62	6249.81	151.17	6249.8

Sol ace (v2). rep									
151.79	6249.8	156.8	6249.75	157.18	6249.75	162.39	6249.74	163.19	6249.73
167.99	6249.66	169.2	6249.65	173.58	6249.63	175.21	6249.61	179.17	6249.53
181.22	6249.51	184.76	6249.46	187.22	6249.41	190.36	6249.34	193.23	6249.23
195.95	6249.1	198	6249.06	199.24	6249.03	201.57	6248.97	205.25	6248.96
207.21	6248.96	211.26	6248.99	212.85	6248.99	217.26	6249	259.3	6249
263.61	6249.17	265.31	6249.25	269.25	6249.41	271.31	6249.49	274.89	6249.62
277.32	6249.73	280.53	6249.85	283.32	6249.96	283.96	6249.99	286.13	6250.07
289.34	6250.2	291.67	6250.34	295.35	6250.51	297.21	6250.62	300	6250.76
301.37	6250.83	302.76	6251.26	307.38	6252.17	308.3	6252.2	313.4	6253
327.17	6253								

Manning's n Values num= 3
 Sta n Val Sta n Val Sta n Val
 0 .05 91.07 .025 112.06 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 91.07 112.06 18.01 18.01 18.01 .1 .3
 Left Levee Station= 72.96 Elevati on= 6252.18
 Right Levee Station= 145.12 Elevati on= 6249.83

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6250.77	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.29	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6249.48	Reach Len. (ft)	18.01	18.01
18.01				
Crit W. S. (ft)	6248.90	Flow Area (sq ft)	8.12	95.68
21.41				
E. G. Slope (ft/ft)	0.003430	Area (sq ft)	8.12	95.68
21.41				
Q Total (cfs)	956.00	Flow (cfs)	16.60	898.32
41.07				
Top Width (ft)	44.69	Top Width (ft)	5.70	20.99
18.00				
Vel Total (ft/s)	7.64	Avg. Vel. (ft/s)	2.04	9.39
1.92				
Max Chl Dpth (ft)	5.48	Hydr. Depth (ft)	1.42	4.56
1.19				
Conv. Total (cfs)	16322.9	Conv. (cfs)	283.5	15338.1
701.3				
Length Wtd. (ft)	18.01	Wetted Per. (ft)	6.38	21.60
18.50				
Min Ch El (ft)	6244.00	Shear (lb/sq ft)	0.27	0.95
0.25				
Al pha	1.42	Stream Power (lb/ft s)	327.17	72.96
145.12				
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.10	1.80
0.72				
C & E Loss (ft)	0.11	Cum SA (acres)	0.09	0.52
0.70				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01

REACH: CH01

RS: 1013

INPUT

Description:

Station	Elevation	Data	num=	134	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6249.97	1.28	6249.97	2.06	6249.96	6.87	6249.92	8.07	6249.91			
12.46	6249.88	14.08	6249.87	18.06	6249.86	20.09	6249.86	23.65	6249.87			
26.1	6249.88	29.24	6249.89	38.12	6249.89	40.43	6249.9	44.13	6249.91			
46.02	6249.95	50.14	6249.99	51.61	6250.05	56.15	6250.11	57.2	6250.16			
62.16	6250.42	62.8	6250.45	68.17	6250.75	68.39	6250.78	71.35	6251.18			
73.98	6251.53	74.18	6251.56	79.57	6251.56	80.19	6251.61	85.17	6249.78			
86.2	6249.3	90.76	6246.92	92.21	6246.15	96.35	6244.92	98.22	6243.96			
99.82	6243.77	101.94	6243.52	104.23	6243.8	107.54	6244.85	110.24	6245.87			
113.13	6246.63	116.25	6247.48	118.72	6248.2	122.26	6249.03	124.31	6249.09			
128.27	6249.2	129.9	6249.25	134.28	6249.35	135.5	6249.37	140.28	6249.36			
146.68	6249.36	151.87	6249.35	158.31	6249.35	163.46	6249.34	164.32	6249.34			
169.05	6249.28	170.33	6249.28	174.64	6249.21	176.34	6249.17	180.24	6249.05			
182.02	6249.01	182.35	6249	185.74	6248.96	188.38	6248.9	191.21	6248.86			
194.4	6248.81	196.68	6248.79	200.43	6248.73	202.15	6248.71	206.45	6248.68			
207.62	6248.69	212.47	6248.68	213.09	6248.69	218.5	6248.72	218.55	6248.72			
219.11	6248.73	224.02	6248.76	224.52	6248.76	229.49	6248.79	230.55	6248.8			
234.96	6248.83	236.57	6248.84	240.43	6248.86	242.59	6248.88	245.9	6248.9			
248.62	6248.92	251.36	6248.93	254.64	6248.95	256.83	6248.94	260.67	6248.99			
262.3	6249.06	266.69	6249.27	267.77	6249.31	272.71	6249.54	273.24	6249.56			
278.39	6249.8	278.71	6249.81	278.74	6249.81	284.17	6250.05	284.76	6250.07			
289.64	6250.26	290.79	6250.3	295.11	6250.46	296.81	6250.51	300	6250.62			
300.58	6250.64	302.83	6250.71	306.05	6250.82	308.86	6250.9	311.52	6251.41			
314.88	6251.9	316.98	6251.99	320.91	6252.21	322.45	6252.26	326.93	6252.4			
327.92	6252.39	332.95	6252.41	333.39	6252.41	337.67	6252.46	338.86	6252.47			
338.98	6252.47	344.33	6252.55	345	6252.56	349.79	6252.66	351.03	6252.69			
355.26	6252.81	357.05	6252.83	360.73	6252.88	363.07	6252.92	366.2	6252.91			
369.1	6252.96	371.67	6252.96	375.12	6253	378.96	6253					

Manning's n	Values	num=	3
Sta	n Val	Sta	n Val
0	.05	92.21	.025
		110.24	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	92.21	110.24		18.13	18.13		.1	.3
Left Levee		Station=	73.92	El evati on=	6251.56			
Right Levee		Station=	146.4	El evati on=	6249.34			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	El ev (ft)	6250.61	Element	Left OB	Channel
Right OB					
Vel Head (ft)	0.94		Wt. n-Val.	0.050	0.025
0.050					
W. S.	El ev (ft)	6249.67	Reach Len. (ft)	18.13	18.13
18.13					
Crit W. S.	(ft)	6249.02	Flow Area (sq ft)	11.80	92.02
121.18					
E. G.	Slope (ft/ft)	0.002495	Area (sq ft)	11.80	92.02
121.18					
Q Total (cfs)	956.00		Flow (cfs)	23.35	786.67
145.97					
Top Width (ft)	190.16		Top Width (ft)	6.80	18.03
165.33					
Vel Total (ft/s)	4.25		Avg. Vel. (ft/s)	1.98	8.55
1.20					
Max Chl Dpth (ft)	6.15		Hydr. Depth (ft)	1.73	5.10

Sol ace (v2). rep

0. 73				
Conv. Total (cfs)	19140. 3	Conv. (cfs)	467. 6	15750. 2
2922. 5				
Length Wtd. (ft)	18. 13	Wetted Per. (ft)	7. 66	18. 83
165. 77				
Min Ch El (ft)	6243. 52	Shear (lb/sq ft)	0. 24	0. 76
0. 11				
Alpha	3. 35	Stream Power (lb/ft s)	378. 96	73. 92
146. 40				
Frctn Loss (ft)	0. 04	Cum Volume (acre-ft)	0. 10	1. 76
0. 69				
C & E Loss (ft)	0. 06	Cum SA (acres)	0. 09	0. 51
0. 66				

Warning: Multiple water surfaces were found that could balance the energy equation. The program selected the water surface whose main channel velocity head was the closest to the previously computed cross section.
 Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1012

INPUT

Description:

Station	Elevation	Data	num=	113					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6249. 53	2. 89	6249. 5	3. 67	6249. 48	8. 8	6249. 43	9. 66	6249. 42
14. 7	6249. 4	15. 66	6249. 39	20. 61	6249. 38	21. 65	6249. 38	26. 51	6249. 39
27. 64	6249. 39	32. 42	6249. 4	33. 64	6249. 4	38. 33	6249. 44	39. 63	6249. 45
44. 23	6249. 51	45. 63	6249. 53	50. 14	6249. 6	51. 62	6249. 63	56. 04	6249. 71
57. 61	6249. 74	61. 95	6249. 83	63. 61	6249. 87	67. 86	6249. 96	69. 6	6250
73. 76	6250. 77	75. 59	6251. 05	79. 67	6251. 65	81. 59	6251. 67	85. 57	6249. 5
87. 58	6248. 84	91. 48	6246. 76	93. 58	6245. 61	97. 38	6244	99. 57	6243. 06
99. 89	6243. 17	103. 29	6244. 3	105. 56	6244. 66	109. 2	6245. 27	111. 56	6246. 41
115. 1	6247. 63	117. 55	6248. 11	121. 01	6248. 55	123. 54	6248. 76	126. 91	6248. 87
129. 54	6249. 02	141. 53	6249. 02	144. 63	6249. 03	171. 5	6249. 03	174. 16	6249. 02
177. 49	6249. 02	180. 07	6248. 95	183. 48	6248. 85	185. 97	6248. 8	189. 48	6248. 71
191. 88	6248. 67	195. 47	6248. 6	197. 78	6248. 58	201. 49	6248. 56	203. 23	6248. 55
207. 51	6248. 52	208. 67	6248. 51	213. 54	6248. 47	214. 12	6248. 48	219. 53	6248. 51
225. 01	6248. 55	225. 59	6248. 55	230. 45	6248. 58	231. 62	6248. 59	235. 9	6248. 62
237. 65	6248. 63	241. 34	6248. 65	243. 68	6248. 67	246. 79	6248. 68	249. 7	6248. 73
252. 23	6248. 76	255. 73	6248. 85	257. 68	6248. 89	261. 76	6249	263. 12	6249. 06
267. 79	6249. 27	268. 57	6249. 31	273. 81	6249. 58	274. 01	6249. 59	275. 89	6249. 69
279. 46	6249. 87	279. 84	6249. 89	284. 9	6250. 08	285. 87	6250. 12	290. 35	6250. 25
291. 9	6250. 3	295. 79	6250. 41	297. 92	6250. 47	300	6250. 53	301. 24	6250. 57
303. 95	6250. 65	306. 68	6250. 73	309. 98	6250. 82	312. 13	6250. 94	316	6251. 05
317. 57	6251. 26	322. 03	6251. 6	323. 02	6251. 62	328. 06	6251. 9	328. 46	6251. 91
332. 24	6251. 98	333. 91	6252. 02	334. 09	6252. 02	339. 35	6252. 1	340. 11	6252. 12
344. 8	6252. 22	346. 14	6252. 25	348. 95	6252. 34				

Manning's n Values	num=	3
Sta n Val	Sta n Val	Sta n Val
0 . 05	93. 58 . 025	109. 2 . 05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	93. 58	109. 2		38. 75 38. 75	38. 75	. 1	. 3

Solace (v2).rep

Left Levee Station= 80.25 Elevation= 6251.65
 Right Levee Station= 145.04 Elevation= 6249.02

CROSS SECTION OUTPUT Profile #Sand Creek

Parameter	Value	Element	Left OB	Channel
E. G. Elev (ft)	6250.51			
Right OB				
Vel Head (ft)	0.74	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6249.77	Reach Len. (ft)	38.75	38.75
38.75				
Crit W. S. (ft)	6249.77	Flow Area (sq ft)	16.49	84.69
172.46				
E. G. Slope (ft/ft)	0.002086	Area (sq ft)	16.49	84.69
172.46				
Q Total (cfs)	956.00	Flow (cfs)	32.34	686.27
237.39				
Top Width (ft)	192.41	Top Width (ft)	8.51	15.62
168.29				
Vel Total (ft/s)	3.49	Avg. Vel. (ft/s)	1.96	8.10
1.38				
Max Chl Dpth (ft)	6.71	Hydr. Depth (ft)	1.94	5.42
1.02				
Conv. Total (cfs)	20931.4	Conv. (cfs)	708.0	15025.7
5197.6				
Length Wtd. (ft)	38.75	Wetted Per. (ft)	9.49	16.42
168.87				
Min Ch El (ft)	6243.06	Shear (lb/sq ft)	0.23	0.67
0.13				
Alpha	3.91	Stream Power (lb/ft s)	348.95	80.25
145.04				
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)	0.09	1.72
0.63				
C & E Loss (ft)	0.00	Cum SA (acres)	0.09	0.50
0.59				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
 Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.
 Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1011

INPUT

Description:

Station	Elevation	Data	num=	114	Station	Elevation	Station	Elevation	Station	Elevation
-55.78	6250.22	-51.68	6250.17	-51.21	6250.16	-45.44	6250.08	-45.21	6250.07	
-39.54	6250	-39.21	6250	-33.21	6249.91	-32.96	6249.9	-27.22	6249.77	
-26.72	6249.76	-21.22	6249.63	-20.48	6249.61	-15.5	6249.5	-15.22	6249.49	

Sol ace (v2). rep

-14.24	6249.47	-9.22	6249.35	-7.99	6249.32	-3.23	6249.21	-1.75	6249.18
2.77	6249.07	4.49	6249.06	8.77	6249.02	10.73	6249.01	14.77	6249.01
16.97	6249	20.76	6248.95	26.76	6248.95	29.45	6248.96	32.76	6249
104.73	6249	110.63	6249.41	110.73	6249.43	112.87	6249.79	116.73	6250.43
116.92	6250.43	122.73	6249.93	123.21	6249.56	128.73	6245.21	129.49	6245.05
134.5	6244.05	134.73	6244	140.73	6244	142.07	6244.52	146.73	6246.11
148.36	6246.58	152.73	6248.04	154.65	6248.11	158.73	6248.28	160.93	6248.36
164.73	6248.51	167.22	6248.61	170.73	6248.68	173.51	6248.73	176.73	6248.77
179.8	6248.76	182.73	6248.78	186.09	6248.75	188.73	6248.72	192.37	6248.69
194.72	6248.67	198.66	6248.63	200.72	6248.62	204.95	6248.6	206.72	6248.58
211.24	6248.46	212.72	6248.44	217.53	6248.3	218.72	6248.26	223.81	6248.11
224.72	6248.08	227.43	6248.04	230.08	6248	254.71	6248	255	6248.01
260.71	6248.16	261.23	6248.17	266.7	6248.33	267.46	6248.35	272.7	6248.51
273.69	6248.54	278.7	6248.69	279.92	6248.72	284.5	6248.85	284.7	6248.86
286.15	6248.91	290.69	6249.06	292.38	6249.12	296.69	6249.27	298.61	6249.33
302.69	6249.47	304.84	6249.54	308.69	6249.68	311.07	6249.78	314.68	6249.9
317.3	6250	320.68	6250.09	323.53	6250.18	326.68	6250.27	329.76	6250.36
332.67	6250.44	335.99	6250.54	338.67	6250.61	342.22	6250.71	344.67	6250.78
348.45	6250.89	350.67	6250.95	354.68	6251.15	356.66	6251.25	360.91	6251.48
362.66	6251.6	367.14	6251.87	368.66	6251.97	369.02	6251.97		

Manning's n	Values	num=	3
Sta	n Val	Sta	n Val
-55.78	.05	128.73	.025
		146.73	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	128.73	146.73		22.91	22.91		.1	.3
Left Levee		Station=	116.04	Elevation=	6250.47			
Right Levee		Station=	181.87	Elevation=	6248.85			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6250.19	Element		Left OB	Channel
Right OB					
Vel Head (ft)	0.78	Wt. n-Val.		0.050	0.025
0.050					
W. S. Elev (ft)	6249.40	Reach Len. (ft)		22.91	22.91
22.91					
Crit W. S. (ft)	6249.40	Flow Area (sq ft)		11.16	87.16
152.55					
E. G. Slope (ft/ft)	0.002397	Area (sq ft)		11.16	87.16
152.55					
Q Total (cfs)	956.00	Flow (cfs)		22.64	713.30
220.07					
Top Width (ft)	177.33	Top Width (ft)		5.32	18.00
154.01					
Vel Total (ft/s)	3.81	Avg. Vel. (ft/s)		2.03	8.18
1.44					
Max Chl Dpth (ft)	5.40	Hydr. Depth (ft)		2.10	4.84
0.99					
Conv. Total (cfs)	19527.5	Conv. (cfs)		462.4	14570.0
4495.2					
Length Wtd. (ft)	22.91	Wetted Per. (ft)		6.77	18.48
154.51					
Min Ch El (ft)	6244.00	Shear (lb/sq ft)		0.25	0.71
0.15					
Alpha	3.48	Stream Power (lb/ft s)		369.02	116.04
181.87					
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)		0.08	1.65
0.49					
C & E Loss (ft)	0.00	Cum SA (acres)		0.08	0.49
0.45					

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
 Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.
 Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1010

INPUT

Description:

Station		Elevation		Data		num= 117		Station		Elevation		Station		Elevation	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-88.21	6250.09	-83.83	6250.03	-82.38	6250.01	-77.54	6249.9	-76.38	6249.87						
-71.25	6249.75	-70.38	6249.73	-64.96	6249.59	-64.38	6249.58	-58.67	6249.44						
-58.38	6249.43	-52.49	6249.29	-52.38	6249.29	-50.31	6249.24	-46.38	6249.14						
-46.08	6249.13	-40.38	6248.98	-39.79	6248.95	-34.38	6248.68	-33.5	6248.64						
-28.38	6248.38	-27.21	6248.34	-22.38	6248.12	-20.92	6248.07	-16.38	6248.01						
-14.63	6248	-8.34	6248	-4.38	6248.09	-2.05	6248.24	1.62	6248.43						
4.73	6248.64	7.71	6248.8	12.17	6248.94	13.8	6249	62.53	6249						
64.29	6249.03	68.62	6249.11	71.74	6249.46	74.71	6249.78	79.19	6250.25						
80.81	6250.33	86.63	6250.13	86.9	6250.13	88.09	6249.34	92.99	6246.06						
94.08	6245.77	99.08	6243.72	99.69	6243.7	101.52	6243.67	105.17	6243.74						
108.97	6245.23	111.26	6245.96	116.42	6247.26	117.35	6247.6	121.57	6247.88						
123.45	6248.01	123.86	6248.01	129.54	6248.06	131.31	6248.09	135.63	6248.16						
138.75	6248.21	141.72	6248.26	146.2	6248.33	147.81	6248.36	153.65	6248.42						
153.9	6248.43	155.06	6248.42	159.99	6248.37	161.09	6248.36	166.09	6248.31						
168.54	6248.28	172.18	6248.25	175.98	6248.2	178.27	6248.17	183.43	6248.04						
184.36	6248.03	185.16	6248.03	190.14	6248	220.43	6248	222.58	6248.04						
226.44	6248.08	229.07	6248.17	232.45	6248.28	235.56	6248.38	238.46	6248.48						
242.04	6248.6	244.47	6248.69	248.53	6248.82	249.69	6248.86	250.48	6248.89						
255.02	6249.06	256.48	6249.12	261.51	6249.33	262.49	6249.38	268	6249.6						
268.5	6249.62	274.48	6249.83	274.51	6249.83	274.87	6249.84	280.52	6249.99						
280.97	6250.01	286.53	6250.1	287.46	6250.12	292.54	6250.26	293.95	6250.3						
298.55	6250.43	300.44	6250.48	304.56	6250.59	306.92	6250.66	310.57	6250.76						
313.41	6250.84	316.58	6250.92	319.9	6251.09	322.59	6251.23	326.39	6251.49						
328.6	6251.66	331.72	6251.86												

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
-88.21	.05	92.99	.025
		111.26	.05

Bank	Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	92.99	111.26		20.32	20.32	20.32		.1	.3
Left	Levee	Station=	80.47	Elevation=	6250.38				
Right	Levee	Station=	154.93	Elevation=	6248.46				

CROSS SECTION OUTPUT Profile #Sand Creek

E. G.	Elev (ft)	6250.00	Element	Left OB	Channel
Right OB					

Sol ace (v2).rep				
Vel Head (ft)	0.78	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6249.23	Reach Len. (ft)	20.32	20.32
20.32				
Crit W. S. (ft)	6249.23	Flow Area (sq ft)	7.49	85.99
154.57				
E. G. Slope (ft/ft)	0.002552	Area (sq ft)	7.49	85.99
154.57				
Q Total (cfs)	956.00	Flow (cfs)	13.49	703.75
238.76				
Top Width (ft)	170.75	Top Width (ft)	4.73	18.27
147.75				
Vel Total (ft/s)	3.85	Avg. Vel. (ft/s)	1.80	8.18
1.54				
Max Chl Dpth (ft)	5.56	Hydr. Depth (ft)	1.58	4.71
1.05				
Conv. Total (cfs)	18925.4	Conv. (cfs)	267.0	13931.8
4726.5				
Length Wtd. (ft)	20.32	Wetted Per. (ft)	5.69	19.11
148.09				
Min Ch El (ft)	6243.67	Shear (lb/sq ft)	0.21	0.72
0.17				
Alpha	3.36	Stream Power (lb/ft s)	331.72	80.47
154.93				
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.08	1.60
0.41				
C & E Loss (ft)	0.01	Cum SA (acres)	0.08	0.48
0.37				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth

for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated

water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program

defaulted to critical depth.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01

REACH: CH01

RS: 1009

INPUT

Description:

Station		Elevation		Data		num=		125	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6250.07	.44	6250.07	5.01	6250	6.45	6249.97	11.44	6249.85
12.46	6249.83	17.87	6249.69	18.46	6249.68	24.3	6249.53	24.47	6249.53
26.94	6249.47	30.47	6249.38	30.72	6249.37	36.48	6249.23	37.15	6249.22
42.49	6249.08	43.01	6249.07	43.58	6249.05	48.49	6248.86	50	6248.78
54.5	6248.53	56.43	6248.43	60.5	6248.21	62.86	6248.12	66.51	6248
90.53	6248	94.99	6248.13	96.57	6248.18	102.67	6248.28	102.69	6248.28
108.8	6248.4	110.39	6248.43	114.92	6248.52	118.08	6248.59	121.04	6248.64
125.78	6248.74	127.16	6248.76	132.52	6248.87	133.28	6248.88	133.47	6248.88
139.39	6248.97	141.17	6248.97	145.51	6249	151.63	6249	156.56	6249.21
157.75	6249.24	162.36	6249.77	163.86	6249.94	164.25	6249.98	169.98	6250.5
171.95	6250.55	176.1	6250.63	179.64	6248.45	182.22	6247.01	187.34	6243.78

Sol ace (v2). rep											
188.34	6243.16	192.2	6242.63	193.01	6242.54	194.45	6242.38	195.03	6242.54		
200.57	6244	202.73	6244.84	206.69	6246.64	210.42	6247.47	212.81	6248		
243.4	6248	248.9	6248.01	249.51	6248	251.89	6247.97	252.84	6247.96		
255.62	6247.94	256.46	6247.92	261.71	6247.8	263.87	6247.73	267.79	6247.61		
271.28	6247.65	273.88	6247.68	278.69	6247.74	279.97	6247.76	285.88	6247.83		
286.06	6247.83	292.14	6247.9	293.51	6247.9	298.23	6247.95	300.92	6247.95		
304.32	6247.98	308.33	6247.98	310.41	6248	316.5	6248	320	6248.11		
322.58	6248.2	323.15	6248.22	328.67	6248.45	330.55	6248.52	334.76	6248.69		
337.96	6248.82	340.85	6248.94	343.01	6249.05	345.37	6249.17	346.93	6249.25		
352.78	6249.54	353.02	6249.56	354.12	6249.61	359.11	6249.83	360.19	6249.87		
365.2	6249.98	367.6	6250	371.29	6250.01	375.01	6250.09	377.37	6250.14		
382.42	6250.26	383.46	6250.28	388.24	6250.39	389.55	6250.43	389.83	6250.43		
395.64	6250.58	397.24	6250.62	401.72	6250.73	404.65	6250.81	407.81	6250.9		
412.06	6251.12	413.9	6251.2	419.47	6251.66	419.99	6251.71	421.28	6251.77		

Manning's n Values num= 3
 Sta n Val Sta n Val Sta n Val
 0 .05 187.34 .025 202.73 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 187.34 202.73 20.66 20.66 20.66 .1 .3
 Left Levee Station= 176.28 El evati on= 6250.64
 Right Levee Station= 212.75 El evati on= 6247.98

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6249.72	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.91	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6248.82	Reach Len. (ft)	20.66	20.66
20.66				
Crit W. S. (ft)	6248.82	Flow Area (sq ft)	20.45	86.34
124.90				
E. G. Slope (ft/ft)	0.002216	Area (sq ft)	20.45	86.34
124.90				
Q Total (cfs)	956.00	Flow (cfs)	46.99	743.73
165.28				
Top Width (ft)	158.88	Top Width (ft)	8.30	15.39
135.19				
Vel Total (ft/s)	4.13	Avg. Vel. (ft/s)	2.30	8.61
1.32				
Max Chl Dpth (ft)	6.44	Hydr. Depth (ft)	2.46	5.61
0.92				
Conv. Total (cfs)	20308.4	Conv. (cfs)	998.2	15799.2
3511.0				
Length Wtd. (ft)	20.66	Wetted Per. (ft)	9.71	15.98
135.76				
Min Ch El (ft)	6242.38	Shear (lb/sq ft)	0.29	0.75
0.13				
Alpha	3.42	Stream Power (lb/ft s)	421.28	176.28
212.75				
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.07	1.56
0.34				
C & E Loss (ft)	0.04	Cum SA (acres)	0.08	0.47
0.31				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Solace (v2).rep

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1008

INPUT

Description:

Station		Elevation		Data		num= 140		Station		Elevation		Station		Elevation	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-199.62	6250.1	-199.53	6250.1	-195.45	6250.05	-193.32	6250.01	-189.45	6249.95						
-187.11	6249.89	-183.46	6249.8	-180.89	6249.74	-177.46	6249.66	-174.68	6249.59						
-171.46	6249.51	-168.47	6249.44	-165.47	6249.36	-162.25	6249.28	-159.47	6249.21						
-156.04	6249.13	-153.47	6249.07	-150.58	6248.94	-149.83	6248.91	-147.48	6248.81						
-143.61	6248.6	-141.48	6248.48	-137.4	6248.25	-135.48	6248.15	-131.19	6248.04						
-129.49	6248	-99.5	6248	-93.82	6248.09	-93.47	6248.09	-87.45	6248.2						
-86.69	6248.21	-81.42	6248.3	-79.95	6248.33	-75.39	6248.41	-73.21	6248.45						
-69.37	6248.52	-66.46	6248.57	-63.34	6248.63	-59.72	6248.69	-57.31	6248.74						
-52.98	6248.81	-51.29	6248.84	-46.24	6248.93	-45.26	6248.95	-39.49	6249						
-39.23	6249	-37.04	6248.94	-33.21	6248.86	-32.75	6248.87	-27.18	6249.08						
-26.01	6249.05	-21.15	6248.77	-19.27	6248.06	-15.13	6246.5	-12.52	6245.65						
-9.1	6244.45	-5.78	6242.95	-3.07	6242.45	-.58	6243.2	.96	6243.67						
2.95	6243.51	7.19	6244.77	7.71	6244.92	8.98	6245.74	14.5	6247.85						
15.01	6248	27.07	6248	28.07	6247.99	33.1	6247.8	34.86	6247.72						
39.13	6247.54	41.65	6247.44	45.16	6247.3	48.44	6247.19	51.2	6247.09						
55.23	6247	69.29	6247	73.1	6247.06	75.32	6247.09	75.6	6247.09						
81.35	6247.19	82.38	6247.21	87.38	6247.3	89.17	6247.33	93.41	6247.4						
95.96	6247.45	99.44	6247.51	102.75	6247.57	105.47	6247.61	109.54	6247.68						
111.5	6247.72	116.33	6247.8	117.53	6247.82	123.12	6247.91	123.56	6247.92						
127.08	6248.01	129.59	6248.08	129.91	6248.09	135.62	6248.42	136.7	6248.48						
141.65	6248.76	143.48	6248.87	147.68	6249.14	149.42	6249.27	150.27	6249.33						
153.71	6249.63	157.06	6249.85	159.74	6250.01	163.85	6250.08	165.77	6250.11						
170.64	6250.19	171.8	6250.21	177.43	6250.3	177.83	6250.3	181.05	6250.36						
183.86	6250.4	184.22	6250.41	189.9	6250.5	191.01	6250.52	195.93	6250.6						
197.8	6250.63	201.96	6250.7	204.59	6250.74	207.99	6250.8	211.37	6250.86						
214.02	6250.91	218.16	6251.05	220.05	6251.09	224.95	6251.67	226.08	6251.8						
231.74	6251.98	232.11	6252	262.26	6252	265.69	6252.02	268.29	6252.02						
272.47	6252.06	274.32	6252.06	279.26	6252.02	280.35	6252.01	282.05	6252.01						

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
-199.62	.05	-12.52	.025
		8.98	.05

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	-12.52	8.98		28.44	28.44	.1	.3
Left Levee		Station=	-26.98	Elevation=	6249.09		
Right Levee		Station=	15.38	Elevation=	6247.99		

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6249.21	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.78	Wt. n-Val.	0.050	0.025
0.050				

		Sol ace (v2).rep		
W. S. Elev (ft)	6248.42	Reach Len. (ft)	28.44	28.44
28.44				
Crit W. S. (ft)	6247.88	Flow Area (sq ft)	11.03	97.90
117.04				
E. G. Slope (ft/ft)	0.002504	Area (sq ft)	11.03	97.90
117.04				
Q Total (cfs)	956.00	Flow (cfs)	20.00	771.29
164.71				
Top Width (ft)	155.89	Top Width (ft)	7.71	21.50
126.68				
Vel Total (ft/s)	4.23	Avg. Vel. (ft/s)	1.81	7.88
1.41				
Max Chl Dpth (ft)	5.97	Hydr. Depth (ft)	1.43	4.55
0.92				
Conv. Total (cfs)	19104.9	Conv. (cfs)	399.6	15413.6
3291.7				
Length Wtd. (ft)	28.44	Wetted Per. (ft)	8.19	22.71
127.13				
Min Ch El (ft)	6242.45	Shear (lb/sq ft)	0.21	0.67
0.14				
Alpha	2.82	Stream Power (lb/ft s)	282.05	-26.98
15.38				
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.06	1.52
0.28				
C & E Loss (ft)	0.10	Cum SA (acres)	0.07	0.46
0.24				

Warning: Multiple water surfaces were found that could balance the energy equation. The program selected the water surface whose main channel velocity head was the closest to the previously computed cross section.

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
REACH: CH01

RS: 1007

INPUT

Description:

Station		Elevation Data		num=		191					
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
-530.82	6250.05	-529.72	6250.04	-525.13	6249.99	-523.76	6249.96	-519.14	6249.87		
-517.8	6249.83	-513.14	6249.73	-511.84	6249.7	-507.15	6249.6	-505.88	6249.57		
-501.16	6249.46	-499.92	6249.44	-495.16	6249.32	-493.96	6249.29	-489.17	6249.18		
-487.99	6249.15	-483.18	6249.04	-482.04	6248.99	-477.87	6248.8	-477.18	6248.77		
-476.11	6248.71	-471.19	6248.45	-470.17	6248.39	-465.2	6248.13	-464.24	6248.11		
-459.2	6248	-434.58	6248	-429.24	6248.05	-428.64	6248.06	-423.24	6248.17		
-422.71	6248.18	-417.25	6248.29	-416.78	6248.29	-411.25	6248.4	-410.85	6248.41		
-405.26	6248.49	-404.91	6248.5	-399.27	6248.58	-398.98	6248.58	-393.27	6248.69		
-393.05	6248.69	-387.28	6248.8	-387.12	6248.8	-381.29	6248.91	-381.18	6248.91		
-375.29	6249	-371.09	6248.95	-369.32	6248.93	-363.39	6248.63	-363.31	6248.62		
-357.45	6248.24	-357.31	6248.23	-351.52	6248	-351.32	6248	-345.59	6246.77		
-345.33	6246.73	-339.66	6244.41	-339.33	6244.29	-333.72	6242.2	-333.34	6242.04		
-327.87	6242.01	-327.79	6242.01	-327.35	6242.04	-321.86	6244.92	-321.35	6245.15		
-315.93	6247.11	-315.36	6247.27	-309.99	6247.68	-309.37	6247.73	-304.06	6247.41		
-303.37	6247.37	-298.13	6247.02	-297.38	6246.96	-292.19	6246.67	-291.39	6246.6		
-286.26	6246.03	-285.39	6246	-280.32	6246	-279.4	6246.02	-274.38	6246.19		
-273.41	6246.24	-268.43	6246.48	-267.41	6246.54	-262.49	6246.84	-261.42	6246.87		

Sol ace (v2). rep

-256.54	6247	-255.43	6247	-250.6	6247.02	-249.43	6247.02	-244.66	6247.11
-243.44	6247.13	-238.71	6247.22	-237.45	6247.25	-232.77	6247.34	-231.45	6247.37
-226.82	6247.46	-225.46	6247.49	-220.88	6247.57	-219.46	6247.6	-214.93	6247.69
-213.47	6247.72	-208.99	6247.82	-207.48	6247.85	-203.05	6247.94	-201.48	6247.98
-197.1	6248.6	-195.49	6248.79	-191.16	6249.09	-189.5	6249.23	-186.56	6249.38
-185.21	6249.44	-183.5	6249.53	-179.24	6249.74	-177.87	6249.8	-177.51	6249.82
-173.27	6249.93	-171.52	6250	-147.55	6250	-143.44	6250.01	-141.55	6250.01
-137.47	6250.06	-135.56	6250.06	-131.5	6250.11	-129.57	6250.1	-125.54	6250.15
-123.57	6250.17	-119.57	6250.22	-117.58	6250.25	-113.6	6250.37	-111.59	6250.45
-107.64	6250.66	-105.59	6250.72	-101.67	6250.83	-99.6	6251	-95.7	6251.03
-93.61	6251.03	-89.74	6251.09	-87.61	6251.09	-83.77	6251.15	-81.62	6251.18
-77.8	6251.19	-75.63	6251.21	-71.84	6251.18	-69.63	6251.17	-65.87	6251.12
-63.64	6251.1	-59.9	6251.07	-57.65	6251.05	-53.93	6251.03	-51.65	6251.02
-47.97	6251	-45.66	6250.99	-42	6250.97	-39.67	6250.96	-36.03	6250.95
-33.67	6250.94	-30.07	6250.93	-27.68	6250.92	-24.1	6250.91	-21.69	6250.9
-18.13	6250.88	-15.69	6250.87	-12.17	6250.87	-9.7	6250.86	-6.2	6250.87
-3.71	6250.88	-.23	6250.89	2.28	6250.9	5.74	6250.91	8.28	6250.92
11.7	6250.93	14.27	6250.93	17.67	6250.95	20.26	6250.96	23.64	6250.98
26.26	6251	29.6	6251.02	32.25	6251.03	35.57	6251.05	38.24	6251.06
41.54	6251.07	44.24	6251.07	47.5	6251.08	50.23	6251.08	53.47	6251.07
56.22	6251.06	59.44	6251.09	62.22	6251.09	65.4	6251.12	68.21	6251.13
69.98	6251.14								

Manning's n Values	num=	3			
Sta n Val	Sta n Val	Sta n Val			
-530.82	.05	-339.66	.025	-321.35	.05

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
-339.66	-321.35	19.26	19.26	19.26	.1	.3	
Left Levee	Station=	-376.72	Elevation=	6249.05			
Right Levee	Station=	-308.78	Elevation=	6247.71			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6249.05	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.44	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6248.61	Reach Len. (ft)	19.26	19.26
19.26				
Crit W. S. (ft)	6247.35	Flow Area (sq ft)	28.84	103.41
190.83				
E. G. Slope (ft/ft)	0.001237	Area (sq ft)	28.84	103.41
190.83				
Q Total (cfs)	956.00	Flow (cfs)	33.98	657.41
264.61				
Top Width (ft)	166.15	Top Width (ft)	23.50	18.31
124.34				
Vel Total (ft/s)	2.96	Avg. Vel. (ft/s)	1.18	6.36
1.39				
Max Chl Dpth (ft)	6.60	Hydr. Depth (ft)	1.23	5.65
1.53				
Conv. Total (cfs)	27179.6	Conv. (cfs)	966.0	18690.5
7523.0				
Length Wtd. (ft)	19.26	Wetted Per. (ft)	24.11	19.50
124.90				
Min Ch El (ft)	6242.01	Shear (lb/sq ft)	0.09	0.41
0.12				
Alpha	3.24	Stream Power (lb/ft s)	69.98	-376.72
-308.78				
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.05	1.45
0.18				

C & E Loss (ft) 0.16 Sol ace (v2). rep 0.00 Cum SA (acres) 0.06 0.45

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01 RS: 1006
 REACH: CH01

INPUT

Description:

Station		Elevation		Data		num= 182		Station		Elevation		Station		Elevation	
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
-295.58	6250.03	-293.14	6250.01	-292.22	6249.99	-287.36	6249.92	-286.23	6249.9						
-281.57	6249.81	-280.23	6249.79	-275.79	6249.71	-274.23	6249.68	-270	6249.59						
-268.24	6249.56	-264.22	6249.47	-262.24	6249.43	-258.43	6249.35	-256.24	6249.3						
-252.65	6249.22	-250.24	6249.17	-246.86	6249.09	-244.25	6249.04	-241.07	6248.9						
-238.71	6248.8	-238.24	6248.78	-235.47	6248.63	-232.24	6248.46	-229.86	6248.34						
-226.23	6248.15	-224.25	6248.1	-220.22	6248	-190.18	6248	-185	6248.15						
-184.17	6248.17	-179.39	6248.26	-178.16	6248.29	-173.79	6248.4	-172.15	6248.45						
-168.18	6248.54	-166.14	6248.59	-162.57	6248.67	-160.13	6248.72	-156.97	6248.78						
-154.13	6248.83	-151.36	6248.87	-148.12	6248.93	-145.75	6248.96	-142.11	6248.99						
-140.14	6249	-124.08	6249	-123.32	6248.95	-118.07	6248.92	-117.71	6248.9						
-112.68	6248.04	-112.11	6247.94	-112.07	6247.93	-106.5	6246.62	-106.06	6246.51						
-100.89	6245.05	-100.05	6244.84	-95.29	6243.25	-94.04	6242.89	-90.65	6242.34						
-89.68	6242.18	-88.71	6242.19	-88.03	6242.2	-84.1	6244.17	-82.02	6244.14						
-78.52	6244.92	-76.01	6246.47	-72.94	6246.63	-70	6246.51	-67.36	6246.2						
-63.99	6245.75	-61.78	6245.71	-57.98	6246.59	-56.2	6246.83	-51.97	6247.47						
-50.61	6247.53	-45.95	6247.36	-45.03	6247.36	-39.94	6247.07	-39.45	6247.07						
-33.93	6247	-33.07	6247	-28.29	6247.01	-27.92	6247	-3.88	6247						
-	39	6247.07	2.13	6247.1	5.2	6247.18	8.14	6247.27	10.78	6247.34					
14.15	6247.45	16.36	6247.52	20.17	6247.64	21.94	6247.69	26.18	6247.83						
27.52	6247.88	32.19	6248.05	33.1	6248.1	38.2	6248.34	38.68	6248.37						
44.21	6248.62	44.26	6248.63	44.97	6248.66	49.84	6248.88	50.22	6248.9						
53.11	6249.04	55.42	6249.15	56.23	6249.18	60.99	6249.41	61.29	6249.42						
62.24	6249.47	66.56	6249.68	68.26	6249.75	72.13	6249.88	74.27	6249.98						
77.7	6249.98	80.28	6250	94.4	6250	98.32	6249.93	99.97	6249.91						
104.33	6249.83	105.54	6249.83	110.34	6249.85	111.11	6249.85	116.35	6249.87						
116.68	6249.87	120.73	6249.89	122.24	6249.9	122.36	6249.9	127.81	6249.92						
128.38	6249.92	133.38	6249.94	134.39	6249.95	138.95	6250.04	140.4	6250.08						
144.52	6250.18	146.41	6250.24	150.09	6250.32	152.43	6250.36	155.66	6250.4						
158.44	6250.44	161.22	6250.47	164.45	6250.51	166.79	6250.51	170.46	6250.52						
172.36	6250.51	176.47	6250.49	177.93	6250.48	182.49	6250.48	183.5	6250.47						
188.5	6250.44	189.07	6250.43	194.51	6250.41	194.64	6250.41	196.22	6250.4						
200.2	6250.39	200.52	6250.39	205.77	6250.38	206.53	6250.38	211.34	6250.36						
212.55	6250.36	216.91	6250.34	218.56	6250.34	222.48	6250.33	224.57	6250.33						
228.05	6250.32	230.58	6250.31	233.62	6250.32	242.61	6250.32	244.75	6250.33						
248.62	6250.34	250.32	6250.34	254.63	6250.35	255.89	6250.35	260.64	6250.36						
261.46	6250.36	266.66	6250.37	267.03	6250.37	271.71	6250.38	278.17	6250.38						
278.68	6250.37	284.01	6250.37												

Manning's n Values		num= 3	
Sta	n Val	Sta	n Val
-295.58	.05	-100.05	.025
		-78.52	.05

Bank	Sta: Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	-100.05	-78.52		13.76	13.76		.1	.3
Left Levee		Station=	-123.45	Elevation=	6249.06			

Right Levee Station= -50.63 Solace (v2).rep
 Elevation= 6247.56

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6249.02	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.43	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6248.59	Reach Len. (ft)	13.76	13.76
13.76				
Crit W. S. (ft)	6247.48	Flow Area (sq ft)	27.12	110.25
175.16				
E. G. Slope (ft/ft)	0.001286	Area (sq ft)	27.12	110.25
175.16				
Q Total (cfs)	956.00	Flow (cfs)	40.55	679.02
236.43				
Top Width (ft)	159.55	Top Width (ft)	15.87	21.53
122.15				
Vel Total (ft/s)	3.06	Avg. Vel. (ft/s)	1.50	6.16
1.35				
Max Chl Dpth (ft)	6.41	Hydr. Depth (ft)	1.71	5.12
1.43				
Conv. Total (cfs)	26655.3	Conv. (cfs)	1130.6	18932.6
6592.0				
Length Wtd. (ft)	13.76	Wetted Per. (ft)	16.32	22.45
122.91				
Min Ch El (ft)	6242.18	Shear (lb/sq ft)	0.13	0.39
0.11				
Alpha	2.94	Stream Power (lb/ft s)	284.01	-123.45
-50.63				
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.04	1.40
0.10				
C & E Loss (ft)	0.00	Cum SA (acres)	0.05	0.44
0.11				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1005

INPUT

Description:

Station	Elevation	Data	num=	213
Sta	Elev	Sta	Elev	Sta
-976.11	6250.01	-974.94	6250	-972.32
6249.97	-969.58	6249.93	-966.28	6249.88
-964.23	6249.85	-960.24	6249.78	-958.87
6249.76	-954.2	6249.66	-953.51	6249.65
-948.15	6249.56	-942.79	6249.47	-942.11
6249.45	-937.43	6249.36	-936.08	6249.34
-931.88	6249.25	-930.06	6249.22	-926.32
6249.15	-924.05	6249.1	-920.76	6249.03
-918.04	6248.96	-915.2	6248.82	-913.28
6248.75	-912.02	6248.7	-909.65	6248.58
-906.01	6248.43	-904.09	6248.34	-900
6248.15	-898.53	6248.12	-893.98	6248
-863.92	6248	-859.64	6248.06	-857.9
6248.07	-854.08	6248.21	-851.89	6248.34
-848.52	6248.43	-845.88	6248.54	-842.96
6248.62	-839.86	6248.72	-837.41	6248.79
-833.85	6248.9	-831.85	6248.97	-827.84
6248.99	-826.29	6249	-797.77	6249
-792.95	6248.31	-791.76	6248.02	-787.39
6246.92	-785.74	6246.52	-781.84	6245.54
-779.73	6245.15	-779.34	6245.05	-776.26
6244.29	-773.72	6243.93	-770.65	6243.17
-767.71	6242.41	-765.05	6242.6	-763.28
6242.42	-761.7	6242.27	-759.45	6242.43

Sol ace (v2). rep

-755.69	6242.89	-753.85	6243.71	-749.69	6245.22	-748.25	6245.02	-743.68	6245.96
-742.64	6246.21	-737.67	6247.82	-737.04	6248	-731.66	6248	-731.44	6247.99
-728.45	6247.97	-725.84	6247.94	-725.65	6247.94	-720.24	6247.68	-719.64	6247.66
-714.64	6247.45	-713.63	6247.41	-709.03	6247.37	-707.62	6247.35	-703.43	6247.28
-701.61	6247.24	-697.83	6247.16	-695.6	6247.11	-692.23	6247.09	-689.6	6247.02
-686.63	6247.02	-683.59	6247	-681.02	6247	-677.58	6247.05	-675.42	6247.11
-671.57	6247.21	-669.82	6247.26	-665.56	6247.36	-664.22	6247.4	-659.55	6247.52
-658.62	6247.54	-653.54	6247.68	-653.01	6247.7	-647.53	6247.86	-647.41	6247.86
-645.76	6247.91	-641.81	6248.04	-641.52	6248.05	-636.21	6248.27	-635.52	6248.3
-630.61	6248.5	-629.51	6248.54	-625.01	6248.71	-623.5	6248.76	-619.4	6248.91
-617.49	6248.97	-613.8	6249.13	-613.28	6249.15	-611.48	6249.22	-608.2	6249.37
-605.47	6249.48	-602.6	6249.59	-599.54	6249.71	-599.46	6249.71	-596.99	6249.79
-593.45	6249.9	-591.37	6249.87	-587.45	6249.86	-585.75	6249.83	-581.44	6249.73
-580.13	6249.72	-575.43	6249.63	-574.51	6249.62	-569.42	6249.56	-568.9	6249.56
-563.42	6249.53	-563.28	6249.53	-561.29	6249.54	-557.66	6249.56	-557.41	6249.56
-552.04	6249.58	-551.4	6249.58	-546.42	6249.61	-545.39	6249.63	-540.8	6249.74
-539.39	6249.76	-535.19	6249.85	-533.38	6249.91	-529.57	6250.01	-527.37	6250.05
-523.95	6250.1	-521.36	6250.11	-518.33	6250.15	-515.36	6250.19	-512.71	6250.23
-509.35	6250.27	-507.1	6250.28	-503.34	6250.31	-501.48	6250.3	-497.33	6250.29
-495.86	6250.28	-491.33	6250.28	-490.24	6250.27	-484.62	6250.27	-479.31	6250.24
-479	6250.23	-474.56	6250.23	-473.39	6250.22	-473.3	6250.22	-467.77	6250.21
-467.3	6250.21	-462.15	6250.2	-461.29	6250.2	-456.53	6250.18	-455.28	6250.18
-450.91	6250.17	-449.27	6250.17	-445.29	6250.16	-443.27	6250.16	-439.68	6250.17
-431.25	6250.17	-428.44	6250.18	-425.24	6250.18	-422.82	6250.19	-419.24	6250.19
-417.2	6250.2	-413.23	6250.2	-411.58	6250.21	-394.73	6250.21	-389.2	6250.2
-387.83	6250.2	-383.49	6250.19	-383.19	6250.19	-377.87	6250.2	-377.18	6250.2
-372.26	6250.21	-371.18	6250.2	-366.64	6250.21	-353.15	6250.21	-349.78	6250.23
-341.14	6250.23	-338.55	6250.24	-335.13	6250.23	-332.93	6250.24	-327.31	6250.24
-323.12	6250.25	-310.45	6250.25	-305.09	6250.23	-304.84	6250.23	-301.11	6250.21
-299.22	6250.2	-299.09	6250.2	-293.6	6250.18	-293.08	6250.18	-287.98	6250.16
-287.07	6250.16	-282.36	6250.14	-280.69	6250.14				

Manning's n Values		num= 3	
Sta n Val	Sta n Val	Sta n Val	Sta n Val
-976.11 .05	-773.72 .025	-753.85 .05	

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff	Contr.	Expan.
-773.72	-753.85	17.89	17.89		.1	.3
Left Levee	Station=	-800.65	Elevation=	6249.02		
Right Levee	Station=	-737.54	Elevation=	6248.03		

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6249.01	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.43	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6248.58	Reach Len. (ft)	17.89	17.89
17.89				
Crit W. S. (ft)	6246.87	Flow Area (sq ft)	50.18	115.20
157.16				
E. G. Slope (ft/ft)	0.001029	Area (sq ft)	50.18	115.20
157.16				
Q Total (cfs)	956.00	Flow (cfs)	83.82	699.01
173.18				
Top Width (ft)	166.37	Top Width (ft)	21.11	19.87
125.39				
Vel Total (ft/s)	2.96	Avg. Vel. (ft/s)	1.67	6.07
1.10				
Max Chl Dpth (ft)	6.31	Hydr. Depth (ft)	2.38	5.80
1.25				
Conv. Total (cfs)	29803.7	Conv. (cfs)	2613.1	21791.8

Sol ace (v2).rep

5398.8					
Length Wtd. (ft)	17.89	Wetted Per. (ft)	21.64	20.29	
126.46					
Min Ch El (ft)	6242.27	Shear (lb/sq ft)	0.15	0.36	
0.08					
Alpha	3.12	Stream Power (lb/ft s)	-280.69	-800.65	
-737.54					
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.03	1.37	
0.05					
C & E Loss (ft)	0.01	Cum SA (acres)	0.05	0.43	
0.07					

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, energy was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1004

INPUT

Description:

Station		Elevation		Data		num=		156	
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
-146.11	6250.03	-144.42	6250.03	-139.57	6250	-138.37	6250	-134.23	6249.97
-132.33	6249.96	-128.9	6249.96	-126.28	6249.94	-123.56	6249.93	-120.23	6249.9
-118.23	6249.87	-114.19	6249.82	-112.9	6249.81	-108.14	6249.74	-107.56	6249.73
-103.19	6249.7	-102.23	6249.69	-102.1	6249.69	-96.89	6249.62	-96.05	6249.61
-91.56	6249.54	-90	6249.52	-86.22	6249.46	-83.96	6249.42	-80.89	6249.36
-77.91	6249.31	-75.55	6249.27	-71.87	6249.2	-70.22	6249.17	-65.82	6249.08
-64.88	6249.06	-59.77	6249	-59.55	6249	-57.83	6248.96	-54.21	6248.88
-53.73	6248.87	-50.9	6248.74	-48.88	6248.65	-47.68	6248.61	-43.54	6248.43
-41.63	6248.36	-38.21	6248.22	-35.59	6248.13	-32.87	6248.11	-29.54	6248
4.47	6248	6.73	6248.08	9.96	6248.19	12.74	6248.34	15.57	6248.53
18.75	6248.68	21.17	6248.77	24.76	6248.85	26.77	6248.84	30.77	6248.89
32.37	6248.89	36.78	6249	54.78	6249	60.38	6248.74	60.82	6248.74
65.98	6247.71	66.82	6247.42	71.58	6246.43	72.83	6246.22	77.19	6245.64
78.84	6245.2	82.79	6244.21	84.85	6243.94	88.39	6243.1	90.86	6242.62
93.99	6242.26	96.87	6242	99.59	6242	102.88	6242.16	105.2	6242.67
108.89	6243.1	110.8	6243.89	114.9	6245.27	116.4	6245.66	120.9	6247.51
122	6247.74	126.91	6248.96	127.6	6248.89	132.92	6248.95	133.21	6248.95
137.09	6248.87	138.81	6248.81	138.93	6248.82	144.41	6248.56	144.94	6248.62
150.01	6248.25	150.95	6248.21	155.61	6248.2	156.96	6247.93	161.21	6247.87
162.97	6247.75	166.82	6247.63	168.98	6247.54	172.42	6247.4	174.99	6247.28
178.02	6247.14	180.99	6247.01	183.62	6247.04	187	6247.04	189.22	6247.09
193.01	6247.19	194.83	6247.23	199.02	6247.34	200.51	6247.38	205.01	6247.5
206.43	6247.53	211.01	6247.65	212.36	6247.69	217	6247.82	218.28	6247.85
223	6248.01	224.21	6248.05	228.99	6248.16	230.13	6248.2	234.98	6248.36
236.06	6248.39	240.98	6248.52	241.98	6248.55	246.97	6248.67	247.9	6248.7
249.1	6248.74	252.96	6248.87	253.83	6248.9	258.96	6249.07	259.75	6249.1
264.95	6249.26	265.68	6249.28	270.94	6249.39	271.6	6249.39	276.94	6249.41
277.53	6249.41	282.93	6249.39	283.45	6249.38	288.92	6249.31	289.38	6249.31
294.92	6249.28	295.3	6249.28	300.91	6249.24	301.22	6249.24	306.91	6249.27
307.15	6249.27	312.9	6249.36	313.07	6249.36	318.89	6249.41	319	6249.41
324.89	6249.58	328.06	6249.74	330.85	6249.88	336.77	6249.99	336.87	6250
340.13	6250								

Manning's n Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val
-146.11	.05	84.85	.025	110.8	.05

Sol ace (v2).rep

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff Contr.	Expan.
	84.85	110.8		111.48	111.48	.1	.3
Ineffective Flow	num=		2				
Sta L	Sta R	Elev	Permanent				
67.58	81.09	6247.14	F				
99.48	111.11	6246.96	F				
Left Levee	Station=	54.64	Elevation=	6249.02			
Right Levee	Station=	132.7	Elevation=	6248.99			

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6248.98	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.40	Wt. n-Val.	0.050	0.025
0.050				
W. S. Elev (ft)	6248.59	Reach Len. (ft)	111.48	111.48
111.48				
Crit W. S. (ft)	6246.97	Flow Area (sq ft)	54.91	154.28
32.59				
E. G. Slope (ft/ft)	0.000780	Area (sq ft)	54.91	154.28
32.59				
Q Total (cfs)	956.00	Flow (cfs)	79.72	831.63
44.66				
Top Width (ft)	63.80	Top Width (ft)	23.25	25.95
14.60				
Vel Total (ft/s)	3.95	Avg. Vel. (ft/s)	1.45	5.39
1.37				
Max Chl Dpth (ft)	6.58	Hydr. Depth (ft)	2.36	5.95
2.23				
Conv. Total (cfs)	34226.5	Conv. (cfs)	2854.1	29773.7
1598.8				
Length Wtd. (ft)	111.48	Wetted Per. (ft)	23.74	26.37
15.37				
Min Ch El (ft)	6242.00	Shear (lb/sq ft)	0.11	0.28
0.10				
Alpha	1.63	Stream Power (lb/ft s)	340.13	54.64
132.70				
Frctn Loss (ft)		Cum Volume (acre-ft)	0.00	1.31
0.01				
C & E Loss (ft)		Cum SA (acres)	0.04	0.42
0.04				

Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

CULVERT

RIVER: Channel 01
 REACH: CH01 RS: 1003.56

INPUT

Description:
 Distance from Upstream XS = 6
 Deck/Roadway Width = 56
 Weir Coefficient = 2.6
 Upstream Deck/Roadway Coordinates
 num= 2
 Sta Hi Cord Lo Cord Sta Hi Cord Lo Cord

8.3 6247 0 177.68 6247 0

Upstream Bridge Cross Section Data

Station Elevation Data num= 19									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6249.5	63.93	6248	68.66	6247	73.38	6246	80.37	6242
84.72	6242	88.86	6242	94.06	6242	99.1	6242	105.34	6242
109.25	6242	112.6	6242	114.73	6242	116.96	6242	119.57	6242
122.19	6245	124.81	6247	134.25	6248	400	6250		

Manning's n Values num= 3					
Sta	n Val	Sta	n Val	Sta	n Val
0	.05	80.37	.025	119.57	.05

Bank Sta:	Left	Right	Coeff	Contr.	Expan.
	80.37	119.57		.1	.3

Ineffective Flow num= 2				
Sta L	Sta R	Elev	Permanent	
67.58	81.09	6247.14	F	
99.48	111.11	6246.96	F	
Left Levee	Station=	54.64	Elevation=	6249.02
Right Levee	Station=	132.7	Elevation=	6248.99

Downstream Deck/Roadway Coordinates num= 2							
Sta Hi	Cord	Lo	Cord	Sta Hi	Cord	Lo	Cord
-17.03	6247	0	300	6247	0		

Downstream Bridge Cross Section Data

Station Elevation Data num= 19									
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6248.5	21.8	6248	32.35	6247	40.76	6246	42.97	6245
45.2	6244	47.41	6243	49.66	6242	51.91	6241	54.17	6240
73.76	6239	184.57	6240	190.47	6241	195.17	6242	199.34	6243
203.17	6244	206.8	6245	210.31	6247	400	6249.5		

Manning's n Values num= 2			
Sta	n Val	Sta	n Val
0	.013	400	.05

Bank Sta:	Left	Right	Coeff	Contr.	Expan.
	0	400		.1	.3

Ineffective Flow num= 3				
Sta L	Sta R	Elev	Permanent	
32.52	51.28	6247	F	
73.8	116.58	6247	F	
133.46	279.06	6247	F	

- Upstream Embankment side slope = 3 hori z. to 1.0 verti cal
- Downstream Embankment side slope = 3 hori z. to 1.0 verti cal
- Maximum allowable submergence for weir flow = .98
- Elevation at which weir flow begins =
- Energy head used in spillway design =
- Spillway height used in design =
- Weir crest shape = Broad Crested

Number of Culverts = 3

Culvert Name	Shape	Ri se	Span
Culvert #1	Ci rcul ar	4	
FHWA Chart # 2 - Corrugated Metal Pipe Culvert			
FHWA Scale # 3 - Pipe projecting from fill			
Soluti on Cri teri a = Highest U. S. EG			

Sol ace (v2).rep

Culvert	Upstrm Dist	Length	Top n	Bottom n	Depth Blocked	Entrance Loss Coef
Exit Loss Coef	10	100	.024	.024	0	.5
.5						
Upstream	Elevation = 6241.91					
	Centerline Station = 116.96					
Downstream	Elevation = 6240.16					
	Centerline Station = 122.87					

Culvert Name	Shape	Rise	Span
Culvert #2	Circular	4	
FHWA Chart # 2 - Corrugated Metal Pipe Culvert			
FHWA Scale # 3 - Pipe projecting from fill			
Solution Criteria = Highest U.S. EG			

Culvert	Upstrm Dist	Length	Top n	Bottom n	Depth Blocked	Entrance Loss Coef
Exit Loss Coef	20	80	.024	.024	0	.5
.5						
Upstream	Elevation = 6242.06					
	Centerline Station = 94.06					
Downstream	Elevation = 6239.73					
	Centerline Station = 69.23					

Culvert Name	Shape	Rise	Span
Culvert #3	Circular	4	
FHWA Chart # 2 - Corrugated Metal Pipe Culvert			
FHWA Scale # 3 - Pipe projecting from fill			
Solution Criteria = Highest U.S. EG			

Culvert	Upstrm Dist	Length	Top n	Bottom n	Depth Blocked	Entrance Loss Coef
Exit Loss Coef	20	80	.024	.024	0	.5
.5						
Upstream	Elevation = 6242.32					
	Centerline Station = 81.95					
Downstream	Elevation = 6240.7					
	Centerline Station = 56.1					

CULVERT OUTPUT Profile #Sand Creek Culv Group: Culvert #1

Q Culv Group (cfs)	128.96	Culv Full Len (ft)	64.79
# Barrels	1	Culv Vel US (ft/s)	10.26
Q Barrel (cfs)	128.96	Culv Vel DS (ft/s)	11.33
E. G. US. (ft)	6248.99	Culv Inv El Up (ft)	6241.91
W. S. US. (ft)	6248.59	Culv Inv El Dn (ft)	6240.16
E. G. DS (ft)	6244.81	Culv Frctn Ls (ft)	2.61
W. S. DS (ft)	6244.28	Culv Exit Loss (ft)	0.75
Delta EG (ft)	4.18	Culv Entr Loss (ft)	0.82
Delta WS (ft)	4.30	Q Weir (cfs)	490.53
E. G. IC (ft)	6249.86	Weir Sta Lft (ft)	54.64
E. G. OC (ft)	6249.01	Weir Sta Rgt (ft)	132.70
Culvert Control	Outlet	Weir Submerg	0.00
Culv WS Inlet (ft)	6245.91	Weir Max Depth (ft)	1.98
Culv WS Outlet (ft)	6243.56	Weir Avg Depth (ft)	1.78
Culv Nml Depth (ft)	4.00	Weir Flow Area (sq ft)	138.97
Culv Crt Depth (ft)	3.40	Min El Weir Flow (ft)	6247.01

Warning: During subcritical analysis, while trying to calculate culvert and weir flow, the program could not get a balance of energy within the specified tolerance and number of trials. The program used the solution with the minimum error.

Note: The normal depth exceeds the height of the culvert. The program assumes that the normal depth is equal to the height

Sol ace (v2).rep

of the culvert.

Note: During supercritical analysis, the culvert direct step method went to critical depth. The program then assumed critical depth at the outlet.

Note: During the supercritical calculations a hydraulic jump occurred inside of the culvert.

Note: The culvert inlet is submerged and the culvert flows full over part or all of its length. Therefore, the culvert inlet

equations are not valid and the supercritical result has been discarded.

The outlet answer will be used.

CULVERT OUTPUT Profile #Sand Creek Culv Group: Culvert #2

Q Culv Group (cfs)	136.30	Culv Full Len (ft)	80.00
# Barrels	1	Culv Vel US (ft/s)	10.85
Q Barrel (cfs)	136.30	Culv Vel DS (ft/s)	10.85
E. G. US. (ft)	6248.99	Culv Inv El Up (ft)	6242.06
W. S. US. (ft)	6248.59	Culv Inv El Dn (ft)	6239.73
E. G. DS (ft)	6244.81	Culv Frctn Ls (ft)	2.51
W. S. DS (ft)	6244.28	Culv Exit Loss (ft)	0.75
Delta EG (ft)	4.18	Culv Entr Loss (ft)	0.91
Delta WS (ft)	4.30	Q Weir (cfs)	490.53
E. G. IC (ft)	6250.67	Weir Sta Lft (ft)	54.64
E. G. OC (ft)	6248.93	Weir Sta Rgt (ft)	132.70
Culvert Control	Outlet	Weir Submerg	0.00
Culv WS Inlet (ft)	6246.06	Weir Max Depth (ft)	1.98
Culv WS Outlet (ft)	6243.73	Weir Avg Depth (ft)	1.78
Culv Nml Depth (ft)	3.38	Weir Flow Area (sq ft)	138.97
Culv Crt Depth (ft)	3.48	Min El Weir Flow (ft)	6247.01

Warning: During subcritical analysis, while trying to calculate culvert and weir flow, the program could not get a balance of

energy within the specified tolerance and number of trials. The program used the solution with the minimum error.

Note: During the supercritical calculations a hydraulic jump occurred inside of the culvert.

Note: The culvert inlet is submerged and the culvert flows full over part or all of its length. Therefore, the culvert inlet

equations are not valid and the supercritical result has been discarded.

The outlet answer will be used.

CULVERT OUTPUT Profile #Sand Creek Culv Group: Culvert #3

Q Culv Group (cfs)	114.44	Culv Full Len (ft)	9.11
# Barrels	1	Culv Vel US (ft/s)	10.53
Q Barrel (cfs)	114.44	Culv Vel DS (ft/s)	10.53
E. G. US. (ft)	6248.99	Culv Inv El Up (ft)	6242.32
W. S. US. (ft)	6248.59	Culv Inv El Dn (ft)	6240.70
E. G. DS (ft)	6244.81	Culv Frctn Ls (ft)	2.69
W. S. DS (ft)	6244.28	Culv Exit Loss (ft)	0.84
Delta EG (ft)	4.18	Culv Entr Loss (ft)	0.64
Delta WS (ft)	4.30	Q Weir (cfs)	490.53
E. G. IC (ft)	6249.03	Weir Sta Lft (ft)	54.64
E. G. OC (ft)	6248.07	Weir Sta Rgt (ft)	132.70
Culvert Control	Inlet	Weir Submerg	0.00
Culv WS Inlet (ft)	6246.32	Weir Max Depth (ft)	1.98
Culv WS Outlet (ft)	6243.93	Weir Avg Depth (ft)	1.78
Culv Nml Depth (ft)	3.41	Weir Flow Area (sq ft)	138.97
Culv Crt Depth (ft)	3.23	Min El Weir Flow (ft)	6247.01

Warning: During subcritical analysis, while trying to calculate culvert and weir

flow, the program could not get a balance of energy within the specified tolerance and number of trials. The program used the solution with the minimum error.

Note: During supercritical analysis, the culvert direct step method went to critical depth. The program then assumed critical depth at the outlet.

Note: During the supercritical calculations a hydraulic jump occurred inside of the culvert.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1003

INPUT

Description:

Station		Elevation		Data		num=		43	
Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	6248.5	2.05	6248.48	3.57	6248.47	8.11	6248.43	9.56	6248.41
14.18	6248.31	15.55	6248.27	20.24	6248.07	21.55	6248.02	26.3	6247.57
27.54	6247.46	32.36	6246.97	33.53	6246.86	38.42	6246.29	39.53	6246.16
44.48	6244.15	45.52	6243.88	50.55	6241.62	51.51	6241.21	56.61	6240.35
57.51	6240	147.41	6240	147.54	6240.02	153.4	6240.03	153.6	6240.03
158.16	6240.18	159.89	6240.22	166.37	6241.25	168.29	6242.01	174.93	6244.79
176.68	6245.28	183.49	6246.84	185.08	6246.88	192.04	6247.02	193.47	6247.05
200.6	6247.27	201.86	6247.31	209.16	6247.55	210.26	6247.58	217.72	6247.79
218.65	6247.82	226.28	6248	280	6248				

Manning's n		Values		num=		3	
Sta	n Val	Sta	n Val	Sta	n Val	Sta	n Val
0	.013	45.52	.013	168.29	.05		

Bank Sta:	Left	Right	Lengths:	Left Channel	Right	Coeff	Contr.	Expan.
	45.52	168.29		87.73	87.73		.1	.3

Ineffective Flow		num=		3	
Sta L	Sta R	Elev	Permanent		
32.52	51.28	6247	F		
73.8	116.58	6247	F		
133.46	279.06	6247	F		

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6244.81	Element	Left OB	Channel
Right OB				
Vel Head (ft)	0.53	Wt. n-Val.		0.013
W. S. Elev (ft)	6244.28	Reach Len. (ft)	87.73	87.73
87.73				
Crit W. S. (ft)	6242.76	Flow Area (sq ft)		164.22
E. G. Slope (ft/ft)	0.000389	Area (sq ft)	0.30	497.29
6.16				
Q Total (cfs)	956.00	Flow (cfs)		956.00
Top Width (ft)	129.55	Top Width (ft)	1.36	122.77
5.42				
Vel Total (ft/s)	5.82	Avg. Vel. (ft/s)		5.82
Max Chl Dpth (ft)	4.28	Hydr. Depth (ft)		4.17
Conv. Total (cfs)	48483.8	Conv. (cfs)		48483.8

Sol ace (v2).rep

Length Wtd. (ft)	87.73	Wetted Per. (ft)	39.56
Min Ch El (ft)	6240.00	Shear (lb/sq ft)	0.10
Alpha	1.00	Stream Power (lb/ft s)	280.00
0.00			0.00
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.00
0.01			0.83
C & E Loss (ft)	0.09	Cum SA (acres)	0.01
0.01			0.23

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
 Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
 This may indicate the need for additional cross sections.
 Note: Multiple critical depths were found at this location. The critical depth with the lowest, valid, water surface was used.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1002

INPUT

Descripti on:

Stati on	El evati on	Data	num=	54
Sta	El ev	Sta	El ev	Sta
0	6247.2	4.15	6247.24	5.8
17.47	6247.35	19.22	6247.37	21
32.64	6247.5	34.53	6247.55	39.35
45.61	6247.84	50.85	6247.96	51.61
63.22	6247.31	63.6	6247.29	69.41
75.59	6245.03	81.59	6242.04	81.78
93.58	6239.86	94.15	6239.86	99.57
103.67	6239.88	106.38	6239.86	110.86
123.5	6245.03	127.64	6245.98	132.06
144.43	6247.22	149.17	6247.36	152.83
166.29	6247.82	169.62	6247.9	174.85
				200

Manni ng' s n	Val ues	num=	3
Sta	n Val	Sta	n Val
0	.05	81.59	.013
		114.94	.05

Bank Sta:	Left	Right	Lengths:	Left	Channel	Right	Coeff	Contr.	Expan.
	81.59	114.94		55.7	55.7	55.7		.1	.3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. El ev (ft)	6244.65	El ement	Left OB	Channel
Right OB				
Vel Head (ft)	1.46	Wt. n-Val.	0.050	0.013
0.050				
W. S. El ev (ft)	6243.20	Reach Len. (ft)	55.70	55.70
55.70				
Crit W. S. (ft)	6243.20	Flow Area (sq ft)	1.34	98.10
3.09				
E. G. Slope (ft/ft)	0.001748	Area (sq ft)	1.34	98.10

Sol ace (v2). rep

3. 09					
Q Total (cfs)	956. 00	Flow (cfs)	1. 08	951. 77	
3. 15					
Top Width (ft)	39. 52	Top Width (ft)	2. 32	33. 35	
3. 85					
Vel Total (ft/s)	9. 32	Avg. Vel. (ft/s)	0. 80	9. 70	
1. 02					
Max Chl Dpth (ft)	3. 36	Hydr. Depth (ft)	0. 58	2. 94	
0. 80					
Conv. Total (cfs)	22863. 1	Conv. (cfs)	25. 8	22762. 1	
75. 3					
Length Wtd. (ft)	55. 70	Wetted Per. (ft)	2. 59	33. 92	
4. 17					
Min Ch El (ft)	6239. 84	Shear (lb/sq ft)	0. 06	0. 32	
0. 08					
Alpha	1. 08	Stream Power (lb/ft s)	200. 00	0. 00	
0. 00					
Frctn Loss (ft)	0. 10	Cum Volume (acre-ft)	0. 00	0. 23	
0. 00					
C & E Loss (ft)	0. 00	Cum SA (acres)	0. 00	0. 08	
0. 00					

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
 Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01
 REACH: CH01 RS: 1001

INPUT

Description:

Station	Elevation	Data	num=	44					
Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev	Sta	El ev
0	6247. 19	. 61	6247. 2	4. 87	6247. 23	9. 07	6247. 27	11. 58	6247. 29
14. 13	6247. 31	18. 29	6247. 34	22. 39	6247. 38	25	6247. 42	27. 65	6247. 48
31. 71	6247. 55	35. 71	6247. 66	38. 42	6247. 74	39. 37	6247. 77	44. 91	6247. 92
47. 67	6247. 91	52. 54	6247. 66	57. 35	6247. 4	60. 18	6247. 27	67. 02	6246. 84
67. 82	6246. 77	70. 81	6246. 28	75. 45	6245. 57	76. 69	6245. 07	83. 09	6241. 79
86. 36	6240. 21	90. 72	6239	105. 7	6239	105. 99	6239. 01	107. 07	6239. 36
113. 63	6241. 18	115. 38	6242. 06	121. 26	6245. 03	125. 05	6246. 2	128. 9	6246. 77
134. 72	6247. 19	136. 54	6247. 26	143. 34	6247. 54	144. 17	6247. 58	144. 39	6247. 58
151. 81	6247. 88	154. 06	6247. 93	159. 44	6248	200	6248		

Manning's n Values	num=	3
Sta n Val	Sta n Val	Sta n Val
0 .05	83. 09 .013	115. 38 .05

Bank Sta: Left	Right	Lengths: Left	Channel	Right	Coeff	Contr.	Expan.
83. 09	115. 38	44. 32	44. 32	44. 32	. 1	. 3	
Right Levee	Station=	130. 04	Elevation=	6246. 94			

CROSS SECTION OUTPUT Profile #Sand Creek

Sol ace (v2). rep

E. G. El ev (ft)	6244. 20	El ement	Left OB	Channel
Right OB				
Vel Head (ft)	1. 47	Wt. n-Val .	0. 050	0. 013
0. 050				
W. S. El ev (ft)	6242. 73	Reach Len. (ft)	44. 32	44. 32
44. 32				
Crit W. S. (ft)	6242. 73	Flow Area (sq ft)	0. 86	98. 05
0. 44				
E. G. Slope (ft/ft)	0. 001723	Area (sq ft)	0. 86	98. 05
0. 44				
Q Total (cfs)	956. 00	Flow (cfs)	0. 59	955. 17
0. 24				
Top Width (ft)	35. 44	Top Width (ft)	1. 83	32. 29
1. 32				
Vel Total (ft/s)	9. 62	Avg. Vel. (ft/s)	0. 69	9. 74
0. 55				
Max Chl Dpth (ft)	3. 73	Hydr. Depth (ft)	0. 47	3. 04
0. 33				
Conv. Total (cfs)	23030. 7	Conv. (cfs)	14. 2	23010. 6
5. 8				
Length Wtd. (ft)	44. 32	Wetted Per. (ft)	2. 05	33. 33
1. 48				
Min Ch El (ft)	6239. 00	Shear (lb/sq ft)	0. 04	0. 32
0. 03				
Al pha	1. 02	Stream Power (lb/ft s)	200. 00	0. 00
130. 04				
Frctn Loss (ft)	0. 08	Cum Volume (acre-ft)	0. 00	0. 10
0. 00				
C & E Loss (ft)	0. 02	Cum SA (acres)	0. 00	0. 03
0. 00				

Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.

Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Channel 01

REACH: CH01

RS: 1000

INPUT

Description:

Station	Elevation	Data	num=	70	Station	Elevation	Station	Elevation	Station	Elevation
0	6247. 17	. 19	6247. 17	6. 42	6247. 22	6. 9	6247. 22	7. 36	6247. 23	
13. 61	6247. 28	19. 94	6247. 33	20. 32	6247. 33	20. 68	6247. 34	27. 03	6247. 43	
33. 46	6247. 58	33. 74	6247. 58	34	6247. 59	40. 31	6247. 77	40. 51	6247. 77	
43. 95	6247. 86	44. 25	6247. 87	46. 17	6247. 82	50. 27	6247. 9	51. 65	6247. 86	
56. 29	6247. 94	57. 12	6247. 94	62. 32	6247. 97	62. 6	6247. 97	65. 42	6247. 99	
68. 08	6247. 98	68. 34	6247. 98	73. 55	6247. 18	74. 36	6247. 19	79. 03	6245. 13	
80. 39	6244. 5	84. 51	6242. 13	86. 41	6241. 04	89. 98	6239. 94	92. 43	6239	
110. 5	6239	111. 89	6239. 55	116. 52	6240. 92	117. 37	6241. 31	122. 55	6244. 01	
122. 84	6244. 11	125. 81	6245. 22	128. 32	6246. 16	128. 57	6246. 24	133. 8	6246. 52	
134. 59	6246. 53	139. 27	6246. 53	140. 62	6246. 56	144. 75	6246. 46	146. 64	6246. 42	

Sol ace (v2).rep
 150.23 6246.38 152.66 6246.35 155.7 6246.31 158.68 6246.28 161.18 6246.25
 164.71 6246.21 166.66 6246.21 170.73 6246.16 172.13 6246.18 176.75 6246.08
 177.61 6246.11 182.78 6246.5 183.09 6246.52 186.2 6246.7 188.56 6246.84
 188.8 6246.86 194.04 6246.99 194.82 6247.04 199.52 6247.06 200 6247.07

Manning's n Values num= 3
 Station Val Station Val Station Val
 0 .05 0 .013 200 .05

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
 0 200 0 0 0 .1 .3

CROSS SECTION OUTPUT Profile #Sand Creek

E. G. Elev (ft)	6244.00	Element	Left OB	Channel
Right OB				
Vel Head (ft)	1.41	Wt. n-Val.		0.013
W. S. Elev (ft)	6242.59	Reach Len. (ft)		
Crit W. S. (ft)	6242.59	Flow Area (sq ft)		100.49
E. G. Slope (ft/ft)	0.001866	Area (sq ft)		100.49
Q Total (cfs)	956.00	Flow (cfs)		956.00
Top Width (ft)	36.12	Top Width (ft)		36.12
Vel Total (ft/s)	9.51	Avg. Vel. (ft/s)		9.51
Max Chl Dpth (ft)	3.59	Hydr. Depth (ft)		2.78
Conv. Total (cfs)	22130.3	Conv. (cfs)		22130.3
Length Wtd. (ft)		Wetted Per. (ft)		37.58
Min Ch El (ft)	6239.00	Shear (lb/sq ft)		0.31
Alpha	1.00	Stream Power (lb/ft s)	200.00	0.00
0.00		Cum Volume (acre-ft)		
Frctn Loss (ft)		Cum SA (acres)		
C & E Loss (ft)				

SUMMARY OF MANNING'S N VALUES

River: Channel 01

Reach	River Sta.	n1	n2	n3
CH01	1053	.05	.025	.05
CH01	1052	.05	.025	.05
CH01	1051	.05	.025	.05
CH01	1050	.05	.025	.05
CH01	1049	.05	.025	.05
CH01	1048	.05	.025	.05
CH01	1047	.05	.025	.05

		Sol ace (v2). rep		
CH01	1046	.05	.025	.05
CH01	1045	.05	.025	.05
CH01	1044	.05	.025	.05
CH01	1043	.05	.025	.05
CH01	1042	.05	.025	.05
CH01	1041	.05	.025	.05
CH01	1040	.05	.025	.05
CH01	1039	.05	.025	.05
CH01	1038	.05	.025	.05
CH01	1037	.05	.025	.05
CH01	1036	.05	.025	.05
CH01	1035	.05	.025	.05
CH01	1034	.05	.025	.05
CH01	1033	.05	.025	.05
CH01	1032	.05	.025	.05
CH01	1031	.05	.025	.05
CH01	1030	.05	.025	.05
CH01	1029	.05	.025	.05
CH01	1028	.05	.025	.05
CH01	1027	.05	.025	.05
CH01	1026	.05	.025	.05
CH01	1025	.05	.025	.05
CH01	1024	.05	.025	.05
CH01	1023	.05	.025	.05
CH01	1022	.05	.025	.05
CH01	1021	.05	.025	.05
CH01	1020	.05	.025	.05
CH01	1019	.05	.025	.05
CH01	1018	.05	.025	.05
CH01	1017	.05	.025	.05
CH01	1016	.05	.025	.05
CH01	1015	.05	.025	.05
CH01	1014	.05	.025	.05
CH01	1013	.05	.025	.05
CH01	1012	.05	.025	.05
CH01	1011	.05	.025	.05
CH01	1010	.05	.025	.05
CH01	1009	.05	.025	.05
CH01	1008	.05	.025	.05
CH01	1007	.05	.025	.05
CH01	1006	.05	.025	.05
CH01	1005	.05	.025	.05
CH01	1004	.05	.025	.05
CH01	1003.56			
			Cul vert	
CH01	1003	.013	.013	.05
CH01	1002	.05	.013	.05
CH01	1001	.05	.013	.05
CH01	1000	.05	.013	.05

SUMMARY OF REACH LENGTHS

Ri ver: Channel 01

Reach	Ri ver Sta.	Left	Channel	Ri ght
CH01	1053	61.75	61.75	61.75
CH01	1052	14	14	14
CH01	1051	16.76	16.76	16.76
CH01	1050	45.02	45.02	45.02
CH01	1049	32.7	32.7	32.7

Sol ace (v2). rep

CH01	1048	22.36	22.36	22.36
CH01	1047	23.82	23.82	23.82
CH01	1046	24.71	24.71	24.71
CH01	1045	51.49	51.49	51.49
CH01	1044	24.27	24.27	24.27
CH01	1043	39.09	39.09	39.09
CH01	1042	39.32	39.32	39.32
CH01	1041	30.04	30.04	30.04
CH01	1040	12.65	12.65	12.65
CH01	1039	28.43	28.43	28.43
CH01	1038	26.37	26.37	26.37
CH01	1037	21.74	21.74	21.74
CH01	1036	41.42	41.42	41.42
CH01	1035	36.85	36.85	36.85
CH01	1034	13.77	13.77	13.77
CH01	1033	26.23	26.23	26.23
CH01	1032	25.6	25.6	25.6
CH01	1031	34.57	34.57	34.57
CH01	1030	24.7	24.7	24.7
CH01	1029	24.82	24.82	24.82
CH01	1028	50.43	50.43	50.43
CH01	1027	25.05	25.05	25.05
CH01	1026	27.07	27.07	27.07
CH01	1025	31.34	31.34	31.34
CH01	1024	16.62	16.62	16.62
CH01	1023	20.93	20.93	20.93
CH01	1022	26.45	26.45	26.45
CH01	1021	19.84	19.84	19.84
CH01	1020	32.65	32.65	32.65
CH01	1019	27.27	27.27	27.27
CH01	1018	36.97	36.97	36.97
CH01	1017	35.86	35.86	35.86
CH01	1016	34.77	34.77	34.77
CH01	1015	47.19	47.19	47.19
CH01	1014	18.01	18.01	18.01
CH01	1013	18.13	18.13	18.13
CH01	1012	38.75	38.75	38.75
CH01	1011	22.91	22.91	22.91
CH01	1010	20.32	20.32	20.32
CH01	1009	20.66	20.66	20.66
CH01	1008	28.44	28.44	28.44
CH01	1007	19.26	19.26	19.26
CH01	1006	13.76	13.76	13.76
CH01	1005	17.89	17.89	17.89
CH01	1004	111.48	111.48	111.48
CH01	1003.56	Cul vert		
CH01	1003	87.73	87.73	87.73
CH01	1002	55.7	55.7	55.7
CH01	1001	44.32	44.32	44.32
CH01	1000	0	0	0

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS


Ri ver: Channel 01

Reach	Ri ver Sta.	Contr.	Expan.
CH01	1053	.1	.3
CH01	1052	.1	.3
CH01	1051	.1	.3

		Sol ace (v2). rep	
CH01	1050	.1	.3
CH01	1049	.1	.3
CH01	1048	.1	.3
CH01	1047	.1	.3
CH01	1046	.1	.3
CH01	1045	.1	.3
CH01	1044	.1	.3
CH01	1043	.1	.3
CH01	1042	.1	.3
CH01	1041	.1	.3
CH01	1040	.1	.3
CH01	1039	.1	.3
CH01	1038	.1	.3
CH01	1037	.1	.3
CH01	1036	.1	.3
CH01	1035	.1	.3
CH01	1034	.1	.3
CH01	1033	.1	.3
CH01	1032	.1	.3
CH01	1031	.1	.3
CH01	1030	.1	.3
CH01	1029	.1	.3
CH01	1028	.1	.3
CH01	1027	.1	.3
CH01	1026	.1	.3
CH01	1025	.1	.3
CH01	1024	.1	.3
CH01	1023	.1	.3
CH01	1022	.1	.3
CH01	1021	.1	.3
CH01	1020	.1	.3
CH01	1019	.1	.3
CH01	1018	.1	.3
CH01	1017	.1	.3
CH01	1016	.1	.3
CH01	1015	.1	.3
CH01	1014	.1	.3
CH01	1013	.1	.3
CH01	1012	.1	.3
CH01	1011	.1	.3
CH01	1010	.1	.3
CH01	1009	.1	.3
CH01	1008	.1	.3
CH01	1007	.1	.3
CH01	1006	.1	.3
CH01	1005	.1	.3
CH01	1004	.1	.3
CH01	1003.56	Cul vert	
CH01	1003	.1	.3
CH01	1002	.1	.3
CH01	1001	.1	.3
CH01	1000	.1	.3

HEC-RAS Model Plan: Default Scenario 6/24/2020


Channel 01 CH01



Legend	
EG Sand Creek	(dotted green line)
WS Sand Creek	(solid blue line)
Crit Sand Creek	(dotted red line with '+' markers)
Ground	(solid black line)
Left Levee	(dashed magenta line with square markers)
Right Levee	(solid purple line with square markers)


HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1053




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1052




HEC-RAS Model Plan: Default Scenario 6/24/2020


RS = 1051




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1050









HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1041




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1040




HEC-RAS Model Plan: Default Scenario 6/24/2020


RS = 1039





HEC-RAS Model Plan: Default Scenario 6/24/2020


RS = 1038



















HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1017
 .05 | .05
 0 | 0
 2 | 2
 5 | 5




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1016
 .05 | .05
 0 | 0
 2 | 2
 5 | 5




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1015
 .05 | .05
 0 | 0
 2 | 2
 5 | 5




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1014
 .05 | .05
 0 | 0
 2 | 2
 5 | 5




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1013




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1012




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1011




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1010




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1009




HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1008




HEC-RAS Model Plan: Default Scenario 6/24/2020





RS = 1007







HEC-RAS Model Plan: Default Scenario 6/24/2020

RS = 1006







Plan: Default Scenario Channel 01 CH01 RS: 1053 Profile: Sand Creek

E.G. Elev (ft)	6269.74	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.47	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6269.27	Reach Len. (ft)	61.75	61.75	61.75
Crit W.S. (ft)	6269.27	Flow Area (sq ft)	2.93	57.96	205.00
E.G. Slope (ft/ft)	0.003352	Area (sq ft)	2.93	57.96	205.00
Q Total (cfs)	760.00	Flow (cfs)	4.23	421.31	334.46
Top Width (ft)	243.35	Top Width (ft)	3.41	17.98	221.96
Vel Total (ft/s)	2.86	Avg. Vel. (ft/s)	1.44	7.27	1.63
Max Chl Dpth (ft)	4.27	Hydr. Depth (ft)	0.86	3.22	0.92
Conv. Total (cfs)	13126.5	Conv. (cfs)	73.0	7276.8	5776.7
Length Wtd. (ft)	61.75	Wetted Per. (ft)	3.82	18.88	222.04
Min Ch El (ft)	6265.00	Shear (lb/sq ft)	0.16	0.64	0.19
Alpha	3.73	Stream Power (lb/ft s)	334.77	0.00	0.00
Frctn Loss (ft)	0.15	Cum Volume (acre-ft)	0.72	4.57	1.23
C & E Loss (ft)	0.02	Cum SA (acres)	0.34	1.09	1.04

Plan: Default Scenario Channel 01 CH01 RS: 1052 Profile: Sand Creek

E.G. Elev (ft)	6264.43	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.67	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6263.76	Reach Len. (ft)	14.00	14.00	14.00
Crit W.S. (ft)	6262.24	Flow Area (sq ft)	4.93	113.69	1.96
E.G. Slope (ft/ft)	0.001753	Area (sq ft)	4.93	113.69	1.96
Q Total (cfs)	760.00	Flow (cfs)	6.40	751.79	1.80
Top Width (ft)	30.96	Top Width (ft)	3.86	24.38	2.72
Vel Total (ft/s)	6.30	Avg. Vel. (ft/s)	1.30	6.61	0.92
Max Chl Dpth (ft)	5.75	Hydr. Depth (ft)	1.28	4.66	0.72
Conv. Total (cfs)	18150.7	Conv. (cfs)	152.9	17954.7	43.1
Length Wtd. (ft)	14.00	Wetted Per. (ft)	4.63	26.25	3.09
Min Ch El (ft)	6258.01	Shear (lb/sq ft)	0.12	0.47	0.07
Alpha	1.09	Stream Power (lb/ft s)	200.00	75.59	0.00
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.71	4.45	1.08
C & E Loss (ft)	0.08	Cum SA (acres)	0.34	1.06	0.88

Plan: Default Scenario Channel 01 CH01 RS: 1051 Profile: Sand Creek

E.G. Elev (ft)	6264.31	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.50	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6262.80	Reach Len. (ft)	16.76	16.76	16.76
Crit W.S. (ft)	6262.80	Flow Area (sq ft)	1.37	76.50	1.61
E.G. Slope (ft/ft)	0.006159	Area (sq ft)	1.37	76.50	1.61
Q Total (cfs)	760.00	Flow (cfs)	2.10	755.28	2.62
Top Width (ft)	28.51	Top Width (ft)	2.30	23.73	2.47
Vel Total (ft/s)	9.56	Avg. Vel. (ft/s)	1.53	9.87	1.63
Max Chl Dpth (ft)	4.23	Hydr. Depth (ft)	0.60	3.22	0.65
Conv. Total (cfs)	9683.8	Conv. (cfs)	26.7	9623.7	33.4
Length Wtd. (ft)	16.76	Wetted Per. (ft)	2.59	24.84	2.76
Min Ch El (ft)	6258.57	Shear (lb/sq ft)	0.20	1.18	0.22
Alpha	1.06	Stream Power (lb/ft s)	200.00	71.68	0.00
Frctn Loss (ft)	0.10	Cum Volume (acre-ft)	0.71	4.42	1.08
C & E Loss (ft)	0.00	Cum SA (acres)	0.33	1.06	0.88

Plan: Default Scenario Channel 01 CH01 RS: 1050 Profile: Sand Creek

E.G. Elev (ft)	6263.15	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.52	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6261.64	Reach Len. (ft)	45.02	45.02	45.02
Crit W.S. (ft)	6261.64	Flow Area (sq ft)	1.40	75.88	2.51
E.G. Slope (ft/ft)	0.006075	Area (sq ft)	1.40	75.88	2.51
Q Total (cfs)	760.00	Flow (cfs)	2.15	753.06	4.79
Top Width (ft)	28.39	Top Width (ft)	2.32	23.22	2.85
Vel Total (ft/s)	9.53	Avg. Vel. (ft/s)	1.53	9.92	1.91
Max Chl Dpth (ft)	4.58	Hydr. Depth (ft)	0.60	3.27	0.88
Conv. Total (cfs)	9750.9	Conv. (cfs)	27.6	9661.9	61.5
Length Wtd. (ft)	45.02	Wetted Per. (ft)	2.60	24.20	3.34
Min Ch El (ft)	6257.06	Shear (lb/sq ft)	0.20	1.19	0.28
Alpha	1.08	Stream Power (lb/ft s)	200.00	37.06	0.00
Frctn Loss (ft)	0.27	Cum Volume (acre-ft)	0.71	4.39	1.08
C & E Loss (ft)	0.00	Cum SA (acres)	0.33	1.05	0.88

Plan: Default Scenario Channel 01 CH01 RS: 1049 Profile: Sand Creek

E.G. Elev (ft)	6262.54	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.56	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6260.98	Reach Len. (ft)	32.70	32.70	32.70
Crit W.S. (ft)	6260.98	Flow Area (sq ft)	3.04	73.54	4.24
E.G. Slope (ft/ft)	0.005893	Area (sq ft)	3.04	73.54	4.24
Q Total (cfs)	760.00	Flow (cfs)	5.84	745.06	9.10
Top Width (ft)	29.13	Top Width (ft)	3.54	21.48	4.10
Vel Total (ft/s)	9.40	Avg. Vel. (ft/s)	1.92	10.13	2.15
Max Chl Dpth (ft)	3.98	Hydr. Depth (ft)	0.86	3.42	1.03
Conv. Total (cfs)	9900.2	Conv. (cfs)	76.1	9705.6	118.6
Length Wtd. (ft)	32.70	Wetted Per. (ft)	3.94	22.23	4.64
Min Ch El (ft)	6257.00	Shear (lb/sq ft)	0.28	1.22	0.34
Alpha	1.14	Stream Power (lb/ft s)	200.00	45.99	0.00
Frctn Loss (ft)	0.20	Cum Volume (acre-ft)	0.71	4.31	1.08
C & E Loss (ft)	0.01	Cum SA (acres)	0.33	1.02	0.87

Plan: Default Scenario Channel 01 CH01 RS: 1048 Profile: Sand Creek

E.G. Elev (ft)	6261.19	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.62	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6259.57	Reach Len. (ft)	22.36	22.36	22.36
Crit W.S. (ft)	6259.57	Flow Area (sq ft)	2.31	72.67	3.59
E.G. Slope (ft/ft)	0.006100	Area (sq ft)	2.31	72.67	3.59
Q Total (cfs)	760.00	Flow (cfs)	4.18	748.00	7.82
Top Width (ft)	27.47	Top Width (ft)	2.96	21.24	3.26
Vel Total (ft/s)	9.67	Avg. Vel. (ft/s)	1.81	10.29	2.18
Max Chl Dpth (ft)	4.44	Hydr. Depth (ft)	0.78	3.42	1.10
Conv. Total (cfs)	9731.0	Conv. (cfs)	53.5	9577.4	100.2
Length Wtd. (ft)	22.36	Wetted Per. (ft)	3.35	22.01	3.93
Min Ch El (ft)	6255.13	Shear (lb/sq ft)	0.26	1.26	0.35
Alpha	1.11	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.14	Cum Volume (acre-ft)	0.70	4.26	1.08
C & E Loss (ft)	0.03	Cum SA (acres)	0.33	1.01	0.87

Plan: Default Scenario Channel 01 CH01 RS: 1047 Profile: Sand Creek

E.G. Elev (ft)	6259.87	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.52	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6258.35	Reach Len. (ft)	23.82	23.82	23.82
Crit W.S. (ft)	6258.35	Flow Area (sq ft)	0.97	76.09	1.96
E.G. Slope (ft/ft)	0.006418	Area (sq ft)	0.97	76.09	1.96
Q Total (cfs)	760.00	Flow (cfs)	1.30	755.09	3.61
Top Width (ft)	28.83	Top Width (ft)	2.13	24.36	2.34
Vel Total (ft/s)	9.62	Avg. Vel. (ft/s)	1.34	9.92	1.84
Max Chl Dpth (ft)	4.33	Hydr. Depth (ft)	0.46	3.12	0.84
Conv. Total (cfs)	9486.4	Conv. (cfs)	16.2	9425.1	45.1
Length Wtd. (ft)	23.82	Wetted Per. (ft)	2.32	25.29	2.88
Min Ch El (ft)	6254.02	Shear (lb/sq ft)	0.17	1.21	0.27
Alpha	1.06	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.15	Cum Volume (acre-ft)	0.70	4.22	1.07
C & E Loss (ft)	0.02	Cum SA (acres)	0.33	1.00	0.87

Plan: Default Scenario Channel 01 CH01 RS: 1046 Profile: Sand Creek

E.G. Elev (ft)	6258.82	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.45	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6257.37	Reach Len. (ft)	24.71	24.71	24.71
Crit W.S. (ft)	6257.37	Flow Area (sq ft)	1.91	77.36	2.64
E.G. Slope (ft/ft)	0.006297	Area (sq ft)	1.91	77.36	2.64
Q Total (cfs)	760.00	Flow (cfs)	3.31	751.54	5.15
Top Width (ft)	31.36	Top Width (ft)	2.69	25.62	3.04
Vel Total (ft/s)	9.28	Avg. Vel. (ft/s)	1.73	9.71	1.95
Max Chl Dpth (ft)	3.90	Hydr. Depth (ft)	0.71	3.02	0.87
Conv. Total (cfs)	9577.6	Conv. (cfs)	41.8	9471.0	64.9
Length Wtd. (ft)	24.71	Wetted Per. (ft)	3.05	26.17	3.50
Min Ch El (ft)	6253.47	Shear (lb/sq ft)	0.25	1.16	0.30
Alpha	1.08	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.14	Cum Volume (acre-ft)	0.70	4.18	1.07
C & E Loss (ft)	0.06	Cum SA (acres)	0.33	0.98	0.87

Plan: Default Scenario Channel 01 CH01 RS: 1045 Profile: Sand Creek

E.G. Elev (ft)	6258.41	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.24	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6257.17	Reach Len. (ft)	51.49	51.49	51.49
Crit W.S. (ft)	6256.95	Flow Area (sq ft)	4.98	80.49	7.13
E.G. Slope (ft/ft)	0.004864	Area (sq ft)	4.98	80.49	7.13
Q Total (cfs)	760.00	Flow (cfs)	10.36	732.40	17.24
Top Width (ft)	33.75	Top Width (ft)	4.41	24.51	4.83
Vel Total (ft/s)	8.21	Avg. Vel. (ft/s)	2.08	9.10	2.42
Max Chl Dpth (ft)	4.08	Hydr. Depth (ft)	1.13	3.28	1.48
Conv. Total (cfs)	10897.6	Conv. (cfs)	148.6	10501.8	247.3
Length Wtd. (ft)	51.49	Wetted Per. (ft)	4.96	24.75	5.66
Min Ch El (ft)	6253.08	Shear (lb/sq ft)	0.31	0.99	0.38
Alpha	1.19	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.13	Cum Volume (acre-ft)	0.70	4.13	1.07
C & E Loss (ft)	0.20	Cum SA (acres)	0.32	0.97	0.87

Plan: Default Scenario Channel 01 CH01 RS: 1044 Profile: Sand Creek

E.G. Elev (ft)	6258.08	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.59	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6257.49	Reach Len. (ft)	24.27	24.27	24.27
Crit W.S. (ft)		Flow Area (sq ft)	9.31	117.56	7.16
E.G. Slope (ft/ft)	0.001547	Area (sq ft)	9.31	117.56	7.16
Q Total (cfs)	760.00	Flow (cfs)	13.38	736.59	10.02
Top Width (ft)	36.72	Top Width (ft)	6.11	26.27	4.34
Vel Total (ft/s)	5.67	Avg. Vel. (ft/s)	1.44	6.27	1.40
Max Chl Dpth (ft)	5.48	Hydr. Depth (ft)	1.52	4.48	1.65
Conv. Total (cfs)	19325.7	Conv. (cfs)	340.3	18730.5	254.9
Length Wtd. (ft)	24.27	Wetted Per. (ft)	6.83	26.79	5.47
Min Ch El (ft)	6252.01	Shear (lb/sq ft)	0.13	0.42	0.13
Alpha	1.19	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.69	4.02	1.06
C & E Loss (ft)	0.07	Cum SA (acres)	0.32	0.94	0.86

Plan: Default Scenario Channel 01 CH01 RS: 1043 Profile: Sand Creek

E.G. Elev (ft)	6257.98	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.35	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6257.64	Reach Len. (ft)	39.09	39.09	39.09
Crit W.S. (ft)		Flow Area (sq ft)	24.34	142.82	19.11
E.G. Slope (ft/ft)	0.000808	Area (sq ft)	24.34	142.82	19.11
Q Total (cfs)	760.00	Flow (cfs)	33.01	699.46	27.52
Top Width (ft)	47.17	Top Width (ft)	11.26	28.66	7.25
Vel Total (ft/s)	4.08	Avg. Vel. (ft/s)	1.36	4.90	1.44
Max Chl Dpth (ft)	5.63	Hydr. Depth (ft)	2.16	4.98	2.63
Conv. Total (cfs)	26741.0	Conv. (cfs)	1161.6	24611.1	968.4
Length Wtd. (ft)	39.09	Wetted Per. (ft)	11.96	28.93	8.58
Min Ch El (ft)	6252.00	Shear (lb/sq ft)	0.10	0.25	0.11
Alpha	1.34	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.68	3.94	1.05
C & E Loss (ft)	0.06	Cum SA (acres)	0.31	0.92	0.86

Plan: Default Scenario Channel 01 CH01 RS: 1042 Profile: Sand Creek

E.G. Elev (ft)	6257.90	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.13	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6257.77	Reach Len. (ft)	39.32	39.32	39.32
Crit W.S. (ft)		Flow Area (sq ft)	26.26	238.63	31.57
E.G. Slope (ft/ft)	0.000275	Area (sq ft)	26.26	238.63	31.57
Q Total (cfs)	760.00	Flow (cfs)	21.57	712.12	26.31
Top Width (ft)	70.08	Top Width (ft)	11.46	44.87	13.74
Vel Total (ft/s)	2.56	Avg. Vel. (ft/s)	0.82	2.98	0.83
Max Chl Dpth (ft)	6.29	Hydr. Depth (ft)	2.29	5.32	2.30
Conv. Total (cfs)	45792.3	Conv. (cfs)	1299.8	42907.3	1585.2
Length Wtd. (ft)	39.32	Wetted Per. (ft)	12.22	45.35	14.37
Min Ch El (ft)	6251.48	Shear (lb/sq ft)	0.04	0.09	0.04
Alpha	1.28	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.01	Cum Volume (acre-ft)	0.66	3.77	1.03
C & E Loss (ft)	0.01	Cum SA (acres)	0.30	0.89	0.85

Plan: Default Scenario Channel 01 CH01 RS: 1041 Profile: Sand Creek

E.G. Elev (ft)	6257.87	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.24	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6257.64	Reach Len. (ft)	30.04	30.04	30.04
Crit W.S. (ft)	6254.94	Flow Area (sq ft)	28.01	179.84	9.95
E.G. Slope (ft/ft)	0.000520	Area (sq ft)	28.01	179.84	9.95
Q Total (cfs)	760.00	Flow (cfs)	31.91	719.35	8.74
Top Width (ft)	52.54	Top Width (ft)	12.13	34.63	5.77
Vel Total (ft/s)	3.49	Avg. Vel. (ft/s)	1.14	4.00	0.88
Max Chl Dpth (ft)	6.61	Hydr. Depth (ft)	2.31	5.19	1.72
Conv. Total (cfs)	33334.3	Conv. (cfs)	1399.7	31551.4	383.3
Length Wtd. (ft)	30.04	Wetted Per. (ft)	12.84	35.46	6.74
Min Ch El (ft)	6251.03	Shear (lb/sq ft)	0.07	0.16	0.05
Alpha	1.25	Stream Power (lb/ft s)	200.00	0.00	121.94
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.64	3.58	1.01
C & E Loss (ft)	0.15	Cum SA (acres)	0.29	0.85	0.84

Plan: Default Scenario Channel 01 CH01 RS: 1040 Profile: Sand Creek

E.G. Elev (ft)	6257.69	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.74	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6255.95	Reach Len. (ft)	12.65	12.65	12.65
Crit W.S. (ft)	6255.83	Flow Area (sq ft)	9.76	65.02	8.88
E.G. Slope (ft/ft)	0.004945	Area (sq ft)	9.76	65.02	8.88
Q Total (cfs)	760.00	Flow (cfs)	26.41	710.45	23.14
Top Width (ft)	25.94	Top Width (ft)	5.85	14.59	5.51
Vel Total (ft/s)	9.08	Avg. Vel. (ft/s)	2.71	10.93	2.61
Max Chl Dpth (ft)	5.03	Hydr. Depth (ft)	1.67	4.46	1.61
Conv. Total (cfs)	10807.4	Conv. (cfs)	375.6	10102.8	329.1
Length Wtd. (ft)	12.65	Wetted Per. (ft)	6.62	15.39	6.38
Min Ch El (ft)	6250.92	Shear (lb/sq ft)	0.46	1.30	0.43
Alpha	1.36	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.07	Cum Volume (acre-ft)	0.62	3.50	1.01
C & E Loss (ft)	0.02	Cum SA (acres)	0.29	0.84	0.84

Plan: Default Scenario Channel 01 CH01 RS: 1039 Profile: Sand Creek

E.G. Elev (ft)	6257.59	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.66	Wt. n-Val.	0.050	0.025	
W.S. Elev (ft)	6255.93	Reach Len. (ft)	28.43	28.43	28.43
Crit W.S. (ft)	6255.93	Flow Area (sq ft)	2.71	68.90	
E.G. Slope (ft/ft)	0.006615	Area (sq ft)	2.71	68.90	
Q Total (cfs)	720.00	Flow (cfs)	5.42	714.58	
Top Width (ft)	22.59	Top Width (ft)	3.12	19.47	
Vel Total (ft/s)	10.06	Avg. Vel. (ft/s)	2.01	10.37	
Max Chl Dpth (ft)	5.64	Hydr. Depth (ft)	0.87	3.54	
Conv. Total (cfs)	8852.6	Conv. (cfs)	66.7	8785.9	
Length Wtd. (ft)	28.43	Wetted Per. (ft)	3.58	21.92	
Min Ch El (ft)	6250.29	Shear (lb/sq ft)	0.31	1.30	
Alpha	1.06	Stream Power (lb/ft s)	200.00	0.00	119.71
Frctn Loss (ft)	0.18	Cum Volume (acre-ft)	0.62	3.48	1.01
C & E Loss (ft)	0.00	Cum SA (acres)	0.28	0.83	0.84

Plan: Default Scenario Channel 01 CH01 RS: 1038 Profile: Sand Creek

E.G. Elev (ft)	6256.41	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.69	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.73	Reach Len. (ft)	26.37	26.37	26.37
Crit W.S. (ft)	6254.73	Flow Area (sq ft)	3.59	67.77	1.04
E.G. Slope (ft/ft)	0.006208	Area (sq ft)	3.59	67.77	1.04
Q Total (cfs)	720.00	Flow (cfs)	7.76	710.75	1.49
Top Width (ft)	24.16	Top Width (ft)	3.49	18.82	1.85
Vel Total (ft/s)	9.94	Avg. Vel. (ft/s)	2.16	10.49	1.44
Max Chl Dpth (ft)	4.69	Hydr. Depth (ft)	1.03	3.60	0.56
Conv. Total (cfs)	9138.0	Conv. (cfs)	98.4	9020.6	19.0
Length Wtd. (ft)	26.37	Wetted Per. (ft)	4.05	20.22	2.16
Min Ch El (ft)	6250.04	Shear (lb/sq ft)	0.34	1.30	0.19
Alpha	1.10	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.16	Cum Volume (acre-ft)	0.62	3.44	1.01
C & E Loss (ft)	0.00	Cum SA (acres)	0.28	0.82	0.83

Plan: Default Scenario Channel 01 CH01 RS: 1037 Profile: Sand Creek

E.G. Elev (ft)	6255.96	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.70	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.27	Reach Len. (ft)	21.74	21.74	21.74
Crit W.S. (ft)	6254.27	Flow Area (sq ft)	3.17	66.87	3.68
E.G. Slope (ft/ft)	0.006002	Area (sq ft)	3.17	66.87	3.68
Q Total (cfs)	720.00	Flow (cfs)	6.36	705.90	7.73
Top Width (ft)	25.26	Top Width (ft)	3.44	18.07	3.75
Vel Total (ft/s)	9.77	Avg. Vel. (ft/s)	2.01	10.56	2.10
Max Chl Dpth (ft)	4.69	Hydr. Depth (ft)	0.92	3.70	0.98
Conv. Total (cfs)	9293.9	Conv. (cfs)	82.2	9112.0	99.8
Length Wtd. (ft)	21.74	Wetted Per. (ft)	3.90	19.27	4.23
Min Ch El (ft)	6249.57	Shear (lb/sq ft)	0.30	1.30	0.33
Alpha	1.15	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.11	Cum Volume (acre-ft)	0.62	3.40	1.00
C & E Loss (ft)	0.14	Cum SA (acres)	0.28	0.81	0.83

Plan: Default Scenario Channel 01 CH01 RS: 1036 Profile: Sand Creek

E.G. Elev (ft)	6255.45	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.23	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.22	Reach Len. (ft)	41.42	41.42	41.42
Crit W.S. (ft)	6253.79	Flow Area (sq ft)	3.98	79.25	1.50
E.G. Slope (ft/ft)	0.004264	Area (sq ft)	3.98	79.25	1.50
Q Total (cfs)	720.00	Flow (cfs)	6.97	711.07	1.97
Top Width (ft)	27.81	Top Width (ft)	4.22	21.21	2.37
Vel Total (ft/s)	8.50	Avg. Vel. (ft/s)	1.75	8.97	1.31
Max Chl Dpth (ft)	5.22	Hydr. Depth (ft)	0.94	3.74	0.63
Conv. Total (cfs)	11026.1	Conv. (cfs)	106.7	10889.3	30.1
Length Wtd. (ft)	41.42	Wetted Per. (ft)	4.66	22.55	2.69
Min Ch El (ft)	6249.00	Shear (lb/sq ft)	0.23	0.94	0.15
Alpha	1.10	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.13	Cum Volume (acre-ft)	0.61	3.36	1.00
C & E Loss (ft)	0.09	Cum SA (acres)	0.28	0.80	0.83

Plan: Default Scenario Channel 01 CH01 RS: 1035 Profile: Sand Creek

E.G. Elev (ft)	6255.24	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.94	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.30	Reach Len. (ft)	36.85	36.85	36.85
Crit W.S. (ft)		Flow Area (sq ft)	23.83	76.71	14.69
E.G. Slope (ft/ft)	0.002270	Area (sq ft)	23.83	76.71	14.69
Q Total (cfs)	720.00	Flow (cfs)	55.35	634.37	30.29
Top Width (ft)	32.52	Top Width (ft)	10.55	14.66	7.31
Vel Total (ft/s)	6.25	Avg. Vel. (ft/s)	2.32	8.27	2.06
Max Chl Dpth (ft)	6.29	Hydr. Depth (ft)	2.26	5.23	2.01
Conv. Total (cfs)	15113.4	Conv. (cfs)	1161.8	13315.9	635.7
Length Wtd. (ft)	36.85	Wetted Per. (ft)	11.34	15.37	8.35
Min Ch El (ft)	6248.01	Shear (lb/sq ft)	0.30	0.71	0.25
Alpha	1.56	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.10	Cum Volume (acre-ft)	0.60	3.28	0.99
C & E Loss (ft)	0.01	Cum SA (acres)	0.27	0.78	0.83

Plan: Default Scenario Channel 01 CH01 RS: 1034 Profile: Sand Creek

E.G. Elev (ft)	6255.13	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.07	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.06	Reach Len. (ft)	13.77	13.77	13.77
Crit W.S. (ft)	6253.35	Flow Area (sq ft)	8.02	83.11	3.15
E.G. Slope (ft/ft)	0.003139	Area (sq ft)	8.02	83.11	3.15
Q Total (cfs)	720.00	Flow (cfs)	16.13	699.16	4.71
Top Width (ft)	28.00	Top Width (ft)	5.33	19.55	3.12
Vel Total (ft/s)	7.64	Avg. Vel. (ft/s)	2.01	8.41	1.49
Max Chl Dpth (ft)	5.51	Hydr. Depth (ft)	1.50	4.25	1.01
Conv. Total (cfs)	12850.4	Conv. (cfs)	287.8	12478.5	84.0
Length Wtd. (ft)	13.77	Wetted Per. (ft)	6.04	20.70	3.70
Min Ch El (ft)	6248.55	Shear (lb/sq ft)	0.26	0.79	0.17
Alpha	1.18	Stream Power (lb/ft s)	200.00	0.00	121.38
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.59	3.22	0.99
C & E Loss (ft)	0.02	Cum SA (acres)	0.26	0.77	0.82

Plan: Default Scenario Channel 01 CH01 RS: 1033 Profile: Sand Creek

E.G. Elev (ft)	6255.07	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.02	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.06	Reach Len. (ft)	26.23	26.23	26.23
Crit W.S. (ft)	6253.17	Flow Area (sq ft)	7.10	82.21	11.86
E.G. Slope (ft/ft)	0.002681	Area (sq ft)	7.10	82.21	11.86
Q Total (cfs)	720.00	Flow (cfs)	12.91	682.12	24.97
Top Width (ft)	28.79	Top Width (ft)	4.64	17.73	6.41
Vel Total (ft/s)	7.12	Avg. Vel. (ft/s)	1.82	8.30	2.11
Max Chl Dpth (ft)	6.06	Hydr. Depth (ft)	1.53	4.64	1.85
Conv. Total (cfs)	13905.2	Conv. (cfs)	249.4	13173.5	482.3
Length Wtd. (ft)	26.23	Wetted Per. (ft)	5.53	18.57	7.40
Min Ch El (ft)	6248.00	Shear (lb/sq ft)	0.21	0.74	0.27
Alpha	1.29	Stream Power (lb/ft s)	200.00	0.00	123.90
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.59	3.19	0.98
C & E Loss (ft)	0.03	Cum SA (acres)	0.26	0.76	0.82

Plan: Default Scenario Channel 01 CH01 RS: 1032 Profile: Sand Creek

E.G. Elev (ft)	6254.98	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.91	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6254.07	Reach Len. (ft)	25.60	25.60	25.60
Crit W.S. (ft)	6252.89	Flow Area (sq ft)	10.20	88.26	6.69
E.G. Slope (ft/ft)	0.002246	Area (sq ft)	10.20	88.26	6.69
Q Total (cfs)	720.00	Flow (cfs)	18.86	690.31	10.82
Top Width (ft)	28.34	Top Width (ft)	5.78	17.99	4.58
Vel Total (ft/s)	6.85	Avg. Vel. (ft/s)	1.85	7.82	1.62
Max Chl Dpth (ft)	6.05	Hydr. Depth (ft)	1.77	4.91	1.46
Conv. Total (cfs)	15193.5	Conv. (cfs)	398.1	14567.0	228.4
Length Wtd. (ft)	25.60	Wetted Per. (ft)	6.78	19.07	5.43
Min Ch El (ft)	6248.02	Shear (lb/sq ft)	0.21	0.65	0.17
Alpha	1.25	Stream Power (lb/ft s)	200.00	0.00	138.69
Frctn Loss (ft)	0.08	Cum Volume (acre-ft)	0.58	3.14	0.98
C & E Loss (ft)	0.07	Cum SA (acres)	0.26	0.75	0.82

Plan: Default Scenario Channel 01 CH01 RS: 1031 Profile: Sand Creek

E.G. Elev (ft)	6254.83	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.62	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.21	Reach Len. (ft)	34.57	34.57	34.57
Crit W.S. (ft)	6253.03	Flow Area (sq ft)	7.19	64.59	9.79
E.G. Slope (ft/ft)	0.004594	Area (sq ft)	7.19	64.59	9.79
Q Total (cfs)	720.00	Flow (cfs)	17.17	678.52	24.30
Top Width (ft)	25.53	Top Width (ft)	4.61	14.43	6.50
Vel Total (ft/s)	8.83	Avg. Vel. (ft/s)	2.39	10.51	2.48
Max Chl Dpth (ft)	5.46	Hydr. Depth (ft)	1.56	4.48	1.51
Conv. Total (cfs)	10622.7	Conv. (cfs)	253.4	10010.7	358.6
Length Wtd. (ft)	34.57	Wetted Per. (ft)	5.56	15.34	7.16
Min Ch El (ft)	6247.75	Shear (lb/sq ft)	0.37	1.21	0.39
Alpha	1.34	Stream Power (lb/ft s)	200.00	0.00	134.78
Frctn Loss (ft)	0.08	Cum Volume (acre-ft)	0.58	3.09	0.97
C & E Loss (ft)	0.29	Cum SA (acres)	0.26	0.74	0.81

Plan: Default Scenario Channel 01 CH01 RS: 1030 Profile: Sand Creek

E.G. Elev (ft)	6254.47	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.65	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.81	Reach Len. (ft)	24.70	24.70	24.70
Crit W.S. (ft)		Flow Area (sq ft)	33.79	125.43	21.07
E.G. Slope (ft/ft)	0.001427	Area (sq ft)	33.79	125.43	21.07
Q Total (cfs)	960.00	Flow (cfs)	64.76	857.70	37.54
Top Width (ft)	47.17	Top Width (ft)	14.55	23.01	9.61
Vel Total (ft/s)	5.32	Avg. Vel. (ft/s)	1.92	6.84	1.78
Max Chl Dpth (ft)	6.61	Hydr. Depth (ft)	2.32	5.45	2.19
Conv. Total (cfs)	25413.2	Conv. (cfs)	1714.4	22705.1	993.8
Length Wtd. (ft)	24.70	Wetted Per. (ft)	15.15	23.60	10.53
Min Ch El (ft)	6247.20	Shear (lb/sq ft)	0.20	0.47	0.18
Alpha	1.49	Stream Power (lb/ft s)	199.96	0.00	0.00
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.56	3.02	0.96
C & E Loss (ft)	0.02	Cum SA (acres)	0.25	0.73	0.81

Plan: Default Scenario Channel 01 CH01 RS: 1029 Profile: Sand Creek

E.G. Elev (ft)	6254.41	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.58	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.83	Reach Len. (ft)	24.82	24.82	24.82
Crit W.S. (ft)		Flow Area (sq ft)	40.35	136.15	9.61
E.G. Slope (ft/ft)	0.001218	Area (sq ft)	40.35	136.15	9.61
Q Total (cfs)	960.00	Flow (cfs)	78.07	868.94	12.98
Top Width (ft)	44.77	Top Width (ft)	15.10	24.26	5.41
Vel Total (ft/s)	5.16	Avg. Vel. (ft/s)	1.94	6.38	1.35
Max Chl Dpth (ft)	6.80	Hydr. Depth (ft)	2.67	5.61	1.78
Conv. Total (cfs)	27503.1	Conv. (cfs)	2236.8	24894.3	372.0
Length Wtd. (ft)	24.82	Wetted Per. (ft)	15.83	25.23	6.47
Min Ch El (ft)	6247.03	Shear (lb/sq ft)	0.19	0.41	0.11
Alpha	1.40	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.54	2.95	0.95
C & E Loss (ft)	0.01	Cum SA (acres)	0.24	0.71	0.80

Plan: Default Scenario Channel 01 CH01 RS: 1028 Profile: Sand Creek

E.G. Elev (ft)	6254.37	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.69	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.68	Reach Len. (ft)	50.43	50.43	50.43
Crit W.S. (ft)	6251.90	Flow Area (sq ft)	47.49	113.10	22.34
E.G. Slope (ft/ft)	0.001399	Area (sq ft)	47.49	113.10	22.34
Q Total (cfs)	960.00	Flow (cfs)	105.28	812.47	42.25
Top Width (ft)	43.84	Top Width (ft)	16.02	19.18	8.64
Vel Total (ft/s)	5.25	Avg. Vel. (ft/s)	2.22	7.18	1.89
Max Chl Dpth (ft)	6.68	Hydr. Depth (ft)	2.96	5.90	2.59
Conv. Total (cfs)	25663.9	Conv. (cfs)	2814.6	21720.0	1129.4
Length Wtd. (ft)	50.43	Wetted Per. (ft)	16.87	19.47	10.07
Min Ch El (ft)	6247.00	Shear (lb/sq ft)	0.25	0.51	0.19
Alpha	1.61	Stream Power (lb/ft s)	200.00	0.00	122.22
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.51	2.87	0.94
C & E Loss (ft)	0.05	Cum SA (acres)	0.23	0.70	0.80

Plan: Default Scenario Channel 01 CH01 RS: 1027 Profile: Sand Creek

E.G. Elev (ft)	6254.26	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.52	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.74	Reach Len. (ft)	25.05	25.05	25.05
Crit W.S. (ft)		Flow Area (sq ft)	50.54	133.77	20.83
E.G. Slope (ft/ft)	0.001014	Area (sq ft)	50.54	133.77	20.83
Q Total (cfs)	960.00	Flow (cfs)	100.06	828.23	31.71
Top Width (ft)	47.04	Top Width (ft)	15.68	22.13	9.23
Vel Total (ft/s)	4.68	Avg. Vel. (ft/s)	1.98	6.19	1.52
Max Chl Dpth (ft)	6.74	Hydr. Depth (ft)	3.22	6.04	2.26
Conv. Total (cfs)	30153.8	Conv. (cfs)	3142.9	26014.8	996.0
Length Wtd. (ft)	25.05	Wetted Per. (ft)	16.69	22.60	10.21
Min Ch El (ft)	6247.00	Shear (lb/sq ft)	0.19	0.37	0.13
Alpha	1.53	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.46	2.73	0.92
C & E Loss (ft)	0.00	Cum SA (acres)	0.21	0.68	0.79

Plan: Default Scenario Channel 01 CH01 RS: 1026 Profile: Sand Creek

E.G. Elev (ft)	6254.23	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.51	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.72	Reach Len. (ft)	27.07	27.07	27.07
Crit W.S. (ft)		Flow Area (sq ft)	34.42	144.38	22.70
E.G. Slope (ft/ft)	0.000999	Area (sq ft)	34.42	144.38	22.70
Q Total (cfs)	960.00	Flow (cfs)	58.11	866.14	35.75
Top Width (ft)	47.61	Top Width (ft)	13.43	24.95	9.23
Vel Total (ft/s)	4.76	Avg. Vel. (ft/s)	1.69	6.00	1.58
Max Chl Dpth (ft)	6.72	Hydr. Depth (ft)	2.56	5.79	2.46
Conv. Total (cfs)	30368.1	Conv. (cfs)	1838.2	27399.1	1130.8
Length Wtd. (ft)	27.07	Wetted Per. (ft)	14.29	25.31	10.46
Min Ch El (ft)	6247.00	Shear (lb/sq ft)	0.15	0.36	0.14
Alpha	1.44	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.43	2.65	0.91
C & E Loss (ft)	0.05	Cum SA (acres)	0.20	0.66	0.78

Plan: Default Scenario Channel 01 CH01 RS: 1025 Profile: Sand Creek

E.G. Elev (ft)	6254.16	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.35	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.81	Reach Len. (ft)	31.34	31.34	31.34
Crit W.S. (ft)	6250.86	Flow Area (sq ft)	32.65	184.33	16.24
E.G. Slope (ft/ft)	0.000613	Area (sq ft)	32.65	184.33	16.24
Q Total (cfs)	960.00	Flow (cfs)	43.20	898.17	18.63
Top Width (ft)	49.08	Top Width (ft)	12.60	30.02	6.46
Vel Total (ft/s)	4.12	Avg. Vel. (ft/s)	1.32	4.87	1.15
Max Chl Dpth (ft)	7.47	Hydr. Depth (ft)	2.59	6.14	2.52
Conv. Total (cfs)	38786.3	Conv. (cfs)	1745.2	36288.3	752.8
Length Wtd. (ft)	31.34	Wetted Per. (ft)	13.54	30.58	8.33
Min Ch El (ft)	6246.34	Shear (lb/sq ft)	0.09	0.23	0.07
Alpha	1.32	Stream Power (lb/ft s)	200.00	0.00	118.87
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.41	2.55	0.89
C & E Loss (ft)	0.00	Cum SA (acres)	0.20	0.64	0.78

Plan: Default Scenario Channel 01 CH01 RS: 1024 Profile: Sand Creek

E.G. Elev (ft)	6254.13	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.39	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.75	Reach Len. (ft)	16.62	16.62	16.62
Crit W.S. (ft)	6250.63	Flow Area (sq ft)	53.36	161.84	18.50
E.G. Slope (ft/ft)	0.000641	Area (sq ft)	53.36	161.84	18.50
Q Total (cfs)	960.00	Flow (cfs)	87.53	851.28	21.19
Top Width (ft)	47.83	Top Width (ft)	15.32	24.14	8.36
Vel Total (ft/s)	4.11	Avg. Vel. (ft/s)	1.64	5.26	1.15
Max Chl Dpth (ft)	7.67	Hydr. Depth (ft)	3.48	6.70	2.21
Conv. Total (cfs)	37915.4	Conv. (cfs)	3457.1	33621.3	837.0
Length Wtd. (ft)	16.62	Wetted Per. (ft)	16.57	24.77	9.85
Min Ch El (ft)	6246.08	Shear (lb/sq ft)	0.13	0.26	0.08
Alpha	1.47	Stream Power (lb/ft s)	200.00	0.00	120.82
Frctn Loss (ft)	0.01	Cum Volume (acre-ft)	0.38	2.42	0.88
C & E Loss (ft)	0.01	Cum SA (acres)	0.19	0.63	0.77

Plan: Default Scenario Channel 01 CH01 RS: 1023 Profile: Sand Creek

E.G. Elev (ft)	6254.12	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.47	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.64	Reach Len. (ft)	20.93	20.93	20.93
Crit W.S. (ft)	6250.84	Flow Area (sq ft)	67.41	131.67	23.91
E.G. Slope (ft/ft)	0.000802	Area (sq ft)	67.41	131.67	23.91
Q Total (cfs)	960.00	Flow (cfs)	135.33	790.83	33.84
Top Width (ft)	45.25	Top Width (ft)	16.92	19.20	9.13
Vel Total (ft/s)	4.31	Avg. Vel. (ft/s)	2.01	6.01	1.42
Max Chl Dpth (ft)	7.64	Hydr. Depth (ft)	3.98	6.86	2.62
Conv. Total (cfs)	33908.2	Conv. (cfs)	4780.0	27933.1	1195.1
Length Wtd. (ft)	20.93	Wetted Per. (ft)	18.29	19.53	10.96
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.18	0.34	0.11
Alpha	1.64	Stream Power (lb/ft s)	200.00	0.00	118.87
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.36	2.37	0.87
C & E Loss (ft)	0.01	Cum SA (acres)	0.18	0.62	0.77

Plan: Default Scenario Channel 01 CH01 RS: 1022 Profile: Sand Creek

E.G. Elev (ft)	6254.09	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.53	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.57	Reach Len. (ft)	26.45	26.45	26.45
Crit W.S. (ft)	6250.86	Flow Area (sq ft)	55.93	124.66	33.68
E.G. Slope (ft/ft)	0.000873	Area (sq ft)	55.93	124.66	33.68
Q Total (cfs)	960.00	Flow (cfs)	111.71	791.95	56.34
Top Width (ft)	43.66	Top Width (ft)	14.85	17.98	10.83
Vel Total (ft/s)	4.48	Avg. Vel. (ft/s)	2.00	6.35	1.67
Max Chl Dpth (ft)	7.56	Hydr. Depth (ft)	3.76	6.93	3.11
Conv. Total (cfs)	32486.1	Conv. (cfs)	3780.2	26799.2	1906.7
Length Wtd. (ft)	26.45	Wetted Per. (ft)	16.30	18.12	12.81
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.19	0.38	0.14
Alpha	1.69	Stream Power (lb/ft s)	200.00	0.00	134.51
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)	0.33	2.31	0.86
C & E Loss (ft)	0.04	Cum SA (acres)	0.17	0.61	0.77

Plan: Default Scenario Channel 01 CH01 RS: 1021 Profile: Sand Creek

E.G. Elev (ft)	6254.01	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.97	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6253.05	Reach Len. (ft)	19.84	19.84	19.84
Crit W.S. (ft)	6251.51	Flow Area (sq ft)	42.29	93.92	21.05
E.G. Slope (ft/ft)	0.001852	Area (sq ft)	42.29	93.92	21.05
Q Total (cfs)	960.00	Flow (cfs)	112.52	803.79	43.70
Top Width (ft)	36.51	Top Width (ft)	12.77	14.86	8.88
Vel Total (ft/s)	6.10	Avg. Vel. (ft/s)	2.66	8.56	2.08
Max Chl Dpth (ft)	7.05	Hydr. Depth (ft)	3.31	6.32	2.37
Conv. Total (cfs)	22308.9	Conv. (cfs)	2614.7	18678.8	1015.5
Length Wtd. (ft)	19.84	Wetted Per. (ft)	14.09	15.34	10.17
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.35	0.71	0.24
Alpha	1.67	Stream Power (lb/ft s)	200.00	0.00	123.06
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.30	2.24	0.84
C & E Loss (ft)	0.03	Cum SA (acres)	0.16	0.60	0.76

Plan: Default Scenario Channel 01 CH01 RS: 1020 Profile: Sand Creek

E.G. Elev (ft)	6253.93	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.29	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6252.64	Reach Len. (ft)	32.65	32.65	32.65
Crit W.S. (ft)	6251.77	Flow Area (sq ft)	21.40	93.37	10.15
E.G. Slope (ft/ft)	0.002822	Area (sq ft)	21.40	93.37	10.15
Q Total (cfs)	960.00	Flow (cfs)	54.04	885.09	20.87
Top Width (ft)	32.42	Top Width (ft)	9.58	16.89	5.95
Vel Total (ft/s)	7.68	Avg. Vel. (ft/s)	2.53	9.48	2.06
Max Chl Dpth (ft)	6.33	Hydr. Depth (ft)	2.23	5.53	1.71
Conv. Total (cfs)	18070.0	Conv. (cfs)	1017.2	16659.9	392.8
Length Wtd. (ft)	32.65	Wetted Per. (ft)	10.58	17.95	6.83
Min Ch El (ft)	6246.31	Shear (lb/sq ft)	0.36	0.92	0.26
Alpha	1.41	Stream Power (lb/ft s)	200.00	0.00	120.54
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)	0.28	2.20	0.84
C & E Loss (ft)	0.01	Cum SA (acres)	0.16	0.59	0.76

Plan: Default Scenario Channel 01 CH01 RS: 1019 Profile: Sand Creek

E.G. Elev (ft)	6253.84	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.26	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6252.58	Reach Len. (ft)	27.27	27.27	27.27
Crit W.S. (ft)	6251.68	Flow Area (sq ft)	31.95	82.29	27.16
E.G. Slope (ft/ft)	0.002565	Area (sq ft)	31.95	82.29	27.16
Q Total (cfs)	960.00	Flow (cfs)	86.40	803.89	69.71
Top Width (ft)	37.00	Top Width (ft)	12.17	13.67	11.16
Vel Total (ft/s)	6.79	Avg. Vel. (ft/s)	2.70	9.77	2.57
Max Chl Dpth (ft)	6.58	Hydr. Depth (ft)	2.62	6.02	2.43
Conv. Total (cfs)	18953.8	Conv. (cfs)	1705.9	15871.6	1376.3
Length Wtd. (ft)	27.27	Wetted Per. (ft)	13.26	14.08	12.20
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.39	0.94	0.36
Alpha	1.76	Stream Power (lb/ft s)	200.00	0.00	118.87
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)	0.26	2.13	0.82
C & E Loss (ft)	0.07	Cum SA (acres)	0.15	0.58	0.75

Plan: Default Scenario Channel 01 CH01 RS: 1018 Profile: Sand Creek

E.G. Elev (ft)	6253.67	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.97	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6251.70	Reach Len. (ft)	36.97	36.97	36.97
Crit W.S. (ft)	6251.70	Flow Area (sq ft)	24.12	63.74	26.14
E.G. Slope (ft/ft)	0.004727	Area (sq ft)	24.12	63.74	26.14
Q Total (cfs)	960.00	Flow (cfs)	83.83	786.52	89.65
Top Width (ft)	32.74	Top Width (ft)	9.65	12.02	11.07
Vel Total (ft/s)	8.42	Avg. Vel. (ft/s)	3.48	12.34	3.43
Max Chl Dpth (ft)	5.70	Hydr. Depth (ft)	2.50	5.30	2.36
Conv. Total (cfs)	13962.4	Conv. (cfs)	1219.3	11439.3	1303.8
Length Wtd. (ft)	36.97	Wetted Per. (ft)	10.87	12.15	12.02
Min Ch El (ft)	6246.00	Shear (lb/sq ft)	0.65	1.55	0.64
Alpha	1.79	Stream Power (lb/ft s)	200.00	68.05	125.29
Frctn Loss (ft)	0.14	Cum Volume (acre-ft)	0.25	2.09	0.81
C & E Loss (ft)	0.15	Cum SA (acres)	0.14	0.57	0.74

Plan: Default Scenario Channel 01 CH01 RS: 1017 Profile: Sand Creek

E.G. Elev (ft)	6253.01	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.47	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6251.54	Reach Len. (ft)	35.86	35.86	35.86
Crit W.S. (ft)	6250.92	Flow Area (sq ft)	27.53	71.76	34.14
E.G. Slope (ft/ft)	0.003198	Area (sq ft)	27.53	71.76	34.14
Q Total (cfs)	960.00	Flow (cfs)	85.70	771.49	102.81
Top Width (ft)	34.94	Top Width (ft)	9.68	12.21	13.05
Vel Total (ft/s)	7.19	Avg. Vel. (ft/s)	3.11	10.75	3.01
Max Chl Dpth (ft)	6.54	Hydr. Depth (ft)	2.84	5.88	2.62
Conv. Total (cfs)	16975.1	Conv. (cfs)	1515.3	13641.8	1818.0
Length Wtd. (ft)	35.86	Wetted Per. (ft)	10.92	12.54	14.23
Min Ch El (ft)	6245.00	Shear (lb/sq ft)	0.50	1.14	0.48
Alpha	1.83	Stream Power (lb/ft s)	200.00	63.31	139.53
Frctn Loss (ft)	0.14	Cum Volume (acre-ft)	0.22	2.03	0.78
C & E Loss (ft)	0.05	Cum SA (acres)	0.14	0.56	0.73

Plan: Default Scenario Channel 01 CH01 RS: 1016 Profile: Sand Creek

E.G. Elev (ft)	6252.82	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.00	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6250.82	Reach Len. (ft)	34.77	34.77	34.77
Crit W.S. (ft)	6250.82	Flow Area (sq ft)	28.30	64.83	20.04
E.G. Slope (ft/ft)	0.004651	Area (sq ft)	28.30	64.83	20.04
Q Total (cfs)	960.00	Flow (cfs)	101.09	800.65	58.26
Top Width (ft)	33.47	Top Width (ft)	10.93	12.11	10.43
Vel Total (ft/s)	8.48	Avg. Vel. (ft/s)	3.57	12.35	2.91
Max Chl Dpth (ft)	5.66	Hydr. Depth (ft)	2.59	5.35	1.92
Conv. Total (cfs)	14076.9	Conv. (cfs)	1482.3	11740.3	854.3
Length Wtd. (ft)	34.77	Wetted Per. (ft)	12.09	12.19	11.67
Min Ch El (ft)	6245.16	Shear (lb/sq ft)	0.68	1.54	0.50
Alpha	1.79	Stream Power (lb/ft s)	200.00	62.75	140.37
Frctn Loss (ft)	0.08	Cum Volume (acre-ft)	0.20	1.97	0.76
C & E Loss (ft)	0.41	Cum SA (acres)	0.13	0.55	0.72

Plan: Default Scenario Channel 01 CH01 RS: 1015 Profile: Sand Creek

E.G. Elev (ft)	6250.93	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.62	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6250.31	Reach Len. (ft)	47.19	47.19	47.19
Crit W.S. (ft)	6248.73	Flow Area (sq ft)	86.05	102.15	16.18
E.G. Slope (ft/ft)	0.001456	Area (sq ft)	86.05	102.15	16.18
Q Total (cfs)	960.00	Flow (cfs)	204.19	730.41	25.40
Top Width (ft)	54.06	Top Width (ft)	27.71	17.92	8.44
Vel Total (ft/s)	4.70	Avg. Vel. (ft/s)	2.37	7.15	1.57
Max Chl Dpth (ft)	6.31	Hydr. Depth (ft)	3.11	5.70	1.92
Conv. Total (cfs)	25157.1	Conv. (cfs)	5350.8	19140.7	665.6
Length Wtd. (ft)	47.19	Wetted Per. (ft)	28.43	18.25	9.94
Min Ch El (ft)	6244.00	Shear (lb/sq ft)	0.28	0.51	0.15
Alpha	1.82	Stream Power (lb/ft s)	200.00	0.00	132.55
Frctn Loss (ft)	0.10	Cum Volume (acre-ft)	0.15	1.91	0.74
C & E Loss (ft)	0.07	Cum SA (acres)	0.11	0.54	0.72

Plan: Default Scenario Channel 01 CH01 RS: 1014 Profile: Sand Creek

E.G. Elev (ft)	6250.77	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.29	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6249.48	Reach Len. (ft)	18.01	18.01	18.01
Crit W.S. (ft)	6248.90	Flow Area (sq ft)	8.12	95.68	21.41
E.G. Slope (ft/ft)	0.003430	Area (sq ft)	8.12	95.68	21.41
Q Total (cfs)	956.00	Flow (cfs)	16.60	898.32	41.07
Top Width (ft)	44.69	Top Width (ft)	5.70	20.99	18.00
Vel Total (ft/s)	7.64	Avg. Vel. (ft/s)	2.04	9.39	1.92
Max Chl Dpth (ft)	5.48	Hydr. Depth (ft)	1.42	4.56	1.19
Conv. Total (cfs)	16322.9	Conv. (cfs)	283.5	15338.1	701.3
Length Wtd. (ft)	18.01	Wetted Per. (ft)	6.38	21.60	18.50
Min Ch El (ft)	6244.00	Shear (lb/sq ft)	0.27	0.95	0.25
Alpha	1.42	Stream Power (lb/ft s)	327.17	72.96	145.12
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.10	1.80	0.72
C & E Loss (ft)	0.11	Cum SA (acres)	0.09	0.52	0.70

Plan: Default Scenario Channel 01 CH01 RS: 1013 Profile: Sand Creek

E.G. Elev (ft)	6250.61	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.94	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6249.67	Reach Len. (ft)	18.13	18.13	18.13
Crit W.S. (ft)	6249.02	Flow Area (sq ft)	11.80	92.02	121.18
E.G. Slope (ft/ft)	0.002495	Area (sq ft)	11.80	92.02	121.18
Q Total (cfs)	956.00	Flow (cfs)	23.35	786.67	145.97
Top Width (ft)	190.16	Top Width (ft)	6.80	18.03	165.33
Vel Total (ft/s)	4.25	Avg. Vel. (ft/s)	1.98	8.55	1.20
Max Chl Dpth (ft)	6.15	Hydr. Depth (ft)	1.73	5.10	0.73
Conv. Total (cfs)	19140.3	Conv. (cfs)	467.6	15750.2	2922.5
Length Wtd. (ft)	18.13	Wetted Per. (ft)	7.66	18.83	165.77
Min Ch El (ft)	6243.52	Shear (lb/sq ft)	0.24	0.76	0.11
Alpha	3.35	Stream Power (lb/ft s)	378.96	73.92	146.40
Frctn Loss (ft)	0.04	Cum Volume (acre-ft)	0.10	1.76	0.69
C & E Loss (ft)	0.06	Cum SA (acres)	0.09	0.51	0.66

Plan: Default Scenario Channel 01 CH01 RS: 1012 Profile: Sand Creek

E.G. Elev (ft)	6250.51	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.74	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6249.77	Reach Len. (ft)	38.75	38.75	38.75
Crit W.S. (ft)	6249.77	Flow Area (sq ft)	16.49	84.69	172.46
E.G. Slope (ft/ft)	0.002086	Area (sq ft)	16.49	84.69	172.46
Q Total (cfs)	956.00	Flow (cfs)	32.34	686.27	237.39
Top Width (ft)	192.41	Top Width (ft)	8.51	15.62	168.29
Vel Total (ft/s)	3.49	Avg. Vel. (ft/s)	1.96	8.10	1.38
Max Chl Dpth (ft)	6.71	Hydr. Depth (ft)	1.94	5.42	1.02
Conv. Total (cfs)	20931.4	Conv. (cfs)	708.0	15025.7	5197.6
Length Wtd. (ft)	38.75	Wetted Per. (ft)	9.49	16.42	168.87
Min Ch El (ft)	6243.06	Shear (lb/sq ft)	0.23	0.67	0.13
Alpha	3.91	Stream Power (lb/ft s)	348.95	80.25	145.04
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)	0.09	1.72	0.63
C & E Loss (ft)	0.00	Cum SA (acres)	0.09	0.50	0.59

Plan: Default Scenario Channel 01 CH01 RS: 1011 Profile: Sand Creek

E.G. Elev (ft)	6250.19	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.78	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6249.40	Reach Len. (ft)	22.91	22.91	22.91
Crit W.S. (ft)	6249.40	Flow Area (sq ft)	11.16	87.16	152.55
E.G. Slope (ft/ft)	0.002397	Area (sq ft)	11.16	87.16	152.55
Q Total (cfs)	956.00	Flow (cfs)	22.64	713.30	220.07
Top Width (ft)	177.33	Top Width (ft)	5.32	18.00	154.01
Vel Total (ft/s)	3.81	Avg. Vel. (ft/s)	2.03	8.18	1.44
Max Chl Dpth (ft)	5.40	Hydr. Depth (ft)	2.10	4.84	0.99
Conv. Total (cfs)	19527.5	Conv. (cfs)	462.4	14570.0	4495.2
Length Wtd. (ft)	22.91	Wetted Per. (ft)	6.77	18.48	154.51
Min Ch El (ft)	6244.00	Shear (lb/sq ft)	0.25	0.71	0.15
Alpha	3.48	Stream Power (lb/ft s)	369.02	116.04	181.87
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.08	1.65	0.49
C & E Loss (ft)	0.00	Cum SA (acres)	0.08	0.49	0.45

Plan: Default Scenario Channel 01 CH01 RS: 1010 Profile: Sand Creek

E.G. Elev (ft)	6250.00	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.78	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6249.23	Reach Len. (ft)	20.32	20.32	20.32
Crit W.S. (ft)	6249.23	Flow Area (sq ft)	7.49	85.99	154.57
E.G. Slope (ft/ft)	0.002552	Area (sq ft)	7.49	85.99	154.57
Q Total (cfs)	956.00	Flow (cfs)	13.49	703.75	238.76
Top Width (ft)	170.75	Top Width (ft)	4.73	18.27	147.75
Vel Total (ft/s)	3.85	Avg. Vel. (ft/s)	1.80	8.18	1.54
Max Chl Dpth (ft)	5.56	Hydr. Depth (ft)	1.58	4.71	1.05
Conv. Total (cfs)	18925.4	Conv. (cfs)	267.0	13931.8	4726.5
Length Wtd. (ft)	20.32	Wetted Per. (ft)	5.69	19.11	148.09
Min Ch El (ft)	6243.67	Shear (lb/sq ft)	0.21	0.72	0.17
Alpha	3.36	Stream Power (lb/ft s)	331.72	80.47	154.93
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.08	1.60	0.41
C & E Loss (ft)	0.01	Cum SA (acres)	0.08	0.48	0.37

Plan: Default Scenario Channel 01 CH01 RS: 1009 Profile: Sand Creek

E.G. Elev (ft)	6249.72	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.91	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6248.82	Reach Len. (ft)	20.66	20.66	20.66
Crit W.S. (ft)	6248.82	Flow Area (sq ft)	20.45	86.34	124.90
E.G. Slope (ft/ft)	0.002216	Area (sq ft)	20.45	86.34	124.90
Q Total (cfs)	956.00	Flow (cfs)	46.99	743.73	165.28
Top Width (ft)	158.88	Top Width (ft)	8.30	15.39	135.19
Vel Total (ft/s)	4.13	Avg. Vel. (ft/s)	2.30	8.61	1.32
Max Chl Dpth (ft)	6.44	Hydr. Depth (ft)	2.46	5.61	0.92
Conv. Total (cfs)	20308.4	Conv. (cfs)	998.2	15799.2	3511.0
Length Wtd. (ft)	20.66	Wetted Per. (ft)	9.71	15.98	135.76
Min Ch El (ft)	6242.38	Shear (lb/sq ft)	0.29	0.75	0.13
Alpha	3.42	Stream Power (lb/ft s)	421.28	176.28	212.75
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.07	1.56	0.34
C & E Loss (ft)	0.04	Cum SA (acres)	0.08	0.47	0.31

Plan: Default Scenario Channel 01 CH01 RS: 1008 Profile: Sand Creek

E.G. Elev (ft)	6249.21	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.78	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6248.42	Reach Len. (ft)	28.44	28.44	28.44
Crit W.S. (ft)	6247.88	Flow Area (sq ft)	11.03	97.90	117.04
E.G. Slope (ft/ft)	0.002504	Area (sq ft)	11.03	97.90	117.04
Q Total (cfs)	956.00	Flow (cfs)	20.00	771.29	164.71
Top Width (ft)	155.89	Top Width (ft)	7.71	21.50	126.68
Vel Total (ft/s)	4.23	Avg. Vel. (ft/s)	1.81	7.88	1.41
Max Chl Dpth (ft)	5.97	Hydr. Depth (ft)	1.43	4.55	0.92
Conv. Total (cfs)	19104.9	Conv. (cfs)	399.6	15413.6	3291.7
Length Wtd. (ft)	28.44	Wetted Per. (ft)	8.19	22.71	127.13
Min Ch El (ft)	6242.45	Shear (lb/sq ft)	0.21	0.67	0.14
Alpha	2.82	Stream Power (lb/ft s)	282.05	-26.98	15.38
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)	0.06	1.52	0.28
C & E Loss (ft)	0.10	Cum SA (acres)	0.07	0.46	0.24

Plan: Default Scenario Channel 01 CH01 RS: 1007 Profile: Sand Creek

E.G. Elev (ft)	6249.05	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.44	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6248.61	Reach Len. (ft)	19.26	19.26	19.26
Crit W.S. (ft)	6247.35	Flow Area (sq ft)	28.84	103.41	190.83
E.G. Slope (ft/ft)	0.001237	Area (sq ft)	28.84	103.41	190.83
Q Total (cfs)	956.00	Flow (cfs)	33.98	657.41	264.61
Top Width (ft)	166.15	Top Width (ft)	23.50	18.31	124.34
Vel Total (ft/s)	2.96	Avg. Vel. (ft/s)	1.18	6.36	1.39
Max Chl Dpth (ft)	6.60	Hydr. Depth (ft)	1.23	5.65	1.53
Conv. Total (cfs)	27179.6	Conv. (cfs)	966.0	18690.5	7523.0
Length Wtd. (ft)	19.26	Wetted Per. (ft)	24.11	19.50	124.90
Min Ch El (ft)	6242.01	Shear (lb/sq ft)	0.09	0.41	0.12
Alpha	3.24	Stream Power (lb/ft s)	69.98	-376.72	-308.78
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.05	1.45	0.18
C & E Loss (ft)	0.00	Cum SA (acres)	0.06	0.45	0.16

Plan: Default Scenario Channel 01 CH01 RS: 1006 Profile: Sand Creek

E.G. Elev (ft)	6249.02	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.43	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6248.59	Reach Len. (ft)	13.76	13.76	13.76
Crit W.S. (ft)	6247.48	Flow Area (sq ft)	27.12	110.25	175.16
E.G. Slope (ft/ft)	0.001286	Area (sq ft)	27.12	110.25	175.16
Q Total (cfs)	956.00	Flow (cfs)	40.55	679.02	236.43
Top Width (ft)	159.55	Top Width (ft)	15.87	21.53	122.15
Vel Total (ft/s)	3.06	Avg. Vel. (ft/s)	1.50	6.16	1.35
Max Chl Dpth (ft)	6.41	Hydr. Depth (ft)	1.71	5.12	1.43
Conv. Total (cfs)	26655.3	Conv. (cfs)	1130.6	18932.6	6592.0
Length Wtd. (ft)	13.76	Wetted Per. (ft)	16.32	22.45	122.91
Min Ch El (ft)	6242.18	Shear (lb/sq ft)	0.13	0.39	0.11
Alpha	2.94	Stream Power (lb/ft s)	284.01	-123.45	-50.63
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.04	1.40	0.10
C & E Loss (ft)	0.00	Cum SA (acres)	0.05	0.44	0.11

Plan: Default Scenario Channel 01 CH01 RS: 1005 Profile: Sand Creek

E.G. Elev (ft)	6249.01	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.43	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6248.58	Reach Len. (ft)	17.89	17.89	17.89
Crit W.S. (ft)	6246.87	Flow Area (sq ft)	50.18	115.20	157.16
E.G. Slope (ft/ft)	0.001029	Area (sq ft)	50.18	115.20	157.16
Q Total (cfs)	956.00	Flow (cfs)	83.82	699.01	173.18
Top Width (ft)	166.37	Top Width (ft)	21.11	19.87	125.39
Vel Total (ft/s)	2.96	Avg. Vel. (ft/s)	1.67	6.07	1.10
Max Chl Dpth (ft)	6.31	Hydr. Depth (ft)	2.38	5.80	1.25
Conv. Total (cfs)	29803.7	Conv. (cfs)	2613.1	21791.8	5398.8
Length Wtd. (ft)	17.89	Wetted Per. (ft)	21.64	20.29	126.46
Min Ch El (ft)	6242.27	Shear (lb/sq ft)	0.15	0.36	0.08
Alpha	3.12	Stream Power (lb/ft s)	-280.69	-800.65	-737.54
Frctn Loss (ft)	0.02	Cum Volume (acre-ft)	0.03	1.37	0.05
C & E Loss (ft)	0.01	Cum SA (acres)	0.05	0.43	0.07

Plan: Default Scenario Channel 01 CH01 RS: 1004 Profile: Sand Creek

E.G. Elev (ft)	6248.98	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.40	Wt. n-Val.	0.050	0.025	0.050
W.S. Elev (ft)	6248.59	Reach Len. (ft)	111.48	111.48	111.48
Crit W.S. (ft)	6246.97	Flow Area (sq ft)	54.91	154.28	32.59
E.G. Slope (ft/ft)	0.000780	Area (sq ft)	54.91	154.28	32.59
Q Total (cfs)	956.00	Flow (cfs)	79.72	831.63	44.66
Top Width (ft)	63.80	Top Width (ft)	23.25	25.95	14.60
Vel Total (ft/s)	3.95	Avg. Vel. (ft/s)	1.45	5.39	1.37
Max Chl Dpth (ft)	6.58	Hydr. Depth (ft)	2.36	5.95	2.23
Conv. Total (cfs)	34226.5	Conv. (cfs)	2854.1	29773.7	1598.8
Length Wtd. (ft)	111.48	Wetted Per. (ft)	23.74	26.37	15.37
Min Ch El (ft)	6242.00	Shear (lb/sq ft)	0.11	0.28	0.10
Alpha	1.63	Stream Power (lb/ft s)	340.13	54.64	132.70
Frctn Loss (ft)		Cum Volume (acre-ft)	0.00	1.31	0.01
C & E Loss (ft)		Cum SA (acres)	0.04	0.42	0.04

Plan: Default Scenario Channel 01 CH01 RS: 1003 Profile: Sand Creek

E.G. Elev (ft)	6244.81	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.53	Wt. n-Val.		0.013	
W.S. Elev (ft)	6244.28	Reach Len. (ft)	87.73	87.73	87.73
Crit W.S. (ft)	6242.76	Flow Area (sq ft)		164.22	
E.G. Slope (ft/ft)	0.000389	Area (sq ft)	0.30	497.29	6.16
Q Total (cfs)	956.00	Flow (cfs)		956.00	
Top Width (ft)	129.55	Top Width (ft)	1.36	122.77	5.42
Vel Total (ft/s)	5.82	Avg. Vel. (ft/s)		5.82	
Max Chl Dpth (ft)	4.28	Hydr. Depth (ft)		4.17	
Conv. Total (cfs)	48483.8	Conv. (cfs)		48483.8	
Length Wtd. (ft)	87.73	Wetted Per. (ft)		39.56	
Min Ch El (ft)	6240.00	Shear (lb/sq ft)		0.10	
Alpha	1.00	Stream Power (lb/ft s)	280.00	0.00	0.00
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)	0.00	0.83	0.01
C & E Loss (ft)	0.09	Cum SA (acres)	0.01	0.23	0.01

Plan: Default Scenario Channel 01 CH01 RS: 1002 Profile: Sand Creek

E.G. Elev (ft)	6244.65	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.46	Wt. n-Val.	0.050	0.013	0.050
W.S. Elev (ft)	6243.20	Reach Len. (ft)	55.70	55.70	55.70
Crit W.S. (ft)	6243.20	Flow Area (sq ft)	1.34	98.10	3.09
E.G. Slope (ft/ft)	0.001748	Area (sq ft)	1.34	98.10	3.09
Q Total (cfs)	956.00	Flow (cfs)	1.08	951.77	3.15
Top Width (ft)	39.52	Top Width (ft)	2.32	33.35	3.85
Vel Total (ft/s)	9.32	Avg. Vel. (ft/s)	0.80	9.70	1.02
Max Chl Dpth (ft)	3.36	Hydr. Depth (ft)	0.58	2.94	0.80
Conv. Total (cfs)	22863.1	Conv. (cfs)	25.8	22762.1	75.3
Length Wtd. (ft)	55.70	Wetted Per. (ft)	2.59	33.92	4.17
Min Ch El (ft)	6239.84	Shear (lb/sq ft)	0.06	0.32	0.08
Alpha	1.08	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)	0.10	Cum Volume (acre-ft)	0.00	0.23	0.00
C & E Loss (ft)	0.00	Cum SA (acres)	0.00	0.08	0.00

Plan: Default Scenario Channel 01 CH01 RS: 1001 Profile: Sand Creek

E.G. Elev (ft)	6244.20	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.47	Wt. n-Val.	0.050	0.013	0.050
W.S. Elev (ft)	6242.73	Reach Len. (ft)	44.32	44.32	44.32
Crit W.S. (ft)	6242.73	Flow Area (sq ft)	0.86	98.05	0.44
E.G. Slope (ft/ft)	0.001723	Area (sq ft)	0.86	98.05	0.44
Q Total (cfs)	956.00	Flow (cfs)	0.59	955.17	0.24
Top Width (ft)	35.44	Top Width (ft)	1.83	32.29	1.32
Vel Total (ft/s)	9.62	Avg. Vel. (ft/s)	0.69	9.74	0.55
Max Chl Dpth (ft)	3.73	Hydr. Depth (ft)	0.47	3.04	0.33
Conv. Total (cfs)	23030.7	Conv. (cfs)	14.2	23010.6	5.8
Length Wtd. (ft)	44.32	Wetted Per. (ft)	2.05	33.33	1.48
Min Ch El (ft)	6239.00	Shear (lb/sq ft)	0.04	0.32	0.03
Alpha	1.02	Stream Power (lb/ft s)	200.00	0.00	130.04
Frctn Loss (ft)	0.08	Cum Volume (acre-ft)	0.00	0.10	0.00
C & E Loss (ft)	0.02	Cum SA (acres)	0.00	0.03	0.00

Plan: Default Scenario Channel 01 CH01 RS: 1000 Profile: Sand Creek

E.G. Elev (ft)	6244.00	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.41	Wt. n-Val.		0.013	
W.S. Elev (ft)	6242.59	Reach Len. (ft)			
Crit W.S. (ft)	6242.59	Flow Area (sq ft)		100.49	
E.G. Slope (ft/ft)	0.001866	Area (sq ft)		100.49	
Q Total (cfs)	956.00	Flow (cfs)		956.00	
Top Width (ft)	36.12	Top Width (ft)		36.12	
Vel Total (ft/s)	9.51	Avg. Vel. (ft/s)		9.51	
Max Chl Dpth (ft)	3.59	Hydr. Depth (ft)		2.78	
Conv. Total (cfs)	22130.3	Conv. (cfs)		22130.3	
Length Wtd. (ft)		Wetted Per. (ft)		37.58	
Min Ch El (ft)	6239.00	Shear (lb/sq ft)		0.31	
Alpha	1.00	Stream Power (lb/ft s)	200.00	0.00	0.00
Frctn Loss (ft)		Cum Volume (acre-ft)			
C & E Loss (ft)		Cum SA (acres)			

Channel Report

Overflow Channel

Trapezoidal


Bottom Width (ft) = 80.00
Side Slopes (z:1) = 6.80, 6.80
Total Depth (ft) = 0.50
Invert Elev (ft) = 6265.66
Slope (%) = 1.68
N-Value = 0.017

Highlighted

Depth (ft) = 0.50
Q (cfs) = 289.57
Area (sqft) = 41.70
Velocity (ft/s) = 6.94
Wetted Perim (ft) = 86.87
Crit Depth, Yc (ft) = 0.50
Top Width (ft) = 86.80
EGL (ft) = 1.25

Calculations

Compute by: Q vs Depth
No. Increments = 10



Channel Report

Overflow Channel

Trapezoidal


Bottom Width (ft) = 50.00
Side Slopes (z:1) = 6.80, 6.80
Total Depth (ft) = 1.00
Invert Elev (ft) = 6265.66
Slope (%) = 1.68
N-Value = 0.033

Highlighted

Depth (ft) = 1.00
Q (cfs) = 306.96
Area (sqft) = 56.80
Velocity (ft/s) = 5.40
Wetted Perim (ft) = 63.75
Crit Depth, Yc (ft) = 1.00
Top Width (ft) = 63.60
EGL (ft) = 1.45

Calculations

Compute by: Q vs Depth
No. Increments = 10



Channel Report

Paonia Street Ex.

User-defined

Invert Elev (ft) = 6271.04
Slope (%) = 1.00
N-Value = 0.016

Highlighted


Depth (ft) = 0.89
Q (cfs) = 211.00
Area (sqft) = 35.88
Velocity (ft/s) = 5.88
Wetted Perim (ft) = 69.60
Crit Depth, Yc (ft) = 1.05
Top Width (ft) = 69.57
EGL (ft) = 1.43

Calculations

Compute by: Known Q
Known Q (cfs) = 211.00

(Sta, El, n)-(Sta, El, n)...

(0.00, 6273.30)-(48.06, 6271.58, 0.016)-(86.95, 6271.04, 0.016)-(95.27, 6271.26, 0.016)-(99.33, 6271.58, 0.016)-(135.09, 6273.05, 0.016)



APPENDIX C

REFERENCE MATERIALS



Federal Emergency Management Agency

Washington, D.C. 20472

JAN 30 2007

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

The Honorable Sallie Clark
Chair, El Paso County
Board of Commissioners
27 East Vermijo Avenue
Colorado Springs, CO 80903

IN REPLY REFER TO:

Case No.: 05-08-0368P
Community Name: El Paso County, CO
Community No.: 080059
Effective Date of
This Revision: **MAY 23 2007**

Dear Ms. Clark:

The Flood Insurance Study report and Flood Insurance Rate Map for your community have been revised by this Letter of Map Revision (LOMR). Please use the enclosed annotated map panel(s) revised by this LOMR for floodplain management purposes and for all flood insurance policies and renewals issued in your community.

Additional documents are enclosed which provide information regarding this LOMR. Please see the List of Enclosures below to determine which documents are included. Other attachments specific to this request may be included as referenced in the Determination Document. If you have any questions regarding floodplain management regulations for your community or the National Flood Insurance Program (NFIP) in general, please contact the Consultation Coordination Officer for your community. If you have any technical questions regarding this LOMR, please contact the Director, Federal Insurance and Mitigation Division of the Department of Homeland Security's Federal Emergency Management Agency (FEMA) in Denver, Colorado, at (303) 235-4830, or the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP). Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Sincerely,

Patrick, F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division

For: William R. Blanton Jr., CFM, Chief
Engineering Management Section
Mitigation Division

List of Enclosures:

Letter of Map Revision Determination Document
Annotated Flood Insurance Rate Map
Annotated Flood Insurance Study Report

cc: The Honorable Lionel Rivera
Mayor, City of Colorado Springs

Regional Floodplain Administrator
Pikes Peak Regional Building Department

J. F. Sato and Associates, Inc.

Engineering and Surveying, Inc.



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT

COMMUNITY AND REVISION INFORMATION		PROJECT DESCRIPTION	BASIS OF REQUEST
COMMUNITY	El Paso County Colorado (Unincorporated Areas)	CHANNELIZATION CULVERT	FLOODWAY HYDRAULIC ANALYSIS NEW TOPOGRAPHIC DATA BASEMAP CHANGES
	COMMUNITY NO.: 080059		
IDENTIFIER	Sand Creek Center Tributary and East Fork LOMR	APPROXIMATE LATITUDE & LONGITUDE: 38.846, -104.720 SOURCE: USGS QUADRANGLE DATUM: NAD 27	
ANNOTATED MAPPING ENCLOSURES		ANNOTATED STUDY ENCLOSURES	
TYPE: FIRM*	NO.: 08041C0752 F DATE: March 17, 1997	DATE OF EFFECTIVE FLOOD INSURANCE STUDY: August 23, 1999	
TYPE: FIRM	NO.: 08041C0753 F DATE: March 17, 1997	PROFILE(S): 206P	
TYPE: FIRM	NO.: 08041C0754 F DATE: March 17, 1997	FLOODWAY DATA TABLE: 5	

Enclosures reflect changes to flooding sources affected by this revision.

* FIRM - Flood Insurance Rate Map; ** FBFM - Flood Boundary and Floodway Map; *** FHBM - Flood Hazard Boundary Map

FLOODING SOURCE(S) & REVISED REACH(ES)

Sand Creek Center Tributary – from approximately 1,350 feet upstream of East Frontage Road to just upstream of Galley Road

SUMMARY OF REVISIONS

Flooding Source	Effective Flooding	Revised Flooding	Increases	Decreases
Sand Creek Center Tributary	Zone AE	Zone AE	YES	YES
	Floodway	Floodway	YES	YES
	BFES*	BFES	NONE	YES
	Zone X (shaded)	Zone X (shaded)	YES	YES

* BFES - Base Flood Elevations

DETERMINATION

This document provides the determination from the Department of Homeland Security's Federal Emergency Management Agency (FEMA) regarding a request for a Letter of Map Revision (LOMR) for the area described above. Using the information submitted, we have determined that a revision to the flood hazards depicted in the Flood Insurance Study (FIS) report and/or National Flood Insurance Program (NFIP) map is warranted. This document revises the effective NFIP map, as indicated in the attached documentation. Please use the enclosed annotated map panels revised by this LOMR for floodplain management purposes and for all flood insurance policies and renewals in your community.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency
Washington, D.C. 20472

**LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)**

OTHER COMMUNITIES AFFECTED BY THIS REVISION

CID Number: 080060 **Name:** City of Colorado Springs, Colorado

AFFECTED MAP PANELS

TYPE: FIRM NO.: 08041C0753 F DATE: March 17, 1997
TYPE: FIRM NO.: 08041C0754 F DATE: March 17, 1997

AFFECTED PORTIONS OF THE FLOOD INSURANCE STUDY REPORT

DATE OF EFFECTIVE FLOOD INSURANCE STUDY: August 23, 1999
PROFILE(S): 205P, 206P, 209P, and 210P
FLOODWAY DATA TABLE: 5

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional Information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Patrick F. Sacbbit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency

Washington, D.C. 20472

LETTER OF MAP REVISION DETERMINATION DOCUMENT (CONTINUED)

COMMUNITY INFORMATION

APPLICABLE NFIP REGULATIONS/COMMUNITY OBLIGATION

We have made this determination pursuant to Section 206 of the Flood Disaster Protection Act of 1973 (P.L. 93-234) and in accordance with the National Flood Insurance Act of 1968, as amended (Title XIII of the Housing and Urban Development Act of 1968, P.L. 90-448), 42 U.S.C. 4001-4128, and 44 CFR Part 65. Pursuant to Section 1361 of the National Flood Insurance Act of 1968, as amended, communities participating in the NFIP are required to adopt and enforce floodplain management regulations that meet or exceed NFIP criteria. These criteria, including adoption of the FIS report and FIRM, and the modifications made by this LOMR, are the minimum requirements for continued NFIP participation and do not supersede more stringent State/Commonwealth or local requirements to which the regulations apply.

We provide the floodway designation to your community as a tool to regulate floodplain development. Therefore, the floodway revision we have described in this letter, while acceptable to us, must also be acceptable to your community and adopted by appropriate community action, as specified in Paragraph 60.3(d) of the NFIP regulations.

NFIP regulations Subparagraph 60.3(b)(7) requires communities to ensure that the flood-carrying capacity within the altered or relocated portion of any watercourse is maintained. This provision is incorporated into your community's existing floodplain management ordinances; therefore, responsibility for maintenance of the altered or relocated watercourse, including any related appurtenances such as bridges, culverts, and other drainage structures, rests with your community. We may request that your community submit a description and schedule of maintenance activities necessary to ensure this requirement.

COMMUNITY REMINDERS

We based this determination on the 1-percent-annual-chance flood discharges computed in the FIS for your community without considering subsequent changes in watershed characteristics that could increase flood discharges. Future development of projects upstream could cause increased flood discharges, which could cause increased flood hazards. A comprehensive restudy of your community's flood hazards would consider the cumulative effects of development on flood discharges subsequent to the publication of the FIS report for your community and could, therefore, establish greater flood hazards in this area.

Your community must regulate all proposed floodplain development and ensure that permits required by Federal and/or State/Commonwealth law have been obtained. State/Commonwealth or community officials, based on knowledge of local conditions and in the interest of safety, may set higher standards for construction or may limit development in floodplain areas. If your State/Commonwealth or community has adopted more restrictive or comprehensive floodplain management criteria, those criteria take precedence over the minimum NFIP requirements.

We will not print and distribute this LOMR to primary users, such as local insurance agents or mortgage lenders; instead, the community will serve as a repository for the new data. We encourage you to disseminate the information in this LOMR by preparing a news release for publication in your community's newspaper that describes the revision and explains how your community will provide the data and help interpret the NFIP maps. In that way, interested persons, such as property owners, insurance agents, and mortgage lenders, can benefit from the information.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional Information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

A handwritten signature in black ink, appearing to read "P. Sacbibit".

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency
Washington, D.C. 20472

**LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)**

We have designated a Consultation Coordination Officer (CCO) to assist your community. The CCO will be the primary liaison between your community and FEMA. For information regarding your CCO, please contact:

Ms. Jeanine D. Petterson
Director, Federal Insurance and Mitigation Division
Federal Emergency Management Agency, Region VIII
Denver Federal Center, Building 710
P.O. Box 25267
Denver, CO 80225-0267
(303) 235-4830

STATUS OF THE COMMUNITY NFIP MAPS

We will not physically revise and republish the FIRM and FIS report for your community to reflect the modifications made by this LOMR at this time. When changes to the previously cited FIRM panel(s) and FIS report warrant physical revision and republication in the future, we will incorporate the modifications made by this LOMR at that time.

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

A handwritten signature in black ink, appearing to read "P. Sacbibit".

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division



Federal Emergency Management Agency
Washington, D.C. 20472

LETTER OF MAP REVISION
DETERMINATION DOCUMENT (CONTINUED)

PUBLIC NOTIFICATION OF REVISION

PUBLIC NOTIFICATION

FLOODING SOURCE	LOCATION OF REFERENCED ELEVATION	BFE (FEET NGVD 29)		MAP PANEL NUMBER(S)
		EFFECTIVE	REVISED	
Sand Creek Center Tributary	Approximately 1,350 feet upstream of East Frontage Road	6,170	6,165	08041C0753 F
	Just downstream of Terminal Avenue	6,216	6,213	08041C0754 F

Within 90 days of the second publication in the local newspaper, a citizen may request that we reconsider this determination. Any request for reconsideration must be based on scientific or technical data. Therefore, this letter will be effective only after the 90-day appeal period has elapsed and we have resolved any appeals that we receive during this appeal period. Until this LOMR is effective, the revised BFEs presented in this LOMR may be changed.

A notice of changes will be published in the *Federal Register*. This information also will be published in your local newspaper on or about the dates listed below.

LOCAL NEWSPAPER Name: *El Paso County News*
 Dates: 02/14/2007 02/21/2007

This determination is based on the flood data presently available. The enclosed documents provide additional information regarding this determination. If you have any questions about this document, please contact the FEMA Map Assistance Center toll free at 1-877-336-2627 (1-877-FEMA MAP) or by letter addressed to the LOMR Depot, 3601 Eisenhower Avenue, Alexandria, VA 22304. Additional information about the NFIP is available on our website at <http://www.fema.gov/nfip>.

Patrick F. Sacbibit, P.E., CFM, Project Engineer
Engineering Management Section
Mitigation Division

CHANGES ARE MADE IN DETERMINATIONS OF BASE FLOOD ELEVATIONS FOR THE CITY OF COLORADO SPRINGS AND THE UNINCORPORATED AREAS OF EL PASO COUNTY, COLORADO, UNDER THE NATIONAL FLOOD INSURANCE PROGRAM

On March 17, 1997, the Department of Homeland Security's Federal Emergency Management Agency identified Special Flood Hazard Areas (SFHAs) in the City of Colorado Springs and in the unincorporated areas of El Paso County, Colorado, through issuance of a Flood Insurance Rate Map (FIRM). The Mitigation Division has determined that modification of the elevations of the flood having a 1-percent chance of being equaled or exceeded in any given year (base flood) for certain locations in these communities is appropriate. The modified Base Flood Elevations (BFEs) revise the FIRM for the communities.

The changes are being made pursuant to Section 206 of the Flood Disaster Protection Act of 1973 (Public Law 93-234) and are in accordance with the National Flood Insurance Act of 1968, as amended (Title XIII of the Housing and Urban Development Act of 1968, Public Law 90-448), 42 U.S.C. 4001-4128, and 44 CFR Part 65.

A hydraulic analysis was performed to incorporate new topographic data for Sand Creek Center Tributary from just upstream of Airport Road to just upstream of Galley Road and for Sand Creek East Fork from approximately 970 feet downstream of Powers Boulevard to just downstream of Stewart Avenue. This has resulted in a revised delineation of the regulatory floodway, increases and decreases in SFHA width, and increased and decreased BFEs for both aforementioned flooding sources. The table below indicates existing and modified BFEs for selected locations along the affected lengths of the flooding source(s) cited above.

Location	Existing BFE (feet)*	Modified BFE (feet)*
Sand Creek Center Tributary:		
¹ Approximately 150 feet upstream of Airport Road	6,109	6,108
¹ Approximately 1,250 feet upstream of East Frontage Road	6,168	6,164
² Approximately 1,350 feet upstream of East Frontage Road	6,170	6,165
² Just downstream of Terminal Avenue	6,216	6,213
Sand Creek East Fork:		
¹ Approximately 810 feet downstream of Powers Boulevard	6,099	6,096
¹ Approximately 140 feet downstream of Stewart Avenue	6,206	6,205

*National Geodetic Vertical Datum, rounded to nearest whole foot

¹City of Colorado Springs

²Unincorporated areas of El Paso County

Under the above-mentioned Acts of 1968 and 1973, the Mitigation Division must develop criteria for floodplain management. To participate in the National Flood Insurance Program (NFIP), the community must use the modified BFEs to administer the floodplain management measures of the NFIP. These modified BFEs will also be used to calculate the appropriate flood insurance premium rates for new buildings and their contents and for the second layer of insurance on existing buildings and contents.

Upon the second publication of notice of these changes in this newspaper, any person has 90 days in which he or she can request, through the Chief Executive Officer of the community, that the Mitigation Division reconsider the determination. Any request for reconsideration must be based on knowledge of

changed conditions or new scientific or technical data. All interested parties are on notice that until the 90-day period elapses, the Mitigation Division's determination to modify the BFEs may itself be changed.

Any person having knowledge or wishing to comment on these changes should immediately notify:

The Honorable Sallie Clark
Chair, El Paso County
Board of Commissioners
27 East Vermijo Avenue
Colorado Springs, CO 80903

OR

The Honorable Lionel Rivera
Mayor, City of Colorado Springs
P.O. Box 1575
Colorado Springs, CO 80901

FLOODING SOURCE		FLOODWAY			BASE FLOOD WATER SURFACE ELEVATION			INCREASE
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQ. FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WATER SURFACE ELEVATION		
						WITHOUT FLOODWAY	WITH FLOODWAY	
						FEET (NGVD)		
Sand Creek East Fork	1,100	100	455	11.9	6,038.7	6,038.7	6,038.7	0.0
	2,400	100	446	12.2	6,054.3	6,054.3	6,054.3	0.0
	3,330	100	450	12.0	6,069.9	6,069.9	6,069.9	0.0
	4,240	100	449	12.1	6,085.1	6,085.1	6,085.1	0.0
	4,870	102	446	12.0	6,095.1	6,095.1	6,095.1	0.0
	6,188	70	489	10.9	6,118.5	6,118.5	6,118.5	0.0
	7,403	71	396	13.5	6,136.0	6,136.0	6,136.0	0.0
	7,931	148	507	10.5	6,158.8	6,158.8	6,158.8	0.0
	8,943	98	444	12.0	6,169.0	6,169.0	6,169.0	0.0
	9,666	86	423	12.6	6,177.0	6,177.0	6,177.0	0.0
	10,721	81	415	12.8	6,193.3	6,193.3	6,193.3	0.0
	11,347	166	526	10.1	6,207.3	6,207.3	6,207.3	0.0
	11,375	173	632	8.4	6,207.9	6,207.9	6,207.9	0.0
	12,610	367	699	7.6	6,228.8	6,228.8	6,228.8	0.1
	13,720	188	570	10.0	6,241.7	6,241.7	6,241.7	0.0
	14,805	125	479	11.1	6,257.9	6,257.9	6,257.9	0.0
	14,885	125	601	8.9	6,259.9	6,259.9	6,259.9	1.0
	15,850	228	582	9.2	6,268.7	6,268.7	6,268.7	0.0
	16,325	300	678	7.9	6,277.3	6,277.3	6,277.5	0.2
	16,995	321	690	7.7	6,291.4	6,291.4	6,292.0	0.6
	17,065	326	667	8.0	6,291.4	6,291.4	6,292.1	0.7
	17,915	388	1,598	3.3	6,293.4	6,293.4	6,294.0	0.6
	18,995	367	683	7.8	6,307.2	6,307.2	6,307.6	0.4
	20,525	413	706	7.5	6,326.4	6,326.4	6,327.1	0.7
	22,125	255	620	8.6	6,348.7	6,348.7	6,348.8	0.1
	23,105	397	706	7.6	6,359.9	6,359.9	6,359.9	0.0
24,835	431	705	7.4	6,383.7	6,383.7	6,383.7	0.0	
26,505	353	667	7.8	6,401.0	6,401.0	6,401.5	0.5	

Revised Data

Revised by LOMR dated OCT 07 2004

¹ Feet above confluence with Sand Creek

FEDERAL EMERGENCY MANAGEMENT AGENCY
EL PASO COUNTY, CO
AND INCORPORATED AREAS

FLOODWAY DATA

SAND CREEK EAST FORK

TABLE 5

FLOODING SOURCE		FLOODWAY				BASE FLOOD WATER SURFACE ELEVATION		
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY FEET (NGVD)	WITH FLOODWAY FEET (NGVD)	INCREASE
Sand Creek Center Tributary								
A	940	40	92	8.6	6,106.5	6,106.5	6,106.5	0.0
B	990	40	118	6.7	6,107.2	6,107.2	6,107.2	0.0
C	2,238	91	120	6.6	6,120.2	6,120.2	6,120.2	0.0
D	3,948	46	95	8.0	6,138.3	6,138.3	6,138.3	0.0
E	4,547	170	159	4.8	6,147.4	6,147.4	6,147.4	0.0
F	5,539	52	97	7.8	6,156.8	6,156.8	6,156.8	0.0
G	7,191	63	104	7.3	6,176.2	6,176.2	6,176.2	0.0
H	7,940	52	00	7.8	6,189.6	6,189.6	6,189.6	0.0
I	8,527	40		7.8	6,197.6	6,197.6	6,197.6	0.0
J	9,366	17	42	9.0	6,213.4	6,213.4	6,213.4	0.0
K	10,055	232	278	4.0	6,221.9	6,221.9	6,221.9	0.0
L	10,627	539	469	2.4	6,230.6	6,230.6	6,230.6	0.0
M	11,321	31	79	9.1	6,241.1	6,241.1	6,241.1	0.0
N	11,648	60	99	7.3	6,244.6	6,244.6	6,244.6	0.8
O	12,840	29	85	9.6	6,253.8	6,253.8	6,253.8	0.0
P	13,730	27	83	9.9	6,273.6	6,273.6	6,273.6	0.0
Q	14,592	26	68	9.3	6,299.7	6,299.7	6,299.7	0.0
R	14,670	40	61	6.9	6,304.2	6,304.2	6,305.2	1.0
S	15,050	20	63	10.1	6,307.6	6,307.6	6,308.1	0.5
T	15,460	25	68	9.5	6,310.8	6,310.8	6,311.4	0.6
U	15,750	20	41	7.8	6,319.6	6,319.6	6,319.6	0.0
V	16,670	20	39	8.1	6,346.0	6,346.0	6,346.0	0.0

Flow rate = 792 cfs

Flow rate = 822 cfs

¹ Feet Above confluence with Sand Creek East Fork

FEDERAL EMERGENCY MANAGEMENT AGENCY
EL PASO COUNTY, CO
AND INCORPORATED AREAS


FLOODWAY DATA

Sand Creek Center Tributary

MAY 2007

TABLE 5


ELEVATION IN FEET (NGVD 29)



STREAM DISTANCE IN THOUSANDS OF FEET ABOVE CONFLUENCE WITH SAND CREEK EAST FORK

38°50'37"

104°43'07"



EL PASO COUNTY
UNINCORPORATED AREAS
080059

- Legend**
- 1% annual chance (100-Year) Floodplain
 - 1% annual chance (100-Year) Floodway
 - 0.2% annual chance (500-Year) Floodplain



APPROXIMATE SCALE IN FEET



NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

EL PASO COUNTY,
COLORADO AND
UNINCORPORATED AREAS

PANEL 752 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)

CONTAINS:
COMMUNITY NUMBER PANEL SUFFIX
COLORADO SPRINGS, CITY OF 080059 0752 F
EL PASO COUNTY, UNINCORPORATED AREAS 080059 0752 F



Federal Emergency Management Agency




MAP NUMBER
08041C0752 F
EFFECTIVE DATE:
MARCH 17, 1997

MAY 29 2007

JOINS PANEL 0754


**EL PASO COUNTY
UNINCORPORATED AREAS
080059**

Legend

-  1% annual chance (100-Year) Floodplain
-  1% annual chance (100-Year) Floodway
-  0.2% annual chance (500-Year) Floodplain



APPROXIMATE SCALE IN FEET



NATIONAL FLOOD INSURANCE PROGRAM

**FIRM
FLOOD INSURANCE RATE MAP**

**EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS**

**PANEL 753 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)**

CONTAINS:
COMMUNITY NUMBER PANEL SUFFIX

COLORADO SPRINGS, CITY OF	080060	0753	F
EL PASO COUNTY, UNINCORPORATED AREAS	080059	0753	F


REVISED TO
REFLECT LOMR
EFFECTIVE MAY 23 2007

MAP NUMBER
08041C0753 F

EFFECTIVE DATE:
MARCH 17, 1997



Federal Emergency Management Agency






JOINS PANEL 0754

R66W
R65W

104°43'07"
38°50'37"

JOINS PANEL 0752

EL PASO COUNTY UNINCORPORATED AREAS 080059

- Legend
-  1% annual chance (100-Year) Floodplain
 -  1% annual chance (100-Year) Floodway
 -  0.2% annual chance (500-Year) Floodplain



APPROXIMATE SCALE IN FEET
500 0 500

NATIONAL FLOOD INSURANCE PROGRAM

FIRM FLOOD INSURANCE RATE MAP

EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS

PANEL 754 OF 1300
(SEE MAP INDEX FOR PANELS NOT PRINTED)

CONTAINS:	COMMUNITY	NUMBER	PANEL SUFFIX
	COLORADO SPRINGS, CITY OF	080060	0754 F
	EL PASO COUNTY, UNINCORPORATED AREAS	080059	0754 F


REVISED TO
REFLECT LOMR
EFFECTIVE MAY 23 2007

MAP NUMBER
08041C0754 F
EFFECTIVE DATE:
MARCH 17, 1997



Federal Emergency Management Agency

JOINS PANEL 0753



NOTE: MAP AREA SHOWN ON
THIS PANEL IS LOCATED
WITHIN TOWNSHIP 14 SOUTH,
RANGE 65 WEST.

AREA REVISED
BY LOMR DATED OCTOBER 7, 2004


CITY OF COLORADO SPRINGS
080060

19

SAND CREEK DRAINAGE BASIN PLANNING STUDY

PRELIMINARY DESIGN REPORT

CITY OF COLORADO SPRINGS, EL PASO COUNTY, COLORADO



PREPARED FOR:

City of Colorado Springs
Department of Comprehensive Planning, Development and Finance
Engineering Division
30 S. Nevada
Colorado Springs, Colorado 80903

PREPARED BY:

Kowa Engineering Corporation
1011 North Weber
Colorado Springs, CO 80903

SAND CREEK
DRAINAGE BASIN PLANNING STUDY
PRELIMINARY DESIGN REPORT

Prepared for:

City of Colorado Springs
Department of Comprehensive Planning, Development And Finance
Engineering Division - MAIL CODE 435
P.O. Box 1575
Colorado Springs, CO 80901-1575

Prepared by:

Kiowa Engineering Corporation
1001 North Weber #200
Colorado Springs, CO 80903

KIOWA Project No. 90.04.09
R185

JANUARY 1993
Revised APRIL 1993
Revised FEBRUARY 1995
Revised APRIL 1995
Revised OCTOBER 1995
Revised March 1996

TABLE OF CONTENTS

	Page	Conclusions	
LIST OF TABLES	ii		34
LIST OF FIGURES	iii		
RESOLUTION OF ADOPTION AND ENGINEER'S STATEMENT	iv		
I. INTRODUCTION			
Authorization	1		51
Purpose and Scope	1		51
Summary of Data Obtained	1		52
Mapping and Surveying	2		52
Project Coordination	2		53
Acknowledgements	3		53
II. STUDY AREA DESCRIPTION			
Basin Description	4		53
Climate	4		53
Soils and Geology	4		54
Property Ownership and Impervious Land Densities	4		54
Park Land and Open Space	5		54
III. HYDROLOGIC ANALYSIS			
Runoff Model	8		58
Basin Characteristics	8		58
Previous Studies	8		59
Impervious Land Density	8		
Design Rainfall	9		
Hydrologic Modeling	9		
Results	9		
IV. HYDRAULIC ANALYSIS AND FLOOD PLAIN DESCRIPTION			
Reach Delineation	18		
Flood History	18		
Hydraulic Structure Inventory	19		
Flood Plains	19		
V. EVALUATION OF CONCEPTUAL ALTERNATIVES			
Introduction	31		
Evaluation Parameters	31		
Environmental Review of Mainstem Sand Creek Basin	31		
Environmental Review for the East Fork Sand Creek Drainage Basin	32		
Summary of Drainageway Habitat Zones	33		
Preliminary Matrix of Conceptual Alternatives	33		
Drainageway System Alternatives	33		
VI. DEVELOPMENT OF ALTERNATIVES AND RECOMMENDED PLAN			
Channel Alternatives	38		38
Impact Upon Habitat	39		39
Development of Recommended Plan	40		40
Discussion of Recommended Plan	40		40
VII. PRELIMINARY DESIGN			
Criteria			51
Hydrology			51
Channels			51
Drop Structures and Check Structures			52
Detention			52
Water Quality			52
Trails			53
Maintenance and Revegetation			53
Right-of-Way			53
Roadway Bridge and Culvert Replacements			53
Erosion and Sedimentation Control			54
General			54
VIII. PLAN IMPLEMENTATION			
General			58
Cost Estimate			58
Unplanted Acreage			58
Drainage and Bridge Fee Calculations			59
APPENDIX A:		Project Correspondence	
PRELIMINARY DESIGN DRAWINGS, PLAN, PROFILES AND DETAILS			

LIST OF TABLES

	<u>Page</u>	<u>Page</u>	
Table III-1	Percent Impervious Values	10	
Table III-2	Summary of Peak Discharges - 24-Hour Duration Storm, Baseline Conditions	10	
Table IV-1	Summary of Hydraulic Structures - Crossings	20-25	
Table IV-2	Summary of Hydraulic Structures - Channels	26-29	
Table V-1	Summary of Wildlife Habitat Acreages	35	
Table VI-1	Matrix of Channel Alternatives	43	
Table VI-2	Evaluation of Conceptual Channel Alternatives Floodplain Preservation	44	
Table VI-3	Evaluation of Conceptual Channel Alternatives Channelization	45	
Table VI-4	Evaluation of Conceptual Channel Alternatives Selective Drainageway Improvements	46	
Table VI-5	Evaluation of Conceptual Channel Alternatives West Fork Sand Creek	47	
Table VI-6	Evaluation of Conceptual Channel Alternatives Center Tributary Sand Creek	48	
Table VI-7	Matrix of Recommended Channel Alternatives	49	
Table VII-1	Summary of Peak Discharges Selected Detention Alternative	55	
Table VII-2	Regional Detention Basin Water Quality Storage Requirements	56	
Table VIII-1	Unit Construction Costs	60	
Table VIII-2	Drainageway Conveyance Cost Estimate	61-71	
Table VIII-3	Tributary Drainageway Conveyance Cost Estimate	72-75	
Table VIII-4	Roadway Culvert Crossing Cost Estimate	76-79	
	Table VIII-5	Detention Basin Cost Estimate	80-81
	Table VIII-6	Miscellaneous Drainageway Cost Estimate	82
	Table VIII-7	Bridge Crossing Cost Estimate	83-84
	Table VIII-8	Drainage Basin Fee Estimation	85
	Table VIII-9	City Bridge Fee Calculation	86
	Table VIII-10	County Bridge Fee Calculation	86
	Table VIII-11	Regional Detention Basin Land Fee Calculation	87
	Table VIII-12	Regional Detention Basin Capital Cost Fee Calculation	87

LIST OF FIGURES

	<u>Page</u>
Figure II-1	5
Vicinity Map	
Figure II-2	6
Hydrologic Soils Map	
Figure II-3	7
Proposed Land Use	
Figure III-1	11
Regional Sub-Basins	
Figure III-2	12
Flood Discharge Profile - Mainstem Sand Creek	
Figure III-3	13
Flood Discharge Profile - Center Tributary Sand Creek	
Figure III-4	14
Flood Discharge Profile - West Fork Sand Creek	
Figure III-5	15
Flood Discharge Profile - East Fork Sand Creek	
Figure III-6	16
Flood Discharge Profile - East Fork Sub-tributary	
Figure III-7	17
Flood Discharge Profile - East and West Bierstadt Creeks	
Figure IV-1	30
Reach Delineations	
Figure V-1	36
Detention Basin Alternatives, Sand Creek	
Figure V-2	37
Detention Basin Alternatives, East Fork Sand Creek	
Figure VI-1	50
Channel Alternatives, East Fork Sand Creek	
Figure VII-1	57
Water Quality Pond Capture Volumes	

Resolution No. 189-95

A RESOLUTION ADOPTING THE SAND CREEK DRAINAGE BASIN PLANNING STUDY AND ESTABLISHING A DRAINAGE FEE, A DETENTION POND CAPITAL FEE, A DETENTION POND LAND FEE, AND AN ARTERIAL BRIDGE FEE FOR THE BASIN.

WHEREAS, the City Engineering Division of the City of Colorado Springs Department of Planning and Development has reviewed the Sand Creek Drainage Basin Planning Study as prepared by Kiowa Engineering Corporation, Colorado Springs, Colorado dated November 2, 1995, and

WHEREAS, the City/County Drainage Board has recommended approval of the above study at their November 2, 1995, meeting;

WHEREAS, the Sand Creek Drainage Basin includes unplatted land within the City limits;

NOW THEREFORE, BE IT RESOLVED by the City Council of the City of Colorado Springs:

Section 1. That the Sand Creek Drainage Basin Planning Study, dated November 1995, by Kiowa Engineering Corporation is adopted for use. City Engineering will utilize that study to assist in evaluating subdivision drainage reports.

Section 2. That a Sand Creek Drainage Basin Fee be established as \$4,895/acre, that a Sand Creek Detention Pond Capital Fee be established as \$1,213/acre, that a Sand Creek Detention Pond Land Fee be established as \$167/acre, and that a Sand Creek Arterial Bridge Fee be established as \$323/acre, as part of.

Dated at Colorado Springs, Colorado, this _____ 28th _____ day of _____ November _____, 1995.


Mayor


ATTEST:


City Clerk

ENGINEER'S STATEMENT:

The attached SAND CREEK DRAINAGE BASIN PLANNING STUDY report was prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the City for drainage reports. I accept responsibility for any liability caused by any negligent acts, errors and omissions on my part in preparing this report.

Kiowa Engineering Corporation, 1011 North Weber St., Suite 200, Colorado Springs, CO 80903


Date: 7/26/96

I. INTRODUCTION

Authorization

The preliminary design of the drainageway and roadway crossing facilities within the Sand Creek Drainage Basin was authorized under the terms of Agreement Number 90-85 between the City of Colorado Springs (City) and Kiowa Engineering Corporation. The agreement was approved by the Colorado Springs City Council, April 10, 1990. Subsequent to this agreement, a change order to the contract to allow for the inclusion of technical information contained in the draft East Fork Sand Creek Drainage Basin Planning Study was approved July, 1993.

Purpose and Scope

The purpose of the study is to identify feasible stormwater management plans to satisfy the existing and future needs within the Sand Creek Drainage Basin. The Sand Creek basin is to be referred to throughout this study and is inclusive of the Sand Creek mainstem and East Fork Sand Creek watersheds. The specific scope of work for this study included the following tasks:

1. Meet with the City to: insure compliance with the services required by this agreement, obtain existing data and general information from participating entities, solicit desires of participating entities and other interested agencies or groups in order to develop alternate plans, procure current information relative to development plans in the basin, procure information relative to right-of-way limitations, proposed stormwater projects, potential hazards due to flooding, and avoid duplication of effort whenever possible by utilizing existing information available from other agencies.
2. Contact the City, County, individuals, and other agencies who have knowledge and/or interest in the study area.
3. Utilize City policies and criteria and applicable information wherever possible.
4. Perform hydraulic and hydrologic analyses within the study area.
5. Identify environmental setting of basin.
6. Identify existing and potential drainage and/or flooding problems.
7. Develop improvement alternatives to reduce existing and potential flooding problems, and to mitigate the impact of stormwater runoff upon environmentally significant areas along the drainageway(s).
8. Examine the operation and maintenance aspects of feasible alternatives.

9. Conduct an economic analysis of each alternative.
10. Recommend and prepare a preliminary design for a selected alternative plan.
11. Develop drainage and bridge fees for the basin.
12. Prepare a written report discussing all items examined in the study.
13. Conduct presentations to public and private entities in order to define project goals, and to involve agencies with specific interest to help define feasible alternatives.

Summary of Data Obtained

Listed below are the technical reports collected for the review as part of preparing this study:

1. Soil Survey for El Paso County, Colorado, dated June 1981.
2. "City of Colorado Springs/El Paso County Drainage Criteria Manual", prepared by City of Colorado Springs, El Paso County, and HDR Infrastructure, Inc., dated May 1987.
3. "Flood Insurance Studies for Colorado Springs, and El Paso County, Colorado", prepared by the Federal Emergency Management Agency (FEMA), revised 1989.
4. Flood Insurance Restudy, Hydrology Report and Hydrologic Analyses, prepared by RCI, Inc., 1989.
5. Sand Creek Drainage Basin Planning Study prepared by Simons, Li & Associates, Inc., dated July, 1985.
6. Flood Hazard Analysis, Sand Creek, City of Colorado Springs and El Paso County, Colorado, prepared by the Soil Conservation Service, dated December, 1973.
7. Banning-Lewis Ranch Master Drainage Plan, prepared by MSM Consultants, Inc., dated June 1981.
8. Sand Creek Drainage Basin Study, prepared by United Planning and Engineering Company, October, 1977.
9. Draft East Fork Sand Creek Drainage Basin Planning Study, prepared by Kiowa Engineering Corporation, January, 1989.
10. Drainage Basin Inventory, Sand Creek Drainage Basin, prepared by Oliver E. Watts, P.E., June 1990.

In addition to the above listed reports there were a number of drainage study reports, sketch plans, preliminary and final design drawings, land use and zoning maps, development

plans, and existing drainage facility maps that were collected from the City, County, and other local agencies.

Reports which were prepared previous to the preliminary design report include the "Sand Creek Drainage Basin Planning Study Hydrology Report," and the "Sand Creek Drainage Basin Planning Study Development of Alternatives Report." These reports were prepared as part of the overall planning effort and have been referred to throughout this report. The Hydrology Report summarized peak flow data for existing and future basin development conditions without improvements in the basin, and established the base line hydrologic conditions from which the alternative planning then proceeded. The Development of Alternatives report evaluated the various combinations of drainageway improvements for the basin, taking into account environmental, cost, construction, right-of-way, maintenance and implementation factors for each feasible alternate plan. These reports are on file with the City Engineering Division, as well as technical addenda for each report. Both of these reports covered only the mainstem of the Sand Creek Basin. The similar information prepared for the draft East Fork Sand Creek Drainage Basin Planning Study has been summarized in this preliminary design report.

Mapping and Surveying

Mapping used in the planning effort for the mainstem of Sand Creek consisted of USGS 7-1/2 minute quadrangles, and 2-foot contour interval, 1-inch to 200-foot scale planimetric topographic maps. For the area of the basin north of Woodmen Road, aerial topographic mapping was compiled in May 1990. For the balance of the basin, the City of Colorado Springs Department of Public Utilities provided topographic mapping compiled from aerial photographs dated 1989. This mapping has been prepared as part of the Facility Inventory Management System (FIMS). The aerial topographic mapping was used in the drainage inventory, hydrologic/hydraulic analyses, and in the alternative planning phases of this project. All topographic mapping was based upon USGS vertical datum.

For the East Fork Sand Creek basin, mapping from the FIMS office and two-foot contour interval topography prepared in 1987 for the Banning-Lewis Ranch property were used in the preparation of the preliminary design. Where topographic mapping was not available, USGS quadrangle maps were used.

Stream cross-section data was obtained from the aerial mapping described above. These sections were verified against the cross-sections compiled in the 1986 City of Colorado Springs Flood Insurance Study (FIS), wherever possible.

Drainageway site inspections were conducted throughout the study area, and photographs were taken documenting the key drainage features.

The following general conditions have been placed upon the use of the FIMS topographic mapping:

-- Use of these products is restricted to the project for which the FIMS products are provided.

-- Only the body content found within the headline of the borrowed maps may appear in any report/publication developed for your study. Also, the labeling that appears on any photographs provided shall not appear in any such report/publication.

-- All FIMS' products provided to contractors involved in the subject study shall be retrieved by your department upon conclusion of the study and either returned to FIMS or destroyed.

-- The report(s) developed in which the FIMS' products are used shall include the following disclaimer statement:

"The maps and photographs included in this report were developed for purposes of the Colorado Springs Department of Utilities and are for internal use only. The Colorado Springs Department of Utilities makes no warranty, expressed or implied, as to the completeness, accuracy, or content of such products or any reproductions thereof. Any other use is not recommended and occurs at the risk of the user; such user is solely responsible and/or liable for the use of such products.

Original maps and photographs are the property of the Colorado Springs Department of Utilities. All rights are reserved. These maps and photographs or any associated record may not, wholly or in part, be reproduced, stored, or transmitted in any form or by any means, electronic, mechanical, photocopying, or otherwise, without the express prior written permission of the Colorado Springs Department of Utilities.

Regardless of the existence of purpoed copies of these official maps and photographs which may from time to time be made or published, there is only one set of official maps and photographs, which are those kept and maintained by the Colorado Springs Department of Utilities."

Project Coordination

Throughout the course of the study, meetings were held with representatives of City, County, State, and Federal agencies with an interest in drainageway planning in general. The primary reason for the coordination effort was to obtain technical information and to identify concerns with regard to the development of drainageway facilities within the basin. During the course of preparing the Development of Alternatives report, the planning constraints and concepts were discussed with the agencies and interested individuals and their input used to refine the feasible alternatives and to eventually identify a recommended drainageway plan for further design evaluation. The complete mailing list and project correspondence is contained in Appendix A of this report.

Coordination with a similar list of agencies and individuals was conducted during the preparation of the draft East Fork Sand Creek Drainage Basin Planning study. This study was authorized and conducted for Artes Properties, Inc. Meetings with state and federal agencies, the City and the County were involved in a series of meetings during the development of the alternative planning concepts and the preliminary design for the East Fork Sand Creek basin.

Acknowledgements

During the preparation of the study, several government agencies and interested individuals were routinely involved in the coordination activities. Representatives from the Colorado Division of Wildlife, U.S. Army Corps of Engineers (COE), and various City Departments provided valuable commentary during the development of the alternative plans. A listing of the individuals and agencies routinely coordinated with during the study has been presented below:

<u>Name</u>	<u>Agency</u>
Alan Morrice	El Paso County Department of Public Works
John Fisher	El Paso County Land Use Department
Sue Johnson	El Paso County Parks Department
Rick O'Connor	El Paso County Planning Department
Hugh King	City of Colorado Springs Street Division
Gary Haynes	City Engineering Division
Bruce Thorson	City Engineering Division
Ken Sampley	City Engineering Division
Steve Jacobsen	City Engineering Division
Christine Lytle	City Engineering Division
Bruce Goforth	Colorado Division of Wildlife
Dan Bunting	Regional Building Department
Sarah Fowler	Environmental Protection Agency
John Liou	Federal Emergency Management Agency
Dave Frick	RCI, Inc., Fort Collins, Colorado
Bill Noonan	U.S. Fish and Wildlife
Anita Culp	U.S. Army Corps of Engineers
John Maynard	Aiken/Audobon Society
John Covert	Palmer Foundation
Peter Kernikump	City Planning Department
Jim Rees	Department of Planning and Development
Fred Mais	City Parks and Recreation
Diana Medina	City of Colorado Springs
Dan Tippie	Department of Public Utilities Gas Division
Russ Nicklin	City of Colorado Springs
Wes Tyson	Department of Public Utilities Wastewater Division
	Department of Public Utilities Water Division
	City Attorney's Office

II. STUDY AREA DESCRIPTION

The Sand Creek drainage basin is a left-bank tributary to the Fountain Creek lying in the west-central portions of El Paso County. Sand Creek's drainage area at Fountain Creek is approximately 54 square miles of which approximately 18.8 square miles are inside the City of Colorado Springs corporate limits. The basin is divided into five major sub-basins, the Sand Creek mainstem, the East Fork Sand Creek, the Central Tributary to East Fork, the West Fork, and the East Fork Subtributary. Figure II-1 shows the location of the Sand Creek basin.

Basin Description

The Sand Creek basin covers a total of 54 square miles in unincorporated El Paso County and Colorado Springs, Colorado. Of this total, approximately 28 square miles is encompassed by the Sand Creek basin, and 26 square miles for the East Fork Sand Creek basin. The basin trends in generally a south to southwesterly direction, entering the Fountain Creek approximately two miles upstream of the Academy Boulevard bridge over Fountain Creek. Two main tributaries drain the basin, those being the mainstem of Sand Creek and East Fork Sand Creek. Development presence is most evident along the mainstem. At this time, approximately 25 percent of the basin is developed. This alternative evaluation focuses upon the Sand Creek basin only.

The maximum basin elevation is approximately 7,620 feet above mean sea level, and falls to approximately 5,790 feet at the confluence with Fountain Creek. The headwaters of the basin originate in the conifer covered areas of The Black Forest. The middle eastern portions of the basin are typified by rolling range land with fair to good vegetative cover associated with semi-arid climates.

Climate

This area of El Paso County can be described, in general as high plains, with total precipitation amounts typical of a semi-arid region. Winters are generally cold and dry. Precipitation ranges from 14 to 16 inches per year, with the majority of this precipitation occurring in spring and summer in the form of rainfall. Thunderstorms are common during the summer months, and are typified by quick-moving low pressure cells which draw moisture from the Gulf of Mexico into the region. Average temperatures range from about 30°F in the winter

to 75° in the summer. The relative humidity ranges from about 25 percent in the summer to 45 percent in the winter.

Soils and Geology

Soils within the Sand Creek basin vary between soil types A through D, as identified by the U. S. Department of Agriculture, Soil Conservation Service. The predominant soil groupings are in the Truckton and Bresser soil associations. The soils consist of deep, well drained soils that formed in alluvium and residuum, derived from sedimentary rock. The soils have high to moderate infiltration rates, and are extremely susceptible to wind and water erosion where poor vegetation cover exists. In undeveloped areas, the predominance of Type A and B soils give this basin a lower runoff per unit area as compared to basins with soils dominated by Types C and D. Presented on Figure II-2 is the Hydrologic Soil distribution map for the Sand Creek basin.

Property Ownership and Impervious Land Densities

Property ownership along the major drainage way within the Sand Creek basin vary from public to private. Along the developed reaches, drainage right-of-ways and greenbelts have been dedicated during the development of the adjacent residential and commercial land. Where development has not occurred, the drainageways remain under private ownership with no delineated drainage right-of-way or easements. There are several public parks which abut the mainstem of Sand Creek. Roadway and utility easements abutting or crossing the major drainageways occur most frequently in the developed portions of the basin.

Land use information for the existing and future conditions were reviewed as part of the planning effort. This information is used in the hydrologic analysis to predict runoff rates and volumes for the purposes of facility evaluation. The identification of land uses abutting the drainageways is also useful in the identification of feasible plans for stabilization and aesthetic treatment of the creek. Presented on Figure II-3 is the proposed land use map used in the evaluation of impervious land densities discussed in the hydrologic section of this report. Figure II-3 is not intended to reflect the future zoning or land use policies of the City or the County.

The land use information within the Banning-Lewis Ranch property was obtained from Aries Properties during the time the draft East Fork Sand Creek Drainage Basin Planning Study was being prepared. The land use information was again reviewed with the City of Colorado Springs Department of Planning and was found to be appropriate for use in the estimation of hydrology for the East Fork Basin. The location of future arterial streets and roadways within

the Banning Lewis property were obtained from the Banning-Lewis Ranch master plan. The location of roadways offsite from the Banning Lewis-Ranch were obtained from the El Paso County Major Transportation Plan dated 1988.

Park Land and Open Space

An inventory of park land and public open space was prepared. Many times, the combination of the drainageway and adjacent park lands can be used to visually extend the limits of a park or open space. The drainageway can also act to link parks and other land uses within the basin if multiple use trails are incorporated into the channel section(s). The Sand Creek drainageway has been identified as a major trail corridor within the City of Colorado Springs Trails Plan. Park land designated within the Banning-Lewis Ranch master plan were taken into account during the siting of stormwater facilities within the Banning-Lewis property.




TABLE IV-1. SUMMARY OF HYDRAULIC STRUCTURES - CROSSINGS
SAND CREEK DRAINAGE BASIN PLANNING STUDY

LOCATION	REACH #	SIZE	TYPE	CAPACITY EXISTING	CAPACITY FUTURE (1)	COMMENTS
Airport Road	CT-1	5-6'x8'	BOX CULVERT	ADEQUATE	ADEQUATE	
Pikes Peak Ave.	CT-1	NONE		INADEQUATE	INADEQUATE	POWERS BLVD. OVERTOPPED FREQUENTLY BETWEEN BLOU ST. AND PIKES PEAK AVE.
Powers Blvd.	CT-1	VARIOUS	METAL PIPE	INADEQUATE	INADEQUATE	
Platte Ave (US 24)	CT-1	8'x4'	BOX CULVERT	INADEQUATE	INADEQUATE	APPROACH CHANNEL IN NEED OF REALIGNMENT
Terminal Avenue	CT-2	2-4'x3'	BOX CULVERT	INADEQUATE	INADEQUATE	
Galley Road	CT-2	3-42'x72"	METAL ARCH PIPE	INADEQUATE	INADEQUATE	
Omaha Boulevard	CT-2	2-36'x37"	METAL ARCH PIPE	INADEQUATE	INADEQUATE	
Powers Boulevard	EFSC-2	90' clear span	CONCRETE BRIDGE	ADEQUATE	ADEQUATE	NEW BRIDGE
Stewart Street	EFSC-2	140'	CONCRETE BRIDGE	ADEQUATE	ADEQUATE	
US 24/Platte Ave	EFSC-2	290'	CONCRETE AND TIMBER BRIDGE	ADEQUATE	ADEQUATE	LIMITED BANK PROTECTION AT INLET AND OUTLET OF BRIDGE
Peterson Road	EFSC-2	4-36"	METAL PIPE	INADEQUATE	INADEQUATE	
Marksheffel Road	EFSC-2	2-36"	METAL PIPE	INADEQUATE	INADEQUATE	

TABLE IV-2: SUMMARY OF HYDRAULIC STRUCTURES - CHANNELS
SAND CREEK DRAINAGE BASIN PLANNING STUDY

LOCATION FROM / TO	REACH #	DIMENSIONS (ft)		TYPE	CAPACITY (1) ADQ. INADQ.	COMMENTS
		TW	SS DEPTH			
CENTER TRIBUTARY						
East Fork Sand Creek to Airport Road	CT-1	45	2:1 6	Riprap lined trapezoidal channel	X	Riprap has failed or is non-existent along some portions of this segment of the Center Tributary
Pikes Peak to Bijou St.	CT-1		N/A	Rubble lined ditches along Powers Blvd.		Flow passes over and along Powers Blvd. street section on a frequent basis. Road closures common.
Bijou St. to Platte Ave.	CT-1		N/A	Unlined, natural.		Overbanks vegetated, channel dry with sand invert, no vegetation. Channel eroded at outlet of US24 culvert.
Platte Ave. to Terminal Ave.	CT-2	15-25	1:1 4-6	Trapezoidal concrete lined.	X	Channel has adequate capacity.
Terminal Avenue to Galley Road	CT-2	21	1:1 5	Trapezoidal concrete lined.	X	Channel has adequate capacity.
Galley Road to Pacoma Ct. (ext)	CT-2	30-40	varies 4-5	Unimproved segment.	X	Channel is degraded and filled with debris. Poor maintenance access.
Pacoma Ct. to Omaha Blvd.	CT-2	21	1:1 5	Trapezoidal concrete lined channel.	X	Maintenance access poor. Debris and trash in channel.
Omaha Blvd. to Palmer Park Blvd.	CT-2	19	1:1 4	"	X	Storm sewers outfall to channel near Palmer Park.

VI. DEVELOPMENT OF ALTERNATIVES AND RECOMMENDED PLAN

The concepts which are available for handling stormwater runoff within the Sand Creek basin have been presented and discussed in detail in the Sand Creek Drainage Basin Planning Study Development of Alternatives Report and the draft East Fork Sand Creek Drainage Basin Planning Study. The process of combining the various channel treatment options, detention schemes and roadway crossing structures into a contiguous plan for all of the reaches is presented in this chapter of the report. As a result of the evaluation of the flood control, environmental, open space, operations and maintenance, and implementation concerns within the Sand Creek basin, the following concepts were identified as having sufficient feasibility to warrant further evaluation and review:

- Channel Concepts:
 - Floodplain Preservation
 - Channelization, 10- or 100-year
 - Selective Improvements
- Detention:
 - Regional detention systems

Channel Concepts: The channel concepts listed above have been evaluated with respect to the parameters listed in the previous chapter. A concept's feasibility depends upon its impact, positive or negative, upon the evaluation parameters. *The floodplain preservation* concept has been considered to be the same as the *"do-nothing"* alternative. The floodplain preservation concept would involve the regulation of the floodplain limits, generally as depicted on the effective City of Colorado Springs and El Paso County Flood Insurance Rate Maps. Regulation of the floodplain so that future encroachments are minimized and the floodproofing of structures which are currently within the 100-year floodplain would presumably be the methods used to address the flood hazard concerns along Sand Creek. In the upper reaches of Sand Creek, the ownership or easements associated with the 100-year floodplain (or greater limits to allow for an erosion buffer zone) would be a primary issue in regards to implementation of such a concept. Detention in the upper reaches of the basin Sand Creek basin and in the East Fork Sand Creek basin will maintain the 100-year floodplain at existing limits within the lower reaches of Sand Creek. The "do-nothing" concept is feasible wherever

the existing drainageway improvements are of adequate capacity to convey flood flows. *Channelization* would involve the lining of the Creek into a more confined flow area, and could be done for either the *100-year or 10-year* flood discharges. Several typical channel concepts have been presented. The primary bank lining material would probably be riprap. Grade control and/or drop structures would be required in a channelization concept so that the flood velocities could be controlled to a level requiring medium to heavy riprap. Soil cement offers an alternative to riprap and concrete for the construction of drops or grade control structures. Revegetation would occur wherever the native vegetation was disturbed by the channel construction. Willows at the toe of the riprap banks would be a minimum replacement. *Selective linings* would involve the construction of grade controls, drop structures, bank linings, storm sewer outlet control structures selectively sited to resist stream erosion or to reduce potential flooding damages. Areas of future concern such as at the outside bends of the creek, or at the outlets of bridges or culverts which will cross the drainageway would be subject to selective improvements.

Detention Concepts: The two general detention concepts evaluated were onsite versus regional detention. During the evaluation process, it was determined that the onsite detention concept has a low feasibility relative to a regional concept. This is because, (1) onsite detention has a unpredictable impact upon lowering peak discharges from urbanized areas to historic conditions (reference, Urbonas and Glidden, "Effect of Detention on Flows in Major Drainageways" ASCE Water Forum '81, 1981), (2) an onsite concept has little impact upon maintaining or enhancing water quality, (3) the number of onsite detention basins, their locations and size cannot be accurately determined in the undeveloped portions of the basin at this time, and (4) onsite detention would present a substantial maintenance responsibility to the jurisdictions involved. For these reasons the onsite detention concept was eliminated and regional detention basin concepts were developed. In the analysis of the channel concepts, regional detention facilities were assumed to be in place.

Channel Alternatives

Presented on Table VI-1 is a matrix of channel alternatives which were evaluated. All reaches of Sand Creek and the East Fork of Sand Creek had at least three alternatives analyzed. Presented on Tables VI-2 through VI-6 are comparative evaluations of the floodplain preservation (do-nothing), channelization and selective lining concepts, for the mainstem Sand Creek basin, by reach. The purpose of the evaluation process was to identify the relative advantages and disadvantages of each concept within each reach.

Presented on Figure VI-1 are the alternative channel concept plans for each reach of the East Fork Sand Creek Basin. Alternative 1, "prismatic or composite" channel shown on Figure VI-1 is synonymous with the "channelization" concept developed for the mainstem Sand Creek basin. Alternative 2, "stabilized floodplain section" shown on Figure VI-1 is synonymous with the "selective improvement" concept developed for the mainstem of Sand Creek. Floodplain preservation or the "do-nothing" concept was evaluated for all reaches of the East Fork.

For the channelization and selective improvement concepts, cost comparisons have been completed. Similarly, cost estimates for each of the detention concepts were developed. The cost of property acquisition for land lying outside of the 100-year floodplain limits and for detention basins will have to be accounted for during the calculation of the drainage basin fee for the Sand Creek basin. The cost evaluation and detailed discussion related to the various channelization and detention concepts are contained within the Sand Creek Drainage Basin Planning Study Development of Alternatives Report and the draft East Fork Sand Creek Drainage Basin Planning Study.

Impact Upon Habitat

For each of the channel alternatives evaluated within the mainstem Sand Creek basin an estimate of each alternative's potential for disturbance of the habitat was made. The acreages presented previously on Table V-1 for the Class I and Class II habitat zones were used in determining the extent of disturbance which a particular alternative may entail if implemented within a given reach. Since it is the goal of planning process to identify concepts which will avoid disturbances to the existing habitat wherever practical, alternatives which would have a greater level of disturbance compared to another must have provisions for mitigating the disturbance. Typical disturbances caused by channelization would include loss of native toe and/or bank vegetation, filling of historic floodplains which may contain wetland or riparian habitat, or degradation of water quality to downstream areas resulting from flow concentrations within unlined areas. Selective improvements could create very similar disturbances as channelization, however because the improvements can be selectively sited, avoidance of disturbances is easier to achieve. The floodplain preservation concept has the potential for disturbance to habitat. The loss of toe and bank vegetation can occur over time from natural erosion of the invert and banks which are unlined. This is currently the situation in Reach 1 of Sand Creek.

For those concepts requiring mitigation, the cost of habitat mitigation needs to be included in the total cost for a particular concept if a fair comparison is to be made. A

comparison of the estimated potential disturbance acreages of the Class I and II habitat was made for each of the alternative channelization schemes. From this evaluation it was determined that the greatest total Class I and Class II habitat disturbance would result from the implementation of the 100-year channelization concept. The disturbances to the habitat could be mitigated by the re-establishment of the toe vegetation, and by replacing riparian habitat along the overbanks of the channel. The total disturbance for a 10-year channel concept is reduced from the case of the 100-year channel. Greater opportunities for habitat preservation and replacement are afforded by a 10-year concept since a residual 100-year floodplain would remain.

The least total disturbance acreage occurs for the floodplain preservation or a selective improvement concept. Some loss of habitat would occur naturally, mainly along the toe and at low channel benches due to the long-term degradation of the invert, and localized bank erosion. Water quality for the downstream reaches would not be improved by a floodplain preservation concept alone because of increasing rates of sediment transport due to increasing low flows and unlined banks and/or inverts. After a bank or invert failure, it would be anticipated that the native vegetation would eventually replace itself over a period of years.

Implementation of a selective improvement plan would result in a slight reduction in potential disturbance area as compared to the floodplain preservation concept. This is because selective improvements, if constructed prior to the onset of active bank and invert erosion, would prevent the loss of native habitat along the existing low flow banks and in floodplain areas. Disturbances due to construction could be better controlled with a selective improvement concept.

Though the above impacts were not specifically quantified for the East Fork basin, the relative advantages and disadvantages between the channelization concepts with regard to habitat impact for the East Fork are basically the same as for the mainstem Sand Creek. Since the East Fork basin is mostly undeveloped and the drainageways relatively unencroached at this time, there is an opportunity to select channel concepts which will result in little or no adverse impact to the existing habitat. In fact, some opportunity for enhancement of the habitat areas is possible in the future by developing channelization plans which will take advantage of the flood control, erosion control and water quality benefits that can be afforded by the natural floodplain zones and detention areas.

100-year peak discharge to levels. This will allow for the channel improvements to be constructed within the existing right-of way.

Reaches SC-5 and SC-6: A selective channel improvement concept has been recommended for these reaches. Detention in Reach SC-8 of the basin will maintain flows to historic peak discharge levels, however the low flows will increase in frequency and volume. For this reason it has been recommended to provide riprap channel linings at selective locations to at least the 10-year water surface and install grade controls. This will prevent the long-term degradation of the invert. A residual 100-year floodplain will remain and will offer opportunities for habitat replacement and open space preservation. Land adjacent to the drainageway is currently undeveloped or unplatted at this time which makes the feasibility of implementing this concept greater in comparison to the urbanized reaches of the creek.

Reaches SC-7 and SC-8: A selective improvement concept involving the localized lining of channel banks and grade control construction has been recommended for these reaches. The feasibility of this concept stems from the fact that flows will be reduced because of detention. Numerous individual rural ownerships cross the drainageway, however no habitable structures lie within the 100-year floodplain. Because of this, the economic feasibility of channelization concepts is low. Non-structural measures can be used to limit encroachments into floodprone areas. Additionally, the City of Colorado Springs Comprehensive plan recommends that the floodplains be maintained as open space. Potential habitat disturbances can be avoided with a selective plan, or simply replaced as part of the particular construction activity which caused the disturbance.

Reach SC-9: A floodplain preservation concept has been recommended for this reach. Little increase in urbanization is anticipated in this reach, and for this reason the existing drainageway is expected to remain stable. Localized improvements may be necessary to limit erosion caused by flow concentrations at culverts or storm sewers. Private ownership of the drainageway is anticipated to continue which lower the feasibility of channel concepts which require permanent right-of-ways or easements for construction and maintenance.

Reaches WF-1 through WF-3: A 100-year channel concept has been recommended for these reaches primarily because of the potential for flooding damages. Several roadway crossings are in need of replacement because of the flood hazard the constrictions create. Some open space enhancement potential exists for this concept since these reaches have been degraded visually by debris accumulation, bank sloughing and sedimentation. Little opportunity exists for widening the drainageway because the

Development of the Recommended Plan

Presented on Table VI-7 is a matrix representing the recommended plan for each major drainageway reach. The selection of a recommended channel treatment scheme has been based upon the qualitative and quantitative information presented in the Sand Creek Drainage Basin Planning Study Development of Alternatives report and the draft East Fork Sand Creek Drainage Basin Planning Study. Contained within the Technical Addendum to the Sand Creek Drainage Basin Planning Study Development of Alternatives report, is the alternative hydrologic, hydraulic and conceptual cost data used in the evaluation and comparison of each of the alternatives within the mainstem Sand Creek basin.

Discussion of Recommended Plan

The recommendation of a particular channel treatment or detention scheme has been based upon the qualitative and quantitative data presented. For each reach the flood hazard, environmental, cost, operations and maintenance and open space aspects of the drainageway were weighed for each alternative concept.

Reach SC-1: For this reach a 10-year channel section was recommended for further evaluation. With the implementation of regional detention in the upper basin, the 100-year floodplain will generally be confined within the existing banks, excepting at roadway crossings lacking 100-year capacity. It is recommended that a 10-year low flow channel be constructed within the invert of the existing channel through the construction of benches and sand bars. As urbanization continues towards the full development scenario, the base flow and annual flows will increase in volume and frequency. For this reason, the low flow area must be stabilized to protect the existing channel banks from undermining and subsequent bank sloughing. The benched areas offer an opportunity for habitat replacement and enhancement. At some locations within this reach, a residual 100-year floodplain will remain which will have to be regulated. The residual 100-year floodplain offers some potential for open space preservation and enhancement. This is particularly true in the portion of the reach downstream of Hancock Expressway.

Reaches SC-2 through SC-4: A 100-year channel concept has been recommended primarily because of the potential for flooding damages which exists in these reaches. Habitat disturbed by the construction of channel linings and grade control structures could be replaced along the channel toes and on the overbanks. The replacement of the Waynoka Road crossing will reduce the potential for flood damages in areas adjacent to these roadways. The detention within the upper reaches will limit the

drainageway is confined within narrow right-of-ways between existing urban developments.

Reaches CT-1 and CT-2: A 100-year channel concept has been recommended because of flood hazard considerations. Urbanization has altered and blocked the natural drainage path for the majority of these reaches. A limited amount of habitat native to the drainageways was found during the environmental review. Revegetation at the top of the channel banks and along the toe of the riprap banks offers some opportunity for open space visual enhancement. The existing flow path has been visually degraded by debris dumping, excessive sediment deposition and sloughing of unprotected banks.

Reach EFSC-1: A 100-year riprap channel has been proposed for this reach of the East Fork. This reach passes through predominantly developed portions of Colorado Springs. Along some segments of this reach riprap has been placed, however the integrity and the continuity of the riprap lining is poor and in need of replacement. Check and drop structures are also recommended within this reach. This reach will be impacted significantly in the future by long duration stormwater releases from the detention basins lying in the reaches upstream of Reach EFSC-2.

Reach EFSC-2: This reach passes through mostly undeveloped areas of Colorado Springs and El Paso County. New bridges are needed at Marksheffel Road, Peterson Road and at an un-named roadway within Peterson Air Force Base. From the confluence with the Center Tributary to Marksheffel Road a 100-year riprap channel concept is recommended. Above Marksheffel Road to the confluence with the East Fork Sub-tributary, a 10-year channel concept and with floodplain preservation is recommended. Channel drop structures and checks are also required to limit the future degradation of the invert. As with reach EFSC-1, this reach will be impacted by stormwater releases from the East Fork Sand Creek detention basins.

Reach EFSC-3: A 10-year riprap lined channel and 100-year floodplain preservation is recommended. Future stormwater discharges through this reach will be limited to historic levels by the upstream regional detention basins. Check structures are recommended to counteract the degrading effect of the long duration discharges from the upstream detention basins. The concept through this reach is to leave the channel bottom width at its current location, thereby limiting the encroachment of fill into the floodway.

Reach EFSC-4: The most significant feature of the recommended plans in this reach is regional detention basin EFSC-#1. This basin will be the lowest flow control point along the East Fork Creek acting to limit discharges to historic levels from the development within the Banning-Lewis Ranch. A 10-year riprap channel is recommended for the segments of the reach above and below detention basin EFSC-#1.

Bridges will be required for proposed Stapleton Drive, Banning-Lewis Parkway and North Carefree Circle. This reach will pass through commercial and industrial areas. The incorporation of the future drainageway and detention basin into a linear open space use is recommended.

Reach EFSC-5: As with reach EFSC-4, the most significant feature of this reach basin is the EFSC-#2 region detention basin. This detention basin is located at an existing embankment which maintains a permanent pool. It is recommended that the detention basin be designed to maintain the permanent pool so that the water quality benefits of a "wet" basin are maximized. The recommended section is a 10-year riprap channel with 100-year floodplain preservation. Check and drop structures are recommended to flatten the gradient of the drainageway and to slow the developed stream velocities to manageable levels. This reach passes through commercial and single-family areas. As with reach EFSC-4, it is recommended that the drainageway and detention basin be incorporated into a linear open space use in the future. A 100-year bridge is needed at proposed Barnes Road.

Reach EFSC-6: This reach includes regional detention basin EFSC-#3. Similar to detention basin EFSC-#2, this detention basin has been sited at an existing embankment which maintains a permanent pool. The permanent pool should be maintained in the design of the regional basin as part of a water quality measure for the basin. A 10-year riprap channel with floodplain preservation is recommended for this reach. Channel drops and checks are recommended to limit the long-term degradation of the invert. A 100-year capacity bridge is required at future Bridlespur Road.

Reach EFSC-7: This reach contains detention basin EFSC-#4. This detention basin is a dry basin, and would be formed by the construction of an embankment and an outlet structure. The embankment and outlet structure could be combined with the roadway improvements for Bridlespur Road. A twin box culvert is proposed at future Bridlespur Road. A 10-year low flow channel and floodplain preservation concept is recommended from the detention basin to future Dublin Road. Above Dublin, a 100-year riprap channel is recommended, extending upstream to Woodmen Road.

Reach EFSC-8: This reach begins at Woodmen Road, and extends northward into the Black Forest area. The recommended improvements for this reach are selective riprap linings with grade control structures. A 100-year box culvert is recommended for Woodmen Road. A 100-year capacity box culvert is recommended for proposed Research Parkway.

Reach EFST-1: This reach begins at the confluence with the mainstem of East Fork Sand Creek, and extends northward to future Barnes Road. Contained in this reach is regional detention basin EFST-#1, located upstream of the existing Chicago and Rock Island railroad embankment. The recommended channel improvement is a 100-year riprap channel with grade control and drop structures, up to the outlet of EFST-#1 detention basin. Above the regional detention basin, a 10-year capacity low flow channel and grade control is recommended to Barnes Road. A 100-year capacity box culvert is recommended for proposed Barnes Road. The existing channel improvements within the Markshoeffel Industrial Park which is located just south of the Chicago and Rock Island Railroad are recommended to remain.

Reach EFST-2: This reach begins at the proposed Barnes Road and extends northward to approximately 3/4-mile north of proposed Dublin Road. The recommended channel improvement is a 100-year riprap channel with drops, aligned parallel to future Stapleton Drive. Culverts with a 100-year capacity are recommended at future Bridlespur Road and Dublin Road.

Reach TR-1: This reach begins at the confluence with the East Fork Sub-tributary and extends northward through the Toy Ranches Subdivision, a rural subdivision within El Paso County. The recommended channel improvement is selective riprap linings with grade control. A new culvert is proposed at Tamlin Road and at future Bridlespur Road (existing Huber Road). The drainage way crosses through private property within the Toy Ranches subdivision, and easements will have to be obtained from property owners to construct and maintain the proposed channel improvements for this reach.

Reach TR-2: This reach begins at the confluence with reach TR-1, and extends northward through the Toy Ranches Subdivision. The recommended channel improvement is selective riprap linings with grade control. A new culvert is proposed at future Bridlespur Road. As with TR-1, the drainage way crosses through private property within the Toy Ranches subdivision, and easements will have to be obtained from property owners to construct and maintain the proposed channel improvements for this reach.

Reach TR-3: This reach begins at the north boundary of the Toy Ranches Subdivision. Regional detention basin TR-#1 is contained within this reach. This regional detention basin is needed in order to maintain future peak discharges which enter the Toy Ranches Subdivision to existing levels. The recommended channel improvement is selective riprap linings with grade control. A new culvert is proposed at future Dublin Road.

Reach EB-1: This reach of East Bierstadt Creek begins at the confluence with the mainstem of East Fork Sand Creek, just upstream of future Barnes Road. The recommended channel improvement is a 10-year riprap channel with 100-year floodplain preservation and grade control structures. This reach ends at the confluence with West Bierstadt Creek.

Reach EB-2: This reach begins at the confluence with West Bierstadt Creek, approximately 3/4-mile upstream of future Barnes Road. The recommended channel improvement is a 100-year riprap channel and drop structures. Culverts with a 100-year capacity are proposed at a future un-named arterial roadway and a future Bridlespur and Dublin roads. A new culvert is proposed under the existing Chicago Rock Island and Pacific railroad grade.

Reach WB-1: This reach begins at the confluence with East Bierstadt Creek and extends northward to the existing Chicago and Rock Island and Pacific railroad grade. The recommended channel improvement is a 100-year riprap channel and drop structures. Culverts with a 100-year capacity are proposed at a future un-named arterial roadway and a future Bridlespur Road.


Reach WB-2: This reach begins at the existing Chicago and Rock Island and Pacific railroad grade and extends northward to approximately one mile north of Woodmen Road. Below Woodmen Road, the recommended channel improvement is a 100-year riprap channel and drop structures. North of Woodmen Road, the recommended drainage way improvements are selective riprap banks with grade control structures. Culverts with a 100-year capacity are proposed at a future Dublin Road and at Woodmen Road.

FLOOD INSURANCE STUDY



EL PASO COUNTY, COLORADO, AND INCORPORATED AREAS

El Paso County



COMMUNITY NAME	COMMUNITY NUMBER
CALHAN, TOWN OF	080192
COLORADO SPRINGS, CITY OF	080060
EL PASO COUNTY (UNINCORPORATED AREAS)	080059
FOUNTAIN, CITY OF	080061
GREEN MOUNTAIN FALLS, TOWN OF	080062
MANITOU SPRINGS, CITY OF	080063
MONUMENT, TOWN OF	080064
PALMER LAKE, TOWN OF	080065
RAMAH, TOWN OF	080066

Revised: December 7, 2018



Federal Emergency Management Agency

FLOOD INSURANCE STUDY NUMBER
08041CV007A

NOTICE TO
FLOOD INSURANCE STUDY USERS

Communities participating in the National Flood Insurance Program have established repositories of flood hazard data for floodplain management and flood insurance purposes. This Flood Insurance Study (FIS) report may not contain all data available within the repository. It is advisable to contact the community repository for any additional data.

Part or all of this FIS report may be revised and republished at any time. In addition, part of this FIS report may be revised by the Letter of Map Revision process, which does not involve republication or redistribution of the FIS report. It is, therefore, the responsibility of the user to consult with community officials and to check the community repository to obtain the most current FIS report components.


This FIS report was revised on December 7, 2018. Users should refer to Section 10.0, Revisions Description, for further information. Section 10.0 is intended to present the most up-to-date information for specific portions of this FIS report. Therefore, users of this report should be aware that the information presented in Section 10.0 superseded information in Sections 1.0 through 9.0 of this FIS report.

Initial Countywide FIS Report Effective Date: March 17, 1997

First Revised Countywide FIS Report Effective Date: August 23, 1999 - to add base flood elevations, to add special flood hazard areas, and to change special flood hazard areas.



Second Revised Countywide FIS Report Effective Date: December 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

FLOOD PROFILES



S
P
R
I
N
G
S

E
D



NFP

PANEL 0752G

FIRM
FLOOD INSURANCE RATE MAP
EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS

PANEL 752 OF 1300
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
COLORADO SPRINGS, CITY OF	080060	0752	G
EL PASO COUNTY	080059	0752	G

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
08041C0752G

MAP REVISED
DECEMBER 7, 2018

Federal Emergency Management Agency

NATIONAL FLOOD INSURANCE PROGRAM

1370000 FT


38° 50' 37.50"

104° 43' 7.50"

525000m E

JOINS PANEL 0754

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov



© 2019 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS © 2019 HERE