

FINAL DRAINAGE REPORT

for


WALDEN PRESERVE 2 – FILING NO. 4

Prepared for:

Custom Castles, Inc.
17145 Colonial Park Drive
Monument, CO 80132

September 5, 2018
Revised February 26, 2019
Revised May 16, 2019

Prepared by:



19 E. Willamette Avenue
Colorado Springs, CO 80903
(719)-477-9429
www.jpsegr.com


JPS Project No. 040201
PCD File No. SF-18-034

**WALDEN PRESERVE 2 – FILING NO. 4
FINAL DRAINAGE REPORT
TABLE OF CONTENTS**

| | <u>PAGE</u> |
|--|-------------|
| EXECUTIVE SUMMARY | i |
| DRAINAGE STATEMENT | ii |
| FLOODPLAIN STATEMENT | iii |
| I. GENERAL LOCATION AND DESCRIPTION..... | 1 |
| II. DRAINAGE BASINS AND SUB-BASINS..... | 3 |
| III. DRAINAGE DESIGN CRITERIA | 4 |
| IV. DRAINAGE PLANNING FOUR STEP PROCESS..... | 6 |
| V. GENERAL DRAINAGE RECOMMENDATIONS | 6 |
| VI. DRAINAGE FACILITY DESIGN | 7 |
| VII. EROSION / SEDIMENT CONTROL | 14 |
| VIII. COST ESTIMATE AND DRAINAGE FEES..... | 14 |
| IX. SUMMARY | 15 |

APPENDICES

| | |
|--------------|---|
| APPENDIX A | Soils Information |
| APPENDIX B 1 | Hydrologic Calculations – SCS Method |
| APPENDIX B2 | Hydrologic Calculations – Rational Method |
| APPENDIX C1 | Hydraulic Calculations – Open Channels |
| APPENDIX C2 | Hydraulic Calculations – Culverts |
| APPENDIX D | Water Quality Calculations – Rain Garden C2 |
| APPENDIX E | Drainage Cost Estimate |
| APPENDIX F | Figures |
| Figure A1 | Vicinity Map |
| Figure A2 | Floodplain Map |
| Figure EX1 | Major Basin / Historic Drainage Plan |
| Figure EX2 | Historic Drainage Plan |
| Figure D1 | Developed Drainage Plan |
| Figure D1.03 | Developed Drainage Plan |



**WALDEN PRESERVE 2 – FILING NO. 4
FINAL DRAINAGE REPORT - EXECUTIVE SUMMARY**

A. Background

- Walden Preserve is a residential subdivision of a 345-acre parcel located in northeastern El Paso County. Walden Preserve 2 Filing No. 4 consists of 23 residential lots in the northwesterly area of the Walden Preserve development.
- The proposed Filing No. 4 conforms to the previously approved Walden Preserve 2 PUD.
- Walden Preserve is located within the Cherry Creek Drainage Basin, which comprises a total drainage area in excess of 30 square miles. The Walden Preserve property represents less than 2 percent of the total basin area.

B. General Drainage Concept

- Developed drainage within the site will be conveyed through paved streets with roadside ditches and culverts, as well as grass-lined channels through open space areas.
- Developed flows from Walden Preserve will be detained to historic levels through on-site stormwater detention ponds.
- The existing tributary channel of West Cherry Creek running through the site will be preserved as a greenway and trail corridor. Main channel improvements have previously been completed with development of Walden Preserve Filing No. 1, including upgrade of two existing stock ponds.

C. Drainage Impacts

- The proposed detention ponds will release historic flows at the downstream property boundary, ensuring no significant adverse impact from developed drainage flows.
- Drainage facilities within public road rights-of-way and open space areas will be designed and constructed to El Paso County standards, and dedicated to the County for maintenance. The proposed stormwater detention ponds will be owned and maintained by the HOA or Metropolitan District.

DRAINAGE STATEMENTS

Engineer's Statement:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for liability caused by negligent acts, errors or omissions on my part in preparing this report.

John P. Schwab, P.E. #29891

Developer's Statement:

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

By:

Printed Name: _____ Date _____
Title: _____

Custom Castles Building Company, Inc.
1230 Scarsbrook Court
Monument, CO 80132

El Paso County's Statement:

Filed in accordance with the requirements of the El Paso County Land Development Code, Drainage Criteria Manual, Volumes 1 and 2, and Engineering Criteria Manual as amended.

Jennifer Irvine, P.E. _____ Date _____
County Engineer / ECM Administrator

Conditions:

I. GENERAL LOCATION AND DESCRIPTION

A. Background

Walden Preserve is a residential subdivision located in the Walden community of northeastern El Paso County, Colorado. The Walden Preserve 2 PUD area is located south and west of Woodhaven Drive, north of Pond View Place, and east of Walden Way, as shown in Figure A1 (Appendix F). The originally approved 2004 Walden Preserve PUD consisted of a combination of medium-density residential lots (0.5-acre average size) and low-density residential lots (2.5-acre minimum size) on a 345-acre property. The currently approved 2014 Walden Preserve 2 PUD includes phased development of 116 new residential lots (1-acre typical lot size), resulting in a total of 211 lots in the Walden Preserve development (including both previously platted lots and proposed lots). All of the proposed lots in the amended PUD area will be served by the existing central water and sewer system.

Walden Preserve 2 Filings No. 1-3 have been completed. These filings comprise 43 lots on the south side of the Walden Preserve 2 PUD area.

The proposed Walden Preserve 2 Filing No. 4 consists of 23 residential lots on 45.3 acres within the previously approved Walden Preserve 2 PUD (part of El Paso County Assessor's Parcel Number 61230-01-023), consisting of the existing meadow area located along the proposed extension of Pinehurst Circle on the east side of Walden Way.

B. Scope

This report is intended to fulfill the El Paso County requirements for a Final Drainage Report (FDR) in support of the final plat application for the proposed Walden Preserve 2 Filing No. 4. The report will provide a summary of site drainage issues impacting the proposed development, including analysis of impacts from upstream drainage areas, site-specific developed drainage patterns, and impacts on downstream facilities. This Final Drainage Report was prepared based on the guidelines and criteria presented in the El Paso County Drainage Criteria Manual.

C. Site Location and Description

The Walden Preserve parcel is located in parts of Sections 14, 15, 22, and 23, Township 11 South, Range 66 West of the 6th Principal Meridian. The site has historically been a vacant forest and meadow tract, with the exception of existing utility facilities (i.e. wastewater lagoon and well sites) serving the Walden Subdivision. The Walden Preserve property was re-zoned to PUD in 2005, with an approved development plan including a band of low-density lots along the south and west sides of the parcel, transitioning to medium-density lots adjacent to the existing platted areas of the Walden Subdivision, which is zoned RR1 for ½-acre lots.

Access to the areas on the west side of the Walden Preserve will be provided by extension of several existing local roads from Walden Way, including Needles Drive, and Pinehurst Circle. Associated site improvements will include paving of new public roadways through the site, as well as grading, drainage, and utility service improvements for the proposed residential lots. Interior roads will all be classified as rural local roads, with 60-foot rights-of-way and paved widths of 28-feet.

The Walden Preserve parcel is bordered by Walker Road to the north, developed areas of the Walden III Subdivision (Zoned RR1) to the east, the Settlers Ranch Subdivision to the south, and developed areas of the Walden Subdivision (Zoned RR5) to the west. Ground elevations within the parcel range from a low point of approximately 7,350 feet above mean sea level at the north boundary of the parcel, to a high point of 7,600 feet at the south boundary.

Surface drainage from this area flows northerly towards a tributary of West Cherry Creek on the west side of Woodhaven Drive. The terrain is rolling with south to north slopes ranging from 1% to 10%. Existing vegetation is typical eastern Colorado prairie grass in the meadow areas and evergreen pines in the forest areas towards the easterly property boundary.

D. General Soil Conditions

According to the Soil Survey of El Paso County prepared by the Soil Conservation Service, the majority of the parcel is classified as “Tomah” series loamy sand, and characterized as hydrologic soils group B. On-site soils are comprised primarily of the following soil types (see Appendix A):

- Type 92 - “Tomah-Crawfoot loamy sands”: slow surface runoff, slight to moderate erosion hazard (Hydrologic Group B)
- Type 71 – “Pring sandy loam”: medium surface runoff, moderate erosion hazard (Hydrologic Group B)
- Type 25 – “Elbeth sandy loam”: slow to medium surface runoff, moderate erosion hazard (Hydrologic group B)

E. References

City of Colorado Springs & El Paso County “Drainage Criteria Manual,” revised October 12, 1994.

City of Colorado Springs “Drainage Criteria Manual, Volumes 1 and 2,” revised May, 2014.

CDOT, “CDOT Drainage Design Manual,” July, 1995.

El Paso County “Engineering Criteria Manual,” January 9, 2006.

ERO Resources Corporation, “Wetland Delineation Report for Walden Village,” March 4, 2003.

Guenther Polok, “Drainage Report, Walden III, Filings 5, 6, and 7,” July, 1983.

JPS Engineering, Inc., “Final Drainage Report for Settlers Ranch Subdivision Filing No. 1,” October 18, 2005 (approved October 19, 2005).

JPS Engineering, Inc., “Final Drainage Report for Settlers Ranch Subdivision Filing No. 2,” May 30, 2008 (approved March 31, 2009).

JPS Engineering, Inc., “Final Drainage Report for Walden Preserve Subdivision Filing No. 1,” May 11, 2005.

JPS Engineering, Inc., “Master Development Drainage Plan (MDDP) and Final Drainage Report for Monument Academy,” April 30, 2019.

JPS Engineering, Inc., “Master Development Drainage Plan (MDDP) and Preliminary Drainage Report for Walden Preserve Subdivision,” December 10, 2004.

JPS Engineering, Inc., “Master Development Drainage Plan (MDDP) and Preliminary Drainage Report for Walden Preserve 2 PUD,” September 17, 2014 (approved November 6, 2014).

JPS Engineering, Inc., “Preliminary Drainage Report for Walden Pines Subdivision,” December 29, 2003.

JPS Engineering, Inc., “Final Drainage Report for Walden Pines Subdivision,” March 24, 2004.

Kiowa Engineering Corporation, “Final Drainage Plan and Erosion Control Plan, Walden III Filing 6 Phase 1, Filing 6 Phase 2 and Filing 7,” February 19, 2002.

M.V.E., Inc., “Settlers Ranch Preliminary Drainage Report,” December 13, 2004.

USDA/NRCS, “Soil Survey of El Paso County Area, Colorado,” June, 1981.

II. DRAINAGE BASINS AND SUB-BASINS

A. Major Basin Description

The proposed development lies within the West Cherry Creek Drainage Basin (CYCY 0400) as classified by El Paso County. Drainage from this site flows northerly to an eastern tributary of West Cherry Creek, which flows to a confluence with the main channel north of Walker Road. Downstream agricultural areas generally drain northerly towards the main channel of West Cherry Creek.

The major drainage basins lying in and around the proposed development are depicted in Figure EX1. The Walden Preserve parcel is located near the southerly limits of the West Cherry Creek Basin, which comprises a total drainage area in excess of 30 square miles.

As such, the proposed 349-acre Walden Preserve subdivision represents less than 2 percent of the total basin area, which is primarily agricultural land.

B. Floodplain Impacts

The proposed development area is located beyond the limits of any 100-year floodplain delineated by the Federal Emergency Management Agency (FEMA). The floodplain limits in the vicinity of the site are shown in Flood Insurance Rate Map (FIRM) Numbers 08041C0285-F and 08041C0325-F, dated March 17, 1997, as shown in Figure A2 (Appendix F). As shown on Figure A2, the FEMA floodplain limit extends slightly south of Walker Road in the vicinity of the existing culvert crossing.

No impacts to the existing drainage channel are proposed as part of this subdivision filing.

C. Sub-Basin Description

The existing drainage basins lying in and around the proposed development are depicted in Figure EX1 (Appendix F). The site is impacted by off-site drainage basins of approximately 515 acres to the south and east, which flow to the existing natural drainage channel that bisects the property. The existing on-site topography has been delineated as five drainage basins. Basins A, B, and C drain into the main tributary channel flowing northerly to the existing culvert crossing Walker Road.

The developed drainage basins lying within the proposed development are depicted in Figures D1 and D1.03 (Appendix F). The interior site layout has been divided into drainage basins based on the road layout and topography within the site. The natural drainage patterns will be impacted through development by site grading and concentration of runoff in subdivision roadside ditches and channels. The majority of sub-basins drain to the north, collecting in the interior roads and drainage channels. On-site flows will be diverted to natural swales draining towards the main tributary channel running through the property, following historic drainage paths.

III. DRAINAGE DESIGN CRITERIA

A. Development Criteria Reference

No Drainage Basin Planning Study (DBPS) has been completed for the West Cherry Creek Drainage Basin. JPS Engineering, Inc. prepared the “Master Development Drainage Plan (MDDP) and Preliminary Drainage Report for Walden Preserve 2 PUD” dated September 17, 2014, which was approved by El Paso County on November 6, 2014 in support of the Walden Preserve 2 PUD and Preliminary Plan. The proposed drainage plan for Walden Preserve 2 Filing No. 4 is in full conformance with the previously approved MDDP.

B. Hydrologic Criteria

SCS procedures were utilized for analysis of the major off-site basin flows impacting the site. In accordance with El Paso County drainage criteria, SCS hydrologic calculations were based on the following assumptions:

- Design storm (minor) 5-year
- Design storm (major) 100-year
- Storm distribution SCS Type II
- 100-year, 24-hour rainfall 4.4 inches (NOAA isopluvial map)
- 5-year, 24-hour rainfall 2.6 inches (NOAA isopluvial map)
- Hydrologic soil type B

- SCS curve number - undeveloped conditions 61 (pasture / range)
- SCS curve number – 1-ac to 2.5-ac lots 68
- SCS curve number – 0.5-acre lots 70

Rational Method procedures were utilized for calculation of peak flows within the on-site drainage basins. Rational Method hydrologic calculations were based on the following assumptions:

- Design storm (minor) 5-year
- Design storm (major) 100-year
- Rainfall Intensities El Paso County I-D-F Curve
- Hydrologic soil type B

- Runoff Coefficients - undeveloped:

| | <u>C5</u> | <u>C100</u> |
|------------------------------|-----------|-------------|
| Existing pasture/range areas | 0.25 | 0.35 |
| Existing forest areas | 0.1 | 0.15 |
- Runoff Coefficients - developed:

| | | |
|--------------------------------------|------|------|
| Proposed lot areas (1-2.5-acre lots) | 0.30 | 0.40 |
| Proposed lot areas (1/2-acre lots) | 0.35 | 0.45 |

To provide for conservative drainage design, the developed flow hydrologic calculations were performed using conservative assumptions for runoff curve numbers and coefficients associated with the 1-acre lots proposed throughout the Walden Preserve 2 PUD. For example, the SCS curve number of 68 for 1-acre lots has been applied without reduction to the majority of developed areas throughout the Walden Preserve 2 PUD, while in fact there are significant open space areas in the subdivision layout. As noted in Table 5-5 of Appendix B, the SCS curve number of 68 is recommended for densities of 1 acre per dwelling unit. The Walden Preserve 2 PUD has an actual gross density of approximately 1.8 acres per dwelling unit, providing for a significant factor of safety in the subdivision drainage design.

Hydrologic calculations are detailed in Appendix B, and peak design flows are identified on the drainage plan drawings in Appendix F.

IV. DRAINAGE PLANNING FOUR STEP PROCESS

El Paso County Drainage Criteria require drainage planning to include a Four Step Process for receiving water protection that focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainageways, and implementing long-term source controls. The Four Step Process is applicable to all new and re-development projects with construction activities that disturb 1 acre or greater or that disturb less than 1 acre but are part of a larger common plan of development. The Four Step Process has been implemented as follows in the planning of this project:

Step 1: Employ Runoff Reduction Practices

- **Minimize Directly Connected Impervious Areas (MDCIA):** The rural residential development will have roadside ditches along all roads, providing for impervious areas to drain across pervious areas. Based on the roadside ditches throughout the subdivision, the subdivision is classified as MDCIA Level One.
- **Grass Swales:** The proposed roadside ditches will drain to existing and proposed grass-lined drainage swales following historic drainage patterns through the property.

Step 2: Stabilize Drainageways

- Proper erosion control measures will be implemented along the roadside ditches and grass-lined drainage channels to provide stabilized drainageways within the site.

Step 3: Provide Water Quality Capture Volume (WQCV)

- **Detention Ponds and Rain Gardens:** The developed site will drain through stormwater detention ponds and rain gardens which will capture and slowly release the WQCV over an extended release period.

Step 4: Consider Need for Industrial and Commercial BMPs

- No industrial or commercial land uses are proposed within this rural residential subdivision.
- On-site drainage will be routed through private detention ponds and rain gardens to minimize introduction of contaminants to the County's public drainage system.

V. GENERAL DRAINAGE RECOMMENDATIONS

The developed drainage plan for the site is to provide and maintain positive drainage away from structures and conform to the established drainage patterns for the overall site. JPS Engineering recommends that positive drainage be established and maintained away from all structures within the site in conformance with applicable building codes and geotechnical engineering recommendations.

Site grading and drainage improvements performed as a part of subdivision infrastructure development includes overlot grading and subdivision drainage improvements depicted on the subdivision construction drawings. Individual lot grading is the sole responsibility of the

individual builders and property owners. Final grading of each home site should establish proper protective slopes and positive drainage in accordance with HUD guidelines and building codes. In general, main floor elevations for each home should be established approximately 2 feet above the top of curb of the adjoining street.

In general, we recommend a minimum of 6 inches clearance from the top of concrete foundation walls to adjacent finished site grades. Positive drainage slopes should be maintained away from all structures, with a minimum recommended slope of 5 percent for the first 10 feet away from buildings in landscaped areas, a minimum recommended slope of 2 percent for the first 10 feet away from buildings in paved areas, and a minimum slope of 1 percent for paved areas beyond buildings.

VI. DRAINAGE FACILITY DESIGN

A. General Concept

Development of the Walden Preserve Subdivision will require site grading and paving, resulting in additional impervious areas throughout the site. The general drainage pattern will consist of grading away from home sites to swales and roadside ditches along the internal roads within the subdivision, conveying runoff flows through the site. Runoff from the site will flow by roadside ditches to cross culverts at low points in the road profiles, and grass-lined channels connecting to existing natural swales at the site boundaries.

The stormwater management concept for the Walden Preserve development will be to provide roadside ditches and grass-lined swales as required to convey developed drainage through the site to existing natural outfalls. Individual lot grading will provide positive drainage away from building sites, and direct developed flows into the system of roadside ditches and drainage swales running through the subdivision.

One of the existing stock ponds along the main channel within the site (“Pond B”) has previously been upgraded to serve as a stormwater retention pond to mitigate the impact of developed flows and ensure that historic flows are maintained downstream of the proposed subdivision. Development of the balance of the western part of the Walden Preserve property will ultimately include construction of one additional detention pond (“Pond C8”), along with other low impact development approaches to further mitigate developed flow impacts.

B. Specific Details

1. Existing Drainage Conditions

Historic drainage conditions within the site are depicted in Figure EX2. The existing tributary channel of West Cherry Creek runs northerly through the site, collecting drainage from numerous natural swales on each side of the main channel.

Off-site flows from Basin OA1 combine with Basin A at the south end of the site, flowing into an existing stock pond (“Pond A”) at Design Point #1, with historic peak flows of $Q_5 = 33.1$ cfs and $Q_{100} = 213.4$ cfs (SCS Method).

Off-site flows from Basin OB1 combine with flows from Basin B near the center of the existing parcel, adding to the flow in the main tributary channel at the second existing stock pond (“Pond B”) located at Design Point #2. Historic peak flows at this location are estimated to be $Q_5 = 65.8$ cfs and $Q_{100} = 287.9$ cfs (SCS Method).

Off-site flows from Basins OC1 and OD1 combine with flows from Basins C and D, joining with flows in the main tributary channel at the existing culvert crossing Walker Road at the northerly property boundary of the Walden Wastewater Treatment Plant property. Historic peak flows at Design Point #4 are calculated as $Q_5 = 222.5$ cfs and $Q_{100} = 582.9$ cfs (SCS Method).

2. Developed Drainage Conditions

Master Development Drainage Plan

The developed drainage basins and projected flows are shown in Figures D1 and D1.03 (Appendix F). As discussed in the approved MDDP, developed Sub-basins A1-A6 are located in the south and southeasterly areas previously developed as Walden Preserve Filings No. 1 and No. 2. Walden Preserve 2 Filings No. 1-3 included development of the areas within Sub-Basins A7-A9 on the north side of Pond View Place between the main drainage channel and Walden Way.

Sub-basins A1-A9 will continue to flow northerly towards the main tributary channel, combining at the existing southerly stock pond (Pond A) with developed peak flows calculated as $Q_5 = 92.1$ cfs and $Q_{100} = 261.3$ cfs (SCS Method) at Design Point #1 (per approved MDDP). While the existing Stock Pond A is not planned for use as a drainage detention pond, the pond will be maintained as an aesthetic feature within the subdivision. The pond was previously upgraded with an engineered overflow spillway during development of Walden Preserve Filing No. 1.

Walden Preserve Filing No. 1 included development of the areas within Sub-basins B1-B4 on the east side of the main drainage channel. Sub-basins B5-B10 include the remaining areas developed as 1-acre lots along the west side of the drainage channel.

Developed Sub-basins B1-B10 will continue to flow northerly towards the main tributary channel, combining at the existing northerly stock pond (Pond B) with developed peak flows of $Q_5 = 208.0$ cfs and $Q_{100} = 551.4$ cfs (SCS Method) at Design Point #2 (per approved MDDP). The existing stock pond (Pond B) has been upgraded to serve as a sub-regional stormwater detention and water quality pond for the remaining phases of the

Walden Preserve Subdivision. Pond B was upgraded with a water quality orifice plate during previous development of Walden Preserve 2 Filings No. 1 and 2. The pond has been designed to “over-detain” to allow for discharges of developed flows from downstream sub-basins, while ensuring that discharges downstream of Walker Road remain below historic levels. An energy dissipation structure has been constructed at the discharge point from Pond B to reduce erosion concerns in the downstream channel.

Sub-basins C1-C4 include areas north of Pond B which will be developed as 1-acre lots. Runoff from these basins will flow northeasterly to the main drainage channel. Proposed Water Quality Ponds C2 and C4 will be constructed on the downstream side of the new extension of Pinehurst Circle through the Walden Preserve 2 PUD area. While Ponds C2 and C4 are not needed for stormwater detention in the overall drainage analysis, these small water quality ponds will encourage infiltration of developed drainage and provide water quality mitigation of developed drainage impacts, consistent with an overall low-impact development approach.

Sub-basins C5-C8 include additional areas to be developed as 1-acre lots. These basins will flow northeasterly to the future Detention Pond C8, which will mitigate developed flow impacts prior to discharging through Basin C9 into the main channel upstream of the proposed emergency access and trail crossing at Highview Drive. Total undetained developed peak flows at Design Point #3 are calculated as $Q_5 = 280.7$ cfs and $Q_{100} = 734.2$ cfs (SCS Method; per approved MDDP).

Sub-basins C10-C12 include additional 1-acre lot areas to be developed in the northwest part of Walden Preserve, and Sub-basin C13 covers the existing Walden Wastewater Treatment Facility at the northwest corner of the Walden property. Water Quality Pond C12 will be constructed in the northeast corner of the future residential development area to mitigate developed flow impacts from Sub-Basins C10-C12. Developed flows from Sub-basins C10-C13 will flow northeasterly, combining with flows in the main tributary channel, and ultimately reaching the existing culvert crossing Walker Road.

Flows from Basins OC1-OC2 on the east side of the channel, along with flows from Basins OD1 and D in vicinity of the Walden Pines Subdivision drain northwesterly across Woodhaven Drive, contributing to the total flow in the main channel. Flows from Basins OA1-OD1 and A1-D1 combine at Design Point #4, with total undetained developed flows calculated as $Q_5 = 298.7$ cfs and $Q_{100} = 785.0$ cfs (SCS Method; per approved MDDP).

As detailed in the previously approved MDDP, SCS hydrologic models were developed using the HEC-HMS software package to evaluate the comparison of historic and developed flow conditions, and confirm sizing of the proposed stormwater detention ponds. The detained flow analysis shows that the combination of Pond B and Pond C8 results in detained flows at Design Point #4 calculated as $Q_5 = 213.5$ cfs and $Q_{100} = 577.1$ cfs, which achieves the goal of remaining below historic flows at the downstream boundary of the subdivision.

WP2 Filing No. 4 Drainage Plan

Walden Preserve 2 Filing No. 4 is located in parts of Basins B8-B10 and C1-C2 as depicted in the enclosed drainage plans (Sh. D1 and D1.03, Appendix F). Developed Sub-basins B5-B8 comprise the areas along the southeast side of the extension of Pinehurst Circle through Filing No. 4. These basins combine at Design Point #B8, with developed peak flows calculated as $Q_5 = 35.9$ cfs and $Q_{100} = 85.1$ cfs (Rational Method). Drainage from these basins will continue to flow northeasterly through grass-lined drainage Channel B8 to Pond B at the east boundary of Filing No. 4.

Developed Sub-basin B9 comprises the area along the northwest side of the extension of Pinehurst Circle through Filing No. 4, flowing northeasterly along the roadside ditch to Culvert B9 (24" RCP) at the low point in the road profile. Developed peak flows at Design Point #B9 are calculated as $Q_5 = 10.0$ cfs and $Q_{100} = 23.7$ cfs (Rational Method). Culvert B9 will convey the flow from this basin easterly through grass-lined drainage Channel B9 to Pond B within Tract A at the east boundary of Filing No. 4.

Developed Sub-basin B10 comprises the area on the easterly downstream side of the extension of Pinehurst Circle through Filing No. 4, sheet flowing northeasterly to Pond B. Developed flows from Sub-basins B5-B10 combine at Design Point #B10, with peak flows calculated as $Q_5 = 53.5$ cfs and $Q_{100} = 126.9$ cfs (Rational Method).

Developed Sub-basin C1 comprises the area along the west side of the extension of Pinehurst Circle at the north end of Filing No. 4. Sub-basin C1 will generally flow southeasterly along the roadside ditch to Culvert C1 at the low point in the road profile. Developed peak flows at Design Point #C1 are calculated as $Q_5 = 11.2$ cfs and $Q_{100} = 26.7$ cfs (Rational Method). Culvert C1 (24" RCP) will convey the flow from this basin easterly across Pinehurst Circle, draining into Water Quality Pond C2.

Developed Sub-basin C2 comprises the area on the easterly downstream side of the extension of Pinehurst Circle at the north end of Filing No. 4, sheet flowing easterly to Water Quality Pond C2. Developed flows from Sub-basins C1-C2 combine at Design Point #C2, with peak flows calculated as $Q_5 = 19.7$ cfs and $Q_{100} = 46.8$ cfs (Rational Method). Water Quality Pond C2 will be constructed on the east side of Basin C2 to provide water quality enhancement for combined Basins C1 and C2.

C. Comparison of Developed to Historic Discharges

Based on the hydrologic calculations in Appendix B, the proposed development will result in developed flows exceeding historic flows from the parcel. The increase in developed flows will be mitigated through on-site stormwater detention facilities.

The comparison of developed to historic discharges at key design points is summarized as follows (per approved MDDP):

| Design Point | Historic Flow | | | Developed Flow | | | Comparison of Developed to Historic Flow (Q ₅ %/Q ₁₀₀ %) |
|---------------------|---------------|----------------------|------------------------|----------------|----------------------|------------------------|--|
| | Area (ac) | Q ₅ (cfs) | Q ₁₀₀ (cfs) | Area (ac) | Q ₅ (cfs) | Q ₁₀₀ (cfs) | |
| 1 | 337.1 | 33.1 | 213.4 | 342.0 | 92.1 | 261.3 | 278% / 122% (increase) |
| 2 (Developed) | 490.5 | 65.8 | 287.9 | 504.7 | 208.0 | 551.4 | 316% / 192% (increase) |
| 2 (Detained) | 490.5 | 65.8 | 287.9 | 504.7 | 82.3 | 311.1 | 125% / 108% (increase) |
| 3 (Developed) | | | | 737.8 | 280.7 | 734.2 | |
| 3 (Detained) | | | | 737.8 | 175.2 | 459.8 | 62% / 63% (decrease) |
| 4 (Developed) | 902.7 | 222.5 | 582.9 | 902.7 | 298.7 | 785.0 | 134% / 135% (increase) |
| 4 (Detained) | 902.7 | 222.5 | 582.9 | 902.7 | 213.5 | 577.1 | 96% / 99% (decrease) |

D. Detention Ponds

The total developed storm runoff downstream of the proposed subdivision will be maintained at historic levels by routing flows through an existing detention pond (Pond B) located along the main tributary channel running through the property, along with ultimate construction of four additional ponds (Rain Garden C2 and Detention Ponds C4, C8, and C12) serving the northern parts of the Walden 2 PUD area. Rain Garden C2 has been designed as a stormwater quality facility in accordance with County and UDFCD criteria, and future Ponds C4 and C12 will also serve as water quality ponds. In accordance with the approved MDDP, future Pond C8 will be designed as a “full-spectrum” detention pond.

Pond B is an existing Retention Pond with a stormwater detention volume of 17.4 acre-feet above the minimum “active” storage volume in the pond. As detailed in the approved MDDP, Detention Ponds B and C8 will provide sufficient stormwater detention to result in a net release at or below historic flows at Design Point #4 downstream (crossing Walker Road), discharging to the existing natural swale downstream.

Development of Walden Preserve 2 Filing No. 4 will include construction of Water Quality Rain Garden C2. Final pond design calculations utilizing the Denver Urban Drainage and Flood Control District (UDFCD) “UD-BMP_v3.06” software package are enclosed in Appendix D. Design parameters for WQ Rain Garden C2 are summarized as follows:

| Pond | Tributary Area (ac) | Percent Impervious (%) | Tributary Impervious Area (ac) | Required WQCV (ac-ft) | Design Volume (ac-ft) |
|------|---------------------|------------------------|--------------------------------|-----------------------|-----------------------|
| C2 | 22.9 | 16.2% | 3.7 | 0.15 | 0.19 |

The existing and proposed detention ponds will be owned and maintained by the Walden Property Owners Association.

E. On-Site Drainage Facility Design

Developed sub-basins and proposed drainage improvements are depicted in the enclosed Drainage Plans (Sheets D1 and D1.03). In accordance with El Paso County standards, new roadways will be graded with a minimum longitudinal slope of 1.0 percent. The typical local road section will consist of a 28-foot paved width with 2-foot gravel shoulders and 4:1 slopes to 2.5-foot deep ditches. On-site drainage facilities will consist of roadside ditches, grass-lined channels, and culverts. Hydraulic calculations for preliminary sizing of major on-site drainage facilities are enclosed in Appendix C, and design criteria are summarized as follows:

1. Culverts

The internal road system will be graded to drain roadside ditches to low points along the road profile, where cross-culverts will convey developed flows into grass-lined channels following historic drainage paths. Culvert pipes have been specified as reinforced concrete pipe (RCP) with a minimum diameter of 18-inches. Final culvert design calculations were performed utilizing the FHWA HY-8 software package to perform a detailed analysis of inlet and outlet control conditions, meeting El Paso County criteria for allowable headwater depths and overtopping. Riprap outlet protection will be provided at all culverts.

2. Open Channels

Drainage easements will be dedicated along major drainage channels following historic drainage paths through the subdivision. These channels have generally been designed as grass-lined channels designed to convey 100-year flows, with a trapezoidal cross-section, variable bottom width and depth, 4:1 maximum side slopes, 1-foot freeboard, and a minimum slope of 0.5 percent.

The proposed drainage channels have been sized utilizing Manning's equation for open channel flow, assuming a friction factor ("n") of 0.030 for dry-land grass channels. Maximum allowable velocities will be evaluated based on El Paso County drainage criteria, typically allowing for a maximum 100-year velocity of 4-5 feet per second. Erosion control mats have been specified for channel segments with maximum 100-year velocities up to 8 feet per second. The proposed channels will generally be seeded with native grasses for erosion control. Erosion control mats, ditch checks, and/or riprap channel lining will be provided where required based on erosive velocities. Ditch flows will be diverted to drainage channels at the nearest practical location to minimize excessive roadside ditch sizes.

The proposed development plan for Walden Preserve provides a substantial open space buffer along the existing Tributary Channel of West Cherry Creek running through the site,

with the intention of protecting this existing greenway and providing an active trail connection along the drainage corridor. The existing main channel upstream of Pond B is a grass-lined channel in stable condition, and the major channel will generally be protected from development. The existing stock ponds have previously been upgraded with engineered outlet structures and spillways.

Primary drainage swales crossing proposed lots have been placed in drainage easements, with variable widths based on the required channel sections.

F. Analysis of Existing and Proposed Downstream Facilities

The general concept of the proposed drainage plan is to mitigate developed flow impacts and attenuate peak flows in the main channel by routing developed flows through on-site detention ponds. Detention Pond B has been designed to “over-detain” to account for release of developed flows from some downstream parts of the Walden Preserve Subdivision.

Downstream of Detention Pond B, the existing channel runs through the back yards of a block of existing developed lots. Detention Pond B has been designed to reduce peak flows below historic levels, so there is no anticipated increase in peak flows to be discharged to the existing channel running through these downstream properties. The channel downstream of Pond B is an existing deficient condition from a drainage design standpoint. No structural improvements (i.e. riprap lining, drop structures) were constructed to stabilize this segment of channel when the original subdivision was developed, and as a result this segment of channel does not meet County standards for public drainage facilities. The pond runs through a row of private backyards, and a number of existing private structures are located along the drainage channel. The channel shows signs of erosion in several areas, and limited maintenance access is available along this private reach of channel.

The proposed drainage plan recognizes the existing deficiencies in the channel downstream of Pond B, and for this reason a primary focus of the proposed drainage plan is to reduce flows to a level below historic flows at Detention Pond B prior to reaching this existing deficient reach of channel. An engineered energy dissipation structure has been constructed at the pond discharge point to further mitigate the impact of flows from the Walden Preserve Subdivision.

The existing 43”x27” elliptical CMP culvert at Walker Road has an estimated capacity of 55 cfs. The existing culvert is undersized based on the calculated historic flows from the basin. While the existing roadway would be expected to overtop during major storm events, we are not aware of any reported drainage problems at this crossing and we are not aware of any County plans for replacement of the existing culvert. The existing stock ponds upstream in the main channel provide a significant level of stormwater detention/retention in their current condition, which likely has minimized historic concerns with flows overtopping the roadway at this crossing.

Combined flows in the East Tributary of West Cherry Creek continue flowing northerly through a grass-lined channel following a 100-foot wide drainage easement through the Shamrock Hills

Subdivision north of Walker Road, ultimately reaching a confluence with West Cherry Creek. The existing channel downstream of the culvert crossing Walker Road consists of a broad grass-lined swale with no signs of active erosion. On-site detention ponds mitigate the developed drainage impacts from the Walden Preserve Subdivision, so there is no need for this development to upgrade existing downstream facilities.

G. Anticipated Drainage Problems and Solutions

Stormwater detention ponds have been designed to mitigate the impacts of developed drainage from the overall Walden Preserve 2 PUD project. The previously completed construction and upgrades to Pond B are sufficient to provide stormwater detention for WP2 Filings No. 1-4. Water Quality Rain Garden C2 will provide stormwater quality mitigation for Filing No. 4.

The overall drainage plan for the subdivision includes a system of roadside ditches, channels, and culverts to convey developed flows through the site. The primary drainage problems anticipated within this development will consist of maintenance of these drainage channels, culverts, and detention pond facilities. Care will need to be taken to implement proper erosion control measures in the proposed roadside ditches, channels, and swales.

Ditches have been designed to meet allowable velocity criteria. Erosion control mats will be installed where necessary to minimize erosion concerns. Proper construction and maintenance of the proposed detention facility will minimize downstream drainage impacts.

VII. EROSION / SEDIMENT CONTROL

The Contractor will be required to implement Best Management Practices (BMP's) for erosion control through the course of construction. Sediment control measures will include installation of silt fence at the toe of disturbed slopes and hay bales protecting drainage ditches. Cut slopes will be stabilized during excavation as necessary and vegetation will be established for stabilization of disturbed areas as soon as possible. All ditches will be designed to meet El Paso County criteria for slope and velocity.

VIII. COST ESTIMATE AND DRAINAGE FEES

A cost estimate for proposed drainage improvements is enclosed in Appendix E.

The developer will finance all construction costs for proposed roadway and drainage improvements, and public facilities will be owned and maintained by El Paso County upon final acceptance. The existing and proposed detention ponds will ultimately be owned and maintained by the Walden Metropolitan District.

This parcel is located in the West Cherry Creek drainage basin. No drainage and bridge fees will be due at time of recordation of the final plat as the subject site is not located in a fee basin.


IX. SUMMARY

Walden Preserve 2 Filing No. 4 consists of 23 proposed lots along the new extension of Pinehurst Circle east of Walden Way. Developed drainage impacts from the Walden Preserve 2 PUD will be mitigated through existing and proposed on-site stormwater detention and water quality facilities. The proposed drainage patterns will remain consistent with historic conditions, and new drainage facilities constructed to El Paso County standards will safely convey runoff to suitable outfalls. Based on the on-site stormwater detention facilities, no downstream drainage improvements are proposed.

The existing and proposed detention ponds have been designed to maintain historic peak flows downstream of the Walden Preserve Subdivision. Proper construction and maintenance of the proposed drainage and erosion control facilities will ensure that this subdivision has no significant adverse drainage impact on downstream or surrounding areas.

APPENDIX A
SOILS INFORMATION


j:\psprojects\040201.walden\walden PRESERVE 2\DWG\CIVIL\SCS-1.dwg Sep 17, 2014 - 9:42am



SCALE: 1"=1000'

(EL PASO COUNTY SCS MAP SHEET NO. 1 & 2)

SCS SOILS MAP



WALDEN PRESERVE

FIGURE SCS-1

JPS PROJ NO. 040201

The presence of princesplume, two-groove milkvetch, and Fremont goldenweed indicates that selenium-bearing plants are in the stand.

Good grazing management is essential to maintain desirable grasses on the Kutch soil. Deferment of grazing early in spring helps to maintain the health and vigor of early season grasses. Proper location of livestock watering facilities helps to control grazing.

If the range has deteriorated, blue grama, junegrass, and native bluegrasses increase. Sleepygrass and annuals replace these grasses if the range has seriously deteriorated. Proper range management and proper location of livestock watering facilities are essential to maintain the potential vegetation on these soils. Seeding is advisable if the range is in poor condition. Seeding of the native vegetation is desirable, but the range can also be seeded with tame species of grasses such as Nordan crested wheatgrass, Russian wildrye, pubescent wheatgrass, or intermediate wheatgrass.

This complex is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitations of these soils for homesites are depth to sandstone and shale, permeability, and the shrink-swell potential of the subsoil. Dwellings and roads should be designed to offset these limitations. Septic tank absorption fields do not function properly because of the depth to shale and permeability. Capability subclass VIIe.

25—Elbeth sandy loam, 3 to 8 percent slopes. This deep, well drained soil formed in material transported from arkose deposits on uplands. Elevation ranges from 7,000 to 7,600 feet. The average annual precipitation is about 18 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

Typically the surface layer is very dark grayish brown sandy loam about 3 inches thick. The subsurface layer is light gray loamy sand about 20 inches thick. The subsoil is brown sandy clay loam about 45 inches thick. The substratum is light brown sandy clay loam.

Included with this soil in mapping are small areas of Tomah-Crowfoot loamy sands, 3 to 8 percent slopes; Kettle gravelly loamy sand, 3 to 8 percent slopes; and Peyton-Pring complex, 3 to 8 percent slopes.

Permeability of this Elbeth soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is high. Surface runoff is slow to medium, and the hazard of erosion is moderate.

This soil is used for woodland, limited livestock grazing, recreation, wildlife habitat, and homesites.

This soil is suited to the production of ponderosa pine. It is capable of producing about 2,240 cubic feet, or 4,900 board feet (International rule), of merchantable timber per acre from a fully stocked, even-aged stand of 80-year-

old trees. Conventional methods can be used for harvesting, but operations may be restricted during wet periods. Reforestation, after harvesting, must be carefully managed to reduce competition of undesirable understory plants.

Woodland wildlife, such as mule deer and wild turkey, is attracted to this soil because of its potential to produce ponderosa pine, Gambel oak, and various grasses and shrubs. Water developments, such as guzzlers, would enhance populations of wild turkey as well as other kinds of wildlife. Where wildlife and livestock share the same range, proper grazing management is needed to prevent overuse and to reduce competition. Livestock watering facilities would also benefit wildlife on this soil.

This soil has good potential for homesites. The main limitation is the moderate shrink-swell potential in the subsoil. Special road design is necessary on this soil to overcome the limitations of shrink-swell potential and frost action. Special planning is needed on this soil to minimize site disturbance and tree and seedling damage. During seasons of low precipitation, fire may become a hazard to homesites on this soil. The hazard can be minimized by installing firebreaks and reducing the amount of potential fuel on the forest floor. Capability subclass VIe.

26—Elbeth sandy loam, 8 to 15 percent slopes. This deep, well drained soil formed in material transported from arkose deposits on uplands. Elevation ranges from 7,300 to 7,600 feet. The average annual precipitation is about 18 inches, the average annual air temperature is about 43 degrees F, and the average frost-free season is about 120 days.

Typically, the surface layer is very dark grayish brown sandy loam about 3 inches thick. The subsurface layer is light gray loamy sand about 20 inches thick. The subsoil is brown sandy clay loam about 45 inches thick. The substratum is light brown.

Included with this soil in mapping are small areas of Tomah-Crowfoot loamy sand, 8 to 15 percent slopes; Peyton-Pring complex, 8 to 15 percent slopes; Kettle gravelly loamy sand, 8 to 40 percent slopes; and Kettle-Rock outcrop complex.

Permeability of this Elbeth soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is high. Surface runoff is slow to medium, and the hazard of erosion is moderate.

This soil is used for woodland, limited livestock grazing, recreation, wildlife habitat, and homesites.

This soil is suited to the production of ponderosa pine. It is capable of producing about 2,240 cubic feet, or 4,900 board feet (International rule), of merchantable timber per acre from a fully stocked, even-aged stand of 80-year-old trees. Conventional methods can be used for harvesting, but operations may be restricted during wet periods. Reforestation, after harvesting, must be carefully managed to reduce competition of undesirable understory plants.

Survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

These soils have a good potential for homesites. The main limitations, especially on the Peyton soil, are low bearing strength and frost-action potential. Buildings and roads can be designed to overcome these limitations. Access roads should have adequate cut-slope grade and be provided with drains to control surface runoff and keep soil losses to a minimum. Capability subclass VIe.

69—Peyton-Pring complex, 8 to 15 percent slopes. These gently to moderately sloping soils are on valley side slopes and on uplands. Elevation ranges from 6,800 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

The Peyton soil makes up about 40 percent of the complex, the Pring soil about 30 percent, and other soils about 30 percent.

Included with these soils in mapping are areas of Holderness loam, 8 to 15 percent slopes; Tomah-Crowfoot loamy sands, 8 to 15 percent slopes; Kettle gravelly loamy sand, 8 to 40 percent slopes; and a few areas of Rock outcrop.

The Peyton soil is commonly on the less sloping part of the landscape. It is deep, noncalcareous, and well drained. It formed in alluvium and residuum derived from weathered, arkosic, sedimentary rock. Typically, the surface layer is grayish brown sandy loam about 12 inches thick. The subsoil, about 23 inches thick, is pale brown sandy clay loam in the upper 13 inches and pale brown sandy loam in the lower 10 inches. The substratum is pale brown sandy loam to a depth of 60 inches or more.

Permeability of the Peyton soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is high. Surface runoff is medium to rapid, and the hazard of erosion is moderate to high. Some gullies have developed along drainageways and livestock trails.

The Pring soil is deep, noncalcareous, and well drained. It formed in sandy sediment derived from weathered, arkosic, sedimentary rock. Typically, the surface layer is dark grayish brown coarse sandy loam about 4 inches thick. The substratum is dark grayish brown coarse sandy loam about 10 inches thick over pale brown gravelly sandy loam that extends to a depth of 60 inches or more.

Permeability of the Pring soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium to rapid, and the hazard of erosion is moderate to high. Some gullies have developed along drainageways and livestock trails.

The soils in this complex are used as rangeland, for wildlife habitat, and for homesites.

These soils are well suited to the production of native vegetation suitable for grazing. The dominant native species are mountain muhly, bluestem grasses, needle-andthread, and blue grama. These soils are subject to invasion of Kentucky bluegrass and Gambel oak. Common forbs are hairy goldenrod, geranium, milkvetch, low larkspur, fringed sage, and buckwheat.

Properly locating livestock watering facilities helps to control grazing. Timely deferment of grazing is needed to protect the plant cover.

Windbreaks and environmental plantings generally are suited to these soils. Soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are well suited to wildlife habitat. They are best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

These soils have good potential for use as homesites. The main limitations are steepness of slope, limited ability to support a load, and frost-action potential. Buildings and roads can be designed to overcome these limitations. These soils also require special site or building designs because of the slope. Access roads should have adequate cut-slope grade and drains should be provided to control surface runoff and keep soil losses to a minimum. Capability subclass VIe.

70—Pits, gravel. Gravel pits are in nearly level to rolling areas. They are open excavations several feet deep and commonly 5 acres or less in size.

Gravel pits are very low in natural fertility and are highly susceptible to soil blowing. A cover of weeds or straw helps to control erosion.

Windbreaks and environmental plantings generally are not suited to these areas. Onsite investigation is needed to determine if plantings are feasible. Capability subclass VIIIc.

71—Pring coarse sandy loam, 3 to 8 percent slopes. This deep, noncalcareous, well drained soil formed in sandy sediment derived from arkosic sedimentary rock on valley side slopes and on uplands. Elevation ranges from 6,800 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

Typically, the surface layer is dark grayish brown coarse sandy loam about 4 inches thick. The substratum is dark grayish brown coarse sandy loam about 10 inches thick over pale brown gravelly sandy loam that extends to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Alamosa loam, 1 to 3 percent slopes, along drainageways; Cruckton sandy loam, 1 to 9 percent slopes; Peyton sandy loam, 1 to 5 percent slopes; Peyton sandy loam, 5 to 9 percent slopes; and Tomah-Crowfoot loamy sands, 3 to 8 percent slopes. In some places arkose beds of sandstone and shale are at a depth of 0 to 40 inches.

Permeability of this Pring soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium, and the hazard of erosion is moderate.

Almost all areas of this soil are used as rangeland. Some areas previously cultivated have been reseeded to grass. This soil is also used for wildlife habitat and homesites.

This soil is well suited to the production of native vegetation suitable for grazing by cattle and sheep. Rangeland vegetation is mainly mountain muhly, little bluestem, needleandthread, Parry oatgrass, and junegrass.

Deferment of grazing in spring helps to maintain vigor and production of the cool-season bunchgrasses. Fencing and properly locating livestock watering facilities help to control grazing.

Windbreaks and environmental plantings generally are suited to this soil. The hazard of soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil is well suited for use as homesites. Erosion control practices are needed to control soil blowing and water erosion on construction sites where the ground cover has been removed. Capability subclass IVe.

72—Pring coarse sandy loam, 8 to 15 percent slopes. This deep, noncalcareous, well drained soil formed in sandy sediment derived from arkosic sedimentary rock on valley side slopes and on uplands. Elevation ranges from 5,000 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 43 degrees F, and the average frost-free period is about 120 days.

Typically, the surface layer is dark grayish brown coarse sandy loam about 4 inches thick. The substratum is dark grayish brown coarse sandy loam about 10 inches thick over pale brown gravelly sandy loam that extends to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Cruckton sandy loam, 1 to 9 percent slopes; Peyton sandy

loam, 5 to 9 percent slopes; and Tomah-Crowfoot loamy sands, 8 to 15 percent slopes. Arkose beds of sandstone and shale are at a depth of 0 to 40 inches in some places.

Permeability of this Pring soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium, and the hazard of erosion is moderate. Some gullies have developed along drainageways.

Almost all areas of this soil are used as rangeland. Some areas previously cultivated have been reseeded to grass. This soil is also used for wildlife habitat and as homesites.

This soil is well suited to the production of native vegetation suitable for grazing by cattle and sheep. The native vegetation is mainly mountain muhly, little bluestem, needleandthread, Parry oatgrass, and junegrass.

Deferment of grazing in spring helps to maintain the vigor and production of the cool-season bunchgrasses. Fencing and properly locating livestock watering facilities help to control grazing.

Windbreaks and environmental plantings generally are suited to this soil. The hazard of soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for urban uses. The main limitation is slope. Special site or building designs are needed because of the slope. Access roads must have adequate cut-slope grade and be provided with drains to control surface runoff. Capability subclass VIe.

73—Razor clay loam, 3 to 9 percent slopes. This moderately deep, well drained, clayey soil formed in residuum derived from calcareous shale on uplands. Elevation ranges from 5,300 to 6,100 feet. The average annual precipitation is about 13 inches, the average annual air temperature is about 49 degrees F, and the average frost-free period is about 145 days.

Typically, the surface layer is light brownish gray clay loam about 3 inches thick. The subsoil is grayish brown heavy clay loam or clay about 15 inches thick. The substratum is grayish brown clay that grades to calcareous shale at a depth of about 31 inches. Visible lime is in the lower part of the subsoil and in the substratum.

Included with this soil in mapping are small areas of Midway clay loam, 3 to 25 percent slopes; Heldt clay loam, 0 to 3 percent slopes; and Stoneham sandy loam, 3 to 8 percent slopes.

strength. Special designs for buildings and roads are required to offset these limitations. Methods of sewage disposal other than septic tank absorption fields are needed because of the limited depth to bedrock. Capability subclass VIe.

92—Tomah-Crowfoot loamy sands, 3 to 8 percent slopes. These gently sloping to moderately sloping soils are on alluvial fans, hills, and ridges in the uplands. Elevation ranges from about 7,300 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 42 degrees F, and the average frost-free period is about 120 days.

The Tomah soil makes up about 50 percent of the complex, the Crowfoot soil about 30 percent, and other soils about 20 percent.

Included with these soils in mapping are areas of Elbeth sandy loam, 3 to 8 percent slopes; Kettle gravelly loamy sand, 3 to 8 percent slopes; and Pring coarse sandy loam, 3 to 8 percent slopes.

The Tomah soil is deep and well drained. It formed in alluvium or residuum derived from arkose beds. Typically, the surface layer is dark grayish brown loamy sand about 10 inches thick. The subsurface layer is very pale brown coarse sand about 12 inches thick. The subsoil, about 26 inches thick, is a matrix of very pale brown coarse sand in which are embedded many thin bands and lamellae of pale brown coarse sandy clay loam. The substratum is very pale brown coarse sand to a depth of 60 inches or more.

Permeability of the Tomah soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, and the hazard of erosion is slight to moderate.

The Crowfoot soil is deep and well drained. It formed in sediment weathered from arkosic sandstone. Typically, the surface layer is grayish brown loamy sand about 12 inches thick. The subsurface layer is very pale brown sand about 11 inches thick. The subsoil is light yellowish brown sandy clay loam about 13 inches thick. The substratum is very pale brown coarse sand to a depth of about 68 inches.

Permeability of the Crowfoot soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, and the hazard of erosion is slight to moderate.

This complex is used as rangeland, for wildlife habitat, and as homesites.

Native vegetation is mainly mountain muhly, bluestem, mountain brome, needleandthread, and blue grama. These soils are subject to invasion by Kentucky bluegrass and Gambel oak. Noticeable forbs are hairy goldenrod, geranium, milkvetch, low larkspur, fringed sage, and buckwheat.

Properly locating livestock watering facilities helps to control grazing. Timely deferment of grazing is needed to protect the plant cover.

Windbreaks and environmental plantings are fairly well suited to these soils. Blowing sand and moderate available water capacity are the principal limitations for the

establishment of trees and shrubs. The soils are so loose that trees need to be planted in shallow furrows and plant cover needs to be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

These soils are best suited to habitat for openland wildlife such as pronghorn antelope and sharp-tailed grouse. Although sharp-tailed grouse are not plentiful, they could be encouraged on these soils, especially where brush species are interspersed with grasses and forbs. If these soils are used as rangeland, wildlife production can be increased by managing livestock grazing to preclude overuse of the more desirable grass species and depletion of the various brush species.

These soils have good potential for use as homesites. The main limitation of the Crowfoot soil is frost-action potential. Roads and streets need to be designed to minimize frost-heave damage. Maintaining the existing vegetation on building sites during construction helps to control erosion. Capability subclass IVe.

93—Tomah-Crowfoot loamy sands, 8 to 15 percent slopes. These moderately sloping to strongly sloping soils are on alluvial fans, hills, and ridges in the uplands. Elevation ranges from about 7,300 to 7,600 feet. The average annual precipitation is about 17 inches, the average annual air temperature is about 42 degrees F, and the average frost-free period is about 120 days.

The Tomah soil makes up about 50 percent of the complex, the Crowfoot soil about 30 percent, and other soils about 20 percent.

Included with these soils in mapping are areas of Elbeth sandy loam, 8 to 15 percent slopes; Peyton-Pring complex, 8 to 15 percent slopes; and Kettle gravelly loamy sand, 8 to 40 percent slopes.

The Tomah soil is deep and well drained. It formed in alluvium or residuum derived from arkose beds. Typically, the surface layer is dark grayish brown loamy sand about 10 inches thick. The subsurface layer is very pale brown coarse sand about 12 inches thick. The subsoil, about 26 inches thick, consists of a matrix of very pale brown coarse sandy clay loam. The substratum is very pale brown coarse sand to a depth of 60 inches or more.

Permeability of the Tomah soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium, and the hazard of erosion is moderate. Some gullies are present in some drainageways and along stock trails.

The Crowfoot soil is deep and well drained. It formed in sediment weathered from arkosic sandstone. Typically, the surface layer is grayish brown loamy sand about 12 inches thick. The subsurface layer is very pale brown sand about 11 inches thick. The subsoil is light yellowish brown sandy clay loam about 13 inches thick. The substratum is very pale brown coarse sand to a depth of about 68 inches.

TABLE 16.--SOIL AND WATER FEATURES--Continued

| Soil name and map symbol | Hydro-logic group | Flooding | | | Bedrock | | Potential frost action |
|---|-------------------|--------------|----------|--------|-------------|----------|------------------------|
| | | Frequency | Duration | Months | Depth In | Hardness | |
| Gravel: 50----- | C | None----- | --- | --- | >60 | --- | High. |
| Manzanola: 51, 52, 53----- | C | None to rare | --- | --- | >60 | --- | Moderate. |
| Midway: 54----- | D | None----- | --- | --- | 10-20 | Rippable | Moderate. |
| Nederland: 55----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| Nelson: 56: Nelson part----- | B | None----- | --- | --- | 20-40 | Rippable | Low. |
| Nessel part----- | D | None----- | --- | --- | 10-20 | Rippable | Low. |
| Neville: 57----- | B | None----- | --- | --- | >60 | --- | High. |
| 58: Neville part----- | B | None----- | --- | --- | >60 | --- | High. |
| Rednun part----- | C | None----- | --- | --- | >60 | --- | Moderate. |
| 59: 60: Olney: 60, 61----- | C | None----- | --- | --- | >60 | --- | Moderate. |
| 62: Olney part----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 63: Olney part----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 64: Olney part----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 65: Pausaugunt: 66: Pausaugunt part----- | D | None----- | --- | --- | 10-20 | Hard | Moderate. |
| 67: Rock outcrop part----- | D | --- | --- | --- | --- | --- | --- |
| 68: 69: Rose: 70: Rose part----- | D | None----- | --- | --- | 10-20 | Rippable | Low. |
| 71: Rose part----- | C | None----- | --- | --- | >60 | --- | High. |
| 72: 73: Spark: 74----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 75: 76: Payton: 77, 78: Payton part----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 79: Payton part----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 80: 81: 82: 83: 84: 85: 86: 87: 88: 89: 90: 91: 92: 93: 94: 95: 96: 97: 98: 99: 100: 101: 102: 103: 104: 105: 106: 107: 108: 109: 110: 111: 112: 113: 114: 115: 116: 117: 118: 119: 120: 121: 122: 123: 124: 125: 126: 127: 128: 129: 130: 131: 132: 133: 134: 135: 136: 137: 138: 139: 140: 141: 142: 143: 144: 145: 146: 147: 148: 149: 150: 151: 152: 153: 154: 155: 156: 157: 158: 159: 160: 161: 162: 163: 164: 165: 166: 167: 168: 169: 170: 171: 172: 173: 174: 175: 176: 177: 178: 179: 180: 181: 182: 183: 184: 185: 186: 187: 188: 189: 190: 191: 192: 193: 194: 195: 196: 197: 198: 199: 200: 201: 202: 203: 204: 205: 206: 207: 208: 209: 210: 211: 212: 213: 214: 215: 216: 217: 218: 219: 220: 221: 222: 223: 224: 225: 226: 227: 228: 229: 230: 231: 232: 233: 234: 235: 236: 237: 238: 239: 240: 241: 242: 243: 244: 245: 246: 247: 248: 249: 250: 251: 252: 253: 254: 255: 256: 257: 258: 259: 260: 261: 262: 263: 264: 265: 266: 267: 268: 269: 270: 271: 272: 273: 274: 275: 276: 277: 278: 279: 280: 281: 282: 283: 284: 285: 286: 287: 288: 289: 290: 291: 292: 293: 294: 295: 296: 297: 298: 299: 300: 301: 302: 303: 304: 305: 306: 307: 308: 309: 310: 311: 312: 313: 314: 315: 316: 317: 318: 319: 320: 321: 322: 323: 324: 325: 326: 327: 328: 329: 330: 331: 332: 333: 334: 335: 336: 337: 338: 339: 340: 341: 342: 343: 344: 345: 346: 347: 348: 349: 350: 351: 352: 353: 354: 355: 356: 357: 358: 359: 360: 361: 362: 363: 364: 365: 366: 367: 368: 369: 370: 371: 372: 373: 374: 375: 376: 377: 378: 379: 380: 381: 382: 383: 384: 385: 386: 387: 388: 389: 390: 391: 392: 393: 394: 395: 396: 397: 398: 399: 400: 401: 402: 403: 404: 405: 406: 407: 408: 409: 410: 411: 412: 413: 414: 415: 416: 417: 418: 419: 420: 421: 422: 423: 424: 425: 426: 427: 428: 429: 430: 431: 432: 433: 434: 435: 436: 437: 438: 439: 440: 441: 442: 443: 444: 445: 446: 447: 448: 449: 450: 451: 452: 453: 454: 455: 456: 457: 458: 459: 460: 461: 462: 463: 464: 465: 466: 467: 468: 469: 470: 471: 472: 473: 474: 475: 476: 477: 478: 479: 480: 481: 482: 483: 484: 485: 486: 487: 488: 489: 490: 491: 492: 493: 494: 495: 496: 497: 498: 499: 500: 501: 502: 503: 504: 505: 506: 507: 508: 509: 510: 511: 512: 513: 514: 515: 516: 517: 518: 519: 520: 521: 522: 523: 524: 525: 526: 527: 528: 529: 530: 531: 532: 533: 534: 535: 536: 537: 538: 539: 540: 541: 542: 543: 544: 545: 546: 547: 548: 549: 550: 551: 552: 553: 554: 555: 556: 557: 558: 559: 560: 561: 562: 563: 564: 565: 566: 567: 568: 569: 570: 571: 572: 573: 574: 575: 576: 577: 578: 579: 580: 581: 582: 583: 584: 585: 586: 587: 588: 589: 590: 591: 592: 593: 594: 595: 596: 597: 598: 599: 600: 601: 602: 603: 604: 605: 606: 607: 608: 609: 610: 611: 612: 613: 614: 615: 616: 617: 618: 619: 620: 621: 622: 623: 624: 625: 626: 627: 628: 629: 630: 631: 632: 633: 634: 635: 636: 637: 638: 639: 640: 641: 642: 643: 644: 645: 646: 647: 648: 649: 650: 651: 652: 653: 654: 655: 656: 657: 658: 659: 660: 661: 662: 663: 664: 665: 666: 667: 668: 669: 670: 671: 672: 673: 674: 675: 676: 677: 678: 679: 680: 681: 682: 683: 684: 685: 686: 687: 688: 689: 690: 691: 692: 693: 694: 695: 696: 697: 698: 699: 700: 701: 702: 703: 704: 705: 706: 707: 708: 709: 710: 711: 712: 713: 714: 715: 716: 717: 718: 719: 720: 721: 722: 723: 724: 725: 726: 727: 728: 729: 730: 731: 732: 733: 734: 735: 736: 737: 738: 739: 740: 741: 742: 743: 744: 745: 746: 747: 748: 749: 750: 751: 752: 753: 754: 755: 756: 757: 758: 759: 760: 761: 762: 763: 764: 765: 766: 767: 768: 769: 770: 771: 772: 773: 774: 775: 776: 777: 778: 779: 780: 781: 782: 783: 784: 785: 786: 787: 788: 789: 790: 791: 792: 793: 794: 795: 796: 797: 798: 799: 800: 801: 802: 803: 804: 805: 806: 807: 808: 809: 810: 811: 812: 813: 814: 815: 816: 817: 818: 819: 820: 821: 822: 823: 824: 825: 826: 827: 828: 829: 830: 831: 832: 833: 834: 835: 836: 837: 838: 839: 840: 841: 842: 843: 844: 845: 846: 847: 848: 849: 850: 851: 852: 853: 854: 855: 856: 857: 858: 859: 860: 861: 862: 863: 864: 865: 866: 867: 868: 869: 870: 871: 872: 873: 874: 875: 876: 877: 878: 879: 880: 881: 882: 883: 884: 885: 886: 887: 888: 889: 890: 891: 892: 893: 894: 895: 896: 897: 898: 899: 900: 901: 902: 903: 904: 905: 906: 907: 908: 909: 910: 911: 912: 913: 914: 915: 916: 917: 918: 919: 920: 921: 922: 923: 924: 925: 926: 927: 928: 929: 930: 931: 932: 933: 934: 935: 936: 937: 938: 939: 940: 941: 942: 943: 944: 945: 946: 947: 948: 949: 950: 951: 952: 953: 954: 955: 956: 957: 958: 959: 960: 961: 962: 963: 964: 965: 966: 967: 968: 969: 970: 971: 972: 973: 974: 975: 976: 977: 978: 979: 980: 981: 982: 983: 984: 985: 986: 987: 988: 989: 990: 991: 992: 993: 994: 995: 996: 997: 998: 999: 1000: 1001: 1002: 1003: 1004: 1005: 1006: 1007: 1008: 1009: 1010: 1011: 1012: 1013: 1014: 1015: 1016: 1017: 1018: 1019: 1020: 1021: 1022: 1023: 1024: 1025: 1026: 1027: 1028: 1029: 1030: 1031: 1032: 1033: 1034: 1035: 1036: 1037: 1038: 1039: 1040: 1041: 1042: 1043: 1044: 1045: 1046: 1047: 1048: 1049: 1050: 1051: 1052: 1053: 1054: 1055: 1056: 1057: 1058: 1059: 1060: 1061: 1062: 1063: 1064: 1065: 1066: 1067: 1068: 1069: 1070: 1071: 1072: 1073: 1074: 1075: 1076: 1077: 1078: 1079: 1080: 1081: 1082: 1083: 1084: 1085: 1086: 1087: 1088: 1089: 1090: 1091: 1092: 1093: 1094: 1095: 1096: 1097: 1098: 1099: 1100: 1101: 1102: 1103: 1104: 1105: 1106: 1107: 1108: 1109: 1110: 1111: 1112: 1113: 1114: 1115: 1116: 1117: 1118: 1119: 1120: 1121: 1122: 1123: 1124: 1125: 1126: 1127: 1128: 1129: 1130: 1131: 1132: 1133: 1134: 1135: 1136: 1137: 1138: 1139: 1140: 1141: 1142: 1143: 1144: 1145: 1146: 1147: 1148: 1149: 1150: 1151: 1152: 1153: 1154: 1155: 1156: 1157: 1158: 1159: 1160: 1161: 1162: 1163: 1164: 1165: 1166: 1167: 1168: 1169: 1170: 1171: 1172: 1173: 1174: 1175: 1176: 1177: 1178: 1179: 1180: 1181: 1182: 1183: 1184: 1185: 1186: 1187: 1188: 1189: 1190: 1191: 1192: 1193: 1194: 1195: 1196: 1197: 1198: 1199: 1200: 1201: 1202: 1203: 1204: 1205: 1206: 1207: 1208: 1209: 1210: 1211: 1212: 1213: 1214: 1215: 1216: 1217: 1218: 1219: 1220: 1221: 1222: 1223: 1224: 1225: 1226: 1227: 1228: 1229: 1230: 1231: 1232: 1233: 1234: 1235: 1236: 1237: 1238: 1239: 1240: 1241: 1242: 1243: 1244: 1245: 1246: 1247: 1248: 1249: 1250: 1251: 1252: 1253: 1254: 1255: 1256: 1257: 1258: 1259: 1260: 1261: 1262: 1263: 1264: 1265: 1266: 1267: 1268: 1269: 1270: 1271: 1272: 1273: 1274: 1275: 1276: 1277: 1278: 1279: 1280: 1281: 1282: 1283: 1284: 1285: 1286: 1287: 1288: 1289: 1290: 1291: 1292: 1293: 1294: 1295: 1296: 1297: 1298: 1299: 1300: 1301: 1302: 1303: 1304: 1305: 1306: 1307: 1308: 1309: 1310: 1311: 1312: 1313: 1314: 1315: 1316: 1317: 1318: 1319: 1320: 1321: 1322: 1323: 1324: 1325: 1326: 1327: 1328: 1329: 1330: 1331: 1332: 1333: 1334: 1335: 1336: 1337: 1338: 1339: 1340: 1341: 1342: 1343: 1344: 1345: 1346: 1347: 1348: 1349: 1350: 1351: 1352: 1353: 1354: 1355: 1356: 1357: 1358: 1359: 1360: 1361: 1362: 1363: 1364: 1365: 1366: 1367: 1368: 1369: 1370: 1371: 1372: 1373: 1374: 1375: 1376: 1377: 1378: 1379: 1380: 1381: 1382: 1383: 1384: 1385: 1386: 1387: 1388: 1389: 1390: 1391: 1392: 1393: 1394: 1395: 1396: 1397: 1398: 1399: 1400: 1401: 1402: 1403: 1404: 1405: 1406: 1407: 1408: 1409: 1410: 1411: 1412: 1413: 1414: 1415: 1416: 1417: 1418: 1419: 1420: 1421: 1422: 1423: 1424: 1425: 1426: 1427: 1428: 1429: 1430: 1431: 1432: 1433: 1434: 1435: 1436: 1437: 1438: 1439: 1440: 1441: 1442: 1443: 1444: 1445: 1446: 1447: 1448: 1449: 1450: 1451: 1452: 1453: 1454: 1455: 1456: 1457: 1458: 1459: 1460: 1461: 1462: 1463: 1464: 1465: 1466: 1467: 1468: 1469: 1470: 1471: 1472: 1473: 1474: 1475: 1476: 1477: 1478: 1479: 1480: 1481: 1482: 1483: 1484: 1485: 1486: 1487: 1488: 1489: 1490: 1491: 1492: 1493: 1494: 1495: 1496: 1497: 1498: 1499: 1500: 1501: 1502: 1503: 1504: 1505: 1506: 1507: 1508: 1509: 1510: 1511: 1512: 1513: 1514: 1515: 1516: 1517: 1518: 1519: 1520: 1521: 1522: 1523: 1524: 1525: 1526: 1527: 1528: 1529: 1530: 1531: 1532: 1533: 1534: 1535: 1536: 1537: 1538: 1539: 1540: 1541: 1542: 1543: 1544: 1545: 1546: 1547: 1548: 1549: 1550: 1551: 1552: 1553: 1554: 1555: 1556: 1557: 1558: 1559: 1560: 1561: 1562: 1563: 1564: 1565: 1566: 1567: 1568: 1569: 1570: 1571: 1572: 1573: 1574: 1575: 1576: 1577: 1578: 1579: 1580: 1581: 1582: 1583: 1584: 1585: 1586: 1587: 1588: 1589: 1590: 1591: 1592: 1593: 1594: 1595: 1596: 1597: 1598: 1599: 1600: 1601: 1602: 1603: 1604: 1605: 1606: 1607: 1608: 1609: 1610: 1611: 1612: 1613: 1614: 1615: 1616: 1617: 1618: 1619: 1620: 1621: 1622: 1623: 1624: 1625: 1626: 1627: 1628: 1629: 1630: 1631: 1632: 1633: 1634: 1635: 1636: 1637: 1638: 1639: 1640: 1641: 1642: 1643: 1644: 1645: 1646: 1647: 1648: 1649: 1650: 1651: 1652: 1653: 1654: 1655: 1656: 1657: 1658: 1659: 1660: 1661: 1662: 1663: 1664: 1665: 1666: 1667: 1668: 1669: 1670: 1671: 1672: 1673: 1674: 1675: 1676: 1677: 1678: 1679: 1680: 1681: 1682: 1683: 1684: 1685: 1686: 1687: 1688: 1689: 1690: 1691: 1692: 1693: 1694: 1695: 1696: 1697: 1698: 1699: 1700: 1701: 1702: 1703: 1704: 1705: 1706: 1707: 1708: 1709: 1710: 1711: 1712: 1713: 1714: 1715: 1716: 1717: 1718: 1719: 1720: 1721: 1722: 1723: 1724: 1725: 1726: 1727: 172 | | | | | | | |

TABLE 16.--SOIL AND WATER FEATURES--Continued

| Soil name and map symbol | Hydro-logic group | Flooding | | | Bedrock | | Potential frost action |
|---|-------------------|-----------------|-----------------|---------|-----------|----------|------------------------|
| | | Frequency | Duration | Months | Depth | Hardness | |
| Tomah: 192, 193: Tomah part----- | B | None----- | --- | --- | In >60 | --- | Moderate. |
| Crowfoot part-- | B | None----- | --- | --- | >60 | --- | Moderate. |
| Travessilla: 194: Travessilla part----- | D | None----- | --- | --- | 6-20 | Hard | Low. |
| Rock outcrop part----- | D | --- | --- | --- | --- | --- | --- |
| Truckton: 95, 96, 97----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| 198: Truckton part-- | B | None----- | --- | --- | >60 | --- | Moderate. |
| Blakeland part- | A | None----- | --- | --- | >60 | --- | Low. |
| 199, 100: Truckton part-- | B | None----- | --- | --- | >60 | --- | Moderate. |
| Bresser part--- | B | None----- | --- | --- | >60 | --- | Low. |
| Hatic: Torrifluvents: 101----- | B | Occasional----- | Very brief----- | Mar-Aug | >60 | --- | Moderate. |
| Talent: 102, 103----- | A | None----- | --- | --- | >60 | --- | Low. |
| Vona: 104, 105----- | B | None----- | --- | --- | >60 | --- | Moderate. |
| Wigton: 106----- | A | None----- | --- | --- | >60 | --- | Low. |
| Wiley: 107, 108----- | B | None----- | --- | --- | >60 | --- | Low. |
| Yoder: 109, 110----- | B | None----- | --- | --- | >60 | --- | Low. |

¹This map unit is made up of two or more dominant kinds of soil. See map unit description for the composition and behavior characteristics of the map unit.

APPENDIX B1

HYDROLOGIC CALCULATIONS – SCS METHOD

(FROM APPROVED 2014 WALDEN PRESERVE MDDP)

TABLE 5-5
RUNOFF CURVE NUMBERS FOR HYDROLOGIC SOIL
COVER COMPLEXES - URBAN AND SUBURBAN CONDITIONS 1/
(Antecedent Moisture Condition II)
(From: U.S. Dept. of Agriculture,
Soil Conservation Service, 1977)

| <u>Land Use</u> | <u>Hydrologic Soil Group</u> | | | |
|--|------------------------------|---|----------|----------|
| | <u>A</u> | <u>B</u> | <u>C</u> | <u>D</u> |
| Open spaces, lawns, parks, golf courses, cemeteries, etc. | | | | |
| Good condition: grass cover on 75% or more of the area | 39* | 61 | 74 | 80 |
| Fair condition: grass cover on 50% to 75% of the area | 49* | 69 | 79 | 84 |
| Commercial and Business areas (85% Impervious) | 89* | 92 | 94 | 95 |
| Industrial Districts 72% Impervious) | 81* | 88 | 91 | 93 |
| Residential: <u>2/</u> | | | | |
| <u>Acres per Dwelling Unit</u> | | <u>Average % Impervious</u> <u>3/</u> | | |
| 1/8 acre or less | 65 | 77* | 85 | 90 |
| 1/4 acre | 38 | 61* | 75 | 83 |
| 1/3 acre | 30 | 57* | 72 | 81 |
| 1/2 acre | 25 | 54* | 70 | 80 |
| 1 acre | 20 | 51* | 68 | 79 |
| Paved parking lots, roofs, driveways, etc. | 98 | 98 | 98 | 98 |
| Streets and Roads: | | | | |
| paved with curbs and storm sewers | 98 | 98 | 98 | 98 |
| gravel | 76* | 85 | 89 | 91 |
| dirt | 72* | 82 | 87 | 89 |

1/ For a more detailed description of agricultural land use curve numbers, refer to the National Engineering Handbook (U.S. Dept. of Agriculture, Soil Conservation Service, 1972).

2/ Curve numbers are computed assuming the runoff from the house and driveway is directed towards the street with a minimum of roof water directed to lawns where additional infiltration could occur.

3/ The remaining pervious areas (lawn) are considered to be in good pasture condition for these curve numbers.

* Not to be used wherever overlot grading or filling is to occur.

WALDEN PRESERVE
IMPERVIOUS AREA CALCULATIONS

| DEVELOPED CONDITIONS | | | | | | | | | | | | |
|----------------------|-----------------|-----------|-------|-------------------------------|--------|-----------|-------------------------------|--------|------|-------------------------------|--------|-----------------|
| IMPERVIOUS AREAS | | | | | | | | | | | | |
| BASIN | TOTAL AREA (AC) | SOIL TYPE | (AC) | SUB-AREA 1 DEVELOPMENT/ COVER | IMP. % | AREA (AC) | SUB-AREA 2 DEVELOPMENT/ COVER | IMP. % | (AC) | SUB-AREA 3 DEVELOPMENT/ COVER | IMP. % | WEIGHTED % IMP. |
| OA1.1 | 83.8 | B | 83.8 | PASTURE | 2.00 | | | | | | | 2.00 |
| OA1.2 | 108.2 | B | 108.2 | PASTURE | 2.00 | | | | | | | 2.00 |
| A1 | 28.25 | B | 28.25 | 2.5-AC LOTS | 11.00 | | | | | | | 11.00 |
| OA1.3 | 14.8 | B | 14.8 | PASTURE | 2.00 | | | | | | | 2.00 |
| A2 | 2.34 | B | 2.34 | 2.5-AC LOTS | 11.00 | | | | | | | 11.00 |
| OA1.3.A2 | 17.14 | B | | | | | | | | | | 3.23 |
| OA1.A1.A2 | 237.99 | B | | | | | | | | | | 3.16 |
| OA1.4 | 25.2 | B | 25.2 | PASTURE | 2.00 | | | | | | | 2.00 |
| A3 | 11.22 | B | 11.22 | 2.5-AC LOTS | 11.00 | | | | | | | 11.00 |
| A4 | 1.58 | B | 1.58 | 2.5-AC LOTS | 11.00 | | | | | | | 11.00 |
| OA1.4.A3.A4 | 38.0 | B | | | | | | | | | | 5.03 |
| A5 | 15.14 | B | 15.14 | 2.5-AC LOTS | 11.00 | | | | | | | 11.00 |
| A6 | 1.98 | B | 1.98 | 2.5-AC LOTS | 11.00 | | | | | | | 11.00 |
| A5.A6 | 17.12 | B | | | | | | | | | | 11.00 |
| A7 | 27.55 | B | 27.55 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| A8 | 4.12 | B | 4.12 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| A9 | 17.78 | B | 17.78 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| OA1.4.A3.A4.A9 | 55.78 | B | | | | | | | | | | 9.80 |
| OA1.A1.A9 | 341.96 | B | | | | | | | | | | 6.20 |
| OB1 | 35.4 | B | 35.4 | 1/2-AC LOTS | 25.00 | | | | | | | 25.00 |
| B1-B4 | 55.5 | B | 55.5 | 1/2-AC LOTS | 25.00 | | | | | | | 25.00 |
| OB1.B1-B4 | 90.90 | B | | | | | | | | | | 25.00 |
| B5-B10 | 71.80 | B | 71.8 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| OB1.B1-B10 | 162.70 | B | | | | | | | | | | 22.79 |
| OA1.OB1.A.B | 504.66 | B | | | | | | | | | | 11.55 |
| OC1 | 129.00 | B | 129 | 1/2-AC LOTS | 25.00 | | | | | | | 25.00 |
| C1-C4 | 40.30 | B | 40.3 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| C5-C8 | 59.30 | B | 59.3 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| C9 | 4.50 | B | 4.5 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| OC1.C1-C9 | 233.10 | B | | | | | | | | | | 22.77 |
| OA1-OC1.A-C9 | 737.76 | B | | | | | | | | | | 15.09 |
| OC2 | 81.70 | B | 81.7 | 1/2-AC LOTS | 25.00 | | | | | | | 25.00 |
| C10-C12 | 26.40 | B | 26.4 | 1-AC LOTS | 20.00 | | | | | | | 20.00 |
| C13 | 22.40 | B | 22.4 | MEADOW | 2.00 | | | | | | | 2.00 |
| OC2.C10-C13 | 130.50 | B | | | | | | | | | | 20.04 |
| OD1 | 3.30 | B | 3.30 | 1/2-AC LOTS | 25.00 | | | | | | | 25.00 |
| OD2 | 4.50 | B | 4.50 | FOREST | 2.00 | | | | | | | 2.00 |
| OD3 | 10.30 | B | 10.30 | FOREST | 2.00 | | | | | | | 2.00 |
| OD4 | 6.00 | B | 6.00 | FOREST | 2.00 | | | | | | | 2.00 |
| D | 10.27 | B | 10.27 | 1/2-AC LOTS | 25.00 | | | | | | | 25.00 |
| OD1-OD4, D | 34.37 | B | | | | | | | | | | 11.08 |
| OA1-OD1.A-D | 902.63 | B | | | | | | | | | | 15.85 |

**WALDEN PRESERVE SUBDIVISION
SCS HYDROLOGIC CALCULATIONS (HEC-HMS)**

HISTORIC FLOWS

| BASIN | DESIGN POINT | AREA (AC) | AREA (SM) | CURVE No. (CN) | S | Ia | PERCENT IMPERVIOUS (%) | Time of Concentration Tc (MIN) | Total Lag Time Tl (MIN) | Peak Flow SCS | |
|-------------|--------------|-----------|-----------|----------------|------|------|------------------------|--------------------------------|-------------------------|---------------|------------|
| | | | | | | | | | | Q5 (CFS) | Q100 (CFS) |
| CA1 | | 232.0 | 0.3625 | 61 | 6.39 | 1.28 | 2 | 34.80 | 20.88 | | |
| A | | 105.1 | 0.1642 | 61 | 6.39 | 1.28 | 2 | 18.80 | 11.28 | | |
| CA1-A | 1 | 337.1 | 0.5267 | 61 | 6.39 | 1.28 | 2 | 53.60 | 32.16 | 33.1 | 213.4 |
| OB1 | | 35.4 | 0.0553 | 70 | 4.29 | 0.86 | 25 | 8.20 | 4.92 | | |
| B | | 118.0 | 0.1844 | 61 | 6.39 | 1.28 | 2 | 13.70 | 8.22 | | |
| CA1-OAB,A-B | 2 | 490.5 | 0.7664 | 61 | 6.39 | 1.28 | 2 | 67.30 | 40.38 | 65.8 | 287.9 |
| OC1 | | 187.6 | 0.2931 | 70 | 4.29 | 0.86 | 25 | 14.40 | 8.64 | | |
| C | | 190.2 | 0.2972 | 61 | 6.39 | 1.28 | 2 | 47.10 | 28.26 | | |
| OD1 | | 24.1 | 0.0377 | 61 | 6.39 | 1.28 | 2 | 30.80 | 18.18 | | |
| D | | 10.27 | 0.0160 | 61 | 6.39 | 1.28 | 2 | 4.50 | 2.70 | | |
| CA1-OC1,A-D | 4 | 902.7 | 1.4104 | 61 | 6.39 | 1.28 | 2 | 114.40 | 68.64 | 222.5 | 582.9 |

DEVELOPED FLOWS

| BASIN | DESIGN POINT | AREA (AC) | AREA (SM) | CURVE No. (CN) | S | Ia | PERCENT IMPERVIOUS (%) | Time of Concentration Tc (HR) | Total Lag Time Tl (HR) | Peak Flow SCS | |
|-------------------|--------------|-----------|-----------|----------------|------|------|------------------------|-------------------------------|------------------------|---------------|------------|
| | | | | | | | | | | Q5 (CFS) | Q100 (CFS) |
| CA1 | | 232.0 | 0.3625 | 61 | 6.39 | 1.28 | 2 | 36.80 | 22.08 | | |
| A9 (A1-A9) | | 110.0 | 0.1719 | 68 | 4.71 | 0.94 | 20 | 19.00 | 11.40 | | |
| CA1,A1-A9 | 1 | 342.0 | 0.5344 | | | | | 55.80 | 33.48 | 92.1 | 261.3 |
| OB1 | | 35.4 | 0.0553 | 70 | 4.29 | 0.86 | 25 | 20.60 | 12.36 | | |
| B4 (B1-B4) | | 55.5 | 0.0867 | 70 | 4.29 | 0.86 | 25 | 21.10 | 12.66 | | |
| B10 (B5-B10) | | 71.8 | 0.1122 | 68 | 4.71 | 0.94 | 20 | 28.70 | 17.22 | | |
| Tt DP1 to DP2 | | | | | | | | 13.70 | 8.22 | | |
| CA1-OB1,A-B | 2 | 504.7 | 0.7886 | | | | | 69.50 | 41.70 | 208.0 | 551.4 |
| OC1 | | 129 | 0.2016 | 69.5 | 4.39 | 0.88 | 23.6 | 14.40 | 8.64 | | |
| C4 (C1-C4) | | 40.3 | 0.0630 | 68 | 4.71 | 0.94 | 20 | 21.70 | 13.02 | | |
| C8 (C5-C8) | | 59.3 | 0.0927 | 68 | 4.71 | 0.94 | 20 | 35.00 | 21.00 | | |
| C9 | | 4.5 | 0.0070 | 61 | 6.39 | 1.28 | 2 | 2.10 | 1.26 | | |
| Tt DP2 to DP3 | | | | | | | | 22.10 | 13.26 | | |
| CA1-OC1,A,B,C1-C8 | 3 | 737.8 | 1.1528 | | | | | 91.60 | 54.96 | 280.7 | 734.2 |
| OC2 | | 81.7 | 0.1277 | 67.9 | 4.73 | 0.95 | 19.1 | 14.40 | 8.64 | | |
| C12 (C10-C12) | | 26.4 | 0.0413 | 68 | 4.71 | 0.94 | 20 | 19.10 | 11.46 | | |
| C13 | | 22.4 | 0.0350 | 61 | 6.39 | 1.28 | 2 | 15.30 | 9.18 | | |
| OD1 | | 24.1 | 0.0377 | 61 | 6.39 | 1.28 | 2 | 30.30 | 18.18 | | |
| D | | 10.3 | 0.0160 | 70 | 4.29 | 0.86 | 25 | 4.50 | 2.70 | | |
| Tt DP3 to DP4 | | | | | | | | 25.40 | 15.24 | | |
| CA1-OC2,A-D | 4 | 902.7 | 1.4104 | | | | | 117.00 | 70.20 | 298.7 | 785.0 |

1) Tc = Tco + Tt (from Rational Method Calculation Spreadsheet)

2) SCS LAG TIME, Tl = 0.6 * Tc

3) PEAK FLOWS CALCULATED BY HEC-HMS 3.5; 5-YR RAINFALL DEPTH = 2.6 IN; 100-YR RAINFALL DEPTH = 4.4 IN

WALDEN PRESERVE SUBDIVISION
SCS HYDROLOGIC CALCULATIONS (HEC-HMS)

| BASIN | DESIGN POINT | AREA (AC) | AREA (SQ. MI) | CURVE No. (CN) | S | I _a | PERCENT IMPERVIOUS (%) | Time of | | Peak Flow | |
|-------------------|--------------|-----------|---------------|----------------|------|----------------|------------------------|--|---|-------------------------|---------------------------|
| | | | | | | | | Concentration T _c ⁽¹⁾ (HR) | Leg Time T _t ⁽²⁾ (HR) | Q5 ⁽³⁾ (CFS) | Q100 ⁽³⁾ (CFS) |
| OA1 | | 232.0 | 0.3625 | 61 | 6.39 | 1.28 | 2 | 36.80 | 22.08 | | |
| A9 (A1-A9) | | 110.0 | 0.1719 | 68 | 4.71 | 0.94 | 20 | 19.00 | 11.40 | | |
| OA1,A1-A9 | 1 | 342.0 | 0.5344 | | | | | 55.80 | 33.48 | 92.1 | 261.3 |
| OB1 | | 35.4 | 0.0553 | 70 | 4.29 | 0.86 | 25 | 20.60 | 12.36 | | |
| B4 (B1-B4) | | 55.5 | 0.0867 | 70 | 4.29 | 0.86 | 25 | 21.10 | 12.66 | | |
| B10 (B6-B10) | | 71.8 | 0.1122 | 68 | 4.71 | 0.94 | 20 | 28.70 | 17.22 | | |
| T1,DP1 to DP2 | | | | | | | | 13.70 | 8.22 | | |
| OA1,OB1,A-B | 2 | 504.7 | 0.7886 | | | | | 69.50 | 41.70 | 82.3 | 311.1 |
| OC1 | | 129 | 0.2016 | 69.5 | 4.39 | 0.88 | 23.6 | 14.40 | 8.64 | | |
| C4 (C1-C4) | | 40.3 | 0.0630 | 68 | 4.71 | 0.94 | 20 | 21.70 | 13.02 | | |
| C8 (C5-C8) | | 59.3 | 0.0927 | 68 | 4.71 | 0.94 | 20 | 35.00 | 21.00 | | |
| C9 | | 4.5 | 0.0070 | 61 | 6.39 | 1.28 | 2 | 2.10 | 1.28 | | |
| T1,DP2 to DP3 | | | | | | | | 22.10 | 13.26 | | |
| OA1-OC1,A,B,C1-C8 | 3 | 737.8 | 1.1528 | | | | | 91.60 | 54.96 | 175.2 | 459.8 |
| OC2 | | 81.7 | 0.1277 | 67.9 | 4.73 | 0.95 | 19.1 | 14.40 | 8.64 | | |
| C12 (C10-C12) | | 26.4 | 0.0413 | 68 | 4.71 | 0.94 | 20 | 19.10 | 11.46 | | |
| C13 | | 23.4 | 0.0350 | 61 | 6.39 | 1.28 | 2 | 15.30 | 9.18 | | |
| OD1 | | 24.1 | 0.0377 | 61 | 6.39 | 1.28 | 2 | 30.30 | 18.18 | | |
| D | | 10.3 | 0.0160 | 70 | 4.29 | 0.86 | 25 | 4.50 | 2.70 | | |
| T1,DP3 to DP4 | | | | | | | | 25.40 | 15.24 | | |
| OA1-OC2,A-D | 4 | 902.7 | 1.4104 | | | | | 117.00 | 70.20 | 213.5 | 577.1 |

1) T_c = T_{c0} + T_t (from Rational Method Calculation Spreadsheet)


2) SCS LAG TIME, T_t = 0.6 * T_c

3) PEAK FLOWS CALCULATED BY HEC-HMS 3.5; 5-YR RAINFALL DEPTH = 2.6 IN; 100-YR RAINFALL DEPTH = 4.4 IN



HEC-HMS

Project : WALD-H
Basin Model : Basin 1
Aug 07 21:25:58 MDT 2013



| | | | |
|-----------------------------------|-----------------------------------|----------------------|----------------|
| Project: WALD-H | Simulation Run: Run 1 | | |
| Hydrologic Element | Drainage Area (MI ²) | Peak Discharge (CFS) | Time of Peak |
| Start of Run: 01Jan3000, 01:00 | Basin Model: Basin 1 | | Volume (AC-FT) |
| End of Run: 02Jan3000, 01:30 | Meteorologic Model: Met 1 | | |
| Compute Time: 07Aug2013, 21:24:43 | Control Specifications: Control 1 | | |

| | | | | |
|-----|--------|-------|------------------|-------|
| OA1 | 0.3625 | 176.1 | 01Jan3000, 13:16 | 21.1 |
| R-1 | 0.3625 | 176.1 | 01Jan3000, 13:27 | 21.0 |
| A | 0.1642 | 118.2 | 01Jan3000, 13:06 | 9.6 |
| DP1 | 0.5267 | 213.4 | 01Jan3000, 13:25 | 30.6 |
| R-2 | 0.5267 | 213.4 | 01Jan3000, 13:33 | 30.5 |
| B | 0.1844 | 154.8 | 01Jan3000, 13:03 | 10.7 |
| OB1 | 0.0553 | 113.5 | 01Jan3000, 12:58 | 6.8 |
| DP2 | 0.7664 | 287.9 | 01Jan3000, 13:02 | 48.0 |
| R-4 | 0.7664 | 287.9 | 01Jan3000, 13:30 | 47.6 |
| C | 0.2972 | 116.4 | 01Jan3000, 13:24 | 17.2 |
| OC1 | 0.2931 | 517.1 | 01Jan3000, 13:02 | 36.0 |
| OD1 | 0.0377 | 20.2 | 01Jan3000, 13:13 | 2.2 |
| R-D | 0.0377 | 20.2 | 01Jan3000, 13:15 | 2.2 |
| D | 0.0160 | 17.4 | 01Jan3000, 12:57 | 0.9 |
| DP4 | 1.4104 | 582.9 | 01Jan3000, 13:03 | 103.9 |




HEC-HMS

Project : WALD_D

Basin Model : Basin 1

Aug 07 21:29:09 MDT 2013



5-YR

Project: WALD_D Simulation Run: Run 1

Start of Run: 01Jan3000, 01:00 Basin Model: Basin 1
 End of Run: 02Jan3000, 01:30 Meteorologic Model: Met 1
 Compute Time: 07Aug2013, 21:31:24 Control Specifications: Control 1

| | | | | |
|-----|--------|-------|------------------|------|
| OA1 | 0.3625 | 24.9 | 01Jan3000, 13:21 | 5.3 |
| R-1 | 0.3625 | 24.9 | 01Jan3000, 13:32 | 5.3 |
| A9 | 0.1719 | 88.9 | 01Jan3000, 13:05 | 7.9 |
| DP1 | 0.5344 | 92.1 | 01Jan3000, 13:06 | 13.2 |
| R-2 | 0.5344 | 92.1 | 01Jan3000, 13:14 | 13.2 |
| B10 | 0.1122 | 46.2 | 01Jan3000, 13:11 | 5.2 |
| B4 | 0.0867 | 52.2 | 01Jan3000, 13:06 | 4.7 |
| OB1 | 0.0553 | 33.7 | 01Jan3000, 13:06 | 3.0 |
| DP2 | 0.7886 | 208.0 | 01Jan3000, 13:11 | 26.1 |
| R3 | 0.7886 | 208.0 | 01Jan3000, 13:24 | 26.1 |
| OC1 | 0.2016 | 137.0 | 01Jan3000, 13:03 | 10.6 |
| C8 | 0.0927 | 33.6 | 01Jan3000, 13:14 | 4.3 |
| C4 | 0.0630 | 30.5 | 01Jan3000, 13:07 | 2.9 |
| C9 | 0.0070 | 1.3 | 01Jan3000, 12:58 | 0.1 |
| DP3 | 1.1529 | 280.7 | 01Jan3000, 13:22 | 43.9 |
| R-4 | 1.1529 | 280.7 | 01Jan3000, 13:37 | 43.8 |
| OC2 | 0.1277 | 72.3 | 01Jan3000, 13:03 | 5.7 |
| C12 | 0.0413 | 21.3 | 01Jan3000, 13:05 | 1.9 |
| OD1 | 0.0377 | 2.9 | 01Jan3000, 13:16 | 0.5 |
| R-D | 0.0377 | 2.9 | 01Jan3000, 13:18 | 0.5 |
| C13 | 0.0350 | 4.1 | 01Jan3000, 13:06 | 0.5 |
| D | 0.0160 | 14.6 | 01Jan3000, 12:56 | 0.9 |
| DP4 | 1.4106 | 298.7 | 01Jan3000, 13:37 | 53.4 |

Project: WALD_D Simulation Run: Run 1

Start of Run: 01Jan3000, 01:00 Basin Model: Basin 1
 End of Run: 02Jan3000, 01:30 Meteorologic Model: Met 1
 Compute Time: 07Aug2013, 21:30:41 Control Specifications: Control 1

| Hydrologic Element | Drainage Area (MI ²) | Peak Discharge (CFS) | Time of Peak | Volume (AC-FT) |
|--------------------|----------------------------------|----------------------|------------------|----------------|
| OA1 | 0.3625 | 169.4 | 01Jan3000, 13:17 | 21.0 |
| R-1 | 0.3625 | 169.4 | 01Jan3000, 13:28 | 21.0 |
| A9 | 0.1719 | 240.1 | 01Jan3000, 13:05 | 18.8 |
| DP1 | 0.5344 | 261.3 | 01Jan3000, 13:06 | 39.8 |
| R-2 | 0.5344 | 261.3 | 01Jan3000, 13:14 | 39.7 |
| B10 | 0.1122 | 125.0 | 01Jan3000, 13:10 | 12.3 |
| B4 | 0.0867 | 129.2 | 01Jan3000, 13:06 | 10.6 |
| OB1 | 0.0553 | 83.3 | 01Jan3000, 13:06 | 6.8 |
| DP2 | 0.7886 | 551.4 | 01Jan3000, 13:11 | 69.4 |
| R3 | 0.7886 | 551.4 | 01Jan3000, 13:24 | 69.3 |
| OC1 | 0.2016 | 345.7 | 01Jan3000, 13:02 | 24.0 |
| C8 | 0.0927 | 91.0 | 01Jan3000, 13:14 | 10.1 |
| C4 | 0.0630 | 82.3 | 01Jan3000, 13:06 | 6.9 |
| C9 | 0.0070 | 8.0 | 01Jan3000, 12:55 | 0.4 |
| DP3 | 1.1529 | 734.2 | 01Jan3000, 13:22 | 110.7 |
| R-4 | 1.1529 | 734.2 | 01Jan3000, 13:37 | 110.4 |
| OC2 | 0.1277 | 197.7 | 01Jan3000, 13:02 | 13.7 |
| C12 | 0.0413 | 57.5 | 01Jan3000, 13:05 | 4.5 |
| OD1 | 0.0377 | 20.2 | 01Jan3000, 13:13 | 2.2 |
| R-D | 0.0377 | 20.2 | 01Jan3000, 13:15 | 2.2 |
| C13 | 0.0350 | 27.9 | 01Jan3000, 13:04 | 2.0 |
| D | 0.0160 | 35.8 | 01Jan3000, 12:56 | 2.0 |
| DP4 | 1.4106 | 785.0 | 01Jan3000, 13:36 | 134.8 |




HEC-HMS

Project : WALD_DET

Basin Model : Basin 1


Sep 07 16:02:43 MDT 2014





Components **Compute** Results

- B
- DP2
- R3
- OC1
- C8
- C
- C4
- C9
- DP3
- R-4
- OC2
- C12



Reservoir Options

Basin Name: Basin 1
 Element Name: B

Description: DP2

Method: Outflow Curve

Storage Method: Elevation-Area-Dischar

*Elev-Area Function: P-B

*Elev-Dis Function: P-B

Primary: Elevation-Discharge

Initial Condition: Elevation

*Initial Elevation (ft): 7447.0

WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'C9'; reduce simulation time interval.

NOTE 41743: Initial abstraction ratio for subbasin 'OC2' is 0.201.

NOTE 41743: Initial abstraction ratio for subbasin 'C12' is 0.1998.

NOTE 41743: Initial abstraction ratio for subbasin 'OD1' is 0.2002.

NOTE 41743: Initial abstraction ratio for subbasin 'C13' is 0.2002.

NOTE 41743: Initial abstraction ratio for subbasin 'D' is 0.2007.

WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'D'; reduce simulation time interval.

NOTE 10185: Finished computing simulation run 'Run 1' at time 07Sep2014, 16:00:36.

NOTE 10184: Began computing simulation run 'Run 1' at time 07Sep2014, 16:02:12.

NOTE 20364: Found no parameter problems in meteorologic model 'Met 1'.

NOTE 40049: Found no parameter problems in basin model 'Basin 1'.

NOTE 41743: Initial abstraction ratio for subbasin 'OA1' is 0.2002.

NOTE 41743: Initial abstraction ratio for subbasin 'A9' is 0.1998.

NOTE 41743: Initial abstraction ratio for subbasin 'B10' is 0.1998.

NOTE 41743: Initial abstraction ratio for subbasin 'B4' is 0.2007.

NOTE 41743: Initial abstraction ratio for subbasin 'OB1' is 0.2007.

NOTE 41743: Initial abstraction ratio for subbasin 'OC1' is 0.2005.

NOTE 41743: Initial abstraction ratio for subbasin 'C8' is 0.1998.

NOTE 41743: Initial abstraction ratio for subbasin 'C4' is 0.1998.

NOTE 41743: Initial abstraction ratio for subbasin 'C9' is 0.2002.

WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'C9'; reduce simulation time interval.

NOTE 41743: Initial abstraction ratio for subbasin 'OC2' is 0.201.

NOTE 41743: Initial abstraction ratio for subbasin 'C12' is 0.1998.

NOTE 41743: Initial abstraction ratio for subbasin 'OD1' is 0.2002.

NOTE 41743: Initial abstraction ratio for subbasin 'C13' is 0.2002.

NOTE 41743: Initial abstraction ratio for subbasin 'D' is 0.2007.

WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'D'; reduce simulation time interval.

NOTE 10185: Finished computing simulation run 'Run 1' at time 07Sep2014, 16:02:13.




D DP4
 Meteorologic Models
 Met 1
 SCS Storm
 Control Specifications
 Control 1
 Paired Data
 Elevation-Area Functions
 Elevation-Discharge Functions
 P-B
 P-C

Components Compute Results

Paired Data Table Graph

| Elevation (FT) | Discharge (CFS) |
|----------------|-----------------|
| 7447.0 | 0.00 |
| 7448.0 | 0.80 |
| 7449.0 | 15.90 |
| 7450.0 | 46.40 |
| 7451.0 | 86.30 |
| 7452.0 | 126.70 |
| 7453.0 | 171.10 |
| 7454.0 | 301.50 |
| 7456.0 | 1136.00 |

Basin Model [Basin 1] Current Run [Run 1]



WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'C9'; reduce simulation time interval.
 NOTE 41743: Initial abstraction ratio for subbasin 'OC2' is 0.201.
 NOTE 41743: Initial abstraction ratio for subbasin 'C12' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'OD1' is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin 'C13' is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin 'D' is 0.2007.
 WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'D'; reduce simulation time interval.
 NOTE 10185: Finished computing simulation run 'Run 1' at time 07Sep2014, 16:00:36.
 NOTE 10184: Began computing simulation run 'Run 1' at time 07Sep2014, 16:00:36.
 NOTE 20364: Found no parameter problems in basin model 'Basin 1'.
 NOTE 40049: Found no parameter problems in basin model 'Basin 1'.
 NOTE 41743: Initial abstraction ratio for subbasin 'OA1' is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin 'A9' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'B10' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'B4' is 0.2007.
 NOTE 41743: Initial abstraction ratio for subbasin 'OC1' is 0.2005.
 NOTE 41743: Initial abstraction ratio for subbasin 'OB1' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'C8' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'C4' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'C9' is 0.2002.
 WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin 'C9'; reduce simulation time interval.
 NOTE 41743: Initial abstraction ratio for subbasin 'OC2' is 0.201.
 NOTE 41743: Initial abstraction ratio for subbasin 'C12' is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin 'OD1' is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin 'C13' is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin 'D' is 0.2007.




DP4
 Meteorologic Models
 Met 1
 SCS Storm
 Control Specifications
 Control 1
 Paired Data
 Elevation-Area Functions
 P-C
 Elevation-Discharge Functions

Components Compute Results

Paired Data Table Graph

| Elevation (FT) | Area (AC) |
|----------------|-----------|
| 7447.0 | 1.76 |
| 7448.0 | 1.95 |
| 7449.0 | 2.12 |
| 7450.0 | 2.27 |
| 7451.0 | 2.43 |
| 7452.0 | 2.61 |
| 7453.0 | 3.17 |
| 7454.0 | 3.79 |
| 7456.0 | 5.30 |

Basin Model [Basin 1] Current Run [Run 1]



WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin "C9"; reduce simulation time interval.
 NOTE 41743: Initial abstraction ratio for subbasin "OC2" is 0.201.
 NOTE 41743: Initial abstraction ratio for subbasin "C12" is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin "OD1" is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin "C13" is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin "D" is 0.2007.
 WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin "D"; reduce simulation time interval.
 NOTE 10185: Finished computing simulation run "Run 1" at time 07/Sep/2014, 16:00:36.
 NOTE 10184: Began computing simulation run "Run 1" at time 07/Sep/2014, 16:00:36.
 NOTE 20364: Found no parameter problems in basin model "Basin 1".
 NOTE 40049: Found no parameter problems in basin model "Basin 1".
 NOTE 41743: Initial abstraction ratio for subbasin "OA1" is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin "A9" is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin "B10" is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin "B4" is 0.2007.
 NOTE 41743: Initial abstraction ratio for subbasin "OB1" is 0.2007.
 NOTE 41743: Initial abstraction ratio for subbasin "OC1" is 0.2005.
 NOTE 41743: Initial abstraction ratio for subbasin "C8" is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin "C4" is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin "C9" is 0.2002.
 WARNING 41784: Simulation time interval is greater than 0.29 * lag for subbasin "C9"; reduce simulation time interval.
 NOTE 41743: Initial abstraction ratio for subbasin "OC2" is 0.201.
 NOTE 41743: Initial abstraction ratio for subbasin "C12" is 0.1998.
 NOTE 41743: Initial abstraction ratio for subbasin "OD1" is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin "C13" is 0.2002.
 NOTE 41743: Initial abstraction ratio for subbasin "D" is 0.2007.




HEC-HMS

Project : WALD_DET

Basin Model : Basin 1

Sep 07 16:03:12 MDT 2014



S-YR

Project: WALD_DET Simulation Run: Run 1

Start of Run: 01Jan3000, 01:00 Basin Model: Basin 1
 End of Run: 02Jan3000, 01:30 Meteorologic Model: Met 1
 Compute Time: 07Sep2014, 16:05:27 Control Specifications: Control 1

| Hydrologic Element | Drainage Area (MI ²) | Peak Discharge (CFS) | Time of Peak | Volume (AC-FT) |
|--------------------|----------------------------------|----------------------|------------------|----------------|
| OA1 | 0.3625 | 24.9 | 01Jan3000, 13:21 | 5.3 |
| R-1 | 0.3625 | 24.9 | 01Jan3000, 13:32 | 5.3 |
| A9 | 0.1719 | 88.9 | 01Jan3000, 13:05 | 7.9 |
| DP1 | 0.5344 | 92.1 | 01Jan3000, 13:06 | 13.2 |
| R-2 | 0.5344 | 92.1 | 01Jan3000, 13:14 | 13.2 |
| B10 | 0.1122 | 46.2 | 01Jan3000, 13:11 | 5.2 |
| B4 | 0.0867 | 52.1 | 01Jan3000, 13:06 | 4.7 |
| OB1 | 0.0553 | 33.6 | 01Jan3000, 13:06 | 3.0 |
| B | 0.7886 | 82.3 | 01Jan3000, 13:36 | 23.5 |
| DP2 | 0.7886 | 82.3 | 01Jan3000, 13:36 | 23.5 |
| R3 | 0.7886 | 82.3 | 01Jan3000, 13:49 | 23.3 |
| OC1 | 0.2016 | 137.0 | 01Jan3000, 13:03 | 10.6 |
| C8 | 0.0927 | 33.6 | 01Jan3000, 13:14 | 4.3 |
| C | 0.0927 | 14.5 | 01Jan3000, 13:40 | 3.4 |
| C4 | 0.0630 | 30.5 | 01Jan3000, 13:07 | 2.9 |
| C9 | 0.0070 | 1.3 | 01Jan3000, 12:58 | 0.1 |
| DP3 | 1.1529 | 175.2 | 01Jan3000, 13:03 | 40.3 |
| R-4 | 1.1529 | 175.2 | 01Jan3000, 13:18 | 40.1 |
| OC2 | 0.1277 | 72.3 | 01Jan3000, 13:03 | 5.7 |
| C12 | 0.0413 | 21.3 | 01Jan3000, 13:05 | 1.9 |
| OD1 | 0.0377 | 2.9 | 01Jan3000, 13:16 | 0.5 |
| R-D | 0.0377 | 2.9 | 01Jan3000, 13:18 | 0.5 |
| C13 | 0.0350 | 4.1 | 01Jan3000, 13:06 | 0.5 |
| D | 0.0160 | 14.6 | 01Jan3000, 12:56 | 0.9 |
| DP4 | 1.4106 | 213.5 | 01Jan3000, 13:17 | 49.7 |

Project: WALD_DET
Simulation Run: Run 1 Reservoir: B



| | | | |
|---------------|---------------------|-------------------------|-----------|
| Start of Run: | 01Jan3000, 01:00 | Basin Model: | Basin 1 |
| End of Run: | 02Jan3000, 01:30 | Meteorologic Model: | Met 1 |
| Compute Time: | 07Sep2014, 16:05:27 | Control Specifications: | Control 1 |

Volume Units: AC-FT

Computed Results

| | | | |
|-----------------|--------------|-----------------------------|------------------|
| Peak Inflow : | 208.1 (CFS) | Date/Time of Peak Inflow : | 01Jan3000, 13:11 |
| Peak Outflow : | 82.3 (CFS) | Date/Time of Peak Outflow : | 01Jan3000, 13:36 |
| Total Inflow : | 26.1 (AC-FT) | Peak Storage : | 8.2 (AC-FT) |
| Total Outflow : | 23.5 (AC-FT) | Peak Elevation : | 7450.9 (FT) |

Reservoir "B" Results for Run "Run 1"



- Run:Run 1 Element:B Result:Storage
- Run:Run 1 Element:B Result:Pool Elevation
- Run:Run 1 Element:B Result:Outflow
- Run:Run 1 Element:B Result:Combined Flow
- Run:Run 1 Element:B Result:Stage

Project: WALD_DET Simulation Run: Run 1

Start of Run: 01Jan3000, 01:00 Basin Model: Basin 1
 End of Run: 02Jan3000, 01:30 Meteorologic Model: Met 1
 Compute Time: 07Sep2014, 16:02:13 Control Specifications: Control 1

| | | | | |
|-----|--------|-------|------------------|-------|
| OA1 | 0.3625 | 169.4 | 01Jan3000, 13:17 | 21.0 |
| R-1 | 0.3625 | 169.4 | 01Jan3000, 13:28 | 21.0 |
| A9 | 0.1719 | 240.1 | 01Jan3000, 13:05 | 18.8 |
| DP1 | 0.5344 | 261.3 | 01Jan3000, 13:06 | 39.8 |
| R-2 | 0.5344 | 261.3 | 01Jan3000, 13:14 | 39.7 |
| B10 | 0.1122 | 125.0 | 01Jan3000, 13:10 | 12.3 |
| B4 | 0.0867 | 129.0 | 01Jan3000, 13:06 | 10.6 |
| OB1 | 0.0553 | 83.2 | 01Jan3000, 13:06 | 6.8 |
| B | 0.7886 | 311.1 | 01Jan3000, 13:36 | 65.6 |
| DP2 | 0.7886 | 311.1 | 01Jan3000, 13:36 | 65.6 |
| R3 | 0.7886 | 311.1 | 01Jan3000, 13:49 | 65.3 |
| OC1 | 0.2016 | 345.7 | 01Jan3000, 13:02 | 24.0 |
| C8 | 0.0927 | 91.0 | 01Jan3000, 13:14 | 10.1 |
| C | 0.0927 | 33.6 | 01Jan3000, 13:42 | 9.2 |
| C4 | 0.0630 | 82.3 | 01Jan3000, 13:06 | 6.9 |
| C9 | 0.0070 | 8.0 | 01Jan3000, 12:55 | 0.4 |
| DP3 | 1.1529 | 459.8 | 01Jan3000, 13:03 | 105.8 |
| R-4 | 1.1529 | 459.8 | 01Jan3000, 13:18 | 105.4 |
| OC2 | 0.1277 | 197.7 | 01Jan3000, 13:02 | 13.7 |
| C12 | 0.0413 | 57.5 | 01Jan3000, 13:05 | 4.5 |
| OD1 | 0.0377 | 20.2 | 01Jan3000, 13:13 | 2.2 |
| R-D | 0.0377 | 20.2 | 01Jan3000, 13:15 | 2.2 |
| C13 | 0.0350 | 27.9 | 01Jan3000, 13:04 | 2.0 |
| D | 0.0160 | 35.8 | 01Jan3000, 12:56 | 2.0 |
| DP4 | 1.4106 | 577.1 | 01Jan3000, 13:17 | 129.9 |

Project: WALD_DET
Simulation Run: Run 1 Reservoir: B


Start of Run: 01Jan3000, 01:00 Basin Model: Basin 1
End of Run: 02Jan3000, 01:30 Meteorologic Model: Met 1
Compute Time: 07Sep2014, 16:02:13 Control Specifications: Control 1

Volume Units: AC-FT

Computed Results

| | | | |
|-----------------|--------------|-----------------------------|------------------|
| Peak Inflow : | 551.7 (CFS) | Date/Time of Peak Inflow : | 01Jan3000, 13:11 |
| Peak Outflow : | 311.1 (CFS) | Date/Time of Peak Outflow : | 01Jan3000, 13:36 |
| Total Inflow : | 69.4 (AC-FT) | Peak Storage : | 17.4 (AC-FT) |
| Total Outflow : | 65.6 (AC-FT) | Peak Elevation : | 7454.0 (FT) |

Reservoir "B" Results for Run "Run 1"



- - - - Run:Run 1 Element:B Result:Storage - · - · - Run:Run 1 Element:B Result:Pool Elevation — Run:Run 1 Element:B Result:Outflow
 - - - - Run:Run 1 Element:B Result:Combined Flow - - - - Run:Run 1 Element:B Result:Stage

APPENDIX B2

HYDROLOGIC CALCULATIONS – RATIONAL METHOD

Determination of Time of Concentration

The time of concentration is the period of time required for stormwater to travel from the most remote point in the basin to the design point. In general, drainageways in an urban area may be composed of overland flow, gully (swale) flow, and channel (gutter) flow. There are many empirical formulas developed for estimating the time of concentration such as Kirpich, Kinematic Wave, Kerby etc.. They indicate that the time of concentration is a function of basin slope, length of waterway, roughness of waterway and rainfall amount. For an urban area, the airport empirical formula is recommended for estimating overland flow time:

* "Airport"

$$T_o = \frac{1.8 (1.1 - C) L_o^{0.5}}{S_o^{0.33}} = \frac{1.8 (1.1 - C) \sqrt{L_o}}{\sqrt[3]{S_o}} \quad (4)$$

in which T_o = overland flow time in minutes, C_5 = runoff coefficient for a 5-year storm, L_o = overland flow length in feet, S_o = overland flow slope in percent.

The U.S. Soil Conservation Service (SCS) upland method is recommended for estimating gully (swale) flow time and channel (gutter) flow time. The SCS upland method classifies the linings of drainageways into six categories. They are: (1) meadow, (2) tillage, (3) lawn, (4) bare soil, (5) grass, and (6) pavement. Flow velocity is approximated by

* "SCS Upland"


$$V = K S^{0.5} \rightarrow T_f = \frac{L_f}{K \sqrt{S} (1.48)} \quad (5)$$

in which V = flow velocity in fps, S = drainageway slope in percent, and K = conveyance coefficient. The values of K for various lining materials are listed as follows: (2 impervious factor)

| Linings | meadow | tillage | lawn | bare soil | grass | pavement |
|------------|--------|---------|------|-----------|-------|----------|
| Value of K | .25 | .45 | .70 | 1.0 | 1.5 | 2.0 |

Applying the SCS upland method to swale and channel flows, we have

Storm Rainfall Time Intensity-Frequency Curves



Rainfall Depth - Duration - Frequency Table derived from Rainfall Atlas III for Colorado
Resource: G.L. James C.Y., (2001) "Urban Storm Water Modeling", Chapter 5: Runoff Prediction
for Small Catchment, published by Auraria Campus Book Company,
University of Colorado at Denver, Denver, Colorado.

TABLE 5-1

RECOMMENDED AVERAGE RUNOFF COEFFICIENTS AND PERCENT IMPERVIOUS

| LAND USE OR SURFACE CHARACTERISTICS | PERCENT IMPERVIOUS | "C" FREQUENCY | | | |
|--|-----------------------|------------------|------|------|------|
| | | 10 | | 100 | |
| | | A&B* | C&D* | A&B* | C&D* |
| Business | | | | | |
| Commercial Areas | 95 | 0.90 | 0.90 | 0.90 | 0.90 |
| Neighborhood Areas | 70 | 0.75 | 0.75 | 0.80 | 0.80 |
| Residential | | | | | |
| 1/8 Acre or less | 65 | 0.60 | 0.70 | 0.70 | 0.80 |
| 1/4 Acre | 40 | 0.50 | 0.60 | 0.60 | 0.70 |
| 1/3 Acre | 30 | 0.40 | 0.50 | 0.55 | 0.60 |
| 1/2 Acre | 25 | 0.35 | 0.45 | 0.45 | 0.55 |
| 1 Acre | 20 | 0.30 | 0.40 | 0.40 | 0.50 |
| Industrial | | | | | |
| Light Areas | 80 | 0.70 | 0.70 | 0.80 | 0.80 |
| Heavy Areas | 90 | 0.80 | 0.80 | 0.90 | 0.90 |
| Parks and Cemeteries | 7 | 0.30 | 0.35 | 0.55 | 0.60 |
| Playgrounds | 13 | 0.30 | 0.35 | 0.60 | 0.65 |
| Railroad Yard Areas | 40 | 0.50 | 0.55 | 0.60 | 0.65 |
| Undeveloped Areas | | | | | |
| Historic Flow Analysis- Greenbelts, Agricultural | 2 | 0.15 | 0.25 | 0.20 | 0.30 |
| Pasture/Meadow | 0 | 0.25 | 0.30 | 0.35 | 0.45 |
| Forest | 0 | 0.10 | 0.15 | 0.15 | 0.20 |
| Exposed Rock | 100 | 0.90 | 0.90 | 0.95 | 0.95 |
| Offsite Flow Analysis (when land use not defined) | 45 | 0.55 | 0.60 | 0.65 | 0.70 |
| Streets | | | | | |
| Paved | 100 | 0.90 | 0.90 | 0.95 | 0.95 |
| Gravel | 80 | 0.80 | 0.80 | 0.85 | 0.85 |
| Drive and Walks | 100 | 0.90 | 0.90 | 0.95 | 0.95 |
| Roofs | 90 | 0.90 | 0.90 | 0.95 | 0.95 |
| Lawns | 0 | 0.25 | 0.30 | 0.35 | 0.45 |

* Hydrologic Soil Group

9/30/90

WALDEN PRESERVE
COMPOSITE RUNOFF COEFFICIENTS

| HISTORIC CONDITIONS | | | | | | | | | | | |
|---------------------|-----------------|-----------|-------|------------------------------|------|-----------|------------------------------|------|------|------------------------------|------------------|
| 5-YEAR C VALUES | | | | | | | | | | | |
| BASIN | TOTAL AREA (AC) | SOIL TYPE | (AC) | SUB-AREA 1 DEVELOPMENT/COVER | C | AREA (AC) | SUB-AREA 2 DEVELOPMENT/COVER | C | (AC) | SUB-AREA 3 DEVELOPMENT/COVER | WEIGHTED C VALUE |
| OA1 | 232 | B | 232 | PASTURE | 0.25 | | | | | | 0.250 |
| A | 105.1 | B | 31.5 | FOREST | 0.1 | 73.6 | PASTURE | 0.25 | | | 0.205 |
| OA1,A | 337.1 | | | | | | | | | | 0.236 |
| OB1 | 35.4 | B | 35.4 | 1/2-AC. LOTS | 0.35 | | | | | | 0.350 |
| B | 118.0 | B | 23.6 | FOREST | 0.1 | 94.4 | PASTURE | 0.25 | | | 0.220 |
| OB1,B | 153.4 | | | | | | | | | | 0.250 |
| OA1,OB1,A,B | 490.5 | | | | | | | | | | 0.240 |
| OC1 | 122.5 | | 122.5 | 1/2-AC. LOTS | 0.35 | | | | | | 0.350 |
| OC2 | 61.4 | | 61.4 | 1/2-AC. LOTS | 0.35 | | | | | | 0.350 |
| C | 190.2 | | 190.2 | FOREST | 0.1 | | | | | | 0.100 |
| OC1,OC2,C | 374.1 | | | | | | | | | | 0.223 |
| OA1-OC1,A-C | 864.6 | | | | | | | | | | 0.233 |
| OD1 | 3.30 | B | 3.30 | 1-AC LOTS | 0.3 | | | | | | 0.300 |
| OD2 | 4.50 | B | 4.50 | FOREST | 0.1 | | | | | | 0.100 |
| OD3 | 10.30 | B | 10.30 | FOREST | 0.1 | | | | | | 0.100 |
| OD4 | 6.00 | B | 6.00 | FOREST | 0.1 | | | | | | 0.100 |
| D | 10.27 | B | 10.27 | FOREST | 0.1 | | | | | | 0.100 |
| OD1-OD4, D | 34.37 | | | | | | | | | | 0.119 |
| OA1-OD1,A-D | 898.9 | | | | | | | | | | 0.228 |
| E | 14.7 | | 14.74 | PASTURE | 0.25 | | | | | | 0.250 |
| F | 7.7 | | 7.71 | PASTURE | 0.25 | | | | | | 0.250 |

| 100-YEAR C VALUES | | | | | | | | | | | | |
|-------------------|-----------------|-----------|-------|------------------------------|------|-----------|------------------------------|------|------|------------------------------|---|------------------|
| BASIN | TOTAL AREA (AC) | SOIL TYPE | (AC) | SUB-AREA 1 DEVELOPMENT/COVER | C | AREA (AC) | SUB-AREA 2 DEVELOPMENT/COVER | C | (AC) | SUB-AREA 3 DEVELOPMENT/COVER | C | WEIGHTED C VALUE |
| OA1 | 232 | B | 232 | PASTURE | 0.35 | | | | | | | 0.350 |
| A | 105.1 | B | 31.5 | FOREST | 0.15 | 73.6 | PASTURE | 0.35 | | | | 0.290 |
| OA1,A | 337.1 | | | | | | | | | | | 0.331 |
| OB1 | 35.4 | B | 35.4 | 1/2-AC. LOTS | 0.45 | | | | | | | 0.450 |
| B | 118.0 | B | 23.6 | FOREST | 0.15 | 94.4 | PASTURE | 0.35 | | | | 0.310 |
| OB1,B | 153.4 | | | | | | | | | | | 0.342 |
| OA1,OB1,A,B | 490.5 | | | | | | | | | | | 0.335 |
| OC1 | 122.5 | | 122.5 | 1/2-AC. LOTS | 0.45 | | | | | | | 0.450 |
| OC2 | 61.4 | | 61.4 | 1/2-AC. LOTS | 0.45 | | | | | | | 0.450 |
| C | 190.2 | | 190.2 | FOREST | 0.15 | | | | | | | 0.150 |
| OC1,OC2,C | 374.1 | | | | | | | | | | | 0.297 |
| OA1-OC1,A-C | 864.6 | | | | | | | | | | | 0.319 |
| OD1 | 3.30 | B | 3.30 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| OD2 | 4.50 | B | 4.50 | FOREST | 0.15 | | | | | | | 0.150 |
| OD3 | 10.30 | B | 10.30 | FOREST | 0.15 | | | | | | | 0.150 |
| OD4 | 6.00 | B | 6.00 | FOREST | 0.15 | | | | | | | 0.150 |
| D | 10.27 | B | 10.27 | FOREST | 0.15 | | | | | | | 0.150 |
| OD1-OD4, D | 34.37 | B | | | | | | | | | | 0.174 |
| OA1-OD1,A-D | 898.9 | | | | | | | | | | | 0.313 |
| E | 14.7 | | 14.74 | PASTURE | 0.35 | | | | | | | 0.350 |
| F | 7.7 | | 7.71 | PASTURE | 0.35 | | | | | | | 0.350 |

WALDEN PRESERVE
RATIONAL METHOD

HISTORIC FLOWS

| BASIN | DESIGN POINT | AREA (AC) | C | | OVERLAND LENGTH (FT) | SLOPE (%) | T _{CO} (MIN) | CHANNEL LENGTH (FT) | CONVEYANCE COEFFICIENT K | SLOPE (%) | SCS VELOCITY (FT/S) | T _t (MIN) | TOTAL T _c (MIN) | INTENSITY ⁽⁵⁾ | | PEAK FLOW Q ₁₀₀ ⁽⁶⁾ (CFS) |
|-------------|--------------|-----------|-----------------------|-------------------------|----------------------|-----------|-----------------------|---------------------|--------------------------|-----------|---------------------|----------------------|----------------------------|--------------------------|----------------|---|
| | | | 5-YEAR ⁽⁷⁾ | 100-YEAR ⁽⁷⁾ | | | | | | | | | | 5-YR (IN/HR) | 100-YR (IN/HR) | |
| OA1 | | 232.0 | 0.250 | 0.350 | 500 | 6.0 | 18.8 | 2900 | 1.50 | 4.1 | 3.04 | 15.9 | 34.8 | 2.22 | 3.96 | 129.00 |
| A | | 105.1 | 0.205 | 0.290 | | | 0.0 | 2650 | 1.50 | 2.45 | 2.35 | 18.8 | 18.8 | 3.11 | 5.53 | 66.97 |
| OA1,A | 1 | 337.1 | 0.236 | 0.331 | | | | | | | | | 53.6 | 1.70 | 3.03 | 135.53 |
| OB1 | | 35.4 | 0.350 | 0.450 | | | 0.0 | 1600 | 1.50 | 4.7 | 3.25 | 8.2 | 8.2 | 4.41 | 7.84 | 54.60 |
| B | | 118.0 | 0.220 | 0.310 | | | 0.0 | 1900 | 1.50 | 2.37 | 2.31 | 13.7 | 13.7 | 3.60 | 6.42 | 93.56 |
| OB1,B | | 153.4 | 0.250 | 0.342 | | | | | | | | | 13.7 | 3.60 | 6.42 | 138.22 |
| OA1,OB1,A,B | 2 | 490.5 | 0.240 | 0.335 | | | | | | | | | 67.3 | 1.47 | 2.61 | 172.87 |
| OC1 | | 122.5 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 151.01 |
| OC2 | | 61.4 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 75.69 |
| C | | 190.2 | 0.100 | 0.150 | | | 0.0 | 5450 | 1.50 | 1.65 | 1.93 | 47.1 | 47.1 | 1.85 | 3.29 | 35.12 |
| OC1,OC2,C | | 374.1 | 0.223 | 0.297 | | | | | | | | | 47.1 | 1.85 | 3.29 | 154.08 |
| OA1-OC2A-C | | 864.6 | 0.233 | 0.319 | | | | | | | | | 114.4 | 1.02 | 1.82 | 205.98 |
| OD1 | | 3.30 | 0.30 | 0.40 | 370 | 5.4 | 15.8 | 450 | 1.50 | 4.4 | 3.15 | 2.4 | 18.2 | 3.16 | 5.63 | 3.13 |
| OD2 | | 4.50 | 0.10 | 0.15 | 525 | 8.2 | 20.5 | 0 | | | | 0.0 | 20.5 | 2.98 | 5.30 | 1.34 |
| OD3 | | 10.30 | 0.10 | 0.15 | 700 | 5.7 | 26.7 | 580 | 1.50 | 3.1 | 2.64 | 3.7 | 30.3 | 2.41 | 4.28 | 2.48 |
| OD4 | | 6.00 | 0.10 | 0.15 | 630 | 5.6 | 25.5 | 340 | 1.50 | 0.9 | 1.42 | 4.0 | 29.4 | 2.45 | 4.36 | 1.47 |
| D | | 10.27 | 0.10 | 0.15 | | | 0.0 | 750 | 1.50 | 3.5 | 2.81 | 4.5 | 5.0 | 5.10 | 9.09 | 5.24 |
| OD1-OD4, D | 4 | 34.37 | 0.12 | 0.17 | | | | | | | | | 34.8 | 2.22 | 3.96 | 9.17 |
| OA1-OD1,A-D | 3 | 898.9 | 0.228 | 0.313 | | | | | | | | | 114.4 | 1.02 | 1.82 | 209.57 |
| E | | 14.7 | 0.250 | 0.350 | 800 | 4.4 | 26.4 | 0 | | | | 0.0 | 26.4 | 2.60 | 4.63 | 9.58 |
| F | | 7.7 | 0.250 | 0.350 | 1000 | 7.0 | 25.3 | 0 | | | | 0.0 | 25.3 | 2.66 | 4.74 | 5.13 |

1) OVERLAND FLOW T_{CO} = (1.87*(1.1-RUNOFF COEFFICIENT)*(OVERLAND FLOW LENGTH*(0.5)/(SLOPE*(0.333)))

2) SCS VELOCITY = K * ((SLOPE(%))^0.5)

K = 0.25 FOR MEADOW

K = 1.5 FOR GRASS CHANNEL

K = 2.0 FOR PAVEMENT

3) GUTTER/SWALE FLOW, T_{CG} = (GUTTER LENGTH/ SCS VELOCITY) / 60 SEC

4) T_c = T_{CO} + T_{CG}

*** IF TOTAL TIME OF CONCENTRATION IS LESS THAN 5 MINUTES, THEN 5 MINUTES IS USED

5) INTENSITY BASED ON I-D-F CURVE IN EL PASO COUNTY DRAINAGE CRITERIA MANUAL, REVISED BY CITY OF COLORADO SPRINGS 1/1/03

I = (A * P) / B + T_d^{0.5}

5-YEAR VALUES: A = 26.65; P₁ = 1.5 IN (1-HOUR DEPTH); B = 10.0; C = 0.76

100-YEAR VALUES: A = 26.65; P = 2.67 IN (1-HOUR DEPTH); B = 10.0; C = 0.76

6) Q = CIA

7) WEIGHTED AVERAGE C VALUES FOR COMBINED BASINS

WALDEN PRESERVE
COMPOSITE RUNOFF COEFFICIENTS

| DEVELOPED CONDITIONS | | | | | | | | | | | | |
|----------------------|-----------------|-----------|--------|------------------------------|------|-----------|------------------------------|---|------|------------------------------|---|------------------|
| 5-YEAR C VALUES | | | | | | | | | | | | |
| BASIN | TOTAL AREA (AC) | SOIL TYPE | (AC) | SUB-AREA 1 DEVELOPMENT/COVER | C | AREA (AC) | SUB-AREA 2 DEVELOPMENT/COVER | C | (AC) | SUB-AREA 3 DEVELOPMENT/COVER | C | WEIGHTED C VALUE |
| OA1,A1-A9 | 341.96 | B | | | | | | | | | | 0.266 |
| OB1,B1-B4 | 90.90 | B | | | | | | | | | | 0.350 |
| B5 | 4.78 | B | 4.78 | 2.5-AC. LOTS | 0.3 | | | | | | | 0.300 |
| B6 | 7.91 | B | 7.91 | 2.5-AC. LOTS | 0.3 | | | | | | | 0.300 |
| B5,B6 | 12.69 | B | | | | | | | | | | 0.300 |
| B7 | 3.24 | B | 3.24 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| B8 | 28.74 | B | 28.74 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| B5-B8 | 44.67 | B | | | | | | | | | | 0.300 |
| B9 | 10.23 | B | 10.23 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| B10 | 16.90 | B | 16.90 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| B5-B10 | 71.80 | B | 71.17 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| OB1,B1-B10 | 162.70 | B | | | | | | | | | | 0.328 |
| OA1,OB1,A,B | 504.66 | B | | | | | | | | | | 0.286 |
| OC1 | 128.95 | B | 128.95 | 1/2-AC. LOTS | 0.35 | | | | | | | 0.350 |
| C1-C4 | 40.40 | B | 40.4 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C5 | 41.43 | B | 41.43 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C6 | 1.32 | B | 1.32 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C8 | 12.44 | B | 12.44 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C5,C6,C8 | 55.19 | B | | | | | | | | | | 0.300 |
| C9 | 4.50 | B | 4.5 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| OC1,C1-C9 | 229.04 | B | | | | | | | | | | 0.328 |
| OA1-OC1,A1-C9 | 733.70 | B | | | | | | | | | | 0.299 |
| OC2 | 81.72 | B | 81.72 | 1/2-AC. LOTS | 0.35 | | | | | | | 0.350 |
| C10 | 2.86 | B | 2.86 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C11 | 8.63 | B | 8.63 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C10-C11 | 11.49 | B | | | | | | | | | | 0.300 |
| C12 | 17.77 | B | 17.77 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| C10-C12 | 29.26 | B | | | | | | | | | | 0.300 |
| C13 | 22.44 | B | 22.44 | MEADOW | 0.25 | | | | | | | 0.250 |
| OC2,C10-C13 | 133.42 | B | | | | | | | | | | 0.322 |
| OD1 | 3.30 | B | 3.30 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| OD2 | 4.50 | B | 4.50 | FOREST | 0.1 | | | | | | | 0.100 |
| OD3 | 10.30 | B | 10.30 | FOREST | 0.1 | | | | | | | 0.100 |
| OD4 | 6.00 | B | 6.00 | FOREST | 0.1 | | | | | | | 0.100 |
| D | 10.27 | B | 10.27 | 1-AC LOTS | 0.3 | | | | | | | 0.300 |
| OD1-OD4, D | 34.37 | B | | | | | | | | | | 0.179 |
| OA1-OD1,A-D | 901.49 | B | | | | | | | | | | 0.298 |

WALDEN PRESERVE
COMPOSITE RUNOFF COEFFICIENTS

| DEVELOPED CONDITIONS | | | | | | | | | | | | |
|----------------------|-----------------|-----------|--------|------------------------------|------|-----------|------------------------------|---|------|------------------------------|---|------------------|
| 100-YEAR C VALUES | | | | | | | | | | | | |
| BASIN | TOTAL AREA (AC) | SOIL TYPE | (AC) | SUB-AREA 1 DEVELOPMENT/COVER | C | AREA (AC) | SUB-AREA 2 DEVELOPMENT/COVER | C | (AC) | SUB-AREA 3 DEVELOPMENT/COVER | C | WEIGHTED C VALUE |
| OA1,A1-A9 | 341.96 | B | | | | | | | | | | 0.366 |
| OB1,B1-B4 | 90.90 | B | | | | | | | | | | 0.450 |
| B5 | 4.78 | B | 4.78 | 2.5-AC. LOTS | 0.4 | | | | | | | 0.400 |
| B6 | 7.91 | B | 7.91 | 2.5-AC. LOTS | 0.4 | | | | | | | 0.400 |
| B5,B6 | 12.69 | B | | | | | | | | | | 0.400 |
| B7 | 3.24 | B | 3.24 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| B8 | 28.74 | B | 28.74 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| B5-B8 | 44.67 | B | | | | | | | | | | 0.400 |
| B9 | 10.23 | B | 10.23 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| B10 | 16.90 | B | 16.90 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| B5-B10 | 71.80 | B | 71.17 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| OB1,B1-B10 | 162.70 | B | | | | | | | | | | 0.428 |
| OA1,OB1,A,B | 504.66 | B | | | | | | | | | | 0.386 |
| OC1 | 128.95 | B | 128.95 | 1/2-AC. LOTS | 0.45 | | | | | | | 0.450 |
| C1-C4 | 40.40 | B | 40.4 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C5 | 41.43 | B | 41.43 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C6 | 1.32 | B | 1.32 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C8 | 12.44 | B | 12.44 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C5,C6,C8 | 55.19 | B | | | | | | | | | | 0.400 |
| C9 | 4.50 | B | 4.5 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| OC1,C1-C9 | 229.04 | B | | | | | | | | | | 0.428 |
| OA1-OC1,A1-C9 | 733.70 | B | | | | | | | | | | 0.399 |
| OC2 | 81.72 | B | 81.72 | 1/2-AC. LOTS | 0.45 | | | | | | | 0.450 |
| C10 | 2.86 | B | 2.86 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C11 | 8.63 | B | 8.63 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C10-C11 | 11.49 | B | | | | | | | | | | 0.400 |
| C12 | 17.77 | B | 17.77 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| C10-C12 | 29.26 | B | | | | | | | | | | 0.400 |
| C13 | 22.44 | B | 22.44 | MEADOW | 0.35 | | | | | | | 0.350 |
| OC2,C10-C13 | 133.42 | B | | | | | | | | | | 0.422 |
| OD1 | 3.30 | B | 3.30 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| OD2 | 4.50 | B | 4.50 | FOREST | 0.15 | | | | | | | 0.150 |
| OD3 | 10.30 | B | 10.30 | FOREST | 0.15 | | | | | | | 0.150 |
| OD4 | 6.00 | B | 6.00 | FOREST | 0.15 | | | | | | | 0.150 |
| D | 10.27 | B | 10.27 | 1-AC LOTS | 0.4 | | | | | | | 0.400 |
| OD1-OD4, D | 34.37 | B | | | | | | | | | | 0.249 |
| OA1-OD1,A-D | 901.49 | B | | | | | | | | | | 0.397 |

RATIONAL METHOD - DRAINAGE CALCULATIONS
DEVELOPED FLOWS

| BASIN | DESIGN POINT | AREA (AC) | C | | OVERLAND LENGTH (FT) | SLOPE (%) | T _{co} ⁽¹⁾ (MIN) | CHANNEL LENGTH (FT) | CONVEYANCE COEFFICIENT K | SLOPE (%) | SCS ⁽²⁾ VELOCITY (FT/S) | T _i ⁽³⁾ (MIN) | TOTAL T _c ⁽⁴⁾ (MIN) | INTENSITY ⁽⁵⁾ | | | PEAK FLOW | |
|--------------------|--------------|-----------|-----------------------|-------------------------|----------------------|-----------|--------------------------------------|---------------------|--------------------------|-----------|------------------------------------|-------------------------------------|---|--------------------------|----------------|-------------------------------------|---------------------------------------|--|
| | | | 5-YEAR ⁽⁷⁾ | 100-YEAR ⁽⁷⁾ | | | | | | | | | | 5-YR (IN/HR) | 100-YR (IN/HR) | Q ₅ ⁽⁶⁾ (CFS) | Q ₁₀₀ ⁽⁶⁾ (CFS) | |
| OA1_A1-A9 | 1 | 341.96 | 0.266 | 0.366 | | | | | | | | | 55.8 | 1.66 | 2.95 | 150.94 | 369.67 | |
| OB1,B1-B4 | B4 | 90.90 | 0.350 | 0.450 | | | | | | | | | 21.1 | 2.11 | 2.83 | 93.31 | 213.54 | |
| B5 | B5 | 4.78 | 0.300 | 0.400 | 300 | 3.7 | 16.1 | 270 | 1.50 | 5.6 | 3.55 | 1.3 | 17.4 | 3.23 | 5.75 | 4.63 | 10.99 | |
| B6 | B6 | 7.91 | 0.300 | 0.400 | | | 0.0 | 380 | 1.50 | 10.0 | 4.74 | 1.3 | 1.3 | 5.0 | 9.09 | 12.11 | 28.75 | |
| B5,B6 | B6 | 12.69 | 0.300 | 0.400 | | | | | | | | | 18.7 | 3.11 | 5.54 | 11.86 | 28.14 | |
| B7 | B7 | 3.24 | 0.300 | 0.400 | 300 | 6.7 | 13.2 | 150 | 1.50 | 8 | 4.24 | 0.6 | 13.8 | 3.59 | 6.39 | 3.49 | 8.28 | |
| WP2 FILING 4: | | | | | | | | | | | | | | | | | | |
| B8 | B8 | 28.74 | 0.300 | 0.400 | | | 0.0 | 1250 | 1.50 | 4.8 | 3.29 | 6.3 | 6.3 | 4.78 | 8.51 | 41.24 | 97.88 | |
| B5-B8 | B8 | 44.67 | 0.300 | 0.400 | | | | | | | | | 25.1 | 2.68 | 4.76 | 35.87 | 142.84 | |
| B9 | B9 | 10.23 | 0.300 | 0.400 | 300 | 4.7 | 14.9 | 540 | 1.50 | 7.4 | 4.08 | 2.2 | 17.1 | 3.26 | 5.80 | 9.99 | 23.72 | |
| B10 | B10 | 16.90 | 0.300 | 0.400 | | | 0.0 | 600 | 1.50 | 3.3 | 2.72 | 3.7 | 3.7 | 5.10 | 9.09 | 25.88 | 61.42 | |
| B5-B10 | B10 | 71.80 | 0.300 | 0.400 | | | | 1900 | 1.50 | 2.4 | 2.31 | 13.7 | 13.7 | 2.48 | 4.42 | 53.46 | 126.87 | |
| Ti from DP1 to DP2 | | | 0.328 | 0.428 | | | | | | | | | 25.1 | 2.68 | 4.76 | 142.84 | 331.77 | |
| OB1,B1-B10 | | 162.70 | 0.286 | 0.386 | | | | | | | | | 69.5 | 1.50 | 2.65 | 216.50 | 516.22 | |
| OA1,OB1,A,B | 2 | 504.66 | | | | | | | | | | | | | | | | |
| OC1.1 | | 121.57 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 149.86 | 342.97 | |
| OC1.2 | | 7.38 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 9.10 | 20.82 | |
| OC1.1,OC1.2 | OC1 | 128.95 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 158.96 | 363.79 | |
| WP2 FILING 5: | | | | | | | | | | | | | | | | | | |
| C1 | C1 | 11.75 | 0.300 | 0.400 | 300 | 4.0 | 15.7 | 550 | 1.50 | 8.2 | 4.30 | 2.1 | 17.9 | 3.19 | 5.68 | 11.24 | 26.68 | |
| C2 | C2 | 11.02 | 0.300 | 0.400 | | | 0.0 | 820 | 1.50 | 5.5 | 3.52 | 3.9 | 3.9 | 5.10 | 9.09 | 16.88 | 40.05 | |
| C1,C2 | C2 | 22.77 | 0.300 | 0.400 | | | | | | | | | 21.7 | 2.89 | 5.14 | 19.73 | 46.82 | |
| C3 | C3 | 2.04 | 0.300 | 0.400 | 100 | 2.0 | 11.4 | 500 | 1.50 | 3.6 | 2.85 | 2.9 | 14.4 | 3.53 | 6.29 | 2.16 | 5.13 | |
| C4 | C4 | 15.59 | 0.300 | 0.400 | 100 | 2.0 | 11.4 | 900 | 1.50 | 6.9 | 3.94 | 3.8 | 15.2 | 3.44 | 6.12 | 16.08 | 38.15 | |
| C3,C4 | C4A | 17.63 | 0.300 | 0.400 | | | | | | | | | 15.2 | 3.44 | 6.12 | 18.18 | 43.15 | |
| C1-C4 | C4 | 40.40 | 0.300 | 0.400 | | | | | | | | | 21.7 | 2.89 | 5.14 | 35.00 | 83.07 | |
| WP2 FILINGS 6-7: | | | | | | | | | | | | | | | | | | |
| C5 | C5 | 41.43 | 0.300 | 0.400 | 100 | 4.0 | 9.1 | 1800 | 1.50 | 4.6 | 3.22 | 9.3 | 18.4 | 3.14 | 5.59 | 39.06 | 92.89 | |
| C6 | C6 | 1.32 | 0.300 | 0.400 | 100 | 6.0 | 7.9 | 250 | 1.50 | 8 | 4.24 | 1.0 | 8.9 | 4.28 | 7.62 | 1.70 | 4.02 | |
| C8 | C8 | 12.44 | 0.300 | 0.400 | 100 | 8.0 | 7.2 | 1200 | 1.50 | 5.5 | 3.52 | 5.7 | 12.9 | 3.70 | 6.59 | 13.82 | 32.79 | |
| Ti from C5 to C8 | | | | | | | | 550 | 1.50 | 3.6 | 2.85 | 3.2 | 3.2 | | | | | |
| C5,C6,C8 (POND C6) | C8 | 55.19 | 0.300 | 0.400 | | | 0.0 | 360 | 1.50 | 3.6 | 2.85 | 2.1 | 2.1 | 5.10 | 9.09 | 47.95 | 113.80 | |
| C9 | C9 | 4.50 | 0.300 | 0.400 | | | | 2700 | 1.50 | 1.9 | 2.04 | 22.1 | 22.1 | 1.50 | 2.65 | 6.89 | 16.36 | |
| Ti from DP2 to DP3 | | | 0.299 | 0.399 | | | | | | | | | 91.6 | 1.50 | 2.65 | 329.06 | 775.78 | |
| OC1,C1-C9 | 3 | 733.70 | | | | | | | | | | | | | | | | |

| BASIN | DESIGN POINT | AREA (AC) | C | | OVERLAND LENGTH (FT) | SLOPE (%) | T _{co} (MIN) | CHANNEL LENGTH (FT) | CONVEYANCE COEFFICIENT K | SLOPE (%) | SCS ⁽²⁾ VELOCITY (FT/S) | T _t (MIN) | TOTAL T _c (MIN) | INTENSITY ⁽⁶⁾ | | | PEAK FLOW | |
|--------------------|--------------|-----------|-----------------------|-------------------------|----------------------|-----------|-----------------------|---------------------|--------------------------|-----------|------------------------------------|----------------------|----------------------------|--------------------------|----------------|-------------------------------------|---------------------------------------|--|
| | | | 5-YEAR ⁽⁷⁾ | 100-YEAR ⁽⁷⁾ | | | | | | | | | | 5-YR (IN/HR) | 100-YR (IN/HR) | Q ₅ ⁽⁶⁾ (CFS) | Q ₁₀₀ ⁽⁶⁾ (CFS) | |
| OC2.1 | | 62.48 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 77.02 | 176.26 | |
| OC2.2 | | 19.24 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 23.72 | 54.28 | |
| OC2.1,OC2.2 | | 81.72 | 0.350 | 0.450 | | | 0.0 | 2800 | 1.50 | 4.64 | 3.23 | 14.4 | 14.4 | 3.52 | 6.27 | 100.74 | 230.54 | |
| C10 | C10 | 2.86 | 0.300 | 0.400 | 100 | 6.0 | 7.9 | 600 | 1.50 | 4.0 | 3.00 | 3.3 | 11.3 | 3.92 | 6.97 | 3.36 | 7.97 | |
| C11 | | 8.63 | 0.300 | 0.400 | 100 | 6.0 | 7.9 | 600 | 1.50 | 6.7 | 3.88 | 2.6 | 10.5 | 4.03 | 7.16 | 10.42 | 24.73 | |
| Tt from C10 to C11 | | | | | | | | 400 | 1.50 | 2.5 | 2.37 | 2.8 | 2.8 | | | | | |
| C11-C12 | C11 | 11.49 | 0.300 | 0.400 | | | | | | | | | 14.1 | 3.56 | 6.34 | 12.28 | 29.15 | |
| C12 | | 17.77 | 0.300 | 0.400 | 100 | 10.0 | 6.7 | 1300 | 1.50 | 3.1 | 2.64 | 8.2 | 14.9 | 3.47 | 6.18 | 18.52 | 43.95 | |
| C10-C12 | C12 | 29.26 | 0.300 | 0.400 | | | | | | | | | 14.9 | 3.47 | 6.18 | 30.49 | 72.36 | |
| C13 | C13 | 22.44 | 0.250 | 0.350 | 300 | 7.3 | 13.7 | 430 | 1.50 | 8.6 | 4.40 | 1.6 | 15.3 | 3.43 | 6.11 | 19.25 | 47.97 | |
| OC1,OC2,C1-C13 | | 867.12 | 0.323 | 0.423 | | | | | | | | | 106.5 | 1.50 | 2.65 | 420.12 | 972.00 | |
| OD1 | | 3.30 | 0.300 | 0.400 | 370 | 5.4 | 15.8 | 450 | 1.50 | 4.4 | 3.15 | 2.4 | 18.2 | 3.16 | 5.63 | 3.13 | 7.43 | |
| OD2 | | 4.50 | 0.100 | 0.150 | 525 | 8.2 | 20.5 | 0 | | | | 0.0 | 20.5 | 2.98 | 5.30 | 1.34 | 3.58 | |
| OD3 | | 10.30 | 0.100 | 0.150 | 700 | 5.7 | 26.7 | 580 | 1.50 | 3.1 | 2.64 | 3.7 | 30.3 | 2.41 | 4.28 | 2.48 | 6.62 | |
| OD4 | | 6.00 | 0.100 | 0.150 | 630 | 5.6 | 25.5 | 340 | 1.50 | 0.9 | 1.42 | 4.0 | 29.4 | 2.45 | 4.36 | 1.47 | 3.92 | |
| OD1-OD4 | | 24.10 | | | | | | | | | | | 30.3 | 30.3 | | | | |
| D | D | 10.27 | 0.300 | 0.400 | | | 0.0 | 750 | 1.50 | 3.5 | 2.81 | 4.5 | 5.0 | 5.0 | 9.09 | 15.73 | 37.33 | |
| OD1-OD4, D | | 34.37 | 0.179 | 0.249 | | | | | | | | | 34.8 | 2.22 | 3.96 | 13.67 | 33.86 | |
| G1 | G1 | 3.28 | 0.300 | 0.400 | 100 | 6.0 | 7.9 | 300 | 1.50 | 6.7 | 3.88 | 1.3 | 9.2 | 4.23 | 7.53 | 4.16 | 9.88 | |
| Tt from DP3 to DP4 | | | | | | | | 2750 | 1.50 | 1.5 | 1.81 | 25.4 | 25.4 | | | | | |
| OD1-OD1,A-D | 4 | 901.49 | 0.298 | 0.397 | | | | | | | | | 116.9 | 1.50 | 2.65 | 402.97 | 948.41 | |

1) OVERLAND FLOW T_{co} = (1.87*(1-1-RUNOFF COEFFICIENT))^(OVERLAND FLOW LENGTH*(0.5))/(SLOPE^(0.333))

2) SCS VELOCITY = K * ((SLOPE(%))^0.5)

K = 0.70 FOR MEADOW / FOREST

K = 1.0 FOR BARE SOIL

K = 1.5 FOR GRASS CHANNEL

K = 2.0 FOR PAVEMENT

3) GUTTERS/SWALE FLOW, TRAVEL TIME, T_t = (CHANNEL LENGTH/SCS VELOCITY) / 60 SEC

4) T_c = T_{co} + T_t

*** IF TOTAL TIME OF CONCENTRATION IS LESS THAN 5 MINUTES, THEN 5 MINUTES IS USED

5) INTENSITY BASED ON I-D-F CURVE IN EL PASO COUNTY DRAINAGE CRITERIA MANUAL, REVISED BY CITY OF COLORADO SPRINGS 1/1/03

I = (A * P) / B + T_d/C

5-YEAR VALUES: A = 26.66; P1 = 1.5 IN (1-HOUR DEPTH); B = 10.0; C = 0.76

100-YEAR VALUES: A = 26.65; P = 2.67 IN (1-HOUR DEPTH); B = 10.0; C = 0.76

6) Q = CIA

7) WEIGHTED AVERAGE C VALUES FOR COMBINED BASINS

APPENDIX C1

HYDRAULIC CALCULATIONS – OPEN CHANNELS

TABLE 10-4

**MAXIMUM PERMISSIBLE VELOCITIES FOR EARTH CHANNELS WITH
VARIED GRASS LININGS AND SLOPES**

| <u>Channel Slope</u> | <u>Lining</u> | <u>Permissible Mean Channel Velocity *</u> (ft/sec) |
|----------------------|-----------------------------|--|
| 0 - 5% | Sodded grass | 7 |
| | Bermudagrass | 6 |
| | Reed canarygrass | 5 |
| | Tall fescue | 5 |
| | Kentucky bluegrass | 5 |
| | Grass-legume mixture | 4 |
| | Red fescue | 2.5 |
| | Redtop | 2.5 |
| | Sericea lespedeza | 2.5 |
| | Annual lespedeza | 2.5 |
| | Small grains (temporary) | 2.5 |
| | 5 - 10% | Sodded grass |
| Bermudagrass | | 5 |
| Reed canarygrass | | 4 |
| Tall fescue | | 4 |
| Kentucky bluegrass | | 4 |
| Grass-legume mixture | | 3 |
| Greater than 10% | Sodded grass | 5 |
| | Bermudagrass | 4 |
| | Reed canarygrass | 3 |
| | Tall fescue | 3 |
| | Kentucky bluegrass | 3 |

* For highly erodible soils, decrease permissible velocities by 25%.

* Grass lined channels are dependent upon assurances of continuous growth and maintenance of grass.

**ALLOWABLE VELOCITY AND MAXIMUM SHEAR STRESS
Streambank and Shoreland Protection Code 580**

| Type of Treatment | Allowable Shear lb/sq ft | Velocity ft/sec |
|---|--------------------------|------------------------------------|
| Brush Mattresses¹ | | |
| Staked only w/ rock riprap toe (initial) | 0.8 - 4.1 | 5 |
| Staked only w/ rock riprap toe (grown) | 4.0 - 8.0 | 12 |
| Coir Geotextile Roll² | | |
| Roll with coir rope mesh staked only without rock riprap toe | 0.2 - 0.8 | < 5 |
| Roll with Polypropylene rope mesh staked only without rock riprap toe | 0.8 - 3.0 | < 8 |
| Roll with Polypropylene rope mesh staked and with rock riprap toe | 3.0 - 4.0 | < 12 |
| Live Fascine³ | | |
| LF Bundle w/ rock riprap toe | 2.0 - 3.1 | 8 |
| Soils⁴ | | |
| Fine colloidal sand | 0.02-0.03 | 1.5 |
| Sandy loam (noncolloidal) | 0.03-0.04 | 1.75 |
| Alluvial silt (noncolloidal) | 0.045-0.05 | 2 |
| Silty loam (noncolloidal) | 0.045-0.05 | 1.75-2.25 |
| Firm loam | 0.075 | 2.5 |
| Fine gravels | 0.075 | 2.5 |
| Stiff clay | 0.26 | 3-4.5 |
| Alluvial silt (colloidal) | 0.26 | 3.75 |
| Graded loam to cobbles | 0.38 | 3.75 |
| Graded silts to cobbles | 0.43 | 4 |
| Shales and hardpan | 0.67 | 6 |
| Gravel/Cobble⁴ | | |
| 1-inch | 0.33 | 2.5-5 |
| 2-inch | 0.67 | 3-6 |
| 6-inch | 2 | 4-7.5 |
| 12-inch | 4 | 5.5-12 |
| Vegetation⁴ | | |
| Class A turf (ret class) | 3.7 | 6-8 |
| Class B turf (ret class) | 2.1 | 4-7 |
| Class C turf (ret class) | 1 | 3.5 |
| Retardance Class D | 0.6 | Design of roadside channels HEC-15 |
| Retardance Class E | 0.35 | |
| Long native grasses | 1.2-1.7 | 4-6 |
| Short native and bunch grass | 0.7-0.95 | 3-4 |

The complete line of RollMax™ products offers a variety of options for both short-term and permanent erosion control needs. Reference the RollMax Products Chart below to find the right solution for your next project.



RollMax Product Selection Chart

| | TEMPORARY | | | | | | |
|--|--|--|--|--|--|---|--|
| | ERONET | | | | | | BIONET |
| |  |  |  |  |  |  |  |
| | DS75 | DS150 | S75 | S150 | SC150 | C125 | S75BN |
| Longevity | 45 days | 60 days | 12 mo. | 12 mo. | 24 mo. | 36 mo. | 12 mo. |
| Applications | Low Flow Channels 4:1-3:1 Slopes | Moderate Flow Channels 3:1-2:1 Slopes | Low Flow Channels 4:1-3:1 Slopes | Moderate Flow Channels 3:1-2:1 Slopes | Medium Flow Channels 2:1-1:1 Slopes | High-Flow Channels 1:1 and Greater Slopes | Low Flow Channels 4:1-3:1 Slopes |
| Design Permissible Shear Stress lbs/ft ² (Pa) | Unvegetated 1.55 (74) | Unvegetated 1.75 (84) | Unvegetated 1.55 (74) | Unvegetated 1.75 (84) | Unvegetated 2.00 (96) | Unvegetated 2.25 (108) | Unvegetated 1.60 (76) |
| Design Permissible Velocity ft/s (m/s) | Unvegetated 5.00 (1.52) | Unvegetated 6.00 (1.52) | Unvegetated 5.00 (1.2) | Unvegetated 6.00 (1.83) | Unvegetated 8.00 (2.44) | Unvegetated 10.00 (3.05) | Unvegetated 5.00 (1.52) |
| Top Net | Lightweight accelerated photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | Lightweight accelerated photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | Lightweight photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | Lightweight photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | Heavyweight UV-stabilized polypropylene 2.9 lbs/1000 ft ² (1.47 kg/100 m ²) approx wt | Heavyweight UV-stabilized polypropylene 2.9 lbs/1000 ft ² (1.47 kg/100 m ²) approx wt | Leno woven, 100% biodegradable jute fiber 9.30 lbs/1000 ft ² (4.53 kg/100 m ²) approx wt |
| Center Net | N/A | N/A | N/A | N/A | N/A | N/A | N/A |
| Fiber Matrix | Straw fiber 0.50 lbs/yd ² (0.27 kg/m ²) | Straw fiber 0.50 lbs/yd ² (0.27 kg/m ²) | Straw fiber 0.50 lbs/yd ² (0.27 kg/m ²) | Straw fiber 0.50 lbs/yd ² (0.27 kg/m ²) | Straw/coconut matrix 70% Straw 0.35 lbs/yd ² (0.19 kg/m ²) 30% Coconut 0.15 lbs/yd ² (0.08 kg/m ²) | Coconut fiber 0.50 lbs/yd ² (0.27 kg/m ²) | Straw fiber 0.50 lbs/yd ² (0.27 kg/m ²) |
| Bottom Net | N/A | Lightweight accelerated photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | N/A | Lightweight photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | Lightweight photodegradable polypropylene 1.50 lbs/1000 ft ² (0.73 kg/100 m ²) approx wt | Heavyweight UV-stabilized polypropylene 2.9 lbs/1000 ft ² (1.47 kg/100 m ²) approx wt | N/A |
| Thread | Accelerated degradable | Accelerated degradable | Degradable | Degradable | Degradable | UV-stabilized polypropylene | Biodegradable |

WALDEN PRESERVE 2 - FILING NO. 4
DITCH CALCULATION SUMMARY

PROPOSED ROADSIDE DITCHES

| ROADWAY | FROM STA | TO STA | SIDE | PROPOSED SLOPE (%) | SIDE SLOPE (Z) | CHANNEL DEPTH (FT) | FRICTION FACTOR (n) | ROW WIDTH (ft) | BASIN | Q100 FLOW (CFS) | DITCH FLOW % OF BASIN | DITCH FLOW (CFS) | Q100 DEPTH (FT) | Q100 VELOCITY (FT/S) | DITCH LINING |
|------------------|----------|--------|------|--------------------|----------------|--------------------|---------------------|----------------|-------|-----------------|-----------------------|------------------|-----------------|----------------------|--------------|
| PINEHURST CIRCLE | 54+42 | 61+00 | N | 8.00 | 4:1/3:1 | 2.5 | 0.030 | 60 | B9 | 23.7 | 5 | 1.2 | 0.3 | 3.8 | GRASS |
| PINEHURST CIRCLE | 54+42 | 61+00 | S | 8.00 | 4:1/3:1 | 2.5 | 0.030 | 60 | B8 | 97.9 | 5 | 4.9 | 0.5 | 5.5 | GRASS / ECB |
| PINEHURST CIRCLE | 51+40 | 54+42 | W | 4.00 | 4:1/3:1 | 2.5 | 0.030 | 60 | B9 | 23.7 | 85 | 20.1 | 1.0 | 6.0 | GRASS / ECB |
| PINEHURST CIRCLE | 51+40 | 54+42 | E | 4.00 | 4:1/3:1 | 2.5 | 0.030 | 60 | B10 | 61.4 | 5 | 3.1 | 0.5 | 3.8 | GRASS |
| PINEHURST CIRCLE | 49+01 | 51+40 | W | 1.62 | 4:1/3:1 | 2.5 | 0.030 | 60 | B9 | 23.7 | 15 | 3.6 | 0.6 | 2.8 | GRASS |
| PINEHURST CIRCLE | 49+01 | 51+40 | E | 1.62 | 4:1/3:1 | 2.5 | 0.030 | 60 | B10 | 61.4 | 5 | 3.1 | 0.6 | 2.7 | GRASS |
| PINEHURST CIRCLE | 46+93 | 49+01 | W | 3.66 | 4:1/3:1 | 2.5 | 0.030 | 60 | C1 | 30.8 | 15 | 4.6 | 0.6 | 4.0 | GRASS / ECB |
| PINEHURST CIRCLE | 46+93 | 49+01 | E | 3.66 | 4:1/3:1 | 2.5 | 0.030 | 60 | C2 | 42.7 | 5 | 2.1 | 0.4 | 3.3 | GRASS |
| DEBOODT COURT | 10+00 | 10+50 | N | 2.00 | 4:1/3:1 | 2.5 | 0.030 | 60 | B10 | 61.4 | 5 | 3.1 | 0.6 | 2.9 | GRASS |
| DEBOODT COURT | 10+00 | 10+50 | S | 2.00 | 4:1/3:1 | 2.5 | 0.030 | 60 | B8 | 97.9 | 10 | 9.8 | 0.9 | 3.9 | GRASS |
| DEBOODT COURT | 10+50 | 14+67 | N | 1.16 | 4:1/3:1 | 2.5 | 0.030 | 60 | B10 | 61.4 | 5 | 3.1 | 0.6 | 2.4 | GRASS |
| DEBOODT COURT | 10+50 | 14+67 | S | 1.16 | 4:1/3:1 | 2.5 | 0.030 | 60 | B8 | 97.9 | 15 | 14.7 | 1.1 | 3.5 | GRASS |

- 1) Channel flow calculations based on Manning's Equation
- 2) n = 0.03 for grass-lined non-irrigated channels
- 3) Vmax = 4.0 fps for 100-year flows w/ native grass-lined channels (per ECM Table 10-4 & NRCS Companion Document 580-10)
- 4) Vmax = 8.0 fps for 100-year flows w/ Erosion Control Blankets (Tensar Eronet SC150 or equal)

Hydraulic Analysis Report

Project Data

Project Title: Walden-WP2-F4-Roadside-Ditches

Designer: JPS

Project Date: Monday, January 21, 2019

Project Units: U.S. Customary Units

Notes:

Channel Analysis: Pinehurst-5442-6100-N

Notes:

Input Parameters

Channel Type: Triangular

Side Slope 1 (Z1): 4.0000 ft/ft

Side Slope 2 (Z2): 3.0000 ft/ft

Longitudinal Slope: 0.0800 ft/ft

Manning's n: 0.0300

Flow: 1.2000 cfs

Result Parameters

Depth: 0.2988 ft

Area of Flow: 0.3124 ft²

Wetted Perimeter: 2.1767 ft

Hydraulic Radius: 0.1435 ft

Average Velocity: 3.8408 ft/s

Top Width: 2.0914 ft

Froude Number: 1.7512

Critical Depth: 0.3754 ft

Critical Velocity: 2.4332 ft/s

Critical Slope: 0.0237 ft/ft

Critical Top Width: 2.68 ft

Calculated Max Shear Stress: 1.4915 lb/ft²

Calculated Avg Shear Stress: 0.7165 lb/ft²

Channel Analysis: Pinehurst-5442-6100-S

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0800 ft/ft
Manning's n: 0.0300
Flow: 4.9000 cfs

Result Parameters

Depth: 0.5064 ft
Area of Flow: 0.8975 ft²
Wetted Perimeter: 3.6892 ft
Hydraulic Radius: 0.2433 ft
Average Velocity: 5.4597 ft/s
Top Width: 3.5447 ft
Froude Number: 1.9121
Critical Depth: 0.6590 ft
Critical Velocity: 3.2238 ft/s
Critical Slope: 0.0196 ft/ft
Critical Top Width: 4.71 ft
Calculated Max Shear Stress: 2.5279 lb/ft²
Calculated Avg Shear Stress: 1.2144 lb/ft²

Channel Analysis: Pinehurst-5140-5442-W

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0400 ft/ft
Manning's n: 0.0300
Flow: 20.1000 cfs

Result Parameters

Depth: 0.9790 ft
Area of Flow: 3.3548 ft²
Wetted Perimeter: 7.1326 ft
Hydraulic Radius: 0.4703 ft
Average Velocity: 5.9915 ft/s
Top Width: 6.8532 ft
Froude Number: 1.5091
Critical Depth: 1.1590 ft
Critical Velocity: 4.2754 ft/s
Critical Slope: 0.0163 ft/ft
Critical Top Width: 8.28 ft
Calculated Max Shear Stress: 2.4437 lb/ft²
Calculated Avg Shear Stress: 1.1740 lb/ft²

Channel Analysis: Pinehurst-5140-5442-E

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0400 ft/ft
Manning's n: 0.0300
Flow: 3.1000 cfs

Result Parameters

Depth: 0.4857 ft
Area of Flow: 0.8256 ft²
Wetted Perimeter: 3.5384 ft
Hydraulic Radius: 0.2333 ft
Average Velocity: 3.7547 ft/s
Top Width: 3.3998 ft
Froude Number: 1.3427
Critical Depth: 0.5487 ft
Critical Velocity: 2.9418 ft/s
Critical Slope: 0.0209 ft/ft
Critical Top Width: 3.92 ft
Calculated Max Shear Stress: 1.2123 lb/ft²
Calculated Avg Shear Stress: 0.5824 lb/ft²

Channel Analysis: Pinehurst-4901-5140-W

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0162 ft/ft
Manning's n: 0.0300
Flow: 3.6000 cfs

Result Parameters

Depth: 0.6086 ft
Area of Flow: 1.2963 ft²
Wetted Perimeter: 4.4337 ft
Hydraulic Radius: 0.2924 ft
Average Velocity: 2.7772 ft/s
Top Width: 4.2600 ft
Froude Number: 0.8872
Critical Depth: 0.5825 ft
Critical Velocity: 3.0311 ft/s
Critical Slope: 0.0205 ft/ft
Critical Top Width: 4.16 ft
Calculated Max Shear Stress: 0.6152 lb/ft²
Calculated Avg Shear Stress: 0.2955 lb/ft²

Channel Analysis: Pinehurst-4901-5140-E

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0162 ft/ft
Manning's n: 0.0300
Flow: 3.1000 cfs

Result Parameters

Depth: 0.5754 ft
Area of Flow: 1.1587 ft²
Wetted Perimeter: 4.1919 ft
Hydraulic Radius: 0.2764 ft
Average Velocity: 2.6753 ft/s
Top Width: 4.0277 ft
Froude Number: 0.8790
Critical Depth: 0.5487 ft
Critical Velocity: 2.9418 ft/s
Critical Slope: 0.0209 ft/ft
Critical Top Width: 3.92 ft
Calculated Max Shear Stress: 0.5816 lb/ft²
Calculated Avg Shear Stress: 0.2794 lb/ft²

Channel Analysis: Pinehurst-4693-4901-W

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0366 ft/ft
Manning's n: 0.0300
Flow: 4.6000 cfs

Result Parameters

Depth: 0.5726 ft
Area of Flow: 1.1476 ft²
Wetted Perimeter: 4.1717 ft
Hydraulic Radius: 0.2751 ft
Average Velocity: 4.0083 ft/s
Top Width: 4.0083 ft
Froude Number: 1.3201
Critical Depth: 0.6425 ft
Critical Velocity: 3.1834 ft/s
Critical Slope: 0.0198 ft/ft
Critical Top Width: 4.59 ft
Calculated Max Shear Stress: 1.3078 lb/ft²
Calculated Avg Shear Stress: 0.6283 lb/ft²

Channel Analysis: Pinehurst-4693-4901-E

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0366 ft/ft
Manning's n: 0.0300
Flow: 2.1000 cfs

Result Parameters

Depth: 0.4267 ft
Area of Flow: 0.6374 ft²
Wetted Perimeter: 3.1090 ft
Hydraulic Radius: 0.2050 ft
Average Velocity: 3.2948 ft/s
Top Width: 2.9872 ft
Froude Number: 1.2570
Critical Depth: 0.4696 ft
Critical Velocity: 2.7213 ft/s
Critical Slope: 0.0220 ft/ft
Critical Top Width: 3.36 ft
Calculated Max Shear Stress: 0.9746 lb/ft²
Calculated Avg Shear Stress: 0.4682 lb/ft²

Channel Analysis: Deboodt-1000-1050-N

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0200 ft/ft
Manning's n: 0.0300
Flow: 3.1000 cfs

Result Parameters

Depth: 0.5531 ft
Area of Flow: 1.0707 ft²
Wetted Perimeter: 4.0295 ft
Hydraulic Radius: 0.2657 ft
Average Velocity: 2.8953 ft/s
Top Width: 3.8717 ft
Froude Number: 0.9702
Critical Depth: 0.5487 ft
Critical Velocity: 2.9418 ft/s
Critical Slope: 0.0209 ft/ft
Critical Top Width: 3.92 ft
Calculated Max Shear Stress: 0.6903 lb/ft²
Calculated Avg Shear Stress: 0.3316 lb/ft²

Channel Analysis: Deboodt-1000-1050-S

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0200 ft/ft
Manning's n: 0.0300
Flow: 9.8000 cfs

Result Parameters

Depth: 0.8516 ft
Area of Flow: 2.5385 ft²
Wetted Perimeter: 6.2044 ft
Hydraulic Radius: 0.4091 ft
Average Velocity: 3.8606 ft/s
Top Width: 5.9614 ft
Froude Number: 1.0426
Critical Depth: 0.8695 ft
Critical Velocity: 3.7032 ft/s
Critical Slope: 0.0179 ft/ft
Critical Top Width: 6.21 ft
Calculated Max Shear Stress: 1.0628 lb/ft²
Calculated Avg Shear Stress: 0.5106 lb/ft²

Channel Analysis: Deboodt-1050-1467-N

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0120 ft/ft
Manning's n: 0.0300
Flow: 3.1000 cfs

Result Parameters

Depth: 0.6087 ft
Area of Flow: 1.2968 ft²
Wetted Perimeter: 4.4346 ft
Hydraulic Radius: 0.2924 ft
Average Velocity: 2.3905 ft/s
Top Width: 4.2608 ft
Froude Number: 0.7636
Critical Depth: 0.5487 ft
Critical Velocity: 2.9418 ft/s
Critical Slope: 0.0209 ft/ft
Critical Top Width: 3.92 ft
Calculated Max Shear Stress: 0.4558 lb/ft²
Calculated Avg Shear Stress: 0.2190 lb/ft²

Channel Analysis: Deboodt-1050-1467-S

Notes:

Input Parameters

Channel Type: Triangular
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 3.0000 ft/ft
Longitudinal Slope: 0.0120 ft/ft
Manning's n: 0.0300
Flow: 14.7000 cfs

Result Parameters

Depth: 1.0911 ft
Area of Flow: 4.1671 ft²
Wetted Perimeter: 7.9494 ft
Hydraulic Radius: 0.5242 ft
Average Velocity: 3.5277 ft/s
Top Width: 7.6380 ft
Froude Number: 0.8417
Critical Depth: 1.0226 ft
Critical Velocity: 4.0160 ft/s
Critical Slope: 0.0170 ft/ft
Critical Top Width: 7.31 ft
Calculated Max Shear Stress: 0.8170 lb/ft²
Calculated Avg Shear Stress: 0.3925 lb/ft²

WALDEN PRESERVE 2 - FILING NO. 4
 CHANNEL CALCULATIONS
 DEVELOPED FLOWS

PROPOSED CHANNELS

| CHANNEL | DESIGN POINT | PROPOSED SLOPE (%) | BOTTOM WIDTH (B, FT) | SIDE SLOPE (Z) | CHANNEL DEPTH (FT) | FRICTION FACTOR (n) | EASEMENT WIDTH (ft) | Q100 FLOW (CFS) | Q100 DEPTH (FT) | Q100 VELOCITY (FT/S) | CHANNEL LINING |
|---------|--------------|--------------------|----------------------|----------------|--------------------|---------------------|---------------------|-----------------|-----------------|----------------------|----------------|
| B8 | B8 | 4.0 | 8 | 4:1 | 2.0 | 0.030 | 24 | 85.1 | 0.9 | 7.8 | ECB |
| B9 | B9 | 10.0 | 8 | 4:1 | 2.0 | 0.030 | 24 | 23.7 | 0.4 | 7.1 | ECB |
| C2 | C2 | 5.0 | 8 | 4:1 | 2.0 | 0.030 | 24 | 46.8 | 0.6 | 7.0 | ECB |

- 1) Channel flow calculations based on Manning's Equation
- 2) Channel depth includes 1' minimum freeboard
- 3) n = 0.03 for grass-lined non-irrigated channels (minimum)
- 4) n = 0.035 for riprap-lined channels
- 5) Vmax = 5.0 fps for 100-year flows w/ grass-lined channels
- 6) Vmax = 9.0 fps for 100-year flows w/ Erosion Control Blankets (NAG C125 or equal)

Hydraulic Analysis Report

Project Data

Project Title: Walden-WP2-F4-Channels
Designer: JPS
Project Date: Thursday, September 6, 2018
Project Units: U.S. Customary Units
Notes:

Channel Analysis: Channel Analysis-B8

Notes:

Input Parameters

Channel Type: Trapezoidal
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 4.0000 ft/ft
Channel Width: 8.0000 ft
Longitudinal Slope: 0.0400 ft/ft
Manning's n: 0.0300
Flow: 85.1000 cfs

Result Parameters

Depth: 0.9321 ft
Area of Flow: 10.9316 ft²
Wetted Perimeter: 15.6861 ft
Hydraulic Radius: 0.6969 ft
Average Velocity: 7.7848 ft/s
Top Width: 15.4566 ft
Froude Number: 1.6313
Critical Depth: 1.2305 ft
Critical Velocity: 5.3522 ft/s
Critical Slope: 0.0139 ft/ft
Critical Top Width: 17.84 ft
Calculated Max Shear Stress: 2.3265 lb/ft²
Calculated Avg Shear Stress: 1.7395 lb/ft²

Channel Analysis: Channel Analysis-B9

Notes:

Input Parameters

Channel Type: Trapezoidal
Side Slope 1 (Z1): 4.0000 ft/ft
Side Slope 2 (Z2): 4.0000 ft/ft
Channel Width: 8.0000 ft
Longitudinal Slope: 0.1000 ft/ft
Manning's n: 0.0300
Flow: 23.7000 cfs

Result Parameters

Depth: 0.3544 ft
Area of Flow: 3.3377 ft²
Wetted Perimeter: 10.9226 ft
Hydraulic Radius: 0.3056 ft
Average Velocity: 7.1006 ft/s
Top Width: 10.8353 ft
Froude Number: 2.2546
Critical Depth: 0.5847 ft
Critical Velocity: 3.9202 ft/s
Critical Slope: 0.0171 ft/ft
Critical Top Width: 12.68 ft
Calculated Max Shear Stress: 2.2115 lb/ft²
Calculated Avg Shear Stress: 1.9068 lb/ft²

Channel Analysis: Channel Analysis-C2

Notes:

Input Parameters

Channel Type: Trapezoidal

Side Slope 1 (Z1): 4.0000 ft/ft

Side Slope 2 (Z2): 4.0000 ft/ft


Channel Width: 8.0000 ft

Longitudinal Slope: 0.0500 ft/ft

Manning's n: 0.0300

Flow: 46.8000 cfs

This does not match the grading. Update and revise the erosion protection if needed.



Result Parameters

Depth: 0.6336 ft

Area of Flow: 6.6742 ft²

Wetted Perimeter: 13.2245 ft

Hydraulic Radius: 0.5047 ft

Average Velocity: 7.0121 ft/s

Top Width: 13.0685 ft

Froude Number: 1.7292

Critical Depth: 0.8752 ft

Critical Velocity: 4.6498 ft/s

Critical Slope: 0.0153 ft/ft

Critical Top Width: 15.00 ft

Calculated Max Shear Stress: 1.9767 lb/ft²

Calculated Avg Shear Stress: 1.5746 lb/ft²

APPENDIX C2

HYDRAULIC CALCULATIONS – CULVERTS

WALDEN PRESERVE 2 FILING NO. 4
 CULVERT DESIGN SUMMARY

| BASIN | DESIGN POINT | RD CL ELEV | INV IN ELEV | INV OUT ELEV | PIPE LENGTH (FT) | # of CULVERTS | PIPE DIA (FT) | TOTAL Q ₅ (CFS) | PER PIPE Q ₅ (CFS) | Q ₅ MAX ALLOWABLE HEADWATER ¹ | CALC Q ₅ HW ELEV | TOTAL Q ₁₀₀ (CFS) | PER PIPE Q ₁₀₀ (CFS) | Q ₁₀₀ MAX ALLOWABLE HEADWATER ² | CALC Q ₁₀₀ HW ELEV |
|-------|--------------|------------|-------------|--------------|------------------|---------------|---------------|----------------------------|-------------------------------|---|-----------------------------|------------------------------|---------------------------------|---|-------------------------------|
| | B8 | 7475.26 | 7469.20 | 7467.00 | 216.0 | 1 | 3.5 | 35.9 | 35.9 | 7472.7 | 7472.0 | 85.1 | 85.10 | 7475.4 | 7475.3 |
| | B9 | 7479.26 | 7475.57 | 7474.78 | 80.0 | 1 | 2.0 | 10.0 | 10.0 | 7477.6 | 7477.2 | 23.7 | 23.70 | 7479.4 | 7478.7 |
| | C1 | 7477.39 | 7473.00 | 7472.18 | 80.0 | 1 | 2.0 | 13.0 | 13.0 | 7475.0 | 7474.9 | 30.8 | 30.80 | 7477.6 | 7477.4 |
| | | | | | | | | | | | | | | | |

¹ Q₅ MAX. ALLOWABLE HEADWATER, HW/D = 1.0

² Q₁₀₀ MAX. ALLOWABLE HEADWATER = 6" DEPTH AT SHOULDER (PER DCM TABLE 6-1)

HY-8 Culvert Analysis Report – Culvert B8

Crossing Discharge Data

Discharge Selection Method: Specify Minimum, Design, and Maximum Flow

Minimum Flow: 15 cfs

Design Flow: 35.9 cfs

Maximum Flow: 85.1 cfs

Table 1 - Summary of Culvert Flows at Crossing: Crossing B8

| Headwater Elevation (ft) | Total Discharge (cfs) | Culvert B8 Discharge (cfs) | Roadway Discharge (cfs) | Iterations |
|--------------------------|-----------------------|----------------------------|-------------------------|-------------|
| 7470.91 | 15.00 | 15.00 | 0.00 | 1 |
| 7471.32 | 22.01 | 22.01 | 0.00 | 1 |
| 7471.67 | 29.02 | 29.02 | 0.00 | 1 |
| 7472.00 | 35.90 | 35.90 | 0.00 | 1 |
| 7472.34 | 43.04 | 43.04 | 0.00 | 1 |
| 7472.71 | 50.05 | 50.05 | 0.00 | 1 |
| 7473.12 | 57.06 | 57.06 | 0.00 | 1 |
| 7473.59 | 64.07 | 64.07 | 0.00 | 1 |
| 7474.11 | 71.08 | 71.08 | 0.00 | 1 |
| 7474.69 | 78.09 | 78.09 | 0.00 | 1 |
| 7475.27 | 85.10 | 84.55 | 0.35 | 38 |
| 7475.26 | 84.42 | 84.42 | 0.00 | Overtopping |

Rating Curve Plot for Crossing: Crossing B8

Total Rating Curve
Crossing: Crossing B8




Table 2 - Culvert Summary Table: Culvert B8

| Total Discharge (cfs) | Culvert Discharge (cfs) | Headwater Elevation (ft) | Inlet Control Depth (ft) | Outlet Control Depth (ft) | Flow Type | Normal Depth (ft) | Critical Depth (ft) | Outlet Depth (ft) | Tailwater Depth (ft) | Outlet Velocity (ft/s) | Tailwater Velocity (ft/s) |
|-----------------------|-------------------------|--------------------------|--------------------------|---------------------------|-----------|-------------------|---------------------|-------------------|----------------------|------------------------|---------------------------|
| 15.00 | 15.00 | 7470.91 | 1.707 | 0.0* | 1-S2n | 0.901 | 1.176 | 0.901 | 0.594 | 7.617 | 3.963 |
| 22.01 | 22.01 | 7471.32 | 2.117 | 0.0* | 1-S2n | 1.097 | 1.434 | 1.097 | 0.723 | 8.500 | 4.415 |
| 29.02 | 29.02 | 7471.67 | 2.471 | 0.0* | 1-S2n | 1.279 | 1.663 | 1.279 | 0.831 | 9.123 | 4.766 |
| 35.90 | 35.90 | 7472.00 | 2.797 | 0.297 | 1-S2n | 1.431 | 1.856 | 1.431 | 0.924 | 9.690 | 5.049 |
| 43.04 | 43.04 | 7472.34 | 3.143 | 0.760 | 1-S2n | 1.589 | 2.039 | 1.598 | 1.010 | 10.057 | 5.302 |
| 50.05 | 50.05 | 7472.71 | 3.511 | 1.253 | 5-S2n | 1.731 | 2.207 | 1.731 | 1.086 | 10.547 | 5.520 |
| 57.06 | 57.06 | 7473.12 | 3.923 | 1.783 | 5-S2n | 1.874 | 2.363 | 1.901 | 1.157 | 10.686 | 5.716 |
| 64.07 | 64.07 | 7473.59 | 4.388 | 2.348 | 5-S2n | 2.015 | 2.506 | 2.042 | 1.223 | 11.004 | 5.895 |
| 71.08 | 71.08 | 7474.11 | 4.909 | 3.382 | 5-S2n | 2.156 | 2.638 | 2.185 | 1.284 | 11.259 | 6.058 |
| 78.09 | 78.09 | 7474.69 | 5.489 | 3.963 | 5-S2n | 2.302 | 2.760 | 2.314 | 1.342 | 11.580 | 6.210 |
| 85.10 | 84.55 | 7475.27 | 6.071 | 4.536 | 5-S2n | 2.441 | 2.862 | 2.453 | 1.397 | 11.752 | 6.351 |


* Full Flow Headwater elevation is below inlet invert.

Straight Culvert

Inlet Elevation (invert): 7469.20 ft, Outlet Elevation (invert): 7467.00 ft


Culvert Length: 216.01 ft, Culvert Slope: 0.0102

Culvert Performance Curve Plot: Culvert B8



Water Surface Profile Plot for Culvert: Culvert B8

Crossing - Crossing B8, Design Discharge - 35.9 cfs
Culvert - Culvert B8, Culvert Discharge - 35.9 cfs



S

Inlet Station: 0.00 ft

Inlet Elevation: 7469.20 ft

Outlet Station: 216.00 ft

Outlet Elevation: 7467.00 ft

Number of Barrels: 1

Culvert Data Summary - Culvert B8

Barrel Shape: Circular

Barrel Diameter: 3.50 ft

Barrel Material: Concrete

Embedment: 0.00 in

Barrel Manning's n: 0.0130

Culvert Type: Straight

Inlet Configuration: Mitered to Conform to Slope

Inlet Depression: NONE

Table 3 - Downstream Channel Rating Curve (Crossing: Crossing B8)

| Flow (cfs) | Water Surface Elev (ft) | Depth (ft) | Velocity (ft/s) | Shear (psf) | Froude Number |
|------------|-------------------------|------------|-----------------|-------------|---------------|
| 15.00 | 7467.59 | 0.59 | 3.96 | 0.74 | 1.06 |
| 22.01 | 7467.72 | 0.72 | 4.41 | 0.90 | 1.09 |
| 29.02 | 7467.83 | 0.83 | 4.77 | 1.04 | 1.11 |
| 35.90 | 7467.92 | 0.92 | 5.05 | 1.15 | 1.13 |
| 43.04 | 7468.01 | 1.01 | 5.30 | 1.26 | 1.14 |
| 50.05 | 7468.09 | 1.09 | 5.52 | 1.36 | 1.15 |
| 57.06 | 7468.16 | 1.16 | 5.72 | 1.44 | 1.16 |
| 64.07 | 7468.22 | 1.22 | 5.89 | 1.53 | 1.17 |
| 71.08 | 7468.28 | 1.28 | 6.06 | 1.60 | 1.18 |
| 78.09 | 7468.34 | 1.34 | 6.21 | 1.68 | 1.18 |
| 85.10 | 7468.40 | 1.40 | 6.35 | 1.74 | 1.19 |

Tailwater Channel Data - Crossing B8

Tailwater Channel Option: Trapezoidal Channel

Bottom Width: 4.00 ft

Side Slope (H:V): 4.00 (1:1)

Channel Slope: 0.0200

Channel Manning's n: 0.0300

Channel Invert Elevation: 7467.00 ft

Roadway Data for Crossing: Crossing B8

Roadway Profile Shape: Constant Roadway Elevation

Crest Length: 100.00 ft

Crest Elevation: 7475.26 ft

Roadway Surface: Paved

Roadway Top Width: 160.00 ft

HY-8 Culvert Analysis Report – Culvert B9

Crossing Discharge Data

Discharge Selection Method: Specify Minimum, Design, and Maximum Flow

Minimum Flow: 5 cfs

Design Flow: 10 cfs

Maximum Flow: 23.7 cfs

Table 1 - Summary of Culvert Flows at Crossing: Crossing B9

| Headwater Elevation (ft) | Total Discharge (cfs) | Culvert B9 Discharge (cfs) | Roadway Discharge (cfs) | Iterations |
|--------------------------|-----------------------|----------------------------|-------------------------|-------------|
| 7476.66 | 5.00 | 5.00 | 0.00 | 1 |
| 7476.88 | 6.87 | 6.87 | 0.00 | 1 |
| 7477.08 | 8.74 | 8.74 | 0.00 | 1 |
| 7477.20 | 10.00 | 10.00 | 0.00 | 1 |
| 7477.43 | 12.48 | 12.48 | 0.00 | 1 |
| 7477.60 | 14.35 | 14.35 | 0.00 | 1 |
| 7477.79 | 16.22 | 16.22 | 0.00 | 1 |
| 7477.99 | 18.09 | 18.09 | 0.00 | 1 |
| 7478.22 | 19.96 | 19.96 | 0.00 | 1 |
| 7478.46 | 21.83 | 21.83 | 0.00 | 1 |
| 7478.74 | 23.70 | 23.70 | 0.00 | 1 |
| 7479.26 | 26.90 | 26.90 | 0.00 | Overtopping |

Rating Curve Plot for Crossing: Crossing B9

Total Rating Curve

Crossing: Crossing B9




Table 2 - Culvert Summary Table: Culvert B9

| Total Discharge (cfs) | Culvert Discharge (cfs) | Headwater Elevation (ft) | Inlet Control Depth (ft) | Outlet Control Depth (ft) | Flow Type | Normal Depth (ft) | Critical Depth (ft) | Outlet Depth (ft) | Tailwater Depth (ft) | Outlet Velocity (ft/s) | Tailwater Velocity (ft/s) |
|-----------------------|-------------------------|--------------------------|--------------------------|---------------------------|-----------|-------------------|---------------------|-------------------|----------------------|------------------------|---------------------------|
| 5.00 | 5.00 | 7476.66 | 1.087 | 0.0* | 1-S2n | 0.624 | 0.783 | 0.624 | 0.329 | 5.769 | 2.858 |
| 6.87 | 6.87 | 7476.88 | 1.311 | 0.302 | 1-S2n | 0.738 | 0.930 | 0.738 | 0.392 | 6.301 | 3.151 |
| 8.74 | 8.74 | 7477.08 | 1.506 | 0.526 | 1-S2n | 0.842 | 1.053 | 0.871 | 0.446 | 6.435 | 3.387 |
| 10.00 | 10.00 | 7477.20 | 1.627 | 0.0* | 1-S2n | 0.909 | 1.126 | 0.939 | 0.480 | 6.675 | 3.524 |
| 12.48 | 12.48 | 7477.43 | 1.856 | 1.014 | 1-S2n | 1.036 | 1.268 | 1.072 | 0.539 | 7.044 | 3.759 |
| 14.35 | 14.35 | 7477.60 | 2.033 | 1.280 | 5-S2n | 1.130 | 1.361 | 1.168 | 0.580 | 7.301 | 3.913 |
| 16.22 | 16.22 | 7477.79 | 2.220 | 1.563 | 5-S2n | 1.224 | 1.447 | 1.265 | 0.618 | 7.510 | 4.052 |
| 18.09 | 18.09 | 7477.99 | 2.423 | 2.102 | 5-S2n | 1.322 | 1.530 | 1.366 | 0.654 | 7.688 | 4.179 |
| 19.96 | 19.96 | 7478.22 | 2.647 | 2.383 | 5-S2n | 1.427 | 1.603 | 1.470 | 0.688 | 7.847 | 4.296 |
| 21.83 | 21.83 | 7478.46 | 2.895 | 2.685 | 5-S2n | 1.546 | 1.668 | 1.591 | 0.720 | 7.952 | 4.405 |
| 23.70 | 23.70 | 7478.74 | 3.166 | 2.983 | 7-M2c | 2.000 | 1.726 | 1.726 | 0.751 | 8.221 | 4.507 |


* Full Flow Headwater elevation is below inlet invert.

Straight Culvert

Inlet Elevation (invert): 7475.57 ft, Outlet Elevation (invert): 7474.78 ft

Culvert Length: 80.00 ft, Culvert Slope: 0.0099


Culvert Performance Curve Plot: Culvert B9



Water Surface Profile Plot for Culvert: Culvert B9

Crossing - Crossing B9, Design Discharge - 10.0 cfs

Culvert - Culvert B9, Culvert Discharge - 10.0 cfs



Site Data - Culvert B9

Site Data Option: Culvert Invert Data

Inlet Station: 0.00 ft

Inlet Elevation: 7475.57 ft

Outlet Station: 80.00 ft

Outlet Elevation: 7474.78 ft

Number of Barrels: 1

Culvert Data Summary - Culvert B9

Barrel Shape: Circular

Barrel Diameter: 2.00 ft

Barrel Material:

Embedment: 0.00 in

Barrel Manning's n: 0.0130

Culvert Type: Straight

Inlet Configuration: Grooved End Projecting

Inlet Depression: None

Table 3 - Downstream Channel Rating Curve (Crossing: Crossing B9)

| Flow (cfs) | Water Surface Elev (ft) | Depth (ft) | Velocity (ft/s) | Shear (psf) | Froude Number |
|------------|-------------------------|------------|-----------------|-------------|---------------|
| 5.00 | 7475.11 | 0.33 | 2.86 | 0.41 | 0.98 |
| 6.87 | 7475.17 | 0.39 | 3.15 | 0.49 | 1.00 |
| 8.74 | 7475.23 | 0.45 | 3.39 | 0.56 | 1.02 |
| 10.00 | 7475.26 | 0.48 | 3.52 | 0.60 | 1.03 |
| 12.48 | 7475.32 | 0.54 | 3.76 | 0.67 | 1.05 |
| 14.35 | 7475.36 | 0.58 | 3.91 | 0.72 | 1.06 |
| 16.22 | 7475.40 | 0.62 | 4.05 | 0.77 | 1.07 |
| 18.09 | 7475.43 | 0.65 | 4.18 | 0.82 | 1.08 |
| 19.96 | 7475.47 | 0.69 | 4.30 | 0.86 | 1.08 |
| 21.83 | 7475.50 | 0.72 | 4.40 | 0.90 | 1.09 |
| 23.70 | 7475.53 | 0.75 | 4.51 | 0.94 | 1.10 |

Tailwater Channel Data - Crossing B9

Tailwater Channel Option: Trapezoidal Channel

Bottom Width: 4.00 ft

Side Slope (H:V): 4.00 (_:1)

Channel Slope: 0.0200

Channel Manning's n: 0.0300

Channel Invert Elevation: 7474.78 ft

Roadway Data for Crossing: Crossing B9

Roadway Profile Shape: Constant Roadway Elevation

Crest Length: 100.00 ft

Crest Elevation: 7479.26 ft

Roadway Surface: Paved

Roadway Top Width: 32.00 ft

HY-8 Culvert Analysis Report – Culvert C1

Crossing Discharge Data

Discharge Selection Method: Specify Minimum, Design, and Maximum Flow

Minimum Flow: 5 cfs

Design Flow: 13 cfs

Maximum Flow: 30.8 cfs

Table 4 - Summary of Culvert Flows at Crossing: Crossing C1

| Headwater Elevation (ft) | Total Discharge (cfs) | Culvert C1 Discharge (cfs) | Roadway Discharge (cfs) | Iterations |
|--------------------------|-----------------------|----------------------------|-------------------------|-------------|
| 7474.09 | 5.00 | 5.00 | 0.00 | 1 |
| 7474.39 | 7.58 | 7.58 | 0.00 | 1 |
| 7474.64 | 10.16 | 10.16 | 0.00 | 1 |
| 7474.88 | 12.74 | 12.74 | 0.00 | 1 |
| 7474.90 | 13.00 | 13.00 | 0.00 | 1 |
| 7475.40 | 17.90 | 17.90 | 0.00 | 1 |
| 7475.71 | 20.48 | 20.48 | 0.00 | 1 |
| 7476.07 | 23.06 | 23.06 | 0.00 | 1 |
| 7476.47 | 25.64 | 25.64 | 0.00 | 1 |
| 7476.93 | 28.22 | 28.22 | 0.00 | 1 |
| 7477.42 | 30.80 | 30.80 | 0.00 | 1 |
| 7477.65 | 31.89 | 31.89 | 0.00 | Overtopping |

Rating Curve Plot for Crossing: Crossing C1

Total Rating Curve
Crossing: Crossing C1




Table 5 - Culvert Summary Table: Culvert C1

| Total Discharge (cfs) | Culvert Discharge (cfs) | Headwater Elevation (ft) | Inlet Control Depth (ft) | Outlet Control Depth (ft) | Flow Type | Normal Depth (ft) | Critical Depth (ft) | Outlet Depth (ft) | Tailwater Depth (ft) | Outlet Velocity (ft/s) | Tailwater Velocity (ft/s) |
|-----------------------|-------------------------|--------------------------|--------------------------|---------------------------|-----------|-------------------|---------------------|-------------------|----------------------|------------------------|---------------------------|
| 5.00 | 5.00 | 7474.09 | 1.086 | 0.0* | 1-S2n | 0.629 | 0.783 | 0.637 | 0.268 | 5.779 | 2.638 |
| 7.58 | 7.58 | 7474.39 | 1.388 | 0.357 | 1-S2n | 0.789 | 0.979 | 0.796 | 0.340 | 6.489 | 3.028 |
| 10.16 | 10.16 | 7474.64 | 1.641 | 0.670 | 1-S2n | 0.931 | 1.135 | 0.939 | 0.401 | 7.020 | 3.330 |
| 12.74 | 12.74 | 7474.88 | 1.880 | 1.020 | 1-S2n | 1.064 | 1.281 | 1.074 | 0.455 | 7.415 | 3.579 |
| 13.00 | 13.00 | 7474.90 | 1.904 | 0.0* | 1-S2n | 1.077 | 1.294 | 1.087 | 0.460 | 7.451 | 3.601 |
| 17.90 | 17.90 | 7475.40 | 2.401 | 2.044 | 5-S2n | 1.331 | 1.522 | 1.338 | 0.549 | 8.024 | 3.976 |
| 20.48 | 20.48 | 7475.71 | 2.713 | 2.435 | 5-S2n | 1.475 | 1.622 | 1.479 | 0.591 | 8.216 | 4.143 |
| 23.06 | 23.06 | 7476.07 | 3.070 | 2.864 | 5-S2n | 1.653 | 1.707 | 1.652 | 0.630 | 8.302 | 4.293 |
| 25.64 | 25.64 | 7476.47 | 3.475 | 3.255 | 7-M2c | 2.000 | 1.777 | 1.777 | 0.667 | 8.691 | 4.431 |
| 28.22 | 28.22 | 7476.93 | 3.927 | 3.840 | 7-M2c | 2.000 | 1.833 | 1.833 | 0.703 | 9.358 | 4.558 |
| 30.80 | 30.80 | 7477.42 | 4.425 | 4.393 | 7-M2c | 2.000 | 1.877 | 1.877 | 0.736 | 10.061 | 4.677 |


* Full Flow Headwater elevation is below inlet invert.

Straight Culvert

Inlet Elevation (invert): 7473.00 ft, Outlet Elevation (invert): 7472.18 ft


Culvert Length: 80.00 ft, Culvert Slope: 0.0102

Culvert Performance Curve Plot: Culvert C1



Water Surface Profile Plot for Culvert: Culvert C1

Crossing - Crossing C1, Design Discharge - 13.0 cfs
Culvert - Culvert C1, Culvert Discharge - 13.0 cfs



S

Inlet Station: 0.00 ft

Inlet Elevation: 7473.00 ft

Outlet Station: 80.00 ft

Outlet Elevation: 7472.18 ft

Number of Barrels: 1

Culvert Data Summary - Culvert C1

Barrel Shape: Circular

Barrel Diameter: 2.00 ft

Barrel Material: Concrete

Embedment: 0.00 in

Barrel Manning's n: 0.0130

Culvert Type: Straight

Inlet Configuration: Grooved End Projecting

Inlet Depression: NONE

Table 6 - Downstream Channel Rating Curve (Crossing: Crossing C1)

| Flow (cfs) | Water Surface Elev (ft) | Depth (ft) | Velocity (ft/s) | Shear (psf) | Froude Number |
|------------|-------------------------|------------|-----------------|-------------|---------------|
| 5.00 | 7472.63 | 0.27 | 2.64 | 0.33 | 0.96 |
| 7.58 | 7472.70 | 0.34 | 3.03 | 0.42 | 1.00 |
| 10.16 | 7472.76 | 0.40 | 3.33 | 0.50 | 1.02 |
| 12.74 | 7472.82 | 0.46 | 3.58 | 0.57 | 1.04 |
| 13.00 | 7472.82 | 0.46 | 3.60 | 0.57 | 1.04 |
| 17.90 | 7472.91 | 0.55 | 3.98 | 0.69 | 1.06 |
| 20.48 | 7472.95 | 0.59 | 4.14 | 0.74 | 1.08 |
| 23.06 | 7472.99 | 0.63 | 4.29 | 0.79 | 1.08 |
| 25.64 | 7473.03 | 0.67 | 4.43 | 0.83 | 1.09 |
| 28.22 | 7473.06 | 0.70 | 4.56 | 0.88 | 1.10 |
| 30.80 | 7473.10 | 0.74 | 4.68 | 0.92 | 1.11 |

Tailwater Channel Data - Crossing C1

Tailwater Channel Option: Trapezoidal Channel

Bottom Width: 6.00 ft

Side Slope (H:V): 4.00 (_:1)

Channel Slope: 0.0200

Channel Manning's n: 0.0300

Channel Invert Elevation: 7472.36 ft

Roadway Data for Crossing: Crossing C1

Roadway Profile Shape: Constant Roadway Elevation

Crest Length: 200.00 ft

Crest Elevation: 7477.65 ft

Roadway Surface: Paved

Roadway Top Width: 32.00 ft

Culvert B8


$$Q_{100} = 85.1 \text{ cfs}$$

$$\Delta = 3.5'$$

$$\frac{Q}{\Delta^{1.5}} = \frac{85.1}{(3.5)^{1.5}} = 13.0$$

$$Y_t = 1.4'$$

$$\frac{Y_t}{\Delta} = \frac{1.4}{3.5} = 0.4$$



Use D_a instead of D whenever flow is supercritical in the barrel.
 ** Use Type L for a distance of $3D$ downstream.

→ Use Type M

FIGURE 5-7. RIPRAP EROSION PROTECTION AT CIRCULAR CONDUIT OUTLET.

Culvert B9


$$Q_{100} = 23.7 \text{ cfs}$$

$$D = 2'$$

$$\frac{Q}{A^{1.5}} = \frac{23.7}{(2)^{1.5}} = 8.4$$

$$Y_t = 0.75'$$

$$\frac{Y_t}{D} = \frac{0.75}{2} = 0.38$$



Use D_0 instead of D whenever flow is supercritical in the barrel.
 ** Use Type L for a distance of $3D$ downstream.

→ Use Type M

FIGURE 5-7. RIPRAP EROSION PROTECTION AT CIRCULAR CONDUIT OUTLET.

Culvert C1


$$Q_{100} = 30.8 \text{ cfs}$$

$$\Delta = 2'$$

$$\frac{Q}{\Delta^{1.5}} = \frac{30.8}{(2)^{1.5}} = 10.9$$

$$Y_t = 0.74'$$

$$\frac{Y_t}{\Delta} = \frac{0.74}{2} = 0.37$$



Use D_0 instead of D whenever flow is supercritical in the barrel.
 ** Use Type L for a distance of $3D$ downstream.

→ Use Type M

FIGURE 5-7. RIPRAP EROSION PROTECTION AT CIRCULAR CONDUIT OUTLET.

**WALDEN PRESERVE 2 - FILING NO. 4
DRIVEWAY CULVERT SUMMARY**

| LOT | DRAINAGE BASIN | Q5 FLOW (CFS) | CULVERT FLOW % OF BASIN | CULVERT FLOW (CFS) | CULVERT SIZE (IN) |
|-----|----------------|---------------|-------------------------|--------------------|-------------------|
| 1 | B8 | 35.9 | 10 | 3.6 | 18" |
| 2 | B8 | 35.9 | 10 | 3.6 | 18" |
| 3 | B8 | 35.9 | 10 | 3.6 | 18" |
| 4 | B8 | 35.9 | 10 | 3.6 | 18" |
| 5 | B8 | 35.9 | 15 | 5.4 | 18" |
| 6 | B8 | 35.9 | 15 | 5.4 | 18" |
| 7 | B8 | 35.9 | 20 | 7.2 | 18" |
| 8 | B8 | 35.9 | 100 | 35.9 | 42" |
| 9 | B8 | 35.9 | 100 | 35.9 | 42" |
| 10 | B8 | 35.9 | 100 | 35.9 | 42" |
| 11 | B10 | 25.9 | 5 | 1.3 | 18" |
| 12 | B10 | 25.9 | 5 | 1.3 | 18" |
| 13 | B10 | 25.9 | 5 | 1.3 | 18" |
| 14 | B10 | 25.9 | 5 | 1.3 | 18" |
| 15 | B10 | 25.9 | 5 | 1.3 | 18" |
| 16 | C2 | 18.0 | 10 | 1.8 | 18" |
| 17 | C1 | 13.0 | 20 | 2.6 | 18" |
| 18 | B9 | 10.0 | 10 | 1.0 | 18" |
| 19 | B9 | 10.0 | 60 | 6.0 | 18" |
| 20 | B9 | 10.0 | 50 | 5.0 | 18" |
| 21 | B9 | 10.0 | 30 | 3.0 | 18" |
| 22 | B9 | 10.0 | 20 | 2.0 | 18" |
| 23 | B9 | 10.0 | 10 | 1.0 | 18" |
| | | | | | |
| | | | | | |

ASSUMPTIONS:

- 1) Driveway Culverts sized based on Max HW/D = 1.5 for Q5 Flows
- 2) Culvert Capacity based on Inlet Control Nomographs (DCM Fig. 9-32)
- 3) Driveway Culverts assumed to be RCP or HDPE

APPENDIX D

WATER QUALITY CALCULATIONS – RAIN GARDEN C2

| WALDEN PRESERVE | | | | | | | | | | |
|------------------------------|-----------------|-----------|-----------|------------------------------|--------|-----------|------------------------------|--------|------------------------------|-----------------------------|
| IMPERVIOUS AREA CALCULATIONS | | | | | | | | | | |
| BASIN | TOTAL AREA (AC) | SOIL TYPE | AREA (AC) | SUB-AREA 1 DEVELOPMENT/COVER | % IMP. | AREA (AC) | SUB-AREA 2 DEVELOPMENT/COVER | % IMP. | SUB-AREA 3 DEVELOPMENT/COVER | WEIGHTED PERCENT IMPERVIOUS |
| OA1,A1-A9 | 341.96 | B | | | | | | | | 6.20 |
| OB1,B1-B4 | 90.90 | B | | | | | | | | 25.00 |
| B5 | 4.78 | B | 4.78 | 2.5-AC. LOTS | 11.0 | | | | | 11.00 |
| B6 | 7.91 | B | 7.91 | 2.5-AC. LOTS | 11.0 | | | | | 11.00 |
| B5,B6 | 12.69 | B | | | | | | | | 11.00 |
| B7 | 3.24 | B | 3.24 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| B8 | 28.74 | B | 28.74 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| B5-B8 | 44.67 | B | | | | | | | | 17.44 |
| B9 | 10.23 | B | 10.23 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| B10 | 16.90 | B | 71.17 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| B5-B10 | 71.80 | B | | | | | | | | 18.41 |
| OB1,B1-B10 | 162.70 | B | | | | | | | | 22.09 |
| OA1,OB1,A,B | 504.66 | B | | | | | | | | 11.32 |
| OC1 | 128.95 | B | 128.95 | 1/2-AC. LOTS | 25.0 | | | | | 25.00 |
| C1 | 11.75 | B | 5.0 | 1-AC. LOTS | 20.0 | 6.8 | 5-AC. LOTS | 7.0 | | 12.53 |
| C2 | 11.02 | B | 11.02 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C1-C2 | 22.77 | B | | | | | | | | 16.15 |
| C3 | 2.04 | B | 2.04 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C4 | 15.59 | B | 15.59 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C1-C4 | 40.40 | B | | | | | | | | 17.83 |
| C5 | 41.43 | B | 41.43 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C6 | 1.32 | B | 1.32 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C8 | 12.44 | B | 12.44 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C5,C6,C8 | 55.19 | B | | | | | | | | 20.00 |
| C9 | 4.50 | B | 4.5 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| OC1,C1-C9 | 229.04 | B | | | | | | | | 22.43 |
| OA1-OC1,A1-C9 | 733.70 | B | | | | | | | | 14.79 |
| OC2 | 81.72 | B | 81.72 | 1/2-AC. LOTS | 25.0 | | | | | 25.00 |
| C10 | 2.86 | B | 2.86 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C11 | 8.63 | B | 8.63 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C12 | 17.77 | B | 17.77 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| C10-C12 | 29.26 | B | | | | | | | | 18.05 |
| C13 | 22.44 | B | 22.44 | MEADOW | 0.0 | | | | | 0.00 |
| OC2,C11-C13 | 133.42 | B | | | | | | | | 19.27 |
| OD1 | 3.30 | B | 3.30 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| OD2 | 4.50 | B | 4.50 | FOREST | 0.0 | | | | | 0.00 |
| OD3 | 10.30 | B | 10.30 | FOREST | 0.0 | | | | | 0.00 |
| OD4 | 6.00 | B | 6.00 | FOREST | 0.0 | | | | | 0.00 |
| D | 10.27 | B | 10.27 | 1-AC LOTS | 20.0 | | | | | 20.00 |
| OD1-OD4, D | 34.37 | B | | | | | | | | 7.90 |
| OA1-OD1,A-D | 901.49 | B | | | | | | | | 15.19 |

Design Procedure Form: Rain Garden (RG)

UD-BMP (Version 3.06, November 2016)

Sheet 1 of 2

Designer: JPS
Company: JPS
Date: April 22, 2019
Project: Walden Preserve 2
Location: Rain Garden C2

| | |
|--|--|
| <p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a (100% if all paved and roofed areas upstream of rain garden)</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a/100$)</p> <p>C) Water Quality Capture Volume (WQCV) for a 12-hour Drain Time ($WQCV = 0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)$)</p> <p>D) Contributing Watershed Area (including rain garden area)</p> <p>E) Water Quality Capture Volume (WQCV) Design Volume $Vol = (WQCV / 12) * Area$</p> <p>F) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> | <p>$I_a =$ <u>16.2</u> %</p> <p>$i =$ <u>0.162</u></p> <p>WQCV = <u>0.08</u> watershed inches</p> <p>Area = <u>993,168</u> sq ft</p> <p>$V_{WQCV} =$ <u>6,555</u> cu ft</p> <p>$d_g =$ _____ in</p> <p>$V_{WQCV\ OTHER} =$ _____ cu ft</p> <p>$V_{WQCV\ USER} =$ _____ cu ft</p> |
| <p>2. Basin Geometry</p> <p>A) WQCV Depth (12-inch maximum)</p> <p>B) Rain Garden Side Slopes ($Z = 4$ min., horiz. dist per unit vertical) (Use "0" if rain garden has vertical walls)</p> <p>C) Minimum Flat Surface Area</p> <p>D) Actual Flat Surface Area</p> <p>E) Area at Design Depth (Top Surface Area)</p> <p>F) Rain Garden Total Volume ($V_T = ((A_{Top} + A_{Actual}) / 2) * Depth$)</p> | <p>$D_{WQCV} =$ <u>12</u> in</p> <p>$Z =$ <u>4.00</u> ft / ft</p> <p>$A_{Min} =$ <u>3218</u> sq ft</p> <p>$A_{Actual} =$ <u>7441</u> sq ft</p> <p>$A_{Top} =$ <u>8882</u> sq ft</p> <p>$V_T =$ <u>8,162</u> cu ft</p> |
| <p>3. Growing Media</p> | <p>Choose One</p> <p><input checked="" type="radio"/> 18" Rain Garden Growing Media</p> <p><input type="radio"/> Other (Explain):</p> <p>_____</p> <p>_____</p> |
| <p>4. Underdrain System</p> <p>A) Are underdrains provided?</p> <p>B) Underdrain system orifice diameter for 12 hour drain time</p> <p style="margin-left: 20px;">i) Distance From Lowest Elevation of the Storage Volume to the Center of the Orifice</p> <p style="margin-left: 20px;">ii) Volume to Drain in 12 Hours</p> <p style="margin-left: 20px;">iii) Orifice Diameter, 3/8" Minimum</p> | <p>Choose One</p> <p><input checked="" type="radio"/> YES</p> <p><input type="radio"/> NO</p> <p>$y =$ <u>2.0</u> ft</p> <p>$Vol_{12} =$ <u>6,555</u> cu ft</p> <p>$D_o =$ <u>1 7/8</u> in</p> |

Design Procedure Form: Rain Garden (RG)

Sheet 2 of 2

Designer: JPS
Company: JPS
Date: April 22, 2019
Project: Walden Preserve 2
Location: Rain Garden C2

| | |
|--|--|
| 5. Impermeable Geomembrane Liner and Geotextile Separator Fabric A) Is an impermeable liner provided due to proximity of structures or groundwater contamination? | Choose One <input type="radio"/> YES <input checked="" type="radio"/> NO |
| 6. Inlet / Outlet Control A) Inlet Control | Choose One <input type="radio"/> Sheet Flow- No Energy Dissipation Required <input checked="" type="radio"/> Concentrated Flow- Energy Dissipation Provided |
| 7. Vegetation | Choose One <input checked="" type="radio"/> Seed (Plan for frequent weed control) <input type="radio"/> Plantings <input type="radio"/> Sand Grown or Other High Infiltration Sod |
| 8. Irrigation A) Will the rain garden be irrigated? | Choose One <input type="radio"/> YES <input type="radio"/> NO |
| Notes: _____ _____ _____ | |

In addition to the UD-BMP, include the UD-Detention worksheet.

APPENDIX E
DRAINAGE COST ESTIMATE


**WALDEN PRESERVE 2 FILING NO. 4
DRAINAGE IMPROVEMENTS COST ESTIMATE**

| Item No. | Description | Quantity | Unit | Unit Cost (\$\$) | Total Cost (\$\$) |
|---|---|----------|------|------------------|-------------------|
| PUBLIC DRAINAGE IMPROVEMENTS (NON-REIMBURSABLE) | | | | | |
| | 24" RCP Culvert | 160 | LF | \$84 | \$13,440 |
| | 24" RCP FES | 4 | EA | \$504 | \$2,016 |
| | Riprap (d ₅₀ = 12") | 10 | CY | \$98 | \$980 |
| | SUBTOTAL | | | | \$16,436 |
| | Contingency @ 15% | | | | \$2,465 |
| | TOTAL | | | | \$18,901 |
| PRIVATE DRAINAGE IMPROVEMENTS (NON-REIMBURSABLE) | | | | | |
| | 15" HDPE Culvert | 56 | LF | \$55 | \$3,080 |
| | 24" HDPE Culvert | 25 | LF | \$84 | \$2,100 |
| | 42" HDPE Culvert | 216 | LF | \$134 | \$28,944 |
| | 15" FES | 1 | EA | \$330 | \$330 |
| | 24" FES | 2 | EA | \$504 | \$1,008 |
| | 42" FES | 2 | EA | \$804 | \$1,608 |
| | Riprap (d ₅₀ = 12") | 15 | CY | \$98 | \$1,470 |
| | Channel Lining (ECB) | 1800 | SY | \$3 | \$5,400 |
| | Rain Garden C2 Outlet Structure | 1 | LS | \$8,000 | \$8,000 |
| | Rain Garden Spillway | 1 | LS | \$6,000 | \$6,000 |
| | SUBTOTAL | | | | \$57,940 |
| | Contingency @ 15% | | | | \$8,691 |
| | TOTAL | | | | \$66,631 |
| | TOTAL DRAINAGE IMPROVEMENTS | | | | \$85,532 |
| | Note: This estimate does not include costs for street improvements (curb & gutter, crosspans, etc.) | | | | |


The cost estimate submitted herein is based on time-honored practices within the construction industry. As such the engineer does not control the cost of labor, materials, equipment or a contractor's method of determining prices and competitive bidding practices or market conditions. The estimate represents our best judgement as design professionals using current information available at the time of the preparation. The engineer cannot guarantee that proposals, bids and/or construction costs will not vary from this cost estimate.

APPENDIX F
FIGURES

j:\jpsprojects\040201.walden\WALDEN PRESERVE 2\DWG\CML\A1.dwg, 8/14/2014 2:51:45 PM



VICINITY MAP




WALDEN PRESERVE

FIGURE A1


JPS PROJ NO. 040201

j:\psprojects\040201.walden\WALDEN PRESERVE 2\DWG\CIVIL\FP-1.dwg Sep 17, 2014 - 9:41am



FIRM PANELS 08041C0285F & 08041C0325F (MARCH 17, 1997)


FLOODPLAIN MAP




WALDEN PRESERVE

FIGURE FP-1

JPS PROJ NO. 040201




- LEGEND**
- FILING LIMITS
 - MAJOR BASIN BOUNDARY
 - EXISTING CONTOUR
 - FLOWLINE
 - DESIGN POINT
 - Qs (cfs)
 - Q100 (cfs)
 - BASIN DESIGNATION
 - BASIN AREA (ACRES)



WALDEN PRESERVE SUBDIVISION

MAJOR BASIN / HISTORIC DRAINAGE PLAN



19 E. Willamette Ave.
Colorado Springs, CO
80903
PH: 719-477-9429
FAX: 719-471-0766
www.jpsegr.com




CALL UTILITY NOTIFICATION
CENTER OF COLORADO
1-800-922-1987
CALL BEFORE YOU DIG. IN ADVANCE
BEFORE YOU DIG, GRADE, OR EXCAVATE
FOR THE MARKING OF UNDERGROUND
MEMBER UTILITIES.


| No. | REVISION | BY | DATE |
|-----|----------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|----------------------|------------------------|
| HORZ. SCALE: 1"=600' | DRAWN: MJP |
| VERT. SCALE: N/A | DESIGNED: JPS |
| SURVEYED: PINNACLE | CHECKED: JPS |
| CREATED: 7/22/02 | LAST MODIFIED: 2/01/19 |
| PROJECT NO: 040201 | MODIFIED BY: BJJ |















SHEET: **EX1**

Z:\040201\walden_dwg\civil\EX1.dwg Feb 01, 2019 - 2:55pm





 300' 0 300' 600'
 ORIGINAL SCALE: 1"=300'
 CONTOUR INTERVAL=5'

LEGEND

-  FILING LIMITS
-  DRAINAGE BASIN BOUNDARY
-  SUB-BASIN BOUNDARY
-  EXISTING CONTOUR
-  PROPOSED CULVERT
-  FLOW DIRECTION ARROW
-  FLOWLINE
-  DESIGN POINT
-  Q_s (cfs)
-  Q_{100} (cfs)
-  DEVELOPED BASIN DESIGNATION
-  BASIN AREA (ACRES)
-  WATERS OF THE U.S.
-  DELINEATED WETLANDS

WALDEN PRESERVE

HISTORIC DRAINAGE PLAN



19 E. Willamette Ave.
 Colorado Springs, CO
 80903
 PH: 719-477-9429
 FAX: 719-471-0766
 www.jpsegr.com



CALL UTILITY NOTIFICATION
 CENTER OF COLORADO
 1-800-922-1987
 BEFORE YOU DIG, GRADE, OR EXCAVATE
 FOR THE MARKING OF UNDERGROUND
 MEMBER UTILITIES

| No. | REVISION | BY | DATE |
|-----|----------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|----------------------|------------------------|
| HORZ. SCALE: 1"=300' | DRAWN: MJP |
| VERT. SCALE: N/A | DESIGNED: JPS |
| SURVEYED: PINNACLE | CHECKED: JPS |
| CREATED: 9/30/11 | LAST MODIFIED: 2/15/19 |
| PROJECT NO: 040201 | MODIFIED BY: BJJ |

SHEET: **EX2**

Z:\040201\walden_dwg\civil\EX2.dwg Feb 15, 2019 - 2:03pm

SUMMARY HYDROLOGY TABLE

| DESIGN POINT | Q5 (CFS) | Q100 (CFS) |
|---------------|----------|------------|
| 1 | 92.1 | 261.3 |
| 2 | 208.0 | 551.4 |
| 3 | 280.7 | 734.2 |
| 4 (DEVELOPED) | 298.7 | 785.0 |
| 4 (DETAINED) | 213.5 | 577.1 |

EXISTING
ELEMENTARY
SCHOOL

WALDEN III
FILING
NO. 5

WALDEN III
FILING
NO. 7

EXISTING
RETENTION POND
B

SHEET D1.01

SHEET D1.02

PROPOSED
WQ RAIN
GARDEN C2

WALDEN III
FILING
NO. 3

PROPOSED
DETENTION
POND C8

WP2
FILING
NO. 6

WALDEN III
FILING
NO. 2

WP2
FILING
NO. 7


WP2
FILING
NO. 5

SHEET D1.03

PROPOSED WQ
POND C4

WALDEN PRESERVE
2 PUD

SHEET D1.04



MONUMENT
ACADEMY
SITE


EAST TRIBUTARY
CHANNEL OF
WEST CHERRY
CREEK

PROPOSED WATER
QUALITY POND C12

KEY MAP

WALDEN PRESERVE

**MASTER DEVELOPMENT
DRAINAGE PLAN**



19 E. Willamette Ave.
Colorado Springs, CO
80903
PH: 719-477-9429
FAX: 719-471-0766
www.jpsegr.com



CALL UTILITY NOTIFICATION
CENTER OF COLORADO
1-800-922-1987
BEFORE YOU DIG, GRADE, OR EXCAVATE
FOR THE MARKING OF UNDERGROUND
MEMBER UTILITIES

| No. | REVISION | BY | DATE |
|-----|----------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|-----------------------|------------------------|
| HORIZ. SCALE: 1"=300' | DRAWN: MJP |
| VERT. SCALE: N/A | DESIGNED: JPS |
| SURVEYED: PINNACLE | CHECKED: JPS |
| CREATED: 10/04/11 | LAST MODIFIED: 5/15/19 |
| PROJECT NO: 040201 | MODIFIED BY: BJJ |

SHEET: **D1**


Z:\040201\walden_dwg\civil\D1.DWG May 16, 2019 - 11:35am

MATCH LINE - SEE SHEET D1.02

PROPOSED WQCV RAIN
GARDEN C2
BOT EL=7440.0
MAX WSL=7441.0
TOP EL=7442.0
WQCV REQ'D=6,555
CF
DSN VOL=8,162 CF


LEGEND

- FILING LIMITS
- DRAINAGE BASIN BOUNDARY
- SUB-BASIN BOUNDARY
- EXISTING CONTOUR
- PROPOSED CULVERT
- FLOW DIRECTION ARROW
- FLOWLINE
- DESIGN POINT
- DEVELOPED BASIN DESIGNATION
- BASIN AREA (ACRES)
- RIPRAP APRON



MATCH LINE - SEE SHEET D1.04

WALDEN PRESERVE



19 E. Willamette Ave.
Colorado Springs, CO
80903
PH: 719-477-9429
FAX: 719-471-0766
www.jpsegr.com




CALL UTILITY NOTIFICATION
CENTER OF COLORADO
1-800-922-1987
CALL BEFORE YOU DIG. IN ADVANCE
BEFORE YOU DIG, GRADE, OR EXCAVATE
FOR THE MARKING OF UNDERGROUND
MEMBER UTILITIES

| NO. | REVISION | BY | DATE |
|-----|----------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

DEVELOPED DRAINAGE & EROSION CONTROL PLAN

SUMMARY HYDROLOGY TABLE

| DESIGN POINT | Q5 (CFS) | Q100 (CFS) |
|--------------|----------|------------|
| B8 | 35.9 | 85.1 |
| B9 | 10.0 | 23.7 |
| B10 | 53.5 | 126.9 |
| C1 | 11.2 | 26.7 |
| C2 | 19.7 | 46.8 |



| | |
|----------------------|------------------------|
| HORZ. SCALE: 1"=100' | DRAWN: BJJ |
| VERT. SCALE: N/A | DESIGNED: JPS |
| SURVEYED: PINNACLE | CHECKED: JPS |
| CREATED: 10/02/13 | LAST MODIFIED: 5/15/19 |
| PROJECT NO: 040201 | MODIFIED BY: BJJ |
| SHEET: | |

D1.03

Z:\040201\walden.dwg\civil\D101-104.dwg May 15, 2019 11:33am