




LSC TRANSPORTATION CONSULTANTS, INC.
2504 East Pikes Peak Avenue, Suite 304
Colorado Springs, CO 80909
(719) 633-2868
FAX (719) 633-5430
E-mail: lsc@lsctrans.com
Website: <http://www.lsctrans.com>

James Irwin Charter Academy
Traffic Impact Study
(LSC #S224370)
PCD File No. COM-2222
September 7, 2022

Traffic Engineer's Statement

This traffic report and supporting information were prepared under my responsible charge and they comport with the standard of care. So far as is consistent with the standard of care, said report was prepared in general conformance with the criteria established by the County for traffic reports.



Developer's Statement

I, the Developer, have read and will comply with all commitments made on my behalf within this report.

Date

James Irwin Charter Academy

Traffic Impact Analysis

Prepared for:

Jeremy Hammers | Project Executive
Elder Construction
4870 Centennial Boulevard, Suite 100
Colorado Springs, CO 80919

SEPTEMBER 7, 2022

LSC Transportation Consultants
Prepared by: Jeffrey C. Hodsdon, P.E.

LSC #S224370

PCD File No. COM-2222



CONTENTS

REPORT CONTENTS	1
SCHOOL LOCATION, ACCESS, AND CIRCULATION	2
Site Location	2
Previous Land Use	3
Site Access Plan	3
EXISTING AND PROJECTED FUTURE STUDENT ENROLLMENT	3
School Enrollment and Operations	3
School Operations	4
SCHOOL BELL AND BUS OPERATIONS	4
AREA PEDESTRIAN AND BICYCLE FACILITIES.....	4
ROADWAY AND TRAFFIC CONDITIONS	4
Study Area	4
Area Roadways	5
ACCESS SIGHT-DISTANCE ANALYSIS.....	6
Existing Traffic Volumes	6
TRIP GENERATION.....	6
Short Term (2023-2024 School Year)	7
Long Term (Maximum Enrollment)	7
Comparison to Previous Land Use.....	8
Short Term	8
Long Term	8
TRIP DISTRIBUTION AND ASSIGNMENT	8
Trip Directional Distribution.....	8
Site-Generated Traffic (Short Term).....	8
Site-Generated Traffic (Long Term).....	9
SHORT-TERM SCENARIO, BASELINE AND TOTAL TRAFFIC.....	9
2042 BACKGROUND TRAFFIC.....	9
2042 TOTAL TRAFFIC.....	10
LEVEL OF SERVICE ANALYSIS.....	10
Powers Boulevard/Waynoka Road.....	10
Waynoka Place/Site Access Points	11

Waynoka Place/North Site Access	11
Waynoka Place/Middle Site Access	11
Waynoka Place/South Site Access	11
Waynoka Road/Waynoka Place	11
Constitution Avenue/Tutt Boulevard/Waynoka Place.....	11
Short Term	12
Long Term	12
Palmer Park Boulevard/Waynoka Road	12
Short Term	12
Long Term	12
Middle Access	13
North Access	14
AUXILIARY TURN-LANE NEED ANALYSIS	14
Powers Boulevard/Waynoka Road.....	14
Waynoka Road at Waynoka Place.....	14
Waynoka Place/North Site Access	15
Waynoka Place/Middle Site Access	15
Waynoka Place/South Site Access	15
Palmer Park Boulevard/Waynoka Road	15
Constitution Avenue/Tutt Boulevard/Waynoka Place.....	15
ON-SITE QUEUING REQUIREMENT (FOR PARENT PICK-UP/DROP-OFF “CAR-LINE”)	16
School On-Site Queueing for Parent Drop-off and Pick-up.....	16
ROADWAY CLASSIFICATIONS	16
CONFORMANCE WITH THE MTCP	17
COUNTY ROAD IMPROVEMENT FEE PROGRAM	17
MULTI-MODAL/TRANSPORTATION DEMAND MANAGEMENT (TDM) OPPORTUNITIES	17
SUMMARY.....	17
Trip Generation	17
Pedestrian and Bicycle Accessibility.....	17
Projected Levels of Service.....	17
Auxiliary Turn-Lane Needs Analysis	18

Enclosures: 18

Table 5

Figure 1 - Figure 15

Traffic Count Reports

Synchro Level of Service Reports

Queuing Reports

MTCP Maps



LSC TRANSPORTATION CONSULTANTS, INC.
2504 East Pikes Peak Avenue, Suite 304
Colorado Springs, CO 80909
(719) 633-2868
FAX (719) 633-5430
E-mail: lsc@lsctrans.com
Website: <http://www.lsctrans.com>

September 7, 2022

Jeremy Hammers | Project Executive
Elder Construction
4870 Centennial Boulevard, Suite 100
Colorado Springs, CO 80919

RE: James Irwin Charter School
Traffic Impact Study
El Paso County, Colorado
PCD File No. COM-2222
LSC #S224370

Dear Mr. Hammers,

LSC Transportation Consultants, Inc. has prepared this traffic impact study (TIS) for the proposed James Irwin Charter School in El Paso County, Colorado. The site is located northeast of the intersection of Powers Boulevard/Waynoka Road at 2460 Waynoka Place (El Paso County parcel ID 5331301024). Access to the site would be to Waynoka Place. No direct access is proposed to Powers Boulevard or Waynoka Road.

This report has been prepared for submittal to El Paso County.

REPORT CONTENTS

- Inventory of the existing adjacent and nearby area road system. This included surface conditions, functional classifications, roadway widths, lane configurations, traffic control, posted speed limits, pavement markings, intersection and access spacing, roadway and intersection alignments, auxiliary left-turn and right-turn lanes, intersection sight distances, etc.;
- Morning, mid-afternoon, and late afternoon peak-hour turning-movement traffic counts at the following "study-area" intersections:
 - Powers Boulevard/Waynoka Road
 - Waynoka Road/Waynoka Place
 - Waynoka Place/all site accesses
 - Constitution Avenue/Tutt Boulevard/Waynoka Place (morning peak only)
 - Palmer Park Road/Waynoka Road
- Review of previously-completed traffic studies in the vicinity of this site for information and findings relative to this development. Other recent studies completed in the area and

any applicable data/transferrable information/analysis etc. from previous LSC studies adjacent to the site were also utilized;

- Evaluation of intersection/access sight distance at the proposed access points based on current criteria in the County's *Engineering Criteria Manual (ECM)*;
- Estimates of average weekday and peak-hour trip generation for the proposed development;
- Estimation of directional distribution of site-generated vehicle trips on the area road system, at the study-area intersections, and at the proposed site-access points.
- Projections of site-generated turning-movement traffic volumes at the following "study-area" intersections:
 - Powers Boulevard/Waynoka Road
 - Waynoka Road/Waynoka Place
 - Waynoka Place/all site accesses
 - Constitution Avenue/Tutt Boulevard/Waynoka Place
 - Palmer Park Road/Waynoka Road
- Estimates of short- and long-term background traffic volumes at the study-area intersections and access points;
- Short-term and long-term total traffic projections at the study-area intersections;
- Level of service (LOS) analysis at the study-area intersections;
- Queuing analysis at the site-access points;
- On-site queue length necessary for parent drop-off/pick-up operations;
- Evaluation of existing, short- and long-term total projected intersection volumes with respect to criteria for auxiliary right-/left-turn lanes on Waynoka Road and Waynoka Place, based on the criteria in the County's *Engineering Criteria Manual*;
- The recommended access plan for the school and recommendations for roadway striping along Waynoka Place north of Waynoka Road;
- Other recommendations and the El Paso County Road Impact Fee Program requirement; and
- Summary of compiled data, analysis, findings, and recommendations.

SCHOOL LOCATION, ACCESS, AND CIRCULATION

Site Location

Figure 1 shows the location of the proposed James Irwin Charter School site relative to the adjacent and nearby streets. The site is in unincorporated El Paso County, adjacent to the city limits of the City of Colorado Springs, Colorado. The site is located at 2460 Waynoka Place (El Paso County parcel ID 5331301024 and is bordered by Powers Boulevard to the west, Waynoka Place to the east, Waynoka Road to the south, and a shopping center to the north. The school campus plan, including buildings, access points, parking areas, and circulation, is shown in Figure 2.

Previous Land Use

The site was originally developed as a large, single-user manufacturing facility. That facility is no longer in operation and existing buildings and parking lots are vacant.

Site Access Plan

Access to the site would be provided via three accesses to Waynoka Place. No direct access would be provided to Powers Boulevard.

- Proposed north access: 588 feet north of Waynoka Place/Waynoka Road (**entrance only** – proposed new access point - recommended by LSC). Only **entering** turning movements will be permitted at the proposed north access, which will be the primary access for parent drop-off/pick-up and student drivers
- Middle access: 375 feet north of Waynoka Place/Waynoka Road (main **exit**, entrance only for buses, visitors, and drop off/pick up of students using inter-school bus service to other James Irwin schools, bus access – existing access to the property).
- South access: 156 feet north of Waynoka Place/Waynoka Road (staff parking lot only – existing access to the property). Staff parking and primarily overflow parking would be served by the south access.

Figure 15 shows the recommended site access and circulation plan. The area is to be used for parent pick-up and drop-off “car line.” The figure also shows a concept for the bus loading and unloading area.

EXISTING AND PROJECTED FUTURE STUDENT ENROLLMENT

School Enrollment and Operations

During the opening school year (2023-2024), James Irwin Charter Academy will serve 359 students. Maximum future enrollment is planned to be about 720 students. Projected enrollment by school year is shown in Table 1, as well as the projected number of buses serving the school and faculty/staff numbers.

Table 1: James Irwin Charter Academy Projected Enrollment, Number of Buses, and Staff

School Year	Student Enrollment	Staff	Buses
2023-2024	359	39	4
2024-2025	395	43	4
2025-2026	489	55	5
2026-2027	525	58	5
2027-2028	574	62	6
2028-2029	623	68	7
Max Enrollment	720	80	8

School Operations

Students in grades 11-12 will generally spend 50-75 percent of their time at the proposed campus in this report, with the remainder of their schedule split between either an internship or at Pikes Peak Community College (PPCC). Each academic classroom will have 25 student desks and one teacher workstation to accommodate 20-25 students at any given time.

Although eligible to enroll at the school, students in grades 13-14 will never attend classes at this proposed campus (studied in this report), as they will attend PPCC full-time. Enrollment numbers for grades 13-14 were not included in Table 1.

SCHOOL BELL AND BUS OPERATIONS

The school day would begin at 7:30 a.m. and end at 2:30 p.m. Buses would transport approximately 100 students from other campuses to the proposed site. Buses would be scheduled to arrive between 7:10 a.m. to 7:15 a.m. and leave between 3:45 p.m. to 4:00 p.m. These buses would also be available for student travel to other campuses.

Unresolved. Explain how the buses will maneuver into the drop site when there are several buses arriving/leaving within a 15 minute window. The drop off site appears to not have enough room for buses to wait and not block access point.

LSC has analyzed the following peak-hour periods to coincide with the arrival/dismissal of students during the school day and the peak hour of adjacent street traffic:

- AM peak hour – 7:00 a.m. to 8:00 a.m.
- Mid-day school peak hour – 2:30 p.m. to 3:30 p.m.
- PM peak hour – 4:00 p.m. to 5:00 p.m.

AREA PEDESTRIAN AND BICYCLE FACILITIES

Sidewalks exist along Waynoka Place, but generally not along Waynoka Road. Sidewalks exist along Constitution Avenue to the north and along Palmer Park Boulevard east of Waynoka.

Future extensions of two major regional trails (Sand Creek Trail and the Rock Island Trail) are planned in close proximity to the site. These future major regional trail connections would provide connectivity to other trails and intersecting roadways (most with sidewalks and some with bicycle lanes).

ROADWAY AND TRAFFIC CONDITIONS

Unresolved. Provide pedestrian routes for the site.

Study Area

The study area is bordered by Constitution Avenue on the north, Palmer Park Boulevard on the south, Powers Boulevard on the west, and a combination of Sand Creek, the Rock Island Trail ROW and the Cherokee Ridge Golf Course on the east. Per the multi-jurisdictional project

meeting, the study-area intersections added include Waynoka/Palmer Park and Constitution/Tutt/Waynoka Place.

Area Roadways

Figure 1 shows the roadways in the vicinity of the site. Major roadways are identified below, followed by a brief description.

Powers Boulevard (State Highway 21) classified by CDOT as a 6-lane F-W: Freeway in the vicinity of the site. Adjacent to the site, Powers has a posted speed limit of 55 miles per hour (mph). No auxiliary turn lanes currently exist at the stop-sign-controlled, right-in/right-out (RIRO) intersection of Powers Boulevard/Waynoka Road. **Note: Pursuant to a recent meeting with CDOT and El Paso County, CDOT will require the permanent closure of the Waynoka Road connection to Powers Boulevard with this project. A cul-de-sac turn-around will be constructed on Waynoka Road just west of Waynoka Place/Waynoka Road intersection.**

Constitution Avenue is shown on the El Paso County *Major Transportation Corridors Plan (MTCP)* as a four-lane Principal Arterial (County portion). Overall, Constitution extends east-to-west between Paseo Road and US Highway (Hwy) 24. The intersection of Constitution Avenue/Tutt Boulevard/Waynoka Place is signalized. This intersection is within the City of Colorado Springs.

Waynoka Road is shown on the *MTCP* as a two-lane Collector (the street is an Urban, Non-Residential Collector). Waynoka Road extends generally north/south for 1.1 miles between Powers Boulevard and Palmer Park Boulevard. The posted speed limit on Waynoka Road is 30 mph. **Note: Pursuant to a recent meeting with CDOT and El Paso County, CDOT will require the permanent closure of the Waynoka Road connection to Powers Boulevard with this project. A cul-de-sac turn-around will be constructed on Waynoka Road just west of Waynoka Place/Waynoka Road intersection.**

Waynoka Place is a local road that extends generally north/south for 0.4 miles between Waynoka Road and Constitution Avenue. No auxiliary turn lanes are striped/mark at the stop-sign-controlled T-intersection of Waynoka Road/Waynoka Place. Much of Waynoka Road and Waynoka Place will likely combine to form portions of the planned future Powers Boulevard frontage Road.

Palmer Park Boulevard extends from west of Union Boulevard east to Shawnee Drive. Classified as a Principal Arterial between Powers Boulevard and Peterson Boulevard, Palmer Park Boulevard has two through lanes in each direction plus a center two-way left-turn lane and a posted speed limit of 35 miles per hour (mph). The intersection of Palmer Park Boulevard/Waynoka Place is a stop sign-controlled, full-movement T-intersection.

ACCESS SIGHT-DISTANCE ANALYSIS

Discuss applicable ECM criteria and design vehicle for site distance calculations.

Both existing site-access points and the proposed north site-access point have been evaluated for intersection and stopping sight distance. Please refer to Figure 3a-c, which show the detailed access sight-distance analysis.

Site improvements (existing-to-remain and proposed new) must not impede sight-distance lines of sight, as the access points will need to meet El Paso County's *Engineering Criteria Manual (ECM)* standards for sight distance.

Existing site landscaping, lower tree branches, bushes, signs, buildings, parking areas, etc. should be removed, if necessary, and new site improvements should not be placed within the *ECM*-required line of sight "triangles."

Existing Traffic Volumes

Existing traffic volumes at the following intersections are shown in Figure 4. Detailed traffic count reports are attached.

- Powers Road/Waynoka Road
 - Thursday, June 9, 2022, from 6:45 – 8:00 a.m.
 - Thursday, June 9, 2022, from 2:30 – 3:30 p.m.
 - Thursday, June 9, 2022, from 4:00 – 6:00 p.m.
- Waynoka Road/Waynoka Place
 - Thursday, June 9, 2022, from 6:45 – 8:00 a.m.
 - Thursday, June 9, 2022, from 2:30 – 3:30 p.m.
 - Thursday, June 9, 2022, from 4:00 – 6:00 p.m.
- Constitution Avenue/Waynoka Place/Tutt Boulevard
 - Tuesday, June 28, 2022, from 6:30 – 8:30 a.m.
- Palmer Park Boulevard/Waynoka Road
 - Tuesday, July 19, 2022, from 6:30 – 8:30 a.m.
 - Tuesday, July 19, 2022, from 1:30 – 3:30 p.m.
 - Tuesday, July 19, 2022, from 4:00 – 6:00 p.m.

TRIP GENERATION

Estimates of the existing and projected vehicle trips to be generated by a site are typically made using the following nationally-published average trip-generation rates in *Trip Generation, 11th Edition, 2021* by the Institute of Transportation Engineers (ITE). LSC used rates for ITE land-use code "538 – Charter School (K-12)" to estimate the school trip generation. LSC has also included a comparison to the trip generation for the previous land use at this site (estimated), for reference.

Short Term (2023-2024 School Year)

Table 2 below presents a summary of the estimated site trip generation for the 2023-2024 school year using ITE rates. The detailed short-term trip-generation estimate for the school is presented in Table 3 (attached).

Table 2: Estimated Site Vehicle-Trip Generation (2023-2024 School Year)

Analysis Period	Weekday		
	In	Out	Total
Morning Peak Hour	179	159	338
Mid-Day Peak Hour	131	131	262
Evening Peak Hour	7	7	14

Based on the ITE estimate for the proposed James Irwin Charter Academy, the site would generate about 785 external vehicle trips on the average weekday during the initial 2023-2024 school year. During the weekday morning peak hour, approximately 179 vehicles would enter and 159 vehicles would exit the site. Approximately 131 entering vehicles and 131 exiting vehicles are projected for the weekday school mid-afternoon peak hour. During the weekday late-afternoon “commuter” peak hour, approximately 7 vehicles would enter and 7 vehicles would exit the site.

Long Term (Maximum Enrollment)

Table 3 below presents a summary of the estimated site trip generation for the maximum enrollment school year using ITE rates. The detailed long-term trip-generation estimate for the school is presented in Table 5 (attached).

Table 3: Estimated Site Vehicle-Trip Generation (Maximum Enrollment School Year)

Analysis Period	Weekday		
	In	Out	Total
Morning Peak Hour	359	318	677
Mid-Day Peak Hour	263	263	526
Evening Peak Hour	13	13	26

Based on the long-term ITE trip estimate for the proposed James Irwin Charter Academy, about 359 vehicles would enter and 318 vehicles would exit the site during the morning peak hour. Approximately 263 entering vehicles and 263 exiting vehicles are projected for the weekday school mid-afternoon peak hour. During the weekday late-afternoon “commuter” peak hour, approximately 13 vehicles would enter and 13 vehicles would exit the site.

Comparison to Previous Land Use

Short Term

During the opening year, compared to the previous land use for the site (an 82,235-square-foot manufacturing building), the proposed James Irwin Charter Academy would generate:

- AM peak hour – 69 additional entering and 144 additional exiting trips
- Mid-day peak hour – 121 additional entering and 82 additional exiting trips
- PM peak hour – 14 fewer entering and 92 fewer exiting trips

Long Term

During the long term, compared to the previous land use for the site (an 82,235-square-foot office building), the proposed James Irwin Charter Academy would generate:

- AM peak hour – 249 additional entering and 303 additional exiting trips
- Mid-day peak hour – 253 additional entering and 214 additional exiting trips
- PM peak hour – 7 fewer entering and 85 fewer exiting trips

TRIP DISTRIBUTION AND ASSIGNMENT

Trip Directional Distribution

Estimating the directional distribution of site-generated vehicle trips to the study-area roads and intersections is a necessary component in determining the site's traffic impacts. Figure 5 shows the percentages of the site-generated vehicle trips projected to be oriented to and from the site's major approaches. Estimates have been based on the following factors: the proposed new land use, the area street and road system serving the site, and the site's geographic location relative to the balance of the City of Colorado Springs and unincorporated areas of El Paso County.

Additionally, the applicant provided a list of zip codes in which currently-enrolled students reside. LSC utilized these data as part of the trip distribution estimate. Please refer to Appendix Figure 1 for more details.

Site-Generated Traffic (Short Term)

Revise to include zip code information since it is not in the appendix.

Figure 6 shows the projected site-generated traffic volumes for the weekday morning and evening peak hours for the short term. Short-term site-generated traffic volumes have been calculated by applying directional-distribution percentages estimated by LSC (from Figure 5) to the short-term trip-generation estimates (from Table 3). The 2022-2023 school year estimates have been used for the short-term school site-generated traffic-volume estimates.

Site-Generated Traffic (Long Term)

Figure 7 shows the projected site-generated traffic volumes for the weekday morning and evening peak hours for the maximum enrollment year. Long-term site-generated traffic volumes have been calculated by applying directional-distribution percentages estimated by LSC (from Figure 5) to the long-term trip-generation estimates (from Table 3). The maximum enrollment school year estimates have been used for the long-term school site-generated traffic-volume estimates.

SHORT-TERM SCENARIO, BASELINE AND TOTAL TRAFFIC

The Waynoka Road connection to Powers Boulevard will be permanently closed **with this project**, as required by CDOT.

Figure 8 shows the estimated short-term baseline traffic volumes, which reflect adjustments and rerouting of existing traffic to account for the planned closure of the Waynoka Road/Powers Boulevard intersection.

Figure 9 shows the projected short-term total traffic volumes, which are the sum of short-term baseline (adjusted existing traffic, from Figure 8) plus estimated James Irwin Charter Academy short-term (2023-2024 school year) site-generated traffic (from Figure 6).

FUTURE LONG-TERM TRAFFIC SCENARIO

Several potential future changes to the area roadway network will affect future traffic volumes in the study area.

- Powers Boulevard is planned as a future freeway. Although Powers Boulevard volumes are likely to continue to increase, the corridor already currently carries high volumes.
- The Waynoka Road connection to Powers Boulevard will be permanently closed **with this project**, as required by CDOT.
- Waynoka Road south of Waynoka Place and Waynoka Place will likely combine to form portions of the planned future Powers Boulevard frontage road.
- Some currently-vacant parcels along Waynoka Road may be developed in the future. Although this will add some additional traffic to Waynoka, the roadway is under-capacity and will be able to accommodate additional trips.

2042 BACKGROUND TRAFFIC

Provide reference for statement.

Figure 10 shows the background traffic volumes for the year 2042. Background traffic is the traffic estimated to be on the adjacent roadway system without consideration of the proposed school. Background traffic includes the through traffic and the traffic generated by adjacent developments (existing and anticipated future) but assumes zero traffic generated by the site.

2042 TOTAL TRAFFIC

Figure 11 shows the total traffic volumes for the year 2042 at the study-area intersections, which are the sum of the 2042 background traffic volumes (from Figure 10) plus the long-term site-generated traffic volumes (from Figure 7).

LEVEL OF SERVICE ANALYSIS

Level of service (LOS) is a quantitative measure of the level of congestion or delay at an intersection and is indicated on a scale from "A" to "F." LOS A is indicative of little congestion or delay. LOS F indicates a high level of congestion or delay. Table 4 shows the level of service delay ranges for signalized and unsignalized intersections.

Table 4: Intersection Levels of Service Delay Ranges

Level of Service	Signalized Intersections	Unsignalized Intersections
	Average Control Delay (seconds per vehicle)	Average Control Delay (seconds per vehicle) ⁽¹⁾
A	10.0 sec or less	10.0 sec or less
B	10.1-20.0 sec	10.1-15.0 sec
C	20.1-35.0 sec	15.1-25.0 sec
D	35.1-55.0 sec	25.1-35.0 sec
E	55.1-80.0 sec	35.1-50.0 sec
F	80.1 sec or more	50.1 sec or more

(1) For unsignalized intersections, if V/C ratio is greater than 1.0 the level of service is LOS F, regardless of the projected average control delay per vehicle.

Detailed Synchro reports are attached. A summary of LOS during the weekday morning and evening peak hours for the study-area intersections is shown in the following figures:

- Figure 4: Existing Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 8: Short-Term Baseline Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 9: Short-Term Baseline + Site Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 10: 2042 Background Traffic, Lane Geometry, Traffic Control, and LOS
- Figure 11: 2042 Background + Site Traffic, Lane Geometry, Traffic Control, and LOS

Powers Boulevard/Waynoka Road

The westbound-right turning movement at Powers Boulevard/Waynoka Road currently operates at LOS D during the morning peak hour but LOS F during the mid-day and PM peak hours. Pursuant to a recent meeting with CDOT and El Paso County, CDOT has indicated that this intersection must be closed prior to the opening of the proposed school. As such, no short- or long-term analysis has been included in this report.

Waynoka Place/Site Access Points

LSC has assumed that Waynoka Road would be restriped with a painted left-turn median. This would either be striping for dedicated left-turn bays or a center two-way left-turn lane (TWLTL) in conjunction with the opening of the charter school.

Waynoka Place/North Site Access

All individual turning movements at the proposed north site access are projected to operate at LOS A through the long-term during all peak periods. Only northbound-left and southbound-right **entering** movements by parents and students would be permitted at this access.

Waynoka Place/Middle Site Access

All individual turning movements at the proposed north site access are projected to operate at LOS D or better through the long-term during all peak periods. Separate eastbound-left and eastbound-right exiting movements would be provided. This access will be the primary exit for the school, including parent and student vehicles. Buses would be permitted to **enter** (and exit) at this access, as would visitors, and parents dropping off/picking up students using inter-school bus service to other James Irwin schools.

Waynoka Place/South Site Access

All individual turning movements at the proposed north site access are projected to operate at LOS B or better through the long-term during all peak periods. Only staff/faculty and overflow parking would be permitted at this full-movement access.

Waynoka Road/Waynoka Place

All single-lane approaches at this intersection currently operate at and are projected to remain at LOS B or better during all peak periods, with or without the addition of site-generated traffic. Note: This analysis has been conducted based on the current laneage of single-lane approaches. Please refer to the following Auxiliary Turn-Lane Needs Analysis section of this report.

Constitution Avenue/Tutt Boulevard/Waynoka Place

Note: LSC did not modify the City's existing signal timings at this intersection when analyzing any short-term or long-term scenario, with or without the addition of site-generated traffic. Based on projected volume increases on Tutt Boulevard and Waynoka Place, the City may opt to adjust existing signal timings to provide more green time to the northbound and southbound approaches in order to improve LOS on the minor-street approaches.

Short Term

Based on existing signal timings, all individual turning movements currently operate at and are projected to remain at LOS D or better during the short term, with or without the addition of site-generated traffic from the proposed charter school.

Long Term

Using existing signal timings, the following individual turning movements are projected to operate at LOS E or worse during the long term, with or without the addition of site-generated traffic from the proposed charter school: southbound-through and northbound-left. The northbound-through/right shared turn lane is projected to operate at LOS E during the maximum enrollment school year.

It is unlikely that LOS on the northbound approach would improve without modifying the existing signal timings to provide more green time on minor-street approaches. There is not sufficient room to add separate northbound-through and northbound-right lanes, so this turning movement is likely to remain a single northbound-through/right shared turn lane in the future. Additionally, the eastbound-right turning movement already exceeds the City's threshold for requiring a right-turn deceleration lane, but this improvement is not feasible due to geometric constraints on the southwest corner of Constitution/Tutt/Waynoka.

Palmer Park Boulevard/Waynoka Road

Short Term

Assuming the existing stop-sign control, all individual turning movements would continue to operate at LOS D or better during the short term, with or without the addition of site-generated traffic from the proposed charter school.

Long Term

Based on the long term projected total volumes, the southbound left-turning movement is projected to operate at LOS E or worse during the morning and mid-afternoon peak hours. Assuming existing traffic control, the southbound-left turning movement is projected to operate at LOS F during all peak hours during the 20-year horizon. This intersection is a short distance east of the Powers/Palmer Park signalized intersection. Relatively long traffic gaps in eastbound traffic are created by this upstream signal and the signal at the adjacent Wendy's/shopping center signal, which benefit southbound-left-turning motorists at Waynoka Road/Palmer Park Boulevard.

Right-of-way has been reserved for potential future realignment of Waynoka Road north of Palmer Park. The Powers Environmental Assessment envisions this realignment such that

Discuss what cross section this section should have to improve LOS.

Waynoka Road would align with the rear access to the former Kmart shopping center, and this four-leg intersection would be signalized. The property owner on the north side of Palmer Park is (and has been) evaluating other short-term and long-term access and traffic-control alternatives for this section of Palmer Park Boulevard.

QUEUEING ANALYSIS – ACCESS POINT INTERSECTIONS AND OFFSITE INTERSECTIONS

A queuing analysis was performed for the eastbound approach at the middle site access to Waynoka Place. Queuing analyses have been run for the short-term total and the 2042 total traffic volumes.

“Upstream block time” represents the percent of time during the peak hour in which the entry point for a turn lane upstream of the subject intersection is blocked by a queue in the adjacent through lane. “Storage block time” is the proportion of time in which the turn lane’s queue exceeds the available storage length and left-turning vehicles overspill the turn lane in the model and into the adjacent through lane.

“Maximum queue” represents the maximum queue length observed for each individual lane during the 15-minute analysis period. SimTraffic records the maximum back of queue observed for every two-minute period. In SimTraffic, a vehicle is considered queued whenever it is behind another vehicle traveling at less than 10 feet/second (approximately 7 mph) or at a stop bar. The maximum observed queue may not occur during the same interval in which the highest upstream block time (percent) or storage block time (percent) occurs. LSC has analyzed the highest value for each metric for each turn lane/approach, regardless of whether or not they occur in the same 15-minute interval.

Reported queue lengths for auxiliary turn lanes in SimTraffic is generally limited by the turn-lane length. SimTraffic simply reports the maximum observed queue length during simulations. Any spillover from a left-to-

Middle Access

Include in the narrative model queue lengths for the northbound left turn lane and determine whether 175 feet will be enough for that queue. Also discuss if queue has enough length for both buses and parent vehicles combined.

Analysis has been run on the eastbound-left and eastbound-right exiting lanes at the middle access to determine the minimum on-site stacking length for parent and student vehicles after pick-up and drop-off operations. These lanes would be striped separately in their entirety after the parent loading zone.

Show the queue lengths in the loading/unloading exhibit.

During the mid-afternoon peak hour, simulation reports indicate that the eastbound-left queue is projected to reach a maximum of about 264 feet, while the eastbound-right queue is projected to reach a maximum of about 135 feet during the long-term afternoon release period.

LSC recommends that the eastbound exiting turn lanes at the middle access each be striped for a minimum of 264 feet, which would accommodate approximately 10-12 vehicles. Please refer

Explain in a narrative how queuing buses are going to affect this second access point and how the circulation will work if queue is in the way when buses are making a left to the unloading zone. Show where buses are going to wait while other buses unload. Per the report, buses are expected to arrive and leave with a 15 minute window.

to the attached SimTraffic reports for projected maximum and 95th percentile mid-day peak-hour queue lengths.

North Access

Analysis has been run to estimate the maximum queue length of the northbound-left lanes at the north access that would extend to the middle access. A 180-foot dedicated northbound-left turn lane is recommended on Waynoka Place between the north and middle site accesses.

SimTraffic simulation reports indicate that the northbound-left queue is projected to reach a maximum of about 105 feet, which would **not** exceed the 180 feet of stacking distance for this turn lane.

AUXILIARY TURN-LANE NEED ANALYSIS

Please refer to the following exhibits (attached) for proposed striping plans at each site access:

- Figure 12: Proposed North Access Laneage
- Figure 13: Proposed Middle Access Laneage
- Figure 14: Proposed South Access Laneage

Powers Boulevard/Waynoka Road

Powers Boulevard is classified as “F-W: Freeway” with a posted speed limit of 55 mph in the vicinity of the site. Waynoka Road is classified as a Non-Residential Collector. No auxiliary right-turn lanes currently exist on Powers Boulevard at Waynoka Road. However, CDOT has indicated that this RIRO intersection will be **closed** in conjunction with the opening of the proposed school.

Waynoka Road at Waynoka Place

Following the closure of the Waynoka Road/Powers intersection, nearly all vehicles would be westbound-right-turning (to head northbound on Waynoka Place), so there would be no need for a separate right-turn deceleration lane on the westbound approach.

Additionally, LSC recommends that the southbound approach on Waynoka Place approaching Waynoka Road should remain a single-lane approach. Striping for a short northbound-left-turn bay is recommended just north of this intersection at the south access (staff/overflow parking lot), and that is achievable with the southbound single-lane approach on Waynoka Place at Waynoka Road.



Discuss whether the 100' left turn bay is long enough for the queue at peak hours.

Waynoka Place/Site Access Points

Provide peak hour left and right turning volumes for all access point and discuss applicable ECM criteria section 2.3.7.D.1. and 2.3.7.D.2.

LSC recommends that Waynoka Place be striped with a painted left-turn median. This would either be striping for dedicated left-turn bays or a center two-way left-turn lane (TWLTL) in conjunction with the opening of the charter school. The preliminary recommended configuration of the access points and associated laneage, striping of Waynoka Place, etc. is shown in Figures Figure 12-Figure 14

Waynoka Place/North Site Access

Only entering turning movements will be permitted at the north access, which will be the ingress for parent and student drivers. Based on projected traffic volumes, *ECM* thresholds for southbound-right and northbound-left turn lanes would be met at the main access. LSC recommends the following turn-lane dimensions at the north access:

- 280-foot southbound right-turn deceleration lane (190 feet with 90-foot taper)
- Northbound left-turn deceleration lane at part of TWLTL

Waynoka Place/Middle Site Access

Determine whether a right turn lane necessary for the southbound vehicles that use this access point per *ECM* 2.3.7.D.2.

The middle access would serve as an exit-only, except for buses, visitors and parents dropping off/picking up students using inter-school bus service to other James Irwin schools. These vehicles would be allowed entry at this middle access. LSC recommends that separate eastbound-left and eastbound-right turn lanes with at least 250 feet of stacking distance per lane be provided to accommodate projected exiting queues.

Waynoka Place/South Site Access

Staff parking and primarily overflow parking would be served by the south access. Due to the short distance on Waynoka Place between the south access and the stop bar at Waynoka Road, LSC recommends striping for a short 100-foot northbound-left turn bay at the south access. This lane would consist of 50 feet of storage and a 50-foot taper.

Palmer Park Boulevard/Waynoka Road

Discuss the east bound left turn lane movement threshold.

Based on projected traffic volumes, the westbound right-turn movement would exceed the *ECM* threshold requiring a separate westbound right-turn deceleration lane. The cross-section of Palmer Park Boulevard includes a striped, center left-turn median (TWLTL).

Constitution Avenue/Tutt Boulevard/Waynoka Place

There is not sufficient room to add separate northbound-through and northbound-right lanes, so this turning movement is likely to remain a single northbound-through/right shared turn lane in the future. Additionally, the eastbound-right turning movement already exceeds the City's

Address right bound turn volumes and determine if there is a deficiency or if this development will create a deficiency per the *ECM* criteria (not City's). Also discuss southbound right turn and left turn thresholds on Constitution Ave.

threshold for requiring a right-turn deceleration lane, but this improvement is not feasible due to geometric constraints on the southwest corner of Constitution/Tutt/Waynoka.

ON-SITE QUEUING REQUIREMENT (FOR PARENT PICK-UP/DROP-OFF “CAR-LINE”)

School On-Site Queueing for Parent Drop-off and Pick-up

The North Carolina Municipal School Transportation Assistance (MSTA) performs studies that address the safety concerns with the overall pedestrian safety and traffic operations on a school campus, and how traffic affects adjacent roadways. To calculate school operations, MSTA has developed a database of specific data related to school operations, including required queue lengths and trip-generation estimates by mode (parent drop-off/pick-up, bus, etc.). LSC has used the MSTA’s spreadsheet in several similar school operations studies, as it has typically been required by jurisdictions as a preferred alternative to ITE rates for schools.

Data indicates that AM traffic operations on a school campus usually operate safely and efficiently due to parent traffic arriving at a broader range of times. PM traffic operations are quite different, as parents often arrive well before the school dismissal and park or queue (back up) along campus driveways. The PM queue often results with vehicles stopped in the roadway or along the shoulder of a major through route, which increase the chances of accidents and similar traffic-related safety concerns.

Per information from the City of Colorado Springs Traffic Engineering Division, the required “high-demand” stacking length on-site in the proposed parent drop-off/pick-up loop for the maximum enrollment (720 students) would be 1,650 feet. The school “carpool” plan will need to show this length of on-site stacking/queueing distance for parent drop-off/pick-up **plus** 175 feet of active loading/unloading zone distance (NC MSTA guidelines). Depending on the site operational characteristics, the necessary on-site queue lengths could potentially be adjusted.

This queue distance is exclusive of a recommended 5-7-vehicle-long drop-off/pick-up zone (the 175-foot distance). The empirical formula adds an additional 30 percent to a base queue-length calculation of required total queue length as a precaution for atypical events, including bad weather, school performances, and other special events. Formula-generated queue lengths are based on afternoon school peak-hour empirical queuing data.

ROADWAY CLASSIFICATIONS

Powers Boulevard is a designated Freeway, Waynoka Road is a Non-Residential Collector, and Waynoka Place is a Local Road. However, Waynoka Place should likely be considered a Non-Residential Collector.

Discuss the configuration of the pick-up line in the next submittal once it has been determined.

Discuss if it is more likely to be a collector because of the development.

CONFORMANCE WITH THE MTCP

No reimbursable roadway improvement projects have been identified as being needed by the year 2040, per Map 13 and Table 4 of El Paso County's 2016 *MTCP*. See the attached *MTCP* maps for reference.

COUNTY ROAD IMPROVEMENT FEE PROGRAM

The applicant will be required to participate in this program.

MULTI-MODAL/TRANSPORTATION DEMAND MANAGEMENT (TDM) OPPORTUNITIES

No multi-modal/transportation demand management (TDM) roadway improvement projects have been identified as being needed by the year 2040 per Map 15 and Table 5 of El Paso County's 2016 *MTCP*.

Please refer to the Pedestrian and bicycle section above for details on sidewalk facilities and two nearby future regional trail extensions/connections.

SUMMARY

Trip Generation

- During the morning peak hour, about 359 vehicles would enter and 318 vehicles would exit the site.
- Approximately 263 vehicles would enter and 263 vehicles would exit the site during the school afternoon peak hour.
- During the PM peak hour, about 13 vehicles would enter and 13 vehicles would exit the site.

Pedestrian and Bicycle Accessibility

- Please refer to the section of the report for details on existing sidewalk locations in the area. Two planned major regional trail corridors intersect near the site. This will provide excellent pedestrian and bicycle accessibility in the future once these trails are established.

Projected Levels of Service

- All individual turning movements and single-lane approaches at the proposed site-access points are projected to operate at LOS D or better through the 20-year horizon following the opening of the charter school. Please refer to the "Level of Service" section for details.

- Please refer to the “Level of Service” section for analysis and results at the two offsite intersections analyzed.

Auxiliary Turn-Lane Needs Analysis

- Please refer to the “Auxiliary Turn-Lane Analysis” section for details.
- Regarding the site-access points and adjacent section of Waynoka Place, Figure 12-Figure 14 show a preliminary laneage concept. LSC will assist the design team with the detailed configuration of the access points, access radii, alignment and width, associated laneage, striping of Waynoka Place, etc. at the design stage.

* * * * *

Please contact me if you have any questions regarding this report.

Respectfully Submitted,

LSC TRANSPORTATION CONSULTANTS, INC.

By: Jeffrey C. Hodsdon, P.E.
Principal

JCH/JAB:jas

Enclosures: Table 5
Figure 1 - Figure 15
Traffic Count Reports
Synchro Level of Service Reports
Queuing Reports
MTCP Maps

Table 5



Table 5: Detailed Trip Generation Estimate

School Year	ITE		Inputs		Average Weekday	Trip Generation Rates ⁴						Average Weekday	Driveway Trips Generated						
	Code	Description	Values	Units		A.M.	Mid-Day ⁵	P.M. ⁶	In	Out	In	Out	A.M.	Mid-Day	P.M.	In	Out		
Previous Land Use																			
-	710	General Office	82.235	KSF	10.84	1.34	0.18	0.12	0.60	0.24	1.20	891	110	15	10	49	20	98	
Based on ITE Rates																			
2023-2024 (Short Term)	538	Charter School (K-12)	359	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	179	159	131	131	7	7	
2024-2025	538	Charter School (K-12)	395	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	197	175	144	144	7	7	
2025-2026	538	Charter School (K-12)	489	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	244	216	178	178	9	9	
2026-2027	538	Charter School (K-12)	525	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	262	232	192	192	10	10	
2027-2028	538	Charter School (K-12)	574	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	286	254	210	210	10	10	
2028-2029	538	Charter School (K-12)	623	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	310	275	227	227	11	11	
Max Enrollment (Long Term)	538	Charter School (K-12)	720	Students	-	0.50	0.44	0.37	0.37	0.02	0.02	-	359	318	263	263	13	13	
Trip Generation Comparison -- Opening Year																			
-	710	General Office	82.235	KSF	10.84	1.34	0.18	0.12	0.60	0.24	1.20	891	110	15	10	49	20	98	
2023-2024 (Short Term)	538	Charter School (K-12)	359	Students	-	0	0	0	0	0	0	-	179	159	131	131	7	7	
												Difference	-	69	144	121	82	-14	-92
Trip Generation Comparison -- Max Enrollment Year																			
-	710	General Office	82.235	KSF	10.84	1.34	0.18	0.12	0.60	0.24	1.20	891	110	15	10	49	20	98	
Max Enrollment (Long Term)	538	Charter School (K-12)	720	Students	-	0	0	0	0	0	0	-	359	318	263	263	13	13	
												Difference	-	249	303	253	214	-7	-85

¹ Assumes 1.5 students per vehicle for on-campus students

² Does not include approximately 100 students who will be transported from/to other campuses to this site at the start/end of each school day from 2 buses and 2 vans off-campus

³ KSF = 1,000 square feet

⁴ Source: *Trip Generation, 11th Edition (2021)* by the Institute of Transportation Engineers (ITE)

⁵ Assumes PM peak trip generation is 5% of School PM (mid-day) trip generation

⁶ Assumes mid-day peak trip generation is 50% of PM trip generation

Figures 1-15





Not to scale



Figure 1
Vicinity Map

James Irwin Charter (LSC# S224370)







Figure 2

Site Plan
















James Irwin Charter (LSC# S224370)








Not to scale



• = Stop Sign  = Traffic Signal




- X = AM Peak-Hour LOS (7:00 - 8:00 am)
- X = School PM Peak-Hour LOS (2:30 - 3:30 pm)
- X = PM Peak-Hour LOS (4:00 - 5:00 pm)
- XX = AM Peak-Hour Traffic (Veh/Hr, 7:00 - 8:00 am)
- XX = School PM Peak-Hour Traffic (Veh/Hr, 2:30 - 3:30 am)
- XX = PM Peak-Hour Traffic (Veh/Hr, 4:00 - 5:00 pm)

Figure 4
Existing Traffic, Lane Geometry, Traffic Control, and LOS

James Irwin Charter (LSC# S224370)



Not to scale



XX% = Estimated % Distribution of Site-Generated Trips

Figure 5
Directional Distribution

James Irwin Charter (LSC# S224370)






Figure 6
Site-Generated Traffic
(Opening Year)

James Irwin Charter (LSC# S224370)



Not to scale



①
Intentionally
Left Blank -
Intersection to
be closed with
this project

$$\begin{array}{r} 118 \\ \frac{97}{5} \\ \hline 151 \\ \frac{110}{6} \end{array}$$

②

$$\begin{array}{r} 22 \\ \frac{18}{1} \\ \hline 13 \\ \frac{10}{1} \\ \hline 16 \\ \frac{12}{1} \\ \hline 134 \\ \frac{99}{5} \end{array} \quad \begin{array}{r} 105 \\ \frac{87}{4} \\ \hline 1 \end{array}$$

③

$$\begin{array}{r} 179 \\ \frac{148}{7} \\ \hline 105 \\ \frac{87}{4} \\ \hline 7 \\ \frac{5}{0} \\ \hline 19 \\ \frac{16}{1} \end{array}$$

④

$$\begin{array}{r} 186 \\ \frac{136}{7} \\ \hline 134 \\ \frac{99}{5} \\ \hline 21 \\ \frac{194}{8} \end{array}$$

⑤

$$\begin{array}{r} 75 \\ \frac{55}{3} \\ \hline 150 \\ \frac{124}{6} \\ \hline 22 \\ \frac{18}{1} \\ \hline 34 \\ \frac{29}{24} \\ \hline 72 \\ \frac{53}{3} \end{array}$$


⑥

$$\begin{array}{r} 136 \\ \frac{100}{5} \\ \hline 70 \\ \frac{58}{3} \\ \hline 48 \\ \frac{39}{2} \\ \hline 29 \\ \frac{21}{1} \end{array}$$


⑦

Figure 7
Site-Generated Traffic
(Full-Enrollment)


Intentionally
Left Blank -
Intersection to
be closed by
CDOT




Intentionally
Left Blank -
Intersection to
be closed by
CDOT




free





6



115




116




A vertical compass rose with a central circle containing the letter 'N' for North. The rose has four points: North (top), South (bottom), East (right), and West (left). The 'N' is bold and black.

free




11



The diagram shows a large circle representing a system. Inside the circle, there are three regions labeled A, B, and C. Region A is at the bottom left, B is at the top center, and C is at the top right. Each region has a specific boundary condition: A has 'free' boundary conditions on its left and bottom edges; B has 'B' boundary conditions on its top and right edges; and C has 'C' boundary conditions on its top and right edges. Arrows indicate the flow direction from left to right across the boundaries.

119



A circular diagram illustrating a division problem. The numbers involved are 362, 114, 45, 74, 104, 823, 30, 18, 67, 110, 40, and 55. Arrows point from the dividend 362 to the quotient 114, and from the divisor 45 to the remainder 74. Another arrow points from the quotient 114 to the divisor 45. The number 6 is enclosed in a circle at the bottom center. Arrows also point from the divisor 45 to the dividend 362, and from the quotient 110 to the divisor 45.

b = Stop Sign

Page 10

X = AM Peak-Hour LOS (7:00 - 8:00 am)
X = School PM Peak-Hour LOS (2:30 - 3:30 pm)
X = PM Peak-Hour LOS (4:00 - 5:00 pm)

XX = School PM Peak-Hour Traffic (Veh/Hr, 2:30 - 3:30 am)


XX PM Peak-Hour Traffic (Veh/Hr, 4:00 - 5:00 pm)

Figure 8

Short-Term Baseline Traffic, Lane Geometry, Traffic Control, and LOS (Opening Year)













James Irwin Charter (LSC# S224370)


Not to scale



Intentionally
Left Blank -
Intersection to
be closed with
this project

①
Intentionally
Left Blank -
Intersection to
be closed with
this project



• = Stop Sign


 = Traffic Signal

X = AM Peak-Hour LOS (7:00 - 8:00 am)
X = School PM Peak-Hour LOS (2:30 - 3:30 pm)
X = PM Peak-Hour LOS (4:00 - 5:00 pm)


XX = AM Peak-Hour Traffic (Veh/Hr, 7:00 - 8:00 am)
XX = School PM Peak-Hour Traffic (Veh/Hr, 2:30 - 3:30 am)
XX = PM Peak-Hour Traffic (Veh/Hr, 4:00 - 5:00 pm)

Figure 9
Short-Term Baseline +
Site Traffic, Lane
Geometry, Traffic
Control, and LOS
(Opening Year)











Intentionally
Left Blank -
Intersection to
be closed with
this project



Intentionally
Left Blank -
Intersection to
be closed with
this project



A compass rose icon with a vertical line through the center. At the top is a black diamond pointing upwards labeled 'N'. At the bottom is a black diamond pointing downwards. A horizontal line extends from the center to the left, ending in a black circle with a crosshair pattern, representing 'W'. Another horizontal line extends from the center to the right, ending in a black circle with a crosshair pattern, representing 'E'.



 = Stop Sign

 = Traffic Signal


X = AM Peak-Hour LOS (7:00 - 8:00 am)
X = School PM Peak-Hour LOS (2:30 - 3:30 pm)
X = PM Peak-Hour LOS (4:00 - 5:00 pm)

XX PM Peak-Hour LOS (4:00 - 5:00 pm)
XX AM Peak-Hour Traffic (Veh/Hr, 7:00 - 8:00 am)
XX = School PM Peak-Hour Traffic (Veh/Hr, 2:30 - 3:30 am)
XX PM Peak-Hour Traffic (Veh/Hr, 4:00 - 5:00 pm)

Figure 10

Figure 10

James Irwin Charter (ISCS# S224370)



X AM Peak-Hour LOS (7:00 - 8:00 am)
 \bar{X} = School PM Peak-Hour LOS (2:30 - 3:30 pm)
X PM Peak-Hour LOS (4:00 - 5:00 pm)

XX AM Peak-Hour Traffic (Veh/Hr, 7:00 - 8:00 am)
 \bar{XX} = School PM Peak-Hour Traffic (Veh/Hr, 2:30 - 3:30 pm)
XX PM Peak-Hour Traffic (Veh/Hr, 4:00 - 5:00 pm)




Figure 12

Proposed Laneage - New North Access

Conceptual Only - not for design

Note: Access design for passenger vehicles only





Figure 13

Proposed Laneage - Middle Access

James Irwin Charter (LSC#S224370)

Conceptual Only - not for design




Note: Access design for passenger vehicles only

Conceptual Only - not for design

Figure 14

Proposed Laneage - South Access

James Irwin Charter (LSC#S224370)



Conceptual Only - not for design

Explain in a narrative how queuing buses are going to affect this second access point. Show where buses are going to wait while other buses unload. Per the report, buses are expected to arrive and leave with a 15 minute window.

Figure 15
Loading/Unloading Areas

James Irwin Charter (LSC#S224370)

Traffic Counts



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304

Colorado Springs, CO 80909

719-633-2868

File Name : Powers Blvd - Waynoka Rd AM

Site Code : S224370

Start Date : 6/9/2022

Page No : 1

Groups Printed- Unshifted

	Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
06:45		0	0	0	0	0	7	0	0	0	7	19	451	0	0	470	0	0	0	0	0	477
Total		0	0	0	0	0	7	0	0	0	7	19	451	0	0	470	0	0	0	0	0	477
07:00		0	0	0	0	0	10	0	0	0	10	23	455	0	0	478	0	0	0	0	0	488
07:15		0	0	0	0	0	3	0	0	0	3	7	484	0	0	491	0	0	0	0	0	494
07:30		0	0	0	0	0	8	0	0	0	8	10	536	0	0	546	0	0	0	0	0	554
07:45		0	0	0	0	0	5	0	0	0	5	16	524	0	0	540	0	0	0	0	0	545
Total		0	0	0	0	0	26	0	0	0	26	56	1999	0	0	2055	0	0	0	0	0	2081
Grand Total		0	0	0	0	0	33	0	0	0	33	75	2450	0	0	2525	0	0	0	0	0	2558
Apprch %		0	0	0	0	0	100	0	0	0	0	3	97	0	0	0	0	0	0	0	0	
Total %		0	0	0	0	0	1.3	0	0	0	1.3	2.9	95.8	0	0	98.7	0	0	0	0	0	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Powers Blvd - Waynoka Rd AM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 2

	Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 6:45:00 AM to 7:45:00 AM - Peak 1 of 1																						
Peak Hour for Entire Intersection Begins at 7:00:00 AM																						
7:00:00 AM	0	0	0	0	0	0	10	0	0	0	10	23	455	0	0	478	0	0	0	0	0	488
7:15:00 AM	0	0	0	0	0	0	3	0	0	0	3	7	484	0	0	491	0	0	0	0	0	494
7:30:00 AM	0	0	0	0	0	0	8	0	0	0	8	10	536	0	0	546	0	0	0	0	0	554
7:45:00 AM	0	0	0	0	0	0	5	0	0	0	5	16	524	0	0	540	0	0	0	0	0	545
Total Volume	0	0	0	0	0	0	26	0	0	0	26	56	1999	0	0	2055	0	0	0	0	0	2081
% App. Total	0	0	0	0			100	0	0	0		2.7	97.3	0	0		0	0	0	0		
PHF	.000	.000	.000	.000	.000	.650	.000	.000	.000	.650	.609	.932	.000	.000	.941	.000	.000	.000	.000	.000	.939	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868


File Name : Powers Blvd - Waynoka Rd AM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 3

Start Time	Southbound				Waynoka Rd Westbound				Powers Blvd Northbound				Eastbound							
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total

Peak Hour Analysis From 6:45:00 AM to 7:45:00 AM - Peak 1 of 1

Peak Hour for Each Approach Begins at:

	6:45:00 AM	6:45:00 AM	7:00:00 AM	6:45:00 AM
+0 mins.	0 0 0 0 0	7 0 0 0 7	23 455 0 0 478	0 0 0 0 0
+5 mins.	0 0 0 0 0	10 0 0 0 10	7 484 0 0 491	0 0 0 0 0
+10 mins.	0 0 0 0 0	3 0 0 0 3	10 536 0 0 546	0 0 0 0 0
+15 mins.	0 0 0 0 0	8 0 0 0 8	16 524 0 0 540	0 0 0 0 0
Total Volume	0 0 0 0 0	28 0 0 0 28	56 1999 0 0 2055	0 0 0 0 0
% App. Total	0 0 0 0	100 0 0 0	2.7 97.3 0 0 0	0 0 0 0 0
PHF	.000 .000 .000 .000 .000	.700 .000 .000 .000 .700	.609 .932 .000 .000 .941	.000 .000 .000 .000 .000



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Powers Blvd - Waynoka Rd Mid
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 1

Groups Printed- Unshifted


	Driveway Accesses Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
14:30	0	0	0	0	0	0	13	0	0	0	13	13	621	0	0	634	0	0	0	0	0	647
14:45	0	0	0	0	0	0	8	0	0	0	8	16	672	0	0	688	0	0	0	0	0	696
Total		0	0	0	0	0	21	0	0	0	21	29	1293	0	0	1322	0	0	0	0	0	1343
15:00	0	0	0	0	0	0	21	0	0	0	21	17	722	0	0	739	0	0	0	0	0	760
15:15	0	0	0	0	0	0	7	0	0	0	7	22	729	0	0	751	0	0	0	0	0	758
Grand Total		0	0	0	0	0	49	0	0	0	49	68	2744	0	0	2812	0	0	0	0	0	2861
Apprch %		0	0	0	0	0	100	0	0	0	0	2.4	97.6	0	0	0	0	0	0	0	0	0
Total %		0	0	0	0	0	1.7	0	0	0	1.7	2.4	95.9	0	0	98.3	0	0	0	0	0	0

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Powers Blvd - Waynoka Rd Mid
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 2

	Driveway Accesses Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 2:30:00 PM to 3:15:00 PM - Peak 1 of 1																						
Peak Hour for Entire Intersection Begins at 2:30:00 PM																						
2:30:00 PM	0	0	0	0	0	0	13	0	0	0	13	13	621	0	0	634	0	0	0	0	0	647
2:45:00 PM	0	0	0	0	0	0	8	0	0	0	8	16	672	0	0	688	0	0	0	0	0	696
3:00:00 PM	0	0	0	0	0	0	21	0	0	0	21	17	722	0	0	739	0	0	0	0	0	760
3:15:00 PM	0	0	0	0	0	0	7	0	0	0	7	22	729	0	0	751	0	0	0	0	0	758
Total Volume	0	0	0	0	0	0	49	0	0	0	49	68	2744	0	0	2812	0	0	0	0	0	2861
% App. Total	0	0	0	0	0	0	100	0	0	0	0	2.4	97.6	0	0	0	0	0	0	0	0	0
PHF	.000	.000	.000	.000	.000	.000	.583	.000	.000	.000	.583	.773	.941	.000	.000	.936	.000	.000	.000	.000	.000	.941



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868


File Name : Powers Blvd - Waynoka Rd Mid
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 3

Start Time	Driveway Accesses Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound				
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total


Peak Hour Analysis From 2:30:00 PM to 3:15:00 PM - Peak 1 of 1

Peak Hour for Each Approach Begins at:

	2:30:00 PM	2:30:00 PM	2:30:00 PM	2:30:00 PM
+0 mins.	0 0 0 0 0	13 0 0 0 13	13 621 0 0 634	0 0 0 0 0
+5 mins.	0 0 0 0 0	8 0 0 0 8	16 672 0 0 688	0 0 0 0 0
+10 mins.	0 0 0 0 0	21 0 0 0 21	17 722 0 0 739	0 0 0 0 0
+15 mins.	0 0 0 0 0	7 0 0 0 7	22 729 0 0 751	0 0 0 0 0
Total Volume	0 0 0 0 0	49 0 0 0 49	68 2744 0 0 2812	0 0 0 0 0
% App. Total	0 0 0 0	100 0 0 0	2.4 97.6 0 0 0	0 0 0 0 0
PHF	.000 .000 .000 .000 .000	.583 .000 .000 .000 .583	.773 .941 .000 .000 .936	.000 .000 .000 .000 .000



Peak Hour Data



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Powers Blvd - Waynoka Rd PM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 1

Groups Printed- Unshifted

	Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
16:00	0	0	0	0	0	0	7	0	0	0	7	34	746	0	0	780	0	0	0	0	0	787
16:15	0	0	0	0	0	0	6	0	0	0	6	26	718	0	0	744	0	0	0	0	0	750
16:30	0	0	0	0	0	0	5	0	0	0	5	25	734	0	0	759	0	0	0	0	0	764
16:45	0	0	0	0	0	0	4	0	0	0	4	44	689	0	0	733	0	0	0	0	0	737
Total		0	0	0	0	0	22	0	0	0	22	129	2887	0	0	3016	0	0	0	0	0	3038
17:00	0	0	0	0	0	0	3	0	0	0	3	48	650	0	0	698	0	0	0	0	0	701
17:15	0	0	0	0	0	0	6	0	0	0	6	24	649	0	0	673	0	0	0	0	0	679
17:30	0	0	0	0	0	0	6	0	0	0	6	16	627	0	0	643	0	0	0	0	0	649
17:45	0	0	0	0	0	0	3	0	0	0	3	13	714	0	0	727	0	0	0	0	0	730
Total		0	0	0	0	0	18	0	0	0	18	101	2640	0	0	2741	0	0	0	0	0	2759
Grand Total		0	0	0	0	0	40	0	0	0	40	230	5527	0	0	5757	0	0	0	0	0	5797
Apprch %		0	0	0	0	0	100	0	0	0	0	4	96	0	0	0	0	0	0	0	0	
Total %		0	0	0	0	0	0.7	0	0	0	0.7	4	95.3	0	0	99.3	0	0	0	0	0	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304

Colorado Springs, CO 80909

719-633-2868

File Name : Powers Blvd - Waynoka Rd PM

Site Code : S224370

Start Date : 6/9/2022

Page No : 2


	Southbound					Waynoka Rd Westbound					Powers Blvd Northbound					Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 4:00:00 PM to 5:45:00 PM - Peak 1 of 1																						
Peak Hour for Entire Intersection Begins at 4:00:00 PM																						
4:00:00 PM	0	0	0	0	0	0	7	0	0	0	7	34	746	0	0	780	0	0	0	0	0	787
4:15:00 PM	0	0	0	0	0	0	6	0	0	0	6	26	718	0	0	744	0	0	0	0	0	750
4:30:00 PM	0	0	0	0	0	0	5	0	0	0	5	25	734	0	0	759	0	0	0	0	0	764
4:45:00 PM	0	0	0	0	0	0	4	0	0	0	4	44	689	0	0	733	0	0	0	0	0	737
Total Volume	0	0	0	0	0	0	22	0	0	0	22	129	2887	0	0	3016	0	0	0	0	0	3038
% App. Total	0	0	0	0	0	0	100	0	0	0	0	4.3	95.7	0	0	0	0	0	0	0	0	0
PHF	.000	.000	.000	.000	.000	.786	.000	.000	.000	.786	.733	.967	.000	.000	.967	.000	.000	.000	.000	.000	.965	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Powers Blvd - Waynoka Rd PM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 3

Start Time	Southbound				Waynoka Rd Westbound				Powers Blvd Northbound				Eastbound								
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 4:00:00 PM to 5:45:00 PM - Peak 1 of 1																					
Peak Hour for Each Approach Begins at:																					
+0 mins.	0	0	0	0	0	7	0	0	0	7	34	746	0	0	780	0	0	0	0	0	0
+5 mins.	0	0	0	0	0	6	0	0	0	6	26	718	0	0	744	0	0	0	0	0	0
+10 mins.	0	0	0	0	0	5	0	0	0	5	25	734	0	0	759	0	0	0	0	0	0
+15 mins.	0	0	0	0	0	4	0	0	0	4	44	689	0	0	733	0	0	0	0	0	0
Total Volume	0	0	0	0	0	22	0	0	0	22	129	2887	0	0	3016	0	0	0	0	0	0
% App. Total	0	0	0	0	0	100	0	0	0	0	4.3	95.7	0	0	0	0	0	0	0	0	0
PHF	.000	.000	.000	.000	.000	.786	.000	.000	.000	.786	.733	.967	.000	.000	.967	.000	.000	.000	.000	.000	.000



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Waynoka PI - Waynoka Rd AM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 1

Groups Printed- Unshifted

	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
06:45	2	0	25	0	27	27	13	3	0	0	16	0	0	0	0	0	0	6	1	0	7	50
Total		2	0	25	0	27	13	3	0	0	16	0	0	0	0	0	0	6	1	0	7	50
07:00	5	0	21	0	26	26	5	9	0	0	14	0	0	0	0	0	0	17	4	0	21	61
07:15	5	0	16	0	21	21	9	5	0	0	14	0	0	0	0	0	1	3	4	0	8	43
07:30	6	0	18	0	24	24	17	9	0	0	26	0	0	0	0	0	0	5	6	0	11	61
07:45	3	0	41	0	44	44	17	2	0	0	19	0	0	1	1	2	0	8	6	0	14	79
Total		19	0	96	0	115	48	25	0	0	73	0	0	1	1	2	1	33	20	0	54	244
Grand Total		21	0	121	0	142	61	28	0	0	89	0	0	1	1	2	1	39	21	0	61	294
Apprch %		14.8	0	85.2	0	68.5	31.5	0	0	0	0	0	0	50	50	0	1.6	63.9	34.4	0	0	
Total %		7.1	0	41.2	0	48.3	20.7	9.5	0	0	30.3	0	0	0.3	0.3	0.7	0.3	13.3	7.1	0	20.7	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304

Colorado Springs, CO 80909

719-633-2868


File Name : Waynoka PI - Waynoka Rd AM

Site Code : S224370

Start Date : 6/9/2022

Page No : 2

Start Time	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 6:45:00 AM to 7:45:00 AM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 7:00:00 AM																					
7:00:00 AM	5	0	21	0	26	5	9	0	0	14	0	0	0	0	0	0	17	4	0	21	61
7:15:00 AM	5	0	16	0	21	9	5	0	0	14	0	0	0	0	0	1	3	4	0	8	43
7:30:00 AM	6	0	18	0	24	17	9	0	0	26	0	0	0	0	0	0	5	6	0	11	61
7:45:00 AM	3	0	41	0	44	17	2	0	0	19	0	0	1	1	2	0	8	6	0	14	79
Total Volume	19	0	96	0	115	48	25	0	0	73	0	0	1	1	2	1	33	20	0	54	244
% App. Total	16.5	0	83.5	0		65.8	34.2	0	0		0	0	50	50		1.9	61.1	37	0		
PHF	.792	.000	.585	.000	.653	.706	.694	.000	.000	.702	.000	.000	.250	.250	.250	.250	.485	.833	.000	.643	.772



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868


File Name : Waynoka PI - Waynoka Rd AM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 3

Start Time	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound				
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total


Peak Hour Analysis From 6:45:00 AM to 7:45:00 AM - Peak 1 of 1

Peak Hour for Each Approach Begins at:

	7:00:00 AM	7:00:00 AM	7:00:00 AM	7:00:00 AM
+0 mins.	5 0 21 0 26	5 9 0 0 14	0 0 0 0 0	0 17 4 0 21
+5 mins.	5 0 16 0 21	9 5 0 0 14	0 0 0 0 0	1 3 4 0 8
+10 mins.	6 0 18 0 24	17 9 0 0 26	0 0 0 0 0	0 5 6 0 11
+15 mins.	3 0 41 0 44	17 2 0 0 19	0 0 1 1 2	0 8 6 0 14
Total Volume	19 0 96 0 115	48 25 0 0 73	0 0 1 1 2	1 33 20 0 54
% App. Total	16.5 0 83.5 0	65.8 34.2 0 0 0	0 0 50 50	1.9 61.1 37 0
PHF	.792 .000 .585 .000 .653	.706 .694 .000 .000 .702	.000 .000 .250 .250 .250	.250 .485 .833 .000 .643



Peak Hour Data



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Waynoka PI - Waynoka Rd Mid
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 1

Groups Printed- Unshifted


	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound						
	Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
14:30	5	0	20	0	25	25	20	9	0	0	29	0	0	0	0	0	0	6	9	0	15	69
14:45	3	0	24	0	27	27	16	6	0	0	22	0	0	0	0	0	0	6	11	0	17	66
Total		8	0	44	0	52	36	15	0	0	51	0	0	0	0	0	0	12	20	0	32	135
15:00	8	0	32	0	40	40	38	13	0	0	51	0	0	0	0	0	0	4	7	0	11	102
15:15	3	0	31	0	34	34	28	7	0	0	35	0	0	0	0	0	0	3	17	0	20	89
Grand Total		19	0	107	0	126	102	35	0	0	137	0	0	0	0	0	0	19	44	0	63	326
Apprch %	15.1	0	84.9	0		74.5	25.5	0	0			0	0	0	0	0	0	30.2	69.8	0		
Total %	5.8	0	32.8	0	38.7	31.3	10.7	0	0		42	0	0	0	0	0	0	5.8	13.5	0	19.3	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Waynoka PI - Waynoka Rd Mid
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 2

Start Time	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 2:30:00 PM to 3:15:00 PM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 2:30:00 PM																					
2:30:00 PM	5	0	20	0	25	20	9	0	0	29	0	0	0	0	0	0	6	9	0	15	69
2:45:00 PM	3	0	24	0	27	16	6	0	0	22	0	0	0	0	0	0	6	11	0	17	66
3:00:00 PM	8	0	32	0	40	38	13	0	0	51	0	0	0	0	0	0	4	7	0	11	102
3:15:00 PM	3	0	31	0	34	28	7	0	0	35	0	0	0	0	0	0	3	17	0	20	89
Total Volume	19	0	107	0	126	102	35	0	0	137	0	0	0	0	0	0	19	44	0	63	326
% App. Total	15.1	0	84.9	0		74.5	25.5	0	0		0	0	0	0	0	0	30.2	69.8	0		
PHF	.594	.000	.836	.000	.788	.671	.673	.000	.000	.672	.000	.000	.000	.000	.000	.000	.792	.647	.000	.788	.799



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868


File Name : Waynoka PI - Waynoka Rd Mid
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 3

Start Time	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound				
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total


Peak Hour Analysis From 2:30:00 PM to 3:15:00 PM - Peak 1 of 1

Peak Hour for Each Approach Begins at:

	2:30:00 PM					2:30:00 PM					2:30:00 PM					2:30:00 PM				
+0 mins.	5	0	20	0	25	20	9	0	0	29	0	0	0	0	0	0	6	9	0	15
+5 mins.	3	0	24	0	27	16	6	0	0	22	0	0	0	0	0	0	6	11	0	17
+10 mins.	8	0	32	0	40	38	13	0	0	51	0	0	0	0	0	0	4	7	0	11
+15 mins.	3	0	31	0	34	28	7	0	0	35	0	0	0	0	0	0	3	17	0	20
Total Volume	19	0	107	0	126	102	35	0	0	137	0	0	0	0	0	0	19	44	0	63
% App. Total	15.1	0	84.9	0		74.5	25.5	0	0		0	0	0	0	0	0	30.2	69.8	0	
PHF	.594	.000	.836	.000	.788	.671	.673	.000	.000	.672	.000	.000	.000	.000	.000	.000	.792	.647	.000	.788



Peak Hour Data



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Waynoka PI - Waynoka Rd PM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 1

Groups Printed- Unshifted


	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
16:00	4	0	20	0	24	31	6	0	0	37	0	0	0	0	0	0	7	25	0	32	93
16:15	3	0	25	0	28	47	8	0	0	55	0	0	0	0	0	0	7	19	0	26	109
16:30	2	0	24	0	26	44	3	0	0	47	0	0	0	0	0	0	5	23	0	28	101
16:45	4	0	21	1	26	43	4	0	0	47	0	0	0	0	0	0	6	34	0	40	113
Total	13	0	90	1	104	165	21	0	0	186	0	0	0	0	0	0	25	101	0	126	416
17:00	2	0	23	0	25	32	1	0	0	33	0	0	0	0	0	0	9	50	0	59	117
17:15	3	0	20	0	23	40	3	0	0	43	0	0	0	0	0	0	8	18	0	26	92
17:30	3	0	23	0	26	42	1	0	0	43	0	0	0	0	0	0	3	8	0	11	80
17:45	3	0	28	0	31	18	2	0	0	20	0	0	0	0	0	0	3	14	0	17	68
Total	11	0	94	0	105	132	7	0	0	139	0	0	0	0	0	0	23	90	0	113	357
Grand Total	24	0	184	1	209	297	28	0	0	325	0	0	0	0	0	0	48	191	0	239	773
Apprch %	11.5	0	88	0.5		91.4	8.6	0	0		0	0	0	0	0	0	20.1	79.9	0		
Total %	3.1	0	23.8	0.1	27	38.4	3.6	0	0	42	0	0	0	0	0	0	6.2	24.7	0	30.9	

LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868

File Name : Waynoka PI - Waynoka Rd PM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 2

Start Time	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 4:00:00 PM to 5:45:00 PM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 4:15:00 PM																					
4:15:00 PM	3	0	25	0	28	47	8	0	0	55	0	0	0	0	0	0	7	19	0	26	109
4:30:00 PM	2	0	24	0	26	44	3	0	0	47	0	0	0	0	0	0	5	23	0	28	101
4:45:00 PM	4	0	21	1	26	43	4	0	0	47	0	0	0	0	0	0	6	34	0	40	113
5:00:00 PM	2	0	23	0	25	32	1	0	0	33	0	0	0	0	0	0	9	50	0	59	117
Total Volume	11	0	93	1	105	166	16	0	0	182	0	0	0	0	0	0	27	126	0	153	440
% App. Total	10.5	0	88.6	1	91.2	8.8	0	0	0	0	0	0	0	0	0	0	17.6	82.4	0	0	0
PHF	.688	.000	.930	.250	.938	.883	.500	.000	.000	.827	.000	.000	.000	.000	.000	.000	.750	.630	.000	.648	.940



LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304
 Colorado Springs, CO 80909
 719-633-2868


File Name : Waynoka PI - Waynoka Rd PM
 Site Code : S224370
 Start Date : 6/9/2022
 Page No : 3

Start Time	Waynoka PI Southbound					Waynoka Rd Westbound					Northbound					Waynoka Rd Eastbound				
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total


Peak Hour Analysis From 4:00:00 PM to 5:45:00 PM - Peak 1 of 1

Peak Hour for Each Approach Begins at:

	4:15:00 PM					4:00:00 PM					4:00:00 PM					4:15:00 PM					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
+0 mins.	3	0	25	0	28	31	6	0	0	37	0	0	0	0	0	0	7	19	0	26	
+5 mins.	2	0	24	0	26	47	8	0	0	55	0	0	0	0	0	0	5	23	0	28	
+10 mins.	4	0	21	1	26	44	3	0	0	47	0	0	0	0	0	0	6	34	0	40	
+15 mins.	2	0	23	0	25	43	4	0	0	47	0	0	0	0	0	0	9	50	0	59	
Total Volume	11	0	93	1	105	165	21	0	0	186	0	0	0	0	0	0	27	126	0	153	
% App. Total	10.5	0	88.6	1		88.7	11.3	0	0		0	0	0	0	0	0	17.6	82.4	0		
PHF	.688	.000	.930	.250	.938	.878	.656	.000	.000	.845	.000	.000	.000	.000	.000	.000	.750	.630	.000	.648	



Peak Hour Data



Levels of Service



Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

2022 Existing

AM

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	55	362	70	67	823	104	26	22	18	74	45	115
Future Volume (vph)	55	362	70	67	823	104	26	22	18	74	45	115
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (ft)	140		0	185		185	50		0	165		150
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (ft)	90			130			25			110		
Lane Util. Factor	1.00	0.91	0.91	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.963				0.850		0.937				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1770	4897	0	1770	5085	1583	1770	1745	0	1770	1863	1583
Flt Permitted	0.288			0.432			0.719			0.649		
Satd. Flow (perm)	536	4897	0	805	5085	1583	1339	1745	0	1209	1863	1583
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		73				109		20				125
Link Speed (mph)		40			40			30				30
Link Distance (ft)		497			574			515				591
Travel Time (s)		8.5			9.8			11.7				13.4
Peak Hour Factor	0.95	0.95	0.56	0.77	0.95	0.95	0.53	0.63	0.73	0.92	0.78	0.92
Adj. Flow (vph)	58	381	125	87	866	109	49	35	25	80	58	125
Shared Lane Traffic (%)												
Lane Group Flow (vph)	58	506	0	87	866	109	49	60	0	80	58	125
Enter Blocked Intersection	No											
Lane Alignment	Left	Left	Right									
Median Width(ft)		12			12			12				12
Link Offset(ft)		0			0			0				0
Crosswalk Width(ft)		16			16			16				16
Two way Left Turn Lane							Yes					
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15		9	15		9	15		9	15		9
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (ft)	20	100		20	100	20	20	100		20	100	20
Trailing Detector (ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Position(ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Size(ft)	20	6		20	6	20	20	6		20	6	20
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(ft)		94			94			94			94	
Detector 2 Size(ft)		6			6			6			6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt	NA		pm+pt	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	5	2		1	6		7	4		3	8	
Permitted Phases	2			6		6	4			8		8

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

2022 Existing

AM



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector Phase	5	2		1	6	6	7	4		3	8	8
Switch Phase												
Minimum Initial (s)	4.0	20.0		4.0	20.0	20.0	4.0	4.0		4.0	4.0	4.0
Minimum Split (s)	10.5	26.0		10.5	26.0	26.0	10.5	24.5		10.5	10.5	10.5
Total Split (s)	25.0	71.0		25.0	71.0	71.0	25.0	25.0		25.0	25.0	25.0
Total Split (%)	17.1%	48.6%		17.1%	48.6%	48.6%	17.1%	17.1%		17.1%	17.1%	17.1%
Maximum Green (s)	20.0	65.0		20.0	65.0	65.0	20.0	18.5		20.0	18.5	18.5
Yellow Time (s)	3.0	4.0		3.0	4.0	4.0	3.0	4.5		3.0	4.5	4.5
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	6.0		5.0	6.0	6.0	5.0	6.5		5.0	6.5	6.5
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Walk Time (s)		7.0			7.0	7.0		7.0			7.0	7.0
Flash Dont Walk (s)		11.0			11.0	11.0		11.0			11.0	11.0
Pedestrian Calls (#/hr)		0			0	0		0			0	0
Act Effect Green (s)	85.0	76.7		87.9	79.8	79.8	38.1	28.2		42.7	32.3	32.3
Actuated g/C Ratio	0.58	0.53		0.60	0.55	0.55	0.26	0.19		0.29	0.22	0.22
v/c Ratio	0.16	0.19		0.16	0.31	0.12	0.13	0.17		0.20	0.14	0.28
Control Delay	11.9	15.9		11.7	19.0	3.2	37.2	36.5		38.2	49.3	9.5
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	11.9	15.9		11.7	19.0	3.2	37.2	36.5		38.2	49.3	9.5
LOS	B	B		B	B	A	D	D		D	D	A
Approach Delay		15.5			16.8			36.8			27.0	
Approach LOS		B			B			D			C	
Queue Length 50th (ft)	20	76		31	165	0	33	32		55	46	0
Queue Length 95th (ft)	39	102		46	201	31	38	47		99	78	56
Internal Link Dist (ft)		417			494			435			511	
Turn Bay Length (ft)	140			185		185	50			165		150
Base Capacity (vph)	503	2606		633	2779	914	471	353		449	412	447
Starvation Cap Reductn	0	0		0	0	0	0	0		0	0	0
Spillback Cap Reductn	0	0		0	0	0	0	0		0	0	0
Storage Cap Reductn	0	0		0	0	0	0	0		0	0	0
Reduced v/c Ratio	0.12	0.19		0.14	0.31	0.12	0.10	0.17		0.18	0.14	0.28

Intersection Summary

Area Type: Other

Cycle Length: 146

Actuated Cycle Length: 146

Offset: 65 (45%), Referenced to phase 2:EBTL and 6:WBTL, Start of Yellow

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.31

Intersection Signal Delay: 18.8

Intersection LOS: B

Intersection Capacity Utilization 45.7%

ICU Level of Service A

Analysis Period (min) 15


Lanes, Volumes, Timings

2022 Existing

1: Waynoka Pl/Tutt Blvd & Constitution Ave

AM

Splits and Phases: 1: Waynoka Pl/Tutt Blvd & Constitution Ave



HCM 6th TWSC
5: Waynoka Rd & Waynoka PI

2022 Existing
AM

Intersection

Int Delay, s/veh 5.4

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	20	33	25	48	96	19
Future Vol, veh/h	20	33	25	48	96	19
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	24	40	30	58	116	23

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	88	0	-	0	147	59
Stage 1	-	-	-	-	59	-
Stage 2	-	-	-	-	88	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1508	-	-	-	845	1007
Stage 1	-	-	-	-	964	-
Stage 2	-	-	-	-	935	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1508	-	-	-	831	1007
Mov Cap-2 Maneuver	-	-	-	-	831	-
Stage 1	-	-	-	-	949	-
Stage 2	-	-	-	-	935	-

Approach	EB	WB	SB
HCM Control Delay, s	2.8	0	10
HCM LOS			B

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1508	-	-	-	856
HCM Lane V/C Ratio	0.016	-	-	-	0.162
HCM Control Delay (s)	7.4	0	-	-	10
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0	-	-	-	0.6

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

2022 Existing
AM

Intersection						
Int Delay, s/veh	2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	71	387	563	25	31	48
Future Vol, veh/h	71	387	563	25	31	48
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	93	77	74	73
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	118	416	605	32	42	66
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	637	0	-	0	1065	319
Stage 1	-	-	-	-	621	-
Stage 2	-	-	-	-	444	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	943	-	-	-	218	677
Stage 1	-	-	-	-	498	-
Stage 2	-	-	-	-	614	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	943	-	-	-	191	677
Mov Cap-2 Maneuver	-	-	-	-	316	-
Stage 1	-	-	-	-	436	-
Stage 2	-	-	-	-	614	-
Approach	EB	WB	SB			
HCM Control Delay, s	2.1	0	13.7			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	943	-	-	-	316	677
HCM Lane V/C Ratio	0.125	-	-	-	0.133	0.097
HCM Control Delay (s)	9.4	-	-	-	18.1	10.9
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.4	-	-	-	0.5	0.3

Lanes, Volumes, Timings
7: Powers Blvd & Waynoka Rd

2022 Existing
AM



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	0	26	1999	56	0	0
Future Volume (vph)	0	26	1999	56	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	0.91	0.91	1.00	1.00
Fr _t		0.865	0.996			
Flt Protected						
Satd. Flow (prot)	0	1611	5065	0	0	0
Flt Permitted						
Satd. Flow (perm)	0	1611	5065	0	0	0
Link Speed (mph)	35		55			55
Link Distance (ft)	712		355			265
Travel Time (s)	13.9		4.4			3.3
Peak Hour Factor	0.76	0.76	0.95	0.94	0.95	0.95
Adj. Flow (vph)	0	34	2104	60	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	34	2164	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(ft)	0		0			0
Link Offset(ft)	0		0			0
Crosswalk Width(ft)	16		16			16
Two way Left Turn Lane						
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15	9		9	15	
Sign Control	Stop		Free			Free
Intersection Summary						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	49.9%					
Analysis Period (min)	15					

HCM 6th TWSC
5: Waynoka Rd & Waynoka PI

2022 Existing
Mid

Intersection						
Int Delay, s/veh	5.3					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	44	19	35	102	107	19
Future Vol, veh/h	44	19	35	102	107	19
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	53	23	42	123	129	23
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	165	0	-	0	233	104
Stage 1	-	-	-	-	104	-
Stage 2	-	-	-	-	129	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1413	-	-	-	755	951
Stage 1	-	-	-	-	920	-
Stage 2	-	-	-	-	897	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1413	-	-	-	726	951
Mov Cap-2 Maneuver	-	-	-	-	726	-
Stage 1	-	-	-	-	885	-
Stage 2	-	-	-	-	897	-
Approach	EB	WB	SB			
HCM Control Delay, s	5.3	0	11			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1413	-	-	-	753	
HCM Lane V/C Ratio	0.038	-	-	-	0.202	
HCM Control Delay (s)	7.6	0	-	-	11	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.8	

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

2022 Existing
Mid

Intersection						
Int Delay, s/veh	2.5					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	67	543	392	40	42	104
Future Vol, veh/h	67	543	392	40	42	104
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	99	77	79	74
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	112	584	396	52	53	141
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	448	0	-	0	938	224
Stage 1	-	-	-	-	422	-
Stage 2	-	-	-	-	516	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	1109	-	-	-	263	779
Stage 1	-	-	-	-	629	-
Stage 2	-	-	-	-	564	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1109	-	-	-	236	779
Mov Cap-2 Maneuver	-	-	-	-	365	-
Stage 1	-	-	-	-	565	-
Stage 2	-	-	-	-	564	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.4	0	12.2			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1109	-	-	-	365	779
HCM Lane V/C Ratio	0.101	-	-	-	0.146	0.18
HCM Control Delay (s)	8.6	-	-	-	16.5	10.6
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.3	-	-	-	0.5	0.7

Lanes, Volumes, Timings
1: Constitution Ave

2022 Existing
Mid

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (ft)	140			185		185	50			165		150
Storage Lanes	1			1		1				1		1
Taper Length (ft)	90			130			25			110		
Lane Util. Factor	1.00	0.91	0.91	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt												
Flt Protected												
Satd. Flow (prot)	1863	5085	0	1863	5085	1863	1863	1863	0	1863	1863	1863
Flt Permitted												
Satd. Flow (perm)	1863	5085	0	1863	5085	1863	1863	1863	0	1863	1863	1863
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)												
Link Speed (mph)		40			40			30			30	
Link Distance (ft)		497			574			515			591	
Travel Time (s)		8.5			9.8			11.7			13.4	
Peak Hour Factor	0.95	0.95	0.56	0.77	0.95	0.95	0.53	0.63	0.73	0.92	0.78	0.92
Adj. Flow (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Enter Blocked Intersection	No											
Lane Alignment	Left	Left	Right									
Median Width(ft)		12			12			12			12	
Link Offset(ft)		0			0			0			0	
Crosswalk Width(ft)		16			16			16			16	
Two way Left Turn Lane								Yes				
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15		9	15		9	15		9	15		9
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (ft)	20	100		20	100	20	20	100		20	100	20
Trailing Detector (ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Position(ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Size(ft)	20	6		20	6	20	20	6		20	6	20
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(ft)		94			94			94			94	
Detector 2 Size(ft)		6			6			6			6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt		pm+pt		Perm	pm+pt			pm+pt			Perm
Protected Phases	5	2		1	6		7	4		3	8	
Permitted Phases	2		6		6	4			8		8	

Lanes, Volumes, Timings

2022 Existing

Mid

1: Constitution Ave



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector Phase	5	2		1	6	6	7	4		3	8	8
Switch Phase												
Minimum Initial (s)	4.0	20.0		4.0	20.0	20.0	4.0	4.0		4.0	4.0	4.0
Minimum Split (s)	10.5	26.0		10.5	26.0	26.0	10.5	24.5		10.5	10.5	10.5
Total Split (s)	25.0	71.0		25.0	71.0	71.0	25.0	25.0		25.0	25.0	25.0
Total Split (%)	17.1%	48.6%		17.1%	48.6%	48.6%	17.1%	17.1%		17.1%	17.1%	17.1%
Maximum Green (s)	20.0	65.0		20.0	65.0	65.0	20.0	18.5		20.0	18.5	18.5
Yellow Time (s)	3.0	4.0		3.0	4.0	4.0	3.0	4.5		3.0	4.5	4.5
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	6.0		5.0	6.0	6.0	5.0	6.5		5.0	6.5	6.5
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Walk Time (s)		7.0			7.0	7.0		7.0			7.0	7.0
Flash Dont Walk (s)		11.0			11.0	11.0		11.0			11.0	11.0
Pedestrian Calls (#/hr)		0			0	0		0			0	0
Act Effect Green (s)												
Actuated g/C Ratio												
v/c Ratio												
Control Delay												
Queue Delay												
Total Delay												
LOS												
Approach Delay												
Approach LOS												
Queue Length 50th (ft)												
Queue Length 95th (ft)												
Internal Link Dist (ft)	417				494			435			511	
Turn Bay Length (ft)												
Base Capacity (vph)												
Starvation Cap Reductn												
Spillback Cap Reductn												
Storage Cap Reductn												
Reduced v/c Ratio												
Intersection Summary												
Area Type:	Other											
Cycle Length:	146											
Actuated Cycle Length:	146											
Offset:	65 (45%), Referenced to phase 2:EBTL and 6:WBTL, Start of Yellow											
Natural Cycle:	75											
Control Type:	Actuated-Coordinated											
Maximum v/c Ratio:	0.00											
Intersection Signal Delay:	0.0				Intersection LOS: A							
Intersection Capacity Utilization	0.0%				ICU Level of Service A							
Analysis Period (min)	15											


Lanes, Volumes, Timings

2022 Existing

1: Constitution Ave

Mid

Splits and Phases: 1: Constitution Ave



Lanes, Volumes, Timings
7: Powers Blvd & Waynoka Rd

2022 Existing
Mid



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	0	49	2744	68	0	0
Future Volume (vph)	0	49	2744	68	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	0.91	0.91	1.00	1.00
Fr _t		0.865	0.996			
Flt Protected						
Satd. Flow (prot)	0	1611	5065	0	0	0
Flt Permitted						
Satd. Flow (perm)	0	1611	5065	0	0	0
Link Speed (mph)	35		55		55	
Link Distance (ft)	712		355		265	
Travel Time (s)	13.9		4.4		3.3	
Peak Hour Factor	0.76	0.76	0.95	0.94	0.95	0.95
Adj. Flow (vph)	0	64	2888	72	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	64	2960	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(ft)	0		0		0	
Link Offset(ft)	0		0		0	
Crosswalk Width(ft)	16		16		16	
Two way Left Turn Lane						
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15	9		9	15	
Sign Control	Stop		Free		Free	
Intersection Summary						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	64.5%					
Analysis Period (min)	15					

Intersection

Int Delay, s/veh 5.2

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	101	25	21	165	90	13
Future Vol, veh/h	101	25	21	165	90	13
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	87	87	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	122	30	24	190	108	16

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	214	0	-	0	393	119
Stage 1	-	-	-	-	119	-
Stage 2	-	-	-	-	274	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1356	-	-	-	611	933
Stage 1	-	-	-	-	906	-
Stage 2	-	-	-	-	772	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1356	-	-	-	555	933
Mov Cap-2 Maneuver	-	-	-	-	555	-
Stage 1	-	-	-	-	823	-
Stage 2	-	-	-	-	772	-

Approach	EB	WB	SB
HCM Control Delay, s	6.3	0	12.8
HCM LOS			B

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1356	-	-	-	585
HCM Lane V/C Ratio	0.09	-	-	-	0.212
HCM Control Delay (s)	7.9	0	-	-	12.8
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0.3	-	-	-	0.8

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

2022 Existing
PM

Intersection						
Int Delay, s/veh	2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	75	725	464	46	46	83
Future Vol, veh/h	75	725	464	46	46	83
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	93	77	91	87
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	125	780	499	60	51	95
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	559	0	-	0	1169	280
Stage 1	-	-	-	-	529	-
Stage 2	-	-	-	-	640	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	1008	-	-	-	186	717
Stage 1	-	-	-	-	555	-
Stage 2	-	-	-	-	487	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1008	-	-	-	163	717
Mov Cap-2 Maneuver	-	-	-	-	296	-
Stage 1	-	-	-	-	486	-
Stage 2	-	-	-	-	487	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.3	0	13.9			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1008	-	-	-	296	717
HCM Lane V/C Ratio	0.124	-	-	-	0.171	0.133
HCM Control Delay (s)	9.1	-	-	-	19.7	10.8
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.4	-	-	-	0.6	0.5

Lanes, Volumes, Timings
7: Powers Blvd & Waynoka Rd

2022 Existing
PM



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	0	22	2887	129	0	0
Future Volume (vph)	0	22	2887	129	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	0.91	0.91	1.00	1.00
Fr _t		0.865	0.994			
Flt Protected						
Satd. Flow (prot)	0	1611	5055	0	0	0
Flt Permitted						
Satd. Flow (perm)	0	1611	5055	0	0	0
Link Speed (mph)	35		55			55
Link Distance (ft)	712		355			265
Travel Time (s)	13.9		4.4			3.3
Peak Hour Factor	0.76	0.76	0.95	0.94	0.95	0.95
Adj. Flow (vph)	0	29	3039	137	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	29	3176	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(ft)	0		0			0
Link Offset(ft)	0		0			0
Crosswalk Width(ft)	16		16			16
Two way Left Turn Lane						
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15	9		9	15	
Sign Control	Stop		Free			Free
Intersection Summary						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	68.6%					
Analysis Period (min)	15					

Lanes, Volumes, Timings

ST Baseline

1: Waynoka Pl/Tutt Blvd & Constitution Ave

AM

	↑	→	↓	↗	↖	↙	↖	↑	↗	↓	↖	
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑↑		↑	↑↑↑	↑	↑	↑		↑	↑	↑
Traffic Volume (vph)	55	362	110	67	823	104	40	30	18	74	45	114
Future Volume (vph)	55	362	110	67	823	104	40	30	18	74	45	114
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (ft)	140		0	185		185	50		0	165		150
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (ft)	90			130			25			110		
Lane Util. Factor	1.00	0.91	0.91	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.949				0.850		0.949				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1770	4826	0	1770	5085	1583	1770	1768	0	1770	1863	1583
Flt Permitted	0.289			0.396			0.719			0.702		
Satd. Flow (perm)	538	4826	0	738	5085	1583	1339	1768	0	1308	1863	1583
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		115				109			15			124
Link Speed (mph)		40			40			30			30	
Link Distance (ft)		497			574			515			591	
Travel Time (s)		8.5			9.8			11.7			13.4	
Peak Hour Factor	0.95	0.95	0.56	0.77	0.95	0.95	0.53	0.63	0.73	0.92	0.78	0.92
Adj. Flow (vph)	58	381	196	87	866	109	75	48	25	80	58	124
Shared Lane Traffic (%)												
Lane Group Flow (vph)	58	577	0	87	866	109	75	73	0	80	58	124
Enter Blocked Intersection	No											
Lane Alignment	Left	Left	Right									
Median Width(ft)		12			12			12			12	
Link Offset(ft)		0			0			0			0	
Crosswalk Width(ft)		16			16			16			16	
Two way Left Turn Lane								Yes				
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15		9	15		9	15		9	15		9
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (ft)	20	100		20	100	20	20	100		20	100	20
Trailing Detector (ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Position(ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Size(ft)	20	6		20	6	20	20	6		20	6	20
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(ft)		94			94			94			94	
Detector 2 Size(ft)		6			6			6			6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt	NA		pm+pt	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	5	2		1	6		7	4		3	8	
Permitted Phases	2			6		6	4			8		8

ST Baseline AM

Synchro 11 Report

Lanes, Volumes, Timings

JAB

Lanes, Volumes, Timings

1: Waynoka Pl/Tutt Blvd & Constitution Ave

ST Baseline

AM



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector Phase	5	2		1	6	6	7	4		3	8	8
Switch Phase												
Minimum Initial (s)	4.0	20.0		4.0	20.0	20.0	4.0	4.0		4.0	4.0	4.0
Minimum Split (s)	10.5	26.0		10.5	26.0	26.0	10.5	24.5		10.5	10.5	10.5
Total Split (s)	25.0	71.0		25.0	71.0	71.0	25.0	25.0		25.0	25.0	25.0
Total Split (%)	17.1%	48.6%		17.1%	48.6%	48.6%	17.1%	17.1%		17.1%	17.1%	17.1%
Maximum Green (s)	20.0	65.0		20.0	65.0	65.0	20.0	18.5		20.0	18.5	18.5
Yellow Time (s)	3.0	4.0		3.0	4.0	4.0	3.0	4.5		3.0	4.5	4.5
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	6.0		5.0	6.0	6.0	5.0	6.5		5.0	6.5	6.5
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Walk Time (s)		7.0			7.0	7.0		7.0			7.0	7.0
Flash Dont Walk (s)		11.0			11.0	11.0		11.0			11.0	11.0
Pedestrian Calls (#/hr)		0			0	0		0			0	0
Act Effect Green (s)	85.0	76.7		87.9	79.8	79.8	39.7	28.2		40.3	28.5	28.5
Actuated g/C Ratio	0.58	0.53		0.60	0.55	0.55	0.27	0.19		0.28	0.20	0.20
v/c Ratio	0.15	0.22		0.17	0.31	0.12	0.19	0.21		0.20	0.16	0.30
Control Delay	11.9	15.0		11.8	19.0	3.2	38.1	42.0		38.2	51.4	10.3
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	11.9	15.0		11.8	19.0	3.2	38.1	42.0		38.2	51.4	10.3
LOS	B	B		B	B	A	D	D		D	D	B
Approach Delay		14.8			16.8			40.0			27.9	
Approach LOS		B			B			D			C	
Queue Length 50th (ft)	20	82		31	165	0	52	47		55	46	0
Queue Length 95th (ft)	39	110		46	201	31	53	63		99	79	58
Internal Link Dist (ft)		417			494			435			511	
Turn Bay Length (ft)	140			185		185	50			165		150
Base Capacity (vph)	504	2589		601	2779	914	471	353		466	363	408
Starvation Cap Reductn	0	0		0	0	0	0	0		0	0	0
Spillback Cap Reductn	0	0		0	0	0	0	0		0	0	0
Storage Cap Reductn	0	0		0	0	0	0	0		0	0	0
Reduced v/c Ratio	0.12	0.22		0.14	0.31	0.12	0.16	0.21		0.17	0.16	0.30

Intersection Summary

Area Type: Other

Cycle Length: 146

Actuated Cycle Length: 146

Offset: 65 (45%), Referenced to phase 2:EBTL and 6:WBTL, Start of Yellow

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.31

Intersection Signal Delay: 19.2

Intersection LOS: B

Intersection Capacity Utilization 45.7%

ICU Level of Service A

Analysis Period (min) 15


Lanes, Volumes, Timings

1: Waynoka Pl/Tutt Blvd & Constitution Ave

ST Baseline

AM

Splits and Phases: 1: Waynoka Pl/Tutt Blvd & Constitution Ave



HCM 6th TWSC
5: Waynoka Rd & Waynoka PI

ST Baseline
AM

Intersection

Int Delay, s/veh 6.1

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	5	5	5	75	125	15
Future Vol, veh/h	5	5	5	75	125	15
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	6	6	6	90	151	18

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	96	0	-	0	69	51
Stage 1	-	-	-	-	51	-
Stage 2	-	-	-	-	18	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1498	-	-	-	936	1017
Stage 1	-	-	-	-	971	-
Stage 2	-	-	-	-	1005	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1498	-	-	-	932	1017
Mov Cap-2 Maneuver	-	-	-	-	932	-
Stage 1	-	-	-	-	967	-
Stage 2	-	-	-	-	1005	-

Approach	EB	WB	SB			
HCM Control Delay, s	3.7	0	9.7			
HCM LOS			A			

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1498	-	-	-	940	
HCM Lane V/C Ratio	0.004	-	-	-	0.179	
HCM Control Delay (s)	7.4	0	-	-	9.7	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0	-	-	-	0.7	

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

ST Baseline
AM

Intersection

Int Delay, s/veh 2.4

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑ ↗	↑↑	↑↗		↗	↗
Traffic Vol, veh/h	100	387	563	25	31	50
Future Vol, veh/h	100	387	563	25	31	50
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	93	77	74	73
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	167	416	605	32	42	68

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	637	0	-
Stage 1	-	-	621
Stage 2	-	-	542
Critical Hdwy	4.14	-	6.84 6.94
Critical Hdwy Stg 1	-	-	5.84
Critical Hdwy Stg 2	-	-	5.84
Follow-up Hdwy	2.22	-	3.52 3.32
Pot Cap-1 Maneuver	943	-	188 677
Stage 1	-	-	498
Stage 2	-	-	547
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	943	-	155 677
Mov Cap-2 Maneuver	-	-	283
Stage 1	-	-	410
Stage 2	-	-	547

Approach	EB	WB	SB
HCM Control Delay, s	2.8	0	14.3
HCM LOS		B	

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	943	-	-	-	283	677
HCM Lane V/C Ratio	0.177	-	-	-	0.148	0.101
HCM Control Delay (s)	9.6	-	-	-	19.9	10.9
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.6	-	-	-	0.5	0.3

HCM 6th TWSC
5: Waynoka Rd & Waynoka PI

ST Baseline
Mid

Intersection

Int Delay, s/veh 4.7

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	10	15	15	140	125	10
Future Vol, veh/h	10	15	15	140	125	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	12	18	18	169	151	12

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	187	0	-
Stage 1	-	-	103
Stage 2	-	-	42
Critical Hdwy	4.12	-	6.42 6.22
Critical Hdwy Stg 1	-	-	5.42
Critical Hdwy Stg 2	-	-	5.42
Follow-up Hdwy	2.218	-	3.518 3.318
Pot Cap-1 Maneuver	1387	-	847 952
Stage 1	-	-	921
Stage 2	-	-	980
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1387	-	839 952
Mov Cap-2 Maneuver	-	-	839
Stage 1	-	-	913
Stage 2	-	-	980

Approach	EB	WB	SB
HCM Control Delay, s	3	0	10.3
HCM LOS			B

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1387	-	-	-	846
HCM Lane V/C Ratio	0.009	-	-	-	0.192
HCM Control Delay (s)	7.6	0	-	-	10.3
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0	-	-	-	0.7

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

ST Baseline
Mid

Intersection						
Int Delay, s/veh	2.9					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	90	543	392	40	42	120
Future Vol, veh/h	90	543	392	40	42	120
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	99	77	79	74
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	150	584	396	52	53	162
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	448	0	-	0	1014	224
Stage 1	-	-	-	-	422	-
Stage 2	-	-	-	-	592	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	1109	-	-	-	235	779
Stage 1	-	-	-	-	629	-
Stage 2	-	-	-	-	516	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1109	-	-	-	203	779
Mov Cap-2 Maneuver	-	-	-	-	334	-
Stage 1	-	-	-	-	544	-
Stage 2	-	-	-	-	516	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.8	0	12.5			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1109	-	-	-	334	779
HCM Lane V/C Ratio	0.135	-	-	-	0.159	0.208
HCM Control Delay (s)	8.8	-	-	-	17.8	10.8
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.5	-	-	-	0.6	0.8

HCM 6th TWSC
5: Waynoka Rd & Waynoka PI

ST Baseline
PM

Intersection

Int Delay, s/veh 2.8

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	12	5	3	294	90	8
Future Vol, veh/h	12	5	3	294	90	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	87	87	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	14	6	3	338	108	10

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	341	0	-	0	206	172
Stage 1	-	-	-	-	172	-
Stage 2	-	-	-	-	34	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1218	-	-	-	782	872
Stage 1	-	-	-	-	858	-
Stage 2	-	-	-	-	988	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1218	-	-	-	773	872
Mov Cap-2 Maneuver	-	-	-	-	773	-
Stage 1	-	-	-	-	848	-
Stage 2	-	-	-	-	988	-

Approach	EB	WB	SB
HCM Control Delay, s	5.6	0	10.4
HCM LOS		B	

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1218	-	-	-	780
HCM Lane V/C Ratio	0.012	-	-	-	0.151
HCM Control Delay (s)	8	0	-	-	10.4
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0	-	-	-	0.5

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

ST Baseline
PM

Intersection

Int Delay, s/veh 2.2

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	100	725	464	46	46	90
Future Vol, veh/h	100	725	464	46	46	90
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	93	77	91	87
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	167	780	499	60	51	103

Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	559	0	-	0	1253	280
Stage 1	-	-	-	-	529	-
Stage 2	-	-	-	-	724	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	1008	-	-	-	164	717
Stage 1	-	-	-	-	555	-
Stage 2	-	-	-	-	441	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1008	-	-	-	137	717
Mov Cap-2 Maneuver	-	-	-	-	269	-
Stage 1	-	-	-	-	463	-
Stage 2	-	-	-	-	441	-

Approach	EB	WB	SB
HCM Control Delay, s	1.6	0	14.4
HCM LOS		B	

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	1008	-	-	-	269	717
HCM Lane V/C Ratio	0.165	-	-	-	0.188	0.144
HCM Control Delay (s)	9.3	-	-	-	21.5	10.9
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.6	-	-	-	0.7	0.5

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

ST Baseline + Site

AM

	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑↓		↑	↑↑↓	↑	↑	↑		↑	↑	↑
Traffic Volume (vph)	55	362	148	103	823	104	101	33	32	74	68	115
Future Volume (vph)	55	362	148	103	823	104	101	33	32	74	68	115
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (ft)	140		0	185		185	50		0	165		150
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (ft)	90			130			25			110		
Lane Util. Factor	1.00	0.91	0.91	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.950				0.850			0.923			0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1770	4831	0	1770	5085	1583	1770	1719	0	1770	1863	1583
Flt Permitted	0.296			0.387			0.575			0.701		
Satd. Flow (perm)	551	4831	0	721	5085	1583	1071	1719	0	1306	1863	1583
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		112				109			30			125
Link Speed (mph)		40			40			30			30	
Link Distance (ft)		497			574			515			591	
Travel Time (s)		8.5			9.8			11.7			13.4	
Peak Hour Factor	0.95	0.95	0.77	0.77	0.95	0.95	0.61	0.78	0.73	0.92	0.78	0.92
Adj. Flow (vph)	58	381	192	134	866	109	166	42	44	80	87	125
Shared Lane Traffic (%)												
Lane Group Flow (vph)	58	573	0	134	866	109	166	86	0	80	87	125
Enter Blocked Intersection	No											
Lane Alignment	Left	Left	Right									
Median Width(ft)		12			12			12			12	
Link Offset(ft)		0			0			0			0	
Crosswalk Width(ft)		16			16			16			16	
Two way Left Turn Lane								Yes				
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15		9	15		9	15		9	15		9
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (ft)	20	100		20	100	20	20	100		20	100	20
Trailing Detector (ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Position(ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Size(ft)	20	6		20	6	20	20	6		20	6	20
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(ft)		94			94			94			94	
Detector 2 Size(ft)		6			6			6			6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt	NA		pm+pt	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	5	2		1	6		7	4		3	8	
Permitted Phases	2			6		6	4			8		8

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

ST Baseline + Site

AM



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector Phase	5	2		1	6	6	7	4		3	8	8
Switch Phase												
Minimum Initial (s)	4.0	20.0		4.0	20.0	20.0	4.0	4.0		4.0	4.0	4.0
Minimum Split (s)	10.5	26.0		10.5	26.0	26.0	10.5	24.5		10.5	10.5	10.5
Total Split (s)	25.0	71.0		25.0	71.0	71.0	25.0	25.0		25.0	25.0	25.0
Total Split (%)	17.1%	48.6%		17.1%	48.6%	48.6%	17.1%	17.1%		17.1%	17.1%	17.1%
Maximum Green (s)	20.0	65.0		20.0	65.0	65.0	20.0	18.5		20.0	18.5	18.5
Yellow Time (s)	3.0	4.0		3.0	4.0	4.0	3.0	4.5		3.0	4.5	4.5
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	6.0		5.0	6.0	6.0	5.0	6.5		5.0	6.5	6.5
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Walk Time (s)		7.0			7.0	7.0		7.0			7.0	7.0
Flash Dont Walk (s)		11.0			11.0	11.0		11.0			11.0	11.0
Pedestrian Calls (#/hr)		0			0	0		0			0	0
Act Effect Green (s)	83.3	75.0		89.4	79.8	79.8	44.7	28.2		34.6	22.8	22.8
Actuated g/C Ratio	0.57	0.51		0.61	0.55	0.55	0.31	0.19		0.24	0.16	0.16
v/c Ratio	0.15	0.23		0.26	0.31	0.12	0.41	0.24		0.23	0.30	0.36
Control Delay	12.0	15.9		12.6	19.0	3.2	42.1	35.5		39.0	59.2	12.0
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	12.0	15.9		12.6	19.0	3.2	42.1	35.5		39.0	59.2	12.0
LOS	B	B		B	B	A	D	D		D	E	B
Approach Delay		15.5			16.7			39.9			33.5	
Approach LOS		B			B			D			C	
Queue Length 50th (ft)	20	84		49	165	0	121	45		55	74	0
Queue Length 95th (ft)	39	114		67	201	31	120	82		99	115	61
Internal Link Dist (ft)		417			494			435			511	
Turn Bay Length (ft)	140			185		185	50			165		150
Base Capacity (vph)	510	2534		593	2779	914	425	356		449	291	352
Starvation Cap Reductn	0	0		0	0	0	0	0		0	0	0
Spillback Cap Reductn	0	0		0	0	0	0	0		0	0	0
Storage Cap Reductn	0	0		0	0	0	0	0		0	0	0
Reduced v/c Ratio	0.11	0.23		0.23	0.31	0.12	0.39	0.24		0.18	0.30	0.36

Intersection Summary

Area Type: Other

Cycle Length: 146

Actuated Cycle Length: 146

Offset: 65 (45%), Referenced to phase 2:EBTL and 6:WBTL, Start of Yellow

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.41

Intersection Signal Delay: 21.1

Intersection LOS: C

Intersection Capacity Utilization 49.2%

ICU Level of Service A

Analysis Period (min) 15


Lanes, Volumes, Timings

ST Baseline + Site

1: Waynoka Pl/Tutt Blvd & Constitution Ave

AM

Splits and Phases: 1: Waynoka Pl/Tutt Blvd & Constitution Ave



HCM 6th TWSC
2: Waynoka PI & Middle Access

ST Baseline + Site
AM

Intersection

Int Delay, s/veh 4.6

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑
Traffic Vol, veh/h	89	52	4	156	150	4
Future Vol, veh/h	89	52	4	156	150	4
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	59	84	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	178	104	8	264	179	8

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	463	183	187	0	-	0
Stage 1	183	-	-	-	-	-
Stage 2	280	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	557	859	1387	-	-	-
Stage 1	848	-	-	-	-	-
Stage 2	767	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	553	859	1387	-	-	-
Mov Cap-2 Maneuver	617	-	-	-	-	-
Stage 1	842	-	-	-	-	-
Stage 2	767	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	11.9	0.2	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT	SBR
Capacity (veh/h)	1387	-	617	859	-	-
HCM Lane V/C Ratio	0.006	-	0.288	0.121	-	-
HCM Control Delay (s)	7.6	-	13.2	9.8	-	-
HCM Lane LOS	A	-	B	A	-	-
HCM 95th %tile Q(veh)	0	-	1.2	0.4	-	-

HCM 6th TWSC
3: Waynoka PI & North Access

ST Baseline + Site
AM

Intersection

Int Delay, s/veh 1.5

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		↑	↑	↑	
Traffic Vol, veh/h	0	0	67	177	154	93
Future Vol, veh/h	0	0	67	177	154	93
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	100	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	88	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	134	272	175	186

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	808	268	361	0	-	0
Stage 1	268	-	-	-	-	-
Stage 2	540	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	350	771	1198	-	-	-
Stage 1	777	-	-	-	-	-
Stage 2	584	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	311	771	1198	-	-	-
Mov Cap-2 Maneuver	429	-	-	-	-	-
Stage 1	690	-	-	-	-	-
Stage 2	584	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	0	2.8	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1198	-	-	-	-
HCM Lane V/C Ratio	0.112	-	-	-	-
HCM Control Delay (s)	8.4	-	0	-	-
HCM Lane LOS	A	-	A	-	-
HCM 95th %tile Q(veh)	0.4	-	-	-	-

HCM 6th TWSC
4: Waynoka PI & South Access

ST Baseline + Site
AM

Intersection

Int Delay, s/veh 0.9

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	11	6	8	147	192	11
Future Vol, veh/h	11	6	8	147	192	11
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	50	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	60	92	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	22	12	16	245	209	22

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	497	220	231	0	-	0
Stage 1	220	-	-	-	-	-
Stage 2	277	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	532	820	1337	-	-	-
Stage 1	817	-	-	-	-	-
Stage 2	770	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	526	820	1337	-	-	-
Mov Cap-2 Maneuver	599	-	-	-	-	-
Stage 1	807	-	-	-	-	-
Stage 2	770	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	10.7	0.5	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1337	-	662	-	-
HCM Lane V/C Ratio	0.012	-	0.051	-	-
HCM Control Delay (s)	7.7	-	10.7	-	-
HCM Lane LOS	A	-	B	-	-
HCM 95th %tile Q(veh)	0	-	0.2	-	-

Intersection

Int Delay, s/veh 6.1

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	5	5	5	150	184	15
Future Vol, veh/h	5	5	5	150	184	15
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	78	54	64	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	6	6	6	278	288	19

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	284	0	-
Stage 1	-	-	145
Stage 2	-	-	18
Critical Hdwy	4.12	-	6.42 6.22
Critical Hdwy Stg 1	-	-	5.42
Critical Hdwy Stg 2	-	-	5.42
Follow-up Hdwy	2.218	-	3.518 3.318
Pot Cap-1 Maneuver	1278	-	828 902
Stage 1	-	-	882
Stage 2	-	-	1005
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1278	-	824 902
Mov Cap-2 Maneuver	-	-	824
Stage 1	-	-	878
Stage 2	-	-	1005

Approach	EB	WB	SB
HCM Control Delay, s	3.9	0	11.9
HCM LOS			B

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1278	-	-	-	828
HCM Lane V/C Ratio	0.005	-	-	-	0.37
HCM Control Delay (s)	7.8	0	-	-	11.9
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0	-	-	-	1.7

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

ST Baseline + Site
AM

Intersection

Int Delay, s/veh 3.8

Movement	EBL	EBT	WBT	WBR	SBL	SBR
----------	-----	-----	-----	-----	-----	-----

Lane Configurations 

Traffic Vol, veh/h 168 387 563 39 55 85

Future Vol, veh/h 168 387 563 39 55 85

Conflicting Peds, #/hr 0 0 0 0 0 0

Sign Control Free Free Free Free Stop Stop

RT Channelized - None - None - None

Storage Length 100 - - - 0 0

Veh in Median Storage, # - 0 0 - 0 -

Grade, % - 0 0 - 0 -

Peak Hour Factor 72 93 93 77 74 74

Heavy Vehicles, % 2 2 2 2 2 2

Mvmt Flow 233 416 605 51 74 115

Major/Minor	Major1	Major2	Minor2
-------------	--------	--------	--------

Conflicting Flow All 656 0 - 0 1305 328

 Stage 1 - - - - 631 -

 Stage 2 - - - - 674 -

Critical Hdwy 4.14 - - - 6.84 6.94

Critical Hdwy Stg 1 - - - - 5.84 -

Critical Hdwy Stg 2 - - - - 5.84 -

Follow-up Hdwy 2.22 - - - 3.52 3.32

Pot Cap-1 Maneuver 927 - - - 152 668

 Stage 1 - - - - 492 -

 Stage 2 - - - - 468 -

Platoon blocked, % - - - -

Mov Cap-1 Maneuver 927 - - - 114 668

Mov Cap-2 Maneuver - - - - 239 -

 Stage 1 - - - - 369 -

 Stage 2 - - - - 468 -

Approach	EB	WB	SB
----------	----	----	----

HCM Control Delay, s 3.7 0 17.5

HCM LOS C

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
-----------------------	-----	-----	-----	-----	-------	-------

Capacity (veh/h) 927 - - - 239 668

HCM Lane V/C Ratio 0.252 - - - 0.311 0.172

HCM Control Delay (s) 10.2 - - - 26.7 11.5

HCM Lane LOS B - - - D B

HCM 95th %tile Q(veh) 1 - - - 1.3 0.6

HCM 6th TWSC
2: Waynoka PI & Middle Access

ST Baseline + Site
Mid

Intersection

Int Delay, s/veh 3.9

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	
Traffic Vol, veh/h	74	43	3	205	143	0
Future Vol, veh/h	74	43	3	205	143	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	85	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	148	86	6	315	168	0

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	495	168	168	0	-	0
Stage 1	168	-	-	-	-	-
Stage 2	327	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	534	876	1410	-	-	0
Stage 1	862	-	-	-	-	0
Stage 2	731	-	-	-	-	0
Platoon blocked, %				-	-	-
Mov Cap-1 Maneuver	531	876	1410	-	-	-
Mov Cap-2 Maneuver	598	-	-	-	-	-
Stage 1	858	-	-	-	-	-
Stage 2	731	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	11.8	0.1	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	EBLn2	SBT
Capacity (veh/h)	1410	-	598	876	-
HCM Lane V/C Ratio	0.004	-	0.247	0.098	-
HCM Control Delay (s)	7.6	-	13	9.6	-
HCM Lane LOS	A	-	B	A	-
HCM 95th %tile Q(veh)	0	-	1	0.3	-

HCM 6th TWSC
3: Waynoka PI & North Access

ST Baseline + Site
Mid

Intersection

Int Delay, s/veh 1.1

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	0	0	49	230	145	68
Future Vol, veh/h	0	0	49	230	145	68
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	100	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	68	83	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	98	338	175	136

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	777	243	311	0	-	0
Stage 1	243	-	-	-	-	-
Stage 2	534	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	365	796	1249	-	-	-
Stage 1	797	-	-	-	-	-
Stage 2	588	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	337	796	1249	-	-	-
Mov Cap-2 Maneuver	448	-	-	-	-	-
Stage 1	735	-	-	-	-	-
Stage 2	588	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	0	1.8	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1249	-	-	-	-
HCM Lane V/C Ratio	0.078	-	-	-	-
HCM Control Delay (s)	8.1	-	0	-	-
HCM Lane LOS	A	-	A	-	-
HCM 95th %tile Q(veh)	0.3	-	-	-	-

HCM 6th TWSC
4: Waynoka PI & South Access

ST Baseline + Site
Mid

Intersection						
Int Delay, s/veh	0.7					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	9	5	6	199	178	8
Future Vol, veh/h	9	5	6	199	178	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	50	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	92	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	18	10	12	306	193	16
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	531	201	209	0	-	0
Stage 1	201	-	-	-	-	-
Stage 2	330	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	509	840	1362	-	-	-
Stage 1	833	-	-	-	-	-
Stage 2	728	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	504	840	1362	-	-	-
Mov Cap-2 Maneuver	581	-	-	-	-	-
Stage 1	826	-	-	-	-	-
Stage 2	728	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	10.8	0.3	0			
HCM LOS	B					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1362	-	653	-	-	
HCM Lane V/C Ratio	0.009	-	0.043	-	-	
HCM Control Delay (s)	7.7	-	10.8	-	-	
HCM Lane LOS	A	-	B	-	-	
HCM 95th %tile Q(veh)	0	-	0.1	-	-	

Intersection						
Int Delay, s/veh	5.2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	10	15	15	195	173	10
Future Vol, veh/h	10	15	15	195	173	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	78	62	71	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	13	19	19	315	244	13
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	334	0	-	0	222	177
Stage 1	-	-	-	-	177	-
Stage 2	-	-	-	-	45	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1225	-	-	-	766	866
Stage 1	-	-	-	-	854	-
Stage 2	-	-	-	-	977	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1225	-	-	-	758	866
Mov Cap-2 Maneuver	-	-	-	-	758	-
Stage 1	-	-	-	-	845	-
Stage 2	-	-	-	-	977	-
Approach	EB	WB	SB			
HCM Control Delay, s	3.2	0	12.1			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1225	-	-	-	763	
HCM Lane V/C Ratio	0.01	-	-	-	0.336	
HCM Control Delay (s)	8	0	-	-	12.1	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0	-	-	-	1.5	

HCM 6th TWSC
6: Palmer Park Blvd & Waynoka Rd

ST Baseline + Site
Mid

Intersection

Int Delay, s/veh 3.6

Movement	EBL	EBT	WBT	WBR	SBL	SBR
----------	-----	-----	-----	-----	-----	-----

Lane Configurations 

Traffic Vol, veh/h 140 543 392 50 62 149

Future Vol, veh/h 140 543 392 50 62 149

Conflicting Peds, #/hr 0 0 0 0 0 0

Sign Control Free Free Free Free Stop Stop

RT Channelized - None - None - None

Storage Length 100 - - - 0 0

Veh in Median Storage, # - 0 0 - 0 -

Grade, % - 0 0 - 0 -

Peak Hour Factor 72 93 93 77 79 83

Heavy Vehicles, % 2 2 2 2 2 2

Mvmt Flow 194 584 422 65 78 180

Major/Minor	Major1	Major2	Minor2
-------------	--------	--------	--------

Conflicting Flow All 487 0 - 0 1135 244

 Stage 1 - - - - 455 -

 Stage 2 - - - - 680 -

Critical Hdwy 4.14 - - - 6.84 6.94

Critical Hdwy Stg 1 - - - - 5.84 -

Critical Hdwy Stg 2 - - - - 5.84 -

Follow-up Hdwy 2.22 - - - 3.52 3.32

Pot Cap-1 Maneuver 1072 - - - 196 757

 Stage 1 - - - - 606 -

 Stage 2 - - - - 465 -

Platoon blocked, % - - -

Mov Cap-1 Maneuver 1072 - - - 161 757

Mov Cap-2 Maneuver - - - - 292 -

 Stage 1 - - - - 496 -

 Stage 2 - - - - 465 -

Approach	EB	WB	SB
----------	----	----	----

HCM Control Delay, s 2.3 0 14.4

HCM LOS B

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
-----------------------	-----	-----	-----	-----	-------	-------

Capacity (veh/h) 1072 - - - 292 757

HCM Lane V/C Ratio 0.181 - - - 0.269 0.237

HCM Control Delay (s) 9.1 - - - 21.8 11.2

HCM Lane LOS A - - - C B

HCM 95th %tile Q(veh) 0.7 - - - 1.1 0.9

HCM 6th TWSC
2: Waynoka PI & Middle Access

ST Baseline + Site
PM

Intersection

Int Delay, s/veh 0.3

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑	↑	↑	↑		
Traffic Vol, veh/h	4	2	0	309	98	0
Future Vol, veh/h	4	2	0	309	98	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	85	87	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	8	4	0	364	113	0

Major/Minor	Minor2	Major1	Major2		
Conflicting Flow All	477	113	-	0	-
Stage 1	113	-	-	-	-
Stage 2	364	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	-
Pot Cap-1 Maneuver	547	940	0	-	0
Stage 1	912	-	0	-	0
Stage 2	703	-	0	-	0
Platoon blocked, %			-	-	-
Mov Cap-1 Maneuver	547	940	-	-	-
Mov Cap-2 Maneuver	599	-	-	-	-
Stage 1	912	-	-	-	-
Stage 2	703	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	10.3	0	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	EBLn1	EBLn2	SBT
Capacity (veh/h)	-	599	940	-
HCM Lane V/C Ratio	-	0.013	0.004	-
HCM Control Delay (s)	-	11.1	8.8	-
HCM Lane LOS	-	B	A	-
HCM 95th %tile Q(veh)	-	0	0	-

Intersection

Int Delay, s/veh 0.1

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	0	0	2	310	99	3
Future Vol, veh/h	0	0	2	310	99	3
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	100	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	85	83	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	4	365	119	6

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	495	122	125	0	-	0
Stage 1	122	-	-	-	-	-
Stage 2	373	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	534	929	1462	-	-	-
Stage 1	903	-	-	-	-	-
Stage 2	696	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	532	929	1462	-	-	-
Mov Cap-2 Maneuver	589	-	-	-	-	-
Stage 1	900	-	-	-	-	-
Stage 2	696	-	-	-	-	-

Approach	EB	NB	SB
HCM Control Delay, s	0	0.1	0
HCM LOS	A		

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1462	-	-	-	-
HCM Lane V/C Ratio	0.003	-	-	-	-
HCM Control Delay (s)	7.5	-	0	-	-
HCM Lane LOS	A	-	A	-	-
HCM 95th %tile Q(veh)	0	-	-	-	-

HCM 6th TWSC
4: Waynoka PI & South Access

ST Baseline + Site
PM

Intersection

Int Delay, s/veh 0

Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	0	0	0	308	100	0
Future Vol, veh/h	0	0	0	308	100	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	50	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	85	92	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	0	362	109	0

Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	471	109	109	0	-	0
Stage 1	109	-	-	-	-	-
Stage 2	362	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	551	945	1481	-	-	-
Stage 1	916	-	-	-	-	-
Stage 2	704	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	551	945	1481	-	-	-
Mov Cap-2 Maneuver	601	-	-	-	-	-
Stage 1	916	-	-	-	-	-
Stage 2	704	-	-	-	-	-

Approach	EB	NB	SB
----------	----	----	----

HCM Control Delay, s 0 0 0

HCM LOS A

Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1481	-	-	-	-
HCM Lane V/C Ratio	-	-	-	-	-
HCM Control Delay (s)	0	-	0	-	-
HCM Lane LOS	A	-	A	-	-
HCM 95th %tile Q(veh)	0	-	-	-	-

Intersection

Int Delay, s/veh 2.7

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	12	5	3	297	92	8
Future Vol, veh/h	12	5	3	297	92	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	78	91	91	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	15	6	4	326	101	10

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	330	0	-
Stage 1	-	-	167
Stage 2	-	-	36
Critical Hdwy	4.12	-	6.42 6.22
Critical Hdwy Stg 1	-	-	5.42
Critical Hdwy Stg 2	-	-	5.42
Follow-up Hdwy	2.218	-	3.518 3.318
Pot Cap-1 Maneuver	1229	-	786 877
Stage 1	-	-	863
Stage 2	-	-	986
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1229	-	777 877
Mov Cap-2 Maneuver	-	-	777
Stage 1	-	-	853
Stage 2	-	-	986

Approach	EB	WB	SB
HCM Control Delay, s	5.6	0	10.3
HCM LOS		B	

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1229	-	-	-	785
HCM Lane V/C Ratio	0.013	-	-	-	0.142
HCM Control Delay (s)	8	0	-	-	10.3
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0	-	-	-	0.5

Intersection						
Int Delay, s/veh	2.1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	102	725	464	47	47	91
Future Vol, veh/h	102	725	464	47	47	91
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	72	93	93	77	91	91
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	142	780	499	61	52	100
Major/Minor						
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	560	0	-	0	1204	280
Stage 1	-	-	-	-	530	-
Stage 2	-	-	-	-	674	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	1007	-	-	-	177	717
Stage 1	-	-	-	-	555	-
Stage 2	-	-	-	-	468	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1007	-	-	-	152	717
Mov Cap-2 Maneuver	-	-	-	-	285	-
Stage 1	-	-	-	-	477	-
Stage 2	-	-	-	-	468	-
Approach						
Approach	EB	WB	SB			
HCM Control Delay, s	1.4	0	14.1			
HCM LOS			B			
Minor Lane/Major Mvmt		EBL	EBT	WBT	WBR	SBLn1 SBLn2
Capacity (veh/h)	1007	-	-	-	285	717
HCM Lane V/C Ratio	0.141	-	-	-	0.181	0.139
HCM Control Delay (s)	9.2	-	-	-	20.4	10.8
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.5	-	-	-	0.7	0.5

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

2042 Background

AM

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	100	650	100	75	1300	150	65	75	25	100	90	230
Future Volume (vph)	100	650	100	75	1300	150	65	75	25	100	90	230
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (ft)	140			185		185	50		0	165		150
Storage Lanes	1			1		1	1		0	1		1
Taper Length (ft)	90			130			25			110		
Lane Util. Factor	1.00	0.91	0.91	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.969				0.850		0.967				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1770	4928	0	1770	5085	1583	1770	1801	0	1770	1863	1583
Flt Permitted	0.134			0.281			0.615			0.563		
Satd. Flow (perm)	250	4928	0	523	5085	1583	1146	1801	0	1049	1863	1583
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		58				118			8			250
Link Speed (mph)		40			40			30			30	
Link Distance (ft)		497			574			515			591	
Travel Time (s)		8.5			9.8			11.7			13.4	
Peak Hour Factor	0.95	0.95	0.56	0.77	0.95	0.95	0.53	0.63	0.73	0.92	0.78	0.92
Adj. Flow (vph)	105	684	179	97	1368	158	123	119	34	109	115	250
Shared Lane Traffic (%)												
Lane Group Flow (vph)	105	863	0	97	1368	158	123	153	0	109	115	250
Enter Blocked Intersection	No											
Lane Alignment	Left	Left	Right									
Median Width(ft)		12			12			12			12	
Link Offset(ft)		0			0			0			0	
Crosswalk Width(ft)		16			16			16			16	
Two way Left Turn Lane								Yes				
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15		9	15		9	15		9	15		9
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (ft)	20	100		20	100	20	20	100		20	100	20
Trailing Detector (ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Position(ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Size(ft)	20	6		20	6	20	20	6		20	6	20
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(ft)		94			94			94			94	
Detector 2 Size(ft)		6			6			6			6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt	NA		pm+pt	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	5	2		1	6		7	4		3	8	
Permitted Phases	2			6		6	4			8		8

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

2042 Background

AM



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector Phase	5	2		1	6	6	7	4		3	8	8
Switch Phase												
Minimum Initial (s)	4.0	20.0		4.0	20.0	20.0	4.0	4.0		4.0	4.0	4.0
Minimum Split (s)	10.5	26.0		10.5	26.0	26.0	10.5	24.5		10.5	10.5	10.5
Total Split (s)	25.0	71.0		25.0	71.0	71.0	25.0	25.0		25.0	25.0	25.0
Total Split (%)	17.1%	48.6%		17.1%	48.6%	48.6%	17.1%	17.1%		17.1%	17.1%	17.1%
Maximum Green (s)	20.0	65.0		20.0	65.0	65.0	20.0	18.5		20.0	18.5	18.5
Yellow Time (s)	3.0	4.0		3.0	4.0	4.0	3.0	4.5		3.0	4.5	4.5
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	6.0		5.0	6.0	6.0	5.0	6.5		5.0	6.5	6.5
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Walk Time (s)		7.0			7.0	7.0		7.0			7.0	7.0
Flash Dont Walk (s)		11.0			11.0	11.0		11.0			11.0	11.0
Pedestrian Calls (#/hr)		0			0	0		0			0	0
Act Effect Green (s)	86.3	76.3		85.7	76.0	76.0	40.9	26.3		39.1	25.4	25.4
Actuated g/C Ratio	0.59	0.52		0.59	0.52	0.52	0.28	0.18		0.27	0.17	0.17
v/c Ratio	0.44	0.33		0.26	0.52	0.18	0.33	0.46		0.32	0.35	0.52
Control Delay	17.0	19.2		12.8	24.0	6.1	40.4	56.9		40.3	57.9	10.4
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	17.0	19.2		12.8	24.0	6.1	40.4	56.9		40.3	57.9	10.4
LOS	B	B		B	C	A	D	E		D	E	B
Approach Delay		18.9			21.6			49.5			28.8	
Approach LOS		B			C			D			C	
Queue Length 50th (ft)	38	156		35	304	18	87	125		77	97	0
Queue Length 95th (ft)	64	195		50	360	58	80	136		128	143	83
Internal Link Dist (ft)		417			494			435			511	
Turn Bay Length (ft)	140			185		185	50			165		150
Base Capacity (vph)	364	2604		496	2648	880	436	331		418	324	482
Starvation Cap Reductn	0	0		0	0	0	0	0		0	0	0
Spillback Cap Reductn	0	0		0	0	0	0	0		0	0	0
Storage Cap Reductn	0	0		0	0	0	0	0		0	0	0
Reduced v/c Ratio	0.29	0.33		0.20	0.52	0.18	0.28	0.46		0.26	0.35	0.52

Intersection Summary

Area Type: Other

Cycle Length: 146

Actuated Cycle Length: 146

Offset: 65 (45%), Referenced to phase 2:EBTL and 6:WBTL, Start of Yellow

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.52

Intersection Signal Delay: 24.1

Intersection LOS: C

Intersection Capacity Utilization 57.5%

ICU Level of Service B


Analysis Period (min) 15

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

2042 Background

AM

Splits and Phases: 1: Waynoka Pl/Tutt Blvd & Constitution Ave



Intersection						
Int Delay, s/veh	5.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	5	5	5	100	135	15
Future Vol, veh/h	5	5	5	100	135	15
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	6	6	6	120	163	18
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	126	0	-	0	84	66
Stage 1	-	-	-	-	66	-
Stage 2	-	-	-	-	18	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1460	-	-	-	918	998
Stage 1	-	-	-	-	957	-
Stage 2	-	-	-	-	1005	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1460	-	-	-	914	998
Mov Cap-2 Maneuver	-	-	-	-	914	-
Stage 1	-	-	-	-	953	-
Stage 2	-	-	-	-	1005	-
Approach	EB	WB	SB			
HCM Control Delay, s	3.7	0	9.9			
HCM LOS			A			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1460	-	-	-	922	
HCM Lane V/C Ratio	0.004	-	-	-	0.196	
HCM Control Delay (s)	7.5	0	-	-	9.9	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0	-	-	-	0.7	

Intersection						
Int Delay, s/veh	2.5					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	125	500	635	35	40	15
Future Vol, veh/h	125	500	635	35	40	15
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	93	77	74	73
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	208	538	683	45	54	21
Major/Minor						
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	728	0	-	0	1391	364
Stage 1	-	-	-	-	706	-
Stage 2	-	-	-	-	685	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	871	-	-	-	133	633
Stage 1	-	-	-	-	450	-
Stage 2	-	-	-	-	462	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	871	-	-	-	101	633
Mov Cap-2 Maneuver	-	-	-	-	224	-
Stage 1	-	-	-	-	342	-
Stage 2	-	-	-	-	462	-
Approach						
Approach	EB	WB	SB			
HCM Control Delay, s	2.9	0	21.9			
HCM LOS			C			
Minor Lane/Major Mvmt		EBL	EBT	WBT	WBR	SBLn1 SBLn2
Capacity (veh/h)		871	-	-	-	224 633
HCM Lane V/C Ratio		0.239	-	-	-	0.241 0.032
HCM Control Delay (s)		10.4	-	-	-	26.1 10.9
HCM Lane LOS		B	-	-	-	D B
HCM 95th %tile Q(veh)		0.9	-	-	-	0.9 0.1

Intersection						
Int Delay, s/veh	3.8					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	10	15	15	265	140	10
Future Vol, veh/h	10	15	15	265	140	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	83	83	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	12	18	18	319	169	12
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	337	0	-	0	220	178
Stage 1	-	-	-	-	178	-
Stage 2	-	-	-	-	42	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1222	-	-	-	768	865
Stage 1	-	-	-	-	853	-
Stage 2	-	-	-	-	980	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1222	-	-	-	760	865
Mov Cap-2 Maneuver	-	-	-	-	760	-
Stage 1	-	-	-	-	844	-
Stage 2	-	-	-	-	980	-
Approach	EB	WB	SB			
HCM Control Delay, s	3.2	0	11.1			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1222	-	-	-	766	
HCM Lane V/C Ratio	0.01	-	-	-	0.236	
HCM Control Delay (s)	8	0	-	-	11.1	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0	-	-	-	0.9	

Intersection						
Int Delay, s/veh	2.8					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	90	675	550	50	50	130
Future Vol, veh/h	90	675	550	50	50	130
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	60	93	99	77	79	74
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	150	726	556	65	63	176
Major/Minor						
Conflicting Flow All	Major1	Major2		Minor2		
	621	0	-	0	1252	311
Stage 1	-	-	-	-	589	-
Stage 2	-	-	-	-	663	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	956	-	-	-	164	685
Stage 1	-	-	-	-	517	-
Stage 2	-	-	-	-	474	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	956	-	-	-	138	685
Mov Cap-2 Maneuver	-	-	-	-	270	-
Stage 1	-	-	-	-	436	-
Stage 2	-	-	-	-	474	-
Approach						
HCM Control Delay, s	EB	WB		SB		
	1.6	0		14.8		
HCM LOS				B		
Minor Lane/Major Mvmt		EBL	EBT	WBT	WBR	SBLn1 SBLn2
Capacity (veh/h)	956	-	-	-	270	685
HCM Lane V/C Ratio	0.157	-	-	-	0.234	0.256
HCM Control Delay (s)	9.5	-	-	-	22.4	12.1
HCM Lane LOS	A	-	-	-	C	B
HCM 95th %tile Q(veh)	0.6	-	-	-	0.9	1

Intersection						
Int Delay, s/veh	3.1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	12	5	3	308	107	8
Future Vol, veh/h	12	5	3	308	107	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	83	83	87	87	83	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	14	6	3	354	129	10
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	357	0	-	0	214	180
Stage 1	-	-	-	-	180	-
Stage 2	-	-	-	-	34	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1202	-	-	-	774	863
Stage 1	-	-	-	-	851	-
Stage 2	-	-	-	-	988	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1202	-	-	-	765	863
Mov Cap-2 Maneuver	-	-	-	-	765	-
Stage 1	-	-	-	-	841	-
Stage 2	-	-	-	-	988	-
Approach	EB	WB	SB			
HCM Control Delay, s	5.7	0	10.7			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1202	-	-	-	771	
HCM Lane V/C Ratio	0.012	-	-	-	0.18	
HCM Control Delay (s)	8	0	-	-	10.7	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0	-	-	-	0.7	

Intersection						
Int Delay, s/veh	2.6					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	115	950	700	60	60	125
Future Vol, veh/h	115	950	700	60	60	125
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	70	93	93	77	91	87
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	164	1022	753	78	66	144
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	831	0	-	0	1631	416
Stage 1	-	-	-	-	792	-
Stage 2	-	-	-	-	839	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	797	-	-	-	92	585
Stage 1	-	-	-	-	407	-
Stage 2	-	-	-	-	384	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	797	-	-	-	73	585
Mov Cap-2 Maneuver	-	-	-	-	193	-
Stage 1	-	-	-	-	323	-
Stage 2	-	-	-	-	384	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.5	0	19.4			
HCM LOS			C			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	797	-	-	-	193	585
HCM Lane V/C Ratio	0.206	-	-	-	0.342	0.246
HCM Control Delay (s)	10.7	-	-	-	33	13.1
HCM Lane LOS	B	-	-	-	D	B
HCM 95th %tile Q(veh)	0.8	-	-	-	1.4	1

Lanes, Volumes, Timings
1: Waynoka Pl/Tutt Blvd & Constitution Ave

2042 Background + Site

AM

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	100	650	175	147	1300	150	245	97	54	100	137	230
Future Volume (vph)	100	650	175	147	1300	150	245	97	54	100	137	230
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (ft)	140			0	185		185	50		0	165	
Storage Lanes	1			0	1		1	1		0	1	
Taper Length (ft)	90				130			25			110	
Lane Util. Factor	1.00	0.91	0.91	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.963				0.850			0.944			0.850
Flt Protected	0.950				0.950			0.950			0.950	
Satd. Flow (prot)	1770	4897	0	1770	5085	1583	1770	1758	0	1770	1863	1583
Flt Permitted	0.141				0.246			0.307			0.616	
Satd. Flow (perm)	263	4897	0	458	5085	1583	572	1758	0	1147	1863	1583
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		74				118			17			229
Link Speed (mph)		40			40			30			30	
Link Distance (ft)		497			574			515			591	
Travel Time (s)		8.5			9.8			11.7			13.4	
Peak Hour Factor	0.95	0.95	0.77	0.77	0.95	0.95	0.61	0.78	0.73	0.92	0.78	0.92
Adj. Flow (vph)	105	684	227	191	1368	158	402	124	74	109	176	250
Shared Lane Traffic (%)												
Lane Group Flow (vph)	105	911	0	191	1368	158	402	198	0	109	176	250
Enter Blocked Intersection	No											
Lane Alignment	Left	Left	Right									
Median Width(ft)		12			12			12			12	
Link Offset(ft)		0			0			0			0	
Crosswalk Width(ft)		16			16			16			16	
Two way Left Turn Lane								Yes				
Headway Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Turning Speed (mph)	15		9	15		9	15		9	15		9
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (ft)	20	100		20	100	20	20	100		20	100	20
Trailing Detector (ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Position(ft)	0	0		0	0	0	0	0		0	0	0
Detector 1 Size(ft)	20	6		20	6	20	20	6		20	6	20
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(ft)		94			94			94			94	
Detector 2 Size(ft)		6			6			6			6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt	NA		pm+pt	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	5	2		1	6		7	4		3	8	
Permitted Phases	2			6		6	4			8		8

Lanes, Volumes, Timings

1: Waynoka Pl/Tutt Blvd & Constitution Ave

2042 Background + Site

AM



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector Phase	5	2		1	6	6	7	4		3	8	8
Switch Phase												
Minimum Initial (s)	4.0	20.0		4.0	20.0	20.0	4.0	4.0		4.0	4.0	4.0
Minimum Split (s)	10.5	26.0		10.5	26.0	26.0	10.5	24.5		10.5	10.5	10.5
Total Split (s)	25.0	71.0		25.0	71.0	71.0	25.0	25.0		25.0	25.0	25.0
Total Split (%)	17.1%	48.6%		17.1%	48.6%	48.6%	17.1%	17.1%		17.1%	17.1%	17.1%
Maximum Green (s)	20.0	65.0		20.0	65.0	65.0	20.0	18.5		20.0	18.5	18.5
Yellow Time (s)	3.0	4.0		3.0	4.0	4.0	3.0	4.5		3.0	4.5	4.5
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	6.0		5.0	6.0	6.0	5.0	6.5		5.0	6.5	6.5
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Walk Time (s)		7.0			7.0	7.0		7.0			7.0	7.0
Flash Dont Walk (s)		11.0			11.0	11.0		11.0			11.0	11.0
Pedestrian Calls (#/hr)		0			0	0		0			0	0
Act Effect Green (s)	82.8	72.8		89.2	76.0	76.0	44.7	26.3		32.2	18.5	18.5
Actuated g/C Ratio	0.57	0.50		0.61	0.52	0.52	0.31	0.18		0.22	0.13	0.13
v/c Ratio	0.44	0.37		0.49	0.52	0.18	1.19	0.60		0.36	0.75	0.62
Control Delay	17.3	21.2		16.2	24.0	6.1	149.4	59.4		41.5	81.0	17.0
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	17.3	21.2		16.2	24.0	6.1	149.4	59.4		41.5	81.0	17.0
LOS	B	C		B	C	A	F	E		D	F	B
Approach Delay		20.8			21.5			119.7			43.0	
Approach LOS		C			C			F			D	
Queue Length 50th (ft)	38	173		73	304	18	~359	160		77	164	18
Queue Length 95th (ft)	64	219		92	360	58	#295	215		128	213	108
Internal Link Dist (ft)		417			494			435			511	
Turn Bay Length (ft)	140			185		185	50			165		150
Base Capacity (vph)	370	2480		465	2648	880	339	330		399	236	400
Starvation Cap Reductn	0	0		0	0	0	0	0		0	0	0
Spillback Cap Reductn	0	0		0	0	0	0	0		0	0	0
Storage Cap Reductn	0	0		0	0	0	0	0		0	0	0
Reduced v/c Ratio	0.28	0.37		0.41	0.52	0.18	1.19	0.60		0.27	0.75	0.63

Intersection Summary

Area Type: Other

Cycle Length: 146

Actuated Cycle Length: 146

Offset: 65 (45%), Referenced to phase 2:EBTL and 6:WBTL, Start of Yellow

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.19

Intersection Signal Delay: 39.5

Intersection LOS: D

Intersection Capacity Utilization 70.2%

ICU Level of Service C

Analysis Period (min) 15


~ Volume exceeds capacity, queue is theoretically infinite.

Queue shown is maximum after two cycles.

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Splits and Phases: 1: Waynoka Pl/Tutt Blvd & Constitution Ave



Intersection						
Int Delay, s/veh	7.8					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑
Traffic Vol, veh/h	148	87	0	391	160	0
Future Vol, veh/h	148	87	0	391	160	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	85	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	296	174	0	602	188	0
Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	790	188	-	0	-	0
Stage 1	188	-	-	-	-	-
Stage 2	602	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	-	-
Pot Cap-1 Maneuver	359	854	0	-	-	0
Stage 1	844	-	0	-	-	0
Stage 2	547	-	0	-	-	0
Platoon blocked, %			-	-	-	-
Mov Cap-1 Maneuver	359	854	-	-	-	-
Mov Cap-2 Maneuver	451	-	-	-	-	-
Stage 1	844	-	-	-	-	-
Stage 2	547	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	20.8	0	0			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	EBLn1	EBLn2	SBT		
Capacity (veh/h)	-	451	854	-		
HCM Lane V/C Ratio	-	0.656	0.204	-		
HCM Control Delay (s)	-	27	10.3	-		
HCM Lane LOS	-	D	B	-		
HCM 95th %tile Q(veh)	-	4.6	0.8	-		

Intersection						
Int Delay, s/veh	1.4					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	0	0	99	435	166	136
Future Vol, veh/h	0	0	99	435	166	136
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	100	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	68	89	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	198	640	187	272
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	1359	323	459	0	-	0
Stage 1	323	-	-	-	-	-
Stage 2	1036	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	164	718	1102	-	-	-
Stage 1	734	-	-	-	-	-
Stage 2	342	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	134	718	1102	-	-	-
Mov Cap-2 Maneuver	254	-	-	-	-	-
Stage 1	602	-	-	-	-	-
Stage 2	342	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	0	2.1	0			
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1102	-	-	-	-	-
HCM Lane V/C Ratio	0.18	-	-	-	-	-
HCM Control Delay (s)	9	-	0	-	-	-
HCM Lane LOS	A	-	A	-	-	-
HCM 95th %tile Q(veh)	0.7	-	-	-	-	-

Intersection						
Int Delay, s/veh	1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		R	U	R	
Traffic Vol, veh/h	18	10	12	374	231	16
Future Vol, veh/h	18	10	12	374	231	16
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	50	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	92	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	36	20	24	575	251	32
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	890	267	283	0	-	0
Stage 1	267	-	-	-	-	-
Stage 2	623	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	313	772	1279	-	-	-
Stage 1	778	-	-	-	-	-
Stage 2	535	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	307	772	1279	-	-	-
Mov Cap-2 Maneuver	419	-	-	-	-	-
Stage 1	763	-	-	-	-	-
Stage 2	535	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	13.1	0.3	0			
HCM LOS	B					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1279	-	501	-	-	
HCM Lane V/C Ratio	0.019	-	0.112	-	-	
HCM Control Delay (s)	7.9	-	13.1	-	-	
HCM Lane LOS	A	-	B	-	-	
HCM 95th %tile Q(veh)	0.1	-	0.4	-	-	

Intersection						
Int Delay, s/veh	5.5					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	10	15	15	375	237	10
Future Vol, veh/h	10	15	15	375	237	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	78	77	79	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	13	19	19	487	300	13
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	506	0	-	0	308	263
Stage 1	-	-	-	-	263	-
Stage 2	-	-	-	-	45	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1059	-	-	-	684	776
Stage 1	-	-	-	-	781	-
Stage 2	-	-	-	-	977	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1059	-	-	-	676	776
Mov Cap-2 Maneuver	-	-	-	-	676	-
Stage 1	-	-	-	-	772	-
Stage 2	-	-	-	-	977	-
Approach	EB	WB	SB			
HCM Control Delay, s	3.4	0	14.7			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1059	-	-	-	680	
HCM Lane V/C Ratio	0.012	-	-	-	0.46	
HCM Control Delay (s)	8.4	0	-	-	14.7	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0	-	-	-	2.4	

Intersection							
Int Delay, s/veh	7.5						
Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↑	↑↑	↑↓		↑	↑	
Traffic Vol, veh/h	265	675	550	71	89	188	
Future Vol, veh/h	265	675	550	71	89	188	
Conflicting Peds, #/hr	0	0	0	0	0	0	
Sign Control	Free	Free	Free	Free	Stop	Stop	
RT Channelized	-	None	-	None	-	None	
Storage Length	100	-	-	-	0	0	
Veh in Median Storage, #	-	0	0	-	0	-	
Grade, %	-	0	0	-	0	-	
Peak Hour Factor	72	93	93	77	79	83	
Heavy Vehicles, %	2	2	2	2	2	2	
Mvmt Flow	368	726	591	92	113	227	
Major/Minor							
Major1	Major2	Minor2					
Conflicting Flow All	683	0	-	0	1736	342	
Stage 1	-	-	-	-	637	-	
Stage 2	-	-	-	-	1099	-	
Critical Hdwy	4.14	-	-	-	6.84	6.94	
Critical Hdwy Stg 1	-	-	-	-	5.84	-	
Critical Hdwy Stg 2	-	-	-	-	5.84	-	
Follow-up Hdwy	2.22	-	-	-	3.52	3.32	
Pot Cap-1 Maneuver	906	-	-	-	~ 79	654	
Stage 1	-	-	-	-	489	-	
Stage 2	-	-	-	-	281	-	
Platoon blocked, %	-	-	-	-	-	-	
Mov Cap-1 Maneuver	906	-	-	-	~ 47	654	
Mov Cap-2 Maneuver	-	-	-	-	152	-	
Stage 1	-	-	-	-	290	-	
Stage 2	-	-	-	-	281	-	
Approach							
	EB	WB	SB				
HCM Control Delay, s	3.9	0	34.4				
HCM LOS			D				
Minor Lane/Major Mvmt		EBL	EBT	WBT	WBR	SBLn1 SBLn2	
Capacity (veh/h)	906	-	-	-	152	654	
HCM Lane V/C Ratio	0.406	-	-	-	0.741	0.346	
HCM Control Delay (s)	11.7	-	-	-	76.7	13.4	
HCM Lane LOS	B	-	-	-	F	B	
HCM 95th %tile Q(veh)	2	-	-	-	4.5	1.5	
Notes							
~: Volume exceeds capacity	\$: Delay exceeds 300s	+: Computation Not Defined	*: All major volume in platoon				

Intersection						
Int Delay, s/veh	7.7					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑
Traffic Vol, veh/h	148	87	0	386	160	5
Future Vol, veh/h	148	87	0	386	160	5
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	85	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	296	174	0	594	188	10
Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	787	193	-	0	-	0
Stage 1	193	-	-	-	-	-
Stage 2	594	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	-	-
Pot Cap-1 Maneuver	360	849	0	-	-	-
Stage 1	840	-	0	-	-	-
Stage 2	552	-	0	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	360	849	-	-	-	-
Mov Cap-2 Maneuver	454	-	-	-	-	-
Stage 1	840	-	-	-	-	-
Stage 2	552	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	20.6	0	0			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	EBLn1	EBLn2	SBT	SBR	
Capacity (veh/h)	-	454	849	-	-	
HCM Lane V/C Ratio	-	0.652	0.205	-	-	
HCM Control Delay (s)	-	26.6	10.3	-	-	
HCM Lane LOS	-	D	B	-	-	
HCM 95th %tile Q(veh)	-	4.6	0.8	-	-	

Intersection						
Int Delay, s/veh	1.4					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	R	
Traffic Vol, veh/h	0	0	99	435	166	136
Future Vol, veh/h	0	0	99	435	166	136
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	100	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	68	89	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	198	640	187	272
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	1359	323	459	0	-	0
Stage 1	323	-	-	-	-	-
Stage 2	1036	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	164	718	1102	-	-	-
Stage 1	734	-	-	-	-	-
Stage 2	342	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	134	718	1102	-	-	-
Mov Cap-2 Maneuver	254	-	-	-	-	-
Stage 1	602	-	-	-	-	-
Stage 2	342	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	0	2.1	0			
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1102	-	-	-	-	-
HCM Lane V/C Ratio	0.18	-	-	-	-	-
HCM Control Delay (s)	9	-	0	-	-	-
HCM Lane LOS	A	-	A	-	-	-
HCM 95th %tile Q(veh)	0.7	-	-	-	-	-

Intersection						
Int Delay, s/veh	1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		R	↑	R	
Traffic Vol, veh/h	18	10	12	374	231	16
Future Vol, veh/h	18	10	12	374	231	16
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	50	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	65	92	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	36	20	24	575	251	32
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	890	267	283	0	-	0
Stage 1	267	-	-	-	-	-
Stage 2	623	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	313	772	1279	-	-	-
Stage 1	778	-	-	-	-	-
Stage 2	535	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	307	772	1279	-	-	-
Mov Cap-2 Maneuver	419	-	-	-	-	-
Stage 1	763	-	-	-	-	-
Stage 2	535	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	13.1	0.3	0			
HCM LOS	B					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1279	-	501	-	-	
HCM Lane V/C Ratio	0.019	-	0.112	-	-	
HCM Control Delay (s)	7.9	-	13.1	-	-	
HCM Lane LOS	A	-	B	-	-	
HCM 95th %tile Q(veh)	0.1	-	0.4	-	-	

Intersection						
Int Delay, s/veh	5.5					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	10	15	15	375	237	10
Future Vol, veh/h	10	15	15	375	237	10
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	78	77	79	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	13	19	19	487	300	13
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	506	0	-	0	308	263
Stage 1	-	-	-	-	263	-
Stage 2	-	-	-	-	45	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	1059	-	-	-	684	776
Stage 1	-	-	-	-	781	-
Stage 2	-	-	-	-	977	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	1059	-	-	-	676	776
Mov Cap-2 Maneuver	-	-	-	-	676	-
Stage 1	-	-	-	-	772	-
Stage 2	-	-	-	-	977	-
Approach	EB	WB	SB			
HCM Control Delay, s	3.4	0	14.7			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1059	-	-	-	680	
HCM Lane V/C Ratio	0.012	-	-	-	0.46	
HCM Control Delay (s)	8.4	0	-	-	14.7	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0	-	-	-	2.4	

Intersection

Int Delay, s/veh 5.4

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	190	675	550	71	89	188
Future Vol, veh/h	190	675	550	71	89	188
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	72	93	93	77	79	83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	264	726	591	92	113	227

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	683	0	-
Stage 1	-	-	637
Stage 2	-	-	891
Critical Hdwy	4.14	-	6.84 6.94
Critical Hdwy Stg 1	-	-	5.84
Critical Hdwy Stg 2	-	-	5.84
Follow-up Hdwy	2.22	-	3.52 3.32
Pot Cap-1 Maneuver	906	-	~ 108 654
Stage 1	-	-	489
Stage 2	-	-	361
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	906	-	~ 77 654
Mov Cap-2 Maneuver	-	-	197
Stage 1	-	-	347
Stage 2	-	-	361

Approach	EB	WB	SB
HCM Control Delay, s	2.8	0	24
HCM LOS			C

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	906	-	-	-	197	654
HCM Lane V/C Ratio	0.291	-	-	-	0.572	0.346
HCM Control Delay (s)	10.6	-	-	-	45.2	13.4
HCM Lane LOS	B	-	-	-	E	B
HCM 95th %tile Q(veh)	1.2	-	-	-	3.1	1.5

Notes

~: Volume exceeds capacity \$: Delay exceeds 300s -: Computation Not Defined *: All major volume in platoon

Intersection						
Int Delay, s/veh	0.4					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑	↑	↑	↑		
Traffic Vol, veh/h	7	4	0	326	116	0
Future Vol, veh/h	7	4	0	326	116	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	85	87	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	14	8	0	384	133	0
Major/Minor	Minor2	Major1	Major2			
Conflicting Flow All	517	133	-	0	-	0
Stage 1	133	-	-	-	-	-
Stage 2	384	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	-	-
Pot Cap-1 Maneuver	518	916	0	-	-	0
Stage 1	893	-	0	-	-	0
Stage 2	688	-	0	-	-	0
Platoon blocked, %			-	-		
Mov Cap-1 Maneuver	518	916	-	-	-	-
Mov Cap-2 Maneuver	580	-	-	-	-	-
Stage 1	893	-	-	-	-	-
Stage 2	688	-	-	-	-	-
Approach	EB	NB	SB			
HCM Control Delay, s	10.5	0	0			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	EBLn1	EBLn2	SBT		
Capacity (veh/h)	-	580	916	-		
HCM Lane V/C Ratio	-	0.024	0.009	-		
HCM Control Delay (s)	-	11.4	9	-		
HCM Lane LOS	-	B	A	-		
HCM 95th %tile Q(veh)	-	0.1	0	-		

Intersection						
Int Delay, s/veh	0.1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		↑	↑	↑	
Traffic Vol, veh/h	0	0	5	328	116	7
Future Vol, veh/h	0	0	5	328	116	7
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	100	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	85	83	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	0	10	386	140	14
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	553	147	154	0	-	0
Stage 1	147	-	-	-	-	-
Stage 2	406	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	494	900	1426	-	-	-
Stage 1	880	-	-	-	-	-
Stage 2	673	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	491	900	1426	-	-	-
Mov Cap-2 Maneuver	561	-	-	-	-	-
Stage 1	874	-	-	-	-	-
Stage 2	673	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s	0	0.2		0		
HCM LOS	A					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1426	-	-	-	-	-
HCM Lane V/C Ratio	0.007	-	-	-	-	-
HCM Control Delay (s)	7.5	-	0	-	-	-
HCM Lane LOS	A	-	A	-	-	-
HCM 95th %tile Q(veh)	0	-	-	-	-	-

Intersection						
Int Delay, s/veh	0.1					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W		T	↑	↑	
Traffic Vol, veh/h	1	1	1	325	119	1
Future Vol, veh/h	1	1	1	325	119	1
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	50	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	50	50	50	85	92	50
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	2	2	2	382	129	2
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	516	130	131	0	-	0
Stage 1	130	-	-	-	-	-
Stage 2	386	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	519	920	1454	-	-	-
Stage 1	896	-	-	-	-	-
Stage 2	687	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	518	920	1454	-	-	-
Mov Cap-2 Maneuver	579	-	-	-	-	-
Stage 1	895	-	-	-	-	-
Stage 2	687	-	-	-	-	-
Approach	EB	NB		SB		
HCM Control Delay, s	10.1	0		0		
HCM LOS	B					
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	SBT	SBR	
Capacity (veh/h)	1454	-	711	-	-	
HCM Lane V/C Ratio	0.001	-	0.006	-	-	
HCM Control Delay (s)	7.5	-	10.1	-	-	
HCM Lane LOS	A	-	B	-	-	
HCM 95th %tile Q(veh)	0	-	0	-	-	

Intersection						
Int Delay, s/veh	2.3					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	12	5	3	314	112	8
Future Vol, veh/h	12	5	3	314	112	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	78	78	78	52	91	78
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	15	6	4	604	123	10
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	608	0	-	0	342	306
Stage 1	-	-	-	-	306	-
Stage 2	-	-	-	-	36	-
Critical Hdwy	4.12	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	2.218	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	970	-	-	-	654	734
Stage 1	-	-	-	-	747	-
Stage 2	-	-	-	-	986	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	970	-	-	-	644	734
Mov Cap-2 Maneuver	-	-	-	-	644	-
Stage 1	-	-	-	-	735	-
Stage 2	-	-	-	-	986	-
Approach	EB	WB	SB			
HCM Control Delay, s	6.2	0	12			
HCM LOS			B			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	970	-	-	-	650	
HCM Lane V/C Ratio	0.016	-	-	-	0.205	
HCM Control Delay (s)	8.8	0	-	-	12	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0	-	-	-	0.8	

Intersection						
Int Delay, s/veh	2.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↑	↑↑	↑↓		↑	↑
Traffic Vol, veh/h	120	950	700	61	62	128
Future Vol, veh/h	120	950	700	61	62	128
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	100	-	-	-	0	0
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	72	93	93	77	91	91
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	167	1022	753	79	68	141
Major/Minor	Major1	Major2	Minor2			
Conflicting Flow All	832	0	-	0	1638	416
Stage 1	-	-	-	-	793	-
Stage 2	-	-	-	-	845	-
Critical Hdwy	4.14	-	-	-	6.84	6.94
Critical Hdwy Stg 1	-	-	-	-	5.84	-
Critical Hdwy Stg 2	-	-	-	-	5.84	-
Follow-up Hdwy	2.22	-	-	-	3.52	3.32
Pot Cap-1 Maneuver	796	-	-	-	91	585
Stage 1	-	-	-	-	406	-
Stage 2	-	-	-	-	382	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	796	-	-	-	72	585
Mov Cap-2 Maneuver	-	-	-	-	192	-
Stage 1	-	-	-	-	321	-
Stage 2	-	-	-	-	382	-
Approach	EB	WB	SB			
HCM Control Delay, s	1.5	0	19.8			
HCM LOS			C			
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	SBLn2
Capacity (veh/h)	796	-	-	-	192	585
HCM Lane V/C Ratio	0.209	-	-	-	0.355	0.24
HCM Control Delay (s)	10.7	-	-	-	33.7	13.1
HCM Lane LOS	B	-	-	-	D	B
HCM 95th %tile Q(veh)	0.8	-	-	-	1.5	0.9

Queuing Reports



Intersection: 2: Waynoka PI & Middle Access, Interval #1

Movement	EB	EB	NB
Directions Served	L	R	LT
Maximum Queue (ft)	62	56	6
Average Queue (ft)	41	31	1
95th Queue (ft)	69	60	9
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 2: Waynoka PI & Middle Access, Interval #2

Movement	EB	EB	NB
Directions Served	L	R	LT
Maximum Queue (ft)	71	57	11
Average Queue (ft)	46	36	2
95th Queue (ft)	78	60	16
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 2: Waynoka PI & Middle Access, Interval #3

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	236	139
Average Queue (ft)	139	62
95th Queue (ft)	264	135
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #4

Movement	EB	EB	NB
Directions Served	L	R	LT
Maximum Queue (ft)	127	68	6
Average Queue (ft)	57	36	0
95th Queue (ft)	116	68	0
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 2: Waynoka PI & Middle Access, All Intervals

Movement	EB	EB	NB
Directions Served	L	R	LT
Maximum Queue (ft)	236	147	16
Average Queue (ft)	71	41	1
95th Queue (ft)	168	90	9
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 3: Waynoka PI & North Access, Interval #1

Movement	NB	SB
Directions Served	L	TR
Maximum Queue (ft)	40	4
Average Queue (ft)	16	1
95th Queue (ft)	45	6
Link Distance (ft)		
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)	100	
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 3: Waynoka PI & North Access, Interval #2

Movement	NB
Directions Served	L
Maximum Queue (ft)	54
Average Queue (ft)	22
95th Queue (ft)	56
Link Distance (ft)	
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	100
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 3: Waynoka PI & North Access, Interval #3

Movement	NB	NB	SB
Directions Served	L	T	TR
Maximum Queue (ft)	96	33	28
Average Queue (ft)	63	8	7
95th Queue (ft)	105	62	26
Link Distance (ft)	156		
Upstream Blk Time (%)	0		
Queuing Penalty (veh)	1		
Storage Bay Dist (ft)	100		
Storage Blk Time (%)	0	0	
Queuing Penalty (veh)	0	0	

Intersection: 3: Waynoka PI & North Access, Interval #4

Movement	NB	SB
Directions Served	L	TR
Maximum Queue (ft)	49	9
Average Queue (ft)	21	2
95th Queue (ft)	53	12
Link Distance (ft)		
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)	100	
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 3: Waynoka PI & North Access, All Intervals

Movement	NB	NB	SB
Directions Served	L	T	TR
Maximum Queue (ft)	96	33	28
Average Queue (ft)	31	2	2
95th Queue (ft)	77	30	14
Link Distance (ft)		156	
Upstream Blk Time (%)		0	
Queuing Penalty (veh)		0	
Storage Bay Dist (ft)	100		
Storage Blk Time (%)	0	0	
Queuing Penalty (veh)	2	0	

Intersection: 4: Waynoka PI & South Access, Interval #1

Movement	EB	NB	SB
Directions Served	LR	L	TR
Maximum Queue (ft)	33	25	6
Average Queue (ft)	14	4	1
95th Queue (ft)	39	22	9
Link Distance (ft)	250		138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 4: Waynoka PI & South Access, Interval #2

Movement	EB	NB	SB
Directions Served	LR	L	TR
Maximum Queue (ft)	32	12	14
Average Queue (ft)	18	2	2
95th Queue (ft)	42	14	20
Link Distance (ft)	250		138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 4: Waynoka PI & South Access, Interval #3

Movement	EB	NB	SB
Directions Served	LR	L	TR
Maximum Queue (ft)	52	31	14
Average Queue (ft)	35	11	2
95th Queue (ft)	57	35	21
Link Distance (ft)	250		138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 4: Waynoka PI & South Access, Interval #4

Movement	EB	NB
Directions Served	LR	L
Maximum Queue (ft)	28	24
Average Queue (ft)	16	4
95th Queue (ft)	38	20
Link Distance (ft)	250	
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		50
Storage Blk Time (%)		0
Queuing Penalty (veh)		0

Intersection: 4: Waynoka PI & South Access, All Intervals

Movement	EB	NB	SB
Directions Served	LR	L	TR
Maximum Queue (ft)	52	31	27
Average Queue (ft)	21	5	1
95th Queue (ft)	48	24	15
Link Distance (ft)	250		138
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #1

Movement	SB
Directions Served	LR
Maximum Queue (ft)	67
Average Queue (ft)	47
95th Queue (ft)	70
Link Distance (ft)	114
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #2

Movement	EB	SB
Directions Served	LT	LR
Maximum Queue (ft)	6	68
Average Queue (ft)	1	47
95th Queue (ft)	9	72
Link Distance (ft)		114
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #3

Movement	EB	SB
Directions Served	LT	LR
Maximum Queue (ft)	18	90
Average Queue (ft)	3	60
95th Queue (ft)	17	93
Link Distance (ft)		114
Upstream Blk Time (%)		0
Queuing Penalty (veh)		0
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #4

Movement	SB
Directions Served	LR
Maximum Queue (ft)	61
Average Queue (ft)	41
95th Queue (ft)	63
Link Distance (ft)	114
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 5: Waynoka Rd & Waynoka Pl, All Intervals

Movement	EB	SB
Directions Served	LT	LR
Maximum Queue (ft)	25	93
Average Queue (ft)	1	49
95th Queue (ft)	9	77
Link Distance (ft)		114
Upstream Blk Time (%)		0
Queuing Penalty (veh)		0
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #1

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	64	55
Average Queue (ft)	37	33
95th Queue (ft)	59	60
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #2

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	60	49
Average Queue (ft)	36	31
95th Queue (ft)	69	51
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #3

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	225	63
Average Queue (ft)	112	43
95th Queue (ft)	217	68
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #4

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	129	53
Average Queue (ft)	49	33
95th Queue (ft)	126	55
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, All Intervals

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	225	72
Average Queue (ft)	59	35
95th Queue (ft)	144	60
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 3: Waynoka PI & North Access, Interval #1

Movement	NB
Directions Served	L
Maximum Queue (ft)	35
Average Queue (ft)	12
95th Queue (ft)	39
Link Distance (ft)	
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	100
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 3: Waynoka PI & North Access, Interval #2

Movement	NB
Directions Served	L
Maximum Queue (ft)	40
Average Queue (ft)	8
95th Queue (ft)	34
Link Distance (ft)	
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	100
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 3: Waynoka PI & North Access, Interval #3

Movement	NB	SB
Directions Served	L	TR
Maximum Queue (ft)	63	9
Average Queue (ft)	43	3
95th Queue (ft)	72	16
Link Distance (ft)		
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)	100	
Storage Blk Time (%)	0	
Queuing Penalty (veh)	0	

Intersection: 3: Waynoka PI & North Access, Interval #4

Movement	NB
Directions Served	L
Maximum Queue (ft)	55
Average Queue (ft)	17
95th Queue (ft)	55
Link Distance (ft)	
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	100
Storage Blk Time (%)	0
Queuing Penalty (veh)	0

Intersection: 3: Waynoka PI & North Access, All Intervals

Movement	NB	SB
Directions Served	L	TR
Maximum Queue (ft)	74	9
Average Queue (ft)	20	1
95th Queue (ft)	58	7
Link Distance (ft)		
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)	100	
Storage Blk Time (%)	0	
Queuing Penalty (veh)	0	

Intersection: 4: Waynoka PI & South Access, Interval #1

Movement	EB
Directions Served	LR
Maximum Queue (ft)	28
Average Queue (ft)	13
95th Queue (ft)	36
Link Distance (ft)	250
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 4: Waynoka PI & South Access, Interval #2

Movement	EB	NB
Directions Served	LR	L
Maximum Queue (ft)	33	12
Average Queue (ft)	13	2
95th Queue (ft)	38	14
Link Distance (ft)	250	
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		50
Storage Blk Time (%)		0
Queuing Penalty (veh)		0

Intersection: 4: Waynoka PI & South Access, Interval #3

Movement	EB	NB	NB
Directions Served	LR	L	T
Maximum Queue (ft)	50	19	6
Average Queue (ft)	26	3	1
95th Queue (ft)	53	20	8
Link Distance (ft)	250		114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 4: Waynoka PI & South Access, Interval #4

Movement	EB	NB	
Directions Served	LR	L	
Maximum Queue (ft)	28	25	
Average Queue (ft)	9	4	
95th Queue (ft)	31	22	
Link Distance (ft)	250		
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 4: Waynoka PI & South Access, All Intervals

Movement	EB	NB	NB
Directions Served	LR	L	T
Maximum Queue (ft)	50	31	6
Average Queue (ft)	16	2	0
95th Queue (ft)	42	16	4
Link Distance (ft)	250		114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		0	
Queuing Penalty (veh)		0	

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #1

Movement	EB	SB
Directions Served	LT	LR
Maximum Queue (ft)	6	66
Average Queue (ft)	2	44
95th Queue (ft)	14	68
Link Distance (ft)	632	114
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #2

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	19	4	59
Average Queue (ft)	3	1	45
95th Queue (ft)	17	7	65
Link Distance (ft)	632	316	114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #3

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	40	9	87
Average Queue (ft)	8	1	55
95th Queue (ft)	32	10	88
Link Distance (ft)	632	316	114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #4

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	25	8	62
Average Queue (ft)	5	1	41
95th Queue (ft)	24	9	63
Link Distance (ft)	632	316	114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 5: Waynoka Rd & Waynoka Pl, All Intervals

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	40	17	90
Average Queue (ft)	4	1	46
95th Queue (ft)	23	7	73
Link Distance (ft)	632	316	114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 2: Waynoka PI & Middle Access, Interval #1

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	23	30
Average Queue (ft)	4	4
95th Queue (ft)	21	21
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #2

Movement	EB	EB
Directions Served	L	R
Maximum Queue (ft)	16	17
Average Queue (ft)	3	2
95th Queue (ft)	18	16
Link Distance (ft)	988	988
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 2: Waynoka PI & Middle Access, Interval #3

Movement	EB	EB	NB
Directions Served	L	R	T
Maximum Queue (ft)	32	24	67
Average Queue (ft)	13	14	12
95th Queue (ft)	38	38	76
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			4
Queuing Penalty (veh)			16
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 2: Waynoka PI & Middle Access, Interval #4

Movement	EB	EB	NB
Directions Served	L	R	T
Maximum Queue (ft)	29	6	88
Average Queue (ft)	6	1	60
95th Queue (ft)	26	9	171
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			19
Queuing Penalty (veh)			58
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 2: Waynoka PI & Middle Access, All Intervals

Movement	EB	EB	NB
Directions Served	L	R	T
Maximum Queue (ft)	33	30	88
Average Queue (ft)	7	5	18
95th Queue (ft)	27	24	94
Link Distance (ft)	988	988	138
Upstream Blk Time (%)			6
Queuing Penalty (veh)			18
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 3: Waynoka PI & North Access, Interval #1

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

Intersection: 3: Waynoka PI & North Access, Interval #2**Movement**

Directions Served

Maximum Queue (ft)

Average Queue (ft)

95th Queue (ft)

Link Distance (ft)

Upstream Blk Time (%)

Queuing Penalty (veh)

Storage Bay Dist (ft)

Storage Blk Time (%)

Queuing Penalty (veh)

Intersection: 3: Waynoka PI & North Access, Interval #3**Movement** NB NB

Directions Served L T

Maximum Queue (ft) 19 109

Average Queue (ft) 3 27

95th Queue (ft) 17 130

Link Distance (ft) 168

Upstream Blk Time (%) 7

Queuing Penalty (veh) 27

Storage Bay Dist (ft) 100

Storage Blk Time (%) 12

Queuing Penalty (veh) 1

Intersection: 3: Waynoka PI & North Access, Interval #4**Movement** NB NB

Directions Served L T

Maximum Queue (ft) 60 110

Average Queue (ft) 9 98

95th Queue (ft) 66 240

Link Distance (ft) 168

Upstream Blk Time (%) 27

Queuing Penalty (veh) 83

Storage Bay Dist (ft) 100

Storage Blk Time (%) 44

Queuing Penalty (veh) 1

Intersection: 3: Waynoka PI & North Access, All Intervals

Movement	NB	NB
Directions Served	L	T
Maximum Queue (ft)	78	110
Average Queue (ft)	3	31
95th Queue (ft)	33	141
Link Distance (ft)		168
Upstream Blk Time (%)		8
Queuing Penalty (veh)		27
Storage Bay Dist (ft)		100
Storage Blk Time (%)		14
Queuing Penalty (veh)		1

Intersection: 4: Waynoka PI & South Access, Interval #1

Movement	EB
Directions Served	LR
Maximum Queue (ft)	22
Average Queue (ft)	3
95th Queue (ft)	17
Link Distance (ft)	250
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 4: Waynoka PI & South Access, Interval #2

Movement	EB
Directions Served	LR
Maximum Queue (ft)	17
Average Queue (ft)	2
95th Queue (ft)	15
Link Distance (ft)	250
Upstream Blk Time (%)	
Queuing Penalty (veh)	
Storage Bay Dist (ft)	
Storage Blk Time (%)	
Queuing Penalty (veh)	

Intersection: 4: Waynoka PI & South Access, Interval #3

Movement	EB	NB	NB
Directions Served	LR	L	T
Maximum Queue (ft)	17	6	39
Average Queue (ft)	5	1	6
95th Queue (ft)	22	9	44
Link Distance (ft)	250	114	
Upstream Blk Time (%)		3	
Queuing Penalty (veh)		16	
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		4	
Queuing Penalty (veh)		0	

Intersection: 4: Waynoka PI & South Access, Interval #4

Movement	NB
Directions Served	T
Maximum Queue (ft)	66
Average Queue (ft)	33
95th Queue (ft)	115
Link Distance (ft)	114
Upstream Blk Time (%)	13
Queuing Penalty (veh)	29
Storage Bay Dist (ft)	
Storage Blk Time (%)	21
Queuing Penalty (veh)	0

Intersection: 4: Waynoka PI & South Access, All Intervals

Movement	EB	NB	NB
Directions Served	LR	L	T
Maximum Queue (ft)	28	6	70
Average Queue (ft)	3	0	10
95th Queue (ft)	16	4	60
Link Distance (ft)	250	114	
Upstream Blk Time (%)		4	
Queuing Penalty (veh)		11	
Storage Bay Dist (ft)		50	
Storage Blk Time (%)		6	
Queuing Penalty (veh)		0	

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #1

Movement	EB	SB
Directions Served	LT	LR
Maximum Queue (ft)	18	60
Average Queue (ft)	3	37
95th Queue (ft)	20	58
Link Distance (ft)	632	114
Upstream Blk Time (%)		
Queuing Penalty (veh)		
Storage Bay Dist (ft)		
Storage Blk Time (%)		
Queuing Penalty (veh)		

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #2

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	19	4	59
Average Queue (ft)	3	1	37
95th Queue (ft)	17	7	61
Link Distance (ft)	632	316	114
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #3

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	31	75	53
Average Queue (ft)	15	11	36
95th Queue (ft)	41	102	51
Link Distance (ft)	632	316	114
Upstream Blk Time (%)		2	
Queuing Penalty (veh)		0	
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Intersection: 5: Waynoka Rd & Waynoka Pl, Interval #4

Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	23	70	57
Average Queue (ft)	7	33	40
95th Queue (ft)	30	170	60
Link Distance (ft)	632	316	114
Upstream Blk Time (%)		4	
Queuing Penalty (veh)		0	
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			


Intersection: 5: Waynoka Rd & Waynoka Pl, All Intervals


Movement	EB	WB	SB
Directions Served	LT	TR	LR
Maximum Queue (ft)	36	83	69
Average Queue (ft)	7	11	37
95th Queue (ft)	29	96	58
Link Distance (ft)	632	316	114
Upstream Blk Time (%)		2	
Queuing Penalty (veh)		0	
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

MTCP Maps




Map 13: Improvements Map





Map 14: 2040 Roadway Plan (Classification and Lanes)

Map 15: Multimodal Improvements





2016 Major Transportation Corridors Plan Update

Roadway Plan

A total of 67 different projects have been identified as being needed by the year 2040. These projects are shown on Map 13 and listed on Table 4, with each project numbered within each improvement category. Capacity improvement projects are concentrated in the developing urban/suburban western part of the County, while paving projects are spread throughout the County with several in the eastern part.

Map 14 shows the 2040 Roadway Plan that results from the implementation of the improvements described above. The map shows road laneage and classification envisioned in 2040 if all 67 projects are implemented.

Table 4: 2040 Roadway Improvement Projects

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
Paving Improvement Projects										
P1	Black Forest Rd	Walker Rd	County Line Rd		Rural	2	Gravel Road	2	Unimproved County Rd	\$1,954,000
P2	Walker Rd	Black Forest Rd	Meridian Rd		Rural	2	Gravel Road	2	Unimproved County Road	\$4,899,000
P3	Sweet Rd	Peyton Hwy	Ellicott Hwy		Rural	2	Gravel Road	2	Unimproved County Road	\$6,431,000
P4	Harrisville Rd	Blasingame Rd	Ramah Hwy		Rural	2	Gravel Road	2	Unimproved County Road	\$1,601,000
P5	Funk Rd	Calhan Hwy	Ramah Hwy		Rural	2	Gravel Road	2	Unimproved County Road	\$7,913,000
P6	Eastonville Rd	Eastonville Loop	Londonderry Dr		Rural	2	Gravel Road	2	Unimproved County Road	\$1,284,000
P7	Blaney Rd S	Meridian Rd	Hoofbeat Rd		Rural	2	Gravel Road	2	Unimproved County Road	\$1,125,000
P8	Drennan Rd	Curtis Rd	Ellicott Hwy		Rural	2	Gravel Road	2	Unimproved County Road	\$7,148,000



2016 Major Transportation Corridors Plan Update

Table 4: 2040 Roadway Improvement Projects

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
P9	Sanborn Rd	Ellicott Hwy	Baggett Rd		Rural	2	Gravel Road	2	Unimproved County Road	\$1,566,000
P10	Log Rd	90-degree bend	SH 94		Rural	2	Gravel Road	2	Unimproved County Road	\$1,550,000
P11	Latigo Blvd	Eastonville Rd	Elbert Rd		Rural	2	Gravel Road	2	Unimproved County Road	\$1,297,000
P12	Hoofbeat	Blaney Rd S	SH 94		Rural	2	Gravel Road	2	Unimproved County Road	\$2,756,000
P13	Soap Weed Rd	South of US 24	Beg. of Paved section		Rural	2	Gravel Road	2	Unimproved County Road	\$2,495,000
									Paving Projects Total	\$42,019,000
Resurfacing Projects										
R1	Boone Rd	Fossinger Rd	Myers Rd		Rural	2	Unimproved County Road	2	Unimproved County Road	\$11,647,000
R2	Sweet Rd	Elbert Rd	Peyton Hwy		Rural	2	Unimproved County Road	2	Unimproved County Road	\$1,633,000
R3	Murphy Rd	Eastonville Rd	Bradshaw Rd		Rural	2	Unimproved County Road	2	Unimproved County Road	\$1,622,000
R4	Chamberlin South	B St	End of street	B	Rural	2	Unimproved County Road	2	Unimproved County Road	\$112,000
R5	Fountain Mesa Rd	Caballero Ave	Fontaine Blvd	B	Rural	2	Unimproved County Road	2	Unimproved County Road	\$355,000
									Resurfacing Projects Total Cost	\$15,369,000



2016 Major Transportation Corridors Plan Update

Table 4: 2040 Roadway Improvement Projects

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
County Road Upgrades										
U1	Curtis Rd	Judge Orr Rd.	SH 94		Rural	2	Unimproved County Road	2	Principal Arterial	\$35,549,000
U2	Curtis Rd	SH 94	Drennan Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$23,379,000
U3	Bradley Rd	COS City Limit	Curtis Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$24,252,000
U4	Old Pueblo Rd	Fountain City Limits	I-25	B	Rural	2	Unimproved County Road	2	Collector	\$16,722,000
U5	Falcon Hwy	US 24	1 mi east of Curtis Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$16,509,000
U6	Hodgen Rd	Goshawk Rd	Meridian Rd.	B	Rural	2	Unimproved County Road	2	Minor Arterial	\$7,698,000
U7	Baptist Rd	Desiree Dr	Roller Coaster Rd		Rural	2	Unimproved County Road	2	Collector	\$5,286,000
U8	Hodgen Rd	Black Forest Rd	Bar X Rd	B	Rural	2	Unimproved County Road	2	Minor Arterial	\$5,053,000
U9	Hodgen Rd	Roller Coaster Rd	SH 83		Rural	2	Unimproved County Road	2	Minor Arterial	\$3,518,000
U10	Meridian Rd	Hodgen Rd	Murphy Rd	B	Rural	2	Unimproved County Road	2	Minor Arterial	\$7,763,000
U11	Black Forest Rd	Hodgen Rd	Stapleton Dr	B	Rural	2	Unimproved County Road	2	Minor Arterial	\$22,714,000
U12	Vollmer Rd	Stapleton Dr	Shoup Rd	B	Rural	2	Unimproved County Road	2	Minor Arterial	\$11,691,000



2016 Major Transportation Corridors Plan Update

Table 4: 2040 Roadway Improvement Projects

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
U13	Shoup Rd	SH 83	Black Forest Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$15,019,000
U14	Milam Rd	Shoup Rd	Old Ranch Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$9,447,000
U15	Walker Rd	Steppler Rd	Black Forest Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$6,783,000
U16	Roller Coaster Rd	Hodgen Rd	Old Northgate Rd		Rural	2	Unimproved County Road	2	Minor Arterial	\$11,697,000
U17	Higby Rd	Cloverleaf Rd	Roller Coaster Rd		Urban	2	Unimproved County Road	2	Minor Arterial	\$6,514,000
U18	Beacon Lite Rd	SH 105	County Line Rd	A	Rural	2	Unimproved County Road	2	Collector	\$5,321,000
U19	Eastonville Rd	McLaughlin Rd	Latigo Blvd	A	Rural	2	Unimproved County Road	2	Minor Arterial	\$18,420,000
U20	Monument Hill	Woodmoor Dr	County Line Rd	A	Rural	2	Unimproved County Road	2	Collector	\$5,224,000
U21	Deer Creek Rd	Monument Hill	Woodmen Dr	A	Rural	2	Unimproved County Road	2	Collector	\$879,000
County Road Upgrade Projects Total Costs										\$259,437.000

**Table 4: 2040 Roadway Improvement Projects**

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
State Highway Improvements										
SH1	SH94	City Limits	Slocum Rd		Rural	2	Principal Arterial	4	Principal Arterial	\$31,129,000
SH2	US 83	Shoup Rd	Northgate Rd		Rural	4	Principal Arterial	6	Principal Arterial	\$5,953,000
SH3	US 24 West	31st St	Manitou Interchange		Urban	4	Principal Arterial	4	Freeway	\$9,045,000
SH4	US 24	Marksheffel Rd	Constitution		Urban	4	Principal Arterial	6	Expressway	\$4,591,000
SH5	US 24	Garratt Rd	Woodmen Rd		Rural	4	Principal Arterial	6	Principal Arterial	\$7,995,000
SH6	US 83	Northgate	Hodgen Rd		Rural	2	Principal Arterial	4	Principal Arterial	\$10,742,000
State Highway Capacity Projects Total Costs										\$69,455,000



2016 Major Transportation Corridors Plan Update

Table 4: 2040 Roadway Improvement Projects

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
County Road Capacity Improvements										
C1	Enoch Rd	SH 94	Schriever		Rural	2	Collector	4	Principal Arterial	\$8,208,000
C2	Marksheffel Rd	Stetson Hills	2000 ft north		Urban	2	Principal Arterial	4	Principal Arterial	\$3,526,000
C3	Marksheffel Rd	Barnes Rd	Carefree Cir. N		Urban	2	Principal Arterial	4	Principal Arterial	\$8,864,000
C4	Marksheffel Rd	0.5 mi. north of Fontaine	Link Rd		Rural	2	Minor Arterial	4	Expressway	\$20,816,000
C5	Fontaine	Marksheffel Rd	Easy St		Urban	2	Minor Arterial	4	Minor Arterial	\$42,449,000
C6	Bradley Rd	Academy Blvd	Hancock Expy		Urban	2	Principal Arterial	4	Principal Arterial	\$18,301,000
C7	Academy Blvd	I-25	Bradley Rd	A	Urban	4	Expressway	6	Expressway	\$22,733,000
C8	Woodmen Rd	Marksheffel Rd	Banning Lewis		Urban	4	Principal Arterial	6	Expressway	\$19,316,000
C9	Walker Rd	SH 83	Steppler Rd		Rural	2	Collector	4	Minor Arterial	\$15,126,000
C10	Meridian Rd	Murphy Rd	Rex Rd	B	Rural	2	Collector	4	Minor Arterial	\$21,081,000
C11	Black Forest Rd	Stapleton Dr	1300 ft south of Silver Pond Heights	B	Urban	2	Minor Arterial	4	Minor Arterial	\$7,507,000
C12	Stapleton Dr	Towner	Judge Orr Rd.	B	Urban	2	Principal Arterial	4	Principal Arterial	\$41,076,000
C13	Vollmer Rd	Marksheffel Rd	Stapleton Dr		Rural	2	Collector	4	Minor Arterial	\$9,599,000
C14	Judge Orr Rd	Eastonville Rd	Peyton Hwy		Rural	2	Minor Arterial	4	Minor Arterial	\$38,248,000
C15	Hwy 105	Knollwood Blvd	SH 83		Rural	2	Principal Arterial	4	Principal Arterial	\$28,297,000
C16	Grinnell St	Powers Blvd	Bradley Rd	B	Rural	2	Minor Arterial	4	Minor Arterial	\$3,807,000
County Road Capacity Projects Total Costs										\$319,856,000



2016 Major Transportation Corridors Plan Update

Table 4: 2040 Roadway Improvement Projects

Project ID	Road Segment	Segment		PPRTA Project	Urban vs. Rural	Existing Conditions		Future Conditions		Total Cost
		Beginning	End			Lanes	Functional Class	Lanes	Functional Class	
New Road Connections										
N1	Roller Coaster Rd	Eliminate jog in alignment			Rural			2	Minor Arterial	\$4,118,000
N2	Black Forest Rd	Eliminate jog in alignment			Rural			2	Minor Arterial	\$2,585,000
N3	Hodgen Rd	Eastonville Rd	Elbert Rd		Rural			2	Collector	\$4,470,000
N4	Rex Rd	Rex Rd	Eastonville Rd		Urban			2	Collector	\$6,359,000
N5	Stapleton Dr	Towner Rd	Black Forest Rd		Urban			4	Principal Arterial	\$55,771,000
N6	Woodmen Hills Rd	Stapleton Dr	Raygor Rd		Urban			2	Collector	\$12,296,000
N7	Peyton Hwy	Judge Orr Rd	Peyton Hwy		Rural			2	Collector	\$8,365,000
N8	Howell Lane	Bridge over Kettle Creek			Rural			2	Collector	\$8,130,000
N9	Meridian Rd	Bradley Rd	Mesa Ridge Pkwy		Rural			2	Minor Arterial	\$11,312,000
N10	Mesa Ridge Pkwy	Marksheffel Rd	Meridian Rd		Rural			2	Minor Arterial	\$5,216,000
N11	Fontaine Blvd	Fontaine Blvd	Meridian Rd		Urban			4	Principal Arterial	\$11,217,000
N12	Marksheffel Rd	Woodmen Rd	Research Pkwy		Urban			4	Principal Arterial	\$40,262,000
N13	Banning Lewis	Woodmen Rd	Stapleton		Urban			4	Principal Arterial	\$11,131,000
N14	Mesa Ridge Pkwy	Powers Blvd	Marksheffel Rd	A	Rural			4	Principal Arterial	\$14,170,000
N15	Tutt Blvd Extension	Dublin Blvd	Templeton Gap	A	Urban			4	Principal Arterial	\$4,506,000
N16	Furrow Rd Ext	Lamplighter Dr	Higby Rd		Urban			2	Collector	\$1,078,000
N17	Bradley Rd	Grinnell St.	Powers Blvd	B	Urban			2	Minor Arterial	\$10,335,000
New Road Connections Total Project Costs										\$208,915,000
Total Project Cost of County Improvements										\$845,596,000
Total Cost for PPRTA A List Projects										\$68,847,000
Total State Highway Improvements Cost										\$69,455,000
Total Cost of All Projects										\$915,051,000



EL PASO COUNTY

2016 Major Transportation Corridors Plan Update

Table 5: 2040 Multi-modal Improvement Projects

Project ID	Road Name	Improvement Type	Beginning (South, West)	End (North, East)	Length
M1	S. Peyton Highway	Bicycle	Squirrel Creek Road	Falcon Highway	15.93
M2	S. Ellicott Highway	Bicycle & Primary Regional Trail	Squirrel Creek Road	Farmer Road	1.93
M3	Squirrel Creek Road	Bicycle & Primary Regional Trail	Shumway Road	S. Ellicott Highway	14.06
M4	Falcon Highway	Bicycle & Secondary Regional Trail	Meridian Road	S. Peyton Highway	6.95
M5	Meridian Road	Bicycle	Blaney Road	Falcon Highway	2.98
M6	Peyton Highway	Bicycle	Falcon Highway	US 24	7.00
M7	Elbert Road	Bicycle	Judge Orr Road	US 24	2.32
M8	Judge Orr Road	Bicycle	Eastonville Road	Peyton Highway	2.98
M9	Stapleton Dr	Bicycle	Meridian Road	US 24	2.56
M10	Hodgen Road	Bicycle	Meridian Road	Eastonville Road	1.67
M11	Vollmer Road	Bicycle & Primary Regional Trail	Marksheffel Road	Shoup Road	4.51
M12	Hodgen Road	Bicycle & Primary Regional Trail	Highway 105	US 83	4.07
M13	US 24	Primary Regional Trail	Manitou	Cascade	3.44
M14	Shoup Road	Bicycle	US 83	Vollmer Road	6.24