HAY CREEK VALLEY

FINAL DRAINAGE REPORT

Prepared for:

VIEW HOMES, INC.
555 Middle Creek Parkway Suite 500
Colorado Springs, CO 80921
(719) 382-9433

Prepared by:

2435 Research Parkway, Suite 300
Colorado Springs, CO 80920
(719) 575-0100
fax (719) 572-0208

December 2023

Project No. 22.886.076

PCD File SF2324

Engineer's Statement:
The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

_____ _____

Jesse Sullivan Date
Registered Professional Engineer
State of Colorado
No. 55600

Owner/Developer's Statement:
I, the owner/developer have read and will comply with all of the requirements specified in this drainage report and plan.

View Homes, Inc.
Business Name

By: _____ _____
Timothy Buschar Date

Title: Director of Land Acquisition and Development

Address: 555 Middle Creek Parkway Suite 500
Colorado Springs, CO 80921

El Paso County:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

_____ _____

Joshua Palmer, P.E.
County Engineer / ECM Administrator Date
Conditions:

TABLE OF CONTENTS

CERTIFICATION I

I. INTRODUCTION 1

II. HYDROLOGIC METHODOLOGY 2

III. PROJECT CHARACTERISTICS 5

IV. BASIN HYDROLOGY 6

V. HYDRAULIC ANALYSIS 12

VI. STORM WATER QUALITY 17

VII. EROSION CONTROL PLAN 18

VIII. FLOODPLAINS 18

IX. FEE DEVELOPMENT 19

X. SUMMARY 21

XI. REFERENCES 22

APPENDICES 23

APPENDIX

A. Hydrologic and Hydraulic Calculations

1. Rational Calculations
2. Inlet Calculations
3. Culvert Calculations
4. Pond Calculations
5. Runoff Reduction Calculations
6. HEC-HMS Results
7. StormCAD Results
8. Swale Calculations

B. Standard Design Charts and Tables

1. Runoff Coefficients
2. ECM Table 3-1
3. Shallow Flow Velocities
4. Basin Fee Schedule
5. ECM Table 10-4

C. Report References

1. HEC-2 Printout
2. FIRMette
3. Soil Survey

D. Maps

1. Vicinity Map
2. Offsite Basins Drainage Basin Map
3. Existing Conditions Drainage Basin Map
4. Proposed Conditions Drainage Basin Map

I. INTRODUCTION

The Hay Creek Valley site is comprised of approximately 214.6 acres of unplatted and mostly undeveloped land. The site is located on Smow Mountain Heights approximately 700 feet south of its intersection with Hay Creek Road. The site is currently comprised of six (6) parcels which are to be subdivided into 20 lots and four (4) tracts. The existing access road will be replaced with a private road located within a proposed 70-foot wide tract which will terminate with a cul-de-sac in the southwestern section of the site.

a. PURPOSE AND SCOPE OF STUDY

The purpose of this Final Drainage Report (FDR) is to evaluate the specific drainage infrastructure requirements which will provide compliance with the approved Hay Creek Valley MDDP / Preliminary Drainage Report, by Matrix, dated August 2023 (MDDP), and the El Paso County Drainage Criteria Manual (DCM) to provide storm water conveyance for associated developments. This study will identify off-site, and on-site drainage patterns associated with respective land uses, provide hydrologic and hydraulic analysis of tributary basins and conveyance structures to a detention pond, and identify effective, safe routing to the downstream outfall. The improvements associated with this report maintain compliance with the DCM by providing full spectrum detention where necessary, which is to be constructed concurrently with the improvements associated with this FDR.

b. DBPS RELATED INVESTIGATIONS

The proposed development is located within the Beaver Creek Drainage Basin. No Drainage Basin Planning Study (DBPS) has been completed for this basin.

c. GENERAL PROJECT DESCRIPTION

The Hay Creek Valley Subdivision is located to the southwest of the intersection of Hay Creek Road and Smow Mountain Heights. The site is located as follows:

1. General Location: Southwest ¼ of Section 34 and the Southeast ¼ of Section 33, Township 11 South, Range 67 West of the 6th P.M. in the County of El Paso, State of Colorado.
2. Drainageway: The Hay Creek Subdivision is located on the southern edge of the Beaver Creek Drainage Basin. Most of the site drains north and into Hay Creek located approximately 200 feet north of the site. Hay Creek is a tributary to Beaver Creek which ultimately drains into Monument Creek. A small portion of the southeast corner of the site drains south into the Air Force Academy Major Drainage Basin.
3. Surrounding Developments: The site is bound Lots 1 through 8 Hay Creek Ranch Subdivision, and 4 unplatted parcels to the north, and by the Air Force Academy the south. The site is bound by Lot 2 Rush Subdivision and Lot 2 Block 1 Smiley Subdivision to the west, and an unplatted parcel to the east.
4. Lots to be Platted: The site is to be subdivided into 20 lots zoned RR-5 and 4 tracts.
5. Area of Disturbance: The Hay Creek Valley development is expected to disturb a total area of approximately 17.28 **acres.**
6. Streamside Zone: This project is not located within a streamside zone.
7. Vegetation: The Hay Creek Valley site contains a single-family residence, a barn and Smow Mountain Heights, a private road that provided access to the site from hay Creek

Matrix Design Group, Inc., 2023©

Road. The vegetation of the site consists of sparse, natural vegetative land cover in the form of grasses and shrubs with sparse trees throughout.

Refer to Appendix D for the Vicinity Map.

d. SOILS CONDITIONS

Soils can be classified in four different hydrologic groups, A, B, C, or D to help predict stormwater runoff rates. Hydrologic group "A" is characterized by deep, well-drained coarse-grained soils with a rapid infiltration rate when thoroughly wet and having a low runoff potential. Group "D" typically has a clay layer at or near to the surface, or a very shallow depth to impervious bedrock and has a very slow infiltration rate and a high runoff potential. See Soils Map, Appendix C. The following soil types are present in the Hay Creek Valley site:

Table 1.1 – NRCS Soil Survey for El Paso County – Hay Creek Valley

Soil ID Number	*Soil*	*Hydrologic Classification*	*Drainage Class*	*Percent of Site*
38	Jarre-Tecolote Complex, 8 to 65 percent slopes	B	Well Drained	50.8%
71	Pring coarse sandy loam, 3 to 8 percent slopes	B	Well Drained	14.5%
93	Tomah-Crowfoot complex, 8 to 15 percent slopes	B	Well Drained	34.7%

DATA SOURCES

Topographical information for the district was found using a combination of ***United States Geological Survey*** (USGS) mapping as well as field surveying. The ***Web Soil Survey,*** created by the ***Natural Resources Conservation Service,*** was utilized to investigate the existing general soil types within the district. Offsite contours are taken from the ***2018 El Paso County LIDAR*** survey and/or USGS Quad Sheets.

e. APPLICABLE CRITERIA AND STANDARDS

This report has been prepared in accordance to the criteria set forth in the City of Colorado Springs and El Paso County DCM, El Paso County Engineering Criteria Manual (ECM) and El Paso County Resolutions 15-042 and 19-245. In addition to the DCM, the **Urban Storm Drainage Criteria Manuals, Volumes 1 through 3**, dated 2016 have been used to supplement the County's Criteria Manual.

II. Hydrologic Methodology

a. MAJOR BASINS AND SUBBASINS

The majority of the Hay Creek Valley site is located within the Beaver Creek Drainage Basin with a small portion of the site tributary to the Air Force Academy Major Drainage Basin. Runoff presently flows overland until reaching an existing natural drainage swale located within the site. This drainage swale directs flows internally until discharging from near the northeastern corner of the site. Drainage

Matrix Design Group, Inc., 2023©

from the developed road will be directed to Pond 1, where the runoff will be treated for water quality and detained to maintain the historic major event discharge rate from the site.

b. METHODOLOGY

i. UD Methods

The hydrology for this project uses both the **SCS Hydrograph Procedure** and the **Rational Method** as recommended by the Drainage Criteria Manual (DCM) for the minor and major storms. The Rational Method is used for drainage basins less than 100-acres in size. The Rational Method uses the following equation:

$Q=C*i*A$

Where:

Q	=	Maximum runoff rate in cubic feet per second (cfs)
C	=	Runoff coefficient
i	=	Average rainfall intensity (inches per hour)
A	=	Area of drainage sub-basin (acres)

Rational Method coefficients from 6-6 of the Drainage Criteria Manual for developed land were utilized in the Rational Method calculations. This method will be used primarily for sizing of storm sewer infrastructure. See Appendix B for more information.

Time of Concentration

The time of concentration consists of the initial time of overland flow and the travel time in a channel to the inlet or point of interest. A minimum time of concentrations of 5 minutes is utilized for urban areas. The Rational Calculation spreadsheet included in Appendix A shows an initial overland flow length, a channel or street flow length for each sub-basin, and also demonstrates the time of concentration calculations for initial (overland) and channel (or street) conditions. A maximum "True Initial" Flow Length of 300 feet will be used for pre-developed sub-basins and a maximum length of 100 feet will be used for Developed sub-basins for time of concentration calculations in compliance with the DCM.

Rainfall Intensity

The hypothetical rainfall depths for the 1-hour storm duration were derived using Table 6-2 of the Colorado Springs DCM (shown below). See Appendix B.

Table 2.1 – Project Area 1-Hour Rainfall Depth

Storm Recurrence Interval	Rainfall Depth (inches)
5-year	1.50
100-year	2.52

The rainfall intensity equation for the Rational Method was taken from Drainage Criteria Manual Volume 1 Figure 6-5.

Matrix Design Group, Inc., 2023©

C-Factors

C-factors for the Rational Method are based on anticipated land use and are taken from Table 6-6. Proposed single family residential is considered as the Single Family – 5 acres category. Areas which will be future open spaces or detention facilities are modeled under the Parks and Cemeteries category. Undeveloped or predevelopment areas are model under Undeveloped Areas-Historic Flow Analysis—Greenbelts, Agriculture category.

ii.HEC-HMS Methods

The DCM requires the use of the SCS Hydrograph Procedure to compute storm water runoff quantities when the drainage area is greater than 100 acres. This report uses HEC-HMS for the routing and analysis of the site conditions.

SCS Lag

The SCS lag calculations are completed as part of this report. Proposed development areas within the Hay Creek area are calculated based on the methodology indicated in the DCM Equations:

Lag Time:

$t_{lag} = 0.6 \cdot t_c$ (Eq. 6-13)

The Time of Concentration is the sum of overland flow time and the t_t values for the various consecutive flow segments:

$$t_c = t_i + t_{t1} + t_{t2} + t_{t3} \ldots t_{tm} \quad \text{(Eq. 6-14)}$$

Where:

t_c = time of concentration (hr)

t_i = overland (initial) flow time (hr)

t_{tm} = travel time for each flow segment (hr)

m = number of flow segments

Overland Flow:

$T_i = 0.007(n \cdot L)^{0.8} / (P_2)^{0.5} S^{0.4}$ (Eq. 6-15)

Where:

T_i = overland flow time (hr)

n = Manning's roughness coefficient L

= flow length (ft)

P_2 = 2-year, 24-hour rainfall (in)

S = slope of hydraulic grade line (ft/ft)

Matrix Design Group, Inc., 2023©

Concentrated Flow:

$T_t = L / (3600 \cdot V)$ (Eq. 6-16)

Where:

T_t = travel time (hr)

L = flow length (ft)

V = velocity (ft/s)

3,600 = conversion factor from seconds to hours

Runoff Analysis

The site has been analyzed using HEC-HMS and the NRCS SCS method. The model indicates approximately 10.5 cfs decrease for Q100 event post development of the Hay Creek site. (**EX-Q5, EX-Q100, PR-Q5, and PR-Q100)** These models look at the 5, and 100-year events for onsite detention within the Hay Creek Site and demonstrate a slight reduction for the 100-year event. Print outs from each model can be found in Appendix A.

Hydrographs for the proposed Pond 1 are taken from MHFD-Detention, where appropriate, and input to the model to represent the detention required within the development to maintain the historic flow discharge downstream of the site and provide water quality for the development in accordance with the DCM.

NRCS SCS curve numbers (CN) are taken from Table 6-10 of the DCM and weighted for each basin based on the soil and development types. As recommended in the DCM storms of 2-hour duration are used for the 5-year event. A 24-hour storm is used for the 100-year event. Lag times are calculated for the basins using the formulas from the DCM shown above.

iii. HGL Profile Methods

Preliminary sizing of storm sewer has been completed using the Manning's channel flow calculation.

To confirm DCM compliant capacity and velocity values the site has been modeled in StormCAD using the Standard head loss method and head loss values taken from Table 9-4 of the DCM. HGL profiles modeled in StormCAD are included in Appendix C.

Table 9-4. STORMCAD Standard Method Coefficients

Bend Loss		
Bend Angle	**K Coefficient**	
0°	0.05	
22.5°	0.10	
45°	0.40	
60°	0.64	
90°	1.32	
LATERAL LOSS		
One Lateral K Coefficient		
Bend Angle	Non-surcharged	Surcharged
45°	0.27	0.47
60°	0.52	0.90
90°	1.02	1.77
Two Laterals K Coefficient		
45°	0.96	
60°	1.16	
90°	1.52	

III. Project Characteristics

a. BASIN LOCATION AND FLOWS

The Hay Creek Valley site is found on the southern border of the Beaver Creek Drainage Basin. In addition to the 214.6-acre site, there are off-site basins east, west, and south of the site that contribute a total tributary area of 98.5 acres. The Hay Creek Valley Road & Storm improvements are anticipated to disturb approximately 17.28 acres.

Matrix Design Group, Inc., 2023©

b. MAJOR DRAINAGEWAYS

Beaver Creek
The majority of the Hay Creek Valley site is located within the Beaver Creek Drainage Basin. Runoff generated within this basin presently flows overland with slopes ranging from 5 to 50% until reaching an existing natural drainage swale located within the site. This drainage swale directs the sites flows internally until discharging from the site near the northeastern corner. Drainage from the developed road will be directed to Pond 1, where the runoff will be treated for water quality and detained to maintain the historic major event discharge rate from the site.

Air Force Academy
The area along the southeastern border of the site drains southeast into the Air Force Academy Major Drainage Basin. Runoff generated within this basin presently flows overland with slopes ranging from 15 to 45% until exiting the site to the southeast into the adjacent property.

c. LAND USES

Presently, the site is unplatted and consists mostly of undeveloped land. The 214.6-acre area is entirely zoned RR-5. The site will consist of residential lots containing 5-acres or more and three tracts, one containing the proposed Pond 1, one containing the proposed roadway, and the other containing the Preble's mouse habitat which is undevelopable.

IV. BASIN HYDROLOGY

a. The ***Pre-development conditions*** for the Hay Creek Valley site have been analyzed and are presented by design points and are described as follows:

Predevelopment conditions have been analyzed using both the SCS Hydrograph Procedure and the routed Rational Method. The existing conditions will discuss the entry of runoff from off-site basins as it relates to the respective design point. Runoff generated, either on-site or off-site, drains overland towards the northeastern corner of the site where it is captured by the existing natural swale that runs northeast, exiting the site and releasing flows to be collected in Hay Creek. Generally, all undeveloped basins are considered to be vegetated with sparse grasses. A delineation of the basin boundaries can be found in Appendix D in drawings DR-01 and DR-02. Runoff calculations can be found in Appendix A. The existing runoff design points are described below:

Design Point 1 (Rational (Q_5 = 3.5 cfs, Q_{100} = 18.9 cfs) HEC-HMS (Q_5 = 0.8 cfs, Q_{100} = 4.1 cfs)) (sub-basin: EX-OS1a; Area: 9.4 Ac.) (Slopes: 5 to 15%) This point represents the discharge from offsite sub-basin EX-OS1a into the site. Stormwater runoff will sheet flow to the east and into sub-basin EX-1.

Design Point 2 (Rational (Q_5 = 12.3 cfs, Q_{100} = 74.6 cfs) HEC-HMS (Q_5 = 2.6 cfs, Q_{100} = 15.7 cfs)) (sub-basin: EX-OS1b; Area: 59.2 Ac.) (Slopes: 5 to 10%) This point represents the discharge from offsite sub-basin EX-OS1b into the site. Stormwater runoff will sheet flow to the east and into sub-basin EX-2.

Design Point 3 (Rational (Q_5 = 7.8 cfs, Q_{100} = 42.0 cfs) HEC-HMS (Q_5 = 1.5 cfs, Q_{100} = 8.0 cfs)) (sub-basin: EX-OS2a; Area: 15.9 Ac.) (Slopes: 20 to 50%) This point represents the discharge from

Matrix Design Group, Inc., 2023©

offsite sub-basin EX-OS2a into the site. Stormwater runoff will sheet flow to the north and into sub-basin EX-2.

Design Point 4 (Rational (Q_5 = 1.3 cfs, Q_{100} = 6.7 cfs) HEC-HMS (Q_5 = 0.3 cfs, Q_{100} = 1.4 cfs)) (sub-basin: EX-OS2b; Area: 2.8 Ac.) (Slopes: 10 to 40%) This point represents the discharge from offsite sub-basin EX-OS2b into the site. Stormwater runoff will sheet flow to the north and into sub-basin EX-3.

Design Point 5 (Rational (Q_5 = 1.6 cfs, Q_{100} = 8.2 cfs) HEC-HMS (Q_5 = 0.3 cfs, Q_{100} = 1.6 cfs)) (sub-basin: EX-OS2c; Area: 3.2 Ac.) (Slopes: 10 to 50%) This point represents the discharge from offsite sub-basin EX-OS2c into the site. Stormwater runoff will sheet flow to the north and into sub-basin EX-3.

Design Point 6 (Rational (Q_5 = 2.7 cfs, Q_{100} = 17.7 cfs) HEC-HMS (Q_5 = 0.2 cfs, Q_{100} = 2.0 cfs)) (sub-basin: EX-OS3; Area: 8.1 Ac.) (Slopes: 10 to 45%) This point represents the discharge from offsite sub-basin EX-OS3 into the site. Stormwater runoff will sheet flow to the west and into sub-basin EX-5.

Design Point 7 (Rational (Q_5 = 2.3 cfs, Q_{100} = 15.6 cfs) HEC-HMS (Q_5 = 2.3 cfs, Q_{100} = 15.6 cfs)) (sub-basin: EX-4; Area: 5.9 Ac.) (Slopes: 10 to 50%) This point represents the discharge from sub-basin EX-4 into the adjacent property. Stormwater runoff will sheet flow to the south and into the adjacent property then continue south along historic paths.

Design Point 8 (Rational (Q_5 = 26.1 cfs, Q_{100} = 153.1 cfs) HEC-HMS (Q_5 = 5.4 cfs, Q_{100} = 30.9 cfs)) (sub-basins: EX-OS1b, EX-OS2a, EX-2; Area: 123.3 Ac.) (Slopes: 5 to 30%) This point represents the combined discharge from sub-basins EX-OS1b, EX-OS2a, and EX-2 into sub-basin EX-1. Stormwater runoff will sheet flow to the north to combine with the flows from sub-basin EX-1 before continuing along historic paths.

Design Point 9 (Rational (Q_5 = 17.6 cfs, Q_{100} = 106.5 cfs) HEC-HMS (Q_5 = 2.9 cfs, Q_{100} = 17.4 cfs)) (sub-basins: EX-OS2b, EX-OS2c, EX-3; Area: 67.6 Ac.) (Slopes: 5 to 60%) This point represents the combined discharge from sub-basins EX-OS2b, EX-OS2c, and EX-3 into sub-basin EX-1. Stormwater runoff will sheet flow to the north to combine with the flows from sub-basin EX-1 before continuing along historic paths.

Design Point 10 (Rational (Q_5 = 13.5 cfs, Q_{100} = 85.3 cfs) HEC-HMS (Q_5 = 1.8 cfs, Q_{100} = 11.9 cfs)) (sub-basins: EX-OS3, EX-5; Area: 51.0 Ac.) (Slopes: 5 to 50%) This point represents the combined discharge from sub-basins EX-OS3, and EX-5 into sub-basin EX-1. Stormwater runoff will sheet flow to the north to combine with the flows from sub-basin EX-1 before continuing along historic paths.

Design Point 11 (Rational (Q_5 = 35.0 cfs, Q_{100} = 210.9 cfs) HEC-HMS (Q_5 = 11.2 cfs, Q_{100} = 69.9 cfs)) (sub-basins: EX-OS1a, EX-OS1b, EX-OS2a, EX-OS2b, EX-OS2c, EX-OS3, EX-1, EX-2, EX-3, EX-5; Area: 307.3 Ac.) (Slopes: 5 to 50%) This point represents the total discharge from the site. Stormwater runoff is collected in a natural swale and directed to the northeast. The channelized flow exits the site near the northeast corner of the site and continues north before draining into Hay Creek approximately 300 feet north of the site.

Matrix Design Group, Inc., 2023©

Design Point HC (Q_{100} = 127 cfs) This point represents the stormwater flows in Hay Creek at the existing private 24"x36" culvert to the north of the site. The existing private 24"x36" culvert conveys the flows in Hay Creek under the existing access road. The proposed flows in Hay Creek come from the HEC-2 analysis provided by the Regional Floodplain Administrator. The HEC-2 results are included in **Appendix C**.

b. The ***fully developed conditions*** for the site are as follows:

Post development conditions have been analyzed using both the SCS Hydrograph Procedure and the rational routed flow. The proposed conditions will discuss the entry of runoff from off-site basins as it relates to the respective design point. Runoff generated, either on-site or off-site, drains overland towards the northeastern corner of the site where it is captured by the existing natural swale that runs northeast, exiting the site and releasing flows to be collected in Hay Creek. Generally, the developed lots are considered to be residential lots containing 5 acres or more, having an imperviousness of 7.0%. Sub-basins PR-8a and PR-8b, which contain the proposed roadway and ditch, have an imperviousness of 66.4%. Sub basins PR-9, and PR-10, containing the proposed Pond 1 and open space are considered to have an imperviousness of 2.0%. A delineation of the basin boundaries can be found in Appendix D in drawing DR-03. Runoff calculations can be found in Appendix A. The proposed runoff design points are described below:

Design Point 1 (Rational (Q_5 = 3.5 cfs, Q_{100} = 18.9 cfs) HEC-HMS (Q_5 = 0.8 cfs, Q_{100} = 3.6 cfs)) (sub-basin: OS1a; Area: 9.4 Ac.) (Slopes: 5 to 15%) This point represents the discharge from offsite sub-basin OS1a into the site. Stormwater runoff will sheet flow to the east and into sub-basin PR-1b.

Design Point 2 (Rational (Q_5 = 12.3 cfs, Q_{100} = 74.6 cfs) HEC-HMS (Q_5 = 2.6 cfs, Q_{100} = 14.2 cfs)) (sub-basin: OS1b; Area: 59.2 Ac.) (Slopes: 5 to 10%) This point represents the discharge from offsite sub-basin OS1b into the site. Stormwater runoff will sheet flow to the east and into sub-basin PR-1a.

Design Point 3 (Rational (Q_5 = 2.2 cfs, Q_{100} = 12.4 cfs) HEC-HMS (Q_5 = 0.4 cfs, Q_{100} = 1.8 cfs)) (sub-basin: OS2a; Area: 5.0 Ac.) (Slopes: 20 to 50%) This point represents the discharge from offsite sub-basin OS2a into the site. Stormwater runoff will sheet flow to the north and into sub-basin PR-1a.

Design Point 4 (Rational (Q_5 = 2.2 cfs, Q_{100} = 12.0 cfs) HEC-HMS (Q_5 = 0.4 cfs, Q_{100} = 2.0 cfs)) (sub-basin: OS2b; Area: 4.7 Ac.) (Slopes: 20 to 50%) This point represents the discharge from offsite sub-basin OS2b into the site. Stormwater runoff will sheet flow to the north and into sub-basin PR-2.

Design Point 5 (Rational (Q_5 = 3.3 cfs, Q_{100} = 17.0 cfs) HEC-HMS (Q_5 = 0.8 cfs, Q_{100} = 2.7 cfs)) (sub-basin: OS2c; Area: 6.1 Ac.) (Slopes: 20 to 50%) This point represents the discharge from offsite sub-basin OS2c into the site. Stormwater runoff will sheet flow to the north and into sub-basin PR-3.

Matrix Design Group, Inc., 2023©

Design Point 6 (Rational (Q_5 = 1.3 cfs, Q_{100} = 6.7 cfs) HEC-HMS (Q_5 = 0.3 cfs, Q_{100} = 1.1 cfs)) (sub-basin: OS2d; Area: 2.8 Ac.) (Slopes: 10 to 50%) This point represents the combined discharge from offsite sub-basin OS2d into the site. Stormwater runoff will sheet flow to the north and into sub-basin PR-4.

Design Point 7 (Rational (Q_5 = 1.6 cfs, Q_{100} = 8.0 cfs) HEC-HMS (Q_5 = 0.3 cfs, Q_{100} = 1.3 cfs)) (sub-basin: OS2e; Area: 3.2 Ac.) (Slopes: 5 to 40%) This point represents the discharge from sub-basin OS2e into the site. Stormwater runoff will sheet flow to the north and into sub-basin PR-5.

Design Point 8 (Rational (Q_5 = 1.5 cfs, Q_{100} = 10.1 cfs) HEC-HMS (Q_5 = 0.1 cfs, Q_{100} = 0.8 cfs)) (sub-basins: OS3a; Area: 4.9 Ac.) (Slopes: 10 to 45%) This point represents the discharge from sub-basin OS3a into the site. Stormwater runoff will sheet flow to the west and into sub-basin PR-8.

Design Point 9 (Rational (Q_5 = 1.1 cfs, Q_{100} = 7.6 cfs) HEC-HMS (Q_5 = 0.1 cfs, Q_{100} = 0.8 cfs)) (sub-basins: OS3b; Area: 3.3 Ac.) (Slopes: 10 to 45%) This point represents the discharge from sub-basin OS3b into the site. Stormwater runoff will sheet flow to the west and into sub-basin PR-8.

Design Point 10 (Rational (Q_5 = 3.1 cfs, Q_{100} = 17.0 cfs)) (sub-basins: PR-8; Area: 5.9 Ac.) (Slopes: 10 to 50%) This point represents the discharge from sub-basin PR-8 into the adjacent property. Stormwater runoff will sheet flow to the south and into the adjacent property then continue south along historic paths. Note: HEC-HMS values not calculated for this basin due to size and its not being tributary to the site infrastructure.

Design Point 11 (Rational (Q_5 = 15.0 cfs, Q_{100} = 88.8 cfs) HEC-HMS (Q_5 = 3.7 cfs, Q_{100} = 19.5 cfs)) (sub-basins: OS1b, OS2a, PR-1a; Area: 77.2 Ac.) (Slopes: 5 to 30%) This point represents the flows from sub-basins OS1b, OS2a and PR-1a that are directed to the proposed private type C inlet at DP-11. The flows collected at DP-11 are conveyed northeast via proposed private 30-inch CMP storm drain towards Design Point 12b (DP-12b).

Design Point 12a (Rational (Q_5 = 4.9 cfs, Q_{100} = 26.8 cfs) HEC-HMS (Q_5 = 1.3 cfs, Q_{100} = 6.1 cfs)) (sub-basins: OS1a, PR-1b; Area: 15.6 Ac.) (Slopes: 5 to 30%) This point represents the flows from sub-basins OS1a, and PR-1b that are directed to the proposed private type D inlet at DP-12a. The flows collected at DP-12a are combined with the flows from DP-11 at DP-12b before being conveyed to the east via proposed private 30-inch CMP storm drain which outfalls via a proposed private flared end section that directs the flows to the east along historic paths.

Design Point 12b (Rational (Q_5 = 18.4 cfs, Q_{100} = 107.5 cfs) HEC-HMS (Q_5 = 5.0 cfs, Q_{100} = 25.2 cfs)) (sub-basins: OS1a, OS2a, OS1b, PR-1a, PR-1b; Area: 92.8 Ac.) (Slopes: 5 to 30%) This point represents the combination of the flows collected at DP-11 and DP-12a. The combined flows are conveyed to the east via proposed private 30-inch CMP storm drain which outfalls via a proposed private flared end section that discharges to a riprap splash pad before continuing along historic paths at a velocity of 4.95 ft/s which is compliant with DCM values for stable channel flow. See appendix A for supporting calculations.

Design Point 13 (Rational (Q_5 = 4.6 cfs, Q_{100} = 24.8 cfs) HEC-HMS (Q_5 = 1.1 cfs, Q_{100} = 5.3 cfs)) (sub-basins: OS2b, PR-2; Area: 12.5 Ac.) (Slopes: 5 to 30%) This point represents the flows from sub-basins OS2b and PR-2 that have been collected in the roadside ditch that runs along the south

Matrix Design Group, Inc., 2023©

side of the proposed roadway. The roadside ditch located upstream of Design Point 12 will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private Type C inlet at Design Point 13 (DP-13). These flows are conveyed under the proposed roadway to the north, discharging via a proposed private 18-inch FES that discharges to a riprap splash pad before continuing along historic paths at a velocity of 3.77 ft/s which is compliant with DCM values for stable channel flow. See appendix A for supporting calculations.

Design Point 14 (Rational (Q_5 = 7.9 cfs, Q_{100} = 42.7 cfs) HEC-HMS (Q_5 = 1.4 cfs, Q_{100} = 5.5 cfs)) (sub-basins: OS2c, PR-3; Area: 24.6 Ac.) (Slopes: 5 to 30%) This point represents the flows from sub-basins OS2c and PR-3 that have been collected in the roadside ditch that runs along the south side of the proposed roadway. The roadside ditch along this stretch will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private Type C inlet at Design Point 14 (DP-14). These flows are conveyed under the proposed roadway to the north, discharging via a proposed private 18-inch FES that discharges to a riprap splash pad before continuing along historic paths at a velocity of 3.91 ft/s which is compliant with DCM values for stable channel flow. See appendix A for supporting calculations.

Design Point 15 (Rational (Q_5 = 5.5 cfs, Q_{100} = 29.8 cfs) HEC-HMS (Q_5 = 1.5 cfs, Q_{100} = 6.6 cfs)) (sub-basins: OS2d, PR-4; Area: 17.0 Ac.) (Slopes: 5 to 60%) This point represents the flows from sub-basins OS2d, and PR-4 that have been collected in the roadside ditch that runs along the south side of the proposed roadway. The roadside ditch along this stretch will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private type C inlet at Design Point 15 (DP-15). These flows are conveyed under the proposed roadway to the north, discharging via a proposed private 18-inch FES that discharges to a riprap splash pad before continuing along historic paths at a velocity of 3.90 ft/s which is compliant with DCM values for stable channel flow. See appendix A for supporting calculations.

Design Point 16 (Rational (Q_5 = 6.4 cfs, Q_{100} = 34.4 cfs) HEC-HMS (Q_5 = 1.6 cfs, Q_{100} = 7.2 cfs)) (sub-basins: OS2e, PR-5; Area: 20.1 Ac.) (Slopes: 5 to 60%) This point represents the flows from sub-basins OS2e, and PR-5 that have been collected in the roadside ditch that runs along the south side of the proposed roadway. The roadside ditch along this stretch will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private type C inlet at Design Point 16 (DP-16). These flows are conveyed under the proposed roadway to the north, discharging via a proposed private 18-inch FES that discharges to a riprap splash pad before continuing along historic paths at a velocity of 4.01 ft/s which is compliant with DCM values for stable channel flow. See appendix A for supporting calculations.

Design Point 17 (Rational (Q_5 = 4.9 cfs, Q_{100} = 26.9 cfs) HEC-HMS (Q_5 = 1.1 cfs, Q_{100} = 5.0 cfs)) (sub-basin: PR-6; Area: 13.9 Ac.) (Slopes: 5 to 60%) This point represents the flows from sub-basin PR-6 that have been collected in the roadside ditch that runs along the south side of the proposed roadway. The roadside ditch along this stretch will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private Type C Inlet at Design Point 17 (DP-17). These flows are conveyed under the proposed roadway to the north, discharging via a proposed private 18-inch FES that discharges to a riprap splash pad before continuing along historic paths at a velocity of 2.95 ft/s which is compliant with DCM values for stable channel flow. See appendix A for supporting calculations.

Matrix Design Group, Inc., 2023©

Design Point 18 (Rational (Q_5 = 9.0 cfs, Q_{100} = 49.0 cfs) HEC-HMS (Q_5 = 2.3 cfs, Q_{100} = 10.6 cfs)) (sub-basin: PR-7; Area: 27.8 Ac.) (Slopes: 5 to 60%) This point represents the flows from sub-basin PR-7 that have been collected in the roadside ditch that runs along the south side of the proposed roadway. The roadside ditch along this stretch will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private Type C Inlet at Design Point 18 (DP-18). These flows are conveyed under the proposed roadway to the north via proposed private 18" RCP, to be combined with the flows collected at Design Point 20a (DP-20a).

Design Point 19 (Rational (Q_5 = 5.5 cfs, Q_{100} = 31.7 cfs) HEC-HMS (Q_5 = 1.2 cfs, Q_{100} = 6.1 cfs)) (sub-basin: OS3a, PR-9; Area: 18.3 Ac.) (Slopes: 5 to 10%) This point represents the flows from sub-basins OS3a, and PR-9 that have been collected in the roadside ditch that runs along the south side of the proposed roadway downstream of DP-19. The roadside ditch along this stretch will be lined with vegetation. These flows travel northeast in the ditch before being collected in the proposed private 18" FES at Design Point 19 (DP-19). These flows are conveyed under the proposed roadway to the west via proposed private 18" RCP.

Design Point 20 (Rational (Q_5 = 29.8 cfs, Q_{100} = 166.4 cfs) HEC-HMS (Q_5 = 9.5 cfs, Q_{100} = 43.0 cfs)) (sub-basins: OS1a, OS1b, OS2a, OS2b, OS2c, OS2d, OS2e, PR-1a, PR-1b, PR-1c, PR-2, PR-3, PR-4, PR-5, PR-6; Area: 234.0 Ac.) (Slopes: 5 to 50%) This point represents the outfall from the proposed private swale located along the northwestern border of the proposed private pond (Pond 1). The combined flows from sub-basins OS1a, OS1b, OS2a, OS2b, OS2c, OS2d, OS2e, PR-1a, PR-1b, PR-1c, PR-2, PR-3, PR-4, PR-5, and PR-6, are collected in the proposed swale and diverted around Pond 1 toward the proposed stilling basin at Design Point 22. The proposed swale will be lined with Type L Rip Rap.

Design Point 21a (Rational (Q_5 = 5.2 cfs, Q_{100} = 10.8 cfs) HEC-HMS (Q_5 = 3.3 cfs, Q_{100} = 7.8 cfs)) (sub-basins: PR-10a; Area: 4.7 Ac.) (Slopes: 2.8 to 6%) This point represents the Proposed Private Type-C inlet located on the north side of the proposed roadway southwest of the proposed pond (Pond 1). All flows from the proposed roadway will drain to the north and into the northern roadside ditch. All runoff from the proposed roadway will drain to the Type C inlet at Design Point 21a. The flows collected in the inlet will be conveyed downstream towards the proposed private forebay at Design Point EDB-IN via proposed private 18-inch RCP pipe.

Design Point 21b (Rational (Q_5 = 10.4 cfs, Q_{100} = 40.4 cfs) HEC-HMS (Q_5 = 5.3 cfs, Q_{100} = 17.9 cfs)) (sub-basins: PR-7, PR-10a; Area: 32.5 Ac.) (Slopes: 2.8 to 6%) This point represents the combination of flows from design points 18 and 21a. The combined flows will be conveyed downstream towards the proposed private forebay at Design Point EDB-IN via proposed private 18-inch RCP pipe.

Design Point EDB-IN (Rational (Q_5 = 11.4 cfs, Q_{100} = 44.5 cfs) HEC-HMS (Q_5 = 4.9 cfs, Q_{100} = 16.5 cfs)) (sub-basins: PR-7, PR-10a, PR-10b, PR-11; Area: 35.3 Ac.) (Slopes: 2.8 to 50%) This point represents the total discharge into the Proposed Private Extended Detention Basin (EDB). Flows will be treated for water quality and released at such a rate that the overall discharge from the site does not increase under proposed conditions.

Design Point EDB-OUT (Q_5 = 4.0 cfs, Q_{100} = 15.9 cfs) (sub-basins: PR-7, PR-10a, PR-10b, PR-11; Area: 35.3 Ac.) (Slopes: 2.8 to 50%) This point represents the discharge from the EDB. The

Matrix Design Group, Inc., 2023©

discharge from Pond 1 will be routed downstream via proposed private 18-inch RCP pipe that will convey the flows to the proposed private stilling basin located at Design Point 22.

Design Point 22 (Rational (Q_5 = 50.2 cfs, Q_{100} 260.0 = cfs) HEC-HMS (Q_5 = 10.9 cfs, Q_{100} = 49.1 cfs) (design points: DP-EDB-OUT, DP-19, DP-20; Area: 283.1 Ac.) (Slopes: 2.8 to 50%) This point represents the proposed private stilling basin located north of proposed Pond 1. Flows from Design Points 19, 20, and EDB-OUT all discharge to the stilling basin which will release the flows at a velocity of 1.57 ft/sec.

Design Point 23 (Rational (Q_5 = 56.1 cfs, Q_{100} = 295.8 cfs) HEC-HMS (Q_5 = 11.5 cfs, Q_{100} = 53.0 cfs)) (sub-basins: DP-22, OS3b, PR-12; Area: 302.8 Ac.) (Slopes: 2.8 to 60%) This point represents the total discharge from the site. Stormwater runoff from the site will continue north in the existing channel before draining into Hay Creek, a tributary of Beaver Creek.

Design Point HC (Q_{100} = 127 cfs) This point represents the stormwater flows in Hay Creek at the proposed private 48" x 48" Box culvert to the north of the site. The proposed private 48" x 48" culvert conveys the flows in Hay Creek under the proposed access road. Culvert calculations for the existing and proposed culvert at DP-HC can be found in Appendix A. The proposed flows in Hay Creek come from the HEC-2 analysis provided by the Regional Floodplain Administrator. The HEC-2 results are included in **appendix C**.

Notes:

- **MHFD-Detention Analysis for the proposed detention pond (Pond 1) which will be constructed as part of the Improvements associated with Hay Creek Valley can be found in Appendix A of this report.**
- **Though the storm pipes are shown as RCP they have been modeled in StormCAD as CMP with a Manning's n of 0.024 which is a more conservative design. Based on the analysis, CMP pipes can be used in place of RCP.**
- **Tables summarizing inlet sizes and capacities, storm pipe sizes and capacities and swale capacities for the proposed improvements can be found in Appendix A and/or in the following section.**
- **All ponds and associated infrastructure are to be owned and maintained by the HOA.**
- **The ratio of the total site discharge in proposed conditions vs existing conditions is 0.8, representing no significant increase in flows in the proposed condition.**
- **The hydraulic model for Beaver Creek indicated approximately 127 cfs from the entire Hay Creek tributary basin which contains the development. We therefore believe the above hydrological analysis with the Rational Method to be quite conservative.**

V. Hydraulic Analysis

a. Proposed Inlets

This project will use Type-C inlets in sump conditions. Sump inlet capacities have been determined utilizing the nomographs available from the El Paso County Drainage Criteria Manual Volume 1 (DCM). Riprap protection has been provided around all inlets to minimize erosion. To ensure a

Matrix Design Group, Inc., 2023©

suitable outfall from each storm drain, outlet protection sized according to the criteria set forth by the DCM has been provided at the outfall of each storm drain. The stormwater velocities at each discharge point have been calculated to ensure the outfalls are suitable. See design point descriptions for further details. The table below lists inlets by design point and corresponding capacity. Figure 1 shows the capacities for Type C inlets in sump conditions.

INLET SUMMARY *HAY CREEK VALLEY*										
DESIGN POINT or SUB-BASIN	*SUB-BASINS/ DESCRIPTION*	*TOTAL AREA (AC)*	*INLET*			*Q(5) TOTAL INFLOW*	*Q5 INLET CAPACTIY*	*Q(100) BYPASS FLOWS (cfs)*	*Q(100) TOTAL INFLOW (cfs)*	*MAX INLET CAPACITY*
			SIZE (Ft.)	*TYPE*	*CONDITION*					
11	**OS1b, OS2a, PR-1a**	77.15	3x6	D	**SUMP**	3.7	**39.0**	**0.0**	19.5	**39.0**
12a	**OS1a, PR-1b**	15.63	3x3	D	**SUMP**	1.3	**39.0**	**0.0**	6.1	**39.0**
13	**OS2b, PR-2**	12.51	3x3	C	**SUMP**	1.1	**16.0**	**0.0**	5.3	**16.0**
14	**OS2c, PR-3**	24.32	3x3	C	**SUMP**	1.4	**16.0**	**0.0**	5.5	**16.0**
15	**OS2d, PR-4**	17.18	3x3	C	**SUMP**	1.5	**16.0**	**0.0**	6.6	**16.0**
16	**OS2e, PR-5**	20.09	3x3	C	**SUMP**	1.6	**16.0**	**0.0**	7.2	**16.0**
17	**PR-6**	20.01	3x3	C	**SUMP**	1.1	**16.0**	**0.0**	5.0	**16.0**
18	**PR-7**	21.64	3x3	C	**SUMP**	2.3	**16.0**	**0.0**	10.6	**16.0**
21a	**PR-8a**	4.73	3x3	C	**SUMP**	3.3	**16.0**	**0.0**	7.8	**16.0**

Note: Inlet sizes indicated are minimums. Larger sizes may be used in the construction plans for conservative design.

Matrix Design Group, Inc., 2023©



Figure 1

Inlet Overflow Routing	
Inlet	***Overflow Routing Under Sump Inlet Blockage Conditions***
11	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff across the proposed driveway and into the type C inlet at DP-12a.
12a	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff across the proposed driveway to the east before continuing along historic paths.
13	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff to the east and continue in the roadside swale before being collected in the proposed Type C inlet at DP-14.
14	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff to the east and continue in the roadside swale before being collected in the proposed Type C inlet at DP-15.
15	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff to the east and continue in the roadside swale before being collected in the proposed Type C inlet at DP-16.
16	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff to the east and continue in the roadside swale before being collected in the proposed Type C inlet at DP-17.
17	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff to the east and continue in the roadside swale before being collected in the proposed Type C inlet at DP-18.
18	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff across the proposed roadway and into the type C inlet at DP-21a.
21a	Blockage of this inlet will cause runoff to surcharge the sump and direct runoff into the proposed Extended Detention Basin.

b. Swales

The initial swale analysis was performed using Hydraflow Express to determine flow depths and velocities. Per the El Paso County DCM Volume 1, Chapter 6, section 6.5.2. Channel Velocity, "***Concrete, riprap, or soil cement linings as approved by the City/County shall be used where channel bottom velocities exceed 6.0 ft/sec***. *Grass lined channels shall not be used where*

Matrix Design Group, Inc., 2023©

velocity exceeds permissible velocities in Table 10-4 or the Froude number is greater than 0.9 for the 100-year storm." Table 10-4 is included in Appendix B for reference. Concentrated stormwater flows that drain along the existing drainage path through sub-basin PR-1c will be collected in a proposed swale west of proposed Pond 1 which will direct the flows around the pond. A 25-foot drainage easement will extend from proposed lot 1 to lot 9 along the existing drainage path to ensure that future developments do not impede the flow of stormwater through the site. The swale calculations have been applied to the most critical swale scenarios for the Site. The table below summarizes the various swales included as part of these improvements.

Swale Capacities						
HAY CREEK VALLEY						
Design Point	Armoring Type	Anticipated Slope %	CHANNEL CAPACITY MAJOR STORM (cfs)	Q(100) TOTAL FLOW (cfs)	Q(100) VELOCTIY (FT/S)	Q100 Flow Depth (ft)
13	Vegetation	5.0%	**5.3**	5.3	3.87	**0.32**
14	Vegetation	4.6%	**5.5**	5.5	3.86	**0.33**
15	Vegetation	4.6%	**6.6**	6.6	4.13	**0.36**
16	Vegetation	4.6%	**7.2**	7.2	4.19	**0.38**
17	Vegetation	4.9%	**5.0**	5.0	3.80	**0.31**
18	Vegetation	4.9%	**10.6**	10.6	4.76	**0.46**
19	Vegetation	2.6%	**6.1**	6.1	3.21	**0.41**
20	Vegetation	2.0%	**43.0**	43.0	4.20	**0.69**
21a	Vegetation	4.8%	**7.8**	7.8	4.39	**0.39**

Note:
1. Basins have been reconfigured as compared to those discussed in the approved MDDP to design for stable velocities under vegetated conditions.
2. Flows at design point 20 exceed 15 cfs and are therefore provided either a drainage easement or contained within a tract.

c. Driveway Culverts

Upon the development of the proposed lots, it will be necessary to place culverts along the roadside ditches to convey flows through driveways. Initial calculations for driveway culvert sizing at each lot is summarized in the table below:

Matrix Design Group, Inc., 2023©

Driveway Culvert Sizes HAY CREEK VALLEY			
Lot	**Q(100) TOTAL FLOW IN DITCH (cfs)**	**Anticipated Slope %**	**Minimum Culvert Inside Diameter (in)**
1-10	7.8	4.8%	**18**
11-12	5.3	5.0%	**18**
13	9.2	4.8%	**18**
14-15	6.7	4.8%	**18**
16	7.2	4.8%	**18**
17-18	7.9	4.8%	**18**
19	9.7	4.8%	**18**
20	6.1	2.7%	**18**

d. Storm Pipes

Preliminary sizing of storm sewer has been completed using the Manning's channel flow calculation. To confirm DCM compliant capacity and velocity values the site has been modeled in StormCAD using the Standard head loss method and head loss values taken from Table 9-4 of the DCM. HGL profiles modeled in StormCAD are included in Appendix C. Outfall protection has been provided at discharge points in accordance with DCM standards. Outfall protection calculations are included in Appendix A. All outfalls have been designed to provide flow velocities consistent with a stable and suitable outfall.

e. Detention

Due to the development of the site and the resulting increase in imperviousness, detention will be required to limit the 100-year discharge to historic rates. The proposed private Extended Detention Basin (Pond 1) has been designed to over detain stormwater flows to reduce the total site discharge to predevelopment levels. The pond will provide detention and water quality treatment for stormwater runoff generated within the Hay Creek Valley site. The proposed private Forebay at the southwestern corner of Pond 1 has been sized based on the untreated WQCV calculated in the UD-BMP worksheet. The forebay calculations and UD-BMP worksheet can be found in Appendix A. The proposed private trickle channel has been sized to accommodate double the release from the proposed private forebay at a minimum. Trickle channel calculations are included in Appendix A. Pond 1 will outfall to a stilling basin to the north. Flows from the pond will combine with flows from Design Points 19 and 20 in the stilling basin which will release the flows with a velocity of 1.57 ft/sec during the 100-year storm event which is considered by the DCM to be stable for the major storm event in the context of open channel flows. The stilling basin will provide a suitable outfall for the concentrated flows into the existing natural swale. The proposed stilling basin has a depth of 24-inches and, when at max capacity, will infiltrate the full volume within 40 hours. Infiltration rates have been determined using the f_0 value for type B soils in Table 6-7 of the MHFD Drainage Criteria Manual Volume 1 (below). Design information including calculations are included in Appendix A. The table below summarizes the detention provided for this development.

Matrix Design Group, Inc., 2023©

Proposed Pond Summary HAY CREEK VALLEY								
Pond	Tributary Area	% Impervious	Pre-Development Peak		Pond Outflow		Pre vs. Post Ratio	
			Q5	Q100	Q5	Q100	Q5	Q100
Pond 1	29.19	17.08	6.2	28.2	2.7	15.2	0.4	0.5

Table 6-7. Recommended Horton's equation parameters

NRCS Hydrologic Soil Group	Infiltration (inches per hour)		Decay Coefficient—a
	Initial—f_i	Final—f_o	
A	5.0	1.0	0.0007
B	4.5	0.6	0.0018
C	3.0	0.5	0.0018
D	3.0	0.5	0.0018

Emergency Overflow
Pond 1: If the emergency overflow weir receives flows, these flows will continue downstream along the existing natural swale and drain into Hay Creek.

VI. Storm Water Quality

Per the DCM Volume 2, Section 4.1, El Paso County recommends the MHFD Four Step Process for receiving water protection that focuses on reducing runoff by disconnecting impervious area, eliminating "unnecessary" impervious area and encouraging infiltration into soils that are suitable, treat and slowly release the WQCV, stabilize stream channels, and implement source controls. The four-step process has been completed below.

Step 1: **Employ Runoff Reduction Practices.**

- The low-density nature of this development and the fact that none of the streets will have curb and gutter, means that most, if not all, runoff from impervious surfaces will sheet flow across pervious areas to grass buffers. The grass buffers, located alongside the proposed roadway will provide runoff reduction for the impervious areas that drain to them.

Step 2: **Stabilize Drainageways.**

- The site is in the Beaver Creek Drainage Fee Basin. Drainage fees, to be paid by the relevant Hay Creek Valley developers at the time of platting, will help fund proposed channel improvements. Information on planned future improvements to the Beaver Creek channel was unavailable for this report.

Matrix Design Group, Inc., 2023©

Step 3: **Provide Water Quality Capture Volume (WQCV).**

- As required by the DCM, runoff from the proposed streets which is feasible to detain, is directed into a proposed detention pond (Pond 1) via grass lined swale. The pond has been designed to meet the DCM standards for the release rates of Full Spectrum Detention Ponds for Water Quality Capture Volumes, and all of the other storm events listed in the MHFD- Detention spreadsheet. Exclusions are listed below:

    - The lots containing large lot residential sites are excluded from WQ treatment per section I.7.1.b.5 of the ECM.

    - Disturbed areas that are not practicable to detain are excluded from WQ treatment per section I.7.1.C.1.a.

  Runoff reduction calculations have been provided for those portions of the proposed roadway that are not being detained to show compliance with the DCM requirements for treatment of the WQCV. Runoff Reduction calculations can be found in Appendix A.

Step 4: **Consider Need for Industrial and Commercial BMPs.**

- There are no commercial or industrial components of this development, therefore no BMPs of this nature are required.

VII. Erosion Control Plan

A grading and erosion control plan (GEC) for the proposed improvements will be submitted for review as separate submittals by the various developments. These will incorporate straw wattles, straw bale check dams, silt fence, vehicle tracking control, inlet & outlet control, sedimentation basins and other best management practices (CMs) identified in the DCM Volume 2.

VIII. Floodplains

Per the *Flood Insurance Rate Map (FIRM) 08041CO267 G*, effective date December 7, 2018, published by the Federal Emergency Management Agency (FEMA), Hay Creek, a Tributary to Beaver Creek runs along the northern bound of the Hay Creek Valley area and has designated 100-year floodplain. The developed portion of the site is generally not touched by the 100 year floodplain, however the road improvements associated with this site will cross the FEMA floodplain at the location where the site access easement crosses Hay Creek. Draft model backed BFEs for this area have been developed as part of Phase 1 for the ongoing El Paso County, CO, Risk MAP Project. The data have been reviewed and approved through FEMA's QA/QC process (May 11, 2022) and are currently in the MIP (Case No. 19-08-0037s). This data is considered "FEMA APPROVED BFEs" This will need to be shown on the prelim plan and plat. Refer to the map in Appendix C.

Matrix Design Group, Inc., 2023©

IX. Fee Development

a. UNDEVELOPED PLATTABLE LAND

The Hay Creek Valley site is located within the Beaver Creek Drainage Fee Basin and within previously unplatted land. The 2023 Drainage Basin Fees for the Beaver Creek Drainage Fee Basin are: $13,797/impervious acre for the Drainage Fee and $0.00/impervious acre for the Bridge Fee. Per the ***El Paso County Engineering Criteria Manual,*** Appendix L, Section 3.10.1a Fee Reductions for Low Density Lots, with the site being developed into 5-acre lots, drainage fees may be reduced by 25%.

Hay Creek
Final Drainage Report
2023 Drainage and Bridge Fees

	Platted Area (Acres)	Imperviousness (%)	Platted Area (Imp. ac.)	Fee/ Imp. Acre	Fee Due	Drainage Fee Reduction	Fee Due at Platting
Drainage Fee	214.63	8.12	17.428	$13,797.00	$240,453.51	$60,113.38	$180,340.13
Bridge Fee	214.63	8.12	17.428	$0.00	$0.00	$0.00	$0.00
TOTAL							$180,340.13

Matrix Design Group, Inc., 2023©

Cost Estimate

Table 12.1

Engineer's Estimate of Probable Construction Costs				
BEAVER CREEK				
HAY CREEK VALLEY				
Private Non-Reimbursable				
Item	Unit	Quantity	Unit Cost	Extension
18" RCP/HP	LF	632	$76.00	$48,032.00
30" RCP/HP	LF	133	$114.00	$15,162.00
36" RCP/HP	LF	185	$140.00	$25,900.00
18" FES	EA	7	$456.00	$3,192.00
30" FES	EA	1	$684.00	$684.00
36" FES	EA	1	$840.00	$840.00
Type C Inlet	EA	6	$6,000.00	$36,000.00
Type D Inlet	EA	2	$7,000.00	$14,000.00
RIPRAP	CY	900	$135.00	$121,500.00
			Sub Total	$265,310.00
			10% Contingency	$26,531.00
			TOTAL:	**$291,841.00**

Engineer's Estimate of Probable Construction Costs				
BEAVER CREEK				
HAY CREEK VALLEY				
Permanent BMP (EDB): Private Non-reimbursable				
Item	Unit	Quantity	Unit Cost	Extension
DETENTION POND GRADING	EA	1	$35,000.00	$35,000.00
3' TRICKLE CHANNEL	LF	310	$250.00	$77,500.00
FOREBAY	EA	1	$40,000.00	$40,000.00
OUTLET STRUCTURE	EA	1	$40,000.00	$40,000.00
EMERGENCY SPILLWAY	EA	1	$5,000.00	$5,000.00
STILLING BASIN	EA	1	$30,000.00	$30,000.00
			Sub Total	$227,500.00
			10% Contingency	$22,750.00
			TOTAL:	**$250,250.00**
			Overall Total	**$542,091.00**

Matrix Design Group, Inc., 2023©

Since the engineer has no control over the cost of labor, materials, equipment, or services furnished by others, or over the contractor's method of determining prices, or over the competitive bidding or market conditions, the opinion of probable construction costs provided herein are made on the basis of the engineer's experience and qualifications and represents the best judgment as an experienced and qualified professional familiar with the construction industry. The engineer cannot, and does not guarantee that proposals, bid or actual construction costs will not vary from the opinion of probable costs.

X. Summary

This report demonstrates that the proposed infrastructure associated with Hay Creek Valley is in conformance with the El Paso County Drainage Criteria Manual, Volumes 1 and 2, October 2018 and all previously approved studies related to the project site. Stormwater flows will generally remain the same in post-development conditions (Rational (Q_5 = 53.7 cfs, Q_{100} = 282.8 cfs) HEC-HMS (Q_5 = 12.9 cfs, Q_{100} = 59.4 cfs)) as in pre-development conditions (Rational (Q_5 = 35.0 cfs, Q_{100} = 210.9 cfs) HEC-HMS (Q_5 = 11.2 cfs, Q_{100} = 69.9 cfs)). These proposed improvements should not adversely affect downstream or surrounding developments and are in conformance with the pertinent studies for the area.

Matrix Design Group, Inc., 2023©

XI. References

1. *El Paso County and City of Colorado Springs Drainage Criteria Manual, Volume 1 & 2*, El Paso County, May 2014
2. *El Paso County Engineering Criteria Manual,* El Paso County, Rev. December 2016
3. *Web Soil Survey of El Paso County Area, Colorado. Unites States Department of Agriculture Soil Conservation Service*.
4. *Flood Insurance Rate Maps for El Paso County, Colorado and Incorporated Areas, Panel 279 of 1275, Federal Emergency Management Agency*, Effective Date December 7, 2018.
5. *Urban Storm Drainage Criteria Manual, Vol. 1-3* by Urban Drainage and Flood Control District (UDFCD), January 2016

Matrix Design Group, Inc., 2023©

Appendices

Matrix Design Group, Inc., 2023©

APPENDIX A

HYDROLOGIC AND HYDRAULIC CALCULATIONS

Rational Method - Existing Conditions

Project Name: Hay Creek
Project Location: El Paso County, Colorado
Designer WCG
Notes: EXISTING CONDITIONS

Avg. Channel Velocity 4 ft/s (If specific channel vel is used, this will be ignored)
Avg. Slope for Initial Flow 0.04 ft/ft (If Elevations are used, this will be ignored)

Channel Flow Type Key
Heavy Meadow 2
Tillage/Field 3
Short Pasture and Lawns 4
Nearly Bare Ground 5
Grassed Waterway 6
Paved Areas 7

7% 100% 2%

Sub-basin	Comments	Area			Soil Group	Rational 'C' Values										Percent Impervious	Flow Lengths										Tc	Rainfall Intensity & Rational Flow Rate							Sub-basin
						5-Acre Lots (7% Impervious)			Pavement (100% Impervious)			Undeveloped/Pervious Areas (2% Impervious)			Composite			Initial	True Initial	Channel	True Channe	Average (decimal)	Initial	Average (%)	Channel Flow Type (See Key above)	Velocity	Channel	Total	i5	Q5	HEC-HMS Q5	i100	Q100	HEC-HMS Q100	
		sf	acres	Sq. Mi.		C5	C100	Area (SF)	C5	C100	Area (SF)	C5	C100	Area	C5	C100		ft	Length ft	ft	Length ft	Slope	Tc (min)	Slope	Ground Type	(ft/s)	Tc (min)	(min)	in/hr	cfs	cfs	in/hr	cfs	cfs	
EX-OS1a		407292	9.35	0.0146	B	0.12	0.39	407292	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	672	672	0.10	14.23	9.9	4	2.20	5.09	19.31	3.07	**3.5**	**0.8**	5.15	**18.9**	**4.1**	*EX-OS1a*
EX-OS1b		2579029	59.21	0.0925	B	0.12	0.39	1173596	0.90	0.96		0.09	0.36	1405433	0.10	0.37	4.28%	300	300	2754	2754	0.07	16.48	6.7	4	1.81	25.33	41.80	1.99	**12.3**	**2.6**	3.34	**74.6**	**15.7**	*EX-OS1b*
EX-OS2a		692771	15.90	0.0248	B	0.12	0.39		0.90	0.96	25423	0.09	0.36	667348	0.12	0.38	5.60%	300	300	84	84	0.31	9.70	31.3	4	3.50	0.40	10.10	4.09	**7.8**	**1.5**	6.87	**42.0**	**8.0**	*EX-OS2a*
EX-OS2b		120503	2.77	0.0043	B	0.12	0.39		0.90	0.96	6033	0.09	0.36	114470	0.13	0.39	6.91%	300	300	113	113	0.15	12.31	14.8	4	2.69	0.70	13.00	3.69	**1.3**	**0.3**	6.20	**6.7**	**1.4**	*EX-OS2b*
EX-OS2c		137929	3.17	0.0049	B	0.12	0.39		0.90	0.96	6548	0.09	0.36	131381	0.13	0.39	6.65%	268	268	0	0	0.17	11.09	17.2	4	2.90	0.00	11.09	3.94	**1.6**	**0.3**	6.62	**8.2**	**1.6**	*EX-OS2c*
EX-OS3		354850	8.15	0.0127	B	0.12	0.39		0.90	0.96	475	0.09	0.36	354375	0.09	0.36	2.13%	300	300	265	265	0.16	12.54	15.8	4	2.78	1.59	14.12	3.56	**2.7**	**0.2**	5.98	**17.7**	**2.0**	*EX-OS3*
EX-OS4		30365	0.70	0.0011	B	0.12	0.39		0.90	0.96	20445	0.09	0.36	9920	0.64	0.76	67.98%	175	175	0	0	0.02	8.78	2.0	7	2.83	0.00	8.78	4.30	**1.9**		7.23	**3.9**		*EX-OS4*
EX-1		2441168	56.04	0.0876	B	0.12	0.39		0.90	0.96	30061	0.09	0.36	2411107	0.10	0.37	3.21%	300	300	4763	4763	0.05	18.23	5.0	4	1.57	50.72	68.94	1.44	**8.2**	**1.6**	2.43	**50.4**	**9.9**	*EX-1*
EX-2		2100638	48.22	0.0754	B	0.12	0.39		0.90	0.96	46438	0.09	0.36	2054200	0.11	0.37	4.17%	300	300	2795	2795	0.06	16.66	6.4	4	1.77	26.31	42.96	1.96	**10.3**	**2.0**	3.29	**59.7**	**11.2**	*EX-2*
EX-3		2684942	61.64	0.0963	B	0.12	0.39		0.90	0.96	31890	0.09	0.36	2653052	0.10	0.37	3.16%	300	300	2002	2002	0.11	13.86	11.4	4	2.36	14.12	27.97	2.52	**15.6**	**2.3**	4.23	**96.6**	**14.7**	*EX-3*
EX-4		256265	5.88	0.0092	B	0.12	0.39		0.90	0.96	0	0.09	0.36	256265	0.09	0.36	2.00%	206	206	0	0	0.29	8.53	28.6	4	3.50	0.00	8.53	4.35	**2.3**	**2.3**	7.30	**15.6**	**15.6**	*EX-4*
EX-5		1865454	42.82	0.0669	B	0.12	0.39		0.90	0.96	18117	0.09	0.36	1847337	0.10	0.37	2.95%	300	300	1427	1427	0.11	14.18	10.7	4	2.29	10.39	24.56	2.71	**11.4**	**1.5**	4.55	**71.8**	**10.0**	*EX-5*
DESIGN POINTS	*Sub-basins*																																	*DESIGN POINTS*
1	*EX-OS1a*	407292	9.35	0.0146	B	0.12	0.39	407292	0.90	0.96	0	0.09	0.36	0	0.12	0.39	7.0%	300	300	672	672	0.10	14.23	9.9	4	2.20	5.09	19.31	3.07	**3.5**	**0.8**	5.15	**18.9**	**4.1**	*1*
2	*EX-OS1b*	2579029	59.21	0.0925	B	0.12	0.39	1173596	0.90	0.96	0	0.09	0.36	1405433	0.10	0.37	4.3%	300	300	2754	2754	0.07	16.48	6.7	4	1.81	25.33	41.80	1.99	**12.3**	**2.6**	3.34	**74.6**	**15.7**	*2*
3	*EX-OS2a*	692771	15.90	0.0248	B	0.12	0.39		0.90	0.96	25423	0.09	0.36	667348	0.12	0.38	5.6%	300	300	84	84	0.31	9.70	31.3	4	3.50	0.40	10.10	4.09	**7.8**	**1.5**	6.87	**42.0**	**8.0**	*3*
4	*EX-OS2b*	120503	2.77	0.0043	B	0.12	0.39		0.90	0.96	6033	0.09	0.36	114470	0.13	0.39	6.9%	300	300	113	113	0.15	12.31	14.8	4	2.69	0.70	13.00	3.69	**1.3**	**0.3**	6.20	**6.7**	**1.4**	*4*
5	*EX-OS2c*	137929	3.17	0.0049	B	0.12	0.39		0.90	0.96	6548	0.09	0.36	131381	0.13	0.39	6.7%	268	268	0	0	0.17	11.09	17.2	4	2.90	0.00	11.09	3.94	**1.6**	**0.3**	6.62	**8.2**	**1.6**	*5*
6	*EX-OS3*	354850	8.15	0.0127	B	0.12	0.39		0.90	0.96	475	0.09	0.36	354375	0.09	0.36	2.1%	300	300	265	265	0.16	12.54	15.8	4	2.78	1.59	14.12	3.56	**2.7**	**0.2**	5.98	**17.7**	**2.0**	*6*
7	*EX-4*	256265	5.88	0.0092	B	0.12	0.39		0.90	0.96	0	0.09	0.36	256265	0.09	0.36	2.0%	206	206	0	0	0.29	8.53	28.6	4	3.50	0.00	8.53	4.35	**2.3**	**2.3**	7.30	**15.6**	**15.6**	*7*
8	*EX-OS1b, EX-OS2a, EX-2*	5372438	123.33	0.1927	B	0.12	0.39	1173596	0.90	0.96	71861	0.09	0.36	4126981	0.11	0.37	4.4%	300	300	2795	2795	0.06	16.67	6.4	4	1.77	26.31	42.97	1.96	**26.1**	**5.4**	3.29	**153.1**	**30.9**	*8*
9	*EX-OS2b, EX-OS2c, EX-3*	2943374	67.57	0.1056	B	0.12	0.39		0.90	0.96	44471	0.09	0.36	2898903	0.10	0.37	3.5%	300	300	2002	2002	0.11	13.82	11.4	4	2.36	14.12	27.93	2.52	**17.6**	**2.9**	4.24	**106.5**	**17.4**	*9*
10	*EX-OS3, EX-5*	2220304	50.97	0.0796	B	0.12	0.39		0.90	0.96	18592	0.09	0.36	2201712	0.10	0.37	2.8%	300	300	1427	1427	0.11	14.19	10.7	4	2.29	10.39	24.58	2.71	**13.5**	**1.8**	4.55	**85.3**	**11.9**	*10*
11	*DP-8, DP-9, DP-10, EX-OS1a, EX-1*	13384576	307.27	0.4801	B	0.12	0.39	1580888	0.90	0.96	164985	0.09	0.36	11638703	0.10	0.37	3.8%	300	300	8062	8062	0.05	18.17	5.0	4	1.57	85.84	104.01	1.09	**35.0**	**11.2**	1.84	**210.9**	**69.9**	*11*
HC	*From PPRBD Regional floodplane Administrator*																															**127.0**	**127.0**	*HC*

Rational Method - Proposed Conditions

Project Name:	Hay Creek
Project Location:	El Paso County, Colorado
Designer	WCG
Notes:	Proposed Condition

Average Channel Velocity 4.00 ft/s (If specific channel vel is used, this will be ignored)
Average Slope for Initial Flow 0.04 ft/ft (If Elevations are used, this will be ignored)

Channel Flow Type Key
Heavy Meadow 2
Tillage/Field 3
Short Pasture and Lawns 4
Nearly Bare Ground 5
Grassed Waterway 6
Paved Areas 7

		Area				Rational 'C' Values										Flow Lengths								Tc	Rainfall Intensity & Rational Flow Rate							
						7%			100%			2%																					
						5-Acre Lots (7% Impervious)			Pavement (100% Impervious)			Undeveloped/Pervious Areas (2% Impervious)			Composite		Percent Impervious	Initial	True Initial	Channel	True Channel	Average (decimal)	Initial	Average (%)	Channel Flow Type (See Key above)	Velocity	Channel	Total	i5	Q5	HEC-HMS Q5	i100	Q100	HEC-HMS Q100	
Sub-basin	**Comments**	sf	acres	Sq. Mi.	Soil Group	C5	C100		C5	C100	Area (SF)	C5	C100	Area	C5	C100		ft	Length ft	ft	Length ft	Slope	Tc (min)	Slope	Ground Type	(ft/s)	Tc (min)	(min)	in/hr	cfs	cfs	in/hr	cfs	cfs	**Sub-basin**
OS1a		407292	9.35	0.0146	B	0.12	0.39	407292	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	672	672	0.10	14.23	9.9	4	2.20	5.09	19.31	3.07	**3.5**	**0.8**	5.15	**18.9**	**3.6**	***OS1a***
OS1b		2579029	59.21	0.0925	B	0.12	0.39	1173596	0.90	0.96		0.09	0.36	1405433	0.10	0.37	4.28%	300	300	2754	2754	0.07	16.48	6.7	4	1.81	25.33	41.80	1.99	**12.3**	**2.6**	3.34	**74.6**	**14.2**	***OS1b***
OS2a		218316	5.01	0.0078	B	0.12	0.39		0.90	0.96	6435	0.09	0.36	211881	0.11	0.38	4.89%	300	300	203	203	0.25	10.54	24.8	4	3.49	0.97	11.51	3.88	**2.2**	**0.4**	6.52	**12.4**	**1.8**	***OS2a***
OS2b		206454	4.74	0.0074	B	0.12	0.39		0.90	0.96	7795	0.09	0.36	198659	0.12	0.38	5.70%	300	300	33	33	0.20	11.18	20.4	4	3.16	0.17	11.34	3.90	**2.2**	**0.4**	6.56	**12.0**	**2.0**	***OS2b***
OS2c		266071	6.11	0.0095	B	0.12	0.39		0.90	0.96	11200	0.09	0.36	254871	0.12	0.39	6.13%	280	280	0	0	0.35	8.99	35.0	4	3.50	0.00	8.98	4.27	**3.3**	**0.8**	7.17	**17.0**	**2.7**	***OS2c***
OS2d		120503	2.77	0.0043	B	0.12	0.39		0.90	0.96	6033	0.09	0.36	114470	0.13	0.39	6.91%	300	300	44	44	0.13	12.72	13.4	4	2.56	0.29	13.01	3.69	**1.3**	**0.3**	6.19	**6.7**	**1.1**	***OS2d***
OS2e		137929	3.17	0.0049	B	0.12	0.39		0.90	0.96	6548	0.09	0.36	131381	0.13	0.39	6.65%	285	285	0	0	0.15	11.87	15.4	4	2.75	0.00	11.86	3.83	**1.6**	**0.3**	6.44	**8.0**	**1.3**	***OS2e***
OS3a		212463	4.88	0.0076	B	0.12	0.39		0.90	0.96		0.09	0.36	212463	0.09	0.36	2.00%	300	300	27	27	0.09	15.39	8.6	4	2.05	0.22	15.61	3.40	**1.5**	**0.1**	5.71	**10.1**	**0.9**	***OS3a***
OS3b		143157	3.29	0.0051	B	0.12	0.39		0.90	0.96		0.09	0.36	143157	0.09	0.36	2.00%	300	300	195	195	0.22	11.24	22.0	4	3.28	0.99	12.22	3.79	**1.1**	**0.1**	6.36	**7.6**	**0.8**	***OS3b***
OS4		30365	0.70	0.0011	B	0.12	0.39		0.90	0.96	20445	0.09	0.36	9920	0.64	0.76	67.98%	175	175	0	0	0.02	8.78	2.0	7	2.83	0.00	8.78	4.30	**1.9**		7.23	**3.9**		***OS4***
PR-1a		563521	12.94	0.0202	B	0.12	0.39	563521	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	479	479	0.05	17.75	5.1	4	1.58	5.05	22.80	2.82	**4.4**	**0.9**	4.73	**24.1**	**4.3**	***PR-1a***
PR-1b		273497	6.28	0.0098	B	0.12	0.39	273497	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	644	644	0.10	14.33	9.7	4	2.18	4.92	19.24	3.07	**2.3**	**0.5**	5.16	**12.7**	**2.5**	***PR-1b***
PR-1c		2318386	53.22	0.0832	B	0.12	0.39	2318386	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	3863	3863	0.05	17.64	5.2	4	1.60	40.33	57.96	1.62	**10.4**	**3.4**	2.72	**56.9**	**15.7**	***PR-1c***
PR-2		338377	7.77	0.0121	B	0.12	0.39	338377	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	576	576	0.12	13.54	11.5	4	2.37	4.04	17.58	3.21	**3.0**	**0.7**	5.40	**16.5**	**3.3**	***PR-2***
PR-3		803224	18.44	0.0288	B	0.12	0.39	803224	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	1250	1250	0.08	15.28	8.1	4	1.99	10.46	25.73	2.64	**5.9**	**0.7**	4.43	**32.1**	**3.3**	***PR-3***
PR-4		618059	14.19	0.0222	B	0.12	0.39	618059	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	1290	1290	0.09	14.74	8.9	4	2.09	10.30	25.03	2.68	**4.6**	**1.2**	4.50	**25.1**	**5.6**	***PR-4***
PR-5		737120	16.92	0.0264	B	0.12	0.39	737120	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	1020	1020	0.08	15.47	7.7	4	1.94	8.75	24.22	2.73	**5.6**	**1.3**	4.58	**30.5**	**6.1**	***PR-5***
PR-6		604142	13.87	0.0217	B	0.12	0.39	604142	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	1180	1180	0.17	11.86	17.1	4	2.89	6.79	18.65	3.12	**5.2**	**1.1**	5.24	**28.6**	**5.0**	***PR-6***
PR-7		1209380	27.76	0.0434	B	0.12	0.39	1209380	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	1400	1400	0.10	14.38	9.6	4	2.17	10.76	25.13	2.67	**9.0**	**2.3**	4.49	**49.0**	**10.6**	***PR-7***
PR-8		255265	5.86	0.0092	B	0.12	0.39	255265	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	206	206	0	0	0.29	8.28	28.6	4	3.50	0.00	8.27	4.39	**3.1**		7.38	**17.0**		***PR-8***
PR-9		585132	13.43	0.0210	B	0.12	0.39	585132	0.90	0.96		0.09	0.36		0.12	0.39	7.00%	300	300	1400	1400	0.10	14.18	10.0	4	2.21	10.54	24.72	2.70	**4.4**	**1.1**	4.53	**23.9**	**5.1**	***PR-9***
PR-10a		206019	4.73	0.0074	B	0.12	0.39		0.90	0.96	129912	0.09	0.36	76107	0.60	0.74	63.80%	300	300	3558	3558	0.05	9.23	4.8	4	1.53	38.67	47.89	1.83	**5.2**	**3.3**	3.07	**10.8**	**7.8**	***PR-10a***
PR-10b		17696	0.41	0.0006	B	0.12	0.39		0.90	0.96	17173	0.09	0.36	523	0.88	0.94	97.10%	50	50	0	0	0.03	1.98	3.0	4	1.21	0.00	5.00	5.10	**1.8**	**0.8**	8.58	**3.3**	**1.7**	***PR-10b***
PR-11		105045	2.41	0.0038	B	0.12	0.39		0.90	0.96		0.09	0.36	130492	0.11	0.45	2.48%	260	260	0	0	0.01	36.14	0.5	4	0.49	0.00	36.13	2.17	**0.6**		3.65	**4.0**		***PR-11***
PR-12		713346	16.38	0.0256	B	0.12	0.39		0.90	0.96	11977	0.09	0.36	701369	0.10	0.37	3.65%	300	300	395	395	0.04	19.25	4.2	4	1.43	4.59	23.84	2.75	**4.7**	**0.6**	4.62	**28.2**	**3.4**	***PR-12***
DESIGN POINTS	***Sub-Basins***																		0		0													***DESIGN POINTS***
1	***OS1a***	407292	9.35	0.0146	B	0.12	0.39	407292	0.90	0.96	0	0.09	0.36	0	0.12	0.39	7.00%	300	300	672	672	0.10	14.23	9.9	4	2.20	5.09	19.31	3.07	**3.5**	**0.8**	5.15	**18.9**	**3.6**	***1***
2	***OS1b***	2579029	59.21	0.0925	B	0.12	0.39	1173596	0.90	0.96	0	0.09	0.36	1405433	0.10	0.37	4.28%	300	300	2754	2754	0.07	16.48	6.7	4	1.81	25.33	41.80	1.99	**12.3**	**2.6**	3.34	**74.6**	**14.2**	***2***
3	***OS2a***	218316	5.01	0.0078	B	0.12	0.39	0	0.90	0.96	6435	0.09	0.36	211881	0.11	0.38	4.89%	300	300	203	203	0.25	10.54	24.8	4	3.49	0.97	11.51	3.88	**2.2**	**0.4**	6.52	**12.4**	**1.8**	***3***
4	***OS2b***	206454	4.74	0.0074	B	0.12	0.39	0	0.90	0.96	7795	0.09	0.36	198659	0.12	0.38	5.70%	300	300	33	33	0.20	11.18	20.4	4	3.16	0.17	11.34	3.90	**2.2**	**0.4**	6.56	**12.0**	**2.0**	***4***
5	***OS2c***	266071	6.11	0.0095	B	0.12	0.39	0	0.90	0.96	11200	0.09	0.36	254871	0.12	0.39	6.13%	280	280	0	0	0.35	8.99	35.0	4	3.50	0.00	8.98	4.27	**3.3**	**0.8**	7.17	**17.0**	**2.7**	***5***
6	***OS2d***	120503	2.77	0.0043	B	0.12	0.39	0	0.90	0.96	6033	0.09	0.36	114470	0.13	0.39	6.91%	300	300	44	44	0.13	12.72	13.4	4	2.56	0.29	13.01	3.69	**1.3**	**0.3**	6.19	**6.7**	**1.1**	***6***
7	***OS2e***	137929	3.17	0.0049	B	0.12	0.39	0	0.90	0.96	6548	0.09	0.36	131381	0.13	0.39	6.65%	285	285	0	0	0.15	11.87	15.4	4	2.75	0.00	11.86	3.83	**1.6**	**0.3**	6.44	**8.0**	**1.3**	***7***
8	***OS3a***	212463	4.88	0.0076	B	0.12	0.39	0	0.90	0.96	0	0.09	0.36	212463	0.09	0.36	2.00%	300	300	27	27	0.09	15.39	8.6	4	2.05	0.22	15.61	3.40	**1.5**	**0.1**	5.71	**10.1**	**0.9**	***8***
9	***OS3b***	143157	3.29	0.0051	B	0.12	0.39	0	0.90	0.96	0	0.09	0.36	143157	0.09	0.36	2.00%	300	300	195	195	0.22	11.24	22.0	4	3.28	0.99	12.22	3.79	**1.1**	**0.1**	6.36	**7.6**	**0.8**	***9***
10	***PR-8***	255265	5.86	0.0092	B	0.12	0.39	255265	0.90	0.96	0	0.09	0.36	0	0.12	0.39	7.00%	206	206	0	0	0.29	8.28	28.6	4	3.50	0.00	8.27	4.39	**3.1**		7.38	**17.0**		***10***
11	***OS1b, OS2a, PR-1a***	3360866	77.15	0.1206	B	0.12	0.39	1737117	0.90	0.96	6435	0.09	0.36	1617314	0.11	0.38	4.77%	300	300	3533	3533	0.07	16.42	6.7	4	1.81	32.50	48.91	1.80	**15.0**	**3.7**	3.03	**88.8**	**19.5**	***11***
12a	***OS1a,PR-1b***	680789	15.63	0.0244	B	0.12	0.39	680789	0.90	0.96	0	0.09	0.36	0	0.12	0.39	7.00%	300	300	1616	1616	0.10	14.23	9.9	4	2.20	12.23	26.45	2.60	**4.9**	**1.3**	4.37	**26.8**	**6.1**	***12a***
12b	***OS1a, OS2a, OS1b, PR-1a, PR-1b***	4041655	92.78	0.1450	B	0.12	0.39	2417906	0.90	0.96	6435	0.09	0.36	1617314	0.11	0.38	5.15%	300	300	3533	3533	0.07	16.38	6.7	4	1.81	32.50	48.88	1.81	**18.4**	**5.0**	3.03	**107.5**	**25.2**	***12b***
13	***OS2b, PR-2***	544831	12.51	0.0195	B	0.12	0.39	338377	0.90	0.96	7795	0.09	0.36	198659	0.12	0.39	6.51%	300	300	908	908	0.12	13.53	11.5	4	2.37	6.38	19.90	3.02	**4.6**	**1.1**	5.08	**24.8**	**5.3**	***13***
14	***OS2c, PR-3***	1069295	24.55	0.0384	B	0.12	0.39	803224	0.90	0.96	11200	0.09	0.36	254871	0.12	0.39	6.78%	300	300	1250	1250	0.08	15.26	8.1	4	1.99	10.46	25.71	2.64	**7.9**	**1.4**	4.44	**42.7**	**5.5**	***14***
15	***OS2d, PR-4***	738562	16.96	0.0265	B	0.12	0.39	618059	0.90	0.96	6033	0.09	0.36	114470	0.12	0.39	6.98%	300	300	1334	1334	0.09	14.72	8.9	4	2.09	10.65	25.36	2.66	**5.5**	**1.5**	4.47	**29.8**	**6.6**	***15***
16	***OS2e, PR-5***	875049	20.09	0.0314	B	0.12	0.39	737120	0.90	0.96	6548	0.09	0.36	131381	0.12	0.39	6.95%	300	300	1300	1300	0.08	15.45	7.7	4	1.94	11.15	26.60	2.59	**6.4**	**1.6**	4.35	**34.4**	**7.2**	***16***
17	***PR-6***	604142	13.87	0.0217	B	0.12	0.39	604142	0.90	0.96	0	0.09	0.36	0	0.12	0.39	7.00%	300	300	1180	1180	0.10	14.18	17.1	4	2.89	6.79	20.97	2.94	**4.9**	**1.1**	4.94	**26.9**	**5.0**	***17***
18	***PR-7***	1209380	27.76	0.0434	B	0.12	0.39	1209380	0.90	0.96	0	0.09	0.36	0	0.12	0.39	7.00%	300	300	1400	1400	0.10	14.38	9.6	4	2.17	10.76	25.13	2.67	**9.0**	**2.3**	4.49	**49.0**	**10.6**	***18***
19	***OS3a, PR-9***	797595	18.31	0.0286	B	0.12	0.39	585132	0.90	0.96	0	0.09	0.36	212463	0.11	0.38	5.67%	300	300	1427	1427	0.10	14.30	10.0	4	2.21	10.74	25.04	2.68	**5.5**	**1.2**	4.50	**31.7**	**6.1**	***19***
20	***PR-1c, DP-12b, DP-13, DP-14, DP-15, DP-16, DP-17***	10191920	233.97	0.3656	B	0.12	0.39	7837214	0.90	0.96	38011	0.09	0.36	2316695	0.12	0.39	6.21%	300	300	8302	8302	0.05	17.71	5.2	4	1.60	86.68	104.38	1.09	**29.8**	**9.5**	1.83	**166.4**	**43.0**	***20***
21a	***PR-10a***	206019	4.73	0.0074	B	0.12	0.39	0	0.90	0.96	129912	0.09	0.36	76107	0.60	0.74	63.80%	300	300	3558	3558	0.05	9.23	4.8	4	1.53	38.67	47.89	1.83	**5.2**	**3.3**	3.07	**10.8**	**7.8**	***21a***
21b	***PR-7, PR-10a***	1415399	32.49	0.0508	B	0.12	0.39	1209380	0.90	0.96	129912	0.09	0.36	76107	0.19	0.44	15.27%	300	300	3558	3558	0.05	16.82	4.8	4	1.53	38.67	55.48	1.67	**10.4**	**5.3**	2.80	**40.4**	**17.9**	***21b***
EDB-IN	***PR-7, PR-10a, PR-10b, PR-11***	1538140	35.31	0.0552	B	0.12	0.39	1209380	0.90	0.96	147085	0.09	0.36	207122	0.19	0.45	15.34%	300	300	3558	3558	0.05	16.77	4.8	4	1.53	38.67	55.43	1.67	**11.4**	**4.9**	2.80	**44.5**	**16.5**	***EDB-IN***
EDB-OUT	***PR-7, PR-10a, PR-10b, PR-11***	1538140	35.31	0.0552	B	0.12	0.39	1209380	0.90	0.96	147085	0.09	0.36	207122	0.19	0.45	15.34%													**2.7**	**4.0**		**15.9**	**15.9**	***EDB-OUT***
22	***EDB-OUT, DP-18, DP-19***	12334202	283.15	0.4424	B	0.12	0.39	9650736	0.90	0.96	185096	0.09	0.36	2523817	0.13	0.39	7.39%													**50.2**	**10.9**		**260.0**	**49.1**	***22***
23	***DP-9, DP-21, PR-12***	13190705	302.82	0.4732	B	0.12	0.39	9650736	0.90	0.96	197073	0.09	0.36	3368343	0.12	0.39	7.13%													**56.1**	**11.5**		**295.8**	**53.0**	***23***
HC	***From FPRBD Regional floodplane Administrator***																															**127.0**	***HC***

INLET SUMMARY

Hay Creek

DESIGN POINT or SUB-BASIN	SUB-BASINS	TOTAL AREA (AC)	INLET			Q(5) BYPASS FLOWS (cfs)	Q(5) TOTAL INFLOW	Q5 INLET CAPACTIY	Q(100) BYPASS FLOWS (cfs)	Q(100) TOTAL INFLOW (cfs)	MAX INLET CAPACITY	NOTES:
			SIZE (Ft.)	TYPE	CONDITION							
11	OS1b, OS2a, PR-1a	77.15	3x6	D	SUMP	0.0	3.70	39.0	0.0	19.50	39.0	
12a	OS1a,PR-1b	15.63	3x3	D	SUMP	0.0	1.30	39.0	0.0	6.10	39.0	
13	OS2b, PR-2	12.51	3x3	C	SUMP	0.0	1.10	16.0	0.0	5.30	16.0	
14	OS2c, PR-3	24.55	3x3	C	SUMP	0.0	1.40	16.0	0.0	5.50	16.0	
15	OS2d, PR-4	16.96	3x3	C	SUMP	0.0	1.50	16.0	0.0	6.60	16.0	
16	OS2e, PR-5	20.09	3x3	C	SUMP	0.0	1.60	16.0	0.0	7.20	16.0	
17	PR-6	13.87	3x3	C	SUMP	0.0	1.10	16.0	0.0	5.00	16.0	
18	PR-7	27.76	3x3	C	SUMP	0.0	2.30	16.0	0.0	10.60	16.0	
21a	PR-10a	4.73	3x3	C	SUMP	0.0	3.30	16.0	0.0	7.80	16.0	



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lots 1 - 10 Driveway Culverts

Invert Elev Dn (ft)	=	6870.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	6871.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	6876.97
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	7.80
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	7.80
Qpipe (cfs)	=	7.80
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	4.82
Veloc Up (ft/s)	=	5.72
HGL Dn (ft)	=	6871.29
HGL Up (ft)	=	6873.00
Hw Elev (ft)	=	6873.67
Hw/D (ft)	=	1.16
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lots 11 & 12 Driveway Culvert

Invert Elev Dn (ft)	=	7030.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	7031.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	7038.25
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	5.30
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	5.30
Qpipe (cfs)	=	5.30
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	3.52
Veloc Up (ft/s)	=	4.88
HGL Dn (ft)	=	7031.19
HGL Up (ft)	=	7032.81
Hw Elev (ft)	=	7033.23
Hw/D (ft)	=	0.87
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lot 13 Driveway Culvert

Invert Elev Dn (ft)	=	7000.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	7001.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	7008.25
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	9.20
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	4.60
Qpipe (cfs)	=	4.60
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	3.13
Veloc Up (ft/s)	=	4.63
HGL Dn (ft)	=	7001.16
HGL Up (ft)	=	7002.74
Hw Elev (ft)	=	7003.11
Hw/D (ft)	=	0.79
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lots 14 - 15 Driveway Culverts

Invert Elev Dn (ft)	=	6950.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	6951.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	6957.77
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	6.70
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	6.70
Qpipe (cfs)	=	6.70
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	4.26
Veloc Up (ft/s)	=	5.35
HGL Dn (ft)	=	6951.25
HGL Up (ft)	=	6952.92
Hw Elev (ft)	=	6953.47
Hw/D (ft)	=	1.03
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lot 16 Driveway Culvert

Invert Elev Dn (ft)	=	6870.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	6871.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	6876.97
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	7.20
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	7.20
Qpipe (cfs)	=	7.20
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	4.52
Veloc Up (ft/s)	=	5.52
HGL Dn (ft)	=	6871.27
HGL Up (ft)	=	6872.96
Hw Elev (ft)	=	6873.56
Hw/D (ft)	=	1.09
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lots 17 & 18 Driveway Culverts

Invert Elev Dn (ft)	=	6870.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	6871.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	6876.97
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	7.90
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	7.90
Qpipe (cfs)	=	7.90
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	4.87
Veloc Up (ft/s)	=	5.75
HGL Dn (ft)	=	6871.29
HGL Up (ft)	=	6873.01
Hw Elev (ft)	=	6873.69
Hw/D (ft)	=	1.18
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lot 19 Driveway Culvert

Invert Elev Dn (ft)	=	6870.00
Pipe Length (ft)	=	40.00
Slope (%)	=	4.80
Invert Elev Up (ft)	=	6871.92
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	6876.97
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	9.70
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	9.70
Qpipe (cfs)	=	9.70
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	5.79
Veloc Up (ft/s)	=	6.40
HGL Dn (ft)	=	6871.35
HGL Up (ft)	=	6873.12
Hw Elev (ft)	=	6874.09
Hw/D (ft)	=	1.45
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

Lot 20 Driveway Culvert

Invert Elev Dn (ft)	=	6870.00
Pipe Length (ft)	=	40.00
Slope (%)	=	2.70
Invert Elev Up (ft)	=	6871.08
Rise (in)	=	18.0
Shape	=	Circular
Span (in)	=	18.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Circular Concrete
Culvert Entrance	=	Square edge w/headwall (C)
Coeff. K,M,c,Y,k	=	0.0098, 2, 0.0398, 0.67, 0.5

Embankment

Top Elevation (ft)	=	6876.97
Top Width (ft)	=	24.00
Crest Width (ft)	=	30.00

Calculations

Qmin (cfs)	=	0.00
Qmax (cfs)	=	6.10
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	6.10
Qpipe (cfs)	=	6.10
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	3.94
Veloc Up (ft/s)	=	5.15
HGL Dn (ft)	=	6871.23
HGL Up (ft)	=	6872.03
Hw Elev (ft)	=	6872.54
Hw/D (ft)	=	0.97
Flow Regime	=	Inlet Control



Culvert Report

Existing Creek Crossing Culvert

Invert Elev Dn (ft)	=	6805.30
Pipe Length (ft)	=	40.00
Slope (%)	=	1.50
Invert Elev Up (ft)	=	6805.90
Rise (in)	=	24.0
Shape	=	Elliptical
Span (in)	=	36.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	Horizontal Ellipse Concrete
Culvert Entrance	=	Groove end projecting (H)
Coeff. K,M,c,Y,k	=	0.0045, 2, 0.0317, 0.69, 0.2

Embankment

Top Elevation (ft)	=	6817.00
Top Width (ft)	=	32.00
Crest Width (ft)	=	100.00

Calculations

Qmin (cfs)	=	127.00
Qmax (cfs)	=	127.00
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	127.00
Qpipe (cfs)	=	83.74
Qovertop (cfs)	=	43.26
Veloc Dn (ft/s)	=	17.77
Veloc Up (ft/s)	=	17.77
HGL Dn (ft)	=	6807.30
HGL Up (ft)	=	6809.21
Hw Elev (ft)	=	6817.28
Hw/D (ft)	=	5.69
Flow Regime	=	Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Thursday, Aug 31 2023

PROPOSED CREEK CROSSING CULVERT

Invert Elev Dn (ft)	=	6809.03
Pipe Length (ft)	=	50.00
Slope (%)	=	4.46
Invert Elev Up (ft)	=	6811.26
Rise (in)	=	48.0
Shape	=	Box
Span (in)	=	48.0
No. Barrels	=	1
n-Value	=	0.013
Culvert Type	=	90D Headwall, Chamfered or Beveled Inlet Edges
Culvert Entrance	=	90D headwall w/3/4-in chamfers
Coeff. K,M,c,Y,k	=	0.515, 0.667, 0.0375, 0.79, 0.2

Embankment

Top Elevation (ft)	=	6821.82
Top Width (ft)	=	32.00
Crest Width (ft)	=	100.00

Calculations

Qmin (cfs)	=	127.00
Qmax (cfs)	=	127.00
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	127.00
Qpipe (cfs)	=	127.00
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	8.88
Veloc Up (ft/s)	=	10.08
HGL Dn (ft)	=	6812.60
HGL Up (ft)	=	6814.41
Hw Elev (ft)	=	6816.69
Hw/D (ft)	=	1.36
Flow Regime	=	Inlet Control



DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.06 (July 2022)

Project: Hay Creek Valley

Basin ID: Beaver Creek



Example Zone Configuration (Retention Pond)

Watershed Information

Selected BMP Type =	EDB	
Watershed Area =	35.31	acres
Watershed Length =	3,000	ft
Watershed Length to Centroid =	1,500	ft
Watershed Slope =	0.048	ft/ft
Watershed Imperviousness =	15.34%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Target WQCV Drain Time =	40.0	hours
Location for 1-hr Rainfall Depths =	User Input	

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

			Optional User Overrides	
Water Quality Capture Volume (WQCV) =	0.279	acre-feet		acre-feet
Excess Urban Runoff Volume (EURV) =	0.527	acre-feet		acre-feet
2-yr Runoff Volume (P1 = 1.19 in.) =	0.629	acre-feet	1.19	inches
5-yr Runoff Volume (P1 = 1.5 in.) =	1.236	acre-feet	1.50	inches
10-yr Runoff Volume (P1 = 1.75 in.) =	1.825	acre-feet	1.75	inches
25-yr Runoff Volume (P1 = 2 in.) =	2.823	acre-feet	2.00	inches
50-yr Runoff Volume (P1 = 2.25 in.) =	3.522	acre-feet	2.25	inches
100-yr Runoff Volume (P1 = 2.52 in.) =	4.509	acre-feet	2.52	inches
500-yr Runoff Volume (P1 = 3.55 in.) =	7.573	acre-feet	3.55	inches
Approximate 2-yr Detention Volume =	0.352	acre-feet		
Approximate 5-yr Detention Volume =	0.532	acre-feet		
Approximate 10-yr Detention Volume =	0.935	acre-feet		
Approximate 25-yr Detention Volume =	1.213	acre-feet		
Approximate 50-yr Detention Volume =	1.280	acre-feet		
Approximate 100-yr Detention Volume =	1.607	acre-feet		

Define Zones and Basin Geometry

Zone 1 Volume (WQCV) =	0.279	acre-feet
Zone 2 Volume (EURV - Zone 1) =	0.247	acre-feet
Zone 3 Volume (100-year - Zones 1 & 2) =	1.081	acre-feet
Total Detention Basin Volume =	1.607	acre-feet
Initial Surcharge Volume (ISV) =	user	ft^3
Initial Surcharge Depth (ISD) =	user	ft
Total Available Detention Depth (H_{total}) =	user	ft
Depth of Trickle Channel (H_{TC}) =	user	ft
Slope of Trickle Channel (S_{TC}) =	user	ft/ft
Slopes of Main Basin Sides (S_{main}) =	user	H:V
Basin Length-to-Width Ratio ($R_{L/W}$) =	user	

Initial Surcharge Area (A_{ISV}) =	user	ft^2
Surcharge Volume Length (L_{ISV}) =	user	ft
Surcharge Volume Width (W_{ISV}) =	user	ft
Depth of Basin Floor (H_{FLOOR}) =	user	ft
Length of Basin Floor (L_{FLOOR}) =	user	ft
Width of Basin Floor (W_{FLOOR}) =	user	ft
Area of Basin Floor (A_{FLOOR}) =	user	ft^2
Volume of Basin Floor (V_{FLOOR}) =	user	ft^3
Depth of Main Basin (H_{MAIN}) =	user	ft
Length of Main Basin (L_{MAIN}) =	user	ft
Width of Main Basin (W_{MAIN}) =	user	ft
Area of Main Basin (A_{MAIN}) =	user	ft^2
Volume of Main Basin (V_{MAIN}) =	user	ft^3
Calculated Total Basin Volume (V_{total}) =	**user**	acre-feet

Depth Increment = ft

Stage - Storage Description	Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft^2)	Optional Override Area (ft^2)	Area (acre)	Volume (ft^3)	Volume (ac-ft)
Top of Micropool	--	0.00	--	--	--	60	0.001		
6865.5	--	0.90	--	--	--	60	0.001	54	0.001
6866	--	1.40	--	--	--	237	0.005	128	0.003
	--	1.90	--	--	--	1,096	0.025	461	0.011
6867	--	2.40	--	--	--	4,884	0.112	1,956	0.045
	--	2.90	--	--	--	12,158	0.279	6,217	0.143
6868	--	3.40	--	--	--	22,987	0.528	15,003	0.344
	--	3.90	--	--	--	33,167	0.761	29,042	0.667
6869	--	4.40	--	--	--	43,762	1.005	48,274	1.108
	--	4.90	--	--	--	49,829	1.144	71,672	1.645
6870	--	5.40	--	--	--	56,410	1.295	98,231	2.255
	--	5.90	--	--	--	59,443	1.365	127,195	2.920
6871	--	6.40	--	--	--	62,026	1.424	157,562	3.617
	--	6.90	--	--	--	64,682	1.485	189,239	4.344
6872	--	7.40	--	--	--	67,380	1.547	222,254	5.102
	--	7.90	--	--	--	70,161	1.611	256,640	5.892
6873	--	8.40	--	--	--	72,971	1.675	292,423	6.713
	--		--	--	--				
	--		--	--	--				
	--		--	--	--			

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.06 (July 2022)





DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)

Project: Hay Creek Valley

Basin ID: Beaver Creek



Example Zone Configuration (Retention Pond)

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	3.27	0.279	Orifice Plate
Zone 2 (EURV)	3.71	0.247	Circular Orifice
Zone 3 (100-year)	4.87	1.081	Weir&Pipe (Restrict)
Total (all zones)		1.607	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

			Calculated Parameters for Underdrain		
Underdrain Orifice Invert Depth =	N/A	ft (distance below the filtration media surface)	Underdrain Orifice Area =	N/A	ft²
Underdrain Orifice Diameter =	N/A	inches	Underdrain Orifice Centroid =	N/A	feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

			Calculated Parameters for Plate		
Centroid of Lowest Orifice =	0.00	ft (relative to basin bottom at Stage = 0 ft)	WQ Orifice Area per Row =	5.764E-03	ft²
Depth at top of Zone using Orifice Plate =	2.44	ft (relative to basin bottom at Stage = 0 ft)	Elliptical Half-Width =	N/A	feet
Orifice Plate: Orifice Vertical Spacing =	N/A	inches	Elliptical Slot Centroid =	N/A	feet
Orifice Plate: Orifice Area per Row =	0.83	sq. inches (diameter = 1 inch)	Elliptical Slot Area =	N/A	ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	1.50						
Orifice Area (sq. inches)	0.83	0.83						

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

	Zone 2 Circular	Not Selected		Calculated Parameters for Vertical Orifice	Zone 2 Circular	Not Selected	
Invert of Vertical Orifice =	3.00	N/A	ft (relative to basin bottom at Stage = 0 ft)	Vertical Orifice Area =	0.07	N/A	ft²
Depth at top of Zone using Vertical Orifice =	3.15	N/A	ft (relative to basin bottom at Stage = 0 ft)	Vertical Orifice Centroid =	0.15	N/A	feet
Vertical Orifice Diameter =	3.50	N/A	inches				

User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

	Zone 3 Weir	Not Selected		Calculated Parameters for Overflow Weir	Zone 3 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	3.86	N/A	ft (relative to basin bottom at Stage = 0 ft)	Height of Grate Upper Edge, H_t =	3.86	N/A	feet
Overflow Weir Front Edge Length =	6.00	N/A	feet	Overflow Weir Slope Length =	4.00	N/A	feet
Overflow Weir Grate Slope =	0.00	N/A	H:V	Grate Open Area / 100-yr Orifice Area =	11.25	N/A	
Horiz. Length of Weir Sides =	4.00	N/A	feet	Overflow Grate Open Area w/o Debris =	16.70	N/A	ft²
Overflow Grate Type =	Type C Grate	N/A		Overflow Grate Open Area w/ Debris =	8.35	N/A	ft²
Debris Clogging % =	50%	N/A	%				

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected		Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate	Zone 3 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	0.25	N/A	ft (distance below basin bottom at Stage = 0 ft)	Outlet Orifice Area =	1.49	N/A	ft²
Outlet Pipe Diameter =	18.00	N/A	inches	Outlet Orifice Centroid =	0.64	N/A	feet
Restrictor Plate Height Above Pipe Invert =	14.10		inches	Half-Central Angle of Restrictor Plate on Pipe =	2.17	N/A	radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

			Calculated Parameters for Spillway	
Spillway Invert Stage=	6.25	ft (relative to basin bottom at Stage = 0 ft)	Spillway Design Flow Depth=	0.34 feet
Spillway Crest Length =	50.00	feet	Stage at Top of Freeboard =	8.40 feet
Spillway End Slopes =	10.00	H:V	Basin Area at Top of Freeboard =	1.68 acres
Freeboard above Max Water Surface =	1.81	feet	Basin Volume at Top of Freeboard =	6.71 acre-ft

Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

Design Storm Return Period =	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.55
CUHP Runoff Volume (acre-ft) =	0.279	0.527	0.629	1.236	1.825	2.823	3.522	4.509	7.573
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.629	1.236	1.825	2.823	3.522	4.509	7.573
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	2.9	8.1	12.4	22.7	28.6	36.6	61.3
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.08	0.23	0.35	0.64	0.81	1.04	1.74
Peak Inflow Q (cfs) =	N/A	N/A	6.0	11.6	16.1	26.4	32.4	40.6	65.9
Peak Outflow Q (cfs) =	0.2	0.3	0.3	4.0	8.3	14.5	15.1	15.9	35.5
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.5	0.7	0.6	0.5	0.4	0.6
Structure Controlling Flow =	Vertical Orifice 1	Vertical Orifice 1	Vertical Orifice 1	Overflow Weir 1	Overflow Weir 1	Outlet Plate 1	Outlet Plate 1	Outlet Plate 1	Spillway
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	0.2	0.5	0.8	0.9	0.9	1.0
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	38	48	52	52	49	45	41	37	26
Time to Drain 99% of Inflow Volume (hours) =	**40**	50	54	57	56	54	53	52	48
Maximum Ponding Depth (ft) =	3.27	3.71	3.75	4.09	4.25	4.51	4.83	5.35	6.49
Area at Maximum Ponding Depth (acres) =	0.46	0.67	0.69	0.85	0.93	1.03	1.12	1.28	1.43
Maximum Volume Stored (acre-ft) =	0.280	0.530	0.558	0.820	0.954	1.210	1.555	2.178	3.731

WE ARE OVER DETAINING TO REDUCE THE TOTAL DISCHARGE FROM THE SITE TO BELOW PRE DEVELOPMENT VALUES. BECAUSE WE ARE OVER DETAINING, THE PLATE ON THE OUTLET FROM THE POND IS SET TO AN ELEVATION THAT ALSO AFFECTS THESE MORE FREQUENT STORM EVENTS.

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)







S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename:

Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
Time Interval	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.05
	0:15:00	0.00	0.00	0.08	0.13	0.17	0.11	0.14	0.14	0.26
	0:20:00	0.00	0.00	0.33	0.77	1.13	0.34	0.41	0.56	1.48
	0:25:00	0.00	0.00	1.99	4.56	7.40	1.93	2.42	3.20	10.28
	0:30:00	0.00	0.00	4.49	9.28	13.31	12.49	15.88	18.87	34.66
	0:35:00	0.00	0.00	5.71	11.25	15.59	20.67	25.74	31.52	53.05
	0:40:00	0.00	0.00	6.02	11.61	16.09	24.78	30.51	37.45	61.68
	0:45:00	0.00	0.00	5.87	11.27	15.81	26.16	32.13	40.11	65.41
	0:50:00	0.00	0.00	5.50	10.59	14.88	26.38	32.36	40.61	65.89
	0:55:00	0.00	0.00	5.12	9.87	14.01	25.12	30.88	39.36	64.10
	1:00:00	0.00	0.00	4.82	9.27	13.31	23.79	29.38	38.20	62.42
	1:05:00	0.00	0.00	4.54	8.68	12.62	22.54	27.96	37.15	60.85
	1:10:00	0.00	0.00	4.21	8.12	11.95	20.98	26.12	34.77	57.37
	1:15:00	0.00	0.00	3.88	7.58	11.43	19.30	24.14	31.97	53.41
	1:20:00	0.00	0.00	3.60	7.11	10.83	17.84	22.36	29.40	49.38
	1:25:00	0.00	0.00	3.35	6.67	10.13	16.53	20.72	27.05	45.51
	1:30:00	0.00	0.00	3.12	6.24	9.41	15.26	19.15	24.86	41.86
	1:35:00	0.00	0.00	2.89	5.81	8.70	14.05	17.63	22.85	38.46
	1:40:00	0.00	0.00	2.66	5.33	8.00	12.88	16.17	20.91	35.19
	1:45:00	0.00	0.00	2.44	4.84	7.31	11.73	14.74	19.02	32.02
	1:50:00	0.00	0.00	2.21	4.34	6.64	10.60	13.33	17.18	28.94
	1:55:00	0.00	0.00	1.99	3.88	6.00	9.50	11.97	15.40	26.02
	2:00:00	0.00	0.00	1.80	3.53	5.50	8.49	10.73	13.79	23.48
	2:05:00	0.00	0.00	1.66	3.27	5.08	7.72	9.77	12.53	21.41
	2:10:00	0.00	0.00	1.54	3.02	4.69	7.08	8.96	11.47	19.60
	2:15:00	0.00	0.00	1.42	2.79	4.32	6.52	8.24	10.52	17.97
	2:20:00	0.00	0.00	1.31	2.57	3.97	6.00	7.58	9.66	16.47
	2:25:00	0.00	0.00	1.21	2.36	3.63	5.53	6.98	8.87	15.09
	2:30:00	0.00	0.00	1.10	2.16	3.31	5.07	6.40	8.12	13.79
	2:35:00	0.00	0.00	1.00	1.96	3.00	4.64	5.85	7.43	12.58
	2:40:00	0.00	0.00	0.91	1.77	2.70	4.22	5.32	6.77	11.44
	2:45:00	0.00	0.00	0.82	1.58	2.42	3.81	4.80	6.13	10.33
	2:50:00	0.00	0.00	0.72	1.40	2.15	3.41	4.29	5.49	9.24
	2:55:00	0.00	0.00	0.63	1.22	1.88	3.01	3.79	4.85	8.16
	3:00:00	0.00	0.00	0.54	1.04	1.62	2.61	3.29	4.22	7.08
	3:05:00	0.00	0.00	0.45	0.87	1.36	2.21	2.79	3.58	6.01
	3:10:00	0.00	0.00	0.36	0.69	1.10	1.82	2.30	2.95	4.94
	3:15:00	0.00	0.00	0.28	0.52	0.84	1.43	1.80	2.33	3.88
	3:20:00	0.00	0.00	0.19	0.36	0.60	1.04	1.32	1.71	2.84
	3:25:00	0.00	0.00	0.13	0.25	0.44	0.67	0.86	1.13	1.96
	3:30:00	0.00	0.00	0.09	0.19	0.35	0.45	0.60	0.77	1.40
	3:35:00	0.00	0.00	0.07	0.15	0.29	0.31	0.43	0.54	1.03
	3:40:00	0.00	0.00	0.06	0.12	0.23	0.23	0.31	0.38	0.75
	3:45:00	0.00	0.00	0.05	0.10	0.19	0.16	0.23	0.26	0.53
	3:50:00	0.00	0.00	0.04	0.08	0.15	0.12	0.17	0.18	0.37
	3:55:00	0.00	0.00	0.03	0.06	0.12	0.09	0.13	0.11	0.25
	4:00:00	0.00	0.00	0.03	0.05	0.09	0.07	0.09	0.07	0.17
	4:05:00	0.00	0.00	0.02	0.04	0.07	0.05	0.07	0.06	0.13
	4:10:00	0.00	0.00	0.02	0.03	0.05	0.04	0.05	0.05	0.10
	4:15:00	0.00	0.00	0.01	0.02	0.04	0.03	0.04	0.04	0.08
	4:20:00	0.00	0.00	0.01	0.01	0.03	0.02	0.03	0.03	0.06
	4:25:00	0.00	0.00	0.01	0.01	0.02	0.02	0.02	0.02	0.05
	4:30:00	0.00	0.00	0.01	0.01	0.01	0.01	0.02	0.02	0.03
	4:35:00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.02
	4:40:00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Figure 13-12b. Emergency Spillway Profile at Embankment



Figure 13-12c. Emergency Spillway Protection

Q=22.4 CFS
LENGTH=50 Feet
UNIT FLOW RATE: 0.45 CFS/FT

=> TYPE VL RIP RAP





Figure 13-12d. Riprap Types for Emergency Spillway Protection

Weir Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Friday, Nov 17 2023

Stilling Basin Outfall

Trapezoidal Weir

Crest	= Sharp
Bottom Length (ft)	= 125.00
Total Depth (ft)	= 1.50
Side Slope (z:1)	= 4.00

Calculations

Weir Coeff. Cw	= 3.10
Compute by:	Known Q
Known Q (cfs)	= 55.50

Highlighted

Depth (ft)	= 0.28
Q (cfs)	= 55.50
Area (sqft)	= 35.31
Velocity (ft/s)	= 1.57
Top Width (ft)	= 127.24

FOREBAY CALCULATION SHEET

Design Point	Imperviousness Decimal	Total Water Quality Control Volume (Cu. Ft.)	Pond Name	Pond Drainage Area (Acres)	Pond Drainage Area Less Pond Footprint (Acres)	Forebay Location	Drainage area tributary to Forebay	Proportion of Total Drainage Area	Trib. WQCV Volume (Cu. Ft.)	Forebay Volume 3% of WQCV (Cu. Ft.)	Q100 to Forebay (cfs)	Forebay Outlet Sizing 2% of Q100 (cfs)	Forebay Slot Sizing (inches)	Forebay Depth (ft)
21b	0.1719	12153.24		35.31	32.90		32.49	0.99	12211.42	366	24.7	0.5	3.33	1.5

	WQCV		Pond Footprint	
EDB Pond	0.279	Acre-Ft	2.41	Acres
Percent of WQCV for Forebay	3%	Between 5 and 20 impervious acres		
Impervious Percentage	15.34%			
	Impervious Acres	5.4	Acres	
ISV	36	CU. FT.		

FOREBAY SLOT: WEIR SIZING EQUATION:

The Francis Formula - Imperial Units

Flow through a rectangular weir can be expressed in imperial units with the Francis formula

$q = 3.33\ (b - 0.2\ h)\ h^{3/2}$ *(1b)*

where

q = flow rate (ft^3/s)

h = head on the weir (ft)

b = width of the weir (ft)

MINIMUM SLOT WIDTH = 3"

Table EDB-4. EDB component criteria

	On-Site EDBs for Watersheds up to 1 Impervious Acre[1]	EDBs with Watersheds between 1 and 2 Impervious Acres[1]	EDBs with Watersheds up to 5 Impervious Acres	EDBs with Watersheds over 5 Impervious Acres	EDBs with Watersheds over 20 Impervious Acres
Forebay Release and Configuration	EDBs should not be used for watersheds with less than 1 impervious acre.	Release 2% of the undetained 100-year peak discharge by way of a wall/notch configuration	Release 2% of the undetained 100-year peak discharge by way of a wall/notch configuration	Release 2% of the undetained 100-year peak discharge by way of a wall/notch configuration	Release 2% of the undetained 100-year peak discharge by way of a wall/notch or berm/pipe[2] configuration
Minimum Forebay Volume		1% of the WQCV	2% of the WQCV	3% of the WQCV	3% of the WQCV
Maximum Forebay Depth		12 inches	18 inches	18 inches	30 inches
Trickle Channel Capacity		≥ the maximum possible forebay outlet capacity	≥ the maximum possible forebay outlet capacity	≥ the maximum possible forebay outlet capacity	≥ the maximum possible forebay outlet capacity
Micropool		Area ≥ 10 ft^2	Area ≥ 10 ft^2	Area ≥ 10 ft^2	Area ≥ 10 ft^2
Initial Surcharge Volume		Depth ≥ 4 inches	Depth ≥ 4 inches	Depth ≥ 4 in. Volume ≥ 0.3% WQCV	Depth ≥ 4 in. Volume ≥ 0.3% WQCV

[1] EDBs are not recommended for sites with less than 2 impervious acres. Consider a sand filter or rain garden.

[2] Round up to the first standard pipe size (minimum 8 inches).

Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Thursday, Aug 24 2023

Trickle Channel

Rectangular

Bottom Width (ft)	= 3.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 2.00
Slope (%)	= 0.50
N-Value	= 0.013

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.00

Highlighted

Depth (ft)	= 0.43
Q (cfs)	= 5.000
Area (sqft)	= 1.29
Velocity (ft/s)	= 3.88
Wetted Perim (ft)	= 3.86
Crit Depth, Yc (ft)	= 0.45
Top Width (ft)	= 3.00
EGL (ft)	= 0.66



Stormwater Detention and Infiltration Design Data Sheet

SDI-Design Data v2.00, Released January 2020

Stormwater Facility Name: **Pond 1**

Facility Location & Jurisdiction: **Hay Creek Valley, El Paso County**

User Input: Watershed Characteristics

Extended Detention Basin (EDB)	EDB	
Watershed Area =	29.19	acres
Watershed Length =	3,000	ft
Watershed Length to Centroid =	1,500	ft
Watershed Slope =	0.048	ft/ft
Watershed Imperviousness =	17.1%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Target WQCV Drain Time =	40.0	hours

Location for 1-hr Rainfall Depths (use dropdown):

User Input

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

Once CUHP has been run and the Stage-Area-Discharge information has been provided, click 'Process Data' to interpolate the Stage-Area-Volume-Discharge data and generate summary results in the table below. Once this is complete, click 'Print to PDF'.

After completing and printing this worksheet to a pdf, go to:
https://maperture.digitaldataservices.com/gvh/?viewer=cswdif
Create a new stormwater facility, and attach the PDF of this worksheet to that record.

User Defined Stage [ft]	User Defined Area [ft^2]	User Defined Stage [ft]	User Defined Discharge [cfs]
0.00	60	0.00	0.00
0.40	60	0.25	0.01
0.90	237	0.50	0.02
1.40	1,096	0.75	0.02
1.90	4,884	1.00	0.03
2.40	12,158	1.25	0.05
2.90	22,987	1.50	0.05
3.40	33,167	1.75	0.06
3.90	43,762	2.00	0.07
4.40	49,829	2.25	0.07
4.90	56,410	2.50	0.08
5.40	59,443	2.75	0.18
5.90	62,026	3.00	0.28
6.40	64,682	3.25	0.34
6.90	67,380	3.50	2.08
7.40	70,161	3.75	8.29
7.90	72,971	4.00	14.49
		4.25	14.92
		4.50	15.35
		4.75	15.76
		5.00	16.16
		5.25	16.55
		5.50	16.93
		5.75	17.30
		6.00	37.17
		6.25	75.30
		6.50	127.50
		6.75	192.72
		7.00	270.62
		7.25	361.10
		7.50	464.21
		7.75	580.07
		7.90	655.78

Routed Hydrograph Results

Design Storm Return Period =	WQCV	2 Year	5 Year	10 Year	50 Year	100 Year	
One-Hour Rainfall Depth =	N/A	1.19	1.50	1.75	2.25	2.52	in
CUHP Runoff Volume =	0.251	0.564	1.075	1.568	2.970	3.784	acre-ft
Inflow Hydrograph Volume =	N/A	0.564	1.075	1.568	2.970	3.784	acre-ft
Time to Drain 97% of Inflow Volume =	38.2	51.8	**52.6**	50.0	42.5	38.3	hours
Time to Drain 99% of Inflow Volume =	39.8	54.8	57.5	56.5	53.7	**52.3**	hours
Maximum Ponding Depth =	2.72	3.17	3.53	3.67	4.04	4.42	ft
Maximum Ponded Area =	0.43	0.65	0.82	0.89	1.04	**1.15**	acres
Maximum Volume Stored =	0.254	0.499	0.762	0.883	1.237	1.658	acre-ft

Stormwater Detention and Infiltration Design Data Sheet





Design Procedure Form: Runoff Reduction

UD-BMP (Version 3.07, March 2018) **Sheet 1 of 1**

Designer: WCG
Company: Matrix Design Group
Date: November 30, 2023
Project: Hay Creek Valley
Location: El Paso County, CO

SITE INFORMATION (User Input in Blue Cells)

WQCV Rainfall Depth = 0.60 inches
Depth of Average Runoff Producing Storm, d_6 = 0.43 inches (for Watersheds Outside of the Denver Region, Figure 3-1 in USDCM Vol. 3)

Area Type	SPA	UIA:RPA	UIA:RPA									
Area ID		PR-12	OS4									
Downstream Design Point ID	Pond 1	Pond 1	Pond 1									
Downstream BMP Type	EDB	EDB	EDB									
DCIA (ft^2)	--	--	--									
UIA (ft^2)	--	26,037	20,642									
RPA (ft^2)	--	15,194	9,723									
SPA (ft^2)	672,115	--	--									
HSG A (%)	0%	0%	0%									
HSG B (%)	100%	100%	100%									
HSG C/D (%)	0%	0%	0%									
Average Slope of RPA (ft/ft)	--	0.100	0.100									
UIA:RPA Interface Width (ft)	--	750.00	550.00									

CALCULATED RUNOFF RESULTS

Area ID		PR-12	OS4									
UIA:RPA Area (ft^2)	--	41,231	30,365									
L / W Ratio	--	0.07	0.10									
UIA / Area	--	0.6315	0.6798									
Runoff (in)	0.00	0.00	0.01									
Runoff (ft^3)	0	0	35									
Runoff Reduction (ft^3)	33606	1085	825									

CALCULATED WQCV RESULTS

Area ID		PR-12	OS4									
WQCV (ft^3)	0	1085	860									
WQCV Reduction (ft^3)	0	1085	825									
WQCV Reduction (%)	0%	100%	96%									
Untreated WQCV (ft^3)	0	0	35									

CALCULATED DESIGN POINT RESULTS (sums results from all columns with the same Downstream Design Point ID)

Downstream Design Point ID	Pond 1											
DCIA (ft^2)	0											
UIA (ft^2)	46,679											
RPA (ft^2)	24,917											
SPA (ft^2)	672,115											
Total Area (ft^2)	743,711											
Total Impervious Area (ft^2)	46,679											
WQCV (ft^3)	1,945											
WQCV Reduction (ft^3)	1,910											
WQCV Reduction (%)	98%											
Untreated WQCV (ft^3)	35											

CALCULATED SITE RESULTS (sums results from all columns in worksheet)

Total Area (ft^2)	743,711
Total Impervious Area (ft^2)	46,679
WQCV (ft^3)	1,945
WQCV Reduction (ft^3)	1,910
WQCV Reduction (%)	98%
Untreated WQCV (ft^3)	35

Model Name: **Hay_Creek_Forest_Manor**

These models reflect full development of the areas included in the Hay Creek development with full spectrum detention provided to maintain historic flows. Areas tributary to Pond 1 have been modeled to drain to "Sink 2" while the pond itself has been modeled using the outflow hydrographs from the MHFD-Detention Spreadsheet.



Project: HAY_CREEK_FOREST_MANOR - UP Simulation Run: PR-Q5

Start of Run: 01Jan2018, 00:00 Basin Model: PR - HAY CREEK_FM
End of Run: 02Jan2018, 00:00 Meteorologic Model: 5 YEAR EVENT
Compute Time: 21Nov2023, 12:38:39 Control Specifications: 1 DAY

Volume Units: (•) IN ( ) AC-FT

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
DP-11	0.1205	3.7	01Jan2018, 12:50	0.14
DP-12	0.0244	1.3	01Jan2018, 12:40	0.21
DP-13	0.0195	1.1	01Jan2018, 12:30	0.20
DP-14	0.0380	2.2	01Jan2018, 12:30	0.21
DP-15	0.0268	1.5	01Jan2018, 12:40	0.21
DP-16	0.0313	1.6	01Jan2018, 12:40	0.21
DP-17	0.0313	1.7	01Jan2018, 12:40	0.21
DP-18	0.0338	2.1	01Jan2018, 12:30	0.21
DP-19	0.0286	1.2	01Jan2018, 12:40	0.17
DP-21	0.0412	4.7	01Jan2018, 12:45	0.54
Junction-1	0.1449	5.0	01Jan2018, 12:45	0.16
Junction-5	0.0195	1.1	01Jan2018, 12:30	0.20
Junction-6	0.0843	4.6	01Jan2018, 12:40	0.21
Junction-7	0.2301	10.9	01Jan2018, 12:50	0.21
OS1a	0.0146	0.8	01Jan2018, 12:40	0.21
OS1b	0.0925	2.6	01Jan2018, 12:50	0.13
OS2a	0.0078	0.4	01Jan2018, 12:25	0.14
OS2b	0.0074	0.4	01Jan2018, 12:30	0.18
OS2c	0.0095	0.8	01Jan2018, 12:25	0.20
OS2d	0.0043	0.3	01Jan2018, 12:35	0.20
OS2e	0.0049	0.3	01Jan2018, 12:30	0.20
OS3a	0.0076	0.1	01Jan2018, 12:40	0.06
OS3b	0.0051	0.1	01Jan2018, 12:30	0.06
POND 1	0.0840	2.7	01Jan2018, 02:05	0.18
PR-10a	0.0074	3.3	01Jan2018, 13:00	2.00
PR-10b	0.0006	0.8	01Jan2018, 12:15	2.66
PR-12	0.0256	0.6	01Jan2018, 12:55	0.11
PR-1a	0.0202	0.9	01Jan2018, 12:50	0.21
PR-1b	0.0098	0.5	01Jan2018, 12:40	0.21
PR-1c	0.0832	3.4	01Jan2018, 13:00	0.21
PR-2	0.0121	0.7	01Jan2018, 12:35	0.21
PR-3	0.0285	1.6	01Jan2018, 12:40	0.21
PR-4	0.0225	1.2	01Jan2018, 12:40	0.21
PR-5	0.0264	1.3	01Jan2018, 12:45	0.21
PR-6	0.0313	1.7	01Jan2018, 12:40	0.21
PR-7	0.0338	2.1	01Jan2018, 12:30	0.21
PR-9	0.0210	1.1	01Jan2018, 12:40	0.21
Reach-1	0.0000	0.0	01Jan2018, 00:00	
Reach-2	0.0195	1.1	01Jan2018, 12:45	0.20
Reach-3	0.2301	10.9	01Jan2018, 12:50	0.21
Reach-4	0.0843	4.6	01Jan2018, 12:50	0.21
Sink-1	0.3734	12.9	01Jan2018, 12:50	0.19
Sink-2	0.0418	4.9	01Jan2018, 12:40	0.57
SITE DISCHARGE	0.3427	12.3	01Jan2018, 12:50	0.20



Project: HAY_CREEK_FOREST_MANOR - UP Simulation Run: PR-Q100

Start of Run: 01Jan2018, 00:00 Basin Model: PR - HAY CREEK_FM
End of Run: 02Jan2018, 00:00 Meteorologic Model: 100 YEAR EVENT
Compute Time: 21Nov2023, 12:35:58 Control Specifications: 1 DAY

Volume Units: (•) IN ( ) AC-FT

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
DP-11	0.1205	19.5	01Jan2018, 12:55	0.74
DP-12	0.0244	6.1	01Jan2018, 12:45	0.92
DP-13	0.0195	5.3	01Jan2018, 12:35	0.89
DP-14	0.0380	9.2	01Jan2018, 12:40	0.89
DP-15	0.0268	6.7	01Jan2018, 12:45	0.91
DP-16	0.0313	7.2	01Jan2018, 12:45	0.91
DP-17	0.0313	7.9	01Jan2018, 12:45	0.92
DP-18	0.0338	9.7	01Jan2018, 12:35	0.92
DP-19	0.0286	6.1	01Jan2018, 12:45	0.82
DP-21	0.0412	16.0	01Jan2018, 12:45	1.58
Junction-1	0.1449	25.2	01Jan2018, 12:55	0.77
Junction-5	0.0195	5.3	01Jan2018, 12:35	0.89
Junction-6	0.0843	21.0	01Jan2018, 12:40	0.90
Junction-7	0.2301	49.7	01Jan2018, 12:50	0.90
OS1a	0.0146	3.6	01Jan2018, 12:45	0.92
OS1b	0.0925	14.2	01Jan2018, 13:00	0.70
OS2a	0.0078	1.8	01Jan2018, 12:30	0.71
OS2b	0.0074	2.0	01Jan2018, 12:35	0.85
OS2c	0.0095	2.7	01Jan2018, 12:25	0.80
OS2d	0.0043	1.1	01Jan2018, 12:40	0.86
OS2e	0.0049	1.3	01Jan2018, 12:35	0.84
OS3a	0.0076	0.9	01Jan2018, 12:50	0.53
OS3b	0.0051	0.8	01Jan2018, 12:35	0.53
POND 1	0.0840	15.2	01Jan2018, 01:40	0.79
PR-10a	0.0074	7.8	01Jan2018, 13:00	4.55
PR-10b	0.0006	1.7	01Jan2018, 12:15	5.49
PR-12	0.0256	3.4	01Jan2018, 13:05	0.65
PR-1a	0.0202	4.3	01Jan2018, 12:55	0.92
PR-1b	0.0098	2.5	01Jan2018, 12:45	0.92
PR-1c	0.0832	15.7	01Jan2018, 13:05	0.91
PR-2	0.0121	3.3	01Jan2018, 12:40	0.92
PR-3	0.0285	7.3	01Jan2018, 12:45	0.92
PR-4	0.0225	5.6	01Jan2018, 12:45	0.92
PR-5	0.0264	6.1	01Jan2018, 12:50	0.92
PR-6	0.0313	7.9	01Jan2018, 12:45	0.92
PR-7	0.0338	9.7	01Jan2018, 12:35	0.92
PR-9	0.0210	5.1	01Jan2018, 12:45	0.92
Reach-1	0.0000	0.0	01Jan2018, 00:00	
Reach-2	0.0195	5.2	01Jan2018, 12:45	0.88
Reach-3	0.2301	49.4	01Jan2018, 12:55	0.90
Reach-4	0.0843	20.9	01Jan2018, 12:50	0.89
Sink-1	0.3734	59.4	01Jan2018, 12:55	0.85
Sink-2	0.0418	16.5	01Jan2018, 12:40	1.63
SITE DISCHARGE	0.3427	55.5	01Jan2018, 12:55	0.87



Model Name: **Hay_Creek_Forest_Manor**
These models reflect the existing conditions on the Hay Creek development.



Project: HAY_CREEK_FOREST_MANOR - UP Simulation Run: EX-Q5

Start of Run: 01Jan2018, 00:00
End of Run: 02Jan2018, 00:00
Compute Time: 28Mar2023, 08:56:35

Basin Model: EX - HAY CREEK_FM
Meteorologic Model: 5 YEAR EVENT
Control Specifications: 1 DAY

Volume Units: (•) IN ( ) AC-FT

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
EX-1	0.0876	1.6	01Jan2018, 13:00	0.10
EX-2	0.0754	2.0	01Jan2018, 12:50	0.13
EX-3	0.0963	2.3	01Jan2018, 12:40	0.10
EX-5	0.0669	1.5	01Jan2018, 12:40	0.09
EX-OS1a	0.0146	0.8	01Jan2018, 12:40	0.23
EX-OS1b	0.0925	2.6	01Jan2018, 12:50	0.14
EX-OS2a	0.0248	1.5	01Jan2018, 12:25	0.18
EX-OS2b	0.0043	0.3	01Jan2018, 12:35	0.23
EX-OS2c	0.0049	0.3	01Jan2018, 12:30	0.22
EX-OS3	0.0127	0.2	01Jan2018, 12:30	0.07
Junction-2	0.1927	5.4	01Jan2018, 12:45	0.14
Junction-3	0.1055	2.9	01Jan2018, 12:35	0.11
Junction-4	0.0796	1.8	01Jan2018, 12:40	0.09
Junction-5	0.2949	7.5	01Jan2018, 12:50	0.13
Junction-6	0.4004	9.8	01Jan2018, 12:50	0.12
Reach-1	0.0146	0.8	01Jan2018, 13:00	0.23
Reach-2	0.2949	7.5	01Jan2018, 13:00	0.13
Reach-3	0.4004	9.8	01Jan2018, 12:55	0.12
Sink-1	0.4800	11.2	01Jan2018, 12:50	0.12
SITE DISCH...	0.4800	11.2	01Jan2018, 12:50	0.12

Project: HAY_CREEK_FOREST_MANOR - UP Simulation Run: EX-Q100

Start of Run: 01Jan2018, 00:00
End of Run: 02Jan2018, 00:00
Compute Time: 28Mar2023, 08:57:29

Basin Model: EX - HAY CREEK_FM
Meteorologic Model: 100 YEAR EVENT
Control Specifications: 1 DAY

Volume Units: (•) IN ( ) AC-FT

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
EX-1	0.0876	9.9	01Jan2018, 13:15	0.62
EX-2	0.0754	11.2	01Jan2018, 13:00	0.69
EX-3	0.0963	14.7	01Jan2018, 12:45	0.62
EX-5	0.0669	10.0	01Jan2018, 12:45	0.61
EX-OS1a	0.0146	4.1	01Jan2018, 12:45	1.01
EX-OS1b	0.0925	15.7	01Jan2018, 13:00	0.76
EX-OS2a	0.0248	8.0	01Jan2018, 12:30	0.89
EX-OS2b	0.0043	1.4	01Jan2018, 12:35	1.01
EX-OS2c	0.0049	1.6	01Jan2018, 12:30	0.99
EX-OS3	0.0127	2.0	01Jan2018, 12:40	0.57
Junction-2	0.1927	30.9	01Jan2018, 12:55	0.75
Junction-3	0.1055	17.4	01Jan2018, 12:45	0.65
Junction-4	0.0796	11.9	01Jan2018, 12:45	0.60
Junction-5	0.2949	43.9	01Jan2018, 13:00	0.72
Junction-6	0.4004	59.2	01Jan2018, 12:55	0.70
Reach-1	0.0146	4.1	01Jan2018, 12:55	1.00
Reach-2	0.2949	43.8	01Jan2018, 13:00	0.72
Reach-3	0.4004	59.1	01Jan2018, 13:00	0.70
Sink-1	0.4800	69.9	01Jan2018, 12:55	0.68
SITE DISCH...	0.4800	69.9	01Jan2018, 12:55	0.68

StormCAD LAYOUT




Storm 1 - Q5 FREE OUTFALL
Label: FES - 1
Type: Manhole
ID: 120
Label: FES - 2
Type: Outfall
ID: 126
Label: PIPE - 2
Type: Conduit
ID: 104
EGL
HGL
Elevation (ft)
6,868.80
6,868.60
6,868.40
6,868.20
6,868.00
6,867.80
6,867.60
6,867.40
6,867.20
6,867.00
6,866.80
6,866.60
6,866.40
6,866.20
6,866.00
6,865.80
6,865.60
6,865.40
6,865.20
6,865.00
6,864.80
6,864.60
6,864.40
6,864.20
6,864.00
6,863.80
6,863.60
6,863.40
6,863.20
6,863.00
6,862.80
6,862.60
6,862.40
6,862.20
6,862.00
6,861.80
0.0
5.0
10.0
15.0
20.0
25.0
30.0
35.0
40.0
45.0
50.0
55.0
60.0
65.0
70.0
75.0
80.0
85.0
90.0
95.0
100.0
105.0
110.0
115.0
120.0
125.0
130.0
ID\Label
104 \ PIPE - 2
Link Length (ft)
129.9
Rise (in)\Material
18.0 \ Concrete
Flow (cfs)
1.20
Slope (ft/ft)
0.028
ID\Label
126 \ FES - 2
120 \ FES - 1
Ground (ft)
6865.18
6868.78
Invert (ft)
6862.18
6865.78
Station (ft)
0.0
129.9

Storm 2 - Q5 FREE OUTFALL



ID\Label		177 \ PIPE - 7
Link Length (ft)		87.0
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		1.10
Slope (ft/ft)		0.012
ID\Label	176 \ INLET - 3	179 \ O-11
Ground (ft)	6911.24	6909.09
Invert (ft)	6908.64	6907.59
Station (ft)	0.0	87.0

Storm 3 - Q5 FREE OUTFALL



ID\Label		102 \ PIPE - 8
Link Length (ft)		89.0
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		1.60
Slope (ft/ft)		0.012
ID\Label	124 \ FES - 5	84 \ INLET - 4
Ground (ft)	6926.52	6928.68
Invert (ft)	6925.02	6926.07
Station (ft)	0.0	89.0

Storm 4 - Q5 FREE OUTFALL



ID\Label		147 \ PIPE - 9
Link Length (ft)		89.8
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		1.50
Slope (ft/ft)		0.018
ID\Label	148 \ O-7	145 \ INLET - 5
Ground (ft)	6945.56	6948.13
Invert (ft)	6943.87	6945.48
Station (ft)	0.0	89.8


Storm 5 - Q5 FREE OUTFALL
Label: INLET - 6
Type: Manhole
ID: 81
Label: PIPE - 11
Type: Conduit
ID: 101
Label: O-12
Type: Outfall
ID: 180
EGL
HGL
Elevation (ft)
6,980.60
6,980.40
6,980.20
6,980.00
6,979.80
6,979.60
6,979.40
6,979.20
6,979.00
6,978.80
6,978.60
6,978.40
6,978.20
6,978.00
6,977.80
6,977.60
6,977.40
6,977.20
6,977.00
6,976.80
6,976.60
6,976.40
6,976.20
6,976.00
6,975.80
6,975.60
6,975.40
0.0 2.0 4.0 6.0 8.0 10.0 12.0 14.0 16.0 18.0 20.0 22.0 24.0 26.0 28.0 30.0 32.0 34.0 36.0 38.0 40.0 42.0 44.0 46.0 48.0 50.0 52.0 54.0 56.0 58.0 60.0 62.0 64.0 66.0 68.0 70.0 72.0 74.0 76.0 78.0 80.0 82.0 84.0 86.0 88.0 90.0 92.0 94.0 96.0 98.0
ID\Label
101 \ PIPE - 11
Link Length (ft)
94.7
Rise (in)\Material
18.0 \ CMP
Flow (cfs)
1.40
Slope (ft/ft)
0.012
ID\Label
180 \ O-12
81 \ INLET - 6
Ground (ft)
6976.96
6980.47
Invert (ft)
6975.36
6976.45
Station (ft)
0.0
94.7

Storm 6 - Q5 FREE OUTFALL



ID\Label		144 \ PIPE - 17
Link Length (ft)		89.4
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		1.10
Slope (ft/ft)		0.017
ID\Label	122 \ FES - 9	117 \ INLET - 7
Ground (ft)	7035.07	7040.08
Invert (ft)	7033.57	7035.09
Station (ft)	0.0	89.4

Storm 7 - Q5 FREE OUTFALL



ID\Label		111 \ PIPE - 16	110 \ PIPE - 15
Link Length (ft)		105.8	78.8
Rise (in)\Material		36.0 \ CMP	36.0 \ CMP
Flow (cfs)		5.00	3.70
Slope (ft/ft)		0.007	0.007
ID\Label	98 \ FES - 10	97 \ INLET - 8	96 \ INLET - 9
Ground (ft)	7054.20	7056.91	7059.70
Invert (ft)	7051.20	7051.99	7052.88
Station (ft)	0.0	105.8	184.6



ID\Label	103 \ PIPE - 4	109 \ PIPE - 5
Link Length (ft)	81.2	50.9
Rise (in)\Material	30.0 \ CMP	30.0 \ CMP
Flow (cfs)	5.30	2.30
Slope (ft/ft)	0.041	0.043

ID\Label	125 \ O-4	86 \ INLET - 2	87 \ INLET - 1
Ground (ft)	6870.50	6883.45	6881.33
Invert (ft)	6868.00	6871.30	6874.51
Station (ft)	0.0	81.2	132.2


Pond-Outfall - Q5 FREE OUTFALL
Label: MH-5
Type: Manhole
ID: 121
EGL
HGL
Elevation (ft)
6,870.20
6,870.00
6,869.80
6,869.60
6,869.40
6,869.20
6,869.00
6,868.80
6,868.60
6,868.40
6,868.20
6,868.00
6,867.80
6,867.60
6,867.40
6,867.20
6,867.00
6,866.80
6,866.60
6,866.40
6,866.20
6,866.00
6,865.80
6,865.60
6,865.40
6,865.20
6,865.00
6,864.80
6,864.60
6,864.40
6,864.20
6,864.00
6,863.80
6,863.60
6,863.40
6,863.20
6,863.00
6,862.80
6,862.60
6,862.40
6,862.20
6,862.00
6,861.80
Label: FES - 3
Type: Outfall
ID: 88
Label: PIPE - 3
Type: Conduit
ID: 99
0.0
2.0
4.0
6.0
8.0
10.0
12.0
14.0
16.0
18.0
20.0
22.0
24.0
26.0
28.0
30.0
32.0
34.0
36.0
38.0
40.0
42.0
44.0
46.0
48.0
50.0
52.0
54.0
56.0
58.0
60.0
62.0
64.0
66.0
68.0
70.0
72.0
ID\Label
99 \ PIPE - 3
Link Length (ft)
71.3
Rise (in)\Material
18.0 \ Concrete
Flow (cfs)
2.70
Slope (ft/ft)
0.033
ID\Label
88 \ FES - 3
121 \ MH-5
Ground (ft)
6863.50
6870.00
Invert (ft)
6862.00
6864.35
Station (ft)
0.0
71.3

	Label	Velocity (ft/s)	Start Node	Invert (Start) (ft)	Hydraulic Grade Line (In) (ft)	Invert (Stop) (ft)	Hydraulic Grade Line (Out) (ft)	Stop Node	Length (User Defined) (ft)	Slope (Calculated) (ft/ft)	Manning's n	Flow (cfs)	Capacity (Design) (cfs)	Depth (Normal) / Rise (%)	Diameter (in)	Elevation Ground (Start) (ft)	Elevation Ground (Stop) (ft)
99: PIPE - 3	PIPE - 3	4.92	MH-5	6,864.35	6,864.97	6,862.00	6,862.52	FES - 3	71.3	0.033	0.024	2.70	10.33	34.9	18.0	6,870.00	6,863.50
101: PIPE - 11	PIPE - 11	2.80	INLET - 6	6,976.45	6,976.94	6,975.36	6,975.80	O-12	94.7	0.012	0.024	1.40	6.10	32.6	18.0	6,980.47	6,976.96
102: PIPE - 8	PIPE - 8	2.94	INLET - 4	6,926.07	6,926.59	6,925.02	6,925.50	FES - 5	89.0	0.012	0.024	1.60	6.18	34.7	18.0	6,928.68	6,926.52
103: PIPE - 4	PIPE - 4	6.13	INLET - 2	6,871.30	6,872.06	6,868.00	6,868.58	O-4	81.2	0.041	0.024	5.30	44.78	23.2	30.0	6,883.45	6,870.50
104: PIPE - 2	PIPE - 2	3.67	FES - 1	6,865.78	6,866.19	6,862.18	6,862.54	FES - 2	129.9	0.028	0.024	1.20	9.47	24.0	18.0	6,868.78	6,865.18
109: PIPE - 5	PIPE - 5	4.90	INLET - 1	6,874.51	6,875.01	6,872.30	6,872.68	INLET - 2	50.9	0.043	0.024	2.30	46.27	15.2	30.0	6,881.33	6,883.45
110: PIPE - 15	PIPE - 15	2.97	INLET - 9	7,052.88	7,053.58	7,052.29	7,053.02	INLET - 8	78.8	0.007	0.024	3.70	31.27	23.2	36.0	7,059.70	7,056.91
111: PIPE - 16	PIPE - 16	3.24	INLET - 8	7,051.99	7,052.80	7,051.20	7,051.90	FES - 10	105.8	0.007	0.024	5.00	31.21	27.1	36.0	7,056.91	7,054.20
144: PIPE - 17	PIPE - 17	3.01	INLET - 7	7,035.09	7,035.48	7,033.57	7,033.96	FES - 9	89.4	0.017	0.024	1.10	7.42	26.0	18.0	7,040.08	7,035.07
147: PIPE - 9	PIPE - 9	3.35	INLET - 5	6,945.48	6,945.94	6,943.87	6,944.32	O-7	89.8	0.018	0.024	1.50	7.62	30.1	18.0	6,948.13	6,945.56
177: PIPE - 7	PIPE - 7	2.67	INLET - 3	6,908.64	6,909.07	6,907.59	6,907.98	O-11	87.0	0.012	0.024	1.10	6.25	28.4	18.0	6,911.24	6,909.09

Figure 1- Q5 – Free Outfall CONDUIT SUMMARY

	ID	Label	Flow (Known) (cfs)	Elevation (Ground) (ft)	Elevation (Rim) (ft)	Depth (Out) (ft)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Headloss Method	Headloss Coefficient (Standard)	Flow (Total Out) (cfs)
81: INLET - 6	81	INLET - 6	1.40	6,980.47	6,980.47	0.49	6,976.94	6,976.94	Standard	0.050	1.40
84: INLET - 4	84	INLET - 4	1.60	6,928.68	6,928.68	0.52	6,926.60	6,926.59	Standard	0.050	1.60
86: INLET - 2	86	INLET - 2	5.30	6,883.45	6,883.45	0.76	6,872.24	6,872.06	Standard	0.640	5.30
87: INLET - 1	87	INLET - 1	2.30	6,881.33	6,881.33	0.50	6,875.01	6,875.01	Standard	0.050	2.30
96: INLET - 9	96	INLET - 9	3.70	7,059.70	7,059.70	0.70	7,053.58	7,053.58	Standard	0.050	3.70
97: INLET - 8	97	INLET - 8	5.00	7,056.91	7,056.91	0.81	7,053.02	7,052.80	Standard	1.320	5.00
117: INLET - 7	117	INLET - 7	1.10	7,040.08	7,040.08	0.39	7,035.49	7,035.48	Standard	0.050	1.10
120: FES - 1	120	FES - 1	1.20	6,868.78	6,868.78	0.41	6,866.20	6,866.19	Standard	0.050	1.20
121: MH-5	121	MH-5	2.70	6,870.00	6,870.00	0.62	6,864.98	6,864.97	Standard	0.050	2.70
145: INLET - 5	145	INLET - 5	1.50	6,948.13	6,948.13	0.46	6,945.95	6,945.94	Standard	0.050	1.50
176: INLET - 3	176	INLET - 3	1.10	6,911.24	6,911.24	0.43	6,909.07	6,909.07	Standard	0.050	1.10

Figure 2- Q5 – Free Outfall NODE SUMMARY

	ID	Label	Elevation (Ground) (ft)	Set Rim to Ground Elevation?	Elevation (Invert) (ft)	Boundary Condition Type	Hydraulic Grade (ft)	Flow (Total Out) (cfs)
88: FES - 3	88	FES - 3	6,863.50	☑	6,862.00	Free Outfall	6,862.52	2.70
98: FES - 10	98	FES - 10	7,054.20	☑	7,051.20	Free Outfall	7,051.90	5.00
122: FES - 9	122	FES - 9	7,035.07	☑	7,033.57	Free Outfall	7,033.96	1.10
124: FES - 5	124	FES - 5	6,926.52	☑	6,925.02	Free Outfall	6,925.50	1.60
125: O-4	125	O-4	6,870.50	☑	6,868.00	Free Outfall	6,868.58	5.30
126: FES - 2	126	FES - 2	6,865.18	☑	6,862.18	Free Outfall	6,862.54	1.20
148: O-7	148	O-7	6,945.56	☑	6,944.06	Free Outfall	6,944.51	1.50
179: O-11	179	O-11	6,909.09	☑	6,907.59	Free Outfall	6,907.98	1.10
180: O-12	180	O-12	6,976.96	☑	6,975.46	Free Outfall	6,975.90	1.40

Figure 3- Q5 – Free Outfall OUTFALL SUMMARY

Storm 1 - Q100 FREE OUTFALL



ID\Label		104 \ PIPE - 2
Link Length (ft)		129.9
Rise (in)\Material		18.0 \ Concrete
Flow (cfs)		6.10
Slope (ft/ft)		0.028
ID\Label	126 \ FES - 2	120 \ FES - 1
Ground (ft)	6865.18	6868.78
Invert (ft)	6862.18	6865.78
Station (ft)	0.0	129.9

Storm 2 - Q100 FREE OUTFALL



ID\Label		177 \ PIPE - 7	
Link Length (ft)		87.0	
Rise (in)\Material		18.0 \ CMP	
Flow (cfs)		5.00	
Slope (ft/ft)		0.012	
ID\Label	176 \ INLET - 3		179 \ O-11
Ground (ft)	6911.24		6909.09
Invert (ft)	6908.64		6907.59
Station (ft)	0.0		87.0

Storm 3 - Q100 FREE OUTFALL



ID\Label	102 \ PIPE - 8	
Link Length (ft)	89.0	
Rise (in)\Material	18.0 \ CMP	
Flow (cfs)	7.20	
Slope (ft/ft)	0.012	
ID\Label	124 \ FES - 5	84 \ INLET - 4
Ground (ft)	6926.52	6928.68
Invert (ft)	6925.02	6926.07
Station (ft)	0.0	89.0

Storm 4 - Q100 FREE OUTFALL



ID\Label		147 \ PIPE - 9
Link Length (ft)		89.8
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		6.60
Slope (ft/ft)		0.018
ID\Label	148 \ O-7	145 \ INLET - 5
Ground (ft)	6945.56	6948.13
Invert (ft)	6943.87	6945.48
Station (ft)	0.0	89.8


Storm 5 - Q100 FREE OUTFALL
Label: INLET - 6
Type: Manhole
ID: 81
Label: PIPE - 11
Type: Conduit
ID: 101
Label: O-12
Type: Outfall
ID: 180
EGL
HGL
Elevation (ft)
6,980.60
6,980.40
6,980.20
6,980.00
6,979.80
6,979.60
6,979.40
6,979.20
6,979.00
6,978.80
6,978.60
6,978.40
6,978.20
6,978.00
6,977.80
6,977.60
6,977.40
6,977.20
6,977.00
6,976.80
6,976.60
6,976.40
6,976.20
6,976.00
6,975.80
6,975.60
6,975.40
0.0 2.0 4.0 6.0 8.0 10.0 12.0 14.0 16.0 18.0 20.0 22.0 24.0 26.0 28.0 30.0 32.0 34.0 36.0 38.0 40.0 42.0 44.0 46.0 48.0 50.0 52.0 54.0 56.0 58.0 60.0 62.0 64.0 66.0 68.0 70.0 72.0 74.0 76.0 78.0 80.0 82.0 84.0 86.0 88.0 90.0 92.0 94.0 96.0 98.0
ID\Label
101 \ PIPE - 11
Link Length (ft)
94.7
Rise (in)\Material
18.0 \ CMP
Flow (cfs)
5.50
Slope (ft/ft)
0.012
ID\Label
180 \ O-12
81 \ INLET - 6
Ground (ft)
6976.96
6980.47
Invert (ft)
6975.36
6976.45
Station (ft)
0.0
94.7

Storm 6 - Q100 FREE OUTFALL



ID\Label		144 \ PIPE - 17
Link Length (ft)		89.4
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		5.30
Slope (ft/ft)		0.017
ID\Label	122 \ FES - 9	117 \ INLET - 7
Ground (ft)	7035.07	7040.08
Invert (ft)	7033.57	7035.09
Station (ft)	0.0	89.4

Storm 7 - Q100 FREE OUTFALL



ID\Label	111 \ PIPE - 16	110 \ PIPE - 15	
Link Length (ft)	105.8	78.8	
Rise (in)\Material	36.0 \ CMP	36.0 \ CMP	
Flow (cfs)	25.20	19.50	
Slope (ft/ft)	0.007	0.007	
ID\Label	98 \ FES - 10	97 \ INLET - 8	96 \ INLET - 9
Ground (ft)	7054.20	7056.91	7059.70
Invert (ft)	7051.20	7051.99	7052.88
Station (ft)	0.0	105.8	184.6



ID\Label	103 \ PIPE - 4	109 \ PIPE - 5
Link Length (ft)	81.2	50.9
Rise (in)\Material	30.0 \ CMP	30.0 \ CMP
Flow (cfs)	17.90	10.60
Slope (ft/ft)	0.041	0.043

ID\Label	125 \ O-4	86 \ INLET - 2	87 \ INLET - 1
Ground (ft)	6870.50	6883.45	6881.33
Invert (ft)	6868.00	6871.30	6874.51
Station (ft)	0.0	81.2	132.2

Pond-Outfall - Q100 FREE OUTFALL



ID\Label		99 \ PIPE - 3
Link Length (ft)		71.3
Rise (in)\Material		18.0 \ Concrete
Flow (cfs)		15.20
Slope (ft/ft)		0.033
ID\Label	88 \ FES - 3	121 \ MH-5
Ground (ft)	6863.50	6870.00
Invert (ft)	6862.00	6864.35
Station (ft)	0.0	71.3

	Label	Velocity (ft/s)	Start Node	Invert (Start) (ft)	Hydraulic Grade Line (In) (ft)	Invert (Stop) (ft)	Hydraulic Grade Line (Out) (ft)	Stop Node	Length (User Defined) (ft)	Slope (Calculated) (ft/ft)	Manning's n	Flow (cfs)	Capacity (Design) (cfs)	Depth (Normal) / Rise (%)	Diameter (in)	Elevation Ground (Start) (ft)	Elevation Ground (Stop) (ft)
99: PIPE - 3	PIPE - 3	8.60	MH-5	6,864.35	6,868.55	6,862.00	6,863.41	FES - 3	71.3	0.033	0.024	15.20	10.33	(N/A)	18.0	6,870.00	6,863.50
101: PIPE - 11	PIPE - 11	3.91	INLET - 6	6,976.45	6,977.56	6,975.36	6,976.26	O-12	94.7	0.012	0.024	5.50	6.10	74.2	18.0	6,980.47	6,976.96
102: PIPE - 8	PIPE - 8	4.07	INLET - 4	6,926.07	6,927.63	6,925.02	6,926.06	FES - 5	89.0	0.012	0.024	7.20	6.18	(N/A)	18.0	6,928.68	6,926.52
103: PIPE - 4	PIPE - 4	8.61	INLET - 2	6,871.30	6,872.73	6,868.00	6,869.10	O-4	81.2	0.041	0.024	17.90	44.78	44.0	30.0	6,883.45	6,870.50
104: PIPE - 2	PIPE - 2	5.69	FES - 1	6,865.78	6,866.73	6,862.18	6,863.06	FES - 2	129.9	0.028	0.024	6.10	9.47	58.4	18.0	6,868.78	6,865.18
109: PIPE - 5	PIPE - 5	7.65	INLET - 1	6,874.51	6,875.60	6,872.30	6,873.11	INLET - 2	50.9	0.043	0.024	10.60	46.27	32.6	30.0	6,881.33	6,883.45
110: PIPE - 15	PIPE - 15	4.66	INLET - 9	7,052.88	7,054.79	7,052.29	7,054.52	INLET - 8	78.8	0.007	0.024	19.50	31.27	57.2	36.0	7,059.70	7,056.91
111: PIPE - 16	PIPE - 16	4.91	INLET - 8	7,051.99	7,054.01	7,051.20	7,052.82	FES - 10	105.8	0.007	0.024	25.20	31.21	68.1	36.0	7,056.91	7,054.20
144: PIPE - 17	PIPE - 17	4.56	INLET - 7	7,035.09	7,036.03	7,033.57	7,034.46	FES - 9	89.4	0.017	0.024	5.30	7.42	62.5	18.0	7,040.08	7,035.07
147: PIPE - 9	PIPE - 9	4.85	INLET - 5	6,945.48	6,946.56	6,943.87	6,944.86	O-7	89.8	0.018	0.024	6.60	7.62	71.9	18.0	6,948.13	6,945.56
177: PIPE - 7	PIPE - 7	3.93	INLET - 3	6,908.64	6,909.65	6,907.59	6,908.45	O-11	87.0	0.012	0.024	5.00	6.25	67.6	18.0	6,911.24	6,909.09

Figure 4- Q100 – Free Outfall CONDUIT SUMMARY

	ID	Label	Flow (Known) (cfs)	Elevation (Ground) (ft)	Elevation (Rim) (ft)	Depth (Out) (ft)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Headloss Method	Headloss Coefficient (Standard)	Flow (Total Out) (cfs)
81: INLET - 6	81	INLET - 6	5.50	6,980.47	6,980.47	1.11	6,977.57	6,977.56	Standard	0.050	5.50
84: INLET - 4	84	INLET - 4	7.20	6,928.68	6,928.68	1.56	6,927.64	6,927.63	Standard	0.050	7.20
86: INLET - 2	86	INLET - 2	17.90	6,883.45	6,883.45	1.43	6,873.11	6,872.73	Standard	0.640	17.90
87: INLET - 1	87	INLET - 1	10.60	6,881.33	6,881.33	1.09	6,875.62	6,875.60	Standard	0.050	10.60
96: INLET - 9	96	INLET - 9	19.50	7,059.70	7,059.70	1.91	7,054.81	7,054.79	Standard	0.050	19.50
97: INLET - 8	97	INLET - 8	25.20	7,056.91	7,056.91	2.02	7,054.52	7,054.01	Standard	1.320	25.20
117: INLET - 7	117	INLET - 7	5.30	7,040.08	7,040.08	0.94	7,036.04	7,036.03	Standard	0.050	5.30
120: FES - 1	120	FES - 1	6.10	6,868.78	6,868.78	0.95	6,866.75	6,866.73	Standard	0.050	6.10
121: MH-5	121	MH-5	15.20	6,870.00	6,870.00	4.20	6,868.61	6,868.55	Standard	0.050	15.20
145: INLET - 5	145	INLET - 5	6.60	6,948.13	6,948.13	1.08	6,946.58	6,946.56	Standard	0.050	6.60
176: INLET - 3	176	INLET - 3	5.00	6,911.24	6,911.24	1.01	6,909.67	6,909.65	Standard	0.050	5.00

Figure 5- Q100 – Free Outfall NODE SUMMARY

	ID	Label	Elevation (Ground) (ft)	Set Rim to Ground Elevation?	Elevation (Invert) (ft)	Boundary Condition Type	Hydraulic Grade (ft)	Flow (Total Out) (cfs)
88: FES - 3	88	FES - 3	6,863.50	☑	6,862.00	Free Outfall	6,863.41	15.20
98: FES - 10	98	FES - 10	7,054.20	☑	7,051.20	Free Outfall	7,052.82	25.20
122: FES - 9	122	FES - 9	7,035.07	☑	7,033.57	Free Outfall	7,034.46	5.30
124: FES - 5	124	FES - 5	6,926.52	☑	6,925.02	Free Outfall	6,926.06	7.20
125: O-4	125	O-4	6,870.50	☑	6,868.00	Free Outfall	6,869.10	17.90
126: FES - 2	126	FES - 2	6,865.18	☑	6,862.18	Free Outfall	6,863.06	6.10
148: O-7	148	O-7	6,945.56	☑	6,944.06	Free Outfall	6,945.05	6.60
179: O-11	179	O-11	6,909.09	☑	6,907.59	Free Outfall	6,908.45	5.00
180: O-12	180	O-12	6,976.96	☑	6,975.46	Free Outfall	6,976.36	5.50

Figure 6- Q100 Free Outfall OUTFALL SUMMARY



ID\Label		104 \ PIPE - 2
Link Length (ft)		129.9
Rise (in)\Material		18.0 \ Concrete
Flow (cfs)		1.20
Slope (ft/ft)		0.028
ID\Label	126 \ FES - 2	120 \ FES - 1
Ground (ft)	6865.18	6868.78
Invert (ft)	6862.18	6865.78
Station (ft)	0.0	129.9

Storm 2 - Q5



ID\Label		177 \ PIPE - 7
Link Length (ft)		87.0
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		1.10
Slope (ft/ft)		0.012
ID\Label	176 \ INLET - 3	179 \ O-11
Ground (ft)	6911.24	6909.09
Invert (ft)	6908.64	6907.59
Station (ft)	0.0	87.0


Storm 3 - Q5
Label: INLET - 4
Type: Manhole
ID: 84
Label: FES - 5
Type: Outfall
ID: 124
Label: PIPE - 8
Type: Conduit
ID: 102
EGL
HGL
Elevation (ft)
6,928.70
6,928.60
6,928.50
6,928.40
6,928.30
6,928.20
6,928.10
6,928.00
6,927.90
6,927.80
6,927.70
6,927.60
6,927.50
6,927.40
6,927.30
6,927.20
6,927.10
6,927.00
6,926.90
6,926.80
6,926.70
6,926.60
6,926.50
6,926.40
6,926.30
6,926.20
6,926.10
6,926.00
6,925.90
6,925.80
6,925.70
6,925.60
6,925.50
6,925.40
6,925.30
6,925.20
6,925.10
6,925.00
0.0 2.0 4.0 6.0 8.0 10.0 12.0 14.0 16.0 18.0 20.0 22.0 24.0 26.0 28.0 30.0 32.0 34.0 36.0 38.0 40.0 42.0 44.0 46.0 48.0 50.0 52.0 54.0 56.0 58.0 60.0 62.0 64.0 66.0 68.0 70.0 72.0 74.0 76.0 78.0 80.0 82.0 84.0 86.0 88.0 90.0 92.0
ID\Label
Link Length (ft)
Rise (in)\Material
Flow (cfs)
Slope (ft/ft)
ID\Label
Ground (ft)
Invert (ft)
Station (ft)
102 \ PIPE - 8
89.0
18.0 \ CMP
1.60
0.012
124 \ FES - 5
84 \ INLET - 4
6926.52
6928.68
6925.02
6926.07
0.0
89.0


Storm 4 - Q5
Label: INLET - 5
Type: Manhole
ID: 145
Label: PIPE - 9
Type: Conduit
ID: 147
Label: O-7
Type: Outfall
ID: 148
EGL
HGL
Elevation (ft)
6,948.20
6,948.10
6,948.00
6,947.90
6,947.80
6,947.70
6,947.60
6,947.50
6,947.40
6,947.30
6,947.20
6,947.10
6,947.00
6,946.90
6,946.80
6,946.70
6,946.60
6,946.50
6,946.40
6,946.30
6,946.20
6,946.10
6,946.00
6,945.90
6,945.80
6,945.70
6,945.60
6,945.50
6,945.40
6,945.30
6,945.20
6,945.10
6,945.00
6,944.90
6,944.80
6,944.70
6,944.60
6,944.50
6,944.40
6,944.30
6,944.20
6,944.10
6,944.00
6,943.90
6,943.80
0.0 2.0 4.0 6.0 8.0 10.0 12.0 14.0 16.0 18.0 20.0 22.0 24.0 26.0 28.0 30.0 32.0 34.0 36.0 38.0 40.0 42.0 44.0 46.0 48.0 50.0 52.0 54.0 56.0 58.0 60.0 62.0 64.0 66.0 68.0 70.0 72.0 74.0 76.0 78.0 80.0 82.0 84.0 86.0 88.0 90.0 92.0
ID\Label
147 \ PIPE - 9
Link Length (ft)
89.8
Rise (in)\Material
18.0 \ CMP
Flow (cfs)
1.50
Slope (ft/ft)
0.018
ID\Label
148 \ O-7
145 \ INLET - 5
Ground (ft)
6945.56
6948.13
Invert (ft)
6943.87
6945.48
Station (ft)
0.0
89.8



ID\Label		101 \ PIPE - 11	
Link Length (ft)		94.7	
Rise (in)\Material		18.0 \ CMP	
Flow (cfs)		1.40	
Slope (ft/ft)		0.012	
ID\Label	180 \ O-12		81 \ INLET - 6
Ground (ft)	6976.96		6980.47
Invert (ft)	6975.36		6976.45
Station (ft)	0.0		94.7

Storm 6 - Q5



ID\Label		144 \ PIPE - 17
Link Length (ft)		89.4
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		1.10
Slope (ft/ft)		0.017
ID\Label	122 \ FES - 9	117 \ INLET - 7
Ground (ft)	7035.07	7040.08
Invert (ft)	7033.57	7035.09
Station (ft)	0.0	89.4

Storm 7 - Q5



ID\Label	111 \ PIPE - 16	110 \ PIPE - 15	
Link Length (ft)	105.8	78.8	
Rise (in)\Material	36.0 \ CMP	36.0 \ CMP	
Flow (cfs)	5.00	3.70	
Slope (ft/ft)	0.007	0.007	
ID\Label	98 \ FES - 10	97 \ INLET - 8	96 \ INLET - 9
Ground (ft)	7054.20	7056.91	7059.70
Invert (ft)	7051.20	7051.99	7052.88
Station (ft)	0.0	105.8	184.6



ID\Label		103 \ PIPE - 4	109 \ PIPE - 5
Link Length (ft)		81.2	50.9
Rise (in)\Material		30.0 \ CMP	30.0 \ CMP
Flow (cfs)		5.30	2.30
Slope (ft/ft)		0.041	0.043
ID\Label	125 \ O-4	86 \ INLET - 2	87 \ INLET - 1
Ground (ft)	6870.50	6883.45	6881.33
Invert (ft)	6868.00	6871.30	6874.51
Station (ft)	0.0	81.2	132.2



ID\Label	99 \ PIPE - 3	
Link Length (ft)	71.3	
Rise (in)\Material	18.0 \ Concrete	
Flow (cfs)	2.70	
Slope (ft/ft)	0.033	
ID\Label	88 \ FES - 3	121 \ MH-5
Ground (ft)	6863.50	6870.00
Invert (ft)	6862.00	6864.35
Station (ft)	0.0	71.3

	Label	Velocity (ft/s)	Start Node	Invert (Start) (ft)	Hydraulic Grade Line (In) (ft)	Invert (Stop) (ft)	Hydraulic Grade Line (Out) (ft)	Stop Node	Length (User Defined) (ft)	Slope (Calculated) (ft/ft)	Manning's n	Flow (cfs)	Capacity (Design) (cfs)	Depth (Normal) / Rise (%)	Diameter (in)	Elevation Ground (Start) (ft)	Elevation Ground (Stop) (ft)
99: PIPE - 3	PIPE - 3	4.92	MH-5	6,864.35	6,864.97	6,862.00	6,862.52	FES - 3	71.3	0.033	0.024	2.70	10.33	34.9	18.0	6,870.00	6,863.50
101: PIPE - 11	PIPE - 11	2.80	INLET - 6	6,976.45	6,976.94	6,975.36	6,975.80	O-12	94.7	0.012	0.024	1.40	6.10	32.6	18.0	6,980.47	6,976.96
102: PIPE - 8	PIPE - 8	2.94	INLET - 4	6,926.07	6,926.59	6,925.02	6,925.50	FES - 5	89.0	0.012	0.024	1.60	6.18	34.7	18.0	6,928.68	6,926.52
103: PIPE - 4	PIPE - 4	6.13	INLET - 2	6,871.30	6,872.06	6,868.00	6,868.85	O-4	81.2	0.041	0.024	5.30	44.78	23.2	30.0	6,883.45	6,870.50
104: PIPE - 2	PIPE - 2	3.67	FES - 1	6,865.78	6,866.19	6,862.18	6,862.54	FES - 2	129.9	0.028	0.024	1.20	9.47	24.0	18.0	6,868.78	6,865.18
109: PIPE - 5	PIPE - 5	4.90	INLET - 1	6,874.51	6,875.01	6,872.30	6,872.68	INLET - 2	50.9	0.043	0.024	2.30	46.27	15.2	30.0	6,881.33	6,883.45
110: PIPE - 15	PIPE - 15	2.97	INLET - 9	7,052.88	7,053.58	7,052.29	7,053.02	INLET - 8	78.8	0.007	0.024	3.70	31.27	23.2	36.0	7,059.70	7,056.91
111: PIPE - 16	PIPE - 16	3.24	INLET - 8	7,051.99	7,052.80	7,051.20	7,051.90	FES - 10	105.8	0.007	0.024	5.00	31.21	27.1	36.0	7,056.91	7,054.20
144: PIPE - 17	PIPE - 17	3.01	INLET - 7	7,035.09	7,035.48	7,033.57	7,033.96	FES - 9	89.4	0.017	0.024	1.10	7.42	26.0	18.0	7,040.08	7,035.07
147: PIPE - 9	PIPE - 9	3.35	INLET - 5	6,945.48	6,945.94	6,943.87	6,944.32	O-7	89.8	0.018	0.024	1.50	7.62	30.1	18.0	6,948.13	6,945.56
177: PIPE - 7	PIPE - 7	2.67	INLET - 3	6,908.64	6,909.07	6,907.59	6,907.98	O-11	87.0	0.012	0.024	1.10	6.25	28.4	18.0	6,911.24	6,909.09

Figure 7- Q5 CONDUIT SUMMARY

	ID	Label	Flow (Known) (cfs)	Elevation (Ground) (ft)	Elevation (Rim) (ft)	Depth (Out) (ft)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Headloss Method	Headloss Coefficient (Standard)	Flow (Total Out) (cfs)
81: INLET - 6	81	INLET - 6	1.40	6,980.47	6,980.47	0.49	6,976.94	6,976.94	Standard	0.050	1.40
84: INLET - 4	84	INLET - 4	1.60	6,928.68	6,928.68	0.52	6,926.60	6,926.59	Standard	0.050	1.60
86: INLET - 2	86	INLET - 2	5.30	6,883.45	6,883.45	0.76	6,872.24	6,872.06	Standard	0.640	5.30
87: INLET - 1	87	INLET - 1	2.30	6,881.33	6,881.33	0.50	6,875.01	6,875.01	Standard	0.050	2.30
96: INLET - 9	96	INLET - 9	3.70	7,059.70	7,059.70	0.70	7,053.58	7,053.58	Standard	0.050	3.70
97: INLET - 8	97	INLET - 8	5.00	7,056.91	7,056.91	0.81	7,053.02	7,052.80	Standard	1.320	5.00
117: INLET - 7	117	INLET - 7	1.10	7,040.08	7,040.08	0.39	7,035.49	7,035.48	Standard	0.050	1.10
120: FES - 1	120	FES - 1	1.20	6,868.78	6,868.78	0.41	6,866.20	6,866.19	Standard	0.050	1.20
121: MH-5	121	MH-5	2.70	6,870.00	6,870.00	0.62	6,864.98	6,864.97	Standard	0.050	2.70
145: INLET - 5	145	INLET - 5	1.50	6,948.13	6,948.13	0.46	6,945.95	6,945.94	Standard	0.050	1.50
176: INLET - 3	176	INLET - 3	1.10	6,911.24	6,911.24	0.43	6,909.07	6,909.07	Standard	0.050	1.10

Figure 8- Q5 NODE SUMMARY

	ID	Label	Elevation (Ground) (ft)	Set Rim to Ground Elevation?	Elevation (Invert) (ft)	Boundary Condition Type	Hydraulic Grade (ft)	Flow (Total Out) (cfs)
88: FES - 3	88	FES - 3	6,863.50	☑	6,862.00	Free Outfall	6,862.52	2.70
98: FES - 10	98	FES - 10	7,054.20	☑	7,051.20	Free Outfall	7,051.90	5.00
122: FES - 9	122	FES - 9	7,035.07	☑	7,033.57	Free Outfall	7,033.96	1.10
124: FES - 5	124	FES - 5	6,926.52	☑	6,925.02	Free Outfall	6,925.50	1.60
125: O-4	125	O-4	6,870.50	☑	6,868.00	User Defined Tailwater	6,868.85	5.30
126: FES - 2	126	FES - 2	6,865.18	☑	6,862.18	Free Outfall	6,862.54	1.20
148: O-7	148	O-7	6,945.56	☑	6,944.06	Free Outfall	6,944.51	1.50
179: O-11	179	O-11	6,909.09	☑	6,907.59	Free Outfall	6,907.98	1.10
180: O-12	180	O-12	6,976.96	☑	6,975.46	Free Outfall	6,975.90	1.40

Figure 9- Q5 OUTFALL SUMMARY

THE TAILWATER CONDITION HAS BEEN DEINED AS THE POND WSE DURING THE CORRESPONDING STORM EVENT FOR OUTFALLS THAT DISCHARGE INTO POND 1.



ID\Label		104 \ PIPE - 2
Link Length (ft)		129.9
Rise (in)\Material		18.0 \ Concrete
Flow (cfs)		6.10
Slope (ft/ft)		0.028
ID\Label	126 \ FES - 2	120 \ FES - 1
Ground (ft)	6865.18	6868.78
Invert (ft)	6862.18	6865.78
Station (ft)	0.0	129.9

Storm 2 - Q100



ID\Label		177 \ PIPE - 7	
Link Length (ft)		87.0	
Rise (in)\Material		18.0 \ CMP	
Flow (cfs)		5.00	
Slope (ft/ft)		0.012	
ID\Label	176 \ INLET - 3		179 \ O-11
Ground (ft)	6911.24		6909.09
Invert (ft)	6908.64		6907.59
Station (ft)	0.0		87.0

Storm 3 - Q100



ID\Label		102 \ PIPE - 8
Link Length (ft)		89.0
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		7.20
Slope (ft/ft)		0.012
ID\Label	124 \ FES - 5	84 \ INLET - 4
Ground (ft)	6926.52	6928.68
Invert (ft)	6925.02	6926.07
Station (ft)	0.0	89.0

Storm 4 - Q100



ID\Label		147 \ PIPE - 9
Link Length (ft)		89.8
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		6.60
Slope (ft/ft)		0.018
ID\Label	148 \ O-7	145 \ INLET - 5
Ground (ft)	6945.56	6948.13
Invert (ft)	6943.87	6945.48
Station (ft)	0.0	89.8



ID\Label		101 \ PIPE - 11
Link Length (ft)		94.7
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		5.50
Slope (ft/ft)		0.012
ID\Label	180 \ O-12	81 \ INLET - 6
Ground (ft)	6976.96	6980.47
Invert (ft)	6975.36	6976.45
Station (ft)	0.0	94.7

Storm 6 - Q100



ID\Label		144 \ PIPE - 17
Link Length (ft)		89.4
Rise (in)\Material		18.0 \ CMP
Flow (cfs)		5.30
Slope (ft/ft)		0.017
ID\Label	122 \ FES - 9	117 \ INLET - 7
Ground (ft)	7035.07	7040.08
Invert (ft)	7033.57	7035.09
Station (ft)	0.0	89.4



ID\Label	111 \ PIPE - 16	110 \ PIPE - 15	
Link Length (ft)	105.8	78.8	
Rise (in)\Material	36.0 \ CMP	36.0 \ CMP	
Flow (cfs)	25.20	19.50	
Slope (ft/ft)	0.007	0.007	
ID\Label	98 \ FES - 10	97 \ INLET - 8	96 \ INLET - 9
Ground (ft)	7054.20	7056.91	7059.70
Invert (ft)	7051.20	7051.99	7052.88
Station (ft)	0.0	105.8	184.6



ID\Label	111 \ PIPE - 16	110 \ PIPE - 15	
Link Length (ft)	105.8	78.8	
Rise (in)\Material	36.0 \ CMP	36.0 \ CMP	
Flow (cfs)	25.20	19.50	
Slope (ft/ft)	0.007	0.007	
ID\Label	98 \ FES - 10	97 \ INLET - 8	96 \ INLET - 9
Ground (ft)	7054.20	7056.91	7059.70
Invert (ft)	7051.20	7051.25	7052.88
Station (ft)	0.0	105.8	184.6

Pond Inlet - Q100



ID\Label		103 \ PIPE - 4	109 \ PIPE - 5
Link Length (ft)		81.2	50.9
Rise (in)\Material		30.0 \ CMP	30.0 \ CMP
Flow (cfs)		17.90	10.60
Slope (ft/ft)		0.041	0.043
ID\Label	125 \ O-4	86 \ INLET - 2	87 \ INLET - 1
Ground (ft)	6870.50	6883.45	6881.33
Invert (ft)	6868.00	6871.30	6874.51
Station (ft)	0.0	81.2	132.2

Pond-Outfall - Q100



ID\Label		99 \ PIPE - 3
Link Length (ft)		71.3
Rise (in)\Material		18.0 \ Concrete
Flow (cfs)		15.20
Slope (ft/ft)		0.033
ID\Label	88 \ FES - 3	121 \ MH-5
Ground (ft)	6863.50	6870.00
Invert (ft)	6862.00	6864.35
Station (ft)	0.0	71.3

	Label	Velocity (ft/s)	Start Node	Invert (Start) (ft)	Hydraulic Grade Line (In) (ft)	Invert (Stop) (ft)	Hydraulic Grade Line (Out) (ft)	Stop Node	Length (User Defined) (ft)	Slope (Calculated) (ft/ft)	Manning's n	Flow (cfs)	Capacity (Design) (cfs)	Depth (Normal) / Rise (%)	Diameter (in)	Elevation Ground (Start) (ft)	Elevation Ground (Stop) (ft)
99: PIPE - 3	PIPE - 3	8.60	MH-5	6,864.35	6,868.55	6,862.00	6,863.41	FES - 3	71.3	0.033	0.024	15.20	10.33	(N/A)	18.0	6,870.00	6,863.50
101: PIPE - 11	PIPE - 11	3.91	INLET - 6	6,976.45	6,977.56	6,975.36	6,976.26	O-12	94.7	0.012	0.024	5.50	6.10	74.2	18.0	6,980.47	6,976.96
102: PIPE - 8	PIPE - 8	4.07	INLET - 4	6,926.07	6,927.63	6,925.02	6,926.06	FES - 5	89.0	0.012	0.024	7.20	6.18	(N/A)	18.0	6,928.68	6,926.52
103: PIPE - 4	PIPE - 4	8.61	INLET - 2	6,871.30	6,872.73	6,868.00	6,869.95	O-4	81.2	0.041	0.024	17.90	44.78	44.0	30.0	6,883.45	6,870.50
104: PIPE - 2	PIPE - 2	5.69	FES - 1	6,865.78	6,866.73	6,862.18	6,863.06	FES - 2	129.9	0.028	0.024	6.10	9.47	58.4	18.0	6,868.78	6,865.18
109: PIPE - 5	PIPE - 5	7.65	INLET - 1	6,874.51	6,875.60	6,872.30	6,873.11	INLET - 2	50.9	0.043	0.024	10.60	46.27	32.6	30.0	6,881.33	6,883.45
110: PIPE - 15	PIPE - 15	4.66	INLET - 9	7,052.88	7,054.79	7,052.29	7,054.52	INLET - 8	78.8	0.007	0.024	19.50	31.27	57.2	36.0	7,059.70	7,056.91
111: PIPE - 16	PIPE - 16	4.91	INLET - 8	7,051.99	7,054.01	7,051.20	7,052.82	FES - 10	105.8	0.007	0.024	25.20	31.21	68.1	36.0	7,056.91	7,054.20
144: PIPE - 17	PIPE - 17	4.56	INLET - 7	7,035.09	7,036.03	7,033.57	7,034.46	FES - 9	89.4	0.017	0.024	5.30	7.42	62.5	18.0	7,040.08	7,035.07
147: PIPE - 9	PIPE - 9	4.85	INLET - 5	6,945.48	6,946.56	6,943.87	6,944.86	O-7	89.8	0.018	0.024	6.60	7.62	71.9	18.0	6,948.13	6,945.56
177: PIPE - 7	PIPE - 7	3.93	INLET - 3	6,908.64	6,909.65	6,907.59	6,908.45	O-11	87.0	0.012	0.024	5.00	6.25	67.6	18.0	6,911.24	6,909.09

Figure 10- Q100 CONDUIT SUMMARY

	ID	Label	Flow (Known) (cfs)	Elevation (Ground) (ft)	Elevation (Rim) (ft)	Depth (Out) (ft)	Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Headloss Method	Headloss Coefficient (Standard)	Flow (Total Out) (cfs)
81: INLET - 6	81	INLET - 6	5.50	6,980.47	6,980.47	1.11	6,977.57	6,977.56	Standard	0.050	5.50
84: INLET - 4	84	INLET - 4	7.20	6,928.68	6,928.68	1.56	6,927.64	6,927.63	Standard	0.050	7.20
86: INLET - 2	86	INLET - 2	17.90	6,883.45	6,883.45	1.43	6,873.11	6,872.73	Standard	0.640	17.90
87: INLET - 1	87	INLET - 1	10.60	6,881.33	6,881.33	1.09	6,875.62	6,875.60	Standard	0.050	10.60
96: INLET - 9	96	INLET - 9	19.50	7,059.70	7,059.70	1.91	7,054.81	7,054.79	Standard	0.050	19.50
97: INLET - 8	97	INLET - 8	25.20	7,056.91	7,056.91	2.02	7,054.52	7,054.01	Standard	1.320	25.20
117: INLET - 7	117	INLET - 7	5.30	7,040.08	7,040.08	0.94	7,036.04	7,036.03	Standard	0.050	5.30
120: FES - 1	120	FES - 1	6.10	6,868.78	6,868.78	0.95	6,866.75	6,866.73	Standard	0.050	6.10
121: MH-5	121	MH-5	15.20	6,870.00	6,870.00	4.20	6,868.61	6,868.55	Standard	0.050	15.20
145: INLET - 5	145	INLET - 5	6.60	6,948.13	6,948.13	1.08	6,946.58	6,946.56	Standard	0.050	6.60
176: INLET - 3	176	INLET - 3	5.00	6,911.24	6,911.24	1.01	6,909.67	6,909.65	Standard	0.050	5.00

Figure 11- Q100 NODE SUMMARY

	ID	Label	Elevation (Ground) (ft)	Set Rim to Ground Elevation?	Elevation (Invert) (ft)	Boundary Condition Type	Hydraulic Grade (ft)	Flow (Total Out) (cfs)
88: FES - 3	88	FES - 3	6,863.50	☑	6,862.00	Free Outfall	6,863.41	15.20
98: FES - 10	98	FES - 10	7,054.20	☑	7,051.20	Free Outfall	7,052.82	25.20
122: FES - 9	122	FES - 9	7,035.07	☑	7,033.57	Free Outfall	7,034.46	5.30
124: FES - 5	124	FES - 5	6,926.52	☑	6,925.02	Free Outfall	6,926.06	7.20
125: O-4	125	O-4	6,870.50	☑	6,868.00	User Defined Tailwater	6,869.95	17.90
126: FES - 2	126	FES - 2	6,865.18	☑	6,862.18	Free Outfall	6,863.06	6.10
148: O-7	148	O-7	6,945.56	☑	6,944.06	Free Outfall	6,945.05	6.60
179: O-11	179	O-11	6,909.09	☑	6,907.59	Free Outfall	6,908.45	5.00
180: O-12	180	O-12	6,976.96	☑	6,975.46	Free Outfall	6,976.36	5.50

Figure 12- Q100 OUTFALL SUMMARY

THE TAILWATER CONDITION HAS BEEN DEINED AS THE POND WSE DURING THE CORRESPONDING STORM EVENT FOR OUTFALLS THAT DISCHARGE INTO POND 1.

	DP12b		DP13		DP14		DP15		DP16		DP17		DP19	
Pipe Size (D)	36	Inches	18	Inches	18	Inches	18	Inches	18	Inches	18	Inches	18	Inches
Q	25.2	cfs	5.3	cfs	9.2	cfs	6.7	cfs	7.2	cfs	7.9	cfs	6.1	cfs
L	9	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet
W	9	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet
D	0	Feet	0	Feet	0	Feet	0	Feet	0	Feet	0	Feet	0	Feet
d_{50}	0.12	Feet	0.07	Feet	0.12	Feet	0.09	Feet	0.10	Feet	0.11	Feet	0.08	Feet
	1.44	Inches	0.86	Inches	1.49	Inches	1.08	Inches	1.17	Inches	1.28	Inches	0.99	Inches
Depth of Flow	2.82	Feet	1.41	Feet	1.4	Feet	1.4	Feet	1.41	Feet	1.4	Feet	1.4	Feet
Q/D^1.5	4.85		2.88		5.01		3.65		3.92		4.30		3.32	
Yt/D	0.940		0.940		0.940		0.94		0.940		0.940		0.94	
Rip Rap	Type L for 3 x Pipe Dia Downstream		Type L for 3 x Pipe Dia Downstream		Type L for 3 x Pipe Dia Downstream		Type L for 3 x Pipe Dia Downstream		Type L for 3 x Pipe Dia Downstream		Type L for 3 x Pipe Dia Downstream		Type L for 3 x Pipe Dia Downstream	
Length of Rock	9	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet
Width of Rock	9.0	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet	4.5	Feet



Use D_a instead of D whenever flow is supercritical in the barrel.
** Use Type L for a distance of 3D downstream.

Figure 9-38. Riprap erosion protection at circular conduit outlet (valid for Q/D2.5 ≤ 6.0)

CLASSIFICATION AND GRADATION OF ORDINARY RIP RAP

Rip Rap Designation by Weight	% Smaller Than Given Size (inches)	Intermediate Rock Dimension	d50* (inches)
Type VL	70 – 100	12	6**
	50 – 70	9	
	35 – 50	6	
	2 - 10	2	
Type L	70 – 100	15	9**
	50 – 70	12	
	35 – 50	9	
	2 - 10	3	
Type M	70 – 100	21	12
	50 – 70	18	
	35 – 50	12	
	2 - 10	4	
Type H	70 – 100	30	18
	50 – 70	24	
	35 – 50	18	
	2 - 10	6	
Type VH	70 – 100	42	24
	50 – 70	33	
	35 – 50	24	
	2 - 10	9	

* d50 = Mean particle size
** Bury types VL and L with native top soil and revegetate to protect from vandalism.

3.2.3 Rock Sizing for Riprap Apron and Low Tailwater Basin

Scour resulting from highly turbulent, rapidly decelerating flow is a common problem at conduit outlets. The following section summarizes the method for sizing riprap protection for both riprap aprons (Section 3.2.1) and low tailwater basins (Section 3.2.2).

Use Figure 9-38 to determine the required rock size for circular conduits and Figure 9-39 for rectangular conduits. Figure 9-38 is valid for $Q/D_c^{2.5}$ of 6.0 or less and Figure 9-39 is valid for $Q/WH^{1.5}$ of 8.0 or less. The parameters in these two figures are:

1. $Q/D^{1.5}$ or $Q/WH^{0.5}$ in which Q is the design discharge in cfs, D_c is the diameter of a circular conduit in feet, and W and H are the width and height of a rectangular conduit in feet.
2. Y_t/D_c or Y_t/H in which Y_t is the tailwater depth in feet, D_c is the diameter of a circular conduit in feet, and H is the height of a rectangular conduit in feet. In cases where Y_t is unknown or a hydraulic jump is suspected downstream of the outlet, use $Y_t/D_t = Y_t/H = 0.40$ when using Figures 9-38 and 9-39.
3. The riprap size requirements in Figures 9-38 and 9-39 are based on the non-dimensional parametric Equations 9-16 and 9-17 (Steven, Simons, and Watts 1971 and Smith 1975).

Circular culvert:

$$d_{50} = \frac{0.023Q}{Y_t^{1.2} D_c^{0.3}} \qquad \text{Equation 9-16}$$

Rectangular culvert:

$$d_{50} = \frac{0.014 H^{0.5} Q}{Y_t W} \qquad \text{Equation 9-17}$$

Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

DP-12b Outfall

Trapezoidal

Bottom Width (ft)	= 5.50
Side Slopes (z:1)	= 10.00, 10.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 1.00
Slope (%)	= 8.20
N-Value	= 0.040

Calculations

Compute by:	Known Q
Known Q (cfs)	= 25.20

Highlighted

Depth (ft)	= 0.49
Q (cfs)	= 25.20
Area (sqft)	= 5.10
Velocity (ft/s)	= 4.95
Wetted Perim (ft)	= 15.35
Crit Depth, Yc (ft)	= 0.50
Top Width (ft)	= 15.30
EGL (ft)	= 0.87



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

DP-13 Outfall

Trapezoidal

Bottom Width (ft)	= 5.50
Side Slopes (z:1)	= 10.00, 10.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 1.00
Slope (%)	= 9.50
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.30

Highlighted

Depth (ft)	= 0.19
Q (cfs)	= 5.300
Area (sqft)	= 1.41
Velocity (ft/s)	= 3.77
Wetted Perim (ft)	= 9.32
Crit Depth, Yc (ft)	= 0.27
Top Width (ft)	= 9.30
EGL (ft)	= 0.41



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-14 Outfall

Trapezoidal

Bottom Width (ft)	= 5.50
Side Slopes (z:1)	= 10.00, 10.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 1.00
Slope (%)	= 9.50
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.50

Highlighted

Depth (ft)	= 0.19
Q (cfs)	= 5.500
Area (sqft)	= 1.41
Velocity (ft/s)	= 3.91
Wetted Perim (ft)	= 9.32
Crit Depth, Yc (ft)	= 0.27
Top Width (ft)	= 9.30
EGL (ft)	= 0.43



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-15 Outfall

Trapezoidal

Bottom Width (ft)	= 5.50
Side Slopes (z:1)	= 10.00, 10.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 1.00
Slope (%)	= 8.50
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 6.60

Highlighted

Depth (ft)	= 0.22
Q (cfs)	= 6.600
Area (sqft)	= 1.69
Velocity (ft/s)	= 3.90
Wetted Perim (ft)	= 9.92
Crit Depth, Yc (ft)	= 0.30
Top Width (ft)	= 9.90
EGL (ft)	= 0.46



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Tuesday, Nov 21 2023

DP-16 Outfall

Trapezoidal

Bottom Width (ft)	= 5.50
Side Slopes (z:1)	= 10.00, 10.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 1.00
Slope (%)	= 8.70
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 7.20

Highlighted

Depth (ft)	= 0.23
Q (cfs)	= 7.200
Area (sqft)	= 1.79
Velocity (ft/s)	= 4.01
Wetted Perim (ft)	= 10.12
Crit Depth, Yc (ft)	= 0.31
Top Width (ft)	= 10.10
EGL (ft)	= 0.48



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-17 Outfall

Trapezoidal

Bottom Width (ft)	= 5.50
Side Slopes (z:1)	= 10.00, 10.00
Total Depth (ft)	= 0.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.80
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.00

Highlighted

Depth (ft)	= 0.22
Q (cfs)	= 5.000
Area (sqft)	= 1.69
Velocity (ft/s)	= 2.95
Wetted Perim (ft)	= 9.92
Crit Depth, Yc (ft)	= 0.26
Top Width (ft)	= 9.90
EGL (ft)	= 0.36



Hydraulic Analysis Report

Project Data

Project Title:

Designer:

Project Date: Wednesday, November 22, 2023

Project Units: U.S. Customary Units

Notes:

Channel Analysis: RIPRAP RUNDOWN @ 5.39%

Notes:

Input Parameters

Channel Type: Trapezoidal

Side Slope 1 (Z1): 10.0000 ft/ft

Side Slope 2 (Z2): 10.0000 ft/ft

Channel Width: 10.0000 ft

Longitudinal Slope: 0.0539 ft/ft

Manning's n: 0.0897

Flow: 49.7000 cfs

Result Parameters

Depth: 0.9226 ft

Area of Flow: 17.7388 ft^2

Wetted Perimeter: 28.5446 ft

Hydraulic Radius: 0.6214 ft

Average Velocity: 2.8018 ft/s

Top Width: 28.4526 ft

Froude Number: 0.6253

Critical Depth: 0.7172 ft

Critical Velocity: 4.0352 ft/s

Critical Slope: 0.1476 ft/ft

Critical Top Width: 24.34 ft

Calculated Max Shear Stress: 3.1031 lb/ft^2

Calculated Avg Shear Stress: 2.0901 lb/ft^2

Channel Lining Analysis: Channel Lining Design Analysis @5.39%

Notes:

Lining Input Parameters

Channel Lining Type: Riprap, Cobble, or Gravel

D50: 0.75 ft

Riprap Specific Weight: 165 lb/ft^3

Water Specific Weight: 62.4 lb/ft^3

Riprap Shape is Angular

Safety Factor: 1

Calculated Safety Factor: 1.11886

Lining Results

Angle of Repose: 41.7 degrees

Relative Flow Depth: 0.831266

Manning's n method: Bathurst

Manning's n: 0.0896539

Channel Bottom Shear Results

V*: 1.26542

Reynold's Number: 77984.2

Shield's Parameter: 0.0714523

shear stress on channel bottom: 3.10314 lb/ft^2

Permissible shear stress for channel bottom: 5.36984 lb/ft^2

channel bottom is stable

Stable D50: 0.484926 ft

Channel Side Shear Results

K1: 1

K2: 1

Kb: 0

shear stress on side of channel: 3.10314 lb/ft^2

Permissible shear stress for side of channel: 5.36984 lb/ft^2

Stable Side D50: 0.484926 lb/ft^2

side of channel is stable

Channel Lining Stability Results

the channel is stable

Channel Summary

Name of Selected Channel: RIPRAP RUNDOWN @ 5.39%

Channel Analysis: RIPRAP RUNDOWN @ 11.3%

Notes:

Input Parameters

Channel Type: Trapezoidal

Side Slope 1 (Z1): 10.0000 ft/ft

Side Slope 2 (Z2): 10.0000 ft/ft

Channel Width: 10.0000 ft

Longitudinal Slope: 0.1130 ft/ft

Manning's n: 0.0534

Flow: 49.7000 cfs

Result Parameters

Depth: 0.5891 ft

Area of Flow: 9.3606 ft^2

Wetted Perimeter: 21.8400 ft

Hydraulic Radius: 0.4286 ft

Average Velocity: 5.3095 ft/s

Top Width: 21.7813 ft

Froude Number: 1.4273

Critical Depth: 0.7172 ft

Critical Velocity: 4.0356 ft/s

Critical Slope: 0.0524 ft/ft

Critical Top Width: 24.34 ft

Calculated Max Shear Stress: 4.1536 lb/ft^2

Calculated Avg Shear Stress: 3.0221 lb/ft^2

Channel Lining Analysis: Channel Lining Design Analysis @11.3%

Notes:

Lining Input Parameters

Channel Lining Type: Riprap, Cobble, or Gravel

D50: 0.75 ft

Riprap Specific Weight: 165 lb/ft^3

Water Specific Weight: 62.4 lb/ft^3

Riprap Shape is Angular

Safety Factor: 1

Calculated Safety Factor: 1.1571

Lining Results

Angle of Repose: 41.7 degrees

Relative Flow Depth: 0.573005

Manning's n method: Bathurst

Manning's n: 0.0534294

Channel Bottom Shear Results

V*: 1.46402

Reynold's Number: 90223.3

Shield's Parameter: 0.0793312

shear stress on channel bottom: 4.1536 lb/ft^2

Permissible shear stress for channel bottom: 5.89025 lb/ft^2

channel bottom is stable

Stable D50: 0.611961 ft

Channel Side Shear Results

K1: 1

K2: 1

Kb: 0

shear stress on side of channel: 4.1536 lb/ft^2

Permissible shear stress for side of channel: 5.89025 lb/ft^2

Stable Side D50: 0.611961 lb/ft^2

side of channel is stable

Channel Lining Stability Results

the channel is stable

Channel Summary

Name of Selected Channel: RIPRAP RUNDOWN @ 11.3%

Channel Analysis: RIPRAP RUNDOWN @ 8.0%

Notes:

Input Parameters

Channel Type: Trapezoidal

Side Slope 1 (Z1): 10.0000 ft/ft

Side Slope 2 (Z2): 10.0000 ft/ft

Channel Width: 10.0000 ft

Longitudinal Slope: 0.0800 ft/ft

Manning's n: 0.0713

Flow: 49.7000 cfs

Result Parameters

Depth: 0.7458 ft

Area of Flow: 13.0211 ft^2

Wetted Perimeter: 24.9912 ft

Hydraulic Radius: 0.5210 ft

Average Velocity: 3.8169 ft/s

Top Width: 24.9168 ft

Froude Number: 0.9305

Critical Depth: 0.7174 ft

Critical Velocity: 4.0337 ft/s

Critical Slope: 0.0931 ft/ft

Critical Top Width: 24.35 ft

Calculated Max Shear Stress: 3.7232 lb/ft^2

Calculated Avg Shear Stress: 2.6010 lb/ft^2

Channel Lining Analysis: Channel Lining Design Analysis @8.0%

Notes:

Lining Input Parameters

Channel Lining Type: Riprap, Cobble, or Gravel

D50: 0.75 ft

Riprap Specific Weight: 165 lb/ft^3

Water Specific Weight: 62.4 lb/ft^3

Riprap Shape is Angular

Safety Factor: 1

Calculated Safety Factor: 1.1421

Lining Results

Angle of Repose: 41.7 degrees

Relative Flow Depth: 0.69678

Manning's n method: Bathurst

Manning's n: 0.0712516

Channel Bottom Shear Results

V*: 1.3861

Reynold's Number: 85421.2

Shield's Parameter: 0.0762399

shear stress on channel bottom: 3.72322 lb/ft^2

Permissible shear stress for channel bottom: 5.6927 lb/ft^2

channel bottom is stable

Stable D50: 0.560228 ft

Channel Side Shear Results

K1: 1

K2: 1

Kb: 0

shear stress on side of channel: 3.72322 lb/ft^2

Permissible shear stress for side of channel: 5.6927 lb/ft^2

Stable Side D50: 0.560228 lb/ft^2

side of channel is stable

Channel Lining Stability Results

the channel is stable

Channel Summary

Name of Selected Channel: RIPRAP RUNDOWN @ 8.0%

SWALE CALCULATIONS

Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Friday, Nov 17 2023

DP-13 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 5.00
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.30

Highlighted

Depth (ft)	= 0.32
Q (cfs)	= 5.300
Area (sqft)	= 1.37
Velocity (ft/s)	= 3.87
Wetted Perim (ft)	= 5.64
Crit Depth, Yc (ft)	= 0.39
Top Width (ft)	= 5.56
EGL (ft)	= 0.55



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-14 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.60
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.50

Highlighted

Depth (ft)	= 0.33
Q (cfs)	= 5.500
Area (sqft)	= 1.43
Velocity (ft/s)	= 3.86
Wetted Perim (ft)	= 5.72
Crit Depth, Yc (ft)	= 0.40
Top Width (ft)	= 5.64
EGL (ft)	= 0.56



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-15 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.60
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 6.60

Highlighted

Depth (ft)	= 0.36
Q (cfs)	= 6.600
Area (sqft)	= 1.60
Velocity (ft/s)	= 4.13
Wetted Perim (ft)	= 5.97
Crit Depth, Yc (ft)	= 0.44
Top Width (ft)	= 5.88
EGL (ft)	= 0.63



Channel Report

DP-16 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.60
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 7.20

Highlighted

Depth (ft)	= 0.38
Q (cfs)	= 7.200
Area (sqft)	= 1.72
Velocity (ft/s)	= 4.19
Wetted Perim (ft)	= 6.13
Crit Depth, Yc (ft)	= 0.46
Top Width (ft)	= 6.04
EGL (ft)	= 0.65



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-17 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.90
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 5.00

Highlighted

Depth (ft)	= 0.31
Q (cfs)	= 5.000
Area (sqft)	= 1.31
Velocity (ft/s)	= 3.80
Wetted Perim (ft)	= 5.56
Crit Depth, Yc (ft)	= 0.38
Top Width (ft)	= 5.48
EGL (ft)	= 0.53



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Dec 4 2023

DP-18 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.90
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 10.60

Highlighted

Depth (ft)	= 0.46
Q (cfs)	= 10.60
Area (sqft)	= 2.23
Velocity (ft/s)	= 4.76
Wetted Perim (ft)	= 6.79
Crit Depth, Yc (ft)	= 0.57
Top Width (ft)	= 6.68
EGL (ft)	= 0.81



Channel Report

DP-19 Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 2.60
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 6.10

Highlighted

Depth (ft)	= 0.41
Q (cfs)	= 6.100
Area (sqft)	= 1.90
Velocity (ft/s)	= 3.21
Wetted Perim (ft)	= 6.38
Crit Depth, Yc (ft)	= 0.42
Top Width (ft)	= 6.28
EGL (ft)	= 0.57



Channel Report

DP-20 Q100

Trapezoidal

Bottom Width (ft)	= 10.00
Side Slopes (z:1)	= 4.00, 10.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 2.00
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 43.00

Highlighted

Depth (ft)	= 0.69
Q (cfs)	= 43.00
Area (sqft)	= 10.23
Velocity (ft/s)	= 4.20
Wetted Perim (ft)	= 19.78
Crit Depth, Yc (ft)	= 0.71
Top Width (ft)	= 19.66
EGL (ft)	= 0.96



Channel Report

Hydraflow Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Friday, Nov 17 2023

DP-21a Q100

Trapezoidal

Bottom Width (ft)	= 3.00
Side Slopes (z:1)	= 4.00, 4.00
Total Depth (ft)	= 1.50
Invert Elev (ft)	= 1.00
Slope (%)	= 4.80
N-Value	= 0.032

Calculations

Compute by:	Known Q
Known Q (cfs)	= 7.80

Highlighted

Depth (ft)	= 0.39
Q (cfs)	= 7.800
Area (sqft)	= 1.78
Velocity (ft/s)	= 4.39
Wetted Perim (ft)	= 6.22
Crit Depth, Yc (ft)	= 0.48
Top Width (ft)	= 6.12
EGL (ft)	= 0.69



APPENDIX B

STANDARD DESIGN CHARTS AND TABLES

Table 6-6. Runoff Coefficients for Rational Method
(Source: UDFCD 2001)

Land Use or Surface Characteristics	Percent Impervious	Runoff Coefficients											
		2-year		5-year		10-year		25-year		50-year		100-year	
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D
Business													
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	0.60	0.65	0.62	0.68
Residential													
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0.59	0.65
1/4 Acre	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.47	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Parks and Cemeteries	7	0.05	0.09	0.12	0.19	0.20	0.29	0.30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
Undeveloped Areas													
Historic Flow Analysis--Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Gravel	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Lawns	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50

3.2 Time of Concentration

One of the basic assumptions underlying the Rational Method is that runoff is a function of the average rainfall rate during the time required for water to flow from the hydraulically most remote part of the drainage area under consideration to the design point. However, in practice, the time of concentration can be an empirical value that results in reasonable and acceptable peak flow calculations.

For urban areas, the time of concentration (t_c) consists of an initial time or overland flow time (t_i) plus the travel time (t_t) in the storm sewer, paved gutter, roadside drainage ditch, or drainage channel. For non-urban areas, the time of concentration consists of an overland flow time (t_i) plus the time of travel in a concentrated form, such as a swale or drainageway. The travel portion (t_t) of the time of concentration can be estimated from the hydraulic properties of the storm sewer, gutter, swale, ditch, or drainageway. Initial time, on the other hand, will vary with surface slope, depression storage, surface cover, antecedent rainfall, and infiltration capacity of the soil, as well as distance of surface flow. The time of concentration is represented by Equation 6-7 for both urban and non-urban areas.

Type of Development	Percent Impervious
Commercial	95%
Industrial	85%
Multi-Family	65%
Single Family - 0.1377 acre lots (6,000 SF)	53%
Single-Family - 0.20 acre lots	43%
Single-Family - 0.25 acre lots	40%
Single-Family - 0.33 acre lots	30%
Single-Family - 0.5 acre lots	25%
Single-Family - 1.0 acre lots	20%
Single-Family - 2.5 acre lots	11%
Single-Family - 5 acre lots	7%

Figure 6-25. Estimate of Average Concentrated Shallow Flow



El Paso County Drainage Basin Fees

Resolution No. 22-442

Basin Number	Receiving Waters	Year Studied	Drainage Basin Name	2023 Drainage Fee (per Impervious Acre)	2023 Bridge Fee (per Impervious Acre)
Drainage Basins with DBPS's:					
CHMS0200	Chico Creek	2013	Haegler Ranch	$12,985	$1,916
CHWS1200	Chico Creek	2001	Bennett Ranch	$14,536	$5,576
CHWS1400	Chico Creek	2013	Falcon	$37,256	$5,118
FOFO2000	Fountain Creek	2001	West Fork Jimmy Camp Creek	$15,802	$4,675
FOFO2600	Fountain Creek	1991*	Big Johnson / Crews Gulch	$23,078	$2,980
FOFO2800	Fountain Creek	1988*	Widefield	$23,078	$0
FOFO2900	Fountain Creek	1988*	Security	$23,078	$0
FOFO3000	Fountain Creek	1991*	Windmill Gulch	$23,078	$346
FOFO3100 / FOFO3200	Fountain Creek	1988*	Carson Street / Little Johnson	$14,077	$0
FOFO3400	Fountain Creek	1984*	Peterson Field	$16,646	$1,262
FOFO3600	Fountain Creek	1991*	Fisher's Canyon	$23,078	$0
FOFO4000	Fountain Creek	1996	Sand Creek	$23,821	$9,743
FOFO4200	Fountain Creek	1977	Spring Creek	$11,969	$0
FOFO4600	Fountain Creek	1984*	Southwest Area	$23,078	$0
FOFO4800	Fountain Creek	1991	Bear Creek	$23,078	$1,262
FOFO5800	Fountain Creek	1964	Camp Creek	$2,557	$0
FOMO1000	Monument Creek	1981	Douglas Creek	$14,514	$321
FOMO1200	Monument Creek	1977	Templeton Gap	$14,900	$346
FOMO2000	Monument Creek	1971	Pulpit Rock	$7,653	$0
FOMO2200	Monument Creek	1994	Cottonwood Creek / S. Pine	$23,078	$1,262
FOMO2400	Monument Creek	1966	Dry Creek	$18,219	$660
FOMO3600	Monument Creek	1989*	Black Squirrel Creek	$10,478	$660
FOMO3700	Monument Creek	1987*	Middle Tributary	$19,259	$0
FOMO3800	Monument Creek	1987*	Monument Branch	$23,078	$0
FOMO4000	Monument Creek	1996	Smith Creek	$9,409	$1,262
FOMO4200	Monument Creek	1989*	Black Forest	$23,078	$628
FOMO5200	Monument Creek	1993*	Dirty Woman Creek	$23,078	$1,262
FOMO5300	Fountain Creek	1993*	Crystal Creek	$23,078	$1,262
Miscellaneous Drainage Basins: [1]					
CHBS0800	Chico Creek		Book Ranch	$21,654	$3,135
CHEC0400	Chico Creek		Upper East Chico	$11,797	$342
CHWS0200	Chico Creek		Telephone Exchange	$12,962	$304
CHWS0400	Chico Creek		Livestock Company	$21,351	$254
CHWS0600	Chico Creek		West Squirrel	$11,129	$4,619
CHWS0800	Chico Creek		Solberg Ranch	$23,078	$0
FOFO1200	Fountain Creek		Crooked Canyon	$6,968	$0
FOFO1400	Fountain Creek		Calhan Reservoir	$5,817	$339
FOFO1600	Fountain Creek		Sand Canyon	$4,203	$0
FOFO2000	Fountain Creek		Jimmy Camp Creek[3]	$23,078	$1,079
FOFO2200	Fountain Creek		Fort Carson	$18,219	$660
FOFO2700	Fountain Creek		West Little Johnson	$1,521	$0
FOFO3800	Fountain Creek		Stratton	$11,070	$495
FOFO5000	Fountain Creek		Midland	$18,219	$660
FOFO6000	Fountain Creek		Palmer Trail	$18,219	$660
FOFO6800	Fountain Creek		Black Canyon	$18,219	$660
FOMO4600	Monument Creek		Beaver Creek	$13,797	$0
FOMO3000	Monument Creek		Kettle Creek	$12,463	$0
FOMO3400	Monument Creek		Elkhorn	$2,094	$0
FOMO5000	Monument Creek		Monument Rock	$10,003	$0
FOMO5400	Monument Creek		Palmer Lake	$15,995	$0
FOMO5600	Monument Creek		Raspberry Mountain	$5,380	$0
PLPL0200	Monument Creek		Bald Mountain	$11,465	$0
Interim Drainage Basins: [2]					
FOFO1800	Fountain Creek		Little Fountain Creek	$2,950	$0
FOMO4400	Monument Creek		Jackson Creek	$9,135	$0
FOMO4800	Monument Creek		Teachout Creek	$6,343	$953

1. The miscellaneous drainage fee previous to September 1999 resolution was the average of all drainage fees for basins with Basin Planning Studies performed within the last 14 years.

2. Interim Drainage Fees are based upon draft Drainage Basin Planning Studies or the Drainage Basin Identification and Fee Estimation Report. (Best available information suitable for setting a fee.)

3. This is an interim fee and will be adjusted when a DBPS is completed. In addition to the Drainage Fee a surety in the amount of $7,285 per impervious acre shall be provided to secure payment of additional fees in the event that the DBPS results in a fee greater than the current fee. Fees paid in excess of the future revised fee will be reimbursed. See Resolution 06-326 (9/14/06) and Resolution 16-320 (9/07/16).

EPC Stormwater Management *Joshua Palmer, P.E.*

Channel Slope	Lining	Permissible Mean Channel Velocity* (ft/sec)
0 - 5%	Sodded grass	7
	Bermudagrass	6
	Reed canarygrass	5
	Tall fescue	5
	Kentucky bluegrass	5
	Grass-legume mixture	4
	Red fescue	2.5
	Redtop	2.5
	Sericea lespedeza	2.5
	Annual lespedeza	2.5
	Small grains (temporary)	2.5
5 - 10%	Sodded grass	6

Channel Slope	Lining	Permissible Mean Channel Velocity* (ft/sec)
	Bermudagrass	5
	Reed canarygrass	4
	Tall fescue	4
	Kentucky bluegrass	4
	Grass-legume mixture	3
Greater than 10%	Sodded grass	5
	Bermudagrass	4
	Reed canarygrass	3
	Tall fescue	3
	Kentucky bluegrass	3
*For highly erodible soils, decrease permissible velocities by 25%.		
*Grass lined channels are dependent upon assurances of continuous growth and maintenance of grass.		

APPENDIX C

REPORT REFERENCES

```
1*************************************************
         ************************************
 *  WATER SURFACE PROFILES                       *
         *  U.S. ARMY CORPS OF ENGINEERS       *
 *  VERSION OF SEPTEMBER 1988                    *
         *  THE HYDROLOGIC ENGINEERING CENTER  *
 *  ERROR: 01,02                                 *
         *  609 SECOND STREET, SUITE D         *
 *  UPDATED:  4 APRIL    1989                    *
         *  DAVIS, CALIFORNIA 95616-4687       *
 *  RUN DATE    11/ 3/ 3   TIME   12:40:22       *
         *  (916) 756-1104, (916) 551-1748     *
 *************************************************
         ************************************
```

THIS DOCUMENT IS THE HEC-2 MODEL PRINT OUT FOR THE 2003 LOMR FOR BEAVER CREEK. IT WAS SOURCED FROM THE REGIONAL FLOODPLAIN ADMINISTRATOR AT PIKES PEAK REGIONAL BUILDING DEPARTMENT (PPRBD).

```
                                                X     X  XXXXXXX   XXXXX
XXXXX
                                                X     X  X        X     X           X
    X
                                                X     X  X        X
    X
                                                XXXXXXX  XXXX     X          XXXXX
XXXXX
                                                X     X  X        X                 X

                                                X     X  X        X     X           X

                                                X     X  XXXXXXX   XXXXX
XXXXXXX
 END OF BANNER
1
    11/ 3/ 3      12:40:22
                                  PAGE    1



 THIS RUN EXECUTED 11/ 3/ 3    12:40:22
 ************************************************
   HEC2 RELEASE DATED SEP 88 UPDATED APR  1989


   ERROR CORR -  01,02
   MODIFICATION -
 ************************************************


 T1      BEAVER CREEK LOMR PROJECT NO. 03012
 T2      BEAVER CREEK FROM MONUMENT CREEK CONFLUENCE THROUGH SOUTH FORK
```

```
 T3      FILE NAME BVREFF.DAT
 T3      100-YEAR FREQUENCY CROSS-SECTIONS L TO R FACING UPSTREAM

 J1  ICHECK    INQ       NINV      IDIR      STRT      METRIC    HVINS     Q
 WSEL      FQ

       0         3         0         0         0         0         0         0
6733.2

 J2  NPROF     IPLOT     PRFVS     XSECV     XSECH     FN        ALLDC     IBW
CHNIM      ITRACE

       1         0        -1

 QT        2       6317      20974

 NC      .07        .07        .05         .2         .4

         CONFLUENCE WITH MONUMENT CREEK
 X1       60         15       1280       1360          0          0          0

 GR     6752       1000       6750       1085       6740       1170       6735
     1235       6730       1250
 GR     6725       1280       6720       1295       6718       1305       6720
     1310       6725       1360
 GR     6730       1445       6735       1525       6740       1560       6745
     1670       6750       1810

 QT        2       3507       6915

 NC      .07        .07        .05

 X1        1         14       1507       1545       1047       1047       1047

 GR     6748       1000       6744       1163       6742       1193       6740
     1313       6740       1358
 GR     6738       1386       6736       1507       6734       1520       6732
     1526       6732       1541
 GR     6740       1548       6746       1563       6746       1748       6748
     1798

 NC      .07        .07        .05         .1         .3

 X1        2         11       1136       1195        759        759        759

 GR     6758       1034       6756       1049       6750       1064       6748
     1076       6748       1136
 GR     6746       1147       6746       1184       6748       1195       6750
     1227       6756       1254
 GR     6758       1274


 QT        2       1847       5128
```

THE QT ROW/CARD REPRESENTS THE FLOW VALUES USED IN THE HEC-2 MODELS. THIS QT CARD IS AT THE CONFLUENCE OF BEAVER AND MONUMENT CREEK WHICH IS LOCATED JUST DOWNSTREAM OF THE HAY AND BEAVER CREEK CONFLUENCE.

THIS QT CARD IS APPROXIMATELY AT THE HAY CREEK CONFLUENCE WITH BEAVER CREEK AND DEMONSTRATES A 127 CFS INCREASE OVER THE UPSTREAM QT CARD. (6915 CFS -6788 CFS=127 CFS). WE THEREFORE BELIEVE 127 CFS TO BE A REASONABLE FLOW TO USE FOR HAY CREEK.

```
NC     .013       .013       .015         .1          .3

        HAY CREEK ROAD 2-72", 1-78" AND 1-84" CMP'S
        CROSS SECTION MODELED FOR ROAD PROFILE
        FLOW OVER ROAD REDUCED FOR CULVERTS CAPACITY
        CULVERTS CALCULATED CAPACITY = 1660 cfs
X1       3          6       1130       1250         845         845         845

GR     6778       1000       6772       1130        6772        1250        6774
    1390        6776        1500
GR     6778       1720

1
   11/ 3/ 3      12:40:22
                                PAGE     2

NC     .025       .025       .025         .1          .3

QT       2       3107       6788

        DELACROCE RANCH ROAD CROSSING 1-84" AND 1-72" CMP
        CROSS SECTION MODELED FOR ROAD PROFILE
        FLOW OVER ROAD REDUCED FOR CULVERTS CAPACITY
        CULVERTS CALCULATED CAPACITY = 400 cfs
X1       4          5       1070       1280         984         984         984

X4       1       6786       1000

GR     6790        900       6784       1070        6784        1280        6790
    1420        6796        1520

NC      .07        .07        .08

X1       5         14       1243       1314         722         722         722

GR     6806       1188       6804       1198        6800        1211        6798
    1221        6786        1246
GR     6786       1272       6788       1314        6790        1344        6796
    1391        6796        1427
GR     6798       1428       6800       1435        6804        1475        6806
    1512

NC     .013       .013       .013         .1          .3

QT       2       3216       6154

NC     .013       .013       .015         .1          .3

X1      6.1          9       1209       1230        1160        1160        1160

GR     6840       1000       6828       1091        6828        1209      6806.6
    1209      6806.6        1230
GR     6828       1230       6828       1316        6830        1457        6840
    1619
```

NOTE THAT, ONCE THE FLOW THROUGH THE CULVERTS IS ACCOUNTED FOR, THE QT CARD MATCHES THE UPSTREAM QT CARD AT 6788 CFS. (5128 CFS + 1660 CFS = 6788 CFS)

THIS QT CARD IS AT THE HAY CREEK ROAD CULVERT JUST UPSTREAM OF THE CONFLUENCE WITH HAY CREEK.

```
SB     1.05       1.25        2.6          0          20         1.0         210
       0      6807.3      6806.6
NC     .013       .013       .015         .3          .5

        LONG VALLEY DRIVE, EXISITNG 2-10' x 10' CBC FACE
X1      6.2          9       1209       1230          48          48          48

X2        0          0          1     6817.3        6828

BT        9       1000       6840       6840        1091        6828        6828
    1209        6828        6828
BT     1209       6828     6817.3       1230        6828      6817.3        1230
    6828        6828        1316
BT     6828       6828       1457       6830        6830        1619        6840
    6840
GR     6840       1000       6828       1091        6828        1209      6807.3
    1209      6807.3        1230
GR     6828       1230       6828       1316        6830        1457        6840
    1619

NC      .07        .07        .08         .1          .3

X1        7          9       1146       1193         856         856         856

GR     6862       1033       6858       1042        6856        1071        6854
    1146        6854        1193
GR     6856       1279       6858       1312        6860        1326        6862
    1354

NC     .015       .015        .02

        BRISTLECONE LAKE CONCRETE SPILLWAY
X1        8          8       1080       1520        1026        1026        1026

GR     6910       1000       6908       1020        6900        1050        6890
    1080        6889        1090
GR     6889       1500       6890       1520        6908        1580


QT        2       4860       8624

NC      .07        .07        .05

        FLOW INTO BRISTLECONE LAKE
X1        9         13       1484       1817        2638        2638        2638

GR     6910       1000       6908       1050        6906        1135        6900
    1173        6894        1260
GR     6890       1484       6890       1817        6894        1824        6894
    1845        6900        1871
GR     6902       1905       6908       1982        6910        1991

1
    11/ 3/ 3      12:40:22
                                PAGE     3
```

```
X1       10         15       1169       1529        590        590        590

GR     6916       1000       6910       1044       6908       1064       6904
     1112       6900       1230
GR     6898       1270       6898       1334       6896       1349       6896
     1361       6898       1379
GR     6900       1392       6902       1530       6910       1614       6912
     1645       6916       1662

NC       .1         .1        .08

X1       11         13       1149       1363        701        701        701

GR     6924       1000       6920       1041       6918       1069       6916
     1077       6910       1149
GR     6908       1165       6904       1177       6904       1216       6906
     1226       6906       1346
GR     6916       1381       6918       1392       6924       1456


X1       12         14       1213       1240        643        643        643

GR     6936       1000       6928       1110       6926       1162       6922
     1176       6922       1213
GR     6916       1226       6916       1228       6922       1240       6922
     1246       6918       1256
GR     6916       1317       6916       1447       6930       1486       6936
     1566

X1       13         10       1139       1345        689        689        689

GR     6948       1000       6944       1053       6940       1139       6938
     1152       6928       1195
GR     6928       1221       6930       1230       6932       1274       6934
     1321       6948       1429

X1       14         11       1184       1401        834        834        834

GR     6964       1000       6956       1071       6954       1119       6948
     1234       6946       1305
GR     6944       1316       6944       1342       6946       1392       6956
     1414       6958       1435
GR     6964       1527


X1       15         17       1091       1278        764        764        764

GR     6978       1000       6970       1047       6966       1081       6962
     1091       6962       1133
GR     6960       1145       6958       1161       6958       1177       6960
     1219       6962       1278
GR     6962       1312       6960       1319       6960       1333       6962
     1336       6970       1371
```

```
GR     6974       1430       6978       1448

X1       16         15       1266       1400         718         718         718

GR     6994       1000       6992       1025       6986       1193       6984
    1205       6980       1266
GR     6974       1321       6974       1331       6976       1364       6980
    1400       6982       1505
GR     6986       1572       6988       1584       6990       1609       6992
    1615       6994       1618

QT        2       4772       8270

        CONFLUENCE OF NORTH AND SOUTH BEAVER CREEK
X1       17         16       1101       1378         547         547         547

GR     7008       1000       7002       1072       6998       1101       6994
    1117       6992       1121
GR     6988       1139       6988       1169       6990       1196       6992
    1213       6996       1277
GR     6996       1324       6998       1378       7000       1410       7002
    1427       7004       1489
GR     7008       1552


QT        2       3757       6754

        BEAVER CREEK SOUTH FORK
X1       18         10       1075       1269         598         598         598

GR     7022       1000       7018       1075       7016       1088       7004
    1122       7002       1128
GR     7002       1151       7008       1187       7012       1237       7020
    1269       7022       1285
1
    11/ 3/ 3      12:40:22
                                PAGE     4


X1       19         16       1115       1341         800         800         800

GR     7046       1000       7044       1021       7038       1072       7034
    1115       7032       1129
GR     7030       1177       7028       1198       7026       1207       7026
    1228       7030       1242
GR     7032       1259       7034       1341       7038       1412       7040
    1473       7042       1536
GR     7046       1578


X1       20         14       1046       1295         625         625         625

GR     7068       1000       7062       1031       7058       1046       7056
    1061       7052       1072
```

```
 GR     7050       1099       7048       1122       7048       1178       7050
     1185       7052       1201
 GR     7058       1264       7060       1295       7062       1384       7068
     1656

 X1       21         17       1066       1246        879        879        879

 GR     7092       1000       7084       1032       7080       1066       7078
     1109       7074       1133
 GR     7072       1139       7072       1171       7074       1180       7076
     1200       7076       1229
 GR     7078       1239       7080       1246       7084       1271       7086
     1306       7086       1328
 GR     7088       1368       7092       1445


 X1       22          8       1032       1179        554        554        554

 GR     7104       1000       7096       1032       7094       1079       7092
     1085       7092       1094
 GR     7094       1108       7096       1179       7104       1252


 X1       23          7       1119       1165        514        514        514

 GR     7124       1000       7110       1119       7108       1145       7108
     1158       7110       1165
 GR     7120       1189       7124       1205




1
    11/ 3/ 3      12:40:22
                                PAGE    5


    SECNO    DEPTH    CWSEL    CRIWS    WSELK    EG       HV       HL       OLOSS
BANK ELEV
    Q        QLOB     QCH      QROB     ALOB     ACH      AROB     VOL      TWA
LEFT/RIGHT
    TIME     VLOB     VCH      VROB     XNL      XNCH     XNR      WTN      ELMIN
   SSTA
    SLOPE    XLOBL    XLCH     XLOBR    ITRIAL   IDC      ICONT    CORAR    TOPWID
   ENDST


 *PROF 1
0

 CCHV=     .200 CEHV=     .400
 *SECNO 60.000
 3720 CRITICAL DEPTH ASSUMED
         CONFLUENCE WITH MONUMENT CREEK
     60.00    15.36  6733.36  6733.36  6733.20  6736.77     3.41      .00      .00
6725.00
```

```
    20974.    1400.   15429.    4145.     193.     921.     588.       0.       0.
 6725.00
      .00     7.27    16.75     7.05     .070     .050     .070     .000  6718.00
1239.93
   .012557       0.       0.       0.        0        4        0      .00   258.76
1498.70
0
 CCHV=     .100 CEHV=     .300
 *SECNO 1.000

 3301 HV CHANGED MORE THAN HVINS

     1.00    11.87  6743.87      .00      .00  6744.18      .30     7.10      .31
6736.00
     6915.    4409.    2319.     187.    1514.     359.      74.      44.       8.
 6732.00
      .07     2.91     6.46     2.53     .070     .050     .070     .000  6732.00
1164.88
   .002082    1047.    1047.    1047.        3        0        0      .00   392.81
1557.69
0
 CCHV=     .100 CEHV=     .300
 *SECNO 2.000

 3301 HV CHANGED MORE THAN HVINS

 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
     2.00     5.95  6751.95  6751.95      .00  6753.89     1.94     3.60      .49
6748.00
     6915.    1999.    4311.     605.     277.     329.     103.      67.      13.
 6748.00
      .09     7.21    13.09     5.87     .070     .050     .070     .000  6746.00
1059.12
   .019770     759.     759.     759.       20        8        0      .00   176.67
1235.79
0
 CCHV=     .100 CEHV=     .300
 *SECNO 3.000

 3301 HV CHANGED MORE THAN HVINS

1
    11/ 3/ 3      12:40:22
                                PAGE    6


    SECNO    DEPTH    CWSEL    CRIWS    WSELK    EG       HV       HL       OLOSS
BANK ELEV
    Q        QLOB     QCH      QROB     ALOB     ACH      AROB     VOL      TWA
LEFT/RIGHT
    TIME     VLOB     VCH      VROB     XNL      XNCH     XNR      WTN      ELMIN
   SSTA
    SLOPE    XLOBL    XLCH     XLOBR    ITRIAL   IDC      ICONT    CORAR    TOPWID
   ENDST
```

```
 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
         HAY CREEK ROAD 2-72", 1-78" AND 1-84" CMP'S
         CROSS SECTION MODELED FOR ROAD PROFILE
         FLOW OVER ROAD REDUCED FOR CULVERTS CAPACITY
         CULVERTS CALCULATED CAPACITY = 1660 cfs
      3.00     2.75  6774.75  6774.75      .00  6775.69      .94     4.43      .10
6772.00
     5128.     506.    2806.    1817.      82.     330.     260.      80.      18.
 6772.00
       .12     6.18     8.51     6.99     .013     .015     .013     .000  6772.00
1070.47
   .001918     845.     845.     845.       20       14        0      .00   360.65
1431.12
0
 CCHV=     .100 CEHV=     .300
 *SECNO 4.000
 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
         DELACROCE RANCH ROAD CROSSING 1-84" AND 1-72" CMP
         CROSS SECTION MODELED FOR ROAD PROFILE
         FLOW OVER ROAD REDUCED FOR CULVERTS CAPACITY
         CULVERTS CALCULATED CAPACITY = 400 cfs
      4.00     2.82  6786.82  6786.82      .00  6787.96     1.14     3.30      .06
6784.00
     6788.     884.    5375.     530.     136.     592.      93.      97.      26.
 6784.00
       .15     6.52     9.08     5.72     .025     .025     .025     .000  6784.00
 979.55
   .005866     984.     984.     984.       20        8        0      .00   366.20
1345.75
0
 *SECNO 5.000

 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =   .54

      5.00     7.93  6793.93      .00      .00  6795.16     1.23     7.17      .03
6798.00
     6788.       0.    5205.    1583.       0.     563.     208.     110.      30.
 6788.00
       .18      .00     9.25     7.59     .000     .080     .070     .000  6786.00
1229.48
   .020365     722.     722.     722.        3        0        0      .00   145.32
1374.79
0
 CCHV=     .100 CEHV=     .300
 CCHV=     .100 CEHV=     .300
 *SECNO 6.100
1
    11/ 3/ 3      12:40:22
                                PAGE    7
```

```
    SECNO     DEPTH     CWSEL     CRIWS     WSELK     EG        HV        HL        OLOSS
BANK ELEV
    Q         QLOB      QCH       QROB      ALOB      ACH       AROB      VOL       TWA
LEFT/RIGHT
    TIME      VLOB      VCH       VROB      XNL       XNCH      XNR       WTN       ELMIN
   SSTA
    SLOPE     XLOBL     XLCH      XLOBR     ITRIAL    IDC       ICONT     CORAR     TOPWID
   ENDST



 3301 HV CHANGED MORE THAN HVINS

 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
      6.10    13.82  6820.42  6820.42      .00  6827.40     6.98     9.61     1.73
6828.00
     6154.       0.    6154.       0.       0.     290.       0.     125.      33.
 6828.00
       .19      .00    21.20      .00     .000     .015     .000     .000  6806.60
1209.00
   .004232    1160.    1160.    1160.       20       14        0      .00    21.00
1230.00
0

 SPECIAL BRIDGE

 5227 DOWNSTREAM ELEV IS    6818.62 , NOT    6820.42 HYDRAULIC JUMP OCCURS
DOWNSTREAM (IF LOW FLOW CONTROLS)

 SB  XK        XKOR      COFQ      RDLEN     BWC       BWP       BAREA     SS
 ELCHU     ELCHD
      1.05      1.25      2.60       .00     20.00      1.00    210.00       .00
6807.30   6806.60

 CCHV=     .300 CEHV=     .500
 *SECNO 6.200

 3301 HV CHANGED MORE THAN HVINS


 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =  1.45

 PRESSURE AND WEIR FLOW,  Weir Submergence Based on TRAPEZOIDAL Shape


  EGPRS      EGLWC       H3       QWEIR      QPR       BAREA   TRAPEZOID      ELLC
   ELTRD     WEIRLN
                                                                 AREA
    6837.09   6829.67       .00     1566.     4591.      210.      190.     6817.30
  6828.00      358.


        LONG VALLEY DRIVE, EXISITNG 2-10' x 10' CBC FACE
```

```
      6.20    18.51  6825.81      .00      .00  6829.70     3.89     2.30      .00
6828.00
     6154.       0.    6154.       0.       0.     389.       0.     125.      33.
 6828.00
       .19      .00    15.84      .00     .000     .015     .000     .000  6807.30
1209.00
   .002023      48.      48.      48.        6        0        5      .00    21.00
1230.00
0
 CCHV=     .100 CEHV=     .300
1
    11/ 3/ 3      12:40:22
                                PAGE    8


    SECNO    DEPTH    CWSEL    CRIWS    WSELK    EG       HV       HL       OLOSS
BANK ELEV
    Q        QLOB     QCH      QROB     ALOB     ACH      AROB     VOL      TWA
LEFT/RIGHT
    TIME     VLOB     VCH      VROB     XNL      XNCH     XNR      WTN      ELMIN
   SSTA
    SLOPE    XLOBL    XLCH     XLOBR    ITRIAL   IDC      ICONT    CORAR    TOPWID
   ENDST


 *SECNO 7.000

 3301 HV CHANGED MORE THAN HVINS

 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
     7.00     3.79  6857.79  6857.79      .00  6859.09     1.29     4.78      .26
6854.00
     6154.    2041.    1773.    2340.     233.     178.     267.     135.      35.
 6854.00
       .22     8.77     9.94     8.78     .070     .080     .070     .000  6854.00
1045.01
   .048456     856.     856.     856.       20       21        0      .00   263.57
1308.58
0
 *SECNO 8.000
 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
        BRISTLECONE LAKE CONCRETE SPILLWAY
     8.00     1.86  6890.86  6890.86      .00  6891.77      .91    11.36      .04
6890.00
     6154.       4.    6145.       5.       1.     802.       1.     153.      44.
 6890.00
       .26     3.76     7.66     3.78     .015     .020     .015     .000  6889.00
1077.43
   .004781    1026.    1026.    1026.       20       11        0      .00   445.42
1522.85
0
 *SECNO 9.000
```

```
 3301 HV CHANGED MORE THAN HVINS


 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =  3.00

         FLOW INTO BRISTLECONE LAKE
      9.00     6.25  6896.25      .00      .00  6896.39      .14     4.54      .08
6890.00
     8624.    1738.    6774.     112.     988.    2081.      88.     273.      76.
 6890.00
       .51     1.76     3.26     1.28     .070     .050     .070     .000  6890.00
1227.40
   .001042    2638.    2638.    2638.        6        0        0      .00   627.35
1854.74
0
 *SECNO 10.000

 3301 HV CHANGED MORE THAN HVINS

 3685 20 TRIALS ATTEMPTED WSEL,CWSEL
1
    11/ 3/ 3      12:40:22
                                PAGE    9


    SECNO    DEPTH    CWSEL    CRIWS    WSELK    EG       HV       HL       OLOSS
BANK ELEV
    Q        QLOB     QCH      QROB     ALOB     ACH      AROB     VOL      TWA
LEFT/RIGHT
    TIME     VLOB     VCH      VROB     XNL      XNCH     XNR      WTN      ELMIN
   SSTA
    SLOPE    XLOBL    XLCH     XLOBR    ITRIAL   IDC      ICONT    CORAR    TOPWID
   ENDST


 3693 PROBABLE MINIMUM SPECIFIC ENERGY
 3720 CRITICAL DEPTH ASSUMED
     10.00     6.42  6902.42  6902.42      .00  6903.79     1.37     1.64      .37
6904.00
     8624.       0.    7868.     756.       0.     806.     197.     301.      83.
 6900.00
       .52      .00     9.76     3.84     .000     .050     .070     .000  6896.00
1158.67
   .020723     590.     590.     590.       20        8        0      .00   375.72
1534.39
0
 *SECNO 11.000

 3301 HV CHANGED MORE THAN HVINS


 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =  1.51

     11.00     8.51  6912.51      .00      .00  6913.11      .60     9.25      .08
6910.00
```

```
     8624.      63.    8336.     226.      38.    1323.      74.     321.      88.
 6906.00
       .55     1.65     6.30     3.04     .100     .080     .100     .000  6904.00
1118.82
   .009130     701.     701.     701.        5        0        0      .00   249.98
1368.80
0
 *SECNO 12.000

 3265 DIVIDED FLOW


 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =   .58

     12.00     5.74  6921.74      .00      .00  6922.57      .83     9.39      .07
6922.00
     8624.       0.     489.    8135.       0.      80.    1101.     340.      92.
 6922.00
       .58      .00     6.08     7.39     .000     .080     .100     .000  6916.00
1213.54
   .027002     643.     643.     643.        2        0        0      .00   242.34
1463.02
0
 *SECNO 13.000
     13.00     9.37  6937.37      .00      .00  6938.49     1.12    15.83      .09
6940.00
     8624.       0.    8495.     129.       0.     993.      44.     357.      95.
 6934.00
       .60      .00     8.55     2.94     .000     .080     .100     .000  6928.00
1154.72
   .019789     689.     689.     689.        3        0        0      .00   192.27
1346.98
0
 *SECNO 14.000
     14.00     8.38  6952.38      .00      .00  6953.10      .72    14.57      .04
6954.00
     8624.       0.    8455.     169.       0.    1234.      45.     380.     100.
 6946.00
       .64      .00     6.85     3.77     .000     .080     .100     .000  6944.00
1150.04
   .015530     834.     834.     834.        5        0        0      .00   255.99
1406.04
0
1
    11/ 3/ 3      12:40:22
                                PAGE   10


    SECNO    DEPTH    CWSEL    CRIWS    WSELK    EG       HV       HL       OLOSS
BANK ELEV
    Q        QLOB     QCH      QROB     ALOB     ACH      AROB     VOL      TWA
LEFT/RIGHT
    TIME     VLOB     VCH      VROB     XNL      XNCH     XNR      WTN      ELMIN
   SSTA
    SLOPE    XLOBL    XLCH     XLOBR    ITRIAL   IDC      ICONT    CORAR    TOPWID
   ENDST
```

```
 *SECNO 15.000
    15.00     7.44  6965.44      .00      .00  6966.26      .82    13.13      .03
6962.00
     8624.      42.    7240.    1342.      15.     953.     264.     402.     104.
 6962.00
       .67     2.81     7.60     5.09     .100     .080     .100     .000  6958.00
1082.39
   .019128     764.     764.     764.        4        0        0      .00   268.67
1351.06
0
 *SECNO 16.000

 3301 HV CHANGED MORE THAN HVINS

    16.00     8.28  6982.28  6981.98      .00  6983.91     1.63    17.41      .24
6980.00
     8624.     114.    8093.     417.      39.     767.     134.     420.     109.
 6980.00
       .69     2.88    10.55     3.10     .100     .080     .100     .000  6974.00
1231.31
   .031727     718.     718.     718.        7        8        0      .00   278.30
1509.60
0
 *SECNO 17.000

 3301 HV CHANGED MORE THAN HVINS

         CONFLUENCE OF NORTH AND SOUTH BEAVER CREEK
    17.00     9.53  6997.53      .00      .00  6998.36      .82    14.36      .08
6998.00
     8270.       0.    8270.       0.       0.    1137.       0.     433.     112.
 6998.00
       .71      .00     7.28      .00     .000     .080     .000     .000  6988.00
1102.86
   .021938     547.     547.     547.        5        0        0      .00   262.59
1365.45
0
 *SECNO 18.000

 3301 HV CHANGED MORE THAN HVINS

         BEAVER CREEK SOUTH FORK
    18.00     9.92  7011.92      .00      .00  7013.30     1.38    14.78      .17
7018.00
     6754.       0.    6754.       0.       0.     716.       0.     445.     115.
 7020.00
       .72      .00     9.43      .00     .000     .080     .000     .000  7002.00
1099.55
   .028896     598.     598.     598.        3        0        0      .00   136.51
1236.06
0
 *SECNO 19.000
    19.00     8.79  7034.79      .00      .00  7035.68      .89    22.33      .05
7034.00
```

```
    SECNO    DEPTH    CWSEL    CRIWS    WSELK    EG       HV       HL       OLOSS
BANK ELEV
    Q        QLOB     QCH      QROB     ALOB     ACH      AROB     VOL      TWA
LEFT/RIGHT
    TIME     VLOB     VCH      VROB     XNL      XNCH     XNR      WTN      ELMIN
   SSTA
    SLOPE    XLOBL    XLCH     XLOBR    ITRIAL   IDC      ICONT    CORAR    TOPWID
   ENDST


 *SECNO 20.000

 3301 HV CHANGED MORE THAN HVINS

     20.00     6.36  7054.36      .00      .00  7055.81     1.45    19.96      .17
7058.00
     6754.       0.    6754.       0.       0.     698.       0.     472.     121.
 7060.00
       .77      .00     9.67      .00     .000     .080     .000     .000  7048.00
1065.51
   .038415     625.     625.     625.        2        0        0      .00   160.28
1225.79
0
 *SECNO 21.000
     21.00     8.56  7080.56      .00      .00  7081.53      .97    25.68      .05
7080.00
     6754.       1.    6752.       1.       1.     854.       1.     487.     125.
 7080.00
       .80      .96     7.90      .96     .100     .080     .100     .000  7072.00
1061.22
   .022960     879.     879.     879.        5        0        0      .00   188.29
1249.51
0
 *SECNO 22.000

 3301 HV CHANGED MORE THAN HVINS


 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =   .65

     22.00     6.61  7098.61  7098.55      .00  7100.44     1.83    18.65      .26
7096.00
     6754.      55.    6570.     128.      14.     598.      31.     497.     127.
 7096.00
```

```
       .82     4.05    10.98     4.11     .100     .080     .100     .000  7092.00
1021.54
   .054047     554.     554.     554.        6       19        0      .00   181.31
1202.86
0
 *SECNO 23.000

 3302 WARNING:  CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE,  KRATIO =  1.42

     23.00     9.38  7117.38      .00      .00  7119.39     2.01    18.90      .05
7110.00
     6754.    1332.    5064.     358.     231.     398.      65.     505.     129.
 7110.00
       .83     5.76    12.71     5.49     .100     .080     .100     .000  7108.00
1056.30
   .026617     514.     514.     514.        4        0        0      .00   126.40
1182.70
0
1
    11/ 3/ 3      12:40:22
                                PAGE   12




 THIS RUN EXECUTED 11/ 3/ 3    12:40:22
 ************************************************
   HEC2 RELEASE DATED SEP 88 UPDATED APR  1989


   ERROR CORR -  01,02
   MODIFICATION -
 ************************************************


 NOTE- ASTERISK (*) AT LEFT OF CROSS-SECTION NUMBER INDICATES MESSAGE IN SUMMARY OF
ERRORS LIST


 100-YEAR FREQUENCY CROSS

 SUMMARY PRINTOUT TABLE  150


       SECNO     XLCH      ELTRD     ELLC      ELMIN       Q       CWSEL     CRIWS
    EG       10*KS      VCH      AREA      .01K

 *     60.000       .00       .00       .00   6718.00  20974.00   6733.36   6733.36
  6736.77    125.57     16.75   1701.40  1871.69

        1.000   1047.00       .00       .00   6732.00   6915.00   6743.87       .00
  6744.18     20.82      6.46   1946.76  1515.58

 *      2.000    759.00       .00       .00   6746.00   6915.00   6751.95   6751.95
  6753.89    197.70     13.09    709.71   491.80
```

```
 *      3.000    845.00       .00       .00   6772.00   5128.00   6774.75   6774.75
  6775.69     19.18      8.51    671.52  1171.06

 *      4.000    984.00       .00       .00   6784.00   6788.00   6786.82   6786.82
  6787.96     58.66      9.08    820.00   886.28

 *      5.000    722.00       .00       .00   6786.00   6788.00   6793.93       .00
  6795.16    203.65      9.25    771.30   475.67

 *      6.100   1160.00       .00       .00   6806.60   6154.00   6820.42   6820.42
  6827.40     42.32     21.20    290.26   946.04

 *      6.200     48.00   6828.00   6817.30   6807.30   6154.00   6825.81       .00
  6829.70     20.23     15.84    388.61  1368.18

 *      7.000    856.00       .00       .00   6854.00   6154.00   6857.79   6857.79
  6859.09    484.56      9.94    677.64   279.57

 *      8.000   1026.00       .00       .00   6889.00   6154.00   6890.86   6890.86
  6891.77     47.81      7.66    804.16   890.04

 *      9.000   2638.00       .00       .00   6890.00   8624.00   6896.25       .00
  6896.39     10.42      3.26   3157.00  2671.12

 *     10.000    590.00       .00       .00   6896.00   8624.00   6902.42   6902.42
  6903.79    207.23      9.76   1002.54   599.08

 *     11.000    701.00       .00       .00   6904.00   8624.00   6912.51       .00
  6913.11     91.30      6.30   1435.60   902.54

 *     12.000    643.00       .00       .00   6916.00   8624.00   6921.74       .00
  6922.57    270.02      6.08   1181.02   524.82

       13.000    689.00       .00       .00   6928.00   8624.00   6937.37       .00
  6938.49    197.89      8.55   1036.84   613.05

       14.000    834.00       .00       .00   6944.00   8624.00   6952.38       .00
  6953.10    155.30      6.85   1278.76   692.03

       15.000    764.00       .00       .00   6958.00   8624.00   6965.44       .00
  6966.26    191.28      7.60   1231.38   623.56

1
    11/ 3/ 3      12:40:22
                                PAGE   13

       SECNO     XLCH      ELTRD     ELLC      ELMIN       Q       CWSEL     CRIWS
    EG       10*KS      VCH      AREA      .01K

       16.000    718.00       .00       .00   6974.00   8624.00   6982.28   6981.98
  6983.91    317.27     10.55    940.80   484.16

       17.000    547.00       .00       .00   6988.00   8270.00   6997.53       .00
  6998.36    219.38      7.28   1136.59   558.36
```

	18.000	598.00	.00	.00	7002.00	6754.00	7011.92	.00	
7013.30	288.96	9.43	716.36	397.32					
	19.000	800.00	.00	.00	7026.00	6754.00	7034.79	.00	
7035.68	269.68	7.58	898.56	411.28					
	20.000	625.00	.00	.00	7048.00	6754.00	7054.36	.00	
7055.81	384.15	9.67	698.47	344.60					
	21.000	879.00	.00	.00	7072.00	6754.00	7080.56	.00	
7081.53	229.60	7.90	856.49	445.74					
*	22.000	554.00	.00	.00	7092.00	6754.00	7098.61	7098.55	
7100.44	540.47	10.98	643.15	290.52					
*	23.000	514.00	.00	.00	7108.00	6754.00	7117.38	.00	
7119.39	266.17	12.71	694.80	413.98					

100-YEAR FREQUENCY CROSS

SUMMARY PRINTOUT TABLE 150

	SECNO	Q	CWSEL	DIFWSP	DIFWSX	DIFKWS	TOPWID	XLCH
*	60.000	20974.00	6733.36	.00	.00	.16	258.76	.00
	1.000	6915.00	6743.87	.00	10.52	.00	392.81	1047.00
*	2.000	6915.00	6751.95	.00	8.08	.00	176.67	759.00
*	3.000	5128.00	6774.75	.00	22.79	.00	360.65	845.00
*	4.000	6788.00	6786.82	.00	12.07	.00	366.20	984.00
*	5.000	6788.00	6793.93	.00	7.11	.00	145.32	722.00
*	6.100	6154.00	6820.42	.00	26.49	.00	21.00	1160.00
*	6.200	6154.00	6825.81	.00	5.38	.00	21.00	48.00
*	7.000	6154.00	6857.79	.00	31.99	.00	263.57	856.00
*	8.000	6154.00	6890.86	.00	33.06	.00	445.42	1026.00
*	9.000	8624.00	6896.25	.00	5.39	.00	627.35	2638.00
*	10.000	8624.00	6902.42	.00	6.17	.00	375.72	590.00
*	11.000	8624.00	6912.51	.00	10.10	.00	249.98	701.00

*	12.000	8624.00	6921.74	.00	9.23	.00	242.34	643.00
	13.000	8624.00	6937.37	.00	15.63	.00	192.27	689.00
	14.000	8624.00	6952.38	.00	15.01	.00	255.99	834.00
	15.000	8624.00	6965.44	.00	13.06	.00	268.67	764.00
	16.000	8624.00	6982.28	.00	16.84	.00	278.30	718.00
	17.000	8270.00	6997.53	.00	15.26	.00	262.59	547.00
	18.000	6754.00	7011.92	.00	14.39	.00	136.51	598.00
	19.000	6754.00	7034.79	.00	22.87	.00	248.53	800.00
	20.000	6754.00	7054.36	.00	19.57	.00	160.28	625.00
	21.000	6754.00	7080.56	.00	26.21	.00	188.29	879.00
*	22.000	6754.00	7098.61	.00	18.05	.00	181.31	554.00

	SECNO	Q	CWSEL	DIFWSP	DIFWSX	DIFKWS	TOPWID	XLCH
*	23.000	6754.00	7117.38	.00	18.77	.00	126.40	514.00

SUMMARY OF ERRORS AND SPECIAL NOTES

CAUTION SECNO= 60.000 PROFILE= 1 CRITICAL DEPTH ASSUMED

CAUTION SECNO= 2.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2.000 PROFILE= 1 PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 2.000 PROFILE= 1 20 TRIALS ATTEMPTED TO BALANCE WSEL

CAUTION SECNO= 3.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3.000 PROFILE= 1 PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 3.000 PROFILE= 1 20 TRIALS ATTEMPTED TO BALANCE WSEL

CAUTION SECNO= 4.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4.000 PROFILE= 1 PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 4.000 PROFILE= 1 20 TRIALS ATTEMPTED TO BALANCE WSEL

```
WARNING SECNO=      5.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

CAUTION SECNO=      6.100  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=      6.100  PROFILE=  1  PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO=      6.100  PROFILE=  1  20 TRIALS ATTEMPTED TO BALANCE WSEL

CAUTION SECNO=      6.200  PROFILE=  1  HYDRAULIC JUMP D.S.
WARNING SECNO=      6.200  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

CAUTION SECNO=      7.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=      7.000  PROFILE=  1  PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO=      7.000  PROFILE=  1  20 TRIALS ATTEMPTED TO BALANCE WSEL

CAUTION SECNO=      8.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=      8.000  PROFILE=  1  PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO=      8.000  PROFILE=  1  20 TRIALS ATTEMPTED TO BALANCE WSEL

WARNING SECNO=      9.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

CAUTION SECNO=     10.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=     10.000  PROFILE=  1  PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO=     10.000  PROFILE=  1  20 TRIALS ATTEMPTED TO BALANCE WSEL

WARNING SECNO=     11.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

WARNING SECNO=     12.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

WARNING SECNO=     22.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

WARNING SECNO=     23.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE
```

NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The **community map repository** should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations** (BFEs) and/or **floodways** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of 0.0' North American Vertical Datum of 1988 (NAVD88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this jurisdiction.

The **projection** used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The **horizontal datum** was NAD83, GRS80 spheroid. Differences in datum, spheroid, projection or UTM zones zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the **North American Vertical Datum of 1988 (NAVD88)**. These flood elevations must be compared to structure and ground elevations referenced to the same **vertical datum**. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at http://www.ngs.noaa.gov/ or contact the National Geodetic Survey at the following address:

NGS Information Services
NOAA, N/NGS12
National Geodetic Survey
SSMC-3, #9202
1315 East-West Highway
Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242 or visit its website at http://www.ngs.noaa.gov/.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, City of Fountain, Bureau of Land Management, National Oceanic and Atmospheric Administration, United States Geological Survey, and Anderson Consulting Engineers, Inc. These data are current as of 2006.

This map reflects more detailed and up-to-date **stream channel configurations and floodplain delineations** than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables if applicable, in the FIS report. As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels; community map repository addresses; and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.

Contact **FEMA Map Service Center** (MSC) via the FEMA Map Information eXchange (FMIX) 1-877-336-2627 for information on available products associated with this FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-358-9620 and its website at http://www.msc.fema.gov/.

If you have **questions about this map** or questions concerning the National Flood Insurance Program in general, please call **1-877-FEMA MAP** (1-877-336-2627) or visit the FEMA website at http://www.fema.gov/business/nfip.

El Paso County Vertical Datum Offset Table

Flooding Source	Vertical Datum Offset (ft)

REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM BY STREAM VERTICAL DATUM CONVERSION INFORMATION

Panel Location Map



This Digital Flood Insurance Rate Map (DFIRM) was produced through a Cooperating Technical Partner (CTP) agreement between the State of Colorado Water Conservation Board (CWCB) and the Federal Emergency Management Agency (FEMA).

Additional Flood Hazard information and resources are available from local communities and the Colorado Water Conservation Board.



NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED WITHIN TOWNSHIP 11 SOUTH, RANGE 67 WEST, AND TOWNSHIP 12 SOUTH, RANGE 67 WEST.

LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

ZONE A No Base Flood Elevations determined.
ZONE AE Base Flood Elevations determined.
ZONE AH Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.
ZONE AO Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
ZONE AR Special Flood Hazard Area Formerly protected from the 1% annual chance flood by a flood control system that was subsequently decertified. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.
ZONE A99 Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
ZONE V Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.
ZONE VE Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.

FLOODWAY AREAS IN ZONE AE

The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.

OTHER FLOOD AREAS

ZONE X Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with drainage areas less than 1 square mile; and areas protected by levees from 1% annual chance flood.

OTHER AREAS

ZONE X Areas determined to be outside the 0.2% annual chance floodplain.
ZONE D Areas in which flood hazards are undetermined, but possible.

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS

OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

Floodplain boundary
Floodway boundary
Zone D Boundary
CBRS and OPA boundary
Boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths or flood velocities.
513 — Base Flood Elevation line and value; elevation in feet*
(EL 987) — Base Flood Elevation value where uniform within zone; elevation in feet*

* Referenced to the North American Vertical Datum of 1988 (NAVD 88)

A — A — Cross section line
23 — 23 — Transect line
97° 07' 30.00" / 32° 22' 30.00" — Geographic coordinates referenced to the North American Datum of 1983 (NAD 83)
4279000 N — 1000-meter Universal Transverse Mercator grid ticks, zone 13
6000000 FT — 5000-foot grid ticks: Colorado State Plane coordinate system, central zone (FIPSZONE 0502), Lambert Conformal Conic Projection
DX5510 — Bench mark (see explanation in Notes to Users section of this FIRM panel)
M1.5 — River Mile

MAP REPOSITORIES
Refer to Map Repositories list on Map Index

EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP
MARCH 17, 1997

EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL
DECEMBER 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

For community map revision history prior to countywide mapping, refer to the Community Map History Table located in the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

MAP SCALE 1" = 500'
250 0 500 1000 FEET
150 0 150 300 METERS

NFIP

PANEL 0267G

NATIONAL FLOOD INSURANCE PROGRAM

FIRM

FLOOD INSURANCE RATE MAP

EL PASO COUNTY, COLORADO AND INCORPORATED AREAS

PANEL 267 OF 1300

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
EL PASO COUNTY	080059	0267	G

Notice to User: The **Map Number** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.

MAP NUMBER 08041C0267G

MAP REVISED DECEMBER 7, 2018

Federal Emergency Management Agency

United States Department of Agriculture

NRCS

Natural Resources Conservation Service

A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for El Paso County Area, Colorado



December 27, 2022

Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface.....2
How Soil Surveys Are Made.....5
Soil Map.....8
Soil Map.....9
Legend.....10
Map Unit Legend.....11
Map Unit Descriptions.....11
El Paso County Area, Colorado.....13
38—Jarre-Tecolote complex, 8 to 65 percent slopes.....13
71—Pring coarse sandy loam, 3 to 8 percent slopes.....14
93—Tomah-Crowfoot complex, 8 to 15 percent slopes.....15
References.....18

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report
Soil Map



MAP LEGEND

Area of Interest (AOI)
- Area of Interest (AOI)

Soils
- Soil Map Unit Polygons
- Soil Map Unit Lines
- Soil Map Unit Points

Special Point Features
- Blowout
- Borrow Pit
- Clay Spot
- Closed Depression
- Gravel Pit
- Gravelly Spot
- Landfill
- Lava Flow
- Marsh or swamp
- Mine or Quarry
- Miscellaneous Water
- Perennial Water
- Rock Outcrop
- Saline Spot
- Sandy Spot
- Severely Eroded Spot
- Sinkhole
- Slide or Slip
- Sodic Spot
- Spoil Area
- Stony Spot
- Very Stony Spot
- Wet Spot
- Other
- Special Line Features

Water Features
- Streams and Canals

Transportation
- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

Background
- Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
Survey Area Data: Version 20, Sep 2, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 9, 2021—Jun 12, 2021

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
38	Jarre-Tecolote complex, 8 to 65 percent slopes	109.5	50.8%
71	Pring coarse sandy loam, 3 to 8 percent slopes	31.1	14.5%
93	Tomah-Crowfoot complex, 8 to 15 percent slopes	74.8	34.7%
Totals for Area of Interest		**215.4**	**100.0%**

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or

landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

El Paso County Area, Colorado

38—Jarre-Tecolote complex, 8 to 65 percent slopes

Map Unit Setting

National map unit symbol: 368c
Elevation: 6,700 to 7,500 feet
Frost-free period: 90 to 125 days
Farmland classification: Not prime farmland

Map Unit Composition

Jarre and similar soils: 40 percent
Tecolote and similar soils: 30 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Jarre

Setting

Landform: Alluvial fans
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium

Typical profile

A - 0 to 5 inches: gravelly sandy loam
Bt - 5 to 22 inches: gravelly sandy clay loam
2C - 22 to 60 inches: very gravelly sandy loam

Properties and qualities

Slope: 8 to 30 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 5.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: B
Ecological site: R048AY222CO - Loamy Park
Hydric soil rating: No

Description of Tecolote

Setting

Landform: Alluvial fans
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium

Typical profile

A - 0 to 3 inches: very stony loam
E - 3 to 12 inches: very gravelly loamy sand
Bt - 12 to 45 inches: extremely gravelly sandy clay loam
C - 45 to 60 inches: extremely gravelly loamy sand

Properties and qualities

Slope: 8 to 65 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.20 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Very low (about 2.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7e
Hydrologic Soil Group: B
Ecological site: R048AY255CO - Pine Grasslands
Hydric soil rating: No

Minor Components

Other soils

Percent of map unit:
Hydric soil rating: No

71—Pring coarse sandy loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 369k
Elevation: 6,800 to 7,600 feet
Farmland classification: Not prime farmland

Map Unit Composition

Pring and similar soils: 85 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Pring

Setting

Landform: Hills
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Linear

Parent material: Arkosic alluvium derived from sedimentary rock

Typical profile

A - 0 to 14 inches: coarse sandy loam
C - 14 to 60 inches: gravelly sandy loam

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: B
Ecological site: R048AY222CO - Loamy Park
Hydric soil rating: No

Minor Components

Pleasant

Percent of map unit:
Landform: Depressions
Hydric soil rating: Yes

Other soils

Percent of map unit:
Hydric soil rating: No

93—Tomah-Crowfoot complex, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 36bb
Elevation: 7,300 to 7,600 feet
Farmland classification: Not prime farmland

Map Unit Composition

Tomah and similar soils: 50 percent
Crowfoot and similar soils: 30 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Tomah

Setting

Landform: Hills, alluvial fans

Landform position (three-dimensional): Side slope, crest
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium derived from arkose and/or residuum weathered from arkose

Typical profile

A - 0 to 10 inches: loamy sand
E - 10 to 22 inches: coarse sand
Bt - 22 to 48 inches: stratified coarse sand to sandy clay loam
C - 48 to 60 inches: coarse sand

Properties and qualities

Slope: 8 to 15 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.60 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 4.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: B
Ecological site: R049XY216CO - Sandy Divide
Hydric soil rating: No

Description of Crowfoot

Setting

Landform: Hills, alluvial fans
Landform position (three-dimensional): Side slope, crest
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium

Typical profile

A - 0 to 12 inches: loamy sand
E - 12 to 23 inches: sand
Bt - 23 to 36 inches: sandy clay loam
C - 36 to 60 inches: coarse sand

Properties and qualities

Slope: 8 to 15 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.60 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 4.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: B
Ecological site: R049XY216CO - Sandy Divide
Hydric soil rating: No

Minor Components

Other soils

Percent of map unit:
Hydric soil rating: No

Pleasant

Percent of map unit:
Landform: Depressions
Hydric soil rating: Yes

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf


104° 53' 55" W
104° 52' 32" W
39° 3' 5" N
39° 2' 23" N
508900
509100
509300
509500
509700
509900
510100
510300
510500
510700
4322500
4322300
4322100
4321900
4321700
4321500
4321300
Hay Creek Rd
Hay Creek
Driveway
38
71
93
38
Soil Map may not be valid at this scale.
Map Scale: 1:9,090 if printed on A landscape (11" x 8.5") sheet.
N
Meters
0 100 200 400 600
Feet
0 400 800 1600 2400
Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 13N WGS84

MAP LEGEND

Area of Interest (AOI)

- Area of Interest (AOI)

Soils

Soil Rating Polygons

- A
- A/D
- B
- B/D
- C
- C/D
- D
- Not rated or not available

Soil Rating Lines

- A
- A/D
- B
- B/D
- C
- C/D
- D
- Not rated or not available

Soil Rating Points

- A
- A/D
- B
- B/D
- C
- C/D
- D
- Not rated or not available

Water Features

- Streams and Canals

Transportation

- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

Background

- Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
Survey Area Data: Version 20, Sep 2, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 9, 2021—Jun 12, 2021

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
38	Jarre-Tecolote complex, 8 to 65 percent slopes	B	109.5	50.8%
71	Pring coarse sandy loam, 3 to 8 percent slopes	B	31.1	14.5%
93	Tomah-Crowfoot complex, 8 to 15 percent slopes	B	74.8	34.7%
Totals for Area of Interest			**215.4**	**100.0%**

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

APPENDIX D

MAPS



VICINITY MAP
HAY CREEK VALLEY
(NTS)



LEGEND

- BASIN BOUNDARY
- EXISTING PROPERTY LINE
- EXISTING CONTOUR
- FLOW DIRECTION
- 2 — DESIGN POINT
- EX-2 — SUB BASIN DESIGNATION
- #### — 5-YEAR STORM EVENT PEAK FLOW (CFS)
- #.# — 100-YEAR STORM EVENT PEAK FLOW (CFS)
- #.# — SUB BASIN AREA (AC.)

N

GRAPHIC SCALE

200' 0' 200' 400'

(IN FEET)
1 inch = 200 ft.

Hay Creek

Existing Conditions
Sub-basin Summary

Basin	Area	Q5	Q100
	acres	cfs	cfs
EX-OS1a	9.4	0.8	4.1
EX-OS1b	59.2	2.6	15.7
EX-OS2a	15.9	1.5	8.0
EX-OS2b	2.8	0.3	1.4
EX-OS2c	3.2	0.3	1.6
EX-OS3	8.1	0.2	2.0
EX-OS4	0.7	1.9	3.9
EX-1	56.0	1.6	9.9
EX-2	48.2	2.0	11.2
EX-3	61.6	2.3	14.7
EX-4	5.9	2.3	15.6
EX-5	42.8	1.5	10.0

Existing Design Point Summary

Hay Creek

Design Point	Sub-Basins	Total Area (ac.)	Q(5) (cfs)	Q(100) (cfs)
1	EX-OS1a	9.35	0.80	4.10
2	EX-OS1b	59.21	2.60	15.70
3	EX-OS2a	15.90	1.50	8.00
4	EX-OS2b	2.77	0.30	1.40
5	EX-OS2c	3.17	0.30	1.60
6	EX-OS3	8.15	0.20	2.00
7	EX-4	5.88	2.30	15.60
8	EX-OS1b, EX-OS2a, EX-2	123.33	5.40	30.90
9	EX-OS2b, EX-OS2c, EX-3	67.57	2.90	17.40
10	EX-OS3, EX-5	50.97	1.80	11.90
11	DP-8, DP-9, DP-10, EX-OS1a, EX-1	307.27	11.20	69.90
HC	From PPRBD Regional floodplane Administrator			127.00

EL PASO COUNTY

HAY CREEK
FINAL DRAINAGE REPORT

OFFSITE DRAINAGE BASINS

DESIGNED BY: WCG
DRAWN BY: WCG
CHECKED BY: JTS

SCALE: HORIZ. / VERT.

DATE ISSUED: DECEMBER 2023

SHEET: 1 OF 4

DRAWING No. DR01

PRELIMINARY
THESE PLANS ARE NOT FOR CONSTRUCTION. THEY ARE APPROVED BY GOVERNING AGENCIES AND IS SUBJECT TO CHANGE

SEAL

FOR AND ON BEHALF OF MATRIX DESIGN GROUP, INC.
PROJECT No. 22.886.076

PREPARED BY: Matrix Excellence by Design

SHEET KEY

REFERENCE DRAWINGS

No.	DATE	DESCRIPTION	BY
####	####	####	####

REVISIONS

COMPUTER FILE MANAGEMENT
FILE NAME: S:\22.886.076 Hay Creek-Forest Manor-O'Leary Properties\200 Design\220 Drainage-WR2222 Reports\FDR\DWG\DR01 - HAY CREEK.dwg
CREATE:
PLOT DATE: November 30, 2023 2:58:02 PM
THIS DRAWING IS CURRENT AS OF PLOT DATE AND MAY BE SUBJECT TO CHANGE



LEGEND

- BASIN BOUNDARY
- EXISTING CONTOUR
- FLOW DIRECTION
- 2 — DESIGN POINT
- EX-2 — SUB BASIN DESIGNATION
- #### — 5-YEAR STORM EVENT PEAK FLOW (CFS)
- #### — 100-YEAR STORM EVENT PEAK FLOW (CFS)
- SUB BASIN AREA (AC.)

N

GRAPHIC SCALE

200' 0' 200' 400'

(IN FEET)
1 inch = 200 ft.

Hay Creek
Existing Conditions
Sub-basin Summary

Basin	Area	Q5	Q100
	acres	cfs	cfs
EX-OS1a	9.4	0.8	4.1
EX-OS1b	59.2	2.6	15.7
EX-OS2a	15.9	1.5	8.0
EX-OS2b	2.8	0.3	1.4
EX-OS2c	3.2	0.3	1.6
EX-OS3	8.1	0.2	2.0
EX-OS4	0.7	1.9	3.9
EX-1	56.0	1.6	9.9
EX-2	48.2	2.0	11.2
EX-3	61.6	2.3	14.7
EX-4	5.9	2.3	15.6
EX-5	42.8	1.5	10.0

Existing Design Point Summary

Hay Creek

Design Point	Sub-Basins	Total Area (ac.)	Q(5) (cfs)	Q(100) (cfs)
1	EX-OS1a	9.35	0.80	4.10
2	EX-OS1b	59.21	2.60	15.70
3	EX-OS2a	15.90	1.50	8.00
4	EX-OS2b	2.77	0.30	1.40
5	EX-OS2c	3.17	0.30	1.60
6	EX-OS3	8.15	0.20	2.00
7	EX-4	5.88	2.30	15.60
8	EX-OS1b, EX-OS2a, EX-2	123.33	5.40	30.90
9	EX-OS2b, EX-OS2c, EX-3	67.57	2.90	17.40
10	EX-OS3, EX-5	50.97	1.80	11.90
11	DP-8, DP-9, DP-10, EX-OS1a, EX-1	307.27	11.20	69.90
HC	From PPRBD Regional floodplane Administrator			127.00

EL PASO COUNTY
HAY CREEK
FINAL DRAINAGE REPORT
PRE DEVELOPMENT DRAINAGE CONDITIONS

DESIGNED BY: WCG
DRAWN BY: WCG
CHECKED BY: JTS
SCALE: HORIZ. / VERT.
DATE ISSUED: DECEMBER 2023
SHEET: 2 OF 4
DRAWING No. DR02

SEAL

PRELIMINARY
THESE PLANS ARE NOT RELEASED FOR PERMITTING BY GOVERNING AGENCIES AND IS SUBJECT TO CHANGE

FOR AND ON BEHALF OF MATRIX DESIGN GROUP, INC.
PROJECT No. 22.886.076

PREPARED BY: Matrix Excellence by Design

SHEET KEY

No.	DATE	DESCRIPTION	BY
####	####	REVISIONS	####

REFERENCE DRAWINGS

COMPUTER FILE MANAGEMENT
FILE NAME: S:\22.886.076 Hay Creek-Forest Manor-O'Leary Properties\200 Design\220 Drainage-WR\222 Reports\FDR\DWG\DR01 - HAY CREEK.dwg
CP: ####
PLOT DATE: November 30, 2023 2:59:33 PM
THIS DRAWING IS CURRENT AS OF PLOT DATE AND MAY BE SUBJECT TO CHANGE



LEGEND

- PR BASIN BOUNDARY
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM DRAIN PIPE
- EXISTING EDGE OF ROAD
- PROPOSED PROPERTY LINE
- PROPOSED SETBACK
- PROPOSED FLOW DIRECTION
- 2 — DESIGN POINT
- PROPOSED MAINTENANCE ACCESS ROAD
- PROPOSED RIP RAP
- EMERGENCY FLOW PATHS
- BASIN (Q5 / Q100 / AREA) — SUB BASIN DESIGNATION
  - 5-YEAR STORM EVENT PEAK FLOW (CFS)
  - 100-YEAR STORM EVENT PEAK FLOW (CFS)
  - SUB BASIN AREA (AC.)

N

GRAPHIC SCALE

200' 0' 200' 400'

(IN FEET)
1 inch = 200 ft.

Hay Creek

Proposed Conditions
Sub-basin Summary

Basin	Area	Q5	Q100
	acres	cfs	cfs
OS1a	9.4	0.8	3.6
OS1b	59.2	2.6	14.2
OS2a	5.0	0.4	1.8
OS2b	4.7	0.4	2.0
OS2c	6.1	0.8	2.7
OS2d	2.8	0.3	1.1
OS2e	3.2	0.3	1.3
OS3a	4.9	0.1	0.9
OS3b	3.3	0.1	0.8
OS4	0.7	1.9	3.9
PR-1a	12.9	0.9	4.3
PR-1b	6.3	0.5	2.5
PR-1c	53.2	3.4	15.7
PR-2	7.8	0.7	3.3
PR-3	18.4	0.7	3.3
PR-4	14.2	1.2	5.6
PR-5	16.9	1.3	6.1
PR-6	13.9	1.1	5.0
PR-7	27.8	2.3	10.6
PR-8	5.9	3.1	17.0
PR-9	13.4	1.1	5.1
PR-10a	4.7	3.3	7.8
PR-10b	0.4	0.8	1.7
PR-11	2.4	0.0	0.0
PR-12	16.4	0.6	3.4

Proposed Design Point Summary - Central Basin

Hay Creek

Design Point	Sub-Basins	Total Area (ac.)	Q(5) (cfs)	Q(100) (cfs)
1	OS1a	9.35	0.80	3.60
2	OS1b	59.21	2.60	14.20
3	OS2a	5.01	0.40	1.80
4	OS2b	4.74	0.40	2.00
5	OS2c	6.11	0.80	2.70
6	OS2d	2.77	0.30	1.10
8	OS3a	4.88	0.10	0.90
9	OS3b	3.29	0.10	0.80
10	PR-8	5.86	3.11	17.01
11	OS1b, OS2a, PR-1a	77.15	3.70	19.50
12a	OS1a,PR-1b	15.63	1.30	6.10
12b	OS1a, OS2a, OS1b, PR-1a, PR-1b	92.78	5.00	25.20
13	OS2b, PR-2	12.51	1.10	5.30
14	OS2c, PR-3	24.55	1.40	5.50
15	OS2d, PR-4	16.96	1.50	6.60
16	OS2e, PR-5	20.09	1.60	7.20
17	PR-6	13.87	1.10	5.00
20	PR-1c, DP-12b, DP-13, DP-14, DP-15, DP-16, DP-17	233.97	9.50	43.00
21a	PR-10a	4.73	3.30	7.80
21b	PR-7, PR-10a	32.49	5.30	17.90
EDB-IN	PR-7, PR-10a, PR-10b, PR-11	35.31	4.90	16.50
EDB-OUT	PR-7, PR-10a, PR-10b, PR-11	35.31	4.00	15.90
22	EDB-OUT, DP-18, DP-19	283.15	10.90	49.10
23	DP-9, DP-21, PR-12	302.82	11.50	53.00
HC	From PPRBD Regional floodplane Administrator			127.00

EL PASO COUNTY

HAY CREEK
FINAL DRAINAGE REPORT

POST DEVELOPMENT DRAINAGE CONDITIONS

DESIGNED BY: WCG
DRAWN BY: WCG
CHECKED BY: JTB

SCALE: HORIZ. / VERT.

DATE ISSUED: DECEMBER 2023

SHEET 3 OF 4

DRAWING No. DR03

SEAL

PRELIMINARY
THESE PLANS ARE NOT APPROVED FOR GOVERNING AGENCIES AND IS SUBJECT TO CHANGE

FOR AND ON BEHALF OF MATRIX DESIGN GROUP, INC.
PROJECT No. 22.886.076

PREPARED BY: Matrix Excellence by Design

SHEET KEY

REFERENCE DRAWINGS

REVISIONS

No.	DATE	DESCRIPTION	BY

COMPUTER FILE MANAGEMENT
FILE NAME: S:\22.886.076 Hay Creek-Forest Manor-OLeary Properties\200 Design\220 Drainage-WR\222 Reports\FDR\DWG\DR02 - HAY CREEK.dwg
PLOT FILE:
PLOT DATE: December 5, 2023 9:53:08 AM
THIS DRAWING IS CURRENT AS OF PLOT DATE AND MAY BE SUBJECT TO CHANGE







LEGEND

- PR BASIN BOUNDARY
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM DRAIN PIPE
- EXISTING EDGE OF ROAD
- PROPOSED SETBACK
- PROPOSED PROPERTY LINE
- PROPOSED FLOW DIRECTION
- 2 — DESIGN POINT
- PROPOSED MAINTENANCE ACCESS ROAD
- PROPOSED RIP RAP
- DISTURBED AREA
- UNDISTURBED AREA
- RECEIVING PERVIOUS AREA
- UNCONNECTED IMPERVIOUS AREA
- EMERGENCY FLOW PATHS
- BASIN / Q5 / Q100 / AREA — SUB BASIN DESIGNATION
- 5-YEAR STORM EVENT PEAK FLOW (CFS)
- 100-YEAR STORM EVENT PEAK FLOW (CFS)
- SUB BASIN AREA (AC.)

Hay Creek Disturbed Area							
Basin ID	Total Area (ac)	Total Proposed Disturbed Area (ac)	Disturbed Area Tributary to Pond 1 (ac)	Disturbed Area Located within a large lot residential site (Excel. I.7.1.C.1.a) (ac)	Impervious areas which are not practicable to detain (Excel. I.7.1.C.1.a) (ac)	Impervious areas to receive water quality treatment via Runoff Reduction (ac)	Total Area Receiving Water Quality Treatment (ac)
OS4	0.70	0.47	0.00	0.00	0.47	0.47	0.47
PR-1a	12.94	0.11	0.00	0.11	0.00	0.00	0.00
PR-1b	6.28	0.17	0.00	0.17	0.00	0.00	0.00
PR-1c	53.22	3.4	0.00	3.4	0.00	0.00	0.00
PR-2	7.77	0.82	0.00	0.82	0.00	0.00	0.00
PR-3	18.44	0.73	0.00	0.73	0.00	0.00	0.00
PR-4	14.19	0.54	0.00	0.54	0.00	0.00	0.00
PR-5	16.92	0.36	0.00	0.36	0.00	0.00	0.00
PR-6	13.87	0.53	0.000	0.53	0.00	0.00	0.00
PR-7	27.76	0.17	0.17	0.00	0.00	0.00	0.17
PR-8	5.86	0.00	0.00	0.00	0.00	0.00	0.00
PR-9	13.43	0.76	0.00	0.76	0.00	0.00	0.00
PR-10a	4.73	4.73	4.73	0.00	0.00	0.00	4.73
PR-10b	0.41	0.41	0.41	0.00	0.00	0.00	0.41
PR-11	2.41	2.41	2.41	0.00	0.00	0.00	2.41
PR-12	16.38	0.85	0.00	0.00	0.85	0.85	0.85
Total	215.30	16.46	7.72	7.42	1.32	1.32	9.04

NOTE: FUTURE RESIDENTIAL CONSTRUCTION FALLS UNDER THE LARGE LOT EXCLUSION FROM WQ TREATMENT, HOWEVER MUCH, IF NOT ALL, OF THE IMPROVEMENTS ASSOCIATED WITH THE RESIDENCES WILL DRAIN ACROSS VEGETATED AREAS AND UNDER THE RUNOFF REDUCTION METHODOLOGY WILL HAVE THE REQUIRED WQ TREATMENT VOLUME REDUCED TO ZERO.

EL PASO COUNTY
HAY CREEK
FINAL DRAINAGE REPORT

POST DEVELOPMENT DISTURBED AREAS

DESIGNED BY: WCD
DRAWN BY: WCD
CHECKED BY: JTS
SCALE: HORIZ. / VERT.
DATE ISSUED: DECEMBER 2023
SHEET 4 OF 4
DRAWING No. DR04

SEAL

PRELIMINARY
THESE DRAWINGS ARE NOT RELEASED FOR GOVERNING AGENCIES AND IS SUBJECT TO CHANGE

FOR AND ON BEHALF OF MATRIX DESIGN GROUP, INC.
PROJECT No. 22.886.076

PREPARED BY: Matrix Excellence by Design

SHEET KEY

REFERENCE DRAWINGS

No.	DATE	DESCRIPTION	BY
		REVISIONS	

COMPUTER FILE MANAGEMENT
FILE NAME: S:\22.886.076 Hay Creek-Forest Manor-O'Leary Properties\200 Design\220 Drainage-WR\222 Reports\FDR\DWG\DR02 - HAY CREEK.dwg
PLOT DATE: December 5, 2023 9:53:59 AM
THIS DRAWING IS CURRENT AS OF PLOT DATE AND MAY BE SUBJECT TO CHANGE.