

Traffic Impact Study

Monument Hill

El Paso County, Colorado

Prepared for:

The Garrett Companies

Kimley»Horn

T R A F F I C I M P A C T S T U D Y

Traffic Engineer's Statement

The attached traffic report and supporting information were prepared under my responsible charge and they comport with the standard of care. So far as is consistent with the standard of care, said report was prepared in general conformance with the criteria established by the County for traffic reports.



Curtis D. Rowe, P.E., PTOE PE #36355

October 24, 2022

Date

Developer's Statement

I, the Developer, have read and will comply with all commitments made on my behalf within this report.

Mr. Karl Stout
The Garrett Companies, Inc.
1051 Greenwood Springs Boulevard
Suite 101
Greenwood, Indiana 46143

Date

Monument Hill

El Paso County, Colorado

Prepared for
The Garrett Companies
1051 Greenwood Springs Boulevard
Suite 101
Greenwood, Indiana

Prepared by
Kimley-Horn and Associates, Inc.
2 North Nevada Avenue
Suite 300
Colorado Springs, Colorado 80903
(719) 453-0180

October 2022



This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

TABLE OF CONTENTS

TABLE OF CONTENTS	i
LIST OF TABLES	ii
LIST OF FIGURES	iii
1.0 EXECUTIVE SUMMARY	1
2.0 INTRODUCTION.....	3
3.0 EXISTING AND FUTURE CONDITIONS	6
3.1 Existing Study Area	6
3.2 Existing Roadway Network	6
3.3 Existing Traffic Volumes	16
3.4 Unspecified Development Traffic Growth.....	16
4.0 PROJECT TRAFFIC CHARACTERISTICS.....	20
4.1 Trip Generation.....	20
4.2 Trip Distribution	21
4.3 Traffic Assignment.....	21
4.4 Total (Background Plus Project) Traffic.....	21
5.0 TRAFFIC OPERATIONS ANALYSIS	26
5.1 Analysis Methodology.....	26
5.2 Key Intersection Operational Analysis	27
5.3 CDOT Analysis.....	39
5.4 El Paso County Turn Lane Requirement Analysis	39
5.5 Vehicle Queuing Analysis	41
5.6 Access Spacing Requirements and Roadway Classifications	41
5.7 Sight Distance Evaluation.....	44
5.8 Bicycle and Pedestrian Access.....	45
5.9 Road Impact Fees	45
5.10 Improvement Summary	45
6.0 CONCLUSIONS AND RECOMMENDATIONS	48

APPENDICES

- Appendix A – Intersection Count Sheets
- Appendix B – Future Traffic Projections and Relevant Adjacent Studies
- Appendix C – Trip Generation Worksheets
- Appendix D – Intersection Analysis Worksheets
- Appendix E – Queue Analysis Worksheets
- Appendix F – Signal Warrant Analysis Worksheets
- Appendix G – Conceptual Site Plan

LIST OF TABLES

Table 1 – Monument Hill Traffic Generation	20
Table 2 – Level of Service Definitions	26
Table 3 – Palmer Divide Road & Monument Hill Road LOS Results	28
Table 4 – Misty Acres Boulevard & Monument Hill Road LOS Results.....	30
Table 5 – Deer Creek Road & Monument Hill Road LOS Results	31
Table 6 – Deer Creek Road and Base Camp Road LOS Results	32
Table 7 – Deer Creek Road & Woodmoor Drive LOS Results	33
Table 8 – Monument Hill Road & Woodmoor Drive LOS Results	36
Table 9 – SH-105 & Woodmoor Drive LOS Results	37
Table 10 – Project Access Level of Service Results.....	38
Table 11 – Turn Lane Queuing Analysis Results.....	41
Table 12 – Road Impact Fees	45
Table 13 – Summary of Recommended Improvements.....	51

LIST OF FIGURES

Figure 1 – Vicinity Map.....	5
Figure 2 – Existing Geometry and Control.....	15
Figure 3 – 2022 Existing Traffic Volumes	17
Figure 4 – 2025 Background Traffic Volumes.....	18
Figure 5 – 2045 Background Traffic Volumes.....	19
Figure 6 – Project Trip Distribution	22
Figure 7 – Project Traffic Assignment	23
Figure 8 – 2025 Total Traffic Volumes	24
Figure 9 – 2045 Total Traffic Volumes	25
Figure 10 – Roadway Classification Map	43
Figure 11 – 2025 Recommended Geometry and Control	46
Figure 12 – 2045 Recommended Geometry and Control	47

1.0 EXECUTIVE SUMMARY

Monument Hill is proposed to be located at 18950 Base Camp Road in El Paso County, Colorado. The project is proposed to include approximately 264 multifamily dwelling units. It is expected that Monument Hill will be completed in the next several years. Therefore, analysis was conducted for the 2025 short-term buildout horizon as well as the 2045 long-term twenty-year planning horizon.

The purpose of this traffic study is to identify project traffic generation characteristics to determine potential project traffic related impacts on the local street system and to develop the necessary mitigation measures required for the identified traffic impacts. The following intersections were incorporated into this traffic study per El Paso County and CDOT standards and requirements:

- Palmer Divide Road and Monument Hill Road (Intersection #1)
- Misty Acres Boulevard and Monument Hill Road (#2)
- Deer Creek Road and Monument Hill Road (#3)
- Deer Creek Road and Base Camp Road (#4)
- Deer Creek Road and Woodmoor Drive (#5)
- Monument Hill Road and Woodmoor Drive (#6)
- State Highway 105 (SH-105) and Woodmoor Drive (#7)
- Monument Hill Road Southern Right-In/Right-Out Movement Access (#8)
- Monument Hill Road Northern Full Movement Access (#9)
- Base Camp Road Full Movement Access (#10)

Regional access to Monument Hill will be provided by Interstate 25 (I-25) and SH-105. Primary access will be provided by Woodmoor Drive and Monument Hill Road. Direct access will be provided by a proposed northern full movement access located approximately 800 feet south of the Palmer Ridge High School bus loop access (measured right-of-way to center) and a southern right-in/right-out access located approximately 800 feet south of the full movement access (measured center to center). Likewise, access to the development will be available at the northern cul-de-sac terminus of Base Camp Road. Traffic using this access will arrive and depart Base Camp Road at the Deer Creek Road (#4) intersection.

Monument Hill is expected to generate approximately 1,768 weekday daily trips, with 106 of these trips occurring during the morning peak hour and 136 of these trips occurring during the afternoon peak hour. The trip generation calculation worksheets are included in **Appendix C**. These trips were added to the background traffic volumes in the 2025 and 2045 horizon analysis years to develop future total traffic volume projections. The background traffic volumes used in this study include traffic anticipated to be generated by the adjacent North Bay at Woodmoor and the Waterside developments which were analyzed in Traffic Impact Studies completed by LSC Transportation Consultants in May and June of 2022, respectively. Additionally, a summary of the Lewis Palmer Trail Safe Routes to School plans within and nearby the study area is included in this traffic study.

2.0 INTRODUCTION

Kimley-Horn and Associates, Inc. has prepared this report to document the results of a Traffic Impact Study for the Monument Hill residential project proposed to be located at 18950 Base Camp Road in El Paso County, Colorado. A vicinity map illustrating the Monument Hill development location is shown in **Figure 1**. For the purposes of this study, Monument Hill is anticipated to include approximately 264 multifamily dwelling units. A conceptual site plan is attached in **Appendix G**. It is expected that Monument Hill will be completed within the next several years; therefore, analysis was conducted for the 2025 short-term buildout horizon as well as the 2045 long-term twenty-year planning horizon.

The purpose of this traffic study is to identify project traffic generation characteristics to determine potential project traffic related impacts on the local street system and to develop the necessary mitigation measures required for the identified traffic impacts. The following intersections were evaluated in this traffic study per El Paso County and CDOT standards and requirements:

- Palmer Divide Road and Monument Hill Road (Intersection #1)
- Misty Acres Boulevard and Monument Hill Road (#2)
- Deer Creek Road and Monument Hill Road (#3)
- Deer Creek Road and Base Camp Road (#4)
- Deer Creek Road and Woodmoor Drive (#5)
- Monument Hill Road and Woodmoor Drive (#6)
- State Highway 105 (SH-105) and Woodmoor Drive (#7)
- Monument Hill Road Southern Right-In/Right-Out Movement Access (#8)
- Monument Hill Road Northern Full Movement Access (#9)
- Base Camp Road Full Movement Access (#10)

Regional access to Monument Hill will be provided by Interstate 25 (I-25) and SH-105. Primary access will be provided by Woodmoor Drive and Monument Hill Road. Direct access will be provided by a proposed northern full movement access (#9) located approximately 800 feet south of the Palmer Ridge High School bus loop access (measured right-of-way to center) and a southern right-in/right-out access (#8) located approximately 800 feet south of the full movement access (measured center to center). Likewise, access to the development will be available at the northern cul-de-sac terminus of Base Camp Road (#10). Traffic using this access is not anticipated to experience measurable delay, and vehicles from this access will arrive and depart Base Camp Road at the Deer Creek Road (#4) intersection.




FIGURE 1
MONUMENT HILL
EL PASO COUNTY, COLORADO
VICINITY MAP

3.0 EXISTING AND FUTURE CONDITIONS

3.1 Existing Study Area

The existing site is comprised of vacant land. Directly east of the development is Palmer Ridge High School and directly west is Interstate 25 (I-25). Extending to the east and north are single family residential homes and to the south are mixed use industrial and retail uses.

3.2 Existing Roadway Network

Palmer Divide Road provides one through lane of travel in each direction, eastbound and westbound, with posted speed limit of 45 miles per hour. This roadway is classified by El Paso County as a two-lane non-residential collector.

Monument Hill Road extends in the north/south direction as a two-lane roadway. The posted speed limit along Monument Hill Road is 35 miles per hour to the north of Misty Acres Boulevard and increases to 45 miles per hour to the south of Misty Acres Boulevard. This roadway is classified by El Paso County as a two-lane non-residential collector. Though not included in the study area or analyzed in this study, Beacon Lite Road is also a collector that travels in the north/south direction that some may use for north/south travel if Monument Hill Road experiences delay.

Misty Acres Boulevard is a two-lane roadway with one through lane in the northbound and southbound direction and a raised median separating each direction throughout most of the roadway. A posted speed limit could not be determined from Google Street View. This roadway is classified by El Paso County as a two-lane residential collector.

Deer Creek Road is a two-lane roadway with one through lane in the eastbound and westbound direction with a 35 mile per hour speed limit through the study area. This roadway is classified by El Paso County as a two-lane local road.

Base Camp Road extends in the northbound and southbound direction with one through lane each way. A posted speed limit could not be determined from Google Street View. Base Camp Road terminates as a cul-de-sac approximately 700 feet north of the Deer Creek Road intersection. This roadway is classified by El Paso County as a two-lane local road.

Woodmoor Drive is a two-lane roadway with one through lane in the north/south direction. The posted speed limit is 30 miles per hour that reduces to 20 miles per hour near the Lewis Palmer Middle School during school arrival and departure times. This roadway is classified by El Paso County as a two-lane residential collector.

Although SH-105 is a north/south state highway, within the study area it extends east/west with two through lanes in each direction through the Woodmoor Drive study intersection. For purposes of this analysis, SH-105 will be referred to in the eastbound/westbound directions. The posted speed limit near the study intersection is 35 miles per hour. The Colorado Department of Transportation classifies this roadway as a Non-Rural Principal Highway (NR-A).

Based on the El Paso County Major Transportation Corridor Study (MTCP) 2040 Roadway Plan, the collectors of Palmer Divide Road, Monument Hill Road, and Misty Acres Boulevard are anticipated to primarily provide one through lane in each direction through this horizon. SH-105 has a proposed roadway improvement project in the long-range horizon to increase from one through lane in each direction to two through lanes in each direction to the east of the I-25 interchange with SH-105, from Knollwood Boulevard to SH-83. When constructed, this improvement to SH-105 will allow for additional capacity along SH-105 to accommodate additional growth occurring in this area of El Paso County.

The unsignalized intersection of Palmer Divide Road and Monument Hill Road (#1) operates with stop control on the northbound and southbound approaches of Monument Hill Road. All four approaches provide a single lane for shared movements. An aerial photo of the existing intersection configuration is below (north is up - typical).



Palmer Divide Road & Monument Hill Road (#1)

The unsignalized 'T'-intersection of Misty Acres Boulevard and Monument Hill Road (#2) operates with stop control on the westbound approach of Misty Acres Boulevard. The northbound approach of Monument Hill Road provides a through lane and a separate right turn lane while the southbound approach provides a separate left turn lane and a through lane. The westbound approach provides a separate left and right turn lane. An aerial photo of the existing intersection configuration is below.



Misty Acres Boulevard & Monument Hill Road (#2)

The unsignalized 'T'-intersection of Deer Creek Road and Monument Hill Road (#3) operates with stop control on the westbound approach of Deer Creek Road. The northbound approach of Monument Hill Road provides a through lane and a separate right turn lane while the southbound approach provides a separate left turn lane and a through lane. The westbound approach provides a separate left and right turn lane. An aerial photo of the existing intersection configuration is below.



Deer Creek Road & Monument Hill Road (#3)

The Deer Creek Road and Base Camp Road (#4) 'T'-intersection operates with stop control on the southbound approach of Base Camp Road. All three approaches provide a single lane shared with all movements. An aerial photo of the existing intersection configuration is below.



Deer Creek Road & Base Camp Road (#4)

The unsignalized intersection of Deer Creek Road and Woodmoor Drive (#5) operates with stop control on the eastbound and westbound approach of Deer Creek Road. All four approaches provide a single lane shared with all movements. An aerial photo of the existing intersection configuration is below.



Deer Creek Road & Woodmoor Drive (#5)

The Monument Hill Road and Woodmoor Drive (#6) unsignalized intersection operates with stop control on the eastbound and westbound approach of Monument Hill Road. The northbound and southbound approaches of Woodmoor Drive provide a left turn lane and a shared through/right turn lane. The eastbound approach of Monument Hill Road provides a separate shared left turn/through lane and a channelized right turn lane. The westbound approach provides a single lane shared with all movements. Of note, the east and west legs of Monument Hill Road at this intersection are currently offset from each other by approximately 25 feet. An aerial photo of the existing intersection configuration is below.



Monument Hill Road & Woodmoor Drive (#6)

The signalized T-intersection of SH-105 and Woodmoor Drive (#7) operates with protected only left turn phasing on the eastbound approach of SH-105. The southbound approach provides dual left turn lanes and a separate right turn lane. The eastbound approach of SH-105 provides dual left turn lanes and two through lanes while the westbound approach provides two through lanes and a separate right turn lane. An aerial photo of the existing intersection configuration is below.



SH-105 & Woodmoor Drive (#7)

The intersection lane configuration and control for the study area intersections are shown in **Figure 2**.







FIGURE 2
MONUMENT HILL
 EL PASO COUNTY, COLORADO
 EXISTING GEOMETRY AND CONTROL



3.3 Existing Traffic Volumes

Existing turning movement counts were conducted at the study intersections Wednesday, September 7, 2022 during the morning and afternoon peak hours. Of note, the nearby schools of Palmer Ridge High School, Lewis-Palmer Middle School, and Lewis-Palmer Elementary School were all in session when these traffic counts were collected. The counts were conducted during the morning and afternoon peak hours of adjacent street traffic in 15-minute intervals from 7:00 AM to 9:00 AM and 2:30 PM to 6:00 PM on these count dates—of note, the counts conducted during these peak periods include the arrival and dismissal times of each of the previously mentioned schools in the study area. The existing intersection traffic volumes are shown in **Figure 3** with count sheets provided in **Appendix A**.

3.4 Unspecified Development Traffic Growth

According to information provided on the website for the Colorado Department of Transportation (CDOT), the 20-year growth factor along SH-105 in the vicinity of the site is 1.39. This 20-year growth factor equates to annual growth rate of 1.66 percent. Therefore, a 1.66 percent annual growth rate was used to estimate the short-term 2025 and long-term 2045 traffic volume projections along SH-105. Likewise, Palmer Divide Road is a corridor similar in nature to SH-105 for growth potential; therefore, a 1.66 percent annual growth was also used to estimate 2025 and 2045 traffic volumes. However, the area surrounding the intersections along Monument Hill Road, Deer Creek Road, Woodmoor Drive, and Misty Acres Boulevard are primarily built out. To provide a conservative analysis along these roadways, a 1.0 percent annual growth rate was applied at these intersections. Traffic information from the CDOT Online Transportation Information System (OTIS) website is included in **Appendix B**.

In addition, the volume associated with the known nearby proposed developments of Waterside and North Bay at Woodmoor were included in the background traffic volumes during both the 2025 and 2045 horizons. The applicable documents from the Waterside Traffic Impact Study and the North Bay at Woodmoor Traffic Impact Study prepared in May and June of 2022 are also included in **Appendix B**. Background traffic volumes for 2025 and 2045 are shown in **Figures 4** and **5**, respectively.







FIGURE 3
MONUMENT HILL
EL PASO COUNTY, COLORADO
2022 EXISTING TRAFFIC VOLUMES









FIGURE 4
MONUMENT HILL
EL PASO COUNTY, COLORADO
2025 BACKGROUND TRAFFIC VOLUMES







FIGURE 5
MONUMENT HILL
EL PASO COUNTY, COLORADO
2045 BACKGROUND TRAFFIC VOLUMES



4.0 PROJECT TRAFFIC CHARACTERISTICS

4.1 Trip Generation

Site-generated traffic estimates are determined through a process known as trip generation. Rates and equations are applied to the proposed land use to estimate traffic generated by the development during a specific time interval. The acknowledged source for trip generation rates is the *Trip Generation Manual*¹ published by the Institute of Transportation Engineers (ITE). ITE has established trip rates in nationwide studies of similar land uses. For this study, Kimley-Horn used the ITE Trip Generation Report fitted curve equations that apply to Multifamily Low-Rise Housing (ITE Land Use Code 220) for the 264 dwelling units for traffic associated with the development per ITE recommendations.

Monument Hill is expected to generate approximately 1,768 weekday daily trips, with 106 of these trips occurring during the morning peak hour and 136 of these trips occurring during the afternoon peak hour. Calculations were based on the procedure and information provided in the ITE *Trip Generation Manual, 11th Edition – Volume 1: User's Guide and Handbook*, 2021. **Table 1** summarizes the estimated trip generation for the Monument Hill development. The trip generation worksheets are included in **Appendix C**.

Table 1 – Monument Hill Traffic Generation

Land Use and Size	Weekday Vehicle Trips						
	Daily	AM Peak Hour			PM Peak Hour		
		In	Out	Total	In	Out	Total
Multifamily Low-Rise Housing (ITE 220) – 264 Dwelling Units	1,768	25	81	106	86	50	136

¹ Institute of Transportation Engineers, *Trip Generation Manual*, Eleventh Edition, Washington DC, 2021.

4.2 Trip Distribution

Distribution of site traffic on the street system was based on the area street system characteristics, existing traffic patterns, existing and anticipated surrounding demographic information, and the proposed access system for the project. The directional distribution of traffic is a means to quantify the percentage of site-generated traffic that approaches the site from a given direction and departs the site back to the original source. The project trip distribution for the proposed development is illustrated in **Figure 6**.

4.3 Traffic Assignment


Monument Hill traffic assignment was obtained by applying the project trip distribution to the estimated traffic generation of the development shown in **Table 1**. Traffic assignment is shown in **Figure 7**.

4.4 Total (Background Plus Project) Traffic

Site traffic volumes (from **Figure 7**) were added to the background volumes (in **Figure 4** for the 2025 background and **Figure 5** for the 2045 background volumes) to represent estimated traffic conditions for the short-term 2025 buildout horizon and long-term 2045 twenty-year planning horizon. These total traffic volumes for the study area are illustrated for the 2025 and 2045 horizon years in **Figures 8** and **9**, respectively. Of note, the northbound and southbound through traffic volumes passing the proposed future accesses along Monument Hill Road (the South Access at Intersection #8 and the North Access at #9) were determined based on the traffic traveling to/from the south at the Deer Creek Road and Monument Hill Road (#3) intersection, from which all vehicles must continue traveling in the north/south direction along Monument Hill Road.



Kimley»»Horn








FIGURE 7
MONUMENT HILL
 EL PASO COUNTY, COLORADO
 PROJECT TRAFFIC ASSIGNMENT





LEGEND

(X) Study Area Key Intersection

(X) Project Access Intersection

XXX(XXX) Weekday AM(PM)
Peak Hour Traffic Volumes

XX,X00 Estimated Daily Traffic Volume*
*2025 Background + Project Assignment




FIGURE 8
MONUMENT HILL
 EL PASO COUNTY, COLORADO
 2025 TOTAL TRAFFIC VOLUMES








FIGURE 9
MONUMENT HILL
EL PASO COUNTY, COLORADO
2045 TOTAL TRAFFIC VOLUMES



5.0 TRAFFIC OPERATIONS ANALYSIS

Kimley-Horn's analysis of traffic operations in the site vicinity was conducted to determine potential capacity deficiencies in the 2025 and 2045 development horizons at the identified key intersections. The acknowledged source for determining overall capacity is the current edition of the *Highway Capacity Manual (HCM)*².

5.1 Analysis Methodology

Capacity analysis results are listed in terms of Level of Service (LOS). LOS is a qualitative term describing operating conditions a driver will experience while traveling on a particular street or highway during a specific time interval. It ranges from A (very little delay) to F (long delays and congestion). Based on El Paso County standards, the threshold for acceptable LOS is not worse than LOS D during peak hours. **Table 2** shows the definition of level of service for signalized and unsignalized intersections.

Table 2 – Level of Service Definitions

Level of Service	Signalized Intersection Average Total Delay (sec/veh)	Unsignalized Intersection Average Total Delay (sec/veh)
A	≤ 10	≤ 10
B	> 10 and ≤ 20	> 10 and ≤ 15
C	> 20 and ≤ 35	> 15 and ≤ 25
D	> 35 and ≤ 55	> 25 and ≤ 35
E	> 55 and ≤ 80	> 35 and ≤ 50
F	> 80	> 50

Definitions provided from the Highway Capacity Manual, Sixth Edition, Transportation Research Board, 2016.

Study area intersections were analyzed based on average total delay analysis for signalized and unsignalized intersections. Under the unsignalized analysis, the LOS for a two-way stop-controlled intersection is determined by the computed or measured control delay and is defined for each minor movement. LOS for a two-way stop-controlled intersection is not defined for the intersection as a whole. LOS for signalized, roundabout, and all-way stop controlled intersections are defined for each approach and for the overall intersection.

² Transportation Research Board, *Highway Capacity Manual*, Sixth Edition, Washington DC, 2016.

5.2 Key Intersection Operational Analysis

Calculations for the operational level of service at the key intersections for the study area are provided in **Appendix D**. The existing year analysis is based on the lane geometry and intersection control shown in **Figure 2**. Existing peak hour factors were used for all horizons while the recommended HCM urban area peak hour factor of 0.92 was used for the project accesses. The signalized intersection analysis utilizes the observed cycle lengths with optimized phasing and timing. Based on increased national attention given to establishing appropriate yellow and all-red clearance intervals to improve intersection safety, these have been calculated and are applied for approaches at the signalized intersection. The increase in yellow and all red time sacrifices intersection capacity for improved safety. Synchro traffic analysis software was used to analyze the signalized and unsignalized key intersections for HCM level of service.

Palmer Divide Road and Monument Hill Road (#1)

The unsignalized intersection of Palmer Divide Road and Monument Hill Road (#1) operates with stop control on the northbound and southbound approaches of Monument Hill Road. The movements operate acceptably at LOS C or better during both peak hours under existing conditions. With project traffic, the intersection movements are expected to continue operating with LOS D or better during both peak hours in the 2025 horizon.

By the 2045 horizon prior to construction of this project, this intersection may experience a failing level of service with its current lane configuration and control. As such, this intersection was analyzed as a single-lane roundabout or a signalized intersection in the 2045 horizon. Of note, a Four-Hour Signal Warrant was conducted in accordance with MUTCD guidelines and based on anticipated 2045 background plus project total volumes. It was found that this intersection is not anticipated to meet warrants for a signal. The volume for the four hours used for the signal warrant analysis include the morning and afternoon peak hour 2045 background plus project traffic volumes shown in **Figure 9**. The third and fourth hours used for the analysis were taken from the next highest morning and afternoon peak hour volumes observed in the existing turning movement counts, with those volumes grown with the aforementioned annual growth rate of 1.66 percent from year 2022 to 2045 while still adding the highest peak hour project volumes to the morning and afternoon periods. It was assumed on the minor approaches to the intersection that approximately half of the right turns would be able to turn on red. The signal warrant worksheets are attached in **Appendix F**. If this intersection were to become signalized, it would be

recommended to provide eastbound and westbound left turn lanes on Palmer Divide Road at this intersection to improve safety while also reducing delay at this intersection. Nevertheless, with the recommended improvements to this intersection of either a roundabout or a traffic signal, the intersection movements are anticipated to operate acceptably through the 2045 horizon. **Table 3** provides the results of the LOS analysis conducted at this intersection.

Table 3 – Palmer Divide Road & Monument Hill Road LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing				
Northbound Approach	21.2	C	14.9	B
Eastbound Left	8.5	A	7.7	A
Westbound Left	7.8	A	8.1	A
Southbound Approach	17.1	C	9.5	A
2025 Background				
Northbound Approach	24.1	C	15.7	C
Eastbound Left	8.5	A	7.8	A
Westbound Left	7.9	A	8.1	A
Southbound Approach	17.9	C	9.6	A
2025 Background Plus Project				
Northbound Approach	26.8	D	16.2	C
Eastbound Left	8.5	A	7.8	A
Westbound Left	7.9	A	8.2	A
Southbound Approach	18.0	C	9.6	A
2045 Background				
Northbound Approach	70.2	F	22.6	C
Eastbound Left	9.2	A	8.0	A
Westbound Left	8.1	A	8.6	A
Southbound Approach	26.7	D	10.2	B
2045 Background Plus Project #	10.4	B	6.4	A
Northbound Approach	4.8	A	5.8	A
Eastbound Approach	5.7	A	6.8	A
Westbound Approach	13.5	B	5.8	A
Southbound Approach	7.5	A	4.2	A
2045 Background Plus Project ##	23.5	C	27.1	C

= Single-lane roundabout; ## = Signalized intersection with eastbound and westbound left turn lanes

Misty Acres Boulevard and Monument Hill Road (#2)

The unsignalized 'T'-intersection of Misty Acres Boulevard and Monument Hill Road (#2) operates with stop control on the westbound approach of Misty Acres Boulevard. The movements operate with LOS D or better during both peak hours under existing conditions. The movements are expected to continue operating with LOS D or better during both peak hours through the 2025 horizon.

However, by the 2045 horizon prior to construction of this project, this intersection may experience a failing level of service in its current intersection configuration. As such, analysis was conducted with this intersection reconfigured as (1) a single-lane three-leg roundabout and (2) a signalized intersection with the current intersection lane configuration. Of note, a Four-Hour Signal Warrant was conducted in accordance with MUTCD guidelines and based on anticipated 2045 background plus project total volumes; this intersection is not anticipated to meet warrants for a signal. The same signal warrant methodology used for the Palmer Divide Road & Monument Hill Road (#1) intersection was used at this intersection. The signal warrant worksheets are attached in **Appendix F**. With the recommended improvements to the intersection of either a roundabout or a signal, the intersection is anticipated to operate at an acceptable level of service with project traffic in the 2045 horizon. **Table 4** provides the results of the LOS analysis conducted at this intersection.

Table 4 – Misty Acres Boulevard & Monument Hill Road LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing				
Westbound Left	26.8	D	12.3	B
Westbound Right	8.8	A	8.8	A
Southbound Left	8.7	A	8.0	A
2025 Background				
Westbound Left	30.2	D	12.6	B
Westbound Right	8.9	A	8.9	A
Southbound Left	8.8	A	8.1	A
2025 Background Plus Project				
Westbound Left	31.5	D	12.9	B
Westbound Right	9.0	A	8.9	A
Southbound Left	8.9	A	9.1	A
2045 Background				
Westbound Left	92.3	F	14.7	B
Westbound Right	9.1	A	9.0	A
Southbound Left	9.4	A	8.3	A
2045 Background Plus Project #	11.1	B	6.3	A
Westbound Approach	8.9	A	6.7	A
Northbound Approach	11.4	B	6.0	A
Southbound Approach	13.8	B	5.7	A
2045 Background Plus Project ##	22.8	C	19.9	B

= Single-lane three-leg roundabout; ## = Signalized intersection with existing lane configuration

Deer Creek Road and Monument Hill Road (#3)

The unsignalized 'T'-intersection of Deer Creek Road and Monument Hill Road (#3) operates with stop control on the westbound approach of Deer Creek Road. The movements at the intersection currently operate with LOS C or better during both peak hours. With the addition of project traffic, the movements are expected to continue operating with LOS D or better during the morning and afternoon peak hours through 2045. Therefore, no improvements or modifications are anticipated to be needed at the intersection. **Table 5** provides the results of the LOS analysis conducted at this intersection.

Table 5 – Deer Creek Road & Monument Hill Road LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing				
Westbound Left	15.9	C	14.3	B
Westbound Right	15.2	C	10.5	B
Southbound Left	9.1	A	8.2	A
2025 Background				
Westbound Left	16.7	C	14.8	B
Westbound Right	16.0	C	10.6	B
Southbound Left	9.3	A	8.3	A
2025 Background Plus Project				
Westbound Left	18.7	C	15.9	C
Westbound Right	16.7	C	11.3	B
Southbound Left	9.4	A	8.6	A
2045 Background				
Westbound Left	20.6	C	17.6	C
Westbound Right	22.5	C	11.4	B
Southbound Left	10.0	B	8.6	A
2045 Background Plus Project				
Westbound Left	25.2	D	19.8	C
Westbound Right	24.9	C	12.3	B
Southbound Left	10.3	B	9.0	A

Deer Creek Road and Base Camp Road (#4)

The Deer Creek Road and Base Camp Road (#4) 'T'-intersection operates with stop control on the southbound approach of Base Camp Road. Currently, the movements at the intersection operate with LOS A during the morning and afternoon peak hours. The movements at the intersection are anticipated to continue operating with LOS B or better during both peak hours with the addition of project traffic through the long-term horizon. Therefore, no improvements or modifications are anticipated to be needed at the intersection. **Table 6** provides the results of the LOS analysis conducted at this intersection.

Table 6 – Deer Creek Road and Base Camp Road LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing				
Eastbound Left	7.7	A	7.4	A
Southbound Approach	9.6	A	9.4	A
2025 Background				
Eastbound Left	7.8	A	7.5	A
Southbound Approach	9.8	A	9.5	A
2025 Background Plus Project				
Eastbound Left	7.8	A	7.5	A
Southbound Approach	10.7	B	9.8	A
2045 Background				
Eastbound Left	7.9	A	7.5	A
Southbound Approach	10.2	B	9.9	A
2045 Background Plus Project				
Eastbound Left	8.0	A	7.6	A
Southbound Approach	11.6	B	10.3	B

Deer Creek Road and Woodmoor Drive (#5)

The unsignalized intersection of Deer Creek Road and Woodmoor Drive (#5) operates with stop control on the eastbound and westbound approach of Deer Creek Road. With existing geometry and control, the movements at the intersection operate with LOS C or better during both peak hours. It is known that a roundabout is being considered at this intersection in the future. As such, the 2025 and 2045 horizon years include analysis of this intersection reconfigured as a roundabout (results shown in blue in **Table 7**) in addition to the horizon analysis completed with its existing configuration. With the addition of project traffic, the intersection movements are expected to continue operating with LOS D or better during both peak hours through the 2045 horizon in its existing configuration. With the modification of the intersection to become a single-

lane roundabout, the intersection movements are anticipated to operate at LOS A during both peak hours through the 2045 horizon. As such, the intersection is anticipated to operate well with either its existing configuration or the single-lane roundabout through the 2045 horizon with the addition of project traffic. **Table 7** provides the results of the LOS analysis conducted at this intersection.

Table 7 – Deer Creek Road & Woodmoor Drive LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing				
Northbound Left	8.2	A	7.7	A
Eastbound Approach	12.1	B	11.3	B
Westbound Approach	16.5	C	13.6	B
Southbound Left	0.0	A	7.6	A
2025 Background				
Northbound Left	8.2	A	7.7	A
Eastbound Approach	12.5	B	11.7	B
Westbound Approach	18.4	C	14.4	B
Southbound Left	0.0	A	7.7	A
2025 Background Plus Project				
Northbound Left	8.3	A	7.7	A
Eastbound Approach	12.6	B	11.8	B
Westbound Approach	19.0	C	14.8	B
Southbound Left	0.0	A	7.7	A
2025 Background Plus Project #	5.2	A	4.4	A
Northbound Approach	3.8	A	4.7	A
Eastbound Approach	4.8	A	3.8	A
Westbound Approach	3.8	A	3.9	A
Southbound Approach	6.3	A	4.2	A
2045 Background				
Northbound Left	8.6	A	7.8	A
Eastbound Approach	14.5	B	13.0	B
Westbound Approach	25.1	D	16.7	C
Southbound Left	0.0	A	7.8	A
2045 Background Plus Project				
Northbound Left	8.6	A	7.8	A
Eastbound Approach	15.7	C	13.6	B
Westbound Approach	28.5	D	17.9	C
Southbound Left	0.0	A	7.8	A
2045 Background Plus Project #	6.2	A	4.9	A
Northbound Approach	4.2	A	5.3	A
Eastbound Approach	5.7	A	4.2	A
Westbound Approach	4.2	A	4.2	A
Southbound Approach	7.8	A	4.7	A

= Single-lane roundabout

Monument Hill Road and Woodmoor Drive (#6)

The Monument Hill Road and Woodmoor Drive (#6) unsignalized intersection operates with stop control on the eastbound and westbound approaches of Monument Hill Road with the eastbound right turn operating with free movement. Based on the analysis conducted in this study, the eastbound left/through and westbound approaches to the intersection both operate at LOS F during the morning peak hour under existing conditions in 2022, while intersection movements currently operate at LOS D or better during the afternoon peak hour. As such, improvements are recommended to be considered at this intersection soon, with or without construction of this project.

Because the eastbound left/through movements along Monument Hill Road and the westbound Mountain Springs Recovery access approach to the intersection are the most poorly performing movements, restriction of these movements on school days from approximately 6:30 to 8:30 AM and 2:00 to 5:00 PM could be considered by posting signage indicating this restriction at the intersection. If a more permanent and restrictive turning movement modification were desired at this intersection, the eastbound left/through turning movements could be removed entirely in addition to the restriction of the westbound approach to westbound right turns only with a raised pork chop island to restrict this access to $\frac{3}{4}$ -turning movements. Cross access to adjacent existing properties may need to be considered if this access to Mountain Springs Recovery is restricted. Of note, any modifications to this intersection are needed today based on existing traffic volumes and are not caused by the project traffic from this study. The restriction of these turning movements either during peak school traffic periods or at all times would allow for this intersection to operate well at LOS C or better through the 2045 horizon as shown in **Table 8** in blue.

For purposes of this study, analysis was also conducted with this intersection reconfigured as a roundabout or a signal in the 2025 and 2045 horizons. The existing eastbound right turn lane that operates with free conditions is recommended to remain unmodified. In the roundabout scenario, the eastbound approach to the roundabout should provide a shared left/through lane, the westbound approach should provide a shared left/through/right turn lane, the northbound approach should provide a left turn lane and a shared through/right turn lane, and the southbound approach should provide a shared left/through lane and a right turn lane. As a roundabout, the intersection is anticipated to operate at LOS C or better during the morning and afternoon peak hours through the 2045 horizon.

The signalized intersection scenario (shown in yellow in **Table 8**) analyzed this intersection based on the existing intersection lane configuration, including the eastbound free right turn lane. As a signalized intersection, this intersection is anticipated to operate at LOS B or better during the morning and afternoon peak hours through the 2045 horizon. However, an MUTCD Four Hour Signal Warrant was conducted at this intersection for 2045 background plus project traffic volumes and a signal is not anticipated to be warranted at this intersection through the 2045 horizon (the eastbound right turning movement volumes are not included in the signal warrant analysis as these vehicles operate with free turning movements outside of the intersection). The signal warrant worksheets are attached in **Appendix F**.

With the addition of project traffic and the recommended improvements—whether that be restricted turning movements, a roundabout, or a signalized intersection—the intersection is expected to operate acceptably during both peak hours through the 2045 horizon. **Table 8** provides the results of the LOS analysis conducted at this intersection.

Table 8 – Monument Hill Road & Woodmoor Drive LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing				
Northbound Left	12.0	B	9.5	A
Eastbound Left/Through	51.1	F	23.7	C
Westbound Approach	77.5	F	27.2	D
Southbound Left	8.4	A	8.1	A
2025 Background				
Northbound Left	12.7	B	9.7	A
Eastbound Left/Through	58.6	F	25.4	D
Westbound Approach	78.2	F	29.9	D
Southbound Left	8.5	A	8.2	A
2025 Background Plus Project #				
Northbound Left	13.3	B	10.2	B
Westbound Right	11.6	B	10.8	B
Southbound Left	8.5	A	8.2	A
2025 Background Plus Project ##				
Northbound Left	10.1	B	7.1	A
Northbound Through/Right	5.5	A	4.7	A
Eastbound Left/Through	6.4	A	5.2	A
Westbound Approach	5.4	A	4.7	A
Southbound Left/Through	7.2	A	6.0	A
Southbound Right	17.1	C	10.5	B
2025 Background Plus Project ###	5.3	A	3.9	A
2045 Background				
Northbound Left	4.9	A	4.1	A
Eastbound Left/Through	18.0	C	10.8	B
Westbound Approach	163.8	F	35.3	E
Southbound Left	79.0	F	54.1	F
	8.9	A	8.4	A
2045 Background Plus Project #				
Northbound Left	19.8	C	11.8	B
Westbound Right	12.8	B	11.7	B
Southbound Left	9.0	A	8.5	A
2045 Background Plus Project ##	21.1	C	9.6	A
Northbound Left	6.4	A	5.2	A
Northbound Through/Right	7.8	A	6.1	A
Eastbound Left/Through	6.9	A	5.5	A
Westbound Approach	9.2	A	7.5	A
Southbound Left/Through	44.6	E	16.0	C
Southbound Right	5.8	A	4.4	A
2045 Background Plus Project ###	16.2	B	6.2	A

= Eastbound left/through and westbound left/through movements restricted during peak hours or permanently; ## = Roundabout; ### = Signal

SH-105 and Woodmoor Drive (#7)

The signalized intersection of SH-105 and Woodmoor Drive (#7) operates with protected-only left turn phasing on the eastbound approach of SH-105. The intersection currently operates with LOS C during the morning and afternoon peak hours. However, based on the analysis conducted in this study, the southbound right-turn lane 95th-percentile queue length was observed to extend past the Lake Woodmoor Drive and Woodmoor Drive intersection located approximately 300 feet to the north of SH-105 and Woodmoor Drive (#7) in the existing conditions. As such, it is recommended with or without construction of this project that the chevron-striped lane between the existing southbound right turn and left turn lanes be modified to become a second southbound right turn lane and the southbound right turn phasing be modified from permissive-overlap phasing to protected-overlap phasing with no right turn on red in the existing horizon. With these improvements, this intersection is anticipated to operate acceptably at LOS C through the 2045 horizon. **Table 9** provides the results of the LOS analysis conducted at this intersection.

Table 9 – SH-105 & Woodmoor Drive LOS Results

Scenario	AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
2022 Existing	31.8	C	30.0	C
2025 Background #	26.3	C	25.9	C
2025 Background Plus Project #	27.6	C	26.9	C
2045 Background #	31.8	C	27.9	C
2045 Background Plus Project #	34.3	C	29.8	C

= Addition of second SB right turn lane with protected-overlap SB right turn phasing

Project Accesses

With completion of the Monument Hill project, a northern full movement access is proposed to be located approximately 800 feet south of the Palmer Ridge High School bus loop access (measured right-of-way to center) and a southern right-in/right-out access is proposed to be located approximately 800 feet south of the full movement access, which is approximately 775 feet north of Deer Creek Road (measured centerline to centerline). In addition, a full movement access will be provided on Base Camp Road at the northern terminus of the cul-de-sac (#10). The northern full movement access (#9) along Monument Hill Road is recommended to operate with stop-control with an R1-1 "STOP" sign is recommended to be installed on the exiting westbound approach. The southern right-in/right-out access (#8) along Monument Hill Road is recommended to operate with stop control with installation of an R1-1 "STOP" sign on the westbound exiting driveway approach. In addition, an R3-2 No Left Turn sign is recommended to be installed below the "STOP" sign to identify the restriction to right out only and on the southeast corner of the intersection visible to southbound drivers to identify the restriction to right in only. The proposed full movement access at Base Camp Road (#10) is located at the northern cul-de-sac terminus of the roadway and as such, vehicles entering and exiting the development from this access are not anticipated to experience measurable delay.

Table 10 provides the results of the level of service for the proposed project access intersections. As shown in the table, the project access intersections along Monument Hill Road are anticipated to have all movements operating with acceptable LOS C or better during the peak hours in both the buildout year 2025 and the 2045 long term horizons.

Table 10 – Project Access Level of Service Results

Intersection	2025 Total				2045 Total			
	AM Peak Hour		PM Peak Hour		AM Peak Hour		PM Peak Hour	
	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS	Delay (sec/veh)	LOS
Monument Hill South Access (RIRO) (#8) Westbound Right	11.2	B	10.3	B	12.1	B	10.8	B
Monument Hill North Access (Full) (#9) Westbound Approach	18.0	C	15.9	C	23.5	C	19.5	C
Southbound Left	8.3	A	8.0	A	8.7	A	8.2	A
Base Camp Road Access (Full) (#10) All Approaches	0.0	A	0.0	A	0.0	A	0.0	A

5.3 CDOT Analysis

The threshold for requiring an access permit along Colorado Department of Transportation (CDOT) roadways occurs when project traffic is anticipated to increase the existing access traffic volumes by more than 20 percent or modifications are needed at the intersection. Based on traffic projections, the addition of project traffic on the north leg of Woodmoor Drive at SH-105 is not anticipated to increase existing access traffic volumes by more than 20 percent, with the maximum expected increase at 7.7 percent during the afternoon peak hour on the north leg (116 project / 1508 existing 2022 counts).

The 116 project-generated vehicles estimated during the afternoon peak hour on the north leg of this intersection are calculated based on **Figure 7** project traffic assignment on the north leg of the intersection, including eastbound left turning vehicles, westbound right turning vehicles, and the southbound left and right turning vehicles. The 1,508 vehicles on this north leg are based on the existing 2022 traffic volumes shown in **Figure 3** for these same turning movements during the 2022 existing afternoon peak hour. The existing 2022 traffic volumes are used per the CDOT State Highway Access Code standards rather than the 2025 background traffic volumes as this provides a more conservative estimate of the impact project traffic will have on CDOT roadways. Because under 20 percent of existing access traffic volumes are anticipated to increase because of project traffic—at 7.7 percent—a CDOT access permit is not anticipated to be required in association with this project.

5.4 El Paso County Turn Lane Requirement Analysis

The El Paso County Engineering Criteria Manual (ECM) was used to determine if left and right turn lanes are warranted along Monument Hill Road and Woodmoor Drive. El Paso County classifies Monument Hill Road and Woodmoor Drive as Collector roadways. According to El Paso County ECM guidelines for Minor Arterials and Lower Classifications, a left turn lane is required for any access with a projected peak hour left turning volume of 25 vehicles per hour or greater, a right turn lane is required for any access with a projected peak hour right turning volume of 50 vehicles per hour or greater, and a right turn acceleration lane is generally not required.

Based on Monument Hill Road providing a posted speed limit of 45 miles per hour to the south of Misty Acres Boulevard and Woodmoor Drive providing a speed limit of 30 miles per hour, the turn lane requirements that the project traffic contributes to are as follows:

Deer Creek Road & Monument Hill Road (#3):

- A northbound right turn lane exists and **is not** warranted at this intersection based on projected 2025 total traffic volumes being 47 northbound right turns during the peak hour and the threshold being 50 vehicles per hour. The existing northbound right turn provides a length of 225 feet.
- A southbound left turn lane exists and **is** warranted at this intersection based on projected 2025 total traffic volumes being 87 southbound left turns during the peak hour and the threshold being 25 vehicles per hour. The existing southbound left turn lane is 475 feet.
- A westbound left turn lane exists and **is** warranted at this intersection based on projected 2025 total traffic volumes being 35 westbound left turns during the peak hour and the threshold being 25 vehicles per hour. The existing westbound left turn lane is 150 feet.

Monument Hill Road & Woodmoor Drive (#6):

- A northbound left turn lane exists and **is** warranted at this intersection based on projected 2025 total traffic volumes being 315 northbound left turns during the peak hour and the threshold being 25 vehicles per hour. The existing southbound left turn lane is 450 feet and is within a two-way left turn lane median.
- An eastbound right turn lane exists and **is** warranted at this intersection based on projected 2025 total traffic volumes being 389 eastbound right turns during the peak hour and the threshold being 50 vehicles per hour. The eastbound right turn lane is channelized, and the movement operates under free conditions.

Southern RIRO Access & Monument Hill Road (#8):

- A northbound right turn lane **is not** warranted at this intersection based on projected 2025 total traffic volumes being 17 northbound right turns during the peak hour and the threshold being 50 vehicles per hour.

Northern Full Access & Monument Hill Road (#9):

- A northbound right turn lane **is not** warranted at this intersection based on projected 2025 total traffic volumes being 39 northbound right turns during the peak hour and the threshold being 50 vehicles per hour.

- A southbound left turn lane **is not** warranted at this intersection based on projected 2025 total traffic volumes being 13 southbound left turns during the peak hour and the threshold being 25 vehicles per hour.

5.5 Vehicle Queuing Analysis

A vehicle queuing analysis was conducted for the study area intersections. The queuing analysis was performed using Synchro presenting the results of the 95th percentile queue lengths. Results are shown in the following **Table 11** with calculations provided within the level of service operational sheets of **Appendix D** for unsignalized intersections and **Appendix E** for signalized intersections.

Table 11 – Turn Lane Queuing Analysis Results

Intersection Turn Lane	Existing Turn Lane Length (feet)	2025 Calculated Queue (feet)	2025 Recommended Length (feet)	2045 Calculated Queue (feet)	2045 Recommended Length (feet)
Misty Acres & Monument (#2)					
Westbound Left	250'	225'	250'	RAB	RAB
Southbound Left	275'	25'	275'	RAB	RAB
Deer Creek & Monument (#3)					
Westbound Left	150'	25'	150'	25'	150'
Southbound Left	475'	25'	475'	25'	475'
Northbound Right	225'	25'	225'	25'	225'
Deer Creek & Monument (#6)					
Northbound Left	450'	25'	450'	50'	450'
Southbound Left	TWLTL	RAB	C	RAB	RAB
SH-105 & Woodmoor Dr (#7)					
Eastbound Left	300' DL	148' DL	300' DL	221' DL	300' DL
Westbound Right	300'	58'	300'	139'	300'
Southbound Left	C DL	182' DL	C/250' DL	242' DL	C/250' DL
Southbound Right	C	242'	C/250' DR	346'	C/250' DR

DL = Dual Left Turn Lanes; DR = Dual Right Turn Lanes; C = Continuous; RAB = Roundabout Approach Lane

All queues are anticipated to remain within the existing or recommended turn lane lengths through 2045.

5.6 Access Spacing Requirements and Roadway Classifications

According to El Paso County 2016 Major Transportation Corridors Plan Update, Monument Hill Road is classified as a collector roadway. The following identifies the intersection spacing requirements for the access intersections associated with the project:

Monument Hill Road South Access (RIRO)

The proposed right-in/right-out South Access is located approximately 800 feet south of the proposed North Access and 775 feet north of the Deer Creek Road intersection (measured centerline to centerline). According to the El Paso County Engineering Criteria Manual, spacing of intersections along urban collector roadways from a local roadway should be 330 feet from the right-of-way line of the local roadway to the centerline of the access roadway. Therefore, the South Access meets El Paso County spacing requirements.

Monument Hill Road North Access (Full)

The proposed full movement North Access is located approximately 800 feet south of the Palmer Ridge High School Bus Loop intersection (measured centerline to centerline). According to the El Paso County Engineering Criteria Manual, spacing of intersections along urban collector roadways from a local roadway should be 330 feet from the right-of-way line of the local roadway to the centerline of the access roadway. Therefore, the North Access meets El Paso County spacing requirements.

SH-105 is projected to have a 2025 volume of approximately 26,700 vehicles per day and is classified as a four-lane minor arterial. The section of Woodmoor Drive from SH-105 to Monument Hill Road is classified as a non-residential collector roadway with an average daily traffic threshold standard of 20,000 vehicles per day and is projecting to carry 17,300 vehicles per day. North of Monument Hill Road, Woodmoor Drive is classified as a residential collector roadway with 8,400 vehicles per day and the El Paso County threshold is 10,000 vehicles per day. In addition, Palmer Divide Road is classified as a non-residential collector roadway with 6,000 to 7,000 vehicles per day anticipated. Misty Acres Boulevard is classified by El Paso County as a residential collector roadway with 4,700 vehicles per day and the threshold is 10,000 vehicles per day. Deer Creek Road is classified by El Paso County as a local road with approximately 800 vehicles per day estimated to the east of Woodmoor Drive and the threshold is 3,000 vehicles per day. Base Camp Road is classified by El Paso County as a local road with approximately 600 vehicles per day and the threshold is 3,000 vehicles per day. **Figure 10** illustrates the circulation plan and street classification map for roadways internal and external to the Monument Hill project.




FIGURE 10
MONUMENT HILL
EL PASO COUNTY, COLORADO
ROADWAY CLASSIFICATION

5.7 Sight Distance Evaluation

It is recommended that sight triangles be provided at all site access points to give drivers exiting the site a clear view of oncoming traffic. Landscaping and objects within sight triangles must not obstruct drivers' views of the adjacent travel lanes. ECM design intersection sight distances for left turn from stop were evaluated at the accesses along Monument Hill Road. ECM does not provide sight distances for right-turning vehicles from stop; therefore, AASHTO standards were used for right-turn from stop distances at the project accesses. The following identifies sight distance requirements for the access intersections associated with the project:

Monument Hill Road South Access (RIRO)

With AASHTO standards and design speed of 50 mph (consistent with ECM Table 2-7, speed limit of 45 mph), the sight distance for a vehicle turning right from stop is 555 feet as stated in the ECM Table 2-21. Therefore, all obstructions for right turning vehicles from stop should be clear to the left within the triangle created with a vertex point located 13 feet from the edge of the major road traveled way and a line-of-sight distance of 555 feet located in the middle of the northbound through lane along Monument Hill Road. Therefore, it is believed that the proposed south access along Monument Hill Road is appropriately located to provide necessary sight distances.

Monument Hill Road North Access (Full)

With El Paso County standards and a roadway design speed of 50 miles per hour along Monument Hill Road (consistent with ECM Table 2-7, speed limit of 45 mph), the intersection sight distance for a vehicle turning left from stop is 555 feet. Therefore, all obstructions for left turning vehicles from stop should be clear to the right within the triangle created with a vertex point located 13 feet from the edge of the major road traveled way and a line-of-sight distance of 555 feet located in the middle of the southbound through lane along Monument Hill Road. Likewise, all obstructions for right turning vehicles from stop should be clear to the left within the triangle created with a vertex point located 13 feet from the edge of the major road traveled way and a line-of-sight distance of 555 feet located in the middle of the northbound through lane along Monument Hill Road. Therefore, it is believed that the proposed north access along Monument Hill Road is appropriately located to provide necessary sight distances.

5.8 Bicycle and Pedestrian Access

Sidewalks are not present on either side of the Monument Hill Road, Deer Creek Road, Misty Acres Boulevard, or along the majority of Woodmoor Drive. Sidewalks are provided on either side of Woodmoor Drive from SH-105 to approximately 800 feet north of SH-105. Bicycle lanes are not provided along any of the study roadways. The development is not proposing to provide sidewalks or bicycle lanes along Monument Hill Road to match the characteristic of the surrounding areas. It is known that the Lewis Palmer School District Trail System is proposing a “Safe Routes to School” pedestrian system in the area. Per the plans provided by El Paso County, this system includes sidewalks and/or trails within the study area along much of Woodmoor Drive, Deer Creek Road, and Lake Woodmoor Drive, with curb ramps and pavement striping at crosswalks to provide safer access to schools in the area.

5.9 Road Impact Fees

Road impact fees were evaluated based on the El Paso County Road Impact Fee Schedule. Based on these fee schedule guidelines, the fee per multi-family dwelling unit is \$2,407. Therefore, the road impact fee for the proposed 264 multi-family residences is expected to be \$635,448. Road impact fee calculations are shown in **Table 12**. During the final plat process, the project team will determine if the impact fees are paid up front or if the property will be included in one of the available public improvement districts with reduced upfront costs. The project team will determine payment methods with the final plat.

Table 12 – Road Impact Fees

Use	Units	Fee / Unit	Total Fee
Multi-Family Housing	264	\$2,407	\$635,448

5.10 Improvement Summary

Based on the results of the intersection operational, turn lane evaluations, and vehicle queuing analysis, the key intersection recommended improvements and control is shown in **Figure 11** for the 2025 short-term horizon and in **Figure 12** for the 2045 long-term horizon.





FIGURE 11
MONUMENT HILL
EL PASO COUNTY, COLORADO
2025 RECOMMENDED GEOMETRY AND CONTROL

6.0 CONCLUSIONS AND RECOMMENDATIONS

Based on the analysis presented in this report, Kimley-Horn believes Monument Hill will be successfully incorporated into the existing and future roadway network. Analysis of the existing street network, the proposed project development, and expected traffic volumes resulted in the following conclusions and recommendations:

2022 Recommendations

- The Monument Hill Road and Woodmoor Drive (#6) intersection experiences a failing level of service today with existing traffic during the morning peak hour. As such, it is recommended this intersection be considered for control improvements to provide acceptable level of service. For purposes of this analysis, the intersection was evaluated with three possible scenarios, including (1) restricted turning movements on the minor street approaches, (2) roundabout control, and (3) a signalized intersection. The existing eastbound right turn lane that operates with free conditions can remain unmodified in all scenarios.
 - Turning movement restriction scenario: the eastbound left/through and westbound left/through movements are the most poorly performing turning movements. As such, restriction of these movements on school days from approximately 6:30 to 8:30 AM and 2:00 to 5:00 PM could be considered by posting signage indicating this restriction at the intersection. If a more permanent and restrictive turning movement modification were desired at this intersection, the eastbound left/through turning movements could be removed entirely in addition to the restriction of the westbound approach to westbound right turns only with a raised pork chop island to restrict this access to $\frac{3}{4}$ -turning movements. Cross access to adjacent existing properties may need to be considered if this access to Mountain Springs Recovery is restricted. The restriction of these turning movements either during peak school traffic periods or at all times would allow for this intersection to operate well at LOS C or better through the 2045 horizon.
 - Roundabout scenario: The eastbound approach to the roundabout should provide a shared left/through lane. The westbound approach should provide a shared left/through/right turn lane. The northbound approach should provide a left turn lane and a shared through/right turn lane. The southbound approach should provide a shared left/through lane and a right turn lane. Each approach to the

roundabout should operate with yield conditions with posted R1-2 “YIELD” signs. As a roundabout, the intersection is anticipated to operate at LOS C or better during the morning and afternoon peak hours through the 2045 horizon.

- Signalized intersection: an MUTCD Four Hour Signal Warrant was conducted at this intersection with 2045 background plus project total volumes and based on these volumes a signal is not anticipated to be warranted at this intersection. However, to provide a complete analysis, an operational analysis of this intersection was conducted based on the existing intersection lane configuration. As a signalized intersection with the existing lane configuration, the intersection is anticipated to operate at LOS B or better during both peak hours through the 2045 horizon.

- At the SH-105 and Woodmoor Drive (#7) intersection, it is recommended that southbound dual right turn lanes be provided due to existing southbound queues extending beyond the Lake Woodmoor Drive intersection to the north. The existing chevron striping between the southbound right turn and left turn lanes should be modified to include a second southbound right turn lane. As such, it is recommended the southbound right turn phasing be modified from permissive-overlap to protected-overlap phasing with no right turn on red. It is anticipated this southbound right turn lane will be a continuous lane from the southbound through lane to the north of the Woodmoor Drive and Lake Woodmoor Drive intersection, while the inner southbound left turn lane also be a continuous lane. The existing southbound right and left turn lanes are recommended to provide 250 feet of storage length.

2025 Recommendations

- The threshold for requiring an access permit along Colorado (CDOT) roadways occurs when project traffic is anticipated to increase the existing access traffic volumes by more than 20 percent or modifications are needed at the intersection. Based on traffic projections, the addition of project traffic on the north leg of Woodmoor Drive at SH-105 is not anticipated to increase existing access traffic volumes by more than 20 percent, with the maximum expected increase at 7.7 percent during the afternoon peak hour on the north leg (116 project / 1508 existing 2022 counts). Therefore, a CDOT access permit is not anticipated to be required in association with this project.

Modifications to intersection are being proposed. Based on that assumption, access permit would be anticipated.

These numbers should be updated to 2025 volumes and then determine % increase to determine if access permit is required

- A southern project right-in/right-out access (#8) is proposed to be located approximately 800 feet south of the full movement access (measured center to center), which would also place it approximately 775 feet north of the Deer Creek Road intersection. An R1-1 “STOP” sign is recommended to be installed on the exiting westbound approach. In addition, an R3-2 No Left Turn sign is recommended to be installed below the “STOP” sign to identify the restriction to right out only and on the southeast corner of the intersection visible to southbound drivers to identify the restriction to right in only.
- With completion of the Monument Hill project, a northern full movement access (#9) is proposed to be located approximately 800 feet south of the Palmer Ridge High School bus loop access (measured right-of-way to center). The access is recommended to operate with stop control with installation of an R1-1 “STOP” sign on the westbound exiting approach.
- A full movement access is proposed to be located at the northern terminus of the cul-de-sac on Base Camp Road (#10). As this access is proposed to be located at the end the cul-de-sac, vehicles entering and exiting this access are not anticipated to experience any vehicle conflict or measurable delay.

2045 Recommendations

- If projected 2045 volumes are realized, the Palmer Divide Road and Monument Hill Road (#1) intersection may need to be reconfigured with control improvements to operate acceptably. This intersection is anticipated to operate acceptably as a single-lane roundabout with a shared left/through/right turn lane at each approach or as a signalized intersection with eastbound and westbound left turn lanes. If a roundabout is constructed, each approach should operate with yield conditions with posted R1-2 “YIELD” signs. Of note, this intersection experiences a failing level of service in the 2045 horizon with or without construction of this project.
- The intersection of Misty Acres Boulevard and Monument Hill Road (#2) may experience a failing level of service in the 2045 horizon if projected volumes are realized. This intersection is also anticipated to operate acceptably as a single-lane roundabout with a shared northbound through/right turn lane, a shared southbound left/through lane, and a shared westbound left/right turn lane or with a traffic signal with the existing intersection configuration.

The east leg of the intersection should still provide the existing configuration of two eastbound through lanes approaching the northern Palmer Ridge High School access, with the outside lane being an eastbound right turn lane into Palmer Ridge High School access and the inside lane continuing to the east. If constructed, each approach to the roundabout should operate with yield conditions with posted R1-2 “YIELD” signs. Of note, this intersection experiences a failing level of service in the 2045 horizon with or without construction of this project.

General Recommendations

- Any onsite or offsite improvements should be incorporated into the Civil Drawings and conform to standards of El Paso County and the Manual on Uniform Traffic Control Devices (MUTCD) – 2009 Edition.

Table 13 provides a summary of recommended improvements and the percent of traffic generated by the project at each intersection versus the traffic occurring at each intersection without project construction. The volumes used in this table include the 2025 and 2045 background traffic volumes—depending on the horizon year in which the recommended improvement is proposed—and the project-generated traffic.

Table 13 – Summary of Recommended Improvements

Horizon Year	Intersection	Improvement	Traffic Volume Source	Percent of Traffic
2025	Monument Hill & Woodmoor (#6)	Turning Movement Restriction/Roundabout/Traffic Signal	Intersection volume	7.1%
	SH-105 & Woodmoor (#7)	Second Southbound Right Turn Lane	Southbound right turn volume	9.3%
	Monument Hill South RI/RO Access (#8)	Construction of Access	Access volume	100.0%
	Monument Hill North Full Access (#9)	Construction of Access	Access volume	100.0%
2045	Palmer Divide & Monument Hill (#1)	Roundabout/Signalized Intersection	Intersection volume	1.9%
	Misty Acres & Monument Hill (#2)	Roundabout/Signalized Intersection	Intersection volume	2.2%

APPENDICES

APPENDIX A

Intersection Count Sheets

Monument Hill Rd Palmer Divide Ave





Peak Hour

Date: 09/07/2022

Count Period: 7:00 AM to 9:00 AM

Peak Hour: 7:00 AM to 8:00 AM



	HV %:	PHF
EB	4.8%	0.60
WB	0.4%	0.89
NB	2.2%	0.58
SB	0.0%	0.50
TOTAL	1.8%	0.80

Two-Hour Count Summaries

Interval Start		Palmer Divide Ave				Palmer Divide Ave				Monument Hill Rd				S Andrews RD				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	0	13	14	0	10	108	0	0	14	1	3	0	0	1	0	164	0
7:15 AM		0	0	37	41	0	30	99	0	0	13	0	11	0	0	0	0	231	0
7:30 AM		0	1	30	7	0	10	106	0	0	29	1	9	0	1	0	1	195	0
7:45 AM		0	1	35	7	0	3	92	0	0	6	1	2	0	0	1	0	148	738
8:00 AM		0	2	28	3	0	1	76	1	0	7	1	1	0	0	1	1	122	696
8:15 AM		0	0	33	9	0	5	79	0	0	6	0	1	0	0	0	1	134	599
8:30 AM		0	2	26	7	0	1	67	0	0	3	0	2	0	1	1	0	110	514
8:45 AM		0	0	37	4	0	3	73	0	0	6	1	2	0	0	3	1	130	496
Count Total		0	6	239	92	0	63	700	1	0	84	5	31	0	2	7	4	1,234	0
Peak Hour	All	0	2	115	69	0	53	405	0	0	62	3	25	0	1	2	1	738	0
	HV	0	0	8	1	0	0	2	0	0	2	0	0	0	0	0	0	13	0
	HV%	-	0%	7%	1%	-	0%	0%	-	-	3%	0%	0%	-	0%	0%	0%	2%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
7:15 AM	2	0	1	0	3	0	0	0	1	1	0	0	0	0	0
7:30 AM	6	1	1	0	8	0	0	0	0	0	0	0	0	0	0
7:45 AM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0
8:00 AM	3	2	1	1	7	0	0	0	0	0	0	0	0	0	0
8:15 AM	3	4	0	0	7	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	3	0	0	3	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	3	1	1	5	0	0	0	0	0	0	0	0	0	0
Count Total	15	14	4	2	35	0	0	0	1	1	0	0	0	0	0
Peak Hour	9	2	2	0	13	0	0	0	1	1	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																		
Interval Start	Palmer Divide Ave				Palmer Divide Ave				Monument Hill Rd				S Andrews RD				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0
7:15 AM	0	0	2	0	0	0	0	0	0	1	0	0	0	0	0	0	3	0
7:30 AM	0	0	5	1	0	0	1	0	0	1	0	0	0	0	0	0	8	0
7:45 AM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	13
8:00 AM	0	0	2	1	0	0	2	0	0	0	1	0	0	0	1	0	7	19
8:15 AM	0	0	2	1	0	0	4	0	0	0	0	0	0	0	0	0	7	23
8:30 AM	0	0	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3	18
8:45 AM	0	0	0	0	0	0	3	0	0	1	0	0	0	0	1	0	5	22
Count Total	0	0	12	3	0	0	14	0	0	3	1	0	0	0	2	0	35	0
Peak Hour	0	0	8	1	0	0	2	0	0	2	0	0	0	0	0	0	13	0

Two-Hour Count Summaries - Bikes																		
Interval Start	Palmer Divide Ave			Palmer Divide Ave			Monument Hill Rd			S Andrews RD			15-min Total	Rolling One Hour				
	Eastbound			Westbound			Northbound			Southbound								
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT						
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
7:15 AM	0	0	0	0	0	0	0	0	0	0	1	0	1	0	0			
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1			
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1			
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
Count Total	0	0	0	0	0	0	0	0	0	0	1	0	1	0	0			
Peak Hour	0	0	0	0	0	0	0	0	0	0	1	0	1	0	0			

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Monument Hill Rd Palmer Divide Ave



Three-and-a-Half-Hour Count Summaries

Interval Start	Palmer Divide Ave Eastbound				Palmer Divide Ave Westbound				Monument Hill Rd Northbound				S Andrews RD Southbound				15-min Total	Rolling One Hour
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
3:45 PM	0	1	75	7	0	1	65	0	1	5	0	2	0	0	0	2	159	0
4:00 PM	0	1	80	6	0	2	58	0	0	19	0	1	0	0	0	0	167	0
4:15 PM	1	1	75	12	0	3	67	0	0	6	0	2	0	0	0	1	168	0
4:30 PM	0	0	93	7	0	3	45	0	0	8	0	1	0	0	0	0	157	651
Peak Hour	All	1	3	323	32	0	9	235	0	1	38	0	6	0	0	3	651	0
	HV	0	1	9	1	0	0	13	0	0	4	0	0	0	0	1	29	0
	HV%	0%	33%	3%	3%	-	0%	6%	-	0%	11%	-	0%	-	-	33%	4%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
3:45 PM	6	1	1	0	8	0	0	0	0	0	0	0	0	0	0
4:00 PM	1	4	3	0	8	0	0	1	0	1	0	0	0	0	0
4:15 PM	2	5	0	1	8	0	0	0	0	0	0	0	0	0	0
4:30 PM	2	3	0	0	5	0	0	0	0	0	0	0	0	0	0
Peak Hour	11	13	4	1	29	0	0	1	0	1	0	0	0	0	0

Three-and-a-Half-Hour Count Summaries																			
Interval Start		Palmer Divide Ave				Palmer Divide Ave				Monument Hill Rd				S Andrews RD				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	1	58	13	0	6	46	0	0	3	1	0	0	1	0	3	132	0
2:45 PM		0	1	53	10	0	9	43	0	0	8	0	5	0	0	0	0	129	0
3:00 PM		0	1	64	5	0	6	52	2	0	15	0	24	1	0	0	3	173	0
3:15 PM		0	0	74	7	0	2	65	0	0	10	0	3	0	0	0	1	162	596
3:30 PM		0	0	72	3	0	1	59	0	0	8	0	7	0	0	0	0	150	614
3:45 PM		0	1	75	7	0	1	65	0	1	5	0	2	0	0	0	2	159	644
4:00 PM		0	1	80	6	0	2	58	0	0	19	0	1	0	0	0	0	167	638
4:15 PM		1	1	75	12	0	3	67	0	0	6	0	2	0	0	0	1	168	644
4:30 PM		0	0	93	7	0	3	45	0	0	8	0	1	0	0	0	0	157	651
4:45 PM		0	0	88	9	0	1	49	0	0	4	1	6	0	0	0	0	158	650
5:00 PM		0	0	88	11	0	3	43	0	0	9	0	2	0	1	1	0	158	641
5:15 PM		0	0	89	11	0	9	52	1	0	3	0	6	0	0	0	0	171	644
5:30 PM		0	0	80	6	0	2	41	1	0	12	0	4	0	0	0	0	146	633
5:45 PM		0	0	80	12	0	2	55	0	0	3	0	5	0	0	0	0	157	632
Count Total		1	6	1,069	119	0	50	740	4	1	113	2	68	1	2	1	10	2,187	0
Peak Hour	All	1	3	323	32	0	9	235	0	1	38	0	6	0	0	0	3	651	0
	HV	0	1	9	1	0	0	13	0	0	4	0	0	0	0	0	1	29	0
	HV%	0%	33%	3%	3%	-	0%	6%	-	0%	11%	-	0%	-	-	-	33%	4%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start		Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)							
		EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total			
2:30 PM		2	5	1	2	10	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM		3	1	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM		4	1	0	0	5	0	0	0	0	0	0	0	0	0	0	0	0	0
3:15 PM		2	4	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0
3:30 PM		2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0
3:45 PM		6	1	1	0	8	0	0	0	0	0	0	0	0	0	0	0	0	0
4:00 PM		1	4	3	0	8	0	0	1	0	1	0	1	0	0	0	0	0	0
4:15 PM		2	5	0	1	8	0	0	0	0	0	0	0	0	0	0	0	0	0
4:30 PM		2	3	0	0	5	0	0	0	0	0	0	0	0	0	0	0	0	0
4:45 PM		0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0
5:00 PM		0	3	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0
5:15 PM		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM		1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0
5:45 PM		0	0	0	0	0	0	1	0	0	1	0	1	0	0	0	0	0	0
Count Total		25	28	5	3	61	0	1	1	0	2	0	0	0	0	0	0	0	0
Peak Hour		11	13	4	1	29	0	0	1	0	1	0	0	0	0	0	0	0	0

Three-and-a-Half-Hour Count Summaries - Heavy Vehicles																		
Interval Start	Palmer Divide Ave				Palmer Divide Ave				Monument Hill Rd				S Andrews RD				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM	0	0	2	0	0	0	5	0	0	0	1	0	0	0	0	2	10	0
2:45 PM	0	0	3	0	0	0	1	0	0	0	0	0	0	0	0	0	4	0
3:00 PM	0	0	4	0	0	0	1	0	0	0	0	0	0	0	0	0	5	0
3:15 PM	0	0	1	1	0	0	4	0	0	0	0	0	0	0	0	0	6	25
3:30 PM	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2	17
3:45 PM	0	0	5	1	0	0	1	0	0	1	0	0	0	0	0	0	8	21
4:00 PM	0	1	0	0	0	0	4	0	0	3	0	0	0	0	0	0	8	24
4:15 PM	0	0	2	0	0	0	5	0	0	0	0	0	0	0	0	1	8	26
4:30 PM	0	0	2	0	0	0	3	0	0	0	0	0	0	0	0	0	5	29
4:45 PM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1	22
5:00 PM	0	0	0	0	0	0	3	0	0	0	0	0	0	0	0	0	3	17
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	9
5:30 PM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	5
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
Count Total	0	1	22	2	0	0	28	0	0	4	1	0	0	0	0	3	61	0
Peak Hour	0	1	9	1	0	0	13	0	0	4	0	0	0	0	0	1	29	0

Three-and-a-Half-Hour Count Summaries - Bikes																		
Interval Start	Palmer Divide Ave				Palmer Divide Ave				Monument Hill Rd				S Andrews RD				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	LT	TH	RT		LT	TH	RT		LT	TH	RT		LT	TH	RT			
2:30 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
2:45 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
3:00 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
3:15 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
3:30 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
3:45 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
4:00 PM	0	0	0		0	0	0		0	1	0		0	0	0		1	1
4:15 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	1
4:30 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	1
4:45 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	1
5:00 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
5:15 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
5:30 PM	0	0	0		0	0	0		0	0	0		0	0	0		0	0
5:45 PM	0	0	0		0	0	1		0	0	0		0	0	0		1	1
Count Total	0	0	0		0	0	1		0	1	0		0	0	0		2	0
Peak Hour	0	0	0		0	0	0		0	1	0		0	0	0		1	0



Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Monument Hill Rd Misty Acres Blvd



Peak Hour

Date: 09/07/2022
Count Period: 7:00 AM to 9:00 AM
Peak Hour: 7:00 AM to 8:00 AM



	HV %:	PHF
EB	-	-
WB	0.3%	0.63
NB	0.7%	0.52
SB	1.4%	0.42
TOTAL	0.7%	0.56

Two-Hour Count Summaries

Interval Start		n/a				Misty Acres Blvd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	0	0	0	0	51	0	10	0	0	8	74	0	4	15	0	162	0
7:15 AM		0	0	0	0	0	92	0	10	0	0	14	129	0	32	52	0	329	0
7:30 AM		0	0	0	0	0	110	0	11	0	0	10	40	0	6	18	0	195	0
7:45 AM		0	0	0	0	0	19	0	2	0	0	6	15	0	1	13	0	56	742
8:00 AM		0	0	0	0	0	18	0	1	0	0	4	18	0	1	7	0	49	629
8:15 AM		0	0	0	0	0	18	0	0	0	0	8	10	0	3	12	0	51	351
8:30 AM		0	0	0	0	0	29	0	3	0	0	4	16	0	1	6	0	59	215
8:45 AM		0	0	0	0	0	27	0	1	0	0	8	29	0	3	6	0	74	233
Count Total		0	0	0	0	0	364	0	38	0	0	62	331	0	51	129	0	975	0
Peak Hour	All	0	0	0	0	0	272	0	33	0	0	38	258	0	43	98	0	742	0
	HV	0	0	0	0	0	0	0	1	0	0	2	0	0	0	2	0	5	0
	HV%	-	-	-	-	-	0%	-	3%	-	-	5%	0%	-	0%	2%	-	1%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
7:15 AM	0	0	1	1	2	0	0	0	1	1	0	0	0	0	0
7:30 AM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0
8:00 AM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
8:15 AM	0	1	2	2	5	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	3	1	0	4	0	0	1	0	1	0	0	0	0	0
Count Total	0	5	7	4	16	0	0	1	1	2	0	0	0	0	0
Peak Hr	0	1	2	2	5	0	0	0	1	1	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																		
Interval Start	n/a				Misty Acres Blvd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1	0
7:15 AM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	2	0
7:30 AM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	5
8:00 AM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1	5
8:15 AM	0	0	0	0	0	1	0	0	0	0	1	1	0	1	1	0	5	8
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	8
8:45 AM	0	0	0	0	0	3	0	0	0	0	0	1	0	0	0	0	4	11
Count Total	0	0	0	0	0	4	0	1	0	0	4	3	0	1	3	0	16	0
Peak Hour	0	0	0	0	0	0	0	1	0	0	2	0	0	0	2	0	5	0


Two-Hour Count Summaries - Bikes																		
Interval Start	n/a			Misty Acres Blvd			Monument Hill Rd			Monument Hill Rd			15-min Total	Rolling One Hour				
	Eastbound			Westbound			Northbound			Southbound								
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT						
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
7:15 AM	0	0	0	0	0	0	0	0	0	0	1	0	1	0				
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1				
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1				
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:45 AM	0	0	0	0	0	0	0	1	0	0	0	0	1	1				
Count Total	0	0	0	0	0	0	0	1	0	0	1	0	2	0				
Peak Hour	0	0	0	0	0	0	0	0	0	0	1	0	1	0				

Note: U-Turn volumes for bikes are included in Left-Turn, if any.


Monument Hill Rd Misty Acres Blvd



Peak Hour



Date: 09/07/2022
Count Period: 2:30 PM to 6:00 PM
Peak Hour: 2:30 PM to 3:30 PM



	HV %:	PHF
EB	-	-
WB	0.4%	0.57
NB	1.2%	0.84
SB	1.4%	0.71
TOTAL	0.9%	0.72

Three-and-a-Half-Hour Count Summaries

Interval Start		n/a				Misty Acres Blvd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	0	0	0	1	30	0	1	0	0	5	61	0	9	16	0	123	0
2:45 PM		0	0	0	0	0	52	0	5	0	0	10	53	0	6	16	0	142	0
3:00 PM		0	0	0	0	1	98	0	10	0	0	27	46	0	4	11	0	197	0
3:15 PM		0	0	0	0	0	46	0	5	0	0	18	26	0	2	7	0	104	566
Peak Hour	All	0	0	0	0	2	226	0	21	0	0	60	186	0	21	50	0	566	0
	HV	0	0	0	0	0	0	0	1	0	0	2	1	0	1	0	0	5	0
	HV%	-	-	-	-	0%	0%	-	5%	-	-	3%	1%	-	5%	0%	-	1%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
2:30 PM	0	0	1	1	2	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
Peak Hour	0	1	3	1	5	0	0	0	0	0	0	0	0	0	0

Three-and-a-Half-Hour Count Summaries																			
Interval Start		n/a				Misty Acres Blvd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
2:30 PM	0	0	0	0	1	30	0	1	0	0	5	61	0	9	16	0	123	0	
2:45 PM	0	0	0	0	0	52	0	5	0	0	10	53	0	6	16	0	142	0	
3:00 PM	0	0	0	0	1	98	0	10	0	0	27	46	0	4	11	0	197	0	
3:15 PM	0	0	0	0	0	46	0	5	0	0	18	26	0	2	7	0	104	566	
3:30 PM	0	0	0	0	0	30	0	2	0	0	13	23	0	0	6	0	74	517	
3:45 PM	0	0	0	0	0	17	0	1	0	0	7	14	0	1	9	0	49	424	
4:00 PM	0	0	0	0	0	18	0	0	0	0	24	29	0	0	5	0	76	303	
4:15 PM	0	0	0	0	0	25	0	0	0	0	15	27	0	1	17	0	85	284	
4:30 PM	0	0	0	0	0	13	0	1	0	0	13	20	0	0	13	0	60	270	
4:45 PM	0	0	0	0	0	18	0	1	0	0	14	25	0	0	10	0	68	289	
5:00 PM	0	0	0	0	0	14	0	0	0	0	12	22	0	1	14	0	63	276	
5:15 PM	0	0	0	0	0	20	0	0	0	0	16	23	0	1	17	0	77	268	
5:30 PM	0	0	0	0	0	20	0	1	0	0	15	23	0	3	9	0	71	279	
5:45 PM	0	0	0	0	0	19	0	0	0	0	12	18	0	1	10	0	60	271	
Count Total		0	0	0	0	2	420	0	27	0	0	201	410	0	29	160	0	1,249	0
Peak Hour	All	0	0	0	0	2	226	0	21	0	0	60	186	0	21	50	0	566	0
	HV	0	0	0	0	0	0	0	1	0	0	2	1	0	1	0	0	5	0
	HV%	-	-	-	-	0%	0%	-	5%	-	-	3%	1%	-	5%	0%	-	1%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start		Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)							
		EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total			
2:30 PM	0	0	1	1	2	0	0	0	0	0	0	0	0	0	0	0	0	0	
2:45 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:00 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:15 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:45 PM	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	
4:00 PM	0	0	3	1	4	0	0	0	0	0	0	0	0	0	0	0	0	0	
4:15 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Count Total		0	2	8	2	12	0	0	0	0	0	0	0	0	0	0	0	0	
Peak Hr		0	1	3	1	5	0	0	0	0	0	0	0	0	0	0	0	0	

Three-and-a-Half-Hour Count Summaries - Heavy Vehicles

Interval Start	n/a				Misty Acres Blvd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0	2	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1	0
3:15 PM	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1	5
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3
3:45 PM	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	2	4
4:00 PM	0	0	0	0	0	0	0	0	0	0	3	0	0	0	1	0	4	7
4:15 PM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1	7
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	7
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	0	0	0	0	0	1	0	1	0	0	6	2	0	1	1	0	12	0
Peak Hour	0	0	0	0	0	0	0	1	0	0	2	1	0	1	0	0	5	0

Three-and-a-Half-Hour Count Summaries - Bikes

Interval Start	n/a			Misty Acres Blvd			Monument Hill Rd			Monument Hill Rd			15-min Total	Rolling One Hour
	Eastbound			Westbound			Northbound			Southbound				
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0



Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Monument Hill Rd Deer Creek Rd



Peak Hour

Date: 09/07/2022
Count Period: 7:00 AM to 9:00 AM
Peak Hour: 7:00 AM to 8:00 AM



	HV %:	PHF
EB	-	-
WB	2.2%	0.43
NB	3.9%	0.58
SB	2.9%	0.66
TOTAL	3.2%	0.57

Two-Hour Count Summaries

Interval Start		N/A				Deer Creek Rd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	0	0	0	0	5	0	33	0	0	83	16	0	24	43	0	204	0
7:15 AM		0	0	0	0	0	6	0	74	0	0	141	3	0	21	111	0	356	0
7:30 AM		0	0	0	0	0	1	0	11	0	0	48	7	0	14	102	0	183	0
7:45 AM		0	0	0	0	0	4	0	2	0	0	19	15	0	8	25	0	73	816
8:00 AM		0	0	0	0	0	3	0	1	0	0	13	3	0	2	26	0	48	660
8:15 AM		0	0	0	0	0	6	0	3	0	0	16	5	0	6	22	0	58	362
8:30 AM		0	0	0	0	0	4	0	5	0	0	22	6	0	2	34	0	73	252
8:45 AM		0	0	0	0	0	5	0	4	0	0	59	11	0	6	20	0	105	284
Count Total		0	0	0	0	0	34	0	133	0	0	401	66	0	83	383	0	1,100	0
Peak Hour	All	0	0	0	0	0	16	0	120	0	0	291	41	0	67	281	0	816	0
	HV	0	0	0	0	0	2	0	1	0	0	13	0	0	0	10	0	26	0
	HV%	-	-	-	-	-	13%	-	1%	-	-	4%	0%	-	0%	4%	-	3%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	0	2	5	2	9	0	0	0	0	0	0	0	0	0	0
7:15 AM	0	0	7	7	14	0	0	0	1	1	0	0	0	0	0
7:30 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	1	1	2	0	0	0	0	0	0	0	0	0	0
8:00 AM	0	1	0	1	2	0	0	0	0	0	0	0	0	0	0
8:15 AM	0	0	1	1	2	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	3	0	3	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	0	2	2	4	0	0	0	0	0	1	1	1	0	3
Count Total	0	4	19	14	37	0	0	0	1	1	1	1	1	0	3
Peak Hr	0	3	13	10	26	0	0	0	1	1	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																			
Interval Start	N/A				Deer Creek Rd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour	
	Eastbound				Westbound				Northbound				Southbound						
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
7:00 AM	0	0	0	0	0	2	0	0	0	0	0	5	0	0	0	2	0	9	0
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	7	0	0	0	7	0	14	0
7:30 AM	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	2	26
8:00 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0	2	19
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	2	7
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	3	9
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	1	1	0	2	0	0	4	11
Count Total	0	0	0	0	0	3	0	1	0	0	18	1	0	2	12	0	0	37	0
Peak Hour	0	0	0	0	0	2	0	1	0	0	13	0	0	0	10	0	0	26	0


Two-Hour Count Summaries - Bikes																			
Interval Start	N/A			Deer Creek Rd			Monument Hill Rd			Monument Hill Rd			15-min Total	Rolling One Hour					
	Eastbound			Westbound			Northbound			Southbound									
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT							
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	0	1	0
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	0	1	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	0	1	0

Note: U-Turn volumes for bikes are included in Left-Turn, if any.


Monument Hill Rd Deer Creek Rd



Peak Hour



	HV %:	PHF
EB	-	-
WB	2.4%	0.70
NB	5.3%	0.79
SB	2.3%	0.54
TOTAL	3.3%	0.73



Three-and-a-Half-Hour Count Summaries

Interval Start		N/A				Deer Creek Rd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	0	0	0	0	8	0	22	0	0	74	3	0	17	29	0	153	0
2:45 PM		0	0	0	0	0	3	0	18	0	0	70	7	0	23	71	0	192	0
3:00 PM		0	0	0	0	0	10	0	10	0	0	39	4	0	34	149	0	246	0
3:15 PM		0	0	0	0	0	5	0	8	0	0	37	9	0	7	66	0	132	723
Peak Hour	All	0	0	0	0	0	26	0	58	0	0	220	23	0	81	315	0	723	0
	HV	0	0	0	0	0	1	0	1	0	0	11	2	0	1	8	0	24	0
	HV%	-	-	-	-	-	4%	-	2%	-	-	5%	9%	-	1%	3%	-	3%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
2:30 PM	0	1	5	0	6	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	1	7	2	10	0	0	0	0	0	1	0	0	0	1
3:00 PM	0	0	0	7	7	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
Peak Hour	0	2	13	9	24	0	0	0	0	0	1	0	0	0	1

Three-and-a-Half-Hour Count Summaries																			
Interval Start		N/A				Deer Creek Rd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	0	0	0	0	8	0	22	0	0	74	3	0	17	29	0	153	0
2:45 PM		0	0	0	0	0	3	0	18	0	0	70	7	0	23	71	0	192	0
3:00 PM		0	0	0	0	0	10	0	10	0	0	39	4	0	34	149	0	246	0
3:15 PM		0	0	0	0	0	5	0	8	0	0	37	9	0	7	66	0	132	723
3:30 PM		0	0	0	0	0	13	0	4	0	0	40	9	0	9	35	0	110	680
3:45 PM		0	0	0	0	0	7	0	6	0	0	19	4	0	2	24	0	62	550
4:00 PM		0	0	0	0	0	8	0	7	0	0	47	3	0	2	23	0	90	394
4:15 PM		0	0	0	0	0	10	0	5	0	0	42	10	0	11	32	0	110	372
4:30 PM		0	0	0	0	0	13	0	9	0	0	30	2	0	10	25	0	89	351
4:45 PM		0	0	0	0	0	12	0	4	0	0	41	5	0	6	30	0	98	387
5:00 PM		0	0	0	0	0	11	0	8	0	0	32	2	0	9	35	0	97	394
5:15 PM		0	0	0	0	0	7	0	7	0	0	45	4	0	11	28	0	102	386
5:30 PM		0	0	0	0	0	7	0	7	0	0	45	4	0	12	45	0	120	417
5:45 PM		0	0	0	0	0	8	0	4	0	0	28	5	0	12	36	0	93	412
Count Total		0	0	0	0	0	122	0	119	0	0	589	71	0	165	628	0	1,694	0
Peak Hour	All	0	0	0	0	0	26	0	58	0	0	220	23	0	81	315	0	723	0
	HV	0	0	0	0	0	1	0	1	0	0	11	2	0	1	8	0	24	0
	HV%	-	-	-	-	-	4%	-	2%	-	-	5%	9%	-	1%	3%	-	3%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)								
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total				
2:30 PM	0	1	5	0	6	0	0	0	0	0	0	0	0	0	0				
2:45 PM	0	1	7	2	10	0	0	0	0	0	1	0	0	0	1				
3:00 PM	0	0	0	7	7	0	0	0	0	0	0	0	0	0	0				
3:15 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0				
3:30 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0				
3:45 PM	0	2	1	0	3	0	0	0	0	0	0	0	0	0	0				
4:00 PM	0	2	0	0	2	0	0	0	1	1	0	0	0	0	0				
4:15 PM	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0				
4:30 PM	0	1	1	0	2	0	0	0	0	0	0	0	0	0	0				
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
5:00 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0				
5:15 PM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0				
5:30 PM	0	2	1	0	3	0	0	0	0	0	0	0	0	0	0				
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
Count Total	0	9	19	10	38	0	0	0	1	1	1	0	0	0	1				
Peak Hr	0	2	13	9	24	0	0	0	0	0	1	0	0	0	1				

Three-and-a-Half-Hour Count Summaries - Heavy Vehicles


Interval Start	N/A				Deer Creek Rd				Monument Hill Rd				Monument Hill Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	1	0	0	5	0	0	0	0	0	6	0
2:45 PM	0	0	0	0	0	1	0	0	0	0	6	1	0	0	2	0	10	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	6	0	7	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	24
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	19
3:45 PM	0	0	0	0	0	0	0	2	0	0	0	1	0	0	0	0	3	12
4:00 PM	0	0	0	0	0	0	0	2	0	0	0	0	0	0	0	0	2	7
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	7
4:30 PM	0	0	0	0	0	1	0	0	0	0	0	1	0	0	0	0	2	8
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	4
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	4
5:30 PM	0	0	0	0	0	2	0	0	0	0	0	1	0	0	0	0	3	5
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5
Count Total	0	0	0	0	0	4	0	5	0	0	11	8	0	1	9	0	38	0
Peak Hour	0	0	0	0	0	1	0	1	0	0	11	2	0	1	8	0	24	0

Three-and-a-Half-Hour Count Summaries - Bikes

Interval Start	N/A			Deer Creek Rd			Monument Hill Rd			Monument Hill Rd			15-min Total	Rolling One Hour
	Eastbound			Westbound			Northbound			Southbound				
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:00 PM	0	0	0	0	0	0	0	0	0	0	1	0	1	1
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	0	0	0	0	0	0	0	0	0	0	1	0	1	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Base Camp Rd Deer Creek Rd



	HV %:	PHF
EB	1.0%	0.67
WB	1.6%	0.41
NB	-	-
SB	7.7%	0.54
TOTAL	1.7%	0.55

Two-Hour Count Summaries

Interval Start		Deer Creek Rd				Deer Creek Rd				n/a				Base Camp Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	3	33	0	0	0	29	1	0	0	0	0	0	0	0	3	69	0
7:15 AM		0	4	21	0	0	0	74	2	0	0	0	0	0	0	0	6	107	0
7:30 AM		0	5	16	0	0	0	15	1	0	0	0	0	0	0	0	1	38	0
7:45 AM		0	4	10	0	0	0	4	0	0	0	0	0	0	0	0	3	21	235
8:00 AM		0	3	2	0	0	0	5	1	0	0	0	0	0	0	0	1	12	178
8:15 AM		0	6	2	0	0	0	2	2	0	0	0	0	0	3	0	4	19	90
8:30 AM		0	5	2	0	0	0	3	2	0	0	0	0	0	1	0	3	16	68
8:45 AM		0	9	1	0	0	0	7	1	0	0	0	0	0	0	0	3	21	68
Count Total		0	39	87	0	0	0	139	10	0	0	0	0	0	4	0	24	303	0
Peak Hour	All	0	16	80	0	0	0	122	4	0	0	0	0	0	0	0	13	235	0
	HV	0	0	1	0	0	0	2	0	0	0	0	0	0	0	0	1	4	0
	HV%	-	0%	1%	-	-	-	2%	0%	-	-	-	-	-	-	-	8%	2%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	0	1	0	1	2	0	0	0	0	0	0	0	0	0	0
7:15 AM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0
7:30 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:00 AM	0	0	0	0	0	0	2	0	0	2	0	0	0	0	0
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	1	2	0	1	4	0	2	0	0	2	0	0	0	0	0
Peak Hr	1	2	0	1	4	0	0	0	0	0	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																		
Interval Start	Deer Creek Rd				Deer Creek Rd				n/a				Base Camp Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1	2	0
7:15 AM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0
7:30 AM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	0	0	1	0	0	0	2	0	0	0	0	0	0	0	0	1	4	0
Peak Hour	0	0	1	0	0	0	2	0	0	0	0	0	0	0	0	1	4	0


Two-Hour Count Summaries - Bikes																	
Interval Start	Deer Creek Rd			Deer Creek Rd			n/a			Base Camp Rd			15-min Total	Rolling One Hour			
	Eastbound			Westbound			Northbound			Southbound							
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT					
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
8:00 AM	0	0	0	0	0	2	0	0	0	0	0	0	2	2	2		
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2		
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2		
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2		
Count Total	0	0	0	0	0	2	0	0	0	0	0	0	2	0	0		
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Base Camp Rd Deer Creek Rd



Date: 09/07/2022
Count Period: 2:30 PM to 6:00 PM
Peak Hour: 2:30 PM to 3:30 PM



	HV %:	PHF
EB	2.0%	0.57
WB	1.6%	0.70
NB	-	-
SB	3.3%	0.54
TOTAL	2.1%	0.69

Three-and-a-Half-Hour Count Summaries

Interval Start		Deer Creek Rd				Deer Creek Rd				n/a				Base Camp Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	2	17	0	0	0	19	2	0	0	0	0	0	4	0	3	47	0
2:45 PM		0	6	19	0	0	0	21	2	0	0	0	0	0	0	0	2	50	0
3:00 PM		0	6	38	0	0	0	7	5	0	0	0	0	0	4	0	10	70	0
3:15 PM		0	4	8	0	0	0	6	2	0	0	0	0	0	3	0	4	27	194
Peak Hour	All	0	18	82	0	0	0	53	11	0	0	0	0	0	11	0	19	194	0
	HV	0	0	2	0	0	0	1	0	0	0	0	0	0	0	0	1	4	0
	HV%	-	0%	2%	-	-	-	2%	0%	-	-	-	-	-	0%	-	5%	2%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
2:30 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0
2:45 PM	1	0	0	1	2	0	0	0	0	0	0	0	0	0	0
3:00 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour	2	1	0	1	4	0	0	0	0	0	0	0	0	0	0

Three-and-a-Half-Hour Count Summaries																			
Interval Start		Deer Creek Rd				Deer Creek Rd				n/a				Base Camp Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
2:30 PM	0	2	17	0	0	0	19	2	0	0	0	0	0	4	0	3	47	0	
2:45 PM	0	6	19	0	0	0	21	2	0	0	0	0	0	0	0	2	50	0	
3:00 PM	0	6	38	0	0	0	7	5	0	0	0	0	0	4	0	10	70	0	
3:15 PM	0	4	8	0	0	0	6	2	0	0	0	0	0	3	0	4	27	194	
3:30 PM	0	6	11	0	0	0	8	3	0	0	0	0	0	3	0	6	37	184	
3:45 PM	0	3	4	0	0	0	9	3	0	0	0	0	0	1	0	6	26	160	
4:00 PM	0	1	3	0	0	0	8	4	0	0	0	0	0	4	0	7	27	117	
4:15 PM	0	8	10	0	0	0	8	1	0	0	0	0	0	3	0	5	35	125	
4:30 PM	0	0	7	0	0	0	8	1	0	0	0	0	0	4	0	11	31	119	
4:45 PM	0	4	11	0	0	0	7	0	0	0	0	0	0	2	0	13	37	130	
5:00 PM	0	3	10	0	0	0	8	2	0	0	0	0	0	1	0	9	33	136	
5:15 PM	0	4	8	0	0	0	6	1	0	0	0	0	0	1	0	4	24	125	
5:30 PM	0	5	14	0	0	0	8	2	0	0	0	0	0	1	0	5	35	129	
5:45 PM	0	1	9	0	0	0	7	2	0	0	0	0	0	1	0	3	23	115	
Count Total		0	53	169	0	0	0	130	30	0	0	0	0	0	32	0	88	502	0
Peak Hour	All	0	18	82	0	0	0	53	11	0	0	0	0	0	11	0	19	194	0
	HV	0	0	2	0	0	0	1	0	0	0	0	0	0	0	1	4	4	0
	HV%	-	0%	2%	-	-	-	2%	0%	-	-	-	-	-	0%	-	5%	2%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start		Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)							
		EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total			
2:30 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
2:45 PM	1	0	0	1	2	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:00 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:30 PM	2	0	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	
3:45 PM	1	2	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	
4:00 PM	0	2	0	0	2	1	1	0	1	3	0	0	0	0	0	0	0	0	
4:15 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	
4:30 PM	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
4:45 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:00 PM	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:30 PM	2	1	0	1	4	0	0	0	0	0	0	0	0	0	0	0	0	0	
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Count Total		9	6	0	3	18	1	1	0	2	4	0	0	0	0	0	0	0	
Peak Hr		2	1	0	1	4	0	0	0	0	0	0	0	0	0	0	0	0	

Three-and-a-Half-Hour Count Summaries - Heavy Vehicles

Interval Start	Deer Creek Rd				Deer Creek Rd				n/a				Base Camp Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0
2:45 PM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1	2	0
3:00 PM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
3:30 PM	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	2	5
3:45 PM	0	1	0	0	0	0	2	0	0	0	0	0	0	0	0	0	3	6
4:00 PM	0	0	0	0	0	0	2	0	0	0	0	0	0	0	0	0	2	7
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	7
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	6
4:45 PM	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	4
5:00 PM	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	3
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3
5:30 PM	0	1	1	0	0	0	1	0	0	0	0	0	0	0	0	1	4	6
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5
Count Total	0	3	6	0	0	0	6	0	0	0	0	0	0	0	0	3	18	0
Peak Hour	0	0	2	0	0	0	1	0	0	0	0	0	0	0	0	1	4	0

Three-and-a-Half-Hour Count Summaries - Bikes

Interval Start	Deer Creek Rd			Deer Creek Rd			n/a			Base Camp Rd			15-min Total	Rolling One Hour
	Eastbound			Westbound			Northbound			Southbound				
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:00 PM	1	0	0	0	0	1	0	0	0	0	0	1	3	3
4:15 PM	0	0	0	0	0	0	0	0	0	1	0	0	1	4
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	4
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	4
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	1	0	0	0	0	1	0	0	0	1	0	1	4	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Woodmoor Rd Deer Creek Rd




Peak Hour

Date: 09/07/2022

Count Period: 7:00 AM to 9:00 AM

Peak Hour: 7:00 AM to 8:00 AM



	HV %:	PHF
EB	1.4%	0.66
WB	0.0%	0.72
NB	0.9%	0.68
SB	1.5%	0.75
TOTAL	1.2%	0.76

Two-Hour Count Summaries

Interval Start		Deer Creek Rd				Deer Creek Rd				Woodmoor Rd				Woodmoor Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	2	0	24	0	13	5	0	0	18	8	1	0	0	59	15	145	0
7:15 AM		0	4	3	13	0	6	9	0	0	27	13	2	0	0	46	44	167	0
7:30 AM		0	5	3	5	0	10	3	0	0	6	13	0	0	0	45	10	100	0
7:45 AM		0	2	1	7	0	6	0	0	0	4	19	4	0	0	49	3	95	507
8:00 AM		0	1	0	2	0	8	0	0	0	14	18	0	0	1	34	3	81	443
8:15 AM		0	4	0	9	0	3	0	0	0	9	15	1	0	0	32	2	75	351
8:30 AM		0	1	0	3	0	11	0	0	0	7	18	3	0	1	50	5	99	350
8:45 AM		0	0	1	7	0	6	0	0	0	6	25	3	0	0	32	5	85	340
Count Total		0	19	8	70	0	63	17	0	0	91	129	14	0	2	347	87	847	0
Peak Hour	All	0	13	7	49	0	35	17	0	0	55	53	7	0	0	199	72	507	0
	HV	0	0	0	1	0	0	0	0	0	1	0	0	0	0	4	0	6	0
	HV%	-	0%	0%	2%	-	0%	0%	-	-	2%	0%	0%	-	-	2%	0%	1%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	0	0	0	2	2	0	2	0	0	2	0	0	0	0	0
7:15 AM	1	0	0	1	2	0	0	0	0	0	0	0	0	0	0
7:30 AM	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0
8:00 AM	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0
8:15 AM	2	0	0	1	3	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0
8:45 AM	0	1	1	1	3	0	0	0	0	0	0	0	0	0	0
Count Total	3	1	6	6	16	0	2	0	0	2	0	0	0	0	0
Peak Hour	1	0	1	4	6	0	2	0	0	2	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																			
Interval Start	Deer Creek Rd				Deer Creek Rd				Woodmoor Rd				Woodmoor Rd				15-min Total	Rolling One Hour	
	Eastbound				Westbound				Northbound				Southbound						
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	2	0
7:15 AM	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	1	0	2	0
7:30 AM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	6
8:00 AM	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	2	6
8:15 AM	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0	1	0	3	7
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	2	8
8:45 AM	0	0	0	0	0	1	0	0	0	0	0	1	0	0	0	1	0	3	10
Count Total	0	1	0	2	0	1	0	0	0	0	2	3	1	0	0	6	0	16	0
Peak Hour	0	0	0	1	0	0	0	0	0	0	1	0	0	0	0	4	0	6	0

Two-Hour Count Summaries - Bikes																		
Interval Start	Deer Creek Rd			Deer Creek Rd			Woodmoor Rd			Woodmoor Rd			15-min Total	Rolling One Hour				
	Eastbound			Westbound			Northbound			Southbound								
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT						
7:00 AM	0	0	0	2	0	0	0	0	0	0	0	0	2	0				
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	2				
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
Count Total	0	0	0	2	0	0	0	0	0	0	0	0	2	0				
Peak Hour	0	0	0	2	0	0	0	0	0	0	0	0	2	0				

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Woodmoor Rd Deer Creek Rd





Peak Hour

Date: 09/07/2022

Count Period: 2:30 PM to 6:00 PM

Peak Hour: 5:00 PM to 6:00 PM



	HV %	PHF
EB	1.4%	0.76
WB	5.3%	0.79
NB	1.2%	0.95
SB	4.0%	0.94
TOTAL	2.2%	0.96

Three-and-a-Half-Hour Count Summaries

Interval Start		Deer Creek Rd				Deer Creek Rd				Woodmoor Rd				Woodmoor Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
5:00 PM		1	5	4	12	0	3	1	0	0	6	47	8	0	0	36	4	127	0
5:15 PM		0	4	1	8	0	3	3	0	0	12	38	10	0	0	33	2	114	0
5:30 PM		0	5	2	5	0	5	0	0	0	20	40	7	0	1	36	3	124	0
5:45 PM		0	7	2	14	0	4	0	0	0	25	37	5	0	0	32	3	129	494
Peak Hour	All	1	21	9	39	0	15	4	0	0	63	162	30	0	1	137	12	494	0
	HV	0	0	0	1	0	1	0	0	0	1	2	0	0	0	6	0	11	0
	HV%	0%	0%	0%	3%	-	7%	0%	-	-	2%	1%	0%	-	0%	4%	0%	2%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
5:00 PM	1	1	1	0	3	0	0	0	0	0	0	0	0	1	1
5:15 PM	0	0	1	4	5	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	1	1	2	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	0	1	1	0	0	0	0	0	0	0	2	0	2
Peak Hour	1	1	3	6	11	0	0	0	0	0	0	0	2	1	3

Three-and-a-Half-Hour Count Summaries																			
Interval Start		Deer Creek Rd				Deer Creek Rd				Woodmoor Rd				Woodmoor Rd				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	5	0	18	0	11	1	0	1	17	27	8	0	1	27	13	129	0
2:45 PM		0	8	0	10	0	8	2	2	0	12	28	4	0	0	24	8	106	0
3:00 PM		0	20	9	18	0	3	1	0	0	7	25	9	0	0	23	5	120	0
3:15 PM		0	6	2	5	0	9	1	0	0	6	34	8	0	0	30	4	105	460
3:30 PM		0	4	2	11	0	5	1	0	0	4	27	9	0	1	28	2	94	425
3:45 PM		0	1	2	6	0	8	2	0	1	5	34	12	0	0	38	2	111	430
4:00 PM		0	3	0	14	0	4	2	0	0	7	59	10	0	0	29	3	131	441
4:15 PM		0	7	0	10	0	3	1	0	0	4	37	5	0	0	40	1	108	444
4:30 PM		0	3	1	8	0	7	2	0	0	4	28	9	0	1	35	5	103	453
4:45 PM		0	7	2	11	0	7	2	2	0	3	36	3	0	0	27	4	104	446
5:00 PM		1	5	4	12	0	3	1	0	0	6	47	8	0	0	36	4	127	442
5:15 PM		0	4	1	8	0	3	3	0	0	12	38	10	0	0	33	2	114	448
5:30 PM		0	5	2	5	0	5	0	0	0	20	40	7	0	1	36	3	124	469
5:45 PM		0	7	2	14	0	4	0	0	0	25	37	5	0	0	32	3	129	494
Count Total		1	85	27	150	0	80	19	4	2	132	497	107	0	4	438	59	1,605	0
Peak Hour	All	1	21	9	39	0	15	4	0	0	63	162	30	0	1	137	12	494	0
	HV	0	0	0	1	0	1	0	0	0	1	2	0	0	0	6	0	11	0
	HV%	0%	0%	0%	3%	-	7%	0%	-	-	2%	1%	0%	-	0%	4%	0%	2%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start		Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)							
		EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total			
2:30 PM		0	0	1	0	1	0	0	0	0	0	0	7	0	4	11			
2:45 PM		0	1	1	0	2	0	0	0	0	0	0	0	0	0	0			
3:00 PM		1	0	1	2	4	0	0	0	0	0	0	4	0	0	4			
3:15 PM		0	0	1	0	1	0	0	0	0	0	0	0	0	0	0			
3:30 PM		1	0	2	1	4	0	0	0	0	0	0	0	0	0	0			
3:45 PM		0	0	1	1	2	0	0	0	0	0	0	0	0	0	0			
4:00 PM		0	1	1	2	4	0	1	0	0	1	0	1	0	0	1			
4:15 PM		0	0	0	0	0	1	0	0	0	1	0	0	0	0	0			
4:30 PM		0	0	0	1	1	0	0	0	0	0	0	0	0	0	0			
4:45 PM		1	1	0	1	3	0	0	0	0	0	0	0	0	0	0			
5:00 PM		1	1	1	0	3	0	0	0	0	0	0	0	0	1	1			
5:15 PM		0	0	1	4	5	0	0	0	0	0	0	0	0	0	0			
5:30 PM		0	0	1	1	2	0	0	0	0	0	0	0	0	0	0			
5:45 PM		0	0	0	1	1	0	0	0	0	0	0	0	2	0	2			
Count Total		4	4	11	14	33	1	1	0	0	2	0	12	2	5	19			
Peak Hour		1	1	3	6	11	0	0	0	0	0	0	0	2	1	3			

Three-and-a-Half-Hour Count Summaries - Heavy Vehicles

Interval Start	Deer Creek Rd				Deer Creek Rd				Woodmoor Rd				Woodmoor Rd				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1	0
2:45 PM	0	0	0	0	0	1	0	0	0	0	1	0	0	0	0	0	2	0
3:00 PM	0	0	0	1	0	0	0	0	0	0	1	0	0	0	2	0	4	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1	8
3:30 PM	0	0	0	1	0	0	0	0	0	1	1	0	0	1	0	0	4	11
3:45 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1	2	11
4:00 PM	0	0	0	0	0	0	1	0	0	0	1	0	0	0	1	1	4	11
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	10
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	7
4:45 PM	0	0	0	1	0	0	0	1	0	0	0	0	0	0	1	0	3	8
5:00 PM	0	0	0	1	0	1	0	0	0	1	0	0	0	0	0	0	3	7
5:15 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	4	0	5	12
5:30 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	2	13
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	11
Count Total	0	0	0	4	0	2	1	1	0	4	7	0	0	1	11	2	33	0
Peak Hour	0	0	0	1	0	1	0	0	0	1	2	0	0	0	6	0	11	0

Three-and-a-Half-Hour Count Summaries - Bikes

Interval Start	Deer Creek Rd			Deer Creek Rd			Woodmoor Rd			Woodmoor Rd			15-min Total	Rolling One Hour
	Eastbound			Westbound			Northbound			Southbound				
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:00 PM	0	0	0	0	1	0	0	0	0	0	0	0	1	1
4:15 PM	0	1	0	0	0	0	0	0	0	0	0	0	1	2
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	2
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	2
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Count Total	0	1	0	0	1	0	0	0	0	0	0	0	2	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Woodmoor Dr Monument Hill Rd





Peak Hour

Date: 09/07/2022

Count Period: 7:00 AM to 9:00 AM

Peak Hour: 7:00 AM to 8:00 AM



	HV %:	PHF
EB	4.1%	0.58
WB	100.0%	0.25
NB	3.7%	0.62
SB	5.1%	0.65
TOTAL	4.3%	0.73

Two-Hour Count Summaries

Interval Start		Monument Hill Rd				Driveway				Woodmoor Dr				Woodmoor Dr				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	0	0	40	0	0	0	0	0	77	185	1	0	0	160	31	494	0
7:15 AM		0	1	0	101	0	0	0	0	0	120	71	5	0	1	139	26	464	0
7:30 AM		0	4	0	124	0	0	0	0	0	58	43	3	0	0	65	4	301	0
7:45 AM		0	1	2	22	0	1	0	0	0	32	50	10	0	0	66	2	186	1,445
8:00 AM		0	0	0	28	0	1	0	0	0	18	53	2	0	0	57	0	159	1,110
8:15 AM		0	1	0	24	0	0	0	0	0	20	40	4	0	0	57	1	147	793
8:30 AM		0	1	0	37	0	1	0	0	0	27	50	11	0	0	74	1	202	694
8:45 AM		0	1	0	22	0	0	0	0	0	64	56	4	0	0	71	1	219	727
Count Total		0	9	2	398	0	3	0	0	0	416	548	40	0	1	689	66	2,172	0
Peak Hour	All	0	6	2	287	0	1	0	0	0	287	349	19	0	1	430	63	1,445	0
	HV	0	0	0	12	0	1	0	0	0	3	20	1	0	0	16	9	62	0
	HV%	-	0%	0%	4%	-	100%	-	-	-	1%	6%	5%	-	0%	4%	14%	4%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	2	0	19	9	30	0	0	0	1	1	0	0	0	0	0
7:15 AM	8	0	3	13	24	0	0	0	0	0	0	0	0	0	0
7:30 AM	1	0	1	2	4	0	0	0	0	0	0	0	0	0	0
7:45 AM	1	1	1	1	4	0	0	0	0	0	0	0	0	0	0
8:00 AM	2	0	3	0	5	0	0	0	0	0	0	0	0	0	0
8:15 AM	1	0	1	2	4	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	3	1	4	0	0	1	0	1	0	0	0	0	0
8:45 AM	0	0	2	3	5	0	0	0	0	0	0	1	0	1	2
Count Total	15	1	33	31	80	0	0	1	1	2	0	1	0	1	2
Peak Hour	12	1	24	25	62	0	0	0	1	1	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																		
Interval Start	Monument Hill Rd				Driveway				Woodmoor Dr				Woodmoor Dr				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	0	0	2	0	0	0	0	0	1	18	0	0	0	5	4	30	0
7:15 AM	0	0	0	8	0	0	0	0	0	2	1	0	0	0	8	5	24	0
7:30 AM	0	0	0	1	0	0	0	0	0	0	1	0	0	0	2	0	4	0
7:45 AM	0	0	0	1	0	1	0	0	0	0	0	1	0	0	1	0	4	62
8:00 AM	0	0	0	2	0	0	0	0	0	1	2	0	0	0	0	0	5	37
8:15 AM	0	1	0	0	0	0	0	0	0	1	0	0	0	0	2	0	4	17
8:30 AM	0	0	0	0	0	0	0	0	0	2	1	0	0	0	1	0	4	17
8:45 AM	0	0	0	0	0	0	0	0	0	0	2	0	0	0	3	0	5	18
Count Total	0	1	0	14	0	1	0	0	0	7	25	1	0	0	22	9	80	0
Peak Hour	0	0	0	12	0	1	0	0	0	3	20	1	0	0	16	9	62	0

Two-Hour Count Summaries - Bikes																		
Interval Start	Monument Hill Rd			Driveway			Woodmoor Dr			Woodmoor Dr			15-min Total	Rolling One Hour				
	Eastbound			Westbound			Northbound			Southbound								
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT						
7:00 AM	0	0	0	0	0	0	0	0	0	0	1	0	1	0				
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1				
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
8:30 AM	0	0	0	0	0	0	0	0	0	1	0	0	0	1				
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	1				
Count Total	0	0	0	0	0	0	0	0	0	1	0	0	0	2				
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	1	0				

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Woodmoor Dr Monument Hill Rd



Three-and-a-Half-Hour Count Summaries

Interval Start		Monument Hill Rd				Driveway				Woodmoor Dr				Woodmoor Dr				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	0	1	34	0	1	0	0	0	63	95	2	0	0	122	12	330	0
2:45 PM		0	1	0	42	0	4	0	1	0	71	70	3	0	1	125	13	331	0
3:00 PM		0	0	0	187	0	5	0	0	0	41	69	1	0	1	86	2	392	0
3:15 PM		0	0	0	78	0	3	1	0	0	44	79	1	0	0	66	1	273	1,326
Peak Hour	All	0	1	1	341	0	13	1	1	0	219	313	7	0	2	399	28	1,326	0
	HV	0	0	0	9	0	0	0	0	0	3	3	0	0	0	18	9	42	0
	HV%	-	0%	0%	3%	-	0%	0%	0%	-	1%	1%	0%	-	0%	5%	32%	3%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
2:30 PM	0	0	1	10	11	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	2	15	17	0	0	0	0	0	0	1	0	0	1
3:00 PM	9	0	3	1	13	0	0	0	0	0	0	1	0	0	1
3:15 PM	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0
Peak Hour	9	0	6	27	42	0	0	0	0	0	0	2	0	0	2

Three-and-a-Half-Hour Count Summaries																			
Interval Start		Monument Hill Rd				Driveway				Woodmoor Dr				Woodmoor Dr				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:30 PM		0	0	1	34	0	1	0	0	0	63	95	2	0	0	122	12	330	0
2:45 PM		0	1	0	42	0	4	0	1	0	71	70	3	0	1	125	13	331	0
3:00 PM		0	0	0	187	0	5	0	0	0	41	69	1	0	1	86	2	392	0
3:15 PM		0	0	0	78	0	3	1	0	0	44	79	1	0	0	66	1	273	1,326
3:30 PM		0	2	0	44	0	2	0	0	0	51	59	2	0	0	77	1	238	1,234
3:45 PM		0	0	0	38	0	2	0	0	0	21	80	1	0	0	75	0	217	1,120
4:00 PM		0	0	0	30	0	3	0	0	0	47	96	0	0	0	75	2	253	981
4:15 PM		0	0	1	39	0	4	1	1	0	47	62	0	0	0	84	3	242	950
4:30 PM		0	1	0	29	0	4	0	1	0	50	69	2	0	0	85	3	244	956
4:45 PM		0	0	0	48	0	4	0	1	0	30	69	3	0	0	67	0	222	961
5:00 PM		0	0	0	43	0	0	0	0	0	34	88	1	0	0	117	1	284	992
5:15 PM		0	0	1	28	0	7	1	0	0	44	85	0	0	0	84	6	256	1,006
5:30 PM		0	0	0	58	0	5	0	1	0	50	69	1	0	0	66	1	251	1,013
5:45 PM		0	0	1	32	0	3	0	1	0	40	91	3	0	0	69	1	241	1,032
Count Total		0	4	4	730	0	47	3	6	0	633	1,081	20	0	2	1,198	46	3,774	0
Peak Hour	All	0	1	1	341	0	13	1	1	0	219	313	7	0	2	399	28	1,326	0
	HV	0	0	0	9	0	0	0	0	0	3	3	0	0	0	18	9	42	0
	HV%	-	0%	0%	3%	-	0%	0%	0%	-	1%	1%	0%	-	0%	5%	32%	3%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start		Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)							
		EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total			
2:30 PM		0	0	1	10	11	0	0	0	0	0	0	0	0	0	0	0	0	
2:45 PM		0	0	2	15	17	0	0	0	0	0	0	0	1	0	0	0	1	
3:00 PM		9	0	3	1	13	0	0	0	0	0	0	0	1	0	0	0	1	
3:15 PM		0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	0	0	
3:30 PM		0	0	4	1	5	0	0	0	0	0	0	0	0	0	0	0	0	
3:45 PM		0	1	2	0	3	0	0	0	0	0	0	0	0	0	0	0	0	
4:00 PM		0	0	3	3	6	0	0	0	0	0	0	0	0	0	0	0	0	
4:15 PM		1	0	1	0	2	0	0	0	0	0	0	0	0	0	0	0	0	
4:30 PM		1	0	3	0	4	0	0	0	0	0	0	0	0	0	0	0	0	
4:45 PM		0	0	1	2	3	0	0	0	0	0	0	0	0	0	0	0	0	
5:00 PM		0	0	2	1	3	0	0	0	0	0	0	0	0	0	0	0	0	
5:15 PM		0	0	2	4	6	0	0	0	0	0	0	0	0	0	0	0	0	
5:30 PM		3	0	3	1	7	0	0	0	1	1	0	0	0	0	0	0	0	
5:45 PM		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Count Total		14	1	27	39	81	0	0	0	1	1	0	2	0	0	0	0	2	
Peak Hour		9	0	6	27	42	0	0	0	0	0	0	2	0	0	0	2		


Three-and-a-Half-Hour Count Summaries - Heavy Vehicles

Interval Start	Monument Hill Rd				Driveway				Woodmoor Dr				Woodmoor Dr				15-min Total	Rolling One Hour	
	Eastbound				Westbound				Northbound				Southbound						
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
2:30 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	10	0	11	0
2:45 PM	0	0	0	0	0	0	0	0	0	2	0	0	0	0	0	6	9	17	0
3:00 PM	0	0	0	9	0	0	0	0	0	0	3	0	0	0	0	1	0	13	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	1	42
3:30 PM	0	0	0	0	0	0	0	0	0	2	2	0	0	0	0	1	0	5	36
3:45 PM	0	0	0	0	0	1	0	0	0	1	1	0	0	0	0	0	0	3	22
4:00 PM	0	0	0	0	0	0	0	0	0	0	3	0	0	0	3	0	0	6	15
4:15 PM	0	0	0	1	0	0	0	0	0	1	0	0	0	0	0	0	0	2	16
4:30 PM	0	0	0	1	0	0	0	0	0	1	2	0	0	0	0	0	0	4	15
4:45 PM	0	0	0	0	0	0	0	0	0	1	0	0	0	0	2	0	0	3	15
5:00 PM	0	0	0	0	0	0	0	0	0	1	1	0	0	0	1	0	0	3	12
5:15 PM	0	0	0	0	0	0	0	0	0	1	1	0	0	0	4	0	0	6	16
5:30 PM	0	0	0	3	0	0	0	0	0	1	2	0	0	0	1	0	0	7	19
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	16
Count Total	0	0	0	14	0	1	0	0	0	12	15	0	0	0	30	9	0	81	0
Peak Hour	0	0	0	9	0	0	0	0	0	3	3	0	0	0	18	9	0	42	0

Three-and-a-Half-Hour Count Summaries - Bikes

Interval Start	Monument Hill Rd			Driveway			Woodmoor Dr			Woodmoor Dr			15-min Total	Rolling One Hour
	Eastbound			Westbound			Northbound			Southbound				
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT		
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	1	0	1	1
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Count Total	0	0	0	0	0	0	0	0	0	0	1	0	1	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

**Two-Hour Count Summaries**

Interval Start		SH 105				SH 105				n/a				Woodmoor Dr				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM		0	84	74	0	0	0	168	217	0	0	0	0	0	80	0	119	742	0
7:15 AM		0	69	132	0	0	0	223	120	0	0	0	0	0	98	0	164	806	0
7:30 AM		0	44	98	0	0	0	258	91	0	0	0	0	1	55	0	146	693	0
7:45 AM		0	39	109	0	0	0	299	98	0	0	0	0	0	34	0	82	661	2,902
8:00 AM		0	24	86	0	0	0	262	85	0	0	0	0	0	27	0	94	578	2,738
8:15 AM		0	19	95	0	0	0	184	78	0	0	0	0	0	30	0	66	472	2,404
8:30 AM		0	56	96	0	0	0	195	85	0	0	0	0	0	40	0	92	564	2,275
8:45 AM		0	63	100	0	0	0	262	97	0	0	0	0	0	48	0	93	663	2,277
Count Total		0	398	790	0	0	0	1,851	871	0	0	0	0	1	412	0	856	5,179	0
Peak Hour	All	0	236	413	0	0	0	948	526	0	0	0	0	1	267	0	511	2,902	0
	HV	0	11	18	0	0	0	22	15	0	0	0	0	0	17	0	13	96	0
	HV%	-	5%	4%	-	-	-	2%	3%	-	-	-	-	0%	6%	-	3%	3%	0

Note: Two-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.


Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
7:00 AM	13	15	0	5	33	0	0	0	0	0	0	0	0	0	0
7:15 AM	2	8	0	21	31	0	0	0	1	1	0	0	0	0	0
7:30 AM	6	8	0	2	16	0	0	0	0	0	0	0	0	0	0
7:45 AM	8	6	0	2	16	0	0	0	0	0	0	0	0	0	0
8:00 AM	11	3	0	3	17	0	0	0	0	0	0	0	0	0	0
8:15 AM	2	7	0	2	11	0	0	0	0	0	0	0	0	0	0
8:30 AM	4	5	0	1	10	0	1	0	0	1	0	0	1	0	1
8:45 AM	2	13	0	5	20	0	0	0	0	0	0	0	0	0	0
Count Total	48	65	0	41	154	0	1	0	1	2	0	0	1	0	1
Peak Hr	29	37	0	30	96	0	0	0	1	1	0	0	0	0	0

Two-Hour Count Summaries - Heavy Vehicles																		
Interval Start	SH 105				SH 105				n/a				Woodmoor Dr				15-min Total	Rolling One Hour
	Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
7:00 AM	0	6	7	0	0	0	2	13	0	0	0	0	0	4	0	1	33	0
7:15 AM	0	1	1	0	0	0	7	1	0	0	0	0	0	11	0	10	31	0
7:30 AM	0	0	6	0	0	0	7	1	0	0	0	0	0	2	0	0	16	0
7:45 AM	0	4	4	0	0	0	6	0	0	0	0	0	0	0	0	2	16	96
8:00 AM	0	1	10	0	0	0	2	1	0	0	0	0	0	2	0	1	17	80
8:15 AM	0	0	2	0	0	0	5	2	0	0	0	0	0	1	0	1	11	60
8:30 AM	0	2	2	0	0	0	2	3	0	0	0	0	0	0	0	1	10	54
8:45 AM	0	0	2	0	0	0	11	2	0	0	0	0	0	0	0	5	20	58
Count Total	0	14	34	0	0	0	42	23	0	0	0	0	0	20	0	21	154	0
Peak Hour	0	11	18	0	0	0	22	15	0	0	0	0	0	17	0	13	96	0


Two-Hour Count Summaries - Bikes																	
Interval Start	SH 105			SH 105			n/a			Woodmoor Dr			15-min Total	Rolling One Hour			
	Eastbound			Westbound			Northbound			Southbound							
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT					
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8:30 AM	0	0	0	0	0	1	0	0	0	0	0	0	0	1	1	1	1
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Count Total	0	0	0	0	0	1	0	0	0	0	0	1	2	0	0	0	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

Woodmoor Dr SH 105



Date: 09/07/2022
Count Period: 2:30 PM to 6:00 PM
Peak Hour: 2:45 PM to 3:45 PM



	HV %:	PHF
EB	2.0%	0.85
WB	2.2%	0.90
NB	-	-
SB	3.4%	0.73
TOTAL	2.5%	0.93

Three-and-a-Half-Hour Count Summaries

Interval Start		SH 105				SH 105				n/a				Woodmoor Dr				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
		UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT		
2:45 PM		0	66	125	0	0	0	271	120	0	0	0	0	0	90	0	118	790	0
3:00 PM		0	56	135	0	0	0	312	90	0	0	0	0	0	118	0	171	882	0
3:15 PM		0	48	109	0	0	0	353	108	0	0	0	0	0	73	0	116	807	0
3:30 PM		0	63	161	0	0	0	290	116	0	0	0	0	0	50	0	105	785	3,264
Peak Hour	All	0	233	530	0	0	0	1,226	434	0	0	0	0	0	331	0	510	3,264	0
	HV	0	3	12	0	0	0	28	8	0	0	0	0	0	19	0	10	80	0
	HV%	-	1%	2%	-	-	-	2%	2%	-	-	-	-	-	6%	-	2%	2%	0

Note: For all three-hour count summary, see next page.

Interval Start	Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)				
	EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total
2:45 PM	4	6	0	16	26	0	0	0	0	0	0	0	0	0	0
3:00 PM	3	13	0	11	27	0	0	0	0	0	0	0	0	0	0
3:15 PM	3	8	0	0	11	0	0	0	0	0	0	0	0	0	0
3:30 PM	5	9	0	2	16	0	0	0	0	0	0	0	0	0	0
Peak Hour	15	36	0	29	80	0	0	0	0	0	0	0	0	0	0

Three-and-a-Half-Hour Count Summaries																			
Interval Start		SH 105				SH 105				n/a				Woodmoor Dr				15-min Total	Rolling One Hour
		Eastbound				Westbound				Northbound				Southbound					
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
2:30 PM	0	64	152	0	0	0	215	128	0	0	0	0	0	87	0	85	731	0	
2:45 PM	0	66	125	0	0	0	271	120	0	0	0	0	0	90	0	118	790	0	
3:00 PM	0	56	135	0	0	0	312	90	0	0	0	0	0	118	0	171	882	0	
3:15 PM	0	48	109	0	0	0	353	108	0	0	0	0	0	73	0	116	807	3,210	
3:30 PM	0	63	161	0	0	0	290	116	0	0	0	0	0	50	0	105	785	3,264	
3:45 PM	0	76	124	0	0	0	274	107	0	0	0	0	0	51	0	106	738	3,212	
4:00 PM	0	61	152	0	0	0	260	98	0	0	0	0	0	57	0	121	749	3,079	
4:15 PM	0	48	152	0	0	0	268	107	0	0	0	0	0	68	0	116	759	3,031	
4:30 PM	0	39	147	0	0	0	292	100	0	0	0	0	0	60	0	104	742	2,988	
4:45 PM	0	61	158	0	0	0	258	114	0	0	0	0	0	52	0	103	746	2,996	
5:00 PM	0	67	187	0	0	0	263	96	0	0	0	0	0	72	0	145	830	3,077	
5:15 PM	0	62	162	0	0	0	244	114	0	0	0	0	0	63	0	111	756	3,074	
5:30 PM	0	59	156	0	0	0	242	93	0	0	0	0	0	48	0	121	719	3,051	
5:45 PM	0	46	124	0	0	0	233	112	0	0	0	0	0	50	0	90	655	2,960	
Count Total		0	816	2,044	0	0	0	3,775	1,503	0	0	0	0	0	939	0	1,612	10,689	0
Peak Hour	All	0	233	530	0	0	0	1,226	434	0	0	0	0	0	331	0	510	3,264	0
	HV	0	3	12	0	0	0	28	8	0	0	0	0	0	19	0	10	80	0
	HV%	-	1%	2%	-	-	-	2%	2%	-	-	-	-	-	6%	-	2%	2%	0
Note: Three-and-a-half-hour count summary volumes include heavy vehicles but exclude bicycles in overall count.																			
Interval Start		Heavy Vehicle Totals					Bicycles					Pedestrians (Crossing Leg)							
		EB	WB	NB	SB	Total	EB	WB	NB	SB	Total	East	West	North	South	Total			
2:30 PM	3	7	0	1	11	0	0	0	0	0	0	0	0	1	0	1			
2:45 PM	4	6	0	16	26	0	0	0	0	0	0	0	0	0	0	0			
3:00 PM	3	13	0	11	27	0	0	0	0	0	0	0	0	0	0	0			
3:15 PM	3	8	0	0	11	0	0	0	0	0	0	0	0	0	0	0			
3:30 PM	5	9	0	2	16	0	0	0	0	0	0	0	0	0	0	0			
3:45 PM	3	10	0	2	15	0	0	0	0	0	0	0	0	0	0	0			
4:00 PM	1	8	0	2	11	0	0	0	0	0	0	0	0	1	0	1			
4:15 PM	2	4	0	1	7	0	0	0	0	0	0	0	0	0	0	0			
4:30 PM	1	19	0	1	21	0	0	0	0	0	0	0	0	0	0	0			
4:45 PM	2	9	0	1	12	0	0	0	0	0	0	0	0	0	0	0			
5:00 PM	3	12	0	3	18	0	0	0	0	0	0	0	0	1	0	1			
5:15 PM	2	4	0	6	12	0	0	0	0	0	0	0	0	1	0	1			
5:30 PM	2	4	0	4	10	0	0	0	0	0	0	0	0	0	0	0			
5:45 PM	0	2	0	0	2	0	0	0	0	0	0	0	0	0	0	0			
Count Total		34	115	0	50	199	0	0	0	0	0	0	0	4	0	4			
Peak Hr		15	36	0	29	80	0	0	0	0	0	0	0	0	0	0			

Three-and-a-Half-Hour Count Summaries - Heavy Vehicles																			
Interval Start	SH 105				SH 105				n/a				Woodmoor Dr				15-min Total	Rolling One Hour	
	Eastbound				Westbound				Northbound				Southbound						
	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT	UT	LT	TH	RT			
2:30 PM	0	1	2	0	0	0	5	2	0	0	0	0	0	0	0	0	1	11	0
2:45 PM	0	1	3	0	0	0	3	3	0	0	0	0	0	0	14	0	2	26	0
3:00 PM	0	0	3	0	0	0	11	2	0	0	0	0	0	0	4	0	7	27	0
3:15 PM	0	0	3	0	0	0	7	1	0	0	0	0	0	0	0	0	0	11	75
3:30 PM	0	2	3	0	0	0	7	2	0	0	0	0	0	0	1	0	1	16	80
3:45 PM	0	2	1	0	0	0	8	2	0	0	0	0	0	0	1	0	1	15	69
4:00 PM	0	0	1	0	0	0	8	0	0	0	0	0	0	0	1	0	1	11	53
4:15 PM	0	0	2	0	0	0	3	1	0	0	0	0	0	0	0	0	1	7	49
4:30 PM	0	0	1	0	0	0	17	2	0	0	0	0	0	0	0	0	1	21	54
4:45 PM	0	0	2	0	0	0	7	2	0	0	0	0	0	0	0	0	1	12	51
5:00 PM	0	1	2	0	0	0	10	2	0	0	0	0	0	0	2	0	1	18	58
5:15 PM	0	2	0	0	0	0	1	3	0	0	0	0	0	0	3	0	3	12	63
5:30 PM	0	1	1	0	0	0	2	2	0	0	0	0	0	0	1	0	3	10	52
5:45 PM	0	0	0	0	0	0	2	0	0	0	0	0	0	0	0	0	0	2	42
Count Total	0	10	24	0	0	0	91	24	0	0	0	0	0	0	27	0	23	199	0
Peak Hour	0	3	12	0	0	0	28	8	0	0	0	0	0	0	19	0	10	80	0

Three-and-a-Half-Hour Count Summaries - Bikes																		
Interval Start	SH 105			SH 105			n/a			Woodmoor Dr			15-min Total	Rolling One Hour				
	Eastbound			Westbound			Northbound			Southbound								
	LT	TH	RT	LT	TH	RT	LT	TH	RT	LT	TH	RT						
2:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
2:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Count Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		

Note: U-Turn volumes for bikes are included in Left-Turn, if any.

APPENDIX B

Future Traffic Projections and Relevant Adjacent Studies

CDOT OTIS: Caliber at Woodmoor

ROUTE	REFPT	ENDREFPT	LENGTH	UPDATEYR	AADT	YR20FACTOR	Annual Growth Rate	DHV	LOCATION
105A	4.731	5.211	0.42	2020	19000	1.39	1.66%	11	ON SH 105 E/O I-25 E/O WOODMOOR DR MONUMENT

North Bay at Woodmoor

Traffic Impact Study Update

Prepared for:

Ms. Beth A. Diana
Planning Manager
La Plata Communities, Inc.
9540 Federal Drive, Suite 200
Colorado Springs, CO 8092

JUNE 2, 2021

LSC Transportation Consultants
Prepared by: Jeffrey C. Hodsdon, P.E.

LSC # S214850



Table 2: Trip Generation Estimate

ITE		Value	Units 1	Trip Generation Rates 2						Total Trips Generated					
Code	Description			Average	A.M.		P.M.		Average	A.M.		P.M.			
		Weekday	In	Out	In	Out	Weekday	In	Out	In	Out				
Current Traffic Report															
215	Single-Family (Attached) Housing	27	DU	7.12	0.14	0.32	0.32	0.24	192	4	9	9	7		
220	Multi-Family Housing (Low-Rise)	8	DU	7.16	0.13	0.41	0.40	0.24	57	1	3	3	2		
	Total	35	DU					Total	249	5	12	12	8		
Prior Traffic Report															
230	Residential Condominium/Townhome	28	DU	-	-	-	-	-	163	2	10	10	5		
				Increase From Prior Traffic Study						86	3	2	2	3	

¹ DU = dwelling units

² Source: Trip Generation, 11th Edition (2021) by the Institute of Transportation Engineers (ITE)



Approximate Scale
Scale: 1" = 80'








Figure 2
Site Plan

North Bay at Woodmoor (LSC #S214850)





1" = 400'
scale



$\frac{XX}{XX}$ = AM Weekday Peak-Hour Traffic (Veh/Hour)
 $\frac{XX}{XX}$ = PM Weekday Peak-Hour Traffic (Veh/Hour)
 X,XXX = Average Daily Traffic (Vehicles/Day)

Figure 7
Site-Generated Traffic
 North Bay at Woodmoor (LSC# 214850)



LSC TRANSPORTATION CONSULTANTS, INC.
2504 East Pikes Peak Avenue, Suite 304
Colorado Springs, CO 80909
(719) 633-2868
FAX (719) 633-5430
E-mail: lsc@lsctrans.com
Website: <http://www.lsctrans.com>

North Bay at Woodmoor Traffic Impact Study (LSC #S214850) June 2, 2022

Traffic Engineer's Statement

This traffic report and supporting information were prepared under my responsible charge and they comport with the standard of care. So far as is consistent with the standard of care, said report was prepared in general conformance with the criteria established by the County for traffic reports.



Developer's Statement

I, the Developer, have read and will comply with all commitments made on my behalf within this report.

A handwritten signature in blue ink, appearing to read 'Ben A. Lerner', written over a horizontal line.

10-3-2022
Date

Table 2: Trip Generation Estimate

ITE		Value	Units ¹	Trip Generation Rates ²								Total Trips Generated							
				Average	A.M.		School PM ³		P.M.		Average	A.M.		School PM ³		P.M.			
Code	Description			Weekday	In	Out	In	Out	In	Out	Weekday	In	Out	In	Out	In	Out		
215	Single-Family (Attached) Housing	36	DU	7.12	0.14	0.32	0.24	0.18	0.32	0.24	256	5	12	9	6	12	9		
220	Multi-Family Housing (Low-Rise)	16	DU	7.16	0.13	0.41	0.30	0.17	0.40	0.24	115	2	7	5	3	6	4		
		52								Total	371	7	18	13	9	18	12		

¹ DU = dwelling units

² Source: *Trip Generation, 11th Edition (2021)* by the Institute of Transportation Engineers (ITE)

³ Source: *Hourly Distribution of Entering and Exiting Vehicle Trips by Land Use* by ITE (assumes school PM peak of 2:15pm - 3:15pm)




1" = 100'
scale



Figure 2

Site Plan

Waterside (LSC# S214860)



PoDI / NHS	
PROJECT OF DIVISION INTEREST (PoDI)?	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
NATIONAL HIGHWAY SYSTEM?	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES

DEPARTMENT OF TRANSPORTATION

STATE OF COLORADO

CONSTRUCTION BID PLANS OF PROPOSED
FEDERAL AID PROJECT NO. SAR M915-009

LEWIS PALMER TRAIL

LEWIS PALMER SCHOOL DISTRICT 38

RELATED PROJECT:
P.E. UNDER PROJECT: PROJECT NUMBER: PROJECT CODE:
R.O.W. PROJECT:
TBD


TABULATION OF LENGTH & DESIGN DATA

STATION			PATH LENGTH (FT)
WOODMOOR DRIVE			
BEGIN PATH	0+00.00		
END PATH	30+99.13		3099.13
WILLOW PARK WAY & LAKE ACCESS ROAD			
BEGIN PATH	30+99.13		
END PATH	52+84.41		2185.28
LAKE WOODMOOR DRIVE			
BEGIN PATH	52+84.41		
END PATH	55+32.09		247.68
CORONADO BEACH DR			
BEGIN PATH	55+32.09		
END PATH	64+33.46		901.37
LOWER LAKE ROAD			
BEGIN PATH	64+33.46		
END PATH	66+69.77		236.31
LAKE WOODMOOR DRIVE			
BEGIN PATH	66+69.77		
END PATH	80+76.62		1406.85
WOODMOOR IMPROVEMENT (ASSOCIATION- OPEN SPACE)			
BEGIN PATH	80+76.62		
END PATH	103+00.00		2223.38
DEER CREEK ROAD			
BEGIN PATH	103+00.00		
END PATH	127+63.00		2463.00

DESIGN DATA

WIDTH- SLOPE 4' 5% MAX
MAXIMUM SLOPE 12.5%
PASSING ZONE 5'x5' MAX 1,000' APART
RESTING ZONES 5% MAX SLOPE

TOWN OF MONUMENT, EL PASO COUNTY, COLORADO



VICINITY MAP
SCALE: 1"=1000'

SHEET INDEX

- 1 - COVER SHEET
- 2 - STANDARDS PLAN LIST
- 3 - LEGEND
- 4 - TYPICAL SECTIONS
- 5-6 - RAMP DETAILS
- 7 - NOTES
- 8 - SUMMARY OF APPROXIMATE QUANTITIES
- 9 - SURVEY TABULATIONS
- 10-12 - HORIZONTAL CONTROL PLANS
- 13-28 - TRAIL PLAN AND PROFILE
- 29-41 - CROSS SECTION


CONTACTS:

OWNER	LEWIS PALMER SCHOOL DISTRICT 38 146 N JEFFERSON STREET MONUMENT, CO 80132 ATTN: RICKY VESTAL P~(719) 757-1430
PROJECT PARTNER	WOODMOOR IMPROVEMENT ASSOCIATION 1691 WOODMOOR DR. MONUMENT, CO 80132 ATTN: P~(719) 488-2693
PROJECT PARTNER	WOODMOOR WATER AND SANITATION DISTRICT PO BOX 1407 MONUMENT, CO 80132 ATTN: P~() -
ENGINEER/SURVEYOR	JR ENGINEERING, LLC ATTN: GLENN ELLIS 5475 TECH CENTER DRIVE, SUITE 235 COLORADO SPRINGS, CO 80919 P~(303) 267-6241
CDOT (REGION 2)	COLORADO DEPARTMENT OF TRANSPORTATION 5615 WILLS BOULEVARD PUEBLO, CO 81008 CONTACT: JUNIOR RODRIGUEZ P~(719) 251-6980

ENGINEER'S STATEMENT



PREPARED UNDER MY SUPERVISION

GLENN D. ELLIS, P.E.
COLORADO P.E. 38861
FOR AND ON BEHALF OF JR ENGINEERING, LLC




Print Date: 05/20/2021	<div><div></div><div></div><div></div><div></div><div></div></div>	Sheet Revisions			<div>Colorado Department of Transportation</div> <div> 5615 WILL BLVD. Pueblo, CO 81008 Phone: 719-546-5750</div> <div> Lewis Palmer School District 38</div> <div>Region 2</div>	As Constructed	LEWIS PALMER TRAIL COVER SHEET				Project No./Code	
File Name:		Date:	Comments	Init.		No Revisions:					M915-009/22585	
Horiz. Scale: N/A							Revised:	Designer: GG	Structure	Numbers	2520300	
Unit name							Void:	Detailer: GG	Subset Sheets:		OF	Sheet Number 1 OF 41
Unit leader								Sheet Subset:				

 **J-R ENGINEERING**
A Westrian Company
Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com



KEY MAP
SCALE: NOT TO SCALE



Print Date: 05/20/2021

File Name:

Horiz. Scale: 1"=80' Vert. Scale: N/A

Unit name Unit leader

J-R ENGINEERING
A Westrian Company
Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com

Sheet Revisions			
Date:	Comments	Init.	

Colorado Department of Transportation



CDOT

5615 WILL BLVD.
Pueblo, CO 81008
Phone: 719-546-5750


Region 2

LP
Lewis Palmer School District 38


As Constructed		LEWIS PALMER TRAIL HORIZONTAL CONTROL				Project No./Code	
No Revisions:						M915-009/22585	
Revised:		Designer:	GG	Structure Numbers		2520300	
Void:		Detailer:	GG				
		Sheet Subset:		Subset Sheets:	OF	Sheet Number 10 OF 41	




KEY MAP
SCALE: NOT TO SCALE



Know what's **below**.
Call before you dig.

[illegible]




Print Date: 05/20/2021

File Name:

Horiz. Scale: 1"=80'

Unit name

**J-R ENGINEERING**
A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com

Unit leader

☐

☐

☐

☐

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation



5615 WILL BLVD.
Pueblo, CO 81008
Phone: 719-546-5750

Region 2

Lewis Palmer
School District 38

As Constructed	LEWIS PALMER TRAIL HORIZONTAL CONTROL				Project No./Code
No Revisions:					M915-009/22585
Revised:	Designer: GG	Structure			2520300
Void:	Detailer: GG	Numbers			
	Sheet Subset:	Subset Sheets:	OF		Sheet Number 12 OF 41

APPENDIX C

Trip Generation Worksheets

Project Caliber at Woodmoor
 Subject Trip Generation for Multifamily Housing (Low-Rise)
 Designed by TJD Date June 24, 2022 Job No. 096481007
 Checked by _____ Date _____ Sheet No. _____ of _____

TRIP GENERATION MANUAL TECHNIQUES

ITE Trip Generation Manual 11th Edition, Fitted Curve Equations

Land Use Code - Multifamily Housing (Low-Rise) (220)

Independent Variable - Dwelling Units (X)

$$X = 264$$

T = Average Vehicle Trip Ends

Peak Hour of Adjacent Street Traffic, One Hour Between 7 and 9 a.m. (200 Series Page 255)

$(T) = 0.31 (X) + 22.85$	Directional Distribution:	24% ent.	76% exit.
$(T) = 0.31 * (264.0) + 22.85$	T = 106	Average Vehicle Trip Ends	
	25 entering	81 exiting	
	25 + 81 = 106		

Peak Hour of Adjacent Street Traffic, One Hour Between 4 and 6 p.m. (200 Series Page 256)

$(T) = 0.43 (X) + 20.55$	Directional Distribution:	63% ent.	37% exit.
$(T) = 0.43 * (264.0) + 20.55$	T = 136	Average Vehicle Trip Ends	
	86 entering	50 exiting	
	86 + 50 = 136		

Weekday (200 Series Page 254)

$(T) = 6.41 (X) + 75.31$	Directional Distribution:	50% ent.	50% exit.
$(T) = 6.41 * (264.0) + 75.31$	T = 1768	Average Vehicle Trip Ends	
	884 entering	884 exiting	
	884 + 884 = 1768		

APPENDIX D

Intersection Analysis Worksheets

HCM 6th TWSC
1: Monument Hill Road & Palmer Divide Road

2022 Existing AM
09/13/2022

Intersection												
Int Delay, s/veh	3.3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		<div>↕</div>			<div>↕</div>			<div>↕</div>			<div>↕</div>	
Traffic Vol, veh/h	2	115	69	53	405	0	62	3	25	1	2	1
Future Vol, veh/h	2	115	69	53	405	0	62	3	25	1	2	1
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	80	80	80	80	80	80	80	80	80	80	80	80
Heavy Vehicles, %	5	5	5	2	2	2	2	2	2	2	2	2
Mvmt Flow	3	144	86	66	506	0	78	4	31	1	3	1
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	506	0	0	230	0	0	833	831	187	849	874	506
Stage 1	-	-	-	-	-	-	193	193	-	638	638	-
Stage 2	-	-	-	-	-	-	640	638	-	211	236	-
Critical Hdwy	4.15	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.245	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1043	-	-	1338	-	-	288	305	855	281	288	566
Stage 1	-	-	-	-	-	-	809	741	-	465	471	-
Stage 2	-	-	-	-	-	-	464	471	-	791	710	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1043	-	-	1338	-	-	270	283	855	253	267	566
Mov Cap-2 Maneuver	-	-	-	-	-	-	270	283	-	253	267	-
Stage 1	-	-	-	-	-	-	807	739	-	464	439	-
Stage 2	-	-	-	-	-	-	429	439	-	756	708	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.9			21.2			17.1		
HCM LOS							C			C		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	334	1043	-	-	1338	-	-	303				
HCM Lane V/C Ratio	0.337	0.002	-	-	0.05	-	-	0.017				
HCM Control Delay (s)	21.2	8.5	0	-	7.8	0	-	17.1				
HCM Lane LOS	C	A	A	-	A	A	-	C				
HCM 95th %tile Q(veh)	1.4	0	-	-	0.2	-	-	0.1				

HCM 6th TWSC
1: Monument Hill Road & Palmer Divide Road

2022 Existing PM
09/13/2022

Intersection												
Int Delay, s/veh	1.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	4	323	32	9	235	0	39	0	6	0	0	3
Future Vol, veh/h	4	323	32	9	235	0	39	0	6	0	0	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	97	97	97	97	97	97	97	97	97	97	97	97
Heavy Vehicles, %	3	3	3	5	5	5	9	9	9	33	2	2
Mvmt Flow	4	333	33	9	242	0	40	0	6	0	0	3
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	242	0	0	366	0	0	620	618	350	621	634	242
Stage 1	-	-	-	-	-	-	358	358	-	260	260	-
Stage 2	-	-	-	-	-	-	262	260	-	361	374	-
Critical Hdwy	4.13	-	-	4.15	-	-	7.19	6.59	6.29	7.43	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Follow-up Hdwy	2.227	-	-	2.245	-	-	3.581	4.081	3.381	3.797	4.018	3.318
Pot Cap-1 Maneuver	1319	-	-	1176	-	-	390	396	678	359	397	797
Stage 1	-	-	-	-	-	-	646	616	-	681	693	-
Stage 2	-	-	-	-	-	-	728	680	-	598	618	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1319	-	-	1176	-	-	385	391	678	352	392	797
Mov Cap-2 Maneuver	-	-	-	-	-	-	385	391	-	352	392	-
Stage 1	-	-	-	-	-	-	643	614	-	678	687	-
Stage 2	-	-	-	-	-	-	719	674	-	590	616	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.3			14.9			9.5		
HCM LOS							B			A		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	409	1319	-	-	1176	-	-	797				
HCM Lane V/C Ratio	0.113	0.003	-	-	0.008	-	-	0.004				
HCM Control Delay (s)	14.9	7.7	0	-	8.1	0	-	9.5				
HCM Lane LOS	B	A	A	-	A	A	-	A				
HCM 95th %tile Q(veh)	0.4	0	-	-	0	-	-	0				

Intersection												
Int Delay, s/veh	3.7											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	2	121	73	55	426	0	69	3	26	1	2	1
Future Vol, veh/h	2	121	73	55	426	0	69	3	26	1	2	1
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	80	80	80	80	80	80	80	80	80	80	80	80
Heavy Vehicles, %	5	5	5	2	2	2	2	2	2	2	2	2
Mvmt Flow	3	151	91	69	533	0	86	4	33	1	3	1
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	533	0	0	242	0	0	876	874	197	892	919	533
Stage 1	-	-	-	-	-	-	203	203	-	671	671	-
Stage 2	-	-	-	-	-	-	673	671	-	221	248	-
Critical Hdwy	4.15	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.245	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1020	-	-	1324	-	-	269	288	844	263	271	547
Stage 1	-	-	-	-	-	-	799	733	-	446	455	-
Stage 2	-	-	-	-	-	-	445	455	-	781	701	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1020	-	-	1324	-	-	251	266	844	235	250	547
Mov Cap-2 Maneuver	-	-	-	-	-	-	251	266	-	235	250	-
Stage 1	-	-	-	-	-	-	797	731	-	445	421	-
Stage 2	-	-	-	-	-	-	409	421	-	745	699	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.9			24.1			17.9		
HCM LOS							C			C		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	309	1020	-	-	1324	-	-	284				
HCM Lane V/C Ratio	0.396	0.002	-	-	0.052	-	-	0.018				
HCM Control Delay (s)	24.1	8.5	0	-	7.9	0	-	17.9				
HCM Lane LOS	C	A	A	-	A	A	-	C				
HCM 95th %tile Q(veh)	1.8	0	-	-	0.2	-	-	0.1				

Intersection												
Int Delay, s/veh	1.3											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	4	339	37	9	247	0	44	0	6	0	0	3
Future Vol, veh/h	4	339	37	9	247	0	44	0	6	0	0	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	97	97	97	97	97	97	97	97	97	97	97	97
Heavy Vehicles, %	3	3	3	5	5	5	9	9	9	33	2	2
Mvmt Flow	4	349	38	9	255	0	45	0	6	0	0	3
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	255	0	0	387	0	0	651	649	368	652	668	255
Stage 1	-	-	-	-	-	-	376	376	-	273	273	-
Stage 2	-	-	-	-	-	-	275	273	-	379	395	-
Critical Hdwy	4.13	-	-	4.15	-	-	7.19	6.59	6.29	7.43	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Follow-up Hdwy	2.227	-	-	2.245	-	-	3.581	4.081	3.381	3.797	4.018	3.318
Pot Cap-1 Maneuver	1304	-	-	1155	-	-	372	380	662	341	379	784
Stage 1	-	-	-	-	-	-	631	604	-	670	684	-
Stage 2	-	-	-	-	-	-	716	671	-	585	605	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1304	-	-	1155	-	-	367	375	662	335	374	784
Mov Cap-2 Maneuver	-	-	-	-	-	-	367	375	-	335	374	-
Stage 1	-	-	-	-	-	-	628	602	-	667	678	-
Stage 2	-	-	-	-	-	-	707	665	-	577	603	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.3			15.7			9.6		
HCM LOS							C			A		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	388	1304	-	-	1155	-	-	784				
HCM Lane V/C Ratio	0.133	0.003	-	-	0.008	-	-	0.004				
HCM Control Delay (s)	15.7	7.8	0	-	8.1	0	-	9.6				
HCM Lane LOS	C	A	A	-	A	A	-	A				
HCM 95th %tile Q(veh)	0.5	0	-	-	0	-	-	0				

HCM 6th TWSC
1: Monument Hill Road & Palmer Divide Road

2025 Total AM
09/13/2022

Intersection												
Int Delay, s/veh	4.4											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	2	121	77	55	426	0	81	3	26	1	2	1
Future Vol, veh/h	2	121	77	55	426	0	81	3	26	1	2	1
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	80	80	80	80	80	80	80	80	80	80	80	80
Heavy Vehicles, %	5	5	5	2	2	2	2	2	2	2	2	2
Mvmt Flow	3	151	96	69	533	0	101	4	33	1	3	1
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	533	0	0	247	0	0	878	876	199	895	924	533
Stage 1	-	-	-	-	-	-	205	205	-	671	671	-
Stage 2	-	-	-	-	-	-	673	671	-	224	253	-
Critical Hdwy	4.15	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.245	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	1020	-	-	1319	-	-	268	287	842	261	269	547
Stage 1	-	-	-	-	-	-	797	732	-	446	455	-
Stage 2	-	-	-	-	-	-	445	455	-	779	698	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1020	-	-	1319	-	-	250	265	842	234	248	547
Mov Cap-2 Maneuver	-	-	-	-	-	-	250	265	-	234	248	-
Stage 1	-	-	-	-	-	-	795	730	-	445	421	-
Stage 2	-	-	-	-	-	-	409	421	-	743	696	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.9			26.8			18		
HCM LOS							D			C		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	300	1020	-	-	1319	-	-	282				
HCM Lane V/C Ratio	0.458	0.002	-	-	0.052	-	-	0.018				
HCM Control Delay (s)	26.8	8.5	0	-	7.9	0	-	18				
HCM Lane LOS	D	A	A	-	A	A	-	C				
HCM 95th %tile Q(veh)	2.3	0	-	-	0.2	-	-	0.1				

HCM 6th TWSC
1: Monument Hill Road & Palmer Divide Road

2025 Total PM
09/13/2022

Intersection												
Int Delay, s/veh	1.5											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	4	339	50	9	247	0	52	0	6	0	0	3
Future Vol, veh/h	4	339	50	9	247	0	52	0	6	0	0	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	97	97	97	97	97	97	97	97	97	97	97	97
Heavy Vehicles, %	3	3	3	5	5	5	9	9	9	33	2	2
Mvmt Flow	4	349	52	9	255	0	54	0	6	0	0	3
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	255	0	0	401	0	0	658	656	375	659	682	255
Stage 1	-	-	-	-	-	-	383	383	-	273	273	-
Stage 2	-	-	-	-	-	-	275	273	-	386	409	-
Critical Hdwy	4.13	-	-	4.15	-	-	7.19	6.59	6.29	7.43	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Follow-up Hdwy	2.227	-	-	2.245	-	-	3.581	4.081	3.381	3.797	4.018	3.318
Pot Cap-1 Maneuver	1304	-	-	1142	-	-	368	376	656	338	372	784
Stage 1	-	-	-	-	-	-	626	600	-	670	684	-
Stage 2	-	-	-	-	-	-	716	671	-	579	596	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1304	-	-	1142	-	-	363	371	656	332	367	784
Mov Cap-2 Maneuver	-	-	-	-	-	-	363	371	-	332	367	-
Stage 1	-	-	-	-	-	-	623	598	-	667	678	-
Stage 2	-	-	-	-	-	-	707	665	-	571	594	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.3			16.2			9.6		
HCM LOS							C			A		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	381	1304	-	-	1142	-	-	784				
HCM Lane V/C Ratio	0.157	0.003	-	-	0.008	-	-	0.004				
HCM Control Delay (s)	16.2	7.8	0	-	8.2	0	-	9.6				
HCM Lane LOS	C	A	A	-	A	A	-	A				
HCM 95th %tile Q(veh)	0.6	0	-	-	0	-	-	0				

Intersection												
Int Delay, s/veh	8.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	3	168	89	67	591	0	83	4	31	1	3	1
Future Vol, veh/h	3	168	89	67	591	0	83	4	31	1	3	1
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	80	80	80	80	80	80	80	80	80	80	80	80
Heavy Vehicles, %	5	5	5	2	2	2	2	2	2	2	2	2
Mvmt Flow	4	210	111	84	739	0	104	5	39	1	4	1

Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	739	0	0	321	0	0	1184	1181	266	1203	1236	739
Stage 1	-	-	-	-	-	-	274	274	-	907	907	-
Stage 2	-	-	-	-	-	-	910	907	-	296	329	-
Critical Hdwy	4.15	-	-	4.12	-	-	7.12	6.52	6.22	7.12	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.12	5.52	-	6.12	5.52	-
Follow-up Hdwy	2.245	-	-	2.218	-	-	3.518	4.018	3.318	3.518	4.018	3.318
Pot Cap-1 Maneuver	854	-	-	1239	-	-	166	190	773	161	176	417
Stage 1	-	-	-	-	-	-	732	683	-	330	355	-
Stage 2	-	-	-	-	-	-	329	355	-	712	646	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	854	-	-	1239	-	-	148	167	773	136	155	417
Mov Cap-2 Maneuver	-	-	-	-	-	-	148	167	-	136	155	-
Stage 1	-	-	-	-	-	-	728	679	-	328	314	-
Stage 2	-	-	-	-	-	-	287	314	-	667	642	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0.1	0.8	70.2	26.7
HCM LOS			F	D

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1
Capacity (veh/h)	189	854	-	-	1239	-	-	172
HCM Lane V/C Ratio	0.78	0.004	-	-	0.068	-	-	0.036
HCM Control Delay (s)	70.2	9.2	0	-	8.1	0	-	26.7
HCM Lane LOS	F	A	A	-	A	A	-	D
HCM 95th %tile Q(veh)	5.3	0	-	-	0.2	-	-	0.1


Intersection												
Int Delay, s/veh	1.7											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	5	472	44	11	343	0	53	0	8	0	0	4
Future Vol, veh/h	5	472	44	11	343	0	53	0	8	0	0	4
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	97	97	97	97	97	97	97	97	97	97	97	97
Heavy Vehicles, %	3	3	3	5	5	5	9	9	9	33	2	2
Mvmt Flow	5	487	45	11	354	0	55	0	8	0	0	4
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	354	0	0	532	0	0	898	896	510	900	918	354
Stage 1	-	-	-	-	-	-	520	520	-	376	376	-
Stage 2	-	-	-	-	-	-	378	376	-	524	542	-
Critical Hdwy	4.13	-	-	4.15	-	-	7.19	6.59	6.29	7.43	6.52	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.19	5.59	-	6.43	5.52	-
Follow-up Hdwy	2.227	-	-	2.245	-	-	3.581	4.081	3.381	3.797	4.018	3.318
Pot Cap-1 Maneuver	1199	-	-	1020	-	-	253	272	550	229	272	690
Stage 1	-	-	-	-	-	-	527	521	-	587	616	-
Stage 2	-	-	-	-	-	-	630	604	-	484	520	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	1199	-	-	1020	-	-	248	267	550	222	267	690
Mov Cap-2 Maneuver	-	-	-	-	-	-	248	267	-	222	267	-
Stage 1	-	-	-	-	-	-	524	518	-	583	608	-
Stage 2	-	-	-	-	-	-	618	596	-	474	517	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.1			0.3			22.6			10.2		
HCM LOS							C			B		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	267	1199	-	-	1020	-	-	690				
HCM Lane V/C Ratio	0.236	0.004	-	-	0.011	-	-	0.006				
HCM Control Delay (s)	22.6	8	0	-	8.6	0	-	10.2				
HCM Lane LOS	C	A	A	-	A	A	-	B				
HCM 95th %tile Q(veh)	0.9	0	-	-	0	-	-	0				

Timings

2045 Total AM - #1,2,6 Signalized

1: Monument Hill Road & Palmer Divide Road

10/20/2022



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations								
Traffic Volume (vph)	5	170	70	595	95	5	5	5
Future Volume (vph)	5	170	70	595	95	5	5	5
Turn Type	Perm	NA	Perm	NA	Perm	NA	Perm	NA
Protected Phases		4		8		2		6
Permitted Phases	4		8		2		6	
Detector Phase	4	4	8	8	2	2	6	6
Switch Phase								
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	62.0	62.0	62.0	62.0	28.0	28.0	28.0	28.0
Total Split (%)	68.9%	68.9%	68.9%	68.9%	31.1%	31.1%	31.1%	31.1%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0		0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5		4.5		4.5
Lead/Lag								
Lead-Lag Optimize?								
Recall Mode	None	None	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	47.6	47.6	47.6	47.6		33.4		33.4
Actuated g/C Ratio	0.53	0.53	0.53	0.53		0.37		0.37
v/c Ratio	0.04	0.36	0.18	0.76		0.31		0.03
Control Delay	7.6	9.8	9.9	21.2		36.5		18.6
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0
Total Delay	7.6	9.8	9.9	21.2		36.5		18.6
LOS	A	A	A	C		D		B
Approach Delay		9.7		20.0		36.5		18.6
Approach LOS		A		C		D		B

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.76

Intersection Signal Delay: 19.5

Intersection LOS: B

Intersection Capacity Utilization 61.1%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 1: Monument Hill Road & Palmer Divide Road




















	Ø2 (R)		Ø4
28 s		62 s	
	Ø6 (R)		Ø8
28 s		62 s	

HCM 6th Signalized Intersection Summary

1: Monument Hill Road & Palmer Divide Road

2045 Total AM - #1,2,6 Signalized

10/20/2022

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	5	170	95	70	595	0	95	5	35	5	5	5
Future Volume (veh/h)	5	170	95	70	595	0	95	5	35	5	5	5
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1826	1826	1826	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	6	212	119	88	744	0	119	6	44	6	6	6
Peak Hour Factor	0.80	0.80	0.80	0.80	0.80	0.80	0.80	0.80	0.80	0.80	0.80	0.80
Percent Heavy Veh, %	5	5	5	2	2	2	2	2	2	2	2	2
Cap, veh/h	143	496	279	417	845	0	519	35	171	268	267	240
Arrive On Green	0.45	0.45	0.45	0.45	0.45	0.00	0.45	0.45	0.45	0.45	0.45	0.45
Sat Flow, veh/h	699	1098	617	1049	1870	0	1006	78	382	478	595	537
Grp Volume(v), veh/h	6	0	331	88	744	0	169	0	0	18	0	0
Grp Sat Flow(s),veh/h/ln	699	0	1715	1049	1870	0	1466	0	0	1610	0	0
Q Serve(g_s), s	0.7	0.0	11.8	5.6	32.6	0.0	5.5	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	33.3	0.0	11.8	17.4	32.6	0.0	6.3	0.0	0.0	0.5	0.0	0.0
Prop In Lane	1.00		0.36	1.00		0.00	0.70		0.26	0.33		0.33
Lane Grp Cap(c), veh/h	143	0	775	417	845	0	725	0	0	774	0	0
V/C Ratio(X)	0.04	0.00	0.43	0.21	0.88	0.00	0.23	0.00	0.00	0.02	0.00	0.00
Avail Cap(c_a), veh/h	274	0	1096	613	1195	0	725	0	0	774	0	0
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	1.00	0.00	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	37.6	0.0	16.7	22.6	22.4	0.0	15.4	0.0	0.0	13.9	0.0	0.0
Incr Delay (d2), s/veh	0.1	0.0	0.4	0.2	5.8	0.0	0.8	0.0	0.0	0.1	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.1	0.0	4.5	1.4	14.7	0.0	2.2	0.0	0.0	0.2	0.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	37.7	0.0	17.1	22.9	28.2	0.0	16.2	0.0	0.0	13.9	0.0	0.0
LnGrp LOS	D	A	B	C	C	A	B	A	A	B	A	A
Approach Vol, veh/h	337			832			169			18		
Approach Delay, s/veh	17.5			27.6			16.2			13.9		
Approach LOS	B			C			B			B		
Timer - Assigned Phs	2			4			6			8		
Phs Duration (G+Y+Rc), s	44.8			45.2			44.8			45.2		
Change Period (Y+Rc), s	4.5			4.5			4.5			4.5		
Max Green Setting (Gmax), s	23.5			57.5			23.5			57.5		
Max Q Clear Time (g_c+I1), s	8.3			35.3			2.5			34.6		
Green Ext Time (p_c), s	0.8			2.1			0.0			6.1		
Intersection Summary												
HCM 6th Ctrl Delay	23.5											
HCM 6th LOS	C											

HCM 6th Roundabout
1: Monument Hill Road & Palmer Divide Road

2045 Total AM
09/13/2022


Intersection				
Intersection Delay, s/veh	10.4			
Intersection LOS	B			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	337	832	169	18
Demand Flow Rate, veh/h	354	849	172	18
Vehicles Circulating, veh/h	102	133	235	970
Vehicles Exiting, veh/h	886	274	221	12
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	5.7	13.5	4.8	7.5
Approach LOS	A	B	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	354	849	172	18
Cap Entry Lane, veh/h	1244	1205	1086	513
Entry HV Adj Factor	0.953	0.980	0.982	0.993
Flow Entry, veh/h	337	832	169	18
Cap Entry, veh/h	1185	1181	1066	510
V/C Ratio	0.285	0.705	0.158	0.035
Control Delay, s/veh	5.7	13.5	4.8	7.5
LOS	A	B	A	A
95th %tile Queue, veh	1	6	1	0

Timings

2045 Total PM - #1,2,6 Signalized

1: Monument Hill Road & Palmer Divide Road

10/20/2022



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBT
Lane Configurations							
Traffic Volume (vph)	5	475	15	345	65	0	0
Future Volume (vph)	5	475	15	345	65	0	0
Turn Type	Perm	NA	Perm	NA	Perm	NA	NA
Protected Phases		4		8		2	6
Permitted Phases	4		8		2		
Detector Phase	4	4	8	8	2	2	6
Switch Phase							
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	61.0	61.0	61.0	61.0	29.0	29.0	29.0
Total Split (%)	67.8%	67.8%	67.8%	67.8%	32.2%	32.2%	32.2%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5		4.5	4.5
Lead/Lag							
Lead-Lag Optimize?							
Recall Mode	None	None	None	None	C-Max	C-Max	C-Max
Act Effect Green (s)	36.7	36.7	36.7	36.7		44.3	44.3
Actuated g/C Ratio	0.41	0.41	0.41	0.41		0.49	0.49
v/c Ratio	0.02	0.74	0.09	0.48		0.11	0.00
Control Delay	11.6	27.4	13.9	20.7		22.7	0.0
Queue Delay	0.0	0.0	0.0	0.0		0.0	0.0
Total Delay	11.6	27.4	13.9	20.7		22.7	0.0
LOS	B	C	B	C		C	A
Approach Delay		27.3		20.4		22.7	
Approach LOS		C		C		C	

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 50

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.74

Intersection Signal Delay: 24.3

Intersection LOS: C

Intersection Capacity Utilization 47.0%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 1: Monument Hill Road & Palmer Divide Road






















HCM 6th Signalized Intersection Summary

1: Monument Hill Road & Palmer Divide Road

2045 Total PM - #1,2,6 Signalized

10/20/2022

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	5	475	60	15	345	0	65	0	10	0	0	5
Future Volume (veh/h)	5	475	60	15	345	0	65	0	10	0	0	5
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1856	1856	1856	1826	1826	1826	1767	1767	1767	1411	1870	1870
Adj Flow Rate, veh/h	5	490	62	15	356	0	67	0	10	0	0	5
Peak Hour Factor	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97
Percent Heavy Veh, %	3	3	3	5	5	5	9	9	9	33	2	2
Cap, veh/h	276	566	72	136	640	0	718	5	97	0	0	871
Arrive On Green	0.35	0.35	0.35	0.35	0.35	0.00	0.55	0.00	0.55	0.00	0.00	0.55
Sat Flow, veh/h	1017	1614	204	836	1826	0	1169	9	176	0	0	1585
Grp Volume(v), veh/h	5	0	552	15	356	0	77	0	0	0	0	5
Grp Sat Flow(s),veh/h/ln	1017	0	1819	836	1826	0	1354	0	0	0	0	1585
Q Serve(g_s), s	0.4	0.0	25.5	1.5	14.2	0.0	2.1	0.0	0.0	0.0	0.0	0.1
Cycle Q Clear(g_c), s	14.5	0.0	25.5	27.0	14.2	0.0	2.4	0.0	0.0	0.0	0.0	0.1
Prop In Lane	1.00		0.11	1.00		0.00	0.87		0.13	0.00		1.00
Lane Grp Cap(c), veh/h	276	0	637	136	640	0	819	0	0	0	0	871
V/C Ratio(X)	0.02	0.00	0.87	0.11	0.56	0.00	0.09	0.00	0.00	0.00	0.00	0.01
Avail Cap(c_a), veh/h	559	0	1142	368	1146	0	819	0	0	0	0	871
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	1.00	0.00	1.00	0.00	0.00	0.00	0.00	1.00
Uniform Delay (d), s/veh	29.4	0.0	27.3	39.9	23.6	0.0	9.6	0.0	0.0	0.0	0.0	9.2
Incr Delay (d2), s/veh	0.0	0.0	3.7	0.4	0.8	0.0	0.2	0.0	0.0	0.0	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.1	0.0	11.2	0.3	6.0	0.0	0.7	0.0	0.0	0.0	0.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	29.5	0.0	31.0	40.2	24.3	0.0	9.9	0.0	0.0	0.0	0.0	9.2
LnGrp LOS	C	A	C	D	C	A	A	A	A	A	A	A
Approach Vol, veh/h	557			371			77			5		
Approach Delay, s/veh	31.0			25.0			9.9			9.2		
Approach LOS	C			C			A			A		
Timer - Assigned Phs	2			4			6			8		
Phs Duration (G+Y+Rc), s	54.0			36.0			54.0			36.0		
Change Period (Y+Rc), s	4.5			4.5			4.5			4.5		
Max Green Setting (Gmax), s	24.5			56.5			24.5			56.5		
Max Q Clear Time (g_c+l1), s	4.4			27.5			2.1			29.0		
Green Ext Time (p_c), s	0.3			4.1			0.0			2.4		
Intersection Summary												
HCM 6th Ctrl Delay	27.1											
HCM 6th LOS	C											

HCM 6th Roundabout
1: Monument Hill Road & Palmer Divide Road

2045 Total PM
09/13/2022







Intersection				
Intersection Delay, s/veh	6.4			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	557	371	77	5
Demand Flow Rate, veh/h	574	390	84	5
Vehicles Circulating, veh/h	16	78	510	463
Vehicles Exiting, veh/h	452	516	80	5
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	6.8	5.8	5.8	4.2
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	574	390	84	5
Cap Entry Lane, veh/h	1358	1274	820	861
Entry HV Adj Factor	0.971	0.952	0.917	1.000
Flow Entry, veh/h	557	371	77	5
Cap Entry, veh/h	1318	1213	752	861
V/C Ratio	0.423	0.306	0.102	0.006
Control Delay, s/veh	6.8	5.8	5.8	4.2
LOS	A	A	A	A
95th %tile Queue, veh	2	1	0	0

HCM 6th TWSC
2: Monument Hill Road & Misty Acres Boulevard

2022 Existing AM
09/12/2022

Intersection

Int Delay, s/veh 10.7

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	272	33	38	258	43	98
Future Vol, veh/h	272	33	38	258	43	98
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	56	56	56	56	56	56
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	486	59	68	461	77	175

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	397	68	0
Stage 1	68	-	-
Stage 2	329	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	608	995	-
Stage 1	955	-	-
Stage 2	729	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	563	995	-
Mov Cap-2 Maneuver	634	-	-
Stage 1	955	-	-
Stage 2	675	-	-

Approach	WB	NB	SB
HCM Control Delay, s	24.9	0	2.7
HCM LOS	C		







Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT
Capacity (veh/h)	-	- 634 995 1038	-	-
HCM Lane V/C Ratio	-	- 0.766 0.059 0.074	-	-
HCM Control Delay (s)	-	- 26.8 8.8 8.7	-	-
HCM Lane LOS	-	- D A A	-	-
HCM 95th %tile Q(veh)	-	- 7.1 0.2 0.2	-	-

HCM 6th TWSC
2: Monument Hill Road & Misty Acres Boulevard

2022 Existing PM
09/12/2022

Intersection

Int Delay, s/veh 5.6

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	228	21	60	186	21	50
Future Vol, veh/h	228	21	60	186	21	50
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	72	72	72	72	72	72
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	317	29	83	258	29	69

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	210	83	0
Stage 1	83	-	-
Stage 2	127	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	778	976	-
Stage 1	940	-	-
Stage 2	899	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	759	976	-
Mov Cap-2 Maneuver	809	-	-
Stage 1	940	-	-
Stage 2	877	-	-

Approach	WB	NB	SB
HCM Control Delay, s	12	0	2.4
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT
Capacity (veh/h)	-	- 809	976	1218
HCM Lane V/C Ratio	-	- 0.391	0.03	0.024
HCM Control Delay (s)	-	- 12.3	8.8	8
HCM Lane LOS	-	- B	A	A
HCM 95th %tile Q(veh)	-	- 1.9	0.1	0.1







HCM 6th TWSC
2: Monument Hill Road & Misty Acres Boulevard

2025 Background AM

09/12/2022

Intersection

Int Delay, s/veh 11.9

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	280	34	44	266	44	103
Future Vol, veh/h	280	34	44	266	44	103
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	56	56	56	56	56	56
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	500	61	79	475	79	184

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	421	79	0
Stage 1	79	-	-
Stage 2	342	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	589	981	-
Stage 1	944	-	-
Stage 2	719	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	543	981	-
Mov Cap-2 Maneuver	622	-	-
Stage 1	944	-	-
Stage 2	663	-	-

Approach	WB	NB	SB
HCM Control Delay, s	27.9	0	2.6
HCM LOS	D		

Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT
Capacity (veh/h)	-	-	622	981
HCM Lane V/C Ratio	-	-	0.804	0.062
HCM Control Delay (s)	-	-	30.2	8.9
HCM Lane LOS	-	-	D	A
HCM 95th %tile Q(veh)	-	-	8	0.2







HCM 6th TWSC
2: Monument Hill Road & Misty Acres Boulevard

2025 Background PM

09/13/2022

Intersection

Int Delay, s/veh 5.6

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	235	22	66	192	22	56
Future Vol, veh/h	235	22	66	192	22	56
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	72	72	72	72	72	72
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	326	31	92	267	31	78

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	232	92	0
Stage 1	92	-	-
Stage 2	140	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	756	965	-
Stage 1	932	-	-
Stage 2	887	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	736	965	-
Mov Cap-2 Maneuver	795	-	-
Stage 1	932	-	-
Stage 2	864	-	-

Approach	WB	NB	SB
HCM Control Delay, s	12.3	0	2.3
HCM LOS	B		







Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT
Capacity (veh/h)	-	- 795 965 1200	-	-
HCM Lane V/C Ratio	-	- 0.411 0.032 0.025	-	-
HCM Control Delay (s)	-	- 12.6 8.9 8.1	-	-
HCM Lane LOS	-	- B A A	-	-
HCM 95th %tile Q(veh)	-	- 2 0.1 0.1	-	-

HCM 6th TWSC
2: Monument Hill Road & Misty Acres Boulevard

2025 Total AM
09/13/2022

Intersection

Int Delay, s/veh 12.1

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	280	34	56	266	44	107
Future Vol, veh/h	280	34	56	266	44	107
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	56	56	56	56	56	56
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	500	61	100	475	79	191

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	449	100	0
Stage 1	100	-	-
Stage 2	349	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	568	956	-
Stage 1	924	-	-
Stage 2	714	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	523	956	-
Mov Cap-2 Maneuver	614	-	-
Stage 1	924	-	-
Stage 2	658	-	-

Approach	WB	NB	SB
HCM Control Delay, s	29.1	0	2.6
HCM LOS	D		







Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT
Capacity (veh/h)	-	- 614 956	998	-
HCM Lane V/C Ratio	-	- 0.814 0.064	0.079	-
HCM Control Delay (s)	-	- 31.5 9	8.9	-
HCM Lane LOS	-	- D A	A	-
HCM 95th %tile Q(veh)	-	- 8.3 0.2	0.3	-

HCM 6th TWSC
2: Monument Hill Road & Misty Acres Boulevard

2025 Total PM
09/13/2022

Intersection







Int Delay, s/veh 5.6







Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	235	22	74	192	22	69
Future Vol, veh/h	235	22	74	192	22	69
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	72	72	72	72	72	72
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	326	31	103	267	31	96

Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	261	103	0
Stage 1	103	-	-
Stage 2	158	-	-
Critical Hdwy	6.42	6.22	-
Critical Hdwy Stg 1	5.42	-	-
Critical Hdwy Stg 2	5.42	-	-
Follow-up Hdwy	3.518	3.318	-
Pot Cap-1 Maneuver	728	952	-
Stage 1	921	-	-
Stage 2	871	-	-
Platoon blocked, %		-	-
Mov Cap-1 Maneuver	709	952	-
Mov Cap-2 Maneuver	778	-	-
Stage 1	921	-	-
Stage 2	848	-	-

Approach	WB	NB	SB
HCM Control Delay, s	12.6	0	2
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT
Capacity (veh/h)	-	- 778 952 1189	-	-
HCM Lane V/C Ratio	-	- 0.42 0.032 0.026	-	-
HCM Control Delay (s)	-	- 12.9 8.9 8.1	-	-
HCM Lane LOS	-	- B A A	-	-
HCM 95th %tile Q(veh)	-	- 2.1 0.1 0.1	-	-

Intersection						
Int Delay, s/veh	34.6					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	342	41	53	324	54	125
Future Vol, veh/h	342	41	53	324	54	125
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	56	56	56	56	56	56
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	611	73	95	579	96	223
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	510	95	0	0	674	0
Stage 1	95	-	-	-	-	-
Stage 2	415	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	~ 523	962	-	-	917	-
Stage 1	929	-	-	-	-	-
Stage 2	666	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	~ 468	962	-	-	917	-
Mov Cap-2 Maneuver	~ 559	-	-	-	-	-
Stage 1	929	-	-	-	-	-
Stage 2	~ 596	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	83.4	0		2.8		
HCM LOS	F					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	WBLn2	SBL	SBT
Capacity (veh/h)	-	-	559	962	917	-
HCM Lane V/C Ratio	-	-	1.093	0.076	0.105	-
HCM Control Delay (s)	-	-	92.3	9.1	9.4	-
HCM Lane LOS	-	-	F	A	A	-
HCM 95th %tile Q(veh)	-	-	18.7	0.2	0.4	-
Notes						
~: Volume exceeds capacity		\$: Delay exceeds 300s		+: Computation Not Defined		*: All major volume in platoon













Intersection						
Int Delay, s/veh	6.5					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	287	26	79	234	26	67
Future Vol, veh/h	287	26	79	234	26	67
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	Stop	-	None	-	None
Storage Length	250	0	-	550	275	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	72	72	72	72	72	72
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	399	36	110	325	36	93
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	275	110	0	0	435	0
Stage 1	110	-	-	-	-	-
Stage 2	165	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	715	943	-	-	1125	-
Stage 1	915	-	-	-	-	-
Stage 2	864	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	692	943	-	-	1125	-
Mov Cap-2 Maneuver	766	-	-	-	-	-
Stage 1	915	-	-	-	-	-
Stage 2	836	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	14.2	0	2.3			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 766 943	1125	-		
HCM Lane V/C Ratio	-	- 0.52 0.038	0.032	-		
HCM Control Delay (s)	-	- 14.7 9	8.3	-		
HCM Lane LOS	-	- B A	A	-		
HCM 95th %tile Q(veh)	-	- 3.1 0.1	0.1	-		

Timings


2045 Total AM - #1,2,6 Signalized

2: Monument Hill Road & Misty Acres Boulevard

10/20/2022

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	345	45	65	325	55	130
Future Volume (vph)	345	45	65	325	55	130
Turn Type	Prot	Perm	NA	Perm	Perm	NA
Protected Phases	8		2			6
Permitted Phases		8		2	6	
Detector Phase	8	8	2	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	47.0	47.0	43.0	43.0	43.0	43.0
Total Split (%)	52.2%	52.2%	47.8%	47.8%	47.8%	47.8%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effct Green (s)	34.0	34.0	47.0	47.0	47.0	47.0
Actuated g/C Ratio	0.38	0.38	0.52	0.52	0.52	0.52
v/c Ratio	0.82	0.11	0.13	0.56	0.20	0.32
Control Delay	35.3	4.0	15.1	5.7	13.8	14.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	35.3	4.0	15.1	5.7	13.8	14.6
LOS	D	A	B	A	B	B
Approach Delay	31.7		7.3			14.3
Approach LOS	C		A			B
Intersection Summary						
Cycle Length: 90						
Actuated Cycle Length: 90						
Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green						
Natural Cycle: 55						
Control Type: Actuated-Coordinated						
Maximum v/c Ratio: 0.82						
Intersection Signal Delay: 17.4				Intersection LOS: B		
Intersection Capacity Utilization 36.3%				ICU Level of Service A		
Analysis Period (min) 15						













Splits and Phases: 2: Monument Hill Road & Misty Acres Boulevard



HCM 6th Signalized Intersection Summary 2: Monument Hill Road & Misty Acres Boulevard

2045 Total AM - #1,2,6 Signalized

10/20/2022

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (veh/h)	345	45	65	325	55	130
Future Volume (veh/h)	345	45	65	325	55	130
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00		1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No		No			No
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	548	71	125	625	131	310
Peak Hour Factor	0.63	0.63	0.52	0.52	0.42	0.42
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	601	535	1052	892	458	1052
Arrive On Green	0.34	0.34	0.56	0.56	0.56	0.56
Sat Flow, veh/h	1781	1585	1870	1585	712	1870
Grp Volume(v), veh/h	548	71	125	625	131	310
Grp Sat Flow(s),veh/h/ln	1781	1585	1870	1585	712	1870
Q Serve(g_s), s	26.5	2.8	2.8	25.6	9.5	7.8
Cycle Q Clear(g_c), s	26.5	2.8	2.8	25.6	12.3	7.8
Prop In Lane	1.00	1.00		1.00	1.00	
Lane Grp Cap(c), veh/h	601	535	1052	892	458	1052
V/C Ratio(X)	0.91	0.13	0.12	0.70	0.29	0.29
Avail Cap(c_a), veh/h	841	748	1052	892	458	1052
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	0.99	0.99
Uniform Delay (d), s/veh	28.5	20.7	9.2	14.2	12.1	10.3
Incr Delay (d2), s/veh	11.0	0.1	0.2	4.6	1.5	0.7
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	12.7	1.0	1.1	9.4	1.6	3.2
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	39.6	20.8	9.5	18.8	13.7	11.0
LnGrp LOS	D	C	A	B	B	B
Approach Vol, veh/h	619		750			441
Approach Delay, s/veh	37.4		17.2			11.8
Approach LOS	D		B			B
Timer - Assigned Phs	2		6		8	
Phs Duration (G+Y+Rc), s	55.1		55.1		34.9	
Change Period (Y+Rc), s	4.5		4.5		4.5	
Max Green Setting (Gmax), s	38.5		38.5		42.5	
Max Q Clear Time (g_c+l1), s	27.6		14.3		28.5	
Green Ext Time (p_c), s	2.6		3.0		1.9	
Intersection Summary						
HCM 6th Ctrl Delay			22.8			
HCM 6th LOS			C			

HCM 6th Roundabout
2: Monument Hill Road & Misty Acres Boulevard

2045 Total AM

09/13/2022













Intersection			
Intersection Delay, s/veh	11.1		
Intersection LOS	B		
Approach	WB	NB	SB
Entry Lanes	1	1	1
Conflicting Circle Lanes	1	1	1
Adj Approach Flow, veh/h	619	750	441
Demand Flow Rate, veh/h	631	766	450
Vehicles Circulating, veh/h	127	134	559
Vehicles Exiting, veh/h	771	875	199
Ped Vol Crossing Leg, #/h	0	0	0
Ped Cap Adj	1.000	1.000	1.000
Approach Delay, s/veh	8.9	11.4	13.8
Approach LOS	A	B	B
Lane	Left	Left	Left
Designated Moves	LR	TR	LT
Assumed Moves	LR	TR	LT
RT Channelized			
Lane Util	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976
Entry Flow, veh/h	631	766	450
Cap Entry Lane, veh/h	1212	1204	780
Entry HV Adj Factor	0.981	0.980	0.980
Flow Entry, veh/h	619	750	441
Cap Entry, veh/h	1189	1179	764
V/C Ratio	0.521	0.636	0.577
Control Delay, s/veh	8.9	11.4	13.8
LOS	A	B	B
95th %tile Queue, veh	3	5	4

Timings


2045 Total PM - #1,2,6 Signalized

2: Monument Hill Road & Misty Acres Boulevard

10/20/2022

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	290	30	90	235	30	80
Future Volume (vph)	290	30	90	235	30	80
Turn Type	Prot	Perm	NA	Perm	Perm	NA
Protected Phases	8		2			6
Permitted Phases		8		2	6	
Detector Phase	8	8	2	2	6	6
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	22.5
Total Split (s)	50.0	50.0	40.0	40.0	40.0	40.0
Total Split (%)	55.6%	55.6%	44.4%	44.4%	44.4%	44.4%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	4.5	4.5	4.5	4.5	4.5	4.5
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Efect Green (s)	27.0	27.0	54.0	54.0	54.0	54.0
Actuated g/C Ratio	0.30	0.30	0.60	0.60	0.60	0.60
v/c Ratio	0.76	0.08	0.11	0.30	0.06	0.10
Control Delay	37.4	6.3	11.9	5.7	6.7	6.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	37.4	6.3	11.9	5.7	6.7	6.5
LOS	D	A	B	A	A	A
Approach Delay	34.5		7.4			6.6
Approach LOS	C		A			A
Intersection Summary						
Cycle Length: 90						
Actuated Cycle Length: 90						
Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green						
Natural Cycle: 45						
Control Type: Actuated-Coordinated						
Maximum v/c Ratio: 0.76						
Intersection Signal Delay: 18.8				Intersection LOS: B		
Intersection Capacity Utilization 31.9%				ICU Level of Service A		
Analysis Period (min) 15						

Splits and Phases: 2: Monument Hill Road & Misty Acres Boulevard









HCM 6th Signalized Intersection Summary

2: Monument Hill Road & Misty Acres Boulevard

2045 Total PM - #1,2,6 Signalized

10/20/2022









Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (veh/h)	290	30	90	235	30	80
Future Volume (veh/h)	290	30	90	235	30	80
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00	1.00		1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No		No			No
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	403	42	125	326	42	111
Peak Hour Factor	0.72	0.72	0.72	0.72	0.72	0.72
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	455	405	1206	1022	662	1206
Arrive On Green	0.26	0.26	0.64	0.64	0.64	0.64
Sat Flow, veh/h	1781	1585	1870	1585	940	1870
Grp Volume(v), veh/h	403	42	125	326	42	111
Grp Sat Flow(s),veh/h/ln	1781	1585	1870	1585	940	1870
Q Serve(g_s), s	19.6	1.8	2.3	8.3	1.6	2.0
Cycle Q Clear(g_c), s	19.6	1.8	2.3	8.3	3.9	2.0
Prop In Lane	1.00	1.00		1.00	1.00	
Lane Grp Cap(c), veh/h	455	405	1206	1022	662	1206
V/C Ratio(X)	0.89	0.10	0.10	0.32	0.06	0.09
Avail Cap(c_a), veh/h	901	801	1206	1022	662	1206
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	32.2	25.6	6.1	7.2	6.8	6.0
Incr Delay (d2), s/veh	5.9	0.1	0.2	0.8	0.2	0.2
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	8.9	0.7	0.9	2.7	0.3	0.8
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	38.2	25.7	6.3	8.0	7.0	6.2
LnGrp LOS	D	C	A	A	A	A
Approach Vol, veh/h	445		451			153
Approach Delay, s/veh	37.0		7.5			6.4
Approach LOS	D		A			A
Timer - Assigned Phs	2				6	8
Phs Duration (G+Y+Rc), s	62.5				62.5	27.5
Change Period (Y+Rc), s	4.5				4.5	4.5
Max Green Setting (Gmax), s	35.5				35.5	45.5
Max Q Clear Time (g_c+l1), s	10.3				5.9	21.6
Green Ext Time (p_c), s	1.9				0.8	1.4
Intersection Summary						
HCM 6th Ctrl Delay			19.9			
HCM 6th LOS			B			

HCM 6th Roundabout
2: Monument Hill Road & Misty Acres Boulevard

2045 Total PM







09/13/2022







Intersection			
Intersection Delay, s/veh	6.3		
Intersection LOS	A		
Approach	WB	NB	SB
Entry Lanes	1	1	1
Conflicting Circle Lanes	1	1	1
Adj Approach Flow, veh/h	445	451	153
Demand Flow Rate, veh/h	454	461	156
Vehicles Circulating, veh/h	127	43	411
Vehicles Exiting, veh/h	376	524	170
Ped Vol Crossing Leg, #/h	0	0	0
Ped Cap Adj	1.000	1.000	1.000
Approach Delay, s/veh	6.7	6.0	5.7
Approach LOS	A	A	A
Lane	Left	Left	Left
Designated Moves	LR	TR	LT
Assumed Moves	LR	TR	LT
RT Channelized			
Lane Util	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976
Entry Flow, veh/h	454	461	156
Cap Entry Lane, veh/h	1212	1321	907
Entry HV Adj Factor	0.980	0.979	0.979
Flow Entry, veh/h	445	451	153
Cap Entry, veh/h	1188	1293	889
V/C Ratio	0.375	0.349	0.172
Control Delay, s/veh	6.7	6.0	5.7
LOS	A	A	A
95th %tile Queue, veh	2	2	1







Intersection						
Int Delay, s/veh	3.3					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	16	120	291	41	67	281
Future Vol, veh/h	16	120	291	41	67	281
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	57	57	57	57	57	57
Heavy Vehicles, %	2	2	4	4	3	3
Mvmt Flow	28	211	511	72	118	493
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1240	511	0	0	583	0
Stage 1	511	-	-	-	-	-
Stage 2	729	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.13	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.227	-
Pot Cap-1 Maneuver	193	563	-	-	986	-
Stage 1	602	-	-	-	-	-
Stage 2	477	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	170	563	-	-	986	-
Mov Cap-2 Maneuver	357	-	-	-	-	-
Stage 1	602	-	-	-	-	-
Stage 2	420	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	15.3	0	1.8			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 357 563	986	-		
HCM Lane V/C Ratio	-	- 0.079 0.374	0.119	-		
HCM Control Delay (s)	-	- 15.9 15.2	9.1	-		
HCM Lane LOS	-	- C C	A	-		
HCM 95th %tile Q(veh)	-	- 0.3 1.7	0.4	-		

HCM 6th TWSC
3: Monument Hill Road & Deer Creek Road

2022 Existing PM
09/12/2022







Intersection						
Int Delay, s/veh	2.3					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	26	58	220	23	81	315
Future Vol, veh/h	26	58	220	23	81	315
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	73	73	73	73	73	73
Heavy Vehicles, %	2	2	5	5	2	2
Mvmt Flow	36	79	301	32	111	432
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	955	301	0	0	333	0
Stage 1	301	-	-	-	-	-
Stage 2	654	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	287	739	-	-	1226	-
Stage 1	751	-	-	-	-	-
Stage 2	517	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	261	739	-	-	1226	-
Mov Cap-2 Maneuver	424	-	-	-	-	-
Stage 1	751	-	-	-	-	-
Stage 2	470	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	11.7	0	1.7			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 424 739	1226	-		
HCM Lane V/C Ratio	-	- 0.084 0.108	0.091	-		
HCM Control Delay (s)	-	- 14.3 10.5	8.2	-		
HCM Lane LOS	-	- B B	A	-		
HCM 95th %tile Q(veh)	-	- 0.3 0.4	0.3	-		

Intersection						
Int Delay, s/veh	3.6					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	20	129	300	44	71	290
Future Vol, veh/h	20	129	300	44	71	290
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	57	57	57	57	57	57
Heavy Vehicles, %	2	2	4	4	3	3
Mvmt Flow	35	226	526	77	125	509
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1285	526	0	0	603	0
Stage 1	526	-	-	-	-	-
Stage 2	759	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.13	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.227	-
Pot Cap-1 Maneuver	182	552	-	-	970	-
Stage 1	593	-	-	-	-	-
Stage 2	462	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	159	552	-	-	970	-
Mov Cap-2 Maneuver	343	-	-	-	-	-
Stage 1	593	-	-	-	-	-
Stage 2	402	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	16.1	0	1.8			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 343 552	970	-		
HCM Lane V/C Ratio	-	- 0.102 0.41	0.128	-		
HCM Control Delay (s)	-	- 16.7 16	9.3	-		
HCM Lane LOS	-	- C C	A	-		
HCM 95th %tile Q(veh)	-	- 0.3 2	0.4	-		

Intersection						
Int Delay, s/veh	2.4					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	30	64	227	29	87	325
Future Vol, veh/h	30	64	227	29	87	325
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	73	73	73	73	73	73
Heavy Vehicles, %	2	2	5	5	2	2
Mvmt Flow	41	88	311	40	119	445
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	994	311	0	0	351	0
Stage 1	311	-	-	-	-	-
Stage 2	683	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	272	729	-	-	1208	-
Stage 1	743	-	-	-	-	-
Stage 2	502	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	245	729	-	-	1208	-
Mov Cap-2 Maneuver	408	-	-	-	-	-
Stage 1	743	-	-	-	-	-
Stage 2	452	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	11.9	0	1.8			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 408 729 1208	-	-		
HCM Lane V/C Ratio	-	- 0.101 0.12 0.099	-	-		
HCM Control Delay (s)	-	- 14.8 10.6 8.3	-	-		
HCM Lane LOS	-	- B B A	-	-		
HCM 95th %tile Q(veh)	-	- 0.3 0.4 0.3	-	-		







HCM 6th TWSC
3: Monument Hill Road & Deer Creek Road







2025 Total AM
09/13/2022







Intersection						
Int Delay, s/veh	3.6					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	28	129	316	47	71	343
Future Vol, veh/h	28	129	316	47	71	343
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	57	57	57	57	57	57
Heavy Vehicles, %	2	2	4	4	3	3
Mvmt Flow	49	226	554	82	125	602
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1406	554	0	0	636	0
Stage 1	554	-	-	-	-	-
Stage 2	852	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.13	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.227	-
Pot Cap-1 Maneuver	153	532	-	-	943	-
Stage 1	575	-	-	-	-	-
Stage 2	418	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	133	532	-	-	943	-
Mov Cap-2 Maneuver	311	-	-	-	-	-
Stage 1	575	-	-	-	-	-
Stage 2	362	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	17.1	0	1.6			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 311 532	943	-		
HCM Lane V/C Ratio	-	- 0.158 0.425	0.132	-		
HCM Control Delay (s)	-	- 18.7 16.7	9.4	-		
HCM Lane LOS	-	- C C	A	-		
HCM 95th %tile Q(veh)	-	- 0.6 2.1	0.5	-		

HCM 6th TWSC
3: Monument Hill Road & Deer Creek Road

2025 Total PM
09/13/2022







Intersection						
Int Delay, s/veh	2.4					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	35	64	283	38	87	358
Future Vol, veh/h	35	64	283	38	87	358
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	73	73	73	73	73	73
Heavy Vehicles, %	2	2	5	5	2	2
Mvmt Flow	48	88	388	52	119	490
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1116	388	0	0	440	0
Stage 1	388	-	-	-	-	-
Stage 2	728	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	230	660	-	-	1120	-
Stage 1	686	-	-	-	-	-
Stage 2	478	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	206	660	-	-	1120	-
Mov Cap-2 Maneuver	379	-	-	-	-	-
Stage 1	686	-	-	-	-	-
Stage 2	427	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	12.9	0	1.7			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	WBLn2	SBL	SBT
Capacity (veh/h)	-	-	379	660	1120	-
HCM Lane V/C Ratio	-	-	0.127	0.133	0.106	-
HCM Control Delay (s)	-	-	15.9	11.3	8.6	-
HCM Lane LOS	-	-	C	B	A	-
HCM 95th %tile Q(veh)	-	-	0.4	0.5	0.4	-

Intersection						
Int Delay, s/veh	4.7					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	24	156	366	54	86	353
Future Vol, veh/h	24	156	366	54	86	353
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	57	57	57	57	57	57
Heavy Vehicles, %	2	2	4	4	3	3
Mvmt Flow	42	274	642	95	151	619
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1563	642	0	0	737	0
Stage 1	642	-	-	-	-	-
Stage 2	921	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.13	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.227	-
Pot Cap-1 Maneuver	123	474	-	-	864	-
Stage 1	524	-	-	-	-	-
Stage 2	388	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	101	474	-	-	864	-
Mov Cap-2 Maneuver	273	-	-	-	-	-
Stage 1	524	-	-	-	-	-
Stage 2	320	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	22.2	0	2			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 273 474	864	-		
HCM Lane V/C Ratio	-	- 0.154 0.577	0.175	-		
HCM Control Delay (s)	-	- 20.6 22.5	10	-		
HCM Lane LOS	-	- C C	B	-		
HCM 95th %tile Q(veh)	-	- 0.5 3.6	0.6	-		

Intersection						
Int Delay, s/veh	2.6					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	36	77	277	34	106	396
Future Vol, veh/h	36	77	277	34	106	396
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	73	73	73	73	73	73
Heavy Vehicles, %	2	2	5	5	2	2
Mvmt Flow	49	105	379	47	145	542
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1211	379	0	0	426	0
Stage 1	379	-	-	-	-	-
Stage 2	832	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	201	668	-	-	1133	-
Stage 1	692	-	-	-	-	-
Stage 2	427	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	175	668	-	-	1133	-
Mov Cap-2 Maneuver	335	-	-	-	-	-
Stage 1	692	-	-	-	-	-
Stage 2	372	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	13.4	0	1.8			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 335 668 1133	-	-		
HCM Lane V/C Ratio	-	- 0.147 0.158 0.128	-	-		
HCM Control Delay (s)	-	- 17.6 11.4 8.6	-	-		
HCM Lane LOS	-	- C B A	-	-		
HCM 95th %tile Q(veh)	-	- 0.5 0.6 0.4	-	-		







HCM 6th TWSC
3: Monument Hill Road & Deer Creek Road




2045 Total AM
09/13/2022

Intersection						
Int Delay, s/veh	5.1					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	35	160	385	60	90	410
Future Vol, veh/h	35	160	385	60	90	410
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	57	57	57	57	57	57
Heavy Vehicles, %	2	2	4	4	3	3
Mvmt Flow	61	281	675	105	158	719
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1710	675	0	0	780	0
Stage 1	675	-	-	-	-	-
Stage 2	1035	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.13	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.227	-
Pot Cap-1 Maneuver	100	454	-	-	833	-
Stage 1	506	-	-	-	-	-
Stage 2	342	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	81	454	-	-	833	-
Mov Cap-2 Maneuver	239	-	-	-	-	-
Stage 1	506	-	-	-	-	-
Stage 2	277	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	25	0	1.9			
HCM LOS	D					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 239 454	833	-		
HCM Lane V/C Ratio	-	- 0.257 0.618	0.19	-		
HCM Control Delay (s)	-	- 25.2 24.9	10.3	-		
HCM Lane LOS	-	- D C	B	-		
HCM 95th %tile Q(veh)	-	- 1 4.1	0.7	-		

HCM 6th TWSC
3: Monument Hill Road & Deer Creek Road




2045 Total PM
09/13/2022

Intersection						
Int Delay, s/veh	2.7					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	45	80	335	45	110	430
Future Vol, veh/h	45	80	335	45	110	430
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	150	0	-	225	475	-
Veh in Median Storage, #	2	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	73	73	73	73	73	73
Heavy Vehicles, %	2	2	5	5	2	2
Mvmt Flow	62	110	459	62	151	589
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1350	459	0	0	521	0
Stage 1	459	-	-	-	-	-
Stage 2	891	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	166	602	-	-	1045	-
Stage 1	636	-	-	-	-	-
Stage 2	401	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	142	602	-	-	1045	-
Mov Cap-2 Maneuver	305	-	-	-	-	-
Stage 1	636	-	-	-	-	-
Stage 2	343	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	15	0	1.8			
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1WBLn2	SBL	SBT		
Capacity (veh/h)	-	- 305 602 1045	-	-		
HCM Lane V/C Ratio	-	- 0.202 0.182 0.144	-	-		
HCM Control Delay (s)	-	- 19.8 12.3 9	-	-		
HCM Lane LOS	-	- C B A	-	-		
HCM 95th %tile Q(veh)	-	- 0.7 0.7 0.5	-	-		

Intersection						
Int Delay, s/veh	1.1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	16	80	122	4	0	13
Future Vol, veh/h	16	80	122	4	0	13
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	55	55	55	55	55	55
Heavy Vehicles, %	2	2	2	2	8	8
Mvmt Flow	29	145	222	7	0	24
Major/Minor	Major1	Major2		Minor2		
Conflicting Flow All	229	0	-	0	429	226
Stage 1	-	-	-	-	226	-
Stage 2	-	-	-	-	203	-
Critical Hdwy	4.12	-	-	-	6.48	6.28
Critical Hdwy Stg 1	-	-	-	-	5.48	-
Critical Hdwy Stg 2	-	-	-	-	5.48	-
Follow-up Hdwy	2.218	-	-	-	3.572	3.372
Pot Cap-1 Maneuver	1339	-	-	-	572	799
Stage 1	-	-	-	-	798	-
Stage 2	-	-	-	-	817	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1339	-	-	-	558	799
Mov Cap-2 Maneuver	-	-	-	-	558	-
Stage 1	-	-	-	-	779	-
Stage 2	-	-	-	-	817	-
Approach	EB	WB		SB		
HCM Control Delay, s	1.3	0		9.6		
HCM LOS				A		
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1339	-	-	-	799	
HCM Lane V/C Ratio	0.022	-	-	-	0.03	
HCM Control Delay (s)	7.7	0	-	-	9.6	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.1	

Intersection




Int Delay, s/veh 2.1




Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	18	82	53	11	11	19
Future Vol, veh/h	18	82	53	11	11	19
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	69	69	69	69	69	69
Heavy Vehicles, %	2	2	2	2	3	3
Mvmt Flow	26	119	77	16	16	28

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	93	0	0 256 85
Stage 1	-	-	- 85 -
Stage 2	-	-	- 171 -
Critical Hdwy	4.12	-	- 6.43 6.23
Critical Hdwy Stg 1	-	-	- 5.43 -
Critical Hdwy Stg 2	-	-	- 5.43 -
Follow-up Hdwy	2.218	-	- 3.527 3.327
Pot Cap-1 Maneuver	1501	-	- 731 971
Stage 1	-	-	- 936 -
Stage 2	-	-	- 857 -
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1501	-	- 717 971
Mov Cap-2 Maneuver	-	-	- 717 -
Stage 1	-	-	- 918 -
Stage 2	-	-	- 857 -

Approach	EB	WB	SB
HCM Control Delay, s	1.3	0	9.4
HCM LOS			A

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1501	-	-	-	859
HCM Lane V/C Ratio	0.017	-	-	-	0.051
HCM Control Delay (s)	7.4	0	-	-	9.4
HCM Lane LOS	A	A	-	-	A
HCM 95th %tile Q(veh)	0.1	-	-	-	0.2




Intersection						
Int Delay, s/veh	1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	16	86	135	4	0	13
Future Vol, veh/h	16	86	135	4	0	13
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	55	55	55	55	55	55
Heavy Vehicles, %	2	2	2	2	8	8
Mvmt Flow	29	156	245	7	0	24
Major/Minor	Major1	Major2		Minor2		
Conflicting Flow All	252	0	-	0	463	249
Stage 1	-	-	-	-	249	-
Stage 2	-	-	-	-	214	-
Critical Hdwy	4.12	-	-	-	6.48	6.28
Critical Hdwy Stg 1	-	-	-	-	5.48	-
Critical Hdwy Stg 2	-	-	-	-	5.48	-
Follow-up Hdwy	2.218	-	-	-	3.572	3.372
Pot Cap-1 Maneuver	1313	-	-	-	546	775
Stage 1	-	-	-	-	779	-
Stage 2	-	-	-	-	808	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1313	-	-	-	533	775
Mov Cap-2 Maneuver	-	-	-	-	533	-
Stage 1	-	-	-	-	760	-
Stage 2	-	-	-	-	808	-
Approach	EB	WB		SB		
HCM Control Delay, s	1.2	0		9.8		
HCM LOS				A		
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1313	-	-	-	-	775
HCM Lane V/C Ratio	0.022	-	-	-	-	0.03
HCM Control Delay (s)	7.8	0	-	-	-	9.8
HCM Lane LOS	A	A	-	-	-	A
HCM 95th %tile Q(veh)	0.1	-	-	-	-	0.1

Intersection						
Int Delay, s/veh	2					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	19	93	62	11	11	20
Future Vol, veh/h	19	93	62	11	11	20
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	69	69	69	69	69	69
Heavy Vehicles, %	2	2	2	2	3	3
Mvmt Flow	28	135	90	16	16	29
Major/Minor	Major1	Major2		Minor2		
Conflicting Flow All	106	0	-	0	289	98
Stage 1	-	-	-	-	98	-
Stage 2	-	-	-	-	191	-
Critical Hdwy	4.12	-	-	-	6.43	6.23
Critical Hdwy Stg 1	-	-	-	-	5.43	-
Critical Hdwy Stg 2	-	-	-	-	5.43	-
Follow-up Hdwy	2.218	-	-	-	3.527	3.327
Pot Cap-1 Maneuver	1485	-	-	-	699	955
Stage 1	-	-	-	-	923	-
Stage 2	-	-	-	-	839	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1485	-	-	-	685	955
Mov Cap-2 Maneuver	-	-	-	-	685	-
Stage 1	-	-	-	-	905	-
Stage 2	-	-	-	-	839	-
Approach	EB	WB		SB		
HCM Control Delay, s	1.3	0		9.5		
HCM LOS				A		
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1485	-	-	-	838	
HCM Lane V/C Ratio	0.019	-	-	-	0.054	
HCM Control Delay (s)	7.5	0	-	-	9.5	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.2	

HCM 6th TWSC
4: Deer Creek Road & Base Camp Road

2025 Total AM

09/13/2022




Intersection						
Int Delay, s/veh	1.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	19	86	135	7	8	21
Future Vol, veh/h	19	86	135	7	8	21
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	55	55	55	55	55	55
Heavy Vehicles, %	2	2	2	2	8	8
Mvmt Flow	35	156	245	13	15	38
Major/Minor	Major1	Major2		Minor2		
Conflicting Flow All	258	0	-	0	478	252
Stage 1	-	-	-	-	252	-
Stage 2	-	-	-	-	226	-
Critical Hdwy	4.12	-	-	-	6.48	6.28
Critical Hdwy Stg 1	-	-	-	-	5.48	-
Critical Hdwy Stg 2	-	-	-	-	5.48	-
Follow-up Hdwy	2.218	-	-	-	3.572	3.372
Pot Cap-1 Maneuver	1307	-	-	-	535	772
Stage 1	-	-	-	-	776	-
Stage 2	-	-	-	-	798	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1307	-	-	-	519	772
Mov Cap-2 Maneuver	-	-	-	-	519	-
Stage 1	-	-	-	-	753	-
Stage 2	-	-	-	-	798	-
Approach	EB	WB		SB		
HCM Control Delay, s	1.4	0		10.7		
HCM LOS				B		
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1307	-	-	-	680	
HCM Lane V/C Ratio	0.026	-	-	-	0.078	
HCM Control Delay (s)	7.8	0	-	-	10.7	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.3	

HCM 6th TWSC
4: Deer Creek Road & Base Camp Road

2025 Total PM
09/13/2022

Intersection




Int Delay, s/veh 2.5




Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	28	93	62	20	16	25
Future Vol, veh/h	28	93	62	20	16	25
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	69	69	69	69	69	69
Heavy Vehicles, %	2	2	2	2	3	3
Mvmt Flow	41	135	90	29	23	36

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	119	0	0 322 105
Stage 1	-	-	- 105 -
Stage 2	-	-	- 217 -
Critical Hdwy	4.12	-	- 6.43 6.23
Critical Hdwy Stg 1	-	-	- 5.43 -
Critical Hdwy Stg 2	-	-	- 5.43 -
Follow-up Hdwy	2.218	-	- 3.527 3.327
Pot Cap-1 Maneuver	1469	-	- 670 947
Stage 1	-	-	- 917 -
Stage 2	-	-	- 817 -
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1469	-	- 650 947
Mov Cap-2 Maneuver	-	-	- 650 -
Stage 1	-	-	- 889 -
Stage 2	-	-	- 817 -

Approach	EB	WB	SB
HCM Control Delay, s	1.7	0	9.8
HCM LOS			A

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1469	-	-	-	804
HCM Lane V/C Ratio	0.028	-	-	-	0.074
HCM Control Delay (s)	7.5	0	-	-	9.8
HCM Lane LOS	A	A	-	-	A
HCM 95th %tile Q(veh)	0.1	-	-	-	0.2

Intersection						
Int Delay, s/veh	1.1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	20	105	162	5	0	16
Future Vol, veh/h	20	105	162	5	0	16
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	55	55	55	55	55	55
Heavy Vehicles, %	2	2	2	2	8	8
Mvmt Flow	36	191	295	9	0	29
Major/Minor	Major1	Major2		Minor2		
Conflicting Flow All	304	0	-	0	563	300
Stage 1	-	-	-	-	300	-
Stage 2	-	-	-	-	263	-
Critical Hdwy	4.12	-	-	-	6.48	6.28
Critical Hdwy Stg 1	-	-	-	-	5.48	-
Critical Hdwy Stg 2	-	-	-	-	5.48	-
Follow-up Hdwy	2.218	-	-	-	3.572	3.372
Pot Cap-1 Maneuver	1257	-	-	-	477	726
Stage 1	-	-	-	-	738	-
Stage 2	-	-	-	-	767	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1257	-	-	-	462	726
Mov Cap-2 Maneuver	-	-	-	-	462	-
Stage 1	-	-	-	-	714	-
Stage 2	-	-	-	-	767	-
Approach	EB	WB		SB		
HCM Control Delay, s	1.3	0		10.2		
HCM LOS	B					
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1257	-	-	-	726	
HCM Lane V/C Ratio	0.029	-	-	-	0.04	
HCM Control Delay (s)	7.9	0	-	-	10.2	
HCM Lane LOS	A	A	-	-	B	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.1	




Intersection						
Int Delay, s/veh	2.1					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	23	112	74	14	14	24
Future Vol, veh/h	23	112	74	14	14	24
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	69	69	69	69	69	69
Heavy Vehicles, %	2	2	2	2	3	3
Mvmt Flow	33	162	107	20	20	35
Major/Minor	Major1	Major2		Minor2		
Conflicting Flow All	127	0	-	0	345	117
Stage 1	-	-	-	-	117	-
Stage 2	-	-	-	-	228	-
Critical Hdwy	4.12	-	-	-	6.43	6.23
Critical Hdwy Stg 1	-	-	-	-	5.43	-
Critical Hdwy Stg 2	-	-	-	-	5.43	-
Follow-up Hdwy	2.218	-	-	-	3.527	3.327
Pot Cap-1 Maneuver	1459	-	-	-	650	932
Stage 1	-	-	-	-	906	-
Stage 2	-	-	-	-	808	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1459	-	-	-	634	932
Mov Cap-2 Maneuver	-	-	-	-	634	-
Stage 1	-	-	-	-	883	-
Stage 2	-	-	-	-	808	-
Approach	EB	WB		SB		
HCM Control Delay, s	1.3	0		9.9		
HCM LOS				A		
Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1	
Capacity (veh/h)	1459	-	-	-	794	
HCM Lane V/C Ratio	0.023	-	-	-	0.069	
HCM Control Delay (s)	7.5	0	-	-	9.9	
HCM Lane LOS	A	A	-	-	A	
HCM 95th %tile Q(veh)	0.1	-	-	-	0.2	

HCM 6th TWSC
4: Deer Creek Road & Base Camp Road

2045 Total AM
09/13/2022

Intersection

Int Delay, s/veh 1.8

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	25	105	165	10	10	25
Future Vol, veh/h	25	105	165	10	10	25
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	55	55	55	55	55	55
Heavy Vehicles, %	2	2	2	2	8	8
Mvmt Flow	45	191	300	18	18	45

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	318	0	0 590 309
Stage 1	-	-	- 309 -
Stage 2	-	-	- 281 -
Critical Hdwy	4.12	-	- 6.48 6.28
Critical Hdwy Stg 1	-	-	- 5.48 -
Critical Hdwy Stg 2	-	-	- 5.48 -
Follow-up Hdwy	2.218	-	- 3.572 3.372
Pot Cap-1 Maneuver	1242	-	- 460 717
Stage 1	-	-	- 731 -
Stage 2	-	-	- 753 -
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1242	-	- 441 717
Mov Cap-2 Maneuver	-	-	- 441 -
Stage 1	-	-	- 701 -
Stage 2	-	-	- 753 -

Approach	EB	WB	SB
HCM Control Delay, s	1.5	0	11.6
HCM LOS			B




Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1242	-	-	-	608
HCM Lane V/C Ratio	0.037	-	-	-	0.105
HCM Control Delay (s)	8	0	-	-	11.6
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0.1	-	-	-	0.3

HCM 6th TWSC
4: Deer Creek Road & Base Camp Road

2045 Total PM
09/13/2022

Intersection

Int Delay, s/veh 2.6

Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Vol, veh/h	35	115	75	25	20	30
Future Vol, veh/h	35	115	75	25	20	30
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	-	0	0	-	0	-
Grade, %	-	0	0	-	0	-
Peak Hour Factor	69	69	69	69	69	69
Heavy Vehicles, %	2	2	2	2	3	3
Mvmt Flow	51	167	109	36	29	43

Major/Minor	Major1	Major2	Minor2
Conflicting Flow All	145	0	0 396 127
Stage 1	-	-	- 127 -
Stage 2	-	-	- 269 -
Critical Hdwy	4.12	-	- 6.43 6.23
Critical Hdwy Stg 1	-	-	- 5.43 -
Critical Hdwy Stg 2	-	-	- 5.43 -
Follow-up Hdwy	2.218	-	- 3.527 3.327
Pot Cap-1 Maneuver	1437	-	- 607 921
Stage 1	-	-	- 896 -
Stage 2	-	-	- 774 -
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	1437	-	- 583 921
Mov Cap-2 Maneuver	-	-	- 583 -
Stage 1	-	-	- 861 -
Stage 2	-	-	- 774 -

Approach	EB	WB	SB
HCM Control Delay, s	1.8	0	10.3
HCM LOS			B

Minor Lane/Major Mvmt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)	1437	-	-	-	748
HCM Lane V/C Ratio	0.035	-	-	-	0.097
HCM Control Delay (s)	7.6	0	-	-	10.3
HCM Lane LOS	A	A	-	-	B
HCM 95th %tile Q(veh)	0.1	-	-	-	0.3

Intersection												
Int Delay, s/veh	4.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	13	7	49	35	17	0	55	53	7	0	199	72
Future Vol, veh/h	13	7	49	35	17	0	55	53	7	0	199	72
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	76	76	76	76	76	76	76	76	76	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	9	64	46	22	0	72	70	9	0	262	95
Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	540	533	310	565	576	75	357	0	0	79	0	0
Stage 1	310	310	-	219	219	-	-	-	-	-	-	-
Stage 2	230	223	-	346	357	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	453	453	730	436	428	986	1202	-	-	1519	-	-
Stage 1	700	659	-	783	722	-	-	-	-	-	-	-
Stage 2	773	719	-	670	628	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	413	424	730	372	401	986	1202	-	-	1519	-	-
Mov Cap-2 Maneuver	413	424	-	372	401	-	-	-	-	-	-	-
Stage 1	656	659	-	734	677	-	-	-	-	-	-	-
Stage 2	700	674	-	602	628	-	-	-	-	-	-	-
Approach	EB		WB		NB		SB					
HCM Control Delay, s	12.1		16.5		3.9		0					
HCM LOS	B		C									
Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR					
Capacity (veh/h)	1202	-	-	599	381	1519	-	-				
HCM Lane V/C Ratio	0.06	-	-	0.152	0.18	-	-	-				
HCM Control Delay (s)	8.2	0	-	12.1	16.5	0	-	-				
HCM Lane LOS	A	A	-	B	C	A	-	-				
HCM 95th %tile Q(veh)	0.2	-	-	0.5	0.6	0	-	-				

Intersection												
Int Delay, s/veh	3.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	22	9	39	15	4	0	63	162	30	1	137	12
Future Vol, veh/h	22	9	39	15	4	0	63	162	30	1	137	12
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	96	96	96	96	96	96	96	96	96	96	96	96
Heavy Vehicles, %	2	2	2	5	5	5	2	2	2	4	4	4
Mvmt Flow	23	9	41	16	4	0	66	169	31	1	143	13

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	471	484	150	494	475	185	156	0	0	200	0	0
Stage 1	152	152	-	317	317	-	-	-	-	-	-	-
Stage 2	319	332	-	177	158	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.15	6.55	6.25	4.12	-	-	4.14	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.545	4.045	3.345	2.218	-	-	2.236	-	-
Pot Cap-1 Maneuver	503	483	896	481	484	850	1424	-	-	1360	-	-
Stage 1	850	772	-	688	649	-	-	-	-	-	-	-
Stage 2	693	644	-	818	761	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	479	457	896	434	458	850	1424	-	-	1360	-	-
Mov Cap-2 Maneuver	479	457	-	434	458	-	-	-	-	-	-	-
Stage 1	806	771	-	652	615	-	-	-	-	-	-	-
Stage 2	653	611	-	771	760	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	11.3		13.6		1.9		0.1	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1424	-	-	641	439	1360	-
HCM Lane V/C Ratio	0.046	-	-	0.114	0.045	0.001	-
HCM Control Delay (s)	7.7	0	-	11.3	13.6	7.6	0
HCM Lane LOS	A	A	-	B	B	A	A
HCM 95th %tile Q(veh)	0.1	-	-	0.4	0.1	0	-

Intersection												
Int Delay, s/veh	4.8											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	13	9	52	44	22	0	62	55	11	0	205	74
Future Vol, veh/h	13	9	52	44	22	0	62	55	11	0	205	74
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	76	76	76	76	76	76	76	76	76	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	12	68	58	29	0	82	72	14	0	270	97
Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	577	569	319	602	610	79	367	0	0	86	0	0
Stage 1	319	319	-	243	243	-	-	-	-	-	-	-
Stage 2	258	250	-	359	367	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	428	432	722	412	409	981	1192	-	-	1510	-	-
Stage 1	693	653	-	761	705	-	-	-	-	-	-	-
Stage 2	747	700	-	659	622	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	381	401	722	344	380	981	1192	-	-	1510	-	-
Mov Cap-2 Maneuver	381	401	-	344	380	-	-	-	-	-	-	-
Stage 1	643	653	-	706	654	-	-	-	-	-	-	-
Stage 2	663	650	-	586	622	-	-	-	-	-	-	-
Approach	EB		WB		NB		SB					
HCM Control Delay, s	12.5		18.4		4		0					
HCM LOS	B		C									
Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR					
Capacity (veh/h)	1192	-	-	575	355	1510	-	-				
HCM Lane V/C Ratio	0.068	-	-	0.169	0.245	-	-	-				
HCM Control Delay (s)	8.2	0	-	12.5	18.4	0	-	-				
HCM Lane LOS	A	A	-	B	C	A	-	-				
HCM 95th %tile Q(veh)	0.2	-	-	0.6	0.9	0	-	-				

Intersection												
Int Delay, s/veh	3.5											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	23	13	45	21	7	0	69	167	39	1	141	12
Future Vol, veh/h	23	13	45	21	7	0	69	167	39	1	141	12
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	96	96	96	96	96	96	96	96	96	96	96	96
Heavy Vehicles, %	2	2	2	5	5	5	2	2	2	4	4	4
Mvmt Flow	24	14	47	22	7	0	72	174	41	1	147	13

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	498	515	154	525	501	195	160	0	0	215	0	0
Stage 1	156	156	-	339	339	-	-	-	-	-	-	-
Stage 2	342	359	-	186	162	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.15	6.55	6.25	4.12	-	-	4.14	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.545	4.045	3.345	2.218	-	-	2.236	-	-
Pot Cap-1 Maneuver	483	464	892	458	468	839	1419	-	-	1343	-	-
Stage 1	846	769	-	669	635	-	-	-	-	-	-	-
Stage 2	673	627	-	809	758	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	455	437	892	405	440	839	1419	-	-	1343	-	-
Mov Cap-2 Maneuver	455	437	-	405	440	-	-	-	-	-	-	-
Stage 1	797	768	-	630	598	-	-	-	-	-	-	-
Stage 2	626	591	-	752	757	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	11.7		14.4		1.9		0	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1419	-	-	620	413	1343	-
HCM Lane V/C Ratio	0.051	-	-	0.136	0.071	0.001	-
HCM Control Delay (s)	7.7	0	-	11.7	14.4	7.7	0
HCM Lane LOS	A	A	-	B	B	A	A
HCM 95th %tile Q(veh)	0.2	-	-	0.5	0.2	0	-

HCM 6th Roundabout
5: Woodmoor Drive & Deer Creek Road

2025 Total AM - Roundabout

09/13/2022

Intersection				
Intersection Delay, s/veh	5.2			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	108	87	172	367
Demand Flow Rate, veh/h	110	89	175	374
Vehicles Circulating, veh/h	334	178	29	177
Vehicles Exiting, veh/h	217	26	415	90
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	4.8	3.8	3.8	6.3
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	110	89	175	374
Cap Entry Lane, veh/h	982	1151	1340	1152
Entry HV Adj Factor	0.980	0.982	0.980	0.980
Flow Entry, veh/h	108	87	172	367
Cap Entry, veh/h	962	1130	1313	1129
V/C Ratio	0.112	0.077	0.131	0.325
Control Delay, s/veh	4.8	3.8	3.8	6.3
LOS	A	A	A	A
95th %tile Queue, veh	0	0	0	1

HCM 6th TWSC
5: Woodmoor Drive & Deer Creek Road

2025 Total AM
09/13/2022

Intersection												
Int Delay, s/veh	5.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	13	9	60	44	22	0	65	55	11	0	205	74
Future Vol, veh/h	13	9	60	44	22	0	65	55	11	0	205	74
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	76	76	76	76	76	76	76	76	76	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	17	12	79	58	29	0	86	72	14	0	270	97

Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	585	577	319	615	618	79	367	0	0	86	0	0
Stage 1	319	319	-	251	251	-	-	-	-	-	-	-
Stage 2	266	258	-	364	367	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	422	427	722	403	405	981	1192	-	-	1510	-	-
Stage 1	693	653	-	753	699	-	-	-	-	-	-	-
Stage 2	739	694	-	655	622	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	374	395	722	330	374	981	1192	-	-	1510	-	-
Mov Cap-2 Maneuver	374	395	-	330	374	-	-	-	-	-	-	-
Stage 1	640	653	-	696	646	-	-	-	-	-	-	-
Stage 2	652	641	-	573	622	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	12.6		19		4.1		0	
HCM LOS	B		C					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1192	-	-	583	343	1510	-
HCM Lane V/C Ratio	0.072	-	-	0.185	0.253	-	-
HCM Control Delay (s)	8.3	0	-	12.6	19	0	-
HCM Lane LOS	A	A	-	B	C	A	-
HCM 95th %tile Q(veh)	0.2	-	-	0.7	1	0	-

HCM 6th Roundabout
5: Woodmoor Drive & Deer Creek Road

2025 Total PM - Roundabout

09/13/2022

Intersection				
Intersection Delay, s/veh	4.4			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	90	29	296	160
Demand Flow Rate, veh/h	91	30	302	166
Vehicles Circulating, veh/h	177	284	39	113
Vehicles Exiting, veh/h	102	57	229	201
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	3.8	3.9	4.7	4.2
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	91	30	302	166
Cap Entry Lane, veh/h	1152	1033	1326	1230
Entry HV Adj Factor	0.986	0.956	0.979	0.965
Flow Entry, veh/h	90	29	296	160
Cap Entry, veh/h	1136	987	1298	1186
V/C Ratio	0.079	0.029	0.228	0.135
Control Delay, s/veh	3.8	3.9	4.7	4.2
LOS	A	A	A	A
95th %tile Queue, veh	0	0	1	0

Intersection												
Int Delay, s/veh	3.7											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	23	13	50	21	7	0	78	167	39	1	141	12
Future Vol, veh/h	23	13	50	21	7	0	78	167	39	1	141	12
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	96	96	96	96	96	96	96	96	96	96	96	96
Heavy Vehicles, %	2	2	2	5	5	5	2	2	2	4	4	4
Mvmt Flow	24	14	52	22	7	0	81	174	41	1	147	13

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	516	533	154	546	519	195	160	0	0	215	0	0
Stage 1	156	156	-	357	357	-	-	-	-	-	-	-
Stage 2	360	377	-	189	162	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.15	6.55	6.25	4.12	-	-	4.14	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.545	4.045	3.345	2.218	-	-	2.236	-	-
Pot Cap-1 Maneuver	470	453	892	444	457	839	1419	-	-	1343	-	-
Stage 1	846	769	-	655	623	-	-	-	-	-	-	-
Stage 2	658	616	-	806	758	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	440	423	892	388	427	839	1419	-	-	1343	-	-
Mov Cap-2 Maneuver	440	423	-	388	427	-	-	-	-	-	-	-
Stage 1	791	768	-	612	583	-	-	-	-	-	-	-
Stage 2	608	576	-	745	757	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	11.8		14.8		2.1		0	
HCM LOS	B		B					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1419	-	-	618	397	1343	-
HCM Lane V/C Ratio	0.057	-	-	0.145	0.073	0.001	-
HCM Control Delay (s)	7.7	0	-	11.8	14.8	7.7	0
HCM Lane LOS	A	A	-	B	B	A	A
HCM 95th %tile Q(veh)	0.2	-	-	0.5	0.2	0	-

Intersection												
Int Delay, s/veh	5.9											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	16	11	64	52	25	0	74	67	13	0	250	91
Future Vol, veh/h	16	11	64	52	25	0	74	67	13	0	250	91
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	76	76	76	76	76	76	76	76	76	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	21	14	84	68	33	0	97	88	17	0	329	120

Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	696	688	389	729	740	97	449	0	0	105	0	0
Stage 1	389	389	-	291	291	-	-	-	-	-	-	-
Stage 2	307	299	-	438	449	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	356	369	659	338	345	959	1111	-	-	1486	-	-
Stage 1	635	608	-	717	672	-	-	-	-	-	-	-
Stage 2	703	666	-	597	572	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	304	335	659	265	313	959	1111	-	-	1486	-	-
Mov Cap-2 Maneuver	304	335	-	265	313	-	-	-	-	-	-	-
Stage 1	576	608	-	650	610	-	-	-	-	-	-	-
Stage 2	603	604	-	508	572	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	14.5		25.1		4.1		0	
HCM LOS	B		D					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1111	-	-	498	279	1486	-
HCM Lane V/C Ratio	0.088	-	-	0.24	0.363	-	-
HCM Control Delay (s)	8.6	0	-	14.5	25.1	0	-
HCM Lane LOS	A	A	-	B	D	A	-
HCM 95th %tile Q(veh)	0.3	-	-	0.9	1.6	0	-

Intersection												
Int Delay, s/veh	3.8											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	28	15	54	25	8	0	83	204	46	1	172	15
Future Vol, veh/h	28	15	54	25	8	0	83	204	46	1	172	15
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	96	96	96	96	96	96	96	96	96	96	96	96
Heavy Vehicles, %	2	2	2	5	5	5	2	2	2	4	4	4
Mvmt Flow	29	16	56	26	8	0	86	213	48	1	179	16

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	602	622	187	634	606	237	195	0	0	261	0	0
Stage 1	189	189	-	409	409	-	-	-	-	-	-	-
Stage 2	413	433	-	225	197	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.15	6.55	6.25	4.12	-	-	4.14	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.545	4.045	3.345	2.218	-	-	2.236	-	-
Pot Cap-1 Maneuver	412	403	855	388	407	795	1378	-	-	1292	-	-
Stage 1	813	744	-	613	591	-	-	-	-	-	-	-
Stage 2	616	582	-	771	732	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	382	373	855	331	377	795	1378	-	-	1292	-	-
Mov Cap-2 Maneuver	382	373	-	331	377	-	-	-	-	-	-	-
Stage 1	754	743	-	568	548	-	-	-	-	-	-	-
Stage 2	562	540	-	704	731	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	13		16.7		1.9		0	
HCM LOS	B		C					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1378	-	-	549	341	1292	-
HCM Lane V/C Ratio	0.063	-	-	0.184	0.101	0.001	-
HCM Control Delay (s)	7.8	0	-	13	16.7	7.8	0
HCM Lane LOS	A	A	-	B	C	A	A
HCM 95th %tile Q(veh)	0.2	-	-	0.7	0.3	0	-

Intersection				
Intersection Delay, s/veh	6.2			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	145	105	217	454
Demand Flow Rate, veh/h	148	107	221	464
Vehicles Circulating, veh/h	409	228	47	214
Vehicles Exiting, veh/h	268	40	510	121
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	5.7	4.2	4.2	7.8
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	148	107	221	464
Cap Entry Lane, veh/h	909	1094	1315	1109
Entry HV Adj Factor	0.977	0.984	0.983	0.979
Flow Entry, veh/h	145	105	217	454
Cap Entry, veh/h	888	1077	1292	1086
V/C Ratio	0.163	0.098	0.168	0.418
Control Delay, s/veh	5.7	4.2	4.2	7.8
LOS	A	A	A	A
95th %tile Queue, veh	1	0	1	2

HCM 6th TWSC
5: Woodmoor Drive & Deer Creek Road

2045 Total AM
09/13/2022

Intersection												
Int Delay, s/veh	6.7											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	20	15	75	55	25	0	80	70	15	0	250	95
Future Vol, veh/h	20	15	75	55	25	0	80	70	15	0	250	95
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	76	76	76	76	76	76	76	76	76	76	76	76
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	26	20	99	72	33	0	105	92	20	0	329	125

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	721	714	392	763	766	102	454	0	0	112	0	0
Stage 1	392	392	-	312	312	-	-	-	-	-	-	-
Stage 2	329	322	-	451	454	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-
Pot Cap-1 Maneuver	343	357	657	321	333	953	1107	-	-	1478	-	-
Stage 1	633	606	-	699	658	-	-	-	-	-	-	-
Stage 2	684	651	-	588	569	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	290	321	657	240	299	953	1107	-	-	1478	-	-
Mov Cap-2 Maneuver	290	321	-	240	299	-	-	-	-	-	-	-
Stage 1	569	606	-	628	592	-	-	-	-	-	-	-
Stage 2	581	585	-	483	569	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	15.7		28.5		4.2		0	
HCM LOS	C		D					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1107	-	-	479	256	1478	-
HCM Lane V/C Ratio	0.095	-	-	0.302	0.411	-	-
HCM Control Delay (s)	8.6	0	-	15.7	28.5	0	-
HCM Lane LOS	A	A	-	C	D	A	-
HCM 95th %tile Q(veh)	0.3	-	-	1.3	1.9	0	-

HCM 6th Roundabout
5: Woodmoor Drive & Deer Creek Road

2045 Total PM - Roundabout

09/13/2022

Intersection				
Intersection Delay, s/veh	4.9			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	109	36	365	203
Demand Flow Rate, veh/h	111	37	372	211
Vehicles Circulating, veh/h	221	351	53	138
Vehicles Exiting, veh/h	128	74	279	250
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	4.2	4.2	5.3	4.7
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	111	37	372	211
Cap Entry Lane, veh/h	1101	965	1307	1199
Entry HV Adj Factor	0.979	0.960	0.980	0.961
Flow Entry, veh/h	109	36	365	203
Cap Entry, veh/h	1078	926	1282	1152
V/C Ratio	0.101	0.038	0.285	0.176
Control Delay, s/veh	4.2	4.2	5.3	4.7
LOS	A	A	A	A
95th %tile Queue, veh	0	0	1	1

HCM 6th TWSC
5: Woodmoor Drive & Deer Creek Road

2045 Total PM
09/13/2022

Intersection												
Int Delay, s/veh	4.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕			↕			↕	
Traffic Vol, veh/h	30	15	60	25	10	0	95	205	50	5	175	15
Future Vol, veh/h	30	15	60	25	10	0	95	205	50	5	175	15
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	96	96	96	96	96	96	96	96	96	96	96	96
Heavy Vehicles, %	2	2	2	5	5	5	2	2	2	4	4	4
Mvmt Flow	31	16	63	26	10	0	99	214	52	5	182	16

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	643	664	190	678	646	240	198	0	0	266	0	0
Stage 1	200	200	-	438	438	-	-	-	-	-	-	-
Stage 2	443	464	-	240	208	-	-	-	-	-	-	-
Critical Hdwy	7.12	6.52	6.22	7.15	6.55	6.25	4.12	-	-	4.14	-	-
Critical Hdwy Stg 1	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.12	5.52	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.518	4.018	3.318	3.545	4.045	3.345	2.218	-	-	2.236	-	-
Pot Cap-1 Maneuver	386	381	852	362	386	792	1375	-	-	1286	-	-
Stage 1	802	736	-	592	574	-	-	-	-	-	-	-
Stage 2	594	564	-	757	724	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	352	347	852	302	352	792	1375	-	-	1286	-	-
Mov Cap-2 Maneuver	352	347	-	302	352	-	-	-	-	-	-	-
Stage 1	734	733	-	542	525	-	-	-	-	-	-	-
Stage 2	533	516	-	684	721	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	13.6		17.9		2.1		0.2	
HCM LOS	B		C					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1375	-	-	528	315	1286	-
HCM Lane V/C Ratio	0.072	-	-	0.207	0.116	0.004	-
HCM Control Delay (s)	7.8	0	-	13.6	17.9	7.8	0
HCM Lane LOS	A	A	-	B	C	A	A
HCM 95th %tile Q(veh)	0.2	-	-	0.8	0.4	0	-

Intersection												
Int Delay, s/veh	3.4											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕	↗		↕		↗	↕		↗	↕	
Traffic Vol, veh/h	6	2	287	1	0	0	287	349	19	1	430	63
Future Vol, veh/h	6	2	287	1	0	0	287	349	19	1	430	63
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	-	0	-	-	0	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	73	73	73	73	73	73	73	73	73	73	73	73
Heavy Vehicles, %	4	4	4	5	5	5	4	4	4	5	5	5
Mvmt Flow	8	3	393	1	0	0	393	478	26	1	589	86
Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	1911	1924	-	1913	1954	491	675	0	0	504	0	0
Stage 1	634	634	-	1277	1277	-	-	-	-	-	-	-
Stage 2	1277	1290	-	636	677	-	-	-	-	-	-	-
Critical Hdwy	7.14	6.54	-	7.15	6.55	6.25	4.14	-	-	4.15	-	-
Critical Hdwy Stg 1	6.14	5.54	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.14	5.54	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.536	4.036	-	3.545	4.045	3.345	2.236	-	-	2.245	-	-
Pot Cap-1 Maneuver	51	66	0	50	63	571	907	-	-	1045	-	-
Stage 1	464	470	0	201	234	-	-	-	-	-	-	-
Stage 2	202	232	0	461	448	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	34	37	-	32	36	571	907	-	-	1045	-	-
Mov Cap-2 Maneuver	85	104	-	51	47	-	-	-	-	-	-	-
Stage 1	263	470	-	114	133	-	-	-	-	-	-	-
Stage 2	114	132	-	458	448	-	-	-	-	-	-	-
Approach	EB		WB		NB		SB					
HCM Control Delay, s	51.1		77.5		5.2		0					
HCM LOS	F		F									
Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	SBL	SBT	SBR			
Capacity (veh/h)	907	-	-	89	-	51	1045	-	-			
HCM Lane V/C Ratio	0.433	-	-	0.123	-	0.027	0.001	-	-			
HCM Control Delay (s)	12	-	-	51.1	0	77.5	8.4	-	-			
HCM Lane LOS	B	-	-	F	A	F	A	-	-			
HCM 95th %tile Q(veh)	2.2	-	-	0.4	-	0.1	0	-	-			

Intersection												
Int Delay, s/veh	2.5											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↰	↱		↰	↱	↰	↱		↰	↱	
Traffic Vol, veh/h	1	1	341	13	1	1	219	313	7	2	399	28
Future Vol, veh/h	1	1	341	13	1	1	219	313	7	2	399	28
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	-	0	-	-	0	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	85	85	85	85	85	85	85	85	85	85	85	85
Heavy Vehicles, %	3	3	3	2	2	2	2	2	2	6	6	6
Mvmt Flow	1	1	401	15	1	1	258	368	8	2	469	33

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	1379	1382	-	1378	1394	372	502	0	0	376	0	0
Stage 1	490	490	-	888	888	-	-	-	-	-	-	-
Stage 2	889	892	-	490	506	-	-	-	-	-	-	-
Critical Hdwy	7.13	6.53	-	7.12	6.52	6.22	4.12	-	-	4.16	-	-
Critical Hdwy Stg 1	6.13	5.53	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.13	5.53	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.527	4.027	-	3.518	4.018	3.318	2.218	-	-	2.254	-	-
Pot Cap-1 Maneuver	121	143	0	122	141	674	1062	-	-	1161	-	-
Stage 1	558	547	0	338	362	-	-	-	-	-	-	-
Stage 2	336	359	0	560	540	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	98	108	-	99	106	674	1062	-	-	1161	-	-
Mov Cap-2 Maneuver	184	207	-	171	175	-	-	-	-	-	-	-
Stage 1	422	546	-	256	274	-	-	-	-	-	-	-
Stage 2	253	272	-	558	539	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	23.7		27.2		3.8		0	
HCM LOS	C		D					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1062	-	-	195	-	180	1161	-	-
HCM Lane V/C Ratio	0.243	-	-	0.012	-	0.098	0.002	-	-
HCM Control Delay (s)	9.5	-	-	23.7	0	27.2	8.1	-	-
HCM Lane LOS	A	-	-	C	A	D	A	-	-
HCM 95th %tile Q(veh)	1	-	-	0	-	0.3	0	-	-

Intersection												
Int Delay, s/veh	3.5											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↰	↱		↰		↰	↱		↰	↱	
Traffic Vol, veh/h	6	2	296	1	0	0	296	369	20	1	463	65
Future Vol, veh/h	6	2	296	1	0	0	296	369	20	1	463	65
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	-	0	-	-	0	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	73	73	73	73	73	73	73	73	73	73	73	73
Heavy Vehicles, %	4	4	4	5	5	5	4	4	4	5	5	5
Mvmt Flow	8	3	405	1	0	0	405	505	27	1	634	89

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	2010	2023	-	2011	2054	519	723	0	0	532	0	0
Stage 1	681	681	-	1329	1329	-	-	-	-	-	-	-
Stage 2	1329	1342	-	682	725	-	-	-	-	-	-	-
Critical Hdwy	7.14	6.54	-	7.15	6.55	6.25	4.14	-	-	4.15	-	-
Critical Hdwy Stg 1	6.14	5.54	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.14	5.54	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.536	4.036	-	3.545	4.045	3.345	2.236	-	-	2.245	-	-
Pot Cap-1 Maneuver	43	57	0	43	54	551	870	-	-	1020	-	-
Stage 1	437	447	0	188	221	-	-	-	-	-	-	-
Stage 2	189	219	0	435	426	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	27	30	-	27	29	551	870	-	-	1020	-	-
Mov Cap-2 Maneuver	74	92	-	-	18	-	-	-	-	-	-	-
Stage 1	233	447	-	100	118	-	-	-	-	-	-	-
Stage 2	101	117	-	432	426	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	58.6		5.5	0
HCM LOS	F	-		







Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2WBLn1	SBL	SBT	SBR
Capacity (veh/h)	870	-	-	78	-	1020	-	-
HCM Lane V/C Ratio	0.466	-	-	0.14	-	0.001	-	-
HCM Control Delay (s)	12.7	-	-	58.6	0	8.5	-	-
HCM Lane LOS	B	-	-	F	A	A	-	-
HCM 95th %tile Q(veh)	2.5	-	-	0.5	-	0	-	-

Intersection												
Int Delay, s/veh	2.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↰	↱		↰	↱	↰	↱		↰	↱	
Traffic Vol, veh/h	1	1	351	13	1	1	226	342	7	2	425	29
Future Vol, veh/h	1	1	351	13	1	1	226	342	7	2	425	29
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	-	0	-	-	0	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	85	85	85	85	85	85	85	85	85	85	85	85
Heavy Vehicles, %	3	3	3	2	2	2	2	2	2	6	6	6
Mvmt Flow	1	1	413	15	1	1	266	402	8	2	500	34

Major/Minor	Minor2		Minor1		Major1			Major2				
Conflicting Flow All	1460	1463	-	1460	1476	406	534	0	0	410	0	0
Stage 1	521	521	-	938	938	-	-	-	-	-	-	-
Stage 2	939	942	-	522	538	-	-	-	-	-	-	-
Critical Hdwy	7.13	6.53	-	7.12	6.52	6.22	4.12	-	-	4.16	-	-
Critical Hdwy Stg 1	6.13	5.53	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.13	5.53	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.527	4.027	-	3.518	4.018	3.318	2.218	-	-	2.254	-	-
Pot Cap-1 Maneuver	106	128	0	107	126	645	1034	-	-	1128	-	-
Stage 1	537	530	0	317	343	-	-	-	-	-	-	-
Stage 2	316	340	0	538	522	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	84	95	-	85	93	645	1034	-	-	1128	-	-
Mov Cap-2 Maneuver	168	191	-	153	159	-	-	-	-	-	-	-
Stage 1	399	529	-	236	255	-	-	-	-	-	-	-
Stage 2	233	253	-	536	521	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	25.4		29.9		3.8		0	
HCM LOS	D		D					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1034	-	-	179	-	162	1128	-	-
HCM Lane V/C Ratio	0.257	-	-	0.013	-	0.109	0.002	-	-
HCM Control Delay (s)	9.7	-	-	25.4	0	29.9	8.2	-	-
HCM Lane LOS	A	-	-	D	A	D	A	-	-
HCM 95th %tile Q(veh)	1	-	-	0	-	0.4	0	-	-

Intersection												
Int Delay, s/veh	3.4											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	0	0	365	0	0	1	315	372	20	1	471	65
Future Vol, veh/h	0	0	365	0	0	1	315	372	20	1	471	65
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	0	450	-	-	200	-	-
Veh in Median Storage, #	-	2	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	73	73	73	73	73	73	73	73	73	73	73	73
Heavy Vehicles, %	4	4	4	5	5	5	4	4	4	5	5	5
Mvmt Flow	0	0	500	0	0	1	432	510	27	1	645	89

Major/Minor	Minor2			Minor1			Major1			Major2		
Conflicting Flow All	-	-	-	-	-	-	524	734	0	0	537	0
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy	-	-	-	-	-	-	6.25	4.14	-	-	4.15	-
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-	-	-	-	-
Follow-up Hdwy	-	-	-	-	-	-	3.345	2.236	-	-	2.245	-
Pot Cap-1 Maneuver	0	0	0	0	0	0	547	862	-	-	1016	-
Stage 1	0	0	0	0	0	0	-	-	-	-	-	-
Stage 2	0	0	0	0	0	0	-	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	-	-	-	-	547	862	-	-	1016	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-

Approach	EB			WB			NB			SB		
HCM Control Delay, s	0			11.6			5.9			0		
HCM LOS	A			B								

















Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	862	-	-	-	547	1016	-
HCM Lane V/C Ratio	0.501	-	-	-	0.003	0.001	-
HCM Control Delay (s)	13.3	-	-	0	11.6	8.5	-
HCM Lane LOS	B	-	-	A	B	A	-
HCM 95th %tile Q(veh)	2.9	-	-	-	0	0	-

Timings

2025 Total AM - #6 Signalized

6: Woodmoor Drive & Monument Hill Road

10/20/2022

									
Lane Group	EBL	EBT	EBR	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations									
Traffic Volume (vph)	6	2	357	1	0	315	372	1	471
Future Volume (vph)	6	2	357	1	0	315	372	1	471
Turn Type	Perm	NA	Perm	Perm	NA	pm+pt	NA	pm+pt	NA
Protected Phases		4			8	5	2	1	6
Permitted Phases	4		4	8		2		6	
Detector Phase	4	4	4	8	8	5	2	1	6
Switch Phase									
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	9.5	22.5	9.5	22.5
Total Split (s)	23.0	23.0	23.0	23.0	23.0	24.1	57.5	9.5	42.9
Total Split (%)	25.6%	25.6%	25.6%	25.6%	25.6%	26.8%	63.9%	10.6%	47.7%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)		4.5	4.5		4.5	4.5	4.5	4.5	4.5
Lead/Lag						Lead	Lag	Lead	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	None	C-Max
Act Effect Green (s)		12.1	12.1		12.1	68.9	67.0	48.9	43.5
Actuated g/C Ratio		0.13	0.13		0.13	0.77	0.74	0.54	0.48
v/c Ratio		0.05	0.86		0.01	0.82	0.40	0.00	0.85
Control Delay		30.2	22.7		29.0	31.7	6.8	6.0	33.8
Queue Delay		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Delay		30.2	22.7		29.0	31.7	6.8	6.0	33.8
LOS		C	C		C	C	A	A	C
Approach Delay		22.8			29.0		17.9		33.8
Approach LOS		C			C		B		C

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.86

Intersection Signal Delay: 24.3

Intersection LOS: C

Intersection Capacity Utilization 66.3%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 6: Woodmoor Drive & Monument Hill Road






















HCM 6th Signalized Intersection Summary

6: Woodmoor Drive & Monument Hill Road

2025 Total AM - #6 Signalized

10/20/2022







												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	6	2	357	1	0	0	315	372	20	1	471	65
Future Volume (veh/h)	6	2	357	1	0	0	315	372	20	1	471	65
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1841	1841	1841	1826	1826	1826	1841	1841	1841	1826	1826	1826
Adj Flow Rate, veh/h	8	3	0	1	0	0	432	510	27	1	645	89
Peak Hour Factor	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73
Percent Heavy Veh, %	4	4	4	5	5	5	4	4	4	5	5	5
Cap, veh/h	85	6		102	0	0	638	1445	77	721	1183	163
Arrive On Green	0.01	0.01	0.00	0.01	0.00	0.00	0.08	0.83	0.83	0.00	0.75	0.75
Sat Flow, veh/h	1094	410	1560	1560	0	0	1753	1732	92	1739	1570	217
Grp Volume(v), veh/h	11	0	0	1	0	0	432	0	537	1	0	734
Grp Sat Flow(s),veh/h/ln	1505	0	1560	1560	0	0	1753	0	1824	1739	0	1787
Q Serve(g_s), s	0.6	0.0	0.0	0.0	0.0	0.0	4.2	0.0	6.2	0.0	0.0	15.5
Cycle Q Clear(g_c), s	0.6	0.0	0.0	0.1	0.0	0.0	4.2	0.0	6.2	0.0	0.0	15.5
Prop In Lane	0.73		1.00	1.00		0.00	1.00		0.05	1.00		0.12
Lane Grp Cap(c), veh/h	91	0		102	0	0	638	0	1522	721	0	1347
V/C Ratio(X)	0.12	0.00		0.01	0.00	0.00	0.68	0.00	0.35	0.00	0.00	0.54
Avail Cap(c_a), veh/h	376	0		366	0	0	876	0	1522	815	0	1347
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	0.00	1.00	0.00	0.00	0.78	0.00	0.78	1.00	0.00	1.00
Uniform Delay (d), s/veh	44.0	0.0	0.0	43.7	0.0	0.0	5.5	0.0	1.8	2.7	0.0	4.6
Incr Delay (d2), s/veh	0.6	0.0	0.0	0.0	0.0	0.0	1.0	0.0	0.5	0.0	0.0	1.6
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	0.0	0.0	0.0	0.0	0.0	2.3	0.0	1.2	0.0	0.0	4.7
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	44.6	0.0	0.0	43.8	0.0	0.0	6.5	0.0	2.3	2.7	0.0	6.2
LnGrp LOS	D	A		D	A	A	A	A	A	A	A	A
Approach Vol, veh/h	11			1			969			735		
Approach Delay, s/veh	44.6			43.8			4.2			6.2		
Approach LOS	D			D			A			A		
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	4.6	79.6		5.8	11.9	72.3		5.8				
Change Period (Y+Rc), s	4.5	4.5		4.5	4.5	4.5		4.5				
Max Green Setting (Gmax), s	5.0	53.0		18.5	19.6	38.4		18.5				
Max Q Clear Time (g_c+I1), s	2.0	8.2		2.6	6.2	17.5		2.1				
Green Ext Time (p_c), s	0.0	4.1		0.0	1.2	5.5		0.0				
Intersection Summary												
HCM 6th Ctrl Delay	5.3											
HCM 6th LOS	A											

Intersection						
Intersection Delay, s/veh	10.1					
Intersection LOS	B					
Approach	EB	WB	NB		SB	
Entry Lanes	1	1	2		2	
Conflicting Circle Lanes	1	1	1		1	
Adj Approach Flow, veh/h	11	1	969		735	
Demand Flow Rate, veh/h	11	1	1007		771	
Vehicles Circulating, veh/h	679	987	12		450	
Vehicles Exiting, veh/h	542	32	678		538	
Ped Vol Crossing Leg, #/h	0	0	0		0	
Ped Cap Adj	1.000	1.000	1.000		1.000	
Approach Delay, s/veh	5.4	7.2	6.0		15.7	
Approach LOS	A	A	A		C	
Lane	Left	Left	Left	Right	Left	Right
Designated Moves	LT	LTR	L	TR	LT	R
Assumed Moves	LT	LTR	L	TR	LT	R
RT Channelized						
Lane Util	1.000	1.000	0.446	0.554	0.879	0.121
Follow-Up Headway, s	2.609	2.609	2.535	2.535	2.535	2.535
Critical Headway, s	4.976	4.976	4.544	4.544	4.544	4.544
Entry Flow, veh/h	11	1	449	558	678	93
Cap Entry Lane, veh/h	690	504	1405	1405	943	943
Entry HV Adj Factor	0.990	1.000	0.962	0.962	0.952	0.957
Flow Entry, veh/h	11	1	432	537	646	89
Cap Entry, veh/h	683	504	1352	1351	898	902
V/C Ratio	0.016	0.002	0.320	0.397	0.719	0.099
Control Delay, s/veh	5.4	7.2	5.5	6.4	17.1	4.9
LOS	A	A	A	A	C	A
95th %tile Queue, veh	0	0	1	2	6	0

HCM 6th TWSC
6: Woodmoor Drive & Monument Hill Road

2025 Total PM - #6 Restricted Movements

10/21/2022

Intersection												
Int Delay, s/veh	2.8											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	0	0	391	0	0	15	291	351	7	2	430	29
Future Vol, veh/h	0	0	391	0	0	15	291	351	7	2	430	29
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	0	450	-	-	200	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	85	85	85	85	85	85	85	85	85	85	85	85
Heavy Vehicles, %	3	3	3	2	2	2	2	2	2	6	6	6
Mvmt Flow	0	0	460	0	0	18	342	413	8	2	506	34

















Major/Minor	Minor2		Minor1		Major1		Major2	
Conflicting Flow All	-	-	-	-	-	417	540	0
Stage 1	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-
Critical Hdwy	-	-	-	-	-	6.22	4.12	-
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-
Follow-up Hdwy	-	-	-	-	-	3.318	2.218	-
Pot Cap-1 Maneuver	0	0	0	0	0	636	1028	-
Stage 1	0	0	0	0	0	-	-	-
Stage 2	0	0	0	0	0	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	-	-	-	636	1028	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0	10.8	4.6	0
HCM LOS	A	B		

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	1028	-	-	-	636	1117	-
HCM Lane V/C Ratio	0.333	-	-	-	0.028	0.002	-
HCM Control Delay (s)	10.2	-	-	0	10.8	8.2	-
HCM Lane LOS	B	-	-	A	B	A	-
HCM 95th %tile Q(veh)	1.5	-	-	-	0.1	0	-

Timings 6: Woodmoor Drive & Monument Hill Road

2025 Total PM - # 6 Signalized
10/20/2022

									
Lane Group	EBL	EBT	EBR	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations									
Traffic Volume (vph)	1	1	389	13	1	291	351	2	430
Future Volume (vph)	1	1	389	13	1	291	351	2	430
Turn Type	Perm	NA	Perm	Perm	NA	pm+pt	NA	pm+pt	NA
Protected Phases		4			8	5	2	1	6
Permitted Phases	4		4	8		2		6	
Detector Phase	4	4	4	8	8	5	2	1	6
Switch Phase									
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	9.5	22.5	9.5	22.5
Total Split (s)	25.0	25.0	25.0	25.0	25.0	23.0	55.4	9.6	42.0
Total Split (%)	27.8%	27.8%	27.8%	27.8%	27.8%	25.6%	61.6%	10.7%	46.7%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)		4.5	4.5		4.5	4.5	4.5	4.5	4.5
Lead/Lag						Lead	Lag	Lead	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	None	C-Max
Act Effect Green (s)		10.0	10.0		10.0	71.0	69.1	61.0	55.6
Actuated g/C Ratio		0.11	0.11		0.11	0.79	0.77	0.68	0.62
v/c Ratio		0.01	0.79		0.10	0.53	0.30	0.00	0.49
Control Delay		30.5	14.0		32.0	6.4	5.5	5.0	14.0
Queue Delay		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Delay		30.5	14.0		32.0	6.4	5.5	5.0	14.0
LOS		C	B		C	A	A	A	B
Approach Delay		14.0			32.0		5.9		14.0
Approach LOS		B			C		A		B

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.79

Intersection Signal Delay: 10.7


Intersection LOS: B

Intersection Capacity Utilization 63.9%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 6: Woodmoor Drive & Monument Hill Road






















HCM 6th Signalized Intersection Summary

6: Woodmoor Drive & Monument Hill Road

2025 Total PM - # 6 Signalized

10/20/2022

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	1	1	389	13	1	1	291	351	7	2	430	29
Future Volume (veh/h)	1	1	389	13	1	1	291	351	7	2	430	29
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1811	1811	1811
Adj Flow Rate, veh/h	1	1	0	15	1	1	342	413	8	2	506	34
Peak Hour Factor	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	6	6	6
Cap, veh/h	78	18		102	2	2	770	1511	29	797	1278	86
Arrive On Green	0.02	0.02	0.00	0.02	0.02	0.02	0.07	0.83	0.83	0.00	0.76	0.76
Sat Flow, veh/h	857	857	1572	1292	86	86	1781	1829	35	1725	1678	113
Grp Volume(v), veh/h	2	0	0	17	0	0	342	0	421	2	0	540
Grp Sat Flow(s),veh/h/ln	1713	0	1572	1464	0	0	1781	0	1864	1725	0	1791
Q Serve(g_s), s	0.0	0.0	0.0	0.9	0.0	0.0	3.2	0.0	4.6	0.0	0.0	9.3
Cycle Q Clear(g_c), s	0.1	0.0	0.0	1.0	0.0	0.0	3.2	0.0	4.6	0.0	0.0	9.3
Prop In Lane	0.50		1.00	0.88		0.06	1.00		0.02	1.00		0.06
Lane Grp Cap(c), veh/h	96	0		106	0	0	770	0	1540	797	0	1364
V/C Ratio(X)	0.02	0.00		0.16	0.00	0.00	0.44	0.00	0.27	0.00	0.00	0.40
Avail Cap(c_a), veh/h	426	0		405	0	0	1016	0	1540	890	0	1364
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	0.00	1.00	0.00	0.00	0.81	0.00	0.81	1.00	0.00	1.00
Uniform Delay (d), s/veh	43.2	0.0	0.0	43.6	0.0	0.0	2.4	0.0	1.8	2.5	0.0	3.7
Incr Delay (d2), s/veh	0.1	0.0	0.0	0.7	0.0	0.0	0.3	0.0	0.4	0.0	0.0	0.9
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.0	0.0	0.0	0.4	0.0	0.0	0.4	0.0	0.9	0.0	0.0	2.7
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	43.3	0.0	0.0	44.3	0.0	0.0	2.7	0.0	2.1	2.5	0.0	4.5
LnGrp LOS	D	A		D	A	A	A	A	A	A	A	A
Approach Vol, veh/h	2			17			763			542		
Approach Delay, s/veh	43.3			44.3			2.4			4.5		
Approach LOS	D			D			A			A		
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	4.7	78.9		6.4	10.6	73.1		6.4				
Change Period (Y+Rc), s	4.5	4.5		4.5	4.5	4.5		4.5				
Max Green Setting (Gmax), s	5.1	50.9		20.5	18.5	37.5		20.5				
Max Q Clear Time (g_c+I1), s	2.0	6.6		2.1	5.2	11.3		3.0				
Green Ext Time (p_c), s	0.0	3.0		0.0	0.9	3.8		0.0				
Intersection Summary												
HCM 6th Ctrl Delay	3.9											
HCM 6th LOS	A											

Intersection						
Intersection Delay, s/veh	7.1					
Intersection LOS	A					
Approach	EB	WB	NB	SB		
Entry Lanes	1	1	2	2		
Conflicting Circle Lanes	1	1	1	1		
Adj Approach Flow, veh/h	2	17	763	542		
Demand Flow Rate, veh/h	2	17	778	574		
Vehicles Circulating, veh/h	553	771	4	365		
Vehicles Exiting, veh/h	386	11	551	423		
Ped Vol Crossing Leg, #/h	0	0	0	0		
Ped Cap Adj	1.000	1.000	1.000	1.000		
Approach Delay, s/veh	4.7	6.0	5.0	10.1		
Approach LOS	A	A	A	B		
Lane	Left	Left	Left	Right	Left	Right
Designated Moves	LT	LTR	L	TR	LT	R
Assumed Moves	LT	LTR	L	TR	LT	R
RT Channelized						
Lane Util	1.000	1.000	0.449	0.551	0.937	0.063
Follow-Up Headway, s	2.609	2.609	2.535	2.535	2.535	2.535
Critical Headway, s	4.976	4.976	4.544	4.544	4.544	4.544
Entry Flow, veh/h	2	17	349	429	538	36
Cap Entry Lane, veh/h	785	629	1415	1415	1019	1019
Entry HV Adj Factor	0.985	0.999	0.980	0.981	0.944	0.944
Flow Entry, veh/h	2	17	342	421	508	34
Cap Entry, veh/h	774	628	1387	1388	961	962
V/C Ratio	0.003	0.027	0.247	0.303	0.528	0.035
Control Delay, s/veh	4.7	6.0	4.7	5.2	10.5	4.1
LOS	A	A	A	A	B	A
95th %tile Queue, veh	0	0	1	1	3	0

Intersection												
Int Delay, s/veh	5.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↰	↱		↰	↱	↰	↱		↰	↱	
Traffic Vol, veh/h	8	3	361	1	0	0	361	448	24	1	561	79
Future Vol, veh/h	8	3	361	1	0	0	361	448	24	1	561	79
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	-	0	-	-	0	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	73	73	73	73	73	73	73	73	73	73	73	73
Heavy Vehicles, %	4	4	4	5	5	5	4	4	4	5	5	5
Mvmt Flow	11	4	495	1	0	0	495	614	33	1	768	108







Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	2445	2461	-	2447	2499	631	876	0	0	647	0	0
Stage 1	824	824	-	1621	1621	-	-	-	-	-	-	-
Stage 2	1621	1637	-	826	878	-	-	-	-	-	-	-
Critical Hdwy	7.14	6.54	-	7.15	6.55	6.25	4.14	-	-	4.15	-	-
Critical Hdwy Stg 1	6.14	5.54	-	6.15	5.55	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.14	5.54	-	6.15	5.55	-	-	-	-	-	-	-
Follow-up Hdwy	3.536	4.036	-	3.545	4.045	3.345	2.236	-	-	2.245	-	-
Pot Cap-1 Maneuver	21	30	0	21	28	476	762	-	-	924	-	-
Stage 1	364	385	0	127	159	-	-	-	-	-	-	-
Stage 2	128	157	0	362	362	-	-	-	-	-	-	-
Platoon blocked, %								-	-	-	-	-
Mov Cap-1 Maneuver	~ 10	11	-	9	10	476	762	-	-	924	-	-
Mov Cap-2 Maneuver	33	45	-	50	71	-	-	-	-	-	-	-
Stage 1	127	385	-	44	56	-	-	-	-	-	-	-
Stage 2	45	55	-	358	362	-	-	-	-	-	-	-

Approach	EB		WB		NB		SB	
HCM Control Delay, s	163.8		79		7.8		0	
HCM LOS	F		F					

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	SBL	SBT	SBR
Capacity (veh/h)	762	-	-	36	-	50	924	-	-
HCM Lane V/C Ratio	0.649	-	-	0.419	-	0.027	0.001	-	-
HCM Control Delay (s)	18	-	-	163.8	0	79	8.9	-	-
HCM Lane LOS	C	-	-	F	A	F	A	-	-
HCM 95th %tile Q(veh)	4.8	-	-	1.4	-	0.1	0	-	-

Notes												
-: Volume exceeds capacity \$: Delay exceeds 300s +: Computation Not Defined *: All major volume in platoon												

Intersection												
Int Delay, s/veh	3.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕	↗		↕		↗	↕		↗	↕	
Traffic Vol, veh/h	1	1	429	16	1	1	275	413	9	3	516	35
Future Vol, veh/h	1	1	429	16	1	1	275	413	9	3	516	35
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	-	0	-	-	0	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	85	85	85	85	85	85	85	85	85	85	85	85
Heavy Vehicles, %	3	3	3	2	2	2	2	2	2	6	6	6
Mvmt Flow	1	1	505	19	1	1	324	486	11	4	607	41
Major/Minor	Minor2		Minor1		Major1		Major2					
Conflicting Flow All	1777	1781	-	1776	1796	492	648	0	0	497	0	0
Stage 1	636	636	-	1140	1140	-	-	-	-	-	-	-
Stage 2	1141	1145	-	636	656	-	-	-	-	-	-	-
Critical Hdwy	7.13	6.53	-	7.12	6.52	6.22	4.12	-	-	4.16	-	-
Critical Hdwy Stg 1	6.13	5.53	-	6.12	5.52	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.13	5.53	-	6.12	5.52	-	-	-	-	-	-	-
Follow-up Hdwy	3.527	4.027	-	3.518	4.018	3.318	2.218	-	-	2.254	-	-
Pot Cap-1 Maneuver	64	82	0	64	80	577	938	-	-	1047	-	-
Stage 1	464	470	0	244	276	-	-	-	-	-	-	-
Stage 2	243	273	0	466	462	-	-	-	-	-	-	-
Platoon blocked, %								-	-		-	-
Mov Cap-1 Maneuver	46	53	-	46	52	577	938	-	-	1047	-	-
Mov Cap-2 Maneuver	111	134	-	89	94	-	-	-	-	-	-	-
Stage 1	304	468	-	160	181	-	-	-	-	-	-	-
Stage 2	158	179	-	463	460	-	-	-	-	-	-	-
Approach	EB		WB		NB		SB					
HCM Control Delay, s	35.3		54.1		4.3		0					
HCM LOS	E		F									
Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1	EBLn2	WBLn1	SBL	SBT	SBR			
Capacity (veh/h)	938	-	-	121	-	94	1047	-	-			
HCM Lane V/C Ratio	0.345	-	-	0.019	-	0.225	0.003	-	-			
HCM Control Delay (s)	10.8	-	-	35.3	0	54.1	8.4	-	-			
HCM Lane LOS	B	-	-	E	A	F	A	-	-			
HCM 95th %tile Q(veh)	1.5	-	-	0.1	-	0.8	0	-	-			

Intersection												
Int Delay, s/veh	5.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	0	0	440	0	0	5	380	455	25	5	570	80
Future Vol, veh/h	0	0	440	0	0	5	380	455	25	5	570	80
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	0	450	-	-	200	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	73	73	73	73	73	73	73	73	73	73	73	73
Heavy Vehicles, %	4	4	4	5	5	5	4	4	4	5	5	5
Mvmt Flow	0	0	603	0	0	7	521	623	34	7	781	110

Major/Minor	Minor2		Minor1		Major1		Major2	
Conflicting Flow All	-	-	-	-	-	640	891	0
Stage 1	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-
Critical Hdwy	-	-	-	-	-	6.25	4.14	-
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-
Follow-up Hdwy	-	-	-	-	-	3.345	2.236	-
Pot Cap-1 Maneuver	0	0	0	0	0	470	752	-
Stage 1	0	0	0	0	0	-	-	-
Stage 2	0	0	0	0	0	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	-	-	-	470	752	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-









Approach	EB	WB	NB	SB
HCM Control Delay, s	0	12.8	8.8	0.1
HCM LOS	A	B		

Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	752	-	-	-	470	916	-
HCM Lane V/C Ratio	0.692	-	-	-	0.015	0.007	-
HCM Control Delay (s)	19.8	-	-	0	12.8	9	-
HCM Lane LOS	C	-	-	A	B	A	-
HCM 95th %tile Q(veh)	5.6	-	-	-	0	0	-

Timings 6: Woodmoor Drive & Monument Hill Road

2045 Total AM - #1,2,6 Signalized

10/20/2022

									
Lane Group	EBL	EBT	EBR	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations									
Traffic Volume (vph)	10	5	425	5	0	380	455	5	570
Future Volume (vph)	10	5	425	5	0	380	455	5	570
Turn Type	Perm	NA	Perm	Perm	NA	pm+pt	NA	pm+pt	NA
Protected Phases		4			8	5	2	1	6
Permitted Phases	4		4	8		2		6	
Detector Phase	4	4	4	8	8	5	2	1	6
Switch Phase									
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	9.5	22.5	9.5	22.5
Total Split (s)	22.5	22.5	22.5	22.5	22.5	23.0	58.0	9.5	44.5
Total Split (%)	25.0%	25.0%	25.0%	25.0%	25.0%	25.6%	64.4%	10.6%	49.4%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)		4.5	4.5		4.5	4.5	4.5	4.5	4.5
Lead/Lag						Lead	Lag	Lead	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	None	C-Max
Act Effect Green (s)		17.7	17.7		17.7	63.3	61.4	45.1	40.0
Actuated g/C Ratio		0.20	0.20		0.20	0.70	0.68	0.50	0.44
v/c Ratio		0.07	0.98		0.03	1.18	0.53	0.02	1.12
Control Delay		30.0	46.8		29.4	127.7	9.8	6.8	95.6
Queue Delay		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Delay		30.0	46.8		29.4	127.7	9.8	6.8	95.6
LOS		C	D		C	F	A	A	F
Approach Delay		46.2			29.4		61.9		94.9
Approach LOS		D			C		E		F

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 140

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.18

Intersection Signal Delay: 69.3

Intersection LOS: E

Intersection Capacity Utilization 76.6%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 6: Woodmoor Drive & Monument Hill Road






















HCM 6th Signalized Intersection Summary







6: Woodmoor Drive & Monument Hill Road

2045 Total AM - #1,2,6 Signalized

10/20/2022

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	10	5	425	5	0	0	380	455	25	5	570	80
Future Volume (veh/h)	10	5	425	5	0	0	380	455	25	5	570	80
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1841	1841	1841	1826	1826	1826	1841	1841	1841	1826	1826	1826
Adj Flow Rate, veh/h	14	7	0	7	0	0	521	623	34	7	781	110
Peak Hour Factor	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73
Percent Heavy Veh, %	4	4	4	5	5	5	4	4	4	5	5	5
Cap, veh/h	96	14		123	0	0	561	1406	77	597	1036	146
Arrive On Green	0.03	0.03	0.00	0.03	0.00	0.00	0.16	0.81	0.81	0.01	0.66	0.66
Sat Flow, veh/h	1036	518	1560	1544	0	0	1753	1729	94	1739	1566	221
Grp Volume(v), veh/h	21	0	0	7	0	0	521	0	657	7	0	891
Grp Sat Flow(s),veh/h/ln	1555	0	1560	1544	0	0	1753	0	1824	1739	0	1786
Q Serve(g_s), s	0.8	0.0	0.0	0.0	0.0	0.0	11.6	0.0	9.5	0.1	0.0	30.3
Cycle Q Clear(g_c), s	1.2	0.0	0.0	0.4	0.0	0.0	11.6	0.0	9.5	0.1	0.0	30.3
Prop In Lane	0.67		1.00	1.00		0.00	1.00		0.05	1.00		0.12
Lane Grp Cap(c), veh/h	110	0		123	0	0	561	0	1483	597	0	1181
V/C Ratio(X)	0.19	0.00		0.06	0.00	0.00	0.93	0.00	0.44	0.01	0.00	0.75
Avail Cap(c_a), veh/h	371	0		360	0	0	639	0	1483	678	0	1181
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	0.00	1.00	0.00	0.00	0.65	0.00	0.65	1.00	0.00	1.00
Uniform Delay (d), s/veh	43.1	0.0	0.0	42.7	0.0	0.0	20.4	0.0	2.5	4.9	0.0	10.3
Incr Delay (d2), s/veh	0.8	0.0	0.0	0.2	0.0	0.0	13.6	0.0	0.6	0.0	0.0	4.5
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.5	0.0	0.0	0.2	0.0	0.0	12.6	0.0	2.1	0.0	0.0	11.4
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	43.9	0.0	0.0	42.9	0.0	0.0	34.0	0.0	3.1	4.9	0.0	14.8
LnGrp LOS	D	A		D	A	A	C	A	A	A	A	B
Approach Vol, veh/h	21			7			1178			898		
Approach Delay, s/veh	43.9			42.9			16.8			14.7		
Approach LOS	D			D			B			B		
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	5.3	77.7		7.0	18.9	64.0		7.0				
Change Period (Y+Rc), s	4.5	4.5		4.5	4.5	4.5		4.5				
Max Green Setting (Gmax), s	5.0	53.5		18.0	18.5	40.0		18.0				
Max Q Clear Time (g_c+I1), s	2.1	11.5		3.2	13.6	32.3		2.4				
Green Ext Time (p_c), s	0.0	5.4		0.0	0.9	3.9		0.0				
Intersection Summary												
HCM 6th Ctrl Delay	16.2											
HCM 6th LOS	B											

Intersection						
Intersection Delay, s/veh	21.1					
Intersection LOS	C					
Approach	EB	WB	NB		SB	
Entry Lanes	1	1	2		2	
Conflicting Circle Lanes	1	1	1		1	
Adj Approach Flow, veh/h	21	7	1178		898	
Demand Flow Rate, veh/h	22	7	1225		943	
Vehicles Circulating, veh/h	834	1205	29		549	
Vehicles Exiting, veh/h	657	49	827		663	
Ped Vol Crossing Leg, #/h	0	0	0		0	
Ped Cap Adj	1.000	1.000	1.000		1.000	
Approach Delay, s/veh	6.9	9.2	7.2		39.8	
Approach LOS	A	A	A		E	
Lane	Left	Left	Left	Right	Left	Right
Designated Moves	LT	LTR	L	TR	LT	R
Assumed Moves	LT	LTR	L	TR	LT	R
RT Channelized						
Lane Util	1.000	1.000	0.442	0.558	0.877	0.123
Follow-Up Headway, s	2.609	2.609	2.535	2.535	2.535	2.535
Critical Headway, s	4.976	4.976	4.544	4.544	4.544	4.544
Entry Flow, veh/h	22	7	542	683	827	116
Cap Entry Lane, veh/h	589	404	1383	1383	862	862
Entry HV Adj Factor	0.942	1.000	0.961	0.962	0.953	0.948
Flow Entry, veh/h	21	7	521	657	788	110
Cap Entry, veh/h	555	404	1330	1331	821	817
V/C Ratio	0.037	0.017	0.392	0.494	0.960	0.135
Control Delay, s/veh	6.9	9.2	6.4	7.8	44.6	5.8
LOS	A	A	A	A	E	A
95th %tile Queue, veh	0	0	2	3	15	0

Intersection												
Int Delay, s/veh	3.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	0	0	480	0	0	25	340	425	10	5	525	35
Future Vol, veh/h	0	0	480	0	0	25	340	425	10	5	525	35
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	Free	-	-	None	-	-	None	-	-	None
Storage Length	-	-	0	-	-	0	450	-	-	200	-	-
Veh in Median Storage, #	-	1	-	-	1	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	85	85	85	85	85	85	85	85	85	85	85	85
Heavy Vehicles, %	3	3	3	2	2	2	2	2	2	6	6	6
Mvmt Flow	0	0	565	0	0	29	400	500	12	6	618	41

Major/Minor	Minor2		Minor1		Major1		Major2	
Conflicting Flow All	-	-	-	-	-	506	659	0
Stage 1	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-
Critical Hdwy	-	-	-	-	-	6.22	4.12	-
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-
Follow-up Hdwy	-	-	-	-	-	3.318	2.218	-
Pot Cap-1 Maneuver	0	0	0	0	0	566	929	-
Stage 1	0	0	0	0	0	-	-	-
Stage 2	0	0	0	0	0	-	-	-
Platoon blocked, %	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	-	-	-	-	-	566	929	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-

Approach	EB	WB	NB	SB
HCM Control Delay, s	0	11.7	5.2	0.1
HCM LOS	A	B		


Minor Lane/Major Mvmt	NBL	NBT	NBR	EBLn1WBLn1	SBL	SBT	SBR
Capacity (veh/h)	929	-	-	-	566	1033	-
HCM Lane V/C Ratio	0.431	-	-	-	0.052	0.006	-
HCM Control Delay (s)	11.8	-	-	0	11.7	8.5	-
HCM Lane LOS	B	-	-	A	B	A	-
HCM 95th %tile Q(veh)	2.2	-	-	-	0.2	0	-

Timings

6: Woodmoor Drive & Monument Hill Road

2045 Total PM - #1,2,6 Signalized

10/20/2022

									
Lane Group	EBL	EBT	EBR	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations		↰	↱		↰	↱	↰	↱	↰
Traffic Volume (vph)	5	5	470	20	5	340	425	5	525
Future Volume (vph)	5	5	470	20	5	340	425	5	525
Turn Type	Perm	NA	Perm	Perm	NA	pm+pt	NA	pm+pt	NA
Protected Phases		4			8	5	2	1	6
Permitted Phases	4		4	8		2		6	
Detector Phase	4	4	4	8	8	5	2	1	6
Switch Phase									
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	22.5	22.5	22.5	22.5	22.5	9.5	22.5	9.5	22.5
Total Split (s)	25.0	25.0	25.0	25.0	25.0	23.0	55.5	9.5	42.0
Total Split (%)	27.8%	27.8%	27.8%	27.8%	27.8%	25.6%	61.7%	10.6%	46.7%
Yellow Time (s)	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
All-Red Time (s)	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Lost Time Adjust (s)		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)		4.5	4.5		4.5	4.5	4.5	4.5	4.5
Lead/Lag						Lead	Lag	Lead	Lag
Lead-Lag Optimize?						Yes	Yes	Yes	Yes
Recall Mode	None	None	None	None	None	None	C-Max	None	C-Max
Act Effect Green (s)		15.8	15.8		15.8	65.2	63.3	48.9	43.6
Actuated g/C Ratio		0.18	0.18		0.18	0.72	0.70	0.54	0.48
v/c Ratio		0.04	0.90		0.13	0.77	0.39	0.01	0.76
Control Delay		27.8	29.0		26.0	22.2	8.1	6.4	22.7
Queue Delay		0.0	0.0		0.0	0.0	0.0	0.0	0.0
Total Delay		27.8	29.0		26.0	22.2	8.1	6.4	22.7
LOS		C	C		C	C	A	A	C
Approach Delay		28.9			26.0		14.3		22.6
Approach LOS		C			C		B		C

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.90

Intersection Signal Delay: 20.8


Intersection LOS: C

Intersection Capacity Utilization 74.3%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 6: Woodmoor Drive & Monument Hill Road






















HCM 6th Signalized Intersection Summary

6: Woodmoor Drive & Monument Hill Road

2045 Total PM - #1,2,6 Signalized


10/20/2022

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	5	5	470	20	5	5	340	425	10	5	525	35
Future Volume (veh/h)	5	5	470	20	5	5	340	425	10	5	525	35
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach	No			No			No			No		
Adj Sat Flow, veh/h/ln	1856	1856	1856	1870	1870	1870	1870	1870	1870	1811	1811	1811
Adj Flow Rate, veh/h	6	6	0	24	6	6	400	500	12	6	618	41
Peak Hour Factor	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85
Percent Heavy Veh, %	3	3	3	2	2	2	2	2	2	6	6	6
Cap, veh/h	85	42		107	10	10	669	1461	35	720	1225	81
Arrive On Green	0.04	0.04	0.00	0.04	0.04	0.04	0.08	0.80	0.80	0.01	0.73	0.73
Sat Flow, veh/h	655	1072	1572	1033	258	258	1781	1819	44	1725	1680	111
Grp Volume(v), veh/h	12	0	0	36	0	0	400	0	512	6	0	659
Grp Sat Flow(s),veh/h/ln	1727	0	1572	1549	0	0	1781	0	1863	1725	0	1791
Q Serve(g_s), s	0.0	0.0	0.0	1.4	0.0	0.0	4.3	0.0	6.7	0.1	0.0	14.2
Cycle Q Clear(g_c), s	0.6	0.0	0.0	2.0	0.0	0.0	4.3	0.0	6.7	0.1	0.0	14.2
Prop In Lane	0.50		1.00	0.67		0.17	1.00		0.02	1.00		0.06
Lane Grp Cap(c), veh/h	127	0		127	0	0	669	0	1496	720	0	1306
V/C Ratio(X)	0.09	0.00		0.28	0.00	0.00	0.60	0.00	0.34	0.01	0.00	0.50
Avail Cap(c_a), veh/h	428	0		410	0	0	889	0	1496	803	0	1306
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	0.00	1.00	0.00	0.00	0.71	0.00	0.71	1.00	0.00	1.00
Uniform Delay (d), s/veh	41.8	0.0	0.0	42.5	0.0	0.0	4.6	0.0	2.4	3.1	0.0	5.2
Incr Delay (d2), s/veh	0.3	0.0	0.0	1.2	0.0	0.0	0.6	0.0	0.4	0.0	0.0	1.4
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	0.0	0.0	0.8	0.0	0.0	1.4	0.0	1.6	0.0	0.0	4.6
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	42.2	0.0	0.0	43.7	0.0	0.0	5.2	0.0	2.8	3.1	0.0	6.6
LnGrp LOS	D	A		D	A	A	A	A	A	A	A	A
Approach Vol, veh/h	12			36			912			665		
Approach Delay, s/veh	42.2			43.7			3.9			6.6		
Approach LOS	D			D			A			A		
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	5.2	76.8		8.0	11.9	70.1		8.0				
Change Period (Y+Rc), s	4.5	4.5		4.5	4.5	4.5		4.5				
Max Green Setting (Gmax), s	5.0	51.0		20.5	18.5	37.5		20.5				
Max Q Clear Time (g_c+I1), s	2.1	8.7		2.6	6.3	16.2		4.0				
Green Ext Time (p_c), s	0.0	3.8		0.0	1.0	4.7		0.1				
Intersection Summary												
HCM 6th Ctrl Delay	6.2											
HCM 6th LOS	A											

Intersection						
Intersection Delay, s/veh	9.6					
Intersection LOS	A					
Approach	EB	WB	NB	SB		
Entry Lanes	1	1	2	2		
Conflicting Circle Lanes	1	1	1	1		
Adj Approach Flow, veh/h	12	36	912	665		
Demand Flow Rate, veh/h	12	36	930	704		
Vehicles Circulating, veh/h	685	924	18	438		
Vehicles Exiting, veh/h	457	24	679	522		
Ped Vol Crossing Leg, #/h	0	0	0	0		
Ped Cap Adj	1.000	1.000	1.000	1.000		
Approach Delay, s/veh	5.5	7.5	5.7	15.3		
Approach LOS	A	A	A	C		
Lane	Left	Left	Left	Right	Left	Right
Designated Moves	LT	LTR	L	TR	LT	R
Assumed Moves	LT	LTR	L	TR	LT	R
RT Channelized						
Lane Util	1.000	1.000	0.439	0.561	0.939	0.061
Follow-Up Headway, s	2.609	2.609	2.535	2.535	2.535	2.535
Critical Headway, s	4.976	4.976	4.544	4.544	4.544	4.544
Entry Flow, veh/h	12	36	408	522	661	43
Cap Entry Lane, veh/h	686	538	1397	1397	953	953
Entry HV Adj Factor	0.985	0.997	0.980	0.981	0.944	0.953
Flow Entry, veh/h	12	36	400	512	624	41
Cap Entry, veh/h	676	536	1370	1370	900	909
V/C Ratio	0.017	0.067	0.292	0.374	0.693	0.045
Control Delay, s/veh	5.5	7.5	5.2	6.1	16.0	4.4
LOS	A	A	A	A	C	A
95th %tile Queue, veh	0	0	1	2	6	0

Timings
7: SH-105 & Woodmoor Drive

2022 Existing AM
09/12/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	236	413	948	526	268	511
Future Volume (vph)	236	413	948	526	268	511
Turn Type	Prot	NA	NA	Perm	Prot	pm+ov
Protected Phases	7	4	8		6	7
Permitted Phases				8		6
Detector Phase	7	4	8	8	6	7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	11.0
Total Split (s)	45.0	97.0	52.0	52.0	23.0	45.0
Total Split (%)	37.5%	80.8%	43.3%	43.3%	19.2%	37.5%
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	3.0
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	3.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	6.0
Lead/Lag	Lead		Lag	Lag		Lead
Lead-Lag Optimize?	Yes		Yes	Yes		Yes
Recall Mode	None	C-Max	C-Max	C-Max	Max	None
Act Effect Green (s)	31.4	90.5	54.1	54.1	18.0	54.4
Actuated g/C Ratio	0.26	0.75	0.45	0.45	0.15	0.45
v/c Ratio	0.30	0.18	0.67	0.57	0.59	0.79
Control Delay	35.1	4.4	29.8	4.4	52.9	34.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	35.1	4.4	29.8	4.4	52.9	34.6
LOS	D	A	C	A	D	C
Approach Delay		15.5	20.8		40.9	
Approach LOS		B	C		D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 99 (83%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.79
 Intersection Signal Delay: 25.0
 Intersection LOS: C
 Intersection Capacity Utilization 67.4%
 ICU Level of Service C
 Analysis Period (min) 15


Splits and Phases: 7: SH-105 & Woodmoor Drive



HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive













2022 Existing AM
09/12/2022



Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↰↱	↕	↕	↱	↰↱	↱	
Traffic Volume (veh/h)	236	413	948	526	268	511	
Future Volume (veh/h)	236	413	948	526	268	511	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1826	1826	1856	1856	1841	1841	
Adj Flow Rate, veh/h	262	459	1053	584	298	401	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Percent Heavy Veh, %	5	5	3	3	4	4	
Cap, veh/h	338	2616	2130	950	510	390	
Arrive On Green	0.10	0.75	0.60	0.60	0.15	0.15	
Sat Flow, veh/h	3374	3561	3618	1572	3401	1560	
Grp Volume(v), veh/h	262	459	1053	584	298	401	
Grp Sat Flow(s),veh/h/ln	1687	1735	1763	1572	1700	1560	
Q Serve(g_s), s	9.1	4.5	20.2	28.1	9.8	18.0	
Cycle Q Clear(g_c), s	9.1	4.5	20.2	28.1	9.8	18.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	338	2616	2130	950	510	390	
V/C Ratio(X)	0.78	0.18	0.49	0.61	0.58	1.03	
Avail Cap(c_a), veh/h	1096	2616	2130	950	510	390	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	52.7	4.2	13.4	15.0	47.5	45.0	
Incr Delay (d2), s/veh	3.8	0.1	0.8	3.0	4.8	52.9	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	4.0	1.5	8.0	10.4	4.5	28.5	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	56.5	4.3	14.2	17.9	52.3	97.9	
LnGrp LOS	E	A	B	B	D	F	
Approach Vol, veh/h		721	1637		699		
Approach Delay, s/veh		23.3	15.6		78.5		
Approach LOS		C	B		E		
Timer - Assigned Phs			4		6	7	8
Phs Duration (G+Y+Rc), s			97.0		23.0	18.0	79.0
Change Period (Y+Rc), s			6.5		5.0	6.0	* 6.5
Max Green Setting (Gmax), s			90.5		18.0	39.0	* 47
Max Q Clear Time (g_c+l1), s			6.5		20.0	11.1	30.1
Green Ext Time (p_c), s			3.5		0.0	0.9	9.2
Intersection Summary							
HCM 6th Ctrl Delay			31.8				
HCM 6th LOS			C				
Notes							

Timings
7: SH-105 & Woodmoor Drive


2022 Existing PM
09/12/2022

						
Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	233	530	1226	434	331	510
Future Volume (vph)	233	530	1226	434	331	510
Turn Type	Prot	NA	NA	Perm	Prot	pm+ov
Protected Phases	7	4	8		6	7
Permitted Phases				8		6
Detector Phase	7	4	8	8	6	7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	11.0
Total Split (s)	37.0	97.0	60.0	60.0	23.0	37.0
Total Split (%)	30.8%	80.8%	50.0%	50.0%	19.2%	30.8%
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	3.0
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	3.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	6.0
Lead/Lag	Lead		Lag	Lag		Lead
Lead-Lag Optimize?	Yes		Yes	Yes		Yes
Recall Mode	None	C-Max	C-Max	C-Max	Max	None
Act Effect Green (s)	26.7	90.5	58.8	58.8	18.0	49.7
Actuated g/C Ratio	0.22	0.75	0.49	0.49	0.15	0.41
v/c Ratio	0.33	0.21	0.76	0.46	0.70	0.83
Control Delay	39.4	4.5	29.4	3.4	56.5	41.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	39.4	4.5	29.4	3.4	56.5	41.5
LOS	D	A	C	A	E	D
Approach Delay		15.2	22.6		47.4	
Approach LOS		B	C		D	

Intersection Summary

Cycle Length: 120
 Actuated Cycle Length: 120
 Offset: 69 (58%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.83
 Intersection Signal Delay: 27.2
 Intersection LOS: C
 Intersection Capacity Utilization 75.1%
 ICU Level of Service D
 Analysis Period (min) 15


Splits and Phases: 7: SH-105 & Woodmoor Drive



HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2022 Existing PM
09/12/2022




Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↰↰	↱↱	↰↰	↱	↰↰	↱	
Traffic Volume (veh/h)	233	530	1226	434	331	510	
Future Volume (veh/h)	233	530	1226	434	331	510	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1856	1856	
Adj Flow Rate, veh/h	251	570	1318	467	356	387	
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	
Percent Heavy Veh, %	2	2	2	2	3	3	
Cap, veh/h	326	2680	2167	967	514	384	
Arrive On Green	0.09	0.75	0.61	0.61	0.15	0.15	
Sat Flow, veh/h	3456	3647	3647	1585	3428	1572	
Grp Volume(v), veh/h	251	570	1318	467	356	387	
Grp Sat Flow(s),veh/h/ln	1728	1777	1777	1585	1714	1572	
Q Serve(g_s), s	8.5	5.6	27.6	19.6	11.8	18.0	
Cycle Q Clear(g_c), s	8.5	5.6	27.6	19.6	11.8	18.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	326	2680	2167	967	514	384	
V/C Ratio(X)	0.77	0.21	0.61	0.48	0.69	1.01	
Avail Cap(c_a), veh/h	893	2680	2167	967	514	384	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	53.1	4.3	14.5	12.9	48.4	45.3	
Incr Delay (d2), s/veh	3.9	0.2	1.3	1.7	7.5	47.7	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	3.9	1.9	11.0	7.2	5.6	27.6	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	56.9	4.5	15.8	14.7	55.8	93.1	
LnGrp LOS	E	A	B	B	E	F	
Approach Vol, veh/h		821	1785		743		
Approach Delay, s/veh		20.5	15.5		75.2		
Approach LOS		C	B		E		
Timer - Assigned Phs				4	6	7	8
Phs Duration (G+Y+Rc), s				97.0	23.0	17.3	79.7
Change Period (Y+Rc), s				6.5	5.0	6.0	* 6.5
Max Green Setting (Gmax), s				90.5	18.0	31.0	* 55
Max Q Clear Time (g_c+l1), s				7.6	20.0	10.5	29.6
Green Ext Time (p_c), s				4.5	0.0	0.8	13.6
Intersection Summary							
HCM 6th Ctrl Delay			30.0				
HCM 6th LOS			C				
Notes							

Timings
7: SH-105 & Woodmoor Drive

2025 Background AM

09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	→→	←←	→	←←	→→
Traffic Volume (vph)	247	434	996	547	289	533
Future Volume (vph)	247	434	996	547	289	533
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	23.0	84.0	61.0	61.0	26.0	
Total Split (%)	20.9%	76.4%	55.5%	55.5%	23.6%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	14.6	77.5	57.9	57.9	21.0	41.6
Actuated g/C Ratio	0.13	0.70	0.53	0.53	0.19	0.38
v/c Ratio	0.62	0.20	0.60	0.55	0.50	0.54
Control Delay	51.0	5.8	20.2	3.3	42.9	23.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.0	5.8	20.2	3.3	42.9	23.4
LOS	D	A	C	A	D	C
Approach Delay		22.2	14.2		30.3	
Approach LOS		C	B		C	

Intersection Summary

Cycle Length: 110
 Actuated Cycle Length: 110
 Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.62
 Intersection Signal Delay: 20.3
 Intersection LOS: C
 Intersection Capacity Utilization 56.6%
 ICU Level of Service B
 Analysis Period (min) 15

Splits and Phases: 7: SH-105 & Woodmoor Drive




HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2025 Background AM

09/13/2022




Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↰↰	↱↱	↰↰	↱	↰↰	↱↱
Traffic Volume (veh/h)	247	434	996	547	289	533
Future Volume (veh/h)	247	434	996	547	289	533
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No	No		No	
Adj Sat Flow, veh/h/ln	1826	1826	1856	1856	1841	1841
Adj Flow Rate, veh/h	274	482	1107	608	321	592
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Percent Heavy Veh, %	5	5	3	3	4	4
Cap, veh/h	344	2444	1932	862	649	804
Arrive On Green	0.10	0.70	0.55	0.55	0.19	0.19
Sat Flow, veh/h	3374	3561	3618	1572	3401	2745
Grp Volume(v), veh/h	274	482	1107	608	321	592
Grp Sat Flow(s),veh/h/ln	1687	1735	1763	1572	1700	1373
Q Serve(g_s), s	8.7	5.2	22.8	31.3	9.3	21.0
Cycle Q Clear(g_c), s	8.7	5.2	22.8	31.3	9.3	21.0
Prop In Lane	1.00			1.00	1.00	1.00
Lane Grp Cap(c), veh/h	344	2444	1932	862	649	804
V/C Ratio(X)	0.80	0.20	0.57	0.71	0.49	0.74
Avail Cap(c_a), veh/h	521	2444	1932	862	649	804
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	48.3	5.6	16.4	18.3	39.8	35.1
Incr Delay (d2), s/veh	4.9	0.2	1.2	4.8	2.7	5.9
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.9	1.8	9.2	12.0	4.1	16.1
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	53.2	5.8	17.6	23.2	42.4	41.0
LnGrp LOS	D	A	B	C	D	D
Approach Vol, veh/h		756	1715		913	
Approach Delay, s/veh		23.0	19.6		41.5	
Approach LOS		C	B		D	
Timer - Assigned Phs			4		6	7
Phs Duration (G+Y+Rc), s			84.0		26.0	17.2
Change Period (Y+Rc), s			6.5		5.0	6.0
Max Green Setting (Gmax), s			77.5		21.0	17.0
Max Q Clear Time (g_c+I1), s			7.2		23.0	10.7
Green Ext Time (p_c), s			3.7		0.0	0.5
Intersection Summary						
HCM 6th Ctrl Delay			26.3			
HCM 6th LOS			C			
Notes						

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings
7: SH-105 & Woodmoor Drive

2025 Background PM

09/13/2022



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	248	557	1288	459	349	531
Future Volume (vph)	248	557	1288	459	349	531
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	20.0	87.0	67.0	67.0	23.0	
Total Split (%)	18.2%	79.1%	60.9%	60.9%	20.9%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	13.0	80.5	62.5	62.5	18.0	37.0
Actuated g/C Ratio	0.12	0.73	0.57	0.57	0.16	0.34
v/c Ratio	0.66	0.23	0.69	0.44	0.67	0.59
Control Delay	54.4	5.0	19.4	2.4	50.0	29.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.4	5.0	19.4	2.4	50.0	29.0
LOS	D	A	B	A	D	C
Approach Delay		20.2	14.9		37.3	
Approach LOS		C	B		D	

Intersection Summary

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.69

Intersection Signal Delay: 21.9


Intersection LOS: C

Intersection Capacity Utilization 66.4%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 7: SH-105 & Woodmoor Drive




HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2025 Background PM

09/13/2022



Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↰↱	↰↱	↰↱	↰	↰↱	↰↱	
Traffic Volume (veh/h)	248	557	1288	459	349	531	
Future Volume (veh/h)	248	557	1288	459	349	531	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1856	1856	
Adj Flow Rate, veh/h	267	599	1385	494	375	571	
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	
Percent Heavy Veh, %	2	2	2	2	3	3	
Cap, veh/h	334	2601	2063	920	561	720	
Arrive On Green	0.10	0.73	0.58	0.58	0.16	0.16	
Sat Flow, veh/h	3456	3647	3647	1585	3428	2768	
Grp Volume(v), veh/h	267	599	1385	494	375	571	
Grp Sat Flow(s),veh/h/ln	1728	1777	1777	1585	1714	1384	
Q Serve(g_s), s	8.3	6.0	29.5	20.9	11.3	18.0	
Cycle Q Clear(g_c), s	8.3	6.0	29.5	20.9	11.3	18.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	334	2601	2063	920	561	720	
V/C Ratio(X)	0.80	0.23	0.67	0.54	0.67	0.79	
Avail Cap(c_a), veh/h	440	2601	2063	920	561	720	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	48.6	4.8	15.9	14.1	43.2	37.9	
Incr Delay (d2), s/veh	7.6	0.2	1.8	2.2	6.2	8.7	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	3.9	2.0	11.8	7.7	5.3	16.0	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	56.2	5.0	17.6	16.3	49.4	46.6	
LnGrp LOS	E	A	B	B	D	D	
Approach Vol, veh/h		866	1879		946		
Approach Delay, s/veh		20.8	17.3		47.7		
Approach LOS		C	B		D		
Timer - Assigned Phs				4	6	7	8
Phs Duration (G+Y+Rc), s				87.0	23.0	16.6	70.4
Change Period (Y+Rc), s				6.5	5.0	6.0	* 6.5
Max Green Setting (Gmax), s				80.5	18.0	14.0	* 62
Max Q Clear Time (g_c+I1), s				8.0	20.0	10.3	31.5
Green Ext Time (p_c), s				4.8	0.0	0.3	16.1
Intersection Summary							
HCM 6th Ctrl Delay			25.9				
HCM 6th LOS			C				


Notes

User approved pedestrian interval to be less than phase max green.

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings
7: SH-105 & Woodmoor Drive

2025 Total AM
09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↔↔	↑↑	↑↑	↔	↔↔	↔↔
Traffic Volume (vph)	255	434	996	561	297	594
Future Volume (vph)	255	434	996	561	297	594
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	23.0	82.0	59.0	59.0	28.0	
Total Split (%)	20.9%	74.5%	53.6%	53.6%	25.5%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	14.8	75.5	55.7	55.7	23.0	43.8
Actuated g/C Ratio	0.13	0.69	0.51	0.51	0.21	0.40
v/c Ratio	0.63	0.20	0.62	0.57	0.47	0.58
Control Delay	51.4	6.5	21.9	3.5	40.7	24.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.4	6.5	21.9	3.5	40.7	24.0
LOS	D	A	C	A	D	C
Approach Delay		23.1	15.3		29.6	
Approach LOS		C	B		C	

Intersection Summary

Cycle Length: 110
 Actuated Cycle Length: 110
 Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 60
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.63
 Intersection Signal Delay: 21.1
 Intersection LOS: C
 Intersection Capacity Utilization 57.1%
 ICU Level of Service B
 Analysis Period (min) 15


Splits and Phases: 7: SH-105 & Woodmoor Drive



HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive


2025 Total AM
09/13/2022



Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↔↔	↑↑	↑↑	↔	↔↔	↔↔	
Traffic Volume (veh/h)	255	434	996	561	297	594	
Future Volume (veh/h)	255	434	996	561	297	594	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1826	1826	1856	1856	1841	1841	
Adj Flow Rate, veh/h	283	482	1107	623	330	660	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Percent Heavy Veh, %	5	5	3	3	4	4	
Cap, veh/h	353	2381	1858	829	711	862	
Arrive On Green	0.10	0.69	0.53	0.53	0.21	0.21	
Sat Flow, veh/h	3374	3561	3618	1572	3401	2745	
Grp Volume(v), veh/h	283	482	1107	623	330	660	
Grp Sat Flow(s),veh/h/ln	1687	1735	1763	1572	1700	1373	
Q Serve(g_s), s	9.0	5.6	23.8	34.1	9.3	23.0	
Cycle Q Clear(g_c), s	9.0	5.6	23.8	34.1	9.3	23.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	353	2381	1858	829	711	862	
V/C Ratio(X)	0.80	0.20	0.60	0.75	0.46	0.77	
Avail Cap(c_a), veh/h	521	2381	1858	829	711	862	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	48.1	6.3	17.9	20.4	38.1	34.1	
Incr Delay (d2), s/veh	5.5	0.2	1.4	6.2	2.2	6.4	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	4.0	1.9	9.7	13.4	4.1	17.8	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	53.6	6.5	19.3	26.6	40.3	40.5	
LnGrp LOS	D	A	B	C	D	D	
Approach Vol, veh/h		765	1730		990		
Approach Delay, s/veh		23.9	22.0		40.5		
Approach LOS		C	C		D		
Timer - Assigned Phs				4	6	7	8
Phs Duration (G+Y+Rc), s				82.0	28.0	17.5	64.5
Change Period (Y+Rc), s				6.5	5.0	6.0	* 6.5
Max Green Setting (Gmax), s				75.5	23.0	17.0	* 54
Max Q Clear Time (g_c+l1), s				7.6	25.0	11.0	36.1
Green Ext Time (p_c), s				3.7	0.0	0.5	10.1
Intersection Summary							
HCM 6th Ctrl Delay			27.6				
HCM 6th LOS			C				
Notes							

Timings
7: SH-105 & Woodmoor Drive

2025 Total PM
09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↔↔	↑↑	↑↑	↔	↔↔	↔↔
Traffic Volume (vph)	274	557	1288	506	354	569
Future Volume (vph)	274	557	1288	506	354	569
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	21.0	86.0	65.0	65.0	24.0	
Total Split (%)	19.1%	78.2%	59.1%	59.1%	21.8%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	13.9	79.5	60.6	60.6	19.0	38.9
Actuated g/C Ratio	0.13	0.72	0.55	0.55	0.17	0.35
v/c Ratio	0.68	0.23	0.71	0.49	0.65	0.60
Control Delay	54.1	5.4	21.1	2.7	48.2	28.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.1	5.4	21.1	2.7	48.2	28.8
LOS	D	A	C	A	D	C
Approach Delay		21.5	15.9		36.2	
Approach LOS		C	B		D	

Intersection Summary

Cycle Length: 110
 Actuated Cycle Length: 110
 Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 70
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.71
 Intersection Signal Delay: 22.5
 Intersection LOS: C
 Intersection Capacity Utilization 67.3%
 ICU Level of Service C
 Analysis Period (min) 15


Splits and Phases: 7: SH-105 & Woodmoor Drive









HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2025 Total PM
09/13/2022




Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations							
Traffic Volume (veh/h)	274	557	1288	506	354	569	
Future Volume (veh/h)	274	557	1288	506	354	569	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1856	1856	
Adj Flow Rate, veh/h	295	599	1385	544	381	612	
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	
Percent Heavy Veh, %	2	2	2	2	3	3	
Cap, veh/h	363	2568	2001	892	592	769	
Arrive On Green	0.11	0.72	0.56	0.56	0.17	0.17	
Sat Flow, veh/h	3456	3647	3647	1585	3428	2768	
Grp Volume(v), veh/h	295	599	1385	544	381	612	
Grp Sat Flow(s),veh/h/ln	1728	1777	1777	1585	1714	1384	
Q Serve(g_s), s	9.2	6.2	30.7	25.1	11.4	19.0	
Cycle Q Clear(g_c), s	9.2	6.2	30.7	25.1	11.4	19.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	363	2568	2001	892	592	769	
V/C Ratio(X)	0.81	0.23	0.69	0.61	0.64	0.80	
Avail Cap(c_a), veh/h	471	2568	2001	892	592	769	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	48.2	5.1	17.2	16.0	42.3	36.8	
Incr Delay (d2), s/veh	8.1	0.2	2.0	3.1	5.3	8.4	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	4.4	2.1	12.4	9.4	5.2	17.0	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	56.2	5.3	19.2	19.1	47.7	45.2	
LnGrp LOS	E	A	B	B	D	D	
Approach Vol, veh/h		894	1929		993		
Approach Delay, s/veh		22.1	19.2		46.1		
Approach LOS		C	B		D		
Timer - Assigned Phs			4		6	7	8
Phs Duration (G+Y+Rc), s			86.0		24.0	17.6	68.4
Change Period (Y+Rc), s			6.5		5.0	6.0	* 6.5
Max Green Setting (Gmax), s			79.5		19.0	15.0	* 60
Max Q Clear Time (g_c+I1), s			8.2		21.0	11.2	32.7
Green Ext Time (p_c), s			4.8		0.0	0.4	15.4
Intersection Summary							
HCM 6th Ctrl Delay			26.9				
HCM 6th LOS			C				
Notes							

Timings
7: SH-105 & Woodmoor Drive

2045 Background AM

09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↔↔	↑↑	↑↑	↔	↔↔	↔↔
Traffic Volume (vph)	301	603	1384	666	350	649
Future Volume (vph)	301	603	1384	666	350	649
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	21.0	86.0	65.0	65.0	24.0	
Total Split (%)	19.1%	78.2%	59.1%	59.1%	21.8%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	14.6	79.5	59.9	59.9	19.0	39.6
Actuated g/C Ratio	0.13	0.72	0.54	0.54	0.17	0.36
v/c Ratio	0.76	0.27	0.81	0.65	0.67	0.71
Control Delay	57.7	5.6	24.6	5.6	49.0	33.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.7	5.6	24.6	5.6	49.0	33.2
LOS	E	A	C	A	D	C
Approach Delay		22.9	18.5		38.7	
Approach LOS		C	B		D	

Intersection Summary

Cycle Length: 110
 Actuated Cycle Length: 110
 Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.81
 Intersection Signal Delay: 24.6
 Intersection LOS: C
 Intersection Capacity Utilization 70.6%
 ICU Level of Service C
 Analysis Period (min) 15

Splits and Phases: 7: SH-105 & Woodmoor Drive




HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2045 Background AM

09/13/2022




Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑	↑↑	↑	←←	↑↑
Traffic Volume (veh/h)	301	603	1384	666	350	649
Future Volume (veh/h)	301	603	1384	666	350	649
Initial Q (Qb), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No	No		No	
Adj Sat Flow, veh/h/ln	1826	1826	1856	1856	1841	1841
Adj Flow Rate, veh/h	334	670	1538	740	389	721
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Percent Heavy Veh, %	5	5	3	3	4	4
Cap, veh/h	397	2507	1940	865	587	798
Arrive On Green	0.12	0.72	0.55	0.55	0.17	0.17
Sat Flow, veh/h	3374	3561	3618	1572	3401	2745
Grp Volume(v), veh/h	334	670	1538	740	389	721
Grp Sat Flow(s),veh/h/ln	1687	1735	1763	1572	1700	1373
Q Serve(g_s), s	10.7	7.3	38.3	44.0	11.8	19.0
Cycle Q Clear(g_c), s	10.7	7.3	38.3	44.0	11.8	19.0
Prop In Lane	1.00			1.00	1.00	1.00
Lane Grp Cap(c), veh/h	397	2507	1940	865	587	798
V/C Ratio(X)	0.84	0.27	0.79	0.86	0.66	0.90
Avail Cap(c_a), veh/h	460	2507	1940	865	587	798
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	1.00	1.00	1.00	1.00
Uniform Delay (d), s/veh	47.5	5.2	19.7	21.0	42.5	37.5
Incr Delay (d2), s/veh	11.7	0.3	3.4	10.6	5.8	15.6
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.1	2.4	15.7	17.7	5.4	20.5
Unsig. Movement Delay, s/veh						
LnGrp Delay(d),s/veh	59.2	5.5	23.1	31.6	48.3	53.1
LnGrp LOS	E	A	C	C	D	D
Approach Vol, veh/h		1004	2278		1110	
Approach Delay, s/veh		23.4	25.9		51.4	
Approach LOS		C	C		D	
Timer - Assigned Phs			4		6	7
Phs Duration (G+Y+Rc), s			86.0		24.0	19.0
Change Period (Y+Rc), s			6.5		5.0	6.0
Max Green Setting (Gmax), s			79.5		19.0	15.0
Max Q Clear Time (g_c+I1), s			9.3		21.0	12.7
Green Ext Time (p_c), s			5.5		0.0	0.3
Intersection Summary						
HCM 6th Ctrl Delay			31.8			
HCM 6th LOS			C			
Notes						

* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.

Timings
7: SH-105 & Woodmoor Drive

2045 Background PM

09/13/2022



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	301	774	1790	558	424	647
Future Volume (vph)	301	774	1790	558	424	647
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	19.0	87.0	68.0	68.0	23.0	
Total Split (%)	17.3%	79.1%	61.8%	61.8%	20.9%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	12.8	80.5	62.7	62.7	18.0	36.8
Actuated g/C Ratio	0.12	0.73	0.57	0.57	0.16	0.33
v/c Ratio	0.81	0.32	0.95	0.52	0.82	0.75
Control Delay	64.5	5.6	34.8	2.9	57.7	37.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	64.5	5.6	34.8	2.9	57.7	37.4
LOS	E	A	C	A	E	D
Approach Delay		22.1	27.2		45.4	
Approach LOS		C	C		D	

Intersection Summary

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.95

Intersection Signal Delay: 30.3


Intersection LOS: C

Intersection Capacity Utilization 83.9%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 7: SH-105 & Woodmoor Drive




HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2045 Background PM


09/13/2022



Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↰↰	↱↱	↱↱	↰	↰↰	↰↰	
Traffic Volume (veh/h)	301	774	1790	558	424	647	
Future Volume (veh/h)	301	774	1790	558	424	647	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1856	1856	
Adj Flow Rate, veh/h	324	832	1925	600	456	696	
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	
Percent Heavy Veh, %	2	2	2	2	3	3	
Cap, veh/h	384	2850	2261	1008	561	761	
Arrive On Green	0.11	0.80	0.64	0.64	0.16	0.16	
Sat Flow, veh/h	3456	3647	3647	1585	3428	2768	
Grp Volume(v), veh/h	324	832	1925	600	456	696	
Grp Sat Flow(s),veh/h/ln	1728	1777	1777	1585	1714	1384	
Q Serve(g_s), s	10.1	6.7	47.3	24.4	14.1	18.0	
Cycle Q Clear(g_c), s	10.1	6.7	47.3	24.4	14.1	18.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	384	2850	2261	1008	561	761	
V/C Ratio(X)	0.84	0.29	0.85	0.60	0.81	0.92	
Avail Cap(c_a), veh/h	408	2850	2261	1008	561	761	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	47.9	2.8	15.9	11.7	44.4	38.6	
Incr Delay (d2), s/veh	14.2	0.3	4.3	2.6	12.2	17.5	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	5.1	1.8	18.7	8.7	6.9	20.2	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	62.1	3.1	20.2	14.3	56.5	56.1	
LnGrp LOS	E	A	C	B	E	E	
Approach Vol, veh/h		1156	2525		1152		
Approach Delay, s/veh		19.6	18.8		56.3		
Approach LOS		B	B		E		
Timer - Assigned Phs				4	6	7	8
Phs Duration (G+Y+Rc), s				94.9	23.0	18.2	76.7
Change Period (Y+Rc), s				6.5	5.0	6.0	* 6.5
Max Green Setting (Gmax), s				80.5	18.0	13.0	* 63
Max Q Clear Time (g_c+l1), s				8.7	20.0	12.1	49.3
Green Ext Time (p_c), s				7.3	0.0	0.1	11.5
Intersection Summary							
HCM 6th Ctrl Delay			27.9				
HCM 6th LOS			C				
Notes							

Timings
7: SH-105 & Woodmoor Drive

2045 Total AM
09/13/2022



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	310	605	1385	680	360	710
Future Volume (vph)	310	605	1385	680	360	710
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	21.0	84.0	63.0	63.0	26.0	
Total Split (%)	19.1%	76.4%	57.3%	57.3%	23.6%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	14.7	77.5	57.8	57.8	21.0	41.7
Actuated g/C Ratio	0.13	0.70	0.53	0.53	0.19	0.38
v/c Ratio	0.77	0.28	0.84	0.67	0.62	0.75
Control Delay	58.9	6.3	27.3	5.9	45.7	33.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	58.9	6.3	27.3	5.9	45.7	33.4
LOS	E	A	C	A	D	C
Approach Delay		24.1	20.2		37.5	
Approach LOS		C	C		D	


Intersection Summary

Cycle Length: 110
 Actuated Cycle Length: 110
 Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 80
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.84
 Intersection Signal Delay: 25.7
 Intersection Capacity Utilization 71.9%
 Analysis Period (min) 15

Intersection LOS: C

ICU Level of Service C


Splits and Phases: 7: SH-105 & Woodmoor Drive



HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive


2045 Total AM
09/13/2022



Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↰↰	↱↱	↰↰	↱	↰↰	↱↱	
Traffic Volume (veh/h)	310	605	1385	680	360	710	
Future Volume (veh/h)	310	605	1385	680	360	710	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1826	1826	1856	1856	1841	1841	
Adj Flow Rate, veh/h	344	672	1539	756	400	789	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Percent Heavy Veh, %	5	5	3	3	4	4	
Cap, veh/h	407	2444	1867	833	649	855	
Arrive On Green	0.12	0.70	0.53	0.53	0.19	0.19	
Sat Flow, veh/h	3374	3561	3618	1572	3401	2745	
Grp Volume(v), veh/h	344	672	1539	756	400	789	
Grp Sat Flow(s),veh/h/ln	1687	1735	1763	1572	1700	1373	
Q Serve(g_s), s	11.0	7.8	40.1	47.9	11.9	21.0	
Cycle Q Clear(g_c), s	11.0	7.8	40.1	47.9	11.9	21.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	407	2444	1867	833	649	855	
V/C Ratio(X)	0.85	0.27	0.82	0.91	0.62	0.92	
Avail Cap(c_a), veh/h	460	2444	1867	833	649	855	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	47.4	6.0	21.6	23.4	40.8	36.6	
Incr Delay (d2), s/veh	12.5	0.3	4.3	15.5	4.3	16.9	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	5.3	2.7	16.8	20.3	5.3	22.4	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	59.9	6.2	25.9	39.0	45.1	53.5	
LnGrp LOS	E	A	C	D	D	D	
Approach Vol, veh/h		1016	2295		1189		
Approach Delay, s/veh		24.4	30.2		50.7		
Approach LOS		C	C		D		
Timer - Assigned Phs			4		6	7	8
Phs Duration (G+Y+Rc), s			84.0		26.0	19.3	64.7
Change Period (Y+Rc), s			6.5		5.0	6.0	* 6.5
Max Green Setting (Gmax), s			77.5		21.0	15.0	* 58
Max Q Clear Time (g_c+l1), s			9.8		23.0	13.0	49.9
Green Ext Time (p_c), s			5.6		0.0	0.3	6.5
Intersection Summary							
HCM 6th Ctrl Delay			34.3				
HCM 6th LOS			C				
Notes							

Timings
7: SH-105 & Woodmoor Drive

2045 Total PM
09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	330	775	1790	605	430	685
Future Volume (vph)	330	775	1790	605	430	685
Turn Type	Prot	NA	NA	Perm	Prot	pt+ov
Protected Phases	7	4	8		6	6 7
Permitted Phases				8		
Detector Phase	7	4	8	8	6	6 7
Switch Phase						
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	
Minimum Split (s)	11.0	24.5	24.0	24.0	23.0	
Total Split (s)	20.0	87.0	67.0	67.0	23.0	
Total Split (%)	18.2%	79.1%	60.9%	60.9%	20.9%	
Yellow Time (s)	3.0	3.5	3.5	3.5	3.0	
All-Red Time (s)	3.0	3.0	2.0	2.0	2.0	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.0	6.5	5.5	5.5	5.0	
Lead/Lag	Lead		Lag	Lag		
Lead-Lag Optimize?	Yes		Yes	Yes		
Recall Mode	None	C-Max	C-Max	C-Max	Max	
Act Effect Green (s)	13.9	80.5	61.6	61.6	18.0	37.9
Actuated g/C Ratio	0.13	0.73	0.56	0.56	0.16	0.34
v/c Ratio	0.82	0.32	0.97	0.56	0.83	0.77
Control Delay	63.0	5.6	38.6	3.4	58.6	37.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	63.0	5.6	38.6	3.4	58.6	37.6
LOS	E	A	D	A	E	D
Approach Delay		22.7	29.7		45.7	
Approach LOS		C	C		D	

Intersection Summary

Cycle Length: 110
 Actuated Cycle Length: 110
 Offset: 0 (0%), Referenced to phase 4:EBT and 8:WBT, Start of Green
 Natural Cycle: 90
 Control Type: Actuated-Coordinated
 Maximum v/c Ratio: 0.97
 Intersection Signal Delay: 31.9
 Intersection LOS: C
 Intersection Capacity Utilization 84.9%
 ICU Level of Service E
 Analysis Period (min) 15


Splits and Phases: 7: SH-105 & Woodmoor Drive



HCM 6th Signalized Intersection Summary

7: SH-105 & Woodmoor Drive

2045 Total PM
09/13/2022






Movement	EBL	EBT	WBT	WBR	SBL	SBR	
Lane Configurations	↖↗	↑↑	↑↑	↖	↖↗	↖↗	
Traffic Volume (veh/h)	330	775	1790	605	430	685	
Future Volume (veh/h)	330	775	1790	605	430	685	
Initial Q (Qb), veh	0	0	0	0	0	0	
Ped-Bike Adj(A_pbT)	1.00			1.00	1.00	1.00	
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	
Work Zone On Approach		No	No		No		
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1856	1856	
Adj Flow Rate, veh/h	355	833	1925	651	462	737	
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	
Percent Heavy Veh, %	2	2	2	2	3	3	
Cap, veh/h	415	2834	2213	987	561	785	
Arrive On Green	0.12	0.80	0.62	0.62	0.16	0.16	
Sat Flow, veh/h	3456	3647	3647	1585	3428	2768	
Grp Volume(v), veh/h	355	833	1925	651	462	737	
Grp Sat Flow(s),veh/h/ln	1728	1777	1777	1585	1714	1384	
Q Serve(g_s), s	11.1	6.8	49.0	28.9	14.3	18.0	
Cycle Q Clear(g_c), s	11.1	6.8	49.0	28.9	14.3	18.0	
Prop In Lane	1.00			1.00	1.00	1.00	
Lane Grp Cap(c), veh/h	415	2834	2213	987	561	785	
V/C Ratio(X)	0.85	0.29	0.87	0.66	0.82	0.94	
Avail Cap(c_a), veh/h	440	2834	2213	987	561	785	
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	
Upstream Filter(l)	1.00	1.00	1.00	1.00	1.00	1.00	
Uniform Delay (d), s/veh	47.5	2.9	17.1	13.3	44.5	38.5	
Incr Delay (d2), s/veh	14.6	0.3	5.0	3.5	12.9	20.2	
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	
%ile BackOfQ(50%),veh/ln	5.6	1.9	19.7	10.5	7.1	21.5	
Unsig. Movement Delay, s/veh							
LnGrp Delay(d),s/veh	62.0	3.2	22.1	16.7	57.3	58.6	
LnGrp LOS	E	A	C	B	E	E	
Approach Vol, veh/h		1188	2576		1199		
Approach Delay, s/veh		20.8	20.7		58.1		
Approach LOS		C	C		E		
Timer - Assigned Phs				4	6	7	8
Phs Duration (G+Y+Rc), s				94.4	23.0	19.2	75.2
Change Period (Y+Rc), s				6.5	5.0	6.0	* 6.5
Max Green Setting (Gmax), s				80.5	18.0	14.0	* 62
Max Q Clear Time (g_c+l1), s				8.8	20.0	13.1	51.0
Green Ext Time (p_c), s				7.4	0.0	0.1	9.4
Intersection Summary							
HCM 6th Ctrl Delay			29.8				
HCM 6th LOS			C				
Notes							

HCM 6th TWSC
8: Monument Hill Road & RIRO Access

2025 Total AM
10/21/2022

Intersection

Int Delay, s/veh 0.1

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	0	4	439	5	0	414
Future Vol, veh/h	0	4	439	5	0	414
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	-	0	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	4	477	5	0	450




Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	-	480	0
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	6.22	-
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	3.318	-
Pot Cap-1 Maneuver	0	586	-
Stage 1	0	-	-
Stage 2	0	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	586	-
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	11.2	0	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBT
Capacity (veh/h)	-	-	586
HCM Lane V/C Ratio	-	-	0.007
HCM Control Delay (s)	-	-	11.2
HCM Lane LOS	-	-	B
HCM 95th %tile Q(veh)	-	-	0

HCM 6th TWSC
8: Monument Hill Road & RIRO Access

2025 Total PM
10/21/2022




Intersection						
Int Delay, s/veh	0					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	0	3	329	17	0	445
Future Vol, veh/h	0	3	329	17	0	445
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	-	0	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	3	358	18	0	484
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	-	367	0	0	-	-
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Critical Hdwy	-	6.22	-	-	-	-
Critical Hdwy Stg 1	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-
Follow-up Hdwy	-	3.318	-	-	-	-
Pot Cap-1 Maneuver	0	678	-	-	0	-
Stage 1	0	-	-	-	0	-
Stage 2	0	-	-	-	0	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	-	678	-	-	-	-
Mov Cap-2 Maneuver	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	10.3	0		0		
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBRWBLn1		SBT		
Capacity (veh/h)	-	678		-		
HCM Lane V/C Ratio	-	0.005		-		
HCM Control Delay (s)	-	10.3		-		
HCM Lane LOS	-	B		-		
HCM 95th %tile Q(veh)	-	0		-		

HCM 6th TWSC
8: Monument Hill Road & RIRO Access

2045 Total AM
10/21/2022

Intersection

Int Delay, s/veh 0.1

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	0	5	530	5	0	490
Future Vol, veh/h	0	5	530	5	0	490
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	-	0	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	5	576	5	0	533




Major/Minor	Minor1	Major1	Major2
Conflicting Flow All	-	579	0
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	6.22	-
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	3.318	-
Pot Cap-1 Maneuver	0	515	-
Stage 1	0	-	-
Stage 2	0	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	515	-
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	12.1	0	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBT
Capacity (veh/h)	-	-	515
HCM Lane V/C Ratio	-	-	0.011
HCM Control Delay (s)	-	-	12.1
HCM Lane LOS	-	-	B
HCM 95th %tile Q(veh)	-	-	0




HCM 6th TWSC
8: Monument Hill Road & RIRO Access

2045 Total PM
10/21/2022

Intersection						
Int Delay, s/veh	0.1					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	0	5	390	20	0	535
Future Vol, veh/h	0	5	390	20	0	535
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	-	0	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	0	5	424	22	0	582
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	-	435	0	0	-	-
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Critical Hdwy	-	6.22	-	-	-	-
Critical Hdwy Stg 1	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-
Follow-up Hdwy	-	3.318	-	-	-	-
Pot Cap-1 Maneuver	0	621	-	-	0	-
Stage 1	0	-	-	-	0	-
Stage 2	0	-	-	-	0	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	-	621	-	-	-	-
Mov Cap-2 Maneuver	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	10.8	0		0		
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBRWBLn1		SBT		
Capacity (veh/h)	-	621		-		
HCM Lane V/C Ratio	-	0.009		-		
HCM Control Delay (s)	-	10.8		-		
HCM Lane LOS	-	B		-		
HCM 95th %tile Q(veh)	-	0		-		




HCM 6th TWSC
9: Monument Hill Road & Full Access

2025 Total AM
10/21/2022

Intersection						
Int Delay, s/veh	1.3					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	53	8	427	11	4	359
Future Vol, veh/h	53	8	427	11	4	359
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	58	9	464	12	4	390
Major/Minor	Minor1		Major1		Major2	
Conflicting Flow All	868	470	0	0	476	0
Stage 1	470	-	-	-	-	-
Stage 2	398	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	323	594	-	-	1086	-
Stage 1	629	-	-	-	-	-
Stage 2	678	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	321	594	-	-	1086	-
Mov Cap-2 Maneuver	321	-	-	-	-	-
Stage 1	629	-	-	-	-	-
Stage 2	675	-	-	-	-	-
Approach	WB		NB		SB	
HCM Control Delay, s	18		0		0.1	
HCM LOS	C					
Minor Lane/Major Mvmt		NBT	NBRWBLn1	SBL	SBT	
Capacity (veh/h)		-	-	342	1086	-
HCM Lane V/C Ratio		-	-	0.194	0.004	-
HCM Control Delay (s)		-	-	18	8.3	0
HCM Lane LOS		-	-	C	A	A
HCM 95th %tile Q(veh)		-	-	0.7	0	-




HCM 6th TWSC
9: Monument Hill Road & Full Access

2025 Total PM
10/21/2022

Intersection						
Int Delay, s/veh	0.9					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	33	5	289	39	13	408
Future Vol, veh/h	33	5	289	39	13	408
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	36	5	314	42	14	443
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	806	335	0	0	356	0
Stage 1	335	-	-	-	-	-
Stage 2	471	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	351	707	-	-	1203	-
Stage 1	725	-	-	-	-	-
Stage 2	628	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	346	707	-	-	1203	-
Mov Cap-2 Maneuver	346	-	-	-	-	-
Stage 1	725	-	-	-	-	-
Stage 2	619	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	15.9	0		0.2		
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1		SBL	SBT	
Capacity (veh/h)	-	-	371	1203	-	
HCM Lane V/C Ratio	-	-	0.111	0.012	-	
HCM Control Delay (s)	-	-	15.9	8	0	
HCM Lane LOS	-	-	C	A	A	
HCM 95th %tile Q(veh)	-	-	0.4	0	-	




HCM 6th TWSC
9: Monument Hill Road & Full Access

2045 Total AM
10/21/2022

Intersection						
Int Delay, s/veh	1.5					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	55	10	525	15	5	440
Future Vol, veh/h	55	10	525	15	5	440
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	60	11	571	16	5	478
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	1067	579	0	0	587	0
Stage 1	579	-	-	-	-	-
Stage 2	488	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	246	515	-	-	988	-
Stage 1	560	-	-	-	-	-
Stage 2	617	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	244	515	-	-	988	-
Mov Cap-2 Maneuver	244	-	-	-	-	-
Stage 1	560	-	-	-	-	-
Stage 2	613	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	23.5	0		0.1		
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBL	SBT		
Capacity (veh/h)	-	-	265	988	-	
HCM Lane V/C Ratio	-	-	0.267	0.006	-	
HCM Control Delay (s)	-	-	23.5	8.7	0	
HCM Lane LOS	-	-	C	A	A	
HCM 95th %tile Q(veh)	-	-	1	0	-	

HCM 6th TWSC
9: Monument Hill Road & Full Access

2045 Total PM
10/21/2022

Intersection						
Int Delay, s/veh	0.9					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Vol, veh/h	35	5	355	40	15	500
Future Vol, veh/h	35	5	355	40	15	500
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	38	5	386	43	16	543
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	983	408	0	0	429	0
Stage 1	408	-	-	-	-	-
Stage 2	575	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	276	643	-	-	1130	-
Stage 1	671	-	-	-	-	-
Stage 2	563	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	270	643	-	-	1130	-
Mov Cap-2 Maneuver	270	-	-	-	-	-
Stage 1	671	-	-	-	-	-
Stage 2	552	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	19.5	0		0.2		
HCM LOS	C					
Minor Lane/Major Mvmt	NBT	NBRWBLn1	SBL	SBT		
Capacity (veh/h)	-	-	291	1130	-	
HCM Lane V/C Ratio	-	-	0.149	0.014	-	
HCM Control Delay (s)	-	-	19.5	8.2	0	
HCM Lane LOS	-	-	C	A	A	
HCM 95th %tile Q(veh)	-	-	0.5	0	-	

APPENDIX E


Queues Analysis Worksheets

Queues

2025 Total AM

7: SH-105 & Woodmoor Drive

09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Group Flow (vph)	283	482	1107	623	330	660
v/c Ratio	0.63	0.20	0.62	0.57	0.47	0.58
Control Delay	51.4	6.5	21.9	3.5	40.7	24.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	51.4	6.5	21.9	3.5	40.7	24.0
Queue Length 50th (ft)	97	58	290	0	106	173
Queue Length 95th (ft)	140	78	371	58	151	231
Internal Link Dist (ft)		920	1314		1179	
Turn Bay Length (ft)	300			300	250	250
Base Capacity (vph)	515	2359	1775	1101	704	1195
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.55	0.20	0.62	0.57	0.47	0.55
Intersection Summary						

Queues

2025 Total PM

7: SH-105 & Woodmoor Drive

09/13/2022




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Group Flow (vph)	295	599	1385	544	381	612
v/c Ratio	0.68	0.23	0.71	0.49	0.65	0.60
Control Delay	54.1	5.4	21.1	2.7	48.2	28.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.1	5.4	21.1	2.7	48.2	28.8
Queue Length 50th (ft)	102	64	370	0	130	176
Queue Length 95th (ft)	148	84	454	49	182	242
Internal Link Dist (ft)		920	1314		1179	
Turn Bay Length (ft)	300			300	250	250
Base Capacity (vph)	468	2557	1948	1116	587	1042
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.63	0.23	0.71	0.49	0.65	0.59
Intersection Summary						

Queues

2045 Total AM

7: SH-105 & Woodmoor Drive

09/13/2022



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Group Flow (vph)	344	672	1539	756	400	789
v/c Ratio	0.77	0.28	0.84	0.67	0.62	0.75
Control Delay	58.9	6.3	27.3	5.9	45.7	33.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	58.9	6.3	27.3	5.9	45.7	33.4
Queue Length 50th (ft)	122	81	466	36	135	257
Queue Length 95th (ft)	#181	104	572	139	186	340
Internal Link Dist (ft)		920	1314		1179	
Turn Bay Length (ft)	300			300	250	250
Base Capacity (vph)	454	2422	1843	1133	642	1065
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.76	0.28	0.84	0.67	0.62	0.74

Intersection Summary


95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

Queues

2045 Total PM

7: SH-105 & Woodmoor Drive

09/13/2022



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Group Flow (vph)	355	833	1925	651	462	737
v/c Ratio	0.95	0.32	0.94	0.55	0.83	0.80
Control Delay	84.7	5.6	32.6	2.8	58.6	40.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	84.7	5.6	32.6	2.8	58.6	40.8
Queue Length 50th (ft)	130	93	625	1	164	261
Queue Length 95th (ft)	#221	118	#838	48	#242	346
Internal Link Dist (ft)		920	1314		1179	
Turn Bay Length (ft)	300			300	250	250
Base Capacity (vph)	374	2589	2042	1187	556	916
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.95	0.32	0.94	0.55	0.83	0.80

Intersection Summary


95th percentile volume exceeds capacity, queue may be longer.
Queue shown is maximum after two cycles.

APPENDIX F

Signal Warrant Analysis Worksheets

WARRANT 2 - FOUR HOUR VEHICULAR VOLUME (70% FACTOR)

(COMMUNITY LESS THAN 10,000 POPULATION OR ABOVE 70 km/h (40 mph) ON MAJOR STREET)



* NOTE: 80 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACH WITH TWO OR MORE LANES AND 60 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACHING WITH ONE LANE.

PALMER DIVIDE & MONUMENT HILL (#1)

SIGNAL WARRANT ANALYSIS


FOUR HOUR VOLUME WARRANT

● 2045 TOTAL TRAFFIC VOLUME

Source: Manual of Uniform Traffic Control Devices 2009

WARRANT 2 - FOUR HOUR VEHICULAR VOLUME (70% FACTOR)

(COMMUNITY LESS THAN 10,000 POPULATION OR ABOVE 70 km/h (40 mph) ON MAJOR STREET)



* NOTE: 80 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACH WITH TWO OR MORE LANES AND 60 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACHING WITH ONE LANE.

MONUMENT HILL & MISTY ACRES (#2)


SIGNAL WARRANT ANALYSIS

FOUR HOUR VOLUME WARRANT

● 2045 TOTAL TRAFFIC VOLUME

Source: Manual of Uniform Traffic Control Devices 2009

WARRANT 2 - FOUR HOUR VEHICULAR VOLUME



* NOTE: 115 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACH WITH TWO OR MORE LANES AND 80 VPH APPLIES AS THE LOWER THRESHOLD VOLUME FOR A MINOR STREET APPROACHING WITH ONE LANE.

MONUMENT HILL & WOODMOOR DR (#6)
SIGNAL WARRANT ANALYSIS
FOUR HOUR VOLUME WARRANT


● 2045 TOTAL TRAFFIC DATA POINT

Source: Manual of Uniform Traffic Control Devices 2009

APPENDIX G

Conceptual Site Plan

K:\COS_Civil\096471007_Monument Hill\CADD\Exhibits\Monument Hill_Site Plan Exhibit.dwg



Monument Hill Road- option 1							22220
THE GARRETT COMPANIES							7/15/22
UNIT TABULATION - 2 STORY BIG HOUSE & 3 STORY RESIDENTIAL							% BREAKDOWN
UNIT NAME	UNIT TYPE	NET AREA(SF)	UNIT COUNT	PARKING	PERCENTAGE	TOTAL AREA	
A1-EU	1br/1ba	663	4	6	2%	2,652	39%
A1L-BH	1br/1ba	676	20	30	8%	13,520	
A1-U-BH	1br/1ba	822	20	30	8%	16,440	
A2U-BH	1br/1ba	956	40	60	15%	38,240	
A2-EU	1br/1ba	759	12	18	5%	9,108	
A3-EU	1br/1ba	824	6	9	2%	4,944	52%
B1-EU	2br/2ba	1,093	12	20	5%	13,116	
B2-EU	2br/2ba	1,175	12	20	5%	14,100	
B3-EU	2br/2ba	1,265	6	10	2%	7,590	
B1U-BH	2br/2ba	1,247	40	40	15%	49,880	
B2L-BH	2br/2ba	1,328	31	31	12%	41,168	9%
B2U-BH	2br/2ba	1,408	31	53	12%	43,648	
B4-EU	2br/2ba	1,265	6	10	2%	7,590	
C1L-BH	3br/2ba	1,508	9	18	3%	13,572	
C1U-BH	3br/2ba	1,577	9	18	3%	14,193	
C1-EU	3br/2ba	1,433	6	12	2%	8,598	
TOTALS			264	356	100%	298,359	

PARKING COUNT

PARKING REQUIRED:
1 BED (102 UNITS) X 1.5 SPACES = 153
2 BED (138 UNITS) X 1.7 SPACES = 235
3 BED (24 UNITS) X 2 SPACES = 48
= 436 SPACES

PARKING PROVIDED:
200 GARAGE SPACES
292 SURFACE SPACES
= 492 SPACES

MONUMENT HILL
PRELIMINARY SITE PLAN
09/13/2022

Kimley»Horn

© 2022 KIMLEY-HORN AND ASSOCIATES, INC.
2 N NEVADA AVE, SUITE 300, COLORADO SPRINGS, 80903
PHONE: 719-453-0180

Traffic Impact Study V3.pdf Markup Summary

Callout (2)

intersection with 1700 feet existing intersection sight sight line
be 200 feet of storage length.
A permit along 1700 feet existing intersection sight sight line
on traffic is anticipated to increase the existing access
to or movements are needed at the intersection. Based
reject traffic on the north leg Woodmoor Drive at SH-
along access traffic volume for more than 20 percent
at 7.7 percent during the afternoon peak hour on the
2022 counts). Therefore, a CDOT access permit is not
on with this project.

Subject: Callout
Page Label: 54
Author: CDurham
Date: 11/14/2022 1:17:53 PM
Status:
Color:
Layer:
Space:

Modifications to intersection are being proposed.
Based on that assumption, access permit would be
anticipated.

A permit along 1700 feet existing intersection sight sight line
on traffic is anticipated to increase the existing access
to or movements are needed at the intersection. Based
reject traffic on the north leg Woodmoor Drive at SH-
along access traffic volume for more than 20 percent
at 7.7 percent during the afternoon peak hour on the
2022 counts). Therefore, a CDOT access permit is not
on with this project.

Subject: Callout
Page Label: 54
Author: CDurham
Date: 11/14/2022 1:19:30 PM
Status:
Color:
Layer:
Space:

These numbers should be updated to 2025
volumes and then determine % increase to
determine if access permit is required