WATER RESOURCES REPORT —RETREAT AT PRAIRIERIDGE FILINGS NO 1-3 Preliminary plan

TOPICAL REPORT



PREPARED BY John McGinn, PE 19534

RESPEC 5540 Tech Center Drive, Suite 100 Colorado Springs, Colorado 80919

PREPARED FOR Falcon Area Water and Wastewater Authority

REVISION SEPTEMBER 11, 2024

Project Number W0242.22001





This report is a submittal for Retreat at PrairieRidge Filings 1-3 Preliminary Plan.. The land is to be provided central water and sewer services through the Falcon Area Water and Wastewater Authority (FAWWA), which will become the overall service entity for, not only Sterling Ranch, but also the Retreat and the future Ranch.

It is expected that an urban residential home the Falcon Area Water and Wastewater Authority will require an average of 0.353 annual acre-feet, which is the adopted user characteristic for FAWWA. This is consistent with historic needs for nearby developments. Note that for the smaller high-density lots, FAWWA has adopted an SFE equivalency ratio to account for substantially reduced water needs, although this is partially offset by estimation of common area irrigation needs.

Retreat at PrairieRidge Filings 1-3 Preliminary Plan includes 193 lots, 24 of which fall into high-density development ratios for small lots, and roughly 3.30 annual acre-feet of water set aside for irrigated landscaping.

The resulting water demand on the central water system is 70.93 acre-feet.

The total 300 year water supply for FAWWA is shown in Table 3 and totals 1962.23 annual acre-feet $_{300}$ $_{year}$, Appendix F is an accounting of active water commitments, which total 1033.87 acre-feet including all subdivisions committed through September 11, 2024.

This leaves a net excess of currently available water of 928.36 $AF_{300 year}$ and therefore there is more than sufficient water supply to meet the needs of Retreat at PrairieRidge Filings 1-3 Preliminary Plan on the 300-year basis.

Highlights of this Revision;

- 6 Large lots on central water
- Pending Case 24 CW 3007 withheld from Water Supply



TABLE OF CONTENTS

1.0	INTRO	DDUCTION	3
	1.1	NEW DEVELOPMENT DESCRIPTION	.3
		ECTION OF WATER NEEDS	
	2.1	ANALYSIS OF WATER NEEDS	.3
	note c	n possible future alternate water supply	.4
3.0 \	NATER	RIGHTS AND SYSTEM FACILITIES	5
	3.1	WATER RIGHTS	.5
	3.2	ADEQUACY OF WATER RIGHTS CURRENT SUPPLY	.7
	3.3	MASTER PLANNING AND LONG-TERM AND FUTURE SOURCES OF SUPPLY	.7
	3.4	SYSTEM INTERCONNECTS	.8
	3.5	SOURCE OF PHYSICAL SUPPLY	.8
	3.6	WATER QUALITY AND TREATMENT	.9
	3.7	WATER STORAGE, DISTRIBUTION, AND TRANSMISSION LINES	.9
	3.8	PUMPING FOR SERVICE PRESSURES	.9
APP	ENDIC	ES	

APPENDIX A – WATER SERVICE AREAS

APPENDIX B - PrairieRidge Filing 1 Preliminary Plan

APPENDIX C – WATER RIGHTS DECREES

APPENDIX D – WELL PERMITS

APPENDIX E - WATER QUALITY FROM STERLING EXISTING WELLS

APPENDIX F - FAWWA WATER SUPPLY VS CURRENT WATER COMMITMENTS

APPENDIX G – WATER SUPPLY SUMMARY FORM

ii.



1.0 INTRODUCTION

The purpose of this study is to provide a preliminary outline of the water resources and wastewater needs that would be necessary for the Retreat at PrairieRidge Filings 1-3 Preliminary Plan development.

1.1 NEW DEVELOPMENT DESCRIPTION

The Retreat at PrairieRidge Filings 1-3 Preliminary Plan development is located east of Vollmer Road and north of Woodmen Road. This 108.89 acre area will include 193 single family lots.

Appendix A contains the Overall Service Area Map for FAWWA,

Appendix B contains the proposed Retreat at PrairieRidge Filings 1-3 Preliminary Plan

2.0 PROJECTION OF WATER NEEDS

2.1 ANALYSIS OF WATER NEEDS

It is expected that the residential lots on central water will be developed with single-family housing with anticipated turf grass landscaping.

For the last five years, there has been a trend in land use that provides for much smaller lots and much denser development in certain areas. Lots smaller than 7,000 square feet are anticipated in certain areas. This is resulting in much lower water needs for these types of developments. The standard SFE adopted in Sterling Ranch has been 0.353 annual acre-feet. However, this is for the formerly typical household anticipating 1500 square feet or more of landscaping. In order to adjust for such increases in density, we are adopting a scaled down equivalency to meet the changes in lot sizes. For instance, lot areas less than 3500 sf have reduced water use that roughly is equivalent to apartments or townhomes where water use is indoor only.

Based on data from other areas, we have established a SFE equivalency factor scale as follows for these smaller lot sizes;

Lot Size	SFE Ratio	Effective Annual Demand
Lots < 2000 SF	0.65	0.23
Lots < 3500 SF	0.75	0.265
Lots < 7000 SF	0.90	0.318
Lots > 7000 SF	1.0	0.353

Table 1	CEE Equivalance for Link Dansity Late
Table 1.	SFE Equivalency for High Density Lots



Retreat at PrairieRidge Filings 1-3 Preliminary Plan has irrigated areas within the common areas or tracts that total roughly 1.32 acres. The landscaping plan specifies a Park on Tract B that we estimate to require 57,636 SF of active or permanent active irrigated landscaping.

Using the above criteria, there are 24 lots in the <7000 SF category and 169 lots in the >7000 SF category. The expected water demands are shown in Table 2 following:

# of Units	Land Use	Water Use Per Unit (AF/Unit)	Annual Demand (AF)	Average Daily Flow (ADF) (GPD)	Maximum Daily Flow (MDF) (@2.45 x ADF) (GPD)	Peak-Hour Flow (@ 1.5 x MDF) (GPM)	
0	Residential < 2000 SF	0.23	0	0	0	0	
0	Residential < 3500 SF	0.265	0	0	0	0	
24	Residential < 7000 SF	0.318	7.632	6813	16,693	17	
169	Residential > 7000 SF	0.353	59.995	53560	131,222	137	
1.32	Acres-Active Net Irrigation	2.5	3.30	2946	7218	8	
Total			70.93	63,319	155,132	162	

Table 2. Projected Water Demands for Retreat at PrairieRidge Filings 1-3

The total annual demand of the subdivision is 70.93 AF.

NOTE ON POSSIBLE FUTURE ALTERNATE WATER SUPPLY

This report bases all water supply for this subdivision on the central water system. It is noted that FAWWA has a pending water case 24 CW 3007, that would provide augmentation for six single family wells that might be used in the future as an alternate supply. If and when that case is complete, FAWWA may wish to apply to the County to shift water supply for six rural size lots in this subdivision to single family wells. Such shift would be insubstantial in terms of overall FAWWA supply and demand as it would represent less than 0.1 % of FAWWA overall supply and demand. If so, 5 of the lots will be served with new wells and 1 existing lot will continue to be provided service through its existing well which will be re-permitted after case approval. FAWWA will set aside an additional 2.6 annual acre-feet for augmented NNT Dawson water for the 5 new wells and one existing well. Additionally, FAWWA will reserve 4.8 Annual AF of LFH water for post pumping depletions for the five new wells.



3.0 WATER RIGHTS AND SYSTEM FACILITIES

3.1 WATER RIGHTS

Water rights adjudications have been decreed by the State of Colorado, Water Division 2 District Court, Water Division 1 District Court, and the Colorado Groundwater Commission. The comprehensive rights for the FAWWA service include both decrees and determinations. Local groundwater rights are associated with the service area components, Sterling, Retreat, and Prairie Ridge. Each of these sites has existing decrees and/or determinations outlining the rights associated with the development lands.

Both the water decrees and determinations are included in **Appendix C** as well as the deeds for the water.

Table 3 on the following page details all of the water rights currently available for the FAWWA service area which now total 1962.23 acre-feet $_{300 year}$.



<u>Table 2</u> Falcon Area Water and Wastewater Authority <u>Comprehensive Water Supply Inventory</u>

OPEN-VICE VICE VICE VICE VICE VICE VICE VICE	Uplaze September 11, 2024	Qurrent Le gal Skapple								
	La.d Formation Aquifer	Determination/	Traibutary Status		Allocation. 100 Year	Allocation 300 Year	Reference Beel	Notes	Sand	Specific
Lamb and angeneSin 2000 angeneSin 2000 			<u></u>	-Site Sterling Wa	ter Leyel Source:		-			
areadsareadsaread <t< td=""><td>Laranie Fox Hills</td><td>86- CW-19 08 CW113</td><td>NT NT</td><td>53,900 40</td><td>539.00 0.40</td><td>179.67 0.13</td><td>TANKA Animarat</td><td>Under 1410 acres Under 41.44 acres,</td><td>255</td><td>15%</td></t<>	Laranie Fox Hills	86- CW-19 08 CW113	NT NT	53,900 40	539.00 0.40	179.67 0.13	TANKA Animarat	Under 1410 acres Under 41.44 acres,	255	15%
NormN							from SR Water			
Angele	<i>i</i> trapahoe	86- CW-18	NT	57500	575.00	191.67		Under 1410 acres	240	17%
name NUMB NUMB <th< td=""><td>Laranzie Fox Hills</td><td>91 (3W35</td><td>NT</td><td>3673</td><td>36.73</td><td>12.08</td><td>Quit Claim</td><td>Bay our Water</td><td>143</td><td>1696</td></th<>	Laranzie Fox Hills	91 (3W35	NT	3673	36.73	12.08	Quit Claim	Bay our Water	143	1696
Description Note Description Descripion Descripion <thde< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></thde<>										
		91 C W 35	^{N1}	4030	49.30	16.45	Unit Charn	Kaygar water	20	1240
	Tatal MT On-Site					400.00				
Note: NCT 100 NT Alt Alt< Alt Alt Alt	Larancie Fex Hills	20(30/3059	20 CW 3059.	Additional Con-St 2784	te and Avenested 27 St	Storilae Wester 9.27	Level Scurves	02.54 acros SR. Oppmy	190	
								(Nom 3)		
New Set 0000 No. 10000 No. 100000 No. 100000								97.56 acres SR Quarry (Nom.5)		
	Berver	20 CW 3059	NNT	4556	45.56	15.19	fran SR Water See	97.54 acres SR Quarry (Nom 3)	295.2	
Televice state stat	Benver	08 CW113 Aug 20 CW 3059	NNT	72893	728.93	242.98	Bur A belowner Post Pumping Depletiens	Starling Ranch 1410 acres	0.158228464	
Televice state stat	6									
		Aug 20 CW 3059			0.00			Starling Ranch 41 44 reduced to 1.44 acres		
Lease for SHA CUT (CUT) CUT (CUT) 	Fatal from 20 CW 3059		84600			282.00				
Argabe Argabe Argabe COUNT BaseTO TO COUNT COUNT COUNT TO <b< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td>el Water (PrairieRidge) and i</td><td></td><td></td><td></td></b<>							el Water (PrairieRidge) and i			
Angels Bree Of CVEUT CVEUT NT Enter CVEUT ST Enter CVEUT ST Enter	Laramie Fox Hills			3850	38.50	12.83			190	15%
NameOf WayOF <th< td=""><td>Anna - Y</td><td></td><td></td><td></td><td></td><td>10.00</td><td></td><td></td><td>262</td><td>1044</td></th<>	Anna - Y					10.00			262	1044
Base If CVD 10 If CVD 10	Arapahoe			5610	26.10	1937			203	177%
Image: Control in the contro	Denver			6920	69 20	0.00	Net augmented		301.7	17%
	Bausen.		NNT	3490	34.90	0.00	Not augmented 12 AF withold for econort wells		173.8	20%
Classification lines: Classific		67 CW 56					indiana congrado	135 Ares Parcel B		
Classification lines: Classific							_			
Jarosh 7s 180 JJC Village CW 460 JT 4.1% 1/13 Usan 1/2	Total from Jaynes/Rheteric Parcel	L.				32.20				
Jarosh 7s 180 JJC Village CW 460 JT 4.1% 1/13 Usan 1/2			Off the Res V	Count Water S	anner filmed i					
Image: constraint of the sector of	Laramie Fox Hills	93-CW-018/85-CW-4451		42,700	427.00			Water purchased in First Tranchefrom Bar X		15%
Imagene JEL RELIGENCE AD AD INTO ADDRESS 100 ADDRE				12,500	125.00	41.67			1840 acres	
Bener 31 CW 4106 CW 40) 97 17 105 00 066 39 7 066 197 0 066 199 7 1000 199 7 West published for Stand Mark 1000 (2000) 199 7 West published for Stand Mark 1000 (2000) 199 7 1000 199 7 West published for Stand Mark 1000 (2000) 199 7 1000 199 7 West published for Stand Mark 1000 (2000) 199 7 1000 199 7	Arapahoe	93-CW-018/(85-CW-445)	NT	74250		247.50				17%
Junc JULY 11 (10 11 (10 11 (10 11 11 11 11 11 11 11 11 11 11 11 11 1										
Image: base in the second se	Berwer	93-CW-018/(85-CW-445)								17%
Interface Image: I	-		NT	-82167	-821.67	-273.89	Bet Set As ide for Sterling Iten	ch Post Pamping Depistions (20 CW3159)		
		93-04018	NNT					Need Augneritation Plan	490	20%
Base NT Acquise NT 64 C013 (C013) NT 1/2 (2,0)	Total Net Supply from Bar-X		Character	178,083 Wort Chrone f W	1780.83	593.61				
Base NT Acquise NT 64 C013 (C013) NT 1/2 (2,0)	Danson	85 C W131	NNT	49,800	498	0.00		Needs Auguentation		
Arg do 177 VI COURT	Denver NNT Denver NT						Special Warranty Beed	Needs Augmentation		
Tani Shamok Wart Image: Sh	Arapahoe NWT	85 C W131	NNT	2,500	25	0.00	Bur-X Sharmock West	Needs Augmentation		
OPEN-VICE VICE VICE VICE VICE VICE VICE VICE	Arap aboe NT	85 CW131	NT	47,400	474	158.00				
Larent-Ya Hill M169 30 Aregular M169 30 (M100) M7 M0 2000 26.00 M0 30 M0 M0 30 M0 M0 M0 30 M0 M0 M0 M0 30 M0 M0 M0 M0 M0 M0 M0 M0 M0 M0 M0 M0 M0 M	Total Shamrock West					220.3				
Aregular 1988 19 19 19 19 19 19 19 19 19 19 19 19 19										
Dence M31 8 B NT 518 8 S12 6 P10 6 900 3 sore 391.3 900 3 sore 301.01 900 3 sore 300 AF named 900		1689-BD	NT	26,300	263.00	87.67		900.52 acres		
Dence M31 8 B NT 518 8 S12 6 P10 6 900 3 sore 391.3 900 3 sore 301.01 900 3 sore 300 AF named 900	Arapahoe	1696-BD	NT	39800	398.80	132.67	Special Warranty Deel McCane	900.52 acres		
Card Med Supply Median Law 197.44 197.46 991.33 Constraints Const	Derver	1691-BD	NT	51300	513.00	171.00				
Conclusion Conclus	Total Net Supply McCune	1		117,400	1174.00	391.33		1500 AF Retained		
Mathematical Strate MT -4.2 Mathematical Strate MT -4.2 Mathematical Strate MT -2.95 MT -2.95 Mathematical Strate MT -2.95 MT -2.95 MT MT -2.95 MT -2.95 MT -2.95 MT MT -2.95 MT MT <td></td>										
Mathematical Strate MT -4.2 Mathematical Strate MT -4.2 Mathematical Strate MT -2.95 MT -2.95 Mathematical Strate MT -2.95 MT -2.95 MT MT -2.95 MT -2.95 MT -2.95 MT MT -2.95 MT MT <td>Laramie For Hills</td> <td>17 (2073)002</td> <td>74</td> <td>On-Site Retro 6,440</td> <td>et Water Leval Se</td> <td>arces (Hote 1)</td> <td></td> <td>Under 225 97 arrow</td> <td>190</td> <td>1%</td>	Laramie For Hills	17 (2073)002	74	On-Site Retro 6,440	et Water Leval Se	arces (Hote 1)		Under 225 97 arrow	190	1%
Litricitizioni di litricitizioni di litriciti d	LP H (Kelained wher by predescer in title)									
Augustantian Turni 1977 Difference 1978 No.	LFH (Relinquishment)	18 CW3002	NT	-2,796				PFD Auguenting 29 wells		
Appendix (result 10) Appendix					30.32					
Approprint Control (Control (Contro) (Contro) (Control (Control (Contro) (Control (Contro) (Contro	Ampahoe	17 CW3002	NT	9,796	97.96	32.65		Under 225.97 acres	255	17%
Approprint Control (Control (Contro) (Contro) (Control (Control (Contro) (Control (Contro) (Contro										
Approprint Control (Control (Contro) (Contro) (Control (Control (Contro) (Control (Contro) (Contro				12.020	120.30	42.76				
Augustatus (Dorea 1877) 1976-1976 Aug. 1973 1969 1973 1973 1973 1974 1975 1976 1976 1976 1976 1976 1976 1976 1976				11,828						
Augustatus (Dorea 1877) 1976-1976 Aug. 1973 1969 1973 1973 1973 1974 1975 1976 1976 1976 1976 1976 1976 1976 1976	August days (Louise 104T) Light Supply Chart		.524	22%	225	23.3	Part Saugh Family Bight	Stoby and ple of the ment		
Augustatus (Dorea 1877) 1976-1976 Aug. 1973 1969 1973 1973 1973 1974 1975 1976 1976 1976 1976 1976 1976 1976 1976	(each ling Lats 11.12) Lots 39 41 of Daves						Di Lui 2. Sta 11 d	- June of and second		
top Lings Report Trans 1 2011/2011/2011/2011/2011/2011/2011/201	mil Dissa 5					\$0}	Barolist of			
top Lings Report Trans 1 2011/2011/2011/2011/2011/2011/2011/201	Auga attain (Drana, NST)	N 442303E	Aur	1:957.5	ue	5.23		Styline + thildy-salar		
annen medit (1782 and 1982 Age Robert Angennen Germ (1977) and 2008 Age 2009 Other State (1972) Anne (1974) Age Providence (1974) Age Providence (1974)										
Auguntaniferenikiti adalah ng 200 10 00 00 00 00 00 00 00 00 00 00 00 0	Light Stoppic Chase 3	and Water Legel Status				\$23	(F769-1)			
	Augustan (Lower IBII)	1000 C	tor	316 D	2.63	(re)	Thuse to Las 11 \$100	Repholana, el Ma espeziolor		
	Lend Surger and La Co									
(() () () () () () () () () (Legel Supply Loss II & Li (26 ssc?)			280 6	24	17				

Note 1. The water listed in the batch of a rea will be used to serve single family wells and is not included in the Total Available for the Central System

Total Current 300-Year Water Supply (AF)



FAWWA Retreat Water Supplies

Bette st Wille provie wells net inclusied as it similation

Respec, Inc



The current water rights inventory by area is as follows:

1	Sterling original o	n-site non-tributary (NT) water rights	399.80 AF _{300 year}
1	02 CW 3059		283.16 AF _{300 year}
1	Retreat at Timber	Ridge on-site rights –	42.76 AF _{300 year}
1	Jaynes/Rhetoric (07 CW56; 23CW3009) –	32.20 AF _{300 year}
1	McCune	BD-1689, BD-1690, BD-1691	391.33 acre-feet 300 year
1	Bar-X Ranch	85CW-445 and 93 CW-018	592.78 acre-feet 300 year
1	Shamrock West	85 CW 131	220.10 acre-feet _{300 year}

FSAWWA-owned and currently available on-site NT and adjudicated not non-tributary (NNT) water totals are 1962.23 $AF_{300 year}$, which would be adequate supply to meet the needs of roughly 5,500SFE.

As of this report September 11, 2024, the total water commitment within FAWWA requires **1033.87** $AF_{300 year}$. See Appendix F – FAWWA detailed Water Supply vs Current Water Commitments.

This leaves a net excess of currently available water of 928.36 $AF_{300 year}$ and therefore there is more than sufficient water supply to meet the needs of Retreat at PrairieRidge Filings 1-3 Preliminary Plan on the 300-year basis.

3.3 MASTER PLANNING AND LONG-TERM AND FUTURE SOURCES OF SUPPLY

The FAWWA water system has only been in operation forfiveyears, so little-to-no usable historic information would be reliable for unique, long-term planning. However, substantial nearby data from the Falcon area is available for use. As of the end of 2023, the system had approximately only 500 active users. Therefore, initial projections have been based on area-wide water user characteristics and a linear buildout rate. This rate is considered to be an average annual rate that might be reasonably maintainable over a 10-year period. The average growth rate is projected as 180 units added per year.

- / 2040 Scenario: Based on the above factors, the FAWWA system might conservatively anticipate serving 3,710 SFEs in the year 2040. This number is a FAWWA service area projection. This would require no additional water.
- / 2060 Scenario: Based on the same factors, the FAWWA system might be expected to serve 7,310 SFEs within its expanded service area, which includes all service area components.. This would be substantially greater than the actual Sterling Ranch. The annual acre-foot requirement might be 640 annual AF, but supply would include water from The Ranch which has not yet been added to inventory.

In addition to adding off-site sources, potential, additional supplies include renewable resources and/or regional projects bringing new water to the area



Long-Term Planning: Future water supply has already been contracted for and plans for implementation are underway. The first project recently completed provides augmentation for certain on-site NNT water, so that that water may be used in existing and expanded well fields on-site.

1. **Regionalization Opportunities:** FAWWA's main supply source is centralized at a point that both Cherokee Metropolitan District and Woodmen Hills Metropolitan District have adjacent major storage and delivery facilities. There are currently no arrangements in place to make connections, but in the future, FAWWA may seek to have interconnections and possibly share supply.

The second element is a much broader regionalization: conducting cooperative actions with Colorado Springs Utilities (CSU), which FAWWA has been open to. CSU is potentially also open to shared physical facility utilization, which would enable Sterling to expand its scope in seeking water rights. While it is not expected that Sterling will provide actual water, the access to facilities opens greater doors for FAWWA.

2. Indirect, Reuse, Lawn Irrigation Return Flows (LIRF) Credits, Aquifer Storage/Recharge, and Direct Reuse: Regarding return flows, initial development is being planned around sourcing available physical supplies. These supplies are all fully-consumable and ultimately result in potential return-flow capabilities. Since FAWWA wastewater is discharged to the Meridian system, which in turn has the potential to convert some reusable flows to available physical supplies, those options will be available and considered by Sterling. With regard to LIRF credits, Sterling has already initiated a case that will make augmentation use of its potential LIRF credits.

3.4 SYSTEM INTERCONNECTS

FAWWA currently has no system interconnections. However, as discussed previously, FAWWA's main supply source is centralized at a point that both Cherokee Metropolitan District and Woodmen Hills Metropolitan District have adjacent major storage and delivery facilities. It is possible that future agreements could be made.

3.5 SOURCE OF PHYSICAL SUPPLY

Municipal water demand would be met using primarily Arapahoe and Laramie-Fox Hills formation wells in the FAWWA area. Two on-site wells are active and three more have been completed, awaiting equipping. Existing well permits are included in **Appendix D**.

FAWWA has begun the process of filing to drill the first set of wells on the McCune site which will possibly be needed in 2027.

Off-site water to the north of the FAWWA service area is generally in the Denver and Arapahoe formations.



3.6 WATER QUALITY AND TREATMENT

Appendix E contains the water quality reports for the initial wells drilled at FAWWA. The quality is generally consistent with Denver Basin water typically encountered in the Falcon area. The quality of water in these aquifers in this area has typically been suitable for potable use with the addition of iron and manganese treatment.

3.7 WATER STORAGE, DISTRIBUTION, AND TRANSMISSION LINES

An initial 1.0-million-gallon tank has already been constructed at the FAWWA site.

For the purpose of fire protection, we recommend eight-inch lines throughout the residential subdivision. The lines should be looped wherever the street layout allows. A transmission line of 24-inches in diameter has been extended south-southwesterly along one of the major roadways from the storage tank into Phase One of the development.

3.8 PUMPING FOR SERVICE PRESSURES

Ground elevations within the development service area range from approximately 6,970 feet to 7,320 feet. Adequate service pressures are generally considered 60 psi for residential service. The tank site is on the Sterling property at a base elevation of approximately 7,310 feet, which would be capable of supplying acceptable service pressures to ground elevations of approximately 7,190 feet. Initial development is anticipated to be at elevations below 7,190 feet, so the tank site will be able to provide adequate pressure.


Development construction has progressed such that the pressure system is likely to be needed sometime in 2023, FAWWA is currently constructing the pressure pump station so that it will be ready when needed next year.

APPENDIX A WATER SERVICE AREAS





RESPEC.COM



APPENDIX B

PRAIRIERIDGE FILING 1 Preliminary plan





RESPEC.COM

GENERAL NOTES:

- 1. ALL SIDEWALKS SHOWN ON PRELIMINARY PLAN ARE TO BE 5' CONCRETE UNLESS OTHERWISE SPECIFIED.
- 2. ALL TRAILS TO BE NON-MOTORIZED TRAILS.
- 3. TRAILS LABELED AS "COUNTY REGIONAL TRAIL" WILL BE MAINTAINED BY EL PASO COUNTY
- 4. LANDSCAPING IN PUBLIC-RIGHTS-OF-WAY WILL BE MAINTAINED BY PRAIRIERIDGE METROPOLITAN DISTRICT.
- 5. DEVELOPER SHALL ANALYZE THE NEED TO PROVIDE ALL NECESSARY OFFSITE ROAD IMPROVEMENTS, WHICH MAY INCLUDE IMPROVEMENTS IN THE CITY OF COLORADO SPRINGS, TO PROVIDE AN APPROPRIATE LEVEL OF SERVICE TO THIS DEVELOPMENT. IF OFFSITE ROAD IMPROVEMENTS ARE NECESSARY, THEY WILL BE SPECIFICALLY OUTLINED PER A SUBDIVISION IMPROVEMENTS AGREEMENT OR DEVELOPMENT AGREEMENT BETWEEN DEVELOPER AND EL PASO COUNTY.
- 6. ALL STREETS SHALL BE NAMED AND CONSTRUCTED TO EL PASO COUNTY STANDARDS AND ANY APPROVED DEVIATION. UPON ACCEPTANCE EL PASO COUNTY, PUBLIC STREETS SHALL BE MAINTAINED BY THE COUNTY.
- 7. NOTWITHSTANDING ANYTHING DEPICTED IN THIS PLAN IN WORDS OR GRAPHIC REPRESENTATION, ALL DESIGN AND CONSTRUCTION RELATED TO ROADS, STORM DRAINAGE AND EROSION CONTROL SHALL CONFORM TO THE STANDARDS AND REQUIREMENTS OF THE MOST RECENT VERSION OF THE RELEVANT ADOPTED EL PASO COUNTY STANDARDS, INCLUDING THE LAND DEVELOPMENT CODE (LDC), THE ECM, THE DRAINAGE CRITERIA MANUAL (DCM), AND THE DCM VOLUME 2. ANY DEVIATIONS FROM THESE STANDARDS MUST BE SPECIFICALLY REQUESTED AND APPROVED IN WRITING TO BE ACCEPTABLE. THE APPROVAL OF THIS PRELIMINARY PLAN DOES NOT IMPLICITLY ALLOW ANY DEVIATIONS OR WAIVERS THAT HAVE NOT BEEN OTHERWISE APPROVED THROUGH THE DEVIATION APPROVAL PROCESS.
- 8. THE SUBDIVIDER(S) AGREE ON BEHALF OF HIM/HERSELF AND ANY DEVELOPER OR BUILDER SUCCESSORS AND ASSIGNEES THAT SUBDIVIDER AND/OR SAID SUCCESSORS AND ASSIGNS SHALL BE REQUIRED TO PAY TRAFFIC IMPACT FEES IN ACCORDANCE WITH THE EL PASO COUNTY ROAD IMPACT FEE PROGRAM RESOLUTIONS (RESOLUTION NO.19-471), OR ANY AMENDMENTS THERETO, AT OR PRIOR TO THE TIME OF BUILDING PERMIT SUBMITTALS. THE FEE OBLIGATION, IF NOT PAID AT FINAL PLAT RECORDING, SHALL BE DOCUMENTED ON ALL SALES DOCUMENTS AND ON PLAT NOTES TO ENSURE THAT A TITLE SEARCH WOULD FIND THE FEE OBLIGATION BEFORE SALE OF THE PROPERTY.
- 9. THE FOLLOWING UTILITY PROVIDERS WILL SERVE RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN AREA INSTALLED BY THE DEVELOPER: WATER: FAWWA (EXCEPT THE 2.5 AC. LOTS ACCESSING POCO ROAD - INDIVIDUAL WELLS BY LOT OWNER) WASTEWATER: FAWWA (EXCEPT THE 2.5 AC. LOTS ACCESSING POCO ROAD - INDIVIDUAL SEPTIC SYSTEMS BY LOT OWNER) GAS: COLORADO SPRINGS UTILITIES GAS (EXCEPT THE 2.5 AC. LOTS ACCESSING POCO ROAD - GAS SERVICE BY BLACK HILLS ENERGY) ELECTRIC: MOUNTAIN VIEW ELECTRIC ASSOCIATION, INC.
- 10. THE FOLLOWING REPORTS HAVE BEEN SUBMITTED IN ASSOCIATION WITH THE PRELIMINARY PLAN FOR THIS SUBDIVISION AND ARE ON FILE AT THE COUNTY PLANNING AND COMMUNITY DEVELOPMENT DEPARTMENT: TRANSPORTATION IMPACT STUDY: DRAINAGE REPORT: WATER RESOURCES REPORT: WASTEWATER DISPOSAL REPORT; GEOLOGY AND SOILS REPORT; FIRE PROTECTION REPORT; WILDFIRE HAZARD REPORT; NATURAL FEATURES REPORT
- 11. DEVELOPER SHALL COMPLY WITH FEDERAL AND STATE LAWS, REGULATION, ORDINANCES, REVIEW AND PERMIT REQUIREMENTS, AND OTHER AGENCY REQUIREMENTS, IF ANY, OF APPLICABLE AGENCIES INCLUDING, BUT NOT LIMITED TO, THE COLORADO PARKS AND WILDLIFE, COLORADO DEPARTMENT OF TRANSPORTATION, U.S. ARMY CORPS OF ENGINEERS AND THE U.S. FISH AND WILDLIFE SERVICE REGARDING THE ENDANGERED SPECIES ACT, PARTICULARLY AS IT RELATES TO THE LISTED SPECIES (E.G., PREBLE'S MEADOW JUMPING MOUSE).
- 12. THE DISTRICT WILL BUILD AND MAINTAIN A NOISE WALL ALONG LOTS ADJACENT TO BRIARGATE PARKWAY AND VOLLMER ROAD OR REAR LOT LINE OF THE LOTS AS INDICATED ON THE PRELIMINARY PLAN. SUCH NOISE WALL IS TO BE CONSTRUCTED BY THE DEVELOPER. A DETAIL OF THE PROPOSED CONCRETE WALL IS ON ATTACHED LANDSCAPE PLAN.
- 13. THE PARTIES RESPONSIBLE FOR THIS PLAN HAVE FAMILIARIZED THEMSELVES WITH ALL CURRENT ACCESSIBILITY CRITERIA AND SPECIFICATIONS AND THE PROPOSED PLAN REFLECTS ALL SITE ELEMENTS REQUIRED BY THE APPLICABLE ADA DESIGN STANDARDS AND GUIDELINES AS PUBLISHED BY THE UNITED STATES DEPARTMENT OF JUSTICE. APPROVAL OF THIS PLAN BY EL PASO COUNTY DOES NOT ASSURE COMPLIANCE WITH THE ADA OR ANY REGULATIONS OR GUIDELINES ENACTED OR PROMULGATED UNDER OR WITH RESPECT TO SUCH LAWS.
- 14. UNLESS OTHERWISE INDICATED, ALL LOTS HAVE THE FOLLOWING EASEMENTS, 7' REAR PUBLIC UTILITY AND DRAINAGE EASEMENT, 5' SIDE PUBLIC EASEMENTS, 5' FRONT PUBLIC UTILITY AND PUBLIC IMPROVEMENT EASEMENT, AND ADDITIONAL 10' FRONT PUBLIC UTILITY EASEMENT. THE SOLE RESPONSIBILITY FOR MAINTENANCE OF THE THESE EASEMENTS IS HEREBY VESTED WITH THE INDIVIDUAL PROPERTY OWNERS.
- 15. THERE SHALL BE NO DIRECT LOT ACCESS TO BRIARGATE PARKWAY, DINES BOULEVARD, OR VOLLMER ROAD FOR ANY RESIDENTIAL LOTS.
- 16. SOILS AND GEOLOGY CONDITIONS: GEOLOGIC HAZARD AREAS AND MITIGATION MEASURES CAN BE FOUND IN THE REPORT ("SOILS AND GEOLOGY STUDY FOR RETREAT AT PRAIRIERIDGE FILINGS 1. 2 AND 3 - PRELIMINARY PLAN. POCO ROAD AND VOLLMER ROAD" PREPARED BY ENTECH ENGINEERING, INC., DATED APRIL 2, 2024) IN FILE NUMBER SP239 AVAILABLE AT THE EL PASO COUNTY PLANNING & COMMUNITY DEVELOPMENT DEPARTMENT.
- ~ POTENTIAL SEASONALLY SHALLOW GROUNDWATER (psw) \sim SEASONALLY WET AREA (sw)
- ~ AREAS OF PONDED/FLOWING WATER (w)
- SEE SHEET 28 FOR GEOLOGIC CONSTRAINTS MAP AND LOTS AFFECTED. FURTHER STUDY TO DETERMINE MITIGATION WILL BE REQUIRED AT FINAL PLAT. IN AREAS OF HIGH GROUNDWATER:
- DUE TO HIGH GROUNDWATER IN AREAS, ALL FOUNDATIONS SHALL INCORPORATE AND UNDERGROUND DRAINAGE SYSTEM. UNDER DRAIN SYSTEM TO BE MAINTAINED BY THE PRAIRIERIDGE METRO DISTRICT.
- 17. EL PASO COUNTY DOES NOT OWN AND IS NOT RESPONSIBLE FOR ANY UNDERDRAINS OR GROUNDWATER DISCHARGE SYSTEMS SHOWN ON THESE PLANS AND ASSUMES NO LIABILITY FOR WATER RIGHTS ADMINISTRATION BY APPROVING THESE PLANS. MAINTENANCE AND WATER RIGHTS ARE THE RESPONSIBILITY OF THE DEVELOPER AND THE PRAIRIERIDGE METRO DISTRICT.
- 18. THE PHASING/FILING LINES SHOWN ON THIS PLAN MAY NOT REFLECT THE EXACT SEQUENCE OF DEVELOPMENT. FILING SIZE AND DEVELOPMENT TIMING ARE MARKET DRIVEN AND WE REQUEST THIS FLEXIBILITY WITH NO FUTURE PLAN AMENDMENTS REQUIRED. 19. NO PROPOSED SCHOOL SITES PROPOSED WITHIN THIS PROPERTY. NO EXISTING FIRE HYDRANTS OR CISTERNS CURRENTLY EXIST ON THE PROPERTY.

	TRACT	AREA (SF)	AREA (AC.)	USE	OWNERSHIP/MAINTENANCE
LING 1	A	271,397	6.23	DETENTION POND, TRAILS, UTILTIES, BUFFER	PRAIRIERIDGE METRO DISTRICT 1
	В	115,247	2.65	PARK, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	С	19,875	0.46	OPEN SPACE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	D	577,481	13.26	FUTURE DEVELOPMENT TRACT	CLASSIC SRJ LAND, LLC
LING 2	A	28,260	0.65	OPEN SPACE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	В	14,407	0.33	OPEN SPACE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	С	19,596	0.45	OPEN SPACE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	D	64,101	1.47	OPEN SPACE, BUFFER LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	E	12,433	0.29	OPEN SPACE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	F	12,831	0.29	PARK, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	G	10,260	0.24	PARK, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	н	12,298	0.28	DRAINAGE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	I	12,886	0.30	DRAINAGE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	J	14,296	0.33	DRAINAGE, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	к	240.599	5.52	PARK, BUFFER, LANDSCAPE, UTILITIES	PRAIRIERIDGE METRO DISTRICT 1
	L	870,112	19.97	FUTURE DEVELOPMENT TRACT	CLASSIC SRJ LAND, LLC

TRACT TABLE

FIL


FI

RETREAT AT PRAIRIERIDGE FILINGS 1-3

A PORTION OF THE SOUTHWEST QUARTER OF SECTION 28 AND THE NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASO COUNTY, STATE OF COLORADO

PRELIMINARY PLAN

MARCH 2024



PROJECT TEAM

OWNER/DEVELOPER:

APPLICANT/CIVIL CONSULTANT:

LANDSCAPE CONSULTANT:

LANDSCAPE CONSULTANT:


COLORADO SPRINGS, CO 80921 (719) 592–9333 MR. LOREN MORELAND

CLASSIC SRJ LAND, LLC

CLASSIC CONSULTING 619 N. CASCADE AVE. SUITE 200 COLORADO SPRINGS, CO 80903 (719) 785–2802 MR. MARC A. WHORTON, P.E.

NES 619 N. CASCADE AVE. SUITE 200 COLORADO SPRINGS, CO 80903 (719) 471–0073 MR. BLAINE PERKINS

SUNFLOWER LANDSCAPES 1925 AEROPLAZA DRIVE COLORADO SPRINGS, CO 80916 (719) 637–0313 MR. MIKE BERTA



2138 FLYING HORSE CLUB DR.

SITE DATA

TAX ID NUMBERS: TOTAL AREA: DEVELOPMENT SCHEDULE SKETCH PLAN: CURRENT ZONING: PROPOSED ZONING:

CURRENT USE:

PROPOSED USE:

LANDSCAPE SETBACKS: VOLLMER ROAD: BRIARGATE PKWY:

<u>FILING 1</u> PROPOSED GROSS DENSITY: PROPOSED NET DENSITY:

FILING 2 PROPOSED GROSS DENSITY: PROPOSED NET DENSITY:

FILING 3 PROPOSED GROSS/NET DENSITY:

TOTAL PROPOSED GROSS DENSITY: PROPOSED NET DENSITY:

PORTION OF 52280-00-024 & 52280-00-025 142.13 ACRES FALL 2024 SKP225 RS-6000, RR-2.5, & RR-0.5 (FUTURE DEVELOPMENT TRACTS TO BE REZONED AT A LATER DATE) AGRICULTURE GRAZING/VACANT

SINGLE FAMILY RESIDENTIAL (DETACHED)

50 FT BUFFER 25 FT BUFFER

1.47 DU/AC (46 LOTS/31.24 AC) 3.97 DU/AC (46 LOTS/11.58 AC) (DENSITIES DO NOT INCLUDE FUTURE DEVELOPMENT TRACT AREA)

2.36 DU/AC (141 LOTS/59.76 AC) 3.68 DU/AC (141 LOTS/38.36 AC) (DENSITIES DO NOT INCLUDE FUTURE DEVELOPMENT TRACT AREA)

0.35 DU/AC (6 LOTS/17.02 AC) (2.5 AC. RURAL LOTS ACCESS FROM EXISTING POCO ROAD)

1.77 DU/AC (193 LOTS/108.93 AC) 2.84 DU/AC (193 LOTS/67.87 AC) (DENSITIES DO NOT INCLUDE FUTURE DEVELOPMENT TRACT AREA)

ZONE DIMENSIONAL STANDARDS

ZONE	MIN. LOT SIZE	MAX. BUILDING HEIGHT	MAX. LOT COVERAGE	MIN. LOT WIDTH AT FRONT SETBACK LINE	FRONT BUILDING SETBACK	SIDE BUILDING SETBACK	REAR BUILDING SETBACK
RS-6000	6,000 SF	30'	40%/45%	50'	25'	5'	25'
RR-2.5	2.5 ACRES	30'	NONE	200'	25'	15'	25'
RR-0.5	21,780 SF	30'	NONE	100'	25'	10'	25'

LAND USE DATA TABLE


LAND USE	ACRES	% OF LAND
SINGLE FAMILY (DETACHED) LOTS	66.96	47.2%
PUBLIC ROAD RIGHT-OF-WAY	22.45	15.8%
PARKS	8.70	6.1%
OPEN SPACE/BUFFER TRACTS	3.65	2.6%
DRAINAGE/DETENTION	7.14	5.0%
FUTURE DEVELOPMENT TRACTS	33.23	23.3%
TOTAL	142.13	100.0%

SHEET INDEX:

COVER SHEET	SHEET 1 OF 28
LEGAL BOUNDARY & ADJACENT OWNERS EXHIBIT	SHEET 2 OF 28
PRELIMINARY PLAN	SHEET 3 OF 28
PRELIMINARY PLAN	SHEET 4 OF 28
PRELIMINARY PLAN	SHEET 5 OF 28
PRELIMINARY PLAN	SHEET 6 OF 28
PRELIMINARY PLAN	SHEET 7 OF 28
PRELIMINARY PLAN	SHEET 8 OF 28
PRELIMINARY GRADING & UTILITY PLAN	SHEET 9 OF 28
PRELIMINARY GRADING & UTILITY PLAN	SHEET 10 OF 28
PRELIMINARY GRADING & UTILITY PLAN	SHEET 11 OF 28
PRELIMINARY GRADING & UTILITY PLAN	SHEET 12 OF 28
PRELIMINARY GRADING & UTILITY PLAN	SHEET 13 OF 28
PRELIMINARY GRADING & UTILITY PLAN	SHEET 14 OF 28
PRELIMINARY ROUND-ABOUT DESIGN	SHEET 14A OF 28
PRELIMINARY LANDSCAPE PLANS & DETAILS	SHEETS 15-27 OF 28
GEOLOGIC CONSTRAINTS EXHIBIT	SHEET 28 OF 28

PCD NO. SP239

CLASSIC.	RETREAT AT PRELIMINAR TITLE SHEET		RIERIDGE FILIN	IGS 1–3	$\frac{4}{CLASSIC}$
CONSULTING	DESIGNED BY	MAW	SCALE	DATE	5/29/2024
	DRAWN BY	MAW	(H) 1"= N/A	SHEET	1 OF 28
619 N. Cascade Avenue, Suite 200 (719)785—0790 Colorado Springs, Colorado 80903 (719)785—0799 (Fax)	CHECKED BY		(V) 1"= N/A	JOB NO.	1305.10



THE NORTHWEST

A PARCEL OF LAND BEING LOCATED IN A PORTION OF THE SOUTH HALF OF SECTION 28 AND THE NORTHWEST QUARTER OF SECTION 33, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO, BEING ALSO A PORTION OF LAND SURVEY PLAT RECORDED UNDER RECEPTION NO. 211900027, BEING MORE PARTICULARLY DESCRIBED AS

BASIS OF BEARINGS: THE SOUTH LINE OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SECTION 28, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, BEING MONUMENTED AT THE WEST END WHICH IS THE SOUTHWEST CORNER OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 28, BY A 3-1/4" ALUMINUM SURVEYORS CAP STAMPED "ESI PLS 10376, 2006" AND AT THE EAST END, WHICH IS A 30' WITNESS CORNER TO THE EAST OF THE EAST QUARTER CORNER OF SAID SECTION 28, BY A 3-1/4" ALUMINUM SURVEYORS CAP STAMPED "ESI 10376, 2006", IS ASSUMED TO BEAR N89°08°28"E, A DISTANCE OF

COMMENCING AT THE CENTER-EAST 1/16 CORNER OF SAID SECTION 28, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO;

THENCE \$83°37'56"W, A DISTANCE OF 62.10 FEET TO A POINT ON THE NORTH LINE OF THE SOUTH HALF OF SECTION 28 SAID POINT BEING THE NORTHEASTERLY CORNER OF LAND SURVEY PLAT RECORDED UNDER RECEPTION NO. 211900027 SAID POINT BEING ALSO IN THE WESTERLY RIGHT OF WAY LINE OF VOLLMER ROAD AND BEING THE POINT OF BEGINNING

THENCE ON SAID WESTERLY RIGHT OF WAY LINE THE FOLLOWING FOUR (4) COURSES:

- 3. THENCE ON THE ARC OF A CURVE TO THE RIGHT WHOSE CENTER BEARS N78°41'41"W, HAVING A DELTA OF 27°06'29", A RADIUS OF 603.83 FEET AND A DISTANCE OF 285.69 FEET;
- 5. THENCE S39°06'28"W, A DISTANCE OF 376.53 FEET;
- 6. THENCE S40°36'08"W, A DISTANCE OF 1,729.38 FEET TO A POINT ON THE WEST LINE OF THE EAST HALF OF THE NORTHWEST QUARTER OF SAID SECTION 33;

THENCE N00°07'28"W, ON SAID WEST LINE, A DISTANCE OF 1,440.85 FEET TO A POINT ON THE WEST LINE OF THE EAST HALF OF THE SOUTHWEST QUARTER OF SAID SECTION 28; THENCE N00°16'33"W, ON SAID WEST LINE, A DISTANCE OF 2,611.38 FEET TO A POINT ON THE NORTH LINE OF THE SOUTH HALF OF SECTION 28; THENCE N89°13'54"E, ON SAID NORTH LINE, A DISTANCE OF 717.48 FEET TO THE EXTERIOR

THENCE ON THE SAID EXTERIOR BOUNDARY THE FOLLOWING THREE (3) COURSES:

- 3. THENCE N00°46'54"W, A DISTANCE OF 544.39 FEET TO A POINT OF SAID NORTH LINE;

THENCE N89°13'54"E, A DISTANCE OF 1,457.61 FEET TO THE POINT OF BEGINNING.


THE DESCRIPTION ABOVE PRODUCES A CALCULATED AREA OF 6,191,054 SQUARE FEET, (142.12705 ACRES) OF LAND MORE OR LESS AND IS DEPICTED ON THE ATTACHED GRAPHICAL EXHIBIT FOR

CITY STATE ZIP
COLORADO SPRINGS, CO 80903
COLORADO SPRINGS, CO 80908
COLORADO SPRINGS, CO 80962
COLORADO SPRINGS, CO 80923
COLORADO SPRINGS, CO 80921
COLORADO SPRINGS, CO 80920
COLORADO SPRINGS, CO 80908
COLORADO SPRINGS, CO 80908
COLORADO SPRINGS, CO 80908
COLORADO SPRINGS, CO 80903


RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN EGAL BOUNDARY MAP AND


ADJACENT OWNERS LIST


DESIGNED BY	MAW	SCALE	DATE 5	5/29/2024
DRAWN BY	MAW	(H) 1"= N/A	SHEET 2	OF 28
CHECKED BY		(V) 1"= N/A	JOB NO.	1305.10



A PORTION OF








SHEET INDEX N.T.S.


EASEMENT NOTES


- 1. ALL LOTS WITHIN FILING 2 (RS-6000 ZONE) WILL HAVE THE FOLLOWING ESMTS. AS SHOWN UNLESS OTHERWISE NOTED:
- 5' SIDE YARD PUBLIC UTIL./ DRAINAGE ESMT. 5' FRONT PUBLIC IMP. ESMT. 15' FRONT PUBLIC UTIL. ESMT. 7' REAR YARD PUBLIC UTIL./ DRAINAGE ESMT.
- 2. ALL LOTS WITHIN FILING 3 (RR-2.5 ZONE) WILL HAVE ESMTS. AS SHOWN AND LABELED.



SCALE: 1" = 60'U.S. SURVEY FOOT

CLASSIC.	RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN FILING 2 & 3					<u>CLASSIC</u>	CONSULTING
CONSULTING	DESIGNED BY	MAW	SCALE	DATE	5/	29/20	324
	DRAWN BY	MAW	(H) 1"= 60'	SHEET	4	OF	28
619 N. Cascade Avenue, Suite 200 (719)785—0790 Colorado Springs, Colorado 80903 (719)785—0799 (Fax)	CHECKED BY		(V) 1"= N/A	JOB NO.	1	305.1	0






SHEET INDEX N.T.S.


EASEMENT NOTES

1. ALL LOTS WITHIN FILING 2 (RS-6000 ZONE) WILL HAVE THE FOLLOWING ESMTS. AS SHOWN UNLESS OTHERWISE NOTED:


> 5' SIDE YARD PUBLIC UTIL./ DRAINAGE ESMT. 5' FRONT PUBLIC IMP. ESMT. 15' FRONT PUBLIC UTIL. ESMT 7' REAR YARD PUBLIC UTIL./ DRAINAGE ESMT.




SCALE: 1'' = 60'U.S. SURVEY FOOT



A PORTION OF






RETREAT AT PRAIRIERIDGE FILINGS 1-3


THE SOUTHWEST QUARTER OF SECTION 28 THE NORTHWEST QUARTER OF SECTION 33, AND TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASO COUNTY, STATE OF COLORADO


PRELIMINARY PLAN


SHEET

SHEET :









SHEET INDEX N.T.S.


EASEMENT NOTES

1. ALL LOTS WITHIN FILING 1 (RS-6000 ZONE) WILL HAVE THE FOLLOWING ESMTS. AS SHOWN UNLESS OTHERWISE NOTED:


5' SIDE YARD PUBLIC UTIL./ DRAINAGE ESMT. 5' FRONT PUBLIC IMP. ESMT. 15' FRONT PUBLIC UTIL. ESMT 7' REAR YARD PUBLIC UTIL./ DRAINAGE ESMT.

2. LOT 7 (RR-0.5 ZONE) HAS THE FOLLOWING ESMTS. AS SHOWN:

10' SIDE YARD PUBLIC UTIL./ DRAINAGE ESMT. 5' FRONT PUBLIC IMP. ESMT. 15' FRONT PUBLIC UTIL. ESMT. 10' REAR YARD PUBLIC UTIL./ DRAINAGE ESMT.



SCALE: 1" = 60' U.S. SURVEY FOOT





APPENDIX C

WATER RIGHTS DECREES





RESPEC.COM

Appendix C Listing of Decrees/Determinations/Deeds in Appendix

Decrees/Determinations

Deeds

07 CW 56 08 CW 113 86 CW 18 86 CW 19 17 CW 3002	QCD Jaynes /CSRJL to FAWWA FAWWA Assignment FAWWA Assignment FAWWA Assignment
18 CW 3002 20 CW 3059 91 CW 35	FAWWA Assignment Classic SRJ Deed
93 CW 018	Deed for first traunche Bar-X
93 CW 010	Special Warranty Deed Bar-X Shamrock West
85 CW 445	Special Warranty Deed Bar-X Shamrock West
85 CW 131	Special Warranty Deed Bar-X Shamrock West
1689 BD 1690 BD 1691 BD	Special Warranty Deed McCune Special Warranty Deed McCune Special Warranty Deed McCune
23 CW 3009 CW 3007 (Pending)	In FAWWA Name In FAWWA Name

24 CW 3007 (Pending)

STATE OF COLORADO

OFFICE OF THE STATE ENGINEER Division of Water Resources Department of Natural Resources

1313 Sherman Street, Room 818 Denver, Colorado 80203 Phone (303) 866-3581 FAX (303) 866-3589

http://www.water.state.co.us

EFILED Document – District Court 2007CW56 CO Pueblo County District Court Unit Filing Date: Sep 24 2007 3:39PM MDT Filing ID: 16424421 Review Clerk: Mardell Didometiconter, Jr. Governor

September 24, 2007

Harris D. Sherman Executive Director

(Vacant) State Engineer

Clerk, Division 2 Water Court 203 Judicial Bldg. 320 W. 10th Street Pueblo, CO 81003

RE: Case No. 07CW56, Aimee Jaynes Living Trust and John Jaynes

Enclosed are the Determination of Facts Reports of the State Engineer concerning the referenced water court application for determination of rights to ground water. These reports are submitted pursuant to CRS 37-92-302(2)(a).

Sincerely Don West

Water Resources Engineer

cc: Division 2 Applicant's Attorney

OFFICE OF THE STATE ENGINEER DETERMINATION OF FACTS

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND WATER RIGHTS IN WATER DIVISION NO. 2, EL PASO COUNTY, COLORADO

CASE NO.: 07CW56

APPLICANT: AIMEE JAYNES LIVING TRUST AND JOHN JAYNES

AQUIFER : DAWSON

In compliance with C.R.S. 37-92-302(2), Aimee Jaynes Living Trust and John Jaynes, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on May 31, 2007.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 135 acres of land as further described in said application.
- 3. The quantity of water in the Dawson Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 135 acres of land claimed in the application is 4692 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 20 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 173.8 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(l) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. The applicant proposes to exclude from decree in this case 12.0 acre-feet of the allowed average annual amount of water available in the aquifer from beneath the overlying land to allow for the excluded water's withdrawal by proposed exempt wells. Under administration of a 100-year aquifer life, 1,200 acre-feet of water should be excluded from this decree to provide for reservation of such water for the proposed exempt wells.
- 6. To ensure that the exempt wells will be limited to the 12 acre-feet per year of availability, and allow administration of both this decree and the proposed exempt wells, the decree shall impose the following conditions on the issuance of the exempt well permits.

Case No.: 07CW56

Applicant: Aimee Jaynes Living Trust and John Jaynes Aquifer: Dawson

- All permits must be issued pursuant to C.R.S. 37-92-602(3)(b)(II)(A), under a presumption of no injury. No permits may be issued pursuant to C.R.S. 37-92-602(3)(b)(I).
- b. Each permit must be issued as the only well on an identified tract of land.
- c. No exempt well may be located on any subdivision of land as defined by C.R.S. 30-28-101(10), whether such subdivision occurs before or after issuance of an exempt permit. Should the tract on which an exempt well is located be subdivided subsequent to issuance of the exempt permit, that permit shall become invalid and the well must either be plugged or re-permitted as a non-exempt well pursuant to this decree.
- d. The decree must identify the number of exempt wells that will be applied for on the 135 acres of overlying land that is the subject of this application, and the annual withdrawal that each well will be limited to, with a cumulative annual withdrawal by all wells not to exceed 12 acre-feet. Should any wells serve lots in a cluster development, those wells must be limited to diversions at a ratio not to exceed one acre-foot of annual withdrawals for each thirty-five acres within the cluster development.
- e. All well permit applications must reference this case, and contain a requested annual withdrawal consistent with the amount identified by the applicant in item D above.
- f. All permits must contain an annual withdrawal limitation.
- g. The cumulative sum of annual withdrawals by all exempt wells withdrawing the reserved water shall not exceed 12 acre-feet.
- h. Applicant shall be placed on notice that the NE1/4, SW1/4, Sec. 28, T12S, R65W, 6th PM is currently encumbered by exempt well permit 131621, and no other exempt well permits may be issued in that 40 acres unless that permit is cancelled.
- 7. The quantity of water in the aquifer underlying the lands claimed in the application that may be decreed is 3492 acre-feet (the quantity of water in the aquifer underlying the land claimed in the application less 1,200 acre-feet), and the allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 34.9 acre-feet (the quantity of water which is considered available for decree divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of these amounts.
- 8. Withdrawal of ground water from the aquifer underlying the land claimed in the application will within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is <u>not</u> nontributary ground water as defined in C.R.S. 37-90-103(10.5). C.R.S. 37-90-137(9)(c) states that judicial approval of a plan for augmentation shall be required prior to use of ground water of the type sought in this application. In the case of the Dawson aquifer such augmentation plans shall provide for the replacement of actual stream depletions to the extent necessary to prevent any injurious effect, based on actual aquifer conditions in existence at the time of the decree.
- 9. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 34.9 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.

Case No.: 07CW56 Applicant: Aimee Jaynes Living Trust and John Jaynes Aquifer: Dawson

Underlying the land claimed in the application, the base of the aquifer is, as specified in 10. the Denver Basin Rules, located to a depth of approximately 402 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this 24 TH day of September 2007. Sieh Wolh

Dick Wolfe

By

Don West Water Resources Engineer

State Engineer

Prepared by: DDW

OFFICE OF THE STATE ENGINEER DETERMINATION OF FACTS

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND WATER RIGHTS IN WATER DIVISION NO. 2, EL PASO COUNTY, COLORADO

CASE NO.: 07CW56

APPLICANT: AIMEE JAYNES LIVING TRUST AND JOHN JAYNES

AQUIFER : DENVER

In compliance with C.R.S. 37-92-302(2), Aimee Jaynes Living Trust and John Jaynes, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on May 31, 2007.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 135 acres of land as further described in said application.
- 3. The quantity of water in the Denver Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 135 acres of land claimed in the application is 6924 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 17 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 301.7 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has not disclosed that there are any existing wells or other water rights claiming or diverting ground water from the aquifer underlying the land claimed by the applicant.
- 6. Withdrawal of ground water from the aquifer underlying the land claimed in the application will, within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is <u>not</u> nontributary ground water as defined in C.R.S. 37-90-103(10.5). The land is more than one mile from any point of contact between any natural surface stream, including its alluvium, and the aquifer. C.R.S. 37-90-137(9)(c) states that judicial approval

Case No.: 07CW56 Applicant: Aimee Jaynes Living Trust and John Jaynes Aquifer: Denver

of a plan for augmentation shall be required prior to the use of ground water of the type sought in this application. In the case of the subject application, such augmentation plan shall provide for the replacement to affected stream systems or system of a total amount of water equal to four percent (4%) of the amount of water withdrawn on an annual basis and such additional amounts that may be required pursuant to Section 37-90-137(9)(c), C.R.S. (1986 Supp).

- 7. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 69.2 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.
- 8. Underlying the land claimed in the application, the aquifer is, as specified in the Denver Basin Rules, located approximately 432 feet to 1339 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this _ Jut day of September

Dick Wolfe State Engineer

Βv

Don West Water Resources Engineer

Prepared by: DDW

OFFICE OF THE STATE ENGINEER DETERMINATION OF FACTS

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND WATER RIGHTS IN WATER DIVISION NO. 2, EL PASO COUNTY, COLORADO

CASE NO.: 07CW56

:

APPLICANT: AIMEE JAYNES LIVING TRUST AND JOHN JAYNES

AQUIFER : ARAPAHOE

In compliance with C.R.S. 37-92-302(2), Aimee Jaynes Living Trust and John Jaynes, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on May 31, 2007.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 135 acres of land as further described in said application.
- 3. The quantity of water in the Arapahoe Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 135 acres of land claimed in the application is 5806 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 17 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 253 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has not disclosed that there are any existing wells or other water rights claiming or diverting ground water from the aquifer underlying the land claimed by the applicant.
- 6. Withdrawal of ground water from the aquifer underlying the land claimed in the application will not, within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is nontributary ground water as defined in C.R.S. 37-90-103(10.5). Pursuant to C.R.S. 37-90-137(9)(b) and the Denver Basin Rules, no more than 98% of the nontributary ground water withdrawn annually shall be consumed and the applicant shall

Case No.: 07CW56 Applicant: Aimee Jaynes Living Trust and John Jaynes Aquifer: Arapahoe

demonstrate to the reasonable satisfaction of the State Engineer that no more than 98% of the water withdrawn will be consumed prior to the issuance of a well permit.

- 7. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 58.1 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.
- 8. Underlying the land claimed in the application, the aquifer is, as specified in the Denver Basin Rules, located approximately 1383 feet to 1872 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this 24th day of September

Hal D. Simpson State Engineer

By:

Don West Vater Resources Engineer

Prepared by: DDW

OFFICE OF THE STATE ENGINEER DETERMINATION OF FACTS

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND WATER RIGHTS IN WATER DIVISION NO. 2, EL PASO COUNTY, COLORADO

CASE NO.: 07CW56

• . •

APPLICANT: AIMEE JAYNES LIVING TRUST AND JOHN JAYNES

AQUIFER : LARAMIE FOX-HILLS

In compliance with C.R.S. 37-92-302(2), Aimee Jaynes Living Trust and John Jaynes, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on May 31, 2007.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 135 acres of land as further described in said application.
- 3. The quantity of water in the Laramie Fox-Hills Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 135 acres of land claimed in the application is 3847 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 15 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 190 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has not disclosed that there are any existing wells or other water rights claiming or diverting ground water from the aquifer underlying the land claimed by the applicant.
- 6. Withdrawal of ground water from the aquifer underlying the land claimed in the application will not, within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is nontributary ground water as defined in C.R.S. 37-90-103(10.5). Pursuant to C.R.S. 37-90-137(9)(b) and the Denver Basin Rules, no more than 98% of the

DISTRICT COURT, WATER DIVISION 2, COLORADO 320 WEST 10 th Street Pueblo, CO 81003 Phone Number: (719) 583-7011	EFILED Document – District Court 2007CW56 <u>CO Pueblo County District Court 10th JD</u> Filing Date: Dec 26 2007 8:57AM MST Filing ID: 17781289 Review Clerk: Mardell Didomenico
CONCERNING THE APPLICATION FOR WATER RIGHTS OF: AIMEE R. JAYNES LIVING TRUST AND JOHN R. JAYNES IN EL PASO COUNTY, COLORADO.	▲ COURT USE ONLY ▲
	CASE NO. 07CW56 WATER DIVISION 2
FINDINGS OF FACT, CONCLUSIONS AND JUDGMENT AND DECRI	-

This matter came before the Court upon the Application of Applicants to Quantify Underground Nontributary and Not Nontributary Water Rights.

The Water Judge referred the Application to the undersigned Water Referee for Water Division No. 2, State of Colorado, in accordance with Article 92 of Chapter 37, Colorado Revised Statutes 1973, known as the Water Rights Determination Act of 1969.

The undersigned Referee has made such investigations as are necessary to determine whether or not the statements in the Application are true, has become fully advised with respect to the subject matter of the Application and has consulted with the Division Engineer for Water Division No. 2. The Referee hereby makes the following determination and ruling as the Referee in this matter.

I. FINDINGS OF FACT

1. <u>Applicants</u>: The Applicants are the Aimee R. Jaynes Living Trust, c/o Kenneth H. Jaynes, whose address is 201 Eighth Street, Glenwood Springs, Colorado 81601 and John R. Jaynes, whose address is 8225 Poco Road, Colorado Springs, Colorado 80908. The Applicants are represented by Balcomb & Green, P.C., P. O. Drawer 790, Glenwood Springs, Colorado 81602, 970/945-6546.

2. <u>The Application</u>: Applicants filed an Application to Quantify Underground Nontributary and Not Nontributary Water Rights on May 31, 2007. The Application was properly published in the resume for Water Division No. 2. All notices required by law have been made, and the Court has jurisdiction over the Application and over all of the parties in this case. No statements of opposition were filed in this case and the time for filing such statements has expired. The Court finds that the relief requested herein is consistent with the relief originally requested in the Application and for which public notice was provided. None of the water rights or structures involved herein are located within a designated groundwater basin.

.'

3

CLAIM TO QUANTIFY UNDERGROUND NONTRIBUTARY AND NOT NONTRIBUTARY WATER RIGHTS

3. <u>Purpose of Application</u>: Applicants own approximately 135 acres, more or less, in El Paso County, Colorado, generally described as portions of Sections 28 and 33, Township 12 South, Range 65 West of the 6th P.M., and as shown on the map attached hereto as **Figure 1**. This Application seeks to adjudicate all the ground water in the Denver Basin Aquifers underlying Applicants' Property. Applicants are the owners of the Property described in **Figure 1**. While some of the water underlying Applicants' Property is classified as not nontributary and requires replacement to the affected stream pursuant to a decreed plan for augmentation, no such diversions or plan for augmentation is sought by this application.

4. <u>Sources of Water</u>: There are four aquifers located beneath Applicants' property; Dawson, Denver, Arapahoe, and the Laramie-Fox Hills. Ground water from the Dawson and Denver aquifers is classified as not nontributary and ground water from the Arapahoe and Laramie-Fox Hills aquifers is classified as nontributary.

5. <u>Right to Ground Water Claimed</u>: Applicants seek a decree for all ground water determined to be available from each aquifer named above underlying the 135 acres of land described above based upon a statutory aquifer life of one hundred years. Withdrawals in the average amounts determined to be available from each named aquifer can be made pursuant to section 37-90-137(4), C.R.S. (2006), without causing material injury to the vested rights of others, provided that withdrawals of not nontributary ground water may be made only pursuant to a judicially approved plan for augmentation of stream depletions caused by such withdrawals.

6. <u>Water Excluded from Quantification</u>: Applicants have excluded 12.0 acre-feet of the average annual amount of withdrawal determined available from the not nontributary Dawson aquifer underlying the 135 acres of land described above. The 12.0 acre-feet per year of ground water shall be available for withdrawal and use through exempt wells located on or to be located on Applicants' property and limited to an annual maximum withdrawal of 3.0 acre-feet per year per year per exempt well permit.

6. <u>Quantification of Available Water</u>: The estimated average annual amounts of withdrawal available from each aquifer are as follows:

Aquifer	Area in Acres	Avg. Saturated Thickness	Specific Yield	Legal Status	Avg. Annual Amount	Excluded Annual Amount	Total Annual Amount Claimed
Dawson	135	173.8 FT	0.20	NNT	46.9 AF	12 AF	34.9 AF
Denver (4% relinquishment)	135	301.7 FT	0.17	NNT	69.2 AF	N/A	69.2 AF
Arapahoe	135	253.0 FT	0.17	NT	58.1 AF	N/A	58.0 AF
Laramie-Fox Hills	135	190.0 FT	0.15	NT	38.5 AF	N/A	38.5 AF

a. Dawson Aquifer. Ground water available from the Dawson aquifer is below the entire property. Withdrawals from the aquifer will require an approved plan for augmentation.

b. Denver Aquifer. Ground water available from the Denver aquifer is below the entire property. The Property overlies that portion of the Denver aquifer that requires four percent (4%) of the annual amount pumped to be relinquished to the stream. Withdrawals from the Denver aquifer will require an approved plan for augmentation.

c. Arapahoe Aquifer. Ground water from the Arapahoe aquifer is below the entire Property. Pursuant to the State Engineer's Rules and Regulations, only 98 percent of the water to be withdrawn will be consumed.

d. Laramie-Fox Hills Aquifer. Ground water from the Laramie- Fox Hills aquifer is below the entire Property. Pursuant to the State Engineer's Rules and Regulations, only 98 percent of the water to be withdrawn will be consumed.

7. <u>Determination of Facts</u>: The amounts and values of water described in paragraph 6 above conform with the State Engineer's September 24, 2007 Determination of Facts Reports.

8. <u>Well Permits</u>: Well permit applications may be applied for at a later time pursuant to the terms of the decree entered in this case. Applicants request the right to construct wells anywhere on the Applicants' Property in order to recover the entire amount of ground water found to be available in each aquifer. Any well to be drilled into any non-tributary aquifer shall be cased so as to prevent withdrawal of water from more than one aquifer.

9. <u>Well Fields</u>: The right to withdraw all of the legally available ground water in the subject aquifers underlying Applicants' Property may be accomplished through any well(s)

initially permitted in such aquifer and any additional well(s) which may in the future become part of the Applicants' well field. As additional wells are constructed, well permit applications will be filed in accordance with § 37-90-137(10), C.R.S. The State Engineer shall issue well permits based on the full acreage of the property described in this Application.

10. <u>Rate of Withdrawal</u>: Applicants may withdraw more than the average annual amount estimated above pursuant to Rule 8A of the <u>Statewide Nontributary Groundwater Rules</u> (2 C.C.R. 402-7). Applicants will withdraw water at whatever rate is required in order to do so, and when the water is needed during the course of any year.

11. <u>Uses</u>: The water quantified herein shall be used, reused, leased, sold, or otherwise used to extinction for: domestic, irrigation, commercial, agricultural, municipal (if sold to a municipality), stock watering, recreational, piscatorial, wildlife, fire protection or other beneficial purposes and for exchange or augmentation of such uses upon or off Applicants' property.

II. CONCLUSIONS OF LAW

1. To the extent they constitute legal conclusions, the foregoing Findings of Fact are incorporated herein.

2. All notices required by law have been properly made, including as required under C.R.S. § 37-92-302(3). The Court has jurisdiction over the Application and over all persons or entities who had standing to appear, even though they did not do so.

3. The Application is completed, covering all applicable matters required pursuant to the Water Right Determination and Administration Act of 1969, C.R.S. §§ 37-92-101 through – 602.

4. The Court has given due consideration to the Office of the State Engineer's Determination of Facts dated September 24, 2007 and the Division Engineer's Summary of Consultation dated November 6, 2007. See C.R.S. § 37-92-302(2)(a).

5. Applicants have fulfilled all legal requirements for an entry of a decree for the requested water rights, including C.R.S. §§ 37-92-302 and 37-92-305.

6. The rights to not nontributary and tributary groundwater determined herein shall not be administered in accordance with priority of appropriation. Such rights are not "conditional water rights" as defined by C.R.S. § 37-92-103(6) and no subsequent diligence findings are required.

Case No. 07CW56 FINDINGS OF FACT, RULING OF REFEREE PAGE 4

III. JUDGMENT AND DECREE

1. The foregoing Findings of Fact and Conclusions of Law are incorporated herein.

2. <u>Adjudication</u>: The water rights claimed herein and described above are hereby confirmed, vested and adjudicated.

3. <u>Well Permits</u>: Exempt well permits issued pursuant to this decree for water from the Dawson aquifer shall be subject to the following conditions:

a. Exempt well permits will be issued pursuant to C.R.S. § 37-92-602(3)(b)(II)(A), under a presumption of no injury. No permits may be issued pursuant to C.R.S. § 37-92-602(3)(B)(I).

b. Exempt well permits must be issued as the only well on an identified tract of land.

c. No exempt well may be located on any subdivision of land as defined by C.RS. § 30-28-101(10), whether such subdivision occurs before or after issuance of an exempt well permit. Should the tract on which an exempt well is located be subdivide subsequent to issuance of the exempt permit, that permit shall become invalid and the well must either be plugged or re-permitted as a non-exempt well pursuant to this decree.

d. Applicant may seek up to four exempt well permits with cumulative annual withdrawals not to exceed twelve acre feet. If any wells are to be located in a cluster development, these wells shall be limited to diversions at a ratio not to exceed one acre foot of annual withdrawals for each thirty-five acres within the cluster development.

e. All applications for an exempt well permit for the property described above must reference this case, and contain a requested annual withdrawal rate.

f. All exempt well permits must contain an annual withdrawal limitation.

g. The cumulative sum of annual withdrawals by all exempt wells withdrawing the reserved water shall not exceed twelve acre feet.

4. <u>Retained Jurisdiction</u>: The Court retains jurisdiction as necessary to adjust the average annual amount of not nontributary and nontributary groundwater underlying the Subject property depicted on Figure 1, to conform to actual local aquifer characteristics as determined from site specific information obtained from the wells, pursuant to C.R.S. § 37-92-305(11).

a. After completion of any well or any test hole(s), Applicants shall geophysically survey the length of any such well or test hole prior to casing and submit

such geophysical log(s) to the State Engineer in a form acceptable to the State Engineer. A geophysical log shall not be required for an exempt well.

b. No later than three years after the submission of such geophysical log(s), any person, including the State Engineer, may invoke the Court's retained jurisdiction to make a Final Determination of Water Right. Within four months of notice that the retained jurisdiction for such purpose has been invoked, the State Engineer shall use the information available to him to make a final determination of rights finding. The State Engineer shall submit such finding to the Court and to the Applicants.

c. If no protest to such finding of the State Engineer is made within sixty days, the Court shall incorporate the Final Determination of Rights into this Amended Ruling and Decree. In the event of a protest, or in the event the State Engineer makes no determination within four months, such final determination shall be made by the Court after notice and hearing.

5. <u>Filing of Decree</u>: It is accordingly ordered that this Ruling of Referee and Judgment and Decree shall be filed with the Water Clerk and shall become effective upon such filing, subject to judicial review pursuant to C.R.S. § 37-92-304, as amended. It is further ordered that a copy of this Ruling of Referee and Judgment and Decree shall be filed with the State Engineer and the Division Engineer for Water Division No. 2.

DONE this ∂C^{\dagger} day of November, 2007.

BY THE REFEREE:

Mardell R. DiDomenico, Water Referee State of Colorado


No protest was filed in this matter. The foregoing Ruling of Referee is confirmed and approved, and is made the Judgment and Decree of this Court.

Done this 12 day of Secember

BY THE COURT:

Dennis Maes, Wáter Judge State of Colorado

CASE NO. 07CW56 FINDINGS OF FACT, RULING OF REFEREE PAGE 6



	EFILED Document – District Court 2008CW113 CO Pueblo County District Court 10th JD
DISTRICT COURT, WATER DIVISION 2 Court Address: 320 W. 10 TH St., #203 Pueblo, CO 81003 Phone Number: (719) 583-7048	Filing Date: Mar 11 2011 3.13PM M9T Filing ID: 36431301 Review Clerk: Mardell Didomenico
CONCERNING THE APPLICATION OF MORLEY-BENTLEY INVESTMENTS, LLC FOR ADJUDICATION OF DENVER BASIN GROUNDWATER	
IN EL PASO COUNTY.	
Attorneys for Applicant:	Δ COURT USE ONLY Δ
William H. Fronczak, #35043 Christopher Sutton #4369 Perkins Coie LLP 1899 Wynkoop Street, Suite 700. Denver, CO 80202 Phone Number: (303) 291-2300	Case No: 08CW113
Fax Number: (303) 291-2400 E-mail: <u>wfronczak@perkinscoie.com</u>	

FINDING OF FACT, CONCLUSIONS OF LAW, RULING OF THE REFEREE, JUDGMENT AND DECREE

FINDINGS OF FACT

1. Morley-Bentley Investments, LLC ("Applicant") filed an Application in this matter on December 31, 2008 (Applicant's mailing address is 20 Boulder Crescent, 2nd Floor, Colorado Springs, CO 80903).

2. Timely and adequate notice of this Application was duly published by the Water Clerk as required by statute on January 15, 2009, and publication costs have been paid. The Court has jurisdiction over the matters raised in the Application and all parties affected thereby, whether they have appeared or not. The lands and water rights involved in this Application are located within the boundaries of the Denver Basin.

3. The deadline for filing a Statement of Opposition was the last day of February 2009. A timely Statement of Opposition was filed by the City of Colorado Springs. Colorado Springs consents to entry of this Ruling. No other Opposer appears in this case.

4. On September 13, 2010, Applicant filed an Unopposed Motion to Amend Application. This motion amended the Application to remove the augmentation plan from the Application (Section III Application for Approval of a Plan for Augmentation).

5. By Order pursuant to C.R.C.P. 15 and Uniform Water Court Rule 4, entered on September 21, 2010, the Court granted Applicant's Unopposed Motion to Amend Application without the need of publication.

6. Applicant seeks to adjudicate and quantify the ground water contained within the Dawson and Denver aquifers underlying Applicant's Property. Applicant is the fee owner of approximately 1,451.44 acres in Sections 27, 28, 32, 33, and 34, Township 12 South, Range 65 West, and Section 4, Township 13 South, Range 65 West, El Paso County, Colorado, as more specifically described in attached Exhibit A ("Applicant's Property"). A map showing the Applicant's Property location is attached hereto.

7. Applicant also seeks to adjudicate and quantify the ground water contained within the Arapahoe and Laramie-Fox Hills aquifers underlying approximately 41.44 acres in the NW1/4 of Section 4, Township 13 South, Range 65 West and in the SE1/4 SW1/4 SE1/4 Section 32, Township 12 South, Range 65 West, of the 6th P.M. This 41.44 acres is a part of the Applicant's Property and is referred to herein as the Additional Property. The Additional Property location is identified on the attached map. The ground water contained within the Arapahoe and Laramie-Fox Hills underlying an approximately 1,410-acre portion of the Applicant's Property ("Previously Adjudicated Property") was previously adjudicated and quantified in Case Nos. 86CW18 and 86CW19 in the Water Court for Division 2, respectively.

8. On March 4, 2009, the Office of the State Engineer filed a Determination of Facts herein for the Dawson and Denver aquifers underlying Applicant's Property and the Arapahoe and Laramie-Fox Hills aquifers underlying the Additional Property. The Court has considered these filings in entering this Ruling and hereby adopts the Determination of Facts by reference herein. Copies of the Determination of Facts are also attached.

9. Applicant has not determined the specific locations for any new wells to be constructed into the Dawson and Denver aquifers on the Applicants Property, but agrees that each well constructed will be within Applicant's Property and designed so that it withdraws water from a single aquifer and is located at least 600 feet from any other well which withdraws from the same aquifer that is not under common ownership. Applicant claims the following pumping rates from the Dawson and Denver aquifers underlying Applicant's Property:

- Dawson 150 gallons per minute.
- Denver 150 gallons per minute.

10. Applicant has also not determined the specific locations for any new wells to be constructed into the Arapahoe and Laramie-Fox Hills aquifers on the Additional Property, but agrees that each well constructed will be within the Additional Property and designed so that it withdraws water from a single aquifer and is located at least 600 feet from any other well which withdraws from the same aquifer that is not under common ownership. Applicant claims the following pumping rates from the Arapahoe and Laramie-Fox Hills aquifers underlying Applicant's Property:

- Arapahoe 150 gallons per minute.
- Laramie-Fox Hills 150 gallons per minute

11. Based upon the attached map, the Determination of Facts quantified the Dawson and Denver ground water available underlying the Applicant's Property and the Arapahoe and Laramie-Fox Hills ground water underlying the Additional Property. Based upon a 100-year aquifer life, the following amounts of ground water are available to Applicant:

Aquifer Sand Thicknes (ft)		Annual Appropriation (af)	Status		
Dawson	145.8	392.5 ¹	N-NT (actual)		
Denver	313.8	728.9 ²	N-NT (4%)		
Arapahoe	251.4	0.60 ³	N-NT (4%)		
Laramie-Fox Hills	190	0.40 ³	NT		

¹ Represents a reduction in the annual appropriation to prevent material injury to the vested water rights of 8745-R, 8746-R, 8747-R and 8748-R.

^{2.} Represents a reduction in the annual appropriation to prevent material injury to the vested water rights 19961-F and 26947-F.

³ Represents a reduction in the annual appropriation to prevent material injury to the vested water right decreed in Case No. 02CW66.

NT - Non-Tributary

N-NT(4 %) – Not Non-Tributary 4 percent replacement of the amount of groundwater withdrawn.

N-NT(actual) – Not Non-Tributary actual replacement of stream depletions.

12. The Application states, and the Determination of Facts finds, that the Laramie-Fox Hills aquifer underlying the Additional Property is non-tributary as defined in C.R.S §37-90-103(10.5). The Court adopts this finding. Accordingly, two percent of all withdrawals from this aquifer are required to be relinquished to the stream system. 13. The Application states, and Determination of Facts finds, that the Arapahoe aquifer underlying the Additional Property and the Denver underlying the Applicant's Property are not non-tributary as defined in C.R.S §37-90-103(10.5). The Determination of Facts also conclude that the Additional Property with respect to the Arapahoe aquifer and the Applicant's Property with respect to the Denver aquifer are located greater than one mile from any point of contact between any natural surface stream, including its alluvium, and these aquifers. The Court adopts this finding. Accordingly, water from the Arapahoe aquifer underlying the Additional Property and the Denver underlying the Applicant's Property cannot be used until a plan for augmentation is approved by the Court to replace depletions caused by pumping this ground water pursuant to C.R.S. §§37-90-137(9)(c) and 37-92-302(1). Such an augmentation plan shall provide for the replacement of affected stream systems or system of a total amount of water equal to four percent (4%) of the amount of water withdrawn on an annual basis from each aquifer.

14. The Application states, and the Determination of Facts finds, that the ground water in the Dawson aquifer underlying the Applicant's Property is not non-tributary as defined in C.R.S. 37-90-103(10.5). The Court adopts this finding. Accordingly, water from this aquifer cannot be used until a plan for augmentation is approved by the Court to replace depletions caused by pumping this ground water pursuant to 337-90-137(9)(c) and 37-92-302(1). Such an augmentation plan shall provide for the replacement of actual stream depletions to the extent necessary to prevent any injurious effect.

15. Applicant seeks to adjudicate the above ground water for domestic, agricultural, industrial, municipal, commercial, irrigation, recreational, aesthetic, piscatorial, fire protection, augmentation, exchange and storage, and successive reuse to extinction so long as such reuse is augmented when necessary. Applicant also seeks to use such water by immediate application or by storage and subsequent application to the beneficial uses and purposes stated herein.

16. Applicant requests the Court determine that Applicant may withdraw full legal entitlement from the Dawson and Denver aquifers underlying Applicant's Property through any combination of wells. Applicant requests that these wells to each respective aquifer be treated as a well field. Applicant also requests that it be entitled to withdraw an amount of ground water in excess of the average annual amount decreed to these aquifers beneath the Applicant's Property, so long as the sum of the total withdrawals from all the wells in the respective aquifer does not exceed the product of the number of years since the date of issuance of the original well permit or the date of entry of a decree, whichever comes first, multiplied by the average annual volume of water which the Applicant is entitled to withdraw from that aquifer underlying the Applicant's Property.

17. As to the not non-tributary Arapahoe and non-tributary Laramie-Fox Hills aquifers underlying the Additional Property, Applicant requests that it be entitled to withdraw those quantities of ground water quantified herein, along with that ground water previously quantified in 86CW18 and 86CW19, respectively, from common structures, in consideration of the contiguity of the overlying land between such adjudications (i.e. Applicant's Property).

Applicant also requests that it be entitled to withdraw an amount of ground water in excess of the average annual amount decreed to the respective aquifer beneath the Additional Property, so long as the sum of the total withdrawals from all the wells in the aquifers do not exceed the product of the number of years since the date of issuance of the first well permit, multiplied by the average annual volume of water which the Applicant is entitled to withdraw from the aquifers underlying the Additional Property.

18. Applicant also requests that the Court retain jurisdiction over this matter to make adjustments in the allowed annual average amount of withdrawal, either upwards or downwards, to conform to actual local aquifer characteristics. The Court will retain jurisdiction in this matter pursuant to paragraph 29 of this Ruling to make any necessary adjustments, and such adjustments shall be made by the Court without Applicant having to refile, republish, or otherwise amend this Application.

CONCLUSIONS OF LAW

19. The Court has jurisdiction in this matter pursuant to C.R.S. \$ 37-90-137(6), 37-92-203(1), and 37-32-302 through 305.

20. The Court concluded that the Application in this matter is one contemplated by law. The Application for a decree confirming Applicant's right to divert and use not non-tributary ground water from the Dawson and Denver underlying the Applicants Property and the not non-tributary Arapahoe and non-tributary Laramie Fox Hills aquifers underlying the Additional Property, pursuant to C.R.S. §§ 37-90-137(4) and 37-90-137(9)(c), should be granted subject to the provision of this decree. The rights confirmed by the by this decree are vested property rights.

21. Timely and adequate notice of the filing and contents of the Application herein was given in the manner required by law, and no additional notice is required. C.R.S. § 37-92-302(3).

22. The Court concludes that the rights to ground water determined herein are not conditional water rights and subsequent showing or finding of reasonable diligence under C.R.S. § 37-32-301(4) are inapplicable and need not be made. Accordingly, each of the water rights adjudicated herein is a final water right.

23. The Court concludes that the rights to ground water determined in this decree do not in any way affect, modify or otherwise change this Court's adjudication, status or quantification of the Arapahoe and Laramie-Fox Hills ground water previously adjudicated in Case Nos. 86CW18 and 86CW19, respectively.

24. The water rights described above are capable of administration by the state water officials.

RULING

25. The provisions of paragraphs 1-24 above are incorporated herein and made a part of the Court's Ruling.

26. Applicant's request for adjudication of the Dawson and Denver ground water underlying the Applicant's Property and the Arapahoe and Laramie-Fox Hills ground water underlying the Additional Property as described in paragraphs 5 through 11 above are hereby granted subject to the terms and conditions set forth herein.

27. Applicant must apply for well permits for all new wells to be constructed within the Laramie-Fox Hills on the Additional Property. The State Engineer shall evaluate those applications pursuant to C.R.S. § 37-90-137(2) consistent with the terms and conditions of the final decree entered herein. Permits shall not be unreasonably withheld. Applicant shall meter and record all well use for reporting purposes.

28. Withdrawal of ground water from the not non-tributary Dawson and Denver underlying the Applicant's Property and the not non-tributary Arapahoe aquifer underlying the Additional Property shall be prohibited without a Court approved augmentation plan and well permits issued by the State Engineer.

29. The Court shall retain jurisdiction over this matter for the purpose of reconsidering the question of injury to the vested water rights of others pursuant to this paragraph. The decree herein grants water rights from the Dawson and Denver underlying the Applicant's Property and the Arapahoe and Laramie-Fox Hills aquifers underlying the Additional Property. The Court retains jurisdiction to provide for adjustment of the average annual amount of withdrawal to conform to actual local aquifer characteristics as determined from analyses of data obtained when the wells are constructed or analysis of other acceptable geophysical information as provided in Statewide Nontributary Rules 2 C.C.R. 402-7. Within 60 days after completion of such well(s) or test hole(s), Applicant shall file with the State Engineer copies of the well logs from such well(s) or test hole(s). Any person, including the State Engineer, may invoke the Court's retained jurisdiction to make a Final Determination of Water Right. The State Engineer, upon notice of the invocation of such retained jurisdiction, shall use the data available to him and make a Final Determination of Water Rights Findings within four (4) months thereafter and submit the same event of a protest or in the event the State Engineer makes no determination within four (4) months after the Court's retained jurisdiction is invoked, such final determination shall be made by the Court after notice and a hearing.

6

30. This Ruling shall be mailed as required by statute.

Dated: March 11, 2011.

BY THE WATER REFEREE:

Mardell R. DiDomenico Water Referee

JUDGMENT AND DECREE

The foregoing Ruling comes before the Court after the time period for raising objections to the same pursuant to C.R.S. §37-92-304(2) has expired. The Court, having reviewed the Ruling and being familiar with the terms of the same, hereby approves and enters said Ruling as a Judgment and Decree of this Court pursuant to C.R.S. §37-92-304(5).

DONE this _____ day of _____, 2010.

BY THE COURT:


Dennis Maes, Water Judge Water Division 2

.

EXHIBIT A – Applicant Property

The Subject Lands consist of the following:

The W1/2 W1/2 E1/2 and the E1/2 W1/2 and the SW1/4 SW1/4 of Section 27; the E1/2 SE1/4 and that portion of the SW1/4 SE1/4 lying South and East of the County Road across said premises, both in Section 28; that portion of the SE1/4 SE1/4 of Section 32 lying South and East of said County Road, that portion of the NE1/4 SE1/4 of said Section 32, lying South and East of said County Road, and that portion of the SE1/4 SW1/4 SE1/4 of Section 32 beginning at the SE corner of the SE1/4 SW1/4 SE1/4, then northerly along the east line of the SE1/4 SW1/4 SE1/4 a distance of 495 feet to a point on Volimer Road, then southwesterly along Volimer Road 660 feet to a point on the south line, then easterly 495 feet to the point of beginning; the E1/2 and the E1/2 SW1/4 and the SW1/4 SW1/4 of Section 33, and all that part of the NW1/4 of said Section 33. lying South and East of the said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road containing approximately 10 acres deeded to Colorado Interstate Gas Company by Warranty Deed recorded in Book 1173 at Page 359 of the El Paso County Records; and the W1/2 E1/2 and the W1/2 of Section 34, all in Township 12 South, Range 65 West of the 6th P.M., located in El Paso County, Colorado. The NW1/4 of the NW1/4 of Section 4, Township 13 South, Range 65 West of the 6th P.M., located in El Paso County. Colorado.



OFFICE OF THE STATE ENGINEER

DETERMINATION OF FACTSEFILED Document – District Court 2008CW113 CO Pueblo County District Court 10th JD

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND MAR 16,2009 1:12PM MST DIVISION NO. 2, EL PASO COUNTY, COLORADO Review Clerk: Mardell Didomenico

CASE NO.: 08CW113

APPLICANT: MORLEY-BENTLEY INVESTMENTS, LLC

AQUIFER : DAWSON

In compliance with C.R.S. 37-92-302(2), Morley-Bentley Investments, LLC, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on December 31, 2008.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 1451.44 acres of land as further described in said application.
- 3. The quantity of water in the Dawson Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 1451.44 acres of land claimed in the application is 42,309 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 20 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 145.8 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has disclosed that there are existing wells or other water rights withdrawing ground water from the aquifer underlying the land claimed by the applicant. The well permit numbers, locations, rates of diversion, and other relevant data concerning such rights are set forth in the attached Exhibit A. To prevent material injury to such vested water rights, the quantity of water underlying the land claimed in the application which is considered available for withdrawal has been reduced to 39,247 acre-feet. This reduction was based on a calculation of the area necessary to provide a quantity of water underlying such lands as would be sufficient for the persons entitled to divert water under existing rights to divert the average annual amount of water from the aquifer for the minimum aquifer life of 100 years. The effect of this calculation is

Case No.: 08CW113 Applicant: Morley-Bentley Investments, LLC Aquifer: Dawson

to reduce the land available for calculating the quantity of water underlying the land claimed in the application to 1,345,92 acres.

- 6. Withdrawal of ground water from the aquifer underlying the land claimed in the application will within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is <u>not</u> nontributary ground water as defined in C.R.S. 37-90-103(10.7). C.R.S. 37-90-137(9)(c) states that judicial approval of a plan for augmentation shall be required prior to use of ground water of the type sought in this application. In the case of the Dawson aquifer such augmentation plans shall provide for the replacement of actual stream depletions to the extent necessary to prevent any injurious effect, based on actual aquifer conditions in existence at the time of the decree.
- 7. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 392.5 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.
- 8. Underlying the land claimed in the application, the aquifer is, as specified in the Denver Basin Rules, located approximately 54 feet to 346 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this _____ day of _____

. 2009.

Dick Wolfe, P.E. Director/State Engineer

By: Sarah Reinsei

Water Resources Engineer

Prepared by: SKR

Case No.: 08CW113 Applicant: Morley-Bentley Investments, LLC Aquifer: Dawson

EXHIBIT A

Well	Location									
Number	<u>Q40</u>	<u>Q160</u>	<u>Sec.</u>	<u>Twp.</u>	<u>Rng.</u>	<u>AF</u>	<u>ST</u>	<u>SY</u>	<u>Radius</u>	<u>Area</u>
8745-R	NE	SW	33	12S	65W	24.2	109	20	1240	87
8746-R	NE	SW	33	12S	65W	16.1	112	20	1001	71
8747-R	NE	SW	33	128	65W	12.9	114	20	886	57
8748-R	NE	SW	33	12S	65W	16.1	109	20	1011	74

Well Number = Well permit number and/or water court case number

- AF = Annual appropriation of the well (acre-feet)
- ST = Thickness of the saturated aquifer material at the well location (feet)
- SY = Specific Yield of the saturated aquifer material (%)

Radius = Radius of the cylinder of appropriation (feet)

Area = Area of the applicant's land that is overlapped by the cylinder of appropriation (acres)

OFFICE OF THE STATE ENGINEER

DETERMINATION OF FACTS EFILED Document – District Court 2008CW113

CO Pueblo County District Court 10th JD

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND FILE AND THE ADDITION FOR UNDERGROUND FILE ADDITION TO A ADDITION AND A ADDITIONAL ADDITIONALADDITICAL ADDITIONAL ADDITICAL ADDITIONAL ADDITIONAL

CASE NO.: 08CW113

APPLICANT: MORLEY-BENTLEY INVESTMENTS, LLC

AQUIFER : DENVER

In compliance with C.R.S. 37-92-302(2), Morley-Bentley Investments, LLC, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on December 31, 2008.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 1,451.44 acres of land as further described in said application.
- 3. The quantity of water in the Denver Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 1,451.44 acres of land claimed in the application is 77,416 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 17 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 313.8 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has disclosed that there are existing wells or other water rights withdrawing ground water from the aquifer underlying the land claimed by the applicant. The well permit numbers, locations, rates of diversion, and other relevant data concerning such rights are set forth in the attached Exhibit A. To prevent material injury to these vested water rights, the land available for calculating the quantity of water underlying the land claimed in the application is reduced to 1,410.00 acres. The effect of this calculation is to reduce the quantity of water underlying the land claimed in the application which is considered available for withdrawal to 72,893 acre-feet.

Case No.: 08CW113 Applicant: Morley-Bentley Investments, LLC Aquifer: Denver

- 6. Withdrawal of ground water from the aquifer underlying the land claimed in the application will, within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is <u>not</u> nontributary ground water as defined in C.R.S. 37-90-103(10.5). The land is more than one mile from any point of contact between any natural surface stream, including its alluvium, and the aquifer. C.R.S. 37-90-137(9)(c) states that judicial approval of a plan for augmentation shall be required prior to the use of ground water of the type sought in this application. In the case of the subject application, such augmentation plan shall provide for the replacement to affected stream systems or system of a total amount of water equal to four percent (4%) of the amount of water withdrawn on an annual basis and such additional amounts that may be required pursuant to Section 37-90-137(9)(c), C.R.S. (1986 Supp).
- 7. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 728.9 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.
- 8. Underlying the land claimed in the application, the aquifer is, as specified in the Denver Basin Rules, located approximately 380 feet to 1,270 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this 4th day of March , 2009.

Dick Wolfe, P.E. Director/State Engineer

By: Saral Reinsel

Water Resources Engineer

Prepared by: SKR

Case No.: 08CW113 Applicant: Morley-Bentley Investments, LLC Aquifer: Denver

~

EXHIBIT A

Well	Location						
<u>Number</u>	<u>Q40</u>			<u>Twp.</u>		<u> AF</u>	<u>Area</u>
19961-F	NE	NE	5	13S	65W	58	1.44
26947-F	SW	SW	32	12S	65W	20.3	40

Well Number = Well permit number and/or water court case number

AF = Annual appropriation of the well (acre-feet)

Area = Area of the applicant's land that is overlapped by the previous allocation (acres)

OFFICE OF THE STATE ENGINEER

DETERMINATION OF FACTS EFILED Document – District Court 2008CW113

CO Pueblo County District Court 10th JD

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND HIM REPORT REPORT OF AN APPLICATION FOR UNDERGROUND HIM REPORT OF AN APPLICATION FOR APPLICAT

CASE NO.: 08CW113

APPLICANT: MORLEY-BENTLEY INVESTMENTS, LLC

AQUIFER : ARAPAHOE

In compliance with C.R.S. 37-92-302(2), Morley-Bentley Investments, LLC, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on December 31, 2008.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 41.44 acres of land as further described in said application.
- 3. The quantity of water in the Arapahoe Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 41.44 acres of land claimed in the application is 1,771 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 17 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 251.4 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has disclosed that there is an existing decreed water right to withdraw ground water from the aquifer underlying a portion of the land claimed by the applicant. Case no. 02CW66 was approved by the Division 2 Water Court on December 3, 2002 to allow for the withdrawal of ground water from the aquifer underlying 132 acres, 40 acres of which overlaps the applicant's claimed overlying land area. To prevent material injury to this vested water right, the land available for calculating the quantity of water underlying the land claimed in the application is reduced to 1.44 acres. The effect of this calculation is to reduce the quantity of water underlying the land claimed in the application which is considered available for withdrawal to 61.5 acre-feet.

Case No.: 08CW113 Applicant: Morley-Bentley Investments, LLC Aquifer: Arapahoe

- 6. Withdrawal of ground water from the aquifer underlying the 1.44 acres of available land claimed in the application will, within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is <u>not</u> nontributary ground water as defined in C.R.S. 37-90-103(10.5). The land is more than one mile from any point of contact between any natural surface stream, including its alluvium, and the aquifer. C.R.S. 37-90-137(9)(c) states that judicial approval of a plan for augmentation shall be required prior to the use of ground water of the type sought in this application. In the case of the subject application, such augmentation plan shall provide for the replacement to affected stream systems or system of a total amount of water equal to four percent (4%) of the amount of water withdrawn on an annual basis and such additional amounts that may be required pursuant to Section 37-90-137(9)(c), C.R.S. (1986 Supp).
- 7. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 0.6 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.
- 8. Underlying the land claimed in the application, the aquifer is, as specified in the Denver Basin Rules, located approximately1,122 feet to 1,628 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this 4th day of March , 2009.

Dick Wolfe, P.E. Director/State Engineer

By:

Sara#Reinsel Water Resources Engineer

Prepared by: SKR

OFFICE OF THE STATE ENGINEER DETERMINATION OF FACTS EFILED Document -- District Court

FAUTS EFILED Document - District 2008CW113

CO Pueblo County District Court 10th JD

IN THE MATTER OF AN APPLICATION FOR UNDERGROUND WATER Date: Mar. 6.2000 1.17PL MST DIVISION NO. 2, EL PASO COUNTY, COLORADO Review Clerk: Mardell Didomenico

CASE NO.: 08CW113

APPLICANT: MORLEY-BENTLEY INVESTMENTS, LLC

AQUIFER : LARAMIE-FOX HILLS

In compliance with C.R.S. 37-92-302(2), Morley-Bentley Investments, LLC, (hereinafter "applicant") submitted an application to the Water Court for a determination of the amount of water available pursuant to C.R.S. 37-90-137(4). Based on information provided to the Court by the applicant and records of the Division of Water Resources, the State Engineer finds as follows:

- 1. The application was received by the Water Court on December 31, 2008.
- 2. According to the application, the applicant owns, or has consent to withdraw ground water underlying 41.44 acres of land as further described in said application.
- 3. The quantity of water in the Laramie-Fox Hills Aquifer (hereinafter "aquifer"), exclusive of artificial recharge, underlying the 41.44 acres of land claimed in the application is 1,181 acre-feet. This determination was based on the following as specified in the Denver Basin Rules:
 - a. The average specific yield of the saturated aquifer materials underlying the land claimed in the application is 15 percent.
 - b. The average thickness of the saturated aquifer materials underlying the land claimed in the application is 190.0 feet.
- 4. In determining the amount of ground water available for withdrawal annually from this aquifer, the provisions of C.R.S. 37-90-137(4) must be applied, and pursuant to C.R.S. 37-90-137(4)(b)(I) annual withdrawals shall be allowed on the basis of an aquifer life of 100 years.
- 5. A review of the records in the State Engineer's Office has disclosed that there is an existing decreed water right to withdraw ground water from the aquifer underlying a portion of the land claimed by the applicant. Case no. 02CW66 was approved by the Division 2 Water Court on December 3, 2002 to allow for the withdrawal of ground water from the aquifer underlying 132 acres, 40 acres of which overlaps the applicant's claimed overlying land area. To prevent material injury to this vested water right, the land available for calculating the quantity of water underlying the land claimed in the application is reduced to 1.44 acres. The effect of this calculation is to reduce the quantity of water underlying the land claimed in the application which is considered available for withdrawal to 41.0 acre-feet.

Case No.: 08CW113 Applicant: Morley-Bentley Investments, LLC Aquifer: Laramie-Fox Hills

- 6. Withdrawal of ground water from the aquifer underlying the land claimed in the application will not, within one hundred years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and therefore the ground water is nontributary ground water as defined in C.R.S. 37-90-103(10.5). Pursuant to C.R.S. 37-90-137(9)(b) and the Denver Basin Rules, no more than 98% of the nontributary ground water withdrawn annually shall be consumed and the applicant shall demonstrate to the reasonable satisfaction of the State Engineer that no more than 98% of the water withdrawn will be consumed prior to the issuance of a well permit.
- 7. The allowed average annual amount of water available for withdrawal from the aquifer underlying the lands claimed in the application is 0.4 acre-feet (the quantity of water which is considered available divided by the 100 year aquifer life). It is recommended that the water court retain jurisdiction necessary to provide for adjustment (increase or decrease) of this amount.
- 8. Underlying the land claimed in the application, the aquifer is, as specified in the Denver Basin Rules, located approximately 1,921 feet to 2,204 feet below land surface. A site specific evaluation must be conducted with each well permit to identify the interval due to the varied elevation of the aquifer and surface topography.

Dated this _____ day of ______, 2009.

Dick Wolfe, P.E. Director/State Engineer

and Sent By:

Sarah Reinsel Water Resources Engineer

Prepared by: SKR

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

DISTRICT COURT, WATER DIVISION NO. 2, STATE OF COLORADO 0CT 29 1986

Case No. 86-CW-18

 $\mathcal{L}_{k^{*}}^{\prime\prime}$

Riscieles Syners

Clerk

FINDINGS OF FACT, CONCLUSIONS OF LAW, JUDGMENT AND DECREE

CONCERNING THE APPLICATION FOR NONTRIBUTARY GROUND WATER RIGHTS OF THE FIRST INTERSTATE BANK OF DENVER N.A., CARLA W. LEWIS, AND SAMUEL S. SHERMAN AS COTRUSTEES UNDER THE LIFE INSURANCE TRUST OF THOMAS M. DINES FROM THE ARAPAHOE FORMATION, EL PASO COUNTY.

THIS MATTER, having come on for hearing before the Court this 29 day of 200, 1986 upon the application of The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines ("Applicants") and the Court having considered the pleadings filed and the evidence presented, and being fully advised in the premises, hereby enters the following Findings of Fact, Conclusions of Law, and Judgment and Decree:

FINDINGS OF FACT

1. The Applicants are The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines whose address is First Interstate Bank of Denver, 633 Seventeenth Street, Denver, Colorado 80202, Attn: Jack Alexander. Applicants filed the application in this case styled Application For Nontributary Ground Water From The Arapahoe Formation (the "Application") on March 28, 1986, seeking an adjudication of nontributary ground water rights from the Arapahoe Formation underlying lands owned by Applicants in El Paso County.

2. Timely and adequate notice of the Application was published as required by statute, and the Court has jurisdiction over the subject matter of this proceeding and over all parties affected hereby, whether they have appeared or not. None of the lands or water rights involved in this case are within the boundaries of a designated groundwater basin.

3. A timely statement of opposition was filed by JVRC, Inc. No other statements of opposition were filed within the time provided by law nor did any other parties enter their appearance or intervene in these proceedings. 4. The Water Referee by Order dated July 19, 1986, under Section 37-92-303(2), C.R.S., rereferred the Application to the Water Judge for all further proceedings.

5. The State Engineer issued a Determination of Facts on the Application, dated July 28, 1986, which has been filed with the Court. The Division Engineer adopted the Determination of Facts as his recommendations on August 8, 1986. The Determination of Facts and the findings contained therein have been reviewed and considered by this Court in accordance with Section 37-92-305(6), C.R.S.

Applicants seek an adjudication of rights 6. to nontributary ground water from the Arapahoe Formation beneath 1,410 acres of land in El Paso County which are described in Exhibit A and depicted on the map attached as Exhibit B, both of which are incorporated herein by this reference (the "Subject Lands"). Applicants are the owners of the Subject Lands and have the right to withdraw and use the waters from the Arapahoe Formation underlying those lands. The waters claimed herein may be withdrawn through the proposed wells described in Paragraph $\overline{7}$ below and through such additional, replacement and supplemental wells as may be necessary to withdraw all of the water in the Arapahoe Formation underlying the Subject Lands without causing material injury to any vested water right whose source of supply is the Arkansas River and any of its tributaries or any other natural stream, or any ground water tributary thereto, and the Applicants have so proven.

7. Applicants will divert the waters claimed herein from the Arapahoe Formation through Dines Wells KA-1, KA-2, KA-3, and KA-4 more particularly described as follows:

Well Name: Dines Well KA-1

- (a) In the SE 1/4 of the NW 1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., 2500 feet from the North Section line and 2200 feet from the West Section line, in El Paso County.
- (b) Depth: 1900 feet.
- (c) Source: Nontributary Arapahoe Formation.
- (d) Pumping rate: 150 gpm.

- 2 -

(e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KA-2

- (a) Location: In the SW 1/4 of the SW 1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., 200 feet from the South Section line and 200 feet from the West Section line, in El Paso County.
- (b) Depth: 1800 feet.
- (c) Source: Nontributary Arapahoe Formation.
- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KA-3

- (a) Location: In the NW 1/4 of the SE 1/4 of Section 33, Township 12 South, Range 65 West of the 6th P.M., 1500 feet from the South Section line and 2100 feet from the East Section line, in El Paso County.
- (b) Depth: 1700 feet.
- (c) Source: Nontributary Arapahoe Formation.
- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KA-4

- (a) Location: In the NE 1/4 of the SW 1/4 of Section 34, Township 12 South, Range 65 West of the 6th P.M., 1400 feet from the South Section line and 2100 feet from the West Section line, in El Paso County.
- (b) Depth: 1700 feet.
- (c) Source: Nontributary Arapahoe Formation.

- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.
- * Not to exceed in total the amount available to Applicants from the Arapahoe Formation pursuant to § 37-90-137(4), C.R.S. and the provisions of this decree.

8. Pursuant to §37-90-137(4), C.R.S., five hundred seventy-five (575) acre-feet of water per year are available to Applicants from the Arapahoe Formation underlying the Subject Lands. The average thickness of saturated sand of the Arapahoe Formation underlying the Subject Lands is 240 feet but the final determination on actual saturated sand thickness will be determined when the wells are drilled, and the amount decreed herein may be subsequently adjusted in accordance with that saturated sand thickness as provided in Paragraph 29 below. The specific yield of the Arapahoe Formation is 17% in and beneath the Subject Lands. This finding is specific to the property involved and does not indicate or in any way reflect upon proper values for the subject aquifer elsewhere. All the water in the Arapahoe Formation underlying the Subject Lands remains available for withdrawal by the wells decreed herein.

The State Engineer in his Determination of Facts 9. found acre-feet per year were that 581 available for appropriation through the subject wells. The State Engineer's determination is based on a finding that only 1395 acres of the Subject Lands are available for appropriation, and based on saturated sand thicknesses of 245 feet and 250 feet for different parts of the Subject Lands and a specific yield of 17% for the Arapahoe Formation. The State Engineer also found that of the total 581 acre-feet per year of water available for appropriation, 569 acre-feet was nontributary and 12 acre-feet was not nontributary. The 12 acre-feet per year the State Engineer found as not nontributary underly 37 acres of Section 32 of the Subject Lands. Applicant has shown by a preponderance of the evidence that there are no existing wells with a right to water from the Arapahoe Formation underlying the Subject Lands and that the water underlying 1410 acres is available for The Court also finds that the appropriation by Applicants. withdrawals through Applicants' proposed wells of the water claimed herein including the amount of water underlying the 37 acres in Section 32 is nontributary. The proposed wells will not, at their location and withdrawing the amounts decreed herein, within one hundred years deplete the flow of any natural stream at a rate greater than one-tenth of one percent of the annual rate of withdrawal. Applicants' engineer has testified that 575 acre-feet per year is available for appropriation calculated with a saturated sand thickness of 240 feet for the

Arapahoe Formation. Subject to the final determination of saturated sand thickness based on the information derived from the drilling of the wells, Applicants will use 240 feet for the saturated sand thickness of the Arapahoe Formation beneath the Applicants' property.

10. The source of water for the proposed wells is nontributary as defined in Section 37-90-103 (10.5), C.R.S. The proposed withdrawals through Dines Wells KA-1, KA-2, KA-3, and KA-4 in the amount of 575 acre-feet per year, or in any lesser or greater amount determined under Paragraph 29, will not, within one hundred years, deplete the flow of any natural stream or its alluvium or any ground water tributary thereto at an annual rate greater than one-tenth of 1% of the annual rate of withdrawal.

11. The waters of the Arapahoe Formation that are the subject of the appropriation claimed herein will be, and Applicants intend that they be used, and Applicants shall have the right of succession of uses, for municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation, exchange, replacement of depletions, augmentation, livestock and agricultural uses. The water will be produced for immediate application to beneficial use and for storage and subsequent application to beneficial use. Subject only to the provisions of Paragraph 31, Applicants shall have the right to make any reuse, successive use or disposition of the developed water claimed herein until totally consumed free of any limitations, restrictions, or requirements as to the place of use, amount of discharge or location of discharge after such reuse, successive use or disposition in accord with Section 37-82-106, C.R.S.

12. All of the requirements of C.R.S. § 37-90-137(4), in effect on this date have been complied with, and the issuance of permits for the subject wells is justified and those permits will be issued as described in Paragraph 34 below.

13. Applicants will relinquish the right to consume after use, reuse, and successive use 2% of the amount of ground water withdrawn through Dines Wells KA-1, KA-2, KA-3 and KA-4 and any additional, supplemental, or replacement, wells without regard to dominion or control of the ground water so relinquished.

14. Applicants seek a decree designating all of the wells described in Paragraph 7 above as original and alternate points of diversion for each other permitting the withdrawal of up to the full cumulative amount by flow rate and volume of water which may be lawfully withdrawn from any one or more of those wells. The Court finds that no material injury will result to the owners or persons entitled to use water under any vested

- 5 -

water right or decreed conditional water right by the granting of this request, and it is hereby granted.

15. Applicants may withdraw more water than the amounts set forth in Paragraph 8 so long as the sum of the withdrawals from all wells decreed herein (as that sum may subsequently be adjusted pursuant to Paragraph 29 hereof) does not exceed the product of the number of years since the date of this decree, times the annual rate of one percent (1%) of the total amount of unappropriated water recoverable from the Arapahoe Formation.

16. Applicants have requested that the Court determine that Applicants have the right to withdraw all of the unappropriated water from the Arapahoe Formation lying below their land and to increase their annual appropriations based upon the local aquifer characteristics established through information obtained from the drilling of the wells upon notice to all parties and approval by the Court, without amending the Application or republishing. The Court finds that there has been full and adequate notice of these claims and Applicants will be entitled to an adjustment under the provisions of Paragraph 29 below on the amount of water to which the wells are entitled.

17. Applicants may construct any well within 200 feet of the described locations without amending the Application or reopening this decree.

18. With respect to the permits to be issued by the State Engineer's office for construction of the wells described in Paragraph 7 herein, the provisions of Paragraph 34 below are and have been justified and shall apply.

19. As of March 3, 1986, Applicants have intended to the waters sought in the Application and have claim so demonstrated by open and physical acts on the ground and by the completion of engineering study an and hydrogeological investigation on the water available for appropriation in the Arapahoe Formation. Applicants have demonstrated and manifested an intent to appropriate the waters claimed herein by giving sufficient notice thereof, all in accordance with law. The evidence presented shows that the Applicants intend to appropriate the waters claimed herein, that such intent to appropriate has been adequately demonstrated, and that Applicants are entitled to a decree for the water rights herein decreed.

20. There is unappropriated water available for withdrawal by the structures decreed herein and the vested water rights of others will not be materially injured by the appropriations as decreed. Only that quantity of water underlying the Subject Lands has been considered to be unappropriated; the minimum useful life of the Arapahoe Formation is at least one hundred (100) years, assuming no substantial artificial recharge within one hundred (100) years; and no material injury to vested water rights will result from the issuance of or exercise of the permits for the subject wells.

CONCLUSIONS OF LAW

21. The Court has jurisdiction to determine Applicants' rights to nontributary ground water pursuant to Sections 37-90-137(6), 37-92-203(1), and 37-92-302 through 305, C.R.S. (Supp. 1985). The procedures and requirements of these statutes have been complied with, full and adequate notice has been given, and no additional notice is required.

22. The Court concludes as a matter of law that the Application herein is one contemplated by law. The Application for a decree confirming Applicants' right to divert and use ground water from the Arapahoe Formation beneath the Subject Lands, pursuant to C.R.S. § 37-90-137(4), should be granted, subject to the provisions of this decree. The rights confirmed by this decree are vested property rights. The amount of water confirmed in this decree is that quantity of water underlying the Subject Lands and the annual withdrawals are based on an aquifer life of one hundred years.

23. The Court concludes that the rights to ground water determined herein are not conditional water rights and subsequent showings or findings of reasonable diligence under Section 37-92-301(4), C.R.S., are inapplicable and need not be made. Accordingly, each of the water rights adjudicated herein is a final vested property right.

24. Applicants are entitled as a matter of law to use, reuse, and successively use to extinction and dispose of all nontributary ground water decreed herein pursuant to Section 37-82-106, C.R.S. (Supp. 1985) subject only to a 2% relinquishment of Applicants' right to total consumption. Failure to use, reuse or recapture such water, including return flows, shall not be deemed a forfeiture or abandonment of the right to such use, reuse or recapture.

25. The Court shall retain jurisdiction over this matter to make adjustments to the amount of water available for withdrawal annually to conform to the actual aquifer characteristics encountered upon the drilling of the wells. This retained jurisdiction may be invoked only by the parties under Paragraph 36.

- 7 -

JUDGMENT AND DECREE

26. The Findings of Fact and Conclusions of Law set forth in Paragraphs 1-25, above are incorporated herein by this reference.

27. The Application for determination of water rights for the subject wells is granted subject to the following limitations.

A right to five hundred seventy-five (575) acre-28. nontributary ground water per year is decreed and feet of confirmed in Applicants pursuant to § 37-90-137(4), C.R.S., for Dines Wells KA-1, KA-2, KA-3, and KA-4, from the Arapahoe Formation for municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation, exchange, replacement of depletions, augmentation, livestock and agricultural uses. Applicants shall have the right to recapture, reuse, and dispose of the water developed by the subject wells. Applicants shall have the right to withdraw water for immediate application to beneficial use and for storage and subsequent application to beneficial use and shall have the right to make any reuse, successive use or disposition of the developed water claimed herein to extinction free of any limitations. restrictions, or requirements as to the place of use, amount of discharge or location of discharge after such reuse, successive use or disposition in accord with Section 37-82-106, C.R.S. subject only to the provisions of Paragraph 31 below. The water may be withdrawn through the wells described in Paragraph 7 above and through such additional wells as may be required in order to maintain the annual appropriation as determined herein. The proposed withdrawals through Dines Wells KA-1, KA-2, KA-3, and KA-4 and any additional, supplemental, or replacement wells in the amount of 575 acre-feet per year, or in any additional amounts of water from the Arapahoe Formation underlying the Subject Lands, will not, within one hundred years, deplete the flow of any natural stream or its alluvium or any ground water tributary thereto at an annual rate greater than one-tenth of 1% annual rate of withdrawal, and those waters of the are nontributary to any natural surface stream, its alluvium, and any ground water tributary thereto, and the proposed withdrawals will not result in material injury to vested water rights.

29. The total amount of water to which Applicants are entitled and which is available to Applicants from the Arapahoe Formation beneath the Subject Lands shall be 575 acre-feet per year or the lesser or greater amount of water each such well is entitled to as subsequently determined from the saturated sand thickness of the Arapahoe Formation determined from the geophysical data obtained from the construction of the wells. Geophysical logs shall be taken in accordance with the applicable rules promulgated by the State Engineer. In making the determination of the final amount of water to which the subject wells are entitled, the following criteria shall apply:

(a) Saturated sand thickness shall be defined as the cumulative thickness of saturated materials as shown on the geophysical logs for each well applying standard accepted geophysical log interpretation methodology;

(b) The specific yield for the Arapahoe Formation shall be 17%;

(c) The water in the Arapahoe Formation underlying the 1410 acres of the Subject Lands shall be considered available for appropriation by the wells decreed herein.

After the completion of the wells subject to this decree, Applicants shall submit the geophysical logs and any other geophysical information obtained from the drilling of the wells to the State Engineer and to the other parties in this action together with a statement from Applicants on the final actual saturated sand thickness and final annual appropriation for each well as determined by Applicants. Within 60 days from the date on which Applicants mail copies of the geophysical logs and statement to the parties herein, any party may petition this Court to invoke the Court's retained jurisdiction under Paragraph 36 of this decree to reconsider the saturated sand thickness of the Arapahoe Formation underlying the Subject Lands for the purpose of adjusting the total entitlement of water to the wells decreed herein. Those proceedings shall be limited exclusively to the issue of saturated sand thickness. If the Court's retained jurisdiction is not invoked within the time prescribed in this Paragraph, the respective amounts set forth in Applicants' statement as the final annual entitlement to each well shall be final, which amount shall be confirmed as final by order of the Court upon Applicants' motion to the Court setting forth facts showing compliance with this Paragraph.

30. The issuance by the Colorado Division of Water Resources pursuant to Colorado Revised Statutes, Section 37-90-137(4) of permits to construct the subject wells is justified and the Division of Water Resources is directed to issue the permits in accordance with Paragraph 34 below. Each of the requirements of the statute has been complied with. Unappropriated waters are available for appropriation from the Arapahoe Formation beneath the Subject Lands and the proposed withdrawals will not result in material injury to other vested water rights. 31. Applicants shall relinquish the right to consume, after use, reuse, and successive use 2% of the water withdrawn through Dines Wells KA-1, KA-2, KA-3 and KA-4 and any additional, supplemental, or replacement wells without regard to dominion or control of the ground water so relinquished.

32. All of the wells described in Paragraph 7 may be used as original and alternate points of diversion for each other permitting the withdrawal by flow rate and volume of up to the full cumulative amount of water which may be lawfully withdrawn from all of those wells from any one or more of those wells. The Court finds that no material injury will result to the owners or persons entitled to use water under any vested water right or decreed conditional water right by the granting of this request, and it is hereby granted.

33. Applicants may withdraw more water than the final annual appropriation for each well so long as the sum of the withdrawals from all wells decreed herein (as that sum may subsequently be adjusted pursuant to Paragraph 29 hereof) does not exceed the product of the number of years since the date of issuance of this decree, times the annual rate of one percent (1%) of the total amount of unappropriated water recoverable from the Arapahoe Formation.

34. With respect to the permits to be issued by the State Engineer's office for construction of the wells described in Paragraph 7 herein, the following provisions shall apply.

(a) The State Engineer shall consider the rights granted herein as valid and shall consider the water sought by Applicants as taken and appropriated by Applicants.

(b) When Applicants are prepared to drill a well described in this decree, Applicants shall apply to the State Engineer for a well permit and that permit shall be issued within 60 days under terms and conditions no less stringent than those set forth in this decree with the conditions for equipping and constructing the well as are specified in Paragraph 35 herein. In the event that a well permit expires prior to the construction of the well and the application of water to beneficial use, Applicants may apply for a new well permit and the State Engineer shall within 60 days issue a new well permit with the same terms and conditions as the permit that expired.

(c) Applicants shall submit well permit applications to the State Engineer's office for any replacement, supplemental or additional wells.

(d) Any well permitted pursuant to this decree which is drilled within 200 feet of the decreed location shall be deemed to have been drilled at the decreed well location and shall not require application for a new or amended well permit.

(e) In determining whether good cause exists for granting a request by Applicants to extend well permits for nontributary wells for one or more additional oneyear periods pursuant to Section 37-90-137(3)(a)(II), C.R.S. (1985 Supp.), the State Engineer shall recognize that each well decreed herein, and such additional wells as are required from time to time to fully recover the annual appropriation herein, are part of a single integrated water supply system to be constructed over a phased period of time. So long as Applicants still desire to use the groundwater the well permits shall be extended.

(f) Prior to constructing any additional wells, Applicants shall submit well permit applications to the State Engineer. In considering such permit applications, the State Engineer shall be governed by Section 37-90-137(10), C.R.S. (1985 Supp.) and the provisions of this decree. Any such permitting action may be reviewed by this Court pursuant to Section 37-92-305(6), C.R.S. (1985 Supp.).

(g) For the purpose of well permit applications, Applicants need not submit separate proof, apart from the terms of this decree, of matters which have been determined herein.

35. Applicants shall geophysically log the entire bore hole of each well prior to the installation of casing. Such logs shall be taken in accordance with the applicable rules promulgated by the State Engineer. In constructing and maintaining any well which will withdraw water from the Arapahoe Formation under this decree, the Applicants shall seal off and encase the well with an impervious lining at all levels, except the level of the Arapahoe Formation, to prevent withdrawal of and mixing of groundwater in other aquifers and a totalizing flow meter shall be installed on each well. After construction the Applicants shall attach an identification tag to the well specifying the name of the well, the permit number and the aquifer from which the water is withdrawn. Applicants shall maintain records of the amounts pumped from each well on a monthly basis and such records shall be provided to the Division Engineer or the State Engineer on request.

36. This Court retains jurisdiction in this case for the reconsideration of the final amounts of water appropriated by the proposed wells in accord with Paragraph 29 above. The Court's retained jurisdiction may be invoked only by the Applicants and JVRC, Inc. The Court's retained jurisdiction may be invoked by written notice to the Court requesting a hearing. Copies of that notice will be served on the parties herein at their latest address of record in this case.

Dated this 29 day of 90t. , 1986.

BY THE COURT

Honorable John Tracey Water Judge Water Division No. 2 State of Colorado

APPROVED AS TO FORM AND SUBSTANCE:

SHERMAN & HOWARD

John L. DeWeerdt #9390

Kenneth L. Salazar #11648 Suite 2900 633 Seventeenth Street Denver, Colorado 80202

Telephone: (303) 297-2900

Attorneys for Applicants, The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines.

Sherman and Howard (Salazar) C: Vranesh & Raisch (Shimmin) Division Engineer State Engineer

VRANESH & RAISCH

Michael D. Shimmin, Post Office Box 871 Boulder, Colorado 80306 Telephone: (303) 443-6151 Attorneys for Objector JVRC, Inc.

Filad in the office of the Clerk, District Court Water Division No. 2, State of Colorado

OCT 29 1986

Priscieles Spress Clork

EXHIBIT A

The Subject Lands consist of the following:


The W1/2 W1/2 E1/2 and the E1/2 W1/2 and the SW1/4 SW1/4 of Section 27; the El/2 SEl/4 and that portion of the SW1/4 SEl/4 lying South and East of the County Road across said premises, both in Section 28; that portion of the SE1/4 SE1/4 of Section 32 lying South and East of said County Road, and that portion of the NEL/4 SEL/4 of said Section 32, lying South and East of said County Road; the El/2 and the El/2 SW1/4 and the SW1/4 SW1/4 of Section 33, and all that part of the NW1/4 of said Section 33 lying South and East of the said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road containing approximately 10 acres deeded to Colorado Interstate Gas Company by Warranty Deed recorded in Book 1173 at Page 359 of the El Paso County Records; and the W1/2 E1/2 and the W1/2 of Section 34, all in Township 12 South, Range 65 West of the 6th P.M., located in El Paso County, Colorado.

> Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

> > OCT 29 1986

Riscilles Adurers

Clerk



SCALE 1:24000

LOCATION MAP

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado OCT 29 1986 Friscilles) S. Lucers Clork

FIGURE 1

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

DISTRICT COURT, WATER DIVISION NO. 2, STATE OF COLORADO 0CT 29 1986

Case No. 86-CW-19

Risciel Artyrers

Clerk

FINDINGS OF FACT, CONCLUSIONS OF LAW, JUDGMENT AND DECREE

CONCERNING THE APPLICATION FOR NONTRIBUTARY GROUND WATER RIGHTS OF THE FIRST INTERSTATE BANK OF DENVER N.A., CARLA W. LEWIS, AND SAMUEL S. SHERMAN AS COTRUSTEES UNDER THE LIFE INSURANCE TRUST OF THOMAS M. DINES FROM THE LARAMIE-FOX HILLS AQUIFER, EL PASO COUNTY.

THIS MATTER, having come on for hearing before the real Court this $\underline{29}$ day of $\underline{6et.}$, 1986 upon the application of The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines ("Applicants") and the Court having considered the pleadings filed and the evidence presented, and being fully advised in the premises, hereby enters the following Findings of Fact, Conclusions of Law, and Judgment and Decree:

FINDINGS OF FACT

1. The Applicants are The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines whose address is First Interstate Bank of Denver, 633 Seventeenth Street, Denver, Colorado 80202, Attn: Jack Alexander. Applicants filed the application in this case styled Application For Nontributary Ground Water From The Laramie-Fox Hills Aquifer (the "Application") on March 28, 1986, seeking an adjudication of nontributary ground water rights from the Laramie-Fox Hills Aquifer underlying lands owned by Applicants in El Paso County.

2. Timely and adequate notice of the Application was published as required by statute, and the Court has jurisdiction over the subject matter of this proceeding and over all parties affected hereby, whether they have appeared or not. None of the lands or water rights involved in this case are within the boundaries of a designated groundwater basin.

3. A timely statement of opposition was filed by JVRC, Inc. No other statements of opposition were filed within the time provided by law nor did any other parties enter their appearance or intervene in these proceedings. 4. The Water Referee by Order dated July 19, 1986, under Section 37-92-303(2), C.R.S., rereferred the Application to the Water Judge for all further proceedings.

Jose T

5. The State Engineer issued a Determination of Facts on the Application, dated July 28, 1986, which has been filed with the Court. The Division Engineer adopted the Determination of Facts as his recommendations on August 8, 1986. The Determination of Facts and the findings contained therein have been reviewed and considered by this Court in accordance with Section 37-92-305(6), C.R.S.

6. Applicants seek an adjudication of rights to nontributary ground water from the Laramie-Fox Hills Aquifer beneath 1,410 acres of land in El Paso County which are described in Exhibit A and depicted on the map attached as Exhibit B, both of which are incorporated herein by this reference (the "Subject Lands"). Applicants are the owners of the Subject Lands and have the right to withdraw and use the waters from the Laramie-Fox Hills Aquifer underlying those lands. The waters claimed herein may be withdrawn through the proposed wells described in Paragraph 7 below and through such additional, replacement and supplemental wells as may be necessary to withdraw all of the water in the Laramie-Fox Hills Aquifer underlying the Subject Lands without causing material injury to any vested water right whose source of supply is the Arkansas River and any of its tributaries or any other natural stream, or any ground water tributary thereto, and the Applicants have so proven.

7. Applicants will divert the waters claimed herein from the Laramie-Fox Hills Aquifer through Dines Wells KLF-1, KLF-2, KLF-3, and KLF-4 more particularly described as follows:

Well Name: Dines Well KLF-1

- (a) In the SE 1/4 of the NW 1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., 2500 feet from the North Section line and 2300 feet from the West Section line, in El Paso County.
- (b) Depth: 2350 feet.
- (c) Source: Nontributary Laramie-Fox Hills Aquifer.
- (d) Pumping rate: 150 gpm.

(e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KLF-2

- (a) Location: In the SW 1/4 of the SW 1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., 100 feet from the South Section line and 100 feet from the West Section line, in El Paso County.
- (b) Depth: 2250 feet.
- (c) Source: Nontributary Laramie-Fox Hills Aquifer.
- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KLF-3

- (a) Location: In the NW 1/4 of the SE 1/4 of Section 33, Township 12 South, Range 65 West of the 6th P.M., 1400 feet from the South Section line and 2200 feet from the East Section line, in El Paso County.
- (b) Depth: 2150 feet.
- (c) Source: Nontributary Laramie-Fox Hills Aquifer.
- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KLF-4

- (a) Location: In the NE 1/4 of the SW 1/4 of Section 34, Township 12 South, Range 65 West of the 6th P.M., 1400 feet from the South Section line and 2200 feet from the West Section line, in El Paso County.
- (b) Depth: 2150 feet.
- (c) Source: Nontributary Laramie-Fox Hills Aquifer.

- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.
- * Not to exceed in total the amount available to Applicants from the Laramie-Fox Aquifer pursuant to § 37-90-137(4), C.R.S. and the provisions of this decree.

8. Pursuant to §37-90-137(4), C.R.S., five hundred thirty-nine (539) acre-feet of water per year are available to Applicants from the Laramie-Fox Hills Aquifer underlying the The average thickness of saturated sand of the Subject Lands. Laramie-Fox Hills Aquifer underlying the Subject Lands is 255 the final determination on actual saturated sand feet but thickness will be determined when the wells are drilled, and the amount decreed herein may be subsequently adjusted in accordance with that saturated sand thickness as provided in Paragraph 29 below. The specific yield of the Laramie-Fox Hills Aquifer is 15% in and beneath the Subject Lands. This finding is specific to the property involved and does not indicate or in any way reflect upon proper values for the subject aquifer elsewhere. All the water in the Laramie-Fox Hills Aquifer underlying the Subject Lands remains available for withdrawal by the wells decreed herein.

9. The State Engineer in his Determination of Facts found that 423 acre-feet per year were available for appropriation through the subject wells based on a specific yield of 15% and a saturated sand thickness of 200 feet for the Laramie-Fox Hill Aquifer beneath the Subject Lands. Applicants' engineer has testified that 539 acre-feet per year is available for appropriation calculated with a saturated sand thickness of 255 feet for the Laramie-Fox Hills Aquifer derived from a review of wells in the vicinity of the Subject Lands. Subject to the final determination of saturated sand thickness based on the information derived from the drilling of the wells, Applicants have shown by a preponderance of the evidence that the saturated sand thickness for the Laramie-Fox Hills Aquifer is 255 feet beneath the Applicants' property.

10. The source of water for the proposed wells is nontributary as defined in Section 37-90-103 (10.5), C.R.S. The proposed withdrawals through Dines Wells KLF-1, KLF-2, KLF-3, and KLF-4 in the amount of 539 acre-feet per year, or in any lesser or greater amount determined under Paragraph 29, will not, within one hundred years, deplete the flow of any natural stream or its alluvium or any ground water tributary thereto at an annual rate greater than one-tenth of 1% of the annual rate of withdrawal.

The waters of the Laramie-Fox Hills Aquifer that 11. are the subject of the appropriation claimed herein will be, and Applicants intend that they be used, and Applicants shall have right of succession of uses, for municipal, domestic, the commercial, fire protection, industrial, residential, recreation, irrigation, exchange, replacement of depletions, augmentation, livestock and agricultural uses. The water will be produced for immediate application to beneficial use and for storage and subsequent application to beneficial use. Subject only to the provisions of Paragraph 31, Applicants shall have the right to make any reuse, successive use or disposition of the developed claimed herein until totally consumed free water of any limitations, restrictions, or requirements as to the place of use, amount of discharge or location of discharge after such reuse, successive use or disposition in accord with Section 37-82-106, C.R.S.

12. All of the requirements of C.R.S. § 37-90-137(4), in effect on this date have been complied with, and the issuance of permits for the subject wells is justified and those permits will be issued as described in Paragraph 34 below.

13. Applicants will relinquish the right to consume after use, reuse, and successive use 2% of the amount of ground water withdrawn through Dines Wells KLF-1, KLF-2, KLF-3 and KLF-4 and any additional, supplemental, or replacement, wells without regard to dominion or control of the ground water so relinquished.

14. Applicants seek a decree designating all of the wells described in Paragraph 7 above as original and alternate points of diversion for each other permitting the withdrawal of up to the full cumulative amount by flow rate and volume of water which may be lawfully withdrawn from any one or more of those wells. The Court finds that no material injury will result to the owners or persons entitled to use water under any vested water right or decreed conditional water right by the granting of this request, and it is hereby granted.

15. Applicants may withdraw more water than the amounts set forth in Paragraph 8 so long as the sum of the withdrawals from all wells decreed herein (as that sum may subsequently be adjusted pursuant to Paragraph 29 hereof) does not exceed the product of the number of years since the date of this decree, times the annual rate of one percent (1%) of the total amount of unappropriated water recoverable from the Laramie-Fox Hills Aquifer.

16. Applicants have requested that the Court determine that Applicants have the right to withdraw all of the unappropriated water from the Larimie-Fox Hills Aquifer lying below their land and to increase their annual appropriations based upon the local aquifer characteristics established through information obtained from the drilling of the wells upon notice to all parties and approval by the Court, without amending the Application or republishing. The Court finds that there has been full and adequate notice of these claims and Applicants will be entitled to an adjustment under the provisions of Paragraph 29 below on the amount of water to which the wells are entitled.

17. Applicants may construct any well within 200 feet of the described locations without amending the Application or reopening this decree.

18. With respect to the permits to be issued by the State Engineer's office for construction of the wells described in Paragraph 7 herein, the provisions of Paragraph 34 below are and have been justified and shall apply.

19. As of March 3, 1986, Applicants have intended to claim the waters sought in the Application and have so demonstrated by open and physical acts on the ground and by the completion of an engineering study and hydrogeological investigation on the water available for appropriation in the Laramie-Fox Hills Aquifer. Applicants have demonstrated and manifested an intent to appropriate the waters claimed herein by giving sufficient notice thereof, all in accordance with law. The evidence presented shows that the Applicants intend to appropriate the waters that such claimed herein, intent to appropriate has been adequately demonstrated, and that Applicants are entitled to a decree for the water rights herein decreed.

20. There is unappropriated water available for withdrawal by the structures decreed herein and the vested water others rights of will not be materially injured by the appropriations as decreed. Only that quantity of water underlying the Subject Lands has been considered to be unappropriated; the minimum useful life of the Laramie-Fox Hills Aquifer is at least one hundred (100) years, assuming no substantial artificial recharge within one hundred (100) years; and no material injury to vested water rights will result from the issuance of or exercise of the permits for the subject wells.

CONCLUSIONS OF LAW

21. The Court has jurisdiction to determine Applicants' rights to nontributary ground water pursuant to Sections 37-90-137(6), 37-92-203(1), and 37-92-302 through 305, C.R.S. (Supp. 1985). The procedures and requirements of these statutes have been complied with, full and adequate notice has been given, and no additional notice is required. 22. The Court concludes as a matter of law that the Application herein is one contemplated by law. The Application for a decree confirming Applicants' right to divert and use ground water from the Laramie-Fox Hills Aquifer beneath the Subject Lands, pursuant to C.R.S. § 37-90-137(4), should be granted, subject to the provisions of this decree. The rights confirmed by this decree are vested property rights. The amount of water confirmed in this decree is that quantity of water underlying the Subject Lands and the annual withdrawals are based on an aquifer life of one hundred years.

23. The Court concludes that the rights to ground water determined herein are not conditional water rights and subsequent showings or findings of reasonable diligence under Section 37-92-301(4), C.R.S., are inapplicable and need not be made. Accordingly, each of the water rights adjudicated herein is a final vested property right.

24. Applicants are entitled as a matter of law to use, reuse, and successively use to extinction and dispose of all nontributary ground water decreed herein pursuant to Section 37-82-106, C.R.S. (Supp. 1985) subject only to a 2% relinquishment of Applicants' right to total consumption. Failure to use, reuse or recapture such water, including return flows, shall not be deemed a forfeiture or abandonment of the right to such use, reuse or recapture.

25. The Court shall retain jurisdiction over this matter to make adjustments to the amount of water available for withdrawal annually to conform to the actual aquifer characteristics encountered upon the drilling of the wells. This retained jurisdiction may be invoked only by the parties under Paragraph 36.

JUDGMENT AND DECREE

26. The Findings of Fact and Conclusions of Law set forth in Paragraphs 1-25, above are incorporated herein by this reference.

27. The Application for determination of water rights for the subject wells is granted subject to the following limitations.

28. A right to five hundred thirty-nine (539) acrefeet of nontributary ground water per year is decreed and confirmed in Applicants pursuant to § 37-90-137(4), C.R.S., for Dines Wells KLF-1, KLF-2, KLF-3, and KLF-4, from the Laramie-Fox Hills Aquifer for municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation,

exchange, replacement of depletions, augmentation, livestock and agricultural uses. Applicants shall have the right to recapture, reuse, and dispose of the water developed by the subject wells. Applicants shall have the right to withdraw water for immediate application to beneficial use and for storage and subsequent application to beneficial use and shall have the right to make any reuse, successive use or disposition of the developed water herein claimed extinction free of to limitations, any restrictions, or requirements as to the place of use, amount of discharge or location of discharge after such reuse, successive use or disposition in accord with Section 37-82-106, C.R.S. subject only to the provisions of Paragraph 31 below. The water may be withdrawn through the wells described in Paragraph 7 above and through such additional wells as may be required in order to maintain the annual appropriation as determined herein. The proposed withdrawals through Dines Wells KLF-1, KLF-2, KLF-3, and KLF-4 and any additional, supplemental, or replacement wells in the amount of 539 acre-feet per year, or in any additional amounts of water from the Laramie-Fox Hills Aquifer underlying the Subject Lands, will not, within one hundred years, deplete the flow of any natural stream or its alluvium or any ground water tributary thereto at an annual rate greater than one-tenth of 1% of the annual rate of withdrawal, and is nontributary to any natural surface stream, its alluvium, and any ground water tributary thereto, and the proposed withdrawals will not result in material injury to vested water rights.

29. The total amount of water to which Applicants are entitled and which is available to Applicants from the Laramie-Fox Hills Aquifer beneath the Subject Lands shall be 539 acrefeet per year or the lesser or greater amount of water each such well is entitled to as subsequently determined from the saturated sand thickness of the Laramie-Fox Hills Aquifer determined from the qeophysical data obtained from the construction of the wells. Geophysical logs shall be taken in accordance with the applicable rules promulgated by the State Engineer. In making the determination of the final amount of water to which the subject wells are entitled, the following criteria shall apply:

(a) Saturated sand thickness shall be defined as the cumulative thickness of saturated materials as shown on the geophysical logs for each well applying standard accepted geophysical log interpretation methodology;

(b) The specific yield for the Laramie-Fox Hills Aquifer shall be 15%;

(c) The water in the Laramie-Fox Hills Aquifer underlying the 1410 acres of the Subject Lands shall be considered available for appropriation by the wells decreed herein.

After the completion of the wells subject to this decree, Applicants shall submit the geophysical logs and any other geophysical information obtained from the drilling of the wells to the State Engineer and to the other parties in this action together with a statement from Applicants on the final actual saturated sand thickness and final annual appropriation for each well as determined by Applicants. Within 60 days from the date on which Applicants mail copies of the geophysical logs and statement to the parties herein, any party may petition this Court to invoke the Court's retained jurisdiction under Paragraph 36 of this decree to reconsider the saturated sand thickness of the Laramie-Fox Hills Aquifer underlying the Subject Lands for the purpose of adjusting the total entitlement of water to the wells decreed herein. Those proceedings shall be limited exclusively to the issue of saturated sand thickness. If the Court's retained jurisdiction is not invoked within the time prescribed in this Paragraph, the respective amounts set forth in Applicants' statement as the final annual entitlement to each shall be final, which amount shall be confirmed as final by well order of the Court upon Applicants' motion to the Court setting forth facts showing compliance with this Paragraph.

30. The issuance by the Colorado Division of Water Resources pursuant to Colorado Revised Statutes, Section 37-90-137(4) of permits to construct the subject wells is justified and the Division of Water Resources is directed to issue the permits in accordance with Paragraph 34 below. Each of the requirements of the statute has been complied with. Unappropriated waters are available for appropriation from the Laramie-Fox Hills Aquifer beneath the Subject Lands and the proposed withdrawals will not result in material injury to other vested water rights.

31. Applicants shall relinquish the right to consume, after use, reuse, and successive use 2% of the water withdrawn through Dines Wells KLF-1, KLF-2, KLF-3 and KLF-4 and any additional, supplemental, or replacement wells without regard to dominion or control of the ground water so relinquished.

32. All of the wells described in Paragraph 7 may be used as original and alternate points of diversion for each other permitting the withdrawal by flow rate and volume of up to the full cumulative amount of water which may be lawfully withdrawn from all of those wells from any one or more of those wells. The Court finds that no material injury will result to the owners or persons entitled to use water under any vested water right or decreed conditional water right by the granting of this request, and it is hereby granted.

33. Applicants may withdraw more water than the final annual appropriation for each well so long as the sum of the withdrawals from all wells decreed herein (as that sum may subsequently be adjusted pursuant to Paragraph 29 hereof) does not exceed the product of the number of years since the date of issuance of this decree, times the annual rate of one percent (1%) of the total amount of unappropriated water recoverable from the Laramie-Fox Hills Aquifer.

34. With respect to the permits to be issued by the State Engineer's office for construction of the wells described in Paragraph 7 herein, the following provisions shall apply.

(a) The State Engineer shall consider the rights granted herein as valid and shall consider the water sought by Applicants as taken and appropriated by Applicants.

(b) When Applicants are prepared to drill a well described in this decree, Applicants shall apply to the State Engineer for a well permit and that permit shall be issued within 60 days under terms and conditions no less stringent than those set forth in this decree with the conditions for equipping and constructing the well as are specified in Paragraph 35 herein. In the event that a well permit expires prior to the construction of the well and the application of water to beneficial use, Applicants may apply for a new well permit and the State Engineer shall within 60 days issue a new well permit with the same terms and conditions as the permit that expired.

(c) Applicants shall submit well permit applications to the State Engineer's office for any replacement, supplemental or additional wells.

(d) Any well permitted pursuant to this decree which is drilled within 200 feet of the decreed location shall be deemed to have been drilled at the decreed well location and shall not require application for a new or amended well permit.

(e) In determining whether good cause exists for granting a request by Applicants to extend well permits for nontributary wells for one or more additional oneyear periods pursuant to Section 37-90-137(3)(a)(II), C.R.S. (1985 Supp.), the State Engineer shall recognize that each well decreed herein, and such additional wells as are required from time to time to fully recover the annual appropriation herein, are part of a single integrated water supply system to be constructed over a phased period of time. So long as Applicants still desire to use the groundwater the well permits shall be extended.

(f) Prior to constructing any additional wells, Applicants shall submit well permit applications to the State Engineer. In considering such permit applications, the State Engineer shall be governed by Section 37-90-137(10), C.R.S. (1985 Supp.) and the provisions of this decree. Any such permitting action may be reviewed by this Court pursuant to Section 37-92-305(6), C.R.S. (1985 Supp.).

(g) For the purpose of well permit applications, Applicants need not submit separate proof, apart from the terms of this decree, of matters which have been determined herein.

35. Applicants shall geophysically log the entire bore hole of each well prior to the installation of casing. Such logs shall be taken in accordance with the applicable rules promulgated by the State Engineer. In constructing and maintaining any well which will withdraw water from the Laramie-Fox Hills Aquifer under this decree, the Applicants shall seal off and encase the well with an impervious lining at all levels, except the level of the Laramie-Fox Hills Aquifer, to prevent withdrawal of and mixing of groundwater in other aquifers and a totalizing flow meter shall be installed on each well. After construction the Applicants shall attach an identification tag to the well specifying the name of the well, the permit number and the aquifer from which the water is withdrawn. Applicants shall maintain records of the amounts pumped from each well on a monthly basis and such records shall be provided to the Division Engineer or the State Engineer on request.

36. This Court retains jurisdiction in this case for the reconsideration of the final amounts of water appropriated by the proposed wells in accord with Paragraph 29 above. The Court's retained jurisdiction may be invoked only by the Applicants and JVRC, Inc. The Court's retained jurisdiction may be invoked by written notice to the Court requesting a hearing. Copies of that notice will be served on the parties herein at their latest address of record in this case.

Dated this 29 day of Oct., 1986.

BY THE COURT

Honorable John Tracey Water Judge Water Division No. 2 State of Colorado

APPROVED AS TO FORM AND SUBSTANCE:

SHERMAN & HOWARD

John L. DeWeerdt #9390

Kenneth L. Salazar #11648 Suite 2900 633 Seventeenth Street Denver, Colorado 80202

Telephone: (303) 297-2900

Attorneys for Applicants, The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines.

c: Sherman and Howard (Salazar) Vranesh & Raisch (Shimmin) Division Engineer State Engineer VRANESH & RAISCH

By: / 4

Michael D. Shimmin, #9182 Post Office Box 871 Boulder, Colorado 80306 Telephone: (303) 443-6151 Attorneys for Objector JVRC, Inc.

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

OCT 29 1986

Riscieles & Surero

EXHIBIT A

The Subject Lands consist of the following:


The W1/2 W1/2 E1/2 and the E1/2 W1/2 and the SW1/4 SW1/4 of Section 27; the El/2 SEl/4 and that portion of the SWl/4 SEl/4 lying South and East of the County Road across said premises, both in Section 28; that portion of the SE1/4 SE1/4 of Section 32 lying South and East of said County Road, and that portion of the NE1/4 SE1/4 of said Section 32, lying South and East of said County Road; the E1/2 and the E1/2 SW1/4 and the SW1/4 SW1/4 of Section 33, and all that part of the NW1/4 of said Section 33 lying South and East of the said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road containing approximately 10 acres deeded to Colorado Interstate Gas Company by Warranty Deed recorded in Book 1173 at Page 359 of the El Paso County Records; and the W1/2 E1/2 and the W1/2 of Section 34, all in Township 12 South, Range 65 West of the 6th P.M., located in El Paso County, Colorado.

> ciled in the office of the Clerk, District Court Water Division No. 2, State of Colorado

> > OCT 29 1986

Riscille Adurero Cierk

A-1



SCALE 1:24000

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

OCT 29 1986

Priseiles & Lyners Clerk

FIGURE 1

LOCATION MAP

2170623135/31/2017 10:16 AMPGS 16\$88.00DF \$0.00Electronically Recorded Official Records El Paso County COChuck Broerman, Clerk and RecorderTD1000N

DISTRICT COURT	, WATER	DIVISION 2,	COLORADO
----------------	---------	--------------------	----------

Court Address: 501 North Elizabeth Street, Suite 116 Pueblo, CO 81003

CONCERNING THE APPLICATION FOR WATER RIGHTS OF:

ARROYA INVESTMENTS, LLC, JACOB DECOTO, MARVIN ORNES and TERRI WAHLBERG

CASE NUMBER: 2017CW3002

DATE FILED: May 31, 2017 9:37 AM

▲ COURT USE ONLY ▲

Case No.: 17CW3002

IN EL PASO COUNTY

FINDINGS OF FACT, CONCLUSIONS OF LAW, RULING OF REFEREE AND DECREE

THIS MATTER comes before the Water Referee on the Application filed by Arroya Investments, LLC, Jacob Decoto, Marvin Ornes and Terri Wahlberg, and having reviewed said Application and other pleadings on file, and being fully advised on this matter, the Water Referee makes the following findings and orders:

GENERAL FINDINGS OF FACT

1. The applicants in this case are Arroya Investments, LLC ("Arroya"), Jacob Decoto ("Decoto"), Marvin Ornes ("Ornes") and Terri Wahlberg ("Wahlberg") (collectively, "Applicants"). Applicants are, collectively, the owners of the four separately owned parcels of land totaling approximately 335.59 acres under which the groundwater sought to be adjudicated herein are located, and are likewise the owners of the place of use where the water is anticipated to be put to beneficial use.

2. The Applicants filed this Application with the Water Court for Water Division 2 on January 31, 2017. The Application was referred to the Water Referee by order of the Court dated February 2, 2017.

3. The time for filing statements of opposition to the Application expired on the last day of March, 2017, and a no statements of opposition were timely filed.

4. On February 2, 2017, the Division 2 Water Court ordered that publication occur in the *Daily Transcript* within El Paso County.

5. The Clerk of this Court has caused publication of the Application filed in this matter as provided by statute and the publication costs have been paid. On February 15, 2017, proof of publication in the *Daily Transcript* was filed with the Court. All notices of the Application have been given in the manner required by law.

6. Pursuant to C.R.S. §37-92-302(2), the Office of the State Engineer has filed Determination of Facts for each aquifer with this Court dated March 14, 2017.

7. Pursuant to C.R.S. §37-92-302(4), the office of the Division Engineer for Water Division 2 filed its Consultation Report dated March 29, 2017, with the Court. The Consultation Report has been considered by the Water Referee in the entry of this Ruling.

8. The Water Court has jurisdiction over the subject matter of these proceedings and over all who have standing to appear as parties whether they have appeared or not. The land and water rights involved in this case are not within a designated groundwater basin.

GROUNDWATER RIGHTS

9. The Applicants requested the adjudication and quantification all Denver Basin groundwater in each aquifer underlying the four (4) specifically described parcels of land owned by each of the Applicants, respectively, as described herein. No plan for augmentation for the use of the not-nontributary groundwater was sought or is decreed herein. The Applicants shall construct such wells as necessary for withdrawal of Applicants' full entitlements of water supplies decreed herein. The following findings are made with respect to such underground water rights:

A. <u>Property Description</u>. All wells to all aquifers will be located on the Applicants respective properties. Such Properties are more specifically described as follows:

i. <u>Arroya Parcel</u>. The "Arroya Parcel" is an approximately 226 acre parcel located in the SE1/4 SE1/4 of Section 21, the W1/2 SW1/4 of Section 22, the E1/2 NE1/4 of Section 28, the W1/2 NW1/4 and the NW1/4 SW1/4 of Section 27, all in Township 21 South, Range 65 West of the 6th P.M., El Paso County, Colorado, as more particularly described on attached **Exhibit A**, and depicted on attached **Exhibit E**. The Arroya Parcel is owned by Applicant Arroya Investments, LLC.

ii. <u>West Parcel No. 1</u>. The "West Parcel No. 1" is an approximately 36.01 acre parcel located in the SW1/4 SE1/4 and the SE1/4 SE1/4 of Section 21, and the NE1/4 NE1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., El Paso County, Colorado, as more particularly described on attached **Exhibit B**, and depicted on attached **Exhibit E**. The West Parcel No. 1 is owned by Applicant Jacob Decoto.

iii. <u>West Parcel No. 2</u>. The "West Parcel No. 2" is an approximately 36.03 acre parcel located in the SW1/4 SE1/4 and the SE1/4 SE1/4 of Section 21, Township 12 South, Range 65 West of the 6th P.M., El Paso County, Colorado, as more particularly described on attached **Exhibit C**, and depicted on attached **Exhibit E**. The West Parcel No. 2 is owned by Applicant Jacob Decoto.

iv. <u>West Parcel No. 3</u>. The "West Parcel No. 3" is an approximately 37.58 acre parcel located in the NW1/4 SE1/4 and the NE1/4 SE1/4 of Section 21, Township 12 South, Range 65 West of the 6th P.M., El Paso County, Colorado, as more particularly described on attached **Exhibit D**, and depicted on attached **Exhibit E**. The West Parcel No. 3 is owned by Applicants Marvin Ornes and Terri Wahlberg.

B. <u>Existing Wells</u>. There is currently one (1) existing well constructed to the Dawson aquifer on West Parcel No. 2 (Decoto): DWR Permit No. 4554, an exempt domestic well. DWR Permit No. 4554 is an exempt structure; water from the Dawson aquifer sufficient to allow for such continued exempt use has been excluded from the quantification herein. Two additional exempt domestic wells have been permitted since the filing of the application in this matter, DWR Permit No. 304551 on West Parcel No. 1 (Decoto), and DWR Permit No. 304498 on West Parcel No. 3 (Ornes/Wahlberg), and are excluded from quantification herein.

C. <u>Additional Wells</u>. Applicants anticipated additional wells will be constructed on each the Applicants' respective properties. To the extent any additional wells may be constructed to the not-nontributary Dawson and/or Denver aquifer(s), such wells may be constructed only pursuant to a subsequent decree providing an approved plan for augmentation, or as exempt well structures pursuant to C.R.S. §37-92-602.

10. Of the statutorily described Denver Basin aquifers, the Dawson, Denver, Arapahoe, and Laramie-Fox Hills aquifers all exist beneath the Applicants' respective properties. The Dawson and Denver aquifers contain not-nontributary water, while the water of the Arapahoe and Laramie-Fox Hills aquifers underlying the Applicants' respective properties is nontributary. The quantity of water in the Denver Basin aquifers exclusive of artificial recharge underlying each of the Applicants' respective properties as allocated on a pro-rata per acre basis from the amounts described in the State Engineer's Determination of Facts, is as follows:

Aquifer	Sand Thickness (Feet)	Total Ground Water Storage (Acre Feet)	Annual Average Withdrawal – 100 Years (Acre Feet)
Dawson (NNT)	270	12,202	122
Denver (NNT)	310	11,909	119.1
Arapahoe (NT)	255	9,796	98
Laramie-Fox Hills (NT)	190	6,440	64.4

	Α.	<u>Arroya</u>	Parcel	(225.97	acres)	:
--	----	---------------	--------	---------	--------	---

Aquifer	Sand Thickness (Feet)	Total Ground Water Storage (Acre Feet)	Annual Average Withdrawal – 100 Years (Acre Feet)
Dawson (NNT)	270	1,944.4	16.44 ¹
Denver (NNT)	310	1,897.7	18.98
Arapahoe (NT)	255	1,561	15.61
Laramie-Fox Hills (NT)	190	1,026.2	10.26

B. <u>West Parcel No. 1 (Decoto – 36.01 acres)</u>:

C. <u>West Parcel No. 2 (Decoto – 36.03 acres)</u>:

Aquifer	Sand Thickness (Feet)	Total Ground Water Storage (Acre Feet)	Annual Average Withdrawal – 100 Years (Acre Feet)
Dawson (NNT)	270	1,945.4	16.45 ²
Denver (NNT)	310	1,898.8	18.99
Arapahoe (NT)	255	1,562	15.62
Laramie-Fox Hills (NT)	190	1,026.8	10.27

D. West Parcel No. 3 (Ornes & Wahlberg – 37.58 acres):

Aquifer	Sand Thickness (Feet)	Total Ground Water Storage (Acre Feet)	Annual Average Withdrawal – 100 Years (Acre Feet)
Dawson (NNT)	270	2,029.2	17.29 ³
Denver (NNT)	310	1,980.5	19.80
Arapahoe (NT)	255	1,629	16.29
Laramie-Fox Hills (NT)	190	1,071	10.7

¹ Three (3) annual acre feet of Dawson groundwater has been reserved from quantification herein for permitting of an exempt domestic well on this parcel pursuant to C.R.S. §37-92-602, *et seq.*, recently permitted as DWR Permit No. 304551.

² Three (3) annual acre feet of Dawson groundwater has been reserved from quantification herein for continued use of DWR Permit No. 4554 as an exempt domestic well on this parcel pursuant to C.R.S. \$37-92-602, et seq.

³ Three (3) annual acre feet of Dawson groundwater has been reserved from quantification herein for permitting of an exempt domestic well on this parcel pursuant to C.R.S. §37-92-602, et seq., recently permitted as DWR Permit No. 304498.

11. Pursuant to \$37-90-137(9)(c.5)(I), C.R.S., the augmentation requirements for wells in the Dawson aquifer require the replacement to the effected stream systems of actual stream depletions on an annual basis, to the extent necessary to prevent injurious effect, based upon actual aquifer conditions. The augmentation requirements for wells to the Denver aquifer are for 4% of pumping. Applicants shall not be entitled to construct a non-exempt well or use water from the not-nontributary Dawson or Denver aquifers except pursuant to an approved augmentation plan in accordance with C.R.S. \$37-90-137(9)(c.5).

12. Applicants shall be entitled to withdraw all legally available groundwater in the Denver Basin aquifers underlying Applicants' respective properties. Said amounts can be withdrawn over the 100-year life for the aquifers as set forth in C.R.S. §37-90-137(4), or withdrawn over a longer period of time based upon local governmental regulations or Applicants' water needs. The average annual amounts of ground water available for withdrawal from the underlying Denver Basin aquifers, based upon the 100-year aquifer life is determined and set forth above, based upon the March 14, 2017 Office of the State Engineer Determination of Facts. Such groundwater may be withdrawn from wells located upon the overlying land or contiguous properties with such contiguity to allow such withdrawal, consistent with the Denver Basin Rules as promulgated by the Office of the State Engineer, as may be amended from time to time.

13. Applicants shall be entitled to withdraw an amount of groundwater in excess of the average annual amount decreed herein from the Denver Basin aquifers underlying Applicants' respective properties, so long as the sum of the total withdrawals from wells in the aquifer does not exceed the product of the number of years since the date of issuance of the original well permit or the date of entry of the decree herein, whichever comes first, and the annual volume of water which Applicants are entitled to withdraw from the aquifer underlying Applicants' respective properties.

The Applicants shall have the right to use the ground water for beneficial 14. uses on or off the Applicants' respective properties consisting of domestic, commercial, irrigation, stock water, recreation, wildlife, wetlands, fire protection, piscatorial, and for storage and augmentation associated with such uses. The amount of groundwater decreed for such uses upon the Applicants' respective properties is reasonable as such uses are to be made for the long term use and enjoyment of the Applicants' respective properties and are to establish and provide for adequate water reserves. The nontributary groundwater, may be used, reused, and successively used to extinction, both on and off the Applicants' respective properties subject, however, to the relinquishment of the right to consume two percent of such nontributary water withdrawn. Applicants may use such water by immediate application or by storage and subsequent application to the beneficial uses and purposes stated herein. Provided however, as set forth above, Applicants shall only be entitled to construct a non-exempt well or use water from the not-nontributary Dawson and Denver aquifers pursuant to a decreed augmentation plan entered by the Court. Withdrawals of groundwater available from the nontributary aquifers beneath the Applicants' respective properties in the amounts determined in accordance with the provisions of this decree will not result in material injury to any other vested water rights or to any other owners or users of water.

15. Applicants may construct such wells on their respective properties as necessary for the withdrawal of all entitlements from each aquifer as described above, and such withdrawals may be made through any combination of wells. As to each of Applicants' respective properties, these wells shall be treated as a well field.

CONCLUSIONS OF LAW

16. The application for adjudication of Denver Basin groundwater was filed with the Water Clerk for Water Division 2 pursuant to C.R.S. \$37-92-302(1)(a) and 37-90-137(9)(c).

17. The Applicants' request for adjudication of these water rights is contemplated and authorized by law, and this Court and the Water Referee have exclusive jurisdiction over these proceedings. C.R.S. §§37-92-302(1)(a), 37-92-203, and 37-92-305.

18. Subject to the terms of this decree, the Applicants are entitled to the sole right to withdraw all the legally available water in the Denver Basin aquifers underlying the Applicants' respective properties, and the right to use that water to the exclusion of all others subject to the terms of this decree.

19. The Applicants have complied with C.R.S. §37-90-137(4), and the groundwater is legally available for withdrawal by the requested nontributary well(s), and legally available for withdrawal by the requested not-nontributary well(s) upon the entry of a subsequent decree approving an augmentation plan pursuant to C.R.S. §37-90-137(9)(c.5). Applicants are entitled to a decree from this Court confirming their rights to withdraw groundwater pursuant to C.R.S. §37-90-137(4).

20. The Denver Basin water rights applied for in this case are not conditional water rights, but are vested water rights determined pursuant to C.R.S. §37-90-137(4). No applications for diligence are required. The claims for nontributary and not-nontributary groundwater meet the requirements of Colorado Law.

21. The determination and quantification of the nontributary and notnontributary groundwater rights in the Denver Basin aquifers as set forth herein is contemplated and authorized by law. C.R.S. §§37-90-137, and 37-92-302 through 37-92-305.

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED AS FOLLOWS:

22. All of the foregoing Findings of Fact and Conclusions of Law are incorporated herein by reference, and are considered to be a part of this decretal portion as though set forth in full.

23. The Application for Adjudication of Denver Basin Groundwater proposed by the Applicants is approved, subject to the terms of this decree.

24. The Applicants have furnished acceptable proof as to all claims and, therefore, the Application for Adjudication of Groundwater as requested by the Applicants is granted and approved in accordance with the terms and conditions of this decree. Approval of this Application will not result in any material injury to senior vested water rights.

25. The Applicants shall comply with C.R.S. §37-90-137(9)(b), requiring the relinquishment of the right to consume two percent (2%) of the amount of the nontributary groundwater withdrawn. Ninety-eight percent (98%) of the nontributary groundwater withdrawn may therefore be consumed. No plan for augmentation shall be required to provide for such relinquishment.

26. The Court retains jurisdiction over this matter to make adjustments in the allowed average annual amount of withdrawal from the Denver Basin aquifers, either upwards or downwards, to conform to actual local aquifer characteristic, and that the Applicants need not refile, republish, or otherwise amend this application to request such adjustments.

A. At such time as adequate data may be available, Applicant or the State Engineer may invoke the Court's retained jurisdiction as provided in this Paragraph 26 for purposes of making a final determination of water rights as to the quantities of water available and allowed average annual withdrawals from any of the Denver Basin aquifers quantified and adjudicated herein. Any person seeking to invoke the Court's retained jurisdiction for such purpose shall file a verified petition with the Court setting forth with particularity the factual basis for such final determination of Denver Basin water rights under this decree, together with the proposed decretal language to effect the petition. Within four months of the filing of such verified petition, the State Engineer's Office shall utilize such information as available to make a final determination of water rights finding, and shall provide such information to the Court, Applicant, and the petitioning party.

B. If no protest is filed with the Court to such findings by the State Engineer's Office within sixty (60) days, this Court shall incorporate by entry of an Amended Decree such "final determination of water rights", and the provisions of this Paragraph 26 concerning adjustments to the Denver Basin ground water rights based upon local aquifer conditions shall no longer be applicable. In the event of a protest being timely filed, or should the State Engineer's Office make no timely determination as provided in Paragraph 26.A., above, the "final determination of water rights" sought in the petition may be made by the Water Court after notice to all parties and following a full and fair hearing, including entry of an Amended Decree, if applicable in the Court's reasonable discretion.

27. Pursuant to C.R.S. §37-92-502(5)(a), the Applicants shall install and maintain such water measurement devices and recording devices as are deemed essential by the State Engineer or Division Engineers, and the same shall be installed and operated in accordance with instructions from said entities. Applicants are to install and maintain a totalizing flow meter on all wells, and any additional or replacement wells. Applicants are also to maintain records and provide reports to the State Engineer or Division Engineers as instructed by said entities, on at least an annual basis.

28. The vested water rights and water right structures decreed herein shall be subject to all applicable administrative rules and regulations, as currently in place or as may in the future be promulgated, of the offices of Colorado State and Division Engineers for administration of such water rights, to the extent such rules and regulations are uniformly applicable to other similarly situated water rights and water users.

29. This Ruling of Referee, when entered as a decree of the Water Court, shall be recorded in the real property records of El Paso County, Colorado. Copies of this ruling shall be mailed as provided by statute.

DATED THIS 5th day of May, 2017.

BY THE REFEREE:



Marado R. Di Dominico

Mardell R. DiDomenico, Water Referee Water Division 2

DECREE

THE COURT FINDS THAT NO PROTEST WAS MADE IN THIS MATTER, THEREFOR THE FORGOING RULING IS CONFIRMED AND APPROVED, AND IS HEREBY MADE THE JUDGMENT AND DECREE OF THIS COURT.

Dated: May 31, 2017.



BY THE COURT:

LARRY C SCHWARTZ, WATER JUDGE WATER DIVISION 2

EXHIBIT A

LEGAL DESCRIPTION – ARROYA PARCEL

A PARCEL OF LAND LOCATED IN A PORTION OF THE SOUTHEAST ONE-QUARTER (SE1/4) OF SECTION 21 AND A PORTION OF THE SOUTHWEST ONE-QUARTER OF SECTION 22, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30°E. A DISTANCE OF 3925.63 FEET;

COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27; THENCE S88°38'56"W ALONG THE NORTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4), A DISTANCE OF 1047.88 FEET TO THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREIN DESCRIBED;

THENCE S88°38'56"W CONTINUING ALONG SAID NORTH LINE, A DISTANCE OF 283.03 FEET TO THE NORTHWEST CORNER OF SAID SECTION 27 SAID POINT ALSO BEING A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 431 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER;

THENCE ALONG THE EASTERLY AND NORTHERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING TWO (2) COURSES:

1. N00°37'14"W SAID LINE ALSO BEING THE WEST LINE OF THE SOUTHWEST ONE-QUARTER (SW1/4) OF SAID SECTION 22, A DISTANCE OF 30.00 FEET; 2. S89°40'23"W, A DISTANCE OF 736.82 FEET TO THE POINT OF INTERSECTION OF THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 430 OF SAID COUNTY RECORDS;

THENCE N21°41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1798.07 FEET;

THENCE N59°58'50'E, A DISTANCE OF 694.83 FEET; THENCE S14°30'58"E, A DISTANCE OF 567.09 FEET; THENCE N69°36'18"E, A DISTANCE OF 603.87 FEET; THENCE S30°23'46"E, A DISTANCE OF 264.58 FEET; THENCE S61°52'38"W, A DISTANCE OF 227.40 FEET;

THENCE S79°15'47"W, A DISTANCE OF 276.17 FEET; THENCE S89°39'18"W, A DISTANCE OF 356.07 FEET; THENCE S40°09'47"W, A DISTANCE OF 310.61 FEET; THENCE S09°56'46"W, A DISTANCE OF 270.03 FEET; THENCE S35°00'25"W, A DISTANCE OF 167.38 FEET; THENCE S57°24'01"W, A DISTANCE OF 235.36 FEET; THENCE S27°23'34"E, A DISTANCE OF 611.29 FEET TO THE POINT OF BEGINNING; SAID PARCEL OF LAND CONTAINS A CALCULATED AREA OF 35.08 ACRES OF LAND, MORE OR LESS.

Along With:

A PARCEL OF LAND BEING THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27, THE SOUTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (SW1/4 NW1/4) OF SECTION 27, THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SECTION 27, A PORTION OF THE SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER OF SECTION 28 AND A PORTION OF THE NORTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (NE1/4 NE1/4) OF SECTION 28, ALL IN TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30"E, A DISTANCE OF 3925.63 FEET;

COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27, SAID POINT ALSO BEING THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREIN DESCRIBED;

THENCE S00°54'30"E ALONG THE EAST LINE OF THE WEST ONE-HALF (W1/2) OF SAID SECTION 27, A DISTANCE OF 3925.63 FEET TO THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER NW1/4 SW1/4) OF SAID SECTION 27,

THENCE S87°35'00"W ALONG THE SOUTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4), A DISTANCE OF 1332.78 FEET TO THE SOUTHWEST CORNER OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4);

THENCE N00°53'18"W ALONG THE WEST LINE OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4), A DISTANCE OF 1316.78 FEET TO THE NORTHWEST CORNER OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4);

THENCE S89°08'28"W ALONG THE SOUTH LINE OF THE SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4) OF SECTION 28, A DISTANCE OF 1326.68 FEET TO THE SOUTHWEST CORNER OF SAID SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4);

THENCE N00°30'49"W ALONG THE WEST LINE OF SAID SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4), A DISTANCE OF 1270.77 FEET TO A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN

BOOK 2678 AT PAGE 430 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER;

THENCE N21°41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1450.84 FEET TO THE POINT OF INTERSECTION OF THE SOUTHERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 431 OF SAID COUNTY RECORDS;

THENCE ALONG THE SOUTHERLY AND EASTERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING TWO (2) COURSES:

1. N89°40'23"E, A DISTANCE OF 761.52 FEET TO A POINT ON THE EAST LINE OF SAID NORTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (NE1/4 NE1/4); 2. N00°52'58"W ALONG SAID EAST LINE, A DISTANCE OF 30.00 FEET TO THE NORTHWEST CORNER OF SAID SECTION 27;

THENCE N88°38'56''E ALONG THE NORTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4), A DISTANCE OF 1330.91 FEET TO THE POINT OF BEGINNING;

SAID PARCEL OF LAND CONTAINS A CALCULATED AREA OF 190.89 ACRES OF LAND, MORE OR LESS.

EXHIBIT B

LEGAL DESCRIPTION TRAILS AT TIMBERLINE WEST PARCEL 1:

A PARCE, OF LAND LOCATED IN A PORTION OF THE SOUTHEAST ONE-QUARTER (SE1/4) OF SECTION 21 AND A PORTION OF THE NORTHCAST ONE-QUARTER (NE1/4) OF SECTION 28, TOMNSHIP 12 SOUTH, HANGE 65 MEST OF THE 5TH P.M., EL PASO DOWNLY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS.

SASIS OF BEARINCS: THE WEST CIRE OF THE SOUTHEAST ONE-QUARTER (SET/4) OF SECTION 21, TOWNSHP 12 SOUTH, RANCE OS WEST IS ASSUMED TO BEAR NOR25732%, A DISTANCE OF 2638.53 FEET.

COMMENSION AT THE REATHINGST CORRECT OF DAID SOUTHEAST ONE-OLARTER (3E1/*) SAID FORT ALSO BEING THE POINT OF BECKNING OF THE PARCEL OF LAND HEREIN DESCRIBED: THENCE NDC25'32'W ALGOLG THE WEST LINE OF SAID SOUTHEAST ONE-QUARTER (SEX/4), A DISTANCE OF 850-11 FEET.

THENCE N89140'SIT, A DISTANCE OF 2077.12 FEET TO A POINT ON THE MESTERLY RIGHT-OF-WAY LINE OF VOLLIMER RUAD AS DESCRIPTION THE OCCULARINT RECORDED IN BOOK 2678 AT PACE 430 GF THE RECORDES OF THE RE PARD COUNTY CLERK AND RECORDER. THENCE SZITATIOW ALONG SAID WESTERLY RIGHT-OF-WAY LINE, A DISTANCE IN 2813.88 FEET TO A POINT

THENCE SETATION ACONG SAID DESTENCT RIGHT-OF-WAY LINE, A DISTANCE OF 2013.38 FEET TO A POINT ON THE EAST LINE OF THE MONTHMEST CINE-QUARTER OF THE NONTHEAST ONE-QUARTER (NUMLA NET/4) OF SAID SECTION 28:

THENCE NOTATITY ALLONG SAID EAST LINE, A DISTANCE OF 1217.12 FUT TO DHE SOUTHEAST DORMER OF THE SOUTHWEST ONE QUARTER OF THE SOUTHEAST ONE-QUARTER (SW174 SEL/4) OF SAID SECTION 21: THENCE 383740'14'W ALONG THE SOUTH UNE OF SAID SOUTHWEST ONE-QUARTER OF THE SOUTHEAST ONE-QUARTER (SW1/4 SEL/4), A DISTANCE OF 1313.40 FEST TO THE POINT OF BEQUINES

SAD PARCEL OF LAND CONTAINS & CALCULATED AREA OF SHOT ACRES OF LAND. ROPE OF LESS

EXHIBIT C

LEGAL DESCRIPTION TRAILS AT TIMBERLINE WEST PARCEL 2:

A PARCEL OF LAND LOCATED IN A PORTION OF THE SOUTHEAST ONE-DUARTER (SE)/A) OF SECTION 21. TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERICIAN, EL PASO COUNTY, COLORADO, BONG MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS. THE WEST LINE OF THE SCUTHEAST ONE-QUARTER (SET/4) OF SECTION 21, TOWNSHIP 12 SOUTH, RANGE 65 WEST IS ASSUMED TO BEAR NOO'25 32"N, A DISTANCE OF 2638-53 FEET,

COMMENCING AT THE SOUTHWEST CORNER OF SAID SOUTHEAST CHE-QUARTER (SCI/4) THENCE NOO'2S'32 W ALONG THE WEST LINE OF SAID SOUTHEAST CHE-QUARTER (SCI/4). A DISTANCE OF 650.11 FLET TO THE POINT OF BEDMINEND OF THE PARCEL OF LAND HEPEDN DESCRIDED. THENCE NOU'2S 32 W CONTINUING ALONG SAID WEST UNE, A DISTANCE OF 705.70 FLET THENCE NOU'SS 32 W CONTINUING ALONG SAID WEST UNE, A DISTANCE OF 705.70 FLET THENCE NOTAGEST AND CONTINUING ALONG SAID WEST UNE, A DISTANCE OF 705.70 FLET VOLUMED ROAD AS DESCRIBED IN THE DOCUMENT RECORDED IN BOOK 2678 AT PAGE 430 OF THE RECORDS OF THE EL PAGE COUNTY OLERS AND RECORDER. THENCE SEGNAD'S WALCING SAID WESTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 762.26 FEEL THENCE SEGNAD'STW. A DISTANCE OF 2077.12 FEET TO THE POINT OF BESINNENG.

SAID PARCEL OF LAND CONTAINS & CALCULATED AREA OF 36:03 ACRES OF LAND , HORE OF JESS.

EXHIBIT D

LEGAL DESCRIPTION TRAILS AT TIMBERLINE WEST PARCEL 3:


A PARCEL OF LAND LOCATED IN A PORTION OF THE SOUTHEAST ONE-QUARTER (SE1/4) OF SECTION 21, TOWNSHEP 12 SOUTH, RANGE 65 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASC COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: THE WEST LINE OF THE SOUTHEAST ONE-OUARTER (SE1/4) OF SECTION 21. TOWNSHIP-12 SOUTH, RANGE 65 WEST IS ASSUMED TO BEAR NOO'25'32'W, A DISTANCE OF 2038,53 FEET;

COMMENCING AT THE SOUTHWEST CORNER OF SAID SOUTHEAST ONE-QUARTER (SE1/4); DENCE NOT22'32'W ALONG THE WEST UNE OF BAID SOUTHEAST ONE-QUARTER (SE1/4); A DISTANCE OF 1356.51 FEET TO THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREW DESCRIBED; DENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THENCE NOT25'32'W CONTINUING ALONG SAID WEST UNE. A DISTANCE OF 656 30 FEET; THE EL PASC COUNTY CONTINUING ALONG SAID WEST DESCRIPTION OF THE RESOLUTION OF THE EL PASCE 136 OF THE RECORDED IN THE OF WEST DESCRIPTION OF THE RECORDED IN BOOK 2578 AT PAGE 136 OF THE RECORDED FT THE EL PASC COUNTY CLERK AND RECORDER;

THENCE ALONG SHID WESTERLY RIGHT-OF-WAY LINE THE FOLLOWING TWO (2) COUPSES: 1. SQU'S7'14'E, A DISTANCE OF 98.54 FEET; 2. S21'N1'NOW, A DISTANCE OF 891.81 FEET;

THENCE 388'40'31'M, A DISTANCE OF 2384.04 FEET TO THE POINT OF BECKNING.



2180925848/9/2018 3:54 PMPGS12\$68.00DF \$0.00Electronically Recorded Official Records El Paso County COChuck Broerman, Clerk and RecorderTD1000N

DISTRICT COURT, WATER DIVISION 2, CO Court Address: 501 North Elizabeth Street, Suite 116 Pueblo, CO 81003 Phone Number: (719) 404-8832	DATE FILED: August 9, 2018 3:38 PM CASE NUMBER: 2018CW3002		
CONCERNING THE APPLICATION FOR WATER RIGHTS OF:	▲ COURT USE ONLY ▲		
ARROYA INVESTMENTS, LLC	Case No.: 18CW3002 (17CW3002)		
IN EL PASO COUNTY			
FINDINGS OF FACT, CONCLUSIONS OF LAW, RULING OF REFEREE AND DECREE			

THIS MATTER comes before the Water Referee on the Application filed by Arroya Investments, LLC, and having reviewed said Application and other pleadings on file, and being fully advised on this matter, the Water Referee makes the following findings and orders:

GENERAL FINDINGS OF FACT

1. The applicant in this case is Arroya Investments, LLC, whose address is 1283 Kelly Johnson Blvd., Colorado Springs, CO 80920 ("Applicant"). Applicant is the owner of the land totaling approximately 72.5 acres (a portion of the larger 225.97-acre Arroya Parcel previously adjudicated in Case No. 17CW3002), on which the structures sought to be adjudicated herein are located, and are the owners of the place of use where the water will be put to beneficial use.

2. The Applicant filed this Application with the Water Court for Water Division 2 on January 9, 2018. The Application was referred to the Water Referee in Division 2 on or about January 18, 2018.

3. The time for filing statements of opposition to the Application expired on the last day of March 2018. No Statements of Opposition were timely filed.

4. On January 18, 2018, the Water Court, Division 2 ordered that publication occur in the *Daily Transcript* within El Paso County.

5. The Clerk of this Court has caused publication of the Application filed in this matter as provided by statute and the publication costs have been paid. On February 15, 2018, proof of publication in the *Daily Transcript* was filed with Water

Court Division 2. All notices of the Application have been given in the manner required by law.

6. Pursuant to C.R.S. §37-92-302(4), the office of the Division Engineer for Water Division 2 has filed its Consultation Report dated May 2, 2018, with the Court, and a Response to the Consultation Report was filed by the Applicant on June 26, 2018. Both the Consultation Report and Response have been considered by the Water Referee in the entry of this Ruling.

7. The Water Court has jurisdiction over the subject matter of these proceedings and over all who have standing to appear as parties whether they have appeared or not. The land and water rights involved in this case are not within a designated groundwater basin.

8. The Applicant, consistent with the decree entered in Case No. 17CW3002, seeks to utilize ground water rights granted therein for the construction of Timber Ridge Wells Nos. 1 through 29 to the Dawson aquifer, and additional or replacement wells associated therewith, for withdrawal of Applicant's full entitlements of supply under the plan for augmentation sought herein.

9. The land overlying the groundwater subject to the adjudication in this case is owned by the Applicant and was previously quantified in Case No. 17CW3002, which concerned a 225.97 acre parcel of land located in El Paso County, Colorado ("Arroya Parcel"). The land relevant to this decree consists of an approximately 72.5 acre portion of the larger Arroya Parcel as described in Case No. 17CW3002, located in a portion of the SE1/4 of Section 21 and a portion of the SW1/4 of Section 22, Township 12 South, Range 65 West of the 6th P.M., El Paso County, Colorado, as more particularly described on the attached **Exhibit A**, and depicted on the attached **Exhibit B** map ("Subject Property"). Applicant intends to subdivide the property into up to twenty-nine (29) lots of approximately 2.5 acres each. All groundwater adjudicated herein shall be withdrawn from the overlying land.

10. <u>Timber Ridge Wells Nos. 1 through 29</u>: Each of the Timber Ridge Wells Nos. 1 through 29 are to be constructed to the not-nontributary Dawson aquifer pursuant to the Plan for Augmentation decreed herein to provide domestic water supplies to a single family residence to be located upon the subdivided Subject Property. Upon entry of this decree and submittal by the Applicant of a complete well permit application and filing fee, the State Engineer shall issue a revised permit for Timber Ridge Wells Nos. 1 through 29 pursuant to C.R.S. §37-90-137(4), consistent with and references the Plan for Augmentation decreed herein.

PLAN FOR AUGMENTATION

11. The structures to be augmented are Timber Ridge Wells Nos. 1 through 29 in the not-nontributary Dawson aquifer underlying the Applicant's Property, along with any additional or replacement wells associated therewith.

12. Pursuant to C.R.S. §37-90-137(9)(c.5), the augmentation obligation for Timber Ridge Wells Nos. 1 through 29, and any additional or replacement wells constructed to the Dawson aquifer requires the replacement of actual stream depletions to the extent necessary to prevent any injurious effect. The water rights to be used for augmentation during pumping are the septic return flows of the not-nontributary Timber Ridge Wells Nos. 1 through 29, to be pumped as set forth in this plan for augmentation. The water rights to be used for augmentation after pumping are a reserved portion of Applicant's nontributary water rights in the Laramie-Fox Hills aquifers. Applicant shall provide for the augmentation of stream depletions caused by pumping the Timber Ridge Wells Nos. 1 through 29 as approved herein. Water use criteria as follows:

A. <u>Use</u>: The Timber Ridge Wells Nos. 1 through 29 may each pump up to 0.32 acre feet of water per year, for a maximum total of 9.32 acre feet being withdrawn from the Dawson aquifer annually. Households will utilize up to 0.26 acre feet of water per year per residence, with the additional pumping available for landscape irrigation, the watering of horses or equivalent livestock, and other beneficial uses decreed in 17CW3002 at each residence. The foregoing figures assume the use of 29 septic systems, with resulting return flows from each. Should Applicant subdivide Applicant's property into fewer than 29 lots, both depletions and return flows for the replacement of the same will be correspondingly reduced, though pumping for uses other than household use may be increased provided at all times septic return flows shall replace the maximum depletions resulting from pumping.

B. <u>Depletions</u>: Applicant has determined that maximum stream depletions over the 300-year pumping period will amount to approximately fifty-six percent (56%) of pumping. Maximum annual depletions for total residential pumping from all wells is therefore 5.22 acre feet in year 300. Should Applicant's pumping be less than the 0.32 acre feet per lot described herein, or should fewer lots be developed, resulting depletions and required replacements will be correspondingly reduced.

C. <u>Augmentation of Depletions During Pumping Life of Wells</u>: Depletions during pumping will be effectively replaced by residential return flows from non-evaporative septic systems. The annual consumptive use for non-evaporative septic systems is 10% per year per residence. At a conservatively estimated household use rate of 0.18 acre feet per residence per year (rather than the full 0.26 acre feet annually), a total of 5.22 acre feet is replaced to the stream system per year, utilizing non-evaporative septic systems, assuming all 29 wells are utilized. With maximum depletions from the pumping of 29 wells at 0.18 acre feet, and anticipated replacement of 5.22 acre feet annually, during pumping, stream depletions will be adequately augmented.

D. <u>Augmentation of Post Pumping Depletions</u>: This plan for augmentation shall have a pumping period of a minimum of 300 years. For the replacement of any injurious post-pumping depletions which may be associated with the use of the Timber Ridge Wells Nos. 1 through 29, Applicant will reserve up to 2,796

acre feet of water from the nontributary Laramie Fox Hills aquifer, less actual stream depletions replaced during the plan pumping period as necessary to replace any injurious post pumping depletions. Applicant also reserves the right to substitute other legally available augmentation sources for such post pumping depletions upon further approval of the Court under its retained jurisdiction. Even though this reservation is made, under the Court's retained jurisdiction, Applicant reserves the right in the future to prove that post pumping depletions will be noninjurious. The reserved nontributary Laramie-Fox Hills groundwater will be used to replace any injurious post-pumping depletions. Upon entry of a decree in this case, the Applicant will be entitled to apply for and receive a new well permit for the Timber Ridge Wells Nos. 1 through 29 for the uses in accordance with this Application and otherwise in compliance with C.R.S. §37-90-137.

13. This decree, upon recording, shall constitute a covenant running with Applicant's Property, benefitting and burdening said land, and requiring construction of well(s) to the nontributary Laramie-Fox Hills aquifer and pumping of water to replace any injurious post-pumping depletions under this decree. Subject to the requirements of this decree, in order to determine the amount and timing of post-pumping replacement obligations, if any, under this augmentation plan, Applicant or its successors shall use information commonly used by the Colorado Division of Water Resources for augmentation plans of this type at the time. Pursuant to this covenant, the water from the nontributary Laramie-Fox Hills aquifer reserved herein may not be severed in ownership from the overlying subject property. This covenant shall be for the benefit of, and enforceable by, third parties owning vested water rights who would be materially injured by the failure to provide for the replacement of post-pumping depletions under the decree, and shall be specifically enforceable by such third parties against the owner of the Applicant's Property.

14. Applicant or its successors shall be required to initiate pumping from the Laramie-Fox Hills aquifer for the replacement of post-pumping depletions when either: (i) the absolute total amount of water available from the Dawson aquifer allowed to be withdrawn under the plan for augmentation decreed herein has been pumped; (ii) the Applicant or its successors in interest have acknowledged in writing that all withdrawals for beneficial use through the Timber Ridge Wells Nos. 1 through 29 have permanently ceased, (iii) a period of 10 consecutive years where either no withdrawals of groundwater has occurred, or (iv) accounting shows that return flows from the use of the water being withdrawn is insufficient to replace depletions caused by the withdrawals that already occurred.

15. Accounting and responsibility for post-pumping depletions in the amount set forth herein shall continue for the shortest of the following periods: (i) the period provided by statute; (ii) the period specified by any subsequent change in statute; (iii) the period required by the Court under its retained jurisdiction; (iv) the period determined by the State Engineer; or (v) the period as established by Colorado Supreme Court final decisions. Should Applicant's obligation hereunder to account for and replace such post-pumping stream depletions be abrogated for any reason, then the Laramie-Fox Hills aquifer groundwater reserved for such a purpose shall be free from the reservation herein and such groundwater may be used or conveyed by its owner without restriction for any post-pumping depletions.

16. The term of this augmentation plan is for a minimum of 300 years, however, the length of the plan for a particular well or wells may be extended beyond such time provided the total plan pumping allocated to such well or wells is not exceeded. Should the actual operation of this augmentation plan depart from the planned diversions described herein such that annual diversions are increased or the duration of the plan is extended, the Applicant must prepare and submit a revised model of stream depletions caused by the actual pumping schedule. This analysis must utilize depletion modeling acceptable to the State Engineer, and to this Court, and must represent the water use under the plan for the entire term of the plan to date. The analysis must show that return flows have equaled or exceeded actual stream depletions throughout the pumping period and that reserved nontributary water remains sufficient to replace post-pumping depletions.

17. Consideration has been given to the depletions from Applicant's use and proposed uses of water, in quantity, time and location, together with the amount and timing of augmentation water which will be provided by the Applicant, and the existence, if any, injury to any owner of or person entitled to use water under a vested water right.

18. It is determined that the timing, quantity and location of replacement water under the protective terms in this decree are sufficient to protect the vested rights of other water users and eliminate material injury thereto. The replacement water shall be of a quantity and quality so as to meet the requirements for which the water of senior appropriators has normally been used, and provided of such quality, such replacement water shall be accepted by the senior appropriators for substitution for water derived by the exercise of the Timber Ridge Wells Nos. 1 through 29. As a result of the operation of this plan for augmentation, the depletions from the Timber Ridge Wells Nos. 1 through 29 and any additional or replacement wells associated therewith will not result in material injury to the vested water rights of others.

CONCLUSIONS OF LAW

19. The Applicant's request for adjudication of the plan for augmentation decreed herein is contemplated and authorized by law, and this Court and the Water Referee have exclusive jurisdiction over these proceedings. C.R.S. §§37-92-302(1)(a), 37-92-203, and 37-92-305.

20. Subject to the terms of the 17CW3002 decree, the Applicant is entitled to the sole right to withdraw all the legally available water in the Denver Basin aquifers underlying the Applicant's Property, and the right to use that water to the exclusion of all others subject to the terms of said 17CW3002 decree.

21. The Applicant's request for approval of a plan for augmentation is contemplated and authorized by law. If administered in accordance with this decree, this plan for augmentation will permit the uninterrupted diversions from the Timber Ridge Wells Nos. 1 through 29 without adversely affecting any other vested water rights in the Arkansas River or its tributaries and when curtailment would otherwise be required to meet a valid senior call for water. C.R.S. §§37-92-305(3),(5), and (8).

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED AS FOLLOWS:

22. All of the foregoing Findings of Fact and Conclusions of Law are incorporated herein by reference, and are considered to be a part of this decretal portion as though set forth in full.

23. The Application for Adjudication of Denver Basin Groundwater and for Approval of Plan for Augmentation proposed by the Applicant is approved, subject to the terms of this decree.

24. The Applicant has furnished acceptable proof as to all claims and, therefore, the Application for Adjudication of Groundwater and Plan for Augmentation, as requested by the Applicant, is granted and approved in accordance with the terms and conditions of this decree. Approval of this Application will not result in any material injury to senior vested water rights.

25. The Applicant shall comply with C.R.S. §37-90-137(9)(b), requiring the relinquishment of the right to consume two percent (2%) of the amount of the nontributary groundwater withdrawn. Ninety-eight percent (98%) of the nontributary groundwater withdrawn may therefore be consumed. No plan for augmentation shall be required to provide for such relinquishment.

26. The State Engineer, the Division Engineer, and/or the Water Commissioner shall not curtail the diversion and use of water covered by the Timber Ridge Wells Nos. 1 through 29 so long as the return flows from the annual diversions associated with the Timber Ridge Wells Nos. 1 through 29 accrue to the stream system pursuant to the conditions contained herein. To the extent that Applicant or one of its successors or assigns is ever unable to provide the replacement water required, then the Timber Ridge Wells Nos. 1 through 29 shall not be entitled to operate under the protection of this plan, and shall be subject to administration and curtailment in accordance with the laws, rules, and regulation of the State of Colorado. Pursuant to C.R.S. §37-92-305(8), the State Engineer shall curtail all out-of-priority diversions which are not so replaced as to prevent injury to vested water rights. In order for this plan for augmentation to operate, return flows from the one or both of the septic systems discussed herein, as appropriate, shall at all times during pumping be in an amount sufficient to replace the amount of stream depletions.

27. Pursuant to C.R.S. §37-92-304(6), the Court shall retain continuing jurisdiction over the plan for augmentation decreed herein for reconsideration of the question of whether the provisions of this decree are necessary and/or sufficient to prevent injury to vested water rights of others, as pertains to the use of Denver Basin groundwater supplies adjudicated herein, including for augmentation purposes.

Except as otherwise specifically provided in Paragraph 28, above, 28. pursuant to the provisions of C.R.S. §37-92-304(6), this plan for augmentation decreed herein shall be subject to the reconsideration of this Court on the question of material injury to vested water rights of others, for a period of five (5) years, except as otherwise provided herein. Any person, within such period, may petition the Court to invoke its retained jurisdiction. Any person seeking to invoke the Court's retained jurisdiction shall file a verified petition with the Court setting forth with particularity the factual basis for requesting that the Court reconsider material injury to petitioner's vested water rights associated with the operation of this decree, together with proposed decretal language to effect the petition. The party filing the petition shall have the burden of proof of going forward to establish a prima facie case based on the facts alleged in the petition. If the Court finds those facts are established, Applicant shall thereupon have the burden of proof to show: (i) that the petitioner is not materially injured, or (ii) that any modification sought by the petitioner is not required to avoid material injury to the petitioner, or (iii) that any term or condition proposed by Applicant in response to the petition does avoid material injury to the petitioner. The Division of Water Resources as a petitioner shall be entitled to assert material injury to the vested water rights of others. If no such petition is filed within such period and the retained jurisdiction period is not extended by the Court in accordance with the revisions of the statute, this matter shall become final under its own terms.

29. Pursuant to C.R.S. §37-92-502(5)(a), the Applicant shall install and maintain such water measurement devices and recording devices as are deemed essential by the State Engineer or Division Engineers, and the same shall be installed and operated in accordance with instructions from said entities. Applicant is to install and maintain a totalizing flow meters on all Timber Ridge Wells or any additional or replacement wells associated therewith. Applicant is also to maintain records and provide reports to the State Engineer or Division Engineers as instructed by said entities, on at least an annual basis.

30. The vested water rights, water right structures, and plan for augmentation decreed herein shall be subject to all applicable administrative rules and regulations, as currently in place or as may in the future be promulgated, of the offices of Colorado State and Division Engineers for administration of such water rights, to the extent such rules and regulations are uniformly applicable to other similarly situated water rights and water users.

31. This Ruling of Referee, when entered as a decree of the Water Court, shall be recorded in the real property records of El Paso County, Colorado. Copies of this ruling shall be mailed as provided by statute.

DATED THIS 18th day of July, 2018.

BY THE REFEREE:



Marall R. Ditemarica

Mardell R. DiDomenico, Water Referee Water Division 2

DECREE

THE COURT FINDS THAT NO PROTEST WAS MADE IN THIS MATTER, THEREFOR THE FORGOING RULING IS CONFIRMED AND APPROVED, AND IS HEREBY MADE THE JUDGMENT AND DECREE OF THIS COURT.

Dated: August 9th, 2018.



BY THE COURT:

EARRY C. SCHWARTZ, WATER JUDGE WATER DIVISION 2

EXHIBIT A

LEGAL DESCRIPTION – ARROYA PARCEL

A PARCEL OF LAND LOCATED IN A PORTION OF THE SOUTHEAST ONE-QUARTER (SE1/4) OF SECTION 21 AND A PORTION OF THE SOUTHWEST ONE-QUARTER OF SECTION 22, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30"E, A DISTANCE OF 3925.63 FEET;

COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27; THENCE S88°38'56"W ALONG THE NORTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4), A DISTANCE OF 1047.88 FEET TO THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREIN DESCRIBED;

THENCE S88°38'56"W CONTINUING ALONG SAID NORTH LINE, A DISTANCE OF 283.03 FEET TO THE NORTHWEST CORNER OF SAID SECTION 27 SAID POINT ALSO BEING A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 431 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER;

THENCE ALONG THE EASTERLY AND NORTHERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING TWO (2) COURSES:

1. N00°37'14"W SAID LINE ALSO BEING THE WEST LINE OF THE SOUTHWEST ONE-QUARTER (SW1/4) OF SAID SECTION 22, A DISTANCE OF 30.00 FEET; 2. S89°40'23"W, A DISTANCE OF 736.82 FEET TO THE POINT OF INTERSECTION OF THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 430 OF SAID COUNTY RECORDS;

THENCE N21°41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1798.07 FEET; THENCE N59°58'50"E, A DISTANCE OF 694.83 FEET; THENCE S14°30'58"E, A DISTANCE OF 567.09 FEET; THENCE N69°36'18"E, A DISTANCE OF 603.87 FEET; THENCE S30°23'46"E, A DISTANCE OF 264.58 FEET; THENCE S61°52'38"W, A DISTANCE OF 227.40 FEET;

THENCE S79°15'47"W, A DISTANCE OF 276.17 FEET; THENCE S89°39'18"W, A DISTANCE OF 356.07 FEET; THENCE S40°09'47"W, A DISTANCE OF 310.61 FEET; THENCE S09°56'46"W, A DISTANCE OF 270.03 FEET; THENCE S35°00'25"W, A DISTANCE OF 167.38 FEET; THENCE S57°24'01"W, A DISTANCE OF 235.36 FEET; THENCE S27°23'34"E, A DISTANCE OF 611.29 FEET TO THE POINT OF BEGINNING; SAID PARCEL OF LAND CONTAINS A CALCULATED AREA OF 35.08 ACRES OF LAND, MORE OR LESS.

Along With:

A PARCEL OF LAND BEING THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27, THE SOUTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (SW1/4 NW1/4) OF SECTION 27, THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SECTION 27, A PORTION OF THE SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER OF SECTION 28 AND A PORTION OF THE NORTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (NE1/4 NE1/4) OF SECTION 28, ALL IN TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30"E, A DISTANCE OF 3925.63 FEET;

COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27, SAID POINT ALSO BEING THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREIN DESCRIBED;

THENCE S00°54'30"E ALONG THE EAST LINE OF THE WEST ONE-HALF (W1/2) OF SAID SECTION 27, A DISTANCE OF 3925.63 FEET TO THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER NW1/4 SW1/4) OF SAID SECTION 27;

THENCE S87°35'00"W ALONG THE SOUTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4), A DISTANCE OF 1332.78 FEET TO THE SOUTHWEST CORNER OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4);

THENCE N00°53'18"W ALONG THE WEST LINE OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4), A DISTANCE OF 1316.78 FEET TO THE NORTHWEST CORNER OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4);

THENCE S89°08'28"W ALONG THE SOUTH LINE OF THE SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4) OF SECTION 28, A DISTANCE OF 1326.68 FEET TO THE SOUTHWEST CORNER OF SAID SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4);

THENCE N00°30'49"W ALONG THE WEST LINE OF SAID SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4), A DISTANCE OF 1270.77 FEET TO A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN

BOOK 2678 AT PAGE 430 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER; THENCE N21°41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1450.84 FEET TO THE POINT OF INTERSECTION OF THE SOUTHERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 431 OF SAID COUNTY


RECORDS;

THENCE ALONG THE SOUTHERLY AND EASTERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING TWO (2) COURSES:

1. N89°40'23"E, A DISTANCE OF 761.52 FEET TO A POINT ON THE EAST LINE OF SAID NORTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (NE1/4 NE1/4); 2. N00°52'58"W ALONG SAID EAST LINE, A DISTANCE OF 30.00 FEET TO THE NORTHWEST CORNER OF SAID SECTION 27;

THENCE N88°38'56"E ALONG THE NORTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4), A DISTANCE OF 1330.91 FEET TO THE POINT OF BEGINNING;

SAID PARCEL OF LAND CONTAINS A CALCULATED AREA OF 190.89 ACRES OF LAND, MORE OR LESS.



DISTRICT COURT, WATER DIVISION 2, COLORADO Court Address: 501 North Elizabeth Street, Suite 116 Pueblo, CO 81003 Phone Number: (719) 404-8832	DATE FILED: March 4, 2022 10:52 AM CASE NUMBER: 2020CW3059	
CONCERNING THE APPLICATION FOR WATER RIGHTS OF: STERLING RANCH METROPOLITAN DISTRICT NO. 1	▲ COURT USE ONLY ▲ Case No.: 20CW3059	
IN EL PASO COUNTY		
FINDINGS OF FACT, CONCLUSIONS OF LAW, AMENDED RULING OF REFEREE AND DECREE: ADJUDICATING DENVER BASIN GROUNDWATER, WATER STORAGE RIGHTS AND APPROVAL OF PLAN FOR AUGMENTATION		

THIS MATTER comes before the Court on the Application filed by Sterling Ranch Metropolitan District No. 1, and having reviewed said Application and other pleadings on file, and being fully advised on this matter, the Court makes the following findings and orders:

GENERAL FINDINGS OF FACT

1. The applicant in this case is Sterling Ranch Metropolitan District No. 1, whose address is 20 Boulder Crescent, #200, Colorado Springs, Colorado 80903 ("Applicant" or "District"). The Applicant seeks the adjudication of surface water rights, groundwater rights, and approval of a plan for augmentation.

2. The land upon which the surface water rights adjudicated herein are located are within the District, and the District is the owner of, or controls, all Denver Basin groundwater described herein. All land is located within the District, where the water will be put to beneficial use.

3. The Applicant filed this Application with the Water Court for Water Division 2 on October 12, 2020, and filed an Amended Application on October 13, 2020. The Application was referred to the Water Referee Division 2 on October 12, 2020.

4. The time for filing statements of opposition to the Application expired on the last day of December 2020. A Statement of Opposition was timely filed by The City of Colorado Springs, acting through its enterprise, Colorado Springs Utilities, on December 28, 2020, and a Statement of Opposition was timely filed by the State Engineer and the

Division Engineer for Water Division No. 2 on December 30, 2020.

5. On October 21, 2020, Water Court, Division 2, ordered that publication occur in El Paso County. The Clerk of this Court has caused publication of the Application filed in this matter as provided by statute and the publication costs have been paid. On November 19, 2020, proof of publication in *The Colorado Springs Gazette* was filed with the Division 2 Water Court. All notices of the Application have been given in the manner required by law.

6. On January 19, 2022, a stipulation between the Applicant and The City of Colorado Springs, acting through its enterprise, Colorado Springs Utilities was filed with the Division 2 Water Court. By Order dated January 24, 2022, the Division 2 Water Court approved such stipulation.

7. On November 5, 2021, a stipulation between the Applicant and the State Engineer and the Division Engineer for Water Division No. 2 was filed with the Division 2 Water Court. By Order dated November 5, 2021, the Division 2 Water Court approved such stipulation.

8. Pursuant to C.R.S. §37-92-302(2), the Office of the State Engineer has filed Determination of Facts for each aquifer with this Court on January 29, 2021.

9. As the State and Division Engineers timely filed a statement of opposition in this matter and obtained party status, no Consultation Report pursuant to C.R.S. §37-92-302(4) is necessary or required.

10. The Water Court has jurisdiction over the subject matter of these proceedings and over all who have standing to appear as parties whether they have appeared or not. The land and water rights involved in this case are not within a designated groundwater basin.

SURFACE WATER STORAGE RIGHTS

11. The Applicant seeks the adjudication of absolute surface water storage rights and the following findings are made with respect those rights:

A. <u>Name of Structure</u>: SRMD Pond No. 1. The terms of this decree concerning SRMD Pond No. 1 abrogate and replace all uses, terms, and conditions of prior decree of this Court in Case No. W-1309 as concerns the like structure decreed therein as Dines Reservoir No. 1, with the exception of claimed appropriation date for stockwater uses.

i. <u>Legal Description of Structure</u>: SRMD Pond No. 1 is located in the NE¼ SW¼ and the NW¼ SE¼ of Section 33, Township 12 South, Range 65 West of the 6th P.M. with the center of the embankment at a point approximately 1,450 feet from the south section line of said Section 33, and approximately 2,590 feet from the east section line of said Section 33, in El Paso County, Colorado.

ii. <u>Source</u>: The source for filling and re-filling of this existing onchannel structure is Sand Creek, a tributary of Fountain Creek, tributary to the Arkansas River.

iii. <u>Date and Initiation of Appropriation</u>: This water right shall be administered with a priority date of October 13, 2020, coincident with the filing of this Application. A stock tank in this location was decreed by the Division 2 Water Court in 1973, Case No. W-1309 as Dines Reservoir No. 1. However, Applicant's uses are far more expansive than those considered in W-1309, and Applicant therefore does not claim the earlier September 24, 1962 appropriation date decreed therein, except as to stockwater uses for purposes of demonstrating in-priority storage of water in support of Applicant's absolute claim for such uses.

iv. <u>Date Water Applied to Beneficial Use</u>: SRMD Pond No. 1 has existed since at least September 24, 1962, per the decree in W-1309.

v. <u>Amount Claimed</u>: 12.25 acre feet, with the right to freshening flows for maintenance of recreational, wildlife, fish propagation and fire protection purposes when in priority or when augmented by the plan approved herein. Since the initial construction of SRMD Pond No. 1 in 1962, there have been a number of instances where the Arkansas River call (and Sand Creek and Fountain Creek, as tributaries thereto), has been junior to the priority date of September 24, 1962 decreed to stockwater uses for this facility in W-1309, including in 1999. Each of these circumstances of in-priority storage occurred for decreed stockwatering purposes, supporting the absolute water rights decreed herein in the amount of 12.25 acre feet for such stockwater uses. All other municipal uses, including domestic, commercial, industrial, recreation, fish propagation, wetlands, wildlife habitat, and fire protection purposes decreed herein are conditional, in the amount of 12.25 acre feet.

vi. <u>Uses</u>: All municipal uses, including domestic, commercial, industrial, recreation, fish propagation, stockwater, wetlands, wildlife habitat, and fire protection purposes.

vii. <u>Pond Specifications</u>: SRMD Pond No. 1 has a maximum surface area at the high-water line of approximately 2.51 acres. The maximum height of the dam is approximately 10 feet and the length of the dam is approximately 510 feet.

viii. <u>Total Capacity of Pond</u>: Approximately 12.25 acre feet, all of which is dead storage.

ix. <u>Place of Use</u>: All uses of water associated with SRMD Pond No. 1 shall be within the boundaries of the District.

B. <u>Name of Structure</u>: SRMD Pond No. 2. The terms of this decree

concerning SRMD Pond No. 2 abrogate and replace all the uses, terms, and conditions of prior decree of this Court in Case No. W-1309 as concerns the like structure decreed therein as Dines Reservoir No. 3, with the exception of appropriation date for stockwater uses.

i. <u>Legal Description of Structure</u>: SRMD Pond No. 2 is located in the SE¼ SE¼ of Section 28, Township 12 South, Range 65 West of the 6th P.M. at a point approximately 115 feet from the south section line of said Section 28, and approximately 156 feet from the east section line of said Section 28, in El Paso County, Colorado.

ii. <u>Source</u>: The source for filling and re-filling of this existing onchannel structure is Sand Creek, a tributary of Fountain Creek, tributary to the Arkansas River.

iii. <u>Date and Initiation of Appropriation</u>: This water right shall be administered with a priority date of October 13, 2020, coincident with the filing of this Application. A stock tank in this location was decreed by the Division 2 Water Court in 1973, Case No. W-1309 as Dines Reservoir No. 3. However, Applicant's uses are far more expansive than those considered in W-1309, and Applicant therefore does not claim the earlier September 24, 1962 appropriation date decreed therein, except as to stockwater uses for purposes of demonstrating in-priority storage of water in support of Applicant's absolute claim for such uses.

iv. <u>Date Water Applied to Beneficial Use</u>: The pond has existed since at least October 4, 1962, per the decree in W-1309.

v. <u>Amount Claimed</u>: 4.29 acre feet, with the right freshening flows for maintenance of recreational, wildlife, fish propagation and fire protection purposes when in priority or when augmented by the plan approved herein. Since the initial construction of SRMD Pond No. 1 in 1962, there have been a number of instances where the Arkansas River call (and Sand Creek and Fountain Creek, as tributaries thereto), has been junior to the priority date of September 24, 1962 decreed to stockwater uses for this facility in W-1309, including in 1999. Each of these circumstances in-priority storage occurred for decreed stockwatering purposes, supporting the absolute water rights decreed herein in the amount of 4.29 acre feet for such stockwater uses. All other municipal uses, including domestic, commercial, industrial, recreation, fish propagation, wetlands, wildlife habitat, and fire protection purposes decreed herein are conditional, in the amount of 4.29 acre feet.

vi. <u>Uses</u>: All municipal uses, domestic, commercial, industrial, recreation, fish propagation, stockwater, wetlands, wildlife habitat, and fire protection purposes.

vii. <u>Pond Specifications</u>: SRMD Pond No. 2 has a maximum surface area at the high-water line of approximately 1.30 acres. The maximum height of

the dam is approximately 10 feet and the length of the dam is approximately 155 feet.

viii. <u>Total Capacity of Pond</u>: Approximately 4.29 acre feet, all of which is dead storage.

ix. <u>Place of Use</u>: All uses of water associated with SRMD Pond No. 2 will be within the boundaries of the District.

The Court finds the absolute surface water storage rights decreed herein 12. have been fully developed and the Applicant has utilized the water rights in-priority for stock-watering beneficial uses, as requested in the application. The Court further finds that the Applicant has completed all of the elements for the appropriation of the absolute water right, as to such stockwater uses, including: (a) formation of the intent to appropriate water; (b) performance of overt acts coincidental with this intent to manifest the intention to appropriate water to beneficial use and to demonstrate the taking of a substantial step toward applying water to beneficial use; (c) these acts were of such a nature as to provide interested third parties with notice of the nature and extent of the proposed diversion and the consequent demand upon the river system water to beneficial use; and as to the absolute water rights for stockwater purposes, (d) unappropriated waters have been diverted and have been applied to the beneficial use set forth herein. Applicant's documented in-priority fill and beneficial use of water stored within SRMD Pond Nos. 1 and 2 for stock-watering purposes is sufficient for creation of an absolute water right. The appropriation dates of the conditional water rights decreed herein establishes such water rights' relative priority among all other water rights or conditional water rights awarded on applications filed in Water Division 2 in the original years of filing for such conditional water rights, but such conditional water right shall be junior to all water rights and conditional water rights awarded on applications filed in previous calendar years.

GROUNDWATER RIGHTS

13. The Applicant requested quantification and adjudication of underground Denver Basin water rights, including as associated with an existing well with Permit No. 26947-F, as constructed to the Denver aquifer, and for an undetermined quantity of additional or replacement wells to one or more of the Denver Basin aquifers, as quantified herein, for withdrawal of Applicant's full entitlement of water supplies underlying the SR Quarry Parcel, as more particularly described on the attached **Exhibit A** and depicted on the **Exhibit B1** map, pursuant to the plan for augmentation decreed herein. Applicant also sought, and this Court decrees that, to the extent wells or well fields constructed on nearby property owned or controlled by Applicant and its affiliates have or are legally interpreted to have contiguity, Applicant shall have the right to withdraw all groundwater entitlements quantified herein from such contiguous wells and be considered a well field. The following findings are made with respect to such groundwater rights:

14. The land overlying the groundwater subject to the adjudication in this case is owned by the Applicant and consists of approximately 97.54 acres located in the S¹/₂ SW¹/₄ and the SW¹/₄ SE¹/₄ in Township 12 South, Range 65 West of the 6th P.M., El Paso

County, Colorado, described as the SR Quarry Parcel, and depicted on the attached **Exhibit B1** map ("SR Quarry Parcel"). All groundwater adjudicated herein shall be withdrawn from the overlying land, or from a contiguous parcel owned or controlled by the Applicant and its affiliates.

15. In accordance with the notice requirements of C.R.S. §37-92-302, lienholders of the SR Quarry Parcel were sent a Letter of Notice dated November 30, 2020. A Certificate of Notice was filed with the District Court, Water Division 2, on December 22, 2020.

16. <u>Existing and Future Wells.</u> All wells will be located on the SR Quarry Parcel, and/or on contiguous parcels thereto. There is an existing well on the property permitted and constructed under Well Permit No. 26947-F constructed to the Denver aquifer. Applicant is awarded the vested right to use the existing well and future wells, along with any necessary additional or replacement wells associated with such structures, for the extraction and use of groundwater from the not-nontributary Denver and Arapahoe aquifers pursuant to the Plan for Augmentation decreed herein. Upon entry of this decree and submittal by the Applicant of a complete well permit application and filing fee, the State Engineer shall issue a revised permit for the existing well, and new permits for any future well pursuant to C.R.S. §37-90-137(4), consistent with and referencing the Plan for Augmentation decreed herein.

17. Of the statutorily described Denver Basin aquifers, the Dawson, Denver, Arapahoe, and Laramie-Fox Hills aquifers all exist beneath the SR Quarry Parcel. The Dawson, Denver, and Arapahoe aquifers underlying the SR Quarry Parcel contain not-nontributary water, while the water of the Laramie-Fox Hills aquifer underlying the SR Quarry Parcel is nontributary. The quantity of water in the Denver Basin aquifers exclusive of artificial recharge underlying the SR Quarry Parcel is as follows:

AQUIFER	NET SAND (ft)	Annual Average Withdrawal 100 Years (Acre Feet)	Annual Average Withdrawal 300 Years (Acre Feet)	Total Withdrawal (Acre Feet)
Dawson (NNT)	50	9.75	3.25	975
Denver (NNT)	300	45.56 ^{1,2}	15.19 ²	4,556 ²
Arapahoe (NNT)	260	43.11	14.37	4,311
Laramie-Fox Hills (NT)	190	27.8	9.27	2,780

¹ Consistent with the State Engineer's Determination of Facts, this entire amount requires the existing well with Permit No. 26947-F to be re-permitted upon entry of this decree, as anticipated. If the well is not re-permitted, the average annual amount shall be reduced to 0 acre-feet.

² Applicant's consultants have estimated the maximum uses of the well with existing Permit No. 26947-F since it was first placed to beneficial use in 1989 as 13.1 acre feet annually, though it is highly unlikely that such maximum pumping actually occurred in each of the past 32 years. Nonetheless, Applicant has conservatively estimated that a total of 419 acre feet has been pumped thereby, and therefore the quantity of water claimed in the Denver aquifer in this decree has been reduced by such amounts.

the 18. Pursuant to C.R.S. §37-90-137(9)(c.5)(I)(B), augmentation requirements for wells in the Dawson aquifer underlying the SR Quarry Parcel requires the replacement to the affected stream systems of actual stream depletions on an annual Pursuant to C.R.S. §37-90-137(9)(c.5)(I)(C), the water of the Denver and basis. Arapahoe aquifers underlying the SR Quarry Parcel, which are located greater than 1 mile from any point of contact between a natural stream, requires replacement to the affected stream system of four percent (4%) of the amount of the water withdrawn from those aguifers on an annual basis. The Applicant shall not be entitled to construct a well or use water from the not-nontributary Dawson, Denver, or Arapahoe aquifers except pursuant to an approved augmentation plan in accordance with C.R.S. §37-90-137(9)(c.5), including as decreed herein as concerns the Denver and Arapahoe aquifers.

19. Subject to the augmentation requirements described in Paragraph 18 and the other requirements and limitations in this decree, Applicant shall be entitled to withdraw all legally available groundwater in the Denver Basin aquifers underlying the SR Quarry Parcel. Said amounts can be withdrawn over the 100-year life for the aquifers as set forth in C.R.S. §37-90-137(4), or withdrawn over a longer period of time based upon local governmental regulations or Applicant's water needs provided withdrawals during such longer period are in compliance with the augmentation requirements of this decree. This decree is based upon a pumping period of 300-years as required by El Paso County, Colorado Land Development Code §8.4.7(C)(1). The average annual amounts of groundwater available for withdrawal from the underlying Denver Basin aquifers, based upon a 300-year aquifer life, are determined and set forth above, based upon the January 29, 2021 Office of the State Engineer Determination of Facts described in Paragraph 8.

20. Applicant shall be entitled to withdraw an amount of groundwater in excess of the average annual amount decreed herein from the Denver Basin aquifers underlying the SR Quarry Parcel for a 300-year aquifer life, so long as the sum of the total withdrawals from wells in each of the aquifers does not exceed the product of the number of years since the date of entry of the decree herein, and the average annual volume of water which Applicant is entitled to withdraw from each of the aquifers underlying the SR Quarry Parcel, subject to the requirement that such banking and excess withdrawals do not violate the terms and conditions of the plan for augmentation decreed herein and any other plan for augmentation decreed by the Court that authorizes withdrawal of the Denver Basin groundwater adjudicated and decreed herein.

21. Subject to the terms and conditions of the plan for augmentation decreed herein and final approval by the State Engineer's Office pursuant to the issuance of well permits in accordance with C.R.S. §§37-90-137(4) or 37-90-137(10), the Applicant shall have the right to use the groundwater for beneficial municipal uses including, without limitation, domestic, commercial, industrial, irrigation of any irrigable acreage within the District boundaries or District service area, stock water, recreation, fish and wildlife propagation, fire protection, central water supply for such uses and also for exchange, aquifer recharge, replacement, and augmentation purposes. The amount of groundwater decreed for such uses is reasonable as such uses are to be made for the long-term use

and enjoyment of those served by Applicant and is to establish and provide for adequate water reserves. The nontributary groundwater in the Laramie-Fox Hills aquifer underlying the SR Quarry Parcel may be used, reused, and successively used to extinction, both on and off the SR Quarry Parcel subject, however, to the requirement under C.R.S. §37-90-137(9)(b) that no more than 98% of the amount withdrawn annually shall be consumed. Applicant may use such water by immediate application or by storage and subsequent application to the beneficial uses and purposes stated herein. Provided, however, as set forth above, Applicant shall only be entitled to construct a well or use water from the not-nontributary Dawson, Denver, and Arapahoe aquifers pursuant to a decreed augmentation plan entered by the Court, including that plan for augmentation decreed herein concerning the Denver and Arapahoe aquifers.

22. Withdrawals of groundwater available from the nontributary Laramie-Fox Hills aquifer beneath the SR Quarry Parcel in the amount determined in accordance with the provisions of this decree will not result in injury to any other vested water rights or to any other owners or users of water.

PLAN FOR AUGMENTATION

23. The structures to be augmented are the existing and future wells as constructed and to be constructed to the not-nontributary Denver and Arapahoe aquifers within the boundaries of the District or contiguous thereto and available to the District and the decree entered in Case No. 08CW113, as well as out-of-priority storage and evaporative depletions associated with the SRMD Pond Nos. 1 and 2.

24. Applicant is hereby decreed a plan for augmentation for out-of-priority depletions associated with the SRMD Pond Nos. 1 and 2, and for the withdrawal of notnontributary Denver Basin groundwater rights in the Denver and Arapahoe aguifers, respectively, underlying property owned and controlled by the Applicant and affiliates Sterling Ranch Metropolitan District Nos. 2 and 3 as previously decreed in Case No. 08CW113, and underlying the SR Quarry Parcel as decreed herein, to support development of land served by the District, more particularly described on the attached Exhibit A, and depicted on the attached Exhibit B1 and B2 maps. During the pumping life of wells to the Denver and Arapahoe aguifers described above, it is anticipated that any out-of-priority depletions will be replaced by Lawn Irrigation Return Flows ("LIRFs") resulting from the irrigation of approximately 48 acres of parks and common areas, supplemented by pumping of decreed nontributary water supplies from the Arapahoe and/or Laramie-Fox Hills aguifers underlying the District and its affiliates, as decreed to Applicant's use in Case Nos. 86CW18, 86CW19 and 08CW113, including from existing Applicant shall utilize a portion of the nontributary Denver Basin SRMD wells. groundwater underlying property outside of the District ("Bar X Parcel") as decreed in Case No. 93CW18 and 93CW19 by the Division 1 Water Court, which amended prior Case No. 85CW445, for replacement of any injurious post-pumping depletions.

25. SRMD Pond Nos. 1 and 2, with a total maximum surface area of 3.81 acres, have been calculated by Applicant's consultants to result in maximum annual evaporative

losses of 10.58 acre feet assuming such ponds are maintained at full stage, resulting in a like depletion to Sand Creek, a tributary of Fountain Creek, tributary to the Arkansas River. As described below, Applicant will replace this 10.58 acre foot annual depletion through dedicated LIRFs accruing to Sand Creek in the vicinity of the District, as depicted on the Exhibit B2 Map, or by pumping of the decreed nontributary supplies decreed in Case Nos. 86CW19 and 08CW113, including from existing SRMD wells. Applicant asserts, and this Court accepts as reasonable, that the SRMD Pond Nos. 1 and 2 were filled in priority in 1999, and have been maintained at full stage since such in-priority fill. Should the SRMD Pond Nos. 1 and 2 be fully or partially drained at any point in the future and thus require partial or complete refill, and should such re-fill be unavailable in priority, Applicant shall augment any such out-of-priority storage and refill of SRMD Pond Nos. 1 and 2 utilizing reusable LIRF credits accruing to Sand Creek and in excess of those required to replace depletions from the pumping of the not-nontributary wells described herein, and in excess of those required to replace evaporative depletions (including from less than full-stage storage), or by pumping of decreed nontributary water supplies from the Arapahoe and/or Laramie-Fox Hills aguifers underlying the District and its affiliates, as decreed to Applicant's use in Case Nos. 86CW18, 86CW19 and 08CW113, including from existing SRMD wells up to a maximum of 16.54 acre feet, being the total combined capacity of both SRMD Pond Nos. 1 and 2.

26. The not-nontributary Denver Basin groundwater underlying the property owned by the District and its affiliates that is available for withdrawal in accordance with this plan for augmentation was previously adjudicated and quantified by the Division 2 Water Court in Case No. 08CW113 as follows:

Aquifer	Annual Average Withdrawal (Acre-Feet) ³
Denver (NNT)	242.97
Arapahoe (NNT)	0.20

As quantified and determined herein, the SR Quarry Parcel has the following additional not-nontributary groundwater that is available for withdrawal in accordance plan for augmentation:

Aquifer	Annual Average Withdrawal (Acre-Feet) ²
Denver (NNT)	15.19

³ This represents the annually estimated available quantity of water for a 300-year pumping life, as required by El Paso County Land Development Code.

Arapahoe (NNT)	14.37
----------------	-------

Depletions from the pumping of the not-nontributary Denver and Arapahoe aquifer water described above are equal to 4% of pumping, a maximum of 10.91 annual acre feet.

27. All existing exempt permitted wells to the Denver and Arapahoe aquifers, if any, shall be either repermitted as augmented structures under the plan for augmentation decreed herein, or abandoned, consistent with the rules and regulations of the State and Division Engineers. Applicant is hereby granted pursuant to the terms and conditions of the augmentation plan decreed herein, the right to withdraw all quantities of not-nontributary Denver Basin groundwater in the Denver and Arapahoe aquifers underlying the SR Quarry Parcel, and underlying the District and its affiliates as described above, through existing, additional or replacement wells located on the subject properties or upon contiguous properties, consistent with Rule 11.A. of the Statewide Nontributary Ground Water Rules, provided Applicant first acquires such interests in the overlying land as may be necessary for construction, maintenance and operation of any such wells, and infrastructure related thereto. Applicant expressly may withdraw the not-nontributary groundwater underlying the SR Quarry Parcel from any and all wells, both existing and as may in the future be developed, available to Applicant on said parcel or other contiguous properties upon which the District has wells and infrastructure to each of the Denver and Arapahoe aquifers, respectively.

28. <u>Water Rights to be Used for Augmentation.</u>

Depletions During Pumping. During the pumping life of the not-Α. nontributary wells described herein, any out-of-priority depletions caused by the pumping of the wells, as well as evaporative depletions from the SRMD Pond Nos. 1 and 2 described herein and located on-channel on Sand Creek with total surface area of approximately 3.81 acres, will be augmented by LIRFs unless and until such a time as the District has reusable treated effluent credits available in proper time, place and amount, and unless such LIRFs are insufficient to fully replace actual out-of-priority depletions. Maximum pumping of the not-nontributary aquifers described herein, in combination, shall be 272.73 acre feet over the pumping life of the wells. If at any time LIRFs prove insufficient to replace out-of-priority depletions, Applicant shall utilize decreed nontributary water supplies from the Arapahoe and/or Laramie-Fox Hills aguifers underlying the District and its affiliates, as decreed to Applicant's use in Case Nos. 86CW18, 86CW19 and 08CW113, including from existing SRMD wells. Applicant's LIRFs will accrue to Sand Creek as a result of irrigation uses throughout the District. Maximum evaporative depletions from SRMD Pond Nos. 1 and 2 are 10.58 acre feet annually, and

maximum depletions from the pumping of the not-nontributary Denver and Arapahoe aquifer wells within the District are 4% of pumping, or 10.91 annual acre feet, for total approximate annual depletions of 21.49 acre feet that are to be replaced under the plan for augmentation decreed herein, plus any out-of-priority storage within SRMD Pond Nos. 1 and 2, as described in Paragraph 25, above. As described in Paragraph 30, below, LIRFs resulting from irrigation within the District's service area will result in up to 27.45 annual acre feet of reusable return flow credits to Sand Creek, though Applicant will be limited to 17.65 annual acre feet of LIRF credits for such augmentation uses unless and until Applicant is awarded a right to additional LIRF credits utilizing the process identified in Paragraph 30, below.

B. <u>Post Pumping Depletions.</u> The water rights to be used for augmentation of any injurious post-pumping depletions occurring after the anticipated 300-year pumping life of the wells resulting from the pumping of the not-nontributary groundwater described in this plan for augmentation are a portion of the nontributary Denver Basin groundwater rights underlying the Bar X Parcel, as decreed in Case Nos. 93CW18 and 93CW19 by the Division 1 Water Court, which amended prior Case No. 85CW445 as owned and controlled by the District:

Aquifer	Total Allocation (AF)
Denver (NT)	136,000
Arapahoe (NT)	81,300
Laramie-Fox Hills (NT)	42,700
BAR X TOTAL:	260,000

Maximum post-pumping depletions resulting from the i. pumping of the not-nontributary Denver and Arapahoe aquifers underlying the lands owned and controlled by the District and its affiliates, including the SR Quarry Parcel, as described herein, should not exceed 258.13 annual acre-feet from the not-nontributary Denver Aquifer, and 14.60 annual acre-feet from the not-nontributary Arapahoe aquifer over 300-years of pumping, a total of 272.73 annual acre feet in combination. To replace any injurious post-pumping depletions Applicant shall dedicate 82,167 acre-feet, equivalent to an average of 272.73 acre feet annually based on 300-years of pumping, from the nontributary Denver aguifer underlying the Bar X Parcel, owned or controlled by SRMD and its affiliates, less the amount of actual stream depletions replaced hereunder during the plan pumping period. Applicant's consultant estimates that a total of 1,978.12 acre-feet of lawn irrigation return flows will replace stream depletions over the 300-year pumping period. The total 82,167 acre feet of reserved post-pumping replacement water, less the amount of actual stream depletions replaced during the plan pumping period, will be sufficient to replace all calculated injurious post-pumping depletions. Applicant's dedication and reservation of up to 82,167 acre feet annually of nontributary Denver aguifer groundwater, being a portion of the Bar X water previously adjudicated in Case No. 93CW18, will provide this maximum post-pumping augmentation supply. The total reserved nontributary groundwater supply, less the amount of actual stream depletions replaced during the plan pumping period, is sufficient to replace all estimated injurious post-pumping depletions.

29. <u>Augmentation of Evaporative and Out-of-Priority Storage Depletions.</u> Applicant's consultants have calculated, and the Court accepts such calculations as reasonable, that net evaporative depletions of the combined maximum surface areas of the SRMD Ponds Nos. 1 and 2, being approximately 3.81 surface acres, will be 46.5 inches. The equations upon which Applicant's consultants have relied upon for calculating evaporative depletions and out-of-priority storage, are more particularly described in Paragraph 29.A., below. Therefore, the SRMD Ponds Nos. 1 and 2 will have combined evaporative depletions of approximately 10.58 annual acre-feet. Evaporative depletions resulting from the SRMD Ponds Nos. 1 and 2 will be augmented by: (1) excess LIRF credits, or (2) pumping from the nontributary Arapahoe and/or Laramie-Fox Hills aquifers underlying the District and its affiliates, as decreed to Applicant's use in Case Nos. 86CW18, 86CW19 and 08CW113, including from existing SRMD wells, as described above.

A. Depletion/Evaporation Formulas:

i. Gross Evaporation at the SRMD Ponds No. 1 and No. 2 = 46.5 inches (per NOAA Plate No. 33 in Colorado)

ii. Monthly Gross Evaporation = (46.5"/12) * (Monthly Evap.

Percentage)

iii. Monthly Evaporation Percentage Table from Colorado Division of Water Resources:

Month	Percentage
January	1.0%
February	3.0 %
March	6.0 %
April	9.0 %
May	12.5 %
June	15.5 %
July	16.0 %
August	13.0 %
September	11.0 %
October	7.5 %
November	4.0 %
December	1.5 %

iv. Monthly Gross Precipitation (inches) = Black Forest WNW Weather Station No. 6

v. Monthly Effective Precipitation (feet) = (Monthly Gross Precipitation) * 70 % / 12

vi. Net Monthly Pond Evaporation = ((Monthly Gross Evap.) * (Monthly %)) – (Effective Precipitation)

vii. Monthly Total Lake Evaporation = (Monthly Net Lake Evaporation) * (Total Surface Area of Ponds) (Note: Total Surface Area of ponds are assumed to be full at 3.81 Acres)

B. <u>Out-of-Priority Storage:</u> The method to accurately obtain monthly out-of-priority storage volumes for the two ponds is as follows:

i. Stage capacity curves for ponds, as constructed, are attached to this Decree collectively as **Exhibit D**.

ii. Prior to storage of water and administration of the augmentation plan decreed herein, a staff gauge shall be installed in each of the ponds with increments sufficient to monument the staff gauge to the stage capacity curves described in **Exhibit D**.

iii. Using the daily accounting summary for Case No. 20CW3059 daily readings of the SRMD Pond No. 1 and No. 2 staff gauges can be recorded with associated pond volumes documented in Acre-Feet to determine out-of-priority storage. Any positive differences in the pond storage can be documented in the daily data entry form as out-of-priority storage that must be augmented hereunder.

C. <u>LIRF Credits.</u> LIRF credits resulting from irrigation of parks and common areas throughout the District, anticipated to be approximately 48 acres, are anticipated to be available in excess of that required for augmentation of the not-nontributary Denver and Arapahoe aquifer wells described herein, as further described in Paragraph 30, below. Applicant shall likewise utilize such LIRF credits to offset and augment all or part of the estimated 10.58 annual acre feet of evaporative depletions associated with SRMD Pond Nos. 1 and 2, supplemented with nontributary water supplies from the Arapahoe and/or Laramie-Fox Hills aquifers underlying the District and its affiliates, as decreed to Applicant's use in Case Nos. 86CW18, 86CW19 and 08CW113, including from existing SRMD wells, as described below.

D. <u>Nontributary Groundwater.</u> In the alternative, and at all times when LIRF credits are insufficient to offset and augment the out-of-priority depletions described herein, including until such time as Applicant has constructed all of the approximately 48 acres of irrigated parks and common areas from which LIRF credits will ultimately accrue, Applicant shall pump to the stream such quantities of nontributary groundwater as necessary to fully augment evaporative depletions associated with SRMD Pond Nos. 1 and 2, estimated to be a maximum of 10.58 annual acre feet, not otherwise augmented through excess LIRF credits. The nontributary Laramie-Fox Hills aquifer underlying approximately 1,410 acres of the District was quantified in Case No. 86CW19 by the Division 2 Water Court, while the nontributary Laramie-Fox Hills aquifer underlying the remaining 41.44 acres of the District was quantified in Case No. 08CW113, Water Division 2. Nontributary groundwater in the Arapahoe aquifer was primarily quantified in Case No. 86CW18, Water Division 1, with a 4 acre-foot portion quantified in Case No. 08CW113, Water Division 2. Such adjudications provide for the combined annual withdrawals of nontributary groundwater well in excess of any depletions created through the use and maintenance of SRMD Pond Nos. 1 and 2, and such groundwater was previously adjudicated for all municipal uses, expressly including augmentation. Such groundwater will be pumped to Sand Creek in times and volumes necessary to prevent injury to other vested water rights users, at or above the point on Sand Creek depicted on the **Exhibit B2** Map. Prior to operation of the augmentation plan decreed herein, Applicant shall design and install infrastructure sufficient to allow Applicant, as contemplated in paragraph 30(L) herein, to deliver non-tributary Denver Basin Groundwater to Sand Creek at a point at or above the point depicted on Exhibit B2.

30. <u>Quantification of Reusable LIRFs</u>. Water use within the District's boundaries will include use for outdoor purposes, including irrigation of lawns, landscaping, open space, medians, and similar (*i.e.* parks and common areas). A portion of the water used for outdoor purposes, being reusable LIRFs, will return to the Sand Creek stream system unconsumed, and is therefore available to replace evaporative and well pumping depletions from the structures described herein. The District's consultants conducted a study of anticipated water uses within the District using water use data, climate data, anticipated irrigated acreages, irrigation requirements, and projected tree canopy areas in order to determine total annual LIRFs as a percentage of total annual outdoor water use. The location, amount, and timing of reusable LIRFs available for use by the District from outdoor water use shall be determined using the procedures described in this Paragraph 30.

As a baseline, the LIRFs available for use as an augmentation supply Α. for purposes of this decree will be a minimum of 15% of the total amount of water applied for irrigation of parks and common areas within the District's current and future boundaries, which will accrue to Sand Creek, tributary to Fountain Creek, tributary to the Arkansas River, estimated at an average of 17.65 acre feet annually. Applicant shall not be entitled to claim greater than 15% of the total amount of water applied for irrigation of common areas and parks within the District as LIRF credits without first complying with all provisions of this Paragraph 30. The approximate location at or upstream of which all such LIRFs are anticipated to accrue is shown on the attached Exhibit B2 map. However, the District's consultants' analysis determined that actual re-usable LIRFs are estimated to be an average of 26.14% of the total amount of water applied to outdoor use, with resulting return flows of 27.45 acre feet annually. The actual re-usable LIRFs will therefore amount to between 15% and 26.14% of total outdoor irrigation uses, based upon the relationship between deep percolation (expressed as a fraction of the amount of water applied) and the amount of water applied (expressed as a fraction of the potential consumptive use of lawn grass), referenced as the "Cottonwood Curve". and the methodology referred to as the "Cottonwood Methodology", first approved in Case No. 81CW142 in Water Division 1. The District has calculated the timing of the deep percolation portion of such reusable LIRFs to the Sand Creek stream system using the

Glover bounded alluvial aquifer equation. Applicant's consultants have estimated based upon zoning and land use plans developed by the District's landscape architects and approved by El Paso County, that approximately 48 acres of parks and common areas will be irrigated throughout the District, resulting in LIRFs calculated at approximately 17.65 to 27.45 acre feet annually, based on the percentages described above, and this Court determines this estimate to be reasonable. With maximum annual depletions from pumping of not-nontributary aquifers estimated at 10.91 acre feet (4% of a maximum of 272.73 annual acre feet of pumping), and evaporative depletions of the SRMD Ponds estimated at a maximum of 10.58 acre feet, for a total of 21.49 annual acre feet to be augmented, LIRFs available after construction and irrigation of approximately 48 acres of parks and common area may sufficiently augment evaporative depletions from the SRMD Ponds and well depletions during pumping, with any shortfall in LIRF supply being supplemented with pumping from the nontributary aquifers located within the District in an amount sufficient to replace any remaining depletions. To determine a final LIRF percentage upon buildout of areas upon which outdoor uses will be made (i.e. construction of the approximately 48 acres of parks and common areas from which LIRFs will accrue, and application of metered irrigation water supplies thereto), should the District wish to claim the minimum 15%, or a greater amount of reusable LIRFs, the District shall utilize the following procedures:

B. Total outdoor water use shall be determined on a monthly basis for the months of April through October of each year as the total amount of metered monthly deliveries to the parks and common areas. Prior to Utilizing LIRFs as an augmentation source, Applicant shall install meters capable of recording the amount of irrigation water provided to each park and/or common area from which LIRFs will accrue.

C. Reusable subsurface LIRFs from outdoor water use shall be preliminarily calculated as 15% of the total metered irrigation use for that month. The location of accretions to Sand Creek is the point where LIRFs are deemed to accrue to Sand Creek, as depicted on **Exhibit B2**.

D. The timing of accretion of such subsurface LIRFs to the alluvium has been determined by Applicant's consultants to be within 30 days, in light of local conditions and the proximity of irrigation to Sand Creek and its alluvium.

E. Prior to taking any credits for LIRFs in percentages greater than the baseline percentage of 15%, the District shall install a series of piezometers in consultation with the State Engineer's Office and complete a piezometer study, in order to document the presence, depth and calculated baseline quantities of the groundwater table, and verify the direction of groundwater flow.

F. To assure that the LIRFs are actually returning to the Sand Creek stream system, in order to take credits for LIRFs in percentages greater than the baseline percentage of 15%, the District shall demonstrate through piezometer measurements the existence of a water table with a hydraulic gradient toward the Sand Creek stream system, including its associated alluvium.

G. To document the quantity of LIRFs accruing to Sand Creek the District shall demonstrate through piezometer observations and measurements the increase in groundwater quantities resulting from LIRFs, and provide the State and Division Engineers, and any opposers in this matter requesting the same, an engineering analysis of such increased groundwater quantities, and calculation of the resulting appropriate LIRF percentage in an amount greater than the baseline 15%.

H. The following additional provisions shall apply to the piezometer study described above, necessary for the District to take credit for LIRFs in percentages greater than the baseline 15%:

i. The exact location of piezometers shall be determined by field observation jointly with the District's consultants and State Engineer staff and, prior to constructing any piezometers, the District shall notify the Division of Water Resources of the date and location when construction will occur to allow for observation, if desired. The contemplated location of piezometers is depicted on the attached **Exhibit B2**.

ii. The piezometer boreholes shall be logged under the supervision of a professional geologist or professional engineer and shall be sampled at not less than 5-foot intervals using a split-barrel sampler using the Standard Penetration Test, ASTM D1586. Written borehole logs shall be prepared that describe the subsurface materials at not less than 5-foot intervals, including a description of grain sizes and induration of sediments encountered during piezometer borehole construction.

iii. The total depth of unconsolidated materials overlying bedrock shall be identified for each piezometer borehole log. The top of bedrock shall be defined as the depth at which geologic materials are consolidated, or when the Standard Penetration Test results in a blow count greater than 29 blows to advance the split-barrel sampler the last 1 foot of the 1.5-foot Standard Penetration Test interval, whichever is shallower.

iv. Piezometer construction shall comply with the Colorado Water Well Construction Rules and shall consist of 2-inch PVC pipe with suitable perforations in the pipe and with a hole drilled in the bottom cap, and shall extend through the entire saturated thickness of the materials. The bottom of the piezometer shall be installed at the depth at which bedrock is encountered.

v. The elevation of the surface at, and the location of, each piezometer shall be determined by survey, and following piezometer construction, the depth to water shall be measured in the piezometers and reported to the Division of Water Resources and, upon request, to any other objector hereto. Piezometers shall be monitored and read on a monthly basis for a minimum period of 12 consecutive months (or longer, in the District's discretion), beginning upon the installation of the piezometer or the first measurement of a water table, and the piezometer water level shall be recorded in a monthly table of groundwater elevation and depth to groundwater.

vi. <u>Piezometer Report</u>. The District shall develop a report prepared by a professional geologist or professional engineer that presents all of the following information:

a. Location of each piezometer;

b. Borehole log and Standard Penetration Test for each piezometer location;

c. Monthly water level measured in each piezometer for twelve (12) consecutive months;

d. Average water level elevation in each piezometer;

e. Map of average piezometer groundwater level elevation that demonstrates a groundwater gradient towards Sand Creek and its tributaries.

vii. Acceptance of Piezometer Report. lf piezometer measurements for a continuous period of 12 months (or longer, in the District's discretion) demonstrate increases in the water table resulting from LIRFs in excess of the baseline 15% authorized by this decree, the District shall serve its Piezometer Report to the Division of Water Resources and the Opposers, to demonstrate that an increase in the percentage of re-usable LIRFs is appropriate. The Opposers will have 63 days from the date of service to provide written comments concerning the Piezometer Report to the District and the Division of Water Resources. Applicant must obtain the Division of Water Resources' approval of the Piezometer Report prior to claiming augmentation credit for LIRFs that is greater than the 15% credit approved herein. The Division of Water Resources shall review said Piezometer Report and the Opposers' comments thereto and within 63 days of receipt of said comments, the Division of Water Resources shall (a) Reject the findings of the Piezometer Report and not allow any increase in LIRF credits; (b) Accept the findings of the Piezometer Report and approve the increase in LIRF credit percentage requested therein by the District; or (c) Accept a portion of the findings of the Piezometer Report while rejecting others and recommending an alternative increase in LIRF credit percentages. Either Applicant or Opposers may appeal any such decision by the Division of Water Resources to this Court under the Court's retained jurisdiction as described in Paragraphs 57 and 58, below, and any such appealing party shall have the burden of proof in such an appeal. Applicant shall have the initial burden of proof that the requested increase in percentage of LIRFs credit will not result in injury to other water users. Following acceptance of the Piezometer Report by the Division of Water Resources or the Court under its retained jurisdiction, in whole or in part, increased LIRF credits may be taken by the District.

viii. The District shall have the right to decide if and when to install each of the said piezometers, but the District shall receive no increased credit for LIRFs

in the Sand Creek basin until the piezometers are installed and the Division of Water Resources has approved any increase in the LIRF credit percentage based upon the Piezometer Report described above.

I. The timing of accrual of LIRFs to the Sand Creek stream system was determined by the District using the Glover equation, using representative aquifer hydraulic characteristics and centroidal distances to live flow in the respective creeks, and the alluvial boundaries for each drainage basin. Such analysis determined that LIRFs will accrue to the alluvium of Sand Creek within 30 days. The timing of accrual of LIRFs is such that the LIRFS will accrue in the month following irrigation water application.

J. The LIRFs available to the District under this Decree may be used, reused, and successively used by the District for the same decreed purposes as the reusable water which generates such LIRFs, including, but not limited to, use as a replacement source for the plan for augmentation decreed herein.

K. LIRF credits in excess of the District's augmentation obligations will remain in the stream, but the District does not waive and expressly reserves its right to claim and use any excess LIRF credits in a subsequent plan for augmentation upon approval by this Court. To the extent LIRF credits are insufficient in any month to replace depletions resulting from not-nontributary well pumping, evaporation, and out-of-priority storage, the District shall during such month, and on a schedule acceptable to the Division Engineer, pump sufficient quantities of nontributary Denver Basin groundwater to Sand Creek at a point at or above the point depicted on **Exhibit B2**. In order to document the amount of monthly nontributary Denver Basin pumping required to augment any alluvial depletions measured to be in excess of available LIRF's, if any, depletions will be tracked on a daily basis in Applicant's accounting, an example of which is provided in **Exhibit C**, and augmented monthly as reported to the Water Commissioner. Depletions will be tracked in the accounting sheet as follows:

1) Daily Total Depletion to Alluvium	=	Column AR
2) Daily Estimated LIRF Volume (Credits to Alluvium)	=	Column AS
Daily Obligations to Alluvium	=	Column AT
Daily Excess Credits to Alluvium	=	Column AU

At the end of each month, if augmentation obligations are in excess of LIRF credits calculated to be available, the District shall pump nontributary groundwater at or above the point depicted on **Exhibit B2**. If there are excess LIRF credits, such LIRF Credits can be carried over for augmentation purposes only for a period of one month as tracked in column AW of the Exhibit C accounting.

31. <u>Other Supplies of Augmentation Water of Limited Duration</u>. Pursuant to C.R.S. §37-92-305(8), the Court may authorize the District to use additional or alternative sources of augmentation water for replacement in this augmentation plan, including water leased by the District, if such sources are part of a substitute water supply plan approved pursuant to C.R.S. §37-92-308, or an interruptible supply agreement approved under C.R.S. §37-92-309, or other applicable and/or successor statutes, or if such sources are

decreed for such use. In order to add these sources to this plan for augmentation, the procedures in Paragraphs 31.A. and 31.B. must be followed. These procedures are adequate to prevent injury to other water rights that might otherwise result from the addition of these sources to this plan.

Additional Water Rights Separately Decreed or Lawfully Available for Α. Augmentation Use. If a water right is decreed or lawfully available for augmentation use and not already approved for such use under this Decree, the District shall give at least 63 days advance written notice of use of the water right for augmentation to the Court, the Division Engineer, and all the objectors herein which shall describe: 1) the water right by name and decree, if any; 2) the annual and monthly amount of water available to SRMD from the water right; 3) the manner by which the water will be used to replace outof-priority depletions associated with this plan for augmentation; 4) the date of initial use of the water in this plan for augmentation; 5) the duration of use of the water in this plan for augmentation; 6) identification of any applicable exchanges, including the exchange reach, if the water is to be introduced downstream of the out-of-priority depletion; 7) if an exchange is required for the water to be used, proposed terms and conditions relative to the exchange operation; 8) the location or locations at which the water will be delivered to the stream; 9) evidence that the claimed amount of water is available for use in this plan for augmentation and is not and will not be used by any other person; and, 10) the manner in which the District will account for use of the augmentation credits. Said notice shall specifically include a request that the Court enter an Order either affirming or denying the District's proposal, and that said Order be attached to this Decree.

i. <u>Objection to Use of New Source</u>. If any person wishes to object to the addition of the noticed water rights to this plan for augmentation, a written objection shall be filed with the court within 63 days after the date the Notice was given by the District. If no objection is so filed, the Court shall promptly enter an Order affirming the District's immediate use of the noticed water rights. If an objection is so filed, then the District may not use the noticed water rights until the Court has determined whether and under what terms and conditions the water rights may be used in this plan.

ii. <u>Hearing on Use of New Source</u>. Where an objection has been filed to the use of a noticed water right in this plan for augmentation, the Court shall promptly schedule a hearing to determine whether and under what terms and conditions the water right may be used in this plan for augmentation. The Court shall conduct whatever proceedings are needed to appropriately address and resolve the disputed issues. At such hearing, the Court shall impose such terms and conditions as necessary to prevent injury to vested water rights and decreed conditional water rights. If the Notice requested temporary use of the noticed water rights in this plan for augmentation for a period not to exceed one year, then the Court shall grant an expedited hearing.

iii. <u>New Sources Requiring Operation of Exchange</u>. Where the use of a noticed water right in this plan for augmentation requires the operation of any new exchange(s), the District must obtain approval of the Division Engineer and Water Commissioner prior to operating such exchanges. The District must submit a separate

Water Court application if seeking to adjudicate any such exchange(s).

B. <u>Additional Water rights – Temporary Administrative Approval</u>. If a water right is not decreed or otherwise lawfully available for augmentation use, and Colorado Statutes or other governing authority provides a mechanism for using such water right without the need of a decree, the District shall provide written notice to the objectors herein of its request for approval of the State Engineer pursuant to C.R.S. §37-92-308, or C.R.S. §37-92-309, or any other applicable statute or rule. Such notice shall be in addition to any notice required by any applicable statute or rule. The District may use such water rights in this plan for augmentation upon the State Engineer's approval of the underlying administrative application for the term of any such approval, unless such approval is reversed or modified on appeal or under the retained jurisdiction provisions of this Case No. 20CW3059.

32. Applicant may substitute other legally available augmentation sources for replacement of any such injurious post-pumping depletions under this Court's retained jurisdiction, as described in Paragraph 31, above. Applicant claims that post-pumping depletions will be noninjurious and need not be replaced to prevent injury, though this Court makes no such finding by this decree. Applicant has reserved the right in the future to prove that said post-pumping depletions will be noninjurious and post-pumping depletions will be noninjurious under the Court's retained jurisdiction pursuant to paragraph 58.

33. Applicant shall replace post-pumping depletions for the shortest of the following: (a) the period provided by C.R.S. §37-90-137(9)(c); (b) the express period specified by the Colorado Legislature, should it specify one; (c) the period determined by the State Engineer, should he choose to set such a period and have jurisdiction to do so; (d) the period established through rulings of the Colorado Supreme Court on relevant cases, or (e) until Applicant petitions the Water Court, and after notice to parties in the case and the State Engineer's Office, proves that it has complied with any statutory requirement.

34. If operated pursuant to the terms and conditions set forth herein, the plan for augmentation decreed herein will allow Applicant to provide for the augmentation of any injurious out-of-priority stream depletions which may be caused by the pumping of the not-nontributary Denver and Arapahoe aquifer groundwater underlying the Sterling Ranch Metropolitan District Nos. 2 and 3, the SR Quarry Parcel, and out-of-priority storage and evaporative depletions from the SRMD Ponds Nos. 1 and 2. Applicant shall utilize the not-nontributary Denver Basin groundwater in the Denver and Arapahoe aguifers underlying the SRMD Metropolitan District Nos. 2 and 3 and the SR Quarry Parcel for municipal uses throughout the District's municipal service area, as currently exists or as may exist in the future, expressly including augmentation purposes. Applicant shall replace any out-of-priority depletions resulting from the SRMD Ponds Nos. 1 and 2, and the Applicant's use of the not-nontributary Denver Basin ground water described in paragraph 28 above during the pumping life of the wells through LIRFs accruing to Sand Creek, or by pumping of the decreed nontributary supplies decreed in Case Nos. 86CW19 and 08CW113, including from existing SRMD wells, and any injurious post-pumping or evaporative depletions through the dedication of nontributary Denver Basin groundwater supplies and excess LIRFs. Applicant has reserved sufficient nontributary Denver Basin groundwater supplies for replacement of any injurious post-pumping depletions.

35. <u>Curtailment.</u> Applicant's plan for augmentation, as decreed herein, is sufficient to permit the pumping of not-nontributary supplies in the Denver and Arapahoe aquifers underlying the District as described herein, including the SR Quarry Parcel, and the evaporative depletions from the SRMD Ponds Nos. 1 and 2, to the extent the District complies with all the terms and conditions of this decree including, but not limited to, providing the necessary replacement water as required by this decree. Pursuant to C.R.S. §37-92-305(8), the State Engineer shall curtail all out-of-priority diversions, the depletions from which are not so replaced to prevent injury to vested water rights.

36. <u>Terms and Conditions</u>. This Court finds that there will be no material injury to the owners or users of water diverted under vested water rights or conditional water rights as a result of operation of the plan for augmentation, so long as there is compliance with and proper administration of the protective terms and conditions herein.

A. <u>Lawn Irrigation Return Flow Credits.</u> The lawn irrigation return flows from the District's use of nontributary and not-nontributary groundwater rights, after meeting replacement requirements, shall only be used as an augmentation source in the instant plan for augmentation. All such return flow credits not utilized in the instant plan for augmentation shall, subject to the terms of a future decree, be available for the District's use and re-use, including for sale or lease to other parties.

Β. The reserved nontributary Denver Basin groundwater rights are adequate for replacement of all anticipated post-pumping depletions resulting from the groundwater withdrawals from the not-nontributary Denver and Arapahoe aguifers underlying the District as described herein, including the SR Quarry Parcel, and the evaporative depletions from the SRMD Ponds Nos. 1 and 2, augmented under this plan for augmentation. The District shall initiate pumping of said nontributary Denver Basin groundwater, or provision of any alternative augmentation supply as may be decreed by the Court, for the replacement of any out-of-priority post-pumping depletions upon cessation of withdrawals from the Denver and Arapahoe aguifers as augmented herein. "Cessation of Withdrawals" occurs when (1) the total volume of water available from the Denver and Arapahoe aguifers allowed to be withdrawn under the plan for augmentation decreed herein has been withdrawn; (2) the District has acknowledged in writing that all withdrawals from such aquifers have ceased permanently; (3) no withdrawals of groundwater have been made from the subject aquifers for a period of ten (10) consecutive calendar years; or (4) accounting shows that the augmentation sources described in Paragraph 28.B, above, are insufficient to replace depletions caused by withdrawals that have already occurred, and Applicant has not provided supplemental or additional augmentation supplies to remedy such insufficiency. Nothing herein shall preclude the District or its successors from resuming withdrawals from such notnontributary aquifers after cessation of withdrawals as defined above has occurred. If pumping is resumed, then the District's augmentation requirements for such wells shall be determined in accordance with Paragraph 28.B of this Decree, and its post-pumping augmentation obligation shall be determined as if no cessation of withdrawals had occurred.

C. A copy of the Decree shall be recorded in the records of the Clerk and Recorder for El Paso County, Colorado, and shall constitute a covenant running with the land, requiring Applicant and its successors in interest to be bound by the terms, conditions, and requirements of this Decree and the plan for augmentation herein, including the requirement to construct and pump well(s) to the nontributary aquifers identified herein or take such other measures as necessary to replace any injurious postpumping depletions upon Cessation of Withdrawals. Failure of Applicant or its successors in interest to comply with such requirements of this Decree may result in enforcement actions from the State Engineer's Office including curtailment or elimination of pumping from the not-nontributary aquifers. The covenant represented by this Decree when so recorded shall be amended as necessary to conform to the provisions of any amendment to this plan for augmentation which may occur

While the adjudications of the Denver Basin groundwater to be D. utilized in this plan for augmentation anticipate an aquifer life of 300 years for each Denver Basin aquifer, the length of this plan for augmentation may be shorter than, or extend beyond, such time period provided the total pumping allocated to any augmented well or wells is not exceeded. Should the actual operation of this augmentation plan depart from the planned diversions described in this decree such that the plan may be extended beyond the anticipated 300-year aquifer life, Applicant may be required to develop a revised model of stream depletions caused by the actual pumping schedule by the State or Division Engineer. Any such revised model analysis shall utilize depletion modelling acceptable to the State Engineer, and shall represent the water use under the plan for the entire term of the plan to date. The analysis shall further demonstrate that return flows have equaled or exceeded actual stream depletions to date throughout the pumping periods and that reserved nontributary water remains sufficient to replace post-pumping and evaporative depletions. If such revised modeling is required by the State and Division Engineers, the District shall serve the revised model on the Opposers and they shall have 63 days from service of the revised model and analysis to provide the Division Engineer with comments, concerns or objections regarding the revised model. The Division Engineer shall have 70 days from the receipt of the opposers comments on the revised model and analysis to consider the analysis and Opposers comments thereto, and to approve or disapprove the extension of the term of the plan, or to suggest terms and conditions appropriate to such an approval. Either Applicant or Opposers may appeal any such decision by the Division Engineer to this Court under the Court's retained jurisdiction as described in Paragraphs 57 and 58, below, and any such appealing party shall have the burden of proof in such an appeal. Applicant shall have the initial burden of proof that the extension of the term of the plan for augmentation will not result in injury to other water users.

37. Consideration has been given to the depletions from Applicant's use and proposed uses of water, in quantity, time and location, together with the amount and

timing of augmentation water which will be provided by the Applicant, and the existence, if any, of injury to any owner of or person entitled to use water under a vested water right.

38. It is determined that the timing, quantity and location of replacement water under the terms and conditions of this decree are sufficient to protect the vested rights of other water users and eliminate injury thereto. The replacement water shall be of a quantity and quality so as to meet the requirements for which the water of senior appropriators has normally been used, and such replacement water shall be accepted by the senior appropriators in substitution for water derived by the exercise of their decreed rights pursuant to CRS § 37-92-305(5) . The depletions from the wells withdrawing not-nontributary water underlying the SR Quarry Parcel, and any additional or replacement wells associated therewith, and the evaporation from the SRMD Ponds Nos. 1 and 2 will not result in injury to the vested water rights of others.

CONCLUSIONS OF LAW

39. Based upon and fully incorporating herein the Findings of Fact set forth above as though fully set forth herein, this Court concludes as a matter of law that:

40. Applicant's request for adjudication of the Denver Basin groundwater underlying the SR Quarry Parcel is contemplated and authorized by law, and this Court and the Water Referee have exclusive jurisdiction over these proceedings. §§ 37-92-302(1)(a), 37-92-203, and 37-92-305, C.R.S.

41. Subject to the terms and conditions of this decree, the Applicant is entitled to the sole right to withdraw all the legally available water in the Denver Basin aquifers underlying the parcels and property described herein, and the right to use that water to the exclusion of all others subject to the terms of this decree.

42. The Applicant has complied with C.R.S. §37-90-137(4), and the Laramie-Fox Hills groundwater underlying the SR Quarry Parcel is legally available for withdrawal, and the not-nontributary Dawson, Denver, and Arapahoe aquifer groundwater underlying the SR Quarry Parcel is legally available for withdrawal upon the entry of a decree approving an augmentation plan pursuant to C.R.S. §37-90-137(9)(c.5), and such a plan for augmentation is decreed herein as concerns the not-nontributary Denver and Arapahoe aquifer groundwater. Applicant is entitled to a decree from this Court confirming its rights to withdraw groundwater pursuant to §37-90-137(4), C.R.S.

43. The Denver Basin water rights described herein are not conditional water rights, but are vested water rights determined pursuant to C.R.S. §37-90-137(4). No applications for diligence are required. The claims for nontributary and not-nontributary groundwater meet the requirements of Colorado Law.

44. The confirmation, determination and quantification of the nontributary and not-nontributary groundwater rights in the Denver Basin aquifers as set forth herein is

contemplated and authorized by law. C.R.S. §§37-90-137, and 37-92-302 through 37-92-305.

45. <u>Satisfaction of Burdens of Proof.</u> Applicant has complied with all requirements and satisfied all standards and burdens of proof including, but not limited to, C.R.S. §§37-92-302 through 305, excepting sections 305(3.5) and 305(3.6) which are inapplicable hereto, as amended. Applicant is entitled to a decree confirming and approving the quantification of Denver Basin groundwater, and the plan for augmentation decreed herein, which will not injuriously affect the owners of or persons entitled to use water under vested water rights or decreed conditional water rights as long as the plan for augmentation is operated and administered in accordance with the terms and conditions herein.

46. The augmentation plan decreed herein is one contemplated by law. If implemented in accordance with the terms and conditions of this decree, the plan will permit the use of water without material injury to the vested or conditionally decreed water rights of others.

47. The Court is required to retain jurisdiction in a decree approving an augmentation plan on the question of injury to vested or conditional water rights. C.R.S. §37-92-304(6). Such jurisdiction is retained and described in detail at Paragraph 57, below.

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED AS FOLLOWS:

48. All of the foregoing Findings of Fact and Conclusions of Law are incorporated herein by reference, and are considered to be a part of this decretal portion as though set forth in full.

49. The Application for Surface Water Storage Rights, Adjudication of Denver Basin Groundwater and for Approval of Plan for Augmentation filed by the Applicant is approved, subject to the terms of this decree.

50. The Applicant will comply with C.R.S. §37-90-137(9)(b) requiring the relinquishment of the right to consume two percent (2%) of the amount of the nontributary groundwater underlying the SR Quarry Parcel adjudicated herein. Ninety eight percent (98%) of the nontributary groundwater withdrawn may therefore be consumed. No plan for augmentation is or shall be required to provide for such relinquishment.

51. The operation of the District's augmentation plan as decreed herein provides for the replacement of all injurious out-of-priority depletions which may result from withdrawals of not-nontributary groundwater from the Denver and Arapahoe aquifers underlying the District, including the SR Quarry Parcel, and out-of-priority storage and evaporative depletions from the use and operation of the SRMD Ponds Nos. 1 and 2, as described herein, augmented during pumping through dedication of lawn irrigation return flows, or pumping of nontributary groundwater decreed in Case Nos. 86CW18, 86CW19

and 08CW113, or additional sources approved in accordance with the terms of this decree, and augmented post-pumping through dedication and pumping of the nontributary Denver Basin groundwater rights decreed in Case No. 93CW18, as more particularly described in Paragraph 28.B, herein. The terms and conditions of this decree are adequate to assure that no injury to any water users will result from operation of this plan for augmentation. The Court approves this plan subject to the terms and conditions contained in this decree.

52. The replacement and augmentation supplies that the District will use for operation of the plan for augmentation decreed herein are of a quality and quantity so as to meet the requirements for which the water of senior appropriators has normally been used.

53. The State and Division Engineers and the Water Commissioner shall administer this augmentation plan in accordance with the terms and conditions contained in this decree. So long as the District operates the SRMD Ponds Nos. 1 and 2, and its wells to the not-nontributary Denver and Arapahoe aquifers in accordance with this decree, this augmentation plan can be operated without adversely affecting the owners or users of vested water rights or decreed conditional water rights on Sand Creek or its tributaries. So long as water is used in conformance with the requirements of this decree, there will be no injurious effects to the vested or decreed conditional water rights of others related to the amount or timing of water availability.

The State Engineer, the Division Engineer, and/or the Water Commissioner 54. shall not curtail the diversion and use of water covered by the plan for augmentation decreed herein, so long as the lawn irrigation return flows necessary for augmentation during the pumping life of the not-nontributary Denver and Arapahoe aquifers described herein continue to accrue to the stream system pursuant to the conditions contained herein or the Applicant utilizes the nontributary water available to it under Case Nos. 86CW18, 86CW19 and 08CW113 to replace depletions. To the extent that Applicant or its successors or assigns is unable to provide the replacement water required, then the wells and ponds shall not be entitled to continue under the protection of this plan, and shall be subject to administration and curtailment in accordance with the laws, rules, and regulation of the State of Colorado. Pursuant to C.R.S. §37-92-305(8), the State Engineer shall curtail all out-of-priority diversions which are not so replaced as to prevent injury to vested water rights. In order for this plan for augmentation to operate, LIRFs must at all times during pumping be in an amount sufficient to replace the amount of stream depletions. The State Engineer shall issue well permits in accordance with C.R.S. §37-90-137(4) and/or (10) and consistent with the terms and conditions of this Decree. All such wells constructed by Applicant pursuant to the augmentation plan decreed herein shall be geophysically logged consistent with applicable rules and regulations of the State and Division Engineers.

55. Applicant shall install such metering and measuring devices as may be reasonably required by the State and Division Engineers to ensure proper measurement and accounting of all withdrawals and pumping.

Accounting. The District has demonstrated an appropriate method of 56. accounting for diversions and stream depletions associated with the operation of this plan for augmentation. The District's accounting under this decree shall include the following information: (1) the daily volume of water pumped from each not-nontributary Denver and Arapahoe aquifer well; (2) the daily amount of water used for irrigation within the District and from which LIRFs are claimed, (3) the weekly out-of-priority stream depletions from prior weeks' pumping and from the current week's pumping; (4) the source and amount of the replacement sources used for augmentation in this plan, which shall be accounted for daily and reported monthly; and (5) the amount of any additional or alternative augmentation supplies allowed under Paragraph 29, which shall be accounted for daily, balanced weekly, and reported monthly. Unless specifically indicated by this decree, all accounting records required by this decree shall be filed with the State Engineer and Division Engineer on a monthly basis. An example of the District's current accounting forms, in which the accounting required by this plan for augmentation will be integrated, is attached as Exhibit C. Such Accounting forms are included as an example only and are not decreed herein. The Applicant's current accounting forms are adequate to account for the water rights and augmentation plan under this decree; however, said forms are not decreed herein and may be changed from time to time so long as the information required by this decree is included in the forms. Applicant shall serve the Opposers and the Division Engineer with any modified accounting forms. The Opposers will have 63 days thereafter to provide written comments concerning the modified accounting forms to Applicant and the Division Engineer. Applicant must obtain the Division Engineer's approval of the modified accounting forms prior to their use. Upon the Division Engineer's approval of the modified accounting forms, Applicant shall file the approved modified accounting forms with the Court, with service on the opposers herein. Applicant shall make its accounting available to the Water Commissioner and to any party who requests it, providing a summary of withdrawals, return flows, depletions, and augmentation releases associated with the District's operation of the augmentation plan approved herein. The daily accounting and all backup and supporting information and documents shall also be provided to any objector making a written request for said accounting for the accounting year, upon payment of reasonable costs. The accounting shall be delivered to the Division Engineer and Water Commissioner in the manner they prescribe and may be delivered to other objectors in paper or electronic format at the District's option.

57. <u>Retained Jurisdiction.</u> Pursuant to the provisions of C.R.S. §37-92-304(6), this plan for augmentation decreed herein shall be subject to the reconsideration of this Court on the question of material injury to vested water rights of others, for a period of five years after Applicant fully utilizes the LIRFs as an augmentation supply, as evidenced by the District's provision of written notice to Opposers herein that all parks and common areas anticipated to result in LIRF credits have been developed and constructed, and the District is irrigating such parks and common areas with approved water sources allowing such LIRF credits to be claimed. Any person, within such period, may petition the Court to invoke its retained jurisdiction. Any person seeking to invoke the Court's retained jurisdiction shall file a verified petition with the Court setting forth the factual basis for the relief requested in the petition, together with proposed decretal language to effect the

petition. The party filing the petition shall have the burden of proof of going forward to establish the facts alleged in the petition. If the Court finds those facts are established, Applicant shall thereupon have the burden of proof to show: (a) that the petitioner is not injured, or (b) that any modification sought by the petitioner is not required to avoid injury to the petitioner, or (c) that any term or condition proposed by Applicant in response to the petition does avoid injury to the petitioner. The Division of Water Resources as a petitioner shall be entitled to assert injury to the vested water rights of others. If no such petition is filed within such period and the retained jurisdiction period is not extended by the Court in accordance with the revisions of the statute, this matter shall become final under its own terms. The Court also retains continuing jurisdiction for the purpose of determining whether the continued reservation of the nontributary Denver Basin water rights in the Denver, Arapahoe, and Laramie-Fox Hills aquifers, more particularly described in Paragraph 28.B., above, for augmentation use hereunder is required and retained jurisdiction for such purpose shall be perpetual. After notice to all objectors, if Applicant can demonstrate to the Court that post-pumping depletions need no longer be replaced and/or are non-injurious, the Court may remove the requirement that the nontributary groundwater must continue to be reserved.

58. Pursuant to C.R.S. §37-92-304(6), the Court shall retain continuing jurisdiction over the plan for augmentation decreed herein for reconsideration of the question of whether the provisions of this decree are necessary and/or sufficient to prevent injury to vested water rights of others, as pertains to the use of Denver Basin groundwater supplies adjudicated herein for augmentation purposes. The Court also retains continuing jurisdiction for the purpose of determining compliance with the terms of the augmentation plan. The Court further retains jurisdiction should the Applicant later seek to amend this decree by seeking to prove that post-pumping depletions are noninjurious, that the extent of replacement for post-pumping matters addressed in Paragraph 28.B. The Court's retained jurisdiction may be invoked using the process set forth in Paragraph 57.

59. Pursuant to C.R.S. §37-92-502(5)(a), the Applicant shall install and maintain such water measurement devices and recording devices as are deemed necessary by the State Engineer or Division Engineers, and the same shall be installed and operated in accordance with instructions from said entities. Applicant is to install and maintain a totalizing flow meter on each well, or any additional or replacement wells associated therewith and are required to include geophysical logging on each well. Applicant shall read and record their well meter readings on April 1st and November 1st of each year and shall submit their meter readings to the Water Commissioner by April 15th and November 15th of each year or more frequently as requested by the Water Commissioner.

60. In compliance with Local Water Court Rule 9, the owner of a conditional water right shall:

Upon the sale or transfer of a conditional water right, the transferee Α. shall file with the Water court a notice of transfer which shall state:

- 1. The title and case number of the case in which the conditional decree was issued:
- 2. The description of the conditional water right transferred;
- The name of the transferor: 3.
- 4. The name and mailing address of the transferee; and
- A copy of the recorded deed. 5.

The transferor of any conditional water rights shall notify the clerk of Β. the water court having jurisdiction of any change in mailing address.

C. The clerk shall place any notice of transfer or change of address in the case file in which the conditional decree was entered and in the case file in which the court first made a finding of reasonable diligence.

As to the conditional water rights, pursuant to C.R.S. §37-92-301(4)(a), the 61. Applicant shall, every sixth year after the calendar year in which this conditional water right was decreed or subsequent diligence decreed or issued, if it desires to maintain the same, file an application for a finding of reasonable diligence or these conditional water rights shall be considered abandoned. Applicant shall, during the month of _, and the year of 2028, file an application for a finding of reasonable March diligence herein, unless Applicant has, prior to that time, made application to make absolute the conditional water rights guaranteed herein.

This Ruling of Referee, when entered as a decree of the Water Court, shall 62. be recorded in the real property records of El Paso County, Colorado. Copies of this ruling shall be mailed as provided by statute.

DATED: March 2, 2022.

BY THE REFEREE:

Kate Brewer, Water Referee Water Division 2

DECREE

THE COURT FINDS THAT NO PROTEST WAS MADE IN THIS MATTER, THEREFOR THE FORGOING RULING IS CONFIRMED AND APPROVED. AND IS HEREBY MADE THE JUDGMENT AND DECREE OF THIS COURT.

Dated: March 4, 2022

Honorable Larry C. Schwartz Water Judge, Water Division 2 State of Colorado

EXHIBIT A – Legal Descriptions

Sterling Ranch Metropolitan District Nos. 1, 2 and 3 DATE FILED: January 24, 2022 11:58 AM

The W1/2 W1/2 E1/2 and the E1/2 W1/2 and the SW1f4 SW1/4 of Section 27; the E1/2 SE1/4 and that portion of the SW1/4 SE1/4 Jying South and East of the County Road across said premises, both in Section 28; that portion of the SE1/4 SE1/4 of Section 32 lying South and East of said County Road, that portion of the NE1/4 SE114 of said Section 32, Jying South and East of said County Road, and that portion of the SE1/4 SW1/4 SE1/4 of Section 32 beginning at the SE comer of the SE1/4 SW1/4 SE1/4, then northerly along the east line of the SE1/4 SW1/4 SE1/4 a distance of 495 feet to a point on Vollmer Road, then southwesterly along Vollmer Road 660 feet to a point on the south line, then easterly 495 feet to the point of beginning; the E1/2 and the E1/2 SW1/4 and the SW1/4 SW114 of Section 33, and all that part of the NW1/4 of said Section 33 lying South and East of the said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road containing approximately 10 acres deeded to Colorado Interstate Gas Company by Warranty Deed recorded in Book 1173 at Page 359 of the El Paso County Records; and the W1/2 E1/2 and the W1/2 of Section 34, all in Township 12 South, Range 65 West of the 6th P.M., located in El Paso County, Colorado. The NW1/4 of the NW1/4 of Section 4, Township 13 South, Range 65 West of the 6th P.M., located in El Paso County, Colorado.

Bar X Land

A parcel of land located in Township 11 South, Range 65 West of the 6th Principal Meridian, El Paso County, Colorado, and more particularly described as follows:

All of Section 16; the E1/2 of the SW1/4 and the SE1/4 of Section 17; the E1/2 of the E1/2 of the W1/2 of Section 20; the NE1/4 and the W1/2, except for the east 30 feet of the SW1/4, of Section 21.

SR Quarry Land

A TRACT OF LAND IN THE SOUTHWEST ONE-QUARTER AND THE SOUTHWEST ONE-QUARTER OF THE SOUTHEAST ONE-QUARTER OF SECTION 32, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH PRINCIPAL MERIDIAN, IN EL PASO COUNTY, COLORADO, DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 32; THENCE N89°23'57"E ALONG THE SOUTH LINE OF SECTION 32, 30.00 FEET TO POINT ON THE EASTERLY LINE OF BLACK FOREST ROAD, ACCORDING TO THE RESOLUTION ADOPTED BY THE BOARD OF COMMISSIONERS OF EL PASO COUNTY RECORDED IN ROAD BOOK A AT PAGE 78, WHICH POINT IS THE POINT OF BEGINNING; THENCE N00°02'19"W ALONG SAID EASTERLY LINE, 125.50 FEET TO A POINT ON THE SOUTH LINE OF THAT TRACT OF LAND DESCRIBED IN BOOK 3859 AT PAGE 151; THENCE ALONG THE BOUNDARY OF SAID TRACT FOR THE FOLLOWING FOUR (4) COURSES; (1) THENCE N89°23'57"E, 25.20 FEET; (2) THENCE N42°32'21"E, 664.79 FEET; (3) THENCE N01°44'16"W, 403.43 FEET; (4) THENCE N87°25'38"W, 463.51 FEET TO A POINT ON SAID EASTERLY LINE OF BLACK FOREST ROAD; THENCE N00°02'19"E ALONG SAID EASTERLY LINE, 124.08 FEET; THENCE N89°27'58"E. 2607.50 FEET; THENCE N00°00'40"W ALONG THE NORTH-SOUTH CENTERLINE OF SECTION 32, 152.93 FEET TO THE SOUTHWEST CORNER OF HOLIDAY HILLS NO. 1, ACCORDING TO THE PLAT RECORDED IN PLAT BOOK E2 AT PAGE 12; THENCE N89°31'30"E ALONG THE SOUTH LINE OF SAID HOLIDAY HILLS NO. 1, 1260.38 FEET; THENCE S00°33'58"E ALONG THE WESTERLY LINE OF GLIDER PORT ROAD, AS DEDICATED IN SAID HOLIDAY HILLS NO. 1, 741.29 FEET; THENCE \$37°18'25"W ALONG THE NORTHWESTERLY LINE OF VOLLMER ROAD, 721.56 FEET; THENCE S89°23'57"W ALONG THE SOUTH LINE OF SECTION 32, 3437.29 FEET TO THE POINT OF BEGINNING, COUNTY OF EL PASO, STATE OF COLORADO

Retreat Land

A PARCEL OF LAND LOCATED IN A PORTION OF THE SOUTHEAST ONE-QUARTER (SE1/4) OF SECTION 21 AND A PORTION OF THE SOUTHWEST ONE-QUARTER OF SECTION 22, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30"E, A DISTANCE OF 3925.63 FEET;


COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27; THENCE S88°38'56"W ALONG THE NORTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4), A DISTANCE OF 1047.88 FEET TO THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREIN DESCRIBED; THENCE S88°38'56"W CONTINUING ALONG SAID NORTH LINE, A DISTANCE OF 283.03 FEET TO THE NORTHWEST CORNER OF SAID SECTION 27 SAID POINT ALSO BEING A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 431 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER; THENCE ALONG THE EASTERLY AND NORTHERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING TWO (2) COURSES:


1.N00°37'14"W SAID LINE ALSO BEING THE WEST LINE OF THE SOUTHWEST ONE-QUARTER (SW1/4) OF SAID SECTION 22, A DISTANCE OF 30.00 FEET; 2.S89°40'23"W, A DISTANCE OF 736.82 FEET TO THE POINT OF INTERSECTION OF THEEASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 430 OF SAID COUNTY RECORDS; THENCE N21°41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1798.07 FEET; THENCE N59°58'50"E, A DISTANCE OF 694.83 FEET; THENCE S14°30'58"E, A DISTANCE OF 567.09 FEET; THENCE N69°36'18"E, A DISTANCE OF 603.87 FEET; THENCE S30°23'46"E, A DISTANCE OF 264.58 FEET; THENCE S61°52'38"W, A DISTANCE OF 227.40 FEET; THENCE S79°15'47"W, A DISTANCE OF 276.17 FEET; THENCE S89°39'18"W, A DISTANCE OF 356.07 FEET; THENCE S40°09'47"W, A DISTANCE OF 310.61 FEET; THENCE S09°56'46"W, A DISTANCE OF 270.03 FEET; THENCE S35°00'25"W, A DISTANCE OF 167.38 FEET; THENCE S57°24'01"W, A DISTANCE OF 235.36 FEET; THENCE S27°23'34"E, A DISTANCE OF 611.29 FEET TO THE POINT OF BEGINNING; SAID PARCEL OF LAND CONTAINS A CALCULATED AREA OF 35.08 ACRES OF LAND, MORE OR LESS.

Along With:

A PARCEL OF LAND BEING THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27, THE SOUTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (SW1/4 NW1/4) OF SECTION 27, THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SECTION 27, A PORTION OF THE SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER OF SECTION 28 AND A PORTION OF THE NORTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (NE1/4 NE1/4) OF SECTION 28, ALL IN TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30"E, A DISTANCE OF 3925.63 FEET; COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST ONE-OUARTER OF THE NORTHWEST ONE-OUARTER (NW1/4 NW1/4) OF SECTION 27, SAID POINT ALSO BEING THE POINT OF BEGINNING OF THE PARCEL OF LAND HEREIN DESCRIBED; THENCE S00°54'30"E ALONG THE EAST LINE OF THE WEST ONE-HALF (W1/2) OF SAID SECTION 27, A DISTANCE OF 3925.63 FEET TO THE SOUTHEAST CORNER OF THE NORTHWEST ONE-OUARTER OF THE SOUTHWEST ONE-QUARTER NW1/4 SW1/4) OF SAID SECTION 27; THENCE S87°35'00"W ALONG THE SOUTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4), A DISTANCE OF 1332.78 FEET TO THE SOUTHWEST CORNER OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4); THENCE N00°53'18"W ALONG THE WEST LINE OF SAID NORTHWEST ONE-OUARTER OF THE SOUTHWEST ONE-OUARTER (NW1/4 SW1/4), A DISTANCE OF 1316.78 FEET TO THE NORTHWEST CORNER OF SAID NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4); THENCE S89°08'28"W ALONG THE SOUTH LINE OF THE SOUTHEAST ONE-OUARTER OF THE NORTHEAST ONE-OUARTER (SE1/4 NE1/4) OF SECTION 28, A DISTANCE OF 1326.68 FEET TO THE SOUTHWEST CORNER OF SAID SOUTHEAST ONE-QUARTER OF THE NORTHEAST ONE-QUARTER (SE1/4 NE1/4); THENCE N00°30'49"W ALONG THE WEST LINE OF SAID SOUTHEAST ONE-OUARTER OF THE NORTHEAST ONE-OUARTER (SE1/4 NE1/4), A DISTANCE OF 1270.77 FEET TO A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 430 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER; THENCE N21°41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1450.84 FEET TO THE POINT OF INTERSECTION OF THE SOUTHERLY RIGHT-OF-WAY LINE AS DESCRIBED IN THE DEED, AS RECORDED IN BOOK 2678 AT PAGE 431 OF SAID COUNTY RECORDS; THENCE ALONG THE SOUTHERLY AND EASTERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING TWO (2) COURSES: 1. N89°40'23"E, A DISTANCE OF 761.52 FEET TO A POINT ON THE EAST LINE OF SAID NORTHEAST ONE-OUARTER OF THE NORTHEAST ONE-OUARTER (NE1/4 NE1/4); 2. N00°52'58"W ALONG SAID EAST LINE, A DISTANCE OF 30.00 FEET TO THE NORTHWEST CORNER OF SAID SECTION 27; THENCE N88°38'56"E ALONG THE NORTH LINE OF SAID NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4), A DISTANCE OF 1330.91 FEET TO THE POINT OF BEGINNING; SAID PARCEL OF LAND CONTAINS A CALCULATED AREA OF 190.89 ACRES OF LAND, MORE OR LESS.





prepared by: JDS-Hydro Consultants, Inc.

EXHIBIT C

ounting - SRMD Pond No. 1 and Pond No. 2

<u>No. 1</u>

Beginning of Day Staff Gauge Reading	ft
Beginning of Day Volume ¹	Acre-feet
End of Day Staff Gauge Reading	ft
End of Day Staff Volume ¹	Acre-feet
End of Day Gain / Loss in Volume (D-B)	ft

<u>No. 2</u>

Beginning of Day Staff Gauge Reading	 ft
Beginning of Day Volume ²	Acre-feet
End of Day Staff Gauge Reading	 ft
End of Day Staff Volume ²	Acre-feet
End of Day Gain / Loss in Volume (I-G)	ft

Total Volume Gain / Loss in Volume (E+J) Acre-feet
Is there a Free River? (yes / no)
Admin Number of Calling Right

Volume from SRMD Pond No. 1 Stage-Storage Table No. 1
 Volume from SRMD Pond No. 2 Stage-Storage Table No. 2

DATE FILED: January 24, 2022 11:58 AM

Evaporation Accounting - SRMD Pond No. 1 and Pond No. 2

Date:

SRMD Pond No. 1

- A) Beginning of Day Staff Gauge Reading
- B) Beginning of Day Surface Area¹
- C) End of Day Staff Gauge Reading
- D) End of Day Staff Surface Area¹
- E) End of Day Average Surface Area (D-B)
- F) Precipitation²
- G) Effective Precipitation (((F)*0.7)/12)

I) Gross Lake Evaporation³

- J) Net Lake Evaporation (I-G)
- K) Daily Average Evaporation (J*E)

SRMD Pond No. 2

- L) Beginning of Day Staff Gauge Reading
- M) Beginning of Day Surface Area²
- N) End of Day Staff Gauge Reading
- O) End of Day Staff Surface Area²
- P) End of Day Average Surface Area (D-B)
- Q) Precipitation²
- R) Effective Precipitation (((Q)*0.7)/12)
- S) Gross Lake Evaporation³
- T) Net Lake Evaporation (S-R)
- U) Daily Average Evaporation (T*P)

Summary


- V) Total Evaporation Volume (U+K) ______Acre-feet
- W) Is there a Free River? (yes / no)

X) Admin Number of Calling Right

Note: 1) Volume from SRMD Pond No. 1 Stage-Surface Area Table No. 1

2) From Black Forest 6 WNW Weather Station

3) Monthly Gross Evaporation Rate from Table 3



ft

ft

ft

ft

ft

Acre-feet

Acre-feet

inches

AF/Acre

AF

2) Volume from SRMD Pond No. 2 Stage-Surface Area Table No. 2

Table 3 - Monthly Gross Evaporation Rates for SRMD

Month	% of Annual Evaporation % of Acres	Gross Lake Evaporation Rate - Feet
January	1.0%	0.039
February	3.0%	0.116
March	6.0%	0.233
April	9.0%	0.349
May	12.5%	0.484
June	15.5%	0.601
July	16.0%	0.620
August	13.0%	0.504
September	11.0%	0.426
October	7.5%	0.291
November	4.0%	0.155
December	1.5%	0.058
Total	1.0	3.875

Well Pumping / Accounting - NT and NNT Wells

Date: _____

Not-Nontributary Well Pumping

1) SR Quarry Denver Well No. 1

A) Meter Reading - Beginning of Day	gallons
B) Meter Reading - End of Day	gallons
C) Total gallons pumped (B-A)	gallons
D) Alluvial depletions (4%*C)	gallons
E) Alluvial deplations (D/325851)	AF
2) SR Quarry Arapahoe Well No. 1	
F) Meter Reading - Beginning of Day	gallons
G) Meter Reading - End of Day	gallons
H) Total gallons pumped (G-F)	gallons
 Alluvial depletions (4%*H) 	gallons
J) Alluvial deplations (I/325851)	AF

3) SRMD Well D-1

K) Meter Reading - Beginning of Day	gallons
L) Meter Reading - End of Day	gallons
M) Total gallons pumped (L-K)	gallons
N) Alluvial depletions (4%*N)	gallons
O) Alluvial deplations (N/325851)	AF

AF

P) Total alluvial depletions (E+J+O)

Nontributary Well Pumping

4) SRMD Well A-1

Q) Meter Reading - Beginning of Day	gallons
R) Meter Reading - End of Day	gallons
S) Total gallons pumped (R-Q)	gallons
T) Total gallons pumped (S/325851)	AF

5) SRMD Well LFH-2

U) Meter Reading - Beginning of Day	gallons
V) Meter Reading - End of Day	gallons
W) Total gallons pumped (R-Q)	gallons
X) Total gallons pumped (S/325851)	AF
Y) Total NT pumped (T+X)	AF

Lawn Irrigation Return Flows (LIRF) Calculations

Date:

LIRF Credit Calculations

A) Metered municipal irrigation use	gallons
B) Metered municipal irrigation use (A/325851)	AF
C) Estimated irrigation losses (B*0.735)	AF
D) Adjusted irrigation application (B-C)	AF
E) Fixed LIRF return flow rate	<u> </u>
F) Estiamted LIRF volume (D*E)	AF

aily Data Entry Form																																	
		0						Conceptor .				Antile	unice.					Mark Deserves									0.0.0						
DATE: SRS	ID Pond Na	Total Storac Storace BOD (BD) (AD)	SRMD Pond 1	6.2 Your	8	IRMD Fund N	6.1 	evaceation	SRMD Pun	nd No. 1	To To	All Free Administration Administratio Administration Administration Administration Administratio	n. Name of	60.0 ···· 0·····		N	an a la an	Well Punking	Text (0)		NT	Transie	Metered Metered	Edmate: Adusted Minimu	un Estimated	Yotel	Cally Se	Remaining	Augmentation	Renairing	Augmentation	Renaiting	Augmentator Credits in Excel Obligations (AE)
BOD (AE)	600	Storage BOE	600	Storace Storace	Area Preci	Gross Gross La Euro Hart	Net To Exec Eve	ar Ave. Surface	Precio Evi	rao Enas	Total Po Evan Eva	as 0=FR Cal	n. Name of r of Calling Right	Purroed Dealer	Desiet (Punaed Dealet	Deplet Punped (AE) (select)	Decist Decis	Dealet Pump	d Aug Water	SEMD Well LEVES	Water I	Metered Metered Municipal Intraction Use Infrastion UP Africa (ME)	Edmand Adusted Minim Losses Interaction LRG dr735% the Rate (AE) (AE) 195	LRF D Volume	Total Depletions to Alluvium (AD)	Total Augmentation Credits to Abuvium	Obligations	of Chigations	Chigations (#E)	Augmentation Oradis in Excess of Obligations (86)	Remaining Augmentation Chalgations (AE)	Chigaton (AE)
810021																								153									
83/2021	_		_																					153									
810021 810021 8202021 8402021 8402021 8402021 8402021 8402021 8402021 8402021 8402021 8402021 8410001 8410001			-			1		+ +	_	-			+ +	_			-		+ +	1	_	1 1		153	4					1			1
86/2021 87/2021																								153									
89/2021	_		_							_														159									
8/15/2021	_		_					_		_			_									-		153		_							
11111001	_		_			_			_	_			_				_			_				*55	_					_			
#15:0021 #16:0021																								193									
#15/2021 #16/2021						-			_				_											159									
8/17/2021			-			-				-			_											159	-								
8/18/2021																								157									
8/21/2021																								159									
#23/2021 #23/2021														-							-			153									
8262021	-					-			-	-			-				_							159									
8/26/2021						_			_	_			_			_								159									
8/28/2021																								153									
8/28/2021 8/25/2021									_															159	-								
8/31/2021 8/1/2021	-					-			-	-			-				_							159									
92/2021						_				_			_			_								159									
84/2021																								153									
86/2021									_															197	-								
970221 9902221							t 1								⊢†			t t	+ +					159						1			L
89/2021 9/10/2021	-		_			_	1												+ +	1				159	-		_	-		1	-		1
911/2021	_		_						_		+						_					+		153	-								-
F14/2021 913/2021																				1 1				153									1
9/16/2021 9/15/2021	T			LET							t t				ĿТ				$\pm \pm$			±_T		159	±-								
916/2021	-		_			_	1												+ +	1				159	-		_	-		1	-		1
918/2021	_		_						_		+						_					+		153	-								-
#18/2021 9/20/2021																								153									
9/21/2021	T			LET							t t				ĿТ				$\pm \pm$			±_T		159	±-								
923/2021	-	1	_		1	_	1 1		T			1							+	1 1				159	-		-	-		1	-		1
¥25/2021							1 1	1 1				+ +					-		1 1	1 1		1 1		157	4								1
926/2021 927/2021																								153									
9282021	-					-			-	-			-				_							159	-								
W35/2021																								151									
10.0.0021																								159									
10/0/2021	-					-			-	-			-				_							159	-								
0.5/2021		_			_	_	-		_	_			_			_	_					_		159						_			
15/7/2021																								159									
15/8/2021														-							-			153									
0100001	-		-			-			_	-			_											159	-								
6150001						_		_				_	_	_						_	_	_		153									
1014/0001																								159									
15150001														-							-			153									
10170001	-					-			-	-			-				_							159									
1016/0001						_		_				_	_	_						_	_	_		153									
19/21 20/21																								159									
1523/2021														-							-			153									
10240001	-		-			-			_	-			_											159	-								
1000000						_		_				_	_	_						_	_	_		155									
10/28/20021																								159									
15362031 15362031														-							-			153									
15/1/2021	-					-			-	-			-				_							159									
15/2/2021						_			_	_			_			_	_							159									
15/6/0021																								157									
154/2021	_		1-					+ +	_											1 1		+ +		153	1					1			L
15/7/2021															⊨									153				_					
159(2021	_ T			ЬŦ		<u>+</u>	LF	<u> </u>			ĿГ				L-F	$\pm - \top$		ШF		<u>+</u> -7		±-T		153	±-					L			<u> </u>
1110001	-	1	_		1	_	1 1		T			1							+	1				159	-		-	-		1	-		1
513/0001	_		-			-		-	_										1 1	1		1 1		153	-					1			-
s 1892021 515/2021																								159	4					1			
516/2021			_																					159						-			
5180001 5180001	— T		+			+-	H-F	+ $ T$		_	+	+	+ - 7		⊢–T	-+-		++-	+	+ - 7		+ T				H T				+			<u> </u>
15262021	_		-						_	_					\square		_							159	-								-
5939001																								159						1			1
9282001 9282001			_																					53						1			
10160001	—T		+	++-T		+	+	<u>+</u> -T	+	+	+	+	+ - 7		⊢–T	-+T		++-	++-	+ - 7		$+$ \mp		153	+	— T				<u> </u>			<u> </u>
19270001							1 1	1 1				+ +							1 1	1 1		1 1		197	-								1
1489/021 526/0021																								159	4					1			
3362031			_																					153	1					-			
30.0021	— T		+	++-		+	+	+ T		+	++-	+	+ - 7		⊢–T	-+-T			++-	+ - 7		+ T		153	+	H				<u> </u>			<u> </u>
2/4/2021	_		_						_		+						_					+		159	-								-
34-2021							1 1	1 1				+ +					-		1 1	1 1		1 1		157	4					1			1
(10021 (8/2021			_																					53						1			1
m 2021 16/2021	—T		+	++-T		+	+	<u>+</u> -T	+	+	+	+	+ - 7		⊢–T	-+T		++-	++-	+ - 7		$+$ \mp		153	+	— T				<u> </u>			<u> </u>
110001			-					1 1		1		+ +							+ 1-			1 1		153	-								
13/0021																				1 1				153									1
140001																								159	1					<u> </u>			
316/2021	-		_			_	1												+ +	1				159	-		_	-		1	-		1
3160001																								153									1
a ma2021 2/20/2021																				1 1				153									1
2210001	— T		+			+-	H-F	+ $ T$		_	+	+	+ - 7		⊢ T	-+-		++-	+	+ - 7		+ T		1 1		H T				+			<u> </u>
3/33/0031	-		1	\square		+		+ +	_	-	++				- 1		_	<u> </u>	+	+ 1		+		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4		_			-			-
						1																		159									1
13/25/20021																								153 153 159									
13060001 13060001 13070001					1 -		1 1	1							I T				1 1														. –
2010001 2010001 2010001 2010001 2010001 2010001 2010001																								165									
22520001 2004/0001 2004/0001 2004/0001 2004/0001 2004/0001 2004/0001						_			-															159									

Stering Karch Metropottan District Case No. 20CH208 - Daily Accounting Summary Is prepared by JDS Hydro Consultants, Inc.

EXHIBIT D

SR	MD Pond No. 1	Elevation-Are	ea-Capacity -	JDS-Hydro -	September 2021
a. 11 a				Capacity	
Staff Gage	Depth	Elevation	Area (ac)	(ac-ft)	
0	0.00	7028	0.000	0.000	Reservoir Bottom
2	2.00	7030	1.235	1.230	
4	4.00	7032	1.619	4.090	
6	6.00	7034	2.013	7.720	
8	8.00	7036	2.516	12.250	Spillway Crest / NWL
10	10.00	7038	3.612	17.390	
12	12.00	7040	4.676	24.600	Dam Crest
	Elevati	on-Area-Capa	city Interpol	-	Oth ft.
Staff Gauge	Depth	Elevation	Area (AC)	Capacity (AF)	Comments
0.00	0.00	7028.00	0.00	0.00	Reservoir Bottom
0.01	0.01	7028.01	0.006	0.006	
0.02	0.02	7028.02	0.012	0.012	
0.03	0.03	7028.03	0.018	0.018	
0.04	0.04	7028.04	0.025	0.025	
0.05	0.05	7028.05	0.031	0.031	
0.06	0.06	7028.06	0.037	0.037	
0.07	0.07	7028.07	0.043	0.043	
0.08	0.08	7028.08	0.049	0.049	
0.09	0.09	7028.09	0.055	0.055	
0.10	0.10	7028.10	0.062	0.062	
0.11	0.11	7028.11	0.068	0.068	
0.12	0.12	7028.12	0.074	0.074	
0.13	0.13	7028.13	0.080	0.080	
0.14	0.14	7028.14	0.086	0.086	
0.15	0.15	7028.15	0.092	0.092	
0.16	0.16	7028.16	0.098	0.098	
0.17	0.17	7028.17	0.105	0.105	
0.18	0.18	7028.18	0.111	0.111	
0.19	0.19	7028.19	0.117	0.117	
0.20	0.20	7028.20	0.123	0.123	
0.21	0.21	7028.21	0.129	0.129	
0.22	0.22	7028.22	0.135	0.135	
0.23	0.23	7028.23	0.141	0.141	
0.24	0.24	7028.24	0.148	0.148	
0.25	0.25	7028.25	0.154	0.154	
0.26	0.26	7028.26	0.160	0.160	
0.27	0.27	7028.27	0.166	0.166	
0.28	0.28	7028.28	0.172	0.172	
0.29	0.29	7028.29	0.178	0.178	
0.30	0.30	7028.30	0.185	0.185	
					1

SRM	MD Pond No. 2	Elevation-Are	ea-Capacity -	JDS-Hydro -	September 2021
Staff Gage	Depth	Elevation	Area (ac)	Capacity (ac-ft)	
0	0.00	DATE F	LE000Jar	uaoyood4,	ReservolirlBothornM
1	1.00	7115	0.031	0.020	
2	2.00	7116	0.662	0.360	
4	4.00	7118	1.015	2.040	
6	6.00	7120	1.233	4.290	Spillway Crest / NWL
8	8.00	7122	1.602	6.76	
10	10.00	7124	2.548	9.96	Dam Crest
	Elevat	ion-Area-Capa	city Interpol	ated to 1/10	0th ft.
Staff Gauge	Depth	Elevation	Area (AC)	Capacity (AF)	Comments
0.00	0.00	7114.00	0.000	0.000	Reservoir Bottom
0.01	0.01	7114.01	0.000	0.000	
0.02	0.02	7114.02	0.001	0.000	
0.03	0.03	7114.03	0.001	0.001	
0.04	0.04	7114.04	0.001	0.001	
0.05	0.05	7114.05	0.002	0.001	
0.06	0.06	7114.06	0.002	0.001	
0.07	0.07	7114.07	0.002	0.001	
0.08	0.08	7114.08	0.002	0.002	
0.09	0.09	7114.09	0.003	0.002	
0.10	0.10	7114.10	0.003	0.002	
0.11	0.11	7114.11	0.003	0.002	
0.12	0.12	7114.12	0.004	0.002	
0.13	0.13	7114.13	0.004	0.003	
0.14	0.14	7114.14	0.004	0.003	
0.15	0.15	7114.15	0.005	0.003	
0.16	0.16	7114.16	0.005	0.003	
0.17	0.17	7114.17	0.005	0.003	
0.17	0.17	7114.17	0.005	0.003	1
0.10	0.10	7114.10	0.005	0.004	<u> </u>
0.15	0.10	7114.19	0.006	0.004 0.004	
0.21	0.21	7114.21	0.006	0.004	
0.21	0.21	7114.21	0.007	0.004	
0.22	0.22	7114.22	0.007	0.004	
0.24 0.25	0.24	7114.24 7114.25	0.007	0.005	
0.26	0.26	7114.26	0.008	0.005	
0.27	0.27	7114.27	0.008	0.005	
0.28	0.28	7114.28	0.008	0.006	
0.29	0.29	7114.29	0.009	0.006	
0.30	0.30	7114.30	0.009	0.006	

0.31	0.31	7028.31	0.191	0.191	
0.32	0.32	7028.32	0.197	0.197	
0.33	0.33	7028.33	0.203	0.203	
0.34	0.34	7028.34	0.209	0.209	
0.35	0.35	7028.35	0.215	0.215	
0.36	0.36	7028.36	0.221	0.221	
0.37	0.37	7028.37	0.228	0.228	
0.38	0.38	7028.38	0.234	0.234	
0.39	0.39	7028.39	0.240	0.240	
0.40	0.40	7028.40	0.246	0.246	
0.41	0.41	7028.41	0.252	0.252	
0.42	0.42	7028.42	0.258	0.258	
0.43	0.43	7028.43	0.264	0.264	
0.44	0.44	7028.44	0.271	0.271	
0.45	0.45	7028.45	0.277	0.277	
0.46	0.46	7028.46	0.283	0.283	
0.47	0.47	7028.47	0.289	0.289	
0.48	0.48	7028.48	0.295	0.295	
0.49	0.49	7028.49	0.301	0.301	
0.50	0.50	7028.50	0.308	0.308	
0.51	0.51	7028.51	0.314	0.314	
0.52	0.52	7028.52	0.320	0.320	
0.53	0.53	7028.53	0.326	0.326	
0.54	0.54	7028.54	0.332	0.332	
0.55	0.55	7028.55	0.338	0.338	
0.56	0.56	7028.56	0.344	0.344	
0.57	0.57	7028.57	0.351	0.351	
0.58	0.58	7028.58	0.357	0.357	
0.59	0.59	7028.59	0.363	0.363	
0.60	0.60	7028.60	0.369	0.369	
0.61	0.61	7028.61	0.375	0.375	
0.62	0.62	7028.62	0.381	0.381	
0.63	0.63	7028.63	0.387	0.387	
0.64	0.64	7028.64	0.394	0.394	
0.65	0.65	7028.65	0.400	0.400	
0.66	0.66	7028.66	0.406	0.406	
0.67	0.67	7028.67	0.412	0.412	
0.68	0.68	7028.68	0.418	0.418	
0.69	0.69	7028.69	0.424	0.424	
0.70	0.70	7028.70	0.430	0.430	
0.71	0.71	7028.71	0.437	0.437	
0.72	0.72	7028.72	0.443	0.443	
0.73	0.73	7028.73	0.449	0.449	
0.74	0.74	7028.74	0.455	0.455	
0.75	0.75	7028.75	0.461	0.461	
0.76	0.76	7028.76	0.467	0.467	

		1	1		
0.31	0.31	7114.31	0.009	0.006	
0.32	0.32	7114.32	0.010	0.006	
0.33	0.33	7114.33	0.010	0.007	
0.34	0.34	7114.34	0.010	0.007	
0.35	0.35	7114.35	0.011	0.007	
0.36	0.36	7114.36	0.011	0.007	
0.37	0.37	7114.37	0.011	0.007	
0.38	0.38	7114.38	0.011	0.008	
0.39	0.39	7114.39	0.012	0.008	
0.40	0.40	7114.40	0.012	0.008	
0.41	0.41	7114.41	0.012	0.008	
0.42	0.42	7114.42	0.013	0.008	
0.43	0.43	7114.43	0.013	0.009	
0.44	0.44	7114.44	0.013	0.009	
0.45	0.45	7114.45	0.014	0.009	
0.46	0.46	7114.46	0.014	0.009	
0.47	0.47	7114.47	0.014	0.009	
0.48	0.48	7114.48	0.014	0.010	
0.49	0.49	7114.49	0.015	0.010	
0.50	0.50	7114.50	0.015	0.010	
0.51	0.51	7114.51	0.015	0.010	
0.52	0.52	7114.52	0.016	0.010	
0.53	0.53	7114.53	0.016	0.011	
0.54	0.54	7114.54	0.016	0.011	
0.55	0.55	7114.55	0.017	0.011	
0.56	0.56	7114.56	0.017	0.011	
0.57	0.57	7114.57	0.017	0.011	
0.58	0.58	7114.58	0.017	0.012	
0.59	0.59	7114.59	0.018	0.012	
0.60	0.60	7114.60	0.018	0.012	
0.61	0.61	7114.61	0.018	0.012	
0.62	0.62	7114.62	0.019	0.012	
0.63	0.63	7114.63	0.019	0.013	
0.64	0.64	7114.64	0.019	0.013	
0.65	0.65	7114.65	0.020	0.013	
0.66	0.66	7114.66	0.020	0.013	
0.67	0.67	7114.67	0.020	0.013	
0.68	0.68	7114.68	0.020	0.014	
0.69	0.69	7114.69	0.021	0.014	
0.70	0.70	7114.70	0.021	0.014	
0.71	0.71	7114.71	0.021	0.014	
0.72	0.72	7114.72	0.022	0.014	
0.72 0.73		7114.72 7114.73	0.022	0.014 0.015	
	0.72				
0.73	0.72 0.73	7114.73	0.022	0.015	

0.77	0.77	7028.77	0.474	0.474	
0.78	0.78	7028.78	0.480	0.480	
0.79	0.79	7028.79	0.486	0.486	
0.80	0.80	7028.80	0.492	0.492	
0.81	0.81	7028.81	0.498	0.498	
0.82	0.82	7028.82	0.504	0.504	
0.83	0.83	7028.83	0.510	0.510	
0.84	0.84	7028.84	0.517	0.517	
0.85	0.85	7028.85	0.523	0.523	
0.86	0.86	7028.86	0.529	0.529	
0.87	0.87	7028.87	0.535	0.535	
0.88	0.88	7028.88	0.541	0.541	
0.89	0.89	7028.89	0.547	0.547	
0.90	0.90	7028.90	0.553	0.553	
0.91	0.91	7028.91	0.560	0.560	
0.92	0.92	7028.92	0.566	0.566	
0.93	0.93	7028.93	0.572	0.572	
0.94	0.94	7028.94	0.578	0.578	
0.95	0.95	7028.95	0.584	0.584	
0.96	0.96	7028.96	0.590	0.590	
0.97	0.97	7028.97	0.597	0.597	
0.98	0.98	7028.98	0.603	0.603	
0.00	0.00	7000.00	0.000	0.000	
0.99	0.99	7028.99	0.609	0.609	
0.99 1.00	1.00	7028.99 7029.00	0.609 0.615	0.609 0.615	
1.00	1.00	7029.00	0.615	0.615	
1.00 1.01	1.00 1.01	7029.00 7029.01	0.615 0.621	0.615 0.621	
1.00 1.01 1.02	1.00 1.01 1.02	7029.00 7029.01 7029.02	0.615 0.621 0.627	0.615 0.621 0.627	
1.00 1.01 1.02 1.03	1.00 1.01 1.02 1.03	7029.00 7029.01 7029.02 7029.03	0.615 0.621 0.627 0.633	0.615 0.621 0.627 0.633	
1.00 1.01 1.02 1.03 1.04	1.00 1.01 1.02 1.03 1.04	7029.00 7029.01 7029.02 7029.03 7029.04	0.615 0.621 0.627 0.633 0.640	0.615 0.621 0.627 0.633 0.640	
1.00 1.01 1.02 1.03 1.04 1.05	1.00 1.01 1.02 1.03 1.04 1.05	7029.00 7029.01 7029.02 7029.03 7029.04 7029.05	0.615 0.621 0.627 0.633 0.640 0.646	0.615 0.621 0.627 0.633 0.640 0.646	
1.00 1.01 1.02 1.03 1.04 1.05 1.06	1.00 1.01 1.02 1.03 1.04 1.05 1.06	7029.00 7029.01 7029.02 7029.03 7029.04 7029.05 7029.06	0.615 0.621 0.627 0.633 0.640 0.640 0.652	0.615 0.621 0.627 0.633 0.640 0.640 0.652	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07	7029.00 7029.01 7029.02 7029.03 7029.04 7029.05 7029.06 7029.07	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08	7029.00 7029.01 7029.02 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09	7029.00 7029.01 7029.02 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10	7029.00 7029.01 7029.02 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.01	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.11	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670 0.676 0.683	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670 0.676 0.683	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.11 7029.12 7029.13 7029.14	0.615 0.621 0.627 0.633 0.640 0.652 0.658 0.664 0.670 0.683 0.689 0.695	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670 0.683 0.683 0.689 0.695 0.701	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.11 7029.12 7029.13	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670 0.683 0.689 0.695	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670 0.683 0.683 0.689 0.695	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.11 7029.12 7029.13 7029.14	0.615 0.621 0.627 0.633 0.640 0.652 0.658 0.664 0.670 0.683 0.689 0.695	0.615 0.621 0.627 0.633 0.640 0.640 0.652 0.658 0.664 0.670 0.670 0.683 0.683 0.689 0.695 0.701	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.10 7029.11 7029.12 7029.13 7029.14 7029.15 7029.16 7029.17	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.689 0.695 0.701 0.707 0.713 0.720	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.689 0.695 0.701 0.707 0.713 0.720	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.10 7029.11 7029.12 7029.13 7029.14 7029.15 7029.16 7029.17 7029.18	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.683 0.689 0.695 0.701 0.707 0.713 0.720 0.726	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.683 0.689 0.695 0.701 0.707 0.713 0.720 0.726	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.10 7029.12 7029.13 7029.14 7029.15 7029.16 7029.17 7029.18 7029.19	0.615 0.621 0.627 0.633 0.640 0.652 0.658 0.664 0.670 0.683 0.683 0.695 0.701 0.713 0.720 0.732	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.689 0.695 0.701 0.701 0.713 0.720 0.726 0.732	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19 1.20	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19 1.20	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.10 7029.12 7029.13 7029.14 7029.15 7029.18 7029.19 7029.19	0.615 0.621 0.627 0.633 0.640 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.689 0.695 0.701 0.701 0.713 0.720 0.726 0.732 0.738	0.615 0.621 0.627 0.633 0.640 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.689 0.695 0.701 0.701 0.713 0.720 0.726 0.732 0.738	
1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19	7029.00 7029.01 7029.03 7029.04 7029.05 7029.06 7029.07 7029.08 7029.09 7029.10 7029.12 7029.13 7029.14 7029.15 7029.16 7029.17 7029.18 7029.19	0.615 0.621 0.627 0.633 0.640 0.652 0.658 0.664 0.670 0.683 0.683 0.695 0.701 0.713 0.720 0.732	0.615 0.621 0.627 0.633 0.640 0.646 0.652 0.658 0.664 0.670 0.670 0.676 0.683 0.689 0.695 0.701 0.701 0.713 0.720 0.726 0.732	

0.77 0.77 7114.77 0.023 0.015 0.78 0.78 7114.78 0.023 0.016 0.79 0.79 7114.79 0.024 0.016 0.80 0.80 7114.80 0.024 0.016 0.81 0.81 7114.81 0.025 0.016 0.82 0.82 7114.83 0.025 0.017 0.84 0.84 7114.83 0.026 0.017 0.85 0.85 7114.86 0.026 0.017 0.86 0.86 7114.86 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.86 0.027 0.018 0.89 0.89 7114.90 0.027 0.018 0.91 0.91 7114.91 0.027 0.018 0.92 0.92 7114.93 0.028 0.019 0.94 0.94 7114.94 0.029 0.019 0.95						
0.79 0.79 7114.79 0.024 0.016 0.80 0.80 7114.81 0.024 0.016 0.81 0.81 7114.82 0.025 0.016 0.82 0.82 7114.82 0.025 0.017 0.84 0.84 7114.84 0.026 0.017 0.85 0.85 7114.86 0.026 0.017 0.86 0.86 7114.86 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.88 0.027 0.018 0.90 7114.89 0.027 0.018 0.91 0.91 7114.92 0.027 0.018 0.92 0.92 7114.93 0.028 0.019 0.91 7114.93 0.028 0.019 0.92 0.92 7114.93 0.028 0.019 0.94 7114.95 $0.$	0.77	0.77	7114.77	0.023	0.015	
0.80 0.80 7114.80 0.024 0.016 0.81 0.81 7114.81 0.025 0.016 0.82 0.83 7114.83 0.025 0.017 0.84 0.84 7114.83 0.025 0.017 0.85 0.85 7114.85 0.026 0.017 0.86 0.86 7114.87 0.026 0.017 0.87 0.87 7114.87 0.026 0.018 0.88 0.88 7114.89 0.027 0.018 0.90 0.907 7114.92 0.028 0.018 0.91 0.914 0.027 0.018 0.91 0.91 7114.92 0.028 0.019 0.94 0.94 0.94 7114.95 0.029 0.019 0.95 7114.95 0.029 0.019 0.96 0.96 7114.97 0.229 0.019 0.99 0.99 <	0.78	0.78	7114.78	0.023	0.016	
0.81 0.81 7114.81 0.024 0.016 0.82 0.82 7114.82 0.025 0.016 0.83 0.83 7114.83 0.025 0.017 0.84 0.84 7114.84 0.025 0.017 0.85 0.85 7114.86 0.026 0.017 0.86 0.86 7114.87 0.026 0.017 0.87 0.87 7114.88 0.026 0.018 0.89 0.89 7114.89 0.027 0.018 0.89 0.99 7114.90 0.027 0.018 0.90 0.91 7114.92 0.028 0.019 0.92 0.92 7114.92 0.028 0.019 0.93 0.93 7114.94 0.028 0.019 0.94 0.94 7114.95 0.029 0.019 0.95 0.96 7114.96 0.029 0.019 0.96 7114.96 0.029 0.019 0.97 0.97	0.79	0.79	7114.79	0.024	0.016	
0.82 0.82 7114.82 0.025 0.016 0.83 0.83 7114.84 0.025 0.017 0.84 0.84 7114.85 0.026 0.017 0.85 0.85 7114.87 0.026 0.017 0.86 0.86 7114.87 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.88 0.027 0.018 0.89 0.89 7114.90 0.027 0.018 0.90 7114.90 0.027 0.018 0.91 0.91 7114.92 0.028 0.019 0.92 0.92 7114.92 0.028 0.019 0.93 0.93 7114.94 0.029 0.019 0.94 0.94 7114.95 0.029 0.019 0.95 0.96 7114.96 0.020 0.020 0.99 0.99 7114.97 0.020 0.020 0.99 7114.98	0.80	0.80	7114.80	0.024	0.016	
0.83 0.83 7114.83 0.025 0.017 0.84 0.84 7114.85 0.026 0.017 0.85 0.85 7114.86 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.89 0.027 0.018 0.89 0.89 7114.90 0.027 0.018 0.91 7114.91 0.027 0.018 0.91 0.91 7114.92 0.028 0.019 0.92 0.92 7114.93 0.027 0.018 0.93 0.93 7114.95 0.029 0.019 0.94 0.94 7114.94 0.028 0.019 0.95 7114.95 0.029 0.019 0.96 0.96 7114.96 0.029 0.019 0.97 0.97 $7114.$	0.81	0.81	7114.81	0.024	0.016	
0.84 0.84 7114.84 0.025 0.017 0.85 0.85 7114.85 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.88 0.026 0.017 0.88 0.88 7114.89 0.027 0.018 0.89 0.89 7114.90 0.027 0.018 0.90 0.90 7114.91 0.027 0.018 0.91 0.91 7114.92 0.028 0.019 0.92 0.92 7114.92 0.028 0.019 0.93 0.93 7114.92 0.028 0.019 0.94 0.94 7114.92 0.029 0.019 0.95 0.95 7114.95 0.029 0.019 0.96 0.96 7114.96 0.029 0.019 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.020 0.020 0.09 0.100	0.82	0.82	7114.82	0.025	0.016	
0.85 0.85 7114.85 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.80 0.026 0.017 0.88 0.88 7114.80 0.027 0.018 0.90 0.90 7114.90 0.027 0.018 0.90 0.90 7114.90 0.027 0.018 0.91 0.91 7114.90 0.027 0.018 0.92 0.92 7114.93 0.028 0.019 0.92 0.92 7114.93 0.028 0.019 0.94 0.94 7114.95 0.029 0.019 0.95 0.95 7114.95 0.029 0.019 0.96 0.96 7114.96 0.029 0.019 0.98 0.98 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.026 1.00	0.83	0.83	7114.83	0.025	0.017	
0.86 0.86 7114.86 0.026 0.017 0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.87 0.026 0.018 0.89 0.89 7114.90 0.027 0.018 0.90 0.90 7114.91 0.027 0.018 0.91 0.91 7114.92 0.028 0.018 0.92 0.92 7114.92 0.028 0.019 0.94 0.94 7114.94 0.029 0.019 0.94 0.94 7114.95 0.029 0.019 0.95 0.95 7114.97 0.029 0.019 0.96 0.96 7114.98 0.029 0.020 0.99 0.99 7114.98 0.029 0.020 0.99 0.99 7114.98 0.020 0.020 1.00 1.00 7115.00 0.030 0.020 1.00	0.84	0.84	7114.84	0.025	0.017	
0.87 0.87 7114.87 0.026 0.017 0.88 0.88 7114.88 0.027 0.018 0.90 0.90 7114.90 0.027 0.018 0.90 0.90 7114.90 0.027 0.018 0.91 0.91 7114.92 0.028 0.018 0.92 0.92 7114.92 0.028 0.019 0.93 0.93 7114.93 0.028 0.019 0.94 0.94 7114.94 0.029 0.019 0.95 0.95 7114.97 0.029 0.019 0.96 0.96 7114.97 0.029 0.019 0.98 0.98 7114.97 0.029 0.020 0.99 0.99 7114.97 0.029 0.020 1.00 1.00 7115.00 0.300 0.020 1.00 1.00 7115.00 0.030 0.022 1.03	0.85	0.85	7114.85	0.026	0.017	
0.88 0.89 7114.88 0.026 0.018 0.90 0.90 7114.90 0.027 0.018 0.91 0.91 7114.91 0.027 0.018 0.92 0.92 7114.92 0.028 0.018 0.92 0.92 7114.92 0.028 0.019 0.93 0.93 7114.93 0.028 0.019 0.94 0.94 7114.95 0.029 0.019 0.95 0.95 7114.95 0.029 0.019 0.96 0.96 7114.97 0.029 0.019 0.97 0.97 7114.98 0.029 0.019 0.98 0.98 7114.98 0.020 0.020 0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.02 0.043 0.026 1.03	0.86	0.86	7114.86	0.026	0.017	
0.89 0.89 7114.89 0.027 0.018 0.90 0.91 7114.91 0.027 0.018 0.92 0.92 7114.92 0.028 0.018 0.93 0.92 7114.92 0.028 0.018 0.93 0.93 7114.93 0.028 0.019 0.94 0.94 7114.94 0.029 0.019 0.94 0.94 7114.97 0.029 0.019 0.95 0.95 7114.97 0.029 0.019 0.96 0.96 7114.97 0.029 0.019 0.97 0.97 7114.97 0.029 0.020 0.98 0.98 7114.98 0.029 0.020 0.99 0.97 7114.99 0.030 0.020 0.99 0.97 7115.00 0.030 0.020 1.00 1.00 7115.00 0.043 0.026 1.03	0.87	0.87	7114.87	0.026	0.017	
0.90 0.90 7114.90 0.027 0.018 0.91 0.91 7114.91 0.027 0.018 0.92 0.92 7114.92 0.028 0.018 0.93 0.93 7114.93 0.028 0.019 0.94 0.94 7114.94 0.028 0.019 0.95 0.95 7114.95 0.029 0.019 0.95 0.95 7114.96 0.029 0.019 0.96 0.96 7114.96 0.029 0.019 0.97 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.99 0.300 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.11 1.11 7115.10 0.093 0.050 1.11 1.11 7115.16 0.093 0.056 <	0.88	0.88	7114.88	0.026	0.018	
0.91 0.91 7114.91 0.027 0.018 0.92 0.92 7114.92 0.028 0.018 0.93 0.93 7114.94 0.028 0.019 0.94 0.94 7114.94 0.028 0.019 0.95 0.95 7114.95 0.029 0.019 0.96 0.96 7114.97 0.029 0.019 0.97 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.97 0.029 0.020 0.99 0.99 7114.97 0.020 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.00 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.12 0.106 0.055 1.11 1.13 7115.15 0.124 0.065 1.14 1.14 7115.15 0.124 0.065	0.89	0.89	7114.89	0.027	0.018	
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	0.90	0.90	7114.90	0.027	0.018	
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	0.91	0.91	7114.91	0.027	0.018	
0.94 0.94 7114.94 0.028 0.019 0.95 0.95 7114.95 0.029 0.019 0.96 0.96 7114.97 0.029 0.019 0.97 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.99 0.030 0.020 0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.06 0.068 0.038 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.11 1.10 7115.10 0.093 0.050 1.11 1.11 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.131 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.19 0.150 0.071	0.92	0.92	7114.92	0.028	0.018	
0.95 0.95 7114.95 0.029 0.019 0.96 0.96 7114.97 0.029 0.019 0.97 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.11 1.10 7115.10 0.093 0.050 1.11 1.10 7115.12 0.106 0.056 1.12 1.12 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.16 0.131 0.068 1.11 1.16 7115.16 0.131 0.068 1.11 1.19 7115.19 0.171 1.18 1.18 7115.20 0.156 1.19 <td< td=""><td>0.93</td><td>0.93</td><td>7114.93</td><td>0.028</td><td>0.019</td><td></td></td<>	0.93	0.93	7114.93	0.028	0.019	
0.96 0.96 7114.96 0.029 0.019 0.97 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.05 0.061 0.035 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11	0.94	0.94	7114.94	0.028	0.019	
0.97 0.97 7114.97 0.029 0.019 0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.10 0.099 0.053 1.12	0.95	0.95	7114.95	0.029	0.019	
0.98 0.98 7114.98 0.029 0.020 0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.131 0.062 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.20 0.156 0.080 1.21 1.20 7115.21 0.162 0.083	0.96	0.96	7114.96	0.029	0.019	
0.99 0.99 7114.99 0.030 0.020 1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.05 0.061 0.035 1.05 1.05 7115.05 0.061 0.038 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.08 1.08 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13	0.97	0.97	7114.97	0.029	0.019	
1.00 1.00 7115.00 0.030 0.020 1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.06 1.06 7115.07 0.074 0.041 1.08 1.08 7115.09 0.087 0.047 1.09 1.09 7115.00 0.093 0.050 1.11 1.10 7115.10 0.093 0.050 1.11 1.11 7115.10 0.099 0.053 1.12 1.12 7115.10 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.15 0.124 0.065 1.16	0.98	0.98	7114.98	0.029	0.020	
1.01 1.01 7115.01 0.036 0.023 1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.12 0.106 0.056 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.15 0.124 0.065 1.14 1.16 7115.16 0.131 0.068 1.17 1.16 7115.17 0.137 0.071 1.18 1.18 7115.19 0.143 0.074 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	0.00	0.00	7114.00	0.020	0.020	
1.02 1.02 7115.02 0.043 0.026 1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.10 7115.10 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.143 0.074 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	0.99	0.99	/114.99	0.030	0.020	
1.03 1.03 7115.03 0.049 0.029 1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.10 7115.10 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.143 0.074 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083						
1.04 1.04 7115.04 0.055 0.032 1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.09 0.087 0.041 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.19 1.19 7115.20 0.156 0.080 1.21 1.21	1.00	1.00	7115.00	0.030	0.020	
1.05 1.05 7115.05 0.061 0.035 1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.09 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.15 0.124 0.065 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.17 0.137 0.071 1.18 1.18 7115.18 0.143 0.074 1.19 1.19 7115.20 0.156 0.080 1.20 1.20 7115.21 0.162 0.083	1.00 1.01	1.00 1.01	7115.00 7115.01	0.030 0.036	0.020 0.023	
1.06 1.06 7115.06 0.068 0.038 1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.10 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.20 1.20 7115.20 0.162 0.083	1.00 1.01 1.02	1.00 1.01 1.02	7115.00 7115.01 7115.02	0.030 0.036 0.043	0.020 0.023 0.026	
1.07 1.07 7115.07 0.074 0.041 1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.20 1.20 7115.21 0.162 0.083	1.00 1.01 1.02 1.03	1.00 1.01 1.02 1.03	7115.00 7115.01 7115.02 7115.03	0.030 0.036 0.043 0.049	0.020 0.023 0.026 0.029	
1.08 1.08 7115.08 0.080 0.044 1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.18 0.143 0.074 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04	1.00 1.01 1.02 1.03 1.04	7115.00 7115.01 7115.02 7115.03 7115.04	0.030 0.036 0.043 0.049 0.055	0.020 0.023 0.026 0.029 0.032	
1.09 1.09 7115.09 0.087 0.047 1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.20 1.20 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05	1.00 1.01 1.02 1.03 1.04 1.05	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05	0.030 0.036 0.043 0.049 0.055 0.061	0.020 0.023 0.026 0.029 0.032 0.035	
1.10 1.10 7115.10 0.093 0.050 1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06	1.00 1.01 1.02 1.03 1.04 1.05 1.06	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06	0.030 0.036 0.043 0.049 0.055 0.061 0.068	0.023 0.023 0.026 0.029 0.032 0.035 0.038	
1.11 1.11 7115.11 0.099 0.053 1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041	
1.12 1.12 7115.12 0.106 0.056 1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044	
1.13 1.13 7115.13 0.112 0.059 1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044	
1.14 1.14 7115.14 0.118 0.062 1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.19 0.150 0.077 1.19 1.19 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050	
1.15 1.15 7115.15 0.124 0.065 1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.18 0.143 0.074 1.19 1.19 7115.19 0.150 0.077 1.20 1.20 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053	
1.16 1.16 7115.16 0.131 0.068 1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.18 0.143 0.074 1.19 1.19 7115.19 0.150 0.077 1.20 1.20 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093 0.099 0.106	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056	
1.17 1.17 7115.17 0.137 0.071 1.18 1.18 7115.18 0.143 0.074 1.19 1.19 7115.19 0.150 0.077 1.20 1.20 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093 0.099 0.106	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056	
1.18 1.18 7115.18 0.143 0.074 1.19 1.19 7115.19 0.150 0.077 1.20 1.20 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093 0.099 0.106 0.112 0.118	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062	
1.19 1.19 7115.19 0.150 0.077 1.20 1.20 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14 7115.15	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.093 0.099 0.106 0.112 0.118 0.124	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062	
1.20 1.20 7115.20 0.156 0.080 1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14 7115.15	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.093 0.099 0.106 0.112 0.118 0.124 0.131	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062 0.065	
1.21 1.21 7115.21 0.162 0.083	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14 1.15 1.16 1.17	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14 7115.15 7115.16 7115.17	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.093 0.099 0.106 0.112 0.118 0.124 0.131	0.020 0.023 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062 0.068 0.071	
	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14 7115.15 7115.16 7115.17 7115.18	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093 0.106 0.112 0.118 0.124 0.137 0.143	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062 0.068 0.071	
1.22 1.22 7115.22 0.169 0.086	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14 7115.15 7115.16 7115.17 7115.18 7115.19	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.093 0.099 0.106 0.112 0.118 0.124 0.137 0.143 0.150	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062 0.068 0.071 0.074	
	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19 1.20	1.00 1.01 1.02 1.03 1.04 1.05 1.06 1.07 1.08 1.09 1.10 1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19 1.20	7115.00 7115.01 7115.02 7115.03 7115.04 7115.05 7115.06 7115.07 7115.08 7115.09 7115.10 7115.11 7115.12 7115.13 7115.14 7115.15 7115.16 7115.17 7115.18 7115.19 7115.20	0.030 0.036 0.043 0.049 0.055 0.061 0.068 0.074 0.080 0.087 0.093 0.099 0.106 0.112 0.118 0.124 0.137 0.143 0.150	0.020 0.023 0.026 0.029 0.032 0.035 0.038 0.041 0.044 0.047 0.050 0.053 0.056 0.059 0.062 0.065 0.068 0.071 0.080	

1.23	1.23	7029.23	0.756	0.756	
1.23	1.23	7029.23	0.763	0.750	
1.24	1.24	7029.24 7029.25	0.763	0.763 0.769	
1.25	1.25	7029.26	0.775	0.775	
1.27	1.27	7029.27	0.781	0.781	
1.28	1.28	7029.28	0.787	0.787	
1.29	1.29	7029.29	0.793	0.793	
1.30	1.30	7029.30	0.799	0.799	
1.31	1.31	7029.31	0.806	0.806	
1.32	1.32	7029.32	0.812	0.812	
1.33	1.33	7029.33	0.818	0.818	
1.34	1.34	7029.34	0.824	0.824	
1.35	1.35	7029.35	0.830	0.830	
1.36	1.36	7029.36	0.836	0.836	
1.37	1.37	7029.37	0.843	0.843	
1.38	1.38	7029.38	0.849	0.849	
1.39	1.39	7029.39	0.855	0.855	
1.40	1.40	7029.40	0.861	0.861	
1.41	1.41	7029.41	0.867	0.867	
1.42	1.42	7029.42	0.873	0.873	
1.43	1.43	7029.43	0.879	0.879	
1.44	1.44	7029.44	0.886	0.886	
1.45	1.45	7029.45	0.892	0.892	
1.46	1.46	7029.46	0.898	0.898	
1.47	1.47	7029.47	0.904	0.904	
1.48	1.48	7029.48	0.910	0.910	
1.49	1.49	7029.49	0.916	0.916	
1.50	1.50	7029.50	0.922	0.922	
1.51	1.51	7029.51	0.929	0.929	
1.52	1.52	7029.52	0.935	0.935	
1.53	1.53	7029.53	0.941	0.941	
1.54	1.54	7029.54	0.947	0.947	
1.55	1.55	7029.55	0.953	0.953	
1.56	1.56	7029.56	0.959	0.959	
1.57	1.57	7029.57	0.966	0.966	
1.58	1.58	7029.58	0.972	0.972	
1.59	1.59	7029.59	0.978	0.978	
1.60	1.60	7029.60	0.984	0.984	
1.61	1.61	7029.61	0.990	0.990	
1.62	1.62	7029.62	0.996	0.996	
1.63	1.63	7029.62	1.002	1.002	
1.64	1.64	7029.63	1.002	1.002	
1.64	1.64	7029.64 7029.65	1.009 1.015	1.009 1.015	
1.66	1.66	7029.66	1.021	1.021	
1.67	1.67	7029.67	1.027	1.027	
1.68	1.68	7029.68	1.033	1.033	

1.23 1.24	1.23	7115.23			
	1.24	7115.24	0.175 0.181	0.089 0.092	
1.25	1.25	7115.25	0.187	0.095	
1.26	1.26	7115.26	0.194	0.098	
1.27	1.27	7115.27	0.200	0.101	
1.28	1.28	7115.28	0.206	0.104	
1.29	1.29	7115.29	0.213	0.107	
1.30	1.30	7115.30	0.219	0.110	
1.31	1.31	7115.31	0.225	0.113	
1.32	1.32	7115.32	0.232	0.116	
1.33	1.33	7115.33	0.238	0.119	
1.34	1.34	7115.34	0.244	0.122	
1.35	1.35	7115.35	0.250	0.125	
1.36	1.36	7115.36	0.257	0.128	
1.37	1.37	7115.37	0.263	0.131	
1.38	1.38	7115.38	0.269	0.134	
1.39	1.39	7115.39	0.276	0.137	
1.40	1.40	7115.40	0.282	0.140	
1.41	1.41	7115.41	0.288	0.143	
1.42	1.42	7115.42	0.295	0.146	
1.43	1.43	7115.43	0.301	0.149	
1.44	1.44	7115.44	0.307	0.152	
1.45	1.45	7115.45	0.313	0.155	
1.46	1.46	7115.46	0.320	0.158	
1.47	1.47	7115.47	0.326	0.161	
1.48	1.48	7115.48	0.332	0.164	
1.49	1.49	7115.49	0.339	0.167	
1.50	1.50	7115.50	0.345	0.170	
1.51	1.51	7115.51	0.351	0.173	
1.52	1.52	7115.52	0.358	0.176	
1.53	1.53	7115.53	0.364	0.179	
1.54	1.54	7115.54	0.370	0.182	
1.55	1.55	7115.55	0.376	0.185	
1.56	1.56	7115.56	0.383	0.188	
1.57	1.57	7115.57	0.389	0.191	
1.58	1.58	7115.58	0.395	0.194	
1.59	1.59	7115.59	0.402	0.197	
1.60	1.60	7115.60	0.408	0.200	
1.61	1.61	7115.61	0.414	0.203	
1.62	1.62	7115.62	0.420	0.206	
1.63	1.63	7115.63	0.427	0.209	
1.64	1.64	7115.64	0.433	0.212	
1.65	1.65	7115.65	0.439	0.215	
1.66	1.66	7115.66	0.446	0.218	
1.67	1.67	7115.67	0.452	0.221	
1.68	1.68	7115.68	0.458	0.224	

1.69	1.69	7029.69	1.039	1.039	
1.70	1.70	7029.70	1.046	1.046	
1.71	1.71	7029.71	1.052	1.052	
1.72	1.72	7029.72	1.058	1.058	
1.73	1.73	7029.73	1.064	1.064	
1.74	1.74	7029.74	1.070	1.070	
1.75	1.75	7029.75	1.076	1.076	
1.76	1.76	7029.76	1.082	1.082	
1.77	1.77	7029.77	1.089	1.089	
1.78	1.78	7029.78	1.095	1.095	
1.79	1.79	7029.79	1.101	1.101	
1.80	1.80	7029.80	1.107	1.107	
1.81	1.81	7029.81	1.113	1.113	
1.82	1.82	7029.82	1.119	1.119	
1.83	1.83	7029.83	1.125	1.125	
1.84	1.84	7029.84	1.132	1.132	
1.85	1.85	7029.85	1.138	1.138	
1.86	1.86	7029.86	1.144	1.144	
1.87	1.87	7029.87	1.150	1.150	
1.88	1.88	7029.88	1.156	1.156	
1.89	1.89	7029.89	1.162	1.162	
1.90	1.90	7029.90	1.169	1.169	
1.91	1.91	7029.91	1.175	1.175	
1.92	1.92	7029.92	1.181	1.181	
1.93	1.93	7029.93	1.187	1.187	
1.94	1.94	7029.94	1.193	1.193	
1.95	1.95	7029.95	1.199	1.199	
1.96	1.96	7029.96	1.205	1.205	
1.97	1.97	7029.97	1.212	1.212	
1.98	1.98	7029.98	1.218	1.218	
1.99	1.99	7029.99	1.224	1.224	
2.00	2.00	7030.00	1.230	1.230	
2.01	2.01	7030.01	1.232	1.244	
2.02	2.02	7030.02	1.234	1.259	
2.03	2.03	7030.03	1.236	1.273	
2.04	2.04	7030.04	1.238	1.287	
2.05	2.05	7030.05	1.240	1.302	
2.06	2.06	7030.06	1.242	1.316	
2.07	2.07	7030.07	1.244	1.330	
2.08	2.08	7030.08	1.246	1.344	
2.09	2.09	7030.09	1.248	1.359	
2.10	2.10	7030.10	1.250	1.373	
2.11	2.11	7030.11	1.251	1.387	
2.12	2.12	7030.12	1.253	1.402	
2.13	2.13	7030.13	1.255	1.416	
2.14	2.14	7030.14	1.257	1.430	

1.00	1.00	7115 00	0.465	0.007	
1.69 1.70	1.69 1.70	7115.69 7115.70	0.465	0.227	
1.71	1.71	7115.71	0.477	0.233	
1.72 1.73	1.72 1.73	7115.72	0.483	0.236	
-		7115.73	0.490	0.239	
1.74	1.74	7115.74	0.496	0.242	
1.75	1.75	7115.75	0.502	0.245	
1.76	1.76	7115.76	0.509	0.248	
1.77	1.77	7115.77	0.515	0.251	
1.78	1.78	7115.78	0.521	0.254	
1.79	1.79	7115.79	0.528	0.257	
1.80	1.80	7115.80	0.534	0.260	
1.81	1.81	7115.81	0.540	0.263	
1.82	1.82	7115.82	0.546	0.266	
1.83	1.83	7115.83	0.553	0.269	
1.84	1.84	7115.84	0.559	0.272	
1.85	1.85	7115.85	0.565	0.275	
1.86	1.86	7115.86	0.572	0.278	
1.87	1.87	7115.87	0.578	0.281	
1.88	1.88	7115.88	0.584	0.284	
1.89	1.89	7115.89	0.591	0.287	
1.90	1.90	7115.90	0.597	0.290	
1.91	1.91	7115.91	0.603	0.293	
1.92	1.92	7115.92	0.609	0.296	
1.93	1.93	7115.93	0.616	0.299	
1.94	1.94	7115.94	0.622	0.302	
1.95	1.95	7115.95	0.628	0.305	
1.96	1.96	7115.96	0.635	0.308	
1.97	1.97	7115.97	0.641	0.311	
1.98	1.98	7115.98	0.647	0.314	
1.99	1.99	7115.99	0.654	0.317	
2.00	2.00	7116.00	0.662	0.360	
2.01	2.01	7116.01	0.664	0.368	
2.02	2.02	7116.02	0.665	0.377	
2.03	2.03	7116.03	0.667	0.385	
2.04	2.04	7116.04	0.669	0.394	
2.05	2.05	7116.05	0.671	0.402	
2.06	2.06	7116.06	0.673	0.410	
2.07	2.07	7116.07	0.674	0.419	
2.08	2.08	7116.08	0.676	0.427	
2.09	2.09	7116.09	0.678	0.436	
2.10	2.10	7116.10	0.680	0.444	
2.11	2.11	7116.11	0.681	0.452	
2.12	2.12	7116.12	0.683	0.461	
2.13	2.13	7116.13	0.685	0.469	
2.14	2.14	7116.14	0.687	0.478	

2.15	2.15	7030.15	1.259	1.445	
2.16	2.16	7030.16	1.261	1.459	
2.17	2.17	7030.17	1.263	1.473	
2.18	2.18	7030.18	1.265	1.487	
2.19	2.19	7030.19	1.267	1.502	
2.20	2.20	7030.20	1.269	1.516	
2.21	2.21	7030.21	1.271	1.530	
2.22	2.22	7030.22	1.273	1.545	
2.23	2.23	7030.23	1.275	1.559	
2.24	2.24	7030.24	1.277	1.573	
2.25	2.25	7030.25	1.279	1.588	
2.26	2.26	7030.26	1.281	1.602	
2.27	2.27	7030.27	1.283	1.616	
2.28	2.28	7030.28	1.285	1.630	
2.29	2.29	7030.29	1.287	1.645	
2.30	2.30	7030.30	1.289	1.659	
2.31	2.31	7030.31	1.290	1.673	
2.32	2.32	7030.32	1.292	1.688	
2.33	2.33	7030.33	1.294	1.702	
2.34	2.34	7030.34	1.296	1.716	
2.35	2.35	7030.35	1.298	1.731	
2.36	2.36	7030.36	1.300	1.745	
2.37	2.37	7030.37	1.302	1.759	
2.38	2.38	7030.38	1.304	1.773	
2.39	2.39	7030.39	1.306	1.788	
2.40	2.40	7030.40	1.308	1.802	
2.41	2.41	7030.41	1.310	1.816	
2.42	2.42	7030.42	1.312	1.831	
2.43	2.43	7030.43	1.314	1.845	
2.44	2.44	7030.44	1.316	1.859	
2.45	2.45	7030.45	1.318	1.874	
2.46	2.46	7030.46	1.320	1.888	
2.47	2.47	7030.47	1.322	1.902	
2.48	2.48	7030.48	1.324	1.916	
2.49	2.49	7030.49	1.326	1.931	
2.50	2.50	7030.50	1.327	1.945	
2.51	2.51	7030.51	1.329	1.959	
2.52	2.52	7030.52	1.331	1.974	
2.53	2.53	7030.53	1.333	1.988	
2.54	2.54	7030.54	1.335	2.002	
2.55	2.55	7030.55	1.337	2.017	
2.56	2.56	7030.56	1.339	2.031	
2.57	2.57	7030.57	1.341	2.045	
2.58	2.58	7030.58	1.343	2.059	
2.59	2.59	7030.59	1.345	2.074	
2.60	2.60	7030.60	1.347	2.088	

2.15	2.15	7116.15	0.688	0.486	
2.16	2.16	7116.16	0.690	0.494	
2.17	2.17	7116.17	0.692	0.503	
2.18	2.18	7116.18	0.694	0.511	
2.19	2.19	7116.19	0.696	0.520	
2.20	2.20	7116.20	0.697	0.528	
2.21	2.21	7116.21	0.699	0.536	
2.22	2.22	7116.22	0.701	0.545	
2.23	2.23	7116.23	0.703	0.553	
2.24	2.24	7116.24	0.704	0.562	
2.25	2.25	7116.25	0.706	0.570	
2.26	2.26	7116.26	0.708	0.578	
2.27	2.27	7116.27	0.710	0.587	
2.28	2.28	7116.28	0.711	0.595	
2.29	2.29	7116.29	0.713	0.604	
2.30	2.30	7116.30	0.715	0.612	
2.31	2.31	7116.31	0.717	0.620	
2.32	2.32	7116.32	0.719	0.629	
2.33	2.33	7116.33	0.720	0.637	
2.34	2.34	7116.34	0.722	0.646	
2.35	2.35	7116.35	0.724	0.654	
2.36	2.36	7116.36	0.726	0.662	
2.37	2.37	7116.37	0.727	0.671	
2.38	2.38	7116.38	0.729	0.679	
2.39	2.39	7116.39	0.731	0.688	
2.40	2.40	7116.40	0.733	0.696	
2.41	2.41	7116.41	0.734	0.704	
2.42	2.42	7116.42	0.736	0.713	
2.43	2.43	7116.43	0.738	0.721	
2.44	2.44	7116.44	0.740	0.730	
2.45	2.45	7116.45	0.742	0.738	
2.46	2.46	7116.46	0.743	0.746	
2.47	2.47	7116.47	0.745	0.755	
2.48	2.48	7116.48	0.747	0.763	
2.49	2.49	7116.49	0.749	0.772	
2.50	2.50	7116.50	0.750	0.780	
2.51	2.51	7116.51	0.752	0.788	
2.52	2.52	7116.52	0.754	0.797	
2.53	2.53	7116.53	0.756	0.805	
2.54	2.54	7116.54	0.757	0.814	
2.55	2.55	7116.55	0.759	0.822	
2.56	2.56	7116.56	0.761	0.830	
2.57	2.57	7116.57	0.763	0.839	
2.58	2.58	7116.58	0.765	0.847	
2.59	2.59	7116.59	0.766	0.856	
2.60	2.60	7116.60	0.768	0.864	

2.61	2.61	7030.61	1.349	2.102	
2.62	2.62	7030.62	1.351	2.117	
2.63	2.63	7030.63	1.353	2.131	
2.64	2.64	7030.64	1.355	2.145	
2.65	2.65	7030.65	1.357	2.160	
2.66	2.66	7030.66	1.359	2.174	
2.67	2.67	7030.67	1.361	2.188	
2.68	2.68	7030.68	1.363	2.202	
2.69	2.69	7030.69	1.365	2.217	
2.70	2.70	7030.70	1.366	2.231	
2.71	2.71	7030.71	1.368	2.245	
2.72	2.72	7030.72	1.370	2.260	
2.73	2.73	7030.73	1.372	2.274	
2.74	2.74	7030.74	1.374	2.288	
2.75	2.75	7030.75	1.376	2.303	
2.76	2.76	7030.76	1.378	2.317	
2.77	2.77	7030.77	1.380	2.331	
2.78	2.78	7030.78	1.382	2.345	
2.79	2.79	7030.79	1.384	2.360	
2.80	2.80	7030.80	1.386	2.374	
2.81	2.81	7030.81	1.388	2.388	
2.82	2.82	7030.82	1.390	2.403	
2.83	2.83	7030.83	1.392	2.417	
2.84	2.84	7030.84	1.394	2.431	
2.85	2.85	7030.85	1.396	2.446	
2.86	2.86	7030.86	1.398	2.460	
2.87	2.87	7030.87	1.400	2.474	
2.88	2.88	7030.88	1.402	2.488	
2.89	2.89	7030.89	1.404	2.503	
2.90	2.90	7030.90	1.405	2.517	
2.91	2.91	7030.91	1.407	2.531	
2.92	2.92	7030.92	1.409	2.546	
2.93	2.93	7030.93	1.411	2.560	
2.94	2.94	7030.94	1.413	2.574	
2.95	2.95	7030.95	1.415	2.589	
2.96	2.96	7030.96	1.417	2.603	
2.97	2.97	7030.97	1.419	2.617	
2.98	2.98	7030.98	1.421	2.631	
2.99	2.99	7030.99	1.423	2.646	
3.00	3.00	7031.00	1.425	2.660	
3.01	3.01	7031.01	1.427	2.674	
3.02	3.02	7031.02	1.429	2.689	
3.03	3.03	7031.03	1.431	2.703	
3.04	3.04	7031.04	1.433	2.717	
3.05	3.05	7031.05	1.435	2.732	
3.06	3.06	7031.06	1.437	2.746	

2.61	2.61	7116.61	0.770	0.872	
2.62	2.62	7116.62	0.772	0.881	
2.63	2.63	7116.63	0.773	0.889	
2.64	2.64	7116.64	0.775	0.898	
2.65	2.65	7116.65	0.777	0.906	
2.66	2.66	7116.66	0.779	0.914	
2.67	2.67	7116.67	0.780	0.923	
2.68	2.68	7116.68	0.782	0.931	
2.69	2.69	7116.69	0.784	0.940	
2.70	2.70	7116.70	0.786	0.948	
2.71	2.71	7116.71	0.788	0.956	
2.72	2.72	7116.72	0.789	0.965	
2.73	2.73	7116.73	0.791	0.973	
2.74	2.74	7116.74	0.793	0.982	
2.75	2.75	7116.75	0.795	0.990	
2.76	2.76	7116.76	0.796	0.998	
2.77	2.77	7116.77	0.798	1.007	
2.78	2.78	7116.78	0.800	1.015	
2.79	2.79	7116.79	0.802	1.024	
2.80	2.80	7116.80	0.803	1.032	
2.81	2.81	7116.81	0.805	1.040	
2.82	2.82	7116.82	0.807	1.049	
2.83	2.83	7116.83	0.809	1.057	
2.84	2.84	7116.84	0.811	1.066	
2.85	2.85	7116.85	0.812	1.074	
2.86	2.86	7116.86	0.814	1.082	
2.87	2.87	7116.87	0.816	1.091	
2.88	2.88	7116.88	0.818	1.099	
2.89	2.89	7116.89	0.819	1.108	
2.90	2.90	7116.90	0.821	1.116	
2.91	2.91	7116.91	0.823	1.124	
2.92	2.92	7116.92	0.825	1.133	
2.93	2.93	7116.93	0.827	1.141	
2.94	2.94	7116.94	0.828	1.150	
2.95	2.95	7116.95	0.830	1.158	
2.96	2.96	7116.96	0.832	1.166	
2.97	2.97	7116.97	0.834	1.175	
2.98	2.98	7116.98	0.835	1.183	
2.99	2.99	7116.99	0.837	1.192	
3.00	3.00	7117.00	0.839	1.200	
3.01	3.01	7117.01	0.841	1.208	
3.02	3.02	7117.02	0.842	1.217	
3.03	3.03	7117.03	0.844	1.225	
3.04	3.04	7117.04	0.846	1.234	
3.05	3.05	7117.05	0.848	1.242	
3.06	3.06	7117.06	0.850	1.250	

2.07	7021.07	1 /20	2 760	
		-		
-		-	-	
		-		
3.25	7031.25	1.474	3.018	
3.26	7031.26	1.476	3.032	
3.27	7031.27	1.478	3.046	
3.28	7031.28	1.480	3.060	
3.29	7031.29	1.482	3.075	
3.30	7031.30	1.483	3.089	
3.31	7031.31	1.485	3.103	
3.32	7031.32	1.487	3.118	
3.33	7031.33	1.489	3.132	
3.34	7031.34	1.491	3.146	
3.35	7031.35	1.493	3.161	
3.36	7031.36	1.495	3.175	
3.37	7031.37	1.497	3.189	
3.38	7031.38	1.499	3.203	
3.39	7031.39	1.501	3.218	
3.40	7031.40	1.503	3.232	
3.41	7031.41	1.505	3.246	
3.42	7031.42	1.507	3.261	
3.43	7031.43	1.509	3.275	
3.44	7031.44	1.511	3.289	
3.45	7031.45	1.513	3.304	
3.46	7031.46	1.515	3.318	
	7024 47	1 5 1 7	3.332	
3.47	/031.4/	1.517		
3.47 3.48	7031.47	1.519	3.346	
3.48	7031.48	1.519	3.346	
3.48 3.49	7031.48 7031.49	1.519 1.521	3.346 3.361	
	3.27 3.28 3.29 3.30 3.31 3.32 3.33 3.34 3.35 3.36 3.37 3.38 3.39 3.40 3.41 3.42 3.43 3.44 3.45 3.46	3.08 7031.08 3.09 7031.09 3.10 7031.11 3.12 7031.12 3.13 7031.13 3.14 7031.14 3.15 7031.15 3.16 7031.17 3.18 7031.18 3.14 7031.17 3.15 7031.17 3.16 7031.17 3.18 7031.19 3.19 7031.19 3.20 7031.20 3.21 7031.21 3.22 7031.23 3.24 7031.24 3.25 7031.25 3.26 7031.26 3.27 7031.27 3.28 7031.28 3.29 7031.29 3.30 7031.30 3.31 7031.31 3.32 7031.32 3.33 7031.33 3.34 7031.34 3.35 7031.36 3.37 7031.37 3.38 7031.38 <td>3.08 7031.08 1.441 3.09 7031.09 1.443 3.10 7031.10 1.444 3.11 7031.12 1.444 3.12 7031.12 1.448 3.13 7031.13 1.450 3.14 7031.14 1.452 3.15 7031.15 1.454 3.16 7031.17 1.458 3.17 7031.17 1.458 3.18 7031.19 1.462 3.20 7031.20 1.464 3.21 7031.21 1.466 3.22 7031.22 1.468 3.23 7031.23 1.470 3.24 7031.24 1.472 3.25 7031.27 1.478 3.26 7031.27 1.478 3.28 7031.29 1.482 3.30 7031.30 1.483 3.31 7031.31 1.485 3.32 7031.32 1.487 3.33 7031.33 1.489 <td>3.087031.081.4412.7743.097031.091.4432.7893.107031.101.4442.8033.117031.121.4482.8323.127031.121.4482.8323.137031.131.4502.8463.147031.141.4522.8603.157031.151.4542.8753.167031.161.4562.8893.177031.171.4582.9033.187031.181.4602.9173.197031.191.4622.9323.207031.201.4642.9463.217031.211.4662.9603.227031.221.4682.9753.237031.231.4702.9893.247031.241.4723.0033.257031.251.4743.0183.267031.261.4763.0323.277031.271.4783.0463.287031.301.4833.0603.297031.311.4853.1033.317031.311.4853.1033.327031.321.4873.1183.337031.331.4893.1323.347031.341.4913.1463.357031.351.4933.1613.367031.361.4973.1893.387031.381.4993.2033.397031.391.5013.2183.407031.411.5053.246<!--</td--></td></td>	3.08 7031.08 1.441 3.09 7031.09 1.443 3.10 7031.10 1.444 3.11 7031.12 1.444 3.12 7031.12 1.448 3.13 7031.13 1.450 3.14 7031.14 1.452 3.15 7031.15 1.454 3.16 7031.17 1.458 3.17 7031.17 1.458 3.18 7031.19 1.462 3.20 7031.20 1.464 3.21 7031.21 1.466 3.22 7031.22 1.468 3.23 7031.23 1.470 3.24 7031.24 1.472 3.25 7031.27 1.478 3.26 7031.27 1.478 3.28 7031.29 1.482 3.30 7031.30 1.483 3.31 7031.31 1.485 3.32 7031.32 1.487 3.33 7031.33 1.489 <td>3.087031.081.4412.7743.097031.091.4432.7893.107031.101.4442.8033.117031.121.4482.8323.127031.121.4482.8323.137031.131.4502.8463.147031.141.4522.8603.157031.151.4542.8753.167031.161.4562.8893.177031.171.4582.9033.187031.181.4602.9173.197031.191.4622.9323.207031.201.4642.9463.217031.211.4662.9603.227031.221.4682.9753.237031.231.4702.9893.247031.241.4723.0033.257031.251.4743.0183.267031.261.4763.0323.277031.271.4783.0463.287031.301.4833.0603.297031.311.4853.1033.317031.311.4853.1033.327031.321.4873.1183.337031.331.4893.1323.347031.341.4913.1463.357031.351.4933.1613.367031.361.4973.1893.387031.381.4993.2033.397031.391.5013.2183.407031.411.5053.246<!--</td--></td>	3.087031.081.4412.7743.097031.091.4432.7893.107031.101.4442.8033.117031.121.4482.8323.127031.121.4482.8323.137031.131.4502.8463.147031.141.4522.8603.157031.151.4542.8753.167031.161.4562.8893.177031.171.4582.9033.187031.181.4602.9173.197031.191.4622.9323.207031.201.4642.9463.217031.211.4662.9603.227031.221.4682.9753.237031.231.4702.9893.247031.241.4723.0033.257031.251.4743.0183.267031.261.4763.0323.277031.271.4783.0463.287031.301.4833.0603.297031.311.4853.1033.317031.311.4853.1033.327031.321.4873.1183.337031.331.4893.1323.347031.341.4913.1463.357031.351.4933.1613.367031.361.4973.1893.387031.381.4993.2033.397031.391.5013.2183.407031.411.5053.246 </td

	-				
3.07	3.07	7117.07	0.851	1.259	
3.08	3.08	7117.08	0.853	1.267	
3.09	3.09	7117.09	0.855	1.276	
3.10	3.10	7117.10	0.857	1.284	
3.11	3.11	7117.11	0.858	1.292	
3.12	3.12	7117.12	0.860	1.301	
3.13	3.13	7117.13	0.862	1.309	
3.14	3.14	7117.14	0.864	1.318	
3.15	3.15	7117.15	0.865	1.326	
3.16	3.16	7117.16	0.867	1.334	
3.17	3.17	7117.17	0.869	1.343	
3.18	3.18	7117.18	0.871	1.351	
3.19	3.19	7117.19	0.873	1.360	
3.20	3.20	7117.20	0.874	1.368	
3.21	3.21	7117.21	0.876	1.376	
3.22	3.22	7117.22	0.878	1.385	
3.23	3.23	7117.23	0.880	1.393	
3.24	3.24	7117.24	0.881	1.402	
3.25	3.25	7117.25	0.883	1.410	
3.26	3.26	7117.26	0.885	1.418	
3.27	3.27	7117.27	0.887	1.427	
3.28	3.28	7117.28	0.888	1.435	
3.29	3.29	7117.29	0.890	1.444	
3.30	3.30	7117.30	0.892	1.452	
3.31	3.31	7117.31	0.894	1.460	
3.32	3.32	7117.32	0.896	1.469	
3.33	3.33	7117.33	0.897	1.477	
3.34	3.34	7117.34	0.899	1.486	
3.35	3.35	7117.35	0.901	1.494	
3.36	3.36	7117.36	0.903	1.502	
3.37	3.37	7117.37	0.904	1.511	
3.38	3.38	7117.38	0.906	1.519	
3.39	3.39	7117.39	0.908	1.528	
3.40	3.40	7117.40	0.910	1.536	
3.41	3.41	7117.41	0.911	1.544	
3.42	3.42	7117.42	0.913	1.553	
3.43	3.43	7117.43	0.915	1.561	
3.44	3.44	7117.44	0.917	1.570	
3.45	3.45	7117.45	0.919	1.578	
3.46	3.46	7117.46	0.920	1.586	
3.47	3.47	7117.47	0.922	1.595	
3.48	3.48	7117.48	0.924	1.603	
3.49	3.49	7117.49	0.926	1.612	
3.50	3.50	7117.50	0.927	1.620	
3.51	3.51	7117.51	0.929	1.628	
3.52	3.52	7117.52	0.931	1.637	
				•	

3.53	3.53	7031.53	1.528	3.418	
3.54	3.54	7031.54	1.530	3.432	
3.55	3.55	7031.55	1.532	3.447	
3.56	3.56	7031.56	1.534	3.461	
3.57	3.57	7031.57	1.536	3.475	
3.58	3.58	7031.58	1.538	3.489	
3.59	3.59	7031.59	1.540	3.504	
3.60	3.60	7031.60	1.542	3.518	
3.61	3.61	7031.61	1.544	3.532	
3.62	3.62	7031.62	1.546	3.547	
3.63	3.63	7031.63	1.548	3.561	
3.64	3.64	7031.64	1.550	3.575	
3.65	3.65	7031.65	1.552	3.590	
3.66	3.66	7031.66	1.554	3.604	
3.67	3.67	7031.67	1.556	3.618	
3.68	3.68	7031.68	1.558	3.632	
3.69	3.69	7031.69	1.560	3.647	
3.70	3.70	7031.70	1.561	3.661	
3.71	3.71	7031.71	1.563	3.675	
3.72	3.72	7031.72	1.565	3.690	
3.73	3.73	7031.73	1.567	3.704	
3.74	3.74	7031.74	1.569	3.718	
3.75	3.75	7031.75	1.571	3.733	
3.76	3.76	7031.76	1.573	3.747	
3.77	3.77	7031.77	1.575	3.761	
3.78	3.78	7031.78	1.577	3.775	
3.79	3.79	7031.79	1.579	3.790	
3.80	3.80	7031.80	1.581	3.804	
3.81	3.81	7031.81	1.583	3.818	
3.82	3.82	7031.82	1.585	3.833	
3.83	3.83	7031.83	1.587	3.847	
3.84	3.84	7031.84	1.589	3.861	
3.85	3.85	7031.85	1.591	3.876	
3.86	3.86	7031.86	1.593	3.890	
3.87	3.87	7031.87	1.595	3.904	
3.88	3.88	7031.88	1.597	3.918	
3.89	3.89	7031.89	1.599	3.933	
3.90	3.90	7031.90	1.600	3.947	
3.91	3.91	7031.91	1.602	3.961	
3.92	3.92	7031.92	1.604	3.976	
3.93	3.93	7031.93	1.606	3.990	
3.94	3.94	7031.94	1.608	4.004	
3.95	3.95	7031.95	1.610	4.019	
3.96	3.96	7031.96	1.612	4.033	
3.97	3.97	7031.97	1.614	4.047	
3.98	3.98	7031.98	1.616	4.061	

3.53	3.53	7117.53	0.933	1.645	
3.54	3.54	7117.54	0.934	1.654	
3.54	3.55	7117.54	0.936	1.662	
3.56	3.56	7117.56	0.938	1.670	
3.50	3.50	7117.50	0.940	1.679	
3.58	3.58	7117.58	0.940	1.687	
3.59	3.59	7117.59	0.942	1.696	
3.59 3.60	3.59	7117.59 7117.60	0.945	1.704	
3.61	3.61	7117.61	0.947	1.712	
3.62	3.62	7117.62	0.949	1.712	
3.63	3.63	7117.63	0.950	1.729	
3.64	3.64	7117.64	0.952	1.725	
3.65	3.65	7117.65	0.954	1.746	
3.66	3.66	7117.66	0.956	1.754	
3.67	3.67	7117.67	0.950	1.763	
3.68	3.68	7117.68	0.959	1.703	
3.69	3.69	7117.69	0.955	1.771	
3.00	3.00 3.70	7117.00	0.963	1.788	
3.71	3.71	7117.71	0.965	1.796	
3.71	3.71	7117.72	0.966	1.805	
3.72	3.72	7117.72	0.968	1.803	
3.74	3.73	7117.73	0.970	1.813	
3.74	3.74	7117.74	0.972	1.830	
3.76	3.76	7117.76	0.972	1.838	
3.70	3.70	7117.77	0.975	1.838	
3.78	3.78	7117.78	0.977	1.855	
3.79	3.79	7117.79	0.979	1.864	
3.80	3.80	7117.80	0.980	1.872	
3.81	3.81	7117.81	0.982	1.880	
3.82	3.82	7117.82	0.984	1.889	
3.83	3.83	7117.83	0.986	1.897	
3.84	3.84	7117.84	0.988	1.906	
3.85	3.85	7117.85	0.989	1.914	
3.86	3.86	7117.86	0.991	1.922	
3.87	3.87	7117.87	0.993	1.931	
3.88	3.88	7117.88	0.995	1.939	
3.89	3.89	7117.89	0.996	1.948	
3.90	3.90	7117.90	0.998	1.956	
3.91	3.91	7117.91	1.000	1.964	
3.92	3.92	7117.92	1.002	1.973	
3.93	3.93	7117.93	1.004	1.981	
3.94	3.94	7117.94	1.005	1.990	
3.95	3.95	7117.95	1.007	1.998	
3.96	3.96	7117.96	1.009	2.006	
3.97	3.97	7117.97	1.011	2.015	
3.98	3.98	7117.98	1.012	2.023	
<u> </u>	•				

3.99	3.99	7031.99	1.618	4.076	
4.00	4.00	7032.00	1.620	4.090	
4.01	4.01	7032.01	1.622	4.108	
4.02	4.02	7032.02	1.624	4.126	
4.03	4.03	7032.03	1.626	4.144	
4.04	4.04	7032.04	1.628	4.163	
4.05	4.05	7032.05	1.630	4.181	
4.06	4.06	7032.06	1.632	4.199	
4.07	4.07	7032.07	1.634	4.217	
4.08	4.08	7032.08	1.636	4.235	
4.09	4.09	7032.09	1.638	4.253	
4.10	4.10	7032.10	1.640	4.272	
4.11	4.11	7032.11	1.641	4.290	
4.12	4.12	7032.12	1.643	4.308	
4.13	4.13	7032.13	1.645	4.326	
4.14	4.14	7032.14	1.647	4.344	
4.15	4.15	7032.15	1.649	4.362	
4.16	4.16	7032.16	1.651	4.380	
4.17	4.17	7032.17	1.653	4.399	
4.18	4.18	7032.18	1.655	4.417	
4.19	4.19	7032.19	1.657	4.435	
4.20	4.20	7032.20	1.659	4.453	
4.21	4.21	7032.21	1.661	4.471	
4.22	4.22	7032.22	1.663	4.489	
4.23	4.23	7032.23	1.665	4.507	
4.24	4.24	7032.24	1.667	4.526	
4.25	4.25	7032.25	1.669	4.544	
4.26	4.26	7032.26	1.671	4.562	
4.27	4.27	7032.27	1.673	4.580	
4.28	4.28	7032.28	1.675	4.598	
4.29	4.29	7032.29	1.677	4.616	
4.30	4.30	7032.30	1.679	4.635	
4.31	4.31	7032.31	1.680	4.653	
4.32	4.32	7032.32	1.682	4.671	
4.33	4.33	7032.33	1.684	4.689	
4.34	4.34	7032.34	1.686	4.707	
4.35	4.35	7032.35	1.688	4.725	
4.36	4.36	7032.36	1.690	4.743	
4.37	4.37	7032.37	1.692	4.762	
4.38	4.38	7032.38	1.694	4.780	
4.39	4.39	7032.39	1.696	4.798	
4.40	4.40	7032.40	1.698	4.816	
4.41	4.41	7032.41	1.700	4.834	
4.42	4.42	7032.42	1.702	4.852	
4.43	4.43	7032.43	1.704	4.870	
4.44	4.44	7032.44	1.706	4.889	

3.99	3.99	7117.99	1.014	2.032	
4.00	4.00	7118.00	1.016	2.040	
4.01	4.01	7118.01	1.017	2.051	
4.02	4.02	7118.02	1.018	2.063	
4.03	4.03	7118.03	1.019	2.074	
4.04	4.04	7118.04	1.020	2.085	
4.05	4.05	7118.05	1.021	2.096	
4.06	4.06	7118.06	1.022	2.108	
4.07	4.07	7118.07	1.023	2.119	
4.08	4.08	7118.08	1.024	2.130	
4.09	4.09	7118.09	1.025	2.141	
4.10	4.10	7118.10	1.026	2.153	
4.11	4.11	7118.11	1.027	2.164	
4.12	4.12	7118.12	1.029	2.175	
4.13	4.13	7118.13	1.030	2.186	
4.14	4.14	7118.14	1.031	2.198	
4.15	4.15	7118.15	1.032	2.209	
4.16	4.16	7118.16	1.033	2.220	
4.17	4.17	7118.17	1.034	2.231	
4.18	4.18	7118.18	1.035	2.243	
4.19	4.19	7118.19	1.036	2.254	
4.20	4.20	7118.20	1.037	2.265	
4.21	4.21	7118.21	1.038	2.276	
4.22	4.22	7118.22	1.039	2.288	
4.23	4.23	7118.23	1.041	2.299	
4.24	4.24	7118.24	1.042	2.310	
4.25	4.25	7118.25	1.043	2.321	
4.26	4.26	7118.26	1.044	2.333	
4.27	4.27	7118.27	1.045	2.344	
4.28	4.28	7118.28	1.046	2.355	
4.29	4.29	7118.29	1.047	2.366	
4.30	4.30	7118.30	1.048	2.378	
4.31	4.31	7118.31	1 0 10		
4.22		/110.31	1.049	2.389	
4.32	4.32	7118.31	1.049	2.389 2.400	
4.32	4.32 4.33				
-		7118.32	1.050	2.400	
4.33	4.33	7118.32 7118.33	1.050 1.051	2.400 2.411	
4.33 4.34	4.33 4.34	7118.32 7118.33 7118.34	1.050 1.051 1.053	2.400 2.411 2.423	
4.33 4.34 4.35	4.33 4.34 4.35	7118.32 7118.33 7118.34 7118.35	1.050 1.051 1.053 1.054	2.400 2.411 2.423 2.434	
4.33 4.34 4.35 4.36	4.33 4.34 4.35 4.36	7118.32 7118.33 7118.34 7118.35 7118.36	1.050 1.051 1.053 1.054 1.055	2.400 2.411 2.423 2.434 2.445	
4.33 4.34 4.35 4.36 4.37	4.33 4.34 4.35 4.36 4.37	7118.32 7118.33 7118.34 7118.35 7118.36 7118.37	1.050 1.051 1.053 1.054 1.055 1.056	2.400 2.411 2.423 2.434 2.445 2.456	
4.33 4.34 4.35 4.36 4.37 4.38	4.33 4.34 4.35 4.36 4.37 4.38	7118.32 7118.33 7118.34 7118.35 7118.36 7118.37 7118.38	1.050 1.051 1.053 1.054 1.055 1.056 1.057	2.400 2.411 2.423 2.434 2.445 2.456 2.468	
4.33 4.34 4.35 4.36 4.37 4.38 4.39	4.33 4.34 4.35 4.36 4.37 4.38 4.39	7118.32 7118.33 7118.34 7118.35 7118.36 7118.37 7118.38 7118.39	1.050 1.051 1.053 1.054 1.055 1.056 1.057 1.058	2.400 2.411 2.423 2.434 2.445 2.456 2.468 2.479	
4.33 4.34 4.35 4.36 4.37 4.38 4.39 4.40	4.33 4.34 4.35 4.36 4.37 4.38 4.39 4.40	7118.32 7118.33 7118.34 7118.35 7118.36 7118.37 7118.38 7118.39 7118.40	1.050 1.051 1.053 1.054 1.055 1.056 1.057 1.058 1.059	2.400 2.411 2.423 2.434 2.445 2.456 2.468 2.479 2.490	
4.33 4.34 4.35 4.36 4.37 4.38 4.39 4.40 4.41	4.33 4.34 4.35 4.36 4.37 4.38 4.39 4.40 4.41	7118.32 7118.33 7118.34 7118.35 7118.36 7118.37 7118.38 7118.39 7118.40 7118.41	1.050 1.051 1.053 1.054 1.055 1.056 1.057 1.058 1.059 1.060	2.400 2.411 2.423 2.434 2.445 2.445 2.456 2.468 2.479 2.490 2.501	

4.45	4.45	7032.45	1.708	4.907	
4.46	4.46	7032.46	1.710	4.925	
4.47	4.47	7032.47	1.712	4.943	
4.48	4.48	7032.48	1.714	4.961	
4.49	4.49	7032.49	1.716	4.979	
4.50	4.50	7032.50	1.717	4.998	
4.51	4.51	7032.51	1.719	5.016	
4.52	4.52	7032.52	1.721	5.034	
4.53	4.53	7032.53	1.723	5.052	
4.54	4.54	7032.54	1.725	5.070	
4.55	4.55	7032.55	1.727	5.088	
4.56	4.56	7032.56	1.729	5.106	
4.57	4.57	7032.57	1.731	5.125	
4.58	4.58	7032.58	1.733	5.143	
4.59	4.59	7032.59	1.735	5.161	
4.60	4.60	7032.60	1.737	5.179	
4.61	4.61	7032.61	1.739	5.197	
4.62	4.62	7032.62	1.741	5.215	
4.63	4.63	7032.63	1.743	5.233	
4.64	4.64	7032.64	1.745	5.252	
4.65	4.65	7032.65	1.747	5.270	
4.66	4.66	7032.66	1.749	5.288	
4.67	4.67	7032.67	1.751	5.306	
4.68	4.68	7032.68	1.753	5.324	
4.69	4.69	7032.69	1.755	5.342	
4.70	4.70	7032.70	1.756	5.361	
4.71	4.71	7032.71	1.758	5.379	
4.72	4.72	7032.72	1.760	5.397	
4.73	4.73	7032.73	1.762	5.415	
4.74	4.74	7032.74	1.764	5.433	
4.75	4.75	7032.75	1.766	5.451	
4.76	4.76	7032.76	1.768	5.469	
4.77	4.77	7032.77	1.770	5.488	
4.78	4.78	7032.78	1.772	5.506	
4.79	4.79	7032.79	1.774	5.524	
4.80	4.80	7032.80	1.776	5.542	
4.81	4.81	7032.81	1.778	5.560	
4.82	4.82	7032.82	1.780	5.578	
4.83	4.83	7032.83	1.782	5.596	
4.84	4.84	7032.84	1.784	5.615	
4.85	4.85	7032.85	1.786	5.633	
4.86	4.86	7032.86	1.788	5.651	
4.87	4.87	7032.87	1.790	5.669	
4.88	4.88	7032.88	1.792	5.687	
4.89	4.89	7032.89	1.794	5.705	
4.90	4.90	7032.90	1.795	5.724	

4.45	4.45	7118.45	1.065	2.546	
4.46	4.46	7118.46	1.066	2.558	
4.47	4.47	7118.47	1.067	2.569	
4.48	4.48	7118.48	1.068	2.580	
4.49	4.49	7118.49	1.069	2.591	
4.50	4.50	7118.50	1.070	2.603	
4.51	4.51	7118.51	1.071	2.614	
4.52	4.52	7118.52	1.072	2.625	
4.53	4.53	7118.53	1.073	2.636	
4.54	4.54	7118.54	1.074	2.648	
4.55	4.55	7118.55	1.075	2.659	
4.56	4.56	7118.56	1.077	2.670	
4.57	4.57	7118.57	1.078	2.681	
4.58	4.58	7118.58	1.079	2.693	
4.59	4.59	7118.59	1.080	2.704	
4.60	4.60	7118.60	1.081	2.715	
4.61	4.61	7118.61	1.082	2.726	
4.62	4.62	7118.62	1.083	2.738	
4.63	4.63	7118.63	1.084	2.749	
4.64	4.64	7118.64	1.085	2.760	
4.65	4.65	7118.65	1.086	2.771	
4.66	4.66	7118.66	1.087	2.783	
4.67	4.67	7118.67	1.089	2.794	
4.68	4.68	7118.68	1.090	2.805	
4.69	4.69	7118.69	1.091	2.816	
4.70	4.70	7118.70	1.092	2.828	
4.71	4.71	7118.71	1.093	2.839	
4.72	4.72	7118.72	1.094	2.850	
4.73	4.73	7118.73	1.095	2.861	
4.74	4.74	7118.74	1.096	2.873	
4.75	4.75	7118.75	1.097	2.884	
4.76	4.76	7118.76	1.098	2.895	
4.77	4.77	7118.77	1.099	2.906	
4.78	4.78	7118.78	1.101	2.918	
4.79	4.79	7118.79	1.102	2.929	
4.80	4.80	7118.80	1.103	2.940	
4.81	4.81	7118.81	1.104	2.951	
4.82	4.82	7118.82	1.105	2.963	
4.83	4.83	7118.83	1.106	2.974	
4.84	4.84	7118.84	1.107	2.985	
4.85	4.85	7118.85	1.108	2.996	
4.86	4.86	7118.86	1.109	3.008	
4.87	4.87	7118.87	1.110	3.019	
4.88	4.88	7118.88	1.111	3.030	
4.89	4.89	7118.89	1.113	3.041	
4.90	4.90	7118.90	1.115	3.053	

4.91	4.91	7032.91	1.797	5.742	
4.92	4.92	7032.92	1.799	5.760	
4.93	4.93	7032.93	1.801	5.778	
4.94	4.94	7032.94	1.803	5.796	
4.95	4.95	7032.95	1.805	5.814	
4.96	4.96	7032.96	1.807	5.832	
4.97	4.97	7032.97	1.809	5.851	
4.98	4.98	7032.98	1.811	5.869	
4.99	4.99	7032.99	1.813	5.887	
5.00	5.00	7033.00	1.815	5.905	
5.01	5.01	7033.01	1.817	5.923	
5.02	5.02	7033.02	1.819	5.941	
5.03	5.03	7033.03	1.821	5.959	
5.04	5.04	7033.04	1.823	5.978	
5.05	5.05	7033.05	1.825	5.996	
5.06	5.06	7033.06	1.827	6.014	
5.07	5.07	7033.07	1.829	6.032	
5.08	5.08	7033.08	1.831	6.050	
5.09	5.09	7033.09	1.833	6.068	
5.10	5.10	7033.10	1.834	6.087	
5.11	5.11	7033.11	1.836	6.105	
5.12	5.12	7033.12	1.838	6.123	
5.13	5.13	7033.13	1.840	6.141	
5.14	5.14	7033.14	1.842	6.159	
5.15	5.15	7033.15	1.844	6.177	
5.16	5.16	7033.16	1.846	6.195	
5.17	5.17	7033.17	1.848	6.214	
5.18	5.18	7033.18	1.850	6.232	
5.19	5.19	7033.19	1.852	6.250	
5.20	5.20	7033.20	1.854	6.268	
5.21	5.21	7033.21	1.856	6.286	
5.22	5.22	7033.22	1.858	6.304	
5.23	5.23	7033.23	1.860	6.322	
5.24	5.24	7033.24	1.862	6.341	
5.25	5.25	7033.25	1.864	6.359	
5.26	5.26	7033.26	1.866	6.377	
5.27	5.27	7033.27	1.868	6.395	
5.28	5.28	7033.28	1.870	6.413	
5.29	5.29	7033.29	1.872	6.431	
5.30	5.30	7033.30	1.873	6.450	
5.31	5.31	7033.31	1.875	6.468	
5.32	5.32	7033.32	1.877	6.486	
5.33	5.33	7033.33	1.879	6.504	
5.34	5.34	7033.34	1.881	6.522	
5.35	5.35	7033.35	1.883	6.540	
5.36	5.36	7033.36	1.885	6.558	

1 1			I		
4.91	4.91	7118.91	1.115	3.064	
4.92	4.92	7118.92	1.116	3.075	
4.93	4.93	7118.93	1.117	3.086	
4.94	4.94	7118.94	1.118	3.098	
4.95	4.95	7118.95	1.119	3.109	
4.96	4.96	7118.96	1.120	3.120	
4.97	4.97	7118.97	1.121	3.131	
4.98	4.98	7118.98	1.122	3.143	
4.99	4.99	7118.99	1.123	3.154	
5.00	5.00	7119.00	1.125	3.165	
5.01	5.01	7119.01	1.126	3.176	
5.02	5.02	7119.02	1.127	3.188	
5.03	5.03	7119.03	1.128	3.199	
5.04	5.04	7119.04	1.129	3.210	
5.05	5.05	7119.05	1.130	3.221	
5.06	5.06	7119.06	1.131	3.233	
5.07	5.07	7119.07	1.132	3.244	
5.08	5.08	7119.08	1.133	3.255	
5.09	5.09	7119.09	1.134	3.266	
5.10	5.10	7119.10	1.135	3.278	
5.11	5.11	7119.11	1.136	3.289	
5.12	5.12	7119.12	1.138	3.300	
5.13	5.13	7119.13	1.139	3.311	
5.14	5.14	7119.14	1.140	3.323	
5.15	5.15	7119.15	1.141	3.334	
5.16	5.16	7119.16	1.142	3.345	
5.17	5.17	7119.17	1.143	3.356	
5.18	5.18	7119.18	1.144	3.368	
5.19	5.19	7119.19	1.145	3.379	
5.20	5.20	7119.20	1.146	3.390	
5.21	5.21	7119.21	1.147	3.401	
5.22	5.22	7119.22	1.148	3.413	
5.23	5.23	7119.23	1.150	3.424	
5.24	5.24	7119.24	1.151	3.435	
5.25	5.25	7119.25	1.152	3.446	
5.26	5.26	7119.26	1.153	3.458	
5.27	5.27	7119.27	1.154	3.469	
5.28	5.28	7119.28	1.155	3.480	
5.29	5.29	7119.29	1.156	3.491	
5.30	5.30	7119.30	1.157	3.503	
5.31	5.31	7119.31	1.158	3.514	
5.32	5.32	7119.32	1.159	3.525	
5.33	5.33	7119.33	1.160	3.536	
5.34	5.34	7119.34	1.162	3.548	
5.35	5.35	7119.35	1.163	3.559	
5.36	5.36	7119.36	1.164	3.570	

5.37	5.37	7033.37	1.887	6.577	
5.38	5.38	7033.38	1.889	6.595	
5.39	5.39	7033.39	1.891	6.613	
5.40	5.39 5.40	7033.39 7033.40	1.891	6.631	
5.41	5.41	7033.41	1.895	6.649	
5.41	5.42	7033.41	1.895	6.667	
5.43	5.43	7033.42	1.897	6.685	
5.44	5.44	7033.44	1.901	6.704	
5.44	5.45	7033.44 7033.45	1.901 1.903	6.722	
5.46	5.46	7033.46	1.905	6.740	
5.47	5.47	7033.40	1.907	6.758	
5.48	5.48	7033.48	1.909	6.776	
5.49	5.49	7033.49	1.905	6.794	
5.50	5.50	7033.40 7033.50	1.911	6.813	
5.51	5.50	7033.51	1.912	6.831	
5.52	5.51	7033.52	1.914	6.849	
5.52	5.53	7033.52	1.918	6.867	
5.54	5.53	7033.54	1.918	6.885	
5.55	5.55 5.55	7033.54 7033.55	1.920	6.903	
5.56	5.56	7033.56	1.924	6.921	
5.57	5.57	7033.50	1.924	6.940	
5.58	5.58	7033.58	1.928	6.958	
5.59	5.59	7033.58	1.928	6.976	
5.60	5.60	7033.59 7033.60	1.930 1.932	6.994	
5.61	5.61	7033.61	1.934	7.012	
5.62	5.62	7033.62	1.936	7.012	
5.63	5.63	7033.63	1.938	7.048	
5.64	5.64	7033.64	1.940	7.067	
5.65	5.65	7033.65	1.942	7.085	
5.66	5.66	7033.66	1.944	7.103	
5.67	5.67	7033.67	1.946	7.121	
5.68	5.68	7033.68	1.948	7.139	
5.69	5.69	7033.69	1.950	7.157	
5.70	5.70	7033.70	1.951	7.176	
5.71	5.71	7033.71	1.953	7.194	
5.72	5.72	7033.72	1.955	7.212	
5.73	5.73	7033.73	1.957	7.230	
5.74	5.74	7033.74	1.959	7.248	
5.75	5.75	7033.75	1.961	7.266	
5.76	5.76	7033.76	1.963	7.284	
5.77	5.77	7033.77	1.965	7.303	
5.78	5.78	7033.78	1.967	7.321	
5.79	5.79	7033.79	1.969	7.339	
5.80	5.80	7033.80	1.971	7.357	
5.81	5.81	7033.81	1.973	7.375	
5.01	5.81	7033.81	1.575	7.575	

				г	
5.37	5.37	7119.37	1.165	3.581	
5.38	5.38	7119.38	1.166	3.593	
5.39	5.39	7119.39	1.167	3.604	
5.40	5.40	7119.40	1.168	3.615	
5.41	5.41	7119.41	1.169	3.626	
5.42	5.42	7119.42	1.170	3.638	
5.43	5.43	7119.43	1.171	3.649	
5.44	5.44	7119.44	1.172	3.660	
5.45	5.45	7119.45	1.174	3.671	
5.46	5.46	7119.46	1.175	3.683	
5.47	5.47	7119.47	1.176	3.694	
5.48	5.48	7119.48	1.177	3.705	
5.49	5.49	7119.49	1.178	3.716	
5.50	5.50	7119.50	1.179	3.728	
5.51	5.51	7119.51	1.180	3.739	
5.52	5.52	7119.52	1.181	3.750	
5.53	5.53	7119.53	1.182	3.761	
5.54	5.54	7119.54	1.183	3.773	
5.55	5.55	7119.55	1.184	3.784	
5.56	5.56	7119.56	1.186	3.795	
5.57	5.57	7119.57	1.187	3.806	
5.58	5.58	7119.58	1.188	3.818	
5.59	5.59	7119.59	1.189	3.829	
5.60	5.60	7119.60	1.190	3.840	
5.61	5.61	7119.61	1.191	3.851	
5.62	5.62	7119.62	1.192	3.863	
5.63	5.63	7119.63	1.193	3.874	
5.64	5.64	7119.64	1.194	3.885	
5.65	5.65	7119.65	1.195	3.896	
5.66	5.66	7119.66	1.196	3.908	
5.67	5.67	7119.67	1.198	3.919	
5.68	5.68	7119.68	1.199	3.930	
5.69	5.69	7119.69	1.200	3.941	
5.70		0 . 0 0			
5.70	5.70	7119.70	1.201	3.953	
				3.953	
5.71	5.71	7119.71	1.202	3.953 3.964	
5.71 5.72	5.71 5.72	7119.71 7119.72	1.202 1.203	3.953 3.964 3.975	
5.71 5.72 5.73	5.71 5.72 5.73	7119.71 7119.72 7119.73	1.202 1.203 1.204	3.953 3.964 3.975 3.986	
5.71 5.72 5.73 5.74	5.71 5.72 5.73 5.74	7119.71 7119.72 7119.73 7119.74	1.202 1.203 1.204 1.205	3.953 3.964 3.975 3.986 3.998	
5.71 5.72 5.73 5.74 5.75	5.71 5.72 5.73 5.74 5.75	7119.71 7119.72 7119.73 7119.74 7119.75	1.202 1.203 1.204 1.205 1.206	3.953 3.964 3.975 3.986 3.998 4.009	
5.71 5.72 5.73 5.74 5.75 5.76	5.71 5.72 5.73 5.74 5.75 5.76	7119.71 7119.72 7119.73 7119.74 7119.75 7119.76	1.202 1.203 1.204 1.205 1.206 1.207	3.953 3.964 3.975 3.986 3.998 4.009 4.020	
5.71 5.72 5.73 5.74 5.75 5.76 5.77	5.71 5.72 5.73 5.74 5.75 5.76 5.77	7119.71 7119.72 7119.73 7119.74 7119.75 7119.76 7119.77	1.202 1.203 1.204 1.205 1.206 1.207 1.208	3.953 3.964 3.975 3.986 3.998 4.009 4.020 4.031	
5.71 5.72 5.73 5.74 5.75 5.76 5.77 5.78	5.71 5.72 5.73 5.74 5.75 5.76 5.77 5.78	7119.71 7119.72 7119.73 7119.74 7119.74 7119.75 7119.76 7119.77 7119.78	1.202 1.203 1.204 1.205 1.206 1.207 1.208 1.210	3.953 3.964 3.975 3.986 3.998 4.009 4.020 4.031 4.043	
5.71 5.72 5.73 5.74 5.75 5.76 5.77 5.78 5.79	5.71 5.72 5.73 5.74 5.75 5.76 5.77 5.78 5.79	7119.71 7119.72 7119.73 7119.74 7119.75 7119.76 7119.77 7119.78 7119.79	1.202 1.203 1.204 1.205 1.206 1.207 1.208 1.210 1.211	3.953 3.964 3.975 3.986 3.998 4.009 4.020 4.031 4.043 4.054	
5.71 5.72 5.73 5.74 5.75 5.76 5.77 5.78	5.71 5.72 5.73 5.74 5.75 5.76 5.77 5.78	7119.71 7119.72 7119.73 7119.74 7119.74 7119.75 7119.76 7119.77 7119.78	1.202 1.203 1.204 1.205 1.206 1.207 1.208 1.210	3.953 3.964 3.975 3.986 3.998 4.009 4.020 4.031 4.043	

5.83	5.83	7033.83	1.977	7.411	
5.84	5.84	7033.84	1.979	7.430	
5.85	5.85	7033.85	1.981	7.448	
5.86	5.86	7033.86	1.983	7.466	
5.87	5.87	7033.87	1.985	7.484	
5.88	5.88	7033.88	1.987	7.502	
5.89	5.89	7033.89	1.989	7.520	
5.90	5.90	7033.90	1.990	7.539	
5.91	5.91	7033.91	1.992	7.557	
5.92	5.92	7033.92	1.994	7.575	
5.93	5.93	7033.93	1.996	7.593	
5.94	5.94	7033.94	1.998	7.611	
5.95	5.95	7033.95	2.000	7.629	
5.96	5.96	7033.96	2.002	7.647	
5.97	5.97	7033.97	2.004	7.666	
5.98	5.98	7033.98	2.006	7.684	
5.99	5.99	7033.99	2.008	7.702	
6.00	6.00	7034.00	2.010	7.720	
6.01	6.01	7034.01	2.013	7.743	
6.02	6.02	7034.02	2.015	7.765	
6.03	6.03	7034.03	2.018	7.788	
6.04	6.04	7034.04	2.020	7.811	
6.05	6.05	7034.05	2.023	7.833	
6.06	6.06	7034.06	2.025	7.856	
6.07	6.07	7034.07	2.028	7.879	
6.08	6.08	7034.08	2.030	7.901	
6.09	6.09	7034.09	2.033	7.924	
6.10	6.10	7034.10	2.035	7.947	
6.11	6.11	7034.11	2.038	7.969	
6.12	6.12	7034.12	2.040	7.992	
6.13	6.13	7034.13	2.043	8.014	
6.14	6.14	7034.14	2.045	8.037	
6.15	6.15	7034.15	2.048	8.060	
6.16	6.16	7034.16	2.050	8.082	
6.17	6.17	7034.17	2.053	8.105	
6.18	6.18	7034.18	2.056	8.128	
6.19	6.19	7034.19	2.058	8.150	
6.20	6.20	7034.20	2.061	8.173	
6.21	6.21	7034.21	2.063	8.196	
6.22	6.22	7034.22	2.066	8.218	
6.23	6.23	7034.23	2.068	8.241	
6.24	6.24	7034.24	2.071	8.264	
6.25	6.25	7034.25	2.073	8.286	
6.26	6.26	7034.26	2.076	8.309	
6.27	6.27	7034.27	2.078	8.332	
6.28	6.28	7034.28	2.081	8.354	

5.00	F 02	7440.00	4 245	4 000	
5.83	5.83	7119.83	1.215	4.099	
5.84 5.85	5.84	7119.84 7119.85	1.216	4.110 4.121	
	5.85		1.217		
5.86	5.86	7119.86	1.218	4.133	
5.87	5.87	7119.87	1.219	4.144	
5.88	5.88	7119.88	1.220	4.155	
5.89	5.89	7119.89	1.222	4.166	
5.90	5.90	7119.90	1.223	4.178	
5.91	5.91	7119.91	1.224	4.189	
5.92	5.92	7119.92	1.225	4.200	
5.93	5.93	7119.93	1.226	4.211	
5.94	5.94	7119.94	1.227	4.223	
5.95	5.95	7119.95	1.228	4.234	
5.96	5.96	7119.96	1.229	4.245	
5.97	5.97	7119.97	1.230	4.256	
5.98	5.98	7119.98	1.231	4.268	
5.99	5.99	7119.99	1.232	4.279	
6.00	6.00	7120.00	1.234	4.290	Spillway / NWS
6.01	6.01	7120.01	1.235	4.302	
6.02	6.02	7120.02	1.237	4.315	
6.03	6.03	7120.03	1.239	4.327	
6.04	6.04	7120.04	1.241	4.339	
6.05	6.05	7120.05	1.243	4.352	
6.06	6.06	7120.06	1.245	4.364	
6.07	6.07	7120.07	1.246	4.376	
6.08	6.08	7120.08	1.248	4.389	
6.09	6.09	7120.09	1.250	4.401	
6.10	6.10	7120.10	1.252	4.414	
6.11	6.11	7120.11	1.254	4.426	
6.12	6.12	7120.12	1.256	4.438	
6.13	6.13	7120.13	1.257	4.451	
6.14	6.14	7120.14	1.259	4.463	
6.15	6.15	7120.15	1.261	4.475	
6.16	6.16	7120.16	1.263	4.488	
6.17	6.17	7120.17	1.265	4.500	
6.18	6.18	7120.18	1.267	4.512	
6.19	6.19	7120.19	1.268	4.525	
6.20	6.20	7120.20	1.270	4.537	
6.21	6.21	7120.21	1.272	4.549	
6.22	6.22	7120.22	1.274	4.562	
6.23	6.23	7120.23	1.276	4.574	
6.24	6.24	7120.24	1.278	4.586	
6.25	6.25	7120.25	1.280	4.599	
6.26	6.26	7120.26	1.281	4.611	
6.27	6.27	7120.27	1.283	4.623	
6.28	6.28	7120.28	1.285	4.636	
					1

6.29	6.29	7034.29	2.083	8.377	
6.30	6.30	7034.30	2.086	8.400	
6.31	6.31	7034.31	2.088	8.422	
6.32	6.32	7034.32	2.091	8.445	
6.33	6.33	7034.33	2.093	8.467	
6.34	6.34	7034.34	2.096	8.490	
6.35	6.35	7034.35	2.099	8.513	
6.36	6.36	7034.36	2.101	8.535	
6.37	6.37	7034.37	2.104	8.558	
6.38	6.38	7034.38	2.106	8.581	
6.39	6.39	7034.39	2.109	8.603	
6.40	6.40	7034.40	2.111	8.626	
6.41	6.41	7034.41	2.114	8.649	
6.42	6.42	7034.42	2.116	8.671	
6.43	6.43	7034.43	2.119	8.694	
6.44	6.44	7034.44	2.121	8.717	
6.45	6.45	7034.45	2.124	8.739	
6.46	6.46	7034.46	2.126	8.762	
6.47	6.47	7034.47	2.129	8.785	
6.48	6.48	7034.48	2.131	8.807	
6.49	6.49	7034.49	2.134	8.830	
6.50	6.50	7034.50	2.137	8.853	
6.51	6.51	7034.51	2.139	8.875	
6.52	6.52	7034.52	2.142	8.898	
6.53	6.53	7034.53	2.144	8.920	
6.54	6.54	7034.54	2.147	8.943	
6.55	6.55	7034.55	2.149	8.966	
6.56	6.56	7034.56	2.152	8.988	
6.57	6.57	7034.57	2.154	9.011	
6.58	6.58	7034.58	2.157	9.034	
6.59	6.59	7034.59	2.159	9.056	
6.60	6.60	7034.60	2.162	9.079	
6.61	6.61	7034.61	2.164	9.102	
6.62	6.62	7034.62	2.167	9.124	
6.63	6.63	7034.63	2.169	9.147	
6.64	6.64	7034.64	2.172	9.170	
6.65	6.65	7034.65	2.174	9.192	
6.66	6.66	7034.66	2.177	9.215	
6.67	6.67	7034.67	2.180	9.238	
6.68	6.68	7034.68	2.182	9.260	
6.69	6.69	7034.69	2.185	9.283	
6.70	6.70	7034.70	2.187	9.306	
6.71	6.71	7034.71	2.190	9.328	
6.72	6.72	7034.72	2.192	9.351	
6.73	6.73	7034.73	2.195	9.373	
6.74	6.74	7034.74	2.197	9.396	

6.29	6.29	7120.29	1.287	4.648	
6.30	6.30	7120.30	1.289	4.661	
6.31	6.31	7120.31	1.291	4.673	
6.32	6.32	7120.32	1.292	4.685	
6.33	6.33	7120.33	1.294	4.698	
6.34	6.34	7120.34	1.296	4.710	
6.35	6.35	7120.35	1.298	4.722	
6.36	6.36	7120.36	1.300	4.735	
6.37	6.37	7120.37	1.302	4.747	
6.38	6.38	7120.38	1.303	4.759	
6.39	6.39	7120.39	1.305	4.772	
6.40	6.40	7120.40	1.307	4.784	
6.41	6.41	7120.41	1.309	4.796	
6.42	6.42	7120.42	1.311	4.809	
6.43	6.43	7120.43	1.313	4.821	
6.44	6.44	7120.44	1.314	4.833	
6.45	6.45	7120.45	1.316	4.846	
6.46	6.46	7120.46	1.318	4.858	
6.47	6.47	7120.47	1.320	4.870	
6.48	6.48	7120.48	1.322	4.883	
6.49	6.49	7120.49	1.324	4.895	
6.50	6.50	7120.50	1.326	4.907	
6.51	6.51	7120.51	1.327	4.920	
6.52	6.52	7120.52	1.329	4.932	
6.53	6.53	7120.53	1.331	4.945	
6.54	6.54	7120.54	1.333	4.957	
6.55	6.55	7120.55	1.335	4.969	
6.56	6.56	7120.56	1.337	4.982	
6.57	6.57	7120.57	1.338	4.994	
6.58	6.58	7120.58	1.340	5.006	
6.59	6.59	7120.59	1.342	5.019	
6.60	6.60	7120.60	1.344	5.031	
6.61	6.61	7120.61	1.346	5.043	
6.62	6.62	7120.62	1.348	5.056	
6.63	6.63	7120.63	1.349	5.068	
6.64	6.64	7120.64	1.351	5.080	
6.65	6.65	7120.65	1.353	5.093	
6.66	6.66	7120.66	1.355	5.105	
6.67	6.67	7120.67	1.357	5.117	
6.68	6.68	7120.68	1.359	5.130	
6.69	6.69	7120.69	1.360	5.142	
6.70	6.70	7120.70	1.362	5.154	
6.71	6.71	7120.71	1.364	5.167	
6.72	6.72	7120.72	1.366	5.179	
6.73	6.73	7120.73	1.368	5.192	
6.74	6.74	7120.74	1.370	5.204	

6.75	6.75	7034.75	2.200	9.419	
6.76	6.76	7034.76	2.202	9.441	
6.77	6.77	7034.77	2.205	9.464	
6.78	6.78	7034.78	2.207	9.487	
6.79	6.79	7034.79	2.210	9.509	
6.80	6.80	7034.80	2.212	9.532	
6.81	6.81	7034.81	2.215	9.555	
6.82	6.82	7034.82	2.217	9.577	
6.83	6.83	7034.83	2.220	9.600	
6.84	6.84	7034.84	2.223	9.623	
6.85	6.85	7034.85	2.225	9.645	
6.86	6.86	7034.86	2.228	9.668	
6.87	6.87	7034.87	2.230	9.691	
6.88	6.88	7034.88	2.233	9.713	
6.89	6.89	7034.89	2.235	9.736	
6.90	6.90	7034.90	2.238	9.759	
6.91	6.91	7034.91	2.240	9.781	
6.92	6.92	7034.92	2.243	9.804	
6.93	6.93	7034.93	2.245	9.826	
6.94	6.94	7034.94	2.248	9.849	
6.95	6.95	7034.95	2.250	9.872	
6.96	6.96	7034.96	2.253	9.894	
6.97	6.97	7034.97	2.255	9.917	
6.98	6.98	7034.98	2.258	9.940	
6.99	6.99	7034.99	2.260	9.962	
7.00	7.00	7035.00	2.263	9.985	
7.01	7.01	7035.01	2.266	10.008	
7.02	7.02	7035.02	2.268	10.030	
7.03	7.03	7035.03	2.271	10.053	
7.04	7.04	7035.04	2.273	10.076	
7.05	7.05	7035.05	2.276	10.098	
7.06	7.06	7035.06	2.278	10.121	
7.07	7.07	7035.07	2.281	10.144	
7.08	7.08	7035.08	2.283	10.166	
7.09	7.09	7035.09	2.286	10.189	
7.10	7.10	7035.10	2.288	10.212	
7.11	7.11	7035.11	2.291	10.234	
7.12	7.12	7035.12	2.293	10.257	
7.13	7.13	7035.13	2.296	10.279	
7.14	7.14	7035.14	2.298	10.302	
7.15	7.15	7035.15	2.301	10.325	
7.16	7.16	7035.16	2.303	10.347	
7.17	7.17	7035.17	2.306	10.370	
7.18	7.18	7035.18	2.309	10.393	
7.19	7.19	7035.19	2.311	10.415	
7.20	7.20	7035.20	2.314	10.438	

6.75	6.75	7120.75	1.372	5.216	
6.76	6.76	7120.76	1.373	5.229	
6.77	6.77	7120.77	1.375	5.241	
6.78	6.78	7120.78	1.377	5.253	
6.79	6.79	7120.79	1.379	5.266	
6.80	6.80	7120.80	1.381	5.278	
6.81	6.81	7120.81	1.383	5.290	
6.82	6.82	7120.82	1.384	5.303	
6.83	6.83	7120.83	1.386	5.315	
6.84	6.84	7120.84	1.388	5.327	
6.85	6.85	7120.85	1.390	5.340	
6.86	6.86	7120.86	1.392	5.352	
6.87	6.87	7120.87	1.394	5.364	
6.88	6.88	7120.88	1.395	5.377	
6.89	6.89	7120.89	1.397	5.389	
6.90	6.90	7120.90	1.399	5.401	
6.91	6.91	7120.91	1.401	5.414	
6.92	6.92	7120.92	1.403	5.426	
6.93	6.93	7120.93	1.405	5.439	
6.94	6.94	7120.94	1.406	5.451	
6.95	6.95	7120.95	1.408	5.463	
6.96	6.96	7120.96	1.410	5.476	
6.97	6.97	7120.97	1.412	5.488	
6.98	6.98	7120.98	1.414	5.500	
6.99	6.99	7120.99	1.416	5.513	
7.00	7.00	7121.00	1.418	5.525	
7.01	7.01	7121.01	1.419	5.537	
7.02	7.02	7121.02	1.421	5.550	
7.02	7.02	7121.02	1.423	5.562	
7.04	7.04	7121.03	1.425	5.574	
7.05	7.05	7121.05	1.427	5.587	
7.06	7.06	7121.06	1.429	5.599	
7.07	7.07	7121.07	1.430	5.611	
7.08	7.08	7121.08	1.432	5.624	
7.09	7.09	7121.09	1.434	5.636	
7.10	7.10	7121.10	1.436	5.648	
7.11	7.11	7121.11	1.438	5.661	
7.12	7.12	7121.11	1.440	5.673	
7.12	7.12	7121.12	1.441	5.686	
7.13	7.13	7121.13	1.443	5.698	
7.15	7.15	7121.15	1.445	5.710	
7.16	7.16	7121.16	1.447	5.723	
7.17	7.10	7121.10	1.449	5.735	
7.18	7.18	7121.17	1.451	5.747	
7.10	7.10	7121.10	1.452	5.760	
7.20	7.20	7121.15	1.454	5.772	
		·•			

7.21	7.21	7035.21	2.316	10.461	
7.22	7.22	7035.22	2.319	10.483	
7.23	7.23	7035.23	2.321	10.506	
7.24	7.24	7035.24	2.324	10.529	
7.25	7.25	7035.25	2.326	10.551	
7.26	7.26	7035.26	2.329	10.574	
7.27	7.27	7035.27	2.331	10.597	
7.28	7.28	7035.28	2.334	10.619	
7.29	7.29	7035.29	2.336	10.642	
7.30	7.30	7035.30	2.339	10.665	
7.31	7.31	7035.31	2.341	10.687	
7.32	7.32	7035.32	2.344	10.710	
7.33	7.33	7035.33	2.346	10.732	
7.34	7.34	7035.34	2.349	10.755	
7.35	7.35	7035.35	2.352	10.778	
7.36	7.36	7035.36	2.354	10.800	
7.37	7.37	7035.37	2.357	10.823	
7.38	7.38	7035.38	2.359	10.846	
7.39	7.39	7035.39	2.362	10.868	
7.40	7.40	7035.40	2.364	10.891	
7.41	7.41	7035.41	2.367	10.914	
7.42	7.41	7035.41	2.369	10.936	
7.43	7.42	7035.42	2.305	10.959	
7.44	7.44	7035.44	2.372	10.982	
7.45	7.45	7035.45	2.377	11.004	
7.46	7.46	7035.46	2.379	11.027	
7.47	7.47	7035.47	2.382	11.050	
7.48	7.48	7035.48	2.384	11.072	
7.49	7.49	7035.49	2.387	11.095	
7.50	7.50	7035.50	2.390	11.118	
7.51	7.51	7035.51	2.392	11.140	
7.52	7.52	7035.52	2.395	11.163	
7.53	7.53	7035.53	2.397	11.185	
7.54	7.54	7035.54	2.400	11.208	
7.55	7.55	7035.55	2.402	11.231	
7.56	7.56	7035.56	2.405	11.253	
7.57	7.57	7035.57	2.407	11.276	
7.58	7.58	7035.58	2.410	11.299	
7.59	7.59	7035.59	2.412	11.321	
7.60	7.60	7035.60	2.415	11.344	
7.61	7.61	7035.61	2.417	11.367	
7.62	7.62	7035.62	2.420	11.389	
7.63	7.63	7035.63	2.422	11.412	
7.64	7.64	7035.64	2.425	11.435	
7.65	7.65	7035.65	2.427	11.457	
7.66	7.66	7035.66	2.430	11.480	

7.21	7.21	7121.21	1.456	5.784	
7.22	7.21	7121.22	1.458	5.797	
7.23	7.23	7121.23	1.460	5.809	
7.24	7.24	7121.24	1.462	5.821	
7.25	7.25	7121.25	1.464	5.834	
7.26	7.26	7121.26	1.465	5.846	
7.27	7.27	7121.27	1.467	5.858	
7.28	7.28	7121.28	1.469	5.871	
7.29	7.29	7121.29	1.471	5.883	
7.30	7.30	7121.30	1.473	5.895	
7.31	7.31	7121.31	1.475	5.908	
7.32	7.32	7121.32	1.476	5.920	
7.33	7.33	7121.33	1.478	5.933	
7.34	7.34	7121.34	1.480	5.945	
7.35	7.35	7121.35	1.482	5.957	
7.36	7.36	7121.36	1.484	5.970	
7.37	7.37	7121.37	1.486	5.982	
7.38	7.38	7121.38	1.487	5.994	
7.39	7.39	7121.39	1.489	6.007	
7.40	7.40	7121.40	1.491	6.019	
7.41	7.41	7121.41	1.493	6.031	
7.42	7.42	7121.42	1.495	6.044	
7.43	7.43	7121.43	1.497	6.056	
7.44	7.44	7121.44	1.498	6.068	
7.45	7.45	7121.45	1.500	6.081	
7.46	7.46	7121.46	1.502	6.093	
7.47	7.47	7121.47	1.504	6.105	
7.48	7.48	7121.48	1.506	6.118	
7.49	7.49	7121.49	1.508	6.130	
7.50	7.50	7121.50	1.510	6.142	
7.51	7.51	7121.51	1.511	6.155	
7.52	7.52	7121.52	1.513	6.167	
7.53	7.53	7121.53	1.515	6.180	
7.54	7.54	7121.54	1.517	6.192	
7.55	7.55	7121.55	1.519	6.204	
7.56	7.56	7121.56	1.521	6.217	
7.57	7.57	7121.57	1.522	6.229	
7.58	7.58	7121.58	1.524	6.241	
7.59	7.59	7121.59	1.526	6.254	
7.60	7.60	7121.60	1.528	6.266	
7.61	7.61	7121.61	1.530	6.278	
7.62	7.62	7121.62	1.532	6.291	
7.63	7.63	7121.63	1.533	6.303	
7.64	7.64	7121.64	1.535	6.315	
7.65	7.65	7121.65	1.537	6.328	
7.66	7.66	7121.66	1.539	6.340	

7.67	7.67	7035.67	2.433	11.503	
7.68	7.68	7035.68	2.435	11.503	
7.69	7.69	7035.69	2.433	11.525	
7.89	7.09	7035.09 7035.70	2.438 2.440	11.548 11.571	
7.71	7.71	7035.70	2.443	11.571	
7.72	7.72		2.443		
		7035.72		11.616	
7.73	7.73	7035.73	2.448	11.638	
7.74	7.74	7035.74	2.450	11.661	
7.75	7.75	7035.75	2.453	11.684	
7.76	7.76	7035.76	2.455	11.706	
7.77	7.77	7035.77	2.458	11.729	
7.78	7.78	7035.78	2.460	11.752	
7.79	7.79	7035.79	2.463	11.774	
7.80	7.80	7035.80	2.465	11.797	
7.81	7.81	7035.81	2.468	11.820	
7.82	7.82	7035.82	2.470	11.842	
7.83	7.83	7035.83	2.473	11.865	
7.84	7.84	7035.84	2.476	11.888	
7.85	7.85	7035.85	2.478	11.910	
7.86	7.86	7035.86	2.481	11.933	
7.87	7.87	7035.87	2.483	11.956	
7.88	7.88	7035.88	2.486	11.978	
7.89	7.89	7035.89	2.488	12.001	
7.90	7.90	7035.90	2.491	12.024	
7.91	7.91	7035.91	2.493	12.046	
7.92	7.92	7035.92	2.496	12.069	
7.93	7.93	7035.93	2.498	12.091	
7.94	7.94	7035.94	2.501	12.114	
7.95	7.95	7035.95	2.503	12.137	
7.96	7.96	7035.96	2.506	12.159	
7.97	7.97	7035.97	2.508	12.182	
7.98	7.98	7035.98	2.511	12.205	
7.99	7.99	7035.99	2.513	12.227	
8.00	8.00	7036.00	2.516	12.250	Spillway Crest / NWS
8.01	8.01	7036.01	2.522	12.276	
8.02	8.02	7036.02	2.527	12.301	
8.03	8.03	7036.03	2.533	12.327	
8.04	8.04	7036.04	2.538	12.353	
8.05	8.05	7036.05	2.544	12.379	
8.06	8.06	7036.06	2.549	12.404	
8.07	8.07	7036.07	2.555	12.430	
8.08	8.08	7036.08	2.560	12.456	
8.09	8.09	7036.09	2.566	12.481	
8.10	8.10	7036.10	2.571	12.507	
8.11	8.11	7036.11	2.577	12.533	
8.12	8.12	7036.12	2.582	12.555	
0.12	0.12	/030.12	2.302	12.330	

			1		
7.67	7.67	7121.67	1.541	6.352	
7.68	7.68	7121.68	1.543	6.365	
7.69	7.69	7121.69	1.544	6.377	
7.70	7.70	7121.70	1.546	6.389	
7.71	7.71	7121.71	1.548	6.402	
7.72	7.72	7121.72	1.550	6.414	
7.73	7.73	7121.73	1.552	6.427	
7.74	7.74	7121.74	1.554	6.439	
7.75	7.75	7121.75	1.556	6.451	
7.76	7.76	7121.76	1.557	6.464	
7.77	7.77	7121.77	1.559	6.476	
7.78	7.78	7121.78	1.561	6.488	
7.79	7.79	7121.79	1.563	6.501	
7.80	7.80	7121.80	1.565	6.513	
7.81	7.81	7121.81	1.567	6.525	
7.82	7.82	7121.82	1.568	6.538	
7.83	7.83	7121.83	1.570	6.550	
7.84	7.84	7121.84	1.572	6.562	
7.85	7.85	7121.85	1.574	6.575	
7.86	7.86	7121.86	1.576	6.587	
7.87	7.87	7121.87	1.578	6.599	
7.88	7.88	7121.88	1.579	6.612	
7.89	7.89	7121.89	1.581	6.624	
7.90	7.90	7121.90	1.583	6.636	
7.91	7.91	7121.91	1.585	6.649	
7.92	7.92	7121.92	1.587	6.661	
7.93	7.93	7121.93	1.589	6.674	
7.94	7.94	7121.94	1.590	6.686	
7.95	7.95	7121.95	1.592	6.698	
7.96	7.96	7121.96	1.594	6.711	
7.97	7.97	7121.97	1.596	6.723	
7.98	7.98	7121.98	1.598	6.735	
7.99	7.99	7121.99	1.600	6.748	
8.00	8.00	7122.00	1.602	6.760	
8.01	8.01	7122.01	1.606	6.776	
8.02	8.02	7122.02	1.611	6.792	
8.03	8.03	7122.03	1.616	6.808	
8.04	8.04	7122.04	1.620	6.824	
8.05	8.05	7122.05	1.625	6.840	
8.06	8.06	7122.06	1.630	6.856	
8.07	8.07	7122.07	1.635	6.872	
8.08	8.08	7122.08	1.639	6.888	
8.09	8.09	7122.09	1.644	6.904	
8.10	8.10	7122.10	1.649	6.920	
8.11				1	
	8.11	7122.11	1.654	6.936	
8.12	8.11 8.12	7122.11 7122.12	1.654 1.658	6.936 6.952	

8.13	8.13	7036.13	2.588	12.584	
8.14	8.14	7036.14	2.593	12.610	
8.15	8.15	7036.15	2.599	12.636	
8.16	8.16	7036.16	2.604	12.661	
8.10	8.10	7036.17	2.610	12.687	
8.18	8.18	7036.18	2.615	12.713	
8.19	8.19	7036.19	2.620	12.738	
8.19	8.19	7036.20	2.626 2.626	12.758 12.764	
8.21	8.21	7036.21	2.631	12.790	
8.22	8.22	7036.22	2.637	12.815	
8.23	8.23	7036.22	2.642	12.815	
8.23	8.23	7036.23	2.648	12.841	
8.24	8.24 8.25	7030.24 7036.25	2.048 2.653	12.807 12.893	
8.26	8.26	7036.26	2.659	12.918	
8.20	8.20			12.918	
8.27	8.27	7036.27 7036.28	2.664 2.670	12.944	
8.28	8.28	7036.28	2.670	12.970	
8.30	8.30	7036.29 7036.30	2.675 2.681	12.995 13.021	
8.31	8.31	7036.31	2.686	13.047	
8.32	8.32	7036.32	2.692	13.072	
8.33	8.33	7036.33	2.697	13.098	
8.34 8.35	8.34 8.35	7036.34 7036.35	2.703 2.708	13.124 13.150	
8.36	8.36	7036.36	2.714	13.175	
8.37	8.37	7036.37	2.719	13.201	
8.38	8.38	7036.38	2.725	13.227	
8.39	8.39	7036.39	2.730	13.252	
8.40	8.40	7036.40	2.736	13.278	
8.41	8.41	7036.41	2.741	13.304	
8.42	8.42	7036.42	2.747	13.329	
8.43	8.43	7036.43	2.752	13.355	
8.44	8.44	7036.44	2.757	13.381	
8.45	8.45	7036.45	2.763	13.407	
8.46	8.46	7036.46	2.768	13.432	
8.47	8.47	7036.47	2.774	13.458	
8.48	8.48	7036.48	2.779	13.484	
8.49	8.49	7036.49	2.785	13.509	
8.50	8.50	7036.50	2.790	13.535	
8.51	8.51	7036.51	2.796	13.561	
8.52	8.52	7036.52	2.801	13.586	
8.53	8.53	7036.53	2.807	13.612	
8.54	8.54	7036.54	2.812	13.638	
8.55	8.55	7036.55	2.818	13.664	
8.56	8.56	7036.56	2.823	13.689	
8.57	8.57	7036.57	2.829	13.715	
8.58	8.58	7036.58	2.834	13.741	

8.13	8.13	7122.13	1.663	6.968	
8.14	8.14	7122.14	1.668	6.984	
8.15	8.15	7122.15	1.672	7.000	
8.16	8.16	7122.16	1.677	7.016	
8.17	8.17	7122.17	1.682	7.032	
8.18	8.18	7122.18	1.687	7.048	
8.19	8.19	7122.19	1.691	7.064	
8.20	8.20	7122.20	1.696	7.080	
8.21	8.21	7122.21	1.701	7.096	
8.22	8.22	7122.22	1.706	7.112	
8.23	8.23	7122.23	1.710	7.128	
8.24	8.24	7122.24	1.715	7.144	
8.25	8.25	7122.25	1.720	7.160	
8.26	8.26	7122.26	1.724	7.176	
8.27	8.27	7122.27	1.729	7.192	
8.28	8.28	7122.28	1.734	7.208	
8.29	8.29	7122.29	1.739	7.224	
8.30	8.30	7122.30	1.743	7.240	
8.31	8.31	7122.31	1.748	7.256	
8.32	8.32	7122.32	1.753	7.272	
8.33	8.33	7122.33	1.758	7.288	
8.34	8.34	7122.34	1.762	7.304	
8.35	8.35	7122.35	1.767	7.320	
8.36	8.36	7122.36	1.772	7.336	
8.37	8.37	7122.37	1.777	7.352	
8.38	8.38	7122.38	1.781	7.368	
8.39	8.39	7122.39	1.786	7.384	
8.40	8.40	7122.40	1.791	7.400	
8.41	8.41	7122.41	1.795	7.416	
8.42	8.42	7122.42	1.800	7.432	
8.43	8.43	7122.43	1.805	7.448	
8.44	8.44	7122.44	1.810	7.464	
8.45	8.45	7122.45	1.814	7.480	
8.46	8.46	7122.46	1.819	7.496	
8.47	8.47	7122.47	1.824	7.512	
8.48	8.48	7122.48	1.829	7.528	
8.49	8.49	7122.49	1.833	7.544	
8.50	8.50	7122.50	1.838	7.560	
8.51	8.51	7122.51	1.843	7.576	
8.52	8.52	7122.52	1.847	7.592	
8.53	8.53	7122.53	1.852	7.608	
8.54	8.54	7122.54	1.857	7.624	
8.55	8.55	7122.55	1.862	7.640	
8.56	8.56	7122.56	1.866	7.656	
8.57	8.57	7122.57	1.871	7.672	
8.58	8.58	7122.58	1.876	7.688	
		•	•	•	-

8.59	8.59	7036.59	2.840	13.766	
8.60	8.60	7036.60	2.845	13.792	
8.61	8.61	7036.61	2.851	13.818	
8.62	8.62	7036.62	2.856	13.843	
8.63	8.63	7036.63	2.862	13.869	
8.64	8.64	7036.64	2.867	13.895	
8.65	8.65	7036.65	2.873	13.921	
8.66	8.66	7036.66	2.878	13.946	
8.67	8.67	7036.67	2.884	13.972	
8.68	8.68	7036.68	2.889	13.998	
8.69	8.69	7036.69	2.894	14.023	
8.70	8.70	7036.70	2.900	14.049	
8.71	8.71	7036.71	2.905	14.075	
8.72	8.72	7036.72	2.911	14.100	
8.73	8.73	7036.73	2.916	14.126	
8.74	8.74	7036.74	2.922	14.152	
8.75	8.75	7036.75	2.927	14.178	
8.76	8.76	7036.76	2.933	14.203	
8.77	8.77	7036.77	2.938	14.229	
8.78	8.78	7036.78	2.944	14.255	
8.79	8.79	7036.79	2.949	14.280	
8.80	8.80	7036.80	2.955	14.306	
8.81	8.81	7036.81	2.960	14.332	
8.82	8.82	7036.82	2.966	14.357	
8.83	8.83	7036.83	2.971	14.383	
8.84	8.84	7036.84	2.977	14.409	
8.85	8.85	7036.85	2.982	14.435	
8.86	8.86	7036.86	2.988	14.460	
8.87	8.87	7036.87	2.993	14.486	
8.88	8.88	7036.88	2.999	14.512	
8.89	8.89	7036.89	3.004	14.537	
8.90	8.90	7036.90	3.010	14.563	
8.91	8.91	7036.91	3.015	14.589	
8.92	8.92	7036.92	3.021	14.614	
8.93	8.93	7036.93	3.026	14.640	
8.94	8.94	7036.94	3.031	14.666	
8.95	8.95	7036.95	3.037	14.692	
8.96	8.96	7036.96	3.042	14.717	
8.97	8.97	7036.97	3.048	14.743	
8.98	8.98	7036.98	3.053	14.769	
8.99	8.99	7036.99	3.059	14.794	
9.00	9.00	7037.00	3.064	14.820	
9.01	9.01	7037.01	3.070	14.846	
9.02	9.02	7037.02	3.075	14.871	
9.03	9.03	7037.03	3.081	14.897	
9.04	9.04	7037.04	3.086	14.923	

			_		
8.59	8.59	7122.59	1.881	7.704	
8.60	8.60	7122.60	1.885	7.720	
8.61	8.61	7122.61	1.890	7.736	
8.62	8.62	7122.62	1.895	7.752	
8.63	8.63	7122.63	1.899	7.768	
8.64	8.64	7122.64	1.904	7.784	
8.65	8.65	7122.65	1.909	7.800	
8.66	8.66	7122.66	1.914	7.816	
8.67	8.67	7122.67	1.918	7.832	
8.68	8.68	7122.68	1.923	7.848	
8.69	8.69	7122.69	1.928	7.864	
8.70	8.70	7122.70	1.933	7.880	
8.71	8.71	7122.71	1.937	7.896	
8.72	8.72	7122.72	1.942	7.912	
8.73	8.73	7122.73	1.947	7.928	
8.74	8.74	7122.74	1.952	7.944	
8.75	8.75	7122.75	1.956	7.960	
8.76	8.76	7122.76	1.961	7.976	
8.77	8.77	7122.77	1.966	7.992	
8.78	8.78	7122.78	1.970	8.008	
8.79	8.79	7122.79	1.975	8.024	
8.80	8.80	7122.80	1.980	8.040	
8.81	8.81	7122.81	1.985	8.056	
8.82	8.82	7122.82	1.989	8.072	
8.83	8.83	7122.83	1.994	8.088	
8.84	8.84	7122.84	1.999	8.104	
8.85	8.85	7122.85	2.004	8.120	
8.86	8.86	7122.86	2.008	8.136	
8.87	8.87	7122.87	2.013	8.152	
8.88	8.88	7122.88	2.018	8.168	
8.89	8.89	7122.89	2.022	8.184	
8.90	8.90	7122.90	2.027	8.200	
8.91	8.91	7122.91	2.032	8.216	
8.92	8.92	7122.92	2.037	8.232	
8.93	8.93	7122.93	2.041	8.248	
8.94	8.94	7122.94	2.046	8.264	
8.95	8.95	7122.94	2.040	8.280	
8.96	8.96	7122.96	2.056	8.296	
8.97	8.97	7122.90	2.050	8.312	
8.98	8.98	7122.97	2.065	8.328	
8.99	8.99	7122.90	2.005	8.344	
9.00	9.00	7122.00	2.075	8.360	
9.01	9.01	7123.01	2.079	8.376	
9.02	9.02	7123.01	2.075	8.392	
9.02	9.03	7123.02	2.084	8.408	
9.04	9.04	7123.03	2.003	8.424	
5.04	5.04	,125.04	2.000	0.127	1

9.05	9.05	7037.05	3.092	14.949	
9.06	9.06	7037.06	3.097	14.974	
9.07	9.07	7037.07	3.103	15.000	
9.08	9.08	7037.08	3.108	15.026	
9.09	9.09	7037.09	3.114	15.051	
9.10	9.10	7037.10	3.119	15.077	
9.11	9.11	7037.11	3.125	15.103	
9.12	9.12	7037.12	3.130	15.128	
9.13	9.13	7037.13	3.136	15.154	
9.14	9.14	7037.14	3.141	15.180	
9.15	9.15	7037.15	3.147	15.206	
9.16	9.16	7037.16	3.152	15.231	
9.17	9.17	7037.17	3.158	15.257	
9.18	9.18	7037.18	3.163	15.283	
9.19	9.19	7037.19	3.168	15.308	
9.20	9.20	7037.20	3.174	15.334	
9.21	9.21	7037.21	3.179	15.360	
9.22	9.22	7037.22	3.185	15.385	
9.23	9.23	7037.23	3.190	15.411	
9.24	9.24	7037.24	3.196	15.437	
9.25	9.25	7037.25	3.201	15.463	
9.26	9.26	7037.26	3.207	15.488	
9.27	9.27	7037.27	3.212	15.514	
9.28	9.28	7037.28	3.218	15.540	
9.29	9.29	7037.29	3.223	15.565	
9.30	9.30	7037.30	3.229	15.591	
9.31	9.31	7037.31	3.234	15.617	
9.32	9.32	7037.32	3.240	15.642	
9.33	9.33	7037.33	3.245	15.668	
9.34	9.34	7037.34	3.251	15.694	
9.35	9.35	7037.35	3.256	15.720	
9.36	9.36	7037.36	3.262	15.745	
9.37	9.37	7037.37	3.267	15.771	
9.38	9.38	7037.38	3.273	15.797	
9.39	9.39	7037.39	3.278	15.822	
9.40	9.40	7037.40	3.284	15.848	
9.41	9.41	7037.41	3.289	15.874	
9.42	9.42	7037.42	3.295	15.899	
9.43	9.43	7037.43	3.300	15.925	
9.44	9.44	7037.44	3.305	15.951	
9.45	9.45	7037.45	3.311	15.977	
9.46	9.46	7037.46	3.316	16.002	
9.47	9.47	7037.47	3.322	16.028	
9.48	9.48	7037.48	3.327	16.054	
9.49	9.49	7037.49	3.333	16.079	
9.50	9.50	7037.50	3.338	16.105	

9.05	9.05	7123.05	2.098	8.440	
9.06	9.06	7123.06	2.103	8.456	
9.07	9.07	7123.07	2.108	8.472	
9.08	9.08	7123.08	2.112	8.488	
9.09	9.09	7123.09	2.117	8.504	
9.10	9.10	7123.10	2.122	8.520	
9.11	9.11	7123.11	2.127	8.536	
9.12	9.12	7123.12	2.131	8.552	
9.13	9.13	7123.13	2.136	8.568	
9.14	9.14	7123.14	2.141	8.584	
9.15	9.15	7123.15	2.145	8.600	
9.16	9.16	7123.16	2.150	8.616	
9.17	9.17	7123.17	2.155	8.632	
9.18	9.18	7123.18	2.160	8.648	
9.19	9.19	7123.19	2.164	8.664	
9.20	9.20	7123.20	2.169	8.680	
9.21	9.21	7123.21	2.174	8.696	
9.22	9.22	7123.22	2.179	8.712	
9.23	9.23	7123.23	2.183	8.728	
9.24	9.24	7123.24	2.188	8.744	
9.25	9.25	7123.25	2.193	8.760	
9.26	9.26	7123.26	2.197	8.776	
9.27	9.27	7123.27	2.202	8.792	
9.28	9.28	7123.28	2.207	8.808	
9.29	9.29	7123.29	2.212	8.824	
9.30	9.30	7123.30	2.216	8.840	
9.31	9.31	7123.31	2.221	8.856	
9.32	9.32	7123.32	2.226	8.872	
9.33	9.33	7123.33	2.231	8.888	
9.34	9.34	7123.34	2.235	8.904	
9.35	9.35	7123.35	2.240	8.920	
9.36	9.36	7123.36	2.245	8.936	
9.37	9.37	7123.37	2.250	8.952	
9.38	9.38	7123.38	2.254	8.968	
9.39	9.39	7123.39	2.259	8.984	
9.40	9.40	7123.40	2.264	9.000	
9.41	9.41	7123.41	2.268	9.016	
9.42	9.42	7123.42	2.273	9.032	
9.43	9.43	7123.43	2.278	9.048	
9.44	9.44	7123.44	2.283	9.064	
9.45	9.45	7123.45	2.287	9.080	
9.46	9.46	7123.46	2.292	9.096	
9.47	9.47	7123.47	2.297	9.112	
9.48	9.48	7123.48	2.302	9.128	
9.49	9.49	7123.49	2.306	9.144	
9.50	9.50	7123.50	2.311	9.160	

9.51	9.51	7037.51	3.344	16.131	
9.52	9.52	7037.52	3.349	16.156	
9.53	9.53	7037.53	3.355	16.182	
9.54	9.54	7037.54	3.360	16.208	
9.55	9.55	7037.55	3.366	16.234	
9.56	9.56	7037.56	3.371	16.259	
9.57	9.57	7037.57	3.377	16.285	
9.58	9.58	7037.58	3.382	16.311	
9.59	9.59	7037.59	3.388	16.336	
9.60	9.60	7037.60	3.393	16.362	
9.61	9.61	7037.61	3.399	16.388	
9.62	9.62	7037.62	3.404	16.413	
9.63	9.63	7037.63	3.410	16.439	
9.64	9.64	7037.64	3.415	16.465	
9.65	9.65	7037.65	3.421	16.491	
9.66	9.66	7037.66	3.426	16.516	
9.67	9.67	7037.67	3.432	16.542	
9.68	9.68	7037.68	3.437	16.568	
9.69	9.69	7037.69	3.442	16.593	
9.70	9.70	7037.70	3.448	16.619	
9.71	9.71	7037.71	3.453	16.645	
9.72	9.72	7037.72	3.459	16.670	
9.73	9.73	7037.73	3.464	16.696	
9.74	9.74	7037.74	3.470	16.722	
9.75	9.75	7037.75	3.475	16.748	
9.76	9.76	7037.76	3.481	16.773	
9.77	9.77	7037.77	3.486	16.799	
9.78	9.78	7037.78	3.492	16.825	
9.79	9.79	7037.79	3.497	16.850	
9.80	9.80	7037.80	3.503	16.876	
9.81	9.81	7037.81	3.508	16.902	
9.82	9.82	7037.82	3.514	16.927	
9.83	9.83	7037.83	3.519	16.953	
9.84	9.84	7037.84	3.525	16.979	
9.85	9.85	7037.85	3.530	17.005	
9.86	9.86	7037.86	3.536	17.030	
9.87	9.87	7037.87	3.541	17.056	
9.88	9.88	7037.88	3.547	17.082	
9.89	9.89	7037.89	3.552	17.107	
9.90	9.90	7037.90	3.558	17.133	
9.91	9.91	7037.91	3.563	17.159	
9.92	9.92	7037.92	3.569	17.184	
9.93	9.93	7037.93	3.574	17.210	
9.94	9.94	7037.94	3.579	17.236	
9.95	9.95	7037.95	3.585	17.262	
9.96	9.96	7037.96	3.590	17.287	

9.51	9.51	7123.51	2.316	9.176	
9.52	9.52	7123.52	2.320	9.192	
9.53	9.53	7123.53	2.325	9.208	
9.54	9.54	7123.54	2.330	9.224	
9.55	9.55	7123.55	2.335	9.240	
9.56	9.56	7123.56	2.339	9.256	
9.57	9.57	7123.57	2.344	9.272	
9.58	9.58	7123.58	2.349	9.288	
9.59	9.59	7123.59	2.354	9.304	
9.60	9.60	7123.60	2.358	9.320	
9.61	9.61	7123.61	2.363	9.336	
9.62	9.62	7123.62	2.368	9.352	
9.63	9.63	7123.63	2.372	9.368	
9.64	9.64	7123.64	2.372	9.384	
9.65	9.65	7123.64 7123.65	2.377	9.400	
9.66	9.66	7123.66	2.387	9.416	
9.67	9.67	7123.67	2.307	9.432	
9.68	9.68	7123.68	2.391	9.448	
9.69	9.69		2.350	9.464	
9.09 9.70	9.09 9.70	7123.69 7123.70	2.401 2.401	9.404 9.480	
9.71	9.71	7123.71	2.400	9.496	
9.72	9.71	7123.71	2.410	9.512	
9.72	9.72	7123.72	2.415	9.512	
9.73	9.73	7123.73	2.420	9.528	
9.74	9.74 9.75	7123.74 7123.75	2.425 2.429	9.544 9.560	
9.76	9.76	7123.76	2.434	9.576	
9.77	9.70	7123.70	2.434	9.592	
9.78	9.78	7123.77	2.433	9.608	
9.78	9.78	7123.78	2.443	9.624	
9.80	9.79 9.80	7123.79 7123.80	2.448	9.640	
9.81	9.81	7123.81	2.458	9.656	
9.82	9.81	7123.81	2.458	9.672	
9.83	9.82	7123.82	2.462	9.688	
9.84	9.83	7123.83	2.407	9.704	
9.85	9.84 9.85	7123.84 7123.85	2.472	9.704 9.720	
9.86	9.86		2.481	9.736	
9.86	9.86	7123.86 7123.87	2.481	9.736	
9.87	9.87	7123.87	2.480	9.752	
9.88	9.88	7123.88	2.491	9.788	
9.89	9.89 9.90	7123.89 7123.90	2.495 2.500	9.784 9.800	
9.91	9.91	7123.91	2.505	9.816	
9.91	9.91	7123.91	2.505	9.816	
9.92	9.92	7123.92	2.510	9.832	
9.93	9.93 9.94	7123.93	2.514	9.848	
9.94 9.95	9.94 9.95	7123.94 7123.95	2.519 2.524	9.864 9.880	
9.96					
9.90	9.96	7123.96	2.529	9.896	

9.97	9.97	7037.97	3.596	17.313	
9.98	9.98	7037.98	3.601	17.339	
9.99	9.99	7037.99	3.607	17.364	
10.00	10.00	7037.99 7038.00	3.612	17.390	
10.01	10.00	7038.01	3.617	17.426	
10.01	10.01	7038.01	3.623	17.462	
10.02	10.02	7038.02	3.623	17.498	
10.03	10.03	7038.03	3.633		
10.04	10.04	7038.04	3.638	17.534 17.571	
10.05 10.06	10.05 10.06	7038.05 7038.06	3.638 3.644	17.607	
10.07	10.07	7038.07	3.649	17.643	
10.08	10.08	7038.08	3.654	17.679	
10.09	10.09	7038.09	3.660	17.715	
10.10	10.10	7038.10	3.665	17.751	
10.11	10.11	7038.11	3.670	17.787	
10.12	10.12	7038.12	3.676	17.823	
10.13	10.13	7038.13	3.681	17.859	
10.14	10.14	7038.14	3.686	17.895	-
10.15	10.15	7038.15	3.692	17.932	
10.16	10.16	7038.16	3.697	17.968	
10.17	10.17	7038.17	3.702	18.004	
10.18	10.18	7038.18	3.708	18.040	
10.19	10.19	7038.19	3.713	18.076	
10.20	10.20	7038.20	3.718	18.112	
10.21	10.21	7038.21	3.724	18.148	
10.22	10.22	7038.22	3.729	18.184	
10.23	10.23	7038.23	3.734	18.220	
10.24	10.24	7038.24	3.740	18.256	
10.25	10.25	7038.25	3.745	18.293	
10.26	10.26	7038.26	3.750	18.329	
10.27	10.27	7038.27	3.756	18.365	
10.28	10.28	7038.28	3.761	18.401	
10.29	10.29	7038.29	3.766	18.437	
10.30	10.30	7038.30	3.771	18.473	
10.31	10.31	7038.31	3.777	18.509	
10.32	10.32	7038.32	3.782	18.545	
10.33	10.33	7038.33	3.787	18.581	
10.34	10.34	7038.34	3.793	18.617	
10.35	10.35	7038.35	3.798	18.654	
10.36	10.36	7038.36	3.803	18.690	
10.37	10.37	7038.37	3.809	18.726	
10.38	10.38	7038.38	3.814	18.762	
10.39	10.39	7038.39	3.819	18.798	
10.40	10.40	7038.40	3.825	18.834	
10.41	10.41	7038.41	3.830	18.870	
10.42	10.42	7038.42	3.835	18.906	


9.97	9.97	7123.97	2.533	9.912	
9.98	9.98	7123.98	2.538	9.928	
9.99	9.99	7123.99	2.543	9.944	
10.00	10.00	7124.00	2.548	9.960	Dam Crest


10.43	10.43	7038.43	3.841	18.942	
10.44	10.45	7038.44	3.846	18.978	
10.45	10.45	7038.45	3.851	19.015	
10.46	10.46	7038.46	3.857	19.051	
10.47	10.47	7038.47	3.862	19.087	
10.48	10.48	7038.48	3.867	19.123	
10.49	10.40	7038.49	3.873	19.159	
10.50	10.49	7038.50	3.878	19.195	
10.51	10.51	7038.51	3.883	19.231	
10.52	10.52	7038.52	3.889	19.267	
10.52	10.52	7038.53	3.894	19.303	
10.55	10.55	7038.53	3.899	19.339	
10.55	10.55	7038.55 7038.55	3.904	19.335	
10.56	10.56	7038.56	3.910	19.412	
10.50	10.50	7038.50	3.915	19.448	
10.57	10.57	7038.57	3.915	19.448	
10.58	10.58	7038.58	3.920	19.484	
10.39 10.60	10.59 10.60	7038.59 7038.60	3.920 3.931	19.520 19.556	
10.61	10.61	7038.61	3.936	19.592	
10.61	10.61	7038.61	3.930	19.592	
	-		3.942		
10.63	10.63	7038.63		19.664	
10.64 10.65	10.64 10.65	7038.64 7038.65	3.952 3.958	19.700 19.737	
10.66	10.66	7038.66	3.963	19.773	
10.67	10.67	7038.67	3.968	19.809	
10.68	10.68	7038.68	3.974	19.845	
10.69 10.70	10.69 10.70	7038.69	3.979 3.984	19.881 19.917	
		7038.70			
10.71	10.71	7038.71	3.990	19.953	
10.72	10.72	7038.72	3.995	19.989	
10.73	10.73	7038.73	4.000	20.025	
10.74	10.74	7038.74	4.006	20.061	
10.75	10.75	7038.75	4.011	20.098	
10.76	10.76	7038.76	4.016	20.134	
10.77	10.77	7038.77	4.022	20.170	
10.78	10.78	7038.78	4.027	20.206	
10.79	10.79	7038.79	4.032	20.242	
10.80	10.80	7038.80	4.037	20.278	
10.81	10.81	7038.81	4.043	20.314	
10.82	10.82	7038.82	4.048	20.350	
10.83	10.83	7038.83	4.053	20.386	
10.84	10.84	7038.84	4.059	20.422	
10.85	10.85	7038.85	4.064	20.459	
10.86	10.86	7038.86	4.069	20.495	
10.87	10.87	7038.87	4.075	20.531	
10.88	10.88	7038.88	4.080	20.567	


10.89	10.89	7038.89	4.085	20.603	
10.90	10.90	7038.90	4.091	20.639	
10.91	10.91	7038.91	4.096	20.675	
10.92	10.91	7038.92	4.101	20.711	
10.92	10.92	7038.93	4.101	20.747	
10.93	10.93	7038.93	4.117	20.747	
10.94	10.94	7038.94 7038.95	4.117	20.783 20.820	
10.96	10.96	7038.96	4.123	20.856	
10.90	10.90	7038.90	4.123	20.892	
10.98	10.98	7038.98	4.133	20.928	
10.99	10.99	7038.99	4.139	20.964	
11.00	10.99	7038.99 7039.00	4.139	20.904 21.000	
11.00	11.00	7039.01	4.149	21.036	
11.01	11.01	7039.01	4.145	21.030	
11.02	11.02	7039.02	4.155	21.108	
11.03	11.03	7039.03	4.165	21.108	
11.04 11.05	11.04	7039.04 7039.05	4.105 4.170	21.144 21.181	
			4.176	21.217	
11.06	11.06	7039.06			
11.07	11.07	7039.07	4.181	21.253	
11.08	11.08	7039.08	4.186	21.289	
11.09	11.09	7039.09	4.192	21.325	
11.10	11.10	7039.10	4.197	21.361	
11.11	11.11	7039.11	4.202	21.397	
11.12	11.12	7039.12	4.208	21.433	
11.13	11.13	7039.13	4.213	21.469	
11.14	11.14	7039.14	4.218	21.505	
11.15	11.15	7039.15	4.224	21.542	
11.16	11.16	7039.16	4.229	21.578	
11.17	11.17	7039.17	4.234	21.614	
11.18	11.18	7039.18	4.240	21.650	
11.19	11.19	7039.19	4.245	21.686	
11.20	11.20	7039.20	4.250	21.722	
11.21	11.21	7039.21	4.256	21.758	
11.22	11.22	7039.22	4.261	21.794	
11.23	11.23	7039.23	4.266	21.830	
11.24	11.24	7039.24	4.272	21.866	
11.25	11.25	7039.25	4.277	21.903	
11.26	11.26	7039.26	4.282	21.939	
11.27	11.27	7039.27	4.288	21.975	
11.28	11.28	7039.28	4.293	22.011	
11.29	11.29	7039.29	4.298	22.047	
11.30	11.30	7039.30	4.303	22.083	
11.31	11.31	7039.31	4.309	22.119	
11.32	11.32	7039.32	4.314	22.155	
11.33	11.33	7039.33	4.319	22.191	
11.34	11.34	7039.34	4.325	22.227	


11.35	11.35	7039.35	4.330	22.264	
11.36	11.36	7039.36	4.335	22.300	
11.37	11.37	7039.37	4.341	22.336	
11.38	11.38	7039.38	4.346	22.372	
11.39	11.39	7039.39	4.351	22.408	
11.40	11.40	7039.40	4.357	22.444	
11.41	11.41	7039.41	4.362	22.480	
11.42	11.42	7039.42	4.367	22.516	
11.43	11.43	7039.43	4.373	22.552	
11.44	11.44	7039.44	4.378	22.588	
11.45	11.45	7039.45	4.383	22.625	
11.46	11.46	7039.46	4.389	22.661	
11.47	11.47	7039.47	4.394	22.697	
11.48	11.48	7039.48	4.399	22.733	
11.49	11.49	7039.49	4.405	22.769	
11.50	11.50	7039.50	4.410	22.805	
11.51	11.51	7039.51	4.415	22.841	
11.52	11.52	7039.52	4.421	22.877	
11.53	11.53	7039.53	4.426	22.913	
11.54	11.54	7039.54	4.431	22.949	
11.55	11.55	7039.55	4.436	22.986	
11.56	11.56	7039.56	4.442	23.022	
11.57	11.57	7039.57	4.447	23.058	
11.58	11.58	7039.58	4.452	23.094	
11.59	11.59	7039.59	4.458	23.130	
11.60	11.60	7039.60	4.463	23.166	
11.61	11.61	7039.61	4.468	23.202	
11.62	11.62	7039.62	4.474	23.238	
11.63	11.63	7039.63	4.479	23.274	
11.64	11.64	7039.64	4.484	23.310	
11.65	11.65	7039.65	4.490	23.347	
11.66	11.66	7039.66	4.495	23.383	
11.67	11.67	7039.67	4.500	23.419	
11.68	11.68	7039.68	4.506	23.455	
11.69	11.69	7039.69	4.511	23.491	
11.70	11.70	7039.70	4.516	23.527	
11.71	11.71	7039.71	4.522	23.563	
11.72	11.72	7039.72	4.527	23.599	
11.73	11.73	7039.73	4.532	23.635	
11.74	11.74	7039.74	4.538	23.671	
11.75	11.75	7039.75	4.543	23.708	
11.76	11.76	7039.76	4.548	23.744	
11.77	11.77	7039.77	4.554	23.780	
11.78	11.78	7039.78	4.559	23.816	
11.79	11.79	7039.79	4.564	23.852	
11.80	11.80	7039.80	4.569	23.888	

11.81	11.81	7039.81	4.575	23.924	
11.82	11.82	7039.82	4.580	23.960	
11.83	11.83	7039.83	4.585	23.996	
11.84	11.84	7039.84	4.591	24.032	
11.85	11.85	7039.85	4.596	24.069	
11.86	11.86	7039.86	4.601	24.105	
11.87	11.87	7039.87	4.607	24.141	
11.88	11.88	7039.88	4.612	24.177	
11.89	11.89	7039.89	4.617	24.213	
11.90	11.90	7039.90	4.623	24.249	
11.91	11.91	7039.91	4.628	24.285	
11.92	11.92	7039.92	4.633	24.321	
11.93	11.93	7039.93	4.639	24.357	
11.94	11.94	7039.94	4.644	24.393	
11.94 11.95	11.94 11.95	7039.94 7039.95	4.644 4.649	24.393 24.430	
-	-		-		
11.95	11.95	7039.95	4.649	24.430	
11.95 11.96	11.95 11.96	7039.95 7039.96	4.649 4.655	24.430 24.466	
11.95 11.96 11.97	11.95 11.96 11.97	7039.95 7039.96 7039.97	4.649 4.655 4.660	24.430 24.466 24.502	









DISTRICT COURT, WATER DIVISION NO. 2, COLORADO

Case No. 91CW35

RULING OF REFEREE Division No. 2, State of SAL BOARD

CONCERNING THE APPLICATION FOR WATER RIGHTS OF: APR 9 1992

COLACO, LTD.,

IN EL PASO COUNTY.

marco Reeino

DIPY RECEIVED

Cleri Pursuant to Order of Referral filed and entered in the above case on October 24, 1991, the undersigned Water Referee.

above case on October 24, 1991, the undersigned Water Referee, having investigated the matter of the Application on file herein, hereby makes the following findings and ruling thereon:

FINDINGS OF FACT

1. That the said Application was filed on October 24, 1991.

2. That the Water Clerk caused publication of such filing as provided by statute; that publication costs have been paid; that the time for filing Statements of Opposition expired on the last day of December, 1991, that one such has been filed by the City of Colorado Springs and that agreement has been reached by the parties on a proposed ruling.

3. That the said Application concerns a claim for four wells located in El Paso County, Colorado.

4. Name of Wells:

- (a) Dawson Aquifer: Colaco DA-1.
- (b) Denver Aquifer: Colaco DN-1,
- (c) Arapahoe Aquifer: Colaco KA-1.
- (d) Laramie-Fox Hills Aquifer: Colaco LFH-1.

5. Legal descriptions of locations of wells:

(a) Colaco DA-1: SE1/4 NE1/4, Section 34, T. 12 S.
 R. 65 W., 6th P.M., at a point 2780 feet from the south section line and 300 feet from the east section line.

- (b) Colaco DN-1: SE1/4 NE1/4, Section 34, T. 12 S., R. 65 W., 6th P.M., at a point 2740 feet from the south section line and 300 feet from the east section line.
- (c) Colaco KA-1: SEJ/4 NEL/4, Section 34, T. 12 S., R. 65 W., 6th P.M. at a point 2690 feet from the south section line and 300 feet from the east section line.
- (d) Colaco LFH-1: SE1/4 NE1/4, Section 34, T. 12
 S., R. 65 W., 6th P.M., at a point 2640 feet from the south section line and 300 feet from the east section line.

6. Source of Water: Dawson, Denver, Arapahoe and Laramie-Fox Hills Aquifers.

7. Date of Appropriation: Not applicable pursuant to C.R.S. 37-92-305(11).

8. The amount of water:

The estimated depths, below land surface, estimated pumping rates and estimated annual withdrawals for each well are as follows:

Estimate	d Depths	Pumpi	ng Rate	Annual Withdrawal
Тор	Bottom	CFS	(GPM)	Acre Feet
43	324	0.67	300	34 🗸
350	1,245	0.67	300	76
1,283	1,785	1,79	800	49
2,054	2,334	0.67	300	36
	<u>Top</u> 43 350 1,283	43 324 350 1,245 1,283 1,785	Top Bottom CFS 43 324 0.67 350 1,245 0.67 1,283 1,785 1.79	Top Bottom CFS (GPM) 43 324 0.67 300 350 1,245 0.67 300 1,283 1,785 1.79 800

9. The use of the water:

Colaco DA-1, Colaco DN-1, Colaco KA-1, Colaco LFH-1 Wells: water withdrawn from these wells may be used, reused and successively used and otherwise disposed of for all purposes including: municipal, domestic, industrial, commercial, irrigation, stockwater, recreation, fish and wildlife, fire protection, sanitary purposes, storage, exchange, and augmentation. Augmentation use cannot be made until a court approved plan for augmentation is obtained or the State Engineer has approved a substitute supply plan or exchange. All subject to provisions of Paragraph 14 and 15 herein. In accordance with C.R.S. 37-90-137(9)(c), judicial approval of a plan for augmentation shall be required prior to the use of ground water from the Dawson Aguifer or from the Denver Aguifer. In the case of the Dawson aguifer such

PAGE 2 - RULING OF REFEREE - CASE NO. 91CW35

augmentation plan shall provide for the replacement of actual stream depletions to the extent necessary to prevent any injurious effect, based on actual aquifer conditions in existence at the time of the decree. In the case of the Denver Aquifer such augmentation plan shall provide for the replacement to affected stream systems or system of a total amount of water equal to four (4) percent of the amount of water withdrawn on an annual basis and such additional amounts that may be required pursuant to Section 37-90-137(9)(c), C.R.S. (1986 Supp.).

10. Applicant claims all water under the 132 acres known as NE1/4 SE1/4, SE1/4 SE1/4, and SE1/4 NE1/4, Section 34, Township 12 South, Range 65 West of the 6th P.M., El Paso County, from the Dawson, Denver, Arapahoe and Laramie-Fox Hills Aquifers.

11. Allowed Average Annual Amount of Withdrawal

The criteria used in determining the allowed average annual amount of withdrawal of groundwater from each aquifer as specified in Paragraph 8, beneath the land described in Paragraph 10 are those criteria prescribed by C.R.S. 37-90-137(4) and the Rules and Regulations adopted by the State Engineer. The values used to calculate the allowed average annual amount of withdrawal are:

	No. of	Saturated Materials	Specific	Acre-Feet
<u>Aquifer</u>	Acres	(feet)	Yield	Per Year
Dawson	132	128	20%	34
Denver	132	340	17%	76
Arapahoe	132	220	17%	49
Laramie-Fox Hills	132	183	15%	36

all in accordance with the Determinations of Facts issued by the State Engineer on January 15, 1992.

The values may be adjusted based on site specific data submitted pursuant to the Statewide Nontributary Groundwater Rules and subject to the retained jurisdiction provisions contained in Paragraph 17.

12. The ground water in the Arapahoe and Laramie-Fox Hills aquifers underlying the Subject Land is nontributary ground water as that term is defined in Section 37-90-103(10.5), 15 C.R.S. (as amended). The withdrawal of the total amount of nontributary ground water underlying the Subject Land will not cause material injury to any other vested water right, and will not, within one hundred years, deplete

PAGE 3 - RULING OF REFEREE - CASE NO. 91CW35

the flow of a natural surface stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal.

Pursuant to the State Engineer's Denver Basin Rules, the ground water underlying the Subject Land in the Dawson and Denver aquifers is "not nontributary" ground water as that term is used in Section 37-90-137(9)(c), C.R.S. Applicant is entitled to withdraw and use all previously unappropriated and legally available ground water from these aquifers. Well Colaco DN-1 is located more than one mile from the nearest point of contact between the Denver aquifer and any natural stream and its alluvium.

13. Construction of Wells

For all wells, applicants shall comply with the following conditions:

A. The entire length of the open bore hole except the surface casing shall be geophysically surveyed prior to casing and copies of the geophysical log submitted to the Division of Water Resources within 60 days of drilling. Applicant may provide a geophysical log from an adjacent well or test hole in accordance with the Statewide Rules and Regulations and acceptable to the State Engineer, which fully penetrates the formation, in satisfaction of the above requirement.

B. The ground water production shall be limited to the aquifers stated in Paragraph 8 herein as defined in the Denver Basin Rules and Regulations. Non-perforated casing must be installed and properly grouted to prevent withdrawal from or intermingling of water between other aquifers.

C. The permit number and name of the aguifer shall be permanently displayed on or near the well at a location easily accessible to water officials.

D. Applicant shall comply with C.R.S. Section 37-91-101, et seq. and the Rules and Regulations promulgated thereto and with such other requirements for constructing and equipping the well as the State Engineer may reasonably require.

E. Unless otherwise authorized by the Division Engineer, applicant shall install a totalizing flow meter on each well. The meter shall be installed according to the manufacturer's recommendations and shall be inspected at least annually, and promptly repaired or recalibrated as needed. If Applicant's meter becomes inoperable, it shall be repaired as soon as possible so that measurements can continue. Permission to operate the well without an operational meter must be obtained from the Division Engineer. F. The Applicant shall keep records of the amount of water pumped and perform the calculations necessary to determine whether Applicant is in compliance with this decree. Applicant shall supply the Division Engineer with those records at least on an annual basis or upon request by the Division Engineer.

14. Limitation on Consumption of Nontributary Groundwater.

Applicant may not consume more than 98 percent of the annual quantity of the nontributary groundwater withdrawn from Colaco KA-1 Well and Colaco LFM-1 Well from the aquifer underlying the property in Paragraph 10. The relinquishment of 2 percent of the annual amount of water withdrawn to the stream system, as required by the Denver Basin Rules effective January 1, 1986, may be satisfied by any method selected by the Applicant, so long as Applicant can demonstrate to the reasonable satisfaction of the State Engineer prior to issuance of the permit that an amount equal to 2 percent of such annual withdrawals (by volume) will be relinquished to the stream system, by quantifiable return flows or otherwise.

15. Any right to reuse or successive use of water approved herein shall be in accordance with C.R.S. 37-82-106(2).

16. Well Permits

N. •

Well Permit No. 31778-F was issued to Colaco DN-1 Well on June 2, 1987. When the applicant is ready to construct Wells Colaco DA-1, Colaco KA-1, and Colaco LFH-1, an application for a well permit shall be filed pursuant to 37-90-137, C.R.S. The State Engineer shall consider the rights granted herein as valid. If Applicant fails to construct the well for which the permit was issued within the period of time authorized by statute, including legally authorized extension of any such time period, then when Applicant is ready to drill the well, Applicant shall file a second application for such well and the State Engineer may issue a well permit with restrictions no more burdensome than are found in this ruling.

17. Retained Jurisdiction.

The Court retains jurisdiction to provide for the adjustment of the annual amount of withdrawal to conform to actual local aquifer characteristics as determined from analyses of data obtained when the wells are constructed or test holes drilled. Within 60 days after the completion of such well(s) or test hole(s), the Applicant shall file with the State Engineer, and serve each of the parties who have appeared herein, copies of the well logs from such well(s) or test hole(s). Any person including the State Engineer can

PAGE 5 - RULING OF REFEREE - CASE NO. 91CW35

invoke the Court's retained jurisdiction to make a Final Determination of Water Right. The State Engineer can invoke the Court's retained jurisdiction to make a Final Determination of Water Right. The State Engineer, upon notification of retained jurisdiction, shall utilize data available to him and make a final Determination of Water Rights Finding within 4 months and submit same to the Water Court. If no protest to such a filing is made within 60 days, the Final Determination of Water Right shall be incorporated into the decree by the Water Court. In the event of a protest, or in the event the State Engineer makes no determination within 4 months, such final determination shall be made by the Water Court after notice and hearing.

18. The rights to nontributary ground water sought by this Application are not "Conditional Water Rights" and Findings of Reasonable Diligence are not required. Pursuant to Section 37-90-305(11), 15 C.R.S. (as amended), the rights to nontributary ground water requested from the Arapahoe and Laramie-Pox Hills aquifers are vested property rights, not conditional water rights, and the requirements of Section 37-92-102(6), 301(4), and 601, 15 C.R.S. (as amended) pertaining to conditional water rights and the requirement for findings of reasonable diligence are inapplicable to rights to such ground water.

The "not nontributary" ground water in the Dawson and Denver aquifers is, pursuant to Section 37-90-137(4) and (9), to be administered over a one hundred year aquifer life and not pursuant to any doctrine of priority of appropriation. For that reason, none of the policies or purposes of conditional water rights and the filings of reasonable diligence associated with the priority of appropriation are applicable to the rights to the "not nontributary" ground water requested herein. As a matter of law, even though the ground water requested from the "not nontributary" Dawson and Denver aquifers has not been diverted and applied to beneficial use, it is a vested property right, and that the requirements of Sections 37-92-102(6), 301(4), and 601, C.R.S. pertaining to conditional water rights and findings of reasonable diligence are inapplicable to the "not nontributary" ground water. The failure to obtain periodic findings of reasonable diligence shall not result in a loss, forfeiture, or abandonment of Applicant's rights to "not nontributary" ground water from the Dawson or Denver aquifers.

19. That Applicant has furnished acceptable proof as to claims made.

IT IS, THEREFORE, CRDERED AS FOLLOWS: That Applicant be, and is hereby, awarded the underground water rights for Colaco DA-1, Colaco DN-1, Colaco KA-1, and Colaco LFH-1 Wells as set forth herein.

NAME AND ADDRESS:

Colaco, Ltd., a Colorado Corporation William A. Fischer, President 1790 Pinnacle Ridge Lane Colorado Springs, CO 80919

IT IS FURTHER ORDERED that Applicant shall install and maintain such water measurement devices, recording devices, content gauges and inlet and outlet measurement and recording devices, as the case may be, as are deemed essential by the Office of the State Engineer, and the same shall be installed and operated in accordance with instructions from said Office.

IT IS FURTHER ORDERED that copies of this ruling shall be mailed as provided by statute.

Dated and filed with the Water Clerk this <u>9th</u> day of April, 1992.

BY THE REFEREE:

Clyde B. Young, Jr. Water Division No. Jr.6 Water Referee

Water Division No. 2^{\checkmark} State of Colorado

> Clerk, District Court Water Division No. 2, State of Colorndo

> > APR 9 1992

mandle Relino

Clerk

PAGE 7 - RULING OF REFEREE - CASE NO. 91CW35

DISTRICT COURT, WATER DIVISION 2, COLORAD CASE NO. <u>91CW35</u>	COPY Filed in the office of the Clerk, District Court Wall Clerk, District Court Wall Colorado
JUDGMENT AND DECREE	and the second s
CONCERNING THE APPLICATION FOR WATER RIGH	
COLACO, LTD.	IN EL PASO County.

THE COURT FINDS That no protest has been filed to the Ruling of the Water Referee within the time provided by law, and that said Ruling should be confirmed, approved and adopted.

IT IS, THEREFORE, ORDERED, ADJUDGED AND DECREED That the Ruling of Referee entered on <u>April 9, 1992</u>, be and is incorporated herein by reference and is confirmed, approved and adopted as the judgment of this Court.

*Dated: <u>May 5, 1992</u> BY THE COURT: . er L 123 TRACEY, WATER JUDGE JOHN R.

N 107

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

DISTRICT COURT, WATER DIVISION NO. 2, STATE OF COLORADO 0CT 29 1986

Case No. 86-CW-18

 $\mathcal{L}_{k^{*}}^{\prime\prime}$

Riscieles Syners

Clerk

FINDINGS OF FACT, CONCLUSIONS OF LAW, JUDGMENT AND DECREE

CONCERNING THE APPLICATION FOR NONTRIBUTARY GROUND WATER RIGHTS OF THE FIRST INTERSTATE BANK OF DENVER N.A., CARLA W. LEWIS, AND SAMUEL S. SHERMAN AS COTRUSTEES UNDER THE LIFE INSURANCE TRUST OF THOMAS M. DINES FROM THE ARAPAHOE FORMATION, EL PASO COUNTY.

THIS MATTER, having come on for hearing before the Court this 29 day of 200, 1986 upon the application of The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines ("Applicants") and the Court having considered the pleadings filed and the evidence presented, and being fully advised in the premises, hereby enters the following Findings of Fact, Conclusions of Law, and Judgment and Decree:

FINDINGS OF FACT

1. The Applicants are The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines whose address is First Interstate Bank of Denver, 633 Seventeenth Street, Denver, Colorado 80202, Attn: Jack Alexander. Applicants filed the application in this case styled Application For Nontributary Ground Water From The Arapahoe Formation (the "Application") on March 28, 1986, seeking an adjudication of nontributary ground water rights from the Arapahoe Formation underlying lands owned by Applicants in El Paso County.

2. Timely and adequate notice of the Application was published as required by statute, and the Court has jurisdiction over the subject matter of this proceeding and over all parties affected hereby, whether they have appeared or not. None of the lands or water rights involved in this case are within the boundaries of a designated groundwater basin.

3. A timely statement of opposition was filed by JVRC, Inc. No other statements of opposition were filed within the time provided by law nor did any other parties enter their appearance or intervene in these proceedings. 4. The Water Referee by Order dated July 19, 1986, under Section 37-92-303(2), C.R.S., rereferred the Application to the Water Judge for all further proceedings.

5. The State Engineer issued a Determination of Facts on the Application, dated July 28, 1986, which has been filed with the Court. The Division Engineer adopted the Determination of Facts as his recommendations on August 8, 1986. The Determination of Facts and the findings contained therein have been reviewed and considered by this Court in accordance with Section 37-92-305(6), C.R.S.

Applicants seek an adjudication of rights 6. to nontributary ground water from the Arapahoe Formation beneath 1,410 acres of land in El Paso County which are described in Exhibit A and depicted on the map attached as Exhibit B, both of which are incorporated herein by this reference (the "Subject Lands"). Applicants are the owners of the Subject Lands and have the right to withdraw and use the waters from the Arapahoe Formation underlying those lands. The waters claimed herein may be withdrawn through the proposed wells described in Paragraph $\overline{7}$ below and through such additional, replacement and supplemental wells as may be necessary to withdraw all of the water in the Arapahoe Formation underlying the Subject Lands without causing material injury to any vested water right whose source of supply is the Arkansas River and any of its tributaries or any other natural stream, or any ground water tributary thereto, and the Applicants have so proven.

7. Applicants will divert the waters claimed herein from the Arapahoe Formation through Dines Wells KA-1, KA-2, KA-3, and KA-4 more particularly described as follows:

Well Name: Dines Well KA-1

- (a) In the SE 1/4 of the NW 1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., 2500 feet from the North Section line and 2200 feet from the West Section line, in El Paso County.
- (b) Depth: 1900 feet.
- (c) Source: Nontributary Arapahoe Formation.
- (d) Pumping rate: 150 gpm.

- 2 -

(e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KA-2

- (a) Location: In the SW 1/4 of the SW 1/4 of Section 27, Township 12 South, Range 65 West of the 6th P.M., 200 feet from the South Section line and 200 feet from the West Section line, in El Paso County.
- (b) Depth: 1800 feet.
- (c) Source: Nontributary Arapahoe Formation.
- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KA-3

- (a) Location: In the NW 1/4 of the SE 1/4 of Section 33, Township 12 South, Range 65 West of the 6th P.M., 1500 feet from the South Section line and 2100 feet from the East Section line, in El Paso County.
- (b) Depth: 1700 feet.
- (c) Source: Nontributary Arapahoe Formation.
- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.*

Well Name: Dines Well KA-4

- (a) Location: In the NE 1/4 of the SW 1/4 of Section 34, Township 12 South, Range 65 West of the 6th P.M., 1400 feet from the South Section line and 2100 feet from the West Section line, in El Paso County.
- (b) Depth: 1700 feet.
- (c) Source: Nontributary Arapahoe Formation.

- (d) Pumping rate: 150 gpm.
- (e) Annual quantity: 240 acre-feet.
- * Not to exceed in total the amount available to Applicants from the Arapahoe Formation pursuant to § 37-90-137(4), C.R.S. and the provisions of this decree.

8. Pursuant to §37-90-137(4), C.R.S., five hundred seventy-five (575) acre-feet of water per year are available to Applicants from the Arapahoe Formation underlying the Subject Lands. The average thickness of saturated sand of the Arapahoe Formation underlying the Subject Lands is 240 feet but the final determination on actual saturated sand thickness will be determined when the wells are drilled, and the amount decreed herein may be subsequently adjusted in accordance with that saturated sand thickness as provided in Paragraph 29 below. The specific yield of the Arapahoe Formation is 17% in and beneath the Subject Lands. This finding is specific to the property involved and does not indicate or in any way reflect upon proper values for the subject aquifer elsewhere. All the water in the Arapahoe Formation underlying the Subject Lands remains available for withdrawal by the wells decreed herein.

The State Engineer in his Determination of Facts 9. found acre-feet per year were that 581 available for appropriation through the subject wells. The State Engineer's determination is based on a finding that only 1395 acres of the Subject Lands are available for appropriation, and based on saturated sand thicknesses of 245 feet and 250 feet for different parts of the Subject Lands and a specific yield of 17% for the Arapahoe Formation. The State Engineer also found that of the total 581 acre-feet per year of water available for appropriation, 569 acre-feet was nontributary and 12 acre-feet was not nontributary. The 12 acre-feet per year the State Engineer found as not nontributary underly 37 acres of Section 32 of the Subject Lands. Applicant has shown by a preponderance of the evidence that there are no existing wells with a right to water from the Arapahoe Formation underlying the Subject Lands and that the water underlying 1410 acres is available for The Court also finds that the appropriation by Applicants. withdrawals through Applicants' proposed wells of the water claimed herein including the amount of water underlying the 37 acres in Section 32 is nontributary. The proposed wells will not, at their location and withdrawing the amounts decreed herein, within one hundred years deplete the flow of any natural stream at a rate greater than one-tenth of one percent of the annual rate of withdrawal. Applicants' engineer has testified that 575 acre-feet per year is available for appropriation calculated with a saturated sand thickness of 240 feet for the

Arapahoe Formation. Subject to the final determination of saturated sand thickness based on the information derived from the drilling of the wells, Applicants will use 240 feet for the saturated sand thickness of the Arapahoe Formation beneath the Applicants' property.

10. The source of water for the proposed wells is nontributary as defined in Section 37-90-103 (10.5), C.R.S. The proposed withdrawals through Dines Wells KA-1, KA-2, KA-3, and KA-4 in the amount of 575 acre-feet per year, or in any lesser or greater amount determined under Paragraph 29, will not, within one hundred years, deplete the flow of any natural stream or its alluvium or any ground water tributary thereto at an annual rate greater than one-tenth of 1% of the annual rate of withdrawal.

11. The waters of the Arapahoe Formation that are the subject of the appropriation claimed herein will be, and Applicants intend that they be used, and Applicants shall have the right of succession of uses, for municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation, exchange, replacement of depletions, augmentation, livestock and agricultural uses. The water will be produced for immediate application to beneficial use and for storage and subsequent application to beneficial use. Subject only to the provisions of Paragraph 31, Applicants shall have the right to make any reuse, successive use or disposition of the developed water claimed herein until totally consumed free of any limitations, restrictions, or requirements as to the place of use, amount of discharge or location of discharge after such reuse, successive use or disposition in accord with Section 37-82-106, C.R.S.

12. All of the requirements of C.R.S. § 37-90-137(4), in effect on this date have been complied with, and the issuance of permits for the subject wells is justified and those permits will be issued as described in Paragraph 34 below.

13. Applicants will relinquish the right to consume after use, reuse, and successive use 2% of the amount of ground water withdrawn through Dines Wells KA-1, KA-2, KA-3 and KA-4 and any additional, supplemental, or replacement, wells without regard to dominion or control of the ground water so relinquished.

14. Applicants seek a decree designating all of the wells described in Paragraph 7 above as original and alternate points of diversion for each other permitting the withdrawal of up to the full cumulative amount by flow rate and volume of water which may be lawfully withdrawn from any one or more of those wells. The Court finds that no material injury will result to the owners or persons entitled to use water under any vested

- 5 -

water right or decreed conditional water right by the granting of this request, and it is hereby granted.

15. Applicants may withdraw more water than the amounts set forth in Paragraph 8 so long as the sum of the withdrawals from all wells decreed herein (as that sum may subsequently be adjusted pursuant to Paragraph 29 hereof) does not exceed the product of the number of years since the date of this decree, times the annual rate of one percent (1%) of the total amount of unappropriated water recoverable from the Arapahoe Formation.

16. Applicants have requested that the Court determine that Applicants have the right to withdraw all of the unappropriated water from the Arapahoe Formation lying below their land and to increase their annual appropriations based upon the local aquifer characteristics established through information obtained from the drilling of the wells upon notice to all parties and approval by the Court, without amending the Application or republishing. The Court finds that there has been full and adequate notice of these claims and Applicants will be entitled to an adjustment under the provisions of Paragraph 29 below on the amount of water to which the wells are entitled.

17. Applicants may construct any well within 200 feet of the described locations without amending the Application or reopening this decree.

18. With respect to the permits to be issued by the State Engineer's office for construction of the wells described in Paragraph 7 herein, the provisions of Paragraph 34 below are and have been justified and shall apply.

19. As of March 3, 1986, Applicants have intended to the waters sought in the Application and have claim so demonstrated by open and physical acts on the ground and by the completion of engineering study an and hydrogeological investigation on the water available for appropriation in the Arapahoe Formation. Applicants have demonstrated and manifested an intent to appropriate the waters claimed herein by giving sufficient notice thereof, all in accordance with law. The evidence presented shows that the Applicants intend to appropriate the waters claimed herein, that such intent to appropriate has been adequately demonstrated, and that Applicants are entitled to a decree for the water rights herein decreed.

20. There is unappropriated water available for withdrawal by the structures decreed herein and the vested water rights of others will not be materially injured by the appropriations as decreed. Only that quantity of water underlying the Subject Lands has been considered to be unappropriated; the minimum useful life of the Arapahoe Formation is at least one hundred (100) years, assuming no substantial artificial recharge within one hundred (100) years; and no material injury to vested water rights will result from the issuance of or exercise of the permits for the subject wells.

CONCLUSIONS OF LAW

21. The Court has jurisdiction to determine Applicants' rights to nontributary ground water pursuant to Sections 37-90-137(6), 37-92-203(1), and 37-92-302 through 305, C.R.S. (Supp. 1985). The procedures and requirements of these statutes have been complied with, full and adequate notice has been given, and no additional notice is required.

22. The Court concludes as a matter of law that the Application herein is one contemplated by law. The Application for a decree confirming Applicants' right to divert and use ground water from the Arapahoe Formation beneath the Subject Lands, pursuant to C.R.S. § 37-90-137(4), should be granted, subject to the provisions of this decree. The rights confirmed by this decree are vested property rights. The amount of water confirmed in this decree is that quantity of water underlying the Subject Lands and the annual withdrawals are based on an aquifer life of one hundred years.

23. The Court concludes that the rights to ground water determined herein are not conditional water rights and subsequent showings or findings of reasonable diligence under Section 37-92-301(4), C.R.S., are inapplicable and need not be made. Accordingly, each of the water rights adjudicated herein is a final vested property right.

24. Applicants are entitled as a matter of law to use, reuse, and successively use to extinction and dispose of all nontributary ground water decreed herein pursuant to Section 37-82-106, C.R.S. (Supp. 1985) subject only to a 2% relinquishment of Applicants' right to total consumption. Failure to use, reuse or recapture such water, including return flows, shall not be deemed a forfeiture or abandonment of the right to such use, reuse or recapture.

25. The Court shall retain jurisdiction over this matter to make adjustments to the amount of water available for withdrawal annually to conform to the actual aquifer characteristics encountered upon the drilling of the wells. This retained jurisdiction may be invoked only by the parties under Paragraph 36.

- 7 -

JUDGMENT AND DECREE

26. The Findings of Fact and Conclusions of Law set forth in Paragraphs 1-25, above are incorporated herein by this reference.

27. The Application for determination of water rights for the subject wells is granted subject to the following limitations.

A right to five hundred seventy-five (575) acre-28. nontributary ground water per year is decreed and feet of confirmed in Applicants pursuant to § 37-90-137(4), C.R.S., for Dines Wells KA-1, KA-2, KA-3, and KA-4, from the Arapahoe Formation for municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation, exchange, replacement of depletions, augmentation, livestock and agricultural uses. Applicants shall have the right to recapture, reuse, and dispose of the water developed by the subject wells. Applicants shall have the right to withdraw water for immediate application to beneficial use and for storage and subsequent application to beneficial use and shall have the right to make any reuse, successive use or disposition of the developed water claimed herein to extinction free of any limitations. restrictions, or requirements as to the place of use, amount of discharge or location of discharge after such reuse, successive use or disposition in accord with Section 37-82-106, C.R.S. subject only to the provisions of Paragraph 31 below. The water may be withdrawn through the wells described in Paragraph 7 above and through such additional wells as may be required in order to maintain the annual appropriation as determined herein. The proposed withdrawals through Dines Wells KA-1, KA-2, KA-3, and KA-4 and any additional, supplemental, or replacement wells in the amount of 575 acre-feet per year, or in any additional amounts of water from the Arapahoe Formation underlying the Subject Lands, will not, within one hundred years, deplete the flow of any natural stream or its alluvium or any ground water tributary thereto at an annual rate greater than one-tenth of 1% annual rate of withdrawal, and those waters of the are nontributary to any natural surface stream, its alluvium, and any ground water tributary thereto, and the proposed withdrawals will not result in material injury to vested water rights.

29. The total amount of water to which Applicants are entitled and which is available to Applicants from the Arapahoe Formation beneath the Subject Lands shall be 575 acre-feet per year or the lesser or greater amount of water each such well is entitled to as subsequently determined from the saturated sand thickness of the Arapahoe Formation determined from the geophysical data obtained from the construction of the wells. Geophysical logs shall be taken in accordance with the applicable rules promulgated by the State Engineer. In making the determination of the final amount of water to which the subject wells are entitled, the following criteria shall apply:

(a) Saturated sand thickness shall be defined as the cumulative thickness of saturated materials as shown on the geophysical logs for each well applying standard accepted geophysical log interpretation methodology;

(b) The specific yield for the Arapahoe Formation shall be 17%;

(c) The water in the Arapahoe Formation underlying the 1410 acres of the Subject Lands shall be considered available for appropriation by the wells decreed herein.

After the completion of the wells subject to this decree, Applicants shall submit the geophysical logs and any other geophysical information obtained from the drilling of the wells to the State Engineer and to the other parties in this action together with a statement from Applicants on the final actual saturated sand thickness and final annual appropriation for each well as determined by Applicants. Within 60 days from the date on which Applicants mail copies of the geophysical logs and statement to the parties herein, any party may petition this Court to invoke the Court's retained jurisdiction under Paragraph 36 of this decree to reconsider the saturated sand thickness of the Arapahoe Formation underlying the Subject Lands for the purpose of adjusting the total entitlement of water to the wells decreed herein. Those proceedings shall be limited exclusively to the issue of saturated sand thickness. If the Court's retained jurisdiction is not invoked within the time prescribed in this Paragraph, the respective amounts set forth in Applicants' statement as the final annual entitlement to each well shall be final, which amount shall be confirmed as final by order of the Court upon Applicants' motion to the Court setting forth facts showing compliance with this Paragraph.

30. The issuance by the Colorado Division of Water Resources pursuant to Colorado Revised Statutes, Section 37-90-137(4) of permits to construct the subject wells is justified and the Division of Water Resources is directed to issue the permits in accordance with Paragraph 34 below. Each of the requirements of the statute has been complied with. Unappropriated waters are available for appropriation from the Arapahoe Formation beneath the Subject Lands and the proposed withdrawals will not result in material injury to other vested water rights. 31. Applicants shall relinquish the right to consume, after use, reuse, and successive use 2% of the water withdrawn through Dines Wells KA-1, KA-2, KA-3 and KA-4 and any additional, supplemental, or replacement wells without regard to dominion or control of the ground water so relinquished.

32. All of the wells described in Paragraph 7 may be used as original and alternate points of diversion for each other permitting the withdrawal by flow rate and volume of up to the full cumulative amount of water which may be lawfully withdrawn from all of those wells from any one or more of those wells. The Court finds that no material injury will result to the owners or persons entitled to use water under any vested water right or decreed conditional water right by the granting of this request, and it is hereby granted.

33. Applicants may withdraw more water than the final annual appropriation for each well so long as the sum of the withdrawals from all wells decreed herein (as that sum may subsequently be adjusted pursuant to Paragraph 29 hereof) does not exceed the product of the number of years since the date of issuance of this decree, times the annual rate of one percent (1%) of the total amount of unappropriated water recoverable from the Arapahoe Formation.

34. With respect to the permits to be issued by the State Engineer's office for construction of the wells described in Paragraph 7 herein, the following provisions shall apply.

(a) The State Engineer shall consider the rights granted herein as valid and shall consider the water sought by Applicants as taken and appropriated by Applicants.

(b) When Applicants are prepared to drill a well described in this decree, Applicants shall apply to the State Engineer for a well permit and that permit shall be issued within 60 days under terms and conditions no less stringent than those set forth in this decree with the conditions for equipping and constructing the well as are specified in Paragraph 35 herein. In the event that a well permit expires prior to the construction of the well and the application of water to beneficial use, Applicants may apply for a new well permit and the State Engineer shall within 60 days issue a new well permit with the same terms and conditions as the permit that expired.

(c) Applicants shall submit well permit applications to the State Engineer's office for any replacement, supplemental or additional wells.

(d) Any well permitted pursuant to this decree which is drilled within 200 feet of the decreed location shall be deemed to have been drilled at the decreed well location and shall not require application for a new or amended well permit.

(e) In determining whether good cause exists for granting a request by Applicants to extend well permits for nontributary wells for one or more additional oneyear periods pursuant to Section 37-90-137(3)(a)(II), C.R.S. (1985 Supp.), the State Engineer shall recognize that each well decreed herein, and such additional wells as are required from time to time to fully recover the annual appropriation herein, are part of a single integrated water supply system to be constructed over a phased period of time. So long as Applicants still desire to use the groundwater the well permits shall be extended.

(f) Prior to constructing any additional wells, Applicants shall submit well permit applications to the State Engineer. In considering such permit applications, the State Engineer shall be governed by Section 37-90-137(10), C.R.S. (1985 Supp.) and the provisions of this decree. Any such permitting action may be reviewed by this Court pursuant to Section 37-92-305(6), C.R.S. (1985 Supp.).

(g) For the purpose of well permit applications, Applicants need not submit separate proof, apart from the terms of this decree, of matters which have been determined herein.

35. Applicants shall geophysically log the entire bore hole of each well prior to the installation of casing. Such logs shall be taken in accordance with the applicable rules promulgated by the State Engineer. In constructing and maintaining any well which will withdraw water from the Arapahoe Formation under this decree, the Applicants shall seal off and encase the well with an impervious lining at all levels, except the level of the Arapahoe Formation, to prevent withdrawal of and mixing of groundwater in other aquifers and a totalizing flow meter shall be installed on each well. After construction the Applicants shall attach an identification tag to the well specifying the name of the well, the permit number and the aquifer from which the water is withdrawn. Applicants shall maintain records of the amounts pumped from each well on a monthly basis and such records shall be provided to the Division Engineer or the State Engineer on request.

36. This Court retains jurisdiction in this case for the reconsideration of the final amounts of water appropriated by the proposed wells in accord with Paragraph 29 above. The Court's retained jurisdiction may be invoked only by the Applicants and JVRC, Inc. The Court's retained jurisdiction may be invoked by written notice to the Court requesting a hearing. Copies of that notice will be served on the parties herein at their latest address of record in this case.

Dated this 29 day of 90t. , 1986.

BY THE COURT

Honorable John Tracey Water Judge Water Division No. 2 State of Colorado

APPROVED AS TO FORM AND SUBSTANCE:

SHERMAN & HOWARD

John L. DeWeerdt #9390

Kenneth L. Salazar #11648 Suite 2900 633 Seventeenth Street Denver, Colorado 80202

Telephone: (303) 297-2900

Attorneys for Applicants, The First Interstate Bank of Denver N.A., Carla W. Lewis, and Samuel S. Sherman as Cotrustees under the Life Insurance Trust of Thomas M. Dines.

Sherman and Howard (Salazar) C: Vranesh & Raisch (Shimmin) Division Engineer State Engineer

VRANESH & RAISCH

Michael D. Shimmin, Post Office Box 871 Boulder, Colorado 80306 Telephone: (303) 443-6151 Attorneys for Objector JVRC, Inc.

Filad in the office of the Clerk, District Court Water Division No. 2, State of Colorado

OCT 29 1986

Priscieles Spress Clork

EXHIBIT A

The Subject Lands consist of the following:


The W1/2 W1/2 E1/2 and the E1/2 W1/2 and the SW1/4 SW1/4 of Section 27; the El/2 SEl/4 and that portion of the SW1/4 SEl/4 lying South and East of the County Road across said premises, both in Section 28; that portion of the SE1/4 SE1/4 of Section 32 lying South and East of said County Road, and that portion of the NEL/4 SEL/4 of said Section 32, lying South and East of said County Road; the El/2 and the El/2 SW1/4 and the SW1/4 SW1/4 of Section 33, and all that part of the NW1/4 of said Section 33 lying South and East of the said County Road across said premises, except that portion of the SW1/4 NW1/4 of said Section 33 lying South and East of said County Road containing approximately 10 acres deeded to Colorado Interstate Gas Company by Warranty Deed recorded in Book 1173 at Page 359 of the El Paso County Records; and the W1/2 E1/2 and the W1/2 of Section 34, all in Township 12 South, Range 65 West of the 6th P.M., located in El Paso County, Colorado.

> Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado

> > OCT 29 1986

Riscilles Adurers

Clerk



SCALE 1:24000

LOCATION MAP

Filed in the office of the Clerk, District Court Water Division No. 2, State of Colorado OCT 29 1986 Priscieles Silvers Clork

FIGURE 1

that black birth and count

DISTRICT COURT, WATER DIVISION NO. 1, COLORADO

SENOV 9 P2: DB

Case No. 85CW445

RULING AND DECREE OF THE WATER COURT

ASTORNALLING COUNT ASTORNALLING COUNT

CONCERNING THE APPLICATION FOR WATER RIGHTS OF ED PENDLETON AND BEVERLY C. PENDLETON

IN THE NONTRIBUTARY DENVER, ARAPAHOE, AND LARAMIE-FOX HILLS AQUIFERS AND THE NOT NONTRIBUTARY UPPER DAWSON AQUIFER, in El Paso County.

THIS CLAIM, having been originally filed with the Water Division No. 1 Water Clerk on December 31, 1985, all matters contained in the application having been reviewed, and testimony having been taken where such testimony is necessary, and such corrections made as are indicated by the evidence presented herein, IT IS HEREBY THE RULING OF THE WATER REFEREE:

FINDINGS OF FACT

1. Name, Address, and Telephone Number of Applicants:

Ed Pendleton and Beverly C. Pendleton c/o Mr. Merle McClung 8085 South Chester Street Englewood, Colorado 80012 (303) 790-1776

Applicants shall be referred to hereafter singularly as the Applicant.

2. <u>History of Case:</u>

The Applicant is represented by Saunders, Snyder, Ross & Dickson, P.C. (William B. Tourtillott and Robert E. Schween). The original application for underground water rights from nontributary sources was filed with this Court on December 31, 1985. An amended application for underground water rights from nontributary and not nontributary sources was filed with this Court on March 31, 1987 and published in the March 1987 Water Resume for Water Division No. 1. A timely statement of opposition was filed to the amended application by the City of Colorado Springs (Gregory L. Johnson). No other statements of opposition or motions to intervene have been filed, and the period for filing of statements of opposition has expired.

3. Subject Matter Jurisdiction:

1.1

Timely and adequate notice of the pendency of these proceedings has been given in the manner required by law. The Water Court has jurisdiction over the subject matter of these proceedings and over all who have standing to appear as parties, whether they have appeared or not.

4. Aquifer and Location of Ground Water:

In this proceeding, Applicant seeks a ruling and decree for rights to all ground water recoverable from the nontributary Denver, Arapahoe, and Laramie-Fox Hills aquifers and the not nontributary Upper Dawson aquifer underlying Applicant's property in El Paso County, Colorado. The Applicant's property, which is subject to this case, is described as follows: all of Section 16; the El/2 SW1/4 and the SE1/4 of Section 17; the El/2 and the El/2 W1/2 of Section 20; the NE 1/4 and the W1/2, except for the east 30 feet of the SW1/4, of Section 21, all in Township 11 South, Range 65 West of the 6th P.M., consisting of 1840 acres, more or less. Applicant is the owner of the ground water rights underlying the above-described land and no part of such land lies within a designated ground water basin. A general location map of the property is attached hereto as Exhibit "A."

5. Specific Wells Claimed:

The legal descriptions of the wells to be constructed under this decree are as follows:

- A. Upper Dawson Aquifer
 - (1) Bar X DA-1: SW1/4 NE1/4, Section 16, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,200 feet from the East Section line and 2,000 feet from the North section line of said Section 16.
 - (2) Bar X DA-2: NE1/4 SE1/4, Section 17, Township 11 South, Range 65 Nest of the 6th P.M., at a point which is 500 feet from the East Section line and 1,500 feet from the South section line of said Section 17.
 - (3) Bar X DA-3: NW1/4 NE1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,200 feet from the East Section line and 800 feet from the North section line of said Section 21.

7260S

(4) Bar X DA-4: NW1/4 SW1/4, Section 21, Township 12 South, Range 65 West of the 6th P.M., at a point which is 400 feet from the West Section line and 1,500 feet from the South section line of said Section 21.

- ---

B. Denver Aquifer

S.,

- (1) Bar X D-1: SW1/4 NE1/4, Section 16, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,150 feet from the East Section line and 2,000 feet from the North section line of said Section 16.
- (2) Bar X D-2: NE1/4 SE1/4, Section 17, Township 11 South, Range 65 West of the 6th P.M., at a point which is 450 feet from the East Section line and 1,500 feet from the South section line of said Section 17.
- (3) Bar X D-3: NW1/4 NE1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,150 feet from the East Section line and 800 feet from the North section line of said Section 21.
- (4) Bar X D-4: NW1/4 SW1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 450 feet from the West Section line and 1,500 feet from the South section line of said Section 21.
- C. <u>Arapahoe Aquifer</u>
 - (1) Bar X A-1: SW1/4 NE1/4, Section 16, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,200 feet from the East Section line and 2,050 feet from the North section line of said Section 16.
 - (2) Bar X A-2: NE1/4 SE1/4, Section 17, Township 11 South, Range 65 West of the 6th P.M., at a point which is 500 feet from the East Section line and 1,450 feet from the South section line of said Section 17.

- (3) Bar X A-3: NW1/4 NE1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,200 feet from the East Section line and 850 feet from the North section line of said Section 21.
- (4) Bar X A-4: NW1/4 SW1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 400 feet from the West Section line and 1,450 feet from the South section line of said Section 21.
- (5) Bar X A-5: SW1/4 NE1/4, Section 20, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,500 feet from the East Section line and 1,500 feet from the North section line of said Section 20.
- D. Laramie-Fox Hills Aquifer
 - (1) Bar X LFH-1: SW1/4 NE1/4, Section 16, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,150 feet from the East Section line and 2,050 feet from the North section line of said Section 16.
 - (2) Bar X LFH-2: NE1/4 SE1/4, Section 17, Township ll South, Range 65 West of the 6th P.M., at a point which is 450 feet from the East Section line and 1,450 feet from the South section line of said Section 17.
 - (3) Bar X LFH-3: NW1/4 NE1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 2,150 feet from the East Section line and 850 feet from the North section line of said Section 21.
 - (4) Bar X LFH-4: NW1/4 SW1/4, Section 21, Township 11 South, Range 65 West of the 6th P.M., at a point which is 450 feet from the West Section line and 1,450 feet from the South section line of said Section 21.

7260S

6. Well Permits:

Applicant will make application for permits for each Α. well described herein at such time as Applicant is ready to construct each well or series of wells.

В. The State Engineer shall consider the rights granted herein as valid. Because a unified municipal water supply system is planned to serve this property, the system will be constructed pursuant to a phased development program over a considerable period of time. Each well will be drilled and completed as it is needed pursuant to such phased development program. Accordingly, the Court determines that if Applicant fails to construct any of said wells within the period of time specified in the corresponding well permits, it may reapply and the State Engineer shall promptly reissue that well permit for the amount of water determined herein with burdens no more restrictive than found herein.

7. Average Annual Amounts of Withdrawal Available:

Not Nontributary Upper Dawson Aquifer:

Pursuant to the Denver Basin Rules, the ground water in the Upper Dawson aguifer underlying Applicant's property is classified as not nontributary ground water. The hydrologic values and the average annual amount available for withdrawal

Sand	Specific	Average Annual Amt.
<u>Thickness</u>	Yield	in Acre-Feet
490 feet	.20%	1803

Nontributary Denver, Arapahoe, and Laramie-Fox Hills в. Aquifers:

Pursuant to the Denver Basin Rules, the ground water in the Denver, Arapahoe, and Laramie-Fox Hills aguifers underlying Applicant's property is classified as nontributary ground water, as defined in § 37-90-103(10.5), C.R.S. The hydrologic values and the average annual amounts available for withdrawal from the Denver, Arapahoe, and Laramie-Fox Hills aquifers are as follows:

<u>Aquifer</u>	<u>Acreage</u>	Sand <u>Thickness</u>	Specific Yield	Average Annual Amt. in Acre-Feet
Denver	1840	435 feet	.17%	1360
Arapahoe	1840	260 feet	.17%	813
Laramie- Fox Hills	1840	200 feet	.15%	552

C. The above values and amounts are consistent with the Determinations of Facts issued by the Office of the State Engineer (April 29, 1986).

8. Nominal Pumping Rates and Estimated Average Well Depths:

Aquifer	Combined	lndividual	Well Depth
	<u>Rate</u>	Well Rate	(Average)
Upper Dawson	1500 gpm (3.3cfs)	375 gpm (.84cfs)	1,040 feet
Denver	1200 gpm (2.6cfs)	300 gpm (.66cfs)	1,930 feet
Arapahoe	750 gpm (1.6cfs)	150 gpm (.33cfs)	2,450 feet
Laramie-Fox Hills	480 gpm (1.0cfs)	120 gpm (.26cfs)	2,950 feet

9. Final Average Annual Amounts of Withdrawal:

A. Final determinations of the applicable average specific yields, saturated sand thicknesses, and resulting average annual amounts available to Applicant from each aquifer will be made pursuant to the retained jurisdiction of this Court, as described in paragraph 21 hereinbelow. In the event this decree is not reopened for a further quantitative determination, the findings herein are final and controlling.

B. The allowed annual amount of ground water which may be withdrawn from such aquifers through the wells specified above and any additional wells, pursuant to § 37-90-137(10), C.R.S. (1985 Supp.), may exceed the average annual amount of withdrawal, as long as the total volume of water withdrawn through such wells and any additional wells therefor subsequent to the date of this decree does not exceed the product of the number of years since the date of the issuance of the well permits or the date of this decree, whichever is earliest in time, multiplied by the average annual amount of withdrawal, as specified above or as determined pursuant to the retained jurisdiction of the Court.

10. <u>Source of Ground Water; Limitations on Consumption;</u> <u>Replacement Obligations and Requirements:</u>

A. The ground water to be withdrawn from the Denver, Arapahoe, and Laramie-Fox Hills aguifers is "nontributary ground water" as defined in § 37-90-103(10.5), C.R.S. (1985 Supp.), and in the Denver Basin Rules, the withdrawal of which will not, within 100 years, deplete the flow of a natural stream, including a natural stream as defined in §§ 37-82-101(2) and 37-92-102(1)(b), C.R.S., at an annual rate greater than 1/10 of 1% of the annual rate of withdrawal. The ground water to be withdrawn from the Upper Dawson aguifer is "not nontributary ground water" as described in the Denver Basin Rules, 2 C.C.R. 402-6, Rule 5A.

B. Applicant may not consume more than 98% of the annual quantity of water withdrawn from the nontributary Denver, Arapahoe, and Laramie-Fox Hills aquifers. The relinquishment of 2% of the annual amount of water withdrawn to the stream system, as required by the Denver Basin Rules effective January 1, 1986, may be satisfied by any method selected by the Applicant and satisfactory to the State Engineer, so long as Applicant can demonstrate that an amount equal to 2% of such withdrawals (by volume) has been relinquished to the stream system.

C. The ground water to be withdrawn from the Upper Dawson aquifer is classified as not nontributary, requiring as a condition precedent to use that Applicant obtain a judicially approved augmentation plan for the replacement of depletions to the affected stream system. Pursuant to the statutory requirement at § 37-90-137(9)(c), C.R.S. (1985 Supp.), the amount of the replacement must be the actual depletive effect caused by withdrawal of the resource to the extent necessary to prevent injury.

11. No Material Injury:

There is unappropriated ground water available for withdrawal from each aquifer beneath the land described herein, and the vested water rights of others will not be materially injured by such withdrawals as described hereby. The minimum useful life of each of the subject aquifers is at least 100 years, assuming no substantial artificial recharge within 100 years. No material injury to vested water rights of others will result from the issuance of permits for the subject wells or the exercise of the rights and limitations specified in this decree therefor.

12. Additional Wells and Well Fields:

A. The Applicant proposes to build a unified municipal water system over the period of many years and will construct its wells as required by development. Any well drilled within 200 feet of a decreed location will be deemed to be constructed at the decreed well location pursuant to the permit and this decree.

B. In addition to the wells described in paragraph 5 above, Applicant may construct additional and replacement wells in order to maintain levels of production, to meet municipal water supply systems demands, or to recover the entire amount of ground water in the subject aquifers underlying the subject property, as described herein. As additional wells are planned, applications shall be filed in accordance with § 37-90-137(10), C.R.S. (1985 Supp.).

C. So long as allowed annual amounts are not exceeded, the pumping rates for the wells may exceed the pumping rates specified herein in order to meet municipal water system supply requirements or to produce the full acre foot allocation of water from each aquifer. Two or more wells constructed into the same aquifer shall be considered a well field. In effecting production of water from such well field, Applicant may produce the entire amount which may be produced hereunder from the particular aquifer through any combination of wells within the well field for that particular aquifer.

D. In considering applications for permits for additional wells to withdraw the ground water which is the subject of this decree, the State Engineer shall be bound by this decree and shall issue said permits in accordance with provisions of § 37-90-137(4), C.R.S. (1985 Supp.). Applicant shall not be required to submit any additional proof or evidence of matters finally determined herein when making application for permits for wells to withdraw the water which is the subject of this decree, except that the State Engineer may require revised land ownership or consent to use affidavits.

E. In the event that the allowed average annual amounts decreed herein are adjusted pursuant to the retained jurisdiction of the Court, any existing permit(s) for any well(s) decreed herein shall be amended to reflect such adjusted average annual amounts. New permits for any wells herein shall likewise reflect any such adjustment of the average annual amounts decreed herein.

13. Proposed Uses of Water:

The water withdrawn from any well may be used, reused, and successively used and otherwise disposed of for all municipal purposes including domestic, industrial, commercial, irrigation, stock watering, recreational, fish and wildlife, fire protection and sanitary purposes subject to the provisions of paragraph 20 herein. This water will be produced for immediate application to said uses, for storage and subsequent application to said uses, for exchange purposes, for replacement of depletions resulting from the use of this ground water or of water from other sources, and for augmentation purposes. Moreover, Applicant may use return flows of this ground water to replace stream depletions under a plan for augmentation approved in compliance with applicable law.

14. Conditions:

For each well constructed pursuant to this decree, Applicant shall comply with the following conditions:

A. A totalizing flow meter shall be installed on the well discharge prior to diverting any water therefrom. Applicant shall keep accurate records of all diversions by the well, make any calculations necessary, and submit such records to the Water Division No. 1 Engineer annually.

B. The entire length of the open bore hole shall be geophysically surveyed prior to casing and copies of the geophysical log submitted to the Division of Water Resources. Applicant may provide a geophysical log from an adjacent well or test hole, pursuant to Rule 8F of the Statewide Rules and acceptable to the State Engineer, which fully penetrates the aquifer, in satisfaction of the above requirement.

C. The ground water production shall be limited to the specific aquifer for which the well was designed. Plain, unperforated casing must be installed and properly grouted to prevent withdrawal from or intermingling of water from zones other than those for which the well was designed.

D. Each well shall be permanently identified by its permit number, this Water Court Case Number, and the name of the producing aquifer on the above-ground portion of the well casing or on the pumphouse.

CONCLUSIONS OF LAW

15. The Water Court has jurisdiction over this proceeding pursuant to § 37-90-137(6), C.R.S. This Court concludes as a matter of law that the application herein is one contemplated by Section 37-90-137(4), C.R.S. The application for a decree law. confirming Applicant's right to withdraw and use all ground water from the named nontributary and not nontributary aquifers beneath its property as described herein pursuant to § 37-90-137(4), C.R.S. (1985 Supp.), should be granted, subject to the provisions of this decree. The nature and extent of the rights to nontributary and not nontributary ground water determined herein are defined by §§ 37-90-137(4) and 37-90-137(9), C.R.S. (1985 Supp.). The withdrawal of the ground water decreed herein in accordance with the terms of this decree will not result in material injury to vested water rights of others as a matter of law.

16. The rights to nontributary and not nontributary ground water determined herein shall not be administered in accordance with priority of appropriation. Such rights are not "conditional water rights" as defined by § 37-92-103(6), C.R.S. The provisions of § 37-92-301(4), C.R.S., requiring quadrennial findings of reasonable diligence are not applicable to the ground water rights determined herein. The determination of ground water rights herein need not include a date of initiation of the withdrawal project. See § 37-92-305(11), C.R.S. (1985 Supp.). Ground water herein which is not nontributary shall be administered only pursuant to §§ 37-90-137(4) and 37-90-137(9), C.R.S. (1985 Supp.).

17. Subject to paragraph 20, below, Applicant is entitled to permits to construct the wells described in paragraph 5 hereof which will withdraw nontributary and not nontributary ground water pursuant to § 37-90-137(4), C.R.S., and such additional wells as may be required in the future to withdraw such ground water pursuant to § 37-90-137(10), C.R.S. (1985 Supp.).

IT IS THEREFORE, ORDERED, ADJUDGED, AND DECREED THAT:

18. The Findings of Fact and Conclusions of Law are incorporated into this decree of the Water Court.

19. Right to Withdraw Nontributary Ground Water:

The Applicant may withdraw the nontributary ground water herein through the wells listed above at the locations listed above and in the average annual amounts and at the rates of flow specified therefor, subject to the limitations herein and the retained jurisdiction by this Court.

20. <u>Replacement Obligation for Use of Not Nontributary Ground</u> <u>Water Rights:</u>

By separate application, Applicant will seek a plan for augmentation of depletions associated with the withdrawal of Upper Dawson ground water decreed hereby. No such augmentation plan is sought in this case. Judicial approval of such a plan for augmentation is a condition precedent to withdrawal and use of this resource.

21. Retained Jurisdiction:

•••

A. The Court retains jurisdiction as necessary to adjust the average annual amounts of nontributary and not nontributary ground water available under the property to conform to actual local aquifer characteristics as determined from adequate information obtained from wells, pursuant to § 37-92-305(11), C.R.S. (1985 Supp.). Within 60 days after completion of any well decreed herein, or any test hole(s), Applicant or any successor in interest to these water rights shall obtain a geophysical log of said well(s) or test hole(s) and shall serve such log(s) upon the State Engineer and notify each of the parties who have appeared herein that copies of the log and well completion report, if the well is completed, are available for review.

B. At such time as adequate data are available and within four months of notice that the retained jurisdiction for such purpose has been invoked, the State Engineer shall use the information available to him to make a final determination of water rights finding. The State Engineer shall submit such finding to the Water Court and to the Applicant, and the Applicant shall serve a copy upon the other parties.

C. If no protest to such finding is made within 60 days, the Final Determination of Water Rights shall be incorporated into the decree by the Water Court. In the event of a protest, or in the event the State Engineer makes no determination within four months, such final determination shall be made by the Water Court after notice and hearing.

D. In the event Applicant fails to invoke retained jurisdiction, the State Engineer or any party hereto may do so. In the interim, the Court retains jurisdiction in this matter pursuant to § 37-92-305(11), C.R.S. (1985 Supp.).

RULING ENTERED this 9th day of November 1988.

ldna

Raymond S. Liesman Water Referee Water Division No. 1 State of Colorado

THE COURT DOTH FIND THAT NO PROTEST TO THE RULING OF THE REFEREE HAS BEEN FILED. THE FOREGOING RULING IS CONFIRMED AND APPROVED, AND IS HEREBY MADE THE JUDGMENT AND DECREE OF THIS COURT.

December 12, 1988 DATED:

22 Robert A. Behrman

Water Judge Water Division No. 1 State of Colorado

THE WATER RIGHT FOR Dowson Azulfer HAS DEEN MOD AR MAR 92-CW

APPROVED AS TO FORM AND CONTENT:

SAUNDERS, SNYDER, ROSS & DICKSON, P.C.

Date: 15 Oct. 1987

William B. Tourtillott, Jr., #184 By

William B. Tourtillott, Jr., #184 Robert E. Schween, #12923 707 17th Street Suite 3500 Denver, Colorado 80202 (303) 292-6600

ATTORNEYS FOR APPLICANT ED PENDLETON AND BEVERLY C. PENDLETON

ANDERSON, JOHNSON, & GIANUNZIO

By_

Gregory L. Johnson/ #448 Mark T. Pifher, #12629 104 S. Cascade Ave., Suite 204 P.O. Box 240 Colorado Springs, Colorado 80901-0240 (303) 632-3545


ATTORNEYS FOR OBJECTOR CITY OF COLORADO SPRINGS

Date: 10-15-87

EXHIBIT A TO RULING AND DECREE CASE NO. 85CW445

€¹⁰ τ

R65W



T11S

£ [*]	RES	Filed in the office whe Clerk, District Coort Water Division Na 2, State of Coheredo
DISTRICT COURT, WATER DIVISION Case No. 85CW131	No. 2. COLOBADO	MAY 18 1988
DECREE OF THE WATER COURT	SAU	Clerk
	ROSS & DICKSUN	

CONCERNING THE APPLICATION FOR WATER RIGHTS OF PENDLETON LAND AND EXPLORATION, INC.

IN THE NONTRIBUTARY DENVER, ARAPAHOE, AND LARAMIE-FOX HILLS AQUIFERS AND THE NOT NONTRIBUTARY DAWSON, DENVER, AND ARAPAHOE AQUIFERS, in El Paso County.

THIS CLAIM, having been originally filed with the Water Division No. 2 Water Clerk on December 31, 1985, all matters contained in the application having been reviewed, and testimony having been taken where such testimony is necessary, and such corrections made as are indicated by the evidence presented herein, the Court makes the following:

FINDINGS OF FACT

1. Name, Address, and Telephone Number of Applicant:

Pendleton Land and Exploration, Inc. c/o Mr. Merle McClung 8085 S. Chester St. Englewood, Colorado 80012 (303) 790-1776

2. <u>History of Case</u>:

The Applicant is represented by Saunders, Snyder, Ross & Dickson, P.C. (William B. Tourtillott and Robert E. Schween). The original application for underground water rights from nontributary sources was filed with this Court on December 31, An amended application for underground water rights from 1985. nontributary and not nontributary sources was filed with this Court on April 24, 1987 and published in the May 1987 Water Resume for Water Division No. 2. Timely statements of opposition were filed to the original and amended application by the City of Colorado Springs (Gregory L. Johnson), JVRC, Inc. (Michael D. Shimmin), Upper District 10 Water Users Association (Gregory L. Johnson), and Black Forest Land Use Committee (Barbara Hosmer). No other statements of opposition or motions to intervene have been filed, and the period for filing of statements of opposition has expired

3. Subject Matter Jurisdiction:

Ł

41

s,

Timely and adequate notice of the pendency of these proceedings has been given in the manner required by law. The Water Court has jurisdiction over the subject matter of these proceedings and over all who have standing to appear as parties, whether they have appeared or not.

4. Aquifers and Location of Ground Water:

A. In this proceeding, Applicant seeks a decree for rights to all ground water recoverable from the nontributary Denver, Arapahoe, and Laramie-Fox Hills aquifers and the not nontributary Dawson, Denver, and Arapahoe aquifers underlying Applicant's property in El Paso County, Colorado.

B. The ground water rights are linked to different portions of Applicant's property as generally described below:

1. <u>Dawson Aquifer</u>

Applicant will withdraw not nontributary ground water from the Dawson aquifer underlying approximately 2280 acres of property as more particularly described on Exhibit "A" attached hereto and made a part hereof. A general location map of the property is attached as Exhibit "B."

2. <u>Denver Aquifer</u>

Applicant will withdraw not nontributary ground water from the Denver aquifer underlying approximately 2080 acres of property and nontributary ground water from the Denver aquifer underlying approximately 200 acres of property as more particularly described on Exhibit "C" attached hereto and made a part hereof. A general location map of the property designated as not nontributary and nontributary in the Denver aquifer is attached as Exhibit "D."

3. Arapahoe Aquifer

Applicant will withdraw not nontributary ground water from the Arapahoe aquifer underlying approximately 634 acres of property and nontributary ground water from the Arapahoe aquifer underlying approximately 1646 acres of property as more particularly described on Exhibit "E" attached hereto and made a part hereof. A general location map of the property designated as not nontributary and nontributary in the Arapahoe aquifer is attached as Exhibit "F "

4. Laramie-Fox Hills Aquifer

Applicant will withdraw nontributary ground water from the Laramie-Fox Hills aquifer underlying approximately 2280 acres of property as more particularly described on Exhibit "A." A general location map of the property is attached as Exhibit "B."

C. Applicant is the owner of the ground water rights underlying the above-described lands and no part of such lands lies within a designated ground water basin.

5. Specific Wells Claimed:

٤,

۲

£.

The legal descriptions of the wells to be constructed under this decree are as follows:

A. <u>Dawson Aquifer</u>

- (1) West DA-1: SW1/4 NW1/4, Section 26, Township 11 South, Range 66 West of the 6th P.M., at a point which is 1,000 feet from the West Section line and 2,000 feet from the North section line of said Section 26.
- (2) West DA-2: SW1/4 NW1/4, Section 25, Township 11 South, Range 66 West of the 6th P.M., at a point which is 300 feet from the West Section line and 1,500 feet from the North section line of said Section 25.
- (3) West DA-3: NW1/4 NW1/4, Section 35, Township 11 South, Range 66 West of the 6th P.M., at a point which is 200 feet from the West Section line and 1,000 feet from the North section line of said Section 35.
- (4) West DA-4: SE1/4 SE1/4, Section 26, Township 11 South, Range 66 West of the 6th P.M., at a point which is 1,000 feet from the East Section line and 500 feet from the South section line of said Section 26.
- (5) West DA-5: NW1/4 SE1/4, Section 35, Township 11 South, Range 66 West of the 6th P.M., at a point which is 2,000 feet from the East Section line and 1,500 feet from the South section line of said Section 35.

- (6) West DA-6: NE1/4 NE1/4, Section 3, Township 12 South, Range 66 West of the 6th P.M., at a point which is 1,200 feet from the East Section line and 300 feet from the North section line of said Section 3.
- B. <u>Denver Aquifer</u>

L

- (1) West D-1: SW1/4 NW1/4, Section 26, Township 11 South, Range 66 West of the 6th P.M., at a point which is 1,050 feet from the West Section line and 2,000 feet from the North section line of said Section 26.
- (2) West D-2: SW1/4 NW1/4, section 25, Township 11 South, Range 66 West of the 6th P M., at a point which is 350 feet from the West line and 1500 feet from the North line of said Section 25.
- (3) West D-3: NW1/4 NW1/4, Section 35, Township 11 South, Range 66 West of the 6th P.M., at a point which is 250 feet from the West Section line and 1,000 feet from the North section line of said Section 35.
- (4) West D-4: SE1/4 SE1/4, Section 26, Township 11 South, Range 66 West of the 6th P.M., at a point which is 950 feet from the East Section line and 500 feet from the South section line of said Section 26.
- (5) West D-5: NW1/4 SE1/4, Section 35, Township 11 South, Range 66 West of the 6th P.M., at a point which is 1,950 feet from the East Section line and 1,500 feet from the South section line of said Section 35.
- (6) West D-6: NE1/4 NE1/4, Section 3, Township 12 South, Range 66 West of the 6th P.M., at a point which is 1,150 feet from the East Section line and 300 feet from the North section line of said Section 3.
- C. Arapahoe Aquifer
 - (1) West A-1. SW1/4 NW1/4, Section 26, Township ll South, Range 66 West of the 6th P M, at a point which is 1,000 feet from the West Section line and 2,050 feet from the North section line of said Section 26.

72705

- (2) West A-2: SW1/4 NW1/4. Section 25. Township 11 South. Range 66 West of the 6th P.M., at a point which is 300 feet from the West Section line and 1,550 feet from the North section line of said Section 25.
- (3) West A-3: NW1/4 NW1/4, Section 35, Township 11 South, Range 66 West of the 6th P.M., at a point which is 200 feet from the West Section line and 1.050 feet from the North section line of said Section 35.
- (4) West A-4: SE1/4 SE1/4. Section 26. Township 11 South. Range 66 West of the 6th P.M., at a point which is 1,000 feet from the East Section line and 450 feet from the South section line of said Section 26.
- (5) West A-5: NW1/4 SE1/4, Section 35, Township 11 South, Range 66 West of the 6th P.M., at a point which is 2,000 feet from the East Section line and 1,450 feet from the South section line of said Section 35.
- (6) West A-6: NE1/4 NE1/4. Section 3. Township 12 South. Range 66 West of the 6th P.M., at a point which is 1,200 feet from the East Section line and 350 feet from the North section line of said Section 3.

D. Laramie-Fox Hills Aquifer

- (1) West LFH-1: SW1/4 NW1/4, Section 26, Township 11 South, Range 66 West of the 6th P.M., at a point which is 1,050 feet from the West Section line and 2,050 feet from the North section line of said Section 26.
- (2) West LFH-3: NW1/4 NW1/4. Section 35. Township 11 South, Range 66 West of the 6th P.M., at a point which is 250 feet from the West Section line and 1,050 feet from the North section line of said Section 35.
- (3) West LFH 4: SE1/4 SE1/4, Section 26, Township 11 South, Range 66 West of the 6th P.M., at a point which is 950 feet from the East Section line and 450 feet from the South section line of said Section 26

ſ

1

L

(4) West LFH-6: NE1/4 NE1/4. Section 3. Township 12 South. Range 66 West of the 6th P M., at a point which is 1,150 feet from the East Section line and 350 feet from the North section line of said Section 3

6. <u>Well Permits</u>:

.

A. Applicant will make application for permits for each well described herein at such time as Applicant is ready to construct each well or series of wells.

B. The State Engineer shall consider the rights granted herein as valid. Because a unified municipal water supply system is planned to serve this property, the system will be constructed pursuant to a phased development program over a considerable period of time. Each well will be drilled and completed as it is needed pursuant to such phased development program. Accordingly, the Court determines that if Applicant fails to construct any of said wells within the period of time specified in the corresponding well permits, it may reapply and the State Engineer shall promptly reissue that well permit for the amount of water determined herein with burdens no more restrictive than found herein.

7. Average Annual Amounts of Withdrawal Available:

A. Not Nontributary Dawson, Denver, and Arapahoe Aquifers:

Pursuant to the Denver Basin Rules, the ground water in the Dawson, Denver, and Arapahoe aquifers underlying all or part of Applicant's property, as described in Paragraph 4 herein. is classified as not nontributary ground water. The hydrologic values and the average annual amounts available for withdrawal from the not nontributary Dawson, Denver, and Arapahoe aquifers are as follows:

<u>Aquifer</u>	<u>Acreage</u>	Sand <u>Thıckness</u>	Specific <u>Yield</u>	Ave. Ann. Amt. in Acre-Feet
Dawson	2280	375 feet	20%	1710
Denver	2080	550 feet	17%	1945
Arapahoe	634	220 feet	17%	237

B. <u>Nontributary Denver, Arapahoe, and Laramie-Fox Hills</u> <u>Aquifers</u>:

Pursuant to the Denver Basin Rules, the ground water in the Denver, Arapahoe, and Laramie-Fox Hills aquifers underlying all or part of Applicant's property, as described in Paragraph 4 herein, is classified as nontributary ground water, pursuant to § 37-90-137(9)(c), C.R.S. The hydrologic values and the average annual amounts available for withdrawal from the nontributary Denver, Arapahoe, and Laramie-Fox Hills aquifers are as follows:

<u>Aquifer</u>	<u>Acreage</u>	Sand <u>Thickness</u>	Specific Yield	Ave. Ann. Amt. <u>IN Acre-Feet</u>
Denver	200	550 feet	17%	187
Arapahoe	1646	220 feet	17%	616
Laramie- Fox Hills	2280	200 feet	15%	684

C. The above values and amounts are consistent with the Findings of the State Engineer issued on March 25, 1986, and supplemented on November 5, 1987.

8. <u>Final and Interim Average Annual Amounts of Withdrawal; and Allowed Amounts of Withdrawal Exceeding Average Annual Amounts:</u>

A. Final determinations of the applicable average saturated sand thicknesses and resulting average annual amounts available to Applicant from each aquifer will be made pursuant to the retained jurisdiction of this Court, as described in paragraph 18 hereinbelow. In the event this decree is not reopened for a further quantitative determination, the findings herein are final and controlling.

B. The allowed annual amount of ground water which may be withdrawn from such aquifers through the wells specified above and any additional wells, pursuant to § 37-90-137(10), C.R.S. (1987 Supp.), may exceed the average annual amount of withdrawal, as long as the total volume of water withdrawn through such wells and any additional wells therefor subsequent to the date of this decree does not exceed the product of the number of years since

t.

the date of the issuance of the well permits or the date of this decree, whichever is earliest in time, multiplied by the average annual amount of withdrawal, as specified above or as determined pursuant to the retained jurisdiction of the Court.

9. <u>Source of Ground Water; Limitations on Consumption;</u> <u>Replacement Obligations and Requirements</u>:

A. The ground water to be withdrawn from the Laramie-Fox Hills aquifer and the described portions of the Denver and Arapahoe aquifers is "nontributary ground water" as defined in § 37-90-103(10.5), C.R.S. (1987 Supp.), and in the Denver Basin Rules, the withdrawal of which will not, within 100 years, deplete the flow of a natural stream, including a natural stream as defined in §§ 37-82-101(2) and 37-92-102(1)(b), C.R.S., at an annual rate greater than 1/10 of 1% of the annual rate of withdrawal.

B. Applicant may not consume more than 98% of the annual quantity of water withdrawn from the nontributary Denver, Arapahoe, and Laramie-Fox Hills aquifers. The relinquishment of 2% of the annual amount of water withdrawn to the stream system, as required by the Denver Basin Rules effective January 1, 1986, may be satisfied by any method selected by the Applicant and satisfactory to the State Engineer, so long as Applicant can demonstrate that an amount equal to 2% of such withdrawals (by volume) has been relinquished to the stream system.

C. Withdrawal of ground water from the Dawson aquifer and the described portions of the Denver and Arapahoe aquifers <u>will</u>, within 100 years, deplete the flow of a natural stream at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal therefrom. Such ground water is not nontributary and requires, as a condition precedent to use, that Applicant obtain a judicially approved augmentation plan for the replacement of depletions to the affected stream system, pursuant to the statutory requirements in effect at such time that the augmentation plan is prosecuted.

D. There is unappropriated ground water available for withdrawal from each aquifer beneath the land described herein, and the vested water rights of others will not be materially injured by such withdrawals as described hereby. The minimum useful life of each of the subject aquifers is at least 100 years, assuming no substantial artificial recharge within 100 years. No

1.

material injury to vested water rights of others will result from the issuance of permits for the subject wells or the exercise of the rights and limitations specified in this decree therefor.

10. Additional Wells and Well Fields:

A. The Applicant proposes to build a unified municipal water system over the period of many years and will construct its wells as required by development. Any well drilled within 200 feet of a decreed location will be deemed to be constructed at the decreed well location pursuant to the permit and this decree.

B. In addition to the wells described in paragraph 5 above, Applicant may construct additional and replacement wells in order to maintain levels of production, to meet municipal water supply systems demands or to recover the entire amount of ground water in the subject aquifers underlying the subject property, as described herein. As additional wells are planned, applications shall be filed in accordance with § 37-90-137(10), C.R.S. (1987 Supp.).

C. The pumping rates for the wells may exceed the pumping rates specified in the State Engineer's Findings in order to meet municipal water supply requirements or to produce the full acre foot allocation of water from each aquifer. Two or more wells constructed into the same aquifer shall be considered a well field. Applicant may produce the entire amount which may be produced hereunder from the particular aquifer through any combination of wells within the well field for that particular aquifer; except that wells constructed in the land area overlying not nontributary ground water may produce only such not nontributary ground water. Moreover, Applicant's augmentation plan will have to separately account for nontributary and not nontributary ground water withdrawals from each aquifer.

D. In considering applications for permits for additional wells to withdraw the ground water which is the subject of this decree, the State Engineer shall be bound by this decree and shall issue said permits in accordance with provisions of § 37-90-137(10), C.R.S. (1987 Supp.). Applicant shall not be required to submit any additional proof or evidence of matters finally determined herein when making application for permits for wells to withdraw the water which is the subject of this decree, except that the State Engineer may require revised land ownership or consent to use affidavits and may require such additional information as specified in the Statewide Nontributary Ground Water Rules, 2 CCR 402-7. E. In the event that the allowed average annual amounts decreed herein are adjusted pursuant to the retained jurisdiction of the Court, any existing permit(s) for any well(s) decreed herein shall be amended to reflect such adjusted average annual amounts. New permits for any wells herein shall likewise reflect any such adjustment of the average annual amounts decreed herein.

11. Proposed Uses of Water:

The water withdrawn from any well may be used, reused, and successively used and otherwise disposed of for all municipal purposes including domestic, industrial, commercial, irrigation, stock watering, recreational, fish and wildlife, fire protection and sanitary purposes subject to the provisions of paragraph 20 herein. This water will be produced for immediate application to said uses, for storage and subsequent application to said uses, for exchange purposes, for replacement of depletions resulting from the use of this ground water or of water from other sources, and for augmentation purposes. Moreover, Applicant may use return flows of this ground water to replace stream depletions under a plan for augmentation approved in compliance with applicable law.

12. <u>Conditions</u>:

1

For each well constructed pursuant to this decree, Applicant shall comply with the following conditions:

A. A totalizing flow meter shall be installed on the well discharge prior to diverting any water therefrom. Applicant shall keep accurate records of all diversions by the well, make any calculations necessary, and submit such records to the Water Division No. 2 Engineer annually.

B. The entire length of the open bore hole shall be geophysically surveyed prior to casing and copies of the geophysical log submitted to the Division of Water Resources. Applicant may provide a geophysical log from an adjacent well or test hole, pursuant to Rule 9A of the Statewide Rules and acceptable to the State Engineer, which fully penetrates the aquifer, in satisfaction of the above requirement.

C. The ground water production shall be limited to the specific aquifer for which the well was designed. Plain, unperforated casing must be installed and properly grouted to prevent withdrawal from or intermingling of water from zones other than those for which the well was designed. D. Each well shall be permanently identified by its permit number, this Water Court Case Number, and the name of the producing aguifer on the above-ground portion of the well casing or on the pumphouse.

CONCLUSIONS OF LAW

The Water Court has jurisdiction over this proceeding 13. pursuant to § 37-90-137(6), C.R.S. This Court concludes as a matter of law that the application herein is one contemplated by Section 37-90-137(4), C.R.S. The application for a decree law. confirming Applicant's right to withdraw and use all ground water from the named nontributary and not nontributary aquifers beneath its property as described herein pursuant to § 37-90-137(4), C.R.S. (1987 Supp.), should be granted, subject to the provisions of this decree. The nature and extent of the rights to nontributary and not nontributary ground water determined herein are defined by §§ 37-90-137(4) and 37-90-137(9), C.R.S. (1987 The withdrawal of the ground water decreed herein in Supp.). accordance with the terms of this decree will not result in material injury to vested water rights of others.

14. The rights to nontributary and not nontributary ground water determined herein shall not be administered in accordance with priority of appropriation. Such rights are not "conditional water rights" as defined by § 37-92-103(6), C.R.S. The provisions of § 37-92-301(4), C.R.S., requiring quadrennial findings of reasonable diligence are not applicable to the ground water rights determined herein. The determination of ground water rights herein need not include a date of initiation of the withdrawal project. See § 37-92-305(11), C.R.S. (1987 Supp.). Ground water herein which is not nontributary shall be administered only pursuant to §§ 37-90-137(4) and 37-90-137(9), C.R.S. (1987 Supp.).

IT IS THEREFORE, ORDERED, ADJUDGED, AND DECREED THAT:

15. The Findings of Fact and Conclusions of Law are incorporated into this decree of the Water Court.

16. Right to Withdraw Nontributary Ground Water:

The Applicant may withdraw the nontributary ground water herein through the wells listed above at the locations listed above and in the average annual amounts and at the rates of flow specified therefor, subject to the limitations herein and the retained jurisdiction by this Court.

.

17. <u>Replacement Obligation for Use of Not Nontributary Ground</u> Water Rights:

By separate application, Applicant will seek a plan for augmentation of depletions associated with the withdrawal of not nontributary Dawson, Denver, and Arapahoe ground water as described in Paragraph 7A herein and decreed hereby. No such augmentation plan is sought in this case. Judicial approval of such a plan for augmentation is a condition precedent to withdrawal and use of these resources.

18. <u>Retained Jurisdiction</u>:

A. The Court retains jurisdiction as necessary to adjust the average annual amounts of nontributary and not nontributary ground water available under the property to conform to actual local aquifer characteristics as determined from adequate information obtained from wells, pursuant to § 37-92-305(11), C.R.S. (1987 Supp.). Within 60 days after completion of any well decreed herein, or any test hole(s), Applicant or any successor in interest to these water rights shall obtain a geophysical log of said well(s) or test hole(s) and shall serve such log(s) upon the State Engineer and notify each of the parties who have appeared herein that copies of the log and well completion report, if the well is completed, are available for review.

B. At such time as adequate data are available and within four months of notice that the retained jurisdiction for such purpose has been invoked, the State Engineer shall use the information available to him to make a final determination of water rights finding. The State Engineer shall submit such finding to the Water Court and to the Applicant, and the Applicant shall serve a copy upon the other parties.

C. If no protest to such finding is made within 60 days, the Final Determination of Water Rights shall be incorporated into the decree by the Water Court. In the event of a protest, or in the event the State Engineer makes no determination within four months, such final determination shall be made by the Water Court after notice and hearing.

D. In the event Applicant fails to invoke retained jurisdiction, the State Engineer or any party hereto may do so. In the interim, the Court retains jurisdiction in this matter pursuant to § 37-92-305(11), C.R.S. (1987 Supp.).

19. Upon obtaining an augmentation for the required replacement of not nontributary withdrawals, Applicant is entitled to permits

to construct the wells described in paragraph 5 hereof which will withdraw not nontributary ground water pursuant to § 37-90-137(4), C.R.S.. and such additional wells as may be required in the future to withdraw such ground water pursuant to § 37-90-137(10), C.R.S. (1985 Supp.). With the entry of this decree, Applicant is entitled to permits to construct such wells which will withdraw nontributary ground water.

DECREE ENTERED this 18 day of Mary 1988.

John R. Tracey Water Judge Water Division No. 2 State of Colorado

APPROVED AS TO FORM AND CONTENT:

SAUNDERS, SNYDER, ROSS & DICKSON, P.C.

Date: 8 FEB. 1988

By

William B. Tourtillott, Jr., #184 Robert E. Schween, #12923 707 17th Street Suite 3500 Denver, Colorado 80202 (303) 292-6600

ATTORNEYS FOR APPLICANT -PENDLETON LAND AND EXPLORATION, INC.

ANDERSON, JOHNSON, & GIANUNZIO

Date _____

Gregory L. Johnson, #448 Mark T. Pifher, #12629 104 S. Cascade Ave., Suite 204 P.O. Box 240 Colorado Springs, Colorado 80901-02 (303) 632-3545

ATTORNEYS FOR CITY OF COLORADO SPRINGS and UPPER DISTRICT 10 WATER USERS ASSOCIATION

VRANESH AND RAISCH

Mh By

Michael D. Shimmin, #9182 P.O. Box 871 Boulder, Colorado 80306 (303) 443-6151

ATTORNEYS FOR JVRC, INC.

By_

By_

Barbara Hosmer, Committee Member 11755 Timberland Court Colorado Springs, Colorado 80908 (303) 495-3948

REPRESENTATIVE OF BLACK FOREST LAND USE COMMITTEE

Date: Jan 4, 1988

Date.____

ANDERSON, JOHNSON, & GIANUNZIO

Date: Fil 11 1990

By

Gregory L. Johnson, #448 Mark T./Pifher, #12629 104 S. Cascade Ave., Suite 204 P.O. Box 240 Colorado Springs, Colorado 80901-02 (303) 632-3545

ATTORNEYS FOR CITY OF COLORADO SPRINGS and UPPER DISTRICT 10 WATER USERS ASSOCIATION

VRANESH AND RAISCH

Bv

Michael D. Shimmin, #9182 P.O. Box 871 Boulder, Colorado 80306 (303) 443-6151

ATTORNEYS FOR JVRC, INC.

Date:_____

Date: (Jan. 4, 1988

By_

Barbara Hosmer, Committee Member 11755 Timberland Court Colorado Springs, Colorado 80908 (303) 495-3948


REPRESENTATIVE OF BLACK FOREST LAND USE COMMITTEE

Wt. Rts. of Pendleton Land & Exploration Case No. 85CW131 Page 16 ANDERSON, JOHNSON, & GIANUNZIO Date By. Gregory L. Johnson, #448 Mark T. Pifher, #12629 104 S. Cascade Ave., Suite 204 P.O. Box 240 Colorado Springs, Colorado 80901-02 (303) 632-3545 ATTORNEYS FOR CITY OF COLORADO SPRINGS and UPPER DISTRICT 10 WATER USERS ASSOCIATION VRANESH AND RAISCH Date: By. Michael D. Shimmin, #9182 P.O. Box 871 Boulder, Colorado 80306 (303) 443-6151 ATTORNEYS FOR JVRC, INC. Date - 05-13-84 DOME By Mitica Barbara Hosmer, Committee Member 11755 Timberland Court Colorado Springs, Colorado 80908 (303) 495-3948

> REPRESENTATIVE OF BLACK FOREST LAND USE COMMITTEE

xc: Robert E. Schween Michael D. Shimmin Black Forest Land Use Committee, pro se Gregory L. Johnson Division Engineer State Engineer

72705



۹,

GENERAL LOCATION MAP

1. A.

A Carlos AN Carlos		
Colorado Department of Natural Resources	Colorado.gov	0
golologo dialod ol	C0101 811 0.90V	CONTRACT US
Whiter Regources		
Colorado's Well Permit Search		
THIS PAGE IS NOT THE ACTUAL PERMIT The information contained on this page is a summary of the permit file and may not reflect all details of the well permit. (Full Disclaimer)		
Permit Issued: Completion Clather United		
Receipt: 3628088A Division: 1		
Permit #: 1689-BD - Water District: 1		
Well Name / #: County: EL PASO Designated Basin: KIOWA-BIJOU Management District:		
Case Number:		
WDID;		
[-] Imaged Documents - Permit File		
Document Name Date Imaged Annotated Findings & Order for Determination 05/21/2009		
[-] Applicant/Contact		
Applicant/Contact Name		
MCCUNE GEORGE F & EVELYN 17480 MERIDIAN RD ELBERT, CO 80106-8916		
[-] Location Information		
Approved Well Location:		
Q40 Q160 Section Township Range PM Footage from Section Lines 24 11.05 65.0W Sixth		
24 11.0S 65.0W Slxth Northing (UTM y): 4325550.5 Easting (UTM x): 533176.3		
Location Accuracy: Spotted from quarters		
Subdivision Name		
Filing Block Lot		
Parcel ID: Acres in Tract: 900.52		
[-] Permit Detalls		
Date Issued: 06/25/2008 Date Expires: Uses (See Imaged Documents for more infomation)		
General Use(s): COMMERCIAL Aquifer(s): LARAMIE FOX HILLS DOMESTIC		
Special Use:		
Area which may be irrigated: Annual volume of appropriation:		
Statute:		
Cross Reference Permit(s): Permit Number Receipt		
Comments: DETER ISSUED		
[-] Construction/Usage Datalls		
Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Upp		
Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate		
[-] Application/Permit History		
Permit Issued 06/25/2008 Application Received 04/17/2008		
Disclaimer		
*The information contained on this page is a symmary of the permit file and may not reflect all details of the well permit. THIS PAGE IS NOT THE ACTUAL PERMIT.		
This page should not be used as a basis for any legal consideration, to determine the allowed uses of the well, to determine construction information, or to determine the terms and conditions under which the well can operate. The complete well permit file should be viewed to obtain details on the allowed uses and other relevant information. A complete copy of this file is available in the "Imaged Documents" section of this page, and can be viewed by opening all of the documents listed under that section (documents will open as pdf files).		
Note that all of the terms and conditions under which a well can operate, particularly for non-exempt wells, may not be specified on the well permit. Wells may also be subject to relevant statutes, rules and decrees. To learn		

more about well permitting in Colorado, please visit <u>DWR's Well Permitting Page</u>. If you have any questions about this well permit file, please contact the <u>DWR Ground Water Information Desk</u>

Copyright @ 2016 Colorado Division of Water Resources. All rights reserved.

Home | Contact Us | Help | Water Links | Colorado.gov | DNR | Privacy Policy | Transparency Online Project (TOP)

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR DETERMINATION OF WATER RIGHT TO ALLOW THE WITHDRAWAL OF GROUND WATER IN THE KIOWA-BIJOU DESIGNATED GROUND WATER BASIN

APPLICANT:	GEORGE F.	MCCUNE AND EVELYN MCCUN	E MARTINE	<u> </u>
AQUIFER:	LARAMIE-FO	X HILLS		201
DETERMINAT	TON NO .:	1689-BD		

In compliance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, George F. McCune and Evelyn McCune (hereinafter "applicant") submitted an application for determination of water right to allow the withdrawal of designated ground water from the Laramie-Fox Hills Aquifer.

FINDINGS

- 1. The application was received complete by the Colorado Ground Water Commission on April 17, 2008.
- 2. The applicant requests a determination of rights to designated ground water in the Laramie-Fox Hills Aquifer (hereinafter "aquifer") underlying 900.52 acres, generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6th Principal Meridian, in El Paso County. According to a signed statement dated April 17, 2008, the applicant owns the 900.52 acres of land, as further described in said affidavit which is attached hereto as Exhibit A, and claims control of the ground water in the aquifer underlying this land area.
- 3. The proposed annual amount of ground water to be allocated and withdrawn from the aquifer for intended beneficial uses is the maximum allowable amount.
- 4. The above described land area overlying the ground water claimed by the applicant is located within the boundaries of the Kiowa-Bijou Designated Ground Water Basin. The Colorado Ground Water Commission (hereinafter *Commission") has jurisdiction.
- 5. The applicant intends to apply the allocated ground water to the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The applicant's proposed place of use of the allocated ground water is the above described 900.52 acre land area.
- 6. The quantity of water in the aquifer underlying the 900.52 acres of land claimed by the applicant is 26300 acre-feet. This determination was based on the following as specified in the Designated Basin Rules:

a. The average specific yield of the saturated permeable material of the aquifer underlying the land under consideration that could yield a sufficient quantity of water that may be extracted and applied to beneficial use is 15 percent.

b. The average thickness of the saturated permeable material of the aquifer underlying the land under consideration that could yield a sufficient quantity of water that may be extracted and applied to beneficial use is 195 feet.

- 7. At this time, there is no substantial artificial recharge that would affect the aquifer within a one hundred year period.
- 8. Pursuant to Section 37-90-107(7), C.R.S., and in accordance with the Designated Basin Rules, the Commission shall allocate ground water in the aquifer based on ownership of the overlying land and an aquifer life of one hundred years. Therefore, the maximum allowed average annual amount of ground water in the aquifer that may be allocated for withdrawal pursuant to the data in the paragraphs above for the 900.52 acres of overlying land claimed by the applicant is 263 acre-feet.
- 9. A review of the records in the Office of the State Engineer has disclosed that none of the water in the aquifer underlying the land claimed by the applicant has been previously allocated or permitted for withdrawal.
- 10. Pursuant to Section 37-90-107(7)(c)(III), C.R.S., an approved determination of water right shall be considered a final determination of the amount of ground water so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 11. The ability of wells permitted to withdraw the authorized amount of water from this non-renewable aquifer may be less than the one hundred years upon which the amount of water in the aquifer is allocated, due to anticipated water level declines.
- 12. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of ground water from the aquifer underlying the land claimed by the applicant will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the ground water is nontributary ground water as defined in Rule 4.2.19 of the Designated Basin Rules. No more than 98% of the amount of ground water withdrawn annually shall be consumed, as required by the Designated Basin Rules.
- 13. In accordance with Section 37-90-107(7), C.R.S., upon Commission approval of a determination of water right, well permits for wells to withdraw the authorized amount of water from the aquifer shall be available upon application, subject to the conditions of this determination and the Designated Basin Rules and subject to approval by the Commission.
- 14. The Commission Staff has evaluated the application relying on the claims to control of the ground water in the aquifer made by the applicant.

- 15. In accordance with Sections 37-90-107(7) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on May 8 and May 15, 2008.
- 16. No objections to the determination of water right and proposed allocation of ground water were received within the time limit set by statute.
- 17. In order to prevent unreasonable impairment to the existing water rights of others within the Kiowa-Bijou Designated Ground Water Basin it is necessary to impose conditions on the determination of water right and proposed allocation of ground water. Under conditions as stated in the following Order, no unreasonable impairment of existing water rights will occur from approval of this determination of water right or from the issuance of well permits for wells to withdraw the authorized amount of allocated ground water from the aquifer.

ORDER

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, the Colorado Ground Water Commission orders that the application for determination of rights to designated ground water in the Laramie-Fox Hills Aquifer underlying 900.52 acres of land, generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6th Principal Meridian, is approved subject to the following conditions:

- 18. The allowed average annual amount of withdrawal of ground water from the aquifer shall not exceed 263 acre-feet. The allowed maximum annual amount of withdrawal may exceed the allowed average annual amount of withdrawal as long as the total volume of water withdrawn does not exceed the product of the number of years since the date of approval of this determination times the allowed average annual amount of withdrawal.
- 19. To conform to actual aquifer characteristics, the Commission may adjust the allowed average annual amount of ground water to be withdrawn from the aquifer based on analysis of geophysical logs or other site-specific data if such analysis indicates that the initial estimate of the volume of water in the aquifer was incorrect.
- 20. The applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- 21. No more than 98% of the ground water withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the water withdrawn is being consumed.
- 22. The use of ground water from this allocation shall be limited to the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The place of use shall be limited to the above described 900.52 acre land area.

Page 3

- 23. The applicant, or subsequent persons controlling this water right, shall record in the public records of the county in which the claimed overlying land is located notice of transfer of any portion of this water right to another within sixty days after the transfer, so that a title examination of the above described 900.52 acre land area, or any part thereof, shall reveal the changes affecting this water right. Such notice shall consist of a signed and dated deed which indicates the determination number, the aquifer, a description of the above described land area, the annual amount of ground water (acre-feet) transferred, name of the recipient, and the date of transfer.
- 24. Subject to the above conditions, well permits for wells to withdraw the allocated annual amount of water from the aquifer shall be available upon application subject to approval by the Commission and the following conditions:

a. The wells shall be located on the above described 900.52 acre overlying land area.

b. The wells must be constructed to withdraw water from only the Laramie-Fox Hills Aquifer. Upon application for a well permit to construct such a well, the estimated top and base of the aquifer at the proposed well location will be determined by the Commission and indicated on the approved well permit. Plain non-perforated casing must be installed, grouted and sealed to prevent diversion of ground water from other aquifers and the movement of ground water between aquifers.

c. The entire depth of each well must be geophysically logged <u>prior</u> to installing the casing as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

d. Each well shall be constructed within 200 feet of the location specified on the approved well permit, but must be more than 600 feet from any existing large-capacity well completed in the same aquifer.

e. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and maintained by the well owner and submitted to the Commission upon their request.

f. The well owner shall mark the well in a conspicuous place with the permit number and the name of the aquifer. The well owner shall take necessary means and precautions to preserve these markings.

25. A copy of this Findings and Order shall be recorded by the applicant in the public records of the county in which the claimed overlying land is located so that a title examination of the above described 900.52 acre overlying land area, or any part thereof, shall reveal the existence of this determination.

Page 4

Dated this 25th day of June 2008.

1. Week

Dick Wolfe, P.E Executive Director Colorado Ground Water Commission

Colorado Ground Water Commission 511 By: Keith Vander Horst, P.E. Jery Water Resource Engineer >

Prepared by: JPM

Page 5

92GWS 1 03/2005

EXHIBIT A

1689-BD

Page 1 of 2

STATE OF COLORADO OFFICE OF THE STATE ENGINEER DIVISION OF WATER RESOURCES 1313 Sherman St. Room 821 Denver, CO 80203 (303) 866-3581 Fax (303) 866-3589

RECEIVED

APR 1 7 2008

WATER RESOLUTCES COLO.

NONTRIBUTARY GROUND WATER LANDOWNERSHIP STATEMENT

I (We) George F. McCune and Evelyn McCune

(Name(s))

claim and say that I (we) am (are) the owner(s) of the following described property consisting of 900.52 acres in the County of El Paso State of Colorado:

(Insert the property legal description)

SW/4SW/4 Section 18 and W/2 of the W/2 Section19, T11S, R64W, and S/2SE/4 Section 13 and All of Section 24, T11S R65W, 6th PM, El Paso County, 900.52 acres

See attached Quitclaim Deed dated November 29, 1976, and map.

and, that the ground water sought to be withdrawn from the Laramie-Fox Hills aquifer underlying the above-described land has not been conveyed or reserved to another, nor has consent been given to its withdrawal by another.

Further, I (we) claim and say that I (we) have read the statements made herein; know the contents hereof; and that the same are true to my (our) knowledge.


Signature <u>Gebrage 7 Mc Cume</u> Date (<u>Cuelyn M Mc Cum</u> Date

INSTRUCTIONS:

Please type or print neatly in black or blue ink. This form may be reproduced by photocopy or word processing means. See additional information on the reverse side.

EXHIBIT A A PAR SHALL LIVE est Copy Available 1689-BD 11 8 18 3 8 Page 2 of 2 Mar in the los STREET, STREET, RECEIVED CUTICEAIM DEED APR 1 7 2008 Sector RAY C. MCUINE and GRETA C. MCCUINE, as humbond and wills, of the County of El Paro and State of Colorado, for the consideration of One Dollar (\$1.00) and other COLORAD COLO great and valuable consideration, in hand paid, hereby sell and quit claim to GEORGE F. McCUNE and EVELYN M. McCUNE, humand and wife, in joint tenancy, of the County of Elbert and State of Colorado, a one-balf interest in and to all minerals underlying the following described property, including oil and gas, solid property lying and being in the ت. تريد County of El Paso and State of Colorado, to wit: The Southwest quarter of the Southwest quarter of Section Eighteen, Township Eleven, Range Shiry-four; the West half of the West half of Section Nineteen, Township Eleven, Range Shiry-four; the South half of the Southeast Quarter of Section Thiefeen, Township Eleven, Range Shiry-five; All of Section Twenty-four, Township Eleven, Range Shiry-five; continuing in all Nine hundred and filty-two hundredits (900,52) acres, more or less, according to Government with all its appurtenances. . . . No DATED and signed this 22 day of Nou. Consideration 1976. STATE DOCUMEN NOV 2 9 1975 (m) PEE & STATE OF COLORADO COUNTY OF EL PASO The foregoing instrument was acknowledged before me this 2. day of Novi 1. 1. A. A STATE OF A STATE 2.8 10.00 · · · ·

COLORADO GROUND WATER RESOURCES SAPE 17 2008 APR 17 200 APR 17 200 APR 10 APR 10 APR	a	
APPLICATION FOR DETERMINATION OF WATER RESOLUTCES APR 1 7 2008 APR 1 7 200 APR 1 APR 1 APR 1 APR 1 APR 1 APR		
APPLICATION FOR DETERMINATION OF WATER RESOLUTCES APR 1 7 2008 APR 1 7 200 APR 1 APR 1 APR 1 APR 1 APR 1 APR	COLORADO GROUND WATER COMMISSION	RfArtites.
1313 Sharman St, Room 195, Denver, CD 80203 APR 1 7 2008 APPLICATION FOR DETERMINATION OF WATER RIGHT WITHIN A DESIGNATED GROUND WATER BASIM PLUSUANT TO SECTION 37-90-107(7), C.R.S. Designation of lange of the second may park be used to apply for a determination of rights to ground water from the Dawren, Dawren, Argenobae or Lammine for Hile aggine index of the apply for a determination of rights to ground water from the Dawren, Dawren, Argenobae or Lammine for Hile aggine index of the apply for a determination. Type or privin in black risk. 1. APPLICANT INFORMATION Index of Application may park be used for each equiter determination. Type or privin in black risk. 1. APPLICANT INFORMATION Index of Application in the Orange of the Clance Medication. Name of Applicatin George F. McCuno and Evelyn McCune Applicant Mating Address 1. APPLICANT INFORMATION Index of the Clance and Evelyn McCune Applicant Mating Address 1. APPLICANT INFORMATION Index of Clance A the Clance and Evelyn McCune Applicant Mating Address 1. APPLICANT INFORMATION (FROLOGE BIES CODE) Index of Application in term #8 below. 2. AMOUNT OF OVERLYNN MCLAND - the Claim and risk of address Index of Application in term #8 below. 2. AMOUNT OF GOVERLYNN MATER - TO SE Withform, for Inforded Denificat uses, from address in advantant to the application. Index of the application in term #8 below. 3. AMOUNT WELLS - Are their advantant to the damed and described condrying the damed and advantant to the application. Index of the applic	DIVISION OF WATER RESOURCES	uereiaen
APPLICATION FOR DETERMINATION OF WATER RIGHT WITHIN A DESIGNATED GROUND WATER BASIN PURSUANT TO SECTION 37-90-107(7), C.R.S. Denver, Angoloe or Lanzas-For this application may reful be used to apply for a deterministion of rights to ground water from the Dewson, entructions on the newsoa of this form. This be used to apply for a deterministion of rights to ground water from the Dewson, entructions on the newsoa of this form. This be used to apply for a deterministion of rights to ground water from the Dewson, entructions on the newsoa of this form. This be used to exch against deterministion. Type or private the with a non-refundable \$20 films fee. A separate form mue be used to exch against deterministion. Type or private black rink. T. APPLICANT INFORMATION Manic of Applicant Manicol Mapplicant Manicol Manicol Manicol Manicol Mani	DEPARTMENT OF NATURAL RESOURCES	
WITHIN A DESIGNATED GROUND WATER BASIN Committee PURSUANT TO SECTION 37-90-107(7), C.R.S. Derver, Arapahee or Laramé-For Hills applietion may only build and areas located within a Designated Ground Water Besin, Roview the instructions on the newses of this form. This Book moreable completed. Signed, debut and submitted to the Ground Water Besin, Roview the instructions on the newses of this form. This Book moreable completed. Signed, debut and submitted to the Ground Water Besin, Roview the instructions on the newses of this form. This Book more be completed. Signed, debut and submitted to the Ground Water Commission with a non-relationship Storemer F. Macchane and Evolyn McCune Applicant Matting Address 17480 Meridian Road, Elbert, CO 80106-8916 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 2 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 17480 Meridian Road, Elbert, CO 80106-8916 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 0 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 0 Constant Tasgonore Namiser (Incluse Blane and Dialor and and and area as an attachment to this application. No	1313 Sherman St, Room 818, Denver, CO 80203	APR 1 7 2008
WITHIN A DESIGNATED GROUND WATER BASIN Committee PURSUANT TO SECTION 37-90-107(7), C.R.S. Derver, Arapahee or Laramé-For Hills applietion may only build and areas located within a Designated Ground Water Besin, Roview the instructions on the newses of this form. This Book moreable completed. Signed, debut and submitted to the Ground Water Besin, Roview the instructions on the newses of this form. This Book moreable completed. Signed, debut and submitted to the Ground Water Besin, Roview the instructions on the newses of this form. This Book more be completed. Signed, debut and submitted to the Ground Water Commission with a non-relationship Storemer F. Macchane and Evolyn McCune Applicant Matting Address 17480 Meridian Road, Elbert, CO 80106-8916 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 2 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 17480 Meridian Road, Elbert, CO 80106-8916 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 0 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 0 Constant Tasgonore Namiser (Incluse Blane and Dialor and and and area as an attachment to this application. No		
WITHIN A DESIGNATED GROUND WATER BASIN Committee PURSUANT TO SECTION 37-90-107(7), C.R.S. Derver, Arapahee or Laramé-For Hills applietion may only build and areas located within a Designated Ground Water Besin, Roview the instructions on the newses of this form. This Book moreable completed. Signed, debut and submitted to the Ground Water Besin, Roview the instructions on the newses of this form. This Book moreable completed. Signed, debut and submitted to the Ground Water Besin, Roview the instructions on the newses of this form. This Book more be completed. Signed, debut and submitted to the Ground Water Commission with a non-relationship Storemer F. Macchane and Evolyn McCune Applicant Matting Address 17480 Meridian Road, Elbert, CO 80106-8916 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 2 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 17480 Meridian Road, Elbert, CO 80106-8916 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 0 Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 0 Constant Tasgonore Namiser (Incluse Blane and Dialor and and and area as an attachment to this application. No	APPLICATION FOR DETERMINATION OF WATER RIGHT	USA FER MERSON
PURSUANT TO SECTION 37-90-107(7), C.R.S. Piese note: This application may only be used to apply for a dotamination of rights to ground water from the Dawson, Dorwer, Argobies or Laman Scholl and Annual Total and Annual Scholl and Marking and Scholl and Annual Scholl and Marking and Scholl and Annual Scholl and Marking and Scholl and Marking Andress Image: The Scholl and Scho	WITHIN A DESIGNATED GROUND WATER BASIN	
Please note: This application may only be used to apply for a determination of rights to ground water from the Dawson, Durver, Arapahe or Laramis-Fox Hills aguifer underlying land areas located within a Designated Ground Water Commission with a non-refuncials \$20 filling fee. A separate form must be unsel for each equilier determination. Type or part in Mack int. Image: Commission of the reverse of the feet. The Non-The State Result of the Commission with a non-refuncials \$20 filling fee. A separate form must be unsel for each equilier determination. Type or part in Mack int. Image: Commission of the reverse of the feet. The Non-The State Result of the State	PURSUANT TO SECTION 27.00 (07/7) O D O	
Instructions on the reverse of this form. This form must be used for each acalier data shorther to the Ground Water Commission with a non-relatable \$80 filling fee. A separate form must be used for each acalier detamination. Type or print in Mark ink. I. APPLICANT INFORMATION Namie of Apolicant George F. McCenne and Evelyn McCune Applicant Mailing Address 17480 Meridian Road, Elbort, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 cleined and described by the applicant in term #8 below, consisting of \$90.62 acres. active Wells - Are there any wells located on the overying land area as an attachment to this application. S. ARNUML AWOUNT OF CHOURD WATER - To be with claimed and described overying land? Yes. No_X described final area claimer with the table bocked on the overying land area as an attachment to this application. No_X S. ARNUML AWOUNT OF CHOUND WATER - To be withridinen, for fibring of the application. S. ARNUML AWOUNT OF CHOUND WATER - to be withridinen, for fibring of and area align attachment to this application. S. ARNUML AWOUNT OF CHOUND WATER - to be withridinen for ground water from the active point on this anount Maximum aloveshie Score fort kinose	10 0L01101 31-30-10/(1), C.K.S.	
Instructions on the reverse of this form. This form must be used for each acalier data shorther to the Ground Water Commission with a non-relatable \$80 filling fee. A separate form must be used for each acalier detamination. Type or print in Mark ink. I. APPLICANT INFORMATION Namie of Apolicant George F. McCenne and Evelyn McCune Applicant Mailing Address 17480 Meridian Road, Elbort, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 eloc Colorado Water Plans, P.O. Box 1988, Elbert, CO 80108-8916 cleined and described by the applicant in term #8 below, consisting of \$90.62 acres. active Wells - Are there any wells located on the overying land area as an attachment to this application. S. ARNUML AWOUNT OF CHOURD WATER - To be with claimed and described overying land? Yes. No_X described final area claimer with the table bocked on the overying land area as an attachment to this application. No_X S. ARNUML AWOUNT OF CHOUND WATER - To be withridinen, for fibring of the application. S. ARNUML AWOUNT OF CHOUND WATER - to be withridinen, for fibring of and area align attachment to this application. S. ARNUML AWOUNT OF CHOUND WATER - to be withridinen for ground water from the active point on this anount Maximum aloveshie Score fort kinose	Please note: This application more and the sector	
Instructions on the reverse of this form. This fear must be used for each aquifer dama submittee factor. Review the owner database SR0 filing fee. A separate form must be used for each aquifer determination. Type or print in black ink. I. APPLICANT INFORMATION Namie of Apolicant Beorge F. McCune and Evelyn McCune Applicant Mailing Address 17480 Meridian Road, Elbort, CO 80:008-8916 cio Colorado Water Flema, P.O. Box 1998, Elbert, CO 80:008-8916 cio Colorado Water Flema, P.O. Box 1998, Elbert, CO 80:008-8916 cio Colorado Water Flema, P.O. Box 1998, Elbert, CO 80:008-8916 cio Colorado Water Flema, P.O. Box 1998, Elbert, CO 80:008-8916 cio Colorado Water Flema, P.O. Box 1998, Elbert, CO 80:008-8916 cio Colorado Water Flema, P.O. Box 1998, Elbert, CO 80:008-8916 cio consisting of 900.62 acres. AMOUNT OF OVERLYING LAND – the total and and described overlying land? Yes	Denver, Arapahoe or Laramie Fox Hills application industrial land apply for a determination of rights to grou	ind water from the Dawson.
with a non-refundable \$20 filing fee. A separate form must be used for each aquifier determination. Type or print in black ink. I. APPLICENT INFORMATION Name of Applicant Applicant Mailing Address 17480 Meridian Road, Elbort, CO 80106-8916 clo caterado Water Plans, P O Box 1985, Elbort, CO 80106-8916 Applicant Mailing Address Applicant Mailing Address Applicant Telephone Number (include state code) 383 448-0069. Contact: 333 644-201 110 - L10 - L10 - L10 - L10 2. AMCOUNT OF OVERLUNG LAND Automation of the state and the state and state and states 3. AQUIFER 2. AMCOUNT OF OVERLUNG 110 - L10 - L10 - L10 - L10 - L10 2. AMCOUNT OF COVERLUNG LAND 2. AMCOUNT OF COVERLUNGE LAND 3. AND LINE OF COVERLUNGE LAND 3. AND LINE OF COVERLUNGE LAND 4. EXISTING WIELLS - Arc thate any wells located on the celained and described overlying land? 4. EXISTING WIELLS - Arc thate any well's located on the celained and described overlying land? 4. EXISTING WIE	instructions on the reverse of this form. This former than a new rocated within a Designated Gro	und Water Basin, Review the
1. APPLICANT INFORMATION Name of Applicant Applicant Mailing Address 17460 Meridien Road, Elbert, CO 80106-8916 elo Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 Applicant Mailing Address Applicant Mailing Address Applicant Tateprove Number (Include Brass 0000) 932-648-0000 Contact: 303 646-4201 119-455-±552 2. AMOUNT OF OVERLY VING LAND - the total and area 3. AQUIFER Lanamide-Fox Hills NT contesting of 800.62 across. 4. EXISTING WELLS - Are there any wells located on the certring land area as an attachment to this application. 6. ANNUAL AMOUNT OF GROUPU WATER - to be withdram, for ritended beneficial uses, from the annual acre-feet, encluding acre-feet annually Maximum allowable	with a non-refundable \$60 filing fee. A separate form must be used for each orustical and submitted to	the Ground Water Commission
Name of Applicant George F. McCune and Evelyn McCune Applicant Mailing Address 17480 Meridian Road, Elbert, CO 80106-8916 eto Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 eto Colorado Water Plane, P O Box 1985, Elbert, CO 80106-8916 Applicant Tasprone Number (netures area coord) 328 448-0000, Context 308 648-4201 119-15-25562 2. AMOUNT OF OVERLYING LAND - the total and area is an attemation to this applicant. Attemating of 900.05 datariss. 4. EXISTING WELLS - Are three any wells located on the oxighing land described owriging land? Yes, movide a complete list of all wells located on the oxighing land described location. 6. ANNOLL ANNOUNT OF GROUND WATER - to be withdrawn, for ithanked Denetical uses, from the aquiller underlying the described lead area datamed by the applicant in item #8 below. Madmum allowable annuals acre-feet annually	i i i i i i i i i i i i i i i i i i i	/pe or print in black ink.
George F. McCune and Evelyn McCune Applicant Mailing Address 17480 Meridian Road, Elbert, CO 80106-8916 Co Colorado Watter Plane, P O Box 1965, Elbert, CO 80106-8916 Applicant Transprote number (include also color) 233 6445-0000, Contact 303 8464-4201 T1915-25-2.2 AMOUNT OF OVERLYING LAND - the total and area and described by the applicatin in item #8 below, consisting of 900.52 acress. 4. EXISTING WELLS - Are there any wells located on the coldimed and described overlying land? 5. ANNUAL AWOUNT OF GROUND WATER - to be withfrimm, for infanded beneficial uses, from the aquifer underlying the described land area dation by the applicatin in term #8 below. 6. EXISTING WELLS - Are there any wells located on the overlying land area as an attachment to this application. 6. ANNUAL AWOUNT OF GROUND WATER - doscription of infended beneficial uses, from the aquifer underlying the described land area dation, the wells annual acre-feet annualy Meanum allowable annual acre-feet 6. UBE OF GROUND WATER - doscription of infended beneficial user and mask, for thoring and anable annual acre-feet insochate application and wells to be well-file annual acre-feet insochate application and wells to be applicating habitat less than 1000 meanset, for replaced in high and area and mask, for thoring and anable acquired insochate application is and all wells application or accurate acade mask and to be and and describe and and be achieved and a stachment application is and asset, for replaced in annual acre-feet insochate applicatin a to and wells the application is and all	1. APPLICANT INFORMATION	
Applicant Mailing Address 17460 Meridian Road, Elbert, CO 80106-8016 elo Colorado Water Plana, P O Box 1965, Elbert, CO 80106 Applicant Tategnom Number (include area doce) 393 645-000C. Contact 303 646-4201 consisting of 000.25 acress. AMOUINT OF OWERLYING LAND - the total and area A. ANOUNT OF OWERLYING LAND - the total and area A. EXISTING WELLS - Are there any wells located on the claimed and described overlying land? Yes, movide a complete list of all wells located on the overlying land area as an attachment to this application. S. ANNUAL AMOUNT OF GROUND WATER - to be withdrawn, for infended beneficial uses, from the aquifer underlying the described land area claimed by the applicant in term #8 below. Please specify one of the following: Mainum allowable		
17460 Meridian Road, Elbert, CO 80108-8916 eto Colorado Weter Plana, P O Box 1955, Elbert, CO 80108 Applicant response number (include area complexed and creation of the control	George F. McCune and Evelyn McCune	
Conversion wears manners, P.O. Box 1985, Elbert, CO 30106 Applicant ratephone Number (include alias code) Applicant ratephone Number (include aliasocode) Applicant ratephone Number (include aliasocode) App	Applicant Mailing Address	
Conversion weater Plants, P.O. Box 1985, Elbert, CO 30106 POD Contract 303 648-4201 TUP - 415 - 35 2 2 AMROUNT OF OVERLYING LAND - The total and area a latent and the applicant in term #8 below. Consisting of 900.62 acress. AEXISTING WELLS - Are there any wells located on the claimed and described overlying land? Yes No _ X If yes, provide a complete list of all wells located on the overlying land area as an attachment to this application. ARNUAL ANDOUNT OF GROUND WATEX - to be withdrawn, for intended beneficial uses, from the aquifer underlying the described land area claimed by the applicant in term #8 below. Aexist and the second by the applicant in term #8 below. Associated and area claimed by the applicant in term #8 below. Aexist and the second by the applicant in term #8 below. Aexist and the second by the applicant in term #8 below. Associated and area claimed by the applicant in term #8 below. Aexist and the second by the applicant in term #8 below. Associated to the following: Madmum allowable annual acre-feet annually Madmum allowable annual acre-feet toon that amount Associate and willife. The water will be produced for immediate applicants to asid water for a divertified tower for application is to asid second for preferences and willife. The water will be produced for immediate applicant to a said water for the following benefician uses of water from or accurate cale action to asid as applicant in the applicant in term #8 below. Item #8 below, unless a legal description or accurate acted area or overlying land area claimed in described by the applicant in terms and the applicant in the acted material application for accurate acted area and will affect area segmentation application accurate acted acted which describes an attachment to the applicant in term #8 below. Item #8 below, unless a legal description or accurate acted acted mon being formal water framate/nd/linea/ place of use. RECOURED LANDOWNERSHIP		
Contractor Veteor Paints, P.O. Box 1955, Elbert, CO 30106 Applicant Tatephone Number (include alias code) Applicant Number (include alias code) Applicant Alias and Number (include alias code) Applicant Tatephone Number (include alias code) Applicant Alias and Number (include alias code) Applicant Ali	17480 Meridian Road, Elbert, CO 80106-8916	
2. AMOUNT OF OVERLYING LAND - the total and area 3. AQUIFER Lanamie-Fox Hills NT caimed and described by the applicant in item #8 below, consisting of \$00.52 acres. 900.52 acres. 4. ENSTING WELLS - Are there any wells located on the overlying land area as an attachment to this application. No _X	We worked water Hans, P O Box 1955, Elbert, CO 80106	
2. AMOUNT OF OVERLYING LAND - the total and area 3. AQUIFER Lanamie-Fox Hills NT caimed and described by the applicant in item #8 below, consisting of \$00.52 acres. 900.52 acres. 4. ENSTING WELLS - Are there any wells located on the overlying land area as an attachment to this application. No _X		
2. AMOUNT OF OVERLYING LAND - the total and area 3. AQUIFER Lanamie-Fox Hills NT caimed and described by the applicant in item #8 below, consisting of 900.52 acres. 900.52 acres. 4. ENSTING WELLS - Are there any wells located on the overlying land area as an attachment to this application. No_X	Applicant Telephone Number (Include alter Code)	
AMOUNT OF OVERLYING LAND - the total and area alimet and described by the applicant in item #8 below, consisting of 900.52 acres. ALEXISTING WELLS - Are there any wells located on the claimed and described overlying land? Yes	-303 648 9000 Contact 303 646 4201	
Consisting of	2. AMOUNT OF OVERLYING LAND - the total and says 12 ADULTER	
Consisting of		lis NT
C. ANUAL ANOUNT OF GROUND WATER - to be withdrawn, for intended beneficial uses, from the aquifer underlying the described land area claimed by the applicant in liter #8 below. Please specify one of the following: Maximum allowable annual acro-feet, excluding acro-feet annually	consisting of 900.52 acres.	
C. ARNUAL ANOUNT OF GROUND WATER - to be withdrawn, for Intended beneficial uses, from the aquifer underlying the described land area claimed by the applicant in Item #8 below. Please specify one of the following: Maximum allowable annual acro-feet annually	4. EXISTING WELLS - Are there any wells located on the alger	
Advected land area claimed by the applicant in item #8 below. Please specify one of the following: Maximum allowable annual acre-feet acre-feet annually acre-feet annual acre-feet, excluding acre-feet annually acre-feet annual acre-feet annually acre-feet annual acre-feet, excluding acre-feet annually acre-feet annual acre-feet annually acre-feet from that arount acre-feet annually acre-feet form that arount acre-feet annually acre-feet annually acre-feet feet footnod water foon the tage acre-feet feet feet footnod water foon the tage and water foon and tees and water foon and tees and ter-feet acre-feet annuellate application to and ter-feet feet feet footn	If yes, provide a complete list of all wells located on the question and described overlying land?	YesNo_X
Maximum allowable ennual acre-feet	5. ANNUAL AMOUNT OF CURRENT INCOMENTATION OF CURRENT IN CONTINUE AND AREA AS AN Attachment to this	application.
Maximum allowable ennual acre-feet	described and area claimed but the area in the described and area claimed by the area in the described and area claimed but the area in the described area and a set of the described area and area and a set of the described	the aquifer underlying the
All annual acre-feet annual acre-feet acre-feet annual acre-feet annual acre-feet acre-feet acre-feet acre-feet acre-feet forn that annual acre-feet forn forn that annual acre-feet forn forn forn forn forn forn forn annual acre-feet forn for fo	The second and the second and the second one of the tollowing.	
All water withdraws will be reused, searcessively used, leased, beneficial uses of the ground water to be withdrawn from the aquifer infestational produced, tessed, leased, leased, sold or effective disposed of for the following leaseficial mest domestic, infestational, irrigation, augmentations, stock watering, recreational water feature poulds and placatorial habitat leas than 1000 uses, for ropiacement of depletion's from the use of water from other sources and for all other agmentations purposes 7. PLACE OF USE – of the ground water shall be considered to be that overlying land area claimed and described by the application to said tess, for ropiacement of depletion's from the use of water from other sources and for all other agmentation purposes 7. PLACE OF USE – of the ground water shall be considered to be that overlying land area claimed and described by the applicant in litem #6 below, unless a legal description or accurate scale map is provided which describes an alternate/edditional place of use. 8. RECURRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the ground Water I andownership Statement (form GWS-1) or Northributary Ground Water Consert Claim (form GWS-40), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be original signature – The matching of lates statements herein constitutes perjury in the second degree, which is punishable as a less 1 medemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements berein, know the contents thereof, and state that they are true to my knowledge. Signature Affect George F. McCume and Evelve Miccune, Owners Date Trans Number. 3628088 A Trans Number. 3628088 A Creect Annotine addition and state that they are true to my knowledge. Div		able annual acro foot another
B. OSE OF GROUND WATER - description of intended beneficial uses of the ground water to be withdrawn from the aquifer All water will be reased, successively used, lessed, sold or etherwise disposed of for the following beacficial uses: domestic, agamar fact and wildlife. The water will be produced for immediate applications to said uses, for ropiaceasest of depletion's from the use of water from other sources and for all other augmentation, stock watering, recreational water sources and for all other augmentation, stock watering, recreational water sources and for all other augmentation purposes PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and described by the applicant in Item #8 below, unless a legal description or accurate scale map is provided which describes an alternate/additional place of use. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Gescription of the overlying land area subject to this determination, must be submitted as an attachment to the application. SIGNATURE OF APPLICANT - must be original signature - the making of face statements herein constitutes particular. Signature American Market they are true to my knowledge. Junce American American American Market and Every McCune. Date Trans Number. 3628088 A		a fact from that some it
indestrial, commercial, irrigation, argementation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 sees, for replacement of depletion's from the use of water from other sources and for all other argementation purposes 7. PLACE OF USE – of the ground water shall be considered to be that overlying land area daimed and described by the applicant in lam #8 below, unless a legal description or accurate scale map is provided which describes an alternate/additional place of use. 8. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Dewson, Deriver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be original signature – The making of talse statement to the application. 9. SIGNATURE OF APPLICANT - must be original signature – The making of talse statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 244-104(13)(a). I have read the statements herein, and state that they are true to my knowledge. Signature Trans Number: 3628088 / Mitrice and Evelow MicCune, Owners PLACE Web	5. USE OF GROUND WATER - description of interded beneficial	
searce feet and wildlife. The water will be produced for immediate application to axid uses, for storage and subsequent application to used uses, for storage and subsequent application to used uses, for replacement of depletion's from the use of water from other sources and for all other augmentation purposes 7. PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and described by the applicant in ltem #8 below, unless a legal description or accurate scale map is provided which describes an attemate/additional place of use. 8. RECUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Dawson, Denver, Arapahoe or Laramis-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be original signature - The making of take statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein, know the contents thereof, and state that they are true to my knowledge. Signature	All water withdrawa will be reused, successively used, leaved, end or otherwise dimension different of the till	norawn from the aquifer
Insert, for replacement of depletion's from the use of water from other sources and for all other augmentation purposes 7. PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and described by the applicant in item #8 below, unless a legal description or accurate scale map is provided which describes an alternate/additional place of use. 8. RECOURED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Ground Water Landownership Statement (form GWS-1) or Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be original signature - The making of false statements berein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have need the statements berein, know the contents thereof, and state that they are true to my knowledge. Signature Arrow the Contents thereof, and state that they are true to my knowledge. Date Print name and title Gaorage F. McCume and Evelyn McCune, Owners Date 0.V	industrial, commercial, irrigation, augmentation, stock watering, recreational water frequencies, and along	beneficial uses: domestic,
7. PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and described by the applicant in lam #8 below, unless a legal description or accurate scale map is provided which describes an alternate/additional place of use. 8. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary Ground Water Consent Claim (form GWS-48), including a Ground Water Loadownership Statement (form GWS-1) or Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to CR.S. 24-4-104(13)(a). I have need the statements herein, know the contents thereof, and state that they are true to my knowledge. Signature	square feet and wildlife. The water will be produced for immediate application to said uses, for storage and	where we are the second s
7. PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and described by the applicant in ltem #8 below, unless a legal description or accurate scale map is provided which describes an atternate/additional place of use. 8. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Dawson, Derver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary Ground Water Commission shall allocate ground water from the description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be onginal signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24 - 104(13)(a). I have read the statements herein, know the contents theorof, and state that they are true to my knowledge. Signature Ample Ample Ample Ample Date - print name and title George F. McCume and Evelyn McCune, Owners POIV	ases, for replacement of depletion's from the use of water from other sources and for all other augmentation	DBTDeses
B. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary description of the overlying land area subject to this determination, must be submitted as an attachment to the application. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein the statements merein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein the statements merein additional place of the statements of the statements merein additional place of the statements of the statements of the statement of the stateme		
B. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary description of the overlying land area subject to this determination, must be submitted as an attachment to the application. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein the statements merein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein the statements merein additional place of the statements of the statements merein additional place of the statements of the statements of the statement of the stateme	Item #8 below unless a level description	described by the applicant in
Basson, Denver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary Ground Water Landownership Statement (form GWS-1) or Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein, know the contents thereof, and state that they are true to my knowledge. Signature Arapt M.C. WM Date Trans Number: 3828088 A FOR OFFICE USE ONLY FOR OFFICE USE ONLY Trans Number: 3828088 A Trans Ammeer: 3828088 Trans Ammeer: 3828088 Trans Ammeer: 3828088 Trans		
Ground Water Landownership Statement (form GWS-10 or Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application. SIGNATURE OF APPLICANT - must be original signature – The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor punsuant to C.R.S. 24-4-104(13)(a). I have read the statements herein, know the contents thereof, and state that they are true to my knowledge. Signature ALMONDATION MCCune Date - print name and title George F. McCune and Evelyn McCune, Ownere FOR OFFICE USE ONLY OIVCOWDBASINMD		
description of the overlying land area subject to this determination, must be submitted as an attachment to the application. 9. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein, know the contents thereof, and state that they are true to my knowledge. Signature Signature of the George F. McCune and Evelve McCune, Owners - print name and title George F. McCune and Evelve McCune, Owners Div Co 9 Co 9 MD 10 MD	Dervison, Denver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overhing land a	For this reason a Manufacture
9. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements herein, know the contents thereor, and state that they are true to my knowledge. Signature Signature JUTTLE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the herein, know the contents thereor, and state that they are true to my knowledge. Signature JUTTLE OF APPLICANT MC. Junt Date Date Date - print name and title George F. McCune and Evolvn McCune, Owners FOR OFFICE USE ONLY Georf Davis (21) Total Trans Amt: \$240.00 CHECK OIV Co MD MD OIV MD	description of the constraints land whether land the constraint of the constraint claim	(form GWS.48) industry
Signature	The second	
herein, know the contents thereof, and state that they are true to my knowledge. Signature Signature Base Date - print name and title George F. McCune and Everyn NicCune, Owners Trans Number: 3628088 A FOR OFFICE USE ONLY George F. McCune and Everyn NicCune, Owners Date Trans Number: 3628088 A FOR OFFICE USE ONLY George T. McCune and Everyn NicCune, Owners Div Div OFFICE USE ONLY Owners Div Div MD	SIGNATURE OF APPLICANT a must be orginal orginal orginal	
Signature Hunge H Me. Cume Date Signature Hunge H Me. Cume Date Trans Number: 3628088 A FOR OFFICE USE ONLY Trans Number: 3628088 A FOR OFFICE USE ONLY Geot Davis (21) Total Trans Amt: \$240.00 CHECK DIV RO 9 COWD BASIN MD MD	second degree, which is punishable as a class 1 misdemeanor pursuant to C.P.S. 24.4 404400000	constitutes perjury in the
Signature Signature Date - print name and side George F. McCune and Evelvn McCune, Ownere Trans Number: 3628088 A FOR OFFICE USE ONLY Trans Number: 3628088 A FOR OFFICE USE ONLY Outer State Trans Number: 3628088 A FOR OFFICE USE ONLY George F. McCune and Evelvn McCune, Ownere Trans Number: 3628088 A OUT BASIN MD Check Attractive: state OUT OUT BASIN MD Check Attractive: state	nerein, know the contents thereof, and state that they are true to my knowledge.	lave read the statements
Date Date Date Date Date Date Date Date	Signature Allital 4 Me une	1
Trans Number: 3628088 A FOR OFFICE USE ONLY Geoff Davis (21) Total Trans Arm: \$240.00 DIV Co WD BASIN MD Check Number: 3628088 A	Date Date	
Trans Number: 3628088 A FOR OFFICE USE ONLY Geoff Davis (21) Total Trans Arm: \$240.00 DIV Co WD BASIN MD Check Number: 3628088 A	- Drint name and title George E Macune and Evile Hild	
FOR OFFICE USE ONLY 41772006 1:34:24 PM Geoff Davis (21) Geoff Davis (21) Total Trans Amt: \$240.00 CHECK DIV CoWD BASINMD Check Number - 9724008) Check Amount: \$240.00 Check Amount: \$240.00	Compression and Everyn mcGune, Owners	
FOR OFFICE USE ONLY 41772006 1:34:24 PM Geoff Davis (21) Geoff Davis (21) Total Trans Amt: \$240.00 CHECK DIV CoWD BASINMD Check Number - 9724008) Check Amount: \$240.00 Check Amount: \$240.00		
g Geoff Devis (21) Total Trans Amt: \$240.00 DIVCoWDBASINMD MDCheck Amount: \$240.00 Check Amount: \$240.00 Check Amount: \$240.00		Trans Number: 3628088 A
DIV 9 CO WD BASIN MD Check Number - 07(24005) Check Amount: \$240.00	FOR UFFICE USE ONLY	Geoff Davis (24)
DIVCOWDBASINMDCHECK Check Number - 07(2005) Check Amount: - 240.00		Total Trans Amt shan on
Check Amount: 5240.005)		CHECK
	MU	Check 2011 (2005)
	·· .)	



THERE ARE NO WATER WELLS ON THE PROPERTY

LOCATION MAP from CDSS

RECEIVED

APR 1 7 2008

STATE ENGINEER

1.22

COLORADO WATER PLANS Water Consultants

Colorado Ground Water Commission Division of Water Resources Department Of Natural Resources 1313 Sherman Street - Room 818 Denver, Colorado 80203

Re: Application for Determination of Water Right Client: George F. McCune and Evelyn McCune

Agent: Colorado Water Plans LLC

Colorado Water Plans LLC has prepared the Application for Determination of Water Right with my permission as Signatory and Landowner. Colorado Water Plans LLC shall have full representational power as "Agent" in regards to this Application for Determination of Water Right, water issues, water facts, water calculations, submittals to governmental agencies, reporting forms, newspaper public notifications, applications, or any other needs within the confines of the Contract for Services. This document shall authorize my "Agent" Colorado Water Plans LLC to manage and conduct all affairs and to exercise all my rights and powers within the enclosed Application for Determination of Water Right.

Colorado Water Plans has no rights, implied or warranted outside the affairs of this agreement, and subject to other provisions of this document, disclaim any interest which might otherwise be transferred or distributed to me from other person or entity.

Client:

g=7 mc Come + Evelyn m. mg Que By:

Date: 4-14-08

Colorado Water Plans LLC Craig L. Curl Dr. W. Jerry Koch Lisa S. Weinstein, Bsq. #35681 Bv: Date: PO Box 1955 / Elizabeth / Colorado / 80107 303//646-9655

DETERMINATION OF WATER RIGHT SECTION 37-90-107(7)

APPLICANT: George F. McCune and Evelyn McCune

BASIN: Kiowa-Bijou

COUNTY: El Paso

AQUIFER: Laramie-Fox Hille RECEIPT NO. 3628088A

NUMBER OF ACRES IN TRACT: 900.52 acres

GENERAL LOCATION: SW/4SW/4, Section 18 and W/2NW/4, W/2SW/4, Section 19, T11S, R64W, 6th PM, S/2SE/4, Section 13 and All of Section 24, T11S, R65W, 6th PM.

AQUIFER DATA

263.4 AFyr

AMOUNT AVAILABLE FOR APPROPRIATION: (195 1

RAPPROPRIATION: (195 feet SS)(900.52 Acres)(0.15 SY) = 26340 AF None

ANNUAL AMOUNT: 263.4 AFyr

PRE.NOV.19, 1973 WELLS (COMPLETED IN AQUIFER) IN VICINITY: N/A

OVERLAP AREA: N/A

ADJUSTMENTS:

AREA CHECKED: Sections 18, 19, and 30, T11S, R64W Sections 13, 14, 23, 24, 25, and 26, T11S, R65W

SMALL-CAPACITY WELLS (COMPLETED IN AQUIFER) LOCATED ON CLAIMED TRACT: N/A

REPLACEMENT WATER STATUS OF CLAIMED LAND AREA: Nontributary


REPLACEMENT PLAN REQUIRED: Not Required


AQUIFER INTERVAL (CENTRAL DATA POINT): 2820 feet to 2940 feet below ground surface


COMMENTS: The SS was considered 195 feet based on the SS map for the Laramie-Fox Hills aquifer.

Evaluated by: Justina Mickelson, Ground Water Commission Staff Reviewed by CBG

C:\Documents and Settings\jpm\My Documents\Water Right Aps\McCune\McCune Laramie Determ.doc









DEPARTMENT OF NATURAL RESOURCES

DIVISION OF WATER RESOURCES

Bill Ritter, Jr. Governor

Harris D. Sherman Executive Director

Dick Wolfe, P.E. Director

May 1, 2008

George F. McCune and Evelyn McCune c/o Colorado Water Plans P.O. Box 1955 Elizabeth, CO 80107

RE: Applications for Determinations of Water Right to Appropriate Ground Water from the Laramie-Fox Hills, Arapahoe, Denver, and Dawson Aquifers Underlying a 900.52-Acre Tract,

Receipt Nos. 3628088A-D

Dear Mr. and Mrs. McCune:

Enclosed is a copy of the legal notice to be published in the Ranchland News newspaper as required for the above described applications. If you find any errors or omissions in the notice, please contact this office by phone as soon as possible so that corrections may be made prior to publication. This office will bill you at a later time for the actual cost of this publication.

If you have any questions concerning these applications, please contact me at this office.

Sincerely,

In Minst

Justina Mickelson Physical Science Researcher Scientist Designated Basins Branch

Enclosures: a/s cc: George and Evelyn McCune

1313 Sherman Street, Suite 818 • Denver, CO 80203 • Phone: 303-866-3581 • Fax: 303-866-3589 www.water.state.co.us OFFICE OF THE STATE ENGINEER Division of Water Resources – Department of Natural Resources 1313 Sherman St, Room 818, Denver, Colorado 80203 Phone 303-866-3581 – FAX 303-866-3589 – www.water.state.co.us

May 1, 2008

Ranchland News PO Box 307 Simla, CO 80835

Applicant: George F. McCune and Evelyn McCune

-EMAIL- DOCUMENT TRANSFER-

Please publish the enclosed legal notice in your editions of May 8, 2008 and May 15, 2008, or as close to these dates as possible. Please single-space all the enclosed material in your standard single column legal notice format. Font size shall not be less than six-point type and not more than nine-point in size.

Prior to publishing the legal notice, a proof copy must be submitted to this office for approval. The Ground Water Commission staff will inspect the proof copy and a reply as to its correctness will be made immediately by phone to your office. The proof copy must be directed to the attention of Justina Mickelson, Colorado Division of Water Resource at the above address, or by email justina.mickelson@state.co.us or fax 303-866-3589.

The state Controller and the State Purchasing Agent require that four copies of the billing and four copies of the proof of publication affidavit must be received in order to process billing invoices for legal notice publications. Two copies of the proof of publication must be notarized.

Since we must re-bill the applicant prior to the official action concerning their application request, please transmit the billing copies together with the proofs of publication as soon as possible.

Should you have any questions concerning publication of this notice, please contact this office.

Sincerely,

Justina, Mickelson Physical Science Researcher Scientist Designated Basins Branch

Enclosure (a/s)

cc: Robert R. Loose, Commission Member

C:\Documents and Settings\jpm\My Documents\Water Right Aps\McCune\RanchlandNews - McCune.doc

BEFORE THE COLORADO GROUND WATER COMMISSION

KIOWA-BIJOU DESIGNATED GROUND WATER BASIN- EL PASO COUNTY

TAKE NOTICE that pursuant to Section 37-90-107(7), C.R.S., George F. McCune and Evelyn McCune (hereinafter "applicant") have applied for determinations of water right to allow the withdrawal of designated ground water from the Laramie-Fox Hills, Arapahoe, Denver, and Dawson aquifers underlying 900.52 acres generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 11 and and control of the ground water in the above-described aquifers under this property. The ground water allocations from these aquifers will be used on the described property for the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The maximum allowable annual amount of ground water in each aquifer underlying the described property will be allocated.

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, the Colorado Ground Water Commission shall allocate ground water from the above-described aquifers based on ownership of the overlying land and an aquifer life of one hundred years. A preliminary evaluation of the applications by the Commission Staff finds the annual amount of water available for allocation from each of the described aquifers underlying the above-described property to be as follows: 263.4 acre-feet for the Laramie-Fox Hills, 398.0 final staff evaluation. The estimated available annual acre-feet allocation amount for each aquifer to indicated above may be increased or decreased by the Commission to conform to the actual aquifer characteristics, based upon site specific data.

In accordance with Rule 5.3.6 of the Designated Basin Rules, the Commission Staff's preliminary evaluation of the applications finds the replacement water requirement status for the above aquifers underlying the above-described property to be as follows: nontributary for the Laramie-Fox Hills, nontributary for the Arapahoe, nontributary for the Denver, and not-nontributary (actual impact replacement) for the Dawson.

Upon Commission approval of these determinations of water right, well permits for wells to withdraw the allowed allocation from a specific aquifer shall be available upon application, subject to the conditions of the determination and the Designated Basin Rules and subject to approval by the Commission. Such wells must be completed in the specified aquifer and located on the above described 900.52 acre property. Well permits for wells to withdraw ground water from the Dawson aquifer would also be subject to the conditions of a replacement plan to be approved by the Commission.

Any person wishing to object to the approval of these determinations of water right must do so in writing, briefly stating the nature of the objection and indicating the above applicant, property description and the specific aquifers that are the subject of the objection. The objection must be accompanied by a \$10 per aquifer fee and must be received by the Commission Staff, Colorado Ground Water Commission, 818 Centennial Building, 1313 Sherman Street, Denver, Colorado 80203, by June 16, 2008.

PUBLISHER'S AFFIDAVIT

STATE OF COLORADO)

I, Susan Lister, do solemnly affirm that I am the Publisher of RANCHLAND NEWS; that the same is a weekly newspaper published at Simia, County of Elbert, State of Colorado, and has a general circulation therein; that said newspaper has been continuously and uninterruptedly published in said County of Elbert for a period of at least 52 consecutive weeks next prior to the first publication of the annexed notice, that said newspaper is entered in the post office at Calhan, Colorado as second class mail matter and that said newspaper is a newspaper within the meaning of the Act of the General Assembly of the State of Colorado, approved March 30, 1923, and entitled "Legal Notices and Adverlisements," with other Acts relating to the printing and publishing of legal notices and advertisements. That the annexed notice was published in the regular and entire issue of said newspaper, once each week for two successive weeks; that the first publication of said notice was in the Issue of said newspaper dated:

May 8 2008


and the last publication of said notice was in the issue of said newspaper dated:

as 800

and that copies of each number of said paper in which said notice and/or list was published were delivered by carriers or transmitted by mail to each of the subscribers of said newspaper, Ranchland News, according to the accustomed mode of busidess in this office.

Publisher

The above certificate of publication was subscribed and affirmed to before me, a Notary Public, to be the identical person described in the above certificate, on the



71

Determinations of Water Right BEFORE THE COLORADO GROUND WATER COMMISSION KIOWA-BIJOU DESIGNATED GROUND WATER BASIN- EL PASO COUNTY TAKE NOTICE that pursuant to Section 37-90-107(7), C.R.S., George F. McCune and Evelyn McCune (hereinafter "applicant") have applied for determinations of water right to allow the withdrawal of designated ground water from the Laramio-Fox Hills, Atapahoe, Danver, and Dawson aquifers underlying 900.52 acres generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2. of the SEI/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6ª PM. The applicant claims ownership of this land and control of the ground water in the above-described equifiers under this property. The ground water allocations from these aquifers will be used on the described property for the following beneficial uses: Somestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The maximum allowable ennual amount of ground water in each aquifer underlying the described property will be allocated.

In accontance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, the Colorado Ground Water Commission shall allocate ground water from the above-described aquifers based on ownership of the overlying land and an aquifer life of one hundred years. A preliminary evaluation of the applications by the Commission Staff finds the annual amount of water available for allocation from each of the described aquifers underlying the abovedescribed property to be as follows: 263.4 acrefeet for the Laramie-Fox Hills, 398.0 acre-feet for the Arapahoe, 528.2 acre-feet for the Denver, and \$19.5 for the Dawson subject to final staff evaluation. The estimated available annual acre-feet allocation amount for each aquifer indicated above may be increased or decreased by ; the Commission to conform to the actual aquifer characteristics, based upon site specific data,

In accordance with Rule 5.3.6 of the Designated Basin Rules, the 'Commission Staff's preliminary evaluation of the applications finds the replacement water requirement status for the above aquifers underlying the above-described property to be as follows: nontributary for the Laramie-For Hills, anotributary for the Arapahoe, nontributary for the Denver, and notnointributary (actual impact replacement) for the Dawson,

Upon Commission approval of these determinations of water right, well pennifs for wells to withdraw the allowed allocation from a specific aquifer shall be available upon application, subject to the conditions of the determination and the Designated Basin Rules and subject to approval by the Commission. Such wells must be completed in the specified aquifer and located on the above described 900.52 nere property. Well pennits for wells to withdraw ground water from the Dawson aquifer would also be subject to the conditions of a replacement plan to be approved by the Commission.

Any person wishing to object to the approval of these determinations of water right must do so in 'writing, briefly stating the nature of the objection and indicating the above applicant, property description and the specific aquifers that are the 'subject of the objection. The objection must be accompanied by a \$10 per aquifers that are the 'subject of the objection. The objection must be accompanied by a \$10 per aquifers that are the 'subject of the objection. The objection must be accompanied by a \$10 per aquifers that are the accompanied by a \$10 per aquifers that are the accompanied by a \$10 per aquifers that are the accompanied by a \$10 per aquifers that are the accompanied by a \$10 per aquifers that are the accompanied by a \$10 per aquifers that are the accompanied by a \$10 per aquifers that are the Building, 1313 Sherman Street, Denver, Colorado \$0203, by June 16, 2008. First Publication May 15, 2008 In Ranchland News Legal No. 12,936

RECEIVED

MAY 1 9 2008

WATER RESOURCES

PUBLISHER'S AFFIDAVIT

STATE OF COLORADO)

I, Susan Lister, do solemnly affirm that I am the Publisher of RANCHLAND NEWS; hat the same is a weekly newspaper pub-Ished at Simia, County of Elbert, State of Solorado, and has a general circulation herein; that said newspaper has been coninuously and uninterruptedly published in said County of Elbert for a period of at least 52 consecutive weeks next prior to the first pubication of the annexed notice, that said newspaper is entered in the post office at Cathan, Colorado as second class mail matter and that ald newspaper is a newspaper within the neaning of the Act of the General Assembly of the State of Colorado, approved March 30, 923, and entitled "Legal Notices and Advarisements," with other Acts relating to the printng and publishing of legal notices and adertisements. That the annexed notice was ublished in the regular and entire issue of aid newspaper, once each week for 100 uccessive weeks; that the first publication of aid notice was in the Issue of said newspaer dated:

May К 2008

nd the last publication of said notice was in te issue of said_newspaper dated;

la 2008

nd that copies of each number of said paper i which said notice and/or list was published ere delivered by carriers or transmitted by iall to each of the subscribers of said newsaper, Ranchland News, according to the coustomed mode of business in this office.

Publisher

The above certificate of publication was ubscribed and affirmed to before me, a Nory Public, to be the identical person dewibed in the above certificate, on the

20<u>0</u>8 -0 Notary Public

ly Notary Public Commission Expiration Date)

ŤŤ

Determinations of Water

Right BEFORE THE COLORADO GROUND WATER COMMISSION KIOWA-BLIOU DESIGNATED GROUND WATER BASIN- EL PASO COUNTY TAKE NOTICE that purplant to Section 37-90-107(7), C.R.S., George F. McCone and Evelyn McCune (hereinafter "applicant") have applied for determinations of water right to allow the withdrawal of designated ground water from the Lammie-Fox Hills, Arapahoe, Denver, and Dewson aquifers underlying 900.52 acres generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6ª PM. The applicant claims ownership of this land and control of the ground water in the above described aquifers under this property. The ground water allocations from these aquifars will be used on the described property for the following beneficial uses: domestic, industrial, commercial, inigation, augmentation, stock watering, recreational water festure ponds and placatorial habitat less than 1000 square fact and wildlife, replacement and all other augmentation purposes. The maximum allowable annual amount of ground water in each aquifer underlying the described property will be allocated

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, the Colorado Ground Water Commission shall allocate ground water from the above-described aquifars based on ownership of the overlying land and an aquifer life of one hundred years. A preliminary evaluation of the applications by the Commission Staff finds the annual amount of water available for allocation from each of the described aquifers underlying the abovedescribed property to be as follows: 263.4 acrefeet for the Laramic-Fox Hills, 398.0 acre-feet for the Anapahoe, 528.2 acre-feet for the Denver, and \$19.5 for the Dawson subject to final staff evaluation. The estimated available annual scre-feet allocation amount for each aquifer indicated above may be increased or decreased by the Commission to conform to the actual aquifer -characteristics, based upon site specific data. In accordance with Rule 5.3.6 of the Designated Basin Rules, the Commission Staff's preliminary evaluation of the applications finds the replacement water requirement status for the above aquifers underlying the above described property to be as follows: nontributary for the Laramie-Fox Hills, sontributary for the Arapahoe, nontribuinary for the Denver, and notnontributary (actual impact replacement) for the Dawson.

Upon Commission approval of these determinations of water right, well permits for wells to withdraw the allowed allocation from a specific aquifer shall be available upon application, subject to the conditions of the determination and the Designated Basin Rules and subject to approval by the Commission. Such wells must be completed in the specified squiftr and located on the above described 900.52 acre property. Well permits for wells to withdraw ground water from the Davien equifier would also be subject to the conditions of a replacement plan to be approved by the Commission.

Any person wishing to object to the approval of these determinations of water right must do so in writing, briefly stating the many of the objection and influences the

and indicating the above applicant, property description and the specific aquifers that are the subject of the objection. The objection must be accompanied by a \$10 pcs aquifer fee and must be received by the Commission Staff, Colorado Ground Water Commission, \$18 Centennial Building, 1313 Sherman Street, Denver, Colorado 60203, by June 16, 2008.

First Publication May 8, 2008 Final Publication May 15, 2008 In Ranchland News

Legal No. 12,936

S Which is a marked

RECEIVED

MAY 1 9 2008

WATER RESOURCES

8/2008 3 NUMBER 3 RECEIVED	MAY 1 9 2008 WATER RESOURCES STATE EXGNUEER	
5/ B DATE		Amount 43.97 30.71 74.68
Invoice		Units 89.000 89.000
	192	Total
News Avenue, PO Box 307 80835	Colorado Ground Water Commission 1313 Sherman Street, Rocan 818 Denver CO 80203	Description Iegal - 11.5 Picas McCune, legal 12,936 Legal - Rerun - 11.5 Picas McCune, legal 12,936 ******* Total
Ranchland News 115 Sioux Avenue, Simla CO 80835	Colorado G 1313 Sherm Denver CO	Date 05/08/2008 05/15/2008

RECEIVED

JUN 0 2 2008



DEPARTMENT OF NATURAL RESOURCES

DIVISION OF WATER RESOURCES

WATER RESOURCES STATE ENGINEER COLO.

Bill Ritter, Jr. Governor Harris D. Sherman Executive Director

Dick Wolfe, P.E. Director

George F. McCune and Evelyn McCune c/o Colorado Water Plans P.O. Box 1955 Elizabeth, CO 80107

Invoice No. 08-PUB-220

Pursuant to Section 37-90-116, C.R.S., applicants are required to pay for the actual expense of publication for determinations of water right, well permit and change of water right applications.

INVOICE

May 21, 2008

Your application for determinations of water right to appropriate ground water from the Laramie-Fox Hills, Arapahoe, Denver, and Dawson aquifers was published in the Ranchland News newspaper on May 8 and May 15, 2008.

The following cost was incurred:

- 1. Actual cost of publication: \$74.68
- 2. Additional fees: лопе

PAYABLE TO: DIVISION OF WATER RESOURCES \$74.68

Your application cannot be considered for approval until the charges are paid. Please return the enclosed copy of this invoice with remittance within thirty (30) days.

(A copy of the publication affidavit is enclosed for your records.)

Sincerely,

tu P. Mila

Justina P. Mickelson Physical Science Researcher Scientist **Designated Basins Branch**

Trans Number: 3629687 6/2/2008 9:32:21 AM Debbie Gonzales (20) Total Trans Amt: \$231,58 CHECK Check Number: 9784 Check Amount: \$231.58

Enclosures (a/s)

Office of the State Engineer 1313 Sherman Street, Suite 818 • Denver, CO 80203 • Phone: 303-866-3581 • Fax: 303-866-3589 www.water.state.co.us



DEPARTMENT OF NATURAL RESOURCES

June 27, 2008

Bill Ritter, Jr. Governor Harris D. Shenman Executive Director Dick Wolfe, P.E. Director

George F. and Evelyn McCune 17480 Meridian Road Elbert, CO 80106-8916

RE: Determination of Water Right

Dear Mr. and Mrs. McCune:

Enclosed is a copy of the Colorado Ground Water Commission's Findings and Order for Determination of Water Right No. 1689-BD, for the allocation of ground water in the Laramie-Fox Hils aquifer. This Findings and Order is the Commission's approval of your application for determination of right to ground water in the above stated aquifer. This document contains important information about your water right and should be reviewed and retained for your records.

As indicated in the Order, a copy of this determination must be recorded by the applicant in the public records of the county – in which the overlying land is located – so that a title examination of the overlying land claimed in the application, or any part thereof, shall reveal this determination. An additional copy of the Findings and Order is enclosed for this purpose.

If you have any questions, please contact this office.

Sincerely,

Justino P. Micas

Justina P. Mickelson Physical Science Researcher Scientist Designated Basins Branch

Enclosures: a/s

Office of the State Engineer 1313 Sherman Street, Suite 818 • Denver, CO 80203 • Phone: 303-866-3581 • Fax: 303-866-3589 www.water.state.co.us .

Colorado Department of Natural Resources	a and the second se
Kejeralo Division of Weiler Resolutions	Colorado.gov Contact Us
Colorado's Well Permit Search	
THIS PAGE IS NOT THE ACTUAL PERMIT The information contained on this page is a summary of the permit file and may not reflect all details of the well permit. (Foll Disclaimer)	
Permit Issued: Completion Status Unknown Receipt: 3628088B Division: 1 Permit #: 1690-BD - Water District: 1 Well Name / #: County: EL PASO Designated Basin: KIOWA-BIJOU Management District: FL PASO WDID: Value Status Unknown Management District: FL PASO	
[-] Imaged Documents - Permit File	
Document Name Date Imaged Annotated Findings & Order for Determination 05/21/2009 No	
[-] Applicant/Contact	
Applicant/Contact Name Mailing Address City/State/Zip MCCUNE GEORGE F & EVELYN 17480 MERIDIAN RD ELBERT, CO 80106-8916	
[-] Location Information Approved Well Location:	
Q40 Q160 Section Township Range PM Footage from Section Lines 24 11.05 65.0W Stath	
Northing (UTM y): 4325550.5 Easting (UTM x): 533176.3 Location Accuracy: Spotted from quarters	
Subdivision Name	
Filing Block Lot	
Parcel ID: Acres in Tract: 900.52	
[-] Permit Details	
Date Issued: 06/25/2008 Date Expires:	
Uses (See <u>Imaged Documents</u> for more infomation) General Use(s): COMMERCIAL Aquifer(s): ARAPAHOE DOMESTIC	
Special Use:	
Area which may be imigated: Annual volume of appropriation:	
Statute: Cross Reference Permit(s): Permit Number Receipt	
Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED	
[-] Construction/Usage Details	
Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use:	
Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate	
[-] Application/Permit History	
Permit Issued 06/25/2008	
Application Received 04/17/2008	
Disclaimer	
*The information contained on this page is a summary of the permit file and may not reflect all details of the well permit. THIS PAGE IS NOT THE ACTUAL PERMIT.	
This page should not be used as a basis for any legal consideration, to determine the allowed uses of the well, to determine construction information, or to determine the terms and conditions under which the well can operate. The complete well permit file should be viewed to obtain details on the allowed uses and other relevant information. A complete copy of this file is available in the "Imaged Documents" section of this page, and can be viewed by opening all of the documents listed under that section (documents will open as pdf files).	
Note that all of the terms and conditions under which a well can operate, particularly for non-exempt wells, may not be specified on the well permit. Wells may also be subject to relevant statutes, rules and decrees. To learn	

more about well permitting In Colorado, please visit <u>DWR's Well Permitting Page</u>. If you have any questions about this well permit file, please contact the <u>DWR Ground Water Information Desk</u>.

Copyright © 2016 Colorado Division of Water Resources. All rights reserved.

Home | Contact Us | Help | Water Links | Colorado.gov | DNR | Privacy Policy | Transparency Online Project (TOP)

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR DETERMINATION OF WATER RIGHT TO ALLOW THE WITHDRAWAL OF GROUND WATER IN THE KIOWA-BIJOU DESIGNATED GROUND WATER BASIN

APPLICANT:	GEORGE F. M	MCCUNE AND EVELYN MCCUNE	Server Contraction		<u>_</u>
AQUIFER:	ARAPAHOE		Stender, Standard	-	14
DETERMINAT	FION NO.:	1690-BD			
			, sam	÷.	ð

J.

In compliance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, George F. McCune and Evelyn McCune (hereinafter "applicant") submitted an application for determination of water right to allow the withdrawal of designated ground water from the Arapahoe Aquifer.

FINDINGS

- 1. The application was received complete by the Colorado Ground Water Commission on April 17, 2008.
- 2. The applicant requests a determination of rights to designated ground water in the Arapahoe Aquifer (hereinafter "aquifer") underlying 900.52 acres, generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6th Principal Meridian, in El Paso County. According to a signed statement dated April 17, 2008, the applicant owns the 900.52 acres of land, as further described in said affidavit which is attached hereto as Exhibit A, and claims control of the ground water in the aquifer underlying this land area.
- 3. The proposed annual amount of ground water to be allocated and withdrawn from the aquifer for intended beneficial uses is the maximum allowable amount.
- 4. The above described land area overlying the ground water claimed by the applicant is located within the boundaries of the Kiowa-Bijou Designated Ground Water Basin. The Colorado Ground Water Commission (hereinafter "Commission") has jurisdiction.
- 5. The applicant intends to apply the allocated ground water to the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The applicant's proposed place of use of the allocated ground water is the above described 900.52 acre land area.
- 6. The quantity of water in the aquifer underlying the 900.52 acres of land claimed by the applicant is 39800 acre-feet. This determination was based on the following as specified in the Designated Basin Rules:

a. The average specific yield of the saturated permeable material of the aquifer underlying the land under consideration that could yield a sufficient quantity of water that may be extracted and applied to beneficial use is 17 percent.

b. The average thickness of the saturated permeable material of the aquifer underlying the land under consideration that could yield a sufficient quantity of water that may be extracted and applied to beneficial use is 260 feet.

- 7. At this time, there is no substantial artificial recharge that would affect the aquifer within a one hundred year period.
- 8. Pursuant to Section 37-90-107(7), C.R.S., and in accordance with the Designated Basin Rules, the Commission shall allocate ground water in the aquifer based on ownership of the overlying land and an aquifer life of one hundred years. Therefore, the maximum allowed average annual amount of ground water in the aquifer that may be allocated for withdrawal pursuant to the data in the paragraphs above for the 900.52 acres of overlying land claimed by the applicant is 398 acre-feet.
- 9. A review of the records in the Office of the State Engineer has disclosed that none of the water in the aquifer underlying the land claimed by the applicant has been previously allocated or permitted for withdrawal.
- 10. Pursuant to Section 37-90-107(7)(c)(III), C.R.S., an approved determination of water right shall be considered a final determination of the amount of ground water so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 11. The ability of wells permitted to withdraw the authorized amount of water from this non-renewable aquifer may be less than the one hundred years upon which the amount of water in the aquifer is allocated, due to anticipated water level declines.
- 12. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of ground water from the aquifer underlying the land claimed by the applicant will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the ground water is nontributary ground water as defined in Rule 4.2.19 of the Designated Basin Rules. No more than 98% of the amount of ground water withdrawn annually shall be consumed, as required by the Designated Basin Rules.
- 13. In accordance with Section 37-90-107(7), C.R.S., upon Commission approval of a determination of water right, well permits for wells to withdraw the authorized amount of water from the aquifer shall be available upon application, subject to the conditions of this determination and the Designated Basin Rules and subject to approval by the Commission.
- 14. The Commission Staff has evaluated the application relying on the claims to control of the ground water in the aquifer made by the applicant.

- 15. In accordance with Sections 37-90-107(7) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on May 8 and May 15, 2008.
- 16. No objections to the determination of water right and proposed allocation of ground water were received within the time limit set by statute.
- 17. In order to prevent unreasonable impairment to the existing water rights of others within the Kiowa-Bijou Designated Ground Water Basin it is necessary to impose conditions on the determination of water right and proposed allocation of ground water. Under conditions as stated in the following Order, no unreasonable impairment of existing water rights will occur from approval of this determination of water right or from the issuance of well permits for wells to withdraw the authorized amount of allocated ground water from the aquifer.

ORDER

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, the Colorado Ground Water Commission orders that the application for determination of rights to designated ground water in the Arapahoe Aquifer underlying 900.52 acres of land, generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6th Principal Meridian, is approved subject to the following conditions:

- 18. The allowed average annual amount of withdrawal of ground water from the aquifer shall not exceed 398 acre-feet. The allowed maximum annual amount of withdrawal may exceed the allowed average annual amount of withdrawal as long as the total volume of water withdrawn does not exceed the product of the number of years since the date of approval of this determination times the allowed average annual amount of withdrawal,
- 19. To conform to actual aquifer characteristics, the Commission may adjust the allowed average annual amount of ground water to be withdrawn from the aquifer based on analysis of geophysical logs or other site-specific data if such analysis indicates that the initial estimate of the volume of water in the aquifer was incorrect.
- 20. The applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- 21. No more than 98% of the ground water withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the water withdrawn is being consumed.
- 22. The use of ground water from this allocation shall be limited to the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The place of use shall be limited to the above described 900.52 acre land area.

- 23. The applicant, or subsequent persons controlling this water right, shall record in the public records of the county in which the claimed overlying land is located notice of transfer of any portion of this water right to another within sixty days after the transfer, so that a title examination of the above described 900.52 acre land area, or any part thereof, shall reveal the changes affecting this water right. Such notice shall consist of a signed and dated deed which indicates the determination number, the aquifer, a description of the above described land area, the annual amount of ground water (acre-feet) transferred, name of the recipient, and the date of transfer.
- 24. Subject to the above conditions, well permits for wells to withdraw the allocated annual amount of water from the aquifer shall be available upon application subject to approval by the Commission and the following conditions:

a. The wells shall be located on the above described 900.52 acre overlying land area.

b. The wells must be constructed to withdraw water from only the Arapahoe Aquifer. Upon application for a well permit to construct such a well, the estimated top and base of the aquifer at the proposed well location will be determined by the Commission and indicated on the approved well permit. Plain non-perforated casing must be installed, grouted and sealed to prevent diversion of ground water from other aquifers and the movement of ground water between aquifers.

c. The entire depth of each well must be geophysically logged <u>prior</u> to installing the casing as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

d. Each well shall be constructed within 200 feet of the location specified on the approved well permit, but must be more than 600 feet from any existing large-capacity well completed in the same aquifer.

e. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and maintained by the well owner and submitted to the Commission upon their request.

f. The well owner shall mark the well in a conspicuous place with the permit number and the name of the aquifer. The well owner shall take necessary means and precautions to preserve these markings.

25. A copy of this Findings and Order shall be recorded by the applicant in the public records of the county in which the claimed overlying land is located so that a title examination of the above described 900.52 acre overlying land area, or any part thereof, shall reveal the existence of this determination.

Page 4

Dated this 25th day of June, 2008.

1 Week

Dick Wolfe, P.E Executive Director Colorado Ground Water Commission

Vinni /s By:_ Keith Vander Horst, P.E. J Jefe Water Resource Engineer

Prepared by: JPM

Page 5

>

92GWS 1 03/2005

EXHIBIT A

1690-BD

Page 1 of 2

STATE OF COLORADO OFFICE OF THE STATE ENGINEER DIVISION OF WATER RESOURCES 1313 Sherman St. Room 821 Denver, CO 80203 (303) 866-3581 Fax (303) 866-3589

Received

APR 1 7 2008

WATER RESOURCES STATE ENGINEER COLO.

NONTRIBUTARY GROUND WATER LANDOWNERSHIP STATEMENT

I (We) George F. NcCune and Evelyn McCune

(Name(s))

claim and say that I (we) am (are) the owner(s) of the following described property consisting of <u>900.52</u> acres in the County of <u>EI Paso</u>.

(Insert the property legal description)

SW/4SW/4 Section 18 and W/2 of the W/2 Section19, T11S, R64W, and S/2SE/4 Section 13

and All of Section 24, T11S R65W, 6th PM, El Paso County, 900.52 acres

See attached Quitclaim Deed dated November 29, 1976, and map.

and, that the ground water sought to be withdrawn from the <u>Arapahoe</u> aquifer underlying the above-described land has not been conveyed or reserved to another, nor has consent been given to its withdrawal by another.

Further, I (we) claim and say that I (we) have read the statements made herein; know the contents hereof; and that the same are true to my (our) knowledge.

Signature

Glorge 7 Mc Cum & Date Eulyn M. McCum

Signature

INSTRUCTIONS:

Please type or print neatly in black or blue ink. This form may be reproduced by photocopy or word processing means. See additional information on the reverse side.

EXHIBIT A 21 **1** 1.5 1690-BD 18 P 20 Page 2 of 2 RECEIVED Beet Copy Available QUITCLAIM DEED APR 1 7 2008 RAY C. McCLINE and GRETA C. McCLINE, as huband and wife, of the County WATAN ALE OUTPORT of El Paso and State of Colorado, for the consideration of One Dollar (\$1.00) and other COLO grad and valuable consideration, in hand paid, hereby sell and quit claim to GEORGE F. 5.2 MCCLINE and EVELYN M. MCCLINE, huntiand and wife, in joint tenancy, of the County of Elbert and State of Calaratio, a one-balf interast in and to all minorals underlying the following described property, including oil and gas, said property lying and being in the . . . County of El Paro and State of Colorado, to wit: The Southwest quarter of the Southwest quarter of Section Eighteen, Township Eliven, Range Shity-four; the West half of the West half of Section Nineteen, Township Eleven, Barge Shity-four; the South half of the Southeast Quarter of Saction Thisteen, Township Eleven, Range Shity-five; All of Section Twenty-fair, Township Eleven, Ringe Shity-five, castifining in all Nine hundred and (Nity-two bundredths (900:52) acres, more or less, according to Government with all its appartenances No DATED and signed this 22 day of Nou. Consideration STATE DOCUMENTS NOV 2 9 1986 nme. · FEE S... STATE OF COLORADO COUNTY OF EL PASO day of le u i

_	ar a h
1.51	COLORADO GROUND WATER COMMISSION
	DIVISION OF WATER RESOURCES
	DEPARTMENT OF NATURAL RESOURCES
	1313 Sherman St, Room 818, Denver, CO 80203

APPLICATION FOR DETERMINATION OF WATER RIGHT WITHIN A DESIGNATED GROUND WATER BASIN PURSUANT TO SECTION 37-90-107(7), C.R.S.

PURSUANT TO SECTION 37-90-107(7), C.R.S. Please note: This application may only be used to apply for a determination of rights to ground water from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifer underlying land areas located within a Designated Ground Water Basin. Review the instructions on the reverse of this form. This form must be completed, signed, dated and submitted to the Ground Water Commission with a non-refundable \$60 filing fee. A separate form must be used for each aquifer determination. Type or print in black ink.

1. APPLICANT INFORMATION				
Name of Applicant				
George F. McCune and Evelyn McCune				
Applicant Mailing Address				
17480 Meridian Road, Elbert, CO 80106-8916				
c/o Colorado Water Plans, P O Box 1955, Elbert, CO 80106				
Applicant Telephone Number (include area code)				
- 303 648-9090 Contact 303 646-4201 719- 495- 2562				
2. AMOUNT OF OVERLYING LAND - the total and area 3. AQUIFER Arapahoe NT				
claimed and described by the applicant in Item #8 below.				
consisting of 900.52 acres.				
4. EXISTING WELLS - Are there any wells located on the claimed and described overlying land? Y	esNo_X			
If yes, provide a complete list of all wells located on the overlying land area as an attachment to this a	pplication.			
5. ANNUAL AMOUNT OF GROUND WATER ~ to be withdrawn, for intended beneficial uses, from	The devices understyles the			
described land area claimed by the applicant in Item #8 below. Please specify one of the following:				
	ble annual acre-feet, excluding			
6. USE OF GROUND WATER - description of intended beneficial uses of the ground water to be with	drawn from the aquiter			
All water withdrawn will be reused, successively used, leased, sold or otherwise disposed of for the following b	eneficial uses: demestic,			
industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscate	rial habitat less than 1000			
square feet and wildlife. The water will be produced for immediate application to said uses, for storage and so uses, for replacement of depletion's from the use of water from other sources and for all other augmentation p	ibsequent application to said			
and so representation a reflection a transfer as or writer from order sources and lot, an other stational b	arposes			
7. PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and	d december of her the second second			
Item #8 below, unless a legal description or accurate scale map is provided which describes an alterna	d described by the applicant in			
8. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall alic	cate ground water from the			
Dawson, Deriver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. F	or this reason, a Nontributary			
Ground Water Landownership Statement (form GWS-1) or Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application.				
9. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein	constitutes perjury in the			
second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I h herein, know the contents thereof, and state that they are true to my knowledge.	ave read the statements			
Signature George 7 MC Curl of Evelyn m. mc Curre Date april	14.2008			
- print name and title George F. McCune and Evelyn McCune, Owners				
	Trans Number: 3628088 K			
FOR OFFICE USE ONLY	W11/2000 1:54:24 FM			
	Geoff Devis (21) Total Trans Amt: \$240.00			
0 1 7	CHECK			
DIV_8_COWD_L_BASIN 2_MD	Check Number: 0724			
	CINECK AMOUNT: \$220.00			

RECEIVED

APR 1 7 2008



COLORADO WATER PLANS

Water Consultants

Colorado Ground Water Commission Division of Water Resources Department Of Natural Resources 1313 Sherman Street - Room 818 Denver, Colorado 80203

Re: Application for Determination of Water Right Client: George F. McCune and Evelyn McCune

Agent: Colorado Water Plans LLC

Colorado Water Plans LLC has prepared the Application for Determination of Water Right with my permission as Signatory and Landowner. Colorado Water Plans LLC shall have full representational power as "Agent" in regards to this Application for Determination of Water Right, water issues, water facts, water calculations, submittals to governmental agencies, reporting forms, newspaper public notifications, applications, or any other needs within the confines of the Contract for Services. This document shall authorize my "Agent" Colorado Water Plans LLC to manage and conduct all affairs and to exercise all my rights and powers within the enclosed Application for Determination of Water Right.

Colorado Water Plans has no rights, implied or warranted outside the affairs of this agreement, and subject to other provisions of this document, disclaim any interest which might otherwise be transferred or distributed to me from other person or entity.

Client:

ange 7 Mc Come + Earlyn M. Ing Come By:

Date: 4-14-08

Colorado Water Plans LLC Craig L. Curl Dr. W. Jerry Koch Lisa S. Weinstein, Bsq. #35688

P.O. Box 1955 / Elizabeth / Colorado / 80107 Office: 303/646-3895 Fax: 303/646-9655

REPETER

2008

DETERMINATION OF WATER RIGHT SECTION 37-90-107(7)

APPLICANT: George F. McCune and Evelyn McCune

BASIN: Kiowa-Bijou

COUNTY: El Paso

AQUIFER: Arapahoe RECEIPT NO. 36280888

NUMBER OF ACRES IN TRACT: 900.52 acres

GENERAL LOCATION: SW/4SW/4, Section 18 and W/2NW/4, W/2SW/4, Section 19, T11S, R64W, 6th PM, S/2SE/4, Section 13 and All of Section 24, T11S, R65W, 6th PM.

AQUIFER DATA

AMOUNT AVAILABLE FOR APPROPRIATION: (260 feet SS)(900.52 Acres)(0.17 SY) = 39803 AF 398.0 AFyr

ADJUSTMENTS: None

ANNUAL AMOUNT: 398.0 AFyr

PRE.NOV.19, 1973 WELLS (COMPLETED IN AQUIFER) IN VICINITY: N/A

OVERLAP AREA: N/A

AREA CHECKED: Sections 18, 19, and 30, T11S, R64W Sections 13, 14, 23, 24, 25, and 26, T11S, R65W

SMALL-CAPACITY WELLS (COMPLETED IN AQUIFER) LOCATED ON CLAIMED TRACT: N/A

REPLACEMENT WATER STATUS OF CLAIMED LAND AREA: Nontributary


REPLACEMENT PLAN REQUIRED: Not Required


AQUIFER INTERVAL (CENTRAL DATA POINT): 1810 feet to 2310 feet below ground surface


COMMENTS: The SS was considered 260 feet based on the SS map for the Arapahoe aquifer.

Evaluated by: Justina Mickelson, Ground Water Commission Staff Reviewed by CBG

C:\Documents and Settings\jpmWy Documents\Water Right Aps\McCune\McCune Arapahoe Determ.doc







DUBLISHER'S AFFIDAVIT

STATE OF COLORADO

I, Susan Lister, do solemnly affirm that I m the Publisher of RANCHLAND NEWS; tat the same is a weekly newspaper pubshed at Simla, County of Elbert, State of olorado, and has a general circulation verein; that said newspaper has been connuously and uninterruptedly published in said county of Elbert for a pariod of at least 52 onsecutive weeks next prior to the first pubsation of the annexed notice, that said newsaper is entered in the post office at Calhan, olorado as second class mail matter and that aid newspaper is a newspaper within the leaning of the Act of the General Assembly the State of Colorado, approved March 30, 923, and entitled "Legal Notices and Adversements," with other Acts relating to the printg and publishing of legal notices and adartisements. That the annexed notice was ublished in the regular and entire issue of ald newspaper, once each week for 100 scessive weeks; that the first publication of aid notice was in the issue of said newspaar dated:

may 8.2008


It the last publication of said notice was in e issue of said newspaper dated:

lay 2008 11

Id that copies of each number of said paper which said notice and/or list was published are delivered by carriers or transmitted by ail to each of the subscribers of said newsaper, Ranchland News, according to the xusterned mode of busiquess in this office.

0 Publisher

The above certificate of publication was ibscribed and affirmed to before me, a Nory Public, to be the identical person deribed in the above certificate, on the



y Notary Public Commission Expiration Date)

Determinations of Water

Right

REFORE THE COLORADO GROUND WATER COMMENSION KIOWA-BLIOU DESIGNATED GROUND WATER BASIN- EL PASO COUNTY TAKE NOTICE that pursuant to Section 37-90-107(7), C.R.S., George F. McCone and Rvelya McCane (harvisafler "applicant") have applied for determinations of water right to allow the withdrawal of designated ground water from the Lammie-Fox Hills, Arapahos, Denver, and Dawnon aquifiers underlying 900.52 same generally described as the SW1/4 of the SW1/4, Section 14, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Rings 64 West of the 6th PM and the S1/2 of the SE1/4, Section 15 and all of Section 24, Township 11 South, Range 65 West of the 6ª PML licent obtate dwinenitip of this land and The are control of the ground water in the above describ squifter under this property. The ground water allocations from these squifters will be used on the described property for the following beneficial men domentic, industrial, commercial, internian, sture pouds and piscatorial habitat loss than 1000 square fost and wildlift, replacement and all other augmentation purposes. The territory allowable summil amount of ground water to each agilifer underlying the described property will be · hetroolle

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, the Colorado Ground Water Commission shall allocate ground water from the above-described. equifters based on ownership of the overlying land and an aquifer life of one hundred years. A preliminary evaluation of the applications by the Commission Staff finds the annual amount of water available, for allocation from each of the described equifers underlying the abovedescribed property to be as follows: 263.4 acrofeet for the Laramie-Fox Hills, 398.0 acre-feet for the Arapahoe, 528.2 acre-first for the Denver. and \$19.5 for the Dewson subject to final staff evaluation. The estimated available annual acro-foet allocation amount for each, squifte indicated above may be increased or decreased by the Commission to conform to the actual equifier characteristics, based upon site specific data.

In accordance with Rule 5.3.6 of the Designated Basin Rules, the Commission Staff's preliminary evaluation of the applications finds the replacement water requirement status for the above aquifers underlying the shows-described property to be as follows: nontributary for the Laramio-Fox Hills, nontributary for the Aragabos, nontributary for the Desver, and nonnoutributary (actual impact replacement) for the Desired.

Dawson. Upon Commission approvel of, these determinations of water right, well journing for wells to withdraw the allocation floor a specific aquifer shall be available upon application, subject to the conditions of the determinations and the Dasignative Basin Rules and subject to opproval by the Commission. Such wells sumt becompleted in the specified aquifer and located on the above described 900.52 are property. Well parants for wells to withdraw ground water from the Davison aquifar would also be athject to the contributes of a replacement plan to be approved by the Councilation.

Any person wishing to object to the approval of these determinations of water right must do so in writing, briefly anting the name of the objection and indicating the showe applicant, property descriptions and the specific aquifirm that are the subject of the objection. The objection, must be accompanied by a \$10 per aquifir for and must be received by the Commission Staff, Colorado [Ground Water Commission, \$18 Contenda] Building, 1313 Sherman Street, Deuver, Colorado \$0203, by June 16, 2008.

ł.

Final Publication May 8, 2008 Final Publication May 15, 2008 in Ranchland News Logal No. 12,936

RECEIVED

MAY 1 9 2008

WATTR PRODUCES

77



DEPARTMENT OF NATURAL RESOURCES

DIVISION OF WATER RESOURCES

Bill Ritter, Jr. Governor

June 27, 2008

Harris D. Sherman , Executive Director Dick Wolfe, P.E. Director

George F. and Evelyn McCune 17480 Meridian Road Elbert, CO 80106-8916

RE: Determination of Water Right

Dear Mr. and Mrs. McCune:

Enclosed is a copy of the Colorado Ground Water Commission's Findings and Order for Determination of Water Right No. 1690-BD, for the allocation of ground water in the Arapahoe aquifer. This Findings and Order is the Commission's approval of your application for determination of right to ground water in the above stated aquifer. This document contains important information about your water right and should be reviewed and retained for your records.

As indicated in the Order, a copy of this determination must be recorded by the applicant in the public records of the county – in which the overlying land is located – so that a title examination of the overlying land claimed in the application, or any part thereof, shall reveal this determination. An additional copy of the Findings and Order is enclosed for this purpose.

If you have any questions, please contact this office.

Sincerely,

Jutto P. Micol

Justina P. Mickelson Physical Science Researcher Scientist Designated Basins Branch

Enclosures: a/s

Office of the State Engineer 1313 Sherman Street, Suite 818 • Denver, CO 80203 • Phone: 303-866-3581 • Fax: 303-866-3589 www.water.state.co.us

Norado Department of Natural Resources	Colorado.gov Contact U:
la laraja Divisia di	Colorado.gov () Collact C.
Neiler Resources	
lorado's Well Permit Search	
THIS PAGE IS NOT THE ACTUAL PERMIT	
The information contained on this page is a summary of the permit file and may not reflect all details of the well permit. (full biodisment)	
Permit Issued; Completion Status Unknown Help Last Refresh: 12/6/2016 12:03:01 AM	A
Receipt: 3628088C Division: 1	
Permit #: 1691-BD - Water District: 1 Weil Name / #: County: EL PASO	
Well Name / #: County: EL PASU Designated Basin: KIOWA-BIJOU Management District:	
Case Number:	
WDID:	
[-] Imaged Documents - Permit File	
Document Name Date Image Annotated Findings & Order for Determination 05/21/2009 No	
[-] Applicant/Contact Applicant/Contact Name Malling Address City/State/Zip	
MCCUNE GEORGE F & EVELYN 17480 MERIDIAN RD ELBERT, CO 80106-8916	
[-] Location Information	
Approved Well Location:	
Q40 Q160 Section Township Range PM Footage from Section Lines 24 11.0S 65.0W Sixth	
Northing (UTM y): 4325550.5 Easting (UTM x): 533176.3	
Location Accuracy: Spotted from quarters	
Subdivision Name	
Filing Block Lot	
Parcel ID: Acres in Tract: 900.52	
[-] Permit Details Date Issued: 06/25/2008 Date Expires:	
Uses (See <u>Imaged Documents</u> for more infomation)	
General Use(s): COMMERCIAL Aquifer(s): DENVER	
DOMESTIC	
Special Use:	
Special Use: Area which may be irrigated:	
Area which may be irrigated: Annual volume of appropriation:	
Area which may be irrigated: Annual volume of appropriation: Statute:	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt	
Area which may be irrigated: Annual volume of appropriation: Statute:	
Area which may be irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date:	
Area which may be irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Well Plugged: 1st Beneficial Use:	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Well Construction Date: Well Plugged: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Well Construction Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008 Application Received 04/17/2008	
Area which may be Irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008 Application Received 04/17/2008 Disclaimer *The Information contained on this page is a summary of the permit file and may not reflect all details of the well permit. THIS PAGE IS NOT THE ACTUAL PERMIT.	
Area which may be irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Construction Date: Well Construction Date: Pump Installation Date: Well Plugged: Ist Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008 Application Received 04/17/2008 Disclaimer **The Information contained on this page is a summary of the permit file and may not reflect all details of the well permit. THIS PAGE IS NOT THE ACTUAL PERMIT. This page should not be used as a basis for any legal consideration to determine the allowed uses of the useull to determine on the information on to determine the terms and conditions under	
Area which may be irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008 Application Received 04/17/2008 Disclaimer *The Information contained on this page is a summary of the permit file and may not reflect all details of the well permit. THIS PAGE IS NOT THE ACTUAL PERMIT. This page should not be used as a basis for any legal consideration, to determine the allowed uses of the well, to determine construction Information, or to determine the terms and conditions under well remit file should be viewed to obtain details on the allowed	
Area which may be irrigated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008 Application Received 04/17/2008 Disclaimer	
Area which may be Irligated: Annual volume of appropriation: Statute: Cross Reference Permit(s): Permit Number Receipt Comments: DETER ISSUED [-] Construction/Usage Details Well Construction Date: Pump Installation Date: Well Plugged: 1st Beneficial Use: Elevation Depth Perforated Casing (Top) Perforated Casing (Bottom) Static Water Level Pump Rate [-] Application/Permit History Permit Issued 06/25/2008 Application Received 04/17/2008 Disclaimer **The Information contained on this page Is a summary of the permit file and may not reflect all details of the well permit. THIS PAGE IS NOT THE ACTUAL PERMIT. This page should not be used as a basis for any legal consideration, to determine the allowed uses of the well, to determine construction Information, or to determine the terms and conditions under the well well to permit file and conditions under the well well of the well. The complete well net file file well as on the allowed	

more about well permitting in Colorado, please visit <u>DWR's Well Permitting Page</u>. If you have any questions about this well permit file, please contact the <u>DWR Ground Water Information Desk</u>.

Copyright © 2016 Colorado Division of Water Resources. All rights reserved.

Home | Contact Us | Help | Water Links | Colorado.gov | DNR | Privacy Policy | Transparency Online Project (TOP)

COLORADO GROUND WATER COMMISSION FINDINGS AND ORDER

IN THE MATTER OF AN APPLICATION FOR DETERMINATION OF WATER RIGHT TO ALLOW THE WITHDRAWAL OF GROUND WATER IN THE KIOWA-BIJOU DESIGNATED GROUND WATER BASIN

APPLICANT:	GEORGE F. N	ICCUNE AND EVELYN MCCUNE	And the second s
AQUIFER:	DENVER		lenne Allenne Allenne
DETERMINATI	ON NO.:	1691-BD	

In compliance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, George F. McCune and Evelyn McCune (hereinafter "applicant") submitted an application for determination of water right to allow the withdrawal of designated ground water from the Denver Aquifer.

FINDINGS

- 1. The application was received complete by the Colorado Ground Water Commission on April 17, 2008.
- 2. The applicant requests a determination of rights to designated ground water in the Denver Aquifer (hereinafter "aquifer") underlying 900.52 acres, generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6th Principal Meridian, in El Paso County. According to a signed statement dated April 17, 2008, the applicant owns the 900.52 acres of land, as further described in said affidavit which is attached hereto as Exhibit A, and claims control of the ground water in the aquifer underlying this land area.
- 3. The proposed annual amount of ground water to be allocated and withdrawn from the aquifer for intended beneficial uses is the maximum allowable amount.
- 4. The above described land area overlying the ground water claimed by the applicant is located within the boundaries of the Kiowa-Bijou Designated Ground Water Basin. The Colorado Ground Water Commission (hereinafter "Commission") has jurisdiction.
- 5. The applicant intends to apply the allocated ground water to the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The applicant's proposed place of use of the allocated ground water is the above described 900.52 acre land area.
- 6. The quantity of water in the aquifer underlying the 900.52 acres of land claimed by the applicant is 52800 acre-feet. This determination was based on the following as specified in the Designated Basin Rules:

a. The average specific yield of the saturated permeable material of the aquifer underlying the land under consideration that could yield a sufficient quantity of water that may be extracted and applied to beneficial use is 17 percent.

b. The average thickness of the saturated permeable material of the aquifer underlying the land under consideration that could yield a sufficient quantity of water that may be extracted and applied to beneficial use is 345 feet.

- 7. At this time, there is no substantial artificial recharge that would affect the aquifer within a one hundred year period.
- 8. Pursuant to Section 37-90-107(7), C.R.S., and in accordance with the Designated Basin Rules, the Commission shall allocate ground water in the aquifer based on ownership of the overlying land and an aquifer life of one hundred years. Therefore, the maximum allowed average annual amount of ground water in the aquifer that may be allocated for withdrawal pursuant to the data in the paragraphs above for the 900.52 acres of overlying land claimed by the applicant is 528 acre-feet.
- 9. A review of the records in the Office of the State Engineer has disclosed that none of the water in the aquifer underlying the land claimed by the applicant has been previously allocated or permitted for withdrawal.
- 10. Pursuant to Section 37-90-107(7)(c)(III), C.R.S., an approved determination of water right shall be considered a final determination of the amount of ground water so determined; except that the Commission shall retain jurisdiction for subsequent adjustment of such amount to conform to the actual local aquifer characteristics from adequate information obtained from well drilling or test holes.
- 11. The ability of wells permitted to withdraw the authorized amount of water from this non-renewable aquifer may be less than the one hundred years upon which the amount of water in the aquifer is allocated, due to anticipated water level declines.
- 12. In accordance with Rule 5.3.6 of the Designated Basin Rules, it has been determined that withdrawal of ground water from the aquifer underlying the land claimed by the applicant will not, within one hundred years, deplete the flow of a natural steam or its alluvial aquifer at an annual rate greater than one-tenth of one percent of the annual rate of withdrawal and, therefore, the ground water is nontributary ground water as defined in Rule 4.2.19 of the Designated Basin Rules. No more than 98% of the amount of ground water withdrawn annually shall be consumed, as required by the Designated Basin Rules.
- 13. In accordance with Section 37-90-107(7), C.R.S., upon Commission approval of a determination of water right, well permits for wells to withdraw the authorized amount of water from the aquifer shall be available upon application, subject to the conditions of this determination and the Designated Basin Rules and subject to approval by the Commission.
- 14. The Commission Staff has evaluated the application relying on the claims to control of the ground water in the aquifer made by the applicant.

- 15. In accordance with Sections 37-90-107(7) and 37-90-112, C.R.S., the application was published in the Ranchland News newspaper on May 8 and May 15, 2008.
- 16. No objections to the determination of water right and proposed allocation of ground water were received within the time limit set by statute.
- 17. In order to prevent unreasonable impairment to the existing water rights of others within the Kiowa-Bijou Designated Ground Water Basin it is necessary to impose conditions on the determination of water right and proposed allocation of ground water. Under conditions as stated in the following Order, no unreasonable impairment of existing water rights will occur from approval of this determination of water right or from the issuance of well permits for wells to withdraw the authorized amount of allocated ground water from the aquifer.

ORDER

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, the Colorado Ground Water Commission orders that the application for determination of rights to designated ground water in the Denver Aquifer underlying 900.52 acres of land, generally described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SE1/4, Section 13 and all of Section 24, Township 11 South, Range 65 West of the 6th Principal Meridian, is approved subject to the following conditions:

- 18. The allowed average annual amount of withdrawal of ground water from the aquifer shall not exceed 528 acre-feet. The allowed maximum annual amount of withdrawal may exceed the allowed average annual amount of withdrawal as long as the total volume of water withdrawn does not exceed the product of the number of years since the date of approval of this determination times the allowed average annual amount of withdrawal amount of withdrawal.
- 19. To conform to actual aquifer characteristics, the Commission may adjust the allowed average annual amount of ground water to be withdrawn from the aquifer based on analysis of geophysical logs or other site-specific data if such analysis indicates that the initial estimate of the volume of water in the aquifer was incorrect.
- 20. The applicant may pump the allowed average annual amount of withdrawal and the allowed maximum annual amount of withdrawal from one or more wells of a well field in any combination, so long as the total combined withdrawal of the wells does not exceed the amounts described in this Order.
- 21. No more than 98% of the ground water withdrawn annually shall be consumed. The Commission may require well owners to demonstrate periodically that no more than 98% of the water withdrawn is being consumed.
- 22. The use of ground water from this allocation shall be limited to the following beneficial uses: domestic, industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife, replacement and all other augmentation purposes. The place of use shall be limited to the above described 900.52 acre land area.

- 23. The applicant, or subsequent persons controlling this water right, shall record in the public records of the county in which the claimed overlying land is located notice of transfer of any portion of this water right to another within sixty days after the transfer, so that a title examination of the above described 900.52 acre land area, or any part thereof, shall reveal the changes affecting this water right. Such notice shall consist of a signed and dated deed which indicates the determination number, the aquifer, a description of the above described land area, the annual amount of ground water (acre-feet) transferred, name of the recipient, and the date of transfer.
- 24. Subject to the above conditions, well permits for wells to withdraw the allocated annual amount of water from the aquifer shall be available upon application subject to approval by the Commission and the following conditions:

a. The wells shall be located on the above described 900.52 acre overlying land area.

b. The wells must be constructed to withdraw water from only the Denver Aquifer. Upon application for a well permit to construct such a well, the estimated top and base of the aquifer at the proposed well location will be determined by the Commission and indicated on the approved well permit. Plain non-perforated casing must be installed, grouted and sealed to prevent diversion of ground water from other aquifers and the movement of ground water between aquifers.

c. The entire depth of each well must be geophysically logged <u>prior</u> to installing the casing as set forth in Rule 9 of the Statewide Nontributary Ground Water Rules, 2 CCR 402-7.

d. Each well shall be constructed within 200 feet of the location specified on the approved well permit, but must be more than 600 feet from any existing large-capacity well completed in the same aquifer.

e. A totalizing flow meter or other Commission approved measuring device shall be installed on each well and maintained in good working order by the well owner. Annual diversion records shall be collected and maintained by the well owner and submitted to the Commission upon their request.

f. The well owner shall mark the well in a conspicuous place with the permit number and the name of the aquifer. The well owner shall take necessary means and precautions to preserve these markings.

25. A copy of this Findings and Order shall be recorded by the applicant in the public records of the county in which the claimed overlying land is located so that a title examination of the above described 900.52 acre overlying land area, or any part thereof, shall reveal the existence of this determination.

Page 4

Dated this <u>. 25 Th</u> day of <u>June</u> 2008.

1. Week

Dick Wolfe, P.E **Executive Director** Colorado Ground Water Commission

J. Manuster 1.10. mil By:_ Keith Vander Horst, PEE

Water Resource Engineer

Prepared by: JPM

Page 5

 $\sum_{i=1}^{n}$

92GWS 1 03/2005

EXHIBIT A

1691-BD

Page 1 of 2

STATE OF COLORADO OFFICE OF THE STATE ENGINEER DIVISION OF WATER RESOURCES 1313 Sherman St. Room 821 Denver, CO 80203 (303) 866-3581 Fax (303) 866-3589

BECEIVED

APR 1 7 2008

WATTE RESOURCES COLO

NONTRIBUTARY GROUND WATER LANDOWNERSHIP STATEMENT

I (We) George F. McCune and Evelyn McCune

(Name(s))

claim and say that I (we) am (are) the owner(s) of the following described property consisting of 900.52 acres in the County of El Paso State of Colorado:

(Insert the property legal description)

SW/4SW/4 Section 18 and W/2 of the W/2 Section19, T11S, R64W, and S/2SE/4 Section 13

and All of Section 24, T11S R65W, 6th PM, El Paso County, 900.52 acres

See attached Quitclaim Deed dated November 29, 1976, and map.

and, that the ground water sought to be withdrawn from the Denver aquifer underlying the above-described land has not been conveyed or reserved to another, nor has consent been given to its withdrawal by another.

Further, I (we) claim and say that I (we) have read the statements made herein; know the contents hereof; and that the same are true to my (our) knowledge.

Signature

George 9 Mc Cune Date Evelyn Mr. Mc Cum

Signature

INSTRUCTIONS:

Please type or print neatly in black or blue ink. This form may be reproduced by photocopy or word processing means. See additional information on the reverse side.

EXHIBIT A 1691-BD . Na sta 5 8 P R. Page 2 of 2 RECEIVED QUITCLAIM DEED Boot COPY Available APR 1 7 2008 **L**OOS RAY C. McCUNE and GRETA C. McCUNE, as huband and wife, of the County Wares Provide And County of El Paro and State of Colorado, for the consideration of One Dollar (\$1.00) and other COLO good and valuable considuration, in hand paid, hereby sell and guit claim to GEORGE F. McCLINE and EVELYN M. McCUNE, husband and wife, in joint tenancy, of the County ·.... of Elbert and State of Colorado, a one-half interest in and to all minerals underlying the following described property, including oil and gas, said property lying and being in the County of El Paus and State of Colorado, to wit: The Southwest quarter of the Southwest quarter of Section Eighteen, Township Eleven, Range Shity-four; the West half of the West half of Section Nineteen, Township Eleven, Range Shity-four; the South half of the Southeast Quarter of Section Thirteen, Township Eleven, Range Shity-five; All of Section Tweaty-four, Township Eleven, Range Shity-five, containing in all Nine hindred and filty-two hundredths (900:52) acres, more or less, according to Government Sections. with all its applatenances. Nø DATED and signed this 22 day of Nou. Consideration STATE DOCU NOV 2 9 1926 FEE & Dome STATE OF COLORADO.) COUNTY OF EL PASO The foregoing instrument was acknowledged before me this 2) day of)ov: . . . e ĝ . \$

DIVISION OF WATER RESOURCES DEPARTMENT OF NATURAL RESOURCES 1313 Sherman St, Room 818, Denver, CO 80203 APPLICATION FOR DETERMINATION OF WATER RIGHT

COLORADO GROUND WATER COMMISSION

1.

منطئه

APPLICATION FOR DETERMINATION OF WATER RIGHT WITHIN A DESIGNATED GROUND WATER BASIN PURSUANT TO SECTION 37-90-107(7), C.R.S.

Please note: This application may only be used to apply for a determination of rights to ground water from the Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifer underlying land areas located within a Designated Ground Water Basin. Review the instructions on the reverse of this form. This form must be completed, signed, dated and submitted to the Ground Water Commission with a non-refundable \$60 filing fee. A separate form must be used for each aquifer determination. Type or print in black ink.

1. APPLICANT INFORMATION
Name of Applicant
George F. McCune and Evelyn McCune
Applicant Mailing Address
17480 Meridian Road, Elbert, CO 80106-8916 c/o Colorado Water Plans, P O Box 1955, Elbert, CO 80106
Applicant Lelephone Number (include area code)
-303 648-9090- Contact 303 646-4201 719- 495-2562
2. AMOUNT OF OVERLYING LAND - the total and area claimed and described by the applicant in Item #8 below, consisting of 900.52 acres.
EXISTING WELLS – Are there any wells located on the claimed and described overlying land? Yes No _X
 ANNUAL AMOUNT OF GROUND WATER – to be withdrawn, for intended beneficial uses, from the aquifer underlying the described land area claimed by the applicant in Item #8 below. Please specify one of the following:
Maximum allowable annual acre-feet annually Maximum allowable annual acre-feet, excluding acre-feet from that amount
6. USE OF GROUND WATER - description of intended beneficial uses of the ground water to be withdrawn from the aquifer
All water withdrawn will be reused, successively used, leased, sold or otherwise disposed of for the following beneficial uses: domestic,
industrial, commercial, irrigation, augmentation, stock watering, recreational water feature ponds and piscatorial habitat less than 1000 square feet and wildlife. The water will be produced for immediate application to said uses, for storage and subsequent application to said uses, for replacement of depletion's from the use of water from other sources and for all other augmentation purposes
7. PLACE OF USE - of the ground water shall be considered to be that overlying land area claimed and described by the applicant in Item #6 below, unless a legal description or accurate scale map is provided which describes an alternate/additional place of use.
8. REQUIRED LANDOWNERSHIP DOCUMENTATION - The Ground Water Commission shall allocate ground water from the
Dawson, Denver, Arapahoe or Laramie-Fox Hills aquifer on the basis of ownership of overlying land. For this reason, a Nontributary Ground Water Landownership Statement (form GWS-1) or Nontributary Ground Water Consent Claim (form GWS-48), including a description of the overlying land area subject to this determination, must be submitted as an attachment to the application.
9. SIGNATURE OF APPLICANT - must be original signature - The making of false statements herein constitutes perjury in the
second degree, which is punishable as a class 1 misdemeanor pursuant to C.R.S. 24-4-104(13)(a). I have read the statements therein, know the contents thereof, and state that they are true to my knowledge.
Signature George 7 Ma Cume Date
Endra The Shall
- print name and title George F. McCune and Evelyn McCune, Owners
4/772008 1:34/24 01
FOR OFFICE USE ONLY Geoff Devis (21) Total Trans Amt: \$240.00
DIVCOWDMD

RECEIVED

APR 1 7 2008

WATER RESOURCES STATE ENGINEER COLO.

COLORADO WATER PLANS

Water Consultants

Colorado Ground Water Commission Division of Water Resources Department Of Natural Resources 1313 Sherman Street - Room 818 Denver, Colorado 80203

Re: Application for Determination of Water Right Client: George F. McCune and Evelyn McCune

Agent: Colorado Water Plans LLC

Colorado Water Plans LLC has prepared the Application for Determination of Water Right with my permission as Signatory and Landowner. Colorado Water Plans LLC shall have full representational power as "Agent" in regards to this Application for Determination of Water Right, water issues, water facts, water calculations, submittals to governmental agencies, reporting forms, newspaper public notifications, applications, or any other needs within the confines of the Contract for Services. This document shall authorize my "Agent" Colorado Water Plans LLC to manage and conduct all affairs and to exercise all my rights and powers within the enclosed Application for Determination of Water Right.

Colorado Water Plans has no rights, implied or warranted outside the affairs of this agreement, and subject to other provisions of this document, disclaim any interest which might otherwise be transferred or distributed to me from other person or entity.

Client: Floring=7 Mc Come + Evelyn M. Mc Que By:

Date: 4-14-08

Colorado Water Plans LLC Craig L. Curl Dr. W. Jerry Koch Lisa S. Weinsteiti, Jsq. #35688

Date:

P.O. Box 1955 / Elizabeth / Colorado / 80107 Office: 303/646-3895 Fax: 303/646-9655

RECEIVED

PR 1 7 2008

DETERMINATION OF WATER RIGHT SECTION 37-90-107(7)

APPLICANT: George F. McCune and Evelyn McCune

BASIN: Kiowa-Bijou

COUNTY: El Paso

AQUIFER: Denver RECEIPT NO. 3628088C

NUMBER OF ACRES IN TRACT: 900.52 acres

GENERAL LOCATION: SW/4SW/4, Section 18 and W/2NW/4, W/2SW/4, Section 19, T11S, R64W, 6th PM, S/2SE/4, Section 13 and All of Section 24, T11S, R65W, 6th PM.

AQUIFER DATA

AMOUNT AVAILABLE FOR APPROPRIATION: (345 feet SS)(900.52 Acres)(0.17 SY) = 52816 AF 528.2 AFyr

ADJUSTMENTS: None

ANNUAL AMOUNT: 528.2 AFyr

PRE.NOV.19, 1973 WELLS (COMPLETED IN AQUIFER) IN VICINITY: N/A

OVERLAP AREA: N/A

AREA CHECKED: Sections 18, 19, and 30, T11S, R64W Sections 13, 14, 23, 24, 25, and 26, T11S, R65W

SMALL-CAPACITY WELLS (COMPLETED IN AQUIFER) LOCATED ON CLAIMED TRACT: N/A

REPLACEMENT WATER STATUS OF CLAIMED LAND AREA: Nontributary


REPLACEMENT PLAN REQUIRED: Not Required


AQUIFER INTERVAL (CENTRAL DATA POINT): 970 feet to 1770 feet below ground surface


COMMENTS: The SS was considered 345 feet based on the SS map for the Denver aquifer.

Evaluated by: Justina Mickelson, Ground Water Commission Staff Reviewed by COC

C:\Documents and Settings\jpm\My Documents\Water Right Aps\McCune\McCune Derver Determ.doc







PUBLISHER'S AFFIDAVIT

COUNTY OF ELBERT

I, Susan Lister, do solemnly affirm that I m the Publisher of RANCHLAND NEWS; at the same is a weekly newspaper pubshed at Simia, County of Elbert, State of clorado, and has a general circulation terein; that said newspaper has been connuously and uninterruptedly published in said ounty of Elbert for a period of at least 52 onsecutive weeks next prior to the first pubcation of the annexed notice, that said newsaper is entered in the post office at Calhan, olorado as second class mall matter and that aid newspaper is a newspaper within the leaning of the Act of the General Assembly I the State of Colorado, approved March 30. 923, and entitled "Legal Notices and Adversements," with other Acts relating to the printg and publishing of legal notices and adartisements. That the annexed notice was blished in the regular and entire issue of aid newspaper, once each week for two iccessive weeks; that the first publication of aid notice was in the issue of said newspaer dated:

May 8 2008


to the last publication of said notice was in e issue of said.newspaper dated;

lay 2008

Ind that copies of each number of said paper which said notice and/or list was published are delivered by carriers or transmitted by all to each of the subscribers of said newssper, Ranchland News, according to the scustoyned mode of busigess in this office.

1 ale 3 Publisher

The above certificate of publication was bscribed and affirmed to before me, a Nory Public, to be the identical person deribed in the above certificate, on the



y Notary Public Commission Expiration Date)

Determinations of Water . . . Right BEFORE THE COLORADO GROUND WATER COMMESSION KIOWA-BUOU DESIGNATED GROUND WATER BASIN- EL PASO COUNTY TAKE NOTICE that , purposet , to Socia 37-90-107(7), C.R.S., George F. McCune and Evelyn McCure (hereinsther "applican") have applied for determinations of water right to allow the withdrawal of designated ground water from the Lammie-Fox Hills, Arapalne, Denver, and Dawnoi squiftre underlying 900.52 sures particully described as the SW1/4 of the SW1/4, Section 18, the W1/2 of the NW1/4 and the W1/2 of the SW1/4, Section 19, Township 11 South, Range 64 West of the 6th PM and the S1/2 of the SEL/4, Section 15 and all of Section 24, Township 11 South, Range 65 West of the 6" PM. The applicant chains ownership of this land and control of the ground water in the above described aquifies under this property. The ground water allocations from these aquifies will be used on the described property for the following beneficial une: dermite, industrial, commercial, inigation, augmentation, stock watering, necreational water feature pende and piscatorial habitat less than 1000 square fost and wildlife, repl rement and all other augmentation purposes. The constitutes allowable amount of ground water in each aquifer underlying the described property will be allocated.

In accordance with Section 37-90-107(7), C.R.S., and the Designated Basin Rules, 2 CCR 410-1, the Colorado Ground Water Consulation shall allocate ground water from the above-described equifies based on ownership of the overlying and and an aquifer life of one handred years. A preliminary evaluation of the applications by fao Commission Staff finds the annual encount of weter available, for allocation from such of the described aquifers underlying the abovedescribed property to be as follows: 263.4 acrofost for the Lytumie-Fox Hills, 398.0 acre-fast for the Ampahos, 528.2 acre-feet for the Denver, and \$19.5 for the Dawnon subject to final staff evaluation. The estimated svailable, annual acco-fact, allocation, amount, for each aquifier indicated above may be increased or decreased by ad by the Commission to conform to the actual equifer ch noteristics, based upon aite specific data.

In accordance with Rule 5.3.6 of the Designated Basin Rules, the Commission Staff's preliminary evaluation of the applications finds the replacement water requirement status for the above aquifes underlying the above-described property to be as follows: nontributary for the Laurane-Fox Hills, nontributary for the Argunhoe, nontributary for the Deaver, and notnontributary (actual impact replacement) for the Dawson.

Upon Commission approval of these determinations of water right, well permits for wells to withdraw the allowed allocation from a specific quiltr shall be available upon application, subject to the conditions of the determination and the Dasignapied Basis Rules and subject to approval by the Commission, Such wells must be completed in the specified squifer and located on the slove described 900.52 areo property. Well permits for wells to withdraw ground water from the Davyce aquifer would also be subject to the conditions of a sephacement plan to be approved by the Commission.

Any permits withing to object to the approval of these deterministices of water right sound do ao in writing, helefly stating the mature of the objection and indicating the above applicant, property description and the specific aquifers that are the subject of the objection. The objection must be accompanied by, a \$10 per aquifers the and must ; be received by the Commission Staff, Colorado Ground Water Commission, \$18 Contended 80203, by June 16, 2008.

à.

First Publication May 8, 2008 Final Publication May 15, 2008 in Ranchland News Legal No. 12,936

RECEIVED

MAY 1 9 2008

WATER CONNECTS 0711-111-140608 0711-111-140608

77.



DEPARTMENT OF NATURAL RESOURCES

DIVISION OF WATER RESOURCES

June 27, 2008

Bill Ritter, Jr. Governor Harris D. Sherman Executive Director Dick Wolfe, P.E. Director

George F. and Evelyn McCune 17480 Meridian Road Elbert, CO 80106-8916

RE: Determination of Water Right

Dear Mr. and Mrs. McCune:

Enclosed is a copy of the Colorado Ground Water Commission's Findings and Order for Determination of Water Right No. 1691-BD, for the allocation of ground water in the Denver aquifer. This Findings and Order is the Commission's approval of your application for determination of right to ground water in the above stated aquifer. This document contains important information about your water right and should be reviewed and retained for your records.

As indicated in the Order, a copy of this determination must be recorded by the applicant in the public records of the county – in which the overlying land is located – so that a title examination of the overlying land claimed in the application, or any part thereof, shall reveal this determination. An additional copy of the Findings and Order is enclosed for this purpose.

If you have any questions, please contact this office.

Sincerely,

Justino P. Micolo

Justina P. Mickelson Physical Science Researcher Scientist Designated Basins Branch

Enclosures: a/s

Office of the State Engineer 1313 Sherman Street, Suite 818 • Denver, CO 80203 • Phone: 303-866-3581 • Fax: 303-866-3589 www.water.state.co.us 22310003912/7/20238:53 AMPGS2\$18.00DF \$0.00Electronically Recorded Official Records El Paso County COSteve Schleiker, Clerk and RecorderTD1000N

QUITCLAIM DEED

(Water Rights)

THIS DEED, made this <u>T</u> day of <u>Decemper</u>, 2023, between Classic SRJ Land, LLC, a Colorado limited liability company ("Grantor"), and Fountain Area Water and Wastewater Authority, a public corporation and political subdivision of the State of Colorado ("Grantee"), whose address is c/o Spencer Fane, LLP, 1700 Lincoln Street, Suite 2000, Denver, CO 80203.

WITNESS, that the Grantor, for and in consideration of good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, has remised, released, sold, and conveyed and quitclaimed, and by these presents does remise, release, sell, convey and quitclaim unto the Grantee, its heirs and assigns forever, all of Grantor's right, title and interest, if any, in and to the following described water and water rights located in the County of El Paso, State of Colorado:

All Water and Water Rights associated with, quantified and described by the Water Court for Water Division No. 2 in Case No. 07CW56, all of which is more specifically described in that guitclaim deed recorded in the records of the El Paso County clerk and recorder at Reception No. 223045600; including, any and all of Grantor's share of any "banked" water (as defined by the Colorado Division of Water Resources) attributable to the above-described groundwater rights, and further including any of Grantor's share of any additional groundwater that may be available from the foregoing Denver Basin aguifers attributable to the abovedescribed groundwater rights based on actual aguifer conditions. Such groundwater rights are subject to all terms and conditions of the above described decrees, as well as the retained jurisdiction of the Division 2 Water Court, and further includes all licenses, permits, certificates, contracts and decrees evidencing such water and water rights, and all wells and fixtures relating thereto, along with all replacements, substitutions, accessions thereto and proceeds deriving therefrom, and further including any after-acquired interests in the above described water and water rights.

TOGETHER, with all the hereditaments and appurtenances thereunto belonging, or in anywise appertaining, the reversions, remainders, rents, issues, and profits thereof, and all the estate, right, title, interest, claim, and demand whatsoever of the Grantor, either in law or equity, in and to the above bargained premises;

TO HAVE AND TO HOLD the rights to divert, apply, extract and use the water and groundwater rights above bargained and described, with the appurtenances, unto the Grantee and assigns forever.

(remainder of page intentionally blank, signatures follow)

IN WITNESS WHEREOF, the Grantor has executed this Quitclaim Deed on the date set forth above.

Classic SRJ Land, LLC, a Colorado limited liability company By: Douglas Stimple, CEO of Manager

STATE OF COLORADO

COUNTY OF EL PASO

The foregoing instrument was acknowledged before me this $\underline{7^{44}}$ day of $\underline{2023}$, by Douglas Stimple as the CEO of the Manager of Classic SRJ Land, LLC, a Colorado limited liability company.


Witness my hand and official seal.

My commission expires: 12.02.2025

) ss.

)

Notary Public



2240414386/3/202410:07 AMPGS22\$118.00DF \$0.00Electronically Recorded Official Records El Paso County COSteve Schleiker, Clerk and RecorderTD1000N

DISTRICT COURT, WATER DIVISION 2, COLORADO Court Address: 501 North Elizabeth Street, Suite 116 Pueblo, CO 81003	DATE FILED: May 30, 2024 3:36 PM CASE NUMBER: 2022CW3009	
CONCERNING THE APPLICATION FOR WATER RIGHTS OF:	Case No.: 23CW3009 Previous case: 20CW3059	
FALCON AREA WATER AND WASTEWATER AUTHORITY		
IN THE ARKANSAS RIVER OR ITS TRIBUTARIES IN EL PASO COUNTY		
FINDINGS OF FACT, CONCLUSIONS OF LAW, RULING OF REFEREE AND DECREE		

THIS MATTER comes before the Court on the Application filed by Falcon Area Water and Wastewater Authority, and having reviewed said Application and other pleadings on file, and being fully advised on this matter, the Court makes the following findings and orders:

GENERAL FINDINGS OF FACT

1. The applicant in this case is Falcon Area Water and Wastewater Authority, whose address is 1700 Lincoln Street, Suite 2000, Denver, Colorado 80203 ("Applicant" FAWWA is made up of multiple municipal or quasi-municipal entity or "FAWWA"). members, including the Sterling Ranch Metropolitan District Nos. 1, 2, and 3 (collectively "SRMD"), and the Retreat Metropolitan District Nos. 1 and 2 (collectively "RMD"). SRMD, RMD, and other entities, have deeded or assigned to FAWWA decreed water rights to Denver Basin groundwater, surface water storage rights, and plans for augmentation. The Applicant seeks to amend the previously issued decrees to create a well field for the withdrawal of all decreed Denver Basin groundwater from both contiguous properties, and from non-contiguous properties so located as to allow for withdrawal of water from wells within the well field, from the same well(s), and to amend the plan for augmentation previously decreed in Case No. 20CW3059 to allow for the use of all such Denver Basin supplies therein, and the return flows resulting therefrom, without increasing pumping entitlements thereunder. FAWWA will comply with Rules 11.A. and 11.B of the Statewide Nontributary Ground Water Rules, as necessary to withdraw the total allowed annual amounts of water from both contiguous and non-contiguous parcels, as described herein.

2. The Applicant is the owner of, or controls, all Denver Basin groundwater described herein, and all land under which such Denver Basin groundwater is located is within Applicant's service area, where such water will be put to beneficial use.

3. The Applicant filed this Application with the Water Court for Water Division 2 on February 24, 2023. The Application was referred to the Water Referee Division 2 on February 24, 2023.

4. A Statement of Opposition was timely filed by the City of Colorado Springs, acting through its enterprise, Colorado Springs Utilities, on April 24, 2023, and a Statement of Opposition was timely filed by the Offices of the State Engineer and the Division Engineer for Water Division No. 2 on April 28, 2023.

5. On March 10, 2023, the Division 2 Water Court ordered that publication occur in El Paso County. The Clerk of this Court caused publication of the Application filed in this matter as provided by statute and the publication costs have been paid. On March 22, 2023, proof of publication in *The Colorado Springs Gazette* was filed with the Division 2 Water Court. All notices of the Application have been given in the manner required by law.

6. On April 11th, 2024, a stipulation between the Applicant and The City of Colorado Springs, acting through its enterprise, Colorado Springs Utilities was filed with the Division 2 Water Court. By Order dated April 16, 2024, the Division 2 Water Court approved such stipulation.

7. On April 11th, 2024, a stipulation between the Applicant and the State Engineer and the Division Engineer for Water Division No. 2 was filed with the Division 2 Water Court. By Order dated April 16, 2024, the Division 2 Water Court approved such stipulation.

8. As the State and Division Engineers timely filed a statement of opposition in this matter and obtained party status, no Consultation Report pursuant to C.R.S. §37-92-302(4) is necessary or required.

9. The Water Court has jurisdiction over the subject matter of these proceedings and over all who have standing to appear as parties whether they have appeared or not. The land and water rights involved in this case are not within a designated groundwater basin.

FAWWA WELL FIELD

10. The Applicant requested amendment of previously issued decrees quantifying Denver Basin groundwater supplies, as described below, based upon the contiguity of certain of such properties, and the proximity of the other of such properties, overlying such Denver Basin supplies, all such property being owned, controlled and/or serviced by FAWWA, allowing all wells constructed upon such properties to be considered a well field, thereby permitting FAWWA to withdraw all such previously decreed Denver Basin groundwater rights from wells located upon other portions of the overlying lands. FAWWA further requested amendment of the plan for augmentation decreed in Case No. 20CW3059 to allow for all wells withdrawing any of the not-nontributary Denver Basin groundwater described herein to be considered augmented structures, and to allow the return flows from Denver Basin groundwater so pumped to be considered potential sources of augmentation supply. The following findings are made with respect to such requests:

11. <u>Sterling Ranch Metropolitan District Nos. 1, 2, and 3 Water Rights</u>. SRMD owns and controls Denver Basin groundwater supplies underlying approximately 1,451.44 acres of land acres located in Sections 27, 28, 32, 33, and 34 of Township 12 South, Range 65 West, and Section 4 of Township 13 South, Range 65 West, all in the 6th P.M., as more particularly described on the attached **Exhibit B**, and depicted on the attached **Exhibit A** map (collectively the "SRMD Properties"). Such decreed water rights include the following:

A. <u>Case No. 86CW18</u>. This case was the original adjudication of the nontributary Arapahoe aquifer underling 1,410 acres of SRMD Properties, and decreed 575 annual acre feet (100-year allocation) of nontributary Arapahoe aquifer groundwater.

B. <u>Case No. 86CW19</u>. This case was the original adjudication of the nontributary Laramie-Fox Hills aquifer underling 1,410 acres of SRMD Properties, and decreed 539 annual acre feet of nontributary Laramie-Fox Hills aquifer water.

C. <u>Case No. 08CW113</u>. This case adjudicated the not-nontributary water supplies in the Dawson and Denver aquifers underlying the entire 1,451.44 acres of the SRMD Properties, as well as not-nontributary Arapahoe groundwater and nontributary Laramie-Fox Hills groundwater not previously adjudicated in Case Nos. 86CW18 and 86CW19, described above (underlying approximately 41.44 acres). The decree in 08CW113 quantified the following groundwater:

<u>Aquifer</u>	<u>Status</u>	<u>100-year Quantity</u>
Dawson	Not-Nontributary	392.5 acre feet
Denver	Not-Nontributary	728.9 acre feet
Arapahoe	Not-Nontributary	0.6 acre feet
Laramie-Fox Hills	Nontributary	0.4 acre feet

D. <u>Case No. 20CW3059</u>. This case adjudicated a plan for augmentation for the use of not-nontributary water supplies adjudicated in Case No.

08CW113, as described above, and further quantified not-nontributary and nontributary groundwater underlying the "SR Quarry Property" (a/k/a the Schmidt property), being approximately 97.54 acres as located in the S½ of Section 32, Township 12 South, Range 65 West, of the 6th P.M., more particularly described on the attached **Exhibit D** and depicted on the attached **Exhibit A** map. The SR Quarry Property, is not contiguous with the SRMD Properties or the RMD Properties because EI Paso County owns Vollmer Road, which separates the SR Quarry Property from the other SRMD Properties and the RMD Properties. The quantities of water available underlying the SR Quarry Property in Case No. 20CW3059 are described as follows:

<u>Aquifer</u>	<u>Status</u>	<u>100-year Quantity</u>
Dawson	Not-Nontributary	9.75 acre feet
Denver	Not-Nontributary	45.56 acre feet
Arapahoe	Not-Nontributary	43.11 acre feet
Laramie-Fox Hills	Nontributary	27.8 acre feet

12. <u>Retreat Metropolitan District Nos. 1 and 2 Water Rights (RMD)</u>. RMD owns and controls property located to the northwest and contiguous to the SRMD Properties, being approximately 191.79 acres located in Sections 27 and 28 of Township 12 South, Range 65 West of the 6th P.M., more particularly described on the attached **Exhibit C**, and depicted on the attached **Exhibit A** map (collectively the "RMD Properties"). The corresponding water rights include the following:

A. <u>Case No. 17CW3002</u>. This case adjudicated Denver basin groundwater supplies under multiple properties. A portion of these properties, and the water rights, are now owned and controlled by FAWWA. This includes a 191.79 acre portion of land, termed the "Arroya Parcel" including the following Denver Basin groundwater rights:

<u>Aquifer</u>	<u>Status</u>	<u>100-year Quantity</u>
Dawson	Not-Nontributary	116 acre feet
Denver	Not-Nontributary	119 acre feet
Arapahoe	Nontributary	98 acre feet
Laramie-Fox Hills	Nontributary	30.34 acre feet ¹

B. <u>Case No. 18CW3002</u>. This case adjudicated a plan for augmentation for a portion of the Denver Basin groundwater quantified in Case No.

¹ As described in Paragraph 12.B., the amount of Laramie-Fox Hills groundwater available to FAWWA under this decree was reduced by 27.96 annual acre feet based upon the reservation of such water in the 18CW3002 plan for augmentation.

17CW3002, reserving 2,796 acre feet (27.96 annual acre feet, 100-year aquifer life) of Laramie-Fox Hills groundwater beneath RMD Properties. This reduced the water in the Laramie-Fox Hills aquifer water from Case No. 17CW3002, available to FAWWA, from 58.3 annual acre feet to 30.34 annual acre feet, based upon a 100-year aquifer life.

13. <u>Jaynes Property</u>. The Jaynes property is located directly to the west of SRMD Properties, being approximately 135 acres located in portions of the S½ and the NE¼ NW¼ of Section 28, and the NW¼ of Section 33, all in Township 12 South, Range 65 West of the 6th P.M., more particularly described on the attached **Exhibit E**, and depicted on the attached **Exhibit A** map. The Jaynes Property is not contiguous with the SRMD Properties or the RMD Properties because El Paso County owns Vollmer Road, which separates the Jaynes Property from the SRMD Properties and the RMD Properties. FAWWA acquired the water rights underlying the Jaynes Property in 2023.

A. <u>Case No. 07CW56</u>. This case adjudicated the groundwater supplies underneath the Jaynes Property as depicted on **Exhibit A**, as follows:

<u>Aquifer</u>	<u>Status</u>	<u>100-year Quantity</u>
Dawson	Not-Nontributary	34.9 acre feet ²
Denver	Not-Nontributary	69.2 acre feet
Arapahoe	Nontributary	58 acre feet
Laramie-Fox Hills	Nontributary	33.8 acre feet ²

14. <u>Raygor Property</u>. The Raygor Property is located to the east of the SRMD Properties, and contiguous thereto, being approximately 40 acres located in the SE¼ NE¼ Section 35, Township 12 South, Range 65 West of the 6th P.M., more particularly described on the attached **Exhibit F**, and depicted on the attached **Exhibit A** map.

A. <u>Case No. 91CW35</u>. This case adjudicated the water beneath Raygor's property as depicted on **Exhibit A**, and FAWWA now owns all of the water rights decreed therein, more particularly described as follows:

Aquifer Status 100-year Quantity

² Twelve (12) annual acre feet of Dawson aquifer groundwater was reserved underlying the Jaynes Property in Case No. 07CW56. A 4.8-acre foot portion of such reserved groundwater is pending adjudication as part of an augmentation plan supporting the subdivision of a portion of the Jaynes Property into six (6) +/-2.5-acre lots, five (5) of which will be augmented in Division 2 Case No. 24CW3007, including the reservation of a 480 acre-foot portion of the nontributary Laramie-Fox Hills aquifer (4.8 acre feet annually) for replacement of post-pumping depletions. The figures in the table above reflect these uses and reservations of water.

Dawson	Not-Nontributary	34 acre feet
Denver	Not-Nontributary	76 acre feet
Arapahoe	Nontributary	49 acre feet
Laramie-Fox Hills	Nontributary	36 acre feet

15. The entirety of the SRMD Properties, RMD Properties, SR Quarry Property, Jaynes Property, and the Raygor Property are collectively referenced hereafter as the "FAWWA Well Field." FAWWA is hereby decreed the right to treat the above described properties as a "well field", as commonly understood and defined by the Statewide Nontributary Ground Water Rules, 2 CCR 402-7:14, and all of the Denver Basin groundwater supplies underlying said FAWWA Well Field may be withdrawn from wells to each respective aquifer located anywhere within the FAWWA Well Field, provided such withdrawals are consistent with Rules 11.A. (for contiguous properties) and 11.B. (for non-contiguous properties) of the Statewide Nontributary Ground Water Rules. The FAWWA Well Field is located in portions of Sections 27, 28, 32, 33, and 34 of Township 12 South, Range 65 West of the 6th Principal Meridian, as depicted on **Exhibit A** and more particularly described on **Exhibits B**, **C**, **D**, **E**, and **F**. The total amounts of groundwater available for withdrawal from the FAWWA Well Field, being the sum total of the various decrees described above (collectively the "Prior Decrees"), is as follows:

<u>Aquifer</u>	<u>Status</u>	<u>100-year Quantity</u>
Dawson	Not-Nontributary	587.15 acre feet
Denver	Not-Nontributary	1,038.66 acre feet
Arapahoe	Not-Nontributary	43.71 acre feet
Arapahoe	Nontributary	780.00 acre feet
Laramie-Fox Hills	Nontributary	660.04 acre feet

16. Existing and Future Wells. All wells will be located within the FAWWA Well Field. FAWWA currently owns and operates two permitted wells to nontributary Arapahoe and Laramie-Fox Hills formations, Permit Nos. 80131-F and 80132-F, respectively. FAWWA has two well applications to the Arapahoe (nontributary), and Laramie-Fox Hills (nontributary) aquifers in connection with Case No. 17CW3002 currently pending and under construction, Permit Nos. 88338-F, and 88339-F, respectively. FAWWA further has a well application to the not-nontributary Denver aquifer pending under Permit No. 330963, which when completed will be augmented under the augmentation plan decreed in Case No. 20CW3059, as hereby amended, and FAWWA may amend all such permits to include all Denver Basin groundwater rights described in Paragraph 15, above, consistent with the terms and conditions of this Decree, and consistent with Rules 11.A. and 11.B. of the Statewide Nontributary Ground Water Rules. Applicant is awarded the vested right to the use of such wells, along with any necessary additional or replacement wells associated with such structures, for the extraction and use of groundwater from the

not-nontributary Dawson, Denver and Arapahoe aquifers, and the nontributary Arapahoe and Laramie-Fox Hills aquifers pursuant to this decree, and pursuant to any applicable plans for augmentation necessary for the withdrawal of not-nontributary groundwater, including the amended Plan for Augmentation decreed herein.

17. Pursuant to C.R.S. §37-90-137(9)(c.5)(I), the augmentation requirements for wells in the not-nontributary Dawson aquifer requires the replacement to the affected stream systems of actual stream depletions, though Applicant does not through this decree seek an augmentation plan that would allow the pumping of the Dawson aquifer groundwater described herein. The ground water in the not-nontributary Denver aquifer, and the not-nontributary portions of the Arapahoe aquifer, underlying the FAWWA Well Field are located greater than 1 mile from any point of contact between a natural stream, and therefore require replacement to the affected stream system of four percent (4%) of the amount of the water withdrawn. The Applicant shall not be entitled to construct a well or use water from the not-nontributary Dawson, Denver, or Arapahoe aquifers except pursuant to an approved augmentation plan in accordance with C.R.S. §37-90-137(9), including as decreed herein as concerns the not-nontributary Denver and Arapahoe aquifers. Applicant shall not be permitted to withdraw not-nontributary supplies from nontributary locations, nor vice versa.

18. Subject to the augmentation requirements described in Paragraph 23 and the other requirements and limitations in this decree, and the 20CW3059 Decree, Applicant shall be entitled to withdraw all legally available groundwater in the Denver Basin aquifers underlying the FAWWA Well Field. Said amounts can be withdrawn over the 100-year life for the aquifers as set forth in C.R.S. §37-90-137(4), or withdrawn over a longer period of time based upon local governmental regulations or Applicant's water needs provided withdrawals during such longer period are in compliance with the augmentation requirements of this decree, specifically including EI Paso County land development code's 300-year requirements. The average annual amounts of ground water available for withdrawal from the underlying Denver Basin aquifers, based upon the 100-year aquifer life, are set forth above, or EI Paso County's 300-year requirements, based upon the Prior Decrees.

19. Applicant shall be entitled to withdraw an amount of groundwater in excess of the average annual amounts decreed herein from the Denver Basin aquifers underlying the FAWWA Well Field, so long as the sum of the total withdrawals from wells in each of the aquifers does not exceed the product of the number of years since the date of issuance of the original well permit or the date of entry of the decree herein, whichever comes first, and the average annual volume of water which Applicant is entitled to withdraw from each of the aquifers underlying the FAWWA Well Field, subject to the requirement that such banking and excess withdrawals do not violate the terms and conditions of the plan for augmentation decreed herein and any other plan for augmentation decreed by the Court that authorizes withdrawal of the Denver Basin groundwater subject of this decree.

Subject to the terms and conditions in the plan for augmentation decreed 20. herein and final approval by the State Engineer's Office pursuant to the issuance of well permits in accordance with C.R.S. §§37-90-137(4) or 37-90-137(10), the Applicant shall have the right to use the Denver Basin groundwater underlying the FAWWA Well Field for all beneficial municipal uses, including as decreed in Case No. 20CW3059, as amended hereby. Such municipal uses include, but are not limited to: domestic, commercial, industrial, recreation, fish propagation, stockwater, wetlands, wildlife habitat, and fire protection, and also for exchange, aquifer recharge, replacement, and augmentation purposes. The amount of groundwater decreed for such uses is reasonable as such uses are to be made for the long-term use and enjoyment of Applicant's municipal customers and is to establish and provide for adequate water reserves. The nontributary groundwater may be used, reused, and successively used to extinction, both on and off the properties which comprise the FAWWA Well Field subject, however, to the requirement under C.R.S. §37-90-137(9)(b) that no more than 98% of the amount withdrawn annually shall be consumed. Applicant may use such water by immediate application or by storage and subsequent application to the beneficial uses and purposes stated herein. Provided however, as set forth above, Applicant shall only be entitled to construct a well or use water from the not-nontributary Dawson, Denver, and Arapahoe aquifers pursuant to a decreed augmentation plan entered by the Court, including the amended plans for augmentation decreed herein. Such use will include reusable return flows from a first municipal use of such Denver Basin supplies from the FAWWA Well Field as a source of augmentation supply for replacement of depletions described in such plans for augmentation, to the extent such sewered return flows and/or Lawn Irrigation Return Flows ("LIRFs") are or may be available in proper time, location and amount.

21. Withdrawals of groundwater available from the nontributary Arapahoe or Laramie-Fox Hills aquifers from the FAWWA Well Field in the amounts determined in accordance with the provisions of this decree will not result in injury to any other vested water rights or to any other owners or users of water.

AMENDMENT OF PLAN FOR AUGMENTATION

22. SRMD (now a member of Applicant) previously obtained a plan for augmentation in Case No. 20CW3059 providing for the augmentation of not-nontributary Denver and Arapahoe aquifer supplies underlying the SRMD Properties, along with quantification of LIRFs derived from municipal irrigation uses thereof as a source of augmentation supply, including of evaporative depletions from certain water storage structures located on the SRMD Properties. SRMD has assigned to FAWWA all its rights,

title and interest under the 20CW3059 Decree. By the application herein, FAWWA requested the inclusion of all not-nontributary Denver and Arapahoe aguifer groundwater underlying the FAWWA Well Field in the 20CW3059 Decree both as augmented water supplies from the augmented structures constituting the FAWWA Well Field, and as a source of augmentation supply in the form of LIRFs to the extent such water supplies are included and accounted for as a source of municipal irrigation supply on the SRMD Properties. FAWWA did not request, and this Decree does not approve, expansion or change to the volumetric pumping entitlements, nor the quantities of LIRFs decreed to be available under the 20CW3059 Decree, nor to otherwise amend said decree, but rather only to include the water associated with all decreed not-nontributary Denver and Arapahoe aquifer groundwater supplies underlying the FAWWA Well Field described herein as sources of supply within the 20CW3059 plan for augmentation, and any reusable return flows therefrom as sources of augmentation supply. All volumetric limitations described in the 20CW3059 decree remain of full force and effect, and the structures to be augmented by the 20CW3059 decree are the existing and future wells as constructed and to be constructed to the not-nontributary Denver and Arapahoe aquifers within the boundaries of the FAWWA Well Field available to FAWWA, subject to existing volumetric limitations. Augmentation sources under the amended augmentation plan in 20CW3059 are LIRFs derived from municipal uses of such Denver and Arapahoe groundwater supplies, quantified and calculated in the same manner as originally decreed in 20CW3059.

23. <u>Amended Augmentation Plan Case No. 20CW3059</u>. Applicant is hereby decreed an amendment to the augmentation plan previously decreed in Case No. 20CW3059. The augmentation plan in Case No. 20CW3059 is hereby amended, and all wells located on the overlying land described herein are included as augmented structures, providing sources of physical supply from the not-nontributary Denver and Arapahoe groundwater sources from the FAWWA Well Field. The Case No. 20CW3059 augmentation plan is further amended to add a source of augmentation supply, being LIRFs resulting from the use of not-nontributary Denver and Arapahoe aquifer groundwater from the FAWWA Well Field, for irrigation of public parks and open space within the SRMD Properties, to be calculated in the same manner and quantities as described in the 20CW3059 Decree.

24. No other changes were requested to the 20CW3059 Decree, nor does this Decree approve any other changes, and Applicant is specifically limited to the volumetric pumping limitations described in the 20CW3059 Decree and further limited in the quantities of LIRFs which may be claimed, as calculated thereunder.

25. Applicant is hereby granted, pursuant to the terms and conditions of the amended augmentation plan decreed herein, the right to withdraw all quantities of not-nontributary Denver and Arapahoe aquifer groundwater underlying the FAWWA Well

Field, through existing, additional or replacement wells located within said FAWWA Well Field, consistent with Rule 11.A. and Rule 11.B. of the Statewide Nontributary Ground Water Rules.

CONCLUSIONS OF LAW

This Court concludes as a matter of law that:

26. All claims within the Application are contemplated and authorized by law, and this Court and the Water Referee have exclusive jurisdiction over these proceedings. \S 37-92-302(1)(a) and (5), 37-92-203, and 37-92-305, C.R.S.

27. Subject to the terms and conditions of this decree, the Applicant is entitled to the sole right to withdraw all the legally available water in the Denver Basin aquifers underlying the FAWWA Well Field, and the right to use that water to the exclusion of all others subject to the terms of this decree.

28. The Applicant has complied with C.R.S. §37-90-137(4), and the nontributary Arapahoe and Laramie-Fox Hills groundwater underlying the FAWWA Well Field is legally available for Applicant's withdrawal, subject to terms and conditions of this decree and the Prior Decrees. Further, the not-nontributary Dawson, Denver, and Arapahoe aquifer groundwater underlying the FAWWA Well Field are legally available for withdrawal upon the entry of a decree approving an augmentation plan pursuant to C.R.S. §37-90-137(9)(c.5), and such a plan for augmentation is decreed herein as concerns the not-nontributary Denver and Arapahoe aquifer groundwater. Applicant is entitled to a decree from this Court confirming its rights to withdraw groundwater pursuant to §37-90-137(4), C.R.S.

29. The Denver Basin water rights described herein are not conditional water rights, but are vested water rights determined pursuant to C.R.S. §37-90-137(4). No applications for diligence are required. The claims for nontributary and not-nontributary groundwater meet the requirements of Colorado Law.

30. The confirmation, determination and quantification of the nontributary and not-nontributary groundwater rights in the Denver Basin aquifers as set forth herein, and as previously decreed, is contemplated and authorized by law. C.R.S. §§37-90-137, and 37-92-302 through 37-92-305.

31. <u>Satisfaction of Burdens of Proof</u>. Applicant has complied with all requirements and satisfied all standards and burdens of proof, including but not limited to C.R.S. §§37-92-302 through 305, excepting sections 305(3.5) and 305(3.6) which are inapplicable hereto, as amended. Applicant is entitled to a decree confirming and

approving the uses and availability of the Denver Basin groundwater underlying the FAWWA Well Field, and the amended plan for augmentation decreed herein, which will not injuriously affect the owners of or persons entitled to use water under vested water rights or decreed conditional water rights as long as the plan for augmentation is operated and administered in accordance with the terms and conditions herein.

32. The amended augmentation plan decreed herein is one contemplated by law. If implemented in accordance with the terms and conditions of this decree, the plan will permit the use of water without material injury to the vested or conditionally decreed water rights of others.

33. The Court is required to retain jurisdiction in a decree approving an augmentation plan on the question of injury to vested or conditional water rights. C.R.S. §37-92-304(6). Such jurisdiction is retained and described in detail at Paragraph 43, below.

IT IS THEREFORE ORDERED, ADJUDGED AND DECREED AS FOLLOWS:

34. All of the foregoing Findings of Fact and Conclusions of Law are incorporated herein by reference, and are considered to be a part of this decretal portion as though set forth in full.

35. The Application for Change of Water Rights and Amendment to Plan for Augmentation filed by the Applicant is approved, subject to the terms of this decree.

36. The Applicant will comply with C.R.S. §37-90-137(9)(b) requiring the relinquishment of the right to consume two percent (2%) of the amount of the nontributary groundwater withdrawn from the FAWWA Wellfield. Ninety eight percent (98%) of the nontributary groundwater withdrawn from the FAWWA Wellfield may therefore be consumed. No plan for augmentation is or shall be required to provide for such relinquishment.

37. The operation of the augmentation plan as decreed in Case No. 20CW3059 and amended herein, provides for the replacement of all injurious out-of-priority depletions which may result from withdrawals of not-nontributary groundwater from the Denver and Arapahoe aquifers underlying the FAWWA Well Field, and evaporative depletions from the use and operation of the SRMD Ponds Nos. 1 and 2. Pumping from the FAWWA Wellfield is augmented during pumping through dedication of LIRFs and/or nontributary pumping as described in the 20CW3059 Decree, and augmented post-pumping through dedication and pumping of the nontributary Denver Basin groundwater rights previously reserved for such purposes in the 20CW3059 Decree³. The terms and

³

In the 20CW3059 Decree, a total of 272.73 acre feet of nontributary groundwater supplies decreed Application of Falcon Area Water and Wastewater Authority Ruling of Referee and Decree Case No. 23CW3009 Page 11

conditions of this decree, in combination with the 20CW3059 Decree, are adequate to assure that no injury to any water users will result from operation of this amended plan for augmentation. The Court approves this amended plan subject to the terms and conditions contained in this decree and the 20CW3059 Decree.

38. The replacement and augmentation supply that FAWWA will use for operation of the amended plan for augmentation decreed herein shall be of a quality and quantity so as to meet the requirements for which the water of senior appropriators has normally been used.

39. The State and Division Engineers and the Water Commissioner shall administer this amended augmentation plan in accordance with the terms and conditions contained in this decree, and the terms and conditions of the original 20CW3059 Decree which were not amended hereby. So long as water is used in conformance with the requirements of this decree, and the 20CW3059 Decree, there will be no injurious effects to the vested or decreed conditional water rights of others related to the amount or timing of water availability.

40. The State Engineer, the Division Engineer, and/or the Water Commissioner shall not curtail the diversion and use of water covered by the amended plan for augmentation decreed herein, so long as the LIRFs necessary for augmentation during the pumping life of the not-nontributary Denver and Arapahoe aguifers described herein continue to accrue to the stream system pursuant to the conditions contained herein. and/or Applicant pumps nontributary groundwater supplies directly to augmentation use, per the terms of the 20CW3059 Decree. To the extent that Applicant or its successors or assigns, is unable to provide the replacement water required, then the wells and ponds shall not be entitled to continue under the protection of this plan, and shall be subject to administration and curtailment in accordance with the laws, rules, and regulation of the State of Colorado. Pursuant to C.R.S. §37-92-305(8), the State Engineer shall curtail all out-of-priority diversions which are not so replaced as to prevent injury to vested water rights. In order for this plan for augmentation to operate, LIRFs must at all times during pumping be in an amount sufficient to replace the amount of stream depletions, or nontributary supplies must be directly pumped to augmentation use in quantities sufficient to replace such stream depletions. The State Engineer shall issue well permits in accordance with C.R.S. §37-90-137(4) and/or (10) and consistent with the terms and conditions of this Decree. All such wells constructed by Applicant pursuant to the augmentation plan decreed herein shall be geophysically logged consistent with applicable rules and regulations of the State and Division Engineers.

in Case Nos. 93CW18, 93CW19, and 85CW445, now owned and controlled by Applicant, were dedicated to replacement of post-pumping depletions. Such reservation remains applicable to pumping from the FAWWA Wellfield as described herein.

41. Applicant shall install such metering and measuring devices as may be reasonably required by the State and Division Engineers to ensure proper measurement and accounting of all withdrawals and pumping.

42. Accounting. FAWWA's accounting under this decree shall be consistent with the accounting required by the original 20CW3059 Decree, and with accounting required by the Prior Decrees, with such integrated accounting to provide consolidated augmentation accounting for water rights produced from the properties within the FAWWA Well Field. All accounting records required by this Decree shall be filed with the State Engineer and Division Engineer on a monthly basis, with actual measurement and accounting calculated on a daily basis. The Applicant's current accounting forms are adequate to account for the water rights and augmentation plan under this decree; however, said forms are not decreed herein and may be changed from time to time so long as the information required by this decree is included in the forms, 35 days advance written notice is provided to the objectors, and such changes are approved by the Division Engineer or the Water Commissioner. Copies of any revised forms shall be provided to objectors at no cost upon request. The daily accounting and all backup and supporting information and documents shall also be provided to any objector making a written request for said accounting for the accounting year, upon payment of reasonable costs. The accounting shall be delivered to the Division Engineer and Water Commissioner in the manner they prescribe and may be delivered to other objectors in paper or electronic format at the Applicant's option.

43. Retained Jurisdiction. Pursuant to the provisions of C.R.S. §37-92-304(6), the amended plan for augmentation decreed herein shall be subject to the reconsideration of this Court on the guestion of material injury to vested water rights of others, for a period of five years after Applicant fully utilizes the LIRFs as an augmentation supply, as evidenced by the Applicant's provision and service of written notice to Opposers herein that all parks and common areas anticipated to result in LIRF credits have been developed and constructed, and FAWWA is irrigating such parks and common areas with approved water sources allowing such LIRF credits to be claimed. Any person, within such period, may petition the Court to invoke its retained jurisdiction. Any person seeking to invoke the Court's retained jurisdiction shall file a verified petition with the Court setting forth the factual basis for the relief requested in the petition, together with proposed decretal language to effect the petition. The party filing the petition shall have the burden of proof of going forward to establish the facts alleged in the petition. If the Court finds those facts are established, Applicant shall thereupon have the burden of proof to show: (a) that the petitioner is not injured, or (b) that any modification sought by the petitioner is not required to avoid injury to the petitioner, or (c) that any term or condition proposed by Applicant in response to the petition does avoid injury to the petitioner. The Division of Water Resources as a petitioner shall be entitled to assert injury to the vested water rights

of others. If no such petition is filed within such period and the retained jurisdiction period is not extended by the Court in accordance with the revisions of the statute, this matter shall become final under its own terms. The Court also retains continuing jurisdiction for the purpose of determining whether the continued reservation of the nontributary Denver Basin water rights is required and retained jurisdiction for such purpose shall be perpetual.

44. Pursuant to C.R.S. §37-92-304(6), the Court shall retain continuing jurisdiction over the amended plan for augmentation decreed herein for reconsideration of the question of whether the provisions of this decree are necessary and/or sufficient to prevent injury to vested water rights of others, as pertains to the use of Denver Basin groundwater supplies adjudicated herein for augmentation purposes. The Court also retains continuing jurisdiction for the purpose of determining compliance with the terms of the augmentation plan. The Court further retains jurisdiction should the Applicant later seek to amend this decree by seeking to prove that post-pumping depletions are noninjurious, that the extent of replacement for post-pumping depletions is less than the amount of water reserved in 20CW3059 Decree, as amended hereby, and other post-pumping matters. The Court's retained jurisdiction may be invoked using the process set forth in Paragraph 43.

45. Pursuant to C.R.S. §37-92-502(5)(a), the Applicant shall install and maintain such water measurement devices and recording devices as are deemed necessary by the State Engineer or Division Engineers, and the same shall be installed and operated in accordance with instructions from said entities. Applicant must install and maintain a totalizing flow meter on each well, or any additional or replacement wells associated therewith and are required to include geophysical logging on each well. Applicant shall read and record their well meter readings on March 31st and October 31st of each year and shall submit their meter readings to the Water Commissioner by April 15th and November 15th of each year or more frequently as requested by the Water Commissioner.

46. This Ruling of Referee, when entered as a decree of the Water Court, shall be recorded in the real property records of El Paso County, Colorado. Copies of this ruling shall be mailed as provided by statute.

DATED: April 25, 2024.

BY THE REFEREE:



Kate Brewer, Water Referee Water Division 2

DECREE

THE COURT FINDS THAT NO PROTEST WAS FILED IN THIS MATTER, THEREFOR THE FORGOING RULING IS CONFIRMED AND APPROVED, AND IS HEREBY MADE THE JUDGMENT AND DECREE OF THIS COURT.

Dated: May 30, 2024.



Monorable Gregory Styduhar Water Judge, Water Division 2 State of Colorado

> Application of Falcon Area Water and Wastewater Authority Ruling of Referee and Decree Case No. 23CW3009 Page 15




EXHIBIT B – SRMD Legal Description

The W¹/₂ W¹/₂ E¹/₂ and the E¹/₂ W¹/₂ and the SW¹/₄ SW¹/₄ of Section 27; the E¹/₂ SE¹/₄ and that portion of the SW¹/₄ SE¹/₄ lying South and East of the County Road across said premises, both in Section 28; that portion of the SE¹/₄ SE¹/₄ of Section 32 lying South and East of said County Road, that portion of the NE¹/₄ SE¹/₄ of Section 32, lying South and East of said County Road, and that portion of the SE¹/₄ SW¹/₄ SE¹/₄ of Section 32 beginning at the SE comer of the SE¹/₄ SW¹/₄ SE¹/₄ then northerly along the east line of the SE¹/₄ SW¹/₄ SE¹/₄ a distance of 495 feet to a point on Vollmer Road, then southwesterly along Vollmer Road 660 feet to a point on the south line, then easterly 495 feet to the point of beginning; the E¹/₂ and the E¹/₂ SW¹/₄ and the SW¹/₄ SW¹/₄ of Section 33, and all that part of the NW¹/₄ of said Section 33 lying South and East of the said County Road across said premises, except that portion of the SW¹/₄ NW¹/₄ of said Section 33 lying South and East of said County Road containing approximately 10 acres deeded to Colorado Interstate Gas Company by Warranty Deed recorded in Book 1173 at Page 359 of the El Paso County Records; and the W¹/₂ E¹/₂ and the W¹/₄ of Section 4, Township 13 South, Range 65 West of the 6th P.M.; located in El Paso County, Colorado.

EXHIBIT C - Retreat Metro Districts Legal Description

A PORTION OF SECTION 21, 22, 27 AND 28, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., EL PASO COUNTY, COLORADO, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BASIS OF BEARINGS: A LINE BETWEEN THE NORTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE NORTHWEST ONE-QUARTER (NW1/4 NW1/4) OF SECTION 27 AND THE SOUTHEAST CORNER OF THE NORTHWEST ONE-QUARTER OF THE SOUTHWEST ONE-QUARTER (NW1/4 SW1/4) OF SAID SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST, MONUMENTED AT THE NORTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND MONUMENTED AT THE SOUTHERLY END BY A 3-1/4" ALUMINUM CAP STAMPED "2006 ESI PLS 10376" AND IS ASSUMED TO BEAR S00°54'30"E, A DISTANCE OF 3925.63 FEET;

COMMENCING AT THE NORTHEAST CORNER OF THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 27, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH P.M., SAID POINT ALSO BEING THE POINT OF BEGINNING;

THENCE S00°54'30"E ON THE EAST LINE OF THE WEST HALF OF THE WEST HALF OF SAID SECTION 27, A DISTANCE OF 3925.63 FEET TO THE SOUTHEAST CORNER OF THE NORTHWEST QUARTER OF THE SOUTHWEST QUARTER OF SAID SECTION 27;

THENCE S87°35'00"W ON THE SOUTH LINE OF SAID NORTHWEST QUARTER OF THE SOUTHWEST QUARTER, A DISTANCE OF 1332.78 FEET TO THE SOUTHWEST CORNER OF SAID NORTHWEST QUARTER OF THE SOUTHWEST QUARTER;

THENCE N00°53'18"W ON THE WEST LINE OF SAID NORTHWEST QUARTER OF THE SOUTHWEST QUARTER, A DISTANCE OF 1316.78 FEET TO THE NORTHWEST CORNER OF SAID NORTHWEST QUARTER OF THE SOUTHWEST QUARTER;

THENCE S89"08'28"W ON THE SOUTH LINE OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF SECTION 28, A DISTANCE OF 1326.68 FEET TO THE SOUTHWEST CORNER OF SAID SOUTHEAST QUARTER OF THE NORTHEAST QUARTER;

THENCE N00°30'49"W ON THE WEST LINE OF SAID SOUTHEAST QUARTER OF THE NORTHEAST QUARTER, A DISTANCE OF 1270.77 FEET TO A POINT ON THE EASTERLY RIGHT-OF-WAY LINE AS RECORDED IN BOOK 2678 AT PAGE 430 OF THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER;

THENCE N21°41'10"E ON SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 1450.84 FEET TO THE POINT OF INTERSECTION OF THE SOUTHERLY RIGHT-OF-WAY LINE AS DESCRIBED IN A DEED RECORDED IN BOOK 2678 AT PAGE 430 OF SAID COUNTY RECORDS;

THENCE ON THE SOUTHERLY, EASTERLY AND NORTHERLY RIGHT-OF-WAY LINES OF SAID DEED THE FOLLOWING FOUR COURSES:

1. N89°40'23"E, A DISTANCE OF 761.52 FEET TO A POINT ON THE EAST LINE OF THE NORTHEAST QUARTER OF SAID SECTION 28;

2. N00°52'58"W ON SAID EAST LINE, A DISTANCE OF 30.00 FEET TO THE SOUTHEAST CORNER OF SAID SECTION 21;

3. N00°37'14"W ON THE WEST LINE OF THE SOUTHWEST QUARTER OF SECTION 22, A DISTANCE OF 30.00 FEET;

4. S89°40'23"W, A DISTANCE OF 736.82 FEET TO THE POINT OF INTERSECTION OF THE EASTERLY RIGHT-OF-WAY LINE AS DESCRIBED IN A DEED RECORDED IN BOOK 2678 AT PAGE 431 OF SAID COUNTY RECORDS;

THENCE N21"41'10"E ALONG SAID EASTERLY RIGHT-OF-WAY LINE, A DISTANCE OF 113.82 FEET; THENCE S68°18'50"E, A DISTANCE OF 145.93 FEET TO A POINT OF CURVE; THENCE ALONG THE ARC OF A CURVE TO THE LEFT HAVING A RADIUS OF 560.00 FEET, A CENTRAL ANGLE OF 22°00'4T FOR A LENGTH OF 215.15 FEET TO A POINT OF TANGENT;

THENCE N89"40'23"E ON A LINE THAT IS 40.00 NORTHERLY OF AND PARALLEL WITH THE SOUTH LINE OF THE SOUTHEAST QUARTER OF SAID SECTION 21, A DISTANCE OF 348.92 FEET;

THENCE N88°38'56"E ON A LINE THAT IS 40.00 NORTHERLY OF AND PARALLEL WITH THE SOUTH LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 22, A DISTANCE OF 477.80 FEET;

THENCE S47°35'42"W, A DISTANCE OF 60.90 FEET;

THENCE N88°38'56"E ON THE SOUTH LINE OF THE SOUTHWEST QUARTER OF SAID SECTION 22, A DISTANCE OF 898.51 FEET TO THE POINT OF BEGINNING.

CONTAINING A CALCULATED AREA OF 8,354,696 SQ. FEET, OR 191.797 ACRES.

EXHIBIT D – Schmidt Legal Description

A TRACT OF LAND IN THE SW¼ AND THE SW¼ OF THE SE¼. OF SECTION 32, TOWNSHIP 12 SOUTH, RANGE 65 WEST OF THE 6TH PRINCIPAL MERIDIAN, IN EL PASO COUNTY, COLORADO, DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 32; THENCE N89°23'57"E ALONG THE SOUTH LINE OF SECTION 32, 30.00 FEET TO POINT ON THE EASTERLY LINE OF BLACK FOREST ROAD, ACCORDING TO THE RESOLUTION ADOPTED BY THE BOARD OF COMMISSIONERS OF EL PASO COUNTY RECORDED IN ROAD BOOK A AT PAGE 78. WHICH POINT IS THE POINT OF BEGINNING; THENCE N00°02'19"W ALONG SAID EASTERLY LINE, 125.50 FEET TO A POINT ON THE SOUTH LINE OF THAT TRACT OF LAND DESCRIBED IN BOOK 3859 AT PAGE 151; THENCE ALONG THE BOUNDARY OF SAID TRACT FOR THE FOLLOWING FOUR (4) COURSES; (1) THENCE N89°23'57"E, 25.20 FEET; (2) THENCE N42°32'21 "E. 664.79 FEET: (3) THENCE N01°44'16"W. 403.43 FEET: (4) THENCE N87°25'38"W, 463.51 FEET TO A POINT ON SAID EASTERLY LINE OF BLACK FOREST ROAD; THENCE N00°02'19"E ALONG SAID EASTERLY LINE, 124.08 FEET; THENCE N89°27'58"E, 2607.50 FEET; THENCE N00°00'40"W ALONG THE NORTH-SOUTH CENTERLINE OF SECTION 32, 152.93 FEET TO THE SOUTHWEST CORNER OF HOLIDAY HILLS NO. 1, ACCORDING TO THE PLAT RECORDED IN PLAT BOOK E2 ATPAGE 12; THENCE N89°3 I '30"E ALONG THE SOUTH LINE OF SAID HOLIDAY HILLS NO. 1, 1260.38 FEET; THENCE S00°33'58"E ALONG THE WESTERL y LINE OF GLIDER PORT ROAD, AS DEDICATED IN SAID HOLIDAY HILLS NO. 1, 741.29 FEET; THENCE S37°18'25"W ALONG THE NORTHWESTERLY LINE OF VOLLMER ROAD, 721.56 FEET; THENCE S89°23'57"W ALONG THE SOUTH LINE OF SECTION 32, 3437.29 FEET TO THE POINT OF BEGINNING. COUNTY OF EL PASO, STATE OF COLORADO.

EXHIBIT E – Jaynes Legal Description

That portion of E¹/₂ of the SW¹/₄ and that portion of the W¹/₂ of the SE¹/₄ of Section 28 and that portion of the E¹/₂ of the NW¹/₄ of Section 33, Township 12 South, Range 65 West of the 6th P.M., El Paso County, Colorado, laying Northwesterly of the existing county road (Vollmer Road), being more particularly described as follows:

Beginning at a point on the east-west centerline of said Section 28, said line also being thee south line of Poco Road as described in Book 2274 at page 314, said point also being the Center West 1/16 corner of said Section 28, from which the West Quarter corner of said Section 28 bears S.89°45'22"W (Bearings based on the line between the West Quarter corner of said Section 28, monumented with a 3¼ inch aluminum cap marked with PLS No. 4842 and the northwest corner of Jaynes Subdivision, monumented with a No. 4 rebar and plastic cap marked with PLS No. 4842, said line bears N89°45'22"E), a distance of 1,310.67 feet; thence N89°45'22"E, along said east-west centerline, a distance of 717.48 feet, to the northwest corner of Lot 1, Jaynes Subdivision (as established on that plat of Jaynes Subdivision filed on December 20, 1984 in the El Paso County Clerk and Recorders Office at Reception No. 119494 in Plat Book X-3 at page 96); thence S00°14'39"E, along the west line of Lot 1, a distance of 544.41 feet, to the southwest corner of said Lot 1; thence N89°46'02"E along the south line of said Lot 1, a distance of 400.10 feet; thence S00°15'34"E, a distance of 598.01 feet; thence N"89°45'22"E, a distance of 1,217.67 feet to a point on the apparent northwesterly right-of-way line of Vollmer Road the following four (4) courses:

- 1. Along the arc of a non-tangential curve to the right, whose center bears N78°14'10"W, having a central angle of 27°06'29" and a radius of 603.83 fet, a distance of 285.69 feet;
- 2. Thence S38°51'49"W, a distance of 1,375.53 feet;
- 3. Thence S39°37'46"W, a distance of 376.52 feet;
- 4. Thence S41°07'37"W, a distance of 1,729.65 feet, to the intersection of said northwesterly right-of-way line and the west line of said E½ of the NW¼ of said Section 33;

Thence N00°25'04"E along said west line of the said E $\frac{1}{2}$ NW $\frac{1}{4}$ of said Section 33, a distance of 1,440.99 feet; thence N00°14'40"E along the west line of the E $\frac{1}{2}$ SW $\frac{1}{4}$ of said section 28, a distance of 2,611.39 feet, to the POINT OF BEGINNING.

EXHIBIT F - Raygor Legal Description

The Southeast Quarter of the Northeast Quarter of Section 34, Township 12, South, Range 65 West of the 6th P.M., County of El Paso, State of Colorado, Except that portion thereof falling within Bow Valley Subdivision.

FILIN CASE	FILED: February 13, 2024 10:26 AM G ID: F4C5B4148C480 NUMBER: 2024CW3007
CONCERNING THE APPLICATION FOR WATER RIGHTS OF:	
FALCON AREA WATER AND WASTEWATER AUTHORITY	
IN EL PASO COUNTY	▲ COURT USE ONLY ▲
Attorneys for Applicant: Chris D. Cummins, #35154 W. James Tilton, #50213 Paul J. Raymond, #58692 Monson, Cummins, Shohet & Farr, LLC 13511 Northgate Estates Dr., Ste. 250 Colorado Springs, CO 80921 Phone Number: (719) 471-1212 E-mail: cdc@cowaterlaw.com wjt@cowaterlaw.com pjr@cowaterlaw.com	Case No: 24CW30
APPLICATION FOR DETERMINATION OF W	ATER RIGHTS, PLAN FOR

AUGMENTATION, AND AMENDMENT TO PLANS FOR AUGMENTATION

NAME, ADDRESS AND TELEPHONE NUMBER OF APPLICANT Ι.

Falcon Area Water & Wastewater Authority c/o Spencer Fane, LLP 1700 Lincoln Street, Suite 2000 Denver, Colorado 80203 (303) 839-3845

Name, Address and Telephone Number of Applicant's Attorneys:

MONSON, CUMMINS, SHOHET & FARR, LLC Chris D. Cummins, #35154 W. James Tilton, #50213 Paul J. Raymond, #58692 13511 Northgate Estates Dr., Ste. 250 Colorado Springs, CO 80921 (719) 471-1212

II. <u>SUMMARY OF APPLICATION</u>.

The Falcon Area Water & Wastewater Authority ("Applicant", or "FAWWA") is a public corporation and political subdivision of the State of Colorado formed pursuant to Title 29, C.R.S. which provides water and wastewater services to its municipal and guasimunicipal members in northern El Paso County, Colorado. FAWWA's available water rights include water rights underlying the "Jaynes Property", upon which FAWWA will provide central municipal water and wastewater services, except as described in the augmentation plan requested herein. The bulk of the water rights underlying the Jaynes Property were previously quantified and adjudicated in Case No. 07CW56 (the "Jaynes Water Rights"), though that decree expressly excluded from such quantification 12 annual acre-feet of Dawson Aquifer ground water. FAWWA recently purchased the Jaynes Water Rights, including the to-date unadjudicated 12 acre feet of Dawson water supplies. This application seeks to quantify a 9 acre foot portion of the previously excluded 12 acre feet of Dawson groundwater underlying the Jaynes Property, and to adjudicate a plan for augmentation for the use of portions thereof in support of a subdivision of a portion of the Jaynes Property, Prairie Ridge Filing No. 1. The Jaynes Property is located in portions of the S¹/₂ and the NE¹/₄ NW¹/₄, of Section 28, and the NW¹/₄ of Section 33, all in Township 12 South, Range 65 West of the 6th P.M., more particularly described and depicted on the attached Exhibit A map.

FAWWA is also the owner of unquantified Denver Basin ground water underlying the "Rhetoric Property", an approximately 30.64 acre parcel of land located in NE¼ NE¼, of Section 5, Township 13 South, Range 65 West of the 6th P.M., more particularly described and depicted on the attached **Exhibit B** map. FAWWA also seeks by this Application to quantify the Denver Basin groundwater underlying the Rhetoric Property, and to add such Denver Basin groundwater supplies to those supplies otherwise available to FAWWA for withdrawal from the FAWWA Wellfield, as pending adjudication in Case No. 23CW3009, pursuant to the augmentation plan decreed in Case No. 20CW3059, as pending amendment in Case No. 23CW3009, and as requested for further amendment herein. The Rhetoric Property is contiguous to land overlying the FAWWA Wellfield, as described in pending Case No. 23CW3009, and FAWWA seeks to add the Rhetoric Property to such FAWWA Wellfield for production of Denver Basin supplies consistent with the Statewide Nontributary Ground Water Rules, specifically Rules 11.A. and 11.B.

III. <u>Determinations of Water rights</u>. The following water and water rights are sought for utilization by FAWWA and its successors or assigns, including through the FAWWA Wellfield described in Case No. 23CW3009.

A. <u>Jaynes Property</u>. The Jaynes Property is an approximately 142 acre property located as described in Paragraph II., above, more particularly described and depicted on the attached **Exhibit A** map.

a. <u>Case No. 07CW56 – Reserved Dawson Aquifer Groundwater</u>. The decree in Case No. 07CW56 quantified and adjudicated all Denver Basin groundwater supplies underlying the Jaynes Property, excepting 12 annual acre feet from not-

nontributary Dawson aquifer. Applicant seeks to now quantify 9 annual acre feet of such previously excluded 12 acre-feet of Dawson aquifer groundwater, and further seeks approval of a plan for augmentation utilizing portions of the same, as described below. Applicant seeks the right to utilize such Dawson aquifer groundwater supplies on the basis of the 100-year aquifer life provided by Colorado Statute, or over the course of 300-years, demonstration of which is required by applicable El Paso County Land Development Code

b. <u>Existing Well</u>. There is an existing well on the Jaynes property, Division of Water Resources Well Permit No. 285607, permitted as an exempt structure pursuant to C.R.S. §37-92-602(3)(b)(II)(A). FAWWA intends to maintain the exempt nature of Permit No. 285607 ("Prairie Ridge Well No. 6") consistent with C.R.S. §37-92-602(IV), for use on one of the six large lots to be developed as part of Prairie Ridge Filing No. 1, described herein, and as described above maintains the reservation of 3 annual acre feet of water (1 annual acre foot on a 300-year basis) previously described in Case No. 07CW56, for such purposes.

B. <u>Rhetoric Property</u>. The Rhetoric Property is an approximately 30.64 acre parcel located as described in Paragraph II, above, more particularly described and depicted on the attached **Exhibit B** map. FAWWA seeks to quantify the Denver Basin groundwater underlying the Rhetoric Property, and additionally seeks to add such water as a source of additional supply for use in FAWWA's augmentation plan as decreed in Case No. 20CW3059, and as pending amendment in Case No. 23CW3009. Applicant's consultants have calculated the approximate amounts of Denver Basin groundwater available beneath the Rhetoric Property as follows:

<u>Aquifer</u>	<u>Status</u>	<u>100-year Quantity</u>
Dawson	Not-Nontributary	3.04 acre feet
Denver	Not-Nontributary	15.91 acre feet
Arapahoe	Not-Nontributary	12.91 acre feet
Laramie-Fox Hills	Nontributary	8.73 acre feet

C. <u>Summary</u>. FAWWA expressly seeks a decree quantifying the amount of Denver Basin groundwater beneath the Rhetoric Property in the amounts above for use throughout FAWWA's system, including as may be produced from the FAWWA Wellfield, as pending adjudication in Case No. 23CW3009, and pursuant to the augmentation previously decreed in Case No. 20CW3059, as amended. FAWWA further seeks a decree quantifying the 9 annual acre feet of Dawson Aquifer water previously excluded from the 07CW56 Decree, and approving an augmentation plan for use of portions of the same through individual wells on up to 5 lots within of the Prairie Ridge Filing No. 1, a subdivision of a portion of the Jaynes Property, described below.

IV. Application for Approval of Plan for Augmentation.

A. <u>Statement of Plan for Augmentation</u>: FAWWA seeks approval of a plan for augmentation to allow the use of Dawson aquifer groundwater underlying the Jaynes Property, as quantified herein. Such Dawson aquifer wells will, during the pumping life of such wells, be augmented by septic return flows through non-evaporative onsite septic systems, resulting from domestic uses, with post-pumping depletions being provided by FAWWA through dedication of nontributary groundwater supplies, as described herein.

B. <u>Augmented Structures</u>. The structures to be augmented under this plan for augmentation are up to 5 residential wells to be located on up to 5 residential lots on a portion of the Jaynes Property (collectively the "Prairie Ridge Wells Nos. 1-5"). Each of these residential wells shall be constructed to the not-nontributary Dawson aquifer, with combined pumping not to exceed the 1.6 acre feet (on a 300-year basis), or 0.32 acre feet per well.

C. <u>Augmentation Supplies</u>. During the anticipated 300-year pumping term of this augmentation plan, depletions resulting from the pumping of the Prairie Ridge Wells 1-5 will be replaced by septic return flows resulting from in-house uses of water by residents of the lots upon which such wells are constructed, following wastewater treatment through onsite septic systems. Post-pumping depletions will be replaced by dedication of the nontributary groundwater supplies described herein to such purposes.

E. <u>Depletions</u>. FAWWA consultants have determined that maximum stream depletions over a 300-year period for the not-nontributary Dawson aquifer is 56% of pumping. Maximum annual depletions from the pumping of 1.6 acre feet annually are therefore 0.896 acre feet in year 300. Should pumping be less than 1.6 acre-feet annually, resulting depletions and required replacements will be correspondingly reduced.

B. <u>Augmentation of Depletions During Pumping</u>. Depletions during pumping will be replaced by return flows from non-evaporative septic systems. The annual consumptive use for a non-evaporative septic system is 10% per year. Therefore, at conservatively estimated in-house use rates of 0.20 acre-feet per year, replacement amounts of 0.18 acre-feet accrue to the stream system annually from each well. With 5 wells this totals 0.9 acre feet annually, exceeding the maximum amount of annual depletions. Thus, during pumping, stream depletion replacement requirements will be met by dedication of septic return flows from the described five large-lot residences within the Prairie Ridge Filing No. 1 subdivision (excluding the 6th large lot continuing to utilize the exempt Prairie Ridge Well No. 6).

C. <u>Augmentation of Post Pumping Depletions</u>. For the replacement of injurious post-pumping depletions which may be associated with the use of the Jaynes Wells, FAWWA reserves and dedicates a total of 480 acre feet (4.8 annual acre feet, 100-year allocation) of the nontributary Laramie-Fox Hills aquifer water underlying the Jaynes Property, as previously adjudicated in Case No. 07CW56. FAWWA reserves the right to

substitute other legally available augmentation sources for replacement of such postpumping depletions.

V. Amendment to Existing Plan for Augmentation. FAWWA seeks to further amend the plan for augmentation decreed in Case No. 20CW3059, and pending amendment in 23CW3009, to add the not-nontributary Arapahoe and Denver aquifer groundwater supplies beneath the Rhetoric Property, quantified by this application as additional sources of supply, including for production through the FAWWA Wellfield. FAWWA further seeks to add as sources of augmentation supply in Case No. 20CW3059, pending amendment in Case No. 23CW3009, all reusable return flows generated from the use of such water, specifically including lawn irrigation return flows. FAWWA further seeks to add the nontributary groundwater supplies in the Laramie-Fox Hills aguifer underlying the Rhetoric Property as a source of additional post-pumping replacement water in Case No. 20CW3059, allowing for increased production from the not-nontributary Denver and Arapahoe aquifers on the basis of such additional post-pumping supplies. By addition of these new supplies, FAWWA seeks a corresponding increase in the pumping available from the FAWWA Well Field, on the same terms and conditions previously decreed in Case No. 20CW3059.

B. <u>Remarks:</u> Additional remarks are as follows:

1. The term of the augmentation plan is for 300 years as decreed in 20CW3059, and as pending amendment both herein and in Case No. 23CW3009. However, the length of the plan for a particular well or wells may be extended beyond such time provided the total plan pumping allocated thereto is not exceeded. Post-pumping stream depletions accrue to a particular well or wells only to the extent related to that well's actual pumping.

2. Before any wells are constructed, applications for well permits will be filed with the State Engineer's office, and well permits shall be granted in accordance with the decree pursuant to this application.

3. The Applicant requests a finding that vested water rights of others will not be materially injured by the withdrawals of ground water and the proposed plan for augmentation.

4. The wells shall be installed and metered as reasonably required by the State and Division Engineer. Each well must be equipped with a totalizing flow meter and Applicant shall submit diversion records to the Division Engineer on an annual basis or as otherwise requested by the Division Engineer. The Applicant shall also provide accountings to the Division Engineer and Water Commissioner as required by them to demonstrate compliance under the plan of augmentation, and all such accountings shall be integrated into other accountings required from Applicant pursuant to subsequently entered decrees so as to accurately account for all water uses by the District from various sources, and to ensure that all out-of-priority depletions associated therewith are adequately replaced in time, place and amount.

5. The Applicant intends to waive the 600 feet well spacing requirement for the wells to be located within the FAWWA Well Field, including as it now exists, or as it may exist in the future.

RESPECTFULLY SUBMITTED this 13th day of February, 2024.

MONSON, CUMMINS, SHOHET & FARR, LLC (Pursuant to C.R.C.P. 121, § 1-26(9), the signed original shall be kept on file at the offices of Monson, Cummins, Shohet & Farr, LLC)

Paul J. Raymond

Chris D. Cummins, #35154 W. James Tilton, #50213 Paul J. Raymond, #58692 13511 Northgate Estates Dr., Ste. 250 Colorado Springs, CO 80921 (719) 471-1212

VERIFICATION

STATE OF COLORADO)) ss. COUNTY OF EL PASO)

I, James Morley, declare under penalty of perjury under the law of Colorado that I am an authorized representative of the Applicant, being the President of the Board of Directors for the Falcon Area Water & Wastewater Authority, and that I have read the foregoing and that all of the statements contained therein are true and accurate to the best of my knowledge and information.

James Morley, President

Falcon Area Water & Wastewater Authority

Executed on the <u>27th</u> day of December, 2023, in the City of <u>Colorado Springs</u>, State of <u>Colorado</u>.

APPENDIX D WELL PERMITS





RESPEC.COM

Form No. GWS-25

OFFICE OF THE STATE ENGINEER COLORADO DIVISION OF WATER RESOURCES 818 Centennial Bldg., 1313 Sherman St., Denver, Colorado 80203

(303) 866-3581

		77785	<u>- F</u>	-
DIV. 2	WD 10	DES. BASIN	MD	

APPLICANT

APPROVED WELL LOCATION

EL PASO COUNTY NE 1/4 NW 1/4 Section 27 Township 12 S Range 65 W Sixth P.M.

DISTANCES FROM SECTION LINES

324Ft. from NorthSection Line2632Ft. from WestSection Line

(719) 491-3024

PERMIT TO CONSTRUCT A WELL

UTM COORDINATES (Meters,Zone:13,NAD83) Easting: Northing:

ISSUANCE OF THIS PERMIT DOES NOT CONFER A WATER RIGHT CONDITIONS OF APPROVAL

- 1) This well shall be used in such a way as to cause no material injury to existing water rights. The issuance of this permit does not ensure that no injury will occur to another vested water right or preclude another owner of a vested water right from seeking relief in a civil court action.
- 2) The construction of this well shall be in compliance with the Water Well Construction Rules 2 CCR 402-2, unless approval of a variance has been granted by the State Board of Examiners of Water Well Construction and Pump Installation Contractors in accordance with Rule 18.
- 3) Approved pursuant to CRS 37-90-137(4) and the decree granted in case no. 86CW19 Division 2 Water Court. The operation of this well is subject to the terms and conditions of said decree.
- 4) The use of ground water from this well is limited to municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation, augmentation, livestock watering and agricultural uses.
- 5) The pumping rate of this well shall not exceed 150 GPM.

MORLEY-BENTLEY INVESTMENTS LLC

20 BOULDER CRESCENT ST

COLORADO SPRINGS, CO 80903-

- 6) The average annual amount of ground water to be appropriated shall not exceed 539 acre-feet.
- 7) Production is limited to the Laramie-Fox Hills aquifer which is located 2,345 feet below land surface and extends to a depth of 2,630 feet. Plain casing must be installed and grouted to prevent the withdrawal of ground water from other aquifers and the movement of ground water between aquifers.
- 8) The entire length of the hole shall be geophysically logged as required by Rule 9 of the Statewide Nontributary Ground Water Rules prior to installing casing.
- 9) The owner shall mark the well in a conspicuous place with well permit number(s), name of the aquifer, and court case number(s) as appropriate. The owner shall take necessary means and precautions to preserve these markings.
- 10) A totalizing flow meter must be installed on this well and maintained in good working order. Permanent records of all diversions must be maintained by the well owner (recorded at least annually) and submitted to the Division Engineer upon request.
- 11) This well shall be constructed at least 600 feet from any existing well, completed in the same aquifer, that is not owned by the applicant.
- 12) This well shall be constructed not more than 200 feet from the location specified on this permit.
- 13) Pursuant to CRS 37-90-137(9)(b) and the Denver Basin Rules, no more than 98% of the nontributary ground water withdrawn annually shall be consumed and the well owner shall demonstrate to the reasonable satisfaction of the State Engineer that no more than 98% of the water withdrawn will be consumed.
- 14) This well is subject to administration by the Division Engineer in accordance with applicable decrees, statutes, rules, and regulations. NOTE: The ability of this well to withdraw its authorized amount of water from this non-renewable aquifer may be less than the 100 years upon which the amount of water in the aquifer is allocated, due to anticipated water level declines.

NOTE: To ensure a maximum productive life of this well, perforated casing should be set through the entire producing interval of the approved zone or aquifer indicated above.

NOTE: This permit will expire on the expiration date unless the well is constructed and a pump is installed by that date. A Well Construction and Test Report (GWS-31) and Pump Installation and Test Report (GWS-32) must be submitted to the Division of Water Resources to verify the well has been constructed and the pump has been installed. A one-time extension of the expiration date may be available. Contact the DWR for additional information or refer to the extension request form (GWS-64) available at: http://www.water.state.co.us

APPROVED IDC	Dil	Wille	Acruani	Cirl .
Receipt No. 3662756	State Engineer DATE ISSUED	12-19-2013	By EXPIRATION DATE	12-19-2014

LIC

Form No. GWS-25

OFFICE OF THE STATE ENGINEER COLORADO DIVISION OF WATER RESOURCES 818 Centennial Bldg., 1313 Sherman St., Denver, Colorado 80203

(303) 866-3581

WELL PER		77786	- F	
DIV. 2	WD 10	DES. BASIN	MD	

APPLICANT

APPROVED WELL LOCATION EL PASO COUNTY

NE 1/4 NW 1/4 Section 27 Township 12 S Range 65 W Sixth P.M.

DISTANCES FROM SECTION LINES

304Ft. from NorthSection Line2632Ft. from WestSection Line

(719) 491-3024

PERMIT TO CONSTRUCT A WELL

UTM COORDINATES (Meters,Zone:13,NAD83) Easting: Northing:

ISSUANCE OF THIS PERMIT DOES NOT CONFER A WATER RIGHT CONDITIONS OF APPROVAL

- 1) This well shall be used in such a way as to cause no material injury to existing water rights. The issuance of this permit does not ensure that no injury will occur to another vested water right or preclude another owner of a vested water right from seeking relief in a civil court action.
- 2) The construction of this well shall be in compliance with the Water Well Construction Rules 2 CCR 402-2, unless approval of a variance has been granted by the State Board of Examiners of Water Well Construction and Pump Installation Contractors in accordance with Rule 18.
- Approved pursuant to CRS 37-90-137(4) and the decree granted in case no. 86CW18 Division 2 Water Court. The operation of this well is subject to the terms and conditions of said decree.
- 4) The use of ground water from this well is limited to municipal, domestic, commercial, fire protection, industrial, residential, recreation, irrigation, augmentation, livestock watering and agricultural uses.
- 5) The pumping rate of this well shall not exceed 150 GPM.

MORLEY-BENTLEY INVESTMENTS LLC

20 BOULDER CRESCENT ST

COLORADO SPRINGS, CO 80903-

- 6) The average annual amount of ground water to be appropriated shall not exceed 575 acre-feet.
- 7) Production is limited to the Arapahoe aquifer which is located 1,585 feet below land surface and extends to a depth of 2,070 feet. Plain casing must be installed and grouted to prevent the withdrawal of ground water from other aquifers and the movement of ground water between aquifers.
- 8) The entire length of the hole shall be geophysically logged as required by Rule 9 of the Statewide Nontributary Ground Water Rules prior to installing casing.
- 9) The owner shall mark the well in a conspicuous place with well permit number(s), name of the aquifer, and court case number(s) as appropriate. The owner shall take necessary means and precautions to preserve these markings.
- 10) A totalizing flow meter must be installed on this well and maintained in good working order. Permanent records of all diversions must be maintained by the well owner (recorded at least annually) and submitted to the Division Engineer upon request.
- 11) This well shall be constructed at least 600 feet from any existing well, completed in the same aquifer, that is not owned by the applicant.
- 12) This well shall be constructed not more than 200 feet from the location specified on this permit.
- 13) Pursuant to CRS 37-90-137(9)(b) and the Denver Basin Rules, no more than 98% of the nontributary ground water withdrawn annually shall be consumed and the well owner shall demonstrate to the reasonable satisfaction of the State Engineer that no more than 98% of the water withdrawn will be consumed.
- 14) This well is subject to administration by the Division Engineer in accordance with applicable decrees, statutes, rules, and regulations. NOTE: The ability of this well to withdraw its authorized amount of water from this non-renewable aquifer may be less than the 100 years upon which the amount of water in the aquifer is allocated, due to anticipated water level declines.

NOTE: To ensure a maximum productive life of this well, perforated casing should be set through the entire producing interval of the approved zone or aquifer indicated above.

NOTE: This permit will expire on the expiration date unless the well is constructed and a pump is installed by that date. A Well Construction and Test Report (GWS-31) and Pump Installation and Test Report (GWS-32) must be submitted to the Division of Water Resources to verify the well has been constructed and the pump has been installed. A one-time extension of the expiration date may be available. Contact the DWR for additional information or refer to the extension request form (GWS-64) available at: http://www.water.state.co.us

·			0	1.0		
APPROVED			Inl	MA	hann	52
IDC		and l	Jalo	- 40	~ man	C.1
	State Engineer		- p	By		
Receipt No. 3662757	Ŧ	DATE ISSUED	12-19-2013	EXPIRAT	ION DATE	12-19-2014

LIC

OFFICE OF THE STATE ENGINEER Form No. **GWS-25** COLO

GWS-25 COLORADO I 818 Centennial Bldg., 13 (303) 866-3581	Sherman St., Denver, Colorado 8020		1148
	WELL PERMIT NUM	IBER 285607	
APPLICANT	DIV. 2 WD 10	DES. BASIN	MD
JOHN JAYNES		APPROVED WEL EL PASO COUNT NW 1/4 SE Township 12 S F	
8225 POCO RD COLORADO SPRINGS, C	O 80908-	DISTANCES FRO 2564 Ft. from So 1786 Ft. from Eas	
(719) 649-8584 PERMIT TO CONSTRUCT A WEI	L	UTM COORDINA Easting:	TES (Meters,Zone:13,NAD83) Northing:
ISSUA	NCE OF THIS PERMIT DOES N CONDITIONS OF A		RRIGHT
,	a way as to cause no material injury vill occur to another vested water rig ion.		•
,	all be in compliance with the Water by the State Board of Examiners of Rule 18.		· • •
/ // /	92-602(3)(b)(II)(A) as the only well o c. 28, Twp. 12 S, Rng. 65 W, Sixth		•
three (3) single family dwellings	nis well is limited to fire protection, o , the watering of poultry, domestic a 1) acre of home gardens and lawns	animals and livestock on a	
5) The pumping rate of this well sh	all not exceed 15 GPM.		
,	not exceed 460 feet, which corresp nd grouted through all unconsolidat		•

- into the bedrock formation to prevent production from other zones.
- The annual withdrawal of ground water from this well shall not exceed 3 acre-feet. 7)
- The return flow from the use of this well must be through an individual waste water disposal system of the 8) non-evaporative type where the water is returned to the same stream system in which the well is located.
- 9) This well shall be constructed not more than 200 feet from the location specified on this permit.

NOTE: This permit will expire on the expiration date unless the well is constructed by that date. A Well Construction and Test Report (GWS-31) must be submitted to the Division of Water Resources to verify the well has been constructed. An extension of the expiration date may be available. Contact the DWR for additional information or refer to the extension request form (GWS-64) available at: http://www.water.state.co.us/pubs/forms.asp

NOTICE: This permit has been approved for an increase in the annual amount of ground water to be withdrawn to be consistant with the amount of water from the Dawson aquifer excluded in Division 2 Court Case 07CW56. You are hereby notified that you have the right to appeal the issuance of this permit, by filing a written request with this office within sixty (60) days of the date of issuance, pursuant to the State Administrative Procedures Act. (See Section 24-4-104 through 106, C.R.S.)

	le	XANDUSAN
SMJ State Engineer Receipt No. 3649795 DATE ISSUED	05-04-2011	By EXPIRATION DATE 05-04-2013

· 1	COLORADO DIVISION OF WAT	ER RESOURCES	Office Use Only	Form GWS-44 (07/2009)
	DEPARTMENT OF NATURAL R	ESOURCES		A City
	1313 SHERMAN ST., RM 818, D	ENVER, CO 80203	1	
	phone - info: (303) 866-3587 main:	(303) 866-3581		
	fax: (303) 866-3589 http://www.wate	r.state.co.us	Δ	PR 0 8 2011
	RESIDENTIAL Note: Alex	use this form to apply for livestock watering	n	
i	Water Well Permit A		-NA1	EX READERCES
	Review form instructions prior to c	ompleting form.	51	ATE ENGINEER COLO
	The form must be completed in bla	ck or blue ink or typed.		
	1. Applicant Information		6. Use Of Well (check applic	able boxes)
	Name of applicant		See instructions to determine use(s)) for which you may qualify
	1 1		A. Ordinary household use in o	ne single-family dwelling
	John Jacoph		(no outside use)	in the second
	Mailing address	<u>^ 1</u>	B. Ordinary household use in 1	to 2 single toppily duplings
	1 8225 Pr	nKd	Number of dwellings:	to a single-lenning uwennings.
	City	Zip code	runnoer or owenings.	_
	Colorado minos (0 80908	Home garden/lawn inigat	ion, not to exceed one acre:
a retil		(optional)	area irrigated	🔲 sq. ft. 💓 acre
6498584	1919648-8584 m	aco250@msp.com	Domestic animal watering	
	2. Type Of Application (chec	k applicable boxes)		
	M Construct new well	Change source (aquifer)	C. Livestock watering (on farm/	ancriviangerpasture)
	Replace existing well	Reapplication (expired permit)	7. Well Data (proposed)	
	Use existing well	Reaftop precip. collection	Maximum pumping rate	Annual amount to be withdrawn
	Change or increase use	Other:	15 gpm	acre-feet
	3. Refer To (if applicable)		Total depth	Aquifer
	3. Keter 10 (II applicable)	Water Court case #	400 feet	In Kon
	AAGI Delunt 4.	FRIE COULDSS #	8. Water Supplier	
	Designated Basin Determination #	Well name of #		
	Designated Datif Detartimetoon #		Is this parcel within boundaries of a	water service area / LIYES K NO
		If (Importanti Cas Instructions)	If yes, provide name of supplier:	
	The structure of the st	II (Important! See Instructions)	9. Type Of Sewage System	
	County PLACEA	NW 1/4 of the SE 1/4	Septic tank / absorption leach fi	eld
	Section Township NorS	Range EorW Principal Megidian	Central system: District name:	
	Section 28 Township Nors	65 DN Sixth		
	Distance of well from section lines (section lines a		Vault: Location sewage to be had a sewage to be	auled to:
	2564 R. from [] NØS	1786 FL trom XEDW	Other (attach copy of engineering	ng design and report)
	For replacement wells only - distance and direction	1100 1	10. Proposed Well Driller L	icense #(optional) ////
	feet	direction	11. Signature Of Applicant	
	Well location address (Include City, State, Zip)	Check If well address is same as in Item 1.		A REAL PROPERTY AND A REAL
	~ .			ein constitutes perjury in the second ass 1 misdemeanor pursuant to C.R.S.
	Olles Lon Dd			tatements herein, know the contents
	STUD FUD NO		thereof and state that they are true	
	Optional: GPS well location information in UTM	formal. GPS unit settings are as follows:	Sign here (Must be original signature)	Dete
	Format must be UTM	518603	\square	
	Zone 12 or Zone 13 Units must be Meters	Lasang UX AQU	John Jay	en 4-4-11
	Units must be Meters Datum must be NAD83	Northing: 4314218	Print name & title	 Construction of the second s second second seco
	Unit must be set to true north		John Jacine	5 ouner
	Was GPS unit checked for above? XYES	Remember to set Datum to NAD83	Office Use Only	
	5. Parcel On Which Well Wi	I Be Located	USGS map name	DWR map no. Surface elev.
		DEED FOR THE SUBJECT PARCEL)		Maan
	A. You must check and complete one			
		or the minorarials	Receipt area	a offay
	Subdivision: Name	TT2f	12. Ant	
		Filing/Unit	Jacre feet	
	County exemption (attach copy of	of county approval & survey):	ľ v	
	Name/#	Lot #		
		· · · · · · · · · · · · · · · · · · ·		
	Parcel less than 35 acres, not in	a subdivision, attach a deed with metes		
		d prior to June 1, 1972, and a current	1 1	
	deed	Name 14		I tane human or or
	Mining claim (attach a copy of the date		AQUAMAP	Litans Number: 3649795
:	Square 40 acre parcel as descri		WE V	4/8/2011 12:53:48 I'M
1	Parcel of 35 or more acres (attach	a metes and bounds description or survey)	WR	Jen McKinney (24)
	Other (attach metes & bounds description			Total Trans AmE \$100.00
		C. Are your the owner of this parcel?		CHECK
1		XYES NO (If no-see instructions)	TOPO	Check Number: 1053
ţ	D. Will this be the only well on this parcel?	and a second		Check Amount: \$100.00
i	. vine and be allo only were despite parcer?		MYLAR	2. 10
İ	En	ARMANE		WD BA MD
	E. State Parcel ID# (optional): Oct	JULILAD		
1				

ĸ

Bedrock Aquifer Evaluation Determination Tool

Denver Basin Aquifer - Specific Location Determination Tool

Applicant:	Jaynes		
Receipt No:	3649795		
Evaluated By:	SJ		
Location:	NW 1/4 of SE 1/4 of Sec. 28, "	Г.12S, R.65W. (2564 SSI	L, 1786 ESL)
Basin Designation:	Location is within the UNKNO	WN Designated Ground W	later Basin.
Ground Surface Elevation:	7200 Feet	Number of Acres:	35.12

AQUIFER	ELEVA	FION (ft)	NET SAND	DEPTH	TO (ft)	ANNUAL	STATUS
	Bot.	Тор		Bot.	Тор	APPROP. (A- F)	
Upper Dawson	6742	7141	200.0	458	59	14.05	NNT
Lower Dawson							
Denver	5799	6716	303.4	1401	484	18.11	NNT
Upper Arapahoe	5274	5758	253.2	1926	1442	15.12	NT
Lower Arapahoe							
Laramie-Fox Hills	4727	5007	190.0	2473	2193	10.01	NT

NOTE: 'E' indicates a location is at an aquifer boundary and the values may be more approximate.

Page 1 of 2

EXHIBIT A

Public Record Property Information

Database Updated: 05/25/2010 Today: Thursday, April 21, 2011 Time: 2:52:23 PM

Personal Information

Schedule No: 5228000025

Owner Name: JAYNES JOHN R

Location: 8455 POCO RD

Mailing Address: 8225 POCO RD COLORADO SPRINGS CO 80908-4727

Previous Parcel

Replaced Parcel

Legal Description

THAT PT OF THE S2 SEC 28-12-65 DESC AS FOLS; COM AT CEN E 1/16 COR, TH S89<40'04"W ALG E-W CEN OF SD SEC 28 60.60 FT TO INTSEC THE S LN OF POCO RD W/THE W LN OF VOLLMER RD, SD PT BEING THE POB, TH S10<11'12"W 120.65 FT, S11<45'20"W 1045.96 FT, S89<40'04"W 1219.10FT, N00<15'34" W 1141.39 FT, TH N89<40'04"E 1458.72 FT TO POB

Market Information (2010Values)

Levy Year: 2010 Mill Levy: 77.764 Exempt Status: Not Exempt

Table	Use Code	2010 Market Value	2010 Assessed Value	Exempt
Land	VACANT LAND = 35 AND < 100 ACR	\$165,487	\$47,990	
	Total Value	\$165,487	\$47,990	

Tax Entity and Levy Information

(District: JCX)

Taxing Entity	Contact Name	Contact Phone
EL PASO COUNTY	COUNTY OFFICE BUILDING	(719) 520-6498
EPC ROAD & BRIDGE (UNSHARED)		(719) 520-6498
ACADEMY SCHOOL NO 20	TOM GREGORY	(719) 234-1200
PIKES PEAK LIBRARY	MIKE VARNET	(719) 531-6333
BLACK FOREST FIRE DISTRICT	FIRE CHIEF	(719) 495-4300
EL PASO COUNTY CONSERVATION	MADELINE NEWELL	(719) 473-7104

Sale Information

	Seq #	Sale Date	Sale Price	Sale Type
	1	01/06/2011	\$0	-
ļ	2	12/22/2010	\$0	-

http://www.land.elpasoco.com/ScheduleDisplayPrint.aspx?schd=5228000025

Land Information

Seq #	Use	Exempt	Area
1	VACANT LAND = 35 AND < 100 ACR		35.12 acres

Residential Information

Commercial Information

Public Record Property Information

Property Search	Personal	Information	RCENEL
<u>Parcel Map</u> <u>Print Data</u> County Zoning	Schedule	5228000025	APR 0 8 2011
<u>Map Sheet</u> 52280.tif	Owner Name:	JAYNES JOHN R	WATEL ALGULACES STATE ENGINEER COLO
<u></u>	Location:	8455 POCO RD	
	Mailing Address:	8225 POCO RD COLORADO SPRINGS CO 80908	

Legal Description

THAT PT OF THE S2 SEC 28-12-65 DESC AS FOLS; COM AT CEN E 1/16 COR, TH S89<40'04''W ALG E-W CEN OF SD SEC 28 60.60 FT TO INTSEC THE S LN OF POCO RD W/THE W LN OF VOLLMER RD, SD PT BEING THE POB, TH S10<11'12''W 120.65

Plat No: 0

Market Information (2010 Values)

Levy Year: 2010 Mill Levy: 77.764 Exempt Status: Not Exempt

Table	Use Code	2010 Market Value	2010 Assessed Value	Exempt
Land	VACANT LAND = 35 AND < 100 ACR	165487	47990	
	Total Value \$	165487	47990	

Tax Entity and Levy Information Estimated Property Tax Information

(District: JCX)

Taxing Entity	Contact Name	Contact Phone
EL PASO COUNTY	COUNTY OFFICE BUILDING	(719) 520-6498
EPC ROAD & BRIDGE (UNSHARED)		(719) 520-6498
		(74.6)



Assessor: Mark Lowderman

Location: 27 E. Vermijo Avenue 2nd Floor Colorado Springs, CO 80903-2208

Telephone: (719) 520-6600

Fax Number: (719) 520-6635

Hours: 8:00 AM - 5:00 PM Monday - Thursday Offices closed: Friday - Sunday, weekly

Send any concerns or comments to: asrweb@elpasoco.com

FORM NO.		VELL CONST	RUCTION A	ND TEST F	REPORT	For Office	Use Only
		LORADO, OFFI					RECEIVED
GWS-31 04/2005	1313 Sherman S	L, Room 818, Der	ver. CO 80203	3			
04/2005	Phone - info (30)	3) 866-3587 Mair	(303) 866-358	81			
	Fax (303) 866-35		http://www	w.water.state.c	x0.US	-	MAY 3 1 201
	RMIT NUMBER:	280	5607				WILL O T CON
	NER INFORMATIO	<u></u>				-	NATER RESOURCES
	WELL OWNER:	Taka	Javn	~~			STATE ENGINEER
	A		2 u ya	ES-	· · · · · · · · · · · · · · · · · · ·	-	coro
MAILING A	ADDRESS: X	225	Poco	Hd_	A	-	
CITY: C	nlorado Sp	CINSSTATE	: CD		ZIP CODE: 81908	_	
TELEPHO	NE NUMBER: (7)	911249-	8584		-1 -		
		D: Alulia	SF-1/4 S	a 28 1	Гwp Д 🖓 🗆 N or 🕅	S. Range 65	E or 🕅 W
WELL LOC	ATION AS DRILLE				section line and 1784	of the from KIF or I	W section line
		ES: 2567					
SUBDIVIS					, LOT, BLO	Ourseds Miell Des	
Ontional (GPS Location: GPS	Unit must use	the following	settings: For	mat must be UTM, Units	Conting	
must be m	eters, Datum must	be NAD83, Unit	must be set	to true N,	Zone 12 or 🗌 Zone 13		
	DDRESS AT WELL	LOCATION	8455	Poco k		Northing:	
				<u></u>		air rota	<u>cu</u>
	SURFACE ELEVAT				DRILLING METHOD		
DATE CO	WPLETED 5-1	<u>7-// т</u>	OTAL DEPTH	1 480	feet DEPTH COM		feet
GEOLOGI					6. HOLE DIAM (in.)	From (ft)	To (ft)
	Туре	Grain Size	Color	Water Loc.	9	O	41
Depth			<u> </u>	1	65	41	48D
7-1	Topsoil	-	<u> </u>	<u> </u>	······································	· <u></u>	
100	salano			<u> </u>			
152	gravel	Sandro	<u>kr</u>	<u> </u>	7. PLAIN CASING:		
165_	Clay 5	androck			OD (in) Kind	Wall Size (in) From	n (ft) To (ft)
206	aravel s	androci	<u>k</u>			<u></u>	
298	Osandra	ock			43 DVC	200 051 10	2 200
324	aravel.	sand roo	tk			/	
381	Osandra						
		Sandrec	k		PERFORATED CASIN	IG: Screen Slot Size	(in): 1/2 //
480	giavers	puna	¶ `	+	11/2 0.10	200 psí 20	480
					4-12- pre-	apple a	
						<u> </u>	
					8. FILTER PACK:	9. PACKER PLA	CEMENT:
					Material	_ Type	hher
		-			Size		
				1	Interval	Depth 2	$\overline{\Omega}$
			<u> </u>	+	10. GROUTING RECO		<u> </u>
			<u> </u>	1	Material Amount	Density Interval	Placement
	l		L			$536aa]_{b-4}$	1 Doured
Remarks:				·	Coment beack	s Jo gai to 4	- pour eq
					l	·	
I. DISINFE	CTION: Type	HTH			Amt. Used Q O		
	ST DATA: Che	k box if Test Da	ita is submitte	d on Form N	umber GWS 39 Suppler	nental Well Test.	
ESTING ME		iclisiant	•		مەر.		
				17-11		Lata 15	
		ate/Time measu			Production F		ι.
	el_ <u>440</u> ft. D	ate/Time measu	red5-	-11-11	Test Length	(nrs)	
			<u></u>				
- Pumping Lev Remarks:		herein and know	the contents th	ereof, and they	are true to my knowledge.	This document is signed	I and certified in
Pumping Lev Remarks:	the statements made			rk 402-2. [108	nung of a document that co	onuains raise statements i	s a violauon or
Pumping Lev Remarks: 3. I have read	Rule 17 4 of the Wat	er Well Constructi	011 Kulcs, 2 CC	0 and/or revoc	ation of the contracting lices		1
Pumping Lev Remarks: 3. I have read ccordance with ection 37-91-10	n Rule 17.4 of the Wat 08(1)(e), C.R.S., and i	er Well Constructi	nes up to \$500	0 and/or revoc			Number
condance with	n Rule 17.4 of the Wat 08(1)(e), C.R.S., and i	er Well Constructi	ines up to \$500	0 and/or revoc	Phone:	720 License	Number 1748
Pumping Lev Remarks: 3. I have read ccordance with ection 37-91-10	n Rule 17.4 of the Wat 08(1)(e), C.R.S., and i	er Well Constructi	illing	0 and/or revoc		720 License	Number 1748
Pumping Lev Remarks: 3. I have read ccordance with ection 37-91-10	n Rule 17.4 of the Wat 08(1)(e), C.R.S., and i ime:	er Well Constructi	illing ky La	0 and/or revoc LLC_ NP_			Number 148
Pumping Lev Remarks: 3. I have read coordance with ection 37-91-10 Company Na	n Rule 17.4 of the Wat 08(1)(e), C.R.S., and i ime:	er Well Constructi	illing ky La	D and/or revoc LLC NC Ma and Title		720 License	Date 2/(~1)

FORM NO. GWS-32 08/2008 BY 2008 BY	For Office Use Only RECEIVED
1. WELL PERMIT NUMBER: 2851007	WAY 3 1 2011
2. WELL OWNER INFORMATION NAME OF OWNER	STATE ENOMILITY
MAILING ADDRESS B225 POCO ROAD	
CITY STATE ZIP CODE COLO SPES CO SOPOS	
TELEPHONE # (7)9 1649 - 8584	
3. WELL LOCATION AS DRILLED: NU1/4, DE 1/4 Sec. 08, Twp. 12 IN ON	∑ S, Range <u>10</u> ⊆ E or ⊠0W
DISTANCES FROM SEC. LINES: 2564 ft. from IN or S section line and	
SUBDIVISION:, LOT	
Optional GPS Location: GPS Unit must use the following settings: Format must	be UTM, Units Easting: 528/003
must be meters, Datum must be NAD83, Unit must be set to true N, [] Zone 12 of	or 2 Zone 13 Northing: 4314218
STREET ADDRESS AT WELL LOCATION: 8455 POCO ROAD	27 (02 2000
4. PUMP DATA: Type: Submersible Da	te Installed: <u>5183, 2011</u>
Pump Manufacturer: JACUZZI Pump Model No. 7	
Design GPM: at RPM HP Volts Full L	
Pump Intake Depth: 440 Feet, Drop/Column Pipe Size Inches, Kind of Drop P	ipe <u>Prc</u>
ADDITIONAL INFORMATION FOR PUMPS GREATER THAN 50 GPM: Turbine Driver Typ	be: 🔲 Electric 🛄 Engine 🗋 Other
Design Head feet Number of Stages	Shaft size inches
5. <u>OTHER EQUIPMENT</u> : Airline Installed Yes ArNo, Orifice Depth ft Monitor Tube Installed	Yes 🔄 No, Depth ft
Meter Readout: Gallons, Thousand Gallons, Acre feet Beginning Reading	
6. <u>TEST DATA</u> : Check box if Test Data is submitted on Supplemental Form.	
Date:	
Total Well Depth: 480ft. Time:	
Static Level: ft. Rate (gpm):	
Date Measured: 5117111 Pumping Level (ft): 440	
7. DISINFECTION: Type 4774 Amt. Used	1002
8. Water Quality analysis available: 🔲 Yes 🕅 No If yes, please submit with this report.	
9. Remarks:	
10. I have read the statements made herein and know the contents thereof, and they are true certified in accordance with Rule 17.4 of the Water Well Construction Rules, 2 CCR 402-2 statements is a violation of section 37-91-108(1)(e), C.R.S., and is punishable by fines up license.]	The filing of a document that contains false
Company Name: Kundle Drilling LLC Phone:	License Number
Mailing Address	3-3120 1148
Signature:	DOR have
	ner 5-26/1

×

	Ear Offer Her Only
FormSTATE OF COLORADONo.OFFICE OF THE STATE ENGINEERGWS-11818 Centennial Bldg., 1313 Sherman St., Denver, CO 80203	For Office Use Only RECEIVED
1/2009 Phone – Info: (303) 866-3587 Main: (303) 866-3581 Fax: (303) 866-3589 http://www.water.state.co.us	RL V
CHANGE IN OWNER NAME/ADDRESS CORRECTION OF THE WELL LOCATION	AUG 192011
Review instructions on the reverse side prior to completing the form.	WATER RÉSOURCES WATE ENGINEER STATE ENGINEER
Name, address and phone of person claiming ownership of the well permit:	· · · · · · · · · · · · · · · · · · ·
NAME(S): Kelley M Scheinert	
Mailing Address: 8225 POCO Rd	
City, St. Zip: <u>C15</u> Co 80908	
Phone: (119) 238-2632	
E-mail (optional): Kelley bear 7@ aol. Com	
This form is filed by the named individual/entity claiming that they are the own filing is made pursuant to C.R.S. 37-90-143.	er of the well permit as referenced below. This
WELL LOCATION: Well Permit Number: 285007 Receipt Num	iber:344 9795case Number:
County EI PUSD Well Name	or # (optional)
County EL PUSO 8225 POCO Road COLOVADO- (Address)	SPVINGS (1) 80908
(Address) (C \underline{NW} 1/4 of the \underline{SE} 1/4, Sec. \underline{ZS} , Twp. $\underline{12}$ \Box N. or \underline{N} S., Range \underline{L}	$5 \square E. or XW. SYM P.M.$
Distance from Section Lines: 2564 Ft. From N. or S., Subdivision Name Jay MCS Lot	
The above listed owner(s) say(s) that he, she (they) own the well permit desc amended for the following reasons:	ribed herein. The existing record is being
Change in name of owner Change in mailing address Correction of 8, 1972 and non-exempt wells permitted before May 17, 1965.	location for exempt wells permitted prior to May
Please see the reverse side for further information regarding correction of the	well location.
I (we) claim and say that I (we) (are) the owner(s) of the well permit described made herein, and state that they are true to my (our) knowledge.	above, know the contents of the statements
Signature(s) of the new owner Please print the Signer's Nan	ne & Title Date
Kelley M Scheinert Kelley MSC	heinert 8-17-11
It is the responsibility of the new owner of this well permit to complete and sig	in this form. Signatures of agents are acceptable
if an original letter of agency signed by the owner is attached to the form upon For Office Use Only	n its receipt.
	CEPTED AS A CHANGE OF OWNERSHIP B/OR MAILING ADDRESS
	B/OR MAILING ADDRESS
Did Wolfe Mind	9-8-4
State Engineer By	Date

APPENDIX E WATER QUALITY FROM EXISTING WELLS







RESPEC.COM

Coloredo Department of Public Health and Environment	1 #	Inor 4300 Fax	Inorganic Chemicals Certified Laboratory Report Forn WQCD - Drinking Water CAS 4300 Cherry Creek Drive South, Denver, CO 80246-153 Fax: (303) 758-1398; cdphe.drinkingwater@state.co.us	emicals Certified Laboratory Report Form WQCD - Drinking Water CAS Creek Drive South, Denver, CO 80246-1530 58-1398; cdphe.drinkingwater@state.co.us	orm 1530 D.us		Revise	Revised 6/13/2014
S	ection I (Sumlied	Section 1 (Sumlied or Completed by Public Water System)	Water System)	Section II (Su	Section II (Supplied or Completed by Certified Laboratory)	w Certified La	aboratory)	
	Public V	Public Water System Information	tion	U	Certified Laboratory Information	nformation		
PWSID#: CO-0121724	121724			Laboratory ID: CO 0015				
System Name: LFH-1	LFH-1			Laboratory Name: Colorado Analytical Laboratory	o Analytical Laborato	L,		
Contact Person: Mark Volle	: Mark Vollc		Phone #: 719-227-0072	Contact Person: Customer Service		Phone: 303-659-2313	2313	
Comments:			Do Samples Need to be Composited BY THE LAB?	Comments:				
			Section III (Supplied or Comp	(Supplied or Completed by Public Water System)	0			
Sample Date: 2/16/17		Collector: Stephanie Schwe Facility II	Facility ID (On Schedule):	San	Sample Pt II) (On Schedule):	le):		
		Seci	Section IV Inorganic Chemicals (Completed by Certified Laboratory)	ompleted by Certified Labon	utory)			
Lab Receipt Date	I ab Analysis Date	Lab Sample II)	Analyte Name	CAS No	Analytical Method	MCL.	Lab MRL	Result (mo/1)
2/17/17	2/17/17	170217005-01	Fluoride	7681-49-4	EPA 300.0	4	60.0	1.07

NT: Not Tested Lab MRL: Laboratory Minimum Reporting Level BDL: Below Laboratory MRL. A less than (<) may also used.

mg/L: Milligrams per Liter MCL: Maximum Contaminant Level







Q		Inor	ganic Chemicals Certified Laboratory] WOCD - Drinking Water CAS	Inorganic Chemicals Certified Laboratory Report Form WOCD - Drinking Water CAS	a		Revise	Revised 4/13/2015
Colorado Departarent of Public Flealth red Environment	NI 100	Subn	nit Online at http://www	Submit Online at http://www.wqcdcompliance.com/login	E			IOC
	Section I (Supplies	Section I (Sumplied or Completed by Public Water Syst	: Water System)	Section II (Sumlie	Section II (Sumplied or Completed hy Certified I aboratory)	stified Lab	matory	
	Public	Public Water System Information	tion	Certifi	Certified Laboratory Information	mation	11 100 10 100	
PWSID#: CO-0121724	-0121724			Laboratory ID: CO 0015				
System Name: LFH-1	LFH-1			Laboratory Name: Colorado Analytical Laboratory	alytical Laboratory			
Contact Person	Contact Person: Mark Volle		Phone #:	Contact Person: Customer Service	Phone:	303-659-2313	313	
Comments:			Do Samples Need to be Composited BY THE LAB?	Comments:				
			Section III (Supplied or Compl	(Supplied or Completed by Public Water System)				
Sample Date: 2/16/17		lector: Stephanie Schwe	Collector: Stephanie Schwe Facility ID (On Schedule):	Sample F	Sample Pt ID (On Schedule):			
Tak Daries			tion IV Inorganic Chemicals (C	Section IV Inorganic Chemicals (Completed by Certified Laboratory)				
Date	t an Analysis Date	Lao Sampie II)	Analyte Name	CAS No	Analytical Method	MCL.	Lab MRL.	Result
2/17/17	2/22/17	170217005-01A	Antimony	7740-36-0	or	0.006	0.001	BD1.
2/17/17	2/22/17	170217005-01A	Arsenic	7440-38-2	EPA 200.8 0	0.01	0.001	0.002
2/1/1/2	2/22/17	170217005-01A	Barium	7440-39-3	EPA 200.8	2	0.001	0.015
11/1/1/2	2/22/17	170217005-01A	Beryllium	7440-41-7	EPA 200.8 0.	0.004	0.001	BDL
21/1/1/2	2/22/17	170217005-01A	Cadmium	7440-43-9	EPA 200.8 0.	0.005	0.001	BDL
1111.172	2/22/17	170217005-01A	Chromium	7440-47-3	EPA 200.8 (0.1	0.001	0.001
2/1/1/2	2/22/17	170217005-01A	Mercury	7439-97-6	EPA 200.8 0.	0.002	0.001	BDL
LV/LV/Z	2/22/17	170217005-01A	Nickel	7440-02-0	EPA 200.8 N	N/A	0.001	0.001
11/1.1/2	2/22/17	170217005-01A	Selenium	7782-49-2	EPA 200.8 0	0.05	0.001	BDL
11/1/17	2/24/17	170217005-01A	Sodium	7440-23-5	EPA 200.7 N	N/A	0.1	142.7
11/11/7	11/77/7	170217005-01A	Thallium	7440-28-0	EPA 200.8 0.	0.002	0.001	BDL

NT: Not Tested Lab MRL: Laboratory Minimum Reporting Level BDI.: Below Laboratory MRL. A less than (<) may also used.

mg/L: Milligrams per Liter MCL: Maximum Contaminant Level







Customer ID: 20040H Account ID: Z01034 Project #: 009-616 ANALYTICAL REPORT

Stuart Nielson Colorado Analytical Laboratories, Inc.

L	ab Sam	ple ID	B16917-001	· ·				
Custom	er Sam	iple ID	170217005-	01 - Lfh-1 - F	WSID: CO	0121724 - LFH-1		
				sampled or	n 02/16/17 (@ 0906 by Stephanie Sch	wenke	
				Precision*	Detection		Analysis	
Parameter		Code	Result	+/-	Limit	Method	Date / Time	Analyst
Gross Alpha	1.4	Т	0.0	0.0	1.5	SM 7110 B	3/2/17 @ 0840	LD
	pCI/L	Т	0.0	2.1	2.2	SM 7110 B	3/2/17 @ 0840	LD
Radium-226	pCI/L	Т	0.0	0.2	0.1	SM 7500-Ra B	3/3/17 @ 0825	LD
	pCi/L	Т	0.0	0.8	0.8	EPA Ra-05	3/14/17 @ 1257	JR
Radon	pCi/L	Т	345	25	13.9	SM 7500-Rn B	2/17/17 @ 1500	AN

Certification ID's: CO/EPA CO00008; CT PH-0152; KS E-10265; NJ CO008; NYSELAP (NELAC Certified) 11417; RI LAO00284; WI 998376610, TX T104704256-15-6

*Variability of the radioactive decay process (counting error) at the 95% confidence level, 1.96 sigma.

Codes: (T) = Total (D) = Dissolved (S) = Susspended (R) = Total Residual (PD) = Potentially Dissolved <= Less Than

			Radionuclide	s Certifie	d Laboratory	Radionuclides Certified Laboratory Report Form			Revision	Revision 6/13/2014
			M	QCD - Dri	WQCD - Drinking Water CAS	CAS				(
Colorado Department		43	00 Cherry Cre	ek Drive S	South; Denver	4300 Cherry Creek Drive South; Denver, CO 80246-1530			02	SAD
of Public Health		ł	Fax: (303) 758-	-1398; cdp	he.drinkingw	(303) 758-1398; cdphe.drinkingwater@state.co.us				
		Section I (Supplied or Completed by Public	sblic Water System)	(iii		Section II (Supplied or Completed by Certified Laboratory)	ed or Completed	by Certified 1	Laboratory)	
		Public Water System Information				Certified L	Certified Laboratory Information	nation		
PWS ID: C00121724	21724				Laboratory ID: CO 00008	00008				
System Name: Lfh-1	L.Ab-1				Laboratory Name:	Laboratory Name: Hazen Research, Inc.				
Contact Person:			Phone #:		Contact Person: Jessica Axen	ssica Axen		Phone #: 303-279-4501	-279-4501	
Comments:			Do Samples Need to be	4	Comments:					
			Composited <u>BY THE LAB?</u>							·
			Section I	II (Supplied	or Completed by	Section III (Supplied or Completed by Public Water System)				
Sample Date: 02/16/2017	02/16/2017	Collector: Stephanie Schwenke Facility ID (On Schedule):	Facility ID (On	Schedule):	Sam	Sample Pt ID (On Schedule):				
			Section IV Radi	onuclides (Su	applied or Comple	Section IV Radionuclides (Supplied or Completed by Certified Laboratory)	lory)			
Lab Receipt Date	Lab Receipt Lab Analysis Date Date	s Lab Sample ID	Analy	Analyte Name (Code)	ode)	CAS No.	Analytical Method	MCL	Lab MRL	Result
610021/00	03/02/2017	B16017-001	Gross Alpha Including Uranium (4002)	acluding Ura	anium (4002)	12587-46-1	SM 7110 B	N/A	1.5	0.0(±0.0)
110711100			Combin	Combined Uranium (4006)	(900+)	7440-61-1	D2907-97	30 ug/L		
02/17/2017	03/03/2017	B16917-001	Radi	Radium -226 (4020)	20)	13982-63-3	SM 7500-Ra B	N/A	0.1	0.0(±0.2)
02/17/2017	03/14/2017	B16917-001	Radi	Radium -228 (4030)	30)	15262-20-1	EPA Ra-05	N/A	0.8	0.0(±0.8)
02/17/2017	03/02/2017	B16917-001	Gro	Gross Beta (4100)	(0)	12587-47-2	SM 7110 B	50 pCi/L*	2.2	0.0(±2.1)
			Total Dis	Total Dissolved Solids (1930)	ls (1930)		EPA 160.3	N/A		
*The MCL ft	or Gross Beta	*The MCL for Gross Beta Particle Activity is 4 mrem/year. Si	Ir. Since there is	no simple co	onversion betwee	nce there is no simple conversion between mrem/year and pCi/L EPA considers 50 pCi/L to be the level of concern.	EPA considers 2	50 pCi/L to b	be the level	of concern.
			Section V (Section V Calculated Values	alues					
		N/N	Gross Alpha Excluding Uranium (4000)	xcluding Un	anium (4000)	Calculated Value	alue	15 pCi/L	N/A	
		14 F.F.	Combined Radium {-226 & -228} (4010)	ium {-226 &	:-228} (4010)	Calculated Value	alue	5 pCi/L	N/A	
Z	NT: Not Tested					ug/L: Micrograms per Liter	as per Liter			5
Ľ	ib MRL: Labo	Lab MRL: Laboratory Minimum Reporting Level				pCi/L: Picocuries per Liter	s per Liter			
BI	DL: Below La	BDL: Below Laboratory MRL. A less than sign (<)	n (<) may also be used	e used		MCL: Maximum Contaminant Level	Contaminant L	evel		

MCL: Maximum Contaminant Level

Drinking	
Water	
Chain	
of Cust	
ody	

	Construction of the second of the second sec		
Report To Information	Bill To Information (If different from report to)	State Form / Project Information	Colorado Analytical
Company Name: <u>Colorado Analytical</u>	Company Name: Same As Report To	PWSID: C00121724	Brighton Lab
Contact Name: Stuart Nielson	Contact Name:	System Name: Lfn-1	240 South Main Street Brighton, CO 80601
Address: <u>240 S. Main St.</u>	Address:	System Address: Ne 1/4 Nw 1/4 S27	Lakewood Lab 12860 W. Cedar Dr. Suite 101
City: Brighton State: CO Zip: 80601	City: State: Zip:	T125 R65w 6th Pm City: Colorado Spgs State: CO Zip: 80908	Lakewood CO 80228
Phone:303-659-2313 Fax:303-659-2315	Phone: Fax:	County: El Paso	Phone: 303-659-2313 Fax: 303-659-2315
Email: stuartnielson@coloradolab.com	Email:	Compliance Samples: Yes 🕅 No 🗌	www.coloradolab.com
Sampler Name: Stephanie Schwenke	PO No.:	Send Forms to State: Yes 🗌 No 🕅	
	PHASE I, I	PHASE I, II, V Drinking Water Analyses (check analysis)	nalysis) Subcontract Analyses

<	Relinquished By:	1.8	-	Instruct						02/16/17	Date		Task	
	shed By:			ions:Pleas					LF	0906	Time		Task Number	
l	4			e print on s					Mas		Client S			
011	Date/Time:			Instructions: Please print on state forms but do not submit to CDPHE. Thanks!					BOTTLES	170217005-01 LFH-1	Client Sample ID / EP Code			
3	6 Rec			do not sub				1	S		IP Code			
	Received By:			mit to C						6	No. o	f Containers		
				DPHE. Th							(mg/l	ual Chlorino _) iamples Only		
				anks!							Tota	Coliform P/	Ά	
											504.	EDB/DBCI	P	
	Date/Time:										505	Pests/PCBs		
	Time										515.4	4 Herbicides		PH
											524.2	2 VOCs		ASE
		Deli		C/S Info:							525.2	2 SOCs-Pest		I, E
	Reli	Delivered Via:		Info;							531.	I Carbamates	;	LV.
	nquis	Via:									547 (Glyphosate		Dria
	Relinquished By:	F	5								548.	I Endothall		PHASE I, II, V Drinking
	ly:	X3 7	F								549.2	2 Diquat		
		S	tage								52.4.2	2 TTHMs		uter .
			Ç								552.2	2 HAA5s		Anal
	Date	C/S Charge									Lead	/Copper		lyses
	Date/Time:	narge		i							Nitra	te		
			\cap								Nitri	te		eck i
		Temp.	100	Seal							Fluo	ride		Water Analyses (check analysis)
	RER		R	Seals Present	Þ						Inorg	anics		ysis)
	A.	°C /Ice	à		Ċ						Alk./	Lang. Index		
		• 8	T	Yes 🗆							TOC	, DOC (Circl	e)	
	Y	Sam	2	No							SUVA	, UV 254 (Circle)	
	0	ple Ph	3	포										
	Date/Time:	Sample Pres. Yes 🔲 No 🗌	٢	Headspace						\boxtimes	Gros	s Alpha/Beta		Sabe
	Dat 7/	Ű	##	ace Yes						\boxtimes	Radi	um 226		ontra
	e/Tim	No.	HAZE		¢					\boxtimes	Radi	um 228		let A
	Date/Time: 43		12	No No	6					\boxtimes	Rado	n		Subcontract Analyses
	0			7							Uran	ium		ž

FEDEX



Ś



Report To: Mark Volle Company: JDS Hydro Consultants 545 E. Pikes Peak Ave Suite 300 Colorado Springs CO 80903 **Analytical Results**

TASK NO: 170217005

Bill To: Jim Morley Company: SR Water 20 Boulder Crescent St. Colorado Springs CO 80903

Task No.: 170217005 Client PO: Client Project: LFH-1 CO-0121724

Date Received: 2/17/17 Date Reported: 3/6/17 Matrix: Water - Drinking

Customer Sample ID LFH-1 Sample Date/Time: 2/16/17 Lab Number: 170217005-01


Test	Result	Method	ML	Date Analyzed	Analyzed By
Bicarbonate	155.5 mg/L as CaCO3	SM 2320-B	0.1	2/20/17	VDB
Calcium as CaCO3	6.3 mg/L	SM 3111-B	0.1	2/24/17	MBN
Carbonate	4.0 mg/L as CaCO3	SM 2320-B	0.1	2/20/17	VDB
Langelier Index	-0.43 units	SM 2330-B		2/24/17	SAN
pH	8.44 units	SM 4500-H-B	0.01	2/17/17	MBN
Temperature	20 °C	SM 4500-H-B	1	2/17/17	MBN
Total Alkalinity	159.5 mg/L as CaCO3	SM 2320-B	0.1	2/20/17	VDB
Total Dissolved Solids	456 mg/L	SM 2540-C	5	2/23/17	ISG


Abbreviations/ References:

ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpn/100 mis = Most Probable Number Index/ 100 mis Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

240 South Main Street / Brighton, CO 80601-0507 / 303-659-2313 Mailing Address: P.O. Box 507 / Brighton, CO 80601-0507 / Fax: 303-659-2315 Page 1 of 3







Collarado Departorent of Pedite (fealth and Eaviconment	Nitrate and Nitrite Submit Onlin	Vitrite as N WQC Online at 1	Vitrogen C JD - Drink http://wwv	e as Nitrogen Certified Laboral WQCD - Drinking Water CAS ie at http://www.wqcdcomplian	e as Nitrogen Certified Laboratory Report Form WQCD - Drinking Water CAS ie at http://www.wqcdcompliance.com/login	port Form /login			Revised	Revised 4/13/2015 NOX
Section I (Sumplied or Completed by Public Water System)	ed by Public Wa	ter System)			Section II (Su	Section II (Supplied or Completed by Certified Laboratory)	pleted by Cer	tified Laho	hatory	
Public Water System Information	an Information					Certified Laboratory Information	atory Inform	nation		
PWSID#: CO-0121724				Laborator	Laboratory ID: CO 0015					
System Name: LFH-1				Laborator	Laboratory Name: Colorado Analytical Laboratory	do Analytical Li	aboratory			
Contact Person: Mark Volle	Ph	Phone #: 719-	719-227-0072	Contact P	Contact Person: Customer Service	Service	Phone: 3	Phone: 303-659-2313	13	
Comments:				Comments:	rs:					
Section III (Supplied or Completed by Public Water System)	ublic Water Syst	tem)		Secti	Section IV (Supplied or Completed by Certified Laboratory)	or Completed b	y Certified L	aboratory)		
Sample Collector Facility ID On Schedule Date	Sample Pt II) (On Schedule	Confirmation?	Lab Receipt Date	Lab Analysis Date	I aboratory Sample ID #	Analyte	Analytical Method	MCL)	Lab MRL. (mg/L)	Result (me/L)
2/16/17 cphanic Schwenk			2/17/17	2/17/17	170217005-01	Nitrate Nitrogen	EPA 300.0	10	0.1	BDL
2/16/17 cephanie Schwenk			2/17/17	2/17/17	170217005-01	Nitrite Nitrogen	EPA 300.0	-	0.1	BDL

NT: Not Tested Lab MRI.: Laboratory Minimum Reporting Level BIDL: Below Laboratory MRI., A less than (<) may also used.

mg/L: Milligrams per Liter MCL: Maximum Contaminant Level





Colonado Deparement of Pasiki itetata ad Expisit itetata Section I (Supplied or Public Wa PWSID#: CO-0121724 System Name: LFH-1 System Name: LFH-1 Contact Person: Mark Volle	Subn						
Public Wa Public Wa		out Unune at attp://www	Submit Online at http://www.wqcdcompliance.com/login	ців		VOC	VOC/SOC
Volle	Section I (Supplied or Completed by Public Water System) Public Water System Information	: Water System) fian	Section JI (Supp	Section JI (Supplied or Completed by Certified Laboratory) Contified Laboratory Information	by Certified L	aboratory)	
Volle			Laboratory ID: CO 00063				
Volle			Laboratory Name: Colorado Analytical Laboratory	Analytical Laborato	, KIK		
		Phone #: 719-227-0072	Contact Person: Customer Service		Phone: 303-659-2313	-2313	
		Do Samples Need to be Composited BY THE LAB?	Comments:				
		Section V (Supplied or Connol	(Supplied or Completed by Public Water System)				
Coll	Collector: Stephanie Schwenk Facil	wenk Facility ID (On Schedule):	Sample	Sample Pt ID (On Schedule):			
	Section VJ Sy	nthetic Organic Chemicals (Sup	Section VI Synthetic Organic Chemicals (Supplied or Completed by Certified Laboratory)	I Laboratory)			
Lab Analysis Date	Lab Sample ID	Analyte Name	CAS No.	Analytical Method	MCL (up/L)	Lab MRL (ug/L)	Result (ue/L.)
2/24/17	170217005-01E	Dibromochloropropane	96-12-8	EPA 504.1	0.2	0.02	BDL
3/1/17	170217005-01G	2,4,-D	94-75-7	EPA 515.4	70	0.1	BDL
3/1/17	170217005-01G	2,4.5-TP	93-72-1	EPA 515.4	50	0.2	BDL
2/23/17	170217005-01H	Alachlor	15972-60-8	EPA 525.2	2	0.2	BDL.
11/7/2	110-200/120/1	Aldicarb	116-06-3	EPA 531.1	N/A	9.6	BDL
3/2/17	170217005-011	Aldicarh suffixide	1040-00-4	EPA 531.1	A/N		BDL
2/23/17	1170217005-0111	Attazine	1912-24-9	EPA 525.2	3	0.1	BDL
2/23/17	170217005-01H	Benzo(a)pyrene	50-32-8	EPA 525.2	0.2	0.02	BDI.
3/2/17	170217005-011	Carbofuran	1563-66-2	EPA 531.1	40	0.9	BDL
2/24/17	170217005-01F	Chlordane	57-74-9	EPA 505	2	0.2	BDI,
3/1/7	170217005-01G	Dalapon	75-99-0	EPA 515.4	200	1	BDL
2/23/17	170217005-0111	Di(2-ethylhexyl)adipate	103-23-1	EPA 525.2	400	0.6	BDL
2/23/17	170217005-01H	Di(2-cthylhexyl)phthalate	117-81-7	EPA 525.2	6	0.6	BDI.
3/1/17	170217005-01G	Dinosch	85-85-7	EPA 515.4	7	0.2	BDL
2/23/17	170217005-01K	Diquat	85-00-7	EPA 549.2	20	0.4	BDL
2/23/17	170217005-01J	Endothall	145-73-3	FPA 548.1	100	6	BDL
212411	110-500/170/1	Endrin	72-20-8	EPA 505	2	0.01	BDL
2/24/17	170217005-01E	Ethylene dibromide	106-93-4	EPA 504.1	0.05	0.01	BDI.
2/23/17	170217005-01H	Heptachlor	76-44-8	EPA 525.2	0.4	0.04	BDL
2/24/17	170217005-01F	Heptachlor epoxide	1024-57-3	EPA 505	0.2	0.02	BDL


Page 1 of 4


			Result	('T/8n)	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDI.	BDI,
				3										
			Lab MRL	('T/Bn)	0.1	0.1	0.02	0.1	-	0.04	0.1	0.1	0.07	
			MCL	(rt/@n)	1	50	0.2	40	200	-	500	0.5	4	9
	Sample Pt ID (On Schedule):	aboratory)	Analytical	Method	EPA 505	EPA 505	EPA 505	EPA 505	I:PA 531.1	EPA 515.4	EPA 515.4	EPA 505	EPA 525.2	EPA 505
olic Water System)	Sample Pt	impleted by Certified Li	CAS No.		118-74-1	77-47-4	58-89-9	72-43-5	23135-22-0	87-86-5	1918-02-1	1336-36-3	122-34-9	8001-35-2
Section V (Supplied or Completed by Public Water System)	chwenk Facility ID (On Schedule):	Section VI Synthetic Organic Chemicals (Supplied or Completed by Certified Laboratory)	Analyte Name		Hexachlorobenzene	Hexachlwrocyclopentadienc	Lindane	Methoxychlor	Oxamyl	Pentachlorophenol	Picloram	Polychlorinated hiphenyl's	Simazine	Toxaphene
	Collector: Stephanie Schwenk Facil	Section VI S	Lab Sample ID		170217005-01F	170217005-01F	170217005-01F	170217005-01F	170217005-011	170217005-01G	170217005-01G	170217005-01F	170217005-01H	170217005-01F
21724	6/17	and the second se	Lab Analysis	Date	2/24/17	2/24/17	2/24/17	2/24/17	3/2/17	3/1/17	3/1/17	2/24/17	2/23/17	2/24/17
PWSID#: CO-0121724	Sample Date: 2/16/17		Lab Receipt	Date	2/17/17	2/17/17	2/17/17	2/17/17	2/17/17	2/1/17	2/17/17	2/17/17	2/17/17	2/17/17

NT: Not Tested ug/L: Micrograms per Liter MCL: Maximum Contaminant Level BDL Below Laboratory MRL A less than sign (<) may also he used.

170217005-01

212. 3/8/17







Report To: Mark Volle Company: JDS Hydro Consultants 545 E. Pikes Peak Ave Suite 300 Colorado Springs CO 80903

Analytical Results

TASK NO: 170217005

Bill To: Jim Morley Company: SR Water 20 Boulder Crescent St. Colorado Springs CO 80903

Task No.: 170217005 Client PO: Client Project: LFH-1 CO-0121724

Date Received: 2/17/17 Date Reported: 3/6/17 Matrix: Water - Drinking

Customer Sample ID	LFH-1
Sample Date/Time:	2/16/17

Lab Number: 170217005-01

Test	Result	Method	ML	Date Analyzed	Analyzed By
Chloride	5.8 mg/L	EPA 300.0	0.1 mg/L	2/17/17	ШG
Cyanide-Free	< 0.005 mg/L	EPA 335.4	0.005 mg/L	2/24/17	VDB
E-Coli	< 1 mpn/100ml	Colilert	1 mpn/100ml	2/18/17	VDB
Sulfate	142.1 mg/L	EPA 300.0	0.1 mg/L	2/17/17	ЦG
Total Coliform	93 mpn/100ml	Colliert	1 mpn/100ml	2/18/17	VDB
Total Organic Carbon	0.8 mg/L	SM 5310-C	0.5 mg/L	2/23/17	ISG
Turbidity	2.49 NTU	SM 2130-B	0.01 NTU	2/17/17	MBN
<u>Total</u>					
Aluminum	0.053 mg/L	EPA 200.8	0.001 mg/L	2/22/17	TCD
Calcium	2.5 mg/L	EPA 200.7	0.1 mg/L	2/22/17	MBN
Соррег	0.0026 mg/L	EPA 200.8	0.0008 mg/L	2/22/17	TCD
iron	0.602 mg/L	EPA 200.7	0.005 mg/L	2/24/17	MBN
Lead	0.0005 mg/L	EPA 200.8	0.0001 mg/L	2/22/17	TCD
Magnesium	0.39 mg/L	EPA 200.7	0.02 mg/L	2/22/17	MBN
Manganese	0.0259 mg/L	EPA 200.8	0.0008 mg/L	2/22/17	TCD
Potassium	1.6 mg/L	EPA 200.7	0.1 mg/L	2/22/17	MBN
Silver	< 0.0001 mg/L	EPA 200.8	0.0001 mg/L	2/22/17	TCD
Strontium	0.037 mg/L	EPA 200.8	0.005 mg/L	2/22/17	TCD
Total Hardness	7.7 mg/L as CaCO3	SM 2340-B	0.1 mg/L as CaCO3	2/24/17	MBN
Uranium	< 0.0002 mg/L	EPA 200.8	0.0002 mg/L	2/22/17	TCD
Zinc	0.004 mg/L	EPA 200.8	0.001 mg/L	2/22/17	TCD

Abbreviations/ References:

ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpn/100 mis = Most Probable Number Index/ 100 mis Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

240 South Main Street / Brighton, CO 80601-0507 / 303-659-2313 Mailing Address: P.O. Box 507 / Brighton, CO 80601-0507 / Fax: 303-659-2315 Page 1 of 4



Report To: Mark Volie Company: JDS Hydro Consultants 545 E. Pikes Peak Ave Suite 300 Colorado Springs CO 80903

Analytical Results

TASK NO: 170217005

Bill To: Jim Morley Company: SR Water 20 Boulder Crescent St. Colorado Springs CO 80903

Task No.: 17 Client PO: Client Project: LF			Received: 2/17/17 Reported: 3/6/17 Matrix: Water		
Customer Sample Sample Date/J Lab Nun					
Test	Result	Method	ML.	Date Analyzed	Analyzed By
<u>Tota/</u> Zinc	0.005 mg/L	EPA 200.8	0.001 mg/L	. 2/22/17	TCD


Abbreviations/ References:


ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpn/100 mls = Most Probable Number Index/ 100 mls Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

240 South Main Street / Brighton, CO 80601-0507 / 303-659-2313 Mailing Address: P.O. Box 507 / Brighton, CO 80601-0507 / Fax: 303-659-2315 Page 2 of 4

170217005 2/2







Billings, MT 800.735.4489 • Casper, WY 888.235.0515 College Station, TX 888.690.2218 • Gillette, WY 866.686.7175 • Helena, MT 877.472.0711

ANALYTICAL SUMMARY REPORT

March 02, 2017

Colorado Analytical Laboratories Inc PO Drawer 507 Brighton, CO 80601

Work Order: C17020566 Quote ID: C4542 - 624, 625, 1,4-Dioxane

Project Name: 170217005 LFH-1 CO-0121724

Energy Laboratories, Inc. Casper WY received the following 1 sample for Colorado Analytical Laboratories Inc on 2/21/2017 for analysis.

Lab ID	Client Sample ID	Collect Date R	eceive Date	Matrix	Test
C17020566-001	170217005-01 LFH-1	02/16/17 0:00	02/21/17	Drinking Water	Azeotropic Distilation Separatory Funnel Liquid-Liquid Ext. Semi-Volatile Organic Compounds 624-Purgeable Organics Volatile Compounds by Azeotropic Distillation

The results as reported relate only to the item(s) submitted for testing. The analyses presented in this report were performed at Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the Laboratory Analytical Report, the QA/QC Summary Report, or the Case Narrative.

If you have any questions regarding these test results, please call.

Report Approved By:

20

Digitally signed by Randy Horton Date: 2017.03.02 10:49:28 -07:00

ENERGY	Trust our People. Trust our Data.	Billings, MT 800.735.4489 • Casper, WY 888.235.0515
1 0413 11-6° 112 \$	www.energylab.com	College Station, TX 888.690.2218 • Gillette, WY 866.686.7175 • Helena, MT 877.472.0711
CLIENT:	Colorado Analytical Laboratories Inc	
Project:	170217005 LFH-1 CO-0121724	Report Date: 03/02/17

CASE NARRATIVE

Tests associated with analyst identified as ELI-B were subcontracted to Energy Laboratories, 1120 S. 27th St., Billings, MT, EPA Number MT00005.

Work Order:

C17020566



LABORATORY ANALYTICAL REPORT Prepared by Casper, WY Branch **Client:** Colorado Analytical Laboratories Inc Report Date: 03/02/17 Project: 170217005 LFH-1 CO-0121724 Collection Date: 02/16/17 Lab ID: C17020566-001 DateReceived: 02/21/17 Client Sample ID: 170217005-01 LFH-1 Matrix: Drinking Water MCL/ Analyses **Result Units** Qualifiers RL QCL Method Analysis Date / By VOCS BY AZEOTROPIC DISTILLATION 1.4-Dioxane ND ug/L 1.0 SW8260M 02/27/17 11:16 / eli-b - Analysis by direct aqueous injection of the sample distillate. A deuterated version of 1,4-Dioxane was added to the sample prior to distillation and used to quantitate the 1.4-Dioxane and account for any variations in the analysis or distillation. VOLATILE ORGANIC COMPOUNDS Acetone ND ug/L 20 E624 02/24/17 19:19 / eli-b Acetonitrile ND ug/L 20 E624 02/24/17 19:19 / eli-b Acrolein ND ug/L 20 F624 02/24/17 19:19 / eli-b Acrylonitrile ND ug/L 20 E624 02/24/17 19:19 / eli-b Benzene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Bromobenzana ND ug/L 1.0 E624 02/24/17 19:19 / ell-b Bromochloromethane ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Bromodichloromethane E624 ND ug/L 1.0 02/24/17 19:19 / eli-b Bromoform ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Bromomethane ND ug/L E624 1.0 02/24/17 19:19 / eli-b Carbon disulfide ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Carbon tetrachloride ug/L ND E624 1.0 02/24/17 19:19 / eli-b Chlorobenzene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Chlorodibromomethane ND 1.0 ug/L E624 02/24/17 19:19 / eli-b Chloroethane ND ug/L 1.0 02/24/17 19:19 / ell-b E624 2-Chloroethyl vinvl ether ug/L ND 1.0 E624 02/24/17 19:19 / eli-b Chloroform ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Chloromethane ug/L ND 1.0 E624 02/24/17 19:19 / eli-b 2-Chlorotoluene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 4-Chlorotoluene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 1.2-Dibromoethane ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Dibromomethane ug/L ND 1.0 E624 02/24/17 19:19 / ell-b 1,2-Dichlorobenzene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 1.3-Dichlorobenzene ug/L E624 ND 1.0 02/24/17 19:19 / eli-b 1.4-Dichlorobenzene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Dichlorodifluoromethane ug/L E624 ND 10 02/24/17 19:19 / eli-b 1.1-Dichloroethane ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 1.2-Dichloroethane ug/L 1.0 ND E624 02/24/17 19:19 / eli-b 1.1-Dichloroethene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b cis-1,2-Dichloroethene ND ug/L 1.0 E624 02/24/17 19:19 / ell-b trans-1,2-Dichloroethene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 1,2-Dichloropropane ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 1,3-Dichloropropane 02/24/17 19:19 / eli-b ND ug/L 1.0 E624 2,2-Dichloropropane ND ug/L 1.0 E624 02/24/17 19:19 / eli-b 1,1-Dichloropropene ND ug/L E624 1.0 02/24/17 19:19 / eli-b cis-1,3-Dichloropropene ND ug/L E624 1.0 02/24/17 19:19 / eli-b trans-1,3-Dichloropropene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b Ethylbenzene ND ug/L 1.0 E624 02/24/17 19:19 / eli-b

Report Definitions: RL - Analyte reporting limit. QCL - Quality control limit. MCL - Maximum contaminant level.



LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

Client:Colorado Analytical Laboratories IncProject:170217005 LFH-1 CO-0121724Lab ID:C17020566-001Client Sample ID:170217005-01 LFH-1

Report Date: 03/02/17 Collection Date: 02/16/17 DateReceived: 02/21/17 Matrix: Drinking Water

Analyses	Result	Units	Qualifiers	RL.	MCL/ QCL Method	Analysis Date / By
VOLATILE ORGANIC COMPOUNDS		um/i		2.0	5604	02/24/17 19:19 / eli-b
Methyl tert-butyl ether (MTBE) Methyl ethyl ketone		ug/L ug/L		2.0	E624 E624	02/24/17 19:19 / eli-b 02/24/17 19:19 / eli-b
		-		20		
Methyl isobutyl ketone		ug/L		10	E624	02/24/17 19:19 / eli-b
Methylene chloride		ug/L		1.0	E624	02/24/17 19:19 / eli-b
Naphthalene		ug/L		0.50	E624	02/24/17 19:19 / eli-b
Styrene	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
Tetrachloroethene		ug/L		1.0	E624	02/24/17 19:19 / eli-b
1,1,1,2-Tetrachloroethane	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
1,1,2,2-Tetrachloroethane	ND	ug/L		1.0	E624	02/24/17 19:19 / ell-b
Toluene		•		1.0	E624	02/24/17 19:19 / ell-b
Trichioroethene		ug/L		1.0	E624	02/24/17 19:19 / slī-b
1,1,1-Trichloroethane	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
1,1,2-Trichloroethane	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
Trichlorofluoromethane	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
1,2,3-Trichloropropane	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
Vinyl Acetate	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
Vinyl chloride	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
m+p-Xylenes	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
o-Xylene	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
Xvienes, Total	ND	ug/L		1.0	E624	02/24/17 19:19 / eli-b
Surr: 1,2-Dichloroethane-d4		%REC		71-139	E624	02/24/17 19:19 / eli-b
Surr: p-Bromofluorobenzene	92.0	%REC		80-127	E624	02/24/17 19:19 / eli-b
Surr: Toluene-d8		%REC		80-123	E624	02/24/17 19:19 / eli-b
SEMI-VOLATILE ORGANIC COMPOU	JNDS					
Acenaphthene	ND	ug/L		10	E625	02/27/17 19:27 / eli-b
Acenaphthylene	ND	ug/L		10	E625	02/27/17 19:27 / eli-b
Anthracene	ND	ug/L		10	E625	02/27/17 19:27 / eli-b
Azobenzene	ND	ug/L		10	E625	02/27/17 19:27 / eli-b
Benzidine		ug/L		10	E625	02/28/17 13:13 / eli-b
Benzo(a)anthracene		ug/L		10	E625	02/27/17 19:27 / eli-b
Berizo(a)pyrene	ND	ug/L		10	E625	02/27/17 19:27 / eli-b
Benzo(b)fluoranthene		ug/L		10	E625	02/27/17 19:27 / eli-b
Benzo(g,h,i)perylene		ug/L		10	E625	02/27/17 19:27 / eli-b
Benzo(k)fluoranthene		ug/L		10	E625	02/27/17 19:27 / eli-b
4-Bromophenyl phenyl ether		ug/L		10	E625	02/27/17 19:27 / eli-b
Butylbenzyiphthalate		ug/L		10	E625	02/27/17 19:27 / eli-b
4-Chloro-3-methylphenoi		ug/L		10	E625	02/27/17 19:27 / eli-b
bis(-2-chloroethoxy)Methane	ND	-		10	E625	02/27/17 19:27 / eli-b
bis(-2-chloroethyl)Ether		-		10	E625	
bis(-2-chloroisopropyi)Ether	ND	-				02/27/17 19:27 / eli-b
	ND	+		10	E625	02/27/17 19:27 / eli-b
2-Chloronaphthaiene	ND			10	E625	02/27/17 19:27 / eli-b
2-Chlorophenol	ND	ug/L		10	E625	02/27/17 19:27 / eli-b

Report Definitions: RL - Analyte reporting limit. QCL - Quality contro! limit. MCL - Maximum contaminant level.



LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

 Client:
 Colorado Analytical Laboratories Inc

 Project:
 170217005 LFH-1 CO-0121724

 Lab ID:
 C17020566-001

 Client Sample ID:
 170217005-01 LFH-1

Report Date: 03/02/17 Collection Date: 02/16/17 DateReceived: 02/21/17 Matrix: Drinking Water

			_	-	MCL/		
Analyses	Result	Units	Qualifiers	RL	QCL M	ethod	Analysis Date / By
SEMI-VOLATILE ORGANIC COMPOUNDS							
4-Chlorophenyl phenyl ether		ug/L		10	F	625	02/27/17 19:27 / eli-b
Chrysene		ug/L		10	-	825	02/27/17 19:27 / eli-b
Diethyl phthalate	ND	ug/L		10	_	625	02/27/17 19:27 / eli-b
Di-n-butyl phthalate	ND	ug/L		10		625	02/27/17 19:27 / eli-b
1.2-Dichlorobenzene	ND	ug/L		10		625	02/27/17 19:27 / eli-b
1,3-Dichlorobenzene	ND	-		10		825	02/27/17 19:27 / ell-b
1.4-Dichlorobenzene	ND	-		10		625	02/27/17 19:27 / eli-b
3,3'-Dichlorobenzidine	ND	ug/L		10		625 625	02/27/17 19:27 / eli-b
	ND	-+		10		625 625	02/27/17 19:27 / ell-b
2,4-Dichlorophenol		ug/L			_		
Dimethyl phthalate	ND	ug/L		10		625	02/27/17 19:27 / eli-b
Di-n-octyl phthalate	ND	ug/L		10		625 805	02/27/17 19:27 / eli-b
Dibenzo(a,h)anthracene	ND	ug/L		10		625	02/27/17 19:27 / eli-b
2,4-Dimethylphenol	ND	ug/L		10		625	02/27/17 19:27 / eli-b
4,6-Dinitro-2-methylphenol	ND	•		50		625	02/27/17 19:27 / eli-b
2,4-Dinitrophenol	ND	ug/L		50		325	02/27/17 19:27 / eli-b
2,4-Dinitrotoluene	ND	ug/L		10		525	02/27/17 19:27 / ell-b
2,6-Dinitrotoluene	ND	ug/L		10	_	525	02/27/17 19:27 / eli-b
ois(2-ethylhexy/)Phthalate	ND	ug/L		10	E	625	02/27/17 19:27 / eli-b
Fluoranthene	ND	ug/L		10	E	325	02/27/17 19:27 / eli-b
Fluorene	ND	ug/L		10	E	325	02/27/17 19:27 / eli-b
Hexachlorobenzene	ND	ug/L		10	E	625	02/27/17 19:27 / eli-b
-lexachlorobutadiene	ND	ug/L		10	E	62 5	02/27/17 19:27 / eli-b
Hexachlorocyclopentadiene	ND	ug/L		10	Ef	325	02/27/17 19:27 / eli-b
Hexachloroethane	ND	ug/L		10	E	625	02/27/17 19:27 / eli-b
ndeno(1,2,3-cd)pyrene	ND	-		10	E	525	02/27/17 19:27 / eli-b
sophorone	ND	ug/L		10	E	325	02/27/17 19:27 / eli-b
n-Nitrosodimethylamine	ND	ug/L		10	E	3 25	02/27/17 19:27 / eli-b
n-Nitroso-di-n-propylamine	ND	ug/L		10		525	02/27/17 19:27 / eli-b
n-Nitrosodiphenylamine	ND	ug/L		10		325	02/27/17 19:27 / eli-b
2-Nitrophenol	ND	ug/L		10		325	02/27/17 19:27 / elí-b
4-Nitrophenol	ND	ug/L		50		525	02/27/17 19:27 / eli-b
Naphthalene	ND	ug/L		10		325	02/27/17 19:27 / eli-b
Nitrobenzene	ND	ug/L		10		325	02/27/17 19:27 / eli-b
Pentachiorophenol	ND	ug/L		50		525	02/27/17 19:27 / eli-b
Phenanthrene		_		10		525 525	02/27/17 19:27 / eli-b
-nenanmiene Phenol		ug/L		10		525 525	02/27/17 19:27 / eli-b
		ug/L		10		525	02/27/17 19:27 / eli-b
		ug/L					
		ug/L		10		325 205	02/27/17 19:27 / eli-b
2,4,6-Trichlorophenol		ug/L		10		325	02/27/17 19:27 / eli-b
Surr: 2-Fluorobiphenyi		%REC		28-107		525 Soc	02/27/17 19:27 / eli-b
Surr: 2-Fluorophenol		%REC		20-56		625	02/27/17 19:27 / eli-b
Surr: Nitrobenzene-d5		%REC		32-94		325	02/27/17 19:27 / eli-b
Surr: Phenol-d5	33.0	%REC		19-45	E	625	02/27/17 19:27 / eli-b

Report Definitions: RL - Analyte reporting limit. QCL - Quality control limit. MCL - Maximum contaminant level.



LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

Client:	Colorado Analytical Laboratories Inc	Report Date:	03/02/17
Project:	170217005 LFH-1 CO-0121724	Collection Date:	02/16/17
Lab ID:	C17020566-001	DateReceived:	02/21/17
Client Sample ID:	170217005-01 LFH-1	Matrix:	Drinking Water

			MCLI	
Analyses	Result Units	Qualifiers RL	QCL Method	Analysis Date / By
SEMI-VOLATILE ORGANIC COMP	OUNDS			
Surr: Terphenyl-d14	69.0 %REC	32-122	E625	02/27/17 19:27 / eli-b
Surr: 2,4,6-Tribromophenol	60.0 %REC	21-130	E625	02/27/17 19:27 / eli-b

The sample was received past the extraction prep hold time. The prep hold time was exceeded by 4.31 days.

Report Definitions: RL - Analyte reporting limit. QCL - Quality control limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E624							An	alytical Run:	R275391
Lab ID:	ccv022417	Continuing Ca	libration \	erification Standa	rd				02/24	/17 09:51
Acetone		40.8	ug/L	20	82	70	130			
Acetonitrile	•	60.0	ug/L	20	120	70	130			
Acrolein		59.2	ug/L	20	118	70	130			
Acrylonitrile	e	46.4	ug/L	20	93	70	130			
Benzene		4.80	ug/L	0.50	96	70	130			
Bromobenz		4,56	ug/L	0.50	91	70	130			
Bromochlo		4,64	ug/L	0.50	93	70	130			
Bromodich	loromethane	4.08	ug/L	0.50	82	70	130			
Bromoform	I	4.08	ug/L	0.50	82	70	130			
Bromometh		5.56	ug/L	0.50	111	70	130			
Carbon dis		4.80	ug/L	0.50	96	70	130			
Carbon tetr		3.70	ug/L	0.50	74	70	130			
Chiorobenz		4.80	ug/L	0.50	96	70	130			
	momethane	4.32	ug/L	0.50	86	70	130			
Chloroetha		4.88	ug/L	0.50	98	70	130			
	nyl vinyi ether	3.07	ug/L	1.0	61	70	130			S
Chloroform		4.36	ug/L	0.50	87	70	130			
Chlorometh		4.60	ug/L	0.50	92	70	130			
2-Chlorotol		4.84	ug/L	0.50	97	70	130			
4-Chiorotol		4.80	ug/L	0.50	96	70	130			
1,2-Dibrom		4.40	ug/L	0.50	88	70	130			
Dibromome		4.60	ug/L	0.50	92	70	130			
1,2-Dichlor		4.72	ug/L	0.50	94	70	130			
1,3-Dichlor		4.84	ug/L	0.50	97	70	130			
1,4-Dichlord		4.76	ug/L	0.50	95	70	130			
	uoromethane	3.87	ug/L	0.50	77	70	130			
1,1-Dichlord		4.40	ug/L	0.50	88	70	130			
1,2-Dichlord		3.78	ug/L	0.50	76	70	130			
1,1-Dichlord cis-1,2-Dich		4.20	ug/L	0.50	84	70	130			
	ichioroethene	4.72 4.64	ug/L	0.50 0. 5 0	94 93	70	130			
1,2-Dichlord		5.20	ug/L	0.50	104	70	130			
1,3-Dichlord		4.64	ug/L ug/L	0.50	93	70 70	130 130			
2,2-Dichlord		3.92	ug/L	0.50	78	70	130			
1,1-Dichlore		4.40	ug/L	0.50	88	70	130			
	nloropropene	4.56	ug/L	0.50	91	70	130			
	ichloropropene	4.04	ug/L	0.50	81	70	130			
Ethylbenzer		4.84	ug/L	0.50	97	70	130			
-	butyl ether (MTBE)	3.68	ug/L	0.50	74	70	130			
Methyl ethy		42.8	ug/L	20	86	70	130			
Methyl isob		45.6	ug/L	20	91	70	130			
Methylene o		5.44	ug/L	0.50	109	70	130			
Naphthalen		4.88	ug/L	0.50	98	70	130			
					_					

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Ξ

QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD RPDLimit Qual
Method: E624							Analytical Run: R275391
Lab ID: ccv022417	Continuing Ca	libration Ver	ification Standa	ard			02/24/17 09:51
Styrene	4.76	ug/L	0.50	95	70	130	
Tetrachloroethene	4.60	ug/L	0.50	92	70	130	
1, 1, 1, 2-Tetrachloroethane	4.24	ug/L	0.50	85	70	130	
1, 1, 2, 2-Tetrachloroethane	4.96	ug/L	0.50	99	70	130	
Toluene	4.96	ug/L	0.50	99	70	130	
Trichloroethene	4.80	ug/L	0.50	96	70	130	
1,1,1-Trichloroethane	3.75	ug/L	0.50	75	70	130	
1,1,2-Trichloroethane	4.76	ug/L	0.50	95	70	130	
Trichlorofluoromethane	3.34	ug/L	0.50	67	70	130	S
1,2,3-Trichloropropane	4.20	ug/L	0.50	84	70	130	
Vinyl Acetate	4.56	ug/L	1.0	91	70	130	
Vinyl chloride	4.84	ug/L	0.50	97	70	130	
m+p-Xylenes	9.76	ug/L	0.50	98	70	130	
o-Xylene	4.76	ug/L	0.50	95	70	130	
Xylenes, Total	14.5	ug/L	0.50	97	70	130	
Surr: 1,2-Dichloroethane-d4			0.50	74	71	139	
Surr: p-Bromofluorobenzene			0.50	88	80	127	
Surr: Toluene-d8			0.50	92	80	123	
Method: E624							Batch: R275391
Lab ID: cs022417	Laboratory Co	-				A.I_170224A	02/24/17 10:31
Acetone	41.6	ug/L	20	83	55	144	
Acetonitrile	60.4	ug/L	20	121	54	142	
Acrolein	49.6	ug/L	20	99	16	233	
Acrylonitrile	46.0	ug/L	20	92	76	127	
Benzene	4.96	ug/L	0.50	99	73	122	
Bromobenzene	4.76	ug/L	0.50	95	74	129	
Bromochloromethane	4.64	ug/L	0.50	93	66	120	
Bromodichioromethane	4.44	ug/L	0.50	89	74	128	
Bromoform	4.36	ug/L	0.50	87	66	128	
Bromomethane	5.76	ug/L	0.50	115	51	123	
Carbon disulfide	4.92	ug/L	0.50	98	46	145	
Carbon tetrachloride	3.80	ug/L	0.50	76	75	125	
Chiorobenzene	4.92	u g /L	0.50	98	80	123	
Chlorodibromomethane	4.64	ug/L	0.50	93	74	125	
Chloroethane	5.04	ug/L	0.50	101	59	142	
2-Chloroethyl vinyl ether Chloroform	2.74	ug/L	1.0	55 88	36	144	
Chloroform	4.40	ug/L	0.50	88	68 53	124	
Chloromethane 2-Chlorotoluene	4.64 5.04	ug/L	0.50 0.50	93 101	53 75	14 6 131	
4-Chiorotoluene	4.68	ug/L	0.50	94	75 74	129	
1,2-Dibromoethane	4.66	ug/L	0.50	94 88	7 4 76	129	
		ug/L					
Dibromomethane	4.76	ug/L	0.50	95	77	125	

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Trust our People. Trust our Data. www.energylab.com

QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624								Batch:	R27539
Lab (D: Ics022417	Laboratory Con	trol Sample			Run: 5971/	A.I_170224A		02/24	/17 10:3
1,2-Dichlorobenzene	4.80	ug/L	0.50	96	74	124			
1,3-Dichlorobenzene	5.00	ug/L	0.50	100	77	122			
1,4-Dichlorobenzene	4.80	ug/L	0.50	96	76	126			
Dichlorodifluoromethane	4.36	ug/L	0.50	87	56	146			
1,1-Dichloroethane	4.56	ug/L	0.50	9 1	74	133			
1,2-Dichloroethane	3.76	ug/L	0.50	75	75	129			
1,1-Dichloroethene	4.28	ug/L	0.50	86	74	132			
cis-1,2-Dichloroethene	4.76	ug/L	0.50	95	81	122			
trans-1,2-Dichloroethene	5.08	ug/L	0.50	102	79	143			
1,2-Dichloropropane	5.20	ug/L	0.50	104	75	126			
1,3-Dichloropropane	4.32	ug/L	0.50	86	71	136			
2,2-Dichloropropane	4.00	ug/L	0.50	80	68	142			
1, 1-Dichloropropene	4.16	ug/L	0.50	83	70	131			
cis-1,3-Dichloropropene	4.12	ug/L	0.50	82	74	135			
trans-1,3-Dichloropropene	3.96	ug/L	0.50	79	76	149			
Ethylbenzene	4.92	ug/L	0.50	98	72	130			
Methyl tert-butyl ether (MTBE)	3.71	ug/L	0.50	74	72	120			
Methyl ethyl ketone	45.2	ug/L	20	90	45	130			
Methyl isobutyl ketone	49.2	ug/L	20	98	58	135			
Methylene chloride	5.64	ug/L	0.50	113	66	142			
Naphthalene	5.44	ug/L	0.50	109	69	124			
Styrene	4.84	ug/L	0.50	97	80	124			
Tetrachloroethene	4.68	ug/L	0.50	94	72	131			
1,1,1,2-Tetrachloroethane	4.16	ug/L	0.50	83	78	124			
1,1,2,2-Tetrachloroethane	4.72	ug/L	0.50	94	68	137			
Toluene	5.16	ug/L	0.50	103	72	135			
Trichloroethene	4.80	ug/L	0.50	96	85	135			
1,1,1-Trichloroethane	3.73	ug/L	0.50	30 75	63	120			
1,1,2-Trichloroethane	4.68		0.50	94					
Trichlorofluoromethane		ug/L	0.50	94 66	78	124			•
1,2,3-Trichloropropane		ug/L	0.50	81	72	120			S
Vinyl Acetate		ug/L		82	64	138			
Vinyl chloride		ug/L	1.0		31	124			
m+p-Xylenes		ug/L	0.50	102	58	140			
o-Xylene		ug/L	0.50	98	67	139			
		ug/L	0.50	97	74	135			
Xylenes, Total	14.7	ug/L	0.50	98	70	137			
Surr: 1,2-Dichloroethane-d4			0.50	72	71	139			
Surr: p-Bromofluorobenzene			0.50	87	80	127			
Surr: Toluene-d8			0.50	92	80	123			
Lab ID: bik022417	Method Blank				Run: 5971A	.I_170224A		02/24/	17 11:30
Acetone		ug/L	20						
Acetonitrile	ND	ug/L	20						

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RĹ	%REC Low Limit High Li	mit RPD	RPDLimit	Qual
Method: E624						Batch:	R275391
Lab ID: bik022417	Method Blank			Run: 5971A.I_17022	4A	02/24	/17 11:30
Acrolein	ND	ug/L	20	-			
Acrylonitrile	ND	ug/L	3.0				
Benzene	ND	ug/L	0.50				
Bromobenzene	ND	ug/L	0.50				
Bromochloromethane	ND	ug/L	0.50				
Bromodichloromethane	ND	ug/L	0.50				
Bromoform	ND	ug/L	0.50				
Bromomethane	ND	ug/L	0.50				
Carbon disulfide	ND	ug/L	0.50				
Carbon tetrachloride	ND	ug/L	0.50				
Chlorobenzene	ND	ug/L	0.50				
Chlorodibromomethane	ND	ug/L	0.50				
Chloroethane	ND	ug/L	0.50				
2-Chloroethyl vinyl ether	ND	ug/L	1.0				
Chieroform	ND	ug/L	0.50				
Chloromethane	ND	ug/L	0.50				
2-Chlorotoluene	ND	ug/L	0.50				
4-Chlorotoluene	ND	ug/L	0.50				
1,2-Dibromoethane	ND	ug/L	0.50				
Dibromomethane	ND	ug/L	0.50				
1,2-Dichlorobenzene	ND	ug/L	0.50				
1,3-Dichlorobenzene	ND	ug/L	0.50				
1,4-Dichlorobenzene	ND	ug/L	0.50				
Dichlorodifiuoromethane	ND	ug/L	0.50				
1,1-Dichlorcethane	ND	ug/L	0.50				
1,2-Dichloroethane	ND	ug/L	0.50				
1,1-Dichloroethene	ND	ug/L	0.50				
cis-1,2-Dichloroethene	ND	ug/L	0.50				
trans-1,2-Dichloroethene	ND	ug/L	0.50				
1,2-Dichloropropane	ND	ug/L	0.50				
1,3-Dichloropropane	ND	ug/L	0.50				
2,2-Dichloropropane	ND	ug/L	0.50				
1,1-Dichloropropene	ND	ug/L	0.50				
cis-1,3-Dichioropropene	ND	ug/L	0.30				
trans-1,3-Dichloropropene	ND	ug/L	0.30				
Ethylbenzene	ND	ug/L	0.50				
Methyl tert-butyl ether (MTBE)	ND	ug/L	0.50				
Methyl ethyl ketone	ND	ug/L	20				
Methyl isobutyl ketone	ND	ug/L	20				
Methylene chloride	ND	ug/L	0.50				
Naphthalene	ND	ug/L	0.50				
Styrene	ND	ug/L	0.50				
Tetrachloroethene	ND	ug/L	0.50				

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc.

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E624								Batch:	R27539
Lab ID:	bik022417	Method Blank				Run: 5971/	A.I_170224A		02/24	/17 11:30
1,1,1,2-Tet	rachloroethane	ND	ug/L	0.50						
1, 1, 2, 2-Tet	rachloroethane	ND	ug/L	0.50						
Toluene		ND	ug/L	0.50						
Trichloroeth	hene	ND	ug/L	0.50						
1, 1, 1-Trichi	loroethane	ND	ug/L	0.50						
1,1,2-Trichi	loroethane	ND	ug/L	0.50						
Trichloroflu	oromethane	ND	ug/L	0.50						
1,2,3-Trichi	loropropane	ND	ug/L	0.50						
Vinyl Aceta	ite	ND	ug/L	1.0						
Vinyl chlorid	de	ND	ug/L	0.40						
m+p-Xylene	es	ND	ug/L	0.50						
o-Xylene		ND	ug/L	0.50						
Xylenes, To	otal	ND	ug/L	0.50						
-	-Dichloroethane-d4		•	0.50	74	71	139			
	Bromofluorobenzene			0.50	90	80	127			
Surr: Tol	uene-d8			0.50	94	80	123			
Lab ID:	b17021110-001bms	Sample Matrix	Spike			Run: 5971/	A.I_170224A		02/24	/17 20:47
Acrolein		ND	ug/L	20	0	16	233			S 1
Acrylonitrile		48.8	ug/L	20	98	76	127			
2-Chloroeth	nyi vinyi ether	3.44	ug/L	1.0	69	36	144			
	-Dichloroethane-d4		•	0.50	80	71	139			
	Iromofluorobenzene			0.50	95	80	127			
Surr: Tol	uene-d8			0.50	100	80	123			
- 1 = This is with the san	a known very reactive compour nple matrix.	nd. The recovery of	this compound was n	ormal in th	e Laborat	ory Control Sa	mple (LCS). The o	compound	appears to hav	/e reacted
Lab ID:	b17021110-001bmsd	Sample Matrix	Spike Duplicate			Run: 59714	.[_170224A		02/24/	/17 21:16
Acrolein		ND	ug/L	20	Ō	16	233		20	S 1
Acrylonitrile	•	48.8	ug/L	20	98	76	127	0.0	20	
-	yl vinyl ether	3.66	ug/L	1.0	73	36	144	6.1	20	
	-Dichloroethane-d4		-	0.50	81	71	139			
Surr. p-B	romofluorobenzene			0.50	96	80	127			
Surr: Tol				0.50	99	80	123			
	a known very reactive compour	nd. The recovery of t	this compound was n	ormal in th	e Laborate	ory Control Sar	mple (LCS). The d	compound	appears to hav	/e reacted
	b17021110-001bms	Sample Matrix	Spike			Run: 5971A	.I_170224A		02/24/	/17 18:21
Lab ID:		40.4	ug/L	20	81	55	144			
		66.0	ug/L	20	132	54	142			
Acetone				0.50	92	73	122			
Acetone Acetonitrile		4.60	ug/L							
Acetone Acetonitrile Benzene			ug/L ug/L	0.50	92	74	129			
Acetone Acetonitrile Benzene Bromobenz	ene	4.60				74 66	129 120			
Acetone Acetonitrile Benzene Bromobenz Bromochlor	ene	4.60 4.60	ug/L	0.50	92					
Lab ID: Acetone Acetonitrile Benzene Bromobenz Bromochlor Bromodichle Bromoform	rene romethane oromethane	4.60 4.60 4.56	ug/L ug/L	0.50 0.50	92 91	66	120			

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624									Batch	: R275391
Lab ID: b17	021110-001bms	Sample Matri	k Spike			Run: 5971/	A.I_170224A		02/24	4/17 18:21
Carbon disulfide		5.12	ug/L	0.50	102	46	145			
Carbon tetrachlori	de	3.59	ug/L	0.50	72	75	125			S
Chlorobenzene		4.52	ug/L	0.50	90	80	123			
Chlorodibromome	thane	4.52	ug/L	0.50	90	74	125			
Chloroethane		5.40	ug/L	0.50	108	59	142			
Chloroform		4.68	ug/L	0.50	82	68	124			
Chloromethane		4.64	ug/L	0.50	93	53	146			
2-Chiorotoluene		4.88	ug/L	0.50	98	75	131			
4-Chlorotoluene		4.68	ug/L	0.50	94	74	129			
1,2-Dibromoethan	e	4.16	ug/L	0.50	83	76	124			
Dibromomethane		4.64	ug/L	0.50	93	77	125			
1,2-Dichlorobenze	ne	4.64	ug/L	0.50	93	74	124			
1,3-Dichlorobenze	ne	4.88	ug/L	0.50	98	77	122			
1,4-Dichlorobenze	ne	4.76	ug/L	0.50	91	76	126			
Dichlorodifluorome	ethane	4.32	ug/L	0.50	86	56	146			
1,1-Dichloroethan	8	4.24	ug/L	0.50	85	74	133			
1,2-Dichloroethan	9	3.48	ug/L	0.50	70	75	129			S
1,1-Dichloroethen	9	4.12	ug/L	0.50	82	74	132			
cis-1,2-Dichloroeth	iene	4.48	ug/L	0.50	90	81	122			
trans-1,2-Dichloro	ethene	4.64	ug/L	0.50	93	79	143			
1,2-Dichloropropa	ne	4.92	ug/L	0.50	98	75	126			
1,3-Dichloropropa	ne	4.24	ug/L	0.50	85	71	136			
2,2-Dichloropropa	ne	3.60	ug/L	0.50	72	68	142			
1,1-Dichloroproper	ne	4.04	ug/L	0.50	81	70	131			
cis-1,3-Dichloropro		4.08	ug/L	0.50	82	74	135			
trans-1,3-Dichlorop	propene	3.97	ug/L	0.50	79	76	149			
Ethylbenzene		4.64	ug/L	0.50	93	72	130			
Methyl tert-butyl et	her (MTBE)	3.63	ug/L	0.50	73	72	120			
Methyl ethyl keton		44.4	ug/L	20	89	45	130			
Methyl isobutyl ket	one	51.2	ug/L	20	102	58	135			
Methylene chloride	ļ	5.44	ug/L	0.50	109	66	142			
Naphthalene		4.84	ug/L	0.50	97	69	124			
Styrene		4.56	ug/L	0.50	91	80	124			
Tetrachloroethene		4.44	ug/L	0.50	89	72	131			
1,1,1,2-Tetrachlord		3.95	ug/L	0.50	79	78	124			
1,1,2,2-Tetrachloro	ethane	4.88	ug/L	0.50	98	68	137			
Toluene		4.88	ug/L	0.50	98	72	135			
Trichloroethene		4.56	ug/L	0. 5 0	91	85	126			
1,1,1-Trichloroetha		3.51	ug/L	0.50	70	63	120			
1,1,2-Trichloroetha		4.52	ug/L	0.50	90	78	124			
Trichlorofluoromet		3.29	ug/L	0.50	66	72	120			S
1,2,3-Trichloroprop	ane	3.90	ug/L	0. 5 0	78	64	138			
Vinyl Acetate		4.00	ug/L	1.0	80	31	124			

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624								Batch:	R27539
Lab ID: b17021110-001bms	Sample Matrix	< Spike			Run: 5971	A.I_170224A		02/24	/17 18:21
Vinyl chloride	5.12	ug/L	0.50	102	58	140			
m+p-Xylenes	9.32	ug/L	0.50	93	67	139			
o-Xylene	4.44	ug/L	0.50	89	74	135			
Xylenes, Total	13.8	ug/L	0.50	92	70	137			
Surr: 1,2-Dichloroethane-d4			0.50	80	71	139			
Surr: p-Bromofluorobenzene			0.50	94	80	127			
Surr: Toluene-d8			0.50	101	80	123			
Lab ID: b17021110-001bmsd	Sample Matrix	Spike Duplicate			Run: 5971,	A.I_170224A		02/24	/17 18:50
Acetone	44.0	ug/L	20	88	55	144	8.5	20	
Acetonitrile	65.6	ug/L	20	131	54	142	0.6	20	
Benzene	5.04	ug/L	0.50	101	73	122	9.1	20	
Bromobenzene	4.96	ug/L	0.50	99	74	129	7.5	20	
Bromochloromethane	4.80	ug/L	0.50	96	66	120	5.1	20	
Bromodichloromethane	4.60	ug/L	0.50	92	74	128	5.4	20	
Bromoform	4.80	ug/L	0.50	96	66	128	8.7	20	
Bromomethane	6.00	ug/L	0.50	120	51	123	2.0	20	
Carbon disulfide	5.20	ug/L	0.50	104	46	145	1.6	20	
Carbon tetrachloride	3.97	ug/L	0.50	79	75	125	10	20	
Chlorobenzene	4.88	ug/L	0.50	98	80	123	7.7	20	
Chlorodibromomethane	4.76	ug/L	0.50	95	74	125	5.2	20	
Chloroethane	5.32	ug/L	0.50	106	59	142	1.5	20	
Chloroform	4.96	ug/L	0.50	87	68	124	5.8	20	
Chloromethane	4.88	ug/L	0.50	98	53	146	5.0	20	
2-Chlorotoluene	5.20	ug/L	0.50	104	75	131	6.3	20	
4-Chlorotoluene	5.04	ug/L	0,50	101	74	129	7.4	20	
1.2-Dibromoethane	4.52	ug/L	0.50	90	76	124	8.3	20	
Dibromomethane	4.88	ug/L	0.50	98	77	125	5.0	20	
1,2-Dichlorobenzene	5.04	ug/L	0.50	101	74	124	8.3	20	
1,3-Dichlorobenzene	5.20	ug/L	0.50	104	77	122	6.3	20	
1.4-Dichlorobenzene	5.12	ug/L	0.50	98	76	126	7.3	20	
Dichlorodifluoromethane	4.36	ug/L	0.50	87	56	146	0.9	20	
1,1-Dichloroethane	4.68	ug/L	0.50	94	74	133	9.9	20	
1,2-Dichloroethane	3.76	ug/L	0.50	75	75	129	7.8	20	
1,1-Dichloroethene	4.44	ug/L	0.50	89	74	132	7.5	20	
cis-1,2-Dichloroethene	4.88	ug/L	0.50	98	81	122	8.5	20	
trans-1,2-Dichloroethene	5.12	ug/L	0.50	102	79	143	9,8	20	
1,2-Dichloropropane	5.24	ug/L	0.50	105	75	126	6.3	20	
1,3-Dichloropropane	4.64	ug/L	0.50	93	71	136	9.0	20	
2,2-Dichloropropane	3.96	ug/L	0.50	79	68	142	9.6	20	
1,1-Dichloropropene	4.44	ug/L	0.50	89	70	131	9.4	20	
cis-1,3-Dichloropropene	4.40	ug/L	0.50	88	74	135	7.5	20	
			0.50	85	76	149	6.6	20	
trans-1,3-Dichloropropene	4.24	ug/L	0.00	00	70	143	0.0	20	

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc.

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624								Batch:	R275391
Lab ID: b17021110-001bmsd	Sample Matrix	Spike Duplicate			Run: 5971	A.I_170224A		02/24	/17 18:50
Ethylbenzene	5.00	ug/L	0.50	100	72	130	7.5	20	
Methyl tert-butyl ether (MTBE)	3.83	ug/L	0.50	77	72	120	5.5	20	
Methyi ethyl ketone	46.0	ug/L	20	92	45	130	3.5	20	
Methyl isobutyl ketone	51.2	ug/L	20	102	58	135	0.0	20	
Methylene chloride	5.72	ug/L	0.50	114	66	142	5.0	20	
Naphthalene	5.56	ug/L	0.50	111	69	124	14	20	
Styrene	4.84	ug/L	0.50	97	80	124	6.0	20	
Tetrachloroethene	4.72	ug/L	0.50	94	72	131	6.1	20	
1,1,1,2-Tetrachloroethane	4.20	ug/L	0.50	84	78	124	6.1	20	
1,1,2,2-Tetrachloroethane	5.20	ug/L	0.50	104	68	137	6.3	20	
Toluene	5.12	ug/L	0.50	102	72	135	4.8	20	
Trichloroethene	4.80	ug/L	0.50	96	85	126	5.1	20	
1,1,1-Trichloroethane	3.94	ug/L	0.50	79	63	120	12	20	
1,1,2-Trichioroethane	4.76	ug/L	0.50	95	78	124	5.2	20	
Trichlorofluoromethane	3.36	ug/L	0.50	67	72	120	2.3	20	S
1,2,3-Trichloropropane	4.20	ug/L	0.50	84	64	138	7.4	20	
Vinyl Acetate	4.20	ug/L	1.0	84	31	124	4.9	20	
Vinyl chloride	5.08	ug/L	0.50	102	58	140	0.8	20	
m+p-Xylenes	9.92	ug/L	0.50	99	67	139	6.2	20	
o-Xylene	4.80	ug/L	0.50	96	74	135	7.8	20	
Xylenes, Total	14.7	ug/L	0.50	98	70	137			
Surr: 1,2-Dichloroethane-d4			0.50	81	71	139			
Surr: p-Bromofluorobenzene			0.50	94	80	127			
Surr: Toluene-d8			0.50	100	80	123			

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E625								Bato	h: 107004
Lab ID:	MB-107004	Method Blank				Run: SV59	73N2.I_170227B		02/27	7/17 18:24
Acenaphthe	ane	ND	ug/L	10			_			
Acenaphthy	lene	ND	ug/L	10						
Anthracene		ND	ug/L	10						
Azobenzen	e	ND	ug/L	10						
Benzo(a)an	thracene	ND	ug/L	10						
Benzo(a)py	rene	ND	ug/L	10						
Benzo(b)flu	oranthene	ND	ug/L	10						
Benzo(g,h,i)perylene	ND	ug/L	10						
Benzo(k)fiu	oranthene	ND	ug/L	10						
4-Bromoph	enyl phenyl ether	ND	ug/L	10						
Butylbenzyl	phthalate	ND	ug/L	10						
4-Chloro-3-	methylphenol	ND	ug/L	10						
bis(-2-chlore	ethoxy)Methane	ND	ug/L	10						
bis(-2-chlore	oethyl)Ether	ND	ug/L	10						
bis(2-chloro	isopropyi)Ether	ND	ug/L	10						
2-Chlorona	ohthalene	ND	ug/L	10						
2-Chloroph	enol	ND	ug/L	10						
4-Chlorophe	enyl phenyl ether	ND	ug/L	10						
Chrysene		ND	ug/L	10						
Diethyl phth	alate	ND	ug/L	10						
Di-n-butyl p	hthalate	ND	ug/L	10						
1,2-Dichloro	benzene	ND	ug/L	10						
1,3-Dichloro	benzene	ND	ug/L	10						
1,4-Dichlord	benzene	ND	u g /L	10						
3,3'-Dichlor	obenzidine	ND	ug/L	10						
2,4-Dichioro	phenol	ND	ug/L	10						
Dimethyl ph	thalate	ND	ug/L	10						
Di-n-octyl pl	nthalate	ND	ug/L	10						
Dibenzo(a,h)anthracene	ND	ug/L	10						
2,4-Dimethy	iphenol	ND	ug/L	10						
4,6-Dinitro-2	-methylphenol	ND	ug/L	50						
2,4-Dinitrop	henol	ND	ug/L	50						
2,4-Dinitroto	luene	ND	ug/L	10						
2,6-Dinitroto		ND	ug/L	10						
bis(2-ethylh	exyl)Phthalate	ND	ug/L	10						
Fluoranthen	e	ND	ug/L	10						
Fluorene		ND	ug/L	10						
Hexachlorot		ND	ug/L	10						
Hexachlorob		ND	ug/L	10						
	cyclopentadiene	ND	ug/L	10						
Hexachioroe		ND	ug/L	10						
Indeno(1,2,3	l-cd)pyrene	ND	ug/L	10						
Isophorone		ND	ug/L	10						

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result I	Jnits	RL %REG	C Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625							Batc	h: 107004
Lab ID: MB-107004	Method Blank			Run: SV59	73N2.I_170227B		02/27	7/17 18:24
n-Nitrosodimethylamine	ND u	ıg/L	10		_			
n-Nitroso-di-n-propylamine	ND t	ıg/L	10					
n-Nitrosodiphenylamine	ND i	ig/L	10					
2-Nitrophenol	ND t	ıg/L	10					
4-Nitrophenol	ND U	ıg/L ÷	50					
Naphthalene	ND u	/g/ ∟	10					
Nitrobenzene	ND U	ıg/∟	10					
Pentachlorophenol	ND t	ıg/L i	50					
Phenanthrene	ND t	ig/L	10					
Phenol	ND t	ıg/∟	10					
Pyrene	ND u	ıg/L ʻ	10					
1,2,4-Trichlorobenzene	ND U	ıg/L ʻ	0					
2.4,6-Trichlorophenol	ND L	ig/L ·	10					
Surr: 2-Fluorobiphenyl		· ·	0 55	5 28	107			
Surr: 2-Fluorophenol			0 36	5 20	56			
Surr: Nitrobenzene-d5		1	10 58	32	94			
Surr: Phenol-d5		1	0 35	5 19	45			
Surr: Terphenyl-d14		li i	0 77	32	122			
Surr: 2,4,6-Tribromophenol		1	0 58	3 21	130			
Lab ID: LCS-107004	Laboratory Contro	ol Sample		Run: SV59	73N2.I_170227B		02/27	/17 18:55
Acenaphthene	81.2 L	ig/L 1	0 81	58	99			
Acenaphthylene	76.5 U	ig/L 1	0 77	57	96			
Anthracene	79.5 0	ig/L 1	0 80	60	107			
Azobenzene	79.3 u	ig/L 1	0 79	56	100			
Benzo(a)anthracene	84.1 u	ig/L 1	0 84	62	114			
Benzo(a)pyrene	80.1 u	ig/L 1	0 80	62	108			
Benzo(b)fluoranthene	88.6 u	g/L 1	0 89	48	127			
Benzo(g,h,i)perylene	81.6 u	ig/L 1	0 82	62	121			
Benzo(k)fluoranthene	79.2 u	g/L 1	0 79	55	111			
4-Bromophenyl phenyl ether	63.0 u	g/L 1	0 83	58	105			
Butylbenzylphthalate	91.6 u	g/L 1	0 92	60	113			
4-Chloro-3-methylphenol	65.7 u	g/L 1	0 66	53	92			
bls(-2-chloroethoxy)Methane	73.9 u	g/L 1	0 74	50	92			
bis(-2-chloroethyl)Ether	63.4 u	g/L 1	0 63	44	82			
bis(2-chloroisopropy!)Ether	61.2 u	g/L 1	0 61	56	87			
2-Chloronaphthalene		-	0 75		95			
2-Chlorophenol		g/L 1	0 60	47	76			
4-Chlorophenyl phenyl ether	75.8 u	g/L 1	0 76	58	99			
Chrysene	81.9 u	g/L 1	0 82	63	106			
onajoono					400			
Diethyl phthalate	78.6 u	g/L 1	0 79	58	103			
		-	0 79 0 88		103			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625								Batc	h: 107004
Lab ID: LCS-107004	Laboratory Cor	trol Sample			Run: SV59	73N2.I_170227B		02/27	/17 18:55
1,3-Dichlorobenzene	60.2	ug/L	10	60	41	79			
1,4-Dichlorobenzene	61.4	ug/L	10	61	42	79			
3,3'-Dichlorobenzídine	68.6	ug/L	10	69	51	93			
2,4-Dichlorophenol	64.7	ug/L	10	65	49	90			
Dimethyl phthalate	76.4	u g /L	10	76	58	104			
Di-n-octyl phthalate	88.3	ug/L	10	88	56	110			
Dibenzo(a,h)anthracene	80.4	ug/L	10	80	61	111			
2,4-Dimethylphenoi	61.8	ug/L	10	62	45	89			
4,6-Dinitro-2-methylphenol	48.2	ug/L	50	48	37	105			
2,4-Dinitrophenol	39.7	ug/L	50	40	27	81			
2,4-Dinitrotoluene	87.7	ug/L	10	88	63	110			
2,6-Dinitrotoluene	75.5	ug/L	10	76	60	107			
bis(2-ethylhexyl)Phthalate	88.6	ug/L	10	89	56	108			
Fluoranthene	83.8	ug/L	10	84	63	110			
Fiuorene	77.4	ug/L	10	77	60	99			
Hexachlorobenzene	78.2	ug/L	10	78	57	103			
Hexachlorobutadiene	67.5	ug/L	10	67	39	83			
Hexachlorocyclopentadiene	68.4	ug/L	10	68	39	91			
Hexachloroethane	59.6	ug/L	10	60	37	75			
Indeno(1,2,3-cd)pyrene	82.0	ug/L	10	82	59	109			
Isophorone	67.1	ug/L	10	67	42	102			
n-Nitrosodimethylamine	36.9	ug/L	10	37	20	45			
n-Nitroso-di-n-propylamine	71.5	ug/L	10	71	49	98			
n-Nitrosodiphenylamine	90.0	ug/L	10	90	61	108			
2-Nitrophenol	68.0	ug/L	10	68	51	96			
4-Nitrophenol	18.3	ug/L	50	18	15	36			
Naphthalene	71.6	ug/L	10	72	48	96			
Nitrobenzene	65.0	ug/L	10	65	51	91			
Pentachiorophenol	70.6	ug/L	50	71	53	109			
Phenanthrene	80.5	ug/L	10	81	58	104			
Phenol	35.4	ug/L	10	35	27	45			
Pyrene	89,3	ug/L	10	89	64	108			
1,2,4-Trichlorobenzene	67.3	ug/L	10	67	49	85			
2,4,6-Trichlorophenol	64.9	ug/L	10	65	47	99			
Surr: 2-Fluorobiphenyl			10	63	28	107			
Surr: 2-Fluorophenol			10	35	20	56			
Surr: Nitrobenzene-d5			10	68	32	94			
Surr: Phenol-d5			10	42	19	45			
Surr: Terphenyl-d14			10	87	32	122			
Surr: 2,4,6-Tribromophenol			10	70	21	130			
Lab ID: B17021688-001CMS	Sample Matrix \$	Spike			Run: SV597	3N2.I_170227B		02/27/	17 20:29
Acenaphthene	86.4	ug/L	10	86	58	99			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E625								Batc	h: 107004
Lab ID:	B17021688-001CMS	Sample Matrix	k Spike			Run: SV59	73N2.I_170227B		02/27	/17 20:29
Acenaphth	ylene	83.0	ug/L	10	83	57	96			
Anthracene	2	86.4	ug/L	10	86	60	107			
Azobenzen	e	84.3	ug/L	10	84	56	100			
Benzo(a)ar	nthracene	90.3	ug/L	10	90	62	114			
Benzo(a)py	/rene	80.9	ug/L	10	81	62	108			
Benzo(b)flu	Joranthene	80.4	ug/L	10	80	48	127			
Benzo(g,h,i		80.5	ug/L	10	81	62	121			
Benzo(k)flu		83.5	ug/L	10	83	55	111			
	enyl phenyl ether	80.4	ug/L	10	80	58	105			
Butylbenzy		99.7	ug/L	10	100	60	113			
-	methyiphenol	77.0	ug/L	10	77	53	92			
	oethoxy)Methane	77.3	ug/L	10	77	50	92			
-	oethyl)Ether	66.7	ug/L	10	67	44	82			
-	pisopropyi)Ether	66.6	ug/L	10	67	56	87			
2-Chlorona		79.8	ug/L	10	80	56	95			
2-Chloroph	•	64.1	ug/L	10	64	47	76			
-	enyl phenyl ether	84.5	ug/L	10	85	58	99			
Chrysene	engi priorigi e urei	85.9	ug/L	10	86	63	106			
Diethyl pht	halate	85.4	ug/L	10	85	58	103			
Di-n-butyl p		96.0	ug/L	10	96	61	110			
1,2-Dichlor		66.1	ug/L	10	66	43	81			
1,3-Dichlor		61.9	ug/L	10	62	41	79			
1,4-Dichlor		61.8	ug/L	10	62	42	79			
3,3'-Dichlor		69.1	ug/L	10	69	51	93			
2,4-Dichlor		68.4	ug/L	10	68	49	90			
Dimethyl pl	•	81.4	ug/L	10	81	58	104			
Di-n-octyl p		90.6	ug/L	10	91	56	110			
	h)anthracene	80.0	ug/L	10	80	61	111			
• •	•	69.2		10	69	45	87			
2,4-Dimethy	2-methylphenol	58.9	ug/L	50	59	45 37	105			
		56.9 54.8	ug/L	50	55	27	81			
2,4-Dinitrop		82.5	ug/L	10	83	63	110			
			ug/L				107			
2,6-Dinitrote		80.8	ug/L	10	81	60 56	108			
Fluoranther	exyl)Phthalate	92.0	ug/L	10	92	56				
	le	88.0	ug/L	10	88	63	110			
Fluorene	h	80.1	ug/L	10	80	60	99			
Hexachloro		82.5	ug/L	10	83	57	103			
Hexachioro		69.0	ug/L	10	69	39	83			
	cyclopentadiene	68.1	ug/L	10	68	39	91			
Hexachioro		65.6	ug/L	10	66	37	75			
-	3-cd)pyrene	82.3	ug/L	10	82	59	109			
Isophorone		71.3	ug/L	10	71	42	102			
n-Nitrosodir	methylamine	41.5	ug/L	10	41	20	45			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit (Qual
Method: E625								Batch:	107004
Lab ID: B17021688-	001CMS Sample Matr	ix Spike			Run: SV59	73N2.I_170227B		02/27/1	7 20:29
n-Nitroso-di-n-propylamin	e 76.9	ug/L	10	77	49	98			
n-Nitrosodiphenylamine	93.7	ug/L	10	94	61	108			
2-Nitrophenol	69.9	ug/L	10	70	51	96			
4-Nitrophenol	24.6	ug/L	50	25	15	36			
Naphthalene	76.0	ug/L	10	76	48	96			
Nitrobenzene	72.5	ug/L	10	73	51	91			
Pentachtorophenol	89.2	ug/L	50	89	53	109			
Phenanthrene	85.1	ug/L	10	85	58	104			
Phenol	36.7	ug/L	10	37	27	45			
Pyrene	89.8	ug/L	10	90	64	108			
1,2,4-Trichlorobenzene	70.9	ug/L	10	71	49	85			
2,4,6-Trichlorophenol	67.7	ug/L	10	68	47	89			
Surr: 2-Fluorobiphenyl			10	62	28	107			
Surr: 2-Fluorophenol			10	39	20	56			
Surr: Nitrobenzene-d5			10	72	32	94			
Surr: Phenol-d5			10	35	19	45			
Surr: Terphenyl-d14			10	87	32	122			
Surr: 2,4,6-Tribromophe	enol		10	75	21	130			
Lab ID: B17021688-	003CMS Sample Matr	ix Spike			Run: SV59	73N2.I_170227B		02/27/1	7 21:3
Acenaphthene	89.8	ug/L	10	90	58	99			
Acenaphthylene	82.2	ug/L	10	82	57	96			
Anthracene	73.2	ug/L	10	73	60	107			
Azobenzene	80.2	ug/L	10	80	56	100			
Benzo(a)anthracene	85.1	ug/L	10	85	62	114			
Benzo(a)pyrene	77.0	ug/L	10	77	62	108			
Benzo(b)fluoranthene	73.3	ug/L	10	73	48	127			
Benzo(g,h,i)perviene	78.5	ug/L	10	79	62	121			
Benzo(k)fluoranthene	83.1	ug/L	10	83	55	111			
4-Bromophenyl phenyl ett	ner 78.1	ug/L	10	78	58	105			
Butylbenzylphthalate	92.9	ug/L	10	93	60	113			
4-Chioro-3-methylphenol	69.5	ug/L	10	69	53	92			
bis(-2-chloroethoxy)Metha		ug/L	10	70	50	92			
bis(-2-chloroethyl)Ether	58.4	ug/L	10	58	44	82			
bis(2-chlorolsopropyl)Ethe	F 57.7	ug/L	10	58	56	87			
2-Chloronaphthalene	77.7	ug/L	10	78	56	95			
2-Chlorophenol	56.6	ug/L	10	57	47	76			
4-Chlorophenyl phenyl eth		ug/L	10	83	58	89			
Chrysene	82.0	ug/L	10	82	63	106			
Diethyl phthalate	80.2	ug/L	10	80	5 8	103			
	86.9	ug/L	10	87	61	110			
Di-n-butyl phthalate	00.0	~ .							
Di-n-butyl phthalate 1,2-Dichlorobenzene	61.5	ug/L	10	62	43	81			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte	Result	Units	RL	701 12 0	LOW LINK	High Limit	KPU	RPDLimit	Qual
Method: E625			······					Batcl	n: 107004
Lab ID: B17021688-003CMS	Sample Matro	(Spike			Run: SV59	73N2.I_170227B		02/27	/17 21:31
1,4-Dichlorobenzene	57.9	ug/L	10	58	42	79			
3,3'-Dichlorobenzidine	52.9	u g /L	10	53	51	93			
2,4-Dichlorophenol	61.5	ug/L	10	62	49	90			
Dimethyl phthalate	74.3	ug/L	10	74	58	104			
Di-n-octyl phthalate	82.5	ug/L	10	83	56	110			
Dibenzo(a,h)anthracene	75.9	ug/L	10	76	61	111			
2,4-Dimethylphenol	60.0	ug/L	10	60	45	87			
4,6-Dinitro-2-methylphenol	41.6	ug/L	50	42	37	105			
2,4-Dinitrophenol	30.1	ug/L	50	30	27	81			
2,4-Dinitrotoluene	86.9	ug/L	10	87	63	110			
2,6-Dinitrotoluene	75.9	ug/L	10	76	60	107			
bls(2-ethylhexyl)Phthalate	81.5	ug/L	10	82	56	108			
Fluoranthene	82.0	ug/L	10	82	63	110			
Fluorene	81.9	ug/L	10	82	60	99			
Hexachlorobenzene	75.8	ug/L	10	76	57	103			
Hexachlorobutadiene	69.3	ug/L	10	69	39	83			
Hexachlorocyclopentadiene	69.5	ug/L	10	70	39	91			
Hexachloroethane	57.7	ug/L	10	58	37	75			
Indeno(1,2,3-cd)pyrene	73.4	ug/L	10	73	59	109			
Isophorone	68.4	ug/L	10	68	42	102			
n-Nitrosodimethylamine	27.8	ug/L	10	28	20	45			
n-Nitroso-di-n-propylamine	68.7	ug/L	10	69	49	98			
n-Nitrosodiphenylamine	84.0	ug/L	10	84	61	108			
2-Nitrophenol	61.8	ug/L	10	62	51	96			
4-Nitrophenol	27.7	ug/L	50	28	15	36			
Naphthalene	72.4	ug/L	10	72	48	96			
Narobenzene	69.7	ug/L	10	70	51	91			
Pentachlorophenol	66.8	ug/L	50	67	53	109			
Phenanthrene	79.7	ug/L	10	80	58	104			
Phenol	33.9	ug/L	10	34	27	45			
Pyrene	81.2	ug/L	10	81	64	108			
1,2,4-Trichlorobenzene	71.3	ug/L	10	71	49	85			
2,4,6-Trichlorophenol	63.8	ug/L	10	64	47	99			
Surr: 2-Fluorobiphenyl	00.0	agre	10	45	28	107			
Surr: 2-Fluorophenol			10	37	20	56			
Sur: Nitrobenzene-d5			10	62	32	94			
Surr: Phenol-d5			10	31	19	45			
Surr: Terphenyl-d14			10	64	32	122			
Surr: 2,4,6-Tribromophenol			10	55	21	130			
Lab ID: MB-107004	Method Blank				Run: SV597	3N2.I_170228A		02/28/	17 12:11
Benzidine	ND	ug/L	10						

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Resuit L	Inits	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E625								Batcl	h: 107004
Lab ID: Benzidine	LCS-107004	Laboratory Contro 63.4 u	bi Sample ⊧g/L	10	63	Run: SV59 10	73N2.I_170228A 100		02/28	/17 12:42
Lab ID: Benzidine	B17021688-001CMS	Sample Matrix Sp 25.8 u	oike Ig/L	20	26	Run: SV59 10	73N2.I_170228A 100		02/28	/17 14:16
Lab ID: Benzidine	B17021688-003CMS	Sample Matrix Sp 28.5 u	i ke g/L	20	28	Run: SV59 10	73N2.I_170228A 100		02/28	/17 15:18



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc.

Project: 170217005 LFH-1 CO-0121724

Report Date:	03/02/17
Work Order:	C17020566

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625	· · · · · · · · · · · · · · · · · · ·					· · · · · ·	Ar	alytical Run:	R275528
Lab ID: 27-Feb-17_CCV_2	Continuing Ca	libration V	erification Standa	ard				02/27	7/17 15:18
Acenaphthene	75.7	ug/L	10	101	80	120			
Acenaphthylene	75.2	ug/L	10	100	80	120			
Anthracene	78.7	ug/L	10	105	80	120			
Azobenzene	79.8	ug/L	10	106	80	120			
Benzo(a)anthracene	78.0	ug/L	10	104	80	120			
Benzo(a)pyrene	78.0	ug/L	10	104	80	120			
Benzo(b)fluoranthene	78.6	ug/L	10	105	80	120			
Benzo(g,h,i)perylene	75.3	ug/L	10	100	80	120			
Benzo(k)fluoranthene	73.2	ug/L	10	98	80	120			
4-Bromophenyl phenyl ether	74.4	ug/L	10	99	80	120			
Butylbenzylphthalate	84.4	ug/L	10	113	80	120			
4-Chloro-3-methylphenol	77.2	ug/L	10	103	80	120			
bis(-2-chloroethoxy)Methane	79.4	ug/L	10	106	80	120			
bis(-2-chloroethyi)Ether	80,8	ug/L	10	108	80	120			
bls(2-chloroisopropyl)Ether	77.8	ug/L	10	104	80	120			
2-Chloronaphthalene	70.3	ug/L	10	94	80	120			
2-Chlorophenol	80.3	ug/L	10	107	80	120			
4-Chlorophenyl phenyl ether	72.9	ug/L	10	97	80	120			
Chrysene	75.0	ug/L	10	100	80	120			
Diethyl phthalate	75.7	ug/L	10	101	80	120			
Di-n-butyl phthalate	81.6	ug/L	10	109	80	120			
1,2-Dichlorobenzene	72.7	ug/L	10	97	80	120			
1,3-Dichlorobenzene	77.8	ug/L	10	104	80	120			
1,4-Dichlorobenzene	74.9	ug/L	10	100	80	120			
3,3'-Dichlorobenzidine	75,8	ug/L	10	101	80	120			
2,4-Dichlorophenol	74.8	ug/L	10	100	80	120			
Dimethyl phthalate	75.3	ug/L	10	100	80	120			
Di-n-octyl phthalate	83.5	ug/L	10	111	80	120			
Dibenzo(a,h)anthracene	74.8	ug/L	10	100	80	120			
2,4-Dimethylphenol	73.0	ug/L	10	97	80	120			
4.6-Dinitro-2-methylphenol	71.3	ug/L	50	95	80	120			
2,4-Dinitrophenol	69.4	ug/L	50	93	80	120			
2,4-Dinitrotoluene	79.4	ug/L	10	106	80	120			
2,6-Dinitrotoluene	78.1	ug/L	10	104	80	120			
bis(2-ethylhexyl)Phthalate	84.4	ug/L	10	112	80	120			
Fluoranthene	76.0	ug/L	10	101	80	120			
Fluorene	77.8	ug/L	10	104	80	120			
Hexachlorobenzene	73.8	ug/L	10	98	80	120			
Hexachlorobutadiene	71.9	ug/L	10	96	80	120			
Hexachlorocyclopentadiene	73.1	ug/L	10	97	80	120			
Hexachloroethane	77.6	ug/L	10	103	80	120			
Indeno(1,2,3-cd)pyrene	75.6	ug/L	10	101	80	120			
Isophorone	78.1	ug/L	10	104	80	120			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date:	03/02/17
Work Order:	C17020566

Analyte	Result	Units	RL	%REC [Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625		·····					Ar	alytical Run:	R275528
Lab ID: 27-Feb-17_CCV_2	Continuing Ca	libration Verific	ation Standa	Ird				02/27	/17 15:18
n-Nitrosodimethylamine	75.3	ug/L	10	100	80	120			
n-Nitroso-di-n-propylamine	77.8	ug/L	10	104	80	120			
n-Nitrosodiphenylamine	78.9	ug/L	10	105	80	120			
2-Nitrophenol	75.8	ug/L	10	101	80	120			
4-Nitrophenol	69.6	ug/L	50	93	80	120			
Naphthalene	79.8	ug/L	10	106	80	120			
Nitrobenzene	76.8	ug/L	10	102	80	120			
Pentachiorophenol	73.3	ug/L	50	98	80	120			
Phenanthrene	74.0	ug/L	10	99	80	120			
Phenoi	79.2	ug/L	10	106	80	120			
Pyrene	75.2	ug/L	10	100	80	120			
1,2,4-Trichlorobenzene	72.8	ug/L	10	97	80	120			
2,4,6-Trichlorophenol	73.6	ug/L	10	98	80	120			
Surr: 2-Fluorobiphenyi		_	10	100	80	120			
Surr: 2-Fluorophenol			10	113	80	120			
Surr: Nitrobenzene-d5			10	105	80	120			
Surr: Phenol-d5			10	121	80	120			S
Surr: Terphenyl-d14			10	101	80	120			
Surr: 2,4,6-Tribromophenol			10	102	80	120			
Method: E625							An	alytical Run:	R275577
Lab ID: 28-Feb-17_CCV_2	Continuing Ca	libration Verific	ation Standa	rd				02/28	/17 11:39
Benzidine	89.5	ug/L	10	119	80	120			

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



=

QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170217005 LFH-1 CO-0121724

Report Date: 03/02/17 Work Order: C17020566

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	SW8260M							/	Analytical Rur	1: 107003
Lab ID:	CCV-107003	Continuing Cal	Ibration Verificatio	n Standa	rd					/17 08:30
1,4-Dioxane		105	ug/L	1.0	105	80	120		GEIZI	/17 00.00
Method:	SW8260M								Batch	n: 107003
Lab (D:	LCS-107003	Laboratory Cor	ntrol Sample			Run: VOA5	973A.I_170227A			/17 09:22
1,4-Dioxane		106	ug/L	1.0	106	70	130			
Lab ID:	MB-107003	Method Blank				Run: VOA5	973A.I_170227A		02/27	(17 09:44
1,4-Dioxane		ND	ug/L	1.0			-			
Lab ID:	C17020566-001BMS	Sample Matrix	Spike			Run: VOA5	973A.I_170227A		02/27/	17 11:37
1,4-Dioxane		200	ug/L	2.0	100	70	130			
Lab iD:	C17020566-001BMSD	Sample Matrix	Spike Duplicate			Run: VOA5	973A.I_170227A		02/27/	17 11:59
1,4-Dioxane		206	ug/L	2.0	103	70	130	3.0	20	



Billings, MT 800.735.4489 • Casper, WY 888.235.0515 Gillette, WY 866.686.7175 • Helena, MT 877.472.0711

C17020566

Work Order Receipt Checklist

Colorado Analytical Laboratories Inc

Login completed by:	Dorian Quis		Date	Received: 2/21/2017
Reviewed by:	Kasey Vidick		Re	ceived by: dcq
Reviewed Date:	2/21/2017		Car	rier name: Ground
Shipping container/cooler in	good condition?	Yes 🗹	No 🔄	Not Present
Custody seals intact on all sh	hipping container(s)/cooler(s)?	Yes	No 🗌	Not Present
Custody seals intact on all sa	imple bottles?	Yes	No 🗌	Not Present 🗹
Chain of custody present?		Yes 🗹	No 🛄	
Chain of custody signed whe	n relinquished and received?	Yes 🖌	No 🗌	
Chain of custody agrees with	sample labels?	Yes 🔽	No 🗌	
Samples in proper container/	bottle?	Yes 🗸	No 📋	
Sample containers intact?		Yes 🗸	No 🗌	
Sufficient sample volume for i	indicated test?	Yes 🔽	No 🗌	
All samples received within he (Exclude analyses that are co such as pH, DO, Res CI, Suit	nsidered field parameters	Yes 🗹	No 📋	
Temp Blank received in all sh	ipping container(s)/cooler(s)?	Yes	No 🗹	Not Applicable
Container/Temp Blank temper	ature:	6.8°C Blue ice		
Water - VOA vials have zero I	neadspace?	Yes 🗸	No 🗌	No VOA vials submitted
Water - pH acceptable upon r	eceipt?	Yes	No 📋	Not Applicable

Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

Contact and Corrective Action Comments:

None

	HOLOI
	uscoay
Ç)
4	5
1	
Ē	5

Report To Information	Bill To Information (If different from report to)	Project Name	Colorado Anal Ara
Company Name: Colorado Analytical	Company Name: Same As Report To	170217005	Laboratories, inc.
Contact Name: Stuart Niclson	Contact Name:	Lfh-1 Co-0121724	Brighton Lab 240 South Main Street
Address: 240 S. Main St.	Address:	Task Number (Lab Use Only)	Brighton, CO 80601 Lakewood Lab
			12860 W. Cedar Dr. Suite 100A
ļ			87700 DO DOD MONHON
City Brighton State CO Zip80601	CityState Zip		Phone: 303-659-2313
Phone:3036592313 Fax:3036592315	Phone: Fax:		Fax: 303-659-2315
Email: stuartnicison@coloradolab.com	Email:	Disposal Date(Lab Use Only)	WWW.coloradolab.com
Sample Collector: Stephanie Schwenke	PO No.:		

<u>Brighton Lab</u> 240 South Main Street Brighton, CO 80601 <u>Lakewood Lab</u> 12860 W. Cedar Dr, Suite 100A Lakewood CO 80228

C MONDAL					
	625 SOCs				CS Charge
	Grab or (Check One Only) Composite 624 VOC Long List				ia: Relinquished By:
	Plant Tissue Other Other Drinking Water			CIS Info	Date/Time: Reling
NAME AND ADDRESS					Received By:
and a state of the state of	Soll Sludge Compost	170217005-01 LFH-I		Peergy Labs	Date/Filme: 730/7 1600
	te Water	2/16/17 17/02/		Instructions. Send viz UPS to Energy Labs	3, A Relinquished By: DADAMA

v Public Water System) Section JI (Sumplied or Completed or Completed or Completed or Completed or Completed or Completed fragmenton) Information Laboratory ID: CO 0015 Phone #: 719-227-0072 Laboratory Namc: Colorado Analytical Laboratory Namc: Colorado Analytical Laboratory Namc: Contract Person: Customer Service Do Samples Need to be Contract Person: Customer Service Do Samples Need to be Comments: Section III (Supplied or Completed by Public Water System) Section III (Supplied or Completed by Certified Laboratory) Section IV Inorganic Chemicals (Completed by Certified Laboratory) Analytical Laboratory) Analyte Name TAB	Colorado Deparaceut		Inor 4300 Fax	Inorganic Chemicals Certified Laboratory Report Form WQCD - Drinking Water CAS 4300 Cherry Creek Drive South, Denver, CO 80246-1530 Fax: (303) 758-1398; cdphe.drinkingwater@state.co.us	emicals Certified Laboratory Report Form WQCD - Drinking Water CAS Creek Drive South, Denver, CO 80246-1530 58-1398; cdphe.drinkingwater@state.co.us	orm 1530 1.us		Revise	Revised 6/13/2014
Public Water System Information 04 Laboratory II 105 Laboratory N 105 Renth MD 105 Phone #: 719-227-0072 105 Contact Person 106 Samples Need to be 107 Contact Person 108 Composited BY THF LAB? 108<	Section	I (Supplied or	r Completed by Public	Water System)	Section JI (Sur	plied or Completed b	v Certified 1	shoratory	
14 Iaboratory ID: C0 0015 nrg Ranch MD Laboratory Name: Colorado Analytical Labor k Volle Phone #: 719-227-0072 Contact Person: Customer Service composited BY THE LAB? Contact Person: Customer Service Collector: Stephanie Schwe Facility ID Section III (Supplied or Completed by Public Water System) Section IV Inorganic Chemicals (Completed by Certified I aboratory) Analysis Date Iab Sample ID Analyte Name Date 170324007-01 Fluoride		Public W	ater System Information	tion	Ŭ	rtified Laboratory I	nformation		
ng Ranch MD k Volle k VVolle k VV	PWSID#: C0012172				Laboratory ID: CO 0015				
*k Volle Phone #: 719-227-0072 Contact Person: Customer Service Do Samples Need to be Composited BY THE LAB? Do Samples Need to be Comments: Comments: Section III (Supplied or Completed by Public Water System) Section III (Supplied or Completed by Public Water System) Analysis Lab Sample ID New Well Sample Pt ID (On Schodule): New Well Section IV Inorganic Chemicals (Completed by Certified Laboratory) Analytical Laboratory) Date 170324007-01 Fluoride	System Name: Sterlir	ng Ranch MD			Laboratory Name: Colorado	Analytical Laborato	L.		
Do Samples Need to be Composited BY THF LAB? Do Ruments: Composited BY THF LAB? Comments: Composited BY THF LAB? Section III (Suppled or Completed by Public Water System) Section III (Suppled or Completed by Public Water System) Analysis Lab Sample P1 ID (On Schedule): New Well Section IV Inorganic Chemicals (Completed by Certified Laboratory) Date Analytical 170324017 170324007-01	Contact Person: Marl	k Volle		Phone #: 719-227-0072	Contact Person: Customer 5		Phone: 303-659-2313	-2313	
Section III (Supplied or Completed by Public Water System) Section III (Supplied or Completed by Public Water System) Section IV ID (On Schedule): New Well Sample P1 ID (On Schedule): Analysis Lab Sample ID Analytical Method 12ate 170324007-01 Fluoride 7681.00.0 Analytical Method	Comments:			Do Samples Need to be Composited BY THE LAB?	Comments:				
Section III (Supplied or Completed by Public Water System) Collector: Stephanie Schwe Facility ID (On Schedule): New Well Section IV Inorganic Chemicals (Completed by Certified Laboratory) b Analysis Lab Sample ID Date CAS No Analysis Constant Construction Analysis Constant Constant Completed by Certified Laboratory) Date CAS No Analyte Name CAS No Method Cm								-	
Collector: Stephanic Schwe Facility ID (On Schedule): New Well Sample P1 ID (On Schedule): Section IV Inorganic Chemicals (Completed by Certified Laboratory) Section IV Inorganic Chemicals (Completed by Certified Laboratory) Mailyical Mailyical Date 1324017 170324007-01 Fluoride 7681.40.4 Fluoride				Section III (Supplied or Comp	leted by Public Water System				
Section IV Inorganic Chemicals (Completed by Certified Laboratory) Lab Sample ID Analytical Mathematicals Completed by Certified Laboratory) 1 ab Analysis Lab Sample ID Analytical M 1 bate 3/24/17 170324007-01 Fluoride 7691.40.4 PAD 200.0	Sample Date: 3/23/17	Collec	tor: Stephanie Schwe	Facility ID (On Schedule):]		ole Pt ID (On Schedu	le): New Well	Vell	
Lab Analysis Lab Sample ID Analyse Name CAS No. Analysical Date 3/24/17 170324007-01 Filuride 7681.40.4 PDA 200.0			Sec	tion IV Inorganic Chemicals (C	ompleted by Certified Labora	torv)			
3/24/17 170324007-01 Fluoride 7681-40-4 PDA 200-0		Analysis Date	Lab Sample (D	Analyte Name	CAS No.		MCL (me/l.)	Lab MRL.	Result
		1/24/17	170324007-01	Flunride	7681-49-4	EPA 300.0	4	0.09	1.22

NT: Not Tested Lab MRL: Laboratory Minimum Reporting Level BDL: Below Laboratory MRL. A less than (<) may also used.

mg/L: Milligrams per Liter MCL: Maximum Contaminant Level

										V #	1				-11								-	7	-				
						¢					yses			ua	nines U												r		
					Lakewood Lab						Subcontract Analyses			I	Radon	T		\square	1			1	\uparrow		Γ	Seals Present Yes 🗆 No 🚺 Headspace Yes 🚺 No 🕅	date i	Date/Time:	
			*			Allmo			el		ract		1	377 W	nibeA						×						<u>لا</u> ر	ime	
			Stree			228	313	20	103.		cont		9	ш 53	uibsA						×					BCC		ate/T	
<u>-9</u> 2		A	ain S	5	읣		59-2	-231	olab		Sab		BI9Ela	nqlA	Gross					×			\square		1	cadsp	li elec T	jä	
Č Š	200	le l	¥۲	5			03-6	-659	orad				70	5-5	िला							×				E.			
Colorado Analytical		<u>Brighton Lab</u>	240 South Main Street		Lakewood Lab	Lakewood CO 80228	Phone: 303-659-2313	Fax: 303-659-2315	<u>www.coloradolab.com</u>			(alaniO) t	57 AN	'YANS											No	3.3 °°°°°.	+	
Ŭ SE SE SE SE SE SE SE SE SE SE			240 R-Io		ABL ABL	lak	Pho	Гах	MM			(ə	(Circl	DOC	, JOT,												0.00	B	Í
76											6		xəpul	.gns.	עזאיע										×	Jen 1	ิญ	Received By:	
											lysi			soinu	agroni									X		s Pre	<i>w</i>	Rece	
	Г		Т	1	•		80				k ans			əp	F)riori										X	Sea			
				9	CRESCENT		State Co Zip & Chos				checl			;	Nitrite						•				X		ŗ	3	
-1	_			4	2		S dz			A	5				Vitrati										X				
t V	matio	3		Y	S		9		N N	, ²	alys		31	ddo)	\beaJ												C's Channal	Date/Time:	
6	Infor	Ì		8	1		State	3	Y cs	Yei	er Al				2225														
page lot 2	State Form / Project Information		System Name:	STERLENC RANCH MD	20 BOULDER			County: El Paso	Compliance Samples: Yes 🔂 No 🗍	Send Forms to State: Yes 🗆 No 🔯	Drinking Water Analyses (check analysis)			_	5.4.2												K V		
B	14/10	S		뇌	3		6 6 5	11	ie Sar	le to S	ing	L			2.942								X				9	ż	
	For			G G	00		(Thy COLO	ly:	- Hane	Form	rink	L			1.842		×										ľ,	Relinquished By:	
	State	201111	Syste	3	<u></u>		City	Court	C.	Send	II, V D	1			9 <i>L</i> 7 5	1											e Vie	quis	
dy	F			1	5		, .				I, II,		Sateme			-										C/S Info:	Delivered VIa. Fed Ex	Relin	
in of Custody	â	.		_	Sce		Ŋ		Mar.		PHASE	<u> </u>	s-Pest			-	<u> </u>	X											P
fCi	port	~	Ń		RE		36				H	<u> </u>			254'5												tes 1		2
ii.	Loth re	WATTER	MORLEY		J		- di No	Fax:	000		ĺ	-	saon icides		1 SO2	×	-	<u> </u>								2	+ \$	E	크
Chai	irent f	HAL	AC		1		ŝ	μ.	9			\vdash				\vdash										1 we	201	Date/Time:	24
er (<u>r diffe</u>	R R	5		P		tate		38.1			J														theluded	Äł	Ā	3
Wat	l) uoj	5	MIL.		BOULDER CRESCENT		3		3						S A/9		-		X							4	1 2		S
Drinking Water Chai	ormat	Vame	ane:				33		707					(Residi J\gm)											3	RECENC Draugh RECENCE the Scinoments		ৰ
inki	o Infe	any l	ict Na		ä		391	*	.9												^					J	3.5	i.	Z
Dr	Bill To Information (If different from report to)	Company Name: SR	Contact Name:	Addee	20		City Specules State Collin 8090 \$	Phone:	Email: jmortey 3870(2) ad	PO No.:		-			10.0N			\$		_	3	3	ſ	~	\leq	preservative was	Please preserve	Received By:	11: 30m/50ice (rulan 3/24/17 1010
	┢	-		+						2					0								6 N.			Sa	Pleas	tecei	50
		3			2		3		J	Schwenke					Cod			8.05					no HEXUsian			R	A c		-V
		N.		4	AN		e de la		ų	Y					EP			8.0					no H220			e con	1. 5. 5. 5. 5. 5.		2
		J	J-I-J		۲.	0	8		PT	N/					0								54				- La -	je:	兰
		-5			Y.	1) 41	ZIP	(time	4	2		Ì			mple		3	3	+	5	9	5		- 1	40	Ŝ	A Pro	Date/Time:	2
		1	뇟		Hilesteal		Stall CZIP 80903	ŇQ		K					Client Sample ID / EP Code	#	E D	#3	44	#	94	4	8 1 7	49	#	14, SOu	500 #	Dat	3-23
	ton	Z	Jark		í	Sulte	State	74	9	T					Clie						4					0	影		
	vrmat,		2		S I	Ń		ß	R	2	ġ	77			2	N.	2	TT.	-	ন্থ	1.20m	3	Х	5	3	2 Z	27	ä	1
	o Infe	E RN -	Vame:		9		5	5	É	Name	ask	170324007		ARF	Time	7:53	LSIL	N	8:1)	7152	3	153	1:58	7:59	5.03	fons:	7 SP	P	th
	Report To Information	Company Name: J DS-H-Cdro Cerrol Hands	Contact Name:	Irea:	345			Phone: 119-207-0079ax.	Email: M Vo / k (jship a for	Sampler Name: Sechante	CAL Task No.	1703		۹	0						•	-			~~	Instructions:	With the both shipment. Samor #8 no soon	Relinquished By:	Z
	Re	C	C	Ado			CIEV	Pho	E	San		<u>к</u> -			Date	5-23	-							\rightarrow	-	Inst	3		P
												F	age 2	? of 3	1					1									×,

Analytical	LABORATORIES, INC.	Brighton Fah	240 South Main Street	Brighton, CO 80601	Lakewood Lab		Lakewood CO 80228	Frome: 303-659-2313 Fax: 303-659-2315	www.coloradolab.com			analysis) Subcontract Analyses	()	ircle)	528 526 529 724 724 724 72 72 72 72 72 72 72 72 72 72 72 72 72	A, DV A, UV A, UV Z, MU Z, MU	Alk. Alk. Cros Cros Cros Cros Cros Cros Cros Cros											Seals Present Yes No Headspace Yes No	ce Sampl	Neceived By: Date/Lime:
page 2 of 2	State Form / Project Information		System Name:	Service Parcy MY	Address: A start A start A start A		15 N. C. 942	E D'		Compliance Samples: Yes N No L		PHASE I, II, V Drinking Water Analyses (check analysis)		יזנ	phosa ndotha iquat FHMs AA5s AA5s	1.1 En 2 D 2 L 	Nitr 2524 5524 5524 5524 549												CS Charge L	
Drinking Water Chain of Custody	erent from report to)	SPUDDEr	moder	0	Jder Cresent		Cirl J. San suil Day 219.2		3870001		20	PHASE I, II, V	d	stes est qes Bs BCI	arbam OCs-P	11 C 27 2 27 2 27 H 2 5 4 H	231 575 515 505 705				*						×	C/S Info:	Date/Time: Relinguish	
Drinking Wa	1	Company Name:			Address: JU Ba		1			UNENKE PO No:				ani Yine	ontain Chlor) o î o Seubis g/L) BRD	оИ зэЯ м)		×	5	2	a	4 Dickene) 3		9	3	<u>.</u>		Received By:	- ć
	Report To Information	Company Name: JDS-14cdrc (cnxul lands)	Contact Name: Mark Volle		WISHS E. PILLERE AND	Sunt 200	City CS Star CZID RU903	e-911.ª	Email: MVolleCidehydre, Com	Sampler Name: Konding of Muserker PO No.		CAL Task No.	170324007	Ра	ARF ARF	w Date Time Client Sample [D / EP Code		117 1018 22-5	C # +10°	× 1 3	117 PC:S		1)0117	17	8177 65-8	1/ 8/12 #19	OCT beis .	Instructions:	Relinquished By Date/Time:	1:200 1:200 1:200

P 500 Drinking Water Chain

Colorado

		Inorg	Inorganic Chemicals Certified Laboratory Report Form	d Laboratory Rej	port Form			Revise	Revised 4/13/2015
Colorado Denorman	I Ħ	Subm	WQCD - Drinking Water CAS Submit Online at http://www.wqcdcompliance.com/login	ng Water CAS wqcdcompliance.	.com/login				IOC
of Public fleath	4		e	¢	D)
S	ection I (Sumplied	Section I (Sumplied or Completed by Public Water Syst	: Water System)	Section	Section II (Supplied or Completed by Certified Laboratory)	Completed by	Certified La	aboratory)	
	Public	Public Water System Information	tion		Certified I.	Certified Laboratory Information	formation		
PWSID#: C00121724	121724			Laboratory ID: CO 0015					
System Name:	System Name: Sterling Ranch MD	Ð		Laboratory Name: Colorado Analytical Laboratory	Solorado Analyti	cal Laboratory			
Contact Person: Mark Volle	: Mark Volle		Phone #:	Contact Person: Customer Service	stomer Service	Phot	Phone: 303-659-2313	-2313	
Comments:			Do Samples Need to be Composited BY THE LAB?	Comments:				1	
				-					
			Section III (Supplied or Compl	(Supplied or Completed by Public Water System)	System)				
Sample Date: 3/23/17		Collector: Stephanie Schwe Facility II		New Well	Sample Pt ID	Sample Pt ID (On Schedule):	c): New Well	Vell	
			Section IV Inorganic Chemicals (C	ganic Chemicals (Completed by Certified Laboratory)	Laboratory)				
Lab Receipt Date	Lab Analysis Date	Lab Sample ID	Analyte Name	CV	CAS No.	Analytical Method	MCL.	Lab MRI.	Result (mu/1)
3/24/17	3/29/17	170324007-01A	Antimony	7740	7740-36-0	FPA 200.8	0.006	0.001	BDL
3/24/17	3/29/17	170324007-01A	Arsenic	7440	7440-38-2	EPA 200.8	0.01	0.001	0.002
3/24/17	3/29/17	170324007-01A	Barium	7440	7440-39-3	EPA 200.8	2	0.001	0.003
3/24/17	3/29/17	170324007-01A	Beryllium	7440	7440-41-7	EPA 200.8	0.004	0.001	BDL
3/24/17	3/29/17	170324007-01A	Cadmium	7440	7440-43-9	EPA 200.8	0.005	0.001	BDL
3/24/17	3/29/17	170324007-01A	Chromium	7440	7440-47-3	EPA 200.8	0.1	0.001	BDL
3/24/17	3/29/17	170324007-01A	Mercury	7439	7439-97-6	EPA 200.8	0.002	0.0001	BDL
3/24/17	3/29/17	170324007-01A	Nickel	7440	7440-02-0	EPA 200.8	V/N	0.001	0.001
3/24/17	3/29/17	170324007-01A	Selenium	7782	7782-49-2	EPA 200.8	0.05	0.001	BDL
3/24/17	3/30/17	170324007-01A	Sodium	7440	7440-23-5	EPA 200.7	V/N	0.1	52.8
3/24/17	3/29/17	170324007-01A	Thallium	7440	7440-28-0	EPA 200.8	0.002	0.001	BDL

NT: Not Tested Lab MRL: Laboratory Minimum Reporting Level BDL: Below Laboratory MRL. A luss than (<) may also used.

mg/L.: Milligrams per Liter MCL.: Maximum Contaminant Level

								V #*	V				-11							-		1					
				×					yses			un	ni ne rU										.		Г		
				Lakewood Lab 12860 W. Cedar Dr, Suite 100A Lakewood CO 2023					Subcontract Analyses			I	Radon				T							Scals Present Yes 🗆 No 🚺 Headspace Yes 🚺 No 🕅	(March	Date/Time:	
		*		Suite			el		ract		1	877 W	uibsA				Γ		×						2		
		<u>Brighton Lab</u> 240 South Main Stread	109	Dr, 1	EIE	NO.	www.coloradolab.com		cont	Γ	9	w 576	nibsA	Γ					X					ace 1			
-87 F	i	و اهر		dar dar	59-2	-231	lolat		Sub		SJBCtg	Alph	Gross	T				×						cadsp	a la c		
ČĘ			ŭ I		03-60	-623	orad				70	5-3	লে				<u> </u>			×				F.	, Car		
Colorado Analytical		Brighton Lab	Brighton, CO 80601	Lakewood Lab 12860 W. Cedar Dr.	Phone: 303-659-2313	Fax: 303-659-2315	v.col			(ələriO) t	ባለ ን?	אאט:											2 S	7		
ŬÆ ∰	5	Brig	Brig	Lak 1280	Pho	Рах	MM			(:	(Circl					ľ									or lies V	By:	
10									6		хәриլ	.gns.	V'XIV										×	lent.	ิญ	Received By:	
									elysi			soinu	inorga Thorage									X		la Pre	() ()	Rece	
	Г				03				k an			эр	nouli										X	Sea	(7) F		
			9	CRESCENT	SG				chec				Nitrite						ŀ				X		,c	3	
	-		-	S.	Z4p		q	E	ses (Nitrat										X		harde	Date/Time:	
(N 4	matio	24		S	9		L.	Ž	naly				lbsol												C/S Charace	Date	
6	Infor	AT.	2		State Co Zip SOG03	R	Yes	Yes	er A				2225														
page lot 2	a lect	00	27	Q		0 a	nples	State:	Wati	L			2.4.22												X V		
B	n/Pr	S	i i i	3	500	II.	ce Sai	ns to 1	ing	L			2.942						_		X			Į	Q	i.	
	State Form / Project Information	PWSID: CO 0121724	stem Name: Strautide Raich MD	Address: 20 Bow Der	(Thy COLOS	County: El Paso	Compliance Samples: Yes 🙀 No 🗌	Send Forms to State: Ves 🗌 No 🙀	Drinking Water Analyses (check analysis)				1.842	<u> </u>											يلا	Relinquished By:	
	Stat	PWS	Syste (A	<u>ş</u> g	City	Cour	- ES	Send	11, V D				247 G	<u> </u>	_	 									N N	Iquis	
dy		,		5	1 -				1		250 1-8 Solanne													C/S Info:	Delivered Via: Fed Ex	Relir	
in of Custody	ê			CRESCENT	N		38701, logo 100		PHASE		s-Pest			-		X									č	 	e
Į C	E port	2	NORLEY	RE	200				PH/	<u> </u>	səpioi	_	254'5											-	- Le		a101 L142
	rom n	TER	7	1	in N	Fax:	00				PCBs									_				2	τş		크
Cha	crent	LNAT	Ă	3	ق		र्षे			H					<u> </u>				_					theluded	أتمك	ter	24
ter	f diff		٢.	A	itate						/d mno			\vdash										2	Ăł	a	10
Wat	lon (I	N.	5	BOULDER	25		य		L		s Only						×							4			B
Drinking Water Cha	Bill To laformation (if different from report to)	Company Name: SR	Contact Name: 37M		CLOORADOUS State Co Zip 8090 \$		Emuli jMorley					nal Chi	ղ/Ձա)										~	Sou	Please preserve Diquot		11. 3m 5000 Milloud 3
inki	o laf	l ynac	net N	5.	39		-7				-								3		-			لو	5.5	الخ	Z
ŋ	E III	Comi	Cont	Address: 20	U _À	Phone:	Emai	PO Na.:		-	220016	ano)'				6				3		~~	1	preservative	30	ved E	N.
				1		-							0								- trouded in switch			2 A	55	Recei	20
		3		8	M		J	Schwenke					Cod			Ś					24			3			2
		No.		Ł	5		é	Å					/EP			8:05					L L			Ľ	いまい	ĺ	2
			2102	Ja Q	∞		- I I	N)					e ID								길				و کې -	:ee	1
		- Shi	5	G M	Zip	6	JST I	لإ					Idma	_	Ŋ	₩ 3	+	# 2	94	51	-18-	5	24	ß	3.00	Date/Time:	3-73
		77	빗	AllesPeritAue	Statucize 80903	12		E.					Client Sample ID / EP Code	*	Ħ	#	44	7	4	4	쿠	#	7	HaSou	10 m	Å	ž
	tłon	20	1 1015	- 7	Stat	1	muster jashindre com	ž					ë						٤						ま		
	orma	티스		NS		الم: الم:	B	(V)	No.	07			ae	3	5	N	-	22	1:52am	3	स्र	হ	3	Z	12	éd By:	1
	Fo Inf	y Nar	Namo	19	S	0	έ	Nam	CAL Task No.	170324007		ARF	Time	7.55	12:1	¢.	8.1)	71.52	Ř	1533	7:5%	1	5.03	tions	Ŧð	at to	Ð
	Report To Information	Company Name: JDS-H-dro Cerrout Hards	Contact Name:	Address: 15 E.		Phone: 119-337-007 Pax:	Email:	Sampler Name: Stechante	CAL	170;			e	3-23										Instructions: No	with the bothe shipment. Sample #8 as seen	Relinquish	Z
	Re	ວິ	ටී	P	City	Ph	빌	Sar		p. -			Date	10								4	-	Ins	3	2	YP
										f	age 2	: 01 3															

Colorado Analytical	LABORATORIES, INC. Brighton Lab 240 South Main Street	Brighton, CO 80601	12860 W. Cedar Dr, Suite 100A Lakewood CO 80228			www.coloradolab.com		Inalysis) Subcontract Analyses	(3. Index OC (Circle 254 (Circle Dia/Beta	Fluoride Inorganic Alk./Lang Gross Alg Gross Alg Radium 2 Radium 2 Radium 2 Radium 2	×				×				Seals Present Yes 🗌 No 🗍 Headspace Yes 🗍 No 🗍	Temn. "C floe Samula Pres Vec 🗆 No 🗍	ceived By:
page 2 of 2	rt Information PELIE 10	AWY	Daulacy Ursent	State ZipSUJU3	0	Yes 🔰 No 🗆	Ves 🗆 No. 🙀	r Analyses (check a			552.2 HA Lead/Cop Nitrate Nitrite										CS Charge 1	1 1
	12	Specifics Barch MY	00 241	cly CS	County: El Paso	Compliance Samples: Yes 💋 No 🗌	Send Forms to State: Yes No.	PHASE I, II, V Drinking Water Analyses (check analysis)		dothall dothall	254'5 D! 248'1 Eu 248'1 Eu 231'1 Cª										Delivered Via:	Relinquished By:
ater Chain of Custody	Bill To Information (If different from report to) Company Name: SR_Warker-		MACH TEXM	Statt DZIP 20103	Fax:	~3870@asl.com	2	PHASE I, I	d	Cs-Pest	252'5 20 212'4 HG 202 Le2 204'1 EI								×	C/S lbfo:	Delive	Date/Time: Rei
Drinking Water Chai		Address:	8	S culolesap	Phone:	Email: JMON Lev	NKCPO Na:			Chlorine	Residual No. of Cc Residual Sam	-	X	n e	nc	Dictor 3	1 1	6	ar.			Received By:
	Report To Information Company Name: JDS-1-Higher Consul Hands	S. P.V.		CS state zin 80903	119-327-0073	Email: M Volle@jdshydro.com	Sampler Name: Kichenke Schusenke PO No.:	CAL Task No.	170324007	ARF	Time Client Sample ID / EP Code	8101 #11	6:mm #13		2:40 ALL	+·1)0117	キレ	814 6:8	004 beis			eid By Date/Time:
	Report To Infor Company Name: Contact Name:	CHC PA		City	Phone:	Email:	Sampler	CALTa	17032	Page 3	c o	3-23	-							Instructions:		Reinquished by



Report To: Mark Volle Company: JDS Hydro Consultants 545 E. Pikes Peak Ave Suite 300 Colorado Springs CO 80903 **Analytical Results**

TASK NO: 170324007

Bill To: Jim Morley Company: SR Water 20 Boulder Crescent St. Colorado Springs CO 80903

Task No.: 170324007 Client PO: Client Project: Sterling Ranch MD CO0121724

Date Received: 3/24/17 Date Reported: 4/21/17 Matrix: Water - Drinking

Customer Sample ID Sterling Ranch MD Sample Date/Time: 3/23/17 8:03 AM Lab Number: 170324007-01

Test	Result	Method	ML	Date Analyzed	Analyzed By
Bicarbonate	99.7 mg/L as CaCO3	SM 2320-B	0.1	3/28/17	VDB
Calcium as CaCO3	2.5 mg/L	SM 3111-B	0.1	3/30/17	MBN
Carbonate	< 0.1 mg/L as CaCO3	SM 2320-B	0.1	3/28/17	VDB
Langelier Index	-1.23 units	SM 2330-B		3/31/17	LJG
pH	8.16 units	SM 4500-H-B	0.01	3/24/17	MBN
Temperature	20 °C	SM 4500-H-B	1	3/24/17	MBN
Total Alkalinity	99.7 mg/L as CaCO3	SM 2320-B	0.1	3/28/17	VDB
Total Dissolved Solids	143 mg/L	SM 2540-C	5	3/29/17	ISG

Abbreviations/ References:

ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpn/100 mis = Most Probable Number Index/ 100 mis Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

240 South Main Street / Brighton, CO 80601-0507 / 303-659-2313 Mailing Address: P.O. Box 507 / Brighton, CO 80601-0507 / Fax: 303-659-2315 Page 1 of 3

170324007 1/ 1

								V #	2				-11							-		1					
									yses			un	viasrU												Г		
				Lakewood Lab 12860 W. Cedar Dr. Suite 100A					Subcontract Analyses			1	nobeA				Ť					\square		Seals Present Yes [] No [V] Headspace Yes [V] No [V]	and a	Date/Time:	
		7		Suite			ci		ract		8	77 W	nibeA	Γ					×						<u>بر</u> د		
		Stres	109	Dr, 1	515	10	0.001		cont		9	ш 52	nibaA						X					acc	1		
Colorado Analytical		<u>Brighton Lab</u> 240 South Main Street	Brighton, CO 80601	Lakewood Lab 12860 W. Cedar Dr.	Dhone: 303-659-2313	Fax: 303-659-2315	<u>www.coloradolab.com</u>		Sub		BJ38/6r	İqİA	eross					×						tadap	a hua		
Č Ť	ĺ	P La	C -			-623	orac				205	<u></u>	5 পে							×				E.	, Ear	5	
Colorado		Brighton Lab	pho	Lakewood Lab 12860 W. Ceda	net	30	w.co			6	oloriO) Þi	2 VU	2074											2 Z	7	\uparrow	
Ŭ₽ ₹	5	Bris 202	Bri	128 T	Pho	Fах	WM			(9	(Circl													K E E	or line vi	B	
11									6		хэриј												×	Sent	M	Received By:	
N									alysi				rgyonl									X		Is Pre	8 13	Rec	
				1.	0]	k an				Fluori										X	Sea			
			9	CRESCENT	50				chec								Ŀ		·				X		,C		
			7	X	Zip		Q	A	Ses (Nitrati										X		er en er	Date/Time:	
Ť	matic	રન	Y	F	9		L N	Ž	naly)/bssJ												C/S ('herree)	Dat	
4	Infor	モリ	Z	R	State Co Zip & OPOS	3	: Yes	Yes	erA	L			2255			<u> </u>	<u> </u>										
page lot 2	State Form / Project Information	PWSID: CO 0121724	STEALENC RANCH MD	Address: 20 BOULDER		0	Compliance Samples: Yes 🗗 No 🛛	Send Forms to State: Yes 🗍 No 🕅	Wat				234.2	1											У Х		
B		S	ii t	3	09	Ū	ce Sa		king	<u> </u>			2.99.2			<u> </u>					X				p	ä	
ï	e For	SID:	System Name: STE PLT	Less:	(Thy COLOGES	nty:	n alian	1 For	Ē				248'I 242 G						_						Ľ	hed	
	Start	PW	is V'	Sca	City	Cou	Com	Sen	II, V Drinking Water Analyses (check analysis)		solaniso			-										ö	N P	Relinquished By:	
ody		1	ł	BOULDER CRESCENT					-	\vdash	Ja-Pest			-							_			C/S Info	Delivered Via. Fed Ex	Reli	
Drinking Water Chain of Custody	9		~	3	0		Mar.		PHASE	\vdash			254.2	+			-				-					r r	e
of C	Loda	ď	MORLEY	RE	808		- 10		H		səbiəid			×	-					-				-0	- Lev		1 [0
ain (from	E	20	U	ZID	Fax:	20			\vdash	\bCB ²	-									—			AC	13	ime:	뷖
Ch	Terent	PC.	2	L.	S		5				BADBCI	EDI	1.402	┢──		-						-		theluded	305	Date/Time:	17
ter	(if dif	R	£	JIN	State		38			V	\9 mioî	iloD	leto T	┢			N.	_	_					2	Ă₹		
W	atton		6	R	R		관				yinO a:	əlqm	s A\q								-	—		8	いい		S
king	Bill To information (if different from report to)	Company Name: 5R WATER	Contact Name: 37LM		CILY EPPENICS State Cozip 8090 \$		Email: jmortey 3870(200)				aninoiri		Mesidu J\gm)											preservative was	Please preserve Diguot		11. 300 5050 millou 3/24/17 1010
rinļ	To F	npany	Iact	Address: 20	24	ie	-7	No.:			ยางก่อน	uoj.	10 .0N			3		-	3	3				3	94	By:	2
Q			Col	Vdd	5 S	Phone:	- 1	PO No.:		\vdash						_			-					F	33	Received By:	No.
		Y N	1	1			Ę	Schwenke					ę			,					no rounded in suit			Ž	se	Rec	W.
		XTT1		ž	2		J	N.C.					о С			8:05				Į				S.			Å
		Ňa.	1	S.	5		2	<u>گ</u>								00				Ī				å	Sen .		2
		e =		3 4	$\overline{\mathbf{v}}$		Ž	N)		ļ			sle II					. 1			≠8 \			D.F.	69	ime:	1
		The second	2	30	3	3	-2	AR AR					Samp	1#	J.	4	#4	ま	94	4	87	# 0	24	hosetl	1700	Date/Time:	3-23
	_	JA S	11 1011	PhiesPear And	State Scy 5303	8	C	-8	,				Client Sample ID / EP Code			*	Ŧ		-		- 7	47			SH S	a	2
	nation	HE			8	10	muster jeshydre. Com	Å		1									<u></u>			_	_	Ŷ	200		
	nforn	ame	li li li li li li li li li li li li li l	5	S	2	3	ne: C	k No.	1007			Time	7.55	T:SIT	N	8:1)	7152	Tistam	133	1:58	S	5.03	1S:	۶٤	d By:	
	t To I	any N	ct Na	J.	ات	الر	٤	er Na	CAL Task No.	170324007		ARF			-	¥ 2	8	5	Ч	7	7	ŕ	5	Iction	Ŧŷ ∠		R
	Report To Information	Company Name: JDS-H-drs Cavoul Kavts	Contact Name:	Addresside E.	City	Phone: 119-337-0079ax:	Email:	Sampler Name: Stechante					Date	3-23	-							1		Instructions:	with the bothe shipment. Sample #8 and seen	Relinquish	.th
1			-		<u> </u>					F	age 2	of 3		1/12								1				~ (K)

															- 24		10	٩	1									
						•								u	nuinerU				\prod		Τ		Τ		Τ		 1	
						12860 W. Cedar Dr, Suite 100A					Subcastante Audimen				nobeЯ	+	1	1-		>	7	\uparrow	+	1	+	Ž	i i	Date/Time:
			÷			Suite								528	muibaA		1-	1		<u> </u>	Ť	1	\uparrow	\uparrow		Seals Present Yes 🗌 No 🔲 Headspace Yes 🗍	Į,	
			240 South Main Street	501		Dr, S	077	2 5	www.coloradolab.com		100			977	muibeA		1		\parallel		1	1		\uparrow		BCe	'	Date/Time:
<u>8</u>	INC.	-		080	କ୍ଷ			-231	deloi		13		Beta	/eydi	A seord	1				\uparrow			1	1		adsp		
<u> Š</u>	RIES.	le. I c	N N	ŭ	od L	0.7		-629	orad			Τ	2	PIV	oya	×									1		(5
Colorado Analytical	LABORATORIES, INC.	Brichton I.ah	Sour	Brighton, CO 80601	<u>Lakewood Lab</u>	12860 W. Cedar Dr.		Fax: 303-659-2315	<u>v.col</u>				(Simic)	1 X 524	U ,AYU2									1	1	No		
ОÆ	LABO	Brid	15	Brig	Lak	128(1.a.L		Fax	LMM		İ.				<u>1 (O</u>				\prod			X		Γ		الا ق	t (1 By:
70											1	ŗĹ	хәрс	11 .gm	8.1\.,¥IA											sent	¢	Received By:
6.											alvei			soir	lnorgar										Γ	2 Pre	-	Rece
	Γ		T		+	,	M			7				9	Fluorid											Sea	ŀ	
2		میہ، دو	J	~	8		5				chec				Sitrite												E	
f		(1 1	0	Ę			No IZ		Q	۲. N	l ses				Nitrate]		7.im
2	matic		T	C	3		C		N N	2 T					D\bs9J													Date/Time:
page 2 of 2	Jafar		hel le la	Ş	27		Staten Zudugo	3	Yes	Yes [er A				2.222													
90	State Form / Project Information			Serlin Ranch MIS	Builder Creent			County: E) PASE	Compliance Samples: Yes 🚺 No 🗌	Send Forms to State: Yes 🗌 No 🙀	V Drinking Water Analyses (check analysis)				2.4.2				║									
			PWSID: CO System Name:	2			S	5	re Sai	ns to	ing	° _		_	2.942													ž.
	e Farr			J.	Address:		1		plian	Forn					248.11													hed B
	Stat		PVvs Svst		PPV		0 C		Com	Send					19 <i>L</i> †\$	<u> </u>				\bot								quis
dy	Γ	-		,			1.0	-	5		I, II,			_	1.152		-		-				X			C/S Info:	Delivered Vis-	Relinquished By:
usto	to)				r Cresent		, 20703		38706021.00		PHASE	L			2.25.2	-		\parallel	+-							2	-	
ç	eport	. 5	moder	M	્સ		09		3		PH	Ľ			4.212					-					X			
in a	from r	Ta	5		Y		Sip 2	Fax:	0			\vdash			d \$0\$			$\left \right $										ë
Cha	erent 1	3	ξ		Lec		Q		5			\vdash	DBCb					\vdash					_	Z	-			Date/Tim
ter (If diff	SP-Water	۶		3		Stat ^C D Zi	Í	I 1/	וו ה		h	//d ແມ					$\left \right $	r			-	_	!				Ď
Drinking Water Chain of Custody	Bill To Information (if different from report to)		Contact Name: J (M			•	Email: 1 mor 1 cu	<i>,</i>		┝			es A\q			╋	\vdash			_						
ing	orma	Company Name:	ame:		2		Cirl Chester		Š						(ng/2m) Residu													
rink	lo Ini	pany	act N		SS		đ		1			\vdash						7	g		\sim		9		3			ž.
á	Bill	Com	Cont		Address:		G	Phone:	Emai	PON		\vdash			No. of		2	4	en	3	73	S			<u>c i</u>			Received By:
		¥			.					X					0						No.							Recei
		4			1		M		g	K					Client Sample ID / EP Code						4 Dichane							
		3			Z		3		Re.	Å					/EP						1							, 3bam
		4	Volle		r r	Suite 300	seele zip 80903		귉	Ň					ē	ĺ					3		\mathbf{S}		d			
		tel n	3		Â	in L	ZIP		3	2K					dug		d	4	5	M	917			5	₩ <i>2</i> (Date/Time: 3-2-5 [
		Ŧ	الح		Sey.	t's	3	Ą	J	2					sut S	#11	#	┫	キュ	#	4	#		#	#			<u>n</u>
	thon	Company Name: JDS-14 redre Consul Harts	Mark		E. PikesPeak Ave	S	Stat	EL20-LEE-PIL	Email: M volle@jdshydre, com	Sampler Name: KORINE SCHUSENKE PONO					Č	*	4											d
	Report To Information		I					6	30	() ;;;	ġ	5			e l	5	6 . co en		R	x	2	2	ন্থ	8.15	5		-	
	To In	iy Nai	Ĩ		5		S	5	2	maN.	ask N	2400		ARF	Time	(5)8	3	Ą	Side	8:2	3.10	الح	5	0	6c:8	LIOUS		quished
	port	nagan	Contact Name:	Asses	510		\sim	Phone:	uail:	mpler	CAL Task No.	170324007		4	9	5		T			5			1		Instructions:		Belinquished By
	Re	ບິ	రి				City	Ē		Sar	0	•	-Dam		Date	323				1				イ		IIIS		· /
													- a9	e 3 o												~		7-1

Submit Online at http://www.wgcdcompliancc.com/login Section I (Sumolied or Completed by Public Water System) Section I (Sumolied or Completed by Public Water System) Section I (Sumolied or Completed by Public Water System) Section I (Sumolied or Completed by Public Water System) Contractor I (Sumolied or Completed by Public Water System) Section II (Sumolied or Completed by Public Water System) Contractor Parlow Analytical Laboratory Information Laboratory ID: CO 0015 System Name: Stering Ranch MD Contact Person: Mark Volic Contact Person: Customer Service Phonee: 303-659-2313 Contact Person: Mark Volic Contact Person: Mark Volic Contact Person: Mark Volic Contact Person: Customer Service Phonee: 303-659-2313 Contact Person: Mark Volic Contact Person: Customer Service Phonee: 303-659-2313 Contact Person: Custom III (Supplied or Completed by Public Water Sy				Nitrate and Nitrite		Nitrogen (Certified L	as Nitrogen Certified Laboratory Report Form	sport Form			Revised	Revised 4/13/2015
$\begin{tabular}{ c c c c c c c c c c c c c c c c c c c$	Colorado Depara Of Padde Lealer and Environmen	cateril Mi		Submit	Online at	http://ww	w.wgcdco.	mpliance.com	v/login			, .	XON
Public Water System InformationCertified Laboratory InformationC0121724Laboratory ID: C0 0015Laboratory ID: C0 0015me: Sterling Ranch MDLaboratory Name: Colorado Analytical LaboratoryLaboratory Name: Colorado Analytical Laboratoryrson: Mark VollePhone #: 719-227-0072Contact Person: Customer ServicePhone: 303-659-23rson: Mark VolleSample Pr DConfirmaton'Lab AnalysisLaboratoryrson ScheduleSample Pr DConfirmaton'Lab AnalysisLaboratoryrson ScheduleSample Pr DConfirmaton'Lab AnalysisLaboratoryrson ScheduleNew WellNew WellNew WellNew WellNew WellNew Mellrson ScheduleNew WellNew WellNew WellNew WellNew WellNew Mellrson ScheduleNew WellNew WellNew WellNew WellNew WellNew Mell		Section I (Supplied or Complet	ed hy Public W	ater System)			Section II (S	upplied or Com	pleted by Cer	rtified Lab	oratory)	
C0121724 C0121724 Laboratory ID: C0 0015 me: Sterling Ranch MD Laboratory Name: Colorado Analytical Laboratory rson: Mark Volle Phone #: 719-227-0072 Laboratory Name: Colorado Analytical Laboratory rson: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 rson: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 rson: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 rson: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 rson: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 rson: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 n11 (Supplied or Completed by Public Water System) Continuation' Laboratory naile Schwenk New Well New Well New Well Method naile Schwenk New Well New Well J24/17 J24/17 J24/17 naile Schwenk New Well New Well Method In			Public Water Syste	em Informatio	1				Certified Labor	atory Infor	mation		-
rson: Kerling Ranch MD rson: Mark Volle rson: Mark Volle Interson: Customer Service Phone: 303-659-23 Contact Person: Customer Service Phone: 303-659-23 Network Person Phone Phone Phone Phone Phone: 303-659-23 Network Person Phone Ph	PWSID#: CO	0121724					Laborato	ry ID: CO 0015					
Image: Solution: Mark Volle Phone #: 719-227-0072 Contact Person: Customer Service Phone: 303-659-23 Image: Solution: Supplied or Completed by Public Water System) Comments: Contact Person: Customer Service Phone: 303-659-23 Image: Solution: Supplied or Completed by Public Water System) Section IV (Supplied or Completed by Certified Laboratory) Malysis Laboratory) Image: Solution: New Well New Well New Well New Well Method Image: Solution: Schwenk New Well New Well New Well New Well Nethod Image: Schwenk New Well New Well New Well New Well S00.0 10	System Name:	:: Sterling	Ranch MD				Laborato	ry Name: Colori	do Analytical L	aboratory			
III (Supplied or Completed by Public Water System) Comments: Collector Facility ID On Schedule Sample Pt ID Confirmation* Lab Analysis Laboratory Analytical MCL Date Date Date Date Sample ID # Method Method Method hanic Schwenk New Well New Yell New Net New Yell New Ye	Contact Perso	on: Mark V	/olle	P		-227-0072	Contact F	erson: Custome	r Service	Phone:	303-659-2	313	
mpletcd by Public Water System) Section IV (Supplied or Completed by Certified Laboratory) On Schedule Sample Pt ID Confirmation ⁰ Lab Receipt Lab Analysis Laboratory Analyte Analyte Analytical MCL On Schedule New Well 0 324/17 170324007-01 Nitrate Nitrogen EPA 300.0 10 New Well 0 3/24/17 3/24/17 170324007-01 Nitrate Nitrogen EPA 300.0 10	Comments:						Commen	its:					
On Schedule Sample Pt ID Confirmation? Lab Receipt Lab Analysis Laboratory Analyte Analyte Analyte Analyte Mcthod On Schedule On Schedule 3/24/17 3/24/17 170324007-01 Nitrate Nitrogen EPA 300.0 10 New Well U 3/24/17 3/24/17 170324007-01 Nitrate Nitrogen EPA 300.0 10	Section I	III (Suppli	ed or Completed by P	ublic Water Sy	(tem)		Sect	ion IV (Supplied	or Completed b	w Certified L	aboratory		
New Well I 3/24/17 3/24/17 170324007-01 Nitrate Nitrogen EPA 300.0 10 New Well I 3/24/17 3/24/17 170324007-01 Nitrate Nitrogen EPA 300.0 10			Facility ID On Schedule	Sample Pt ID On Schedule	Confirmation?	Lab Receipt Date	Lab Analysis Date	Laboratory Sample ID #	Analyte	Analytical Method	MCL (mg/L)		Result (mg/L)
New Well 3/24/17 3/24/17 170324007-01 Nitrite Nitrogen EPA 300.0 1		tie Schwenk	New Well	New Well		3/24/17	3/24/17	170324007-01	Nitrate Nitrogen	EPA 300.0	10	0.1	BDL
	3/23/17 tephan	tic Schwenk	New Well	New Well		3/24/17	3/24/17	170324007-01	Nitrite Nitrogen	EPA 300.0	-	0.1	BDL

NT: Not Tested Lab MRL: Laboratory Minimum Reporting Level BDL: Below Laboratory MRL. A less than (<) may also used.

mg/L: Milligrams per Liter MCL: Maximum Contaminant Level

								V ar	6			-11							+							
				<					yses		un	i ns iU										,		Г		
				Lakewood Lab 12860 W. Cedar Dr, Suite 100A					Subcontract Analyses		ι	Rador		1						_			Seals Present Yes 🗆 No 🗸 Headspace Yes 🛛 No 🕅	No l	Date/Time:	
			÷	iuite			ci		ract		822 m	uibsA		 				X						کلیک		
		;	SO1	Dr, S	313	2 40	.com		conti		w 556	uibeA						X					ace Y		te L	
<u>केव</u> ्	Ś			間칠	0 80 2025	-231	<u>lolab</u>		Sub	हाज	8/shqlA	Gross					×						cadap	T star	a	
S S S S S S S S S S S S S S S S S S S		9				-623	orad			7	05-5	en							×			1	H			
Colorado		Brighton Lab	240 South Main Street Brighton, CO 80601	Lakewood Lab 12860 W. Ceda	Lakewood CO 80228 Phone: 303.659-2313	Fax: 303-659-2315	<u>www.coloradolab.com</u>			(ələri	DA 524 (C	'VANS											No	3.3 °C/le V	+	
<u>ୁ</u> ଅଠ		Brie	24U Brig	<u>Lak</u> 128(Lak Pho	Гах	MM			ircle)	DOC (C	, JOT											j J	Clie	By:	
710									6	Xə	bal .gas.	V'או¥										×	sent	Ŋ	ived	
							34		lysi		ຣວງເມຍ	Inorg									Х		s Pre	_w_	Received By:	
			Τ			}			k an		эр	nouli										X	Sea	E C		-
			9	CRESCENT	B				chec		9	ointiN						•				Х		Ļ		
				J.	Zip 4			X	jes (IsuiN										X		baroe	Date/Time:	
	matio	Ţ		J	9		k N	2	haily		Copper													C/S Charge []	Date	
<u>e</u>	Logu I	H H		2	State Co Zlp & Of 03	3	Yes	Ye.	er Ai		SCAAH															
page lot 2	State Form / Project Information	00	System Name:	Address: 20 BounDerR		10	Compliance Samples: Yes 🙀 No 🗖	Send Forms to State: Yes 🗆 No 🙀	[1, V Drinking Water Analyses (check analysis)		SMHTT													х V		
B		S S	별성	3	500	17	c Sar	15 to 1	jng		Diquat									X				d d	ž	
-	For		N H		(Thy Colors	ly:	plian	Fora	rink		shtobn3			×	<u> </u>						_			Ľ	Relinquished By:	
	State	PWS	Syste A	<u>1</u>	City	Court	Com	Send		I	jyphosat													d Via	Iduis	
dy				5	i ·				1, El ,		Smethan							\downarrow	\downarrow		_		C/S Info:	Delivered VIa:Fed EX	Relir	
in of Custody	<u></u>		\downarrow	K.	N		. Com		PHASE		COC2-Fo				X			_	_	_	_		-	ة ج		e
ç	Toda	~	Ŵ	RE	SQ CQ				HH	sar	Herbicia									_	-	_	~	ES 2		2
	10m n	WATER	NORLEY	J	29 12	Fax:	200			L	IOd/sisa		×						\downarrow		\dashv	_	Thelwded	τş	me:	IJ
Cha	crent	AL	M	E.	Ŝ		2			L	EDB\DI							-+	+	-		_	15	Not Series	Ite/T	12
ter	r din		5	4	State		38				motiloD		\vdash			Ň		\rightarrow				_	ž,	Άž	å	ŝ
Wai	tion (SR.	日	BOULDER CRESCENT	39		ञ				nO səlqma							+	-+	\dashv	+	-	3	22		00
Drinking Water Chai	Bill To Information (If different from report to)	Company Name:	Contact Name: JTM	1 1	COLORADOU CILY SPADULS State Cozin 80905		Emelli jmortey 3870(200)				inal Chlorii ()	ງ/ສືເມ)											preservative was	Please preserve Diguot		117 32m 52050 Mulbon 3/2417 1010
ink	0 Inf	pany	act N	6	201		7				Containe				ろ			3	\exists	-	\rightarrow	-	Y	5.5	iy.	Ę
D		Com	Cont	Address: 20		Phone:	Emal	PO Na.:										1.1	2			7	F	JOJ	ved	N.
	-	र्भु										o											rva.	50	Recei	20
		n la		3	M		J	Schwenke				Cod			8:05				ļ	trouded in Sugar			3	A° Ç	-	
		S A			5		Q	Er-				/EP			\$				f	신			č	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	ĺ	2
		J.	كالحال		2155		-01-1	NV.				<u>0</u>								1				۽ <u>ڳ</u> ۽	Date/Time:	
		- Phi		S-Par		de la	35	ليح				ampl	-	Ĩ	#3	+	12	94	せっ	18	5	24	3	12.00	Ę	3-23
		5	Z	PhilesPericture	scale Scy 80903	73	R	ja l				Client Sample ID / EP Code	*	44	#	+++	-	4	**	귀	40	4	Hosetl	170	Å	à
	tion	凹。	11/an			-76	muster joshindre com	X				Ciệ						٤					0	E		1
	orma	실				ų.	3	<u>ت</u> ارک	No.	107		ar	7:55	T2:T	W.	8.11	71.52	1:32m	52	X	5	8	<u>ل</u> ۲	JE	éd By:)
	To Int	ly Nal	Nam	5	S	5	٤	Nam	CAL Task No.	170324007	ARF	Time		ĥ	ł,	30	Ē	H	1.53	1:58	1:59	8.00	tion	¥Š	phie	Þ
	Report To Information	Company Name: J DS-H-dro Caroli Harits	Contact Name:	Addressid 6	Þ	Phone: 119-207-007	Email:	Sampler Name: Secharite	CAL	170	-	Date	3-23								\mathbf{n}		Instructions: No	with the bothe shipment. Sample #8 an soon	Relinquish	A
	R	ő	ວິ	N I	City	<u>s</u>	5	Sau		Pag	07000		ŝ								\Rightarrow	r	Ins	3	2	:XY
										rag	je 2 of 3	•													7	\sim

														×L.		17												
										Ses			ш	insiU													1	
					100						`		1	Radon	+	\vdash	H	-	×	7	+	+		┢	Ž	No.		ł
					12860 W. Cedar Dr. Suite 100A					Subcontract Analyses	\vdash	8	77 u	uibeA	┢	\vdash	\square		ſ	╞		+	\vdash	╞		Samule Pres. Vec 🗍 No 🗍		
			treet 01		r, S	20	2	E COM		ontr	\vdash	9	77 W	wibeA		$\left \right $			+		╞──	+	\vdash		N S	A	Date/Time:	
<u> </u>	Ľ,		ii S 806	4		N 2	2315	<u>olab.</u>		Subc	\vdash	stad\s	ıdıA	Gross	+	\vdash	H	┼	┢	\uparrow	<u> </u>	+		\vdash	gspa	ale P	Da	
ŭ Ŭ Ŭ		Lab	N S		1 8		629	rado			┢	21	102	れっ		, '	H	+	┢	\vdash	<u> </u>	+			Ê	Sam		
Colorado Analytical		<u>Brighton Lab</u>	240 South Main Street Brighton, CO 80 601	de l'hannala l		Lakewood CU 80228	rnone: 303-659-2315 Fax: 303-659-2315	www.coloradolab.com				(ələriD) bi			F		Η		-	+		+		\vdash	Seals Present Yes 📋 No 🔲 Headspace Yes 🗍			
No F		i i i	4 (5) 1 2 2 1		2860	ake	ax:	WW.			h	sloriO) (Η		+		X		1	\vdash		°C /lee	.i.	
	3	82) ·			-1 - - 1		1, <u>12</u>	2				xəpuj		-	+				+	╞					int Ya	Jo	Received By:	
AC.										ysis)	`		soim	Inorga	+		Η		┼─	$\left \right $		-	┢	\vdash	Pres		eceiv	
	_					~^^		-1	······	anal			әр	Fluori	+			-	-	\vdash	+		╎	┢──	Seals	Tenn	~	
				-	5	10				eck	-			Nitrite	+				+	\vdash	-						1	
2		5		2	3	3	2				·[-		9	Nitrat		-	Н				\vdash	\vdash	-		1	_ agu	lime:	
2 d	1 E	Γ	۶ [5			No	2	lyse	,	er.	ddoj	/peəJ	┥				\vdash	\vdash					{	C/S Charge	Date/Time:	
page 2012	State Form / Project Information	helle in	System Name:	5.	Fruiter Ursent	5-15 21 St. 90 3		Compliance Samples: Yes M No	Send Forms to State: Yes 🗆 No. 🖉	PHASE I, II, V Drinking Water Analyses (check analysis)	\vdash	sçı	₩¥	222.2	\vdash	-				-		-	-	┝		5		
ર્દ્ર		ī ī	5	δ	3	Ĵ	5 D.		te: Y	ater	┢	۶MI	HLL	224.2	-				\vdash			-	 	-				
6-	Proje	6) :: ()	zh	K			Samo	lo Sta	N N		tet	upiŒ	2.942.2									\vdash					
		Pwsin-C		Address:	2	S		j j	orms	akin		lladto	Dua	1.842			-		+	\vdash		-	\vdash		1		d By	
	ate E	UiSA	٦ پ	۶ B	0			ilama ilama	nd F	IQ		osate	ιλbμ	D L#S					╞	-						Viai:	ishe	
	S	ă	Ś	×	1	3					F	sətsmad	the D	1.152	1			+				X			:oju	ered 1	Relinquished By:	
iin of Custody		1	1	-	म	10		3870(202)		E I,	\vdash	js-Pest	DOS	2.252			+	+	-	-	-				C/S Info:	Delivered Via:	ž	
Cust	(Q)	1	t	7	レスシート	Zin 2192		0		TAS	7	Q1 [6-14-3	\square			+-						X	-			
of (from report to)	Parer .	3		3	R		g				sebioid						\uparrow										
ain	L from	8	montery		5	Zio		0				PCBs	/SISƏ	I \$0\$			┫	-					X				rime:	
C	fferen	3	≥∣	17	č T	9		5		·	-	B/DBCE	EDI	1.402			1	×									Date/T	
Drinking Water Cha	Bill To Information (If different	K	3		R	Stat					V	\9 mot	iloD	IstoT			Ť						- 1					_
Ň	ation	<u> </u>	Contact Name: Jim	N				Email: 1 Mor / Eu	۳ 	.	1	vinO a:	əlqma	S A\9			1											
cing	form	Company Name:	Valle	10		Cirl J. Sar	T	Ê				aninolia	() ()	Resid L\2m							-	4	- 22	•				
rinl	Tol	npan	tact [Address:	1	2	} :	ul: \	? :: §			zranisi	Ino Di	No. 0	_	X	त	3	α	3	3	-24	\mathcal{M}	$\overline{\mathbf{v}}$			By:	
Q	· · ·		C	Vdd		C		Emi			-						┦			5		-	- 54	4			Received By:	
		Str	1					Ę	Z					qe						Nak				ł			Reci	
		417				M	[J.	X					ů						Dicker								4
		3		A		ふ	ļ	100	Ę					0 / EI						5								11. 50an
		්	Volle	2	۲. ۲	3		Ž	\mathcal{A}					le ID			L		ι.	5		30		d				
		-	3	10		ZIP		J.	NK.					amp		d	\mathbb{T}	オン	M.	1	1	4	5	すし			Date/Time:	5-15
		E	الد	1.6	Suit 200	Statle Zip 80903	ងុ	0	phane Schwenke		}			Client Sample ID / EP Code	117	#	4	せ	#	#	#		Ŧ	#				
	tion	ä	Merk	D.V.C. Dan A.L.	50	Sta	37	الح	X					อี	T												0	4
	orma	۲. از ۲		N	1		6200-LEE-PIL	mvolle@jdshydre, com	ار .ل ان	o	Ŀ			a	5	6 : 00 m		2	x	3	ର	500	স	39	14	-		4
	ro Ini	iy Nai	Name	17	3	S	1/9	<u> </u> Σ	Nam.	ask N	2400	Ľ	AX4	Time	(5:5	7. 19		Side	8:2	が、か	ŝ	ž	3	Pe:8	tions		ished	Tran/
	Report To Information	Company Name: JUD-Hydre Censul Harts	Contact Name:	Address:15	Š.		Phone:		Sampler Name:	CAL Task No.	170324007	Ĩ	<	g	S		-		_	\mathbf{T}					Instructions:		Relinquished By	
	R	ບິ	ಲಿ	PA	 	City	ł	8	Sar	U S	,	Daws	2-1-	Date	333				1	\square			7		Ins		1	か
												Page	J 0)	ι UI													V	-)

Colorado Doperarent of Poplic Fealth and Environment		Org	Organic Chemicals Certified Laboratory R WQCD - Drinking Water CAS Submit Online at http://www.wqcdcomplian	Organic Chemicals Certified Laboratory Report Form WQCD - Drinking Water CAS ubmit Online at http://www.wqcdcompliance.com/login	e ë		Revise VOC	Revised 4/13/2015 VOC/SOC
Ser	ction I (Supply	Section I (Supplied or Completed by Public Water System)	c Water System)	Section J1 (Sum	Section J1 (Sumplied or Completed by Certified Laboratory)	by Certified L	aboratory)	
PWSID#: C00121724	1	A TT ALCO SYSTEM LIMULING		Laboratory ID: CO 00063	CETTURED LADOFATORY INTORMATION	Information		
System Name: S	Sterling Ranch MD	MD		Laboratory Name: Colorado /	Colorado Analytical Laboratory	LT.		
Contact Person: Mark Volle	Mark Volle		Phone #: 719-227-0072	Contact Person: Customer Service		Phone: 303-659-2313	-2313	
Comments:			Do Samples Need to be Composited BY THE LAB?	Comments:				
PWSID#: CO0121724	724		Section V (Supplied or Compl	(Supplied or Completed by Public Water System)				
Sample Date: 3/23/17	717	Collector: Stephanie Schwenk Facil	hwenk Facility ID (On Schedule):	New Well Sample	Sample Pt ID (On Schedule):	: New Well	0	
		Section VI Sy	inthetic Organic Chemicals (Sur	leted by C	I Laboratory)			
Lab Receipt Date	Lab Analysis Date	Lab Sample ID	Analyte Name	CAS No	Analytical Method	MCL (us/L)	Lab MRL (us/L)	Result (uo/1.)
3/24/17	4/3/17	170324007-01E	Dibromochloropropane	96-12-8	EPA 504.1	0.2	0.02	BDL
3/24/17	3/29/17	170324007-01G	2,4D	94-75-7	EPA 515.4	70	0.1	BDL
3/24/17	3/29/17	170324007-01G	2,4,5-TP	93-72-1	EPA 515.4	50	0.2	BDL
3/24/17	3/31/17	170324007-011	Alachlor	15972-60-8	EPA 525.2	2	0.2	BDL
3/24/17	3/31/17	170324007-01J	Aldicarb	116-06-3	EPA 531.1	N/A	0.6	BDL
3/24/17	3/31/17	170324007-01J	Aldicarb sulfone	1646-88-4	EPA 531.1	N/A	1	BDL
3/24/17	3/31/17	170324007-01J	Aldicarb sulfoxide	1646-87-3	EPA 531.1	N/A	0.7	BDL
3/24/17	3/31/17	170324007-011	Atrazine	1912-24-9	EPA 525.2	3	0.1	BDL
3/24/17	3/31/17	170324007-011	Benzo(a)pyrene	50-32-8	EPA 525.2	0.2	0.02	BDL
3/24/17	3/31/17	170324007-011	Carbofuran	1563-66-2	EPA 531.1	40	6.0	BDL
11/4/15	3/30/17	170324007-01F	Chlordanc	57-74-9	FPA 505	7	0.2	BDL
11/1-7/5	11/67/5	11/032400/-011	Dalapon	75-99-0	EPA 515.4	200	-	BDL
111-710	11/12/2	170324007-011	Dil 2-cuny incxy i batic	103-23-1	EPA 525.2	400	9.6	BDL
211-210	11/10/2	11/02/400/-010	LJN(2-ctrtyIncxyI)prtnalate	117-81-7	EPA 525.2	9	0.6	BDI,
11/47/2	11/67/6	010-/0020001	Diposch	85-85-7	EPA 515.4	7	0.2	BDL
114710	3/24/17	710-/0072001	Diquat	85-00-7	EPA 549.2	20	0.4	BDL
3/24/1/	3/29/17	170324007-01K	Endothall	145-73-3	EPA 548,1	100	6	BDL
11/47/2	3/30/1/	1/032400/-015	Endrin	72-20-8	EPA 505	2	0.01	BDL
3/24/17	4/3/17	170324007-01E	Ethylene dibromide	106-93-4	EPA 504.1	0.05	0.01	BDL
3/24/1/	3/31/17	170324007-011	Heptachlor	76-44-8	EPA 525.2	0.4	0.04	BDL
3/24/1/	3/30/17	170324007-01F	Hentachlor epoxide	1024-57-3	HPA 505	0.2	0.02	BDL
NT: Not Tested ug/L:	Micrograms per l	Liter MCL: Maximum Contamir	nant Level BDL Below Laboratory MI	NT: Not Tested ug/L: Micrograms per Liter MCL: Maximum Contaminant Level BDL Below Laboratory MRL A less than sign (<) may also be used	xt.		170324007-01	N 1/2 4/21/17

Page 1 of 4

PWSID#: CO0121724	21724		Section V (Supplied or Completed	(Supplied or Completed by Public Water System)				
Sample Date: 3/23/17	23/17	Collector: Stephanie S	Stephanie Schwenk Facility ID (On Schedule):	New Well Sample	Sample Pt ID (On Schedule):	New Well		
		Section VI 5	Section VI Synthetic Organic Chemicals (Supplied or Completed by Certified Laboratory)	d or Completed by Certified	Laboratory)			
Lab Receipt	Lab Analysis	Lab Sample ID	Analyte Name	CAS No	Analytical	MCL	Lab MRL	Result
LUate	Date				Method	("I/an)	(ng/L)	(/T/20)
3/24/17	3/30/17	170324007-01F	Hexachlorobenzene	118-74-1	EPA 505	1	0.1	RDI
3/24/17	3/30/17	170324007-01F	Hexachlorocyclopentadiene	77-47-4	EPA 505	50	6	BUL
3/24/17	3/30/17	170324007-01F	Lindane	58-89-9	EPA 505	0.2	2010	BDL
3/24/17	3/30/17	170324007-01F	Methoxychlor	72-43-5	EPA 505	40	10	IUN
3/24/17	3/31/17	170324007-01J	Oxamyl	23135-22-0	EPA 531.1	200	-	BUI
3/24/17	3/29/17	170324007-01G	Pentachlorophenol	87-86-5	EPA 515.4	-	104	IUI
3/24/17	3/29/17	170324007-01G	Picloram	1918-02-1	EPA 515.4	500	10	IUI
3/24/17	3/30/17	170324007-01F	Polychlorinated biphenyl's	1336-36-3	EPA 505	0.5	0.1	RNL
3/24/17	3/31/17	170324007-011	Simazine	122-34-9	EPA 525.2	4	0.07	RDI.
3/24/17	3/30/17	170324007-01F	Toxaphene	8001-35-2	EPA 505	3	-	BDL

NT: Not Tested ug/L: Micrograms per Liter MCL: Maximum Contaminant Level BDL Below Laboratory MRL A less than sign (<) may also be used.

170324007-01 N 2/2 4/21/17

Page 2 of 4

									V ar	6			-	-11								1	1					
					•					yses			un	ui ne tU												Г		
					12860 W. Cedar Dr. Suite 100A Lakewood CO 80228					Subcontract Analyses			1	Radon	1			1				\vdash	\square		Seals Present Yes 🗖 No 🚺 Headspace Yes 🚺 No 🕅		Date/Time:	Ì
			*		Suite			ci		ract			877 W	wibsA						×						للر ا	ime:	
		;	Stree 501		Dr, 5	EIE EIE	10			cont			977 W	nibeA						X					BCC V			
<u> </u>		ص		ą	dar O Si	50-7	-231	lolat		Sub		st5E/	siqlA	Gross					×						cadsp		Ő	
ŎĘ		er :	≅ŭ ≞≓	od L	Ce / Ce	101	-623	orac				70	5-5	sen)	'						×				E.			
Colorodo Anolytical		Brighton Lab	240 South Main Street Brighton, CO 80601	Lakewood Lab	12860 W. Cedar Dr. 1 Latewood CO 80228	Phone: 303-659-2313	Fax: 303-659-2315	www.coloradolab.com			(əlmiD)	M 254	አለሀሪ											°N	3.3 minut	+	
<u>ର</u> ମ୍ଚ 🖁			Bris Bris	Lak	128(1.ak	Pho	Нах	LWW			(2			,20T											Ķ.		BÅ.	
70										1	L	хэри		AIK./L										×	sent	Ŋ	Received By:	
C -								-		alysi	_		soin	egion]									X		La la	3	Rec	
			1			19				kan				nouli										X	Sea	W/		_
			4		Ş	5				chec	L			Nitrite						•				X		Ļ] ä	
				H		Zap			À	() 88				usrtiV			<u> </u>							X	1	, and	Date/Time:	
lot 2	State Form / Project Information	10		diffes:	5	State CO Zip 80903		Compliance Samples: Yes 🗗 No 🗖	Send Forms to State: Yes D No K	Drinking Water Analyses (check analysis))\bsə.1		L	_									L'unit ac	Dat	
<u>e</u>	Infor	POLICIO OD SUSA		Ž o		State	County: El Pase	: Ycs	Xes	erA				252.2		<u> </u>	<u> </u>											-
page	aject	000	2	22			2	mples	States	Wat				2.4.2	\downarrow		<u> </u>									× V		
ba	E/P	9				04	Ū	ce Sa	ins to	ding	<u> </u>			249.2								X				54	B B	
r	e For	Ci	System Name:	Address		(Thy COLORS	nty:	nsilqi	Fort	Ē	L			248°.1 242 G	-											Ľ	Relinquished By:	
	Stat	PW	Syst	130	ļ	City	Cou	Com	Send					1.152	┢	-										Š	sinpa	
dy		1)		į	1				I, II, V				2.252.2	-								<u> </u>		C/S Info:	nelivered vie. Fed Ex	Reli	
usta	(ĝ		+	~ 25 Cre. ~		0		(Jan)		PHASE				254.2	+												й И	e
of C	thoda	ď	NORLEY	q		808				H	\vdash			7.212									 		-	Lev.		2
tin C	from	F	SP I	1	1	Zip •	Fax:	e D					files and the second			-	-					<u> </u>			4 C	\$ 9	imet	扫
Cha	crent	WATTER	Ā	ů		9		4				DBCL			-	\vdash	\vdash								Included	300	Date/Time:	12
ter	if dìfi	S	5			State		33				A mu			+	┢		Ň			-	<u> </u>		_	2	Άł	ä	3
Drinking Water Chain of Custody	Bill To Information (if different from report to)	4)	Contact Name: JTM	BAU ACA	,	COLORADO		Email: inortey 3870(200)				Ouly	səiqmu	s ∧\q											3	Please preserve Diguot as viou receive the shoment		margard 3/2417 1010
ing	lorma	Company Name:_	anie:	í	1	22		Mol) Ist Chi	ໆ/ ສີພ)										~	and	33		3
link	To Ini	pany	net N	Address:		39	ij	-7			┢			10.0V			3			N	3				4	Serpres	By:	3
Ā			Con	Add			Phone:	Ema	PO Na.		\vdash	`			+					-		2)		_	preservative	30	Received By:	50se
		У З		1	A			Ę						e								no HEXON with			No.	Pleas	19	3
		ור		2		3		J	Schwenke					U C C			05								N.	• •		S.
		Na	.1			8090		0	Ê								8					nt estudion			Č Q	5		11:32
		e	كااحم	2	Q	$\widetilde{\infty}$		2	\mathcal{N}					le ID								12			2	۽ چ م	ime:	1
		25		193	22	R	de la	3	للا تاريخ					amp	14	3	3	1	いキ	94	す	8	حر	9#	N N	72	Date/Time:	52-52
		E-	2	Piles Per KP	4	State	8	6	R					Client Sample ID / EP Code		H	#	44	T	4		7	#	7	HaSou	الجرب	â	h
	ntion	9	War		1 21	Sta	-16	Ĕ	X					5						ξ					9	ま		
	form			32	1 1	.^	q	3	V J U	No	707			Time	7:55	7:57	H	8:11	7152	Tistam	7:53	1.58	S	5.03	4	36	éd By:)
	To In	ny Na	(Nam	1.0		S	51	٤	E R	CAL Task No.	170324007		ARF	F		1	Ş,	\$	r	ř	4	-	4	3	tion	≠v	L.	Þ
	Report To Information	Company Name: JDS-H-Caroli Lavis	Contact Name:_	Addressing 6		ð	Phone: 119-337-0079ax	Email: M V> 16 (jashindre Com	Sampler Name: Sechante	CAL	170			Date	3-23										Instructions:	with the bothe shipment.	Relinquish	A
	R	Ŭ	Ŭ	¥		City	Ę	5	ŝ			age	3074		ŝ								7		ã	3	2	A
												-Be																\sim

Colorado Anolytical LABORATORIES, INC.	Brighton Lab 240 South Main Street		Lakewood Lab 12860 W. Cedar Dr. Snite 100A			Fax: 303-659-2315	www.coloradolab.com		k analysis) Subcontract Analyses	((Circle) (Circle) JC /Beta	m n 228 n 228 y phys y								×			Seals Present Yes No C Headspace Yes No C	Temp. °C/Ice Sample Pres. Yes 🗌 No 🗍	Received By: Date/Time:
page 2 of 2 oject Information	Hellei	AW YR	Leer Creen		Statto Ziporto 3	0	Yes 🚺 No 🗆	Kes 🗆 No. 👿	r Analyses (checl	,		c Cobbe	552.2 Lead/ Nitrate Nitrate								_		_	C/S Charge	Date/Time:
Page 20	HELIE 10 CO: UISMA	System name: Ser line Ranch MS	Address: Bruider Crewit		City (S	County: El Paso	Compliance Samples: Yes 🚺 No 🗌	Send Forms to State: Yes No. W	PHASE 1, 11, V Drinking Water Analyses (check analysis)		ihall tt	onqvi Endor Bique	254°5 248°1 248°1 248°1										ioj	Delivered Via:	Relinquished By:
Drinking Water Chain of Custody Bill To Information (If different from report to)	Company Name: SR Wader	Davied	and der Cresent	AL COAL	Stat DZip 20"103	Fax:	38706021.00	2	PHASE 1, I		s-Pest	ROC	2.25.2 2.15.4 2.15.4 1.502 1.502				*					×	C/S Info:	 Ă	Date/Time: Rel
Drinking Wa			- Address: JU Ba		Ciril Cherter	Phone:	M Email: J Mor / ear	Ke PO No.:			orine Only	səjdure	No. 0 Resid	-	×	5	2	<i>Cb</i> ^{<i>i</i>}	3	0	0	<u>.</u>	-	-	Keceived By:
lon	Company Name: JDS-14 color Consul Hards		E. PikesPeak Ave	10 200 V	Statt UZIP NU IU S	37-00 (at	Email: M Volle Cjdshydro, com	Sampler Name: Kong ng Schusenke PO No.					Client Sample ID / EP Code	#11	61# -		オレ	#15	4 16 (1,4 Dionan	. 1 -	110	Unt A		1	- ZDAn
Report To Information	Company Name: J		540 E.	V		Phone: 1/9-7-00 (3	Email: MVol	Sampler Name:	CAL Task No.	170324007		Jave 4 of	Date	3-23 8,01	6:00		3:26	8:12		2		60.8	Instructions:	 Dalinaniahad D.	A Cherry

			Radion	uclides C	Certified I	aboratory	Radionuclides Certified Laboratory Report Form			Revision	Revision 6/13/2014
				うと		WULU - UTIDIAD WAIGT CAS	CAD			A.	
Colocado Department		43	00 Chei	ry Creek	Drive Sou	uth; Denver	4300 Cherry Creek Drive South; Denver, CO 80246-1530				
of Public Health and Environment		μ.	Fax: (30:	3) 758-13	98; cdphe.	.drinkingwa	(303) 758-1398; cdphe.drinkingwater@state.co.us				
	Section	Section I (Supplied or Completed by Public		Water System)			Section II (Supplied or Completed by Certified Laboratory)	ed or Completed	by Certified I	aboratory)	
	4	Public Water System Information	1				Certified L	Certified Laboratory Information	nation		
PWS ID: C00121724	21724				Lab	Laboratory ID: CO 00008	00008				
System Name:	System Name: Sterling Ranch MD	Ą			Lab	oratory Name:	Laboratory Name: Hazen Research, Inc.				
Contact Person:			Phone #:		C	Contact Person: Jessica Axen	ssica Axen		Phone #: 303-279-4501	279-4501	
Comments:			Do Samp Composi	Do Samples Need to be Composited <u>BY THE LAB?</u>		Comments:					
				lection III (5	Smanlied or ("omnleted hv	Section III (Smalled or Completed by Public Weter Scatem)				
							a monte ve aven e second				
Sample Date: 03/23/2017	03/23/2017	Collector:	Facility	Facility ID (On Schedule):	hedule):	Samp	Sample Pt ID (On Schedule):				
			Section	IV Radionu	iclides (Suppl	lied or Comply	Section IV Radionuclides (Supplied or Completed by Certified Laboratory)	lory)			
Lab Receipt Date	Lab Analysis Date	Lab Sample ID		Analyte ?	Analyte Name (Code)		CAS No.	Analytical Method	MCL	Lab MRL	Result
03/24/2017	04/18/2017	C27017-001	Gross	Alpha Inclu	Gross Alpha Including Uranium (4002)	tm (4002)	12587-46-1	SM 7110 B	N/A.	1.5	0.0(±1.5)
				Combined (Combined Uranium (4006)	06)	7440-61-1	D2907-97	30 ug/L		
03/24/2017	04/07/2017	C27017-001		Radium	Radium -226 (4020)		13982-63-3	SM 7500-Ra B	N/A	0.1	0.4(±0.3)
03/24/2017	03/30/2017	C27017-001		Radium	Radium -228 (4030)		15262-20-1	EPA Ra-05	N/A	0.6	0.2(±0.6)
03/24/2017	04/18/2017	C27017-001		Gross E	Gross Beta (4100)		12587-47-2	SM 7110 B	50 pCi/L*	2.1	0.0(±2.0)
			T.	otal Dissolv	Total Dissolved Solids (1930)	930)		EPA 160.3	N/A		
*The MCL fo	r Gross Beta F	*The MCL for Gross Beta Particle Activity is 4 mrem/year. Since there is no simple conversion between mrem/year and pCi/L EPA considers 50 pCi/L to be the level of concern.	ar. Since l	there is no s	simple conve	ersion betwee	in mrem/year and pCi/L	EPA considers 2	50 pCi/L to b	e the level o	of concern.
			Sei	tion V Calc	Section V Calculated Values	99					
	~	N/A	Gross /	Alpha Exch	Gross Alpha Excluding Uranium (4000)	am (4000)	Calculated Value	alue	15 pCi/L	N/A	
			Combin	led Radium	Combined Radium {-226 & -228} (4010)	28} (4010)	Calculated Value	alue	5 pCi/L	N/A	
IN	NT: Not Tested						ug/L: Micrograms per Liter	15 per Liter			
La	MRL: Labor	Lab MRL: Laboratory Minimum Reporting Level	svel				pCi/L: Picocuries per Liter	s per Liter			

BDL: Below Laboratory MRL. A less than sign (<) may also be used

pUtL: Picocuries per Liter MCL: Maximum Contaminant Level

Drinking	
Water	
Chain	
of	
Custody	

Bill To Information (If different from report to) State Form / Project Company Name: same PWSID: CO01217 Contact Name: System Name: Sterili Address: System Name: Sterili City: State: Zip: City: State: Zip: Phone: Fax: County: El Paso Email: Compliance Samples PO No.: Send Forms to State	Sampler Name:	2	Email: stuartnielson@coloradolab.com	Phone:303-659-2313 Fax:303-659-2315	City: Brighton State: CO Zip: 80601	Address: P.O. Box 507	Contact Name: Stuart Nielson	Company Name: Colorado Analytical Labs	Report To Information
State Form / Project Information PWSID: CO0121724 System Name: Sterling Ranch MD System Address: 20 Boulder Crescent City: Colo Spgs State: CO Zip: 8090 County: El Paso Compliance Samples: Yes X No Send Forms to State: Yes No	PO No.:		Email:	Phone:	State:	Address:	Contact Name:	Company Name: same	Bill To Information (If different from report to)
	Send Forms to State: Yes 🔲 No 🕅		Compliance Samples: Yes 🛛 No 🗌	County: El Paso	City: Colo Spgs State: CO Zip: 80903	System Address: 20 Boulder Crescent	System Name: Sterling Ranch MD	PWSID: C00121724	State Form / Project Information

ILING Colle	Relinquished By:	>	Please print results o						3/23/17 08:03	Date Time	ARF	170324007	CAL Task No.
1150	Daye/Timf: Re		Please print results on Colorado State form but do not submit to CDPHE. Thank you.						170324007 Sterling Ranch MD	Client Sample ID / EP Code			
	Received By:		submit i			 	 	 	6	No. c	f Containers		
	<u>у</u> :		** Combined Radium -226 & -228. abmit to CDPHE. Thank you.							(mg/l	lual Chlorine L) Samples Only		
			Thar							Tota	l Coliform H	9/A	
			-226 nk yo							504.	I EDB/DBC	P	
	Date/Time:		H -2							505	Pests/PCBs		
	Time:		28.							515.	4 Herbicide	8	PH
	••	<i></i>								524.	2 VOCs		ASE
		Deli	C/S INIO;							525.	2 SOCs-Pes	t	PHASE I, II, V Drinking Wa
	Reli	Delivered Via:	Into:							531.	1 Carbamate	5	S.
	Relinquished By:	Via:								547	Glyphosate		Drie
	shed	-								548.	I Endothall		king
	By:	5								549.	2 Diquat		
										524.	2 TTHMs		ater
		-								552.	2 HAA5s		ter Analyses (check analysis)
	Dat	C/S Charge								Lead	/Copper		lyse
	Date/Time:	harge								Nitra	ite		i (ch
	le:	Ď								Nitri	te		eck
		Temp.	Sea							Fluo	ride		anal
25	12	mp.	IIS PTC							Inor	ganics		ysis)
R	Scj h	°C/Iœ	Seals Present Yes							Alk	Lang. Index	ζ.	
	Received By:	8	3							тос	, DOC (Cin	cie)	
	Ľ	Sam	DN							SUVA	, UV 254 (Circ	:le)	
		ple P											
331		× s	causp						\boxtimes	Gros	s Alpha /Be	ta	Subo
03/24/2017	Da	Sample Pres. Yes 🗋 No 🗆	neauspace res							Radi	um 226		Subcontract Analyses
22	te/Til	N N		ם ב						Radi	um 228		act A
が	Date/Time? /		INOL						\boxtimes	Rado	on .		Inaly
	2		L							Uran	ium		Sea
L	+									L			

Colorado Analytical

<u>Brighton Lab</u> 240 South Main Street Brighton, CO 80601

Lakewood Lab 12860 W. Cedar Dr, Suite 101 Lakewood CO 80228

Phone: 303-659-2313 Fax: 303-659-2315

www.coloradolab.com



Report To: Mark Volle **Company: JDS Hydro Consultants** 545 E. Pikes Peak Ave Suite 300 Colorado Springs CO 80903 **Analytical Results**

TASK NO: 170324007

Bill To: Jim Morley Company: SR Water 20 Boulder Crescent St. Colorado Springs CO 80903

> Facility ID: New Well Sample Point ID: New Well

Task No.: 170324007 **Client PO:** Client Project: Sterling Ranch MD CO0121724

Date Received: 3/24/17 Date Reported: 4/21/17 Matrix: Water - Drinking

Customer Sample ID Sterling Ranch MD Sample Date/Time: 3/23/17

8:03 AM Lab Number: 170324007-01

Test	Result	Method	ML	Date Analyzed	Analyzed By
Chloride	1.3 mg/L	EPA 300.0	0.1 mg/L	3/24/17	LIG
Cyanide-Free	< 0.005 mg/L	EPA 335.4	0.005 mg/L	3/28/17	VDB
E-Coli	< 1 mpn/100ml	Colliert	1 mpn/100ml	3/25/17	VDB
Sulfate	10.7 mg/L	EPA 300.0	0.1 mg/L	. 3/24/17	LJG
Total Coliform	68 mpn/100ml	Colifert	1 mpn/100ml	3/25/17	VDB
Total Organic Carbon	< 0.5 mg/L	SM 5310-C	0.5 mg/L	. 3/28/17	ISG
Turbidity	1.08 NTU	SM 2130-B	0.01 NTU	3/24/17	MBN
<u>Total</u>					
Aluminum	0.032 mg/L	EPA 200.8	0.001 mg/L	. 3/29/17	TCD
Calcium	1.0 mg/L	EPA 200.7	0.1 mg/L	. 3/29/17	MBN
Copper	< 0.0008 mg/L	EPA 200.8	0.0008 mg/L	3/29/17	TCD
iron	0.180 mg/L	EPA 200.7	0.005 mg/L	3/30/17	MBN
Lead	0.0002 mg/L	EPA 200.8	0.0001 mg/L	3/29/17	TCD
Magnesium	0.06 mg/L	EPA 200.7	0.02 mg/L	3/29/17	MBN
Manganese	0.0071 mg/L	EPA 200.8	0.0008 mg/L	3/29/17	TCD
Potassium	1.0 mg/L	EPA 200.7	0.1 mg/L	3/29/17	MBN
Silver	< 0.0001 mg/L	EPA 200.8	0.0001 mg/L	3/29/17	TCD
Strontium	0.009 mg/L	EPA 200.8	0.005 mg/L	3/29/17	TCD
Total Hardness	2.7 mg/L as CaCO3	SM 2340-B	0.1 mg/L as CaCO3	3/30/17	MBN
Uranium	< 0.0002 mg/L	EPA 200.8	0.0002 mg/L	3/29/17	TCD
Zinc	0.002 mg/L	EPA 200.8	0.001 mg/L	3/29/17	TCD

Abbreviations/ References:

ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Microgrems Per Liter or PPB mpn/100 m/s = Most Probable Number Index/ 100 m/s Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

240 South Main Street / Brighton, CO 80601-0507 / 303-659-2313 Mailing Address: P.O. Box 507 / Brighton, CO 80601-0507 / Fax: 303-659-2315 Page 1 of 4



Report To: Mark Volle Company: JDS Hydro Consultants 545 E. Pikes Peak Ave Suite 300 Colorado Springs CO 80903

Analytical Results

TASK NO: 170324007

Bill To: Jim Morley Company: SR Water 20 Boulder Crescent St. Colorado Springs CO 80903

Task No.: 170324007 Client PO: Client Project: Sterling Ran	ch MD CO0121724		Received: 3/24/1 Reported: 4/21/1 Matrix: Water	7	
Customer Sample ID Sterli Sample Date/Time: 3/23/ Lab Number: 17032			Facility Sample Point	ID: New Well ID: New Well	
est	Result	Method	ML	Date Analyzed	Analyzed By
<u>otal</u> Zinc	0.002 mg/L	EPA 200.8	0.001 mg	/L 3/29/17	TCD

Abbreviations/ References:

ML = Minimum Level = LRL = RL mg/L = Milligrams Per Liter or PPM ug/L = Micrograms Per Liter or PPB mpr/100 mis = Most Probable Number Index/ 100 mis Date Analyzed = Date Test Completed

DATA APPROVED FOR RELEASE BY

240 South Main Street / Brighton, CO 80601-0507 / 303-659-2313 Mailing Address: P.O. Box 507 / Brighton, CO 80601-0507 / Fax: 303-659-2315 Page 2 of 4

170324007 2/2

							×	V #*					26.1	1	1	1	r			4							_
				V					Subcontract Analyses				insiU								<u> </u>			B	Ę		
				te 10					t Ans				Nedo:	-										Ž			
			eet	<u>Lakewood Lab</u> 12860 W. Cedar Dr. Suite 100A	20	•			itrac				uibeA						×					Seals Present Yes 🗆 No 🗸 Headspace Yes 🖸 No 🕅	2	Date/Time:	
		i	1090 0601	, Dr.	9022	115	b.co		ibcor				Radiu	<u> </u>		-			X					apace	Pres	Date	
<u>80</u>		괾		edan edan	õ	-62A	<u>dola</u>		ŝ		pla/Bet						<u> </u>	×						Head	a m ché		-
Colorado		Brighton Lab	240 South Main Street Brighton, CO 80601	Lakewood Lab 12860 W. Ceda	Lakewood CO 80228	Phone: 303-659-2315 Fax: 303-659-2315	www.coloradolab.com			<u> </u>	205			-					-	×					-		
		मुब	u So ight	860 Y	kew	one: x 30	VW.C				254 (Circ					ļ								Ž	3.3 °C lies V		
O de s	5	B		12	Ľ		MM				ериі . 			┞										t Yes	0.0	Received By:	
									sts)	<u> </u>			gnonl 	-						_			\geq	LCBCM	M	ceive	
6							<u></u>		naly	<u> </u>				-	<u> </u>							X		e la la	(N)	Be	
				16		2			ck a	<u> </u>		_	Fluor	-	-		-						-	Й		4	
			stem Name:	CRESCENT	· V				Drinking Water Analyses (check analysis)	┣—			Nitrie Nitrie	-		-	ŀ						X		C/S Charae [1]	me:	Ì
N	E.		1 3	Ne.s.		Ì	2		yses	-	ber.		/beə.l			╞							X		Char	Date/Time:	
page lot 2	State Form / Project Information	10		i 1		3	Compliance Samples: Yes 🙀 No 🗌	Send Forms to State: Yes 🗆 No 🙀	Anal				2255	-		-									S	Da	
<u>ت</u>	it Info	ENC		2			s: Ye	e: Ye	ter	┣──			2.4.22	-											×		
ناق	20	Ō	System Name:	Address: 20 BOULDER		PAC-		Stat	N N B	<u> </u>			2.642	\vdash		-									Ý		ł
A		00	A 1	S.	0,07) Sol	rms to	iking	\vdash	lishtob				X			\square			~	_			b D	By:	
	19 2	in the second seco	E C		8		aild m	Id Fo	Dri		posate			-					-	_	_				بلا	ished	
	S	Å	ŝ	Scd			ද ද	Se	1, II, V	55	ternech				-									ij	red V	Relinquished By:	
n of Custody		1	ł	BOULDER CRESCENT			ε				Cs-Pes	OS a	2.252			\mathbf{X}						_		C/S Info:	Delivered Via: Fed EX	Re	
Cust	19		+	3	CONNADO	2	Email: inortey 3870(200) .com		PHASE		s)(OA	254"5														
of C	Epol	ď	NORLEY	3	0 ×		0		1	s	picide	He	515.4	X								_		7	Į		5
ain	Fom	E	OP		1		6				² \bCB ²	Pest	SOS											PP -	59	Lime	F
<u>G</u>	fferen	WATER	Ì	g		3	5			ď	B\DBC	ED	204"											theluded	300	Date/Time:	4
ater	(if di	K	£	TT			3			V/c	l moli	lo D	listo T				Ň							E	A₹		
Drinking Water Chai	Bill To laformation (if different from report to)	Company Name: <u>SR</u>	Contact Name: 375M	8	8	5	بع ا				les Only	dure	S ¥/d											Son	Please preserve Diquet as you receive the Shoment,	IF 3. Corro A iblo 212411 101-	ð Y
king	form	y Nan	Nambe	3	TY Y		e e				eninold.		Kesid I/gm)								-		-	3	33	21 4	{
rinl	Tola	apan	Itect]	Address:	ð	Phone:	ij	PO No.:			zrənista	ოეკ	0.0N	-	-	С	-	ノ	3	3	_			Y	الم م	By: By:	3
Q			ů.	P V						<u> </u>												\neg	—	preservative	ふう	Received By:	4
		7	1				Ę	Schwenke					ę			١.					no reversion on the			3	J.S	ž V	
		1 I T K		2	1 A		J	Ŷ					С С			8:05					ni espuent			S,	-	į	र्र
		, Ya		N	JE	5	19	Ę.					0/E			ŝ					1			ð	5.8	1 1 1	T
		e	2101	3			J.	1					ole II					. ~		~	N			D.F.	કુકુ	lime:	
		PT-	I	PhiesPerit Ave	and the KNANZ	10	1	NK VK					Client Sample ID / EP Code		Ũ	4	#4	いま	94	4	100	4 0	24	hoseti	300	Date/Time:	ľ
		J	3		¥ S	18	0	F					lient			-	Ŧ		4		- T	4			- The		2
	lation	H	11 Jar		Juit 6	10	P	Å		ł			<u>ਹ</u>						<u></u>	_	\square			Ŷ	to o		
	uform	ame: .	_		1	19	3		k No.	1007			Time	7:53	13:1	뾠	8:1)	7152	1:30m	133	1:5%	2	5.03		25	d By:	
	t To L	uny Ni	tt Nar	J.H.	C	15	8	IL NA	CAL Task No.	170324007	ARF		H	<u> </u>	1	7 *	8	5	М	5	-	ŕ	2	ction	Fi		R
	Report To Information	Company Name: J DS-H-dro Cerryul Hards	Contact Name:	Address: 45 E.	ą	Phone 219-337-0074	Emili M W /6 joshuda Com	Sampler Name: Secturity					Date	3-23	-									Instructions:	with the bothe shipment.	Relinquibh	ħ
			<u> </u>			<u></u>		60		Pa	age 3 d	of 4		ĝ								7	•	-		" ()	1)

															Y		1	4										
											ses			шт	inerU												Г	
						100					lian				горвЯ				-	×				+	╞	ž	ž	
					;	uite					act A		8	77 W	nibs A								\vdash	\vdash	\vdash			
			reet	2	l	r, Si 28		2	com		ontri	\vdash	9		Radiu	+		╞┼┨	+		-			-	\vdash	х З	>	Date/Time:
07 s	į		240 South Main Street Brinkton CO 90601	NA0	ا م	12860 W. Cedar Dr, Suite 100A Lakewood CO 80228	Phone: 303.650.0313	Fax: 303-659-2315	www.coloradolab.com		Subcontract Analyses	-	a/Beta	ıdıv	Gross	+			┢	+		-			┢	Headspace Yes 🗌	Samnle Pres Ves 🗌 No 🗍	Da
Colorado Anolytical	5	Lab	W S	3	Lakewood Lab			226-2	rado			┢╌	25		1			╞╋	+	\vdash				<u> </u>		Ē	Tel Ser	
		<u>Brighton Lab</u>	outh		vood	Noov	2		coloi				4 (Circle			$rac{1}{2}$	1	H	+	+			-	┞		Seals Present Yes 🗋 No 🗖		
		<u>rich</u>	10 N	20	akev	2860 akev			WW.				(Circle				<u> </u>	┝┤	+	-		X		┢	┢	ģ.	of /Ice	
	1		8 ¤	9					≥ I				xəpul					┤┥	┢	-		P	-			nt Ye	Jo	Received By:
X.											(sis)				igroni	\vdash		$\left \right $	╀	-	-	\vdash	┝	╞	┢	Prese		eceiv
											Inal				Fluor	\vdash			┢	+				┢	-	seals	Temn	ž
					+	1	10				eck :	\vdash			Nitrite			┝╌╋		$\left \right $	_		-	<u> </u>		92		1 1
5		7		Δ	26		ŝ				(ch	\vdash			Nitrat		-	\mathbb{H}	+	\vdash			-	┣─		-	CS Charge	
Let .	tion	-		Z	J		Ž	1	2 2	의 의	lyses	⊢	er		\bea.l	+		$\left \cdot \right $	-	┝			-			-	Cha	Date/Time:
لو	DTIMAL	Ta	8	5	ડ્રે		Statto Zindugu 3	n		Ō	Anal	\vdash			2255		H	$\left \cdot \right $						\vdash	-		CSS	ã
page 2or2	State Form / Project Information	helle in	System Name:	ž	Address: Builder Creent		Sta	Country El Pase	Compliance Samples: Yes 💋 No 🗌	Send Forms to State: Yes No.	I, II, V Drinking Water Analyses (check analysis)	┝			2.4.22			\vdash	-						-			
6	Proje			Y	NÃ			0	ampl	o Stat	N ⁸	⊢			2.942			Η					-	\vdash				
		CI / UNING	١ <u>۽</u>	مر المرز			C	E	nceS	rms to	king	\vdash			1'875					-				╞				By:
	tte Fo			剂.					all all all all all all all all all all	ld Fo	Dric	-			2470	\vdash		\neg		┢─				-			į	ished
	St	nd	Ŝ				C	<u>්</u>	ථ	2	I, V		esterne										X	╞	-	ie	red V	Relinquished By:
Drinking Water Chain of Custody		1			+				5.00		E 1,]		1səd-s	SOC	2.25.2		-	╉	-	-					-	C/S Info:	Delivered Via:	Re
Cust	t to)			2	er Cresent		zip 20703				PHASE	7	6⁄1 <u>F</u>		6-14-1			╉							X			
of C	repor	2	3		ુ		8		3		a l	F	sabioid					╁										
ain	Bill To Information (If different from report to)	Nater-	when		5		Zip	Fax:	10000			╞──	PCBs	Pests/	\$0\$			╉	-		-			X				Date/Time:
Ch	Terent		٤		4		9		3870			6	NDBCI	EDB	1.402			╈	×									ate/
ıter	(if dif	N/	8		R		Stat			2		V	/d uno)	liloD	lato T			╉				-		1				
M	tion	ر ار	Contact Name: Jim		•				1661				ynny z	əlqma	S A\¶			+			-							
ting	form	Nam	(ame:		2		5	「	Ě				annoli		Resid (mg/L								4	×,				
luir	Toln	Company Name:	tact N		Vauress		Clift	ij) 			eranie	Ino.D.1	0 '0N	_	X	9	3	3	2	3		$\tilde{\mathbf{w}}$	3			By:
â	Bill	Con	Con	PPY			City	Phone:	Email: 10001	PO No.:								-			1							Received By:
		¥.													e						NaN NaN							Rece
		417					M		Ĵ	K					ů Ú			Į			Dicken							ž
		3			Ł		S S		C.	P					/ EI						5							:: ()` 304m
	•	J.	olle		F	X	S		乽	N.					le ID			k			5		50		d			ime:
		马	3	1	2	лл Ы	Zip	Ser. 1	rel a	NA NA					amp		6	1	オー	<u>M</u>	7	1	1	#10	Ň			Date/Time: 3-23 (
		H	k		ž	Suite 200	Star CO XID Store 3	성	0	R					Client Sample ID / EP Code	114	#	Ť	4	#	4	#	İ	#	#			· /
	ttion	ä	Merk	1	Pilesterkhy	Ś	Sta	5100-LEG- PIL	الح	X					Ē	T	5	ľ										d
	Corma				S			6	5	/.] <u>ä</u>	ó	2			Time	5	6 : 00 en	·	Side	Ŋ	ないで	র	Ker 8	<u>े</u> श्र	29	10	-	
		iy Nai	Nam		5		S	51	2	Ea.	ask N	170324007	ł	ARF	Ë	5:0	 		Ś	8:0	ŝ	2	Å	3	8:39	tion		quished
	Report To Information	Company Name: JDS-Highe Consul I tants	Contact Name:	dree	542		-	Phone:	Email: M Volle@jdshybre, com	Sampler Name: Kychenke Schusenke	CAL Task No.	1703	,	4	Date	3-23	_	-		_				1	<u> </u>	Instructions:		Belinquished
l	ž	ű	ŭ	V	6		City	Ph	E	Sa	1		Page	4.0	ă	<i>w</i>				1				1		Ĩ		
															-													\sqrt{J}

- XL



ANALYTICAL SUMMARY REPORT

April 06, 2017

Colorado Analytical Laboratories Inc PO Drawer 507 Brighton, CO 80601

Work Order: C17030850 Quote ID: C4542 - 624, 625, 1,4-Dioxane

Project Name: 170324007 Sterling Ranch MD

Energy Laboratories, Inc. Casper WY received the following 1 sample for Colorado Analytical Laboratories Inc on 3/28/2017 for analysis.

Lab ID	Client Sample ID	Collect Date Re	ceive Date	Matrix	Test
C17030850-001	170324007 Sterling Ranch MD	03/23/17 8:03 0	03/28/17	Groundwater	Azeotropic Distilation Separatory Funnel Liquid-Liquid Ext. Semi-Volatile Organic Compounds 624-Purgeable Organics Volatile Compounds by Azeotropic Distillation

The results as reported relate only to the item(s) submitted for testing. The analyses presented in this report were performed at Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the Laboratory Analytical Report, the QA/QC Summary Report, or the Case Narrative.

If you have any questions regarding these test results, please call.

Report Approved By:

Digitally signed by Randy Horton Date: 2017.04.06 16:31:29 -06:00

ENERGY CABODATORIES	Trust our People. Trust our Data. www.energylab.com	Billings, MT 800.735.4489 • Casper, WY 888.235.0515 Gillette, WY 886.686.7175 • Helena, MT 877.472.0711
CLIENT:	Colorado Analytical Laboratories Inc	Report Date: 04/06/17
Project:	170324007 Sterling Ranch MD	Report Date. 04/00/17
Work Order:	C17030850	CASE NARRATIVE

Tests associated with analyst identified as ELI-B were subcontracted to Energy Laboratories, 1120 S. 27th St., Billings, MT, EPA Number MT00005.

.



LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

Client: Project: Lab ID: Client Sample (D:	Colorado Analytical Lab 170324007 Sterling Rar C17030850-001 170324007 Sterling Rar	ich MD	s inc				Collec	Received:	03/23/17 08:03
Analyses		Result	Units	Qualifiers	RL	MCL/ QCL	Method	Analy	/sis Date / By
VOCS BY AZEOTR	OPIC DISTILLATION								
1,4-Dioxane		ND	ug/L		1.0		SW8260	A 04/08	6/17 09:34 / eli-b
 Analysis by direct a quantitate the 1,4-Direct 	queous injection of the sample of exame and account for any variat	istillate. A ions in the	deuterated analysis or	version of 1,4-Dio	xane was	added to th	ie sample pi	ior to distillati	on and used to
VOLATILE ORGAN	IIC COMPOUNDS								
Acetone		ND	ug/L		20		E624	03/31	/17 16:09 / eli-b
Acetonitrile		ND	ug/L		20		E624	03/31	/17 16:09 / eli-b
Acrolein		ND	ug/L		20		E624	03/31	/17 16:09 / eli-b
Acrylonitrile		ND	ug/L		20		E624	03/31	/17 16:09 / ell-b
Benzene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
Bromobenzene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
Bromochioromethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
Fromodichloromethan	e	ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
iromoform		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
romomethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
arbon disulfide		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
arbon tetrachloride		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
hlorobenzene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
hlorodibromomethan	e	ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
hloroethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eil-b
-Chloroethyl vinyl eth	er	ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
chloroform		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
Chloromethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
-Chlorotoluene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
-Chlorotoluene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
2-Dibromoethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
libromomethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / ell-b
2-Dichlorobenzene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
,3-Dichlorobenzene		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
4-Dichlorobenzene		ND	ug/L		1.0		E624	03/31	/17 16:09 / ell-b
ichlorodifiuorom ethal	ne	ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
1-Dichloroethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
2-Dichloroethane		ND	ug/L		1.0		E624	03/31	/17 16:09 / eli-b
1-Dichloroethene			ug/L		1.0		E624	03/31	/17 16:09 / eli-b
s-1,2-Dichioroethene	1		ug/L		1.0		E624	03/31	/17 16:09 / eli-b
ans-1,2-Dichloroethe	ne		ug/L		1.0		E624	03/31	/17 16:09 / eli-b
2-Dichloropropane			ug/L		1.0		E624	03/31	/17 16:09 / eli-b
3-Dichloropropane			ug/L		1.0		E624	03/31	/17 16:09 / eli-b
,2-Dichloropropane			ug/L		1.0		E624	03/31	/17 16:09 / ell-b
1-Dichloropropene			ug/L		1.0		E624	03/31	/17 16:09 / eli-b
is-1,3-Dichloroproper	6	ND			1.0		E624		/17 16:09 / eli-b
ans-1,3-Dichioroprop			ug/L		1.0		E624		/17 16:09 / eli-b
thylbenzene		ND	-		1.0		E624		/17 16:09 / ell-b

Report Definitions:

RL - Analyte reporting limit. QCL - Quality control limit. MCL - Maximum contaminant level.



LABORATORY ANALYTICAL REPORT Prepared by Casper, WY Branch

Client:Colorado Analytical Laboratories IncProject:170324007 Sterling Ranch MDLab ID:C17030850-001Client Sample ID:170324007 Sterling Ranch MD

Report Date: 04/06/17 Collection Date: 03/23/17 08:03 DateReceived: 03/28/17 Matrix: Groundwater

Analyses Result Units Qualifiers RL QCL Method Analysis Date / i VOLATILE ORGANIC COMPOUNDS Methyl tert-butyi ether (MTBE) ND ug/L 2.0 E624 03/31/17 16:09 / Methyl tert-butyi ether (MTBE) ND ug/L 20 E624 03/31/17 16:09 / Methyl tert-butyi ether (MTBE) ND ug/L 10 E624 03/31/17 16:09 / Methyl tert-butyi ketone ND ug/L 10 E624 03/31/17 16:09 / Methyl isobutyi ketone ND ug/L 10 E624 03/31/17 16:09 / Methylene chloride ND ug/L 0.50 E624 03/31/17 16:09 / Naphthalene ND ug/L 1.0 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 /	20
Methyl tert-butyl ether (MTBE) ND ug/L 2.0 E624 03/31/17 16:09 / Methyl ethyl ketone ND ug/L 20 E624 03/31/17 16:09 / Methyl isobutyl ketone ND ug/L 10 E624 03/31/17 16:09 / Methyl isobutyl ketone ND ug/L 10 E624 03/31/17 16:09 / Methyl isobutyl ketone ND ug/L 10 E624 03/31/17 16:09 / Methylene chloride ND ug/L 1.0 E624 03/31/17 16:09 / Naphthalene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0	28
Methyl ethyl ketone ND ug/L 20 E624 03/31/17 16:09 / Methyl isobutyl ketone ND ug/L 10 E624 03/31/17 16:09 / Methyl isobutyl ketone ND ug/L 10 E624 03/31/17 16:09 / Methyl ene chloride ND ug/L 1.0 E624 03/31/17 16:09 / Naphthalene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / Tetrachloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / <t< td=""><td></td></t<>	
Methyl isobutyl ketone ND ug/L 10 E624 03/31/17 16:09 / Methylene chloride ND ug/L 1.0 E624 03/31/17 16:09 / Naphthalene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / Tetrachloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Methylene chloride ND ug/L 1.0 E624 03/31/17 16:09 / Naphthalene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / Tetrachloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Toluene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03	eli-b
Naphthalene ND ug/L 0.50 E624 03/31/17 16:09 / Styrene ND ug/L 1.0 E624 03/31/17 16:09 / Tetrachloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Toluene ND ug/L 1.0 E624 03/31/17 16:09 / Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Styrene ND ug/L 1.0 E624 03/31/17 16:09 / Tetrachloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Toluene ND ug/L 1.0 E624 03/31/17 16:09 / Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624<	eli-b
Tetrachloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Toluene ND ug/L 1.0 E624 03/31/17 16:09 / Trichloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0	eli-b
Instruction Instruction	eli-b
1,1,2,2-Tetrachloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Toluene ND ug/L 1.0 E624 03/31/17 16:09 / Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Trichlorofiuoromethane ND ug/L 1.0 E624 03/31/17 16:09 /	ell-b
Toluene ND ug/L 1.0 E624 03/31/17 16:09 / Trichloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Trichlorofiuoromethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Trichloroethene ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Trichlorofiuoromethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
1,1,1-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / 1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Trichlorofiuoromethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
1,1,2-Trichloroethane ND ug/L 1.0 E624 03/31/17 16:09 / Trichlorofluoromethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Trichlorofluoromethane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
	eli-b
4 D D Triphionenene	ell-b
1,2,3-Trichloropropane ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Vinyl Acetate ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Vinyl chloride ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
m+p-Xylenes ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
o-Xylene ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Xylenes, Total ND ug/L 1.0 E624 03/31/17 16:09 /	eli-b
Surr: 1,2-Dichloroethane-d4 105 %REC 71-139 E624 03/31/17 16:09 /	eli-b
Surr: p-Bromofluorobenzene 102 %REC 80-127 E624 03/31/17 16:09 /	∋lí-b
Surr: Toluene-d8 92.0 %REC 80-123 E624 03/31/17 16:09 / 6	ali-b
SEMI-VOLATILE ORGANIC COMPOUNDS	
Acenaphthene ND ug/L 10 E625 03/30/17 17:14 / 0	
Acenaphthylene ND ug/L 10 E625 03/30/17 17:14 / 0	eli-b
Anthracene ND ug/L 10 E625 03/30/17 17:14 / 0	
Azobenzene ND ug/L 10 E625 03/30/17 17:14 / 0	eli-b
Benzidine ND ug/L 10 E625 03/30/17 17:14 / 0	
Benzo(a)anthracene ND ug/L 10 E625 03/30/17 17:14 / 0	eli -b
Benzo(a)pyrene ND ug/L 10 E625 03/30/17 17:14 / 0	eli-b
Benzo(b)fluoranthene ND ug/L 10 E625 03/30/17 17:14 / 6	eli-b
Benzo(g,h,i)perylene ND ug/L 10 E625 03/30/17 17:14 / 6	elí-b
Benzo(k)fluoranthene ND ug/L 10 E625 03/30/17 17:14 / 6	eli -b
4-Bromophenyl phenyl ether ND ug/L 10 E625 03/30/17 17:14 / 6	eli -b
Butylbenzylphthalate ND ug/L 10 E625 03/30/17 17:14 / 6	
4-Chloro-3-methyiphenoi ND ug/L 10 E625 03/30/17 17:14 / e	eli-b
bis(-2-chloroethoxy)Methane ND ug/L 10 E625 03/30/17 17:14 / 6	li-b
bis(-2-chloroethyl)Ether ND ug/L 10 E625 03/30/17 17:14 / e	li-b
bis(2-chloroisopropyl)Ether ND ug/L 10 E625 03/30/17 17:14 / 6	li-b
2-Chloronaphthalene ND ug/L 10 E625 03/30/17 17:14 / e	d b
2-Chlorophenol ND ug/L 10 E625 03/30/17 17:14 / e	-u-D

Report Definitions: RL - Analyte reporting limit. QCL - Quality control limit. MCL - Maximum contaminant level.



LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

Client:	Colorado Analytical Laboratories Inc
Project:	170324007 Sterling Ranch MD
Lab ID:	C17030850-001
Client Sample ID:	170324007 Sterling Ranch MD

Report Date: 04/06/17 Collection Date: 03/23/17 08:03 DateReceived: 03/28/17 Matrix: Groundwater

					MCL/	
Analyses	Result	Units	Qualifiers	RL	QCL Method	Analysis Date / By
SEMI-VOLATILE ORGANIC COMPOUNDS	,					
4-Chlorophenyl phenyl ether	ND	ug/L		10	E625	03/30/17 17:14 / ell-b
Chrysene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Diethyl phthalate	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Di-n-butyi phthalate	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
1.2-Dichlorobenzene	ND			10	E625	03/30/17 17:14 / ell-b
1,3-Dichlorobenzene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
1,4-Dichlorobenzene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
3.3'-Dichlorobenzidine	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
		_		10	E625	03/30/17 17:14 / eli-b
2,4-Dichlorophenol	ND	ug/L				
Dimethyl phthaiate	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Di-n-octyl phthalate	ND	ug/L		10	E625	03/30/17 17:14 / ell-b
Dibenzo(a,h)anthracene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
2,4-Dimethylphenol	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
4,6-Dinitro-2-methylphenol	ND	ug/L		50	E625	03/30/17 17:14 / eli-b
2,4-Dinitrophenol	ND	ug/L		50	E625	03/30/17 17:14 / ell-b
2,4-Dinitrotoluene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
2,6-Dinitrotoluene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
bis(2-ethylhexyl)Phthalate	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Fluoranthene	ND	ug/L		10	E625	03/30/17 17:14 / ell-b
Fluorene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Hexachlorobenzene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Hexachlorobutadiene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Hexachlorocyclopentadiene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Hexachloroethane	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Indeno(1,2,3-cd)pyrene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Isophorone	ND	ug/L		10	E625	03/30/17 17:14 / ell-b
n-Nitrosodimethylamine	ND	ug/L		10	E625	03/30/17 17:14 / ell-b
n-Nitroso-di-n-propylamine	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
n-Nitrosodiphenylamine	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
2-Nitrophenol	ND	ug/L		10	E625	03/30/17 17:14 / ell-b
4-Nitrophenol	ND	ug/L		50	E625	03/30/17 17:14 / eli-b
	ND	-		10	E625	03/30/17 17:14 / eli-b
Naphthalene		ug/L		10	E625	03/30/17 17:14 / eli-b
Nitrobenzene	ND	ug/L				03/30/17 17:14 / eli-b
Pentachiorophenol	ND	ug/L		50	E625	
Phenanthrene	ND	ug/L		10	E625	03/30/17 17:14 / eli-b
Phenoi		ug/L		10	E625	03/30/17 17:14 / eli-b
Pyrene		ug/L		10	E625	03/30/17 17:14 / eli-b
1,2,4-Trichlorobenzene		ug/L		10	E625	03/30/17 17:14 / eli-b
2,4,6-Trichlorophenol		ug/L		10	E625	03/30/17 17:14 / ell-b
Surr: 2-Fluorobiphenyl		%REC		28-107	E625	03/30/17 17:14 / eli-b
Surr: 2-Fluorophenol		%REC		20-56	E625	03/30/17 17:14 / eli-b
Surr: Nitrobenzene-d5	63.0	%REC		32-94	E625	03/30/17 17:14 / eli-b
Surr: Phenoi-d5	27.0	%REC		1 9-4 5	E625	03/30/17 17:14 / eli-b

Report Definitions: RL - Analyte reporting limit. QCL - Quality control limit. MCL - Maximum contaminant level.



LABORATORY ANALYTICAL REPORT Prepared by Casper, WY Branch

Client:	Colorado Analytical Laboratories Inc
Project:	170324007 Sterling Ranch MD
Lab ID:	C17030850-001
Client Sample ID:	170324007 Sterling Ranch MD

Report Date: 04/06/17 Collection Date: 03/23/17 08:03 DateReceived: 03/28/17 Matrix: Groundwater

Analyses	Result Units	Qualifiers RL	MCL/ QCL Method	Analysis Date / By
SEMI-VOLATILE ORGANIC COMPO	UNDS			
Surr: Terphenyl-d14	70.0 %REC	32-122	E625	03/30/17 17:14 / ell-b
Surr: 2,4,6-Tribromophenol	68.0 %REC	21-130	E625	03/30/17 17:14 / eli-b



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624							Ar	alytical Run	R277281
Lab ID: ccv033117	Continuing Ca	libration Verit	fication Standa	ard				03/31	1/17 08:45
Acetone	58.0	ug/L	20	116	70	130			
Acetonitrile	56.4	ug/L	20	113	70	130			
Acrolein	56.4	ug/L	20	113	70	130			
Acrylonitrile	49.6	ug/L	20	99	70	130			
Benzene	5.08	ug/L	0.50	102	70	130			
Bromobenzene	5.04	ug/L	0.50	101	70	130			
Bromochloromethane	5.36	ug/L	0.50	107	70	130			
Bromodichloromethane	4.92	ug/L	0,50	98	70	130			
Bromoform	5.04	ug/L	0.50	101	70	130			
Bromomethane	4,28	ug/L	0.50	86	70	130			
Carbon disulfide	5.32	ug/L	0.50	106	70	130			
Carbon tetrachloride	5.80	ug/L	0.50	116	70	130			
Chlorobenzene	4.56	ug/L	0.50	91	70	130			
Chlorodibromomethane	5.04	ug/L	0.50	101	70	130			
Chloroethane	4.80	ug/L	0.50	96	70	130			
2-Chloroethyl vinyl ether	2.90	ug/L	1.0	58	70	130			S
Chloroform	5.60	ug/L	0.50	112	70	130			
Chloromethane	3,82	ug/L	0.50	76	70	130			
2-Chlorotoluene	5.00	ug/L	0.50	100	70	130			
4-Chiorotoluene	5.44	ug/L	0.50	109	70	130			
1,2-Dibromoethane	4.68	ug/L	0.50	94	70	130			
Dibromomethane	4.96	ug/L	0.50	99	70	130			
1,2-Dichlorobenzene	5.04	ug/L	0.50	101	70	130			
1,3-Dichlorobenzene	5.16	ug/L	0.50	103	70	130			
1,4-Dichlorobenzene	5.00	ug/L	0.50	100	70	130			
Dichlorodifluoromethane	5,20	ug/L	0.50	104	70	130			
1,1-Dichloroethane	4.96	ug/L	0.50	99	70	130			
1,2-Dichloroethane	6.24	ug/L	0.50	125	70	130			
1,1-Dichloroethene	5.12	ug/L	0.50	102	70	130			
cis-1,2-Dichloroethene	4.76	ug/L	0.50	95	70	130			
trans-1,2-Dichloroethene	5.00	ug/L	0.50	100	70	130			
1,2-Dichloropropane	4.88	ug/L	0.50	98	70	130			
1,3-Dichloropropane	4.88	ug/L	0.50	98	70	130			
2,2-Dichloropropane	5.72	ug/L	0.50	114	70	130			
1,1-Dichloropropene	5.44	ug/L	0.50	109	70	130			
cls-1,3-Dichloropropene	4.80	ug/L	0.50	96	70	130			
trans-1,3-Dichloropropene	4.84	ug/L	0.50	97	70	130			
Ethylbenzene	4.88	ug/L	0.50	98	70	130			
Methyl tert-butyl ether (MTBE)	5.20	ug/L	0.50	104	70	130			
Methyl ethyl ketone	54.0	ug/L	20	108	70	130			
Methyl isobutyl ketone	50.4	ug/L	20	101	70	130			
Methylene chloride	5.88	ug/L	0.50	118	70	130			
Naphthalene	5.08	ug/L	0.50	102	70	130			

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624							Ar	alytical Run:	R277281
Lab ID: ccv033117	Continuing Ca	libration Verif	ication Stands	ard				03/31	/17 08:45
Styrene	4.52	ug/L	0.50	90	70	130			
Tetrachloroethene	4.68	ug/L	0.50	94	70	130			
1,1,1,2-Tetrachlorcethane	4.72	ug/L	0.50	94	70	130			
1,1,2,2-Tetrachloroethane	4.96	ug/L	0.50	99	70	130			
Toluene	4.76	ug/L	0.50	95	70	130			
Trichlorcethene	4.92	ug/L	0.50	98	70	130			
1,1,1-Trichloroethane	5.72	ug/L	0.50	114	70	130			
1,1,2-Trichloroethane	4.72	ug/L	0.50	94	70	130			
Trichiorofluoromethane	4,88	ug/L	0.50	98	70	130			
1,2,3-Trichloropropane	5.24	ug/L	0.50	105	70	130			
Vinyl Acetate	5.32	ug/L	1.0	106	70	130			
Vinyl chloride	4.60	ug/L	0.50	92	70	130			
m+p-Xylenes	9.32	ug/L	0.50	93	70	130			
o-Xylene	4.52	ug/L	0,50	90	70	130			
Xylenes, Total	13.8	ug/L	0.50	92	70	130			
Surr: 1,2-Dichloroethane-d4			0.50	107	71	139			
Surr: p-Bromofluorobenzene			0.50	102	80	127			
Surr: Toluene-d8			0.50	91	80	123			
Method: E624								Batch:	R277281
Lab ID: [cs033117	Laboratory Co	ntrol Comple			Bue: 50714	A.I_170331A			/17 09:19
	56.0	ug/L	20	112	55	144		60101.	111 00.10
Acetone Acetonitrile	56.8	-	20	114	55 54	144			
Acrolein	42.4	ug/L	20	85	54 16	233			
	48.4	ug/L	20	97	76	127			
Acrylonitrile	40.4	ug/L	20 0.50		78				
Benzene		u g/L		98		122			
Bromobenzene	4.96	ug/L	0.50	99	74	129			
Bromochloromethane	5.16	ug/L	0.50	103	66	120			
Bromodichioromethane	5.16	ug/L	0.50	103	74	128			
Bromoform	5.12	ug/L	0.50	102	66	128			
Bromomethane	4.76	ug/L	0.50	95	51	123			
Carbon disuifide	5.36	ug/L	0.50	107	46	145			
Carbon tetrachloride	5.72	ug/L	0.50	114	75	125			
Chiorobenzene	4.64	ug/L	0.50	93	80	123			
Chiorodibromomethane	5.32	ug/L	0.50	106	74	125			
Chloroethane	4.48	ug/L	0.50	90	59	142			
2-Chloroethyl vinyl ether	2.62	ug/L	1.0	52	36	144			
Chloroform	5.52	ug/L	0.50	110	68	124			
Chloromethane	3.77	ug/L	0.50	75	53	146			
2-Chlorotoluene	5.08	ug/L	0.50	102	75	131			
4-Chlorotoluene	5.36	ug/L	0.50	107	74	129			
1,2-Dibromoethane	4.64	ug/L	0.50	93	76	124			
Dibromomethane	5.16	ug/L	0.50	103	77	125			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Jnits	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624								Batch:	R277281
Lab ID: Ics033117	Laboratory Contr	ol Sample			Run: 5971/	A.I_170331A		03/31	/17 09:19
1,2-Dichlorobenzene	4.96 1	ıg/L	0.50	99	74	124			
1,3-Dichlorobenzene	5.12 0	ig/L	0.50	102	77	122			
1,4-Dichlorobenzene	4.96 (ig/L	0.50	99	76	126			
Dichlorodifluoromethane	5.60 i	ıg/L	0.50	112	56	146			
1,1-Dichloroethane	4.72	íg/L	0.50	94	74	133			
1,2-Dichloroethane	5.76 เ	íg/L	0.50	115	75	129			
1,1-Dichloroethene	5.16 i	ig/L	0.50	103	74	132			
cis-1,2-Dichloroethene	4.88 i	ıg/L	0.50	98	81	122			
trans-1,2-Dichloroethene	5.12 (ig/L	0.50	102	79	143			
1,2-Dichloropropane	4.60 (ıg/L	0.50	92	75	126			
1,3-Dichloropropane	4.68 เ	ig/L	0,50	94	71	136			
2,2-Dichloropropane	5.68 נ	ig/L	0.50	114	68	142			
1,1-Dichloropropene	5.00 u	ig/L	0.50	100	70	131			
cis-1,3-Dichloropropene	4.40 (ıg/L	0.50	88	74	135			
trans-1,3-Dichloropropene	4.84 (ıg/L	0.50	97	76	149			
Ethylbenzene	4.96 (ıg/L	0.50	99	72	130			
Methyl tert-butyl ether (MTBE)	5.12 u	ig/L	0.50	102	72	120			
Methyl ethyl ketone	52.0 L	ig/L	20	104	45	130			
Methyl isobutyl ketone	50.8 L	ig/L	20	102	58	135			
Methylene chloride	6.08 L	ig/L	0.50	122	66	142			
Naphthalene	5.60 L	ig/L	0.50	112	69	124			
Styrene	4.56 L	ig/L	0.50	91	80	124			
Tetrachloroethene	4.72 u	ig/L	0.50	94	72	131			
1,1,1,2-Tetrachloroethane		g/L	0.50	93	78	124			
1,1,2,2-Tetrachloroethane		lg/L	0.50	95	68	137			
Toluene		ig/L	0.50	95	72	135			
Trichloroethene		ig/L	0.50	96	85	126			
1,1,1-Trichloroethane	5.40 u	ig/L	0.50	108	63	120			
1,1,2-Trichloroethane		ig/L	0.50	90	78	124			
Trichlorofluoromethane		g/L	0.50	90	72	120			
1,2,3-Trichloropropane		g/L	0.50	94	64	138			
Vinyl Acetate		g/L	1.0	95	31	124			
Vinyi chloride		g/L	0.50	95	58	140			
m+p-Xylenes		g/L	0.50	91	67	139			
o-Xylene		g/L	0.50	90	74	135			
Xylenes, Total	13.6 u	g/L	0.50	90	70	137			
Surr: 1,2-Dichloroethane-d4			0,50	109	71	139			
Surr: p-Bromofluorobenzene			0.50	102	80	127			
Surr: Toluene-d8			0.50	92	80	123			
Lab ID: bik033117	Method Blank				Run: 5971A			03/31	17 10:18
Acetone	ND u	g/L	20						
Acetonitrile	ND u	g/L	20						

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC Low Limit Hig	ih Limit	RPD	RPDLimit	Quai
Method: E624							Batch:	R277281
Lab (D: bik033117	Method Blank			Run: 5971A.I_1	70331A		03/31	/17 10:18
Acrolein	ND	ug/L	20	_				
Acrylonitrile	ND	ug/L	20					
Benzene	ND	ug/L	0.50					
Bromobenzene	ND	ug/L	0.50					
Bromochloromethane	ND	ug/L	0.50					
Bromodichloromethane	ND	ug/L	0.50					
Bromoform	ND	ug/L	0.50					
Bromomethane	ND	ug/L	0.50					
Carbon disulfide	ND	ug/L	0.50					
Carbon tetrachloride	ND	ug/L	0.50					
Chlorobenzene	ND	ug/L	0.50					
Chlorodibromomethane	ND	ug/L	0.50					
Chloroethane	ND	ug/L	0.50					
2-Chloroethyl vinyl ether	ND	ug/L	1.0					
Chloroform	ND	ug/L	0.50					
Chloromethane	ND	ug/L	0.50					
2-Chiorotoluene	ND	ug/L	0.50					
4-Chiorotoluene	ND	ug/L	0.50					
1,2-Dibromoethane	ND	ug/L	0.50					
Dibromomethane	ND	ug/L	0.50					
1.2-Dichlorobenzene	ND	ug/L	0.50					
1,3-Dichlorobenzene	ND	ug/L	0.50					
1,4-Dichlorobenzene	ND	ug/L	0.50					
Dichlorodifiuoromethane	ND	ug/L	0.50					
1,1-Dichloroethane	ND	ug/L	0.50					
1,2-Dichloroethane	ND	ug/L	0.50					
1,1-Dichloroethene	ND	ug/L	0.50					
cis-1,2-Dichloroethene	ND	ug/L	0.50					
trans-1,2-Dichloroethene	ND	ug/L	0.50					
1,2-Dichloropropane	ND	ug/L	0.50					
1,3-Dichloropropane	ND	ug/L	0.50					
	ND	-	0.50					
2,2-Dichloropropane	ND	ug/L	0.50					
1,1-Dichloropropene		ug/L						
cis-1,3-Dichloropropene	ND	ug/L	0.50					
trans-1,3-Dichloropropene	ND	ug/L	0.50					
Ethylbenzene Mathyl tart hutul athen (MTRE)	ND	ug/L	0.50					
Methyl tert-butyl ether (MTBE)	ND	ug/L	0.50					
Methyl ethyl ketone	ND	ug/L	20					
Methyl isobutyl ketone	ND	ug/L	20					
Methylene chloride	ND	ug/L	0.50					
Naphthalene	ND	ug/L	0.50					
Styrene	ND	ug/L	0.50					
Tetrachloroethene	ND	ug/L	0.50					

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624								Batch:	R27728
Lab (D: bik033117	Method Blank	t			Run: 5971/	A.I_170331A		03/31	/17 10:18
1,1,1,2-Tetrachloroethau	ne ND	ug/L	0.50						
1,1,2,2-Tetrachloroetha	ne ND	ug/L	0.50						
Toluene	ND	ug/L	0.50						
Trichloroethene	ND	ug/L	0.50						
I,1,1-Trichloroethane	ND	ug/L	0.50						
1,1,2-Trichloroethane	ND	ug/L	0.50						
richlorofluoromethane	ND	u g/L	0.50						
1,2,3-Trichloropropane	ND	ug/L	0.50						
/inyl Acetate	ND	ug/L	1.0						
/inyl chloride	ND	ug/L	0.50						
n+p-Xylenes	ND	ug/L	0.50						
-Xylene	ND	ug/L	0.50						
(yienes, Total	ND	ug/L	0.50						
Surr: 1,2-Dichloroetha	ane-d4	-	0.50	105	71	139			
Surr: p-Bromofluorob			0.50	104	80	127			
Surr: Toluene-d8			0.50	92	80	123			
ab D: b1703187	5-001dms Sample Matrix	x Spike			Run: 5971/	A.I_170331A		03/31	/17 14:1:
cetone	378	u g/L	100	109	55	144			
cetonitrile	274	ug/L	100	110	54	142			
lenzene	24.6	ug/L	2.5	98	73	122			
romobenzene	24.8	ug/L	2.5	99	74	129			
romochloromethane	25.2	ug/L	2.5	101	66	120			
romodichloromethane	26.2	ug/L	2.5	105	74	128			
Bromoform	27.0	ug/L	2.5	108	66	128			
Iromomethane	18.8	ug/L	2.5	75	51	123			
Carbon disulfide	26.4	ug/L	2.5	106	46	145			
Carbon tetrachloride	28.2	ug/L	2,5	113	75	125			
chiorobenzene	22.8	ug/L	2.5	91	80	123			
hlorodibromomethane	26.8	ug/L	2.5	107	74	125			
Chloroethane	20.2	ug/L	2.5	81	59	142			
Chieroform	33.2	ug/L	2.5	110	68	124			
Chloromethane	18.6	ug/L	2.5	74	53	146			
2-Chlorotoluene	24.8	ug/L	2.5	99	75	131			
-Chlorotoluene	25.8	ug/L	2.5	103	74	129			
,2-Dibromoethane	24.0	ug/L	2.5	96	76	124			
Dibromomethane	26.2	ug/L	2.5	105	77	125			
,2-Dichlorobenzene	24.6	ug/L	2.5	98	74	124			
,3-Dichlorobenzene	24.6	ug/L	2.5	98	77	122			
,4-Dichlorobenzene	24.6	ug/L	2.5	98	76	126			
) Dichlorodifiuoromethane		ug/L	2.5	108	56	146			
,1-Dichloroethane	24.2	ug/L	2.5	97	74	133			
-	29.2	ug/L	2.5	117	75	129			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E624								Batch:	R277281
Lab ID: b17031875-001dms	Sample Matri	k Spike			Run: 5971	A.I_170331A		03/31	/17 14:12
1,1-Dichloroethene	26.6	ug/L	2.5	106	74	132			
cis-1,2-Dichloroethene	24.4	ug/L	2.5	98	81	122			
trans-1,2-Dichloroethene	25.8	ug/L	2.5	103	79	143			
1,2-Dichloropropane	23.0	ug/L	2.5	92	75	126			
1,3-Dichloropropane	22.4	ug/L	2.5	90	71	136			
2,2-Dichloropropane	28.0	ug/L	2.5	112	68	142			
1,1-Dichioropropene	25.2	ug/L	2.5	101	70	131			
cis-1,3-Dichloropropene	22.2	ug/L	2.5	89	74	135			
trans-1,3-Dichloropropene	24.6	ug/L	2.5	98	76	149			
Ethylbenzene	23.6	ug/L	2.5	94	72	130			
Methyl tert-butyl ether (MTBE)	25.6	ug/L	2.5	102	72	120			
Methyl ethyl ketone	268	ug/L	100	107	45	130			
Methyl isobutyl ketone	258	ug/L	100	103	58	135			
Methylene chloride	32.2	ug/L	2.5	129	66	142			
Naphthalene	27.6	ug/L	2.5	110	69	124			
Styrene	22.4	ug/L	2.5	90	80	124			
Tetrachloroethene	22.8	ug/L	2.5	91	72	131			
1,1,1,2-Tetrachioroethane	23.0	ug/L	2.5	92	78	124			
1,1,2,2-Tetrachloroethane	26.0	ug/L	2.5	104	68	137			
Toluene	24.4	ug/L	2.5	95	72	135			
Trichloroethene	23.8	ug/L	2.5	95	85	126			
1,1,1-Trichloroethane	26.8	ug/L	2.5	107	63	120			
1,1,2-Trichloroethane	23.4	ug/L	2.5	94	78	124			
Trichlorofluoromethane	21.2	ug/L	2.5	85	72	120			
1,2,3-Trichloropropane	26.2	ug/L	2.5	105	64	138			
Vinyl Acetate	24.4	ug/L	5.0	98	31	124			
Vinyl chloride	22.6	ug/L	2.5	90	58	140			
m+p-Xylenes	44.8	ug/L	2.5	90	67	139			
o-Xylene	22.6	ug/L	2.5	90	74	135			
Xylenes, Total	67.4	ug/L	2.5	90	70	137			
Surr: 1,2-Dichloroethane-d4			2.5	110	71	139			
Surr: p-Bromofluorobenzene			2.5	102	80	127			
Surr: Toluene-d8			2.5	93	80	123			
Lab ID: b17031875-001dmsd	Sample Matrix	Spike Duplicate			Run: 5971/	.I_170331A		03/31	/ 17 15:1 1
Acetone	410	ug/L	100	122	55	144	8.1	20	
Acetonitrile	262	ug/L	100	105	54	142	4.5	20	
Benzene	25.0	ug/L	2.5	100	73	122	1.6	20	
Bromobenzene	25.6	ug/L	2.5	102	74	129	3.2	20	
Bromochloromethane	25,2	ug/L	2.5	101	66	120	0.0	20	
Bromodichloromethane	27.2	ug/L	2.5	109	74	128	3.7	20	
Bromoform	28.4	ug/L	2.5	114	66	128	5.1	20	
Bromomethane	20.8	ug/L	2.5	83	51	123	10	20	

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPOLimit	Qual
Method:	E624								Batch:	R27728
Lab ID:	b17031875-001dmsd	Sample Matrix	c Spike Duplicate			Run: 5971/	A.I_170331A		03/31	/17 15:11
Carbon dis	ulfide	25.6	ug/L	2.5	102	46	145	3.1	20	
Carbon tet	rachloride	28.6	ug/L	2.5	114	75	125	1.4	20	
Chlorobena	zene	23.6	ug/L	2.5	94	80	123	3.4	20	
Chlorodibro	omomethane	28.0	ug/L	2.5	112	74	125	4.4	20	
Chloroetha	ine	20.6	ug/L	2.5	82	59	142	2.0	20	
Chloroform	1	33.6	ug/L	2.5	111	68	124	1.2	20	
Chlorometi	hane	19.3	ug/L	2.5	77	53	146	3.8	20	
2-Chloratol	luene	26.4	ug/L	2.5	106	75	131	6.2	20	
4-Chlorotol	uene	27.2	ug/L	2.5	109	74	129	5.3	20	
1.2-Dibrom	oethane	24.0	ug/L	2.5	96	76	124	0.0	20	
Dibromome	ethane	26.8	ug/L	2.5	107	77	125	2.3	20	
1,2-Dichlor		25.8	ug/L	2.5	103	74	124	4.8	20	
1,3-Dichlor		26.0	ug/L	2.5	104	77	122	5.5	20	
1,4-Dichior		25.4	ug/L	2.5	102	76	126	3.2	20	
	luoromethane	25.8	ug/L	2.5	103	56	146	4.5	20	
1,1-Dichlor		24.8	ug/L	2.5	99	74	133	2.4	20	
1,2-Dichlor		29.2	ug/L	2.5	117	75	129	0.0	20	
1,1-Dichlor		26.8	ug/L	2.5	107	74	132	0.7	20	
•	hloroethene	25.2	ug/L	2.5	101	81	122	3.2	20	
	lichloroethene	26.4	ug/L	2.5	106	79	143	2.3	20	
1,2-Dichlor		23.6	ug/L	2.5	94	75	126	2.6	20	
1,3-Dichlor	• •	23.8	ug/L	2.5	95	71	136	6.1	20	
2,2-Dichlor		28.6	ug/L	2.5	114	68	142	2.1	20	
1,1-Dichlor		25.8	ug/L	2.5	103	70	131	2.4	20	
•	hloropropene	23.2	ug/L	2.5	93	74	135	4.4	20	
	lichloropropene	25.4	ug/L	2.5	102	76	149	3.2	20	
Ethylbenze		25.0	ug/L	2.5	100	72	130	5,8	20	
	-buty! ether (MTBE)	26.6	ug/L	2.5	106	72	120	3.8	20	
Methyl ethy		292	ug/L	100	117	45	130	8.6	20	
	putyl ketone	286	ug/L	100	114	43 58	135	10	20	
		31.4		2.5	126	66	142	2.5	20	
Methylene Naphthaler		27.8	ug/L	2.5	111	69	142	0.7	20	
	16	27.8	ug/L	2.5	91		124	1.8	20	
Styrene	- the		ug/L			80				
		23.8	ug/L	2,5 2.5	95 93	72 78	131 124	4.3 0,9	20 20	
	rachloroethane	23.2	ug/L							
	rachloroethane	27.4	ug/L	2.5	110	68	137	5.2	20	
Toluene Trick(croot)		24.4	ug/L	2.5	95 100	72	135	0.0	20	
Trichloroeti		25.0	ug/L	2.5	100	85	126	4.9	20	
	loroethane	27.4	ug/L	2.5	110	63	120	2.2	20	
1,1,2-Trich		24.8	ug/L	2.5	99	78	124	5.8	20	
	oromethane	22.4	ug/L	2.5	90	72	120	5.5	20	
	loropropane	26.8	ug/L	2.5	107	64	138	2.3	20	
Vinyl Aceta	te	24.4	ug/L	5.0	98	31	124	0.0	20	

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E624								Batch:	R277281
Lab ID:	b17031875-001dmsd	Sample Matrix	k Spike Duplicate			Run: 5971/	A.I_170331A		03/31	/17 15:11
Vinyl chlo	ride	22.8	ug/L	2.5	91	58	140	0.9	20	
m+p-Xyler	nes	46.0	ug/L	2.5	92	67	139	2.6	20	
o-Xylene		23.4	ug/L	2.5	94	74	135	3.5	20	
Xylenes, 1	Total	69.4	ug/L	2.5	93	70	137			
Surr: 1,	2-Dichloroethane-d4			2.5	112	71	139			
Surr: p-	Bromofluorobenzene			2.5	105	80	127			
Surr: To	oluene-d8			2.5	93	80	123			



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E625								Bato	h: 107942
Lab ID:	MB-107942	Method Blank				Run: SV59	73N2.I_170330B		03/30	0/17 16:12
Acenaphthe	ene	ND	ug/L	10						
Acenaphth)	/lene	ND	ug/L	10						
Anthracene		ND	ug/L	10						
Azobenzen	e	ND	ug/L	10						
Benzidine		ND	ug/L	10						
Benzo(a)an	thracene	ND	ug/L	10						
Benzo(a)py	rene	ND	ug/L	10						
Benzo(b)fiu	oranthene	ND	ug/L	10						
Benzo(g,h,i)perylene	ND	ug/L	10						
Benzo(k)flu	oranthene	ND	ug/L	10						
4-Bromophe	enyl phenyl ether	ND	ug/L	10						
Butylbenzyl	phthalate	ND	ug/L	10						
4-Chloro-3-	methylphenol	ND	ug/L	10						
bis(-2-chior	oethoxy)Methane	ND	ug/L	10						
bis(-2-chlore	pethyl)Ether	ND	ug/L	10						
bis(2-chloro	isopropyl)Ether	ND	ug/L	10						
2-Chlorona	ohthalene	ND	ug/iL	10						
2-Chloroph	BNO	ND	ug/L	10						
4-Chlorophe	anyl phenyl ether	ND	ug/L	10						
Chrysene		ND	ug/L	10						
Diethyl phth	alate	ND	ug/L	10						
Di-n-butyl p	hthalate	ND	ug/L	10						
1,2-Dichloro	benzene	ND	ug/L	10						
1,3-Dichlord	benzene	ND	ug/L	10						
1,4-Dichlord	benzene	ND	ug/L	10						
3,3'-Dichlor	obenzidine	ND	ug/L	10						
2,4-Dichlord	phenol	ND	ug/L	10						
Dimethyl ph		ND	ug/L	10						
Di-n-octyl pl		ND	ug/L	10						
	i)anthracene	ND	ug/L	10						
2,4-Dimethy	•	ND	ug/L	10						
	2-methylphenol	ND	u g /L	50						
2,4-Dinitrop		ND	ug/L	50						
2,4-Dinitroto		ND	ug/L	10						
2,6-Dinitroto		ND	ug/L	10						
	exyl)Phthalate	ND	ug/L	10						
Fluoranthen	e	ND	ug/L	10						
Fluorene		ND	ug/L	10						
Hexachlorol		ND	ug/L	10						
Hexachlorol		ND	ug/L	10						
	cyclopentadiene	ND	ug/L	10						
Hexachloroe		ND	ug/L	10						
Indeno(1,2,	3-cd)pyrene	ND	ug/L	10						

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result U	nits RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Quai
Method: E625							Batcl	n: 10794 2
Lab ID: MB-107942	Method Blank			Run: SV59	73N2.I_170330B		03/30	/17 16:12
Isophorone	ND uş	g/L 10						
n-Nitrosodimethylamine	ND ug	J/L 10						
n-Niroso-di-n-propylamine	ND uş	g/L 10						
n-Nitrosodiphenylamine	ND uş	J/L 10						
2-Nitrophenol	ND uş	j/L 10						
4-Nitrophenol	ND uş	y/L 50						
Naphthalene	ND uş	J/L 10						
Nitrobenzene	ND uş	y/L 10						
Pentachlorophenol	ND uş	/L 50						
Phenanthrene	ND uş	3/L 10						
Phenol	ND ug	j/L 10						
Pyrene	ND uç	∦/L 10						
1,2,4-Trichlorobenzene	ND uş	j/L 10						
2,4,6-Trichlorophenol	ND ug	g/L 10						
Surr: 2-Fluorobiphenyl		10	57	28	107			
Surr: 2-Fluorophenol		10	42	20	56			
Surr: Nitrobenzene-d5		10	62	32	94			
Surr: Phenoi-d5		10	30	19	45			
Surr: Terphenyl-d14		10	80	32	122			
Surr: 2,4,6-Tribromophenol		10	68	21	130			
Lab ID: LCS-107942	Laboratory Control	i Sample		Run: SV59	73N2.I_170330B		03/30	/17 16:43
Acenaphthene	89.1 ug	J/L 10	89	58	99			
Acenaphthylene	84.2 ug	µ′∟ 10	84	57	96			
Anthracene	75.6 ug	g/L 10	76	60	107			
Azobenzene	78.0 ug	µ/L 10	78	56	100			
Benzidine	53.1 ug	10 JL	53	10	100			
Benzo(a)anthracene	86.4 ug	/L 10	86	62	114			
Benzo(a)pyrene	84.7 ug	µ/L 10	85	62	108			
Benzo(b)fluoranthene	gu 8.68	µ/L 10	90	48	127			
Benzo(g,h,i)perylene	87.2 ug	µ/L 10	87	62	121			
Benzo(k)fluoranthene	84.0 ug	/L 10	84	55	111			
4-Bromophenyl phenyl ether	87.1 uç	r/L 10	87	58	105			
Butylbenzylphthalate	90.8 ug	r/L 10	91	60	113			
4-Chloro-3-methyiphenoi	74.6 ug	J/L 10	75	53	92			
bis(-2-chloroethoxy)Methane	69.9 ug	/L 10	70	50	92			
bis(-2-chloroethyl)Ether		µ/L 10	72	44	82			
bis(2-chloroisopropyl)Ether		∦/L 10	63	56	87			
2-Chloronaphthalene		µ/L 10	85	56	95			
2-Chlorophenol		µ/L 10	67	47	76			
4-Chlorophenyl phenyl ether		ı/L 10	83	58	99			
Chrysene		j/∟ 10	87	63	106			
Diethyl phthalate	84.6 ug	j/L 10	85	58	103			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625		·						Batc	h: 107942
Lab ID: LCS-107942	Laboratory Con	froi Sample			Run: SV59	73N2.I_170330B		03/30)/17 16:43
Di-n-butyl phthalate	87.1	ug/L	10	87	61	110			
1,2-Dichlorobenzene	69.3	ug/L	10	69	43	81			
1,3-Dichlorobenzene	64.0	ug/L	10	64	41	79			
1,4-Dichlorobenzene	64.5	ug/L	10	64	42	79			
3,3'-Dichlorobenzidine	64.8	ug/L	10	65	51	93			
2,4-Dichlorophenol	70.6	ug/L	10	71	49	90			
Dimethyl phthalate	82.5	ug/L	10	82	58	104			
Di-n-octyl phthalate	93.4	ug/L	10	93	56	110			
Dibenzo(a,h)anthracene	87.8	ug/L	10	88	61	111			
2,4-Dimethylphenol	66.2	ug/L	10	66	45	89			
4,6-Dinitro-2-methylphenol	66.1	u g /L	50	66	37	105			
2,4-Dinitrophenol	54.1	ug/L	50	54	27	81			
2,4-Dinitrotoluene	86.2	ug/L	10	86	63	110			
2,6-Dinitrotoluene	77.2	u g/L	10	77	60	107			
bis(2-ethylhexyl)Phthalate	86.0	ug/L	10	86	56	108			
Fluoranthene	84.2	ug/L	10	84	63	110			
Fluorene	89.3	ug/L	10	89	60	99			
Hexachlorobenzene	82.7	ug/L	10	83	57	103			
Hexachiorobutadiene	71.7	ug/L	10	72	39	83			
Hexachiorocyclopentadlene	81.0	ug/L	10	81	39	91			
Hexachloroethane	65.0	ug/L	10	65	37	75			
Indeno(1,2,3-cd)pyrene	83.2	ug/L	10	83	59	109			
Isophorone	69.8	ug/L	10	70	42	102			
n-Nitrosodimethylamine	36.8	ug/L	10	37	20	45			
n-Nitroso-di-n-propylamine	76.6	ug/L	10	77	49	98			
n-Nitrosodiphenyiamine	91.5	ug/L	10	92	61	108			
2-Nitrophenol	72.3	ug/L	10	72	51	96			
4-Nitrophenol	27.4	ug/L	50	27	15	36			
Naphthalene	68. 1	ug/L	10	68	48	96			
Nitrobenzene	77.9	ug/L	10	78	51	91			
Pentachiorophenol	72.4	ug/L	50	72	53	109			
Phenanthrene	82.0	ug/L	10	82	58	104			
Phenol	40.6	ug/L	10	41	27	45			
Pyrene	85.0	ug/L	10	85	64	108			
1,2,4-Trichlorobenzene	71.2	ug/L	10	71	49	85			
2,4,6-Trichlorophenol	73.9	ug/L	10	74	47	99			
Surr: 2-Fluorobiphenyl			10	69	28	107			
Surr: 2-Fluorophenol			10	42	20	56			
Surr: Nitrobenzene-d5			10	72	32	94			
Surr: Phenoi-d5			10	36	19	45			
Surr: Terphenyl-d14			10	80	32	122			
Surr: 2,4,6-Tribromophenoi			10	70	21	130			

Qualifiers:

RL - Analyte reporting limit.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte		Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E625								Batcl	h: 107942
Lab (D:	C17030850-001CMS	Sample Matrix	x Spike			Run: SV59	73N2.I_1703308	ł	03/30	/17 17:45
Acenaphthe	ene	86.7	ug/L	10	87	58	- 99			
Acenaphth	ylene	75.5	ug/L	10	76	57	96			
Anthracene)	81.6	ug/L	10	82	60	107			
Azobenzen	e	84.6	ug/L	10	85	56	100			
Benzidine		122	ug/L	20	122	10	100			S
Benzo(a)an	thracene	83.4	ug/L	10	83	62	114			
Benzo(a)py	rene	78.4	ug/L	10	78	62	108			
Benzo(b)flu	oranthene	79.9	ug/L	10	80	48	127			
Benzo(g,h,i)perylene	83.2	ug/L	10	83	62	121			
Benzo(k)flu	oranthene	84.5	ug/L	10	84	55	111			
4-Bromoph	enyl phenyl ether	79.5	ug/L	10	79	58	105			
Butylbenzyl	phthalate	89.2	ug/L	10	89	60	113			
4-Chloro-3-	methylphenol	78,3	ug/L	10	78	53	92			
	oethoxy)Methane	77.9	ug/L	10	78	50	92			
bis(-2-chlor	oethyl)Ether	71.5	ug/L	10	71	44	82			
•	visopropyl)Ether	58.4	ug/L	10	58	56	87			
2-Chlorona	phthalene	77.6	ug/L	10	78	56	95			
2-Chloroph		63.7	ug/L	10	64	47	76			
4-Chioroph	enyi phenyi ether	81.0	ug/L	10	81	58	99			
Chrysene		85.9	ug/L	10	86	63	106			
Diethyl phth	nalate	84.0	ug/L	10	84	58	103			
Di-n-butyl p	hthalate	87.0	ug/L	10	87	61	110			
1,2-Dichlord		67.3	ug/L	10	67	43	81			
1,3-Dichloro		66.0	ug/L	10	66	41	79			
1,4-Dichloro		66.7	ug/L	10	67	42	79			
3,3'-Dichlor		131	ug/L	10	131	51	93			S
2,4-Dichlord	-	70.0	ug/L	10	70	49	90			
Dimethyl ph		79.3	ug/L	10	79	58	104			
Di-n-octyi pi		81.8	ug/L	10	82	56	110			
)anthracene	80.1	ug/L	10	80	61	111			
2,4-Dimethy		70.7	ug/L	10	71	45	87			
	2-methylphenol	53.1	ug/L	50	53	37	105			
2,4-Dinitrop		43.0	ug/L	50	43	27	81			
2,4-Dinitroto		85.6	ug/L	10	86	63	110			
2,6-Dinitroto		81.5	ug/L	10	81	60	107			
	exyl)Phthalate	77.5	ug/L	10	77	56	108			
Fluoranthen	e	84.0	ug/L	10	84	63	110			
Fluorene		80.0	ug/L	10	80	60	89			
Hexachlorot		78.2	ug/L	10	78	57	103			
Hexachlorot		69.1	ug/L	10	69	39	83			
	cyclopentadiene	69.0	ug/L	10	69	39	91			
Hexachloroe		62.6	ug/L	10	63	37	75			
Indeno(1,2,3	3-cd)pyrene	76.3	ug/L	10	7 6	59	109			

Qualifiers:

RL - Analyte reporting limit.

S - Spike recovery outside of advisory limits.



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625								Batc	h: 107942
Lab ID: C17030850-001CMS	Sample Matrix	c Spike			Run: SV59	73N2.I_170330B		03/30	/17 17:45
lsophorone	71.4	ug/L	10	71	42	102			
n-Nitrosod/methylamine	26.1	ug/L	10	26	20	45			
n-Nitroso-di-n-propylamine	76.1	ug/L	10	76	49	98			
n-Nitrosodiphenylamine	105	ug/L	10	105	61	108			
2-Nitrophenol	73.5	ug/L	10	74	51	96			
4-Nitrophenol	25.8	ug/L	50	26	15	36			
Naphthalene	75.6	ug/L	10	76	48	96			
Nitrobenzene	75 .6	ug/L	10	76	51	91			
Pentachlorophenol	60.3	ug/L	50	60	53	109			
Phenanthrene	83.8	ug/L	10	84	58	104			
Phenol	38.7	ug/L	10	39	27	45			
Pyrene	87.0	ug/L	10	87	64	108			
1,2,4-Trichlorobenzene	74.7	ug/L	10	75	49	85			
2,4,6-Trichlorophenol	68.8	ug/L	10	69	47	99			
Surr: 2-Fluorobiphenyl			10	51	28	107			
Surr: 2-Fluorophenol			10	41	20	56			
Surr: Nitrobenzene-d5			10	64	32	94			
Surr: Phenol-d5			10	33	19	45			
Surr: Terphenyl-d14			10	73	32	122			
Surr: 2,4,6-Tribromophenol			10	67	21	130			



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625							An	alytical Run:	R277253
Lab ID: 30-Mar-17_CCV	_11 Continuing C	alibration V	erification Standa	rd				03/30)/17 15:40
Acenaphthene	75.3	ug/L	10	100	80	120			
Acenaphthylene	79.7	ug/L	10	106	80	120			
Anthracene	75.2	ug/L	10	100	80	120			
Azobenzene	75.1	ug/L	10	100	80	120			
Benzidine	70.6	ug/L	10	94	80	120			
Benzo(a)anthracene	76.3	ug/L	10	102	80	120			
Benzo(a)pyrene	81.9	ug/L	10	109	80	120			
Benzo(b)fluoranthene	78.3	ug/L	10	104	80	120			
Benzo(g,h,l)perylene	78.0	ug/L	10	104	80	120			
Benzo(k)fluoranthene	81.6	ug/L	10	109	80	120			
4-Bromophenyl phenyl ether	81.6	ug/L	10	109	80	120			
Butylbenzylphthalate	78.0	ug/L	10	104	80	120			
4-Chloro-3-methylphenol	76.0	ug/L	10	101	80	120			
bis(-2-chloroethoxy)Methane	70.4	ug/L	10	94	80	120			
bis(-2-chloroethyl)Ether	77.2	ug/L	10	103	80	120			
bis(2-chloroisopropyl)Ether	76.7	ug/L	10	102	80	120			
2-Chloronaphthalene	79.8	ug/L	10	106	80	120			
2-Chlorophenol	72.7	ug/L	10	97	80	120			
4-Chlorophenyl phenyl ether	72.7	ug/L	10	97	80	120			
Chrysene	74.9	ug/L	10	100	80	120			
Diethyl phthalate	76.8	ug/L	10	102	80	120			
Di-n-butyl phthalate	76.9	ug/L	10	102	80	120			
1,2-Dichlorobenzene	76.8	ug/L	10	102	80	120			
1,3-Dichlorobenzene	72.1	ug/L	10	96	80	120			
1,4-Dichlorobenzene	74.8	ug/L	10	100	80	120			
3,3'-Dichlorobenzidine	76.2	ug/L	10	102	80	120			
2,4-Dichlorophenol	73.5	ug/L	10	98	80	120			
Dimethyl phthalate	77.0	ug/L	10	103	80	120			
Di-n-octyl phthalate	81.2	ug/L	10	108	80	120			
Dibenzo(a,h)anthracene	76.2	ug/L	10	102	80	120			
2,4-Dimethylphenol	70.3	ug/L	10	94	80	120			
4,6-Dinitro-2-methylphenol	77.4	ug/L	50	103	80	120			
2,4-Dinitrophenol	80.2	ug/L	50	107	80	120			
2,4-Dinitrotoluene 2,6-Dinitrotoluene	79.8	ug/L	10	106	80	120			
•	80.8	ug/L	10	108	80	120			
bis(2-ethylhexyi)Phthalate Fluoranthene	77.3	ug/L	10	103	80	120			
Fluorene	76.8 82.8	ug/L	10	102	80 80	120			
Hexachiorobenzene	82.8 74.2	ug/L	10	110	80	120			
Hexachlorobutadiene	74.2	ug/L	10	99	80 80	120			
Hexachiorocyclopentadiene	73.0 79.2	ug/L	10	97 106	80 80	120			
Hexachloroethane	79.2 74.4	ug/L	10 10	106	80	120			
Indeno(1,2,3-cd)pyrene	74.4	ug/L		99 08	80 80	120			
	£3.5	ug/L	10	98	80	120			

Qualifiers:

RL - Analyte reporting limit.



-

QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method: E625							Ar	aiytical Run:	R277253
Lab ID: 30-Mar-17_CCV_11	Continuing Ca	libration Verific	cation Standa	urd				03/30)/17 15:40
Isophorone	71.5	ug/L	10	95	80	120			
n-Nitrosodimethylamine	79.5	ug/L	10	106	80	120			
n-Nitroso-di-n-propylamine	76.0	ug/L	10	101	80	120			
n-Nitrosodiphenylamine	77.5	ug/L	10	103	80	120			
2-Nitrophenol	74.6	ug/L	10	99	80	120			
4-Nitrophenol	72.4	ug/L	50	97	80	120			
Naphthalene	68.4	ug/L	10	91	80	120			
Nitrobenzene	77.1	ug/L	10	103	80	120			
Pentachlorophenol	71.7	ug/L	50	96	80	120			
Phenanthrene	70,9	ug/L	10	95	80	120			
Phenol	79.0	ug/L	10	105	80	120			
Pyrene	79.0	ug/L	10	105	80	120			
1,2,4-Trichlorobenzene	73.1	ug/L	10	98	80	120			
2,4,6-Trichlorophenol	71.0	ug/L	10	95	80	120			
Surr: 2-Fluorobiphenyl			10	108	80	120			
Surr: 2-Fluorophenol			10	105	80	120			
Surr: Nitrobenzene-d5			10	101	80	120			
Surr: Phenol-d5			10	102	80	120			
Surr: Terphenyl-d14			10	104	80	120			
Surr: 2,4,6-Tribromophenol			10	105	80	120			



Prepared by Billings, MT Branch

Client: Colorado Analytical Laboratories Inc

Project: 170324007 Sterling Ranch MD

Report Date: 04/06/17 Work Order: C17030850

Analyte		Result	Units	RL.	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	SW8260M								Analytical Ru	n: 108173
Lab (D:	CCV-108173	Continuing Ca	libration Verificatio	on Standa	Ird				04/06	/17 08:29
1,4-Dioxane		95.7	ug/L	1.0	96	80	120			
Method:	SW8260M								Batci	h: 108173
Lab ID:	LCS-108173	Laboratory Co	ntrol Sample			Run: VOA5	5973A.I_170406A		04/06	/17 08:51
1,4-Dioxane		87.5	ug/L	1.0	88	70	130			
Lab ID:	MB-108173	Method Blank				Run: VOA5	973A.I_170406A		04/06	/17 09:12
1,4-Dioxane		ND	ug/L	1.0			_			
Lab ID:	C17030850-001AMS	Sample Matrix	Spike			Run: VOA5	973A.I_170406A		04/06	/17 09:55
1,4-Dioxane		194	ug/L	2.0	97	70	130			
Lab (D:	C17030850-001AMSD	Sample Matrix	Spike Duplicate			Run: VOA5	973A.I_170406A		04/06	/17 10:17
1,4-Dioxane		206	ug/L	2.0	103	70	130	6.0	20	



C17030850

Work Order Receipt Checklist

Colorado Analytical Laboratories Inc

Login completed by:	Corinne Wagner		Date	Received: 3/28/2017	
Reviewed by:	Kasey Vidick		Re	ceived by: ckw	
Reviewed Date:	3/29/2017		Car	rier name: Ground	
Shipping container/cooler in	good condition?	Yes 🖌	No 🗌	Not Present	
Custody seals intact on all sh	hipping container(s)/cooler(s)?	Yes	No 🗌	Not Present 🗹	
Custody seals intact on all sa	ample bottles?	Yes	No 🗌	Not Present	
Chain of custody present?		Yes 🗹	No		
Chain of custody signed whe	n relinguished and received?	Yes 🗸	No 🗌		
Chain of custody agrees with	sample labels?	Yes 🗹	No 🗌		
Samples in proper container/	bottle?	Yes 🗹	No 🗌		
Sample containers intact?		Yes 🗸	No 🗌		
Sufficient sample volume for	indicated test?	Yes 🗸	No 🗌		
Ail samples received within h (Exclude analyses that are co such as pH, DO, Res Cl, Sul	onsidered field parameters	Yes 🗹	No 🗌		
Temp Blank received in all st	hipping container(s)/cooler(s)?	Yes 🗌	No 🗸	Not Applicable	
Container/Temp Blank tempe	rature:	6,6°C On Ice -	From Field		
Water - VOA vials have zero	headspace?	Yes 🗹	No 🗌	No VOA vials submitted	
Water - pH acceptable upon	receipt?	Yes	No 🗌	Not Applicable	

Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

Contact and Corrective Action Comments:

None

	 Colorado Analytical Laboratories, inc. 	Brighton Lab	240 South Main Street Brighton, CO 80601	Lakewood Lab	Lakewood CO 80228	V Phone: 303-659-2313 Fax: 303-659-2315	www.coloradolah.com			UTAZO50											Seals Present Yes D No D UNY	Temp. 6 (%Clice) Sample Pres. Yes 🗆 No 🗆	Received By: Date/Time:	NDX (3. H-1
	Project Name	170324007	Sterling Ranch MD	Task Number (Lab Use Only)	CAL Task No. 15-11 170324007	ţ	ARE	Disposal Date(Lab Use Only)					void Isid	5005 Fous 0 1't-	¢79 978						Scals Pri	C/S Charge 🔲 Temp. (
Chain of Custody Form	Bill To Information (If different from report to)	Company Name: Same	Contact Name:	Address:		City State Zip	Phone: Fax:		PO No.:				anO z	01 Cc	or (C/S lufo:	Deliver V	Date/Time:	
		Company Name: <u>Colorado Analytical Laboratoy</u>	vielson			State CO Zip80601	Fax:303-659-2315	oloradolab.com				Soil	Sladge	Compost		170324007 Sterling Ranch MD					rgy Labs		Date/Time: Received By: 3/27/77	1100
	Report To Information	Company Name: Colori	Contact Name: Stuart Nielson	Address: P.O. Roy 507	240 S Main St		Phone:303-659-2313	Email: stuarmielson@coloradolab.com	Sample Collector:		和限制。其外的基本可能	Waste Water	Ground Water 🛛	Surface Water		· .					Instructions: UPS to Energy Labs		Relinquished By:	M.M.Celler

APPENDIX F

FAWA WATER SUPPLY VS CURRENT WATER COMMITMENTS





RESPEC.COM

Appendix F Falcon Area Water and Wastewater Authority Commitments within FAWWA Service Area Update September 11, 2024

		Analy	vsis of Water Co	ommitments				Volumetric
	Development		eliminary Commit			inal Commitments		Commitment
	Development	Commitment	Supply / Commitment	Letter or Summary	Commitment	Commitment	Letter or Summary	(300 yearAcre- feet)
	The Retreat at TimberRidge Preliminary Plan (Central System	SFE 167	Acre-Feet 58.951	Date/Notes April 2018 Report	SFE	Acre-Feet	Date/Notes	17685.3
	Only)	107	50.751	Supplement Nov 2020				11005.0
	Final #1 Final #2				59 SFE 78 SFE	20.827 27.53	23-Aug-20 April 30,2021	
Retreat	Final #2				30 SFE	10.59	July, 2022	
Ret	Stimple Subdivision	1	0.353	August 2024 Latter			(reissued May 15, 2023)	105.0
	Stimple Subdivision	I	0.353	August, 2024 Letter				105.9
	Retreat at Timberidge Filing 4				10	3.53	20-Feb-24	1059.0
	Sterling Ranch Preliminary Plan Phase One	726	255.96	June 2015 Report/Summa	r <mark>y</mark>			
				Update February 2019				
	Sterling Ranch Filing #1				0	0	Tracts Only	
					Ť	Ť	Tradio o my	
	Tract BB (10.545) Branding Iron at Sterling Ranch Filing No. 1				51	17.85	Summary and Letter	5355.0
	Branding Iron Filing No. 2				88	31.07	Revised Feb 20, 2020	9321.0
							(includes School13 SFE/75 Residential)	
	Sterling Ranch Filing #2				61	21.59	Includes 4.29 AF Irrigation	6477.0
	(49 SF lots with 4.29 AF landscaping)				(61 SFE w irrigation)		Revised Feb 10, 2021	
st	Sterling Ranch Filing No 5	72	24.26				Previously Tract B Branding	7278.0
Sterling Ranch West	Sterning Kation Friing NO 5	12	24.20 March 31, 2023 Letter				Iron N2	12/0.0
anch	Tract G (19.574) Homestead at Sterling Ranch Filing No. 1				72	25.42		7624.8
ng Rá	Tract E (29.658) Homestead at Sterling Ranch Filing No. 2				104	36.71	25-Sep-19	11013.6
terlir	Homestead at Sterling Ranch Filing No 3 (Vacation and Replat)				-2	-0.71	6-Mar-23	-211.5
S	Copper Chase at Sterling Ranch	142.9	50.45	17-Dec-21	147.68	52.13	0 mili 20	15639.0
	resubmittal		138 single family lots	17-Dee-21	147.00	52.15	October 12, 2022 138 single family lots includes	15057.0
			12/21/2021 includes 1.39 Ac Park				1.39 Ac Park additonal irrigation	
			710 7 ши					
	Sterling Ranch Preliminary Plan Phase Two	214.5	75.719	July, 2020 Re-issue Feb 26, 2021			School commitment (13 SFE) contained in Branding Iron Filing #2 above	22715.6
	Sterling Ranch Filing #4				159 Lots (2.667 Acres Irrigation) Specific Note 1	51.91		
	Homestead North at Sterling Ranch Preliminary Plan	147	62.47	Letter November 4, 2022 includes	1		Letter November 4, 2022 includes 10.58	18741.0
				10.58 AFs irrigation			AFs irrigation	
	Homestead North at Sterling Ranch Filing No. 3	77	41.31	Letter dated June 10, 2022				12393.0
		(5.65 acres irrigation)		updated November 3, 2022				
	Foursquare at Sterling Ranch PUD Preliminary Plan	158 High Density Units		Letter dated June 10, 2022 Update November 3, 2022				
	g	(1.424 acres irrigation)	50.73	Opdate November 5, 2022				15219.0
		227		Letter Updated August 30, 2	2024 Prior Letters dated June 10, 2022			
	Villages at Sterling Ranch PUD and Final Plat	High Density Units (1.934 acres irrigation)	67.64		16, 2022 April, 2024			20292.0
		(1.754 acres inigation)					Note prior commitment for elementary school in Branding Iron	
	Sterling Ranch East Preliminary Phase One	761	335.68	Letter dated June 10, 2022 Revision October 18, 2022			No 2	100704.0
		(28.31 acres irrigation) 35 acre K-8 School						
East	Sterling Ranch East Filing No 1				294 SFE, 18.809 acres irrigated	144.15	Letter dated November 15,	
Ch E	Sterling Ranch East Filing 1A						2022	
Ranch					42 lots; 1.088 acres irrigation	16.85	Letter dated November 15, 2022	
Sterling I	Sterling Ranch East Preliminary Filing 5	160		Letter dated August 11,				
Ste	Sterning Kanen Last Frenhundry Filing 5	(plus 2.42 AF Irrigation)	57.08	2023				17124
,U		4.07	1.71		Commercial/Industrial 0.25			
Rhetoric	Lot 1 Sterling Crushing Facility SDP	4.27	1.51		acres Irrigation			453
Ř				Deviced U. dev. C.				
â	Retreat at PraireRidge Filing No 1-3 Preliminary Plan	193	70.93	Revised Update September 11, 2024				21279
Ridge					o 6 large rural lots that wil have private th Case 24 CW 3007 Pending. 4.8 Ann			
irie F					th Case 24 CW 3007 Pending. 4.8 Ann upport augmentation for the 5 large lots		and has been set aside (snown	
(Pra								
Jaynes (Prairie Ridge)								
Jay								
							-	
		Total	Findings at Prelin	nmary	1	fotal Findings at Fin	al	
Totals	Total Active Commitments Either actual Finding of Sufficiency or	Units 2109.8	AF 846.28		Units 533.7	AF 187.593		Total Volume 310267.7
۴	anticipated Finding	2109.0	040.20			107.393		310267.7 300-year
L				Total Active Cor	nmitments (AF-year)	1033.87		
	-						-	

Specific Note 1; Lolts 147 -157 were previously platted as lots 22-32 Sterling Ranch Filing No. 2 Water was committed under Sterling Ranch Filing No 2

General Note 1. As of January 1, 2022 the Falcon Area Water and Wastewater Authority is managing all water among various Districts, who are participating agencies. Therefore, water accounting changes were adopted on January 1, that do not separately balance or account for separate water accounting within the respective area. Going forward, the commitment sheet will be streamlined by simply adding the total commitments across the FAWWA participating entities.


General Note 2: <u>Sketch Plans do not have hard commitments and are not shown here</u>. Subdivisions can either have a finding of sufficiency at preliminary or final plat stage. Water reports/commitments are sometimes submitted at both stages, even though sufficiency might be achieved at different stages. In order to attempt to track this possible discrepancy we will show the active water commitment in yellow highlight as best as possible. Summation of active water commitments will only track the totals highlighted in yellow. If/when a submitted preliminary plan commitment does not result in a finding of sufficiency and an ensuing finding occurs at final plat, only the final commitment will be tallied.

General Note 3; Yellow highlight signifies applicable commitments, where commitments have been over-riden, changed or modified and are no longer active, they are not highlighted in yellow

Gneral Note 4; March 6, 2023 was a vacation and replat within Homestead at Sterling Ranch No 2 resulting in a net loss of 2 lots, therefore a negative allocation has been applied

Respec Inc

APPENDIX G WATER SUPPLY SUMMARY FORM





RESPEC.COM

WATER SUPPLY INFORMATION SUMMARY

Section 30-28-133,(d), C.R.S. requires that the applicant submit to the County, "Adequate evidence that a Water supply that

is sufficient in terms of quantity, quality, and dependability will be available to ensure an adeuate supply of water"

1. NAME OF DEVELOPMENT A	AS PROPOSED						<u>Retreat at PrairieRidge F</u>	-ilings No 1	<u>I-3</u>
2. LAND USE ACTION							Preliminary Pla	an	
3. NAME OF EXISTING PARCE	L AS RECORD	ED			<u>N/A</u>				
SUBDIVISION	See Above	FILING	Preliminary	BLOCK	All	Lot	<u>All</u>		
4. TOTAL ACERAGE	<u>108.89</u>	5. NUMBER	R OF LOTS PROPOSE	D	<u></u> <u>193</u>	PLAT M	APS ENCLOSED	√ YES F	Preliminary Plan Separate Cover
6. PARCEL HISTORY - Please a	ttach copies of de	eds, plats, or ot	her evidence or documen	tation. (In su	bmittal package)				
A. Was parcel recorded with c					✓ YES	NO			
B. Has the parcel ever been pa	art of a division	of land actic	on since June 1, 1972	?			VES NO		
If yes, describe the previou	s action								
7. LOCATION OF PARCEL - In	clude a map del	liniating the pr	oject area and tie to a	section corner.	(In submittal)				
<u>portion</u> OF <u>NW/4</u>	SECTION 2	8 and a potrtic	on OF NW/4 of SECTION	ON <u>33</u> 7	ownship <u>12</u>		N	R	XANGE <u>65</u> E
OF 1SECTION	TOWNS	SHIP		_					
PRINCIPAL MERIDIAN:			✓ 6TH	N.M.	✓ UTE	E	COSTILLA		
8. PLAT - Location of all wells of	n property must	be plotted an	d permit numbers prov	ided.					
Surveyors plat			YES	NO			If not, scaled hand -drawn sketch	✓ YES	NO N/A
9. ESTIMATED WATER REQU	REMENTS - Ga	allons per Day	or Acre Foot per Year				10. WATER SUPPLY SOURCE	D	ENVER BASIN
							EXISTING DEVELOP	PED	NEW WELLS
HOUSEHOLD USE #	193	_of units	60,376	GPD GPD	67.63	AF	WELLS SPRING Well Permit Numbers	5	Proposed Aquifers - (Check One) Alluvial Upper Arapahoe
- COMMERCIAL USE #		Acres		GPD GPD		_AF	<u>LFH 80131-F</u> <u>Arapahoe 80132-F</u>		Upper Dawson Lower Arapahoe
IRRIGATION # **	1.32	acres	2,946	GPD	3.30	AF			Denver Dakota
STOCK WATERING #		_of head		GPD		AF	✓ MUNICIPAL		WATER COURT DECREE CASE NUMBERS
OTHER				GPD		AF	✓ COMPANY✓ DISTRICT		<u>23 CW 3009; 24 CW 3007 Pending</u> 07 CW 56; 08 CW-113; 08 CW -018
TOTAL -			63,322	GPD	70.93	AF			<u>86 CW -019, 17 CW 3002, 18 CW 3002</u>
							NAME_Falcon Area Water and Wastewater Authority		<u>20 CW 3059, 93 CW 018, 85 CW 131</u>
*Irrigation for common are	a active land	Iscaping					LETTER OF COMMITMENT FOR SERVICE YES	NO	<u>1689 BD, 1690 BD, 1691 BD</u>
11. ENGINEER'S WATER SUP	PLY REPORT		✓ YES	NO		lf yes, ple	ase forward with this form. (This may be re	equired befor ou	r review is completed)
12. TYPE OF SEWAGE DISPO	SAL SYSTEM		Central Sewer	plus 6 sept	<u>ic</u>				
SEPTIC TANK/LEACH	H FIELD						ITRAL SYSTEM - DISTRICT NAME	E:	Falcon Area Water and Watsewater
						VAL	ILT - LOCATION SEWAGE HAULED	D TO:	Authority
✓ ENGINEERED SYSTI	EM (Attach a	copy of eng	gineering design)				IER:		