



INNOVATIVE DESIGN. CLASSIC RESULTS.

**PRELIMINARY DRAINAGE REPORT
FOR
RETREAT AT PRAIRIERIDGE FILINGS 1-3
PRELIMINARY PLAN
(Formerly known as Jaynes Property – SKP-225)**

Prepared for:

CLASSIC COMPANIES

2138 FLYING HORSE CLUB DRIVE
COLORADO SPRINGS CO 80921
(719) 592-9333

Prepared by:

CLASSIC CONSULTING

619 N. CASCADE AVE SUITE 200
COLORADO SPRINGS CO 80903
(719) 785-0790


Job No. 1305.10
PCD File No. SP239



**PRELIMINARY DRAINAGE REPORT FOR
RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN**

ENGINEER'S STATEMENT:

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors, or omissions on my part in preparing this report.



Marc A. Whorton, Colorado P.E. #37155

7/15/2024
Date

OWNER'S/DEVELOPER'S STATEMENT:

I, the owner/developer, have read and will comply with all of the requirements specified in this drainage report and plan.

Business Name: CLASSIC COMPANIES

By: 

Title: VICE PRESIDENT

Address: 2138 Flying Horse Club Drive

Colorado Springs, CO 80921

EL PASO COUNTY:

Filed in accordance with the requirements of the Drainage Criteria Manual, Volumes 1 and 2, El Paso County Engineering Criteria Manual and Land Development Code as amended.

Joshua Palmer, P.E.
County Engineer / ECM Administrator

10/30/2024

Date

Conditions:



PRELIMINARY DRAINAGE REPORT FOR RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN

TABLE OF CONTENTS:

PURPOSE	Page 1
GENERAL DESCRIPTION	Page 1
EXISTING DRAINAGE CONDITIONS	Page 2
PROPOSED DRAINAGE CHARACTERISTICS	Page 8
DETENTION FACILITIES / STORMWATER QUALITY	Page 18
DRAINAGE CRITERIA	Page 19
FLOODPLAIN STATEMENT	Page 21
DRAINAGE AND BRIDGE FEES	Page 22
SUMMARY	Page 22
REFERENCES	Page 23

APPENDICES

VICINITY MAP
SOILS MAP (S.C.S. SURVEY)
F.E.M.A. MAP
WETLANDS JURISDICTIONAL DETERMINATION (JD)
HYDROLOGIC / STORMWATER QUALITY CALCULATIONS
DRAINAGE MAPS



PRELIMINARY DRAINAGE REPORT FOR RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN

PURPOSE

The intent of the owner/developer is to develop the PrairieRidge Filing No. 1 Property. The purpose of this Preliminary Drainage Report, as part of the Preliminary Plan submittal, is to identify all drainage features and facilities and to estimate peak rates of stormwater runoff, from on-site and off-site sources. Also, the purpose is to outline the necessary improvements to safely route developed storm water runoff to adequate outfall facilities. The drainage improvements proposed in this report are preliminary in nature and final drainage reports are required upon any development within the property that detail the 'to be constructed' drainage systems and detention ponds.

GENERAL DESCRIPTION


PrairieRidge Filing No. 1 Preliminary Plan covers the majority of the property in 108.89 acres, as located in a portion of sections 28 and 33, township 12 south, range 65 west of the sixth principal meridian. The site is bounded on the north by Poco Road, to the south and east by Vollmer Road and to the west by existing platted large lot residential subdivisions. The site is within the upper portion of the Sand Creek drainage basin. The proposed uses as shown on the Sketch Plan are as follows: Varying density single family residential developed as (6) 2.5-ac. rural lots, (17) 0.5-ac. urban lots, (170) RS-6000 zoned urban lots and neighborhood parks, open space/greenway buffers and detention pond. The total number of residential units proposed is 193. Roadway access will be from Vollmer Road, the proposed Briargate Parkway extension with only the (6) 2.5-ac. rural lots accessed from Poco Road.

The average soil condition reflects Hydrologic Group "B" (Pring coarse sandy loam) as determined by the "Soil Survey of El Paso County Area," prepared by the Soil Conservation Service (see map in Appendix).



EXISTING DRAINAGE CONDITIONS

This property is located in the upper reaches of the Sand Creek Basin. Existing conditions in this basin are largely rolling hills vegetated with native grasses, yucca and sparse pine trees on the northwestern portion of the site with natural ravines and swales with little to no trees on the south portion of the property. Existing slopes range from 20% to 2% across the site. The entire property generally drains in a southerly direction through numerous natural ravines created from the off-site flows north of Poco Road. This property is not specifically discussed in the Sand Creek DBPS (March 1996), however, improvements along Vollmer Road to handle flows from and through the property are detailed on the following excerpt from the DBPS. The



existing culvert crossing Vollmer Road is shown to be replaced with a 60" CMP for 100-yr capacity. This improvement along with the downstream channel improvements within the Sterling Ranch properties are currently being constructed as a part of the adjacent Vollmer Road improvements (CDR 21-10) and Homestead North at Sterling Ranch Filing No. 1 development (SF 22-013). These plans also include the construction of public storm sewer within Vollmer



Road to handle the anticipated developed flows from the urbanization of this stretch of the Vollmer Road corridor.

There are three major off-site basins north of Poco Road represented by EX-3, EX-4A and EX-4B. This nomenclature matches this same area as presented in the Sterling Ranch MDDP and the recently approved Jaynes Property MDDP (SKP-225). Currently there are multiple corrugated metal culverts within Poco Road allowing these off-site flows from the north to enter the site. However, a recent site investigation reports that these culverts are badly silted in with minimal flow able to be conveyed. They also appear to only be sized for the smaller storm events. As presented on the drainage map, it is recommended that El Paso County visually inspect these facilities and consider up-sizing for larger storm events based on the current basin hydrology or at a minimum clean out the current facilities to allow for better conveyance. However, no evidence of the road overtopping at these crossing locations was found. This off-site property north of Poco Road seems to be all large lot rural residential with property sizes ranging from 5-acre to 35-acres. As this off-site basin stretches north it starts to get into the Black Forest north of Wildflower Road.

At the northern edge of the property there remains an out parcel with a home accessed from Poco Road that is not a part of this development. This area is also a highpoint in Poco Road and creates the two major natural ravines running north to south through the property. Near the corner of Poco Road and Vollmer Road there is also another exiting home that also accesses Poco Road. This home is part of the development property and will eventually be abandoned and demolished. There are existing natural ravines on both sides of this existing home site that eventually combine into one and continue to travel in a southerly direction through the site towards an on-site stock pond near Vollmer Road. There are no records or design plans for this stock pond. For this existing condition analysis this pond was removed from the project model. In the central portion of the property exists several structures with gravel driveway access directly to Vollmer Road. These structures will also eventually be abandoned and demolished



upon the proposed development. The natural ravine along the western portion of the property travels due south all the way to Vollmer Road. A few minor off-site basins (OS-1 and OS-2) from the neighboring large lot residential development to the west also drain onto the property. The entire site drains towards Vollmer Road and into the side road ditch along the west side of Vollmer. Only a very small portion of the site, represented by Basin EX-D, in the extreme northwest corner of the property sheet flows off-site.

As mentioned earlier, the stretch of Vollmer Road adjacent to the property is planned for widening improvements along with the Sterling Ranch development to the east (Homestead North at Sterling Ranch Filing 1 – SF2213). As recommended in the Final Drainage Report for this project and shown on the street and storm improvement plans for Vollmer Road, multiple storm sewer stubs will be provided for this property and the off-site properties to the north of Poco Road. Given that these facilities are currently under construction and will most likely be in place prior to the development, this report assumes these as existing facilities as described and shown on the maps. Please also reference the Appendix for the Homestead North drainage maps as reference material.

These ravines and stock pond areas contain some wetlands vegetation. These wetlands were field delineated by CORE Consultants, Inc. and provided on the drainage maps as shown. However, a Jurisdictional Determination (Action No. SPA-2022-00123) was provided by the Corps of Engineers finding that none of these wetland areas contain waters of the U.S. As such, these areas are NOT regulated by the U.S. Army Corps of Engineers under Section 404 of the Federal Clean Water Act. (See Appendix for JD) Given the non-jurisdictional status of these wetlands and the urban nature of this development, the majority of the wetlands within the urban lots will be removed with overlot grading, public roadway and utility construction. The future final drainage report(s) will better define the extent of any wetland mitigation along with possible monitoring/mitigation on the high groundwater areas.



The following descriptions represent the existing on and off-site basins and design points affecting this property:

Design Point E1 ($Q_5 = 14$ cfs, $Q_{100} = 82$ cfs) consists of the approximated 77.0-acre off-site tributary area from Basin EX-4A. As mentioned earlier, this area is developed as large lot residential (lots ranging from 5-acre to 35-acre) all draining towards Poco Road and the existing 24" CMP that is silted in. These off-site flows then enter the property within one of the natural ravines and convey the flows to the south towards the existing stock pond.

Design Point E2 ($Q_5 = 10$ cfs, $Q_{100} = 58$ cfs) consists of the approximated 70.0-acre off-site tributary area from Basin EX-4B. As mentioned earlier, this area is also developed as large lot residential (lots ranging from 5-acre to 35-acre) all draining towards an off-site stock pond at the northwest corner of Poco Road and Vollmer Road. Verified visually in the field, this facility appears to have an 18" CMP outlet crossing Poco Road to the south. These off-site flows then enter the property within one of the natural ravines and convey the flows to the south towards the existing stock pond.

Design Point E3 ($Q_5 = 1$ cfs, $Q_{100} = 7$ cfs) consists of the 3.6-acre tributary area from Basins EX-A and EX-B. This on-site area drains in a southerly direction towards the side road ditch along Vollmer Road and then captured by a Type D CDOT Inlet with a 24" RCP storm outfall. These facilities are detailed in the "Homestead North at Sterling Ranch Filing No. 1" Final Drainage Report and CDs, prepared by JR Engineering, approved Sept. 2022 (SF2213). The location of this facility is represented by Design Point 10 within the Homestead North at Sterling Ranch Filing No. 1 development ($Q_5 = 0.8$ cfs, $Q_{100} = 6.0$ cfs). (See Reference Material in Appendix) These improvements will be constructed with that development and the Vollmer Road improvements and are able to handle the minor additional flow based on capacity of the existing 24" pipe being 21.6 cfs. (See Appendix) The existing 24" CMP culvert near this location will be removed.



Design Point E4 ($Q_5 = 25$ cfs, $Q_{100} = 155$ cfs) consists of the 41.4-acre tributary area from on-site Basin EX-C along with the combined off-site flows from Design Points E1 and E2. These combined flows travel in the natural ravine towards the existing stock pond on-site. As mentioned earlier, this facility was removed for this existing drainage model. The total flows then travel towards Vollmer Road where they are then captured by a (Sterling Ranch designed) 6' diameter overflow Manhole with grate and a 48" RCP storm outfall into the planned Vollmer roadway widening improvements. The location of this facility is represented by Design Point 20 within the Homestead North at Sterling Ranch Filing No. 1 development (**$Q_5 = 27.1$ cfs, $Q_{100} = 190.9$ cfs**). (See Reference Material in Appendix)

Again, these improvements will be constructed with the Homestead North development and the Vollmer Road improvements. The existing 24" CMP culvert near this location will be removed.

Design Point E5 ($Q_5 = 12$ cfs, $Q_{100} = 70$ cfs) consists of the approximated 44.3-acre off-site tributary area from Basin EX-3. As mentioned earlier, this area is developed as large lot residential (lots ranging from 5-acre to 35-acre) all draining towards Poco Road and the existing 24" CMP that is silted in. These off-site flows then enter the property within the westerly natural ravine and convey the flows to the south through the property.

Design Point E6 ($Q_5 = 2$ cfs, $Q_{100} = 13$ cfs) consists of the 8.3-acre tributary area from the minor on-site Basin EX-G. These pre-developed flows travel in a southerly direction towards the road side ditch along the west side of Vollmer Road. An existing CDOT Type D inlet (Sterling Ranch designed) captures these flows and routes them under Vollmer Road in a 24" RCP system. The location of the CDOT Type D Inlet facility is represented by Design Point 10 within the Homestead at Sterling Ranch Filing No. 1 development (**$Q_5 = 4.8$ cfs, $Q_{100} = 26.3$ cfs**). (See Reference Material in Appendix)



Design Point E7 ($Q_5 = 1$ cfs, $Q_{100} = 10$ cfs) consists of the 6.5-acre tributary area from the minor on-site Basin EX-H. These pre-developed flows travel in a southerly direction towards the road side ditch along the west side of Vollmer Road. An existing CDOT Type C inlet (Sterling Ranch designed) captures these flows and routes them under Vollmer Road in an 18" RCP system. The location of this CDOT Type C Inlet facility is represented by Design Point 11 within the Homestead at Sterling Ranch Filing No. 1 development ($Q_5 = 2.2$ cfs, $Q_{100} = 12.3$ cfs). (See Reference Material in Appendix)

Design Point E8 ($Q_5 = 20$ cfs, $Q_{100} = 125$ cfs) consists of the 72.4-acre tributary area from the on-site Basin EX-E, the off-site basin OS-2 (5.3 ac.) along with the flows from Design Point E5. These combined flows travel in a southerly direction within the on-site natural ravines towards the side road ditch along Vollmer Road and an existing 24" RCP culvert. This facility seems to be silted in and thus conveys little flow. Rather, the flows continue to be conveyed by the ditch in a southeasterly direction along the north side of Vollmer Road into basin EX-F.

Design Point E9 ($Q_5 = 20$ cfs, $Q_{100} = 127$ cfs) consists of the 8.7-acre tributary area from the on-site Basin EX-F, the off-site basin OS-1 (2.0 ac.) along with the flows from Design Point E8. These combined flows travel in a southeasterly direction within the side road ditch along Vollmer Road to the corner of the property. At this location, within the sideroad ditch and ROW for Vollmer Road, an exist. modified 4'x14' CDOT Type D Inlet was constructed along with the Homestead at Sterling Ranch Filing No. 1 Development to capture these off-site flows. This facility has an existing 54" public RCP storm outfall that crosses Vollmer Road and passes through the Homestead at Sterling Ranch Filing No. 1 development and daylights directly into Sand Creek. The location of the CDOT Type D Inlet facility is represented by Design Point 12 within the Homestead at Sterling Ranch Filing No. 1 development ($Q_5 = 18.9$ cfs, $Q_{100} = 133.7$ cfs). (See Reference Material in Appendix)



Design Point E10 ($Q_5 = 0.4$ cfs, $Q_{100} = 3$ cfs) consists of the 1.3-acre tributary area from the on-site Basin EX-D. This minor portion of the property sheet flows off-site into a natural ravine and then into a private stock pond on Lot 3A or Sunrise Meadow Subd. No. 2.

PROPOSED DRAINAGE CONDITIONS

Development within the proposed Preliminary Plan is planned for urban residential with associated curb, gutter, sidewalk and paved streets, other than the 6 rural 2.5-ac. lots accessed directly off the existing Poco Road (Rural Local Gravel). Overlot grading is anticipated for the majority of the development along with installation of urban services provided through the Falcon Area Water and Wastewater Authority (FAWWA). Proposed impervious areas will sheet flow across yards and landscape areas to slow runoff and increase time of concentration. This will minimize the effects of impervious areas. At design points where developed flows are greater than in the existing condition, detention facilities will be proposed providing an Excess Urban Runoff Volume (EURV) in the lower portion of the facility storage volume with an outlet control device. Frequent and infrequent inflows are released at rates approximating undeveloped conditions. This concept provides some mitigation of increased runoff volume by releasing a portion of the increased runoff at a low rate over an extended period of time, up to 72 hours. This means that frequent storms, smaller than the 2 year event, will be reduced to very low flows near or below the sediment carrying threshold value for downstream drainage ways. Also, by incorporating an outlet structure that limits the 100-year runoff to the undeveloped condition rate, the discharge hydrograph for storms between the 2 year and the 100 year event will approximate the hydrograph for the undeveloped conditions and will help effectively mitigate the effects of development. Prior to development within this property, final drainage reports and construction plans will be required detailing the requirements and specifics of proposed facilities.



Per the Sand Creek DBPS, this area was planned for both large lot residential and single family residential. There were no recommendations for detention facilities within the area but due to current drainage criteria, detention/stormwater quality facilities are proposed. The following are preliminary design points for developed conditions with descriptions of anticipated basin areas and preliminary storm systems:

As described in the recently approved Jaynes Property MDDP and the Homestead North at Sterling Ranch Filing No. 1 FDR, the eastern portion of this proposed development and the existing rural large lots northeast of Poco Road have been accounted for in the off-site FSD Pond C, located just northeast of the intersection of Briargate Pkwy. and Wheatland Dr., constructed with the Homestead North at Sterling Ranch Filing No. 1 development. Existing storm systems within the property and stubbed across Vollmer Road will collect these flows and convey them to this facility. The following basin descriptions are tributary to this facility:

Tributary area to Homestead North Filing No. 1 FSD Pond C

Design Point 1 ($Q_5 = 13$ cfs, $Q_{100} = 79$ cfs) consists of off-site flows from Basin EX-4A north of Poco Road and developed flows from Basin A. These combined flows will be collected by a 36" RCP within a drainage tract maintained by the Metro District and routed further downstream in the proposed public storm system within the roadway. **Design Point 2 ($Q_5 = 10$ cfs, $Q_{100} = 58$ cfs)** consists of off-site flows from Basin EX-4B north of Poco Road and developed flows from Basin B. These combined flows will also be collected by a 36" RCP within a drainage tract maintained by the Metro District and routed further downstream in the proposed public storm system within the roadway.

Design Point 3 ($Q_5 = 4$ cfs, $Q_{100} = 16$ cfs) consists of developed flows from Basin C1. At this location, a 10' Type R at-grade inlet will collect a portion of the flows. These collected flows will



be routed further downstream via an 18" RCP. The bypass flows will then travel to DP-4. **Design Point 4 ($Q_5 = 2$ cfs, $Q_{100} = 13$ cfs)** consists of developed flows from Basin C2 and the flow-by from DP-3. At this location, a 10' Type R sump inlet will completely collect these flows. **Design Point 5 ($Q_5 = 1.4$ cfs, $Q_{100} = 4$ cfs)** consists of developed flows from Basin D. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is around the corner and south down Bluebell Meadow Way.

Design Point 6 ($Q_5 = 5$ cfs, $Q_{100} = 12$ cfs) consists of developed flows from Basin E. At this location, a 10' Type R at-grade inlet will collect a portion of the flows. These collected flows will be routed further downstream via an 18" RCP. The bypass flows will enter Basin J and then travel to DP-11.

Design Point 7 ($Q_5 = 2.2$ cfs, $Q_{100} = 5$ cfs) consists of developed flows from Basin F. At this location, a 10' Type R at-grade inlet will collect a portion of the flows. These collected flows will be routed further downstream via an 18" RCP. The bypass flows will also enter Basin J and travel to DP-11.

Design Point 8 ($Q_5 = 3$ cfs, $Q_{100} = 6$ cfs) consists of developed flows from Basin G. At this location, a 5' Type R sump inlet will completely collect these flows. With a max. 100-yr. ponding depth of 9", the emergency overflow route is over the curb to the south and into Dines Blvd.

Design Point 9 ($Q_5 = 5$ cfs, $Q_{100} = 10$ cfs) consists of developed flows from Basin H. At this location, a 10' Type R sump inlet will completely collect these flows. **Design Point 10 ($Q_5 = 1.8$ cfs, $Q_{100} = 4$ cfs)** consists of developed flows from Basin I. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the highpoint to the east within Sunlit Prairie Place.



Design Point 11 ($Q_5 = 7$ cfs, $Q_{100} = 20$ cfs) consists of developed flows from Basin J and flow-by from DP-6 and DP-7. At this location, a 10' Type R sump inlet will completely collect these flows.

Design Point 12 ($Q_5 = 3$ cfs, $Q_{100} = 5$ cfs) consists of developed flows from Basin K. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within a drainage easement. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the curb to the south and into Basin M.

Design Point 13 ($Q_5 = 3$ cfs, $Q_{100} = 6$ cfs) consists of developed flows from the north half of Basin N. At this location, an 18" RCP storm stub is provided for that portion of the future development.

Design Point 14 ($Q_5 = 3$ cfs, $Q_{100} = 6$ cfs) consists of developed flows from the south half of Basin N. At this location, a 24" RCP storm stub is provided for that portion of the future development.

Design Point 15 ($Q_5 = 2$ cfs, $Q_{100} = 13$ cfs) consists of developed flows from Basin M. At this location, an existing manhole with grated lid was anticipated to and will collect these developed flows. These flows are then combined with the on-site routed storm system (48" RCP) and connected to the 48" RCP stub provided with the construction of the Vollmer Road improvements and Homestead North at Sterling Ranch Filing No. 1, as mentioned earlier. **The following shows a comparison of the total developed flows leaving the site at this location and tributary to the off-site FSD Pond C:**

Proposed Developed Flows:

$Q_5 = 36$ cfs, $Q_{100} = 158$ cfs

Flows per Homestead North Fil. 1:

$Q_5 = 27.1$ cfs, $Q_{100} = 190.9$ cfs

(See Appendix for Area Runoff/effective imperviousness tributary to this off-site existing facility)



Pipe Run 24 ($Q_5 = 36$ cfs, $Q_{100} = 158$ cfs) represents the total developed flows tributary to the existing 48" RCP storm outfall mentioned earlier at this location, represented by Design Point 20 within the Homestead North at Sterling Ranch Filing No. 1 development (**$Q_5 = 27.1$ cfs, $Q_{100} = 190.9$ cfs**). These total off-site flows, along with collected flows from the Vollmer Road improvements, then travel via an existing 60" RCP (Sterling Ranch designed) south down Vollmer then southeast down Briargate Parkway towards Pond C just north of Briargate Parkway and west of Sand Creek within the Homestead North Filing No. 1 development. (See Reference Material in Appendix) This is the maximum developed flows allowed to be released at this location and treated further downstream in Pond C with the Sterling Ranch Development. The final design for this area must follow this maximum flow and percent impervious as described in the Homestead North FDR. (See Appendix for applicable reference material) At the MDDP and PDR level of design, the total anticipated off-site flows from this property are fairly consistent with what was previously shown in the Homestead North Filing No. 1 FDR. However, the percent impervious is higher as the Homestead North FDR assumed all the off-site area as undeveloped, whereas the following chart better defines the developed imperviousness for this property. The intent of this PDR is to maintain what was previously planned for the total off-site flows and imperviousness tributary to Pond C. The final drainage report(s) for the property will better define the exact flow amounts being released along with site imperviousness based on a formalized site plan. At that time, it will be determined if additional developed property within this development will need to be routed elsewhere to remain consistent with the approved Pond C design and outlet structure.

Tributary area to proposed on-site FSD Pond 1

Design Point 16 ($Q_5 = 2$ cfs, $Q_{100} = 12$ cfs) consists of off-site flows from Basin EX-3A and developed flows from Basin R. These combined flows will travel within the public drainage easement and routed further downstream towards DP 17. **Design Point 17 ($Q_5 = 14$ cfs, $Q_{100} = 84$ cfs)** consists of off-site flows from Basin EX-3 north of Poco Road, developed flows from Basin



S and then the previously described DP-16. These combined flows will then be collected by a 36" RCP within a drainage tract maintained by the Metro District and routed further downstream in the proposed public storm system within the roadway.

Design Point 18 ($Q_5 = 4$ cfs, $Q_{100} = 12$ cfs) consists of developed flows from Basin U. At this location, a 10' Type R sump inlet will completely collect these flows. **Design Point 19 ($Q_5 = 1.6$ cfs, $Q_{100} = 3$ cfs)** consists of developed flows from Basin V. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is around the corner and south down Foxglove Field Dr. **Pipe Run 28 ($Q_5 = 18$ cfs, $Q_{100} = 94$ cfs)** represents the total developed flows within the public 42" RCP storm system at this point.

Design Point 20 ($Q_5 = 7$ cfs, $Q_{100} = 17$ cfs) consists of developed flows from Basin W. At this location, a 10' Type R sump inlet will completely collect these flows. **Design Point 21 ($Q_5 = 0.5$ cfs, $Q_{100} = 1.2$ cfs)** consists of developed flows from Basin X. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the highpoint in the roadway and southwest down Sunlit Prairie Place. **Pipe Run 31 ($Q_5 = 7$ cfs, $Q_{100} = 18$ cfs)** represents the total developed flows within the public 30" RCP storm system at this point.

Design Point 22 ($Q_5 = 4$ cfs, $Q_{100} = 12$ cfs) consists of developed flows from Basin Y. At this location, a 10' Type R sump inlet will completely collect these flows. **Design Point 23 ($Q_5 = 2$ cfs, $Q_{100} = 6$ cfs)** consists of developed flows from Basin Z. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is due south within the open space tract



towards Briargate Pkwy. **Pipe Run 35 ($Q_5 = 28$ cfs, $Q_{100} = 120$ cfs)** represents the total developed flows within the public 48" RCP storm system at this point.

Design Point 24 ($Q_5 = 2$ cfs, $Q_{100} = 8$ cfs) consists of developed flows from off-site basin OS-2A and Basin AA. At this location, a CDOT Type C sump inlet will completely collect these flows.

Design Point 25 ($Q_5 = 1$ cfs, $Q_{100} = 6$ cfs) consists of developed flows from off-site Basin OS-2B and Basin BB. At this location, another CDOT Type C inlet will completely collect these flows. The collected flows from these sump conditions will then be routed further downstream within a private storm system within a drainage easement at the rear of these lots. With a max. 100-yr. ponding depth of 12", the emergency overflow route is due south within the associated drainage easements and then ultimate into Briargate Pkwy. **Pipe Run 37 ($Q_5 = 3$ cfs, $Q_{100} = 13$ cfs)** represents the total developed flows within the private 24" RCP storm system at this point.

Design Point 26 ($Q_5 = 4$ cfs, $Q_{100} = 7$ cfs) consists of developed flows from Basin EE. At this location, a 5' Type R sump inlet will completely collect these flows. **Design Point 27 ($Q_5 = 4$ cfs, $Q_{100} = 11$ cfs)** consists of developed flows from Basin FF. At this location, a 10' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the highpoint to the west and then west in Briargate Pkwy. **Pipe Run 41 ($Q_5 = 7$ cfs, $Q_{100} = 16$ cfs)** represents the total developed flows within the public 24" RCP storm system at this point.

Design Point 28 ($Q_5 = 2$ cfs, $Q_{100} = 6$ cfs) consists of developed flows from Basin CC. At this location, a 5' Type R sump inlet will completely collect these flows. **Design Point 29 ($Q_5 = 2$ cfs, $Q_{100} = 4$ cfs)** consists of developed flows from Basin DD. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the highpoint in the roadway and



south down Dines Blvd. **Pipe Run 45 ($Q_5 = 37$ cfs, $Q_{100} = 145$ cfs)** represents the total developed flows within the public 48" RCP storm system at this point.

Design Point 30 ($Q_5 = 2$ cfs, $Q_{100} = 5$ cfs) consists of developed flows from Basin JJ. At this location, a 5' Type R sump inlet will completely collect these flows. The collected flows from this sump condition within the cul-de-sac will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the curb and south down Dines Blvd. **Pipe Run 47 ($Q_5 = 39$ cfs, $Q_{100} = 147$ cfs)** represents the total developed flows within the public 48" RCP storm system at this point.

Design Point 31 ($Q_5 = 4$ cfs, $Q_{100} = 9$ cfs) consists of developed flows from Basin KK. At this location, a 10' Type R at-grade inlet will collect a portion of the flows. These collected flows will be routed further downstream via an 18" RCP. The bypass flows will then travel to DP-32. **Design Point 32 ($Q_5 = 4$ cfs, $Q_{100} = 10$ cfs)** consists of developed flows from Basin LL and flow-by from DP-31. At this location, a 10' Type R at-grade inlet will collect a portion of the flows. These collected flows will be routed further downstream via an 18" RCP. The bypass flows will then travel to DP-34. **Pipe Run 51 ($Q_5 = 44$ cfs, $Q_{100} = 156$ cfs)** represents the total developed flows within the public 48" RCP storm system at this point.

Design Point 33 ($Q_5 = 6$ cfs, $Q_{100} = 11$ cfs) consists of developed flows from Basin NN. At this location, a 10' Type R sump inlet will completely collect these flows. **Design Point 34 ($Q_5 = 5$ cfs, $Q_{100} = 13$ cfs)** consists of developed flows from Basin MM and the flow-by from DP-32. At this location, a 10' Type R sump inlet will completely collect these flows. The collected flows from this sump condition will then be routed further downstream within a public storm system within the roadway. With a max. 100-yr. ponding depth of 12", the emergency overflow route is over the highpoint to the southeast and then southwest down Vollmer Road. **Pipe Run 56 ($Q_5 = 56$ cfs, $Q_{100} = 185$ cfs)** represents the total developed flows within the public 54" RCP storm system at this point.



Design Point 35 ($Q_5 = 8$ cfs, $Q_{100} = 18$ cfs) consists of approximately half of Basin II. Exact tributary area will be better defined with the FDR. At this location, a proposed 30" RCP storm stub will be provided to handle a portion of the future PUD development. **Design Point 36 ($Q_5 = 8$ cfs, $Q_{100} = 18$ cfs)** consists of the other half of Basin II. Again, the exact tributary area will be better defined with the FDR. At this location, a proposed 30" RCP storm stub will be provided to handle this portion of the future PUD development.

Design Point 37 ($Q_5 = 14$ cfs, $Q_{100} = 30$ cfs) consists of the anticipated Basin O. Exact tributary area will be better defined with the FDR. At this location, a proposed 30" RCP storm stub will be provided to handle this portion of the future PUD development. **Design Point 38 ($Q_5 = 9$ cfs, $Q_{100} = 21$ cfs)** consists of the anticipated Basin P. Exact tributary area will be better defined with the FDR. At this location, a proposed 30" RCP storm stub will be provided to handle the future Commercial development. **Design Point 39 ($Q_5 = 5$ cfs, $Q_{100} = 11$ cfs)** consists of developed flows from Basin GG. At this location, a 15' Type R at-grade inlet will collect a portion of the flows. These collected flows will be routed further downstream via an 18" RCP. The bypass flows will then travel south in Vollmer Road. **Design Point 40 ($Q_5 = 5$ cfs, $Q_{100} = 9$ cfs)** consists of developed flows from Basin HH. At this location, a 15' Type R at-grade inlet will collect a portion of the flows. These collected flows will be routed further downstream via an 18" RCP. The bypass flows will then travel around the corner down Vollmer Road. **Pipe Run 62 ($Q_5 = 28$ cfs, $Q_{100} = 61$ cfs)** represents the total developed flows within the public 36" RCP storm system at this point.

Design Point 41 ($Q_5 = 4$ cfs, $Q_{100} = 8$ cfs) consists of developed flows from Basin OO. At this location, a 10' Type R sump inlet will completely collect these flows. The collected flows from this sump condition within the cul-de-sac will then be routed further downstream within a public storm system within the park tract. With a max. 100-yr. ponding depth of 9", the emergency overflow route is over the curb and south within the park. **Design Point 42 ($Q_5 = 4$ cfs, $Q_{100} = 15$ cfs)** consists of developed flows from off-site basin OS-2C and Basins PP, UU and TT. At this



location, a CDOT Type C sump inlet will completely collect these flows. **Design Point 43 ($Q_5 = 1$ cfs, $Q_{100} = 5$ cfs)** consists of developed flows from off-site Basin OS-1A and Basin QQ. At this location, another CDOT Type C inlet will completely collect these flows. The collected flows from these sump conditions will then be routed further downstream within a private storm system within a drainage easement at the rear of these lots. With a max. 100-yr. ponding depth of 12", the emergency overflow route is due south within the associated drainage easements and then ultimate into the proposed pond. **Pipe Run 69 ($Q_5 = 8$ cfs, $Q_{100} = 26$ cfs)** represents the total westerly developed flows discharging into the proposed FSD Pond 1. This outfall will include the design of the required concrete forebay. However, the final design for these facilities will be provided with the FDR. **Pipe Run 65 ($Q_5 = 84$ cfs, $Q_{100} = 244$ cfs)** represents the total easterly developed flows discharging into the proposed FSD Pond 1. This outfall will include the design of the required concrete forebay. However, the final design for these facilities will also be provided with the FDR. **The following shows a comparison of the total developed flows tributary and released from the proposed FSD Pond 1 at Design Point 44, including Basin RR:**

Proposed Developed Flows:

$Q_5 = 93$ cfs, $Q_{100} = 279$ cfs

Flows per Jaynes MDDP:

$Q_5 = 69$ cfs, $Q_{100} = 222$ cfs

(See Appendix for Area Runoff/effective imperviousness tributary to this off-site existing facility)

Proposed Release:

$Q_5 = 16.4$ cfs, $Q_{100} = 126.3$ cfs

Prop. Release per Homestead North Fil. 1 FDR:

$Q_5 = 18.9$ cfs, $Q_{100} = 133.7$ cfs



DETENTION FACILITIES / STORMWATER QUALITY

Final design of this recommended facility that include planning for water quality management of storm water runoff features will be designed during final design and construction of the proposed improvements. Storm water quality measures will be utilized in order to reduce the amount of sediment, debris and pollutants that are allowed to enter Sand Creek. These features include but are not limited to Full Spectrum Extended Detention Basin Sedimentation Facilities, Sand Filter Basins, and Rain Gardens. Site Planning and design techniques should limit impervious area, minimize directly impervious area, lengthen time of travel and increase infiltration in order to decrease the rate and volume of stormwater runoff. Facilities that require detention will provide an Excess Urban Runoff Volume (EURV) in the lower portion of the facility storage volume that will release the more frequent storms at a slower rate to help minimize the effects of development of the Jaynes Property. These measures will be taken into consideration upon final design of the individual detention facilities as well as the development of the individual land uses within the Jaynes Property.

The proposed Pond 1 is intended to provide detention and stormwater quality for nearly the entire western portion of the property, including the off-site basin EX-3 north of Poco Road and excluding Basin L (1.3 Ac.) and any area that is tributary and being treated by the off-site Pond C within the Sterling Ranch Development as described above. The total anticipated developed flows entering this facility are as follows:

(See Appendix for MHFD-Detention pond design sheets):



Pond 1 (Full Spectrum EDB)

Total Tributary Acreage: 144.43 ac.

Total Site Impervious tributary to Pond 1: 32.6%

1.918 Ac.-ft. WQCV required

2.946 Ac.-ft. EURV required with 4:1 max. slopes

5.242 Ac.-ft. 100-yr. required storage

10.106 Ac.-ft. required total

11.262 Ac.-ft. provided

Total Peak In-flow: $Q_5 = 93$ cfs, $Q_{100} = 279$ cfs

Pond Peak Design Release: $Q_5 = 16.4$ cfs, $Q_{100} = 126.3$ cfs

Release per Homestead at Sterling Ranch Filing 1 (DP-12): $Q_5 = 18.9$ cfs, $Q_{100} = 133.7$ cfs

This proposed detention facility is to be private with maintenance by the PrairieRidge Metro District with all drainage facilities within the public Right of Way to be public with maintenance by El Paso County. As mentioned previously in this report, just outside of the very southwest corner of the property, within the Vollmer Road ROW exists a (Sterling Ranch designed) 4'x14' modified CDOT Type D inlet with a 54" RCP storm outfall. This facility was planned to accept and convey treated developed flows per the "Homestead at Sterling Ranch Filing No. 1" Final Drainage Report and CDs (SF1725), prepared by M&S Civil Consultants, Inc. approved Nov. 2018. It is anticipated that the proposed Pond 1 storm outfall will connect directly to this facility. These flows are then routed via the existing 54" RCP storm system (maintained by Sterling Ranch Metro. District) directly to Sand Creek.

DRAINAGE CRITERIA

Hydrologic calculations were performed using the City of Colorado Springs/El Paso County Drainage Criteria Manual, as revised in November 1991 and October 1994 with County adopted Chapter 6 and Section 3.2.1 of Chapter 13 of the City of Colorado Springs/El Paso County Drainage Criteria Manual as revised in May 2014. Individual basin design used for detention/SWQ basin



sizing was calculated using the Rational Method. Runoff Coefficients are based on the imperviousness of the particular land use and the hydrologic soil type in accordance with Table 6-6. The average rainfall intensity, by recurrence interval found in the Intensity-Duration-Frequency (IDF) curves in Figure 6-5. Mile High Flood District (MHFD)-Detention spreadsheet Ver. 4.05 used for Preliminary Detention/SWQ design. (See Appendix)

The City of Colorado Springs/El Paso County DCM requires the Four Step Process for receiving water protection that focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainage ways, and implementing long-term source controls. The Four Step Process pertains to management of smaller, frequently occurring storm events, as opposed to larger storms for which drainage and flood control infrastructure are sized. Implementation of these four steps helps to achieve storm water permit requirements.

This site adheres to this **Four Step Process** as follows:

1. **Employ Runoff Reduction Practices:** Proposed urban lot impervious areas (roof tops, patios, etc.) will sheet flow across landscaped yards and through open space areas to slow runoff and increase time of concentration prior to being conveyed to the proposed public streets or detention facilities. This will minimize directly connected impervious areas within the project site.
2. **Stabilize Drainageways:** The two major natural drainageways on-site within basins A, G and J will be overlotted graded and urbanized with the proposed residential development. Within this development, urban street sections will be constructed along with buried storm systems to handle the developed runoff. The larger residential lots towards the north portion of these basins will be planned such to adequately accept these off-site flows within their natural corridors. The final drainage report(s) will better detail these capture methods and any required improvements to do so along with necessary hydraulic



analysis and emergency overflow routing methods per County standards. After developed flows utilize the runoff reduction practices through the front and rear yards, developed flows will travel via curb and gutter within the public streets and eventually public storm systems. These collected flows are then routed directly to the proposed extended detention basin (full-spectrum facility).

3. **Provide Water Quality Capture Volume (WQCV):** Runoff from this development will be treated through capture and slow release of the WQCV and excess urban runoff volume (EURV) in the proposed Full-Spectrum permanent Extended Detention Basin designed per current El Paso County drainage criteria. The few basins that are not able to be captured and routed to a permanent extended detention basin (T, SS and VV) qualify for exclusions I.7.1.B.5 – Large Lot 2.5 ac. and I.7.1.B.7 – Open Space/buffer tracts.

4. **Consider need for Industrial and Commercial BMPs:** No industrial uses are proposed within this development. However, a site-specific storm water quality and erosion control plan and narrative will be submitted along with the grading and erosion control plan. Details such as site-specific sediment and erosion control construction BMP's as well as temporary and permanent BMP's for commercial use will be detailed in this plan and narrative to protect receiving waters. Multiple temporary BMP's are anticipated based on specific phasing of the overall development. BMP's will be constructed and maintained as the development has been graded and erosion control methods employed.

FLOODPLAIN STATEMENT

No portion of this site is located within a floodplain as determined by the Flood Insurance Rate Maps (F.I.R.M.) Map Numbers 08041C0533G and 0841C0535G, effective date, December 7, 2018 (See Appendix).



DRAINAGE AND BRIDGE FEES

Any applicable fees shall be provided prior to final plat recordation of any development within this site. These fees will be calculated in the FDR(s) for County review and approval.

SUMMARY

The proposed PrairieRidge property development is within the Upper reach of the Sand Creek Drainage Basin. Recommendations are made within this report concerning necessary improvements that may be required as a result of development of this property. The points of storm water release from the proposed site are required to be at or below the calculated historic flow quantities. This development does not impact any downstream facility or property to an extent greater than that which currently exists in the 'historic' conditions. All drainage facilities within this report were sized according to the Drainage Criteria Manuals and the full-spectrum storm water quality requirements. Upon development of the individual parcels within the property, separate Final Drainage Reports will be required to be submitted and approved by El Paso County that details all storm systems, pond design and fee calculation.

PREPARED BY:

Classic Consulting Engineers & Surveyors, LLC



Marc A. Whorton, P.E.
Project Manager

maw/1305.10/130510PDR.doc



REFERENCES

1. City of Colorado Springs/County of El Paso Drainage Criteria Manual as revised in November 1991 and October 1994 with County adopted Chapter 6 and Section 3.2.1 of Chapter 13 of the City of Colorado Springs/El Paso County Drainage Criteria Manual as revised in May 2014.
2. "Urban Storm Drainage Criteria Manual Volume 1, 2 & 3" Urban Drainage and Flood Control District, dated January 2016.
3. "Sand Creek Drainage Basin Planning Study," Kiowa Engineering Corporation, dated March 1996.
4. "2018 Sterling Ranch MDDP", M&S Civil Consultants, Inc., June 2018
5. "Final Drainage Report for Retreat at TimberRidge Filing No. 1", Classic Consulting, approved November, 2020.
6. "Final Drainage Report for Homestead North at Sterling Ranch Filing No. 1", JR Engineering, LLC, dated June 2022
7. "Final Drainage Report for Homestead at Sterling Ranch Filing No. 1", M&S Civil Consultants, Inc. dated Nov. 2018
8. "MDDP Amendment for Sterling Ranch", JR Engineering, LLC, dated June 2022
9. "MDDP for Jaynes Property, Classic Consulting, dated January 18, 2023



APPENDIX

VICINITY MAP


Google Maps Jaynes Property Vicinity Map




Imagery ©2022 CNES / Airbus, Maxar Technologies, USDA/FPAC/GEO, Map data ©2022 500 ft

SOILS MAP (S.C.S SURVEY)

Soil Map—El Paso County Area, Colorado



Soil Map may not be valid at this scale.



MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado
 Survey Area Data: Version 19, Aug 31, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 19, 2018—May 26, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
8	Blakeland loamy sand, 1 to 9 percent slopes	13.2	2.9%
19	Columbine gravelly sandy loam, 0 to 3 percent slopes	7.8	1.7%
71	Pring coarse sandy loam, 3 to 8 percent slopes	433.5	95.4%
Totals for Area of Interest		454.5	100.0%

El Paso County Area, Colorado

71—Pring coarse sandy loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 369k

Elevation: 6,800 to 7,600 feet

Farmland classification: Not prime farmland

Map Unit Composition

Pring and similar soils: 85 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Pring

Setting

Landform: Hills

Landform position (three-dimensional): Side slope

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Arkosic alluvium derived from sedimentary rock

Typical profile

A - 0 to 14 inches: coarse sandy loam

C - 14 to 60 inches: gravelly sandy loam

Properties and qualities

Slope: 3 to 8 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High
(2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water supply, 0 to 60 inches: Low (about 6.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: B

Ecological site: R048AY222CO - Loamy Park

Hydric soil rating: No

Minor Components

Pleasant

Percent of map unit:

Landform: Depressions

Hydric soil rating: Yes

Other soils

Percent of map unit:

Hydric soil rating: No

Data Source Information

Soil Survey Area: El Paso County Area, Colorado

Survey Area Data: Version 19, Aug 31, 2021

F.E.M.A. MAP



NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations (BFEs)** and/or **floodways** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of 0.0' North American Vertical Datum of 1988 (NAVD88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this jurisdiction.

The **projection** used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The **horizontal datum** was NAD83, GRS80 spheroid. Differences in datum, spheroid, projection or UTM zones zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the **North American Vertical Datum of 1988 (NAVD88)**. These flood elevations must be compared to structure and ground elevations referenced to the same **vertical datum**. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov> or contact the National Geodetic Survey at the following address:

NGS Information Services
NOAA, NIMS12
National Geodetic Survey
SSMC-3, #9202
1315 East-West Highway
Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242 or visit its website at <http://www.ngs.noaa.gov>.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, and Anderson Consulting Engineers, Inc. These data are current as of 2008.

This map reflects more detailed and up-to-date **stream channel configurations and floodplain delineations** than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables if applicable, in the FIS report. As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels; community map repository addresses; and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.


Contact **FEMA Map Service Center (MSC)** via the FEMA Map Information eXchange (FIRM) 1-877-336-2627 for information on available products associated with this FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-358-9620 and its website at <http://www.msc.fema.gov>.

If you have **questions about this map** or questions concerning the National Flood Insurance Program in general, please call **1-877-FEMA MAP (1-877-336-2627)** or visit the FEMA website at <http://www.fema.gov/business/nfp>.

El Paso County Vertical Datum Offset Table	
Flooding Source	Vertical Datum Offset (ft)

REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM BY STREAM VERTICAL DATUM CONVERSION INFORMATION


Panel Location Map



This Digital Flood Insurance Rate Map (DFIRM) was produced through a Cooperating Technical Partner (CTP) agreement between the State of Colorado Water Conservation Board (CWCB) and the Federal Emergency Management Agency (FEMA).



Additional Flood Hazard information and resources are available from local communities and the Colorado Water Conservation Board.



THIS PANEL SHOWN AT A SCALE OF 1"=500' ON MAP NUMBER 08041C0533

NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED WITHIN TOWNSHIP 12 SOUTH, RANGE 65 WEST, AND TOWNSHIP 13 SOUTH, RANGE 65 WEST.

LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equalled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

- ZONE A** No Base Flood Elevations determined.
- ZONE AE** Base Flood Elevations determined.
- ZONE AH** Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.
- ZONE AO** Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
- ZONE AR** Special Flood Hazard Area Formerly protected from the 1% annual chance flood by a flood control system that was subsequently decertified. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.
- ZONE A99** Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
- ZONE V** Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.
- ZONE VE** Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.

FLOODWAY AREAS IN ZONE AE
The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.

OTHER FLOOD AREAS
ZONE X Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot, or with drainage areas less than 1 square mile; and areas protected by levees from 1% annual chance flood.

OTHER AREAS
ZONE X Areas determined to be outside the 0.2% annual chance floodplain.
ZONE D Areas in which flood hazards are undetermined, but possible.

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS
OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

- Floodplain boundary
- Floodway boundary
- Zone D Boundary
- CBRS and OPA boundary
- Boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths or flood velocities.
- Base Flood Elevation line and value; elevation in feet* (EL 987)
- Base Flood Elevation value where uniform within zone; elevation in feet*


* Referenced to the North American Vertical Datum of 1988 (NAVD 88)

- Cross section line
- Transsect line
- Geographic coordinates referenced to the North American Datum of 1983 (NAD 83)
- 1000-meter Universal Transverse Mercator grid ticks, zone 13
- 5000-foot grid ticks: Colorado State Plane coordinate system, central zone (FIPSZONE 0502), Lambert Conformal Conic Projection
- Bench mark (see explanation in Notes to Users section of this FIRM panel)
- River Mile

MAP REPOSITORIES
Refer to Map Repositories list on Map Index
EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP
MARCH 17, 1997

EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL
DECEMBER 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

For community map revision history prior to countywide mapping, refer to the Community Map History Table located in the Flood Insurance Study report for this jurisdiction.
To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.



PANEL 0535G

FIRM
FLOOD INSURANCE RATE MAP
EL PASO COUNTY, COLORADO AND INCORPORATED AREAS

PANEL 535 OF 1300
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:	COMMUNITY	NUMBER	PANEL	SUFFIX
COLORADO SPRINGS, CITY OF	08080	0535		G
EL PASO COUNTY	08009	0535		G

Notice to User: The Map Number shown below should be used when placing map orders. The Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
08041C0535G

MAP REVISED
DECEMBER 7, 2018
Federal Emergency Management Agency

NOTES TO USERS

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations (BFEs)** and/or **floodways** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Coastal Base Flood Elevations shown on this map apply only landward of 0.0' North American Vertical Datum of 1988 (NAVD88). Users of this FIRM should be aware that coastal flood elevations are also provided in the Summary of Stillwater Elevations table in the Flood Insurance Study report for this jurisdiction. Elevations shown in the Summary of Stillwater Elevations table should be used for construction and/or floodplain management purposes when they are higher than the elevations shown on this FIRM.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to section 2.4 "Flood Protection Measures" of the Flood Insurance Study report for information on flood control structures for this jurisdiction.

The **projection** used in the preparation of this map was Universal Transverse Mercator (UTM) zone 13. The **horizontal datum** was NAD83, GRS80 spheroid. Differences in datum, spheroid, projection or UTM zones zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the **North American Vertical Datum of 1988 (NAVD88)**. These flood elevations must be compared to structure and ground elevations referenced to the same **vertical datum**. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov/> or contact the National Geodetic Survey at the following address:

NGS Information Services
NOAA, NIMS12
National Geodetic Survey
SSMC-3, #9202
1315 East-West Highway
Silver Spring, MD 20910-3282

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242 or visit its website at <http://www.ngs.noaa.gov/>.

Base Map information shown on this FIRM was provided in digital format by El Paso County, Colorado Springs Utilities, and Anderson Consulting Engineers, Inc. These data are current as of 2008.

This map reflects more detailed and up-to-date **stream channel configurations and floodplain delineations** than those shown on the previous FIRM for this jurisdiction. The floodplains and floodways that were transferred from the previous FIRM may have been adjusted to conform to these new stream channel configurations. As a result, the Flood Profiles and Floodway Data tables in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on this map. The profile baselines depicted on this map represent the hydraulic modeling baselines that match the flood profiles and Floodway Data Tables if applicable, in the FIS report. As a result, the profile baselines may deviate significantly from the new base map channel representation and may appear outside of the floodplain.

Corporate limits shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.

Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels; community map repository addresses; and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.

Contact **FEMA Map Service Center (MSC)** via the FEMA Map Information eXchange (FIRM) 1-877-336-2627 for information on available products associated with this FIRM. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. The MSC may also be reached by Fax at 1-800-358-9620 and its website at <http://www.msc.fema.gov/>.


If you have **questions about this map** or questions concerning the National Flood Insurance Program in general, please call **1-877-FEMA MAP (1-877-336-2627)** or visit the FEMA website at <http://www.fema.gov/business/nfp>.

El Paso County Vertical Datum Offset Table

Flooding Source	Vertical Datum Offset (ft)

REFER TO SECTION 3.3 OF THE EL PASO COUNTY FLOOD INSURANCE STUDY FOR STREAM BY STREAM VERTICAL DATUM CONVERSION INFORMATION


Panel Location Map



This Digital Flood Insurance Rate Map (DFIRM) was produced through a Cooperating Technical Partner (CTP) agreement between the State of Colorado Water Conservation Board (CWCB) and the Federal Emergency Management Agency (FEMA).



Additional Flood Hazard information and resources are available from local communities and the Colorado Water Conservation Board.



NOTE: MAP AREA SHOWN ON THIS PANEL IS LOCATED WITHIN TOWNSHIP 12 SOUTH, RANGE 65 WEST, AND TOWNSHIP 13 SOUTH, RANGE 65 WEST.

LEGEND

SPECIAL FLOOD HAZARD AREAS (SFHAS) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD

The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equalled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

- ZONE A** No Base Flood Elevations determined.
- ZONE AE** Base Flood Elevations determined.
- ZONE AH** Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.
- ZONE AO** Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
- ZONE AR** Special Flood Hazard Area Formerly protected from the 1% annual chance flood by a flood control system that was subsequently decertified. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.
- ZONE A99** Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
- ZONE V** Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.
- ZONE VE** Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.

FLOODWAY AREAS IN ZONE AE
The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.

OTHER FLOOD AREAS
ZONE X Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with drainage areas less than 1 square mile; and areas protected by levees from 1% annual chance flood.

OTHER AREAS
ZONE X Areas determined to be outside the 0.2% annual chance floodplain.
ZONE D Areas in which flood hazards are undetermined, but possible.

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS
OTHERWISE PROTECTED AREAS (OPAs)

CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.

- Floodplain boundary
- Floodway boundary
- Zone D Boundary
- CBRS and OPA boundary

— Boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths or flood velocities.
— (EL 987) Base Flood Elevation value where uniform within zone; elevation in feet*

* Referenced to the North American Vertical Datum of 1988 (NAVD 88)

- A — A Cross section line
- 23 — 23 Transsect line
- 97° 07' 30.00" 32' 22' 30.00" Geographic coordinates referenced to the North American Datum of 1983 (NAD 83)
- 4750000N 1000-meter Universal Transverse Mercator grid ticks, zone 13
- 6000000 FT 5000-foot grid ticks: Colorado State Plane coordinate system, central zone (EPSG:3023), Lambert Conformal Conic Projection
- DX5510 Bench mark (see explanation in Notes to Users section of this FIRM panel)
- M1.5 River Mile


MAP REPOSITORIES
Refer to Map Repositories list on Map Index

EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP
MARCH 17, 1997

EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL
DECEMBER 7, 2018 - to update corporate limits, to change Base Flood Elevations and Special Flood Hazard Areas, to update map format, to add roads and road names, and to incorporate previously issued Letters of Map Revision.

For community map revision history prior to countywide mapping, refer to the Community Map History Table located in the Flood Insurance Study report for this jurisdiction.

To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.



NFIP **PANEL 0533G**

FIRM
FLOOD INSURANCE RATE MAP
EL PASO COUNTY,
COLORADO
AND INCORPORATED AREAS

PANEL 533 OF 1300
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
COLORADO SPRINGS, CITY OF	08060	0533	G
EL PASO COUNTY	08059	0533	G

Notice to User: The Map Number shown below should be used when placing map orders. The Community Number shown above should be used on insurance applications for the subject community.

MAP NUMBER
08041C0533G

MAP REVISED
DECEMBER 7, 2018
Federal Emergency Management Agency

WETLANDS JURISDICTIONAL DETERMINATION (JD)





DEPARTMENT OF THE ARMY
CORPS OF ENGINEERS, ALBUQUERQUE DISTRICT
SOUTHERN COLORADO REGULATORY BRANCH
201 WEST 8TH STREET, SUITE 350
PUEBLO, COLORADO 81003

June 30, 2022

Regulatory Division

SUBJECT: Jurisdictional Determination- Action No.SPA-2022-00123

Classic Communities
Attn: Loren Moreland
6385 Corporate Dr., Suite 200
Colorado Springs, Colorado 80919
lorenm@classichomes.com

Dear Mr. Moreland:

This letter responds to your request for a jurisdictional determination (JD) for forty (40) wetlands and one man-made pond associated with the *Classic Communities-Jayne's Parcel*, residential development. The approximately 141-acre project site is located near Sand Creek, centered at latitude 38.976682°, longitude -104.668357°, Colorado Springs, El Paso County, Colorado. We have assigned Action No. SPA-2022-00123 to your request. Please reference this number in all future correspondence concerning the site.

Based on the information provided, we concur with your aquatic resource delineation for the site, as depicted on the enclosed drawing labeled, *SPA-2022-00123, Figure 1*, prepared by Core Consultants, Inc. (enclosure 1). We have determined that the site does not contain waters of the United States that are subject to regulation under Section 404 of the Clean Water Act. The approximately 9.66-acres of aquatic resources identified as *Wetlands WT-A1* through *WT-A40* and one man-made pond, on the above drawing are intrastate isolated aquatic resources with no apparent interstate or foreign commerce connection. As such, these aquatic resources are not regulated by the U.S. Army Corps of Engineers. This disclaimer of jurisdiction is only for Section 404 of the Federal Clean Water Act.

We are enclosing a copy of the *Approved Jurisdictional Determination Form* for your site (enclosure 2). A copy of this JD is also available at <http://www.spa.usace.army.mil/req/JD>. This approved JD is valid for five years unless new information warrants revision of the determination before the expiration date.

You may accept or appeal this approved JD or provide new information in accordance with the attached Notification of Administration Appeal Options and Process and Request for Appeal (NAAOP-RFA) (enclosure 3). If you elect to appeal this approved JD, you must complete Section II of the form and return it to the Army Engineer Division, South Pacific, CESP-D-PDS-O, Attn: Tom Cavanaugh, Administrative

Appeal Review Officer, P.O. Box 36023, 450 Golden Gate Ave, San Francisco, CA 94102 within 60 days of the date of this notice. Failure to notify the Corps within 60 days of the date of this notice means that you accept the approved JD in its entirety and waive all rights to appeal the approved JD.

If you have any questions, please contact Senior Project Manager Kyle Zibung by email at kyle.d.zibung@usace.army.mil, or telephone at (651) 290-5877. For program information or to complete our Customer Survey, visit our website at <https://www.spa.usace.army.mil/Missions/Regulatory-Program-and-Permits/>.

Sincerely,

A handwritten signature in black ink, appearing to read "Kyle Zibung". The signature is written in a cursive style with a large, sweeping flourish at the end.

for
Kara Hellige
Chief, Southern Colorado Branch

Enclosures

cc:

Natalie Graves, Core Consultants, Inc. (ngraves@liveyourcore.com)




Figure 4.4 Potential WOTUS Location Map (North)




Figure 4.4 Potential WOTUS Location Map (South)

APPROVED JURISDICTIONAL DETERMINATION FORM
U.S. Army Corps of Engineers

This form should be completed by following the instructions provided in Section IV of the JD Form Instructional Guidebook.

SECTION I: BACKGROUND INFORMATION

A. REPORT COMPLETION DATE FOR APPROVED JURISDICTIONAL DETERMINATION (JD): June 30, 2022

B. ST PAUL, MN DISTRICT OFFICE, FILE NAME, AND NUMBER: SPA-2022-00123, Classic Communities-Jayne's Parcel AJD

C. PROJECT LOCATION AND BACKGROUND INFORMATION:

State: Colorado

County/parish/borough: El Paso

City: Colorado Springs

Center coordinates of site (lat/long in degree decimal format): Lat. 38.976682° N, Long. -104.668357° W.

Universal Transverse Mercator: 13

Name of nearest waterbody: Sand Creek

Name of watershed or Hydrologic Unit Code (HUC): 11020003-Fountain

- Check if map/diagram of review area and/or potential jurisdictional areas is/are available upon request.
 Check if other sites (e.g., offsite mitigation sites, disposal sites, etc...) are associated with this action and are recorded on a different JD form.

D. REVIEW PERFORMED FOR SITE EVALUATION (CHECK ALL THAT APPLY):

- Office (Desk) Determination. Date: June 2, 2022
 Field Determination. Date(s):

SECTION II: SUMMARY OF FINDINGS

A. RHA SECTION 10 DETERMINATION OF JURISDICTION.

There are no "navigable waters of the U.S." within Rivers and Harbors Act (RHA) jurisdiction (as defined by 33 CFR part 329) in the review area.

B. CWA SECTION 404 DETERMINATION OF JURISDICTION.

There are no "waters of the U.S." within Clean Water Act (CWA) jurisdiction (as defined by 33 CFR part 328) in the review area.

1. Waters of the U.S.: N/A

2. Non-regulated waters/wetlands (check if applicable):¹

Potentially jurisdictional waters and/or wetlands were assessed within the review area and determined to be not jurisdictional. Explain: **The review area for this determination is comprised of 40 individual Wetlands (identified as WT A1 through WT-A40) totaling 9.51 acres and one man-made pond totaling 0.15 acre located on the approximately 141-acre tract. Based on a review of the National Hydrography Dataset (NHD) the nearest mapped potential relatively permanent water (RPW) is Sand Creek located approximately 1,500 feet southeast of the review area. The National Wetland Inventory (NWI) and NHD shows mapped wetland drainages with two mapped ephemeral streams in the eastern and western portion of the review area, however, the February 2022 Core Consultants, Inc., wetland delineation report (Core Report) did not find any defined bed/banks nor ordinary high water mark indicators within these two mapped features. The Core Report determined the mapping layers to be inaccurate and best characterized both features as multiple depressional wetlands separated by upland swales. The upland swales sever a surface connection between the wetlands, pond, and Sand Creek. The Core Report notes that a culvert is present under Vollmer Road in the eastern portion of the review area near WT-A38, however, the outlet channel is comprised of a meandering upland swale with no observed surface connection to Sand Creek. Much of the land south of the JD review area has been previously graded for residential development resulting in altered surface hydrology patterns. Due to their small size and/or disturbed characteristics, Wetlands WT-A1 through WT-A40 and the man-made pond provide limited habitat functions to surrounding areas and exhibit tenuous ecological connections to nearby surface waters. Based on this information, the Corps has determined that Wetlands WT-A1 through WT-A40 and the man-made pond are isolated features with no surface or shallow subsurface hydrologic connection or ecological connection to a RPW or TNW. Wetlands WT-A1 through WT-A40 and the man-made pond do not border, neighbor, nor are contiguous with another water of the U.S. Wetlands WT-A1 through WT-A40 and the man-made pond are not separated from other WOTUS by man-made dikes, barriers, or berms. Wetlands WT-A1 through WT-A40 and the man-made pond do not support a link to interstate or foreign commerce; they are not known to be used by interstate or foreign travelers for recreation or**

¹ Supporting documentation is presented in Section III.F.

other purposes; They do not produce fish or shellfish that could be taken and sold in interstate or foreign commerce; and they are not known to be used for industrial purposes by industries in interstate commerce. Therefore, the Corps has determined that Wetlands WT-A1 through WT-A40 and the man-made pond are isolated and therefore not regulated by the Corps under Section 404 of the CWA.

SECTION III: CWA ANALYSIS

- A. TNWs AND WETLANDS ADJACENT TO TNWs: N/A
- B. CHARACTERISTICS OF TRIBUTARY (THAT IS NOT A TNW) AND ITS ADJACENT WETLANDS (IF ANY): N/A
- C. SIGNIFICANT NEXUS DETERMINATION: N/A
- D. DETERMINATIONS OF JURISDICTIONAL FINDINGS. THE SUBJECT WATERS/WETLANDS ARE (CHECK ALL THAT APPLY): N/A
- E. ISOLATED [INTERSTATE OR INTRA-STATE] WATERS, INCLUDING ISOLATED WETLANDS, THE USE, DEGRADATION OR DESTRUCTION OF WHICH COULD AFFECT INTERSTATE COMMERCE, INCLUDING ANY SUCH WATERS (CHECK ALL THAT APPLY): N/A

F. NON-JURISDICTIONAL WATERS, INCLUDING WETLANDS (CHECK ALL THAT APPLY):

- If potential wetlands were assessed within the review area, these areas did not meet the criteria in the 1987 Corps of Engineers Wetland Delineation Manual and/or appropriate Regional Supplements.
- Review area included isolated waters with no substantial nexus to interstate (or foreign) commerce.
 - Prior to the Jan 2001 Supreme Court decision in "SWANCC," the review area would have been regulated based solely on the "Migratory Bird Rule" (MBR).
- Waters do not meet the "Significant Nexus" standard, where such a finding is required for jurisdiction. Explain:
- Other (explain, if not covered above):

Provide acreage estimates for non-jurisdictional waters in the review area, where the sole potential basis of jurisdiction is the MBR factors (i.e., presence of migratory birds, presence of endangered species, use of water for irrigated agriculture), using best professional judgment (check all that apply):

- Non-wetland waters (i.e., rivers, streams): linear feet width (ft).
- Lakes/ponds: 0.15 acres.
- Other non-wetland waters: acres. List type of aquatic resource: .
- Wetlands: 9.51 acres.

Provide acreage estimates for non-jurisdictional waters in the review area that do not meet the "Significant Nexus" standard, where such a finding is required for jurisdiction (check all that apply):

- Non-wetland waters (i.e., rivers, streams): linear feet, width (ft).
- Lakes/ponds: acres.
- Other non-wetland waters: acres. List type of aquatic resource: .
- Wetlands: acres.

SECTION IV: DATA SOURCES.

A. SUPPORTING DATA. Data reviewed for JD (check all that apply - checked items shall be included in case file and, where checked and requested, appropriately reference sources below):

- Maps, plans, plots or plat submitted by or on behalf of the applicant/consultant: February 2022 Core Consultants, Inc. Wetland Delineation Report
- Data sheets prepared/submitted by or on behalf of the applicant/consultant.
 - Office concurs with data sheets/delineation report.
 - Office does not concur with data sheets/delineation report.
- Data sheets prepared by the Corps:
- Corps navigable waters' study:
- U.S. Geological Survey Hydrologic Atlas:
 - USGS NHD data.
 - USGS 8 and 12 digit HUC maps.
- U.S. Geological Survey map(s). Cite scale & quad name: 1:24K Falcon NW
- USDA Natural Resources Conservation Service Soil Survey. Citation: El Paso County Soil Survey
- National wetlands inventory map(s). Cite name: USFWS National Wetland Inventory
- State/Local wetland inventory map(s):
- FEMA/FIRM maps:
- 100-year Floodplain Elevation is: (National Geodetic Vertical Datum of 1929)

- Photographs: Aerial (Name & Date): 2020, 2018, 2017, 2015, 2013, 2010, 2008, 2006, 2005, 2000, 1994
or Other (Name & Date):
- Previous determination(s). File no. and date of response letter:
- Applicable/supporting case law:
- Applicable/supporting scientific literature:
- Other information (please specify):

B. ADDITIONAL COMMENTS TO SUPPORT JD:

NOTIFICATION OF ADMINISTRATIVE APPEAL OPTIONS AND PROCESS AND REQUEST FOR APPEAL

Applicant: Classic Communities c/o Loren Moreland	File No.: SPA-2022-00123	Date: June 30, 2022
Attached is:		See Section below
	INITIAL PROFFERED PERMIT (Standard Permit or Letter of permission)	A
	PROFFERED PERMIT (Standard Permit or Letter of permission)	B
	PERMIT DENIAL	C
→	APPROVED JURISDICTIONAL DETERMINATION	D
	PRELIMINARY JURISDICTIONAL DETERMINATION	E

SECTION I - The following identifies your rights and options regarding an administrative appeal of the above decision. Additional information may be found at http://www.usace.army.mil/cecw/pages/reg_materials.aspx or Corps regulations at 33 CFR Part 331.

A: INITIAL PROFFERED PERMIT: You may accept or object to the permit.

- **ACCEPT:** If you received a Standard Permit, you may sign the permit document and return it to the district engineer for final authorization. If you received a Letter of Permission (LOP), you may accept the LOP and your work is authorized. Your signature on the Standard Permit or acceptance of the LOP means that you accept the permit in its entirety, and waive all rights to appeal the permit, including its terms and conditions, and approved jurisdictional determinations associated with the permit.
- **OBJECT:** If you object to the permit (Standard or LOP) because of certain terms and conditions therein, you may request that the permit be modified accordingly. You must complete Section II of this form and return the form to the district engineer. Your objections must be received by the district engineer within 60 days of the date of this notice, or you will forfeit your right to appeal the permit in the future. Upon receipt of your letter, the district engineer will evaluate your objections and may: (a) modify the permit to address all of your concerns, (b) modify the permit to address some of your objections, or (c) not modify the permit having determined that the permit should be issued as previously written. After evaluating your objections, the district engineer will send you a proffered permit for your reconsideration, as indicated in Section B below.

B: PROFFERED PERMIT: You may accept or appeal the permit

- **ACCEPT:** If you received a Standard Permit, you may sign the permit document and return it to the district engineer for final authorization. If you received a Letter of Permission (LOP), you may accept the LOP and your work is authorized. Your signature on the Standard Permit or acceptance of the LOP means that you accept the permit in its entirety, and waive all rights to appeal the permit, including its terms and conditions, and approved jurisdictional determinations associated with the permit.
- **APPEAL:** If you choose to decline the proffered permit (Standard or LOP) because of certain terms and conditions therein, you may appeal the declined permit under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer (address on reverse). This form must be received by the division engineer within 60 days of the date of this notice.

C: PERMIT DENIAL: You may appeal the denial of a permit under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer (address on reverse). This form must be received by the division engineer within 60 days of the date of this notice.

D: APPROVED JURISDICTIONAL DETERMINATION: You may accept or appeal the approved JD or provide new information.

- **ACCEPT:** You do not need to notify the Corps to accept an approved JD. Failure to notify the Corps within 60 days of the date of this notice, means that you accept the approved JD in its entirety, and waive all rights to appeal the approved JD.
- **APPEAL:** If you disagree with the approved JD, you may appeal the approved JD under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer (address on reverse). This form must be received by the division engineer within 60 days of the date of this notice.

E: PRELIMINARY JURISDICTIONAL DETERMINATION: You do not need to respond to the Corps regarding the preliminary JD. The Preliminary JD is not appealable. If you wish, you may request an approved JD (which may be appealed), by contacting the Corps district for further instruction. Also you may provide new information for further consideration by the Corps to reevaluate the JD.

SECTION II - REQUEST FOR APPEAL or OBJECTIONS TO AN INITIAL PROFFERED PERMIT

REASONS FOR APPEAL OR OBJECTIONS: (Describe your reasons for appealing the decision or your objections to an initial proffered permit in clear concise statements. You may attach additional information to this form to clarify where your reasons or objections are addressed in the administrative record.)

ADDITIONAL INFORMATION: The appeal is limited to a review of the administrative record, the Corps memorandum for the record of the appeal conference or meeting, and any supplemental information that the review officer has determined is needed to clarify the administrative record. Neither the appellant nor the Corps may add new information or analyses to the record. However, you may provide additional information to clarify the location of information that is already in the administrative record.

POINT OF CONTACT FOR QUESTIONS OR INFORMATION:

If you have questions regarding this decision and/or the appeal process you may contact:

Kyle Zibung
U.S. Army Corps of Engineers
201 West 8th Street, Suite 350
Pueblo, Colorado 81003
Phone: 651-290-5877
Email: kyle.d.zibung@usace.army.mil

If you only have questions regarding the appeal process you may also contact:

Thomas J. Cavanaugh
Administrative Appeal Review Officer
U.S. Army Corps of Engineers
South Pacific Division
P.O. Box 36023, 450 Golden Gate Ave
San Francisco, California 94103-1399
Phone: 415-503-6574, FAX 415-503-6646
Email: Thomas.J.Cavanaugh@usace.army.mil

RIGHT OF ENTRY: Your signature below grants the right of entry to Corps of Engineers personnel, and any government consultants, to conduct investigations of the project site during the course of the appeal process. You will be provided a 15 day notice of any site investigation and will have the opportunity to participate in all site investigations.

Signature of appellant or agent.

Date:

Telephone number:

HYDROLOGIC / STORMWATER QUALITY CALCULATIONS

For Colorado Springs and much of the Fountain Creek watershed, the 1-hour depths are fairly uniform and are summarized in Table 6-2. Depending on the location of the project, rainfall depths may be calculated using the described method and the NOAA Atlas maps shown in Figures 6-6 through 6-17.

Table 6-2. Rainfall Depths for Colorado Springs

Return Period	1-Hour Depth	6-Hour Depth	24-Hour Depth
2	1.19	1.70	2.10
5	1.50	2.10	2.70
10	1.75	2.40	3.20
25	2.00	2.90	3.60
50	2.25	3.20	4.20
100	2.52	3.50	4.60

Where $Z = 6,840 \text{ ft}/100$

These depths can be applied to the design storms or converted to intensities (inches/hour) for the Rational Method as described below. However, as the basin area increases, it is unlikely that the reported point rainfalls will occur uniformly over the entire basin. To account for this characteristic of rain storms an adjustment factor, the Depth Area Reduction Factor (DARF) is applied. This adjustment to rainfall depth and its effect on design storms is also described below. The UDFCD UD-Rain spreadsheet, available on UDFCD's website, also provides tools to calculate point rainfall depths and Intensity-Duration-Frequency curves² and should produce similar depth calculation results.

2.2 Design Storms

Design storms are used as input into rainfall/runoff models and provide a representation of the typical temporal distribution of rainfall events when the creation or routing of runoff hydrographs is required. It has long been observed that rainstorms in the Front Range of Colorado tend to occur as either short-duration, high-intensity, localized, convective thunderstorms (cloud bursts) or longer-duration, lower-intensity, broader, frontal (general) storms. The significance of these two types of events is primarily determined by the size of the drainage basin being studied. Thunderstorms can create high rates of runoff within a relatively small area, quickly, but their influence may not be significant very far downstream. Frontal storms may not create high rates of runoff within smaller drainage basins due to their lower intensity, but tend to produce larger flood flows that can be hazardous over a broader area and extend further downstream.

- **Thunderstorms:** Based on the extensive evaluation of rain storms completed in the Carlton study (Carlton 2011), it was determined that typical thunderstorms have a duration of about 2 hours. The study evaluated over 300,000 storm cells using gage-adjusted NEXRAD data, collected over a 14-year period (1994 to 2008). Storms lasting longer than 3 hours were rarely found. Therefore, the results of the Carlton study have been used to define the shorter duration design storms.

To determine the temporal distribution of thunderstorms, 22 gage-adjusted NEXRAD storm cells were studied in detail. Through a process described in a technical memorandum prepared by the City of Colorado Springs (City of Colorado Springs 2012), the results of this analysis were interpreted and normalized to the 1-hour rainfall depth to create the distribution shown in Table 6-3 with a 5 minute time interval for drainage basins up to 1 square mile in size. This distribution represents the rainfall

Table 6-6. Runoff Coefficients for Rational Method
(Source: UDFCD 2001)

Land Use or Surface Characteristics	Percent Impervious	Runoff Coefficients											
		2-year		5-year		10-year		25-year		50-year		100-year	
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D
Business													
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0.89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	0.60	0.65	0.62	0.68
Residential													
1/8 Acre or less	65	0.41	0.45	0.45	0.49	0.49	0.54	0.54	0.59	0.57	0.62	0.59	0.65
1/4 Acre	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.47	0.57
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Parks and Cemeteries													
Parks	7	0.05	0.09	0.12	0.19	0.20	0.29	0.30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0.46	0.54	0.50	0.58
Undeveloped Areas													
Historic Flow Analysis-- Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Gravel	80	0.57	0.60	0.59	0.63	0.63	0.66	0.66	0.70	0.68	0.72	0.70	0.74
Drive and Walks													
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	0.96	0.96
Roofs													
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Lawns													
Lawns	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50

3.2 Time of Concentration

One of the basic assumptions underlying the Rational Method is that runoff is a function of the average rainfall rate during the time required for water to flow from the hydraulically most remote part of the drainage area under consideration to the design point. However, in practice, the time of concentration can be an empirical value that results in reasonable and acceptable peak flow calculations.

For urban areas, the time of concentration (t_c) consists of an initial time or overland flow time (t_i) plus the travel time (t_t) in the storm sewer, paved gutter, roadside drainage ditch, or drainage channel. For non-urban areas, the time of concentration consists of an overland flow time (t_i) plus the time of travel in a concentrated form, such as a swale or drainageway. The travel portion (t_t) of the time of concentration can be estimated from the hydraulic properties of the storm sewer, gutter, swale, ditch, or drainageway. Initial time, on the other hand, will vary with surface slope, depression storage, surface cover, antecedent rainfall, and infiltration capacity of the soil, as well as distance of surface flow. The time of concentration is represented by Equation 6-7 for both urban and non-urban areas.

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)*	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

* For buried riprap, select C_v value based on type of vegetative cover.

The travel time is calculated by dividing the flow distance (in feet) by the velocity calculated using Equation 6-9 and converting units to minutes.

The time of concentration (t_c) is then the sum of the overland flow time (t_o) and the travel time (t_t) per Equation 6-7.

3.2.3 First Design Point Time of Concentration in Urban Catchments

Using this procedure, the time of concentration at the first design point (typically the first inlet in the system) in an urbanized catchment should not exceed the time of concentration calculated using Equation 6-10. The first design point is defined as the point where runoff first enters the storm sewer system.

$$t_c = \frac{L}{180} + 10 \quad (\text{Eq. 6-10})$$

Where:

t_c = maximum time of concentration at the first design point in an urban watershed (min)

L = waterway length (ft)

Equation 6-10 was developed using the rainfall-runoff data collected in the Denver region and, in essence, represents regional “calibration” of the Rational Method. Normally, Equation 6-10 will result in a lesser time of concentration at the first design point and will govern in an urbanized watershed. For subsequent design points, the time of concentration is calculated by accumulating the travel times in downstream drainageway reaches.


3.2.4 Minimum Time of Concentration

If the calculations result in a t_c of less than 10 minutes for undeveloped conditions, it is recommended that a minimum value of 10 minutes be used. The minimum t_c for urbanized areas is 5 minutes.

3.2.5 Post-Development Time of Concentration

As Equation 6-8 indicates, the time of concentration is a function of the 5-year runoff coefficient for a drainage basin. Typically, higher levels of imperviousness (higher 5-year runoff coefficients) correspond to shorter times of concentration, and lower levels of imperviousness correspond to longer times of

Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency



IDF Equations

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

FINAL DRAINAGE REPORT ~ BASIN RUNOFF COEFFICIENT SUMMARY

BASIN	TOTAL AREA (AC)	DEVELOPED AREA/IMPERVIOUS AREA				LANDSCAPE/UNDEVELOPED AREAS				WEIGHTED			WEIGHTED CA			IMPERVIOUSNESS
		AREA (AC)	C(2)	C(5)	C(100)	AREA (AC)	C(2)	C(5)	C(100)	C(2)	C(5)	C(100)	CA(2)	CA(5)	CA(100)	
EX-A	0.78	0.00	0.03	0.09	0.36	0.78	0.03	0.09	0.36	0.03	0.09	0.36	0.02	0.07	0.28	2%
EX-B	2.80	0.00	0.03	0.09	0.36	2.80	0.03	0.09	0.36	0.03	0.09	0.36	0.08	0.25	1.01	2%
EX-C	41.40	0.00	0.03	0.09	0.36	41.40	0.03	0.09	0.36	0.03	0.09	0.36	1.24	3.73	14.90	2%
EX-D	1.30	0.00	0.03	0.09	0.36	1.30	0.03	0.09	0.36	0.03	0.09	0.36	0.04	0.12	0.47	2%
EX-E	72.40	0.00	0.03	0.09	0.36	72.40	0.03	0.09	0.36	0.03	0.09	0.36	2.17	6.52	26.06	2%
EX-F	8.70	0.00	0.03	0.09	0.36	8.70	0.03	0.09	0.36	0.03	0.09	0.36	0.26	0.78	3.13	2%
EX-G	8.30	0.00	0.03	0.09	0.36	8.30	0.03	0.09	0.36	0.03	0.09	0.36	0.25	0.75	2.99	2%
EX-H	6.50	0.00	0.03	0.09	0.36	6.50	0.03	0.09	0.36	0.03	0.09	0.36	0.20	0.59	2.34	2%
OS-1	2.00	2.00	0.06	0.13	0.40	0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.12	0.26	0.80	10%
OS-2	5.30	5.30	0.06	0.13	0.40	0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.32	0.69	2.12	10%
EX-3	44.30	44.30	0.04	0.11	0.38	0.00	0.02	0.08	0.35	0.04	0.11	0.38	1.77	4.65	16.61	5%
EX-4A	77.00	77.00	0.04	0.11	0.38	0.00	0.02	0.08	0.35	0.04	0.11	0.38	3.08	8.09	28.88	5%
EX-4B	70.00	70.00	0.04	0.11	0.38	0.00	0.02	0.08	0.35	0.04	0.11	0.38	2.80	7.35	26.25	5%

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALC'D BY: MAW

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)* $t_c = \frac{L}{180} + 10$	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

*For buried riprap, select C_v value based on type of vegetative cover.

Return Period	1-Hour Depth
2	1.19
5	1.50
10	1.75
25	2.00
50	2.25
100	2.52

$$t_i = \frac{0.395(1.1 - C_s)\sqrt{L}}{S^{0.33}}$$

$$V = C_v S_w^{0.5} \quad T_c = L/V$$

FINAL DRAINAGE REPORT ~ BASIN RUNOFF SUMMARY

BASIN	WEIGHTED			OVERLAND			STREET / CHANNEL FLOW				Tc TOTAL (min)	INTENSITY			TOTAL FLOWS			
	CA(2)	CA(5)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)		Tc (min)	I(2) (in/hr)	I(5) (in/hr)	I(100) (in/hr)	Q(2) (cfs)	Q(5) (cfs)	Q(100) (cfs)
EX-A	0.02	0.07	0.28	0.09	240	9	18.3					18.3	2.58	3.23	5.41	0.1	0.2	2
EX-B	0.08	0.25	1.01	0.09	300	24	15.9	120	2.0%	1.0	2.0	17.9	2.60	3.25	5.46	0.2	0.8	6
EX-C	1.24	3.73	14.90	0.09	300	18	17.5	1300	2.9%	1.7	12.7	30.2	1.98	2.47	4.15	2	9	62
EX-D	0.04	0.12	0.47	0.09	225	10	16.7					16.7	2.68	3.36	5.64	0.1	0.4	3
EX-E	2.17	6.52	26.06	0.09	280	20	15.9	3400	2.5%	1.6	35.8	51.8	1.34	1.66	2.79	3	11	73
EX-F	0.26	0.78	3.13	0.09	300	12	20.0	560	2.0%	1.4	6.6	26.6	2.13	2.66	4.47	1	2	14
EX-G	0.25	0.75	2.99	0.09	300	10	21.2	420	2.0%	1.4	4.9	26.2	2.15	2.69	4.51	1	2	13
EX-H	0.20	0.59	2.34	0.09	300	10	21.2	800	2.0%	1.4	9.4	30.7	1.96	2.45	4.11	0.4	1.4	10
OS-1	0.12	0.26	0.80	0.08	300	10	21.4					21.4	2.39	2.99	5.01	0.3	0.8	4
OS-2	0.32	0.69	2.12	0.08	300	12	20.2					20.2	2.46	3.08	5.16	1	2	11
EX-3	1.77	4.65	16.61	0.08	300	10	21.4	650	2.0%	1.4	7.7	29.1	2.02	2.53	4.24	4	12	70
EX-4A	3.08	8.09	28.88	0.08	300	9	22.2	2400	2.0%	1.4	28.3	50.5	1.37	1.70	2.85	4	14	82
EX-4B	2.80	7.35	26.25	0.08	300	10	21.4	3500	1.8%	1.3	43.5	64.9	1.07	1.32	2.22	3	10	58

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

FINAL DRAINAGE REPORT ~ SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Inlet Size
					I(5)	I(100)	Q(5)	Q(100)	
E1	EX-4A	8.09	28.88	50.5	1.70	2.85	14	82	EX. 24" CMP CULVERT
E2	EX-4B	7.35	26.25	64.9	1.32	2.22	10	58	EX. STOCK OFF-SITE POND
E3	EX-A, EX-B	0.32	1.29	18.3	3.23	5.41	1	7	TYPE D CDOT INLET W/ 24" RCP
E4	EX-4A, EX-4B, EX-C	19.16	70.03	64.9	1.32	2.22	25	155	PLANNED 48" RCP W/ MH AND GRATE
E5	EX-3	4.65	16.61	29.1	2.53	4.24	12	70	EX. 24" CMP CULVERT
E6	EX-G	0.75	2.99	26.2	2.69	4.51	2	13	TYPE D CDOT INLET W/ 24" RCP
E7	EX-H	0.59	2.34	30.7	2.45	4.11	1	10	TYPE C CDOT INLET W/ 18" RCP
E8	EX-3, EX-E, OS-2	11.86	44.80	51.8	1.66	2.79	20	125	EX. 24" CMP CULVERT
E9	DP-E8, EX-F, OS-1	12.90	48.73	55.8	1.55	2.60	20	127	MODIFIED 4'X14' TYPE D CDOT INLET W/ 54" RCP
E10	EX-D	0.12	0.47	16.7	3.36	5.64	0.4	3	SHEET FLOW TO NATURAL RAVINE

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

BASIN RUNOFF COEFFICIENT SUMMARY

BASIN	TOTAL AREA (AC)	C VALUE DCM TABLE 6-6						C VALUE DCM TABLE 6-6						WEIGHTED "C" VALUE			WEIGHTED CA			WEIGHTED IMP.
		LAND USE	PERCENT IMP.	AREA (AC)	C(2)	C(5)	C(100)	LAND USE	PERCENT IMP.	AREA (AC)	C(2)	C(5)	C(100)	C(2)	C(5)	C(100)	CA(2)	CA(5)	CA(100)	PERCENT
EX-3	41.80	RES. 5 AC.	5.0%	41.80	0.04	0.11	0.38			0.00	0.02	0.08	0.35	0.04	0.11	0.38	1.67	4.39	15.68	5.0%
EX-3A	2.50	RES. 5 AC.	5.0%	2.50	0.04	0.11	0.38			0.00	0.02	0.08	0.35	0.04	0.11	0.38	0.10	0.26	0.94	5.0%
EX-4A	74.20	RES. 5 AC.	5.0%	74.20	0.04	0.11	0.38			0.00	0.02	0.08	0.35	0.04	0.11	0.38	2.97	7.79	27.83	5.0%
EX-4B	70.00	RES. 5 AC.	5.0%	70.00	0.04	0.11	0.38			0.00	0.02	0.08	0.35	0.04	0.11	0.38	2.80	7.35	26.25	5.0%
EX-4C	2.80	RES. 5 AC.	5.0%	2.80	0.04	0.11	0.38			0.00	0.02	0.08	0.35	0.04	0.11	0.38	0.11	0.29	1.05	5.0%
OS-1A	0.30	RES. 2.5 AC.	10.0%	0.30	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.02	0.04	0.12	10.0%
OS-1B	0.80	RES. 2.5 AC.	10.0%	0.80	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.05	0.10	0.32	10.0%
OS-2A	1.20	RES. 2.5 AC.	10.0%	1.20	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.07	0.16	0.48	10.0%
OS-2B	0.53	RES. 2.5 AC.	10.0%	0.53	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.03	0.07	0.21	10.0%
OS-2C	3.60	RES. 2.5 AC.	10.0%	3.60	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.22	0.47	1.44	10.0%
A	3.00	RES. 2.5 AC.	10.0%	2.65	0.06	0.13	0.40	RES. 1/3 AC.	30.0%	0.35	0.18	0.25	0.47	0.07	0.14	0.41	0.22	0.43	1.22	12.3%
B	2.10	RES. 2.5 AC.	10.0%	1.68	0.06	0.13	0.40	RES. 1/3 AC.	30.0%	0.42	0.18	0.25	0.47	0.08	0.15	0.41	0.18	0.32	0.87	14.0%
C1	7.70	RES. 2.5 AC.	10.0%	3.80	0.06	0.13	0.40	RES. 1/3 AC.	30.0%	3.90	0.18	0.25	0.47	0.12	0.19	0.44	0.93	1.47	3.35	20.1%
C2	2.50	RES. 1/3 AC.	30.0%	2.50	0.18	0.25	0.47			0.00	0.08	0.08	0.08	0.18	0.25	0.47	0.45	0.63	1.18	30.0%
D	1.10	RES. 1/6 AC.	52.5%	1.10	0.32	0.38	0.55			0.00	0.02	0.08	0.35	0.32	0.38	0.55	0.35	0.41	0.60	52.5%
E	4.00	RES. 1/6 AC.	52.5%	3.75	0.32	0.38	0.55	POCKET PARK	7.0%	0.25	0.05	0.12	0.39	0.30	0.36	0.54	1.21	1.44	2.14	49.7%
F	1.70	RES. 1/6 AC.	52.5%	1.70	0.32	0.38	0.55			0.00	0.02	0.08	0.35	0.32	0.38	0.55	0.54	0.64	0.93	52.5%
G	1.70	RES. 1/8 AC.	65.0%	1.70	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	0.70	0.77	1.00	65.0%
H	3.20	RES. 1/8 AC.	65.0%	3.20	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	1.31	1.44	1.89	65.0%
I	1.10	RES. 1/8 AC.	65.0%	1.10	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	0.45	0.50	0.65	65.0%
J	5.40	RES. 1/6 AC.	52.5%	5.40	0.32	0.38	0.55			0.00	0.02	0.08	0.35	0.32	0.38	0.55	1.73	2.03	2.94	52.5%
K	0.80	ROADWAY	100.0%	0.80	0.89	0.90	0.96			0.00	0.02	0.08	0.35	0.89	0.90	0.96	0.71	0.72	0.77	100.0%
L	0.60	RES. 1/3 AC.	30.0%	0.50	0.18	0.25	0.47	ROADWAY	100.0%	0.10	0.89	0.90	0.96	0.30	0.36	0.55	0.18	0.22	0.33	41.7%
M	5.90	PARK	7.0%	5.90	0.05	0.12	0.39			0.00	0.02	0.08	0.35	0.05	0.12	0.39	0.30	0.71	2.30	7.0%
N	3.70	RES. 1/8 AC.	65.0%	3.70	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	1.52	1.67	2.18	65.0%
O	9.50	RES. 1/8 AC.	65.0%	9.50	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	3.90	4.28	5.61	65.0%
P	5.70	COMMERCIAL	95.0%	4.50	0.41	0.45	0.59	OS BUFFER	7.0%	1.20	0.05	0.12	0.39	0.33	0.38	0.55	1.91	2.17	3.12	76.5%
Q	1.90	RES. 1/8 AC.	65.0%	0.90	0.41	0.45	0.59	OS BUFFER	7.0%	1.00	0.05	0.12	0.39	0.22	0.28	0.48	0.42	0.53	0.92	34.5%
R	3.40	RES. 2.5 AC.	10.0%	3.40	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.20	0.44	1.36	10.0%
S	4.50	RES. 2.5 AC.	10.0%	4.22	0.06	0.13	0.40	RES. 1/3 AC.	30.0%	0.28	0.18	0.25	0.47	0.07	0.14	0.40	0.30	0.62	1.82	11.2%
T	1.30	RES. 2.5 AC.	10.0%	1.30	0.06	0.13	0.40			0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.08	0.17	0.52	10.0%
U	5.10	RES. 1/2 AC.	25.0%	5.10	0.15	0.22	0.46			0.00	0.02	0.08	0.35	0.15	0.22	0.46	0.77	1.12	2.35	25.0%
V	0.90	RES. 1/8 AC.	65.0%	0.90	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	0.37	0.41	0.53	65.0%
W	5.40	RES. 1/6 AC.	52.5%	5.40	0.32	0.38	0.55			0.00	0.02	0.08	0.35	0.32	0.38	0.55	1.73	2.03	2.94	52.5%
X	0.30	RES. 1/8 AC.	65.0%	0.30	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	0.12	0.14	0.18	65.0%
Y	4.20	RES. 1/5 AC.	46.0%	4.20	0.28	0.34	0.52			0.00	0.02	0.08	0.35	0.28	0.34	0.52	1.16	1.42	2.19	46.0%
Z	2.20	RES. 1/2 AC.	25.0%	2.20	0.15	0.22	0.46			0.00	0.02	0.08	0.35	0.15	0.22	0.46	0.33	0.48	1.01	25.0%
AA	2.00	RES. 1 AC.	20.0%	2.00	0.12	0.20	0.44			0.00	0.02	0.08	0.35	0.12	0.20	0.44	0.24	0.40	0.88	20.0%
BB	1.80	RES. 1 AC.	20.0%	1.80	0.12	0.20	0.44			0.00	0.02	0.08	0.35	0.12	0.20	0.44	0.22	0.36	0.79	20.0%
CC	1.50	RES. 1/4 AC.	40.0%	1.20	0.23	0.30	0.50	ROADWAY	100.0%	0.30	0.89	0.90	0.96	0.36	0.42	0.59	0.54	0.63	0.89	52.0%
DD	0.60	ROADWAY	100.0%	0.45	0.89	0.90	0.96	PARKWAY	7.0%	0.15	0.05	0.12	0.39	0.68	0.71	0.82	0.41	0.42	0.49	76.8%
EE	1.10	ROADWAY	100.0%	0.60	0.89	0.90	0.96	RES. 1/8 AC.	65.0%	0.50	0.41	0.45	0.59	0.67	0.70	0.79	0.74	0.77	0.87	84.1%
FF	3.20	RES. 1/6 AC.	52.5%	3.20	0.32	0.38	0.55			0.00	0.02	0.08	0.35	0.32	0.38	0.55	1.02	1.20	1.74	52.5%
GG	2.40	ROADWAY	100.0%	1.35	0.89	0.90	0.96	PARKWAY	7.0%	1.05	0.05	0.12	0.39	0.52	0.56	0.71	1.25	1.34	1.71	59.3%
HH	1.50	ROADWAY	100.0%	1.35	0.89	0.90	0.96	PARKWAY	7.0%	0.15	0.05	0.12	0.39	0.81	0.82	0.90	1.21	1.23	1.35	90.7%

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

BASIN RUNOFF COEFFICIENT SUMMARY

BASIN	TOTAL AREA (AC)	C VALUE DCM TABLE 6-6						C VALUE DCM TABLE 6-6						WEIGHTED "C" VALUE			WEIGHTED CA			WEIGHTED IMP.
		LAND USE	PERCENT IMP.	AREA (AC)	C(2)	C(5)	C(100)	LAND USE	PERCENT IMP.	AREA (AC)	C(2)	C(5)	C(100)	C(2)	C(5)	C(100)	CA(2)	CA(5)	CA(100)	PERCENT
II	12.00	RES. 1/8 AC.	65.0%	10.50	0.41	0.45	0.59	OS BUFFER	7.0%	1.50	0.05	0.12	0.39	0.37	0.41	0.57	4.38	4.91	6.78	57.8%
JJ	1.20	RES. 1/6 AC.	52.5%	0.80	0.32	0.38	0.55	ROADWAY	100.0%	0.40	0.89	0.90	0.96	0.51	0.55	0.68	0.61	0.66	0.82	68.3%
KK	2.60	RES. 1/8 AC.	65.0%	2.60	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	1.07	1.17	1.53	65.0%
LL	2.40	RES. 1/8 AC.	65.0%	2.40	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	0.98	1.08	1.42	65.0%
MM	3.30	RES. 1/8 AC.	65.0%	3.30	0.41	0.45	0.59			0.00	0.02	0.08	0.35	0.41	0.45	0.59	1.35	1.49	1.95	65.0%
NN	2.40	ROADWAY	100.0%	0.80	0.89	0.90	0.96	RES. 1/8 AC.	65.0%	1.60	0.41	0.45	0.59	0.57	0.60	0.71	1.37	1.44	1.71	76.7%
OO	2.40	RES. 1 AC.	20.0%	1.60	0.12	0.20	0.44	ROADWAY	100.0%	0.80	0.89	0.90	0.96	0.38	0.43	0.61	0.90	1.04	1.47	46.7%
PP	2.40	RES. 1 AC.	20.0%	2.40	0.12	0.20	0.44			0.00	0.02	0.08	0.35	0.12	0.20	0.44	0.29	0.48	1.06	20.0%
QQ	1.50	RES. 1 AC.	20.0%	1.50	0.12	0.20	0.44			0.00	0.02	0.08	0.35	0.12	0.20	0.44	0.18	0.30	0.66	20.0%
RR	7.70	RES. 1/8 AC.	65.0%	0.50	0.41	0.45	0.59	PARK/POND	7.0%	7.20	0.05	0.12	0.39	0.07	0.14	0.40	0.57	1.09	3.10	10.8%
SS	0.80	OPEN SPACE	7.0%	0.80	0.05	0.12	0.39			0.00	0.02	0.08	0.35	0.05	0.12	0.39	0.04	0.10	0.31	7.0%
TT	0.30	ROADWAY	100.0%	0.24	0.89	0.90	0.96	PARKWAY	7.0%	0.06	0.05	0.12	0.39	0.72	0.74	0.85	0.22	0.22	0.25	81.4%
UU	0.20	ROADWAY	100.0%	0.14	0.89	0.90	0.96	PARKWAY	7.0%	0.06	0.05	0.12	0.39	0.64	0.67	0.79	0.13	0.13	0.16	72.1%
VV	0.70	OPEN SPACE	7.0%	0.70	0.05	0.12	0.39			0.00	0.02	0.08	0.35	0.05	0.12	0.39	0.04	0.08	0.27	7.0%

TOTAL AREA TRIBUTARY TO OFF-SITE POND C 193.40 12.9%

TOTAL AREA TRIBUTARY TO PROP. ON-SITE POND 1 144.43 32.6%

TOTAL AREA TRIBUTARY TO 60" OUTFALL 126.33 35.2%

TOTAL AREA TRIBUTARY TO 30" OUTFALL 10.40 25.5%

- Basins tributary to off-site Pond C constructed within Homestead North at Sterling Ranch Filing No. 1 (SF-22-013)
- Basins tributary to proposed on-site Pond
- Basin w/ exclusion I.7.1.B.5 (Large lot 2.5 ac. min)
- Basin w/ exclusion I.7.1.B.7 (Open Space/Buffer Tract)

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 07/28/03
 CALC'D BY: MAW

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)* $t_c = \frac{L}{180} + 10$	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

*For buried riprap, select C_v value based on type of vegetative cover.

Return Period	1-Hour Depth
2	1.19
5	1.50
10	1.75
25	2.00
50	2.25
100	2.52

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L}}{S^{0.33}}$$

$$V = C_v S_w^{0.5} \quad Tc = LV$$

BASIN RUNOFF SUMMARY

BASIN	WEIGHTED			OVERLAND				STREET / CHANNEL FLOW				Tc TOTAL (min)	INTENSITY			TOTAL FLOWS		
	CA(2)	CA(5)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)	Tc (min)		I(2) (in/hr)	I(5) (in/hr)	I(100) (in/hr)	Q(2) (cfs)	Q(5) (cfs)	Q(100) (cfs)
EX-3	1.67	4.39	15.68	0.08	300	10	21.4	650	2.0%	1.4	7.7	29.1	2.02	2.53	4.24	3	11	66
EX-3A	0.10	0.26	0.94	0.08	300	17	18.0					18.0	2.60	3.25	5.45	0.3	0.9	5
EX-4A	2.97	7.79	27.83	0.08	300	9	22.2	2400	2.0%	1.4	28.3	50.5	1.37	1.70	2.85	4	13	79
EX-4B	2.80	7.35	26.25	0.08	300	10	21.4	3500	1.8%	1.3	43.5	64.9	1.07	1.32	2.22	3	10	58
EX-4C	0.11	0.29	1.05	0.08	300	10	21.4					21.4	2.39	2.99	5.01	0.3	0.9	5
OS-1A	0.02	0.04	0.12	0.08	140	5	14.3					14.3	2.87	3.59	6.03	0.1	0.1	0.7
OS-1B	0.05	0.10	0.32	0.08	300	10	21.4					21.4	2.39	2.99	5.01	0.1	0.3	1.6
OS-2A	0.07	0.16	0.48	0.08	300	14	19.2					19.2	2.52	3.15	5.29	0.2	0.5	2.5
OS-2B	0.03	0.07	0.21	0.08	100	4	11.7					11.7	3.11	3.90	6.55	0.1	0.3	1.4
OS-2C	0.22	0.47	1.44	0.08	300	12	20.2					20.2	2.46	3.08	5.16	0.5	1.4	7
A	0.22	0.43	1.22	0.08	200	12	14.4	150	2.0%	1.4	1.8	16.2	2.72	3.41	5.72	0.6	1.5	7
B	0.18	0.32	0.87	0.08	220	12	15.6	180	3.5%	1.9	1.6	17.2	2.65	3.31	5.56	0.5	1.1	5
C1	0.93	1.47	3.35	0.08	300	10	21.4	150	3.0%	1.7	1.4	22.9	2.31	2.89	4.85	2	4	16
C2	0.45	0.63	1.18	0.08	100	2	14.7	300	2.0%	2.8	1.8	16.4	2.70	3.39	5.68	1	2	7

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 07/28/03
 CALC'D BY: MAW

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)* $t_c = \frac{L}{180} + 10$	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

*For buried riprap, select C_v value based on type of vegetative cover.

Return Period	1-Hour Depth
2	1.19
5	1.50
10	1.75
25	2.00
50	2.25
100	2.52

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L}}{S^{0.33}}$$

$$V = C_v S_w^{0.5} \quad Tc = LV$$

BASIN RUNOFF SUMMARY

BASIN	WEIGHTED			OVERLAND				STREET / CHANNEL FLOW				Tc TOTAL (min)	INTENSITY			TOTAL FLOWS		
	CA(2)	CA(5)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)	Tc (min)		I(2) (in/hr)	I(5) (in/hr)	I(100) (in/hr)	Q(2) (cfs)	Q(5) (cfs)	Q(100) (cfs)
D	0.35	0.41	0.60	0.08	100	2	14.7	100	1.5%	2.4	0.7	15.3	2.79	3.49	5.86	1.0	1.4	4
E	1.21	1.44	2.14	0.08	100	2	14.7	600	2.0%	2.8	3.5	18.2	2.58	3.23	5.43	3	5	12
F	0.54	0.64	0.93	0.08	100	2	14.7	180	5.0%	4.5	0.7	15.3	2.79	3.49	5.86	1.5	2.2	5
G	0.70	0.77	1.00	0.08	50	1	10.4	475	4.0%	4.0	2.0	12.3	3.04	3.81	6.40	2	3	6
H	1.31	1.44	1.89	0.08	100	2	14.7	500	1.5%	2.4	3.4	18.1	2.59	3.24	5.44	3	5	10
I	0.45	0.50	0.65	0.08	50	1	10.4	500	1.5%	2.4	3.4	13.8	2.91	3.65	6.13	1.3	1.8	4
J	1.73	2.03	2.94	0.08	60	1.2	11.3	650	1.5%	2.4	4.4	15.8	2.75	3.45	5.78	5	7	17
K	0.71	0.72	0.77	0.08	15	0.3	5.7	650	1.5%	2.4	4.4	10.1	3.28	4.11	6.91	2	3	5
L	0.18	0.22	0.33	0.08	100	3	12.8	80	2.0%	2.8	0.5	13.3	2.96	3.70	6.22	0.5	0.8	2.1
M	0.30	0.71	2.30	0.08	300	20	17.1					17.1	2.66	3.33	5.59	1	2	13
N	1.52	1.67	2.18	0.08	100	2	14.7	500	2.0%	2.8	2.9	17.6	2.62	3.28	5.51	4	5	12
O	3.90	4.28	5.61	0.08	100	2	14.7	650	2.0%	2.8	3.8	18.5	2.56	3.21	5.38	10	14	30
P	1.91	2.17	3.12	0.12	30	0.6	7.7	400	1.5%	2.4	2.7	10.4	3.24	4.07	6.83	6	9	21
Q	0.42	0.53	0.92	0.12	80	1.6	12.6	300	4.0%	2.0	2.5	15.1	2.81	3.51	5.90	1.2	1.8	5
R	0.20	0.44	1.36	0.08	300	20	17.1	200	4.0%	2.0	1.7	18.7	2.55	3.19	5.35	0.5	1.4	7
S	0.30	0.62	1.82	0.25	300	20	14.2	250	4.0%	2.0	2.1	16.3	2.71	3.40	5.70	0.8	2.1	10

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 07/28/03
 CALC'D BY: MAW

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)* $t_c = \frac{L}{180} + 10$	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

*For buried riprap, select C_v value based on type of vegetative cover.

Return Period	1-Hour Depth
2	1.19
5	1.50
10	1.75
25	2.00
50	2.25
100	2.52

$$t_i = \frac{0.395(1.1 - C_s)\sqrt{L}}{S^{0.33}}$$

$$V = C_v S_w^{0.5} \quad Tc=L/V$$

BASIN RUNOFF SUMMARY

BASIN	WEIGHTED			OVERLAND				STREET / CHANNEL FLOW				Tc TOTAL (min)	INTENSITY			TOTAL FLOWS		
	CA(2)	CA(5)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)	Tc (min)		I(2) (in/hr)	I(5) (in/hr)	I(100) (in/hr)	Q(2) (cfs)	Q(5) (cfs)	Q(100) (cfs)
T	0.08	0.17	0.52	0.08	200	9	15.9					15.9	2.75	3.44	5.77	0.2	0.6	3
U	0.77	1.12	2.35	0.08	100	2	14.7	800	2.0%	2.8	4.7	19.4	2.51	3.14	5.27	2	4	12
V	0.37	0.41	0.53	0.08	50	1	10.4	275	4.0%	4.0	1.1	11.5	3.13	3.92	6.58	1.2	1.6	3
W	1.73	2.03	2.94	0.08	50	1	10.4	900	2.5%	3.2	4.7	15.1	2.80	3.51	5.89	5	7	17
X	0.12	0.14	0.18	0.08	50	1	10.4	100	1.5%	2.4	0.7	11.0	3.18	3.98	6.68	0.4	0.5	1.2
Y	1.16	1.42	2.19	0.08	100	2	14.7	650	1.5%	2.4	4.4	19.1	2.53	3.16	5.31	3	4	12
Z	0.33	0.48	1.01	0.08	50	1	10.4	650	1.5%	2.4	4.4	14.8	2.83	3.54	5.95	1	2	6
AA	0.24	0.40	0.88	0.08	100	3	12.8	375	3.5%	1.9	3.3	16.2	2.72	3.41	5.72	0.7	1.4	5
BB	0.22	0.36	0.79	0.08	80	3	10.6	430	1.5%	1.2	5.9	16.5	2.70	3.38	5.67	0.6	1.2	4
CC	0.54	0.63	0.89	0.08	100	6	10.2	150	1.5%	2.4	1.0	11.2	3.16	3.96	6.64	2	2	6
DD	0.41	0.42	0.49	0.12	30	0.9	6.7	70	1.5%	2.4	0.5	7.2	3.68	4.62	7.75	2	2	4
EE	0.74	0.77	0.87	0.45	10	0.2	3.0	550	4.0%	4.0	2.3	5.2	4.06	5.10	8.56	3	4	7
FF	1.02	1.20	1.74	0.08	85	2.5	11.9	550	4.0%	4.0	2.3	14.2	2.88	3.60	6.05	3	4	11
GG	1.25	1.34	1.71	0.12	40	1.2	7.8	750	2.0%	2.8	4.4	12.2	3.06	3.83	6.43	4	5	11
HH	1.21	1.23	1.35	0.12	30	0.9	6.7	750	2.0%	2.8	4.4	11.2	3.16	3.96	6.66	4	5	9
II	4.38	4.91	6.78	0.12	100	2	14.1	800	1.5%	2.4	5.4	19.5	2.50	3.13	5.25	11	15	36

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 07/28/03
 CALC'D BY: MAW

Table 6-7. Conveyance Coefficient, C_v

Type of Land Surface	C_v
Heavy meadow	2.5
Tillage/field	5
Riprap (not buried)* $t_c = \frac{L}{180} + 10$	6.5
Short pasture and lawns	7
Nearly bare ground	10
Grassed waterway	15
Paved areas and shallow paved swales	20

*For buried riprap, select C_v value based on type of vegetative cover.

Return Period	1-Hour Depth
2	1.19
5	1.50
10	1.75
25	2.00
50	2.25
100	2.52

$$t_i = \frac{0.395(1.1 - C_5)\sqrt{L}}{S^{0.33}}$$

$$V = C_v S_w^{0.5} \quad Tc = LV$$

BASIN RUNOFF SUMMARY

BASIN	WEIGHTED			OVERLAND				STREET / CHANNEL FLOW				Tc TOTAL (min)	INTENSITY			TOTAL FLOWS		
	CA(2)	CA(5)	CA(100)	C(5)	Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (fps)	Tc (min)		I(2) (in/hr)	I(5) (in/hr)	I(100) (in/hr)	Q(2) (cfs)	Q(5) (cfs)	Q(100) (cfs)
JJ	0.61	0.66	0.82	0.08	100	2	14.7	180	1.5%	2.4	1.2	15.9	2.74	3.44	5.77	2	2	5
KK	1.07	1.17	1.53	0.08	100	2	14.7	300	4.0%	4.0	1.3	15.9	2.74	3.43	5.76	3	4	9
LL	0.98	1.08	1.42	0.08	100	2	14.7	300	4.0%	4.0	1.3	15.9	2.74	3.43	5.76	3	4	8
MM	1.35	1.49	1.95	0.08	100	2	14.7	450	4.0%	4.0	1.9	16.5	2.70	3.38	5.67	4	5	11
NN	1.37	1.44	1.71	0.45	80	2.4	7.3	1000	4.0%	4.0	4.2	11.5	3.13	3.92	6.59	4	6	11
OO	0.90	1.04	1.47	0.08	60	1.2	11.3	1100	4.0%	4.0	4.6	15.9	2.74	3.43	5.76	2	4	8
PP	0.29	0.48	1.06	0.08	100	6	10.2	450	2.0%	1.4	5.3	15.5	2.77	3.47	5.83	0.8	1.7	6
QQ	0.18	0.30	0.66	0.08	100	4	11.7	350	2.0%	2.8	2.1	13.7	2.92	3.65	6.14	0.5	1.1	4
RR	0.57	1.09	3.10	0.12	100	3	12.3	600	1.0%	1.0	10.0	22.3	2.34	2.93	4.91	1	3	15
SS	0.04	0.10	0.31	0.08	100	6	10.2					10.2	3.27	4.10	6.88	0.1	0.4	2.1
TT	0.22	0.22	0.25	0.12	40	1.2	7.8	80	1.5%	2.4	0.5	8.3	3.51	4.40	7.39	0.8	1.0	1.9
UU	0.13	0.13	0.16	0.12	15	0.45	4.8	80	1.5%	2.4	0.5	5.3	4.05	5.08	8.53	0.5	0.7	1.3

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

*ALL STORM SEWER TO BE PRIVATE UNLESS OTHERWISE NOTED

SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins / Design Point	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Facility/ Inlet Size*
					I(5)	I(100)	Q(5)	Q(100)	
1	EX-4A, A	8.22	29.05	53.5	1.61	2.71	13	79	PROP. 36" RCP
2	EX-4B, B	7.67	26.57	65.9	1.30	2.18	10	58	PROP. 36" RCP
3	C1	1.47	3.35	22.9	2.89	4.85	4	16	10' TYPE R AT-GRADE INLET
4	C2, Flowby from DP-3	0.64	2.65	23.4	2.86	4.79	2	13	10' TYPE R SUMP INLET
5	D	0.41	0.60	15.3	3.49	5.86	1.4	4	5' TYPE R SUMP INLET
6	E	1.44	2.14	18.2	3.23	5.43	5	12	10' TYPE R AT-GRADE INLET
7	F	0.64	0.93	15.3	3.49	5.86	2.2	5	10' TYPE R AT-GRADE INLET
8	G	0.77	1.00	12.3	3.81	6.40	3	6	5' TYPE R SUMP INLET
9	H	1.44	1.89	18.1	3.24	5.44	5	10	10' TYPE R SUMP INLET
10	I	0.50	0.65	13.8	3.65	6.13	1.8	4	5' TYPE R SUMP INLET
11	J, Flowby from DP-6 & DP-7	2.11	3.75	19.7	3.11	5.23	7	20	10' TYPE R SUMP INLET
12	K	0.72	0.77	10.1	4.11	6.91	3	5	5' TYPE R SUMP INLET
13	1/2 N	0.83	1.09	17.6	3.28	5.51	3	6	PROP. 18" RCP

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

*ALL STORM SEWER TO BE PRIVATE UNLESS OTHERWISE NOTED

SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins / Design Point	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Facility/ Inlet Size*
					I(5)	I(100)	Q(5)	Q(100)	
14	1/2 N	0.83	1.09	17.6	3.28	5.51	3	6	PROP. 24" RCP
15	M	0.71	2.30	17.1	3.33	5.59	2	13	EXIST. MH WITH GRATE
16	EX-3A, R	0.70	2.30	18.7	3.19	5.35	2	12	
17	EX-3, S, DP-16	5.71	19.79	29.1	2.53	4.24	14	84	PROP. 42" RCP
18	U	1.12	2.35	19.4	3.14	5.27	4	12	10' TYPE R SUMP INLET
19	V	0.41	0.53	11.5	3.92	6.58	1.6	3	5' TYPE R SUMP INLET
20	W	2.03	2.94	15.1	3.51	5.89	7	17	10' TYPE R SUMP INLET
21	X	0.14	0.18	11.0	3.98	6.68	0.5	1.2	5' TYPE R SUMP INLET
22	Y	1.42	2.19	19.1	3.16	5.31	4	12	10' TYPE R SUMP INLET
23	Z	0.48	1.01	14.8	3.54	5.95	2	6	5' TYPE R SUMP INLET
24	AA, OS-2A	0.56	1.36	16.2	3.41	5.72	2	8	CDOT TYPE C INLET
25	BB, OS-2B	0.43	1.00	16.5	3.38	5.67	1	6	CDOT TYPE C INLET
26	EE	0.77	0.87	5.2	5.10	8.56	4	7	5' TYPE R SUMP INLET

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

*ALL STORM SEWER TO BE PRIVATE UNLESS OTHERWISE NOTED

SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins / Design Point	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Facility/ Inlet Size*
					I(5)	I(100)	Q(5)	Q(100)	
27	FF	1.20	1.74	14.2	3.60	6.05	4	11	10' TYPE R SUMP INLET
28	CC	0.63	0.89	11.2	3.96	6.64	2	6	5' TYPE R SUMP INLET
29	DD	0.42	0.49	7.2	4.62	7.75	2	4	5' TYPE R SUMP INLET
30	JJ	0.66	0.82	15.9	3.44	5.77	2	5	5' TYPE R SUMP INLET
31	KK	1.17	1.53	15.9	3.43	5.76	4	9	10' TYPE R AT-GRADE INLET
32	LL, Flowby from DP-31	1.09	1.80	17.2	3.32	5.57	4	10	10' TYPE R AT-GRADE INLET
33	NN	1.44	1.71	11.5	3.92	6.59	6	11	10' TYPE R SUMP INLET
34	MM, Flowby from DP-32	1.50	2.45	19.0	3.17	5.31	5	13	10' TYPE R SUMP INLET
35	II (1/2 Basin)	2.45	3.39	19.5	3.13	5.25	8	18	PROP. 30" RCP
36	II (1/2 Basin)	2.45	3.39	19.5	3.13	5.25	8	18	PROP. 30" RCP
37	O	4.28	5.61	18.5	3.21	5.38	14	30	PROP. 30" RCP
38	P	2.17	3.12	10.4	4.07	6.83	9	21	PROP. 30" RCP
39	GG	1.34	1.71	12.2	3.83	6.43	5	11	15' TYPE R AT-GRADE INLET

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

*ALL STORM SEWER TO BE PRIVATE UNLESS OTHERWISE NOTED

SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins / Design Point	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Facility/ Inlet Size*
					I(5)	I(100)	Q(5)	Q(100)	
40	HH	1.23	1.35	11.2	3.96	6.66	5	9	15' TYPE R AT-GRADE INLET
41	OO	1.04	1.47	15.9	3.43	5.76	4	8	10' TYPE R SUMP INLET
42	OS-2C, PP, TT, UU	1.30	2.91	20.2	3.08	5.16	4	15	CDOT TYPE C INLET
43	OS-1A, QQ	0.34	0.78	14.3	3.59	6.03	1	5	CDOT TYPE C INLET
44	TOTAL TRIBUTARY AREA TO ON-SITE POND	38.94	69.68	32.0	2.38	4.00	93	279	PROP. ON-SITE POND 1

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

* PIPES ARE LISTED AT MAXIMUM SIZE REQUIRED TO ACCOMMODATE Q100 FLOWS AT MINIMUM SLOPE.
 REFER TO INDIVIDUAL PIPE SHEETS FOR HYDRAULIC INFORMATION.
 PIPES ARE TO BE PRIVATE UNLESS OTHERWISE NOTED.
 PRIVATE STORM MATERIALS TO BE RCP OR DOUBLE WALL POLYPROPYLENE (DWPP) TO BE SELECTED BY CONTRACTOR

PIPE ROUTING SUMMARY

Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Pipe Size*
					I(5)	I(100)	Q(5)	Q(100)	
1	DP-1	8.22	29.05	53.48	1.61	2.71	13	79	PROP. 36" RCP
2	DP-2	7.67	26.57	65.92	1.30	2.18	10	58	PROP. 36" RCP
3	DP-4	0.64	2.65	23.38	2.86	4.79	2	13	PROP. 24" RCP
4	DP-5	0.41	0.60	15.3	3.49	5.86	1.4	4	PROP. 18" RCP
5	PR-2, PR-3, PR-4	8.73	29.82	65.9	1.30	2.18	11	65	PROP. 42" RCP
6	PR-1, PR-5	16.95	58.87	65.9	1.30	2.18	22	128	PROP. 48" RCP
7	DP-3 Collected	1.45	1.88	22.9	2.89	4.85	4	9	PROP. 18" RCP
8	PR-6, PR-7	18.40	60.75	66.4	1.29	2.16	24	131	PROP. 48" RCP
9	DP-6	1.44	2.14	18.2	3.23	5.43	5	12	PROP. 24" RCP
10	DP-7	0.64	0.93	15.3	3.49	5.86	2.2	5	PROP. 18" RCP
11	PR-8, PR-9, PR-10	20.48	63.81	66.9	1.28	2.14	26	137	PROP. 48" RCP
12	DP-9	1.44	1.89	18.1	3.24	5.44	5	10	PROP. 24" RCP

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

* PIPES ARE LISTED AT MAXIMUM SIZE REQUIRED TO ACCOMMODATE Q100 FLOWS AT MINIMUM SLOPE.
 REFER TO INDIVIDUAL PIPE SHEETS FOR HYDRAULIC INFORMATION.
 PIPES ARE TO BE PRIVATE UNLESS OTHERWISE NOTED.
 PRIVATE STORM MATERIALS TO BE RCP OR DOUBLE WALL POLYPROPYLENE (DWPP) TO BE SELECTED BY CONTRACTOR

PIPE ROUTING SUMMARY

Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Pipe Size*
					I(5)	I(100)	Q(5)	Q(100)	
13	DP-10	0.50	0.65	13.8	3.65	6.13	1.8	4	PROP. 18" RCP
14	PR-12, PR-13	1.94	2.54	18.6	3.20	5.38	6	14	PROP. 24" RCP
15	PR-11, PR-14	22.41	66.35	67.2	1.27	2.13	28	141	PROP. 48" RCP
16	DP-8	0.77	1.00	12.3	3.81	6.40	3	6	PROP. 18" RCP
17	DP-11	2.11	3.75	19.7	3.11	5.23	7	20	PROP. 30" RCP
18	DP-12	0.72	0.77	10.1	4.11	6.91	3	5	PROP. 18" RCP
19	PR-17, PR-18	2.83	4.52	19.9	3.10	5.20	9	23	PROP. 30" RCP
20	PR-15, PR-16, PR-19	26.01	71.87	67.7	1.26	2.11	33	152	PROP. 48" RCP
21	DP-13	0.83	1.09	17.6	3.28	5.51	3	6	PROP. 18" RCP
22	PR-20, PR-21	26.84	72.96	68.2	1.25	2.09	34	153	PROP. 48" RCP
23	DP-14	0.83	1.09	17.6	3.28	5.51	3	6	PROP. 24" RCP
24	PR-22, PR-23	27.67	74.05	68.2	1.25	2.09	35	155	PROP. 48" RCP

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

* PIPES ARE LISTED AT MAXIMUM SIZE REQUIRED TO ACCOMMODATE Q100 FLOWS AT MINIMUM SLOPE.
 REFER TO INDIVIDUAL PIPE SHEETS FOR HYDRAULIC INFORMATION.
 PIPES ARE TO BE PRIVATE UNLESS OTHERWISE NOTED.
 PRIVATE STORM MATERIALS TO BE RCP OR DOUBLE WALL POLYPROPYLENE (DWPP) TO BE SELECTED BY CONTRACTOR

PIPE ROUTING SUMMARY

Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Pipe Size*
					I(5)	I(100)	Q(5)	Q(100)	
25	DP-17	5.71	19.79	29.1	2.53	4.24	14	84	PROP. 42" RCP
26	DP-19	0.41	0.53	11.5	3.92	6.58	1.6	3	PROP. 18" RCP
27	DP-18, PR-26	1.53	2.88	19.4	3.14	5.27	5	15	PROP. 24" RCP
28	PR-25, PR-27	7.24	22.67	30.3	2.47	4.14	18	94	PROP. 42" RCP
29	DP-20	2.03	2.94	15.1	3.51	5.89	7	17	PROP. 24" RCP
30	DP-21	0.14	0.18	11.0	3.98	6.68	0.5	1.2	PROP. 18" RCP
31	PR-29, PR-30	2.16	3.12	15.9	3.43	5.76	7	18	PROP. 30" RCP
32	DP-22	1.42	2.19	19.1	3.16	5.31	4	12	PROP. 24" RCP
33	DP-23	0.48	1.01	14.8	3.54	5.95	2	6	PROP. 18" RCP
34	PR-31, PR-32, PR-33	4.06	6.33	19.1	3.16	5.31	13	34	PROP. 30" RCP
35	PR-28, PR-34	11.30	29.00	30.5	2.46	4.12	28	120	PROP. 48" RCP
36	DP-24	0.56	1.36	16.2	3.41	5.72	2	8	PROP. 18" RCP

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

* PIPES ARE LISTED AT MAXIMUM SIZE REQUIRED TO ACCOMMODATE Q100 FLOWS AT MINIMUM SLOPE.
 REFER TO INDIVIDUAL PIPE SHEETS FOR HYDRAULIC INFORMATION.
 PIPES ARE TO BE PRIVATE UNLESS OTHERWISE NOTED.
 PRIVATE STORM MATERIALS TO BE RCP OR DOUBLE WALL POLYPROPYLENE (DWPP) TO BE SELECTED BY CONTRACTOR

PIPE ROUTING SUMMARY

Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Pipe Size*
					I(5)	I(100)	Q(5)	Q(100)	
37	DP-25, PR-36	0.98	2.36	16.7	3.36	5.64	3	13	PROP. 24" RCP
38	PR-35, PR-37	12.29	31.36	30.6	2.45	4.11	30	129	PROP. 48" RCP
39	DP-26	0.77	0.87	5.2	5.10	8.56	4	7	PROP. 18" RCP
40	DP-27	1.20	1.74	14.2	3.60	6.05	4	11	PROP. 24" RCP
41	PR-39, PR-40	1.97	2.62	14.2	3.60	6.05	7	16	PROP. 24" RCP
42	PR-38, PR-41	14.25	33.97	30.7	2.45	4.11	35	139	PROP. 48" RCP
43	DP-28	0.63	0.89	11.2	3.96	6.64	2	6	PROP. 18" RCP
44	DP-29, PR-43	1.05	1.38	11.3	3.94	6.62	4	9	PROP. 24" RCP
45	PR-42, PR-44	15.30	35.35	30.9	2.44	4.09	37	145	PROP. 48" RCP
46	DP-30	0.66	0.82	15.9	3.44	5.77	2	5	PROP. 18" RCP
47	PR-45, PR-46	15.96	36.17	31.2	2.42	4.07	39	147	PROP. 48" RCP
48	DP-31 Collected	1.16	1.15	15.9	3.43	5.76	4	7	PROP. 18" RCP

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

* PIPES ARE LISTED AT MAXIMUM SIZE REQUIRED TO ACCOMMODATE Q100 FLOWS AT MINIMUM SLOPE.
 REFER TO INDIVIDUAL PIPE SHEETS FOR HYDRAULIC INFORMATION.
 PIPES ARE TO BE PRIVATE UNLESS OTHERWISE NOTED.
 PRIVATE STORM MATERIALS TO BE RCP OR DOUBLE WALL POLYPROPYLENE (DWPP) TO BE SELECTED BY CONTRACTOR

PIPE ROUTING SUMMARY

Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Pipe Size*
					I(5)	I(100)	Q(5)	Q(100)	
49	PR-47, PR-48	17.12	37.32	31.4	2.41	4.05	41	151	PROP. 48" RCP
50	DP-32 Collected	1.08	1.30	17.2	3.32	5.57	4	7	PROP. 18" RCP
51	PR-49, PR-50	18.20	38.62	31.6	2.40	4.03	44	156	PROP. 48" RCP
52	DP-35	2.45	3.39	19.5	3.13	5.25	8	18	PROP. 30" RCP
53	PR-51, PR-52	20.66	42.01	31.8	2.39	4.02	49	169	PROP. 54" RCP
54	DP-33	1.44	1.71	11.5	3.92	6.59	6	11	PROP. 24" RCP
55	DP-34, PR-54	2.94	4.16	19.0	3.17	5.31	9	22	PROP. 30" RCP
56	PR-53, PR-55	23.59	46.17	31.8	2.39	4.02	56	185	PROP. 54" RCP
57	DP-37	4.28	5.61	18.5	3.21	5.38	14	30	PROP. 30" RCP
58	DP-38	2.17	3.12	10.4	4.07	6.83	9	21	PROP. 30" RCP
59	DP-39 Collected, PR-58	3.51	4.64	12.2	3.83	6.43	13	30	PROP. 36" RCP
60	PR-57, PR-59	7.79	10.25	18.5	3.21	5.38	25	55	PROP. 36" RCP

JOB NAME: RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN
 JOB NUMBER: 1305.10
 DATE: 04/04/24
 CALCULATED BY: MAW

* PIPES ARE LISTED AT MAXIMUM SIZE REQUIRED TO ACCOMMODATE Q100 FLOWS AT MINIMUM SLOPE.
 REFER TO INDIVIDUAL PIPE SHEETS FOR HYDRAULIC INFORMATION.
 PIPES ARE TO BE PRIVATE UNLESS OTHERWISE NOTED.
 PRIVATE STORM MATERIALS TO BE RCP OR DOUBLE WALL POLYPROPYLENE (DWPP) TO BE SELECTED BY CONTRACTOR

PIPE ROUTING SUMMARY

Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity		Flow		Pipe Size*
					I(5)	I(100)	Q(5)	Q(100)	
61	DP-40 Collected	1.23	1.29	11.2	3.96	6.66	5	9	PROP. 18" RCP
62	PR-60, PR-61	9.02	11.53	19.2	3.15	5.29	28	61	PROP. 36" RCP
63	DP-36	2.45	3.39	19.5	3.13	5.25	8	18	PROP. 30" RCP
64	PR-62, PR-63	11.47	14.92	20.1	3.08	5.17	35	77	PROP. 42" RCP
65	PR-56, PR-64	35.06	61.09	32.0	2.38	4.00	84	244	PROP. 60" RCP
66	DP-42	1.30	2.91	21.2	3.00	5.04	4	15	PROP. 24" RCP
67	DP-43, PR-66	1.64	3.69	21.3	3.00	5.03	5	19	PROP. 24" RCP
68	DP-41	1.04	1.47	15.9	3.43	5.76	4	8	PROP. 18" RCP
69	PR-67-PR-68	2.68	5.16	21.5	2.98	5.00	8	26	PROP. 30" RCP

Design Procedure Form: Extended Detention Basin (EDB)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 3

Designer: Marc A. Whorton, P.E.
Company: Classic Consulting
Date: April 4, 2024
Project: Retreat at PrairieRidge Filings 1-3 Preliminary Plan - PDR
Location: Pond 1 - 30" Outfall

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)</p> <p>C) Contributing Watershed Area</p> <p>D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>E) Design Concept (Select EURV when also designing for flood control)</p> <p>F) Design Volume (WQCV) Based on 40-hour Drain Time ($V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$)</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume ($V_{WQCV\ OTHER} = (d_6 * V_{DESIGN} / 0.43)$)</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> <p>I) NRCS Hydrologic Soil Groups of Tributary Watershed i) Percentage of Watershed consisting of Type A Soils ii) Percentage of Watershed consisting of Type B Soils iii) Percentage of Watershed consisting of Type C/D Soils</p> <p>J) Excess Urban Runoff Volume (EURV) Design Volume For HSG A: $EURV_A = 1.68 * i^{1.28}$ For HSG B: $EURV_B = 1.36 * i^{1.08}$ For HSG C/D: $EURV_{C/D} = 1.20 * i^{1.08}$</p> <p>K) User Input of Excess Urban Runoff Volume (EURV) Design Volume (Only if a different EURV Design Volume is desired)</p>	<p>$I_a =$ <input type="text" value="25.5"/> %</p> <p>$i =$ <input type="text" value="0.255"/></p> <p>Area = <input type="text" value="10.400"/> ac</p> <p>$d_6 =$ <input type="text" value="0.42"/> in</p> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> <p>Choose One</p> <p><input type="radio"/> Water Quality Capture Volume (WQCV)</p> <p><input checked="" type="radio"/> Excess Urban Runoff Volume (EURV)</p> </div> <p>$V_{DESIGN} =$ <input type="text"/> ac-ft</p> <p>$V_{DESIGN\ OTHER} =$ <input type="text" value="0.116"/> ac-ft</p> <p>$V_{DESIGN\ USER} =$ <input type="text"/> ac-ft</p> <p>HSG _A = <input type="text" value="0"/> % HSG _B = <input type="text" value="100"/> % HSG _{C/D} = <input type="text" value="0"/> %</p> <p>$EURV_{DESIGN} =$ <input type="text" value="0.269"/> ac-ft</p> <p>$EURV_{DESIGN\ USER} =$ <input type="text"/> ac-ft</p>
<p>2. Basin Shape: Length to Width Ratio (A basin length to width ratio of at least 2:1 will improve TSS reduction.)</p>	<p>L : W = <input type="text" value="2.0"/> : 1</p>
<p>3. Basin Side Slopes</p> <p>A) Basin Maximum Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Z = <input type="text" value="4.00"/> ft / ft</p>
<p>4. Inlet</p> <p>A) Describe means of providing energy dissipation at concentrated inflow locations:</p>	<p>Concrete Forebay</p> <hr/> <hr/> <hr/>
<p>5. Forebay</p> <p>A) Minimum Forebay Volume ($V_{FMIN} =$ <input type="text" value="2"/> % of the WQCV)</p> <p>B) Actual Forebay Volume</p> <p>C) Forebay Depth ($D_F =$ <input type="text" value="18"/> inch maximum)</p> <p>D) Forebay Discharge</p> <p>i) Undetained 100-year Peak Discharge</p> <p>ii) Forebay Discharge Design Flow ($Q_F = 0.02 * Q_{100}$)</p> <p>E) Forebay Discharge Design</p> <p>F) Discharge Pipe Size (minimum 8-inches)</p> <p>G) Rectangular Notch Width</p>	<p>$V_{FMIN} =$ <input type="text" value="0.002"/> ac-ft</p> <p>$V_F =$ <input type="text" value="0.002"/> ac-ft</p> <p>$D_F =$ <input type="text" value="12.0"/> in</p> <p>$Q_{100} =$ <input type="text" value="26.00"/> cfs</p> <p>$Q_F =$ <input type="text" value="0.52"/> cfs</p> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> <p>Choose One</p> <p><input type="radio"/> Berm With Pipe</p> <p><input checked="" type="radio"/> Wall with Rect. Notch</p> <p><input type="radio"/> Wall with V-Notch Weir</p> </div> <p>Calculated $D_P =$ <input type="text"/> in</p> <p>Calculated $W_N =$ <input type="text" value="4.3"/> in</p> <p style="color: blue; font-size: small;">Flow too small for berm w/ pipe</p>

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Marc A. Whorton, P.E.
Company: Classic Consulting
Date: April 4, 2024
Project: Retreat at PrairieRidge Filings 1-3 Preliminary Plan - PDR
Location: Pond 1 - 30" Outfall

<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Choose One <input checked="" type="radio"/> Concrete <input type="radio"/> Soft Bottom </div> <p>S = <input type="text" value="0.0070"/> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft² minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>D_M = <input type="text" value="2.5"/> ft</p> <p>A_M = <input type="text" value="170"/> sq ft</p> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Choose One <input checked="" type="radio"/> Orifice Plate <input type="radio"/> Other (Describe): _____ _____ </div> <p>D_{orifice} = <input type="text" value="2.86"/> inches</p> <p>A_{orifice} = <input type="text" value="19.29"/> square inches</p>
<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>D_{IS} = <input type="text" value="6"/> in</p> <p>V_{IS} = <input type="text"/> cu ft</p> <p>V_s = <input type="text" value="85.0"/> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: $A_t = A_{ot} * 38.5 * (e^{-0.095D})$</p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open are to the total screen are for the material specified.)</p> <p style="margin-left: 40px;">Other (Y/N): <input type="text" value="N"/></p> <p>C) Ratio of Total Open Area to Total Area (only for type 'Other')</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H_{TR})</p> <p>G) Width of Water Quality Screen Opening (W_{opening}) (Minimum of 12 inches is recommended)</p>	<p>A_t = <input type="text" value="566"/> square inches</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 10px; font-size: small;"> Aluminum Amico-Klemp SR Series with Cross Rods 2" O.C. </div> <p>_____</p> <p>_____</p> <p>User Ratio = <input type="text"/></p> <p>A_{total} = <input type="text" value="797"/> sq. in.</p> <p>H = <input type="text" value="6.38"/> feet</p> <p>H_{TR} = <input type="text" value="104.56"/> inches</p> <p>W_{opening} = <input type="text" value="12.0"/> inches VALUE LESS THAN RECOMMENDED MIN. WIDTH. WIDTH HAS BEEN SET TO 12 INCHES.</p>

Design Procedure Form: Extended Detention Basin (EDB)

Sheet 3 of 3

Designer: Marc A. Whorton, P.E.
Company: Classic Consulting
Date: April 4, 2024
Project: Retreat at PrairieRidge Filings 1-3 Preliminary Plan - PDR
Location: Pond 1 - 30" Outfall

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Buried Rip-Rap</p> <hr/> <hr/> <p>Ze = <input type="text" value="4.00"/> ft / ft</p>
<p>11. Vegetation</p>	<p>Choose One</p> <p><input type="radio"/> Irrigated</p> <p><input checked="" type="radio"/> Not Irrigated</p>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p>Per Maintenance Manual</p> <hr/> <hr/> <hr/> <hr/>
<p>Notes: _____</p> <hr/> <hr/> <hr/>	

Design Procedure Form: Extended Detention Basin (EDB)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 3

Designer: Marc A. Whorton, P.E.
Company: Classic Consulting
Date: April 4, 2024
Project: Retreat at PrairieRidge Filings 1-3 Preliminary Plan - PDR
Location: Pond 1 - 60" Outfall

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, I_a</p> <p>B) Tributary Area's Imperviousness Ratio ($i = I_a / 100$)</p> <p>C) Contributing Watershed Area</p> <p>D) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>E) Design Concept (Select EURV when also designing for flood control)</p> <p>F) Design Volume (WQCV) Based on 40-hour Drain Time ($V_{DESIGN} = (1.0 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i) / 12 * Area)$)</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume ($V_{WQCV\ OTHER} = (d_s * V_{DESIGN} / 0.43)$)</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p> <p>I) NRCS Hydrologic Soil Groups of Tributary Watershed i) Percentage of Watershed consisting of Type A Soils ii) Percentage of Watershed consisting of Type B Soils iii) Percentage of Watershed consisting of Type C/D Soils</p> <p>J) Excess Urban Runoff Volume (EURV) Design Volume For HSG A: $EURV_A = 1.68 * i^{1.28}$ For HSG B: $EURV_B = 1.36 * i^{1.08}$ For HSG C/D: $EURV_{C/D} = 1.20 * i^{1.08}$</p> <p>K) User Input of Excess Urban Runoff Volume (EURV) Design Volume (Only if a different EURV Design Volume is desired)</p>	<p>$I_a =$ <input type="text" value="35.2"/> %</p> <p>$i =$ <input type="text" value="0.352"/></p> <p>Area = <input type="text" value="126.330"/> ac</p> <p>$d_s =$ <input type="text" value="0.42"/> in</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> <p>Choose One</p> <p><input type="radio"/> Water Quality Capture Volume (WQCV)</p> <p><input checked="" type="radio"/> Excess Urban Runoff Volume (EURV)</p> </div> <p>$V_{DESIGN} =$ <input type="text"/> ac-ft</p> <p>$V_{DESIGN\ OTHER} =$ <input type="text" value="1.715"/> ac-ft</p> <p>$V_{DESIGN\ USER} =$ <input type="text"/> ac-ft</p> <p>HSG _A = <input type="text" value="0"/> % HSG _B = <input type="text" value="100"/> % HSG _{C/D} = <input type="text" value="0"/> %</p> <p>$EURV_{DESIGN} =$ <input type="text" value="4.636"/> ac-ft</p> <p>$EURV_{DESIGN\ USER} =$ <input type="text"/> ac-ft</p>
<p>2. Basin Shape: Length to Width Ratio (A basin length to width ratio of at least 2:1 will improve TSS reduction.)</p>	<p>L : W = <input type="text" value="2.0"/> : 1</p>
<p>3. Basin Side Slopes</p> <p>A) Basin Maximum Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Z = <input type="text" value="4.00"/> ft / ft</p>
<p>4. Inlet</p> <p>A) Describe means of providing energy dissipation at concentrated inflow locations:</p>	<p>Concrete Forebay</p> <hr/> <hr/> <hr/>
<p>5. Forebay</p> <p>A) Minimum Forebay Volume ($V_{FMIN} =$ <input type="text" value="3%"/> of the WQCV)</p> <p>B) Actual Forebay Volume</p> <p>C) Forebay Depth ($D_F =$ <input type="text" value="30"/> inch maximum)</p> <p>D) Forebay Discharge</p> <p>i) Undetained 100-year Peak Discharge</p> <p>ii) Forebay Discharge Design Flow ($Q_F = 0.02 * Q_{100}$)</p> <p>E) Forebay Discharge Design</p> <p>F) Discharge Pipe Size (minimum 8-inches)</p> <p>G) Rectangular Notch Width</p>	<p>$V_{FMIN} =$ <input type="text" value="0.051"/> ac-ft</p> <p>$V_F =$ <input type="text" value="0.051"/> ac-ft</p> <p>$D_F =$ <input type="text" value="30.0"/> in</p> <p>$Q_{100} =$ <input type="text" value="244.00"/> cfs</p> <p>$Q_F =$ <input type="text" value="4.88"/> cfs</p> <div style="border: 1px solid black; padding: 5px; margin: 5px 0;"> <p>Choose One</p> <p><input type="radio"/> Berm With Pipe</p> <p><input checked="" type="radio"/> Wall with Rect. Notch</p> <p><input type="radio"/> Wall with V-Notch Weir</p> </div> <p>Calculated $D_P =$ <input type="text"/> in</p> <p>Calculated $W_N =$ <input type="text" value="10.4"/> in</p>

Design Procedure Form: Extended Detention Basin (EDB)

Designer: Marc A. Whorton, P.E.
Company: Classic Consulting
Date: April 4, 2024
Project: Retreat at PrairieRidge Filings 1-3 Preliminary Plan - PDR
Location: Pond 1 - 60" Outfall

<p>6. Trickle Channel</p> <p>A) Type of Trickle Channel</p> <p>F) Slope of Trickle Channel</p>	<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Choose One <input checked="" type="radio"/> Concrete <input type="radio"/> Soft Bottom </div> <p>S = <input type="text" value="0.0070"/> ft / ft</p>
<p>7. Micropool and Outlet Structure</p> <p>A) Depth of Micropool (2.5-foot minimum)</p> <p>B) Surface Area of Micropool (10 ft² minimum)</p> <p>C) Outlet Type</p> <p>D) Smallest Dimension of Orifice Opening Based on Hydrograph Routing (Use UD-Detention)</p> <p>E) Total Outlet Area</p>	<p>D_M = <input type="text" value="2.5"/> ft</p> <p>A_M = <input type="text" value="170"/> sq ft</p> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Choose One <input checked="" type="radio"/> Orifice Plate <input type="radio"/> Other (Describe): _____ _____ </div> <p>D_{orifice} = <input type="text" value="2.86"/> inches</p> <p>A_{out} = <input type="text" value="19.29"/> square inches</p>
<p>8. Initial Surcharge Volume</p> <p>A) Depth of Initial Surcharge Volume (Minimum recommended depth is 4 inches)</p> <p>B) Minimum Initial Surcharge Volume (Minimum volume of 0.3% of the WQCV)</p> <p>C) Initial Surcharge Provided Above Micropool</p>	<p>D_{IS} = <input type="text" value="6"/> in</p> <p>V_{IS} = <input type="text" value="224"/> cu ft</p> <p>V_s = <input type="text" value="85.0"/> cu ft</p>
<p>9. Trash Rack</p> <p>A) Water Quality Screen Open Area: $A_t = A_{ot} * 38.5 * (e^{-0.095D})$</p> <p>B) Type of Screen (If specifying an alternative to the materials recommended in the USDCM, indicate "other" and enter the ratio of the total open are to the total screen are for the material specified.)</p> <p style="text-align: right;">Other (Y/N): <input type="text" value="N"/></p> <p>C) Ratio of Total Open Area to Total Area (only for type 'Other')</p> <p>D) Total Water Quality Screen Area (based on screen type)</p> <p>E) Depth of Design Volume (EURV or WQCV) (Based on design concept chosen under 1E)</p> <p>F) Height of Water Quality Screen (H_{TR})</p> <p>G) Width of Water Quality Screen Opening (W_{opening}) (Minimum of 12 inches is recommended)</p>	<p>A_t = <input type="text" value="566"/> square inches</p> <div style="border: 1px solid black; padding: 2px; margin-bottom: 10px;"> Aluminum Amico-Klemp SR Series with Cross Rods 2" O.C. </div> <p>_____</p> <p>_____</p> <p>User Ratio = <input type="text"/></p> <p>A_{total} = <input type="text" value="797"/> sq. in.</p> <p>H = <input type="text" value="6.38"/> feet</p> <p>H_{TR} = <input type="text" value="104.56"/> inches</p> <p>W_{opening} = <input type="text" value="12.0"/> inches VALUE LESS THAN RECOMMENDED MIN. WIDTH. WIDTH HAS BEEN SET TO 12 INCHES.</p>

Design Procedure Form: Extended Detention Basin (EDB)


Sheet 3 of 3

Designer: Marc A. Whorton, P.E.
Company: Classic Consulting
Date: April 4, 2024
Project: Retreat at PrairieRidge Filings 1-3 Preliminary Plan - PDR
Location: Pond 1 - 60" Outfall

<p>10. Overflow Embankment</p> <p>A) Describe embankment protection for 100-year and greater overtopping:</p> <p>B) Slope of Overflow Embankment (Horizontal distance per unit vertical, 4:1 or flatter preferred)</p>	<p>Buried Rip-Rap</p> <hr/> <hr/> <p>Ze = <input type="text" value="4.00"/> ft / ft</p>
<p>11. Vegetation</p>	<p>Choose One</p> <p><input type="radio"/> Irrigated</p> <p><input checked="" type="radio"/> Not Irrigated</p>
<p>12. Access</p> <p>A) Describe Sediment Removal Procedures</p>	<p>Per Maintenance Manual</p> <hr/> <hr/> <hr/> <hr/>
<p>Notes: _____</p> <hr/> <hr/> <hr/>	

DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.06 (July 2022)




DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)

Project: **RETREAT AT PRAIRIERIDGE FILINGS 1-3 PRELIMINARY PLAN - PDR**

Basin ID: **POND 1**



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	4.54	1.918	Orifice Plate
Zone 2 (EURV)	6.38	2.946	Orifice Plate
Zone 3 (100-year)	8.43	5.242	Weir&Pipe (Restrict)
Total (all zones)		10.106	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
 Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain
 Underdrain Orifice Area = ft²
 Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Centroid of Lowest Orifice = 0.00 ft (relative to basin bottom at Stage = 0 ft)
 Depth at top of Zone using Orifice Plate = 6.38 ft (relative to basin bottom at Stage = 0 ft)
 Orifice Plate: Orifice Vertical Spacing = 25.50 inches
 Orifice Plate: Orifice Area per Row = 6.43 sq. inches (use rectangular openings)

Calculated Parameters for Plate
 WQ Orifice Area per Row = 4.465E-02 ft²
 Elliptical Half-Width = N/A feet
 Elliptical Slot Centroid = N/A feet
 Elliptical Slot Area = N/A ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	2.13	4.25					
Orifice Area (sq. inches)	6.43	6.43	6.43					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

	Not Selected	Not Selected	
Invert of Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	N/A	N/A	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =	N/A	N/A	inches

Calculated Parameters for Vertical Orifice

	Not Selected	Not Selected	
Vertical Orifice Area =	N/A	N/A	ft ²
Vertical Orifice Centroid =	N/A	N/A	feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

	Zone 3 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	6.38	N/A	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	18.00	N/A	feet
Overflow Weir Grate Slope =	6.00	N/A	H:V
Horiz. Length of Weir Sides =	6.00	N/A	feet
Overflow Grate Type =	Type C Grate	N/A	
Debris Clogging % =	50%	N/A	%

Calculated Parameters for Overflow Weir

	Zone 3 Weir	Not Selected	
Height of Grate Upper Edge, H _u =	7.38	N/A	feet
Overflow Weir Slope Length =	6.08	N/A	feet
Grate Open Area / 100-yr Orifice Area =	7.92	N/A	
Overflow Grate Open Area w/o Debris =	76.20	N/A	ft ²
Overflow Grate Open Area w/ Debris =	38.10	N/A	ft ²

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	2.50	N/A	ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	42.00	N/A	inches
Restrictor Plate Height Above Pipe Invert =	42.00		inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate

	Zone 3 Restrictor	Not Selected	
Outlet Orifice Area =	9.62	N/A	ft ²
Outlet Orifice Centroid =	1.75	N/A	feet
Half-Central Angle of Restrictor Plate on Pipe =	3.14	N/A	radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage =	9.00	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	90.00	feet
Spillway End Slopes =	3.00	H:V
Freeboard above Max Water Surface =	1.00	feet

Calculated Parameters for Spillway

Spillway Design Flow Depth =	0.96	feet
Stage at Top of Freeboard =	10.96	feet
Basin Area at Top of Freeboard =	3.91	acres
Basin Volume at Top of Freeboard =	19.11	acre-ft




Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	3.48
One-Hour Rainfall Depth (in) =	1.918	4.864	4.891	7.750	10.365	14.247	17.223	21.158	33.093
CUHP Runoff Volume (acre-ft) =	N/A	N/A	4.891	7.750	10.365	14.247	17.223	21.158	33.093
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	14.3	40.2	61.3	111.5	139.8	178.7	289.1
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	18.9					133.7	
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.10	0.13	0.42	0.77	0.97	0.93	2.00
Peak Inflow Q (cfs) =	N/A	N/A	59.3	96.1	124.4	180.8	217.9	262.7	404.7
Peak Outflow Q (cfs) =	0.9	1.3	1.3	16.4	34.2	66.5	90.5	126.3	284.0
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.9	0.6	0.6	0.6	0.9	1.0
Structure Controlling Flow =	Plate	Overflow Weir 1	Plate	Overflow Weir 1	Spillway				
Max Velocity through Grate 1 (fps) =	N/A	N/A	N/A	0.2	0.4	0.8	1.2	1.6	1.9
Max Velocity through Grate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	38	66	67	70	68	65	63	61	54
Time to Drain 99% of Inflow Volume (hours) =	40	70	71	76	75	74	73	71	68
Maximum Ponding Depth (ft) =	4.54	6.38	6.26	7.09	7.51	8.07	8.43	8.90	9.62
Area at Maximum Ponding Depth (acres) =	1.19	2.05	1.99	2.39	2.61	2.90	3.08	3.33	3.55
Maximum Volume Stored (acre-ft) =	1.923	4.873	4.631	6.423	7.472	9.041	10.087	11.626	14.110

DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-Detention, Version 4.06 (July 2022)



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: _____


Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.25	0.02	1.23
	0:15:00	0.00	0.00	2.10	3.48	4.34	2.94	3.84	3.63	6.91
	0:20:00	0.00	0.00	8.85	13.71	17.93	9.40	11.21	12.05	22.76
	0:25:00	0.00	0.00	27.89	46.57	65.04	28.08	33.88	39.02	82.34
	0:30:00	0.00	0.00	49.68	82.37	109.64	97.41	119.58	138.35	233.91
	0:35:00	0.00	0.00	59.27	96.09	124.36	157.06	191.00	228.00	359.69
	0:40:00	0.00	0.00	58.94	93.33	119.79	180.85	217.88	262.75	404.71
	0:45:00	0.00	0.00	54.09	85.12	110.39	178.49	213.98	262.22	400.82
	0:50:00	0.00	0.00	48.60	77.16	100.31	169.28	202.80	250.33	382.05
	0:55:00	0.00	0.00	43.85	69.79	91.03	155.38	186.36	233.12	356.25
	1:00:00	0.00	0.00	40.16	63.65	83.86	140.57	169.14	216.26	331.69
	1:05:00	0.00	0.00	37.16	58.37	77.70	128.38	154.98	202.98	311.79
	1:10:00	0.00	0.00	33.60	53.25	71.67	115.53	139.83	183.63	283.15
	1:15:00	0.00	0.00	29.76	47.85	65.82	102.22	123.97	160.54	249.23
	1:20:00	0.00	0.00	26.14	42.32	59.40	88.70	107.60	137.00	213.75
	1:25:00	0.00	0.00	23.40	38.19	53.63	76.72	93.17	116.63	183.18
	1:30:00	0.00	0.00	21.50	35.26	48.60	67.54	82.08	101.33	159.39
	1:35:00	0.00	0.00	19.94	32.70	44.10	59.82	72.72	89.04	139.98
	1:40:00	0.00	0.00	18.54	29.79	40.04	53.16	64.58	78.41	123.05
	1:45:00	0.00	0.00	17.16	26.67	36.27	47.11	57.19	68.77	107.69
	1:50:00	0.00	0.00	15.80	23.66	32.68	41.56	50.40	59.84	93.41
	1:55:00	0.00	0.00	14.11	20.78	28.96	36.23	43.87	51.40	79.95
	2:00:00	0.00	0.00	12.25	17.92	24.87	31.10	37.62	43.49	67.38
	2:05:00	0.00	0.00	10.09	14.58	20.11	25.28	30.51	34.97	53.71
	2:10:00	0.00	0.00	7.89	11.21	15.43	19.18	23.06	26.22	40.13
	2:15:00	0.00	0.00	6.00	8.53	12.04	13.65	16.47	18.63	29.33
	2:20:00	0.00	0.00	4.67	6.74	9.73	10.12	12.37	13.72	22.04
	2:25:00	0.00	0.00	3.79	5.47	7.95	7.69	9.47	10.27	16.70
	2:30:00	0.00	0.00	3.10	4.46	6.48	5.95	7.34	7.67	12.59
	2:35:00	0.00	0.00	2.54	3.64	5.25	4.59	5.67	5.69	9.42
	2:40:00	0.00	0.00	2.06	2.94	4.20	3.57	4.40	4.17	6.93
	2:45:00	0.00	0.00	1.66	2.35	3.31	2.74	3.37	3.01	5.04
	2:50:00	0.00	0.00	1.34	1.85	2.58	2.10	2.57	2.22	3.75
	2:55:00	0.00	0.00	1.08	1.45	2.01	1.64	2.01	1.75	2.93
	3:00:00	0.00	0.00	0.88	1.14	1.57	1.29	1.58	1.40	2.33
	3:05:00	0.00	0.00	0.70	0.89	1.22	1.01	1.24	1.12	1.84
	3:10:00	0.00	0.00	0.55	0.67	0.93	0.78	0.95	0.87	1.41
	3:15:00	0.00	0.00	0.41	0.49	0.69	0.58	0.71	0.64	1.04
	3:20:00	0.00	0.00	0.29	0.34	0.49	0.42	0.51	0.46	0.73
	3:25:00	0.00	0.00	0.19	0.23	0.32	0.28	0.34	0.30	0.47
	3:30:00	0.00	0.00	0.12	0.14	0.18	0.17	0.20	0.18	0.27
	3:35:00	0.00	0.00	0.06	0.08	0.09	0.09	0.10	0.09	0.12
	3:40:00	0.00	0.00	0.03	0.03	0.03	0.03	0.03	0.03	0.03
	3:45:00	0.00	0.00	0.01	0.01	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

REFERENCE MATERIAL

EXISTING DRAINAGE MAP HOMESTEAD NORTH



SEE SHEET 2

Tributary Sub-basin	Area (acres)	Percent Impervious	C _s	C ₁₀₀	t _c (min)	Q _s (cfs)	Q ₁₀₀ (cfs)
E-1	4.50	9%	0.14	0.39	48.7	1.1	5.2
E-2	180.30	3%	0.09	0.35	47.4	28.1	192.9
E-3	12.39	4%	0.10	0.37	46.9	2.2	13.7
E-4	70.90	2%	0.08	0.35	49.0	9.9	72.7
E-5	18.80	2%	0.08	0.35	34.9	3.4	24.9
E6.1	124.90	2%	0.08	0.35	48.1	17.7	130.0
E6.2	49.61	2%	0.08	0.35	44.2	7.5	55.4
H1	45.20	3%	0.09	0.36	34.7	8.9	61.0
H2	16.10	2%	0.08	0.35	25.1	3.5	26.0
H3	28.40	3%	0.09	0.35	31.3	5.9	40.8

DP	Q5		Q100	
	Total	Total	Total	Total
1h	8.0	52.4		
2h	10.2	69.0		
3h	32.5	223.2		
1o	1.1	5.2		
2o	28.1	192.9		
3o	2.2	13.7		
4o	9.9	72.7		
5o	12.5	92.0		
6.2o	7.5	55.4		
6.1o	36.9	270.9		

LEGEND

BASIN ID
A: BASIN LABEL
B: AREA
C: C - 100 YR
D: C - 5 YR



DESIGN POINT



EXISTING FLOW DIRECTION



BASIN DRAINAGE AREA



EXISTING STORM SEWER



EXISTING PROPERTY LINE



ROW EXISTING



FL EXISTING




SIDEWALK EXISTING



DRAINAGE ACCESS & MAINTENANCE EASEMENT



EXISTING



EX DRAINAGE MAP
HOMESTEAD NORTH
JOB NO. 25188.00
1-4-2022
SHEET 1 OF 2

J-R ENGINEERING
A Westrian Company

Centennial 303-740-9393 • Colorado Springs 719-593-2593
Fort Collins 970-491-9888 • www.jrengineering.com

DRAINAGE MAP

LEGEND


BASIN ID
 A: BASIN LABEL
 B: AREA
 C: C-100 YR
 D: C-5 YR

DESIGN POINT
 PROPOSED FLOW DIRECTION

BASIN DRAINAGE AREA
 EXISTING STORM SEWER
 STORM SEWER PROPOSED
 PROPOSED R.O.W



PROPOSED PROPERTY LINES
 PROPOSED SIDEWALK
 EXISTING PROPERTY LINE
 ROW EXISTING
 FL EXISTING
 SIDEWALK EXISTING
 DRAINAGE ACCESS & MAINTENANCE
 EASEMENT

EXISTING
 PROPOSED




Tributary Sub-basin	Area (acres)	Percent Impervious	C5	C100	tc (min)	Q5 (cfs)	Q100 (cfs)
C1	2.82	69%	0.52	0.65	13.1	5.4	11.4
C2.1	0.20	91%	0.82	0.90	5.0	0.8	1.6
C2.2	4.69	73%	0.56	0.68	12.8	9.9	20.3
C2.3	0.83	67%	0.54	0.68	10.1	1.9	3.9
C3.1	0.35	73%	0.68	0.79	5.0	1.2	2.4
C3.2	1.46	71%	0.56	0.68	8.4	3.6	7.4
C4.1	6.34	65%	0.49	0.63	12.0	12.1	25.9
C4.2	3.59	57%	0.44	0.58	12.9	5.9	13.1
C5	0.16	81%	0.74	0.84	6.4	0.6	1.0
C6	2.59	20%	0.21	0.43	6.8	2.5	8.8
D1	1.77	40%	0.40	0.60	16.5	2.4	6.0
D2	1.44	56%	0.55	0.78	15.0	2.8	6.6
D3	0.18	68%	0.63	0.76	5.4	0.6	1.2
D4	0.19	57%	0.54	0.70	6.3	0.5	1.1
D5	0.91	77%	0.71	0.82	6.0	3.1	6.1
D6	0.83	69%	0.64	0.77	6.4	2.5	5.2
D7	0.75	79%	0.72	0.82	5.0	2.8	5.3
D8	0.72	69%	0.64	0.74	5.0	2.4	4.6
OS1	2.84	2%	0.08	0.35	14.5	0.8	6.0
OS2	179.61	2%	0.08	0.35	47.4	27.1	190.9
OS3	11.98	2%	0.08	0.35	47.6	1.7	12.6

DP	Q5 Total	Q100 Total
1c	5.4	11.4
2.3c	7.1	14.9
2.3i	7.0	11.5
2.1c	0.8	1.6
2.1i	0.8	1.5
2.2C	9.8	20.1
4.2c	5.9	13.1
4.2i	5.9	10.5
4C	18.8	41.8
3.1	4.7	11.6
3.1c	1.2	2.4
3.1i	1.2	1.9
3.2	7.9	12.9
3.3	9.1	17.6
3.4	26.0	54.9
3.2c	3.6	7.8
5C	4.1	8.7
6C	2.5	8.8
3.5	30.7	65.0
o1	0.8	6.0
1d	2.4	6.0
1.1d	3.2	11.7
2d	2.8	6.6
1.2d	5.8	18.0
3d	0.6	1.2
4d	0.5	1.1
4.1d	0.5	1.1
1.3d	1.0	2.2
1.4d	6.6	19.6
2o	27.1	190.9
6d	2.1	4.3
6.1d	28.1	192.5
1.5d	29.2	195.0
5d	3.1	6.1
1.6d	32.7	205.4
1.7d	36.1	221.0
3o	1.7	12.6
8d	2.5	14.3
2.1d	2.5	13.2
7d	2.4	5.3
2.2d	3.5	16.0
1.7d	36.1	221.0
5	56.0	264.1



DRAINAGE MAP
 HOMESTEAD NORTH - FILLING ONE
 JOB NO. 25188.00
 6/13/22
 SHEET 1 OF 2


SEE SHEET 2



Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

DRAINAGE MAP

SEE SHEET 1



LEGEND

BASIN ID
 A: BASIN LABEL
 B: AREA
 C: C -100 YR
 D: C-5 YR

DESIGN POINT
 PROPOSED FLOW DIRECTION

BASIN DRAINAGE AREA
 EXISTING STORM SEWER
 STORM SEWER PROPOSED

PROPOSED R.O.W
 PROPOSED PROPERTY LINES
 PROPOSED SIDEWALK
 EXISTING PROPERTY LINE
 ROW EXISTING
 FL EXISTING
 SIDEWALK EXISTING
 DRAINAGE ACCESS & MAINTENANCE EASEMENT


EXISTING
 PROPOSED

Design Point	Inlet Size
Inlet DP 2.3C	15' Type R
Inlet DP 2.1C	5' Type R
Inlet DP 4.2C	15' Type R
Inlet DP 3.1C	5' Type R
Inlet DP 4C	15' Type R
Inlet DP 5C	15' Type R
Inlet DP 3D	5' Type R
Inlet DP 4D	5' Type R
Inlet DP 5D	10' Type R
Inlet DP 6D	10' Type R
Inlet DP 7D	10' Type R
Inlet DP 8D	20' Type R
Inlet DP 1D	Type D Inlet
Inlet DP 2D	Type D Inlet

Tributary	Area	Percent			tc	Q5	Q100
Sub-basin	(acres)	Impervious	C5	C100	(min)	(cfs)	(cfs)
C1	2.82	69%	0.52	0.65	13.1	5.4	11.4
C2.1	0.20	91%	0.82	0.90	5.0	0.8	1.6
C2.2	4.69	73%	0.56	0.68	12.8	9.9	20.3
C2.3	0.83	67%	0.54	0.68	10.1	1.9	3.9
C3.1	0.35	73%	0.68	0.79	5.0	1.2	2.4
C3.2	1.46	71%	0.56	0.68	8.4	3.6	7.4
C4.1	6.34	65%	0.49	0.63	12.0	12.1	25.9
C4.2	3.59	57%	0.44	0.58	12.9	5.9	13.1
C5	0.16	81%	0.74	0.84	6.4	0.6	1.0
C6	2.59	20%	0.21	0.43	6.8	2.5	8.8
D1	1.77	40%	0.40	0.60	16.5	2.4	6.0
D2	1.44	56%	0.55	0.78	15.0	2.8	6.6
D3	0.18	68%	0.63	0.76	5.4	0.6	1.2
D4	0.19	57%	0.54	0.70	6.3	0.5	1.1
D5	0.91	77%	0.71	0.82	6.0	3.1	6.1
D6	0.83	69%	0.64	0.77	6.4	2.5	5.2
D7	0.75	79%	0.72	0.82	5.0	2.8	5.3
D8	0.72	69%	0.64	0.74	5.0	2.4	4.6
OS1	2.84	2%	0.08	0.35	14.5	0.8	6.0
OS2	179.61	2%	0.08	0.35	47.4	27.1	190.9
OS3	11.98	2%	0.08	0.35	47.6	1.7	12.6

DP	Q5		Q100	
	Total	Total	Total	Total
1c	5.4	11.4		
2.3c	7.1	14.9		
2.3i	7.0	11.5		
2.1c	0.8	1.6		
2.1i	0.8	1.5		
2.2c	9.8	20.1		
4.2c	5.9	13.1		
4.2i	5.9	10.5		
4C	18.8	41.8		
3.1	4.7	11.6		
3.1c	1.2	2.4		
3.1i	1.2	1.9		
3.2	7.9	12.9		
3.3	9.1	17.6		
3.4	26.0	54.9		
3.2c	3.6	7.8		
5C	4.1	8.7		
6C	2.5	8.8		
3.5	30.7	65.0		
o1	0.8	6.0		
1d	2.4	6.0		
1.1d	3.2	11.7		
2d	2.8	6.6		
1.2d	5.8	18.0		
3d	0.6	1.2		
4d	0.5	1.1		
4.1d	0.5	1.1		
1.3d	1.0	2.2		
1.4d	6.6	19.6		
2o	27.1	190.9		
6d	2.1	4.3		
6.1d	28.1	192.5		
Inlet DP 3D	5' Type R			
1.5d	29.2	195.0		
5d	3.1	6.1		
1.6d	32.7	205.4		
1.7d	36.1	221.0		
3o	1.7	12.6		
8d	2.5	14.3		
2.1d	2.5	13.2		
7d	2.4	5.3		
2.2d	3.5	16.0		
1.7d	36.1	221.0		
5	56.0	264.1		

DESIGN POINT FROM M&S MDDP (PROPOSED CONDITIONS MAP) TO BE EXISTING AT THE TIME OF CHANNEL DEVELOPMENT
 $Q_{(100)} = 1775.7$ CFS
 $Q_{(5)} = 366.6$ CFS




DRAINAGE MAP
 HOMESTEAD NORTH FILLING NO. 1
 JOB NO. 25188.00
 6/13/22
 SHEET 2 OF 2



Centennial 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

WATER QUALITY CAPTURE PLAN


HOMESTEAD NORTH



NOTE:

1. A SEPARATE PLAN FOR STERLING RANCH ROAD AND BRIARGATE PKWY WILL BE PROVIDED IN A THE SEPARATE FDR REQUIRED FOR CONSTRUCTION OF THESE ROADWAYS.
2. A TOTAL OF 15,488 SQ-FT ON SITE IS LEFT UNTREATED.
3. POND C TREATS THE IMPROVEMENTS TO VOLLMER ROAD AND THE OFFSITE TRIBUTARY AREA

POND C 224.3 ACRES, 10.3% IMPERVIOUS



WQ - POND C
 HOMESTEAD NORTH - FILING ONE
 JOB NO. 25188.00
 06-13-2022
 SHEET 1 OF 1

JR ENGINEERING
 A Westlan Company

Central 303-740-9393 • Colorado Springs 719-593-2593
 Fort Collins 970-491-9888 • www.jrengineering.com

COMPOSITE % IMPERVIOUS & COMPOSITE RUNOFF COEFFICIENT CALCULATIONS

Subdivision: Homestead North Fil. 1
 Location: El Paso County

Project Name: Homestead North-Filing 1
 Project No.: 25188.00
 Calculated By: ARJ
 Checked By: _____
 Date: 6/15/22

Basin ID	Total Area (ac)	Streets/Paved (100% Impervious)				Residential (45%-65% Impervious)				Lawns (2% Impervious)				Basins Total Weighted C Values		Basins Total Weighted % Imp.
		C ₅	C ₁₀₀	Area (ac)	Weighted % Imp.	C ₅	C ₁₀₀	Area (ac)	Weighted % Imp.	C ₅	C ₁₀₀	Area (ac)	Weighted % Imp.	C ₅	C ₁₀₀	
C1	2.82	0.90	0.96	0.49	17.2%	0.45	0.59	2.25	51.7%	0.08	0.35	0.09	0.1%	0.52	0.65	69.0%
C2.1	0.20	0.90	0.96	0.18	90.5%	0.45	0.59	0.00	0.0%	0.08	0.35	0.02	0.2%	0.82	0.90	90.7%
C2.2	4.69	0.90	0.96	1.26	26.9%	0.45	0.59	3.33	46.1%	0.08	0.35	0.10	0.0%	0.56	0.68	73.0%
C2.3	0.83	0.90	0.96	0.28	34.1%	0.45	0.59	0.41	32.4%	0.08	0.35	0.13	0.3%	0.54	0.68	66.9%
C3.1	0.35	0.90	0.96	0.25	72.8%	0.45	0.59	0.00	0.0%	0.08	0.35	0.09	0.5%	0.68	0.79	73.3%
C3.2	1.66	0.90	0.96	0.42	25.1%	0.45	0.59	0.96	37.7%	0.08	0.35	0.28	0.3%	0.50	0.64	63.2%
C4.1	6.34	0.90	0.96	1.04	16.4%	0.45	0.59	4.76	48.8%	0.08	0.35	0.55	0.2%	0.49	0.63	65.5%
C4.2	3.59	0.90	0.96	0.59	16.4%	0.45	0.59	2.20	39.8%	0.08	0.35	0.65	0.4%	0.44	0.58	56.6%
C5	0.16	0.90	0.96	0.13	80.9%	0.45	0.59	0.00	0.0%	0.08	0.35	0.03	0.4%	0.74	0.84	81.3%
C6	2.59	0.90	0.96	0.27	10.6%	0.45	0.59	0.32	8.1%	0.08	0.35	1.89	1.5%	0.21	0.43	20.2%
36" Pipe w/ Forebay	23.23															61.3%
D1	1.77	0.90	0.96	0.69	38.8%	0.45	0.59	0.00	0.0%	0.08	0.35	1.14	1.3%	0.40	0.60	40.1%
D2	1.44	0.90	0.96	0.79	54.9%	0.45	0.59	0.00	0.0%	0.08	0.35	1.02	1.4%	0.55	0.78	56.4%
D3	0.18	0.90	0.96	0.12	67.0%	0.45	0.59	0.00	0.0%	0.08	0.35	0.06	0.7%	0.63	0.76	67.6%
D4	0.19	0.90	0.96	0.11	56.6%	0.45	0.59	0.00	0.0%	0.08	0.35	0.08	0.9%	0.54	0.70	57.5%
D5	0.91	0.90	0.96	0.70	76.5%	0.45	0.59	0.00	0.0%	0.08	0.35	0.21	0.5%	0.71	0.82	77.0%
D6	0.83	0.90	0.96	0.57	68.4%	0.45	0.59	0.00	0.0%	0.08	0.35	0.26	0.6%	0.64	0.77	69.0%
D7	0.75	0.90	0.96	0.59	78.5%	0.45	0.59	0.00	0.0%	0.08	0.35	0.14	0.4%	0.72	0.82	78.9%
D8	0.72	0.90	0.96	0.49	68.8%	0.45	0.59	0.00	0.0%	0.08	0.35	0.17	0.5%	0.64	0.74	69.3%
OffSite Basins																
OS1	2.84	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.08	0.35	2.85	2.0%	0.08	0.35	2.0%
OS2	179.61	0.90	0.96	0.91	0.5%	0.45	0.59	0.00	0.0%	0.08	0.35	178.71	2.0%	0.08	0.35	2.5%
OS3	11.98	0.90	0.96	0.00	0.0%	0.45	0.59	0.00	0.0%	0.08	0.35	11.99	2.0%	0.08	0.35	2.0%
60" Pipe w/ Forebay	201.22															4.4%
Pond C	224.4															10.3%

point 5C, a 15' type R sump inlet. Basin C5 collects runoff from basin C3.2 and C5. The runoff from basin C ultimately outfalls into pond C. In the event the inlet clogs at Basin C5 the runoff will overflow to pond C. A berm has been graded to ensure that the overflow path will go into pond C.

Basin C6 2.59 acres and 20% percent impervious, is comprised of pond C and some single-family residential area. Runoff ($Q_5=2.5$ cfs, $Q_{100}=8.8$ cfs) generated in Basin B11 sheet flows into Pond C where it is treated for water-quality and is detained up until the 100 year-event. The MHFD Detention sheet for pond C is shown in Appendix C of this report.

Pond C has a tributary area of 224.3 acres and is 10.3 % impervious. Pond C has been graded in to fit the design volume, as shown in Appendix C of this report. This pond will be built in phase 1 of Homestead North at Sterling Ranch. The Pond C overflow emergency spillway will overflow into Sand Creek. The WQCV, 5 year and 100 year volumes, releases rates and stages for pond C are shown in Table 2.3 below. These results correspond to the Routed Hydrograph results, as shown in Appendix C of this report.


TABLE 2.3 Pond C			
	Stage –ft	Volume (Acres)	Release Rate (cfs)
WQCV	3.32	1.288	0.7
5 Year	6.22	4.310	20.6
100 Year	9.94	9.263	173.8

The following basins are tributary to the adjacent portion of Vollmer Road being designed by JR Engineering. Runoff will be detained within pond C and the runoff will then be released into Sand Creek adjacent to the crossing of Briargate road and Sand Creek.

Basin D1 has a tributary area of 1.77 acres and is 40.1% impervious. Basin D1 consists of the northwest portion of Vollmer road (Rural Cross Section). Runoff from basin D1 ($Q_5=2.4$ cfs, $Q_{100}=6.0$ cfs) drains to an adjacent roadside swale and drains into a type C inlet at design point 1D runoff is then piped at design point 1.1D in confluence with upstream runoff from the inlet collect at design point 1o. From here on the runoff is piped with upstream runoff from basin OS1 into the Vollmer storm sewer system.

Basin D2 has a tributary area of 1.44 acres and is 56.4% impervious. Basin D2 consists of the northeast portion of Vollmer road (Rural Cross Section). Runoff from basin D2 ($Q_5=2.8$ cfs, $Q_{100}=6.6$ cfs) drains to an adjacent roadside swale and drains into a type C inlet at design point 2D. From here






DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD-*Detention*, Version 4.04 (February 2021)

Project: Pond C with offsite flow

Basin ID: _____



Example Zone Configuration (Retention Pond)

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WOCV)	3.32	1.285	Orifice Plate
Zone 2 (EURV)	4.27	0.892	Orifice Plate
Zone 3 (100-year)	9.35	6.216	Weir&Pipe (Restrict)
Total (all zones)		8.393	

User Input: Orifice at Underdrain Outlet (typically used to drain WOCV in a Filtration BMP)

Underdrain Orifice Invert Depth = ft (distance below the filtration media surface)
 Underdrain Orifice Diameter = inches

Calculated Parameters for Underdrain
 Underdrain Orifice Area = ft²
 Underdrain Orifice Centroid = feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WOCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice = ft (relative to basin bottom at Stage = 0 ft)
 Depth at top of Zone using Orifice Plate = ft (relative to basin bottom at Stage = 0 ft)
 Orifice Plate: Orifice Vertical Spacing = inches
 Orifice Plate: Orifice Area per Row = sq. inches (use rectangular openings)

Calculated Parameters for Plate
 W/O Orifice Area per Row = ft²
 Elliptical Half-Width = feet
 Elliptical Slot Centroid = feet
 Elliptical Slot Area = ft²

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (required)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	0.00	1.25	2.50					
Orifice Area (sq. inches)	4.69	4.69	4.69					

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)								
Orifice Area (sq. inches)								

User Input: Vertical Orifice (Circular or Rectangular)

	Not Selected	Not Selected	
Invert of Vertical Orifice =	<input type="text" value="N/A"/>	<input type="text" value="N/A"/>	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =	<input type="text" value="N/A"/>	<input type="text" value="N/A"/>	ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =	<input type="text" value="N/A"/>	<input type="text" value="N/A"/>	inches

Calculated Parameters for Vertical Orif
 Vertical Orifice Area =
 Vertical Orifice Centroid =

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir (and No Outlet Pipe))

	Zone 3 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	4.36	N/A	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	7.00	N/A	feet
Overflow Weir Gate Slope =	4.00	N/A	H:V
Horiz. Length of Weir Sides =	12.42	N/A	feet
Overflow Gate Type =	Close Mesh Gate	N/A	
Debris Clogging % =	75%	N/A	%

Calculated Parameters for Overflow W
 Height of Gate Upper Edge, H₁ =
 Overflow Weir Slope Length =
 Gate Open Area / 100-yr Orifice Area =
 Overflow Gate Open Area w/o Debris =
 Overflow Gate Open Area w/ Debris =

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

	Zone 3 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	6.29	0.00	ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	48.00		inches
Restrictor Plate Height Above Pipe Invert =	48.00		inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Pl
 Outlet Orifice Area =
 Outlet Orifice Centroid =
 Half-Central Angle of Restrictor Plate on Pipe =

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = ft (relative to basin bottom at Stage = 0 ft)
 Spillway Crest Length = feet
 Spillway End Slopes = H:V
 Freeboard above Max Water Surface = feet

Calculated Parameters for Spillway
 Spillway Design Flow Depth = feet
 Stage at Top of Freeboard = feet
 Basin Area at Top of Freeboard = acres
 Basin Volume at Top of Freeboard = acre-ft

Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AI)

	WOCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
Design Storm Return Period =	N/A	N/A						
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52
CUHP Runoff Volume (acre-ft) =	1.285	2.177	3.053	6.690	10.314	16.752	21.154	27.479
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	3.053	6.690	10.314	16.752	21.154	27.479
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	17.6	49.5	77.1	142.3	179.0	229.8
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A						
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.08	0.22	0.34	0.63	0.80	1.02
Peak Inflow Q (cfs) =	N/A	N/A	29.2	62.9	90.7	154.6	191.5	243.2
Peak Outflow Q (cfs) =	0.7	0.8	2.3	20.6	43.8	91.5	124.0	173.8
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	0.4	0.6	0.6	0.7	0.8
Structure Controlling Flow =	Plate	Plate	Overflow Weir 1					
Max Velocity through Gate 1 (fps) =	N/A	N/A	0.02	0.3	0.6	1.3	1.7	2.4
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	38	50	58	55	51	45	41	37
Time to Drain 99% of Inflow Volume (hours) =	40	54	62	62	60	57	55	53
Maximum Ponding Depth (ft) =	3.32	4.27	4.80	6.22	7.11	8.35	9.02	9.94
Area at Maximum Ponding Depth (acres) =	0.87	1.01	1.06	1.17	1.25	1.35	1.41	1.49
Maximum Volume Stored (acre-ft) =	1.288	2.178	2.724	4.310	5.376	7.001	7.928	9.263

HOMESTEAD AT STERLING RANCH FILING NO. 1

COUNTY OF EL PASO, STATE OF COLORADO

FINAL DRAINAGE MAP

APRIL 2018

LEGEND

- BASIN DESIGNATION: Z, 25, .25, .35, C5, C100
- PIPE RUN REFERENCE LABEL: 4
- SURFACE DESIGN POINT: 6
- BASIN BOUNDARY:
- EXISTING CONTOUR: (6920)
- PROP CONTOUR: 6920
- FILING NO. 4 BOUNDARY:
- EXISTING STORM SEWER PIPE:
- EXISTING STORM SEWER PIPE:
- CROSSSPAN:
- INLET:
- EXISTING FLOW DIRECTION ARROW:
- FLOW DIRECTION:
- FLARED END SECTION:
- HIGH POINT:
- LOW POINT:

BASIN SUMMARY

BASIN	AREA (ACRES)	Q ₅	Q ₁₀₀
OS2	2.10	8.9	15.9
OS3	0.43	0.4	1.3
OS4	0.61	0.5	1.9
OS5	1.54	5.6	10.0
OS6	9.73	12.5	30.4
OS7	1.97	0.7	5.3
A	2.79	3.6	8.7
B	2.70	3.6	8.6
C	2.92	4.2	10.1
D	2.90	4.3	10.4
E	5.34	8.2	19.9
F	1.12	4.3	7.7
G	0.61	0.5	1.9
EX-H	0.19	0.9	1.6
M	1.15	1.0	3.6
M2	1.60	0.4	3.2
N	2.08	1.6	5.7
O	0.57	0.5	1.8
W-2	10.00	2.7	19.7
OS1 HISTORIC	111.70	18.9	136.8
SUB-BASIN OS1A	2.70	0.7	5.3
SUB-BASIN OS1B	9.09	2.4	17.8
SUB-BASIN OS1C	5.64	1.5	11.1
SUB-BASIN OS1D	94.3	16.3	119.5
V1A	0.31	1.4	2.6
V1B	0.26	1.2	2.2
V1C	0.21	1.0	1.7
V1D	0.13	0.6	1.1
V2	0.32	1.5	2.7
RP-2B	2.04	4.9	9.9
RP-2C	1.28	4.3	8.2

DESIGN POINT SUMMARY

DESIGN POINT	Q ₅	Q ₁₀₀	BASIN	STRUCTURE
1	3.6	8.7	A	15' AT-GRADE INLET
2	3.6	8.6	B	15' AT-GRADE INLET
3	4.2	10.1	C	8' SUMP INLET
4	16.1	36.7	D, E, F	15' AT-GRADE INLET
5	4.2	19.7	G, EX-H, FLOWBY DP4	EX 15' AT-GRADE INLET
6	14.1	28.7	OS2, OS3, OS4, OS5	EX 15' AT-GRADE INLET
7	12.6	30.5	OS6	EX 18" RCP
8	49.2	105.3	OS7, PR4, PR6, PR7	EX FDS POND 4
9	1.6	7.0	OS1A, V1A	EX 12" CMP CULVERT
10	4.8	26.3	OS1B, V1B, DP6	EX 2.9'x5.7' CDOT TYPE D INLET
11	2.2	12.3	OS1C, V1C	EX 2.9'x2.9' CDOT TYPE C INLET
12	18.9	133.7	OS1D, V1D, W-2, V2	EX 4'x14' MOD CDOT TYPE D INLET
13	2.8	5.6	RP-2B	EX CDOT EMBANKMENT PROTECTOR TYPE 5
14	8.9	21.2	M, M2, RP2C, DP13	EX FDS POND W-9

STORM SEWER SUMMARY

PIPE RUN	Q ₅	Q ₁₀₀	PIPE SIZE	CONTRIBUTING PIPES/DP'S
1	3.6	8.7	30" RCP	DP1
2	7.1	17.2	36" RCP	DP2, PR1
3	4.2	10.1	18" RCP	DP3
4	16.8	29.4	30" RCP	DP4, PR3
5	10.8	30.0	36" RCP	DP5, PR2
6	21.0	44.6	36" RCP	DP6, PR5
7	12.6	30.5	24" RCP	DP7
8	1.6	7.0	12" CMP	DP9
9	4.8	26.3	24" RCP	DP10
10	2.2	12.3	18" RCP	DP11
11	7.0	38.6	30" RCP	PR5, PR6
12	18.9	133.7	54" RCP	DP12
13	0.6	8.7	18" RCP	OUTFLOW EDB POND W-9
14	7.6	47.2	30" RCP	PR7, PR9
15	23.8	164.1	54" RCP	PR8, PR10
16	2.7	36.2	30" RCP	OUTFLOW EDB POND 4
17	26.5	200.3	60" RCP	PR11, PR12

REVISED POND 4 FSD BASIN DATA




WQ WATER SURFACE EL = 7056.39
 WQ VOLUME=0.046 AC-FT
 EURV WATER SURFACE EL = 7058.46
 EURV VOLUME=1.510 AC-FT
 100-YR WATER SURFACE EL=7059.98
 SPILLWAY CREST EL=7060.0
 TOP OF EMBANKMENT EL=7063.0
 100-YR VOLUME=2.915 AC-FT
 100-YR INFLOW = 105.3 CFS
 100-YR RELEASE = 36.8 CFS

REVISED POND W-9 FSD BASIN DATA

WQ WATER SURFACE EL = 7086.59
 WQ VOLUME=0.092 AC-FT
 EURV WATER SURFACE EL = 7087.99
 EURV VOLUME=0.390 AC-FT
 100-YR WATER SURFACE EL=7088.84
 SPILLWAY CREST EL=7088.84
 TOP OF EMBANKMENT EL=7090.5
 100-YR VOLUME=0.638 AC-FT
 100-YR INFLOW = 21.2 CFS
 100-YR RELEASE = 8.7 CFS

OFF-SITE DRAINAGE MAP

FOR LOCATING & MARKING GAS, ELECTRIC, WATER & TELEPHONE LINES
 FOR BURIED UTILITY INFORMATION 48 HRS BEFORE YOU DIG CALL 1-800-922-1987




HOMESTEAD AT STERLING RANCH FIL NO. 1

FINAL DRAINAGE MAP

PROJECT NO. 09-005	SCALE: HORIZONTAL: 1"=80' VERTICAL: N/A	DATE: 4/12/2018
DESIGNED BY: CMN	CHECKED BY: VAS	SHEET 1 OF 1
		FDM01


File: C:\Users\jandrew\MyDocuments\Temp\Proposed Drainage Map_1_1_53096.dwg Plotstamp: 4/24/2018 10:06 AM

DRAINAGE MAPS



LEGEND

- BASIN ID - SC3-77
- DESIGN POINT - 87
- REACH IDENTIFIER - RT-17A
- BASIN BOUNDARY - - - - -
- EAST FORK SAND CREEK - - - - -
- BASIN BOUNDARY - - - - -
- FLOW DIRECTION - >>>



BASIN SUMMARY									
BASIN	CN	AREA (ACRES)	AREA (SQ MI)	Q ₂ (CFS)	Q ₅ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₅₀ (CFS)	Q ₁₀₀ (CFS)
EX-0	62	23.8	0.037	5.0	8.2	13.0	19.6	25.7	32.2
EX-1	62	25.7	0.040	4.8	7.9	12.4	18.7	24.5	30.9
EX-2	62	5.5	0.009	1.1	1.8	2.8	4.3	5.6	7.1
EX-3	62	136.8	0.214	22.0	36.4	57.6	86.9	114.0	143.1
EX-3A	61	188.1	0.294	28.3	47.4	75.7	115.1	152.2	192.6
EX-4	62	192.0	0.300	30.1	49.9	79.1	119.5	157.0	197.3
EX-4A	62	151.5	0.237	24.7	40.8	64.4	97.0	127.2	160.1
EX-5	62	153.9	0.240	24.2	40.0	63.4	95.9	125.9	158.2
EX-6	62	90.2	0.141	15.3	25.5	40.1	60.7	79.9	100.5
EX-7	56	165.0	0.258	11.6	21.5	37.5	60.9	83.1	107.4
EX-8	45	42.0	0.066	0.5	1.7	4.5	9.4	14.5	20.5
EX-9	54	131.9	0.206	12.2	23.9	43.1	70.9	97.0	125.2
EX-10	60	270.7	0.423	32.7	56.0	91.1	140.1	185.9	236.1
EX-10A	41	179.3	0.280	0.6	2.2	7.3	17.4	29.1	43.1
EX-11	43	209.3	0.327	18.0	29.8	47.7	73.4	98.3	126.1
EX-12	51	39.5	0.062	2.2	5.1	10.1	17.7	25.1	33.3
EX-13	55	89.3	0.139	7.7	15.2	27.1	44.2	60.5	78.4
EX-20	62	143.4	0.224	25.4	42.1	66.7	100.7	132.3	166.2
EX-20A	64	179.7	0.281	32.2	51.9	80.5	119.8	155.9	194.6
EX-21	65	33.3	0.052	8.6	13.5	20.7	30.5	39.4	49.0
EX-24	59	63.1	0.099	9.5	16.6	27.5	42.9	57.4	73.0
EX-25	43	54.4	0.085	0.3	1.5	4.8	10.7	17.2	25.1
EX-73	63	90.0	0.141	16.4	26.4	41.3	62.1	81.3	102.0
EX-74	63	119.7	0.187	22.3	36.5	57.3	85.9	112.3	140.7
EX-75	63	79.3	0.124	13.1	21.5	33.7	50.5	66.1	82.8
EX-76	63	86.4	0.135	14.2	23.1	36.4	54.6	71.4	89.6
EX-77	62	230.6	0.360	34.7	56.9	90.6	137.5	180.9	227.7
EX-78	63	155.6	0.243	28.1	45.3	70.6	106.2	139.1	174.5
EX-79	63	189.0	0.295	34.9	57.0	89.5	134.3	175.6	220.1
EX-80	63	147.7	0.231	27.3	44.3	69.6	104.5	136.8	171.4
EX-81	62	262.9	0.411	42.6	70.2	111.0	167.4	219.6	275.7
EX-82	62	117.8	0.184	20.0	33.2	52.8	80.0	105.1	132.3
EX-88	62	139.2	0.217	22.2	36.7	58.0	87.6	115.0	144.4

DESIGN POINT SUMMARY (PEAK FLOW)							
DESIGN POINT	AREA (SQ MI)	Q ₂ (CFS)	Q ₅ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₅₀ (CFS)	Q ₁₀₀ (CFS)
DP-74	0.371	39.3	65.3	104.8	158.9	209.1	262.8
DP-75	1.413	141.2	235.1	376.6	566.6	750.9	950.5
DP-78	0.538	59.7	98.4	154.0	232.6	306.2	385.3
DP-73	2.528	225.9	380.7	618.0	957.0	1260.4	1582.3
DP-71	2.669	229.3	388.9	629.7	978.8	1277.3	1637.9
DP-69	3.209	253.0	434.8	707.7	1100.0	1453.3	1870.4
DP-63	3.446	251.4	430.7	713.1	1113.2	1496.2	1911.5
DP-10	0.508	36.5	56.0	106.4	162.9	220.6	287.2
DP-9A	0.557	55.3	94.3	150.3	227.7	299.5	380.5
DP-9	0.505	52.8	88.8	142.1	214.2	281.0	351.4
DP-8A	0.139	7.7	15.2	27.1	44.2	60.5	78.4
DP-8	0.528	24.2	45.1	77.8	124.4	169.5	220.9
DP-7	0.703	32.4	57.1	97.3	156.1	213.8	277.9
DP-6	0.206	12.2	23.9	43.1	70.9	97.0	125.2
DP-5	0.066	0.5	1.7	4.5	9.4	14.5	20.5
DP-4	0.258	11.6	21.5	37.5	60.9	83.1	107.4
DP-3	0.009	1.1	1.8	2.8	4.3	5.6	7.1
DP-2	0.040	4.8	7.9	12.4	18.7	24.5	30.9
DP-1	0.037	5.0	8.2	13.0	19.6	25.7	32.2
DP-60A	3.545	247.7	430.2	707.1	1113.0	1496.6	1913.5
DP-56	0.466	23.2	42.5	71.9	115.6	157.4	202.9
DP-53A	4.138	262.1	454.0	763.2	1196.5	1609.8	2061.5

DESIGN POINT SUMMARY (VOLUME)							
DESIGN POINT	AREA (SQ MI)	V ₂ (AC-FT)	V ₅ (AC-FT)	V ₁₀ (AC-FT)	V ₂₅ (AC-FT)	V ₅₀ (AC-FT)	V ₁₀₀ (AC-FT)
DP-74	0.371	5.9	9.0	13.6	19.8	25.5	31.6
DP-75	1.413	22.7	34.5	51.7	75.4	97.1	120.5
DP-78	0.538	8.9	13.5	20.1	29.3	37.7	46.7
DP-73	2.528	40.4	61.5	92.1	134.3	173.1	214.9
DP-71	2.669	42.5	64.9	97.1	141.6	182.5	226.6
DP-69	3.209	50.7	77.4	116.1	169.4	216.6	271.4
DP-63	3.446	54.1	82.5	123.8	180.8	233.3	289.9
DP-10	0.508	7.6	11.7	17.6	25.8	33.4	41.6
DP-9A	0.557	9.3	14.1	21.1	30.7	39.4	48.8
DP-9	0.505	8.4	12.7	19.0	27.6	35.5	44.0
DP-8A	0.139	1.3	2.1	3.4	5.2	7.0	8.9
DP-8	0.528	4.4	7.0	11.1	16.8	22.3	28.4
DP-7	0.703	6.1	10.0	15.9	24.3	32.4	41.3
DP-6	0.206	2.4	4.0	6.3	9.6	12.7	16.0
DP-5	0.066	0.2	0.4	0.8	1.4	1.9	2.6
DP-4	0.258	2.6	4.2	6.7	10.2	13.5	17.2
DP-3	0.009	0.1	0.2	0.3	0.5	0.6	0.8
DP-2	0.040	0.6	0.9	1.4	2.1	2.7	3.4
DP-1	0.037	0.6	0.9	1.3	1.9	2.5	3.1
DP-60A	3.545	55.3	84.4	126.4	184.8	238.5	296.6
DP-56	0.466	4.0	6.3	9.9	14.9	19.8	25.1
DP-53A	4.138	63.0	96.4	144.7	211.8	273.9	340.9

OFF-SITE DRAINAGE MAP

File: C:\09002A\Sterling Ranch - District\Eng - Exhibits\2018-MDDP-2018-MDDP-ExistCondWSWMap.dwg Plotstamp: 11/13/2018 1:52 PM

FOR LOCATING & MARKING GAS, ELECTRIC, WATER & TELEPHONE LINES
FOR BURIED UTILITY INFORMATION 48 HRS BEFORE YOU DIG CALL 1-800-922-1987

EFSC DBPS DESIGN POINT SUMMARY (PEAK FLOW)			
DBPS DESIGN POINT	AREA (SQ MI)	Q ₂ (CFS)	Q ₁₀₀ (CFS)
DP-50	0.32	47.0	195.7
DP-51 (BASIN 86)	0.33	17.7	74.1
DP-52	1.67	80.5	456.5
DP-56	0.79	63.6	265.0

Values reported from SCDBPS
(DP 50, 51, 52 Not analyzed as a part of this study)
DBPS Reach 85(Basin#1)=Q10=28.8cfs Q100=115.2cfs

M&S CIVIL CONSULTANTS, INC.
20 BOULDER CRESCENT, SUITE 110
COLORADO SPRINGS, CO 80903
PHONE: 719.955.5485

2018 STERLING RANCH MDDP
EXISTING HYDROLOGIC CONDITIONS MAP

PROJECT NO. 09-002 FILE: \\dwg\Eng - Exhibits\2018-MDDP-ExistCondWSWMap.dwg

DESIGNED BY: DLM SCALE: DATE: 08-22-18
DRAWN BY: DLM HORIZ: NTS
CHECKED BY: VAS VERT: NTS

DM1

FINAL DRAINAGE REPORT - BASIN RUNOFF COEFFICIENT SUMMARY


BASIN	TOTAL AREA (AC)	DEVELOPED AREA IMPERVIOUS AREA				LANDSCAPE/UNDEVELOPED AREAS				WEIGHTED			WEIGHTED CA			IMPERVIOUSNESS %
		AREA (AC)	C(2)	C(5)	C(100)	AREA (AC)	C(2)	C(5)	C(100)	C(2)	C(5)	C(100)	CA(2)	CA(5)	CA(100)	
EX-A	0.78	0.00	0.03	0.09	0.36	0.78	0.03	0.09	0.36	0.03	0.09	0.36	0.02	0.07	0.28	2%
EX-B	2.80	0.00	0.03	0.09	0.36	2.80	0.03	0.09	0.36	0.03	0.09	0.36	0.08	0.25	1.01	2%
EX-C	41.40	0.00	0.03	0.09	0.36	41.40	0.03	0.09	0.36	0.03	0.09	0.36	1.24	3.73	14.90	2%
EX-D	1.30	0.00	0.03	0.09	0.36	1.30	0.03	0.09	0.36	0.03	0.09	0.36	0.04	0.12	0.47	2%
EX-E	72.40	0.00	0.03	0.09	0.36	72.40	0.03	0.09	0.36	0.03	0.09	0.36	2.17	6.52	26.06	2%
EX-F	8.70	0.00	0.03	0.09	0.36	8.70	0.03	0.09	0.36	0.03	0.09	0.36	0.26	0.78	3.13	2%
EX-G	8.30	0.00	0.03	0.09	0.36	8.30	0.03	0.09	0.36	0.03	0.09	0.36	0.25	0.75	2.99	2%
EX-H	6.50	0.00	0.03	0.09	0.36	6.50	0.03	0.09	0.36	0.03	0.09	0.36	0.20	0.59	2.34	2%
OS-1	2.00	2.00	0.06	0.13	0.40	0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.12	0.26	0.80	10%
OS-2	5.30	5.30	0.06	0.13	0.40	0.00	0.02	0.08	0.35	0.06	0.13	0.40	0.32	0.69	2.12	10%
EX-3	44.30	44.30	0.04	0.11	0.38	0.00	0.02	0.08	0.35	0.04	0.11	0.38	1.77	4.65	16.61	5%
EX-4A	77.00	77.00	0.04	0.11	0.38	0.00	0.02	0.08	0.35	0.04	0.11	0.38	3.08	8.09	28.88	5%
EX-4B	70.00	70.00	0.04	0.11	0.38	0.00	0.02	0.08	0.35	0.04	0.11	0.38	2.80	7.35	26.25	5%

FINAL DRAINAGE REPORT - BASIN RUNOFF SUMMARY

BASIN	CA(2)	CA(5)	CA(100)	OVERLAND			STREET / CHANNEL FLOW			Tc (min)	INTENSITY I(2) (in/hr)	I(5) (in/hr)	I(100) (in/hr)	TOTAL FLOWS					
				Length (ft)	Height (ft)	Tc (min)	Length (ft)	Slope (%)	Velocity (ft/s)					TOTAL (cfs)	Q(2) (cfs)	Q(5) (cfs)	Q(100) (cfs)		
EX-A	0.02	0.07	0.28	0.09	340	9	18.3	2.98	3.23	5.41	0.1	0.2	7						
EX-B	0.08	0.25	1.01	0.09	300	24	17.9	2.60	3.25	5.46	0.2	0.8	6						
EX-C	1.24	3.73	14.90	0.09	300	18	17.5	1300	2.9%	1.7	12.7	30.2	1.98	2.47	4.15	2	9	62	
EX-D	0.04	0.12	0.47	0.09	225	10	16.7	16.7	2.88	3.36	5.54	0.1	0.4	3					
EX-E	2.17	6.52	26.06	0.09	300	20	15.9	3400	2.5%	1.6	36.8	51.8	1.34	1.96	2.79	3	11	73	
EX-F	0.26	0.78	3.13	0.09	300	12	20.0	560	2.0%	1.4	6.6	26.6	2.13	2.96	4.47	1	2	14	
EX-G	0.25	0.75	2.99	0.09	300	10	21.2	420	2.0%	1.4	4.9	26.2	2.15	2.89	4.91	1	2	13	
EX-H	0.20	0.59	2.34	0.09	300	10	21.2	800	2.0%	1.4	9.4	30.7	1.96	2.45	4.11	0.4	1.4	10	
OS-1	0.12	0.26	0.80	0.08	300	10	21.4						21.4	2.39	2.99	5.01	0.3	0.8	4
OS-2	0.32	0.69	2.12	0.08	300	12	20.2						20.2	2.48	3.08	5.16	1	2	11
EX-3	1.77	4.65	16.61	0.08	300	10	21.4	650	2.0%	1.4	7.7	29.1	2.02	2.53	4.24	4	12	76	
EX-4A	3.08	8.09	28.88	0.08	300	9	22.2	2400	2.0%	1.4	28.3	50.5	1.37	1.70	2.85	4	14	62	
EX-4B	2.80	7.35	26.25	0.08	300	10	21.4	3500	1.8%	1.3	43.5	64.9	1.07	1.32	2.22	3	10	58	

FINAL DRAINAGE REPORT - SURFACE ROUTING SUMMARY

Design Point(s)	Contributing Basins	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity				Inlet Size
					I(5)	I(100)	Q(5)	Q(100)	
E1	EX-4A	8.09	28.88	50.5	1.70	2.85	14	82	EX 24" CMP CULVERT
E2	EX-4B	7.35	26.25	64.9	1.32	2.22	10	58	EX STOCK OFF-SITE POND
E3	EX-A, EX-B	0.32	1.29	18.3	3.23	5.41	1	7	TYPE D CDOT INLET W/ 24" RCP
E4	EX-4A, EX-4B, EX-C	19.16	70.03	64.9	1.32	2.22	25	155	PLANNED 48" RCP W/ MH AND GRATE
E5	EX-3	4.65	16.61	29.1	2.53	4.24	12	70	EX 24" CMP CULVERT
E6	EX-G	0.75	2.99	26.2	2.69	4.51	2	13	TYPE D CDOT INLET W/ 24" RCP
E7	EX-H	0.59	2.34	30.7	2.45	4.11	1	10	TYPE C CDOT INLET W/ 18" RCP
E8	EX-3, EX-E, OS-2	11.86	44.80	51.8	1.66	2.79	20	125	EX 24" CMP CULVERT
E9	DP-E8, EX-F, OS-1	12.90	48.73	55.8	1.55	2.60	20	127	MODIFIED 4'x14" TYPE D CDOT INLET W/ 54" RCP
E10	EX-D	0.12	0.47	16.7	3.36	5.64	0.4	3	SHEET FLOW TO NATURAL RAVINE



LEGEND

DESCRIPTION	SYMBOL
EXISTING GROUND CONTOUR	(6910)
PROPOSED FINISHED CONTOUR	6910
BASIN BOUNDARY	---
DESIGN POINT	E1
BASIN IDENTIFIER	BB 100
AREA IN ACRES	
EXISTING DIRECTION OF FLOW	→
EXISTING STORM SEWER	---
WETLAND DELINEATION	---

SCALE: 1" = 200'

CLASSIC CONSULTING


RETREAT AT PRAIRIERIDGE FILINGS 1-3
PRELIMINARY PLAN
PRELIMINARY DRAINAGE REPORT
PRE-DEVELOPMENT CONDITIONS

DESIGNED BY	MAW	SCALE	DATE	12-8-23
DRAWN BY	MAW	(H) 1" = 200'	SHEET	1 OF 3
CHECKED BY	(V) 1" = N/A	JOB NO.	1305.10	

619 N. Cascade Avenue, Suite 200 (719) 785-0790
Colorado Springs, Colorado 80903 (719) 785-0799 (Fax)

N:\1305\1305\PRELIMINARY DRAINAGE REPORT\1305.DWG 4/4/2024 9:50:21 AM 1:1

NOTE:
EXISTING PUBLIC CULVERTS CROSSING POCO ROAD ADJACENT TO THE PRAIRIERIDGE PROPERTY APPEAR TO BE SILTED IN AND UNDERSIZED FOR THE 100-YR EVENT.
IT IS RECOMMENDED THAT EL PASO COUNTY VISUALLY INSPECT THESE FACILITIES AND CONSIDER UP-SIZING FOR LARGER STORM EVENTS BASED ON THE CURRENT BASIN HYDROLOGY OR AT MINIMUM CLEAN OUT THE CURRENT FACILITIES TO ALLOW FOR BETTER CONVEYANCE.



PIPE ROUTING SUMMARY									
Pipe Run	Contributing Basin / Design Point / Pipe Run	Equivalent CA(5)	Equivalent CA(100)	Maximum Tc	Intensity			Flow	Pipe Size*
					I(5)	I(100)	Q(5)		
1	DP-1	8.22	29.05	53.48	1.61	2.71	13	79	PROP. 36" RCP
2	DP-2	7.67	26.57	65.92	1.30	2.18	10	58	PROP. 36" RCP
3	DP-4	0.64	2.65	23.38	2.86	4.79	2	13	PROP. 24" RCP
4	DP-5	0.41	0.60	15.3	3.49	5.86	1.4	4	PROP. 18" RCP
5	PR-2, PR-3, PR-4	8.73	29.02	65.9	1.30	2.18	11	65	PROP. 42" RCP
6	PR-1, PR-5	16.95	58.87	65.9	1.30	2.18	22	128	PROP. 48" RCP
7	DP-3 Collected	1.45	1.88	22.9	2.89	4.85	4	9	PROP. 18" RCP
8	PR-6, PR-7	18.40	60.75	66.4	1.29	2.16	24	131	PROP. 48" RCP
9	DP-6	1.44	2.14	18.2	3.23	5.43	5	12	PROP. 24" RCP
10	DP-7	0.64	0.93	15.3	3.49	5.86	2.2	5	PROP. 18" RCP
11	PR-8, PR-9, PR-10	20.48	63.81	66.9	1.28	2.14	26	137	PROP. 48" RCP
12	DP-9	1.44	1.89	18.1	3.24	5.44	5	10	PROP. 24" RCP
13	DP-10	0.50	0.65	13.8	3.65	6.13	1.8	4	PROP. 18" RCP
14	PR-12, PR-13	1.94	2.54	18.6	3.20	5.38	6	14	PROP. 24" RCP
15	PR-11, PR-14	22.41	66.35	67.2	1.27	2.13	28	141	PROP. 48" RCP
16	DP-8	0.77	1.00	12.3	3.81	6.40	3	6	PROP. 18" RCP
17	DP-11	2.11	3.75	19.7	3.11	5.23	7	20	PROP. 30" RCP
18	DP-12	0.72	0.77	10.1	4.11	6.91	3	5	PROP. 18" RCP
19	PR-17, PR-18	2.83	4.52	19.9	3.10	5.20	9	23	PROP. 30" RCP
20	PR-15, PR-16, PR-19	26.01	71.87	67.7	1.26	2.11	33	152	PROP. 48" RCP
21	DP-13	0.83	1.09	17.6	3.28	5.51	3	6	PROP. 18" RCP
22	PR-20, PR-21	26.84	72.96	68.2	1.25	2.09	34	153	PROP. 48" RCP
23	DP-14	0.83	1.09	17.6	3.28	5.51	3	6	PROP. 24" RCP
24	PR-22, PR-23	27.87	74.05	68.2	1.25	2.09	35	155	PROP. 48" RCP
25	DP-17	5.71	19.79	29.1	2.53	4.24	14	84	PROP. 42" RCP
26	DP-19	0.41	0.53	11.5	3.92	6.58	1.6	3	PROP. 18" RCP
27	DP-18, PR-26	1.53	2.88	19.4	3.14	5.27	5	15	PROP. 24" RCP
28	PR-25, PR-27	7.24	22.67	30.3	2.47	4.14	18	94	PROP. 42" RCP
29	DP-20	2.03	2.94	15.1	3.51	5.89	7	17	PROP. 24" RCP
30	DP-21	0.14	0.18	11.0	3.98	6.68	0.5	1.2	PROP. 18" RCP
31	PR-29, PR-30	2.16	3.12	15.9	3.43	5.76	7	18	PROP. 30" RCP
32	DP-22	1.42	2.19	19.1	3.16	5.31	4	12	PROP. 24" RCP
33	DP-23	0.48	1.01	14.8	3.34	5.95	2	6	PROP. 18" RCP
34	PR-31, PR-32, PR-33	4.06	6.33	19.1	3.16	5.31	13	34	PROP. 30" RCP
35	PR-32, PR-34	11.30	29.00	30.5	2.46	4.12	28	120	PROP. 48" RCP
36	DP-24	0.56	1.36	16.2	3.41	5.72	2	8	PROP. 18" RCP
37	DP-25, PR-36	0.98	2.36	16.7	3.36	5.64	3	13	PROP. 24" RCP
38	PR-35, PR-37	12.29	31.36	30.6	2.45	4.11	30	129	PROP. 48" RCP
39	DP-26	0.77	0.87	5.2	5.10	8.56	4	7	PROP. 18" RCP
40	DP-27	1.20	1.74	14.2	3.60	6.05	4	11	PROP. 24" RCP
41	PR-38, PR-40	1.97	2.82	14.2	3.80	6.05	7	16	PROP. 24" RCP
42	PR-38, PR-41	14.25	33.97	30.7	2.45	4.11	35	139	PROP. 48" RCP
43	DP-28	0.63	0.89	11.2	3.96	6.64	2	6	PROP. 18" RCP
44	DP-29, PR-43	1.05	1.38	11.3	3.94	6.62	4	9	PROP. 24" RCP
45	PR-42, PR-44	15.30	35.35	30.9	2.44	4.09	37	145	PROP. 48" RCP
46	DP-30	0.66	0.82	15.9	3.44	5.77	2	5	PROP. 18" RCP
47	PR-45, PR-46	15.96	36.17	31.2	2.42	4.07	39	147	PROP. 48" RCP
48	DP-31 Collected	1.16	1.15	15.9	3.43	5.76	4	7	PROP. 18" RCP
49	PR-47, PR-48	17.12	37.32	31.4	2.41	4.05	41	151	PROP. 48" RCP
50	DP-32 Collected	1.08	1.30	17.2	3.32	5.57	4	7	PROP. 18" RCP
51	PR-49, PR-50	18.20	38.62	31.6	2.40	4.03	44	156	PROP. 48" RCP
52	DP-35	2.45	3.39	19.5	3.13	5.25	8	18	PROP. 30" RCP
53	DP-51, PR-52	20.66	42.01	31.8	2.39	4.02	49	169	PROP. 54" RCP
54	DP-33	1.44	1.71	11.5	3.92	6.59	6	11	PROP. 24" RCP
55	DP-34, PR-54	2.94	4.16	19.0	3.17	5.31	9	22	PROP. 30" RCP
56	PR-53, PR-55	23.59	46.17	31.8	2.39	4.02	56	185	PROP. 54" RCP
57	DP-37	4.28	5.61	18.5	3.21	5.38	14	30	PROP. 30" RCP
58	DP-38	2.17	3.12	10.4	4.07	6.83	9	21	PROP. 30" RCP
59	DP-39 Collected, PR-58	3.51	4.64	12.2	3.83	6.43	13	30	PROP. 36" RCP
60	PR-57, PR-59	7.79	10.25	18.5	3.21	5.38	25	55	PROP. 36" RCP
61	DP-40 Collected	1.23	1.29	11.2	3.96	6.66	5	9	PROP. 18" RCP
62	PR-60, PR-61	9.02	11.53	19.2	3.15	5.29	28	61	PROP. 36" RCP
63	DP-36	2.45	3.39	19.5	3.13	5.25	8	18	PROP. 30" RCP
64	PR-62, PR-63	11.47	14.92	20.1	3.08	5.17	35	77	PROP. 42" RCP
65	PR-56, PR-64	35.06	61.09	32.0	2.38	4.00	84	244	PROP. 60" RCP
66	DP-42	1.30	2.91	21.2	3.00	5.04	4	15	PROP. 24" RCP
67	DP-43, PR-66	1.64	3.69	21.3	3.00	5.03	5	19	PROP. 24" RCP
68	DP-41	1.04	1.47	15.9	3.43	5.76	4	8	PROP. 18" RCP
69	PR-67, PR-68	2.88	5.16	21.5	2.98	5.00	8	26	PROP. 30" RCP

LEGEND

EXISTING GROUND CONTOUR	(6910)
PROPOSED FINISHED CONTOUR	6910
BASIN BOUNDARY	---
DESIGN POINT	①
PIPE ROUTING	②
BASIN IDENTIFIER	③
AREA IN ACRES	④
EXISTING DIRECTION OF FLOW	→
EXISTING STORM SEWER	---
PROPOSED STORM SEWER	---
WETLAND DELINEATION	---
DETENTION/STORMWATER QUALITY HANDLED IN FSD POND C WITHIN HOMESTEAD NORTH FILING NO. 1	■

TOTAL AREA TRIBUTARY TO OFF-SITE POND C: 193.40 (12.9%)
SEE APPENDIX FOR BASIN BREAKDOWN

SCALE: 1" = 100'


CLASSIC CONSULTING

RETREAT AT PRAIRIERIDGE FILINGS 1-3
PRELIMINARY PLAN
PRELIMINARY DRAINAGE REPORT
DEVELOPED CONDITIONS

DESIGNED BY	MAW	SCALE	DATE	10-5-23
DRAWN BY	MAW	(H) 1" = 100'	SHEET	2 OF 3
CHECKED BY	(V) 1" = N/A	JOB NO.	1305.10	

619 N. Cascade Avenue, Suite 200 (719) 785-0790
Colorado Springs, Colorado 80903 (719) 785-0799 (Fax)

N:\130510\REPORTS\PRELIMINARY DRAINAGE REPORT\130510.dwg, 7/15/2024, 10:25:32 AM, ET



SURFACE ROUTING SUMMARY

Design Point	Contributing Basins / Design Point	Equivalent CA			Intensity			Flow			Facility / Inlet Size
		CA(5)	CA(10)	CA(15)	(5)	(10)	(15)	Q(5)	Q(10)	Q(15)	
1	EX-4A	8.22	29.05	33.0	1.61	2.71	1.3	7.9	PROF. 36" RCP		
2	EX-4B	7.67	26.57	65.9	1.90	2.18	1.0	5.8	PROF. 36" RCP		
3	C1	1.47	3.35	22.9	2.90	4.66	4	16	10" TYPE R AT-GRADE INLET		
4	C2	0.64	2.65	23.4	2.96	4.79	2	13	10" TYPE R AT-GRADE INLET		
5	D	0.41	0.60	15.3	3.49	5.66	1.4	4	10" TYPE R AT-GRADE INLET		
6	E	1.44	2.14	18.2	3.23	5.43	5	12	10" TYPE R AT-GRADE INLET		
7	F	0.64	0.60	15.3	3.49	5.66	2.2	5	10" TYPE R AT-GRADE INLET		
8	G	0.77	1.00	12.3	3.81	6.40	3	6	8" TYPE R AT-GRADE INLET		
9	H	1.44	1.89	18.1	3.24	5.44	5	10	10" TYPE R AT-GRADE INLET		
10	I	0.50	0.65	19.8	3.05	6.13	1.8	4	10" TYPE R AT-GRADE INLET		
11	J	1.10	3.75	19.7	3.11	5.23	7	20	10" TYPE R AT-GRADE INLET		
12	K	0.72	0.77	10.1	4.11	6.91	3	5	8" TYPE R AT-GRADE INLET		
13	L	0.83	1.09	17.6	3.28	5.51	3	6	PROF. 18" RCP		
14	M	0.83	1.09	17.6	3.28	5.51	3	6	PROF. 24" RCP		
15	N	0.71	2.30	17.1	3.33	5.59	2	13	EXIST. 18" WITH GRATE		
16	EX-3A	0.70	2.30	17.1	3.19	5.36	2	12	PROF. 42" RCP		
17	EX-3, S, DP-16	5.71	19.79	28.1	2.53	4.24	14	84	PROF. 42" RCP		
18	O	1.12	2.36	19.4	3.14	5.27	4	12	10" TYPE R AT-GRADE INLET		
19	P	0.41	0.53	11.5	3.92	6.56	1.4	3	8" TYPE R AT-GRADE INLET		
20	Q	2.03	2.94	15.1	3.51	5.89	7	17	10" TYPE R AT-GRADE INLET		
21	R	1.14	0.18	11.0	3.68	6.08	0.5	1.2	10" TYPE R AT-GRADE INLET		
22	Y	1.42	2.19	19.1	3.16	5.31	4	12	10" TYPE R AT-GRADE INLET		
23	Z	0.48	1.01	14.8	3.54	5.95	2	6	8" TYPE R AT-GRADE INLET		
24	AA, OS-2A	0.56	1.36	16.2	3.41	5.72	2	8	EXIST. 18" WITH GRATE		
25	BB, OS-2B	0.43	1.00	16.5	3.30	5.61	1	6	EXIST. 18" WITH GRATE		
26	EE	0.77	0.67	5.2	5.10	8.56	4	7	10" TYPE R AT-GRADE INLET		
27	FF	1.20	1.74	14.2	3.00	5.05	4	11	10" TYPE R AT-GRADE INLET		
28	CC	0.63	0.89	11.2	3.96	6.64	2	6	10" TYPE R AT-GRADE INLET		
29	DD	0.42	0.49	7.2	4.62	7.75	2	4	8" TYPE R AT-GRADE INLET		
30	JJ	0.68	0.82	15.9	3.44	5.77	2	5	10" TYPE R AT-GRADE INLET		
31	KK	1.17	1.53	15.9	3.43	5.76	4	9	10" TYPE R AT-GRADE INLET		
32	LL	1.69	1.80	17.2	3.32	5.57	4	10	10" TYPE R AT-GRADE INLET		
33	MM	1.44	1.71	11.5	3.92	6.58	6	11	10" TYPE R AT-GRADE INLET		
34	NN	1.50	2.45	19.0	3.17	5.31	5	13	10" TYPE R AT-GRADE INLET		
35	OO	2.45	3.39	19.5	3.13	5.26	8	18	PROF. 36" RCP		
36	PP	2.45	3.39	19.5	3.13	5.26	8	18	PROF. 36" RCP		
37	QO	4.26	5.61	18.5	3.21	5.38	14	30	PROF. 36" RCP		
38	R	2.17	3.12	10.4	4.07	6.83	9	20	PROF. 36" RCP		
39	SS	1.34	1.71	11.2	3.83	6.43	5	11	10" TYPE R AT-GRADE INLET		
40	HH	1.23	1.36	11.2	3.96	6.66	5	9	10" TYPE R AT-GRADE INLET		
41	DD	1.04	1.47	15.9	3.43	5.76	4	8	10" TYPE R AT-GRADE INLET		
42	OS-2C, PP, TT, UU	1.30	2.91	20.2	3.08	5.16	4	15	10" TYPE R AT-GRADE INLET		
43	OS-1A, QQ	0.34	0.78	14.3	3.59	6.03	1	5	EXIST. 18" WITH GRATE		
44	TOTAL TRIBUTARY AREA TO OFF-SITE POND	38.84	69.68	32.0	2.38	4.00	93	279	PROF. ON-SITE POND		

BASIN RUNOFF SUMMARY

BASIN	CA(5)	CA(10)	CA(15)	OVERLAND			STREET CHANNEL FLOW			TOTAL	INTENSITY	TOTAL FLOWS	
				Length (ft)	Height (ft)	Tc (min)	Length (ft)	Velocity (ft/s)	Tc (min)				Q(5) (cfs)
OS-1	4.50	15.48	3.00	10	2.14	68	2.96	2.4	7.7	26.1	2.68	1.4	1.4
EX-3A	5.30	18.24	3.60	10	1.63	58	2.96	2.4	7.7	18.3	2.68	1.4	1.4
EX-4A	2.87	7.79	2.80	300	9	222	280	2.6	114	263	1.07	1.0	1.0
EX-4B	2.80	7.35	2.625	300	10	214	280	1.9	113	243	1.07	1.0	1.0
EX-4C	0.11	0.29	1.05	300	10	214	280	1.9	113	243	1.07	1.0	1.0

BASIN RUNOFF COEFFICIENT SUMMARY

BASIN	TOTAL AREA (AC)	LAND USE	PERCENT IMP.	C VALUE					WEIGHTED C VALUE	WEIGHTED CA	WEIGHTED IMP.		
				CA(5)	CA(10)	CA(15)	CA(5)	CA(10)				CA(15)	
EX-3	41.50	RES. 2.5 AC	5.0%	0.04	0.11	0.30	0.04	0.11	0.30	1.87	4.39	15.80	5.0%
EX-3A	2.50	RES. 5 AC	5.0%	0.04	0.11	0.30	0.04	0.11	0.30	0.10	0.28	0.94	5.0%
EX-4A	74.20	RES. 3 AC	5.0%	0.04	0.11	0.30	0.04	0.11	0.30	2.97	7.79	27.53	5.0%
EX-4B	70.00	RES. 3 AC	5.0%	0.04	0.11	0.30	0.04	0.11	0.30	2.80	7.35	26.25	5.0%
EX-4C	2.80	RES. 5 AC	5.0%	0.04	0.11	0.30	0.04	0.11	0.30	0.11	0.29	1.05	5.0%

TOTAL AREA TRIBUTARY TO OFF-SITE POND C

Design Point	Contributing Basins / Design Point	Equivalent CA	Intensity	Flow	Facility / Inlet Size				
1	EX-4A	8.22	29.05	33.0	1.61	2.71	1.3	7.9	PROF. 36" RCP
2	EX-4B	7.67	26.57	65.9	1.90	2.18	1.0	5.8	PROF. 36" RCP
3	C1	1.47	3.35	22.9	2.90	4.66	4	16	10" TYPE R AT-GRADE INLET
4	C2	0.64	2.65	23.4	2.96	4.79	2	13	10" TYPE R AT-GRADE INLET
5	D	0.41	0.60	15.3	3.49	5.66	1.4	4	10" TYPE R AT-GRADE INLET
6	E	1.44	2.14	18.2	3.23	5.43	5	12	10" TYPE R AT-GRADE INLET
7	F	0.64	0.60	15.3	3.49	5.66	2.2	5	10" TYPE R AT-GRADE INLET
8	G	0.77	1.00	12.3	3.81	6.40	3	6	8" TYPE R AT-GRADE INLET
9	H	1.44	1.89	18.1	3.24	5.44	5	10	10" TYPE R AT-GRADE INLET
10	I	0.50	0.65	19.8	3.05	6.13	1.8	4	10" TYPE R AT-GRADE INLET
11	J	1.10	3.75	19.7	3.11	5.23	7	20	10" TYPE R AT-GRADE INLET
12	K	0.72	0.77	10.1	4.11	6.91	3	5	8" TYPE R AT-GRADE INLET
13	L	0.83	1.09	17.6	3.28	5.51	3	6	PROF. 18" RCP
14	M	0.83	1.09	17.6	3.28	5.51	3	6	PROF. 24" RCP
15	N	0.71	2.30	17.1	3.33	5.59	2	13	EXIST. 18" WITH GRATE
16	EX-3A	0.70	2.30	17.1	3.19	5.36	2	12	PROF. 42" RCP
17	EX-3, S, DP-16	5.71	19.79	28.1	2.53	4.24	14	84	PROF. 42" RCP
18	O	1.12	2.36	19.4	3.14	5.27	4	12	10" TYPE R AT-GRADE INLET
19	P	0.41	0.53	11.5	3.92	6.56	1.4	3	8" TYPE R AT-GRADE INLET
20	Q	2.03	2.94	15.1	3.51	5.89	7	17	10" TYPE R AT-GRADE INLET
21	R	1.14	0.18	11.0	3.68	6.08	0.5	1.2	10" TYPE R AT-GRADE INLET
22	Y	1.42	2.19	19.1	3.16	5.31	4	12	10" TYPE R AT-GRADE INLET
23	Z	0.48	1.01	14.8	3.54	5.95	2	6	8" TYPE R AT-GRADE INLET
24	AA, OS-2A	0.56	1.36	16.2	3.41	5.72	2	8	EXIST. 18" WITH GRATE
25	BB, OS-2B	0.43	1.00	16.5	3.30	5.61	1	6	EXIST. 18" WITH GRATE
26	EE	0.77	0.67	5.2	5.10	8.56	4	7	10" TYPE R AT-GRADE INLET
27	FF	1.20	1.74	14.2	3.00	5.05	4	11	10" TYPE R AT-GRADE INLET
28	CC	0.63	0.89	11.2	3.96	6.64	2	6	10" TYPE R AT-GRADE INLET
29	DD	0.42	0.49	7.2	4.62	7.75	2	4	8" TYPE R AT-GRADE INLET
30	JJ	0.68	0.82	15.9	3.44	5.77	2	5	10" TYPE R AT-GRADE INLET
31	KK	1.17	1.53	15.9	3.43	5.76	4	9	10" TYPE R AT-GRADE INLET
32	LL	1.69	1.80	17.2	3.32	5.57	4	10	10" TYPE R AT-GRADE INLET
33	MM	1.44	1.71	11.5	3.92	6.58	6	11	10" TYPE R AT-GRADE INLET
34	NN	1.50	2.45	19.0	3.17	5.31	5	13	10" TYPE R AT-GRADE INLET
35	OO	2.45	3.39	19.5	3.13	5.26	8	18	PROF. 36" RCP
36	PP	2.45	3.39	19.5	3.13	5.26	8	18	PROF. 36" RCP
37	QO	4.26	5.61	18.5	3.21	5.38	14	30	PROF. 36" RCP
38	R	2.17	3.12	10.4	4.07	6.83	9	20	PROF. 36" RCP
39	SS	1.34	1.71	11.2	3.83	6.43	5	11	10" TYPE R AT-GRADE INLET
40	HH	1.23	1.36	11.2	3.96	6.66	5	9	10" TYPE R AT-GRADE INLET
41	DD	1.04	1.47	15.9	3.43	5.76	4	8	10" TYPE R AT-GRADE INLET
42	OS-2C, PP, TT, UU	1.30	2.91	20.2	3.08	5.16	4	15	10" TYPE R AT-GRADE INLET
43	OS-1A, QQ	0.34	0.78	14.3	3.59	6.03	1	5	EXIST. 18" WITH GRATE
44	TOTAL TRIBUTARY AREA TO OFF-SITE POND	38.84	69.68	32.0	2.38	4.00	93	279	PROF. ON-SITE POND

TOTAL AREA TRIBUTARY TO OFF-SITE POND C

Design Point	Contributing Basins / Design Point	Equivalent CA	Intensity	Flow	Facility / Inlet Size				
1	EX-4A	8.22	29.05	33.0	1.61	2.71	1.3	7.9	PROF. 36" RCP
2	EX-4B	7.67	26.57	65.9	1.90	2.18	1.0	5.8	PROF. 36" RCP
3	C1	1.47	3.35	22.9	2.90	4.66	4	16	10" TYPE R AT-GRADE INLET
4	C2	0.64	2.65	23.4	2.96	4.79	2	13	10" TYPE R AT-GRADE INLET
5	D	0.41	0.60	15.3	3.49	5.66	1.4	4	10" TYPE R AT-GRADE INLET
6	E	1.44	2.14	18.2	3.23	5.43	5	12	10" TYPE R AT-GRADE INLET
7	F	0.64	0.60	15.3	3.49	5.66	2.2	5	10" TYPE R AT-GRADE INLET
8	G	0.77	1.00	12.3	3.81	6.40	3	6	8" TYPE R AT-GRADE INLET
9	H	1.44	1.89	18.1	3.24	5.44	5	10	10" TYPE R AT-GRADE INLET
10	I	0.50	0.65	19.8	3.05	6.13	1.8	4	10" TYPE R AT-GRADE INLET
11	J	1.10	3.75	19.7	3.11	5.23	7	20	10" TYPE R AT-GRADE INLET
12	K	0.72	0.77	10.1	4.11	6.91	3	5	8" TYPE R AT-GRADE INLET
13	L	0.83	1.09	17.6	3.28	5.51	3	6	PROF. 18" RCP
14	M	0.83	1.09	17.6	3.28	5.51	3	6	PROF. 24" RCP
15	N	0.71	2.30	17.1	3.33	5.59	2	13	EXIST. 18" WITH GRATE
16	EX-3A	0.70	2.30	17.1	3.19	5.36	2	12	PROF. 42" RCP
17	EX-3, S, DP-16	5.71	19.79	28.1	2.53	4.24	14	84	PROF. 42" RCP
18	O	1.12	2.36	19.4	3.14	5.27	4	12	10" TYPE R AT-GRADE INLET
19	P	0.41	0.53	11.5	3.92	6.56	1.4	3	8" TYPE R AT-GRADE INLET
20	Q	2.03	2.94	15.1	3.51	5.89	7	17	10" TYPE R AT-GRADE INLET
21	R	1.14							