

2022 Financial Assurance Estimate Form (with pre-plat construction)

Updated: 11/4/2021

PROJECT INFORMATION		
Woodmen Frontage Road Turn Lane	7/29/2022	CDR-21-018
Project Name	Date	PCD File No.

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)	
						% Complete	Remaining
SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)							
* Earthwork							
less than 1,000; \$5,300 min	180	CY	\$ 8.00	=	\$ 5,300.00		\$ 5,300.00
1,000-5,000; \$8,000 min		CY	\$ 6.00	=	\$ -		\$ -
5,001-20,000; \$30,000 min		CY	\$ 5.00	=	\$ -		\$ -
20,001-50,000; \$100,000 min		CY	\$ 3.50	=	\$ -		\$ -
50,001-200,000; \$175,000 min		CY	\$ 2.50	=	\$ -		\$ -
greater than 200,000; \$500,000 min		CY	\$ 2.00	=	\$ -		\$ -
* Permanent Seeding (inc. noxious weed mgmnt.)	0.13	AC	\$ 886.00	=	\$ 115.18		\$ 115.18
* Mulching		AC	\$ 831.00	=	\$ -		\$ -
* Permanent Erosion Control Blanket		SY	\$ 7.00	=	\$ -		\$ -
* Permanent Pond/BMP Construction		CY	\$ 22.00	=	\$ -		\$ -
* Permanent Pond/BMP (provide engineer's estimate)		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
Safety Fence		LF	\$ 3.00	=	\$ -		\$ -
Temporary Erosion Control Blanket		SY	\$ 3.00	=	\$ -		\$ -
Vehicle Tracking Control		EA	\$ 2,625.00	=	\$ -		\$ -
Silt Fence	812	LF	\$ 3.00	=	\$ 2,436.00		\$ 2,436.00
Temporary Seeding		AC	\$ 695.00	=	\$ -		\$ -
Temporary Mulch		AC	\$ 831.00	=	\$ -		\$ -
Erosion Bales		EA	\$ 28.00	=	\$ -		\$ -
Erosion Logs/Straw Wattles	50	LF	\$ 6.00	=	\$ 300.00		\$ 300.00
Rock Check Dams	5	EA	\$ 554.00	=	\$ 2,770.00		\$ 2,770.00
Inlet Protection		EA	\$ 185.00	=	\$ -		\$ -
Sediment Basin		EA	\$ 1,952.00	=	\$ -		\$ -
Concrete Washout Basin		EA	\$ 997.00	=	\$ -		\$ -
				=	\$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -
				=	\$ 1,927.10		\$ 1,927.10
MAINTENANCE (35% of Construction BMPs)				=	\$ 1,927.10		\$ 1,927.10
Section 1 Subtotal				=	\$ 12,848.28		\$ 12,848.28

* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

SECTION 2 - PUBLIC IMPROVEMENTS *

ROADWAY IMPROVEMENTS							
Construction Traffic Control	1	LS	\$ 500.00	=	\$ 500.00		\$ 500.00
Aggregate Base Course (135 lbs/cf)		Tons	\$ 31.00	=	\$ -		\$ -
Aggregate Base Course (135 lbs/cf)	225	CY	\$ 56.00	=	\$ 12,600.00		\$ 12,600.00
Asphalt Pavement (3" thick)	1,538	SY	\$ 16.00	=	\$ 24,608.00		\$ 24,608.00
Asphalt Pavement (4" thick)		SY	\$ 21.00	=	\$ -		\$ -
Asphalt Pavement (6" thick)		SY	\$ 32.00	=	\$ -		\$ -
Asphalt Pavement (147 lbs/cf) ___" thick		Tons	\$ 97.00	=	\$ -		\$ -
Raised Median, Paved		SF	\$ 9.00	=	\$ -		\$ -
Regulatory Sign/Advisory Sign		EA	\$ 333.00	=	\$ -		\$ -
Guide/Street Name Sign		EA		=	\$ -		\$ -
Epoxy Pavement Marking	1,250	SF	\$ 15.00	=	\$ 18,750.00		\$ 18,750.00
Thermoplastic Pavement Marking	150	SF	\$ 26.00	=	\$ 3,900.00		\$ 3,900.00
Barricade - Type 3		EA	\$ 221.00	=	\$ -		\$ -
Delineator - Type I		EA	\$ 27.00	=	\$ -		\$ -
Curb and Gutter, Type A (6" Vertical)		LF	\$ 32.00	=	\$ -		\$ -
Curb and Gutter, Type B (Median)		LF	\$ 32.00	=	\$ -		\$ -
Curb and Gutter, Type C (Ramp)		LF	\$ 32.00	=	\$ -		\$ -
4" Sidewalk (common areas only)		SY	\$ 53.00	=	\$ -		\$ -
5" Sidewalk		SY	\$ 66.00	=	\$ -		\$ -
6" Sidewalk		SY	\$ 80.00	=	\$ -		\$ -
8" Sidewalk		SY	\$ 106.00	=	\$ -		\$ -
Pedestrian Ramp		EA	\$ 1,273.00	=	\$ -		\$ -
Cross Pan, local (8" thick, 6' wide to include return)		LF	\$ 67.00	=	\$ -		\$ -
Cross Pan, collector (9" thick, 8' wide to include return)	113	LF	\$ 102.00	=	\$ 11,526.00		\$ 11,526.00
Curb Chase		EA	\$ 1,639.00	=	\$ -		\$ -
Guardrail Type 3 (W-Beam)		LF	\$ 55.00	=	\$ -		\$ -
Guardrail Type 7 (Concrete)		LF	\$ 80.00	=	\$ -		\$ -
Guardrail End Anchorage		EA	\$ 2,324.00	=	\$ -		\$ -
Guardrail Impact Attenuator		EA	\$ 4,172.00	=	\$ -		\$ -
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 87.00	=	\$ -		\$ -
Sound Barrier Fence (panels, 6' high)		LF	\$ 89.00	=	\$ -		\$ -
Electrical Conduit, Size =		LF	\$ 18.00	=	\$ -		\$ -
Traffic Signal, complete intersection		EA	\$ 470,666	=	\$ -		\$ -
Gravel Shoulder	28	CY	\$ 50	=	\$ 1,400.00		\$ 1,400.00
Concrete Valley Gutter	85	LF	\$ 10.00	=	\$ 850.00		\$ 850.00
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -

PROJECT INFORMATION

Woodmen Frontage Road Turn Lane

7/29/2022

CDR-21-018

Project Name

Date

PCD File No.

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)		
						% Complete	Remaining	
STORM DRAIN IMPROVEMENTS								
Concrete Box Culvert (M Standard), Size (W x H)		LF		=	\$ -		\$ -	
18" Reinforced Concrete Pipe		LF	\$ 70.00	=	\$ -		\$ -	
24" Reinforced Concrete Pipe		LF	\$ 83.00	=	\$ -		\$ -	
30" Reinforced Concrete Pipe		LF	\$ 104.00	=	\$ -		\$ -	
36" Reinforced Concrete Pipe		LF	\$ 128.00	=	\$ -		\$ -	
42" Reinforced Concrete Pipe		LF	\$ 171.00	=	\$ -		\$ -	
48" Reinforced Concrete Pipe		LF	\$ 209.00	=	\$ -		\$ -	
54" Reinforced Concrete Pipe		LF	\$ 272.00	=	\$ -		\$ -	
60" Reinforced Concrete Pipe		LF	\$ 319.00	=	\$ -		\$ -	
66" Reinforced Concrete Pipe		LF	\$ 368.00	=	\$ -		\$ -	
72" Reinforced Concrete Pipe		LF	\$ 421.00	=	\$ -		\$ -	
18" Corrugated Steel Pipe		LF	\$ 90.00	=	\$ -		\$ -	
24" Corrugated Steel Pipe		LF	\$ 103.00	=	\$ -		\$ -	
30" Corrugated Steel Pipe		LF	\$ 131.00	=	\$ -		\$ -	
36" Corrugated Steel Pipe		LF	\$ 157.00	=	\$ -		\$ -	
42" Corrugated Steel Pipe		LF	\$ 180.00	=	\$ -		\$ -	
48" Corrugated Steel Pipe		LF	\$ 190.00	=	\$ -		\$ -	
54" Corrugated Steel Pipe		LF	\$ 278.00	=	\$ -		\$ -	
60" Corrugated Steel Pipe		LF	\$ 300.00	=	\$ -		\$ -	
66" Corrugated Steel Pipe		LF	\$ 364.00	=	\$ -		\$ -	
72" Corrugated Steel Pipe		LF	\$ 428.00	=	\$ -		\$ -	
78" Corrugated Steel Pipe		LF	\$ 492.00	=	\$ -		\$ -	
84" Corrugated Steel Pipe		LF	\$ 588.00	=	\$ -		\$ -	
Flared End Section (FES) RCP Size = <i>(unit cost = 6x pipe unit cost)</i>		EA		=	\$ -		\$ -	
Flared End Section (FES) CSP Size = <i>(unit cost = 6x pipe unit cost)</i>		EA		=	\$ -		\$ -	
End Treatment- Headwall		EA		=	\$ -		\$ -	
End Treatment- Wingwall		EA		=	\$ -		\$ -	
End Treatment - Cutoff Wall		EA		=	\$ -		\$ -	
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 6,138.00	=	\$ -		\$ -	
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 7,981.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =5', 10' ≤ Depth < 15'		EA	\$ 9,242.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =10', Depth < 5'		EA	\$ 8,447.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =10', 5' ≤ Depth < 10'		EA	\$ 8,706.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =10', 10' ≤ Depth < 15'		EA	\$ 10,898.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =15', Depth < 5'		EA	\$ 10,984.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =15', 5' ≤ Depth < 10'		EA	\$ 11,775.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =15', 10' ≤ Depth < 15'		EA	\$ 12,876.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =20', Depth < 5'		EA	\$ 11,706.00	=	\$ -		\$ -	
Curb Inlet (Type R) L =20', 5' ≤ Depth < 10'		EA	\$ 12,920.00	=	\$ -		\$ -	
Grated Inlet (Type C), Depth < 5'		EA	\$ 5,138.00	=	\$ -		\$ -	
Grated Inlet (Type D), Depth < 5'		EA	\$ 6,347.00	=	\$ -		\$ -	
Storm Sewer Manhole, Box Base		EA	\$ 12,876.00	=	\$ -		\$ -	
Storm Sewer Manhole, Slab Base		EA	\$ 7,082.00	=	\$ -		\$ -	
Geotextile (Erosion Control)		SY	\$ 7.00	=	\$ -		\$ -	
Rip Rap, d50 size from 6" to 24"		Tons	\$ 89.00	=	\$ -		\$ -	
Rip Rap, Grouted		Tons	\$ 105.00	=	\$ -		\$ -	
Drainage Channel Construction, Size (W x H)		LF	\$ -	=	\$ -		\$ -	
Drainage Channel Lining, Concrete		CY	\$ 631.00	=	\$ -		\$ -	
Drainage Channel Lining, Rip Rap		CY	\$ 124.00	=	\$ -		\$ -	
Drainage Channel Lining, Grass		AC	\$ 1,626.00	=	\$ -		\$ -	
Drainage Channel Lining, Other Stabilization				=	\$ -		\$ -	
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -	
Section 2 Subtotal					=	\$ 74,134.00		\$ 74,134.00

* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

PROJECT INFORMATION

Woodmen Frontage Road Turn Lane	7/29/2022	CDR-21-018
Project Name	Date	PCD File No.


Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)	
						% Complete	Remaining
SECTION 3 - COMMON DEVELOPMENT IMPROVEMENTS (Private or District and NOT Maintained by EPC)**							
ROADWAY IMPROVEMENTS							
Utility Relocation (See MVEA Separate Contract)		EA	\$ -	=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
STORM DRAIN IMPROVEMENTS (Exception: Permanent Pond/BMP shall be itemized under Section 1)							
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
WATER SYSTEM IMPROVEMENTS							
Water Main Pipe (PVC), Size 8"		LF	\$ 71.00	=	\$ -		\$ -
Water Main Pipe (Ductile Iron), Size 8"		LF	\$ 83.00	=	\$ -		\$ -
Gate Valves, 8"		EA	\$ 2,058.00	=	\$ -		\$ -
Fire Hydrant Assembly, w/ all valves		EA	\$ 7,306.00	=	\$ -		\$ -
Water Service Line Installation, inc. tap and valves		EA	\$ 1,466.00	=	\$ -		\$ -
Fire Cistern Installation, complete		EA		=	\$ -		\$ -
				=	\$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -
SANITARY SEWER IMPROVEMENTS							
Sewer Main Pipe (PVC), Size 8"		LF	\$ 71.00	=	\$ -		\$ -
Sanitary Sewer Manhole, Depth < 15 feet		EA	\$ 4,858.00	=	\$ -		\$ -
Sanitary Service Line Installation, complete		EA	\$ 1,553.00	=	\$ -		\$ -
Sanitary Sewer Lift Station, complete		EA		=	\$ -		\$ -
				=	\$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -
LANDSCAPING IMPROVEMENTS (For subdivision specific condition of approval, or PUD)							
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
		EA		=	\$ -		\$ -
Section 3 Subtotal					=	\$ -	\$ -

** - Section 3 is not subject to defect warranty requirements

PROJECT INFORMATION

Woodmen Frontage Road Turn Lane	7/29/2022	CDR-21-018
Project Name	Date	PCD File No.

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS	\$ 5,000.00	= \$ 5,000.00		\$ 5,000.00
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS		= \$ -		\$ -
Total Construction Financial Assurance					\$	91,982.28
(Sum of all section subtotals plus as-builts and pond/BMP certification)						
Total Remaining Construction Financial Assurance (with Pre-Plat Construction)					\$	91,982.28
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)						
Total Defect Warranty Financial Assurance					\$	15,909.84
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)						



Approvals

I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.

08/02/2022

Engineer (P.E. Seal Required) _____

Approved by Owner / Applicant _____ Date 8/2/22

APPROVED

Approved by El Paso County Engineer / ECM Administrator _____

Engineering Review

09/29/2022 12:47:28 PM
dsdrice
JeffRice@elpasoco.com
(719) 520-7877
EPC Planning & Community
Development Department