



**ENTECH**  
ENGINEERING, INC.

505 ELKTON DRIVE  
COLORADO SPRINGS, CO 80907  
PHONE (719) 531-5599

**SOILS AND GEOLOGY STUDY  
MERIDIAN RANCH – ROLLING HILLS RANCH NORTH  
FILING NOS. 1 AND 2  
EL PASO COUNTY, COLORADO**

Prepared for:  
**Tech Contractors**  
**3575 Kenyon Street, Suite 200**  
**San Diego, California 92110**

Attn: Raul Guzman

February 12, 2024

Respectfully Submitted,

ENTECH ENGINEERING, INC.

Reviewed by:

Logan L. Langford, P.G.  
Sr. Geologist



Digitally signed by  
Joseph C Goode Jr.  
Date: 2024.02.12  
14:16:12 -07'00'  
Joseph C. Goode Jr., P.E.  
President

LLL

**EPC: PUD SP-235**

**Table of Contents**

**1 SUMMARY..... 1**

**2 GENERAL SITE CONDITIONS AND PROJECT DESCRIPTION ..... 2**

**3 SCOPE OF THE REPORT ..... 2**

**4 FIELD INVESTIGATION ..... 3**

**5 SOIL, GEOLOGY, AND ENGINEERING GEOLOGY..... 3**

    5.1 General Geology ..... 3

    5.2 Soil Conservation Survey ..... 4

    5.3 Site Stratigraphy ..... 4

    5.4 Soil Conditions ..... 5

    5.5 Groundwater ..... 7

**6 ENGINEERING GEOLOGY – IDENTIFICATION AND MITIGATION OF GEOLOGIC HAZARDS ..... 7**

    6.1 Relevance of Geologic Conditions to Land Use Planning ..... 9

**7 ECONOMIC MINERAL RESOURCES ..... 11**

**8 EROSION CONTROL ..... 12**

**9 ROADWAY, EMBANKMENT, and STORMWATER DETENTION FACILITY CONSTRUCTION RECOMMENDATIONS ..... 13**

**10 CLOSURE..... 14**

**11 REFERENCES..... 15**

**FIGURES**

- Figure 1: Vicinity Map
- Figure 2: USGS Map
- Figure 3: Development Plan/Test Boring Location Map
- Figure 4: Cut/Fill Map
- Figure 5: Soil Survey Map
- Figure 6: Falcon NW Quadrangle Geology Map
- Figure 7: Geology Map/Engineering Geology
- Figure 8: Floodplain Map
- Figure 9: Typical Perimeter Drain Details
- Figure 10: Underslab Drainage Layer (Capillary Break)
- Figure 11: Interceptor Drain Detail

- APPENDIX A: Site Photographs
- APPENDIX B: Subsurface Soil Investigation, Entech Job No. 220455
- APPENDIX C: Soil Survey Descriptions
- APPENDIX D: Entech Overlot Fill Testing Records

## 1 SUMMARY

### ***Project Location***

The project lies in a portion of N½ of Section 20, Township 12 South, Range 64 West of the 6<sup>th</sup> Principal Meridian in El Paso County, Colorado. The site is located approximately five miles northeast of Colorado Springs in northern El Paso County, Colorado, northeast of the intersection of Estate Ridge Drive and Rex Road in the Meridian Ranch Subdivision.

### ***Project Description***

Meridian Ranch – Rolling Hills Ranch North Filing Nos. 1 and 2 will consist of the development of approximately 147 acres with two hundred and twenty-four (224) lots proposed. The proposed development is to consist of single-family residential lots, which will be serviced by Woodmen Hills Metropolitan District.

### ***Scope of Report***

This report presents the results of our geologic evaluation and treatment of engineering geologic hazard study.

### ***Land Use and Engineering Geology***

This site was found to be suitable for the proposed development. Areas were encountered where the geologic conditions will impose some minor constraints on development and land use. These include areas of expansive soils, shallow bedrock, seasonally shallow groundwater areas, and potential for elevated radon levels. Based on the proposed development plan, it appears that these areas will have some impact on the development. These conditions will be discussed in greater detail in the report.

In general, it is our opinion that the development can be achieved if the observed geologic conditions on site are either avoided or properly mitigated. All recommendations are subject to the limitations discussed in the report.

## **2 GENERAL SITE CONDITIONS AND PROJECT DESCRIPTION**

The site is located in a portion of N½ of Section 20, Township 12 South, Range 64 West of the 6<sup>th</sup> Principal Meridian in El Paso County, Colorado. The site is located approximately five miles northeast of Colorado Springs in northern El Paso County, Colorado, northeast of the intersection of Estate Ridge Drive and Rex Road in the Meridian Ranch Subdivision. The location of the site is as shown on the Vicinity Map, Figure 1.

The topography of the site is gently rolling hills and valleys with a general southeast-sloping trend. A drainage is located through the central portion of the site, and a minor drainage swale in the northeastern portion of the site within a proposed open space area. Vegetation consisted of field grasses and weeds. Existing residences and proposed developments are located to the west and southwest of the site, undeveloped land lies immediately north, south, and east and Eastonville Road to the east. The site boundaries are indicated on the USGS Map, Figure 2. Previous land uses have consisted of undeveloped grazing and pasture land. Site photographs, taken February 1, 2024, are included in Appendix A.

Meridian Ranch – Rolling Hills Ranch North Filing Nos. 1 and 2 will consist of the development of approximately 147 acres with two hundred and twenty-four (224) residential lots proposed. The development is to consist of single-family residential, which will be serviced by Woodmen Hills Metropolitan District. Site grading plans indicated cuts up to 21 feet and fills up to 12 feet. The majority of the cuts and fills were in the 2 to 8-foot range. Figure 4 shows the Cut/Fill Map. At the time of our site observations and field mapping the grading was completed. The Development Plan/Test Boring Location Map is presented in Figure 3.

## **3 SCOPE OF THE REPORT**

The scope of the report will include a general geologic analysis utilizing published geologic data. Detailed site-specific mapping will be conducted to obtain general information in respect to major geographic and geologic features, geologic descriptions and their effects on the development of the property.

## 4 FIELD INVESTIGATION

Our field investigation consisted of the preparation of a geologic map of any bedrock features and significant surficial deposits. The Natural Resource Conservation Service (NRCS), previously the Soil Conservation Service (SCS) survey was also reviewed to evaluate the site. The position of mappable units within the subject property are shown on the Geologic Map. Our mapping procedures involved both field reconnaissance and measurements and air photo reconnaissance and interpretation. The same mapping procedures have also been utilized to produce the Engineering Geology Map which identified pertinent geologic conditions affecting development. The field mapping was performed by personnel of Entech Engineering, Inc. on February 1, 2024.

Nineteen Test Borings were drilled as part of the *Subsurface Soil Investigation*, dated April 20, 2022, Entech Job No. 220455 (Reference 1, Appendix B) to determine general soil and bedrock characteristics. This report was used in the preparation of the *Soils and Geology Study*. The locations of the test borings are indicated on the Exploration/Site Plan, Figure 3. The Test Boring Logs and Laboratory testing Results are included in Appendix B. Results of this testing will be discussed later in this report. The *Soil, Geology, and Geologic Hazard Evaluation for Meridian Ranch – Rolling Hills Ranch, Filings 1 through 4*, dated September 20, 2019, Entech Job No. 190300 (Reference 2) was also utilized in the preparation of this report.

## 5 SOIL, GEOLOGY, AND ENGINEERING GEOLOGY

### 5.1 General Geology

Physiographically, the site lies in the western portion of the Great Plains Physiographic Province. Approximately 17 miles to the west is a major structural feature known as the Rampart Range Fault. This fault marks the boundary between the Great Plains Physiographic Province and the Southern Rocky Mountain Province. The site exists within the southeastern edge of a large structural feature known as the Denver Basin. Bedrock in the area tends to be very gently dipping in a northerly direction (Reference 3). The rocks in the area of the site are sedimentary in nature and typically Upper Cretaceous in age. The bedrock underlying the site consists of the Dawson Formation. Overlying this formation are unconsolidated deposits of alluvial soils of Quaternary Age. The alluvial soils were deposited by water on site and as stream terraces along Sand Creek and the drainages located on the site. Man-made soils exist as fill piles located in the southern portion of the site. The site's stratigraphy will be discussed in more detail in Section 5.3.

## 5.2 Soil Conservation Survey

The Natural Resource Conservation Service (Reference 4), previously the Soil Conservation Service (Reference 5) has mapped two soil types on the site (Figure 5). In general, the soils classify as coarse sandy loam. The soils are described as follows:

<u>Type</u>	<u>Description</u>
19	Columbine Gravelly Sandy Loam, 0 to 3% slopes
83	Stapleton Sandy Loam, 3 to 8% slopes

Complete descriptions of each soil type are presented in Appendix C. The soils have generally been described to have moderate to moderately rapid permeabilities. Possible hazards with soil erosion are present on the site. The erosion potential can be controlled with vegetation. The majority of the soils have been described to have moderate erosion hazards

## 5.3 Site Stratigraphy

The Falcon Quadrangle Geology Map showing the site is presented in Figure 6 (Reference 6). The Geology Map prepared for the site is presented in Figure 7. Five mappable units were identified on this site which are described as follows:

- Qda Disturbed Area of Holocene Age:** These are the recent cut/fill operations for the development that have been completed. The fill placement was observed and tested by representatives of Entech, and the Cut/Fill Map is presented in Figure 4. The overlot fill density records are included in Appendix D.
- Qaf Artificial Fill of Holocene Age:** These recent man-made deposits associated with an erosion berm located in the northeastern portion of the site. The berm is currently located in the proposed open space area and will be avoided. Additionally, the grading for the development has been completed. The fill placement was observed and tested by representatives of Entech. The Cut/Fill Map is presented in Figure 4. The overlot fill density records are included in Appendix D.
- Qa<sub>1</sub> Alluvium One of late Holocene Age:** These are water deposited along the active drainage as stream terrace deposits that typically consist of silty to clayey sands and may contain clay layers. The Alluvium one correlates with the Post-Piney Creek Alluvium.

- Qa<sub>3</sub>**     **Alluvium Three of late Pleistocene Age:** These are water deposited as stream terrace deposits that typically consist of silty to clayey sands and may contain clay layers. The Alluvium Three correlates with the Broadway Alluvium.
- Tda**     **Dawson Arkose Formation of Tertiary Age:** The Dawson Formation typically consists of arkosic sandstone with interbedded fine-grained sandstone, siltstone and claystone. Overlying this formation is a variable layer of residual soil. The residual soils were derived from the in-situ weathering of the bedrock materials on-site. These soils consisted of silty sands and may contain layers of sandy clays.

The bedrock underlying the site consists of the Dawson Formation of Tertiary Age. The Dawson Formation typically consists of arkosic sandstone with interbedded fine-grained sandstone, siltstone and claystone. Overlying this formation are variable layers of man-placed fill deposits, alluvial deposits, and residual soil. The residual soils were derived from the in-situ weathering of the bedrock materials on-site. These soils consisted of silty to clayey sands and sandy clays.

The soils listed above were mapped from site-specific mapping, the *Geologic Map of the Falcon Quadrangle* distributed by the Colorado Geological Survey in 2012 (Reference 6), the *Geologic Map of the Colorado Springs-Castle Rock Area*, distributed by the US Geological Survey in 1981 (Reference 8), and the *Geologic Map of the Denver 1<sup>o</sup> x 2<sup>o</sup> Quadrangle*, distributed by the US Geological Survey in 1981 (Reference 8). The Test Borings used in evaluating the site and are included in Appendix B. The Geology/Engineering Geology Map prepared for the site is presented in Figure 7.

#### **5.4 Soil Conditions**

The soils encountered in the Test Borings can be grouped into three general soil types. The soils were classified using the Unified Soil Classification System (USCS).

Soil Type 1 classified as native silty to clayey to very clayey sand (SM, SC). The sand was encountered in all of the test borings at the existing ground surface and extending to depth ranging from 1 to 4 feet below ground surface (bgs). Standard Penetration Testing conducted on the sand resulted in SPT N-values ranging from 27 to 47 blows per foot (bpf), indicating medium dense to dense states. Water content and grain size testing of selected soil samples resulted in a water content range of 2 to 9 percent, and 40 percent of the soil particles passing the No. 200 sieve. Atterberg limits testing on a sample of very clayey sand resulted in a Liquid Limit of 40 and a

Plastic Index of 27. Swell/Consolidation testing on a sample of very clayey sand resulted in a volume change of 0.2 percent, indicating a low expansion potential. Sulfate testing resulted in less than 0.01 percent soluble sulfate by weight, which indicates a negligible potential for below grade concrete degradation due to sulfate attack.

Soil Type 2 classified as native sandy clay (CL). The clay was encountered in Test Boring Nos. 2 and 11 at the surface and extending to 3 and 4 feet bgs. Standard Penetration Testing conducted on the clay resulted in SPT N-values from 26 and 31, which indicates stiff consistencies. Water content and grain size testing resulted in a water content of 12 percent, and 83 to 90.5 percent of the soil particles passing the No. 200 sieve. Atterberg Limits testing resulted in Liquid Limit of 31 and a Plastic Index of 17. Swell/Consolidation testing on the clay resulted in volume changes of +1.0 to -1.1 percent, indicating low to moderate consolidation and expansion potential.

Soil Type 3 classified as slightly silty to silty to very clayey sandstone bedrock (SM-SW, SM, SC). The sandstone was encountered in all the test borings below the Type 1 and 2 soils, at 1 to 9 feet bgs and extending to various depths or to termination of borings (20 to 30 feet). Standard Penetration Testing conducted on the sandstone resulted in SPT N-values of 38 to greater than 50 bpf, which indicates dense to very dense states. Water content and grain size testing resulted in a water content range of 1 to 12, and 7 to 49 percent the soil size particles passing the No. 200 sieve. Atterberg limits testing on a sample of the slightly silty sandstone resulted in no values. Swell/Consolidation testing on the sandstone resulted in volume changes of -0.1 to -0.3 percent, indicating a low consolidation and expansion potential.

Soil Type 4 classified as a sandy to very sandy claystone (CL). The claystone was encountered below the surficial soils or interbedded in the sandstone at varying depths. Standard Penetration Testing on the claystone resulted in greater than 50 bpf, indicating hard consistencies. Water content and grain size testing resulted in 8 to 15 percent water content with 51 to 81 percent of soil size particles passing the No. 200 sieve. Atterberg limits testing resulted in liquid limits of 36 to 42 percent and plastic indexes of 19 to 22 percent. Swell/Consolidation testing of random claystone samples resulted in volume changes of -1.1 to +0.1, indicating a low to moderate consolidation potential and a low expansion potential. Sulfate testing indicated a negligible degradation potential due to sulfate attack.

The Test Boring Logs are presented in Appendix B. Laboratory Test Results are presented in Appendix C, and a Summary of Laboratory Test Results is presented in Table 1C.



## 5.5 Groundwater

Groundwater was only encountered in two of the test borings at a depth of 16 and 17 feet (TB-2 and TB-12). All other test borings were dry to the depth drilled. These areas are discussed in the following section. Fluctuation in groundwater conditions may occur due to variations in rainfall and other factors not readily apparent at this time. It should be noted that in the sandy materials on-site, some groundwater conditions might be encountered due to the variability in the soil profile. Isolated sand and gravel layers within the soils, sometimes only a few feet in thickness and width, can carry water in the subsurface. Groundwater may also flow on top of the underlying bedrock. Builders and planners should be cognizant of the potential for the occurrence of such subsurface water features during construction on-site and deal with each individual problem as necessary at the time of construction.

## 6 ENGINEERING GEOLOGY – IDENTIFICATION AND MITIGATION OF GEOLOGIC HAZARDS

Detailed mapping has been performed on this site to produce a Geology/Engineering Geology Map Figure 7. This map shows the location of various geologic conditions of which the developers should be cognizant during the planning, design and construction stages of the project. These hazards and the recommended mitigation techniques are as follows:

### Artificial Fill – Constraint

These are areas of man-made fill associated with earthen berm in the northeastern portion of the site.

Mitigation: This erosion berm will be avoided. Any uncontrolled fill encountered beneath foundations will require removal and recompaction at a minimum of 95% of its maximum Modified Procter Dry Density, ASTM D-1557.

### Disturbed Area – Constraint

This area is associated with the grading for the development has been completed. The fill placement was observed and tested by representatives of Entech, and the Cut/Fill Map is presented in Figure 4. The overlot fill density records are included in Appendix D. The fill is considered controlled for construction purposes, however, where clay or claystone are encountered mitigation for expansive soils will be required.

### Expansive Soils – Constraint

Expansive soils were encountered in the test borings drilled on site. These occurrences are typically sporadic; therefore, none have been indicated on the maps. The clays and claystone, if encountered at foundation grade, can cause differential movement in structures. These occurrences should be identified and dealt with on an individual basis.

Mitigation Should expansive soils be encountered beneath foundations; mitigation will be necessary. Mitigation of expansive soils will require special foundation design. Overexcavation 3 to 5 feet and replacement with non-expansive soils at a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557 is a suitable mitigation, which is common in the area. Floor slabs on expansive soils should be expected to experience movement. Overexcavation and replacement has been successful in minimizing slab movements. The use of structural floors should be considered for basement construction on highly expansive clays. Final recommendations should be determined after additional investigation of the building sites.

### Shallow Bedrock – Constraint

Bedrock was encountered in all the test borings at depths ranging from 1 to 9 feet. Shallow bedrock will be encountered in some areas of this site. Where claystone or sandstone are encountered, excavation/grading may be difficult requiring track-mounted excavators. Bedrock will likely be encountered cuts for utility excavations.

### Groundwater and Floodplain Areas – Constraint

The site is not mapped within floodplain zones according to the FEMA Map No. 08041CO552G, Figure 8 (Reference 7). A drainage is located through the central portion of the site, and a minor drainage swale in the northeastern portion of the site within a proposed open space area. The main drainage through the central portion of the site is within a drainage easement and will be avoided with developed lots. These areas are discussed as follows:

### Seasonal Shallow Groundwater Area – Constraint

In these areas, we would anticipate the potential for periodically high subsurface moisture conditions, frost heave potential and highly organic soils. These areas are associated with the drainage through the central portion of the site which will be avoided by the construction on the lots. Construction of the roadway crossing the drainage and utility installation may encounter shallow groundwater, and may require the use of temporary dewatering measures.

Mitigation: Foundations must have a minimum 30-inch depth for frost protection. In areas where high subsurface moisture conditions are anticipated periodically, subsurface perimeter drains are

recommended to help prevent the intrusion of water into areas below grade. Areas may experience higher groundwater levels during period of higher precipitation where water can flow through permeable sands on top of less permeable bedrock materials. Subsurface perimeter drains may be necessary to prevent the intrusion of water into areas below grade. Typical drain details are presented in Figure 9. Where shallow groundwater is encountered, underslab drains or interceptor drains may be necessary. Typical drain details are presented in Figures 9 and 11. Specific recommendations should be made after additional investigation of the lots has been completed.

Radon – Hazard

Radon levels for the area have been reported by the Colorado Geologic Survey in the open file, Report No. 91-4 (Reference 11). Average Radon levels for the 80831-zip code is 4.50 pCi/l. The following is a table of radon levels in this area:

<u>80831</u>	
0 < 4 pCi/l	0.00%
4 < 10 pCi/l	100.00%
10 < 20 pCi/l	0.00%
> 20 pCi/l	0.00%

Mitigation:

The potential for high radon levels is present for the site. Build-up of radon gas can usually be mitigated by providing increased ventilation of basement and crawlspace and sealing joints. Specific requirements for mitigation should be based on site specific testing.

**6.1 Relevance of Geologic Conditions to Land Use Planning**

As mentioned earlier in this report, we understand that the development will be single-family residential. It is our opinion that the existing geologic and engineering geologic conditions will impose some minor constraints on the proposed development and construction. The constraints affecting development will be those associated with the expansive soils, shallow bedrock, and potential for elevated radon levels on the site that can be satisfactorily mitigated through proper engineering design and construction practices or avoidance. Shallow groundwater areas will be encountered during road construction across the drainage.

The upper residual soils are typically at medium to very dense states. The granular soils encountered in the upper soil profiles of the test borings should provide good support for foundations.

The overlot grading was performed prior to the completion of this report. Overlot fill placement was observed and tested by representatives of Entech. The Cut/Fill Map is presented in Figure 4. The overlot fill density records are included in Appendix D. The fill is considered controlled for construction purposes, however, where clay or claystone are encountered mitigation for expansive soils will be required.

Expansive soils were encountered on portions of the site that will require mitigation. Foundations anticipated for the site are standard spread footings possibly in conjunction with overexcavation in areas of expansive soils. Areas containing arkosic sandstone will have high allowable bearing conditions. Difficult excavation should be anticipated in areas of shallow bedrock. Expansive layers may also be encountered in the soil and bedrock on this site. Areas of expansive soils encountered on site are sporadic; therefore, none have been indicated on the maps. Expansive soils, if encountered, will require special foundation design and/or overexcavation. These soils will not prohibit development. Bearing capacities of 2000 to 2400 psf for granular soils or structural fill, and 3000 to 3500 psf for undisturbed sandstone are anticipated. Site specific subsurface investigations will need to be conducted and recommendations provided prior to construction.

Areas of seasonal shallow groundwater were observed on site. These areas will be avoided by the development of the lots, however, construction of the roadway crossing drainage and utility installation may encounter shallow groundwater, and may require the use of temporary dewatering measures. Subsurface perimeter drains will be recommended for all basements; typical perimeter drain details are presented in Figure 9. If shallow groundwater is encountered, underslab drains or interceptor drains may be necessary. Typical drain details are presented in Figures 9 and 11. Specific recommendations should be made after additional investigation of the lots has been completed.

In summary, development of the site can be achieved if the items mentioned above are mitigated. These items can be mitigated through proper design and construction or through avoidance. Investigation on each lot is recommended prior to construction.

## 7 ECONOMIC MINERAL RESOURCES

Some of the sandy materials on-site could be considered a low-grade sand resource. According to the *El Paso County Aggregate Resource Evaluation Map* (Reference 12) and the *Atlas of Sand, Gravel and Quarry Aggregate Resources, Colorado Front Range Counties* distributed by the Colorado Geological Survey (Reference 13), the area is mapped with U4-upland deposits (probable aggregate resource) and A3-Alluvial Fan deposits (sand, fine aggregate resource). According to the *Evaluation of Mineral and Mineral Fuel Potential* (Reference 14), the area of the site has been mapped as “Fair” for industrial minerals. However, considering the silty nature of much of these materials and abundance of similar materials through the region and the close proximity to developed land, they would be considered to have little significance as an economic resource.

According to the *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands* (Reference 14), the site is mapped within the Denver Basin Coal Region. However, the area of the site has been mapped as “Poor” for coal resources. No active or inactive mines have been mapped in the area of the site. No metallic mineral resources have been mapped on-site (Reference 14).

The site has been mapped as “Fair” for oil and gas resources (Reference 14). No oil or gas fields have been discovered in the area of the site. The sedimentary rocks in the area may lack the geologic structure for trapping oil or gas; therefore, it may not be considered a significant resource. Hydraulic fracturing is a new method that is being used to extract oil and gas from rocks. It utilizes pressurized fluid to extract oil and gas from rocks that would not normally be productive. The area of the site has not been explored to determine if the rocks underlying the site would be commercially viable utilizing hydraulic fracturing. The practice of hydraulic fracturing has come under review due to concerns about environmental impacts, health and safety.

## 8 EROSION CONTROL

The soil types observed on the site are mildly to highly susceptible to wind erosion, and moderately to highly susceptible to water erosion. A minor wind erosion and dust problem may be created for a short time during and immediately after construction. Should the problem be considered severe enough during this time, watering of the cut areas or the use of chemical palliative may be required to control dust. However, once construction has been completed and vegetation re-established, the potential for wind erosion should be considerably reduced.

With regard to water erosion, loosely compacted soils will be the most susceptible to water erosion, residually weathered soils become increasingly less susceptible to water erosion. For the typical soils observed on-site, allowable velocities on unvegetated and unlined earth channels would be on the order of 3 to 4 feet/second, depending upon the sediment load carried by the water. Permissible velocities may be increased through the use of vegetation to something on the order of 4 to 7 feet/second, depending upon the type of vegetation established. Should the anticipated velocities exceed these values, some form of channel lining material may be required to reduce erosion potential. These might consist of some of the synthetic channel lining materials on the market or conventional riprap. In cases where ditch-lining materials are still insufficient to control erosion, small check dams or sediment traps may be required. The check dams will serve to reduce flow velocities, as well as provide small traps for containing sediment. The determination of the amount, location and placement of ditch linings, check dams and of the special erosion control features should be performed by or in conjunction with the drainage engineer who is more familiar with the flow quantities and velocities.

Cut and fill slope areas will be subjected primarily to sheetwash and rill erosion. Unchecked rill erosion can eventually lead to concentrated flows of water and gully erosion. The best means to combat this type of erosion is, where possible, the adequate re-vegetation of cut and fill slopes. Cut and fill slopes having gradients more than three (3) horizontal to one (1) vertical become increasingly more difficult to revegetate successfully. Therefore, recommendations pertaining to the vegetation of the cut and fill slopes may require input from a qualified landscape architect and/or the Soil Conservation Service.

## **9 ROADWAY, EMBANKMENT, AND STORMWATER DETENTION FACILITY CONSTRUCTION RECOMMENDATIONS**

In general, the site soils are suitable for the proposed roadways and embankments. Groundwater may be encountered in deeper cuts and along drainages and low-lying areas. Additional investigation of these areas is recommended as plans are completed. If excavations encroach on the groundwater level unstable soil conditions may be encountered. Excavation of saturated soils will be difficult with rubber-tired equipment. Stabilization using shot rock or geogrids may be necessary.

Any areas to receive fill should have all topsoil, organic material or debris removed. Prior to fill placement Entech should observe the subgrade. Fill must be properly benched and compacted to minimize potentially unstable conditions in slope areas. Fill slopes should be 3:1 or flatter. The subgrade should be scarified and moisture conditioned to within 2% of optimum moisture content and compacted to a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557, prior to placing new fill. Areas receiving fill may require stabilization with rock or fabric if shallow groundwater conditions are encountered.

New fill should be placed in thin lifts not to exceed 6 inches after compaction while maintaining at least 95% of its maximum Modified Proctor Dry Density, ASTM D-1557. These materials should be placed at a moisture content conducive to compaction, usually 0 to  $\pm 2\%$  of Proctor optimum moisture content. The placement and compaction of fill should be observed and tested by Entech during construction. Entech should approve any import materials prior to placing or hauling them to the site. Additional investigation will be required for pavement designs once roadway grading is completed and utilities are installed.

## 10 CLOSURE

It is our opinion that the existing geologic engineering and geologic conditions will impose some constraints on development and construction of the site. The majority of these conditions can be mitigated through proper engineering design and construction practices. The proposed development and use are consistent with anticipated geologic and engineering geologic conditions.

It should be pointed out that because of the nature of data obtained by random sampling of such variable and non-homogeneous materials as soil and rock, it is important that we be informed of any differences observed between surface and subsurface conditions encountered in construction and those assumed in the body of this report. Individual investigations for building sites will be required prior to construction. Construction and design personnel should be made familiar with the contents of this report. Reporting such discrepancies to Entech Engineering, Inc. soon after they are discovered would be greatly appreciated and could possibly help avoid construction and development problems.

This report has been prepared for Tech Contractors. for application to the proposed project in accordance with generally accepted geologic soil and engineering practices. No other warranty expressed or implied is made.

We trust that this report has provided you with all the information that you required. Should you require additional information, please do not hesitate to contact Entech Engineering, Inc.



## 11 REFERENCES

1. Entech Engineering, Inc. April 20, 2022. *Subsurface Soil Investigation, Meridian Ranch, Rolling Hills Ranch North, Filing Nos. 1 and 2, North of Rex Road, El Paso County, Colorado.* Entech Job No. 220455.
2. Entech Engineering, Inc. September 20, 2019. *Soil, Geology, and Geologic Hazard Evaluation, Meridian Ranch – Rolling Hills Ranch, Filings 1 through 4, El Paso County, Colorado.* Entech Job No. 190300.
3. Bryant, Bruce; McGrew, Laura W. and Wobus, Reinhard A. 1981. *Geologic Structure Map of the Denver 1° x 2° Quadrangle, North-Central Colorado.* Sheet 2. U.S. Geologic Survey. Map 1-1163.
4. Natural Resource Conservation Service, August 24, 2023. *Web Soil Survey.* United States Department Agriculture, <http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>.
5. United States Department of Agriculture Soil Conservation Service. June 1981. *Soil Survey of El Paso County Area, Colorado.*
6. Morgan, Matthew L., and White, Jonathan L., 2012. *Geologic Map of the Falcon Quadrangle, El Paso County, Colorado.* Colorado Geological Survey. Open-File Report 12-05.
7. Trimble, Donald E. and Machette, Michael N. 1979. *Geologic Map of the Colorado Springs-Castle Rock Area, Front Range Urban Corridor, Colorado.* USGS, Map I-857-F.
8. Bryant, Bruce; McGrew, Laura W. and Wobus, Reinhard A. 1981. *Geologic Structure Map of the Denver 1° x 2° Quadrangle, North-Central Colorado.* U.S. Geologic Survey. Map 1-1163.
9. Federal Emergency Management Agency. December 7, 2018. *Flood Insurance Rate Maps for El Paso County, Colorado and Incorporated Areas.* Map Number 08041CO552G.
10. Kirkman, Robert M. and Rogers, William P. 1981. *Earthquake Potential in Colorado.* Colorado Geological Survey. Bulletin 43.
11. Colorado Geological Survey. 1991. *Results of the 1987-88 EPA Supported Radon Study in Colorado.* Open-file Report 91-4.
12. El Paso County Planning Development. December 1995. *El Paso County Aggregate Resource Evaluation Maps.*
13. Schwochow, S.D.; Shroba, R.R. and Wicklein, P.C. 1974. *Atlas of Sand, Gravel, and Quarry Aggregate Resources, Colorado Front Range Counties.* Colorado Geological Survey. Special Publication 5-B.
14. Keller, John W.; TerBest, Harry and Garrison, Rachel E. 2003. *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands Administered by the Colorado State Land Board.* Colorado Geological Survey. Open-File Report 03-07.

## FIGURES



**PROJECT  
SITE**




**VICINITY MAP**

MERIDIAN RANCH  
ROLLING HILLS RANCH NORTH  
TECH CONTRACTORS

JOB NO.  
220455

**FIG. 1**



PROJECT  
SITE





**USGS TOPOGRAPHY MAP**

MERDIAN RANCH  
ROLLING HILLS RANCH NORTH  
TECH CONTRACTORS

JOB NO.  
220455

**FIG. 2**



- EXISTING BORINGS
- ◆ PROPOSED BORINGS

- ◆ - APPROXIMATE TEST BORING LOCATION AND NUMBER
- Ⓟ - APPROXIMATE PHOTOGRAPH LOCATION AND NUMBER



**SITE / TEST BORING  
LOCATION MAP**  
ADDRESS  
CITY  
CLIENT

JOB NO.  
231532  
**FIG. 3**




**CUT/FILL MAP**  
 MERIDIAN RANCH  
 ROLLING HILLS RANCH NORTH  
 TECH CONTRACTORS

JOB NO.  
220455

**FIG. 4**

PROJECT  
SITE




**SOIL SURVEY MAP**

MERIDIAN RANCH  
ROLLING HILLS RANCH NORTH  
TECH CONTRACTORS

JOB NO.  
220455

**FIG. 5**





**GEOLOGIC MAP OF THE FALCON  
QUADRANGLE**  
MERIDIAN RANCH  
ROLLING HILLS NORTH RANCH  
TECH CONTRACTORS

JOB NO.  
220455

**FIG. 6**





- EXISTING BORINGS
- ◆ PROPOSED BORINGS

- Legend:**
- Qda - Disturbed Area of Holocene Age:  
cut/fill grading for lots and roadways
  - Qaf - Artificial Fill of Holocene Age:  
man placed fill deposit
  - Qa1 - Alluvium one of late Holocene Age:  
recent water deposited clayey to silty sands
  - Qa3 - Alluvium three of late Pleistocene Age:  
stream terrace deposited sands
  - Tda - Dawson Arkose of Tertiary Age:  
arkosic sandstone with interbedded claystone and siltstone
  - sw - seasonal shallow groundwater area



**GEOLOGY / ENGINEERING MAP**

MERIDIAN RANCH  
ROLLING HILLS RANCH NORTH  
TECH CONTRACTORS

JOB NO.  
220455

**FIG. 7**




**FEMA FLOODPLAIN MAP**

MERIDIAN RANCH  
ROLLING HILLS RANCH NORTH  
TECH CONTRACTORS

JOB NO.  
220455

**FIG. 8**



NOTES:

-GRAVEL SIZE IS RELATED TO DIAMETER OF PIPE PERFORATIONS-85% GRAVEL GREATER THAN 2x PERFORATION DIAMETER.

-PIPE DIAMETER DEPENDS UPON EXPECTED SEEPAGE. 4-INCH DIAMETER IS MOST OFTEN USED.

-ALL PIPE SHALL BE PERFORATED PLASTIC. THE DISCHARGE PORTION OF THE PIPE SHOULD BE NON-PERFORATED PIPE.

-FLEXIBLE PIPE MAY BE USED UP TO 8 FEET IN DEPTH, IF SUCH PIPE IS DESIGNED TO WITHSTAND THE PRESSURES. RIGID PLASTIC PIPE WOULD OTHERWISE BE REQUIRED.

-MINIMUM GRADE FOR DRAIN PIPE TO BE 1% OR 3 INCHES OF FALL IN 25 FEET.

-DRAIN TO BE PROVIDED WITH A FREE GRAVITY OUTFALL, IF POSSIBLE. A SUMP AND PUMP MAY BE USED IF GRAVITY OUTFALL IS NOT AVAILABLE.




**PERIMETER DRAIN DETAIL**

MERIDIAN RANCH  
ROLLING HILLS RANCH NORTH  
TECH CONTRACTORS

JOB NO.  
220455


**FIG. 9**



**TYP. UNDERSLAB DRAINAGE LAYER  
(CAPILLARY BREAK)**  
 MERIDIAN RANCH  
 ROLLING HILLS RANCH NORTH  
 TECH CONTRACTORS

JOB NO.  
220455

**FIG. 10**



NOTE:  
 EXTEND INTERCEPTOR DRAIN TO UNDERDRAIN OR TO SUMP.  
 BENCH DRAIN INTO NATIVE SOILS 12 INCHES MINIMUM.

## INTERCEPTOR DRAIN DETAIL

N.T.S.



### INTERCEPTOR DRAIN DETAIL


MERIDIAN RANCH  
 ROLLING HILLS RANCH NORTH  
 TECH CONTRACTORS

JOB NO.  
 220455

**FIG. 11**




## **APPENDIX A: Site Photographs**




**Looking west from the southeastern portion of the site.**

February 1, 2024




**Looking north from the southeastern portion of the site.**

February 1, 2024



**Looking west from the southeastern portion of the site.**


February 1, 2024



**Looking north from the southeastern portion of the site.**


February 1, 2024






**Looking from the central portion of the site.**

February 1, 2024




**Looking southwest from the central portion of the site.**

February 1, 2024




**Looking north from the central portion of the site.**

February 1, 2024




**Looking west along the future drainage crossing.**

February 1, 2024



**Looking west from the western portion of the site.**

February 1, 2024



**Looking east from the western portion of the site.**

February 1, 2024



**APPENDIX B: Entech, Subsurface Soil Investigation,  
Job No. 220455**



**ENTECH**  
ENGINEERING, INC.

505 ELKTON DRIVE  
COLORADO SPRINGS, CO 80907  
PHONE (719) 531-5599  
FAX (719) 531-5238

**SUBSURFACE SOIL INVESTIGATION  
MERIDIAN RANCH, ROLLING HILLS RANCH NORTH  
FILING NOS. 1 AND 2  
NORTH OF REX ROAD  
EL PASO COUNTY, COLORADO**

Prepared for:

Tech Contractors  
3575 Kenyon Street, Suite 200  
San Diego, California 92110

Attn: Mr. Raul Guzman

April 20, 2022

Respectfully Submitted,

ENTECH ENGINEERING, INC.

Stuart Wood  
Geologist



Reviewed by:

Joseph C. Goode, Jr., P.E.  
President

DPS/drc

Encl.

Entech Job No. 220455  
AAprojects/2022/220455/220455 SSI

Table of Contents

1.0 INTRODUCTION ..... 2
2.0 PROJECT AND SITE DESCRIPTION ..... 3
3.0 SUBSURFACE EXPLORATIONS AND LABORATORY TESTING ..... 3
4.0 SUBSURFACE CONDITIONS ..... 4
4.1 Soil and Bedrock ..... 4
4.2 Groundwater ..... 6
5.0 PRELIMINARY DEVELOPMENT CONSIDERATIONS ..... 6
5.1 Groundwater ..... 6
5.2 Expansive Soils ..... 7
5.3 Sandstone and Claystone ..... 7
6.0 SITE GRADING ..... 7
6.1 Stripping ..... 8
6.2 Fill Preparation ..... 8
6.3 Compaction ..... 8
7.0 UNDERGROUND UTILITY CONSTRUCTION ..... 9
8.0 UNDERDRAIN SYSTEM ..... 9
9.0 PAVEMENT CONSIDERATIONS ..... 10
10.0 ANTICIPATED RESIDENTIAL FOUNDATION SYSTEMS ..... 10
11.0 RESIDENCE ON-GRADE FLOOR SLABS ..... 11
12.0 CONCRETE DEGRADATION DUE TO SULFATE ATTACK ..... 11
13.0 EXCAVATION STABILITY ..... 11
14.0 SURFACE AND SUBSURFACE DRAINAGE ..... 12
15.0 WINTER CONSTRUCTION ..... 12
16.0 CONSTRUCTION OBSERVATIONS ..... 12
17.0 CLOSURE ..... 13

Table

- Table 1: Summary of Laboratory Test Results
Table 2: Summary of Test Borings and Water Measurements

Figures

- Figure 1: Vicinity Map
Figure 2: Test Boring Location Plan
Figure 3: Cut/Fill Plan

List of Appendices

- Appendix A: Test Boring Logs
Appendix B: Laboratory Testing Results
Appendix C: Pavement Test Results

**SUBSURFACE SOIL INVESTIGATION  
MERIDIAN RANCH, ROLLING HILLS RANCH NORTH  
FILING NOS. 1 AND 2  
NORTH OF REX ROAD  
EL PASO COUNTY, COLORADO**

**1.0 INTRODUCTION**

The project consists of the development of the site for the construction of single-family residences in Rolling Hills Ranch North Filings 1 and 2. Development is expected to include site grading, installation of subsurface utilities, roadways, and drainage structures. The subdivision is in Meridian Ranch in the northern portion of El Paso County, Colorado. The approximate location of the project site is shown on the Vicinity Map, Figure 1. The test boring locations are shown on Figure 2, the Test Boring Location Plan. Test Boring locations were staked by the client.

This report describes the subsurface investigation conducted for the site and provides recommendations for development design and construction. The Subsurface Soil Investigation included the drilling of nineteen borings across the site, collecting samples of soil, and conducting a geotechnical evaluation of the investigation findings. All drilling and subsurface investigation activities were performed by Entech Engineering, Inc. (Entech). The contents of this report, including the geotechnical evaluation and recommendations, are subject to the limitations and assumptions presented in Section 17.0.

## **2.0 PROJECT AND SITE DESCRIPTION**

The project will consist of developing the site for single family residential structures. The planned lots are located in the Rolling Hills Ranch North subdivision in Meridian Ranch. The investigation was performed at predetermined locations based on the roadway alignment and proposed grading on the site plan provided to us. At the time of drilling, the site was vacant and not developed. The site has not been graded for the planned development. Site grading plans were provided to us with proposed cuts up to 21 feet and fills up to 12 feet. The majority of the cuts and fills are in the 2 to 8-foot range. Figure 3 shows the Cut/Fill Plan. Approximate finished grades are shown on the Test Boring Logs (Appendix A). The topography of the site is gently rolling hills and valleys with a general southeast-sloping trend. Vegetation consisted of grasses and weeds. Existing residences and proposed developments are located to the west and southwest of the site, undeveloped land lies immediately north, south, and east and Eastonville Road to the east. Natural earthen drainage trends to the southeast with one primary north/south drainage traversing the property near the center.

## **3.0 SUBSURFACE EXPLORATIONS AND LABORATORY TESTING**

Subsurface conditions on the site were explored by drilling nineteen test borings at the approximate locations shown on Figure 2. The boring locations were determined and staked by others. The borings were drilled within the proposed roadway alignments. The borings were drilled to depths of 20 to 30 feet below the existing ground surface (bgs). The drilling was performed using a truck-mounted, continuous flight auger-drilling rig supplied and operated by Entech. Boring logs descriptive of the subsurface conditions encountered during drilling are presented in Appendix A. At the conclusion and subsequent to drilling, observations for groundwater levels were made in each of the open boreholes.

Soil and bedrock samples were obtained from the borings utilizing the Standard Penetration Test (ASTM D-1586) using 2-inch O.D. split-barrel and California samplers. Results of the Standard Penetration Test (SPT) are included on the boring logs in terms of N-values expressed in blows per foot (bpf). Soil and bedrock samples recovered from the borings were visually classified and recorded on the boring logs. The soil and bedrock classifications were later verified utilizing laboratory testing and grouped by soil type. The soil and bedrock type



numbers are included on the boring logs. It should be understood that the soil and bedrock descriptions shown on the boring logs may vary between boring location and sample depth. It should also be noted that the lines of stratigraphic separation shown on the boring logs represent approximate boundaries between soil and bedrock types and the actual stratigraphic transitions may be more gradual or variable with location.

Water content testing (ASTM D-2216) was performed on the samples recovered from the borings, and the results are shown on the boring logs. Grain-Size Analysis (ASTM D-422) and Atterberg Limits testing (ASTM D-4318) were performed on selected samples to assist in classifying the materials encountered in the borings. Volume change testing was performed on selected samples using the Swell/Consolidation Test (ASTM D-4546) in order to evaluate potential expansion/compression characteristics of the soil and bedrock. Soluble sulfate testing was performed on select soil samples to evaluate the potential for below grade degradation of concrete due to sulfate attack. The Laboratory Testing Results are summarized on Table 1 and are presented in Appendix B.

#### **4.0 SUBSURFACE CONDITIONS**

Two soil types and two bedrock types were encountered in the test borings drilled for the subsurface investigation: Type 1: native silty to clayey to very clayey sand (SM, SC), Type 2: native sandy clay (CL), Type 3: slightly silty to silty to very clayey sandstone (SM-SW, SM, SC), and Type 4: sandy to very sandy claystone (CL). The soil and bedrock were classified in accordance with the Unified Soil Classification System (USCS) and American Association of State Highway and Transportation Officials (AASHTO) System using the laboratory testing results and the observations made during drilling.

##### **4.1 Soil and Bedrock**

Soil Type 1 classified as native silty to clayey to very clayey sand (SM, SC). The sand was encountered in all of the test borings at the existing ground surface and extending to depth ranging from 1 to 4 feet below ground surface (bgs). Standard Penetration Testing conducted on the sand resulted in SPT N-values ranging from 27 to 47 blows per foot (bpf), indicating medium dense to dense states. Water content and grain size testing of selected soil samples

resulted in a water content range of 2 to 9 percent, and 40 percent of the soil particles passing the No. 200 sieve. Atterberg limits testing on a sample of very clayey sand resulted in a Liquid Limit of 40 and a Plastic Index of 27. Swell/Consolidation testing on a sample of very clayey sand resulted in a volume change of 0.2 percent, indicating a low expansion potential. Sulfate testing resulted in less than 0.01 percent soluble sulfate by weight, which indicates a negligible potential for below grade concrete degradation due to sulfate attack.

Soil Type 2 classified as native sandy clay (CL). The clay was encountered in Test Boring Nos. 2 and 11 at the surface and extending to 3 and 4 feet bgs. Standard Penetration Testing conducted on the clay resulted in SPT N-values from 26 and 31, which indicates stiff consistencies. Water content and grain size testing resulted in a water content of 12 percent, and 83 to 90.5 percent of the soil particles passing the No. 200 sieve. Atterberg Limits testing resulted in Liquid Limit of 31 and a Plastic Index of 17. Swell/Consolidation testing on the clay resulted in volume changes of +1.0 to -1.1 percent, indicating low to moderate consolidation and expansion potential.

Soil Type 3 classified as slightly silty to silty to very clayey sandstone bedrock (SM-SW, SM, SC). The sandstone was encountered in all the test borings below the Type 1 and 2 soils, at 1 to 9 feet bgs and extending to various depths or to termination of borings (20 to 30 feet). Standard Penetration Testing conducted on the sandstone resulted in SPT N-values of 38 to greater than 50 bpf, which indicates dense to very dense states. Water content and grain size testing resulted in a water content range of 1 to 12, and 7 to 49 percent the soil size particles passing the No. 200 sieve. Atterberg limits testing on a sample of the slightly silty sandstone resulted in no values. Swell/Consolidation testing on the sandstone resulted in volume changes of -0.1 to -0.3 percent, indicating a low consolidation and expansion potential.

Soil Type 4 classified as a sandy to very sandy claystone (CL). The claystone was encountered below the surficial soils or interbedded in the sandstone at varying depths. Standard Penetration Testing on the claystone resulted in greater than 50 bpf, indicating hard consistencies. Water content and grain size testing resulted in 8 to 15 percent water content with 51 to 81 percent of soil size particles passing the No. 200 sieve. Atterberg limits testing resulted in liquid limits of 36 to 42 percent and plastic indexes of 19 to 22 percent. Swell/Consolidation testing of random

claystone samples resulted in volume changes of -1.1 to +0.1, indicating a low to moderate consolidation potential and a low expansion potential. Sulfate testing indicated a negligible degradation potential due to sulfate attack.

#### **4.2 Groundwater**

Depth to groundwater was measured in each of the borings at the conclusion of drilling and subsequent to drilling. Groundwater was encountered in two test borings subsequent to drilling, Test Boring Nos. 2 and 12 at a depth of approximately 17 feet. Groundwater should not affect building foundation excavations, roadway and utilities construction on this site. It should be noted that groundwater levels could change due to seasonal variations, changes in land runoff characteristics and future development including nearby areas. Shallow groundwater may also be encountered near drainages.

### **5.0 PRELIMINARY DEVELOPMENT CONSIDERATIONS**

*The following discussion is based on the subsurface conditions encountered in the test borings drilled at the site. This investigation is for the site discussed in 2.0 Project and Site Description. If subsurface conditions different from those described herein are encountered during construction or if the project elements change from those described, Entech Engineering, Inc. should be notified so that the evaluation and recommendations presented can be reviewed and revised if necessary.*

Subsurface soil conditions encountered in the test borings drilled on the site generally consisted of a thin layer of surficial sands or clay over sandstone and claystone bedrock. Bedrock was encountered at depths ranging from 1 to 9 feet bgs. Shallow bedrock (1 to 2 feet) was encountered in 13 of the test borings. Consideration should be given to several conditions on this site in planning and excavating the development including groundwater, expansive soils and sandstone/claystone materials.

#### **5.1 Groundwater**

Groundwater should not impact the development of this site. Subsequent to completion of overlot grading cuts per the grading plan presented to us, the groundwater table should be at

such a depth as to propose no threat to developing this site, unless deep utilities are required. Groundwater was measured in Test Boring Nos. 2 and 12 at a depth of approximately 17 feet. Shallow cut and fills are proposed in this area. Unstable conditions should be expected where groundwater is shallow or close to excavated depths. Procedures and equipment to mitigate groundwater impact during and after construction may be necessary. Pumps, cofferdams, wide area and localized drain systems and other procedures and equipment may be necessary. Shotrock and geotextiles may be appropriate for stabilizing excavations. An underdrain system can be considered for long term groundwater mitigation. Frequently, groundwater levels rise following development as result of increased irrigation and decreased potential area of evaporation.

## **5.2 Expansive Soils**

Expansive soils [clayey sand, claystone, and sandy clay] are present on the site exhibiting low to moderate potential for expansion and consolidation. These soils, where encountered, will require mitigation for residential construction. Damage to structures can occur due to expansive/ compressive soils; occurrence and severity of distress can be reduced by moisture treatments and overexcavation mitigation approaches.

## **5.3 Sandstone and Claystone**

Sandstone and claystone were encountered at shallow depths across the site. Excavation of sandstone and claystone should be expected to be moderate to difficult. Track type equipment likely will be needed to accomplish excavations particularly where harder materials or lenses are present. Upon completion of site grading per the plan provided to us, sandstone or claystone bedrock is expected to be exposed across the majority of the areas tested.

## **6.0 SITE GRADING**

Shallow bedrock was encountered in all of the test borings. Depth to bedrock in each boring is indicated on the Test Boring Plan, Figure 2. Excavation of dense and hard materials on site is expected to be moderate to difficult with heavy duty earthmoving equipment. Claystone and sandstone materials may require track equipment and ripping teeth. For conditions with no groundwater seepage, cut and fill slopes no steeper than 3 to 1 (horizontal to vertical) should be

considered. If seepage occurs, then flatter slopes or a drain system should be considered. Recommendations may be subject to change depending upon particular field conditions.

### **6.1 Stripping**

Debris, topsoil and organic materials should be stripped from the ground surface of areas to be filled. Any uncontrolled fill materials should be completely removed. The materials may be used as fill pending approval if they are free of organic material and debris. Although soft areas are not expected any soft or loose soils should be stabilized or removed to expose suitable material prior to placement of fill. Topsoil may be stored in stock piles and placed at the surface in landscape areas.

### **6.2 Fill Preparation**

Surfaces which will receive fill should be scarified to depths of 6 inches, moisture conditioned to within 0 to 3 percent of optimum moisture, and compacted to minimum of 95 percent of Standard Proctor Dry Density (ASTM D-698) for cohesive materials and within 2 percent of optimum moisture, and compacted to minimum of 95 percent of Modified Proctor Dry Density (ASTM D-1557) for cohesionless soils. On-site natural soils and bedrock are anticipated to be used as site grading fill. Bedrock must be processed and broken down to small gravel-sized materials, where placed in the fill. Expansive materials used for fill should be placed at sufficient moisture content to mitigate potential swell. The fill quality will influence the performance of foundations, slabs-on-grade, and pavements. Fill settlement can be minimized by placing thin lifts at suitable moisture content and by verification of compaction with frequent density tests.

### **6.3 Compaction**

Overlot grading fill consisting of granular soils should be placed in lifts to exceed 6 inches following compaction and compacted to at least 95 percent of the maximum dry density determined by Modified Proctor (ASTM D-1557). Clay materials should be placed in compacted lifts less than 6 inches thick compacted to at least 95 percent of maximum Standard Proctor (ASTM D 698) dry density. Fills below 10 feet in depth should be moisture conditioned as above and compacted to 98 percent of Standard Proctor dry density (ASTM D 698) for cohesive materials or 98 percent of maximum modified Proctor Dry Density (ASTM D 1557) for granular

materials. The soil materials should be placed at a moisture content conducive to adequate compaction, usually within  $\pm 2$  percent of optimum moisture content. Fill placement and compaction should be observed and tested by Entech during construction to verify that adequate moisture and density has been achieved.

## **7.0 UNDERGROUND UTILITY CONSTRUCTION**

Generally, excavation is expected to be moderate to difficult utilizing heavy-duty track hoes. Rock buckets and rock teeth will likely be required where excavations extend into very hard sandstone or cemented materials. Special procedures or equipment may be required to remove water and/or achieve stability in utility trenches, where excavations approach or intercept groundwater.

Utilities including water and sewer lines are usually constructed beneath paved roads. Placement of fill and degree of compaction applied to trench backfill will influence performance of overlying structures including pavements. Fill placed into utility trenches should be compacted according to requirements of the local jurisdiction. Fill should be placed in horizontal lifts having compacted thickness of six inches or less and at a water content conducive adequate compaction, usually within  $\pm 2$  percent of optimum water content. Typical compaction specifications would be similar to specifications in the Site Grading section. Mechanical methods should be used for fill placement; however, heavy equipment should be kept at a distance away from structures to avoid damage. No water flooding techniques of any type should be used for compaction or placement of utility trench backfill.

Trench backfill should be performed in accordance with El Paso County specifications and requirements. Excavations and excavation shoring/bracing should be performed in accordance with OSHA guidelines.

## **8.0 UNDERDRAIN SYSTEM**

Depending on final site grading anticipated depths of excavations and structure foundations relative to groundwater occurrence, an underdrain system may be considered to be included as part of sewer system design and installation. The underdrain system drain pipe shall consist of

smooth wall non perforated rigid PVC pipe typically placed at a slope to match the sanitary sewer system. Shallower pipe grades can be considered for larger diameter underdrain pipes and areas to daylight the drainage systems. Concrete or clay material fill may be strategically placed at the manhole locations to slow the water flow down the trench. The underdrain below sewer should be constructed with adequate depth to allow connection of residence foundation drain systems. Drain elements should be of appropriate slopes and sizes for anticipated flows. Maintenance of the underdrain system should be anticipated. Gravity outlet should be planned such that other developments and properties are not adversely affected.

## **9.0 PAVEMENT CONSIDERATIONS**

Materials exposed at pavement subgrade elevations will be dependent upon native materials exposed at final overlot grading and the specific materials placed as fill at and near finish grade elevations. The predominate materials are generally expected to be silty sand, sandstone, clayey sand, and clay. Materials anticipated at subgrade elevation generally would be rated as good, but some areas likely would be rated as poor AASHTO classifications of A-1-b, A-2-6, and A-4 were determined for the sandstone and upper granular soils. Based on depth to claystone and estimated cut, claystone with AASHTO classification of A-6 and associated poor rating is likely not to be encountered. The claystone classifies as A-6 which has poor asphalt support characteristics. Thickness of asphalt pavements to be anticipated generally range between 4 to 5 inches of asphalt overlying 6 to 10 inches of basecourse depending on specific subgrade materials and Roadway Classification of each particular street. Cement treated subgrade thickness of 10 to 12 inches are common. Actual thickness may exceed anticipated thickness at some areas. For specific thickness determinations, a subsurface investigation and pavement design should be completed after completion of overlot grading.

## **10.0 ANTICIPATED RESIDENTIAL FOUNDATION SYSTEMS**

Subsurface soil conditions consisted of areas of sandstone, expansive clayey soils and claystone materials. We anticipate conventional spread footing foundation systems will be appropriate for residences constructed on the majority of the site. Where expansive materials are encountered at or near foundation grades, use of spread footings with overexcavation and replacement with non-expansive fill should be expected. Drilled pier foundations may be a

suitable alternative where expansive soils are encountered. A Subsurface Soils Investigation report should be prepared after completion of overlot grading to address appropriate foundation systems. Perimeter below grade drain systems should be anticipated for all structures with basements. Shallow groundwater was not encountered in the Test Borings. Temporary and permanent dewatering systems may be necessary at various foundation excavations. Shotrock and geotextiles may be appropriate for stabilizing excavations. An area wide subdrain may be considered for discharge of collected water.

### **11.0 RESIDENCE ON-GRADE FLOOR SLABS**

On-grade floor slabs for the planned structures could be supported by on-site non-expansive soils or compacted, non-expansive, structural fill. Loose or expansive soils encountered at or near floor slab grade should be penetrated or overexcavated a distance below slab subgrade and replaced with a non-expansive structural fill to improve floor slab performance. If slab movement and cracks cannot be tolerated a structural floor system should be used. Evaluation of subgrade materials should be included within a Subsurface Soils Investigation for each specific lot.

### **12.0 CONCRETE DEGRADATION DUE TO SULFATE ATTACK**

Sulfate solubility testing was conducted on three samples recovered from the test borings to evaluate the potential for sulfate attack on concrete placed below surface grade. The test results indicated 0.00 to less than 0.01 percent soluble sulfate (by weight). The test results indicate the sulfate component of the in-place soils presents a negligible exposure threat to concrete placed below the site grade. Type II cement is recommended for the on-site soils. Additional testing should be conducted following completion of overlot grading.

### **13.0 EXCAVATION STABILITY**

Excavation walls must be properly sloped/benched or otherwise supported in order to maintain stable conditions. All excavation openings and work execution shall conform to OSHA standards as in CFR 29, Part 1926.650-652 (Subpart D).



## **14.0 SURFACE AND SUBSURFACE DRAINAGE**

Surface drainage will influence performance of structures at the site including streets and residences. Drainage is recommended around each building perimeter at a minimum slope of 5 percent in the first 10 feet adjacent to exterior foundation walls and for unpaved areas, where possible. For paved areas and other impervious surfaces, a minimum slope of 2 percent is recommended. Drainage should be planned to avoid ponding of water. Collected water and irrigation should discharge well beyond foundation backfill zones. Surface runoff should be designed to avoid sheet flow and erosion. Slopes should be protected from erosion by materials such as mulch or appropriate plants or other methods. All fills and backfills should be properly compacted. Unprotected surfaces may be subject to undesirable, heavy erosion.

## **15.0 WINTER CONSTRUCTION**

In the event construction occurs during winter, concrete and soil materials should be protected from freezing conditions. Concrete should not be placed on frozen soil and once concrete has been placed, it should not be allowed to freeze. Similarly, once exposed, the soil subgrades should not be allowed to freeze. During grading operations and subgrade preparation, care should be taken to avoid burial of snow, ice or frozen material within the planned construction area.

## **16.0 CONSTRUCTION OBSERVATIONS**

It is recommended that Entech observe and document the following activities during construction of the building foundations.

- Excavated subgrades and subgrade preparation.
- Placement of foundation perimeter drains (if installed).
- Placement/compaction of fill materials.
- Placement/compaction of utility bedding and trench backfill.

## **17.0 CLOSURE**

The subsurface investigation, geotechnical evaluation and preliminary recommendations presented in this report are intended for use by Tech Contractors with application to the planned development of the single-family residential project site located in the Rolling Hills Ranch North Subdivision, Filing Nos. 1 and 2 in Meridian Ranch in northern El Paso County, Colorado. In conducting the subsurface soil investigation, laboratory testing, engineering evaluation and reporting, Entech Engineering, Inc. endeavored to work in accordance with generally accepted professional geotechnical and geologic practices and principles consistent with the level of care and skill ordinarily exercised by members of the geotechnical profession currently practicing in same locality and under similar conditions. No other warranty, expressed or implied is made. Additional subsurface investigations and testing are recommended to further evaluate the individual sites and roadways after final development plans are prepared and after the site has been graded. During final design and/or construction, if conditions are encountered which appear different from those described in this report, Entech Engineering, Inc. requests that it be notified so that the evaluation and recommendations presented herein can be reviewed and modified as appropriate.

If there are any questions regarding the information provided herein or if Entech Engineering, Inc. can be of further assistance, please do not hesitate to contact us.

## TABLE

**TABLE 1**  
**SUMMARY OF LABORATORY TEST RESULTS**

CLIENT   TECH CONTRACTORS  
PROJECT   ROLLING HILLS NORTH  
JOB NO.   220455

SOIL TYPE	TEST BORING NO.	DEPTH (FT)	WATER (%)	DRY DENSITY (PCF)	PASSING NO. 200 SIEVE (%)	LIQUID LIMIT (%)	PLASTIC INDEX (%)	SULFATE (WT %)	FHA SWELL (PSF)	SWELL/ CONSOL (%)	UNIFIED CLASSIFICATION	SOIL DESCRIPTION
1	8	2-3	10.1	111.3	40.2	43	27	<0.01		0.2	SC	SAND, VERY CLAYEY
2	11	2-3	13.0	99.5	90.5					1.0	CL	CLAY, SANDY
2	15	5	9.2	111.9	83.3	31	17			-1.1	CL	CLAY, SANDY
3	11	15			13.0						SM	SANDSTONE, SILTY
3	16	5			35.2						SC	SANDSTONE, CLAYEY
3	4	5			6.9	NV	NP				SM-SW	SANDSTONE, SLIGHTLY SILTY
3	5	2-3			20.8						SM	SANDSTONE, SILTY
3	9	10			8.6						SM-SW	SANDSTONE, SLIGHTLY SILTY
3	10	2-3			17.4						SM	SANDSTONE, SILTY
3	12	20	10.5	117.9	47.9					-0.1	SC	SANDSTONE, VERY CLAYEY
3	13	10			13.9						SM	SANDSTONE, SILTY
3	14	5			26.8						SM	SANDSTONE, SILTY
3	18	20			49.0						SC	SANDSTONE, VERY CLAYEY
3	19	15	11.4	120.9	32.8					-0.3	SC	SANDSTONE, CLAYEY
4	1	15			67.4	36	19	0.00			CL	CLAYSTONE, SANDY
4	2	5			78.6	42	22	0.00			CL	CLAYSTONE, SANDY
4	3	10	12.6	114.6	80.0					0.1	CL	CLAYSTONE, SANDY
4	4	20	14.6	111.6	51.3					-0.4	CL	CLAYSTONE, VERY SANDY
4	6	10	13.1	121.5	81.5					0.1	CL	CLAYSTONE, SANDY
4	7	5	11.7	121.5	75.5					0.8	CL	CLAYSTONE, SANDY
4	17	10	12.5	106.7	74.6					-1.1	CL	CLAYSTONE, SANDY

## FIGURES



**SITE**

Rex Rd

Hotred Joe's reds and customs

Sunrise Ridge Dr

Rolling Peaks Dr

Rex Rd

Rolling Peaks Dr

Rolling Peaks Dr

Rex Rd

Alebra Peak Dr

Rainbow Bridge Dr

Silver Peak Dr

Google



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5299

VICINITY MAP  
ROLLING HILLS NORTH  
COLORADO SPRINGS, CO  
For: TECH CONTRACTORS

DRAWN:  
JAC



DATE:  
04/08/22

CHECKED:  
DPS

DATE:

JOB NO.:  
220455

FIG NO.:  
1



**TB- APPROXIMATE TEST BORING LOCATIONS AND NUMBERS (DEPTH TO BEDROCK)**

REVISION	BY

**ENTTECH**  
ENGINEERING, INC.  
305 ELKTON DRIVE  
COLORADO SPRINGS, CO 80907  
(719) 531-5599

TEST BORING LOCATION MAP  
ROLLING HILLS NORTH  
COLORADO SPRINGS, CO  
For: TECH CONTRACTORS

DATE	04/08/22
DRAWN BY	JAC
CHECKED BY	DPB
SCALE	1:300
PROJECT NO.	220455
ISSUE NO.	1
TOTAL SHEETS	2


REVISION	BY

**ENTTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599



CUT & FILL MAP  
ROLLING HILLS NORTH  
COLORADO SPRINGS, CO  
For: TECH CONTRACTORS

DRWN	JAC
CHECKED	DPS
DATE	04/08/22
SCALE	1:300
JOB NO.	220466
FIGURE NO.	3



◆ TB- APPROXIMATE TEST BORING LOCATIONS AND NUMBERS (DEPTH TO BEDROCK)



## **APPENDIX A: Test Boring Logs**

TEST BORING NO. 1  
 DATE DRILLED 3/8/2022  
 Job # 220455

TEST BORING NO. 2  
 DATE DRILLED 3/8/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS

DRY TO 20', 3/22/22  
 SAND, SILTY, BROWN

SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, DENSE  
 TO VERY DENSE, MOIST GRADE

CLAYSTONE, SANDY, GRAY  
 BROWN, HARD, MOIST  
 SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, VERY  
 DENSE, MOIST

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
0					1
5			42	3.6	3
			50	4.4	3
			5"		
10			50	8.4	3
			5"		
15			50	13.7	4
			6"		
20			50	12.3	3
			5"		

REMARKS

WATER @ 17', 3/22/22  
 CLAY, SANDY, TAN, STIFF,  
 MOIST

CLAYSTONE, SANDY, GRAY  
 BROWN, HARD, MOIST

SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, VERY  
 DENSE, MOIST

>4'  
 FILL



Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
0					
5			26	10.5	2
			50	10.1	4
			6"		
10			50	11.6	4
			6"		
15			50	8.4	3
			7"		
20			50	11.2	3
			7"		



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED:

DATE:

SW

4-12-22

JOB NO.:  
 220455

FIG NO.:  
 A- 1

TEST BORING NO. 3  
 DATE DRILLED 3/14/2022  
 Job # 220455

TEST BORING NO. 4  
 DATE DRILLED 3/11/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
	>4' FILL					
DRY TO 20', 3/22/22						
SAND, SILTY, BROWN	1	1				1
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, DRY TO MOIST	5			50 11" 50 8"	2.4 4.8	3 3
CLAYSTONE, SANDY, BROWN, HARD, MOIST	10			50 6"	11.4	4
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, DRY TO MOIST	15			50 5"	2.9	3
	20			50 6"	7.1	3

REMARKS

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 30', 3/22/22						
SAND, SILTY, BROWN	1	1				1
SANDSTONE, SLIGHTLY SILTY TO SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, DRY TO MOIST	5			50 8" 50 8"	1.3 2.6	3 3
	10			50 6"	7.6	3
	15			50 7"	9.3	3
	20			50 6"	11.0	4
CLAYSTONE, VERY SANDY, GRAY BROWN, HARD, MOIST	25			50 5"	12.0	3
SANDSTONE, SILTY, FINE TO COARSE GRAINED, GRAY BROWN, VERY DENSE, MOIST	30			50 3"	8.0	3



**ENTECH**  
 ENGINEERING, INC.

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED: SW

DATE: 4-12-22

JOB NO.: 220455

FIG NO.: A-2

TEST BORING NO. 5  
 DATE DRILLED 3/14/2022  
 Job # 220455

TEST BORING NO. 6  
 DATE DRILLED 3/11/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS

DRY TO 25', 3/22/22

SAND, SILTY, BROWN  
 SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, VERY  
 DENSE, DRY TO MOIST

GRADE

CLAYSTONE, SANDY, BROWN,  
 HARD, MOIST

SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, VERY  
 DENSE, MOIST

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
1	1-1				1
3			50 6"	1.5	3
5			50 3"	2.0	3
10			50 6"	6.1	3
15			50 6"	7.4	3
20			50 6"	13.1	4
25			50 6"	7.4	3

REMARKS

DRY TO 30', 3/22/22

SAND, SILTY, BROWN  
 SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, VERY  
 DENSE, DRY TO MOIST

CLAYSTONE, SANDY, BROWN,  
 HARD, MOIST

SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, TAN, VERY  
 DENSE, MOIST

GRADE

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
1	1-1				1
3			50	2.8	3
5			50 11"	12.0	3
10			50 6"	15.1	4
15			50 5"	9.1	3
20			50 6"	7.7	3
25			50 4"	6.6	3
30			50 5"	10.8	3



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED: *SW*

DATE: *4-12-22*

JOB NO:  
 220455

FIG NO:  
 A-3

TEST BORING NO. 7  
 DATE DRILLED 3/14/2022  
 Job # 220455

TEST BORING NO. 8  
 DATE DRILLED 3/8/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
	>4'												
FILL													
DRY TO 20', 3/22/22							DRY TO 20', 3/22/22						
CLAY, SANDY, TAN, VERY STIFF, MOIST				31	8.9	2	SAND, VERY CLAYEY, FINE TO MEDIUM GRAINED, TAN, MEDIUM DENSE, MOIST				26	9.4	1
							GRADE						
CLAYSTONE, SANDY, GRAY BROWN, HARD, MOIST	5		50 7"	15.6		4	SANDSTONE, SILTY, FINE TO COARSE GRAINED, DARK BROWN TO TAN, VERY DENSE, MOIST	5		50 6"	6.2		3
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	10		50 4"	6.4		3		10		50 6"	8.6		3
				*	7.0	3							
CLAYSTONE, SANDY, GRAY BROWN, HARD, MOIST	15		50 8"	12.6		4		15		50 7"	7.0		3
* - BULK SAMPLE TAKEN	20		50 5"	12.0		4		20		50 5"	9.1		3



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**TEST BORING LOG**

DRAWN:

DATE:

CHECKED:

DATE:

SW 4-12-22

JOB NO.:  
 220455

FIG NO.:  
 A- 4

TEST BORING NO. 9  
 DATE DRILLED 3/9/2022  
 Job # 220455

TEST BORING NO. 10  
 DATE DRILLED 3/9/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 20', 3/22/22							DRY TO 20', 3/22/22						
SAND, SILTY, BROWN						1	SAND, SILTY, BROWN						1
SANDSTONE, SLIGHTLY SILTY						3	SANDSTONE, SLIGHTLY SILTY						3
TO SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	5	GRADE		50	2.8	3	TO SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	5	GRADE		50	4.7	3
				8"	5.6	3					9"	4.4	3
	10			50	5.1	3		10			50	5.0	3
				7"							5"		
	15			50	10.1	3	CLAYSTONE, SANDY, GRAY BROWN, HARD, MOIST	15			50	12.2	4
				6"							6"		
	20			50	8.3	3	SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	20			50	8.7	3
				5"							7"		



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**TEST BORING LOG**

DRAWN:

DATE:

CHECKED: *SW*

DATE: *4-12-22*

JOB NO:  
 220455

FIG NO:  
 A- 5

TEST BORING NO. 11  
 DATE DRILLED 3/9/2022  
 Job # 220455

TEST BORING NO. 12  
 DATE DRILLED 3/9/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS						REMARKS					
Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 20', 3/22/22						WATER @ 16.5' 3/22/22					
CLAY, SANDY, TAN, VERY STIFF, MOIST			31	12.0	2	SAND, SILTY, FINE TO COARSE GRAINED, TAN, DENSE, DRY			47	2.2	1
			50	8.1	3				50	7.5	3
			5"						8"		
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST			50	9.1	3	SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST			50	9.6	3
			6"						7"		
			50	7.8	3				50	7.2	3
			6"						7"		
			50	7.1	3				50	10.2	3
			5"			SANDSTONE, VERY CLAYEY, FINE GRAINED, TAN, VERY DENSE, MOIST			6"		
									50	10.2	3
									6"		

GRADE

GRADE



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED: SW

DATE: 4-12-22

JOB NO.: 220455

FIG NO.: A-6

TEST BORING NO. 13  
 DATE DRILLED 3/14/2022  
 Job # 220455

TEST BORING NO. 14  
 DATE DRILLED 3/11/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS

DRY TO 20', 3/22/22

SAND, SILTY, BROWN  
 SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, BROWN,  
 VERY DENSE, DRY TO MOIST

GRADE

CLAYSTONE, SANDY, GRAY  
 BROWN, HARD, MOIST

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
1	1				1
3			50 9"	2.7	3
5			50 9"	7.7	3
10			50 8"	10.0	3
15			50 4"	10.0	4
20			50 4"	11.5	4

REMARKS

>6'  
FILL

DRY TO 20', 3/22/22

SAND, SILTY, BROWN  
 SANDSTONE, SILTY, FINE TO  
 COARSE GRAINED, BROWN,  
 VERY DENSE, DRY TO MOIST

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
1	1				1
3			50 6"	2.2	3
5			50 5"	6.3	3
10			50 6"	6.1	3
15			50 6"	6.7	3
20			50 6"	6.9	3



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED: SW

DATE: 4-12-22

JOB NO. 220455

FIG NO. A-7



TEST BORING NO. 15  
 DATE DRILLED 3/11/2022  
 Job # 220455

TEST BORING NO. 16  
 DATE DRILLED 3/10/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
>4' FILL						
DRY TO 20', 3/22/22						
SAND, SILTY, FINE TO COARSE GRAINED, TAN, DENSE, MOIST				37	3.9	1
CLAY, SANDY, TAN, STIFF, MOIST	5			28	17.2	2
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	10			50 6"	11.0	3
	15			50 5"	5.2	3
	20			50 4"	6.2	3

REMARKS

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
>4' FILL						
DRY TO 20', 3/22/22						
SAND, SILTY, BROWN SANDSTONE, CLAYEY, FINE TO COARSE GRAINED, BROWN, VERY DENSE, MOIST	1			50 8"	4.9	3
	5			50 6"	8.8	3
	10			50 8"	8.6	3
	15			50 7"	9.5	3
	20			50 7"	9.5	3



**ENTECH**  
**ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN: DATE: CHECKED: DATE: 3/12/22

JOB NO.: 220455

FIG NO.: A- 8

TEST BORING NO. 17  
 DATE DRILLED 3/10/2022  
 Job # 220455

TEST BORING NO. 18  
 DATE DRILLED 3/9/2022  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 20', 3/22/22							DRY TO 20', 3/22/22 GRADE						
SAND, SILTY, BROWN	1	1				1	SAND, SILTY, BROWN	1	1				1
SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	5			50	6.5	3	SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, VERY DENSE, MOIST	5			50	3.9	3
				8"							8"		
				50	6.8	3					50	8.3	3
				6"							6"		
CLAYSTONE, SANDY, GRAY BROWN, HARD, MOIST	10			50	11.9	4	CLAYSTONE, SANDY, GRAY BROWN, HARD, MOIST	10			50	14.2	4
				6"							8"		
	15			50	11.4	4	SANDSTONE, VERY CLAYEY, FINE TO MEDIUM GRAINED, BROWN, VERY DENSE, MOIST	15			50	6.1	3
				5"							5"		
	20			50	7.8	4		20			50	8.2	3
				5"							1"		



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**TEST BORING LOG**

DRAWN:

DATE:

CHECKED: SW

DATE: 4-12-22

JOB NO.:  
 220455

FIG NO.:  
 A- 9

TEST BORING NO. 19  
 DATE DRILLED 3/9/2022  
 Job # 220455

TEST BORING NO.  
 DATE DRILLED  
 CLIENT TECH CONTRACTORS  
 LOCATION ROLLING HILLS NORTH

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type	REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 20', 3/22/22													
SAND, SILTY, BROWN WEATHERED TO FORMATIONAL SANDSTONE, SILTY, FINE TO COARSE GRAINED, TAN, DENSE TO VERY DENSE, MOIST	1 5			38 50 6"	7.2 5.8	3 3		5					
	10			50 7"	8.2	3		10					
SANDSTONE, CLAYEY, FINE TO MEDIUM GRAINED, GRAY BROWN, VERY DENSE, MOIST	15			50	18.7	3		15					
	20			50 1"	8.1	3		20					

GRADE



**ENTECH**  
 ENGINEERING, INC.

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG


DRAWN: DATE: CHECKED: SW DATE: 4-12-22

JOB NO:  
 220455

FIG NO:  
 A- 10

## **APPENDIX B: Laboratory Testing Results**

<b>UNIFIED CLASSIFICATION</b>	SC	<b>CLIENT</b>	TECH CONTRACTORS
<b>SOIL TYPE #</b>	1	<b>PROJECT</b>	ROLLING HILLS NORTH
<b>TEST BORING #</b>	8	<b>JOB NO.</b>	220455
<b>DEPTH (FT)</b>	2-3	<b>TEST BY</b>	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	95.9%
20	86.2%
40	73.6%
100	50.2%
200	40.2%

Atterberg Limits	
Plastic Limit	16
Liquid Limit	43
Plastic Index	27
Swell	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	




**ENTECH ENGINEERING, INC.**  
505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------

JOB NO.: 220455  
FIG NO.: *B-1*

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	2	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	11	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	2-3	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	
10	
20	100.0%
40	99.8%
100	98.9%
200	90.5%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED: *SW*

DATE:


*3-25-22*

JOB NO.:  
220455

FIG NO.:

*B-2*

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	2	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	15	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	5	<u>TEST BY</u>	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	
10	
20	100.0%
40	98.3%
100	96.8%
200	83.3%

Atterberg Limits	
Plastic Limit	14
Liquid Limit	31
Plastic Index	17

Swell	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH  
ENGINEERING, INC.**  
505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------


JOB NO.:  
220455

FIG NO.:  
*8-3*

**UNIFIED CLASSIFICATION** SM  
**SOIL TYPE #** 3  
**TEST BORING #** 11  
**DEPTH (FT)** 15

**CLIENT** TECH CONTRACTORS  
**PROJECT** ROLLING HILLS NORTH  
**JOB NO.** 220455  
**TEST BY** BL

**Sieve Analysis  
Grain Size Distribution**



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	100.0%
3/8"	82.9%
4	68.8%
10	46.7%
20	30.3%
40	22.8%
100	15.5%
200	13.0%

**Atterberg Limits**  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

**Swell**  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH**  
**ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**


DRAWN:	DATE:	CHECKED: SW	DATE: 3-25-22
--------	-------	-------------	---------------

JOB NO.:  
220455

FIG NO.:  
B-4



UNIFIED CLASSIFICATION	SC	CLIENT	TECH CONTRACTORS
SOIL TYPE #	3	PROJECT	ROLLING HILLS NORTH
TEST BORING #	16	JOB NO.	220455
DEPTH (FT)	5	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	100.0%
3/8"	97.4%
4	92.1%
10	82.0%
20	71.0%
40	61.4%
100	43.3%
200	35.2%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**


DRAWN:	DATE:	CHECKED: SW	DATE: 3-25-22
--------	-------	-------------	---------------

JOB NO.:  
220455

FIG NO.:  
B-5

<b>UNIFIED CLASSIFICATION</b>	SM-SW	<b>CLIENT</b>	TECH CONTRACTORS
<b>SOIL TYPE #</b>	3	<b>PROJECT</b>	ROLLING HILLS NORTH
<b>TEST BORING #</b>	4	<b>JOB NO.</b>	220455
<b>DEPTH (FT)</b>	5	<b>TEST BY</b>	BL

**Sieve Analysis  
Grain Size Distribution**



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	100.0%
3/8"	97.4%
4	86.1%
10	54.1%
20	29.3%
40	18.5%
100	9.6%
200	6.9%

Atterberg Limits	
Plastic Limit	NP
Liquid Limit	NV
Plastic Index	NP

Swell	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80807


**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------

JOB NO.:  
220455

FIG NO.:  
*B-6*

<b>UNIFIED CLASSIFICATION</b>	SM	<b>CLIENT</b>	TECH CONTRACTORS
<b>SOIL TYPE #</b>	3	<b>PROJECT</b>	ROLLING HILLS NORTH
<b>TEST BORING #</b>	5	<b>JOB NO.</b>	220455
<b>DEPTH (FT)</b>	2-3	<b>TEST BY</b>	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	95.1%
10	69.6%
20	48.7%
40	38.9%
100	27.0%
200	20.8%

**Atterberg Limits**  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

**Swell**  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------

JOB NO.:  
220455

FIG NO.:  
**B-7**

<u>UNIFIED CLASSIFICATION</u>	SM-SW	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	3	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	9	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	10	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	91.1%
10	77.7%
20	56.2%
40	36.1%
100	12.9%
200	8.6%

- Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index
- Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)




**ENTECH ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------

JOB NO.: 220455  
 FIG NO.: *B-8*

<b>UNIFIED CLASSIFICATION</b>	SM	<b>CLIENT</b>	TECH CONTRACTORS
<b>SOIL TYPE #</b>	3	<b>PROJECT</b>	ROLLING HILLS NORTH
<b>TEST BORING #</b>	10	<b>JOB NO.</b>	220455
<b>DEPTH (FT)</b>	2-3	<b>TEST BY</b>	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	100.0%
3/8"	97.4%
4	92.0%
10	69.1%
20	41.1%
40	29.2%
100	20.7%
200	17.4%

**Atterberg Limits**  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

**Swell**  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED: *SW*


DATE:

*3-25-22*

JOB NO.:  
220455

FIG NO.:  
*B-9*

<u>UNIFIED CLASSIFICATION</u>	SC	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	3	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	12	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	20	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	91.2%
20	76.8%
40	66.0%
100	54.6%
200	47.9%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**


<u>DRAWN:</u>	<u>DATE:</u>	<u>CHECKED:</u> SW	<u>DATE:</u> 3-25-22
---------------	--------------	-----------------------	-------------------------

JOB NO.:  
220455

FIG NO.:  
B-10

<u>UNIFIED CLASSIFICATION</u>	SM	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	3	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	13	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	10	<u>TEST BY</u>	BL

**Sieve Analysis  
Grain Size Distribution**



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	95.0%
10	67.1%
20	37.0%
40	27.5%
100	17.2%
200	13.9%

- Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index
- Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH**  
**ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST  
RESULTS**

<u>DRAWN:</u>	<u>DATE:</u>	<u>CHECKED:</u> SW	<u>DATE:</u> 3-25-22
---------------	--------------	--------------------	----------------------

JOB NO.:  
220455

FIG NO.:  
B-11

UNIFIED CLASSIFICATION	SM	CLIENT	TECH CONTRACTORS
SOIL TYPE #	3	PROJECT	ROLLING HILLS NORTH
TEST BORING #	14	JOB NO.	220455
DEPTH (FT)	5	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	99.5%
10	86.5%
20	65.5%
40	51.6%
100	32.8%
200	26.8%

- Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index
- Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------

JOB NO.: 220455  
 FIG NO.: *B-12*



UNIFIED CLASSIFICATION	SC	CLIENT	TECH CONTRACTORS
SOIL TYPE #	3	PROJECT	ROLLING HILLS NORTH
TEST BORING #	18	JOB NO.	220455
DEPTH (FT)	20	TEST BY	BL



U.S. Sieve #	Percent Finer	Atterberg Limits
3"		Plastic Limit
1 1/2"		Liquid Limit
3/4"		Plastic Index
1/2"		
3/8"		
4	100.0%	<u>Swell</u>
10	96.4%	Moisture at start
20	84.8%	Moisture at finish
40	74.1%	Moisture increase
100	57.9%	Initial dry density (pcf)
200	49.0%	Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED:

SW

DATE:


3-25-22

JOB NO.:  
220455

FIG NO.:

B-13

UNIFIED CLASSIFICATION	SC	CLIENT	TECH CONTRACTORS
SOIL TYPE #	3	PROJECT	ROLLING HILLS NORTH
TEST BORING #	19	JOB NO.	220455
DEPTH (FT)	15	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	94.9%
10	68.9%
20	49.1%
40	42.0%
100	36.0%
200	32.8%

- Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index
- Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-22-25</i>
--------	-------	--------------------	----------------------

JOB NO.:  
220455

FIG NO.:  
*B-14*

<b>UNIFIED CLASSIFICATION</b>	CL	<b>CLIENT</b>	TECH CONTRACTORS
<b>SOIL TYPE #</b>	4	<b>PROJECT</b>	ROLLING HILLS NORTH
<b>TEST BORING #</b>	1	<b>JOB NO.</b>	220455
<b>DEPTH (FT)</b>	15	<b>TEST BY</b>	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	99.2%
10	95.5%
20	94.2%
40	93.4%
100	81.5%
200	67.4%

Atterberg Limits	
Plastic Limit	17
Liquid Limit	36
Plastic Index	19

Swell	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED:

SW

DATE:


3-25-22

JOB NO.:  
220455

FIG NO.:

B-15

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	4	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	2	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	5	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	98.8%
20	96.9%
40	94.9%
100	88.6%
200	78.6%

<u>Atterberg Limits</u>	
Plastic Limit	20
Liquid Limit	42
Plastic Index	22

<u>Swell</u>	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST  
RESULTS**

<u>DRAWN:</u>	<u>DATE:</u>	<u>CHECKED:</u> <i>SW</i>	<u>DATE:</u> <i>3-25-22</i>
---------------	--------------	---------------------------	-----------------------------

JOB NO.:  
220455

FIG NO.:  
*B-16*

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	4	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	3	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	10	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	98.3%
20	96.1%
40	94.7%
100	90.5%
200	80.0%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED: *SW*


DATE:

*3-25-22*

JOB NO.:  
220455

FIG NO.:  
*B-17*

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	4	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	4	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	20	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	94.5%
20	85.6%
40	76.8%
100	59.9%
200	51.3%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST  
RESULTS**

<u>DRAWN:</u>	<u>DATE:</u>	<u>CHECKED:</u> SW	<u>DATE:</u> 3-25-22
---------------	--------------	--------------------	----------------------

JOB NO.:  
220455

FIG NO.:  
B-18

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	4	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	6	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	10	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	99.2%
20	96.9%
40	94.6%
100	88.0%
200	81.5%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED: *SW*

DATE:


*3-25-22*

JOB NO.:  
220455

FIG NO.:

*B-19*

<u>UNIFIED CLASSIFICATION</u>	CL	<u>CLIENT</u>	TECH CONTRACTORS
<u>SOIL TYPE #</u>	4	<u>PROJECT</u>	ROLLING HILLS NORTH
<u>TEST BORING #</u>	7	<u>JOB NO.</u>	220455
<u>DEPTH (FT)</u>	5	<u>TEST BY</u>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	97.4%
20	92.8%
40	89.5%
100	82.6%
200	75.5%

Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index

Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:

DATE:

CHECKED: *SW*

DATE:


*3-25-22*

JOB NO.:  
220455

FIG NO.:  
*B-2D*



<b>UNIFIED CLASSIFICATION</b>	CL	<b>CLIENT</b>	TECH CONTRACTORS
<b>SOIL TYPE #</b>	4	<b>PROJECT</b>	ROLLING HILLS NORTH
<b>TEST BORING #</b>	17	<b>JOB NO.</b>	220455
<b>DEPTH (FT)</b>	10	<b>TEST BY</b>	BL



<u>U.S. Sieve #</u>	<u>Percent Finer</u>
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	
4	100.0%
10	97.2%
20	93.8%
40	91.1%
100	81.4%
200	74.6%

- Atterberg Limits  
 Plastic Limit  
 Liquid Limit  
 Plastic Index
- Swell  
 Moisture at start  
 Moisture at finish  
 Moisture increase  
 Initial dry density (pcf)  
 Swell (psf)



**ENTECH  
ENGINEERING, INC.**  
 505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED: <i>SW</i>	DATE: <i>3-25-22</i>
--------	-------	--------------------	----------------------


JOB NO.:  
220455

FIG NO.:  
*B-21*

**CONSOLIDATION TEST RESULTS**

TEST BORING #	8	DEPTH(ft)	2-3
DESCRIPTION	SC	SOIL TYPE	1
NATURAL UNIT DRY WEIGHT (PCF)			111
NATURAL MOISTURE CONTENT			10.1%
SWELL/CONSOLIDATION (%)			0.2%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

SWELL CONSOLIDATION  
 TEST RESULTS

DRAWN:

DATE:

CHECKED:

SW

DATE:

3-25-22


JOB NO.:  
220455

FIG NO.:  
B-22

**CONSOLIDATION TEST RESULTS**

TEST BORING #	11	DEPTH(ft)	2-3
DESCRIPTION	CL	SOIL TYPE	2
NATURAL UNIT DRY WEIGHT (PCF)	99		
NATURAL MOISTURE CONTENT	13.0%		
SWELL/CONSOLIDATION (%)	1.0%		

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
TEST RESULTS**

DRAWN:

DATE:

CHECKED:

SW

DATE:

3-25-22


JOB NO.:  
220455

FIG NO.:  
B-23

**CONSOLIDATION TEST RESULTS**

TEST BORING #	15	DEPTH(ft)	5
DESCRIPTION	CL	SOIL TYPE	2
NATURAL UNIT DRY WEIGHT (PCF)			112
NATURAL MOISTURE CONTENT			9.2%
SWELL/CONSOLIDATION (%)			-1.1%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
 ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
 TEST RESULTS**

DRAWN:

DATE:

CHECKED:

SW

DATE:

3-25-22


JOB NO:  
 220455

FIG NO:  
 B-24

**CONSOLIDATION TEST RESULTS**

TEST BORING #	12	DEPTH(ft)	20
DESCRIPTION	SC	SOIL TYPE	3
NATURAL UNIT DRY WEIGHT (PCF)			118
NATURAL MOISTURE CONTENT			10.5%
SWELL/CONSOLIDATION (%)			-0.1%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
 TEST RESULTS**

DRAWN:

DATE:

CHECKED:  
*SW*

DATE:  
 3-25-22


JOB NO.:  
 220455

FIG NO.:  
 B-25

**CONSOLIDATION TEST RESULTS**

TEST BORING #	19	DEPTH(ft)	15
DESCRIPTION	SC	SOIL TYPE	3
NATURAL UNIT DRY WEIGHT (PCF)			121
NATURAL MOISTURE CONTENT			11.4%
SWELL/CONSOLIDATION (%)			-0.3%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
 ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

SWELL CONSOLIDATION  
 TEST RESULTS

DRAWN:

DATE:

CHECKED: *SW*

DATE: *3-25-22*


JOB NO:  
 220455

FIG NO:  
*B-26*

**CONSOLIDATION TEST RESULTS**

TEST BORING #	3	DEPTH(ft)	10
DESCRIPTION	CL	SOIL TYPE	4
NATURAL UNIT DRY WEIGHT (PCF)			115
NATURAL MOISTURE CONTENT			12.6%
SWELL/CONSOLIDATION (%)			0.1%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

605 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
TEST RESULTS**

DRAWN:

DATE:

CHECKED: *SW*

DATE: *3-25-22*


JOB NO.:  
220455

FIG NO.:  
*B-27*

**CONSOLIDATION TEST RESULTS**

TEST BORING #	4	DEPTH(ft)	20
DESCRIPTION	CL	SOIL TYPE	4
NATURAL UNIT DRY WEIGHT (PCF)			112
NATURAL MOISTURE CONTENT			14.6%
SWELL/CONSOLIDATION (%)			-0.4%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
TEST RESULTS**

DRAWN:

DATE:

CHECKED:

SW

DATE:

3-25-22

JOB NO:  
220455


FIG NO:  
B-28



**CONSOLIDATION TEST RESULTS**

TEST BORING #	6	DEPTH(ft)	10
DESCRIPTION	CL	SOIL TYPE	4
NATURAL UNIT DRY WEIGHT (PCF)			122
NATURAL MOISTURE CONTENT			13.1%
SWELL/CONSOLIDATION (%)			0.1%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
TEST RESULTS**

DRAWN:

DATE:

CHECKED: *SW*

DATE: *3-25-22*


JOB NO.:  
220455

FIG NO.:  
*B-29*

**CONSOLIDATION TEST RESULTS**

TEST BORING #	7	DEPTH(ft)	5
DESCRIPTION	CL	SOIL TYPE	4
NATURAL UNIT DRY WEIGHT (PCF)			121
NATURAL MOISTURE CONTENT			11.7%
SWELL/CONSOLIDATION (%)			0.8%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
TEST RESULTS**

DRAWN:

DATE:

CHECKED: *SW*

DATE: *3-25-22*


JOB NO.:  
220455

FIG NO.:  
*B-30*

**CONSOLIDATION TEST RESULTS**

TEST BORING #	17	DEPTH(ft)	10
DESCRIPTION	CL	SOIL TYPE	4
NATURAL UNIT DRY WEIGHT (PCF)			107
NATURAL MOISTURE CONTENT			12.5%
SWELL/CONSOLIDATION (%)			-1.1%

JOB NO. 220455  
 CLIENT TECH CONTRACTORS  
 PROJECT ROLLING HILLS NORTH



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

**SWELL CONSOLIDATION  
TEST RESULTS**

DRAWN:

DATE:

CHECKED:

SW

DATE:

3-25-22

JOB NO.:  
220455

FIG NO.:  
B-31

CLIENT	TECH CONTRACTORS	JOB NO.	220455
PROJECT	ROLLING HILLS NORTH	DATE	3/18/2022
LOCATION	ROLLING HILLS NORTH	TEST BY	BL

BORING NUMBER	DEPTH, (ft)	SOIL TYPE NUMBER	UNIFIED CLASSIFICATION	WATER SOLUBLE SULFATE, (wt%)
TB-1	15	0		0.00
TB-2	5	0		0.00
TB-8	2-3	0		<0.01

QC BLANK PASS



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
SULFATE RESULTS**

DRAWN:	DATE:	CHECKED: <u>SW</u>	DATE: <u>3-25-22</u>
--------	-------	--------------------	----------------------

JOB NO.:  
220455

FIG NO.:  
B-32



## **APPENDIX C: Soil Survey Descriptions**

## El Paso County Area, Colorado

### 19—Columbine gravelly sandy loam, 0 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 367p  
*Elevation:* 6,500 to 7,300 feet  
*Mean annual precipitation:* 14 to 16 inches  
*Mean annual air temperature:* 46 to 50 degrees F  
*Frost-free period:* 125 to 145 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Columbine and similar soils:* 97 percent  
*Minor components:* 3 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Columbine

##### Setting

*Landform:* Flood plains, fan terraces, fans  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Alluvium

##### Typical profile

*A - 0 to 14 inches:* gravelly sandy loam  
*C - 14 to 60 inches:* very gravelly loamy sand

##### Properties and qualities

*Slope:* 0 to 3 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Well drained  
*Runoff class:* Very low  
*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (5.95 to 19.98 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water supply, 0 to 60 inches:* Very low (about 2.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 4e  
*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* R049XY214CO - Gravelly Foothill  
*Hydric soil rating:* No

#### Minor Components

##### Fluvaquentic haplaquolls

*Percent of map unit:* 1 percent

*Landform: Swales*  
*Hydric soil rating: Yes*

**Other soils**

*Percent of map unit: 1 percent*  
*Hydric soil rating: No*

**Pleasant**

*Percent of map unit: 1 percent*  
*Landform: Depressions*  
*Hydric soil rating: Yes*

## Data Source Information

Soil Survey Area: El Paso County Area, Colorado  
Survey Area Data: Version 21, Aug 24, 2023

## El Paso County Area, Colorado

### 83—Stapleton sandy loam, 3 to 8 percent slopes

#### Map Unit Setting

*National map unit symbol:* 369z

*Elevation:* 6,500 to 7,300 feet

*Mean annual precipitation:* 14 to 16 inches

*Mean annual air temperature:* 46 to 48 degrees F

*Frost-free period:* 125 to 145 days

*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Stapleton and similar soils:* 97 percent

*Minor components:* 3 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Stapleton

##### Setting

*Landform:* Hills

*Landform position (three-dimensional):* Side slope

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Parent material:* Sandy alluvium derived from arkose

##### Typical profile

*A - 0 to 11 inches:* sandy loam

*Bw - 11 to 17 inches:* gravelly sandy loam

*C - 17 to 60 inches:* gravelly loamy sand

##### Properties and qualities

*Slope:* 3 to 8 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* High  
(2.00 to 6.00 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Available water supply, 0 to 60 inches:* Low (about 4.7 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 3e

*Hydrologic Soil Group:* B

*Ecological site:* R049XY214CO - Gravelly Foothill

*Hydric soil rating:* No



### **Minor Components**

#### **Fluvaquentic haplaquolls**

*Percent of map unit:* 1 percent

*Landform:* Swales

*Hydric soil rating:* Yes

#### **Other soils**

*Percent of map unit:* 1 percent

*Hydric soil rating:* No

#### **Pleasant**

*Percent of map unit:* 1 percent

*Landform:* Depressions

*Hydric soil rating:* Yes


## **Data Source Information**

Soil Survey Area: El Paso County Area, Colorado

Survey Area Data: Version 21, Aug 24, 2023



## **APPENDIX D: Entech Overlot Fill Testing Records**




**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
1	120' north and 410' east of the southwest corner of Rolling Hills north lot, 5' below grade.	7/28/2022	95	95	7.2	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
2	115' north and 310' east of the southwest corner of Rolling Hills north lot, 3' below grade.	7/28/2022	95	95	6.8	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
3	110' north and 200' west of the southwest corner of Rolling Hills north lot, 1' below grade.	7/28/2022	96	95	7.6	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
4	105' north and 450' west of the southwest corner of Rolling Hills north lot, 4' below grade.	7/28/2022	95	95	8.4	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
5	115' north and 320' west of the southwest corner Rolling Hills north lot, 2' below grade.	7/28/2022	97	95	9.1	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
6	110' north and 120' west off the southwest corner of Rolling Hills north lot, at grade.	7/28/2022	95	95	7.9	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
7	120' north and 400' west off he southwest corner of Rolling Hills Ln, 3' below grade.	7/28/2022	96	95	6.2	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
8	105' north and 180' west of the southwest corner of Rolling Hills Ln, 1' below grade.	7/28/2022	95	95	6.5	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
9	170' north and 410' east off the southwest corner of Rolling Hills north lot 2' below grade.	7/29/2022	95	95	7.2	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
10	150' north and 250' east off the southwest corner of Rolling Hills north lot, 1' below grade.	7/29/2022	96	95	8.1	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
11	120' north and 100' east of the southwest corner of Rolling Hills north lot, at grade.	7/29/2022	96	95	6.4	SM	M - 127.8 @ 7.8	<input type="checkbox"/>
12	105' north and 120' east off the southwest corner of Rolling Hills north lot, at grade.	7/29/2022	95	95	7.5	SM	M - 127.8 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
13	Marker GPS # 1047, 4' below grade.	8/3/2022	98	95	8.2	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
14	Marker GPS # 1123, 4' below grade.	8/3/2022	98	95	8.4	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
15	Marker GPS # 1022, 4' below grade.	8/3/2022	98	95	8.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
16	Marker GPS # 1286, 4' below grade.	8/3/2022	98	95	8.2	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
17	Marker GPS # 1049, 4' below grade.	8/4/2022	98	95	7.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
18	Marker GPS # 1032, 4' below grade.	8/4/2022	98	95	8.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
19	Marker GPS # 1044, 4' below grade.	8/4/2022	98	95	8.6	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
20	Marker GPS # 1011, 4' below grade.	8/5/2022	98	95	8.2	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
21	Marker GPS # 1013, 4' below grade.	8/5/2022	98	95	8.4	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
22	Marker GPS # 1002, 4' below grade.	8/5/2022	98	95	8.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
23	Marker GPS # 1047, 2' below grade.	8/5/2022	98	95	8.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
24	Marker GPS # 1123, 2' below grade.	8/5/2022	98	95	7.7	SM	M - 130.4 @ 7.6	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
25	Marker GPS # 1072, 2' below grade.	8/5/2022	98	95	7.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
26	Marker GPS # 1286, 2' below grade.	8/5/2022	99	95	8.2	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
27	Marker GPS # 1049, 2' below grade.	8/9/2022	97	95	8.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
28	Marker GPS # 1032, 2' below grade.	8/9/2022	97	95	8.6	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
29	Marker GPS # 1044, 2' below grade.	8/10/2022	97	95	7.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
30	Marker GPS # 1011, 2' below grade.	8/10/2022	97	95	8.5	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
31	Marker GPS # 1013, 2' below grade.	8/11/2022	97	95	8.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
32	Marker GPS # 1002, 2' below grade.	8/11/2022	97	95	8.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
33	Marker GPS # 1047, at grade.	8/12/2022	98	95	9.2	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
34	Marker GPS # 1123, at grade.	8/12/2022	98	95	9.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
35	Marker GPS # 1072, at grade.	8/15/2022	98	95	8.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
36	Marker GPS # 1286, at grade.	8/15/2022	98	95	9.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
37	Marker GPS # 1049, at grade.	8/15/2022	98	95	9.4	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
38	Marker GPS # 1032, at grade.	8/15/2022	98	95	9.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
39	Marker GPS # 1044, at grade.	8/16/2022	98	95	9.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
40	Marker GPS # 1011, at grade.	8/16/2022	98	95	9.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
41	Marker GPS # 1013, at grade.	8/19/2022	98	95	9.8	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
42	Marker GPS # 1002, at grade.	8/19/2022	98	95	9.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
43	Shelter Creek Dr, Lot 310, 4' below grade.	8/22/2022	98	95	8.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
44	Shelter Creek Dr, Lot 306, 4' below grade.	8/22/2022	98	95	7.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
45	Shelter Creek Dr, Lot 304, 4' below grade.	8/22/2022	98	95	8.6	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
46	Shelter Creek Dr, Lot 298, 4' below grade.	8/22/2022	98	95	7.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
47	Shelter Creek Dr, Lot 294, 4' below grade.	8/22/2022	98	95	8.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
48	Shelter Creek Dr, Lot 310, 2' below grade.	8/22/2022	98	95	8.7	SM	M - 130.4 @ 7.6	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
49	Shelter Creek Dr, Lot 306, 2' below grade.	8/23/2022	98	95	8.4	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
50	Shelter Creek Dr, Lot 304, 2' below grade.	8/23/2022	98	95	7.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
51	Shelter Creek Dr, Lot 298, 2' below grade.	8/23/2022	98	95	7.7	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
52	Shelter Creek Dr, Lot 294, 2' below grade.	8/23/2022	98	95	7.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
53	Shelter Creek Dr, Lot 310, at grade.	8/23/2022	98	95	7.6	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
54	Shelter Creek Dr, Lot 306, at grade.	8/23/2022	98	95	8.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
55	Shelter Creek Dr, Lot 304, at grade.	8/24/2022	98	95	7.4	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
56	Shelter Creek Dr, Lot 298, at grade.	8/24/2022	98	95	8.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
57	Shelter Creek Dr, Lot 294, at grade.	8/24/2022	98	95	9.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
58	Manzanola Dr, Lot # 278, 4' below grade.	8/24/2022	98	95	8.6	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
59	Manzanola Dr, Lot # 279, 4' below grade.	8/24/2022	98	95	9.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
60	Manzanola Dr, Lot # 280, 4' below grade.	8/24/2022	98	95	8.7	SM	M - 130.4 @ 7.6	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
61	Manzanola Dr, Lot # 277, 4' below grade.	8/25/2022	98	95	8.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
62	Manzanola Dr, Lot # 276, 4' below grade.	8/25/2022	98	95	8.4	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
63	Manzanola Dr, Lot # 276, 2' below grade.	8/25/2022	98	95	8.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
64	Manzanola Dr, Lot # 277, 2' below grade.	8/25/2022	97	95	7.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
65	Manzanola Dr, Lot # 278, 2' below grade.	8/25/2022	97	95	8.0	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
66	Manzanola Dr, Lot # 279, 2' below grade.	8/25/2022	98	95	7.7	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
67	Manzanola Dr, Lot # 280, 2' below grade.	8/26/2022	98	95	7.3	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
68	Manzanola Dr, Lot # 276, at grade.	8/26/2022	98	95	8.1	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
69	Manzanola Dr, Lot # 277, at grade.	8/26/2022	98	95	8.6	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
70	Manzanola Dr, Lot # 278, at grade.	8/26/2022	98	95	7.8	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
71	Manzanola Dr, Lot # 279, at grade.	8/26/2022	98	95	7.7	SM	M - 130.4 @ 7.6	<input type="checkbox"/>
72	Manzanola Dr, Lot # 280, at grade.	8/26/2022	98	95	7.9	SM	M - 130.4 @ 7.6	<input type="checkbox"/>






**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
73	Lot # 78 on Arrica Drive, 3' below grade.	8/29/2022	98	95	9.0	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
74	Lot # 77 on Arrica Drive, 3' below grade.	8/29/2022	98	95	8.7	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
75	Lot # 76 on Arrica Drive, 3' below grade.	8/29/2022	98	95	8.3	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
76	Lot # 75 on Arrica Drive, 3' below grade.	8/29/2022	98	95	8.2	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
77	Lot # 78 on Arrica Drive, 2' below grade.	8/29/2022	98	95	8.4	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
78	Lot # 77 on Arrica Drive, 2' below grade.	8/29/2022	98	95	8.9	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
79	Lot # 76 on Arrica Drive, 2' below grade.	8/30/2022	98	95	7.7	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
80	Lot # 75 on Arrica Drive, 2' below grade.	8/30/2022	98	95	8.3	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
81	Lot # 78 on Arrica Drive, at grade.	8/30/2022	98	95	8.1	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
82	Lot # 77 on Arrica Drive, at grade.	8/30/2022	98	95	8.7	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
83	Lot # 76 on Arrica Drive, at grade.	8/30/2022	98	95	8.6	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
84	Lot # 75 on Arrica Drive, at grade.	8/30/2022	97	95	8.0	SM	M - 130.1 @ 7.6	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
85	Lot # 31 on Retreat Peak, 4' below grade.	8/31/2022	97	95	8.7	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
86	Lot # 29 on Retreat Peak, 4' below grade.	8/31/2022	97	95	7.7	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
87	Lot # 27 on Retreat Peak, 4' below grade.	8/31/2022	98	95	7.6	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
88	Lot # 25 on Retreat Peak, 4' below grade.	8/31/2022	98	95	7.3	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
89	Lot # 23 on Retreat Peak, 4' below grade.	8/31/2022	98	95	7.7	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
90	Lot # 21 on Retreat Peak, 4' below grade.	8/31/2022	98	95	8.3	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
91	Lot # 31 on Retreat Peak, 2' below grade.	9/1/2022	98	95	8.2	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
92	Lot # 29 on Retreat Peak, 2' below grade.	9/1/2022	98	95	8.6	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
93	Lot # 27 on Retreat Peak, 2' below grade.	9/1/2022	98	95	8.4	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
94	Lot # 25 on Retreat Peak, 2' below grade.	9/1/2022	98	95	8.1	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
95	Lot # 23 on Retreat Peak, 2' below grade.	9/1/2022	98	95	7.9	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
96	Lot # 21 on Retreat Peak, 2' below grade.	9/1/2022	98	95	7.9	SM	M - 130.1 @ 7.6	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
97	Lot # 31 on Retreat Peak, at grade.	9/2/2022	98	95	8.6	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
98	Lot # 29 on Retreat Peak, at grade.	9/2/2022	98	95	8.3	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
99	Lot # 27 on Retreat Peak, at grade.	9/2/2022	98	95	8.1	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
100	Lot # 25 on Retreat Peak, at grade.	9/2/2022	98	95	8.4	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
101	Lot # 23 on Retreat Peak, at grade.	9/2/2022	98	95	8.0	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
102	Lot # 21 on Retreat Peak, at grade.	9/2/2022	98	95	8.3	SM	M - 130.1 @ 7.6	<input type="checkbox"/>
103	Lot # 322 on Cuchara Way, 6' below grade.	9/6/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
104	Lot # 323 on Cuchara Way, 6' below grade.	9/6/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
105	Lot # 324 on Cuchara Way, 6' below grade.	9/6/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
106	Lot # 325 on Cuchara Way, 6' below grade.	9/6/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
107	Lot # 322 on Cuchara Way, 4' below grade.	9/7/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
108	Lot # 323 on Cuchara Way, 4' below grade.	9/7/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
109	Lot # 324 on Cuchara Way, 4' below grade.	9/8/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
110	Lot # 325 on Cuchara Way, 4' below grade.	9/8/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
111	Lot # 322 on Cuchara Way, 2' below grade.	9/8/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
112	Lot # 323 on Cuchara Way, 2' below grade.	9/8/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
113	Lot # 324 on Cuchara Way, 2' below grade.	9/8/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
114	Lot # 325 on Cuchara Way, 2' below grade.	9/8/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
115	Lot # 322 on Cuchara Way, at grade.	9/8/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
116	Lot # 323 on Cuchara Way, at grade.	9/8/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
117	Lot # 324 on Cuchara Way, at grade.	9/9/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
118	Lot # 325 on Cuchara Way, at grade.	9/9/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
119	Overlot, Lot # 141, 3' below grade.	9/12/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
120	Overlot, Lot # 140, 3' below grade.	9/12/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
121	Overlot, Lot # 139, 3' below grade.	9/12/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
122	Overlot, Lot # 138, 3' below grade.	9/12/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
123	Overlot, Lot # 137, 3' below grade.	9/13/2022	98	95	7.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
124	Overlot, Lot # 141, 2' below grade.	9/13/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
125	Overlot, Lot # 140, 2' below grade.	9/13/2022	98	95	8.5	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
126	Overlot, Lot # 139, 2' below grade.	9/13/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
127	Overlot, Lot # 138, 2' below grade.	9/13/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
128	Overlot, Lot # 137, 2' below grade.	9/13/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
129	Overlot, Lot # 141, 1' below grade.	9/14/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
130	Overlot, Lot # 140, 1' below grade.	9/14/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
131	Overlot, Lot # 139, 1' below grade.	9/14/2022	98	95	7.8	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
132	Overlot, Lot # 138, 1' below grade.	9/14/2022	98	95	7.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
133	Overlot, Lot # 137, 1' below grade.	9/15/2022	97	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
134	Overlot, Lot # 141, at grade.	9/15/2022	97	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
135	Overlot, Lot # 140, at grade.	9/15/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
136	Overlot, Lot # 139, at grade.	9/15/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
137	Overlot, Lot # 138, at grade.	9/16/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
138	Overlot, Lot # 137, at grade.	9/16/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
139	Overlot, Lot # 156, 2' below grade.	9/19/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
140	Overlot, Lot # 155, 2' below grade.	9/19/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
141	Overlot, Lot # 154, 2' below grade.	9/20/2022	98	95	9.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
142	Overlot, Lot # 153, 2' below grade.	9/20/2022	98	95	9.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
143	Overlot, Lot # 156, at grade.	9/21/2022	98	95	8.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
144	Overlot, Lot # 155, at grade.	9/21/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
145	Overlot, Lot # 154, at grade.	9/23/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
146	Overlot, Lot # 153, at grade.	9/23/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
147	Lot # 37, 4' below grade.	9/27/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
148	Lot # 37, 3' below grade.	9/27/2022	99	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
149	Lot # 37, 2' below grade.	9/28/2022	99	95	9.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
150	Lot # 37, 1' below grade.	9/28/2022	99	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
151	Lot # 37, at grade.	9/29/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
152	Lot # 38, 3' below grade.	9/29/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
153	Lot # 38, 2' below grade.	9/30/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
154	Lot # 38, at grade.	9/30/2022	99	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
155	Lot # 140 on Shelter Creek, 2' below grade.	10/3/2022	98	95	8.4	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
156	Lot # 141 on Shelter Creek, 2' below grade.	10/3/2022	98	95	7.9	SM	M - 130.2 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
157	Lot # 142 on Shelter Creek, 2' below grade.	10/4/2022	98	95	8.6	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
158	Lot # 143 on Shelter Creek, 2' below grade.	10/4/2022	98	95	8.0	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
159	Lot # 144 on Shelter Creek, 2' below grade.	10/4/2022	97	95	9.1	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
160	Lot # 140 on Shelter Creek, 1' below grade.	10/4/2022	97	95	9.0	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
161	Lot # 141 on Shelter Creek, 1' below grade.	10/5/2022	97	95	8.3	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
162	Lot # 142 on Shelter Creek, 1' below grade.	10/5/2022	98	95	8.1	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
163	Lot # 143 on Shelter Creek, 1' below grade.	10/5/2022	98	95	8.6	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
164	Lot # 144 on Shelter Creek, 1' below grade.	10/5/2022	98	95	8.3	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
165	Lot # 140 on Shelter Creek, at grade.	10/6/2022	98	95	8.4	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
166	Lot # 141 on Shelter Creek, at grade.	10/6/2022	98	95	8.6	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
167	Lot # 142 on Shelter Creek, at grade.	10/6/2022	98	95	8.0	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
168	Lot # 143 on Shelter Creek, at grade.	10/6/2022	98	95	7.8	SM	M - 130.2 @ 7.8	<input type="checkbox"/>






**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
169	Lot # 144 on Shelter Creek, at grade.	10/7/2022	98	95	8.3	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
170	Lot # 145 on Shelter Creek, at grade.	10/7/2022	98	95	8.6	SM	M - 130.2 @ 7.8	<input type="checkbox"/>
171	Lot # 110 on Sunrise Ridge, 2' below grade.	10/10/2022	98	95	9.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
172	Lot # 112 on Sunrise Ridge, 2' below grade.	10/10/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
173	Lot # 114 on Sunrise Ridge, 2' below grade.	10/11/2022	97	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
174	Lot # 116 on Sunrise Ridge, 2' below grade.	10/11/2022	97	95	8.5	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
175	Lot # 118 on Sunrise Ridge, 2' below grade.	10/11/2022	97	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
176	Lot # 120 on Sunrise Ridge, 2' below grade.	10/11/2022	97	95	8.8	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
177	Lot # 122 on Sunrise Ridge, 2' below grade.	10/12/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
178	Lot # 124 on Sunrise Ridge, 2' below grade.	10/12/2022	97	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
179	Lot # 126 on Sunrise Ridge, 2' below grade.	10/13/2022	97	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
180	Lot # 119 on Sunrise Ridge, 2' below grade.	10/13/2022	97	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
181	Lot # 1 on Sunrise Ridge, 2' below grade.	10/17/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
182	Lot # 2 on Sunrise Ridge, 2' below grade.	10/17/2022	97	95	7.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
183	Lot # 3 on Sunrise Ridge, 2' below grade.	10/18/2022	97	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
184	Lot # 4 on Sunrise Ridge, 2' below grade.	10/18/2022	97	95	7.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
185	Lot # 5 on Sunrise Ridge, 2' below grade.	10/19/2022	97	95	7.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
186	Lot # 6 on Sunrise Ridge, 2' below grade.	10/19/2022	98	95	7.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
187	Lot # 7 on Sunrise Ridge, 2' below grade.	10/20/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
188	Lot # 8 on Sunrise Ridge, 2' below grade.	10/20/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
189	Lot # 9 on Sunrise Ridge, 2' below grade.	10/21/2022	97	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
190	Lot # 10 on Sunrise Ridge, 2' below grade.	10/21/2022	97	95	7.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
191	Overlot, Shelter Creek, Lot # 132, 2' below grade.	10/24/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
192	Overlot, Shelter Creek, Lot # 133, 2' below grade.	10/24/2022	97	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
193	Overlot, Shelter Creek, Lot # 134, 2' below grade.	10/24/2022	97	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
194	Overlot, Shelter Creek, Lot # 135, 2' below grade.	10/24/2022	97	95	8.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
195	Overlot, Shelter Creek, Lot # 136, 2' below grade.	10/24/2022	97	95	8.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
196	Overlot, Shelter Creek, Lot # 137, 2' below grade.	10/25/2022	98	95	9.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
197	Overlot, Shelter Creek, Lot # 138, 2' below grade.	10/25/2022	98	95	9.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
198	Overlot, Shelter Creek, Lot # 139, 2' below grade.	10/26/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
199	Overlot, Shelter Creek, Lot # 140, 2' below grade.	10/26/2022	98	95	8.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
200	Overlot, Shelter Creek, Lot # 141, 2' below grade.	10/26/2022	98	95	9.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
201	Overlot, Shelter Creek, Lot # 132, at grade.	10/27/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
202	Overlot, Shelter Creek, Lot # 133, at grade.	10/27/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
203	Overlot, Shelter Creek, Lot # 134, at grade.	10/27/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
204	Overlot, Shelter Creek, Lot # 135, at grade.	10/27/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
205	Overlot, Shelter Creek, Lot # 136, at grade.	10/27/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
206	Overlot, Shelter Creek, Lot # 137, at grade.	10/28/2022	97	95	9.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
207	Overlot, Shelter Creek, Lot # 138, at grade.	10/28/2022	97	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
208	Overlot, Shelter Creek, Lot # 139, at grade.	10/28/2022	97	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
209	Overlot, Shelter Creek, Lot # 140, at grade.	10/28/2022	97	95	9.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
210	Overlot, Shelter Creek, Lot # 141, at grade.	10/28/2022	98	95	9.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
211	Overlot, Sunrise Ridge, Lot # 170, 2' below grade.	10/31/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
212	Overlot, Sunrise Ridge, Lot # 171, 2' below grade.	10/31/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
213	Overlot, Sunrise Ridge, Lot # 172, 2' below grade.	11/1/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
214	Overlot, Sunrise Ridge, Lot # 173, 2' below grade.	11/1/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
215	Overlot, Sunrise Ridge, Lot # 174, 2' below grade.	11/2/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
216	Overlot, Sunrise Ridge, Lot # 175, 2' below grade.	11/2/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
217	Overlot, Sunrise Ridge, Lot # 176, 2' below grade.	11/3/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
218	Overlot, Sunrise Ridge, Lot # 177, 2' below grade.	11/3/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
219	Overlot, Sunrise Ridge, Lot # 178, 2' below grade.	11/4/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
220	Overlot, Sunrise Ridge, Lot # 179, 2' below grade.	11/4/2022	98	95	8.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
221	Overlot, Chalk Cliffs, Lot # 112, 3' below grade.	11/7/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
222	Overlot, Chalk Cliffs, Lot # 113, 3' below grade.	11/7/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
223	Overlot, Chalk Cliffs, Lot # 114, 3' below grade.	11/8/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
224	Overlot, Chalk Cliffs, Lot # 115, 3' below grade.	11/8/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
225	Overlot, Chalk Cliffs, Lot # 116, 3' below grade.	11/8/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
226	Overlot, Chalk Cliffs, Lot # 117, 3' below grade.	11/8/2022	98	95	7.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
227	Overlot, Chalk Cliffs, Lot # 118, 3' below grade.	11/8/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
228	Overlot, Chalk Cliffs, Lot # 119, 3' below grade.	11/8/2022	98	95	9.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
229	Overlot, Chalk Cliffs, Lot # 120, 3' below grade.	11/8/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
230	Overlot, Chalk Cliffs, Lot # 121, 3' below grade.	11/8/2022	98	95	9.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
231	Overlot, Chalk Cliffs, Lot # 112, at grade.	11/9/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
232	Overlot, Chalk Cliffs, Lot # 113, at grade.	11/9/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
233	Overlot, Chalk Cliffs, Lot # 114, at grade.	11/10/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
234	Overlot, Chalk Cliffs, Lot # 115, at grade.	11/10/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
235	Overlot, Chalk Cliffs, Lot # 116, at grade.	11/11/2022	98	95	9.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
236	Overlot, Chalk Cliffs, Lot # 117, at grade.	11/11/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
237	Overlot, Chalk Cliffs, Lot # 118, at grade.	11/11/2022	98	95	8.8	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
238	Overlot, Chalk Cliffs, Lot # 119, at grade.	11/11/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
239	Overlot, Chalk Cliffs, Lot # 120, at grade.	11/11/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
240	Overlot, Chalk Cliffs, Lot # 121, at grade.	11/11/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
241	Overlot, Crystal Falls Drive, Lot # 207, 2' below grade.	11/14/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
242	Overlot, Crystal Falls Drive, Lot # 209, 2' below grade.	11/14/2022	98	95	7.8	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
243	Overlot, Crystal Falls Drive, Lot # 211, 2' below grade.	11/14/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
244	Overlot, Crystal Falls Drive, Lot # 213, 2' below grade.	11/14/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
245	Overlot, Crystal Falls Drive, Lot # 213, 2' below grade.	11/14/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
246	Overlot, Crystal Falls Drive, Lot # 217, 2' below grade.	11/15/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
247	Overlot, Crystal Falls Drive, Lot # 219, 2' below grade.	11/15/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
248	Overlot, Crystal Falls Drive, Lot # 221, 2' below grade.	11/15/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
249	Overlot, Crystal Falls Drive, Lot # 223, 2' below grade.	11/15/2022	97	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
250	Overlot, Crystal Falls Drive, Lot # 199, 2' below grade.	11/15/2022	97	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
251	Overlot, Crystal Falls Drive, Lot # 207, at grade.	11/16/2022	98	95	7.8	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
252	Overlot, Crystal Falls Drive, Lot # 209, at grade.	11/16/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
253	Overlot, Crystal Falls Drive, Lot # 211, at grade.	11/16/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
254	Overlot, Crystal Falls Drive, Lot # 213, at grade.	11/16/2022	98	95	8.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
255	Overlot, Crystal Falls Drive, Lot # 215, at grade.	11/16/2022	98	95	8.2	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
256	Overlot, Crystal Falls Drive, Lot # 217, at grade.	11/17/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
257	Overlot, Crystal Falls Drive, Lot # 219, at grade.	11/17/2022	98	95	8.6	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
258	Overlot, Crystal Falls Drive, Lot # 221, at grade.	11/17/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
259	Overlot, Crystal Falls Drive, Lot # 223, at grade.	11/17/2022	98	95	8.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
260	Overlot, Crystal Falls Drive, Lot # 199, at grade.	11/17/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
261	Overlot, House Rock Drive, Lot # 142, at grade.	11/21/2022	98	95	8.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
262	Overlot, House Rock Drive, Lot # 143, at grade.	11/21/2022	98	95	8.7	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
263	Overlot, House Rock Drive, Lot # 144, at grade.	11/21/2022	98	95	9.0	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
264	Overlot, House Rock Drive, Lot # 145, at grade.	11/22/2022	98	95	9.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>






**ENTECH**  
ENGINEERING, INC.  
**Density Testing Summary**

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
265	Overlot, House Rock Drive, Lot # 146, at grade.	11/22/2022	98	95	8.9	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
266	Overlot, House Rock Drive, Lot # 147, at grade.	11/22/2022	98	95	8.8	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
267	Overlot, House Rock Drive, Lot # 148, at grade.	11/23/2022	98	95	8.4	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
268	Overlot, House Rock Drive, Lot # 149, at grade.	11/23/2022	98	95	9.3	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
269	Overlot, House Rock Drive, Lot # 150, at grade.	11/23/2022	98	95	9.1	SM	M - 130.5 @ 7.8	<input type="checkbox"/>
270	Lot # 103 on Cardenas Drive, 2' below grade.	11/28/2022	98	95	7.9	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
271	Lot # 105 on Cardenas Drive, 2' below grade.	11/28/2022	98	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
272	Lot # 107 on Cardenas Drive, 2' below grade.	11/28/2022	98	95	7.6	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
273	Lot # 109 on Cardenas Drive, 2' below grade.	11/28/2022	98	95	8.0	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
274	Lot # 111 on Cardenas Drive, 2' below grade.	11/28/2022	98	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
275	Lot # 113 on Cardenas Drive, 2' below grade.	11/29/2022	98	95	8.4	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
276	Lot # 100 on Cardenas Drive, 2' below grade.	11/29/2022	98	95	8.2	SM	M - 128.2 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
277	Lot # 99 on Cardenas Drive, 2' below grade.	11/29/2022	98	95	8.7	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
278	Lot # 98 on Cardenas Drive, 2' below grade.	11/29/2022	98	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
279	Lot # 97 on Cardenas Drive, 2' below grade.	11/29/2022	98	95	8.0	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
280	Lot # 103 on Cardenas Drive, at grade.	11/29/2022	98	95	8.2	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
281	Lot # 105 on Cardenas Drive, at grade.	11/29/2022	98	95	8.4	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
282	Lot # 107 on Cardenas Drive, at grade.	11/29/2022	98	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
283	Lot # 109 on Cardenas Drive, at grade.	11/29/2022	98	95	8.9	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
284	Lot # 111 on Cardenas Drive, at grade.	11/29/2022	98	95	7.6	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
285	Lot # 113 on Cardenas Drive, at grade.	12/1/2022	98	95	7.9	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
286	Lot # 100 on Cardenas Drive, at grade.	12/1/2022	98	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
287	Lot # 99 on Cardenas Drive, at grade.	12/1/2022	98	95	8.4	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
288	Lot # 98 on Cardenas Drive, at grade.	12/1/2022	98	95	8.1	SM	M - 128.2 @ 7.8	<input type="checkbox"/>




**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input type="checkbox"/> = Fail
289	Lot # 97 on Cardenas Drive, at grade.	12/1/2022	98	95	8.0	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
290	Lot # 84 on Cardenas Drive, at grade.	12/2/2022	98	95	8.7	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
291	Lot # 85 on Cardenas Drive, at grade.	12/2/2022	98	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
292	Lot # 86 on Cardenas Drive, at grade.	12/2/2022	98	95	8.6	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
293	Lot # 87 on Cardenas Drive, at grade.	12/2/2022	98	95	8.4	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
294	Lot # 88 on Cardenas Drive, at grade.	12/2/2022	98	95	7.9	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
295	Overlot, Esplanade Drive, Lot # 01, at grade.	12/5/2022	98	95	8.0	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
296	Overlot, Esplanade Drive, Lot # 03, at grade.	12/5/2022	98	95	7.8	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
297	Overlot, Esplanade Drive, Lot # 05, at grade.	12/6/2022	98	95	7.6	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
298	Overlot, Esplanade Drive, Lot # 07, at grade.	12/6/2022	98	95	7.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
299	Overlot, Esplanade Drive, Lot # 09, at grade.	12/7/2022	98	95	7.9	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
300	Overlot, Esplanade Drive, Lot # 11, at grade.	12/7/2022	98	95	7.8	SM	M - 128.2 @ 7.8	<input type="checkbox"/>



**ENTECH**  
ENGINEERING, INC.  
Density Testing Summary

**Client:** Tech Contractors  
**Project:** Rolling Hills Ranch North  
**Entech Job #:** 221455.1  
**Subject:** Overlot

**QC Reviewed by:** \_\_\_\_\_  
**QA Reviewed by:** \_\_\_\_\_  
**Report Date:** 23-Jan-24

Test #	Test Location	Testing Date	Percent Compaction	Percent Required	Percent Moisture	Soil Type	Proctor Type/Value	Pass/Fail <input checked="" type="checkbox"/> = Fail
301	Overlot, Esplanade Drive, Lot # 13, at grade.	12/8/2022	97	95	8.3	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
302	Overlot, Horn Hill Drive, Lot # 74, at grade.	12/8/2022	97	95	8.6	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
303	Overlot, Horn Hill Drive, Lot # 75, at grade.	12/9/2022	97	95	8.7	SM	M - 128.2 @ 7.8	<input type="checkbox"/>
304	Overlot, Horn Hill Drive, Lot # 60, at grade.	12/9/2022	97	95	8.0	SM	M - 128.2 @ 7.8	<input type="checkbox"/>