

2026 Financial Assurance Estimate Form (with pre-plat construction)

Updated: 2/2026


PROJECT INFORMATION			
Project Name: HILLPOINTE PETERSON	Date: 2026-08-14	PCD File No. PPR2613	

Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)	Remaining
SECTION 1 - GRADING AND EROSION CONTROL (Construction and Permanent BMPs)							
Earthwork							
less than 5,000; \$8,000 min		CY	\$ 7.50	=	\$ -		\$ -
5,001-20,000; \$30,000 min		CY	\$ 6.50	=	\$ -		\$ -
20,001-50,000; \$100,000 min		CY	\$ 4.50	=	\$ -		\$ -
50,001-200,000; \$175,000 min	55404.	CY	\$ 3.00	=	\$ 175,000.00		\$ 175,000.00
greater than 200,000; \$500,000 min		CY	\$ 2.50	=	\$ -		\$ -
Erosion Control Blanket	1510.	SY	\$ 6.00	=	\$ 9,060.00		\$ 9,060.00
Seeding (inc. noxious weed mgmnt.) & Mulching	2.	AC	\$ 2,037.00	=	\$ 4,074.00		\$ 4,074.00
Permanent Pond/PCM (provide engineer's estimate)	1.	EA	\$ 75,825.00	=	\$ 75,825.00		\$ 75,825.00
					\$ -		\$ -
					\$ -		\$ -
[insert items not listed but part of construction plans]					\$ -		\$ -
Safety Fence		LF	\$ 5.00	=	\$ -		\$ -
Inlet Protection	21.	EA	\$ 322.00	=	\$ 6,762.00		\$ 6,762.00
Rock Check Dam		EA	\$ 908.00	=	\$ -		\$ -
Concrete Washout Basin	1.	EA	\$ 1,790.00	=	\$ 1,790.00		\$ 1,790.00
Sediment Basin	3.	EA	\$ 3,483.00	=	\$ 10,449.00		\$ 10,449.00
Sediment Trap		EA	\$ 877.00	=	\$ -		\$ -
Silt Fence	4531.	LF	\$ 3.00	=	\$ 13,593.00		\$ 13,593.00
Slope Drain		LF	\$ 30.00	=	\$ -		\$ -
Straw Bale		EA	\$ 56.00	=	\$ -		\$ -
Straw Wattle/Rock Sock	1478.	LF	\$ 11.00	=	\$ 16,258.00		\$ 16,258.00
Surface Roughening		AC	\$ 507.00	=	\$ -		\$ -
Vehicle Tracking Control	2.	EA	\$ 3,840.00	=	\$ 7,680.00		\$ 7,680.00
					\$ -		\$ -
					\$ -		\$ -
					\$ -		\$ -
[insert items not listed but part of construction plans]					\$ -		\$ -
MAINTENANCE (35% of Construction BMPs)					=	\$ 19,786.20	\$ 19,786.20
Section 1 Subtotal					=	\$ 340,277.20	\$ 340,277.20
SECTION 2 - PUBLIC IMPROVEMENTS *							
ROADWAY IMPROVEMENTS							
Construction Traffic Control		LS	\$ 5,000.00	=	\$ -		\$ -
Aggregate Base Course (135 lbs/cf)		Tons	\$ 42.00	=	\$ -		\$ -
Aggregate Base Course (135 lbs/cf)	22.	CY	\$ 81.00	=	\$ 1,782.00		\$ 1,782.00
Asphalt Pavement (3" thick)		SY	\$ 22.00	=	\$ -		\$ -
Asphalt Pavement (4" thick)	64.	SY	\$ 31.00	=	\$ 1,984.00		\$ 1,984.00
Asphalt Pavement (6" thick)		SY	\$ 47.00	=	\$ -		\$ -
Asphalt Pavement (147 lbs/cf) _" thick		Tons	\$ 140.00	=	\$ -		\$ -
Raised Median, Paved		SF	\$ 15.00	=	\$ -		\$ -
Signs (regulatory/advisory/guide/street)	5.	EA	\$ 293.00	=	\$ 1,465.00		\$ 1,465.00
Epoxy Pavement Marking	2805.	SF	\$ 19.00	=	\$ 53,295.00		\$ 53,295.00
Thermoplastic Pavement Marking		SF	\$ 29.00	=	\$ -		\$ -
Barricade - Type 3		EA	\$ 380.00	=	\$ -		\$ -
Delineator - Type I		EA	\$ 38.00	=	\$ -		\$ -
Curb and Gutter, Type A (6" Vertical)		LF	\$ 49.00	=	\$ -		\$ -
Curb and Gutter, Type B (Median)		LF	\$ 50.00	=	\$ -		\$ -
Curb and Gutter, Type C (Ramp)		LF	\$ 51.00	=	\$ -		\$ -
4" Sidewalk (common areas only)		SY	\$ 69.00	=	\$ -		\$ -
5" Sidewalk	25.	SY	\$ 85.00	=	\$ 2,125.00		\$ 2,125.00
6" Sidewalk		SY	\$ 113.00	=	\$ -		\$ -
8" Sidewalk		SY	\$ 141.00	=	\$ -		\$ -
Pedestrian Ramp	2.	EA	\$ 1,961.00	=	\$ 3,922.00		\$ 3,922.00
Cross Pan, local (8" thick, 6' wide to include return)		LF	\$ 87.00	=	\$ -		\$ -
Cross Pan, collector (9" thick, 8' wide to include return)	100.	LF	\$ 131.00	=	\$ 13,100.00		\$ 13,100.00
Curb Opening with Drainage Chase		EA	\$ 2,341.00	=	\$ -		\$ -
Guardrail Type 3 (W-Beam)		LF	\$ 87.00	=	\$ -		\$ -
Guardrail Type 7 (Concrete)		LF	\$ 104.00	=	\$ -		\$ -
Guardrail End Anchorage		EA	\$ 2,485.00	=	\$ -		\$ -
Guardrail Impact Attenuator		EA	\$ 22,568.00	=	\$ -		\$ -
Sound Barrier Fence (CMU block, 6' high)		LF	\$ 113.00	=	\$ -		\$ -
Sound Barrier Fence (panels, 6' high)		LF	\$ 115.00	=	\$ -		\$ -
Electrical Conduit, Size =		LF	\$ 33.00	=	\$ -		\$ -
Traffic Signal, (provide engineer's estimate)		EA		=	\$ -		\$ -
Survey Monumentation		EA	\$ 638.00	=	\$ -		\$ -
				=	\$ -		\$ -

PROJECT INFORMATION							
Project Name: HILLPOINTE PETERSON			Date: 2026-08-14		PCD File No. PPR2613		
Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction) % Complete	Remaining
				=	\$ -		\$ -
				=	\$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -
STORM DRAIN IMPROVEMENTS							
Concrete Box Culvert (M Standard), Size (W x H)		LF		=	\$ -		\$ -
18" Reinforced Concrete Pipe		LF	\$ 111.00	=	\$ -		\$ -
24" Reinforced Concrete Pipe		LF	\$ 161.00	=	\$ -		\$ -
30" Reinforced Concrete Pipe		LF	\$ 167.00	=	\$ -		\$ -
36" Reinforced Concrete Pipe		LF	\$ 191.00	=	\$ -		\$ -
42" Reinforced Concrete Pipe		LF	\$ 275.00	=	\$ -		\$ -
48" Reinforced Concrete Pipe		LF	\$ 349.00	=	\$ -		\$ -
54" Reinforced Concrete Pipe		LF	\$ 465.00	=	\$ -		\$ -
60" Reinforced Concrete Pipe		LF	\$ 476.00	=	\$ -		\$ -
66" Reinforced Concrete Pipe		LF	\$ 550.00	=	\$ -		\$ -
72" Reinforced Concrete Pipe		LF	\$ 616.00	=	\$ -		\$ -
18" Corrugated Steel Pipe		LF	\$ 136.00	=	\$ -		\$ -
24" Corrugated Steel Pipe		LF	\$ 229.00	=	\$ -		\$ -
30" Corrugated Steel Pipe		LF	\$ 244.00	=	\$ -		\$ -
36" Corrugated Steel Pipe		LF	\$ 244.00	=	\$ -		\$ -
42" Corrugated Steel Pipe		LF	\$ 226.00	=	\$ -		\$ -
48" Corrugated Steel Pipe		LF	\$ 465.00	=	\$ -		\$ -
54" Corrugated Steel Pipe		LF	\$ 459.00	=	\$ -		\$ -
60" Corrugated Steel Pipe		LF	\$ 501.00	=	\$ -		\$ -
66" Corrugated Steel Pipe		LF	\$ 580.00	=	\$ -		\$ -
72" Corrugated Steel Pipe		LF	\$ 654.00	=	\$ -		\$ -
78" Corrugated Steel Pipe		LF	\$ 728.00	=	\$ -		\$ -
84" Corrugated Steel Pipe		LF	\$ 901.00	=	\$ -		\$ -
Flared End Section (FES) RCP Size = <i>(unit cost = 6x pipe unit cost)</i>		EA		=	\$ -		\$ -
Flared End Section (FES) CSP Size = <i>(unit cost = 6x pipe unit cost)</i>		EA		=	\$ -		\$ -
				=	\$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -
End Treatment- Headwall		EA		=	\$ -		\$ -
End Treatment- Wingwall		EA		=	\$ -		\$ -
End Treatment - Cutoff Wall		EA		=	\$ -		\$ -
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 8,814.00	=	\$ -		\$ -
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 10,835.00	=	\$ -		\$ -
Curb Inlet (Type R) L=5', 10' ≤ Depth < 15'		EA	\$ 12,206.00	=	\$ -		\$ -
Curb Inlet (Type R) L=10', Depth < 5'		EA	\$ 11,438.00	=	\$ -		\$ -
Curb Inlet (Type R) L=10', 5' ≤ Depth < 10'		EA	\$ 12,689.00	=	\$ -		\$ -
Curb Inlet (Type R) L=10', 10' ≤ Depth < 15'		EA	\$ 16,174.00	=	\$ -		\$ -
Curb Inlet (Type R) L=15', Depth < 5'		EA	\$ 14,452.00	=	\$ -		\$ -
Curb Inlet (Type R) L=15', 5' ≤ Depth < 10'		EA	\$ 17,237.00	=	\$ -		\$ -
Curb Inlet (Type R) L=15', 10' ≤ Depth < 15'		EA	\$ 21,610.00	=	\$ -		\$ -
Curb Inlet (Type R) L=20', Depth < 5'		EA	\$ 16,499.00	=	\$ -		\$ -
Curb Inlet (Type R) L=20', 5' ≤ Depth < 10'		EA	\$ 20,012.00	=	\$ -		\$ -
Grated Inlet (Type C), Depth < 5'		EA	\$ 8,156.00	=	\$ -		\$ -
Grated Inlet (Type D), Depth < 5'		EA	\$ 11,435.00	=	\$ -		\$ -
Storm Sewer Manhole, Box Base		EA	\$ 18,950.00	=	\$ -		\$ -
Storm Sewer Manhole, Slab Base		EA	\$ 9,314.00	=	\$ -		\$ -
Geotextile (Erosion Control)		SY	\$ 6.00	=	\$ -		\$ -
Rip Rap, d50 size from 6" to 24"		Tons	\$ 102.00	=	\$ -		\$ -
Rip Rap, Grouted		Tons	\$ 136.00	=	\$ -		\$ -
Drainage Channel Construction, Size (W x H)		LF		=	\$ -		\$ -
Drainage Channel Lining, Concrete		CY	\$ 815.00	=	\$ -		\$ -
Drainage Channel Lining, Rip Rap		CY	\$ 234.00	=	\$ -		\$ -
Drainage Channel Lining, Grass		AC	\$ 2,100.00	=	\$ -		\$ -
Permanent Drainage Channel Lining or Roadside Ditch TRM		SY	\$ 13.00	=	\$ -		\$ -
				=	\$ -		\$ -
				=	\$ -		\$ -
<i>[insert items not listed but part of construction plans]</i>				=	\$ -		\$ -
Section 2 Subtotal				=	\$ 77,673.00		\$ 77,673.00

* - Subject to defect warranty financial assurance. A minimum of 20% shall be retained until final acceptance (MAXIMUM OF 80% COMPLETE ALLOWED)

PROJECT INFORMATION									
Project Name: HILLPOINTE PETERSON				Date: 2026-08-14			PCD File No. PPR2613		
Description	Quantity	Units	Unit Cost		Total	(with Pre-Plat Construction)			
						% Complete	Remaining		
SECTION 3 - COMMON DEVELOPMENT IMPROVEMENTS (Private or District and NOT Maintained by EPC)**									
ROADWAY IMPROVEMENTS									
Aggregate Base Course (135 lbs/cf)	3663.	CY	\$ 81.00	=	\$ 296,703.00		\$ 296,703.00		
Asphalt Pavement (4" thick)	21976.	SY	\$ 31.00	=	\$ 681,256.00		\$ 681,256.00		
Curb and Gutter, Type A (6" Vertical)	11346.	LF	\$ 49.00	=	\$ 555,954.00		\$ 555,954.00		
5" Sidewalk	5038.	SY	\$ 85.00	=	\$ 428,230.00		\$ 428,230.00		
Pedestrian Ramp	50.	EA	\$ 1,961.00	=	\$ 98,050.00		\$ 98,050.00		
				=	\$ -		\$ -		
STORM DRAIN IMPROVEMENTS (Exception: Permanent Pond/BMP shall be itemized under Section 1)									
Curb Inlet (Type R) L=5', Depth < 5'	20.	EA	\$ 8,814.00	=	\$ 176,280.00		\$ 176,280.00		
Curb Inlet (Type R) L=10', Depth < 5'	1.	EA	\$ 11,438.00	=	\$ 11,438.00		\$ 11,438.00		
HDPE/RCP Storm Main Pipe	2973.	LF	\$ 150.00	=	\$ 445,950.00		\$ 445,950.00		
Storm Sewer Manhole, Slab Base	23.	EA	\$ 9,314.00	=	\$ 214,222.00		\$ 214,222.00		
				=	\$ -		\$ -		
				=	\$ -		\$ -		
WATER SYSTEM IMPROVEMENTS									
Water Main Pipe (PVC), Size 8"	3123.	LF	\$ 90.00	=	\$ 281,070.00		\$ 281,070.00		
Water Main Pipe (Ductile Iron), Size 8"		LF	\$ 105.00	=	\$ -		\$ -		
Gate Valves, 8"	89.	EA	\$ 2,599.00	=	\$ 231,311.00		\$ 231,311.00		
Fire Hydrant Assembly, w/ all valves	13.	EA	\$ 9,228.00	=	\$ 119,964.00		\$ 119,964.00		
Water Service Line Installation, inc. tap and valves	468.	EA	\$ 1,852.00	=	\$ 866,736.00		\$ 866,736.00		
Fire Cistern Installation, complete		EA		=	\$ -		\$ -		
				=	\$ -		\$ -		
[insert items not listed but part of construction plans]									
				=	\$ -		\$ -		
SANITARY SEWER IMPROVEMENTS									
Sewer Main Pipe (PVC), Size 8"	2146.	LF	\$ 90.00	=	\$ 193,140.00		\$ 193,140.00		
Sanitary Sewer Manhole, Depth < 15 feet	11.	EA	\$ 6,136.00	=	\$ 67,496.00		\$ 67,496.00		
Sanitary Service Line Installation, complete		EA	\$ 1,962.00	=	\$ -		\$ -		
Sanitary Sewer Lift Station, complete		EA		=	\$ -		\$ -		
				=	\$ -		\$ -		
[insert items not listed but part of construction plans]									
				=	\$ -		\$ -		
LANDSCAPING IMPROVEMENTS (For subdivision specific condition of approval, or PUD)									
SEE SEPARATE TABLE FOR LANDSCAPE IMPS.	1.	EA	\$777,247.00	=	\$ 777,247.00		\$ 777,247.00		
		EA		=	\$ -		\$ -		
		EA		=	\$ -		\$ -		
		EA		=	\$ -		\$ -		
		EA		=	\$ -		\$ -		
** - Section 3 is not subject to defect warranty requirements				Section 3 Subtotal	=	\$ 5,445,047.00		\$ 5,445,047.00	
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS		=	\$ -		\$ -		
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS		=	\$ -		\$ -		
Total Construction Financial Assurance						\$	5,862,997.20		
(Sum of all section subtotals plus as-builts and pond/BMP certification)									
Total Remaining Construction Financial Assurance (with Pre-Plat Construction)						\$	5,862,997.20		
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)									
Total Defect Warranty Financial Assurance						\$	68,326.40		
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)									

Approval	
I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.	
	
Engineer (P.E. Seal Required)	
	8/14/2026
Approved by Owner / Applicant	Date
Approved by El Paso County Engineer / ECM Administrator	Date