### STANDARD NOTES FOR EL PASO OCUNTY GRADING AND EROSION CONTROL PLANS

- 1. CONSTRUCTION MAY NOT COMMENCE UNTIL A CONSTRUCTION PERMIT IS OBTAINED FROM PLANNING AND COMMUNITY DEVELOPMENT AND A PRECONSTRUCTION CONFERENCE IS HELD WITH PLANNING AND COMMUNITY DEVELOPMENT INSPECTIONS.
- 2. STORMWATER DISCHARGES FROM CONSTRUCTION SITES SHALL NOT CAUSE OR THREATEN TO CAUSE POLLUTION, CONTAMINATION, OR DEGRADATION OF STATE WATERS. ALL WORK AND EARTH DISTURBANCE SHALL BE DONE IN A MANNER THAT MINIMIZES POLLUTION OF ANY ON-SITE OR OFF SITE WATERS, INCLUDING WETLANDS.
- 3. NOTWITHSTANDING ANYTHING DEPICTED IN THESE PLANS IN WORDS OR GRAPHIC REPRESENTATION, ALL DESIGN AND CONSTRUCTION RELATED TO ROADS, STORM DRAINAGE AND EROSION CONTROL SHALL CONFORM TO THE STANDARDS AND REQUIREMENTS OF THE MOST RECENT VERSION OF THE RELEVANT ADOPTED EL PASO COUNTY STANDARDS, INCLUDING THE LAND DEVELOPMENT CODE, THE ENGINEERING CRITERIA MANUAL, THE DRAINAGE CRITERIA MANUAL, AND THE DRAINAGE CRITERIA MANUAL VOLUME 2. ANY DEVIATIONS TO REGULATIONS AND STANDARDS MUST BE REQUESTED, AND APPROVED, IN WRITING.
- 4. A SEPARATE STORMWATER MANAGEMENT PLAN (SWMP) FOR THIS PROJECT SHALL BE COMPLETED AND AN EROSION AND STORMWATER QUALITY CONTROL PERMIT (ESQCP) ISSUED PRIOR TO COMMENCING CONSTRUCTION. DURING CONSTRUCTION THE SWMP IS THE RESPONSIBILITY OF THE DESIGNATED STORMWATER MANAGER, SHALL BE LOCATED ON SITE AT ALL TIMES AND SHALL BE KEPT UP TO DATE WITH WORK PROGRESS AND CHANGES IN THE FIELD.
- 5. ONCE THE ESQCP HAS BEEN ISSUED, THE CONTRACTOR MAY INSTALL THE INITIAL STAGE EROSION AND SEDIMENT CONTROL BMPS AS INDICATED ON THE GEC. A PRECONSTRUCTION MEETING BETWEEN THE CONTRACTOR, ENGINEER, AND EL PASO COUNTY WILL BE HELD PRIOR TO ANY CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE APPLICANT TO COORDINATE THE MEETING TIME AND PLACE WITH COUNTY DSD INSPECTIONS STAFF.
- 6. SOIL EROSION CONTROL MEASURES FOR ALL SLOPES, CHANNELS, DITCHES, OR ANY DISTURBED LAND AREA SHALL BE COMPLETED WITHIN 21 CALENDAR DAYS AFTER FINAL GRADING, OR FINAL EARTH DISTURBANCE, HAS BEEN COMPLETED. DISTURBED AREAS AND STOCKPILES WHICH ARE NOT AT FINAL GRADE BUT WILL REMAIN DORMANT FOR LONGER THAN 30 DAYS SHALL ALSO BE MULCHED WITHIN 21 DAYS AFTER INTERIM GRADING. AN AREA THAT IS GOING TO REMAIN IN AN INTERIM STATE FOR MORE THAN 60 DAYS SHALL ALSO BE SEEDED. ALL TEMPORARY SOIL EROSION CONTROL MEASURES AND BMPS SHALL BE MAINTAINED UNTIL PERMANENT SOIL EROSION CONTROL MEASURES ARE IMPLEMENTED AND ESTABLISHED.
- 7. TEMPORARY SOIL EROSION CONTROL FACILITIES SHALL BE REMOVED AND EARTH DISTURBANCE AREAS GRADED AND STABILIZED WITH PERMANENT SOIL EROSION CONTROL MEASURES PURSUANT TO STANDARDS AND SPECIFICATION PRESCRIBED IN THE DCM VOLUME II AND THE ENGINEERING CRITERIA MANUAL (ECM) APPENDIX I.
- 8. ALL PERSONS ENGAGED IN EARTH DISTURBANCE SHALL IMPLEMENT AND MAINTAIN ACCEPTABLE SOIL EROSION AND SEDIMENT CONTROL MEASURES INCLUDING BMPS IN CONFORMANCE WITH THE EROSION CONTROL TECHNICAL STANDARDS OF THE DRAINAGE CRITERIA MANUAL (DCM) VOLUME II AND IN ACCORDANCE WITH THE STORMWATER MANAGEMENT PLAN (SWMP).
- 9. ALL TEMPORARY EROSION CONTROL FACILITIES INCLUDING BMPS AND ALL PERMANENT FACILITIES INTENDED TO CONTROL EROSION OF ANY EARTH DISTURBANCE OPERATIONS, SHALL BE INSTALLED AS DEFINED IN THE APPROVED PLANS, THESWMP AND THE DCM VOLUME II AND MAINTAINED THROUGHOUT THE DURATION OF THE EARTH DISTURBANCE OPERATION.
- 10. ANY EARTH DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER SO AS TO EFFECTIVELY REDUCE ACCELERATED SOIL EROSION AND RESULTING SEDIMENTATION. ALL DISTURBANCES SHALL BE DESIGNED, CONSTRUCTED, AND COMPLETED SO THAT THE EXPOSED AREA OF ANY DISTURBED LAND SHALL BE LIMITED TO THE SHORTEST PRACTICAL PERIOD OF TIME.
- 11. ANY TEMPORARY OR PERMANENT FACILITY DESIGNED AND CONSTRUCTED FOR THE CONVEYANCE OF STORMWATER AROUND, THROUGH, OR FROM THE EARTH DISTURBANCE AREA SHALL BE DESIGNED TO LIMIT THE DISCHARGE TO A NON-EROSIVE VELOCITY.
- 12. CONCRETE WASH WATER SHALL BE CONTAINED AND DISPOSED OF IN ACCORDANCE WITH THE SWMP. NO WASH WATER SHALL BE DISCHARGED TO OR ALLOWED TO RUNOFF TO STATE WATERS, INCLUDING ANY SURFACE OR SUBSURFACE STORM DRAINAGE SYSTEM OR FACILITIES.
- 13. EROSION CONTROL BLANKETING IS TO BE USED ON SLOPES STEEPER THAN 3:1.
- 14. BUILDING, CONSTRUCTION, EXCAVATION, OR OTHER WASTE MATERIALS SHALL NOT BE TEMPORARILY PLACED OR STORED IN THE STREET, ALLEY, OR OTHER PUBLIC WAY, UNLESS IN ACCORDANCE WITH AN APPROVED TRAFFIC CONTROL PLAN. BMP'S MAY BE REQUIRED BY EL PASO COUNTY ENGINEERING IF DEEMED NECESSARY, BASED ON SPECIFIC CONDITIONS AND CIRCUMSTANCES.
- 15. VEHICLE TRACKING OF SOILS AND CONSTRUCTION DEBRIS OFF-SITE SHALL BE MINIMIZED.

  MATERIALS TRACKED OFFSITE SHALL BE CLEANED UP AND PROPERLY DISPOSED OF IMMEDIATELY.
- 16. CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL WASTES FROM THE CONSTRUCTION SITE FOR DISPOSAL IN ACCORDANCE WITH LOCAL AND STATE REGULATORY REQUIREMENTS. NO CONSTRUCTION DEBRIS, TREE SLASH, BUILDING MATERIAL WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURIED, DUMPED, OR DISCHARGED AT THE SITE.
- 17. THE OWNER, SITE DEVELOPER, CONTRACTOR, AND/OR THEIR AUTHORIZED AGENTS SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL CONSTRUCTION DEBRIS, DIRT, TRASH, ROCK, SEDIMENT, AND SAND THAT MAY ACCUMULATE IN THE STORM SEWER OR OTHER DRAINAGE CONVEYANCE SYSTEM AND STORMWATER APPURTENANCES AS A RESULT OF SITE DEVELOPMENT.
- 18. THE QUANTITY OF MATERIALS STORED ON THE PROJECT SITE SHALL BE LIMITED, AS MUCH AS


PRACTICAL, TO THAT QUANTITY REQUIRED TO PERFORM THE WORK IN AN ORDERLY SEQUENCE. ALL MATERIALS STORED ON-SITE SHALL BE STORED IN A NEAT, ORDERLY MANNER, IN THEIR ORIGINAL CONTAINERS, WITH ORIGINAL MANUFACTURER'S LABELS.

- 19. NO CHEMICALS ARE TO BE USED BY THE CONTRACTOR, WHICH HAVE THE POTENTIAL TO BE RELEASED IN STORMWATER UNLESS PERMISSION FOR THE USE OF A SPECIFIC CHEMICAL IS GRANTED IN WRITING BY THE ECM ADMINISTRATOR. IN GRANTING THE USE OF SUCH CHEMICALS, SPECIAL CONDITIONS AND MONITORING MAY BE REQUIRED.
- 20. BULK STORAGE STRUCTURES FOR PETROLEUM PRODUCTS AND OTHER CHEMICALS SHALL HAVE ADEQUATE PROTECTION SO AS TO CONTAIN ALL SPILLS AND PREVENT ANY SPILLED MATERIAL FROM ENTERING STATE WATERS, INCLUDING ANY SURFACE OR SUBSURFACE STORM DRAINAGE SYSTEM OR
- 21. NO PERSON SHALL CAUSE THE IMPEDIMENT OF STORMWATER FLOW IN THE FLOW LINE OF THE CURB AND GUTTER OR IN THE DITCHLINE.
- 22. INDIVIDUALS SHALL COMPLY WITH THE "COLORADO WATER QUALITY CONTROL ACT" (TITLE 25, ARTICLE 8, CRS), AND THE "CLEAN WATER ACT" (33 USC 1344), IN ADDITION TO THE REQUIREMENTS INCLUDED IN THE DCM VOLUME II AND THE ECM APPENDIX I. ALL APPROPRIATE PERMITS MUST BE OBTAINED BY THE CONTRACTOR PRIOR TO CONSTRUCTION (NPDES, FLOODPLAIN, 404, FUGITIVE DUST, ETC.). IN THE EVENT OF CONFLICTS BETWEEN THESE REQUIREMENTS AND LAWS, RULES, OR REGULATIONS OF OTHER FEDERAL, STATE, OR
- COUNTY AGENCIES, THE MORE RESTRICTIVE LAWS, RULES, OR REGULATIONS SHALL APPLY.
- 23. ALL CONSTRUCTION TRAFFIC MUST ENTER/EXIT THE SITE AT APPROVED CONSTRUCTION ACCESS POINTS.
- 24. PRIOR TO ACTUAL CONSTRUCTION THE PERMITEE SHALL VERIFY THE LOCATION OF EXISTING UTILITIES.
- 25. A WATER SOURCE SHALL BE AVAILABLE ON SITE DURING EARTHWORK OPERATIONS AND UTILIZED AS REQUIRED TO MINIMIZE DUST FROM EARTHWORK EQUIPMENT AND WIND.
- 26. THE SOILS REPORT FOR THIS SITE HAS BEEN PREPARED BY KLEINFELDER (PROJ. NO. 20172793.001A, 12-21-16) AND SHALL BE CONSIDERED A PART OF THESE PLANS.
- 27. AT LEAST TEN DAYS PRIOR TO THE ANTICIPATED START OF CONSTRUCTION, FOR PROJECTS THAT WILL DISTURB 1 ACRE OR MORE, THE OWNER OR OPERATOR OF CONSTRUCTION ACTIVITY SHALL SUBMIT A PERMIT APPLICATION FOR STORMWATER DISCHARGE TO THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT, WATER QUALITY DIVISION. THE APPLICATION CONTAINS CERTIFICATION OF COMPLETION OF A STORMWATER MANAGEMENT PLAN (SWMP), OF WHICH THIS GRADING AND EROSION CONTROL PLAN MAY BE A PART. FOR INFORMATION OR APPLICATION MATERIALS CONTACT:

COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT WATER QUALITY CONTROL DIVISION WQCD - PERMITS 4300 CHERRY CREEK DRIVE SOUTH DENVER, CO 80246-1530

ATTN: PERMITS UNIT

# GRADING, EROSION AND SEDIMENT CONTROL PLANS FOR MONUMENT HILL BUSINESS CENTER EL PASO COUNTY, COLORADO



### SHEET INDEX

1	C2.0	GESC COVER SHEET
2	C2.1	GESC PLAN
4	C1.4	STORM SEWER PLAN AND PROFILE
5	C1.5	STORM SEWER DETAILS

### CIVIL ENGINEER

greg@kelleydev.com

KELLY DEVELOPMENT SERVICES, LLC 9301 SCRUB OAK DRIVE LONE TREE, COLORADO 80124 PHONE: 303-888-6338 CONTACT: GREG S. KELLY, P. E.

DEVELOPER
STAN SIEVERS
MONUMENT HILL BUSINESS PARK, LLC
16152 OLD FOREST POINT, UNIT 2-202
MONUMENT, CO 80132
PHONE: (720) 219-2366

stansrsco@aol.com

### **LEGAL DESCRIPTION:**

LOT 3. GREATER EUROPE MISSION SUBDIVISION FILING NO. 1

# PROJECT BENCHMARK:

SOUTHEASTERLY CORNER OF LOT 3, GREATER EUROPE MISSION SUBDIVISION FILING NO. 1 RECORDED UNDER RECEPTION NO. 200033900 IN THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER BEING A 1-1/2" ALUMINUM CAP STAMPED "LS 17502". ASSUMED ELEVATION = 7109.99'.

# PROJECT BASIS OF BEARING:

BEARINGS ARE BASED ON THE EASTERLY LINE OF LOT 3, GREATER EUROPE MISSION SUBDIVISION FILING NO. 1 RECORDED UNDER RECEPTION NO. 200033900 IN THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER BEING MONUMENTED BY AN ALUMINUM CAP STAMPED "LS 38252" AT THE NORTH AND A 1-1/2" ALUMINUM CAP STAMPED "LS 17502" AT THE SOUTH, BEARING S07°25'35"E.

# SECTION LORNER BENGMARK ELECTRICAL CORDUIT ICC GAS GAS UGT UNDERGROUND TELEPHONE FO UNDERGROUND TELEPHONE FO UNDERGROUND CAME FO THE LINE WATER MANN 6"W 6"W 6"WATER MANN 12"W 12"WATER MANN 16"W 16"WATER MANN 112"W 12"WATER MANN 112"W 12"WATER MANN 116"W WATER MANN 110"WATER MANN MATER MANN MATER MANN MATER MANN 110"SS 110"SS 112"SS 112"SS 112"SS 115"SS SANITARY MANN 115"SANITARY MANN 115"SS SANITARY MANN 110"SS 112"SS SANITARY MANN 115"SS SANITARY MANN SANITARY MANN SANITARY MANN SANITARY MANN

LEGEND

**EXISTING** 

**PROPOSED** 

### KNOV CRITI PLAN NEGL PLAN

FOR AND ON BEHALF OF KELLY DEVELOPMENT SERVICES. LLC

drawn by

designed by

approved by

REVISION DESCRIPTION

1508.01

# ENGINEER'S STATEMENT:

THIS GRADING AND EROSION CONTROL PLAN WAS PREPARED UNDER MY DIRECTION AND SUPERVISION AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. SAID PLAN HAS BEEN PREPARED ACCORDING TO THE CRITERIA ESTABLISHED BY THE COUNTY FOR GRADING AND EROSION CONTROL PLANS. I ACCEPT RESPONSIBILITY FOR ANY LIABILITY CAUSED BY ANY NEGLIGENT ACTS, ERRORS OR OMISSIONS ON MY PART IN PREPARING THIS PLAN.

GREG KELLY, P.E. #15813

01/12/2017 DATE

# OWNER/DEVELOPER'S STATEMENT:

I, THE OWNER/DEVELOPER HAVE READ AND WILL COMPLY WITH THE REQUIREMENTS OF THE GRADING AND EROSION CONTROL PLAN.

STAN SIEVERS
MONUMENT HILL BUSINESS PARK, LLC
16152 OLD FOREST POINT, UNIT 2-202
MONUMENT, CO 80132

02/07/18 DATE

DATE

# EL PASO COUNTY:

COUNTY PLAN REVIEW IS PROVIDED ONLY FOR GENERAL CONFORMANCE WITH COUNTY DESIGN CRITERIA. THE COUNTY IS NOT RESPONSIBLE FOR THE ACCURACY AND ADEQUACY OF THE DESIGN, DIMENSIONS, AND/OR ELEVATIONS WHICH SHALL BE CONFIRMED AT THE JOB SITE. THE COUNTY THROUGH THE APPROVAL OF THIS DOCUMENT ASSUMES NO RESPONSIBILITY FOR COMPLETENESS AND/OR ACCURACY OF THIS DOCUMENT.

FILED IN ACCORDANCE WITH THE REQUIREMENTS OF THE EL PASO COUNTY LAND DEVELOPMENT CODE, DRAINAGE CRITERIA MANUAL, VOLUMES 1 AND 2, AND ENGINEERING CRITERIA MANUAL AS AMENDED.

IN ACCORDANCE WITH ECM SECTION 1.12, THESE CONSTRUCTION DOCUMENTS WILL BE VALID FOR CONSTRUCTION FOR A PERIOD OF 2 YEARS FROM THE DATE SIGNED BU EL PASO COUNTY ENGINEER. IF CONSTRUCTION HAS NOT STARTED WITHIN THOSE 2 YEARS, THE PLANS WILL NEED TO BE RESUBMITTED FOR APPROVAL, INCLUDING PAYMENT OF REVIEW FEES AT THE PLANNING AND COMMUNITY DEVELOPMENT DIRECTOR'S DISCRETION.

JENNIFER IRVINE, P.E.
COUNTY ENGINEER/ECM ADMINISTRATOR

By:Jennifer Irvine, County Engineer

DATE

Date:03/14/2018

El Paso County Department of Public Works

PCD PROJECT NO. PPR-17-007



THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND,

ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUCH CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

	#	DATE	
PREPARED FOR:	$\triangle$		
HOVER ARCHITECTURE	$\triangle$		
HOVER ARCHITECTURE	$\triangle$		
TROY KIRSCHMAN	$\triangle$		
8089 S. LINCOLN ST., SUITE 201 LITTLETON, CO 80122	р	roject no.	
PH: 720-773-2801		date	
FAX:		dwg.	

# MONUMENT HILL BUSINESS CENTER

LOT 3, GREATER EUROPE MISSION FILING NO. 1 EL PASO COUNTY, CO

GESC COVER SHEET

# KELLY DEVELOPMENT SERVICES, LLC

9301 SCRUB OAK DR LONE TREE, CO 80124 303-888-6338 greg@kellydev.com SHEET NUMBER

SHEET 1
PROJECT NUMBER
1704.01


LOT 3, GREATER EUROPE MISSION SUBDIVISION FILING NO. 1


### PROJECT BENCHMARK:

SOUTHEASTERLY CORNER OF LOT 3, GREATER EUROPE MISSION SUBDIVISION FILING NO. 1 RECORDED UNDER RECEPTION NO. 200033900 IN THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER BEING A 1-1/2" ALUMINUM CAP STAMPED "LS 17502". ASSUMED ELEVATION = 7109.99'.


### PROJECT BASIS OF BEARING:

BEARINGS ARE BASED ON THE EASTERLY LINE OF LOT 3, GREATER EUROPE MISSION SUBDIVISION FILING NO. 1 RECORDED UNDER RECEPTION NO. 200033900 IN THE RECORDS OF THE EL PASO COUNTY CLERK AND RECORDER BEING MONUMENTED BY AN ALUMINUM CAP STAMPED "LS 38252" AT THE NORTH AND A 1-1/2" ALUMINUM CAP STAMPED "LS 17502" AT THE SOUTH, BEARING S07°25'35"E.





	BMP SUMMARY TABLE									
	SILT FENCE	STABLIZED STAGING AREA	CONCRETE WASHOUT AREA	VTC WITH WHEEL WASH	INLET PROTECTION	SEDIMENT BASIN	SEEDING & MULCHING	EROSION CONTROL BLANKET	CHECK DAM	ROCK SOCKS
INSTALLATION	PRIOR TO GRADING	IMMEDIATELY AFTER SITE GRADING	IMMEDIATELY AFTER SITE GRADING	IMMEDIATELY AFTER SITE GRADING	IMMEDIATELY AFTER SITE GRADING	IMMEDIATELY AFTER SITE GRADING	IMMEDIATELY AFTER STORM SEWER CONSTRUCTION	IMMEDIATELY AFTER SITE GRADING	PRIOR TO GRADING	PRIOR TO GRADING
REMOVAL	AFTER FINAL STABLIZATION	AT THE TIME OF SITE PAVING	AFTER COMPLETTION OF SITE CONCRETE	AT THE TIME OF SITE PAVING	AFTER FINAL STABILIZATION	AT THE TIME OF FINAL STABILIZATION	PERMANENT	AFTER FINAL STABILIZATION	AFTER FINAL STABILIZATION	AFTER FINAL STABILIZATION



# BMP LEGEND

	$\square \square \bigcirc \bigcirc \bigcirc \bigcirc$	CHECK DAM, PER DETAIL SHEET
	IP	INLET PROTECTION, PER DETAIL SHEET
×	—X— (SF)	SILT FENCE, PER DETAIL SHEET
	VTC	VEHICLE TRACKING CONTROL, PER DETAIL SHEE
	(LOC)	LIMITS OF CONSTRUCTION
	CWA)	CONCRETE WASHOUT AREA, PER DETAIL
	SSA	STABILIZED STAGING AREA, PER DETAIL SHEET
	RS	ROCK SOCKS

SEED AND MULCH

ECB) EROSION CONTROL BLANKET

# SEEDMIX:

20% ANNUAL RYEGRASS
15% SLENDER WHEATGRASS
12% CRESTED WHEATGRASS
10% MOUNTAIN BROME
10% HARD FESCUE
10% CANADA BLUEGRASS
6% SIDEOATS GRAMA
6% BIG BLUESTEM
5% BLUE GRAMA (COATED)
5% SWITCHGRASS
1% SAND DROPSEED

SEEDING RATE: BORADCAST: 20-25 LBS/AC LOLIUM MULTIFLORUM
AGROPYRON TRACHYCAULUM
AGROPYRON CRISTATUM
BROMUS MARGINATUS
FESTUCA OVINA SPP. DURIUSCULA
POA COMPRESSA
BOUTELOUA CURTIPENDULA
ANDROPOGON GERARDII
BOUTELOUA GRACILIS
PANICUM VIRGATUM
SPOROBOLUS CRYPTANDRUS

DRILLED: 15-20 LBS/AC OVERSEEDING



COLORADO 811.

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND,

THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUCH CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

PREPARED FOR:	<u>#</u>
HOVER ARCHITECTURE	Z
TROY KIRSCHMAN 8089 S. LINCOLN ST., SUITE 201	<u> </u>
LITTLETON, CO 80122 PH: 720-773-2801	
FAX:	

	#	DATE	REVISION DESCRIPTION		BY
	$\triangle$				
	$\triangle$				
=					
۱ 1					
2	pro	oject no.	1508.01	drawn by	
1		date	10/19/2017 — 8:00 am	designed by	
		dwg.	C2.1 — Erosion Control Plan2.dwg	approved by	

# MONUMENT HILL BUSINESS CENTER

LOT 3, GREATER EUROPE MISSION FILING NO. 1 EL PASO COUNTY, CO

GESC PLAN

KELLY DEVELOPMENT SERVICES, LLC
9301 SCRUB OAK DR
LONE TREE, CO 80124


C2.1

SHEET 2
PROJECT NUMBER
1704.01

SHEET NUMBER


[C-MA.dwg] [C-PN.dwg] [C-TO.dwg] [C-UT.dwg] [V-MA.dwg] [V-PN.dwg] [V-TO.dwg] [V-UT.dwg] [VICMAP.c

303-888-6338 greg@kellydev.com



CAUTION NOTICE TO CONTRACTORS THE CONTRACTOR IS SPECIFICALLY COLORADO 811 CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, HERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT

O BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUCH CALL 811 T LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE PH: CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.



# MONUMENT HILL BUSINESS CENTER

LOT 3, GREATER EUROPE MISSION FILING NO. 1 EL PASO COUNTY, CO

**KELLY DEVELOPMENT SERVICES, LLC** 9301 SCRUB OAK DR **LONE TREE, CO 80124** 

303-888-6338


greg@kellydev.com

SHEET NUMBER

SHEET 2 PROJECT NUMBER 1704.01

EPC 3.14.18

**EROSION CONTROL DETAILS** 



CAUTION NOTICE TO CONTRACTORS THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR COLORADO 811 CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF

THE VARIOUS UTILITY COMPANIES AND, HERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT O BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUCH CALL 811 T LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

PREPARED FOR: HOVER ARCHITECTURE TROY KIRSCHMAN 8089 S. LINCOLN ST., SUITE 201 LITTLETON, CO 80122 PH: 720-773-2801

FAX:

	# DATE REVISION DESCRIPTION				BY
	$\triangle$				
	$\triangle$				
I	$\triangle$				
2	р	roject no.	1508.01	drawn by	
		date	2/15/2017 - 1:07 pm	designed by	
		dwg.	C2.3 — Erosion Control Details.dwg	approved by	

# MONUMENT HILL BUSINESS CENTER

LOT 3, GREATER EUROPE MISSION FILING NO. 1 EL PASO COUNTY, CO

**EROSION CONTROL DETAILS** 


**KELLY DEVELOPMENT SERVICES, LLC** 9301 SCRUB OAK DR

**LONE TREE, CO 80124** 303-888-6338 greg@kellydev.com

SHEET 3 PROJECT NUMBER 1704.01

SHEET NUMBER

EPC 3.14.18



drawn by

designed by

approved by

CAUTIONED THAT THE LOCATION AND/OR

CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS

	# DATE	REVISION DESCRIPTION	
PREPARED FOR:	<u> 1</u> 01/28/20	REVISE STRUCTURE & WEIR ELEVS. PER REVISED	GRADING
LIOVED ADOLUTECTUDE	$\triangle$		
HOVER ARCHITECTURE	$\triangle$		
TROY KIRSCHMAN			
8089 S. LINCOLN ST., SUITE 201			
LITTLETON, CO 80122	project no.	1508.01	drawn
PH: 720-773-2801	date		designed
FAX:	dwg.		approved

# MONUMENT HILL BUSINESS PARK

LOT 3, GREATER EUROPE MISSION FILING NO. 1 EL PASO COUNTY, CO

STORM SEWER CONSTRUCTION DETAILS

# **KELLY DEVELOPMENT SERVICES, LLC**

9301 SCRUB OAK DR LONE TREE, CO 80124 303-888-6338 greg@kellydev.com

SHEET NUMBER

SHEET 5 PROJECT NUMBER 1704.01