



# SITE SPREADER<sup>®</sup>

## Truck Mount Site Spreader International Model SST 16/20

Spreader for Cement, flyash, quicklime and other dry, flowable materials



Spreader with high capacity filter can



Fill directly from the bulk tanker



Spreader with popup filters on roof



Fits 40' HC container

### Standard Features

- Designed to fit into a standard shipping container
- Mounted on customer supplied chassis
- Automatic or manual rate controller
- 15 ton "half-tanker" or 27 ton full tanker capacity
- Sealed, reinforced 7-ga steel hopper
- 30" [762 mm] hardened D667KC conveyor chain
- Hi-torque, hi-speed hydraulics
- Hydraulic rear metering gate
- 4" [101.6 mm] Pneumatic fill
- High flow low pressure relief valve
- High capacity filter can
- 8 ft [2.43 m] Hydraulic spreading auger w/ dust curtains
- Side access panels
- Spread rate: up to 120 lb/yd<sup>2</sup> @ 2mph, 80 lb/yd<sup>2</sup> @ 3 mph  
[65 kg/m<sup>2</sup> @ 3.2 kph, 43 kg/m<sup>2</sup> @ 4.8 kph]

### Popular Options

- 10 ft [3.04m] or 12 ft [3.65m] Spreading auger
- 24" Manway on roof for top-loading
- Popup filter bags on roof (instead of filter can)
- Vulcan (6 load cell) digital scale

Dimensions	SST 16	SST 20
Volume, ft <sup>3</sup> [m <sup>3</sup> ]	475 [13.5]	741 [20.9]
Length, ft [mm]	16 [4877]	20 [6096]
Width, in [mm]	86 [2184]	86 [2184]
Height, in [mm]	84 [2134]	97 [2464]
Truck C-A, ft [mm]	11.7 [3566]	15 [4572]

### **Stoltz Mfg., LLC**

121 Morgan Way, PO Box 527  
Morgantown, PA 19543 USA

+610-286-5146

800-843-8731

[www.stoltzmf.com](http://www.stoltzmf.com)