

EROSION CONTROL LEGEND

KEY	TITLE	SYMBOL	IMPLEMENTATION PHASE
SF	SILT FENCE	— SF —	FINAL
CF	CONSTRUCTION FENCE	— CF —	FINAL
CIP	CULVERT INLET PROTECTION		FINAL
IP	INLET PROTECTION		FINAL
SBB	STRAW BALE BARRIER		FINAL
SP	STOCKPILE PROTECTION		FINAL
VTC	VEHICLE TRACKING CONTROL		FINAL
CWA	CONCRETE WASHOUT AREA		FINAL
SSA	STABILIZED STAGING AREA		FINAL
TSM	TEMPORARY SEEDING AND MULCHING		FINAL

GRADING LEGEND

8' EXISTING CONTOUR	6810	100-YEAR HWL HEC-RAS ANALYSIS
1' EXISTING CONTOUR	6802	
5' PROPED CONTOUR	6810	
1' PROPED CONTOUR	6802	
LIMITS OF DISTURBANCE/CONSTRUCTION BOUNDARY		
SUBDIVISION BOUNDARY		
CUT/FILL LINE		
DIRECTION OF SURFACE FLOW		
HIGH POINT	HPX	
LOW POINT	LPX	
A LOT	"A"	
B LOT	"B"	
WALK OUT LOT MODIFIED	"WO"	
GARDEN LEVEL LOT MODIFIED	"G"	
100-Y FEMA FLOODPLAIN		
100-Y HWL PER HECRAS ANALYSIS		
AREAS OF DE-WATERING		

WETLANDS LEGEND

EXISTING WETLANDS	
TEMPORARY WETLAND DISTURBANCE	
PERMANENT WETLAND DISTURBANCE	


VEGETATION NOTE:

EXISTING VEGETATION CONSISTS OF NATIVE PRAIRIE GRASSES AND SHRUBS WITH FAIR TO GOOD COVERAGE OF 50% TO 70%

NOTES:
NO BATCH PLANTS ARE PROPOSED
ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR

RUNOFF REDUCTION LEGEND

UNCONNECTED IMPERVIOUS AREA	
RECEIVING PERVIOUS AREA	
EXCLUDED UNDEVELOPED PERVIOUS AREA PER THE EXCLUSION IN ECM APPENDIX 1.7.1.B.7 - SITES WITH LAND DISTURBANCE TO UNDEVELOPED LAND THAT WILL REMAIN UNDEVELOPED	



REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
COLORADO SPRINGS, CO 80949
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150

Terra Nova
Engineering, Inc.
Civil Engineering

721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.terra-nova.com

WATERBURY FILING NO. 1

CONSTRUCTION SET
GRADING AND EROSION CONTROL PLAN
FINAL EROSION CONTROL PLAN 1

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA

H-SCALE 1" = 100'
V-SCALE N/A

JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 2 OF 39

QUENTIN ARMOJO
COLORADO P.E. NO. 37170

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

GENERAL NOTES

- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITIES ALONG THE SITE. THE OMISSION FROM OR THE INCLUSION OF UTILITY LOCATIONS ON THE PLANS IS NOT TO BE CONSIDERED AS THE NON-EXISTENCE OF OR A DEFINITE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- THE CONTRACTOR WILL TAKE THE NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES, BUILDINGS, FENCES, AND ROADWAYS FROM DAMAGE DUE TO THIS OPERATION. ANY DAMAGE TO THE ABOVE WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE, AND ANY SERVICE DISRUPTION WILL BE SETTLED BY THE CONTRACTOR.
- BULK GRADING SHALL BE COMPLETED TO A SUBGRADE TOLERANCE OF PLUS OR MINUS 0.2'.
- CONTRACTOR TO OBTAIN COPIES OF THE SOILS REPORT FROM THE GEOTECHNICAL ENGINEER AND TO BE KEPT ONSITE DURING ALL EARTHWORK OPERATIONS.
- MAXIMUM CUT/FILL SLOPES SHALL NOT EXCEED 3:1, UNLESS OTHERWISE NOTED.
- ALL BOTOM OF WALL (BW) CALLOUTS ARE FOR THE BOTTOM OF WALL AT GRADE. THEY DO NOT REPRESENT THE BOTTOM OF THE CONSTRUCTED WALL OR FOOTING, WHICH IS NOT SPECIFIED ON THESE PLANS.

SOIL TYPES

ONSITE SOILS ARE HYDROLOGIC GROUPS "A" (COLUMBINE GRAVELLY SANDY LOAM) AND "B" (STAPLETON SANDY LOAM) (PER NRCS WEB SOIL SURVEY MAP)

AREA OF DISTURBANCE


ESTIMATED AREA OF DISTURBANCE = 68.70 ACRES

EARTHWORK VOLUMES

ESTIMATED CUT = 73,990 CY, ESTIMATED FILL = 287,149* CY, NET = 213,159 CY <FILL>
 *20% COMPACTION ASSUMED FOR PLACEMENT OF FILL

BLACK SQUIRREL CREEK NOTE:

IF AN UNDERDRAIN SYSTEMS ARE NEEDED FOR HOMES LOCATED WITH HIGH GROUNDWATER WILL NEED TO DISCHARGE INTO A GROUNDWATER RECHARGE FACILITY, NOT A STORM DRAIN SYSTEM.




NOTES:

NO BATCH PLANTS ARE PROPOSED
 ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR


GRADING LEGEND

- 8' EXISTING CONTOUR
- 1' EXISTING CONTOUR
- 5' PROPED CONTOUR
- 1' PROPED CONTOUR
- LIMITS OF DISTURBANCE/ CONSTRUCTION BOUNDARY
- SUBDIVISION BOUNDARY
- CUT/FILL LINE
- DIRECTION OF SURFACE FLOW
- HIGH POINT
- LOW POINT
- A LOT
- B LOT
- WALK OUT LOT MODIFIED
- GARDEN LEVEL LOT MODIFIED




WETLANDS LEGEND

- EXISTING WETLANDS
- TEMPORARY WETLAND DISTURBANCE
- PERMANENT WETLAND DISTURBANCE



- 100-Y FEMA FLOODPLAIN
- 100-Y HWL PER HECRAS ANLYSIS
- AREAS OF DE-WATERING




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN ARMUJO
 COLORADO P.E. NO. 37170

REVISIONS	NO.	DESCRIPTION	DATE
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY REVIEW AGENCIES OR TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND SITE SPECIFIC BY WRITTEN AUTHORIZATION.			
PREPARED FOR: 4-WAY RANCH JOINT VENTURE ATTN: PETER MARTZ P.O. BOX 50223 COLORADO SPRINGS, CO 80949 719-491-3150			
Terra Nova Engineering, Inc. Civil/Environmental Engineers 721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnecinc.com			
WATERBURY FILING NO. 1 CONSTRUCTION SET GRADING EROSION & CONTROL PLAN FINAL EROSION CONTROL PLAN 2			
DESIGNED BY DLF DRAWN BY QNA CHECKED BY QNA H-SCALE N/A V-SCALE N/A JOB NO. 1715.00 DATE ISSUED 2/6/23 SHEET NO. 3 OF 39			


SC-6 Inlet Protection (IP)



IP-1. BLOCK AND ROCK SOCK SUMP OR ON GRADE INLET PROTECTION

BLOCK AND CURB SOCK INLET PROTECTION INSTALLATION NOTES

- SEE ROCK SOCK DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.
- CONCRETE "CINDER" BLOCKS SHALL BE LAID ON THEIR SIDES AROUND THE INLET IN A SINGLE ROW, ABUTTING ONE ANOTHER WITH THE OPEN END FACING AWAY FROM THE CURB.
- GRAVEL BAGS SHALL BE PLACED AROUND CONCRETE BLOCKS, CLOSELY ABUTTING ONE ANOTHER AND JOINED TOGETHER IN ACCORDANCE WITH ROCK SOCK DESIGN DETAIL.



IP-2. CURB ROCK SOCKS UPSTREAM OF INLET PROTECTION

CURB ROCK SOCK INLET PROTECTION INSTALLATION NOTES

- SEE ROCK SOCK DESIGN DETAIL INSTALLATION REQUIREMENTS.
- PLACEMENT OF THE SOCK SHALL BE APPROXIMATELY 30 DEGREES FROM PERPENDICULAR IN THE OPPOSITE DIRECTION OF FLOW.
- SOCKS ARE TO BE FLUSH WITH THE CURB AND SPACED A MINIMUM OF 5 FEET APART.
- AT LEAST TWO CURB SOCKS IN SERIES ARE REQUIRED UPSTREAM OF ON-GRADE INLETS.

SC-6 Inlet Protection (IP)

GENERAL INLET PROTECTION INSTALLATION NOTES

- SEE PLAN VIEW FOR:
- LOCATION OF INLET PROTECTION.
- TYPE OF INLET PROTECTION (IP-1, IP-2, IP-3, IP-4, IP-5, IP-6)
- INLET PROTECTION SHALL BE INSTALLED PROMPTLY AFTER INLET CONSTRUCTION OR PAVING IS COMPLETE (TYPICALLY WITHIN 48 HOURS). IF A RAINFALL/RUNOFF EVENT IS FORECAST, INSTALL INLET PROTECTION PRIOR TO ONSET OF EVENT.
- MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

INLET PROTECTION MAINTENANCE NOTES


- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
- SEDIMENT ACCUMULATED UPSTREAM OF INLET PROTECTION SHALL BE REMOVED AS NECESSARY TO MAINTAIN BMP EFFECTIVENESS, TYPICALLY WHEN STORAGE VOLUME REACHES 50% OF CAPACITY, A DEPTH OF 6" WHEN SILT FENCE IS USED, OR 1/4 OF THE HEIGHT FOR STRAW BALES.
- INLET PROTECTION IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED, UNLESS THE LOCAL JURISDICTION APPROVES EARLIER REMOVAL OF INLET PROTECTION IN STREETS.
- WHEN INLET PROTECTION AT AREA INLETS IS REMOVED, THE DISTURBED AREA SHALL BE COVERED WITH TOP SOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)


NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

NOTE: THE DETAILS INCLUDED WITH THIS FACT SHEET SHOW COMMONLY USED, CONVENTIONAL METHODS OF INLET PROTECTION IN THE DENVER METROPOLITAN AREA. THERE ARE MANY PROPRIETARY INLET PROTECTION METHODS ON THE MARKET. UDFCD NEITHER ENDORSES NOR DISAPPROVES USE OF PROPRIETARY INLET PROTECTION; HOWEVER, IN THE EVENT PROPRIETARY METHODS ARE USED, THE APPROPRIATE DETAIL FROM THE MANUFACTURER MUST BE INCLUDED IN THE SWMP AND THE BMP MUST BE INSTALLED AND MAINTAINED AS SHOWN IN THE MANUFACTURER'S DETAILS.

NOTE: SOME MUNICIPALITIES DISCOURAGE OR PROHIBIT THE USE OF STRAW BALES FOR INLET PROTECTION. CHECK WITH LOCAL JURISDICTION TO DETERMINE IF STRAW BALE INLET PROTECTION IS ACCEPTABLE.



	Case 1	Case 2
Gravel Thickness	9"	3"
Filter Fabric	YES	NO



VEHICLE TRACKING INSTALLATION REQUIREMENTS

- ALL ENTRANCES TO THE CONSTRUCTION SITE ARE TO BE STABILIZED PRIOR TO CONSTRUCTION BEGINNING.
- CONSTRUCTION ENTRANCES ARE TO BE BUILT WITH AN APRON TO ALLOW FOR TURNING TRAFFIC, BUT SHOULD NOT BE BUILT OVER EXISTING PAVEMENT EXCEPT FOR A SLIGHT OVERLAP.
- AREAS TO BE STABILIZED ARE TO BE PROPERLY GRADED AND COMPACTED PRIOR TO LAYING DOWN GEOTEXTILE AND STONE.
- CONSTRUCTION ROADS, PARKING AREAS, LOADING/UNLOADING ZONES, STORAGE AREAS, AND STAGING AREAS ARE TO BE STABILIZED.
- CONSTRUCTION ROADS ARE TO BE BUILT TO CONFORM TO SITE GRADES, BUT SHOULD NOT HAVE SIDE SLOPES OR ROAD GRADES THAT ARE EXCESSIVELY STEEP.

VEHICLE TRACKING MAINTENANCE REQUIREMENTS

- REGULAR INSPECTIONS ARE TO BE MADE OF ALL STABILIZED AREAS, ESPECIALLY AFTER STORM EVENTS.
- STONES ARE TO BE REAPPLIED PERIODICALLY AND WHEN REPAIR IS NECESSARY.
- SEDIMENT TRACKED ONTO PAVED ROADS IS TO BE REMOVED DAILY BY SHOVELING OR SWEEPING. SEDIMENT IS NOT TO BE WASHED DOWN STORM SEWER DRAINS.
- STORM SEWER INLET PROTECTION IS TO BE IN PLACE, INSPECTED, AND CLEANED IF NECESSARY.
- OTHER ASSOCIATED SEDIMENT CONTROL MEASURES ARE TO BE INSPECTED TO ENSURE GOOD WORKING CONDITION.

Revegetation Chapter 14

Table 14-10. Recommended Seed Mix for Transition Areas¹

Common Name (Variety)	Scientific Name	Growth Season	Growth Form	Seeds/Lb	Lbs PLS/Acre Drilled	Lbs PLS/Acre Broadcast or Hydroseeded
Sheep fescue (Duras)	<i>Festuca ovina</i>	Cool	Bunch	680,000	1.3	2.6
Western wheatgrass (Ariba)	<i>Pascopyrum smithii</i>	Cool	Sod	110,000	7.9	15.8
Alkali sacaton	<i>Sporobolus airoides</i>	Warm	Bunch	1,758,000	0.5	1.0
Slender wheatgrass	<i>Elymus trachycaulus</i>	Cool	Bunch	159,000	5.5	11.0
Canadian bluegrass (Ruebens)	<i>Poa compressa</i>	Cool	Sod	2,500,000	0.3	0.6
Switchgrass (Pathfinder)	<i>Panicum virgatum</i>	Warm	Sod/Bunch	389,000	1.3	2.6
Annual rye	<i>Lolium multiflorum</i>	Cool	Cover crop	227,000	10.0	20.0
			TOTAL		26.8	53.6
Wildflowers						
Blanket flower	<i>Faillardia aristata</i>	---	---	132,000	0.25	0.50
Prairie coneflower	<i>Ratibida columnaris</i>	---	---	1,230,000	0.20	0.40
Purple prairie clover	<i>Petalostemum purpurea</i>	---	---	210,000	0.20	0.40
Gayfeather	<i>Liatris punctata</i>	---	---	138,000	0.06	0.12
Flax	<i>Linum lewisii</i>	---	---	293,000	0.20	0.40
Penstemon	<i>Penstemon strictus</i>	---	---	592,000	0.20	0.40
Yarrow	<i>Achillea millefolium</i>	---	---	2,770,000	0.03	0.06
			TOTAL		1.14	2.28

¹For side slopes or between wet and dry areas.
²Substitute 1.7 lbs PLS/acre of inland saltgrass (*Dactyloctenium aegyptium*) in salty soils.

SEED MIX FOR POND BOTTOMS

THE CITY OF COLORADO SPRINGS ENGINEERING DEPARTMENT GENERAL SPECIFICATIONS SHOULD BE USED AS A RESOURCE WHEN DEVELOPING TECHNICAL SPECIFICATIONS FOR RE-VEGETATION. GENERAL GUIDELINES AND RECOMMENDATIONS FOR RE-VEGETATION INCLUDE:


- SEED MIXTURES SHOULD BE SOWN AT THE PROPER TIME OF YEAR FOR THE MIXTURE. GENERALLY, THERE ARE TWO OPTIMAL SEEDING PERIODS DURING THE YEAR. THE FIRST PERIOD IS IN THE SPRING, MARCH TO MAY. THE SECOND PERIOD IS IN LATE SUMMER TO EARLY FALL, AUGUST TO SEPTEMBER.
- SEED SHOULD BE DRILL-SEEDED, WHENEVER POSSIBLE.
- BROADCAST SEEDING OR HYDRO-SEEDED MAY BE SUBSTITUTED ON SLOPES STEEPER THAN 3:1 OR ON OTHER AREAS NOT PRACTICAL TO DRILL SEED.
- SEEDING RATES SHOULD BE DOUBLED FOR BROADCAST SEEDING OR INCREASED BY 50% IF USING A BRILLION DRILL OR HYDRO-SEEDED.
- BROADCAST SEED SHOULD BE LIGHTLY HAND-RAKED INTO THE SOIL.
- SEED DEPTH SHOULD BE 1/3 TO 1/2 INCH FOR MOST MIXTURES.
- SEEDED AREAS SHOULD BE MULCHED, AND THE MULCH SHOULD BE ADEQUATELY SECURED.
- IF HYDRO-SEEDED IS CONDUCTED, MULCHING SHOULD BE CONDUCTED AS A SEPARATE, SECOND OPERATION.
- CONTAINERIZED NURSERY STOCK SHOULD BE KEPT IN A LIVE AND HEALTHY CONDITION PRIOR TO INSTALLATION.
- CONTAINERIZED TREES AND SHRUBS SHOULD BE INSTALLED ACCORDING TO THE PLANTING DETAILS PROVIDED IN THE COLORADO SPRINGS LANDSCAPE CODE AND POLICY MANUAL, UNIT FOUR, APPENDICES FOR TREE AND SHRUB PLANTING DETAILS.
- LIVE STAKES, POLES AND WILLOW BUNDLES SHOULD BE INSTALLED WHEN DORMANT (LATE WINTER AND EARLY SPRING).
- IF BEAVER ARE KNOWN TO BE IN THE AREA, BEAVER PROTECTION SHOULD BE PROVIDED FOR TREES AND SHRUBS.

ALLOWABLE PLANT VARIETIES (SEE DRAINAGE CRITERIA MANUAL, VOLUME 1, CHAPTER 14, TABLE 14-5)


- SPECIES**
- WESTERN WHEATGRASS (PASCOPYRUM SMITHII)
 - SWITCHGRASS (PANICUM VIRGATUM)
 - SLENDER WHEATGRASS (ELYMUS TRACHYCAULUS SSP. TRACHYCAULUS)
 - PUBESCENT WHEATGRASS (TRIGIA INTERMEDIA SSP. TRICHOPHORUM)
 - INDIAN GRASS (ACHNATHERUM HYMENOIDES)
 - BIG BLUESTEM (POA AMPLA)
 - BLUE GRAMA (BOUPELOUA GRACILIS)
 - SWITCHGRASS (PANICUM VIRGATUM)
 - SIDE-OATS GRAMA (BOUPELOUA CURTIPENDULA)
 - NEEDLE AND THREAD (HESPEROSTIPA COMATA SSP. COMATA)

*SEED MIX SHOULD BE APPROVED BY THE COUNTY

Sediment Control Log (SCL) SC-2



Sediment Control Log (SCL) SC-2



REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE MOST RECENT DATE OF WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150

Terra Nova Engineering, Inc.
Civil Engineering
721 S. ZUBO STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnec.com


WATERBURY FILING NO. 1

CONSTRUCTION SET
GRADING EROSION & STORMWATER CONTROL PLAN
EROSION CONTROL DETAILS

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE NA
V-SCALE N/A
JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 4 OF 39

Concrete Washout Area (CWA)

MM-1



CONCRETE WASHOUT AREA PLAN

SECTION A

CWA-1. CONCRETE WASHOUT AREA

CWA INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - CWA INSTALLATION LOCATION.
- DO NOT LOCATE AN UNLINED CWA WITHIN 400' OF ANY NATURAL DRAINAGE PATHWAY OR WATERBODY. DO NOT LOCATE WITHIN 1,000' OF ANY WELLS OR DRINKING WATER SOURCES. IF SITE CONSTRAINTS MAKE THIS INFEASIBLE, OR IF HIGHLY PERMEABLE SOILS EXIST ON SITE, THE CWA MUST BE INSTALLED WITH AN IMPERMEABLE LINER (1/8 MIL MIN. THICKNESS) OR SURFACE STORAGE ALTERNATIVES USING PREFABRICATED CONCRETE WASHOUT DEVICES OR A LINED ABOVE GROUND STORAGE ARE SHOULD BE USED.
- THE CWA SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE.
- CWA SHALL INCLUDE A FLAT SUBSURFACE PIT THAT IS AT LEAST 8' BY 8' SLOPES LEADING OUT OF THE SUBSURFACE PIT SHALL BE 3:1 OR FLATTER. THE PIT SHALL BE AT LEAST 3' DEEP.
- BERM SURROUNDING SIDES AND BACK OF THE CWA SHALL HAVE MINIMUM HEIGHT OF 1'.
- VEHICLE TRACKING PAD SHALL BE SLOPED 2% TOWARDS THE CWA.
- SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CWA, AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CWA TO OPERATORS OF CONCRETE TRUCKS AND PUMP TRUCKS.
- USE EXCAVATED MATERIAL FOR PERIMETER BERM CONSTRUCTION.

November 2010 Urban Drainage and Flood Control District CWA-3
Urban Storm Drainage Criteria Manual Volume 3

MM-1

Concrete Washout Area (CWA)


CWA MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - THE CWA SHALL BE REPAIRED, CLEANED, OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE. CONCRETE MATERIALS, ACCUMULATED IN PIT, SHALL BE REMOVED ONCE THE MATERIALS HAVE REACHED A DEPTH OF 2'.
 - CONCRETE WASHOUT WATER, WASTED PIECES OF CONCRETE AND ALL OTHER DEBRIS IN THE SUBSURFACE PIT SHALL BE TRANSPORTED FROM THE JOB SITE IN A WATER-TIGHT CONTAINER AND DISPOSED OF PROPERLY.
 - THE CWA SHALL REMAIN IN PLACE UNTIL ALL CONCRETE FOR THE PROJECT IS PLACED.
 - WHEN THE CWA IS REMOVED, COVER THE DISTURBED AREA WITH TOP SOIL, SEED AND MULCH OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM DOUGLAS COUNTY, COLORADO AND THE CITY OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

CWA-4 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Stockpile Management (SP)

MM-2



STOCKPILE PROTECTION PLAN

SECTION A

SP-1. STOCKPILE PROTECTION

STOCKPILE PROTECTION INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION OF STOCKPILES.
 - TYPE OF STOCKPILE PROTECTION.
- INSTALL PERIMETER CONTROLS IN ACCORDANCE WITH THEIR RESPECTIVE DESIGN DETAILS. SILT FENCE IS SHOWN IN THE STOCKPILE PROTECTION DETAILS; HOWEVER, OTHER TYPES OF PERIMETER CONTROLS INCLUDING SEDIMENT CONTROL LOGS OR ROCK SOCKS MAY BE SUITABLE IN SOME CIRCUMSTANCES. CONSIDERATIONS FOR DETERMINING THE APPROPRIATE TYPE OF PERIMETER CONTROL FOR A STOCKPILE INCLUDE WHETHER THE STOCKPILE IS LOCATED ON A PERVIOUS OR IMPERVIOUS SURFACE, THE RELATIVE HEIGHTS OF THE PERIMETER CONTROL AND STOCKPILE, THE ABILITY OF THE PERIMETER CONTROL TO CONTAIN THE STOCKPILE WITHOUT FAILING IN THE EVENT THAT MATERIAL FROM THE STOCKPILE SEEDS OR SLUMPS AGAINST THE PERIMETER, AND OTHER FACTORS.
- STABILIZE THE STOCKPILE SURFACE WITH SURFACE ROUGHENING, TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS, OR SOIL BINDERS. SOILS STOCKPILED FOR AN EXTENDED PERIOD (TYPICALLY FOR MORE THAN 60 DAYS) SHOULD BE SEED AND MULCHED WITH A TEMPORARY GRASS COVER ONCE THE STOCKPILE IS PLACED (TYPICALLY WITHIN 14 DAYS). USE OF MULCH ONLY OR A SOIL BINDER IS ACCEPTABLE IF THE STOCKPILE WILL BE IN PLACE FOR A MORE LIMITED TIME PERIOD (TYPICALLY 30-60 DAYS).
- FOR TEMPORARY STOCKPILES ON THE INTERIOR PORTION OF A CONSTRUCTION SITE, WHERE OTHER DOWNGRADIENT CONTROLS, INCLUDING PERIMETER CONTROL, ARE IN PLACE, STOCKPILE PERIMETER CONTROLS MAY NOT BE REQUIRED.

November 2010 Urban Drainage and Flood Control District SP-3
Urban Storm Drainage Criteria Manual Volume 3

MM-2

Stockpile Management (SM)


STOCKPILE PROTECTION MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - IF PERIMETER PROTECTION MUST BE MOVED TO ACCESS SOIL STOCKPILE, REPLACE PERIMETER CONTROLS BY THE END OF THE WORKDAY.
 - STOCKPILE PERIMETER CONTROLS CAN BE REMOVED ONCE ALL THE MATERIAL FROM THE STOCKPILE HAS BEEN USED.
- (DETAILS ADAPTED FROM PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SP-4 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Silt Fence (SF)

SC-1



SILT FENCE

SECTION A

SF-1. SILT FENCE

SC-1

Silt Fence (SF)

SILT FENCE INSTALLATION NOTES

- SILT FENCE MUST BE PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER PONDING. SILT FENCE AT THE TOE OF A SLOPE SHOULD BE INSTALLED IN A FLAT LOCATION AT LEAST SEVERAL FEET (2-5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR PONDING AND DEPOSITION.
- A UNIFORM 6" X 4" ANCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT FENCE INSTALLATION DEVICE. NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL BE USED.
- COMPACT ANCHOR TRENCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.
- SILT FENCE SHALL BE PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD BE NO NOTICEABLE SAG BETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES.
- SILT FENCE FABRIC SHALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES OR NAILS WITH 1" HEADS. STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC DOWN THE STAKE.
- AT THE END OF A RUN OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TURNED PERPENDICULAR TO THE CONTOUR TO CREATE A "J-HOOK." THE "J-HOOK" EXTENDING PERPENDICULAR TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP RUNOFF FROM FLOWING AROUND THE END OF THE SILT FENCE (TYPICALLY 10' - 20').
- SILT FENCE SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.


SILT FENCE MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - SEDIMENT ACCUMULATED UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED TO MAINTAIN THE FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 6".
 - REPAIR OR REPLACE SILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING, TEARING, OR COLLAPSE.
 - SILT FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER SEDIMENT CONTROL BMP.
 - WHEN SILT FENCE IS REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEEDING AND MULCH OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SF-4 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

SC-3

Straw Bale Barrier (SBB)



STRAW BALE

TRENCH FOR STRAW BALE

SECTION A

SBB-1. STRAW BALE

Straw Bale Barrier (SBB)

SC-3

STRAW BALE INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION(S) OF STRAW BALES.
- STRAW BALES SHALL CONSIST OF CERTIFIED WEED FREE STRAW OR HAY. LOCAL JURISDICTIONS MAY REQUIRE PROOF THAT BALES ARE WEED FREE.
- STRAW BALES SHALL CONSIST OF APPROXIMATELY 5 CUBIC FEET OF STRAW OR HAY AND WEIGH NOT LESS THAN 35 POUNDS.
- WHEN STRAW BALES ARE USED IN SERIES AS A BARRIER, THE END OF EACH BALE SHALL BE TIGHTLY ABUTTING ONE ANOTHER.
- STRAW BALE DIMENSIONS SHALL BE APPROXIMATELY 36"X18"X18".
- A UNIFORM ANCHOR TRENCH SHALL BE EXCAVATED TO A DEPTH OF 4". STRAW BALES SHALL BE PLACED SO THAT BINDING TWINE IS ENCOMPASSING THE VERTICAL SIDES OF THE BALES(S). ALL EXCAVATED SOIL SHALL BE PLACED ON THE UPHILL SIDE OF THE STRAW BALE(S) AND COMPACTED.
- TWO (2) WOODEN STAKES SHALL BE USED TO HOLD EACH BALE IN PLACE. WOODEN STAKES SHALL BE 2"x2"x24". WOODEN STAKES SHALL BE DRIVEN 6" INTO THE GROUND.

STRAW BALE MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - STRAW BALES SHALL BE REPLACED IF THEY BECOME HEAVILY SOILED, ROTTEN, OR DAMAGED BEYOND REPAIR.
 - SEDIMENT ACCUMULATED UPSTREAM OF STRAW BALE BARRIER SHALL BE REMOVED AS NEEDED TO MAINTAIN FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 1/2 OF THE HEIGHT OF THE STRAW BALE BARRIER.
 - STRAW BALES ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.
 - WHEN STRAW BALES ARE REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEEDING AND MULCH OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAILS ADAPTED FROM TOWN OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SBB-2 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

November 2010 Urban Drainage and Flood Control District SF-3
Urban Storm Drainage Criteria Manual Volume 3

REVISIONS	NO.	DESCRIPTION	DATE
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE MOST PART BY WRITTEN AUTHORIZATION.			

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150

Terra Nova
Engineering, Inc.
Civil/Environmental Engineers

721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.terrannova.com


WATERBURY FILING NO. 1

CONSTRUCTION SET
GRADING AND EROSION CONTROL PLAN
EROSION CONTROL DETAILS


DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	NA
V-SCALE	N/A
JOB NO.	1715.00
DATE ISSUED	2/6/23
SHEET NO.	5 OF 39

Dewatering Operations (DW)


SM-9



DW-1. DEWATERING POND ALREADY FILLED WITH WATER




DW-2. DEWATERING SUMP FOR SUBMERSED PUMP



DW-3. SUMP DISCHARGE SETTLING BASIN SECTION A

November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 DW-3

SM-9 Dewatering Operations (DW)



DW-4. DEWATERING FILTER BAG

- DEWATERING INSTALLATION NOTES**
- SEE PLAN VIEW FOR:
 - LOCATION OF DEWATERING EQUIPMENT.
 - TYPE OF DEWATERING OPERATION (DW-1 TO DW-4).
 - THE OWNER OR CONTRACTOR SHALL OBTAIN A CONSTRUCTION DISCHARGE (DEWATERING) PERMIT FROM THE STATE PRIOR TO ANY DEWATERING OPERATIONS DISCHARGING FROM THE SITE. ALL DEWATERING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE PERMIT.
 - THE OWNER OR OPERATOR SHALL PROVIDE, OPERATE, AND MAINTAIN DEWATERING SYSTEMS OF SUFFICIENT SIZE AND CAPACITY TO PERMIT EXCAVATION AND SUBSEQUENT CONSTRUCTION IN DRY CONDITIONS AND TO LOWER AND MAINTAIN THE GROUNDWATER LEVEL A MINIMUM OF 2- FEET BELOW THE LOWEST POINT OF EXCAVATION AND CONTINUOUSLY MAINTAIN EXCAVATIONS FREE OF WATER UNTIL BACK-FILLED TO FINAL GRADE.

DW-4 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 November 2010

Dewatering Operations (DW)

SM-9

- DEWATERING INSTALLATION NOTES**
- DEWATERING OPERATIONS SHALL USE ONE OR MORE OF THE DEWATERING SUMPS SHOWN ABOVE, WELL POINTS, OR OTHER MEANS APPROVED BY THE LOCAL JURISDICTION TO REDUCE THE PUMPING OF SEDIMENT, AND SHALL PROVIDE A TEMPORARY SEDIMENT BASIN OR FILTRATION BMP TO REDUCE SEDIMENT TO ALLOWABLE LEVELS PRIOR TO RELEASE OFF SITE OR TO A RECEIVING WATER. A SEDIMENT BASIN MAY BE USED IN LIEU OF SUMP DISCHARGE SETTLING BASIN SHOWN ABOVE IF A 4'-FOOT-SQUARE RIPRAP PAD IS PLACED AT THE DISCHARGE POINT AND THE DISCHARGE END OF THE LINE IS STAKED IN PLACE TO PREVENT MOVEMENT OF THE LINE.
- DEWATERING MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - DEWATERING BMPs ARE REQUIRED IN ADDITION TO ALL OTHER PERMIT REQUIREMENTS.
 - TEMPORARY SETTLING BASINS SHALL BE REMOVED WHEN NO LONGER NEEDED FOR DEWATERING OPERATIONS. ANY DISTURBED AREA SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.
- NOTE:** MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.
- (DETAILS ADAPTED FROM DOUGLAS COUNTY, COLORADO, NOT AVAILABLE IN AUTOCAD)

November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 DW-5




Figure 9-28. Check structure details (Part 3 of 3)

September 2017 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 2 9-57

SLOPE DRAIN

INSTALLATION REQUIREMENTS

- THE SLOPE DRAIN IS TO BE DESIGNED TO CONVEY THE PEAK RUNOFF FOR THE 2-YEAR STORM.
- PIPE MATERIAL MAY INCLUDE CORRUGATED METAL OR RIGID OR FLEXIBLE PLASTIC.
- EMBANKMENT MATERIAL SHALL CONSIST OF SOIL WITH A MINIMUM OF 15% PASSING A #200 SIEVE. EXCAVATED SOIL CAN BE USED IF IT MEETS THIS REQUIREMENT.
- EMBANKMENT IS TO BE COMPACTED TO AT LEAST 90% OF MAXIMUM DENSITY AND WITHIN 2% OF OPTIMUM MOISTURE CONTENT ACCORDING TO ASTM D 698.
- SLOPE DRAIN SECTIONS ARE TO BE SECURELY FASTENED TOGETHER AND HAVE WATER-TIGHT FITTINGS.
- THE OUTLET IS TO BE STABILIZED AND, UNLESS THE DRAIN DISCHARGES DIRECTLY TO A SEDIMENT BASIN, A TEMPORARY SURFACE IS TO BE PROVIDED TO CONVEY FLOWS DOWN STREAM.
- IMMEDIATELY STABILIZE ALL AREAS DISTURBED BY INSTALLATION OR REMOVAL OF THE PIPE SLOPE DRAIN.

MAINTENANCE REQUIREMENTS

- INLET AND OUTLET POINTS ARE TO BE CHECKED REGULARLY, AND AFTER HEAVY STORMS FOR CLOGGING AND OVERCHANGING. ANY BREAKS IN THE PIPE ARE TO BE PROMPTLY REPAIRED, AND CLOGS REMOVED AS NEEDED.
- WATER IS NOT TO BYPASS OR UNDERCUT THE INLET OR PIPE. IF THESE PROBLEMS DO EXIST, THE HEADWALL NEEDS TO BE REINFORCED WITH COMPACT EARTH OR SANDBAGS.
- THE OUTLET POINT IS TO BE FREE OF EROSION, AND, IF NECESSARY, ADDITIONAL OUTLET PROTECTION SHOULD BE INSTALLED.
- CONSTRUCTION TRAFFIC IS NOT TO CROSS THE SLOPE DRAIN AND MATERIALS ARE NOT TO BE PLACED ON IT.
- THE SLOPE DRAIN IS TO REMAIN IN PLACE UNTIL THE SLOPE HAS BEEN COMPLETELY STABILIZED OR UP TO 30 DAYS AFTER PERMANENT SLOPE STABILIZATION.

City of Colorado Springs Stormwater Quality Figure SD-1 Slope Drain Construction Detail and Maintenance Requirements 3-39

Hydraulic Structures Chapter 9

SECTION A SHEET PILE CHECK

SECTION B CONCRETE CHECK

Figure 9-27. Check structure details (Part 2 of 3)

9-56 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 2 September 2017

TYPICAL SECTION SAYBROOK

TYPICAL SECTION - 50' ROW 30' MAT

N.T.S.

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE SITE SPECIFIC BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
 ATTN: PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

Terra Nova
 Engineering, Inc.
 Civil/Environmental Engineers

721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshinc.com


WATERBURY FILING NO. 1

CONSTRUCTION SET
 GRADING AND EROSION CONTROL PLAN
 EROSION CONTROL DETAILS

DESIGNED BY DLF
 DRAWN BY QNA
 CHECKED BY QNA

H-SCALE NA
 V-SCALE N/A


JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 6 OF 39



CURB RETURN CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C1	58.27'	40.00'	83°28'17"
C2	66.73'	40.00'	95°35'02"
C3	32.37'	20.00'	92°43'54"
C4	32.11'	20.00'	91°59'17"
C5	30.76'	20.00'	88°07'18"
C6	30.78'	20.00'	88°11'16"

SAYBROOK ROAD
 STA. 1+00.00 - 8+28.17 - RES. COLLECTOR
 (DESIGN SPEED 35 MPH)

SEE APPROVED DEVIATION REQUESTS
 FOR LEFT AND RIGHT TURN LANES,
 MEDIAN WITHIN SAYBROOK ROAD AND
 POSTED SPEED LIMIT REDUCTION.



SAYBROOK ROAD
 STA. 11+94.17 - 16+00.00 - LOCAL
 (DESIGN SPEED 25 MPH)


POSTED SPEED LIMIT
 IS 25 M.P.H.

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN N. ARMJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

UNLESS SHOWN OTHERWISE, ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF.
 DRAWINGS ARE APPROVED FOR CONSTRUCTION BY THE ENGINEER OF RECORD.
 PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

DESIGNED BY: QNA
 DRAWN BY: QNA
 CHECKED BY:
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 7 OF 39




721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com




WATERBURY FILING NO. 1

CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SAYBROOK ROAD


DESIGNED BY: QNA
 DRAWN BY: QNA
 CHECKED BY:
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 7 OF 39



CURVE	LENGTH	RADIUS	DELTA
C7	31.42'	20.00'	90°00'00"
C8	31.42'	20.00'	90°00'00"
C9	33.05'	20.00'	94°41'12"
C10	30.14'	20.00'	86°20'39"



CURVE	LENGTH	RADIUS	DELTA
C7	31.42'	20.00'	90°00'00"
C8	31.42'	20.00'	90°00'00"
C9	33.05'	20.00'	94°41'12"
C10	30.14'	20.00'	86°20'39"




SAYBROOK ROAD
 STA. 16+00.00 - 18+34.35 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)


GILBERT DRIVE (70' ROW)
 STA. 1+90.24 - 4+33.08 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com



SAYBROOK ROAD PROFILE
 STA. 16+00.00 - 18+34.35



GILBERT DRIVE
 STA. 2+14.16 - 4+33.08

UNLESS SHOWN OTHERWISE, ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF.

DATE: _____

REVISIONS: _____

NO. _____

DESCRIPTION: _____

UNTIL SUCH TIME AS APPROVED DRAWINGS ARE PROVIDED BY THE REVIEWING AGENCIES TO TERRA NOVA ENGINEERING, INC. AND SURVEYING, INC. APPROVED FOR USE ONLY AS SHOWN HEREIN. DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

DESIGNED BY QNA

DRAWN BY QNA

CHECKED BY _____


H-SCALE 1"=50'

V-SCALE 1"=5'


JOB NO. 1715.00

DATE ISSUED 2/6/23

SHEET NO. 8 OF 39



CURVE	LENGTH	RADIUS	DELTA
C9	33.05'	20.00'	94°41'12"
C10	30.14'	20.00'	86°20'39"
C11	60.68'	35.83'	97°01'39"
C12	121.10'	51.17'	135°36'09"
C13	31.42'	20.00'	90°00'00"
C14	31.42'	20.00'	90°00'00"
C43	23.17'	68.83'	19°17'15"
C44	23.17'	68.83'	19°17'15"



SCALE: 1" = 50'

SANDY NECK CIRCLE (50' ROW)
 STA. 1+00.00 - 11+00.00 URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

POSTED SPEED LIMIT IS 25 M.P.H.

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

DATE: _____


REVISIONS:

NO.	DESCRIPTION

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES FOR THE TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVED FOR THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com




WATERBURY FILING NO. 1

CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SAYBROOK ROAD

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY _____

H-SCALE 1"=50'
 V-SCALE 1"=5'


JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 9 OF 39



CURB RETURN CURVE TABLE


CURVE	LENGTH	RADIUS	DELTA
C13	31.42'	20.00'	90°00'00"
C14	31.42'	20.00'	90°00'00"
C15	31.42'	20.00'	90°00'00"
C16	32.51'	20.00'	93°07'57"
C27	31.42'	20.00'	90°00'00"
C28	31.42'	20.00'	90°00'00"

SUNKEN MEADOW ROAD
 STA. 1+00.00 - STA. 13+25.81 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170




SUNKEN MEADOW ROAD PROFILE
 STA. 1+00.00 - STA. 13+25.81

DATE	
DESCRIPTION	
REVISIONS	
NO.	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES AND TERRA NOVA ENGINEERING, INC. AND SURVEYING, INC. APPROVES THEIR USE ONLY APPROXIMATE PERCENTAGE DESIGNATED BY WRITTEN AUTHORIZATION.	
PREPARED FOR:	4-WAY RANCH JOINT VENTURE
	PETER MARTZ
	P.O. BOX 50223
	COLORADO SPRINGS, CO 80949
	719-491-3150
DESIGNED BY	QNA
DRAWN BY	QNA
CHECKED BY	
H-SCALE	1"=50'
V-SCALE	1"=5'
JOB NO.	1715.00
DATE ISSUED	2/6/23
SHEET NO.	10 OF 39




721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnec.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SUNKEN MEADOW ROAD




FISH CAMP DRIVE
 STA. 1+00.00 – 6+00.00 – URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

CURVE	LENGTH	RADIUS	DELTA
C3	32.37'	20.00'	92°43'54"
C4	32.11'	20.00'	91°59'17"
C5	30.76'	20.00'	88°07'18"
C6	30.78'	20.00'	89°11'16"
C11	60.88'	35.83'	97°01'39"
C12	121.01'	51.17'	135°36'09"
C29	28.92'	48.83'	33°56'21"
C30	131.24'	51.17'	146°57'06"
C31	19.44'	48.83'	22°48'47"
C32	58.84'	35.83'	94°05'49"
C33	30.84'	20.00'	89°21'09"
C34	30.84'	20.00'	89°21'09"
C43	23.17'	68.83'	191°71'55"
C44	23.17'	68.83'	191°71'55"




FISH CAMP DRIVE
 STA. 6+00.00 – 14+74.56 – URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



PREPARED FOR:
4-WAY RANCH JOINT VENTURE
 PETER MARTZ
 AND SURVEYING, INC.
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

UNLIT SUCH TIME AS APPROVED
 DRAWINGS ARE APPROVED
 REVIEWING AGENCIES
 TERRA NOVA ENGINEERING,
 INC. AND SURVEYING, INC.
 APPROVES THEIR USE ONLY
 AUTHORIZED BY WRITTEN
 AUTHORIZATION.

NO.	REVISIONS	DESCRIPTION	DATE




FISH CAMP DRIVE PROFILE
 STA. 1+00.00 – 14+74.56


WATERBURY FILING NO. 1

CONSTRUCTION SET
 STREET PLAN AND PROFILE
 FISH CAMP DRIVE


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 11 OF 39



CURB RETURN CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C11	60.68'	35.83'	97°01'39"
C12	121.10'	51.17'	135°36'09"
C29	28.92'	48.83'	33°56'21"
C30	131.24'	51.17'	146°57'06"
C31	19.44'	48.83'	22°48'47"
C32	58.84'	35.83'	94°05'49"
C43	23.17'	68.83'	19°17'15"
C44	23.17'	68.83'	19°17'15"





VERTICAL SCALE
1" = 5'



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
COLORADO P.E. NO. 37170


DATE	
DESCRIPTION	
REVISIONS	
NO.	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE FOLLOWING AGENCIES:	
	TERRA NOVA ENGINEERING, INC.
	AND SURVEYING, INC.
	APPROVES FOR USE ONLY
	DESIGNATED BY WRITTEN AUTHORIZATION.
PREPARED FOR:	
4-WAY RANCH JOINT VENTURE	
PETER MARTZ	
P.O. BOX 50223	
COLORADO SPRINGS, CO 80949	
719-491-3150	
	
721 S. 2960 STREET	
COLORADO SPRINGS, CO 80904	
OFFICE: 719-635-6422	
FAX: 719-635-6426	
www.tnec.com	
WATERBURY FILING NO. 1	
CONSTRUCTION SET	
STREET PLAN AND PROFILE	
SANDY NECK/FISH CAMP KNUCKLE - FISH CAMP KNUCKLE	
DESIGNED BY QNA	
DRAWN BY QNA	
CHECKED BY	
H-SCALE 1"=50'	
V-SCALE 1"=5'	
JOB NO. 1715.00	
DATE ISSUED 2/6/23	
SHEET NO. 12 OF 39	



CURVE	LENGTH	RADIUS	DELTA
C15	31.42'	20.00'	90°00'00"
C16	32.51'	20.00'	93°07'57"
C17	60.82'	35.83'	97°15'00"
C18	22.02'	48.83'	25°50'31"
C19	133.01'	51.17'	148°56'02"
C20	22.02'	48.83'	25°50'31"


MANOR HAVEN WAY KNUCKLE PLAN
 STA. 1+00.00 - 2+77.05 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

MANOR HAVEN WAY
 STA. 0+00.00 - 7+17.39 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



721 S. 2960 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 MANOR HAVEN WAY

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 13 OF 39



MANOR HAVEN WAY PROFILE
 STA. 0+00.00 - 7+17.39

MANOR HAVEN WAY KNUCKLE PROFILE
 STA. 1+00.00 - 2+77.05


NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 BY THE BOARD OF COUNTY
 REVIEWING AGENCIES, THE
 TERRA NOVA ENGINEERING,
 AND SURVEYING, INC. ONLY
 APPROVES THEIR USE. ANY
 OTHER USE IS WITHOUT
 AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

BEECH CREEK KNUCKLE PLAN
 STA. 1+00.00 - 2+77.05 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

CURB RETURN CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C21	22.02'	48.83'	25°50'31"
C22	45.94'	51.17'	51°26'26"
C23	49.27'	51.17'	55°10'01"
C24	22.02'	48.83'	25°50'31"
C25	15.04'	35.83'	24°03'23"
C26	12.80'	35.83'	22°27'48"
C27	31.42'	20.00'	90°00'00"
C28	31.42'	20.00'	90°00'00"




BEECH CREEK CIRCLE
 STA. 8+00.00 - 16+95.49 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



721 S. 2960 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com

WATERBURY FILING NO. 1


CONSTRUCTION SET
 STREET PLAN AND PROFILE
 BEECH CREEK CIRCLE


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 14 OF 39

UNTL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 BY THE BOARD OF
 REVIEWING ENGINEERS OF
 TERRA NOVA ENGINEERING,
 AND SURVEYING, INC.
 APPROVED FOR USE ONLY
 AS SHOWN HEREIN. USE ONLY
 AS AUTHORIZED BY WRITTEN
 AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

NO.	REVISIONS	DESCRIPTION	DATE





CURB RETURN CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C35	32.03'	20.00'	91°44'53"
C36	32.03'	20.00'	91°44'53"
C37	31.42'	20.00'	90°00'00"
C38	30.92'	20.00'	88°34'27"




MASONBORO WAY
 STA. 0+00.00 - 2+40.54 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)


MEGANSETT WAY
 STA. 0+00.00 - 2+10.14 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



MASONBORO WAY PROFILE
 STA. 0+00.00 - 2+40.54




MEGANSETT WAY PROFILE
 STA. 0+00.00 - 2+10.14

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEW AGENCIES FOR THE TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVED FOR USE ONLY AS SHOWN HEREIN. DESIGNATED BY WRITTEN AUTHORIZATION.







PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150



721 S. 2960 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshinc.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 MANOR HAVEN WAY


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 16 OF 39



NO.	DESCRIPTION	DATE

UNLESS SHOWN OTHERWISE, DRAWINGS ARE APPROVED FOR CONSTRUCTION BY TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
 ATTN: PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-631-3150



721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnainc.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 ROUNDABOUT DETAILED GRADING


DESIGNED BY DLF
 DRAWN BY QNA
 CHECKED BY QNA
 H-SCALE N/A
 V-SCALE N/A
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 17 OF 39



REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL PUBLIC WORKS DEPARTMENT, THESE DRAWINGS ARE NOT TO BE USED FOR CONSTRUCTION. TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
 ATTN: PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150



721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tninc.com


WATERBURY FLING NO. 1
 CONSTRUCTION SET
 ROUNDABOUT DETAILED GRADING

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE NA
V-SCALE N/A
JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 18 OF 39



RAIL LENGTH TABLE *

TYPE 3 BARRICADE		LENGTH
FIXED	MOVABLE	
F - A	M - A	8' - 14'
F - B	M - B	15' - 24'
F - C	M - C	25' - 35'
F - D	M - D	> 35'



- NOTES
- TYPE 3 BARRICADES HAVE 3 REFLECTORIZED RAIL FACES IF FACING TRAFFIC IN ONE DIRECTION AND 6 IF FACING TRAFFIC IN TWO DIRECTIONS.
 - THE PORTION OF THE POST ABOVE THE GROUND LINE SHALL BE PAINTED IN ACCORDANCE WITH THE APPROPRIATE GENERAL NOTE.
 - DETACHABLE EXTENSION WING RAILS FOR DISPOSING OF CONSTRUCTION EQUIPMENT ARE PERMITTED, WHEN NECESSARY, ON FIXED OR MOVABLE TYPE 3 BARRICADES. THE LENGTH SHALL BE ADEQUATE TO CLOSE THE BORROW PIT AND/OR SHOULDER AS REQUIRED.







Figure 9C-3. Word, Symbol, and Arrow Pavement Markings for Bicycle Lanes



NOTE:
ALL INTERNAL SIGNS SHALL BE 4" FONT LETTER SIZE.

48 HOURS BEFORE YOU DIG,

REVISIONS

NO.	DESCRIPTION	DATE

UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER, THE REVIEWING AGENCIES, THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES OF THE WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150



DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA

H-SCALE NA
V-SCALE N/A



JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 19 OF 39

WATERBURY FLING NO. 1

CONSTRUCTION SET
SIGNING & STRIPING
SAYBROOK & ROUNDABOUT




DESIGN SPEED IS 50 M.P.H.



CURB FL CURVE TABLE				
CURVE	LENGTH	RADIUS	DELTA	ANGLE
1	66.73	40.00	95°35'02"	
2	58.27	40.00	83°28'17"	

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
COLORADO P.E. NO. 37170



DATE: _____

REVISIONS: _____

NO. _____

DESCRIPTION: _____

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE REVIEWING AGENCIES ARE NOT RESPONSIBLE FOR THE DESIGN OR CONSTRUCTION OF THE PROJECT. APPROVED FOR USE ONLY AS SHOWN ON THESE DRAWINGS. AUTHORIZED BY: _____

PREPARED FOR: 4-WAY RANCH JOINT VENTURE
PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150

DESIGNED BY QNA
DRAWN BY QNA
CHECKED BY _____


H-SCALE 1"=50'
V-SCALE 1"=5'

JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 20 OF 39


WATERBURY FILING NO. 1
CONSTRUCTION SET
STREET PLAN AND PROFILE
STAPLETON ROAD

721 S. 2900 STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAK: 719-635-6426
www.tnengine.com


Terra Nova Engineering, Inc.
Professional Engineer
Civil Engineer No. 37170




STAPLETON DRIVE
SECTION 1+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 1+73.24
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 2+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 2+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 3+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 3+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 4+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 4+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 5+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 5+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 6+01.61
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 6+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 7+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 7+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 7+99.45
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 8+43.78
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 9+06.19
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'



STAPLETON DRIVE
SECTION 9+41.64
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'



STAPLETON DRIVE
SECTION 10+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'




STAPLETON DRIVE
SECTION 10+53.39
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL AGENCIES, THE REVIEWING AGENCIES, THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE COST OF THE WRITTEN AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150





721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnainc.com

WATERBURY FILING NO. 1
CONSTRUCTION SET
STAPLETON DRIVE
CROSS SECTIONS


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE NA
V-SCALE N/A
JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 21 OF 39



STAPLETON DRIVE
STRIPING REMOVAL PLAN



STAPLETON DRIVE
SIGNAGE AND STRIPING PLAN



NOTE TO CONTRACTOR
SIGNS AND POLES SHALL BE PER CDOT STANDARDS S-614-8, S-614-2, AND S-614-3, LATEST REVISION.

ALL SIGNAGE INSTALLATION IS TO BE IN COMPLIANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL 4", 8" SOLID OR SKIP PAVEMENT MARKING ARE TO BE EPOXY.

STOP BARS ARE TO BE 90 MIL PREFORMED THERMOPLASTIC PAVEMENT MARKING TYPE B. (INLAYED)

DESIGN SPEED IS 50 M.P.H.


STRIPING LEGEND		
STRIPE	PAVEMENT MARKINGS	MARKING DESCRIPTION
1	CENTER LINES (EPOXY)	DOUBLE SOLID YELLOW, 4" WIDE-SPACED 3" APART
2	LANE LINES (EPOXY)	BROKEN WHITE, 4" WIDE-10' SEGMENTS WITH 30' GAPS
3	EDGE LINES (EPOXY)	SOLID WHITE, 4" WIDE
4	CHANNELIZING LINES (EPOXY)	SOLID WHITE, 8" WIDE
5	STOP LINES (THERMO PLASTIC)	SOLID WHITE, 24" WIDE

*NOTE: ALL STRIPING INSTALLATION SHALL BE PER COLORADO DEPARTMENT OF TRANSPORTATION "M&S STANDARDS" STANDARD PLAN NO. S-627-1

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF SUPERVISORS OF TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE MOST PART BY WRITTEN AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150





721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnainc.com

WATERBURY FILING NO. 1
SIGNAGE AND STRIPING
STAPLETON DRIVE


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE NA
V-SCALE N/A
JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 22 OF 39



STORM SEWER RUN-1 (PIPE RUN 7)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN-2 (PIPE RUN 5-6)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170




STORM SEWER RUN-1 (PIPE RUN 7)
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER RUN-2 (PIPE RUN 5-6)
 PROPOSED PUBLIC RCP STORM SEWER



<p>UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.</p>	<p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NO.</th> <th>DESCRIPTION</th> <th>DATE</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table>	NO.	DESCRIPTION	DATE			
NO.	DESCRIPTION	DATE					
<p>PREPARED FOR: 4-WAY RANCH JOINT VENTURE PETER RANTZ P.O. BOX 50223 COLORADO SPRINGS, CO 80949 719-491-3150</p>							
 <p>721 S. 2900 STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tneshc.com</p>							
<p>WATERBURY FILING NO. 1</p> <p>CONSTRUCTION SET STORM SEWER PLAN AND PROFILE STORM RUNS 1 & 2</p>							
<p>DESIGNED BY QNA DRAWN BY QNA CHECKED BY</p>							
<p>H-SCALE 1"=50' V-SCALE 1"=5'</p>							
<p>JOB NO. 1715.00 DATE ISSUED 2/6/23 SHEET NO. 23 OF 39</p>							



STORM SEWER RUN-3 (PIPE RUN 3-4)
PROPOSED PUBLIC RCP STORM SEWER
1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN-4 (PIPE RUN 1-2)
PROPOSED PUBLIC RCP STORM SEWER
1" = 50' HORIZ. 1" = 5' VERT.




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
COLORADO P.E. NO. 37170

6950																					6950
6940																					6940
6930																					6930
6920																					6920
6910																					6910
	1+00		2+00		1+00		2+00		3+00		4+00		5+00		6+00		1+00		2+00		6910



STORM SEWER RUN-3 (PIPE RUN 3-4)
PROPOSED PUBLIC RCP STORM SEWER



STORM SEWER RUN-4 (PIPE RUN 1-2)
PROPOSED PUBLIC RCP STORM SEWER

WATERBURY FILING NO. 1

CONSTRUCTION SET
STORM SEWER PLAN AND PROFILE
STORM RUNS 3 & 4

DESIGNED BY QNA	DATE
DRAWN BY QNA	DESCRIPTION
CHECKED BY	NO.
H-SCALE 1"=50'	REVISIONS
V-SCALE 1"=5'	UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES AND TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.
JOB NO. 1715.00	DATE ISSUED 2/6/23
SHEET NO. 24 OF 37	

Terra Nova
Engineering, Inc.
Civil Engineering

721 S. 2500 STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAK: 719-635-6426
www.tneshc.com

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150

NO.	DESCRIPTION	DATE




UNTL. SUCH TIME AS THESE DRAWINGS ARE APPROVED BY REVIEWING AGENCIES. THE TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

Terra Nova Engineering, Inc.
 721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY

H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 25 OF 37




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 STORM RUNS 5, 8 & 10



STORM SEWER LATERAL-3 & RUN-8 (PIPE RUN 16 & 17)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE REVIEWING AGENCIES, TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
 4-WAY RANCH JOINT VENTURE
 PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

Terra Nova Engineering, Inc.
 721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com




Station	Elevation	Notes
0+00	6930	15.44 L.F. ~ 18" RCP STORM SEWER @ 17.80% (PR-16 Q _{max} = 3 CFS)
0+00	6920	100 YR. HGL
0+00	6910	100 YR. HGL
0+00	6900	100 YR. HGL
0+00	6890	100 YR. HGL
1+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
1+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
1+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
1+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
1+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
2+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
2+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
2+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
2+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
2+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
3+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
3+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
3+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
3+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
3+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
4+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
4+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
4+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
4+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
4+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
5+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
5+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
5+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
5+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
5+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
6+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
6+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
6+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
6+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
6+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
7+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
7+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
7+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
7+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
7+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
8+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
8+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
8+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
8+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
8+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)
9+00	6930	60.00 L.F. ~ 36" RCP STORM SEWER @ 1.00% (PR-13 Q _{max} = 34 CFS)
9+00	6920	50.50 L.F. ~ 36" RCP STORM SEWER @ 9.68% (CLASS 4 RCP) (PR-17 Q _{max} = 34 CFS)
9+00	6910	231.50 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
9+00	6900	220.45 L.F. ~ 36" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 34 CFS)
9+00	6890	153.11 L.F. ~ 42" RCP STORM SEWER @ 0.70% (PR-17 Q _{max} = 31 CFS)

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY


H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 27 OF 37

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 LATERAL 3 & STORM RUN-8



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.
QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
COLORADO P.E. NO. 37170



DATE: _____

DESCRIPTION: _____

REVISIONS:

NO.	DESCRIPTION

UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ENGINEERS AND SURVEYORS, INC. AND APPROVED THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150


Terra Nova Engineering, Inc.
Professional Engineer
721 S. 29th STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tneng.com

WATERBURY FILING NO. 1
CONSTRUCTION SET
STORM SEWER PLAN AND PROFILE
LATERALS 4-6



DESIGNED BY QNA
DRAWN BY QNA
CHECKED BY _____

H-SCALE 1"=50'
V-SCALE 1"=5'



JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 28 OF 3



STORM SEWER RUN - 9 (PIPE RUN 29)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN - 9 (PIPE RUN 31 & 33)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER LATERAL - 9 & 10 (PIPE RUN 30 & 32)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



SCALE: 1" = 50'
 THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.
 QUENTIN N. ARMJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



STORM SEWER RUN - 9 (PIPE RUN 29, 31 & 33)
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER LATERAL - 10 (PIPE RUN 32)
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER LATERAL - 9 (PIPE RUN 30)
 PROPOSED PUBLIC RCP STORM SEWER

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY

H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 29 OF 37


WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 RUNS 9 & 10 AND LATERAL 9 & 10

PREPARED FOR:
 4-WAY RANCH JOINT VENTURE
 PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150



UNTL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 FOR REVISIONS BY THE
 REVIEWING AGENCIES OR
 TERRA NOVA ENGINEERING,
 AND SURVEYING, INC.
 APPROVES THEIR USE ONLY
 AS INDICATED BY THE
 AUTHORIZATION.

REVISIONS
 NO. DESCRIPTION DATE


Terra Nova
 Engineering, Inc.
 721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com



STORM SEWER LATERAL - 8 (PIPE RUN 27 & 28)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN - 9 (PIPE RUN 20, 22 & 26)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 31710




STORM SEWER RUN - 9 (PIPE RUN 20, 22 & 26)
 PROPOSED PUBLIC RCP STORM SEWER

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES FOR THE TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150





721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER RUN 9 & LATERAL 8



DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 30 OF 37




STORM SEWER LATERAL - 10 (PIPE RUN 34)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER RUN - 11 (PIPE RUN 36)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER RUN - 12 (PIPE RUN 35)
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

6940		6940		6940		6940		6940		6940	
6930		6930		6930		6930		6930		6930	
6920		6920		6920		6920		6920		6920	
6910		6910		6910		6910		6910		6910	
	<p>STORM SEWER LATERAL - 10 (PIPE RUN 34) PROPOSED PUBLIC RCP STORM SEWER</p>				<p>STORM SEWER RUN - 11 (PIPE RUN 36) PROPOSED PUBLIC RCP STORM SEWER</p>				<p>STORM SEWER RUN - 12 (PIPE RUN 35) PROPOSED PUBLIC RCP STORM SEWER</p>		
	3+00	2+00	1+00		1+00	2+00	3+00		1+00	2+00	3+00

DATE: _____

REVISIONS: _____

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE REVIEWING AGENCIES, TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY _____


H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 31 OF 37



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER RUN 10, 11 & 12

721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com


Terra Nova
 Engineering, Inc.
 Registered Professional Engineer



STORM SEWER LATERAL-11 (PIPE RUN 39)
 PROPOSED PRIVATE HDPE STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER LATERAL-12 (PIPE RUN 40)
 PROPOSED PRIVATE HDPE STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMUO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



STORM SEWER LATERAL-11 (PIPE RUN 39)
 PROPOSED PRIVATE HDPE STORM SEWER




STORM SEWER LATERAL-12 (PIPE RUN 40)
 PROPOSED PRIVATE HDPE STORM SEWER

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 BY THE LOCAL AGENCIES
 REVIEWING AGENCIES OR
 TERRA NOVA ENGINEERING,
 AND SURVEYING, INC.
 APPROVES THEIR USE ONLY
 AS INDICATED BY THE
 DESIGNATED BY WRITTEN
 AUTHORIZATION.




PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
 P.O. BOX 50223
 COLORADO SPRINGS, CO 80949
 719-491-3150



721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneshc.com



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER LATERAL 13, 14

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 1715.00
 DATE ISSUED 2/6/23
 SHEET NO. 33 OF 39



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
COLORADO P.E. NO. 37170



REVISIONS	NO.	DESCRIPTION	DATE


UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEW AGENCIES TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150



721 S. 2800 STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tneshc.com

WATERBURY FILING NO. 1
CONSTRUCTION SET
STORM SEWER LATERAL 11, 12


DESIGNED BY QNA
DRAWN BY QNA
CHECKED BY
H-SCALE 1"=50'
V-SCALE 1"=5'
JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 32 OF 3



DUAL 42" RCP STORM SEWER CROSSING & 18" RCP SIDE DITCH CULVERT CROSSING




DUAL 42" RCP STORM SEWER CROSSING
HORIZONTAL SCALE: 1" = 30'
VERTICAL SCALE: 1" = 5'




18" RCP STORM SEWER CROSSING
HORIZONTAL SCALE: 1" = 30'
VERTICAL SCALE: 1" = 5'

NORTHWEST HEADWALL/WINGWALLS
PER CDOT M-601-20
SEE CDOT M-601-20 FOR DESIGN REQUIREMENTS
INV. IN EL = 6935.82
EL AT TOP OF HEADWALL = 6940.32
EL AT TOP OF WINGWALL NW1 = 6939.82
EL AT TOP OF WINGWALL NW2 = 6937.11
EL AT TOP OF NW1 FOOTING = 6935.82
EL AT TOP OF NW2 FOOTING = 6936.11




NORTHWEST WINGWALL TOP
N.T.S.
(WALL NW1)




NORTHWEST WINGWALL BOTTOM
N.T.S.
(WALL NW2)

NORTHEAST HEADWALL/WINGWALLS
PER CDOT M-601-20
SEE CDOT M-601-20 FOR DESIGN REQUIREMENTS
INV. IN EL = 6935.82
EL AT TOP OF HEADWALL = 6940.32
EL AT TOP OF WINGWALL NE1 = 6939.82
EL AT TOP OF WINGWALL NE2 = 6937.11
EL AT TOP OF NE1 FOOTING = 6935.82
EL AT TOP OF NE2 FOOTING = 6936.11




NORTHEAST WINGWALL TOP
N.T.S.
(WALL NE1)




NORTHEAST WINGWALL BOTTOM
N.T.S.
(WALL NE2)

SOUTHWEST HEADWALL/WINGWALLS
PER CDOT M-601-20
SEE CDOT M-601-20 FOR DESIGN REQUIREMENTS
INV. OUT EL = 6934.18
EL AT TOP OF HEADWALL = 6938.68
EL AT TOP OF WINGWALL SW1 = 6938.18
EL AT TOP OF WINGWALL SW2 = 6936.11
EL AT TOP OF SW1 FOOTING = 6934.18
EL AT TOP OF SW2 FOOTING = 6934.11




SOUTHWEST WINGWALL TOP
N.T.S.
(WALL SW1)




SOUTHWEST WINGWALL BOTTOM
N.T.S.
(WALL SW2)

SOUTHEAST HEADWALL/WINGWALLS
PER CDOT M-601-20
SEE CDOT M-601-20 FOR DESIGN REQUIREMENTS
INV. OUT EL = 6934.18
EL AT TOP OF HEADWALL = 6938.68
EL AT TOP OF WINGWALL SE1 = 6938.18
EL AT TOP OF WINGWALL SE2 = 6936.13
EL AT TOP OF SE1 FOOTING = 6934.18
EL AT TOP OF SE2 FOOTING = 6934.13




SOUTHEAST WINGWALL TOP
N.T.S.
(WALL SE1)




SOUTHEAST WINGWALL BOTTOM
N.T.S.
(WALL SE2)





DATE	
REVISIONS	
NO.	
DESCRIPTION	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEW AGENCIES (SEE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE DESIGNATED BY WRITTEN AUTHORIZATION.	
PREPARED FOR: 4-WAY RANCH JOINT VENTURE ATTN: PETER MARTZ P.O. BOX 50223 COLORADO SPRINGS, CO 80949 719-491-3150	
721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnainc.com	
WATERBURY FILING NO. 1	
CONSTRUCTION SET STORM SEWER PLAN AND PROFILE GILBERT DRIVE CROSSING CULVERTS	
DESIGNED BY DLF	
DRAWN BY QNA	
CHECKED BY QNA	
H-SCALE NA	
V-SCALE N/A	
JOB NO. 1715.00	
DATE ISSUED 2/6/23	
SHEET NO. 34 OF 39	



WEST CONCRETE FOREBAY/MICROPOOL DETAILS



EAST CONCRETE FOREBAY DETAILS



DETENTION FACILITY 1


DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	NA
V-SCALE	N/A
JOB NO.	1715.00
DATE ISSUED	2/6/23
SHEET NO.	35 OF 39

REVISIONS	NO.	DESCRIPTION	DATE
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE REVIEWING AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES STATED BY WRITTEN AUTHORIZATION.			


PREPARED FOR:	RANCH, JOINT VENTURE
ATTN:	PETER MARTZ
P.O. BOX	50223
COLORADO SPRINGS, CO	80949
PHONE	719-491-3150

721 S. 23RD STREET	COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422	FAX: 719-635-6426
www.tnove.com	


WATERBURY FILING NO. 1
CONSTRUCTION SET
POND 1 DETAILS




GRATE CONSTRUCTION
ALL WELDED CONSTRUCTION
SCALE: 1"=2'




FLARED END SECTION
SCALE: N.T.S.




TRASH RACK DETAIL: F.E.S. DETAIL
SCALE: N.T.S.




EMERGENCY SPILLWAY CROSS SECTION
SCALE: N.T.S.




PERMANENT FOREBAY DETAIL
SCALE: 1"=5'



INTERIM POND 1
SCALE: 1"=30'




CONCRETE OUTLET BOX DETAILS
SCALE: 1"=10'



REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEW AGENCIES, THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150




721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnecinc.com


WATERBURY FILING NO. 1

CONSTRUCTION SET
POND 2 DETAILS


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE NA
V-SCALE N/A
JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 37 OF 39




NORTH CONCRETE FOREBAY
SCALE: 1"=10'




EAST CONCRETE FOREBAY/MICROPOOL DETAILS
SCALE: 1"=10'



EMERGENCY SPILLWAY CROSS SECTION
SCALE: N.T.S.




SCALE: 1" = 30'





POND 3
SCALE: 1"=30'

REVISIONS	NO.	DESCRIPTION	DATE
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES, THE REVIEWING AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.			
PREPARED FOR: 4-WAY RANCH JOINT VENTURE ATTN: PETER MARTZ P.O. BOX 50223 COLORADO SPRINGS, CO 80949 719-491-3150			
721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnecinc.com			
WATERBURY FILING NO. 1			
CONSTRUCTION SET POND 3 DETAILS			
DESIGNED BY DLF			
DRAWN BY QNA			
CHECKED BY QNA			
H-SCALE NA			
V-SCALE N/A			
JOB NO. 1715.00			
DATE ISSUED 2/6/23			
SHEET NO. 38 OF 39			




GRATE CONSTRUCTION
ALL WELDED CONSTRUCTION
SCALE: 1"=2'



NOTES:

1. WELD PLATES MAY BE SUBSTITUTED FOR PIPE EMBEDMENT.
2. CONTRACTOR SHALL SUBMIT HANDRAIL SHOP DRAWINGS TO ENGINEER OF RECORD FOR APPROVAL PRIOR TO FABRICATION.
3. DESIGN CRITERIA SHALL BE IN ACCORDANCE WITH AASHTO STANDARDS.
4. HANDRAIL DESIGN SHALL BE COMPATIBLE WITH THE DESIGN OF THE WINGWALLS AND HEADWALLS.
5. RAILING POSTS SHALL BE SET TO NORMAL TO GRADE. RAILS SHALL RUN PARALLEL TO THE SLOPES OF TOPS OF THE WALLS.
6. ALL RAILS SHALL HAVE EXPANSION JOINTS SPACED AT 40'-0" MAX. JOINT ENDS SHALL BE FREE OF ANY SHARP EDGES OR CORNERS.



SECTION B-B
SCALE: 1"=1'

STEEL FABRICATION NOTES:


FABRICATED STEEL STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH AISC AND AWS SPECIFICATIONS.

THE OUTLET STRUCTURE BARGRATE IS DESIGNED FOR A VERTICAL LOAD OF 300 LBS./SQ. FT.


ALL STRUCTURAL STEEL SHAPES TO INCLUDE: ANGLE, PLATE, AND BAR SHALL MEET ASTM A36 SPECIFICATIONS, FY = 36 KSI MINIMUM. STRUCTURAL TUBING SHALL MEET ASTM A500 GRADE B SPECIFICATIONS, FY = 48 KSI MINIMUM. STEEL PIPE SHALL BE STANDARD WEIGHT PIPE ASTM A53 GRADE B, FY = 35 KSI MINIMUM.

WELDS NOT INDICATED SHALL BE 1/8" MINIMUM FILLET OR GROOVE, CONTINUOUS SO FAR AS POSSIBLE, CONSIDER VANDALISM LOADS, WELD ACCORDINGLY AT CRITICAL LOCATIONS.


PRIOR TO PAINTING REMOVE ALL OIL, SCALE, AND SLAG, GRIND OFF BURRS AND SHARP EDGES.



CONCRETE MICROPOOL
SCALE: 1"=2'



OUTLET STRUCTURE MODIFIED TYPE 1 MH
SCALE: 1"=2'



OUTLET STRUCTURE MODIFIED TYPE 1 MH
SCALE: 1"=2'

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA

H-SCALE NA
V-SCALE N/A

JOB NO. 1715.00
DATE ISSUED 2/6/23
SHEET NO. 39 OF 39

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY REVIEWING AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES STATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
4-WAY RANCH JOINT VENTURE
ATTN: PETER MARTZ
P.O. BOX 50223
COLORADO SPRINGS, CO 80949
719-491-3150

Terra Nova
Engineering, Inc.
Civil Engineering

721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnainc.com

WATERBURY FILING NO. 1

CONSTRUCTION SET
POND 3 DETAILS