


NOTE:

ALL EXISTING UNDERGROUND AND ABOVE GROUND UTILITY LOCATIONS, INVERTS AND SIZES ARE APPROXIMATE ONLY AND MUST BE FIELD VERIFIED PRIOR TO CONSTRUCTION...

- 1. STORMWATER DISCHARGES FROM CONSTRUCTION SITES SHALL NOT CAUSE OR THREATEN TO CAUSE POLLUTION, CONTAMINATION, OR DEGRADATION OF STATE WATERS...
2. NOTWITHSTANDING ANYTHING DEPICTED IN THESE PLANS IN WORDS OR GRAPHIC REPRESENTATION, ALL DESIGN AND CONSTRUCTION RELATED TO ROADS, STORM DRAINAGE AND EROSION CONTROL...

WATERBURY FILING NO. 1
EL PASO COUNTY, CO
CONSTRUCTION SET
NOVEMBER 2024



VICINITY MAP

GENERAL NOTES

- 1. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITIES...
2. THE CONTRACTOR WILL TAKE THE NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES, BUILDINGS, FENCES, AND ROADWAYS FROM DAMAGE...

SIGNING AND STRIPING NOTES

- 1. ALL SIGNS AND PAVEMENT MARKINGS SHALL BE IN COMPLIANCE WITH THE CURRENT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)...
2. REMOVAL OF EXISTING PAVEMENT MARKINGS SHALL BE ACCOMPLISHED BY A METHOD THAT DOES NOT MATERIALLY DAMAGE THE PAVEMENT...

TRAFFIC CONTROL NOTE

THE CONTRACTOR SHALL PROVIDE ALL TRAFFIC CONTROL DEVICES AND MONITORING NECESSARY TO SAFELY COMPLETE THE WORK SHOWN IN THESE CONSTRUCTION DOCUMENTS...

SHEET INDEX

Table listing sheet numbers and descriptions: COVER SHEET, INITIAL EROSION CONTROL PLAN 1, INTERIM EROSION CONTROL PLAN 2, etc.

CONTACT INFORMATION:

Contact information table with columns: OWNER, CIVIL ENGINEER, ENGINEERING DIVISION, METRO DISTRICT, GAS DEPARTMENT, ELECTRIC DEPARTMENT, FIRE DEPARTMENT, TELEPHONE COMPANY.

BENCHMARKS

- 1. THE TOP OF A 1-1/2' ALUMINUM SURVEYORS CAP STAMPED JR LD PLS 31161, AT THE MOST EASTERLY CORNER OF LOT 36 AS PLATED IN 4-WAY RANCH FILING NO. 1...

BASIS OF BEARING

THE NORTH LINE OF SECTION 28, TOWNSHIP 12 SOUTH, RANGE 64 WEST OF THE SIXTH PRINCIPAL MERIDIAN, EL PASO COUNTY, COLORADO BEING MONUMENTED AT EACH END BY A 3-1/4" ALUMINUM SURVEYOR'S CAP STAMPED "PINC LS 30087..."

ENGINEER'S STATEMENT

THESE DETAILED PLANS AND SPECIFICATIONS WERE PREPARED UNDER MY DIRECTION AND SUPERVISION. SAID PLANS AND SPECIFICATIONS HAVE BEEN PREPARED ACCORDING TO THE CRITERIA ESTABLISHED BY THE COUNTY FOR DETAILED ROADWAY, DRAINAGE, GRADING AND EROSION CONTROL PLANS AND SPECIFICATIONS...

OWNER/DEVELOPER'S STATEMENT

I THE OWNER/DEVELOPER HAVE READ AND WILL COMPLY WITH THE REQUIREMENTS SPECIFIED IN THESE DETAILED PLANS AND SPECIFICATIONS.

Signature line for Andrew R. Klein, authorized representative, with date field.

EL PASO COUNTY APPROVAL

COUNTY PLAN REVIEW IS PROVIDED ONLY FOR GENERAL CONFORMANCE WITH COUNTY DESIGN CRITERIA. THE COUNTY IS NOT RESPONSIBLE FOR THE ACCURACY AND ADEQUACY OF THE DESIGN, DIMENSIONS, AND/OR ELEVATIONS WHICH SHALL BE COMPLETED AT THE JOB SITE...

IN ACCORDANCE WITH EGM SECTION 1.12, THESE CONSTRUCTION DOCUMENTS WILL BE VALID FOR CONSTRUCTION FOR A PERIOD OF 2 YEARS FROM THE DATE SIGNED BY THE EL PASO COUNTY ENGINEER...

Signature line for Joshua Palmer, P.E., County Engineer / EGM Administrator, with date field.

4-WAY RANCH METROPOLITAN DISTRICT NO 2

THESE CONSTRUCTION DOCUMENTS HAVE BEEN REVIEWED AND APPROVED FOR SANITARY SEWER, WATER MAIN AND ASSOCIATED UTILITY SERVICE CONSTRUCTION.


FOR AND ON BEHALF OF THE 4-WAY RANCH METRO. DISTRICT NO 2

SF237

Table with columns: REVISIONS, NO., DESCRIPTION, DATE.

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS...

PREPARED FOR: ACM ALF V III JV SUB II LLC, ATTN: JASON POCK, 4100 E. MISSISSIPPI AVE., STE. 500, DENVER, CO 80246.



Professional Engineer seal for Jason Pock, No. 37170, State of Colorado, expires 12/13/24.


4100 E. MISSISSIPPI AVE., STE. 500, DENVER, CO 80246. OFFICE: 719-635-6422. FAX: 719-635-6426. www.terranovallc.com

Design and drawing information block: DESIGNED BY QNA, DRAWN BY QNA, CHECKED BY, H-SCALE AS SHOWN, V-SCALE N/A, JOB NO. 2356.00, DATE ISSUED 12/22/24, SHEET NO. 1 OF 54.

EROSION CONTROL LEGEND

KEY	TITLE	SYMBOL	IMPLEMENTATION PHASE
SF	SILT FENCE	SF	INITIAL
CF	CONSTRUCTION FENCE	CF	INITIAL
SCL	SEDIMENT CONTROL LOGS	SCL	INITIAL
SP	STOCKPILE PROTECTION	SP	INITIAL
VTC	VEHICLE TRACKING CONTROL	VTC	INITIAL
SSA	STABILIZED STAGING AREA	SSA	INITIAL
TSB	TEMPORARY SEDIMENT BASIN	TSB	INITIAL
DW	DEWATERING	DW	INITIAL

GRADING LEGEND	
8' EXISTING CONTOUR	---
5' EXISTING CONTOUR	---
1' PROPOSED CONTOUR	---
1' PROPOSED CONTOUR	---
LIMITS OF DISTURBANCE/CONSTRUCTION BOUNDARY	---
SUBDIVISION BOUNDARY	---
CUT/FILL LINE	---
TRIBUTARY AREA TO TSB	---
DIRECTION OF SURFACE FLOW	---
HIGH POINT	HPX
LOW POINT	LPX
A LOT	"A"
B LOT	"B"
WALK OUT LOT MODIFIED	"W"
GARDEN LEVEL LOT MODIFIED	"G"
100-Y FEMRA FLOODPLAIN	---
AREAS OF DE-WATERING	---



DEWATERING NOTE:
 CONTRACTOR TO DISCHARGE GROUND WATER TO THE PROPOSED TEMPORARY SEDIMENT BASINS PER DETAIL ON SHEET 10

NOTES:
 1. NO BATCH PLANTS ARE PROPOSED
 2. ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR
 3. SWALE E-E IS TO BE SEEDED AND MULCHED IN INITIAL PHASE

SCALE: 1"=100'

REVISIONS

NO.	DESCRIPTION	DATE

UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE FOLLOWING ENGINEERS: TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT DESCRIBED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
 ACM ALF VIII JV SUB
 ATTN: JASON POCK
 100 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

Terra Nova Engineering, Inc.
 721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnengine.com

WATERBURY FILING NO. 1

GRADING AND EROSION CONTROL PLAN
 INITIAL EROSION CONTROL PLAN 1


DESIGNED BY DLF
 DRAWN BY QNA
 CHECKED BY QNA

H-SCALE 1" = 100'
 V-SCALE N/A


JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 2 OF 54

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


QUENTIN ARMJO
 COLORADO P.E. NO. 37170




DIVERSION SWALE A-A
SEE PREVIOUS SHEET




DIVERSION SWALE B-B
SEE PREVIOUS SHEET



DIVERSION SWALE C-C
SEE PREVIOUS SHEET



DIVERSION SWALE D-D
SEE PREVIOUS SHEET




DIVERSION SWALE E-E
SEE PREVIOUS SHEET


NOTES:
NO BATCH PLANTS ARE PROPOSED
ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR

GRADING LEGEND

10' EXISTING CONTOUR		6810
2' EXISTING CONTOUR		6802
LIMITS OF DISTURBANCE/ CONSTRUCTION BOUNDARY		
SUBDIVISION BOUNDARY		
TRIBUTARY AREA TO TSB		
PROPOSED DIVERSION SWALE		
DIRECTION OF SURFACE FLOW		
EXISTING WETLANDS		
100-Y FEMA FLOODPLAIN		
AREAS OF DE-WATERING		
PERMANENT WETLAND DISTURBANCE		



MATCHLINE SEE SHEET 2 FOR FILING 1 & FILING 2



GENERAL NOTES

- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITIES ALONG THE SITE. THE OMISSION FROM OR THE INCLUSION OF UTILITY LOCATIONS ON THE PLANS IS NOT TO BE CONSIDERED AS THE NON-EXISTENCE OF OR A DEFINITE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- THE CONTRACTOR WILL TAKE THE NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES, BUILDINGS, FENCES, AND ROADWAYS FROM DAMAGE DUE TO THIS OPERATION. ANY DAMAGE TO THE ABOVE WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE, AND ANY SERVICE DISRUPTION WILL BE SETTLED BY THE CONTRACTOR.
- BULK GRADING SHALL BE COMPLETED TO A SUBGRADE TOLERANCE OF PLUS OR MINUS 0.2'.
- CONTRACTOR TO OBTAIN COPIES OF THE SOILS REPORT FROM THE GEOTECHNICAL ENGINEER AND TO BE KEPT ONSITE DURING ALL EARTHWORK OPERATIONS.
- MAXIMUM CUT/FILL SLOPES SHALL NOT EXCEED 3:1, UNLESS OTHERWISE NOTED.
- ALL BOTTOM OF WALL (BW) CALLOUTS ARE FOR THE BOTTOM OF WALL AT GRADE. THEY DO NOT REPRESENT THE BOTTOM OF THE CONSTRUCTED WALL OR FOOTING, WHICH IS NOT SPECIFIED ON THESE PLANS.

SOIL TYPES

ON-SITE SOILS ARE HYDROLOGIC GROUPS "A" (COLUMBINE GRAVELLY SANDY LOAM) AND "B" (STAPLETON SANDY LOAM) (PER NRCS WEB SOIL SURVEY MAP)

AREA OF DISTURBANCE

ESTIMATED AREA OF DISTURBANCE = 74.33 ACRES

EARTHWORK VOLUMES

ESTIMATED CUT = 73,990 CY, ESTIMATED FILL = 287,149* CY, NET = 213,159 CY <FILL>
*20% COMPACTION ASSUMED FOR PLACEMENT OF FILL

BLACK SQUIRREL CREEK NOTE:

IF AN UNDERDRAIN SYSTEMS ARE NEEDED FOR HOMES LOCATED WITH HIGH GROUNDWATER WILL NEED TO DISCHARGE INTO A GROUNDWATER RECHARGE FACILITY, NOT A STORM DRAIN SYSTEM.


THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF PROFESSIONAL ENGINEERS, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECTS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800



721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnec.com

WATERBURY FILING NO. 1
GRADING EROSION CONTROL PLAN
INITIAL EROSION CONTROL PLAN 2

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE AS SHOWN
V-SCALE N/A
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 3 OF 54

EROSION CONTROL LEGEND


KEY	TITLE	SYMBOL	IMPLEMENTATION PHASE
SF	SILT FENCE		INITIAL
CF	CONSTRUCTION FENCE		INITIAL
CIP	CULVERT INLET PROTECTION		INTERIM
IP	INLET PROTECTION		INTERIM
SBB	STRAW BALE BARRIER		INTERIM
SP	STOCKPILE PROTECTION		INITIAL
VTC	VEHICLE TRACKING CONTROL		INITIAL
CWA	CONCRETE WASHOUT AREA		INTERIM
SSA	STABILIZED STAGING AREA		INITIAL
TSM	TEMPORARY SEEDING AND MULCHING		INTERIM
DW	DEWATERING		INITIAL
TSB	TEMPORARY SEDIMENT BASIN		INITIAL

GRADING LEGEND

8' EXISTING CONTOUR		6810
1' EXISTING CONTOUR		6802
5' PROPED CONTOUR		6810
1' PROPED CONTOUR		6802
LIMITS OF DISTURBANCE/CONSTRUCTION BOUNDARY		
SUBDIVISION BOUNDARY		
CUT/FILL LINE		
TRIBUTARY AREA TO TSB		
DIRECTION OF SURFACE FLOW		4.0%
HIGH POINT		HPX
LOW POINT		LPX
A LOT		"A"
B LOT		"B"
WALK OUT LOT MODIFIED		"WO"
GARDEN LEVEL LOT MODIFIED		"G"
100-Y FEMA FLOODPLAIN		
AREAS OF DE-WATERING		

WETLANDS LEGEND

EXISTING WETLANDS	
PERMANENT WETLAND DISTURBANCE	




VEGETATION NOTE:

EXISTING VEGETATION CONSISTS OF NATIVE PRAIRIE GRASSES AND SHRUBS WITH FAIR TO GOOD COVERAGE OF 50% TO 70%

NOTES:
NO BATCH PLANTS ARE PROPOSED
ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR

GENERAL NOTE:
ALL AREAS TO BE VEGETATED WITH PERMANENT SEEDING SHOULD ALSO BE TEMPORARY STABILIZED VIA TRACK ROLLING OR SOME OTHER MEANS.



DATE: _____

REVISIONS:

NO.	DESCRIPTION

UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE COLORADO DEPARTMENT OF NATURAL RESOURCES AND TERRA NOVA ENGINEERING, INC. APPROVES THE USE ONLY FOR THE PROJECT AND FOR WHICH IT HAS WRITTEN AUTHORIZATION.

PREPARED FOR: ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800







Terra Nova Engineering, Inc.
Civil Engineering
751 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnainc.com

WATERBURY FILING NO. 1



GRADING AND EROSION CONTROL PLAN
INTERIM EROSION CONTROL PLAN 1

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE 1" = 100'
V-SCALE N/A
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 4 OF 54

DESIGNED BY: QUENTIN ARMIJO
COLORADO P.E. NO. 37170



- NOTES:**
NO BATCH PLANTS ARE PROPOSED
ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR
- GRADING LEGEND**
- 8' EXISTING CONTOUR
 - 1' EXISTING CONTOUR
 - 5' PROPEL CONTOUR
 - 1' PROPEL CONTOUR
 - LIMITS OF DISTURBANCE/ CONSTRUCTION BOUNDARY
 - SUBDIVISION BOUNDARY
 - CUT/FILL LINE
 - TRIBUTARY AREA TO TSB
 - DIRECTION OF SURFACE FLOW
 - HIGH POINT
 - LOW POINT
 - A LOT
 - B LOT
 - WALK OUT LOT MODIFIED
 - GARDEN LEVEL LOT MODIFIED
- WETLANDS LEGEND**
- EXISTING WETLANDS
 - PERMANENT WETLAND DISTURBANCE




4 WAY RANCH JOINT VENTURE, LLC
P.O. Box 50223
Colorado Springs, CO 80949
ZONED PUD
Use Vacant Land
PARCEL 4200000366

MATCHLINE SEE SHEET 4 FOR FILING 1 & FILING 2

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL AGENCIES TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECTS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POKK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800



721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnengine.com

WATERBURY FILING NO. 1
GRADING EROSION & STORMWATER CONTROL PLAN
INTERIM EROSION CONTROL PLAN 2

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	AS SHOWN
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	5 OF 54

EROSION CONTROL LEGEND

Table with 3 columns: KEY, TITLE, and SYMBOL. Lists erosion control measures such as Silt Fence, Construction Fence, Culvert Inlet Protection, Inlet Protection, Straw Bale Barrier, Stockpile Protection, Vehicle Tracking Control, Concrete Washout Area, Stabilized Staging Area, Temporary Seeding and Mulching, Permanent Seeding and Mulching, and De-watering.

IMPLEMENTATION PHASE

Table with 3 columns: KEY, TITLE, and SYMBOL. Lists implementation phases: INITIAL, INTERIM, and FINAL, with corresponding symbols for various erosion control measures.

GRADING LEGEND

Table with 3 columns: TITLE, SYMBOL, and VALUE. Lists grading features such as existing and proposed contours, limits of disturbance, cut/fill lines, and floodplains.

WETLANDS LEGEND

Table with 3 columns: TITLE, SYMBOL, and VALUE. Lists wetland features: Existing Wetlands and Permanent Wetland Disturbance.

RUNOFF REDUCTION LEGEND

Table with 3 columns: TITLE, SYMBOL, and VALUE. Lists runoff reduction features: Unconnected Impervious Area, Receiving Pervious Area, and Excluded Undeveloped Pervious Area.

VEGETATION NOTE: EXISTING VEGETATION CONSISTS OF NATIVE PRAIRIE GRASSES AND SHRUBS WITH FAIR TO GOOD COVERAGE OF 50% TO 70%.

GENERAL NOTE: ALL AREAS TO BE VEGETATED WITH PERMANENT SEEDING SHOULD ALSO BE TEMPORARY STABILIZED VIA TRACK ROLLING OR SOME OTHER MEANS.

GENERAL NOTE: 1. NO BATCH PLANTS ARE PROPOSED. 2. ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR. 3. FOR INFORMATION ONLY? FOR PRE-SUBDIVISION SITE GRADING THERE WILL BE NO CURB AND GUTTER AND STORM DRAIN, ONLY SEEDING AND MULCHING.




Table titled 'MINIMUM FINISHED FLOOR ELEVATIONS BASED 100-Y HWL'. Lists lot numbers (44-165) and their corresponding minimum finished floor elevations.

REVISIONS table with columns for NO., DESCRIPTION, and DATE. Includes a note: 'UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ADJUSTMENT, TERRA NOVA ENGINEERING, INC. APPROVES THE USE ONLY FOR THE PROJECT AND FOR THE WRITTEN AUTHORIZATION.'

PREPARED FOR: ACM ALF VIII JV SUB II LLC. ATTN: JASON POKK. 100 E. MISSISSIPPI AVE., STE 500. DENVER, CO 80246. 303-984-9800.

WATERBURY FILING NO. 1. GRADING AND EROSION CONTROL PLAN. FINAL EROSION CONTROL PLAN 1.


DESIGNED BY DLF. DRAWN BY QNA. CHECKED BY QNA. H-SCALE 1" = 100'. V-SCALE N/A. JOB NO. 2356.00. DATE ISSUED 12/22/24. SHEET NO. 6 OF 54.




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

EROSION CONTROL LEGEND

KEY	TITLE	SYMBOL
SF	SILT FENCE	SF
CF	CONSTRUCTION FENCE	CF
CIP	CULVERT INLET PROTECTION	CIP
IP	INLET PROTECTION	IP
SBB	STRAW BALE BARRIER	SBB
SP	STOCKPILE PROTECTION	SP
VTC	VEHICLE TRACKING CONTROL	VTC
CWA	CONCRETE WASHOUT AREA	CWA
SSA	STABILIZED STAGING AREA	SSA
TSM	TEMPORARY SEEDING AND MULCHING	TSM
PSM	PERMANENT SEEDING AND MULCHING	PSM
DW	DE-WATERING	DW



DIVERSION SWALE E-E




15' MAINTENANCE ACCESS ROAD SECTION PHASE 1


SCALE: N.T.S.

MINIMUM FINISHED FLOOR ELEVATIONS BASED 100-Y

Lot	Min. FF	HWL
Lot 44	Min. FF	6915.00
Lot 45	Min. FF	6916.00
Lot 46	Min. FF	6919.00
Lot 47	Min. FF	6920.00
Lot 48	Min. FF	6921.00
Lot 49	Min. FF	6921.00
Lot 75	Min. FF	6925.50
Lot 88	Min. FF	6927.00
Lot 89	Min. FF	6928.00
Lot 90	Min. FF	6933.50
Lot 91	Min. FF	6935.00
Lot 92	Min. FF	6938.50
Lot 113	Min. FF	6941.00
Lot 131	Min. FF	6964.00
Lot 132	Min. FF	6962.00
Lot 133	Min. FF	6960.00
Lot 134	Min. FF	6959.00
Lot 135	Min. FF	6958.00
Lot 136	Min. FF	6957.00
Lot 137	Min. FF	6954.00
Lot 150	Min. FF	6952.00
Lot 151	Min. FF	6949.00
Lot 152	Min. FF	6947.00
Lot 153	Min. FF	6946.00
Lot 154	Min. FF	6944.00
Lot 155	Min. FF	6944.00
Lot 156	Min. FF	6941.00
Lot 157	Min. FF	6941.00
Lot 158	Min. FF	6939.00
Lot 159	Min. FF	6939.00
Lot 160	Min. FF	6938.00
Lot 161	Min. FF	6937.00
Lot 162	Min. FF	6936.00
Lot 163	Min. FF	6936.00
Lot 164	Min. FF	6935.00
Lot 165	Min. FF	6935.00



MATCHLINE SEE SHEET 6 FOR FILING 1 & FILING 2



NOTES:
NO BATCH PLANTS ARE PROPOSED
ALL CONTROL MEASURES ARE BEING IMPLEMENTED BY THE OWNER/DEVELOPER/CONTRACTOR


GRADING LEGEND

8' EXISTING CONTOUR	6810
1' EXISTING CONTOUR	6802
5' PROPED CONTOUR	6810
1' PROPED CONTOUR	6802
LIMITS OF DISTURBANCE/ CONSTRUCTION BOUNDARY	[Green dashed line]
SUBDIVISION BOUNDARY	[Blue dashed line]
CUT/FILL LINE	[Black dashed line]
TRIBUTARY AREA TO TSB	[Dotted pattern]
DIRECTION OF SURFACE FLOW	4.0%
HIGH POINT	HPX
LOW POINT	LPX
A LOT	"A"
B LOT	"B"
WALK OUT LOT MODIFIED	"WO"
GARDEN LEVEL LOT MODIFIED	"G"


100-Y FEMA FLOODPLAIN



100-Y HWL PER HECRAS ANALYSIS



AREAS OF DE-WATERING



WETLANDS LEGEND

EXISTING WETLANDS	[Green dotted pattern]
PERMANENT WETLAND DISTURBANCE	[Red hatched pattern]


THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL JURISDICTION REVIEWING AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800




721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnec.com

WATERBURY FILING NO. 1
GRADING EROSION & CONTROL PLAN
FINAL EROSION CONTROL PLAN 2


DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	AS SHOWN
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	7 OF 54

SC-6 Inlet Protection (IP)



IP-1. BLOCK AND ROCK SOCK SUMP OR ON GRADE INLET PROTECTION

- BLOCK AND CURB SOCK INLET PROTECTION INSTALLATION NOTES**
- SEE ROCK SOCK DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.
 - CONCRETE "ONDER" BLOCKS SHALL BE LAID ON THEIR SIDES AROUND THE INLET IN A SINGLE ROW, ABUTTING ONE ANOTHER WITH THE OPEN END FACING AWAY FROM THE CURB.
 - GRAVEL BAGS SHALL BE PLACED AROUND CONCRETE BLOCKS, CLOSELY ABUTTING ONE ANOTHER AND JOINED TOGETHER IN ACCORDANCE WITH ROCK SOCK DESIGN DETAIL.



IP-2. CURB ROCK SOCKS UPSTREAM OF INLET PROTECTION

- CURB ROCK SOCK INLET PROTECTION INSTALLATION NOTES**
- SEE ROCK SOCK DESIGN DETAIL INSTALLATION REQUIREMENTS.
 - PLACEMENT OF THE SOCK SHALL BE APPROXIMATELY 30 DEGREES FROM PERPENDICULAR IN THE OPPOSITE DIRECTION OF FLOW.
 - SOCKS ARE TO BE FLUSH WITH THE CURB AND SPACED A MINIMUM OF 5 FEET APART.
 - AT LEAST TWO CURB SOCKS IN SERIES ARE REQUIRED UPSTREAM OF ON-GRADE INLETS.

SC-6 Inlet Protection (IP)

GENERAL INLET PROTECTION INSTALLATION NOTES

- SEE PLAN VIEW FOR:
-LOCATION OF INLET PROTECTION.
-TYPE OF INLET PROTECTION (IP.1, IP.2, IP.3, IP.4, IP.5, IP.6)
- INLET PROTECTION SHALL BE INSTALLED PROMPTLY AFTER INLET CONSTRUCTION OR PAVING IS COMPLETE (TYPICALLY WITHIN 48 HOURS). IF A RAINFALL/RUNOFF EVENT IS FORECAST, INSTALL INLET PROTECTION PRIOR TO ONSET OF EVENT.
- MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

INLET PROTECTION MAINTENANCE NOTES



- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
- SEDIMENT ACCUMULATED UPSTREAM OF INLET PROTECTION SHALL BE REMOVED AS NECESSARY TO MAINTAIN BMP EFFECTIVENESS, TYPICALLY WHEN STORAGE VOLUME REACHES 50% OF CAPACITY, A DEPTH OF 6" WHEN SILT FENCE IS USED, OR 1/4 OF THE HEIGHT FOR STRAW BALES.
- INLET PROTECTION IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED, UNLESS THE LOCAL JURISDICTION APPROVES EARLIER REMOVAL OF INLET PROTECTION IN STREETS.
- WHEN INLET PROTECTION AT AREA INLETS IS REMOVED, THE DISTURBED AREA SHALL BE COVERED WITH TOP SOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

NOTE: THE DETAILS INCLUDED WITH THIS FACT SHEET SHOW COMMONLY USED, CONVENTIONAL METHODS OF INLET PROTECTION IN THE DENVER METROPOLITAN AREA. THERE ARE MANY PROPRIETARY INLET PROTECTION METHODS ON THE MARKET. UDFCD NEITHER ENDORSES NOR DISCOURAGES USE OF PROPRIETARY INLET PROTECTION. HOWEVER, IN THE EVENT PROPRIETARY METHODS ARE USED, THE APPROPRIATE DETAIL FROM THE MANUFACTURER MUST BE INCLUDED IN THE BMP AND THE BMP MUST BE INSTALLED AND MAINTAINED AS SHOWN IN THE MANUFACTURER'S DETAILS.

NOTE: SOME MUNICIPALITIES DISCOURAGE OR PROHIBIT THE USE OF STRAW BALES FOR INLET PROTECTION. CHECK WITH LOCAL JURISDICTION TO DETERMINE IF STRAW BALE INLET PROTECTION IS ACCEPTABLE.




Revegetation Chapter 14

Table 14-10. Recommended Seed Mix for Transition Areas¹

Common Name (Variety)	Scientific Name	Growth Season	Growth Form	Seeds/Lb	Lbs PLS/Acre Drilled	Lbs PLS/Acre Broadcast or Hydroseeded
Sheep fescue (Dura)	<i>Festuca ovina</i>	Cool	Bunch	680,000	1.3	2.6
Western wheatgrass (Arriba)	<i>Pascopyrum smithii</i>	Cool	Sod	110,000	7.9	15.8
Alkali sacaton	<i>Spolobolus airoides</i>	Warm	Bunch	1,758,000	0.5	1.0
Slender wheatgrass	<i>Elymus trachycaulus</i>	Cool	Bunch	159,000	5.5	11.0
Canadian bluegrass (Ruebens)	<i>Poa compressa</i>	Cool	Sod	2,500,000	0.3	0.6
Switchgrass (Pathfinder)	<i>Panicum virgatum</i>	Warm	Sod/Bunch	389,000	1.3	2.6
Annual rye	<i>Lolium multiflorum</i>	Cool	Cover crop	227,000	10.0	20.0
				TOTAL	26.8	53.6
Wildflowers						
Blanket flower	<i>Fallardia arvensis</i>	---	---	132,000	0.25	0.50
Prairie coneflower	<i>Ratibida columnaris</i>	---	---	1,230,000	0.20	0.40
Purple prairie clover	<i>Petalostemum purpurea</i>	---	---	210,000	0.20	0.40
Gayfeather	<i>Liatris punctata</i>	---	---	138,000	0.06	0.12
Flax	<i>Linum lewisii</i>	---	---	293,000	0.20	0.40
Penstemon	<i>Penstemon strictus</i>	---	---	592,000	0.20	0.40
Yarrow	<i>Achillea millefolium</i>	---	---	2,770,000	0.03	0.06
				TOTAL	1.14	2.28

¹For side slopes or between wet and dry areas.
²Substitute 1.7 lbs PLS/acre of inland saltgrass (*Dactylis spicata*) in salty soils.

SM-3 Construction Fence (CF)



CF-1. PLASTIC MESH CONSTRUCTION FENCE

CONSTRUCTION FENCE INSTALLATION NOTES

- SEE PLAN VIEW FOR:
-LOCATION OF CONSTRUCTION FENCE.
- CONSTRUCTION FENCE SHOWN SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.
- CONSTRUCTION FENCE SHALL BE COMPOSED OF ORANGE, CONTRACTOR-GRADE MATERIAL THAT IS AT LEAST 4" HIGH. METAL POSTS SHOULD HAVE A PLASTIC CAP FOR SAFETY.
- STUDDED STEEL TEE POSTS SHALL BE UTILIZED TO SUPPORT THE CONSTRUCTION FENCE. MAXIMUM SPACING FOR STEEL TEE POSTS SHALL BE 10'.
- CONSTRUCTION FENCE SHALL BE SECURELY FASTENED TO THE TOP, MIDDLE, AND BOTTOM OF EACH POST.

Construction Fence (CF) SM-3


CONSTRUCTION FENCE MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
- CONSTRUCTION FENCE SHALL BE REPAIRED OR REPLACED WHEN THERE ARE SIGNS OF DAMAGE SUCH AS RIPS OR SAGS. CONSTRUCTION FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.
- WHEN CONSTRUCTION FENCES ARE REMOVED, ALL DISTURBED AREAS ASSOCIATED WITH THE INSTALLATION, MAINTENANCE, AND/OR REMOVAL OF THE FENCE SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)

Inlet Protection (IP) SC-6



CIP-1. CULVERT INLET PROTECTION

CULVERT INLET PROTECTION INSTALLATION NOTES

- SEE PLAN VIEW FOR:
-LOCATION OF CULVERT INLET PROTECTION.
- SEE ROCK SOCK DESIGN DETAIL FOR ROCK GRADATION REQUIREMENTS AND JOINING DETAIL.

CULVERT INLET PROTECTION MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
- SEDIMENT ACCUMULATED UPSTREAM OF THE CULVERT SHALL BE REMOVED WHEN THE SEDIMENT DEPTH IS 1/2 THE HEIGHT OF THE ROCK SOCK.
- CULVERT INLET PROTECTION SHALL REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.

(DETAILS ADAPTED FROM AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SEED MIX FOR POND BOTTOMS

THE CITY OF COLORADO SPRINGS ENGINEERING DEPARTMENT GENERAL SPECIFICATIONS SHOULD BE USED AS A RESOURCE WHEN DEVELOPING TECHNICAL SPECIFICATIONS FOR RE-VEGETATION. GENERAL GUIDELINES AND RECOMMENDATIONS FOR RE-VEGETATION INCLUDE:

- SEED MIXTURES SHOULD BE SOWN AT THE PROPER TIME OF YEAR FOR THE MIXTURE. GENERALLY, THERE ARE TWO OPTIMAL SEEDING PERIODS DURING THE YEAR. THE FIRST PERIOD IS IN THE SPRING, MARCH TO MAY. THE SECOND PERIOD IS IN LATE SUMMER TO EARLY FALL, AUGUST TO SEPTEMBER.
- SEED SHOULD BE DRILL-SEEDED, WHENEVER POSSIBLE.
- BROADCAST SEEDING OR HYDRO-SEEDED MAY BE SUBSTITUTED ON SLOPES STEEPER THAN 3:1 OR ON OTHER AREAS NOT PRACTICAL TO DRILL SEED.

- SEEDING RATES SHOULD BE DOUBLED FOR BROADCAST SEEDING OR INCREASED BY 50% IF USING A BRILLIANT DRILL OR HYDRO-SEEDED.
- BROADCAST SEED SHOULD BE LIGHTLY HAND-RAKED INTO THE SOIL.
- SEED DEPTH SHOULD BE 1/2 TO 1/4 INCH FOR MOST MIXTURES.
- SEEDED AREAS SHOULD BE MULCHED, AND THE MULCH SHOULD BE ADEQUATELY SECURED.
- IF HYDRO-SEEDED IS CONDUCTED, MULCHING SHOULD BE CONDUCTED AS A SEPARATE, SECOND OPERATION.
- CONTAINERIZED NURSERY STOCK SHOULD BE KEPT IN A LIVE AND HEALTHY CONDITION PRIOR TO INSTALLATION.
- CONTAINERIZED TREES AND SHRUBS SHOULD BE INSTALLED ACCORDING TO THE PLANTING DETAILS PROVIDED IN THE COLORADO SPRINGS LANDSCAPE CODE AND POLICY MANUAL, UNIT FOUR, APPENDICES FOR TREE AND SHRUB PLANTING DETAILS.
- LIVE STAKES, POLES AND WILLOW BUNDLES SHOULD BE INSTALLED WHEN DORMANT (LATE WINTER AND EARLY SPRING).
- IF BEAVER ARE KNOWN TO BE IN THE AREA, BEAVER PROTECTION SHOULD BE PROVIDED FOR TREES AND SHRUBS.

ALLOWABLE PLANT VARIETIES SPECIES

- WESTERN WHEATGRASS (*PASCOPYRUM SMITHII*)
 - SWITCHGRASS (*PANICUM VIRGATUM*)
 - SLENDER WHEATGRASS (*ELYMUS TRACHYCAULUS* SPP. *TRACHYCAULUS*)
 - PUBESCENT WHEATGRASS (*TRIGIA INTERMEDIA* SPP. *TRICHOPOHORUM*)
 - INDIAN GRASS (*ACHNATHERUM HYMENOIDES*)
 - BIG BLUESTEM (*POA AMPLA*)
 - BLUE GRAMA (*BOUPELLOU GRACILIS*)
 - SWITCHGRASS (*PANICUM VIRGATUM*)
 - SIDE-OATS GRAMA (*BOUPELLOU CURTIPENDULA*)
 - NEEDLE AND THREAD (*HESPEROSTIPA COMATA* SPP. *COMATA*)
- *SEED MIX SHOULD BE APPROVED BY THE COUNTY

REVISIONS	DATE	DESCRIPTION
NO.		

UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER FOR THE TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800

Terra Nova Engineering, Inc.
Civil Engineering
721 S. ZILBO STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnec.com

WATERBURY FILING NO. 1
GRADING EROSION & STORMWATER CONTROL PLAN
EROSION CONTROL DETAILS

DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	NA
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	8 OF 54

Concrete Washout Area (CWA) MM-1



CWA-1. CONCRETE WASHOUT AREA

- CWA INSTALLATION NOTES**
- SEE PLAN VIEW FOR:
 - CWA INSTALLATION LOCATION.
 - DO NOT LOCATE AN UNLINED CWA WITHIN 400' OF ANY NATURAL DRAINAGE PATHWAY OR WATERBODY. DO NOT LOCATE WITHIN 1,000' OF ANY WELLS OR DRINKING WATER SOURCES. IF SITE CONSTRAINTS MAKE THIS INFEASIBLE, OR IF HIGHLY PERMEABLE SOILS EXIST ON SITE, THE CWA MUST BE INSTALLED WITH AN IMPERMEABLE LINER (16 MIL MIN. THICKNESS) OR SURFACE STORAGE ALTERNATIVES USING PREFABRICATED CONCRETE WASHOUT DEVICES OR A LINED ABOVE GROUND STORAGE ARE SHOULD BE USED.
 - THE CWA SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE.
 - CWA SHALL INCLUDE A FLAT SUBSURFACE PIT THAT IS AT LEAST 8' BY 8' SLOPES LEADING OUT OF THE SUBSURFACE PIT SHALL BE 3:1 OR FLATTER. THE PIT SHALL BE AT LEAST 3' DEEP.
 - BERM SURROUNDING SIDES AND BACK OF THE CWA SHALL HAVE MINIMUM HEIGHT OF 1'.
 - VEHICLE TRACKING PAD SHALL BE SLOPED 2% TOWARDS THE CWA.
 - SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CWA, AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CWA TO OPERATORS OF CONCRETE TRUCKS AND PUMP TRUCKS.
 - USE EXCAVATED MATERIAL FOR PERIMETER BERM CONSTRUCTION.


November 2010 Urban Drainage and Flood Control District CWA-3
Urban Storm Drainage Criteria Manual Volume 3

MM-1 Concrete Washout Area (CWA)

- CWA MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - THE CWA SHALL BE REPAIRED, CLEANED, OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE, CONCRETE MATERIALS, ACCUMULATED IN PIT, SHALL BE REMOVED ONCE THE MATERIALS HAVE REACHED A DEPTH OF 2'.
 - CONCRETE WASHOUT WATER, WASTED PIECES OF CONCRETE AND ALL OTHER DEBRIS IN THE SUBSURFACE PIT SHALL BE TRANSPORTED FROM THE JOB SITE IN A WATER-TIGHT CONTAINER AND DISPOSED OF PROPERLY.
 - THE CWA SHALL REMAIN IN PLACE UNTIL ALL CONCRETE FOR THE PROJECT IS PLACED.
 - WHEN THE CWA IS REMOVED, COVER THE DISTURBED AREA WITH TOP SOIL, SEED AND MULCH OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM DOUGLAS COUNTY, COLORADO AND THE CITY OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

November 2010 Urban Drainage and Flood Control District MM-3
Urban Storm Drainage Criteria Manual Volume 3

Stockpile Management (SP) MM-2



SP-1. STOCKPILE PROTECTION

- STOCKPILE PROTECTION INSTALLATION NOTES**
- SEE PLAN VIEW FOR:
 - LOCATION OF STOCKPILES.
 - TYPE OF STOCKPILE PROTECTION.
 - INSTALL PERIMETER CONTROLS IN ACCORDANCE WITH THEIR RESPECTIVE DESIGN DETAILS. SILT FENCE IS SHOWN IN THE STOCKPILE PROTECTION DETAILS; HOWEVER, OTHER TYPES OF PERIMETER CONTROLS INCLUDING SEDIMENT CONTROL LOGS OR ROCK SOCKS MAY BE SUITABLE IN SOME CIRCUMSTANCES. CONSIDERATIONS FOR DETERMINING THE APPROPRIATE TYPE OF PERIMETER CONTROL FOR A STOCKPILE INCLUDE WHETHER THE STOCKPILE IS LOCATED ON A PERVIOUS OR IMPVIOUS SURFACE, THE RELATIVE HEIGHTS OF THE PERIMETER CONTROL AND STOCKPILE, THE ABILITY OF THE PERIMETER CONTROL TO CONTAIN THE STOCKPILE WITHOUT FAILING IN THE EVENT THAT MATERIAL FROM THE STOCKPILE SHIFTS OR SLUMPS AGAINST THE PERIMETER, AND OTHER FACTORS.
 - STABILIZE THE STOCKPILE SURFACE WITH SURFACE ROUGHENING, TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS, OR SOIL BINDERS. SOILS STOCKPILED FOR AN EXTENDED PERIOD (TYPICALLY FOR MORE THAN 60 DAYS) SHOULD BE SEED AND MULCHED WITH A TEMPORARY GRASS COVER ONCE THE STOCKPILE IS PLACED (TYPICALLY WITHIN 14 DAYS). USE OF MULCH ONLY OR A SOIL BINDER IS ACCEPTABLE IF THE STOCKPILE WILL BE IN PLACE FOR A MORE LIMITED TIME PERIOD (TYPICALLY 30-60 DAYS).
 - FOR TEMPORARY STOCKPILES ON THE INTERIOR PORTION OF A CONSTRUCTION SITE, WHERE OTHER DOWNGRADIENT CONTROLS, INCLUDING PERIMETER CONTROL, ARE IN PLACE, STOCKPILE PERIMETER CONTROLS MAY NOT BE REQUIRED.


November 2010 Urban Drainage and Flood Control District SP-3
Urban Storm Drainage Criteria Manual Volume 3

MM-2 Stockpile Management (SM)

- STOCKPILE PROTECTION MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
- STOCKPILE PROTECTION MAINTENANCE NOTES**
- IF PERIMETER PROTECTION MUST BE MOVED TO ACCESS SOIL STOCKPILE, REPLACE PERIMETER CONTROLS BY THE END OF THE WORKDAY.
 - STOCKPILE PERIMETER CONTROLS CAN BE REMOVED ONCE ALL THE MATERIAL FROM THE STOCKPILE HAS BEEN USED.
- (DETAILS ADAPTED FROM PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

November 2010 Urban Drainage and Flood Control District MM-3
Urban Storm Drainage Criteria Manual Volume 3

Silt Fence (SF) SC-1



SF-1. SILT FENCE

- SILT FENCE INSTALLATION NOTES**
- SILT FENCE MUST BE PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER PONDING. SILT FENCE SHOULD BE INSTALLED IN A FLAT LOCATION AT LEAST SEVERAL FEET (2-5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR PONDING AND DEPOSITION.
 - A UNIFORM 6" X 4" ANCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT FENCE INSTALLATION DEVICE. NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL BE USED.
 - COMPACT ANCHOR TRENCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.
 - SILT FENCE SHALL BE PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD BE NO NOTICEABLE SAG BETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES.
 - SILT FENCE FABRIC SHALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES OR NAILS WITH 1" HEADS. STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC DOWN THE STAKE.
 - AT THE END OF A RUN OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TURNED PERPENDICULAR TO THE CONTOUR TO CREATE A "J-HOOK". THE "J-HOOK" EXTENDING PERPENDICULAR TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP RUNOFF FROM FLOWING AROUND THE END OF THE SILT FENCE (TYPICALLY 10' - 20').
 - SILT FENCE SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.
- SILT FENCE MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - SEDIMENT ACCUMULATED UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED TO MAINTAIN THE FUNCTIONALITY OF THE BMP. TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 6".
 - REPAIR OR REPLACE SILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING, TEARING, OR COLLAPSE.
 - SILT FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER SEDIMENT CONTROL BMP.
 - WHEN SILT FENCE IS REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.


November 2010 Urban Drainage and Flood Control District SF-3
Urban Storm Drainage Criteria Manual Volume 3

SC-1 Silt Fence (SF)

- SILT FENCE INSTALLATION NOTES**
- SILT FENCE MUST BE PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER PONDING. SILT FENCE SHOULD BE INSTALLED IN A FLAT LOCATION AT LEAST SEVERAL FEET (2-5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR PONDING AND DEPOSITION.
 - A UNIFORM 6" X 4" ANCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT FENCE INSTALLATION DEVICE. NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL BE USED.
 - COMPACT ANCHOR TRENCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.
 - SILT FENCE SHALL BE PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD BE NO NOTICEABLE SAG BETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES.
 - SILT FENCE FABRIC SHALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES OR NAILS WITH 1" HEADS. STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC DOWN THE STAKE.
 - AT THE END OF A RUN OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TURNED PERPENDICULAR TO THE CONTOUR TO CREATE A "J-HOOK". THE "J-HOOK" EXTENDING PERPENDICULAR TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP RUNOFF FROM FLOWING AROUND THE END OF THE SILT FENCE (TYPICALLY 10' - 20').
 - SILT FENCE SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.
- SILT FENCE MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - SEDIMENT ACCUMULATED UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED TO MAINTAIN THE FUNCTIONALITY OF THE BMP. TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 6".
 - REPAIR OR REPLACE SILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING, TEARING, OR COLLAPSE.
 - SILT FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER SEDIMENT CONTROL BMP.
 - WHEN SILT FENCE IS REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

November 2010 Urban Drainage and Flood Control District SF-3
Urban Storm Drainage Criteria Manual Volume 3

SC-3 Straw Bale Barrier (SBB)



SBB-1. STRAW BALE

- STRAW BALE INSTALLATION NOTES**
- SEE PLAN VIEW FOR:
 - LOCATION(S) OF STRAW BALES.
 - STRAW BALES SHALL CONSIST OF CERTIFIED WEED FREE STRAW OR HAY. LOCAL JURISDICTIONS MAY REQUIRE PROOF THAT BALES ARE WEED FREE.
 - STRAW BALES SHALL CONSIST OF APPROXIMATELY 5 CUBIC FEET OF STRAW OR HAY AND WEIGH NOT LESS THAN 35 POUNDS.
 - WHEN STRAW BALES ARE USED IN SERIES AS A BARRIER, THE END OF EACH BALE SHALL BE TIGHTLY ABUTTING ONE ANOTHER.
 - STRAW BALE DIMENSIONS SHALL BE APPROXIMATELY 36"x18"x18".
 - A UNIFORM ANCHOR TRENCH SHALL BE EXCAVATED TO A DEPTH OF 4". STRAW BALES SHALL BE PLACED SO THAT BINDING TWINE IS ENCOMPASSING THE VERTICAL SIDES OF THE BALET(S). ALL EXCAVATED SOIL SHALL BE PLACED ON THE UPHILL SIDE OF THE STRAW BALET(S) AND COMPACTED.
 - TWO (2) WOODEN STAKES SHALL BE USED TO HOLD EACH BALE IN PLACE. WOODEN STAKES SHALL BE 2"x2"x24". WOODEN STAKES SHALL BE DRIVEN 6" INTO THE GROUND.
- STRAW BALE MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - STRAW BALES SHALL BE REPLACED IF THEY BECOME HEAVILY SOILED, ROTTEN, OR DAMAGED BEYOND REPAIR.
 - SEDIMENT ACCUMULATED UPSTREAM OF STRAW BALE BARRIER SHALL BE REMOVED AS NEEDED TO MAINTAIN FUNCTIONALITY OF THE BMP. TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 1/4 OF THE HEIGHT OF THE STRAW BALE BARRIER.
 - STRAW BALES ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.
 - WHEN STRAW BALES ARE REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAILS ADAPTED FROM TOWN OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

November 2010 Urban Drainage and Flood Control District SBB-3
Urban Storm Drainage Criteria Manual Volume 3

SC-3 Straw Bale Barrier (SBB)


- STRAW BALE INSTALLATION NOTES**
- SEE PLAN VIEW FOR:
 - LOCATION(S) OF STRAW BALES.
 - STRAW BALES SHALL CONSIST OF CERTIFIED WEED FREE STRAW OR HAY. LOCAL JURISDICTIONS MAY REQUIRE PROOF THAT BALES ARE WEED FREE.
 - STRAW BALES SHALL CONSIST OF APPROXIMATELY 5 CUBIC FEET OF STRAW OR HAY AND WEIGH NOT LESS THAN 35 POUNDS.
 - WHEN STRAW BALES ARE USED IN SERIES AS A BARRIER, THE END OF EACH BALE SHALL BE TIGHTLY ABUTTING ONE ANOTHER.
 - STRAW BALE DIMENSIONS SHALL BE APPROXIMATELY 36"x18"x18".
 - A UNIFORM ANCHOR TRENCH SHALL BE EXCAVATED TO A DEPTH OF 4". STRAW BALES SHALL BE PLACED SO THAT BINDING TWINE IS ENCOMPASSING THE VERTICAL SIDES OF THE BALET(S). ALL EXCAVATED SOIL SHALL BE PLACED ON THE UPHILL SIDE OF THE STRAW BALET(S) AND COMPACTED.
 - TWO (2) WOODEN STAKES SHALL BE USED TO HOLD EACH BALE IN PLACE. WOODEN STAKES SHALL BE 2"x2"x24". WOODEN STAKES SHALL BE DRIVEN 6" INTO THE GROUND.
- STRAW BALE MAINTENANCE NOTES**
- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - STRAW BALES SHALL BE REPLACED IF THEY BECOME HEAVILY SOILED, ROTTEN, OR DAMAGED BEYOND REPAIR.
 - SEDIMENT ACCUMULATED UPSTREAM OF STRAW BALE BARRIER SHALL BE REMOVED AS NEEDED TO MAINTAIN FUNCTIONALITY OF THE BMP. TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 1/4 OF THE HEIGHT OF THE STRAW BALE BARRIER.
 - STRAW BALES ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.
 - WHEN STRAW BALES ARE REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAILS ADAPTED FROM TOWN OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

November 2010 Urban Drainage and Flood Control District SBB-3
Urban Storm Drainage Criteria Manual Volume 3

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER, ALL WORK SHALL BE STOPPED IMMEDIATELY. TERRA NOVA ENGINEERING, INC. APPROVES THE USE ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800



WATERBURY FILING NO. 1

GRADING AND EROSION CONTROL PLAN
EROSION CONTROL DETAILS

DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	NA
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/21
SHEET NO.	9 OF 54




TABLE SB-1, SIZING INFORMATION FOR STANDARD SEDIMENT BASIN



UPSTREAM DRAINAGE AREA (AC)	BASIN BOTTOM WIDTH (FT)	SPILLWAY CREST LENGTH (FT)	HOLE DIAMETER (IN)
1	12 1/2	2	3/8
2	21	3	1/2
3	28	4	5/8
4	33 1/2	5	3/4
5	38 1/2	6	7/8
6	43	7	1
7	47 1/2	8	1 1/8
8	51	9	1 1/4
9	55	10	1 1/2
10	58 1/2	11	1 5/8
11	61	12	1 3/4
12	64	13	1 7/8
13	67 1/2	14	2
14	70 1/2	15	2 1/8
15	73 1/2	16	2 1/4

INSTALLATION NOTES


- FOR STANDARD BASIN, BOTTOM DIMENSION MAY BE MODIFIED AS LONG AS BOTTOM AREA IS NOT REDUCED.
- EMBANKMENT MATERIAL SHALL CONSIST OF SOIL FREE OF DEBRIS, ORGANIC MATERIAL, AND ROCKS OR CONCRETE, GREATER THAN 3 INCHES, AND SHALL HAVE A MINIMUM OF 15 PERCENT BY WEIGHT PASSING THE No. 200 SIEVE.
- EMBANKMENT MATERIAL SHALL BE COMPACTED TO AT LEAST 95 PERCENT OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM D-698.
- PIPE SCHEDULE 40 OR GREATER SHALL BE USED.
- THE DETAILS SHOWN ON THESE SHEETS PERTAIN TO STANDARD SEDIMENT BASIN(S) FOR DRAINAGE AREAS LESS THAN 15 ACRES. SEE CONSTRUCTION DRAWINGS FOR EMBANKMENT, STORAGE VOLUME, SPILLWAY, OUTLET, AND OUTLET PROTECTION DETAILS FOR ANY SEDIMENT BASIN(S) THAT HAVE BEEN INDIVIDUALLY DESIGNED FOR DRAINAGE AREAS LARGER THAN 15 ACRES. DESIGN CALCULATIONS MUST BE APPROVED PRIOR TO IMPLEMENTATION.

MAINTENANCE NOTES

- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN CONTROL MEASURES IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- SEDIMENT ACCUMULATED IN BASIN SHALL BE REMOVED AS NEEDED TO MAINTAIN CONTROL MEASURE EFFECTIVENESS, TYPICALLY WHEN SEDIMENT DEPTH REACHES ONE FOOT (I.E. TWO FEET BELOW SPILLWAY CREST).
- SEDIMENT BASINS ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS PERMANENTLY STABILIZED.
- PERMANENTLY STABILIZE AREA AFTER SEDIMENT BASIN REMOVAL.




Dewatering Operations (DW) SM-9




November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 DW-3

SM-9 Dewatering Operations (DW)




DW-4 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 November 2010

Dewatering Operations (DW) SM-9



November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 DW-5

Chapter 9 Hydraulic Structures



September 2017 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 2 9-57

DESIGNED BY DLF
 DRAWN BY QNA
 CHECKED BY QNA
 H-SCALE NA
 V-SCALE N/A
 JOB NO. 2356.00
 DATE ISSUED 12/22/20
 SHEET NO. 10 OF 52

REVISIONS NO. DESCRIPTION DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER, THE USER ASSUMES ALL LIABILITY FOR ANY DAMAGE TO PERSONS OR PROPERTY. TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 ATTN: JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

Terra Nova Engineering, Inc.
 721 S. ZABO STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnecinc.com

WATERBURY FILING NO 1
 GRADING AND EROSION CONTROL PLAN
 EROSION CONTROL DETAILS

...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\C-G.jpg

...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\PED_RAMP.jpg

...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\PED_RAMP MID_BLDCK.jpg


...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\TRUNCATED_DOME.jpg

design details fell off


...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\PLDWABLE_NDSE.jpg

...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\X-PAN.jpg


...\\...\\shared\\Standards\\El Paso County\\Engineering standards\\PATTERN_CDNC.jpg




PHASING
SCALE 1"=300'



MODIFIED COLLECTOR SECTION
SAYBROOK ROAD
DESIGN SPEED 40 MPH
POSTED SPEED 30 MPH
NO SCALE



URBAN RESIDENTIAL LOCAL SECTION
SAYBROOK RD., SANDY NECK CIR., SUNKEN MEADOW RD.,
FISH CAMP DR., MANOR HAVEN WAY, BEECH CIRCLE DR.,
MUDDY POND ST., MASONBORO WAY, MEGANSETT WAY
DESIGN SPEED 25 MPH
POSTED SPEED 25 MPH
NO SCALE



MODIFIED URBAN RESIDENTIAL LOCAL SECTION
GILBER RD.
DESIGN SPEED 25 MPH
POSTED SPEED 25 MPH
NO SCALE

REVISIONS NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE CITY ENGINEER, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECTS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
1000 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800

Terra Nova
Engineering, Inc.
Civil Engineering

721 S. ZABO STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6428
www.tnec.com


WATERBURY FILING NO. 1

CONSTRUCTION SET
STREET DETAILS

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA

H-SCALE N/A
V-SCALE N/A

JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 11 OF 54



CURVE	LENGTH	RADIUS	DELTA
C1	58.27'	40.00'	83°28'17"
C2	66.73'	40.00'	95°35'02"
C3	32.37'	20.00'	92°43'54"
C4	32.11'	20.00'	91°59'17"
C5	30.76'	20.00'	88°07'18"
C6	30.78'	20.00'	88°11'16"


SAYBROOK ROAD PHASE 1
 STA. 1+00.00 - 8+28.17 - RES. COLLECTOR
 (DESIGN SPEED 35 MPH)

SAYBROOK ROAD PHASE 2
 STA. 11+94.17 - 16+00.00 - LOCAL
 (DESIGN SPEED 25 MPH)

SEE APPROVED DEVIATION REQUESTS FOR LEFT AND RIGHT TURN LANES, MEDIAN WITHIN SAYBROOK ROAD AND POSTED SPEED LIMIT REDUCTION.

POSTED SPEED LIMIT IS 30 M.P.H.


POSTED SPEED LIMIT IS 25 M.P.H.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



DATE: _____
 REVISIONS: _____
 UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.
 PREPARED FOR:
ACM ALF VJ SUB II LLC
JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800




VERTICAL SCALE
 1" = 5'


(SEE ROUNDABOUT FLOWLINE PROFILES - SHEET 22)

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SAYBROOK ROAD


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 12 OF 54




SAYBROOK ROAD PHASE 2
 STA. 16+00.00 - 18+34.35 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



CURB RETURN CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C7	31.42'	20.00'	90°00'00"
C8	31.42'	20.00'	90°00'00"
C9	33.05'	20.00'	94°41'12"
C10	30.14'	20.00'	86°20'39"




GILBERT DRIVE (70' ROW) PHASE 1
 STA. 1+90.24 - 4+33.08 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



DATE: _____

REVISIONS

NO.	DESCRIPTION

UNTIL SUCH TIME AS APPROVED DRAWINGS ARE PROVIDED BY THE ENGINEER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION SHOWN ON THESE DRAWINGS. APPROVED FOR THE CLIENT:

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'


JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 13 OF 54

Terra Nova
 Engineering, Inc.
 721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnengine.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SAYBROOK ROAD CONT'D & GILBERT DRIVE



CURVE	LENGTH	RADIUS	DELTA
C9	33.05'	20.00'	94°41'12"
C10	30.14'	20.00'	86°20'39"
C11	60.68'	35.83'	97°01'39"
C12	121.10'	51.17'	135°36'09"
C13	31.42'	20.00'	90°00'00"
C14	31.42'	20.00'	90°00'00"
C43	23.17'	68.83'	191°7'15"
C44	23.17'	68.83'	191°7'15"



SANDY NECK CIRCLE PHASE 1 & 2
 STA. 1+00.00 - 11+00.00 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

POSTED SPEED LIMIT IS 25 M.P.H.


THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

DATE: _____
 REVISIONS: _____
 UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
 100 E. MISSISSIPPI AVE., STE 5
 DENVER, CO 80246
 303-984-9800

Terra Nova
 Engineering, Inc.
 721 S. 29th STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnase.com




WATERBURY FILING NO. 1

CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SANDY NECK CIR.

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'


JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 14 OF 54




CURB RETURN CURVE TABLE

CURVE	LENGTH	RADIUS	DELTA
C13	31.42'	20.00'	90°00'00"
C14	31.42'	20.00'	90°00'00"
C15	31.42'	20.00'	90°00'00"
C16	32.51'	20.00'	93°07'57"
C27	31.42'	20.00'	90°00'00"
C28	31.42'	20.00'	90°00'00"

SUNKEN MEADOW ROAD
 STA. 1+00.00 - STA. 13+25.81 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



REVISIONS


NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS, PROFESSIONAL LAND SURVEYORS AND SURVEYING ENGINEERS AND SURVEYING ENGINEERS, THEIR USE IS ONLY AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
 P.O. BOX 50223
 DENVER, CO 80246
 303-984-9800

721 S. 29th STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnec.com

Terra Nova
 Engineering, Inc.
 Professional Engineer
 Quentine Civil Engineer 108




WATERBURY FILING NO. 1

CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SUNKEN MEADOW ROAD

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'


JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 15 OF 54




FISH CAMP DRIVE PHASE 2
 STA. 1+00.00 - 6+00.00 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

CURB RETURN CURVE TABLE


CURVE	LENGTH	RADIUS	DELTA
C3	32.37'	20.00'	92°43'54"
C4	32.11'	20.00'	91°59'17"
C5	30.76'	20.00'	88°07'18"
C6	30.78'	20.00'	89°11'16"
C11	69.68'	35.83'	97°01'39"
C12	121.10'	51.17'	135°36'09"
C19	28.92'	48.83'	33°56'21"
C30	131.24'	51.17'	146°57'06"
C31	19.44'	48.83'	22°48'47"
C32	58.84'	35.83'	94°05'49"
C33	30.84'	20.00'	89°21'09"
C34	30.84'	20.00'	89°21'09"
C43	23.17'	68.83'	191°71'15"
C44	23.17'	68.83'	191°71'15"



FISH CAMP DRIVE PHASE 2
 STA. 6+00.00 - 14+74.56 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.





REVISIONS

NO.	DESCRIPTION

UNPLATTED
 STA. 14+51.41 FISH CAMP =
 STA. 14+09.79 MUDDY POND =


PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800




FISH CAMP DRIVE PROFILE
 STA. 1+00.00 - 14+74.56

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 FISH CAMP DRIVE



DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 16 OF 54



CURVE	LENGTH	RADIUS	DELTA
C11	60.68'	35.83'	97°01'39"
C12	121.10'	51.17'	135°36'09"
C29	28.92'	48.83'	33°56'21"
C30	131.24'	51.17'	146°57'06"
C31	19.44'	48.83'	22°48'47"
C32	58.84'	35.83'	94°05'49"
C43	23.17'	68.83'	19°17'15"
C44	23.17'	68.83'	19°17'15"




**SANDY NECK CIRCLE/FISH CAMP DRIVE
KNUCKLE PHASE 2**
 STA. 1+00.00 - 2+67.44 URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 POSTED SPEED LIMIT
 IS 25 M.P.H.



FISH CAMP DRIVE KNUCKLE PHASE 2
 STA. 1+00.00 - 2+05.95 URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 POSTED SPEED LIMIT
 IS 25 M.P.H.


THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POCK
 00 E. MISSISSIPPI AVE., STE 510
 DENVER, CO 80246
 303-948-9800


NO.	DESCRIPTION	DATE



VERTICAL SCALE
 1" = 5'


WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 SANDY NECK/FISH CAMP KNUCKLE - FISH CAMP KNUCKLE

DESIGNED BY: QNA
 DRAWN BY: QNA
 CHECKED BY: JS
 H-SCALE: 1"=50'
 V-SCALE: 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 17 OF 54





MANOR HAVEN WAY PHASE 2
 STA. 0+00.00 - 7+17.39 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

CURVE	LENGTH	RADIUS	DELTA
C15	31.42'	20.00'	90°00'00"
C16	32.51'	20.00'	93°07'57"
C17	60.82'	35.83'	97°15'00"
C18	22.02'	48.83'	25°50'31"
C19	133.01'	51.17'	148°56'02"
C20	22.02'	48.83'	25°50'31"



MANOR HAVEN WAY KNUCKLE PHASE 2
 STA. 1+00.00 - 2+77.05 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.




MANOR HAVEN WAY PROFILE
 STA. 0+00.00 - 7+17.39

MANOR HAVEN WAY KNUCKLE PROFILE
 STA. 1+00.00 - 2+77.05

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 BY THE APPROPRIATE
 REVIEWING AGENCIES
 TERRA NOVA ENGINEERING,
 AND SURVEYING, INC.
 APPROVES THEIR USE ONLY
 AS DESIGNATED BY WRITTEN
 AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 246949
 303-948-9800




721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnase.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 MANOR HAVEN WAY


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 18 OF 54

BEECH CREEK KNUCKLE PHASE 2
 STA. 1+00.00 - 2+77.05 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)


CURVE	LENGTH	RADIUS	DELTA
C21	22.02'	48.83'	25°50'31"
C22	45.94'	51.17'	51°26'26"
C23	49.27'	51.17'	55°10'01"
C24	22.02'	48.83'	25°50'31"
C25	15.94'	35.83'	24°03'23"
C26	12.80'	35.83'	20°27'48"
C27	31.42'	20.00'	90°00'00"
C28	31.42'	20.00'	90°00'00"



BEECH CREEK CIRCLE PHASE 2
 STA. 8+00.00 - 16+95.49 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



REVISIONS



NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS OF THE STATE OF COLORADO, ANY USE OF THESE DRAWINGS WITHOUT THE WRITTEN AUTHORIZATION OF TERRA NOVA ENGINEERING, INC. IS PROHIBITED.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
 4100 E. MISSISSIPPI
 DENVER, CO 80246
 303-984-9800

QUENTIN N. ARMILJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

721 S. 29th STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnase.com




WATERBURY FILING NO. 1

CONSTRUCTION SET
 STREET PLAN AND PROFILE
 BEECH CREEK CIRCLE

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 19 OF 54




CURB RETURN CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C6	30.78'	20.00'	89°11'16"
C7	31.42'	20.00'	90°00'00"
C33	30.84'	20.00'	88°21'09"
C34	30.84'	20.00'	88°21'09"
C35	32.03'	20.00'	91°44'53"
C36	32.03'	20.00'	91°44'53"
C37	31.42'	20.00'	90°00'00"
C38	30.92'	20.00'	88°34'27"
C39	21.53'	68.83'	17°55'21"
C40	122.31'	51.17'	136°57'24"
C41	20.94'	68.83'	17°25'53"
C42	63.88'	35.83'	102°09'18"

NO.	DATE	DESCRIPTION


REVISIONS

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEERING DIVISION OF THE DENVER AREA OFFICE OF TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVED FOR THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
**ACM ALF VIII JV SUB II LLC
 JASON POCK
 500 E. MISSISSIPPI AVE., STE. 500
 DENVER, CO 80246
 303-984-9800**



MUDDY POND STREET PHASE 2
 STA. 0+00.00 - 15+67.06 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)




MUDDY POND STREET KNUCKLE PROFILE
 STA. 0+00.00 - 1+64.82

MUDDY POND STREET PROFILE
 STA. 0+33.02 - 15+67.06

731 S. 2950 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnna.com



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 MUDDY POND ST.

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 20 OF 54




CURVE	LENGTH	RADIUS	DELTA
C35	32.03'	20.00'	91°44'53"
C36	32.03'	20.00'	91°44'53"
C37	31.42'	20.00'	90°00'00"
C38	30.92'	20.00'	88°34'27"

MASONBORO WAY PHASE 2
 STA. 0+00.00 - 2+40.54 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)




MEGANSETT WAY PHASE 2
 STA. 0+00.00 - 2+10.14 - URBAN LOCAL
 (DESIGN SPEED 25 MPH)
 (POSTED SPEED LIMIT IS 25 MPH)




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.




PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800



721 S. 2960 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneng.com



MASONBORO WAY PROFILE
 STA. 0+00.00 - 2+40.54








MEGANSETT WAY PROFILE
 STA. 0+00.00 - 2+10.14

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STREET PLAN AND PROFILE
 MASONBORO WAY & MEGANSETT WAY

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 21 OF 54


REVISIONS	NO.	DESCRIPTION	DATE
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.			



- NOTES**
1. DENOTES PEDESTRIAN RAMP
 2. DENOTES RAISED CONCRETE PLATFORM SEE DETAIL TO LEFT

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin Arrijo
 QUENTIN ARRIJO
 COLORADO P.E. NO. 37170







DATE	
DESCRIPTION	
REVISIONS	
NO.	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.	
PREPARED FOR: SUB	
ACM ALF VIII JV SUB II LLC	
ATTN: JASON POCK	
100 E. MISSISSIPPI AVE., STE 500	
DENVER, CO 80246	
303-984-9800	
Terra Nova Engineering, Inc. <i>Creating Civil Engineering</i>	
721 S. 23RD STREET COLORADO SPRINGS, CO 80904	
OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnva.com	
DESIGNED BY DLF	
DRAWN BY QNA	
CHECKED BY QNA	
H-SCALE AS SHOWN	
V-SCALE AS SHOWN	
JOB NO. 2356.00	
DATE ISSUED 12/22/12	
SHEET NO. 22 OF 54	

CURVE	LENGTH	RADIUS	DELTA	TYPE	C&G
C1	28.99'	97.00'	1707'24"	SPILL	
C2	91.94'	301.90'	1726'57"	SPILL	
C3	3.10'	2.00'	88'40'34"	SPILL	
C4	0.93'	2.00'	26'37'49"	CARRY	
C5	2.87'	2.00'	82'16'43"	SPILL	
C6	5.58'	12.00'	26'37'49"	SPILL	
C7	3.13'	2.00'	89'35'44"	SPILL	
C8	16.28'	97.00'	936'56"	CARRY	
C9	4.22'	2.00'	120'52'49"	CARRY	
C10	18.69'	64.00'	1644'06"	SPILL	
C11	7.68'	4.00'	109'57'33"	SPILL	
C12	3.23'	2.00'	92'32'44"	SPILL	
C13	7.35'	2.50'	168'26'54"	SPILL	
C14	16.00'	97.00'	926'59"	SPILL	
C15	2.89'	2.00'	82'54'05"	SPILL	
C16	1.08'	2.00'	30'50'43"	SPILL	
C17	3.11'	2.00'	89'12'04"	SPILL	
C18	16.99'	500.00'	1'56'47"	SPILL	
C19	6.46'	12.00'	30'50'43"	CARRY	
C20	3.11'	2.00'	88'58'41"	CARRY	
C21	16.45'	97.00'	943'01"	SPILL	
C22	4.28'	2.00'	122'37'40"	SPILL	
C23	18.43'	64.00'	1629'57"	SPILL	
C24	7.72'	4.00'	110'36'47"	CARRY	
C25	3.31'	2.00'	94'50'33"	CARRY	
C26	7.28'	2.50'	166'54'50"	SPILL	
C27	13.23'	97.00'	748'45"	SPILL	
C28	2.86'	2.00'	81'56'28"	CARRY	
C29	1.10'	2.00'	31'27'17"	CARRY	
C30	3.11'	2.00'	89'07'39"	CARRY	
C31	14.18'	500.00'	1'37'28"	SPILL	
C32	6.59'	12.00'	31'27'17"	SPILL	
C33	3.14'	2.00'	89'55'48"	SPILL	
C34	16.12'	97.00'	931'15"	SPILL	
C35	4.22'	2.00'	120'56'17"	SPILL	
C36	17.27'	64.00'	1527'31"	SPILL	
C37	7.71'	4.00'	110'22'54"	SPILL	
C38	3.32'	2.00'	95'11'04"	SPILL	
C39	7.35'	2.50'	168'26'54"	CARRY	
C40	16.00'	97.00'	926'59"	SPILL	
C41	2.89'	2.00'	82'54'05"	SPILL	
C42	1.08'	2.00'	30'50'43"	SPILL	
C43	3.11'	2.00'	89'12'04"	CARRY	
C44	16.99'	500.00'	1'56'47"	SPILL	
C45	6.46'	12.00'	30'50'43"	CARRY	
C46	3.11'	2.00'	88'58'41"	CARRY	
C47	16.45'	97.00'	943'01"	SPILL	
C48	4.28'	2.00'	122'37'40"	SPILL	
C49	18.43'	64.00'	1629'57"	SPILL	
C50	7.72'	4.00'	110'36'47"	SPILL	
C51	3.31'	2.00'	94'50'33"	CARRY	

LINE	LENGTH	BEARING	TYPE	C&G
L1	3.92	S48°49'28"W	CARRY	
L2	4.47	S75°27'16"W	CARRY	
L3	3.57	N75°27'16"E	SPILL	
L4	13.96	S38°37'48"E	SPILL	
L5	3.79	N48°49'28"E	SPILL	
L6	3.46	S13°23'02"E	SPILL	
L7	2.80	S44°13'45"E	SPILL	
L8	2.72	N13°23'02"W	CARRY	
L9	14.08	N50°36'49"E	SPILL	
L10	2.60	N44°13'45"W	CARRY	
L11	3.19	S76°55'44"W	CARRY	
L12	2.34	S45°28'28"W	CARRY	
L13	2.21	S76°55'44"W	SPILL	
L14	13.90	N39°20'28"W	SPILL	
L15	2.09	S45°28'28"W	SPILL	
L16	3.46	N44°13'45"W	SPILL	
L17	2.80	N44°13'45"W	SPILL	
L18	2.72	S13°23'02"E	CARRY	
L19	14.08	S50°36'49"W	CARRY	
L20	2.60	S44°13'45"E	CARRY	


NOTE
LINE AND CURVE TABLES REFER TO THE
FLOWLINE OF THE C&G




- NOTES
1. DENOTES PEDESTRIAN RAMP
 2. DENOTES RAISED CONCRETE PLATFORM
SEE DETAIL TO RIGHT

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN ARMIJO
COLORADO P.E. NO. 37170





DATE	
DESCRIPTION	
REVISIONS	
NO.	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECTS AUTHORIZED BY WRITTEN AUTHORIZATION.	
PREPARED FOR:	ACM ALF VIII JV SUB II LLC
ATTN:	JASON POCK
ADDRESS:	100 E. MISSISSIPPI AVE., STE 500 DENVER, CO 80246
PHONE:	303-984-9800
721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnec.com	
WATERBURY FILING NO. 1	
CONSTRUCTION SET	
ROUNDABOUT DETAILED GRADING	
DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	AS SHOWN
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/20
SHEET NO.	23 OF 54



SAYBROOK AND ROUNDABOUT SIGNING & STRIPING





RAIL LENGTH TABLE *

TYPE 3 BARRICADE	LENGTH
F - A M - A	8' - 14'
F - B M - B	15' - 24'
F - C M - C	25' - 35'
F - D M - D	> 35'



- BARRICADE NOTES**
- TYPE 3 BARRICADES HAVE 3 REFLECTORIZED RAIL FACES IF FACING TRAFFIC IN ONE DIRECTION AND 6 IF FACING TRAFFIC IN TWO DIRECTIONS.
 - THE PORTION OF THE POST ABOVE THE GROUND LINE SHALL BE PAINTED IN ACCORDANCE WITH THE APPROPRIATE GENERAL NOTE.
 - DETACHABLE EXTENSION WING RAILS FOR BYPASSING OF CONSTRUCTION EQUIPMENT ARE PERMITTED, WHEN NECESSARY, ON FIXED OR MOVABLE TYPE 3 BARRICADES. THE LENGTH SHALL BE ADEQUATE TO CLOSE THE BORROW PIT AND/OR SHOULDER AS REQUIRED.

TYP. TYPE 3 BARRICADES



STATE LAW

YIELD (R1-2)
36"x36"x36"

MEDIAN (R4-7)

OBJECT MARKER (OM2-1V)

PED (R1-6)
WITHIN CROSSWALK

STREET NAME NO OUTLET

STREET NAME

STREET NAME (D-3)

SPEED LIMIT 30
SPEED LIMIT (R2-1)


ONE WAY
ONE WAY (R6-1)

PED (W11-2)

NO PARKING ANY TIME
NO PARKING (R7-1)

NOTE:
ALL INTERNAL SIGNS SHALL BE 4" FONT LETTER SIZE.
STAPELTON ROAD INTERSECTION SIGNS SHALL BE 6" FONT LETTER SIZE

- NOTES**
- ⊙ DENOTES PEDESTRIAN RAMP
 - ▨ DENOTES RAISED CONCRETE PLATFORM SEE DETAIL TO LEFT
 - DENOTES A PROPOSED DRIVEWAY LOCATION



Missing or invalid reference
File: N:\Jobs\1715.00\PDFs\BIKE MARKINGS 1.pdf
Sheet: 1

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPLICABLE AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800

Terra Nova
Engineering, Inc.
Civil Engineering

721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnna.com

WATERBURY FILING NO. 1

CONSTRUCTION SET
SIGNING & STRIPING
SAYBROOK & ROUNDABOUT


THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN ARMIJO
COLORADO P.E. NO. 37170


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA

H-SCALE AS SHOWN
V-SCALE N/A

JOB NO. 2356.00
DATE ISSUED 12/22/20
SHEET NO. 24 OF 54



1 LIGHT POLE DETAIL - P3, P4
NOT TO SCALE



2 LIGHT POLE DETAIL - P5
NOT TO SCALE

WATERBURY SITE LIGHTING FIXTURE SCHEDULE												
LUMINAIRE			LAMP									
ID	MANUFACTURER	CATALOG NUMBER	DESCRIPTION	DISTRIBUTION	VOLTAGE	DIMMING	MOUNTING	QTY.	TYPE	WATTS	LUMENS	COLOR TEMP-CRI
P3	KIM LIGHTING	UR20-56L-75-4K7-3-UNV-A34-BLT-7PR-TL-CLR POLE: R55-H-18-40-B-1-K2-BLT	20\"/>									



GENERAL NOTES
A. FIXTURES SIZES SHOWN ARE DIAGRAMMATICAL AND ARE LOCATED TO STAY OUTSIDE MVEA EASEMENTS.

REVISIONS NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND SITE SPECIFIC AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
WATERBURY SITE DEVELOPMENT
STAPLETON ROAD AND
EASTONVILLE ROAD
FALCON

721 S. ZIBRO STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6428
www.terra-nova.com

ELECTRICAL SITE DEVELOPMENT PLAN

ELECTRICAL SITE DEVELOPMENT PLAN
SCALE: 1" = 100'-0"




PLANT
ENGINEERING CONSULTANTS
320 WEST FILLMORE STREET COLORADO SPRINGS CO 80907
719.473.7077 www.planteci.com

DESIGNED BY CAO
DRAWN BY PJN/CAO
CHECKED BY MPP
H-SCALE AS NOTED
V-SCALE AS NOTED
JOB NO. 24086
DATE ISSUED 10/04/24
SHEET NO. 25 OF 54

GENERAL NOTES

- A. CONTRACTOR SHALL VERIFY ALL UTILITY LOCATIONS PRIOR TO ANY EXCAVATION. NOT ALL EXISTING CONDITIONS ARE SHOWN FOR CLARITY.
- B. CONTRACTOR SHALL PROVIDE ALL REQUIRED CUTTING, TRENCHING, BACKFILLING, AND RESTORATION.
- C. THESE PHOTOMETRIC CALCULATIONS ARE BASED ON MANUFACTURER'S IES FILES AND 0.95 LIGHT DEPRECIATION FACTOR.
- D. ACTUAL ILLUMINANCE LEVELS MAY DIFFER FROM THE FOOT CANDLE LEVELS SHOWN DUE TO VARIABLE FIELD CONDITIONS, SUCH AS NEARBY EXISTING LUMINAIRES, LUMINAIRE DIRT DEPRECIATION, LANDSCAPING, AND FUTURE DEVELOPMENTS.



1 WATERBURY SITE DEVELOPMENT RENDERING - TOP VIEW
SCALE: NO SCALE

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
10' Property Line	Illuminance	Fc	0.00	0.0	0.0	N.A.	N.A.
Property Line	Illuminance	Fc	0.00	0.1	0.0	N.A.	N.A.
Site	Illuminance	Fc	0.20	4.3	0.0	N.A.	N.A.



DEVELOPMENTAL SITE PHOTOMETRIC PLAN
SCALE: 1" = 100'-0"




PLANT
ENGINEERING CONSULTANTS
320 WEST FILLMORE STREET COLORADO SPRINGS CO 80907
719 473 7077 www.planteci.com

REVISIONS	DESCRIPTION	DATE
NO.		

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEW ENGINEER, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
WATERBURY SITE DEVELOPMENT
STAPLETON ROAD AND
EASTONVILLE ROAD
FALCON



721 S. ZIBRO STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6428
www.terra-nova.com

DESIGNED BY CAO
DRAWN BY PJN/CAO
CHECKED BY MPP
H-SCALE AS NOTED
V-SCALE AS NOTED
JOB NO. 24086
DATE ISSUED 10/04/24
SHEET NO. 26 OF 54

DEVELOPMENTAL SITE
PHOTOMETRIC PLAN

UR20-Arm Mount ARCHITECTURAL AREA/SITE

- FEATURES
- 20" size in post top, pole and wall mount
- High performance optics up to 17,000 delivered lumens
- Elegant form factor
- Diffusion lens option
- UL/ULX listed for wet locations, IP66 and 4G/1.5G vibration rated



CONTROL TECHNOLOGY



SPECIFICATIONS


CONSTRUCTION

- Low copper aluminum alloy die-casting is designed as one-piece with internal cooling fins.
- Solid, cast aluminum wall creates a thermal barrier between the optical and electrical compartments.
- Molded silicone gasket throughout insures the sealing between the two compartments and provides ingress protection.
- Housing is designed with integral LED heat sink utilized for thermal transfer and for securing the location of each LED module.
- All external fasteners are stainless steel.
- One-piece low copper aluminum alloy die-cast lens frame is secured to housing with 6 screws.

- OPTICS
- LEDs mount to a metal printed circuit board assembly (MCPCB).
- Optical lenses are clear injection molded PMMA acrylic.
- Optional Backlight Control on each LED module to completely control unwanted backlight.
- Standard lens (CLR) IK08
- Clear Polycarbonate Lens (CP) IK10

- INSTALLATION
- Fixtures must be grounded in accordance with national, state and/or local electrical codes. Failure to do so may result in serious personal injury.

UR20-Arm Mount ARCHITECTURAL AREA/SITE



ELECTRICAL

- Universal voltage, 120 through 277V with a +/-10% tolerance. Driver is Underwriters Laboratories listed.
- High voltage configurations, 347/480. Driver has a 0-10V dimming interface for multi-level illumination options. Driver is Underwriters Laboratories listed.
- Thermal Shield, secondary side, thermistor provides protection for the sustainable life of LED module and electronic components.
- Drivers shall have greater than a 0.9 power factor, less than 20% harmonic distortion, and be suitable for operation in -40°C to 40°C ambient environments.
- Luminaire shall be capable of operating at 100% brightness in a 40°C environment. Both driver and optical array have integral thermal protection that will dim the luminaire upon detection of temperatures in excess of 85°C.
- Surge protection: 10,000k in parallel, 20,000k in series
- Wiring: No. 18AWM rated 105°C, wet rating.

CONTROLS

- Fully gasketed and wired 7-pin receptacle option. Easy access location above the electrical compartment. 7-pin construction allows for a user-defined interface and provides a controlled definition of operational performance. ANSI twist-lock control module by others.
- Traditional on/off photoelectric control.
- 5-pin wireless photoelectric control for added dimming feature.
- 7-pin wireless photoelectric control for dimming and additional I/O connections for customer use.

Standard customer operation modes:
- Traditional on/off photoelectric control.
- 5-pin wireless photoelectric control for added dimming feature.
- 7-pin wireless photoelectric control for dimming and additional I/O connections for customer use.

© 2024 H&S Solutions, Inc. All rights reserved. Information and specifications subject to change without notice. All values are design or typical values when measured under laboratory conditions.

(Specifications continued on page 5)

UR20 - Post Top ARCHITECTURAL AREA/SITE

- FEATURES
- 20" size in single/dual arm post top, pole and wall mount
- High performance optics up to 16,874 delivered lumens
- Elegant form factor
- Diffusion lens option
- UL/ULX listed for wet locations, IP66 and 4G/1.5G vibration rated



CONTROL TECHNOLOGY



SPECIFICATIONS

CONSTRUCTION

- Low copper aluminum alloy die-casting is designed as one-piece.
- Molded silicone gasket throughout insures the sealing between the two compartments and provides ingress protection.
- Cover is secured to lens frame by the latch and hinge.
- All external fasteners are stainless steel.
- LEDs mount to a metal printed circuit board assembly (MCPCB).
- Optical lenses are clear injection molded PMMA acrylic.
- Optional Backlight Control on each LED module to completely control unwanted backlight.
- Optional fixture finish optical surfaces will not exceed BUG ratings of the standard white finish.

- OPTICS
- Standard lens (CLR) IK08
- Clear Polycarbonate Lens (CP) IK10

- INSTALLATION
- Fixtures must be grounded in accordance with national, state and/or local electrical codes. Failure to do so may result in serious personal injury.

UR20 - Post Top ARCHITECTURAL AREA/SITE



Weight and EPA table for UR20 fixture

ELECTRICAL

- Universal voltage, 120 through 277V with a +/-10% tolerance. Driver is Underwriters Laboratories listed.
- High voltage configurations, 347/480. Driver has a 0-10V dimming interface for multi-level illumination options. Driver is Underwriters Laboratories listed.
- Thermal Shield, secondary side, thermistor provides protection for the sustainable life of LED module and electronic components.
- Drivers shall have greater than a 0.9 power factor, less than 20% harmonic distortion, and be suitable for operation in -40°C to 40°C ambient environments.
- Luminaire shall be capable of operating at 100% brightness in a 40°C environment. Both driver and optical array have integral thermal protection that will dim the luminaire upon detection of temperatures in excess of 85°C.
- Surge protection: 10,000k in parallel, 20,000k in series
- Wiring: No. 18AWM rated 105°C, wet rating.

CONTROLS

- Fully gasketed and wired 7-pin receptacle option. Easy access location above the electrical compartment. 7-pin construction allows for a user-defined interface and provides a controlled definition of operational performance. ANSI twist-lock control module by others.
- Traditional on/off photoelectric control.
- 5-pin wireless photoelectric control for added dimming feature.
- 7-pin wireless photoelectric control for dimming and additional I/O connections for customer use.

(Specifications continued on page 5)

UR20-Arm Mount ARCHITECTURAL AREA/SITE

ORDERING GUIDE

Example: UR20-24L-2S-3K8-3-L-UNV-ASO-BL7-7PR-BC

HOUSING

Table with columns: Model, LED Engine, CCT/CRI, Distribution, Rotation, Voltage

Mounting, Fixture Finish, Control Options, Options, Control Accessories

Table with columns: Mounting, Fixture Finish, Control Options, Options, Control Accessories

UR20 - Post Top ARCHITECTURAL AREA/SITE

ORDERING GUIDE

Example: UR20-24L-2S-3K8-3-L-UNV-FMSA33-BL7-7PR-BC

HOUSING


Table with columns: Model, LED Engine, CCT/CRI, Distribution, Rotation, Voltage

Mounting, Fixture Finish, Control Options, Options, Control Accessories

Table with columns: Mounting, Fixture Finish, Control Options, Options, Control Accessories


Table with columns: REVISIONS, NO., DESCRIPTION, DATE


UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED... WATERBURY SITE DEVELOPMENT STAPLETON ROAD AND EASTONVILLE ROAD FALCON



721 S. ZARO STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6428 www.tnecinc.com

CUT SHEETS table






STAPLETON ROAD
STA. 1+00.00 - 10+53.39

FLOWLINE LINE TABLE



LINE	LENGTH (LF)	BEARING
L1	28.92	N65°59'04"E
L2	44.22	N63°23'32"E
L3	214.19	N65°59'04"E
L4	141.33	N65°14'44"E
L5	94.94	N70°45'02"E

FLOWLINE CURVE TABLE

CURVE	LENGTH (LF)	RADIUS (LF)	Δ
C1	197.97	3018	03°45'30"
C2	245.74	1346	10°27'38"
C3	68.59	250	15°43'11"
C4	51.92	330.23	09°00'30"




DESIGN SPEED IS 50 M.P.H.



STAPLETON ROAD/SAYBOOK ROAD
CURB TRANSITION DETAIL

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
COLORADO P.E. NO. 37170



REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS, INC. APPROVES THEIR USE ONLY AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
00 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800

721 S. 2900 STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tneng.com

WATERBURY FILING NO. 1
CONSTRUCTION SET
STREET PLAN AND PROFILE
STAPLETON ROAD

DESIGNED BY QNA
DRAWN BY QNA
CHECKED BY JS
H-SCALE 1"=50'
V-SCALE 1"=5'
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 28 OF 54

STAPLETON DRIVE
SECTION 1+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 1+73.24
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 2+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 2+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 3+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 3+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 4+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 4+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 5+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 5+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 6+01.61
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 6+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 7+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 7+50.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 7+99.45
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 8+43.78
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 9+06.19
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 9+41.64
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'


STAPLETON DRIVE
SECTION 10+00.00
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

STAPLETON DRIVE
SECTION 10+53.39
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1"=5'

Images missing

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


Quentin Armijo
QUENTIN ARMIJO
COLORADO P.E. NO. 37170



REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE
DRAWINGS ARE APPROVED
FOR CONSTRUCTION BY
REVIEWING AGENCIES
TERRA NOVA ENGINEERING,
INC. APPROVES THEIR USE
ONLY FOR THE PROJECTS
SPECIFICALLY AUTHORIZED BY
WRITTEN AUTHORIZATION.


PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800





721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnva.com

WATERBURY FILING NO. 1
CONSTRUCTION SET
STAPLETON DRIVE
CROSS SECTIONS


DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	NA
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	29 OF 54




**STAPLETON DRIVE
C&G AND STRIPING REMOVAL PLAN**



**STAPLETON DRIVE
SIGNAGE AND STRIPING PLAN**



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



STRIPING LEGEND		
STRIPE	PAVEMENT MARKINGS	MARKING DESCRIPTION
1	CENTER LINES (EPOXY)	DOUBLE SOLID YELLOW, 4" WIDE-SPACED 3" APART
2	LANE LINES (EPOXY)	BROKEN WHITE, 4" WIDE-10' SEGMENTS WITH 30' GAPS
3	EDGE LINES (EPOXY)	SOLID WHITE, 4" WIDE
4	CHANNELIZING LINES (EPOXY)	SOLID WHITE, 8" WIDE
5	STOP LINES (THERMO PLASTIC)	SOLID WHITE, 24" WIDE
6	CHEVRON LINES (THERMO PLASTIC)	SOLID WHITE, 8" WIDE, 8" C-C, 45° ANGLE
7	SKIP CHANNELIZING LINES (EPOXY)	SOLID WHITE, 4" WIDE, 2'-4" SKIP

*NOTE: ALL STRIPING INSTALLATION SHALL BE PER COLORADO DEPARTMENT OF TRANSPORTATION "M&S STANDARDS" STANDARD PLAN NO. S-627-1

NOTE TO CONTRACTOR
SIGNS AND POLES SHALL BE PER CDOT STANDARDS S-614-8, S-614-2, AND S-614-3, LATEST REVISION.
ALL SIGNAGE INSTALLATION IS TO BE IN COMPLIANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
ALL 4", 8" SOLID OR SKIP PAVEMENT MARKING ARE TO BE EPOXY.
STOP BARS ARE TO BE 90 MIL PREFORMED THERMOPLASTIC PAVEMENT MARKING TYPE B. (INLAYED)

DESIGN SPEED IS 50 M.P.H.

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE RELEVANT AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POKK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800


Terra Nova
Engineering, Inc.
Civil Engineering

721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.terra-nova.com



WATERBURY FILING NO. 1

SIGNING & STRIPING
C&G AND STRIPING REMOVAL
STAPLETON DRIVE


DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	AS SHOWN
V-SCALE	N/A
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	30 OF 54



STORM SEWER RUN-1 (PIPE RUN 7) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN-2 (PIPE RUN 5-6) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



STORM SEWER RUN-1 (PIPE RUN 7) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER RUN-2 (PIPE RUN 5-6)
 PROPOSED PUBLIC RCP STORM SEWER

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS, INC. AND APPROVED FOR THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

Terra Nova
 Engineering, Inc.
 Professional Engineer

721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnengine.com



WATERBURY FILING NO. 1

CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 STORM RUNS 1 & 2



DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 31 OF 54



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 32 OF 54

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 STORM RUNS 3 & 4

PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

REVISIONS
 NO. DESCRIPTION DATE

UNTL. SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE AGENCIES TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.

721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnva.com

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF PROFESSIONAL ENGINEERS AND SURVEYORS, INC. APPROVED THEIR USE ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM Alf VIII JV SUB II LLC
JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMILJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170





721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneng.com


WATERBURY FILING NO. 1

CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 STORM RUNS 5, 8 & 10


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 33 OF 54






STORM SEWER RUN-7 & LATERAL-1 (PIPE RUN 11, 13 & 14) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER LATERAL-2 (PIPE RUN 12) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


Quentin N. Armijo
 QUENTIN N. ARMILLO
 37170
 10/13/24
 PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



Terra Nova
 Engineering, Inc.
 721 S. 29th STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnengine.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 STORM RUN-7 & LATERALS 1-2

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 34 OF 54



STORM SEWER RUN-7 LATERAL-1 (PIPE RUN 11, 13 & 14) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER



STORM SEWER LATERAL-1 (PIPE RUN 11) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER LATERAL-2 (PIPE RUN 12) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 BY THE APPROPRIATE
 REVIEWING AGENCIES
 TERRA NOVA ENGINEERING
 AND SURVEYING, INC.
 APPROVES THEIR USE ONLY
 DESIGNATED BY WRITTEN
 AUTHORIZATION.


PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800



STORM SEWER LATERAL-3 & RUN-8 (PIPE RUN 16 & 17) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


Quentin N. Armijo
 QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



Terra Nova Engineering, Inc.
 721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnasec.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 LATERAL 3 & STORM RUN-8


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 35 OF 54





REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS, INC. APPROVES THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800




STORM SEWER LATERAL - 4 (PIPE RUN 19) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER LATERAL - 5 (PIPE RUN 21) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER LATERAL - 6 & 7 (PIPE RUN 23, 24 & 25) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armiyo
 QUENTIN N. ARMIYO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE
 DRAWINGS ARE APPROVED
 BY THE APPROPRIATE
 REVIEWING AGENCIES,
 TERRA NOVA ENGINEERING
 AND SURVEYING, INC. IS
 THE ONLY AUTHORITY FOR
 THE PURPOSES OF THIS
 DESIGNATED BY WRITTEN
 AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

6960	*USE WATERTIGHT JOINTS FOR PR 19	6960	*USE WATERTIGHT JOINTS FOR PR 21	6960	*USE WATERTIGHT JOINTS FOR PR 23 & PR 25	6960	*USE WATERTIGHT JOINTS FOR PR 24	6960
6950		6950		6950		6950		6950
6940		6940		6940		6940		6940
6930		6930		6930		6930		6930
1+50		1+00		3+00		2+00		1+00
STORM SEWER LATERAL - 4 (PIPE RUN 19) PHASE 2		STORM SEWER LATERAL - 5 (PIPE RUN 21) PHASE 2		STORM SEWER LATERAL - 6 (PIPE RUN 23 & 25) PHASE 2		STORM SEWER LATERAL - 7 (PIPE RUN 24) PHASE 2		
PROPOSED PUBLIC RCP STORM SEWER		PROPOSED PUBLIC RCP STORM SEWER		PROPOSED PUBLIC RCP STORM SEWER		PROPOSED PUBLIC RCP STORM SEWER		

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS


H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 2356.00
 DATE ISSUED 12/22/22
 SHEET NO. 36 OF 54



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 LATERALS 4-6

721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnva.com



Terra Nova
 Engineering, Inc.
 Colorado Licensed Professional Engineer
 37170
 10/13/2010




STORM SEWER RUN - 9 (PIPE RUN 29) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER RUN - 9 (PIPE RUN 31 & 33) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER LATERAL - 9 & 10 (PIPE RUN 30 & 32) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


Quentin N. Armijo
 QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE RELEVANT AGENCIES TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800



STORM SEWER RUN - 9 (PIPE RUN 29, 31 & 33) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER LATERAL - 10 (PIPE RUN 32) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER LATERAL - 9 (PIPE RUN 30) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS


H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 37 OF 54



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER PLAN AND PROFILE
 RUNS 9 & 10 AND LATERAL 9 & 10

721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnva.com


Terra Nova
 Engineering, Inc.
 Professional Engineer
 Colorado License No. 37170



STORM SEWER LATERAL - 8 (PIPE RUN 27 & 28) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN - 9 (PIPE RUN 20, 22 & 26) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

QUENTIN N. ARMILJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



STORM SEWER LATERAL - 8 (PIPE RUN 27 & 28) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER

STORM SEWER RUN - 9 (PIPE RUN 20, 22 & 26) PHASE 2
 PROPOSED PUBLIC RCP STORM SEWER

DATE: _____

REVISIONS

NO.	DESCRIPTION

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS, PROFESSIONAL LAND SURVEYORS AND SURVEYING, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS


H-SCALE 1"=50'
 V-SCALE 1"=5'

JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 38 OF 54



WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER RUN 9 & LATERAL 8

721 S. 2900 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnva.com


Terra Nova
 Engineering, Inc.
 Professional Engineer
 Colorado License No. 37170




STORM SEWER LATERAL - 10 (PIPE RUN 34) PHASE 1
 PROPOSED PRIVATE RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




SANITARY SEWER UNDERDRAIN OUTFALL TO EJECTOR PIT - PHASE 1
 PROPOSED PUBLIC 8" PVC
 1" = 50' HORIZ. 1" = 5' VERT.



STORM SEWER RUN - 12 (PIPE RUN 35) PHASE 1
 PROPOSED PRIVATE RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



6940		6940		6940		6940		6940	
6930	35.34 LF ~ 24" STORM SEWER @ 1.35% (PR-34 Q ₁₀₀ = 11 CFS)	6930		6930		6930		6930	
6920	105.58 LF ~ 30" STORM SEWER @ 0.50% (PR-34 Q ₁₀₀ = 24 CFS)	6920		6920		6920		6920	
6910	7.07 LF SOLID 8" PVC	6910		6910		6910		6910	
6900	56.28 LF SOLID 8" PVC	6900		6900		6900		6900	
3+00	2+00	1+00		200+50	200+00		1+00	2+00	3+00

STORM SEWER RUN - 10 (PIPE RUN 34) PHASE 1
 PROPOSED PUBLIC RCP STORM SEWER


SANITARY SEWER UNDERDRAIN OUTFALL TO EJECTOR PIT - PHASE 1
 PROPOSED PUBLIC 8" PVC

STORM SEWER RUN - 12 (PIPE RUN 35) PHASE 1
 PROPOSED PRIVATE RCP STORM SEWER

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPROPRIATE AGENCIES, TERRA NOVA ENGINEERING AND SURVEYING, INC. APPROVES THEIR USE ONLY AS DESIGNATED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
ACM ALF VIII JV SUB II LLC
JASON POKK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800





721 S. 2500 STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneng.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER RUN 10, 11 & 12


DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 39 OF 54



STORM SEWER LATERAL-12 (PIPE RUN 39) PHASE 1
 PROPOSED PRIVATE 12" HDPE STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER LATERAL-13 (PIPE RUN 40) PHASE 1
 PROPOSED PRIVATE 12" HDPE STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMIJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170




STORM SEWER LATERAL-12 (PIPE RUN 39) PHASE 1
 PROPOSED PRIVATE 12" HDPE STORM SEWER





STORM SEWER LATERAL-13 (PIPE RUN 40) PHASE 1
 PROPOSED PRIVATE 12" HDPE STORM SEWER


DATE	
DESCRIPTION	
REVISIONS	
NO.	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY DESIGNATED BY WRITTEN AUTHORIZATION.	
PREPARED FOR:	ACM ALF VIII JV SUB II LLC
	JASON POKK
	00 E. MISSISSIPPI AVE., STE 500
	DENVER, CO 80246
	303-984-9800
721 S. 2900 STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tneng.com	
WATERBURY FILING NO. 1	
CONSTRUCTION SET	
STORM SEWER LATERAL 13, 14	
DESIGNED BY	QNA
DRAWN BY	QNA
CHECKED BY	JS
H-SCALE	1"=50'
V-SCALE	1"=5'
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	40 OF 54



STORM SEWER LATERAL-14 PIPE RUN 38 PHASE 2
 PROPOSED PRIVATE 12" HDPE STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER LATERAL-15 (PIPE RUN 37) PHASE 2
 PROPOSED PRIVATE 12" HDPE STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMILLO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



STORM SEWER LATERAL-14 (PIPE RUN 38) PHASE 2
 PROPOSED PRIVATE 12" HDPE STORM SEWER



STORM SEWER LATERAL-15 (PIPE RUN 37) PHASE 2
 PROPOSED PRIVATE 12" HDPE STORM SEWER

NO.	DESCRIPTION	DATE

UNLESS OTHERWISE SPECIFIED, THESE DRAWINGS SHALL BE APPROVED BY THE APPROPRIATE AGENCIES. TERRA NOVA ENGINEERING, INC. ONLY APPROVES THESE DRAWINGS FOR THE PURPOSES DESIGNATED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VII JV SUB II LLC
JASON POKK
 100 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnva.com

Terra Nova
 Engineering, Inc.
 Creative Civil Engineer Inc.


WATERBURY FILING NO. 1

CONSTRUCTION SET
 STORM SEWER LATERAL 11, 12



DESIGNED BY QNA
 DRAWN BY QNA
 CHECKED BY JS

H-SCALE 1"=50'
 V-SCALE 1"=5'


JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 41 OF 54



STORM SEWER RUN-16 (PIPE RUN 41 & 43) PHASE 1
 PROPOSED PUBLIC 24" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




STORM SEWER RUN-17 (PIPE RUN 44) PHASE 1
 PROPOSED PRIVATE 18" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.





THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMILJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170



NO.	DESCRIPTION	DATE

PREPARED FOR:
ACM ALF VII JV SUB II LLC
JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800




STORM SEWER RUN-16 (PIPE RUN 41 & 43) PHASE 1
 PROPOSED PUBLIC 24" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.

STORM SEWER RUN-17 (PIPE RUN 44) PHASE 1
 PROPOSED PRIVATE 18" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.

721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnva-inc.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER RUNS 16 & 17


DESIGNED BY QNA
DRAWN BY JS
CHECKED BY JS
H-SCALE 1"=50'
V-SCALE 1"=5'
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 42 OF 54




STORM SEWER RUN-15 (PIPE RUN 42) PHASE 1
 PROPOSED PUBLIC 18" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.



SCALE: 1" = 50'




STORM SEWER RUN-18 (PIPE RUN 45) PHASE 1
 PROPOSED PUBLIC 30" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.




SCALE: 1" = 50'

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
 FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin N. Armijo
 QUENTIN N. ARMUJO, PROFESSIONAL ENGINEER
 COLORADO P.E. NO. 37170




PREPARED FOR:
ACM ALF VII JV SUB
JASON POCK
 00 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800



721 S. 23RD STREET,
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tneng.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 STORM SEWER RUNS 15 & 18








DESIGNED BY QNA
 DRAWN BY JS
 CHECKED BY JS
 H-SCALE 1"=50'
 V-SCALE 1"=5'
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 43 OF 54



STORM SEWER RUN-15 (PIPE RUN 42) PHASE 1
 PROPOSED PUBLIC 18" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.

STORM SEWER RUN-18 (PIPE RUN 45) PHASE 1
 PROPOSED PUBLIC 30" RCP STORM SEWER
 1" = 50' HORIZ. 1" = 5' VERT.


*USE WATERTIGHT JOINTS FOR PR 45




THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.




DATE	
REVISIONS	
NO.	
DESCRIPTION	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS, PROFESSIONAL LAND SURVEYORS, AND PROFESSIONAL ENGINEERS, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND ONLY AS AUTHORIZED BY WRITTEN AUTHORIZATION.	
PREPARED FOR: ACM ALF VIII JV SUB II LLC ATTN: JASON POKK 1000 E. MISSISSIPPI AVE., STE 500 DENVER, CO 80246 303-984-9800	
 Terra Nova Engineering, Inc. Civil Engineering 721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnec.com	
WATERBURY FILING NO. 1	
CONSTRUCTION SET	
STORM SEWER PLAN AND PROFILE	
GILBERT DRIVE CROSSING CULVERTS	
DESIGNED BY	DLF
DRAWN BY	QNA
CHECKED BY	QNA
H-SCALE	AS SHOWN
V-SCALE	AS SHOWN
JOB NO.	2356.00
DATE ISSUED	12/22/24
SHEET NO.	44 OF 54




POND 1 WEST CONCRETE FOREBAY/MICROPOOL DETAILS PHASE 1




POND 1 EAST CONCRETE FOREBAY DETAILS PHASE 1




POND 1 FLARED END SECTION PHASE 1
SCALE: N.T.S.




POND 1 TRASH RACK PHASE 1
F.E.S. DETAIL
SCALE: N.T.S.




24" RCP POND 1 OUTFALL PROFILE PHASE 1
PRIVATE
HORIZONTAL SCALE: 1" = 50'
VERTICAL SCALE: 1" = 5'



15" MAINTENANCE ACCESS
ROAD SECTION PHASE 1
NOT TO SCALE




TRICKLE CHANNEL PHASE 1
TYPICAL SECTION
N.T.S.





DETENTION POND 1 PHASE 1

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE AS SHOWN
V-SCALE AS SHOWN
JOB NO. 2356.00
DATE ISSUED 12/22/20
SHEET NO. 45 OF 54




DATE	DESCRIPTION	REVISIONS
		NO.
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE REVIEWING AGENCIES TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND ONLY FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.		
PREPARED FOR: ACM ALF VIII JV SUB II LLC ATTN: JASON POCK 100 E. MISSISSIPPI AVE., STE 500 DENVER, CO 80246 303-984-9800		
721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnec.com		
WATERBURY FILING NO. 1		
CONSTRUCTION SET POND 1 DETAILS		



**GRATE POND 1 & 2
PHASE 1 CONSTRUCTION**
ALL WELDED CONSTRUCTION
SCALE: N.T.S.




- NOTES:
1. WELD PLATES MAY BE SUBSTITUTED FOR PIPE EMBEDMENT.
 2. CONTRACTOR SHALL SUBMIT HANDRAIL SHOP DRAWINGS TO ENGINEER OF RECORD FOR APPROVAL PRIOR TO FABRICATION.
 3. DESIGN CRITERIA SHALL BE IN ACCORDANCE WITH AASHTO STANDARDS. HANDRAIL DESIGN SHALL BE COMPATIBLE WITH THE DESIGN OF THE WINGWALLS AND HEADWALLS.
 4. RAILING POSTS SHALL BE SET TO NORMAL TO GRADE. RAILS SHALL RUN PARALLEL TO THE SLOPES OF TOPS OF THE WALLS.
 5. ALL RAILS SHALL HAVE EXPANSION JOINTS SPACED AT 40'-0" MAX. JOINT ENDS SHALL BE FREE OF ANY SHARP EDGES OR CORNERS.






STEEL FABRICATION NOTES:


1. FABRICATED STEEL STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH AISC AND AWS SPECIFICATIONS.
2. THE OUTLET STRUCTURE BARGRATE IS DESIGNED FOR A VERTICAL LOAD OF 300 LBS./SQ. FT.
3. ALL STRUCTURAL STEEL SHAPES TO INCLUDE: ANGLE, PLATE, AND BAR SHALL MEET ASTM A36 SPECIFICATIONS, FY = 36 KSI MINIMUM. STRUCTURAL TUBING SHALL MEET ASTM A500 GRADE B SPECIFICATIONS, FY = 46 KSI MINIMUM. STEEL PIPE SHALL BE STANDARD WEIGHT PIPE ASTM A53 GRADE B, FY = 35 KSI MINIMUM.
4. WELDS NOT INDICATED SHALL BE 1/8" MINIMUM FILLET OR GROOVE, CONTINUOUS SO FAR AS POSSIBLE. CONSIDER VANDALISM LOADS, WELD ACCORDINGLY AT CRITICAL LOCATIONS.
5. PRIOR TO PAINTING REMOVE ALL OIL, SCALE, AND SLAG, GRIND OFF BURRS AND SHARP EDGES.
6. PAINT WITH ONE SHOP COAT OF ZINC RICH PRIMER AND TWO COATS OF ALUMINUM PAINT, AASHTO M-69



POND 1 & 2 CONCRETE MICROPOOL PHASE 1
SCALE: N.T.S.



**POND 1 OUTLET STRUCTURE PHASE 1
MODIFIED TYPE 1 MH**
SCALE: N.T.S.



Unresolved from Submittal 1.2: Is this an orifice? The orifice hole center is at the invert - this would not be possible to construct the full orifice hole as the bottom half is lower than the structural steel plate.


Update from Submittal 3: This design appears unconstructable. With low the plate is shown, the orifice hole would only be half drilled. The bottom half of the lowest orifice is within the concrete of the outlet structure, the plate will need a watertight seal and this design as shown appears to be impossible. I drew the orifice hole where it appears to be located within the concrete.

**POND 1 OUTLET STRUCTURE PHASE 1
MODIFIED TYPE 1 MH**
SCALE: N.T.S.

**WARNING
THIS AREA IS A
STORMWATER
FACILITY
AND IS SUBJECT TO
PERIODIC FLOODING**

**PET WASTE
MUST BE
PICKED UP**

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION
FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



DATE	
DESCRIPTION	
REVISIONS	
NO.	
UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER OF RECORD, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.	
PREPARED FOR: ACM ALF VIII JV SUB II LLC ATTN: JASON POCK 1100 E. MISSISSIPPI AVE., SE 50 DENVER, CO 80246 303-984-9800	
 Terra Nova Engineering, Inc. Civil Engineering 721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnainc.com	
WATERBURY FILING NO. 1	
CONSTRUCTION SET	
POND 1 DETAILS	
DESIGNED BY DLF	
DRAWN BY QNA	
CHECKED BY QNA	
H-SCALE NA	
V-SCALE N/A	
JOB NO. 2356.00	
DATE ISSUED 12/22/24	
SHEET NO. 46 OF 54	

REVISIONS	NO.	DESCRIPTION	DATE



UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL AGENCIES REVIEWING AGENCIES: TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
 ATTN: JASON POCK
 100 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800

Terra Nova
 Engineering, Inc.
 721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.terra-nova.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 POND 2 DETAILS

DESIGNED BY DLF
 DRAWN BY QNA
 CHECKED BY QNA
 H-SCALE AS SHOWN
 V-SCALE AS SHOWN
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 47 OF 54








WARNING
 THIS AREA IS A
 STORMWATER
 FACILITY
 AND IS SUBJECT TO
 PERIODIC FLOODING

PET WASTE
 MUST BE
 PICKED UP

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.






Quentin Armojo
 QUENTIN ARMOJO
 COLORADO P.E. NO. 37170

COLORADO LICENSED
 37170
 10/13/20



Unresolved from Submittal 1.2. Hole size not match detail below or what is shown in DR calcs. Revise to remove discrepancy.

What does this line represent and why does it extend through the outlet box? I believe this line is supposed to be at the top of the concrete. Add dimension to the concrete thickness as well.



DATE: _____

REVISIONS

NO. DESCRIPTION

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS OF THE STATE OF COLORADO, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND ONLY FOR THE PURPOSES AUTHORIZED BY WRITTEN AUTHORIZATION.


PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800

Terra Nova Engineering, Inc.
Civil Engineer
721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.tnec.com



WATERBURY FILING NO. 1

CONSTRUCTION SET
POND 3 DETAILS

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE AS SHOWN
V-SCALE N/A
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 48 OF 54




POND 3 GRATE PHASE 1 CONSTRUCTION
ALL WELDED CONSTRUCTION
SCALE: N.T.S.



NOTES:


1. WELD PLATES MAY BE SUBSTITUTED FOR PIPE EMBEDMENT.
2. CONTRACTOR SHALL SUBMIT HANDRAIL SHOP DRAWINGS TO ENGINEER OF RECORD FOR APPROVAL PRIOR TO FABRICATION.
3. DESIGN CRITERIA SHALL BE IN ACCORDANCE WITH AASHTO STANDARDS.
4. HANDRAIL DESIGN SHALL BE COMPATIBLE WITH THE DESIGN OF THE WINGWALLS AND HEADWALLS.
5. RAILING POSTS SHALL BE SET TO NORMAL TO GRADE. RAILS SHALL RUN PARALLEL TO THE SLOPES OF TOPS OF THE WALLS.
6. ALL RAILS SHALL HAVE EXPANSION JOINTS SPACED AT 40'-0" MAX. JOINT ENDS SHALL BE FREE OF ANY SHARP EDGES OR CORNERS.





SECTION B-B
SCALE: 1"=1'

STEEL FABRICATION NOTES:


1. FABRICATED STEEL STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH AISC AND AWS SPECIFICATIONS.
2. THE OUTLET STRUCTURE BARGRATE IS DESIGNED FOR A VERTICAL LOAD OF 300 LBS./SQ. FT.
3. ALL STRUCTURAL STEEL SHAPES TO INCLUDE: ANGLE, PLATE, AND BAR SHALL MEET ASTM A36 SPECIFICATIONS, FY = 36 KSI MINIMUM. STRUCTURAL TUBING SHALL MEET ASTM A500 GRADE B SPECIFICATIONS, FY = 46 KSI MINIMUM. STEEL PIPE SHALL BE STANDARD WEIGHT PIPE ASTM A53 GRADE B, FY = 35 KSI MINIMUM.
4. WELDS NOT INDICATED SHALL BE 1/8" MINIMUM FILLET OR GROOVE, CONTINUOUS SO FAR AS POSSIBLE. CONSIDER VANDALISM LOADS, WELD ACCORDINGLY AT CRITICAL LOCATIONS.
5. PRIOR TO PAINTING REMOVE ALL OIL, SCALE, AND SLAG, GRIND OFF BURRS AND SHARP EDGES.



POND 3 CONCRETE MICROPOOL PHASE 1
SCALE: N.T.S.



POND 3 OUTLET STRUCTURE MODIFIED TYPE 1 MH PHASE 1
SCALE: N.T.S.



POND 3 OUTLET STRUCTURE MODIFIED TYPE 1 MH PHASE 1
SCALE: N.T.S.

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



DATE:	DESCRIPTION:	REVISIONS:
UNTL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER OF RECORD, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECTS AUTHORIZED BY WRITTEN AUTHORIZATION.		
PREPARED FOR: ACM ALF VIII JV SUB II LLC ATTN: JASON POKK 100 E. MISSISSIPPI AVE., STE 500 DENVER, CO 80246 303-984-9800		
 Terra Nova Engineering, Inc. Civil Engineer 721 S. 23RD STREET COLORADO SPRINGS, CO 80904 OFFICE: 719-635-6422 FAX: 719-635-6426 www.tnec.com		
WATERBURY FILING NO. 1		
CONSTRUCTION SET POND 3 DETAILS		
DESIGNED BY: DLF	DRAWN BY: QNA	CHECKED BY: QNA
H-SCALE: AS SHOWN	V-SCALE: N/A	
JOB NO. 2356.00	DATE ISSUED 12/22/21	SHEET NO. 49 OF 54

Riprap Materials

STEP 1 (Materials):

- Riprap should be crushed, angular granite.
- Verify that riprap meets requirements for color, size and gradation. Confirm size and gradations by checking delivery tickets and measure dimensions of the rock using a tape measure.
- Due to quarry availability and material variability, it may be necessary to adjust the size. Get approval from the Engineer before making any material adjustments.

The District has 5 different riprap sizes or gradations:

- Type VL (D50 6")
- Type L (D50 9")
- Type M (D50 12")
- Type H (D50 18")
- Type VH (D50 24")



Type VH Riprap (D50 = 24-inches)

Conventional and Soil Riprap Construction Guidance Checklist

4

Riprap Materials

Table 1: Riprap Gradation

Riprap Designation	% Smaller than Given Size by Weight	Intermediate Rock Dimension (inches)	d_{50} (inches)
Type VL	70 - 100	12	6
	50 - 70	9	
	35 - 50	6	
Type L	70 - 100	15	9
	50 - 70	12	
	35 - 50	9	
Type M	70 - 100	21	12
	50 - 70	18	
	35 - 50	12	
Type H	70 - 100	30	18
	50 - 70	24	
	35 - 50	18	
Type VH	70 - 100	41	24
	50 - 70	33	
	35 - 50	24	

* d_{50} - Mean Particle Size

Conventional and Soil Riprap Construction Guidance Checklist

6

Soil Riprap Mixing

STEP 2 (Soil Riprap Mixing):

- Soil riprap is created by mixing 2/3 riprap with 1/3 soil by volume. Soil material should be native or topsoil.
- Front end loaders or excavators should be used to scoop up the riprap and soil material and add into a combined mixing pile.
- Verify that the proper proportions of the riprap and soil are used.
- Verify that the materials are thoroughly mixed using a loader or large track excavator. The final product should consist of a uniform mixture of soil and riprap without voids.



Soil riprap being mixed

Conventional and Soil Riprap Construction Guidance Checklist


7

Conventional/Soil Riprap Subgrade

STEP 3 (Subgrade):

Verify that the subgrade is prepared prior to riprap installation.

- Confirm that areas to receive riprap are excavated to a depth that accounts for the riprap thickness, topsoil and granular bedding thickness if specified.
- Subgrade should be firm and unyielding.
- There should be no groundwater present during riprap installation.



Excavated subgrade for riprap

Conventional and Soil Riprap Construction Guidance Checklist


8

Conventional/Soil Riprap Installation

STEP 4 (Bedding):

Granular bedding material is generally required under conventional riprap to prevent piping of underlying subgrade soils. It is not typically required for soil riprap. Verify that:

- Granular bedding is crushed, angular rock that meets gradation requirements.
- Granular bedding is placed at specified thickness.



Granular Bedding

Conventional and Soil Riprap Construction Guidance Checklist


9

Conventional/Soil Riprap Installation

STEP 5 (Installation):

Riprap should be installed to the lines and grades shown on the plans. Verify that:

- Riprap is placed at thickness specified.
- Riprap is placed and well distributed such that there are no large accumulations of either smaller or larger sizes of stone. If segregation occurs during placement, riprap will need to be reworked to ensure that it is well mixed.
- Larger rock material is flush to the top surface and arranged to minimize voids with smaller rock material in between.



Soil riprap installation complete before topsoil placement

Conventional and Soil Riprap Construction Guidance Checklist

10

Conventional/Soil Riprap Installation

STEP 5 (Installation continued):

- Make sure that conventional and soil riprap is consolidated and compacted with an excavator bucket (plated) or a tracked piece of equipment to smooth the surface and interlock the rock material.
- For soil riprap, verify that there are no excessively thick zones or pockets of soil that could create a weak spot and be prone to washing out.



Conventional and Soil Riprap Construction Guidance Checklist

11

Conventional/Soil Riprap Installation

STEP 5 (Installation continued):

- Following placement, soil riprap is sometimes specified to be buried with several inches of topsoil.




Soil riprap installed and ready to be covered with topsoil

Conventional and Soil Riprap Construction Guidance Checklist

12

Finished Installation

After mixing, placing and compacting, soil riprap should be smooth on the surface and all the voids filled with soil.



Finished installation of soil riprap along channel bank (prior to being covered with topsoil)


Conventional and Soil Riprap Construction Guidance Checklist

14

REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE ENGINEER, NO CONSTRUCTION SHALL BE PERMITTED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POKK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800




721 S. 23RD STREET
COLORADO SPRINGS, CO 80904
OFFICE: 719-635-6422
FAX: 719-635-6426
www.treshinc.com


WATERBURY FILING NO. 1
CONSTRUCTION SET
SOIL RIPRAP DETAILS

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE NA
V-SCALE N/A
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 50 OF 54




QUENTIN ARMIJO
COLORADO P.E. NO. 37170




TYPICAL SOIL/RIPRAP BANK LINING
SCALE: N.T.S.





PLAN VIEW



PROFILE VIEW (CENTER LINE)
GROUTED BOULDER DROP STRUCTURE DETAIL
NOT TO SCALE



12' OR 20' CHANNEL MAINTENANCE ACCESS ROAD SECTION
SCALE: N.T.S.



GENERAL NOTES

- B24 BOULDERS ARE 24" MIN.

CONSTRUCTION REQUIREMENT NOTES

- GROUT DEPTH RANGES FROM HALF TO FULL BOULDER HEIGHT. ALL GROUT SHALL BE A MINIMUM HALF BOULDER HEIGHT.
- AN EDGE WALL IS REQUIRED AROUND THE ENTIRE DROP STRUCTURE.
- THE MAX ALLOWABLE INDIVIDUAL DROP HEIGHT OFF A BOULDER IS 1.5' (0.5' USED IN DESIGN).

CHANNEL REVEGETATION SPECS (OUTSIDE WETLANDS)

SEED DISTURBED CHANNEL AREA PER COLORADO SPRINGS SCM TABLE 5-1 EL PASO COUNTY CONSERVATION DISTRICT ALL-PURPOSE MIX FOR UPLAND, TRANSITION AND PERMANENT CONTROL MEASURE AREAS AND COLORADO SPRINGS DCM VOL 1 TABLE 14-10 'WILDFLOWER MIX'. SEED ALL DISTURBED.

LEGEND

- EXISTING MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- PROPOSED CONTOUR
- SUBDIVISION BOUNDARY
- CHANNEL FLOW LINE
- 100-Y FEMA FLOODPLAIN
- EXISTING 100-Y HWL PER HECRAS ANALYSIS
- PROPOSED 100-Y HWL PER HECRAS ANALYSIS
- PROPOSED RIPRAP
- PROPOSED PLANTING AREA


THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



REVISIONS	NO.	DESCRIPTION	DATE


UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL JURISDICTION, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
ATTN: JASON POCK
100 E. MISSISSIPPI AVE., STE 500
DENVER, CO 80246
303-984-9800



WATERBURY FILING NO. 1
CONSTRUCTION SET
WEST CHANNEL - CHANNEL IMPROVEMENTS PLAN


DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE AS SHOWN
V-SCALE N/A
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 51 OF 54



WATERBURY WEST CHANNEL (HAEGLER RANCH TRIBUTARY 1) PLAN & PROFILE VIEW
 HORZ SCALE: 1"=100' - VERT SCALE: 1"=10'

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

Quentin Armijo
 QUENTIN ARMJO
 COLORADO P.E. NO. 37170



REVISIONS	NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE BOARD OF ARCHITECTS, ENGINEERS AND SURVEYORS OF THE STATE OF COLORADO, THIS DOCUMENT IS NOT TO BE USED FOR ANY PROJECT WITHOUT WRITTEN AUTHORIZATION.

PREPARED FOR:
 ACM ALF VIII JV SUB II LLC
 ATTN: JASON POCK
 100 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 303-984-9800


Terra Nova
 Engineering, Inc.
 Creative Civil Engineering

721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnec.com

WATERBURY FILING NO. 1

CONSTRUCTION SET
 WEST CHANNEL - PLAN AND PROFILE

DESIGNED BY DLF
DRAWN BY QNA
CHECKED BY QNA
H-SCALE AS SHOWN
V-SCALE AS SHOWN
JOB NO. 2356.00
DATE ISSUED 12/22/24
SHEET NO. 52 OF 54



HATCH LEGEND:

UNDERDRAIN PIPE CONFORMS TO DETAIL B

LOCATION WHERE UNDERDRAIN PIPES ARE A HIGHER THE SANITARY SEWER MAIN

NO HATCH OVER SANITARY MAIN CONFORMS TO DETAIL A


UNDERDRAIN NOTES:

1. ALL PROPOSED UNDERDRAINS SHALL BE 6" PERFORATED PVC ACTIVE UNDERDRAINS UNLESS OTHERWISE NOTED.
2. ALL UNHATCHED AND CROSS-HATCHED SANITARY PIPES SHOWN ARE TO CONFORM TO EXHIBIT A UNLESS OTHERWISE NOTED. SEE DETAILS NEXT SHEET.
3. UNDERDRAIN SIZING IS PRELIMINARY ONLY. FINAL DESIGN TO BE DONE BY ENTECH ENGINEERING, INC.

GENERAL CONSTRUCTION NOTES:

1. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITIES ALONG THE ROUTE OF THE WORK. THE OMISSION FROM OR THE INCLUSION OF UTILITY LOCATIONS ON THE PLANS IS NOT TO BE CONSIDERED AS THE NONEXISTENCE OF OR A DEFINITE LOCATION OF EXISTING UNDERGROUND UTILITIES.
2. THE CONTRACTOR WILL TAKE THE NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES FROM DAMAGE DUE TO THIS OPERATION. ANY DAMAGE TO THE UTILITIES WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE, AND ANY SERVICE DISRUPTION WILL BE SETTLED BY THE CONTRACTOR.
3. ADDITIONAL EROSION CONTROL STRUCTURES MAY BE REQUIRED AT THE TIME OF CONSTRUCTION.
4. ALL BACKFILL, SUB-BASE AND/OR BASE COURSE (CLASS 6) MATERIAL SHALL BE COMPACTED TO THE SOILS ENGINEER'S RECOMMENDATIONS, AND APPROVED BY EL PASO COUNTY DEVELOPMENT SERVICES ENGINEERING DIVISION.
5. ALL STATIONING IS CENTERLINE UNLESS OTHERWISE INDICATED. ALL ELEVATIONS ARE FLOWLINE UNLESS OTHERWISE INDICATED.
6. ALL DISTURBED PAVEMENT EDGES SHALL BE CUT TO NEAT LINES. REPAIR SHALL CONFORM TO THE EPC ECM APPENDIX K - 1.2C.
7. ALL INTERSECTION ACCESSES TO BE CONSTRUCTED WITH A 25 FOOT SIGHT VISIBILITY TRIANGLES EXCEPT STAPLETON DRIVE WHICH IS AN ARTERIAL AND A 50 FOOT SIGHT VISIBILITY TRIANGLE IS REQUIRED AND THERE SHALL BE NO OBSTRUCTIONS GREATER THAN 18" IN THIS AREA.
8. ALL CULVERT AND STORM DRAIN PIPES SHALL BE SMOOTH INTERIOR CORRUGATED POLYETHYLENE PIPE (HDPE), REINFORCED CONCRETE PIPE (RCP). ALL CULVERTS SHALL BE PLACED COMPLETE WITH FLARED END SECTIONS. ADEQUACY OF MATERIAL THICKNESS FOR ANY CSP INSTALLED SHALL BE VERIFIED BY OWNER'S GEOTECHNICAL ENGINEER TO SUPPORT MINIMUM 50 YEAR DESIGN LIFE. CULVERTS MUST CONFORM TO EPC ECM SECTION 3.32 - CULVERTS.
9. ADDITIONAL STRUCTURES INCLUDING EROSION CONTROL MAY BE REQUIRED AT TIME OF CONSTRUCTION.
10. ASPHALT THICKNESS AND BASE COURSE THICKNESS (COMPACTED) FOR ROADS SHALL BE PER DESIGN REPORT BY OWNER'S GEOTECHNICAL ENGINEER. OWNER'S GEOTECHNICAL ENGINEER TO BE ON SITE AT TIME OF ROAD CONSTRUCTION TO EVALUATE SOIL CONDITIONS AND DETERMINE IF ADDITIONAL MEASURES ARE NECESSARY TO ASSURE STABILITY OF THE NEW ROADS. PAVEMENT DESIGN SHALL BE APPROVED BY EL PASO COUNTY DEVELOPMENT SERVICES ENGINEERING DIVISION PRIOR TO CONSTRUCTION.
11. TYPE L RIP-RAP WITH MIRAFI W 700 OR EQUAL IS REQUIRED UNDER ALL RIP-RAP PADS.
12. ALL MATERIALS AND INSTALLATION PROCEDURES SHALL BE IN COMPLIANCE WITH ANY AND ALL APPLICABLE EL PASO COUNTY STANDARDS AND WITH 4-WAY RANCH METRO DISTRICT CONSULTING ENGINEER APPROVAL.
13. ALL POTABLE WATER MAINS SHALL BE AWWA C900-D14 PVC WITH PUSH-ON SINGLE GASKET TYPE JOINTS AND SHALL MEET THE REQUIREMENTS OF ANSI/NSF 61.
14. ALL WATER MAIN FITTINGS SHALL BE CAST IRON AND FURNISHED WITH MECHANICAL JOINT ENDS. ALL FITTINGS SHALL HAVE A PRESSURE RATING OF 250 PSI AND SHALL MEET THE REQUIREMENTS OF ANSI/NSF 61.
15. ALL WATER LINE BENDS, TEES, BLOW-OFFS AND PLUGS AT DEAD-END MAINS SHALL BE PROTECTED FROM THRUST BY USING CONCRETE THRUST BLOCKS AND/OR RODDING AND RESTRAINED PIPE PER THE 4-WAY RANCH METRO DISTRICT CONSULTING ENGINEER APPROVAL.
16. MAXIMUM DEFLECTION OF 8" & 12" PVC WATER MAIN JOINTS IS 4 DEGREES. CORRESPONDING MINIMUM CURVE RADIUS IS 286'. ADDITIONAL 11.25" OR 22.5" BENDS MAY BE REQUIRED FOR PROPER ALIGNMENT.
17. CONTRACTOR IS RESPONSIBLE FOR PROVIDING DETAILED AS-BUILTS OF ALL WATER MAIN, STORM SEW AND SAN. SEW. MAIN INSTALLATIONS, INCLUDING ACCURATE DISTANCES OF MAIN LINES, VALVES, FITTINGS, MANHOLES AND LOCATIONS OF WATER AND SEWER SERVICES.
18. SANITARY SEWER PIPE AND FITTINGS: PVC 4"-8" ASTM D3034, TYPE PSM, SDR 35; PUSH-ON JOINTS AND MOLDED RUBBER GASKETS MAXIMUM HORIZONTAL DEFLECTION AFTER INSTALLATION AND BACK FILLING SHALL NOT EXCEED 3% OF THE PIPE DIAMETER. (MINIMUM CURVE RADIUS IS 100' FOR 8" PVC SAN. SEW. MAIN)

THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.



DATE	
DESCRIPTION	
REVISIONS	
NO.	

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE APPLICABLE AGENCIES REVIEWING AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND AS AUTHORIZED BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
 ATTN: JASON POCK
 100 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 (303) 984-9800

721 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnainc.com

Terra Nova
 Engineering, Inc.




WATERBURY FILING NO. 1

CONSTRUCTION SET
 UNDERDRAIN PLAN
 SOUTH




DESIGNED BY QNA
 DRAWN BY JS
 CHECKED BY QNA

H-SCALE 1"=50'
 V-SCALE N/A

JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 53 OF 54



HATCH LEGEND:
 UNDERDRAIN PIPE CONFORMS TO DETAIL B
 LOCATION WHERE UNDERDRAIN PIPES ARE A HIGHER ELEVATION THAN THE SANITARY SEWER MAIN
 NO HATCH OVER SANITARY MAIN CONFORMS TO DETAIL A



THIS DESIGN WAS PREPARED UNDER MY DIRECT SUPERVISION FOR AND ON BEHALF OF TERRA NOVA ENGINEERING, INC.

REVISIONS

NO.	DESCRIPTION	DATE

UNTIL SUCH TIME AS THESE DRAWINGS ARE APPROVED BY THE LOCAL JURISDICTION REVIEWING AGENCIES, TERRA NOVA ENGINEERING, INC. APPROVES THEIR USE ONLY FOR THE PROJECT AND SITE SPECIFIC AUTHORIZATION BY WRITTEN AUTHORIZATION.

PREPARED FOR:
ACM ALF VIII JV SUB II LLC
 ATTN: JASON POCK
 100 E. MISSISSIPPI AVE., STE 500
 DENVER, CO 80246
 (303) 984-9800

Terra Nova Engineering, Inc.
 727 S. 23RD STREET
 COLORADO SPRINGS, CO 80904
 OFFICE: 719-635-6422
 FAX: 719-635-6426
 www.tnainc.com

WATERBURY FILING NO. 1
 CONSTRUCTION SET
 UNDERDRAIN PLAN
 NORTH

DESIGNED BY QNA
 DRAWN BY JS
 CHECKED BY QNA
 H-SCALE 1"=50'
 V-SCALE N/A
 JOB NO. 2356.00
 DATE ISSUED 12/22/24
 SHEET NO. 54 OF 54

MATCHLINE - SEE SHEET 53