

O UNION PACIFIC RAILROAD  
1700 FARNAM ST.  
OMAHA, NE 68102-2022

5  
N48°18'00"E 187.91'  
238.09'  
24.00'

KENTUCKY COFFEETREE  
PONDEROSA PINE  
AGGREGATE 'A'

EXISTING 42" RCP  
STORM SEWER

SCHEDULE NO.: 6510100011  
CITY OF COLORADO SPRINGS

EXISTING 14"  
SLUDGELINE

EXISTING TRAFFIC  
SIGNALS

SCHEDULE NO.: 6510100007  
CITY OF COLORADO SPRINGS  
C/O LAND OFFICE  
P.O. BOX 1103  
COLORADO SPRINGS, CO 80903

PLAN NORTH  
0' 30' 60' 90'  
SCALE: 1" = 30' - 0"

**William Gunnar & Associates, Ltd.**  
731 North Weber Street, Suite 10  
Colorado Springs, CO 80903  
719.633.9700 fax 719.633.4250  
Email: WGunnar@aol.com

NOTE: THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE EXCLUSIVE PROPERTY OF WILLIAM GUNNAR & ASSOCIATES, LTD. WHETHER WORK FOR WHICH IT WAS PREPARED IS EXECUTED OR NOT. UNAUTHORIZED USE AND/OR REPRODUCTION OF THIS DRAWING FOR ANY PURPOSE IS STRICTLY PROHIBITED WITHOUT WRITTEN CONSENT FROM GUNNAR.

**South Academy Business Center  
Landscape Development Plan**  
ACADEMY BLVD., COLORADO SPRINGS, CO

DATE: 08/07/2017  
DRAWN: GEM  
CHECKED: WFG


REVISIONS:		
DATE:	BY:	COMMENTS:
02/28/2020	GEM	Revised per note 10a

LANDSCAPE  
DEVELOPMENT  
PLAN

SHEET NO.

**LS1**  
1 of 4 SHEETS







**William Gunnar & Associates, Ltd.**  
URBAN PLANNING | COMMUNITY DESIGN | LANDSCAPE ARCHITECTURE  
731 North Weber Street, Suite 10  
Colorado Springs, CO 80903  
719.633.9700 fax 719.633.4250  
Email: WGunnar@aol.com

©2017. THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE EXCLUSIVE PROPERTY OF WILLIAM GUNNAR & ASSOCIATES, LTD. WHETHER WORK FOR WHICH IT WAS PREPARED IS EXECUTED OR NOT. UNAUTHORIZED USE AND/OR REPRODUCTION OF THIS DRAWING FOR ANY PURPOSE IS STRICTLY PROHIBITED WITHOUT WRITTEN CONSENT FROM GUNNAR.

NOTE: ALL DRAWINGS ARE DIAGRAMMATIC. IN THE EVENT OF CONFLICT, QUANTITIES WHICH CAN BE DETERMINED GRAPHICALLY SUPERSEDE ALL OTHER SCHEDULED QUANTITIES, STATED OR IMPLIED. CHANGES WHICH ARE MADE WITHOUT PRIOR APPROVAL OF ENTITIES HAVING JURISDICTION OVER REVIEW AND APPROVAL OF THE RECORD DRAWINGS MAY RESULT IN DELAY OF FINAL ACCEPTANCE AND ISSUANCE OF CERTIFICATE OF OCCUPANCY WHERE APPLICABLE.

ONLY DRAWINGS WHICH BEAR THE OFFICIAL STAMP OF THE LICENSED LANDSCAPE ARCHITECT IN THE STATE OF COLORADO ARE VALID FOR CONSTRUCTION PURPOSES.

**South Academy Business Center**  
**Landscape Development Plan**  
ACADEMY BLVD., COLORADO SPRINGS, CO

DATE: 08/07/2017  
DRAWN: GEM  
CHECKED: WFG

REVISIONS:		
DATE:	BY:	COMMENTS:
02/28/2020	GEM	Revised per note 10a

LANDSCAPE DEVELOPMENT PLAN

SHEET NO.






**LS2**

2 OF 4 SHEETS






LANDSCAPE SCHEDULE  
Planting Schedule:

SYM.	QTY.	BOTANICAL/COMMON NAME	MATURE HT. W/D.	PLANTING SIZE	WATER REQUIREMENT
TREES					
	19	KENTUCKY COFFEETREE (Gymnocladia dioica 'Espresso')	50-60' 40-50'	2.0' cal.	Low
	10	WHITE FIR (Abies concolor)	80-90' 10-20'	2.0' cal.	Medium
	9	COLORADO BLUE SPRUCE (Picea pungens glauca)	40-60' 10-20'	2.0' cal.	Medium
	8	PONDEROSA PINE (Pinus ponderosa)	60-80' 30-40'	6' H.	Low
	107	SKYROCKET JUNIPER (Juniperus scopulorum 'Skyrocket')	15-20' 2-4'	6' H.	Low

SHRUBS

SYMBOL KEY:					
	AGGREGATE A: 3/4" SIZE CIMARRON DECORATIVE ROCK PLACED TO A UNIFORM DEPTH OF 3" ON FABRIC UNDERLAYMENT. (Equal to that supplied by Pioneer Sand and Gravel, Colorado Springs, CO)				

SITE CATEGORY CALCULATIONS

LANDSCAPE SETBACKS (or Double Frontage Lot Streetscapes)					
Street Name or Zone Boundary (elev.)	Street or Zone Boundary Classification ("SB")	Width (in ft.) Req. / Prov.	Linear Footage	Tree/Foot	No. of Trees Req./Prov.
HIGHWAY 65/87	Industrial	15' / 15'	1,813'	1/40'	46' / 46
Shrub Substitutes Required / Provided	Ornamental Grass Substitutes Required / Provided	Setback Plant Abbr. Denoted on Plan*	Percent Ground Plane Veg. Req. / Provided		
N/A	N/A	N/A	75%/75%		

\* Note existing trees to remain. = 0 existing to remain

MOTOR VEHICLE LOTS					
No. of Vehicle Spaces Provided	Shade Trees (1/15 Spaces Required / Provided)	Vehicle Lot Frontage (ft.)	Length of Frontage (ft.) (excluding driveways)	2/3 Length of Frontage (ft.)	
0	N/A	N/A	N/A	N/A	
Min. 3' Screening Plants Req./Prov.	Evergreen Plants Req.(50%) / Prov.	Length of Screening Wall or Berm Provided	Vehicle Lot Plant Abbr. on Plan*	Percent Ground Plane Veg. Req. / Provided	
N/A	N/A	N/A	N/A	N/A	

\* Note existing trees to remain.

INTERNAL LANDSCAPING					
Net Site Area (SF) (less public R.O.W.)	Percent Min. Internal Area (%)	Internal Area (SF) Required / Provided	Internal Trees (1/500 SF) Required / Provided		
N/A	N/A	N/A	N/A		
Shrub Substitutes Required / Provided	Ornamental Grass Substitutes Required / Provided	Internal Plant Abbr. Denoted on Plan	Percent Ground Plane Veg. Req. / Provided		
N/A	N/A	N/A	N/A		


LANDSCAPE BUFFERS & SCREENS					
Street Name or Property Line (elev.)	Width (in ft.) Req. / Prov.	Linear Footage	Buffer Trees (1/ 25') (=BT) Required / Provided	Evergreen Trees Req.(50%) / Provided	
East property line	15'/15'	1,921'	77' / 107'	100%	
Length of 6 ft. Opaque Structure Req. / Prov.	Buffer Tree Abbr. Denoted on Plan*	Ground Plane % Veg. Req. / Provided			
N/A	N/A	N/A			

OVERALL TOTAL TREES (Required/Provided):				123/ 153
OVERALL TOTAL SHRUB SUBSTITUTIONS (Required/Provided @ 1 Tree = 10 Shrubs):				N/A
OVERALL GROSS SITE AREA:	335,720 s.f. (7.71 ac)	100 %		
BUILDINGS:	0 s.f.	0 %		
PAVEMENT & PARKING LOTS:	279,748 s.f. (6.43 ac)	83.3 %		
SEEDDED/ REVEGETATED NON-IRRIGATED AREA:	0 s.f.	0 %		
SCODED/ IRRIGATED AREA:	0 s.f.	0 %		
AGGREGATE PLANTER BED AREA:	55,972 s.f. (1.28 ac)	16.7 %		


NOTES:  
A - THE LAND OWNER IS RESPONSIBLE FOR MAINTAINING ALL LANDSCAPING AS FIRST APPROVED BY THE PLANNING DEPARTMENT OR AS SUBSEQUENTLY AMENDED.  
B - REGULAR AND NORMAL LANDSCAPE MAINTENANCE SHALL INCLUDE WEEDING, IRRIGATION, FERTILIZING, AND PRUNING AND MOWING.  
C - REPLACEMENT OF DEAD, DISEASED OR SUBSTANTIALLY DAMAGED PLANT MATERIALS SHALL BE OF THE SAME OR SIMILAR TYPE AS SET FORTH IN THE LANDSCAPE PLAN APPROVED BY THE PLANNING DEPARTMENT. REPLACEMENT SHALL OCCUR IN THE NEXT PLANTING SEASON BUT IN ANY EVENT SUCH REPLACEMENT SHALL BE MADE IN A TIME PERIOD NOT EXCEEDING ONE YEAR.  
D - SEEDDED AREAS SHALL HAVE NO BARE AREAS LARGER THAN SIX (6) SQUARE INCHES AFTER GERMINATION.

LANDSCAPE NOTES:


- REFER TO SPECIFICATION **SECTION 32-94-00: LANDSCAPE ACCESSORIES** FOR REQUIRED INSTALLATION AND WORKMANSHIP STANDARDS FOR NEW LANDSCAPING. IN THE EVENT OF A CONFLICT IN REQUIREMENTS THE MOST STRINGENT INTERPRETATION WILL PREVAIL.
- DRAWINGS ARE DIAGRAMMATIC; PRECISE PLACEMENT OF LANDSCAPE ACCESSORIES MAY NOT BE POSSIBLE AS INDICATED. CONSULT PROJECT LANDSCAPE ARCHITECT PRIOR TO MAKING RANDOM FIELD CHANGES WHICH MAY ALTER DESIGN INTENT.
- QUANTITIES ARE PROVIDED FOR REFERENCE ONLY; VERIFY ALL QUANTITIES PRIOR TO SUBMITTING COST PROPOSAL. IN THE EVENT OF A CONFLICT BETWEEN SCHEDULED, IMPLIED, OR EXPRESSED QUANTITIES, QUANTITIES WHICH CAN BE DETERMINED GRAPHICALLY FROM THE DRAWINGS WILL PREVAIL IN ANY CASE.
- THE CONTRACTOR IS RESPONSIBLE FOR INSPECTION AND VERIFICATION OF ALL FIELD CONDITIONS AND RESOLVING CONFLICTS PERTAINING TO DIMENSIONS, LAYOUT, ETC., WHICH MAY AFFECT THE LANDSCAPE INSTALLATION. MOBILING SHALL BE CONSTRUED AS ACCEPTANCE OF CONDITIONS.
- COORDINATE ALL WORK INDICATED ON THESE DRAWINGS WITH WORK OF OTHER TRADES.
- THE PROJECT LANDSCAPE ARCHITECT RESERVES THE RIGHT TO CONSIDER AND APPROVE ALTERNATE INSTALLATIONS AT ANY TIME WHICH IN THE LANDSCAPE ARCHITECT'S OPINION MAXIMIZES THE CONSTRUCTION BUDGET AND MAINTAINS DESIGN INTENT.
- PROVIDE A 3 FOOT CLEAR SPACE AROUND THE CIRCUMFERENCE AROUND ALL FIRE HYDRANTS AND LIGHTING STANDARDS.
- CONTRACTOR TO UTILIZE STOCKPILED TOPSOIL FROM GRADING OPERATION AS MAY BE AVAILABLE. IF THE AMOUNT OF TOPSOIL NEEDED TO COMPLETE FINAL GRADING IS NOT AVAILABLE, THE CONTRACTOR SHALL IMPORT THE AMOUNT OF SOIL NEEDED.
- CONTRACTOR SHALL ENSURE THAT PROPER IRRIGATION IS CAPABLE OF ESTABLISHING AND SUSTAINING PLANT GROWTH FROM THE TIME OF INSTALLATION.
- SOIL AMENDMENT AND FINAL GRADING FOR ALL SOD AND SEEDDED TURF AREAS TO BE PROVIDED IN ACCORDANCE WITH SPECIFICATIONS.
- 4"x14 GAUGE GALVANIZED STEEL MAINTENANCE EDGING TO BE INSTALLED TO SEPARATE ALL ORGANIC AND AGGREGATE MULCHES FROM ADJACENT SOD AND SEEDDED TURF AREAS. PIN EDGING WITH 1/2" STEEL EDGING PINS AT 24" SPACING.
- ALL PLANT MATERIAL TO BE INSTALLED PER DETAILS AND SPECIFICATIONS. GUY AND STAKE ALL DECIDUOUS AND EVERGREEN TREES PER DETAILS. PROVIDE SHREDED MULCH RINGS IN RETENTION BASINS AROUND ALL TREES PLANTED IN SOD AND SEEDDED AREAS (MULCH RINGS ARE NOT REQUIRED FOR TREES PLANTED IN AGGREGATE MULCH AREAS).
- PLANT QUANTITIES AND SIZES INDICATED ARE THE MINIMUM TO SATISFY LANDSCAPE CODE REQUIREMENTS. NO SUBSTITUTIONS ARE PERMITTED WITHOUT PRIOR APPROVAL OF THE MUNICIPAL REVIEWING AGENCY.



A DECIDUOUS TREE PLANTING DETAIL  
NOT TO SCALE



B SHRUB PLANTING DETAIL  
NOT TO SCALE



C EVERGREEN TREE PLANTING DETAIL  
NOT TO SCALE

**William Gaman & Associates, Ltd.**  
URBAN PLANNING | COMMUNITY DESIGN | LANDSCAPE ARCHITECTURE

731 North Weber Street, Suite 10  
Colorado Springs, CO 80903  
719.633.9700 fax 719.633.4250  
Email: WGaman@aol.com

REGISTERED AMERICAN ARCHITECT - SEE LANDSCAPE ARCHITECTS

©2017. THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE EXCLUSIVE PROPERTY OF WILLIAM GAMAN & ASSOCIATES, LTD. WHETHER WORK FOR WHICH IT WAS PREPARED IS EXECUTED OR NOT. UNAUTHORIZED USE AND/OR REPRODUCTION OF THIS DRAWING FOR ANY PURPOSE IS STRICTLY PROHIBITED WITHOUT WRITTEN CONSENT FROM GUMAL.

NOTE: ALL DRAWINGS ARE DIAGRAMMATIC. IN THE EVENT OF CONFLICT, QUANTITIES WHICH CAN BE DETERMINED GRAPHICALLY SUPERSEDE ALL OTHER SCHEDULED QUANTITIES, STATED OR IMPLIED. CHANGES WHICH ARE MADE WITHOUT PRIOR APPROVAL OF ENTITIES HAVING JURISDICTION OVER REVIEW AND APPROVAL OF THE RECORD DRAWINGS MAY RESULT IN DELAY OF FINAL ACCEPTANCE AND ISSUANCE OF CERTIFICATE OF OCCUPANCY WHERE APPLICABLE.

ONLY DRAWINGS WHICH BEAR THE OFFICIAL STAMP OF THE LICENSED LANDSCAPE ARCHITECT IN THE STATE OF COLORADO ARE VALID FOR CONSTRUCTION PURPOSES.

South Academy Business Center  
Landscape Development Key  
ACADEMY BLVD., COLORADO SPRINGS, CO

DATE: 08/07/2017  
DRAWN: GEM  
CHECKED: WFG

REVISIONS:		
DATE:	BY:	COMMENTS:
02/28/2020	GEM	Revised per new base

LANDSCAPE & DEVELOPMENT  
DETAILS

SHEET NO.

LS4

4 of 4 SHEETS











