



# Final Drainage Report

Additional new comments may be provided on the re-submittal due to the comments provided.

# I68 Training Facility

+/-158.45 Acre Parcel

Project No. 61224

October 30, 2024

PCD File No. PPR2440

# **Final Drainage Report**

for

**I68 Training Facility** 

Project No. 61224

October 30, 2024

prepared for

**K. Marc Fitzwater** 9758 Vistas Park Drive Peyton, CO 80831

prepared by

MVE, Inc. 1903 Lelaray Street, Suite 200 Colorado Springs, CO 80909 719.635.5736

Copyright © MVE, Inc., 2024

61224-168 Training Facility-FDR.odt

# Statements and Acknowledgments

# **Engineer's Statement**

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by El Paso County for drainage reports and said report is in conformity with the applicable master plan of the drainage basin. I accept responsibility for any liability caused by any regligent acts, errors or omissions on my part in preparing this report.

Colorado No. 13348 For and on Behalf of MVE, Inc.

Developer's Statement	
I, the owner/developer have read and will comply with al drainage report and plan.	II of the requirements specified in this
K. Marc Fitzwater Owner	- Date
9758 Vistas Park Dr. Peyton, CO 80831	
El Paso County	
Filed in accordance with the requirements of the Drainage Paso County Engineering Criteria Manual and Land Develop	
Joshua Palmer P.E. County Engineer / ECM Administrator	Date

Conditions:

# Contents

Sı	tatements and Acknowledgments				
C	ontents	١			
Fi	inal Drainage Report	1			
1	General Location and Description	1			
	1.1 Location	1			
	1.2 Description of Property	1			
2	Drainage Basins and Sub-Basins	2			
	2.1 Major Basin Descriptions	2			
	2.2 Sub-Basin Description	2			
3	Drainage Design Criteria	2			
	3.1 Development Criteria Reference	2			
	3.2 Previous Drainage Studies	3			
	3.3 Hydrologic Criteria	3			
4	Drainage Facility Design	3			
	4.1 General Concept	3			
	4.2 Existing / Developed Hydrologic Conditions	3			
	4.3 Erosion Control	4			
	4.4 Four Step Process	2			
5	Drainage and Bridge Fees	4			
6	Conclusion	E			

References	7
Appendices	9
1 General Maps and Supporting Data	9
2 Hydrologic Calculations	10
3 Report Maps	41

# Final Drainage Report

In the introduction, please clarify whether this report is only for Phases 1-3 and a drainage letter will be submitted for Phase 4, or if this report is supposed to encompass the full development.

The purpose of this Final Drainage Report is to identify drainage patterns and quantities within and affecting the proposed I68 Training Facility site. The development project is to build an elite firearms training facility. The report will identify specific solutions to drainage concerns on-site and off-site resulting from the proposed project. The report and included maps present results of hydrologic and drainage facilities analyses. The report will discuss the recommended drainage improvements to the site and identify drainage requirements relative to the proposed project. This report has been prepared and submitted in accordance with the requirements of the El Paso County development approval process. An Appendix is included with this report with pertinent calculations and graphs used in the drainage analyses and design.

# 1 General Location and Description

### 1.1 Location

The proposed I68 Training Facility site is a tract of property located in Section 7, Township 13 South, Range 61 W of the 6<sup>th</sup> P.M. in El Paso County, Colorado. The 158.45 acre site is situated to the west of Calhan Highway, and this would be the road in which the site will be accessed from. The property is currently zoned as A-35.

The properties to the north and to the south of the site are also zoned as A-35 and are undeveloped. To the west of the site is Liberty Road.

A **Vicinity Map** is included in the **Appendix**. The entire site is located in El Paso County's Upper Big Springs Creek Drainage Basin.

# 1.2 Description of Property

The I68 Training Facility site 158.45 acres and is zoned A-35 (Agriculture). The property is undeveloped. El Paso County Tax Assessor's Schedule Number: 1300000712. The proposed I68 Training Facility includes a gravel access driveway, gravel parking areas, 6 shooting range areas each with a shooting overhead cover structure and one long distance shooting range.

The ground cover, which is in good condition, consists of native grasses. The land use is categorized as grazing.

The existing site topography slopes to the south-west with grades that range from 3% to 5%.

There are no major drainage ways in the I68 Training Facility site. For the entire site, all storm runoff flows drain to the south-west. There is no storm drain system in the surrounding area. The site is located in El Paso County's Upper Big Springs Creek Drainage Basin and the flows from the site flow south-west and eventually enter Big Springs Creek.

According to the National Resource Conservation Service, there are three (3) soil types in the I68 Training Facility site. Yoder gravelly-sandy loam (map unit 110) makes up about 80.9% of the site, Truckton sandy loam (map unit 97) makes up about 18.7% of the site and Bresser Sandy Loam (map unit 11) makes up about 0.3% of the soil on the site.

Please address the channel on the Western part of the site and minor drainage ways on the site

# Final Drainage Report

2

Yoder gravelly sandy loam is deep and somewhat excessively drained. Permeability is moderately rapid, surface runoff is medium to rapid, and the hazard of erosion is moderate. Yoder gravelly sandy loam is classified as being part of Hydrologic Soil Group A.

Truckton sandy loam is deep and well drained. Permeability is moderately rapid, surface runoff is slow to medium, and the hazard of erosion is moderate. Truckton sandy loam is classified as being part of Hydrologic Soil Group A.

The other soil type located on the site is Bresser sandy loam and this soil type makes up a very small portion of the site @ 0.3%. The soil is deep and well drained. Permeability is moderate, surface runoff is slow, and the hazard of erosion is moderate. Bresser sandy loam is classified as being part of Hydrologic Soil Group B.

A portion of the Soil Map and data tables from the National Cooperative Soil Survey and relevant Official Soil Series Descriptions (OSD) are included in the Appendix. 12

# 2 Drainage Basins and Sub-Basins

# 2.1 Major Basin Descriptions

The I68 Training Facility site is located in the Upper Big Springs Creek Drainage Basin (CHBG0400). No Drainage Basin Planning Studies are on file for this drainage basin.

The current Flood Insurance Study of the region includes Flood Insurance Rate Maps (FIRM), effective on December 7, 2018.3 The proposed training facility is included in the Community Panel Numbered 08041C0625 G of the Flood Insurance Rate Maps for the El Paso County. No part of the site is shown to be included in a 100-year flood hazard area as determined by FEMA. A portion of the current FEMA Flood Insurance Rate Maps with the site delineated is included in the Appendix.

# 2.2 Sub-Basin Description

The existing and developed drainage patterns of the I68 Training Facility project are described by four (4) on-site drainage basins and four (4) offsite basins. All of these basins are previously undisturbed. All existing basin delineations and data are depicted on the attached Existing Drainage Map.

# 2.2.1 Existing / Developed Drainage Patterns (Off-Site)

Off-site sub-basin OS-1 is located north and to the east end of the site, containing pasture/meadow areas, drains south onto the site. This flow enters the onsite sub-basin EX-A and continues through the site.

Off-site sub-basin OS-2 is located north of the site, containing pasture/meadow areas, drains south onto the site. This flow enters the onsite sub-basin EX-B and continues through the site.

Off-site sub-basin OS-3 is located north of the site and to the east of off-site sub-basin OS-2, containing pasture/meadow areas, drains south onto the site. This flow enters the onsite sub-basin EX-C and continues through the site.

Off-site sub-basin OS-4 is located north and to the west end of the site, containing pasture/meadow areas, drains south onto the site. This flow enters the onsite sub-basin EX-D and continues through the site.

# 2.2.2 Existing / Developed Drainage Patterns (On-Site)

Sub-basin EX-A is to the eastern portion of the site, containing pasture/meadow, drains south. The combined flows of sub-basin OS-1 and EX-A drains to the south and exits the site into the adjacent property.

OSD

Please include a simple

acceptable.

justification as to why having

one offsite basin at 145 acres is

Sub-basin EX-B is to the eastern-middle portion of the site, containing pasture/meadow, drains south-west. The combined flows of sub-basin OS-2 and EX-B drains to the south-west and exits the site into the adjacent property.

Sub-basin EX-C is to the western-middle portion of the site, containing pasture/meadow, drains south. The combined flows of sub-basin OS-3 and EX-C drains to the south and exits the site into the adjacent property.

Sub-basin EX-D is to the western portion of the site, containing pasture/meadow, drains south-west. The combined flows of sub-basin OS-4 and EX-D drains to the south-west and exits the site into the adjacent property.

# 3 Drainage Design Criteria

# 3.1 Development Criteria Reference

This Final Drainage Report for I68 Training Facility has been prepared according to the report guidelines presented in the latest edition of El Paso County Drainage Criteria Manual (DCM)4. The County has also adopted portions of the City of Colorado Springs Drainage Criteria Manual Volumes 1 and 2, especially concerning the calculation of rainfall runoff flow rates. 5 6 The hydrologic analysis is based on a collection of data from the DCM, the NRCS Web Soil Survey<sup>7</sup>, and existing topographic data by Polaris. OS-4 is shown as 145 acres.

# 3.2 Previous Drainage Studies

No drainage reports were found for any of the surrounding developments.

# 3.3 Hydrologic Criteria

For this Final Drainage Report, the Rational Method as described in the Drainage Criteria Manual has been used for all Storm Runoff calculations, as the development and all sub-basins are less than 130 acres in area. "Colorado Springs Rainfall Intensity Duration Frequency" curves, Figure 6-5 in the DCM, was used to obtain the design rainfall values; a copy is included in the Appendix. The "Overland (Initial) Flow Equation" (Eq. 6-8) in the DCM, and Manning's equation with estimated depths were used in time of concentration calculations. "Runoff Coefficients for Rational Method", Table 6-6 in the DCM, was utilized as a guide in estimating runoff coefficient and Percent Impervious values; a copy is included in the Appendix. Peak runoff discharges were calculated for each drainage sub-basin for both the 5-year storm event and the 100-year storm event with the Rational Method formula, (Eq. 6-5) in the DCM.8

# 4 Drainage Facility Design

### 4.1 General Concept

The intent of the drainage concept presented in this Final Drainage Report is to allow for the development of the 158.45+/- acres while maintaining the existing drainage patterns on the site. The site will be in compliance with the County's Stormwater Management regulations without the need for permanent water quality treatment facilities. Major and minor storm flows will continue to be safely conveyed through the site and downstream.

The site is expected to be constructed in several Phases as detailed in the Site Development Plan. This Drainage Report reflects the ultimate build out conditions and the maximum impact of the project.

The proposed drainage map and calculations do not include all of the proposed buildings mentioned in the LOI (admin, lodging, support, gym) or the Connex City.

DCM Section 4.3 and Section 4.4

CS DCM Vol 1 CS DCM Vol 2

WSS

DCM

All offsite basin flows should be included in onsite basins.

### 4 Final Drainage Report

The existing and proposed drainage hydrologic conc Please revise/clarify the sub-basin boundaries on the data and results for all calculations are included in the are also included in the **Appendix**.

drainage map. There are 3 proposed basins yet it appears that there are multiple sub-basins shown.

# 4.2 Existing Developed Hydrologic Conditions

The I68 Training Facility site includes four (4) sub-basins, four (4) on site and four (4) off site. The site generally drains south and south-west. The sub-basins are described in more detail below.

Offsite sub-bas n OS-1, located to the north and east side of the site, is 24.59± acres in area. Subbasin OS-1 contains a meadow/pasture area. Peak storm runoff rates are  $Q_5 = 3.1$  cfs and  $Q_{100} =$ 22.8 cfs (existing / developed flows) which drain on-site to the south. These flows continue south through sub-basin PR-A.

Sub-basin PR-A, located in the eastern portion of the site, is 18.94± acres in area and accepts the flows from off-site sub-basin OS-1. Sub-basin PR-A contains currently meadow/pasture and is proposed to have a gravel driveway. Proposed gravel driveway contains 20,607sf. Peak storm runoff rates are  $Q_5 = 3.8$  cfs and  $Q_{100} = 27.8$  cfs (existing flows) and runoff rates of  $Q_5 = 4.4$  cfs and  $Q_{100} =$ 28.7 cfs (developed flows) which drain to the south and onto the adjacent property over the length of the property and the flow is not concentrated. This is an increase of  $Q_5 = 0.6$  cfs (14%) and  $Q_{100} =$ 0.9 cfs (3%), which is minimal and will have no negative impact on downstream areas. The flows leave the site in an existing wide shallow depression.

Offsite sub-basin OS-2, located to the north and east-middle side of the site, is 113.37± acres in area. Sub-basin OS-2 contains a meadow/pasture area. Peak storm runoff rates are Q<sub>5</sub> = 9.2 cfs and  $Q_{100}$  = 67.1 cfs (existing / developed flows) which drain on-site to the south. These flows continue south through sub-basin PR-B. Map shows PR-C.

Sub-basin PR-B, to the eastern-middle portion of the site, is 56.08± acres in area. Sub-basin PR-B contains meadow/pasture, roofs from the shooting overhead cover structure, lawn/turf field, landscaping and a 140,871 sf of gravel driveway and gravel parking lots. Peak storm runoff rates are  $Q_5$  = 10.3 cfs and  $Q_{100}$  = 75.7 cfs (existing flows) and runoff rates of  $Q_5$  = 12.4 cfs and  $Q_{100}$  = 68.9 cfs (developed flows) which drain south and onto the adjacent property over the length of the property and the flow is not concentrated. This is an increase of  $Q_5 = 2.1$  cfs (17%) and a <u>decrease</u> of Q<sub>100</sub> = 6.8 cfs (9%). There is less flow for the proposed 100-yr. flows in this basin due to there being a difference in the time of concentrations. The time of concentration in the proposed basin condition is 8.4 minutes longer, and this is due to the proposed site grading simply making a longer path. Based on the rational equation, the longer time of concentration value, resulted in less flow volume. By comparing the change in flows for the existing and proposed conditions in this subbasin, the difference is minimal (and even reduced for the 100-yr event), thus, having no negative impact on downstream areas. The flows generally sheet flow off of the site to the south.

Offsite sub-basin OS-3, located to the north and west-middle side of the site, is 40.47± acres in area. Sub-basin OS-3 contains a meadow/pasture area. Peak storm runoff rates are  $Q_5$  = 6.8 cfs and  $Q_{100}$ = 50.2 cfs (existing / developed flows) which drain on-site to the south. These flows continue south through sub-basin PR-C. Map shows PR-D

Sub-basin PR-C, to the western-middle portion of the site, is 55.95± acres in area. Sub-basin PR-C contains meadow/pasture, roofs from the shooting overhead cover structure, lawn/turf field, landscaping and a 91,171 sf of gravel driveway and gravel parking lots. Peak storm runoff rates are  $Q_5 = 10.8$  cfs and  $Q_{100} = 79.6$  cfs (existing flows) and runoff rates of  $Q_5 = 12.0$  cfs and  $Q_{100} = 73.0$  cfs (developed flows) which drain south and onto the adjacent property over the length of the property and is not concentrated. This is an increase of  $Q_5 = 1.2$  cfs (10%) and a decrease of  $Q_{100} = 6.6$  cfs (8%). Similar to sub-basin PR-B, the time of concentration in the proposed basin condition is longer, due to the proposed site grading making a longer path. The flow reduction in this sub-basin, will result in no negative impacts on downstream areas. The flows leave the site to the south in several existing shallow swales.

Same comment as PR-A.

Offsite sub-basin OS-4, located to the north and west side of the site, is 145.35± acres in area. Subbasin OS-4 contains a meadow/pasture area. Peak storm runoff rates are  $Q_5 = 9.2$  cfs and  $Q_{100} =$ 

The contours and aerials show concentrated flows leaving the site.

67.6 cfs (existing / developed flows) which drain on-site to the south. These flows continue south through sub-basin PR-D.

Sub-basin PR-D, to the western portion of the site, is  $27.48\pm$  acres in area. Sub-basin PR-D contains meadow/pasture. Peak storm runoff rates are  $Q_5 = 5.0$  cfs and  $Q_{100} = 36.8$  cfs (existing flows) and runoff rates of  $Q_5 = 5.0$  cfs and  $Q_{100} = 36.8$  cfs (developed flows) which drain south-west and onto the adjacent property over the length of the property and is not concentrated. There are no flow increases in this sub-basin as this sub-basin remains undeveloped. Flows leave the site to the south in the existing drainage patterns.

### 4.3 Erosion Control

Proposed grading for the site will be associated with the shooting berms construction and gravel driveway and gravel parking lot installation. Control measures (CM's) for each phase of the project shall be installed individually for each phase and shall include temporary silt fencing.

# 4.4 Four Step Process

Please address erosion comments on the drainage maps

The El Paso County Engineering Criteria Manual (Appendix I, Section I.7.2) requires the consideration of a "Four Step Process for receiving water protection that focuses on reducing runoff volumes, treating the water quality capture volume (WQCV), stabilizing drainageways, and implementing long term source controls". The Four Step Process is incorporated in this project and the elements are discussed below.

The entire site consists of low impact development which is excluded from Post Construction Stormwater Management requirements by ECM I.7.1.B.5 due to the low development density as an agricultural zoned land, greater than 2.5 acres and having a total tract impervious area of less than 10%. There is no public roadway being dedicated or constructed as part of this project. The site is not subject to Post Construction Stormwater Treatment requirements.

- 1) Runoff Reduction Practices are employed in this project. Impervious surfaces have been reduced as much as practically possible. There is only minimal hard surfaces proposed. Minimized Directly Connected Impervious Areas (MDCIA) is employed on the project because runoff passes through an open space pasture/meadow area before leaving the site.
- 2) There are no drainage paths on the site that are required to be stabilized as they are well vegetated with no visual erosion.
- 3) The project contains no potentially hazardous uses. The site is exempted from the use of WQCV CMs by ECM 1.7.1.B.5 by virtue of the large agricultural lands zoning of the site and having percent imperiousness of less than 10%
- 4) The agricultural tract of land is not anticipated to contain storage of potentially harmful substances or use of potentially harmful substances. No site specific or other source control CMs are required.

# 5 Drainage and Bridge Fees

Please add percentage of imperviousness for the activities associated with this PPR/stage of the project.

The site is located within the Upper Big Springs Creek Drainage Basin, El Paso Basin Number CHBG0400, which which has no DBPS. There are no fees associated with this basin.

Note that as future phases occur, the site imperviousness will need to be assessed again to ensure the site is still in compliance with exclusion I.7.1.B.5

# This drainage report should cover the phases specifically shown in the GEC Plan and SDP, not full buildout. So please also make it clear what the % imperviousness for this stage itself so it is documented that this phase independently is under 10%. I understand it may be redundant but if future full build out changes this may not be an accurate % and doesn't address what is proposed at this time.

# 6 Conclusion

This Final Drainage Report presents existing and proposed drainage conditions for the proposed I68 Training Facility project. The development will have negligible and inconsequential effects on the existing site drainage and drainage conditions downstream. The site is exempted from the use of WQCV CMs by ECM 1.7.1.B.5 by virtue low development density as an agricultural zoned land, greater than 2.5 acres and having a total tract impervious area of less than 10%. The entire site upon final development of all phases, will be 3.1% impervious. The site is not subject to Post Construction Stormwater Treatment requirements. With such a negligible increase in stormwater flows from the site, detention will not be necessary for the proposed development and will not be provided. The proposed project will not, with respect to stormwater runoff, negatively impact the adjacent properties and downstream properties.

Please provide adequate justification for not providing detention.
Provide a comparison of the existing flows leaving the site with the proposed flows. Increased flows shall be mitigated as to not adversely impact the downstream properties.

Does this include the phase 4 buildings (admin, lodging, support, gym) or the Connex City as these are not included in the drainage map or calculations?

please refer to planners comments regarding the paving of the parking areas and revise accordingly.

# References

NRCS Web Soil Survey. United States Department of Agriculture, Natural Resources Conservation Service ("http://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx", accessed March, 2018).

NRCS Official Soil Series Descriptions. United States Department of Agriculture, Natural Resources Conservation Service

("http://soils.usda.gov/technical/classification/osd/index.html", accessed March, 2018).

Flood Insurance Rate Map. Federal Emergency Management Agency, National Flood Insurance Program (Washingon D.C.: FEMA, December 7, 2018).

*NCSS Web Soil Survey.* United States Department of Agriculture, Natural Resources Conservation Service ("http://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx", accessed May, 2017).

Drainage Criteria Manual Volume 2, Stormwater Quality Policies, Procedures and Best Management Practices (BMPs). City of Colorado Spring Engineering Division (Colorado Springs: , May 2014).

City of Colorado Springs Drainage Criterial Manual, Volume 1. City of Colorado Springs Engineering Division Staff, Matrix Desgin Group/Wright Water Engineers (Colorado Springs: , May 2014).

City of Colorado Springs/El Paso County Drainage Criteria Manual. City of Colorado Springs, Department of Public Works, Engineering Division; HDR Infrastructure, Inc.; El Paso County, Department of Public Works, Engineering Division (Colorado Springs: City of Colorado Springs, Revised November 1991).

City of Colorado Springs Drainage Criteria Manual Volume 1. City of Colorado Springs Engineering Division with Matrix Design Group and Wright Water Engineers (Colorado Springs, Colorado: , May 2014).

61224-168 Training Facility-FDR.odt

# Appendices

# 1 General Maps and Supporting Data


Vicinity Map
Portions of Flood Insurance Rate Map
NRCS Soil Map and Tables
SCS Soil Type Descriptions
Hydrologic Soil Group Map and Tables

# 2 Hydrologic Calculations

Runoff Coefficients and Percent Imperviousness Table 6-6
Colorado Springs Rainfall Intensity Duration Frequency Table 6-5
Hydrologic Calculations Summary Form SF-1 for Existing & Developed Conditions
Hydrologic Calculations Summary 5-yr Form SF-2 for Existing & Developed Conditions
Hydrologic Calculations Summary 100-yr Form SF-2 for Existing & Developed Conditions

# 3 Report Maps

Existing Drainage Map (Map Pocket) Proposed Drainage Map (Map Pocket)



# National Flood Hazard Layer FIRMette



# Legend SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT Without Base Flood Elevation (BFE) With BFE or Depth Zone AE, AO, AH, VE, AR SPECIAL FLOOD HAZARD AREAS Regulatory Floodway 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X **Future Conditions 1% Annual** Chance Flood Hazard Zone X Area with Reduced Flood Risk due to Levee. See Notes. Zone X OTHER AREAS OF Area with Flood Risk due to Levee Zone D FLOOD HAZARD NO SCREEN Area of Minimal Flood Hazard Zone X Effective LOMRs OTHER AREAS Area of Undetermined Flood Hazard Zone D - - - Channel, Culvert, or Storm Sewer **GENERAL** STRUCTURES | LILLIL Levee, Dike, or Floodwall 20.2 Cross Sections with 1% Annual Chance Water Surface Elevation **Coastal Transect** www 513 www Base Flood Elevation Line (BFE) Limit of Study Jurisdiction Boundary -- Coastal Transect Baseline OTHER **Profile Baseline FEATURES** Hydrographic Feature Digital Data Available No Digital Data Available MAP PANELS Unmapped

an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below.


The basemap shown complies with FEMA's basemap

The pin displayed on the map is an approximate point selected by the user and does not represent

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 10/9/2024 at 4:58 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

accuracy standards

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.








Natural Resources Conservation Service A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

# Custom Soil Resource Report for El Paso County Area, Colorado

**168 Training Facility** 



# **Preface**

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2 053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# **Contents**

Preface	2
How Soil Surveys Are Made	
Soil Map	
Soil Map (168 Training Facility)	9
Legend	10
Map Unit Legend (168 Training Facility)	11
Map Unit Descriptions (168 Training Facility)	11
El Paso County Area, Colorado	13
11—Bresser sandy loam, cool, 0 to 3 percent slopes	13
97—Truckton sandy loam, 3 to 9 percent slopes	14
110—Yoder gravelly sandy loam, 8 to 25 percent slopes	15
References	17

# **How Soil Surveys Are Made**

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

# Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.


After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

# Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



### MAP LEGEND

### Area of Interest (AOI)

Area of Interest (AOI)

### Soils

Soil Map Unit Polygons

-

Soil Map Unit Lines



Soil Map Unit Points

### Special Point Features

Blowout

Borrow Pit

Clay Spot

Closed Depression

Š

Gravel Pit

Gravelly Spot

Landfill

٨.

Lava Flow

عله

Marsh or swamp

Mine or Quarry

Miscellaneous Water

Perennial Water

Rock Outcrop

+

Saline Spot

Sandy Spot

Severely Eroded Spot

Sinkhole

3> 5

Slide or Slip

Sodic Spot

# 8

Spoil Area



Stony Spot



Very Stony Spot



Wet Spot Other



Special Line Features

### Water Features

~

Streams and Canals

### Transportation

ransp

Rails

~

Interstate Highways

~

**US Routes** 

 $\sim$ 

Major Roads Local Roads

# Background

100

Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: El Paso County Area, Colorado Survey Area Data: Version 22, Sep 3, 2024

Soil map units are labeled (as space allows) for map scales 1:50.000 or larger.

Date(s) aerial images were photographed: Sep 11, 2018—Oct 20, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# Map Unit Legend (168 Training Facility)

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
11	Bresser sandy loam, cool, 0 to 3 percent slopes	0.6	0.3%
97	Truckton sandy loam, 3 to 9 percent slopes	35.2	18.7%
110	Yoder gravelly sandy loam, 8 to 25 percent slopes	151.8	80.9%
Totals for Area of Interest		187.6	100.0%

# Map Unit Descriptions (168 Training Facility)

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate

# Custom Soil Resource Report

pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

# El Paso County Area, Colorado

# 11—Bresser sandy loam, cool, 0 to 3 percent slopes

# **Map Unit Setting**

National map unit symbol: 2tlph Elevation: 5,850 to 6,880 feet

Mean annual precipitation: 15 to 19 inches Mean annual air temperature: 48 to 52 degrees F

Frost-free period: 100 to 130 days

Farmland classification: Prime farmland if irrigated and the product of I (soil

erodibility) x C (climate factor) does not exceed 60

# **Map Unit Composition**

Bresser, cool, and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Bresser, Cool**

# Setting

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Linear Across-slope shape: Convex

Parent material: Tertiary aged alluvium derived from arkose

# Typical profile

Ap - 0 to 5 inches: sandy loam

Bt1 - 5 to 8 inches: sandy loam

Bt2 - 8 to 27 inches: sandy clay loam

Bt3 - 27 to 36 inches: sandy loam

C - 36 to 80 inches: loamy coarse sand

# Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high

(0.60 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum content: 5 percent

Maximum salinity: Nonsaline to very slightly saline (0.1 to 2.0 mmhos/cm)

Available water supply, 0 to 60 inches: Low (about 5.4 inches)

# Interpretive groups

Land capability classification (irrigated): 3e Land capability classification (nonirrigated): 4c

Hydrologic Soil Group: B

Ecological site: R049XB210CO - Sandy Foothill

Hydric soil rating: No

# **Minor Components**

### **Truckton**

Percent of map unit: 10 percent

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Linear Across-slope shape: Linear

Ecological site: R049XB210CO - Sandy Foothill

Hydric soil rating: No

## Yoder

Percent of map unit: 5 percent Landform: Alluvial fans Down-slope shape: Linear Across-slope shape: Linear

Ecological site: R049XY214CO - Gravelly Foothill

Hydric soil rating: No

# 97—Truckton sandy loam, 3 to 9 percent slopes

# Map Unit Setting

National map unit symbol: 2x0j2 Elevation: 5,300 to 6,850 feet

Mean annual precipitation: 14 to 19 inches Mean annual air temperature: 48 to 52 degrees F

Frost-free period: 85 to 155 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Truckton and similar soils: 85 percent Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Truckton**

# **Setting**

Landform: Hillslopes, interfluves

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Linear Across-slope shape: Linear

Parent material: Re-worked alluvium derived from arkose

# Typical profile

A - 0 to 4 inches: sandy loam
Bt1 - 4 to 12 inches: sandy loam
Bt2 - 12 to 19 inches: sandy loam
C - 19 to 80 inches: sandy loam

# Custom Soil Resource Report

# **Properties and qualities**

Slope: 3 to 9 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum content: 1 percent Maximum salinity: Nonsaline (0.1 to 1.9 mmhos/cm)

Available water supply, 0 to 60 inches: Moderate (about 6.6 inches)

# Interpretive groups

Land capability classification (irrigated): 6e Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: A

Ecological site: R049XB210CO - Sandy Foothill

Hydric soil rating: No

# **Minor Components**

### Blakeland

Percent of map unit: 8 percent Landform: Hillslopes, interfluves

Landform position (two-dimensional): Shoulder, backslope, summit

Landform position (three-dimensional): Side slope, crest

Down-slope shape: Convex, linear Across-slope shape: Convex, linear

Ecological site: R049XB210CO - Sandy Foothill

Hydric soil rating: No

## Bresser

Percent of map unit: 7 percent Landform: Low hills, interfluves

Landform position (two-dimensional): Footslope, toeslope Landform position (three-dimensional): Base slope

Down-slope shape: Concave, linear

Across-slope shape: Concave, linear

Ecological site: R049XB210CO - Sandy Foothill

Hydric soil rating: No

# 110—Yoder gravelly sandy loam, 8 to 25 percent slopes

# Map Unit Setting

National map unit symbol: 367f Elevation: 6.200 to 6.900 feet

Mean annual precipitation: 14 to 16 inches
Mean annual air temperature: 46 to 50 degrees F

# Custom Soil Resource Report

Frost-free period: 125 to 145 days

Farmland classification: Not prime farmland

# **Map Unit Composition**

Yoder and similar soils: 95 percent *Minor components*: 5 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

# **Description of Yoder**

# Setting

Landform: Hills

Landform position (three-dimensional): Side slope

Down-slope shape: Linear Across-slope shape: Linear

Parent material: Noncalcareous alluvium derived from arkose

# **Typical profile**

A - 0 to 6 inches: gravelly sandy loam
Bt - 6 to 12 inches: gravelly sandy clay loam

2C - 12 to 60 inches: very gravelly loamy coarse sand

# Properties and qualities

Slope: 8 to 25 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00

in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water supply, 0 to 60 inches: Low (about 4.2 inches)

# Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: A

Ecological site: R049XY214CO - Gravelly Foothill

Hydric soil rating: No

# **Minor Components**

# Other soils

Percent of map unit: 4 percent

Hydric soil rating: No

# **Pleasant**

Percent of map unit: 1 percent Landform: Depressions

Hydric soil rating: Yes

# References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2 053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084

# Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE\_DOCUMENTS/nrcs142p2\_052290.pdf

Typically, the surface layer is dark grayish brown sandy loam about 10 inches thick. The subsoil is dark grayish brown and brown sandy loam about 26 inches thick. The substratum is light brownish gray gravelly sandy loam.

Included with this soil in mapping are small areas of Blakeland loamy sand, 1 to 9 percent slopes; Bresser sandy loam, 0 to 3 percent slopes; Truckton sandy loam, 0 to 3 percent slopes; Ellicott loamy coarse sand, 0 to 5 percent slopes; and Ustic Torrifluvents, loamy.

Permeability of this Blendon soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, and the hazards of erosion and soil blowing are moderate.

Most areas of this soil are used as rangeland, but some small areas are cultivated. Some homesite development has taken place on this soil.

Native vegetation is mainly cool- and warm-season grasses such as western wheatgrass, side-oats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of plant cover from the soil. Interseeding improves the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Proper location of livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings are generally suited to this soil. Soil blowing is the principal limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is well suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. In cropland areas, habitat favorable for ring-necked pheasant, mourning dove, and many nongame species can be developed by establishing areas for nesting and escape cover. For pheasant, the provision of undisturbed nesting cover is vital and should be included in plans for habitat development. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for homesites. The main limitation for the construction of local roads and streets is a moderate frost action potential. Roads can be designed to overcome this limitation. Capability subclass IIIe.

11—Bresser sandy loam, 0 to 3 percent slopes. This deep, well drained soil formed in arkosic alluvium and residuum on terraces and uplands. Elevation ranges from 6,000 to 6,800 feet. The average annual precipitation is about 15 inches, the average annual air temperature is about 47 degrees F, and the average frost-free period is about 135 days.

Typically, the surface layer is grayish brown sandy loam about 5 inches thick. The subsoil is brown sandy clay loam about 31 inches thick. The substratum is light yellowish brown loamy coarse sand to a depth of 60 inches.

Included with this soil in mapping are small areas of Truckton sandy loam, 0 to 3 percent slopes; Ascalon sandy loam, 1 to 3 percent slopes; Fort Collins loam, 0 to 3 percent slopes; and Yoder gravelly sandy loam, 1 to 8 percent slopes. Some areas of Ustic Torrifluvents, loamy, occur along narrow drainageways.

Permeability of this Bresser soil is moderate. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, the hazard of erosion is slight to moderate, and the hazard of soil blowing is moderate.

Most areas of this soil are cultivated. The remaining acreage is used as rangeland.

A rotation of winter wheat and fallow is used because precipitation is insufficient for annual cropping. A feedgrain crop such as millet or sorghum can be substituted for wheat in some years. Crop residue management and minimum tillage are needed to control erosion.

Native vegetation is mainly cool- and warm-season grasses such as western wheatgrass, side-oats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of plant cover from the soil. Interseeding improves the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Proper location of livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings are generally suited to this soil. Soil blowing is the principal limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is well suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. In cropland areas, habitat favorable for ring-necked pheasant, mourning dove, and many nongame species can be developed by establishing areas for nesting and escape cover. For pheasant, the provision of undisturbed nesting cover is vital and should be included in plans for habitat development. This is especially true in areas of intensive farming. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for homesites. Limiting the disturbance of the soil and the removal of existing plant cover during construction helps to control erosion. Capability subclass IIIc.

60 SOIL SURVEY

Almost all areas of this soil are used as rangeland. A few areas of crops such as alfalfa and corn are grown under sprinkler irrigation.

This soil is well suited to the production of native vegetation suitable for grazing. It is best suited to deeprooted grasses. The native vegetation is mainly cool- and warm-season grasses such as western wheatgrass, sideoats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of the plant cover. Interseeding is used to improve the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Properly locating livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings are fairly well suited to this soil. Blowing sand is the main limitation for the establishment of trees and shrubs. The soil is so loose that trees need to be planted in shallow furrows and plant cover needs to be maintained between the rows. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to openland and rangeland wildlife habitat. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for use as homesites. The main limitation of this soil for roads and streets is frost action potential. Special designs for roads are needed to minimize this limitation. Practices are needed to control soil blowing and water erosion on construction sites where the plant cover has been removed. Capability subclass VIe, nonirrigated.

96—Truckton sandy loam, 0 to 3 percent slopes. This deep, well drained soil formed in alluvium and residuum derived from arkosic sedimentary rock on uplands. Elevation ranges from 6,000 to 7,000 feet. The average annual precipitation is about 15 inches, the average annual air temperatue is about 47 degrees F, and the average frost-free period is about 135 days.

Typically, the surface layer is grayish brown sandy loam about 5 inches thick. The next layer is dark grayish brown sandy loam about 3 inches thick. The subsoil is brown sandy loam about 16 inches thick. The substratum is light yellowish brown coarse sandy loam to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Blakeland loamy sand, 1 to 9 percent slopes; Bresser sandy loam, 0 to 3 percent slopes; Ellicott loamy coarse sand, 0 to 5 percent slopes; and Ustic Torrifluvents, loamy.

Permeability of this Truckton soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow, and the hazards of erosion and soil blowing are moderate.

This soil is used mainly for cultivated crops. It is also used for livestock grazing, for wildlife habitat, and as homesites.

Crops are commonly grown in combination with summer fallow because moisture is insufficient for annual cropping. Alfalfa can also be grown on this soil. When this soil is used as cropland, crop residue management and minimum tillage are necessary conservation practices.

This soil is well suited to the production of native vegetation suitable for grazing (fig. 7). It favors deeprooted grasses. The native vegetation is mainly cool- and warm-season grasses such as western wheatgrass, sideoats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of the plant cover. Interseeding is used to improve the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Properly locating livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings generally are suited to this soil. Soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. In cropland areas, habitat favorable for ring-necked pheasant, mourning dove, and many nongame species can be developed by establishing areas for nesting and escape cover. For pheasant, undisturbed nesting cover is vital and should be provided in plans for habitat development. This is especially true in areas of intensive farming. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

This soil has good potential for use as homesites. The main limitation of this soil for roads and streets is frost-action potential. Special designs for roads are needed to overcome this limitation. Capability subclasses IIIe, nonirrigated, and IIe, irrigated.

97—Truckton sandy loam, 3 to 9 percent slopes. This deep, well drained soil formed in alluvium and residuum derived from arkosic sedimentary rock on uplands. Elevation ranges from 6,000 to 7,000 feet. The average annual precipitation is about 15 inches, the average annual air temperature is about 47 degrees F, and the average frost-free period is about 135 days.

Typically, the surface layer is grayish brown sandy loam about 5 inches thick. The next layer is dark grayish brown sandy loam about 3 inches thick. The subsoil is brown sandy loam about 16 inches thick. The substratum is light yellowish brown coarse sandy loam to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Blakeland loamy sand, 1 to 9 percent slopes; Bresser sandy loam, 3 to 5 percent slopes; and Truckton sandy loam, 0 to 3 percent slopes. Also included are small areas of soils that have arkosic sandstone or shale at a depth of less than 40 inches.

Permeability of this Truckton soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is slow to medium, and the hazards of erosion and soil blowing are moderate.

More than half of this soil is used as rangeland, for wildlife habitat, and as homesites. The rest, consisting of the less sloping areas, is used for wheat and sorghum. Rangeland or pastureland is the most suitable use because the permanent plant cover protects the soil.

This soil is well suited to the production of native vegetation suitable for grazing. Native vegetation is mainly cool- and warm-season grasses such as western wheatgrass, side-oats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of the plant cover from this soil. Interseeding improves the existing vegetation. Deferment of grazing in spring increases plant vigor and soil stability. Properly locating livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings generally are well suited to this soil. Soil blowing is the main limitation to the establishment of trees and shrubs. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Supplemental irrigation may be needed when planting and during dry periods. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. In cropland areas, habitat favorable for ring-necked pheasant, mourning dove, and many nongame species can be developed by establishing areas for nesting and escape cover. For pheasant, undisturbed nesting cover is vital and should be provided for in plans for habitat development. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitation of this soil for construction is frostaction potential. Special designs for roads are needed to overcome this limitation. Because of the sandy nature of the soil, practices must be provided to minimize surface runoff and thus keep erosion to a minimum. Access roads must have adequate cut-slope grade and be provided with drains to control surface runoff. Capability subclasses VIe, nonirrigated, and IVe, irrigated.

98—Truckton-Blakeland complex, 9 to 20 percent slopes. These strongly sloping to moderately steep soils

are on uplands. Elevation ranges from 6,000 to 7,000 feet. The average annual precipitation is about 15 inches, the average annual air temperature is about 47 degrees F, and the average frost-free period is about 135 days.

The Truckton soil makes up about 60 percent of the complex, the Blakeland soil about 25 percent, and other soils about 15 percent.

Included with these soils in mapping are areas of Bresser sandy loam, 5 to 9 percent slopes, and Yoder gravelly sandy loam, 8 to 25 percent slopes.

The Truckton soil is deep and well drained. It formed in alluvium and residuum weathered from arkosic sedimentary rock. Typically, the surface layer is grayish brown sandy loam about 5 inches thick. The next layer is dark grayish brown sandy loam about 3 inches thick. The subsoil is brown sandy loam about 16 inches thick. The substratum is light yellowish brown coarse sandy loam to a depth of 60 inches or more.

Permeability of the Truckton soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is moderate. Surface runoff is medium to rapid, and the hazard of erosion is moderate to high. Soil slippage is common on the upper part of slopes.

The Blakeland soil is deep and somewhat excessively drained. It formed in arkosic sandy alluvium and eolian sediment derived from arkosic sedimentary rock. Typically, the surface layer is dark grayish brown loamy sand about 11 inches thick. The underlying material is brown loamy sand about 16 inches thick; it grades to pale brown sand that extends to a depth of 60 inches or more.

Permeability of the Blakeland soil is rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Surface runoff is medium, and the hazard of erosion is moderate to high, and the hazard of soil blowing is high. Soil slippage is common on the upper part of slopes.

The soils in this complex are used for grazing livestock and wildlife habitat.

These soils are suited to the production of native vegetation suitable for grazing. The native vegetation is dominantly western wheatgrass, side-oats grama, and needleandthread.

Proper range management is needed to prevent excessive removal of the plant cover from these soils. Interseeding improves the existing vegetation. Deferment of grazing in spring improves plant vigor and soil stability. Properly locating livestock watering facilities helps to control grazing.

Soil blowing is the main limitation for the establishment of trees and shrubs on these soils. This limitation can be overcome by cultivating only in the tree rows and leaving a strip of vegetation between the rows. Trees need to be planted in shallow furrows on the Blakeland soil because of its loose, sandy surface layer. Supplemental irrigation may be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, Siberian elm, Russian-olive, and hackberry. Shrubs that are best suited are skunkbush sumac, lilac, and Siberian peashrub.

68 SOIL SURVEY

suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac and lilac.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly managing livestock grazing, and reseeding range where needed.

The main limitation of this soil for excavations is the high gravel content, which causes cut banks to cave in. Excavations for underground utilities need to be designed to overcome this limitation. Capability subclass VIe.

110—Yoder gravelly sandy loam, 8 to 25 percent slopes. This deep, well drained, gravelly soil formed in noncalcareous alluvium derived from arkosic deposits on uplands. Elevation ranges from 6,200 to 6,900 feet. The average annual precipitation is about 15 inches, the average annual air temperature is about 47 degrees F, and the average frost-free period is about 135 days.

Typically, the surface layer is grayish brown gravelly sandy loam about 6 inches thick. The subsoil is brown gravelly sandy clay loam about 6 inches thick. The substratum is very gravelly loamy coarse sand to a depth of 60 inches or more.

Included with this soil in mapping are small areas of Louviers silty clay loam, 3 to 18 percent slopes, and Truckton-Bresser complex, 5 to 20 percent slopes.

Permeability of this Yoder soil is moderately rapid. Effective rooting depth is 60 inches or more. Available water capacity is low to moderate. Surface runoff is medium to rapid, and the hazard of erosion is moderate. Some gullies have developed along drainageways, and there is some soil slippage on the steeper slopes.

This soil is used as rangeland and for wildlife habitat.

The native vegetation is mainly western wheatgrass, side-oats grama, needleandthread, and little bluestem. The most prominent shrub on this soil is true mountain-mahogany.

Vegetation is very difficult to reestablish on this soil if the native vegetation is destroyed. Properly locating livestock watering facilities helps to control grazing.

Windbreaks and environmental plantings are suited to this soil. Low available water capacity is the main limitation for the establishment of tree and shrub plantings. Summer fallow a year in advance and continued cultivation for weed control are needed to insure the establishment and survival of plantings. Supplemental irrigation may also be needed to insure survival. Trees that are best suited and have good survival are Rocky Mountain juniper, eastern redcedar, ponderosa pine, and Siberian elm. Shrubs that are best suited are skunkbush sumac and lilac.

This soil is suited to wildlife habitat. It is best suited to habitat for openland and rangeland wildlife. Rangeland wildlife, such as pronghorn antelope, can be encouraged by developing livestock watering facilities, properly

managing livestock grazing, and reseeding range where needed.

The main limitation of this soil for homesites is slope. The high gravel content can cause some excavation problems, such as unstable cut banks. Special designs for buildings and roads are required to overcome this limitation. Access roads must have adequate cut-slope grade and be provided with drains to control surface runoff and keep soil losses to a minimum. Capability subclass VIe.

## Use and management of the soils

The soil survey is a detailed inventory and evaluation of the most basic resource of the survey area—the soil. It is useful in adjusting land use, including urbanization, to the limitations and potentials of natural resources and the environment. Also, it can help avoid soil-related failures in uses of the land.

While a soil survey is in progress, soil scientists, conservationists, engineers, and others keep extensive notes about the nature of the soils and about unique aspects of behavior of the soils. These notes include data on erosion, drought damage to specific crops, yield estimates, flooding, the functioning of septic tank disposal systems, and other factors affecting the productivity, potential, and limitations of the soils under various uses and management. In this way, field experience and measured data on soil properties and performance are used as a basis for predicting soil behavior.

Information in this section is useful in planning use and management of soils for crops and pasture, rangeland, and woodland; as sites for buildings, highways and other transportation systems, sanitary facilities, and parks and other recreation facilities; and for wildlife habitat. From the data presented, the potential of each soil for specified land uses can be determined, soil limitations to these land uses can be identified, and costly failures in houses and other structures, caused by unfavorable soil properties, can be avoided. A site where soil properties are favorable can be selected, or practices that will overcome the soil limitations can be planned.

Planners and others using the soil survey can evaluate the impact of specific land uses on the overall productivity of the survey area or other broad planning area and on the environment. Productivity and the environment are closely related to the nature of the soil. Plans should maintain or create a land-use pattern in harmony with the natural soil.

Contractors can find information that is useful in locating sources of sand and gravel, roadfill, and topsoil. Other information indicates the presence of bedrock, wetness, or very firm soil horizons that cause difficulty in excavation.

Health officials, highway officials, engineers, and many other specialists also can find useful information in this soil survey. The safe disposal of wastes, for example, is closely related to properties of the soil. Pavements, sidewalks, campsites, playgrounds, lawns, and trees and shrubs are influenced by the nature of the soil.




Table 6-6. Runoff Coefficients for Rational Method (Source: UDFCD 2001)

Cooper Sac col I but I	4						Runoff Co	Runoff Coefficients					
Characteristics	Impervious	2-y	2-year	5-year	ear	10-year	ear	25-1	25-year	50-1	50-year	100-	100-year
		HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D	HSG A&B	HSG C&D
Business													
Commercial Areas	95	0.79	0.80	0.81	0.82	0.83	0.84	0.85	0.87	0.87	0.88	0.88	0,89
Neighborhood Areas	70	0.45	0.49	0.49	0.53	0.53	0.57	0.58	0.62	09.0	0.65	0.62	0.68
Docidontin													
1/8 Arra or loce	T.	177	270	27.0	07.0	0,0	200	25.0	0	[	5	61.0	100
1/4 Acre	40	0.23	0.78	0.30	0.35	0.45	0.042	0.24	5.0	0.07	7970	0.59	0,65
1/3 Acre	30	0.18	0.22	0.25	0.30	0.32	0.38	0.39	0.47	0.43	0.52	0.20	0.30
1/2 Acre	25	0.15	0.20	0.22	0.28	0.30	0.36	0.37	0.46	0.41	0.51	0.46	0.56
1 Acre	20	0.12	0.17	0.20	0.26	0.27	0.34	0.35	0.44	0.40	0.50	0.44	0.55
Industrial													
Light Areas	80	0.57	09:0	0.59	0.63	0.63	0.66	99'0	0.70	0.68	0.72	0.70	0.74
Heavy Areas	90	0.71	0.73	`0.73	0.75	0.75	0.77	0.78	08.0	0.80	0.82	0.81	0.83
Parks and Cemeteries	7	0.05	60'0	0.12	0.19	0.20	0.29	0:30	0.40	0.34	0.46	0.39	0.52
Playgrounds	13	0.07	0.13	0.16	0.23	0.24	0.31	0.32	0.42	0.37	0.48	0.41	0.54
Railroad Yard Areas	40	0.23	0.28	0.30	0.35	0.36	0.42	0.42	0.50	0,46	0.54	0.50	0.58
Undeveloped Areas							4						
Historic Flow Analysis Greenbelts, Agriculture	2	0.03	0.05	0.09	0.16	0.17	0.26	0.26	0.38	0.31	0.45	0.36	0.51
Pasture/Meadow	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0:30	0.44	0.35	0.50
Forest	0	0.02	0.04	0.08	0.15	0.15	0.25	0.25	0.37	0:30	0.44	0.35	0.50
Exposed Rock	100	0.89	0.89	0.90	06.0	0.92	0.92	0.94	0.94	0.95	0.95	96.0	0.96
Offsite Flow Analysis (when landuse is undefined)	45	0.26	0.31	0.32	0.37	0.38	0.44	0.44	0.51	0.48	0.55	0.51	0.59
Streets													
Paved	100	0.89	0.89	0.90	0.30	0.92	0.92	0.94	0.94	0.95	0.95	96'0	96'0
Gravel	80	0.57	09'0	0.59	0.63	0.63	99'0	99.0	0.70	99.0	0.72	0.70	0.74
Drive and Walks	100	0.89	0.89	0.90	0.90	0.92	0.92	0.94	0.94	0.95	0.95	96.0	0.96
Roofs	90	0.71	0.73	0.73	0.75	0.75	0.77	0.78	0.80	0.80	0.82	0.81	0.83
Lawns	0	0.02	9.0	0.08	0,15	0.15	0.25	0.25	0.37	0.30	0.44	0.35	0.50




Figure 6-5. Colorado Springs Rainfall Intensity Duration Frequency

# **IDF** Equations

$$I_{100} = -2.52 \ln(D) + 12.735$$

$$I_{50} = -2.25 \ln(D) + 11.375$$

$$I_{25} = -2.00 \ln(D) + 10.111$$

$$I_{10} = -1.75 \ln(D) + 8.847$$

$$I_5 = -1.50 \ln(D) + 7.583$$

$$I_2 = -1.19 \ln(D) + 6.035$$

Note: Values calculated by equations may not precisely duplicate values read from figure.

### **Sub-Basin EX-A Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: Jurisdiction **DCM** Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runc	off Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	825178	18.94	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	825,178	18.94	0.02	0.08	0.15	0.25	0.30	0.35	0.0%

825178

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Pastu	ıre/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	1,372	50	-	-	-	-	
Initial Time	300	15	0.050	-	18.8	N/A DCM Eq	. 6-8
Shallow Channel	567	21	0.037	1.3	7.0	- DCM Eq	. 6-9
Channelized	505	14	0.028	2.2	3.8	- V-Ditch	
				t <sub>c</sub>	29.6 n	nin.	

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00	(in)	a =	1		Water Quality i	s NOT requir	red
WQCV	0.00	(in)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
K <sub>i</sub> (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.18943	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-8,252	WQCV	0%	U	0	0

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.00	2.50	2.92	3.33	3.75	4.20
Runoff (cfs)	0.8	3.8	8.3	15.8	21.3	27.8
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	0.8	3.8	8.3	15.8	21.3	27.8
DCM:	I = C1 * In	(tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin EX-B Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	2442664.9	56.08	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	2,442,665	56.08	0.02	0.08	0.15	0.25	0.30	0.35	0.0%
	2442664.9								

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{\text{max,Overland}}$	300	ft		$C_{v}$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	1,896	103	-	-	-	-	
Initial Time	300	19	0.063	-	17.3	N/A DCM Eq.	6-8
Shallow Channel	1,596	84	0.053	1.6	16.6	- DCM Eq.	6-9
Channelized			0.000	0.0	0.0	- V-Ditch	
				t <sub>c</sub>	33.9 r	nin.	

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00 (in)	)	a =	1		Water Quality is	s NOT require	ed
WQCV	0.00 (in)	)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
$K_{i}$ (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.56076	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-24,427	WQCV	0%	0	0	0

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.84	2.30	2.68	3.06	3.45	3.86
Runoff (cfs)	2.1	10.3	22.5	42.9	58.0	75.7
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	2.1	10.3	22.5	42.9	58.0	75.7
DCM:	I = C1 * In	(tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin EX-C Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: Jurisdiction **DCM** Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	2437292.29	55.95	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	<b>2,437,292</b> 2437292.29	55.95	0.02	0.08	0.15	0.25	0.30	0.35	0.0%

### **Basin Travel Time**

-							
Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	1,425	62	-	-	-	-	
Initial Time	300	18	0.060	-	17.7	N/A DCM Eq.	6-8
Shallow Channel	1,125	44	0.039	1.4	13.5	- DCM Eq.	6-9
Channelized			0.000	0.0	0.0	- V-Ditch	
				t <sub>c</sub>	31.2	min.	

C2

6.035

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00	(in)	a =	1		Water Quality is	s NOT required	i
WQCV	0.00	(in)						
i (return period)	5-year	10-year	100-year			Desig	n Volume (1	it <sup>3</sup> )
K <sub>i</sub> (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.55953	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-24,373	WQCV	0%	U	0	0

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.94	2.42	2.83	3.23	3.63	4.06
Runoff (cfs)	2.2	10.8	23.7	45.2	61.0	79.6
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	2.2	10.8	23.7	45.2	61.0	79.6
DCM: I =	C1 * In (t	c) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52

7.583

8.847

10.111 11.375 12.735

### **Sub-Basin EX-D Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	1197023.3	27.48	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	1,197,023	27.48	0.02	0.08	0.15	0.25	0.30	0.35	0.0%
	1197023.3							·	

### **Basin Travel Time**

Sha	allow Channel Gro	und Cover	Short Pastu	ure/Lawns		
	$L_{max,Overland}$	300	ft		$C_v$	7
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	1,668	61	-	-	-	-
Initial Time	300	15	0.050	-	18.8	N/A DCM Eq. 6-8
Shallow Channel	1,101	39	0.035	1.3	13.9	- DCM Eq. 6-9
Channelized	267	7	0.026	2.7	1.7	- V-Ditch
				t <sub>c</sub>	34.4 ı	min.

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00 (in)		a =	1		Water Quality is	s NOT require	ed
WQCV	0.00 (in)							
i (return period)	5-year 1	10-year	100-year			Desig	n Volume	(ft³)
$K_{i}$ (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.2748	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-11,970	WQCV	0%	0	0	0

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.83	2.28	2.66	3.04	3.42	3.82
Runoff (cfs)	1.0	5.0	11.0	20.9	28.2	36.8
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	1.0	5.0	11.0	20.9	28.2	36.8
DCM:	I = C1 * In (to	c) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin OS-1 Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	1071306.993	24.59	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	1,071,307	24.59	0.02	0.08	0.15	0.25	0.30	0.35	0.0%
	1071306.993								

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{\text{max,Overland}}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	1,754	32	-	-	-	-	
Initial Time	300	3	0.010	-	31.9	N/A DCM	Eq. 6-8
Shallow Channel	990	15	0.015	0.9	19.1	- DCM	Eq. 6-9
Channelized	464	14	0.030	2.0	3.8	- Trap	Ditch
				t <sub>c</sub>	54.8	min.	

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00	(in)	a =	1		Water quality Is	S required	
WQCV	0.00	(in)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
K <sub>i</sub> (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.24594	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-10,713	WQCV	0%	U	0	0

### Rainfall Intensity & Runoff

	0.77-	F V-	40 1/-	0F V-	FA 17-	400 17
	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.27	1.58	1.84	2.10	2.36	2.64
Runoff (cfs)	0.6	3.1	6.8	12.9	17.4	22.8
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	0.6	3.1	6.8	12.9	17.4	22.8
DCM:	I = C1 * In (	(tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin OS-2 Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	4938509.735	113.37	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	4,938,510	113.37	0.02	0.08	0.15	0.25	0.30	0.35	0.0%
	4938509.735								

### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	4,142	117	-	-	-	-	
Initial Time	300	5	0.017	-	26.9	N/A DCM Eq.	6-8
Shallow Channel	3,635	100	0.028	1.2	52.2	- DCM Eq.	6-9
Channelized	207	12	0.058	3.7	0.9	- V-Ditch	
				t <sub>c</sub>	80.1	min.	

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00 (in)		a =	1		Water Quality is	s NOT require	ed
WQCV	0.00 (in)							
i (return period)	5-year 10	)-year	100-year			Desig	n Volume	(ft³)
$K_{i}$ (ft)	0.0000 0.	.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-1.13373	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-49,385	WQCV	0%	0	0	0

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	0.82	1.01	1.18	1.35	1.51	1.69
Runoff (cfs)	1.9	9.2	20.0	38.1	51.5	67.1
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	1.9	9.2	20.0	38.1	51.5	67.1
DCM:	I = C1 * In (t	c) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin OS-3 Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: 168 Training Facility Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	1762811.871	40.47	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	1,762,812	40.47	0.02	0.08	0.15	0.25	0.30	0.35	0.0%

#### 1762811.871

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	2,384	125	-	-	-	-	
Initial Time	300	20	0.067	-	17.1	N/A DO	CM Eq. 6-8
Shallow Channel	1,928	95	0.049	1.6	20.7	- DO	CM Eq. 6-9
Channelized	156	10	0.064	4.1	0.6	- V-	Ditch
				t <sub>c</sub>	38.4	min.	

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00	(in)	a =	1		Water Quality i	s NOT requir	red
WQCV	0.00	(in)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
K <sub>i</sub> (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.40469	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-17,628	WQCV	0%	U	0	0

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.69	2.11	2.46	2.82	3.17	3.54
Runoff (cfs)	1.4	6.8	15.0	28.5	38.5	50.2
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	1.4	6.8	15.0	28.5	38.5	50.2
DCM:	I = C1 * In (	tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin OS-4 Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: 168 Training Facility Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area	1		Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Pasture/Meadow	6331228.27	145.35	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	6,331,228	145.35	0.02	0.08	0.15	0.25	0.30	0.35	0.0%
	6331228.272								

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	5,348	175	-	-	-	-	
Initial Time	300	5	0.017	-	26.9	N/A	DCM Eq. 6-8
Shallow Channel	5,048	170	0.034	1.3	65.5	-	DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- '	V-Ditch
				t.	92.4	min.	

## **Storage Volume**

		40	-hr release time		Detention is NO	OT required	
EURV	0.00 (in)	a =	1		Water Quality i	s NOT require	ed
WQCV	0.00 (in)						
i (return period)	5-year 10-ye	ar 100-year	•		Desig	n Volume	(ft <sup>3</sup> )
$K_{i}$ (ft)	0.000 0.00	00 0	)	% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000 0.0	00 -1.45345	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0 -63,312	WQCV	0%	0	0	0

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	0.65	0.79	0.93	1.06	1.19	1.33
Runoff (cfs)	1.9	9.2	20.2	38.4	51.9	67.6
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	1.9	9.2	20.2	38.4	51.9	67.6
DCM:	I = C1 * In (	tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735

### **Sub-Basin PR-A Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: **168 Training Facility** Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Gravel	20606.9527	0.47	0.57	0.59	0.63	0.66	0.68	0.7	80%
Pasture/Meadow	804,571	18.47	0.02	80.0	0.15	0.25	0.3	0.35	0%
Combined	825,178	18.94	0.03	0.09	0.16	0.26	0.31	0.36	2.0%

825178

#### **Basin Travel Time**

-							
Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_{v}$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	1,372	50	-	-	-	-	
Initial Time	300	15	0.050	-	18.5	N/A DCM Eq. 6-8	3
Shallow Channel	567	21	0.037	1.3	7.0	- DCM Eq. 6-9	9
Channelized	505	14	0.028	2.2	3.8	- V-Ditch	
				t <sub>c</sub>	29.3	min.	

C2

6.035

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00 (ii	n)	a =	1		Water Quality is	s NOT requir	red
WQCV	0.00 (ii	n)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
$K_{i}$ (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.0947	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-4,125	WQCV	0%	0	0	0

### Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	2.01	2.51	2.93	3.35	3.77	4.22
Runoff (cfs)	1.3	4.4	9.0	16.5	22.1	28.7
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	1.3	4.4	9.0	16.5	22.1	28.7
DCM: I	= C1 * In (	(tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52

7.583

8.847

10.111 11.375 12.735

### **Sub-Basin PR-B Runoff Calculations**

Job No.: Date: 10/31/2024 14:03

Project: 168 Training Facility Calcs by: SLB

Checked by:

Jurisdiction DCM Soil Type

Runoff Coefficient Surface Type Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area	Area			Runoff Coefficient						
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.		
Roofs	9480	0.22	0.71	0.73	0.75	0.78	0.8	0.81	90%		
Lawns	312,051	7.16	0.02	0.08	0.15	0.25	0.30	0.35	0%		
Gravel	140,871	3.23	0.57	0.59	0.63	0.66	0.68	0.7	80%		
Landscaping	23,759	0.55	0.03	0.09	0.17	0.26	0.31	0.36	2%		
Pasture/Meadow	1,956,504	44.92	0.02	0.08	0.15	0.25	0.3	0.35	0%		
Combined	2,442,665	56.08	0.05	0.11	0.18	0.28	0.32	0.37	5.0%		

2442664.9

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	2,198	99	-	-	-	-	
Initial Time	300	9	0.030	-	21.5	N/A	DCM Eq. 6-8
Shallow Channel	1,898	90	0.047	1.5	20.8	-	DCM Eq. 6-9
Channelized			0.000	0.0	0.0	-	V-Ditch

t<sub>c</sub> 42.3 min.

## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00 (in)		a =	1		Water Quality is	s NOT requir	red
WQCV	0.00 (in)							
i (return period)	5-year 10	0-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
$K_{i}$ (ft)	0.0000	0.000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	0.134792	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	5,872	WQCV	0%	0	0	0

### Rainfall Intensity & Runoff

1						
	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.58	1.97	2.30	2.62	2.95	3.30
Runoff (cfs)	4.8	12.4	23.2	40.6	53.6	68.9
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	4.8	12.4	23.2	40.6	53.6	68.9
DCM:	I = C1 * In (	(tc) + C2				
C1	1 10	1 5	1 75	2	2.25	2 52

C1 1.19 1.5 1.75 2 2.25 2.52 C2 6.035 7.583 8.847 10.111 11.375 12.735

### **Sub-Basin PR-C Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project:

Checked by:

**168 Training Facility** Calcs by: SLB

DCM Jurisdiction Soil Type

Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area			Runo	ff Coeffici	ent			%
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.
Roofs	5056	0.12	0.71	0.73	0.75	0.78	0.8	0.81	90%
Gravel	91,171	2.09	0.57	0.59	0.63	0.66	0.68	0.7	80%
Lawns	389,323	8.94	0.02	0.08	0.15	0.25	0.30	0.35	0%
Landscaping	29,441	0.68	0.03	0.09	0.17	0.26	0.31	0.36	2%
Pasture/Meadow	1,922,301	44.13	0.02	0.08	0.15	0.25	0.3	0.35	0%
Combined	2,437,293	55.95	0.04	0.10	0.17	0.27	0.32	0.36	3.2%

2437292.29

#### **Basin Travel Time**

Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns		
	$L_{max,Overland}$	300	ft		$C_v$	7
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)
Total	1,721	62	-	-	-	-
Initial Time	300	12	0.040	-	19.8	N/A DCM Eq. 6-8
Shallow Channel	1,421	50	0.035	1.3	18.0	- DCM Eq. 6-9
Channelized			0.000	0.0	0.0	- V-Ditch
				t.	37.8	min.

# **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00	(in)	a =	1		Water Quality is	s NOT requir	ed
WQCV	0.00	(in)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
$K_{i}$ (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.11185	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-4,872	WQCV	0%	0	0	0

## Rainfall Intensity & Runoff

	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr			
Intensity (in/hr)		2.13	2.49			3.58			
Runoff (cfs)		12.0	23.6		56.5	73.0			
Release Rates (cfs/ac)		_		_	_				
Allowed Release (cfs)		12.0	23.6	42.4	56.5	73.0			
DCM: I = C1 * In (tc) + C2									

C1 2.52 1.5 2 2.25 1.19 1.75 C2 6.035 7.583 8.847 10.111 11.375

### **Sub-Basin PR-D Runoff Calculations**

Job No.: 61224 Date: 10/31/2024 14:03 Project: 168 Training Facility Calcs by: SLB Checked by: DCM Jurisdiction Soil Type Runoff Coefficient **Surface Type** Urbanization Non-Urban

### **Basin Land Use Characteristics**

	Area				Runoff Coefficient					
Surface	(SF)	(Acres)	C2	C5	C10	C25	C50	C100	Imperv.	
Pasture/Meadow	1197023.3	27.48	0.02	0.08	0.15	0.25	0.3	0.35	0%	
	1 107 000	0= 10							2.20/	
Combined	1,197,023	27.48	0.02	0.08	0.15	0.25	0.30	0.35	0.0%	
	1197023.3									

#### **Basin Travel Time**


Sha	allow Channel Gro	ound Cover	Short Past	ure/Lawns			
	$L_{max,Overland}$	300	ft		$C_v$	7	
	L (ft)	$\Delta Z_0$ (ft)	S <sub>0</sub> (ft/ft)	v (ft/s)	t (min)	t <sub>Alt</sub> (min)	
Total	1,668	61	-	-	-	-	
Initial Time	300	15	0.050	-	18.8	N/A D	CM Eq. 6-8
Shallow Channel	1,101	39	0.035	1.3	13.9	- D	CM Eq. 6-9
Channelized	267	7	0.026	2.7	1.7	- V	'-Ditch
				t <sub>c</sub>	34.4	min.	


## **Storage Volume**

			40	-hr release time		Detention is NO	OT required	
EURV	0.00 (i	in)	a =	1		Water Quality i	s NOT requir	red
WQCV	0.00 (i	in)						
i (return period)	5-year	10-year	100-year			Desig	n Volume	(ft <sup>3</sup> )
$K_{i}$ (ft)	0.0000	0.0000	0		% Storage	100-year	WQCV	Total
V <sub>i</sub> (acre-ft)	0.000	0.000	-0.2748	EURV	0%	0	0	0
$V_i$ (ft <sup>3</sup> )	0	0	-11,970	WQCV	0%	0	0	0

## Rainfall Intensity & Runoff


	2-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr
Intensity (in/hr)	1.83	2.28	2.66	3.04	3.42	3.82
Runoff (cfs)	1.0	5.0	11.0	20.9	28.2	36.8
Release Rates (cfs/ac)	-	-	-	-	-	-
Allowed Release (cfs)	1.0	5.0	11.0	20.9	28.2	36.8
DCM:	I = C1 * In (	tc) + C2				
C1	1.19	1.5	1.75	2	2.25	2.52
C2	6.035	7.583	8.847	10.111	11.375	12.735







50 0 100 300 600 1" = 300' 1:3,600



DESIGNED BY
DRAWN BY
CHECKED BY
AS-BUILTS BY

+158 Acre Parcel
168 Training Facility

DRAINAGE REPORT

EX. DRAINAGE MAP

MVE PROJECT 61224

MVE DRAWING EXDRAIN MAP

**OCT. 30, 2024 SHEET** 1 **OF** 2

