

# Parcel Map Check Report

**Client:****Prepared by:**

Thomas Wendland  
MVE, Inc.  
1903 Lelaray St

Date: 3/21/2022 9:48:58 AM

---

Parcel Name: Site 1 - Standard : 1

**Description:**

Process segment order counterclockwise: False

Enable mapcheck across chord: False

North: 1,462,316.3470' East: 3,226,488.7840'

**Segment# 1: Line**

Course: N0° 07' 55"W Length: 1,326.90'

North: 1,463,643.2435' East: 3,226,485.7283'

**Segment# 2: Line**

Course: N89° 36' 06"E Length: 1,183.90'

North: 1,463,651.4742' East: 3,227,669.5997'

**Segment# 3: Line**

Course: S0° 21' 20"W Length: 1,326.19'

North: 1,462,325.3097' East: 3,227,661.3699'

**Segment# 4: Line**

Course: S89° 33' 44"W Length: 1,172.62'

North: 1,462,316.3502' East: 3,226,488.7842'

Perimeter: 5,009.61'

Area: 1,562,935.76Sq.Ft.

Error Closure: 0.0032

Course: N3° 10' 37"E

Error North : 0.00319

East: 0.00018

Precision 1: 1,565,503.13