


PROJECT INFORMATION			
Space Village Filing No. 4	4/17/2023	MS227	
Project Name	Date	PCD File No.	

Description	Quantity	Units	Unit Cost	=	\$	Total	(with Pre-Plat Construction)		
							% Complete	Remaining	
[insert items not listed but part of construction plans]				=	\$	-		\$ -	
[insert items not listed but part of construction plans]				=	\$	-		\$ -	
STORM DRAIN IMPROVEMENTS									
Concrete Box Culvert (M Standard), Size (W x H)		LF		=	\$	-		\$ -	
18" Reinforced Concrete Pipe		LF	\$ 70.00	=	\$	-		\$ -	
24" Reinforced Concrete Pipe		LF	\$ 83.00	=	\$	-		\$ -	
30" Reinforced Concrete Pipe		LF	\$ 104.00	=	\$	-		\$ -	
36" Reinforced Concrete Pipe		LF	\$ 128.00	=	\$	-		\$ -	
42" Reinforced Concrete Pipe		LF	\$ 171.00	=	\$	-		\$ -	
48" Reinforced Concrete Pipe		LF	\$ 209.00	=	\$	-		\$ -	
54" Reinforced Concrete Pipe		LF	\$ 272.00	=	\$	-		\$ -	
60" Reinforced Concrete Pipe		LF	\$ 319.00	=	\$	-		\$ -	
66" Reinforced Concrete Pipe		LF	\$ 368.00	=	\$	-		\$ -	
72" Reinforced Concrete Pipe		LF	\$ 421.00	=	\$	-		\$ -	
18" Corrugated Steel Pipe		LF	\$ 90.00	=	\$	-		\$ -	
24" Corrugated Steel Pipe		LF	\$ 103.00	=	\$	-		\$ -	
30" Corrugated Steel Pipe		LF	\$ 131.00	=	\$	-		\$ -	
36" Corrugated Steel Pipe		LF	\$ 157.00	=	\$	-		\$ -	
42" Corrugated Steel Pipe		LF	\$ 180.00	=	\$	-		\$ -	
48" Corrugated Steel Pipe		LF	\$ 190.00	=	\$	-		\$ -	
54" Corrugated Steel Pipe		LF	\$ 278.00	=	\$	-		\$ -	
60" Corrugated Steel Pipe		LF	\$ 300.00	=	\$	-		\$ -	
66" Corrugated Steel Pipe		LF	\$ 364.00	=	\$	-		\$ -	
72" Corrugated Steel Pipe		LF	\$ 428.00	=	\$	-		\$ -	
78" Corrugated Steel Pipe		LF	\$ 492.00	=	\$	-		\$ -	
84" Corrugated Steel Pipe		LF	\$ 588.00	=	\$	-		\$ -	
Flared End Section (FES) RCP Size =		EA		=	\$	-		\$ -	
(unit cost = 6x pipe unit cost)									
Flared End Section (FES) CSP Size =		EA		=	\$	-		\$ -	
(unit cost = 6x pipe unit cost)									
End Treatment- Headwall		EA		=	\$	-		\$ -	
End Treatment- Wingwall		EA		=	\$	-		\$ -	
End Treatment - Cutoff Wall		EA		=	\$	-		\$ -	
Curb Inlet (Type R) L=5', Depth < 5'		EA	\$ 6,138.00	=	\$	-		\$ -	
Curb Inlet (Type R) L=5', 5' ≤ Depth < 10'		EA	\$ 7,981.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =5', 10' ≤ Depth < 15'		EA	\$ 9,242.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =10', Depth < 5'		EA	\$ 8,447.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =10', 5' ≤ Depth < 10'		EA	\$ 8,706.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =10', 10' ≤ Depth < 15'		EA	\$ 10,898.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =15', Depth < 5'		EA	\$ 10,984.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =15', 5' ≤ Depth < 10'		EA	\$ 11,775.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =15', 10' ≤ Depth < 15'		EA	\$ 12,876.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =20', Depth < 5'		EA	\$ 11,706.00	=	\$	-		\$ -	
Curb Inlet (Type R) L =20', 5' ≤ Depth < 10'		EA	\$ 12,920.00	=	\$	-		\$ -	
Grated Inlet (Type C), Depth < 5'		EA	\$ 5,138.00	=	\$	-		\$ -	
Grated Inlet (Type D), Depth < 5'		EA	\$ 6,347.00	=	\$	-		\$ -	
Storm Sewer Manhole, Box Base		EA	\$ 12,876.00	=	\$	-		\$ -	
Storm Sewer Manhole, Slab Base		EA	\$ 7,082.00	=	\$	-		\$ -	
Geotextile (Erosion Control)		SY	\$ 7.00	=	\$	-		\$ -	
Rip Rap, d50 size from 6" to 24"		Tons	\$ 89.00	=	\$	-		\$ -	
Rip Rap, Grouted		Tons	\$ 105.00	=	\$	-		\$ -	
Drainage Channel Construction, Size (W x H)		LF	\$ -	=	\$	-		\$ -	
Drainage Channel Lining, Concrete		CY	\$ 631.00	=	\$	-		\$ -	
Drainage Channel Lining, Rip Rap		CY	\$ 124.00	=	\$	-		\$ -	
Drainage Channel Lining, Grass		AC	\$ 1,626.00	=	\$	-		\$ -	
Drainage Channel Lining, Other Stabilization				=	\$	-		\$ -	
[insert items not listed but part of construction plans]				=	\$	-		\$ -	
[insert items not listed but part of construction plans]				=	\$	-		\$ -	
Section 2 Subtotal				=	\$	-		\$ -	



Fill out for the proposed channels and move them to section 3.

and level spreader

See responses above. Cost reflects grading. Seeding added per response. Riprap rundowns included. In Section 3 per comment.

PROJECT INFORMATION		
Space Village Filing No. 4	4/17/2023	MS227
Project Name	Date	PCD File No.

Description	Quantity	Units	Unit Cost	Total	(with Pre-Plat Construction)	
					% Complete	Remaining
AS-BUILT PLANS (Public Improvements inc. Permanent WQCV BMPs)		LS		= \$ -		\$ -
POND/BMP CERTIFICATION (inc. elevations and volume calculations)		LS		= \$ -		\$ -
Total Construction Financial Assurance						\$ 146,470.18
(Sum of all section subtotals plus as-builts and pond/BMP certification)						
Total Remaining Construction Financial Assurance (with Pre-Plat Construction)						\$ 146,470.18
(Sum of all section totals less credit for items complete plus as-builts and pond/BMP certification)						
Total Defect Warranty Financial Assurance						\$ 6,311.00
(20% of all items identified as (*). To be collateralized at time of preliminary acceptance)						

Unresolved Review 2
 Comment:
 - Include costs for as-built plans and pond certification letter.

Revised.

A

I hereby certify that this is an accurate and complete estimate of costs for the work as shown on the Grading and Erosion Control Plan and Construction Drawings associated with the Project.

Engineer (P.E. Seal Required)

Approved by Owner / Applicant Date

Approved by El Paso County Engineer / ECM Administrator Date



4 / 17 / 23