

# FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO. 2 EL PASO COUNTY, COLORADO

**Prepared for:**

Doubletree Ventures  
106 S. Kyrene Road #2  
Chandler, AZ 85226  
(480) 313-2724

**Prepared by:**

M&S Civil Consultants  
212 N. Wahsatch Avenue  
Suite 305  
Colorado Springs, CO 80903 (719) 955-5485

**February 2023**

Project #10-020  
PCD Filing No.: VR233 k



**FINAL DRAINAGE REPORT FOR CLAREMONT  
BUSINESS PARK 2 FILING NO. 2  
EL PASO COUNTY COLORADO**

**DRAINAGE PLAN STATEMENTS**

**ENGINEERS STATEMENT**

The attached drainage plan and report was prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

\_\_\_\_\_  
Virgil A. Sanchez, P.E. #37160  
For and on Behalf of M&S Civil Consultants, Inc

**DEVELOPER'S STATEMENT**

I, the developer(s) have read and will comply with all the requirements specified in this drainage report and plan.

BY: \_\_\_\_\_

TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

ADDRESS: Brian Zurek  
106 S. Kryene Road  
Chandler, AZ 85226

**EL PASO COUNTY'S STATEMENT**

Filed in accordance with the requirements of El Paso County Land Development Code, Drainage Criteria Manual Volumes 1 and 2, and the Engineering Manual, as amended.

BY: \_\_\_\_\_ DATE: \_\_\_\_\_

Joshua Palmer, P.E.  
~~Interim~~ County Engineer / ECM Administrator

CONDITIONS:



# FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO. 2 EL PASO COUNTY COLORADO

## TABLE OF CONTENTS

Purpose	4
General Location and Description	4
Soils	5
Previous Reports	5
Drainage Criteria	7
Floodplain Statement	7
Existing Drainage Conditions	7
Four Step Process	9
Proposed Drainage Conditions	10
Water Quality Provisions and Maintenance	14
Erosion Control	15
Construction Cost Opinion	15
Drainage & Bridge Fees	16
Summary	16
References	17

## APPENDIX

Vicinity Map  
Soils Map  
FEMA FIRM Panel  
Hydrologic Calculations  
Hydraulic Calculations / SFB WQCV Calculations  
BOCC Resolution 16-426  
Proposed Drainage Map  
Existing Drainage Map

Move Ex & Pr Drainage  
Maps to back of report

# FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO. 2 EL PASO COUNTY COLORADO

## Purpose

This Final Drainage Report for Claremont Business Park 2 Filing No. 2 is in support of the Final Plat, Preliminary Plan, and Construction Drawings of the subject site. This report functions to identify the existing and proposed runoff patterns and recommend proposed drainage improvements which are intended to safely convey runoff through the proposed development, while minimizing impacts to downstream facilities and adjacent properties. The analysis has been prepared in accordance with the requirements set forth by El Paso County and remains in compliance with the Final Drainage Report for Claremont Business Park 2 Filing No. 1 by M&S Civil Consultants.

## General Location and Description

The Claremont Business Park 2 Filing No.2 is a Replat of Lots 8, 9 & 10 and Tract B of Claremont Business Park 2 Filing No.1. The site is located in the Northeast  $\frac{1}{4}$  of the Northeast  $\frac{1}{4}$  of Section 8, and the Southeast  $\frac{1}{4}$  of the Southeast  $\frac{1}{4}$  of Section 5, Township 14 South, Range 65 West of the 6th P.M. in El Paso County, Colorado. The site is bordered to the southeast by U.S. Highway 24 and to the northeast by N. Marksheffel Road, to the north and west by Meadowbrook Parkway, and to the south by Claremont Business Park 2 Filing No. 1 (Lots 1-7). See Vicinity Map in Appendix for details.

The site consists of 4.988 acres which is currently vacant land. The replat will eliminate Tract B and redistribute the three (3) lots based around a newly aligned private roadway. The development project will construct a roadway and utilities through the site and into Filing 1. An existing access easement which is a portion of existing Lots 6 and 7 will allow for the proposed roadway to connect to the existing roadway (Gary Watson Point.) The Claremont Business Park 2 Filing 2 site is currently zoned "CS" and the proposed principal use for the site will be neighborhood commercial and light industrial.

In addition to the construction of the roadway and utilities, a storm sewer system will be constructed that will function to collect runoff from the future lots and a single (1) sand filter basin water quality pond will initially be provided to treat runoff from aforementioned improvements. The proposed storm sewer will tie into an existing system near Meadowbrook Parkway, which ultimately conveys runoff southwest into the East Fork of Sand Creek.

Per Resolution 16-426 of the BoCC, on-site WQCV is required but on-site stormwater detention is not required. (refer to appendix).

Individual drainage letters and/or reports shall be required with the development of each lot not otherwise clearly analyzed by this report for Claremont Business Park 2 Filing No. 2.

## Soils

The Natural Resources Conservation Service, United States Department of Agriculture, Web Soil Survey, indicates that the soils for this project are: Blakeland Loamy Sand (8), Blendon Sandy Loam (10) and Ellicott Loamy Course Sand (28). These soils have been characterized as having Hydrologic Soil Types "A" & "B". The soils classification used for this study is "B". Refer to the Soils Map located in the Appendix of this report

## Previous Studies

The proposed site and surrounding existing drainage facilities have been included in multiple drainage letters and reports. The following is a list of existing documents that were pertinent to analyzing this site.

- Falcon Drainage Basin Planning Study, by Matrix Design Group, dated September 2015.
- Final Drainage Report for Claremont Business Park Filing No.2, by Matrix Design Group, Inc. dated November 2006.
- Final Drainage Report for Claremont Business Park 2 Filing No. 1, by M&S Civil Consultants, approved 2/11/2021.
- Final Drainage Letter for Lot 1 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 4/01/2021.
- Final Drainage Letter for Lot 2 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 5/19/2021.
- Final Drainage Letter for Lot 3 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 05/19/2021.
- Final Drainage Letter for Lot 4 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 05/19/2021.
- Final Drainage Letter for Lot 5 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 03/03/2021.
- Final Drainage Letter for Lot 6 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 07/08/2021.
- Final Drainage Letter for Lot 7 of Claremont Business Park 2 Filing No.1, by M&S Civil Consultants, approved 3/31/2021.

## Drainage Criteria

As required by El Paso County, Colorado, this report has been prepared in accordance to the criteria set forth in the El Paso County Drainage Criteria Manual Volume 1 & 2 (DCM), the El Paso County Engineering Criteria Manual (ECM), and El Paso County Resolutions 15-042 and 19-245.

### **Design Event Frequency**

The 100-year storm event was used as the major storm for the project, and the 5-year storm event was used as the minor storm.

### **Method of Analysis**

The rational method was used to calculate peak flows as the tributary areas are less than 100 acres.

Where:  $Q=C*i*A$

Q = Maximum runoff rate in cubic feet per second (cfs)

C = Runoff coefficient

i = Average rainfall intensity (inches per hour)

A = Area of drainage sub-basin (acres)

### **Runoff Coefficient**

Rational Method coefficients from Table 6-6 of the Drainage Criteria Manual for developed land were utilized in the Rational Method calculations. Composite percent impervious and C values were calculated using roofs, commercial areas, asphalt drives, landscaped areas and parks found within the aforementioned table.

### **Time of Concentration**

The time of concentration consists of the initial time of overland flow and the travel time (street or channel, etc) to a downstream structure or point of interest. A minimum time of concentrations of 5 minutes is utilized for urban areas.

### **Rainfall Intensity**

The hypothetical rainfall depths for the 1-hour storm duration were taken from Table 6-2 of the Drainage Criteria Manual.

Project 1-Hour Rainfall Depth Storm Recurrence Interval Rainfall Depth (inches)

5-year 1.50" 100-year 2.52"

The rainfall intensity equation for the Rational Method was taken from Drainage Criteria Manual Volume 1 Figure 6-5.

### **Hydraulic Grade Line Analysis**

StormCAD was utilized to analyze the proposed storm sewer system and determine the Hydraulic Grade Line (HGL's) profiles for the major and minor storms. The standard method was used to calculate head loss in the system with K coefficients taken from Table 9-4 of the Colorado Springs DCM.

In addition to the DCM, The Mile High Flood District BMP Sizing (UD-BMPv.3.07) and Detention Design (MHFD Detention v4.06) worksheets were utilized for to check to verify the existing the water quality

ponds still functions with the revised tributary areas and impervious values. These spreadsheets were also utilized for the design of the proposed and future on-site water quality ponds. The MFHD-Inlet v5.02 worksheet was utilized to calculate both the street capacities and evaluate inlet capacities.

## Floodplain Statement

According to the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) Panel No. 08041C0756G, revised December 7, 2018. No portion of this site is located within the 100 year floodplain. See Appendix.

## Existing Drainage Conditions

As the site has been graded previously with the development of Filing 1, the vegetation is sparse, consisting primarily of native grasses and weeds. Existing site terrain generally slopes from north to southwest at grade rates that vary between 1.2% and 2%. A soil retention wall runs along the eastside of the proposed site, next to U.S. Highway 24 and N. Marksheffel Road, and borders a large portion of the back of the proposed lots. A depression or sediment pond is located in the southwest corner of the site, which was to serve as a future singular water quality pond for the 3 future lots. An existing 24" ADS private storm drain has been constructed along the east side of Meadowbrook Parkway that extends to this existing sediment pond. This pipe will serve as the outfall for the proposed site development.

As the proposed project will construct street improvements within Lots 6 and 7 of Claremont Business Park Filing No. 1, the existing and proposed drainage analysis will be expanded to evaluate changes in drainage patterns to ensure no negative affects to downstream facilities. An existing conditions drainage map is included in the appendix of this report to accompany the following discussion.

### Existing Conditions Detailed Drainage Discussion

**Design Point 1** (Q5 = 1.8 cfs, Q100 = 11.8 cfs) consists of runoff from undeveloped **Basins A, B, and C**. **Basins A and B** are 0.19 and 0.30 acres of existing roadway embankment located generally between the subject site and existing US. Hwy 24 and Marksheffel Road. **Basin C** consists of 4.90 acres of that generally consist of the remaining undeveloped portions of the subject site. Runoff from the three basins is conveyed to an existing sediment pond located in the southwest corner of the site at DP1.

An existing 24" ADS (Pipe 11) is located at the southwest corner of the pond which collects runoff.

**Design Point 2** was omitted.

**Design Point 3** (Q5 = 2.2 cfs, Q100 = 4.4 cfs) consists of runoff from **Basin H1** and **Basin I1**. **Basin H1** is 0.18 acres of undeveloped roadway embankment and **Basin I1** consists 0.57 acres of roof top, asphalt paving and landscaped areas. Runoff from the two basins flow into an existing 3.0 foot wide x 6 inch high concrete chase with 6 inch curb heights which discharges into the cul-de-sac of Gary Watson Point.

base on existing  
map.

**Design Point 4** (Q5 = 1.8 cfs, Q100 = 4.1 cfs) consists of runoff from **Basin H2** and **Basin I2**. **Basin H2** is 0.40 acres of undeveloped roadway embankment and **Basin I2** consists 0.48 acres of asphalt paving and landscaped areas. Runoff from basins is collected in curb and gutter which discharges into the cul-de-sac of Gary Watson Point.

**Design Point 5** (Q5 = 0.8 cfs, Q100 = 1.6 cfs) consists of runoff from **Basin H3** and **Basin I7**. **Basin H3** is 0.04 acres of undeveloped roadway embankment and **Basin I7** consists 0.23 acres of asphalt paving and landscaped areas. Runoff from basins is collected in curb and gutter which discharges into the cul-de-sac of Gary Watson Point.

DP3 thru 5 per hydrology spreadsheet

WQ Pond 2

**Design Point 6** (Q5 = 8.2 cfs, Q100 = 16.5 cfs) consists of runoff from **Basin I3, I4, I5, I6** and **DP1-3**. **Basins I3, I4, I5,** and **I6** are of 0.58, 0.43, 0.23, and 0.19 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. The runoff from the four basins combines with flows from **DP1-3** within the private street section of Gary Watson. Runoff is collected by a pair of existing 15' Type R at grade inlets located at **DP6**. Collected runoff is conveyed to the west underground via private 24" storm sewer to an existing WQ pond (**PR13-14**). **Inlet 3** collects Q5=4.1 and Q100=7.9cfs, with Q5=0.0 cfs and Q5=0.4 cfs of flow-by in the respective storm events. **Inlet 4** collects Q5=4.1 and Q100=8.0cfs, with Q5=0.0 cfs and Q5=0.3 cfs of flow-by in the respective storm events. Runoff bypassing the existing inlets continues westward to **Design Point 7** and **8**.

Q100

**Design Point 7** (Q5 = 2.4 cfs, Q100 = 7.5 cfs) consists of flow-by runoff from **Inlet 3** and flows within **Basin J1**. **Basin J1** consists 0.76 acres of rooftop, asphalt paving and landscaped areas. Runoff from **Basin J1** and flow-by from the inlet is conveyed within the curb and gutter to an existing 15' Type R at grade inlets located at **DP7**. **Inlet 5** collects Q5=2.4 and Q100=7.3cfs, with Q5=0.0 cfs and Q5=0.2 cfs of flow-by in the respective storm events. An existing 18" storm sewer (**PR15**) conveys the intercepted runoff underneath Gary Watson.

Q100

**Design Point 8** (Q5 = 0.9 cfs, Q100 = 4.1 cfs) consists of flow-by runoff from **Inlet 4** and flows within **Basin J2 and J3**. **Basins J2** and **J3** are of 0.25 and 0.01 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. Runoff from **Basins J2** and **J3** and flow-by from the inlet is conveyed within the curb and gutter to an existing 15' Type R at grade inlets located at **DP8**. **Inlet 6** collects Q5=0.9 and Q100=4.1cfs, with no flow-by in either of the storm events. An existing 18" storm sewer (**PR16**) conveys the intercepted runoff from the pair of inlets southward underground.

**Design Point 9** (Q5 = 3.8 cfs, Q100 = 9.7 cfs) consists of runoff from **Basin H4, L** and **M4**. **Basin H4** and **L** are 0.10 and 1.32 acres of undeveloped roadway embankment and **Basin M4** consists of 0.98 acres of roof top, asphalt paving and landscaped areas. Runoff from the three basins flow into an existing a 2' foot trapezoidal channel located at the south end of the property.

**Design Point 10** (Q5 = 5.3 cfs, Q100 = 12.3 cfs) consists of runoff from **Basin M2, M3** and **DP9**. **Basins M2** and **M3** are of 0.24 and 0.37 acres in size respectively and consist of roof top, asphalt paving and



landscaped areas within the development. Runoff from the two basins combine with **DP9** flows in an existing a 2' foot trapezoidal channel located at the south end of the property. Runoff at **DP10** will enter the existing Filing 1 **WQ Pond 2** via an existing trapezoidal grouted riprap rundown.

**Design Point 11** (Q5 = 1.4 cfs, Q100 = 2.5 cfs) consists of runoff from **Basin M1** and **K4**. **Basins M1** and **K4** are of 0.28 and 0.05 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. The runoff from the two basins is directed into the existing **WQ Pond 2** via an existing concrete rundown at **DP11**.

**Design Point 12** (Q5 = 1.1 cfs, Q100 = 2.0 cfs) consists of runoff from **Basin K2, K3** and **N1**. **Basins K2, K3** and **N1** are of 0.05, 0.15 and 0.06 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. The runoff from the t**3** basins is directed into the existing **WQ Pond 2** via an existing concrete rundown at **DP12**.

**Design Point 13** (Q5 = 0.7 cfs, Q100 = 1.3 cfs) consists of runoff from **Basin K1**. **Basins K1** is 0.17 acres in size and consists of roof top, asphalt paving and landscaped areas within the development. The runoff from the basins is directed to an existing beehive grated manhole located in the southwest corner of the lot. Runoff collect by the inlet combines with flows conveyed by **PR12**, in **PR13** a private 24" storm sewer that outfalls into **WQ Pond 2**.

Is this Inlet 7 as labeled on the existing drainage map? If so, please include the name in the text.

**Design Point 14** (Q5 = 19.3 cfs, Q100 = 43.9 cfs) consists of runoff from **Basin N2** and **DP10-13**. **Basins N2** is 0.41 acres in size and consists of a sand filter water quality pond (**WQ Pond 2**).

#### **Basin D, O1, O2,**

**Basins D, O1,** and **O2** are 0.23, 0.12 and 0.06 acres in size and consist of asphalt, concrete, and landscaped areas along the western periphery of the development. The runoff from the three basins is directed to Existing Meadowbrook Parkway. The 5 year event and 100 year event peak runoff rates from **Basin D, O1,** and **O2** are Q5 = 0.1 cfs, Q100 = 0.7 cfs, Q5 = 0.1 cfs, Q100 = 0.4 cfs and Q5 = 0.1 cfs, Q100 = 0.3 cfs respectively.

#### **Basin P**

**Basins P** (Q5 = 0.0 cfs, Q100 = 0.3 cfs) is 0.11 acres in size and consists of landscaped and undeveloped areas along the southern periphery of the development. The runoff from the basins is directed to the adjacent development.

## **Four Step Process**

The development will follow the "Four Step Process" as outlined below:

### **Step 1 - Employ Runoff Reduction Practices**

The proposed development uses Low Impact Development (LID) practices to reduce runoff. When possible runoff is to be directed to pervious areas to promote infiltration and limit directly connected impervious areas. .

### **Step 2 - Stabilize Drainageways**

There are no drainageways on-site to stabilize. The site is upstream of an existing 42"/48" RCP storm sewer system that discharges directly into the Sand Creek Channel via an outlet structure with wingwalls (privately owned and maintained by the Central Marksheffel Metropolitan District). The Claremont Commercial Filing No. 2 site proposes Sand Filter Water Quality Facilities that will treat runoff prior to discharging to the existing storm sewer system. There will be no adverse affects on downstream developments as a result of the development of this subdivision.

### **Step 3 - Provide Water Quality Capture Volume**

One (1) Sand Filter Basin water quality facility is proposed to provide WQCV at the time of the writing of this report. Up to four (4) future Sand Filter water quality facilities maybe required with the full build out of the parcel.

### **Step 4 - Consider Need for Industrial and Commercial BMP's**

This submittal provides a Preliminary Grading and Erosion Control plan. A Final GEC plan with BMP's in place shall be required with a Final Plat and Site Development applications. The proposed project will use silt fence, a vehicle tracking control pad, a concrete washout area, mulching and reseeding to mitigate the potential for erosion across the site.

## **Proposed Drainage Characteristics**

### **General Concept Drainage Discussion**

The "Final Drainage Report for Claremont Business Park Filing No. 2", dated November 2006, by Matrix Design Group, Inc. indicated that flows discharged from the subject site were to be collected and conveyed to the East Fork of Sand Creek Channel via a storm system that was to parallel Meadowbrook Parkway. As a portion of the construction of Claremont Business Park 2 Filing No.1 the existing storm sewer system was extended along the eastern side of Meadowbrook Parkway to collect runoff from the Lots 8, 9 & 10 and Tract B of Claremont Business Park 2 Filing No.1 and thus remain in compliance with the previous drainage plans and studies.

The Claremont Business Park 2 Filing No.2 project will Replat of Lots 8, 9 & 10 and Tract B of Claremont Business Park 2 Filing No.1, eliminate Tract B and redistribute the three (3) lots based around a newly aligned private roadway. The subject site is anticipated to continue to consist of neighborhood commercial and light industrial use and thus the properties will consist of asphalt, curb and gutter, parking areas, buildings, and landscaping.

A private storm sewer will be extended via drainage easements to collect runoff from each lot and the roadway. In lieu of a singular water quality pond (as previously anticipated by the CBP2, Filing 1 FDR) to treat the runoff from the subject site, each lot will be required to provide and maintain its own water quality facilities.

Pond 4 is shown as future on drainage map on pdf pg 126 below. Revise text and/or map to remove discrepancy.

The initial construction of the project will include the construction of storm main to each lot, the construction of El Jefe Heights roadway and subsurface utilities such as water and wastewater to support future development. Temporary sediment basins will be constructed at the terminus of the storm sewers stubs to collect runoff from the undeveloped lots. A permanent water quality pond will be constructed at the southwest corner of Lot 2 to provide treatment for the proposed roadway and a portion of Lot 2. With the exception of the current permanent WQ Pond 4, no routing was considered when evaluating the discharge from the proposed lots to size the proposed storms sewer.

Individual drainage letters and/or reports shall be required with the development of each future lot not otherwise clearly analyzed by this report. A proposed conditions drainage map is included in the Appendix of this report to accompany the following discussion.

### Proposed Conditions Detailed Drainage Discussion

**Design Point 1** (Q5 = 5.9 cfs, Q100 = 11.2 cfs) consists of runoff from **Basin A** and **Basin B**. **Basin A** is 0.21 acres of undeveloped roadway embankment and **Basin B** consists 1.50 acres of future roof top, asphalt paving and landscaped areas associated with commercial or industrial development. Runoff from the two basins will be directed to the southwest and collected by a private 18" ADS storm (**PR1**) at the southwest corner of the lot. A WQ facility or CDS unit will need to be provided upon development.

**Design Point 2** (Q5 = 3.0 cfs, Q100 = 5.8 cfs) consists of runoff from **Basin C** and **Basin D**. **Basin C** is 0.12 acres of undeveloped roadway embankment and **Basin D** consists 0.77 acres of future roof top, asphalt paving and landscaped areas associated with commercial or industrial development within the northern half of Lot 2. Runoff from the basin will be directed to the southwest and collected by a private 18" ADS storm (**PR2**) at the middle of the western boundary of the lot. A WQ facility or CDS unit will need to be provided upon development.

**Design Point 3** (Q5 = 1.2 cfs, Q100 = 2.3 cfs) consists of runoff from **Basin F**. **Basin F** consists 0.30 acres of future roof top, asphalt paving and landscaped areas associated with commercial or industrial development within the northeastern portion of Lot 3. Runoff from the basin will be directed to the southeast and collected by a private 18" ADS storm at the middle of the eastern boundary of the lot. A WQ facility or CDS Unit will need to be provided upon development.

**Design Point 4** (Q5 = 1.0 cfs, Q100 = 1.7 cfs) consists of runoff from **Basin E2**. **Basin E2** consists 0.21 acres of asphalt paving, sidewalks, and landscaped areas associated with a portion of EL Jefe Heights. Runoff from the basin will be directed to the south and collected at low point by a private 5' Type R sump inlet. A proposed private 18" ADS Storm Drain will convey the collected runoff east under the roadway. (Inlet 1)

**Design Point 5** (Q5 = 1.2 cfs, Q100 = 2.2 cfs) consists of runoff from **Basin E1**. **Basin E1** consists 0.27 acres of asphalt paving, sidewalks, and landscaped areas associated with a portion of EL Jefe Heights. Runoff from the basin will be directed to the south and collected at low point by a private 5' Type R sump inlet. (Inlet 2)

sump inlet. Runoff collect by the inlet combines with flows conveyed by **PR5**, in **PR6** a private 18" storm sewer that outfalls into **WQ Pond 2**. In the event that the inlets at **DP4** and **DP5** were to become clogged runoff would overtop the localized high point of the road and continue south within El Jefe Heights.

**Design Point 6** (Q5 = 5.1 cfs, Q100 = 9.6 cfs) consists of runoff from **Basin C1, D1** and **Pipe Run 6 (PR6)**. **Basin C1** is 0.17 acres of undeveloped roadway embankment and **Basin D** consists 0.78 acres of future roof top, asphalt paving and landscaped areas associated with commercial or industrial development within the northern half of Lot 2. Runoff from the basin will be directed to the southwest to a permanent WQ facility and combine with flows conveyed within **PR6**. A permanent sand filter water quality facility will discharge runoff to the south where it will combine with flows conveyed within **PR4**, a private 24" ADS storm sewer (**PR8**) at peak flow rates of Q5 = 5.9 cfs, Q100 = 13.1 cfs.

**Design Point 7** (Q5 = 4.7 cfs, Q100 = 8.7 cfs) consists of runoff from **Basin G2**. **Basin G2** consists 1.15 acres of future roof top, asphalt paving and landscaped areas associated with commercial or industrial development within the northeastern portion of Lot 3. Runoff from the basin will be directed to the southwest and collected by a private 24" ADS storm at the middle of the eastern boundary of the lot. A WQ facility or CDS unit will need to be provided upon development.

The subject site fully developed peak flow being discharge to an existing 24" ADS (**PR11**) which is located at the southwest corner of the site is estimated at Q5 = 7.1 cfs, Q100 = 16.2 cfs.

**Design Point 8** (Q5 = 2.2 cfs, Q100 = 4.3 cfs) consists of runoff from **Basin H1** and **Basin I1**. **Basin H1** is 0.16 acres of undeveloped roadway embankment and **Basin I1** consists 0.55 acres of roof top, asphalt paving and landscaped areas. Runoff from the two basins flow into an existing 3.0 foot wide x 6 inch high concrete chase with 6 inch curb heights which discharges into the cul-de-sac of Gary Watson Point.

Label chase on drainage map


**Design Point 9** (Q5 = 1.8 cfs, Q100 = 4.1 cfs) consists of runoff from **Basin H2** and **Basin I2**. **Basin H2** is 0.40 acres of undeveloped roadway embankment and **Basin I2** consists 0.48 acres of asphalt paving and landscaped areas. Runoff from basins is collected in curb and gutter which discharges into the cul-de-sac of Gary Watson Point.

**Design Point 10** (Q5 = 0.8 cfs, Q100 = 1.6 cfs) consists of runoff from **Basin H3** and **Basin I7**. **Basin H3** is 0.04 acres of undeveloped roadway embankment and **Basin I7** consists 0.23 acres of asphalt paving and landscaped areas. Runoff from basins is collected in curb and gutter which discharges into the cul-de-sac of Gary Watson Point.

DP 3 thru 5

**Design Point 11** (Q5 = 8.4 cfs, Q100 = 16.7 cfs) consists of runoff from **Basin I3, I4, I5, I6** and **DP1-3**. **Basins I3, I4, I5,** and **I6** are of 0.45, 0.55, 0.23, and 0.19 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. The runoff from the four basins combines with flows from **DP1-3** within the private street section of Gary Watson. Runoff is collected by a pair of existing 15' Type R at grade inlets located at **DP6**. Collected runoff is conveyed to the west underground via private 24" storm sewer to an existing WQ pond (Fil1Pond) (**PR13-14**). **Inlet 3** collects

Q5=4.1 cfs and Q100=7.9 cfs, with Q5=0.0 cfs and Q5=0.4 cfs of flow-by in the respective storm events. **Inlet 4** collects Q5=4.2 cfs and Q100=8.0cfs, with Q5=0.0 cfs and Q5=0.3 cfs of flow-by in the respective storm events. Runoff bypassing the existing inlets continues westward to **Design Point 12** and **13**.




**Design Point 12** (Q5 = 2.8 cfs, Q100 = 8.1 cfs) consists of flow-by runoff from **Inlet 3** and flows within **Basin J1**. **Basin J1** consists 0.69 acres of rooftop, asphalt paving and landscaped areas. Runoff from **Basin J1** and flow-by from the inlet is conveyed within the curb and gutter to an existing 15' Type R at grade inlets located at **DP7**. **Inlet 5** collects Q5=2.4 cfs and Q100=7.3 cfs, with Q5=0.0 cfs and Q5=0.2 cfs of flow-by in the respective storm events. An existing 18" storm sewer (**PR15**) conveys the intercepted runoff underneath Gary Watson.



Include O1 in DP12 and show flow arrows for O1

**Design Point 13** (Q5 = 1.0 cfs, Q100 = 5.0 cfs) consists of flow-by runoff from **Inlet 4** and flows within **Basin J2 and J3**. **Basins J2 and J3** are of 0.25 and 0.01 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. Runoff from **Basins J2 and J3** and flow-by from the inlet is conveyed within the curb and gutter to an existing 15' Type R at grade inlets located at **DP13**. **Inlet 6** collects Q5=1.0 cfs and Q100=5.0 cfs, with no flow-by in the respective storm events. An existing 18" storm sewer (**PR16**) conveys the intercepted runoff from the pair of inlets southward underground.

**Design Point 14** (Q5 = 3.8 cfs, Q100 = 9.7 cfs) consists of runoff from **Basin H4, L and M4**. **Basin H4 and L** are 0.10 and 1.32 acres of undeveloped roadway embankment and **Basin M4** consists of 0.98 acres of roof top, asphalt paving and landscaped areas. Runoff from the three basins flow into an existing a 2' foot trapezoidal channel located at the south end of the property.



**Design Point 15** (Q5 = 5.3 cfs, Q100 = 12.3 cfs) consists of runoff from **Basin M2, M3 and DP9**. **Basins M2 and M3** are of 0.24 and 0.37 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. Runoff from the two basins combine with **DP14** flows in an existing a 2' foot trapezoidal channel located at the south end of the property. Runoff at **DP15** will enter the existing Filing 1 **WQ Pond 2** via an existing trapezoidal grouted riprap rundown.

**Design Point 16** (Q5 = 1.4 cfs, Q100 = 2.5 cfs) consists of runoff from **Basin M1 and K4**. **Basins M1 and K4** are of 0.28 and 0.05 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. The runoff from the two basins is directed into the existing **WQ Pond 2** via an existing concrete rundown.

**Design Point 17** (Q5 = 1.1 cfs, Q100 = 2.0 cfs) consists of runoff from **Basin K2, K3 and N1**. **Basins K2, K3 and N1** are of 0.05, 0.15 and 0.06 acres in size respectively and consist of roof top, asphalt paving and landscaped areas within the development. The runoff from the **3** basins is directed into the existing **WQ Pond 2** via an existing concrete rundown.

**Design Point 18** (Q5 = 0.7 cfs, Q100 = 1.3 cfs) consists of runoff from **Basin K1**. **Basins K1** is 0.17 acres in size and consists of roof top, asphalt paving and landscaped areas within the

development. The runoff from the basins is directed to an existing beehive grated manhole located in the southwest corner of the lot.

DP15-18

**Design Point 19** (Q5 = 19.8 cfs, Q100 = 44.7 cfs) consists of runoff from **Basin N2** and **DP10-13**. **Basins N2** is 0.41 acres in size and consists of a sand filter water quality pond (**WQ Pond 2**).

#### **Basin G1, O1, O2,**

**Basins G1, O1,** and **O2** are 0.27, 0.12 and 0.06 acres in size and consist of asphalt, concrete, and landscaped areas along the western periphery of the development. The runoff from the three basins is directed to Existing Meadowbrook Parkway. The 5 year event and 100 year event peak runoff rates from Basin **G1, O1,** and **O2** are Q5 = 0.4 cfs, Q100 = 1.2 cfs, Q5 = 0.1 cfs, Q100 = 0.4 cfs and Q5 = 0.1 cfs, Q100 = 0.3 cfs respectively.

#### **Basin P**

**Basins P** (Q5 = 0.0 cfs, Q100 = 0.3 cfs) is 0.11 acres in size and consists of landscaped and undeveloped areas along the southern periphery of the development. The runoff from the basins is directed to the adjacent development.

The Matrix "Final Drainage Report for Claremont Business Park Filing No. 2" calculated that DP 1 combining Sub Basins B1 and B2 generated of (Q5=31.5 cfs and Q100=63.6). The proposed developments (CBPF2 Filings 1 and 2) will release Q5=19.8 cfs and Q100=44.7 which is less than what was anticipated by the Matrix report. Therefore the proposed development shall not have a negative impact on the downstream storm system and is adequately sized to convey the proposed generated flows.

## **Water Quality Provision and Maintenance**

The subject site was previously analyzed within the Final Drainage Report for Claremont Business Park Filing No. 2 prepared by Matrix Design Group approved April 24, 2006. Per Resolution 16-426 of the BoCC, on-site WQCV is required but on-site stormwater full spectrum detention (refer FDR for Claremont Business Park Fil. 2). The water quality volume required for the site has been determined using the MHFD UD-Detention workbook per the guidelines set forth in the City of Colorado Springs/El Paso County Drainage Criteria Manual - Volume II.

As previously discussed water quality for the site (CBP2F2) will be provided by proposed Sand Filter Basins (SFB). Pond 3 is to be constructed initially and will function to treat runoff from the newly constructed improvements (roadway, sidewalks) and the western half of Lot 2 or approx 1.43 acres at 81.8 imperviousness.

Pond 3 will provide 0.032 acre-feet of water quality storage. Per ECM section 1.7.1.C.1, 20% of the project site (not to exceed 1.0 acre) may be excluded from the 100% WQ treatment requirement per El Paso County criteria. This report identifies that **Basins G1, O1, O2** and **P** is unable to reach one of the

Which two? This section only previously mentions Pond 3.

Lots 8-10 are being renamed with the subdivision. Please revise lot numbers.

proposed WQ ponds. Combined total acreage of the Basins is 0.56 AC, and doesn't exceed the 1.0 acre maximum allowance of acreage runoff allowed per EPC criteria.

Flows tributary to the two SFBs are released through outlet structures into an existing storm sewer system located along Meadowbrook Parkway. Water quality pond 1 will be private and shall be maintained by the property owners (equal shares determined by size of lots 8-10). Water quality pond 2 will be private and shall be maintained by the property owners (equal shares determined by size of lots 1-7). Access shall be granted to the owner and El Paso County for access and maintenance of the private WQCV facility. A private maintenance agreement document shall accompany the final drainage report(s) submittal(s) which construct the two ponds.

The report identifies Pond 3 being built and Pond 5 (location of existing sediment basin on Tract B) being removed. Please revise paragraph for consistency.

This paragraph only mentions Pond 1 and 2. What about Pond 4 and 5? (Pond 3 already previously discussed in this section)

Erosion Control

It is the policy of the El Paso County that a grading and erosion control plan (GEC) with the drainage report. The GEC incorporates silt fence, vehicle traffic control, inlet and outlet controls, sediment basin and other best management practices (BMP's) as identified in the DCM Volume 2.

### Construction Cost Opinion

#### Private Drainage Facilities (NON-Reimbursable) Including Sand Filter WQ Pond 3:

Item	Description	Quantity	Unit Cost	Cost
1.	18" PP	394 LF	\$48 /LF	\$18,912.00
2.	18" RCP	50 LF	\$60 /LF	\$3,000.00
3.	18" RCP FES	2 LF	\$650 /LF	\$1,300.00
4.	24" PP	851 LF	\$75 /EA	\$63,825.00
5.	Type L Riprap	6 CY	\$75 /CY	\$450.00
6.	CDOT Type C Grated Inlet	1 EA	\$4,500 /EA	\$4,500.00
7.	CDOT Type R 5' Sump Inlet	2 EA	\$6,500 /EA	\$13,000.00
8.	Type II Manhole	7 EA	\$5,000 /EA	\$35,000.00
9.	WQCV Sand Filter Pond	1 EA	\$25,000 /EA	\$25,000.00
				<b>\$164,987.00</b>
Engineering Costs (10%)				<b>16,498.70</b>
				<b>181,485.70</b>

Note: The required infrastructure (private) and future ponds (private) for Claremont Business Park 2 Filing 2, Lots 1-3 will be provided in subsequent drainage report and/or letters.

M & S Civil Consultants, Inc. (M & S) cannot and does not guarantee the construction cost will not vary from these opinions of probable costs. These opinions represent our best judgment as design professionals familiar with the construction industry and this development in particular. The above is only an estimate of the facility cost in 2023.

Provide an estimate of the proposed imperviousness of the site and difference from the previously approved drainage report.

### Drainage and Bridge Fees

This site is in the Sand Creek Drainage Basin. The site was previously subdivided into ten commercial lots as a portion of Claremont Business Park 2, Filing No.1. The proposed project will replat the existing Lot and create Claremont Business Park 2, Filing No.2

Drainage fees were paid at the time of the previous platting as Tract C of Claremont Business Park Filing No. 2 (Reception No. 207712506), therefore no additional Drainage Bridge and/or Pond fees are required.

### Summary

The proposed design meets the design assumptions utilized in the "Final Drainage Report for Claremont Business Park Filing No. 2", by Matrix Design Group, Inc that is included in Appendix. The Matrix "Final Drainage Report for Claremont Business Park Filing No. 2" calculated that DP 1 combining Sub Basins B1 and B2 generated of (Q5=31.5 cfs and Q100=63.6). The proposed developments (Filing 1 and Filing 2) will release Q5=19.8 cfs and Q100=44.7 which is less than what was anticipated by the Matrix report. Therefore the proposed development shall not have a negative impact on the downstream storm system and is adequately sized to convey the proposed generated flows. Thus the development of Claremont Business Park 2 Filing No.2 shall not adversely affect the surrounding development. The proposed drainage facilities will adequately convey, detain and route runoff from the onsite & offsite flows to existing facilities. All drainage facilities described herein and shown on the included Proposed Drainage Map (See Appendix) are subject to change being dependent upon individual lot development but owners/developer of the lots shall comply with this final drainage report that will be submitted with the final plat application. Care will be taken to accommodate overland emergency flow routes on site and temporary drainage conditions.

Completing a "Water Quality Treatment Summary Table" like the example provided below would greatly help us clearly see that WQ req's are being met for the whole site, if you could do one for this site.

The areas of Basin G1, O1, O2, and P would be in this column

delete this column if no RR is anticipated for this site.

From the PBMP Form, this column should be blank.

Add rows for each basin within this filing.

Make a column for each of the 5 ponds.

Basin ID	Total Area (ac)	Total Proposed Disturbed Area (ac)	Area Trib to Pond A (ac)	Disturbed Area Treated via Runoff Reduction (ac)	Area Excluded from WQ per ECM App I.7.1.C.1 (ac)	Area Excluded from WQ per ECM App I.7.1.B.# (ac)	Applicable WQ Exclusions (App I.7.1.B.#)
A	4.50	4.50	4.50	-	-	-	
B	1.25	1.25	-	1.00	0.25	-	
C	6.00	4.00	-	-	-	4.00	ECM App I.7.1.B.5
D	2.50	2.50	1.00	-	0.50	1.00	ECM App I.7.1.B.7
E	3.00	-	3.00	-	-	-	
F	8.25	-	-	-	-	-	
Total	25.50	12.25	8.50	1.00	0.75	5.00	
Comments		[For each row, the sum of the values in Columns 4-7 must be greater than or equal to the value in Column 3 above.]	[Values in this column can be more than Column 3 if over-treating non-disturbed areas.]	See RR calc spreadsheet.	[Total must be <20% of site and <1ac.]		






## References

1. "El Paso County and City of Colorado Springs Drainage Criteria Manual".
2. "Urban Storm Drainage Criteria Manual"
3. Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Web Soil Survey. Available online at the following link: <http://websoilsurvey.sc.egov.usda.gov/>. Accessed: February 02, 2023.
4. Flood Insurance Rate Map (FIRM), Federal Emergency Management Agency, Effective dated December 7, 2018.
5. "Final Drainage Report for Claremont Business Park Filing No. 2", by Matrix Design Group, Inc dated November 2006.
6. "Falcon Drainage Basin Planning Study", by Matrix Design Group, dated September 2015.
7. "Final Drainage Report for Claremont Business Park Filing No.2", by Matrix Design Group, Inc. dated November 2006.
8. "Final Drainage Report for Claremont Business Park 2 Filing No. 1", by M&S Civil Consultants, approved 2/11/2021.
9. "Final Drainage Letter for Lot 1 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 04/01/2021.
10. "Final Drainage Letter for Lot 2 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 05/19/2021.
11. "Final Drainage Letter for Lot 3 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 05/19/2021.
12. "Final Drainage Letter for Lot 4 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 05/19/2021.
13. "Final Drainage Letter for Lot 5 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 03/03/2021.
14. "Final Drainage Letter for Lot 6 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 07/08/2021.
15. "Final Drainage Letter for Lot 7 of Claremont Business Park 2 Filing No.1", by M&S Civil Consultants, approved 03/31/2021.

## Appendix

# Vicinity Map



# VICINITY MAP

N.T.S.





## Soils Map


CLAREMONT BUSINESS PARK 2 FILING NO. 2


2/2/2023 11:50 AM


O:\10020A-CBP-Dunkin Donuts\Donuts\Eng Exhibits\10020-Soils Map.dwg



HYDROLOGIC TYPE A SOILS 


HYDROLOGIC TYPE B SOILS 

WATERSHED BOUNDARY 

SITE BOUNDARY 




1" = 300'



Scale in Feet

Map unit symbol	Map unit name	Rating
8	Blakeland loamy sand, 1 to 9 percent slopes	A
10	Blendon sandy loam, 0 to 3 percent slopes	B
28	Ellicott loamy coarse sand, 0 to 5 percent slopes	A


SOILS MAP



CIVIL CONSULTANTS, INC.

212 N. WAHSATCH AVE., STE 305  
 COLORADO SPRINGS, CO 80903  
 PHONE: 719.955.5485

## FEMA FIRM Panel



**FLOOD HAZARD INFORMATION**  
SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP  
FOR DRAFT FIRM PANEL LAYOUT

	Without Base Flood Elevation (BFE) Zone A, V, A59
	With BFE or Depth Zone AE, AH, VE, AR
	Regulatory Floodway
	0.2% Annual Chance Flood Hazard, Areas of 1% Annual Chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
	Future Conditions 1% Annual Flood Zone X
	Area with Reduced Flood Risk due to Levee Sea Walls Zone X
	Area with Flood Risk due to Levee Zone D
	NO SCREEN Area of Minimal Flood Hazard Zone X
	Effective LOMs
	Area of Undetermined Flood Hazard Zone D
	Channel, Culvert, or Storm Sewer
	Levee, Dike, or Floodwall
	20.2 Cross Sections with 1% Annual Chance
	17.5 Water Surface Elevation
	Coastal Transsect
	Profile Baseline
	Hydrographic Feature
	Base Flood Elevation Line (BFE)
	Limit of Study
	Jurisdiction Boundary

**NOTES TO USERS**

For information and questions about this Flood Insurance Rate Map (FIRM), available products associated with this map, or to request a copy of this map, please contact the FEMA Map Information Data Center at 1-877-FEMA-MAP (1-877-352-2527) or visit the FEMA Flood Map Service Center website at <https://msc.fema.gov>. Additional information about this map, including a list of products, can be obtained directly from the website, and/or original versions of this map. Many of these products can be obtained directly from the website. Communities already listed on adjacent FIRM panels must obtain a current copy of the adjacent panel as well as the current FIRM index. These may be obtained directly from the Flood Map Service Center at the number listed above.


For community and countywide map dates, refer to the Flood Insurance Study Report for this jurisdiction. To determine if flood insurance is available in this community, contact your insurance agent or call the National Flood Insurance Program at 1-800-456-6620.

Base map information shown on this FIRM was provided in digital format by the United States Geological Survey (USGS). The base map shown is the USGS National Map, Contouring, L, last revised October, 2020.

This map was prepared from FEMA's National Flood Hazard Layer (NFHL) with 12/27/2022 3:40 PM and does not include any changes or updates to the NFHL. This map is not a final product and is subject to change or become superseded by new data over time. For additional information, please see the Flood Hazard Mapping Updates Overview Fact Sheet at <https://www.fema.gov/media-library/assets/documents/115418>.

This map complies with FEMA's standards for the use of digital flood maps. If it is not void as described below, the map is not a final product and is subject to change or become superseded by new data over time. The following map elements do not appear: boundary imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date.

**SCALE**



**LEGEND**



**SITE BOUNDARY**

**NATIONAL FLOOD INSURANCE PROGRAM**  
FLOOD INSURANCE RATE MAP

PANEL **756** of **1275**

Panel Contents:  
**COMMUNITY** EL PASO COUNTY  
**CITY OF COLORADO** SPRINGS  
**NUMBER** 080059  
080060  
**PANEL** 0756  
0756



**MAP NUMBER** 080410756G  
**EFFECTIVE DATE** December 07, 2018

1" = 500'



0 250 500 1000

Scale in Feet

**FIRM MAP**





## HYDROLOGIC CALCULATIONS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**EXISTING DRAINAGE CALCULATIONS**  
**(Area Runoff Coefficient Summary)**

BASIN	TOTAL AREA (SF)	TOTAL AREA (Acres)	ROOFS 0.73-0.81 COMMERCIAL AREAS 0.81-0.88 ASPHALT DRIVES 0.90-0.96			LANDSCAPED AREAS 0.16-0.41 GRAVEL STORAGE YARD 0.30-0.50 LIGHT INDUST AREAS 0.59-0.70			PARKS 0.12-0.39 GREENBELTS/AGRI. 0.09-0.36			WEIGHTED	
			AREA (Acres)	C <sub>5</sub>	C <sub>100</sub>	AREA (Acres)	C <sub>5</sub>	C <sub>100</sub>	AREA (Acres)	C <sub>5</sub>	C <sub>100</sub>	C <sub>5</sub>	C <sub>100</sub>
A	8359.8	0.19	0.00	0.90	0.96	0.00	0.16	0.41	0.19	0.09	0.36	0.09	0.36
B	13279.6	0.30	0.00	0.81	0.88	0.00	0.30	0.50	0.30	0.09	0.36	0.09	0.36
C	213471.0	4.90	0.00	0.90	0.96	0.00	0.16	0.41	4.90	0.09	0.36	0.09	0.36
D	9961.3	0.23	0.00	0.90	0.96	0.00	0.16	0.41	0.23	0.09	0.36	0.09	0.36
H1	7641.7	0.18	0.00	0.90	0.96	0.00	0.73	0.81	0.18	0.09	0.36	0.09	0.36
H2	17510.6	0.40	0.00	0.90	0.96	0.00	0.73	0.81	0.40	0.09	0.36	0.09	0.36
H3	1583.1	0.04	0.00	0.90	0.96	0.00	0.73	0.81	0.04	0.09	0.36	0.09	0.36
H4	4363.6	0.10	0.00	0.81	0.88	0.00	0.30	0.50	0.10	0.09	0.36	0.09	0.36
I1	24996.2	0.57	0.33	0.90	0.96	0.21	0.73	0.81	0.03	0.16	0.41	0.80	0.88
I2	21018.4	0.48	0.32	0.90	0.96	0.12	0.73	0.81	0.05	0.16	0.41	0.79	0.87
I3	25471.7	0.58	0.32	0.90	0.96	0.08	0.73	0.81	0.18	0.16	0.41	0.65	0.77
I4	18732.1	0.43	0.28	0.90	0.96	0.11	0.73	0.81	0.03	0.16	0.41	0.80	0.88
I5	10207.0	0.23	0.12	0.90	0.96	0.08	0.73	0.81	0.04	0.16	0.41	0.73	0.83
I6	8155.2	0.19	0.12	0.90	0.96	0.00	0.73	0.81	0.07	0.16	0.41	0.62	0.75
I7	10159.6	0.23	0.19	0.90	0.96	0.00	0.73	0.81	0.04	0.16	0.41	0.77	0.87
J1	33120.0	0.76	0.45	0.90	0.96	0.12	0.73	0.81	0.19	0.16	0.41	0.69	0.80
J2	10980.0	0.25	0.14	0.90	0.96	0.08	0.73	0.81	0.04	0.16	0.41	0.73	0.83
J3	626.0	0.01	0.00	0.90	0.96	0.00	0.73	0.81	0.01	0.16	0.41	0.16	0.41
K1	7398.7	0.17	0.12	0.90	0.96	0.04	0.73	0.81	0.01	0.16	0.41	0.83	0.90
K2	2320.2	0.05	0.01	0.90	0.96	0.04	0.73	0.81	0.00	0.16	0.41	0.72	0.81
K3	6474.8	0.15	0.09	0.90	0.96	0.05	0.73	0.81	0.01	0.16	0.41	0.78	0.87
K4	2266.5	0.05	0.00	0.90	0.96	0.05	0.73	0.81	0.00	0.16	0.41	0.69	0.78
L	57315.2	1.32	0.00	0.90	0.96	0.00	0.73	0.81	1.32	0.09	0.36	0.09	0.36
M1	12396.2	0.28	0.19	0.90	0.96	0.08	0.73	0.81	0.02	0.16	0.41	0.81	0.88
M2	10573.8	0.24	0.00	0.90	0.96	0.20	0.73	0.81	0.05	0.16	0.41	0.62	0.73
M3	15906.8	0.37	0.33	0.90	0.96	0.00	0.73	0.81	0.04	0.16	0.41	0.83	0.91
M4	42578.8	0.98	0.77	0.90	0.96	0.11	0.73	0.81	0.10	0.12	0.39	0.80	0.89
N1	2827.1	0.06	0.06	0.90	0.96	0.00	0.73	0.81	0.00	0.16	0.41	0.90	0.96
N2	18017.7	0.41	0.00	0.90	0.96	0.00	0.30	0.50	0.41	0.12	0.39	0.12	0.39
O1	5318.2	0.12	0.01	0.90	0.96	0.00	0.30	0.50	0.12	0.12	0.41	0.16	0.44
O2	2824.6	0.06	0.01	0.90	0.96	0.00	0.30	0.50	0.06	0.12	0.41	0.22	0.48
P	4961.4	0.11	0.00	0.90	0.96	0.00	0.30	0.50	0.11	0.09	0.36	0.09	0.36

Calculated by: DLM  
Date: 2/20/2023  
Checked by: VAS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**EXISTING DRAINAGE CALCULATIONS**  
**(Area Drainage Summary)**

From Area Runoff Coefficient Summary				OVERLAND				STREET / CHANNEL FLOW				Time of Travel (T <sub>t</sub> )		INTENSITY *		TOTAL FLOWS	
BASIN	AREA TOTAL (Acres)	C <sub>5</sub>	C <sub>100</sub>	C <sub>5</sub>	Length (ft)	Height (ft)	T <sub>c</sub> (min)	Length (ft)	Slope (%)	Velocity (fps)	T <sub>t</sub> (min)	*TOTAL (min)	CHECK (min)	I <sub>5</sub> (in/hr)	I <sub>100</sub> (in/hr)	Q <sub>5</sub> (c.f.s.)	Q <sub>100</sub> (c.f.s.)
		From DCM Table 5-1															
A	0.19	0.09	0.36	0.09	40	5.0	5.0	0	0.0%	0.0	0.0	5.0	10.2	5.2	8.7	0.1	0.6
B	0.30	0.09	0.36	0.09	40	8.0	4.3	0	0.0%	0.0	0.0	4.3	10.2	5.2	8.7	0.1	1.0
C	4.90	0.09	0.36	0.09	100	2.0	14.5	637	1.7%	1.3	8.3	22.8	14.1	3.6	6.1	1.6	10.7
D	0.23	0.09	0.36	0.09	20	0.5	6.0	0	0.0%	0.0	0.0	6.0	10.1	4.9	8.2	0.1	0.7
H1	0.18	0.09	0.36	0.09	76	20.0	5.4	0	0.0%	0.0	0.0	5.4	10.4	5.1	8.5	0.1	0.5
H2	0.40	0.09	0.36	0.09	100	17.0	7.2	0	0.0%	0.0	0.0	7.2	10.6	4.6	7.8	0.2	1.1
H3	0.04	0.09	0.36	0.09	100	17.0	7.2	0	2.0%	1.4	0.0	7.2	10.6	4.6	7.8	0.0	0.1
H4	0.10	0.09	0.36	0.09	100	17.0	7.2	0	0.0%	0.0	0.0	7.2	10.6	4.6	7.8	0.0	0.3
I1	0.57	0.80	0.88	0.80	100	3.0	3.8	216	2.5%	3.2	1.1	5.0	11.8	5.2	8.7	2.4	4.4
I2	0.48	0.79	0.87	0.79	50	2.0	2.5	261	1.0%	2.0	2.2	5.0	11.7	5.2	8.7	2.0	3.6
I3	0.58	0.65	0.77	0.65	67	2.6	4.3	246	0.9%	1.8	2.2	6.5	11.7	4.8	8.0	1.8	3.6
I4	0.43	0.80	0.88	0.80	67	2.6	2.8	246	0.9%	1.8	2.2	5.0	11.7	5.2	8.7	1.8	3.3
I5	0.23	0.73	0.83	0.73	25	0.5	2.6	146	1.4%	2.4	1.0	5.0	11.0	5.2	8.7	0.9	1.7
I6	0.19	0.62	0.75	0.62	31	0.3	4.8	120	1.3%	2.3	0.9	5.7	10.8	5.0	8.3	0.6	1.2
I7	0.23	0.77	0.87	0.77	50	0.3	5.2	133	1.1%	2.1	1.1	6.2	11.0	4.8	8.1	0.9	1.6
J1	0.76	0.69	0.80	0.69	85	3.0	4.5	327	0.9%	1.9	2.8	7.4	12.3	4.6	7.7	2.4	4.7
J2	0.25	0.73	0.83	0.73	25	0.5	2.6	185	1.4%	2.3	1.3	5.0	11.2	5.2	8.7	1.0	1.8
J3	0.01	0.16	0.41	0.16	10	1.0	2.6	0	0.0%	0.0	0.0	5.0	10.1	5.2	8.7	0.0	0.1
K1	0.17	0.83	0.90	0.83	25	0.5	2.0	115	3.0%	3.5	0.5	5.0	10.8	5.2	8.7	0.7	1.3
K2	0.05	0.72	0.81	0.72	25	0.5	2.7	55	1.8%	2.7	0.3	5.0	10.4	5.2	8.7	0.2	0.4
K3	0.15	0.78	0.87	0.78	25	0.5	2.3	120	1.4%	2.4	0.8	5.0	10.8	5.2	8.7	0.6	1.1
K4	0.05	0.69	0.78	0.69	25	0.5	3.0	91	1.0%	2.0	0.8	5.0	10.6	5.2	8.7	0.2	0.4
L	1.32	0.09	0.36	0.09	100	17.0	7.2	0	0.0%	0.0	0.0	7.2	10.6	4.6	7.8	0.5	3.7
M1	0.28	0.81	0.88	0.81	25	0.5	2.1	203	1.0%	2.0	1.7	5.0	11.3	5.2	8.7	1.2	2.2
M2	0.24	0.62	0.73	0.62	25	0.5	3.5	148	1.0%	1.5	1.6	5.1	11.0	5.1	8.6	0.8	1.5
M3	0.37	0.83	0.91	0.83	50	2.0	2.2	112	2.5%	3.2	0.6	5.0	10.9	5.2	8.7	1.6	2.9
M4	0.98	0.80	0.89	0.80	100	1.0	5.3	326	1.2%	2.2	2.4	7.8	12.4	4.5	7.6	3.5	6.6
N1	0.06	0.90	0.96	0.90	50	1.0	2.0	0	0.0%	0.0	0.0	5.0	10.3	5.2	8.7	0.3	0.5
N2	0.41	0.12	0.39	0.12	60	1.2	10.9	30	33.0%	11.5	0.0	10.9	10.5	4.1	6.8	0.2	1.1
O1	0.12	0.16	0.44	0.16	32	0.5	8.3	0	0.0%	0.0	0.0	8.3	10.2	4.4	7.4	0.1	0.4
O2	0.06	0.22	0.48	0.22	25	0.5	6.3	0	0.0%	0.0	0.0	6.3	10.1	4.8	8.1	0.1	0.3
P	0.11	0.09	0.36	0.09	25	0.5	7.1	0	0.0%	0.0	0.0	7.1	10.1	4.6	7.8	0.0	0.3

\* Intensity equations assume a minimum travel time of 5 minutes.

Calculated by: DLM  
Date: 2/20/2023  
Checked by: VAS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**EXISTING DRAINAGE CALCULATIONS**  
**(Basin Routing Summary)**

From Area Runoff Coefficient Summary				OVERLAND			PIPE / CHANNEL FLOW				Time of Travel (T <sub>t</sub> )	INTENSITY *		TOTAL FLOWS		COMMENTS		
DESIGN POINT	CONTRIBUTING BASINS DPS AND/OR PIPES	CA <sub>5</sub>	CA <sub>100</sub>	C <sub>s</sub>	Length (ft)	Height (ft)	T <sub>c</sub> (min)	Length (ft)	Slope (%)	Velocity (fps)	T <sub>t</sub> (min)	*TOTAL (min)	I <sub>5</sub> (in/hr)	I <sub>100</sub> (in/hr)	Q <sub>5</sub> (c.f.s.)		Q <sub>100</sub> (c.f.s.)	
1	A, B, C	0.49	1.94		Basin C Tc used								14.1	3.6	6.1	1.8	11.8	Exist PVT 24" Storm Sewer
2					NOT USED													
3	H1, I1	0.47	0.57		Basin H1 Tc used + Basin I1 routing								7.1	4.6	7.8	2.2	4.4	Existing Curb and Gutter
							5.4	316	2.1%	2.9	1.7							
4	H2, I2	0.42	0.56		Basin H2 Tc used + Basin I2 routing								8.9	4.3	7.2	1.8	4.1	Existing Curb and Gutter
							7.2	235	2.8%	3.3	1.7							
5	H3, I7	0.18	0.22		Basin H1 Tc used + Basin I1 routing								8.6	4.4	7.3	0.8	1.6	Existing Curb and Gutter
							7.2	183	1.1%	2.1	1.5							
6	DP3, DP4, DP5 I3, I4, I5, I6	2.09	2.51		Basin H3 Tc used + Basin I7 Routing								11.5	3.9	6.6	8.2	16.5	2-Exist 15' CDOT Type R Inlet
		1.04	1.25				7.2	520	1.0%	2.0	4.3					4.1	8.3	(assumed split flows 100-yr)
7	FB INLET 3, J1	0.52	0.97		Basin J1 Tc Used								7.4	4.6	7.7	2.4	7.5	Exist 15' CDOT Type R Inlet
8	FB INLET 4, J2, J3	0.18	0.47		Basin J2 Tc Used								5.0	5.2	8.7	0.9	4.1	Exist 15' CDOT Type R Inlet
9	H4, L, M4	0.91	1.38		Basin L Tc used + Basin M4 Routing								9.6	4.2	7.0	3.8	9.7	Existing Pvt Swale
							7.2	326	1.2%	2.2	2.4							
10	DP9, M2, M3	1.37	1.88		Basin DP9 Tc used + Basin M3 Routing								11.7	3.9	6.5	5.3	12.3	Existing Pvt Swale/Concrete Riprap Rundown
							9.6	125	1.0%	1.0	2.1							
11	M1, K4	0.27	0.29		Basin M1 Tc Used								5.0	5.2	8.7	1.4	2.5	Existing Conc. Rock Rundown
12	K2, K3, N1	0.21	0.23		Basin K3 Tc Used								5.0	5.2	8.7	1.1	2.0	Existing Conc. Rock Rundown
13	K1	0.14	0.15		Basin K1 Tc Used								5.0	5.2	8.7	0.7	1.3	Existing Inlet
14	DP10, DP11, DP12 DP13, N2, PR14, PR17	4.96	6.72		DP10 Tc Used								11.7	3.9	6.5	19.3	43.9	Existing Sand Filter FSD Pond 2

\* Intensity equations assume a minimum travel time of 5 minutes.

Calculated by: DLM  
Date: 2/20/2023  
Checked by: VAS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**EXISTING DRAINAGE CALCULATIONS**  
**(Storm Sewer Routing Summary)**

PIPE RUN	Contributing Pipes/Design Points	Equivalent $CA_5$	Equivalent $CA_{100}$	Maximum $T_C$	Intensity*		Flow		Pipe Size
					$I_5$	$I_{100}$	$Q_5$	$Q_{100}$	
11	DP1	0.49	1.94	14.1	3.6	6.1	1.8	11.8	EX 24" PP
12	PR11	0.49	1.94	14.1	3.6	6.1	1.8	11.8	EX 24" PP
13	INLET 3	1.05	1.20	11.5	3.9	6.6	4.1	7.9	EX 15" PP
14	PR13, INLET 4	2.09	2.42	11.5	3.9	6.6	8.2	15.9	EX 24" PP
15	INLET 5	0.52	0.95	7.4	4.6	7.7	2.4	7.3	EX 18" PP
16	PR15, INLET 6	0.70	1.42	7.4	4.6	7.7	3.2	11.0	EX 24" PP
17	PR16, DP13	0.84	1.57	7.4	4.6	7.7	3.9	12.1	EX 24" PP
18	POND 2 OUTFALL	5.52	5.75	30.0	2.5	4.2	13.7	23.9	EX 30" PP
19	PR12, PR18	6.01	7.69	22.0	2.9	4.9	17.7	38.0	EX 24" PP

\* Intensity equations assume a minimum travel time of 5 minutes.

DP - Design Point  
PR - Pipe Run

FB- Flow By from Design Point  
INT- Intercepted Flow from Design Point

Calculated by: DLM  
Date: 2/20/2023  
Checked by: VAS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**PROPOSED DRAINAGE CALCULATIONS**  
**(Area Runoff Coefficient Summary)**

			ROOFS 0.73-0.81 COMMERCIAL AREAS 0.81-0.88 ASPHALT DRIVES 0.90-0.96				LANDSCAPED AREAS 0.16-0.41 GRAVEL STORAGE YARD 0.30-0.50 LIGHT INDUST AREAS 0.59-0.70				PARKS 0.12-0.39 GREENBELTS/AGRI. 0.09-0.36				WEIGHTED		
BASIN	TOTAL AREA (SF)	TOTAL AREA (Acres)	AREA (Acres)	C <sub>2</sub>	C <sub>5</sub>	C <sub>100</sub>	AREA (Acres)	C <sub>2</sub>	C <sub>5</sub>	C <sub>100</sub>	AREA (Acres)	C <sub>2</sub>	C <sub>5</sub>	C <sub>100</sub>	C <sub>2</sub>	C <sub>5</sub>	C <sub>100</sub>
A	9300.8	0.21	0.00	0.89	0.90	0.96	0.00	0.07	0.16	0.41	0.21	0.03	0.09	0.36	0.03	0.09	0.36
B	65284.4	1.50	1.50	0.79	0.81	0.88	0.00	0.23	0.30	0.50	0.00	0.05	0.12	0.39	0.79	0.81	0.88
C	5372.3	0.12	0.00	0.89	0.90	0.96	0.00	0.07	0.16	0.41	0.12	0.03	0.09	0.36	0.03	0.09	0.36
CI	7457.3	0.17	0.00	0.89	0.90	0.96	0.00	0.07	0.16	0.41	0.17	0.03	0.09	0.36	0.03	0.09	0.36
D	33587.9	0.77	0.77	0.79	0.81	0.88	0.00	0.23	0.30	0.50	0.00	0.05	0.12	0.39	0.79	0.81	0.88
DI	34028.4	0.78	0.78	0.79	0.81	0.88	0.00	0.23	0.30	0.50	0.00	0.05	0.12	0.39	0.79	0.81	0.88
E1	11683.7	0.27	0.22	0.89	0.90	0.96	0.05	0.79	0.81	0.88	0.00	0.05	0.12	0.39	0.87	0.88	0.95
E2	9082.0	0.21	0.17	0.89	0.90	0.96	0.04	0.79	0.81	0.88	0.00	0.05	0.12	0.39	0.87	0.88	0.95
F	12955.1	0.30	0.30	0.79	0.81	0.88	0.00	0.07	0.16	0.41	0.00	0.05	0.12	0.39	0.79	0.81	0.88
G1	11586.1	0.27	0.06	0.89	0.90	0.96	0.00	0.57	0.59	0.70	0.21	0.05	0.12	0.39	0.25	0.30	0.52
G2	50180.3	1.15	0.00	0.89	0.90	0.96	1.15	0.79	0.81	0.88	0.00	0.03	0.09	0.36	0.79	0.81	0.88
H1	7154.6	0.16	0.00	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.16	0.03	0.09	0.36	0.03	0.09	0.36
H2	17510.6	0.40	0.00	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.40	0.03	0.09	0.36	0.03	0.09	0.36
H3	1583.1	0.04	0.00	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.04	0.03	0.09	0.36	0.03	0.09	0.36
H4	4363.6	0.10	0.00	0.79	0.81	0.88	0.00	0.23	0.30	0.50	0.10	0.03	0.09	0.36	0.03	0.09	0.36
I1	23800.3	0.55	0.33	0.89	0.90	0.96	0.21	0.71	0.73	0.81	0.00	0.07	0.16	0.41	0.82	0.83	0.90
I2	21018.4	0.48	0.32	0.89	0.90	0.96	0.12	0.71	0.73	0.81	0.05	0.07	0.16	0.41	0.77	0.79	0.87
I3	19407.4	0.45	0.31	0.89	0.90	0.96	0.08	0.71	0.73	0.81	0.05	0.07	0.16	0.41	0.76	0.78	0.87
I4	23928.1	0.55	0.40	0.89	0.90	0.96	0.11	0.71	0.73	0.81	0.04	0.07	0.16	0.41	0.80	0.81	0.89
I5	10207.0	0.23	0.12	0.89	0.90	0.96	0.08	0.71	0.73	0.81	0.04	0.07	0.16	0.41	0.71	0.73	0.83
I6	8155.2	0.19	0.12	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.07	0.07	0.16	0.41	0.58	0.62	0.75
I7	10159.6	0.23	0.19	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.04	0.07	0.16	0.41	0.75	0.77	0.87
J1	30237.3	0.69	0.52	0.89	0.90	0.96	0.12	0.71	0.73	0.81	0.06	0.07	0.16	0.41	0.79	0.81	0.89
J2	10980.0	0.25	0.14	0.89	0.90	0.96	0.08	0.71	0.73	0.81	0.04	0.07	0.16	0.41	0.71	0.73	0.83
J3	626.0	0.01	0.00	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.01	0.07	0.16	0.41	0.07	0.16	0.41
K1	7398.7	0.17	0.12	0.89	0.90	0.96	0.04	0.71	0.73	0.81	0.01	0.07	0.16	0.41	0.81	0.83	0.90
K2	2320.2	0.05	0.01	0.89	0.90	0.96	0.04	0.71	0.73	0.81	0.00	0.07	0.16	0.41	0.70	0.72	0.81
K3	6474.8	0.15	0.09	0.89	0.90	0.96	0.05	0.71	0.73	0.81	0.01	0.07	0.16	0.41	0.76	0.78	0.87
K4	2266.5	0.05	0.00	0.89	0.90	0.96	0.05	0.71	0.73	0.81	0.00	0.07	0.16	0.41	0.66	0.69	0.78
L	57315.2	1.32	0.00	0.89	0.90	0.96	0.00	0.71	0.73	0.81	1.32	0.03	0.09	0.36	0.03	0.09	0.36
M1	12396.2	0.28	0.19	0.89	0.90	0.96	0.08	0.71	0.73	0.81	0.02	0.07	0.16	0.41	0.79	0.81	0.88
M2	10573.8	0.24	0.00	0.89	0.90	0.96	0.20	0.71	0.73	0.81	0.05	0.07	0.16	0.41	0.58	0.62	0.73
M3	15906.8	0.37	0.33	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.04	0.07	0.16	0.41	0.81	0.83	0.91
M4	42578.8	0.98	0.77	0.89	0.90	0.96	0.11	0.71	0.73	0.81	0.10	0.05	0.12	0.39	0.79	0.80	0.89
N1	2827.1	0.06	0.06	0.89	0.90	0.96	0.00	0.71	0.73	0.81	0.00	0.07	0.16	0.41	0.89	0.90	0.96
N2	18017.7	0.41	0.00	0.89	0.90	0.96	0.00	0.23	0.30	0.50	0.41	0.05	0.12	0.39	0.05	0.12	0.39
O1	5318.2	0.12	0.01	0.89	0.90	0.96	0.00	0.23	0.30	0.50	0.12	0.05	0.12	0.41	0.10	0.16	0.44
O2	2824.6	0.06	0.01	0.89	0.90	0.96	0.00	0.23	0.30	0.50	0.06	0.05	0.12	0.41	0.16	0.22	0.48
P	4961.4	0.11	0.00	0.89	0.90	0.96	0.00	0.23	0.30	0.50	0.11	0.03	0.09	0.36	0.03	0.09	0.36

Calculated by: DLM  
Date: 2/20/2023  
Checked by: VAS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**PROPOSED DRAINAGE CALCULATIONS**  
**(Area Drainage Summary)**

From Area Runoff Coefficient Summary					OVERLAND				STREET / CHANNEL FLOW				Time of Travel (T <sub>t</sub> )		INTENSITY *			TOTAL FLOWS			
BASIN	AREA TOTAL (Acres)	C <sub>2</sub>	C <sub>5</sub>	C <sub>100</sub>	C <sub>5</sub>	Length (ft)	Height (ft)	T <sub>c</sub> (min)	Length (ft)	Slope (%)	Velocity (fps)	T <sub>t</sub> (min)	*TOTAL (min)	CHECK (min)	I <sub>2</sub> (in/hr)	I <sub>5</sub> (in/hr)	I <sub>100</sub> (in/hr)	Q <sub>2</sub> (c.f.s.)	Q <sub>5</sub> (c.f.s.)	Q <sub>100</sub> (c.f.s.)	
		From DCM Table 3-1																			
A	0.21	0.03	0.09	0.36	0.09	40	5.0	5.0	0	0.0%	0.0	0.0	5.0	10.2	4.1	5.2	8.7	0.0	0.1	0.7	
B	1.50	0.79	0.81	0.88	0.81	80	1.0	4.4	240	1.7%	2.6	1.5	5.9	11.8	3.9	4.9	8.3	4.6	6.0	10.9	
C	0.12	0.03	0.09	0.36	0.09	40	16.0	3.4	0	0.0%	0.0	0.0	5.0	10.2	4.1	5.2	8.7	0.0	0.1	0.4	
CI	0.17	0.03	0.09	0.36	0.09	60	22.0	4.3	0	0.0%	0.0	0.0	5.0	10.3	4.1	5.2	8.7	0.0	0.1	0.5	
D	0.77	0.79	0.81	0.88	0.81	60	1.2	3.2	250	1.6%	2.5	1.6	5.0	11.7	4.1	5.2	8.7	2.5	3.2	5.9	
D1	0.78	0.79	0.81	0.88	0.81	60	1.2	3.2	250	1.6%	2.5	1.6	5.0	11.7	4.1	5.2	8.7	2.5	3.3	6.0	
E1	0.27	0.87	0.88	0.95	0.88	30	0.6	1.7	280	2.0%	2.8	1.7	5.0	11.7	4.1	5.2	8.7	1.0	1.2	2.2	
E2	0.21	0.87	0.88	0.95	0.88	30	0.6	1.7	280	2.0%	2.8	1.7	5.0	11.7	4.1	5.2	8.7	0.7	1.0	1.7	
F	0.30	0.79	0.81	0.88	0.81	60	1.2	3.2	150	1.3%	2.3	1.1	5.0	11.2	4.1	5.2	8.7	1.0	1.2	2.3	
G1	0.27	0.25	0.30	0.52	0.30	30	1.0	5.3	0	0.0%	0.0	0.0	5.3	10.2	4.1	5.1	8.5	0.3	0.4	1.2	
G2	1.15	0.79	0.81	0.88	0.81	60	0.6	4.1	400	1.0%	2.0	3.3	7.4	12.6	3.7	4.6	7.7	3.3	4.3	7.8	
H1	0.16	0.03	0.09	0.36	0.09	76	20.0	5.4	0	0.0%	0.0	0.0	5.4	10.4	4.0	5.1	8.5	0.0	0.1	0.5	
H2	0.40	0.03	0.09	0.36	0.09	100	17.0	7.2	0	0.0%	0.0	0.0	7.2	10.6	3.7	4.6	7.8	0.0	0.2	1.1	
H3	0.04	0.03	0.09	0.36	0.09	100	17.0	7.2	0	2.0%	1.4	0.0	7.2	10.6	3.7	4.6	7.8	0.0	0.0	0.1	
H4	0.10	0.03	0.09	0.36	0.09	100	17.0	7.2	0	0.0%	0.0	0.0	7.2	10.6	3.7	4.6	7.8	0.0	0.0	0.3	
I1	0.55	0.82	0.83	0.90	0.83	100	3.0	3.4	216	2.5%	3.2	1.1	5.0	11.8	4.1	5.2	8.7	1.8	2.3	4.3	
I2	0.48	0.77	0.79	0.87	0.79	50	2.0	2.5	261	1.0%	2.0	2.2	5.0	11.7	4.1	5.2	8.7	1.5	2.0	3.6	
I3	0.45	0.76	0.78	0.87	0.78	67	2.6	3.0	246	0.9%	1.8	2.2	5.2	11.7	4.1	5.1	8.6	1.4	1.8	3.3	
I4	0.55	0.80	0.81	0.89	0.81	67	2.6	2.7	246	0.9%	1.8	2.2	5.0	11.7	4.1	5.2	8.7	1.8	2.3	4.2	
I5	0.23	0.71	0.73	0.83	0.73	25	0.5	2.6	146	1.4%	2.4	1.0	5.0	11.0	4.1	5.2	8.7	0.7	0.9	1.7	
I6	0.19	0.58	0.62	0.75	0.62	31	0.3	4.8	120	1.3%	2.3	0.9	5.7	10.8	4.0	5.0	8.3	0.4	0.6	1.2	
I7	0.23	0.75	0.77	0.87	0.77	50	0.3	5.2	133	1.1%	2.1	1.1	6.2	11.0	3.9	4.8	8.1	0.7	0.9	1.6	
J1	0.69	0.79	0.81	0.89	0.81	85	3.0	3.2	327	0.9%	1.9	2.8	6.1	12.3	3.9	4.9	8.2	2.1	2.7	5.1	
J2	0.25	0.71	0.73	0.83	0.73	25	0.5	2.6	185	1.4%	2.3	1.3	5.0	11.2	4.1	5.2	8.7	0.7	1.0	1.8	
J3	0.01	0.07	0.16	0.41	0.16	10	1.0	2.6	0	0.0%	0.0	0.0	5.0	10.1	4.1	5.2	8.7	0.0	0.0	0.1	
K1	0.17	0.81	0.83	0.90	0.83	25	0.5	2.0	115	3.0%	3.5	0.5	5.0	10.8	4.1	5.2	8.7	0.6	0.7	1.3	
K2	0.05	0.70	0.72	0.81	0.72	25	0.5	2.7	55	1.8%	2.7	0.3	5.0	10.4	4.1	5.2	8.7	0.2	0.2	0.4	
K3	0.15	0.76	0.78	0.87	0.78	25	0.5	2.3	120	1.4%	2.4	0.8	5.0	10.8	4.1	5.2	8.7	0.5	0.6	1.1	
K4	0.05	0.66	0.69	0.78	0.69	25	0.5	3.0	91	1.0%	2.0	0.8	5.0	10.6	4.1	5.2	8.7	0.1	0.2	0.4	
L	1.32	0.03	0.09	0.36	0.09	100	17.0	7.2	0	0.0%	0.0	0.0	7.2	10.6	3.7	4.6	7.8	0.1	0.5	3.7	
M1	0.28	0.79	0.81	0.88	0.81	25	0.5	2.1	203	1.0%	2.0	1.7	5.0	11.3	4.1	5.2	8.7	0.9	1.2	2.2	
M2	0.24	0.58	0.62	0.73	0.62	25	0.5	3.5	148	1.0%	1.5	1.6	5.1	11.0	4.1	5.1	8.6	0.6	0.8	1.5	
M3	0.37	0.81	0.83	0.91	0.83	50	2.0	2.2	112	2.5%	3.2	0.6	5.0	10.9	4.1	5.2	8.7	1.2	1.6	2.9	
M4	0.98	0.79	0.80	0.89	0.80	100	1.0	5.3	326	1.2%	2.2	2.4	7.8	12.4	3.6	4.5	7.6	2.8	3.5	6.6	
N1	0.06	0.89	0.90	0.96	0.90	50	1.0	2.0	0	0.0%	0.0	0.0	5.0	10.3	4.1	5.2	8.7	0.2	0.3	0.5	
N2	0.41	0.05	0.12	0.39	0.12	60	1.2	10.9	30	33.0%	11.5	0.0	10.9	10.5	3.2	4.1	6.8	0.1	0.2	1.1	
O1	0.12	0.10	0.16	0.44	0.16	32	0.5	8.3	0	0.0%	0.0	0.0	8.3	10.2	3.5	4.4	7.4	0.0	0.1	0.4	
O2	0.06	0.16	0.22	0.48	0.22	25	0.5	6.3	0	0.0%	0.0	0.0	6.3	10.1	3.8	4.8	8.1	0.0	0.1	0.3	
P	0.11	0.03	0.09	0.36	0.09	25	0.5	7.1	0	0.0%	0.0	0.0	7.1	10.1	3.7	4.6	7.8	0.0	0.0	0.3	

\* Intensity equations assume a minimum travel time of 5 minutes.

Calculated by: DLM  
Date: 2/20/2023  
Checked by: VAS

**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**PROPOSED DRAINAGE CALCULATIONS**  
**(Basin Routing Summary)**

DESIGN POINT	CONTRIBUTING BASINS DPS AND/OR PIPES	From Area Runoff Coefficient Summary			OVERLAND				PIPE / CHANNEL FLOW				Time of Travel (T <sub>t</sub> ) *TOTAL (min)	INTENSITY*			TOTAL FLOWS			COMMENTS
		CA <sub>2</sub>	CA <sub>4</sub>	CA <sub>100</sub>	C <sub>s</sub>	Length (ft)	Height (ft)	T <sub>c</sub> (min)	Length (ft)	Slope (%)	Velocity (fps)	T <sub>t</sub> (min)		I <sub>2</sub> (in/hr)	I <sub>5</sub> (in/hr)	I <sub>100</sub> (in/hr)	Q <sub>2</sub> (c.f.s.)	Q <sub>5</sub> (c.f.s.)	Q <sub>100</sub> (c.f.s.)	
1	A, B	1.19	1.23	1.40				5.0	240	1.7%	2.6	1.5	6.6	3.8	4.8	8.0	4.5	5.9	11.2	Proposed PVT 18" Storm Sewer
2	C, D	0.61	0.64	0.72				5.0	250	1.6%	2.5	1.6	6.6	3.8	4.7	8.0	2.3	3.0	5.8	Proposed PVT 15" Storm Sewer
3	F	0.23	0.24	0.26									5.0	4.1	5.2	8.7	1.0	1.2	2.3	Proposed PVT 15" Storm Sewer
4	E2	0.18	0.18	0.20									5.0	4.1	5.2	8.7	0.7	1.0	1.7	Proposed 5" Type R Sump Inlet
5	E1	0.23	0.24	0.25									5.0	4.1	5.2	8.7	1.0	1.2	2.2	Proposed 5" Type R Sump Inlet
6	C1, D1, PR6	1.04	1.07	1.20				5.0	250	1.6%	2.5	1.6	6.6	3.8	4.7	8.0	3.9	5.1	9.6	Exist PVT 24" Storm Sewer
7	G2	0.91	0.93	1.01									5.3	4.1	5.1	8.5	3.7	4.7	8.7	Existing Curb and Gutter
8	H1, I1	0.45	0.47	0.55				5.4	316	2.1%	2.9	1.7	7.1	3.7	4.6	7.8	1.7	2.2	4.3	Existing Curb and Gutter
9	H2, I2	0.38	0.42	0.56				7.2	235	2.8%	3.3	1.7	8.9	3.4	4.3	7.2	1.3	1.8	4.1	Existing Curb and Gutter
10	H3, I7	0.18	0.18	0.22				7.2	183	1.1%	2.1	1.5	8.6	3.5	4.4	7.3	0.6	0.8	1.6	Existing Curb and Gutter
11	DP3, DP4, DP5 I3, I4, I5, I6	2.06	2.15	2.54				7.2	520	1.0%	2.0	4.3	11.5	3.1	3.9	6.6	6.5	8.4	16.7	2-Exist 15" CDOT Type R Inlet
12	FB INLET 3, J1	1.03	1.08	1.27									6.1	3.9	4.9	8.2	3.2	4.2	8.4	(assumed split flows 100-yr) Exist 15" CDOT Type R Inlet
13	FB INLET 4, J2, J3	0.55	0.58	0.98									5.0	4.1	5.2	8.7	2.1	2.8	8.1	Exist 15" CDOT Type R Inlet
14	H4, L, M4	0.18	0.19	0.58									5.0	4.1	5.2	8.7	0.7	1.0	5.0	Exist 15" CDOT Type R Inlet
15	DP14 DP9, M2, M3	0.81	0.91	1.38				7.2	326	1.2%	2.2	2.4	9.6	3.3	4.2	7.0	2.7	3.8	9.7	Existing Pnt Swale
16	M1, K4	1.25	1.37	1.88				9.6	125	1.0%	1.0	2.1	11.7	3.1	3.9	6.5	3.9	5.3	12.3	Existing Pnt Swale/Concrete Riprap Rounddown
17	K2, K3, N1	0.26	0.27	0.29									5.0	4.1	5.2	8.7	1.1	1.4	2.5	Existing Conc. Rock Rounddown
18	K1	0.21	0.21	0.23									5.0	4.1	5.2	8.7	0.9	1.1	2.0	Existing Conc. Rock Rounddown
19	DP10, DP11, DP12 DP13, N2, PR14, PR17	0.14	0.14	0.15									5.0	4.1	5.2	8.7	0.6	0.7	1.3	Existing Inlet
		2.74	5.09	6.84									11.7	3.1	3.9	6.5	8.5	19.8	44.7	Existing Sand Filter FSD Pond 2

\* Intensity equations assume a minimum travel time of 5 minutes.

Calculated by: DLM  
 Date: 2/20/2023  
 Checked by: VAS

DP15 thru 18 instead of 10 thru 13



**FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2**  
**PROPOSED DRAINAGE CALCULATIONS**  
**(Storm Sewer Routing Summary)**

PIPE RUN	Contributing Pipes/Design Points	Equivalent CA <sub>5</sub>	Equivalent CA <sub>100</sub>	Maximum T <sub>C</sub>	Intensity*		Flow		Pipe Size
					I <sub>5</sub>	I <sub>100</sub>	Q <sub>5</sub>	Q <sub>100</sub>	
1	FUTURE POND 1 OUTFALL	0.98	1.37	30.0	2.5	4.2	2.4	5.7	PROP 18" PP
2	FUTURE POND 2 OUTFALL	0.42	0.58	30.0	2.5	4.2	1.0	2.4	PROP 18" PP
3	FUTURE POND 4 OUTFALL	0.18	0.24	30.0	2.5	4.2	0.4	1.0	PROP 18" PP
4	PR1, PR2, PR3	1.58	2.19	30.0	2.5	4.2	3.9	9.1	PROP 24" PP
5	DP4	0.18	0.20	5.0	5.2	8.7	1.0	1.7	PROP 24" PP
6	PR5, DP5	0.42	0.45	5.0	5.2	8.7	2.2	3.9	PROP 18" PP
6A	C1 90%D1	0.56	0.58	5.0	5.2	8.7	2.9	5.1	PROP 18" PP
7	POND 3 OUTFALL	0.78	0.96	30.0	2.5	4.2	1.9	4.0	PROP 24" PP
8	PR4, PR7	2.36	3.15	30.0	2.5	4.2	5.9	13.1	PROP 18" PP
9	FUTURE POND 5 OUTFALL	0.52	0.73	30.0	2.5	4.2	1.3	3.0	PROP 24" PP
10	PR8, PR9	2.88	3.88	30.0	2.5	4.2	7.1	16.2	PROP 24" PP
11	PR10	2.88	3.88	30.0	2.5	4.2	7.1	16.2	EX 24" PP
12	PR11	2.88	3.88	30.0	2.5	4.2	7.1	16.2	EX 24" PP
13	INLET 3	1.07	1.22	11.5	3.9	6.6	4.2	8.0	PROP 15" PP
14	PR13, INLET 4	2.15	2.43	11.5	3.9	6.6	8.4	16.0	PROP 24" PP
15	INLET 5	0.58	0.95	6.1	4.9	8.2	2.8	7.8	PROP 24" PP
16	PR15, INLET 6	0.77	1.53	6.1	4.9	8.2	3.7	12.6	PROP 18" PP
17	PR16, DP18	0.91	1.69	6.1	4.9	8.2	4.4	13.8	EXIST 24" PP
18	POND 2 OUTFALL	5.52	5.72	30.0	2.5	4.2	13.7	23.8	EXIST 24" PP
19	PR18, PR12	8.40	9.60	30.0	2.5	4.2	20.8	40.0	EXIST 42" RCP

\* Intensity equations assume a minimum travel time of 5 minutes.

DP - Design Point  
PR - Pipe Run

FB- Flow By from Design Point  
INT- Intercepted Flow from Design Point

Calculated by: DLM

Date: 2/20/2023

Checked by: VAS

\*\*Existing undeveloped

\*\*\*Ultimate build out, developed. Used to size future pond 1 and storm sewer.


## HYDRAULIC CALCULATIONS / SFB WQCV CALCULATIONS

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing No. 2 (Existing Conditions)**


Inlet ID: **Inlet 3 DP 6 (North)**



<b>Gutter Geometry:</b>					
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft				
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft				
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$				
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches				
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft				
Gutter Width	$W = 2.00$ ft				
Street Transverse Slope	$S_x = 0.020$ ft/ft				
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft				
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.012$ ft/ft				
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.015$				
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> </tr> <tr> <td>15.8</td> <td>17.0</td> </tr> </table> ft	Minor Storm	Major Storm	15.8	17.0
Minor Storm	Major Storm				
15.8	17.0				
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> </tr> <tr> <td>4.6</td> <td>7.8</td> </tr> </table> inches	Minor Storm	Major Storm	4.6	7.8
Minor Storm	Major Storm				
4.6	7.8				
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> </tr> <tr> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>	Minor Storm	Major Storm	<input type="checkbox"/>	<input type="checkbox"/>
Minor Storm	Major Storm				
<input type="checkbox"/>	<input type="checkbox"/>				
MINOR STORM Allowable Capacity is based on Depth Criterion					
MAJOR STORM Allowable Capacity is based on Spread Criterion					
Minor storm max. allowable capacity GOOD - greater than the design peak flow of 4.10 cfs on sheet 'Inlet Management'					
Major storm max. allowable capacity GOOD - greater than the design peak flow of 8.30 cfs on sheet 'Inlet Management'					
	<table border="1"> <tr> <th>Minor Storm</th> <th>Major Storm</th> </tr> <tr> <td>6.5</td> <td>12.7</td> </tr> </table> cfs	Minor Storm	Major Storm	6.5	12.7
Minor Storm	Major Storm				
6.5	12.7				

## INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - $Q < \text{Allowable Street Capacity}$			
Total Inlet Interception Capacity	4.1	7.9	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	0.4	cfs
Capture Percentage = $Q_i/Q_n$	100	96	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing No. 2 (Existing Conditions)**


Inlet ID: **Inlet 4 DP6 (South)**



<b>Gutter Geometry:</b>										
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft									
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft									
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$									
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches									
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft									
Gutter Width	$W = 2.00$ ft									
Street Transverse Slope	$S_x = 0.020$ ft/ft									
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft									
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.011$ ft/ft									
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$									
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> </tr> <tr> <td><math>T_{MAX}</math></td> <td>15.8</td> <td>17.0</td> </tr> <tr> <td><math>d_{MAX}</math></td> <td>4.6</td> <td>7.8</td> </tr> </table>		Minor Storm	Major Storm	$T_{MAX}$	15.8	17.0	$d_{MAX}$	4.6	7.8
	Minor Storm	Major Storm								
$T_{MAX}$	15.8	17.0								
$d_{MAX}$	4.6	7.8								
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm										
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<table border="1"> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> </tr> <tr> <td><math>Q_{allow}</math></td> <td>5.8</td> <td>11.4</td> </tr> </table>		Minor Storm	Major Storm	$Q_{allow}$	5.8	11.4			
	Minor Storm	Major Storm								
$Q_{allow}$	5.8	11.4								
<p>MINOR STORM Allowable Capacity is based on Depth Criterion</p> <p>MAJOR STORM Allowable Capacity is based on Spread Criterion</p> <p><b>Minor storm max. allowable capacity GOOD - greater than the design peak flow of 4.10 cfs on sheet 'Inlet Management'</b></p> <p><b>Major storm max. allowable capacity GOOD - greater than the design peak flow of 8.30 cfs on sheet 'Inlet Management'</b></p>										

# INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - $Q < \text{Allowable Street Capacity}$			
Total Inlet Interception Capacity	4.1	8.0	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	0.3	cfs
Capture Percentage = $Q_i/Q_n$	100	96	%

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing No. 2 (Existing Conditions)**


Inlet ID: **Inlet 5 DP7 (North)**



<b>Gutter Geometry:</b>									
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft								
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft								
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$								
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches								
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft								
Gutter Width	$W = 2.00$ ft								
Street Transverse Slope	$S_x = 0.020$ ft/ft								
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft								
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.010$ ft/ft								
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.015$								
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>ft</td> </tr> <tr> <td><math>T_{MAX} =</math></td> <td>15.8</td> <td>17.0</td> <td></td> </tr> </table>		Minor Storm	Major Storm	ft	$T_{MAX} =$	15.8	17.0	
	Minor Storm	Major Storm	ft						
$T_{MAX} =$	15.8	17.0							
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>inches</td> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>4.6</td> <td>7.8</td> <td></td> </tr> </table>		Minor Storm	Major Storm	inches	$d_{MAX} =$	4.6	7.8	
	Minor Storm	Major Storm	inches						
$d_{MAX} =$	4.6	7.8							
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>		Minor Storm	Major Storm	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	Minor Storm	Major Storm							
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>							
MINOR STORM Allowable Capacity is based on Depth Criterion									
MAJOR STORM Allowable Capacity is based on Spread Criterion									
<b>Minor storm max. allowable capacity GOOD - greater than the design peak flow of 2.40 cfs on sheet 'Inlet Management'</b>									
<b>Major storm max. allowable capacity GOOD - greater than the design peak flow of 7.50 cfs on sheet 'Inlet Management'</b>									
$Q_{allow} =$	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>cfs</td> </tr> <tr> <td></td> <td>5.9</td> <td>11.6</td> <td></td> </tr> </table>		Minor Storm	Major Storm	cfs		5.9	11.6	
	Minor Storm	Major Storm	cfs						
	5.9	11.6							

# INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)



Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - Q < Allowable Street Capacity			
Total Inlet Interception Capacity	Q = 2.4	Q = 7.3	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q <sub>b</sub> = 0.0	Q <sub>b</sub> = 0.2	cfs
Capture Percentage = Q <sub>i</sub> /Q <sub>s</sub>	C% = 100	C% = 98	%




## ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

**Project:** Claremont Business Park 2 Filing No. 2 (Existing Conditions)


**Inlet ID:** Inlet 6 DP7 (South)



<b>Gutter Geometry:</b>							
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft						
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft						
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$						
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches						
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft						
Gutter Width	$W = 2.00$ ft						
Street Transverse Slope	$S_x = 0.020$ ft/ft						
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft						
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.010$ ft/ft						
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.016$						
Max. Allowable Spread for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <td style="text-align: center;">Minor Storm</td> <td style="text-align: center;">Major Storm</td> <td></td> </tr> <tr> <td style="text-align: center;">15.8</td> <td style="text-align: center;">17.0</td> <td style="text-align: right;">ft</td> </tr> </table>	Minor Storm	Major Storm		15.8	17.0	ft
Minor Storm	Major Storm						
15.8	17.0	ft					
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <td style="text-align: center;">Minor Storm</td> <td style="text-align: center;">Major Storm</td> <td></td> </tr> <tr> <td style="text-align: center;">4.6</td> <td style="text-align: center;">7.8</td> <td style="text-align: right;">inches</td> </tr> </table>	Minor Storm	Major Storm		4.6	7.8	inches
Minor Storm	Major Storm						
4.6	7.8	inches					
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<input type="checkbox"/> <input type="checkbox"/>						
<p>MINOR STORM Allowable Capacity is based on Depth Criterion</p> <p>MAJOR STORM Allowable Capacity is based on Spread Criterion</p>	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <td style="text-align: center;">Minor Storm</td> <td style="text-align: center;">Major Storm</td> <td></td> </tr> <tr> <td style="text-align: center;">5.5</td> <td style="text-align: center;">10.9</td> <td style="text-align: right;">cfs</td> </tr> </table>	Minor Storm	Major Storm		5.5	10.9	cfs
Minor Storm	Major Storm						
5.5	10.9	cfs					
<p><b>Minor storm max. allowable capacity GOOD - greater than the design peak flow of 0.90 cfs on sheet 'Inlet Management'</b></p> <p><b>Major storm max. allowable capacity GOOD - greater than the design peak flow of 4.10 cfs on sheet 'Inlet Management'</b></p>							

# INLET ON A CONTINUOUS GRADE


MHFD-Inlet, Version 5.02 (August 2022)



Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - $Q < \text{Allowable Street Capacity}$			
Total Inlet Interception Capacity	0.9	4.1	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	0.0	0.0	cfs
Capture Percentage = $Q_i/Q_o$	100	100	%

## AREA INLET IN A SWALE

**Claremont Business Park 2 Filing No. 2 (Existing Conditions)**  
**Inlet 7 (DP13)**



This worksheet uses the NRCS vegetative retardance method to determine Manning's n.  
 For more information see Section 7.2.3 of the USDCM.

<b>Analysis of Trapezoidal Grass-Lined Channel Using SCS Method</b>		A, B, C, D, or E =																									
NRCS Vegetal Retardance (A, B, C, D, or E)		n = 0.025																									
Manning's n (Leave cell D16 blank to manually enter an n value)		S <sub>0</sub> = 0.1200 ft/ft																									
Channel Invert Slope		B = 0.00 ft																									
Bottom Width		Z1 = 3.00 ft/ft																									
Left Side Slope		Z2 = 3.00 ft/ft																									
Right Side Slope		Choose One: <input type="checkbox"/> Non-Cohesive <input checked="" type="checkbox"/> Cohesive <input type="checkbox"/> Paved																									
Check one of the following soil types: <table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th style="text-align: left;">Soil Type:</th> <th>Max. Velocity (V<sub>MAX</sub>)</th> <th>Max Froude No. (F<sub>MAX</sub>)</th> </tr> </thead> <tbody> <tr> <td>Non-Cohesive</td> <td>5.0 fps</td> <td>0.60</td> </tr> <tr> <td>Cohesive</td> <td>7.0 fps</td> <td>0.80</td> </tr> <tr> <td>Paved</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>		Soil Type:	Max. Velocity (V <sub>MAX</sub> )	Max Froude No. (F <sub>MAX</sub> )	Non-Cohesive	5.0 fps	0.60	Cohesive	7.0 fps	0.80	Paved	N/A	N/A	<table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td>T<sub>MAX</sub> =</td> <td>1.92</td> <td>2.40</td> <td>ft</td> </tr> <tr> <td>d<sub>MAX</sub> =</td> <td>0.32</td> <td>0.40</td> <td>ft</td> </tr> </tbody> </table>			Minor Storm	Major Storm		T <sub>MAX</sub> =	1.92	2.40	ft	d <sub>MAX</sub> =	0.32	0.40	ft
Soil Type:	Max. Velocity (V <sub>MAX</sub> )	Max Froude No. (F <sub>MAX</sub> )																									
Non-Cohesive	5.0 fps	0.60																									
Cohesive	7.0 fps	0.80																									
Paved	N/A	N/A																									
	Minor Storm	Major Storm																									
T <sub>MAX</sub> =	1.92	2.40	ft																								
d <sub>MAX</sub> =	0.32	0.40	ft																								
Maximum Allowable Top Width of Channel for Minor & Major Storm																											
Maximum Allowable Water Depth in Channel for Minor & Major Storm																											
<b>Allowable Channel Capacity Based On Channel Geometry</b>		<table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>allow</sub> =</td> <td>1.8</td> <td>3.3</td> <td>cfs</td> </tr> <tr> <td>d<sub>allow</sub> =</td> <td>0.32</td> <td>0.40</td> <td>ft</td> </tr> </tbody> </table>			Minor Storm	Major Storm		Q <sub>allow</sub> =	1.8	3.3	cfs	d <sub>allow</sub> =	0.32	0.40	ft												
	Minor Storm	Major Storm																									
Q <sub>allow</sub> =	1.8	3.3	cfs																								
d <sub>allow</sub> =	0.32	0.40	ft																								
MINOR STORM Allowable Capacity is based on Depth Criterion MAJOR STORM Allowable Capacity is based on Depth Criterion																											
<b>Water Depth in Channel Based On Design Peak Flow</b>																											
Design Peak Flow		<table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"> <tbody> <tr> <td>Q<sub>o</sub> =</td> <td>0.7</td> <td>1.3</td> <td>cfs</td> </tr> <tr> <td>d =</td> <td>0.22</td> <td>0.28</td> <td>ft</td> </tr> </tbody> </table>		Q <sub>o</sub> =	0.7	1.3	cfs	d =	0.22	0.28	ft																
Q <sub>o</sub> =	0.7	1.3	cfs																								
d =	0.22	0.28	ft																								
Water Depth																											
<p style="color: red; margin: 0;"><b>Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'</b></p> <p style="color: red; margin: 0;"><b>Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'</b></p>																											

## AREA INLET IN A SWALE

**Claremont Business Park 2 Filing No. 2 (Existing Conditions)**  
**Inlet 7 (DP13)**

Inlet Design Information (Input)																							
Type of Inlet	CDOT Type C (Depressed) <span style="float: right;">Inlet Type = CDOT Type C (Depressed)</span>																						
Angle of Inclined Gate (must be <= 30 degrees)	$\theta = 0.00$ degrees																						
Width of Gate	$W = 3.00$ ft																						
Length of Gate	$L = 3.00$ ft																						
Open Area Ratio	$A_{RATIO} = 0.70$																						
Height of Inclined Gate	$H_B = 0.00$ ft																						
Clogging Factor	$C_f = 0.50$																						
Grate Discharge Coefficient	$C_d = 0.84$																						
Orifice Coefficient	$C_o = 0.56$																						
Weir Coefficient	$C_w = 1.81$																						
Water Depth at Inlet (for depressed inlets, 1 foot is added for depression)	$d =$																						
Total Inlet Interception Capacity (assumes clogged condition)	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>Q_a =</math></td> <td style="text-align: center;">1.22</td> <td style="text-align: center;">1.28</td> <td rowspan="3" style="text-align: right; vertical-align: middle;">cfs</td> </tr> <tr> <td><math>Q_b =</math></td> <td style="text-align: center;">15.7</td> <td style="text-align: center;">16.1</td> </tr> <tr> <td><math>C\% =</math></td> <td style="text-align: center;">0.0</td> <td style="text-align: center;">0.0</td> </tr> <tr> <td style="padding: 5px;">Bypassed Flow</td> <td style="padding: 5px;"><math>Q_b =</math></td> <td style="padding: 5px;"><math>0.0</math></td> <td style="text-align: right;">cfs</td> </tr> <tr> <td style="padding: 5px;">Capture Percentage = <math>Q_a/Q_o</math></td> <td style="padding: 5px;"><math>C\% =</math></td> <td style="padding: 5px;"><math>100</math></td> <td style="text-align: right;">%</td> </tr> </tbody> </table>		MINOR	MAJOR		$Q_a =$	1.22	1.28	cfs	$Q_b =$	15.7	16.1	$C\% =$	0.0	0.0	Bypassed Flow	$Q_b =$	$0.0$	cfs	Capture Percentage = $Q_a/Q_o$	$C\% =$	$100$	%
	MINOR	MAJOR																					
$Q_a =$	1.22	1.28	cfs																				
$Q_b =$	15.7	16.1																					
$C\% =$	0.0	0.0																					
Bypassed Flow	$Q_b =$	$0.0$	cfs																				
Capture Percentage = $Q_a/Q_o$	$C\% =$	$100$	%																				

**Warning 04: Froude No. exceeds USDCM Volume I recommendation.**

CLAREMONT COMMERCIAL FILING NO. 2 (EXISTING CONDITIONS)

<b>Weighted Percent Imperviousness of Ex Fill WQ Sand Filter Pond 2</b>				
<b>Contributing Basins</b>	<b>Area (Acres)</b>	<b>C<sub>s</sub></b>	<b>Impervious % (I)</b>	<b>(Acres)*(I)</b>
H1	0.18	0.09	2	0.35
H2	0.40	0.09	2	0.80
H3	0.04	0.09	2	0.07
H4	0.10	0.09	2	0.20
I1	0.57	0.80	94.4	54.17
I2	0.48	0.79	93.8	45.26
I3	0.58	0.65	84.3	49.29
I4	0.43	0.80	94.4	40.59
I5	0.23	0.73	90	21.09
I6	0.19	0.62	82.1	15.37
I7	0.23	0.77	92.5	21.57
J1	0.76	0.69	87.1	66.22
J2	0.25	0.73	90	22.69
J3	0.01	0.16	13	0.19
K1	0.17	0.83	96.1	16.32
K2	0.05	0.72	89.3	4.76
K3	0.15	0.78	93.1	13.84
K4	0.05	0.69	87.1	4.53
L	1.32	0.09	2	2.63
M1	0.28	0.81	95	27.03
M2	0.24	0.62	82.1	19.93
M3	0.37	0.83	96.1	35.09
M4	0.98	0.80	94.4	92.27
N1	0.06	0.90	100	6.49
N2	0.41	0.12	7	2.90
<b>Totals</b>	<b>8.55</b>			<b>563.68</b>
<b>Imperviousness of WQ Pond 2</b>	<b>65.9</b>			


8.55 B soils  
8.55 total area

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.02 (February 2020)

Project: **CLAREMONT COMMERCIAL FILING NO.2**

Basin ID: **WQCV POND 2 (Remodeled Existing Conditions)**



**Example Zone Configuration (Retention Pond)**

**Watershed Information**

Selected BMP Type =	<b>SF</b>	
Watershed Area =	8.55	acres
Watershed Length =	665	ft
Watershed Length to Centroid =	325	ft
Watershed Slope =	0.018	ft/ft
Watershed Imperviousness =	65.90%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Target WQCV Drain Time =	12.0	hours
Location for 1-hr Rainfall Depths =	User Input	

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

Water Quality Capture Volume (WQCV) =	0.147	acre-feet
Excess Urban Runoff Volume (EURV) =	0.616	acre-feet
2-yr Runoff Volume (P1 = 1.19 in.) =	0.539	acre-feet
5-yr Runoff Volume (P1 = 1.5 in.) =	0.733	acre-feet
10-yr Runoff Volume (P1 = 1.75 in.) =	0.899	acre-feet
25-yr Runoff Volume (P1 = 2 in.) =	1.100	acre-feet
50-yr Runoff Volume (P1 = 2.25 in.) =	1.274	acre-feet
100-yr Runoff Volume (P1 = 2.52 in.) =	1.485	acre-feet
500-yr Runoff Volume (P1 = 2.53 in.) =	1.492	acre-feet
Approximate 2-yr Detention Volume =	0.478	acre-feet
Approximate 5-yr Detention Volume =	0.640	acre-feet
Approximate 10-yr Detention Volume =	0.815	acre-feet
Approximate 25-yr Detention Volume =	0.877	acre-feet
Approximate 50-yr Detention Volume =	0.913	acre-feet
Approximate 100-yr Detention Volume =	0.986	acre-feet

**Optional User Overrides**

		acre-feet
		acre-feet
	1.19	inches
	1.50	inches
	1.75	inches
	2.00	inches
	2.25	inches
	2.52	inches
	2.53	inches



**Define Zones and Basin Geometry**

Zone 1 Volume (WQCV) =	0.147	acre-feet
Zone 2 Volume (100-year - Zone 1) =	0.839	acre-feet
Select Zone 3 Storage Volume (Optional) =		acre-feet
Total Detention Basin Volume =	0.986	acre-feet
Initial Surcharge Volume (ISV) =	N/A	ft <sup>3</sup>
Initial Surcharge Depth (ISD) =	N/A	ft
Total Available Detention Depth (H <sub>total</sub> ) =	user	ft
Depth of Trickle Channel (H <sub>TC</sub> ) =	N/A	ft
Slope of Trickle Channel (S <sub>TC</sub> ) =	N/A	ft/ft
Slopes of Main Basin Sides (S <sub>main</sub> ) =	user	H:V
Basin Length-to-Width Ratio (R <sub>L/W</sub> ) =	user	
Initial Surcharge Area (A <sub>ISV</sub> ) =	user	ft <sup>2</sup>
Surcharge Volume Length (L <sub>ISV</sub> ) =	user	ft
Surcharge Volume Width (W <sub>ISV</sub> ) =	user	ft
Depth of Basin Floor (H <sub>FLOOR</sub> ) =	user	ft
Length of Basin Floor (L <sub>FLOOR</sub> ) =	user	ft
Width of Basin Floor (W <sub>FLOOR</sub> ) =	user	ft
Area of Basin Floor (A <sub>FLOOR</sub> ) =	user	ft <sup>2</sup>
Volume of Basin Floor (V <sub>FLOOR</sub> ) =	user	ft <sup>3</sup>
Depth of Main Basin (H <sub>MAIN</sub> ) =	user	ft
Length of Main Basin (L <sub>MAIN</sub> ) =	user	ft
Width of Main Basin (W <sub>MAIN</sub> ) =	user	ft
Area of Main Basin (A <sub>MAIN</sub> ) =	user	ft <sup>2</sup>
Volume of Main Basin (V <sub>MAIN</sub> ) =	user	ft <sup>3</sup>
Calculated Total Basin Volume (V <sub>total</sub> ) =	user	acre-feet

Depth Increment =		ft									
Stage - Storage Description	Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft <sup>2</sup> )	Optional Override Area (ft <sup>2</sup> )	Area (acre)	Volume (ft <sup>3</sup> )	Volume (ac-ft)		
Media Surface	--	0.00	--	--	--	2,450	0.056				
6365	--	0.55	--	--	--	3,196	0.073	1,553	0.036		
6366	--	1.55	--	--	--	4,546	0.104	5,424	0.125		
6367	--	2.55	--	--	--	6,018	0.138	10,706	0.246		
6368	--	3.55	--	--	--	7,623	0.175	17,526	0.402		

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.02 (February 2020)*




Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

Define "Remodeled Existing Conditions." How is this different for the other calcs for this same pond shown on pdf page 60 below? Please discuss in the FDR text above.

## DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention Version 4.02 (February 2020)*

**Project: CLAREMONT COMMERCIAL FILING NO.2**  
**Basin ID: WQCV POND 2 (Remodeled Existing Conditions)**



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	1.76	0.147	Filtration Media
Zone 2 (100-year)	#VALUE!	0.839	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.986</b>	

**User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)**

Underdrain Orifice Invert Depth = <input type="text" value="2.50"/> ft (distance below the filtration media surface)	Underdrain Orifice Area = <input type="text" value="0.0"/> ft <sup>2</sup>
Underdrain Orifice Diameter = <input type="text" value="1.66"/> inches	Underdrain Orifice Centroid = <input type="text" value="0.07"/> feet

**User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)**

Invert of Lowest Orifice = <input type="text" value="N/A"/> ft (relative to basin bottom at Stage = 0 ft)	WQ Orifice Area per Row = <input type="text" value="N/A"/> ft <sup>2</sup>
Depth at top of Zone using Orifice Plate = <input type="text" value="N/A"/> ft (relative to basin bottom at Stage = 0 ft)	Elliptical Half-Width = <input type="text" value="N/A"/> feet
Orifice Plate: Orifice Vertical Spacing = <input type="text" value="N/A"/> inches	Elliptical Slot Centroid = <input type="text" value="N/A"/> feet
Orifice Plate: Orifice Area per Row = <input type="text" value="N/A"/> inches	Elliptical Slot Area = <input type="text" value="N/A"/> ft <sup>2</sup>

**User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)**

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

**User Input: Vertical Orifice (Circular or Rectangular)**

Invert of Vertical Orifice = <input type="text" value="Not Selected"/> <input type="text" value="Not Selected"/> ft (relative to basin bottom at Stage = 0 ft)	Vertical Orifice Area = <input type="text" value="Not Selected"/> ft <sup>2</sup>
Depth at top of Zone using Vertical Orifice = <input type="text" value="Not Selected"/> ft (relative to basin bottom at Stage = 0 ft)	Vertical Orifice Centroid = <input type="text" value="Not Selected"/> feet
Vertical Orifice Diameter = <input type="text" value="Not Selected"/> inches	

**User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir (and No Outlet Pipe))**

Overflow Weir Front Edge Height, H <sub>o</sub> = <input type="text" value="1.75"/> <input type="text" value="Not Selected"/> ft (relative to basin bottom at Stage = 0 ft)	Height of Grate Upper Edge, H <sub>g</sub> = <input type="text" value="1.75"/> feet
Overflow Weir Front Edge Length = <input type="text" value="7.00"/> feet	Overflow Weir Slope Length = <input type="text" value="2.91"/> feet
Overflow Weir Grate Slope = <input type="text" value="0.00"/> H:V	Grate Open Area / 100-yr Orifice Area = <input type="text" value="6.47"/>
Horiz. Length of Weir Sides = <input type="text" value="2.91"/> feet	Overflow Grate Open Area w/o Debris = <input type="text" value="14.26"/> ft <sup>2</sup>
Overflow Grate Open Area % = <input type="text" value="70%"/> % , grate open area/total area	Overflow Grate Open Area w/ Debris = <input type="text" value="7.13"/> ft <sup>2</sup>
Debris Clogging % = <input type="text" value="50%"/> %	

**User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)**

Depth to Invert of Outlet Pipe = <input type="text" value="2.75"/> <input type="text" value="Not Selected"/> ft (distance below basin bottom at Stage = 0 ft)	Outlet Orifice Area = <input type="text" value="2.20"/> ft <sup>2</sup>
Outlet Pipe Diameter = <input type="text" value="30.00"/> inches	Outlet Orifice Centroid = <input type="text" value="0.67"/> feet
Restrictor Plate Height Above Pipe Invert = <input type="text" value="13.80"/> inches	Half-Central Angle of Restrictor Plate on Pipe = <input type="text" value="1.49"/> <input type="text" value="N/A"/> radians

**User Input: Emergency Spillway (Rectangular or Trapezoidal)**

Spillway Invert Stage = <input type="text" value="3.00"/> ft (relative to basin bottom at Stage = 0 ft)	Spillway Design Flow Depth = <input type="text" value="0.75"/> feet
Spillway Crest Length = <input type="text" value="12.50"/> feet	Stage at Top of Freeboard = <input type="text" value="4.75"/> feet
Spillway End Slopes = <input type="text" value="4.00"/> H:V	Basin Area at Top of Freeboard = <input type="text" value="0.18"/> acres
Freeboard above Max Water Surface = <input type="text" value="1.00"/> feet	Basin Volume at Top of Freeboard = <input type="text" value="0.40"/> acre-ft




**Routed Hydrograph Results** *The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	2.53
One-Hour Rainfall Depth (in)	N/A	N/A	0.539	0.733	0.899	1.100	1.274	1.485	1.492
CUHP Runoff Volume (acre-ft)	N/A	N/A	0.539	0.733	0.899	1.100	1.274	1.485	1.492
Inflow Hydrograph Volume (acre-ft)	N/A	N/A	1.2	3.2	4.8	8.5	10.6	13.3	13.4
CUHP Predevelopment Peak Q (cfs)	N/A	N/A							
OPTIONAL Override Predevelopment Peak Q (cfs)	N/A	N/A							
Predevelopment Unit Peak Flow, q (cfs/acre)	N/A	N/A	0.14	0.38	0.56	0.99	1.24	1.55	1.56
Peak Inflow Q (cfs)	N/A	N/A	10.9	14.8	17.5	21.8	25.4	30.0	30.1
Peak Outflow Q (cfs)	0.2	42.6	8.2	13.7	16.1	22.5	23.0	23.9	23.9
Ratio Peak Outflow to Predevelopment Q	N/A	N/A	N/A	4.3	3.4	2.7	2.2	1.8	1.8
Structure Controlling Flow	Overflow Weir 1	Outlet Plate 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Outlet Plate 1	Outlet Plate 1	Outlet Plate 1	Outlet Plate 1
Max Velocity through Gate 1 (fps)	0.00	1.59	0.57	1.0	1.1	1.6	1.6	1.7	1.7
Max Velocity through Gate 2 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours)	13	12	14	14	13	13	12	12	11
Time to Drain 99% of Inflow Volume (hours)	13	13	15	15	15	15	15	14	14
Maximum Ponding Depth (ft)	1.76	2.54	2.08	2.22	2.27	2.42	2.62	2.97	2.98
Area at Maximum Ponding Depth (acres)	0.11	0.14	0.12	0.13	0.13	0.13	0.14	0.15	0.15
Maximum Volume Stored (acre-ft)	0.147	0.243	0.183	0.201	0.207	0.227	0.256	0.306	0.307



# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.00 (December 2019)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			



CLAREMONT BUSINESS PARK 2 FILING NO. 2 (PROPOSED CONDITIONS)

<b>Weighted Percent Imperviousness of Proposed WQ Sand Filter Pond 1</b>				
<b>Contributing Basins</b>	<b>Area (Acres)</b>	<b>C<sub>5</sub></b>	<b>Impervious % (I)</b>	<b>(Acres)*(I)</b>
<b>A</b>	0.21	0.09	2	0.43
<b>B</b>	1.50	0.81	90	134.89
<b>Totals</b>	<b>1.71</b>			<b>135.31</b>
<b>Imperviousness % to FSD</b>	<b>79.0</b>			


A soils 35%  
 B soils 65%

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.06 (July 2022)

Project: **Claremont Business Park 2 Filing No. 2**

Basin ID: **Lot 1 - Future Pond 1**



**Watershed Information**

Selected BMP Type =	<b>SF</b>
Watershed Area =	1.71 acres
Watershed Length =	300 ft
Watershed Length to Centroid =	150 ft
Watershed Slope =	0.017 ft/ft
Watershed Imperviousness =	79.00% percent
Percentage Hydrologic Soil Group A =	35.0% percent
Percentage Hydrologic Soil Group B =	65.0% percent
Percentage Hydrologic Soil Groups C/D =	0.0% percent
Target WQCV Drain Time =	12.0 hours
Location for 1-hr Rainfall Depths =	User Input

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

Water Quality Capture Volume (WQCV) =	0.037	acre-feet
Excess Urban Runoff Volume (EURV) =	0.159	acre-feet
2-yr Runoff Volume (P1 = 1.19 in.) =	0.121	acre-feet
5-yr Runoff Volume (P1 = 1.5 in.) =	0.159	acre-feet
10-yr Runoff Volume (P1 = 1.75 in.) =	0.192	acre-feet
25-yr Runoff Volume (P1 = 2 in.) =	0.229	acre-feet
50-yr Runoff Volume (P1 = 2.25 in.) =	0.263	acre-feet
100-yr Runoff Volume (P1 = 2.52 in.) =	0.303	acre-feet
500-yr Runoff Volume (P1 = 3.14 in.) =	0.388	acre-feet
Approximate 2-yr Detention Volume =	0.118	acre-feet
Approximate 5-yr Detention Volume =	0.155	acre-feet
Approximate 10-yr Detention Volume =	0.190	acre-feet
Approximate 25-yr Detention Volume =	0.211	acre-feet
Approximate 50-yr Detention Volume =	0.223	acre-feet
Approximate 100-yr Detention Volume =	0.237	acre-feet

**Optional User Overrides**

	acre-feet
	acre-feet
1.19	inches
1.50	inches
1.75	inches
2.00	inches
2.25	inches
2.52	inches
	inches


**Define Zones and Basin Geometry**

Zone 1 Volume (WQCV) =	0.037	acre-feet
Zone 2 Volume (100-year - Zone 1) =	0.200	acre-feet
Select Zone 3 Storage Volume (Optional) =		acre-feet
Total Detention Basin Volume =	0.237	acre-feet
Initial Surcharge Volume (ISV) =	N/A	ft <sup>3</sup>
Initial Surcharge Depth (ISD) =	N/A	ft
Total Available Detention Depth (H <sub>total</sub> ) =	user	ft
Depth of Trickle Channel (H <sub>TC</sub> ) =	N/A	ft
Slope of Trickle Channel (S <sub>TC</sub> ) =	N/A	ft/ft
Slopes of Main Basin Sides (S <sub>main</sub> ) =	user	H:V
Basin Length-to-Width Ratio (R <sub>LW</sub> ) =	user	
Initial Surcharge Area (A <sub>ISV</sub> ) =	user	ft <sup>2</sup>
Surcharge Volume Length (L <sub>ISV</sub> ) =	user	ft
Surcharge Volume Width (W <sub>ISV</sub> ) =	user	ft
Depth of Basin Floor (H <sub>FLOOR</sub> ) =	user	ft
Length of Basin Floor (L <sub>FLOOR</sub> ) =	user	ft
Width of Basin Floor (W <sub>FLOOR</sub> ) =	user	ft
Area of Basin Floor (A <sub>FLOOR</sub> ) =	user	ft <sup>2</sup>
Volume of Basin Floor (V <sub>FLOOR</sub> ) =	user	ft <sup>3</sup>
Depth of Main Basin (H <sub>MAIN</sub> ) =	user	ft
Length of Main Basin (L <sub>MAIN</sub> ) =	user	ft
Width of Main Basin (W <sub>MAIN</sub> ) =	user	ft
Area of Main Basin (A <sub>MAIN</sub> ) =	user	ft <sup>2</sup>
Volume of Main Basin (V <sub>MAIN</sub> ) =	user	ft <sup>3</sup>
Calculated Total Basin Volume (V <sub>total</sub> ) =	user	acre-feet

Stage - Storage Description	Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft <sup>2</sup> )	Optional Override Area (ft <sup>2</sup> )	Area (acre)	Volume (ft <sup>3</sup> )	Volume (ac-ft)
Media Surface	--	0.00	--	--	873	873	0.020		
	--	0.50	--	--	1,265	1,265	0.029	534	0.012
	--	1.50	--	--	2,124	2,124	0.049	2,229	0.051
	--	2.50	--	--	3,084	3,084	0.071	4,833	0.111
	--	3.50	--	--	4,144	4,144	0.095	8,447	0.194
	--	4.00	--	--	4,712	4,712	0.108	10,661	0.245

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.06 (July 2022)*




Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

## RETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD- Detention, Version 4.06 (July 2022)

**Project: Claremont Business Park 2 Filing No. 2**  
**Basin ID: Lot 1 - Future Pond 1**



**Example Zone Configuration (Retention Pond)**

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	1.19	0.037	Filtration Media
Zone 2 (100-year)	3.93	0.200	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.237</b>	

**User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)**

Underdrain Orifice Invert Depth =	2.50	ft (distance below the filtration media surface)
Underdrain Orifice Diameter =	0.89	inches

**Calculated Parameters for Underdrain**

Underdrain Orifice Area =	0.0	ft <sup>2</sup>
Underdrain Orifice Centroid =	0.04	feet

**User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)**

Centroid of Lowest Orifice =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing =	N/A	inches
Orifice Plate: Orifice Area per Row =	N/A	sq. inches

**Calculated Parameters for Plate**

WQ Orifice Area per Row =	N/A	ft <sup>2</sup>
Elliptical Half-Width =	N/A	feet
Elliptical Slot Centroid =	N/A	feet
Elliptical Slot Area =	N/A	ft <sup>2</sup>

**User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)**

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

**User Input: Vertical Orifice (Circular or Rectangular)**

	Not Selected	Not Selected	
Invert of Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =			inches

**Calculated Parameters for Vertical Orif**

	Not Selected	Not Selected
Vertical Orifice Area =		
Vertical Orifice Centroid =		

**User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)**

	Zone 2 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	1.19		ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	2.91		feet
Overflow Weir Gate Slope =	0.00		H:V
Horiz. Length of Weir Sides =	2.91		feet
Overflow Gate Type =	Type C Gate		
Debris Clogging % =	50%		%

**Calculated Parameters for Overflow Weir**

	Zone 2 Weir	Not Selected
Height of Gate Upper Edge, H <sub>t</sub> =	1.19	
Overflow Weir Slope Length =	2.91	
Gate Open Area / 100-yr Orifice Area =	3.34	
Overflow Gate Open Area w/o Debris =	5.89	
Overflow Gate Open Area w/ Debris =	2.95	

**User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)**

	Zone 2 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	2.75		ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	18.00		inches
Restrictor Plate Height Above Pipe Invert =	18.00		inches

**Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate**

	Zone 2 Restrictor	Not Selected
Outlet Orifice Area =	1.77	
Outlet Orifice Centroid =	0.75	
Half-Central Angle of Restrictor Plate on Pipe =	3.14	N/A

**User Input: Emergency Spillway (Rectangular or Trapezoidal)**

Spillway Invert Stage =	2.00	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	20.00	feet
Spillway End Slopes =	4.00	H:V
Freeboard above Max Water Surface =	1.00	feet

**Calculated Parameters for Spillway**

Spillway Design Flow Depth =	0.21	feet
Stage at Top of Freeboard =	3.21	feet
Basin Area at Top of Freeboard =	0.09	acres
Basin Volume at Top of Freeboard =	0.17	acre-ft




**Routed Hydrograph Results**

*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AI)*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
Design Storm Return Period =	N/A	N/A	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52
CUHP Runoff Volume (acre-ft) =	0.037	0.159	0.121	0.159	0.192	0.229	0.263	0.303
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.121	0.159	0.192	0.229	0.263	0.303
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	0.0	0.3	0.7	1.3	1.8	2.3
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A						
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.02	0.20	0.38	0.78	1.03	1.34
Peak Inflow Q (cfs) =	N/A	N/A	2.5	3.2	3.9	4.8	5.5	6.2
Peak Outflow Q (cfs) =	0.0	20.3	1.7	2.8	3.4	4.7	5.6	6.5
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	8.1	5.1	3.5	3.2	2.8
Structure Controlling Flow =	Overflow Weir 1	Spillway	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1
Max Velocity through Gate 1 (fps) =	N/A	3.26	0.28	0.5	0.6	0.8	0.9	1.1
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	12	6	13	13	13	12	12	12
Time to Drain 99% of Inflow Volume (hours) =	12	7	14	14	14	14	14	14
Maximum Ponding Depth (ft) =	1.19	3.12	1.39	1.47	1.51	1.58	1.63	1.68
Area at Maximum Ponding Depth (acres) =	0.04	0.09	0.05	0.05	0.05	0.05	0.05	0.05
Maximum Volume Stored (acre-ft) =	0.037	0.160	0.046	0.050	0.051	0.055	0.058	0.060

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

# DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: \_\_\_\_\_

## Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.04	0.00	0.14
	0:15:00	0.00	0.00	0.38	0.61	0.76	0.51	0.62	0.62	0.85
	0:20:00	0.00	0.00	1.24	1.59	1.86	1.16	1.34	1.45	1.86
	0:25:00	0.00	0.00	2.45	3.21	3.90	2.40	2.76	2.95	3.90
	0:30:00	0.00	0.00	2.49	3.23	3.76	4.79	5.53	6.17	7.93
	0:35:00	0.00	0.00	1.96	2.51	2.92	4.56	5.23	6.22	7.93
	0:40:00	0.00	0.00	1.53	1.90	2.20	3.87	4.43	5.21	6.62
	0:45:00	0.00	0.00	1.14	1.47	1.74	2.95	3.38	4.17	5.30
	0:50:00	0.00	0.00	0.87	1.18	1.35	2.45	2.80	3.38	4.30
	0:55:00	0.00	0.00	0.67	0.90	1.05	1.82	2.09	2.66	3.39
	1:00:00	0.00	0.00	0.55	0.72	0.87	1.38	1.59	2.13	2.71
	1:05:00	0.00	0.00	0.50	0.65	0.81	1.11	1.27	1.80	2.30
	1:10:00	0.00	0.00	0.42	0.63	0.79	0.89	1.03	1.31	1.68
	1:15:00	0.00	0.00	0.37	0.57	0.79	0.78	0.90	1.04	1.33
	1:20:00	0.00	0.00	0.35	0.52	0.71	0.65	0.74	0.76	0.97
	1:25:00	0.00	0.00	0.33	0.48	0.60	0.57	0.65	0.61	0.77
	1:30:00	0.00	0.00	0.32	0.46	0.53	0.48	0.55	0.50	0.64
	1:35:00	0.00	0.00	0.32	0.45	0.49	0.43	0.49	0.45	0.56
	1:40:00	0.00	0.00	0.32	0.39	0.47	0.40	0.45	0.42	0.52
	1:45:00	0.00	0.00	0.32	0.35	0.45	0.39	0.44	0.41	0.51
	1:50:00	0.00	0.00	0.32	0.33	0.44	0.38	0.42	0.40	0.50
	1:55:00	0.00	0.00	0.25	0.31	0.42	0.37	0.42	0.40	0.50
	2:00:00	0.00	0.00	0.21	0.29	0.37	0.37	0.42	0.40	0.50
	2:05:00	0.00	0.00	0.13	0.17	0.22	0.22	0.25	0.24	0.30
	2:10:00	0.00	0.00	0.07	0.10	0.13	0.13	0.15	0.14	0.18
	2:15:00	0.00	0.00	0.04	0.06	0.07	0.07	0.08	0.08	0.10
	2:20:00	0.00	0.00	0.02	0.03	0.04	0.04	0.05	0.05	0.06
	2:25:00	0.00	0.00	0.01	0.01	0.02	0.02	0.02	0.02	0.03
	2:30:00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01
	2:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	



CLAREMONT BUSINESS PARK 2 FILING NO. 2 (PROPOSED CONDITIONS)



<b>Weighted Percent Imperviousness of Proposed WQ Sand Filter Pond 2</b>				
<i>Contributing Basins</i>	<i>Area (Acres)</i>	<i>C<sub>s</sub></i>	<i>Impervious % (I)</i>	<i>(Acres)*(I)</i>
<i>C</i>	0.12	0.09	2	0.25
<i>D</i>	0.77	0.81	90	69.40
<b>Totals</b>	<b>0.89</b>			<b>69.64</b>
<b>Imperviousness of WQ Pond 2</b>	<b>77.9</b>			

A soils 48%  
 B soils 52%



# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.06 (July 2022)*




Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

## RETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD- Detention, Version 4.06 (July 2022)

**Project: Claremont Business Park 2 Filing No. 2**  
**Basin ID: Lot 2 - Future Pond 2**



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.99	0.017	Filtration Media
Zone 2 (100-year)	3.34	0.098	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.115</b>	

**User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)**

Underdrain Orifice Invert Depth =	2.50	ft (distance below the filtration media surface)
Underdrain Orifice Diameter =	0.61	inches

**Calculated Parameters for Underdrain**

Underdrain Orifice Area =	0.0	ft <sup>2</sup>
Underdrain Orifice Centroid =	0.03	feet

**User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)**

Centroid of Lowest Orifice =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing =	N/A	inches
Orifice Plate: Orifice Area per Row =	N/A	sq. inches

**Calculated Parameters for Plate**

WQ Orifice Area per Row =	N/A	ft <sup>2</sup>
Elliptical Half-Width =	N/A	feet
Elliptical Slot Centroid =	N/A	feet
Elliptical Slot Area =	N/A	ft <sup>2</sup>

**User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)**

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

**User Input: Vertical Orifice (Circular or Rectangular)**

	Not Selected	Not Selected	
Invert of Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =			inches

**Calculated Parameters for Vertical Orif**

	Not Selected	Not Selected
Vertical Orifice Area =		
Vertical Orifice Centroid =		

**User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)**

	Zone 2 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	0.99		ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	3.00		feet
Overflow Weir Gate Slope =	0.00		H:V
Horiz. Length of Weir Sides =	3.00		feet
Overflow Gate Type =	Type C Gate		
Debris Clogging % =	70%		%

**Calculated Parameters for Overflow Weir**

	Zone 2 Weir	Not Selected
Height of Gate Upper Edge, H <sub>t</sub> =	0.99	
Overflow Weir Slope Length =	3.00	
Gate Open Area / 100-yr Orifice Area =	5.01	
Overflow Gate Open Area w/o Debris =	6.26	
Overflow Gate Open Area w/ Debris =	1.88	

**User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)**

	Zone 2 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	2.75		ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	18.00		inches
Restrictor Plate Height Above Pipe Invert =	12.00		inches

**Calculated Parameters for Outlet Pipe w/ Flow Restriction Pl**

	Zone 2 Restrictor	Not Selected
Outlet Orifice Area =	1.25	
Outlet Orifice Centroid =	0.56	
Half-Central Angle of Restrictor Plate on Pipe =	1.91	N/A

**User Input: Emergency Spillway (Rectangular or Trapezoidal)**

Spillway Invert Stage =	2.00	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	10.00	feet
Spillway End Slopes =	4.00	H:V
Freeboard above Max Water Surface =	1.00	feet

**Calculated Parameters for Spillway**

Spillway Design Flow Depth =	0.18	feet
Stage at Top of Freeboard =	3.18	feet
Basin Area at Top of Freeboard =	0.06	acres
Basin Volume at Top of Freeboard =	0.11	acre-ft




**Routed Hydrograph Results**

*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AI)*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
Design Storm Return Period =								
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52
CUHP Runoff Volume (acre-ft) =	0.017	0.078	0.059	0.077	0.093	0.111	0.128	0.148
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.059	0.077	0.093	0.111	0.128	0.148
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	0.0	0.1	0.2	0.4	0.6	0.8
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A						
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.01	0.09	0.22	0.52	0.71	0.96
Peak Inflow Q (cfs) =	N/A	N/A	1.0	1.3	1.5	1.9	2.2	2.5
Peak Outflow Q (cfs) =	0.0	9.3	0.7	1.0	1.4	1.8	2.1	2.4
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	13.6	7.5	4.2	3.5	3.0
Structure Controlling Flow =	Filtration Media	Spillway	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1
Max Velocity through Gate 1 (fps) =	N/A	2.12	0.12	0.2	0.2	0.3	0.3	0.4
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	12	9	14	13	13	13	12	12
Time to Drain 99% of Inflow Volume (hours) =	12	10	15	15	15	14	14	14
Maximum Ponding Depth (ft) =	0.97	2.67	1.15	1.19	1.23	1.28	1.31	1.34
Area at Maximum Ponding Depth (acres) =	0.02	0.05	0.03	0.03	0.03	0.03	0.03	0.03
Maximum Volume Stored (acre-ft) =	0.017	0.078	0.021	0.022	0.024	0.025	0.026	0.027

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

# DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: \_\_\_\_\_

## Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.05
	0:15:00	0.00	0.00	0.13	0.21	0.26	0.18	0.22	0.21	0.30
	0:20:00	0.00	0.00	0.44	0.58	0.67	0.42	0.49	0.53	0.68
	0:25:00	0.00	0.00	0.90	1.18	1.43	0.89	1.02	1.09	1.44
	0:30:00	0.00	0.00	1.00	1.29	1.53	1.79	2.08	2.31	3.00
	0:35:00	0.00	0.00	0.88	1.12	1.32	1.88	2.16	2.54	3.27
	0:40:00	0.00	0.00	0.76	0.95	1.11	1.73	1.99	2.33	2.98
	0:45:00	0.00	0.00	0.62	0.79	0.94	1.48	1.71	2.07	2.65
	0:50:00	0.00	0.00	0.51	0.67	0.78	1.29	1.48	1.78	2.28
	0:55:00	0.00	0.00	0.44	0.58	0.68	1.05	1.21	1.50	1.92
	1:00:00	0.00	0.00	0.39	0.50	0.60	0.89	1.02	1.31	1.68
	1:05:00	0.00	0.00	0.33	0.43	0.52	0.77	0.88	1.16	1.49
	1:10:00	0.00	0.00	0.27	0.37	0.46	0.62	0.72	0.91	1.17
	1:15:00	0.00	0.00	0.22	0.31	0.41	0.51	0.58	0.71	0.91
	1:20:00	0.00	0.00	0.19	0.27	0.36	0.39	0.45	0.52	0.66
	1:25:00	0.00	0.00	0.18	0.25	0.32	0.33	0.38	0.40	0.51
	1:30:00	0.00	0.00	0.17	0.24	0.29	0.28	0.32	0.32	0.41
	1:35:00	0.00	0.00	0.16	0.23	0.26	0.25	0.28	0.28	0.35
	1:40:00	0.00	0.00	0.16	0.21	0.25	0.22	0.25	0.25	0.31
	1:45:00	0.00	0.00	0.16	0.19	0.24	0.21	0.23	0.22	0.28
	1:50:00	0.00	0.00	0.16	0.17	0.23	0.20	0.22	0.21	0.26
	1:55:00	0.00	0.00	0.13	0.16	0.22	0.19	0.21	0.20	0.25
	2:00:00	0.00	0.00	0.12	0.15	0.20	0.19	0.21	0.20	0.25
	2:05:00	0.00	0.00	0.08	0.11	0.14	0.13	0.15	0.14	0.18
	2:10:00	0.00	0.00	0.06	0.08	0.10	0.09	0.10	0.10	0.12
	2:15:00	0.00	0.00	0.04	0.05	0.07	0.07	0.07	0.07	0.09
	2:20:00	0.00	0.00	0.03	0.03	0.05	0.04	0.05	0.05	0.06
	2:25:00	0.00	0.00	0.02	0.02	0.03	0.03	0.03	0.03	0.04
	2:30:00	0.00	0.00	0.01	0.01	0.02	0.02	0.02	0.02	0.03
	2:35:00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.02
	2:40:00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01
	2:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

CLAREMONT BUSINESS PARK 2 FILING NO. 2 (PROPOSED CONDITIONS)

<b>Weighted Percent Imperviousness of Proposed WQ Sand Filter Pond 3</b>				
<b>Contributing Basins</b>	<b>Area (Acres)</b>	<b>C<sub>5</sub></b>	<b>Impervious % (I)</b>	<b>(Acres)*(I)</b>
<i>C1</i>	0.17	0.09	2	0.34
<i>D1</i>	0.78	0.81	90	70.31
<i>E1</i>	0.27	0.88	97	26.02
<i>E2</i>	0.21	0.88	97	20.22
<b>Totals</b>	<b>1.43</b>			<b>116.89</b>
<b>Imperviousness of WQ Pond 2</b>	<b>81.8</b>			



A soils      85%  
 B soils      15%





# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.06 (July 2022)*




# DETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD- Detention, Version 4.06 (July 2022)

**Project: Claremont Business Park 2 Filing No. 2**

**Basin ID: Lot 2 - Pond 3**



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	1.14	0.032	Filtration Media
Zone 2 (100-year)	4.25	0.184	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.216</b>	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth = 2.50 ft (distance below the filtration media surface)  
 Underdrain Orifice Diameter = 0.84 inches

Calculated Parameters for Underdrain  
 Underdrain Orifice Area = 0.0 ft<sup>2</sup>  
 Underdrain Orifice Centroid = 0.04 feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Centroid of Lowest Orifice = N/A ft (relative to basin bottom at Stage = 0 ft)  
 Depth at top of Zone using Orifice Plate = N/A ft (relative to basin bottom at Stage = 0 ft)  
 Orifice Plate: Orifice Vertical Spacing = N/A inches  
 Orifice Plate: Orifice Area per Row = N/A sq. inches

Calculated Parameters for Plate  
 WQ Orifice Area per Row = N/A ft<sup>2</sup>  
 Elliptical Half-Width = N/A feet  
 Elliptical Slot Centroid = N/A feet  
 Elliptical Slot Area = N/A ft<sup>2</sup>

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

User Input: Vertical Orifice (Circular or Rectangular)

Invert of Vertical Orifice = Not Selected ft (relative to basin bottom at Stage = 0 ft)  
 Depth at top of Zone using Vertical Orifice = Not Selected ft (relative to basin bottom at Stage = 0 ft)  
 Vertical Orifice Diameter = Not Selected inches

Calculated Parameters for Vertical Orif  
 Vertical Orifice Area = Not Selected ft<sup>2</sup>  
 Vertical Orifice Centroid = Not Selected feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)

Overflow Weir Front Edge Height, Ho = 1.14 ft (relative to basin bottom at Stage = 0 ft)  
 Overflow Weir Front Edge Length = 3.00 feet  
 Overflow Weir Gate Slope = 0.00 H:V  
 Horiz. Length of Weir Sides = 3.00 feet  
 Overflow Gate Type = Type C Gate  
 Debris Clogging % = 70%

Calculated Parameters for Overflow W  
 Height of Gate Upper Edge, H<sub>t</sub> = 1.14 feet  
 Overflow Weir Slope Length = 3.00 feet  
 Gate Open Area / 100-yr Orifice Area = 15.64  
 Overflow Gate Open Area w/o Debris = 6.26  
 Overflow Gate Open Area w/ Debris = 1.88

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Depth to Invert of Outlet Pipe = 2.75 ft (distance below basin bottom at Stage = 0 ft)  
 Outlet Pipe Diameter = 18.00 inches  
 Restrictor Plate Height Above Pipe Invert = 5.00 inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Pl  
 Outlet Orifice Area = 0.40 ft<sup>2</sup>  
 Outlet Orifice Centroid = 0.25 feet  
 Half-Central Angle of Restrictor Plate on Pipe = 1.11

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage = 5.00 ft (relative to basin bottom at Stage = 0 ft)  
 Spillway Crest Length = 18.00 feet  
 Spillway End Slopes = 4.00 H:V  
 Freeboard above Max Water Surface = 1.00 feet

Calculated Parameters for Spillway  
 Spillway Design Flow Depth = 0.19 feet  
 Stage at Top of Freeboard = 6.19 feet  
 Basin Area at Top of Freeboard = 0.09 acres  
 Basin Volume at Top of Freeboard = 0.37 acre-ft




## Routed Hydrograph Results

The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AI)

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
Design Storm Return Period =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52
One-Hour Rainfall Depth (in) =	N/A	N/A	0.105	0.135	0.160	0.191	0.219	0.251
CUHP Runoff Volume (acre-ft) =	0.032	0.151	0.105	0.135	0.160	0.191	0.219	0.251
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.0	0.0	0.0	0.5	0.8	1.2
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	0.01	0.02	0.03	0.36	0.57	0.83
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A	0.01	0.02	0.03	0.36	0.57	0.83
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	2.0	2.6	3.0	3.7	4.3	4.9
Peak Inflow Q (cfs) =	0.0	4.6	1.3	1.9	2.4	3.3	3.9	4.0
Peak Outflow Q (cfs) =	N/A	N/A	N/A	68.8	49.5	6.4	4.8	3.4
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	68.8	49.5	6.4	4.8	3.4
Structure Controlling Flow =	Filtration Media	Outlet Plate 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Outlet Plate 1	Outlet Plate 1
Max Velocity through Gate 1 (fps) =	N/A	0.74	0.20	0.3	0.4	0.5	0.6	0.6
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	11	11	13	13	13	12	12	12
Time to Drain 99% of Inflow Volume (hours) =	12	12	14	14	14	14	14	14
Maximum Ponding Depth (ft) =	1.13	3.31	1.37	1.44	1.49	1.57	1.62	1.79
Area at Maximum Ponding Depth (acres) =	0.04	0.07	0.04	0.04	0.04	0.04	0.04	0.05
Maximum Volume Stored (acre-ft) =	0.032	0.152	0.042	0.044	0.047	0.050	0.052	0.060

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

# DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: \_\_\_\_\_

**Inflow Hydrographs**

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.



Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.03	0.00	0.11
	0:15:00	0.00	0.00	0.30	0.49	0.61	0.41	0.50	0.50	0.69
	0:20:00	0.00	0.00	1.01	1.30	1.51	0.95	1.09	1.18	1.52
	0:25:00	0.00	0.00	1.96	2.55	3.02	1.92	2.21	2.35	3.03
	0:30:00	0.00	0.00	2.03	2.56	2.94	3.71	4.27	4.76	6.15
	0:35:00	0.00	0.00	1.65	2.05	2.36	3.61	4.14	4.92	6.31
	0:40:00	0.00	0.00	1.33	1.62	1.85	3.13	3.59	4.22	5.41
	0:45:00	0.00	0.00	1.02	1.28	1.49	2.48	2.83	3.49	4.47
	0:50:00	0.00	0.00	0.81	1.06	1.20	2.05	2.35	2.84	3.65
	0:55:00	0.00	0.00	0.65	0.84	0.97	1.59	1.82	2.28	2.94
	1:00:00	0.00	0.00	0.52	0.67	0.79	1.25	1.43	1.87	2.42
	1:05:00	0.00	0.00	0.45	0.58	0.70	1.00	1.14	1.56	2.02
	1:10:00	0.00	0.00	0.38	0.55	0.68	0.79	0.90	1.14	1.47
	1:15:00	0.00	0.00	0.34	0.50	0.67	0.68	0.78	0.91	1.17
	1:20:00	0.00	0.00	0.31	0.46	0.61	0.58	0.65	0.68	0.87
	1:25:00	0.00	0.00	0.30	0.43	0.53	0.51	0.58	0.55	0.70
	1:30:00	0.00	0.00	0.29	0.41	0.48	0.44	0.49	0.46	0.59
	1:35:00	0.00	0.00	0.28	0.40	0.44	0.39	0.44	0.41	0.51
	1:40:00	0.00	0.00	0.28	0.35	0.42	0.36	0.41	0.38	0.47
	1:45:00	0.00	0.00	0.28	0.32	0.40	0.35	0.39	0.36	0.45
	1:50:00	0.00	0.00	0.28	0.29	0.39	0.34	0.38	0.36	0.44
	1:55:00	0.00	0.00	0.23	0.28	0.38	0.33	0.37	0.35	0.44
	2:00:00	0.00	0.00	0.20	0.26	0.34	0.33	0.37	0.35	0.44
	2:05:00	0.00	0.00	0.12	0.16	0.21	0.21	0.23	0.23	0.28
	2:10:00	0.00	0.00	0.08	0.10	0.13	0.13	0.15	0.14	0.18
	2:15:00	0.00	0.00	0.04	0.06	0.08	0.08	0.09	0.09	0.11
	2:20:00	0.00	0.00	0.02	0.04	0.05	0.05	0.05	0.05	0.06
	2:25:00	0.00	0.00	0.01	0.02	0.02	0.03	0.03	0.03	0.03
	2:30:00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01
	2:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	





# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.06 (July 2022)*




Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

## RETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD- Detention, Version 4.06 (July 2022)

**Project: Claremont Business Park 2 Filing No. 2**  
**Basin ID: Lot 3 - Pond 4**



**Example Zone Configuration (Retention Pond)**

	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	0.82	0.008	Filtration Media
Zone 2 (100-year)	2.70	0.043	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.051</b>	

**User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)**

Underdrain Orifice Invert Depth =	2.50	ft (distance below the filtration media surface)
Underdrain Orifice Diameter =	0.42	inches

**Calculated Parameters for Underdrain**

Underdrain Orifice Area =	0.0	ft <sup>2</sup>
Underdrain Orifice Centroid =	0.02	feet

**User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)**

Centroid of Lowest Orifice =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing =	N/A	inches
Orifice Plate: Orifice Area per Row =	N/A	sq. inches

**Calculated Parameters for Plate**

WQ Orifice Area per Row =	N/A	ft <sup>2</sup>
Elliptical Half-Width =	N/A	feet
Elliptical Slot Centroid =	N/A	feet
Elliptical Slot Area =	N/A	ft <sup>2</sup>

**User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)**

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

**User Input: Vertical Orifice (Circular or Rectangular)**

	Not Selected	Not Selected	
Invert of Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =			ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =			inches

**Calculated Parameters for Vertical Orif**

	Not Selected	Not Selected
Vertical Orifice Area =		
Vertical Orifice Centroid =		

**User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)**

	Zone 2 Weir	Not Selected	
Overflow Weir Front Edge Height, Ho =	0.82		ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	3.00		feet
Overflow Weir Gate Slope =	0.00		H:V
Horiz. Length of Weir Sides =	3.00		feet
Overflow Gate Type =	Type C Gate		
Debris Clogging % =	70%		%

**Calculated Parameters for Overflow W**

	Zone 2 Weir	Not Selected
Height of Gate Upper Edge, H <sub>t</sub> =	0.82	
Overflow Weir Slope Length =	3.00	
Gate Open Area / 100-yr Orifice Area =	5.10	
Overflow Gate Open Area w/o Debris =	6.26	
Overflow Gate Open Area w/ Debris =	1.88	

**User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)**

	Zone 2 Restrictor	Not Selected	
Depth to Invert of Outlet Pipe =	2.75		ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	15.00		inches
Restrictor Plate Height Above Pipe Invert =	15.00		inches

**Calculated Parameters for Outlet Pipe w/ Flow Restriction Pl**

	Zone 2 Restrictor	Not Selected
Outlet Orifice Area =	1.23	
Outlet Orifice Centroid =	0.63	
Half-Central Angle of Restrictor Plate on Pipe =	3.14	N/A

**User Input: Emergency Spillway (Rectangular or Trapezoidal)**

Spillway Invert Stage =	1.50	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	6.00	feet
Spillway End Slopes =	4.00	H:V
Freeboard above Max Water Surface =	1.00	feet

**Calculated Parameters for Spillway**

Spillway Design Flow Depth =	0.13	feet
Stage at Top of Freeboard =	2.63	feet
Basin Area at Top of Freeboard =	0.03	acres
Basin Volume at Top of Freeboard =	0.05	acre-ft

**Routed Hydrograph Results**




*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AI)*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
Design Storm Return Period =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52
One-Hour Rainfall Depth (in) =	N/A	N/A	0.025	0.032	0.037	0.044	0.050	0.057
CUHP Runoff Volume (acre-ft) =	0.008	0.037	0.025	0.032	0.037	0.044	0.050	0.057
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.0	0.0	0.0	0.0	0.1	0.1
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	0.0	0.0	0.0	0.0	0.1	0.1
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A	0.0	0.0	0.0	0.0	0.1	0.1
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.00	0.00	0.00	0.13	0.28	0.47
Peak Inflow Q (cfs) =	N/A	N/A	0.4	0.5	0.6	0.7	0.8	0.9
Peak Outflow Q (cfs) =	0.0	5.5	0.3	0.4	0.6	0.7	0.8	1.0
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	#DIV/0!	#DIV/0!	18.9	9.3	6.8
Structure Controlling Flow =	Overflow Weir 1	Spillway	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1
Max Velocity through Gate 1 (fps) =	N/A	1.97	0.04	0.1	0.1	0.1	0.1	0.2
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	12	0	14	13	13	13	13	12
Time to Drain 99% of Inflow Volume (hours) =	12	0	15	14	14	14	14	14
Maximum Ponding Depth (ft) =	0.82	2.24	0.90	0.93	0.95	0.98	0.98	1.01
Area at Maximum Ponding Depth (acres) =	0.01	0.03	0.01	0.01	0.01	0.01	0.01	0.02
Maximum Volume Stored (acre-ft) =	0.008	0.037	0.009	0.009	0.010	0.010	0.010	0.011



# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

# DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: \_\_\_\_\_

## Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.



Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.00	0.02
	0:15:00	0.00	0.00	0.05	0.09	0.11	0.07	0.09	0.09	0.12
	0:20:00	0.00	0.00	0.18	0.24	0.28	0.18	0.20	0.22	0.28
	0:25:00	0.00	0.00	0.37	0.47	0.56	0.36	0.41	0.44	0.56
	0:30:00	0.00	0.00	0.40	0.51	0.58	0.68	0.77	0.85	1.09
	0:35:00	0.00	0.00	0.36	0.44	0.51	0.70	0.80	0.93	1.18
	0:40:00	0.00	0.00	0.31	0.38	0.44	0.65	0.74	0.86	1.09
	0:45:00	0.00	0.00	0.26	0.32	0.37	0.56	0.64	0.76	0.97
	0:50:00	0.00	0.00	0.21	0.27	0.31	0.49	0.56	0.66	0.84
	0:55:00	0.00	0.00	0.19	0.24	0.27	0.40	0.46	0.56	0.71
	1:00:00	0.00	0.00	0.16	0.21	0.24	0.35	0.40	0.49	0.62
	1:05:00	0.00	0.00	0.14	0.18	0.22	0.30	0.34	0.44	0.56
	1:10:00	0.00	0.00	0.12	0.16	0.19	0.25	0.29	0.35	0.45
	1:15:00	0.00	0.00	0.10	0.14	0.17	0.21	0.24	0.28	0.36
	1:20:00	0.00	0.00	0.08	0.12	0.15	0.17	0.19	0.21	0.27
	1:25:00	0.00	0.00	0.08	0.11	0.13	0.14	0.16	0.16	0.21
	1:30:00	0.00	0.00	0.07	0.10	0.12	0.12	0.13	0.14	0.17
	1:35:00	0.00	0.00	0.07	0.10	0.11	0.10	0.12	0.12	0.15
	1:40:00	0.00	0.00	0.07	0.09	0.11	0.10	0.11	0.10	0.13
	1:45:00	0.00	0.00	0.07	0.08	0.10	0.09	0.10	0.10	0.12
	1:50:00	0.00	0.00	0.07	0.08	0.10	0.08	0.10	0.09	0.11
	1:55:00	0.00	0.00	0.06	0.07	0.09	0.08	0.09	0.09	0.11
	2:00:00	0.00	0.00	0.05	0.07	0.08	0.08	0.09	0.08	0.11
	2:05:00	0.00	0.00	0.04	0.05	0.06	0.06	0.06	0.06	0.08
	2:10:00	0.00	0.00	0.03	0.03	0.04	0.04	0.05	0.04	0.05
	2:15:00	0.00	0.00	0.02	0.02	0.03	0.03	0.03	0.03	0.04
	2:20:00	0.00	0.00	0.01	0.02	0.02	0.02	0.02	0.02	0.03
	2:25:00	0.00	0.00	0.01	0.01	0.01	0.01	0.02	0.01	0.02
	2:30:00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01
	2:35:00	0.00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01
	2:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	2:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	





# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.06 (July 2022)*




Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

## RETENTION BASIN OUTLET STRUCTURE DESIGN

MHFD- Detention, Version 4.06 (July 2022)

**Project: Claremont Business Park 2 Filing No. 2**  
**Basin ID: Lot 3 - Pond 5**



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	1.14	0.031	Filtration Media
Zone 2 (100-year)	4.03	0.165	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.196</b>	

**User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)**

Underdrain Orifice Invert Depth =	2.50	ft (distance below the filtration media surface)
Underdrain Orifice Diameter =	0.82	inches

**Calculated Parameters for Underdrain**

Underdrain Orifice Area =	0.0	ft <sup>2</sup>
Underdrain Orifice Centroid =	0.03	feet

**User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)**

Centroid of Lowest Orifice =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Orifice Plate =	N/A	ft (relative to basin bottom at Stage = 0 ft)
Orifice Plate: Orifice Vertical Spacing =	N/A	inches
Orifice Plate: Orifice Area per Row =	N/A	sq. inches

**Calculated Parameters for Plate**

WQ Orifice Area per Row =	N/A	ft <sup>2</sup>
Elliptical Half-Width =	N/A	feet
Elliptical Slot Centroid =	N/A	feet
Elliptical Slot Area =	N/A	ft <sup>2</sup>

**User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)**

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

**User Input: Vertical Orifice (Circular or Rectangular)**

	Not Selected	Not Selected
Invert of Vertical Orifice =		ft (relative to basin bottom at Stage = 0 ft)
Depth at top of Zone using Vertical Orifice =		ft (relative to basin bottom at Stage = 0 ft)
Vertical Orifice Diameter =		inches

**Calculated Parameters for Vertical Orif**

	Not Selected	Not Selected
Vertical Orifice Area =		
Vertical Orifice Centroid =		

**User Input: Overflow Weir (Dropbox with Flat or Sloped Gate and Outlet Pipe OR Rectangular/Trapezoidal Weir and No Outlet Pipe)**

	Zone 2 Weir	Not Selected
Overflow Weir Front Edge Height, Ho =	1.15	ft (relative to basin bottom at Stage = 0 ft)
Overflow Weir Front Edge Length =	3.00	feet
Overflow Weir Gate Slope =	0.00	H:V
Horiz. Length of Weir Sides =	3.00	feet
Overflow Gate Type =	Type C Gate	
Debris Clogging % =	70%	%

**Calculated Parameters for Overflow Weir**

	Zone 2 Weir	Not Selected
Height of Gate Upper Edge, H <sub>t</sub> =	1.15	
Overflow Weir Slope Length =	3.00	
Gate Open Area / 100-yr Orifice Area =	5.10	
Overflow Gate Open Area w/o Debris =	6.26	
Overflow Gate Open Area w/ Debris =	1.88	

**User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)**

	Zone 2 Restrictor	Not Selected
Depth to Invert of Outlet Pipe =	2.75	ft (distance below basin bottom at Stage = 0 ft)
Outlet Pipe Diameter =	15.00	inches
Restrictor Plate Height Above Pipe Invert =	15.00	inches

**Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate**

	Zone 2 Restrictor	Not Selected
Outlet Orifice Area =	1.23	
Outlet Orifice Centroid =	0.63	
Half-Central Angle of Restrictor Plate on Pipe =	3.14	N/A

**User Input: Emergency Spillway (Rectangular or Trapezoidal)**

Spillway Invert Stage =	2.00	ft (relative to basin bottom at Stage = 0 ft)
Spillway Crest Length =	10.00	feet
Spillway End Slopes =	4.00	H:V
Freeboard above Max Water Surface =	1.00	feet

**Calculated Parameters for Spillway**

Spillway Design Flow Depth =	0.21	feet
Stage at Top of Freeboard =	3.21	feet
Basin Area at Top of Freeboard =	0.07	acres
Basin Volume at Top of Freeboard =	0.14	acre-ft




**Routed Hydrograph Results**

*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AI)*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year
Design Storm Return Period =								
One-Hour Rainfall Depth (in) =	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52
CUHP Runoff Volume (acre-ft) =	0.031	0.141	0.097	0.125	0.148	0.172	0.196	0.223
Inflow Hydrograph Volume (acre-ft) =	N/A	N/A	0.097	0.125	0.148	0.172	0.196	0.223
CUHP Predevelopment Peak Q (cfs) =	N/A	N/A	0.0	0.0	0.0	0.1	0.3	0.5
OPTIONAL Override Predevelopment Peak Q (cfs) =	N/A	N/A						
Predevelopment Unit Peak Flow, q (cfs/acre) =	N/A	N/A	0.00	0.01	0.01	0.12	0.25	0.40
Peak Inflow Q (cfs) =	N/A	N/A	1.4	1.7	2.0	2.4	2.8	3.2
Peak Outflow Q (cfs) =	0.0	17.3	0.9	1.3	1.6	2.2	2.5	3.0
Ratio Peak Outflow to Predevelopment Q =	N/A	N/A	N/A	120.0	104.1	15.6	8.9	6.5
Structure Controlling Flow =	Filtration Media	Spillway	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1
Max Velocity through Gate 1 (fps) =	N/A	2.19	0.14	0.2	0.2	0.4	0.4	0.5
Max Velocity through Gate 2 (fps) =	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours) =	12	8	14	14	13	13	13	12
Time to Drain 99% of Inflow Volume (hours) =	12	9	15	15	15	15	14	14
Maximum Ponding Depth (ft) =	1.14	3.30	1.33	1.38	1.41	1.48	1.51	1.55
Area at Maximum Ponding Depth (acres) =	0.03	0.07	0.04	0.04	0.04	0.04	0.04	0.04
Maximum Volume Stored (acre-ft) =	0.031	0.141	0.038	0.039	0.041	0.043	0.044	0.046

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.06 (July 2022)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			

# DETENTION BASIN OUTLET STRUCTURE DESIGN

Outflow Hydrograph Workbook Filename: \_\_\_\_\_

## Inflow Hydrographs

The user can override the calculated inflow hydrographs from this workbook with inflow hydrographs developed in a separate program.

Time Interval	SOURCE	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP	CUHP
	TIME	WQCV [cfs]	EURV [cfs]	2 Year [cfs]	5 Year [cfs]	10 Year [cfs]	25 Year [cfs]	50 Year [cfs]	100 Year [cfs]	500 Year [cfs]
5.00 min	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.02	0.00	0.06
	0:15:00	0.00	0.00	0.16	0.27	0.33	0.22	0.28	0.27	0.38
	0:20:00	0.00	0.00	0.58	0.76	0.89	0.56	0.65	0.70	0.91
	0:25:00	0.00	0.00	1.18	1.53	1.80	1.16	1.34	1.42	1.82
	0:30:00	0.00	0.00	1.37	1.73	1.99	2.20	2.52	2.77	3.53
	0:35:00	0.00	0.00	1.27	1.59	1.82	2.41	2.75	3.18	4.05
	0:40:00	0.00	0.00	1.15	1.41	1.62	2.31	2.64	3.05	3.88
	0:45:00	0.00	0.00	1.00	1.26	1.45	2.08	2.37	2.81	3.57
	0:50:00	0.00	0.00	0.88	1.12	1.28	1.90	2.16	2.55	3.24
	0:55:00	0.00	0.00	0.77	0.98	1.13	1.66	1.88	2.27	2.88
	1:00:00	0.00	0.00	0.69	0.88	1.02	1.45	1.65	2.02	2.56
	1:05:00	0.00	0.00	0.63	0.81	0.95	1.29	1.47	1.84	2.33
	1:10:00	0.00	0.00	0.56	0.75	0.89	1.14	1.30	1.58	2.01
	1:15:00	0.00	0.00	0.50	0.68	0.83	1.02	1.15	1.37	1.73
	1:20:00	0.00	0.00	0.43	0.59	0.74	0.88	0.99	1.14	1.44
	1:25:00	0.00	0.00	0.38	0.52	0.63	0.75	0.85	0.93	1.18
	1:30:00	0.00	0.00	0.33	0.46	0.54	0.62	0.70	0.76	0.96
	1:35:00	0.00	0.00	0.30	0.42	0.48	0.51	0.58	0.61	0.77
	1:40:00	0.00	0.00	0.28	0.37	0.45	0.44	0.50	0.51	0.64
	1:45:00	0.00	0.00	0.28	0.34	0.42	0.40	0.45	0.45	0.57
	1:50:00	0.00	0.00	0.27	0.32	0.41	0.37	0.41	0.41	0.52
	1:55:00	0.00	0.00	0.24	0.30	0.39	0.35	0.39	0.38	0.48
	2:00:00	0.00	0.00	0.21	0.28	0.36	0.33	0.38	0.36	0.45
	2:05:00	0.00	0.00	0.17	0.22	0.28	0.26	0.29	0.28	0.35
	2:10:00	0.00	0.00	0.13	0.16	0.21	0.20	0.22	0.21	0.26
	2:15:00	0.00	0.00	0.10	0.13	0.16	0.15	0.17	0.16	0.20
	2:20:00	0.00	0.00	0.07	0.09	0.12	0.11	0.13	0.12	0.15
	2:25:00	0.00	0.00	0.05	0.07	0.09	0.08	0.09	0.09	0.11
	2:30:00	0.00	0.00	0.04	0.05	0.07	0.06	0.07	0.07	0.08
	2:35:00	0.00	0.00	0.03	0.04	0.05	0.05	0.05	0.05	0.06
	2:40:00	0.00	0.00	0.02	0.03	0.03	0.03	0.04	0.04	0.04
	2:45:00	0.00	0.00	0.01	0.02	0.02	0.02	0.03	0.02	0.03
	2:50:00	0.00	0.00	0.01	0.01	0.01	0.01	0.02	0.02	0.02
	2:55:00	0.00	0.00	0.00	0.01	0.01	0.01	0.01	0.01	0.01
	3:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	3:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	4:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:05:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:10:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:15:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:20:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:25:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:30:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:35:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:40:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:45:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:50:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	5:55:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	



CLAREMONT BUSINESS PARK 2 FILING NO. 2 (PROPOSED CONDITIONS)

<b>Weighted Percent Imperviousness of Ex Fil 1 WQ Sand Filter Pond 2</b>				
<b>Contributing Basins</b>	<b>Area (Acres)</b>	<b>C<sub>5</sub></b>	<b>Impervious % (I)</b>	<b>(Acres)*(I)</b>
H1	0.16	0.09	2	0.33
H2	0.40	0.09	2	0.80
H3	0.04	0.09	2	0.07
H4	0.10	0.09	2	0.20
I1	0.55	0.83	96.1	52.51
I2	0.48	0.79	93.8	45.26
I3	0.45	0.78	93.1	41.48
I4	0.55	0.81	95	52.18
I5	0.23	0.73	90	21.09
I6	0.19	0.62	82.1	15.37
I7	0.23	0.77	92.5	21.57
J1	0.69	0.81	95	65.94
J2	0.25	0.73	90	22.69
J3	0.01	0.16	13	0.19
K1	0.17	0.83	96.1	16.32
K2	0.05	0.72	89.3	4.76
K3	0.15	0.78	93.1	13.84
K4	0.05	0.69	87.1	4.53
L	1.32	0.09	2	2.63
M1	0.28	0.81	95	27.03
M2	0.24	0.62	82.1	19.93
M3	0.37	0.83	96.1	35.09
M4	0.98	0.80	94.4	92.27
N1	0.06	0.90	100	6.49
N2	0.41	0.12	7	2.90
<b>Totals</b>	<b>8.43</b>			<b>565.48</b>
<b>Imperviousness of WQ Pond 2</b>	<b>67.1</b>			


A soils      100%  
 B soils      0%

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

MHFD-Detention, Version 4.02 (February 2020)

Project: **CLAREMONT COMMERCIAL FILING NO.2**

Basin ID: **WQCV POND 2 (Remodeled Proposed Conditions)**



**Watershed Information**

Selected BMP Type =	<b>SF</b>	
Watershed Area =	8.43	acres
Watershed Length =	665	ft
Watershed Length to Centroid =	325	ft
Watershed Slope =	0.018	ft/ft
Watershed Imperviousness =	67.10%	percent
Percentage Hydrologic Soil Group A =	0.0%	percent
Percentage Hydrologic Soil Group B =	100.0%	percent
Percentage Hydrologic Soil Groups C/D =	0.0%	percent
Target WQCV Drain Time =	12.0	hours

Location for 1-hr Rainfall Depths = User Input

After providing required inputs above including 1-hour rainfall depths, click 'Run CUHP' to generate runoff hydrographs using the embedded Colorado Urban Hydrograph Procedure.

Water Quality Capture Volume (WQCV) =	0.148	acre-feet
Excess Urban Runoff Volume (EURV) =	0.619	acre-feet
2-yr Runoff Volume (P1 = 1.19 in.) =	0.541	acre-feet
5-yr Runoff Volume (P1 = 1.5 in.) =	0.734	acre-feet
10-yr Runoff Volume (P1 = 1.75 in.) =	0.897	acre-feet
25-yr Runoff Volume (P1 = 2 in.) =	1.095	acre-feet
50-yr Runoff Volume (P1 = 2.25 in.) =	1.267	acre-feet
100-yr Runoff Volume (P1 = 2.52 in.) =	1.474	acre-feet
500-yr Runoff Volume (P1 = 2.53 in.) =	1.481	acre-feet
Approximate 2-yr Detention Volume =	0.482	acre-feet
Approximate 5-yr Detention Volume =	0.644	acre-feet
Approximate 10-yr Detention Volume =	0.818	acre-feet
Approximate 25-yr Detention Volume =	0.880	acre-feet
Approximate 50-yr Detention Volume =	0.916	acre-feet
Approximate 100-yr Detention Volume =	0.986	acre-feet

**Optional User Overrides**

	acre-feet
	acre-feet
	inches
	inches
	inches
	inches
	inches
	inches
	inches
	inches



**Define Zones and Basin Geometry**

Zone 1 Volume (WQCV) =	0.148	acre-feet
Zone 2 Volume (100-year - Zone 1) =	0.838	acre-feet
Select Zone 3 Storage Volume (Optional) =		acre-feet
Total Detention Basin Volume =	0.986	acre-feet
Initial Surcharge Volume (ISV) =	N/A	ft <sup>3</sup>
Initial Surcharge Depth (ISD) =	N/A	ft
Total Available Detention Depth (H <sub>total</sub> ) =	user	ft
Depth of Trickle Channel (H <sub>TC</sub> ) =	N/A	ft
Slope of Trickle Channel (S <sub>TC</sub> ) =	N/A	ft/ft
Slopes of Main Basin Sides (S <sub>main</sub> ) =	user	H:V
Basin Length-to-Width Ratio (R <sub>L/W</sub> ) =	user	
Initial Surcharge Area (A <sub>ISV</sub> ) =	user	ft <sup>2</sup>
Surcharge Volume Length (L <sub>ISV</sub> ) =	user	ft
Surcharge Volume Width (W <sub>ISV</sub> ) =	user	ft
Depth of Basin Floor (H <sub>FLOOR</sub> ) =	user	ft
Length of Basin Floor (L <sub>FLOOR</sub> ) =	user	ft
Width of Basin Floor (W <sub>FLOOR</sub> ) =	user	ft
Area of Basin Floor (A <sub>FLOOR</sub> ) =	user	ft <sup>2</sup>
Volume of Basin Floor (V <sub>FLOOR</sub> ) =	user	ft <sup>3</sup>
Depth of Main Basin (H <sub>MAIN</sub> ) =	user	ft
Length of Main Basin (L <sub>MAIN</sub> ) =	user	ft
Width of Main Basin (W <sub>MAIN</sub> ) =	user	ft
Area of Main Basin (A <sub>MAIN</sub> ) =	user	ft <sup>2</sup>
Volume of Main Basin (V <sub>MAIN</sub> ) =	user	ft <sup>3</sup>
Calculated Total Basin Volume (V <sub>total</sub> ) =	user	acre-feet

Depth Increment =		ft									
Stage - Storage Description	Stage (ft)	Optional Override Stage (ft)	Length (ft)	Width (ft)	Area (ft <sup>2</sup> )	Optional Override Area (ft <sup>2</sup> )	Area (acre)	Volume (ft <sup>3</sup> )	Volume (ac-ft)		
Media Surface	--	0.00	--	--	--	2,450	0.056				
6365	--	0.55	--	--	--	3,196	0.073	1,553	0.036		
6366	--	1.55	--	--	--	4,546	0.104	5,424	0.125		
6367	--	2.55	--	--	--	6,018	0.138	10,706	0.246		
6368	--	3.55	--	--	--	7,623	0.175	17,526	0.402		

# DETENTION BASIN STAGE-STORAGE TABLE BUILDER

*MHFD-Detention, Version 4.02 (February 2020)*




Define "Remodeled Proposed Conditions."  
 How is this different for the other calcs for this same pond shown on pdf page 60 above?  
 Please discuss in the FDR text above.

## DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention Version 4.02 (February 2020)*

**Project: CLAREMONT COMMERCIAL FILING NO.2**  
**Basin ID: WQCV POND 2 (Remodeled Proposed Conditions)**



	Estimated Stage (ft)	Estimated Volume (ac-ft)	Outlet Type
Zone 1 (WQCV)	1.77	0.148	Filtration Media
Zone 2 (100-year)	#VALUE!	0.838	Weir&Pipe (Restrict)
Zone 3			
<b>Total (all zones)</b>		<b>0.986</b>	

User Input: Orifice at Underdrain Outlet (typically used to drain WQCV in a Filtration BMP)

Underdrain Orifice Invert Depth =  ft (distance below the filtration media surface)  
 Underdrain Orifice Diameter =  inches

Calculated Parameters for Underdrain  
 Underdrain Orifice Area =  ft<sup>2</sup>  
 Underdrain Orifice Centroid =  feet

User Input: Orifice Plate with one or more orifices or Elliptical Slot Weir (typically used to drain WQCV and/or EURV in a sedimentation BMP)

Invert of Lowest Orifice =  ft (relative to basin bottom at Stage = 0 ft)  
 Depth at top of Zone using Orifice Plate =  ft (relative to basin bottom at Stage = 0 ft)  
 Orifice Plate: Orifice Vertical Spacing =  inches  
 Orifice Plate: Orifice Area per Row =  inches

Calculated Parameters for Plate  
 WQ Orifice Area per Row =  ft<sup>2</sup>  
 Elliptical Half-Width =  feet  
 Elliptical Slot Centroid =  feet  
 Elliptical Slot Area =  ft<sup>2</sup>

User Input: Stage and Total Area of Each Orifice Row (numbered from lowest to highest)

	Row 1 (optional)	Row 2 (optional)	Row 3 (optional)	Row 4 (optional)	Row 5 (optional)	Row 6 (optional)	Row 7 (optional)	Row 8 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	Row 9 (optional)	Row 10 (optional)	Row 11 (optional)	Row 12 (optional)	Row 13 (optional)	Row 14 (optional)	Row 15 (optional)	Row 16 (optional)
Stage of Orifice Centroid (ft)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Orifice Area (sq. inches)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

User Input: Vertical Orifice (Circular or Rectangular)

Invert of Vertical Orifice =   ft (relative to basin bottom at Stage = 0 ft)  
 Depth at top of Zone using Vertical Orifice =   ft (relative to basin bottom at Stage = 0 ft)  
 Vertical Orifice Diameter =   inches

Calculated Parameters for Vertical Orifice  
 Vertical Orifice Area =   ft<sup>2</sup>  
 Vertical Orifice Centroid =   feet

User Input: Overflow Weir (Dropbox with Flat or Sloped Grate and Outlet Pipe OR Rectangular/Trapezoidal Weir (and No Outlet Pipe)

Overflow Weir Front Edge Height, H<sub>o</sub> =   ft (relative to basin bottom at Stage = 0 ft)  
 Overflow Weir Front Edge Length =   feet  
 Overflow Weir Grate Slope =   H:V  
 Horiz. Length of Weir Sides =   feet  
 Overflow Grate Open Area % =   %, grate open area/total area  
 Debris Clogging % =   %

Calculated Parameters for Overflow Weir  
 Height of Grate Upper Edge, H<sub>u</sub> =   feet  
 Overflow Weir Slope Length =   feet  
 Grate Open Area / 100-yr Orifice Area =    
 Overflow Grate Open Area w/o Debris =   ft<sup>2</sup>  
 Overflow Grate Open Area w/ Debris =   ft<sup>2</sup>

User Input: Outlet Pipe w/ Flow Restriction Plate (Circular Orifice, Restrictor Plate, or Rectangular Orifice)

Depth to Invert of Outlet Pipe =   ft (distance below basin bottom at Stage = 0 ft)  
 Outlet Pipe Diameter =   inches  
 Restrictor Plate Height Above Pipe Invert =   inches

Calculated Parameters for Outlet Pipe w/ Flow Restriction Plate  
 Outlet Orifice Area =   ft<sup>2</sup>  
 Outlet Orifice Centroid =   feet  
 Half-Central Angle of Restrictor Plate on Pipe =   radians

User Input: Emergency Spillway (Rectangular or Trapezoidal)

Spillway Invert Stage =   ft (relative to basin bottom at Stage = 0 ft)  
 Spillway Crest Length =   feet  
 Spillway End Slopes =   H:V  
 Freeboard above Max Water Surface =   feet

Calculated Parameters for Spillway  
 Spillway Design Flow Depth =   feet  
 Stage at Top of Freeboard =   feet  
 Basin Area at Top of Freeboard =   acres  
 Basin Volume at Top of Freeboard =   acre-ft




### Routed Hydrograph Results

*The user can override the default CUHP hydrographs and runoff volumes by entering new values in the Inflow Hydrographs table (Columns W through AF).*

	WQCV	EURV	2 Year	5 Year	10 Year	25 Year	50 Year	100 Year	500 Year
Design Storm Return Period	N/A	N/A	1.19	1.50	1.75	2.00	2.25	2.52	2.53
One-Hour Rainfall Depth (in)	0.148	0.619	0.541	0.734	0.897	1.095	1.267	1.474	1.481
CUHP Runoff Volume (acre-ft)	N/A	N/A	0.541	0.734	0.897	1.095	1.267	1.474	1.481
Inflow Hydrograph Volume (acre-ft)	N/A	N/A	1.1	3.2	4.7	8.3	10.4	13.0	13.1
CUHP Predevelopment Peak Q (cfs)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
OPTIONAL Override Predevelopment Peak Q (cfs)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Predevelopment Unit Peak Flow, q (cfs/acre)	N/A	N/A	0.14	0.37	0.56	0.99	1.24	1.55	1.56
Peak Inflow Q (cfs)	N/A	N/A	11.0	14.8	17.5	21.7	25.3	29.7	29.9
Peak Outflow Q (cfs)	0.2	42.6	8.3	13.7	16.0	22.5	23.0	23.8	23.8
Ratio Peak Outflow to Predevelopment Q	N/A	N/A	N/A	4.3	3.4	2.7	2.2	1.8	1.8
Structure Controlling Flow	Overflow Weir 1	Outlet Plate 1	Overflow Weir 1	Overflow Weir 1	Overflow Weir 1	Outlet Plate 1	Outlet Plate 1	Outlet Plate 1	Outlet Plate 1
Max Velocity through Gate 1 (fps)	0.01	1.59	0.57	0.9	1.1	1.6	1.6	1.7	1.7
Max Velocity through Gate 2 (fps)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Time to Drain 97% of Inflow Volume (hours)	13	12	14	14	13	13	12	12	12
Time to Drain 99% of Inflow Volume (hours)	13	13	15	15	15	15	15	14	14
Maximum Ponding Depth (ft)	1.77	2.56	2.08	2.21	2.27	2.41	2.61	2.95	2.96
Area at Maximum Ponding Depth (acres)	0.11	0.14	0.12	0.13	0.13	0.13	0.14	0.15	0.15
Maximum Volume Stored (acre-ft)	0.148	0.246	0.185	0.201	0.207	0.227	0.253	0.302	0.304

# DETENTION BASIN OUTLET STRUCTURE DESIGN

*MHFD-Detention, Version 4.00 (December 2019)*



S-A-V-D Chart Axis Override	X-axis	Left Y-Axis	Right Y-Axis
minimum bound			
maximum bound			



## Design Procedure Form: Sand Filter (SF)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

**Designer:** Darin Moffett  
**Company:** M&S Civil Consultants  
**Date:** February 23, 2023  
**Project:** Lot 1 Pond 1 (Future)  
**Location:** Lot 1 - Claremont Buiness Park 2 - Filing No. 2

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, <math>I_p</math> (100% if all paved and roofed areas upstream of sand filter)</p> <p>B) Tributary Area's Imperviousness Ratio (<math>i = I_p/100</math>)</p> <p>C) Water Quality Capture Volume (WQCV) Based on 12-hour Drain Time <math>WQCV = 0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)</math></p> <p>D) Contributing Watershed Area (including sand filter area)</p> <p>E) Water Quality Capture Volume (WQCV) Design Volume <math>V_{WQCV} = WQCV / 12 * Area</math></p> <p>F) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p>	<p><math>I_p = </math> <input type="text" value="83.4"/> %</p> <p><math>i = </math> <input type="text" value="0.834"/></p> <p>WQCV = <input type="text" value="0.28"/> watershed inches</p> <p>Area = <input type="text" value="74,372"/> sq ft</p> <p><math>V_{WQCV} = </math> <input type="text" value=""/></p> <p><math>d_e = </math> <input type="text" value="0.60"/> in</p> <p><math>V_{WQCV \text{ OTHER}} = </math> <input type="text" value="2,426"/> cu ft</p> <p><math>V_{WQCV \text{ USER}} = </math> <input type="text" value=""/></p>
<p>2. Basin Geometry</p> <p>A) WQCV Depth</p> <p>B) Sand Filter Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred). Use "0" if sand filter has vertical walls.</p> <p>C) Minimum Filter Area (Flat Surface Area)</p> <p>D) Actual Filter Area</p> <p>E) Volume Provided</p>	<p><math>D_{WQCV} = </math> <input type="text" value="1.2"/> ft</p> <p><math>Z = </math> <input type="text" value="4.00"/> ft / ft</p> <p><math>A_{Min} = </math> <input type="text" value="775"/> sq ft</p> <p><math>A_{Actual} = </math> <input type="text" value="873"/> sq ft</p> <p><math>V_T = </math> <input type="text" value=""/></p>
<p>3. Filter Material</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> 18" CDOT Class B or C Filter Material</p> <p><input type="radio"/> Other (Explain): _____</p> <p>_____</p> <p>_____</p>
<p>4. Underdrain System</p> <p>A) Are underdrains provided?</p> <p>B) Underdrain system orifice diameter for 12 hour drain time</p> <p style="margin-left: 20px;">i) Distance From Lowest Elevation of the Storage Volume to the Center of the Orifice</p> <p style="margin-left: 20px;">ii) Volume to Drain in 12 Hours</p> <p style="margin-left: 20px;">iii) Orifice Diameter, 3/8" Minimum</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> YES</p> <p><input type="radio"/> NO</p> <p><math>y = </math> <input type="text" value="2.5"/> ft</p> <p><math>Vol_{12} = </math> <input type="text" value="2,426"/> cu ft</p> <p><math>D_o = </math> <input type="text" value="1 1/16"/> in</p>

Design Procedure Form: Sand Filter (SF)

Sheet 2 of 2

Designer: Darin Moffett  
Company: M&S Civil Consultants  
Date: February 23, 2023  
Project: Lo1 Pond 1 (Future)  
Location: Lot 1 - Claremont Buisness Park 2 - Filing No. 2

5. Impermeable Geomembrane Liner and Geotextile Separator Fabric

A) Is an impermeable liner provided due to proximity of structures or groundwater contamination?

Choose One

YES  NO

6. Inlet / Outlet Works

A) Describe the type of energy dissipation at inlet points and means of conveying flows in excess of the WQCV through the outlet

TBD  
Concrete Outlet Box with Unrestricted 18" RCP  
\_\_\_\_\_  
\_\_\_\_\_

Notes: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_



## Design Procedure Form: Sand Filter (SF)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

**Designer:** Darin Moffett  
**Company:** M&S Civil Consultants  
**Date:** February 23, 2023  
**Project:** Lot 2 Pond 2 (Future)  
**Location:** Lot 2 - Claremont Buiness Park 2 - Filing No. 2

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, <math>I_p</math> (100% if all paved and roofed areas upstream of sand filter)</p> <p>B) Tributary Area's Imperviousness Ratio (<math>i = I_p/100</math>)</p> <p>C) Water Quality Capture Volume (WQCV) Based on 12-hour Drain Time <math>WQCV = 0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)</math></p> <p>D) Contributing Watershed Area (including sand filter area)</p> <p>E) Water Quality Capture Volume (WQCV) Design Volume <math>V_{WQCV} = WQCV / 12 * Area</math></p> <p>F) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p>	<p><math>I_p = </math> <input style="width: 50px;" type="text" value="77.9"/> %</p> <p><math>i = </math> <input style="width: 50px;" type="text" value="0.779"/></p> <p>WQCV = <input style="width: 50px;" type="text" value="0.25"/> watershed inches</p> <p>Area = <input style="width: 50px;" type="text" value="38,960"/> sq ft</p> <p><math>V_{WQCV} = </math> <input style="width: 50px;" type="text" value=""/></p> <p><math>d_e = </math> <input style="width: 50px;" type="text" value="0.60"/> in</p> <p><math>V_{WQCV \text{ OTHER}} = </math> <input style="width: 50px;" type="text" value="1,144"/> cu ft</p> <p><math>V_{WQCV \text{ USER}} = </math> <input style="width: 50px;" type="text" value=""/></p>
<p>2. Basin Geometry</p> <p>A) WQCV Depth</p> <p>B) Sand Filter Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred). Use "0" if sand filter has vertical walls.</p> <p>C) Minimum Filter Area (Flat Surface Area)</p> <p>D) Actual Filter Area</p> <p>E) Volume Provided</p>	<p><math>D_{WQCV} = </math> <input style="width: 50px;" type="text" value="1.0"/> ft</p> <p><math>Z = </math> <input style="width: 50px;" type="text" value="4.00"/> ft / ft</p> <p><math>A_{Min} = </math> <input style="width: 50px;" type="text" value="379"/> sq ft</p> <p><math>A_{Actual} = </math> <input style="width: 50px;" type="text" value="513"/> sq ft</p> <p><math>V_T = </math> <input style="width: 50px;" type="text" value=""/></p>
<p>3. Filter Material</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> 18" CDOT Class B or C Filter Material</p> <p><input type="radio"/> Other (Explain): _____</p> <p>_____</p> <p>_____</p>
<p>4. Underdrain System</p> <p>A) Are underdrains provided?</p> <p>B) Underdrain system orifice diameter for 12 hour drain time</p> <p style="margin-left: 20px;">i) Distance From Lowest Elevation of the Storage Volume to the Center of the Orifice</p> <p style="margin-left: 20px;">ii) Volume to Drain in 12 Hours</p> <p style="margin-left: 20px;">iii) Orifice Diameter, 3/8" Minimum</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> YES</p> <p><input type="radio"/> NO</p> <p><math>y = </math> <input style="width: 50px;" type="text" value="2.5"/> ft</p> <p><math>Vol_{12} = </math> <input style="width: 50px;" type="text" value="1,144"/> cu ft</p> <p><math>D_o = </math> <input style="width: 50px;" type="text" value="3/4"/> in</p>

Design Procedure Form: Sand Filter (SF)

Sheet 2 of 2

Designer: Darin Moffett  
Company: M&S Civil Consultants  
Date: February 23, 2023  
Project: Lot 2 Pond 2 (Future)  
Location: Lot 2 - Claremont Buisness Park 2 - Filing No. 2

5. Impermeable Geomembrane Liner and Geotextile Separator Fabric

A) Is an impermeable liner provided due to proximity of structures or groundwater contamination?

Choose One

YES  NO

6. Inlet / Outlet Works

A) Describe the type of energy dissipation at inlet points and means of conveying flows in excess of the WQCV through the outlet

TBD  
Concrete Outlet Box with Unrestricted 18" RCP  
\_\_\_\_\_  
\_\_\_\_\_

Notes: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## Design Procedure Form: Sand Filter (SF)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

**Designer:** Darin Moffett  
**Company:** M&S Civil Consultants  
**Date:** February 23, 2023  
**Project:** Lot 2 Pond 3  
**Location:** Lot 2 - Claremont Buisness Park 2 - Filing No. 2

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, <math>I_p</math> (100% if all paved and roofed areas upstream of sand filter)</p> <p>B) Tributary Area's Imperviousness Ratio (<math>i = I_p/100</math>)</p> <p>C) Water Quality Capture Volume (WQCV) Based on 12-hour Drain Time <math>WQCV = 0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)</math></p> <p>D) Contributing Watershed Area (including sand filter area)</p> <p>E) Water Quality Capture Volume (WQCV) Design Volume <math>V_{WQCV} = WQCV / 12 * Area</math></p> <p>F) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p>	<p><math>I_p = </math> <input type="text" value="81.8"/> %</p> <p><math>i = </math> <input type="text" value="0.818"/></p> <p>WQCV = <input type="text" value="0.27"/> watershed inches</p> <p>Area = <input type="text" value="62,251"/> sq ft</p> <p><math>V_{WQCV} = </math> <input type="text" value=""/></p> <p><math>d_e = </math> <input type="text" value="0.60"/> in</p> <p><math>V_{WQCV \text{ OTHER}} = </math> <input type="text" value=""/> cu ft</p> <p><math>V_{WQCV \text{ USER}} = </math> <input type="text" value="1,393"/> cu ft</p>
<p>2. Basin Geometry</p> <p>A) WQCV Depth</p> <p>B) Sand Filter Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred). Use "0" if sand filter has vertical walls.</p> <p>C) Minimum Filter Area (Flat Surface Area)</p> <p>D) Actual Filter Area</p> <p>E) Volume Provided</p>	<p><math>D_{WQCV} = </math> <input type="text" value="1.3"/> ft</p> <p><math>Z = </math> <input type="text" value="4.00"/> ft / ft</p> <p><math>A_{Min} = </math> <input type="text" value="637"/> sq ft</p> <p><math>A_{Actual} = </math> <input type="text" value="784"/> sq ft</p> <p><math>V_T = </math> <input type="text" value=""/> cu ft</p>
<p>3. Filter Material</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> 18" CDOT Class B or C Filter Material</p> <p><input type="radio"/> Other (Explain): _____</p> <p>_____</p> <p>_____</p>
<p>4. Underdrain System</p> <p>A) Are underdrains provided?</p> <p>B) Underdrain system orifice diameter for 12 hour drain time</p> <p style="margin-left: 20px;">i) Distance From Lowest Elevation of the Storage Volume to the Center of the Orifice</p> <p style="margin-left: 20px;">ii) Volume to Drain in 12 Hours</p> <p style="margin-left: 20px;">iii) Orifice Diameter, 3/8" Minimum</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> YES</p> <p><input type="radio"/> NO</p> <p><math>y = </math> <input type="text" value="2.5"/> ft</p> <p><math>Vol_{12} = </math> <input type="text" value="1,393"/> cu ft</p> <p><math>D_o = </math> <input type="text" value="13/16"/> in</p>

Design Procedure Form: Sand Filter (SF)

Sheet 2 of 2

Designer: Darin Moffett  
Company: M&S Civil Consultants  
Date: February 23, 2023  
Project: Lot 2 Pond 3  
Location: Lot 2 - Claremont Buisness Park 2 - Filing No. 2

5. Impermeable Geomembrane Liner and Geotextile Separator Fabric

A) Is an impermeable liner provided due to proximity of structures or groundwater contamination?

Choose One

YES  NO

6. Inlet / Outlet Works

A) Describe the type of energy dissipation at inlet points and means of conveying flows in excess of the WQCV through the outlet

TBD  
Concrete Outlet Box with Restricted 18" RCP  
\_\_\_\_\_  
\_\_\_\_\_

Notes: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## Design Procedure Form: Sand Filter (SF)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

**Designer:** Darin Moffett  
**Company:** M&S Civil Consultants  
**Date:** February 23, 2023  
**Project:** Lot 3 Pond 4  
**Location:** Lot 2 - Claremont Buisness Park 2 - Filing No. 2

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, <math>I_p</math> (100% if all paved and roofed areas upstream of sand filter)</p> <p>B) Tributary Area's Imperviousness Ratio (<math>i = I_p/100</math>)</p> <p>C) Water Quality Capture Volume (WQCV) Based on 12-hour Drain Time <math>WQCV = 0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)</math></p> <p>D) Contributing Watershed Area (including sand filter area)</p> <p>E) Water Quality Capture Volume (WQCV) Design Volume <math>V_{WQCV} = WQCV / 12 * Area</math></p> <p>F) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p>	<p><math>I_p = </math> <input type="text" value="90.0"/> %</p> <p><math>i = </math> <input type="text" value="0.900"/></p> <p>WQCV = <input type="text" value="0.32"/> watershed inches</p> <p>Area = <input type="text" value="12,955"/> sq ft</p> <p><math>V_{WQCV} = </math> <input type="text" value=""/> cu ft</p> <p><math>d_e = </math> <input type="text" value="0.60"/> in</p> <p><math>V_{WQCV OTHER} = </math> <input type="text" value=""/> cu ft</p> <p><math>V_{WQCV USER} = </math> <input type="text" value="349"/> cu ft</p>
<p>2. Basin Geometry</p> <p>A) WQCV Depth</p> <p>B) Sand Filter Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred). Use "0" if sand filter has vertical walls.</p> <p>C) Minimum Filter Area (Flat Surface Area)</p> <p>D) Actual Filter Area</p> <p>E) Volume Provided</p>	<p><math>D_{WQCV} = </math> <input type="text" value="0.8"/> ft</p> <p><math>Z = </math> <input type="text" value="4.00"/> ft / ft</p> <p><math>A_{Min} = </math> <input type="text" value="146"/> sq ft</p> <p><math>A_{Actual} = </math> <input type="text" value="288"/> sq ft</p> <p><math>V_T = </math> <input type="text" value="350"/> cu ft</p>
<p>3. Filter Material</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> 18" CDOT Class B or C Filter Material</p> <p><input type="radio"/> Other (Explain): _____</p> <p>_____</p> <p>_____</p>
<p>4. Underdrain System</p> <p>A) Are underdrains provided?</p> <p>B) Underdrain system orifice diameter for 12 hour drain time</p> <p style="margin-left: 20px;">i) Distance From Lowest Elevation of the Storage Volume to the Center of the Orifice</p> <p style="margin-left: 20px;">ii) Volume to Drain in 12 Hours</p> <p style="margin-left: 20px;">iii) Orifice Diameter, 3/8" Minimum</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> YES</p> <p><input type="radio"/> NO</p> <p><math>y = </math> <input type="text" value="2.5"/> ft</p> <p><math>Vol_{12} = </math> <input type="text" value="349"/> cu ft</p> <p><math>D_o = </math> <input type="text" value="7/16"/> in</p>

Design Procedure Form: Sand Filter (SF)

Sheet 2 of 2

Designer: Darin Moffett  
Company: M&S Civil Consultants  
Date: February 23, 2023  
Project: Lot 3 Pond 4  
Location: Lot 2 - Claremont Buisness Park 2 - Filing No. 2

5. Impermeable Geomembrane Liner and Geotextile Separator Fabric

A) Is an impermeable liner provided due to proximity of structures or groundwater contamination?

Choose One

YES  NO

6. Inlet / Outlet Works

A) Describe the type of energy dissipation at inlet points and means of conveying flows in excess of the WQCV through the outlet

TBD  
Concrete Outlet Box with Unrestricted 18" RCP  
\_\_\_\_\_  
\_\_\_\_\_

Notes: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## Design Procedure Form: Sand Filter (SF)

UD-BMP (Version 3.07, March 2018)

Sheet 1 of 2

**Designer:** Darin Moffett  
**Company:** M&S Civil Consultants  
**Date:** February 23, 2023  
**Project:** Lot 3 Pond 5  
**Location:** Lot 2 - Claremont Buisness Park 2 - Filing No. 2

<p>1. Basin Storage Volume</p> <p>A) Effective Imperviousness of Tributary Area, <math>I_p</math> (100% if all paved and roofed areas upstream of sand filter)</p> <p>B) Tributary Area's Imperviousness Ratio (<math>i = I_p/100</math>)</p> <p>C) Water Quality Capture Volume (WQCV) Based on 12-hour Drain Time <math>WQCV = 0.8 * (0.91 * i^3 - 1.19 * i^2 + 0.78 * i)</math></p> <p>D) Contributing Watershed Area (including sand filter area)</p> <p>E) Water Quality Capture Volume (WQCV) Design Volume <math>V_{WQCV} = WQCV / 12 * Area</math></p> <p>F) For Watersheds Outside of the Denver Region, Depth of Average Runoff Producing Storm</p> <p>G) For Watersheds Outside of the Denver Region, Water Quality Capture Volume (WQCV) Design Volume</p> <p>H) User Input of Water Quality Capture Volume (WQCV) Design Volume (Only if a different WQCV Design Volume is desired)</p>	<p><math>I_p = </math> <input type="text" value="90.0"/> %</p> <p><math>i = </math> <input type="text" value="0.900"/></p> <p>WQCV = <input type="text" value="0.32"/> watershed inches</p> <p>Area = <input type="text" value="50,180"/> sq ft</p> <p><math>V_{WQCV} = </math> <input type="text" value=""/> cu ft</p> <p><math>d_e = </math> <input type="text" value="0.60"/> in</p> <p><math>V_{WQCV \text{ OTHER}} = </math> <input type="text" value="1,874"/> cu ft</p> <p><math>V_{WQCV \text{ USER}} = </math> <input type="text" value=""/> cu ft</p>
<p>2. Basin Geometry</p> <p>A) WQCV Depth</p> <p>B) Sand Filter Side Slopes (Horizontal distance per unit vertical, 4:1 or flatter preferred). Use "0" if sand filter has vertical walls.</p> <p>C) Minimum Filter Area (Flat Surface Area)</p> <p>D) Actual Filter Area</p> <p>E) Volume Provided</p>	<p><math>D_{WQCV} = </math> <input type="text" value="0.8"/> ft</p> <p><math>Z = </math> <input type="text" value="4.00"/> ft / ft</p> <p><math>A_{Min} = </math> <input type="text" value="565"/> sq ft</p> <p><math>A_{Actual} = </math> <input type="text" value="887"/> sq ft</p> <p><math>V_T = </math> <input type="text" value=""/> cu ft</p>
<p>3. Filter Material</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> 18" CDOT Class B or C Filter Material</p> <p><input type="radio"/> Other (Explain): _____</p> <p>_____</p> <p>_____</p>
<p>4. Underdrain System</p> <p>A) Are underdrains provided?</p> <p>B) Underdrain system orifice diameter for 12 hour drain time</p> <p style="margin-left: 20px;">i) Distance From Lowest Elevation of the Storage Volume to the Center of the Orifice</p> <p style="margin-left: 20px;">ii) Volume to Drain in 12 Hours</p> <p style="margin-left: 20px;">iii) Orifice Diameter, 3/8" Minimum</p>	<p>Choose One _____</p> <p><input checked="" type="radio"/> YES</p> <p><input type="radio"/> NO</p> <p><math>y = </math> <input type="text" value="2.5"/> ft</p> <p><math>Vol_{12} = </math> <input type="text" value="1,874"/> cu ft</p> <p><math>D_o = </math> <input type="text" value="15/16"/> in</p>

Design Procedure Form: Sand Filter (SF)

Sheet 2 of 2

Designer: Darin Moffett  
Company: M&S Civil Consultants  
Date: February 23, 2023  
Project: Lot 3 Pond 5  
Location: Lot 2 - Claremont Buisness Park 2 - Filing No. 2

5. Impermeable Geomembrane Liner and Geotextile Separator Fabric

A) Is an impermeable liner provided due to proximity of structures or groundwater contamination?

Choose One

YES  NO

6. Inlet / Outlet Works

A) Describe the type of energy dissipation at inlet points and means of conveying flows in excess of the WQCV through the outlet

TBD  
Concrete Outlet Box with Unrestricted 18" RCP  
\_\_\_\_\_  
\_\_\_\_\_

Notes: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_




**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing 2 (Proposed Conditions)**

Inlet ID: **Inlet 1 (DP5)**



**Gutter Geometry:**

Maximum Allowable Width for Spread Behind Curb  
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)  
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

Height of Curb at Gutter Flow Line  
 Distance from Curb Face to Street Crown  
 Gutter Width  
 Street Transverse Slope  
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)  
 Street Longitudinal Slope - Enter 0 for sump condition  
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

Max. Allowable Spread for Minor & Major Storm  
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm  
 Check boxes are not applicable in SUMP conditions

MINOR STORM Allowable Capacity is not applicable to Sump Condition  
 MAJOR STORM Allowable Capacity is not applicable to Sump Condition

$T_{BACK}$ =	7.5	ft
$S_{BACK}$ =	0.020	ft/ft
$n_{BACK}$ =	0.020	


$H_{CURB}$ =	6.00	inches
$T_{CROWN}$ =	18.0	ft
$W$ =	2.00	ft
$S_x$ =	0.020	ft/ft
$S_w$ =	0.083	ft/ft
$S_0$ =	0.000	ft/ft
$n_{STREET}$ =	0.015	

	Minor Storm	Major Storm	
$T_{MAX}$ =	15.8	18.0	ft
$d_{MAX}$ =	4.6	7.8	inches
	<input type="checkbox"/>	<input type="checkbox"/>	

	Minor Storm	Major Storm	
$Q_{allow}$ =	SUMP	SUMP	cfs

# INLET IN A SUMP OR SAG LOCATION


MHFD-Inlet, Version 5.02 (August 2022)



Design Information (Input)	MINOR		MAJOR																																																																																																																																													
Type of Inlet	CDOT Type R Curb Opening																																																																																																																																															
Local Depression (additional to continuous gutter depression 'a' from above)																																																																																																																																																
Number of Unit Inlets (Grate or Curb Opening)	1																																																																																																																																															
Water Depth at Flowline (outside of local depression)																																																																																																																																																
<b>Grate Information</b>																																																																																																																																																
Length of a Unit Grate																																																																																																																																																
Width of a Unit Grate																																																																																																																																																
Open Area Ratio for a Grate (typical values 0.15-0.90)																																																																																																																																																
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)																																																																																																																																																
Grate Weir Coefficient (typical value 2.15 - 3.60)																																																																																																																																																
Grate Orifice Coefficient (typical value 0.60 - 0.80)																																																																																																																																																
<b>Curb Opening Information</b>																																																																																																																																																
Length of a Unit Curb Opening																																																																																																																																																
Height of Vertical Curb Opening in Inches																																																																																																																																																
Height of Curb Orifice Throat in Inches																																																																																																																																																
Angle of Throat (see USDCM Figure ST-5)																																																																																																																																																
Side Width for Depression Pan (typically the gutter width of 2 feet)																																																																																																																																																
Clogging Factor for a Single Curb Opening (typical value 0.10)																																																																																																																																																
Curb Opening Weir Coefficient (typical value 2.3-3.7)																																																																																																																																																
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)																																																																																																																																																
<b>Low Head Performance Reduction (Calculated)</b>																																																																																																																																																
Depth for Grate Midwidth																																																																																																																																																
Depth for Curb Opening Weir Equation																																																																																																																																																
Grated Inlet Performance Reduction Factor for Long Inlets																																																																																																																																																
Curb Opening Performance Reduction Factor for Long Inlets																																																																																																																																																
Combination Inlet Performance Reduction Factor for Long Inlets																																																																																																																																																
Total Inlet Interception Capacity (assumes clogged condition)																																																																																																																																																
<b>Inlet Capacity IS GOOD for Minor and Major Storms (&gt;Q Peak)</b>																																																																																																																																																
<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Type =</td> <td colspan="2" style="text-align: center;">CDOT Type R Curb Opening</td> <td></td> </tr> <tr> <td>a<sub>local</sub> =</td> <td style="text-align: center;">3.00</td> <td style="text-align: center;">3.00</td> <td>inches</td> </tr> <tr> <td>No =</td> <td style="text-align: center;">1</td> <td style="text-align: center;">1</td> <td></td> </tr> <tr> <td>Ponding Depth =</td> <td style="text-align: center;">4.6</td> <td style="text-align: center;">5.8</td> <td>inches</td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>feet</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>feet</td> </tr> <tr> <td>A<sub>ratio</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>f</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (C) =</td> <td style="text-align: center;">5.00</td> <td style="text-align: center;">5.00</td> <td>feet</td> </tr> <tr> <td>H<sub>vert</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>H<sub>throat</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>Theta =</td> <td style="text-align: center;">63.40</td> <td style="text-align: center;">63.40</td> <td>degrees</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">2.00</td> <td style="text-align: center;">2.00</td> <td>feet</td> </tr> <tr> <td>C<sub>f</sub> (C) =</td> <td style="text-align: center;">0.10</td> <td style="text-align: center;">0.10</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (C) =</td> <td style="text-align: center;">3.60</td> <td style="text-align: center;">3.60</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (C) =</td> <td style="text-align: center;">0.67</td> <td style="text-align: center;">0.67</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td></tr></tbody></table></td></tr></tbody></table>						MINOR	MAJOR		Type =	CDOT Type R Curb Opening			a <sub>local</sub> =	3.00	3.00	inches	No =	1	1		Ponding Depth =	4.6	5.8	inches	<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>feet</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>feet</td> </tr> <tr> <td>A<sub>ratio</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>f</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (C) =</td> <td style="text-align: center;">5.00</td> <td style="text-align: center;">5.00</td> <td>feet</td> </tr> <tr> <td>H<sub>vert</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>H<sub>throat</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>Theta =</td> <td style="text-align: center;">63.40</td> <td style="text-align: center;">63.40</td> <td>degrees</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">2.00</td> <td style="text-align: center;">2.00</td> <td>feet</td> </tr> <tr> <td>C<sub>f</sub> (C) =</td> <td style="text-align: center;">0.10</td> <td style="text-align: center;">0.10</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (C) =</td> <td style="text-align: center;">3.60</td> <td style="text-align: center;">3.60</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (C) =</td> <td style="text-align: center;">0.67</td> <td style="text-align: center;">0.67</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td></tr></tbody></table>						MINOR	MAJOR		L <sub>o</sub> (G) =	N/A	N/A	feet	W <sub>o</sub> =	N/A	N/A	feet	A <sub>ratio</sub> =	N/A	N/A		C <sub>f</sub> (G) =	N/A	N/A		C <sub>w</sub> (G) =	N/A	N/A		C <sub>o</sub> (G) =	N/A	N/A		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (C) =</td> <td style="text-align: center;">5.00</td> <td style="text-align: center;">5.00</td> <td>feet</td> </tr> <tr> <td>H<sub>vert</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>H<sub>throat</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>Theta =</td> <td style="text-align: center;">63.40</td> <td style="text-align: center;">63.40</td> <td>degrees</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">2.00</td> <td style="text-align: center;">2.00</td> <td>feet</td> </tr> <tr> <td>C<sub>f</sub> (C) =</td> <td style="text-align: center;">0.10</td> <td style="text-align: center;">0.10</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (C) =</td> <td style="text-align: center;">3.60</td> <td style="text-align: center;">3.60</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (C) =</td> <td style="text-align: center;">0.67</td> <td style="text-align: center;">0.67</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		L <sub>o</sub> (C) =	5.00	5.00	feet	H <sub>vert</sub> =	6.00	6.00	inches	H <sub>throat</sub> =	6.00	6.00	inches	Theta =	63.40	63.40	degrees	W <sub>o</sub> =	2.00	2.00	feet	C <sub>f</sub> (C) =	0.10	0.10		C <sub>w</sub> (C) =	3.60	3.60		C <sub>o</sub> (C) =	0.67	0.67		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		d <sub>grate</sub> =	N/A	N/A	ft	d <sub>curth</sub> =	0.22	0.32	ft	RF <sub>grate</sub> =	N/A	N/A		RF <sub>curth</sub> =	1.00	1.00		RF <sub>combination</sub> =	N/A	N/A		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table>						MINOR	MAJOR		Q <sub>s</sub> =	2.8	5.0	cfs	Q <sub>PEAK REQUIRED</sub> =	1.2	2.2	cfs
	MINOR	MAJOR																																																																																																																																														
Type =	CDOT Type R Curb Opening																																																																																																																																															
a <sub>local</sub> =	3.00	3.00	inches																																																																																																																																													
No =	1	1																																																																																																																																														
Ponding Depth =	4.6	5.8	inches																																																																																																																																													
<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>feet</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>feet</td> </tr> <tr> <td>A<sub>ratio</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>f</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (G) =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (C) =</td> <td style="text-align: center;">5.00</td> <td style="text-align: center;">5.00</td> <td>feet</td> </tr> <tr> <td>H<sub>vert</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>H<sub>throat</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>Theta =</td> <td style="text-align: center;">63.40</td> <td style="text-align: center;">63.40</td> <td>degrees</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">2.00</td> <td style="text-align: center;">2.00</td> <td>feet</td> </tr> <tr> <td>C<sub>f</sub> (C) =</td> <td style="text-align: center;">0.10</td> <td style="text-align: center;">0.10</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (C) =</td> <td style="text-align: center;">3.60</td> <td style="text-align: center;">3.60</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (C) =</td> <td style="text-align: center;">0.67</td> <td style="text-align: center;">0.67</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td></tr></tbody></table>						MINOR	MAJOR		L <sub>o</sub> (G) =	N/A	N/A	feet	W <sub>o</sub> =	N/A	N/A	feet	A <sub>ratio</sub> =	N/A	N/A		C <sub>f</sub> (G) =	N/A	N/A		C <sub>w</sub> (G) =	N/A	N/A		C <sub>o</sub> (G) =	N/A	N/A		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (C) =</td> <td style="text-align: center;">5.00</td> <td style="text-align: center;">5.00</td> <td>feet</td> </tr> <tr> <td>H<sub>vert</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>H<sub>throat</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>Theta =</td> <td style="text-align: center;">63.40</td> <td style="text-align: center;">63.40</td> <td>degrees</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">2.00</td> <td style="text-align: center;">2.00</td> <td>feet</td> </tr> <tr> <td>C<sub>f</sub> (C) =</td> <td style="text-align: center;">0.10</td> <td style="text-align: center;">0.10</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (C) =</td> <td style="text-align: center;">3.60</td> <td style="text-align: center;">3.60</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (C) =</td> <td style="text-align: center;">0.67</td> <td style="text-align: center;">0.67</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		L <sub>o</sub> (C) =	5.00	5.00	feet	H <sub>vert</sub> =	6.00	6.00	inches	H <sub>throat</sub> =	6.00	6.00	inches	Theta =	63.40	63.40	degrees	W <sub>o</sub> =	2.00	2.00	feet	C <sub>f</sub> (C) =	0.10	0.10		C <sub>w</sub> (C) =	3.60	3.60		C <sub>o</sub> (C) =	0.67	0.67		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		d <sub>grate</sub> =	N/A	N/A	ft	d <sub>curth</sub> =	0.22	0.32	ft	RF <sub>grate</sub> =	N/A	N/A		RF <sub>curth</sub> =	1.00	1.00		RF <sub>combination</sub> =	N/A	N/A		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table>						MINOR	MAJOR		Q <sub>s</sub> =	2.8	5.0	cfs	Q <sub>PEAK REQUIRED</sub> =	1.2	2.2	cfs																									
	MINOR	MAJOR																																																																																																																																														
L <sub>o</sub> (G) =	N/A	N/A	feet																																																																																																																																													
W <sub>o</sub> =	N/A	N/A	feet																																																																																																																																													
A <sub>ratio</sub> =	N/A	N/A																																																																																																																																														
C <sub>f</sub> (G) =	N/A	N/A																																																																																																																																														
C <sub>w</sub> (G) =	N/A	N/A																																																																																																																																														
C <sub>o</sub> (G) =	N/A	N/A																																																																																																																																														
<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>L<sub>o</sub> (C) =</td> <td style="text-align: center;">5.00</td> <td style="text-align: center;">5.00</td> <td>feet</td> </tr> <tr> <td>H<sub>vert</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>H<sub>throat</sub> =</td> <td style="text-align: center;">6.00</td> <td style="text-align: center;">6.00</td> <td>inches</td> </tr> <tr> <td>Theta =</td> <td style="text-align: center;">63.40</td> <td style="text-align: center;">63.40</td> <td>degrees</td> </tr> <tr> <td>W<sub>o</sub> =</td> <td style="text-align: center;">2.00</td> <td style="text-align: center;">2.00</td> <td>feet</td> </tr> <tr> <td>C<sub>f</sub> (C) =</td> <td style="text-align: center;">0.10</td> <td style="text-align: center;">0.10</td> <td></td> </tr> <tr> <td>C<sub>w</sub> (C) =</td> <td style="text-align: center;">3.60</td> <td style="text-align: center;">3.60</td> <td></td> </tr> <tr> <td>C<sub>o</sub> (C) =</td> <td style="text-align: center;">0.67</td> <td style="text-align: center;">0.67</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		L <sub>o</sub> (C) =	5.00	5.00	feet	H <sub>vert</sub> =	6.00	6.00	inches	H <sub>throat</sub> =	6.00	6.00	inches	Theta =	63.40	63.40	degrees	W <sub>o</sub> =	2.00	2.00	feet	C <sub>f</sub> (C) =	0.10	0.10		C <sub>w</sub> (C) =	3.60	3.60		C <sub>o</sub> (C) =	0.67	0.67		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		d <sub>grate</sub> =	N/A	N/A	ft	d <sub>curth</sub> =	0.22	0.32	ft	RF <sub>grate</sub> =	N/A	N/A		RF <sub>curth</sub> =	1.00	1.00		RF <sub>combination</sub> =	N/A	N/A		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table>						MINOR	MAJOR		Q <sub>s</sub> =	2.8	5.0	cfs	Q <sub>PEAK REQUIRED</sub> =	1.2	2.2	cfs																																																										
	MINOR	MAJOR																																																																																																																																														
L <sub>o</sub> (C) =	5.00	5.00	feet																																																																																																																																													
H <sub>vert</sub> =	6.00	6.00	inches																																																																																																																																													
H <sub>throat</sub> =	6.00	6.00	inches																																																																																																																																													
Theta =	63.40	63.40	degrees																																																																																																																																													
W <sub>o</sub> =	2.00	2.00	feet																																																																																																																																													
C <sub>f</sub> (C) =	0.10	0.10																																																																																																																																														
C <sub>w</sub> (C) =	3.60	3.60																																																																																																																																														
C <sub>o</sub> (C) =	0.67	0.67																																																																																																																																														
<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>d<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td>ft</td> </tr> <tr> <td>d<sub>curth</sub> =</td> <td style="text-align: center;">0.22</td> <td style="text-align: center;">0.32</td> <td>ft</td> </tr> <tr> <td>RF<sub>grate</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td>RF<sub>curth</sub> =</td> <td style="text-align: center;">1.00</td> <td style="text-align: center;">1.00</td> <td></td> </tr> <tr> <td>RF<sub>combination</sub> =</td> <td style="text-align: center;">N/A</td> <td style="text-align: center;">N/A</td> <td></td> </tr> <tr> <td colspan="5" style="text-align: center;"> <table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table> </td> </tr> </tbody> </table>						MINOR	MAJOR		d <sub>grate</sub> =	N/A	N/A	ft	d <sub>curth</sub> =	0.22	0.32	ft	RF <sub>grate</sub> =	N/A	N/A		RF <sub>curth</sub> =	1.00	1.00		RF <sub>combination</sub> =	N/A	N/A		<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table>						MINOR	MAJOR		Q <sub>s</sub> =	2.8	5.0	cfs	Q <sub>PEAK REQUIRED</sub> =	1.2	2.2	cfs																																																																																																			
	MINOR	MAJOR																																																																																																																																														
d <sub>grate</sub> =	N/A	N/A	ft																																																																																																																																													
d <sub>curth</sub> =	0.22	0.32	ft																																																																																																																																													
RF <sub>grate</sub> =	N/A	N/A																																																																																																																																														
RF <sub>curth</sub> =	1.00	1.00																																																																																																																																														
RF <sub>combination</sub> =	N/A	N/A																																																																																																																																														
<table border="1" style="margin: auto;"> <thead> <tr> <th></th> <th style="text-align: center;">MINOR</th> <th style="text-align: center;">MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td>Q<sub>s</sub> =</td> <td style="text-align: center;">2.8</td> <td style="text-align: center;">5.0</td> <td>cfs</td> </tr> <tr> <td>Q<sub>PEAK REQUIRED</sub> =</td> <td style="text-align: center;">1.2</td> <td style="text-align: center;">2.2</td> <td>cfs</td> </tr> </tbody> </table>						MINOR	MAJOR		Q <sub>s</sub> =	2.8	5.0	cfs	Q <sub>PEAK REQUIRED</sub> =	1.2	2.2	cfs																																																																																																																																
	MINOR	MAJOR																																																																																																																																														
Q <sub>s</sub> =	2.8	5.0	cfs																																																																																																																																													
Q <sub>PEAK REQUIRED</sub> =	1.2	2.2	cfs																																																																																																																																													

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**  
 (Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


**Project:** Claremont Business Park 2 Filing 2 (Proposed Conditions)  
**Inlet ID:** Inlet 2 (DP5)



<b>Gutter Geometry:</b>									
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft								
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft								
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$								
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches								
Distance from Curb Face to Street Crown	$T_{CROWN} = 18.0$ ft								
Gutter Width	$W = 2.00$ ft								
Street Transverse Slope	$S_x = 0.020$ ft/ft								
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft								
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.000$ ft/ft								
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.015$								
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>ft</td> </tr> <tr> <td><math>T_{MAX} =</math></td> <td>15.8</td> <td>18.0</td> <td></td> </tr> </table>		Minor Storm	Major Storm	ft	$T_{MAX} =$	15.8	18.0	
	Minor Storm	Major Storm	ft						
$T_{MAX} =$	15.8	18.0							
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>inches</td> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>4.6</td> <td>7.8</td> <td></td> </tr> </table>		Minor Storm	Major Storm	inches	$d_{MAX} =$	4.6	7.8	
	Minor Storm	Major Storm	inches						
$d_{MAX} =$	4.6	7.8							
Check boxes are not applicable in SUMP conditions	<input type="checkbox"/> <input type="checkbox"/>								
MINOR STORM Allowable Capacity is not applicable to Sump Condition									
MAJOR STORM Allowable Capacity is not applicable to Sump Condition									
<b>Q<sub>allow</sub> =</b>	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>cfs</td> </tr> <tr> <td></td> <td><b>SUMP</b></td> <td><b>SUMP</b></td> <td></td> </tr> </table>		Minor Storm	Major Storm	cfs		<b>SUMP</b>	<b>SUMP</b>	
	Minor Storm	Major Storm	cfs						
	<b>SUMP</b>	<b>SUMP</b>							

# INLET IN A SUMP OR SAG LOCATION

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a' from above)	3.00	3.00	inches
Number of Unit Inlets (Grate or Curb Opening)	1	1	
Water Depth at Flowline (outside of local depression)	4.6	5.8	inches
<b>Grate Information</b>			
Length of a Unit Grate	N/A	N/A	feet
Width of a Unit Grate	N/A	N/A	feet
Open Area Ratio for a Grate (typical values 0.15-0.90)	N/A	N/A	
Clogging Factor for a Single Grate (typical value 0.50 - 0.70)	N/A	N/A	
Grate Weir Coefficient (typical value 2.15 - 3.60)	N/A	N/A	
Grate Orifice Coefficient (typical value 0.60 - 0.80)	N/A	N/A	
<b>Curb Opening Information</b>			
Length of a Unit Curb Opening	5.00	5.00	feet
Height of Vertical Curb Opening in Inches	6.00	6.00	inches
Height of Curb Orifice Throat in Inches	6.00	6.00	inches
Angle of Throat (see USDCM Figure ST-5)	63.40	63.40	degrees
Side Width for Depression Pan (typically the gutter width of 2 feet)	2.00	2.00	feet
Clogging Factor for a Single Curb Opening (typical value 0.10)	0.10	0.10	
Curb Opening Weir Coefficient (typical value 2.3-3.7)	3.60	3.60	
Curb Opening Orifice Coefficient (typical value 0.60 - 0.70)	0.67	0.67	
<b>Low Head Performance Reduction (Calculated)</b>			
Depth for Grate Midwidth	N/A	N/A	ft
Depth for Curb Opening Weir Equation	0.22	0.32	ft
Grated Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
Curb Opening Performance Reduction Factor for Long Inlets	1.00	1.00	
Combination Inlet Performance Reduction Factor for Long Inlets	N/A	N/A	
<b>Total Inlet Interception Capacity (assumes clogged condition)</b>			
<b>Inlet Capacity IS GOOD for Minor and Major Storms (&gt;Q Peak)</b>	<b>2.8</b>	<b>5.0</b>	<b>cfs</b>
Q PEAK REQUIRED =	1.0	1.7	cfs

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing 2 (Proposed Conditions)**


Inlet ID: **Inlet 3 (DP11 North)**



<b>Gutter Geometry:</b>									
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft								
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft								
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$								
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches								
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft								
Gutter Width	$W = 2.00$ ft								
Street Transverse Slope	$S_x = 0.020$ ft/ft								
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft								
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.012$ ft/ft								
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.015$								
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> <tr> <td><math>T_{MAX} =</math></td> <td>15.8</td> <td>17.0</td> <td>ft</td> </tr> </table>		Minor Storm	Major Storm		$T_{MAX} =$	15.8	17.0	ft
	Minor Storm	Major Storm							
$T_{MAX} =$	15.8	17.0	ft						
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>4.6</td> <td>7.8</td> <td>inches</td> </tr> </table>		Minor Storm	Major Storm		$d_{MAX} =$	4.6	7.8	inches
	Minor Storm	Major Storm							
$d_{MAX} =$	4.6	7.8	inches						
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<table border="1"> <tr> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>	<input type="checkbox"/>	<input type="checkbox"/>						
<input type="checkbox"/>	<input type="checkbox"/>								
MINOR STORM Allowable Capacity is based on Depth Criterion									
MAJOR STORM Allowable Capacity is based on Spread Criterion									
<b>Minor storm max. allowable capacity GOOD - greater than the design peak flow of 4.20 cfs on sheet 'Inlet Management'</b>									
<b>Major storm max. allowable capacity GOOD - greater than the design peak flow of 8.40 cfs on sheet 'Inlet Management'</b>									
$Q_{allow} =$	<table border="1"> <tr> <th></th> <th>Minor Storm</th> <th>Major Storm</th> <th></th> </tr> <tr> <td></td> <td>6.5</td> <td>12.7</td> <td>cfs</td> </tr> </table>		Minor Storm	Major Storm			6.5	12.7	cfs
	Minor Storm	Major Storm							
	6.5	12.7	cfs						

# INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - Q < Allowable Street Capacity			
Total Inlet Interception Capacity	<b>Q</b> =	<b>4.2</b>	<b>8.0</b> cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	<b>Q<sub>b</sub></b> =	<b>0.0</b>	<b>0.4</b> cfs
Capture Percentage = Q <sub>i</sub> /Q <sub>s</sub>	<b>C%</b> =	<b>100</b>	<b>95</b> %

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing 2 (Proposed Conditions)**

Inlet ID: **Inlet 4 (DP11 South)**



**Gutter Geometry:**

Maximum Allowable Width for Spread Behind Curb  
 Side Slope Behind Curb (leave blank for no conveyance credit behind curb)  
 Manning's Roughness Behind Curb (typically between 0.012 and 0.020)

$T_{BACK}$ =	7.5	ft
$S_{BACK}$ =	0.020	ft/ft
$n_{BACK}$ =	0.020	

Height of Curb at Gutter Flow Line  
 Distance from Curb Face to Street Crown  
 Gutter Width  
 Street Transverse Slope  
 Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)  
 Street Longitudinal Slope - Enter 0 for sump condition  
 Manning's Roughness for Street Section (typically between 0.012 and 0.020)

$H_{CURB}$ =	6.00	inches
$T_{CROWN}$ =	17.0	ft
$W$ =	2.00	ft
$S_x$ =	0.020	ft/ft
$S_w$ =	0.083	ft/ft
$S_o$ =	0.011	ft/ft
$n_{STREET}$ =	0.015	

Max. Allowable Spread for Minor & Major Storm  
 Max. Allowable Depth at Gutter Flowline for Minor & Major Storm  
 Allow Flow Depth at Street Crown (check box for yes, leave blank for no)

	Minor Storm	Major Storm	
$T_{MAX}$ =	15.8	17.0	ft
$d_{MAX}$ =	4.6	7.8	inches
	<input type="checkbox"/>	<input type="checkbox"/>	


MINOR STORM Allowable Capacity is based on Depth Criterion  
 MAJOR STORM Allowable Capacity is based on Spread Criterion

	Minor Storm	Major Storm	
$Q_{allow}$ =	6.2	12.2	cfs

**Minor storm max. allowable capacity GOOD - greater than the design peak flow of 4.20 cfs on sheet 'Inlet Management'**  
**Major storm max. allowable capacity GOOD - greater than the design peak flow of 8.40 cfs on sheet 'Inlet Management'**

# INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - Q < Allowable Street Capacity			
Total Inlet Interception Capacity	<b>Q = 4.2</b>	<b>8.0</b>	<b>cfs</b>
Total Inlet Carry-Over Flow (flow bypassing inlet)	<b>Q<sub>b</sub> = 0.0</b>	<b>0.4</b>	<b>cfs</b>
Capture Percentage = Q <sub>i</sub> /Q <sub>s</sub>	<b>C% = 100</b>	<b>95</b>	<b>%</b>



**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**  
 (Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)


**Project:** Claremont Business Park 2 Filing 2 (Proposed Conditions)  
**Inlet ID:** Inlet 5 (DP12)



<b>Gutter Geometry:</b>	
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft
Gutter Width	$W = 2.00$ ft
Street Transverse Slope	$S_x = 0.020$ ft/ft
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_w = 0.083$ ft/ft
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.010$ ft/ft
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.015$
Max. Allowable Spread for Minor & Major Storm	$T_{MAX} = \begin{matrix} \text{Minor Storm} & \text{Major Storm} \\ 15.8 & 17.0 \end{matrix}$ ft
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	$d_{MAX} = \begin{matrix} \text{Minor Storm} & \text{Major Storm} \\ 4.6 & 7.8 \end{matrix}$ inches
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<input type="checkbox"/> <input type="checkbox"/>
<a href="#">MINOR STORM Allowable Capacity is based on Depth Criterion</a>	
<a href="#">MAJOR STORM Allowable Capacity is based on Spread Criterion</a>	
<b>Minor storm max. allowable capacity GOOD - greater than the design peak flow of 2.80 cfs on sheet 'Inlet Management'</b>	
<b>Major storm max. allowable capacity GOOD - greater than the design peak flow of 8.10 cfs on sheet 'Inlet Management'</b>	
$Q_{allow} =$	$\begin{matrix} \text{Minor Storm} & \text{Major Storm} \\ 5.9 & 11.6 \end{matrix}$ cfs

# INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - Q < Allowable Street Capacity			
Total Inlet Interception Capacity	<b>Q</b> =	<b>2.8</b>	<b>7.8</b> cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	<b>Q<sub>b</sub></b> =	<b>0.0</b>	<b>0.3</b> cfs
Capture Percentage = Q <sub>i</sub> /Q <sub>s</sub>	<b>C%</b> =	<b>100</b>	<b>96</b> %

**ALLOWABLE CAPACITY FOR ONE-HALF OF STREET (Minor & Major Storm)**

(Based on Regulated Criteria for Maximum Allowable Flow Depth and Spread)

Project: **Claremont Business Park 2 Filing 2 (Proposed Conditions)**


Inlet ID: **Inlet 6 (DP13)**



<b>Gutter Geometry:</b>									
Maximum Allowable Width for Spread Behind Curb	$T_{BACK} = 7.5$ ft								
Side Slope Behind Curb (leave blank for no conveyance credit behind curb)	$S_{BACK} = 0.020$ ft/ft								
Manning's Roughness Behind Curb (typically between 0.012 and 0.020)	$n_{BACK} = 0.020$								
Height of Curb at Gutter Flow Line	$H_{CURB} = 6.00$ inches								
Distance from Curb Face to Street Crown	$T_{CROWN} = 17.0$ ft								
Gutter Width	$W = 2.00$ ft								
Street Transverse Slope	$S_x = 0.020$ ft/ft								
Gutter Cross Slope (typically 2 inches over 24 inches or 0.083 ft/ft)	$S_y = 0.083$ ft/ft								
Street Longitudinal Slope - Enter 0 for sump condition	$S_o = 0.010$ ft/ft								
Manning's Roughness for Street Section (typically between 0.012 and 0.020)	$n_{STREET} = 0.015$								
Max. Allowable Spread for Minor & Major Storm	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>ft</td> </tr> <tr> <td><math>T_{MAX} =</math></td> <td>15.8</td> <td>17.0</td> <td></td> </tr> </table>		Minor Storm	Major Storm	ft	$T_{MAX} =$	15.8	17.0	
	Minor Storm	Major Storm	ft						
$T_{MAX} =$	15.8	17.0							
Max. Allowable Depth at Gutter Flowline for Minor & Major Storm	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>inches</td> </tr> <tr> <td><math>d_{MAX} =</math></td> <td>4.6</td> <td>7.8</td> <td></td> </tr> </table>		Minor Storm	Major Storm	inches	$d_{MAX} =$	4.6	7.8	
	Minor Storm	Major Storm	inches						
$d_{MAX} =$	4.6	7.8							
Allow Flow Depth at Street Crown (check box for yes, leave blank for no)	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> </tr> <tr> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>		Minor Storm	Major Storm	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
	Minor Storm	Major Storm							
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>							
MINOR STORM Allowable Capacity is based on Depth Criterion									
MAJOR STORM Allowable Capacity is based on Spread Criterion									
<b>Minor storm max. allowable capacity GOOD - greater than the design peak flow of 1.00 cfs on sheet 'Inlet Management'</b>									
<b>Major storm max. allowable capacity GOOD - greater than the design peak flow of 5.00 cfs on sheet 'Inlet Management'</b>									
$Q_{allow} =$	<table border="1"> <tr> <td></td> <td>Minor Storm</td> <td>Major Storm</td> <td>cfs</td> </tr> <tr> <td></td> <td>5.9</td> <td>11.6</td> <td></td> </tr> </table>		Minor Storm	Major Storm	cfs		5.9	11.6	
	Minor Storm	Major Storm	cfs						
	5.9	11.6							

# INLET ON A CONTINUOUS GRADE

MHFD-Inlet, Version 5.02 (August 2022)




Design Information (Input)	MINOR	MAJOR	
Type of Inlet	CDOT Type R Curb Opening		
Local Depression (additional to continuous gutter depression 'a')	3.0	3.0	inches
Total Number of Units in the Inlet (Grate or Curb Opening)	3	3	
Length of a Single Unit Inlet (Grate or Curb Opening)	5.00	5.00	ft
Width of a Unit Grate (cannot be greater than W, Gutter Width)	N/A	N/A	ft
Clogging Factor for a Single Unit Grate (typical min. value = 0.5)	N/A	N/A	
Clogging Factor for a Single Unit Curb Opening (typical min. value = 0.1)	0.10	0.10	
Street Hydraulics: OK - Q < Allowable Street Capacity			
Total Inlet Interception Capacity	Q = 1.0	Q = 5.0	cfs
Total Inlet Carry-Over Flow (flow bypassing inlet)	Q <sub>b</sub> = 0.0	Q <sub>b</sub> = 0.0	cfs
Capture Percentage = Q <sub>i</sub> /Q <sub>s</sub>	C% = 100	C% = 100	%

## AREA INLET IN A SWALE

**Claremont Business Park 2 Filing 2 (Proposed Conditions)**

**Inlet 7 (DP18)**



This worksheet uses the NRCS vegetal retardance method to determine Manning's n.

For more information see Section 7.2.3 of the USDCM.

**Analysis of Trapezoidal Grass-Lined Channel Using SCS Method**

NRCS Vegetal Retardance (A, B, C, D, or E)		
Manning's n (Leave cell D16 blank to manually enter an n value)		
Channel Invert Slope		
Bottom Width		
Left Side Slope		
Right Side Slope		
Check one of the following soil types:		
Soil Type:	Max. Velocity (V <sub>MAX</sub> )	Max Froude No. (F <sub>MAX</sub> )
Non-Cohesive	5.0 fps	0.60
Cohesive	7.0 fps	0.80
Paved	N/A	N/A

A, B, C, D, or E =	
n =	0.025
S <sub>0</sub> =	0.1200 ft/ft
B =	0.00 ft
Z1 =	3.00 ft/ft
Z2 =	3.00 ft/ft

Choose One:

Non-Cohesive

Cohesive

Paved

Maximum Allowable Top Width of Channel for Minor & Major Storm  
 Maximum Allowable Water Depth in Channel for Minor & Major Storm

	Minor Storm	Major Storm	
T <sub>MAX</sub> =	1.92	2.40	ft
d <sub>MAX</sub> =	0.32	0.40	ft

**Allowable Channel Capacity Based On Channel Geometry**

MINOR STORM Allowable Capacity is based on Depth Criterion  
 MAJOR STORM Allowable Capacity is based on Depth Criterion

	Minor Storm	Major Storm	
Q <sub>allow</sub> =	1.8	3.3	cfs
d <sub>allow</sub> =	0.32	0.40	ft

**Water Depth in Channel Based On Design Peak Flow**

Design Peak Flow  
 Water Depth

Q <sub>o</sub> =	0.7	1.3	cfs
d =	0.22	0.28	ft

**Minor storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'**  
**Major storm max. allowable capacity GOOD - greater than the design flow given on sheet 'Inlet Management'**

MHFD-Inlet, Version 5.02 (August 2022)  
**AREA INLET IN A SWALE**

**Claremont Business Park 2 Filing 2 (Proposed Conditions)**  
**Inlet 7 (DP18)**

Inlet Design Information (Input)																					
Type of Inlet	CDOT Type C (Depressed)																				
Inlet Type =	CDOT Type C (Depressed)																				
Angle of Inclined Grate (must be <= 30 degrees)	$\theta = 0.00$ degrees																				
Width of Grate	$W = 3.00$ ft																				
Length of Grate	$L = 3.00$ ft																				
Open Area Ratio	$A_{RATIO} = 0.70$																				
Height of Inclined Grate	$H_B = 0.00$ ft																				
Clogging Factor	$C_f = 0.50$																				
Grate Discharge Coefficient	$C_d = 0.84$																				
Orifice Coefficient	$C_o = 0.56$																				
Weir Coefficient	$C_w = 1.81$																				
Water Depth at Inlet (for depressed inlets, 1 foot is added for depression)																					
Total Inlet Interception Capacity (assumes clogged condition)	<table border="1"> <thead> <tr> <th></th> <th>MINOR</th> <th>MAJOR</th> <th></th> </tr> </thead> <tbody> <tr> <td><math>d =</math></td> <td>1.22</td> <td>1.28</td> <td></td> </tr> <tr> <td><math>Q_a =</math></td> <td><b>15.7</b></td> <td><b>16.1</b></td> <td><b>cfs</b></td> </tr> <tr> <td><math>Q_b =</math></td> <td><b>0.0</b></td> <td><b>0.0</b></td> <td><b>cfs</b></td> </tr> <tr> <td><math>C\% =</math></td> <td><b>100</b></td> <td><b>100</b></td> <td><b>%</b></td> </tr> </tbody> </table>		MINOR	MAJOR		$d =$	1.22	1.28		$Q_a =$	<b>15.7</b>	<b>16.1</b>	<b>cfs</b>	$Q_b =$	<b>0.0</b>	<b>0.0</b>	<b>cfs</b>	$C\% =$	<b>100</b>	<b>100</b>	<b>%</b>
	MINOR	MAJOR																			
$d =$	1.22	1.28																			
$Q_a =$	<b>15.7</b>	<b>16.1</b>	<b>cfs</b>																		
$Q_b =$	<b>0.0</b>	<b>0.0</b>	<b>cfs</b>																		
$C\% =$	<b>100</b>	<b>100</b>	<b>%</b>																		
Bypassed Flow																					
Capture Percentage = $Q_a/Q_o$																					

**Warning 04: Froude No. exceeds USDCM Volume I recommendation.**



CIVIL CONSULTANTS, INC.

2-11-23

212 N. Wahsatch Ave., Ste. 305  
Colorado Springs, CO  
719.955.5485

Project: CLAREMONT BUSINESS PARK 2 PHASE 2

Date: RIDRAP APRON CALL

Proposed 18" RCP (Future Dev. Lot)

$$n = 0.013 \quad D = 1.5'$$

$$S = 0.01 \text{ (Assumed)} \quad Q_{100} = 6.0 \text{ cfs} \quad \text{BASINS C \& D}$$

$$TW = m.n. = 0.4 \times 1.5 = 0.6$$

Flow is supercritical (Flowmeter)  $V_p = 0.808$

$$y_p = 6.14$$

$$D' = \frac{D + y_p}{2}$$

$$D' = (1.5 + 0.81) / 2 = 1.16$$

$$D_{50} = 0.2 (1.16) \left( \frac{6.0}{\sqrt{32.2} \cdot (1.16)^{2.5}} \right)^{0.15} \left( \frac{1.16}{0.6} \right) = 0.009 < 1''$$

$$\text{Use } D_{50} = 9'' \quad \text{Depth} = 2.0 \times D_{50} = 18''$$

$$L = 4.0 \times 1.5 = 6.0$$

$$\begin{aligned} \text{End Width} &= 3.0 \times D + \frac{2}{3}L \\ &= 3.0 \times 1.5 + \frac{2}{3}(6.0) \end{aligned}$$

$$4.5 + 4 = 8.5$$



CIVIL CONSULTANTS, INC.

212 N. Wahsatch Ave., Ste. 305  
Colorado Springs, CO  
719.955.5485

Project: CUREMONT BUSINESS PARK 2 FILING 2  
Date: RIPRAP APPROX CUR.

2-12-22

Prop 18" RCP

$$n = 0.013 \quad D = 1.5'$$

$$S = 0.005 \quad Q_{100} = 3.9 \text{ cfs}$$

$$TW = \text{min} = 0.4 D = 0.4 (1.5) = 0.6$$

Flow is supercritical  $y_0 = 9.3'' = 0.775$   
 $y_0 = 4.25''$

$$D' = \frac{(D + y_0)}{2}$$

$$D' = (1.5 + .78) / 2 = 1.14'$$


$$D_{50} = 0.2 (1.14) \left( \frac{3.9}{1.482 \cdot (1.14)^{2.5}} \right)^{4/3} \left( \frac{1.14}{0.6} \right) = 0.003 < 1''$$

Use  $D_{50} = 9''$  Depth =  $2.0 \times D_{50} = 1.5'$

$$L = 4.0 \times D = 6.0'$$

$$\text{END WIDTH} = 3.0 + D + 2/3 L \\ = 8.5'$$





Label various ponds as existing, proposed or future .

Try to print all of stormcad table on one sheet, or include "Label" column with second sheet

### Conduit FlexTable: STRM 1,2,3 - 100YR

Include pipe slope in table. ID, Fr #, % Flow/Capacity, critical depth, & EGL's is not needed in table.


Label	ID	Upstream Structure	Flow (cfs)	Flow / Capacity (Design) (%)	Length (Unified) (ft)
PR1	601	POND 1 OUTFALL	5.70	76.9	57.1
PR1A	582	MH-9	5.70	39.7	137.3
PR2	603	POND 2 OUTFALL	2.40	32.5	56.5
PR3	613	POND 3 OUTFALL	1.00	13.1	11.4
PR4	580	MH-8	9.10	56.8	119.5
PR5	604	INLET 1	1.70	22.7	37.3
PR6	608	INLET 2	3.90	38.3	20.2
PR6A	631	FWL2	5.10	44.4	30.1
PR7	605	POND 3 OUTFALL	4.00	55.5	14.9
PR7A	596	MH-7A	4.00	53.3	60.6
PR8	578	MH-7	13.10	82.1	181.1
PR9	576	POND 5 OUTFALL	3.00	22.6	12.5
PR10	548	MH-6	16.20	101.3	30.0
PR11	616	MH-5	16.20	85.6	84.3
PR11A	615	MH-4A	16.20	39.1	115.8
PR12	568	MH-4	16.20	88.5	239.6
PR18	570	POND 2 OUTFALL	23.80	23.0	39.7
PR19	567	MH-2	40.00	36.2	23.2
Velocity (ft/s)	Froude Number	Depth (Normal) (ft)	Depth (Critical) (ft)	Energy Grade Line (In) (ft)	Energy Grade Line (Out) (ft)
4.63	(N/A)	0.99	0.92	6,375.32	6,375.09
7.66	(N/A)	0.66	0.92	6,374.72	6,372.36
3.74	(N/A)	0.59	0.59	6,372.25	6,372.21
2.98	(N/A)	0.37	0.37	6,372.19	6,372.19
5.26	(N/A)	1.08	1.08	6,371.85	6,371.25
3.43	(N/A)	0.49	0.49	6,372.28	6,372.27
2.21	(N/A)	0.64	0.76	6,372.24	6,372.22
2.89	(N/A)	0.70	0.87	6,372.34	6,372.27
4.18	(N/A)	0.80	0.77	6,368.99	6,368.97
2.26	(N/A)	0.78	0.77	6,368.83	6,368.74
5.67	(N/A)	1.38	1.30	6,368.50	6,367.92
6.07	(N/A)	0.48	0.66	6,368.69	6,368.57
5.16	(N/A)	1.66	1.45	6,367.69	6,367.54
6.77	(N/A)	1.42	1.45	6,366.91	6,366.32
12.37	(N/A)	0.87	1.45	6,366.32	6,363.52
6.58	(N/A)	1.46	1.45	6,362.21	6,360.64
17.12	(N/A)	0.82	1.66	6,362.92	6,360.41
10.56	(N/A)	1.46	1.97	6,359.77	6,359.62

Length does not match CD's


### Conduit FlexTable: STRM 1,2,3 - 100YR

Hydraulic Grade Line (In) (ft)	Hydraulic Grade Line (Out) (ft)	Headloss (ft)	Upstream Structure Hydraulic Grade Line (In) (ft)	Upstream Structure Velocity (In-Governing) (ft/s)	Upstream Structure Headloss Coefficient
6,375.01	6,374.85	0.16	6,375.48	4.48	1.500
6,374.33	6,372.18	2.15	6,374.85	3.97	1.320
6,372.20	6,372.18	0.02	6,372.27	1.77	1.500
6,372.18	6,372.18	0.00	6,372.19	0.62	1.500
6,371.42	6,370.82	0.60	6,372.18	1.44	1.770
6,372.26	6,372.25	0.01	6,372.28	1.10	1.500
6,372.17	6,372.14	0.03	6,372.25	0.99	1.100
6,372.21	6,372.14	0.07	6,372.40	2.89	1.500
6,368.90	6,368.89	0.01	6,369.04	2.46	1.500
6,368.75	6,368.66	0.09	6,368.89	2.38	1.770
6,368.19	6,367.65	0.54	6,368.66	2.26	1.520
6,368.44	6,368.10	0.34	6,368.81	4.02	1.500
6,367.28	6,367.12	0.15	6,367.65	4.17	0.900
6,366.22	6,365.67	0.56	6,367.12	5.16	1.320
6,365.63	6,361.17	4.46	6,365.67	6.47	0.050
6,361.53	6,359.95	1.58	6,361.57	12.30	0.050
6,362.19	6,359.79	2.41	6,363.29	6.87	1.500
6,358.97	6,358.37	0.60	6,359.79	6.35	1.020
Upstream Structure Headloss (ft)	Elevation Ground (Start) (ft)	Elevation Ground (Stop) (ft)	Invert (Start) (ft)	Invert (Stop) (ft)	Conduit Description
0.47	6,375.49	6,379.87	6,373.99	6,373.71	Circle - 18.0 in
0.51	6,379.87	6,376.08	6,373.41	6,370.84	Circle - 18.0 in
0.07	6,373.10	6,376.08	6,371.12	6,370.84	Circle - 18.0 in
0.01	6,376.08	6,372.40	6,370.84	6,370.90	Circle - 18.0 in
0.76	6,376.08	6,375.45	6,370.34	6,369.74	Circle - 24.0 in
0.03	6,375.11	6,375.11	6,371.03	6,370.84	Circle - 18.0 in
0.08	6,375.11	6,370.35	6,370.54	6,370.35	Circle - 18.0 in
0.19	6,370.35	6,372.21	6,370.35	6,370.71	Circle - 18.0 in
0.14	6,371.49	6,376.00	6,367.60	6,367.53	Circle - 18.0 in
0.14	6,376.00	6,375.45	6,367.23	6,366.92	Circle - 18.0 in
0.47	6,375.45	6,374.49	6,366.42	6,365.52	Circle - 24.0 in
0.38	6,369.78	6,374.49	6,367.78	6,367.58	Circle - 18.0 in
0.37	6,373.76	6,374.49	6,365.07	6,365.22	Circle - 24.0 in
0.90	6,372.41	6,373.76	6,364.18	6,364.77	Circle - 24.0 in
0.03	6,370.58	6,372.41	6,360.30	6,364.18	Circle - 24.0 in
0.03	6,367.74	6,370.58	6,358.50	6,360.07	Circle - 24.0 in
1.10	6,366.20	6,367.74	6,360.53	6,358.00	Circle - 30.0 in
0.82	6,367.70	6,367.74	6,356.72	6,357.00	Circle - 42.0 in


Storm - 100 yr - Time: 0.00




Storm 1 - Lat 1 - 100 yr




Storm 1 - Lat 2 - 100 yr



Storm 1 - Lat 3 - 100 yr




Storm 1 - Lat 4 - 100 yr






Storm 2 - 100 yr



Storm 3 - 100 yr




## EXISTING DRAINAGE MAP

# FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.2

COUNTY OF EL PASO, STATE OF COLORADO

## EXISTING CONDITIONS DRAINAGE MAP

FEBRUARY 2023



### LEGEND

- BASIN DESIGNATION
- PIPE RUN REFERENCE LABEL
- SURFACE DESIGN POINT
- BASIN BOUNDARY
- EXISTING CONTOUR
- PROP CONTOUR
- UNDERGROUND ELECTRICAL
- EXISTING GAS LINE
- STORM SEWER PIPE
- EXISTING STORM SEWER PIPE
- CROSSSPAN
- INLET
- EXISTING FLOW DIRECTION ARROW
- EMERGENCY OVERFLOW DIRECTION
- FLOW DIRECTION
- FLARED END SECTION
- HIGH POINT
- LOW POINT

### BASIN SUMMARY

BASIN	AREA (ACRES)	Q <sub>5</sub>	Q <sub>100</sub>
A	0.19	0.1	0.6
B	0.30	0.1	1.0
C	4.90	1.6	10.7
D	0.23	0.1	0.7
H1	0.18	0.1	0.5
H2	0.40	0.2	1.1
H3	0.04	0.0	0.1
H4	0.10	0.0	0.3
I1	0.57	2.4	4.4
I2	0.48	2.0	3.6
I3	0.58	1.8	3.6
I4	0.43	1.8	3.3
I5	0.23	0.9	1.7
I6	0.19	0.6	1.2
I7	0.23	0.9	1.6
J1	0.76	2.4	4.7
J2	0.25	1.0	1.8
J3	0.01	0.0	0.1
K1	0.17	0.7	1.3
K2	0.05	0.2	0.4
K3	0.15	0.6	1.1
K4	0.06	0.2	0.4
L	1.32	0.5	3.7
M1	0.28	1.2	2.2
M2	0.24	0.8	1.5
M3	0.37	1.6	2.9
M4	0.98	3.5	6.6
N1	0.06	0.3	0.5
N2	0.41	0.2	1.1
O1	0.12	0.1	0.4
O2	0.06	0.1	0.3
P	0.11	0.0	0.3

### DESIGN POINT SUMMARY

DESIGN POINT	Q <sub>5</sub>	Q <sub>100</sub>	BASIN	STRUCTURE
1	1.8	11.8	A, B, C	24" PP
2			NOT USED	
3	2.2	4.4	H1, I1	EX STREET
4	1.8	4.1	H2, I2	EX STREET
5	0.8	1.6	H3, I7	EX STREET
6	8.2	16.5	DP3-5, I3-16	EX 15" INLETS
7	2.4	7.5	FB INLETS, J1	EX 15" INLET
8	0.9	4.1	FB INLET4, J2, J3	EX 15" INLET
9	3.8	9.7	H3, L, M4	EX SWALE
10	5.3	12.3	DP9, M2, M3	EX SWALE/RD
11	1.4	2.5	M1, K4	EX CONC. RD
12	1.1	2.0	K2, K3, N1	EX CONC. RD
13	0.7	1.3	K1	EX AREA INLET
14	19.3	43.9	DPT0-13, N2, PR14, PR17	EX FSD POND 2

### STORM SEWER SUMMARY

PIPE RUN	Q <sub>5</sub>	Q <sub>100</sub>	PIPE SIZE	CONTRIBUTING DP/BASIN/PIPES
11	1.8	11.8	EX 24"	DP1
12	1.8	11.8	EX 24"	PR11
13	4.1	7.9	EX 15"	INLET 3
14	8.2	15.9	EX 24"	PR13, INLET 4
15	2.4	7.3	EX 18"	INLET 5
16	3.2	11.0	EX 24"	PR15, INLET 6
17	3.9	12.1	EX 24"	PR16, DP13
18	13.7	23.9	EX 30"	POND 2 OUTFALL
19	17.7	38.0	EX 42"	PR12, PR18

Add Contour Labels

H4

Labels cut off

Label rundowns


Label pipe

Label chase

File: c:\10020\EDM\Drawings\Drainage\Drawings\Drainage\Drawings\Drainage\10020 EDM.dwg Plotstamp: 2/28/2023 11:05 AM

FOR LOCATING & MARKING GAS, ELECTRIC, WATER & TELEPHONE LINES

FOR BURIED UTILITY INFORMATION 48 HRS BEFORE YOU DIG CALL 1-800-922-1987



102 E. PIKES PEAK AVE., 5TH FLOOR  
COLORADO SPRINGS, CO 80903  
PHONE: 719.955.5485

CLAREMONT BUSINESS PARK 2 FIL. NO.2  
EXISTING CONDITIONS DRAINAGE MAP

PROJECT NO. 10-022A FILE: \dwg\Eng Exhibits\10020 EDM.dwg

DESIGNED BY: DLM SCALE: DATE: 02-23-2023  
DRAWN BY: DLM HORIZ: 1"=60'  
CHECKED BY: VAS VERT: N/A

SHEET 1 OF 1 EDM01

## PROPOSED DRAINAGE MAP

# FINAL DRAINAGE REPORT FOR CLAREMONT BUSINESS PARK 2 FILING NO.1

## COUNTY OF EL PASO, STATE OF COLORADO

# PROPOSED CONDITIONS DRAINAGE MAP

FEBRUARY 2023

### LEGEND

BASIN DESIGNATION: Z 25, 25, 35, C5, C100  
ACRES

PIPE RUN REFERENCE LABEL: 4, 6

SURFACE DESIGN POINT: 6

BASIN BOUNDARY: ---

EXISTING CONTOUR: - - - (6920)

PROP CONTOUR: — 6920 —

UGE: - - -

EXISTING GAS LINE: ---

STORM SEWER PIPE: ———

EXISTING STORM SEWER PIPE: - - -

CROSSSPAN: ———

INLET: □

EXISTING FLOW DIRECTION: →

EMERGENCY OVERFLOW DIRECTION: ↗

FLOW DIRECTION: →

FLARED END SECTION: ▽

HIGH POINT: H.P. X

LOW POINT: L.P. X

### BASIN SUMMARY

BASIN	AREA (ACRES)	Q <sub>5</sub>	Q <sub>100</sub>
A	0.21	0.1	0.7
B	1.50	6.0	10.9
C	0.12	0.1	0.4
C1	0.17	0.1	0.5
D	0.77	3.2	5.9
D1	0.78	3.3	6.0
E1	0.27	1.2	2.2
E2	0.21	1.0	1.7
G1	0.27	0.4	1.2
G2	1.15	4.3	7.8
H1	0.16	0.1	0.5
H2	0.40	0.2	1.1
H3	0.04	0.0	0.1
H4	0.10	0.0	0.3
I1	0.55	2.3	4.3
I2	0.48	2.0	3.6
I3	0.45	1.8	3.3
I4	0.55	2.3	4.2
I5	0.23	0.9	1.7
I6	0.19	0.6	1.2
I7	0.23	0.9	1.6
J1	0.69	2.7	5.1
J2	0.25	1.0	1.8
J3	0.01	0.0	0.1
K1	0.17	0.7	1.3
K2	0.05	0.2	0.4
K3	0.15	0.6	1.1
K4	0.05	0.2	0.4
L	1.32	5.3	9.7
M1	0.28	1.2	2.2
M2	0.24	0.8	1.5
M3	0.37	1.6	2.9
M4	0.98	3.5	6.6
N1	0.06	0.3	0.5
N2	0.41	0.2	1.1
O1	0.12	0.1	0.4
O2	0.06	0.1	0.3
P	0.11	0.0	0.3

### DESIGN POINT SUMMARY

DESIGN POINT	Q <sub>5</sub>	Q <sub>100</sub>	BASIN	STRUCTURE
1	5.9	11.2	A, B	18" PP
2	3.0	5.8	C, D	15" PP
3	1.2	2.3	F	15" PP
4	1.0	1.7	E2	PROP 5" INLET
5	1.2	2.2	E1	PROP 5" INLET
6	5.1	9.6	C1, D1, PR6	24" PP
7	4.7	8.7	G2	EX STREET
8	2.2	4.3	H1, I1	EX STREET
9	1.8	4.1	H2, I2	EX STREET
10	0.8	1.6	H3, I7	EX STREET
11	8.4	16.7	DP3-5, I3-16	EX 15" INLETS
12	2.8	8.1	FB INLETS, J1	EX 15" INLET
13	1.0	5.0	FB INLET4, J2, J3	EX 15" INLET
14	3.8	9.7	H4, L, M4	EX SWALE
15	5.3	12.3	DP9, M2, M3	EX SWALE/RD
16	1.4	2.5	M1, K4	EX CONC. RD
17	1.1	2.0	K2, K3, N1	EX CONC. RD
18	0.7	1.3	K1	EX AREA INLET
19	19.8	44.7	PR10-13, N2, PR14, PR17	EX FSD POND 2

### STORM SEWER SUMMARY

PIPE RUN	Q <sub>5</sub>	Q <sub>100</sub>	PIPE SIZE	CONTRIBUTING DP/BASIN/PIPES
1	2.4	5.7	18"	FUT POND 1 OUTFALL
2	1.0	2.4	18"	FUT POND 2 OUTFALL
3	0.4	1.0	18"	FUT POND 4 OUTFALL
4	3.9	9.1	24"	PR1-PR3
5	1.0	1.7	18"	DP4
6	2.2	3.9	18"	PR5, DP5
6A	2.9	5.1	18"	C1, 90% D1
7	1.9	4.0	18"	POND 3 OUTFALL
8	5.9	13.1	24"	PR4, PR7
9	1.3	3.0	18"	FUT POND 5 OUTFALL
10	7.1	16.2	24"	PR8, PR9
11	7.1	16.2	24"/EX24"	PR10
12	7.1	16.2	EX 24"	PR11
13	4.2	8.0	EX 15"	INLET 3
14	8.4	16.0	EX 24"	PR13, INLET 4
15	2.8	7.8	EX 18"	INLET 5
16	3.7	12.6	EX 24"	PR15, INLET 6
17	4.4	13.8	EX 24"	PR16, DP18
18	13.7	23.8	EX 30"	EX POND 2 OUTFALL
19	20.8	40.0	EX 42"	DP18, PR12

### SF WQCV FUTURE PONDS SUMMARY

EPC/URBAN DRAINAGE SAND FILTER BASIN-SEE STD. DET.	AREA REQUIRED	AREA PROVIDED
POND 1	773 SF	773 SF
POND 2	379 SF	379 SF
POND 4	288 SF	288 SF
POND 5	565 SF	565 SF


### SF WQCV POND 3 SUMMARY

EPC/URBAN DRAINAGE SAND FILTER BASIN-SEE STD. DET.	AREA REQUIRED	AREA PROVIDED
POND 3	637 SF	784 SF

SF ELEV = 6370.35

### POND 3 SAND FILTER DETENTION BASIN DATA

WO WATER SURFACE EL = 6371.48  
 WO VOLUME = 0.032 AC-FT  
 100-YR WATER SURFACE EL = 6372.14  
 100-YR VOLUME = 0.06 AC-FT  
 SPILLWAY CREST EL = 6375.30  
 TOP OF EMBANKMENT EL = 6376.55  
 RATIONAL 100-YR INFLOW = 9.6 CFS  
 MHFD 100-YR INFLOW = 4.9 CFS  
 MHFD 100-YR RELEASE = 4.0 CFS



CLAREMONT BUSINESS PARK 2 FIL. NO.2  
 PROP. CONDITIONS DRAINAGE MAP

PROJECT NO. 10-022A FILE: \dwg\Eng Exhibits\10020 PDM.dwg

DESIGNED BY: DLM SCALE: DATE: 02-24-2023  
 DRAWN BY: DLM HORIZ: 1"=60'  
 CHECKED BY: VAS VERT: N/A SHEET 1 OF 1 PDM01

Move "Lot 1" text that is behind "Claremont"

Show riprap

Label DP3

Label rundowns

Move text over so the "4" in "Pond 4" is visible.

-Add contour labels  
 -Indicate if facilities are public or private

Label proposed storm pipe.

Fix cut off label

File: C:\10020-2-CBP-Dunkin\Drawings\Drainage\Map\10020-PDM.dwg Plotstamp: 2/28/2023 11:06 AM

FOR LOCATING & MARKING GAS, ELECTRIC, WATER & TELEPHONE LINES  
 FOR BURIED UTILITY INFORMATION 48 HRS BEFORE YOU DIG CALL 1-800-922-1987

**EXCERPT OF "FINAL DRAINAGE REPORT FOR CLAREMONT  
BUSINESS PARK FIL NO. 2 ", BY MATRIX DESIGN DATED  
NOVEMBER 2006  
&  
EXISTING DRAINAGE MAP**




**FINAL DRAINAGE REPORT**  
**For**  
**“Claremont Business Park Filing No. 2”**

Prepared for:  
**El Paso County**  
**Department of Public Works**  
**Engineering Division**

On Behalf of:  
**Claremont Development, Inc.**

Prepared by:



**Matrix Design Group, Inc.**  
Integrated Design Solutions     *Infrastructure Engineering*  
*Community Development*  
*Program Management*

2435 Research Parkway, Suite 300  
Colorado Springs, CO 80920  
(719) 575-0100  
fax (719) 572-0208

Revised November 2006



**Engineer's Statement:**

The *revisions* (changes made to the base Final Drainage Report since July, 2006) to the attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. The revisions encompassed adding additional right of way to the study area at the County's request, the handling of offsite drainage due to the additional right of way, a breakdown of private drainage within lot numbers 10 through 25 of Filing No. 2 due to cross-lot drainage (contrary to note # 25 on the recorded plat), profiling additional inlets along the channel edge, and rip-rap sizing for outlet structures along the channel. The Final Drainage Report dated July, 2006 was prepared under the direct supervision of Richard G. Gallegos, Jr. in July, 2006 and stamped (see next sheet).

The Final Drainage Report was prepared according to the criteria established by the County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing the *revisions* to this report.

---

Brady A. Shyrock  
Registered Professional Engineer  
State of Colorado  
No. 38164

SEAL




**Engineer's Statement:**

The attached drainage plan and report were prepared under my direction and supervision and are correct to the best of my knowledge and belief. Said drainage report has been prepared according to the criteria established by the County for drainage reports and said report is in conformity with the master plan of the drainage basin. I accept responsibility for any liability caused by any negligent acts, errors or omissions on my part in preparing this report.

SEAL

Richard G. Gallegos, Jr.  
Registered Professional Engineer  
State of Colorado  
No. 36247



**Developer's Statement:**

I, the developer have read and will comply with all of the requirements specified in this drainage report and plan.

Claremont Development, Inc.

Business Name

By: \_\_\_\_\_

Title: \_\_\_\_\_

Address: 3460 Capital Drive

Colorado Springs, CO 80915

**El Paso County:**

Filed in accordance with Section 51.1 of the El Paso Land Development Code, as amended.

*John Hamacher*  
Mr. John McCarty, County Engineer/Director

4/23/07  
Date

Conditions:

**D. Drainage and Bridge Fees**

Claremont Business Park Filing No. 2 has not been previously platted. The drainage basin and bridge fees have been determined per the El Paso County Drainage Basin Fees Sheet, dated February 3, 2006, Resolution No. 06-31. The site is located entirely within the Sand Creek Drainage Basin. The fees are based upon the percent impervious of the development, which have been included within the appendix of this report. The fees due have been calculated as follows.

**Claremont Business Park Filing No. 2**  
Final Drainage Report  
Drainage and Bridge Fees

	Area (ac.)	Fee/Imp. Acre	% Imp.	Fee Due	Reimbursable Const. Costs	Fee Credit	Fee Due at Platting	Fee Credit Remaining
Drainage Fee	62.967	\$15,000.00	80%	\$755,604.00	\$0.00	\$1,225,355.45	\$0.00	\$469,751.45
Bridge Fee	62.967	\$1,503.00	80%	\$75,711.52	\$75,711.52	\$0.00	\$0.00	\$0.00
<b>Total Fee Due at Platting</b>							<b>\$0.00</b>	

The developer of Claremont Business Park is completing the construction of the channel improvements on behalf of the Central Marksheffel Metropolitan District. The construction costs for both Filing 1 and Filing 2 combined exceed the drainage fees due for the site. No drainage fees will be required at the time of platting.

It should be noted that the Central Marksheffel Business District is reimbursing the developer of Claremont Business Park Filing 2 for the construction costs of the channel minus the drainage fees due for the site. The District has \$1,225,355.45 of drainage credits available within the Sand Creek Basin. This credit amount is based upon the construction cost estimate for the channel minus the drainage fees assessed for Claremont Business Park Filing No. 1. The District will use an additional \$755,604.00 of the drainage credits for the platting of Claremont Business Park Filing No. 2. The District will have \$469,751.45 of drainage credits left within the Sand Creek Fee basin.


The Central Marksheffel Business District has also constructed the Marksheffel Road Bridge over East Fork Sand Creek. This structure has been identified as a needed public improvement within the Drainage Basin Planning Study for Sand Creek and is eligible for reimbursement. Since the construction of the Marksheffel Bridge is in excess of the \$75,711.52 in bridge fees due for this site, no bridge fees are required at the time of platting. The fee will be deducted from the eligible reimbursable construction costs of the bridge and the remaining credits will be utilized or reimbursement applied for by the Central Marksheffel Business District.



DESIGN POINT SUMMARY

NO.	DATE	DESCRIPTION
1	02/15/2017	PRELIMINARY
2	03/15/2017	REVISED
3	04/15/2017	REVISED
4	05/15/2017	REVISED
5	06/15/2017	REVISED
6	07/15/2017	REVISED
7	08/15/2017	REVISED
8	09/15/2017	REVISED
9	10/15/2017	REVISED
10	11/15/2017	REVISED
11	12/15/2017	REVISED
12	01/15/2018	REVISED
13	02/15/2018	REVISED
14	03/15/2018	REVISED
15	04/15/2018	REVISED
16	05/15/2018	REVISED
17	06/15/2018	REVISED
18	07/15/2018	REVISED
19	08/15/2018	REVISED
20	09/15/2018	REVISED
21	10/15/2018	REVISED
22	11/15/2018	REVISED
23	12/15/2018	REVISED
24	01/15/2019	REVISED
25	02/15/2019	REVISED
26	03/15/2019	REVISED
27	04/15/2019	REVISED
28	05/15/2019	REVISED
29	06/15/2019	REVISED
30	07/15/2019	REVISED
31	08/15/2019	REVISED
32	09/15/2019	REVISED
33	10/15/2019	REVISED
34	11/15/2019	REVISED
35	12/15/2019	REVISED
36	01/15/2020	REVISED
37	02/15/2020	REVISED
38	03/15/2020	REVISED
39	04/15/2020	REVISED
40	05/15/2020	REVISED
41	06/15/2020	REVISED
42	07/15/2020	REVISED
43	08/15/2020	REVISED
44	09/15/2020	REVISED
45	10/15/2020	REVISED
46	11/15/2020	REVISED
47	12/15/2020	REVISED
48	01/15/2021	REVISED
49	02/15/2021	REVISED
50	03/15/2021	REVISED
51	04/15/2021	REVISED
52	05/15/2021	REVISED
53	06/15/2021	REVISED
54	07/15/2021	REVISED
55	08/15/2021	REVISED
56	09/15/2021	REVISED
57	10/15/2021	REVISED
58	11/15/2021	REVISED
59	12/15/2021	REVISED
60	01/15/2022	REVISED
61	02/15/2022	REVISED
62	03/15/2022	REVISED
63	04/15/2022	REVISED
64	05/15/2022	REVISED
65	06/15/2022	REVISED
66	07/15/2022	REVISED
67	08/15/2022	REVISED
68	09/15/2022	REVISED
69	10/15/2022	REVISED
70	11/15/2022	REVISED
71	12/15/2022	REVISED
72	01/15/2023	REVISED
73	02/15/2023	REVISED
74	03/15/2023	REVISED
75	04/15/2023	REVISED
76	05/15/2023	REVISED
77	06/15/2023	REVISED
78	07/15/2023	REVISED
79	08/15/2023	REVISED
80	09/15/2023	REVISED
81	10/15/2023	REVISED
82	11/15/2023	REVISED
83	12/15/2023	REVISED
84	01/15/2024	REVISED
85	02/15/2024	REVISED
86	03/15/2024	REVISED
87	04/15/2024	REVISED
88	05/15/2024	REVISED
89	06/15/2024	REVISED
90	07/15/2024	REVISED
91	08/15/2024	REVISED
92	09/15/2024	REVISED
93	10/15/2024	REVISED
94	11/15/2024	REVISED
95	12/15/2024	REVISED
96	01/15/2025	REVISED
97	02/15/2025	REVISED
98	03/15/2025	REVISED
99	04/15/2025	REVISED
100	05/15/2025	REVISED

# DRAINAGE PLAN CLAREMONT BUSINESS PARK FILING NO. 2




<p>REFERENCE DRAWINGS</p> <p>1. 18" x 24" - 04-02-001</p> <p>2. 18" x 24" - 04-02-001</p> <p>3. 18" x 24" - 04-02-001</p> <p>4. 18" x 24" - 04-02-001</p> <p>5. 18" x 24" - 04-02-001</p> <p>6. 18" x 24" - 04-02-001</p> <p>7. 18" x 24" - 04-02-001</p> <p>8. 18" x 24" - 04-02-001</p> <p>9. 18" x 24" - 04-02-001</p> <p>10. 18" x 24" - 04-02-001</p>		<p>NO.</p> <p>DATE</p> <p>DESCRIPTION</p> <p>BY</p> <p>REVISIONS</p> <p>BENCHMARK DATA/ELEV.</p> <p>(94.114) 888.888.888.888</p> <p>(7) DESCRIPTION / LOCATION</p>	
<p>SUBDIVIDER</p> <p>HAMMERS CONSTRUCTION INC.</p> <p>3460 W. STATE ST.</p> <p>COLORADO SPRINGS, CO 80915-9710</p>		<p>FOR AND ON BEHALF OF</p> <p>MARKIX DESIGN GROUP, INC.</p>	
<p>CLAREMONT BUSINESS PARK</p> <p>REVISED FINAL DRAINAGE PLAN</p> <p>MASTER DEVELOPMENT DRAINAGE PLAN</p> <p>REVISED FINAL DRAINAGE PLAN</p> <p>FILING NO. 2</p>		<p>DR02</p>	



**BOCC RESOLUTION 16-426**

502  
Chuck Broerman  
11/28/2016 11:50:04 AM  
Doc \$0.00 2  
Rec \$0.00 Pages

EL PASO COUNTY, W



216137149

**RESOLUTION NO. 16- 426**

**BOARD OF COUNTY COMMISSIONERS  
COUNTY OF EL PASO, STATE OF COLORADO**

**Resolution Denying an Appeal by Hammers Construction LLC (APP-16-002) of the Administrative Determination made by the Planning and Community Development Department Executive Director regarding the requirement for permanent/post construction Water Quality (permanent stormwater quality best management practices or BMP's).**

**WHEREAS**, pursuant to §§30-11-101(1)(e) and 30-11-107(1)(e), C.R.S., the Board of County Commissioners of El Paso County, Colorado (hereinafter "Board") has the legislative authority to manage the concerns of El Paso County when deemed by the Board to be in the best interests of the County and its inhabitants; and

**WHEREAS**, after consultation with the County Attorney's Office, the Executive Director of Planning and Community Development on August 4, 2016 issued an administrative determination finding made an administrative determination that all undeveloped lots within the Claremont Business Park are subject to installation of permanent stormwater management best management practices (BMP's) associated with development, and that the terms of a 2008 approved deviation relieving the developer of the requirements have not been met.; and

**WHEREAS**, an appeal of the administrative determination was filed by Hammers Construction on August 10, 2016, and a hearing date was set for September 27, 2016 to hear the appeal; and

**WHEREAS**, the hearing was continued to a date certain of November 22, 2016; and

**WHEREAS**, at the Applicant's appeal hearing on November 22, 2016, testimony from the Applicant and the Applicant's representatives was heard by the Board in favor of the appeal, testimony from representatives of Planning and Community Development Department and was presented, and such testimony and associated evidence was weighed by the Board; and



**WHEREAS**, the Board, having reviewed the testimony and evidence, hereby finds and determines that the requested appeal of the administrative determination by the Planning and Community Development Executive Director by the Applicant did not satisfy the criteria of approval to overturn the administrative determination.

**NOW, THEREFORE, BE IT RESOLVED** that the Board of County Commissioners of El Paso County, Colorado, hereby denies the appeal of the administrative determination by Hammers Construction and determines that permanent stormwater management best management practices (BMP's) are required with new development within the Claremont Business Park: and

**BE IT FURTHER RESOLVED** that Sallie Clark, duly elected, qualified member and Chair of the Board of County Commissioners, or Darryl Glenn, duly elected, qualified member and Vice Chair of the Board of County Commissioners, be and is hereby authorized on behalf of the Board to execute any and all documents necessary to carry out the intent of the Board as described herein.

**DONE THIS 22<sup>nd</sup>** day of November, 2016, at Colorado Springs Colorado.


**BOARD OF COUNTY COMMISSIONERS  
EL PASO COUNTY, COLORADO**

ATTEST:  Richard D. Broerman  
County Clerk & Recorder

By: Sallie Clark  
Chair of the Board


# V1\_Final Drainage Report Redlines.pdf Markup Summary

## Glenn Reese - EPC Stormwater (33)



**Subject:** SW - Textbox with Arrow  
**Page Label:** 11  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 3:36:12 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Pond 4 is shown as future on drainage map on pdf pg 126 below. Revise text and/or map to remove discrepancy.



**Subject:** SW - Textbox with Arrow  
**Page Label:** 15  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 3:48:58 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Which two? This section only previously mentions Pond 3.

ance of acreage run  
ry to the two SFBs are  
d along Meadowbrook  
y the property owners


**Subject:** SW - Highlight  
**Page Label:** 15  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 3:47:36 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

the two SFBs




**Subject:** SW - Textbox with Arrow  
**Page Label:** 15  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 3:49:06 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

This paragraph only mentions Pond 1 and 2. What about Pond 4 and 5? (Pond 3 already previously discussed in this section)




**Subject:** Image  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 3:54:55 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Make a column for each of the 5 ponds.



**Subject:** SW - Textbox with Arrow  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:21:45 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

delete this column if no RR is anticipated for this site.



**Subject:** SW - Textbox with Arrow  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:21:48 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add rows for each basin within this filing.

**Subject:** SW - Textbox with Arrow  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:21:43 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add rows for each basin within this filing.

and calculations used to create the proposed plan sheet. Review Part 2 Filing No.1 and not identify other the same design features and proposed storm water and road meeting features. All storage facilities structural types and sizes that are necessary or needed to manage storm water and runoff are identified. The design of the storm water management features and structures shall be based on a comprehensive analysis of the site and its surroundings.

**Subject:** SW - Textbox  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:22:36 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Completing a "Water Quality Treatment Summary Table" like the example provided below would greatly help us clearly see that WQ req's are being met for the whole site, if you could do one for this site.

From the PBMP Form, this column should be blank.

**Subject:** SW - Textbox with Arrow  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:21:52 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

From the PBMP Form, this column should be blank.

Upon individual lot development but go report that will be submitted with the final emergency flow routes on site and

**Subject:** SW - Textbox with Arrow  
**Page Label:** 16  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:21:50 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

The areas of Basin G1, O1, O2, and P would be in this column

Define "Remodeled Existing Conditions." How is this different for the other calcs for this same pond shown on pdf page 60 below? Please discuss in the FDR text above.

**Subject:** SW - Textbox with Arrow  
**Page Label:** 48  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/29/2023 7:53:46 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Define "Remodeled Existing Conditions." How is this different for the other calcs for this same pond shown on pdf page 60 below? Please discuss in the FDR text above.

Define "Remodeled Existing Conditions." How is this different for the other calcs for this same pond shown on pdf page 60 below? Please discuss in the FDR text above.


**Subject:** SW - Textbox  
**Page Label:** 48  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:31:23 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

Define "Remodeled Existing Conditions." How is this different for the other calcs for this same pond shown on pdf page 60 below? Please discuss in the FDR text above.

**Subject:** SW - Textbox  
**Page Label:** 54  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:31:37 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"



**Subject:** SW - Textbox  
**Page Label:** 60  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:31:43 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"

User Input: Orifice at  
 Underd  
 Unc

**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:52:01 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Input: Orifice at Und  
 Underdrain  
 Underdr  
 Input: Orifice Plate

**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:53:39 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

User Input: Ov  
 Overflc  
 Ov

**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:54:08 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Overflow Weir Fr  
 Overflow We  
 Overfl  
 Horiz.

**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:54:28 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Overflow Weir  
 Overflc  
 Horiz. L  
 C

**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:54:30 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

User Input: Outlet Pipe  
 Depth  
 Restrictor Plate H

**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:54:55 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Depth to Inver  
Outlet  
Factor Plate Height Ab



**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:54:57 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Restrict  
User Input:



**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:58:14 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Emergency Spillwa  
Spillwa  
Spillwa  
c



**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:59:34 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Emergency Spillwa  
Spillwa  
Spillwa  
Spillwa  
reehward above Max



**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:59:36 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Spillway  
Spillway C  
Spillway  
board above Max W



**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:59:37 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Freeboa




**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:59:39 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Time to l  
Time to l  
Area




**Subject:** Checkmark  
**Page Label:** 66  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 5:05:26 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0




**Subject:** SW - Textbox  
**Page Label:** 72  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:32:05 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"



**Subject:** SW - Textbox  
**Page Label:** 78  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:32:11 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add text to the PDF at the top of all calc sheets of ponds that aren't to be constructed with this project (ie: just the roads and Pond 3) that these "CALCS PROVIDED FOR INFORMATION ONLY, POND # [insert "1," "2," "4", and "5" as appropriate] TO BE DESIGNED AND CONSTRUCTED WITH FUTURE DEVELOPMENT"




**Subject:** SW - Textbox with Arrow  
**Page Label:** 84  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/29/2023 7:53:32 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Define "Remodeled Proposed Conditions." How is this different for the other calcs for this same pond shown on pdf page 60 above? Please discuss in the FDR text above.



**Subject:** SW - Textbox with Arrow  
**Page Label:** 126  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 3:36:29 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0


Move text over so the "4" in "Pond 4" is visible.



**Subject:** SW - Textbox with Arrow  
**Page Label:** 126  
**Author:** Glenn Reese - EPC Stormwater  
**Date:** 3/28/2023 4:05:52 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Move "Lot 1" text that is behind "Claremont"

**CDurham (38)**



**Subject:** Callout  
**Page Label:** 3  
**Author:** CDurham  
**Date:** 3/30/2023 9:55:19 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Move Ex & Pr Drainage Maps to back of report



**Subject:** Callout  
**Page Label:** 7  
**Author:** CDurham  
**Date:** 3/30/2023 10:02:27 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label chase on existing drainage map.

7. Basin H3 is  
talt p  
nto th  
hydrology spreadsheet  
16 and DP1-3.  
ist of roof top,

**Subject:** Callout  
**Page Label:** 8  
**Author:** CDurham  
**Date:** 3/30/2023 10:09:50 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

DP3 thru 5 per hydrology spreadsheet

inlets located at DP6. Collected runoff  
to an existing WQ pond (PR13-14)  
d Q5=0.4 cfs of flow-by in the respective  
h Q5=0.2 cfs and Q5=0.3 cfs of flow-by  
inlets continue westward to Design Poi  
7.5 cfs) consists of flow-by runoff from  
es of rooftop, asphalt paving and landsc  
removed within the curb and gutter to

**Subject:** Callout  
**Page Label:** 8  
**Author:** CDurham  
**Date:** 3/30/2023 10:12:56 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Q100

flows within  
Runoff from  
15' Type R at  
nd Q5=0.2 cfs  
e intercepted

**Subject:** Callout  
**Page Label:** 8  
**Author:** CDurham  
**Date:** 3/30/2023 10:18:20 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Q100

is collected in curb and gutter which discha  
WQ Pond 2  
= 16.5 cfs) consists of runoff from Basin 13, 1  
43, 0.23, and 0.19 acres in size respectively an  
as within the development. The runoff fr  
hin the private street section of Gary Watson  
inlets located at DP6. Collected runoff is c  
wer to an existing WQ pond (PR13-14). Inl  
nd Q5=0.4 cfs of flow-by in the respective st

**Subject:** Callout  
**Page Label:** 8  
**Author:** CDurham  
**Date:** 3/30/2023 11:20:00 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

WQ Pond 2

t  
3  
b

**Subject:** Text Box  
**Page Label:** 9  
**Author:** CDurham  
**Date:** 3/30/2023 11:23:36 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

3

IK1 is 0.17  
whole  
flows  
DP10-13.  
nd 21.

**Subject:** Callout  
**Page Label:** 9  
**Author:** CDurham  
**Date:** 3/30/2023 11:25:50 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Is this Inlet 7 as labeled on the existing drainage map? If so, please include the name in the text.

(Inlet 1)

**Subject:** Text Box  
**Page Label:** 11  
**Author:** CDurham  
**Date:** 3/30/2023 11:53:27 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

(Inlet 1)

its.  
| (Inlet 2)

**Subject:** Text Box  
**Page Label:** 11 (Inlet 2)  
**Author:** CDurham  
**Date:** 3/30/2023 11:54:32 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

..., asphalt  
: x 6 inch  
on Point.  
asin H2 is  
aving and  
te cul-de-

Label chase on  
drainage map

**Subject:** Callout  
**Page Label:** 12 Label chase on drainage map  
**Author:** CDurham  
**Date:** 3/30/2023 12:01:58 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

ilt paving  
o the cul-  
id DP1-3.  
roof top,

DP 3 thru 5

**Subject:** Callout  
**Page Label:** 12 DP 3 thru 5  
**Author:** CDurham  
**Date:** 3/30/2023 12:10:39 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

and Q5=0.4 cfs of flow-by in the respect  
ith Q5=0.0 cfs and Q5=0.3 cfs of flow-b  
lets continues westward to Design Pair

Q100

**Subject:** Callout  
**Page Label:** 13 Q100  
**Author:** CDurham  
**Date:** 3/30/2023 12:11:46 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

1 and flow-by from the inlet  
nlets located at DP7. Inlet  
flow-by in the respective :  
pted runoff underneath Gar  
Point 13 (Q5 = 1.0 cfs, Q10

DP12

**Subject:** Callout  
**Page Label:** 13 DP12  
**Author:** CDurham  
**Date:** 3/30/2023 12:14:01 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

s flow into an  
DP9. Basins  
alt paving and


DP14

**Subject:** Callout  
**Page Label:** 13 DP14  
**Author:** CDurham  
**Date:** 3/30/2023 12:17:08 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

3


**Subject:** Text Box  
**Page Label:** 13 3  
**Author:** CDurham  
**Date:** 3/30/2023 12:19:57 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0





**Subject:** Callout  
**Page Label:** 14  
**Author:** CDurham  
**Date:** 3/30/2023 12:22:24 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

DP15-18



**Subject:** Callout  
**Page Label:** 32  
**Author:** CDurham  
**Date:** 3/30/2023 12:29:19 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

DP14



**Subject:** Callout  
**Page Label:** 32  
**Author:** CDurham  
**Date:** 3/30/2023 12:30:21 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

DP15 thru 18 instead of 10 thru 13

Label various ponds as existing, proposed or future .

**Subject:** Text Box  
**Page Label:** 113  
**Author:** CDurham  
**Date:** 3/30/2023 4:16:44 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label various ponds as existing, proposed or future .

Try to print all of stormcad table on one sheet, or include "Label" column with second sheet

Length (Unified)

**Subject:** Text Box  
**Page Label:** 114  
**Author:** CDurham  
**Date:** 3/30/2023 4:18:28 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Try to print all of stormcad table on one sheet, or include "Label" column with second sheet

Include pipe slope in table. ID, Fr #, % Flow/Capacity, critical depth, & EGL's is not needed in table.

Length does not match CD's

**Subject:** Text Box  
**Page Label:** 114  
**Author:** CDurham  
**Date:** 3/30/2023 4:32:48 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Include pipe slope in table. ID, Fr #, % Flow/Capacity, critical depth, & EGL's is not needed in table.

**Subject:** Callout  
**Page Label:** 114  
**Author:** CDurham  
**Date:** 3/30/2023 4:50:00 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Length does not match CD's

4	1.8	4.1	H6, U
5	2.0	1.4	H6, V
6	2.2	1.6	SP-6, U
7	2.4	2.5	FR MATL
8	2.6	4.1	FR MATL
9	2.8	6.7	FR MATL
10	3.0	9.3	SP, ML, U
11	3.2	11.9	SP, ML, V
12	3.4	14.5	FR MATL
13	3.6	17.1	FR MATL
14	3.8	19.7	FR MATL


**Subject:** Callout  
**Page Label:** 124  
**Author:** CDurham  
**Date:** 3/30/2023 12:38:08 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

H4

Add Contour Labels


**Subject:** Text Box  
**Page Label:** 124  
**Author:** CDurham  
**Date:** 3/30/2023 12:38:23 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Add Contour Labels




**Subject:** Callout  
**Page Label:** 124  
**Author:** CDurham  
**Date:** 3/30/2023 12:38:44 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Labels cut off




**Subject:** Callout  
**Page Label:** 124  
**Author:** CDurham  
**Date:** 3/30/2023 12:39:09 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label rundowns



**Subject:** Callout  
**Page Label:** 124  
**Author:** CDurham  
**Date:** 3/30/2023 12:40:03 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label pipe




**Subject:** Callout  
**Page Label:** 124  
**Author:** CDurham  
**Date:** 3/30/2023 12:39:41 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label chase



**Subject:** Cloud+  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:40:37 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Show riprap




**Subject:** Callout  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:41:02 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label DP 17




**Subject:** Callout  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:42:39 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label rundowns



**Subject:** Callout  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:42:50 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Fix cut off label



**Subject:** Callout  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:43:06 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

DP15-18

STRUCTURE
18" PP
15" PP
15" PP
PROP 5' INLET

**Subject:** Highlight  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:43:14 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

15" PP
15" PP
ROP 5' INLET

**Subject:** Highlight  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:43:16 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

MARY	18" per report
SIN	STRUCTURE
B	18" PP
D	15" PP
F	15" PP

**Subject:** Callout  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:43:28 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

18" per report

-Add contour labels  
- Indicate if facilities are public or private

**Subject:** Text Box  
**Page Label:** 126  
**Author:** CDurham  
**Date:** 3/30/2023 12:44:07 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

-Add contour labels  
- Indicate if facilities are public or private

Carlos (10)

120  
VR233

**Subject:** Text Box  
**Page Label:** 1  
**Author:** Carlos  
**Date:** 3/28/2023 3:03:19 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

VR233

Joshua Palmer  
Interim County Engineer

**Subject:** Line  
**Page Label:** 2  
**Author:** Carlos  
**Date:** 3/20/2023 9:40:33 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Joshua Palmer, P.E.  
Interim County Engineer / ECM Administrator  
Remove

**Subject:** Callout  
**Page Label:** 2  
**Author:** Carlos  
**Date:** 3/28/2023 3:03:37 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Remove

Interim County Engineer / ECM Administrator

**Subject:** Text Box  
**Page Label:** 13  
**Author:** Carlos  
**Date:** 3/28/2023 11:29:53 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Include O1 in DP12 and show flow arrows for O1

Interim County Engineer / ECM Administrator

**Subject:** Highlight  
**Page Label:** 15  
**Author:** Carlos  
**Date:** 3/28/2023 11:36:50 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

(equal shares determined by size of lots 8-10)

Interim County Engineer / ECM Administrator

**Subject:** Callout  
**Page Label:** 15  
**Author:** Carlos  
**Date:** 3/28/2023 11:37:22 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Lots 8-10 are being renamed with the subdivision.  
Please revise lot numbers.

at structures into an existing storm sewer  
to pond 4 with the proposed pond 2  
and 3. Minor quality pond 2  
with final stormwater treatment for  
use for access and maintenance of the pipe  
and final treatment (the final drainage report).

The report identifies Pond 3 being built and  
Pond 4 being removed. Please review  
the report for consistency.

revision control plan (CCP) with the drainage  
report. Note that water control, sediment basin  
at the DCM Volume 2.

**Subject:** Text Box  
**Page Label:** 15  
**Author:** Carlos  
**Date:** 3/28/2023 3:58:49 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

The report identifies Pond 3 being built and Pond 5 (location of existing sediment basin on Tract B) being removed. Please revise paragraph for consistency.


EXISTING POND TO BE  
FILLED

PROP. ST. TYPE R  
SUMP INLET  
(INLET 1)

Label DP3


**Subject:** Text Box  
**Page Label:** 16  
**Author:** Carlos  
**Date:** 3/28/2023 5:01:52 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Provide an estimate of the proposed imperviousness of the site and difference from the previously approved drainage report.



**Subject:** Callout  
**Page Label:** 126  
**Author:** Carlos  
**Date:** 3/27/2023 4:34:08 PM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label DP3



**Subject:** Callout  
**Page Label:** 126  
**Author:** Carlos  
**Date:** 3/28/2023 11:26:03 AM  
**Length:** 0  
**Area:** 0  
**Volume:** 0

Label proposed storm pipe.