

March 13, 2023



**ENTECH**  
ENGINEERING, INC.

505 ELKTON DRIVE  
COLORADO SPRINGS, CO 80907  
PHONE (719) 531-5599  
FAX (719) 531-5238

GWH, LLC  
6547 North Academy Boulevard, Suite 1009  
Colorado Springs, CO 80918

Attn: Rocky Manning

Re: Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

Please add:  
PCD File SF2521

Dear Mr. Manning:

## GENERAL SITE CONDITIONS AND PROJECT DESCRIPTION

The site is located in the SW¼ of Section 12, Township 14 South, Range 63 West of the 6<sup>th</sup> Principal Meridian in El Paso County, Colorado. The site is located approximately 15 miles east of Colorado Springs, Colorado, east of Peyton Highway and Highway 94 in El Paso County, Colorado. The location of the site is as shown on the Vicinity Map, Figure 1.

The topography of the site is generally gradually sloping to the southeast. Three dry drainages were observed on the site, in the southwest corner, the south-central portion and along the east portion of the site. The drainage swales trend in a south to southeasterly direction. Water was not observed in the drainages at the time of this investigation. The site boundaries are indicated on the USGS Map, Figure 2. Previous land uses have included residential, agricultural grazing and undeveloped land. The site contains primarily field grasses, weeds, and yucca with planted trees around the existing homes and the corral areas in the northwest portion of the site. Site photographs, taken February 1, 2023, are included in Appendix A.

Total acreage involved in the proposed subdivision is 60-acres. A new rural subdivision consisting of 10 lots is planned for the replat. The lots for this site are anticipated to be approximately 5 to 7-acres in size. The lots will be serviced by individual on-site wastewater treatment systems and water wells. The Site Plan is presented in Figure 3.

## LAND USE AND ENGINEERING GEOLOGY

9

This site was found to be suitable for the proposed development, which will consist of rural, residential lots and associated site improvements. Areas were encountered where the geologic conditions will impose some constraints on development and land use. These include areas of floodplains, seasonally shallow groundwater, and potentially seasonal shallow groundwater areas. Based on the proposed development plan, it appears that these areas will have minor impacts on the development. These conditions will be discussed in greater detail in the report.

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

In general, it is our opinion that the development can be achieved if the observed geologic conditions on site are properly mitigated. All recommendations are subject to the limitations discussed in the report.

## **SCOPE OF THE REPORT**

The scope of the report includes a general geologic analysis utilizing published geologic data. Detailed site-specific mapping will be conducted to obtain general information with respect to major geographic and geologic features, geologic descriptions and their effects on the development of the property.

## **FIELD INVESTIGATION**

Our field investigation consisted of the preparation of a geologic map of bedrock features and significant surficial deposits. The Natural Resource Conservation Service (NRCS) (Reference 2), previously the Soil Conservation Service (SCS) survey was also reviewed to evaluate the site (Reference 3). The position of mappable units within the subject site are shown on the Geologic Map Figure, 6. Our mapping procedures involved both field reconnaissance and measurements, and aerial photo reconnaissance and interpretation. The field mapping was performed by personnel of Entech Engineering, Inc. on February 1, 2023.

Six (6) test borings were drilled and five (5) test pits were excavated on the site to determine general suitability of the soil characteristics for residential construction and on-site wastewater treatment systems. The locations of the test borings are indicated on the Site Plan/Test Boring Location Map, Figure 3. The Test Boring Logs are presented in Appendix B, and Laboratory Testing results are included in Appendix C.

## **SOIL AND GEOLOGIC CONDITIONS**

### Soil Survey

The Natural Resource Conservation Service (NRCS) (Reference 2, Figure 4), previously the Soil Conservation Service (Reference 3) has mapped two soil types on the site. Complete descriptions of the soils are presented in Appendix D. In general, the soils consist of loamy sand and sandy loam. The soils are described as follows:

Type	Description
19	Columbine Gravelly Sandy Loam, 0 – 3% Slopes
28	Ellicott loamy Coarse Sand, 0 – 5% Slopes

The Columbine Gravelly Sandy Loam has been described to have rapid permeabilities and the Ellicott Loamy Coarse Sand has been described to have very limited permeabilities. The soils are described as well suited for use as home sites. Possible hazards with soils erosion are

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

present on the site. The erosion potential can be controlled with vegetation. The soils have been described to have moderate erosion hazards (Reference 2).

### Soils

Two soil types were encountered in the test borings on the site. Soil Type 1: slightly silty to silty sand (SM, SM-SW) and Soil Type 2: sandy silt. Bedrock was not encountered in the test borings which were drilled to 20 feet bgs. Each soil type was classified in accordance with the Unified Soil Classification System (USCS) using the laboratory testing results.

Soil Type 1 classified as slightly silty to silty sand (SM, SM-SW). The sand was encountered in Test Boring Nos. 1 through 4 and 6 at the existing ground surface and at 3 feet below ground surface (bgs) extending to the termination of test borings (20 feet). Standard Penetration Testing on the sand resulted in N-values of 7 to greater than 50 blows per foot (bpf) indicating loose to very dense states. The very high blow counts encountered in the test borings are due to gravel. The majority of the sands were encountered at medium dense to dense states. Water content and grain size testing resulted in approximately 1 to 18 percent water content with 5 to 19 percent of the soil size particles passing the No. 200 sieve. Atterberg limit test was performed on samples of the slightly silty to silty sand resulted in Liquid Limits of No-Value and Plastic Indexes of Non-Plastic. Sulfate testing resulted in less than 0.01 to 0.02 percent soluble sulfate by weight, indicating negligible to low potential for below grade concrete degradation due to sulfate attack.

Soil Type 2 classified as slightly sandy silt (ML). The silt was encountered in Test Boring No. 5 at the existing ground surface and extending to 3 feet bgs. Standard Penetration Testing on the silt resulted in N-values of 17 bpf indicating stiff consistencies. Water content and grain size testing resulted in approximately 8 percent water content with 78 percent of the soil size particles passing the No. 200 sieve. The silt soils are anticipated to be penetrated by the foundation excavation

### Groundwater

Groundwater was encountered in Test Boring Nos. 1, 3 and 4 at depths of 10 to 12 feet. It is not anticipated that groundwater will affect construction of shallow crawl space foundations. Basements should be excavated to a maximum depth of 6 feet in areas with water at 10 feet. It should be noted that fluctuation in groundwater levels could change due to seasonal variations, changes in land runoff characteristics and future development of nearby areas. Isolated sand layers within the soil profile can carry water in the subsurface. Contractors should be cognizant of the potential for the occurrence of subsurface water during construction.

### Geology

Approximately 25½ miles west of the site is the southern extent of a major structural feature known as the Rampart Range Fault. This fault marks the boundary between the Great Plains Physiographic Province and the Southern Rocky Mountain Province. The site exists within a large structural feature known as the Denver Basin. Bedrock in the area is typically gently

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

dipping in a northerly direction (Reference 4). Overlying the Dawson Formation are alluvial deposited sands and clays.

The geology of the site was evaluated using the *Geologic Map of Pueblo 1-degree x 2-degrees' quadrangle, South-Central Colorado*, by Scott, G.R., et.al. in 1976, (Reference 4, Figure 5). The Geology Map for the site is presented in Figure 6. One mappable unit was identified on this site which is described as follows:

**Q1 Louviers Alluvium of Pleistocene Age:** These deposits are light brown silty sands which contain an abundance of gravels. They commonly occur as stream terrace deposits above the valley floors.

The soils listed above were mapped from site-specific mapping, the *Geologic map of the Pueblo 1-degree x 2-degrees' quadrangle, south-central Colorado* published by the U.S. Geologic Survey in 1976 (Reference 4). The test borings and test pits were used in evaluating the site and are included in Appendix B. The Geology Map prepared for the site is presented in Figure 6.

## ENGINEERING GEOLOGIC HAZARDS

Mapping has been performed on this site to identify areas where various geologic conditions exist of which developers should be cognizant during the planning, design and construction stages should new construction be proposed. The engineering geologic hazards identified on this site include potentially seasonally wet areas, seasonally wet areas, and shallow groundwater areas. These hazards and recommended mitigation techniques are discussed as follows:

### Loose or Collapsible Soils – Constraint

Loose or collapsible soils were encountered in the upper portions of two of the six borings drilled on the site.

**Mitigation:** The potential for settlement movement is directly related to saturation of the soils below the foundation areas. Therefore, good surface and subsurface drainage is extremely critical in these areas in order to minimize the potential for saturation of these soils. The ground surface around all permanent structures should be positively sloped away from the structure to all points, and water must not be allowed to stand or pond anywhere on the site. We recommend that the ground surface within 10 feet of the structures be sloped away with a minimum gradient of five percent. If this is not possible on the upslope side of the structures, then a well-defined swale should be created to intercept the surface water and carry it quickly and safely around and away from the structures. Roof drains should be made to discharge well away from the structures and into areas of positive drainage. Where several structures are involved, the overall drainage design should be such that water directed away from one structure is not directed against an adjacent building. Planting and watering in the immediate vicinity of the structures, as well as general lawn irrigation, should be minimized. Should loose

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

or collapsible soils be encountered beneath foundations, removal and recompaction of the upper 2 to 3 feet with thorough moisture conditioning and recompaction at 95% of Modified Proctor Dry Density, ASTM D-1557 will be necessary. **Specific recommendations should be made after additional investigation of each building site.**

Floodplain (fp) – Hazard:

December 7, 2018

Portions of the site lie within a floodplain zone according to the FEMA Map Nos. 08041CO807G and 08041CO809G, dated March 17, 2018 (Figure 7, Reference 6). The approximate FEMA floodplain boundaries are also indicated on the Engineering Geology Map, Figure 5. The exact location of the floodplain will be required prior to development. **Exact locations of floodplain and specific drainage studies are beyond the scope of this report.** Those areas that currently lie within the FEMA floodplain area will require approval of the Drainage Basin Report prior to construction. Structures should not block drainages. Significant grading and dewatering will be necessary should construction be considered in this area. Channelization of the floodplain and raising the building areas will be necessary. Finished floor levels must be located a minimum of one foot above floodplain levels. Two other areas in the southern portion of the lot are mapped as potentially seasonally wet these areas should be avoided or will require to be regrade if construction is mandatory.

Seasonally Wet Areas (sw) - Constraint:

In these areas, high subsurface moisture condition, frost heave potential and highly organic soils may exist, particularly on a seasonal basis.

Mitigation: These areas lie within drainages which will likely be avoided by construction. If development is desired, in these areas grading can mitigate the drainages. All organic material, soft or wet soils should be removed prior to any filling. The same mitigation recommendations for potentially high groundwater areas as discussed previously should be followed in these areas of seasonally high groundwater. In some areas, it may be necessary to dewater the excavation. Underslab drains or interceptor drains may be used in addition to perimeter drains to prevent the intrusion of water into areas below grade. Typical Drain Details are presented in Figures 8 through 9. It may be desirable to build up the building areas to raise the foundation further above the groundwater level. Any grading should be done in a manner that directs surface flow around construction to avoid areas of ponded water. Structures should not block drainages, but swales should be created to intercept surface runoff and carry it safely around and away from structures. Additional investigation will be necessary to determine the water depth and its effect on development once plans are available. Other areas than those mapped could encounter groundwater that could affect shallow foundations on-site.

Potentially Seasonally Wet Areas (psw) – Constraint:

In these areas, we would anticipate the potential for periodic high subsurface moisture conditions and frost heave potential. These areas did not indicate the yearly presence of shallow groundwater as the seasonal high groundwater areas did, however, based on topography and site conditions, the potential exists for high groundwater during high moisture

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

periods or years. The same mitigation recommendations for Seasonal High Groundwater areas apply to these Potentially Seasonal High Groundwater areas. Further investigation of each building site may be necessary to delineate the depth to groundwater. Groundwater may be at sufficient depth to not affect shallow foundations in these areas.

## RELEVANCE OF GEOLOGIC CONDITIONS TO LAND USE PLANNING

The proposed development will consist of subdividing the parcel for rural residential lots, and associated site improvements. The existing geologic and engineering geologic conditions will impose some minor constraints on development and construction. The geologic conditions on the site include loose or collapsible soils, and seasonal shallow groundwater areas which can be satisfactorily mitigated through proper engineering design and construction practices, or avoidance.

The upper granular soils in the borings drilled on the site were encountered at loose to very dense states. Loose or collapsible soils, if encountered beneath foundation or floor slabs, will require recompaction. Expansive layers may also be encountered on this site. Expansive soils, if encountered, will require mitigation/special foundation design. These soils will not prohibit development. Overexcavation and replacement with non-expansive soils at a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557 is a suitable mitigation, which is common in the area. Floor slabs on expansive soils should be expected to experience movement.

An active floodplain is mapped in the southwest corner of this site. No construction should take place without further investigation within the floodplain. (Drainage channels associated with the windblown sands are located in some areas across the site and that have been mapped as potentially seasonally wet areas and are discussed in the following section.) These low-lying areas are indicated in the Geology/Engineering Geology Map (Figure 6). Due to the lot sizes these areas can be avoided. In these areas, we would anticipate the potential for periodically high subsurface moisture conditions, frost heave potential and highly organic soils.

In summary, the granular soils will likely provide suitable support for shallow foundations. The geologic conditions encountered on site can be mitigated with avoidance or proper engineering and construction practices. **Individual investigations for new building sites and septic systems will be required prior to construction.**

## EROSION CONTROL

The soil types observed on the site are mildly to highly susceptible to wind erosion, and moderately to highly susceptible to water erosion. A minor wind erosion and dust problem may be created for a short time during and immediately after construction. Should the problem be considered severe enough during this time, watering of the cut areas or the use of chemical palliative may be required to control dust. However, once construction has been completed and vegetation re-established, the potential for wind erosion should be considerably reduced.

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

With regard to water erosion, loosely compacted soils will be the most susceptible to water erosion, residually weathered soils and weathered bedrock materials become increasingly less susceptible to water erosion. For the typical soils observed on site, allowable velocities or unvegetated and unlined earth channels would be on the order of 3 to 4 feet/second, depending upon the sediment load carried by the water. Permissible velocities may be increased through the use of vegetation to something on the order of 4 to 7 feet/second, depending upon the type of vegetation established. Should the anticipated velocities exceed these values, some form of channel lining material may be required to reduce erosion potential. These might consist of some of the synthetic channel lining materials on the market or conventional riprap. In cases where ditch-lining materials are still insufficient to control erosion, small check dams or sediment traps may be required. The check dams will serve to reduce flow velocities, as well as provide small traps for containing sediment. The determination of the amount, location and placement of ditch linings, check dams and of the special erosion control features should be performed by or in conjunction with the drainage engineer who is more familiar with the flow quantities and velocities.

Cut and fill slope areas will be subjected primarily to sheetwash and rill erosion. Unchecked rill erosion can eventually lead to concentrated flows of water and gully erosion. The best means to combat this type of erosion is, where possible, the adequate re-vegetation of cut and fill slopes. Cut and fill slopes having gradients more than three (3) horizontal to one (1) vertical become increasingly more difficult to revegetate successfully. Therefore, recommendations pertaining to the vegetation of the cut and fill slopes may require input from a qualified landscape architect and/or the Soil Conservation Service.

## **ROADWAY AND EMBANKMENT CONSTRUCTION RECOMMENDATIONS**

In general, the site soils are suitable for the proposed roadways and embankments. Groundwater should be expected to be encountered in deeper cuts and along drainage areas. If excavations encroach on the groundwater level unstable soil conditions may be encountered. Excavation of saturated soils will be difficult with rubber-tired equipment. Stabilization using shot rock or geogrids may be necessary.

Any areas to receive fill should have all topsoil, organic material or debris removed. Prior to fill placement Entech should observe the subgrade. Fill must be properly benched and compacted to minimize potentially unstable conditions in slope areas. Fill slopes should be 3:1. The subgrade should be scarified and moisture conditioned to within 2% of optimum moisture content and compacted to a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557, prior to placing new fill. Areas receiving fill may require stabilization with rock or fabric if shallow groundwater conditions are encountered.

New fill should be placed in thin lifts not to exceed 6 inches after compaction while maintaining at least 95% of its maximum Modified Proctor Dry Density, ASTM D-1557. These materials should be placed at a moisture content conducive to compaction, usually 0 to  $\pm 2\%$  of Proctor optimum moisture content. The placement and compaction of fill should be observed and

GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

tested by Entech during construction. Entech should approve any import materials prior to placing or hauling them to the site. Additional investigation will be required for pavement designs once roadway grading is completed and utilities are installed.

## **ECONOMIC MINERAL RESOURCES**

Some of the sandy materials on-site could be considered a low-grade sand resource. According to the *El Paso County Aggregate Resource Evaluation Map* (Reference 6), the area is mapped as upland deposits. According to the *Atlas of Sand, Gravel and Quarry Aggregate Resources, Colorado Front Range Counties* distributed by the Colorado Geological Survey (Reference 6), surrounding areas to the site are mapped as U3 – Upland Deposits: sand resource. According to the *Evaluation of Mineral and Mineral Fuel Potential* (Reference 7), the area of the site has been mapped as “Good” for industrial minerals. Generally, the Dawson formation does not contain significant industrial mineral resources. The sands associated with the eolian and alluvial deposits may be considered a sand resource. Considering the silty to clayey nature of much of these materials and abundance of similar materials through the region, they would be considered to have little significance as an economic resource.

According to the *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands* (Reference 7), the site is mapped within the Denver Basin Coal Region. However, the area of the site has been mapped as “Poor” for coal resources. No active or inactive mines have been mapped in the area of the site. No metallic mineral resources have been mapped on the site (Reference 7).

Areas neighboring the site have been mapped as “Fair” for oil and gas resources (Reference 7). No oil or gas fields have been discovered in the area of the site. Two wells were previously drilled in the area to 537 feet in 1924 to an unknown formation, and to 6,514 feet deep to the Jurassic Morrison Formation in 1972. No oil or gas was reported and both wells were plugged. The sedimentary rocks in the area may lack the geologic structure for trapping oil or gas; therefore, it would not be considered a significant resource.



GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

## CLOSURE

It should be pointed out that because of the nature of data obtained by random sampling of such variable nonhomogeneous materials as soil and rock, it is important that we be informed of any differences observed between surface and subsurface conditions encountered in construction and those assumed in the body of this report. Any new construction considered on this site will require additional investigation. Construction and design personnel should be made familiar with the contents of this report. Specific construction and foundation recommendations will be provided when investigations are completed at each building site prior to new construction.

This report has been prepared for GWH, LLC for application to the proposed development in accordance with generally accepted geologic, soil and engineering practices. No other warranty expresses or implied is made.

We trust that this report has provided you with all the information that you required. Should you have any questions or require additional information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.



Logan L. Langford, P.G.  
Geologist

LLL/jr

Encl.

AAprojects/2023/230089 sg&ghs

Reviewed by:



Joseph C. Goode, Jr.  
President



GWH, LLC  
Soil, Geology and Geologic Hazard Evaluation  
23218 Highway 94  
Tax Schedule Nos. 34120-00-026  
El Paso County, Colorado  
Entech Job No. 230089

## BIBLIOGRAPHY

1. Natural Resource Conservation Service, June 5, 2020. *Web Soil Survey*. United States Department Agriculture, <http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>.
2. United States Department of Agriculture Soil Conservation Service. June 1981. *Soil Survey of El Paso County Area, Colorado*.
3. Scott, G.R., Taylor R.B, Epis, R.C., and Wobus, R.A., 1976. Geologic map of the Pueblo 1-degree x 2-degrees' quadrangle, south-central Colorado. USGS, Map MF-775.
4. Federal Emergency Management Agency. December 7, 2018. *Flood Insurance Rate Maps for the City of Colorado Springs, Colorado*. Map Numbers 08041CO807G & 08041CO809G.
5. El Paso County Planning Development. December 1995. *El Paso County Aggregate Resource Evaluation Maps*.
6. Schwochow, S.D.; Shroba, R.R. and Wicklein, P.C. 1974. *Atlas of Sand, Gravel, and Quarry Aggregate Resources, Colorado Front Range Counties*. Colorado Geological Survey. Special Publication 5-B.
7. Keller, John W.; TerBest, Harry and Garrison, Rachel E. 2003. *Evaluation of Mineral and Mineral Fuel Potential of El Paso County State Mineral Lands Administered by the Colorado State Land Board*. Colorado Geological Survey. Open-File Report 03-07.

## TABLE

CLIENT GWH  
 PROJECT 23218 HIGHWAY 94  
 JOB NO. 230089


TABLE 1  
 SUMMARY OF LABORATORY TEST RESULTS

SOIL TYPE	TEST BORING NO.	DEPTH (FT)	WATER (%)	DRY DENSITY (PCF)	PASSING NO. 200 SIEVE (%)	LIQUID LIMIT (%)	PLASTIC INDEX (%)	SULFATE (WT %)	FHA SWELL (PSF)	SWELL/CONSOL (%)	UNIFIED CLASSIFICATION	SOIL DESCRIPTION
1	1	2-3			5.0	NV	NP	<0.01			SM-SW	SAND, SLIGHTLY SILTY
1	2	15			18.5						SM	SAND, SILTY
1	3	10			13.8	NV	NP	0.02			SM	SAND, SILTY
1	4	5			7.2						SM-SW	SAND, SLIGHTLY SILTY
1	6	10			11.0						SM-SW	SAND, SLIGHTLY SILTY
2	5	2-3			78.0						ML	SILT, SANDY

**Table 2: Summary of Groundwater and Bedrock Depths**

<b>Test Boring No.</b>	<b>Depth to Bedrock (ft.)</b>	<b>Depth to Groundwater (ft.)</b>
1	N/A	12
2	N/A	N/A
3	N/A	10
4	N/A	10
5	N/A	10
6	N/A	N/A

## FIGURES



**ENTECH**  
ENGINEERING, INC.

505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

VICINITY MAP  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN:  
JHR


DATE:  
2/9/23

CHECKED:

DATE:

JOB NO.:  
230089

FIG NO.:  
1



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

USGS MAP TOPOGRAPHY MAP  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN:  
JHR

DATE:  
2/9/23


CHECKED:

DATE:





JOB NO.:  
230089

FIG NO.:  
2





**LEGEND:**

-  - APPROXIMATE TEST PIT LOCATION
-  - APPROXIMATE TEST BORING LOCATION
-  - APPROXIMATE PHOTOGRAPH LOCATION AND DIRECTION
-  - Man Made- Structure





REVISION	BY

**ENTTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907  
(719) 531-5599

OWTS SUITABILITY MAP  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN JHR
CHECKED LLI
DATE 2/9/23
SCALE N.T.S.
JOB NO. 230089
FIGURE No. 3



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

SOIL SURVEY MAP  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN:  
JHR


DATE:  
2/9/23

CHECKED:

DATE:

JOB NO.:  
230089

FIG NO.:  
4



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

GEOLOGIC MAP OF THE PUEBLO 1° X 2° QUADRANGLE  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN:  
JHR

DATE:  
2/9/23


CHECKED:

DATE:

JOB NO.:  
230089

FIG NO.:  
5






- Legend:
- QI - Louviers Alluvium of Pliestocene Age:  
silty sand terrace deposits with abundance of gravels
  - psw - potentially seasonally wet area
  - fp - floodplain
  - sw - seasonally wet area




REVISION	BY

**ENTTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599



OWTS SUTABILITY MAP  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN JHR
CHECKED LLL
DATE 2/9/23
SCALE N.T.S.
JOB NO. 230089
FIGURE No. 6



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

FEMA FLOODPLAIN MAP  
23218 HIGHWAY 94  
EL PASO COUNTY, CO.  
FOR: GWH

DRAWN:  
JHR



DATE:  
2/9/23

CHECKED:

DATE:

JOB NO.:  
230089

FIG NO.:  
7



#### NOTES:

—GRAVEL SIZE IS RELATED TO DIAMETER OF PIPE PERFORATIONS—85% GRAVEL GREATER THAN 2x PERFORATION DIAMETER.

—PIPE DIAMETER DEPENDS UPON EXPECTED SEEPAGE. 4-INCH DIAMETER IS MOST OFTEN USED.

—ALL PIPE SHALL BE PERFORATED PLASTIC. THE DISCHARGE PORTION OF THE PIPE SHOULD BE NON-PERFORATED PIPE.

—FLEXIBLE PIPE MAY BE USED UP TO 8 FEET IN DEPTH, IF SUCH PIPE IS DESIGNED TO WITHSTAND THE PRESSURES. RIGID PLASTIC PIPE WOULD OTHERWISE BE REQUIRED.

—MINIMUM GRADE FOR DRAIN PIPE TO BE 1% OR 3 INCHES OF FALL IN 25 FEET.

—DRAIN TO BE PROVIDED WITH A FREE GRAVITY OUTFALL, IF POSSIBLE. A SUMP AND PUMP MAY BE USED IF GRAVITY OUTFALL IS NOT AVAILABLE.



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

#### PERIMETER DRAIN DETAIL

DRAWN:

DATE:

DESIGNED:

CHECKED:


JOB NO.:

230089

FIG NO.:

8





## OVEREXCAVATION DRAIN DETAIL

N.T.S.

NOTE:

EXTEND DRAIN TO SUMP AS REQ'D.



**ENTECH**  
ENGINEERING, INC.  
505 ELKTON DRIVE  
COLORADO SPRINGS, CO. 80907 (719) 531-5599

### OVEREXCAVATION DRAIN DETAIL

DRAWN:

DATE:

DESIGNED BY:

CHECKED:

JOB NO.:


230089

FIG. NO.:

4


## **APPENDIX A: Site Photographs**





**Looking northwest  
from the southeast  
corner of the site.**

February 1, 2023



**Looking southwest  
from the northeast  
corner of the site.**


February 1, 2023





**Looking southeast  
from the northwest  
corner of the site.**

February 1, 2023



**Looking northeast  
from the southeast  
corner of the site.**


February 1, 2023





**Looking southeast  
along dry drainage in  
the southwest corner  
of the site.**


February 1, 2023



**Looking northwest  
along dry drainage in  
the southwest corner  
of the site.**


February 1, 2023





**Looking west-  
southwest from the  
northwest portion of  
the site.**


February 1, 2023



**Looking northeast at  
existing home.**


February 1, 2023





**Looking northwest at  
existing home.**

February 1, 2023



**Looking southeast at  
corrals from the  
central point of the  
north property line.**

February 1, 2023

## **APPENDIX B: Test Boring Logs**

TEST BORING NO. 1  
DATE DRILLED 1/31/2023  
Job # 230089

TEST BORING NO. 2  
DATE DRILLED 1/31/2023  
CLIENT GWH  
LOCATION 23218 HIGHWAY 94

REMARKS

WATER @ 12', 2/1/23

SAND, SLIGHTLY SILTY TO SILTY,  
FINE TO COARSE GRAINED, TAN,  
LOOSE TO VERY DENSE, DRY  
TO WET

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
5			9	1.5	1
			7	1.5	1
10			40	3.9	1
15			50	9.7	1
			11"		
20			50	7.5	1
			11"		



REMARKS

DRY TO 20', 2/1/23

SAND, SLIGHTLY SILTY TO SILTY,  
FINE TO COARSE GRAINED, TAN,  
LOOSE TO VERY DENSE, DRY TO  
MOIST

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
5			10	0.7	1
			8	1.3	1
10			36	4.7	1
15			50	9.2	1
20			12	18.4	1



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED:  
JHR

DATE:  
2/24/23

JOB NO.:  
230089

FIG NO.:  
B-11

TEST BORING NO. 3  
 DATE DRILLED 1/31/2023  
 Job # 230089

TEST BORING NO. 4  
 DATE DRILLED 1/31/2023  
 CLIENT GWH  
 LOCATION 23218 HIGHWAY 94

REMARKS

WATER @ 10', 2/1/23

SAND, SLIGHTLY SILTY TO SILTY,  
 FINE TO COARSE GRAINED, TAN,  
 MEDIUM DENSE TO VERY DENSE,  
 MOIST TO WET

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
5			14	3.0	1
			35	4.5	1
10			50	7.7	1
			11"		
15			40	15.3	1
20			36	6.7	1



REMARKS

WATER @ 10', 2/1/23

SAND, SLIGHTLY SILTY TO SILTY,  
 FINE TO COARSE GRAINED, TAN,  
 MEDIUM DENSE TO DENSE,  
 DRY TO WET

Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
5			23	4.2	1
			25	1.7	1
10			39	8.3	1
15			26	8.8	1
20			16	6.7	1



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG

DRAWN:

DATE:

CHECKED:

DATE:

SHR

2/22/23

JOB NO.:  
 230089

FIG NO.: -

B-2



TEST BORING NO. 5  
 DATE DRILLED 1/31/2023  
 Job # 230089

TEST BORING NO. 6  
 DATE DRILLED 1/31/2023  
 CLIENT GWH  
 LOCATION 23218 HIGHWAY 94

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 20', 1/31/23						
SILT, SANDY, BROWN, STIFF, MOIST						
SAND, SILTY, FINE TO COARSE GRAINED, TAN, MEDIUM DENSE TO DENSE, DRY TO MOIST						
	5			17	7.8	2
	5			22	1.8	1
	10			33	10.6	1
	15			25	9.0	1
	20			29	8.8	1

REMARKS	Depth (ft)	Symbol	Samples	Blows per foot	Watercontent %	Soil Type
DRY TO 20', 1/31/23						
SAND, SLIGHTLY SILTY TO SILTY, FINE TO COARSE GRAINED, TAN, MEDIUM DENSE TO DENSE, DRY TO MOIST						
	5			14	1.8	1
	5			19	1.6	1
	10			20	8.6	1
	15			41	4.2	1
	20			15	9.7	1



**ENTECH**  
**ENGINEERING, INC.**

505 ELKTON DRIVE  
 COLORADO SPRINGS, COLORADO 80907

### TEST BORING LOG

DRAWN:

DATE:

CHECKED:

DATE:

JHR

2/22/23


JOB NO.:  
 230089

FIG NO.:

15-3

## **APPENDIX C: Laboratory Testing Results**

UNIFIED CLASSIFICATION	SM-SW	CLIENT	GWH
SOIL TYPE #	1	PROJECT	23218 HIGHWAY 94
TEST BORING #	1	JOB NO.	230089
DEPTH (FT)	2-3	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	93.1%
10	71.6%
20	50.3%
40	35.4%
100	10.7%
200	5.0%

<u>Atterberg Limits</u>	
Plastic Limit	NP
Liquid Limit	NV
Plastic Index	NP

<u>Swell</u>	
Moisture at start	
Moisture at finish	
Moisture increase	
Initial dry density (pcf)	
Swell (psf)	



**ENTECH  
ENGINEERING, INC.**  
505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907


**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED:	DATE:
		JHR	2/22/23

JOB NO.:  
230089

FIG NO.:  
C-1

UNIFIED CLASSIFICATION	SM	CLIENT	GWH
SOIL TYPE #	1	PROJECT	23218 HIGHWAY 94
TEST BORING #	2	JOB NO.	230089
DEPTH (FT)	15	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	87.4%
10	57.8%
20	44.0%
40	36.7%
100	28.1%
200	18.5%

Atterberg  
Limits  
Plastic Limit  
Liquid Limit  
Plastic Index

Swell  
Moisture at start  
Moisture at finish  
Moisture increase  
Initial dry density (pcf)  
Swell (psf)



**ENTECH  
ENGINEERING, INC.**  
505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

**LABORATORY TEST  
RESULTS**

DRAWN:	DATE:	CHECKED: JHR	DATE: 2/22/23
--------	-------	-----------------	------------------


JOB NO.:  
230089

FIG NO.:  
C-2

UNIFIED CLASSIFICATION	SM
SOIL TYPE #	1
TEST BORING #	3
DEPTH (FT)	10

CLIENT	GWH
PROJECT	23218 HIGHWAY 94
JOB NO.	230089
TEST BY	BL

### Sieve Analysis Grain Size Distribution



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	99.1%
10	51.6%
20	26.8%
40	19.1%
100	14.6%
200	13.8%

Atterberg  
Limits

Plastic Limit	NP
Liquid Limit	NV
Plastic Index	NP

Swell

Moisture at start

Moisture at finish

Moisture increase

Initial dry density (pcf)

Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

### LABORATORY TEST RESULTS

DRAWN:

DATE:

CHECKED:

DATE:

JHR

2/22/23

JOB NO.:  
230089


FIG NO.:

63

UNIFIED CLASSIFICATION	SM-SW
SOIL TYPE #	1
TEST BORING #	4
DEPTH (FT)	5

CLIENT	GWH
PROJECT	23218 HIGHWAY 94
JOB NO.	230089
TEST BY	BL

### Sieve Analysis Grain Size Distribution



U.S.  
Sieve #

3"  
1 1/2"  
3/4"  
1/2"  
3/8"  
4  
10  
20  
40  
100  
200

Percent  
Finer

100.0%  
95.6%  
70.9%  
46.8%  
33.1%  
11.9%  
7.2%

Atterberg  
Limits  
Plastic Limit  
Liquid Limit  
Plastic Index

Swell  
Moisture at start  
Moisture at finish  
Moisture increase  
Initial dry density (pcf)  
Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

### LABORATORY TEST RESULTS

DRAWN:

DATE:

CHECKED:

DATE:

JHR


2/22/23

JOB NO.:  
230089

FIG NO.:

C4

UNIFIED CLASSIFICATION	ML	CLIENT	GWH
SOIL TYPE #	2	PROJECT	23218 HIGHWAY 94
TEST BORING #	5	JOB NO.	230089
DEPTH (FT)	2-3	TEST BY	BL



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	
3/8"	100.0%
4	98.6%
10	97.1%
20	94.1%
40	91.7%
100	87.3%
200	78.0%

Atterberg  
Limits  
Plastic Limit  
Liquid Limit  
Plastic Index

Swell  
Moisture at start  
Moisture at finish  
Moisture increase  
Initial dry density (pcf)  
Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

## LABORATORY TEST RESULTS

DRAWN:

DATE:

CHECKED:  
*JHR*

DATE:  
*2/22/23*

JOB NO.:  
230089


FIG NO.:

*C-5*

UNIFIED CLASSIFICATION	SM-SW
SOIL TYPE #	1
TEST BORING #	6
DEPTH (FT)	10

CLIENT	GWH
PROJECT	23218 HIGHWAY 94
JOB NO.	230089
TEST BY	BL

### Sieve Analysis Grain Size Distribution



U.S. Sieve #	Percent Finer
3"	
1 1/2"	
3/4"	
1/2"	100.0%
3/8"	95.7%
4	91.8%
10	69.2%
20	47.3%
40	30.5%
100	13.8%
200	11.0%

Atterberg  
Limits  
Plastic Limit  
Liquid Limit  
Plastic Index

Swell  
Moisture at start  
Moisture at finish  
Moisture increase  
Initial dry density (pcf)  
Swell (psf)



**ENTECH  
ENGINEERING, INC.**

505 ELKTON DRIVE  
COLORADO SPRINGS, COLORADO 80907

### LABORATORY TEST RESULTS

DRAWN:

DATE:

CHECKED: JLR

DATE: 2/22/23

JOB NO.:  
230089

FIG NO.:  
C-6





## **APPENDIX D: Soil Survey Descriptions**

## El Paso County Area, Colorado

### 19—Columbine gravelly sandy loam, 0 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 367p  
*Elevation:* 6,500 to 7,300 feet  
*Mean annual precipitation:* 14 to 16 inches  
*Mean annual air temperature:* 46 to 50 degrees F  
*Frost-free period:* 125 to 145 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Columbine and similar soils:* 97 percent  
*Minor components:* 3 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Columbine

##### Setting

*Landform:* Fans, fan terraces, flood plains  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Alluvium

##### Typical profile

*A - 0 to 14 inches:* gravelly sandy loam  
*C - 14 to 60 inches:* very gravelly loamy sand

##### Properties and qualities

*Slope:* 0 to 3 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Well drained  
*Runoff class:* Very low  
*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (5.95 to 19.98 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water supply, 0 to 60 inches:* Very low (about 2.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 4e  
*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* R049XY214CO - Gravelly Foothill  
*Hydric soil rating:* No

#### Minor Components

##### Fluvaquentic haplaquolls

*Percent of map unit:* 1 percent  
*Landform:* Swales  
*Hydric soil rating:* Yes

**Other soils**

*Percent of map unit:* 1 percent

*Hydric soil rating:* No

**Pleasant**

*Percent of map unit:* 1 percent

*Landform:* Depressions

*Hydric soil rating:* Yes

**28—Ellicott loamy coarse sand, 0 to 5 percent slopes**

**Map Unit Setting**

*National map unit symbol:* 3680

*Elevation:* 5,500 to 6,500 feet

*Mean annual precipitation:* 13 to 15 inches

*Mean annual air temperature:* 47 to 50 degrees F

*Frost-free period:* 125 to 145 days

*Farmland classification:* Not prime farmland

**Map Unit Composition**

*Ellicott and similar soils:* 97 percent

*Minor components:* 3 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Ellicott**

**Setting**

*Landform:* Stream terraces, flood plains

*Landform position (three-dimensional):* Tread

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Parent material:* Sandy alluvium

**Typical profile**

*A - 0 to 4 inches:* loamy coarse sand

*C - 4 to 60 inches:* stratified coarse sand to sandy loam

**Properties and qualities**

*Slope:* 0 to 5 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Somewhat excessively drained

*Runoff class:* Very low

*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (5.95 to 19.98 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* NoneFrequent

*Frequency of ponding:* None

*Available water supply, 0 to 60 inches:* Low (about 4.1 inches)

**Interpretive groups**

*Land capability classification (irrigated):* None specified

## Custom Soil Resource Report

*Land capability classification (nonirrigated): 7w*

*Hydrologic Soil Group: A*

*Ecological site: R069XY031CO - Sandy Bottomland*

*Other vegetative classification: SANDY BOTTOMLAND (069AY031CO)*

*Hydric soil rating: No*

### Minor Components

#### **Fluvaquentic haplaquoll**

*Percent of map unit: 1 percent*

*Landform: Swales*

*Hydric soil rating: Yes*

#### **Other soils**

*Percent of map unit: 1 percent*

*Hydric soil rating: No*

#### **Pleasant**

*Percent of map unit: 1 percent*

*Landform: Depressions*

*Hydric soil rating: Yes*

## **APPENDIX E: Existing Septic Records**

EL PASO COUNTY DEPARTMENT OF HEALTH AND ENVIRONMENT  
INDIVIDUAL SEWAGE DISPOSAL SYSTEM INSPECTION FORM

Permit # 3349  
Date 10/31/01

# 3412000026

APPROVED: YES ☒ NO ☐

ENVIRONMENTALIST Kurt Dahl

Address 23218 Hwy 94

Owner Manuel Saenz

Legal Description NE 1/4 of the SW 1/4 and E 1/2 of the NW of the SW 1/4 of Tract 2  
Residence ☒ # of bedrooms 3; Commercial ☐; System Installer Self

SEPTIC TANK:

Commercial ☒; Noncommercial ☐; L ☐; W ☐; WD ☐  
Construction Material Precast Concrete, capacity 1,500 gallons.

DISPOSAL FIELD:

Rock Systems:

Trench: depth ☐, width ☐, total length ☐, sq. feet ☐  
Bed: depth ☐, length ☐, width ☐, sq. feet ☐  
Rock type ☐, depth ☐, under PVC ☐, over PVC ☐  
Seepage Pits: # of pits ☐, total # of rings ☐, working depth(s) ☐  
size of pit(s) L X W ☐, lining material ☐, total sq. feet ☐

Rockless Systems:

Chamber: Type bio. filter, number of chambers 25, bed ☐, trench ☒  
sq. ft./section 24, reduction allowed ☐, sq. ft. required 463  
total sq. ft. installed 600, depth of installation 30"

Engineer Design Y or ☒ N, Designing Engineer ☐


Approval letter provided? Y or ☒ N

Well 50 feet from tank ☒ or N 100 feet from leach field ☒ or N

Well installed at time of septic system inspection ☒ or N Public Water ☐

\*Approval will be revoked if in the future the well is found to be within 50 feet of the septic tank and/or 100 feet of the disposal field.

NOTES: All pipes are SDR 35



## INDIVIDUAL SEWAGE DISPOSAL SYSTEM PERMIT

OWNER NAME: MANUEL SAENZ  
ADDRESS: 23222 HWY 94  
CITY, STATE, ZIP: ELLICOTT CO 80808  
INSTALLED BY:

PERMIT NUMBER: ON0003349  
DATE PERMITTED: 10/23/01  
PHONE NUMBER: 3038415030

This permit is issued in accordance with 25-10-107 Colorado Revised Statutes. PERMIT EXPIRES upon completion-installation of sewage-disposal system or at the end of twelve (12) months from date of issue- whichever occurs first-(unless work is in progress). If both a building and an ISDS permit are issued for the same property and construction has not commenced prior to the expiration date of the building permit, the ISDS permit shall expire at the same time as the building permit. This permit is revokable if all stated requirements are not met.  
Sewage disposal system to be installed by an El Paso County Licensed System Contractor or the property owner.

**THIS PERMIT DOES NOT DENOTE APPROVAL OF ZONING AND ACREAGE REQUIREMENTS.**

*John Lawrence*

DIRECTOR, EL PASO COUNTY DEPARTMENT OF HEALTH AND ENVIRONMENT

PERMIT EXPIRATION DATE :  
Expires twelve months from date of issue

*Yvett Dahl* (719) 578-3289  
ENVIRONMENTALIST / PHONE NUMBER

NOTE: 48 HOUR ADVANCE NOTICE REQUIRED  
LEAVE THE ENTIRE SEWAGE DISPOSAL SYSTEM UNCOVERED FOR FINAL INSPECTION.

WATER SOURCE: WELL

MINIMUM SEPTIC TANK SIZE : 1,250 GALLONS MINIMUM ABSORPTION AREA REQUIRED 463 SQ FT

PLANNING DEPARTMENT ☒ ENUMERATION ☒ FLOOD PLAIN ☒ WASTEWATER ☒

### COMMENTS:

MUST MEET MINIMUM SETBACK REQUIREMENTS OF THE CURRENT EL PASO COUNTY DEPARTMENT OF HEALTH AND ENVIRONMENT ISDS REGULATIONS. INSTALL SEPTIC SYSTEM AT SITE B PERCOLATION TEST, AT A DEPTH OF NO MORE THAN 48 INCHES. IF GROUND WATER IS ENCOUNTERED WHILE INSTALLING THE SYSTEM, CALL THE EL PASO COUNTY DEPARTMENT OF HEALTH AND ENVIRONMENT. ~~UPON COMPLETION OF THE SYSTEM, THE ENGINEER MUST PROVIDE AN APPROVAL LETTER.~~ KHD

The Health Office shall assume no responsibility in case of failure or inadequacy of a sewage-disposal system, beyond consulting in good faith with the property owner or representative. Free access to the property shall be authorized at reasonable time for the purpose of making such inspections as are necessary to determine compliance with requirements of this law.

### FOR ADMINISTRATIVE USE ONLY

Permit Ready: 10-24-01 Called DM Mailed

Final Inspection Requested: BY: Ed Date Called In: 10/25/01

Phone # \_\_\_\_\_ Septic Site will be ready: 10/24/01



Inspector

Kurt Dahl - 0024

Record I.D.

3349

## EL PASO COUNTY ENVIRONMENTAL HEALTH SERVICES

301 South Union Boulevard • Colorado Springs, CO • 80910-3123 • (719) 578-3126

## APPLICATION FOR AN ON-SITE TREATMENT SYSTEM:

☒ NEW    ☐ REPAIR TANK    ☐ REPAIR/ADD LEACH FIELD    ☐ P.E. DESIGN

Owner Manuel L. Saenz Daytime Phone 303-841-5030  
 Address of Property 23235 Highway 94 Ellicott City & Zip Ellicott Co.  
 Legal Description N.E. 1/4 of the S.W. 1/4 and E 1/2 of the N.W. 1/4  
 Owner's MAILING Address 9644 Summit Ridge Pl. City, State & Zip Parker Co 80138  
 Lot Size 60 acres Tax Schedule # 34120-00-025 Septic Contractor Hudson Septic  
 Type of Building: ☐ Frame ☐ Modular ☐ Mobile ☐ Commercial ☒ Manufactured ☐ Other \_\_\_\_\_  
 Water Supply: ☒ Well or Spring ☐ Cistern ☐ Public Inside City Limits: ☐ No ☐ Yes-City \_\_\_\_\_  
☐ MAIL PERMIT OR ☒ PICK UP PERMIT ☐ THERE IS AN ADDITIONAL RESIDENCE ON THIS PROPERTY

MAXIMUM POTENTIAL BEDROOMS 8<sup>KHP</sup> 3Percolation Test Attached (Y) NGarbage Disposal Y (N)Basement Y (N)Clothes Washer (Y) N

I have supplied a plot plan as described on the back of this form. I acknowledge the completeness of the application is conditional upon such further mandatory and additional tests and reports as may be required by the Department to be made and furnished by an applicant for purposes of evaluating the application, and issuance of the permit is subject to such terms and conditions as deemed necessary to ensure compliance with rules and regulations adopted pursuant to C.R.S. 25-10-107 et. seq. I hereby certify all represented to be true and correct to the best of my knowledge and belief, and are designed to be relied on by the El Paso County Department of Health and Environment in evaluating the same for purposes of issuing the permit applied for herein. I further understand any falsification or misrepresentation may result in the denial of the application or revocation of any permit granted based upon said application and in legal action for perjury as provided by law.

OWNER'S SIGNATURE

Manuel L. SaenzDate 7/16/01

## DEPARTMENT OF HEALTH USE ONLY

Eng Design 463 sq ft  
 Minimum Absorption Area

Eng Design 1,250 gal  
 Minimum Tank Capacity

8/21/01  
 Date of Site Inspection

## REMARKS

OK  
~~Install per engineer design corrected aug. dated July 12, 2001~~  
~~Note that first septic tank is a 2250 gallon single compartment tank~~  
 Must meet minimum setback requirements of the current El Paso County department of Health and Environment ISDS regulations. Install septic system at site B percolation test, at a depth of no more than 48". If groundwater is found encountered while installing the system, call the El Paso County Dept of Health and Environment. Upon completion of the system, the engineer must provide an approval letter.

EHS INSPECTOR

Kurt DahlDATE 9/5/01APPROVED

DENIED

FEE AS OF 8/1/00: NEW \$315 -

REPAIR TO LEACH FIELD \$150 -

REPAIR TO TANK OR LINE \$75 -

Resubmit  
 DATE TO PLANNING / WASTEWATER
7/7/018-31-0110-17-01

- 1) We require an original of your **PERCOLATION (PERC) TEST** with an original professional engineer's (PE) stamp and signature as well as a plot of the percolation test holes.
- 2) **PROPERTY ADDRESS OR LOT NUMBER MUST BE POSTED AND CLEARLY VISIBLE FROM ROAD. PERC HOLES MUST BE CLEARLY MARKED.**
- 3) A **PLOT PLAN** must be drawn (not to scale) on an 8 1/2 x 11 sheet of paper. The plot plan must include:
 


1) a north bearing	4) all buildings (proposed or existing)	7) driveway (proposed or existing and name of adjoining street)
2) property lines	5) proposed septic system site	
3) property dimensions	6) alternate septic system site	
- 4) Initial any of the following features that apply to your property and **INCLUDE** them on your **PLOT PLAN**.
 

<input checked="" type="checkbox"/> Well(s)	<input type="checkbox"/> Adjacent property well(s)	<input type="checkbox"/> Subsoil drain
<input type="checkbox"/> Cistern	<input type="checkbox"/> Water line	
- 5) Initial any of the following that are within 100 feet of your proposed septic system and **INCLUDE** on your **PLOT PLAN**.
 

<input type="checkbox"/> Spring(s)	<input type="checkbox"/> Lake(s)
<input type="checkbox"/> Pond(s)	<input type="checkbox"/> Stream(s)
<input type="checkbox"/> Dry Gulch(es)	<input type="checkbox"/> Natural drainage course(s)

6) GIVE COMPLETE DIRECTIONS TO THE PROPERTY FROM A MAIN HIGHWAY


Hwy 94 E To Elliott LEFT on DIRT RD (PRIVATE RD) north 1/2 mile To GATE (west side)



# V1\_Soils & Geology Report.pdf Markup Summary


[1] FEMA 8X11.5 (4)


Please add:  
PCD File SF2521


**Subject:** Planner  
**Page Label:** [1] FEMA 8X11.5  
**Author:** JoeLetke  
**Date:** 7/17/2025 7:50:59 AM  
**Status:**  
**Color:**   
**Layer:**  
**Space:**

Please add:  
PCD File SF2521

involved in the  
10 lots is planne  
5 to 7-acres in s  
ams and water we


**Subject:** Highlight  
**Page Label:** [1] FEMA 8X11.5  
**Author:** Joseph Sandstrom  
**Date:** 7/15/2025 1:57:11 PM  
**Status:**  
**Color:**   
**Layer:**  
**Space:**

d in the proposed subdivision  
is planned for the replat. The l  
acres in size. The lots will be se  
water wells. The Site Plan is pre  
  
ENGINEERING GEOLOGY 

**Subject:** Callout  
**Page Label:** [1] FEMA 8X11.5  
**Author:** Joseph Sandstrom  
**Date:** 7/15/2025 1:57:18 PM  
**Status:**  
**Color:**   
**Layer:**  
**Space:**

9

riated beneath foundations, removal and  
gh moisture conditioning and recompactio  
1507 will be necessary. Specific recomme  
gation of each building site.  
  
December 7, 2018  
  
floodplain zone according to the FEMA Map  
uch 14, 2018 (Figure 7, Reference 6). Th  
indicated on the Engineering Geology Map  
e required prior to development. Exact loc  
es are beyond the scope of this repo  
condition area will require approval of this."

**Subject:** Callout  
**Page Label:** [1] FEMA 8X11.5  
**Author:** Joseph Sandstrom  
**Date:** 7/15/2025 2:07:26 PM  
**Status:**  
**Color:**   
**Layer:**  
**Space:**

December 7, 2018