

FIRE FLOW FIRE HYDRANT TESTING & MAINTENANCE SERVICES, LLC

4905 Alberta Falls Way Colorado Springs, CO 80924
(719) 495-5699

Pikes Peak Building Department
Fire Suppression Hydrant Technician License ID Number 11176
Fire Protection Contractor CSA21807 CTFH2

AWWA Fire Flow Test Report

ADDRESS	11860 Stapleton Drive	DATE:	08/18/2023
OCCUPANT	The Shops at Meridian Ranch, LLC Vacant Lot	TIME:	0945
RESPONSIBLE PARTY	Meridian Ranch Metropolitan District	PHONE:	719-495-6567
WITNESSES:	None	NUMBER OF HYDRANTS:	TWO
PURPOSE OF TEST:	All testing follows AWWA & Colorado Springs Fire Codes. All flow testing was completed at the 2 1/2 -inch hose nozzle on each hydrant.		

Hydrant	Hydrant Location on Property	Year and Make of Hydrant	Valve Present at Grade	Static psi	Pitot psi	Actual Flow gpm	Residual psi	Max Flow @ 20 psi Residual
1	11850 Stapleton Rd. Entry Road	2015 AVK	YES	87	28	888	75	2248 gpm
2	Fleece Flower Wy & Eagle Crest Ct.	2015 AVK	YES	88	28	888	75	2170 gpm

REMARKS:

Both hydrants worked well and as expected without showing signs of issues that would indicate the need for maintenance beyond the routine annual testing and maintenance services.