

LEGAL DESCRIPTION FOR MILLER DOWNS AT WYOMING LANE ADDITION No. 1

A portion of the East half and a portion of the Northwest Quarter of Section 8, Township 13 South, Range 65 West of the 6th P.M., County of El Paso, State of Colorado, described as follows:

BASIS OF BEARINGS: Bearings are based upon the West line of the Southeast Quarter of Section 8, Township 13 South, Range 65 West of the 6th P.M., monumented at the North end with a #6 rebar & 3.25" aluminum cap stamped "Barron Land PLS 38141" and monumented at the South end with a #6 rebar & 3.25" aluminum cap stamped "WATTS PLS 9853", and is assumed to bear S 00°06'23" W, a field measured distance of 1,329.76 feet.

BEGINNING at the Northwest corner of the Southeast Quarter of said Section 8;
thence S 00°06'23" W along the West line of the Southeast Quarter of said Section 8, a distance of 1329.76 feet to the Southwest corner of the Northwest Quarter of the Southeast Quarter of said Section 8;
thence N 89°06'33" E along the South line of the Northwest Quarter of the Southeast Quarter of said Section 8, a distance of 500.15 feet to intersect the Southerly extension of the West line of the Ruth K. Adams Tract as recorded under Book 2088 at Page 738 of the records of the El Paso County Clerk and Records Office;
thence N 00°01'48" W along said Southerly extension of said West line, a distance of 897.10 feet to the Northwest corner of said Ruth K. Adams Tract, said corner also being the most Southerly corner of that parcel of land as described under the Quitclaim Deed as recorded under Reception No. 225004905;
thence the following three (3) courses along the West and North lines of said parcel:
1) N 00°41'29" W, a distance of 432.17 feet to a point on the North line of said Southeast Quarter of Section 8;
2) N 00°41'29" W, a distance of 38.00 feet;
3) N 89°09'21" E, parallel to said North line of the Southeast Quarter of Section 8, a distance of 205.51 feet;
thence N 00°10'20" E, a distance of 336.96 feet to the South line of the Lois Slocum Tract as recorded under Book 1537 at Page 546 of said records, said corner also being the Southeast corner of that parcel of land as described under the Quitclaim Deed as recorded under Reception No. 225004903;
thence the following three (3) courses along the East, North and West lines of said parcel:
1) N 00°10'20" E, a distance of 18.50 feet;
2) S 89°49'06" W, a distance of 697.41 feet to a point on the West line of the Northeast Quarter of said Section 8;
3) S 00°05'23" W, along said West line of the Northeast Quarter of Section 8, a distance of 18.50 feet to the Southwest corner of said Lois Slocum Tract;
thence continuing S 00°05'23" W along said West line of the Northeast Quarter of Section 8, a distance of 89.64 feet to a point on said West line;
thence S 73°59'25" W, a distance of 60.56 feet to a point on the West line of Tract H, Quail Brush Creek Filing No. 2 recorded under Reception No. 215713674;

thence the following two (2) courses along the West and South lines of said Tract H:

1) S 00°23'45" E, a distance of 4.56 feet;

2) N 89°38'51" E, a distance of 58.15 feet to a point on the West line of the Northeast Quarter of said Section 8;

thence S 00°05'23" W along said West line, a distance of 272.47 feet to the POINT OF BEGINNING.

Containing a calculated area of 931,727 square feet (21.390 acres) of land, more or less.