March 5, 2020



ENTECH ENGINEERING, INC.

505 ELKTON DRIVE COLORADO SPRINGS, CO 80907 PHONE (719) 531-5599 FAX (719) 531-5238

D. Stefano-Building & Restoration, Inc. 520 West 21st Street, G-2 #710 Norfolk, Virginia 23517

Attn: David Stefano

Re: OWTS – Site Evaluation

7765 Electronic Drive El Paso County, Colorado Please show at least two potential septic locations for the lots and include the information that Cherokee has provided as to why its not feasible to hook in to central wastewater services.

Provide document from Cherokee stating that they either will not allow tyeing in to their services or provide documentation allowing connection the their services.

Dear Mr. Stefano:

As requested, personnel of Entech Engineering, Inc. observed two test pits at the address above. The test pits were excavated in the area of the proposed on-site wastewater treatment system (OWTS) absorption field. This letter presents the results of our testing.

Test pits Nos. 1 & 2 were excavated on February 12, 2020, to approximately 8 feet deep. Soils encountered in the test pits consisted of sandy clay. The Test Pit Logs and Laboratory Test Results are shown in Figures 2 and 3. Bedrock was not encountered in the test pits. Signs of seasonally occurring groundwater were not observed in the test pits.

Visual and tactile evaluation of the soils was performed. The limiting layer encountered in the test pits is the sandy clay, which classifies as USDA Soil Type 4. The corresponding LTAR Value of 0.20 gallons per day per square foot is recommended for Treatment Level 1. An engineered system will be required. Installation of the system should be performed in accordance with El Paso County Health Department regulations and requirements.

We trust that this has provided you with the information you required. If you have any assertions or need additional information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.

Reviewed by:

effery A. Muffay, P.E.

JM/rj

Entech Job No. 200127

Robert P. Jaquet, E.I.

AAprojects/2020/200127 owts-site evaluation





TP- APPROXIMATE TEST PIT LOCATION AND NUMBER

- TP-1 38°52'22.21"N, 104°41'5.01"W
- TP-2 38°52'22.08"N, 104°41'5.31"W



TEST PIT LOCATION MAP 7765 ELECTRONIC DRIVE EL PASO COUNTY, COLORADO FOR: DAVID STEFANO

DRAWN: DATE: CHECKED: DATE: 3/4/20

JOB NO.: 200127

FIG NO.:

TEST PIT NO. TEST PIT NO. 2 DATE EXCAVATED 2/12/2020 DATE EXCAVATED 2/12/2020 Job # 200127 CLIENT D. Stefano-Building & Restoration, Inc. LOCATION 7765 ELECTRONIC DRIVE REMARKS REMARKS Soil Structure Shape Soil Structure Grade Soil Structure Shape Soil Structure Grade **USDA Soil Type** Depth (ft) Samples Depth (ft) Samples Symbol Symbol topsoil sandy loam, brown topsoil sandy loam, brown sandy clay, fine to medium S sandy clay, fine to medium gr gr s grained, brown grained, brown 2 3

Soil Structure Shape granular - gr platy - pl blocky - bl prismatic - pr single grain - sg massive - ma 8

9


Soil Structure Grade weak - w moderate - m strong - s loose - I 9



TEST PIT LOG				
DRAWN:	DATE	CHECKED:	3/3/20	

JOB NO.: 200127 FIG NO.:

UNIFIED CLASSIFICATION	SC	CLIENT	D. STEFANO
SOIL TYPE #	1	PROJECT	7765 ELECTRONIC DRIVE
TEST BORING #	TP-1	JOB NO.	200127
DEPTH (FT)	4-6	TEST BY	BL



U.S. Sieve # 3" 1 1/2" 3/4" 1/2" 3/8"	Percent <u>Finer</u>		Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
4	100.0% 99.8%		Swell Moisture at start
20	95.3%		Moisture at start
40	84.7%		Moisture increase
100 200	61.6% 47.0%		Initial dry density (pcf) Swell (psf)



LABORATORY TEST RESULTS					
DRAWN;	DATE:	CHECKED	DATE: 3/5/20		
		-			

JOB NO.: 200127

FIG NO: