

APPLICATION FORM FOR GEOLOGIC HAZARD WAIVER

Applicant: DHN Development	Telephone: 719-244-9851
Address: 2335 Coralbell Grove, Unit 101	Email:
City/State/Zip: Colorado Springs, CO 80910	
Site Location: Southmoor Drive and Fontaine E	Boulevard
Tax Schedule Number: 65133-14-015, 65133-00-021, 65	5242-00-052, and 65242-00-053
In accordance with the City of Colorado Springs Unified Developme consultation with written approval of the City Engineer, may waive the Hazard Study for development proposals on property that falls under	he requirement for the submittal of a Geologic
 Land Use Plans, Development Plans, or Subdivision Plat previously prepared and reviewed and which are still co Development proposals which exhibit none of the followa. Slopes (existing or proposed) exceeding thirt unstable or potentially unstable. Underground mining or subsidence activity. A history of a landfill or uncontrolled or undocted. Seismicity, collapsible or compressible soils, slopedrock, expansive soils or bedrock that can design/construction practices. 	onsidered by the City Engineer as relevant. wing characteristics: y three percent (33%) or that are otherwise umented fill activity. hallow water table or springs, steeply dipping
A letter shall accompany this application that states the project meet professional geologist or professional geotechnical engineer, who Development Code Subsection, 7.4.503.	
Professional Geologist / Professional Geotechnical Engin	<u> </u>
I hereby formally request that the development at be exempted from the requirement to submit a Geologic Hazard observation of the project has confirmed that all of the above reference attest that I am a: Professional Geologist as defined by C.R.S. § 23-41-	Study on the basis that review and on-site ced exemption criteria have been met. I hereby
A Professional Geotechnical Engineer licensed by the Architects, Professional Engineers and Professional Submitted for and on behalf of: DHN Development	Land Surveyors.
Submitted for and on behalf of: DHN Development Submitted by:	Date: 2/15/2024
City Engineering:	Date:

February 15, 2024

ENTECH ENGINEERING, INC. 505 ELKTON DRIVE COLORADO SPRINGS, CO 80907 PHONE (719) 531-5599

DHN Development 2335 Coralbell Grove, Unit 101 Colorado Springs, Colorado 80910

Attn: Bryan Kniep

Re: Geologic Hazard Waiver Request

Southmoor Ridge

Parcel Nos. 65133-14-015, 65133-00-021,

65242-00-052, and 65242-00-053

Southmoor Drive and Fontaine Boulevard

Fountain, Colorado Entech Job No. 240217

Dear Mr. Kniep:

This letter is to request a waiver from the Geologic Hazard Study for the above referenced project. The project is to consist of single family (townhomes) and multi-family residential development. The site is currently zoned as PUD (Planned Unit Development) according to City of Fountain Planning and Zoning (Reference 1).

The site is located in a portion of the SW¼ of Section 13 the NW¼ of Section 24, Township 15 South, Range 66 West, in the northwestern portion of Fountain, Colorado. The location of the site is shown on the Vicinity Map, Figure 1, and the USGS Topography Map, Figure 2. The proposed Development Plan is shown on Figure 3. The geology of the site was evaluated using the following investigations completed by Entech Engineering, Inc. (Entech) *Preliminary Subsurface Soil Investigation* (Reference 2, Appendix B) and *Infiltration Rates* (*Percolation Testing Method*) (Reference 3, Appendix C), the *Geologic Map of the Fountain Quadrangle* completed by Colorado Geological Survey 2017 (Reference 4, Figure 4). Site photographs taken February 13, 2024, are included in Appendix A.

In our opinion, the site is suitable for a Geologic Hazard Waiver as it does not exhibit any of the following characteristics:

- Slopes (existing or proposed) exceeding 33% or which are unstable or potentially unstable.
- · History of underground mining or subsidence activity.
- History of a landfill, uncontrolled or undocumented fill activity.

The conditions on the site were investigated by Entech *Preliminary Subsurface Soil Investigation*, (Reference 2, Appendix B), and *Infiltration Rates (Percolation Testing Method)* (Reference 3, Appendix C). These investigations consisted of drilling fourteen shallow test borings on the site. The test borings were drilled to depths of 10 to 20 feet below the existing surface grade. Soils encountered in the test borings consisted of very clayey sand (SC), gravelly clean to silty sand (SW, SM-SW), sandy silt (ML), and sandy clay (CL) overlying weathered claystone and shale bedrock (CL, ML). Bedrock was encountered in four of the borings a depths ranging from 13 to 19 feet below the existing surface grade. Groundwater was encountered in one test boring TB-2 at a depth of 15.5 feet, the remaining borings were dry.

DHN Development Geologic Hazard Waiver Request Southmoor Ridge Parcel Nos. 65133-14-015, 65133-00-021, 65242-00-052, and 65242-00-053 Southmoor Drive and Fontaine Boulevard Fountain Colorado, Colorado Page 2



The site soils are associated with the Alluvial gravel five (Qag₅) of lower Pleistocene Age (Reference 4, Figure 4). Overlying the Alluvial gravel five are areas of fill associated with past stockpiling and dumping on the property. Bedrock underlying the site consists of the Pierre Shale Formation of Upper Cretaceous Age. The claystone and shale associated with the Pierre Shale Formation are typically expansive. Additional geotechnical investigation of the site will be required once development plans are finalized to provide foundation recommendations.

No areas of unstable or potentially unstable slopes were observed on the site. The site slopes are gradually sloping to the southeast. The site is not located in any area of past underground mining or subsidence activity (References 5 and 6).

The site does lie within a 500-year floodplain zone according to the FEMA Map No. 08041CO951G (Reference 7). Groundwater was encountered in one test boring TB-2 at a depth of 15.5 feet (Reference 2, Appendix B). Any grading modifications should direct surface flows around the structures. Drainage studies are beyond the scope of this report.

We trust that this has provided you with the information required regarding a Geologic Hazard Waiver, a copy of Geologic Hazard Waiver form is attached with this letter. If you have any questions or need additional information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.

Logan L. Langford, P.G.

Sr. Geologist

Reviewed by:

Joseph C

Goode Jr.

Digitally signed by Joseph C Goode Jr. Date: 2024.02.15 09:50:28 -07'00'

Joseph C. Goode, Jr. P.E.

President

Encl.

LLL

 $F: AA\ Projects \ 2024 \ 240217-DHN\ Dev-Southmoor\ Ridge-Gehoaz \ 09-Reports \ 240217\ geo\ waiver. docx$

DHN Development Geologic Hazard Waiver Request Southmoor Ridge Parcel Nos. 65133-14-015, 65133-00-021, 65242-00-052, and 65242-00-053 Southmoor Drive and Fontaine Boulevard Fountain Colorado, Colorado Page 3




REFERENCES

- 1. City of Fountain, Colorado, updated April 2023. *Fountain Planning & Map.* https://fountainco.maps.arcgis.com/apps/webappviewer/index.html?id=16d6981f04904cb3b48b24e7f90f9c6b
- 2. Entech Engineering, Inc., dated June 29, 2022. *Preliminary Subsurface Soil Investigation, Southmoor Properties, Fountain, Colorado.* Entech Job No. 221305.
- 3. Entech Engineering, Inc., dated October 26, 2022. *Infiltration Rates (Percolation Test Method), Southmoor Drive, Parcel Nos. 6513314015, 6513300021, 6524200052, and 6524200053, Fountain, Colorado.* Entech Job No. 222077.
- 4. White, Jonathan L., Lindsey, Kassandra O., Morgan, Matthew L., and Mahan, Shannon A., 2017. *Geologic Map of the Fountain Quadrangle, El Paso County, Colorado*. Colorado Geological Survey. Open-File Report 17-05.
- 5. Amuedo and Ivey. *Inactive Mine Reclamation Program, Extent of Mining Map.* Colorado Department of Natural Resources.
- 6. Dames and Moore. 1985. *Colorado Springs Subsidence Investigation*. State of Colorado, Division of Mined Land Reclamation.
- 7. Federal Emergency Management Agency. December 7, 2018. Flood Insurance Rate Maps for the City of Colorado Springs, Colorado. Map Number 08041CO951G.




FIGURES






VICINITY MAP

SOUTHMOOR RIDGE FOUNTAIN, COLORADO DHN DEVELOPMENT JOB NO. 240217






SOUTHMOOR RIDGE FOUNTAIN, COLORADO DHN DEVELOPMENT JOB NO. 240217





DEVELOPMENT PLAN


SOUTHMOOR RIDGE FOUNTAIN, COLORADO DHN DEVELOPMENT JOB NO. 240217





GEOLOGIC MAP OF THE FOUNTAIN QUADRANGLE

SOUTHMOOR DRIVE FOUNTAIN, COLORADO DHN DEVELOPMENT JOB NO. 240217






FEMA FLOODPLAIN MAP

SOUTHMOOR RIDGE FOUNTAIN, COLORADO DHN DEVELOPMENT JOB NO. 240217



APPENDIX A: Site Photographs





Looking northwest from eastern side of the site.

February 13, 2024





Looking southeast from the western side of site.

February 13, 2024

Job No. 240217






Looking north from western side of the site.

February 13, 2024





Looking south from the northern side of site.

February 13, 2024

Job No. 240217



APPENDIX B: EEI, Preliminary Subsurface Soil Investigation, Job No. 221305

ENTECH ENGINEERING, INC.

505 ELKTON DRIVE COLORADO SPRINGS, CO 80907 PHONE (719) 531-5599 FAX (719) 531-5238

June 29, 2022

Front Row Properties 1378 Promontory Bluff View Colorado Springs, CO 80921

Attn: Ron Waldthausen

Re: Preliminary Subsurface Soil Investigation

Southmoor Properties Fountain, Colorado

Dear Mr. Waldthausen:

As requested, personnel of Entech Engineering, Inc. have drilled twelve test borings to evaluate the site soil conditions for the anticipated development. This letter presents the results of our soils investigation, laboratory testing, and preliminary foundation recommendations.

SITE CONDITIONS:

The site development has not been determined and will likely consist of commercial and/or residential development with associated site improvements. Adjacent properties consist of commercial shopping center to the north and east, and a mix of rural residential and commercial properties to the west. The location of the site is shown in the vicinity map, Figure, 1. The site is gradually sloping to the southeast. At the time of our site investigation stables and out buildings were located in the southern portion of the site, and the remaining portion of the site was undeveloped. Vegetation consists of field grasses and weeds, with scattered trees in portions of the site, and fill piles were observed in the western portion of the site.

FIELD INVESTIGATION AND LABORATORY TESTING PROGRAM:

Subsurface conditions on the site were explored by drilling twelve test borings across the site. The test borings were drilled at the approximate locations shown on the Site Map/Test Boring Location Map, Figure 2. The borings were drilled to approximately 20 feet below the existing ground surface (bgs). The drilling was performed using a truck-mounted, continuous flight auger-drilling rig supplied and operated by Entech. Boring logs descriptive of the subsurface conditions encountered during drilling are presented in Appendix A. At the conclusion of drilling, observations for groundwater levels were made in the open boreholes.

Soil samples were obtained from the borings utilizing the Standard Penetration Test (ASTM D-1586) using 2-inch O.D. split-barrel and California samplers. Results of the Standard Penetration Test (SPT) are included on the boring logs in terms of N-values expressed in blows per foot (bpf). Soil samples recovered from the borings were visually classified and recorded on the boring logs. The soil classifications were later verified utilizing laboratory testing and grouped by soil type. The soil type numbers are included on the boring logs and in the provided chart. It should be understood that the soil descriptions shown on the boring logs may vary between boring location and sample depth. It should also be noted that the lines of stratigraphic separation shown on the boring logs represent approximate boundaries between soil types and the actual stratigraphic transitions may be more gradual and vary with location.

Moisture content testing (ASTM D-2216) was performed on the samples recovered from the borings, and the results are shown on the boring logs. Grain-Size Analysis Testing (ASTM D-422) was performed on selected samples to assist in classifying the materials encountered in the borings. Volume change testing was performed on selected samples using Swell/Consolidation (ASTM D-4546) tests in order to evaluate potential expansion/compression characteristics of the soil. Sulfate testing was performed on selected samples to evaluate potential for below grade concrete degradation due to sulfate attack. The Laboratory Testing Results are summarized on Table 1 and are presented in Appendix B.

SUBSURFACE CONDITIONS:

Three soil and rock types were encountered during drilling. The soils consisted of Type 1: very clayey sand, clean sand, and silty to slightly silty sand (SC, SW, SM, SM-SW), Type 2: sandy silt and sandy clay (ML, CL). The soils were classified using the Unified Soil Classification System (USCS).

<u>Soil Type 1</u> classified as very clayey sand, clean sand, and silty to slightly silty sand (SC, SW, SM, SM-SW). The sand was encountered in all test borings from the existing ground surface to depths of 13 to 18 feet bgs, and to the termination of Test Boring Nos. 6, and 8 – 10 (20 feet). Standard Penetration Testing resulted in SPT N-values of 2 to 41 bpf, indicating very loose to dense states. The majority of the sands were encountered at medium dense states. Moisture contents of 1 to 9 percent were measured, indicating dry to moist conditions. Grain size testing resulted in 5 to 49 percent of the soil passing the No. 200 sieve. Atterberg Limits Testing on a sample of the very clayey sand resulted in a liquid limit of 26 and plastic index of 10. Sulfate testing on a sample of very clayey sand resulted in less than 0.1 percent sulfate by weight, indicating a low potential for below grade concrete degradation.

<u>Soil Type 2</u> is classified as sandy silt and sandy clay (ML, CL). The silt and clay were encountered in five the test borings at depths of 13 to 19 feet bgs, extending to depths ranging from 17 to 19 feet, and the termination of Test Boring Nos. 4, 5, and 12 (20 feet bgs). Standard Penetration Testing resulted in an SPT N-value of 19 to 45 bpf, indicating stiff to very stiff consistencies. Moisture contents of 11 to 22 percent were measured, indicating moist conditions. Grain size testing resulted in 70 to 99 percent of the soil passing the No. 200 sieve. Atterberg Limits Testing resulted in a liquid limit of 49 and a plastic index of 21. Swell/Consolidation Testing resulted in volume changes of 0.7 to 1.7 percent, indicating a low to moderate expansion potential. Sulfate testing on the clay resulted in less than 0.1 percent sulfate by weight, indicating a low potential for below grade concrete degradation.

Soil Type 3 is classified as claystone and shale (CL, ML). The claystone and shale were encountered in four the test borings at depths of 13 to 19 feet bgs, extending to the termination of the test borings (20 feet bgs). Standard Penetration Testing resulted in an SPT N-value of 28 to greater than 50 bpf, indicating stiff to hard consistencies. Moisture contents of 13 to 17 percent were measured, indicating moist conditions. Grain size testing resulted in 88 to 97 percent of the soil passing the No. 200 sieve. Atterberg Limits Testing on the shale resulted in liquid limits of 40 and 44 and plastic indexes of 14 to 16. Swell/Consolidation Testing resulted in a volume change of 0.8 percent, indicating a low expansion potential. Sulfate testing on the shale resulted in 0.00 to 0.02 percent sulfate by weight, indicating a low potential for below grade concrete degradation.

Depth to groundwater was measured in each of the borings at the conclusion and subsequent to drilling. Groundwater was encountered in Test Boring No. 2 at 15.5 feet, groundwater was not

encountered in the remaining test borings were which drilled to depths of 20 feet bgs. It is anticipated groundwater will not affect construction on the site. Development of this site and adjacent properties, as well as seasonal precipitation changes, and changes in runoff may affect groundwater elevations.

GEOTECHNICAL EVALUATION AND RECOMMENDATIONS:

The following discussion is based on the subsurface conditions encountered in the borings drilled for the planned development. If subsurface conditions different from those described herein are encountered during construction or if the project elements change from those described, Entech Engineering, Inc. should be notified so that the evaluation and recommendations presented can be reviewed and revised if necessary.

The site is to be developed with commercial and/or residential structures and associated site improvements. Very loose to loose soils were encountered in several of the borings in the upper profile. Fill piles were observed on the site, however, fill was not encountered in the testing borings. If uncontrolled fill is encountered beneath foundations mitigation will be required. Loose soils or uncontrolled fill encountered within the building areas must be completely removed and recompacted. To provide a uniform bearing pad, at a minimum, it is recommended that the loose soils be penetrated or moisture-conditioned, and recompacted below the building(s). Prior to placing the structural fill, the subgrade should be scarified, moisture-conditioned, and compacted. Fill placed in building areas should be compacted according to the "Structural Fill" paragraph. Preliminary design considerations are discussed in the following sections. Additional subsurface soil investigation is recommended once development plans are prepared. The extent of overexcavation/recompaction will be determined at the time of the open excavation observations.

Expansive soils were encountered in the borings, however, are sporadic. Should expansive soils be encountered beneath the foundations, mitigation will be necessary. Mitigation of expansive soils will require overexcavation and replacement with non-expansive soils at 95% of its maximum Modified Proctor Dry Density, ASTM D-1557 is a suitable mitigation which is common in the area. Floor slabs on expansive soils should be expected to experience movement. Overexcavation and replacement has been successful in minimizing slab movements. Final recommendations should be determined after additional investigation of each building site.

PRELIMINARY FOUNDATION RECOMMENDATIONS:

Shallow spread footing/stemwall foundation systems in conjunction with overexcavation/fill mitigation is anticipated for any structures to be built on this site. An allowable bearing pressure of 2000 pounds per square foot (psf) are anticipated for the site soils. Exterior footings should extend to a minimum of 30 inches for frost protection. Recommendations should be made after additional investigation and completion of the grading plans. Density testing of the reconditioned soil or structural fill placed on this site should be performed by a qualified individual.

Foundation walls retaining soils should be designed to resist lateral pressures generated by the soils. An equivalent hydrostatic fluid pressure (in the active state) of 45 pcf is recommended for the site soils. It should be noted that this value applies to level backfill conditions. Pressures may increase depending on the conditions adjacent to the walls. Surcharge loading if any, should be considered in wall designs. Equivalent fluid pressures for sloping conditions should be determined on an individual basis.

FOUNDATION EXCAVATION OBSERVATION:

The open foundation excavations should be observed by a representative of Entech Engineering, Inc. prior to construction of the foundation in order to verify that no anomalies are present, materials at the proper design bearing capacity have been encountered, and no soft or loose areas or debris are present in the excavation. Loose areas that require removal and or recompaction should be identified during site observations.

CONCRETE:

Type II cement is recommended for all concrete on this site. Concrete should not be placed on frozen or wet ground. Care should be taken to prevent the accumulation and ponding of water in the footing excavation prior to the placement of concrete. If standing water is present in the excavation, it should be removed from the excavation by pumping it away from the building area. Concrete placed during cold temperatures must be kept from freezing, which may require covering the concrete with insulated blankets and heating it.

FLOOR SLABS:

Floor slabs placed on loose soils should be expected to experience movement. The uncontrolled fill must be mitigated below slabs. Floor slabs on grade, if any should be separated from structural portions of the building, unless they are designed as part of the foundation system. Backfill placed below floor slabs should be compacted to a minimum of 95% of its maximum Modified Proctor Dry Density, ASTM D-1557.

SITE SEISMIC CLASSIFICATION

Based on the subsurface conditions encountered at the site and in accordance with Section 1613 of the 2015 International Building Code (IBC), the site meets the conditions of a Site Class E.

SURFACE AND SUBSURFACE DRAINAGE:

Positive surface drainage must be maintained around the structure to minimize infiltration of surface water. A minimum gradient of 5 percent in the first 10 feet adjacent to foundations is recommended. A minimum gradient of 2 percent is recommended for paved areas. All grades should be directed away from the structure. All downspouts should be extended to discharge well beyond the backfill zone of the structure.

A subsurface drain is recommended around portions of the structure which will have useable space located below the finished ground surface. A perimeter drain will not be required for slab on grade construction is the slab if above exterior grade. Typical drain details are included with this letter.

STRUCTURAL FILL:

Areas to receive structural fill should have all topsoil, organic material or debris removed. Fill must be properly benched. Prior to placing new fill, the surface should be scarified and moisture conditioned to within ±2 percent of its optimum moisture content and compacted to 95 percent of its maximum Modified Proctor Dry Density (ASTM D-1557) or to 95 percent of the soils maximum Standard Proctor Dry Density, ASTM D-698 at or above optimum moisture content. New fill should be placed in lifts not to exceed 6 inches after compaction while maintaining the above noted compaction requirements. Fill should be placed at a moisture

content conducive to compaction. The placement and compaction of fill should be observed and tested by Entech. Any imported soils should be approved by Entech prior to being hauled to the site. The on-site soils may be used as structural fill pending approval by Entech.

UTILITIES:

Backfill placed in utility trenches should be compacted to a minimum of 95 percent of its maximum Modified Proctor Dry Density (ASTM D-1557). Utility backfill should be placed in lifts having a compacted thickness of six inches or less and a moisture content conducive to adequate compaction, usually ±2 percent of its optimum Proctor moisture content. Mechanical methods should be used in placement of backfill; however, heavy equipment should be kept away from foundation walls. No water flooding techniques of any type should be used in compaction of backfill on the site.

Trench backfilling should be performed in accordance with City of Fountain specifications. Excavating should be performed in accordance with OSHA guidelines.

CLOSING:

The test borings were located to provide preliminary geotechnical information; variations in subsurface conditions may be encountered. In the event that the project scope changes, the conclusions and recommendations in this report should not be considered valid unless the changes are reviewed and the conclusions of this report are verified in writing or, if necessary, modified. Additional investigation will be required on the site as development/grading plans are prepared.

This report has been prepared for Front Row Properties for application to the proposed project in accordance with generally accepted soil and foundation engineering practices. No other warranty expressed or implied is made.

Respectfully Submitted,

ENTECH ENGINEERING, INC.

Logan L. Langford, P.G.

Geologist

LLL

Encl.

Entech Job No. 221305 AA projects\2022\221305-pssi Reviewed by:

Joseph C. Goode, Jr., P.E.

President






TABLE 1

SUMMARY OF LABORATORY TEST RESULTS

FRONT ROW PROPERTIES SOUTHMOOR DRIVE 221305 CLIENT PROJECT JOB NO.

TEST DRY PASSING LIQUID PLASTIC SULFATE SWELL (PSF) CONSOL (PSF) UNIFIED (PSF) SOIL DESCRIPTION 1 1 2-3 (PCF) (%) (WT %) (WT %) (PSF) (%) UNIFIED SOIL DESCRIPTION 1 4 5 4.7 4.3 26 10 <0.01 SOIL DESCRIPTION 1 4 5 4.7 (%) (WT %) (WT %) (PSF) (%) CLASSIFICATION SOIL DESCRIPTION 1 4 5 4.7 4.7 6 5 5 SOIL DESCRIPTION 1 4 5 4.7 4.7 6 5 5 SOIL DESCRIPTION 1 4 5 4.7 4.7 6 5 CLASSIFICATION SOIL DESCRIPTION 1 4 5 4.7 4.7 4.7 4.8 5 5 1 4 4.9 4.9 4.9 4.9 4.			_		_	_	_	_	_	_	_	_		_
TEST NO. MATER DENSITY NO. 200 SIEVE NO. 200 S		SOIL DESCRIPTION	SAND, VEHY CLAYEY	SAND	SAND, SLIGHTLY SILTY	SAND, SLIGHTLY SILTY	SAND, VERY CLAYEY	SAND, SILTY	SAND,S ILTY	SILT, SANDY	CLAY, SANDY	CLAY, SANDY	SHALE	SHALE
TEST BORING DEPTH WATER PLASING NO. 200 SIEVE NO.		UNIFIED CLASSIFICATION	SC	MS	MS-MS	MS-WS	os	SM	SM	ME	CL	כו	ML	MI
TEST BORING DEPTH WATER 10. DRY PASSING LIMIT INDEX PLASTIC (%) PASSING LIMIT INDEX PLASTIC (%) LIMIT INDEX PLASTIC (%) CPCF) (%) (%) (%) (%) (%) (WT%)	SWELL	CONSOL (%)								1.7	1.3	7.0	0.8	
TEST DRY NATER PASSING LIMIT INDEX NO. 200 SIEVE NO. 200	FHA	SWELL (PSF)												
TEST DHY PASSING LIMIT NO. 200 SIEVE		SULFATE (WT %)	<0.01							<0.01			0.00	0.02
TEST NO. (FT) (%) PASSING NO. 200 SIEVE NO. (FT) (%) (PCF) (%) (%) (PCF) (%) (%) (PCF) (%) (%) (PCF) (PCF) (%) (PCF) (PCF) (%) (PCF) (PLASTIC	INDEX (%)	10							21			16	14
TEST NO. (FT) (%) (PCF) NO. (FT) (%) (PCF)	LIQUID	LIMIT (%)	56							49			4	40
TEST BORING DEPTH WATER NO. (FT) (%) 1 2-3 (6 5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	PASSING	NO. 200 SIEVE (%)	43.9	4.7	5.1	10.2	49.1	24.2	22.4	97.4	98.5	70.2	0.76	88.2
TEST BORING DEPTH NO. (FT) NO. (FT) 1 2-3 4 6 6 5 6 5 8 2-3 9 2-3 10 5 11 10 5 15 7 15 7 15 2 15 3 20	PHO	DENSITY (PCF)		:						100.0	97.7	89.5	97.5	
TEST BORING NO. 1 1 1 10 10 10 12 2 2 3										14.9	21.9	23.4	15.1	
			2.3	2	2	2-3	2-3	5	10	15	15	20	15	8
SOIL TYPE 1 1 1 1 1 1 2 2 2 2 2 3 3	TEST	BORING NO.	 - 	4	9	8	8	10	11	5	7	12	2	က
		SOIL	1	1	1	1	1	١	1	2	2	7	3	හ








VICINITY MAP
SOUTHMOOR DRIVE PROPERTIES
FOUNTAIN, COLORADO
FOR: FRONT ROW PROPERTIES

DRAWN: DATE: CHECKED: DATE:

JOB NO.: 221305

FIG NO.:






SITE MAP/TEST BORING LOCATION MAP SOUTHMOOR DRIVE PROPERTIES FOUNTAIN, COLORADO FOR: FRONT ROW PROPERTIES

DRAWN: DATE: CHECKED: DATE:

JOB NO.: 221305

> FIG NO.: 2



NOTES:

- -GRAVEL SIZE IS RELATED TO DIAMETER OF PIPE PERFORATIONS-85% GRAVEL GREATER THAN 2x PERFORATION DIAMETER.
- -PIPE DIAMETER DEPENDS UPON EXPECTED SEEPAGE. 4-INCH DIAMETER IS MOST OFTEN USED.
- -ALL PIPE SHALL BE PERFORATED PLASTIC. THE DISCHARGE PORTION OF THE PIPE SHOULD BE NON-PERFORATED PIPE.
- -FLEXIBLE PIPE MAY BE USED UP TO 8 FEET IN DEPTH, IF SUCH PIPE IS DESIGNED TO WITHSTAND THE PRESSURES. RIGID PLASTIC PIPE WOULD OTHERWISE BE REQUIRED.
- -MINIMUM GRADE FOR DRAIN PIPE TO BE 1% OR 3 INCHES OF FALL IN 25 FEET.
- -DRAIN TO BE PROVIDED WITH A FREE GRAVITY OUTFALL, IF POSSIBLE. A SUMP AND PUMP MAY BE USED IF GRAVITY OUT FALL IS NOT AVAILABLE.



PERIMETER DRAIN DETAIL						
						
DRAWN:	DATE:	DESIGNED:	CHECKED:			

JOB NO.; 221305 FIC NO.; **APPENDIX A: Test Boring Logs**

TEST BORING NO. TEST BORING NO. DATE DRILLED 6/7/2022 DATE DRILLED 6/7/2022 FRONT ROW PROPERTIES CLIENT Job# 221305 LOCATION **SOUTHMOOR DRIVE** REMARKS REMARKS Blows per foot Blows per foot Watercontent Watercontent Soil Type Samples Soil Type Depth (ft) Samples Symbol Symbol DRY TO 18.5', 6/9/22 WATER @ 15.5', 6/9/22 ٥.,٥ SAND, GRAVELLY, SILTY, FINE SAND, VERY CLAYEY, FINE TO TO COARSE GRAINED, BROWN, COARSE GRAINED, BROWN, 25 1 5.0 MEDIUM DENSE, MOIST 24 3.8 MEDIUM DENSE TO LOOSE, SAND, GRAVELLY, SILTY, FINE MOIST 5 15 3.1 1 8 2.3 1 TO COARSE GRAINED, BROWN, MEDIUM DENSE TO DENSE, MOIST TO DRY 10 33 1.3 1 10 11 1.6 1 CLAYSTONE, SANDY, DARK 15 3 <u>50</u> | 12.9 44 | 14.0 | GRAY, HARD, MOIST 15 SHALE, GRAY BROWN, VERY 10" STIFF TO HARD, MOIST 50 5" 13.4 3 50 13.8 3

A	ENTECH
7.7	ENGINEERING, INC.
	505 ELKTON DRIVE COLORADO SPRINGS, COLORADO 80907

	TE	ST BORING LO	OG
DRAWN:	DATE:	CHECKED:	DATE: 6/27/22

JOB NO.: 221305 FIG NO.: A- 1

TEST BORING NO. TEST BORING NO. DATE DRILLED DATE DRILLED 6/7/2022 6/7/2022 Job# 221305 CLIENT FRONT ROW PROPERTIES LOCATION SOUTHMOOR DRIVE REMARKS REMARKS Blows per foot Blows per foot Watercontent Watercontent Type Depth (ft) Soil Type Depth (ft) Samples Samples Symbol Symbol Symbol DRY TO 18.5', 6/9/22 DRY TO 19', 6/9/22 SAND, GRAVELLY, SILTY, FINE SAND, GRAVELLY, CLEAN TO TO COARSE GRAINED, BROWN SILTY, FINE TO COARSE GRAINED, 0 TO TAN, MEDIUM DENSE TO 13 0.9 TAN, DENSE TO MEDIUM DENSE. 32 1.7 1 DENSE, DRY DRY TO MOIST 5 7 41 0.8 1 27 2.3 1 10 T 10 14 2.4 1 15 2.7 1 15 15 TZ 20 10.7 2 CLAY, SANDY, GRAY BROWN, 19 3.2 1 STIFF, MOIST WEATHERED SHALE, GRAY 28 17.3 3 CLAY, SANDY, GRAY BROWN, 33 10.9 2 BROWN, STIFF, MOIST VERY STIFF, MOIST

€>	ENTECH
	ENGINEERING, INC.
	505 ELKTON DRIVE COLORADO SPRINGS, COLORADO 6090

TEST BORING LOG				
DRAWN:	DATE:	CHECKED:	DATE 6/27/22	

221305 FIG NO.: A- 2

TEST BORING NO. TEST BORING NO. DATE DRILLED 6/7/2022 DATE DRILLED 6/7/2022 Job# 221305 FRONT ROW PROPERTIES CLIENT LOCATION SOUTHMOOR DRIVE REMARKS REMARKS % Samples Blows per foot Blows per foot Watercontent Watercontent Soil Type Depth (ft) Soil Type Depth (ft) Samples Symbol Symbol DRY TO 19', 6/9/22 DRY TO 18', 6/9/22 SAND, GRAVELLY, SILTY, FINE SAND, GRAVELLY, SLIGHTLY TO COARSE GRAINED, TAN, SILTY, FINE TO COARSE GRAINED, 7 LOOSE TO DENSE, DRY 1.0 4 TAN, LOOSE TO MEDIUM DENSE. 1.2 1 DRY TO MOIST 5 8 1.5 1 14 1.2 1 10 33 1.7 1 10 2 7.3 1 SILT, SANDY, DARK GRAY, 15 45 13.8 2 15 **7** VERY STIFF TO STIFF, MOIST 26 3.0 1 23 12.1 2 20 9 2.9 7.0. 1

	ENTECH
T.7	ENGINEERING, INC.
	505 ELKTON DRIVE COLORADO SPRINGS, COLORADO 80907

TEST BORING LOG					
DRAWN:	DATE:	CHECKED:	DATE: 6/27/22		

221305 FIG NO.: A- 3

TEST BORING NO. TEST BORING NO. 7 8 DATE DRILLED DATE DRILLED 6/7/2022 6/7/2022 Job# 221305 CLIENT FRONT ROW PROPERTIES LOCATION SOUTHMOOR DRIVE REMARKS REMARKS % Blows per foot Blows per foot Watercontent Watercontent Soil Type Depth (ft) Samples Samples Symbol Symbol Soil DRY TO 18.5', 6/9/22 DRY TO 15.5', 6/9/22 SAND, GRAVELLY, SILTY, FINE .6. SAND, GRAVELLY, SLIGHTLY TO COARSE GRAINED, TAN, SILTY, FINE TO COARSE GRAINED. 0.9 LOOSE TO DENSE, DRY 23 1 TAN, MEDIUM DENSE, MOIST 15 6.0 1 5 24 1.5 1 5 5.6 1 14 10 22 1.9 1 10 20 3.1 1 CLAY, SANDY, TAN, STIFF. 15 28 22.1 2 MOIST 15 28 4.3 CLAYSTONE, SANDY, GRAY BROWN, HARD, MOIST <u>50</u> 17.3 3 12 20 8.5 · o · ·



DRAWN:	DATE:	CHECKED:	DATE: 6/27/22


JOB NO.: 221305 FIG NO.: A- 4

TEST BORING NO. TEST BORING NO. 10 DATE DRILLED DATE DRILLED 6/8/2022 6/8/2022 Job# 221305 CLIENT FRONT ROW PROPERTIES LOCATION SOUTHMOOR DRIVE REMARKS REMARKS Blows per foot Blows per foot Watercontent Watercontent Soil Type Depth (ft) Depth (ft) Samples Samples Symbol Symbol DRY TO 20', 6/9/22 DRY TO 20', 6/8/22 SAND, VERY CLAYEY, FINE SAND, GRAVELLY, SILTY, FINE GRAINED, BROWN, MEDIUM TO COARSE GRAINED, BROWN, 17 5.8 DENSE, MOIST MEDIUM DENSE TO DENSE. 24 8.7 1 MOIST TO DRY 5 19 6.1 1 5 17 2.8 1 SAND, GRAVELLY, SILTY, FINE TO COARSE GRAINED, BROWN, 10 14 1.6 1 10 32 2.1 1 MEDIUM DENSE, DRY TO MOIST 15 35 15 27 4.1 1 7.3 1 28 4.5 1 20 36 1 6.3



	EST BORING LO	og	
DRAWN:	DATE:	CHECKED:	DATE: 6/27/27_

JOB NO.: 221305 FIG NO.: A- 5






TEST BORING LOG					
DRAWN:	DATE:	CHECKED:	DATE: (0/27/27		

221305 FIG NO. 6 **APPENDIX B: Laboratory Test Results**

UNIFIED CLASSIFICATION	SC	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	1	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	1	<u>JOB NO.</u>	221305
DEPTH (FT)	2-3	TEST BY	BL



U.S. <u>Sieve #</u> 3" 1 1/2"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit 16 Liquid Limit 26
3/4"		Plastic Index 10
1/2"		
3/8"	100.0%	
4	98.3%	<u>Swell</u>
10	89.6%	Moisture at start
20	78.7%	Moisture at finish
40	71.6%	Moisture increase
100	57.2%	Initial dry density (pcf)
200	43.9%	Swell (psf)




	LABOR RESUL	ATORY TEST TS	
DRAWN:	DATE:	CHECKED:	DATE: 6/27/22

JOB NO.: 221305

FIG NO.:

UNIFIED CLASSIFICATION	<u>on</u> sw	CLIENT FRONT ROW PROPERTIES
SOIL TYPE #	1	PROJECT SOUTHMOOR DRIVE
TEST BORING #	4	<u>JOB NO.</u> 221305
DEPTH (FT)	5	TEST BY BL



U.S. Sieve # 3" 1 1/2" 3/4"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
1/2"	100.0%	
3/8"	72.8%	
4	62.6%	<u>Swell</u>
10	41.8%	Moisture at start
20	24.8%	Moisture at finish
40	15.6%	Moisture increase
100	6.7%	Initial dry density (pcf)
200	4.7%	Swell (psf)




LABORATORY TEST RESULTS				
DRAWN:	DATE:	CHECKED:	DATE: 6/27/27	

JOB NO.: 221305

FIG NO.

UNIFIED CLASSIFICATION	SM-SW	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	1	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	8	<u>JOB NO.</u>	221305
DEPTH (FT)	2-3	TEST BY	BL



U.S. <u>Sieve #</u> 3"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit
1 1/2"		Liquid Limit
3/4"		Plastic Index
1/2"	100.0%	
3/8"	95.5%	
4	88.8%	<u>Swell</u>
10	64.3%	Moisture at start
20	42.2%	Moisture at finish
40	29.7%	Moisture increase
100	15.3%	Initial dry density (pcf)
200	10.2%	Swell (psf)




LABORATORY TEST RESULTS			
DRAWN:	DATE:	CHECKED:	DATE: 6/27/22

JOB NO.:: 221305

FIG NO.:

B-3

UNIFIED CLASSIFICATION	SM-SW	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	1	<u>PROJECT</u>	SOUTHMOOR DRIVE
TEST BORING #	6	<u>JOB NO.</u>	221305
DEPTH (FT)	5	TEST BY	BL




U.S. <u>Sieve #</u> 3" 1 1/2" 3/4"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
1/2" 3/8"	100.0% 87.7%	
4	71.8%	<u>Swell</u>
10	48.6%	Moisture at start
20	34.2%	Moisture at finish
40	24.1%	Moisture increase
100	7.7%	Initial dry density (pcf)
200	5.1%	Swell (psf)



	LABOF RESUL	RATORY TEST .TS	
DRAWN:	DATE:	CHECKED:	6/27/22

UNIFIED CLASSIFICATION	SC	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	1	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	9	JOB NO.	221305
DEPTH (FT)	2-3	TEST BY	BL




U.S. <u>Sieve #</u> 3" 1 1/2" 3/4"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
1/2"	100.00	
3/8"	100.0%	
4	96.4%	<u>Swell</u>
10	93.2%	Moisture at start
20	88.5%	Moisture at finish
40	83.1%	Moisture increase
100	64.2%	Initial dry density (pcf)
200	49.1%	Swell (psf)



LABORATORY TEST RESULTS			
DRAWN: DATE: CHECKED: DATE: LLL 6/27/2			

FIGNO:

UNIFIED CLASSIFICATION	SM	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	1	<u>PROJECT</u>	SOUTHMOOR DRIVE
TEST BORING #	10	<u>JOB NO.</u>	221305
DEPTH (FT)	5	TEST BY	BL




U.S. <u>Sieve #</u> 3" 1 1/2" 3/4"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
1/2" 3/8"	100.0%	Flastic moex
4	96.0%	Swell
10	82.8%	Moisture at start
20	71.4%	Moisture at finish
40	58.6%	Moisture increase
100	36.5%	Initial dry density (pcf)
200	24.2%	Swell (psf)



	LABOR RESUL	ATORY TEST		
DRAWN:	DRAWN: DATE: CHECKED: DATE:			
•				

FIG NO.: B-4

UNIFIED CLASSIFICATION	SM	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	1	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	11	<u>JOB NO.</u>	221305
DEPTH (FT)	10	<u>TEST BY</u>	BL



U.S. <u>Sieve #</u> 3" 1 1/2" 3/4"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
1/2" 3/8"	100.0%	
4	98.7%	<u>Swell</u>
10	83.0%	Moisture at start
20	58.2%	Moisture at finish
40	41.9%	Moisture increase
100 200	27.8% 22.4%	Initial dry density (pcf) Swell (psf)




LABORATORY TEST RESULTS			
DRAWN:	DATE:	CHECKED:	DATE: (g/27/2Z

FIG NO.:

B-7

UNIFIED CLASSIFICATION	ML	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	2	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	5	JOB NO.	221305
DEPTH (FT)	15	TEST BY	BL




U.S. <u>Sieve #</u> 3" 1 1/2" 3/4" 1/2" 3/8"	Percent <u>Finer</u>	Atterberg Limits Plastic Limit 28 Liquid Limit 49 Plastic Index 21
4 10		<u>Şwell</u> Moisture at start
20 40		Moisture at start Moisture at finish Moisture increase
100 200	100.0% 97.4%	Initial dry density (pcf) Swell (psf)



LABORATORY TEST RESULTS			
DRAWN:	DATE:	CHECKED:	DATE: 6/27/27

UNIFIED CLASSIFICATION	CL	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	2	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	7	JOB NO.	221305
DEPTH (FT)	15	TEST BY	BL



U.S. <u>Sieve #</u> 3" 1 1/2" 3/4" 1/2" 3/8"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
4 10		<u>Swell</u> Moisture at start
20 40		Moisture at finish Moisture increase
100 200	100.0% 98.5%	Initial dry density (pcf) Swell (psf)




	LABOF RESUL	RATORY TEST TS	
DRAWN:	DATE:	CHECKED:	DATE: 6/27/22
		•	

FIG NO.:

B-9

UNIFIED CLASSIFICATION	CL	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	2	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	12	JOB NO.	221305
DEPTH (FT)	20	TEST BY	BL




U.S. Sieve # 3" 1 1/2" 3/4" 1/2"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
3/8"	100.0%	Q
4	99.4%	Swell
10	94.7%	Moisture at start
20	89.2%	Moisture at finish
40	84.5%	Moisture increase
100	74.7%	Initial dry density (pcf)
200	70.2%	Swell (psf)



	LABOF RESUL	RATORY TEST LTS	
DRAWN: DATE: CHECKED: DATE: Ce/27/			

FIGNO:

UNIFIED CLASSIFICATION	ML	CLIENT	FRONT ROW PROPERTIES
SOIL TYPE #	3	PROJECT	SOUTHMOOR DRIVE
TEST BORING #	2	JOB NO.	221305
DEPTH (FT)	15	TEST BY	BL




U.S. <u>Sieve #</u> 3" 1 1/2" 3/4" 1/2" 3/8"	Percent <u>Finer</u>	Atterberg Limits Plastic Limit 28 Liquid Limit 44 Plastic Index 16
4 10		<u>Swell</u> Moisture at start
20 40		Moisture at finish Moisture increase
100 200	100.0% 97.0%	Initial dry density (pcf) Swell (psf)



LABORATORY TEST RESULTS			
DRAWN:	DATE:	CHECKED:	DATE (0/27/22

FIGNO.

UNIFIED CLASSIFICAT	ION ML	<u>CLIENT</u> FRONT ROW PROPERTIES
SOIL TYPE #	3	PROJECT SOUTHMOOR DRIVE
TEST BORING #	3	<u>JOB NO.</u> 221305
DEPTH (FT)	20	TEST BY BL




U.S. <u>Sieve #</u> 3" 1 1/2" 3/4" 1/2" 3/8"	Percent <u>Finer</u>	Si	Atterberg <u>Limits</u> Plastic Limit 26 Liquid Limit 40 Plastic Index 14
4	100.0% 98.8%		<u>Swell</u> Moisture at start
20 40	91.4% 88.9%		Moisture at finish Moisture increase
100 200	88.3% 88.2%		Initial dry density (pcf) Swell (psf)



LABORATORY TEST RESULTS			
DRAWN:	DATE:	CHECKED:	DATE: (a/27/22

TEST BORING # 5 DEPTH(ft) 15
DESCRIPTION ML SOIL TYPE 2
NATURAL UNIT DRY WEIGHT (PCF) 100
NATURAL MOISTURE CONTENT 14.9%
SWELL/CONSOLIDATION (%) 1.7%

JOB NO. 221305
CLIENT FRONT ROW PROPERTIES
PROJECT SOUTHMOOR DRIVE






SWELL CONSOLIDATION TEST RESULTS				
PAWN:	DATE:	CHECKED:	DATE:	

JOB NO.: 221305

B-/3

TEST BORING #	7	DEPTH(ft)	15
DESCRIPTION	CL	SOIL TYPE	2
NATURAL UNIT DRY	WEIG	HT (PCF)	98
NATURAL MOISTUR	E CON	TENT	21.9%
SWELL/CONSOLIDA			1.3%

JOB NO. 221305
CLIENT FRONT ROW PROPERTIES
PROJECT SOUTHMOOR DRIVE





SWELL CONSOLIDATION
TEST RESULTS


DRAWN: DATE: CHECKED: DATE: (e/27/27

JOB NO. 221305

FIG NO.: 8-14

TEST BORING #	12	DEPTH(ft)	20	
DESCRIPTION	CL		2	
NATURAL UNIT DRY	WEIGI	HT (PCF)	89	
NATURAL MOISTUR	E CON	TENT	23.4%	
SWELL/CONSOLIDA	TION (%)	0.7%	

JOB NO. 221305
CLIENT FRONT ROW PROPERTIES
PROJECT SOUTHMOOR DRIVE





SWELL CONSOLIDATION
TEST RESULTS


DRAWN: DATE: CHECKED: DATE: 6/27/22

JOB NO.: 221305

FIG NO: 8-15

TEST BORING #	2	DEPTH(ft)	15	
DESCRIPTION	ML		3	
NATURAL UNIT DRY	WEIGH	HT (PCF)	98	
NATURAL MOISTUR	E CON	ΓENT	15.1%	
SWELL/CONSOLIDA			0.8%	

JOB NO. 221305
CLIENT FRONT ROW PROPERTIES
PROJECT SOUTHMOOR DRIVE





SWELL CONSOLIDATION TEST RESULTS	
20 AV	

DRAWN: DATE: GHECKED: DATE:

LLL G/27/22

JOB NO.: 221305

CLIENT	FRONT ROW PROPERTIES	JOB NO.	221305
PROJECT	SOUTHMOOR DRIVE	DATE	6/22/2022
LOCATION	SOUTHMOOR DRIVE	TEST BY	BL

BORING NUMBER	DEPTH, (ft)	SOIL TYPE NUMBER	UNIFIED CLASSIFICATION	WATER SOLUBLE SULFATE, (wt%)
TB-1	2-3	1	sc	<0.01
TB-2	15	3	ML	0.00
TB-3	20	3	ML	0.02
TB-5	15	2	ML	<0.01
		. <u>.</u>		
	:			

QC BLANK PASS



		ATORY TEST TE RESULTS	
DRAWN:	DATE:	CHECKED:	DATE: 4/27/11

JOB NO.: **221305**

FIG NO.: B-17



APPENDIX C: EEI, Infiltration Rates (Percolation Test Method), Job No. 222077





505 ELKTON DRIVE COLORADO SPRINGS, CO 80907 PHONE (719) 531-5599 FAX (719) 531-5238

October 26, 2022

Front Row Properties 1378 Promontory Bluff View Colorado Springs, CO 80921

Attn:

Ron Waldthausen

Re:

Infiltration Rates (Percolation Test Method)

Southmoor Drive

Parcel Nos. 6513314015, 6513300021, 6524200052, and 6524200053

Fountain, Colorado

Dear Mr. Waldthausen:

As requested, personnel of Entech Engineering, Inc. have performed percolation testing at the above referenced site to evaluate the site soils to determine the infiltration rate for the proposed detention pond.

The testing was performed on October 21, 2022. The site vicinity map is shown in Figure 1 and the test locations are shown in Figure 2. The Test Boring Logs, Percolation Test results, Infiltration Rates, and Laboratory Test results are shown in Figures 3 through 11. Soils encountered in the profile and percolation hole consisted of silty to very silty sand. Bedrock and groundwater were not encountered in the profile holes, which was drilled to 10 feet.

The percolation rates were 4 minutes/inch for P1, 3 minutes/inch for P2, and 4 minutes/inch for P3. The percolation rates correspond to adjusted average Infiltration Rate of 1.95 inches/hour for pond 1, 3.31 inches/hour for pond 2, and 2.15 inches/hour for pond 3.

We trust that this has provided you with the information you required. If you have any questions or need additional information, please do not hesitate to contact us.

Respectfully Submitted,

ENTECH ENGINEERING, INC.

Logan L. Langford, P.G.

Geologist


LLL/jr


Encl.

Entech Job No. 222077 AAprojects/2022/222077 Infiltration Rate Reviewed by:

Austin M. Nossokoff, P.E.

Project Engineer







SITE PLAN/PERCOLATION HOLE LOCATION MAP SOUTHMOOR DRIVE FOUNTAIN, COLORADO FOR: FRONT ROW PROPERTIES				
DRAWN:	DATE:	CHECKED:	DATE:	
JHR	10/21/22	LLL		

JOB NO.: 222077 FIG NO.: 2

TEST BORING NO. TEST BORING NO. 2 DATE DRILLED 10/19/2022 DATE DRILLED 10/19/2022 Job# 222077 CLIENT FRONT ROW PROPERTIES LOCATION SOUTHMOOR DRIVE REMARKS REMARKS Watercontent % Blows per foot Blows per foot Watercontent Depth (ft) Depth (ft) Soil Type Samples Samples Symbol Symbol DRY TO 10', 10/19/22 DRY TO 10', 10/19/22 SAND, SILTY, FINE TO COARSE SAND, VERY SILTY, FINE TO GRAINED, TAN, MEDIUM DENSE, MEDIUM GRAINED, TAN, MEDIUM MOIST TO DRY 3.5 DENSE TO DENSE, MOIST 23 24 6.7 26 1.3 12 4.4 10 111 10 1.4 30 4.6 * - BULK SAMPLE TAKEN 15 15 20



	TES	ST BORING LO)G
DRAWN:	DATE:	CHECKED:	DATE: 10- 21- 22




TEST BORING NO. TEST BORING NO. DATE DRILLED 10/19/2022 DATE DRILLED Job# CLIENT FRONT ROW PROPERTIES 222077 LOCATION SOUTHMOOR DRIVE REMARKS REMARKS Watercontent % Watercontent % Samples Blows per foot Blows per foot Soil Type Soil Type Depth (ft) Depth (ft) Samples Symbol Symbol DRY TO 10', 10/19/22 SAND, VERY SILTY, FINE TO MEDIUM GRAINED, TAN, MEDIUM 20 6.0 DENSE, MOIST TO DRY 15 l 3.0 10 1.9 * - BULK SAMPLE TAKEN 15 20

4	ENTECH
7.7	ENGINEERING, INC.
	505 ELKTON DRIVE
	COLORADO SPRINGS, COLORADO 80907

	TE	ST BORING L	og
DRAWN:	DATE:	CHECKED:	DATE: 10-21-22



BORING NO. PH-1 <u>UNIFIED CLASSIFICATION</u> SM <u>TEST BY</u> BL
DEPTH(ft) 2-3 <u>AASHTO CLASSIFICATION</u> JOB NO. 222077
CLIENT FRONT ROW PROPERTIES



U.S. <u>Sieve #</u> 3" 1 1/2" 3/4" 1/2" 3/8"	Percent <u>Finer</u>	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
4	92.8% 81.3%	<u>Swell</u> Moisture at start
20	70.5%	Moisture at finish
40	62.2%	Moisture increase
100	46.3%	Initial dry density (pcf)
200	36.7%	Swell (psf)



	LABORATO RESULTS	DRY TEST	
DRAWN:	DATE:	CHECKED: JHR	Id-74-22

JOB NO.:

BORING NO. PH-2

2-3

UNIFIED CLASSIFICATION **AASHTO CLASSIFICATION** TEST BY


BL


DEPTH(ft) **CLIENT**

FRONT ROW PROPERTIES

SM

JOB NO. 222077





U.S.	Percent	Atterberg
Sieve_#	<u>Finer</u>	<u>Limits</u>
3"		Plastic Limit
1 1/2"		Liquid Limit
3/4"		Plastic Index
1/2"		
3/8"	100.0%	
4	99.5%	<u>Swell</u>
10	96.2%	Moisture at start
20	90.3%	Moisture at finish
40	81.9%	Moisture increase
100	62.7%	Initial dry density (pcf)
200	48.6%	Swell (pst)



	LABORATO RESULTS	ORY TEST	
DRAWN:	DATE:	2HK CHECKED:	DATE:

JOB NO.: FIG NO.:

6

BORING NO. PH-3

UNIFIED CLASSIFICATION AASHTO CLASSIFICATION TEST BY


BL

DEPTH(ft) **CLIENT**

2-3 FRONT ROW PROPERTIES SM

JOB NO. 222077





U.S. Sieve # 3" 1 1/2" 3/4" 1/2" 3/8"	Percent Finer	Atterberg <u>Limits</u> Plastic Limit Liquid Limit Plastic Index
4	97.8%	<u>Swell</u>
10	90.1%	Moisture at start
20	81.3%	Moisture at finish
40	72.6%	Moisture increase
100	55.5%	Initial dry density (pcf)
200	45.1%	Swell (psf)



	LABORATO RESULTS	DRY TEST	Ì
DRAWN:	DATE:	CHECKED:	DATE:

JOB NO.:

Client:

Front Row Properties

Test Location:

Southmoor Drive

Job Number:

222077

PERCOLATION HOLES #1

Date Holes Prepared:

10/19/2022

Date Hole Completed:

10/20/2022

Hole No. 1

<u>Trial</u>

1

2

3

59"

Hole No. 2

3

61" Depth:

Water

Hole No. 3

Depth:

Depth:

Time

(min.)

5

5

5

Water Level Change (in.)

Time Trial (min.) 1 5 2 5

Level Change (in.) 2 2 2

Time Trial (min.) 1 5

2

3

Water Level Change (in.)

Perc Rate (min./in.):

4

1

2

Perc Rate (min./in.):

5

2.5

Perc Rate (min./in.):

5

5

5

1

1

Average Perc Rate (min./in.)

PROFILE HOLE

Date Profile Hole Completed:

10/19/2022

Depth 0-10'

Visual Classification

Sand, silty, fine to coarse grained, tan

Remarks

No Bedrock No Groundwater

23 Blows / ft. @ 21 26 Blows / ft. @ 4'

Remarks:

GPS Coordinates: 38° 73.74694' N, -104° 73.4822' W

Observer: N. Schletzbaum

By:



PERCOLATION TEST RESULTS

CHECKED: DRAWN: DATE:

JOB NO.; 222077 FIG NO.:

Client:

Front Row Properties

Test Location:

Southmoor Drive

Job Number:

222077

PERCOLATION HOLES #2

Date Holes Prepared:

10/19/2022

Date Hole Completed:

10/20/2022

Hole No. 4

Depth:

Hole No. 5

Depth:

Hole No. 6

Depth:

 Trial
 (min.)
 Change (in.)

 1
 5
 1
 1/2

 2
 5
 1/2

 3
 5
 1

Trial (min.) Change (in.)

1 5 3
2 5 2
3 5 2

Perc Rate (min./in.):

3 1/2

Perc Rate (min./in.):

2

Perc Rate (min./in.):

2

Average Perc Rate (min./in.)

3

PROFILE HOLE

Date Profile Hole Completed:

10/19/2022

Depth 0-10' Visual Classification

Sand, very silty, fine to coarse grained, tan

Remarks

No Bedrock No Groundwater

24 Blows / ft. @ 2'

12 Blows / ft. @ 4'

30 Blows / ft. @ 9'

Remarks:

GPS Coordinates: 38° 73.76873' N, -104° 73.3695' W

Observer: N. Schletzbaum

By:



PERCOLATION	TEST	RESULTS

DRAWN: DATE: CHECKED: DATE: 10-12-12

JOB NO.:

Client:

Front Row Properties

Test Location:

Southmoor Drive

Job Number:

222077

PERCOLATION HOLES #3

Time

(min.)

5

5

5

Date Holes Prepared:

10/19/2022

Date Hole Completed:

10/20/2022

Hole No. 7

Trial

1

2

3

Hole No. 8

Hole No. 9 Depth:

3

Depth:

Water
Level
Change (in.)
I

Depth:

Trial

1

2

3

Water
Level
Change (in.)
2
1

Time

Trial (min.)

1 5
2 5

5

Perc Rate (min./in.):

- 5

Perc Rate (min./in.):

Time

(min.)

5

5

5

4

Perc Rate (min./in.):

3

2

1

2

Water

Level

Change (in.)

Average Perc Rate (min./in.)

4

PROFILE HOLE

Date Profile Hole Completed:

10/19/2022

Depth 0-10' Visual Classification

Sand, very silty, fine to coarse grained, tan

Remarks

No Bedrock No Groundwater

20 Blows / ft. @ 2' 15 Blows / ft. @ 4'

Remarks:

GPS Coordinates: 38° 73.59461' N, -104° 73.2943' W

Observer: N. Schletzbaum

By:



PERCOLATION TEST RESULTS

DRAWN:

DATE:

CHI

ECKED: DATE: 10-21-22

JOB NO.:

Infiltration Rate (I) = Percolation Rate (P)/ Reduction Factor(RF)

CLIENT FRONT ROW PROPERTIES
PROJECT SOUTHMOOR DRIVE
JOB NO. 222077

 $R_{f} = [(2d_1 - \Delta d) / dia] + 1$

d₁ = initial water depth (in.)

 Δd = final water level drop (in.)

dia = diameter of the percolation hole (in.)

Test No. P1 Perc Rate= dia =	<u>(PH-1)</u> 15 in/hr 8	Test No. P2 Perc Rate= dia =	<u>(PH-1)</u> 24 in/hr 8	Test No. P3 Perc Rate= dia =	(PH-1) 12 in/hr 8
$\begin{aligned} & \underbrace{\textbf{P1}}_{\textbf{d}_1} = \\ & \Delta \textbf{d} = \\ & \textbf{R}_f = \end{aligned}$	36.0 1.0 9.9	$ \frac{P2}{d_1} = \Delta d = R_t = R_t $	26.0 2.0 7.3	$\begin{aligned} & \underline{P3} \\ & d_1 = \\ & \Delta d = \\ & R_f = \end{aligned}$	43.0 1.0 11.6
1=	1.519 in/hr	I =	3.310 in/hr	I =	1.032 in/hr

(PH-1) I AVG= 1.954 in/hr

Test No. P1 Perc Rate= dia =	(PH-2) 17.14 in/hr 8	Test No. P2 Perc Rate= dia =		Test No. P3 (PH-2) Perc Rate= 30 dia = 8	in/hr
$\frac{P1}{d_1} = \\ \Delta d = \\ R_f =$	32.0 1.0 8.9	$ \frac{\mathbf{P2}}{d_1} = \\ \Delta d = \\ R_f = $	19.0 0.0 5.8	$ \frac{P3}{d_1} = 40.0 $ $ \Delta d = 2.0 $ $ R_f = 10.8 $	
l =	1.932 in/hr	1 =	5.217 in/hr	l = 2.791	in/hr
(PH-2) AVG= 3.313 in/hr					

Test No. P1 Perc Rate= dia =		Test No. P2 Perc Rate≠ dia =	-	Test No. P3 Perc Rate= dia =	20 in/hr 8
$\begin{aligned} &\frac{P1}{d_1} = \\ &\Delta d = \\ &R_f = \end{aligned}$	21.0 1.0 6.1	$\begin{aligned} & \underline{P2} \\ & d_1 = \\ & \Delta d = \\ & R_f = \end{aligned}$	39.0 1.0 10.6	$ \frac{P3}{d_1} = \Delta d = R_f = R_f $	23.0 2.0 6.5
I =	1.959 in/hr	I =	1.412 in/hr	I =	3.077 in/hr
(PH-3) AVG= 2.149 in/hr					



	INFILTRAT	ION TEST RES	SULTS
DRAWN:	DATE:	CHECKED:	DATE: 10-20-22

JOB NO.:

