



**ENTECH**  
 ENGINEERING, INC.  
 505 Elkton Drive  
 Colorado Springs, CO 80907  
 (719) 531-5599 • (719) 531-5238 (fax)

Client:	FLRD #5
Project:	Forest Lakes Residential Development, Filing 5
Entech Job #	192273

### CONCRETE TEST

RL			Test #: 53		
Date:	# of Specimens	Specified Strength (psi)	Time of Test	Hours Field Cured	Lab Receive Date:
5/26/2021	4	4000	9:20 AM	24	5/27/2021
<b>Specimen Type</b>		<b>Test Type</b>		<b>Type of Cure</b>	
<b>Cylinders 4x8</b>		<b>Field</b>		<b>Tank</b>	
Contractor:		Supplier:		Mix Design Number	
Trax Construction		Transit Mix		T34592110	
Truck Number		Ticket Number		Batch Time:	
25		86479220		8:22 AM	

Location:  
 Sidewalk; 2' North & 8' West off of the Northeast corner off of the intersection of Mesa Top Drive & Forest Lakes Drive.

Slump (in.):	Air (%):	Unit Weight (PCF):	Concrete Temp (°F)	Air Temp (°F)
4.5	4.5	141.0	70	56
<b>7-Day Strength</b>	<b>28-Day Strength</b>	<b>-Day Strength</b>	<b>56-Day Strength</b>	<b>-Day Strength</b>
4430	5640			
	5700			
	5920			
Average:	Average:	Average:	Average:	Average:
4430	5750			
Break Date:	Break Date:	Break Date:	Break Date:	Break Date:
6/2/2021	6/23/2021			

Remarks:  
 28 Day Results; Driver Notified of test results and added 5 oz of air.

Specifications:	Break Sequence:
4000 PSI, 5-8% Air, 4" Max Slump	1@7, 3@28
Summary Comments:	
Trax Construction, Transit Mix	

Reviewed By: *RPJ*

