



ENTECH
 ENGINEERING, INC.
 505 Elkton Drive
 Colorado Springs, CO 80907
 (719) 531-5599 • (719) 531-5238 (fax)

Client:	FLRD #5
Project:	Forest Lakes Residential Development, Filing 5
Entech Job #	192273

CONCRETE TEST

RL			Test #: 51		
Date:	# of Specimens	Specified Strength (psi)	Time of Test	Hours Field Cured	Lab Receive Date:
5/27/2021	0	4500	10:00 AM		
Specimen Type		Test Type		Type of Cure	
Cylinders 4x8		Field		Tank	
Contractor:		Supplier:		Mix Design Number	
Trax Construction		Transit Mix		T34592110	
Truck Number		Ticket Number		Batch Time:	
62		86479287		8:45 AM	

Location:
 Curb & Gutter; 5' South & 4' East off of the Southeast corner of the driveway at 15748 Long Valley Drive.

Slump (in.):	Air (%):	Unit Weight (PCF):	Concrete Temp (°F)	Air Temp (°F)
2.5	3.5	145.4	70	54
<i>7-Day Strength</i>	<i>28-Day Strength</i>	<i>-Day Strength</i>	<i>56-Day Strength</i>	<i>-Day Strength</i>
Average:	Average:	Average:	Average:	Average:
Break Date:	Break Date:	Break Date:	Break Date:	Break Date:

Remarks:
 No samples due to failing test. Notified truck driver who adjusted mix by adding 10oz of air & 5 gallons of water. Retesting same truck.

Specifications: 4500 PSI, 5-8% Air, 1" Max Slump	Break Sequence:
---	-----------------

Summary Comments:
 Trax Construction, Transit Mix

Reviewed By: *[Signature]*