



ENTECH
 ENGINEERING, INC.
 505 Elkton Drive
 Colorado Springs, CO 80907
 (719) 531-5599 • (719) 531-5238 (fax)

Client: **FLRD #5**
 Project: **Forest Lakes Residential Development, Filing 5**
 Entech Job # **192273**

CONCRETE TEST

EO			Test #: 12		
Date: 8/10/2020	# of Specimens: 4	Specified Strength (psi): 4500	Time of Test: 11:38 AM	Hours Field Cured: 24	Lab Receive Date: 8/11/2020
Specimen Type		Test Type		Type of Cure	
Cylinders 4x8		Field		Tank	
Contractor: PPC Construction		Supplier: Pete Lien		Mix Design Number: 90DJ50	
Truck Number: 987		Ticket Number: 974109		Batch Time: 10:34 AM	

Location:
 (Outlet Wing Walls) 150' east and 15' south off northeast corner of Lot 29, Forest Lakes Drive.


Slump (in.): 3.75	Air (%): 7.5	Unit Weight (PCF): 137.1	Concrete Temp (°F): 83	Air Temp (°F): 86
--------------------------	---------------------	---------------------------------	-------------------------------	--------------------------

7-Day Strength	28-Day Strength	-Day Strength	56-Day Strength	-Day Strength
3960	5220			
	5570			
Average: 3960	Average: 5400	Average:	Average:	Average:
Break Date: 8/17/2020	Break Date: 9/7/2020	Break Date:	Break Date:	Break Date:

Remarks:
28 Day Results

Specifications:
 4500 PSI, 4" Max Slump, 4.5-7.5% Air
 Summary Comments:
PPC Construction, Pete Lien

Break Sequence:
 1@7, 2@28, 1@hold



Reviewed By: *RLJ*