




LSC TRANSPORTATION CONSULTANTS, INC.  
2504 East Pikes Peak Avenue, Suite 304  
Colorado Springs, CO 80909  
(719) 633-2868  
FAX (719) 633-5430  
E-mail: [lsc@lsctrans.com](mailto:lsc@lsctrans.com)  
Website: <http://www.lsctrans.com>

## Sterling Ranch Sketch Plan Amendment Master Traffic Impact Study (LSC #S224440) October 26, 2022 **SKP-22-004**

### Traffic Engineer's Statement

This traffic report and supporting information were prepared under my responsible charge and they comport with the standard of care. So far as is consistent with the standard of care, said report was prepared in general conformance with the criteria established by the County for traffic reports.



### Developer's Statement

I, the Developer, have read and will comply with all commitments made on my behalf within this report.

A handwritten signature in blue ink, appearing to read 'H. C. Hodson, P.E.'

10/26/2022  
Date

# **Sterling Ranch Sketch Plan Amendment**

## **Master Traffic Impact Study**

Prepared for:

Loren J. Moreland

Vice President/ Project Manager

Classic SRJ

2138 Flying Horse Club Drive

Colorado Springs, CO 80921

OCTOBER 21, 2022

---

LSC Transportation Consultants

Prepared by: Kirstin D. Ferrin, P.E.

Reviewed by: Jeffrey C. Hodsdon, P.E.

LSC #S224440



## **CONTENTS**

REPORT CONTENTS .....	1
RECENT TRAFFIC REPORTS .....	2
Briargate-Stapleton Corridor Study/PPACG Model .....	2
STUDY AREA.....	3
Sketch Plan.....	3
Study-Area Access Plan .....	3
EXISTING ROAD AND TRAFFIC CONDITIONS.....	4
Existing Traffic Volumes .....	5
Existing Levels of Service .....	6
Burgess/Vollmer.....	6
Dines/Vollmer .....	6
Vollmer/Black Forest.....	6
Woodmen/Black Forest.....	7
Woodmen/Marksheffel.....	7
Safety and Accident Analysis.....	7
BASELINE CONDITIONS .....	7
TRIP GENERATION.....	8
TRIP DISTRIBUTION AND ASSIGNMENT.....	9
2042 TOTAL TRAFFIC.....	9
LEVEL OF SERVICE ANALYSIS .....	9
Intersection #1: Vollmer/Burgess.....	10
Intersection #2: Vollmer/Arroya .....	10
Intersection #3: Black Forest/Briargate.....	10
Intersection #4: Vollmer/Briargate .....	10
Intersection #5: Sterling Ranch/Briargate .....	10
Intersection #6: Banning Lewis/Briargate .....	11
Intersection #7: Dines/Vollmer .....	11
Intersection #8: E-W Collector/Sterling Ranch .....	11
Intersection #9: E-W Collector/Banning Lewis .....	11
Intersection #10: Dines/Sterling Ranch .....	11
Intersection #11: Black Forest/Research/Marksheffel .....	11

Intersection #12: Vollmer/Marksheffel .....	12
Intersection #13: Sterling Ranch/Marksheffel.....	12
Intersection #14: Vollmer/Black Forest.....	12
Intersection #15: Woodmen/Black Forest.....	12
Intersection #16: Woodmen/Marksheffel.....	12
Intersection #17: Woodmen/Banning Lewis .....	13
ROADWAY FUNCTIONAL CLASSIFICATIONS AND LANEAGE.....	13
AREA MTCP 2040 ROADWAY IMPROVEMENT PROJECTS .....	13
ROADWAY IMPROVEMENTS SUMMARY TABLE .....	14
CONCLUSIONS AND RECOMMENDATIONS .....	14
Trip Generation.....	14
Level of Service .....	15
Recommended Improvements.....	15
Enclosures: .....	16
Tables 1, 3, and 4	
Figures 1-12	
2008 TIS TAZ Map	
MTCP Maps	
Traffic Count Reports	
Level of Service Reports	
Crash History	
Sketch Plan Amendment	



LSC TRANSPORTATION CONSULTANTS, INC.  
2504 East Pikes Peak Avenue, Suite 304  
Colorado Springs, CO 80909  
(719) 633-2868  
FAX (719) 633-5430  
E-mail: [lsc@lsctrans.com](mailto:lsc@lsctrans.com)  
Website: <http://www.lsctrans.com>

October 21, 2022

Loren J. Moreland  
Vice President/ Project Manager  
Classic SRJ  
2138 Flying Horse Club Drive  
Colorado Springs, CO 80921

RE: Sterling Ranch  
Sketch Plan Amendment  
Master Traffic Impact Study  
El Paso County, Colorado  
LSC #S224440

Dear Mr. Moreland:

LSC Transportation Consultants, Inc. has prepared this Master Traffic Impact Study for the proposed Sterling Ranch Sketch Plan Amendment. As shown in Figure 1, Sterling Ranch is located east of Vollmer Road near Lochwinnoch Lane between the future extensions of Marksheffel Road and Stapleton Drive in El Paso County, Colorado.

## REPORT CONTENTS

The preparation of this report included the following:

- A list of previous Sterling Ranch traffic reports and the context of this project;
- A summary of the proposed land use and access plan;
- The existing roadway and traffic conditions in the site's vicinity including the roadway widths, surface conditions, lane geometries, traffic controls, and posted speed limits;
- Existing traffic volume data;
- Estimates of projected long-term baseline traffic volumes;
- The projected average weekday and peak-hour vehicle trips to be generated by the proposed future development within the sketch plan area;
- The assignment of the projected sketch-plan site-generated traffic volumes to the area roadways;
- The projected long-term total traffic volumes on the area roadways;
- The projected levels of service at the key intersections within the study area.;

- Master-study-level findings and recommendations for study area roadways and intersections, including number of lanes, auxiliary turn lanes, intersection traffic control, etc.
- The recommended street classifications;

## RECENT TRAFFIC REPORTS

LSC prepared a previous master traffic impact study (TIS) for the entire Sterling Ranch development dated June 5, 2008. Since 2008 LSC and SM Rocha, LLC have completed multiple studies for individual filings and phases within Sterling Ranch. A list of other traffic studies within Sterling Ranch and in the vicinity of area of study completed within the past five years (that LSC is aware of) is attached for reference. This study accounts for the land use, trip generation, and the roadway network included in these studies.

### **Briargate-Stapleton Corridor Study/PPACG Model**

The El Paso County Department of Public Works recently released a draft traffic report prepared by Wilson & Company (December 9, 2021) as part of Briargate-Stapleton Corridor Study. The forecast 2045 total traffic volumes in that study were developed using the PPACG 2045 fiscally constrained RTP model as well as reference studies including the *Black Forest Widening Project Traffic Impact Study* and traffic impact studies completed for the Wolf Ranch, The Ranch, Sterling Ranch, Highland Park, and Eagle Rising developments.

Sterling Ranch is included in the PPACG model as part of traffic analysis zones (TAZs) 238 and 842. These TAZs also include the areas planned to be developed as The Ranch and Percheron. The Sterling Ranch Sketch Plan is currently capped at 5,225 dwelling units, but this report has been based on an anticipated maximum of 4,800 dwelling units. The Ranch Sketch Plan, located east of Sterling Ranch, shows the potential for up to 2,144 future dwelling units. Percheron will be capped at 2,650 dwelling units and the section north of Woodmen Road will likely be developed with a maximum of 2,200 dwelling units.

These three developments include the potential for a total of 9,144 potential dwelling units within the areas shown as TAZs 238 and 842. The 2045 PPACG model includes 8,900 households within these two TAZs. This is about 669 fewer dwelling units than could be developed within the area containing Sterling Ranch, The Ranch and Percheron based on the respective traffic studies. However, the maximum density may not be achieved for each of these projects and/or they may not all be fully built out by 2045.

## STUDY AREA

### Sketch Plan

Figure 2 shows the proposed amendment to the Sketch Plan. The 1,444-acre Sterling Ranch Sketch Plan area is partially developed and planned to ultimately include a mix of residential, commercial, and educational land uses. The 2008 TIS divided the sketch plan area into 21 traffic analysis zones (TAZs). Figure 3 from that report showed the location and boundary of each TAZ. A copy of this TAZ figure is attached for reference. Table 1 shows a comparison of the land use assumed in the 2008 TIS and the land uses proposed as part of the current Sketch Plan Amendment. Figure 3 shows the location of the current TAZs. **The number of residential dwelling units for Sterling Ranch is now proposed to be capped at 4,800.** Please note that although the maximum number of dwelling units for the approved Sketch Plan was 5,225, the 2008 TIS assumed 5,500 residential dwelling units within Sterling Ranch.

 This has been added as a condition  
on the sketch plan.

### Study-Area Access Plan

The access plan for the current Sketch Plan is generally consistent with the access plan shown in the 2008 Master TIS.

Figure 4 shows the current access plan for **Briargate Parkway**. The figure also highlights some minor changes to the access plan depicted in the 2008 Master TIS.

The following summarizes the minor changes:

- The access to Vollmer Road for TAZ 2 shown in the 2008 TIS report has since been shifted about 885 feet south (approximately halfway between the future locations of Marksheffel Road and Lochwinnoch Lane) and restricted to right-in/right-out only. This street connection to Vollmer is part of Sterling Ranch Filing No. 2 and is a public street called Alzada Drive. The Alzada Drive/Vollmer Road intersection is right-in/right-out only.  
**Note:** The June 2008 TIS report showed a shared access (shared with the adjacent Barbarick Subdivision industrial development) aligning with the existing Vollmer Road/Lochwinnoch Lane intersection.
- The originally-proposed right-in/right-out access on Marksheffel Road to TAZ 2 is no longer proposed and is not shown on the existing plans.
- The Sterling Ranch access to Briargate Parkway just east of Vollmer Road (Wheatland Drive), previously shown as a right-in/right-out-only intersection for both the north and south sides of Briargate in the Sketch Plan, is now a three-quarter-movement (left-in/right-in/right-out-only) access for the south leg (the north side access will remain right-in/right-out). A deviation request for this access point was submitted and approved.

The Briargate Parkway-Stapleton Road Corridor Study Appendix D: Access Control Plan shows the access locations and intersection access restrictions along Briargate Parkway between Black Forest Road and Meridian Road. The currently proposed Sterling Ranch Sketch Plan Amendment has several access points that are not included in the access control plan.

- The access control plan shows a right-in/right-out access to the south side of Briargate Parkway at Wheatland Drive between Vollmer Road and Sterling Ranch Road. The currently proposed Sketch Plan Amendment shows a three-quarter movement access for the south leg and a right-in/right-out access on the north leg. A deviation request for this access point has been submitted and approved.
- The access control plan shows a right-in/right-out access point north and south of Briargate Parkway between Wheatland Drive and Sterling Ranch Road. The currently proposed sketch plan shows two offset three-quarter movement (left-in/right-in/right-out only) access points.
- The access control plan shows the intersection of Briargate Parkway/Sterling Ranch Road as a three-leg intersection. The currently proposed Sketch Plan includes a north leg at this future full-movement signal-controlled intersection.
- The currently proposed Sketch Plan Amendment shows a right-in/right-out access to the north side of Briargate Parkway about 1,230 feet east of Sterling Ranch Road that is not shown on the access control plan.
- The access control plan shows a right-in/right-out access to the south side of Briargate Parkway just west of Banning Lewis Parkway. The currently proposed Sketch Plan Amendment shows a right-in/right-out access to the north side of Briargate and a three-quarter movement access to the south side of Briargate at approximately the same location (1,085 feet west of Banning Lewis Parkway).
- The access control plan shows the intersection of Briargate/Banning Lewis as a three-leg intersection. The currently proposed Sketch Plan includes a north leg at this future full-movement signal-controlled intersection.

#### **EXISTING ROAD AND TRAFFIC CONDITIONS**

**Review changes in access points for potential deviation requests. Provide additional deviation requests where required.**

The adjacent streets are shown in Figure 1 and are described below. Copies of the *2016 El Paso County Major Transportation Corridors Plan (MTCP)*, *2040 Roadway Plan*, and *2016 MTCP 2060 Corridor Preservation Plan* with the site location identified on them have been attached to this report.

**Vollmer Road** is currently a five-lane urban street within the City of Colorado Springs limits between Black Forest Road and Cowpoke Road; and a two-lane, rural, paved roadway north of Cowpoke Road extending to north of Hodgen Road. In the southbound direction, Vollmer Road has a posted speed limit of 45 mph. South of Cowpoke Road, Vollmer Road has a 40-mph posted speed limit. The *2040 El Paso County Major Transportation Corridors Plan (MTCP)* and the prior Sterling Ranch master traffic study show Vollmer Road as a four-lane Urban Minor Arterial in the vicinity of the site.

**Marksheffel Road** is a Principal Arterial extending north from the City of Fountain to Woodmen Road. Marksheffel Road is planned to ultimately be widened to six lanes and extended north and west from Woodmen Road to connect to Research Parkway at Black Forest Road. Marksheffel Road is shown as a four-lane Principal Arterial through the site on the El Paso County *MTCP*. The City of Colorado Springs intends to take ownership and maintenance of Marksheffel Road when it is constructed from Vollmer to the east and south to where it will connect to the segment constructed north of Woodmen Road in the City.

The section of Marksheffel Road adjacent to Sterling Ranch is planned to be constructed on 107 feet of right-of-way to the City's required cross section(s) and criteria. The section of Marksheffel Road between Sterling Ranch Road and Vollmer Road will be constructed in the very short-term future and the section of Marksheffel Road southeast of Sterling Ranch Road (to connect to the segment recently constructed) will be completed in the short term and will open the connection to Woodmen Road. Marksheffel will be constructed as a four-lane roadway to the previously agreed upon cross section.

**Briargate Parkway** is a six-lane, Principal Arterial that extends east from I-25 to Grand Lawn Circle (about one-half mile east of Powers Boulevard). Briargate Parkway is planned ultimately to extend to Towner Drive. The segment of Briargate Parkway between Vollmer Road and Sterling Ranch Road is planned to be constructed in the short term.

**Sterling Ranch Road** is a planned Non-Residential Collector shown extending through the Sterling Ranch development between Marksheffel Road and the north end of the Sketch Plan area (Arroya Road). The segment south of Briargate Parkway will be constructed in the short term.

**Tahiti Drive** is a gravel road which extends for about 750 feet north from Vollmer Road. The intersection of Vollmer/Tahiti is located just south of the future location of the intersection of Vollmer/Marksheffel. This intersection is planned to be closed with the construction of Marksheffel Road between Vollmer Road and Sterling Ranch Road. Access for the existing home using this access will be relocated north to Loch Fyne Lane.

### **Existing Traffic Volumes**

Figures 5a and 5b show the existing average weekday and peak-hour traffic volumes at the key study-area intersections. The peak-hour traffic volumes shown are based on manual turning-movement counts by LSC Transportation Consultants and All Traffic Data Services. The date of each count is shown in Figure 5b. The average weekday traffic volumes shown in Figure 5a are estimates by LSC, based on the manual peak-hour traffic-count data. The traffic count sheets are attached.

### Existing Levels of Service

Level of service (LOS) is a quantitative measure of the level of congestion or delay at an intersection. Level of service is indicated on a scale from “A” to “F.” LOS A represents control delay of less than 10 seconds for unsignalized intersections. LOS F represents control delay of more than 50 seconds for unsignalized intersections. Table 2 shows the level of service delay ranges.

**Table 2: Intersection Levels of Service Delay Ranges**

Level of Service	Signalized Intersections	Unsignalized Intersections
	Average Control Delay (seconds per vehicle)	Average Control Delay (seconds per vehicle) <sup>(1)</sup>
A	10.0 sec or less	10.0 sec or less
B	10.1-20.0 sec	10.1-15.0 sec
C	20.1-35.0 sec	15.1-25.0 sec
D	35.1-55.0 sec	25.1-35.0 sec
E	55.1-80.0 sec	35.1-50.0 sec
F	80.1 sec or more	50.1 sec or more

(1) For unsignalized intersections, if V/C ratio is greater than 1.0 the level of service is LOS F, regardless of the projected average control delay per vehicle.

The signalized intersections of Vollmer/Black Forest, Woodmen/Black Forest, and Woodmen/Marksheffel have been analyzed using Synchro. The intersections Burgess/Vollmer and Dines/Vollmer have been analyzed based on the unsignalized-intersection analysis procedures from the *Highway Capacity Manual, 6th Edition* by the Transportation Research Board.

#### Burgess/Vollmer

The stop-sign-controlled intersection of Burgess/Vollmer is currently operating at LOS E for the eastbound approach and LOS F for the westbound approach during the afternoon peak hour.

#### Dines/Vollmer

All movements at the stop-sign-controlled intersection of Dines/Vollmer are currently operating at LOS B or better during the peak hours.

#### Vollmer/Black Forest

The signal-controlled intersection of Vollmer/Black Forest is currently operating at an overall LOS C during the morning peak hour and LOS B during the afternoon peak hour.

### Woodmen/Black Forest

The signal-controlled intersection of Woodmen/Black Forest is currently operating at an overall LOS C during the morning and afternoon peak hours. The northbound, eastbound, and westbound left-turn movements are currently operating at LOS E during the peak hours.

### Woodmen/Marksheffel

Based on the existing signal-timing plan, the intersection of Woodmen/Marksheffel is currently operating at an overall LOS C during the morning and afternoon peak hours. The northbound left-turn movement is currently operating at LOS F and the eastbound left-turn, westbound left-turn, and southbound through movements are currently operating at LOS E during the peak hours.

### **Safety and Accident Analysis**

The Colorado State Patrol (CSP) provided LSC with crash history data for Vollmer Road between Tahiti Drive and Burgess Road from September 2019 through September 2022. During the reported time period, there were twelve reported crashes. Of the twelve reports, ten were single-vehicle non-intersection-related crashes on Vollmer Road. One crash involved a southbound vehicle that turned right onto Poco Road and crashed into several cars parked on Poco Road partially in the lane. The only intersection related crash occurred in June 2022. A vehicle heading northbound on Vollmer Road was slowing to turn left at Lochwinnoch Road and the vehicle behind them attempted to pass on the left side. The crash history data has been attached.

### **BASELINE CONDITIONS**

Baseline traffic is the traffic estimated to be on the adjacent roadways and at adjacent intersections without the proposed development's trip generation of site-generated traffic volumes. Baseline traffic (for a specified horizon year) includes the through traffic and the traffic generated by nearby developments (existing and planned) but assumes zero traffic generated by land uses within Sterling Ranch, including traffic generated by existing developments within Sterling Ranch.

Figure 6a shows the projected 2042 baseline daily traffic volumes on key street segments at the key area intersections and Figure 6b shows the projected 2042 peak-hour baseline traffic volumes at the key area intersections. These volumes assume buildout of the area street network, including the completion of Marksheffel Road between Vollmer Road and Black Forest Road, Briargate Parkway between Meridian Road and Black Forest Road, and Sterling Ranch Road between Marksheffel Road and Briargate Parkway.

Refer to FHU comment memorandum regarding these commitments.

The 2042 baseline traffic volumes are estimates by LSC, based on the traffic projections, the *Briargate-Stapleton Corridor Study (Draft)* by Wilson & Company dated December 9, 2021. This report indicates that the Pikes Peak Area Council of Governments' (PPACG) 2045 regional model was utilized as a basis for the projections. Previous reports completed in the area were also used to estimate the future baseline/background traffic (see Appendix Table 1).

Figure 6c shows the lane geometry, traffic control, and level of service at the key area intersections, based on the 2042 baseline volumes.

#### TRIP GENERATION

Refer to comments on Table 1 and Table 3 regarding trip generation and update this text accordingly.

The site-generated vehicle trips were estimated using the nationally-published trip-generation rates from *Trip Generation, 11th Edition*, 2021 by the Institute of Transportation Engineers (ITE). Table 3 shows the trip-generation estimates. The trip generation estimate is based on the average rates for all land uses. This may result in conservative estimate, especially at intersections well removed from the site. The average weekday trip generation rate for Land Use 210: Single-Family Detached Housing is 9.43 trips per dwelling units. The weekday trip generation rate based on the fitted curve equation for a development with 4,800 dwelling units would be 7.40 trips per dwelling unit. Using the fitted rate equation for 4,800 dwelling units instead of the average rate would result in a trip generation estimate of 9,729 fewer trips per day.

The total number of vehicle trips generated by the land uses has been reduced to account for the internal vehicle trips made within Sterling Ranch between land uses, without use of the external streets surrounding the site. Table 3 shows the number of internal trips assumed for each land use. Based on the number of residential dwelling units and the number of students at each school about 60 percent of the school related trips were assumed to be internal to the Sterling Ranch development. Based on the number of dwelling units and the size of the mixed-use parcels about seven percent of the “shopping plaza” trips were assumed to be internal to the Sterling Ranch development. The residential internal trips were then balanced with the school and shopping plaza internal trips.

The total number of vehicle trips generated has also been reduced to take into account the “pass by” phenomena. A pass-by trip is made by a motorist who would already be on the adjacent roadways regardless of the proposed development, but who stops in at the site while passing by. The motorist would then continue on his or her way to a final destination in the original direction. The pass-by percentages shown on Table 3 are from the Trip Generation Handbook - An ITE Proposed Recommended Practice, 3rd Edition, 2017 by ITE.

The Sterling Ranch Sketch Plan is projected to generate about 51,513 new external vehicle trips on the average weekday, with about half entering and half exiting the site during a 24-hour period. This is about 3,448 fewer daily trips than were estimated in the 2008 Master TIS. During the morning peak hour, which generally occurs for one hour between 6:30 and 8:30 a.m., about

1,185 vehicles would enter and 2,461 vehicles would exit the site. During the afternoon peak hour, which generally occurs for one hour between 4:15 and 6:15 p.m., about 3,189 vehicles would enter and 2,159 vehicles would exit the site.

### **TRIP DISTRIBUTION AND ASSIGNMENT**

The directional distribution of the site-generated traffic volumes on the street and roadway system serving the site is one of the most important factors in determining the site's traffic impacts. The distribution estimates for residential related traffic and non-residential related traffic are shown in Figures 7 and 8, respectively. The directional-distribution estimates are based on the following factors: the location of the site with respect to the Colorado Springs metropolitan area, the planned access system for the site, the street and roadway system serving the site, and the land uses proposed for the site.

When the distribution percentages (from Figures 7 and 8) are applied to the new, external trip-generation estimates (from Table 3), the resulting site-generated traffic volumes can be determined. The internal trips were assigned separately based on the location of the residential dwelling units and school sites within Sterling Ranch. The pass-by trips for each of the mixed-use parcels were assigned separately based on the projected 2042 baseline traffic volumes on the adjacent Arterial roadways.

Figure 9a shows the sum of the new external, internal, and pass-by site-generated traffic generated average weekday traffic volumes on key street segments within the study area. Figure 9b shows the sum of the new external, internal, and pass-by site-generated peak hour traffic at key study-area intersections. Appendix Figure 2 show the site-generated traffic volumes at the minor (Local) Sterling Ranch access points to the adjacent Arterial roadways.

### **2042 TOTAL TRAFFIC**

Figure 10a shows the projected 2042 total daily traffic volumes on key street segments and Figure 10b shows the projected 2042 total peak-hour traffic volumes at the key study-area intersections. These volumes are the sum of the 2042 baseline traffic volumes (from Figures 6a and 6b) and the site-generated traffic volumes (from Figures 9a and 9b).

Figure 10c shows the level of service analysis results for the key area intersections based on the projected 2042 total volumes. The figure also shows the general intersection lane geometry and intersection traffic control used in the analysis .

### **LEVEL OF SERVICE ANALYSIS**

The key area future signalized intersections have been analyzed to determine the projected intersection levels of service for 2042 baseline and total traffic scenarios for the morning and

afternoon peak-hour periods using Synchro. The key area future stop-sign-controlled and modern-roundabout-controlled intersections have been analyzed based on the unsignalized-intersection analysis procedures from the *Highway Capacity Manual 6th Edition*. Figures 6c and 10c show the level of service analysis results. The level of service reports are attached.

**Compile intersection improvements in a commitment table similar to Table 4 - Roadway Segment Improvements (typical all intersections in this section).**

**Intersection #1: Vollmer/Burgess**

The stop-sign-controlled intersection of Burgess/Vollmer is currently operating at LOS E for the eastbound approach and LOS F for the westbound approach during the afternoon peak hour. By 2042, it was assumed that this intersection would be reconstructed as a modern one-lane roundabout with a northbound right-turn bypass lane. As a modern roundabout it is projected to operate at LOS C or better for all approaches during the peak hours based on the projected 2042 total traffic volumes.

**Intersection #2: Vollmer/Arroya**

All movements at the stop-sign-controlled intersection of Vollmer/Arroya are projected to operate at LOS C or better during the peak hours based on the projected 2042 total traffic volumes.

**Intersection #3: Black Forest/Briargate**

The intersection of Black Forest/Briargate is projected to operate at an overall LOS D or better during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry show in Figure 10c. The northbound left-turn movement is projected to operate at LOS E during the morning peak hour based on the projected 2042 baseline and total traffic volumes.

**Intersection #4: Vollmer/Briargate**

The intersection of Vollmer/Briargate is projected to operate at an overall LOS C during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

**Intersection #5: Sterling Ranch/Briargate**

The intersection of Sterling Ranch/Briargate is projected to operate at an overall LOS C during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

### **Intersection #6: Banning Lewis/Briargate**

The intersection of Banning Lewis/Briargate is projected to operate at an overall LOS C during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c. The northbound left-turn movement is projected to operate at LOS E during the morning peak hour and LOS D during the afternoon peak hour and the westbound left-turn movement is projected to operate at LOS E during both the morning and afternoon peak hours.

### **Intersection #7: Dines/Vollmer**

The stop-sign controlled intersection of Dines/Vollmer is projected to operate at LOS D or better for all movements based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

### **Intersection #8: E-W Collector/Sterling Ranch**

The intersection of Sterling Ranch Road and the future east-west collector is projected to operate at LOS D or better for all movements as a stop-sign-controlled intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

### **Intersection #9: E-W Collector/Banning Lewis**

The intersection of Banning Lewis Parkway and the future east-west collector is projected to operate at an overall LOS B or better for all movements as a signal-controlled intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c. The northbound left-turn movement is projected to operate at LOS E during the morning peak hour.

### **Intersection #10: Dines/Sterling Ranch**

The intersection of Dines/Sterling Ranch is projected to operate at LOS D or better for all movements as a stop-sign controlled intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

### **Intersection #11: Black Forest/Research/Marksheffel**

The intersection of Black Forest/Research/Marksheffel is projected to operate at an overall LOS D or better during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c. The southbound

left-turn movement is projected to operate at LOS E during the morning peak hour based on the projected 2042 baseline and total traffic volumes.

#### **Intersection #12: Vollmer/Marksheffel**

The intersection of Vollmer/Marksheffel is projected to operate at an overall LOS C or better during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

#### **Intersection #13: Sterling Ranch/Marksheffel**

The intersection of Sterling Ranch/Marksheffel is projected to operate at an overall LOS C or better during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

#### **Intersection #14: Vollmer/Black Forest**

The intersection of Vollmer/Black Forest is projected to operate at an overall LOS C or better during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c.

#### **Intersection #15: Woodmen/Black Forest**

The intersection of Woodmen/Black Forest is projected to operate at an overall LOS D during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c. During the morning peak hour, all of the left-turn movements are projected to operate at LOS E. During the afternoon peak hour, the eastbound left-turn movement, eastbound through movement, northbound left-turn movement, and southbound left-turn movement are projected to operate at LOS E and the westbound left-turn movement is projected to operate at LOS F.

#### **Intersection #16: Woodmen/Marksheffel**

The intersection of Woodmen/Marksheffel is projected to operate at an overall LOS D during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry shown in Figure 10c. During the morning peak hour, the eastbound and northbound left-turn movements are projected to operate at LOS E. During the afternoon peak hour, all of the left-turn movements and the northbound through movement are projected to operate at LOS E.

### **Intersection #17: Woodmen/Banning Lewis**

The intersection of Woodmen/Banning Lewis is projected to operate at an overall LOS D during the peak hours as a signalized intersection based on the projected 2042 total traffic volumes shown in Figure 10band the lane geometry shown in Figure 10c. The eastbound, westbound, and southbound left-turn movements projected to operate at LOS E during the morning and afternoon peak hours. The northbound left-turn movement is projected to operate at LOS F during the morning and afternoon peak hours.

### **ROADWAY FUNCTIONAL CLASSIFICATIONS AND LANEAGE**

Figure 11 shows the recommended functional classifications and number of through lanes for the streets in the study area. Figure 11 also shows a comparison of the projected average weekday traffic volume (ADT) and the design ADT from the *ECM* for the key street segments in the vicinity of the site. All of the projected weekday traffic volumes are below the design ADT volumes.

### **MTCP ROADWAY CORRIDOR PRESERVATION**

Figure 11 is consistent with the *MTCP Corridor Preservation Plan (CPP)*. Aside from the 2040 classifications and number of lanes, the *MTCP CPP* shows Woodmen Road expansion to six lanes east of Banning Lewis Parkway and Vollmer Road expansion to four lanes north to Burgess Road. The *CPP* also shows Black Forest Road expansion to four lanes north of Briargate Parkway between 2040 and 2060.

### **AREA MTCP 2040 ROADWAY IMPROVEMENT PROJECTS**

The *El Paso County 2016 Major Transportation Corridors Plan Update* identified the following 2040 roadway improvement projects within the study area:

- C13: Vollmer Road from Marksheffel Road to Stapleton Drive as a Rural 4-Lane Minor Arterial;
- N5 Stapleton Drive [Briargate Parkway] from Towner Road to Black Forest Road as a 4-Lane Urban Principal Arterial;
- N12: Marksheffel Road from Woodman Road to Research Parkway as a 4-Lane Urban Principal Arterial; and
- M11: Vollmer Road Bicycle & Primary Regional Trail from Marksheffel Road to Shoup Road.

### **INTERSECTION APPROACH LANEAGE AND TRAFFIC CONTROL**

Figure 10c shows the recommended general intersection approach laneage including preliminary recommendations for left and or right auxiliary turn lanes (or dual lanes where shown). The figure also shows the anticipated traffic-control device that will likely be needed at each key

intersection (i.e., stop-sign control, traffic-signal control, roundabout-intersection control, etc.). These general, master-TIS-level recommendations are based primarily on the roadway corridor number of through lanes, the auxiliary turn lane thresholds in the *ECM*, and the 2042 capacity (LOS) analysis.

## **ROADWAY IMPROVEMENTS SUMMARY TABLE**

A list of the roadway segment improvements is presented in Table 4. The location of each roadway segment is identified in Figure 12.

## **MULTI-MODAL AND TRANSPORTATION DEMAND MANAGEMENT (TDM) OPPORTUNITIES**

The *El Paso County 2016 Major Transportation Corridors Plan Update* identified the following multi-modal improvement projects within the study area:

- M11: Bicycle & Primary Regional Trail along Vollmer Road between Marksheffel Road and Shoup Road.

The attached copy of the Sterling Ranch Sketch Plan Amendment shows the location of the planned major trails. This plan is consistent with the planned regional trail shown on Map 15: Bicycle and Pedestrian Network and Improvements from the 2016 *MTCP*.

Pedestrian plans will be part of preliminary plans. With urban development sidewalks will be required on all streets. A detached sidewalk will be provided along the east side of Vollmer Road adjacent to the development and along Sterling Ranch Road, Briargate Parkway and Marksheffel Road adjacent to the site. The county road cross sections in the *ECM* with shoulders generally accommodate bicycles. The section of Vollmer Road within the City of Colorado Springs (generally from Black Forest Road to Cowpoke Road) has existing bicycle lanes and future improvements on Vollmer Road should be consistent.

## **CONCLUSIONS AND RECOMMENDATIONS**

### **Trip Generation**

The Sterling Ranch Sketch Plan is projected to generate about 51,513 new external vehicle trips on the average weekday, with about half entering and half exiting the site during a 24-hour period. This is about 3,448 fewer daily trips than were estimated in the 2008 Master TIS. During the morning peak hour, which generally occurs for one hour between 6:30 and 8:30 a.m., about 1,185 vehicles would enter and 2,461 vehicles would exit the site. During the afternoon peak hour, which generally occurs for one hour between 4:15 and 6:15 p.m., about 3,189 vehicles would enter and 2,159 vehicles would exit the site.

### **Level of Service**

All of the intersections analyzed are projected to operate at an overall satisfactory level of service (LOS D or better) during the peak hours, based on the projected 2042 total traffic volumes shown in Figure 10b and the lane geometry and traffic control show in Figure 10c.

Some of the left-turn movements at the intersections of Black Forest/Briargate, Banning Lewis/Briargate, E-W Collector/Banning Lewis, Black Forest/Research/Marksheffel are projected to operate at LOS E during the peak hours. These movements have projected delays in the LOS E range simply because they arrive at the traffic signal at the beginning of the red phase at an intersection with many phases and a long cycle length. These movements would not be considered “failing” since their volume-to-capacity ratios are less than one. The justification is that to progress through traffic along an arterial corridor, the traffic signal offsets and left-turn phase times have been adjusted to favor the through band, which can result in higher delay for the left-turn movements, even though there is sufficient capacity for them.

**This paragraph outlines the need for progression analyses  
in accordance with the ECM. Please include in the TIS.**

Some of the left-turn movements and through movements at the intersections along Woodmen Road are projected to operate at LOS E or F during the peak hours. It may be necessary to provide additional laneage such as four through lanes on Woodmen Road or triple left-turn lanes to maintain an acceptable level of service in the future.

### **Recommended Improvements**

Figure 10c shows the general/preliminary laneage requirements for the key study area intersections and Table 4 shows a list of the roadway segment improvements. These recommendations are consistent with the recently published *Briargate-Stapleton Corridor Study (Draft)* by Wilson & Company dated December 9, 2021. Detailed lane geometry will be provided at the preliminary plan stage for individual developments. Generally, turn lanes, right-of-way and cross sections of street segments will need to conform to ECM criteria. Right of Way preservation may also be needed per the *MTCP Corridor Preservation Plan*.

\* \* \* \* \*

Please contact me if you have any questions regarding this report.

Sincerely,

LSC TRANSPORTATION CONSULTANTS, INC.

By Jeffrey C. Hodsdon, P.E.  
Principal

KDF:JCH:jas

Enclosures: Tables 1, 3, and 4  
Figures 1-12  
2008 TIS TAZ Map  
MTCP Maps  
Traffic Count Reports  
Level of Service Reports  
Crash History  
Sketch Plan Amendment

## **Tables 1, 3, and 4**

---



Sterling

Why is this referred to as mixed use here when it is shown as "Shopping Center" in Table 3?

Sterling Ranch Sketch Plan Amendment Traffic Technical Memorandum, October 30, 2018																
2008 Traffic Analysis Zone <sup>(1)</sup>	Sterling Ranch Updated Traffic Impact Analysis, June 5, 2008				Currently Proposed Sketch Plan Amendment				Change from 2008							
	Area (Acres)	Land Use	Quantity	Unit	Area (Acres)	Land Use	Quantity	Unit	Traffic Analysis Zone <sup>(2)</sup>	Name	Status	Land Use	Quantity	Unit	Quantity	Unit
1	14	Shopping Center	152	KSF <sup>(3)</sup>	11	Commercial	119.79	KSF	107	Mixed Use 11 Acres (South of Marksheffel)	Future	Mixed Use	120	KSF	-32.46	KSF
2	63	Single-Family Detached Housing	234	DU <sup>(4)</sup>	26	Single-Family Detached Housing	109	DU	6	Sterling Ranch Fil 2	Approved	Residential 3-5 DU/Ac	49	DU	3	DU
3	12	Elementary School	500	Students	19	Single-Family Detached Housing	177	DU	10	Sterling Ranch Fil 4 (north)	Short-Term Future		50	DU		-500
4	6	Apartment	89	DU	12	Elementary School	500	Students	5	Copper Chase	Under Review	Residential 5-8 DU/Ac	138	DU	82	DU
5	22	Single-Family Detached Housing	82	DU	5	Apartment	74	DU	16	Sterling Ranch Future Filing (SW Sterling Ranch/Dines)	Future	Residential 5-8 DU/Ac	82	DU	-89	DU
6	17	Single-Family Detached Housing	103	DU	62	Single-Family Detached Housing	259	DU	108	Industrial 5 Acres	Future	Industrial (Lift Station)	---	---	16	DU
7	101	Single-Family Detached Housing	611	DU	101	Single-Family Detached Housing	422	DU	10	Sterling Ranch Fil 4 (south)	Short-Term Future	Residential 3-5 DU/Ac	98	DU	-40	DU
8	17	Shopping Center	185	KSF	14	Shopping Center	152.46	KSF	7&8	Sterling Ranch Fil 3	Approved	Residential 3-5 DU/Ac	63	DU	-309	DU
9	35	Middle School/Junior High School	1000	students					1	Branding Iron Fil No. 1	Existing	Residential 3-5 DU/Ac	51	DU	-134.13	KSF
10	94	Single-Family Detached Housing	350	DU					2	Homestead Fil No. 1		Residential 3-5 DU/Ac	72	DU	233	DU
11	68	Single-Family Detached Housing	253	DU					4	Branding Iron Fil No. 2		Residential 3-5 DU/Ac	75	DU	100	Students
12	46	Single-Family Detached Housing	171	DU					3	Homestead Fil No. 2		Residential 3-5 DU/Ac	104	DU	-56	DU
13	70	Single-Family Detached Housing	260	DU					105	Mixed Use 14 Ac (SE Briargate/Vollmer)	Future	Mixed Use	51	KSF	-66	DU
17	72	Single-Family Detached Housing	268	DU					103	Sterling Ranch East Phase 1	Under Review	K-8 School	1100	students	600	Students
14	10	Elementary School	500	Students					22 & 26			Residential 3-5 DU/Ac	294	DU	-78	DU
15	32	Residential Condominium/Townhouse	298	DU					17, 23 & 24			Residential 3-5 DU/Ac	168	DU	100	Students
16	35	Apartment	521	DU					38			Residential 2 DU/Ac	19	DU	-52	DU
18	25	Shopping Center	272	KSF					102			Elementary School	600	students	-415	DU
19	91	Single-Family Detached Housing	34	DU					27, 28, 29, 31, 33 & 39	Sterling Ranch East Future Filings	Future	Residential 3-5 DU/Ac	603	DU	-192	KSF
20	314	Active Adult Residential	1,899	DU					39	Sterling Ranch East Future Filings	Future	Residential 2 DU/Ac	18	DU	367	DU
21	88	Single-Family Detached Housing	327	DU					104	Sterling Ranch East Future School	Future	Elementary School	600	students	431	DU
<b>TOTAL</b>														<b>TOTAL</b>		
<b>Figure 2?</b>				Residential	5,500	DU			18 & 37	Sterling Ranch East Phase 1	Under Review	Residential 3-5 DU/Ac	280	DU	4,800	DU
				Commercial	610	KSF			19	Four Square at Sterling Ranch	Under Review	Residential 5-8 DU/Ac	158	DU	251	KSF
				School	2,000	Students			30, 34, 35 & 36		Future	Residential 3-5 DU/Ac	871	DU	2,300	Students
Notes:														73	DU	
(1) See Appendix Figure 1 for 2008 Traffic Analysis Zones boundaries														74	DU	
(2) See Figure 3 for Traffic Analysis Zone boundaries														77	DU	
(3) KSF = thousand square feet of floor area														-103	DU	
(4) DU = dwelling unit														Oct-22		

It is very difficult to relate this table to Figure 2. Clarify.

Trip generation should be evaluated for each TAZ shown here.

Why is there no trip generation for this land use?

seems high

This land use code is only valid up to 150ksf, but the quantity shown here is 251ksf. Split up by TAZ.

There are multiple ES sites. Split up by TAZ.

Table 3 Sterling Ranch Sketch Plan Trip Generation															Raw ITE Trip Generation (Individual Driveway Trips)						Internal Trips (%)						Sterling Ranch Sketch Plan Area Internal Trip Calculations (Long-Term Scenario Only)						New External Trips Generated					
ITE Code	ITE Land Use	Quantity Unit	Trip Generation Rates <sup>(1)</sup>						Raw ITE Trip Generation (Individual Driveway Trips)						Internal Trips (%)						Total Internal Trips Generated						Total External Trips Generated						Passby <sup>(2)</sup> (%)	Daily				
			Daily		AM Peak Hour		PM Peak Hour		Daily		AM Peak Hour		PM Peak Hour		Daily		AM		PM		Daily		AM Peak Hour		PM Peak Hour		Daily		AM Peak Hour		PM Peak Hour		Passby <sup>(2)</sup> (%)	Daily				
			In	Out	In	Out	In	Out	In	Out	In	Out	In	Out	Daily	In	Out	In	Out	Daily	In	Out	In	Out	Daily	In	Out	In	Out	Daily	(%)							
<b>Trip Generation Estimate Based on the Currently Proposed Sterling Ranch Sketch Plan Amendment</b>																																						
<b>Non-Residential Land Uses</b>																																						
821 Shopping Plaza <sup>(3)</sup>	251 KSF <sup>(4)</sup>	67.52	1.07	0.66	2.54	2.65	16,948	269	165	638	664	7%	7%	7%	7%	7%	1,186	19	12	45	47	15,762	250	153	593	617	34%	10,403										
520 Elementary School	1,800 Students	2.27	0.40	0.34	0.07	0.09	4,086	719	613	132	156	60%	60%	30%	30%	60%	2,452	432	184	40	93	1,634	287	429	92	63	0%	1,634										
521 Middle School/Junior High	500 Students	2.10	0.36	0.31	0.07	0.08	1,050	181	154	36	39	60%	60%	30%	30%	60%	630	109	46	11	23	420	72	108	25	16	0%	420										
			Total Non-Residential Land Uses						22,084	1,169	932	807	859																	17,816	609	690	711	696	12,457			
<b>Residential Land Uses</b>																																						
210 Single-Family Detached Housing	4,054 DU <sup>(5)</sup>	0.43	0.18	0.52	0.59	0.35	38,229	738	2,100	2,401	1,410	10%	30%	24%	6%	6%	3,766	219	504	148	87	34,463	519	1,596	2,253	1,323	0%	34,463										
215 Single Family Attached Housing	146 DU <sup>(5)</sup>	7.20	0.15	0.33	0.32	0.25	1,051	22	48	47	36	10%	28%	25%	6%	6%	104	6	12	3	2	947	16	36	44	34	0%	947										
220 Multifamily Housing (Low-Rise)	600 DU	6.74	0.10	0.30	0.32	0.19	4,044	58	182	193	113	10%	30%	24%	6%	6%	398	17	44	12	7	3,646	41	138	181	106	0%	3,646										
			Total Residential Land Uses						43,324	817	2,331	2,641	1,559																17,816	690	609	696	711	39,056				
<b>Trip Generation Estimate From the Sterling Ranch Updated Traffic Impact Analysis, June 5, 2008</b>																																						
<b>Change in the Trip Generation Estimate</b>																																						
			Total						65,408	1,987	3,263	3,448	2,418																	8,536	802	802	259	259	51,513			
			70,399							1,680	3,100	3,714	2,728																	63,241	1,191	2,361	3,427	2,502	54,961			
			-4,991							307	163	-266	-310																		-6,369	-6	100	-238	-343	-3,448		
<b>Notes:</b>																																						
(1) Source: "Trip Generation, 11th Edition, 2021" by the Institute of Transportation Engineers (ITE)																																						
(2) Source: "Trip Generation Handbook - An ITE Proposed Recommended Practice 3rd Edition, September 2017" by ITE																																						
(3) Rates based on a shopping plaza with no supermarket																																						
(4) KSF = thousand square feet of floor area																																						
(5) DU = Dwelling Unit																																						
Source: LSC Transportation Consultants, Inc.																																						
Oct-22																																						

Split up by TAZ

There is no middle school in Table 1.  
Evaluate K-8 school instead.

Table 4

(page 1 of 2)

## Sterling Ranch Sketch Plan Amendment

## Roadway Segment Improvements

Segment ID <sup>(1)</sup> (See Figure 12 for map)	Improvement Description	Timing	Design ADT (vpd)	Projected 2042 ADT (vpd)	Define trigger: Responsibility
V1 northbound	Restriping the 38' of pavement for two 11' southbound lanes (remove the bike lane), a 12' northbound lane and a 4' outside paved shoulder along the east edge <sup>(2)</sup> Removal of bike lane is not appropriate. (Pending City Traffic Engineering Approval) Consider other improvement option(s).	With Sterling Ranch Filing No. 4	5,500 (Directional northbound)	13,080	Sterling Ranch
V1 southbound			10,000 (Directional southbound)		
V1	Improve Vollmer Road between Dry Needle Place and the Sterling Ranch south boundary to a standard 4-Lane Urban Minor Arterial Cross Section (Add a second northbound through lane and painted center median) <sup>(2)</sup>	Intermediate-Term Future	20,000		Sterling Ranch, if necessary prior to construction by Others
V2	Improve Vollmer Road between the Sterling Ranch south boundary to Lochwinnoch Lane/Sterling property boundary to a standard 4-Lane Urban Minor Arterial Cross Section <sup>(2)</sup>	Short-Term Future (With Sterling Ranch Fil No. 2 Or Sterling Ranch Phase 2)	20,000 (Note: Existing Capacity 8,000 <sup>(3)</sup> )	14,385	Sterling Ranch
V3	Short Term: Improve Vollmer Road from Lochwinnoch Lane to Sterling Ranch boundary (northeast of Glider Loop) to provide 36' of pavement (existing pavement 1 approx. 23.38') and stripe for one through lane and plus a 6' paved, striped outside shoulder in each direction <sup>(2)</sup>	Short-Term Future (With Homestead North)	11,000 (Note: Existing Capacity 8,000)	15,040	Sterling Ranch
	Long Term: Improve Vollmer Road from Lochwinnoch Lane to Sterling Ranch boundary (northeast of Glider Loop) to a standard 4-Lane Urban Minor Arterial Cross Section <sup>(2)</sup>	Long-Term Future	20,000		By others - pursuant to the recent development agreement between Sterling Ranch and EPC.
V4	Improve Vollmer Road from Sterling Ranch boundary (northeast of Glider Loop) to Briargate Parkway to a standard 4-Lane Urban Minor Arterial Cross Section <sup>(2)</sup>	Short-Term Future— May 2024 Updated 10/15/2022 - Sections V4, V5, V6 to be constructed by May 2024 (prior note: With Homestead North Filing 1)	20,000	14,495	Sterling Ranch
V5	Improve Vollmer Road from Briargate Parkway to Jane Kirkham Drive to a standard 4-Lane Urban Minor Arterial Cross Section <sup>(2)</sup>	Short-Term Future— May 2024 Updated 10/15/2022 - Sections V4, V5, v6 to be constructed by May 2024 (prior note: prior note: With Homestead North Filing 1)	20,000	11,690	Sterling Ranch
V6	Improve Vollmer Road from Jane Kirkham Drive to Sam Bass Drive to a standard 4-Lane Urban Minor Arterial Cross Section <sup>(2)</sup>	Short-Term Future— May 2024 Updated 10/15/2022 - Sections V4, V5, v6 to be constructed by May 2024 (prior note: prior note: With Homestead North Filing 2)	20,000	11,425	Sterling Ranch
V7	Improve Vollmer Road between Sam Bass Drive and Poco Road to a 4-lane Urban Minor Arterial but with necessary lane transitions, redirect tapers, etc. south of Poco to adequately transition between the 4-Lane Urban Minor Arterial Cross Section and the 2-Lane Rural Arterial Cross Section north of Poco Road.	Short-Term Future – May 2024 Updated 10/15/2022 - Sections V4, V5, v6 to be constructed by May 2024 (prior note: With Homestead North Filing 3)	20,000	9,920	Sterling Ranch
V8	Improve Vollmer Road from Poco Road to Shoup Road to a Rural 2-Lane Arterial Cross Section <sup>(2)</sup>	Long-Term Future	10,000	8,760	El Paso County Project ID U-12

Part 1/2 of this table (see Part 2 on next page)

## Notes:

(1) See Figure 10

(2) Adequate transition/redirect tapers would be needed between the various cross sections on Vollmer Road. Based on the criteria contained in Table 2-29 of the *El Paso Engineering Criteria Manual* an appropriate taper ratio for a roadway with a design speed of 40 mile per hour is 20:1

(3) Source: Table 20 Road Impact Fee Study Updated November 16, 2016

Source: LSC Transportation Consultants, Inc. (October 25, 2022)

Sterling Ranch with potential  
County assistance with ROW  
acquisition

Table 4

(page 2 of 2)

## Sterling Ranch Sketch Plan Amendment

## Roadway Segment Improvements

Segment ID <sup>(1)</sup> (See Figure 12 for map)	Improvement Description	Timing	Design ADT (vpd)	Projected 2042 ADT (vpd)	Responsibility
SR1	Construct Sterling Ranch Road as an Urban Non-Residential Collector from Marksheffel Road to Dines Boulevard	Short Term - with Sterling Ranch Fil No. 2	20,000	14,620	Sterling Ranch
SR2	Construct Sterling Ranch Road as an Urban Non-Residential Collector from Dines Boulevard to Briargate Parkway	Short-Term	20,000	10,055	Sterling Ranch
SR3	Construct Sterling Ranch Road as an Urban Collector from Briargate Parkway to Vancouver Street.	Short Term	10,000	9,045	Sterling Ranch
SR4	Construct Sterling Ranch Road from Vancouver Street north to Arroya (or ultimate north terminus)	Long-Term Future	10,000	4,260	Sterling Ranch
M1	Construct Marksheffel Road as an Urban Principal Arterial to City of Colorado Springs standards in 107' of right-of-way between Vollmer Road and Sterling Ranch Road	Updated 10/15/2022: to be completed by the end of 2022 (prior note: With Sterling Ranch Fil No. 2)	40,000	23,790	Sterling Ranch
M2	Construct Marksheffel Road as an Urban Principal Arterial to City of Colorado Springs standards in 107' of right-of-way between Sterling Ranch Road and the south boundary of the Sterling Ranch Master Plan Area. <b>10/16/2022 NOTE: With the completion of M2 in 2023, the connection between Vollmer and Woodmen Road (via M3) will be completed.</b>	Short Term Updated 10/15/2022: to be completed in 2023 (prior note: With Sterling Ranch Phase 2)	40,000	29,525	Sterling Ranch
M3	Construct Marksheffel Road between the south boundary of the Sterling Ranch Master Plan Area and Woodmen Road (Note this segment is located within the City of Colorado Springs) <b>10/16/2022 NOTE: With the completion of M2 in 2023, the connection between Vollmer and Woodmen Road (via M3) will be completed.</b>	Updated 10/15/2022: <u>Completed</u> (by Others)	40,000	24,525	Others (Completed)
M4	Construct Marksheffel Road between Black Forest Road and Vollmer Road	Long-Term Future	40,000	27,910	Others
B1	Construct the south half section of Briargate Pkwy (4-Lane Principal Arterial) between Vollmer Road and Wheatland Drive [now full section by 2023]	Short-Term Future Updated 10/15/2022: Full section to be completed in 2023 with Homestead at Sterling Ranch Filing No. 1 (prior note: With Homestead at Sterling Ranch Fil 2)	20,000	24,685	Sterling Ranch
	Construct the north half section of Briargate Pkwy (4-Lane Principal Arterial) between Vollmer Road and Wheatland Drive [now full section by 2023]	Short-Term Future Updated 10/15/2022: Full section to be completed in 2023 with Homestead at Sterling Ranch Filing No. 1 (prior note: Long-Term Future)	40,000		Sterling Ranch
B2	Construct Briargate Pkwy (full section) as a 4-Lane Principal Arterial between Wheatland Dr and Sterling Ranch Road	Short-Term Future Updated 10/15/2022: Full section to be completed in 2023 or Spring 2024 (prior note: Long-Term Future)	40,000	26,310	Sterling Ranch
B3	Construct Briargate Pkwy as a 4-Lane Principal Arterial between Sterling Ranch Road and Banning Lewis Parkway	Intermediate Term	40,000	20,935	Sterling Ranch
B4	Construct Stapleton Road as a 4-Lane Principal Arterial between Banning Lewis Parkway and Meridian Road (including upgrade of existing rural two-lane segment between Towner and Meridian)	Long-Term Future	40,000	17,945	Others
B5	Construct Briargate Pkwy as a 4-Lane Principal Arterial between its current terminus and Black Forest Road and between Black Forest Road and Vollmer Road	Long-Term Future	40,000	23,320	Others
BL1	Construct Banning Lewis Parkway as a 4-Lane Principal Arterial between the south Sterling Ranch boundary and Briargate Pkwy	Long-Term Future	40,000	20,295	Financial assurances for half-section, Sterling Ranch half-section or full-section w/ cost recovery
BL2	Construct Banning Lewis Parkway as a 4-Lane Principal Arterial between Woodmen Road and the south Sterling Ranch boundary (Note this segment will be located within the City of Colorado Springs)	Long-Term Future	40,000	28,480	Others
W1	Widen Woodmen Road from 4-lane to 6-lane section from Powers Boulevard to US 24	Long-Term Future	72,000	66,690	Others

## Part 2/2 of this table

## Notes:

(1) See Figure 10

(2) Adequate transition/redirect tapers would be needed between the various cross sections on Vollmer Road. Based on the criteria contained in Table 2-29 of the *El Paso Engineering Criteria Manual* an appropriate taper ratio for a roadway with a design speed of 40 mile per hour is 20:1

(3) Source: Table 20 Road Impact Fee Study Updated November 16, 2016

Source: LSC Transportation Consultants, Inc. (October 25, 2022)

## **Figures 1-12**

---








Figure 1

Vicinity

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)









Figure 4





## LEGEND:


**XXX** = Average Weekday Traffic (vehicles per day)

Counts are estimates by LSC based on factored turning movement count data shown on Figure 5b


Figure 5a

# Existing ADTs

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)



  
Not to scale



#### LEGEND:

$$\frac{A}{B} = \frac{\text{AM Individual Movement Peak-Hour Level of Service}}{\text{PM Individual Movement Peak-Hour Level of Service}}$$

$$\frac{C}{D} = \frac{\text{AM Entire Intersection Peak-Hour Level of Service}}{\text{PM Entire Intersection Peak-Hour Level of Service}}$$

▪ = Stop Sign

 = Traffic Signal





Figure 5c  
**Existing Lane Geometry,  
Traffic Control, and Level of Service**



It is unclear how many of these roadway segments will be built in the baseline scenario since many segments will be funded by Sterling Ranch per Table 4. (typical all baseline figures)


## LEGEND:


**XXX** = Average Weekday Traffic (AWT) (vehicles per day)

# 2042 Baseline Average Weekday Traffic

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)










Figure 7  
**Buildout Long-Term Directional Distribution  
of Residential-Generated Traffic**

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)



Not to scale





Figure 8

## Buildout Long-Term Directional Distribution of Non-Residential-Generated Traffic

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)



Not to scale




LEGEND:

XXX = Average Weekday Traffic (AWT)(vehicles per day)




Figure 9a  
Site-Generated Average Weekday Traffic

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)






Not to scale



LEGEND:

XXX = Average Weekday Traffic (AWT)(vehicles per day)

Figure 10a  
2042 Total Average Weekday Traffic  
Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)




Not to scale

Figure 10b

2042 Total Peak-Hour Traffic

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)





Not to scale

#### LEGEND:

$\frac{XX,XXX}{XX,XXX}$  = Projected Average Daily Traffic  
Design Average Daily Traffic

- 6-lane urban expressway
- 4-lane urban principal arterial
- 4-lane urban minor arterial
- - - 2-lane rural minor arterial
- urban non-residential collector
- - - urban residential collector







Figure 11

## Proposed Roadway Functional Classification

Sterling Ranch Sketch Plan - 2022 Amendment (LSC# S224440)







# 2008 TIS TAZ Map

---


The next page is included in the previous section., Can  
this cover page and the duplicate figure be removed?





Figure 3  
LSC # 074230


Traffic Analysis Zones  
Sterling Ranch



# MTCP Maps


---






Map 14: 2040 Roadway Plan (Classification and Lanes)


# Map 17: 2060 Corridor Preservation





## **Map 13: Roadway Improvement Projects**

## Call out site on this figure



Map 15: Bicycle and Pedestrian Network and Improvements

# Traffic Counts

---



# LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304  
 Colorado Springs, CO 80909  
 719-633-2868

File Name : Vollmer Rd - Burgess Rd AM  
 Site Code : S224440  
 Start Date : 7/28/2022  
 Page No : 1

## Groups Printed- Unshifted


Start Time	Vollmer Rd Southbound					Burgess Rd Westbound					Vollmer Rd Northbound					Burgess Rd Eastbound					Int. Total
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	
06:30	0	15	5	0	20	19	47	10	0	76	4	5	1	0	10	0	6	0	0	6	112
06:45	1	15	4	0	20	17	35	13	0	65	5	5	1	0	11	3	6	1	0	10	106
Total	1	30	9	0	40	36	82	23	0	141	9	10	2	0	21	3	12	1	0	16	218
07:00	2	20	9	0	31	15	51	14	0	80	6	9	1	0	16	2	10	0	0	12	139
07:15	2	14	8	0	24	21	57	12	0	90	4	11	5	0	20	1	8	0	0	9	143
07:30	2	17	7	0	26	19	58	12	0	89	4	19	5	0	28	3	13	1	0	17	160
07:45	3	16	10	0	29	17	51	8	0	76	9	11	3	0	23	0	8	2	0	10	138
Total	9	67	34	0	110	72	217	46	0	335	23	50	14	0	87	6	39	3	0	48	580
08:00	3	22	5	0	30	17	61	12	0	90	7	8	4	0	19	6	14	0	0	20	159
08:15	2	16	6	0	24	7	36	15	0	58	13	16	3	0	32	3	9	1	0	13	127
Grand Total	15	135	54	0	204	132	396	96	0	624	52	84	23	0	159	18	74	5	0	97	1084
Apprch %	7.4	66.2	26.5	0		21.2	63.5	15.4	0		32.7	52.8	14.5	0		18.6	76.3	5.2	0		
Total %	1.4	12.5	5	0	18.8	12.2	36.5	8.9	0	57.6	4.8	7.7	2.1	0	14.7	1.7	6.8	0.5	0	8.9	

# LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304  
 Colorado Springs, CO 80909  
 719-633-2868

File Name : Vollmer Rd - Burgess Rd AM  
 Site Code : S224440  
 Start Date : 7/28/2022  
 Page No : 2

Start Time	Vollmer Rd Southbound					Burgess Rd Westbound					Vollmer Rd Northbound					Burgess Rd Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
<b>Peak Hour Analysis From 6:30:00 AM to 8:15:00 AM - Peak 1 of 1</b>																					
<b>Peak Hour for Entire Intersection Begins at 7:15:00 AM</b>																					
7:15:00 AM	2	14	8	0	24	21	57	12	0	90	4	11	5	0	20	1	8	0	0	9	143
7:30:00 AM	2	17	7	0	26	19	58	12	0	89	4	19	5	0	28	3	13	1	0	17	160
7:45:00 AM	3	16	10	0	29	17	51	8	0	76	9	11	3	0	23	0	8	2	0	10	138
8:00:00 AM	3	22	5	0	30	17	61	12	0	90	7	8	4	0	19	6	14	0	0	20	159
Total Volume	10	69	30	0	109	74	227	44	0	345	24	49	17	0	90	10	43	3	0	56	600
% App. Total	9.2	63.3	27.5	0		21.4	65.8	12.8	0		26.7	54.4	18.9	0		17.9	76.8	5.4	0		
PHF	.833	.784	.750	.000	.908	.881	.930	.917	.000	.958	.667	.645	.850	.000	.804	.417	.768	.375	.000	.700	.938




# LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304  
 Colorado Springs, CO 80909  
 719-633-2868

File Name : Vollmer Rd - Burgess Rd PM  
 Site Code : S224440  
 Start Date : 7/27/2022  
 Page No : 1

## Groups Printed- Unshifted

	Vollmer Rd Southbound					Burgess Rd Westbound					Vollmer Rd Northbound					Burgess Rd Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
16:00	2	19	22	0	43	7	21	7	0	35	9	17	6	0	32	3	37	3	0	43	153
16:15	5	13	29	0	47	6	23	11	0	40	18	11	8	0	37	4	37	5	0	46	170
16:30	2	19	31	0	52	10	30	9	0	49	12	19	4	0	35	5	46	3	0	54	190
16:45	1	8	20	0	29	8	33	17	0	58	16	14	5	0	35	1	65	0	0	66	188
Total	10	59	102	0	171	31	107	44	0	182	55	61	23	0	139	13	185	11	0	209	701
17:00	5	16	28	0	49	14	29	9	0	52	16	18	3	0	37	1	56	3	0	60	198
17:15	1	25	38	0	64	11	31	10	0	52	18	18	4	0	40	5	77	3	0	85	241
17:30	1	10	30	0	41	11	21	19	0	51	13	23	4	0	40	5	46	1	0	52	184
17:45	6	14	19	0	39	11	23	5	0	39	14	16	1	0	31	6	43	6	0	55	164
Total	13	65	115	0	193	47	104	43	0	194	61	75	12	0	148	17	222	13	0	252	787
Grand Total	23	124	217	0	364	78	211	87	0	376	116	136	35	0	287	30	407	24	0	461	1488
Apprch %	6.3	34.1	59.6	0		20.7	56.1	23.1	0		40.4	47.4	12.2	0		6.5	88.3	5.2	0		
Total %	1.5	8.3	14.6	0	24.5	5.2	14.2	5.8	0	25.3	7.8	9.1	2.4	0	19.3	2	27.4	1.6	0	31	




# LSC Transportation Consultants, Inc.

2504 E. Pikes Peak Ave, Suite 304  
 Colorado Springs, CO 80909  
 719-633-2868

File Name : Vollmer Rd - Burgess Rd PM  
 Site Code : S224440  
 Start Date : 7/27/2022  
 Page No : 2

Start Time	Vollmer Rd Southbound					Burgess Rd Westbound					Vollmer Rd Northbound					Burgess Rd Eastbound					
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 4:00:00 PM to 5:45:00 PM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 4:30:00 PM																					
4:30:00 PM	2	19	31	0	52	10	30	9	0	49	12	19	4	0	35	5	46	3	0	54	190
4:45:00 PM	1	8	20	0	29	8	33	17	0	58	16	14	5	0	35	1	65	0	0	66	188
5:00:00 PM	5	16	28	0	49	14	29	9	0	52	16	18	3	0	37	1	56	3	0	60	198
5:15:00 PM	1	25	38	0	64	11	31	10	0	52	18	18	4	0	40	5	77	3	0	85	241
Total Volume	9	68	117	0	194	43	123	45	0	211	62	69	16	0	147	12	244	9	0	265	817
% App. Total	4.6	35.1	60.3	0		20.4	58.3	21.3	0		42.2	46.9	10.9	0		4.5	92.1	3.4	0		
PHF	.450	.680	.770	.000	.758	.768	.932	.662	.000	.909	.861	.908	.800	.000	.919	.600	.792	.750	.000	.779	.848




**Location:** 1 Black Forest Road & Vollmer Road AM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 07:15 AM - 08:15 AM

**Peak 15-Minutes:** 07:45 AM - 08:00 AM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Vollmer Road Eastbound				Vollmer Road Westbound				Black Forest Road Northbound				Black Forest Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		West	East	South	North	
7:00 AM	0	0	0	0	0	88	0	0	0	0	46	75	0	2	85	0	296	1,630	0	0	0	0
7:15 AM	0	0	0	0	0	88	0	2	0	0	77	92	0	0	77	0	336	1,708	0	0	0	0
7:30 AM	0	0	0	0	0	118	0	0	0	0	86	162	0	0	104	0	470	1,708	0	0	0	0
7:45 AM	0	0	0	0	0	149	0	1	0	0	98	140	0	2	138	0	528	1,587	0	0	0	0
8:00 AM	0	0	0	0	0	139	0	0	0	0	78	70	0	1	86	0	374	1,416	0	0	0	0
8:15 AM	0	0	0	0	0	105	0	0	0	0	71	78	0	1	81	0	336	0	0	0	0	0
8:30 AM	0	0	0	0	0	111	0	0	0	0	63	81	0	0	94	0	349	0	0	0	0	0
8:45 AM	0	0	0	0	0	97	0	0	0	0	84	97	0	1	78	0	357	0	0	0	0	0
Count Total	0	0	0	0	0	895	0	3	0	0	603	795	0	7	743	0	3,046	0	0	0	0	0
Peak Hour	0	0	0	0	0	494	0	3	0	0	339	464	0	3	405	0	1,708	0	0	0	0	0


**Location:** 2 Vollmer Road & Cowpoke Road AM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 07:15 AM - 08:15 AM

**Peak 15-Minutes:** 07:45 AM - 08:00 AM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Cowpoke Road Eastbound				Cowpoke Road Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings						
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	West	East	South	North			
7:00 AM	0	1	1	0	0	6	7	1	0	0	5	52	5	0	0	0	36	6	120	851	0	0	0	0
7:15 AM	0	0	2	2	0	8	16	0	0	0	33	47	5	0	0	0	46	9	168	919	0	0	1	0
7:30 AM	0	3	5	5	0	11	15	1	0	0	73	57	2	0	0	0	50	16	238	907	0	0	0	1
7:45 AM	0	15	14	41	0	8	21	5	0	78	62	3	0	0	1	60	17	325	823	1	0	1	3	
8:00 AM	0	6	3	11	0	12	11	2	0	20	42	3	0	0	2	66	10	188	667	0	0	0	0	
8:15 AM	0	5	2	8	0	7	10	0	0	0	19	34	8	0	2	54	7	156	0	0	0	0	0	
8:30 AM	0	3	4	1	0	13	6	1	0	0	3	51	5	0	2	59	6	154	1	0	1	0	0	
8:45 AM	0	4	1	3	0	14	6	1	0	23	50	7	0	1	48	11	169	0	0	0	0	0		
Count Total	0	37	32	71	0	79	92	11	0	254	395	38	0	8	419	82	1,518	2	0	3	4	4		
Peak Hour	0	24	24	59	0	39	63	8	0	204	208	13	0	3	222	52	919	1	0	2	4			


**Location:** 3 Vollmer Road & Tahiti Drive AM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 07:45 AM - 08:45 AM

**Peak 15-Minutes:** 07:45 AM - 08:00 AM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Tahiti Drive Eastbound				Tahiti Drive Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		West	East	South	North	
7:00 AM	0	0	0	0	0	0	0	0	0	0	0	42	0	0	0	30	0	72	374	0	0	0
7:15 AM	0	0	0	0	0	0	0	0	0	0	0	33	0	0	0	47	0	80	400	0	0	0
7:30 AM	0	0	0	0	0	0	0	0	0	0	0	41	0	0	0	55	0	96	400	0	0	0
7:45 AM	0	0	0	0	0	0	0	0	0	0	0	75	0	0	0	51	0	126	407	0	0	0
8:00 AM	0	0	0	0	0	0	0	0	0	0	0	37	0	0	0	61	0	98	375	0	0	0
8:15 AM	0	0	0	0	0	0	0	0	0	0	0	34	0	0	0	46	0	80	0	0	0	0
8:30 AM	0	0	0	0	0	0	0	0	0	0	0	47	0	0	0	56	0	103	0	0	0	0
8:45 AM	0	0	0	0	0	0	0	0	0	0	0	41	0	0	0	53	0	94	0	0	0	0
Count Total	0	0	0	0	0	0	0	0	0	0	0	350	0	0	0	399	0	749	0	0	0	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	193	0	0	0	214	0	407	0	0	0	0


**Location:** 4 Vollmer Road & Lochwinnoch Lane AM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 07:45 AM - 08:45 AM

**Peak 15-Minutes:** 07:45 AM - 08:00 AM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Lochwinnoch Lane				Vollmer Road				Vollmer Road				Pedestrian Crossings						
	Eastbound		Westbound		Northbound		Southbound		Hour	West	East	South	North						
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total						
7:00 AM	0	0	0	2	0	1	0	0	0	0	0	28	0	74	389	0 0 0 0			
7:15 AM	0	0	0	3	0	0	0	0	0	1	33	2	0	1	84	413	0 0 0 0		
7:30 AM	0	0	0	1	0	2	0	0	0	1	40	3	0	1	57	1	106	416	0 0 0 0
7:45 AM	0	0	0	2	0	2	0	1	0	0	68	7	0	1	44	0	125	417	0 0 0 0
8:00 AM	0	1	0	1	0	4	0	0	2	1	33	3	0	0	52	1	98	388	0 0 0 0
8:15 AM	0	2	0	3	0	1	0	2	0	5	26	3	0	1	42	2	87		0 0 0 0
8:30 AM	0	2	0	5	0	3	0	2	0	4	41	1	0	1	46	2	107		0 0 0 0
8:45 AM	0	0	0	5	0	0	0	0	0	0	41	1	0	1	48	0	96		0 0 0 0
Count Total	0	5	0	22	0	13	0	5	2	12	325	20	0	6	360	7	777		0 0 0 0
Peak Hour	0	5	0	11	0	10	0	5	2	10	168	14	0	3	184	5	417		0 0 0 0


**Location:** 5 Vollmer Road & Dines Blvd AM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 07:15 AM - 08:15 AM

**Peak 15-Minutes:** 07:45 AM - 08:00 AM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Dines Blvd Eastbound				Dines Blvd Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	West	East	South	North	
7:00 AM	0	0	0	0	0	11	0	1	0	0	25	14	0	2	16	0	69	370	0	0	0	0
7:15 AM	0	0	0	0	0	15	0	3	0	0	22	13	0	1	29	0	83	389	0	0	0	0
7:30 AM	0	0	0	0	0	21	0	5	0	0	27	13	0	0	39	0	105	381	0	0	0	0
7:45 AM	0	0	0	0	0	11	0	6	0	0	38	21	0	1	36	0	113	375	0	0	0	0
8:00 AM	0	0	0	0	0	23	0	3	0	0	25	7	0	1	29	0	88	348	0	0	0	0
8:15 AM	0	0	0	0	0	18	0	2	0	0	23	8	0	0	24	0	75	0	0	0	0	0
8:30 AM	0	0	0	0	0	23	0	1	1	0	28	13	1	2	30	0	99	0	0	0	0	0
8:45 AM	0	0	0	0	0	15	0	4	0	0	31	8	0	0	28	0	86	0	0	0	0	0
Count Total	0	0	0	0	0	137	0	25	1	0	219	97	1	7	231	0	718	0	0	0	0	0
Peak Hour	0	0	0	0	0	70	0	17	0	0	112	54	0	3	133	0	389	0	0	0	0	0


**Location:** 6 Vollmer Road & Poco Road AM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 07:15 AM - 08:15 AM

**Peak 15-Minutes:** 07:45 AM - 08:00 AM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Poco Road Eastbound				Poco Road Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		West	East	South	North	
7:00 AM	0	0	0	0	0	0	0	0	0	0	10	15	0	1	20	0	46	264	0	0	0	0
7:15 AM	0	0	0	0	0	1	0	2	0	0	18	8	0	2	27	0	58	279	0	0	0	0
7:30 AM	0	0	0	0	0	1	0	2	0	1	26	8	0	2	36	0	76	273	0	0	0	0
7:45 AM	0	0	0	0	0	4	0	0	0	0	34	9	0	4	33	0	84	265	0	0	0	0
8:00 AM	0	0	0	0	0	0	1	0	0	0	18	10	0	0	32	0	61	245	0	0	0	0
8:15 AM	0	0	0	0	0	1	0	1	0	0	24	3	0	0	23	0	52		0	0	0	0
8:30 AM	0	0	0	2	0	3	0	2	0	1	24	6	0	1	29	0	68		0	0	0	0
8:45 AM	0	2	0	1	0	1	0	0	0	1	23	10	0	0	26	0	64		0	0	0	0
Count Total	0	2	0	3	0	11	1	7	0	3	177	69	0	10	226	0	509		0	0	0	0
Peak Hour	0	0	0	0	0	6	1	4	0	1	96	35	0	8	128	0	279		0	0	0	0



(303) 216-2439  
[www.alltrafficdata.net](http://www.alltrafficdata.net)


**Location:** 1 Black Forest Road & Vollmer Road PM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 04:45 PM - 05:45 PM

**Peak 15-Minutes:** 05:30 PM - 05:45 PM

## Peak Hour - All Vehicles



## **Peak Hour - Pedestrians/Bicycles on Crosswalk**



Note: Total study counts contained in parentheses.

## Traffic Counts

Interval Start Time	Vollmer Road Eastbound				Vollmer Road Westbound				Black Forest Road Northbound				Black Forest Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	West	East	South	North	
4:00 PM	0	0	0	0	0	120	0	0	0	0	102	140	0	1	140	0	503	1,927	0	0	0	0
4:15 PM	0	0	0	0	0	104	0	2	0	0	100	147	0	2	107	0	462	1,904	0	0	0	0
4:30 PM	0	0	0	0	0	139	0	2	0	0	100	135	0	1	116	0	493	1,955	0	0	0	0
4:45 PM	0	0	0	0	0	94	0	5	0	0	105	152	0	2	111	0	469	1,983	0	0	0	0
5:00 PM	0	0	0	0	0	113	0	1	0	0	108	137	0	1	120	0	480	1,975	0	0	0	0
5:15 PM	0	0	0	0	0	108	0	1	0	0	103	154	0	3	144	0	513		0	0	0	0
5:30 PM	0	0	0	0	0	136	0	3	0	0	97	148	0	2	135	0	521		0	0	0	0
5:45 PM	0	0	0	0	0	92	0	0	0	0	118	143	0	2	106	0	461		0	0	0	0
Count Total	0	0	0	0	0	906	0	14	0	0	833	1,156	0	14	979	0	3,902		0	0	0	0
Peak Hour	0	0	0	0	0	451	0	10	0	0	413	591	0	8	510	0	1,983		0	0	0	0


**Location:** 2 Vollmer Road & Cowpoke Road PM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 04:00 PM - 05:00 PM

**Peak 15-Minutes:** 04:00 PM - 04:15 PM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Cowpoke Road Eastbound				Cowpoke Road Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		Total	West	East	South	North
4:00 PM	0	8	1	7	0	7	5	1	0	12	64	20	0	3	91	4	223	818	0	0	0	0
4:15 PM	0	6	4	6	0	9	5	1	0	11	70	15	0	2	51	5	185	783	0	0	0	0
4:30 PM	0	4	7	8	0	5	6	0	0	4	74	10	0	0	76	2	196	762	0	0	0	0
4:45 PM	0	7	11	15	0	14	5	0	0	13	71	7	0	2	65	4	214	771	0	0	0	0
5:00 PM	0	5	8	3	0	9	4	1	0	12	61	14	0	2	63	6	188	725	0	0	3	0
5:15 PM	0	5	4	4	0	11	4	1	0	8	59	7	0	3	53	5	164	0	0	0	0	0
5:30 PM	0	5	9	9	0	11	6	0	0	16	62	10	0	1	68	8	205	0	0	0	0	0
5:45 PM	0	7	5	4	0	8	5	1	0	9	58	17	0	0	49	5	168	0	0	0	0	0
Count Total	0	47	49	56	0	74	40	5	0	85	519	100	0	13	516	39	1,543	0	0	3	0	0
Peak Hour	0	25	23	36	0	35	21	2	0	40	279	52	0	7	283	15	818	0	0	0	0	0


**Location:** 3 Vollmer Road & Tahiti Drive PM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 04:00 PM - 05:00 PM

**Peak 15-Minutes:** 04:00 PM - 04:15 PM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Tahiti Drive Eastbound				Tahiti Drive Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		West	East	South	North	
4:00 PM	0	0	0	0	0	0	0	0	0	0	0	66	0	0	0	73	1	140	503	0	0	0
4:15 PM	0	0	0	0	0	0	0	0	0	0	0	68	0	0	0	52	0	120	467	0	0	0
4:30 PM	0	0	0	0	0	0	0	0	0	0	0	49	0	0	0	63	0	112	463	0	0	0
4:45 PM	0	0	0	0	0	0	0	0	0	0	0	80	0	0	0	51	0	131	453	0	0	0
5:00 PM	0	0	0	0	0	0	0	0	0	0	0	55	0	0	0	49	0	104	428	0	0	0
5:15 PM	0	0	0	0	0	0	0	0	0	0	0	62	0	0	0	54	0	116	0	0	0	0
5:30 PM	0	0	0	0	0	0	0	0	0	0	0	54	0	0	0	48	0	102	0	0	0	0
5:45 PM	0	0	0	0	0	0	0	0	0	0	0	61	0	0	0	45	0	106	0	0	0	0
Count Total	0	0	0	0	0	0	0	0	0	0	0	495	0	0	0	435	1	931	0	0	0	0
Peak Hour	0	0	0	0	0	0	0	0	0	0	0	263	0	0	0	239	1	503	0	0	0	0




**Location:** 4 Vollmer Road & Lochwinnoch Lane PM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 04:00 PM - 05:00 PM

**Peak 15-Minutes:** 04:00 PM - 04:15 PM

## **Peak Hour - All Vehicles**



## **Peak Hour - Pedestrians/Bicycles on Crosswalk**



Note: Total study counts contained in parentheses.

## Traffic Counts

Interval Start Time	Lochwinnoch Lane Eastbound				Lochwinnoch Lane Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings					
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		Total	West	East	South	North	
4:00 PM	0	4	0	4	0	2	0	0	0	0	6	56	4	0	0	70	0	146	524	0	0	0	0
4:15 PM	0	1	0	3	0	2	0	0	0	0	3	64	1	0	1	49	0	124	489	0	0	0	0
4:30 PM	0	1	0	2	0	5	0	1	0	3	45	2	0	0	0	55	2	116	484	0	0	0	0
4:45 PM	0	3	1	4	0	1	0	2	0	5	68	6	0	0	0	46	2	138	475	0	0	0	0
5:00 PM	0	2	0	3	0	8	1	2	0	2	52	2	0	2	37	0	111	439	0	0	0	0	
5:15 PM	0	1	0	1	0	0	0	1	0	5	58	1	0	0	0	51	1	119	0	0	0	0	
5:30 PM	0	0	0	4	0	4	0	0	0	2	53	0	0	1	42	1	107	0	0	0	0	0	
5:45 PM	0	1	0	2	0	0	0	1	0	6	51	0	0	0	0	41	0	102	0	0	0	0	
Count Total	0	13	1	23	0	22	1	7	0	32	447	16	0	4	391	6	963	0	0	0	0	0	
Peak Hour	0	9	1	13	0	10	0	3	0	17	233	13	0	1	220	4	524	0	0	0	0	0	


**Location:** 5 Vollmer Road & Dines Blvd PM

**Date:** Thursday, March 24, 2022


**Peak Hour:** 04:00 PM - 05:00 PM

**Peak 15-Minutes:** 04:00 PM - 04:15 PM

### Peak Hour - All Vehicles



### Peak Hour - Pedestrians/Bicycles on Crosswalk



Note: Total study counts contained in parentheses.

### Traffic Counts

Interval Start Time	Dines Blvd Eastbound				Dines Blvd Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings				
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right		West	East	South	North	
4:00 PM	0	0	0	0	0	24	0	3	0	0	46	18	0	2	44	0	137	470	0	0	0	0
4:15 PM	0	0	0	0	0	13	0	5	0	0	36	25	0	5	37	0	121	441	0	0	0	0
4:30 PM	0	0	0	0	0	12	0	2	0	0	35	11	0	3	30	0	93	436	0	0	0	0
4:45 PM	0	0	0	0	0	16	0	0	0	0	49	21	0	3	30	0	119	452	0	0	0	0
5:00 PM	0	0	0	0	0	14	0	5	0	0	42	18	0	2	27	0	108	425	0	0	0	0
5:15 PM	0	0	0	0	0	17	0	3	0	0	39	17	0	4	36	0	116	0	0	0	0	
5:30 PM	0	0	0	0	0	12	0	1	0	0	36	21	0	8	31	0	109	0	0	0	0	
5:45 PM	0	0	0	0	0	14	0	1	0	0	30	16	0	4	27	0	92	0	0	0	0	
Count Total	0	0	0	0	0	122	0	20	0	0	313	147	0	31	262	0	895	0	0	0	0	
Peak Hour	0	0	0	0	0	65	0	10	0	0	166	75	0	13	141	0	470	0	0	0	0	


**Location:** 6 Vollmer Road & Poco Road PM

Date: Thursday, March 24, 2022


**Peak Hour:** 04:00 PM - 05:00 PM

**Peak 15-Minutes:** 04:15 PM - 04:30 PM

## Peak Hour - All Vehicles



## **Peak Hour - Pedestrians/Bicycles on Crosswalk**



Note: Total study counts contained in parentheses.

## Traffic Counts

Interval Start Time	Poco Road Eastbound				Poco Road Westbound				Vollmer Road Northbound				Vollmer Road Southbound				Rolling Hour	Pedestrian Crossings					
	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	U-Turn	Left	Thru	Right	Total	West	East	South	North		
4:00 PM	0	0	0	0	0	8	1	4	0	0	41	4	0	1	29	2	90	339	0	0	0	0	0
4:15 PM	0	1	0	0	0	4	0	2	0	0	40	6	0	1	39	2	95	325	0	0	0	0	0
4:30 PM	0	0	0	0	0	2	0	0	0	0	32	3	0	1	28	0	66	313	0	0	0	0	0
4:45 PM	0	1	0	1	0	7	0	1	0	0	43	8	0	0	27	0	88	321	0	0	0	0	0
5:00 PM	0	0	0	2	0	6	0	1	0	0	44	3	0	0	20	0	76	302	0	0	0	0	0
5:15 PM	0	0	0	0	0	12	0	0	0	0	37	4	0	0	29	1	83		0	0	0	0	0
5:30 PM	0	0	0	0	0	6	0	2	0	0	33	3	0	1	29	0	74		0	0	0	0	0
5:45 PM	0	0	0	0	0	5	0	1	0	1	27	4	0	0	31	0	69		0	0	0	0	0
Count Total	0	2	0	3	0	50	1	11	0	1	297	35	0	4	232	5	641		0	0	0	0	0
Peak Hour	0	2	0	1	0	21	1	7	0	0	156	21	0	3	123	4	339		0	0	0	0	0

# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
 Colorado Springs, CO 80905  
 719-633-2868

File Name : Blackforest Rd - Woodmen Rd AM  
 Site Code : S214590  
 Start Date : 7/6/2021  
 Page No : 1


## Groups Printed- Unshifted

	Black Forest Rd Southbound					Woodmen Rd Westbound					Black Forest Rd Northbound					Woodmen Rd Eastbound					Int. Total
	Start Time	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total
06:30 AM	45	28	96	0	169	9	306	35	0	350	14	14	10	0	38	45	87	17	0	149	706
06:45 AM	51	33	98	0	182	24	256	46	1	327	10	23	19	0	52	47	117	31	0	195	756
Total	96	61	194	0	351	33	562	81	1	677	24	37	29	0	90	92	204	48	0	344	1462
07:00 AM	55	23	99	1	178	23	283	50	0	356	31	21	12	0	64	70	101	8	0	179	777
07:15 AM	57	29	136	0	222	21	310	65	0	396	37	48	14	0	99	60	125	12	0	197	914
07:30 AM	56	31	115	0	202	25	350	50	1	426	29	30	18	0	77	95	150	17	1	263	968
07:45 AM	56	46	108	0	210	21	299	49	1	370	36	45	18	0	99	62	145	25	0	232	911
Total	224	129	458	1	812	90	1242	214	2	1548	133	144	62	0	339	287	521	62	1	871	3570
08:00 AM	40	34	98	0	172	16	284	58	2	360	25	39	17	0	81	61	157	12	0	230	843
08:15 AM	59	30	128	0	217	13	256	46	2	317	23	35	20	0	78	67	124	5	0	196	808
Grand Total	419	254	878	1	1552	152	2344	399	7	2902	205	255	128	0	588	507	1006	127	1	1641	6683
Apprch %	27	16.4	56.6	0.1		5.2	80.8	13.7	0.2		34.9	43.4	21.8	0		30.9	61.3	7.7	0.1		
Total %	6.3	3.8	13.1	0	23.2	2.3	35.1	6	0.1	43.4	3.1	3.8	1.9	0	8.8	7.6	15.1	1.9	0	24.6	

# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
Colorado Springs, CO 80905  
719-633-2868

File Name : Blackforest Rd - Woodmen Rd AM  
Site Code : S214590  
Start Date : 7/6/2021  
Page No : 3



# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
 Colorado Springs, CO 80905  
 719-633-2868

File Name : Blackforest Rd - Woodmen Rd PM  
 Site Code : S214590  
 Start Date : 7/6/2021  
 Page No : 1


## Groups Printed- Unshifted

Start Time	Black Forest Rd Southbound					Woodmen Rd Westbound					Black Forest Rd Northbound					Woodmen Rd Eastbound					Int. Total
	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	
04:00 PM	54	29	105	0	188	16	231	54	1	302	26	62	35	0	123	125	241	10	0	376	989
04:15 PM	63	40	95	0	198	11	252	62	1	326	26	51	39	0	116	96	297	17	1	411	1051
04:30 PM	53	45	95	0	193	11	250	69	1	331	28	59	24	0	111	127	309	9	1	446	1081
04:45 PM	60	36	114	0	210	13	253	61	3	330	22	77	26	0	125	108	285	16	1	410	1075
Total	230	150	409	0	789	51	986	246	6	1289	102	249	124	0	475	456	1132	52	3	1643	4196
05:00 PM	67	50	134	0	251	10	249	76	0	335	17	68	43	0	128	149	286	8	0	443	1157
05:15 PM	67	47	102	0	216	13	225	68	1	307	18	76	25	0	119	100	347	5	0	452	1094
05:30 PM	50	37	103	0	190	15	227	59	2	303	15	68	37	0	120	130	324	14	0	468	1081
05:45 PM	66	38	113	0	217	17	188	47	2	254	18	69	30	0	117	116	295	13	1	425	1013
Total	250	172	452	0	874	55	889	250	5	1199	68	281	135	0	484	495	1252	40	1	1788	4345
Grand Total	480	322	861	0	1663	106	1875	496	11	2488	170	530	259	0	959	951	2384	92	4	3431	8541
Apprch %	28.9	19.4	51.8	0		4.3	75.4	19.9	0.4		17.7	55.3	27	0		27.7	69.5	2.7	0.1		
Total %	5.6	3.8	10.1	0	19.5	1.2	22	5.8	0.1	29.1	2	6.2	3	0	11.2	11.1	27.9	1.1	0	40.2	

# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
Colorado Springs, CO 80905  
719-633-2868

File Name : Blackforest Rd - Woodmen Rd PM  
Site Code : S214590  
Start Date : 7/6/2021  
Page No : 3



# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
 Colorado Springs, CO 80905  
 719-633-2868

File Name : Marksheffel Rd - Woodmen Rd AM 8-21 AM  
 Site Code : S214630  
 Start Date : 8/3/2021  
 Page No : 1


## Groups Printed- Unshifted

Start Time	Marksheffel Rd Southbound					Woodmen Rd Westbound					Marksheffel Rd Northbound					Woodmen Rd Eastbound					Int. Total
	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	
06:30 AM	1	12	14	0	27	52	251	0	0	303	90	6	34	0	130	2	109	86	2	199	659
06:45 AM	2	9	15	0	26	65	213	3	0	281	124	11	56	0	191	10	148	81	1	240	738
Total	3	21	29	0	53	117	464	3	0	584	214	17	90	0	321	12	257	167	3	439	1397
07:00 AM	2	16	14	0	32	88	269	4	0	361	106	5	54	0	165	2	121	93	1	217	775
07:15 AM	4	28	15	1	48	119	302	4	0	425	114	11	76	0	201	7	125	90	0	222	896
07:30 AM	1	17	25	0	43	135	334	1	0	470	119	13	69	1	202	7	154	98	2	261	976
07:45 AM	4	15	37	0	56	125	228	2	0	355	131	21	70	0	222	12	144	88	4	248	881
Total	11	76	91	1	179	467	1133	11	0	1611	470	50	269	1	790	28	544	369	7	948	3528
08:00 AM	0	7	23	0	30	54	238	3	0	295	120	13	70	0	203	8	140	78	1	227	755
08:15 AM	2	3	19	0	24	79	213	1	0	293	115	20	56	0	191	9	112	65	2	188	696
Grand Total	16	107	162	1	286	717	2048	18	0	2783	919	100	485	1	1505	57	1053	679	13	1802	6376
Apprch %	5.6	37.4	56.6	0.3		25.8	73.6	0.6	0		61.1	6.6	32.2	0.1		3.2	58.4	37.7	0.7		
Total %	0.3	1.7	2.5	0	4.5	11.2	32.1	0.3	0	43.6	14.4	1.6	7.6	0	23.6	0.9	16.5	10.6	0.2	28.3	

# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
Colorado Springs, CO 80905  
719-633-2868

File Name : Marksheffel Rd - Woodmen Rd AM 8-21 AM  
Site Code : S214630  
Start Date : 8/3/2021  
Page No : 3



# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
 Colorado Springs, CO 80905  
 719-633-2868

File Name : Marksheffel Rd - Woodmen Rd AM 8-21 PM  
 Site Code : S214630  
 Start Date : 8/3/2021  
 Page No : 1


## Groups Printed- Unshifted

Start Time	Marksheffel Rd Southbound					Woodmen Rd Westbound					Marksheffel Rd Northbound					Woodmen Rd Eastbound					Int. Total
	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	L	T	R	U	App. Total	
04:00 PM	3	9	20	0	32	64	231	3	1	299	111	16	108	4	239	14	244	98	1	357	927
04:15 PM	3	11	12	0	26	92	208	1	0	301	124	9	104	0	237	15	295	114	0	424	988
04:30 PM	2	2	10	0	14	135	206	0	0	341	94	22	89	0	205	10	308	111	0	429	989
04:45 PM	2	10	17	0	29	65	179	3	0	247	143	17	141	0	301	16	278	94	2	390	967
Total	10	32	59	0	101	356	824	7	1	1188	472	64	442	4	982	55	1125	417	3	1600	3871
05:00 PM	1	7	14	0	22	126	191	3	0	320	110	11	100	0	221	27	265	133	2	427	990
05:15 PM	3	14	14	0	31	76	184	2	0	262	135	14	135	0	284	27	303	117	2	449	1026
05:30 PM	3	3	14	0	20	52	236	2	0	290	93	9	135	0	237	28	348	121	1	498	1045
05:45 PM	2	7	19	0	28	56	167	1	0	224	104	10	155	2	271	20	301	117	5	443	966
Total	9	31	61	0	101	310	778	8	0	1096	442	44	525	2	1013	102	1217	488	10	1817	4027
Grand Total	19	63	120	0	202	666	1602	15	1	2284	914	108	967	6	1995	157	2342	905	13	3417	7898
Apprch %	9.4	31.2	59.4	0		29.2	70.1	0.7	0		45.8	5.4	48.5	0.3		4.6	68.5	26.5	0.4		
Total %	0.2	0.8	1.5	0	2.6	8.4	20.3	0.2	0	28.9	11.6	1.4	12.2	0.1	25.3	2	29.7	11.5	0.2	43.3	

# LSC Transportation Consultants, Inc.

545 E Pikes Peak Ave, Suite 210  
Colorado Springs, CO 80905  
719-633-2868

File Name : Marksheffel Rd - Woodmen Rd AM 8-21 PM  
Site Code : S214630  
Start Date : 8/3/2021  
Page No : 3



## Levels of Service

---

Consider using a different analysis tool  
for roundabouts. (typical all scenarios)

Appropriate Y+AR times should be calculated  
and included in all future signalized analyses.  
These values should come from agency signal  
timing data for existing signalized intersections,



HCM 6th TWSC  
1: Vollmer Rd & Burgess Rd

Existing Traffic  
AM Peak Hour

Intersection																
Int Delay, s/veh	12.4															
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR				
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+				
Traffic Vol, veh/h	3	43	10	44	227	74	17	49	24	30	69	10				
Future Vol, veh/h	3	43	10	44	227	74	17	49	24	30	69	10				
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0				
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free				
RT Channelized	-	-	None	-	-	None	-	-	Free	-	-	None				
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-				
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-				
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-				
Peak Hour Factor	78	78	78	87	87	87	80	80	80	83	83	83				
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2				
Mvmt Flow	4	55	13	51	261	85	21	61	30	36	83	12				
Major/Minor	Minor2		Minor1		Major1		Major2									
Conflicting Flow All	437	264	89	298	270	61	95	0	-	61	0	0				
Stage 1	161	161	-	103	103	-	-	-	-	-	-	-				
Stage 2	276	103	-	195	167	-	-	-	-	-	-	-				
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-				
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-				
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-				
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-				
Pot Cap-1 Maneuver	530	641	969	654	636	1004	1499	-	0	1542	-	-				
Stage 1	841	765	-	903	810	-	-	-	0	-	-	-				
Stage 2	730	810	-	807	760	-	-	-	0	-	-	-				
Platoon blocked, %								-	-	-	-	-				
Mov Cap-1 Maneuver	314	615	969	583	611	1004	1499	-	-	1542	-	-				
Mov Cap-2 Maneuver	314	615	-	583	611	-	-	-	-	-	-	-				
Stage 1	828	746	-	889	798	-	-	-	-	-	-	-				
Stage 2	443	798	-	719	741	-	-	-	-	-	-	-				
Approach	EB		WB		NB		SB									
HCM Control Delay, s	11.5		18.2		1.9		2									
HCM LOS	B		C													
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	WBLn1	SBL	SBT	SBR									
Capacity (veh/h)	1499	-	624	663	1542	-	-									
HCM Lane V/C Ratio	0.014	-	0.115	0.598	0.023	-	-									
HCM Control Delay (s)	7.4	0	11.5	18.2	7.4	0	-									
HCM Lane LOS	A	A	B	C	A	A	-									
HCM 95th %tile Q(veh)	0	-	0.4	4	0.1	-	-									

Intersection

Int Delay, s/veh 2.3

Movement	WBL	WBR	NBT	NBR	SBL	SBT
----------	-----	-----	-----	-----	-----	-----

Lane Configurations						
---------------------	--	--	--	--	--	--

Traffic Vol, veh/h	70	17	112	54	3	133
--------------------	----	----	-----	----	---	-----

Future Vol, veh/h	70	17	112	54	3	133
-------------------	----	----	-----	----	---	-----

Conflicting Peds, #/hr	0	0	0	0	0	0
------------------------	---	---	---	---	---	---

Sign Control	Stop	Stop	Free	Free	Free	Free
--------------	------	------	------	------	------	------

RT Channelized	-	None	-	None	-	None
----------------	---	------	---	------	---	------

Storage Length	0	0	-	155	205	-
----------------	---	---	---	-----	-----	---

Veh in Median Storage, #	0	-	0	-	-	0
--------------------------	---	---	---	---	---	---

Grade, %	0	-	0	-	-	0
----------	---	---	---	---	---	---

Peak Hour Factor	78	78	70	70	83	83
------------------	----	----	----	----	----	----

Heavy Vehicles, %	2	2	2	2	2	2
-------------------	---	---	---	---	---	---

Mvmt Flow	90	22	160	77	4	160
-----------	----	----	-----	----	---	-----

Major/Minor	Minor1	Major1	Major2
-------------	--------	--------	--------

Conflicting Flow All	248	160	0	0	237	0
----------------------	-----	-----	---	---	-----	---

Stage 1	160	-	-	-	-	-
---------	-----	---	---	---	---	---

Stage 2	88	-	-	-	-	-
---------	----	---	---	---	---	---

Critical Hdwy	6.63	6.23	-	-	4.13	-
---------------	------	------	---	---	------	---

Critical Hdwy Stg 1	5.43	-	-	-	-	-
---------------------	------	---	---	---	---	---

Critical Hdwy Stg 2	5.83	-	-	-	-	-
---------------------	------	---	---	---	---	---

Follow-up Hdwy	3.519	3.319	-	-	2.219	-
----------------	-------	-------	---	---	-------	---

Pot Cap-1 Maneuver	730	884	-	-	1329	-
--------------------	-----	-----	---	---	------	---

Stage 1	868	-	-	-	-	-
---------	-----	---	---	---	---	---

Stage 2	926	-	-	-	-	-
---------	-----	---	---	---	---	---

Platoon blocked, %	-	-	-	-	-	-
--------------------	---	---	---	---	---	---

Mov Cap-1 Maneuver	728	884	-	-	1329	-
--------------------	-----	-----	---	---	------	---

Mov Cap-2 Maneuver	728	-	-	-	-	-
--------------------	-----	---	---	---	---	---

Stage 1	868	-	-	-	-	-
---------	-----	---	---	---	---	---

Stage 2	923	-	-	-	-	-
---------	-----	---	---	---	---	---

Approach	WB	NB	SB
----------	----	----	----

HCM Control Delay, s	10.3	0	0.2
----------------------	------	---	-----

HCM LOS	B
---------	---

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	WBLn2	SBL	SBT
-----------------------	-----	-----	-------	-------	-----	-----

Capacity (veh/h)	-	-	728	884	1329	-
------------------	---	---	-----	-----	------	---

HCM Lane V/C Ratio	-	-	0.123	0.025	0.003	-
--------------------	---	---	-------	-------	-------	---

HCM Control Delay (s)	-	-	10.6	9.2	7.7	-
-----------------------	---	---	------	-----	-----	---

HCM Lane LOS	-	-	B	A	A	-
--------------	---	---	---	---	---	---

HCM 95th %tile Q(veh)	-	-	0.4	0.1	0	-
-----------------------	---	---	-----	-----	---	---

Timings  
14: Black Forest Rd & Vollmer Rd

All existing conditions  
signalized analyses should  
use existing signal timings.

Existing Traffic  
AM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	↑ ↗	↗ ↗	↑ ↗	↗ ↗	↗ ↗	↗ ↗
Traffic Volume (vph)	494	3	339	469	3	405
Future Volume (vph)	494	3	339	469	3	405
Turn Type	Prot	Prot	NA	Perm	Perm	NA
Protected Phases	3	3	2			6
Permitted Phases				2	6	
Detector Phase	3	3	2	2	6	6
Switch Phase						
Minimum Initial (s)	15.0	15.0	15.0	15.0	15.0	15.0
Minimum Split (s)	19.5	19.5	20.0	20.0	20.0	20.0
Total Split (s)	40.0	40.0	50.0	50.0	50.0	50.0
Total Split (%)	44.4%	44.4%	55.6%	55.6%	55.6%	55.6%
Yellow Time (s)	3.5	3.5	3.0	3.0	3.0	3.0
All-Red Time (s)	1.0	1.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0
Total Lost Time (s)	4.5	4.5	5.0	5.0		5.0
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	33.2	33.2	47.3	47.3		47.3
Actuated g/C Ratio	0.37	0.37	0.53	0.53		0.53
v/c Ratio	0.91	0.01	0.44	0.54		0.57
Control Delay	46.7	11.0	15.7	3.1		18.1
Queue Delay	0.0	0.0	0.0	0.0		0.0
Total Delay	46.7	11.0	15.7	3.1		18.1
LOS	D	B	B	A		B
Approach Delay	46.4			8.4		18.1
Approach LOS	D			A		B

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green

Natural Cycle: 55

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.91

Intersection Signal Delay: 21.3

Intersection LOS: C

Intersection Capacity Utilization 59.0%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 14: Black Forest Rd & Vollmer Rd



Timings  
15: Black Forest Rd & Woodmen Rd

Existing Traffic

AM Peak Hour

	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group												
Lane Configurations	↑↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑	↑
Traffic Volume (vph)	278	577	66	83	1243	222	127	162	67	209	140	457
Future Volume (vph)	278	577	66	83	1243	222	127	162	67	209	140	457
Turn Type	Prot	NA	Perm	Prot	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases						6			8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	8.0	15.0	15.0	8.0	15.0	15.0	8.0	10.0	10.0	8.0	10.0	10.0
Minimum Split (s)	13.0	20.0	20.0	13.0	20.0	20.0	13.0	15.0	15.0	13.0	15.0	15.0
Total Split (s)	25.0	55.0	55.0	25.0	55.0	55.0	15.0	25.0	25.0	15.0	25.0	25.0
Total Split (%)	20.8%	45.8%	45.8%	20.8%	45.8%	45.8%	12.5%	20.8%	20.8%	12.5%	20.8%	20.8%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max	Max	None	Max	Max
Act Effect Green (s)	15.2	61.3	61.3	11.3	54.8	54.8	9.3	20.0	20.0	30.7	20.7	20.7
Actuated g/C Ratio	0.13	0.51	0.51	0.09	0.46	0.46	0.08	0.17	0.17	0.26	0.17	0.17
v/c Ratio	0.66	0.33	0.08	0.51	0.78	0.27	0.49	0.28	0.19	0.61	0.45	0.89
Control Delay	57.1	19.0	1.0	61.7	32.4	3.5	59.3	45.2	3.3	44.3	49.9	38.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.1	19.0	1.0	61.7	32.4	3.5	59.3	45.2	3.3	44.3	49.9	38.1
LOS	E	B	A	E	C	A	E	D	A	D	D	D
Approach Delay		29.2			29.9			42.4			41.8	
Approach LOS		C			C			D			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.89

Intersection Signal Delay: 33.6


Intersection LOS: C

Intersection Capacity Utilization 81.8%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 15: Black Forest Rd & Woodmen Rd



Timings  
16: Marksheffel Rd & Woodmen Rd

Existing Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑	↑↑
Traffic Volume (vph)	49	598	364	393	1090	6	337	184	260	7	65	229
Future Volume (vph)	49	598	364	393	1090	6	337	184	260	7	65	229
Turn Type	Prot	NA	Perm	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases				2		Free		8		Free	4	
Detector Phase	5	2	2	1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	4.0	25.0	25.0	4.0	25.0		4.0	10.0		4.0	10.0	
Minimum Split (s)	9.0	32.5	32.5	9.0	32.5		9.0	17.5		9.0	17.5	
Total Split (s)	20.0	63.0	63.0	25.0	68.0		25.0	25.0		25.0	25.0	
Total Split (%)	14.5%	45.7%	45.7%	18.1%	49.3%		18.1%	18.1%		18.1%	18.1%	
Yellow Time (s)	3.0	5.5	5.5	3.0	5.5		3.0	5.5		3.0	5.5	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0	-3.0	-1.0	-3.0		-1.0	-2.0		-1.0	-2.0	
Total Lost Time (s)	4.0	4.5	4.5	4.0	4.5		4.0	5.5		4.0	5.5	
Lead/Lag	Lead	Lag	Lag	Lead	Lag		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	C-Max	C-Max	None	C-Max		None	None		None	None	
Act Effect Green (s)	7.6	64.2	64.2	26.0	84.5	138.0	35.3	31.6	138.0	17.2	12.3	138.0
Actuated g/C Ratio	0.06	0.47	0.47	0.19	0.61	1.00	0.26	0.23	1.00	0.12	0.09	1.00
v/c Ratio	0.28	0.39	0.41	0.77	0.64	0.01	0.99	0.47	0.18	0.05	0.24	0.17
Control Delay	65.9	26.3	3.7	61.8	20.6	0.0	91.9	49.7	0.2	37.4	60.3	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	65.9	26.3	3.7	61.8	20.6	0.0	91.9	49.7	0.2	37.4	60.3	0.2
LOS	E	C	A	E	C	A	F	D	A	D	E	A
Approach Delay		20.1			31.4			51.4			14.1	
Approach LOS		C			C			D			B	

Intersection Summary

Cycle Length: 138

Actuated Cycle Length: 138

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.99

Intersection Signal Delay: 31.1


Intersection LOS: C

Intersection Capacity Utilization 70.5%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 16: Marksheffel Rd & Woodmen Rd



Provide justification for lost time adjustments or remove (typical all signalized analyses)

Intersection																
Int Delay, s/veh	31.1															
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR				
Lane Configurations	+	+	+	+	+	+	+	+	+	+	+	+				
Traffic Vol, veh/h	9	244	12	45	123	43	16	69	62	117	68	9				
Future Vol, veh/h	9	244	12	45	123	43	16	69	62	117	68	9				
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0				
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free				
RT Channelized	-	-	None	-	-	None	-	-	Free	-	-	None				
Storage Length	-	-	-	-	-	-	-	-	-	-	-	-				
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-				
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-				
Peak Hour Factor	78	78	78	87	87	87	92	92	92	76	76	76				
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2				
Mvmt Flow	12	313	15	52	141	49	17	75	67	154	89	12				
Major/Minor	Minor2		Minor1		Major1		Major2									
Conflicting Flow All	607	512	95	676	518	75	101	0	-	75	0	0				
Stage 1	403	403	-	109	109	-	-	-	-	-	-	-				
Stage 2	204	109	-	567	409	-	-	-	-	-	-	-				
Critical Hdwy	7.12	6.52	6.22	7.12	6.52	6.22	4.12	-	-	4.12	-	-				
Critical Hdwy Stg 1	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-				
Critical Hdwy Stg 2	6.12	5.52	-	6.12	5.52	-	-	-	-	-	-	-				
Follow-up Hdwy	3.518	4.018	3.318	3.518	4.018	3.318	2.218	-	-	2.218	-	-				
Pot Cap-1 Maneuver	408	465	962	367	462	986	1491	-	0	1524	-	-				
Stage 1	624	600	-	896	805	-	-	-	0	-	-	-				
Stage 2	798	805	-	508	596	-	-	-	0	-	-	-				
Platoon blocked, %	-															
Mov Cap-1 Maneuver	259	410	962	125	407	986	1491	-	-	1524	-	-				
Mov Cap-2 Maneuver	259	410	-	125	407	-	-	-	-	-	-	-				
Stage 1	617	536	-	885	795	-	-	-	-	-	-	-				
Stage 2	616	795	-	186	532	-	-	-	-	-	-	-				
Approach	EB		WB		NB		SB									
HCM Control Delay, s	43.2		53.3		1.4		4.6									
HCM LOS	E		F													
Minor Lane/Major Mvmt	NBL	NBT	EBLn1	WBLn1	SBL	SBT	SBR									
Capacity (veh/h)	1491	-	413	299	1524	-	-									
HCM Lane V/C Ratio	0.012	-	0.823	0.811	0.101	-	-									
HCM Control Delay (s)	7.4	0	43.2	53.3	7.6	0	-									
HCM Lane LOS	A	A	E	F	A	A	-									
HCM 95th %tile Q(veh)	0	-	7.6	6.6	0.3	-	-									

Intersection						
Int Delay, s/veh	2.3					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	↑	↑	↑	↑	↑	↑↑
Traffic Vol, veh/h	65	10	166	75	13	141
Future Vol, veh/h	65	10	166	75	13	141
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	155	205	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	69	69	87	87	84	84
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	94	14	191	86	15	168
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	305	191	0	0	277	0
Stage 1	191	-	-	-	-	-
Stage 2	114	-	-	-	-	-
Critical Hdwy	6.63	6.23	-	-	4.13	-
Critical Hdwy Stg 1	5.43	-	-	-	-	-
Critical Hdwy Stg 2	5.83	-	-	-	-	-
Follow-up Hdwy	3.519	3.319	-	-	2.219	-
Pot Cap-1 Maneuver	675	850	-	-	1284	-
Stage 1	841	-	-	-	-	-
Stage 2	899	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	667	850	-	-	1284	-
Mov Cap-2 Maneuver	667	-	-	-	-	-
Stage 1	841	-	-	-	-	-
Stage 2	888	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	11	0	0.7			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	WBLn2	SBL	SBT
Capacity (veh/h)	-	-	667	850	1284	-
HCM Lane V/C Ratio	-	-	0.141	0.017	0.012	-
HCM Control Delay (s)	-	-	11.3	9.3	7.8	-
HCM Lane LOS	-	-	B	A	A	-
HCM 95th %tile Q(veh)	-	-	0.5	0.1	0	-

Timings  
14: Black Forest Rd & Vollmer Rd

Existing Traffic  
PM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	↑ ↗	↗ ↑	↑ ↗	↗ ↑	↗ ↘	↖ ↘
Traffic Volume (vph)	451	10	413	591	8	510
Future Volume (vph)	451	10	413	591	8	510
Turn Type	Prot	Prot	NA	Perm	Perm	NA
Protected Phases	3	3	2			6
Permitted Phases				2	6	
Detector Phase	3	3	2	2	6	6
Switch Phase						
Minimum Initial (s)	15.0	15.0	15.0	15.0	15.0	15.0
Minimum Split (s)	20.0	20.0	20.0	20.0	20.0	20.0
Total Split (s)	35.0	35.0	55.0	55.0	55.0	55.0
Total Split (%)	38.9%	38.9%	61.1%	61.1%	61.1%	61.1%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0		5.0
Lead/Lag						
Lead-Lag Optimize?						
Recall Mode	None	None	C-Max	C-Max	C-Max	C-Max
Act Effect Green (s)	27.5	27.5	52.5	52.5		52.5
Actuated g/C Ratio	0.31	0.31	0.58	0.58		0.58
v/c Ratio	0.88	0.02	0.40	0.53		0.50
Control Delay	48.4	10.9	12.2	2.7		13.7
Queue Delay	0.0	0.0	0.0	0.0		0.0
Total Delay	48.4	10.9	12.2	2.7		13.7
LOS	D	B	B	A		B
Approach Delay	47.5			6.6		13.7
Approach LOS	D			A		B

Intersection Summary

Cycle Length: 90

Actuated Cycle Length: 90

Offset: 80 (89%), Referenced to phase 2:NBT and 6:SBTL, Start of Green

Natural Cycle: 50

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.88

Intersection Signal Delay: 18.0


Intersection LOS: B

Intersection Capacity Utilization 72.2%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 14: Black Forest Rd & Vollmer Rd



Timings  
15: Black Forest Rd & Woodmen Rd

Existing Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑	↑
Traffic Volume (vph)	484	1227	38	47	977	274	85	280	118	247	178	445
Future Volume (vph)	484	1227	38	47	977	274	85	280	118	247	178	445
Turn Type	Prot	NA	Perm	Prot	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases						6				8	4	4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	5.0	15.0	15.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0
Total Split (s)	25.0	63.0	63.0	12.0	50.0	50.0	15.0	30.0	30.0	15.0	30.0	30.0
Total Split (%)	20.8%	52.5%	52.5%	10.0%	41.7%	41.7%	12.5%	25.0%	25.0%	12.5%	25.0%	25.0%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max	Max	None	Max	Max
Act Effect Green (s)	19.5	60.4	60.4	6.7	45.5	45.5	8.3	25.0	25.0	36.7	26.7	26.7
Actuated g/C Ratio	0.16	0.50	0.50	0.06	0.38	0.38	0.07	0.21	0.21	0.31	0.22	0.22
v/c Ratio	0.88	0.70	0.05	0.48	0.74	0.36	0.37	0.39	0.27	0.75	0.44	0.78
Control Delay	67.5	26.3	0.1	71.6	36.5	4.3	57.4	42.8	4.1	48.3	44.6	26.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	67.5	26.3	0.1	71.6	36.5	4.3	57.4	42.8	4.1	48.3	44.6	26.1
LOS	E	C	A	E	D	A	E	D	A	D	D	C
Approach Delay		37.1			31.0			35.9			36.2	
Approach LOS		D			C			D			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.88

Intersection Signal Delay: 35.0


Intersection LOS: C

Intersection Capacity Utilization 79.5%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 15: Black Forest Rd & Woodmen Rd



Timings  
16: Marksheffel Rd & Woodmen Rd

Existing Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	73	1193	573	335	863	12	345	149	424	9	42	154
Future Volume (vph)	73	1193	573	335	863	12	345	149	424	9	42	154
Turn Type	Prot	NA	Perm	Prot	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases				2		Free		8		Free	4	
Detector Phase	5	2	2	1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	4.0	25.0	25.0	4.0	25.0		4.0	10.0		4.0	10.0	
Minimum Split (s)	9.0	32.5	32.5	9.0	32.5		9.0	17.5		9.0	17.5	
Total Split (s)	20.0	63.0	63.0	25.0	68.0		25.0	25.0		25.0	25.0	
Total Split (%)	14.5%	45.7%	45.7%	18.1%	49.3%		18.1%	18.1%		18.1%	18.1%	
Yellow Time (s)	3.0	5.5	5.5	3.0	5.5		3.0	5.5		3.0	5.5	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0	-3.0	-1.0	-3.0		-1.0	-2.0		-1.0	-2.0	
Total Lost Time (s)	4.0	4.5	4.5	4.0	4.5		4.0	5.5		4.0	5.5	
Lead/Lag	Lead	Lag	Lag	Lead	Lag		Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes	Yes	Yes	Yes	Yes		Yes	Yes		Yes	Yes	
Recall Mode	None	C-Max	C-Max	None	C-Max		None	None		None	None	
Act Effect Green (s)	8.5	67.1	67.1	23.4	82.0	138.0	35.0	31.3	138.0	17.0	12.0	138.0
Actuated g/C Ratio	0.06	0.49	0.49	0.17	0.59	1.00	0.25	0.23	1.00	0.12	0.09	1.00
v/c Ratio	0.37	0.75	0.57	0.76	0.54	0.01	1.01	0.38	0.29	0.06	0.16	0.11
Control Delay	66.6	33.7	4.1	63.3	19.0	0.0	97.9	48.0	0.5	38.2	59.7	0.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	66.6	33.7	4.1	63.3	19.0	0.0	97.9	48.0	0.5	38.2	59.7	0.1
LOS	E	C	A	E	B	A	F	D	A	D	E	A
Approach Delay		25.8			31.1			44.8			13.9	
Approach LOS		C			C			D			B	

Intersection Summary

Cycle Length: 138

Actuated Cycle Length: 138

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.01

Intersection Signal Delay: 30.9


Intersection LOS: C

Intersection Capacity Utilization 80.0%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 16: Marksheffel Rd & Woodmen Rd



Intersection					
Approach	EB	WB	NB	SB	
Entry Lanes	1	1	1	1	
Conflicting Circle Lanes	1	1	1	1	
Adj Approach Flow, veh/h	115	579	250	254	
Demand Flow Rate, veh/h	117	590	254	259	
Vehicles Circulating, veh/h	353	198	120	496	
Vehicles Exiting, veh/h	402	116	350	292	
Ped Vol Crossing Leg, #/h	0	0	0	0	
Ped Cap Adj	1.000	1.000	1.000	1.000	
Approach Delay, s/veh	5.0	9.4	3.3	7.9	
Approach LOS	A	A	A	A	
Lane	Left	Left	Left	Bypass	Left
Designated Moves	LTR	LTR	LT	R	LTR
Assumed Moves	LTR	LTR	LT	R	LTR
RT Channelized				Free	
Lane Util	1.000	1.000	1.000	1.000	
Follow-Up Headway, s	2.609	2.609	2.609	2.609	
Critical Headway, s	4.976	4.976	4.976	60	4.976
Entry Flow, veh/h	117	590	194	1938	259
Cap Entry Lane, veh/h	963	1128	1221	0.980	832
Entry HV Adj Factor	0.980	0.981	0.983	59	0.981
Flow Entry, veh/h	115	579	191	1900	254
Cap Entry, veh/h	943	1106	1200	0.031	817
V/C Ratio	0.122	0.523	0.159	0.0	0.311
Control Delay, s/veh	5.0	9.4	4.4	A	7.9
LOS	A	A	A	0	A
95th %tile Queue, veh	0	3	1		1

Intersection						
Int Delay, s/veh	0.2					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B			A	
Traffic Vol, veh/h	9	1	181	3	0	325
Future Vol, veh/h	9	1	181	3	0	325
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	9	1	191	3	0	342
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	535	193	0	0	194	0
Stage 1	193	-	-	-	-	-
Stage 2	342	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	506	849	-	-	1379	-
Stage 1	840	-	-	-	-	-
Stage 2	719	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	506	849	-	-	1379	-
Mov Cap-2 Maneuver	506	-	-	-	-	-
Stage 1	840	-	-	-	-	-
Stage 2	719	-	-	-	-	-
Approach	WB	NB	SB			
HCM Control Delay, s	12	0	0			
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT	
Capacity (veh/h)	-	-	527	1379	-	
HCM Lane V/C Ratio	-	-	0.02	-	-	
HCM Control Delay (s)	-	-	12	0	-	
HCM Lane LOS	-	-	B	A	-	
HCM 95th %tile Q(veh)	-	-	0.1	0	-	

## Timings

2042 Baseline Traffic

AM Peak Hour



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	150	333	338	97	726	66	497	309	45	31	639	65
Future Volume (vph)	150	333	338	97	726	66	497	309	45	31	639	65
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0		8.0	15.0		8.0	15.0	
Minimum Split (s)	13.0	23.0		13.0	23.0		15.0	23.0		13.0	23.0	
Total Split (s)	15.0	40.0		22.0	47.0		25.0	46.0		13.0	33.0	
Total Split (%)	12.4%	33.1%		18.2%	38.8%		20.7%	38.0%		10.7%	27.3%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	41.4	31.5	121.0	42.3	32.0	121.0	23.4	56.3	121.0	43.8	35.8	121.0
Actuated g/C Ratio	0.34	0.26	1.00	0.35	0.26	1.00	0.19	0.47	1.00	0.36	0.30	1.00
v/c Ratio	0.76	0.38	0.22	0.28	0.82	0.04	0.79	0.20	0.03	0.08	0.64	0.04
Control Delay	49.6	37.5	0.3	24.9	49.2	0.0	55.7	21.7	0.0	17.9	41.9	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	49.6	37.5	0.3	24.9	49.2	0.0	55.7	21.7	0.0	17.9	41.9	0.0
LOS	D	D	A	C	D	A	E	C	A	B	D	A
Approach Delay		24.4			43.0			40.4			37.2	
Approach LOS		C			D			D			D	

## Intersection Summary

Cycle Length: 121

Actuated Cycle Length: 121

Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.82

Intersection Signal Delay: 36.4


Intersection LOS: D

Intersection Capacity Utilization 76.9%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 3: Black Forest Rd &amp; Briarate Pkwy



Timings  
4: Vollmer Rd & Briargate Pkwy

2042 Baseline Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	62	395	55	86	694	36	49	111	48	27	269	125
Future Volume (vph)	62	395	55	86	694	36	49	111	48	27	269	125
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2			6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	15.0	15.0	15.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	20.0	20.0	20.0	20.0	20.0	10.0	10.0	10.0	10.0	10.0	10.0
Total Split (s)	12.0	57.0	57.0	20.0	65.0	65.0	17.0	28.0	28.0	15.0	26.0	26.0
Total Split (%)	10.0%	47.5%	47.5%	16.7%	54.2%	54.2%	14.2%	23.3%	23.3%	12.5%	21.7%	21.7%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0	0.0	0.0	-2.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0	5.0	5.0	3.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	Max	Max	None	Max	Max	None	None	None	None	None	None
Act Effect Green (s)	60.2	57.1	55.1	15.3	63.3	61.3	22.3	17.2	17.2	19.4	14.0	14.0
Actuated g/C Ratio	0.58	0.55	0.53	0.15	0.61	0.59	0.21	0.16	0.16	0.19	0.13	0.13
v/c Ratio	0.14	0.21	0.06	0.18	0.34	0.04	0.22	0.19	0.13	0.10	0.60	0.38
Control Delay	9.2	15.6	0.1	44.0	12.9	0.1	33.5	40.5	0.7	31.6	49.5	7.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	9.2	15.6	0.1	44.0	12.9	0.1	33.5	40.5	0.7	31.6	49.5	7.8
LOS	A	B	A	D	B	A	C	D	A	C	D	A
Approach Delay		13.1			15.6			29.4			36.0	
Approach LOS		B			B			C			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 104.6

Natural Cycle: 60

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 0.60

Intersection Signal Delay: 20.8

Intersection LOS: C

Intersection Capacity Utilization 52.4%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 4: Vollmer Rd & Briargate Pkwy



## Intersection

Int Delay, s/veh 0.2

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑ ↗	↑ ↗	↗	↖	↑ ↗	↗	↖	↑	↗	↖	↑	↗
Traffic Vol, veh/h	2	468	0	4	807	2	1	1	8	6	1	9
Future Vol, veh/h	2	468	0	4	807	2	1	1	8	6	1	9
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	Free	-	-	Free
Storage Length	535	-	0	310	-	0	410	-	155	235	-	155
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	95	95	95	95	95	95	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	493	0	4	849	2	1	1	8	6	1	9

Major/Minor	Major1	Major2		Minor1		Minor2		
Conflicting Flow All	851	0	0	493	0	0	930	1356
Stage 1	-	-	-	-	-	-	497	497
Stage 2	-	-	-	-	-	-	433	859
Critical Hdwy	4.14	-	-	4.14	-	-	7.54	6.54
Critical Hdwy Stg 1	-	-	-	-	-	-	6.54	5.54
Critical Hdwy Stg 2	-	-	-	-	-	-	6.54	5.54
Follow-up Hdwy	2.22	-	-	2.22	-	-	3.52	4.02
Pot Cap-1 Maneuver	783	-	-	1067	-	-	222	148
Stage 1	-	-	-	-	-	-	523	543
Stage 2	-	-	-	-	-	-	571	371
Platoon blocked, %	-	-	-	-	-	-	0	318
Mov Cap-1 Maneuver	783	-	-	1067	-	-	220	147
Mov Cap-2 Maneuver	-	-	-	-	-	-	220	147
Stage 1	-	-	-	-	-	-	521	541
Stage 2	-	-	-	-	-	-	567	370

Approach	EB	WB		NB		SB						
HCM Control Delay, s	0	0		25.5		28.3						
HCM LOS				D		D						
<hr/>												
Minor Lane/Major Mvmt	NBLn1	NBLn2	NBLn3	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1	SBLn2	SBLn3
Capacity (veh/h)	220	147	-	783	-	-	1067	-	-	162	147	-
HCM Lane V/C Ratio	0.005	0.007	-	0.003	-	-	0.004	-	-	0.039	0.007	-
HCM Control Delay (s)	21.4	29.7	0	9.6	-	-	8.4	-	-	28.1	29.7	0
HCM Lane LOS	C	D	A	A	-	-	A	-	-	D	D	A
HCM 95th %tile Q(veh)	0	0	-	0	-	-	0	-	-	0.1	0	-

## Timings

2042 Baseline Traffic

AM Peak Hour

## 6: Banning Lewis Pkwy &amp; Briargate Pkwy



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	1	334	147	270	601	3	212	9	285	8	25	1
Future Volume (vph)	1	334	147	270	601	3	212	9	285	8	25	1
Turn Type	pm+pt	NA	Free	Prot	NA	Perm	Prot	NA	Free	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		Free			6			Free	4		4
Detector Phase	5	2		1	6	6	3	8		7	4	4
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0	15.0	8.0	10.0		8.0	10.0	10.0
Minimum Split (s)	15.0	20.0		20.0	20.0	20.0	13.0	15.0		13.0	15.0	15.0
Total Split (s)	12.0	43.0		20.0	51.0	51.0	32.0	45.0		12.0	25.0	25.0
Total Split (%)	10.0%	35.8%		16.7%	42.5%	42.5%	26.7%	37.5%		10.0%	20.8%	20.8%
Yellow Time (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0		0.0	-2.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0		5.0	3.0	5.0	5.0	5.0		5.0	5.0	5.0
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Act Effect Green (s)	46.1	41.1	120.0	13.9	57.6	55.6	13.1	49.6	120.0	40.9	33.9	33.9
Actuated g/C Ratio	0.38	0.34	1.00	0.12	0.48	0.46	0.11	0.41	1.00	0.34	0.28	0.28
v/c Ratio	0.00	0.29	0.10	0.71	0.37	0.00	0.59	0.01	0.19	0.02	0.03	0.00
Control Delay	17.0	29.9	0.1	61.5	21.2	0.0	57.3	23.3	0.3	20.4	32.8	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	17.0	29.9	0.1	61.5	21.2	0.0	57.3	23.3	0.3	20.4	32.8	0.0
LOS	B	C	A	E	C	A	E	C	A	C	C	A
Approach Delay		20.8			33.6			24.5			29.0	
Approach LOS		C			C			C			C	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.71

Intersection Signal Delay: 27.9


Intersection LOS: C

Intersection Capacity Utilization 47.7%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 6: Banning Lewis Pkwy &amp; Briargate Pkwy



Timings  
11: Black Forest Rd & Research Pkwy

2042 Baseline Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	200	421	100	100	485	231	275	366	100	332	450	375
Future Volume (vph)	200	421	100	100	485	231	275	366	100	332	450	375
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free	2		Free			Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	15.0		8.0	15.0	
Minimum Split (s)	10.0	23.0		10.0	23.0		10.0	23.0		15.0	23.0	
Total Split (s)	19.0	44.0		15.0	40.0		12.0	36.0		25.0	49.0	
Total Split (%)	15.8%	36.7%		12.5%	33.3%		10.0%	30.0%		20.8%	40.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	40.4	26.9	120.0	32.0	22.7	120.0	61.7	46.5	120.0	17.4	48.6	120.0
Actuated g/C Ratio	0.34	0.22	1.00	0.27	0.19	1.00	0.51	0.39	1.00	0.14	0.40	1.00
v/c Ratio	0.77	0.56	0.07	0.38	0.76	0.15	0.54	0.28	0.07	0.70	0.33	0.25
Control Delay	47.6	43.7	0.1	30.9	53.8	0.2	21.6	32.9	0.1	56.6	26.4	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.6	43.7	0.1	30.9	53.8	0.2	21.6	32.9	0.1	56.6	26.4	0.4
LOS	D	D	A	C	D	A	C	C	A	E	C	A
Approach Delay			38.8			35.9			24.3			26.6
Approach LOS			D			D			C			C

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.77

Intersection Signal Delay: 30.9


Intersection LOS: C

Intersection Capacity Utilization 68.9%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 11: Black Forest Rd & Research Pkwy



Timings  
12: Vollmer Rd & Marksheffel Rd

2042 Baseline Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	47	736	40	27	741	61	92	99	34	103	212	95
Future Volume (vph)	47	736	40	27	741	61	92	99	34	103	212	95
Turn Type	pm+pt	NA	Perm									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0
Total Split (s)	12.0	66.0	66.0	12.0	66.0	66.0	12.0	30.0	30.0	12.0	30.0	30.0
Total Split (%)	10.0%	55.0%	55.0%	10.0%	55.0%	55.0%	10.0%	25.0%	25.0%	10.0%	25.0%	25.0%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max	Max	None	Max	Max
Act Effect Green (s)	70.2	66.0	66.0	68.7	63.6	63.6	32.0	25.0	25.0	32.0	25.0	25.0
Actuated g/C Ratio	0.58	0.55	0.55	0.57	0.53	0.53	0.27	0.21	0.21	0.27	0.21	0.21
v/c Ratio	0.13	0.40	0.05	0.07	0.42	0.07	0.30	0.14	0.09	0.29	0.30	0.24
Control Delay	10.4	17.1	0.1	7.5	17.2	2.9	33.6	39.4	0.4	33.5	41.4	7.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	10.4	17.1	0.1	7.5	17.2	2.9	33.6	39.4	0.4	33.5	41.4	7.7
LOS	B	B	A	A	B	A	C	D	A	C	D	A
Approach Delay		15.9			15.9				31.1		31.6	
Approach LOS		B			B			C			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.42

Intersection Signal Delay: 20.2


Intersection LOS: C

Intersection Capacity Utilization 55.4%

ICU Level of Service B


Analysis Period (min) 15

Splits and Phases: 12: Vollmer Rd & Marksheffel Rd



Timings  
13: Sterling Ranch Rd & Marksheffel Rd

2042 Baseline Traffic  
AM Peak Hour



Lane Group	EBT	EBR	WBL	WBT	NBL	NBT	NBR	SBT	Ø5	Ø7
Lane Configurations	↑↑	↗	↖	↑↑	↖	↑	↗	↑		
Traffic Volume (vph)	873	10	26	791	39	8	55	4		
Future Volume (vph)	873	10	26	791	39	8	55	4		
Turn Type	NA	Perm	pm+pt	NA	pm+pt	NA	Perm	NA		
Protected Phases	2			1	6	3	8		4	5
Permitted Phases				2	6		8		8	
Detector Phase	2	2	1	6	3	8	8	8	4	
Switch Phase										
Minimum Initial (s)	15.0	15.0	5.0	15.0	5.0	10.0	10.0	10.0	5.0	20.0
Minimum Split (s)	20.0	20.0	10.0	20.0	10.0	15.0	15.0	20.0	10.0	25.0
Total Split (s)	51.0	51.0	12.0	51.0	12.0	25.0	25.0	45.0	12.0	32.0
Total Split (%)	42.5%	42.5%	10.0%	42.5%	10.0%	20.8%	20.8%	37.5%	10%	27%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0		
Lead/Lag	Lag	Lag	Lead	Lag	Lead	Lag	Lag	Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes							
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None	None	None	None
Act Effect Green (s)	94.9	94.9	100.6	101.6	11.5	12.4	12.4	10.0		
Actuated g/C Ratio	0.79	0.79	0.84	0.85	0.10	0.10	0.10	0.08		
v/c Ratio	0.33	0.01	0.06	0.28	0.27	0.04	0.19	0.03		
Control Delay	4.8	0.0	3.1	3.0	52.1	45.6	1.4	51.0		
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		
Total Delay	4.8	0.0	3.1	3.0	52.1	45.6	1.4	51.0		
LOS	A	A	A	A	D	D	A	D		
Approach Delay	4.7				3.0		24.1		51.0	
Approach LOS	A				A		C		D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.33

Intersection Signal Delay: 5.2


Intersection LOS: A

Intersection Capacity Utilization 41.3%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 13: Sterling Ranch Rd & Marksheffel Rd



Timings  
14: Black Forest Rd & Vollmer Rd

2042 Baseline Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑
Traffic Volume (vph)	23	13	39	489	6	130	36	500	432	95	1270	14
Future Volume (vph)	23	13	39	489	6	130	36	500	432	95	1270	14
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4			4			8	2		2	6	
Detector Phase	7	4	4	3	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)	5.0	10.0	10.0	5.0	10.0	10.0	5.0	15.0	15.0	5.0	15.0	15.0
Minimum Split (s)	10.0	15.0	15.0	10.0	15.0	15.0	10.0	20.0	20.0	10.0	20.0	20.0
Total Split (s)	12.0	23.0	23.0	39.0	50.0	50.0	12.0	46.0	46.0	12.0	46.0	46.0
Total Split (%)	10.0%	19.2%	19.2%	32.5%	41.7%	41.7%	10.0%	38.3%	38.3%	10.0%	38.3%	38.3%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max						
Act Effect Green (s)	14.4	10.0	10.0	23.3	28.2	28.2	67.9	61.2	61.2	73.1	67.4	67.4
Actuated g/C Ratio	0.12	0.08	0.08	0.19	0.24	0.24	0.57	0.51	0.51	0.61	0.56	0.56
v/c Ratio	0.13	0.09	0.15	0.77	0.01	0.29	0.19	0.29	0.44	0.20	0.67	0.02
Control Delay	30.4	52.4	1.2	53.9	34.0	7.4	6.0	8.3	5.9	13.3	28.8	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	30.4	52.4	1.2	53.9	34.0	7.4	6.0	8.3	5.9	13.3	28.8	0.0
LOS	C	D	A	D	C	A	A	A	A	B	C	A
Approach Delay		19.1			44.0			7.1			27.4	
Approach LOS		B			D			A			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.77

Intersection Signal Delay: 24.2


Intersection LOS: C

Intersection Capacity Utilization 72.4%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 14: Black Forest Rd & Vollmer Rd



## Timings

2042 Baseline Traffic

15: Black Forest Rd &amp; Woodmen Rd

AM Peak Hour

	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group												
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑↑	↑
Traffic Volume (vph)	380	832	200	273	1632	350	360	227	168	400	145	944
Future Volume (vph)	380	832	200	273	1632	350	360	227	168	400	145	944
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	10.0		5.0	10.0	
Minimum Split (s)	10.0	23.0		10.0	23.0		10.0	23.0		10.0	23.0	
Total Split (s)	23.0	56.0		20.0	53.0		20.0	24.0		20.0	24.0	
Total Split (%)	19.2%	46.7%		16.7%	44.2%		16.7%	20.0%		16.7%	20.0%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	17.0	52.1	120.0	13.9	49.0	120.0	14.8	19.0	120.0	15.0	19.2	120.0
Actuated g/C Ratio	0.14	0.43	1.00	0.12	0.41	1.00	0.12	0.16	1.00	0.12	0.16	1.00
v/c Ratio	0.80	0.38	0.13	0.70	0.80	0.23	0.87	0.41	0.11	0.95	0.18	0.61
Control Delay	62.8	23.9	0.2	50.7	32.0	0.2	72.4	48.0	0.1	77.4	40.6	4.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	62.8	23.9	0.2	50.7	32.0	0.2	72.4	48.0	0.1	77.4	40.6	4.3
LOS	E	C	A	D	C	A	E	D	A	E	D	A
Approach Delay		31.0			29.3			49.0			27.5	
Approach LOS		C			C			D			C	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.95

Intersection Signal Delay: 31.8


Intersection LOS: C

Intersection Capacity Utilization 78.8%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 15: Black Forest Rd &amp; Woodmen Rd



Timings  
16: Marksheffel Rd & Woodmen Rd

2042 Baseline Traffic

AM Peak Hour

	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Group												
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	230	757	413	544	1522	260	535	237	297	256	203	198
Future Volume (vph)	230	757	413	544	1522	260	535	237	297	256	203	198
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+ov	Prot	NA	Free
Protected Phases	5	2		1	6		3	8	1	7	4	
Permitted Phases			Free			Free			8			Free
Detector Phase	5	2		1	6		3	8	1	7	4	
Switch Phase												
Minimum Initial (s)	4.0	4.0		4.0	4.0		4.0	4.0	4.0	4.0	4.0	4.0
Minimum Split (s)	9.0	11.0		9.0	11.0		9.0	10.0	9.0	9.0	10.0	
Total Split (s)	25.0	36.0		31.0	42.0		24.0	27.0	31.0	26.0	29.0	
Total Split (%)	20.8%	30.0%		25.8%	35.0%		20.0%	22.5%	25.8%	21.7%	24.2%	
Yellow Time (s)	3.0	5.0		3.0	5.0		3.0	4.0	3.0	3.0	4.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0		-1.0	-3.0		-1.0	-2.0	0.0	-1.0	-2.0	
Total Lost Time (s)	4.0	4.0		4.0	4.0		4.0	4.0	5.0	4.0	4.0	
Lead/Lag	Lead	Lag		Lead	Lag		Lead	Lag	Lead	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	Yes	
Recall Mode	None	C-Max		None	C-Max		None	None	None	None	None	
Act Effect Green (s)	14.5	43.7	120.0	25.8	55.0	120.0	20.0	19.1	47.9	15.4	14.5	120.0
Actuated g/C Ratio	0.12	0.36	1.00	0.22	0.46	1.00	0.17	0.16	0.40	0.13	0.12	1.00
v/c Ratio	0.57	0.42	0.27	0.75	0.67	0.17	0.95	0.43	0.44	0.59	0.49	0.13
Control Delay	75.4	33.1	0.5	50.6	27.9	0.2	77.8	48.3	20.3	54.8	52.8	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	75.4	33.1	0.5	50.6	27.9	0.2	77.8	48.3	20.3	54.8	52.8	0.2
LOS	E	C	A	D	C	A	E	D	C	D	D	A
Approach Delay		30.4			30.1			55.3			37.7	
Approach LOS		C			C			E			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green, Master Intersection

Natural Cycle: 60

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.95

Intersection Signal Delay: 36.0


Intersection LOS: D

Intersection Capacity Utilization 70.2%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 16: Marksheffel Rd & Woodmen Rd



## Timings

17: Banning Lewis Pkwy &amp; Woodmen Rd

2042 Baseline Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	262	540	490	211	1149	25	742	219	173	31	221	226
Future Volume (vph)	262	540	490	211	1149	25	742	219	173	31	221	226
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	10.0		5.0	10.0	
Minimum Split (s)	10.0	20.0		10.0	20.0		10.0	15.0		10.0	15.0	
Total Split (s)	19.0	41.0		15.0	37.0		30.0	47.0		17.0	34.0	
Total Split (%)	15.8%	34.2%		12.5%	30.8%		25.0%	39.2%		14.2%	28.3%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	13.2	36.0	120.0	10.0	32.8	120.0	25.0	51.7	120.0	6.6	29.0	120.0
Actuated g/C Ratio	0.11	0.30	1.00	0.08	0.27	1.00	0.21	0.43	1.00	0.06	0.24	1.00
v/c Ratio	0.73	0.37	0.33	0.78	0.87	0.02	1.09	0.15	0.11	0.17	0.27	0.15
Control Delay	63.6	33.9	0.5	73.1	49.7	0.0	106.1	22.4	0.2	55.7	38.0	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	63.6	33.9	0.5	73.1	49.7	0.0	106.1	22.4	0.2	55.7	38.0	0.2
LOS	E	C	A	E	D	A	F	C	A	E	D	A
Approach Delay		27.3			52.4			73.8			21.3	
Approach LOS		C			D			E			C	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.09

Intersection Signal Delay: 47.0


Intersection LOS: D

Intersection Capacity Utilization 75.8%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 17: Banning Lewis Pkwy &amp; Woodmen Rd



Intersection					
Approach	EB	WB	NB	SB	
Entry Lanes	1	1	1	1	
Conflicting Circle Lanes	1	1	1	1	
Adj Approach Flow, veh/h	424	364	653	334	
Demand Flow Rate, veh/h	433	371	666	341	
Vehicles Circulating, veh/h	433	493	591	353	
Vehicles Exiting, veh/h	261	577	275	511	
Ped Vol Crossing Leg, #/h	0	0	0	0	
Ped Cap Adj	1.000	1.000	1.000	1.000	
Approach Delay, s/veh	10.5	10.1	11.6	7.7	
Approach LOS	B	B	B	A	
Lane	Left	Left	Left	Bypass	Left
Designated Moves	LTR	LTR	LT	R	LTR
Assumed Moves	LTR	LTR	LT	R	LTR
RT Channelized				Free	
Lane Util	1.000	1.000	1.000	1.000	
Follow-Up Headway, s	2.609	2.609	2.609	2.609	
Critical Headway, s	4.976	4.976	4.976	187	4.976
Entry Flow, veh/h	433	371	479	1938	341
Cap Entry Lane, veh/h	887	835	755	0.980	963
Entry HV Adj Factor	0.980	0.982	0.980	183	0.980
Flow Entry, veh/h	424	364	470	1900	334
Cap Entry, veh/h	870	819	740	0.096	944
V/C Ratio	0.488	0.445	0.634	0.0	0.354
Control Delay, s/veh	10.5	10.1	16.1	A	7.7
LOS	B	B	C	0	A
95th %tile Queue, veh	3	2	5		2

Intersection

Int Delay, s/veh 0.1

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B	A			
Traffic Vol, veh/h	6	1	446	10	1	256
Future Vol, veh/h	6	1	446	10	1	256
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	6	1	469	11	1	269

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	746	475	0	0	480
Stage 1	475	-	-	-	-
Stage 2	271	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	381	590	-	-	1082
Stage 1	626	-	-	-	-
Stage 2	775	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	381	590	-	-	1082
Mov Cap-2 Maneuver	381	-	-	-	-
Stage 1	626	-	-	-	-
Stage 2	774	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	14.1	0	0
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	401	1082	-
HCM Lane V/C Ratio	-	-	0.018	0.001	-
HCM Control Delay (s)	-	-	14.1	8.3	0
HCM Lane LOS	-	-	B	A	A
HCM 95th %tile Q(veh)	-	-	0.1	0	-

## Timings

2042 Baseline Traffic

## 3: Black Forest Rd &amp; Briarate Pkwy

PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	190	624	318	163	482	39	408	782	208	51	510	210
Future Volume (vph)	190	624	318	163	482	39	408	782	208	51	510	210
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0		5.0	15.0		5.0	15.0	
Minimum Split (s)	13.0	23.0		13.0	23.0		10.0	23.0		10.0	23.0	
Total Split (s)	20.0	49.0		17.0	46.0		23.0	42.0		12.0	31.0	
Total Split (%)	16.7%	40.8%		14.2%	38.3%		19.2%	35.0%		10.0%	25.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	41.9	28.2	120.0	37.5	26.0	120.0	20.4	55.1	120.0	47.2	39.9	120.0
Actuated g/C Ratio	0.35	0.24	1.00	0.31	0.22	1.00	0.17	0.46	1.00	0.39	0.33	1.00
v/c Ratio	0.65	0.79	0.21	0.71	0.66	0.03	0.74	0.51	0.14	0.17	0.46	0.14
Control Delay	36.0	50.3	0.3	42.6	47.0	0.0	39.9	18.1	0.1	17.8	35.0	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	36.0	50.3	0.3	42.6	47.0	0.0	39.9	18.1	0.1	17.8	35.0	0.2
LOS	D	D	A	D	D	A	D	B	A	B	C	A
Approach Delay		33.8			43.3			21.8			24.4	
Approach LOS		C			D			C			C	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.79

Intersection Signal Delay: 29.4


Intersection LOS: C

Intersection Capacity Utilization 68.7%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 3: Black Forest Rd &amp; Briarate Pkwy



Timings  
4: Vollmer Rd & Briargate Pkwy

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	194	602	94	65	513	31	108	329	79	31	170	108
Future Volume (vph)	194	602	94	65	513	31	108	329	79	31	170	108
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2			6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	15.0	15.0	15.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	20.0	20.0	20.0	20.0	20.0	10.0	10.0	10.0	10.0	10.0	10.0
Total Split (s)	12.0	57.0	57.0	20.0	65.0	65.0	17.0	28.0	28.0	15.0	26.0	26.0
Total Split (%)	10.0%	47.5%	47.5%	16.7%	54.2%	54.2%	14.2%	23.3%	23.3%	12.5%	21.7%	21.7%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0	0.0	0.0	-2.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0	5.0	5.0	3.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	Max	Max	None	Max	Max	None	None	None	None	None	None
Act Effect Green (s)	61.9	58.4	56.4	15.0	62.1	60.1	26.6	19.8	19.8	19.1	12.0	12.0
Actuated g/C Ratio	0.57	0.53	0.52	0.14	0.57	0.55	0.24	0.18	0.18	0.17	0.11	0.11
v/c Ratio	0.39	0.33	0.11	0.14	0.27	0.04	0.39	0.53	0.20	0.15	0.46	0.37
Control Delay	12.0	17.1	0.8	44.2	13.2	0.1	36.5	45.1	1.1	32.2	49.6	6.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	12.0	17.1	0.8	44.2	13.2	0.1	36.5	45.1	1.1	32.2	49.6	6.0
LOS	B	B	A	D	B	A	D	D	A	C	D	A
Approach Delay		14.2			15.8				36.4		32.6	
Approach LOS		B			B				D		C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 109.5

Natural Cycle: 60

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 0.53

Intersection Signal Delay: 22.0


Intersection LOS: C

Intersection Capacity Utilization 58.2%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 4: Vollmer Rd & Briargate Pkwy



## Intersection

Int Delay, s/veh 0.4

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑	↑	↑	↑	↑
Traffic Vol, veh/h	8	703	0	9	603	7	10	1	6	4	1	6
Future Vol, veh/h	8	703	0	9	603	7	10	1	6	4	1	6
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	Free	-	-	Free
Storage Length	535	-	0	310	-	0	410	-	155	235	-	155
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	95	95	95	95	95	95	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	8	740	0	9	635	7	11	1	6	4	1	6

Major/Minor	Major1	Major2		Minor1		Minor2						
Conflicting Flow All	642	0	0	740	0	0	1092	1416	-	1040	1409	-
Stage 1	-	-	-	-	-	-	756	756	-	653	653	-
Stage 2	-	-	-	-	-	-	336	660	-	387	756	-
Critical Hdwy	4.14	-	-	4.14	-	-	7.54	6.54	-	7.54	6.54	-
Critical Hdwy Stg 1	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Follow-up Hdwy	2.22	-	-	2.22	-	-	3.52	4.02	-	3.52	4.02	-
Pot Cap-1 Maneuver	939	-	-	862	-	-	169	136	0	185	137	0
Stage 1	-	-	-	-	-	-	366	414	0	423	462	0
Stage 2	-	-	-	-	-	-	652	458	0	608	414	0
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	939	-	-	862	-	-	166	133	-	181	134	-
Mov Cap-2 Maneuver	-	-	-	-	-	-	166	133	-	181	134	-
Stage 1	-	-	-	-	-	-	363	410	-	419	457	-
Stage 2	-	-	-	-	-	-	644	453	-	601	410	-

Approach	EB	WB		NB		SB						
HCM Control Delay, s	0.1	0.1		28.6		26.7						
HCM LOS				D		D						
<hr/>												
Minor Lane/Major Mvmt	NBLn1	NBLn2	NBLn3	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1	SBLn2	SBLn3
Capacity (veh/h)	166	133	-	939	-	-	862	-	-	181	134	-
HCM Lane V/C Ratio	0.063	0.008	-	0.009	-	-	0.011	-	-	0.023	0.008	-
HCM Control Delay (s)	28.2	32.3	0	8.9	-	-	9.2	-	-	25.4	32.1	0
HCM Lane LOS	D	D	A	A	-	-	A	-	-	D	D	A
HCM 95th %tile Q(veh)	0.2	0	-	0	-	-	0	-	-	0.1	0	-

## Timings

2042 Baseline Traffic

## 6: Banning Lewis Pkwy &amp; Briargate Pkwy

PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	1	406	307	270	377	9	242	28	285	5	16	1
Future Volume (vph)	1	406	307	270	377	9	242	28	285	5	16	1
Turn Type	pm+pt	NA	Free	Prot	NA	Perm	Prot	NA	Free	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		Free			6			Free	4		4
Detector Phase	5	2		1	6	6	3	8		7	4	4
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0	15.0	8.0	10.0		8.0	10.0	10.0
Minimum Split (s)	15.0	20.0		20.0	20.0	20.0	13.0	15.0		13.0	15.0	15.0
Total Split (s)	15.0	38.0		25.0	48.0	48.0	32.0	43.0		14.0	25.0	25.0
Total Split (%)	12.5%	31.7%		20.8%	40.0%	40.0%	26.7%	35.8%		11.7%	20.8%	20.8%
Yellow Time (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0		0.0	-2.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0		5.0	3.0	5.0	5.0	5.0		5.0	5.0	5.0
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Act Effect Green (s)	45.8	39.8	120.0	15.2	57.4	55.4	14.2	49.4	120.0	40.8	32.8	32.8
Actuated g/C Ratio	0.38	0.33	1.00	0.13	0.48	0.46	0.12	0.41	1.00	0.34	0.27	0.27
v/c Ratio	0.00	0.36	0.20	0.66	0.23	0.01	0.63	0.02	0.19	0.01	0.02	0.00
Control Delay	17.0	32.2	0.3	57.1	19.6	0.0	57.1	23.1	0.3	20.4	33.7	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	17.0	32.2	0.3	57.1	19.6	0.0	57.1	23.1	0.3	20.4	33.7	0.0
LOS	B	C	A	E	B	A	E	C	A	C	C	A
Approach Delay		18.4			34.8			26.2			29.3	
Approach LOS		B			C			C			C	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.66

Intersection Signal Delay: 26.3


Intersection LOS: C

Intersection Capacity Utilization 45.4%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 6: Banning Lewis Pkwy &amp; Briargate Pkwy



Timings  
11: Black Forest Rd & Research Pkwy

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	250	664	100	100	524	461	125	770	100	353	324	270
Future Volume (vph)	250	664	100	100	524	461	125	770	100	353	324	270
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free	2		Free			Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	15.0		5.0	15.0	
Minimum Split (s)	10.0	23.0		10.0	23.0		10.0	23.0		10.0	23.0	
Total Split (s)	23.0	44.0		15.0	36.0		12.0	39.0		22.0	49.0	
Total Split (%)	19.2%	36.7%		12.5%	30.0%		10.0%	32.5%		18.3%	40.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	45.7	31.4	120.0	33.1	23.9	120.0	51.0	41.9	120.0	17.4	50.2	120.0
Actuated g/C Ratio	0.38	0.26	1.00	0.28	0.20	1.00	0.42	0.35	1.00	0.14	0.42	1.00
v/c Ratio	0.82	0.75	0.07	0.48	0.78	0.31	0.27	0.66	0.07	0.75	0.23	0.18
Control Delay	49.3	46.0	0.1	31.6	53.7	0.5	18.6	46.9	0.1	48.9	23.2	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	49.3	46.0	0.1	31.6	53.7	0.5	18.6	46.9	0.1	48.9	23.2	0.2
LOS	D	D	A	C	D	A	B	D	A	D	C	A
Approach Delay		42.3			29.1			38.6			26.2	
Approach LOS		D			C			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.82

Intersection Signal Delay: 34.1


Intersection LOS: C

Intersection Capacity Utilization 76.4%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 11: Black Forest Rd & Research Pkwy



Timings  
12: Vollmer Rd & Marksheffel Rd

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	69	701	91	83	613	131	90	315	92	108	63	158
Future Volume (vph)	69	701	91	83	613	131	90	315	92	108	63	158
Turn Type	pm+pt	NA	Perm									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0
Total Split (s)	20.0	56.0	56.0	19.0	55.0	55.0	15.0	30.0	30.0	15.0	30.0	30.0
Total Split (%)	16.7%	46.7%	46.7%	15.8%	45.8%	45.8%	12.5%	25.0%	25.0%	12.5%	25.0%	25.0%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max	Max	None	Max	Max
Act Effect Green (s)	64.6	56.9	56.9	66.4	59.5	59.5	34.7	25.7	25.7	35.3	25.9	25.9
Actuated g/C Ratio	0.54	0.47	0.47	0.55	0.50	0.50	0.29	0.21	0.21	0.29	0.22	0.22
v/c Ratio	0.17	0.44	0.12	0.23	0.37	0.16	0.23	0.44	0.23	0.36	0.09	0.35
Control Delay	12.0	22.2	3.0	10.8	17.1	2.2	30.0	43.3	7.1	32.3	38.6	8.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	12.0	22.2	3.0	10.8	17.1	2.2	30.0	43.3	7.1	32.3	38.6	8.1
LOS	B	C	A	B	B	A	C	D	A	C	D	A
Approach Delay		19.3				14.1			34.2			21.9
Approach LOS		B				B			C			C

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.44

Intersection Signal Delay: 20.9


Intersection LOS: C

Intersection Capacity Utilization 55.3%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 12: Vollmer Rd & Marksheffel Rd



Timings  
13: Sterling Ranch Rd & Marksheffel Rd

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBT	EBR	WBL	WBT	NBL	NBT	NBR	SBL	SBT	SBR	Ø5
Lane Configurations	↑↑	↑	↑	↑↑	↑	↑	↑	↑	↑	↑	
Traffic Volume (vph)	862	22	78	800	27	6	37	1	9	1	
Future Volume (vph)	862	22	78	800	27	6	37	1	9	1	
Turn Type	NA	Perm	pm+pt	NA	pm+pt	NA	Perm	Prot	NA	Perm	
Protected Phases	2			1	6	3	8		7	4	5
Permitted Phases				2	6		8		8		4
Detector Phase	2	2	1	6	3	8	8	7	4	4	
Switch Phase											
Minimum Initial (s)	15.0	15.0	5.0	15.0	5.0	10.0	10.0	20.0	10.0	10.0	5.0
Minimum Split (s)	20.0	20.0	10.0	20.0	10.0	15.0	15.0	25.0	20.0	20.0	10.0
Total Split (s)	68.0	68.0	12.0	60.0	10.0	15.0	15.0	25.0	30.0	30.0	20.0
Total Split (%)	56.7%	56.7%	10.0%	50.0%	8.3%	12.5%	12.5%	20.8%	25.0%	25.0%	17%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lag	Lag	Lead	Lag	Lead	Lag	Lag	Lead	Lag	Lag	Lead
Lead-Lag Optimize?	Yes	Yes									
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None	None	None	None	None
Act Effect Green (s)	92.9	92.9	101.0	103.0	9.0	10.0	10.0	20.0	13.0	13.0	
Actuated g/C Ratio	0.77	0.77	0.84	0.86	0.08	0.08	0.08	0.17	0.11	0.11	
v/c Ratio	0.33	0.02	0.17	0.28	0.23	0.04	0.12	0.00	0.04	0.00	
Control Delay	5.2	0.0	4.8	4.1	48.0	51.3	0.8	42.0	44.6	0.0	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	5.2	0.0	4.8	4.1	48.0	51.3	0.8	42.0	44.6	0.0	
LOS	A	A	A	A	D	D	A	D	D	A	
Approach Delay	5.0				4.2		23.1		40.3		
Approach LOS	A				A		C		D		

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.33

Intersection Signal Delay: 5.5


Intersection LOS: A

Intersection Capacity Utilization 53.0%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 13: Sterling Ranch Rd & Marksheffel Rd



Timings  
14: Black Forest Rd & Vollmer Rd

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑	↑	↑↑	↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	10	12	21	291	13	195	58	1010	496	110	700	23
Future Volume (vph)	10	12	21	291	13	195	58	1010	496	110	700	23
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4			4		8	2		2	6		6
Detector Phase	7	4	4	3	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)	5.0	10.0	10.0	5.0	10.0	10.0	5.0	15.0	15.0	5.0	15.0	15.0
Minimum Split (s)	10.0	15.0	15.0	10.0	15.0	15.0	10.0	20.0	20.0	10.0	20.0	20.0
Total Split (s)	12.0	23.0	23.0	33.0	44.0	44.0	12.0	52.0	52.0	12.0	52.0	52.0
Total Split (%)	10.0%	19.2%	19.2%	27.5%	36.7%	36.7%	10.0%	43.3%	43.3%	10.0%	43.3%	43.3%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max						
Act Effect Green (s)	12.1	10.0	10.0	16.0	22.6	22.6	78.1	71.2	71.2	82.8	75.2	75.2
Actuated g/C Ratio	0.10	0.08	0.08	0.13	0.19	0.19	0.65	0.59	0.59	0.69	0.63	0.63
v/c Ratio	0.07	0.08	0.08	0.67	0.04	0.44	0.13	0.51	0.46	0.34	0.33	0.02
Control Delay	33.9	52.2	0.6	56.7	36.8	8.5	4.8	14.0	3.8	12.3	18.8	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	33.9	52.2	0.6	56.7	36.8	8.5	4.8	14.0	3.8	12.3	18.8	0.4
LOS	C	D	A	E	D	A	A	B	A	B	B	A
Approach Delay		23.1			37.3			10.4			17.4	
Approach LOS		C			D			B			B	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.67

Intersection Signal Delay: 17.2


Intersection LOS: B

Intersection Capacity Utilization 61.5%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 14: Black Forest Rd & Vollmer Rd



Timings  
15: Black Forest Rd & Woodmen Rd

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑↑	↑
Traffic Volume (vph)	550	2407	360	201	1748	300	300	286	263	300	222	619
Future Volume (vph)	550	2407	360	201	1748	300	300	286	263	300	222	619
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0		8.0	10.0		8.0	10.0	
Minimum Split (s)	13.0	20.0		13.0	20.0		13.0	15.0		13.0	15.0	
Total Split (s)	31.0	63.0		17.0	49.0		19.0	23.0		17.0	21.0	
Total Split (%)	25.8%	52.5%		14.2%	40.8%		15.8%	19.2%		14.2%	17.5%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0		-1.0	-3.0		-1.0	-2.0		-1.0	-2.0	
Total Lost Time (s)	4.0	2.0		4.0	2.0		4.0	3.0		4.0	3.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	24.6	61.8	120.0	12.2	49.4	120.0	14.5	20.0	120.0	13.0	18.5	120.0
Actuated g/C Ratio	0.20	0.52	1.00	0.10	0.41	1.00	0.12	0.17	1.00	0.11	0.15	1.00
v/c Ratio	0.80	0.94	0.23	0.59	0.85	0.19	0.74	0.50	0.17	0.82	0.29	0.40
Control Delay	54.4	35.9	0.3	71.9	21.4	0.2	62.1	48.7	0.2	78.3	42.4	2.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.4	35.9	0.3	71.9	21.4	0.2	62.1	48.7	0.2	78.3	42.4	2.3
LOS	D	D	A	E	C	A	E	D	A	E	D	A
Approach Delay			35.1			23.1			38.4			30.1
Approach LOS			D			C			D			C

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.94

Intersection Signal Delay: 31.1


Intersection LOS: C

Intersection Capacity Utilization 83.4%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 15: Black Forest Rd & Woodmen Rd



Timings  
16: Marksheffel Rd & Woodmen Rd

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑↑	↑	↑↑	↑↑↑↑	↑	↑↑	↑↑↑↑	↑	↑↑	↑↑↑↑	↑
Traffic Volume (vph)	388	1917	665	447	1626	193	491	147	467	314	155	132
Future Volume (vph)	388	1917	665	447	1626	193	491	147	467	314	155	132
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+ov	Prot	NA	Free
Protected Phases	5	2		1	6		3	8	1	7	4	
Permitted Phases			Free			Free			8			Free
Detector Phase	5	2		1	6		3	8	1	7	4	
Switch Phase												
Minimum Initial (s)	4.0	4.0		4.0	4.0		4.0	4.0	4.0	4.0	4.0	
Minimum Split (s)	9.0	11.0		9.0	11.0		9.0	10.0	9.0	9.0	10.0	
Total Split (s)	25.0	51.0		22.0	48.0		23.0	26.0	22.0	21.0	24.0	
Total Split (%)	20.8%	42.5%		18.3%	40.0%		19.2%	21.7%	18.3%	17.5%	20.0%	
Yellow Time (s)	3.0	5.0		3.0	5.0		3.0	4.0	3.0	3.0	4.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0		-1.0	-3.0		-1.0	-2.0	0.0	-1.0	-2.0	
Total Lost Time (s)	4.0	4.0		4.0	4.0		4.0	4.0	5.0	4.0	4.0	
Lead/Lag	Lead	Lag		Lead	Lag		Lead	Lag	Lead	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	Yes	
Recall Mode	None	C-Max		None	C-Max		None	None	None	None	None	
Act Effect Green (s)	19.9	50.3	120.0	22.0	52.4	120.0	19.0	15.8	40.7	15.9	12.7	120.0
Actuated g/C Ratio	0.17	0.42	1.00	0.18	0.44	1.00	0.16	0.13	0.34	0.13	0.11	1.00
v/c Ratio	0.69	0.92	0.43	0.73	0.75	0.12	0.92	0.32	0.81	0.70	0.42	0.09
Control Delay	56.0	25.5	0.4	53.4	31.8	0.2	73.7	49.2	41.1	58.5	53.3	0.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.0	25.5	0.4	53.4	31.8	0.2	73.7	49.2	41.1	58.5	53.3	0.1
LOS	E	C	A	D	C	A	E	D	D	E	D	A
Approach Delay		23.9			33.4			56.6			44.3	
Approach LOS		C			C			E			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green, Master Intersection

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.92

Intersection Signal Delay: 34.0


Intersection LOS: C

Intersection Capacity Utilization 85.7%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 16: Marksheffel Rd & Woodmen Rd



Timings  
17: Banning Lewis Pkwy & Woodmen Rd

2042 Baseline Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	354	1285	844	437	1040	45	769	323	308	40	326	387
Future Volume (vph)	354	1285	844	437	1040	45	769	323	308	40	326	387
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	10.0		5.0	10.0	
Minimum Split (s)	10.0	20.0		10.0	20.0		10.0	15.0		10.0	15.0	
Total Split (s)	23.0	37.0		20.0	34.0		32.0	51.0		12.0	31.0	
Total Split (%)	19.2%	30.8%		16.7%	28.3%		26.7%	42.5%		10.0%	25.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-2.0	-3.0		-2.0	-3.0		-1.0	-2.0		-1.0	-2.0	
Total Lost Time (s)	3.0	2.0		3.0	2.0		4.0	3.0		4.0	3.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	18.6	35.0	120.0	17.0	33.4	120.0	28.0	50.6	120.0	7.5	28.0	120.0
Actuated g/C Ratio	0.16	0.29	1.00	0.14	0.28	1.00	0.23	0.42	1.00	0.06	0.23	1.00
v/c Ratio	0.68	0.88	0.54	0.92	0.75	0.03	0.98	0.22	0.20	0.19	0.40	0.25
Control Delay	54.7	48.9	1.3	75.9	43.7	0.0	73.3	23.4	0.3	55.3	40.7	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.7	48.9	1.3	75.9	43.7	0.0	73.3	23.4	0.3	55.3	40.7	0.4
LOS	D	D	A	E	D	A	E	C	A	E	D	A
Approach Delay		33.6			51.7			45.7			20.8	
Approach LOS		C			D			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.98

Intersection Signal Delay: 39.2


Intersection LOS: D

Intersection Capacity Utilization 81.6%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 17: Banning Lewis Pkwy & Woodmen Rd



Intersection

Intersection Delay, s/veh 8.2

Intersection LOS A

Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	129	586	324	279
Demand Flow Rate, veh/h	131	597	330	284
Vehicles Circulating, veh/h	385	268	120	525
Vehicles Exiting, veh/h	424	116	396	340
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	5.3	10.8	3.9	8.7
Approach LOS	A	B	A	A

Lane	Left	Left	Left	Bypass	Left
Designated Moves	LTR	LTR	LT	R	LTR
Assumed Moves	LTR	LTR	LT	R	LTR
RT Channelized				Free	
Lane Util	1.000	1.000	1.000		1.000
Follow-Up Headway, s	2.609	2.609	2.609		2.609
Critical Headway, s	4.976	4.976	4.976	66	4.976
Entry Flow, veh/h	131	597	264	1938	284
Cap Entry Lane, veh/h	932	1050	1221	0.980	808
Entry HV Adj Factor	0.982	0.981	0.980	65	0.981
Flow Entry, veh/h	129	586	259	1900	279
Cap Entry, veh/h	915	1030	1197	0.034	793
V/C Ratio	0.141	0.569	0.216	0.0	0.352
Control Delay, s/veh	5.3	10.8	4.9	A	8.7
LOS	A	B	A	0	A
95th %tile Queue, veh	0	4	1		2

Intersection						
Int Delay, s/veh	0.4					
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B		A		
Traffic Vol, veh/h	13	5	248	5	2	367
Future Vol, veh/h	13	5	248	5	2	367
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	14	5	261	5	2	386
Major/Minor	Minor1	Major1		Major2		
Conflicting Flow All	654	264	0	0	266	0
Stage 1	264	-	-	-	-	-
Stage 2	390	-	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218	-
Pot Cap-1 Maneuver	431	775	-	-	1298	-
Stage 1	780	-	-	-	-	-
Stage 2	684	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	430	775	-	-	1298	-
Mov Cap-2 Maneuver	430	-	-	-	-	-
Stage 1	780	-	-	-	-	-
Stage 2	683	-	-	-	-	-
Approach	WB	NB		SB		
HCM Control Delay, s	12.6	0		0		
HCM LOS	B					
Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT	
Capacity (veh/h)	-	-	491	1298	-	
HCM Lane V/C Ratio	-	-	0.039	0.002	-	
HCM Control Delay (s)	-	-	12.6	7.8	0	
HCM Lane LOS	-	-	B	A	A	
HCM 95th %tile Q(veh)	-	-	0.1	0	-	

Timings  
3: Black Forest Rd & Briarate Pkwy

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	150	466	350	97	1054	120	509	314	45	62	644	65
Future Volume (vph)	150	466	350	97	1054	120	509	314	45	62	644	65
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0		8.0	15.0		8.0	15.0	
Minimum Split (s)	13.0	23.0		13.0	23.0		15.0	23.0		13.0	23.0	
Total Split (s)	15.0	40.0		22.0	47.0		25.0	46.0		13.0	33.0	
Total Split (%)	12.4%	33.1%		18.2%	38.8%		20.7%	38.0%		10.7%	27.3%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	51.1	41.1	121.0	50.6	40.9	121.0	20.3	44.7	121.0	37.8	29.8	121.0
Actuated g/C Ratio	0.42	0.34	1.00	0.42	0.34	1.00	0.17	0.37	1.00	0.31	0.25	1.00
v/c Ratio	0.76	0.41	0.23	0.27	0.93	0.08	0.93	0.25	0.03	0.18	0.78	0.04
Control Delay	48.8	31.9	0.3	20.3	52.5	0.1	73.9	28.4	0.0	21.7	49.9	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	48.8	31.9	0.3	20.3	52.5	0.1	73.9	28.4	0.0	21.7	49.9	0.0
LOS	D	C	A	C	D	A	E	C	A	C	D	A
Approach Delay		23.1			45.1			53.6			43.4	
Approach LOS		C			D			D			D	

Intersection Summary

Cycle Length: 121

Actuated Cycle Length: 121

Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.93

Intersection Signal Delay: 41.2


Intersection LOS: D

Intersection Capacity Utilization 86.4%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 3: Black Forest Rd & Briarate Pkwy



Timings  
4: Vollmer Rd & Briargate Pkwy

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	69	548	64	239	1024	96	90	132	111	121	305	138
Future Volume (vph)	69	548	64	239	1024	96	90	132	111	121	305	138
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2			6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	15.0	15.0	15.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	20.0	20.0	20.0	20.0	20.0	10.0	10.0	10.0	10.0	10.0	10.0
Total Split (s)	12.0	57.0	57.0	20.0	65.0	65.0	17.0	28.0	28.0	15.0	26.0	26.0
Total Split (%)	10.0%	47.5%	47.5%	16.7%	54.2%	54.2%	14.2%	23.3%	23.3%	12.5%	21.7%	21.7%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0	0.0	0.0	-2.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0	5.0	5.0	3.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	Max	Max	None	Max	Max	None	None	None	None	None	None
Act Effect Green (s)	58.8	54.1	52.1	15.0	64.8	62.8	25.7	16.0	16.0	25.3	15.7	15.7
Actuated g/C Ratio	0.52	0.48	0.46	0.13	0.57	0.56	0.23	0.14	0.14	0.22	0.14	0.14
v/c Ratio	0.25	0.33	0.08	0.55	0.53	0.11	0.38	0.27	0.33	0.39	0.65	0.41
Control Delay	11.9	19.5	0.2	51.7	17.3	2.8	35.6	44.0	5.1	35.9	52.5	9.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	11.9	19.5	0.2	51.7	17.3	2.8	35.6	44.0	5.1	35.9	52.5	9.4
LOS	B	B	A	D	B	A	D	D	A	D	D	A
Approach Delay		16.8			22.4			28.6			38.4	
Approach LOS		B			C			C			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 112.7

Natural Cycle: 60

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 0.65

Intersection Signal Delay: 24.9


Intersection LOS: C

Intersection Capacity Utilization 61.7%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 4: Vollmer Rd & Briargate Pkwy



Timings  
5: Sterling Ranch Rd & Briargate Pkwy

2042 Total Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑	↑	↑	↑↑	↑
Traffic Volume (vph)	77	624	137	103	945	24	269	115	120	103	263	158
Future Volume (vph)	77	624	137	103	945	24	269	115	120	103	263	158
Turn Type	pm+pt	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		Free	4		Free
Detector Phase	5	2	2	1	6	6	3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	20.0		5.0	20.0	
Minimum Split (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	25.0		10.0	25.0	
Total Split (s)	12.0	56.0	56.0	12.0	56.0	56.0	20.0	32.0		20.0	32.0	
Total Split (%)	10.0%	46.7%	46.7%	10.0%	46.7%	46.7%	16.7%	26.7%		16.7%	26.7%	
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-2.0	-2.0	0.0	0.0	-2.0	0.0	0.0	0.0		0.0	0.0	
Total Lost Time (s)	3.0	3.0	5.0	5.0	3.0	5.0	5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag	Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes		Yes	Yes								
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max		None	Max	
Act Effect Green (s)	61.9	53.1	51.1	59.0	55.4	53.4	45.9	31.7	120.0	37.5	27.3	120.0
Actuated g/C Ratio	0.52	0.44	0.43	0.49	0.46	0.44	0.38	0.26	1.00	0.31	0.23	1.00
v/c Ratio	0.31	0.42	0.19	0.32	0.61	0.03	0.79	0.25	0.08	0.25	0.65	0.10
Control Delay	16.4	24.0	4.0	7.2	14.8	0.5	45.2	37.3	0.1	25.7	50.6	0.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	16.4	24.0	4.0	7.2	14.8	0.5	45.2	37.3	0.1	25.7	50.6	0.1
LOS	B	C	A	A	B	A	D	D	A	C	D	A
Approach Delay		20.0				13.7			32.7			30.5
Approach LOS		C				B			C			C

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 63 (53%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 65

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.79

Intersection Signal Delay: 21.8


Intersection LOS: C

Intersection Capacity Utilization 77.0%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 5: Sterling Ranch Rd & Briargate Pkwy



## Timings

## 6: Banning Lewis Pkwy &amp; Briargate Pkwy

2042 Total Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	2	488	352	300	661	13	312	61	291	53	200	2
Future Volume (vph)	2	488	352	300	661	13	312	61	291	53	200	2
Turn Type	pm+pt	NA	Free	Prot	NA	Perm	Prot	NA	Free	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		Free			6			Free	4		4
Detector Phase	5	2		1	6	6	3	8		7	4	4
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0	15.0	8.0	10.0		8.0	10.0	10.0
Minimum Split (s)	15.0	20.0		20.0	20.0	20.0	13.0	15.0		13.0	15.0	15.0
Total Split (s)	12.0	43.0		20.0	51.0	51.0	32.0	45.0		12.0	25.0	25.0
Total Split (%)	10.0%	35.8%		16.7%	42.5%	42.5%	26.7%	37.5%		10.0%	20.8%	20.8%
Yellow Time (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0		0.0	-2.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0		5.0	3.0	5.0	5.0	5.0		5.0	5.0	5.0
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Act Effect Green (s)	45.7	40.7	120.0	14.3	57.6	55.6	16.8	42.4	120.0	37.2	30.2	30.2
Actuated g/C Ratio	0.38	0.34	1.00	0.12	0.48	0.46	0.14	0.35	1.00	0.31	0.25	0.25
v/c Ratio	0.01	0.43	0.23	0.77	0.41	0.02	0.68	0.05	0.19	0.13	0.24	0.00
Control Delay	12.5	20.0	0.3	64.5	21.8	0.1	55.5	29.1	0.3	22.0	37.4	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	12.5	20.0	0.3	64.5	21.8	0.1	55.5	29.1	0.3	22.0	37.4	0.0
LOS	B	B	A	E	C	A	E	C	A	C	D	A
Approach Delay		11.7			34.6			28.9			34.0	
Approach LOS		B			C			C			C	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.77

Intersection Signal Delay: 26.1


Intersection LOS: C

Intersection Capacity Utilization 58.0%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 6: Banning Lewis Pkwy &amp; Briargate Pkwy



Intersection

Int Delay, s/veh 1.1

Movement	WBL	WBR	NBT	NBR	SBL	SBT
----------	-----	-----	-----	-----	-----	-----

Lane Configurations	↖ ↗ ↘ ↗ ↖ ↘ ↗					
Traffic Vol, veh/h	43	48	285	26	10	597
Future Vol, veh/h	43	48	285	26	10	597
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	155	205	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	45	51	300	27	11	628

Major/Minor	Minor1	Major1	Major2
-------------	--------	--------	--------

Conflicting Flow All	636	150	0	0	327	0
Stage 1	300	-	-	-	-	-
Stage 2	336	-	-	-	-	-
Critical Hdwy	6.84	6.94	-	-	4.14	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	-	-	2.22	-
Pot Cap-1 Maneuver	410	870	-	-	1229	-
Stage 1	725	-	-	-	-	-
Stage 2	696	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	406	870	-	-	1229	-
Mov Cap-2 Maneuver	508	-	-	-	-	-
Stage 1	725	-	-	-	-	-
Stage 2	690	-	-	-	-	-

Approach	WB	NB	SB
----------	----	----	----

HCM Control Delay, s	11	0	0.1
HCM LOS	B		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	WBLn2	SBL	SBT
-----------------------	-----	-----	-------	-------	-----	-----

Capacity (veh/h)	-	-	508	870	1229	-
HCM Lane V/C Ratio	-	-	0.089	0.058	0.009	-
HCM Control Delay (s)	-	-	12.8	9.4	8	-
HCM Lane LOS	-	-	B	A	A	-
HCM 95th %tile Q(veh)	-	-	0.3	0.2	0	-

Intersection												
Int Delay, s/veh	7.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑	↑↑	↑↑	↑	↑↑	↑↑	
Traffic Vol, veh/h	125	58	102	165	0	186	0	366	110	63	245	3
Future Vol, veh/h	125	58	102	165	0	186	0	366	110	63	245	3
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	0	-	0	0	-	0	-	-	205	205	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	95	95	95	95	95	95	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	132	61	107	174	0	196	0	385	116	66	258	3
Major/Minor	Minor2	Minor1			Major1			Major2				
Conflicting Flow All	585	893	131	677	-	193	-	0	0	501	0	0
Stage 1	392	392	-	385	-	-	-	-	-	-	-	-
Stage 2	193	501	-	292	-	-	-	-	-	-	-	-
Critical Hdwy	7.54	6.54	6.94	7.54	-	6.94	-	-	-	4.14	-	-
Critical Hdwy Stg 1	6.54	5.54	-	6.54	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.54	5.54	-	6.54	-	-	-	-	-	-	-	-
Follow-up Hdwy	3.52	4.02	3.32	3.52	-	3.32	-	-	-	2.22	-	-
Pot Cap-1 Maneuver	394	279	894	339	0	816	0	-	-	1059	-	-
Stage 1	604	605	-	610	0	-	0	-	-	-	-	-
Stage 2	790	541	-	692	0	-	0	-	-	-	-	-
Platoon blocked, %							-	-	-	-	-	-
Mov Cap-1 Maneuver	285	262	894	247	-	816	-	-	-	1059	-	-
Mov Cap-2 Maneuver	388	354	-	364	-	-	-	-	-	-	-	-
Stage 1	604	567	-	610	-	-	-	-	-	-	-	-
Stage 2	600	541	-	509	-	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	15.3			16.8			0			1.7		
HCM LOS	C			C			A			C		
Minor Lane/Major Mvmt	NBT	NBR	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	SBL	SBT	SBR		
Capacity (veh/h)	-	-	388	354	894	364	816	1059	-	-		
HCM Lane V/C Ratio	-	-	0.339	0.172	0.12	0.477	0.24	0.063	-	-		
HCM Control Delay (s)	-	-	19	17.3	9.6	23.6	10.8	8.6	-	-		
HCM Lane LOS	-	-	C	C	A	C	B	A	-	-		
HCM 95th %tile Q(veh)	-	-	1.5	0.6	0.4	2.5	0.9	0.2	-	-		

Timings  
9: Banning Lewis Pkwy & E-W Collector

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (vph)	19	273	124	645	802	50
Future Volume (vph)	19	273	124	645	802	50
Turn Type	Prot	Free	pm+pt	NA	NA	Perm
Protected Phases	4		5	2	6	
Permitted Phases		Free		2		6
Detector Phase	4		5	2	6	6
Switch Phase						
Minimum Initial (s)	15.0		8.0	15.0	15.0	15.0
Minimum Split (s)	20.0		13.0	20.0	20.0	20.0
Total Split (s)	30.0		12.0	90.0	78.0	78.0
Total Split (%)	25.0%		10.0%	75.0%	65.0%	65.0%
Yellow Time (s)	3.0		3.0	3.0	3.0	3.0
All-Red Time (s)	2.0		2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0		5.0	5.0	5.0	5.0
Lead/Lag		Lead		Lag		Lag
Lead-Lag Optimize?		Yes		Yes		Yes
Recall Mode	None		None	C-Max	C-Max	C-Max
Act Effect Green (s)	15.0	120.0	107.0	110.0	93.8	93.8
Actuated g/C Ratio	0.12	1.00	0.89	0.92	0.78	0.78
v/c Ratio	0.09	0.18	0.23	0.21	0.31	0.04
Control Delay	47.7	0.3	2.6	1.8	7.3	3.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.7	0.3	2.6	1.8	7.3	3.2
LOS	D	A	A	A	A	A
Approach Delay	3.3			1.9	7.0	
Approach LOS	A			A	A	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green

Natural Cycle: 55

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.31

Intersection Signal Delay: 4.4

Intersection LOS: A

Intersection Capacity Utilization 54.0%

ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 9: Banning Lewis Pkwy & E-W Collector



Intersection																			
Int Delay, s/veh	1.9																		
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR							
Lane Configurations	↑ ↗	↑ ↘	↗ ↙	↖ ↗	↑ ↗	↗ ↙	↙ ↖	↖ ↖	↙ ↖	↖ ↗	↑ ↗	↗ ↙							
Traffic Vol, veh/h	25	299	7	3	542	14	21	1	9	27	0	68							
Future Vol, veh/h	25	299	7	3	542	14	21	1	9	27	0	68							
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0							
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop							
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None							
Storage Length	205	-	155	205	-	-	-	-	-	-	-	155							
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-							
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-							
Peak Hour Factor	95	95	95	95	95	95	95	95	95	95	95	95							
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2							
Mvmt Flow	26	315	7	3	571	15	22	1	9	28	0	72							
Major/Minor																			
Major1		Major2			Minor1			Minor2											
Conflicting Flow All	586	0	0	322	0	0	659	959	158	795	959	293							
Stage 1	-	-	-	-	-	-	367	367	-	585	585	-							
Stage 2	-	-	-	-	-	-	292	592	-	210	374	-							
Critical Hdwy	4.14	-	-	4.14	-	-	7.54	6.54	6.94	7.54	6.54	6.94							
Critical Hdwy Stg 1	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-							
Critical Hdwy Stg 2	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-							
Follow-up Hdwy	2.22	-	-	2.22	-	-	3.52	4.02	3.32	3.52	4.02	3.32							
Pot Cap-1 Maneuver	985	-	-	1235	-	-	349	256	859	278	256	703							
Stage 1	-	-	-	-	-	-	625	621	-	464	496	-							
Stage 2	-	-	-	-	-	-	692	492	-	773	616	-							
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-							
Mov Cap-1 Maneuver	985	-	-	1235	-	-	306	249	859	268	249	703							
Mov Cap-2 Maneuver	-	-	-	-	-	-	306	249	-	268	249	-							
Stage 1	-	-	-	-	-	-	609	605	-	452	495	-							
Stage 2	-	-	-	-	-	-	620	491	-	743	600	-							
Approach																			
EB			WB			NB			SB										
HCM Control Delay, s	0.7		0			15.6			13.3										
HCM LOS	C						B												
Minor Lane/Major Mvmt																			
NBLn1		EBL	EBT	EBR	WBL	WBT	WBR	SBLn1	SBLn2										
Capacity (veh/h)	373	985	-	-	1235	-	-	268	703										
HCM Lane V/C Ratio	0.087	0.027	-	-	0.003	-	-	0.106	0.102										
HCM Control Delay (s)	15.6	8.8	-	-	7.9	-	-	20	10.7										
HCM Lane LOS	C	A	-	-	A	-	-	C	B										
HCM 95th %tile Q(veh)	0.3	0.1	-	-	0	-	-	0.4	0.3										

Timings  
11: Black Forest Rd & Research Pkwy

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	200	527	100	100	705	248	275	366	100	349	450	375
Future Volume (vph)	200	527	100	100	705	248	275	366	100	349	450	375
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free	2		Free			Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	15.0		8.0	15.0	
Minimum Split (s)	10.0	23.0		10.0	23.0		10.0	23.0		15.0	23.0	
Total Split (s)	19.0	44.0		15.0	40.0		12.0	36.0		25.0	49.0	
Total Split (%)	15.8%	36.7%		12.5%	33.3%		10.0%	30.0%		20.8%	40.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	47.8	34.3	120.0	39.2	30.0	120.0	50.0	39.0	120.0	17.5	45.5	120.0
Actuated g/C Ratio	0.40	0.29	1.00	0.33	0.25	1.00	0.42	0.32	1.00	0.15	0.38	1.00
v/c Ratio	0.81	0.55	0.07	0.36	0.84	0.16	0.64	0.33	0.07	0.74	0.35	0.25
Control Delay	50.8	38.1	0.1	25.5	51.8	0.2	33.4	36.2	0.1	58.1	28.1	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	50.8	38.1	0.1	25.5	51.8	0.2	33.4	36.2	0.1	58.1	28.1	0.4
LOS	D	D	A	C	D	A	C	D	A	E	C	A
Approach Delay		36.6			37.2			30.3			28.2	
Approach LOS		D			D			C			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.84

Intersection Signal Delay: 32.9


Intersection LOS: C

Intersection Capacity Utilization 75.0%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 11: Black Forest Rd & Research Pkwy



Timings  
12: Vollmer Rd & Marksheffel Rd

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	72	836	42	148	922	70	115	170	94	120	388	132
Future Volume (vph)	72	836	42	148	922	70	115	170	94	120	388	132
Turn Type	pm+pt	NA	Perm									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0
Total Split (s)	12.0	66.0	66.0	12.0	66.0	66.0	12.0	30.0	30.0	12.0	30.0	30.0
Total Split (%)	10.0%	55.0%	55.0%	10.0%	55.0%	55.0%	10.0%	25.0%	25.0%	10.0%	25.0%	25.0%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max	Max	None	Max	Max
Act Effect Green (s)	67.7	61.0	61.0	69.0	63.4	63.4	32.0	25.0	25.0	32.0	25.0	25.0
Actuated g/C Ratio	0.56	0.51	0.51	0.58	0.53	0.53	0.27	0.21	0.21	0.27	0.21	0.21
v/c Ratio	0.25	0.49	0.05	0.47	0.52	0.08	0.51	0.24	0.24	0.36	0.55	0.32
Control Delay	11.9	20.5	0.1	13.2	9.3	0.2	39.9	40.7	7.6	35.1	45.8	8.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	11.9	20.5	0.1	13.2	9.3	0.2	39.9	40.7	7.6	35.1	45.8	8.5
LOS	B	C	A	B	A	A	D	D	A	D	D	A
Approach Delay		18.9			9.3				32.2			36.1
Approach LOS		B			A			C				D

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.55

Intersection Signal Delay: 20.5


Intersection LOS: C

Intersection Capacity Utilization 65.1%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 12: Vollmer Rd & Marksheffel Rd



Timings  
13: Sterling Ranch Rd & Marksheffel Rd

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑	↑	↑↑	↑	↑
Traffic Volume (vph)	139	900	10	47	809	171	39	8	55	460	9	292
Future Volume (vph)	139	900	10	47	809	171	39	8	55	460	9	292
Turn Type	pm+pt	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm	Prot	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		8			4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	5.0	15.0	15.0	5.0	10.0	10.0	20.0	10.0	10.0
Minimum Split (s)	10.0	20.0	20.0	10.0	20.0	20.0	10.0	15.0	15.0	25.0	20.0	20.0
Total Split (s)	12.0	51.0	51.0	12.0	51.0	51.0	12.0	25.0	25.0	32.0	45.0	45.0
Total Split (%)	10.0%	42.5%	42.5%	10.0%	42.5%	42.5%	10.0%	20.8%	20.8%	26.7%	37.5%	37.5%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	None	None	None	None	None
Act Effect Green (s)	74.1	65.6	65.6	67.4	60.5	60.5	14.6	10.0	10.0	22.7	25.1	25.1
Actuated g/C Ratio	0.62	0.55	0.55	0.56	0.50	0.50	0.12	0.08	0.08	0.19	0.21	0.21
v/c Ratio	0.39	0.49	0.01	0.15	0.48	0.20	0.21	0.05	0.21	0.75	0.02	0.57
Control Delay	17.2	15.3	0.0	12.0	22.3	3.6	32.8	51.6	1.8	53.5	35.6	11.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	17.2	15.3	0.0	12.0	22.3	3.6	32.8	51.6	1.8	53.5	35.6	11.6
LOS	B	B	A	B	C	A	C	D	A	D	D	B
Approach Delay		15.4			18.7			17.4			37.2	
Approach LOS		B			B			B			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.75

Intersection Signal Delay: 22.3


Intersection LOS: C

Intersection Capacity Utilization 62.4%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 13: Sterling Ranch Rd & Marksheffel Rd



Timings  
14: Black Forest Rd & Vollmer Rd

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑
Traffic Volume (vph)	23	24	39	740	19	130	36	500	546	95	1270	14
Future Volume (vph)	23	24	39	740	19	130	36	500	546	95	1270	14
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		4			8	2		2	6		6
Detector Phase	7	4	4	3	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)	5.0	10.0	10.0	5.0	10.0	10.0	5.0	15.0	15.0	5.0	15.0	15.0
Minimum Split (s)	10.0	15.0	15.0	10.0	15.0	15.0	10.0	20.0	20.0	10.0	20.0	20.0
Total Split (s)	12.0	23.0	23.0	39.0	50.0	50.0	12.0	46.0	46.0	12.0	46.0	46.0
Total Split (%)	10.0%	19.2%	19.2%	32.5%	41.7%	41.7%	10.0%	38.3%	38.3%	10.0%	38.3%	38.3%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max						
Act Effect Green (s)	14.4	10.0	10.0	31.1	36.0	36.0	59.8	53.0	53.0	65.6	59.4	59.4
Actuated g/C Ratio	0.12	0.08	0.08	0.26	0.30	0.30	0.50	0.44	0.44	0.55	0.50	0.50
v/c Ratio	0.13	0.16	0.15	0.88	0.04	0.24	0.23	0.34	0.56	0.22	0.76	0.02
Control Delay	27.6	53.8	1.2	54.3	29.2	6.1	12.8	12.0	10.0	17.7	36.2	0.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	27.6	53.8	1.2	54.3	29.2	6.1	12.8	12.0	10.0	17.7	36.2	0.1
LOS	C	D	A	D	C	A	B	B	B	B	D	A
Approach Delay		22.8				46.7			11.0			34.6
Approach LOS		C				D			B			C

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.88

Intersection Signal Delay: 30.0


Intersection LOS: C

Intersection Capacity Utilization 79.6%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 14: Black Forest Rd & Vollmer Rd



Timings  
15: Black Forest Rd & Woodmen Rd

2042 Total Traffic  
AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑↑	↑
Traffic Volume (vph)	448	888	200	294	1790	350	360	273	178	400	244	1095
Future Volume (vph)	448	888	200	294	1790	350	360	273	178	400	244	1095
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	10.0		5.0	10.0	
Minimum Split (s)	10.0	23.0		10.0	23.0		10.0	23.0		10.0	23.0	
Total Split (s)	23.0	56.0		20.0	53.0		20.0	24.0		20.0	24.0	
Total Split (%)	19.2%	46.7%		16.7%	44.2%		16.7%	20.0%		16.7%	20.0%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	17.8	51.9	120.0	14.1	48.2	120.0	14.8	19.0	120.0	15.0	19.2	120.0
Actuated g/C Ratio	0.15	0.43	1.00	0.12	0.40	1.00	0.12	0.16	1.00	0.12	0.16	1.00
v/c Ratio	0.90	0.41	0.13	0.74	0.89	0.23	0.87	0.50	0.11	0.95	0.31	0.71
Control Delay	71.7	24.4	0.2	57.5	31.4	0.2	72.4	49.6	0.1	75.4	35.9	6.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	71.7	24.4	0.2	57.5	31.4	0.2	72.4	49.6	0.1	75.4	35.9	6.4
LOS	E	C	A	E	C	A	E	D	A	E	D	A
Approach Delay		35.0			30.0			48.8			26.4	
Approach LOS		D			C			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.95

Intersection Signal Delay: 32.6


Intersection LOS: C

Intersection Capacity Utilization 83.8%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 15: Black Forest Rd & Woodmen Rd



Timings  
16: Marksheffel Rd & Woodmen Rd

2042 Total Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	263	791	413	563	1595	315	535	352	307	348	489	304
Future Volume (vph)	263	791	413	563	1595	315	535	352	307	348	489	304
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+ov	Prot	NA	Free
Protected Phases	5	2		1	6		3	8	1	7	4	
Permitted Phases			Free			Free			8			Free
Detector Phase	5	2		1	6		3	8	1	7	4	
Switch Phase												
Minimum Initial (s)	4.0	4.0		4.0	4.0		4.0	4.0	4.0	4.0	4.0	4.0
Minimum Split (s)	9.0	11.0		9.0	11.0		9.0	10.0	9.0	9.0	10.0	
Total Split (s)	25.0	36.0		31.0	42.0		24.0	27.0	31.0	26.0	29.0	
Total Split (%)	20.8%	30.0%		25.8%	35.0%		20.0%	22.5%	25.8%	21.7%	24.2%	
Yellow Time (s)	3.0	5.0		3.0	5.0		3.0	4.0	3.0	3.0	4.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0		-1.0	-3.0		-1.0	-2.0	0.0	-1.0	-2.0	
Total Lost Time (s)	4.0	4.0		4.0	4.0		4.0	4.0	5.0	4.0	4.0	
Lead/Lag	Lead	Lag		Lead	Lag		Lead	Lag	Lead	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	Yes	
Recall Mode	None	C-Max		None	C-Max		None	None	None	None	None	
Act Effect Green (s)	15.6	36.0	120.0	25.0	45.5	120.0	20.0	24.6	52.6	18.4	22.9	120.0
Actuated g/C Ratio	0.13	0.30	1.00	0.21	0.38	1.00	0.17	0.20	0.44	0.15	0.19	1.00
v/c Ratio	0.60	0.53	0.27	0.80	0.85	0.20	0.95	0.50	0.42	0.68	0.74	0.20
Control Delay	62.0	39.2	0.4	54.3	39.9	0.3	77.8	45.1	18.4	54.5	52.7	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	62.0	39.2	0.4	54.3	39.9	0.3	77.8	45.1	18.4	54.5	52.7	0.3
LOS	E	D	A	D	D	A	E	D	B	D	D	A
Approach Delay		32.4			38.2			52.9			39.3	
Approach LOS		C			D			D			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green, Master Intersection

Natural Cycle: 65

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.95

Intersection Signal Delay: 39.8


Intersection LOS: D

Intersection Capacity Utilization 80.4%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 16: Marksheffel Rd & Woodmen Rd



Timings  
17: Banning Lewis Pkwy & Woodmen Rd

2042 Total Traffic

AM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	308	586	534	211	1179	89	762	369	173	170	623	322
Future Volume (vph)	308	586	534	211	1179	89	762	369	173	170	623	322
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	10.0		5.0	10.0	
Minimum Split (s)	10.0	20.0		10.0	20.0		10.0	15.0		10.0	15.0	
Total Split (s)	19.0	41.0		15.0	37.0		30.0	47.0		17.0	34.0	
Total Split (%)	15.8%	34.2%		12.5%	30.8%		25.0%	39.2%		14.2%	28.3%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	13.7	36.0	120.0	10.0	32.3	120.0	25.0	43.2	120.0	10.8	29.0	120.0
Actuated g/C Ratio	0.11	0.30	1.00	0.08	0.27	1.00	0.21	0.36	1.00	0.09	0.24	1.00
v/c Ratio	0.83	0.40	0.36	0.78	0.91	0.06	1.12	0.31	0.11	0.58	0.77	0.21
Control Delay	70.0	34.4	0.6	73.1	53.1	0.1	115.9	28.7	0.2	59.9	49.3	0.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	70.0	34.4	0.6	73.1	53.1	0.1	115.9	28.7	0.2	59.9	49.3	0.3
LOS	E	C	A	E	D	A	F	C	A	E	D	A
Approach Delay		29.5			52.7			75.9			36.8	
Approach LOS		C			D			E			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.12

Intersection Signal Delay: 48.8


Intersection LOS: D

Intersection Capacity Utilization 87.2%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 17: Banning Lewis Pkwy & Woodmen Rd



Intersection

Intersection Delay, s/veh 12.1

Intersection LOS B

Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	447	369	712	388
Demand Flow Rate, veh/h	456	376	726	396
Vehicles Circulating, veh/h	493	548	591	375
Vehicles Exiting, veh/h	278	577	358	549
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	12.3	11.2	14.2	8.8
Approach LOS	B	B	B	A

Lane	Left	Left	Left	Bypass	Left
Designated Moves	LTR	LTR	LT	R	LTR
Assumed Moves	LTR	LTR	LT	R	LTR
RT Channelized				Free	
Lane Util	1.000	1.000	1.000	1.000	
Follow-Up Headway, s	2.609	2.609	2.609	2.609	
Critical Headway, s	4.976	4.976	4.976	192	4.976
Entry Flow, veh/h	456	376	534	1938	396
Cap Entry Lane, veh/h	835	789	755	0.980	941
Entry HV Adj Factor	0.981	0.982	0.981	188	0.980
Flow Entry, veh/h	447	369	524	1900	388
Cap Entry, veh/h	819	775	741	0.099	923
V/C Ratio	0.546	0.477	0.707	0.0	0.421
Control Delay, s/veh	12.3	11.2	19.2	A	8.8
LOS	B	B	C	0	A
95th %tile Queue, veh	3	3	6		2

Intersection

Int Delay, s/veh 0.3

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	W	B		A		
Traffic Vol, veh/h	10	4	500	16	6	327
Future Vol, veh/h	10	4	500	16	6	327
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	11	4	526	17	6	344

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	891	535	0	0	543
Stage 1	535	-	-	-	-
Stage 2	356	-	-	-	-
Critical Hdwy	6.42	6.22	-	-	4.12
Critical Hdwy Stg 1	5.42	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-
Follow-up Hdwy	3.518	3.318	-	-	2.218
Pot Cap-1 Maneuver	313	545	-	-	1026
Stage 1	587	-	-	-	-
Stage 2	709	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	311	545	-	-	1026
Mov Cap-2 Maneuver	311	-	-	-	-
Stage 1	587	-	-	-	-
Stage 2	704	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	15.6	0	0.2
HCM LOS	C		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	SBL	SBT
Capacity (veh/h)	-	-	354	1026	-
HCM Lane V/C Ratio	-	-	0.042	0.006	-
HCM Control Delay (s)	-	-	15.6	8.5	0
HCM Lane LOS	-	-	C	A	A
HCM 95th %tile Q(veh)	-	-	0.1	0	-

Timings  
3: Black Forest Rd & Briarate Pkwy

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	190	1032	349	163	734	74	434	794	208	101	524	210
Future Volume (vph)	190	1032	349	163	734	74	434	794	208	101	524	210
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free	pm+pt	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free			Free	6		Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0		5.0	15.0		5.0	15.0	
Minimum Split (s)	13.0	23.0		13.0	23.0		10.0	23.0		10.0	23.0	
Total Split (s)	20.0	49.0		17.0	46.0		23.0	42.0		12.0	31.0	
Total Split (%)	16.7%	40.8%		14.2%	38.3%		19.2%	35.0%		10.0%	25.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	54.1	41.2	120.0	51.1	39.7	120.0	18.5	39.9	120.0	36.4	28.9	120.0
Actuated g/C Ratio	0.45	0.34	1.00	0.43	0.33	1.00	0.15	0.33	1.00	0.30	0.24	1.00
v/c Ratio	0.65	0.89	0.23	0.75	0.66	0.05	0.86	0.71	0.14	0.51	0.65	0.14
Control Delay	28.1	47.5	0.3	45.7	37.3	0.1	50.2	29.9	0.1	32.5	46.0	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	28.1	47.5	0.3	45.7	37.3	0.1	50.2	29.9	0.1	32.5	46.0	0.2
LOS	C	D	A	D	D	A	D	C	A	C	D	A
Approach Delay		34.7			35.9			31.8			32.8	
Approach LOS		C			D			C			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.89

Intersection Signal Delay: 33.7


Intersection LOS: C

Intersection Capacity Utilization 81.8%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 3: Black Forest Rd & Briarate Pkwy



Timings  
4: Vollmer Rd & Briargate Pkwy

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	227	1010	122	210	743	74	167	415	283	109	211	118
Future Volume (vph)	227	1010	122	210	743	74	167	415	283	109	211	118
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2			6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	15.0	15.0	15.0	5.0	5.0	5.0	5.0	5.0	5.0
Minimum Split (s)	10.0	20.0	20.0	20.0	20.0	20.0	10.0	10.0	10.0	10.0	10.0	10.0
Total Split (s)	12.0	57.0	57.0	20.0	65.0	65.0	17.0	28.0	28.0	15.0	26.0	26.0
Total Split (%)	10.0%	47.5%	47.5%	16.7%	54.2%	54.2%	14.2%	23.3%	23.3%	12.5%	21.7%	21.7%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0	0.0	0.0	-2.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0	5.0	5.0	3.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	Max	Max	None	Max	Max	None	None	None	None	None	None
Act Effect Green (s)	59.1	54.1	52.1	15.0	62.1	60.1	31.1	19.6	19.6	26.9	17.5	17.5
Actuated g/C Ratio	0.51	0.47	0.45	0.13	0.53	0.52	0.27	0.17	0.17	0.23	0.15	0.15
v/c Ratio	0.64	0.63	0.16	0.50	0.41	0.09	0.54	0.71	0.64	0.50	0.42	0.34
Control Delay	22.5	26.1	2.3	52.1	17.5	1.4	38.6	52.6	16.8	38.6	47.0	5.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	22.5	26.1	2.3	52.1	17.5	1.4	38.6	52.6	16.8	38.6	47.0	5.7
LOS	C	C	A	D	B	A	D	D	B	D	D	A
Approach Delay		23.3			23.4				38.0			33.8
Approach LOS		C			C				D			C

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 116.1

Natural Cycle: 70

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 0.71

Intersection Signal Delay: 28.0


Intersection LOS: C

Intersection Capacity Utilization 73.8%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 4: Vollmer Rd & Briargate Pkwy



Timings  
5: Sterling Ranch Rd & Briargate Pkwy

2042 Total Traffic

PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑	↑	↑	↑	↑
Traffic Volume (vph)	329	923	129	152	827	105	191	190	83	86	87	133
Future Volume (vph)	329	923	129	152	827	105	191	190	83	86	87	133
Turn Type	pm+pt	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Free	pm+pt	NA	Free
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		Free	4		Free
Detector Phase	5	2	2	1	6	6	3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	20.0		5.0	20.0	
Minimum Split (s)	10.0	23.0	23.0	10.0	23.0	23.0	10.0	25.0		10.0	25.0	
Total Split (s)	22.0	68.0	68.0	12.0	58.0	58.0	15.0	30.0		10.0	25.0	
Total Split (%)	18.3%	56.7%	56.7%	10.0%	48.3%	48.3%	12.5%	25.0%		8.3%	20.8%	
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-2.0	-2.0	0.0	0.0	-2.0	0.0	0.0	0.0		0.0	0.0	
Total Lost Time (s)	3.0	3.0	5.0	5.0	3.0	5.0	5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag	Lead	Lag		Lead	Lag	
Lead-Lag Optimize?	Yes		Yes	Yes								
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	None		None	None	
Act Effect Green (s)	77.0	65.0	63.0	61.8	56.8	54.8	35.0	25.0	120.0	25.0	20.0	120.0
Actuated g/C Ratio	0.64	0.54	0.52	0.52	0.47	0.46	0.29	0.21	1.00	0.21	0.17	1.00
v/c Ratio	0.77	0.51	0.15	0.53	0.52	0.14	0.56	0.52	0.05	0.36	0.30	0.09
Control Delay	24.6	18.5	2.8	19.0	24.1	5.3	41.1	47.6	0.1	38.3	46.8	0.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	24.6	18.5	2.8	19.0	24.1	5.3	41.1	47.6	0.1	38.3	46.8	0.1
LOS	C	B	A	B	C	A	D	D	A	D	D	A
Approach Delay		18.5			21.5			36.5			24.2	
Approach LOS		B			C			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.77

Intersection Signal Delay: 22.6


Intersection LOS: C

Intersection Capacity Utilization 83.3%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 5: Sterling Ranch Rd & Briargate Pkwy



## Timings

## 6: Banning Lewis Pkwy &amp; Briargate Pkwy

2042 Total Traffic

PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	7	530	476	332	518	56	541	229	292	43	153	2
Future Volume (vph)	7	530	476	332	518	56	541	229	292	43	153	2
Turn Type	pm+pt	NA	Free	Prot	NA	Perm	Prot	NA	Free	pm+pt	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		Free			6			Free	4		4
Detector Phase	5	2		1	6	6	3	8		7	4	4
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0	15.0	8.0	10.0		8.0	10.0	10.0
Minimum Split (s)	15.0	20.0		20.0	20.0	20.0	13.0	15.0		13.0	15.0	15.0
Total Split (s)	15.0	38.0		25.0	48.0	48.0	32.0	43.0		14.0	25.0	25.0
Total Split (%)	12.5%	31.7%		20.8%	40.0%	40.0%	26.7%	35.8%		11.7%	20.8%	20.8%
Yellow Time (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
All-Red Time (s)	2.0	2.0		2.0	2.0	2.0	2.0	2.0		2.0	2.0	2.0
Lost Time Adjust (s)	0.0	-2.0		0.0	-2.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	5.0	3.0		5.0	3.0	5.0	5.0	5.0		5.0	5.0	5.0
Lead/Lag	Lead	Lag		Lead	Lag	Lag	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?	Yes	Yes		Yes	Yes	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	None	C-Max		None	C-Max	C-Max	None	Max		None	Max	Max
Act Effect Green (s)	44.0	38.0	120.0	17.0	57.4	55.4	24.2	41.4	120.0	31.0	22.8	22.8
Actuated g/C Ratio	0.37	0.32	1.00	0.14	0.48	0.46	0.20	0.34	1.00	0.26	0.19	0.19
v/c Ratio	0.02	0.50	0.32	0.72	0.32	0.07	0.82	0.20	0.19	0.13	0.24	0.00
Control Delay	25.1	53.0	0.6	57.8	20.7	0.2	54.4	32.8	0.3	23.1	43.3	0.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	25.1	53.0	0.6	57.8	20.7	0.2	54.4	32.8	0.3	23.1	43.3	0.0
LOS	C	D	A	E	C	A	D	C	A	C	D	A
Approach Delay		28.2			33.0			34.9			38.5	
Approach LOS		C			C			C			D	

## Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.82

Intersection Signal Delay: 32.4


Intersection LOS: C

Intersection Capacity Utilization 63.7%

ICU Level of Service B

Analysis Period (min) 15

Splits and Phases: 6: Banning Lewis Pkwy &amp; Briargate Pkwy



Intersection

Int Delay, s/veh 1.6

Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations	↑	↑	↑↑	↑	↑	↑↑
Traffic Vol, veh/h	64	73	791	87	34	509
Future Vol, veh/h	64	73	791	87	34	509
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	0	-	155	205	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	67	77	833	92	36	536

Major/Minor	Minor1	Major1	Major2		
Conflicting Flow All	1173	417	0	0	925
Stage 1	833	-	-	-	-
Stage 2	340	-	-	-	-
Critical Hdwy	6.84	6.94	-	-	4.14
Critical Hdwy Stg 1	5.84	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-
Follow-up Hdwy	3.52	3.32	-	-	2.22
Pot Cap-1 Maneuver	185	585	-	-	734
Stage 1	387	-	-	-	-
Stage 2	692	-	-	-	-
Platoon blocked, %	-	-	-	-	-
Mov Cap-1 Maneuver	176	585	-	-	734
Mov Cap-2 Maneuver	295	-	-	-	-
Stage 1	387	-	-	-	-
Stage 2	658	-	-	-	-

Approach	WB	NB	SB
HCM Control Delay, s	16.2	0	0.6
HCM LOS	C		

Minor Lane/Major Mvmt	NBT	NBR	WBLn1	WBLn2	SBL	SBT
Capacity (veh/h)	-	-	295	585	734	-
HCM Lane V/C Ratio	-	-	0.228	0.131	0.049	-
HCM Control Delay (s)	-	-	20.8	12.1	10.2	-
HCM Lane LOS	-	-	C	B	B	-
HCM 95th %tile Q(veh)	-	-	0.9	0.5	0.2	-

Intersection												
Int Delay, s/veh	4.2											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑	↑↑	↑↑	↑	↑	↑↑	
Traffic Vol, veh/h	37	16	28	120	0	136	0	318	150	50	283	0
Future Vol, veh/h	37	16	28	120	0	136	0	318	150	50	283	0
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Free	Free	Free	Free	Free	Free
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	0	-	0	0	-	0	-	-	205	205	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	95	95	95	95	95	95	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	39	17	29	126	0	143	0	335	158	53	298	0
Major/Minor	Minor2	Minor1		Major1		Major2						
Conflicting Flow All	572	897	149	599	-	168	-	0	0	493	0	0
Stage 1	404	404	-	335	-	-	-	-	-	-	-	-
Stage 2	168	493	-	264	-	-	-	-	-	-	-	-
Critical Hdwy	7.54	6.54	6.94	7.54	-	6.94	-	-	-	4.14	-	-
Critical Hdwy Stg 1	6.54	5.54	-	6.54	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	6.54	5.54	-	6.54	-	-	-	-	-	-	-	-
Follow-up Hdwy	3.52	4.02	3.32	3.52	-	3.32	-	-	-	2.22	-	-
Pot Cap-1 Maneuver	403	278	871	385	0	847	0	-	-	1067	-	0
Stage 1	594	598	-	653	0	-	0	-	-	-	-	0
Stage 2	817	545	-	718	0	-	0	-	-	-	-	0
Platoon blocked, %							-	-	-	-	-	-
Mov Cap-1 Maneuver	322	264	871	345	-	847	-	-	-	1067	-	-
Mov Cap-2 Maneuver	425	360	-	452	-	-	-	-	-	-	-	-
Stage 1	594	568	-	653	-	-	-	-	-	-	-	-
Stage 2	679	545	-	640	-	-	-	-	-	-	-	-
Approach	EB	WB		NB		SB						
HCM Control Delay, s	12.8	12.9		0		1.3						
HCM LOS	B	B		C		A		C		B		A
Minor Lane/Major Mvmt	NBT	NBR	EBLn1	EBLn2	EBLn3	WBLn1	WBLn2	SBL	SBT			
Capacity (veh/h)	-	-	425	360	871	452	847	1067	-			
HCM Lane V/C Ratio	-	-	0.092	0.047	0.034	0.279	0.169	0.049	-			
HCM Control Delay (s)	-	-	14.3	15.5	9.3	16	10.1	8.5	-			
HCM Lane LOS	-	-	B	C	A	C	B	A	-			
HCM 95th %tile Q(veh)	-	-	0.3	0.1	0.1	1.1	0.6	0.2	-			

Timings  
9: Banning Lewis Pkwy & E-W Collector

2042 Total Traffic  
PM Peak Hour



Lane Group	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	↑ ↗	↗ ↘	↖ ↗	↑ ↑	↑ ↑	↗
Traffic Volume (vph)	31	224	344	1031	888	74
Future Volume (vph)	31	224	344	1031	888	74
Turn Type	Prot	Free	pm+pt	NA	NA	Perm
Protected Phases	4		5	2	6	
Permitted Phases		Free		2		6
Detector Phase	4		5	2	6	6
Switch Phase						
Minimum Initial (s)	15.0		5.0	15.0	15.0	15.0
Minimum Split (s)	20.0		10.0	20.0	20.0	20.0
Total Split (s)	30.0		20.0	90.0	70.0	70.0
Total Split (%)	25.0%		16.7%	75.0%	58.3%	58.3%
Yellow Time (s)	3.0		3.0	3.0	3.0	3.0
All-Red Time (s)	2.0		2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0		5.0	5.0	5.0	5.0
Lead/Lag		Lead		Lag	Lag	
Lead-Lag Optimize?		Yes		Yes	Yes	
Recall Mode	None		None	C-Max	C-Max	C-Max
Act Effect Green (s)	15.0	120.0	103.0	105.0	85.7	85.7
Actuated g/C Ratio	0.12	1.00	0.86	0.88	0.71	0.71
v/c Ratio	0.15	0.15	0.66	0.35	0.37	0.07
Control Delay	48.8	0.2	9.1	2.9	18.4	6.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	48.8	0.2	9.1	2.9	18.4	6.7
LOS	D	A	A	A	B	A
Approach Delay	6.2			4.5	17.5	
Approach LOS	A			A	B	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green

Natural Cycle: 60

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.66

Intersection Signal Delay: 9.5


Intersection LOS: A

Intersection Capacity Utilization 68.6%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 9: Banning Lewis Pkwy & E-W Collector



Intersection												
Int Delay, s/veh	1.9											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↔	↔	↑	↑	↑	
Traffic Vol, veh/h	97	569	29	3	374	10	18	1	2	4	1	67
Future Vol, veh/h	97	569	29	3	374	10	18	1	2	4	1	67
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	205	-	155	205	-	-	-	-	-	-	-	155
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	95	95	95	95	95	95	95	95	95	95	95	95
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	102	599	31	3	394	11	19	1	2	4	1	71
Major/Minor	Major1		Major2		Minor1		Minor2					
Conflicting Flow All	405	0	0	630	0	0	1007	1214	300	910	1240	203
Stage 1	-	-	-	-	-	-	803	803	-	406	406	-
Stage 2	-	-	-	-	-	-	204	411	-	504	834	-
Critical Hdwy	4.14	-	-	4.14	-	-	7.54	6.54	6.94	7.54	6.54	6.94
Critical Hdwy Stg 1	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Follow-up Hdwy	2.22	-	-	2.22	-	-	3.52	4.02	3.32	3.52	4.02	3.32
Pot Cap-1 Maneuver	1150	-	-	948	-	-	195	180	696	230	174	804
Stage 1	-	-	-	-	-	-	343	394	-	593	596	-
Stage 2	-	-	-	-	-	-	779	593	-	518	381	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1150	-	-	948	-	-	165	163	696	212	158	804
Mov Cap-2 Maneuver	-	-	-	-	-	-	165	163	-	212	158	-
Stage 1	-	-	-	-	-	-	312	359	-	540	594	-
Stage 2	-	-	-	-	-	-	707	591	-	469	347	-
Approach	EB		WB		NB		SB					
HCM Control Delay, s	1.2		0.1		28.1		10.9					
HCM LOS					D		B					
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1	SBLn2			
Capacity (veh/h)	178	1150	-	-	948	-	-	198	804			
HCM Lane V/C Ratio	0.124	0.089	-	-	0.003	-	-	0.027	0.088			
HCM Control Delay (s)	28.1	8.4	-	-	8.8	-	-	23.7	9.9			
HCM Lane LOS	D	A	-	-	A	-	-	C	A			
HCM 95th %tile Q(veh)	0.4	0.3	-	-	0	-	-	0.1	0.3			

Timings  
11: Black Forest Rd & Research Pkwy

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	250	935	100	100	704	499	125	770	100	398	324	270
Future Volume (vph)	250	935	100	100	704	499	125	770	100	398	324	270
Turn Type	pm+pt	NA	Free	pm+pt	NA	Free	pm+pt	NA	Free	Prot	NA	Free
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		Free	8		Free	2		Free			Free
Detector Phase	7	4		3	8		5	2		1	6	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	15.0		5.0	15.0	
Minimum Split (s)	10.0	23.0		10.0	23.0		10.0	23.0		10.0	23.0	
Total Split (s)	23.0	44.0		15.0	36.0		12.0	39.0		22.0	49.0	
Total Split (%)	19.2%	36.7%		12.5%	30.0%		10.0%	32.5%		18.3%	40.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Total Lost Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	None		None	None		None	C-Max		None	C-Max	
Act Effect Green (s)	51.1	37.1	120.0	38.5	29.5	120.0	44.2	36.8	120.0	17.1	46.4	120.0
Actuated g/C Ratio	0.43	0.31	1.00	0.32	0.25	1.00	0.37	0.31	1.00	0.14	0.39	1.00
v/c Ratio	0.85	0.90	0.07	0.54	0.85	0.33	0.31	0.75	0.07	0.86	0.25	0.18
Control Delay	54.7	51.4	0.1	32.2	53.7	0.6	19.6	47.9	0.1	53.6	22.3	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	54.7	51.4	0.1	32.2	53.7	0.6	19.6	47.9	0.1	53.6	22.3	0.2
LOS	D	D	A	C	D	A	B	D	A	D	C	A
Approach Delay		48.1			31.7			39.6			28.8	
Approach LOS		D			C			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.90

Intersection Signal Delay: 37.4


Intersection LOS: D

Intersection Capacity Utilization 82.6%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 11: Black Forest Rd & Research Pkwy



Timings  
12: Vollmer Rd & Marksheffel Rd

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑	↑	↑↑	↑
Traffic Volume (vph)	143	947	96	187	716	154	171	595	186	132	241	200
Future Volume (vph)	143	947	96	187	716	154	171	595	186	132	241	200
Turn Type	pm+pt	NA	Perm									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		8	4		4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0	10.0	23.0	23.0
Total Split (s)	20.0	56.0	56.0	19.0	55.0	55.0	14.0	31.0	31.0	14.0	31.0	31.0
Total Split (%)	16.7%	46.7%	46.7%	15.8%	45.8%	45.8%	11.7%	25.8%	25.8%	11.7%	25.8%	25.8%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	Max	Max	None	Max	Max
Act Effect Green (s)	63.7	53.5	53.5	66.3	54.8	54.8	35.1	26.1	26.1	34.9	26.0	26.0
Actuated g/C Ratio	0.53	0.45	0.45	0.55	0.46	0.46	0.29	0.22	0.22	0.29	0.22	0.22
v/c Ratio	0.39	0.63	0.13	0.64	0.47	0.20	0.52	0.81	0.42	0.71	0.33	0.42
Control Delay	14.8	28.3	3.8	38.7	15.5	1.7	36.7	54.3	12.1	50.7	41.1	7.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	14.8	28.3	3.8	38.7	15.5	1.7	36.7	54.3	12.1	50.7	41.1	7.8
LOS	B	C	A	D	B	A	D	D	B	D	D	A
Approach Delay		24.7			17.6			42.9			31.7	
Approach LOS		C			B			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 70

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.81

Intersection Signal Delay: 28.4


Intersection LOS: C

Intersection Capacity Utilization 77.0%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 12: Vollmer Rd & Marksheffel Rd



Timings  
13: Sterling Ranch Rd & Marksheffel Rd

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑↑	↑	↑	↑↑	↑	↑	↑	↑	↑↑	↑	↑
Traffic Volume (vph)	302	946	22	130	841	577	27	7	37	346	24	189
Future Volume (vph)	302	946	22	130	841	577	27	7	37	346	24	189
Turn Type	pm+pt	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm	Prot	NA	Perm
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases	2		2	6		6	8		8			4
Detector Phase	5	2	2	1	6	6	3	8	8	7	4	4
Switch Phase												
Minimum Initial (s)	5.0	15.0	15.0	5.0	15.0	15.0	5.0	10.0	10.0	20.0	10.0	10.0
Minimum Split (s)	10.0	20.0	20.0	10.0	20.0	20.0	10.0	15.0	15.0	25.0	20.0	20.0
Total Split (s)	20.0	68.0	68.0	12.0	60.0	60.0	10.0	15.0	15.0	25.0	30.0	30.0
Total Split (%)	16.7%	56.7%	56.7%	10.0%	50.0%	50.0%	8.3%	12.5%	12.5%	20.8%	25.0%	25.0%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	None	None	None	None	None
Act Effect Green (s)	80.5	69.1	69.1	69.7	62.7	62.7	11.0	10.0	10.0	20.0	23.0	23.0
Actuated g/C Ratio	0.67	0.58	0.58	0.58	0.52	0.52	0.09	0.08	0.08	0.17	0.19	0.19
v/c Ratio	0.75	0.49	0.02	0.41	0.48	0.54	0.20	0.05	0.12	0.64	0.07	0.43
Control Delay	38.4	11.0	0.0	12.8	20.9	3.6	37.8	51.4	0.8	52.3	39.2	8.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	38.4	11.0	0.0	12.8	20.9	3.6	37.8	51.4	0.8	52.3	39.2	8.5
LOS	D	B	A	B	C	A	D	D	A	D	D	A
Approach Delay		17.4			13.7			19.6			36.9	
Approach LOS		B			B			B			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.75

Intersection Signal Delay: 19.0


Intersection LOS: B

Intersection Capacity Utilization 73.3%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 13: Sterling Ranch Rd & Marksheffel Rd



Timings  
14: Black Forest Rd & Vollmer Rd

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑	↑
Traffic Volume (vph)	10	22	21	502	23	195	58	1010	818	110	700	23
Future Volume (vph)	10	22	21	502	23	195	58	1010	818	110	700	23
Turn Type	pm+pt	NA	Perm	Prot	NA	Perm	pm+pt	NA	Perm	pm+pt	NA	Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases	4		4			8	2		2	6		6
Detector Phase	7	4	4	3	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)	5.0	10.0	10.0	5.0	10.0	10.0	5.0	15.0	15.0	5.0	15.0	15.0
Minimum Split (s)	10.0	15.0	15.0	10.0	15.0	15.0	10.0	20.0	20.0	10.0	20.0	20.0
Total Split (s)	12.0	23.0	23.0	33.0	44.0	44.0	12.0	52.0	52.0	12.0	52.0	52.0
Total Split (%)	10.0%	19.2%	19.2%	27.5%	36.7%	36.7%	10.0%	43.3%	43.3%	10.0%	43.3%	43.3%
Yellow Time (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Lead/Lag	Lead	Lag	Lag									
Lead-Lag Optimize?	Yes											
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max						
Act Effect Green (s)	12.1	10.0	10.0	23.4	30.0	30.0	70.7	63.5	63.5	75.3	67.5	67.5
Actuated g/C Ratio	0.10	0.08	0.08	0.20	0.25	0.25	0.59	0.53	0.53	0.63	0.56	0.56
v/c Ratio	0.07	0.15	0.08	0.79	0.05	0.37	0.14	0.57	0.70	0.39	0.37	0.03
Control Delay	29.9	53.5	0.6	54.9	31.5	6.5	6.8	18.9	11.1	17.2	24.0	0.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.1	0.0	0.0	0.0
Total Delay	29.9	53.5	0.6	54.9	31.5	6.5	6.8	18.9	11.2	17.2	24.0	0.4
LOS	C	D	A	D	C	A	A	B	B	B	C	A
Approach Delay		28.1			41.0			15.2			22.4	
Approach LOS		C			D			B			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 65

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.79

Intersection Signal Delay: 22.4


Intersection LOS: C

Intersection Capacity Utilization 77.6%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 14: Black Forest Rd & Vollmer Rd



Timings  
15: Black Forest Rd & Woodmen Rd

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑↑	↑
Traffic Volume (vph)	751	2613	360	221	1869	300	300	406	292	300	300	752
Future Volume (vph)	751	2613	360	221	1869	300	300	406	292	300	300	752
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	8.0	15.0		8.0	15.0		8.0	10.0		8.0	10.0	
Minimum Split (s)	13.0	20.0		13.0	20.0		13.0	15.0		13.0	15.0	
Total Split (s)	31.0	63.0		17.0	49.0		19.0	23.0		17.0	21.0	
Total Split (%)	25.8%	52.5%		14.2%	40.8%		15.8%	19.2%		14.2%	17.5%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0		-1.0	-3.0		-1.0	-2.0		-1.0	-2.0	
Total Lost Time (s)	4.0	2.0		4.0	2.0		4.0	3.0		4.0	3.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	27.0	61.6	120.0	12.4	47.0	120.0	14.5	20.0	120.0	13.0	18.5	120.0
Actuated g/C Ratio	0.22	0.51	1.00	0.10	0.39	1.00	0.12	0.17	1.00	0.11	0.15	1.00
v/c Ratio	0.99	1.02	0.23	0.64	0.96	0.19	0.74	0.70	0.19	0.82	0.39	0.48
Control Delay	77.2	53.0	0.3	81.5	25.2	0.1	62.1	54.4	0.3	79.4	37.6	3.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	77.2	53.0	0.3	81.5	25.2	0.1	62.1	54.4	0.3	79.4	37.6	3.1
LOS	E	D	A	F	C	A	E	D	A	E	D	A
Approach Delay		52.8			27.3			40.9			27.7	
Approach LOS		D			C			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.02

Intersection Signal Delay: 40.2


Intersection LOS: D

Intersection Capacity Utilization 90.7%

ICU Level of Service E

Analysis Period (min) 15

Splits and Phases: 15: Black Forest Rd & Woodmen Rd



Timings  
16: Marksheffel Rd & Woodmen Rd

2042 Total Traffic

PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	527	2012	665	471	1689	339	491	512	500	419	381	210
Future Volume (vph)	527	2012	665	471	1689	339	491	512	500	419	381	210
Turn Type	Prot	NA	Free	Prot	NA	Free	Prot	NA	pm+ov	Prot	NA	Free
Protected Phases	5	2		1	6		3	8	1	7	4	
Permitted Phases			Free			Free			8			Free
Detector Phase	5	2		1	6		3	8	1	7	4	
Switch Phase												
Minimum Initial (s)	4.0	4.0		4.0	4.0		4.0	4.0	4.0	4.0	4.0	
Minimum Split (s)	9.0	11.0		9.0	11.0		9.0	10.0	9.0	9.0	10.0	
Total Split (s)	25.0	51.0		22.0	48.0		23.0	26.0	22.0	21.0	24.0	
Total Split (%)	20.8%	42.5%		18.3%	40.0%		19.2%	21.7%	18.3%	17.5%	20.0%	
Yellow Time (s)	3.0	5.0		3.0	5.0		3.0	4.0	3.0	3.0	4.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-1.0	-3.0		-1.0	-3.0		-1.0	-2.0	0.0	-1.0	-2.0	
Total Lost Time (s)	4.0	4.0		4.0	4.0		4.0	4.0	5.0	4.0	4.0	
Lead/Lag	Lead	Lag		Lead	Lag		Lead	Lag	Lead	Lead	Lag	
Lead-Lag Optimize?	Yes	Yes		Yes	Yes		Yes	Yes	Yes	Yes	Yes	
Recall Mode	None	C-Max		None	C-Max		None	None	None	None	None	
Act Effect Green (s)	20.9	47.1	120.0	18.3	44.6	120.0	19.0	21.5	42.9	17.0	19.5	120.0
Actuated g/C Ratio	0.17	0.39	1.00	0.15	0.37	1.00	0.16	0.18	0.36	0.14	0.16	1.00
v/c Ratio	0.90	1.03	0.43	0.92	0.91	0.22	0.92	0.82	0.83	0.88	0.68	0.14
Control Delay	58.5	44.3	0.3	74.2	44.5	0.3	73.7	59.1	42.0	70.8	53.7	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	58.5	44.3	0.3	74.2	44.5	0.3	73.7	59.1	42.0	70.8	53.7	0.2
LOS	E	D	A	E	D	A	E	E	D	E	D	A
Approach Delay		37.5			44.1			58.2			49.7	
Approach LOS		D			D			E			D	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green, Master Intersection

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.03

Intersection Signal Delay: 44.8


Intersection LOS: D

Intersection Capacity Utilization 92.6%

ICU Level of Service F

Analysis Period (min) 15

Splits and Phases: 16: Marksheffel Rd & Woodmen Rd



Timings  
17: Banning Lewis Pkwy & Woodmen Rd

2042 Total Traffic  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑↑	↑↑↑	↑	↑↑	↑↑↑	↑	↑↑	↑↑	↑	↑↑	↑↑	↑
Traffic Volume (vph)	492	1331	893	437	1106	201	840	848	308	144	643	483
Future Volume (vph)	492	1331	893	437	1106	201	840	848	308	144	643	483
Turn Type	Prot	NA	Free									
Protected Phases	5	2		1	6		3	8		7	4	
Permitted Phases			Free			Free			Free			Free
Detector Phase	5	2		1	6		3	8		7	4	
Switch Phase												
Minimum Initial (s)	5.0	15.0		5.0	15.0		5.0	10.0		5.0	10.0	
Minimum Split (s)	10.0	20.0		10.0	20.0		10.0	15.0		10.0	15.0	
Total Split (s)	23.0	37.0		20.0	34.0		32.0	51.0		12.0	31.0	
Total Split (%)	19.2%	30.8%		16.7%	28.3%		26.7%	42.5%		10.0%	25.8%	
Yellow Time (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
All-Red Time (s)	2.0	2.0		2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)	-2.0	-3.0		-2.0	-3.0		-1.0	-2.0		-1.0	-2.0	
Total Lost Time (s)	3.0	2.0		3.0	2.0		4.0	3.0		4.0	3.0	
Lead/Lag	Lead	Lag										
Lead-Lag Optimize?	Yes	Yes										
Recall Mode	None	C-Max		None	C-Max		None	Max		None	Max	
Act Effect Green (s)	20.0	35.0	120.0	17.0	32.0	120.0	28.0	48.0	120.0	8.0	28.0	120.0
Actuated g/C Ratio	0.17	0.29	1.00	0.14	0.27	1.00	0.23	0.40	1.00	0.07	0.23	1.00
v/c Ratio	0.88	0.92	0.58	0.92	0.83	0.13	1.07	0.61	0.20	0.64	0.80	0.31
Control Delay	66.4	51.7	1.5	75.9	47.9	0.2	96.1	30.9	0.3	68.2	51.5	0.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	66.4	51.7	1.5	75.9	47.9	0.2	96.1	30.9	0.3	68.2	51.5	0.5
LOS	E	D	A	E	D	A	F	C	A	E	D	A
Approach Delay		37.9			49.4			53.6			34.0	
Approach LOS		D			D			D			C	

Intersection Summary

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 1.07

Intersection Signal Delay: 43.9


Intersection LOS: D

Intersection Capacity Utilization 93.3%

ICU Level of Service F

Analysis Period (min) 15

Splits and Phases: 17: Banning Lewis Pkwy & Woodmen Rd



# Crash History

---



AccidentDate	TotalVehicles	ReferencePointName	ReferencePointAtName	AccidentNarrative
2019-09-29	1	VOLLMER RD	GLIDER LP	Vehicle #1 was traveling northbound on Vollmer Road .8 miles north of Glider Loop. Vehicle # 1's right side tires dropped off the right side of the roadway as it entered a sharp left curve. Vehicle #1 lost control on the roadway for approximately 131' before it traveled approximately 100' off the right side of the roadway. Vehicle #1 collided its rear with a barbed-wire fence. Vehicle #1 was moved prior to investigation.
2019-10-01	1	VOLLMER RD	S POCO RD	Vehicle #1 was northbound on Vollmer Road in a left hand curve. Vehicle #1 ran off the right side of the road for 107.3'. Vehicle over corrected, reentered the roadway, spinning counter clockwise. Vehicle #1 was out of control for 98.5'. Vehicle #1 ran off the left side of the road for 99.8', rolling 1 1/2 times. Vehicle #1 came to rest on its top facing west.
2019-11-14	1	VOLLMER RD	GLIDER PL	Vehicle 1 was southbound on Vollmer Road south of Burgess Road. Vehicle 1 was travelling in excessive speed, when it failed to negotiate a right hand bend in the roadway. Vehicle left heavy left side tire skids marks for 115.8 feet in the northbound lane, after which it traveled for 59.4 across the southbound lane. Vehicle 1 ran off the right side of the road for 130.9 feet where it began to overturn, airborne for 20.7 feet, colliding with the ground, traveled another 25.9 feet and rolled another 52.2 feet where it came to final rest facing east on its right side 23.9 feet from the west road edge.
2020-04-23	1	VOLLMER RD	WILDFLOWER RD	Vehicle #1 was traveling south on Vollmer Rd approaching Wildflower Rd. Vehicle #1 failed to navigate the slight left curve in the roadway at which point it ran off the right side of the road. Vehicle #1 crashed through the fence on the right side of the road, traveled southwest into the yard of 8455 Wildflower Rd, rolled, crashed into a well, and came to rest on its wheels facing south.
2020-05-26	1	VOLLMER	WILD FLOWER	Vehicle #1 was southbound on Vollmer. Driver of vehicle #1 lost control and went off the right side of the road and overturned. Vehicle #1 was moved prior to investigation.
2020-07-25	1	VOLLMER RD	POCO RD	Vehicle 1 was traveling in an easterly direction on Vollmer Road approaching a left curve. Vehicle 1 drove on the wrong side of the road to avoid a deceased raccoon in the middle of its lane. Vehicle 1 returned to its lane while navigating the curve. Vehicle 1's right tires dropped off the right edge of the road. Driver 1 pulled the wheel to the left causing Vehicle 1 to spin out of control. Driver 1 overcorrected to the right and the vehicle rolled 3/4 times off the right side of the road. Vehicle 1 came to final rest on top of a fence facing south on its right side.
2021-03-24	1	VOLLMER RD	POCO RD	Vehicle #1 was southbound on Vollmer Road just south of Poco Road. Vehicle #1 lost control on the icy covered roadway and slid off of the west edge of the roadway for approximately 50 feet while rotating 1/4 times clockwise. Vehicle #1 then collided with a barbed wire fence approximately 15 feet west of the road edge and overturned 1/4 times onto its left. Vehicle #1 came to final rest on its left side, approximately 15 feet west of the road edge facing west.
2021-09-13	3	VOLLMER RD	POCO RD	Vehicle #1 was traveling southbound on Vollmer Road. Vehicle #2 was parked on Poco Road, facing east, just west of the intersection of Vollmer Rd. and Poco Rd. Vehicle #2 was partially in the lane and partially on what would be a shoulder, as the entire road is dirt. Vehicle #3 was parked likewise, behind vehicle #2. Vehicle #1 made a right hand turn, to travel westbound on Poco Rd. The left front of vehicle #1 crashed into the left front of vehicle #2. Vehicle #2, being on dirt, slid backwards into the front of vehicle #3. Both vehicles #2 and #3 were unoccupied. Vehicle #1 pulled through and pulled over further down Poco Road to a safe location.
2021-11-11	1	VOLLMER RD	POCO RD	Vehicle #1 was travelling northbound on Vollmer Rd approaching Poco Rd. Vehicle #1 failed to negotiate a curve to the left and travelled off the right side of the road. Vehicle #1 overcorrected to the left, travelled across both lanes of traffic, and drove off the left side of the road. Vehicle #1 rotated counter-clockwise and hit a trip point in the soft dirt. Vehicle #1 rolled 1 and 3/4 times, coming to rest on its left side facing southwest approximately 30 feet off the road. The driver of the vehicle was ejected out of the passenger window during the rollover and came to rest in the field approximately 50 feet northwest of the vehicle.
2022-04-07	1	VOLLMER RD	WILDFLOWER RD	Vehicle 1 was traveling southbound on Vollmer Rd approaching the intersection of Wildflower Rd. Vehicle 1 failed to negotiate a curve and drove off the right side of the roadway at the intersection of Wildflower Rd. Vehicle 1 drove approximately 19 feet off of the right side of the roadway impacting an embankment and came to final rest 85 feet south of Wildflower Rd on the southwest side of the intersection facing south.
2022-06-19	2	VOLLMER RD	LOCHWINNOCH LN	VEHICLE 1 WAS NORTHBOUND ON VOLLMER ROAD. VEHICLE 2 WAS NORTHBOUND ON VOLLMER ROAD, IN FRONT OF VEHICLE 1. VEHICLE 2 BEGAN TO SLOW TO MAKE A LEFT TURN ONTO LOCHWINNOCH ROAD. VEHICLE 1 ATTEMPTED TO PASS VEHICLE 2 ON THE LEFT SIDE IN A MARKED NO PASSING ZONE. VEHICLE 2 BEGAN TO MAKE THE LEFT TURN WHERE VEHICLE 2 WAS STRUCK IN THE FRONT DRIVERS SIDE, BY THE FRONT PASSENGER SIDE OF VEHICLE 1. THE COLLISION OCCURRED WITHIN THE SOUTHBOUND LANE OF VOLLMER ROAD. VEHICLE 1 THEN ROTATED 1/2 TIME CLOCKWISE ACROSS THE NORTHBOUND LANE. VEHICLE 1 THEN DROVE OFF THE NORTHBOUND SIDE OF THE ROAD AND OVERTURNED 1/2 TIME, COMING TO FINAL REST ON ITS ROOF FACING SOUTH. VEHICLE 2 CAME TO A CONTROLLED FINAL REST ON LOCHWINNOCH LN.
2022-07-03	1	VOLLMER RD	POCO RD	Motorcycle was traveling on Vollmer Rd headed northbound. Motorcycle traveled off the right side of the road. Motorcycle lost control and rolled multiple times, the rider was ejected. Motorcycle came to rest on the left side. Rider came to rest on his back.

# Sketch Plan Amendment

---



# STERLING RANCH SKETCH PLAN AMENDMENT

LAND USE LEGEND:	
44 AC. RESIDENTIAL: 0.2 DU/AC,	9 D.U.
33 AC. RESIDENTIAL: 0.4 DU/AC,	13 D.U.
35 AC. RESIDENTIAL: 1 DU/AC,	35 D.U.
163 AC. RESIDENTIAL: 2 DU/AC,	326 D.U.
790 AC. RESIDENTIAL: 3-5 DU/AC,	3,642 D.U.
86 AC. RESIDENTIAL: 5-8 DU/AC,	600 D.U.
47 AC. MIXED USE 8-25 DU/AC *	600 D.U.
57 AC. ELEMENTARY / K-8 SCHOOL	
18 AC. NEIGHBORHOOD PARK	
25 AC. COMMUNITY PARK	
62 AC. OPEN SPACE / PARK / GREENWAY	
43 AC. OPEN SPACE / BUFFER	
9 AC. UTILITY PARCEL	
5 AC. INDUSTRIAL	


TOTAL: 1,444 AC. \* COMMERCIAL/HIGH DENSITY RESIDENTIAL NOT NECESSARILY IN SAME BUILDING

TOTAL: 5,225 D.U. Max

## SYMBOL LEGEND:

- ROAD
- FULL MOVEMENT ACCESS POINT
- - - 100-YEAR FLOODPLAIN
- - - TRAIL
- - - BUFFER / OS TRAIL CORRIDOR / EASEMENT
- NEIGHBORHOOD PARK
- X,XXX' ACCESS SPACING (FEET)

## VICINITY MAP:



PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

Overall Development Dwelling Unit Table

Dwelling Units	04-029	SF-06-017	SF-19-004	SF-19-018	Sterling Ranch Fil 2 SF-20-015	Total Entitled Units	Remaining Developable Units	Maximum Dwelling Units
Dwelling Units	72	51	104	75	49	351	4874	5225

ROAD CLASSIFICATION TABLE

Roadway	Existing	2040 MTCP	2060 MTCP/CPP	Sterling Ranch Proposed
Vollmer Road	2 lane Collector - 60'	4 lane Minor - 100'	4 lane Minor - 100'	4 lane Minor - 100'
Briargate Parkway	4 lane Principal - 160'	4 lane Principal - 130'	4 lane Principal - 130'	4 lane Principal - 130'
Banning Lewis Ranch Parkway		4 lane Principal - 130'	4 lane Principal - 130'	4 lane Principal - 130'
Marksheffel Road	2 lane Principal -	4 lane Principal - 130'	4 lane Principal - 130'	TBD *

\*A deviation is requested for Marksheffel Road to be built to the City of Colorado Springs standards.

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT

COTTONWOOD CREEK

PUD RURAL RES.

A-5

School District 20 / School District 49

City of Colorado Springs

City of Colorado Springs

City of Colorado Springs

PUD VACANT

PUD VACANT</