

Please provide the actual well permit. This is just the test report.

FORM NO. GWS-31 01/93		WELL CONSTRUCTION AND TEST REPORT STATE OF COLORADO, OFFICE OF THE STATE ENGINEER		For Office Use only	
1. WELL PERMIT NUMBER		58342-F			
2. OWNER NAME(S)		ANTHONY DAMIANO			
Mailing Address		6221 W DEL RIO			
City, St, Zip		CHANDLER, AZ 85228			
Phone (480)		699-0859			
3. WELL LOCATION AS DRILLED: NE 1/4 SW 1/4, Sec 18 Twp. 14 SOUTH Range 67 WEST					
DISTANCES FROM SEC. LINES: 2500 ft. from SOUTH Sec. line, and 1450 ft from WEST Sec. line. OR					
SUBDIVISION: CRYSTAL PARK CHRISTIAN COMMUNITY LOTS 157 BLOCK FILING(UNIT) 2					
STREET ADDRESS AT WELL LOCATION:					
4. GROUND SURFACE ELEVATION _____ ft. DRILLING METHOD Air Percussion					
DATE COMPLETED 10/15/02 TOTAL DEPTH 300 ft. DEPTH COMPLETED 300 ft.					
5. GEOLOGIC LOG:			6. HOLE DIAM. (in.)		
Depth Description of Material (Type, Size, Color, Water Location)			From (ft) To (ft)		
0 - 30X GRANITE, BROWN, GREY, TAN LAYERS			8 5/8 0 40		
			6 1/8 40 300		
7. PLAIN CASING					
OD (in)		Kind	Wall Size	From(ft)	To(ft)
8 5/8		Steel	.188	+1	41
4		PVC	SCH 40	10	240
4		PVC	SCH 40	280	300
PERF. CASING: Screen Slot Size: 035					
4		PVC	SCH 40	240	280
8. FILTER PACK:			9. PACKER PLACEMENT:		
Material N/A			Type N/A		
Size _____			Depth _____		
Interval _____					
10. GROUTING RECORD:					
Material	Amount	Density	Interval	Placement	
Portland	5 sack	15#pg	9-41	pour/vibrate	
REMARKS:					
11. DISINFECTION Type Granular Chlorine Amt. Used 2 CUPS					
12. WELL TEST DATA. <input type="checkbox"/> Check box if Test Data is submitted on Form No. GWS 39 Supplemental Well Test.					
TESTING METHOD Air lift					
Static Level 180 ft.		Date/Time measured 10/15/02		Production Rate 6 gpm.	
Pumping level 300 ft.		Date/Time measured 10/15/02		Test length (hrs.) 2	
Remarks					
13. I have read the statements made herein and know the contents thereof and that they are true to my knowledge. [Pursuant to Section 24-4-104 (13)(a) C.R.S. the making of false statements herein constitutes perjury in the second degree and is punishable as a class 1 misdemeanor.]					
CONTRACTOR Black Mountain Drilling		Phone (719) 687-5708		Lic. No. 1261	
Mailing Address P O Box 644, Divide, CO 80814					
Name/Title (Please type or print)		Signature		Date	
David D Wiley Contractor		<i>David Wiley</i>		10/21/02	