



GENERAL CONSTRUCTION NOTES:

1. OWNER FURNISHED MATERIALS, T-MOBILE "THE COMPANY" WILL PROVIDE AND THE CONTRACTOR WILL INSTALL
- A. BTS EQUIPMENT FRAME (PLATFORM) AND ICEBRIDGE SHELTER (GROUND BUILD/CO-LOCATE ONLY)

B. AC/TELCO INTERFACE BOX (PPC)

C. ICE BRIDGE (CABLE TRAY WITH COVER) (GROUND BUILD/CO-LOCATE ONLY, GC TO FURNISH AND INSTALL FOR ROOFTOP INSTALLATION)

D. TOWERS, MONOPOLES

E. TOWER LIGHTING

F. GENERATORS & LIQUID PROPANE TANK

G. ANTENNA STANDARD BRACKETS, FRAMES AND PIPES FOR MOUNTING

H. ANTENNAS (INSTALLED BY OTHERS)

I. TRANSMISSION LINE

J. TRANSMISSION LINE JUMPERS

K. TRANSMISSION LINE CONNECTORS WITH WEATHERPROOFING KITS

L. TRANSMISSION LINE GROUND KITS

M. HANGERS

N. HOISTING GRIPS

O. BTS EQUIPMENT
2. THE CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL OTHER MATERIALS FOR THE COMPLETE INSTALLATION OF THE SITE INCLUDING, BUT NOT LIMITED TO, SUCH MATERIALS AS FENCING, STRUCTURAL STEEL SUPPORTING SUB-FRAME FOR PLATFORM, ROOFING LABOR AND MATERIALS, GROUNDING RINGS, GROUNDING WIRES, COPPER-CLAD OR XIT CHEMICAL GROUND ROD(S), BUSS BARS, TRANSFORMERS AND DISCONNECT SWITCHES WHERE APPLICABLE, TEMPORARY ELECTRICAL POWER, CONDUIT, LANDSCAPING COMPOUND STONE, CRANES, CORE DRILLING, SLEEPERS AND RUBBER MATTING, REBAR, CONCRETE CAISSONS, PADS AND/OR AUGER MOUNTS, MISCELLANEOUS FASTENERS, CABLE TRAYS, NON-STANDARD ANTENNA FRAMES AND ALL OTHER MATERIAL AND LABOR REQUIRED TO COMPLETE THE JOB ACCORDING TO THE DRAWINGS AND SPECIFICATIONS. IT IS THE POSITION OF T-MOBILE TO APPLY FOR PERMITTING AND CONTRACTOR RESPONSIBLE FOR PICKUP AND PAYMENT OF REQUIRED PERMITS.
3. ALL WORK SHALL CONFORM TO ALL CURRENT APPLICABLE FEDERAL, STATE, AND LOCAL CODES, INCLUDING ANSI/EIA/TIA-222, AND COMPLY WITH ATC CONSTRUCTION SPECIFICATIONS.
4. CONTRACTOR SHALL CONTACT LOCAL 811 FOR IDENTIFICATION OF UNDERGROUND UTILITIES PRIOR TO START OF CONSTRUCTION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED INSPECTIONS.
6. ALL DIMENSIONS TO, OF, AND ON EXISTING BUILDINGS, DRAINAGE STRUCTURES, AND SITE IMPROVEMENTS SHALL BE VERIFIED IN FIELD BY CONTRACTOR WITH ALL DISCREPANCIES REPORTED TO THE ENGINEER.
7. DO NOT CHANGE SIZE OR SPACING OF STRUCTURAL ELEMENTS.
8. DETAILS SHOWN ARE TYPICAL; SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS UNLESS OTHERWISE NOTED.
9. THESE DRAWINGS DO NOT INCLUDE NECESSARY COMPONENTS FOR CONSTRUCTION SAFETY WHICH SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
10. CONTRACTOR SHALL BRACE STRUCTURES UNTIL ALL STRUCTURAL ELEMENTS NEEDED FOR STABILITY ARE INSTALLED. THESE ELEMENTS ARE AS FOLLOWS: LATERAL BRACING, ANCHOR BOLTS, ETC.
11. CONTRACTOR SHALL DETERMINE EXACT LOCATION OF EXISTING UTILITIES, GROUNDS DRAINS, DRAIN PIPES, VENTS, ETC. BEFORE COMMENCING WORK.
12. INCORRECTLY FABRICATED, DAMAGED, OR OTHERWISE MISFITTING OR NONCONFORMING MATERIALS OR CONDITIONS SHALL BE REPORTED TO THE T-MOBILE REP PRIOR TO REMEDIAL OR CORRECTIVE ACTION. ANY SUCH REMEDIAL ACTION SHALL REQUIRE WRITTEN APPROVAL BY THE T-MOBILE REP PRIOR TO PROCEEDING.
13. EACH CONTRACTOR SHALL COOPERATE WITH THE T-MOBILE REP, AND COORDINATE HIS WORK WITH THE WORK OF OTHERS.
14. CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED BY CONSTRUCTION OF THIS PROJECT TO MATCH EXISTING PRE-CONSTRUCTION CONDITIONS TO THE SATISFACTION OF THE T-MOBILE CONSTRUCTION MANAGER.
15. ALL CABLE/CONDUIT ENTRY/EXIT PORTS SHALL BE WEATHERPROOFED DURING INSTALLATION USING A SILICONE SEALANT.
16. WHERE EXISTING CONDITIONS DO NOT MATCH THOSE SHOWN IN THIS PLAN SET, CONTRACTOR SHALL NOTIFY THE T-MOBILE REP AND ENGINEER OF RECORD IMMEDIATELY.
17. CONTRACTOR SHALL ENSURE ALL SUBCONTRACTORS ARE PROVIDED WITH A COMPLETE AND CURRENT SET OF DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.
18. CONTRACTOR SHALL REMOVE ALL RUBBISH AND DEBRIS FROM THE SITE AT THE END OF EACH DAY.
19. CONTRACTOR SHALL COORDINATE WORK SCHEDULE WITH AMERICAN TOWER CORPORATION (ATC) AND TAKE PRECAUTIONS TO MINIMIZE IMPACT AND DISRUPTION OF OTHER OCCUPANTS OF THE FACILITY.
20. CONTRACTOR SHALL FURNISH T-MOBILE AND AMERICAN TOWER CORPORATION (ATC) WITH A PDF MARKED UP AS-BUILT SET OF DRAWINGS UPON COMPLETION OF WORK.
21. PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COORDINATE WITH T-MOBILE REP TO DETERMINE WHAT, IF ANY, ITEMS WILL BE PROVIDED. ALL ITEMS NOT PROVIDED SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR. CONTRACTOR WILL INSTALL ALL ITEMS PROVIDED.

22. PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COORDINATE WITH T-MOBILE REP TO DETERMINE IF ANY PERMITS WILL BE OBTAINED BY CONTRACTOR. ALL REQUIRED PERMITS NOT OBTAINED BY T-MOBILE MUST BE OBTAINED, AND PAID FOR, BY THE CONTRACTOR.
23. CONTRACTOR SHALL INSTALL ALL SITE SIGNAGE IN ACCORDANCE WITH T-MOBILE SPECIFICATIONS AND REQUIREMENTS.
24. CONTRACTOR SHALL SUBMIT ALL SHOP DRAWINGS TO T-MOBILE FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
25. ALL EQUIPMENT SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND LOCATED ACCORDING TO T-MOBILE SPECIFICATIONS, AND AS SHOWN IN THESE PLANS.
26. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.
27. CONTRACTOR SHALL NOTIFY T-MOBILE REP A MINIMUM OF 48 HOURS IN ADVANCE OF POURING CONCRETE OR BACKFILLING ANY UNDERGROUND UTILITIES, FOUNDATIONS OR SEALING ANY WALL, FLOOR OR ROOF PENETRATIONS FOR ENGINEERING REVIEW AND APPROVAL.
28. CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SAFETY INCLUDING COMPLIANCE WITH ALL APPLICABLE OSHA STANDARDS AND RECOMMENDATIONS AND SHALL PROVIDE ALL NECESSARY SAFETY DEVICES INCLUDING PPE AND PPM AND CONSTRUCTION DEVICES SUCH AS WELDING AND FIRE PREVENTION, TEMPORARY SHORING, SCAFFOLDING, TRENCH BOXES/SLOPING, BARRIERS, ETC.
29. THE CONTRACTOR SHALL PROTECT AT HIS OWN EXPENSE, ALL EXISTING FACILITIES AND SUCH OF HIS NEW WORK LIABLE TO INJURY DURING THE CONSTRUCTION PERIOD. ANY DAMAGE CAUSED BY NEGLIGENCE ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, OR BY THE ELEMENTS DUE TO NEGLIGENCE ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, EITHER TO THE EXISTING WORK, OR TO HIS WORK OR THE WORK OF ANY OTHER CONTRACTOR, SHALL BE REPAIRED AT HIS EXPENSE TO THE OWNER'S SATISFACTION.
30. ALL WORK SHALL BE INSTALLED IN A FIRST CLASS, NEAT AND WORKMANLIKE MANNER BY MECHANICS SKILLED IN THE TRADE INVOLVED. THE QUALITY OF WORKMANSHIP SHALL BE SUBJECT TO THE APPROVAL OF THE T-MOBILE REP. ANY WORK FOUND BY THE T-MOBILE REP TO BE OF INFERIOR QUALITY AND/OR WORKMANSHIP SHALL BE REPLACED AND/OR REWORKED AT CONTRACTOR EXPENSE UNTIL APPROVAL IS OBTAINED.
31. IN ORDER TO ESTABLISH STANDARDS OF QUALITY AND PERFORMANCE, ALL TYPES OF MATERIALS LISTED HEREINAFTER BY MANUFACTURER'S NAMES AND/OR MANUFACTURER'S CATALOG NUMBER SHALL BE PROVIDED BY THESE MANUFACTURERS AS SPECIFIED.
32. T-MOBILE FURNISHED EQUIPMENT SHALL BE PICKED-UP AT THE T-MOBILE WAREHOUSE, NO LATER THAN 48HR AFTER BEING NOTIFIED INSURED, STORED, UNCRATE, PROTECTED AND INSTALLED BY THE CONTRACTOR WITH ALL APPURTENANCES REQUIRED TO PLACE THE EQUIPMENT IN OPERATION, READY FOR USE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE EQUIPMENT AFTER PICKING IT UP.
33. T-MOBILE OR HIS ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT ANY EQUIPMENT OR MATERIALS WHICH, IN HIS OWN OPINION ARE NOT IN COMPLIANCE WITH THE CONTRACT DOCUMENTS, EITHER BEFORE OR AFTER INSTALLATION AND THE EQUIPMENT SHALL BE REPLACED WITH EQUIPMENT CONFORMING TO THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE CONTRACTOR AT NO COST TO T-MOBILE OR THEIR ARCHITECT/ENGINEER.
- SPECIAL CONSTRUCTION
- ANTENNA INSTALLATION NOTES:
1. WORK INCLUDED:

A. ANTENNA AND COAXIAL CABLES ARE FURNISHED BY T-MOBILE UNDER A SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OD COORDINATION AND SITE ACCESS. ERECTION SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF PERSONNEL AND

B. INSTALL ANTENNA AS INDICATE ON DRAWINGS AND T-MOBILE SPECIFICATIONS.

C. INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS

D. INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE.

E. CONTRACTOR SHALL PROVIDE FOUR (4) SETS OF SWEEP TESTS USING ANRITZU-PACKARD 8713B RF SCALAR NETWORK ANALYZER. SUBMIT FREQUENCY DOMAIN REFLECTOMETER(FDR) TESTS RESULTS TO THE PROJECT MANAGER. SWEEP TESTS SHALL BE AS PER ATTACHED RFS "MINIMUM FIELD TESTING RECOMMENDED FOR ANTENNA AND HELIAX COAXIAL CABLE SYSTEMS" DATED 10/5/93. TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING SERVICE AND BE BOUND AND SUBMITTED WITHIN ONE WEEK OF WORK COMPLETION.

F. INSTALL COAXIAL CABLES AND TERMINATING BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTIONS BETWEEN THE ANTENNA AND EQUIPMENT PER MANUFACTURER'S REQUIREMENTS. TERMINATE ALL COAXIAL CABLE THREE (3) FEET IN EXCESS OF ENTRY PORT LOCATION UNLESS OTHERWISE STATED.

G. ANTENNA AND COAXIAL CABLE GROUNDING:
2. ALL EXTERIOR #6 GREED GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE WEATHER SEALED WITH RFS CONNECTORS/SPICE WEATHERPROOFING KIT #221213 OR EQUAL.
3. ALL COAXIAL CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL CABLE (NOT WITHIN BENDS)

ALL DISCREPANCIES FROM WHAT IS SHOWN ON THESE CONSTRUCTION DRAWINGS SHALL BE COMMUNICATED TO ATC ENGINEERING IMMEDIATELY FOR CORRECTION OR RE-DESIGN. FAILURE TO COMMUNICATE DIRECTLY WITH ATC ENGINEERING OR ANY CHANGES FROM THE DESIGN CONDUCTED WITHOUT PRIOR APPROVAL FROM ATC ENGINEERING SHALL BE THE SOLE RESPONSIBILITY OF THE GENERAL CONTRACTOR.



AMERICAN TOWER®  
ATC TOWER SERVICES, LLC  
3500 REGENCY PARKWAY  
SUITE 100  
CARY, NC 27518  
PHONE: (919) 468-0112

THE USE AND PUBLICATION OF THESE DRAWINGS SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OR THE SPECIFIED CARRIER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION.

REV.	DESCRIPTION	BY	DATE
△	FOR CONSTRUCTION	BP	11/09/20
△			
△			
△			
△			

ATC SITE NUMBER:

370609

ATC SITE NAME:

WIDEFIELD HIGH  
SCHOOL II

T-MOBILE SITE NAME:

WIDEFIELD-ATC-370609

SITE ADDRESS:

509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911

SEAL:



Authorized by "Patrick P. Barry"

13 Nov 2020 04:39:43

DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E

GENERAL NOTES

SHEET NUMBER:

G-002

REVISION:

0



SITE PLAN NOTES:


1.

THIS SITE PLAN REPRESENTS THE BEST PRESENT KNOWLEDGE AVAILABLE TO THE ENGINEER AT THE TIME OF THIS DESIGN. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO CONSTRUCTION AND VERIFY ALL EXISTING CONDITIONS RELATED TO THE SCOPE OF WORK FOR THIS PROJECT.
2.

ICE BRIDGE, CABLE LADDER, COAX PORT, AND COAX CABLE ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM THE EXACT LOCATION OF ALL PROPOSED AND EXISTING EQUIPMENT AND STRUCTURES DEPICTED ON THIS PLAN. BEFORE UTILIZING EXISTING CABLE SUPPORTS, COAX PORTS, INSTALLING NEW PORTS OR ANY OTHER EQUIPMENT, CONTRACTOR SHALL VERIFY ALL ASPECTS OF THE COMPONENTS MEET THE ATC SPECIFICATIONS.
3.

NO ELECTRICAL SCOPE IS INCLUDED IN THIS PROJECT.


LEGEND	
⊗	GROUNDING TEST WELL
ATS	AUTOMATIC TRANSFER SWITCH
B	BOLLARD
CSC	CELL SITE CABINET
D	DISCONNECT
E	ELECTRICAL
F	FIBER
GEN	GENERATOR
G	GENERATOR RECEPTACAL
HH, V	HAND HOLE, VAULT
IB	ICE BRIDGE
K	KENTROX BOX
LC	LIGHTING CONTROL
M	METER
PB	PULL BOX
PP	POWER POLE
T	TELCO
TRN	TRANSFORMER
— x —	CHAINLINK FENCE



- PROPOSED CABLE LENGTH:**
1.

ESTIMATED LENGTH OF PROPOSED CABLE IS **150'**. ESTIMATED LENGTH OF CABLE WAS PROVIDED BY CUSTOMER OR CALCULATED BY ADDING THE RAD CENTER AND THE DISTANCE FROM THE SHELTER ENTRY PLATE TO THE TOWER (ALONG THE ICE BRIDGE) AND A SAFETY FACTOR MEASUREMENT OF 15% (OF THE TWO PREVIOUS VALUES). CDS DEFER TO GREATEST CABLE LENGTH.
2.


ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. IF ADEQUATE SPACE EXISTS, ROUTE CABLES THROUGH ENTRY PORT HOLE, UP INSIDE OF MONOPOLE, AND THROUGH EXIT PORT HOLE. IF ROUTING OUTSIDE THE MONOPOLE, ATTACH CABLES USING STAND-OFF ADAPTERS MOUNTED TO TOWER USING STAINLESS STEEL BANDING. ADEQUATELY SECURE CABLES USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE MANUFACTURER.



THE USE AND PUBLICATION OF THESE DRAWINGS SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OR THE SPECIFIED CARRIER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION.

REV.	DESCRIPTION	BY	DATE
0	FOR CONSTRUCTION	BP	11/09/20

ATC SITE NUMBER:  
**370609**  
ATC SITE NAME:  
**WIDEFIELD HIGH SCHOOL II**  
T-MOBILE SITE NAME:  
**WIDEFIELD-ATC-370609**  
SITE ADDRESS:  
509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:43


DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E

DETAILED SITE PLAN

SHEET NUMBER:	REVISION:
<b>C-101</b>	<b>0</b>

SITE PLAN NOTES:

1. CONTRACTOR TO VERIFY THERE IS NO LIVE AAV FIBER RUNNING THROUGH EXISTING DEAD EQUIPMENT. IF SO, THIS WILL NEED TO BE RERUN THROUGH CONDUIT PRIOR TO REMOVING DEAD 2G (6201 CABS) EQUIPMENT.
2. REMOVE EXISTING 2G CABINETS, AND POWER / TELCO WHIPS ASSOCIATED WITH THE DEAD EQUIPMENT IF APPLICABLE.
3. ALL OPEN PORTS NEED TO BE SEALED / WEATHERPROOFED PROPERLY
4. ALL UNNEEDED / EXCESS EQUIPMENT AND GARBAGE TO BE REMOVED FROM EQUIPMENT AREA. DISPOSE OF MATERIALS PROPERLY OFF SITE.




1 EXISTING GROUND EQUIPMENT LAYOUT

0 5' 10'

SCALE: 1"=5' (11X17)  
1"=2.5' (22X34)

LEGEND	
	EXISTING EQUIPMENT TO BE REMOVED

T-MOBILE CM APPROVAL REQUIRED BEFORE INSTALLING CABINETS



2 PROPOSED GROUND EQUIPMENT LAYOUT

0 5' 10'

SCALE: 1"=5' (11X17)  
1"=2.5' (22X34)

LEGEND	
	PROPOSED EQUIPMENT TO BE INSTALLED



**AMERICAN TOWER®**  
**ATC TOWER SERVICES, LLC**  
3500 REGENCY PARKWAY  
SUITE 100  
CARY, NC 27518  
PHONE: (919) 468-0112

THE USE AND PUBLICATION OF THESE DRAWINGS SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OR THE SPECIFIED CARRIER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION.

REV.	DESCRIPTION	BY	DATE
0	FOR CONSTRUCTION	BP	11/09/20
1			
2			
3			
4			

ATC SITE NUMBER:  
**370609**  
ATC SITE NAME:  
**WIDEFIELD HIGH SCHOOL II**  
T-MOBILE SITE NAME:  
**WIDEFIELD-ATC-370609**  
SITE ADDRESS:  
509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911





Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:44

DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E

DETAILED GROUND PLAN

SHEET NUMBER:	REVISION:
<b>C-102</b>	<b>0</b>





PER MOUNT ANALYSIS COMPLETED BY MED,  
DATED 10/07/20, THE EXISTING MOUNT MUST BE  
MODIFIED TO ADEQUATELY SUPPORT THE  
PROPOSED LOADING. THE MOUNT MODIFICATION  
PROPOSED IN THE MOD DRAWINGS, INCLUDED  
AT THE END OF THIS PLAN SET, MUST BE  
INSTALLED PRIOR TO THE INSTALLATION OF THE  
PROPOSED ANTENNAS AND OTHER EQUIPMENT

- TOWER NOTE:
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO  
CONFIRM WITH THE PROJECT MANAGER THAT  
THEY HAVE THE MOST RECENT VERSION OF THE  
STRUCTURAL ANALYSIS BEFORE COMMENCING  
WORK. EXISTING AND PROPOSED TOWER  
APPURTENANCES, MOUNTS, AND ANTENNAS ARE  
SHOWN BASED ON THE STRUCTURAL ANALYSIS.
  - WHERE APPLICABLE, ALL NEW ANTENNAS,  
EQUIPMENT, MOUNTS, CABLING, ETC. SHALL BE  
PAINTED/SOCKED TO MATCH EXISTING EQUIPMENT  
IN ACCORDANCE WITH FAA, JURISDICTION, AND/OR  
OTHER LOCAL REQUIREMENTS.
  - ROUTE PROPOSED CABLES ALONG SAME PATH AS  
EXISTING CABLES AND IN ACCORDANCE WITH  
STRUCTURAL ANALYSIS. IF ADEQUATE SPACE  
EXISTS, ROUTE CABLES THROUGH ENTRY PORT  
HOLE, UP INSIDE OF MONOPOLE, AND THROUGH  
EXIT PORT HOLE. IF ROUTING OUTSIDE THE  
MONOPOLE, ATTACH CABLES USING STAND-OFF  
ADAPTERS MOUNTED TO TOWER USING STAINLESS  
STEEL BANDING. ADEQUATELY SECURE CABLES  
USING EITHER APPROPRIATELY SIZED STAINLESS  
STEEL SNAP-INS OR MOUNTING HARDWARE AND  
BRACKETS AS SPECIFIED BY CABLE  
MANUFACTURER.
  - TOWER ELEVATIONS ARE MEASURED FROM TOP  
OF BASE PLATE TO MATCH STRUCTURAL  
ANALYSIS. ELEVATIONS DO NOT REFLECT TRUE  
ABOVE GROUND LEVEL (A.G.L.)



**AMERICAN TOWER®**  
**ATC TOWER SERVICES, LLC**  
3500 REGENCY PARKWAY  
SUITE 100  
CARY, NC 27518  
PHONE: (919) 468-0112

THE USE AND PUBLICATION OF THESE DRAWINGS  
SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR  
WHICH THEY ARE PREPARED. ANY USE OR  
DISCLOSURE OTHER THAN THAT WHICH RELATES  
TO AMERICAN TOWER OR THE SPECIFIED CARRIER  
IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT  
NOR THE ENGINEER WILL BE PROVIDING ON-SITE  
CONSTRUCTION REVIEW OF THIS PROJECT.  
CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS  
AND ADVISE AMERICAN TOWER OR THE SPECIFIED  
CARRIER OF ANY DISCREPANCIES. ANY PRIOR  
ISSUANCE OF THIS DRAWING IS SUPERSEDED BY  
THE LATEST VERSION.

REV.	DESCRIPTION	BY	DATE
0	FOR CONSTRUCTION	BP	11/09/20

ATC SITE NUMBER:  
**370609**  
ATC SITE NAME:  
**WIDEFIELD HIGH  
SCHOOL II**  
T-MOBILE SITE NAME:  
**WIDEFIELD-ATC-370609**  
SITE ADDRESS:  
509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911

SEAL:





Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:44

DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E

TOWER ELEVATION

SHEET NUMBER:	REVISION:
C-201	0



PER MOUNT ANALYSIS COMPLETED BY MED, DATED 10/07/20. THE EXISTING MOUNT MUST BE MODIFIED TO ADEQUATELY SUPPORT THE PROPOSED LOADING. THE MOUNT MODIFICATION PROPOSED IN THE MOD DRAWINGS, INCLUDED AT THE END OF THIS PLAN SET, MUST BE INSTALLED PRIOR TO THE INSTALLATION OF THE PROPOSED ANTENNAS AND OTHER EQUIPMENT

EXISTING ANTENNA SCHEDULE								
LOCATION			ANTENNA SUMMARY				NON ANTENNA SUMMARY	
SECTOR	RAD	AZ	POS	ANTENNA	BAND	MECH/ELEC D-TILT	STATUS	ADDITIONAL TOWER MOUNTED EQUIPMENT
ALPHA	108'	340°	A1	—	—	—	—	FRLB
			A2	FASB	L700,L1900,U2100,L2100	0°/2°	RMV	—
BETA	108'	100°	B1	—	—	—	—	FRLB
			B2	FASB	L700,L1900,U2100,L2100	0°/2°	RMV	—
GAMMA	108'	220°	C1	—	—	—	—	FRLB
			C2	FASB	L700,L1900,U2100,L2100	0°/2°	RMV	—

- NOTES
1. CONFIRM WITH T-MOBILE REP FOR APPLICABLE UPDATES/REVISIONS AND MOST RECENT RFDS FOR NSN CONFIGURATION (CONFIG). GC TO CAP ALL UNUSED PORTS.
  2. CONFIRM SPACING OF PROPOSED EQUIP DOES NOT CAUSE TOWER CONFLICTS NOR IMPEDE TOWER CLIMBING PEGS.

STATUS ABBREVIATIONS

RMV: TO BE REMOVED  
RMN: TO REMAIN  
REL: TO BE RELOCATED  
ADD: TO BE ADDED

CABLE LENGTHS FOR JUMPERS


JUNCTION BOX TO RRU: 15'  
RRU TO ANTENNA: 10'

FINAL ANTENNA SCHEDULE									
LOCATION			ANTENNA SUMMARY				NON ANTENNA SUMMARY		
SECTOR	RAD	AZ	POS	ANTENNA	BAND	MECH/ELEC D-TILT	STATUS	ADDITIONAL TOWER MOUNTED EQUIPMENT	STATUS
ALPHA	108'	340°	A1	FFHH-65C-R3	L700,L600,N600,U2100,L2100,L1900	0°	ADD	AHFIG AHLOA	ADD
			A2	AEHC	L2500,N2500	0°	ADD	-	-
BETA	108'	100°	B1	FFHH-65C-R3	L700,L600,N600,U2100,L2100,L1900	0°	ADD	AHFIG AHLOA	ADD
			B2	AEHC	L2500,N2500	0°	ADD	-	-
GAMMA	108'	220°	C1	FFHH-65C-R3	L700,L600,N600,U2100,L2100,L1900	0°	ADD	AHFIG AHLOA	ADD
			C2	AEHC	L2500,N2500	0°	ADD	-	-

EXISTING FIBER DISTRIBUTION/OVP BOX		EXISTING CABLING SUMMARY		
MODEL NUMBER	STATUS	COAX	HYBRID	STATUS
COVP	RMV	—	(1) 150' NSN HIGHCAP HCS	RMV
—	—	—	—	—

3 EQUIPMENT SCHEDULES

FINAL FIBER DISTRIBUTION / OVP BOX		FINAL CABLING SUMMARY		
MODEL NUMBER	STATUS	COAX	HYBRID	STATUS
(2) HELIAX FIBERFEED 12 RRU PENDANT CONNECT	ADD	-	(2) 150' HCS 2.0 TRUNK-12#6AWG 24 SM FIBER PR	ADD
-	-	-	-	-




**AMERICAN TOWER®**  
**ATC TOWER SERVICES, LLC**  
3500 REGENCY PARKWAY  
SUITE 100  
CARY, NC 27518  
PHONE: (919) 468-0112

THE USE AND PUBLICATION OF THESE DRAWINGS SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OR THE SPECIFIED CARRIER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION.


REV.	DESCRIPTION	BY	DATE
0	FOR CONSTRUCTION	BP	11/09/20
1			
2			
3			
4			

ATC SITE NUMBER:  
**370609**  
ATC SITE NAME:  
**WIDEFIELD HIGH SCHOOL II**  
T-MOBILE SITE NAME:  
**WIDEFIELD-ATC-370609**  
SITE ADDRESS:  
509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911

SEAL:



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:45




DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E


**ANTENNA INFORMATION & SCHEDULE**

SHEET NUMBER: <b>C-401</b>	REVISION: <b>0</b>
-------------------------------	-----------------------






1 PROPOSED ANTENNA MOUNTING DETAIL - TYPICAL  
SCALE: N.T.S.



2 PROPOSED 5G ANTENNA MOUNTING DETAIL - TYPICAL  
SCALE: N.T.S.



3 PROPOSED RRU MOUNTING DETAIL - TYPICAL  
SCALE: N.T.S.



**AMERICAN TOWER®**  
**ATC TOWER SERVICES, LLC**  
3500 REGENCY PARKWAY  
SUITE 100  
CARY, NC 27518  
PHONE: (919) 468-0112

THE USE AND PUBLICATION OF THESE DRAWINGS SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OR THE SPECIFIED CARRIER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION.

REV.	DESCRIPTION	BY	DATE
0	FOR CONSTRUCTION	BP	11/09/20

ATC SITE NUMBER:  
**370609**  
ATC SITE NAME:  
**WIDEFIELD HIGH SCHOOL II**  
T-MOBILE SITE NAME:  
**WIDEFIELD-ATC-370609**  
SITE ADDRESS:  
509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911

SEAL:




Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:45

DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E

## CONSTRUCTION DETAILS


SHEET NUMBER:	REVISION:
<b>C-501</b>	<b>0</b>



NOTES:

- THIS DETAIL IS INTENDED TO SHOW THE GENERAL GROUNDING REQUIREMENTS. SLIGHT ADJUSTMENTS MAY BE REQUIRED BASED ON EXISTING SITE CONDITIONS. THE CONTRACTOR SHALL MAKE FIELD ADJUSTMENTS AS NEEDED AND INFORM THE CONSTRUCTION MANAGER OF ANY CONFLICTS.
- SITE GROUNDING SHALL COMPLY WITH T-MOBILE GROUNDING STANDARDS, LATEST EDITION, AND COMPLY WITH T-MOBILE GROUNDING CHECKLIST, LATEST VERSION. WHEN NATIONAL AND LOCAL GROUNDING CODES ARE MORE STRINGENT THEY SHALL GOVERN.


1 TYPICAL ANTENNA GROUNDING DIAGRAM  
SCALE: N.T.S.



GROUND KIT NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
- CONTRACTOR SHALL PROVIDE WEATHERPROOFING KIT (ANDREW PART NUMBER 221213) AND INSTALL/TAPE PER MANUFACTURER'S SPECIFICATIONS.

2 CABLE GROUND KIT CONNECTION DETAIL  
SCALE: N.T.S.



GROUND BAR NOTES:

- GROUND BAR KITS COME WITH ALL HARDWARE, NUTS, BOLTS, WASHERS, ETC. EXCEPT THE STRUCTURAL MOUNTING MEMBER(S).
- GROUND BAR TO BE BONDED DIRECTLY TO TOWER.

3 TOWER GROUND BAR DETAIL  
SCALE: N.T.S.

ELECTRICAL NOTES:

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH THE T-MOBILE REPRESENTATIVE AND LOCAL UTILITY COMPANY FOR THE INSTALLATION OF CONDUITS, CONDUCTORS, BREAKERS, DISCONNECTS, OR ANY OTHER EQUIPMENT REQUIRED FOR ELECTRICAL SERVICE. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH LATEST EDITION OF THE STATE AND NATIONAL CODES, ORDINANCES AND REGULATIONS APPLICABLE TO THIS PROJECT.
- ATC HAS NOT VERIFIED ANY EXISTING T-MOBILE GROUND EQUIPMENT OR ELECTRICAL LOADING. PROPOSED WORK BASED ON INSTALLATION CONFIGURATION PROVIDED BY T-MOBILE. CONTRACTOR TO VERIFY EXISTING T-MOBILE PANEL HAS SUFFICIENT SPACE FOR PROPOSED BREAKER. PROPOSED CABLE AND CONDUIT SHALL BE MINIMUM SIZE PER BELOW:

OCPD SIZE	WIRE SIZE	GROUND SIZE	CONDUIT SIZE
80A/2P	2#3 AWG	#8 AWG	1-1/4"
100/2P	2#2 AWG	#8 AWG	1-1/4"
125A/2P	2#1 AWG	#8 AWG	1-1/2"
150A/2P	2#1/0 AWG	#8 AWG	1-1/2"

THE USE AND PUBLICATION OF THESE DRAWINGS SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OR THE SPECIFIED CARRIER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION.

REV.	DESCRIPTION	BY	DATE
Δ	FOR CONSTRUCTION	BP	11/09/20
Δ			
Δ			
Δ			
Δ			

ATC SITE NUMBER:  
**370609**  
ATC SITE NAME:  
**WIDEFIELD HIGH SCHOOL II**  
T-MOBILE SITE NAME:  
**WIDEFIELD-ATC-370609**  
SITE ADDRESS:  
509 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911

SEAL:



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:46

DATE DRAWN:	11/09/20
ATC JOB NO:	13323293_G3
CUSTOMER ID:	WIDEFIELD-ATC-370609
CUSTOMER #:	DN04166E

GROUNDING DETAILS

SHEET NUMBER:  
**E-501**  
REVISION:  
**0**






MANUFACTURER: DELTA  
MODEL: HPL3 SITE SUPPORT CABINET  
WEIGHT: 551 LBS (WITHOUT EQUIPMENT)  
DIMENSIONS: 30.0"x35.0"x72.0"

NOTE:


- CORRECT KNOCKOUT TOOL REQUIRED FOR PUNCHING KNOCKOUTS. DO NOT DRILL KNOCKOUTS THROUGH
- CONDUIT MUST BE PROPERLY SECURED TO PREVENT DAMAGE TO CABINETS AND/OR CABLING

RACK ASSIGNMENT		
RU SLOT	DESCRIPTION	DESCRIPTION
27		CSR-SAR/SAS
26		
25		
24	AIRSCALE	
23		
22	FIBER MUX	
21		AIRSCALE
20		
19		
18	FIBER MUX	
17		AIRSCALE
16		
15		
14	FIBER MUX	
13		AIRSCALE
12		
11		
10	FIBER MUX	
9		LEGACY BASEBAND
8		
7		
6		
5		LEGACY BASEBAND
4		
3		
2		
1		


SHIPPING HOOKS TO BE REMOVED AFTER CABINET INSTALL




ISO VIEW N.T.S.



REAR VIEW



FRONT VIEW



PLAN VIEW

(4X) 5/8"Ø FOR CABINET ANCHORAGE

KNOCKOUT

DC CABLES (RED)

FIBER CABLES (YELLOW)

KNOCKOUT

ETHERNET CABLES (BLUE)


KNOCKOUT

ACCESS PANEL


INTERNAL ROUTING

SKU# 33554 DELTA 6in PLINTH PLAN VIEW


SKU# 33554 DELTA 6in PLINTH SIDE VIEW



LEFT VIEW



RIGHT VIEW



FRONT VIEW (OPEN)

SKU# 33929 - DELTA HPL3 SITE SUPPORT CABINET

22"x34" SCALE: N.T.S. 11"x17" SCALE: N.T.S.

EQUIPMENT SPECIFICATIONS

SHEET NUMBER:

R-602

REVISION:

0


NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED AT THE REQUEST OF THE CUSTOMER WITHOUT EDIT.




MANUFACTURER: DELTA  
MODEL: LB3 BATTERY SUPPORT CABINET  
WEIGHT: 509 LBS (WITHOUT EQUIPMENT)  
DIMENSIONS: 30.0"x35.0"x72.0"

NOTE:


- CORRECT KNOCKOUT TOOL REQUIRED FOR PUNCHING KNOCKOUTS. DO NOT DRILL KNOCKOUTS THROUGH
- CONDUIT MUST BE PROPERLY SECURED TO PREVENT DAMAGE TO CABINETS AND/OR CABLING




SKU# 33554 DELTA 6in PLINTH PLAN VIEW    SKU# 33554 DELTA 6in PLINTH SIDE VIEW




PLAN VIEW




PLAN VIEW (ANCHORAGE)




ISO VIEW  
N.T.S.



LEFT VIEW



FRONT VIEW



FRONT VIEW  
(OPEN)

SKU# 33932 - DELTA LB3 BATTERY SUPPORT CABINET

22"x34" SCALE: N.T.S.    11"x17" SCALE: N.T.S.

1

## EQUIPMENT SPECIFICATIONS

SHEET NUMBER:

R-603

REVISION:

0



Eng. Number 13323293\_C8\_01  
October 6, 2020  
Page 1

## Antenna Mount Analysis Report

ATC Site Name : Widefield High School II, CO  
ATC Site Number : 370609  
Engineering Number : 13323293\_C8\_01  
Mount Elevation : 105 ft  
Carrier : T-Mobile  
Carrier Site Name : Widefield - ATC 370609  
Carrier Site Number : DN04166E  
Site Location : 523 Widefield Drive  
Colorado Springs, CO 80911-0000  
38.75483333, -104.7305556  
County : El Paso  
Date : October 6, 2020  
Max Usage : 153%  
Result : Fail

Prepared By:  
Rohith Koduru  
Structural Engineer I

Reviewed By:



Authorized by "EOR"  
07 Oct 2020 10:14:03 cosign

### Introduction

The purpose of this report is to summarize results of the antenna mount analysis performed for T-Mobile at 105 ft.

### Supporting Documents

Specifications Sheet	Site Pro 1 SNP8HR-396, dated November 21, 2014
Radio Frequency Data Sheet	RFDS ID #DN04166E, dated May 11, 2020
Reference Photos	Site photos from 2020

### Analysis

This antenna mount was analyzed using American Tower Corporation's Mount Analysis Program and RISA-3D

Basic Wind Speed:	130 mph (3-Second Gust)
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 1/4" radial ice concurrent
Codes:	ANSI/TIA-222-H / 2018 IBC
Exposure Category:	C
Risk Category:	II
Topographic Factor Procedure:	Method 2
Feature:	Flat
Crest Height (H):	0 ft
Crest Length (L):	0 ft
Spectral Response:	Ss = 0.185, S1 = 0.059
Site Class:	D - Stiff Soil
Live Loads: *	Lm = 500 lbs

\* Based on experience, it has been determined that the Lv load cases will not control over Lm load cases in platform mount analyses. Therefore, these load cases have been excluded from this analysis.

### Conclusion

Based on the analysis results, the antenna mount does not meet the requirements per the applicable codes listed above. The mount can support the equipment as described in this report after the modifications listed below are completed:

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED AT THE REQUEST OF THE CUSTOMER WITHOUT EDIT. PLEASE REFERENCE THE MOUNT ANALYSIS REPORT FOR COMPLETE MOUNT ANALYSIS CALCULATIONS AND DETAILS. SUPPLEMENTAL PAGES INCLUDED IN THE CONSTRUCTION DRAWINGS ARE FOR REFERENCE ONLY. GENERAL CONTRACTOR IS TO VERIFY THEY HAVE THE MOST RECENT MOUNT ANALYSIS PRIOR TO CONTRUCTION.

SUPPLEMENTAL

SHEET NUMBER:	REVISION:
R-604	0






GENERAL

1. ALL WORK TO BE COMPLETED PER APPLICABLE LOCAL, STATE, FEDERAL CODES AND ORDINANCES AND COMPLY WITH ATC CONSTRUCTION SPECIFICATIONS FOR WIRELESS TOWER SITES. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND ABIDING BY ALL REQUIRED PERMITS.
2. ALL WORK INDICATED ON THESE DRAWINGS SHALL BE PERFORMED BY QUALIFIED CONTRACTORS EXPERIENCED IN TOWER AND FOUNDATION CONSTRUCTION.
3. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IMMEDIATELY OF ANY INSTALLATION INTERFERENCES. ALL NEW WORK SHALL ACCOMMODATE EXISTING CONDITIONS. DETAILS NOT SPECIFICALLY SHOWN ON THE DRAWINGS SHALL FOLLOW SIMILAR DETAILS FOR THIS JOB.
4. ANY SUBSTITUTIONS SHALL CONFORM TO THE REQUIREMENTS OF THESE NOTES AND SPECIFICATIONS, AND SHOULD BE SIMILAR TO THOSE SHOWN. ALL SUBSTITUTIONS SHALL BE SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
5. ANY MANUFACTURED DESIGN ELEMENTS SHALL CONFORM TO THE REQUIREMENTS OF THESE NOTES AND SPECIFICATIONS AND SHOULD BE SIMILAR TO THOSE SHOWN. THESE DESIGN ELEMENTS MUST BE STAMPED BY AN ENGINEER PROFESSIONALLY REGISTERED IN THE STATE OF THE PROJECT, AND SUBMITTED TO THE ENGINEER OF RECORD FOR APPROVAL PRIOR TO FABRICATION.
6. ALL WORK SHALL BE DONE IN ACCORDANCE WITH LOCAL CODES AND OSHA SAFETY REGULATIONS.
7. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND EXECUTION OF ALL MISCELLANEOUS SHORING, BRACING, TEMPORARY SUPPORTS, ETC. NECESSARY, PER ANSI/TIA-322 AND ANSI/ASSE A10.48, TO PROVIDE A COMPLETE AND STABLE STRUCTURE AS SHOWN ON THESE DRAWINGS.
8. CONTRACTOR'S PROPOSED INSTALLATION SHALL NOT INTERFERE, NOR DENY ACCESS TO, ANY EXISTING OPERATIONAL AND SAFETY EQUIPMENT.

STRUCTURAL STEEL

1. ALL DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE AISC SPECIFICATIONS, LATEST EDITION.
2. ALL EXPOSED STRUCTURAL STEEL MEMBERS SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION PER ASTM A123. EXPOSED STEEL HARDWARE AND ANCHOR BOLTS SHALL BE GALVANIZED PER ASTM A153 OR B695.
3. ALL U-BOLTS SHALL BE ASTM A36 OR EQUIVALENT, WITH LOCKING DEVICE, UNLESS NOTED OTHERWISE.
4. FIELD CUT EDGES, EXCEPT DRILLED HOLES, SHALL BE GROUND SMOOTH.
5. ALL FIELD CUT SURFACES, FIELD DRILLED HOLES & GROUND SURFACES WHERE EXISTING PAINT OR GALVANIZATION REMOVAL WAS REQUIRED SHALL BE REPAIRED WITH (2) BRUSHED COATS OF ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURERS RECOMMENDATIONS.
6. ALL STRUCTURAL STEEL EMBEDDED IN THE CONCRETE SHALL BE APPLIED WITH (2) BRUSHED COATS OF POLYGUARD CA-14 MASTIC OR EQUIVALENT. REFER TO THE MANUFACTURER SPECIFICATIONS FOR SURFACE PREPARATION AND APPLICATION. APPLICATION OF POLYGUARD 400 WRAP IS NOT ESSENTIAL.
7. CONTRACTOR SHALL PERFORM WORK ON ONLY ONE (1) TOWER FACE AND REPLACE/REINFORCE ONE (1) BOLT/MEMBER AT A TIME.
8. ALL FIELD DRILLED HOLES TO BE USED FOR FIELD BOLTING INSTALLATION SHALL BE STANDARD HOLES, AS DEFINED BY AISC, UNLESS NOTED OTHERWISE.



PAINT

1. AS REQUIRED, CLEAN AND PAINT PROPOSED STEEL ACCORDING TO FAA ADVISORY CIRCULAR AC 70/7460-1L.

WELDING

1. ALL WELDING TO BE PERFORMED BY AWS CERTIFIED WELDERS AND CONDUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE AWS WELDING CODE D1.1.
2. ALL WELDS SHALL BE INSPECTED VISUALLY. IF DIRECTED BY ENGINEER OF RECORD, 25% OF WELDS SHALL BE INSPECTED WITH DYE PENETRANT OR MAGNETIC PARTICLE (100% IF REJECTABLE DEFECTS ARE FOUND) TO MEET THE ACCEPTANCE CRITERIA OF AWS D1.1. REPAIR ALL WELDS AS NECESSARY.
3. INSPECTION SHALL BE PERFORMED BY AN AWS CERTIFIED WELD INSPECTOR.
4. ALL ELECTRODES TO BE LOW HYDROGEN, MATCHING FILLER AND/OR BASE METAL, PER AWS D1.1, UNLESS NOTED OTHERWISE.
5. IN CASES WHERE BASE METAL GRADE IS UNKNOWN, ALL WELDING ON LATTICE TOWERS SHALL BE DONE WITH E70XX ELECTRODES; ALL WELDING ON POLE STRUCTURES SHALL BE DONE WITH E80XX ELECTRODES, UNLESS NOTED OTHERWISE.
6. PRIOR TO FIELD WELDING GALVANIZED MATERIAL, CONTRACTOR SHALL GRIND OFF GALVANIZING 1/2" BEYOND ALL FIELD WELD SURFACES. AFTER WELD AND WELD INSPECTION IS COMPLETE, REPAIR ALL GROUND AND WELDED SURFACES WITH ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURERS RECOMMENDATIONS.

BOLT TIGHTENING PROCEDURE

1. STRUCTURAL CONNECTIONS TO BE ASSEMBLED AND INSPECTED IN ACCORDANCE WITH RCSC SPECIFICATIONS.
2. FLANGE BOLTS SHALL BE INSTALLED AND TIGHTENED USING DIRECT TENSION INDICATING (DTI) SQUIRTER WASHERS. DTI SQUIRTER WASHERS ARE TO BE INSTALLED AND ORIENTED / TIGHTENED PER MANUFACTURER SPECIFICATIONS TO ACHIEVE DESIRED LEVEL OF BOLT PRE-TENSION.
3. IN LIEU OF USING DTI SQUIRTER WASHERS, FLANGE BOLTS MAY BE TIGHTENED USING AISC / RCSC "TURN-OF-THE-NUT" METHOD, PENDING APPROVAL BY THE ENGINEER OF RECORD (EOR). TIGHTEN FLANGE BOLTS USING THE CHART BELOW:

BOLT LENGTHS UP TO AND INCLUDING FOUR DIAMETERS

1/2"	BOLTS UP TO AND INCLUDING 2.0 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
5/8"	BOLTS UP TO AND INCLUDING 2.5 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
3/4"	BOLTS UP TO AND INCLUDING 3.0 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
7/8"	BOLTS UP TO AND INCLUDING 3.5 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
1"	BOLTS UP TO AND INCLUDING 4.0 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
1-1/8"	BOLTS UP TO AND INCLUDING 4.5 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
1-1/4"	BOLTS UP TO AND INCLUDING 5.0 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
1-3/8"	BOLTS UP TO AND INCLUDING 5.5 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT
1-1/2"	BOLTS UP TO AND INCLUDING 6.0 INCH LENGTH	+1/3 TURN BEYOND SNUG TIGHT

BOLT LENGTHS OVER FOUR DIAMETERS BUT NOT EXCEEDING EIGHT DIAMETERS

1/2"	BOLTS 2.25 TO 4.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
5/8"	BOLTS 2.75 TO 5.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
3/4"	BOLTS 3.25 TO 6.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
7/8"	BOLTS 3.75 TO 7.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1"	BOLTS 4.25 TO 8.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1-1/8"	BOLTS 4.75 TO 9.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1-1/4"	BOLTS 5.25 TO 10.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1-3/8"	BOLTS 5.75 TO 11.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1-1/2"	BOLTS 6.25 TO 12.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT

BOLT TIGHTENING PROCEDURE (CONTINUED)

4. SPLICE BOLTS SUBJECT TO DIRECT TENSION SHALL BE INSTALLED AND TIGHTENED AS PER SECTION 8.2.1 OF THE AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING A325 OR A490 BOLTS", LOCATED IN THE AISC MANUAL OF STEEL CONSTRUCTION. THE INSTALLATION PROCEDURE IS PARAPHRASED AS FOLLOWS:

FASTENERS SHALL BE INSTALLED IN PROPERLY ALIGNED HOLES AND TIGHTENED BY ONE OF THE METHODS DESCRIBED IN SUBSECTION 8.2.1 THROUGH 8.2.4.

8.2.1 TURN-OF-NUT PRETENSIONING  
BOLTS SHALL BE INSTALLED IN ALL HOLES OF THE CONNECTION AND BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8.1, UNTIL ALL THE BOLTS ARE SIMULTANEOUSLY SNUG TIGHT AND THE CONNECTION IS FULLY COMPACTED. FOLLOWING THIS INITIAL OPERATION ALL BOLTS IN THE CONNECTION SHALL BE TIGHTENED FURTHER BY THE APPLICABLE AMOUNT OF ROTATION SPECIFIED ABOVE. DURING THE TIGHTENING OPERATION THERE SHALL BE NO ROTATION OF THE PART NOT TURNED BY THE WRENCH. TIGHTENING SHALL PROGRESS SYSTEMATICALLY.

5. ALL OTHER BOLTED CONNECTIONS SHALL BE BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8.1 OF THE SPECIFICATION.

ALL BOLT HOLES SHALL BE ALIGNED TO PERMIT INSERTION OF THE BOLTS WITHOUT UNDUE DAMAGE TO THE THREADS. BOLTS SHALL BE PLACED IN ALL HOLES WITH WASHERS POSITIONED AS REQUIRED AND NUTS THREADED TO COMPLETE THE ASSEMBLY. COMPACTING THE JOINT TO THE SNUG-TIGHT CONDITION SHALL PROGRESS SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT. THE SNUG-TIGHTENED CONDITION IS THE TIGHTNESS THAT IS ATTAINED WITH A FEW IMPACTS OF AN IMPACT WRENCH OR THE FULL EFFORT OF AN IRONWORKER USING AN ORDINARY SPUD WRENCH TO BRING THE CONNECTED PLIES INTO FIRM CONTACT.

MODIFICATION INSPECTION NOTES

THE MOUNT MODIFICATION INSPECTION (MMI) PROCEDURE IS INTENDED TO CONFIRM THAT CONSTRUCTION AND INSTALLATION MEETS ENGINEERING DESIGN, ATC PROCEDURES AND ATC STANDARD SPECIFICATIONS FOR WIRELESS TOWER SITES.

TO ENSURE THAT THE REQUIREMENTS OF THE MMI ARE MET, IT IS VITAL THAT THE GENERAL CONTRACTOR SUBMIT ALL REQUIRED PHOTOGRAPHS AND DRAWINGS TO AMERICAN TOWER CORPORATION (ATC).

GENERAL CONTRACTOR

THE GENERAL CONTRACTOR IS REQUIRED TO:

- REVIEW THE REQUIREMENTS OF THE MMI CHECKLIST.
- UNDERSTAND ALL INSPECTION REQUIREMENTS.

THE GENERAL CONTRACTOR SHALL PERFORM AND RECORD THE INSPECTION RESULTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE MMI CHECKLIST.

MOUNT MODIFICATION INSPECTION CHECKLIST			
INSPECTION DOCUMENT	DESCRIPTION	INSPECTION TESTING REQUIRED	RESPONSIBILITY
ON-SITE COLD GALVANIZING VERIFICATION	PHOTOGRAPHIC EVIDENCE OF COLD GALVANIZATION TYPE AND APPLICATION IN ALL APPLICABLE LOCATIONS TO BE INCLUDED WITHIN THE MMI REPORT	✓	GC
GC AS-BUILT DRAWINGS WITH CONSTRUCTION RED-LINES	"AS-BUILT" DRAWINGS INDICATING ANY APPROVED CHANGES TO ENGINEERED PLANS TO MMI FOR APPROVAL/REVIEW AND INCLUSION IN MMI REPORT	✓	GC
PHOTOGRAPHS	PHOTOGRAPHIC EVIDENCE OF MOUNT MODIFICATION INSPECTION, ON SITE REMEDIATION, AND ITEMS FAILING INSPECTION & REQUIRING FOLLOW UP TO BE INCLUDED WITHIN THE MMI REPORT. COMPLETE PHOTO LOG IS TO BE SUBMITTED WITHIN MMI REPORT.	✓	GC

TABLE KEY:  
MMI - MOUNT MODIFICATION INSPECTION  
GC - GENERAL CONTRACTOR  
ATC - AMERICAN TOWER CORPORATION



THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATION AS INSTRUMENTS OR SERVICE ARE THE EXCLUSIVE PROPERTY OF AMERICAN TOWER. THEIR USE AND PUBLICATION SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. TITLE TO THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF AMERICAN TOWER WHETHER OR NOT THE PROJECT IS EXECUTED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION ON FILE WITH AMERICAN TOWER.

REV.	DESCRIPTION	BY	DATE
△	FIRST ISSUE	AMM	11/02/20
△			
△			
△			
△			

ATC SITE NUMBER:  
370609  
ATC SITE NAME:  
WIDEFIELD HIGH SCHOOL II  
COLORADO  
SITE ADDRESS:  
515 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:47



DRAWN BY:	AMM
APPROVED BY:	MCC
DATE DRAWN:	11/02/20
ATC JOB NO:	13323293_C9_03

IBC GENERAL NOTES  
AND MOUNT MODIFICATION  
INSPECTION


SHEET NUMBER:

G-002


REVISION:

0







**MOUNT MODIFICATION  
TOP VIEW**



**MOUNT MODIFICATION  
ISOMETRIC VIEW**



**MOUNT MODIFICATION  
FRONT VIEW**



**SAFETY CLIMB LOCATION**



**NOTE:**

1. CONTRACTOR TO INSTALL MOUNT MODIFICATIONS PER THE MANUFACTURERS SPECIFICATION. MODIFICATIONS SHALL NOT OBSTRUCT, INTERFERE, OR BLOCK EXISTING SAFETY CLIMB SYSTEM. IF ANY OF THESE OCCURS DURING INSTALLATION CONTACT THE AMERICAN TOWER PMI INBOX [PMI@AMERICANTOWER.COM](mailto:PMI@AMERICANTOWER.COM)
2. IN THE EVENT A PROPOSED MODIFICATION PART LISTED IN THE DRAWINGS IS NOT AVAILABLE, AN APPROVED EQUIVALENT CAN BE SUBSTITUTED. FOR APPROVAL OF EQUIVALENT PART OR QUESTIONS PLEASE CONTACT AMERICAN TOWER PMI INBOX AT [PMI@AMERICANTOWER.COM](mailto:PMI@AMERICANTOWER.COM).



**AMERICAN TOWER®**  
**ATC TOWER SERVICES, LLC**  
3500 REGENCY PARKWAY  
SUITE 100  
CARY, NC 27518  
PHONE: (919) 468-0112

THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATION AS INSTRUMENTS OR SERVICE ARE THE EXCLUSIVE PROPERTY OF AMERICAN TOWER. THEIR USE AND PUBLICATION SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. TITLE TO THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF AMERICAN TOWER WHETHER OR NOT THE PROJECT IS EXECUTED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION ON FILE WITH AMERICAN TOWER.

REV.	DESCRIPTION	BY	DATE
0	FIRST ISSUE	AMM	11/02/20

ATC SITE NUMBER:

370609

ATC SITE NAME:

WIDEFIELD HIGH SCHOOL II

COLORADO

SITE ADDRESS:

515 WIDEFIELD DRIVE  
COLORADO SPRINGS, CO 80911



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:48



DRAWN BY:	AMM
APPROVED BY:	MCC
DATE DRAWN:	11/02/20
ATC JOB NO:	13323293_C9_03

MODIFICATION PROFILE


SHEET NUMBER:

S-101

REVISION:

0





NOTE: THIS SHEET WAS CREATED BY OTHERS AND PROVIDED AT THE REQUEST OF THE CUSTOMER WITHOUT EDIT. PLEASE REFERENCE THE MOUNT ANALYSIS REPORT FOR COMPLETE MOUNT ANALYSIS CALCULATIONS AND DETAILS. SUPPLEMENTAL PAGES INCLUDED IN THE CONSTRUCTION DRAWINGS ARE FOR REFERENCE ONLY. GENERAL CONTRACTOR IS TO VERIFY THEY HAVE THE MOST RECENT MOUNT ANALYSIS PRIOR TO CONTRUCTION.

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:49



SUPPLEMENTAL

SHEET NUMBER:  
R-601

REVISION:  
0

ATC Engineering Replacement Recommendation

Tower Info	
Tower Number	370609
Tower Name	Widefield High School II
State	Colorado

Jurisdictional Codes	
Design TIA Code	Unknown
Current TIA Code	ANSI/TIA-222-H
IBC	2015 IBC
Other	-

Project Information	
Carrier	T-Mobile
Structure Type	Monopole

Recommended Mount Replacement	Site Pro 1 VFA10-SD-S*
*or approved equivalent	

Additional Info	
Can modifications be Installed?	Yes
What is the post-mod capacity?	92%

Project Requirements		
New Mount Face Width	150	in
Number of Sectors	3	

Replacement Cost	\$	36,000.00
------------------	----	-----------

Estimate for Platform w/ Handrails @ 370609 (Widefield High School II) -- 13323293\_C9\_03

Site Data and Design Parameters				
Asset OTM #	370609			
Asset Name	Widefield High School II			
State	Colorado			
County	El Paso			
City	COLORADO SPRINGS			
Failing Analysis Eng. #	13323293_C8_01			
Mod. Drawing Eng. #	13323293_C9_03			
Building Codes	TIA/IBC:	ANSI/TIA-222-H	/	2015 IBC
	Local:			
Failing Analysis % / Code	153%	/		TIA-H
Post Mod % / Controlling Member	92%	/		Mount Pipes
Usage Limit % / Reason	105%	/		N/A

Any modification design comments or assumptions? No (including notes to the Estimator)

Full Modification Summary	
Item #	Scope Item
1	Install Site Pro 1 PRK-SFS V Style Stabilizer on All (3) MP sector(s)

As-Is Modification Cost Estimate	\$10,000
----------------------------------	----------

1:25 PM 10/26/2020

Dates and Designers				
Mount Analysis Date / By	CAD	10/6	/ RK	
Design Date / By		10/26/2020	/ MCC	
Checked Date / By			/	
Detailer (Prev/Current/Level)		/	/	/
Software	RISA			
Mapping or Cut Sheet Available?	Yes			
Tower Type		Monopole	18-sided	
Mount Type	Platform w/ Handrails			
Carriers				
# of RADs	1			
Carrier	T-Mobile			

X:\W-Z\Widefield High School II, CO (370609)\13323293 T-MOBILE\13323293\_03\_MOUNT\_DRW\Mount Modification SOW v1.4.3

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:49



SUPPLEMENTAL

SHEET NUMBER:

R-602

REVISION:

0



## Antenna Mount Analysis Report

**ATC Site Name** : Widefield High School II, CO  
**ATC Site Number** : 370609  
**Engineering Number** : 13323293\_C9\_03  
**Mount Elevation** : 105 ft  
**Carrier** : T-Mobile  
**Carrier Site Name** : Widefield - ATC 370609  
**Carrier Site Number** : DN04166E  
**Site Location** : 523 Widefield Drive  
Colorado Springs, CO 80911-0000  
38.75483333 , -104.7305556  
**County** : El Paso  
**Date** : October 26, 2020  
**Max Usage** : 92%  
**Result** : Contingent Pass

Prepared By:  
Mitchell Chen  
Structural Engineer I

Reviewed By:



Eng. Number 13323293\_C9\_03  
October 26, 2020

### Table of Contents

Introduction .....	1
Supporting Documents.....	1
Analysis .....	1
Conclusion .....	1
Antenna Loading.....	2
Structure Usages.....	2
Mount Layout .....	3
Equipment Layout .....	4
Standard Conditions.....	7
Calculations .....	Attached

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:50

cosign

SUPPLEMENTAL

SHEET NUMBER:

R-603

REVISION:

0





Introduction

The purpose of this report is to summarize results of the antenna mount analysis performed for T-Mobile at 105 ft.

Supporting Documents

Specifications Sheet	Site Pro 1 SNP8HR-3XX, dated November 21, 2014
Radio Frequency Data Sheet	RFDS ID #DN04166E, dated May 11, 2020
Reference Photos	Site photos from 2020

Analysis

This antenna mount was analyzed using American Tower Corporation’s Mount Analysis Program and RISA-3D

Basic Wind Speed:	130 mph (3-Second Gust)
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 1/4" radial ice concurrent
Codes:	ANSI/TIA-222-H / 2018 IBC / Larimer County Amendments
Exposure Category:	C
Risk Category:	II
Topographic Factor Procedure:	Method 2
Feature:	Flat
Crest Height (H):	0 ft
Crest Length (L):	0 ft
Spectral Response:	Ss = 0.185, S1 = 0.059
Site Class:	D - Stiff Soil
Live Loads: *	Lm = 500 lbs

\* Based on experience, it has been determined that the Lv load cases will not control over Lm load cases in platform mount analyses. Therefore, these load cases have been excluded from this analysis.

Conclusion

Based on the analysis results, the antenna mount meets the requirements per the applicable codes listed above provided the modifications listed below are completed:

- Install modifications per ATC drawing #13323293\_C9\_03.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.



Application Loading

Mount Centerline (ft)	Antenna Centerline (ft)	Qty	Antenna Model
105.0	108.0	3	Nokia AEHC
		3	Commscope FFHH-65C-R3
		2	Commscope HELIAX FiberFeed 12 RRU Pendant Connect
		3	Nokia AHFIG 70.55 lbs
		3	Nokia AirScale Dual RRH 4T4R B12/71 240W AHLOA

Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Horizontals	34%	Pass
Mount Pipes	92%	Pass
Handrail	52%	Pass
Connection	23%	Pass
Mod-Kit	13%	Pass

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:51



SUPPLEMENTAL

SHEET NUMBER:

R-604


REVISION:

0




Eng. Number 13323293\_C9\_03  
October 26, 2020  
Page 3

Mount Layout



Eng. Number 13323293\_C9\_03  
October 26, 2020  
Page 4

Equipment Layout



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:51



SUPPLEMENTAL

SHEET NUMBER:

R-605


REVISION:

0




Eng. Number 13323293\_C9\_03  
October 26, 2020  
Page 5

Equipment Layout Cont'd.



Eng. Number 13323293\_C9\_03  
October 26, 2020  
Page 6

Equipment Layout Cont'd.



Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:52  
Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:53



SUPPLEMENTAL

SHEET NUMBER:

R-606

REVISION:

0





Eng. Number 13323293\_C9\_03  
October 26, 2020  
Page 7

Standard Conditions

All engineering services performed by ATC Tower Services, LLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of ATC Tower Services, LLC

It is the responsibility of the client to ensure that the information provided to ATC Tower Services, LLC and used in the performance of our engineering services is correct and complete.

American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

All connections are to be verified for condition and tightness by the installation contractor preceding any changes to the appurtenance mounting system and/or equipment attached to it.

Unless explicitly agreed by both the client and ATC Tower Services, LLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. ATC Tower Services, LLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.



Site Number: 370609  
Project Number: 13323293\_C9\_03  
Carrier: T-Mobile  
Mount Elevation: 105 ft  
Date: 10/26/2020

Mount Analysis Force Calculations

Wind & Ice Load Calculations				Seismic Load Calculations			
Velocity Pressure Coefficient	K <sub>z</sub>	1.28		Short Period DSRAP	S <sub>DS</sub>	0.197	
Topographic Factor	K <sub>zt</sub>	1.00		1 Second DSRAP	S <sub>D1</sub>	0.094	
Rooftop Wind Speed-up Factor	K <sub>s</sub>	1.00		Importance Factor	I	1.0	
Shielding Factor	K <sub>a</sub>	0.90		Response Modification Coefficient	R	2.0	
Ground Elevation Factor	K <sub>e</sub>	0.81		Seismic Response Coefficient	C <sub>s</sub>	0.099	
Wind Direction Probability Factor	K <sub>d</sub>	0.95		Amplification Factor	A	1.0	
Basic Wind Speed	V	130	mph	Total Weight	W	2329.8	lbs
Velocity Pressure	q <sub>z</sub>	42.6	psf	Total Shear Force	V <sub>s</sub>	229.9	lbs
Height Escalation Factor	K <sub>iz</sub>	1.12		Horizontal Seismic Load	E <sub>h</sub>	229.9	lbs
Thickness of Radial Glaze Ice	T <sub>iz</sub>	0.28	in	Vertical Seismic Load	E <sub>v</sub>	91.9	lbs

Antenna Calculations (Elevations per Application/RFDS)*								
Equipment	Height	Width	Depth	Weight	EPA <sub>N</sub>	EPA <sub>T</sub>	EPA <sub>NI</sub>	EPA <sub>TI</sub>
Model #	in	in	in	lbs	sqft	sqft	sqft	sqft
Nokia AEHC	38.2	21.5	8.1	103.6	6.84	1.82	7.13	1.98
Commscope FFHH-65C-R3	96.0	25.2	9.3	125.7	21.14	3.72	21.73	3.97
Commscope HELIAX FiberFeed 12 RRU Pendant Connect	16.9	6.7	4.7	20.0	N/A	N/A	N/A	N/A
Nokia AHFIG 70.55 lbs	27.4	12.1	5.2	70.6	2.76	1.31	2.95	1.48
Nokia AirScale Dual RRH 4T4R B12/71 240W AHLOA	22.0	12.1	7.4	83.8	2.22	1.38	2.38	1.52

\* Equipment with EPA values N/A were not considered in the mount analysis

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:54  
Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:55



SUPPLEMENTAL

SHEET NUMBER:

R-607

REVISION:

0



Site Number: 370609  
Project Number: 13323293\_C9\_03  
Carrier: T-Mobile  
Mount Elevation: 105 ft  
Date: 10/26/2020


Mount-to-Tower Connection Analysis

Applied Loads from RISA 3D				
Controlling Load Combination		102		
Node Label		N002		
Force in X	F <sub>x</sub>	136.5	lbs	
Force in Y	F <sub>y</sub>	1353.1	lbs	
Force in Z	F <sub>z</sub>	-272.5	lbs	
Moment about X	M <sub>x</sub>	4123.2	lb-ft	
Moment about Y	M <sub>y</sub>	-201.6	lb-ft	
Moment about Z	M <sub>z</sub>	781.0	lb-ft	

Bolt Shear and Tensile Capacity				
Bolt Quantity	n	4		
Bolt Diameter	D <sub>B</sub>	5/8	in	
Bolt Edge Distance	e	1	in	
Bolt Grade		A325		
Bolt F <sub>y</sub>	F <sub>yB</sub>	92	ksi	
Bolt F <sub>u</sub>	F <sub>uB</sub>	120	ksi	
Applied Shear	V <sub>u</sub>	0.48	k	
Applied Tension	T <sub>u</sub>	4.26	k	
Tensile Strength	φT <sub>n</sub>	20.3	k	
Interaction Capacity	(T <sub>u</sub> +V <sub>u</sub> )/φT <sub>n</sub>	23%	Pass	

Plate Flexural Capacity				
Plate Height	H	8	in	
Plate Width	W	8	in	
Plate Thickness	T	3/4	in	
Plate Grade		A36		
Plate F <sub>y</sub>	F <sub>yP</sub>	36	ksi	
Plate F <sub>u</sub>	F <sub>uP</sub>	58	ksi	
Shear Capacity	φV <sub>n</sub>	40.4	k	
Applied Moment	M <sub>u</sub>	8.5	k-in	
Flexural Strength	φM <sub>n</sub>	58.7	k-in	
Flexural Capacity	M <sub>u</sub> /φM <sub>n</sub>	14%	Pass	


Prying Action Considerations				
Moment Arm	b	1.00	in	
Effective Moment Arm	b'	0.69	in	
Tributary Length	p	2.75	in	
Effective Edge Distance	a'	1.31	in	



Weld and Base Metal Capacity				
Standoff Type		Tube		
Standoff Member		HSS4x4x4		
Member Edge Distance	E	2	in	
Member Width	w	4	in	
Member Thickness	t	0.250	in	
Member Grade		A53 Gr. B		
Member F <sub>y</sub>	F <sub>yM</sub>	35	ksi	
Member F <sub>u</sub>	F <sub>uM</sub>	60	ksi	
Weld Size	a	1/4	in	
Weld Length	l	16.0	in	
Applied Load	P <sub>u</sub>	8.5	k	
Weld Strength	φR <sub>n</sub>	44.5	k	
Weld Capacity	P <sub>u</sub> /φR <sub>n</sub>	19%	Pass	

Minimum Base Metal Thickness	0.206	in
Controlling Base Metal Thickness	0.250	in
Base Metal Result	Acceptable	

Minimum Thickness	t <sub>min</sub>	0.22	in
No Prying Thickness	t <sub>np</sub>	0.29	in
Min Bolt Strength Thickness	t <sub>c</sub>	0.62	k-in
Prying Action Bolt Tension	T <sub>up</sub>	0.00	k




American Tower Corp.	370609, Widefield High School II	SK - 1
Mitchell.Chen	3D Rendering (Final Configuration)	Oct 26, 2020 at 1:08 PM
13323293_C9_03		R3D. T-MOBILE @ 370609, Widefie...

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:56  
Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:57



SUPPLEMENTAL

SHEET NUMBER:	REVISION:
R-608	0




American Tower Corp.  
Mitchell.Chen  
13323293\_C9\_03

370609, Widefield High School II  
3D Rendering (Proposed Configuration)

SK - 2  
Oct 26, 2020 at 1:08 PM  
R3D. T-MOBILE @ 370609, Widefie...

Page 2



American Tower Corp.  
Mitchell.Chen  
13323293\_C9\_03

370609, Widefield High School II  
3D Rendering (Current Configuration)

SK - 3  
Oct 26, 2020 at 1:08 PM  
R3D. T-MOBILE @ 370609, Widefie...

Page 3

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:57  
Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:58

cosign  
cosign

SUPPLEMENTAL


SHEET NUMBER:

R-609


REVISION:

0





American Tower Corp.	370609, Widefield High School II	SK - 4
Mitchell.Chen		Oct 26, 2020 at 1:09 PM
13323293_C9_03		R3D. T-MOBILE @ 370609, Widefie...



American Tower Corp.	370609, Widefield High School II	SK - 5
Mitchell.Chen		Oct 26, 2020 at 1:09 PM
13323293_C9_03		R3D. T-MOBILE @ 370609, Widefie...


Authorized by "Patrick P. Barry"  
13 Nov 2020 04:39:59  
Authorized by "Patrick P. Barry"  
13 Nov 2020 04:40:00



SUPPLEMENTAL

SHEET NUMBER:  
**R-610**

REVISION:	0
-----------	---



Member Code Checks Displayed (Enveloped)  
Results for LC 1, 1.4D

American Tower Corp.	370609, Widefield High School II Unity Bending Checks	SK - 6
Mitchell.Chen		Oct 26, 2020 at 1:09 PM
13323293 C9_03		R3D. T-MOBILE @ 370609, Widefie...

Member Shear Checks Displayed (Enveloped)  
Results for LC 1, 1.4D

American Tower Corp.	370609, Widefield High School II  Shear Checks	SK - 7
Mitchell.Chen		Oct 26, 2020 at 1:09 PM
13323293 C9 03		R3D. T-MOBILE @ 370609, Widef...

Authorized by "Patrick P. Barry"  
13 Nov 2020 04:40:01  
Authorized by "Patrick P. Barry"  
13 Nov 2020 04:40:02



0